

FEB 5 1968

UNCLASSIFIED

MASTER

CLASSIFICATION LEVEL
(S, C OR U)



ATOMICS INTERNATIONAL
A Division of North American Aviation Inc.


NAA-SR-MEMO COVER SHEET

REPORT TITLE

AUTHOR

NAA-SR-MEMO 10667

(This Document Contains 26 Pages.
This is Copy of Series)



CLASSIFICATION TYPE
(RD OR DI)

NAA-SR-MEMOs are working papers and may be expanded, modified, or withdrawn at any time, and are intended for internal use only.

THIS REPORT MAY NOT BE PUBLISHED WITHOUT THE APPROVAL OF THE PATENT BRANCH, AEC.

LEGAL NOTICE

This report was prepared as an account of Government sponsored work. Neither the United States, nor the Commission, nor any person acting on behalf of the Commission:

A. Makes any warranty or representation, express or implied, with respect to the accuracy, completeness, or usefulness of the information contained in this report, or that the use of any information, apparatus, method, or process disclosed in this report may not infringe privately owned rights; or

B. Assumes any liabilities with respect to the use of, or for damages resulting from the use of information, apparatus, method, or process disclosed in this report.

As used in the above, "person acting on behalf of the Commission" includes any employee or contractor of the Commission, or employee of such contractor, to the extent that such employee or contractor of the Commission, or employee of such contractor prepares, disseminates, or provides access to, any information pursuant to his employment or contract with the Commission, or his employment with such contractor.

UNCLASSIFIED

CLASSIFICATION LEVEL
(S, C OR U)

DO NOT REMOVE THIS SHEET

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

ATOMICS INTERNATIONAL <small>A Division of North American Aviation, Inc.</small>		NAA-SR- TDR NO. 10667	APPROVALS
TECHNICAL DATA RECORD		PAGE 1 OF 26	<i>A. N. Gallegos</i>
AUTHOR C. M. Quirk T. M. Funakura		DEPT. & GROUP NO. 722-22 722-22	DATE 11-4-64 <i>MA Perlow</i>
		GO NO. 7561	<i>Keen</i>
TITLE SNAP 10A PbSnTe T/E Pump S/N-038 Acceptance Test		S/A NO. 4521	TWR 002
		SECURITY CLASSIFICATION	
		(CHECK ONE BOX ONLY)	(CHECK ONE BOX ONLY)
PROGRAM SNAP 10A		UNCL. <input checked="" type="checkbox"/> AEC <input checked="" type="checkbox"/> DOD <input checked="" type="checkbox"/> CONF. <input type="checkbox"/> SECRET <input type="checkbox"/>	RESTRICTED DATA <input type="checkbox"/> DEFENSE INFO. <input type="checkbox"/>
SUBACCOUNT TITLE T/E Pump and Emissivity Coating		AUTHORIZED CLASSIFIER SIGNATURE <i>A. N. Gallegos</i> DATE 11-5-64	
DISTRIBUTION HQ-1 G. Alm HQ-2 J. V. Addison J. B. Brunings H. M. Dieckamp I. B. Sexton R. J. Smith D. S. Thompson HQ-5 J. B. Tathwell SS-036 K. A. Davis R. D. Keen A. N. Gallegos M. A. Perlow W. D. Leonard SS-038 S. R. Rocklin		STATEMENT OF PROBLEM Present the results of the Acceptance Test of the SNAP 10A PbSnTe T/E Pump S/N-038, in a NaK 78 Acceptance Test Loop, in accordance with Test Specification NA 0204-005, Revision "A".	
		ABSTRACT: The SNAP 10A PbSnTe T/E Pump S/N-038 was Acceptance Tested in accordance with Test Specification NA 0204-005, Revision "A" and data as obtained, is submitted with a short summary of the results. The maximum output obtained during the Orbital Full Flow Test was measured as 15.00 gpm of 1010°F NaK at a pressure of 1.060 psi. The maximum output obtained during the Pre-Reactor Startup Test at a NaK temperature of 90°F was measured to be 0.29 gpm at a pressure of 0.00415 psi, with a startup current of 40 amperes DC. Based on the results of the above tests, T/E Pump S/N-038 meets the requirements of the Test Specification NA 0204-005, Revision "A", with regards to the Orbital Full Test but does not meet the Pre-Reactor Startup requirements.	

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. NAA-SR-TDR 10667
DATE 11-4-64
PAGE 2 OF 26

Acceptance Test Report of T/E Pump S/N-038

Summary of Data and Performance

The SNAP 10A PbSnTe T/E Pump S/N-038 was Acceptance tested in accordance with Test Specification NAO204-005, Revision "A", and data as obtained is submitted with a short summary of the results.

Full Flow Test - With the test loop valve in the "open" position, the maximum output obtained at 1010°F NaK temperature was measured to be 15.00 gpm at a pressure of 1.060 psi.

Pressure vs. Flow measurements were obtained at 800°F, 900°F and 1010°F NaK temperatures.

Pre-Reactor Startup Test - The maximum output obtained during this phase of the test was measured as 0.29 gpm at a pressure of 0.00415 psi, with a startup current of 40 amperes DC and a NaK temperature of 90°F.

The pump was instrumented to measure T/E element voltages and hot and cold junction temperatures. The pump magnet was magnetized to a maximum obtainable field strength of 2500 gauss as measured at the center axis of the pump throat, prior to delivery to the Environmental Test Unit. Upon its return from the Environmental Test Unit, the pump magnet field strength was measured to be 2460 gauss. The raw data obtained from the above tests is contained in AI Log Notebook B-266251.

Based on the results of the above tests, the T/E Pump S/N-038 meets the requirements of the Test Specification NAO204-005, Revision "A" with regards to the Full Flow Test but does not meet the Pre-Reactor Startup requirements.

Included in this report are the data and results of the Environmental Acceptance Test performed by the Environmental Test Unit.

NOTE: Pump pressures are presented above using measured values plus a tare pressure which was re-calculated by W. D. Leonard, taking into account the temperature effect on density and viscosity of NaK. Also included are the transition from turbulent flow to laminar flow in the low flow region. Previous tare values were based on the temperature effect on the density of NaK only. (Reference IL #1)

- (1) IL: To K. A. Davis from W. D. Leonard
Dated: July 24, 1964
Subject: SNAP 10A T/E Pump Hydraulic Losses and Test Loop Tare Losses.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. NAA-SR-TDR 10667

DATE 11-4-64

PAGE 3 OF 26

Schedule of Events

- October 19, 1964 - Received pump from Emissivity Coating Unit
- October 19, 1964 - Visual Inspection of the pump
- October 19, 1964 - Pressure test and Helium Leak Check of the pump
- October 20, 1964 - Pump Magnet Magnetization
- October 20, 1964 - Pump delivered to Environmental Test Unit for Environmental Acceptance Test

- October 23, 1964 - Received pump from Environmental Test Unit
- October 23, 1964 - Visual Inspection of the pump
- October 23, 1964 - Pump magnet field strength measurement
- October 26, 1964 - Pump installation into Acceptance Test Loop A-3
- October 26, 1964 - Helium leak check pump test loop
- October 26, 1964 - Installation and checkout of pump instrumentation
- October 26-27, 1964 - Vacuum Vessel and Pump Test Loop Evacuation
- October 27, 1964 - Test system NaK Loading
- October 27, 1964 - System heatup to 850°F
- October 27, 1964 - System cool down to 100°F
- October 27-28, 1964 - System heatup to 1010°F
- October 28, 1964 - Pressure vs. Flow at 1010°F
- October 28, 1964 - Pressure vs. Flow at 900°F
- October 28, 1964 - Pressure vs. Flow at 800°F
- October 28-29, 1964 - 20 hours test at 1010°F
- October 29, 1964 - Pressure vs. Flow at 100°F NaK, (Pre-Reactor Startup)
- October 30, 1964 - Pressure vs. Flow at 90°F NaK, (Pre-Reactor Startup)
- October 30, 1964 - Test System Shut down

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. NAA-SR-TDR 10667

DATE 11-4-64

PAGE 4 OF 26

Component: SNAP 10A PbSnTe T/E Pump S/N-038
Drawing Number: 10FS-81001
Data Source: AI Log Notebook
Test Performed by: Liquid Metals Test Unit, 722-22
Delivered to: Special Testing

Test Results:

Pages 5 to 7 Environmental Test data and results
Figure 1 Flow and Pressure vs. NaK temperature
Figure 2 Flowmeter Output and Wall Voltage vs. NaK temperature
Figure 3 Flowmeter Output and Wall Voltage vs. NaK Flow
Figure 4 Pressure vs. Flow at NaK temperatures indicated
Figure 5 Pressure vs. Flow (Pre-Reactor Startup)
Figure 6 Pump Instrument Callout
Page 14 Instrument Calibration
Figure 7-8 Pressure drop in pump loop without pump
Figures 9-14 Test Flowmeter Calibration at 200°F, 400°F, 600°F, 800°F, 900°F and 1000°F NaK temperatures.
Page 23 to 26 Raw Data

TO:

DEPT.

DATE

ENVIRONMENTAL EVALUATION COMPONENT TEST REPORT # 494

Component Identification SNAP 10A Thermoelectric NaK Pump #038.

Responsible Engineer and/or Unit supplying component K. A. Davis date rec'd 10-20-64

Applicable environmental specifications NAO204-005 "NaK Pump, Thermoelectric SNAP 10A Acceptance Test," 11-26-64.

Tests requested Vibration

Acceptance

TEST PLAN OF ACTION

Test assigned to A. L. Jones ; ext 6464 date 10-20-64 scheduled test start 10-22-64

Test equipment to be utilized 246 shaker system

Instrumentation required Table input; control accelerometer on pump top, X-Y plotter.

Measurements required Convertor element resistance and magnetic field measurement after each pass; X-Y plot of table input and pump top response.

Specimen support fixture Pump was installed in the acceptance test fixture #ETLA-1; struts were torqued per drawing #10FS-12001.

Test inputs: VIBRATION (constant octave sweep rate requiring 30 minutes)

Lateral and normal axes	<u>5 to 14 cps @ 1/2 "DA</u>	Longitudinal	<u>5 to 11 cps @ 1/2 "DA</u>
	<u>14 to 50 cps @ 5 g</u>		<u>11 to 30 cps @ 3 g</u>
	<u>50 to 100 cps @ 2.5 g</u>		<u>30 to 80 cps @ 4 g</u>
	<u>100 to 250 cps @ 1.0 g</u>		<u>80 to 2000 cps @ 2.5 g</u>
	<u>250 to 2000 cps @ 2.5 g</u>		<u> to cps @ g</u>

Vibration (other) The response on the pump top was limited to 5 g in the lateral and normal axes and to 4 g in the longitudinal tests per Specification.

Test sequence was X, Y, and Z.

SHOCK

Lateral and g, 1/2 sine millisec pulse;
 Normal axes shocks in each direction of each axis

LONGITUDINAL

 g, 1/2 sine,
 millisec pulse;
 shocks in each direction

ACCELERATION

Lateral and g, for a total
 Normal axes of minutes

LONGITUDINAL

 g, aft direction, for a total
of minutes.
 g, forward direction, for a total
of minutes.

TEST RESULTSTest conducted by A. L. Jones ext 6464 date 10-23-64 IN page NoB-262792B-262793B-262794

Results A detailed visual inspection showed no apparent physical damage as a
result of the test. Thermoelectric resistance readings of the telluride elements
were recorded. To counteract the effect of emf generated in the telluride
material, readings were taken in each direction through each element as noted
in the table of results. It is extremely difficult to make accurate resistance
measurements in the low micro-ohm range because the thermal emf from the telluride
and the thermal emf present in the junctions between the test leads and the copper
bars and/or radiators are of the same order magnitude as the IR drop of the telluride
material. Since the trend of readings for each element from test to test did not
vary significantly, it is assumed that within the resolution of the measuring
device employed, no appreciable damage to the telluride material and/or interfaces
occurred.

Specimen disposal Pump returned to Pumps and Emissivity UnitReport prepared by A. L. Jones date 10-23-64 approved _____ date _____

ATOMICS INTERNATIONAL


A Division of North American Aviation, Inc.

NO. NAA-SR-TDR 10667

DATE 11-4-64

PAGE 7 OF 26

NaK Pump #038 Vibration Test Results



Read Out Location	Resistance Readings ln Micro Ohms			
	Readings	X Axis	Y Axis	Z Axis
1 to 2	16 (5)	15 (12)	18 (7)	12 (12)
1 to 3	18 (6)	14 (10)	15 (8)	12 (12)
1 to 5	28 (18)	21 (16)	21 (18)	22 (18)
4 to 5	28 (16)	26 (17)	25 (18)	23 (20)
5 to 6	27 (14)	24 (16)	25 (18)	24 (19)
Gauss *	2480	2480	2480	2480

*Magnetic flux at internal Center of pump throat

() Leads reversed

Figure 1

T/E PUMP 5N-038
FLOW and PRESSURE
VS
NaK TEMPERATURE




Figure 2




Figure 3

7E PUMP 3N-038
FLOWMETER OUTPUT and WALL VOLTAGE
VS.
NAK FLOW




Figure 4

*7/8" PUMP #N-038
PRESSURE VS. FLOW
AT NaK TEMPERATURES INDICATED*





Figure 5


T/E PUMP 3/W-038
PRESSURE VS. FLOW
(PRE-REACTOR STARTUP)



DESIGN POINT PER
SPECIFICATION
NA-0204-005, REK/A
⊙

S-10A T/E PUMP S/N 038

FRONT VIEW Positive Copper



Calibrated T/c's

- #1 5361
- 2 5366
- 3 5359
- 4 5370

○ Thermocouples
 #10 in Neg copper opposite #9

□ Voltage Probes
 #5 in Neg copper opposite #1
 #4 on Neg side opposite #2
 #6 on Neg side opposite #3
 #7 on Neg side opposite #8

Instrument Calibration

<u>Instrument</u>	<u>Calibration Date</u>
Robertshaw Pressure Gage	September, 1964
Temperature Recorder	October 20, 1964
Flow Recorder	October 20, 1964
Temperature Controller	October 20, 1964
Rubicon Potentiometer	August 28, 1964
Level Probe Meter	September, 1964
Level Probe	September, 1964
D.C. Power Supply	August 19, 1964
Leak Detector	Prior to each test
Immersion Thermocouples	January 8, 1964

NOTE: All calibrations were made by the Instrumentation Unit, Department 744-42, Santa Susana, with the exception of the PM Flowmeter, the Immersion Thermocouples and the RFL Gaussmeter.

- A. The test loop Flowmeter was calibrated over a flow range of 1-12 gpm against a calibrated Venturi Meter at Santa Susana by the Liquid Metals Test Unit, Department 722-22, Lab Notebook B-222251.
- B. Immersion Thermocouples were fabricated by the Liquid Metals Test Unit, and calibrated by the AI Standards Lab at HQ, DeSoto.
- C. The pump magnet was magnetized with the Sweinhart Electronic Magnetizer, Model LG 5. The magnet field strength was measured at the center axis of the pump throat with the RFL Gaussmeter, Model 1890. The Gaussmeter was calibrated prior to each magnet field strength measurement and accuracy of measurements were in the order of $\pm 0.75\%$ as specified in the Manufacturer's Manual.

Figure 7


SNAP 10A T/E PUMP ACCEPTANCE TEST LOOP
TAKE CURVE

NO NAA-SR-TDR 10667

Date 11-4-64

PAGE 15 of 26

PRESSURE, PSI




References:

IL: to K. A. Davis from
 W. D. Leonard
 Dated: July 24, 1964
 Subject: SNAP 10A T/E Pump
 Hydraulic Losses and Test Loop
 Take Losses

FLOW, GPM

Figure 8



5 X 3 CACFEF
K. H. PEE - KEGULST. & LEPPK. CO. - ANNE ARBOR, MICH.

Figure 9




Figure 10




Figure 11





Figure 12

SNAP-10 ACCEPTANCE LOOP A-3.
FLOWMETER SIN FM-23.
NAK TEMPERATURE - 600°F.
B FIELD STRENGTH 1625 gauss at 95°F.
DATA SOURCE L N 9-22226A.
ESTIMATED ACCURACY ± 4% FOR Q > 10 ppm.

MILLIVOLTS



NAK FLOW RATE - 9PPM


NO NAA-SR-PDR 10667
Date 11-7-64
Page 20 of 26

2/ken

Figure 13

SWAMP 1041 ACCEPTANCE TEST LOOP A-B
FLOWMETER S/N-FM-23
NAK TEMPERATURE - 900°F
E FIELD STRENGTH - 1625 gauss at 75V
DATA SOURCE - INTERPOLATED FROM 800°F & 1000°F DATA
ESTIMATED ACCURACY ± 6% FOR "O" > 10 gpm

SLIPSTREAM




NO. NAA-SB-PDR 10667
DATE 11-11-64
PAGE 21 OF 26

John W. ...

Figure 14

SNAP TO ACCEPTANCE LABOR A-3.
FLOWMETER SIN EM-23.
NAK TEMPERATURE - 1000⁰⁰2
E FIELD STRENGTH - 1625 gauss at 7507.
DATA SOURCE L.N. B-227745.
ESTIMATED ACCURACY $\pm 4\%$ FOR 8.0 ± 1.0 ppm.



NO. NAA-SR-IDR 10667
Date 11-14-64
Page 22 of 26

Pump No. S/N 038

Test Acceptance

Date	Running Time Hrs	ΔP			FLOWMETERS			T _{NaK}		FIN TEMPERATURE				T _{sink}
		"-NaK	T _{NaK} °F	ΔP psi	Loop MV/GPM	FT-1T MV	FT-2T MV	T _{in} °F	T _{out} °F	TC24 °F	TC25 °F	RT17 °F	RT18 °F	
10/27/64		.125	105	.0039	.003 .01	.020	.040	99	100	100	100	100	99	77
10/28		.312	110	.0097	.181 .40	.538	.841	142	140	110	108	110	106	80
		.562	120	.0175	.353 .85	1.043	1.635	189	186	131	130	133	129	80
		.562	150	.0175	.410 1.02	1.237	1.915	225	223	164	162	165	160	85
		.875	170	.0270	.540 1.34	1.60	2.48	260	256	189	185	189	185	90
		1.312	200	.0408	.720 1.79	2.20	3.41	295	294	209	204	209	205	82
		2.00	250	.0915	1.32 2.26	4.10	6.44	400	396	260	255	260	255	80
		5.625	270	.1711	2.02 5.0	6.36	10.30	500	496	304	297	305	296	85
		8.50	290	.256	2.70 6.92	8.48	14.31	600	596	350	348	350	344	83
		12.06	305	.364	3.48 8.90	10.90	19.27	704	699	388	382	390	380	87
		18.50	400	.550	4.21 11.12	13.29	24.24	801	796	431	425	434	425	90
		25.31	460	.746	5.00 13.50	16.26	29.68	900	895	474	473	482	473	83
		30.25	450	.892	5.58 15.0	18.50	34.79	1010	1004	521	517	524	517	97

Pump No. SIN 038

Test Acceptance

Date	Running Time Hrs	ΔP			FLOWMETERS			T _{NaK}		FIN TEMPERATURE				T _{sink}
		T _{NaK} °F	ΔP psi	Loop MV/GPM	FT-1T MV	FT-2T MV	T _{in} °F	T _{out} °F	TC24 °F	TC25 °F	RT17 °F	RT18 °F		
10/28		Pressure Vs Flow data at 1010°F												
		30.25	450	.892	5.58 / 15.0	18.50	34.79	1010	1004	521	517	524	517	96
		34.94	450	1.031	5.20 / 14.0	17.52	33.60	1011	1003	521	521	526	517	98
		39.94	450	1.178	4.83 / 13.0	16.61	32.51	1013	1005	523	521	527	519	100
		44.25	450	1.306	4.46 / 12.0	15.67	31.40	1013	1005	523	520	527	519	100
		48.50	450	1.431	4.09 / 11.0	14.77	30.30	1010	1001	522	519	526	517	93
		52.63	450	1.553	3.72 / 10.0	13.86	29.16	1010	1000	522	520	526	517	100
		Pressure Vs Flow data at 900°F												
		25.44	450	.75	5.02 / 13.50	16.40	29.82	900	895	480	477	483	476	77
		28.13	450	.83	4.82 / 13.0	15.86	29.18	901	894	481	477	483	476	77
		32.81	450	.968	4.45 / 12.0	14.91	28.06	900	892	480	476	482	476	78
		37.31	450	1.101	4.08 / 11.0	14.04	27.02	900	890	480	476	482	476	82
		41.75	450	1.232	3.72 / 10.0	13.11	25.90	898	889	480	476	481	475	83
		46.31	450	1.366	3.35 / 9.0	12.21	24.84	897	889	480	476	482	475	84

Pump No. SIN 038

Test Acceptance

Date	Running Time Hrs	ΔP			FLOWMETERS			T _{NaK}		FIN TEMPERATURE				T _{sink}
		"-NaK	T _{NaK} °F	ΔP psi	Loop MV/GPM	FT-1T MV	FT-2T MV	T _{in} °F	T _{out} °F	TC24 °F	TC25 °F	RT17 °F	RT18 °F	
<i>Pressure Vs Flow data at 800°F</i>														
10/28/64		20.56	450	.606	4.41 / 11.6	14.30	25.04	800	795	441	438	444	438	84
		24.00	450	.708	4.17 / 11.0	13.67	24.34	801	795	442	438	444	439	86
		29.13	450	.860	3.79 / 10.0	12.76	23.34	801	795	442	438	444	439	82
		34.13	450	1.007	3.40 / 9.0	11.80	22.22	803	795	443	439	445	440	82
		38.75	450	1.144	3.02 / 8.0	10.85	21.20	805	796	443	440	445	440	82
		43.25	450	1.276	2.64 / 7.0	9.90	20.05	805	797	444	440	445	440	82
<i>20 Hour Test data at 1010°F</i>														
10/28	0 hrs.	30.50	450	.90	5.61 / 15.05	18.69	35.00	1014	1006	521	519	525	517	82
	4 hrs.	30.38	450	.896	5.60 / 15.02	18.50	34.73	1008	1001	520	518	525	516	80
10/29	8 hrs	30.19	450	.890	5.60 / 15.02	18.55	34.70	1008	1000	525	519	525	517	87
	12 hrs	30.50	450	.90	5.60 / 15.02	18.58	34.77	1010	1002	521	520	525	518	93
	16 hrs	30.56	450	.901	5.60 / 15.02	18.60	34.86	1010	1005	522	521	526	520	85
	20 hrs	30.63	450	.903	5.60 / 15.02	18.61	34.86	1010	1005	522	521	526	519	80

Pump No. S/N 038

Test Acceptance

Date	Running Time Hrs	ΔP			FLOWMETERS			T _{NaK}		FIN TEMPERATURE				T _{sink}
		"NaK	T _{NaK} °F	ΔP psi	Loop MV/GPM	FT-1T MV	FT-2T MV	T _{in} °F	T _{out} °F	TC24 °F	TC25 °F	RT17 °F	RT18 °F	
10/29		Pre Reactor Start-up Data at 100°F 40 Amps D.C.												
		.125	105	.0039	.118 / .29	.330	.330	100	100	100	103	101	100	101
		.437	105	.0136	.100 / .25	.291	.280	100	100	100	100	100	100	100
		.875	105	.0272	.08 / .20	.240	.230	100	100	100	100	100	100	99
		1.813	105	.0565	.04 / .10	.141	.140	99	100	100	100	100	100	99
		2.25	105	.0701	.02 / .05	.092	.100	99	99	100	99	99	100	97
		Pre Reactor Start-up Data at 90°F 40 Amps D.C.												
		.125	90	.0039	.118 / .29	.318	.320	89	89	90	89	90	90	87
		.50	90	.0156	.10 / .25	.278	.290	89	89	90	90	90	90	87
		1.0	90	.0312	.08 / .20	.227	.244	89	89	90	90	90	90	87
		1.937	90	.0605	.04 / .10	.129	.154	89	89	90	89	90	90	87
		2.375	90	.0741	.02 / .05	.079	.112	89	89	90	89	90	90	88