THIS DOCUMENT CONFIRMED AS
UNCLASSIFIED
DIVISION OF CLASSIFICATION
BY John J. B. Moore
DATE 10/1/74

Westinghouse Advanced Reactors Division

Released

WESTINGHOUSE ADVANCED REACTORS DIVISION

R1717

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

NOTICE

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Atomic Energy Commission, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

WARD-4210T3-7
UC-25

STAINLESS STEEL CLADDING DEVELOPMENT
QUARTERLY PROGRESS REPORT
FOR THE PERIOD ENDING JUNE 30, 1971

THIS DOCUMENT CONFIRMED AS
UNCLASSIFIED
DIVISION OF CLASSIFICATION
BY G. H. Kahan
DATE 10/15/71

Approved by:

W. E. Ray
Principal Investigator

P. Murray
Project Manager

Prepared for the U. S. Atomic Energy Commission
Division of Reactor Development and Technology
Under Contract No. AT(30-1)-4210, Task 3

Submitted to AEC/NY00 in August 1971

Westinghouse Electric Corporation
Advanced Reactors Division
P. O. Box 158
Madison, Pennsylvania 15663

R1717

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Atomic Energy Commission, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

Printed in the United States of America
Available from
National Technical Information Service
Springfield, Virginia 22151
Price: Printed Copy \$3.00; Microfiche \$0.95

TABLE OF CONTENTS

Section	Page
1 Introduction.....	1
1.0 General.....	1
2.0 Summary of Objectives.....	1
3.0 Summary of Prior Work.....	2
4.0 Summary of Progress.....	2
SSDA-210 Evaluation of Austenitic Stainless Steel Cladding.....	5
1.0 Objectives.....	5
2.0 Prior Work.....	5
3.0 Current Progress.....	6
3.1 Procurement and Handling.....	6
3.2 Defects Evaluation Program.....	8
3.3 Non-Destructive Testing.....	10
3.4 Stress Rupture Testing - Defected Specimens.....	19
3.5 Post-Stress Rupture Specimen Characterization....	23
3.6 Post-Test Evaluation.....	33
3.7 Characterization of Carpenter Technology Tubing..	37
List of References.....	39

LIST OF FIGURES

Figure		Page
1	Eddy Current Trace of 12 Notch Standard Type 316 Stainless Steel Tubing - Superior Lot 42402.....	11
2	NDT Chart Recordings of 20 Percent Cold Worked, Type 316 Stainless Steel.....	12
3	NDT Strip Chart Recordings of 20 Percent Cold Worked, Type 316 Stainless Steel Containing a Naturally Occurring Longitudinal Scratch.....	13
4	Typical Wall Thickness Recording for Lot 42402 Type 316 Stainless Steel Tubing with 0.015-inch Wall.....	14
5	Eddy Current Responses - Various Lots of Tubing.....	16
6	Biaxial Stress Rupture Results for 0.15 in Wall, Type 316 Stainless Steel Tubing at 1300°F.....	22
7	Rupture Morphologies of Defected Stress Rupture Specimens.	24
8	Strain Profile Plots - Type 316 Stainless Steel Tubing Tested to Rupture at 23,000 psi Hoop Stress at 1300°F in Argon.....	25
9	Local Wall Thickness Reduction Versus Angle Around Tube Circumference.....	27
10	Rupture Area of Specimen "A".....	28
11	Scanning Electron Micrographs of Specimen "A" Rupture.....	29
12	Rupture Area of Specimen "B".....	31
13	Rupture Area of Specimen "C".....	34
14	Schematic of Rupture Sequence in Notched Specimens.....	35
15	Characterizations of 20% Cold Worked Carpenter Technology Tubing.....	38

LIST OF TABLES

Table		Page
1	Fabrication Variations of Plug Drawn Tubing Procured During FY-1971.....	7
2	Wall Thickness Variations for Lot 42402, Type 316 Stainless Steel Tubing.....	15
3	Eddy Current Defect Indication Frequency Evaluation of Various Tubing Lots	17
4	Ranking of Various Tubing Lots According to Increasing Eddy Current Defect Indication Frequencies.....	18
5	Biaxial Stress Rupture Data for Type 316 Stainless Steel Tubing Tested in Argon.....	20
6	Biaxial Stress Rupture Data for Type 316 Stainless Steel Tubing Tested in Air	21
7	Carpenter Technology Tubing - Preliminary Characterizations.....	37

SECTION 1 INTRODUCTION

1.0 GENERAL

This is the twelfth and last quarterly progress report for the program and covers:

1. The work performed during the fourth quarter of FY-1971
2. A partial review of the results to the present time for the Defects Evaluation Task

The project was terminated at the end of the FY-1971.

2.0 SUMMARY OF OBJECTIVES

The project was focused on the short term, and was concerned with steps to improve commercially available Type 316 austenitic stainless steels for use as cladding in LMFBR fuel rods. The overall project objective was to determine the influence of structure on mechanical properties of Type 316 austenitic stainless steel so that optimum specifications, which would assure maximum performance under LMFBR service conditions, could be selected.

The influence of structure on mechanical properties has been well demonstrated in the published literature. For example, in one series of experiments, [1] prestraining of Type 316 austenitic stainless steel, followed by a specific heat treatment to produce carbide precipitation, decreased the minimum creep rate at temperatures of interest to LMFBR by as much as a factor of 250, and increased creep rupture life by as much as a factor of 25.

Initially in the cladding development program, a survey was made to determine tubing material property and microstructural variability based on procurement of tubing under an existing FFTF specification. This specification was used as a starting point. Materials with various fabrication histories were procured and evaluated in both the as-fabricated condition and after post-fabrication heat treatment. The relations between mechanical properties and structure were investigated.

It was anticipated that this first phase of the cladding program would culminate at the end of FY-1972 with a definition of the most desirable mechanical and microstructural properties in austenitic stainless steel, to maximize the strength and ductility of the material under the most limiting LMFBR service conditions.

3.0 SUMMARY OF PRIOR WORK

All work related to the present investigations and performed prior to the present period has been fully reported in:

- WARD-3791-26 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending September 30, 1968."
- WARD-3791-29 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending December 31, 1968."
- WARD-3791-35 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending March 31, 1969."
- WARD-3791-41 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending June 30, 1969."
- WARD-4135-2 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending September 30, 1969."
- WARD-4135-5 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending December 31, 1969."
- WARD-4135-9 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending March 31, 1970."
- WARD-4134-12 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending June 30, 1970."
- WARD-4135-14 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending September 30, 1970."
- WARD-4210T3-2 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending December 31, 1970."
- WARD-4210T3-4 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending March 31, 1971."
- WARD-4210T3-5 Combined Topical Report
 - I. "Structural Characterization and Biaxial Mechanical Properties of Vacuum Melted, Type 316 Stainless Steel Tubing," T. R. Padden, W. E. Ray, E. J. Tarby, K. C. Thomas
 - II. "Cladding Weldability Study," D. N. Elliott and W. E. Ray

4.0 SUMMARY OF CURRENT PROGRESS

Under Task SSDA-210, the major activities were directed to completion of the topical report for the Vacuum Melted Steels Task and the continuation of Defects Evaluation Task.

The following procurements, characterizations, tests, measurements, and observations were completed during the report period:

The final delivery of tubing ordered for the Defects Evaluation Task was received and accepted, and the order was closed.

Preliminary non-destructive eddy current characterization of 12 tubing lots, having various finishing steps, was completed and the effects of the variables evaluated.

A total of 12 stress rupture tests in argon and one in air of defected and non-defected specimens were completed. The results were compared with the stress rupture curve previously obtained for this lot of material.

Three stress rupture specimens which had failed at previously defined defects were characterized by rupture morphology, strain profile, post-test wall thickness measurements, light microscopy, and scanning electron microscopy. A preliminary and tentative evaluation was made of the effect of longitudinal defects on rupture life, rupture ductility, local wall strain, and rupture morphology.

Characterization of as-fabricated Cartech tubing was initiated using the methods employed in the Vacuum Melted Steels Task.

SSDA-210 EVALUATION OF AUSTENITIC STAINLESS STEEL CLADDING

T. R. Padden, W. E. Ray, E. J. Tarby, and K. C. Thomas

1.0 OBJECTIVES

The objective of this task was to characterize in detail, by microstructural analysis, chemical analysis, and mechanical property testing, thin-wall stainless steel tubing, fabricated under carefully controlled commercial practice. This information was to be used for:

1. Enhancing the understanding of the effect of fabrication processes and resulting structure on the properties of thin-wall tubing.
2. Providing out-of-reactor data required to predict and improve swelling behavior and strain limits of cladding in LMFBR environments.

The objective of a supplementary weldability investigation was to determine the effect of the degree of cold working on the weldability of Type 316 stainless steel tubing.

2.0 PRIOR WORK

During the first year (FY-1969), a test program was prepared and initiated with air melted, annealed Type 316 stainless steel tubing, 0.300-inch OD at three wall thicknesses (0.010, 0.012, and 0.014-inch), and 0.250-inch OD by 0.016-inch wall. Extensive biaxial burst testing at 850, 1000, 1200, and 1300°F and chemical and microstructural evaluation of the tubing were performed, and biaxial stress rupture testing was initiated. This part of the program was completed during the second year and included a thermal aging study of several lots of the air melted materials aged for times up to 5000 hours.

The program was extended to include a systematic investigation of vacuum melted, Type 316 stainless steel plug drawn tubing. Twelve lots of tubing ordered during FY-1969 and received at the beginning of FY-1970 were extensively tested and characterized during FY-1970 and the beginning of FY-1971. This tubing included 12 combinations of three vacuum melting practices, two grain sizes and the two finished conditions (20 percent cold worked and solution annealed). In addition, two lots of planetary swaged tubing were procured and included in the test program.

The characterizations of these tubing lots included light and electron microscopy, electron and X-ray diffraction, hardness measurements, chemical analysis, electron probe analysis, pole figure studies, and mechanical property testing. Tubing was tested under biaxial conditions to determine both

short-time tensile and the longer-time stress rupture properties. Post-test specimens were evaluated for rupture morphology, strain profile, local wall strain, and microstructural changes. This vacuum melted steels study was completed during FY-1971.

A cladding defects evaluation study currently in progress was also initiated during the FY-1971. The work program for this study included eddy current and ultrasonic non-destructive testing (NDT) of tubing procured from two suppliers and with various finishing procedures, along with statistical evaluation of NDT results and limited mechanical property testing. The program also included application of previously developed pre- and post-test specimen characterization procedures to defected and non-defected specimens with the objective of evaluating the effects of various types of cladding defects on mechanical properties.

The work completed up to March 31, 1971 under Contract No. AT(30-1)-4210, Task 3 has been reported in detail in eleven quarterly progress reports.^[3-13] In addition a combined topical report,^[2] summarizing the results and conclusions of vacuum melted steels study and a supplementary weldability investigation, was issued in July 1971. A paper covering part of this work was also presented at the 1970 Winter Meeting of the ANS.^[14]

A thermal aging study conducted on air melted, Type 316 stainless steel during the second year of this contract is fully covered in quarterly progress report WARD 4135-5.^[8] Subsequent, relevant thermal aging studies conducted as Westinghouse research programs are covered in Westinghouse reports by Weiss, Stickler, and co-workers.^[15, 16] A related deformation study by Stickler and co-workers is covered in another Westinghouse report.^[17]

3.0 CURRENT PROGRESS

3.1 Procurement and Handling

A total of 18 lots of tubing were received from Superior Tube Co. during FY 1971. The 12 tubing lots listed in Table 1 were 20 percent cold worked, Type 316 stainless steel tubing plug drawn to a reduction schedule similar to Superior Lot No. 42402, but with different finishing steps. The variations in finishing operations included: pickling and no pickling; polishing and no polishing; straightening by various procedures and no straightening. The straightening methods included Mackintosh-Hemphill, Whizzy, Medart, stretch, and hand straightening. In addition, two NDT acceptance standards were specified for the order, one being more stringent than the other. The purpose of the two standards was to obtain tubing with two different levels of naturally occurring defects and fabricated by the same procedure.

The remaining six lots of tubing contained experimental planetary swaged tubing; these lots had various reduction schedules for the swaging operations. The six lots included annealed, 10, 20, and 30 percent cold worked tubing.

Table 1. Fabrication Variations of Plug Drawn Tubing
Procured During FY-1971

Superior Lot No.	NDT Specifications	Pickling	Polishing	Straightening
58390	A	YES	YES	WHIZZY
58391	B	YES	YES	WHIZZY
58393	Not Tested ^(a)	YES	NO	HAND
58394	A	YES	NO	STRETCH
58395	A	YES	NO	MEDART
58396	A	YES	NO	MACKENTOSH- HEMPHILL
58397	A	YES	NO	WHIZZY
58398	Not Tested ^(a)	YES	NO	NONE
58399	B	YES	NO	WHIZZY
58401	A	NO	NO	WHIZZY
58402	Not Tested ^(a)	NO	NO	NONE
58403	B	NO	NO	WHIZZY
<p>All 12 lots fabricated from Cartech heat 91695, double vacuum melted, Type 316 stainless steel by the sequence of tube reducing, rod drawing, and plug drawing according to a reduction schedule similar to lot 42402.</p> <p>NDT Spec. 'A' - Tubing showing indications less than the minimum response from a standard containing one each, ID and OD longitudinal and circumferential EDM notches 1.0 mil deep x 2.0 mils wide x 30.0 mils long</p> <p>NDT Spec. 'B' - Tubing which failed NDT Specification A but passed B standard containing one OD longitudinal EDM notch 1.5 mils deep x 4.0 mils wide x 250 mils long and a radial hole 6.0 mils diameter x 85 percent of wall thickness.</p>				
<p>(a) Not UT tested because of insufficient straightness.</p>				

3.2 Defects Evaluation Program

3.2.1 General

During the latter part of FY-1970 and the early part of FY-1971, non-destructive testing equipment was procured and installed, using Westinghouse funds. Throughout FY-1971 various modifications and additions were made as required.

As part of the Defects Evaluation Program, this equipment was tested and calibrated against standards fabricated at ARD according to a drawing supplied by WADCO,^[18] and a calibration standard developed at ARD,^[19] based on WADCO information. Initial eddy current runs, calibrated against a 12-notch standard,^[18] were made on 10 tubes (130 ft) of Lot 42402 previously procured for the Vacuum Melted Steels Program. These runs were used to test the equipment and to establish procedures for evaluating tubing which had been ordered but not received.

A series of 90 runs (10 runs/day for 9 days) were then made on the 12-notch standard to establish the average response and the 95 percent confidence limits for each notch in the standard. Using these results as a basis, 640 feet of Lot 42402 tubing was then tested and evaluated. When the new tubing order was received, the developed procedures and evaluations were applied to a total of 805 feet of 20 percent cold worked tubing, representing 12 combinations of finishing steps and ultrasonic acceptance levels.

A similar sequence of testing and calibration steps was started for the ultrasonic test equipment, but the systematic UT test program was hampered by equipment failure. This equipment has now been returned to the manufacturer as not being acceptable.

Also, a replica procedure was developed for use as the basis of comparison between microscopy evaluation of naturally occurring internal diameter (ID) defects and non-destructive testing.

Concurrent with the NDT calibration and procedure development, stress rupture tests were initiated on intentionally defected specimens and on specimens containing handling scratches. The progress of the Defects Evaluation Program through March 31, 1971 has been reported in the previous three quarterly progress reports for the year.^[11, 12, 13] Included in this final report are the recent results, plus those previous results which are pertinent to the evaluation of the current data, and a listing of the NDT equipment now in use at ARD. This report also contains a summary of the stress rupture results from defected specimens and an evaluation of three post-stress rupture specimens which had different types of defects.

3.2.2 Non-Destructive Test Facilities

The non-destructive test facilities at ARD were procured and put into operation with Westinghouse funds. The equipment consists of the following:

EDDY CURRENT UNIT

One Nortec NDT-1 Eddy Current Tester
One Tektronix 564-B Storage Oscilloscope
One Nortec Drive Mechanism
One Superior 16-B Powerstat Speed Control
One Brush (6 channel) 260 Strip Chart Recorder

AIR GAGE UNIT

Two Federal 232 Amplifiers
Two Federal Air Electronic Transducers
One Federal 0.200-inch ID Probe
One Federal 0.230-inch OD Ring
One Westinghouse Tube Transport
One Federal MDR4 Regulator
One Federal AFL-9 Filter
One Hankinson Refrigeration Type Drier

ULTRASONIC UNIT

1. Flaw Detection:

Four Nortec 102 Plug-in Modules
Two Tektronix 127 Preamplifiers
One Tektronix RM15 Oscilloscope
Four Nortec 10 MHz Transducers
One Brush (6 channel) 260 Strip Chart Recorder
One Tac-Tic Transport System

2. Wall Thickness and Eccentricity Unit:

One Sonics VTR 12 Visual Trace Readout
One Sonics DTG2R Digital Thickness Gage
One Sonics TAM-3 Thickness Alarm Module
One Tektronix R561B Dual Trace Oscilloscope
One Honeywell 117-06 Preamplifier
One Honeywell 1508 Visicorder
One Aerotech 10 MHz Transducer
One Tac-Tic Transport System

3.2.3 Evaluation of Facilities

3.2.3.1 Eddy Current

The eddy current equipment is sufficiently sensitive for cladding characterization, and together with the standardized adjustment and calibration procedures gives reproducible results and appears to be satisfactorily stable over long periods of time.

Figure 1 is an example of the response obtained from a 12-notch EDM standard.^[18] Figures 2 and 3 illustrate the response obtained from a control specimen containing no defects, and from specimen areas containing handling scratches identified and located visually with a microscope. Also included in these figures are the ultrasonic test responses from these same areas. The sizes of standard notches which would give the same magnitudes as the responses observed are given for each trace.

In general, the eddy current equipment is quite sensitive to OD scratches, both axial and transverse in orientation. Based on a comparison of eddy current response to depth of defect, this test method appeared to be more sensitive to scratches than to EDM notches. In general, actual depth of the scratch was less than that of an EDM notch which would give the same response. The ultrasonic responses to the same scratches indicated sufficient sensitivity in three of the four specimens examined but no response in the fourth. Additional work and more reliable UT equipment and procedures would be required to make a definitive comparison between the two test methods.

3.2.3.2 Ultrasonic Testing

After numerous difficulties and repairs, the UT equipment appeared to be functioning satisfactorily and a number of runs were made. Then a long-term stability problem was discovered when the 12-notch standard was run 23 times along with approximately 250 feet of stainless steel tubing (Superior Tube Company Lot #42402). Reduction and subsequent evaluation of the 23 ultrasonic traces showed that the notch standard impulse response could not be held within the 95 percent confidence limits previously established for the notch acceptance criteria. Attempts were made to correct the difficulties, and finally the four Nortec modules were returned to the manufacturer as "not repairable." Ultrasonic testing has been discontinued until these problems are resolved.

3.2.3.3 Wall Thickness and Eccentricity Measurements

The wall thickness and eccentricity equipment appears to be satisfactory. Traces representing approximately 250 feet of tubing (Superior Tube Company Lot #42402) were reduced for data analysis subsequent to calibration of these units using the source material reference standards.^[19] It was found that all tubes (23) were within the specified wall thickness tolerance of 0.015 inch (± 0.001 inch). The measured variation was from 0.1460 inch to 0.01581 inch. Typical examples of the variations within individual tubes are given in Table 2. An example of a typical wall thickness trace is shown in Figure 4.

3.3 Non-Destructive Testing

3.3.1 Eddy Current

A total of 805 feet of the tubing, purchased for the Defects Evaluation

NOTCH	ORIENTATION	LOCATION	DEPTH (mils)
1	A	ID	0.5
2	A	ID	1.5
3	A	OD	0.5
4	A	OD	1.5
5	C	OD	1.5
6	C	OD	0.5
7	C	ID	1.5
8	C	ID	0.5
9	A	OD	1.0
10	C	OD	1.0
11	A	ID	1.0
12	C	ID	1.0

A - AXIAL	OD - OUTSIDE SURFACE
C - CIRCUMFERENTIAL	ID - INSIDE SURFACE

Figure 1. Eddy Current Trace of 12 Notch Standard Type 316 Stainless Steel Tubing - Superior Lot 42402

4309-1

SAMPLE 42402-6-2 CONTROL-NO DEFECTS

**EDDY CURRENT CHART
NO RESPONSE**

**ULTRASONIC CHART
NO RESPONSE**

SAMPLE 42402-7-1 TRANSVERSE SCRATCH

**EDDY CURRENT CHART
RESPONSE < 0.5 mil
STANDARD TRANSVERSE
OD NOTCH**

**ULTRASONIC CHART
RESPONSE < 0.5 mil
STANDARD TRANSVERSE
OD NOTCH**

Figure 2. NDT Strip Chart Recordings of 20 Percent Cold Worked, Type 316 Stainless Steel

SAMPLE 42402-1-1

EDDY CURRENT CHART
RESPONSE ≈ 0.5 mil
STANDARD AXIAL OD NOTCH

ULTRASONIC CHART
RESPONSE ≈ 0.5 mil
STANDARD AXIAL OD NOTCH

SAMPLE 42402-6-1

EDDY CURRENT CHART
RESPONSE ≈ 1.0 mil
STANDARD AXIAL OD NOTCH

ULTRASONIC CHART
NO RESPONSE

SAMPLE 42402-8-1

EDDY CURRENT CHART
RESPONSE < 0.5 mil
STANDARD AXIAL OD NOTCH

ULTRASONIC CHART
RESPONSE ≈ 0.5 mil
STANDARD AXIAL OD NOTCH

Figure 3. NDT Strip Chart Recordings of 20 Percent Cold Worked, Type 316 Stainless Steel Containing a Naturally Occurring Longitudinal Scratch

4309 3

Figure 4. Typical Wall Thickness Recording for Lot 42402 Type 316 Stainless Steel Tubing With 0.015 Inch Wall

4309-4

Table 2. Wall Thickness Variations for Lot 42402, Type 316 Stainless Steel Tubing		
Tube No.	Min. Wall Thickness (mils)	Max. Wall Thickness (mils)
42402-1	15.06	17.70
42402-6	14.61	15.30
42402-7	14.62	15.30
42402-8	14.60	15.32

Program, has been eddy current tested and the results evaluated. All tubing was fabricated from Cartech heat No. 91695, double vacuum melted, Type 316 stainless steel and was plug drawn to a reduction schedule similar to Superior Lot No. 42402. The various combinations (12 lots) of pickling, polishing, straightening, and NDT acceptance testing are shown in Table 1.

Surface polishing is the fabrication variable showing the most pronounced effect when observed by eddy current testing (Figure 5). Polishing causes an eddy current background noise level which is sufficiently high that small-size defects would be obscured. As a result, the defect levels in the two polished lots could not be evaluated by the eddy current tests.

The difference in background noise level due to the other variables in non-polished tubing is relatively slight and the absolute level is sufficiently low that small defects can be detected.

The eddy current traces from these 10 lots were measured and the data reduced. Table 3 lists the lot numbers for these materials, the total number of feet tested for each lot, and the eddy current indication frequency per foot in three size classes. The table also includes the accumulated frequencies per foot for indications greater than 3 chart units in a standardized test and greater than 6 chart units, which is twice background. Table 4 ranks these tubing lots according to increasing frequency per foot for defect indications greater than 6 chart units. The rank based on indications greater than 3 chart units is included for comparison. Also included in Table 4 is the description of the fabrication variables for each lot.

The combinations of variables showing the lowest indication frequencies are the two lots which were Whizzy straightened and passed standard A. The Whizzy-straightened materials which failed standard A, but passed standard B (UT tests) are lower in rank in the table. The three lots having the highest indication frequencies, are the lots which were mechanically straightened by the Mackintosh-Hemphill, stretch, and Medart processes. These three lots ranked 8, 9, 10 in the table in both size classes in spite of the fact that they all had passed the A acceptance test.

Hand-straightening and no straightening were intermediate in rank. However, from a practical view point, hand straightening or no-straightening would

LOT 58390

POLISHED, PICKLED,
WHIZZY STRAIGHTENED

LOT 58398

NOT POLISHED, PICKLED,
NOT STRAIGHTENED

LOT 58397

NOT POLISHED, PICKLED,
WHIZZY STRAIGHTENED

LOT 58402

NOT POLISHED, NOT PICKLED,
NOT STRAIGHTENED

Figure 5. Typical Eddy Current Responses - Various Lots of Tubing

Table 3. Eddy Current Defect Indication Frequency Evaluation of Various Tubing Lots

Lot	Ft. Tested Eddy Current	UT Acceptance Standard	Eddy Current Indications/ft for Indicated Size Ranges in Standard Chart Units				Accumulated Frequency >3 Chart Units	Accumulated Frequency >6 Chart Units
			3-6	6-9	9-15	>15		
58390	205(a)	A	--	--	--	--	--	--
58391	102(a)	B	--	--	--	--	--	--
58393	40	(b)	0.60	0.40	0.18	0.15	1.33	0.73
58394	13	A	0.92	0.77	0.15	0.08	1.92	1.00
58395	26	A	1.07	0.81	0.08	0.19	2.15	1.08
58396	33	A	1.12	0.58	0.15	0.15	2.00	0.88
58397	66	A	0.99	0.21	0.12	0.03	1.35	0.36
58398	32	(b)	1.09	0.16	0.12	0.22	1.59	0.50
58399	27	B	0.96	0.67	0.15	0.04	1.78	0.82
58401	111	A	0.86	0.30	0.10	0.04	1.30	0.44
58402	88	(b)	0.74	0.51	0.10	0.12	1.58	0.74
58403	52	B	1.02	0.27	0.19	0.08	1.56	0.54

(a) Not evaluated by Eddy Current because of high background noise

(b) Not tested by Ultrasonics because of insufficient straightness

A Standard - Longitudinal and circumferential ID and OD notches
0.030-inch long, 0.002-inch wide and 0.001-inch deep.

B Standard - Longitudinal notch 0.250-inch long, 0.004-inch wide and 0.0015-inch deep plus radial hole 0.006-inch diameter x 85% of wall in depth (0.0015-inch)

Table 4. Ranking of Various Tubing Lots According to Increasing Eddy Current Defect Indication Frequencies

Lot	UT Acceptance Standard	Pickled	Polished	Straightened	Rank For >6 Chart Units	Rank For >3 Chart Units
58397	A	Yes	No	Whizzy	1	3
58401	A	No	No	Whizzy	2	1
58398	(a)	Yes	No	None	3	6
58403	B	No	No	Whizzy	4	4
58393	(a)	Yes	No	Hand	5	2
58402	(a)	No	No	None	6	5
58399	B	Yes	No	Whizzy	7	7
58396	A	Yes	No	Mackintosh Hemphill	8	9
58394	A	Yes	No	Stretch	9	8
58395	A	Yes	No	Medart	10	10
(a) Not tested by Eddy Current because of insufficient straightness						

have to be eliminated from consideration for cladding specifications since the tubing produced by these methods is not sufficiently straight for the application. There appears to be no strong correlation of defect frequency with pickling. For two pairs of pickled and non-pickled lots the pickled material ranked higher in the table, but for a third pair it ranked lower.

Considering the table as a whole:

1. Whizzy straightening is the best straightening process from an eddy current viewpoint.
2. Pickling appears to have little effect.
3. Pre-selection of the tubing by ultrasonic testing to the more restrictive specification (standard A) reduces the observed eddy current defect indication frequency relative to material tested to the B standard.

3.3.2 Discussion of Eddy Current Testing Relative to Ultrasonic Testing

Although there is correlation between results from eddy current testing and ultrasonic testing, there are several pieces of experimental evidence which indicate that eddy current and ultrasonic testing can not be used interchangeably to measure defects frequencies. The surface polished tubing from this set of materials (lots 58390 and 58391) could not be evaluated by eddy current testing because of the high background noise. This general noise level was about 12 chart units in a standardized test and corresponded to the eddy

current response level which would be obtained from a 1-mil-deep EDM notch in an unpolished tube. The ultrasonic tests gave quite different results. Lot 58390 gave UT indications lower than the A standard which contained both ID and OD notches one-mil deep. Lot 48391 similarly passed UT, calibrated against the B standard which contained a 1.5-mil notch. The UT charts supplied with the tubing showed that UT background noise levels for these two polished lots were similar to those from comparable non-polished lots in the series. No effect of polishing was observed.

With respect to detecting scratches (Figures 2 and 3), eddy current and ultrasonic testing gave comparable responses to some scratches and not to others.

3.4 Stress Rupture Testing - Defected Specimens

Nine defected specimens and two non-defected control specimens from the 20 percent cold worked lot (42402) were stress rupture tested in argon and one defected specimen was tested in air. In addition, one non-defected, annealed specimen from lot 42403 was tested in argon. Some of the defects in these specimens were natural defects, others were EDM notches of various sizes. All tests were conducted at 1300°F (nominal) and 23,000 psi (nominal) hoop stress.

The stress rupture data are listed in Tables 5 and 6 along with the defect type, defect size, and location for each specimen.

The three possible direct results expected from stress rupture testing defected specimens were observed in this series of tests.

1. The specimen fails at the defect and there is significant reduction in rupture life.

This is illustrated by Specimens 10-7 and 10-9.

2. The specimen fails at the defect and there is no reduction in rupture life. In this case the defect appears to cause a slight preference for rupture to occur at that particular location.

This case is illustrated by Specimen 1-1.

3. The specimen fails away from the defect, and therefore, the defect has no effect on the rupture life of that specimen.

This case is illustrated by the seven other defected specimens in Table 5 and the one specimen in Table 6.

The rupture times for the twelve lot 42402 specimens were normalized to 1300°F using the m-factor of the Chitty-Duval parameter,^[9] and are plotted in Figure 6. For comparison, both the average stress rupture line for lot 42402 that was obtained previously as part of the Vacuum Melted Steels Program^[2] and the minimum and maximum limits in the rupture time which would be expected from variations in wall thickness of ± 1 mil (the wall thickness

**Table 5. Biaxial Stress Rupture Data for Type 316
Stainless Steel Tubing Tested in Argon**

Sample	Material Condition	Wall Dimension (in.)	Nom. Temp (°F)	Test Temp (°F)	Stress (ksi)	Rupture Time (hr)	Rupture Type
42402-10-2	IVCEV-20%CW-FG	0.015	1300	1303	23	305.5	Pinhole
42402-10-4				1298	23	328.1	Split
42402-10-5				1302	23	319.0	Pinhole
42402-10-6				1305	23	159.0	Split
42402-10-7(a)				1302	23	148.7	Split
42402-10-9(a)				1305	23	140.3	Pinhole
42402-1-1(a)				1308	23	218.5	Split
42402-6-1				1308	23	171.0	Split
42402-6-2				1303	23	458.0	Split
42402-7-1				1296	23	226.0	Pinhole
42402-8-1				1301	23	169.5	Pinhole
42403-00-1	IVCEV-ANN-FG	0.015	1300	1300	23	15.5	Pieces

Sample	Defect Type & location	Length (in.)	Width (in.)	Depth (in.)	Failure at Defect
42402-10-2	EDM - I - OD	0.0302	0.0022	0.00105	no
42402-10-4	EDM - I - ID	0.0302	0.0021	0.0010	no
42402-10-5	EDM - L - ID	0.0303	0.0021	0.00155	no
42402-10-6	EDM - L - OD	0.240	0.0022	0.00054	no
42402-10-7(a)	EDM - L - OD	0.240	0.0022	0.00108	yes
42402-10-9(a)	EDM - L - ID	0.240	0.0023	0.00160	yes
42402-1-1(a)	NAT - L - OD	5.25	-	0.0001	yes
42402-6-1	NAT - L - OD	1.25	-	0.0001	no
42402-6-2	Control sample no defect	-	-	-	-
42402-7-1	NAT - C - OD	Spiral	-	0.0001	no
42402-8-1	NAT - L - OD	0.1875	-	0.0001	no
42403-00-1	Control sample no defect	-	-	-	-

CW - Cold Worked

ANN - Annealed

IVCEV - Consumable +
Induction Vacuum Melt

L - Longitudinal

EDM - Electro-Discharge
Machining

NAT - Naturally Occurring

FG - Fine Grain

ID - Inside Diameter

C - Circumferential

OD - Outside Diameter

(a) Destructively Evaluated After Test

42402-10-7 Refer to as specimen A

42402-10-9 Refer to as specimen B

42402-1-1 Refer to as specimen C

Table 6. Biaxial Stress Rupture Data for Type 316
Stainless Steel Tubing Tested in Air

Sample	Material Condition	Wall Dimension (in)	Nom. Temp. (°F)	Test Temp. (°F)	Stress (ksi)	Rupture Time (hr)	Rupture Type
42402-10-1	IVCEV-20%CW-FG	0.015	1300	1304	23	198.5	Split
Sample contains an electrodischarge machined longitudinal OD notch, 0.0301" long x 0.0021" wide x 0.00058" deep - sample failed away from notch.							

tolerance in the specification for this lot) are included in Figure 6. These rupture time limits were the times taken from the average curve using the hoop stresses which would exist in 14 and 16-mil wall tubing having the same internal gas pressure as 15-mil tubing at 23,000 psi hoop stress.

Of the four specimens (1-1, 6-1, 7-1 and 8-1) which contained naturally occurring handling scratches (all 0.1 mil deep or less), only one specimen (1-1) failed at the defect. It had a longitudinal OD scratch and showed no significant reduction in rupture life. The other three specimens in this group also ruptured within the maximum and minimum time limits due to possible wall thickness variations.

Specimen 6-2 was a control sample which was carefully selected to be defect free by eddy current, ultrasonic, and visual inspection. It showed a slightly longer than expected rupture life. In this case, wall thickness variations allowed by the specification alone would not account for the increased stress rupture life of this specimen.

Specimens 10-4, 10-5, 10-9, 10-2, 10-6, and 10-7 contained EDM notches. Only samples 10-7 and 10-9 failed at the defect site, and both showed a reduction in stress rupture life; the samples which broke away from the defect showed no significant reduction of stress rupture life. Specimens 10-7 and 10-9 contained EDM notches 240 mils long, corresponding to 16 times the nominal wall thickness. Specimen 10-7 had a longitudinal OD notch 1.1 mils deep, and specimen 10-9 had a longitudinal ID notch 1.6 mils deep. In both cases the local wall thickness reduction due to the notch depth was sufficient to account for the reduced stress rupture life, even assuming that the wall in the vicinity of the notch had been a full 15-mils-thick prior to test.

The specimens which failed away from the defects contained EDM notches just as deep or deeper than the two specimens which failed at the notches; however, the notches in these specimens were only 30 mils long (i.e., two times the wall thickness).

For long EDM notches (240 mils) there also appears to be a depth effect in addition to the apparent length effect. The specimen with a longitudinal 0.5-mil-deep OD notch failed away from the defect; however, a specimen with

Figure 6. Biaxial Stress Rupture Results for 0.015 in. Wall, Type 316 Stainless Steel Tubing at 1300°F

4309-6

a notch 1.1 mils deep failed at the defect and had a reduced rupture life. The specimen with a 240-mil-long ID longitudinal notch 1.5 mils deep also failed at the notch and showed reduced rupture life.

The apparent length effect of EDM notches is tentatively interpreted as follows: at each end of a longitudinal notch there is a change in the local hoop stress resulting from the change in the local wall thickness; this change in stress level is not abrupt, however, since the tubing just outside the end of the notch tends to support the wall just inside the notch; and there is a smearing of both the stress and the strain at the end of the notch. Since smearing extends over some distance from the end of the notch toward its center, there should be some critical length for narrow longitudinal notches where the end effects from both ends overlap and the notch effect is minimized. For specimens tested under these conditions, that critical length appears to be between 2 times and 16 times the wall thickness.

3.5 Post-Stress Rupture Specimen Characterization

The three specimens footnoted as A, B, and C in Table 5 were evaluated after test using the characterization methods previously described in the topical report for Vacuum Melted Steels Program.^[2] All three specimens were fabricated from the same double vacuum melted, fine grained, 20 percent cold worked tubing (Lot 42402), and tested to rupture at 1300°F nominal and 23,000 psi hoop stress.

Figure 7 illustrates the rupture morphologies of these three specimens which had different kinds of pretest defects. Specimen A failed with a split-type rupture initiating at an intentional OD longitudinal electro-discharge machined (EDM) notch (240 mils long x 2.2 mils wide x 1.1 mils deep). The discoloration pattern due to oxidation on the rupture surface indicated that longitudinal cracks had formed which penetrated only part way through the wall but extended over the whole length of the EDM notch before final loss of the gas pressure occurred, and that the gaping split was the final step. Stereo examination of the split showed that the rupture surface was markedly tilted with respect to the hoop direction and that the direction of the tilt changed in several areas along the length of the rupture.

Specimen B failed with a pin hole rupture initiating at an intentional ID longitudinal EDM notch (240 mils long x 2.3 mils wide x 1.6 mils deep). The OD surface of the tube showed only a depressed flat area and a few very fine cracks. The width of the depressed area, on the OD surface, over the 2.3-mil wide ID notch was about 30 mils wide and about 240 to 250 mils long.

Specimen C failed at an OD handling scratch in preference to an OD longitudinal EDM notch (30 mils long x 2.2 mils wide x 1 mil deep), located 1-1/2 inches from the failure site. This rupture consisted of a crack-type separation, 200 mils long, which initiated at the OD surface.

Figure 8 illustrates the strain profile curves for the three specimens. Both A and B failed with reduced rupture life and lower shoulder ductility ($\Delta D/D$ measured adjacent to the rupture) than Specimen C, which reached full term rupture life before failure.

(a) CONTAINED EDM INTENTIONAL OD-L NOTCH
240 x 2.2 x 1.1 mils DEEP
RUPTURED WITH SPLIT AT NOTCH
 $T_R = 149$ hr, 23,000 psi, 1302°F

10X

(b) CONTAINED EDM INTENTIONAL ID-L NOTCH
240 x 2.3 x 1.6 mils DEEP
RUPTURED WITH PINHOLE AT NOTCH
 $T_R = 140$ hr, 23,000 psi, 1305°F

10X

(c) CONTAINED LONGITUDINAL OD HANDLING
SCRATCH AND EDM INTENTIONAL OD-L
NOTCH, 30 x 2.2 x 1.0 mils DEEP
RUPTURED AT SCRATCH WITH LONGITUDINAL
CRACK, $T_R = 305$ hr, 23,000 psi, 1303°F

10X

Figure 7. Rupture Morphologies of Defected Stress Rupture Specimens

4309-7

Figure 8. Strain Profile Plots - Type 316 Stainless Steel Tubing Tested to Rupture at 23,000 psi Hoop Stress at 1300°F in Argon

4309-8

Figure 9 illustrates the local wall thickness reduction ($\Delta t/t_0$) around the tube circumference at the transverse planes indicated in Figure 8. These local wall strain curves based on the nominal pretest wall thickness and post-test wall measurements indicate that both the ruptured and non-ruptured sections of all three specimens had non-uniform wall strain during test. Based on results presented previously^[2] the most probable cause for the non-uniform strain is local wall thickness variations in the pretest tubing.

Specimens A and B were cut from the same tube and all four sections from these two specimens have the same relative angular orientation as plotted in Figure 9. The curve shapes indicate that, prior to test, this tube had a thin side and a thick side (i.e., longitudinally aligned eccentricity), and that the EDM notches had been placed in the thick side in each case.

The $\Delta t/t_0$ curve for specimen B is of particular interest since it exhibits pronounced local wall strain in the immediate vicinity of the rupture and low wall strain a short distance away. Specimen C shows high local wall strain on one side of the rupture but not on the other. Specimen A was only measured 3/4-around the circumference. A piece of this specimen was removed, before mounting, for other purposes.

Figure 10 shows the microstructures of the rupture edge of specimen A in the transverse plane indicated in the insert. Several features of this rupture are apparent. The tilt angle of the rupture edge, viewed in cross-section, is approximately 35 degrees relative to the hoop direction of the tube. The cross-section of about half of the EDM notch can be seen in the upper left of this rupture surface. The dark line extending from the OD down about 0.8 of the rupture surface is the oxide film previously described. The structure in the vicinity of the rupture shows a fairly high concentration of grain boundary cavities, particularly near the OD, and there is considerable grain distortion near the ID edge. The rupture surface near the ID edge probably failed rapidly as the final split occurred.

The scanning electron micrographs in Figure 11 illustrate several other significant features of this rupture not previously described. Figure 11b and c shows the ends of the split and the outline of the original EDM notch. The OD crack which initiated the rupture was formed entirely within the 2.2-mil width of the EDM notch, and the length of the final split was generally confined to the 240-mil length of the notch. High magnification scanning electron micrographs of numerous areas of the split edge revealed mostly dimple-ductile-type rupture surface morphology as illustrated by the scan shown in Figure 11e, but occasionally, areas were observed which appeared to contain the grain boundary cavities observed in polished sections; Figure 11d is an example of this.

In spite of extensive examination at 5 transverse locations through the notch of specimen B, no continuous rupture through the wall of this specimen was observed. Apparently, it failed by leaking the internal pressurizing gas through inter connected grain boundary cavities.

Several transverse planes through the ID notch of specimen B (Figure 12) illustrate a number of significant rupture features of this specimen. Figure 12a is a transverse section through the ID notch showing a shearing

0 DEGREE LOCATION ARBITRARILY ASSIGNED TO RUPTURE.
 ANGULAR ORIENTATION OF ADDITIONAL SECTION RELATIVE
 TO THE RUPTURE IS MAINTAINED

Figure 9. Local Wall Thickness Reduction Versus Angle Around Tube Circumference
 4309-9

NOTCH SIZE
AT 500X

(a)

(b)

(c)

- (a) CROSS SECTION OF RUPTURE EDGE (90X)
- (b) MACROGRAPH SHOWING TRANSVERSE PLANE EXAMINED (10X)
- (c) HIGHER MAGNIFICATION MICROGRAPH OF RUPTURE EDGE (450X)

人 SPECIMEN PLANE

Figure 10. Rupture Area of Specimen "A"

4309-10

(a) 160X

(b) 160X

(a,b) TERMINI OF SPLIT, SHOWING OUTLINE
OF EDM NOTCH PLACED IN SPECIMEN
PRIOR TO TEST

(c) MACROGRAPH OF RUPTURE

(d) GRAIN BOUNDARY CAVITY AREA

(e) DIMPLE-DUCTILE-TYPE RUPTURE

LM SECTION

(c) 20X

(d) 2000X

(e) 800X

Figure 11. Scanning Electron Micrographs
of Specimen "A" Rupture

- (a) TRANSVERSE SECTION THROUGH ID NOTCH (100X)
 (b) TRANSVERSE SECTION THROUGH ID NOTCH 10 TO 15 mils
 DEEPER THAN NOTCH (a) (100X)
 (c) LOWER MAGNIFICATION OF PLANE SHOWN IN (b) ILLUSTRATING
 THE HIGH LOCAL WALL STRAIN (50X)
 (d) MAGNIFICATION OF 45 DEGREE SHEAR ZONE SHOWN IN (a) (500X)

(a)

(b)

(c)

Figure 12. Rupture Area of Specimen "B"
 4309-12

mode of failure along a plane approximately 45 degrees to the hoop direction. Figure 12b is a higher magnification micrograph of this shear zone showing the intergranular cavities resulting from grain boundary sliding. Figure 12c is also a transverse section through the ID notch, but 10 to 15 mils deeper into the specimen than a. At this cross section, the shear zones are apparent in both the 45 degree directions, relative to the hoop direction. Figure 12d is a lower magnification of the plane shown in c. This micrograph illustrates the high local wall strain in a triangular wedge of the tube wall having a 90-degree apex adjacent to the notch, and the depressed flat area opposite the notch.

The structure (Figure 13) of the transverse plane through the rupture of specimen C pictorially shows the high local wall strain on the one side of the rupture, and relatively low strain on the other (described graphically in Figure 9c). The right side appears to have pulled away from the left. The tilted rupture edge of the left side of this specimen is also, on the average, about 35 degrees to the hoop direction as in specimen A but not as uniform as in either specimen A or B. Specimen C also contains a much higher frequency of grain boundary cavities than either A or B, but this is to be expected since it reached full term rupture life whereas both A and B failed prematurely.

3.6 Post-Test Evaluation

Considering the results from specimens A and B together, it appears that the effect of long axially oriented EDM notch-type defects is as follows:

When the notch is sufficiently long and deep that its end effects are insufficient to overcome the local wall thickness reduction, the local hoop stress at the notch increases significantly, and the specimen fails at the notch with reduced rupture life. There is also a reduction in shoulder ductility ($\Delta D/D$), relative to a non-defected specimen run under the same nominal test conditions, because the areas of the defected tube remote from the rupture experience the same hoop stress and thus the same creep rate as a non-defected specimen, but for a shorter time.

There is also a secondary notch influence on the rupture, resulting from the asymmetry of the wall shape in the cross sectional plane. Initially, the cross section of the wall appears as is schematically shown in Figure 14a, but apparently the stress distribution is such that the wall tends to assume a shape similar to 14b. This, combined with the resolution of the hoop stress into zones of high shear stress oriented 35 to 45 degrees to the hoop direction, produces a configuration similar to 14c. In the presence of the notch and in the absence of other local perturbations, both 45 degree directions are equally probable, and the result is a wall configuration which is symmetrical about a radial plane going through the notch, with two high shear zones originating at the notch.

Because of the high shear strain along those zones, grain boundary cavities are formed. This further weakens the structure in these locations. As a result, a local wedge-shaped area of the wall with the apex at the notch experiences high strain both along the shear direction and in the hoop

(a)

80X

(b)

500X

Figure 13. Rupture Area of Specimen "C"

Figure 14 Schematic Interpretation of Rupture Sequence in Notched Specimens

4309 14

direction. This permits the wall surface opposite the notch to become depressed and thus tend to balance the stresses.

The depressed surface opposite the notch, bounded by the ends of the shear zones, is considerably larger than the notch size. For a specimen with a 15-mil wall and 45 degree shear zones, the depressed area on the surface opposite the notch should be about 30 mils wide. When such a specimen fails, it may rupture along one or the other of the shear zones or alternate between them along the length of the rupture, as was observed in specimen A.

The rupture area of specimen B appears to be a fortuitous situation where the stresses in both 45 degree shear directions are about equally balanced. In addition, failure of this specimen without splitting also permitted a good cross sectional view of the mode of failure. The width of the depressed surface on a macrograph of this specimen (Figure 7b) is about 30 mils wide and corresponds to the width of the depressed surface in the cross sectional micrograph (Figure 12d).

There are two major differences between specimens A and B other than the location of the notch (on the ID in the one case and the OD in the other): In specimen B (which had the ID notch), the shear zones were about 45 degrees to the hoop direction, and in specimen A (with an OD notch), the shear zones were about 35 degrees. The second difference is that A ruptured with a split alternating between the two shear zones along the length of the rupture, and B failed with a pin hole rupture of interconnected cavities. The split in A, however, is probably a slightly more extreme case of the same sequence of failure which occurred in B.

It appears that the observed differences in rupture morphology between specimens with relatively deep (1 to 1.5 mil) longitudinal notches and specimens with shallow scratches (0.1 mil deep) or no visible defects are the result of the initially greater unbalance in stress distribution which exists in the notched specimens. In the unnotched specimens, there is the same tendency to form shear zones and rupture along directions 35 to 45 degrees to the hoop direction, but these zones are not so well defined as exemplified by Figure 13.

Based on our preliminary evaluation of a limited number of defected specimens, a tentative hypotheses are:

1. Type 316 stainless steel tubing is not notch sensitive. At least most of the reduction in rupture life and ductility can be accounted for simply by the reduction in wall thickness due to the notch.
2. There is probably a critical length of longitudinal notches as well as critical notch depth to cause significant reduction in rupture life. For longitudinal EDM notches the critical length is probably between 2 to 16 times the wall thickness (30 and 240 mils), and for long axial oriented notches the critical depth is probably between 0.5 mil and 1.1 mils.

3. Notches can influence the rupture morphology as well as the rupture life and the shoulder ductility.

3.7 Characterization of Carpenter Technology Tubing

Work in progress included the detailed characterization of annealed and 20 percent cold worked Cartech tubing. Table 7 summarizes the preliminary results, and Figure 15 illustrates some of the observations from the cold worked lot.

The results obtained for hardness, surface morphology, grain size, transmission microstructure (38-157 only), and inclusion identification by electron and X-ray diffraction were generally similar to those previously obtained for Superior Tube Company material. There were two slight differences. The OD surface morphology of the Cartech tubing showed no evidence of surface polishing as would be expected from the specification. The previously characterized Superior tubing, (lots 42402 and 42403) showed circumferential marks which together with the fabrication history were interpreted as the result of surface polished prior to the last draw. The specimens of Cartech tubing examined also showed a greater grain size variation than comparable Superior materials. There was insufficient time during the report period to evaluate this observation quantitatively.

Table 7. Carpenter Technology Tubing - Preliminary Characterizations		
Tube Identification	Tube 38-157 117210 Item 1	Tube 33-099 117210 Item 2
Condition	20% Cold Worked	Annealed
Hardness	273 DPH (500 gm)	143 DPH (300 gm)
Grain Size	ASTM 9-10	ASTM 9-10
Inclusions	Continuous and discontinuous thin stingers plus isolated particles	Same
Inclusion Identification	X-ray diffraction No results Selected area diffraction indicates SiO_2 and M_{23}C_6	X-ray diffraction M_{23}C_6 Selected area diffraction indicates M_{23}C_6
ID and OD Surface Morphology	Shows grain structure no grinding marks	Same
Transmission Structure	Heavily dislocated structure	No results Specimen appeared to be damaged in preparation

ID 180X OD 180X
SURFACE MORPHOLOGY

180X
LIGHTLY ETCHED LONGITUDINAL SECTION

360X
ETCHED TRANSVERSE SECTION

12,700X
TRANSMISSION ELECTRON MICROGRAPH

9,200X
ELECTRON MICROGRAPH OF
EXTRACTION REPLICA

SELECTED AREA DIFFRACTION OF
EXTRACTED INCLUSIONS

Figure 15. Characterizations of 20 Percent Cold Worked Carpenter Technology
Tubing
4309-15

LIST OF REFERENCES

1. F. Garafalo, F. Von Gemingin, and W. F. Domis, "Creep Behavior of Austenitic Stainless Steel as Affected by Carbides Precipitated on Dislocation," ASM Transactions, 54, No. 3, pp. 430-444, (September 1961).
2. WARD-4210T3-5 Combined Topical Report
T. R. Padden, W. E. Ray, E. J. Tarby, and K. C. Thomas, "Structural Characterization and Biaxial Mechanical Properties of Vacuum Melted Type 316 Stainless Steel Tubing."
D. N. Elliott and W. E. Ray, "Cladding Weldability Study."
3. WARD-3791-26 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending September 30, 1968."
4. WARD-3791-29 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending December 31, 1968."
5. WARD-3791-35 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending March 31, 1969."
6. WARD-3791-41 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending June 30, 1969."
7. WARD-4135-2 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending September 30, 1969."
8. WARD-4135-5 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending December 31, 1969."
9. WARD-4135-9 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending March 31, 1970."
10. WARD-4135-12 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending June 30, 1970."
11. WARD-4135-14 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending September 30, 1970."
12. WARD-4210T3-2 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending December 31, 1970."
13. WARD-4210T3-4 "Stainless Steel Cladding Development Quarterly Progress Report for the Period Ending March 31, 1971."

LIST OF REFERENCES (continued)

14. T. R. Padden, W. E. Ray, H. J. Snyder, and K. C. Thomas, "Development of Type 316 Stainless-Steel Tubing for LMFBR Fuel Element Cladding," Trans. Am. Nucl. Soc. 13, pp. 590-591 (1970)
15. B. Weiss and R. Stickler, "Phase Instabilities During High Temperature Exposure of 316 Austenitic Stainless Steel," Westinghouse Research Laboratories, Scientific Paper 70-1D4-STABL-P1, July 1970.
16. B. Weiss, C. W. Hughes, and R. Stickler, "SEM-Techniques for the Micro-characterization of Metals and Alloys," Westinghouse Research Laboratories, Scientific Paper 70-1D4-ANATT-P1, October 1970.
17. R. Stickler, C. W. Hughes, and G. R. Booker, "Application of the SA-ECP Method to Deformation Studies," Westinghouse Research Laboratories, Scientific Paper 71-1D4-ANATT-P1, February 1971.
18. USAEC-PNL Drawing SK3-15229 "Standard for Non-Destructive Testing of FFTF Fuel Cladding."
19. ARD Drawing ARD-210-M5, "Item 2 Wall Thickness Standard for Non-Destructive Testing."

DISTRIBUTION LIST

Division of Reactor Development and Technology
U. S. Atomic Energy Commission
Washington, D. C. 20545

Attn: Director

Assistant Director, Engineering Standards
Assistant Director, Nuclear Safety
Assistant Director, Plant Engineering
Assistant Director, Program Analysis
Assistant Director, Project Management (2)
Assistant Director, Reactor Engineering (2)
Assistant Director, Reactor Technology
Chief, Fuels and Materials Branch (3)
Chief, Fuel Engineering Branch
Chief, Reactor Vessels Branch
Chief, Coolant Chemistry Branch
Chief, Core Design Branch

Assistant Director
Pacific Northwest Programs
U. S. Atomic Energy Commission
P. O. Box 550
Richland, Washington 99352

USAEC-RDT Site Office
Argonne National Laboratory
Building 2
Argonne, Illinois 60439

USAEC-RDT Site Office
P. O. Box 2108
Idaho Falls, Idaho 83401

USAEC-RDT Site Office
P. O. Box 1446
Canoga Park, California 90304

USAEC-RDT Site Office
310 DeGuigne Drive
Sunnyvale, California 94086

USAEC-RDT Site Office
P. O. Box 2325
San Diego, California 92112

USAEC-RDT Site Office
P. O. Box 154
Madison, Pennsylvania 15663

USAEC-RDT Site Office
P. O. Box X
Oak Ridge, Tennessee 37830

USAEC-RDT Site Office
P. O. Box 550
Richland, Washington 99352

Division of Naval Reactors
Chief, Nuclear Materials Branch
U. S. Atomic Energy Commission
Washington, D. C. 20545

U. S. Atomic Energy Commission - DTIE(3)*(135)**
P. O. Box 62
Oak Ridge, Tennessee 37831

Manager (2)
U. S. Atomic Energy Commission
New York Operations Office
376 Hudson Street
New York, New York 10014

Office of Asst. General Counsel for Patents
U. S. Atomic Energy Commission
Washington, D. C. 20545

Director (2)
LMFBR Program Office-ANL
9700 South Cass Avenue
Argonne, Illinois 60430

Director, Metallurgy Division (2)
Argonne National Laboratory
9700 South Cass Avenue
Argonne, Illinois 60439

Manager, FFTF Project (2)
WADCO
P. O. Box 1970
Richland, Washington 99352

FFTF Fuels Department (2)
WADCO
P. O. Box 1970
Richland, Washington 99352

* submitted with transmittal form AEC-426

**submitted for transmittal to recipients under UKAEA/USAEC and
EURATOM/USAEC Fast Breeder Information Exchange arrangements.

Manager, Chemistry and Metallurgy Div.
Battelle Northwest Laboratory
P. O. Box 999
Richland, Washington 99352

Division Leader, Chemistry and Metallurgy Div. (CMB)
Los Alamos Scientific Laboratory
P. O. Box 1663
Los Alamos, New Mexico 87544

Director, Metallurgy and Materials Science Division
Brookhaven National Laboratory
Upton, New York 11973

Director, Metals and Ceramics Division (2)
Oak Ridge National Laboratory
P. O. Box X
Oak Ridge, Tennessee 37820

Division Chief, M & S Division
NASA - Lewis Research Center
2100 Brook Park Road
Cleveland, Ohio 44135

Director
Atomics International
Liquid Metal Engineering Center
P. O. Box 309
Canoga Park, California 91305

Manager-Advanced Development Activity
General Electric Company
Knolls Atomic Power Laboratory
P. O. Box 1072
Schenectady, New York 12301

General Manager
Westinghouse Electric Corporation
Bettis Atomic Power Laboratory
P. O. Box 79
West Mifflin, Pennsylvania 15122

Director, LMFBR Technology Program
Atomics International
P. O. Box 309
Canoga Park, California 91304

Associate Manager, Materials Engineering Dept.
Battelle Memorial Institute
Columbus, Ohio 43201

Director, Nuclear Development Center
The Babcock and Wilcox Company
Atomic Energy Division
Lynchburg, Virginia 24501

Manager, Plutonium Chemistry and Ceramics Fuels Development
Nuclear Materials and Equipment Corporation
Leechburg, Pennsylvania 15656

Manager, Sodium Reactor Technology
General Electric Company
Breeder Reactor Development Operation
310 DeGuigne Drive
Sunnyvale, California 94086

Manager, Nuclear Laboratories
Combustion Engineering, Inc.
Nuclear Division
Prospect Hill Road
Windsor, Connecticut 06095

Laboratory Assistant Director
Gulf Energy & Environmental Systems, Inc.
P. O. Box 608
San Diego, California 92112

Manager, Research
United Nuclear Corporation
Research and Engineering Center
Grasslands Road
Elmsford, New York 10523

Head, Fuels and Materials
Atomic Power Development Associates
1911 First Street
Detroit, Michigan 48226

K-2 Group Leader
Reactor Division
Los Alamos Scientific Laboratory
P. O. Box 1663
Los Alamos, New Mexico 87544

Irradiations Coordinator
EBR-II Project
Argonne National Laboratory
P. O. Box 1096
Idaho Falls, Idaho 83401

Director
Vallecitos Nuclear Center
General Electric Company
P. O. Box 846
Pleasanton, California 94566

Experiment Manager
EBR-II Project
Argonne National Laboratory
9700 South Cass Avenue
Argonne, Illinois 60430