MASTER

**Coal Technology Program
Progress Report for November 1975**

OAK RIDGE NATIONAL LABORATORY

OPERATED BY UNION CARBIDE CORPORATION • FOR THE U.S. ATOMIC ENERGY COMMISSION

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

Printed in the United States of America. Available from
National Technical Information Service
U.S. Department of Commerce
5285 Port Royal Road, Springfield, Virginia 22161
Price: Printed Copy \$5.00; Microfiche \$2.25

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the Energy Research and Development Administration, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

Contract No. W-7405-eng-26

COAL TECHNOLOGY PROGRAM
PROGRESS REPORT FOR NOVEMBER 1975

JANUARY 1976

NOTICE
This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Energy Research and Development Administration, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

NOTICE This document contains information of a preliminary nature and was prepared primarily for internal use at the Oak Ridge National Laboratory. It is subject to revision or correction and therefore does not represent a final report.

OAK RIDGE NATIONAL LABORATORY
Oak Ridge, Tennessee 37830
operated by
UNION CARBIDE CORPORATION
for the
ENERGY RESEARCH AND DEVELOPMENT ADMINISTRATION

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

PREVIOUS REPORTS IN THIS SERIES

ORNL-TM-5044, Progress Report for August 1974
 ORNL-TM-5045, Progress Report for September 1974
 ORNL-TM-5046, Progress Report for October 1974
 ORNL-TM-4787, Progress Report for November 1974
 ORNL-TM-4796, Progress Report for December 1974
 ORNL-TM-4850, Progress Report for January 1975
 ORNL-TM-4873, Progress Report for February 1975
 ORNL-TM-4892, Progress Report for March 1975
 ORNL-TM-4946, Progress Report for April 1975
 ORNL-TM-4966, Progress Report for May 1975
 ORNL-TM-5010, Progress Report for June 1975
 ORNL-TM-5037, Progress Report for July 1975
 ORNL-TM-5092, Progress Report for August 1975
 ORNL-TM-5124, Progress Report for September 1975
 ORNL-TM-5186, Progress Report for October 1975

CONTENTS

	<u>Page</u>
Abstract	1
1. Summary	1
2. Hydrocarbonization Research	3
2.1 Review and Evaluation	3
2.2 Experimental Development	3
2.3 Bench-Scale System	4
2.4 Residua Carbonization	6
3. Supporting Research and Development on Separations Technology	7
3.1 Batch Settling Studies	7
3.2 Continuous Settling Studies	8
3.3 Additive Agglomeration Studies	8
3.4 Bench-Scale Development	9
3.5 Characterization Studies	9
4. Chemical Research and Development	11
4.1 Physical Structure of Coal	11
4.2 Removal of Heteroatoms from Coal	11
5. Engineering Evaluations of Nuclear Process Heat for Coal Conversion	13
6. Engineering Evaluations of the Hydrocarbonization and Synthoil Processes	15
6.1 Synthoil Process	15
6.2 Hydrocarbonization Evaluation	18
7. COAL-FUELED MIUS	20

COAL TECHNOLOGY PROGRAM PROGRESS REPORT FOR NOVEMBER 1975

ABSTRACT

This report - the sixteenth of a series - is a compendium of monthly progress reports for the ORNL research and development projects that are in support of the increased utilization of coal as a source of clean energy. The projects reported this month include those for hydrocarbonization, solid-liquid separations, chemical research and development, engineering evaluations of nuclear process heat for coal conversion, engineering evaluations of the Hydrocarbonization and Synthoil processes

1. SUMMARY

J. P. Nichols

Highlights of our progress in November are summarized below:

° Two shakedown runs were completed in hydrocarbonization research. Five and twenty pounds of coal were pyrolyzed at $\sim 1050^{\circ}\text{F}$ under 5 atm nitrogen pressure. A third run is planned at 20 atm nitrogen pressure. Hopefully hydrogen will be introduced into the system in January. In the residua carbonization work design and operational data were reviewed and evaluated.

° In supporting research and development on separations technology, batch settling test results indicated that with 20% toluene, settling was faster at low temperatures than at high temperatures. Also, additives have been found which in parts-per-million concentrations give complete settling at very short residence times. A continuous laboratory-scale settling apparatus has been constructed to examine process operating parameters.

° Activities in chemical research and development continue with the use of transmission electron microscopy to examine the microporosity of coals. Design has begun of an experiment which will use gas chromatographic detection of hydrogen sulfide. The sensitivity of the thermal conductivity detector will need to be increased because hydrogen sulfide requires a sensitivity of at least 10 vol ppm which is beyond the present sensitivity of the chromatograph.

° Work is continuing in the engineering evaluations of nuclear process heat from coal conversion. Two new programs were transmitted and the materials evaluation effort reviewed. Design studies by United Engineers on two H-Coal plants and a steam gasifying plant are described.

° In the engineering evaluations work for Synthoil, design of the high-temperature shift section and analysis of unit reactor vessels were initiated. Data continue to be received and evaluated from various manufacturers on various sections of the process and are described. In the hydrocarbonization work flowsheet data have been firmed up and negotiations continue with a number of subcontractors for design and cost estimate information.

° In the MIUS program, a Request for Directive to proceed with procurement and construction activities of Phase III was prepared and submitted for approval. The AiResearch design study is well under way, and vibration tests of tubes within the fluidized-bed model and initial air-leakage tests of a flanged joint sealed with a ceramic gasket were completed. Installation of the coal feed and metering test equipment was completed and shakedown tests were initiated.

2. HYDROCARBONIZATION RESEARCH

H. D. Cochran, Jr.

Summary

During November the first two shakedown runs with the bench-scale system were completed successfully. In the first run, some 5 lb of pulverized coal was fed to the reactor and pyrolyzed at $\sim 1050^{\circ}\text{F}$ under 5 atm nitrogen pressure. In the second run, 20 lb of pulverized coal was fed and pyrolyzed at similar conditions. Although some shakedown difficulties were encountered in the first run, these were readily corrected and the second run had no problems. A third shakedown run at 20 atm nitrogen pressure is scheduled for early in the next month, and first operation with hydrogen is planned for the first week of January.

Some results are reported from the atmospheric pressure reactor which is undergoing modification for the Residua Carbonization project.

2.1 Review and Evaluation

(Completed)

2.2 Experimental Development

J. B. Gibson, P. R. Westmoreland, and J. C. Rose

Work Accomplished

Ambient Mock-Ups. Effort on this part of the project has been curtailed.

High-Temperature Studies. The material balance for Run AHC-6 failed to close; carbon recovery was only 83.9% of feed. Lack of closure is a result of tar and char losses in the line between the reactor and the cyclone.

Two experiments were initiated in November, attempting to repeat Run AHC-6. Run AHC-7 was aborted because of a plug between reactor and cyclone shortly after reactor heat up began (at about 250°F). Since definite layering of impervious solid was found and since the line had not been cleaned since Run AHC-6, the bulk of the plug was evidently residue from the previous run, sealed by carryover of fines. Run AHC-8 was completed successfully, and samples were submitted for chemical analysis.

Work Forecast

Ambient Mock-Ups. No effort is planned in this area during the next month.

High-Temperature Studies. Two runs are planned during the next month, in preparation for the Residua Carbonization project. The second of these runs will utilize the modified reactor containing an axial draft tube.

2.3 Bench-Scale System

Work Accomplished

Fabrication and Installation. The Bendix gas chromatograph was installed in the process exhaust line. The sample system was constructed to allow selection of either sample or calibration gas from the control room. Solenoid valves at both the sample inlet and instrument exhaust lines prevent over-pressure in the instrument during emergency purge. Valving for feed gas was completed. Two three-way valves in series first split the incoming gas between the preheater and pneumatic transport line and then provide a temperature trim by allowing a portion of cold gas to bypass the preheater. The line between the preheater and reactor was trace heated using three 2000-W resistance heaters. The connecting piping between the reactor and scrubber was heated with two 2000-W heaters to prevent liquid condensation. These two lines can be operated at 350 psi and 1250°F. A pressure equalization line was installed on the char overflow leg between the reactor and char receiver. It prevents overstressing the weld at the reactor due to the pressure reaction force at the expansion joint. A 2-in. ball valve was welded to the top of the feed hopper to facilitate filling with coal. Rupture disks and relief valves on each vessel were connected to a 2-in. header which extends 10 ft above the building roof. A coal flow monitor was fabricated and placed on the pneumatic transport line. Installation of the hydrogen supply station was resumed and will be completed in time for the first planned experiment with hydrogen.

Operation. The first two shakedown runs were completed successfully during November. For these runs 25 lb of nominal -50 +140 mesh coal was charged to the feed hopper. (Subsequent particle size analysis indicated a larger than expected percentage of -140 mesh fines in the feed charge.)

During the first run the system was brought to 5 atm pressure with nitrogen. The preheater and reactor were then brought to 1250°F and 1050°F, respectively, the system was leak checked, and coal feed at ~5 lb/hr was initiated. Difficulties with the orifice flow meter on feed gas precluded accurate flow measurement or control. Consequently, the run was terminated after only about 5 lb of coal had been fed to the reactor.

Several other problems were encountered during the first shakedown run. The most serious was that the coal feed rate appeared to be unstable (we had no direct measurement of coal feed rate other than feeder rpm for this first run). There also appeared to be significant fines carryover to the scrubber. Several minor difficulties with process instrumentation were detected and later corrected.

Prior to the second run, the orifice flow meter on the feed gas was inspected and repaired. In addition, a coal flow meter (based on the heat transport principle described earlier) was installed on the coal feed line.

For the second run, the system was again pressurized to 5 atm with nitrogen. The preheater and reactor were then brought up to 1250°F and 1050°F, respectively, the system was leak checked, and coal feed was initiated at about 10 lb/hr. The feed gas control was satisfactory, and the coal flow meter performed well. The remaining 20 lb of coal was transported to the reactor and ~8 lb of char overflowed to the char receiver.

During the second run there was some difficulty with plugging of the pressure taps used to measure differential pressure through the fluidized bed in the reactor. Other parts of the system performed well. No attempt was made to recover products for a material balance, but some qualitative observations were made. The char from the char receiver was free flowing, and the particle size distribution was similar to that of the feed coal. The liquid from the scrubber appeared to contain three phases - a lighter than water phase, an aqueous phase, and a heavy tar phase. The liquid was readily flushed from the scrubber. (The cold trap was not cooled, and only traces of tar were recovered from this vessel.) The filter on the effluent gas was slightly loaded with tar.

In summary, although the expected types of minor problems were encountered during the first two shakedown runs, the overall performance of the system was satisfactory. Significantly, no problems with gas leaks, with accommodating thermal expansion of vessels, or with any of major process components were encountered.

Work Forecast

Fabrication and Installation. Installation of the hydrogen supply station will be completed, and a few remaining details of installation of the bench-scale system will be finished.

Operation. A third shakedown run, at 20 atm nitrogen pressure, is planned for early in the next month. If warranted, a fourth shakedown run with nitrogen may also be completed. Product recovery and analysis for closure of the material balance will be the primary goal during the month. Plans call for the first experiment with hydrogen as feed gas during the first week of January.

2.4 Residua Carbonization

H. D. Cochran, Jr. and J. B. Gibson

Summary

This project for supporting research and development on residua carbonization is supported by the Division of Coal Conversion and Utilization of ERDA. The work in the year beginning November 1, 1975, consists of three tasks: (1) a review and evaluation of experience with the low-temperature carbonizer in the Cresap, West Virginia, pilot plant, (2) modification of an existing reactor to permit continuous feed of solids-laden residua, and (3) operation of the reactor with three feedstocks (vacuum distillation bottoms from the H-Coal process and solvent extraction underflows from SRC and CSF product liquids) at three temperatures up to 1200°F.

Work Accomplished

During the past month, work began on the residua carbonization project. Design and operational data from the Cresap (CSF) carbonizer were reviewed. Literature reviewed included the appropriate sections of the 116 monthly reports of the Cresap project and OCR R&D Reports Nos. 39, 45, 50, 62, and 70.

Modifications to the design of the bench-scale reactor to allow for the continuous residua feed and a recirculating fluidized bed were established. The reactor design can accommodate either a slurry feed or a feed stream of finely ground solids. The reactor is currently designed for batch operation with respect to char, but with little modification can be made continuous.

Substantial problems have been encountered in deciding the proper method of feeding residua to the reactor and in the design of the feed vessel. These problems result from the lack of information on the physical and chemical properties of the three feedstocks. The only feedstock for which physical properties are available is the H-Coal vacuum tower bottoms. Conversations with Norman Feinberg of Hydrocarbon Research, Inc. (HRI) and the result of ORNL laboratory experiments with H-Coal vacuum tower bottoms indicate that feeding finely ground solids may be the best feeding method. Obtaining a temperature high enough to ensure that the vacuum tower bottoms flow as a slurry would cause pyrolysis of the feedstock in the feed vessel. Since no properties have been available for the SRC and CSF feedstocks, it is not known if they can be fed as a solid.

Work Forecast

The first draft of the review and evaluation of the Cresap carbonizer should be completed in the next month. Modifications to the reactor and design of the feed vessel should be completed.

3. SUPPORTING RESEARCH AND DEVELOPMENT ON SEPARATIONS TECHNOLOGY

B. R. Rodgers

Summary

Results this month were obtained in five areas: batch settling tests, continuous settling tests, additive agglomeration, bench-scale development, and characterization analyses.

Batch settling tests surprisingly showed that when 20% toluene was present, settling was faster at low temperatures than at high temperatures. Low temperatures and pressures are desirable from a process design viewpoint.

A continuous settling apparatus at laboratory-scale was constructed to examine process operating parameters for a simulated full scale plant unit operation. Initial operation gave satisfactory results for short settling times.

Additives have been found which in parts-per-million range concentrations give complete settling at very short residence times. This represents a significant breakthrough in producing particle agglomeration in coal-derived liquids by modifying the solid surface characteristics.

The bench-scale apparatus for verification of solvent agglomeration/fractionation processes has been pressure tested, and initial results have been obtained for filtered oil from the Solvent Refined Coal Process.

Characterization analyses on new samples of SRC process oils derived from Pittsburgh No. 8 coal showed that the materials were similar to the Illinois No. 6 derived liquids used in previous tests, except for lower ash and sulfur concentrations. Electron microscope studies showed an increase in particle size and a change in particle shape upon heating an unfiltered oil.

3.1 Batch Settling Studies

P. R. Westmoreland, S. Katz, and B. R. Rodgers

Chemical analyses for ash and sulfur in a matrix of settling experiments (0-20% toluene, 150-250°C) indicate that optimal toluene fractionation occurred at 150°C with 20% toluene blended in Solvent Refined Coal Unfiltered Oil (SRC-UFO); this was the highest toluene concentration and the lowest temperature tested. Samples also were heated in a hood at 80°C for 16 hr to evaporate toluene, so that variations in toluene concentration after settling could be observed. Data scatter made

quantitative conclusions difficult, but when significant settling took place, toluene concentration decreased near the bottom of the settling tube.

Low temperatures, such as 150°C, would benefit a separations process by allowing lower pressures during settling; the pressure for the best separation obtained above was 30 psig. To obtain equivalent settling without toluene would require a pressure of 75 psig, two and one-half times that of the toluene/SRC-UFO mixture. Although low temperatures and pressures are desirable, any gains due to the use of solvent must be balanced by the costs of solvent recovery. Future experiments will further investigate concentration and temperature effects on fractionation with toluene and other solvents, and will study solvent recovery.

3.2 Continuous Settling Studies

S. Katz and B. R. Rodgers

The encouraging results from batch settling experiments prompted laboratory-scale studies to determine some parameters of a continuous flow system. A dynamic settling system has been constructed which will permit continuous feed and overhead removal at various feed rates and temperature conditions. The feed of unfiltered coal derived liquid is accomplished by using nitrogen pressure in excess of the vapor pressure over the unfiltered liquid as the driving force. The feed pot is a 500-cc closed stainless steel container fitted with a mechanical stirrer through a teflon gland. The settling chamber is a 2.54-cm-ID stainless steel tube 44 cm in length which is immersed in a silicone oil heating bath. The feed line enters the settling chamber at a point 9.6 cm from the top of the settler, giving a settler volume above the feed point of 41.8 cc. Flow rate of overhead "product" leaving the top of the settling chamber is controlled with a needle valve.

Preliminary runs made with SRC-UFO indicate that operation is satisfactory for short residence times, but long residence times will require an improvement in flow control.

3.3 Additive Agglomeration Studies

S. Katz and B. R. Rodgers

Screening studies have continued with the testing of 24 additives provided by the Tretolite Division of Petrolite Corporation. Additive concentrations were 4000 ppm in SRC-UFO derived from Pittsburgh No. 8 coal. As in previous additive studies, tests were conducted for 60-70 min at 280-290°C, which usually results in incomplete settling for unfiltered oil.

Since the surface characteristics and agglomerating tendencies of particles in coal-derived liquids is poorly understood, three broad classifications of additives were studied: anionic, nonionic, and cationic. Other materials tested include metal-organic salts, hydrocarbon copolymers, and crypto-anionic and crypto-cationic/nonionic additives. Ash analyses of the top fraction from each of the 24 tests were used to determine the degree of settling; they ranged from 0.02 to 2.5 wt %, i.e., from complete settling to no settling. Three additives gave nearly complete settling, three produced adequate settling, eight gave significant settling, and ten gave little or no settling. The best settling was given by two anionic types (0.02 and 0.03 wt % ash) and a hydrocarbon copolymer (0.09 wt % ash), followed by three nonionic types (0.18, 0.27, and 0.30 wt % ash). Further tests will examine the better additives at a concentration of 1000 ppm.

3.4 Bench-Scale Development

B. R. Rodgers, S. Katz, and D. A. McWhirter

The bench-scale apparatus described in ORNL-TM-4968 for solvent/agglomeration fractionation studies was debugged and in-situ pressure tested during this report period. Initial tests with SRC-filtered oil demonstrated operability. Tests with SRC-unfiltered oil are scheduled to begin next month.

3.5 Characterization Studies

B. R. Rodgers and D. A. McWhirter

Analyses of coal liquefaction process streams have engendered large quantities of data, but little attention has been given to the effect of sampling techniques and aging on the results. The effect of sampling will be ascertained by comparing "on site" analyses of SRC liquids by Catalytic, Inc. to those at ORNL after the samples have been confined and transported in drums or steel cans. The effect of aging will be determined by bimonthly analyses of samples from the SRC (Wilsonville) process streams before and after the filtration section. The effect of storing the samples in steel cans at room temperature, 30°F, and 140°F; and at room temperature with a N₂ blanket will be determined.

Other characterization studies underway include electron microscope particle size distributions, inorganic particle identification by scanning electron microscope, low-temperature ashing analyses, petrographic analyses, and gel permeation chromatography of unfiltered and filtered oils.

Aging Tests

Results of base line analyses for SRC-FO was presented in last month's report. These results were averaged and the standard deviation of each analysis determined. There was little change after two months at any of the previously mentioned storage conditions; the most significant changes were slight increases in the carbon/hydrogen ratios, viscosity, and acetone solids content.

The drum of SRC-UFO derived from Pittsburgh No. 8 coal was received from Wilsonville, and base line analyses were run. The material was similar to the unfiltered oil derived from Illinois No. 6 coal, but contained more saturated material; consequently, it was less dense and less viscous. The sulfur and ash contents were also significantly lower.

Electron Microscope Characterization of Solid Particles

A sample of SRC-UFO derived from Illinois No. 6 coal was examined by an electron microscope before and after heating for 1 hr at 300°C. The electron microscope at 24,000X and 48,000X magnifications showed that the unheated SRC-UFO sample consisted of a broad range of particle sizes, some with diameters as small as 0.01 μ . The particles with diameters near 0.8 μ appeared to be rough at the edges and may be made up of smaller particles. Small particle bridges between large particles were common in the unheated sample. In contrast, the heated sample contained particles which were highly agglomerated and there were few particles less than 1 μ in size. The surface edges of these particles appeared smooth, and there were no small particle bridges.

These results are consistent with previous results which indicated that restructuring of the particulates occurred with heating. The fact that these materials have undergone a similar heating experience in their conversion from coal in the pilot plant suggests that some conditions in the temperature and pressure let-down system caused the larger particles and agglomerates to break into smaller particles.

4. CHEMICAL RESEARCH AND DEVELOPMENT

G. P. Smith

The following report on the physical structure of coal is supported by the Fossil Energy branch of ERDA while the report on catalysts is supported by the Division of Physical Research of ERDA.

4.1 Physical Structure of Coal

L. A. Harris and C. S. Yust

The use of transmission electron microscopy to examine the microporosity of coals is continuing. Channel-like pores whose diameters range from 200 Å to 1 µm have been observed in spore exines. Fine granular material (micrinite) with particles as small as 50 Å is intimately associated with the spore exines.

In coal petrography we are attempting to establish the reliability of the Quantimet image analysis instrument in doing pyrite and inertinite volume, and size-frequency determinations. Data recently processed on a sample of Illinois No. 6 coal showed excellent agreement with chemical analyses.

4.2 Removal of Heteroatoms from Coal

R. A. Strehlow and P. A. Agron

Earlier work showed that a solid cobalt molybdate catalyst could be titrated with hydrogen sulfide at elevated temperatures to yield a sulfided form of the catalyst. The work also showed that hydrogen could then be used to titrate the sulfided catalyst and that the reduction of the catalyst strongly affected the catalytic activity. The essential finding was that a minimum in the activity of the catalyst for reduction of butene to butane occurred at a hydrogen sulfide content of about 90-100 vol ppm, the level of an endpoint in the titration by hydrogen.

Since simple techniques such as gas-phase titrations might be useful as measures of the concentration of catalytically active centers, we have begun design of an experiment which will use gas chromatographic detection of hydrogen sulfide and permit titration studies to be carried out with greater facility.

In the projected gas chromatographic studies, however, a sensitivity for hydrogen sulfide of at least 10 vol ppm is needed which was beyond the sensitivity of the chromatograph. We have, therefore, been modifying

the gas chromatograph in order to enhance the sensitivity of the thermal conductivity detector. A preamplifier with variable gain factor up to ten was installed by the Electronic Services Department. Tests indicate that the existing 4-ft-long Porapak T column alone or in series with a 10-ft-long Porapak Q column will be satisfactory for these equilibrium studies. Since simultaneous water analysis would be desired, a 3-ft-long Teflon column packed with Porapak Q was prepared and tested under a variety of conditions. Optimum conditions were determined, and it appeared that a sensitivity of about 10 vol ppm could be obtained. This would be a useful level if the resolution of the column for water and hydrogen sulfide were adequate. Some further trials will be conducted. We had planned on using a hydrogen sulfide-hydrogen mixture (2% H_2S) to sulfide the catalyst initially. The occurrence of a small leak in the gas cylinder safety relief occasioned the venting of the gas mixture. Thiophene will therefore be used as the source of sulfur. Design of the catalyst reactor is continuing. A quartz tube reactor and gas manifold assembly with a recycle capability (to assure equilibrium) is contemplated for this study.

In the pulse catalytic microreactor, the water saturator has been used for initial study of the equilibrium for hydrolysis of a partially reduced cobalt molybdate. No significant replacement of sulfur by oxygen was observed, but since equilibrium might not have been attained, the system is being adapted to permit variable recycle of the gas with the catalyst.

5. ENGINEERING EVALUATIONS OF NUCLEAR PROCESS HEAT FOR COAL CONVERSION

W. R. Gambill

Summary

Two new program proposals were transmitted and the materials evaluation effort reviewed. An ongoing design study by United Engineers on two H-Coal plants (all coal and VHTR driven) is described, as are preliminary design results for a plant steam gasifying coal directly with VHTR heat.

Two revised program and budget proposals, one covering the period January 1976 through September 1976 and the other the interval January 1976 through September 1977, were reviewed and formally transmitted.

The materials evaluation program for three processes (steam/carbon reaction, steam/ CH_4 reforming, and thermochemical H_2 production) was reviewed with Metals and Ceramics Division personnel.

We visited United Engineers and Constructors in Philadelphia on November 20 and discussed the status of their subcontract work on the preliminary design of two variations of an H-Coal plant producing crude liquids: an all-coal unit and a second unit utilizing the thermal and electrical energy delivered by a Very High Temperature Reactor (VHTR). The mixed-liquid output will be a heavy oil with a gravity less than 20° API and a total sulfur content of $\sim 3/4$ wt %. Design data have been taken from HRI reports, the independent Amoco review, the 1973 NPC evaluation, and the 1974-75 DCCU Annual Report.

The all-coal plant will produce $\sim 200,000$ BPD from a coal feed rate of 54,000 TPD. The coal feed will be the same for the VHTR-driven plant, but the net increase in liquids production has not been calculated.

There will probably be nine processing lines beyond the coal storage area. The coal selected is a hvbb coal with an HHV of 12,080 Btu/lb and containing 7.5 wt % water, 9.5 wt % ash, and 3.5 wt % sulfur. An air-blown fluid-bed coker is used to crack the residual oil (975°F) to a high HV, 4 wt % sulfur coke. The chemical reactors operate at 780°F, 2700 psig, and a space velocity of 28 lb coal/hr ft³. Williams stated the total H_2 consumption to be 0.052 ton H_2 /ton coal, which corresponds to 18,500 scf H_2 /ton coal. The reformer is fed with C_1 - C_6 gas and operates at an exit condition of $\sim 1400^\circ\text{F}$ and 350 psig. The utilities balance had not been closed, and values for overall energy-conversion efficiency were not available. By-products will be coke, liquid NH_3 , and sulfur.

The nuclear variant will include a 3000 MW(t) VHTR, an intermediate heat-exchange loop, and a reformer convectively heated by He. The corresponding core-exit He temperature will probably approach 1700°F.

The larger plant United Engineers/Constructors (UE/C) is evaluating will require more than the 384 MW(e) generated and used in-plant in the General Atomics/Stone & Webster (GA/S&W) reference design for coal to SPG. Following considerable discussion, we agreed that the VHTR plant would be based on power from the VHTR and the all-coal plant on power from a coal-fired power plant, using a 38% net efficiency in each case. Since this ground rule is somewhat arbitrary, it was agreed that the basis and consequences would be clearly stated in UE/C's report. Newman said their schedule calls for completion of the report by December 19, and that we should meet again in Philadelphia or Oak Ridge to review the draft on December 11.

A brief discussion was held with Wiggins and Frey concerning the other portion of this subcontract: to identify, quantify, and compare the pollution outputs and water usages of the GA/S&W, H-Coal, Hygas, K-T, and Lurgi processes. They are looking at SO_x, NO_x, NH₃, HCs, particulates, and trace elements. Emphasis had been placed on Lurgi and K-T because of the broader data base. They had located very little information on coal conversion plant solid-waste leaching rates.

In addition to the above, we asked UE/C to review and revise their report to ORNL of June 30, 1975 ("Engineering Evaluation of Process Heat Applications for Very High Temperature Nuclear Reactors") with regard to:

- (1) the process efficiencies, especially their relative values for syngas, H₂, and SPG products from a given process.
- (2) using a fixed gas delivery pressure of 1000 psig rather than the range of 100 to 1400 psig in the subject report.
- (3) the hydrogen purities, which in some flowsheets may be six or seven percentage points lower than those indicated.
- (4) responding to a GA letter (Oct. 28, 1975) stating that GA/S&W syngas is more suitable for methanol production than indicated by the June 1975 UE/C report (since CO₂ as well as CO can be used for methanol synthesis and because the syngas is available at 300 psi rather than 100 psi).

Newman agreed to issue a revised report, addressing these points and including revised economics, on January 15, 1976.

The UE/C work seems to include sufficient detail to evaluate more realistically the relative promise of the crude liquids VHTR case identified in their June 1975 overview report.

After assembling available data on steam gasification rates (percent carbon per minute) vs temperature for various coal types, a preliminary flowsheet was prepared for a VHTR-driven direct steam-coal gasifier. With a 3000-MW(t) VHTR (1800°F core-exit He temperature), 7163 TPD of coal would be converted to 6120 TPD of clean syngas (79.3 mol % H₂ and 20.7 mol % CO). The fluid-bed temperature is 1472°F, and the preliminary energy conversion efficiency 78%. Of the 3000 thermal MW, 1200 MW(t) would be available outside the gasifier, producing, e.g., 456 MW(e) for a 38% net power generation efficiency.

6. ENGINEERING EVALUATIONS OF THE HYDROCARBONIZATION AND SYNTHOIL PROCESSES

J. M. Holmes, R. Salmon, and E. G. St. Clair

Summary

Synthoil. Computer programs were written for calculating the overall block flow material balance and the heat and material balances for the high-temperature CO shift unit. Design of the high-temperature shift section was initiated. An analysis of the design, fabrication, and operation of the Synthoil unit reactor vessels was initiated. The completed analysis will treat hot-wall vessels and refractory-lined vessels with regard to materials of construction, code requirements, fabrication techniques, vendor capabilities, and costs. Capital, utility, and chemical make-up costs for the potassium carbonate scrubbing units were received from the Benfield Corporation. The Pennwalt Corporation provided all available data on the testing of Synthoil liquids in Sharples centrifuges at about 200°F. The Johns-Manville Company supplied a conceptual design of a rotary drum precoat filter specifically designed for coal-derived liquids.

Hydrocarbonization. Flowsheet data have been firmed up based upon estimated yields from U.S. Steel's "Clean Coke" process. Preliminary process flowsheets and material balances were prepared by McNally-Pittsburg Corporation for the coal yard and coal beneficiation plant. Linde Division of Union Carbide Corporation agreed to prepare a design and cost estimate for a cryogenic system to separate the hydrocarbonizer make gases into a pipeline gas and a hydrogen stream. Subcontract negotiations were initiated with Fluid Bed Combustion Company for the design and cost estimate of an atmospheric fluid bed combustor. Hydrocarbon Research, Incorporated, agreed to provide the design and cost estimate for an H-oil hydrotreater for the tars and liquids produced by the hydrocarbonizers.

6.1 Synthoil Process

R. Salmon, M. S. Edwards, D. E. Reagan, E. G. St. Clair, and W. C. Ulrich

A computer program was completed for calculating the overall block flow material balance and the material balance calculated by this program was incorporated into the overall flow diagram.

The R. M. Parsons Company was contacted regarding the sulfur plant, and they expect to have the design and costs to us in about three weeks.

Compressor and driver selections and costs were received from the Elliott Company. Similar selections are expected from Dresser-Clark in about two weeks.

A Fortran program was written for the heat and material balance calculations of the high-temperature CO shift unit. The flow diagram is being completed using the tabulated material balance from this program. The results agree well with those of the Girdler program. It was necessary to write our own program because the Girdler program provides only the information around the reactor and does not include a material or a heat balance.

A Lawrence Livermore Laboratory computer program for multicomponent fractionation was tested and ran successfully. It was then used to check the Synthoil recycle gas methane absorber. The results agreed well with those of our own calculations.

The PDA (Process Design Analysis) computer code of McDonnell-Douglas Automation Company was used to determine coefficients of a cubic equation for the effect of temperature on the enthalpy of a number of compounds and petroleum fractions at four pressures (2, 800, 1600, and 2499 psia) for use in heat balance calculations. The coefficients were determined for the compounds and petroleum fractions for both the gaseous and liquid states (i.e., there are eight coefficients for each compound or petroleum fraction).

A subroutine was written to calculate the enthalpy of a given compound at a specific temperature and pressure for use in heat duty calculations. The subroutine calculates the enthalpy at the temperature for all four pressures and then uses the Lagrangian interpolation method to determine the enthalpy at the desired pressure.

The various sections of the Synthoil flowsheet have progressed as follows:

(1) Synthoil Reactor Vessel: As presently conceived, the Synthoil unit will require 36 reactor vessels, each with an 8 ft, 4 in. internal diameter and a 14 ft, 6 in. catalyst bed depth. Process conditions dictate that the reactor vessel be designed to operate at approximately 4250 psig and 860°F and to resist attack by high partial pressures of hydrogen and the corrosive effects of hydrogen sulfide. An analysis of the design, fabrication, and operation of the reactor vessels is currently underway. The completed analysis will treat hot-wall vessels and refractory-lined vessels (both with alloy liners) with regard to materials of construction, code requirements, fabrication techniques, vendor capabilities, and costs. The intent of the brief analysis is not to provide a detailed design, but rather to survey the problems involved, develop an acceptable solution, and provide a cost estimate for use in determining the overall Synthoil unit capital investment and layout.

(2) Gasification: A computer program was developed for calculating the raw gas production and composition for various combinations of coal and char feed rates to the gasifier. Work continued on sizing equipment (heat exchangers, pumps, etc.) for the gasification section.

(3) Carbonization: A computer program was developed for calculating material and energy balances for the low-temperature carbonizer section. Work continued on sizing equipment (heat exchangers, pumps, etc.) for this section.

(4) Acid Gas Removal: The Benfield Corporation provided capital, utility, and chemical make-up costs for the Synthoil facility K_2CO_3 scrubbing units, and similar estimates for the Hydrocarbonization facility are expected soon. Flowsheets and equipment sizing were not provided because of the nonproprietary nature of our agreement, but could be made available under a contract which includes a secrecy agreement.

Several manufacturers of towers and tower internals were contacted with regard to the design of a DEA regenerator. The Glitsch Company sent details for the design of such towers. This, when combined with the technique for tray design in multipass towers of William L. Bolles of the Monsanto Chemical Company, should provide a firm basis for design. A letter was sent to Koch Engineering Company detailing the tower specifications, and they have agreed to design a tray or packed tower, whichever is more suitable.

When the design procedure for the DEA regenerator internals is complete, the DEA computer model can be reassembled. It will then be used for design of DEA plants in both the Synthoil and Hydrocarbonization facilities.

(5) CO Shift Conversion: Design of the CO shift sections of both the Hydrocarbonization and Synthoil facilities is well underway based on data supplied by the Girdler Company and the use of the Girdler catalysts. The BASF representative in Washington, D.C., Jack Dart Associates, stated that they completed the evaluation relating to BASF shift catalysts in our system and mailed it to us. Any new information provided will be incorporated into our present designs.

Design of the high-temperature shift section of Synthoil facility was recently initiated. Because the pressure drop through the reactors is excessive when only one or two trains are used (about 200 psi or more across the high-temperature shift plant), a design using four parallel trains was proposed. The pressure drop through this system appears to be less than 30 psi overall. In all cases, three reactors in series with inter-reactor cooling to permit maximum CO conversion are provided.

(6) Solid-Liquid Separation: Two centrifuge vendors were contacted to establish a firm base for the evaluation of centrifugation. The Bird Machine Company was unable to help us with data but may be able to provide information at a later date based on a reevaluation of the operation of the Bird centrifuge at Cresap, West Virginia.

The Pennwalt Corporation (Sharples-Stokes Division) provided ORNL with all available data on the testing of Synthoil liquids in Sharples centrifuges. However, all the data are at temperatures of about 200°F, and at the conditions expected to be required (about 600°F), no data are available.

The Johns-Manville Company provided us with the conceptual design of a rotary drum precoat filter specifically designed for coal-derived liquids. This design was prepared under a contract with EPRI. Stearns-Roger provided the expertise in equipment design for the report. Although the filter design was not for the size expected to be needed in a commercial facility, it does give many of the filtration parameters required for such a design.

The Envirotech Corporation (Goslin Division) was visited to acquire background on their experience in the area of coal liquids separation problems. Information on the design, modifications, and operations of Goslin-Birmingham filters in the coal liquids area was obtained, and is currently being evaluated.

6.2 Hydrocarbonization Evaluation

J. M. Holmes, D. S. Joy, G. R. Peterson, M. S. Edwards,
C. B. Smith, D. A. Dyslin, and J. R. Johnson

Flowsheet data have been firmed up based upon estimated yields from U.S. Steel's "Clean Coke" process. Material balance information derived from the PDU experiments will be used for the first stage yields but estimates will be employed for the yields from the second stage carbonizer. These estimates will be based upon the reported volatile matter content of the feed and product char, and the rates of gas production, since the tar yields are not available. Overall estimated yields of coal liquids for the two stages are in the range of 15 to 16% of the moisture and ash free coal feed.

The various sections of the hydrocarbonization flowsheet progressed as follows:

(1) Coal Beneficiation: Preliminary process flowsheets and material balances were prepared by McNally-Pittsburg Corporation for the Hydrocarbonization Facility coal yard and coal beneficiation plant. The coal yard includes coal unloading facilities, crushers for reducing the ROM coal to 2 in. x 0, and three parallel coal storage piles, each with stacker-reclaimers. The coal cleaning plant consists of three parallel lines, each having a capacity of 850 TPH. Generally, the beneficiation process involves primary and secondary heavy-media separation of the coarse coal (2 in. x 28 mesh) and froth flotation of the fine coal (minus 28 mesh).

Initial design showed the primary and secondary heavy media separations operating at low specific gravities (1.325 and 1.50 respectively), and the refuse stream contained about 6% maf coal which is considerably higher than expected. McNally-Pittsburg agreed to increase the operating specific gravities to 1.40 and 1.85 which will lower the refuse stream to about 1-2% maf coal containing 67.4% ash and 9.35% sulfur.

The final moisture contents of the high-grade coal and low-grade coal streams after beneficiation are 19.9 and 24.7%, respectively. These high moisture contents present handling problems in the storage silos and the Petrocarb coal injection system. Predrying of the coal to 2% surface moisture will be needed to eliminate the problem.

(2) Hydrocarbonization: Recent data from U.S. Steel confirmed our earlier suspicion that a significant amount of the light hydrocarbons in the recycle gas stream will be coked in the fluid bed combustion unit. The original flowsheet heated a recycle gas stream to 1750°F to provide sufficient heat for the second stage hydrocarbonizer. The recycle gas stream will contain a significant amount of light hydrocarbons (C_1 through C_4). From the U.S. Steel data it is apparent that the recycle gas stream cannot be heated beyond 1450°F. A quantity of steam must also be added to the recycle gas stream to react with any coke formed.

The material balance computer program is being revised to reflect the composition change in the recycle gas stream upon heating. A char burner is also being included to supply the additional heat required by the second stage by recycling hot char and ash. A rough calculation shows that approximately 1.5% of the char product will be burned.

(3) Cryogenic Separation System: Linde Division of Union Carbide Corporation agreed to prepare a design and cost estimate for the cryogenic system to separate the hydrocarbonizer make gases into a pipeline gas product and a hydrogen stream suitable for use in hydrotreating. Preparation of this estimate is currently underway.

(4) Fluid Bed Combustor: Subcontract negotiations were initiated with Fluid Bed Combustion Company for the design and cost estimate of an atmospheric fluid bed combustor. This system was revised to provide heated gas for drying the coal feed to the hydrocarbonizers in addition to the recycle gas heating and high pressure steam requirements.

(5) Tar Hydrotreater: Hydrocarbon Research, Inc., agreed to provide the design and cost information for an H-oil hydrotreater for the tars and liquids produced by the hydrocarbonizers. An advantage of the H-oil system is its capability for hydrotreating liquids containing significant concentrations of solids since it utilizes an ebullating bed type reactor. Therefore, solids-liquid separation can be performed on the hydrotreated liquids which will be far less viscous and easier to filter than the tars prior to hydrotreating.

7. COAL-FUELED MIUS

A. P. Fraas and W. R. Nixon

This project for analysis, design, and demonstration of a concept utilizing a fluidized-bed coal combustion system as a heat source for a gas turbine generator suitable for applications in Modular Integrated Utility Systems (MIUS) is carried out under the ORNL-HUD-MIUS Program within the Energy Division. Work is supported by the U.S. Department of Housing and Urban Development under HUD Interagency Agreement No. 1AA-H-40-72 and by the Energy Research and Development Administration, Office of Fossil Energy, under OCR contract No. 14-32-0001-1742. The project consists of four phases: I - Conceptual Preliminary Evaluation; II - Conceptual Design; III - Detailed Design and Construction; and IV - Shakedown, Performance, and Endurance Tests.

Summary

A Request for Directive to proceed with procurement and construction activities of Phase III was prepared and submitted for approval. The AiResearch design study is well under way, and vibration tests of tubes within the fluidized-bed model and initial air-leakage tests of a flanged joint sealed with a ceramic gasket were completed. Installation of the coal feed and metering test equipment was completed and shakedown tests were initiated.

Detailed Design and Construction Phase

A Request for Directive to proceed with procurement and construction of the coal-fueled MIUS test unit was prepared by General Engineering and forwarded through channels to ERDA/ORO for approval. Procurement of long lead-time components and materials, to include the Incoloy 800 tubing, will be initiated on receipt of authorization from ORO.

Layout Studies

A revised furnace design was completed which reduces the number of flanged joints and the requirements for small dimensional tolerances. Review by three steel fabricators resulted in suggestions for additional modifications.

Turbine-Generator Unit

Work at AiResearch on their design study contract is well under way. They have prepared new models for the analysis of the stability and control of the system and are supplying detailed performance characteristics

of both the compressor-turbine-generator unit and the recuperator so that the ORNL computer program can be refined. AiResearch has also advocated making more use of the compressor bypass valve as opposed to feed and bleed control of system pressure. This would be applicable to both open and closed-cycle operation. They also recommend that the large vent valve be available for emergencies and plan to use a pneumatic starter motor which can drive the unit up to 30% speed for long periods.

Coal Flow Tests of a Fluidized Bed

Preliminary data on tube vibration indicate that the frequencies vary from 8 to 16 cycles per second depending on the air flow rate through the bed. In no case were large amplitudes of vibratory motion measured.

The 4-ft square cold flow test unit is being instrumented for investigations of the rate at which coal particles will be dispersed in the bed. Tests are scheduled to resume early in December 1975.

Test of Furnace Gasket Material

The initial test of a flanged joint employing a ceramic gasket material has been completed. The unit was operated for 250 hr through 20 full thermal cycles. No increase in the leakage rate was detected throughout the course of the test. A new test will be conducted to determine the effect of clamp pressure on leakage rate using thicker gasket material.

Coal Metering and Feed System

Installation has been completed of the Iron Fireman and the vibratory coal metering unit together with the necessary lines, cyclone separators, and other equipment for recirculating the material. Initial shakedown tests were started the last week in November. Some difficulty was encountered with the Iron Fireman motor because of the much higher blower load when handling room temperature air than when handling the 400°F (200°C) stack gas for which the unit was designed. A larger motor will be installed next month.

THIS PAGE
WAS INTENTIONALLY
LEFT BLANK

INTERNAL DISTRIBUTION

ORNL-TM-5214

1. R. G. Affel
2. T. D. Anderson
3. S. I. Auerbach
4. J. K. Baird
5. R. E. Barker
6. H. C. Beeson
7. M. Bender
8. B. G. Blaylock
9. N. E. Bolton
10. R. E. Brooksbank
11. W. A. Bush
12. D. A. Canonico
13. R. S. Carlsmith
14. J. A. Carter
15. H. D. Cochran, Jr.
16. E. Copenhaver
17. L. T. Corbin
18. D. A. Creasia
19. W. K. Crowley
20. O. L. Culberson
21. F. L. Culler
22. J. E. Cunningham
23. V. A. DeCarlo
24. D. G. Doherty
25. A. S. Dworkin
26. M. S. Edwards
27. F. J. Endelman
28. G. G. Fee
29. D. E. Ferguson
30. L. M. Ferris
31. R. C. Forrester III
32. A. P. Fraas
33. W. Fulkerson
34. W. R. Gambill
35. D. A. Gardiner
36. C. W. Gehrs
37. J. B. Gibson
38. M. R. Guerin
39. C. W. Hancher
40. L. A. Harris
41. S. E. Herbes
42. R. M. Hill
43. R. S. Holcomb
44. J. M. Holmes
45. R. B. Honea
46. J. K. Huffstetler
47. C. L. Hunt
48. F. J. Hurst
49. G. R. Jasny, Y-12
50. W. F. Johnson
51. L. L. Johnston
52. R. L. Jolley
53. J. E. Jones
54. D. S. Joy
55. S. Katz
56. O. L. Keller
57. R. F. Kimball
58. J. J. Kurtz
59. W. R. Laing
60. P. M. Lantz
61. R. S. Livingston
62. A. P. Malinauskas
63. G. B. Marrow, Y-12
64. W. R. Martin
65. W. J. McDowell
66. J. R. McWherter
67. C. J. McHargue
68. J. W. Michel
- 69-71. W. R. Mixon
72. J. E. Mrochek
73. G. E. Moore
74. P. Nettesheim
- 75-84. J. P. Nichols
85. L. C. Oakes
86. G. R. Peterson
- 87-88. T. W. Pickel
89. W. W. Pitt
90. H. Postma
91. J. J. Prisliger
92. W. T. Rainey
93. D. E. Reichle
94. C. R. Richmond
95. B. R. Rodgers
- 96-97. M. W. Rosenthal
98. W. L. Russell
99. Royes Salmon
100. R. W. Schede, Y-12
101. C. D. Scott
102. A. J. Shor
103. D. S. Shriner
104. W. D. Shults
105. C. B. Smith
106. G. P. Smith
107. I. Spiewak
108. R. L. Spore
109. E. G. St. Clair
110. J. B. Storer
111. R. A. Strehlow
112. O. K. Tallent
113. E. H. Taylor

114. A. J. Thompson	124. L. V. Wilson
115. D. B. Trauger	125. R. G. Wymer
116. W. C. Ulrich	126. G. L. Yoder
117. P. R. Vanstrum, Y-12	127. C. S. Yust
118. J. S. Watson	128. Patent Office
119. J. R. Weir	129. Lab. Records-RC
120. P. R. Westmoreland	130-134. Lab. Records
121. M. E. Whatley	135-137. Central Research Library
122. J. C. White	138. Document Reference Sect.
123. M. K. Wilkinson	

EXTERNAL DISTRIBUTION

ERDA, Oak Ridge Operations

139. Research and Technical Support Division

ERDA, Washington

140. D. Ballantine	154. G. A. Mills, FE
141. J. D. Batchelor, FE (Fossil Energy)	155. W. E. Mott, DBER
142. T. Beresovski, DRRD	156. M. B. Neuworth, FE
143. E. L. Clark, FE	157. E. S. Pierce, DPR
144. N. P. Cochran, FE	158. H. E. Podall, FE
145. C. W. Edington, DBER	159. J. L. Powell
146. R. Franklin, DBER	160. Robert Rabin, DBER
147. S. W. Gouse, FE	161. E. Schmetz, FE
148. W. S. Harmon, FE	162. G. Stapleton, DBER
149. G. E. Larson, FE	163. R. E. Vener, FE
150. T. K. Lau, FE	164. H. Wasson, DBER
151. R. W. A. LeGassie, AA/PA	165. P. C. White, AA/FE
152. J. L. Liverman, AA/ES	166. R. L. Zahradnik, FE
153. C. Miller, FE	

Department of Housing and Urban Development, 451 7th Street, S.W.,
Washington, D.C. 20410167. G. S. Leighton
168. J. H. Rothenberg

National Science Foundation, 1800 G Street, N.W., Washington, D.C. 20550

169. R. S. Goor
170. Charles Johnson

Resource Planning Associates, Inc., 44 Brattle St., Cambridge, Mass. 02138

171. Robert Rea

U.S. Environmental Protection Agency, ETRL, 1055 Laidlaw,
Cincinnati, Ohio 45237

172. William E. Pepelko

U.S. Environmental Protection Agency, Research Triangle Park, N.C. 27711

173. Charles B. Sedman

U.S. Steel Corp. Applied Research Laboratory, 125 Jamison Lane,
Monroeville, Pa. 15146

174. N. S. Boodman, Section Supervisor

University of Kentucky, Institute for Mining and Minerals Research,
213 Bradley Hall, Lexington, Kentucky 40506

175. Theresa Wiley, Institute Librarian

176. O. J. Haun

177. J. K. Shou

178. The Director, Morgantown Energy Research Center, P.O. Box 800,
Morgantown, West Virginia 26506

179. The Director, Pittsburgh Energy Research Center, U.S. Bureau
of Mines, 4800 Forbes Ave., Pittsburgh, Pa. 15213

180. Tom K. Brotherton, Vice President, Coalcon Company, Union Carbide
Corp., P.O. Box 8361, South Charleston, West Virginia 25303

181. D. E. Eissenberg, Union Carbide Corp. 270 Park Ave.,
New York, N.Y. 10017

182. R. E. Davis, Kerr-McGee Technical Center, P.O. Box 25861,
Oklahoma City, Oklahoma 73125

183. H. Beuther, Gulf Research and Development Company, P.O. Drawer
2038, Pittsburgh, Pennsylvania 15230

184. Robert Hangebrauck, National Environmental Research Center,
Research Triangle Park, North Carolina 27711

185. P. H. Given, Pennsylvania State University, College of Earth
and Mineral Sciences, University Park, Pennsylvania 16802

186. John W. Larson, Department of Chemistry, University of Tennessee,
Knoxville, Tenn. 37916

187. Wendall H. Wiser, University of Utah, Department of Mineral
Engineering, Salt Lake City, Utah 84112

188. William A. Peters, Massachusetts Institute of Technology,
Department of Chemical Engineering, Cambridge, Mass. 02139

189. Donald Hanson, University of California, Department of Chemical
Engineering, Berkeley, California 94720

190. S. G. Wellborn, Manager, Feedstocks Development, E. I. du Pont
de Nemours & Company, Inc., Wilmington, Delaware 19898

191. Tetra Tech, Inc., 1911 N. Ft. Myer Drive, Suite 601, Arlington,
Virginia 22209, Attention: Walter McGough, Jr.

192-193. Jack Gillespie, UCCND, P.O. Box 1410, Paducah, Ky. 42001

194-220. Technical Information Center, ERDA, ORO