Antelope - Fossil Rebuild Project

Environmental Assessment

DOE/EA-0701

Bonneville
POWER ADMINISTRATION

MASTER

April 1992

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

COLUMBIA POWER COOPERATIVE ASSOCIATION
ANTELOPE-FOSSIL REBUILD PROJECT
ENVIRONMENTAL ASSESSMENT

1.0 Project Description

The Columbia Power Cooperative Association (CPCA), Monument, Oregon, proposes to upgrade a 69-kV transmission line in Wasco and Wheeler Counties, Oregon, between the Antelope Substation and the Bonneville Power Administration's (BPA) Fossil Substation (Figure 1). The project involves rebuilding and reconductoring 23.2 miles of transmission line, including modifying it for future use at 115 kV. Related project activities will include setting new wood pole structures, removing and disposing of old structures, conductors, and insulators, and stringing new conductor, all within the existing right-of-way. No new access roads will be required.

A Borrower's Environmental Report was prepared for the 1992-1993 Work Plan for Columbia Power Cooperative Association in March 1991. This report investigated cultural resources, threatened or endangered species, wetlands and floodplains, and other environmental issues, and included correspondence with appropriate Federal, state and local agencies. The report was submitted to the Rural Electrification Administration for their use in preparing their environmental documentation for the project.

BPA prepared an environmental report for adjacent sections of the line which were rebuilt in 1987, and determined that the rebuilding of these portions could be categorically excluded. The BPA report did not directly address the 23.2-mile section of line currently proposed for rebuilding. However, terrain and topographic features are very similar throughout the project vicinity. Therefore, the discussion of environmental impacts presented in the BPA report is applicable to the proposed project.

2.0 Purpose of and Need for Action

The purposes of the project are to increase the reliability of the existing transmission line and to decrease maintenance costs. The line is in need of replacement after approximately 42 years of service and is in a generally deteriorated condition, particularly with respect to the conductor. Weathering of poles, crossarms, hardware, and components other than the conductor also represent the need to replace the line.

Portions of the transmission line are located in areas where the wind and ice loads have historically caused major operating and maintenance problems during adverse weather conditions. The CPCA crew does not have the capability to continually remove ice from conductors during inclement weather conditions, a condition which increases the possibility of power outages. During extreme frost and ice conditions, conductor clearances above ground can fall below minimum values allowed by the National Electric Safety Code, resulting in a situation of non-compliance with safety codes as well as incurring the risk of liability for possible damages.

1 INCH = 4.8 MILES

Antelope - Fossil Line
Columbia Power Cooperative Association

The need for the upgrade of the line from 69 to 115 kV is a matter of economic prudence. The relatively small incremental cost of modifying the line for future use at 115 kV during the rebuild justifies this action.

3.0 Alternatives

The no-action alternative would involve retaining the present 69-kV system with the structures and conductor in their current condition. This would not meet the purpose of the project. The condition of the line would continue to deteriorate, increasing the costs of maintenance and jeopardizing the reliability of the service to the customers. The remote location of the line precludes providing service to the customers through alternative transmission lines. Safety hazards and code violations would also continue to be a liability during winter weather. For these reasons, the no-action alternative was not pursued further.

A possible project alternative would be to rebuild the line for continued operation at 69 kV instead of the proposed rebuilding for future use at 115 kV. This action could result in an estimated 10 to 15 percent cost savings at present. However, the voltage upgrade would permit increased operating capacity and future service capability without further line modification and is economically superior, over the life of the project, to the transmission line repair and replacement alternatives.

No alternative routing has been identified for this project. The existing routing appears to be the most feasible and accessible from both a site acquisition and a construction and maintenance standpoint. Following the present route avoids the possible impacts of increased erosion and disruption of habitat which could result from equipment moving and operation in less accessible locations.

4.0 Environmental Impacts

Correspondence included in the Borrower's Environmental Report with the appropriate state and Federal agencies regarding cultural resources, threatened or endangered species, floodplains, wetlands, fish and wildlife, and prime farmlands, reflects an absence of concerns for this project by these agencies.

The present 69-kV transmission line to be upgraded parallels State Highway 218 near Grub Hollow Creek to the east of the town of Antelope, crosses the John Day River south of Clarno, passes to the south of the John Day Fossil Beds, and then extends generally northeast toward the town of Fossil. The project route is predominantly undeveloped with relatively few areas containing homesites or developed lands. Predominant land use consists of cattle grazing with interspersed farms. A few scattered agricultural areas under cultivation are situated along the John Day River floodplain.

The project would directly impact the transmission line corridor during the brief duration of the construction and restringing of the new conductor. As represented in the Borrower's Environmental Report, overall impacts would

be minimal. None of the improvements associated with this project would impact areas outside of substations or other facilities along the route, other than for possible temporary staging of equipment or materials in an area to be designated at a later date. Staging areas and other areas along the transmission route where vegetation is significantly disrupted during construction will be reseeded with an appropriate seed mix to help restore native vegetation and stabilize soils.

Rebuilding the existing powerline will not result in any agricultural land being taken out of production or cultivation. New structures will be placed in either the same location as present transmission poles, or (in several instances) on higher ground to avoid potential environmentally sensitive sites.

A National Monument, the John Day Fossil Beds is located near a portion of the proposed transmission line upgrade (see Figure 1). Camp Hancock, a developed group campsite, and a small picnic area are located within the southernmost portion of the monument boundaries. The transmission line passes this site on the opposite side of the highway and thus would not interfere with these designated areas.

The portion of the John Day River crossed by the transmission line is a state-designated scenic waterway and a Federally-designated recreational river under the Wild and Scenic Rivers Act. However, the existing line now crosses the river and the new line will not change in appearance from the viewpoint along the river. The project would not adversely affect the characteristics, values, or eligibility of the river as a recreation resource. The Oregon Department of Parks and Recreation has reviewed the project and expressed no concerns. No other natural areas, parks, designated landmarks, recreation areas, or designated land uses are located in the project vicinity.

Construction of the proposed project would not impair nor interfere with water resources or watershed characteristics in the area. The existing line crosses a floodplain shown on National Flood Insurance Program maps along the John Day River near Clarno on the Wasco County-Wheeler County line. Several of the existing structures are located within the designated 100-year floodplain at the point of crossing and along Pine Creek and Cove Creek tributaries. Crossing the floodplain is unavoidable because the two substations involved are on opposite sides of the floodplain. The new structures to be placed in the floodplain would be designed to withstand flooding, so there would be little or no hazard to the transmission line from flooding. Construction activities associated with the transmission line would not alter floodplain characteristics or create the potential for greater loss of property or life during flooding. For these reasons, the proposed project minimizes potential harm within the floodplain and would not significantly impact the floodplain.

Much of the area consists of uneven terrain along the base of steeper hillsides and is predominantly well-drained with respect to runoff. Intermittent drainages are present along fields, and seasonally provide channels for runoff. However, during wet seasons some areas of standing water

are evident in meadows and along the highway. The existing line traverses two areas of seasonally flooded wetlands that are represented on the U.S. Dept. of Fish and Wildlife National Wetlands Inventory maps. Field inspection revealed that these two sites are of possible concern, but placement of structures will avoid interference to these seasonally wet areas. It is feasible in each case to locate structures away from low-lying drainages or fields where runoff patterns have resulted in these small seasonal wetlands.

The viewshed is characterized by semi-arid fields, open terrain and ravines, dissected hills, and range habitat along the route. The powerline is visible in the background along Highway 218 from the roadside in many locations. However, the rebuilding of the existing transmission line would not result in increased visual impacts to the observer beyond those presently encountered.

An intensive cultural resource survey was conducted in the project area in 1987 by Eastern Washington University for the previous rebuild work. This survey did not locate any cultural resources considered to be eligible for the National Register of Historic Places. The State Historic Preservation Office reviewed the Borrower's Environmental Report and concluded that the proposed action would have no effect on sites on, or eligible for inclusion in, the National Register.

No burning or other air discharges would occur in relation to the proposed action, and no significant or long-term impacts to regional air quality would occur. Impacts on air quality would be limited to construction activities which will generate limited amounts of fugitive dust and exhaust emissions from equipment and vehicles, primarily along the transmission line route. Very little solid waste will be generated by the project due to extensive recycling and salvage of old conductor, hardware components, and other materials. No hazardous waste materials nor toxic substances will be introduced into the project area due to proposed construction.

5.0 Conclusion

The rebuild of the existing transmission line involving new poles, crossarms, hardware, conductor, and other related components will result in minimal impacts to the environment. The proposed routing of the rebuild will closely parallel the present line and result in few impacts to property and natural conditions. No viable alternatives have been identified other than following the existing route between Antelope and Fossil Substations. Wetlands will be avoided by careful structure placement.

6.0 Agencies and Persons Consulted

BPA and CPCA have consulted with the persons and agencies listed below regarding issues relevant to the Antelope-Fossil Rebuild Project.

Rex D. Brown Consulting Engineer, Inc.

Federal Emergency Management Agency

U.S. Fish and Wildlife Service

Oregon Department of Fish and Wildlife

Oregon State Historic Preservation, Parks and Recreation Division

Oregon State Parks and Recreation Department

Soil Conservation Service

U.S. Department of the Army, Portland District Corps of Engineers

7.0 References

Borrower's Environmental Report for 1992 - 1993 Work Plan for Columbia Power Cooperative Association, Monument, Oregon, March 1991.

U.S. Dept. of the Interior Fish and Wildlife Service, National Wetlands Inventory Maps.

U.S. Department of Housing and Urban Development, Flood Hazard Boundary Maps for Wasco and Wheeler Counties, Oregon.

4255c

**DATE
FILMED
8/10/92**