**Volume 5
Field Investigation Report**

JUN 24 1992

March 1991
(Reissued March 1992)

Prepared for
Wright-Patterson Air Force Base
2750 Air Base Wing
Office of Environmental Management

Prepared by
IT Corporation
Cincinnati, Ohio

for Environmental Management Operations
under a Related Services Agreement
with the U.S. Department of Energy

Engineering drawings for this project
are identified as CAPE- 3032
Inquiries may be directed to:

Office of Scientific and
Technical Information
P. O. Box 62
Oak Ridge, TN 37831

Environmental Management Operations
Richland, Washington 99352

MASTER

ABSTRACT

An environmental investigation of ground water conditions has been undertaken at Wright-Patterson Air Force Base (WPAFB), Ohio to obtain data to assist in the evaluation of a potential removal action to prevent, to the extent practicable, migration of contaminated ground water across Base boundaries. Field investigations were limited to the central section of the southwestern boundary of Area C and the Springfield Pike boundary of Area B. Further, the study was limited to a maximum depth of 150 feet below grade. Three primary activities of the field investigation were: 1) installation of 22 monitoring wells, 2) collection and analysis of ground water from 71 locations, and 3) measurement of ground water elevations at 69 locations.

Ground water at the southwest boundary of Area C moves in a west to northwest direction toward the Mad River. The aquifer appears to consist of a single unit with thickness at the boundary approximately one-half of that expected from regional data. Volatile organic compounds including trichloroethylene, perchloroethylene, and/or vinyl chloride were detected in concentrations exceeding Maximum Contaminant Levels (MCL) at three locations within the Area C investigation area.

Ground water at the Springfield Pike boundary of Area B occurs in two primary units, separated by a thicker-than-expected clay layer. Below the clay layer, ground water flows from the Base in a northward direction; data gathered during the investigation were insufficient to determine the direction of flow in the upper portion of the aquifer. One well within Area B was determined to exceed the MCL for trichloroethylene.

EXECUTIVE SUMMARY

INTRODUCTION

Volume 5 of the "Environmental Investigation of Ground Water Contamination at Wright-Patterson Air Force Base, Ohio" has been prepared to describe activities of the Phase I, Task 4, Field Investigation. A limited and Ohio Environmental Protection Agency (EPA) approved field investigation was conducted between September 7 and October 1, 1990 to obtain selected data to assist in the evaluation of a potential removal action under the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA). To the extent practicable, it is the purpose of the off-site migration project to prevent migration of ground water contamination across the boundaries of Wright-Patterson AFB. The field investigation to collect data to support objectives of the off-site migration project was limited to the central section of the southwestern boundary of Area C and the Springfield Pike boundary of Area B. Further, the study (i.e., installation of new data collection points) was limited to a maximum depth of 150 feet below grade.

Field Program Activities

The Phase I, Task 4, Field Investigation was conducted in accordance with procedures outlined in the Field Sampling Plan (FSP) and Quality Assurance Project Plan (QAPP) which are contained in the Volume 3, Sampling and Analysis Plan (SAP). The three primary activities of the field investigation were: 1) installation of 22 monitoring wells, 2) collection and analysis of ground water samples from 71 new and existing monitoring and production wells, and 3) measurement of ground water elevations at 69 new and existing monitoring wells. Data collected were used to characterize hydrogeologic conditions at the Base boundaries, and to determine the quality of ground water at the Base for purposes of designing and implementing a removal action.

The field program was conducted by IT Corporation (IT) under contract with the Environmental Management Operations (EMO)^(a). IT utilized the services of a drilling subcontractor, a licensed surveyor, and a geotechnical

---

(a) EMO is operated for the U.S. Department of Energy by Battelle Memorial Institute.

analytical laboratory to complete the field efforts. Water quality samples were analyzed by the IT Analytical Services (ITAS) Laboratory in Cincinnati, Ohio, and geologic samples were analyzed by ATEC Associates, Inc. located in Cincinnati.

Borehole construction and monitoring well installation was accomplished utilizing four drilling rigs (three cable tool and one hollow stem auger). A total of 22 wells were installed as eight well clusters along the boundaries of Areas B and C. In Area B three clusters were installed (CW-1, CW-2, and CW-3); in Area C, five clusters were installed (CW-4, CW-5, CW-6, CW-7, and CW-8). Because the drilling and well installation program was exploratory in nature, the final well network varied somewhat from that described in the Volume 2, Work Plan.

All monitoring wells were constructed of 304 or 316 stainless steel riser pipe with either 10-foot or 20-foot long sections of 316 stainless steel screen. Deep wells in Area B (CW1-121, CW2-90, and CW3-77) were double-cased through a clay confining layer with grouted eight-inch mild steel casings. The annular space of the wells was sand packed in the screened interval and sealed to land surface. Following installation, each well was developed to remove fine sediments.

Twenty-two new wells and 49 existing monitoring wells and production wells were sampled for chemical analysis. All samples were analyzed for the list of volatile organic compounds (VOCs) contained in the CERCLA Target Compound List (TCL). Ground water samples were analyzed for total petroleum hydrocarbons (TPH) by the California Leaking Underground Fuel Tank (LUFT) method. Six new wells were also analyzed for general water quality constituents (i.e., cations, anions, hardness, alkalinity, TDS, pH, and TOC). Wells were screened prior to sampling for presence of nonaqueous phase liquids (NAPLs) and dense nonaqueous phase liquids (DNAPLs).

To assure the quality of the laboratory results, several QA/QC samples were prepared. These samples included trip blanks, equipment blanks, duplicate samples, and matrix spike/matrix spike duplicate pairs. The laboratory utilized method blanks and surrogates to check the quality of its efforts.

The health and safety of the working crew was of utmost importance during the field effort. Photoionization detectors (PIDs) and compound-specific colorimetric tubes were used to monitor the breathing space, bore-hole, and cuttings for VOCs. One crew member was assigned to continually monitor these conditions during drilling. No unsafe conditions were identified by the monitoring effort.

All water generated during the drilling, development, and sampling activities was collected and stored in large tanks for disposal to the city of Dayton wastewater treatment plant. Cuttings found to contain trace levels of VOCs during screening were stored for off-site disposal.

Hydrogeologic Findings

While the primary emphasis of this Phase I, Task 4, Field Investigation was to determine ground water quality at the Base boundaries, data generated during this study were used to support the description of hydrogeologic conditions. Two major differences in the hydrogeologic conditions were identified which were contrary to previous interpretations.

First, the thickness of the aquifer at the Area C southwestern boundary is almost one-half of that expected, especially beneath well clusters CW-4, CW-5, and CW-6. (Bedrock was not encountered at the maximum drilling depth of 150 feet at CW-7 or CW-8). Bedrock was encountered at all three locations at depths of about 100 feet or less. In Area C the shaley bedrock is directly overlain by clay.

Second, the thickness of a clay till zone in Area B which separates the Mad River Valley Aquifer into two units is almost twice as thick as expected. This finding indicates that the upper flow system is about 20 feet instead of 50 to 70 feet thick as expected. The thickness of the deeper system was not evaluated during this study.

Ground water in Area C is flowing off the Base toward the Mad River to the west and northwest. On the date of ground water level measurement, the Mad River was acting as a point of discharge for at least the shallow portions of the Mad River Valley Aquifer. The Rohrer's Island Well Field pumpage appears to have no direct effect on ground water flow from Area C.

In Area B, data are insufficient to define whether ground water flows off the Base toward the Rohrer's Island Well Field at the water table. Below the till, pumpage from the well field causes ground water to flow off the Base in a northerly direction.

Water Quality Findings

VOCs were detected in 55 percent of all wells sampled. This is consistent with previously available information. Thirteen of the 22 new wells yielded ground water samples with detectable environmental volatiles. A total of 15 different environmentally attributable compounds were identified in samples, however, only trichloroethylene, dichloroethylene, perchloroethylene, and vinyl chloride were confirmed to be present in ground water samples with any frequency.

VOCs were detected in ground water samples from wells at all depths in the Mad River Valley Aquifer. Of all the wells with detected VOCs, 60 percent contained concentrations less than 5 $\mu\text{g/L}$ of total VOCs. However, 16 percent of the wells yielded samples with concentrations greater than 50 $\mu\text{g/L}$ of total VOCs.

Ground water samples from ten wells (MW-21, CW3-77, CW5-55, CW5-85, CW6-77, HD-11, HD-12S, HD-12M, HD-13S, and HD-14S) exceeded U.S. EPA Maximum Contaminant Levels (MCLs) for trichloroethylene, perchloroethylene, and/or vinyl chloride. The VOC which most frequently exceeded its MCL is trichloroethylene which was predominantly detected in wells at the Area C boundary. Only one new well in Area B, CW3-77, exceeded MCLs for trichloroethylene.

Currently available data indicate the ground water which contains VOCs in excess of MCLs is leaving the southwest boundary of Area C. The area affected includes new cluster well locations CW-4, CW-5, and CW-6. Available data are insufficient to determine if contaminated ground water is leaving the Base along the Springfield Pike boundary of Area B.

ACRONYMS

AFSC	Air Force Systems Command
AFLC	Air Force Logistics Command
APR	Air Purifying Respirator
ASTM	American Society for Testing and Materials
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CLP	Contract Laboratory Program
DL	Detection Limit
DNAPL	Dense Non-Aqueous Phase Liquid
DQO	Data Quality Objective
DRMO	Defense Reutilization and Marketing Office
EMO	Environmental Management Operations
EPA	Environmental Protection Agency
FID	Flame Ionization Detector
FSP	Field Sampling Plan
GC	Gas Chromatograph
HSA	Hollow Stem Auger
HSP	Health and Safety Plan
IP	Ionization Potential
IRP	Installation Restoration Program
IT	IT Corporation
ITAS	IT Analytical Services
LUFT	Leaking Underground Fuel Tank
MCD	Miami Conservancy District
MCLs	Maximum Contaminant Levels

MRWF	Mad River Well Field
MS	Matrix Spike
MSD	Matrix Spike Duplicate
MSL	Mean Sea Level
NAPL	Non-Aqueous Phase Liquid
NGVD	National Geodetic Vertical Datum
NTU	Nephelometric Turbidity Unit
OEM	Office of Environmental Management
Ohio EPA	Ohio Environmental Protection Agency
OVA	Organic Vapor Analyzer
PEL	Permissible Exposure Limit
PHC	Petroleum Hydrocarbons
PID	Photoionization Detector
POL	Petroleum, Oils and Lubricants
PVC	Polyvinylchloride
QA/QC	Quality Assurance/Quality Control
QAPP	Quality Assurance Project Plan
RI/FS	Remedial Investigation/Feasibility Study
RPD	Relative Percent Difference
SAP	Sampling and Analysis Plan
SAS	Special Analytical Services
SOPs	Standard Operating Procedures
TCL	Target Compound List
TDS	Total Dissolved Solids
TICs	Tentatively Identified Compounds
TLs	Target Levels

TOC	Total Organic Carbon
TPH	Total Petroleum Hydrocarbons
USGS	U.S. Geological Survey
VOC	Volatile Organic Compound
WPAFB	Wright-Patterson Air Force Base

CONTENTS

ABSTRACT	ii
EXECUTIVE SUMMARY	iii
ACRONYMS	vii
FIGURES	xv
TABLES	xvi
APPENDICES	xviii
PLATES	xix
1.0 INTRODUCTION	1.1
1.1 PURPOSE AND SCOPE	1.1
1.2 EXTENT OF PROBLEM	1.1
1.3 FIELD INVESTIGATION SUMMARY	1.2
1.4 REPORT OVERVIEW	1.3
2.0 BACKGROUND INFORMATION	2.1
2.1 SITE DESCRIPTION	2.1
2.2 GROUND WATER INVESTIGATION PROJECT HISTORY	2.1
2.3 PROJECT DATA NEEDS	2.4
2.3.1 Hydrogeologic and Hydraulic Data	2.5
2.3.2 Ground Water Quality Data	2.5
2.4 TECHNICAL WORK PLAN EXECUTION - OVERVIEW	2.6
2.4.1 Installation of New Wells	2.6
2.4.2 Sampling of Existing Wells	2.8
2.4.3 Sampling of New Wells	2.8
2.4.4 Measurement of Water Levels	2.8
3.0 ENVIRONMENTAL SETTING	3.1
3.1 LOCATION AND PHYSICAL SETTING	3.1

CONTENTS (cont.)

3.2	CLIMATE	3.1
3.3	DRAINAGE	3.2
3.4	SURFACE WATER FEATURES	3.2
3.5	GEOLOGY	3.3
	3.5.1 Stratigraphy and Lithology	3.3
	3.5.2 Depositional Environment	3.3
3.6	HYDROGEOLOGY	3.5
	3.6.1 Regional Hydrogeology	3.5
	3.6.2 Site Hydrogeology	3.5
	3.6.3 Hydraulics	3.6
4.0	FIELD PROGRAM ACTIVITIES AND PROCEDURES	4.1
4.1	BOREHOLE CONSTRUCTION, SAMPLING, AND MONITORING WELL INSTALLATION	4.2
	4.1.1 Soil Boring Installation	4.4
	4.1.2 Monitoring Well Construction	4.7
	4.1.3 Borehole and Monitoring Well Abandonment	4.7
	4.1.4 Sample Collection for Grain-Size Analysis	4.8
	4.1.5 Well Development	4.8
	4.1.6 Well Elevation Survey	4.9
4.2	GROUND WATER SAMPLING, SAMPLE HANDLING, AND ANALYTICAL PROCEDURES	4.12
	4.2.1 Well Evacuation and Ground Water Sampling	4.12
	4.2.2 Field and Laboratory Quality Assurance/Quality Control (QA/QC)	4.14
	4.2.3 Sample Identification, Labeling, Preparation and Shipping	4.15
	4.2.3.1 Sample Identification and Labeling	4.15

CONTENTS (cont.)

4.2.3.2	Sample Nomenclature System	4.15
4.2.3.2.1	Well Identification	4.18
4.2.3.2.2	Sampling Date	4.18
4.2.3.2.3	Sample Purpose	4.18
4.2.3.3	Sample Preparation	4.18
4.2.3.4	Storage and Shipping	4.20
4.2.4	Chain-of-Custody Procedures	4.20
4.2.4.1	Sample Collection Logs	4.21
4.2.4.2	Request-for-Analysis	4.21
4.2.5	Laboratory Analysis	4.22
4.3	WATER LEVEL MEASUREMENTS	4.22
4.4	VOC SCREENING ACTIVITIES DURING THE FIELD PROGRAM	4.26
4.4.1	Air Monitoring During Drilling Activities	4.29
4.4.2	Screening of Borehole Cuttings and Water	4.31
4.5	DISPOSAL OF DRILL CUTTINGS AND FLUIDS	4.33
4.5.1	Handling and Disposal of Fluids Generated During the Field Investigation	4.33
4.5.2	Handling and Disposal of Cuttings Generated During Borehole Construction	4.34
4.6	PERSONAL PROTECTION AND DECONTAMINATION OF EQUIPMENT	4.34
4.6.1	Personal Protection	4.37
4.6.2	Equipment Decontamination	4.39
5.0	SUMMARY OF HYDROGEOLOGIC RESULTS	5.1
5.1	SITE GEOLOGY	5.1
5.1.1	Geology in Area C	5.1
5.1.2	Geology in Area B	5.3

CONTENTS (cont.)

5.1.3	Bedrock Configuration	5.4
5.2	SITE HYDROGEOLOGY	5.4
5.2.1	Hydrogeologic Setting in Area C	5.5
5.2.2	Hydrogeologic Setting in Area B	5.6
5.2.3	Ground Water Contour Maps	5.6
5.3	HYDRAULICS	5.7
5.3.1	Hydraulic Conductivity	5.7
5.3.2	Transmissivity	5.8
5.3.3	Flow Systems	5.8
6.0	SUMMARY OF WATER QUALITY DATA	6.1
6.1	GROUND WATER ANALYTICAL RESULTS	6.1
6.1.1	Inorganics	6.1
6.1.2	Organics	6.3
6.1.3	QA/QC Results	6.16
6.2	GROUND WATER QUALITY TRENDS	6.17
6.2.1	Occurrence of VOCs in Ground Water	6.17
6.2.2	Designation of Water Quality Zones for Evaluation of Ground Water Data	6.18
6.2.3	Study of VOCs as a Composite Concentration	6.18
6.2.4	Study of VOCs as Specific Compounds	6.21
6.2.5	VOC Concentrations in Ground Water Exceeding MCLs	6.23
6.2.6	Vertical Distribution of Selected VOCs	6.25
7.0	FINDINGS AND CONCLUSIONS	7.1
7.1	HYDROGEOLOGY	7.2
7.1.1	Hydrogeology of Area C	7.2
7.1.2	Hydrogeology of Area B	7.3

CONTENTS (cont.)

7.2	GROUND WATER QUALITY	7.3
7.2.1	Area C Boundary	7.4
7.2.2	Area B Boundary	7.5
7.2.3	Other Areas	7.5
7.3	EXTENT OF CONTAMINATION	7.6
REFERENCES CITED	. . . . .	R.1

FIGURES

2.1	Area Location Map	2.2
2.2	Wright-Patterson Air Force Base	2.3
2.3	Location of New Phase I, Task 4, Monitoring Well Clusters	2.7
2.4	Location of Wells That Were Sampled for Phase I, Task 4	2.10
2.5	Location of Monitoring Wells Where Water Levels Were Measured for Phase I, Task 4	2.12

TABLES

2.1	Phase I, Task 4, Monitoring Well Installation Program	2.9
2.2	List of Laboratory Analytical Parameters	2.11
3.1	Generalized Bedrock Stratigraphy	3.4
4.1	Chronology of Activities During the Phase I, Task 4, Field Investigation	4.3
4.2	Deviations for Phase I, Task 4, Drilling Program	4.5
4.3	Summary of Well Construction Information for Task 4 Field Investigation	4.6
4.4	Final Turbidity Measurements and Development Status	4.10
4.5	Well Elevation Survey for Task 4 Field Investigation	4.11
4.6	Quality Control Limits for Volatile Organic Compounds	4.16
4.7	Surrogate Samples That Exceeded Method Acceptance Limits	4.17
4.8	Water Sampling Specifications	4.19
4.9	Summary of Methods and QC Requirements	4.23
4.10	TPH Samples Which Were Not Extracted by LUFT Method	4.25
4.11	Water Level Measurements	4.27
4.12	Air Monitoring During Borehole Construction	4.30
4.13	Headspace Screening of Cuttings From Borehole Construction	4.32
4.14	Summary of Wastewater Analyses	4.35
4.15	Summary of Water Truck Analyses	4.36
4.16	Summary of Personal Protection Levels Donned During Drilling Program	4.38
5.1	Estimated Hydraulic Conductivity for Collected Soil Samples	5.9
6.1	Summary of Inorganic Results for Ground Water Samples	6.2
6.2	Summary of VOC Results for Ground Water Samples	6.4
6.3	Summary of Trip Blank and Equipment Blank Results for Ground Water Samples	6.10

TABLES (cont.)

6.4	Summary of Method Blank Results for Ground Water Samples	6.12
6.5	Designation of Wells by Aquifer Layers	6.19
6.6	Maximum Contaminant Levels for Organic Compounds in Public Water Systems	6.24

APPENDICES

(provided under separate cover)

PART 1

- A SELECTED PHOTOGRAPHS THAT DOCUMENT PHASE I, TASK 4, FIELD ACTIVITIES
- B SOIL BORING LOGS
- C WELL CONSTRUCTION LOGS
- D WELL DEVELOPMENT LOGS
- E X-RAY DIFFRACTION RESULTS FOR GROUND WATER SAMPLES
- F GROUND WATER SAMPLING FORMS
- G CHAIN-OF-CUSTODY RECORDS AND REQUEST-FOR-ANALYSIS FORMS

PART 2

- H PHOTOIONIZATION DETECTOR AND COMPOUND-SPECIFIC COLORIMETRIC TUBE FIELD SCREENING LOGS
- I ANALYTICAL RESULTS FOR WASTEWATER AND WATER TRUCK SAMPLES
- J GRAIN-SIZE DISTRIBUTION ANALYSIS
- K ANALYTICAL RESULTS FOR GROUND WATER SAMPLES
- L TENTATIVELY IDENTIFIED COMPOUNDS FOR WELLS CW-7 AND CW-8

PLATES

(provided under separate cover)

- 5.1 Geologic Cross Sections
- 5.2 Ground Water Vertical-Flow-Gradient Cross Sections
- 5.3 Schematic Ground Water View Cross-Sections
- 5.4 Water Table Contour Map, October 1990
- 6.1 Concentration of Volatile Organic Compounds in the Upper Water-Quality Zone (Area B)
- 6.2 Concentration of Volatile Organic Compounds in the Upper Water-Quality Zone (Area C)
- 6.3 Concentration of Volatile Organic Compounds in the Middle Water-Quality Zone (Area B)
- 6.4 Concentration of Volatile Organic Compounds in the Middle Water-Quality Zone (Area C)
- 6.5 Concentration of Volatile Organic Compounds in the Lower Water-Quality Zone (Area B)
- 6.6 Concentration of Volatile Organic Compounds in the Lower Water-Quality Zone (Area C)
- 6.7 Concentration of Trichloroethylene in the Upper Water-Quality Zone (Area B)
- 6.8 Concentration of Trichloroethylene in the Upper Water-Quality Zone (Area C)
- 6.9 Concentration of Trichloroethylene in the Middle Water-Quality Zone (Area B)
- 6.10 Concentration of Trichloroethylene in the Middle Water-Quality Zone (Area C)
- 6.11 Concentration of Trichloroethylene in the Lower Water-Quality Zone (Area B)
- 6.12 Concentration of Trichloroethylene in the Lower Water-Quality Zone (Area C)
- 6.13 Concentration of 1,2 Dichloroethylene in the Upper Water-Quality Zone (Area B)

1.0 INTRODUCTION

1.1 PURPOSE AND SCOPE

This Field Investigation Report has been prepared for the Office of Environmental Management (OEM) at Wright-Patterson Air Force Base (WPAFB) as part of the Environmental Investigation of Ground Water Contamination being conducted at the Base under the Installation Restoration Program (IRP) in accordance with the Administrative Orders of Consent issued to WPAFB from the Ohio Environmental Protection Agency (Ohio EPA). The objective of the Field Investigation was to obtain additional data for evaluation of a potential removal action under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA).

The services of the Environmental Management Operations (EMO)^(a) and its principal subcontractor, IT Corporation (IT) were retained by WPAFB to complete Phase I of the Environmental Investigation of Ground Water Contamination at the Base. Phase I involves the short-term evaluation and design of a program to prevent ground water contamination from migrating across the southwest boundary of Area C and across the Springfield Pike boundary adjacent to Area B (refer to Figure 2.2 for locations). The potential CERCLA removal action will be based on a Focused Feasibility Study that is subject to approval by the Ohio EPA.

1.2 EXTENT OF PROBLEM

The primary ground water resource at WPAFB is the Mad River Valley Aquifer, which underlies most of the site. Chlorinated solvents (e.g., trichloroethylene, perchloroethylene, etc.) have been detected in ground water samples collected from production wells in Area C of WPAFB and in a well providing drinking water for the caretaker's cottage near Huffman Dam, west of the Area C boundary of WPAFB. Ground water samples collected from production wells in Area B and at the northeast corner of the Rohrer's Island section of

---

(a) EMO is operated for the U.S. Department of Energy by Battelle Memorial Institute.

the city of Dayton's Mad River Well Field (MRWF) have also contained detectable concentrations of chlorinated solvents.

Several ground water monitoring wells were installed by the city of Dayton in May and June 1990 at a location upgradient of the Rohrer's Island Well Field and downgradient of the western boundary of Area C. Based on analytical results of ground water obtained from these wells, chlorinated solvents have been detected at concentrations ranging from nondetected to a level of several hundred parts per billion. The analytical results indicate that chlorinated solvents from WPAFB may potentially be migrating to the Rohrer's Island Well Field.

1.3 FIELD INVESTIGATION SUMMARY

Task 4 of the Phase I investigation involved the collection of additional geologic, hydrogeologic, and ground water quality data at the Area C and Springfield Pike boundaries of WPAFB. This Field Investigation Report describes the Task 4 Field Investigation, which was conducted between September 7 and October 1, 1990. All field activities were performed in accordance with the following three documents dated August 1990:

- Volume 2, Work Plan for the Phase I, Task 4, Field Investigation - The Work Plan presents the rationale and scope of the technical services necessary to achieve the study objectives.
- Volume 3, Sampling and Analysis Plan (SAP) of the Phase I, Task 4, Field Investigation - The SAP consists of a Quality Assurance Project Plan (QAPP) and a Field Sampling Plan (FSP), which provide guidance for all field work by defining the sampling and data-gathering methods that were used in this investigation.
- Volume 4, Health and Safety Plan (HSP) for the Phase I, Task 4, Field Investigation - The HSP provides general and site-specific health and safety requirements and an assessment of on-site physical and chemical hazards, including a determination of permissible exposure limits and an estimate of potential employee exposure to hazards, and the related protection requirements.

1.4 REPORT OVERVIEW

This Field Investigation Report has been prepared utilizing the U.S. Environmental Protection Agency's (EPA) Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA, Interim Final, October 1988. The remaining sections of this report are as follows:

- Section 2 - Background Information
- Section 3 - Environmental Setting
- Section 4 - Field Program Activities and Procedures
- Section 5 - Summary of Hydrogeologic Results
- Section 6 - Summary of Water Quality Data
- Section 7 - Findings and Conclusions

Appendix materials for this report are bound separately in two parts; Part 1 (Appendices A through G) and Part 2 (Appendices H through L). A set of plates, that are bound separately (Plates 5.1 through 5.4 and 6.1 through 6.23), were also prepared for this report.

2.0 BACKGROUND INFORMATION

2.1 SITE DESCRIPTION

Wright-Patterson Air Force Base (WPAFB) is located in the southwestern portion of Ohio, approximately 3 miles east of downtown Dayton and 60 miles north and east of Cincinnati (Figure 2.1). The Base consists of approximately 8,500 acres of land, which contains both an active air field (Patterson Field) and an inactive air field (Wright Field). The Base is divided into four areas: 1) Area A, which contains Air Force Logistics Command (AFLC) Headquarters, the Foreign Technology Division of Air Force Systems Command (AFSC), and a number of other administrative and warehouse facilities; 2) Area B, which contains the Aeronautical Systems Division of AFSC, the Air Force Institute of Technology, various AFSC laboratories, and the Air Force Museum; 3) Area C, which contains the 4950th Test Wing (AFSC), the 906th Tactical Fighter Wing (Ohio ANG), the main Petroleum, Oils and Lubricants (POL) storage areas, and other facilities related to the operation of aircraft and the administration of Base personnel; and 4) Kittyhawk Center, which contains the Commissary, Main Exchange, Base Theater, and other recreational facilities. All four areas are maintained and supported by the 2750th Air Base Wing (AFLC). Figure 2.2 provides a map of the Base.

The Base has been in continuous operation since before World War II and has been the scene of numerous activities, including flight operations and maintenance, research and development, prototype fabrication, and other industrial operations.

2.2 GROUND WATER INVESTIGATION PROJECT HISTORY

In April 1990, the OEM at WPAFB, initiated an effort for the evaluation and potential remediation of ground water contamination at the Base. This effort was initiated through the IRP in accordance with Administrative Orders on Consent issued to WPAFB from the Ohio EPA. The effort involves a potential removal action under CERCLA to prevent, to the extent practicable, the migration of ground water contamination in the Mad River Valley Aquifer across the Base boundaries.

FIGURE 2.1. Area Location Map

FIGURE 2.2. Wright-Patterson Air Force Base

Phase I of the ground water contamination investigation was designed to assess the nature and extent of ground water contamination at the southwest boundary of Area C and along Springfield Pike adjacent to Area B at WPAFB.

The Phase I efforts include the following tasks and deliverables:

- Task 1: Data Collection
- Task 2: Data Review and Analysis - Volume 1, Site Assessment Report
- Task 3: Project Plans - Volume 2, Work Plan; Volume 3, Sampling and Analysis Plan (SAP); and Volume 4, Health and Safety Plan (HSP)
- Task 4: Field Investigation - Volume 5, Field Investigation Report
- Task 5: Focused Feasibility Study and Design - Several volumes to be prepared following submittal of Volume 5.

The Volume 1, Site Assessment Report was developed under Task 2 by using existing studies and reports from previous field evaluations, RI/FSs, site surveys, well-sampling data, and other available data sources that were compiled under Task 1. The Task 2 data review and analysis effort identified data deficiencies that would compromise selection and design of potential removal actions. The Phase I, Task 4, Field Investigation was required to offset these deficiencies. A Work Plan, SAP, and a HSP were developed under Task 3, to be used for the Task 4, Field Investigation (IT, 1990). During completion of the Task 4, Field Investigation Report, Task 5, efforts were being conducted to develop and screen removal-action alternatives for the control or removal of contamination which may be migrating across Base boundaries and to design a preferred removal-action alternative.

2.3 PROJECT DATA NEEDS

Existing data which were reviewed during Phase I, Task 2, were determined to be inconclusive with regard to hydrogeologic conditions and environmental quality of the Mad River Valley Aquifer in the area of investigation. The Task 4, Field Investigation was thus developed to collect critical data needed to conduct an evaluation of removal alternatives in a localized area.

The Phase I, Task 4, Field Investigation was not, however, comprehensive in scope or intent due to severe time constraints. It was designed for rapid completion, and the emphasis of this effort was to confirm pre-existing information or interpretations for a limited number of environmental contaminants.

Site specific information on hydrogeology, hydraulics, and ground water quality was generated during the Phase I, Task 4, Field Investigation. The following sections present an overview of the data collected during this field effort.

2.3.1 Hydrogeologic and Hydraulic Data

During the Phase I, Task 2, Site Assessment, it was determined that a numerical model was needed to test removal strategies. The existing data on hydraulic properties (e.g., transmissivity and storativity) and recharge/discharge relationships of the aquifer were believed to be sufficient for development of a numerical flow model using a proven code (e.g., MODFLOW) to represent the Mad River Valley Aquifer at WPAFB and the Mad River Well Field (MRWF). Therefore, for the Phase I ground water investigation, the decision was made to utilize existing hydrogeologic and hydraulic data for input in the computer model. Hydrogeologic input for the computer model would be adjusted as necessary if the Phase I, Task 4, drilling program identified conditions that were significantly different from those previously reported.

Calibration of the ground water flow model for a unique time in history, however, required the collection of water level data from newly installed Phase I, Task 4, wells and selected existing monitoring wells. Water level data were intended to be used for computer model input parameters. Calibration of the model would continue until the baseline potentiometric configuration developed from the new water level data could be reproduced.

2.3.2 Ground Water Quality Data

One objective of the Phase I, Task 4, Field Investigation was to evaluate water quality conditions at the southwest boundary of Area C and the area adjacent to Springfield Pike in Area B. Prior to the field investigation, available data suggested that a plume of perchloroethylene (tetrachloroethylene) and trichloroethylene was migrating off the Base from Area C near Landfill 5; however, the lateral or vertical extent of this plume could

not be fully defined. Also, because no wells were located between the Area B production wells and the Area B boundary, no data were available for determining whether contaminants were migrating off the Base along this boundary.

Filling these data gaps would require several new monitoring well clusters at the Base boundaries in an attempt to determine lateral and vertical water quality conditions. Three new well clusters were deemed necessary along the Area B property line and five new well clusters were needed along the west property line in Area C. New monitoring well locations were selected to assist in the evaluation of contaminant migration from Area B and C toward the Rohrer's Island Well Field. The Task 4 effort was not designed to include installation of wells farther upgradient or downgradient of either Base boundary.

The Task 4, Field Investigation included a single sampling of several existing and new wells located in close proximity to the west boundary of Area C and the Springfield Pike boundary of Area B. The collected data were intended to verify previously available information from existing wells and to supplement that general data base with information from installation of the new wells.

2.4 TECHNICAL WORK PLAN EXECUTION - OVERVIEW

The Phase I, Task 4, Field Investigation was completed in the following four basic steps:

- Installation of new wells
- Ground water quality sampling of existing wells
- Ground water quality sampling of new wells
- Water level measurements of existing and new wells

The following sections present an overview of Phase I, Task 4, activities completed for this investigation.

2.4.1 Installation of New Wells

As a means of providing more detailed information on lateral and vertical ground water quality conditions at the Area C and Area B property boundaries, 22 new wells (constituting eight clusters) were installed (Figure 2.3). New monitoring well locations were selected based on expected ground

water flow pathways and on general knowledge of ground water quality. Table 2.1 presents information on the new wells installed during this effort.

2.4.2 Sampling of Existing Wells

For the development of a current data base on the ground water quality conditions at WPAFB and the MRWF, 49 existing monitoring and production wells (in addition to the 22 newly installed wells) were sampled for chemical analysis. Wells sampled included all existing wells in the vicinity of the west boundary of Area C and the Springfield Pike boundary of Area B, as well as those Rohrer's Island Well Field monitoring and production wells previously reported to contain detectable VOCs. These wells were sampled over a three-week period. Figure 2.4 shows the location of the wells sampled under the Phase I, Task 4, Field Investigation.

Ground water samples were analyzed for the volatile organics fraction of the CERCLA Target Compound List (TCL) plus total petroleum hydrocarbons (TPH or PHC) to represent the environmentally mobile contaminants previously detected at WPAFB. Table 2.2 contains a complete listing of the TCL volatile organics for which analyses were performed in addition to other analytes of the testing program.

2.4.3 Sampling of New Wells

After installation and development, each new well was sampled for analysis of TCL volatile organics and TPH. In addition, six of the 22 new wells (wells in clusters CW-2 and CW-8) were sampled and analyzed to provide some general information for remedial design engineering purposes (i.e., cations, anions, hardness, alkalinity, TDS, pH, and TOC). Table 2.2 lists the analytical parameters for ground water samples collected from the new monitoring wells.

2.4.4 Measurement of Water Levels

For calibration of the ground water flow model, water level measurements were taken on October 1, 1990 at 47 existing wells and 22 new monitoring wells. The wells used for water level measurements were not necessarily the same wells used for the ground water quality assessment, therefore, the total number of wells used for both activities differ. Figure 2.5 shows the

TABLE 2.1. Phase I, Task 4, Monitoring Well Installation Program^(a)

Cluster Well ID	Well No.	Well Depth (ft)	Screened Interval (ft)
CW1	CW1-27	27	17-27
	CW1-35	35	25.5-35.5
	CW1-121	121	111-121
CW2	CW2-35	35	15-35
	CW2-44	44	35.75-45.75
	CW2-90	90	80-90
CW3	CW3-27	27	7.33-27.33
	CW3-35	36	25-35
	CW3-77	77	66.8-76.8
CW4	CW4-60	60	49.67-59.67
	CW4-85	85	74-84
CW5	CW5-55	55	45-55
	CW5-85	85	75-85
CW6	CW6-77	77	67-77
	CW7-55	55	44.5-54.5
CW7	CW7-100	100	90-100
	CW7-148	148	138-148
	CW8-17	17	7.25-17.25
CW8	CW8-55	55	44.67-54.67
	CW8-85	85	75-85
	CW8-110	110	100-110
	CW8-150	150	140-150

^(a) See Figure 2.3 for locations of Phase I, Task 4 monitoring well clusters.

TABLE 2.2. List of Laboratory Analytical Parameters

<u>TCL Volatile Organic Compounds</u>	<u>Metals^(a)</u>
Acetone	Calcium
Benzene	Iron
Bromodichloromethane	Magnesium
Bromoform	Manganese
Bromomethane	Potassium
2-Butanone	Sodium
Carbon disulfide	
Carbon tetrachloride	
Chlorobenzene	<u>Anions^(a)</u>
2-Chloroethyl vinyl ether	Chlorides
Chloroform	Sulfates
Chloroethane	
Chloromethane	
Cis-1,3-dichloropropene	
Dibromochloromethane	<u>Miscellaneous Parameters</u>
1,1-Dichloroethane	Alkalinity ^(a)
1,1-Dichloroethene	Hardness ^(a)
1,2-Dichloroethane	pH ^(a)
1,2-Dichloroethene	TDS ^(a)
1,2-Dichloropropane	TOC ^(a)
Ethylbenzene	PHC-Low Boilers
2-Hexanone	PHC-High Boilers
4-Methyl-2 pentanone	
Methylene chloride	
Styrene	
Tetrachloroethene	
1,1,2,2-Tetrachloroethane	
Toluene	
Trans-1,3-dichloropropene	
1,1,1-Trichloroethane	
1,1,2-Trichloroethane	
Trichloroethene	
Vinyl acetate	
Vinyl chloride	
Total Xylenes	

^(a) Six new wells only.

location of the monitoring wells from which water level data were collected. Collection of water level data was limited to the vicinity of the west property line of Area C and the Springfield Pike portion of Area B. The area of investigation includes those wells that are far enough upgradient to define upflow conditions and far enough downgradient to include the MRWF. Water level measurements were made at monitoring wells only.

3.0 ENVIRONMENTAL SETTING

3.1 LOCATION AND PHYSICAL SETTING

Located in southwest Ohio, WPAFB lies between the cities of Dayton and Fairborn (Figure 2.1) and occupies portions of Greene and Montgomery counties. It consists of two sections--Areas A and C, and Area B (Figure 2.2). Areas A and C comprise approximately 5,700 acres and contain Patterson Field. Area B covers approximately 2,800 acres and contains Wright Field, including the Air Force Museum and the Air Force Institute of Technology.

The Base rests within the Till Plains Section of the Central Lowland Physiographic Province (Fenneman, 1938). Except along a north-to-south-trending bedrock ridge in the eastern third of Area B, the topography is flat to gently rolling. Large segments of the Base are within the Mad River floodplain. The land surface altitude ranges from about 750 feet above sea level on the northwest boundary of Area B to 980 feet above sea level along National Road on the east boundary of Area B. Within Areas A and C, elevations range from about 790 feet above sea level on the southwest boundary near the Huffman Dam to 830 feet above sea level along the northeast boundary of the Base.

3.2 CLIMATE

The climate of WPAFB and surrounding areas is humid and temperate; the mean annual temperature is 52.5°F (NOAA, 1988). Recorded temperatures during the period 1936 to 1975 indicate a mean monthly minimum of 21.4°F in the winter. The recorded mean monthly maximum in the summer is 85.2°F (NOAA, 1988). Annual precipitation is about 36 inches. Mean monthly precipitation ranges from 2.17 inches in February to 3.73 inches in May. Mean annual precipitation measured as snowfall for the same period of record is 27.7 inches. Average annual lake evaporation is estimated to be 33 inches (Bloyd, 1974).

3.3 DRAINAGE

In general, surface water runoff within WPAFB discharges to the Mad River and its tributaries. Runoff in Areas A and C is carried by a network of storm sewers and unnamed tributaries to Hebble Creek, Trout Creek, and Mud Run. Hebble Creek, Trout Creek, and Mud Run subsequently drain into the Mad River east of Huffman Dam. The eastern section of Area B is drained by a combined network of storm sewers, drainage ditches, and unnamed tributaries to Hebble Creek. The western section of Area B is drained by a network of storm sewers and drainage ditches to an unnamed stream that enters the Mad River south of Rohrer's Island.

Most of the natural drainage system at WPAFB has been altered over the years to improve surface water runoff. For example, the Mad River in the vicinity of the WPAFB has been straightened. Huffman Dam was constructed across the Mad River immediately downstream of Area C as a means of flood control. Portions of Trout Creek and Hebble Creek have also been straightened and channelized over the years.

3.4 SURFACE WATER FEATURES

The dominant surface water feature at WPAFB is the Mad River, which forms the north boundary of the Base along its entire east-west length. In 1921, the Miami Conservancy District (MCD) constructed the Huffman Dam approximately 2,000 feet west of the western boundary of Area C as a flood-control structure for the Mad River and its tributaries.

The Mad River is a perennial stream that flows during much of the year as a result of ground water discharge to the river. As measured at Huffman Dam, the average flow of the river is 630 cubic feet per second (cfs) or 407 million gallons per day (mgd). Since 1914, the recorded extreme flow rates are 61 and 13,695 mgd (Weston, 1989).

Below Huffman Dam, a portion of the Mad River's flow is diverted to recharge lagoons on Rohrer's Island. These lagoons are maintained solely for replenishing the aquifer (Geraghty & Miller, 1987).

Several artificial lakes in the MRWF store water that is also available for recharge. The west lake, the east lake, and the Dayton Hydrobowl are among the lakes of the well field.

Area C of WPAFB has several artificial lakes. Bass Lake, Gravel Lake, and the Twin Lakes (all former gravel quarries) are the major surface water features. The golf courses also have artificial ponds. These stationary water bodies are used primarily for recreational purposes.

Approximately 92 acres of wetland areas exist in both Areas B and C. Wetlands in Area C lie northeast of the MCD's property near Gravel Lake. Three wetland areas in Area B are associated with springs emanating from the base of the Brassfield Formation.

3.5 GEOLOGY

3.5.1 Stratigraphy and Lithology

The geology of the Dayton area consists of Ordovician and Silurian Age sedimentary rocks overlain by glacial till and outwash deposits of Pleistocene Age. Shale and limestone of The Richmond Group of the Ordovician Age is the bedrock unit underlying most of the Base. Table 3.1 presents a summary of the general bedrock stratigraphy. Bedrock is exposed in the north-to-south ridge located in the eastern third of Area B. Bedrock also outcrops at several locations along Hebble Creek and the Mad River.

3.5.2 Depositional Environment

Unconsolidated materials of Pleistocene Age overlie the bedrock and are represented in the area by till and outwash deposits. These materials were deposited during the last period of major glaciation and are present throughout the area. Glacial till consisting of a heterogeneous mixture of cobbles, gravel, sand, silt, and clay was deposited directly by the glacier as it moved over the region. The till is generally interbedded with sand and gravel zones. Melt streams flowing from the glacier deposited large accumulations of sand and gravel identified as outwash deposits. These outwash deposits attain a maximum thickness of 250 feet in the Dayton area (Norris and Spieker, 1966).

TABLE 3.1. Generalized Bedrock Stratigraphy^(a)

System	Group	Formation	Character of Material	Water-Bearing Properties	Average Thickness (feet)
Silurian	Niagara	Cedarville dolomite	Massive, porous.	Generally good water supplies available for farm and domestic requirements, except from the Osgood shale. Wells ordinarily yield from 6 to 15 gpm. A few wells yield from 100 to 200 gpm. Water is very hard. Important spring horizon at base of system.	50+
		Springfield dolomite	Well-bedded, dense.		14
		Euphemia dolomite of Foerste	Massive, porous.		8
		Laurel dolomite	Well-bedded, dense.		5
		Osgood Formation	Shale, calcareous, with limestone beds.		15
		Dayton limestone	Limestone or dolomite, well-bedded, dense.		8
	Clinton	Brassfield limestone	Fossiliferous, massive to irregularly bedded.		30
Ordovician	Richmond Maysville Eden Group, Undifferentiated		Shale, soft, calcareous, interbedded with thin, hard, limestone layers; called Cincinnati shale in old reports.	Wells generally yield no water, or seldom more than 1 gpm. Water is sometimes highly charged with iron or salt compounds. Where water is present it generally occurs in top few feet of strata.	980
	Pre-Eden	Trenton limestone	Limestone or dolomite with some shale.	Generally yields salt water at base.	500

^(a) Source: Engineering-Science, 1989

Sediments of Recent Age, deposited in relatively thin layers by modern streams, are present at the ground's surface adjacent to all major streams. This alluvium consists of both sorted and unsorted accumulations of sand, silt, gravel, and clay.

3.6 HYDROGEOLOGY

3.6.1 Regional Hydrogeology

The Base lies within the Ohio Ground Water Resource Region of the United States (Bloyd, 1974). Ground water resources of the region are primarily associated with unconsolidated sediments of glacial origin. These sediments and the ground water they contain are an important and integral component of the area's hydrologic cycle. The major recharge to local aquifers includes infiltration of precipitation, stream-flow infiltration, and artificial or induced recharge through engineered structures.

The Mad River Valley Aquifer (i.e., the Pleistocene, fluvial-glacial sediments), which underlies most of WPAFB and the MRWF, is the most extensive water-bearing medium underlying the Base. This aquifer receives contributions of ground water underflow and surface water infiltration from the surrounding uplands and the many natural and artificial recharge features described in Section 3.4. Immediately at the Mad River, the aquifer may discharge to the river or be recharged by the river based on seasonal and local pumping influences.

The Mad River Valley Aquifer, designated a sole-source aquifer by the EPA, is the primary source of drinking water in the area. The cities of Dayton and Fairborn, WPAFB, and Wright State University derive water from the aquifer. Some industries, commercial enterprises, and residences that are not connected to public water systems also use water from the aquifer for various purposes, including processing, heating, cooling, irrigation, and consumption.

3.6.2 Site Hydrogeology

Most of Area C is underlain by unconsolidated glacial outwash sands and gravel, as is the western half of Area B. These outwash deposits fill a preglacial valley of the Teays River System. Outwash deposits may be more than 200 feet thick toward the center of the preglacial valley.

The configuration of the glacial outwash deposits is controlled by the bedrock surface, which is at a maximum depth of approximately 285 feet in Areas B and C. A major bedrock valley system trends in a northeasterly to southwesterly direction beneath Area C toward Huffman Dam. A northwesterly trending valley from the south joins the primary valley in Area A. West of Huffman Dam, a second northwesterly trending valley exists beneath Area B.

3.6.3 Hydraulics

A potentiometric surface map of the water table on the Base, as measured by Weston, Inc., in March 1988, indicates that the regional flow direction of the aquifer is toward the Mad River and parallel to the southwest trend of the Mad River Valley (Weston, 1989). Over portions of the Base, however, ground water flows in a more northerly direction. Pumping and recharging the MRWF influences ground water flow in the aquifer toward the center of the well field.

Potentiometric maps prepared by Geraghty & Miller (1987) for the MRWF indicate that the hydraulic head of the water table is greater than the head in lower sections of the aquifer in most areas. This vertical head difference indicates a potential for vertical movement of water from the shallower to the deeper segments of the Mad River Valley Aquifer.

4.0 FIELD PROGRAM ACTIVITIES AND PROCEDURES

The Phase I, Task 4, Field Investigation was conducted according to procedures outlined in the FSP and QAPP which are contained in Volume 3 of the SAP (IT 1990). The three primary activities of the field investigation program at WPAFB were the installation of 22 monitoring wells, ground water sampling and analysis, and ground water elevation measurements. Pursuant to requests by the Ohio EPA, draft Standard Operating Procedures (SOPs) prepared by Martin-Marietta Energy Systems, Inc. (1990) for the Base-wide RI/FS were used to complete this investigation. These modified draft SOPs are found in Appendix A of the Volume 3 SAP.

This section describes the field activities which began on September 7 and were completed on October 1, 1990. Subsection 4.1 describes the borehole and monitoring well construction and the collection and analysis of geologic samples. Subsection 4.2 describes the ground water sampling, sample handling, and analytical procedures. Subsection 4.3 summarizes the ground water elevation measurement procedure. Subsection 4.4 describes volatile organic compound screening procedures conducted during the field program. Subsection 4.5 describes disposal procedures for drill cuttings, development water, purge water, and decontamination fluids generated by the field activities. Subsection 4.6 summarizes the decontamination procedures for equipment used during the field activities and the levels of personnel protection used during the field program. Selected photographs documenting various activities conducted during the investigation are presented in Appendix A.

The field program was conducted by IT, which utilized the services of a drilling subcontractor (Mid-Eastern Geotech) and a surveyor (Judge Engineering). To achieve the highly compressed field investigation schedule, IT initiated a 24-hour work schedule on September 7, 1990. Two crews, each consisting of 15 IT and 16 Mid-Eastern Geotech personnel, worked 12-hour shifts to complete the field program during the 28-day work schedule required by the Work Plan. To achieve maximum continuity, the IT crew changed shifts at noon and midnight, whereas the Mid-Eastern crew changed at 8:00 a.m. and 8:00 p.m.

Four drilling rigs were mobilized to the site to complete all the required activities. Three rigs were equipped for cable tool drilling and one was equipped for hollow-stem auger (HSA) drilling. Each rig was manned by a two-person Mid-Eastern Geotech crew and a two-person IT crew. The IT crew consisted of a geologist or engineer, who was responsible for overseeing the drilling operation and assuring compliance with the Work Plan, and a health and safety technician, who was responsible for monitoring the safety of the working conditions. The health and safety technician monitored site conditions by using a photoionization detector (PID) for general screening of VOCs and compound-specific colorimetric tubes for evaluation of several critical contaminants.

In addition, IT and Mid-Eastern Geotech maintained a crew of several people to provide supplies, to decontaminate equipment, and to handle and dispose of drill cuttings and drilling fluids. During most of the field program, a three-man IT ground water sampling crew worked a 12-hour shift each day to collect ground water samples and to prepare associated QA/QC samples. IT also maintained a full-time site coordinator who was present during all field activities. Table 4.1 presents a generalized chronology of the Phase I, Task 4, Field Investigation.

4.1 BOREHOLE CONSTRUCTION, SAMPLING, AND MONITORING WELL INSTALLATION

Eight well clusters consisting of one to five monitoring wells were installed along the boundaries of Areas B and C at the locations shown on Figure 2.3. Three well clusters (CW-1, CW-2, and CW-3) were installed in Area B. In Area C, five well clusters (CW-4, CW-5, CW-6, CW-7 and CW-8) were installed along the western property line. Because the drilling and well installation program were exploratory in nature, the final well network varies somewhat from the program outlined in the Work Plan (IT, 1990). The specifics of the actual well installation program are discussed in the following sections.

TABLE 4.1. Chronology of Activities During the Phase I, Task 4, Field Investigation.

Activity	August	September	October
Mobilization	Aug. 27 [Bar]	Sept. 6 [Bar]	
Well Installation		Sept. 7 [Bar] Sept. 29 [Bar]	
Well Development		Sept. 15 [Bar] Sept. 30 [Bar]	
Ground Water Sampling		Sept. 10 [Bar] Oct. 1 [Bar]	
Water Level Measurements		Oct. 1 [Bar]	
Demobilization		Oct. 1 [Bar] Oct. 5 [Bar]	

4.1.1 Soil Boring Installation

The boreholes and monitoring wells were installed by Mid-Eastern Geotech under direct supervision of the IT site coordinator and field geologist/engineer. In general, borehole construction and monitoring well installation procedures contained in SOPs FP5-1 and FP5-2 were followed during the field investigation. Deviation in actual completion of each borehole and monitoring well from that as outlined in the SAP was caused by 1) unexpected lithologic conditions, such as the presence of bedrock at shallower depths than expected or the presence of non-water-bearing lithologic units (e.g., clay layers); or 2) the presence of VOCs as measured in either drill cuttings or borehole air. Table 4.2 presents a summary of the deviations encountered during drilling and the reasons for the deviations.

Boreholes were constructed with both cable tool and HSA drilling rigs. The HSA type rig was mounted on a four-wheel drive vehicle. 4.25-inch inside diameter (i.d.) HSAs were used to install boreholes that were completed less than 60 feet below grade. Three cable-tool rigs were used to install boreholes that were completed between 85 and 150 feet below grade. A minimum 6-inch-i.d. mild steel casing and drive shoe were used to install boreholes constructed with cable tool rigs.

Soil samples were collected from all boreholes at 5-foot intervals. Boreholes installed with a HSA were sampled with a standard geotechnical split-spoon sampler. Boreholes installed by cable tool methods were sampled by collecting cuttings from the bailer bucket used to evacuate cuttings from the inside of the steel drive casing. These samples were used to create the lithologic logs for each boring contained in Appendix B. Cuttings removed from the boreholes were screened with a PID for VOCs as described in Subsection 4.4. In general, a split-spoon sample was collected from the screened interval of each borehole for grain size analysis (as described in Subsection 4.1.4). Additional split-spoon samples were collected from boreholes to determine the exact locations of clay layers and bedrock. Table 4.3 presents a summary of borehole and well construction information for Phase I, Task 4.

TABLE 4.2. Deviations for Phase I, Task 4, Drilling Program

Cluster ^(a) ID	Actual Well No.	SAP Well No.	Total Drilling Depth (ft)	Proposed Depth (ft)	Reason for Deviation
CW1	CW1-27	CW1-35	27	35	Water table at 17 ft
	CW1-35	CW1-70	35	60-70	Clay layer at 35 ft
	CW1-121	CW1-100	121	90-100	Gravel layer in clay
	CW2-35	CW2-35	35	35	No deviation
CW2	CW2-44	CW2-70	44	60-70	Clay layer at 44 ft
	CW2-90	CW2-100	90	90-100	Gravel layer in clay
	CW3-27	CW3-35	27	35	Water table at 20 ft
	CW3-35	CW3-70	36	60-70	Clay layer at 36 ft
CW3	CW3-77	CW3-100	77	90-100	Gravel layer in clay
	CW4-60	CW4-70	60	50-70	HNu, total VOCs at 50 ft
	CW4-85	CW4-150	85	130-150	Bedrock at 86 ft
	CW5-55	CW5-110	55	90-110	HNu, chloroform at 50 ft
CW5	CW5-85	CW5-150	85	130-150	Bedrock at 104 ft, clay at 85 ft.
	CW6-77	CW6-80	77	70-80	Clay layer at 75 ft
	CW6-X ^(b)	CW6-120	NA ^(c)	100-150	Clay layer at 75, bedrock 104 ft
	CW7-55	CW7-70	55	40-70	HNu, total VOCs at 50 ft
CW7	CW7-100	CW7-110	100	90-110	HNu, total VOCs at 90 ft
	CW7-148	CW7-150	148	130-150	No deviation
	CW8-17	CW8-30	17	20-30	Water table at 9 ft
	CW8-55	None	55	None	HNu, Chloroform at 51 ft
CW8	CW8-85	CW8-70	85	40-70	HNu, total VOCs at 75-80 ft
	CW8-110	CW8-110	110	90-110	No deviation
	CW8-150	CW8-150	150	130-150	No deviation

^(a) Refer to Figure 2.3 for locations of cluster wells.

^(b) Borehole abandoned.

^(c) NA = Not Applicable.

TABLE 4.3. Summary of Well Construction Information for Task 4 Field Investigation^(a)

Well No.	Date Completed	Drilling Method ^(b)	Total Drilling Depth (ft)	Backfill Interval (ft BGS) ^(c)	Total Well Depth (ft)	Filter Pack Interval (ft)	Screen Interval (ft)	Bentonite Seal Interval (ft)	Grout Interval (ft)
CW1-27	09/10/90	HSA	30	27 - 30	27	15 - 27	17 - 27	12 - 15	0 - 12
CW1-35	09/09/90	HSA	44	35.5 - 44	35.5	22.5 - 35.5	25.5 - 35.5	20.5 - 22.5	0 - 20.5
CW1-121 ^(d)	09/26/90	CT ^(e)	150	125 - 150	121	109 - 125	111 - 121	106 - 109	0 - 106
CW2-35	09/10/90	HSA	35	0	35	12.75 - 35	15 - 35	10.75 - 12.75	0 - 10.75
CW2-44	09/12/90	HSA	48	45.75 - 48	45.75	32.25 - 45.75	35.75 - 45.75	30.25 - 32.25	0 - 30.25
CW2-90 ^(e)	09/25/90	CT ^(e)	150	91.5 - 150	90	77 - 91.5	80 - 90	74 - 77	0 - 74
CW3-27	09/11/90	HSA	27	0	27.33	5.33 - 27.33	7.33 - 27.33	3.33 - 5.33	0 - 3.33
CW3-35	09/11/90	HSA	42	36 - 42	35	23 - 36	25 - 35	21 - 23	0 - 21
CW3-77 ^(f)	09/24/90	CT ^(e)	106	81.6 - 106	78.6	64.6 - 81.6	66.8 - 76.8	61.6 - 64.6	0 - 61.6
CW4-60	09/13/90	CT	60	0	59.67	47 - 59.67	49.67 - 59.67	44.2 - 47	0 - 44.2
CW4-85	09/10/90	CT	90	85 - 90	84	72 - 85	74 - 84	69 - 72	0 - 69
CW5-55	09/18/90	CT	104	57 - 104	55	43 - 57	45 - 55	40.5 - 43	0 - 40.5
CW5-85	09/15/90	CT	87	85 - 87	85	73 - 85	75 - 85	70 - 73	0 - 70
CW6-77	09/15/90	CT	90	80 - 90	77	65 - 80	67 - 77	62 - 65	0 - 62
CW6-X ^(g)	09/11/90	CT	104	NA ^(h)	NA	NA	NA	NA	0 - 104
CW7-55	09/14/90	HSA	54	0	54.5	42.5 - 54.75	44.5 - 54.5	39.7 - 42.5	0 - 39.7
CW7-100	09/14/90	CT	100	0	100	88 - 100	90 - 100	85 - 88	0 - 85
CW7-148	09/27/90	CT	148	0	148	136 - 148	138 - 148	133 - 136	0 - 133
CW8-17	09/13/90	HSA	17	0	17.25	5.25 - 17.25	7.25 - 17.25	3 - 5.25	0 - 3
CW8-55	09/18/90	HSA	54	0	54.67	42.4 - 54.67	44.67 - 54.67	38.4 - 42.4	0 - 38.4
CW8-85	09/17/90	CT	85	0	85	73 - 85	75 - 85	70 - 73	0 - 70
CW8-110	09/15/90	CT	110	0	110	97 - 110	100 - 110	94 - 97	0 - 94
CW8-150	09/18/90	CT	150	0	150	138 - 150	140 - 150	135 - 138	0 - 135

^(a) Well construction logs are found in Appendix C.

^(b) CT = Cable Tool; HSA = Hollow-Stem Auger

^(c) BGS = Below Ground Surface

^(d) Double-cased hole. 10 in. casing to 49 ft.

^(e) Double-cased hole. 10 in. casing to 50.5 ft.

^(f) Double-cased hole. 10 in. casing to 42 ft.

^(g) Boring abandoned. Well scheduled to be double-cased. Encountered bedrock directly beneath clay layer.

^(h) NA = Not Applicable

4.1.2 Monitoring Well Construction

Twenty-two ground water monitoring wells were installed in completed boreholes. Wells were constructed of 2-inch-i.d. 304 or 316 stainless steel riser with 10-foot-long or 20-foot-long, 0.010-inch wire-wrapped 316 stainless steel screen. In order to prevent communication between water-bearing zones above and below a clay layer, wells installed below the layer were double-cased with 8-inch-i.d. mild steel.

The well screen and riser were decontaminated per SOP FP3-2 before they were assembled and installed through the HSAs or steel casing. A filter pack consisting of coarse-grained, washed, quartz sand, 3 to 5 times larger than the screen slot, was placed around the screened interval. The pack extended 2 to 3 feet above the top of the screen. A 3-ft.-thick bentonite slurry seal was placed on top of the filter pack in the annular space. The remaining annular space was back-filled with neat portland cement, per SOP FP 5-2. Tremies were used to install the bentonite seal and grout. The filter pack was installed by gravity from the surface. A tremie was also used to grout double-cased wells on both the inside and outside of the 8-inch conductor casing.

The 2-inch stainless steel riser pipe was extended approximately 2 feet above the ground surface. A lockable, 6-inch-i.d., protective steel casing marked with a permanent identification was installed over the riser pipe and cemented in place. A 6-inch-thick, 3-ft. by 3-ft. concrete pad was installed around the protective casing at the ground surface. Three-inch-diameter, concrete-filled, guard posts were installed around the concrete pads.

A geologist or engineer was present during all drilling operations and maintained a detailed boring log and construction log for each well. These logs serve as a record of drilling procedures, lithology encountered, and construction procedures. Boring logs were completed in accordance with SOP FP7-3 contained in Volume 3 of the SAP. Copies of soil boring logs and well construction logs are contained in Appendices B and C respectively.

4.1.3 Borehole and Monitoring Well Abandonment

During the course of the Phase I, Task 4, Field Investigation, it became necessary to abandon three ground water monitoring wells and one borehole.

Two deep ground water monitoring wells at cluster location CW-7 were abandoned prior to completion of well CW7-148. The first well was abandoned because the well was found to be contaminated with grout. The second well was abandoned because the drive casing broke during installation of the well allowing formation materials to collapse around the well. The third abandoned well (the original well CW2-35) was abandoned because the riser pipe was not plumb. The only soil boring abandoned was CW6-X (total depth of 104 feet). During the drilling of this borehole, no water-bearing zone was identified into which a well could be installed. Soil boring and well abandonment were conducted in accordance with the Ohio Administrative Code (OAC) Section 3745-9-10 and SOP FP5-7 of the SAP.

4.1.4 Sample Collection for Grain-Size Analysis

One standard split-spoon sample was collected from the anticipated screened interval of 19 of 22 newly installed wells. Three wells (CW1-35, CW3-35 and CW4-85) were installed at shallower depths than indicated in the Work Plan. As a result, the interval at which the well screen was set was drilled through, without collection of a split-spoon sample for grain-size analysis. Table 4.2 provides additional information on the factors that resulted in this deviation from the Work Plan.

Each sample was submitted to ATEC Associates, Incorporated, in Cincinnati for grain-size distribution analysis. Grain-size data were obtained to verify the visual classification of soils and to provide a general indication of hydraulic conductivity for sediments in the screened intervals.

4.1.5 Well Development

Monitoring wells were developed in accordance with SOP FP5-4. The purpose of development is to remove fine-grained materials (i.e., silt and clay) from the vicinity of the well screen and filter pack, so as to increase the hydraulic communication between the well and the aquifer. The wells were developed by pumping and surging with a centrifugal pump connected to flexible PVC piping. The pump was equipped with a check valve and washers, which were used to seal the annular space firmly between the tubing and the 2-inch-i.d. stainless steel riser and screen. Raising and lowering the flexible pipe across the screen resulted in a simultaneous surging and pumping action. A

bailer was used to check the bottom of the well screen to assure the removal of any sediments that may have settled in that area. Prior to its use, all equipment placed into the well was decontaminated per SOP FP3-1 to prevent cross-contamination between wells. Well development records are contained in Appendix D.

Wells were developed until 1) clear water was produced; 2) sediment load in the development water reached a point of marginal decrease between cycles of surging and pumping; or 3) the development effort had been proceeding for a total of 8 hours. Based on these criteria, seven wells were not developed to a point sufficient to produce nonturbid water based on the criteria in SOP FP5-4. These wells did not achieve a turbidity measurement equal to or below 5 Nephelometric Turbidity Units (NTU) as determined by a nephelometer. Samples were collected from these seven wells and submitted for X-ray diffraction analysis of the sediment as required by SOP FP5-4. Table 4.4 presents a summary of final turbidity measurements and development status for each well. Appendix E contains the laboratory report for the X-ray diffraction analysis conducted on the seven ground water samples. The results indicate a predominance of quartz, calcite, dolomite, and metallic compounds with minimal clay occurrence. Based on the fact that very little clay was identified, and per RCRA Ground Water Monitoring Technical Enforcement Guide protocol (EPA, 1986) the well network is considered valid.

4.1.6 Well Elevation Survey

After completion of the wells, a licensed surveyor, Judge Engineering Company, was subcontracted to survey and determine the horizontal locations and elevations of the 22 newly installed monitoring wells. Surveying was conducted in accordance with SOP FP1-4. A survey transit, data collector, and calibrated steel engineer's tapes were used to conduct the survey. Well elevation survey data for the Phase I, Task 4, Field Investigation are summarized in Table 4.5.

TABLE 4.4. Final Turbidity Measurements and Development Status

Well No.	Final Turbidity Measurment (NTU) ^(a)	Development Status	Further Action As Determined By XRD
CW1-27	10.8	XRD ^(b)	None
CW1-35	18.7	XRD	None
CW1-121	11.3	XRD	None
CW2-35	3.36	Complete ^(c)	---
CW2-44	5.8	XRD	None
CW2-90	49	XRD	None
CW3-27	1.15	Complete	---
CW3-35	1.32	Complete	---
CW3-77	1.91	Complete	---
CW4-60	84.7	XRD	None
CW4-85	NA ^(d)	XRD	None
CW5-55	4.73	Complete	---
CW5-85	4.27	Complete	---
CW6-77	4.72	Complete	---
CW7-55	2.1	Complete	---
CW7-100	4.24	Complete	---
CW7-148	4.3	Complete	---
CW8-17	4.95	Complete	---
CW8-55	3.63	Complete	---
CW8-85	3.09	Complete	---
CW8-110	0.65	Complete	---
CW8-150	3.18	Complete	---

(a) NTU = Nephelometric Turbidity Units

(b) Well requires sampling and X-ray diffraction analysis of sediments.

(c) Well development is complete. No further action is required.

(d) NA = Not Available. Final turbidity measurement not taken at this well.

TABLE 4.5. Well Elevation Survey for Task 4 Field Investigation

Well No.	Top of Protective Casing	Ground Elevation (ft NGVD) ^(a)	Measuring Point Elevation (ft NGVD) ^{(a)(b)}	State Plane Coordinate System	
				North	East
CW1-27	789.86	786.90	789.46	655533.28795	1548178.51765
CW1-35	789.79	787.18	789.38	655539.28354	1548189.57384
CW1-121	789.88	787.18	789.50	655522.61759	1548158.38094
CW2-35	793.63	791.70	793.45	656365.97174	1549567.12411
CW2-44	794.03	791.49	793.72	656373.81400	1549582.16766
CW2-90	793.94	791.58	793.65	656382.86084	1549596.04839
CW3-27	791.62	788.83	791.21	656889.27565	1550744.04304
CW3-35	791.58	788.88	791.20	656896.00759	1550758.46118
CW3-77	791.56	789.14	791.26	656905.11052	1550780.87322
CW4-60	792.37	789.35	792.07	659875.49924	1554831.59062
CW4-85	790.62	788.61	790.08	659891.95580	1554819.52922
CW5-55	794.10	791.17	793.59	660303.89117	1554816.06909
CW5-85	794.35	790.77	793.85	660331.09466	1554805.96780
CW6-77	793.90	790.67	793.32	660560.55981	1554784.76447
CW7-55	792.19	789.69	791.79	661102.11391	1554791.70511
CW7-100	792.05	789.61	791.69	661124.82494	1554794.77929
CW7-148	792.18	790.01	791.78	661148.83885	1554785.01313
CW8-17	788.43	786.17	788.21	661298.82813	1554729.46888
CW8-55	788.30	785.50	787.91	661323.97597	1554720.72342
CW8-85	787.64	785.54	787.47	661314.68414	1554725.69889
CW8-110	786.98	785.06	786.81	661328.69595	1554711.17862
CW8-150	787.01	785.05	786.72	661334.50038	1554697.16621

(a) NGVD = National Geodetic Vertical Datum

(b) Measuring Point is top of 2" stainless steel riser.

4.2 GROUND WATER SAMPLING, SAMPLE HANDLING, AND ANALYTICAL PROCEDURES

All 22 newly installed monitoring wells and 49 existing monitoring and production wells were sampled to determine ground water quality in the area of the Phase I, Task 4, Field Investigation (Figure 2.4). The SAP stated that 53 existing wells would be sampled during the investigation. Four wells (WPAFB production wells A, C, and F and MRWF production well P-41) were not sampled, however, because they were inaccessible during the investigation. In addition, city of Dayton MRWF production wells P-4, P-35, and P-39 were not sampled as they were inoperable. Instead, production wells P-11, P-55, and P-56 were sampled.

All wells were sampled in accordance with SOP FP6-5 during a 21-day period between September 10 and October 1, 1990. Prior to sampling, the new wells were allowed to stabilize for at least 24 hours after development. The following subsections describe well evacuation, ground water sampling, sample preparation, chain-of-custody, and laboratory analyses.

4.2.1 Well Evacuation and Ground Water Sampling

Prior to sampling, pertinent information, including well number, sample identification number, date, time, sampling personnel, and weather conditions, were recorded on Ground Water Sampling Forms. Ground Water Sampling Forms for this field investigation are contained in Appendix F.

Well headspace at all monitoring wells was screened with a PID to determine the presence of VOCs. Headspace screening results for each well were recorded on the Ground Water Sampling Forms included in Appendix F. No VOCs were detected during the headspace screening.

The presence of any floating nonaqueous phase liquid (NAPL) in monitoring wells was determined by removing one bailer of liquid from the top of the well, visually inspecting it, and screening it with a PID to determine if free product was present. The presence of any dense nonaqueous phase liquid (DNAPL) in monitoring wells was determined by dropping a bottom-filling bailer to the bottom of the well, visually inspecting it, and screening it with a PID to determine whether a "sinker" was present. The city of Dayton's HD-series wells (i.e., HD-10 through HD-14) located west of Area C wells could not be examined for NAPLs or DNAPLs due to the presence of dedicated bladder pump

systems and the associated piping and tubing. The presence of any DNAPL or NAPL was not observed in any well examined using these procedures.

Monitoring wells were evacuated by bailing in accordance with SOPs FP5-5 and FP5-6 of the SAP. After each well was purged, pH, temperature, and conductivity measurements were made of fresh samples collected from the well. Results of the field measurements were recorded on Ground Water Sampling Forms (Appendix F). Ground water field measurements for pH, temperature, and conductivity were taken until three consecutive readings were within 0.1 S.U, 0.10°C, and 10 percent, respectively. Evacuation was considered complete when field conditions had stabilized and at least three well volumes had been removed. A thoroughly decontaminated bailer was used for evacuation. One deep well (HR-10) was evacuated with a nonairlift, portable, submersible pump because of the very large quantity of water that had to be removed from the 12-inch well. The well was then sampled with a Teflon bailer. The city of Dayton HD-series monitoring wells were equipped with dedicated pumps that were used to facilitate evacuation and sampling.

Production wells operating at the time of sampling were evacuated by opening the spigot on the well or the discharge line closest to the pump and draining the tap for at least 5 minutes until ground water field measurements (e.g., pH, temperature, and conductivity) stabilized.

Ground water samples were collected from monitoring wells using a bailer, as indicated in SOP FP6-5 of the SAP. Samples were collected from the production wells before any in-line treatment (e.g., activated carbon filter or water softener) was performed by placing sample bottles immediately below the spigot while maintaining flow at the lowest possible rate to minimize potential volatilization. Samples from all wells were collected in order of descending volatility (i.e., the volatiles analysis aliquot was collected first, followed by the aliquot to be analyzed for petroleum hydrocarbons).

Upon collection, all ground water samples were stored in a cooler with ice for subsequent preparation and shipment to the laboratory (see Subsection 4.2.3).

All sampling equipment was decontaminated prior to sample collection at each well in accordance with SOP FP3-1 of the SAP.

4.2.2 Field and Laboratory Quality Assurance/Quality Control (QA/QC)

To check the quality of data from field sampling efforts and laboratory handling, blanks and duplicate samples were collected and submitted to the IT Analytical Services (ITAS) laboratory for analysis. As a means of maintaining their confidentiality, blank and duplicate samples were treated as separate samples during identification, logging, and shipping (see Subsection 4.2.3). Analytical results for blank and duplicate samples were filed together with the appropriate field sample data.

Trip blank samples were used to check for container contamination or contamination from exposure to airborne or ambient contaminants during travel. Trip blanks consisted of VOC vials filled with organic-free water at the laboratory and shipped with empty sample containers to the project site. One trip blank sample per cooler accompanied VOC vials into the field throughout the sampling effort and was submitted to the lab with the samples collected for that day. The trip blank sample remained unopened until the time of analysis. One cooler and, therefore, one trip blank per daily shipment was prepared. Trip blanks were analyzed for TCL VOCs.

Field or equipment blanks were prepared to determine whether decontamination procedures were effective in cleaning sampling equipment. The sampling equipment was thoroughly decontaminated in accordance with procedures outlined in SOP FP3-1 of the SAP. The sampling device was then rinsed with clean deionized/distilled water. This water was collected in appropriate sample containers for laboratory analysis for TCL VOCs. One field blank was prepared each day the sampling team was at the site.

Duplicate or split samples were collected to evaluate the precision of both the sample collection and analytical procedures. One duplicate sample was collected for every 10 environmental samples collected at the site (10% duplicate sampling rate) and analyzed for the same parameters as the original sample. A total of 7 duplicates were prepared for this investigation.

Routine QC analytical procedures included the use of a method blank, matrix spike (MS), and matrix spike duplicate (MSD). The method blank is used to assess possible contamination resulting from the analytical process. Per Contract Laboratory Program (CLP) protocol, MS and MSD analysis was conducted

at a rate of one MS/MSD pair per 20 samples (5% MS/MSD sampling rate). An additional sample was collected for each MS/MSD pair. This field sample was split at the laboratory and spiked to determine the accuracy and precision of the laboratory analytical procedure. Table 4.6 lists the laboratory QA objectives for MS/MSD and surrogate spike samples.

The laboratory adds surrogates to a sample to assess the accuracy of the laboratory analysis. As shown in Table 4.7, reported surrogate recovery was outside of method acceptance limits for only six samples. All but two exceedences were for 1,2-dichloroethane. One surrogate (CW3-27/0927/01) exceeded method acceptance limits for toluene, and one surrogate (CW8-85/0924/01) exceeded method acceptance limits for bromofluorobenzene. A method or matrix effect was confirmed when five of the six samples were reanalyzed. Because of insufficient sample volume, CW3-27/0927/01 was not reanalyzed; therefore, a method or matrix effect could not be confirmed for this sample.

4.2.3 Sample Identification, Labeling, Preparation and Shipping

4.2.3.1 Sample Identification and Labeling

All sample containers were marked for identification from the time of collection. Sample identification included project name, sample number, collection date/time, collector's name, sample location, sample type, analysis, and preservation.

4.2.3.2 Sample Nomenclature System

A sample nomenclature system was used by field personnel to permit easy identification of the sample type and sample location during the retrieval of data, the review of analytical results, or the manipulation of data. The nomenclature selected for this project consists of three unique alphanumeric or numeric codes separated by slashes.

Samples from existing wells were identified by using the well names assigned by the contractor who installed the wells; however, modifiers such as the sampling date code and the sample purpose code were added by the sampling crew. Upon receipt of the samples for analysis, the ITAS Laboratory

TABLE 4.6. Quality Control Limits for Volatile Organic Compounds

Matrix Spike/Matrix Spike Duplicate		
<u>Matrix Spike Compound</u>	<u>% Recovery</u>	Relative Percent <u>Difference</u>
1,1-dichloroethene	61-145	14
trichloroethene	71-120	14
chlorobenzene	75-130	13
toluene	76-125	13
benzene	76-127	11
Surrogates		
<u>Surrogate Compound</u>	<u>% Recovery</u>	
toluene - d8	88-110	
bromofluorobenzene	86-115	
1,2-dichloroethane-d4	76-114	

TABLE 4.7. Surrogate Samples That Exceeded Method Acceptance Limits

Sample ID	Surrogate Recovery, Percent		
	D4-1,2-Dichloroethane	D8-Toluene	P-Bromofluoro Benzene
CW8-85/0924/01	119 ^(a)	NA ^(b)	NA
CW8-85/0924/01 (Reanalysis 1)	125 ^(a)	NA	83 ^(a)
CW8-110/0924/01	156 ^(a)	NA	NA
CW8-110/0924/01 (Reanalysis 1)	115 ^(a)	NA	NA
CW8-110/0924/01 (Reanalysis 2)	121 ^(a)	NA	NA
19-564-M/0913/01	72 ^(a)	NA	NA
19-564-M/0913/01 (Reanalysis 1)	75 ^(a)	NA	NA
19-564-M/0913/04	69 ^(a)	NA	NA
19-564-M/0913/04 (Reanalysis 1)	71 ^(a)	NA	NA
HD-14S/0919/03	49 ^(a)	NA	NA
HD-14S/0919/03 (Reanalysis 1)	131 ^(a)	NA	NA
CW3-27/0927/01	NA	111 ^(c)	NA

^(a) Surrogates outside of method acceptance limits; reanalysis confirmed a method effect.

^(b) NA = Not Applicable.

^(c) Surrogates outside of method acceptance limits; insufficient sample for reanalysis.

assigned a different unique alphanumeric code for the sample to maintain the confidentiality of the sample.

4.2.3.2.1 Well Identification. The first alphanumeric series of the sample nomenclature indicates the well being sampled. For example, CW1-121 indicates that the sample was collected from the 121-foot-deep well at cluster location CW-1; and MR-110S indicates the sample was from an existing well.

4.2.3.2.2 Sampling Date. The second series of the sample nomenclature indicates the date the sample was collected. For example, CW1-121/0930 indicates that a ground water sample was collected from the 121-foot-deep well at well cluster location CW-1 on September 30.

4.2.3.2.3 Sample Purpose. The third series of the sample nomenclature indicates the purpose of the sample. For example, CW1-121/0930/01 indicates the sample is the original or actual sample collected for the study, whereas CW1-121/0930/05 is the MS aliquot collected from the 121-foot-deep well at cluster location CW-1. Each sample type collected during the sampling program is identified by the following two-digit alpha codes:

- 01 - Actual Data Sample
- 02 - Field Duplicate
- 03 - Trip Blanks
- 04 - Equipment Blanks
- 05 - Matrix Spike
- 06 - Matrix Spike Duplicate

4.2.3.3 Sample Preparation

As each sample was collected in the field, it was placed in a labeled sample bottle with appropriate preservatives and stored in an iced cooler as stipulated in SOP FP6-7 in the SAP. Chain-of-Custody and Request-for-Analysis documents were prepared for all samples shipped to the laboratory. Sample containers and appropriate preservatives used during this field investigation are presented in Table 4.8. Samples requiring preservation were preserved in the field; the appropriate reagents were supplied by the analytical laboratory. Sample bottles such as I-Chem Protocol A, purchased precleaned in accordance with U. S. EPA specifications, were provided by the laboratory.

TABLE 4.8. Water Sampling Specifications

Parameter	Container ^(a)	Sample Preservation	Holding Time
Volatile Organic Compounds	Two 40-ml glass vials, no headspace	HCl to pH<2 Using 3 drops HCl Immediately After Sampling Ice to 4°C	Analyze in 14 days
Total Petroleum Hydrocarbons	Low - Two 40-ml glass vials High - Two 2-gallon brown glass bottles	Ice to 4°C	28 days
Metals and Hardness (Na, Ca, Fe, Mg, Mn, K)	1 liter plastic bottle	HNO ₃ to pH<2 Ice to 4°C	6 months
Anions, TDS, Alkalinity, and pH	1 liter plastic bottle	Ice to 4°C	28 days for chlorides and sulfates 7 days for TDS 14 days for alkalinity pH test required immediately upon collection
TOC	1 liter brown glass	H ₂ SO ₄ to pH<2 Ice to 4°C	28 days

^(a)All containers have Teflon lined lids (Septa for VOAs) and are EPA approved.

4.2.3.4 Storage and Shipping

The sealed sample containers were picked up and delivered to the laboratory by a representative of the ITAS laboratory in Cincinnati. Samples were prepared for shipment by the following procedures:

- Sample bottle lids were hand-tightened. Custody tape was placed over the lid and sample label.
- About 3 inches of packing material was placed in the bottom of a waterproof cooler.
- Bottles were sealed in clear plastic bags and placed in a cooler to prevent contact with each other.
- Ice was placed in plastic bags and arranged in the cooler on and around the bottles.
- The remaining space of the cooler was filled with packing material.
- Paperwork was placed in plastic bags and taped to the inside of the cooler lid.
- The cooler drain was taped shut.
- The cooler lid was secured by taping completely around the outside with strapping tape at two locations.
- The analytical laboratory address was placed on top of the cooler. "This Side Up" labels were placed on all four sides of the cooler and "Fragile" labels were placed on at least two sides of the cooler.
- Custody seals were affixed on the front right and back left corners of the cooler. Wide clear tape was used to cover seals as appropriate.

All samples were preserved and shipped on the day they were collected. New sample containers and the trip blanks were delivered to the site at the time of sample pickup (about 7:00 p.m.).

4.2.4 Chain-of-Custody Procedures

Documentation of the sample chain-of-custody was provided by the use of chain-of-custody forms that record the sampling location, the type and amount of sample collected, the date and time of sample collection, the signature(s) of the person(s) responsible for sample collection, and the date, time, and

signatures of all custody transfers. Chain-of-custody procedures document sample possession from the time of collection to disposal. Chain-of-custody records for this investigation are included in Appendix G.

4.2.4.1 Sample Collection Logs

Sample collection logs were filled out for each ground water sample in order to record information pertaining to the location, condition, and collection of field samples. The following information was documented on the field sample collection report form:

- Date and time sample collected
- Field engineer/scientist responsible for sample collection
- Sample identification number
- Field testing results of pH, temperature, specific conductance
- Weather conditions
- Water-level depth collected, if monitoring well
- General field observations

Ground water sampling forms completed for this field investigation are included in Appendix F.

4.2.4.2 Request-for-Analysis

Laboratory Request-for-Analysis forms were filled out to indicate the testing program required for the collected samples. The following pertinent information was recorded on the laboratory Request-for-Analysis forms:

- Project name and number
- Date samples shipped and the carrier
- Required report date and turnaround times for analysis
- Contact (with telephone number) for receipt of the analytical report and billing invoices
- Sample identification numbers
- Sample volume collected and appropriate preservatives
- Requested analysis and laboratory methods

Laboratory Request-For-Analysis forms completed for this investigation are included in Appendix G.

4.2.5 Laboratory Analysis

All ground water samples, field equipment blank samples, and MS/MSD samples were analyzed for TCL VOCs by the most recent CLP Special Analytical Services (SAS) Scope of Work Methods (Table 4.9). TPH samples were extracted and analyzed by the Gas Chromatography with Flame Ionization Detection (GC/FID) method described in the California Leaking Underground Fuel Tank (LUFT) Field Manual - Guidelines for Site Assessments, Cleanup, and Underground Storage Tank Closure. Due to poor recoveries obtained using LUFT extraction procedures, SW-846 extraction procedures were used for those samples listed in Table 4.10. This approach allowed for a more aggressive extraction of these samples to overcome matrix interference problems, and provided for more accurate data.

Ground water samples were collected from three new monitoring wells in Area B (CW2-35, CW2-44, and CW2-90) and three new monitoring wells in Area C (CW8-17, CW8-55, and CW8-150) for general ground water quality analyses to assist in the evaluation of above-ground treatment facilities. Each sample collected from these wells was analyzed for metals (calcium, sodium, iron, potassium, magnesium, and manganese), anions (chloride and sulfate), hardness, alkalinity, TDS, pH, and TOC. Because of an oversight by field and analytical personnel, these samples were not analyzed for carbonate and bicarbonate as specified in the SAP.

ITAS SOPs for laboratory equipment calibration, sample preparation, analyses, and decontamination are found in Appendix B of the SAP (IT 1990).

4.3 WATER LEVEL MEASUREMENTS

One round of ground water elevation measurements was performed on October 1, 1990 according to SOP FP7-2 of the SAP. Water levels were taken with a clean electronic water level indicator to obtain a nearly instantaneous picture of the ground water flow conditions. Water levels were taken at 69 monitoring wells instead of 72 as indicated in the SAP (Figure 2.5). Water levels could not be measured at wells MR-106D, MR-113S, and MR-120D due to the presence of dedicated pumps installed in the wells which altered the true depth-to-water.

TABLE 4.9. Summary of Methods and QC Requirements

Parameter	Method	Analysis Aliquot ^(a)	Preservation	Detection Limit	Holding Time	Precision (RPD)	Accuracy (% Recovery)
<u>Volatile Organics</u>							
Water	Current CLP-SAS SOW Exhibit D (modified)	25 ml	Cool to 4°C HCl to pH<2		Analyze in 14 Days (<24 Hours on Site)	See Table 4.6 ^(b)	See Table 4.6 ^(b)
Acetone				2 µg/L			
Benzene				1 µg/L			
Bromodichloromethane				1 µg/L			
Bromoform				1 µg/L			
Bromomethane				2 µg/L			
2-Butanone				1 µg/L			
Carbon disulfide				1 µg/L			
Carbon tetrachloride				1 µg/L			
Chlorobenzene				1 µg/L			
Chloroform				2 µg/L			
Chloroethane				2 µg/L			
Chloromethane				1 µg/L			
Cis-1,3-dichloropropane				1 µg/L			
Dibromochloromethane				1 µg/L			
1,1-Dichloroethane				1 µg/L			
1,1-Dichloroethene				1 µg/L			
1,2-Dichloroethane				1 µg/L			
1,2-Dichloroethene				1 µg/L			
1,2-Dichloropropane				1 µg/L			
Ethylbenzene				2 µg/L			
2-Hexanone				2 µg/L			
4-Methyl-2-pentanone				1 µg/L			
Methylene chloride				1 µg/L			
Styrene				1 µg/L			
Tetrachloroethene				1 µg/L			
1,1,2,2-Tetrachloroethane				1 µg/L			
Toluene				1 µg/L			
Trans-1,3-dichloropropane				1 µg/L			
1,1,1-Trichloroethane				1 µg/L			
1,1,2-Trichloroethane				1 µg/L			
Trichloroethene				1 µg/L			
Vinyl acetate				1 µg/L			
Vinyl chloride				1 µg/L			
Xylenes				1 µg/L			

TABLE 4.9. (cont.)

Parameter	Method	Analysis Aliquot ^(a)	Preservation	Detection Limit	Holding Time	Precision (RPD)	Accuracy (% Recovery)
<u>Total Petroleum Hydrocarbons</u>							
Water	GC/FID ^(c)	1 L	Cool to 4°C	50 µg/L ^(d)	Extract in 14 days; Analyze in 40 days	20	40-160
High Boilers					Analyze in 14 days	20	40-160
Low Boilers		5 ml		50 µg/L			
<u>Metals</u>							
Water	Current		HNO ₃ to pH<2	5,000 µg/L	6 months	20	75-125
Sodium	CLP SOW	100 ml		5,000 µg/L	6 months	20	75-125
Calcium	200.7 CLP-M	100 ml		100 µg/L	6 months	20	75-125
Iron	200.7 CLP-M	100 ml		5,000 µg/L	6 months	20	75-125
Magnesium	200.7 CLP-M	100 ml		15 µg/L	6 months	20	75-125
Manganese	200.7 CLP-M	100 ml		5,000 µg/L	6 months	20	75-125
Potassium	200.7 CLP-M	100 ml				20	75-125
<u>Anions</u>							
Water	9252	50 ml	Cool to 4°C	0.5 mg/L	Analyze in 28 days	20	75-125
Chlorides	9038	25 ml		2 mg/L	Analyze in 28 days	20	75-125
Sulfates	310.1	50 ml		1 mg/L	Analyze in 14 days	20	80-120 ^(e)
Carbonate	310.1	50 ml		1 mg/L	Analyze in 14 days	20	80-120 ^(e)
Bicarbonate							
<u>Others</u>							
Water	130.2	50 ml	HNO ₃ to pH<2	1 mg/L	6 months	20	80-120 ^(e)
Hardness	160.1	100 ml	Cool to 4°C	2 mg/L	Analyze in 7 days	20	80-120 ^(e)
TDS	310.1	50 ml	Cool to 4°C	1 mg/L	Analyze in 14 days	20	80-120 ^(e)
Alkalinity	150.1	25 ml	Cool to 4°C	NA ^(f)	Immediately	20	NA
pH			Cool to 4°C				
TOC	9060	25 ml	Cool to 4°C	3 mg/L	Analyze in 28 days	20	75-125

^(a) Amount used for single analysis, not amount collected.^(b) Representative compounds were used for spikes.^(c) Reference from California, Leaking Underground Fuel Tank Field Manual - Guidelines for Site Assessments, Cleanup and Underground Storage Tank Closure, Section 3, Appendix B.^(d) 500 µg/L for lubricating oils.^(e) For these parameters, blank spikes were used to assess accuracy.^(f) NA = Not Applicable

TABLE 4.10. TPH Samples Which Were Not Extracted by LUFT Method

<u>Sample ID</u>	<u>Analytical Method^(a)</u>	
	<u>Extraction</u>	<u>Analysis</u>
PHC-HI ^(b)		
CW1-27/0929/01	SW-846	LUFT
CW1-35/0929/01	SW-846	LUFT
CW1-35/0929/02	SW-846	LUFT
CW1-27/0929/04	SW-846	LUFT
CW3-27/0927/03	SW-846	LUFT
CW3-27/0927/01	SW-846	LUFT
CW3-27/0927/02	SW-846	LUFT
CW3-35/0927/01	SW-846	LUFT
CW3-35/0927/04	SW-846	LUFT
PHC-LO ^(b)		
CW3-77/0928/03	SW-846	LUFT
CW3-77/0928/01	SW-846	LUFT
CW3-77/0928/04	SW-846	LUFT
P-19/0928/01	SW-846	LUFT
P-25/0928/01	SW-846	LUFT
P-37/0928/01	SW-846	LUFT

^(a) LUFT refers to the California Leaking Underground Fuel Tank Field Manual Method. SW-846 refers to procedures in U.S. EPA Test Methods for Evaluating Solid Waste, Volume II, Field Manual.

^(b) PHC-HI and PHC-LO are equivalent to TPH.

The probe of the water-level indicator was decontaminated between its use at each well by the procedures described in SOP FP3-1 of the SAP. Water-level measurements were recorded in the field notebooks. Table 4.11 presents a summary of water-level measurements and calculated water elevations obtained during the Phase I, Task 4, Field Investigation.

4.4 VOC SCREENING ACTIVITIES DURING THE FIELD PROGRAM

Portable photoionization instruments were used to screen air quality in the breathing zone during the drilling program, the well head and samples during ground water sampling, and cuttings and water removed from the boreholes during borehole construction. The purpose of the screening was twofold. The first purpose was to determine if VOCs were present (i.e., any concentration above 0.0 ppm) in the breathing zone at borehole locations and ground water monitoring wells to assure that personnel were not exposed to contaminants during drilling and sampling activities. The second purpose of the VOC monitoring was to screen drill cuttings to determine their proper disposal.

If VOCs were detected during the screening with the PID, specific compound analytical testing with colorimetric tube air samplers was performed to determine the type and approximate concentration of the compound responsible for the PID reading. Colorimetric tubes for perchloroethylene, 1,1,1 trichloroethane, chloroform, trichloroethylene, 1,1 dichloroethane, 1,2 dichloroethane, and vinyl chloride were used when required. These compounds were selected as representative of the major contaminants potentially present at the site.

All VOC measurements were recorded in field notebooks by a member of the IT field team assigned to the monitoring task at each drilling location, or by a member of the ground water sampling team. The data recorded in the notebooks are compiled on PID and compound-specific colorimetric tube Field Screening Logs presented in Appendix H.

The PID was calibrated as specified in SOP FP2-2. The HSP specified 11.7-eV lamps for the PID (IT 1990), however, because an insufficient number of 11.7-eV lamps was available from the supplier at the initiation of the

TABLE 4.11. Water Level Measurements
(October 1, 1990)

Well No. ^(a)	Depth-To-Water (ft) ^(b)	Reference Elevation (ft, NGVD) ^(c)	Water Elevation (ft, NGVD) ^(d)
08-522-M	8.50	793.90	785.40
08-523-M	6.10	791.30	785.20
08-524-M	6.35	790.80	784.45
08-525-M	9.70	792.60	782.90
08-526-M	11.66	791.50	779.84
08-527-M	10.19	789.90	779.71
08-528-M	11.80	791.30	779.50
09-529-M	9.65	797.20	787.55
09-530-M	6.35	795.20	788.85
09-531-M	6.68	794.60	787.92
18-559-M	24.60	784.00	759.40
18-560-M	36.99	785.80	748.81
18-561-M	27.25	786.60	759.35
19-564-M	24.70	795.40	770.70
MW-20	12.05	791.12	779.07
MW-21	11.80	791.00	779.20
MW-22	16.10	796.24	780.14
MW-23	6.60	791.94	785.34
MW-24	9.85	796.24	786.39
CW1-27	24.33	789.46	765.13
CW1-35	24.20	789.38	765.18
CW1-121	36.50	789.50	753.00
CW2-35	26.55	793.45	766.90
CW2-44	26.70	793.72	767.02
CW2-90	36.70	793.65	756.95
CW3-27	22.22	791.21	768.99
CW3-35	22.10	791.20	769.10
CW3-77	22.05	791.26	769.21
CW4-60	13.35	792.07	778.72
CW4-85	11.32	790.08	778.76
CW5-55	14.68	793.59	778.91
CW5-85	14.65	793.85	779.20
CW6-77	14.20	793.32	779.12
CW7-55	9.70	791.79	782.09
CW7-100	9.00	791.69	782.69
CW7-148	10.31	791.78	781.47
CW8-17	10.50	788.21	777.71
CW8-55	9.95	787.91	777.96
CW8-85	9.15	787.47	778.32
CW8-110	8.85	786.81	777.96
CW8-150	9.95	786.72	776.77
HW-2D	25.68	785.54	759.86
HW-2	27.02	786.77	759.75
HW-19D	24.60	784.71	760.11
HW-19S	24.65	784.86	760.21

TABLE 4.11. (cont.)

Well No. ^(a)	Depth-To-Water (ft) ^(b)	Reference Elevation (ft, NGVD) ^(c)	Water Elevation (ft, NGVD) ^(d)
MR-106S	20.03	775.84	756.81
MR-106D	NA ^(e)	776.50	NA ^(e)
MR-107S	16.40	780.45	764.05
MR-108S	10.57	785.06	774.49
MR-108D	33.67	785.47	751.80
MR-109S	12.18	783.75	771.57
MR-110S	30.61	799.65	769.04
MR-111S	24.51	791.87	767.36
MR-112S	27.10	787.07	759.97
MR-112D	29.90	786.64	756.74
MR-113S	NA ^(e)	785.74	NA ^(e)
MR-114S	14.97	769.15	754.18
MR-114D	28.98	770.23	741.25
MR-120S	15.57	779.96	764.39
MR-120D	NA ^(e)	779.38	NA ^(e)
HD-10D	14.67	793.24 ^(f)	778.57
HD-11	13.18	791.86 ^(f)	778.68
HD-12S	12.74	791.56 ^(f)	778.82
HD-12M	13.57	792.46 ^(f)	778.89
HD-13S	10.94	789.55 ^(f)	778.61
HD-13D	11.78	790.34 ^(f)	778.56
HD-14S	13.30	790.94 ^(f)	777.64
HR-2	22.05	797.82 ^(g)	775.77
HR-10	14.40	790.29 ^(g)	775.89
HR-20	14.53	790.27 ^(g)	775.74
HR-30	14.92	790.29 ^(g)	775.37
HR-40	15.28	790.23 ^(g)	774.95

(a) Figure 2.5 is a map showing locations of monitoring wells where water levels were measured.

(b) Depth-to-water measured with an M-scope.

(c) Reference elevation for depth-to-water is top of casing unless noted otherwise.

(d) Water elevation is calculated by subtracting depth to water from the reference elevation.

(e) NA=Not Available. Water levels could not be measured at these wells due to the presence of dedicated pumps installed in the wells that altered the true depth-to-water.

(f) Reference elevation for these wells is approximate.

(g) Reference elevation is top of 6-inch pipe on top of well.

field program, instruments equipped with 10.2-eV lamps were used until 11.7-eV lamps could be substituted as they became available. Use of 11.7-eV lamps for the PID was required by the HSP to accurately quantify chloroform which has an ionization potential (IP) of 11.42-eV. A 10.2-eV lamp, however, was sufficient to create a qualitative response in the presence of chloroform. In order to compensate for the use of 10.2-eV lamps, the action level for using compound-specific colorimetric tubes was decreased from the HSP directed action level of 5 ppm total VOCs to any quantifiable response by the PID. By reducing the action level and thus increasing the frequency of compound-specific colorimetric tube usage, the potential for personnel exposure was minimized.

4.4.1 Air Monitoring During Drilling Activities

The two specific objectives of the air monitoring program during drilling activities were as follows:

1. To determine if VOCs were present in the breathing zone or in the borehole during drilling activities.
2. To screen the cuttings and fluids derived from the borehole to determine proper disposal.

During drilling, regular periodic measurements were taken of air quality in the breathing zone and borehole to assure that on-site personnel were not exposed to unacceptable levels of VOCs escaping from the subsurface via the borehole. If a detectable concentration of VOCs was measured during this monitoring, compound-specific colorimetric tube readings were taken to determine which compound(s) were responsible for the concentration measured with the PID. Any detectable reading by the PID during the drilling triggered the upgrading of personal protection for drilling crews at that location. Upgrading of personal protection is discussed in Subsection 4.6. Borehole air measurements were also used to select screen settings for monitoring wells installed at the well cluster.

Table 4.12 presents a summary of all detected ambient air measurements recorded during the drilling program. Detected PID readings for total VOCs ranged between 0.02 and 8.03 ppm with both the 10.2-eV and 11.7-eV lamps. No

TABLE 4.12. Air Monitoring During Borehole Construction

Well No.	Date	Measured	Air Measuring Device	Measuring Location/Material	Compound Measured	Concentration (ppm)
CW2-35	09/20/90	PID 11.7 ^(a)		Borehole ^(d)	Volatile organics ^(e)	1
CW2-44	09/11/90	PID 10.2 ^(b)		Borehole	Volatile organics	0.5
				Borehole	Volatile organics	1
CW3-77	09/20/90	PID 11.7		Borehole	Volatile organics	0.2
	09/22/90	CSC ^(c) Tube		Borehole	Chloroform	1
CW4-60	09/11/90	PID 10.2		Borehole	Volatile organics	1
CW4-85	09/08/90	PID 10.2		Borehole	Volatile organics	6
				Borehole	Volatile organics	1
				Breathing zone	Volatile organics	0.02
				Borehole	Volatile organics	8.03
				Borehole	Volatile organics	0.03
				Breathing zone	Volatile organics	0.02
				Borehole	Volatile organics	0.02
				Borehole	Volatile organics	0.03
CW8-55	09/18/90	PID 11.7		Background	Volatile organics	0.5
				Borehole	Volatile organics	1.5
				Background	Volatile organics	0.5
				Borehole	Volatile organics	1.0
				Background	Volatile organics	0.5
				Borehole	Volatile organics	1.5
			CSC Tube	Borehole	Chloroform	3
				Background	Chloroform	2
CW8-85	09/15/90	CSC Tube		Borehole	Chloroform	3
				Borehole	Chloroform	2
	09/16/90	CSC Tube		Breathing zone	Chloroform	2
				Breathing zone	Chloroform	4
				Breathing zone	Chloroform	4
				Breathing zone	Chloroform	4
				Breathing zone	Chloroform	2
CW8-110	09/12/90	PID 10.2		Borehole	Volatile organics	8
CW8-150	09/07/90	PID 10.2		Breathing zone	Volatile organics	0.2
				Background	Volatile organics	3
	09/08/90	PID 10.2		Background	Volatile organics	0.2
				Background	Volatile organics	0.2
				Breathing zone	Volatile organics	0.2
				Borehole	Volatile organics	1

^(a) 11.7-eV lamp on the Photoionization detector (PID).

^(b) 10.2-eV lamp on the PID.

^(c) Compound-specific colorimetric (CSC) tubes.

^(d) Air collected from the top of the drill casing at the ground surface.

^(e) Total volatile organic compounds.

PID VOC measurement exceeded 1.0 ppm in the breathing zone, and when recorded, background concentrations ranged between 0.5 and 1.0 ppm. The highest concentration measured (8.03 ppm) was present in the borehole constructed for monitoring well CW4-85. Compound-specific colorimetric tube sampling for specific compounds detected only chloroform in concentrations ranging between 1 and 4 ppm. On several occasions the level of chloroform in air briefly reached 4.0 ppm in the breathing zone during the installation of CW8-85. No other specific VOCs were detected during the air monitoring activities.

4.4.2 Screening of Borehole Cuttings and Water

Substantial volumes of cuttings and water were generated during soil boring construction. These cuttings and fluids (water) were containerized in steel drums upon their removal from the hole. A lid was placed on each drum and the contents were allowed to set for 15 to 20 minutes. During this period, any volatiles in the cutting materials were permitted to volatilize into the headspace of the drum. The VOC screening was conducted in the drum headspace via a small threaded port in the top of each drum lid. If a detectable quantity of VOCs (i.e., any measurable concentration) was determined to be present, the cuttings were transferred to a roll-off box for offsite disposal. If no detectable quantity of VOCs (i.e., PID reading of 0.0 ppm) was determined to be present, the cuttings were spread on the ground at the borehole site. All water derived from drilling operations (regardless of PID readings) was containerized for ultimate disposal. Subsection 4.5 presents a detailed description of borehole cuttings and fluid disposal. Detection of VOC concentrations in borehole cuttings triggered an increase in the level of personal protection at the drilling site, as outlined in Subsection 4.6.

Table 4.13 summarizes the detected VOC readings derived from analyzing the headspace of drums containing cuttings and drilling fluids. Total concentrations of VOCs ranged from 0.2 ppm for cuttings from the borehole at well CW5-85 to 28 ppm for cuttings from the borehole at well CW8-150. Chloroform was quantified in concentrations ranging from 2.0 to 3.0 ppm. Vinyl chloride was quantified at CW2-35 at 0.2 ppm.

TABLE 4.13. Headspace Screening of Cuttings from Borehole Construction

Well No.	Date Measured	Air Measuring Device	Compound Measured	Concentration (ppm)
CW1-35	09/08/90	PID 10.2 ^(a)	Volatile organics ^(d)	6
CW2-35	09/20/90	PID 11.7 ^(b)	Volatile organics	4
			Volatile organics	6.2
		CSC Tube	Chloroform	2
			Vinyl Chloride	0.2
CW2-35	09/10/90	PID 10.2	Volatile organics	2
CW3-77	09/20/90	PID 11.7	Volatile organics	0.2
		CSC Tube	Chloroform	2
		CSC Tube	Chloroform	2
		CSC Tube	Chloroform	2.5
	09/22/90	CSC Tube	Chloroform	3
CW4-85	09/08/90	PID 10.2	Volatile organics	1
			Volatile organics	0.03
CW5-85	09/13/90	PID 10.2	Volatile organics	0.2
			Volatile organics	0.2
CW8-85	09/16/90	CSC Tube	Chloroform	2
CW8-110	09/11/90	PID 10.2	Volatile organics	22
CW8-150	09/07/90	PID 10.2	Volatile organics	2
	09/08/90	PID 10.2	Volatile organics	22
			Volatile organics	28
			Volatile organics	7
			Volatile organics	2
			Volatile organics	4
	09/09/90	PID 10.2	Volatile organics	10
			Volatile organics	1

^(a) 10.2-eV lamp on the Photoionization detector (PID).

^(b) 11.7-eV lamp on the PID.

^(c) Compound-specific colorimetric (CSC) tube.

^(d) Total volatile organic compounds.

4.5 DISPOSAL OF DRILL CUTTINGS AND FLUIDS

All fluids generated during the field investigation (specifically ground water from boreholes during drilling, ground water from well development activities, and water derived from decontamination of sampling equipment) was containerized and sampled to determine proper disposal. Cuttings determined to contain VOCs as indicated in Subsection 4.4.2 were transferred from the drums used to perform the headspace screening to covered 20 cubic yard roll-off boxes. Subsection 4.5.1 describes the procedures for the handling, analysis, and disposal of all fluids generated during the drilling program. Subsection 4.5.2 describes the procedures for the handling and disposal of drill cuttings determined to be potentially hazardous.

4.5.1 Handling and Disposal of Fluids Generated During the Field Investigation

Ground water generated during borehole construction was transferred from drums staged adjacent to the drilling rig to small 500-gallon polypropylene tanks mounted on pickup trucks. Soap and water from steam cleaning at the decontamination pads and ground water derived from well development and purging was also transferred from the drums staged at each unit to the same truck-mounted tanks.

Once these fluids were loaded into the pickup-mounted tanks, they were transported to a central location adjacent to Building 899 (the horse stables) on Battle Creek Road in Area A and transferred to two 5,000-gallon polypropylene tanks. This storage location was selected because it is centrally located with respect to drilling activities in both Areas B and C, and is also adjacent to a permitted sewer-discharge point at the Base. Additional storage capacity in two 8,000-gallon tanks at Landfill 8 was used when capacity was exceeded at the tanks adjacent to Building 899. Approximately 18,000 gallons of fluid was collected during this investigation.

Conditions of WPAFB's sewer discharge permit required that fluids placed into the permitted discharge point be analyzed and that the city of Dayton be notified prior to a release. A sample representative of the contents of both tanks at Building 899 was collected and analyzed for parameters on U.S. EPA's Priority Pollutant Volatile and Semivolatile Organic Compound List. Wastewater analytical results are presented in Appendix I and summarized in

Table 4.14. The analytical results indicated that the water did not exceed the permitted discharge level of 2.13 ppm as Total Toxic Organics. The city of Dayton was notified and permission was granted to discharge the contents of the tanks to the sewer.

Potable water used for drilling and decontamination was supplied by the Base water supply system through use of a fire hydrant along Friar Circle in Area C. The water was transported to each point of usage in a tank truck provided by the drilling subcontractor. As required by the SAP, a sample of the water used for these purposes was collected from the water truck and analyzed for the same constituents as the Field Program. Analytical results for this sampling are contained in Appendix I and summarized in Table 4.15.

4.5.2 Handling and Disposal of Cuttings Generated During Borehole Construction

All drill cuttings generated from borehole construction were transferred from either the cuttings bailer on cable tool rigs or shoveled from the ground surface adjacent to the hollow-stem augers to drums for screening (as described in Subsection 4.4.2). Cuttings determined to contain VOCs were transferred to lined roll-off boxes (one roll-off box each was located in the immediate vicinity of drilling in Areas B and C). The tops of the boxes were covered with tarps to isolate their contents. Barricade fencing was placed around each box to prevent tampering. The roll-off boxes were turned over to the Base Project Manager for sampling and disposal of the contents.

4.6 PERSONAL PROTECTION AND DECONTAMINATION OF EQUIPMENT

The basic level of personal protection used during the field program was Level D, as described in the HSP (IT 1990). Upgrading of personal protection was triggered by the VOC screening procedures outlined in Subsection 4.4.

Equipment and materials used to construct and sample monitoring wells were decontaminated in accordance with SOPs FP3-1, FP3-2, and FP3-3 of the SAP.

TABLE 4.14. Summary of Wastewater Analyses^(a)

Sample No.	Chemical Parameter	Concentration ^(b) μg/L
Wastewater		
WST-01/0918/01	Trichloroethylene	8.0
	Di-n-butyl phthalate	2.0 JB
	Bis(2-ethylhexyl) phthalate	5.0 J
Method Blanks		
SBLK971	Di-n-butyl phthalate	2.0 J

^(a) Appendix H contains the analytical reports for wastewater samples.

^(b) A "J" code is used to indicate an estimated value; the compound was found to be present but the result is less than the specified detection limit.

TABLE 4.15. Summary of Water Truck Analyses^(a)

Sample No.	Chemical Parameter	Concentration ^(b) μg/L
Water Truck		
WT/0917/01	Methylene chloride	8.4 B
	Carbon disulfide	0.9 JB
	Chloroform	0.4 JB
	Bromodichloromethane	0.9 J
	Dibromochloromethane	2.2
	Bromoform	2.7
	Toluene	0.5 JB
	Styrene	0.2 JB
	Total xylenes	0.5 JB
Method Blanks		
VBLKA9	Chloroform	0.3 J
VBLKB6	Methylene chloride	4.1
	Carbon disulfide	0.3 J
	1,2-Dichloroethylene	0.5 J
	1,1,1-Trichloroethane	0.3 J
	Benzene	0.2 J
	Toluene	0.5 J
	Styrene	0.6 J
	Total xylenes	0.8 J
Trip Blank		
WT/0917/03	Methylene chloride	2.1B

^(a) Appendix H contains the analytical reports for water truck samples.

^(b) A "J" code is used to indicate an estimated value; the compound was found to be present but the result is less than the specified detection limit. A "B" code is used to indicate that the analyte was found in the blank as well as the sample indicating possible blank contamination.

4.6.1 Personal Protection

In general, all work activities for this investigation, including soil boring and monitoring well installation, well development, and soil and ground water sampling, were conducted in Level D protection. Level D protection was utilized under the following scenarios: 1) direct reading instruments (i.e., an PID) and specific compound devices (i.e., compound-specific colorimetric tubes) indicated levels at or below background levels in the breathing zone; and 2) splashes, immersion, or potential for inhalation of any chemicals were not expected to be encountered.

Several instances occurred during the Phase I, Task 4, Field Investigation when personal protective equipment was upgraded to Level D-Plus, which required mandatory use of rubber or PVC gloves, disposable latex or rubber outer boots, and disposable polycoated Tyvek coveralls in addition to the standard protective equipment required for Level D. Use of Level D-Plus was implemented when direct reading instruments indicated any concentration of VOCs above background conditions in either ambient air, borehole air, or cuttings. Table 4.16 presents a summary of personal protection used. Each borehole was considered an independent activity requiring independent evaluation of personnel protection requirements. As can be noted on Table 4.16 differing levels of protection are evident within a specific well cluster. It should also be noted that the table indicates an upgrade to D-Plus without indicating that the upgrade may not have occurred until a substantial amount of drilling was completed. Upgrading from Level D to Level D-Plus was never determined to be necessary during ground water sampling activities.

When VOC concentrations were detected by the PID, personnel were not allowed to continue to work in the area until the cause for the reading was determined with a direct measuring device (i.e. compound-specific colorimetric tubes). Representative tubes (e.g., chloroform, trichloroethylene, perchloroethylene, and vinyl chloride) reflecting the range of contaminant types anticipated were used to identify the type of chemical threat presented. The determination was documented on the PID and compound-specific colorimetric tube Field Screening Logs (Appendix H).

TABLE 4.16. Summary of Personal Protection Levels
Donned During Drilling Program

Monitoring Well/Soil Boring No.	Personal Protection Level
CW1-27	D
CW1-35	D-Plus
CW1-121	D
CW2-35	D-Plus
CW2-44	D
CW2-90	D-Plus
CW3-27	D
CW3-35	D
CW3-77	D-Plus
CW4-60	D-Plus
CW4-85	D-Plus
CW5-55	D-Plus
CW5-85	D
CW6-77	D
CW7-55	D
CW7-100	D
CW7-148	D
CW8-17	D-Plus
CW8-55	D-Plus
CW8-85	D-Plus
CW8-110	D-Plus
CW8-150	D-Plus

As specified in the HSP, personnel working within the Exclusion Zone were required to pass through a decontamination station to remove their protective equipment and clothing before being allowed to enter the uncontaminated support areas of the job site (IT, 1990). Protective equipment was placed in plastic trash bags for disposal. Used protective clothing was disposed of in accordance with applicable State and Federal regulations.

4.6.2 Equipment Decontamination

Two decontamination pads, one located in Area B between cluster well locations CW-2 and CW-3 and the other located north of CW-8 in Area C, were used during the Phase I, Task 4, Field Investigation to decontaminate equipment such as augers, mild steel casings, and drilling rigs and tools. The first stage of decontamination for stainless steel riser pipes and screens was also performed on these pads. The decontamination pads were comprised of framing lumber and plywood configured into a platform and sloped to a box sump. The surface of the pads was lined with heavy-gauge plastic. Submersible sump pumps were placed in the sump portion of each pad. These pumps transferred liquids to steel drums where they were held for pickup by larger truck-mounted tanks (as discussed in Subsection 4.5). Portable hot-water pressure washers (steam generators) and nonphosphate detergent were used to decontaminate drilling equipment, stainless steel riser pipe, and screen. All personnel operating decontamination equipment wore Level D-Plus protection.

Sampling equipment and water level-measurement devices were decontaminated (as directed in SOP FP3-1) at a third decontamination pad adjacent to the pad north of CW-8 in Area C. This pad was used to segregate more potentially hazardous decontamination solutions, (i.e., hexane, dilute nitric acid, and methanol) to keep them from being put in the bulk water handling system.

5.0 SUMMARY OF HYDROGEOLOGIC RESULTS

5.1 SITE GEOLOGY

As described in Subsection 3.5, the geology in the vicinity of WPAFB consists of Ordovician and Silurian Age limestones and shales unconformably overlain by Pleistocene and Recent Age sediments. Pleistocene Age glacially derived sediments consist of glacial till deposited directly by ice movement and fluvial-glacial sediments deposited and reworked by waters melting from retreating ice. The eroded surface of the carbonate and shale bedrock in the immediate area of the Base forms several steep, partially buried troughs. Glacially derived fluvial-glacial sediments fill the deepest part of the troughs, and glacial till forms a thin blanket along the higher elevations of the bedrock surface except in a few areas where bedrock is exposed as outcrops. Recent Age sediments consisting of alluvium derived from the Mad River and lesser tributaries form a thin blanket in floodplain areas adjacent to rivers and streams.

During this Phase I, Task 4, Field Investigation, soil borings were installed in and through the unconsolidated sediments at eight locations beneath the area of investigation at WPAFB. These borings were installed to a maximum depth of 150 feet. Lithologic descriptions of material collected during construction of each boring (Appendix B) provide information regarding the geologic conditions of the site. These new data supplement the body of knowledge previously available concerning the geologic setting beneath WPAFB. The following subsections present a discussion of geologic conditions as identified during this investigation. Subsection 5.1.1 focuses on the data obtained during the drilling program in Area C, whereas Subsection 5.1.2 concentrates on the data obtained during the installation of soil borings in Area B.

5.1.1 Geology in Area C

Previously available information concerning the subsurface conditions beneath Area C along the perimeter of WPAFB suggested that the geologic sequence consisted of a layer of unconsolidated fluvial-glacial sand and gravel ranging in thickness from 150 to 250 feet (Norris and Spieker, 1966;

Walton and Scudder, 1960). These materials were deposited on and immediately overlie northerly sloping shale and limestone bedrock. Information from several of the city of Dayton's borings (HD-series wells) constructed along the fenced boundary between WPAFB and the MCD property suggested that a "boulder zone" was present at approximately 100 feet below grade. The vertical and horizontal extent of this "boulder zone" was unknown.

During the Phase I, Task 4, Field Investigation, 13 soil borings were constructed at five locations (CW-4, CW-5, CW-6, CW-7, and CW-8) along the Area C boundary (Figure 2.3 shows locations). At each cluster location, the deepest borings, which extend to depths ranging between 90 and 150 feet below grade, provide the most detailed description of geologic conditions in this area.

Plate 5.1 presents a north-south geologic cross section of Area C based on the lithologic descriptions in the logs for the newly constructed soil borings. The cross section illustrates a northerly sloping bedrock surface overlain by fluvial-glacial deposits of sand and gravel. As is characteristic of fluvial-glacial deposits, the distribution of sediments is highly variable and sand and gravel are predominant in the area. Some lenses of sand and gravel contained a relatively greater volume of silty clay, and lenses of larger sediments, such as coarse gravels with cobbles of up to 6 inches in diameter, were also encountered. All borings encountered a thin (approximately 10 foot thick) surface layer of Recent Age silt at the surface.

Shale bedrock was encountered during drilling and was confirmed by collection of split-spoon samples at three of the five cluster locations (CW-4, CW-5, CW-6) at depths ranging from 88 to 104 feet below grade. A 5- to 20-foot thick layer of clay-till or weathered bedrock was encountered in these borings just above the bedrock surface. Bedrock was not encountered in boreholes installed to the maximum drilling depth of 150 feet required by this investigation at cluster locations CW-7 and CW-8.

Previously available data suggested that the bedrock beneath all drilling locations in Area C was deeper than 150 feet below grade. Recently installed city of Dayton monitoring wells installed (HD-13D, HD-11, and HD-12M) at locations adjacent to cluster well locations CW-4, CW-5, and CW-6

indicated a "boulder zone" at approximately 100 feet below grade. Based on the discovery of bedrock at similar depths at cluster locations CW-4, CW-5, and CW-6, the HC-series wells may not be terminated in a "boulder zone" but actually are terminated in bedrock. The depth to bedrock at locations CW-7 and CW-8 cannot be determined based on data collected during this investigation. Plate 5.1 is therefore interpretive in these areas.

5.1.2 Geology in Area B

Previously available information on subsurface conditions beneath Area B along Springfield Pike indicated that the lithologic sequence consisted of a 50- to 60-foot-thick layer of fluvial-glacial gravel underlain by a 10- to 15-foot-thick layer of glacial silts and clays (Norris and Spieker, 1966; Geraghty & Miller, 1987). A fluvial-glacial sand and gravel layer was also thought to be present beneath the silt and clay, and the thickness of this deposit may be 100 feet or more. These materials were deposited on and immediately overlie a southwesterly plunging shale and limestone bedrock surface. Information found during the soil boring activities of Phase I, Task 4 provides a different geologic interpretation.

As shown in Figure 2.3, nine soil borings were constructed at three locations (CW-1, CW-2, and CW-3) along the Area B boundary. At each cluster location the deepest borings, which reached depths ranging between 106 and 150 feet below grade, provide the most detailed description of geologic conditions.

Plate 5.1 presents an east-west geologic cross section along the Area B boundary, which was constructed using the soil boring logs from the Phase I, Task 4, Field Investigation and the lithologic logs for several other borings located along this boundary. All new borings encountered an upper layer of fluvial-glacial sand and gravel underlain by a thick layer of heterogeneous silty clay with gravel inclusions. Thin layers (less than 10 feet thick) of fluvial-glacial sand and gravel were encountered within the silty clay sequence. The abundance of gravel in the silty clay suggests a glacial till.

The upper sand and gravel unit encountered in the three new well clusters is about half as thick as originally expected (i.e., 35 to 40 feet instead of 60 to 70 feet). The silty clay layer, however, is much thicker

than previously reported (up to 100 feet or more). This layer of silty clay with gravel continues downward to bedrock (at a depth of 103 feet below grade at location CW-3) or to the maximum depth of the borings (150 feet) at locations CW-1 and CW-2.

5.1.3 Bedrock Configuration

The depth to bedrock beneath some portion of Area C of WPAFB is significantly less than previously reported. Published data (Walton and Scudder, 1960) representing the study area indicated that bedrock should occur at approximately 200 feet below grade at each boring location in Area C. Bedrock was encountered at 87 feet below grade in boring CW4-85, at 104 feet below grade in boring CW5-85, and at 103 feet below grade in boring CW6-77.

Bedrock was not encountered at the maximum drilling depth of 150 feet at cluster well locations CW-7 and CW-8. Bedrock was encountered at boring CW-3 in Area B at 103 feet below grade. Borings at CW-1 and CW-2 did not encounter bedrock at the maximum drilling depth of 150 feet.

5.2 SITE HYDROGEOLOGY

Information available prior to completion of this investigation concerning the hydrogeologic setting of the Mad River Valley Aquifer indicated that there may be two major flow regimes present within the aquifer. The first system, which includes the water table and has an average thickness of 50 feet, consists of fine-grained materials such as silts, lenses of sand and occasional coarse gravel. The second system, ranging in thickness from 10 feet to over 100 feet, consists of layers of coarse sand and gravel. The two flow systems are separated by a 10- to 55-foot-thick layer of silty clay. The layer of silty clay separating the aquifer was considered a leaky confining layer which would represent a hydraulic separation of the two flow regimes. Ongoing hydrogeologic studies being conducted by the U.S. Geological Survey (USGS) suggest, however, that the confining layer may not be present beneath Area C (DeRoche, 1990).

Previously available data indicated that ground water flow in the aquifer is southwesterly, parallel to the Mad River. At the Mad River and its tributaries ground water flow directions in the upper portion of the aquifer

would be affected by recharge to or discharge from the surface water bodies. Ground water flow direction would also be affected by the presence of operating production wells.

For a better assessment of the hydrogeologic conditions along the boundaries of Area C and Area B along Springfield Pike, 22 ground water monitoring wells were installed during the Phase I, Task 4, Field Investigation. These new monitoring wells were installed as well clusters to investigate conditions from the water table to a maximum depth of 150 feet below grade. Ground water elevations were also determined at 47 existing wells.

For better illustration of the results of the Phase I, Task 4, Field Program, ground water contour maps and vertical gradient cross sections have been prepared using the hydrogeologic data generated during the study. Subsection 5.2.1 focuses on the hydrogeologic setting of Area C, and Subsection 5.2.2 focuses on the hydrogeologic setting in Area B. Subsection 5.2.3 presents the ground water flow regimes for the entire study area.

5.2.1 Hydrogeologic Setting in Area C

The hydrogeologic setting of Area C presented as a vertical geological cross section (Plate 5.2) consists primarily of fluvial-glacial sand and gravel overlying shale bedrock. No extensive layers of silty clay or other fine-grained materials were encountered that would represent a laterally continuous confining layer separating the aquifer into easily identifiable flow regimes. Aquifer heterogeneity, however, will result in locally discontinuous flow systems. Data collected during this investigation does not permit identification of this "micro-structure" and thus the aquifer can be represented as a single hydrogeologic unit.

Previously, the saturated thickness of the Mad River Valley Aquifer was reported to be 100 to 200 feet thick in this area. In as much as bedrock was encountered at three of the five cluster locations (CW-4, CW-5, and CW-6) in Area C, observed saturated thicknesses, of the aquifer are as little as 50 to 75 feet in the vicinity of cluster locations CW-4, CW-5 and CW-6.

The water level data collected on October 1, 1990 from the 13 new monitoring wells and three existing wells (MW-20, MW-21, and 08-525-M) along the Area C boundary are plotted as a cross section (Plate 5.2) and on a more

stylized vertical depiction (Plate 5.3). These data show that there is little difference in water levels with depth in the aquifer. Differences that are observed reflect local permeability variations and potentially transient water level changes. These data indicate that the aquifer at Area C is best represented as a single flow system. The presence of multiple flow systems at other locations cannot be judged from these data.

5.2.2 Hydrogeologic Setting in Area B

The hydrogeologic setting at the Springfield Pike boundary of Area B is presented as a geologic cross section on Plate 5.2. An upper layer of predominantly fluvial-glacial sand and gravel (approximately 35 feet thick) is identified overlying a thick (greater than 100 feet) layer of silty clay till with thin (10 feet or less) isolated sand or sand and gravel lenses. In the immediate area of the Phase I, Task 4, Field Investigation, the till extends to bedrock or to the maximum depth of investigation (i.e., 150 feet). To the west, and specifically at wells MR-112D, P-14 and MR-114D, the till layer thins and a deeper layer of sand and gravel is reported.

The till identified during this investigation probably represents a confining layer separating the Mad River Valley Aquifer into two or more flow regimes. The thickness and extent of the lower flow regime cannot be determined from the newly acquired data.

The extent and continuity of the thin layers of sand and gravel encountered in the till at CW-1, CW-2, and CW-3 are unknown.

The water level data collected on October 1, 1990, from the nine new monitoring wells and existing wells MR-112D and MR-114D were used to create a vertical cross section (Plate 5.2) and a schematic cross section (Plate 5.3). Both plates suggest a downward gradient. The gradient observed may be influenced by pumping of the Rohrer's Island Well Field, but data collected during this investigation are not sufficient to fully determine this.

5.2.3 Ground Water Contour Maps

Plate 5.4 depicts water-table elevations from wells screened across the water table. Table 4.11 contains all of the water level elevations measured during the investigation. In general, the water-table mirrors the topography

of the fluvial-glacial valley fill. Regionally, the gradient of the water table is southwesterly, parallel to the valley trend. The data collected on October 1, 1990 are not sufficient to indicate the specific relationships between the Mad River and the water table. The water level data suggest but do not confirm that ground water is discharging to the river east of Huffman Dam, but that the Mad River is discharging to ground water west of the dam.

The Phase I, Task 4, investigation did not provide a sufficient quantity of data to prepare a potentiometric map for any flow regimes deeper than the water table. The available data suggest a southwesterly flow in the deeper flow regimes from Area C and a northwesterly flow from Area B. These observations are consistent with historical data (Geraghty & Miller, 1987).

5.3 HYDRAULICS

In the context of this report the term hydraulics will address the hydraulic conductivity, transmissivity, and flow regime of the Mad River Valley Aquifer in the study area. During this limited investigation, no efforts were made to determine other hydraulic properties such as storativity, leakance, recharge rates, or surface water/ground water interconnectedness.

5.3.1 Hydraulic Conductivity

As the scope of this investigation did not provide for completion of slug tests or controlled pumping tests to determine hydraulic conductivity, soil samples were collected from the screened interval of 19 monitoring wells to allow assessment of hydraulic conductivity using grain-size distribution. The samples were submitted to ATEC Associates, Inc., for grain-size distribution analysis by American Society for Testing and Materials (ASTM) Method 421-85. Grain-size distribution data are presented in Appendix J.

The Holtz and Kovacs application of the Hazen formula was used to calculate the approximate hydraulic conductivity of the samples (Holtz and Kovacs, 1981). The Hazen formula is an empirical formula curve-matching procedure relating conductivity to the effective grain size. While the formula is most applicable to clean sands with less than 5 percent of the sample passing a No. 200 sieve it is adequate for this program to estimate hydraulic

conductivity. Table 5.1 presents the results of the Hazen formula calculations.

In general, the calculated hydraulic conductivity ranged between 5×10^{-3} cm/s and 1×10^{-1} cm/s and 106 to 2,118 gpd/ft². The arithmetic mean hydraulic conductivity for the collected soil samples is 5×10^{-2} cm/s (1,059 gpd/ft²). These values appear to be consistent with values presented in previous investigations (Weston, 1989; Geraghty & Miller, 1987).

5.3.2 Transmissivity

A critical criterion for the design of ground water withdrawal systems is the determination of aquifer transmissivity. This hydraulic measurement is usually determined via controlled pumping tests, but it can only be estimated for this study because no pumping tests were conducted. Transmissivity measures the quantity of water passing through the saturated thickness of the aquifer; therefore, the value can be calculated by multiplying hydraulic conductivity by measured saturated thickness.

As indicated in Subsection 5.1, this field investigation did not identify the thick fluvial-glacial deposits previously reported to be present in the areas of study. In fact, at the locations of cluster wells CW-1, CW-2, CW-3, CW-4, CW-5, and CW-6, the aquifer's saturated thickness is about half of that predicted. Since measured hydraulic conductivity is about as expected, aquifer transmissivity is half of that expected.

5.3.3 Flow Systems

Water level data collected from 69 new and existing monitoring wells provide insight into the ground water flow system of the Mad River Valley Aquifer. As previously reported, the Mad River Valley Aquifer is complex relative to movement of water within the aquifer.

Ground water in the Mad River Valley Aquifer flows both laterally and vertically under the influence of natural and artificial controls. Plate 5.4 presents the configuration of the water table in the study area and shows the basic flow pattern as determined on October 1, 1990.

Vertical flow sections (Plates 5.2 and 5.3) indicate that hydraulic head pressures at all depths in Area C are about equal indicating only lateral

TABLE 5.1. Estimated Hydraulic Conductivity for Collected Soil Samples

Well No.	Depth Interval (ft BGS) ^(a)	Hydraulic Conductivity (cm/s) ^(b)
CW1-27	24-25.5	0.02
CW1-121	113-115	0.09
CW2-35	20-22	0.4
CW2-44	33.75-35.75	0.005
CW2-90	76-77	0.005
CW3-27	20-21.5	0.005
CW3-77	75-77	0.005
CW4-60	50-52	0.1
CW5-55	50	0.04
CW5-85	75-76.5	0.03
CW6-77	70-75	0.02
CW7-55	49-51	0.01
CW7-100	93-95	0.02
CW7-148	145-147	0.005
CW8-17	15-17	0.04
CW8-55	50-52	0.03
CW8-85	80-81	0.02
CW8-110	100-101.5	0.005
CW8-150	145-147	0.1

(a) BGS = Below Ground Surface.

(b) Hydraulic conductivity calculated by applying the Hazen formula to grain size distribution analysis performed on material samples collected from the screened interval of each monitoring well (Holtz and Kovacs, 1981).

ground water flow. In Area B hydraulic heads are highest at the water table indicating a potential for vertically downward flow. The condition observed in Area B may be artificially caused by pumping at the Rohrer's Island Wellfield.

6.0 SUMMARY OF WATER QUALITY DATA

6.1 GROUND WATER ANALYTICAL RESULTS

During the Phase I, Task 4, Field Investigation, samples from 22 newly installed wells, 35 existing monitoring wells, and 14 existing production wells were collected for chemical analysis. Table 2.2 lists the analytical parameters for this investigation. All ground water samples were analyzed for 35 VOCs and for TPH (detected as high or low boilers). For engineering purposes, samples were collected from six new monitoring wells in Areas B and C for analysis of 13 general ground water quality parameters. The following is an overview of ground water analytical results for both inorganic and organic parameters analyzed. The set of analytical parameters is not all inclusive; therefore, the presence or absence of other constituents in ground water should not be inferred.

6.1.1 Inorganics

To assist in the evaluation of pre-treatment facilities for any removal action, ground water samples were collected from six new monitoring wells (CW2-35, CW2-44, CW2-90, CW8-17, CW8-55, and CW8-150) and were analyzed for six metals (calcium, iron, magnesium, manganese, potassium, and sodium), two anions (chloride and sulfate), and five water quality indicators (alkalinity, hardness, pH, TDS, and TOC). Table 6.1 summarizes the analytical results for these inorganic parameters.

These data are not intended to quantify or define the lateral or vertical distribution of inorganic constituents in the ground water at WPAFB. As such, no conclusions should be drawn from these data concerning the inorganic chemistry of ground water in the Mad River Valley Aquifer.

As shown on Table 6.1, the concentration of metals in the six samples ranges from 123 to 647 mg/L for calcium, 5.87 to 234 mg/L for iron, 42 to 279 mg/L for magnesium, 0.18 to 4.41 mg/L for manganese, 2.31 to 18.2 mg/L for potassium, and 7.22 to 37 mg/L for sodium. It should be noted that the results of analysis of the sample from well CW2-35 are conspicuously out of line with the other samples. The cause of this condition cannot be determined at this time.

TABLE 6.1. Summary of Inorganic Results for Ground Water Samples

Parameter (a)	Detection Limit (b)	Sample ID (e)						
		CW2-35/0929/01	CW2-44/0929/01	CW2-90/0929/01	CW8-17/0924/01	CW8-55/0924/01	CW8-150/0924/01	
Calcium	0.001	647	117	146	211	123	126	
Iron	0.012	234	5.97	20.6	29.8	6.98	6.51	
Magnesium	0.002	279	45.4	54	69.6	42	49.9	
Manganese	0.002	4.41	0.18	0.44	2.12	0.227	0.234	
Potassium	0.9	18.2	3.7	5.82	2.58	2.31	3.69	
Sodium	0.034	32.1	37	31.1	17.4	14.8	7.22	
Chloride	0.5 - 0.6	47	59	67	34	39	30	
Sulfate	0.44 - 0.5	780	76	39	190	120	95	
Alkalinity	0.74 - 0.8	22.9	350	420	620	360	420	
pH	NA (c)	7.14	7.21	7.63	7.12	7.22	7.41	
TDS	2	520	520	460	530	530	440	
TOC	7.4	31.1	ND (d)	14.3	17.6	10.9	13.1	
Hardness	<0.5 - 1	2650	480	600	312	467	513	

(a) All units are reported in mg/L except pH, which is reported in Standard Units (S.U.).

(b) In some cases, two different detection limits are applicable to the analyses; a range is listed to reflect this situation.

(c) NA = Not Applicable.

(d) ND = Not Detected.

(e) Sample identification "CW2-35" refers to well number; "/0929" refers to date sampled; "/01" refers to environmental sample.

Concentrations of chloride and sulfate ranged from 30 to 67 mg/L and 39 to 780 mg/L respectively. The highest concentration of chloride was detected in the sample from well CW2-90 and the highest concentration of sulfate was detected in the sample from well CW2-35.

The data in Table 6.1 show that general water quality indicators (alkalinity, hardness, pH, TDS, and TOC) vary considerably among wells. The six samples range in concentration from 22.9 to 620 mg/L for alkalinity, 312 to 2,650 mg/L for hardness, 440 to 530 mg/L for TDS, and nondetectable to 31.1 mg/L for TOC. The range in pH is from 7.12 to 7.63. The inorganic data represent water that is hard to very hard and contains large amounts of iron and scaling materials that may adversely affect some water-treatment equipment.

6.1.2 Organics

Eighteen of 35 VOCs analyzed for were detected in one or more ground water samples. Table 6.2 contains a summary of the ground water analytical results for this investigation. Laboratory reports are contained in Appendix K. Associated QA/QC data (i.e., trip blanks, equipment blanks, and method blanks) for all VOC analyses are summarized in Tables 6.3 and 6.4. Trip blank and equipment blank QA/QC data are arranged by date sampled, date analyzed, and sample number for each parameter. Method blank QA/QC data are arranged by date analyzed and sample number for each parameter.

Analytical results are sometimes designated by the laboratory with a code. A "J" flag is used to indicate an estimated value; that is, the compound was identified to be present in the sample, but the level is less than the specified detection limit. A "B" flag is used by the laboratory to indicate that the analyte was found in the laboratory method blank as well as in the environmental sample. Detection in the sample may indicate contamination caused by the laboratory's handling of the sample.

Ground water sampling results for the common laboratory contaminants methylene chloride, acetone, and carbon disulfide, were validated according to accepted OEPA procedure. That is, if the amount in the sample is less than 10 times the detection limit (DL) then the concentration is considered to be attributable to laboratory contamination. Data which meet this validation

TABLE 6.2. Summary of VOC Results for Ground Water Samples

Chemical Parameter ^(a) (µg/L)									
Well No. ^(a)	Sample ID	Date Sampled	Date Analyzed	Methylene chloride	Acetone	Carbon disulfide	1,2-Dichloro- ethylene	Trichloro- ethylene	Perchloro- ethylene
				D.L.=1	D.L.=2	D.L.=1	D.L.=1	D.L.=1	D.L.=1
WPAFB Monitoring Wells									
08-523-M	08-523-M/0911/01	09/11/90	09/13/90	0.3 JB ^(d)	0.7 J ^(d)	ND	ND	ND	ND
08-524-M	08-524-M/0911/01	09/11/90	09/13/90	0.2 JB ^(d)	0.3 J ^(d)	ND	ND	ND	ND
08-525-M	08-525-M/0911/01	09/11/90	09/13/90	0.6 JB ^(d)	ND	ND	ND	ND	ND
08-528-M	08-528-M/0913/01	09/13/90	09/20/90	1.1 ^(d)	ND	ND	ND	0.3 J	3.3
09-530-M	09-530-M/0910/01	09/10/90	09/12/90	0.52 JB ^(d)	ND	ND	ND	ND	ND
09-530-M DUP ^(c)	09-530-M/0910/02	09/10/90	09/12/90	0.56 JB ^(d)	ND	ND	ND	ND	ND
18-559-M	18-559-M/0912/01	09/12/90	09/13/90	0.2 JB ^(d)	ND	ND	ND	ND	ND
18-560-M	18-560-M/0912/01	09/12/90	09/13/90	0.3 JB ^(d)	ND	ND	ND	0.4 J	ND
19-564-M	19-564-M/0913/01	09/13/90	09/20/90	0.4 J ^(d)	ND	ND	ND	0.1 J	0.3 J
MW-20	MW-20/0911/01	09/11/90	09/13/90	0.4 JB ^(d)	ND	ND	ND	ND	0.3 J
MW-20 DUP	MW-20/0910/01	09/10/90	09/12/90	0.6 JB ^(d)	ND	ND	ND	ND	0.3 J
MW-21	MW-21/0911/01	09/11/90	09/13/90	0.31 JB ^(d)	ND	ND	7.0	18	3.3
MW-22	MW-22/0911/01	09/11/90	09/13/90	ND	ND	1.0 ^(d)	2.1	ND	ND
MW-23	MW-23/0911/01	09/11/90	09/13/90	0.3 JB ^(d)	0.4 J ^(d)	ND	ND	ND	ND
CW1-27	CW1-27/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	3.8	ND
CW1-35	CW1-35/0929/01	09/29/90	10/07/90	ND	ND	0.8 J ^(d)	ND	2.5	ND
CW2-35	CW2-35/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	2.2	ND
CW2-44	CW2-44/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	2.4	ND
CW3-27	CW3-27/0927/01	09/27/90	10/07/90	0.4 J ^(d)	ND	ND	ND	2.8	ND
CW3-27 DUP	CW3-27/0927/02	09/27/90	10/06/90	6.4 B ^(d)	ND	ND	ND	0.7 J	ND
CW3-35	CW3-35/0927/01	09/27/90	10/06/90	ND	ND	ND	0.3 J	0.8 J	ND
CW3-77	CW3-77/0928/01	09/28/90	10/06/90	2.3 B ^(d)	ND	ND	5.1	9.7	0.1 J
CW4-60	CW4-60/0921/01	09/21/90	10/09/90	8.5 B ^(d)	ND	ND	0.3 J	ND	ND
CW4-85	CW4-85/0921/01	09/21/90	09/27/90	2.9 B ^(d)	ND	0.3 J ^(d)	8.9 B	ND	ND
CW5-55	CW5-55/0926/01	09/26/90	09/27/90	3.2 B ^(d)	ND	ND	41	550	ND
CW5-85	CW5-85/0926/01	09/26/90	10/06/90	7.5 B ^(d)	ND	ND	40	770	ND
CW6-77	CW6-77/0925/01	09/25/90	10/06/90	7.0 B ^(d)	ND	ND	1.3	6.2	ND
CW7-55	CW7-55/0925/01	09/25/90	10/02/90	0.5 JB ^(d)	ND	ND	ND	ND	ND
CW7-100	CW7-100/0925/01	09/25/90	10/02/90	2.9 B ^(d)	ND	ND	ND	ND	ND
CW8-17	CW8-17/0924/01	09/24/90	09/30/90	0.5 JB ^(d)	ND	ND	ND	ND	ND
WPAFB Production Wells									
P-1	P-1/0913/01	09/13/90	09/20/90	ND	ND	ND	ND	2.6	ND
P-2	P-2/0913/01	09/13/90	09/20/90	0.2 J ^(d)	ND	ND	0.2 J	4.5	ND
P-5	P-5/0913/01	09/13/90	09/20/90	ND	ND	ND	2.3	1.0	ND
City of Dayton									
Monitoring Wells									
MR-109S	MR-109S/0919/01	09/19/90	09/25/90	1.3 B ^(d)	ND	ND	3.2	4.7	1.4
MR-109S DUP	MR-109S/0919/02	09/19/90	09/21/90	1.7 ^(d)	ND	ND	4.0	6.9	1.9
MR-110S	MR-110S/0920/01	09/20/90	09/27/90	5.2 B ^(d)	ND	ND	5.3	0.8 J	ND
MR-111S	MR-111S/0920/01	09/20/90	09/27/90	5.4 B ^(d)	ND	ND	0.3 J	4.8	ND

TABLE 6.2. (cont.)

Well No. (a)	Sample ID	Date Sampled	Date Analyzed	Chemical Parameter (µg/L)					
				Methylene chloride D.L.=1	Acetone D.L.=2	Carbon disulfide D.L.=1	1,2-Dichloro-ethylene D.L.=1	Trichloro-ethylene D.L.=1	Perchloro-ethylene D.L.=1
MR-112S	MR-112S/0919/01	09/19/90	09/25/90	1.9 B ^(a)	ND	0.6 J ^(a)	ND	ND	0.3 J
MR-112C	MR-112C/0920/01	09/20/90	09/26/90	4.8 B ^(a)	ND	0.3 J ^(a)	ND	ND	ND
MR-113S	MR-113S/0920/01	09/20/90	09/27/90	5.1 B ^(a)	ND	2.6 ^(a)	ND	ND	ND
HD-100	HD-100/0918/01	09/18/90	09/25/90	ND	5.1 ^(a)	ND	ND	ND	ND
HD-11	HD-11/0918/01	09/18/90	09/26/90	4.1 B ^(a)	ND	0.6 J ^(a)	21	600	ND
HD-12S	HD-12S/0918/01	09/18/90	09/25/90	4.6 B ^(a)	ND	0.7 JB ^(a)	ND	1.0	62
HD-12M	HD-12M/0918/01	09/18/90	09/25/90	ND	ND	ND	ND	9.1	ND
HD-13S	HD-13S/0918/01	09/18/90	09/26/90	2.8 B ^(a)	ND	0.5 J ^(a)	63	35	ND
HD-130	HD-130/0918/01	09/18/90	09/21/90	0.9 J ^(a)	ND	ND	24	ND	ND
HD-14S	HD-14S/0919/01	09/19/90	09/25/90	1.6 B ^(a)	ND	0.4 J ^(a)	73	ND	ND
City of Dayton									
Production Wells									
P-11	P-11/1001/01	10/01/90	10/07/90	0.4 J ^(a)	ND	ND	ND	ND	ND
P-14	P-14/0924/01	09/24/90	09/27/90	3.4 B ^(a)	ND	ND	ND	ND	ND
P-14 DUP	P-14/0924/02	09/24/90	09/30/90	ND	ND	ND	ND	0.1 J	ND
P-15	P-15/0926/01	09/26/90	10/08/90	9.2 ^(a)	ND	ND	ND	ND	ND
P-19	P-19/0928/01	09/28/90	10/06/90	8.6 B ^(a)	ND	ND	ND	ND	ND
P-25	P-25/0928/01	09/28/90	10/06/90	8 B ^(a)	ND	ND	ND	ND	ND
P-37	P-37/0928/01	09/28/90	10/06/90	2 B ^(a)	ND	ND	ND	ND	ND
P-56	P-56/0926/01	09/26/90	10/04/90	7.8 B ^(a)	ND	ND	ND	ND	ND
P-57	P-57/0924/01	09/24/90	09/30/90	ND	ND	ND	0.3 J	0.4 J	ND
P-58	P-58/0926/01	09/26/90	10/04/90	6.8 B ^(a)	ND	ND	0.5 J	1.2	ND
MCD Monitoring Wells									
MR-10	MR-10/0921/01	09/21/90	09/27/90	1.7 B ^(a)	ND	ND	10	4.4	0.8 J
GR-50	GR-50/0918/01	09/18/90	09/25/90	ND	ND	ND	1.9	1.4	ND
DAP Monitoring Wells									
HV-2	HV-2/0914/01	09/14/90	09/25/90	1.1 B ^(a)	ND	ND	ND	ND	ND
HV-20	HV-20/0914/01	09/14/90	09/24/90	5.9 B ^(a)	ND	0.5 J ^(a)	ND	ND	0.2 J
HV-19S	HV-19S/0914/01	09/14/90	09/24/90	0.4 JB ^(a)	ND	ND	ND	ND	ND
HV-190	HV-190/0914/01	09/14/90	09/24/90	1.8 B ^(a)	ND	ND	ND	ND	ND

TABLE 6.2. (cont.)

Well No. ^(a)	Sample ID	Date Sampled	Date Analyzed	Chemical Parameter ^(b) (µg/L)					
				1,1,1-Trichloro-ethane					
				Dibromochloro-methane D.L.=1	Chloroform D.L.=1	D.L.=1	Bromodichloro-methane D.L.=1	Benzene D.L.=1	Toluene D.L.=1
WPAFB Monitoring Wells									
08-523-M	08-523-M/0911/01	9/11/90	ND	ND	ND	ND	ND	ND	ND
08-524-M	08-524-M/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
08-525-M	08-525-M/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
08-528-M	08-528-M/0913/01	09/13/90	09/20/90	ND	ND	ND	ND	ND	ND
09-530-M	09-530-M/0910/01	09/10/90	09/12/90	ND	ND	ND	ND	ND	ND
09-530-M DUP ^(c)	09-530-M/0910/02	09/10/90	09/12/90	ND	ND	ND	ND	ND	ND
18-559-M	18-559-M/0912/01	09/12/90	09/13/90	ND	1.6 B	ND	ND	ND	ND
18-560-M	18-560-M/0912/01	09/12/90	09/13/90	ND	ND	1.1	ND	ND	ND
19-564-M	19-564-M/0913/01	09/13/90	09/20/90	ND	ND	ND	ND	ND	ND
MW-20	MW-20/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
MW-20 DUP	MW-20/0911/02	09/11/90	09/13/90	0.1 J	ND	ND	ND	ND	ND
MW-21	MW-21/0910/01	09/10/90	09/12/90	ND	ND	ND	ND	ND	ND
MW-22	MW-22/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
MW-23	MW-23/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
CW1-27	CW1-27/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	ND	ND
CW1-35	CW1-35/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	ND	ND
CW1-35 DUP	CW1-35/0929/02	09/29/90	10/07/90	ND	ND	ND	ND	ND	ND
CW2-35	CW2-35/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	ND	ND
CW2-44	CW2-44/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	ND	ND
CW3-27	CW3-27/0927/01	09/27/90	10/09/90	ND	ND	ND	ND	ND	ND
CW3-27 DUP	CW3-27/0927/02	09/27/90	10/06/90	ND	ND	ND	ND	ND	0.2 J
CW3-35	CW3-35/0927/01	09/27/90	10/06/90	ND	ND	ND	ND	ND	0.5 J
CW3-77	CW3-77/0928/01	09/28/90	10/09/90	ND	ND	ND	ND	ND	ND
CW4-60	CW4-60/0921/01	09/21/90	09/27/90	ND	ND	ND	ND	ND	ND
CW4-85	CW4-85/0921/01	09/21/90	09/27/90	ND	ND	ND	ND	ND	ND
CW5-55	CW5-55/0926/01	09/26/90	10/06/90	ND	ND	ND	ND	ND	0.3 J
CW5-85	CW5-85/0926/01	09/26/90	10/06/90	ND	ND	ND	ND	ND	ND
CW6-77	CW6-77/0925/01	09/25/90	10/02/90	ND	ND	ND	ND	ND	ND
CW7-55	CW7-55/0925/01	09/25/90	10/02/90	ND	ND	ND	ND	ND	ND
CW7-100	CW7-100/0925/01	09/25/90	10/02/90	ND	ND	ND	ND	ND	ND
CW8-17	CW8-17/0924/01	09/24/90	09/30/90	ND	ND	ND	ND	ND	0.3 J
WPAFB Production Wells									
P-1	P-1/0913/01	09/13/90	09/20/90	ND	ND	0.3 J	ND	ND	ND
P-2	P-2/0913/01	09/13/90	09/20/90	ND	ND	0.2 J	ND	ND	ND
P-5	P-5/0913/01	09/13/90	09/20/90	ND	ND	ND	ND	ND	ND
City of Dayton Monitoring Wells									
MR-109S	MR-109S/0919/01	09/19/90	09/25/90	ND	ND	ND	ND	ND	ND
MR-109S DUP	MR-109S/0919/02	09/19/90	09/21/90	ND	ND	ND	ND	ND	ND
MR-110S	MR-110S/0920/01	09/20/90	09/27/90	ND	ND	0.3 J	ND	ND	ND

TABLE 6.2. (cont.)

Chemical Parameter ^(a) (µg/L)														
Well No. ^(a)	Sample ID	Date Sampled	Date Analyzed	Dibromochloro- methane		Chloroform D.L.=1	1,1,1-Trichloro- ethane		Bromodichloro- methane D.L.=1	Benzene D.L.=1	Toluene D.L.=1			
				D.L.=1	D.L.=1		D.L.=1	D.L.=1						
MR-111S	MR-111S/0920/01	09/20/90	09/27/90	ND	ND	ND	0.4 J	ND	ND	ND	ND			
MR-112S	MR-112S/0919/01	09/19/90	09/25/90	ND	ND	ND	ND	ND	ND	ND	ND			
MR-112D	MR-112D/0920/01	09/20/90	09/26/90	ND	ND	0.3 J	0.3 J	ND	ND	ND	ND			
MR-113S	MR-113S/0920/01	09/20/90	09/27/90	ND	ND	ND	0.3 J	ND	ND	ND	ND			
MR-113S	MR-113S/0920/01	09/20/90	09/27/90	ND	ND	ND	0.3 J	ND	ND	ND	ND			
MD-11	MD-11/0918/01	09/18/90	09/26/90	ND	ND	ND	0.3 J	ND	ND	ND	ND			
MD-12S	MD-12S/0918/01	09/18/90	09/25/90	ND	ND	0.2 J	0.3 JB	ND	ND	ND	ND			
MD-12M	MD-12M/0918/01	09/18/90	09/25/90	ND	ND	ND	ND	0.4 J	0.3 J	0.3 J	0.2 J			
MD-13S	MD-13S/0918/01	09/18/90	09/26/90	ND	ND	0.3 J	0.3 J	ND	ND	ND	ND			
MD-13D	MD-13D/0918/01	09/18/90	09/21/90	ND	ND	ND	ND	ND	ND	ND	ND			
MD-14S	MD-14S/0919/01	09/19/90	09/25/90	ND	ND	ND	ND	ND	ND	ND	ND			
City of Dayton Production Wells														
P-11	P-11/1001/01	10/01/90	10/07/90	ND	ND	ND	ND	ND	ND	ND	ND			
P-14	P-14/0924/01	09/24/90	09/27/90	ND	ND	ND	ND	ND	ND	ND	ND			
P-14 DUP	P-14/0924/02	09/24/90	09/30/90	ND	ND	ND	ND	ND	ND	ND	ND			
P-15	P-15/0926/01	09/26/90	10/08/90	ND	ND	ND	ND	ND	ND	ND	ND			
P-19	P-19/0928/01	09/28/90	10/06/90	ND	ND	ND	ND	ND	ND	ND	ND			
P-25	P-25/0928/01	09/28/90	10/06/90	ND	ND	ND	ND	ND	ND	ND	ND			
P-37	P-37/0928/01	09/28/90	10/06/90	ND	ND	ND	ND	ND	ND	ND	ND			
P-56	P-56/0926/01	09/26/90	10/04/90	ND	ND	ND	ND	ND	ND	ND	ND			
P-57	P-57/0924/01	09/24/90	09/30/90	ND	ND	ND	ND	ND	ND	ND	ND			
P-58	P-58/0926/01	09/26/90	10/04/90	ND	ND	ND	ND	ND	ND	ND	ND			
MCD Monitoring Wells														
MR-10	MR-10/0921/01	09/21/90	09/27/90	ND	ND	ND	ND	ND	ND	ND	ND			
GR-50	GR-50/0918/01	09/18/90	09/25/90	ND	ND	ND	ND	ND	ND	ND	ND			
DAP Monitoring Wells														
HU-2	HU-2/0914/01	09/14/90	09/25/90	ND	ND	ND	ND	ND	ND	ND	ND			
HU-2D	HU-2D/0914/01	09/14/90	09/24/90	ND	ND	ND	2.8	ND	ND	ND	ND			
HU-19S	HU-19S/0914/01	09/14/90	09/24/90	ND	ND	ND	ND	ND	ND	ND	ND			
HU-19D	HU-19D/0914/01	09/14/90	09/24/90	ND	ND	ND	ND	ND	ND	ND	ND			

TABLE 6.2. (cont.)

Well No. (a)	Sample ID	Date Sampled	Date Analyzed	Chemical Parameter (b) (µg/L)					
				Chloro- benzene D.L.=1	Styrene D.L.=1	1,2-Dichloro- ethane D.L.=1	Carbon tetrachloride D.L.=1	1,1-Dichloro- ethane D.L.=1	Vinyl chloride D.L.=1-2
UPAFB Monitoring Wells									
08-523-M	08-523-M/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
08-524-M	08-524-M/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
08-525-M	08-525-M/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
08-528-M	08-528-M/0913/01	09/13/90	09/20/90	ND	ND	ND	ND	ND	ND
09-530-M	09-530-M/0910/01	09/10/90	09/12/90	ND	ND	ND	ND	ND	ND
09-530-M DUP (c)	09-530-M/0910/02	09/10/90	09/11/90	ND	ND	ND	2.9	ND	ND
18-559-M	18-559-M/0912/01	09/12/90	09/13/90	ND	ND	ND	ND	ND	ND
18-560-M	18-560-M/0912/01	09/12/90	09/13/90	ND	ND	ND	ND	0.2 J	ND
19-564-M	19-564-M/0913/01	09/13/90	09/20/90	ND	ND	ND	ND	ND	ND
MU-20	MU-20/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
MU-20 DUP	MU-20/0911/02	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
MU-21	MU-21/0910/01	09/10/90	09/12/90	ND	0.22 J	ND	ND	ND	12
MU-22	MU-22/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
MU-23	MU-23/0911/01	09/11/90	09/13/90	ND	ND	ND	ND	ND	ND
CU1-27	CU1-27/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	ND	ND
CU1-35	CU1-35/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	ND	ND
CU1-35 DUP	CU1-35/0929/02	09/29/90	10/07/90	ND	ND	ND	ND	ND	ND
CU2-35	CU2-35/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	ND	ND
CU2-44	CU2-44/0929/01	09/29/90	10/07/90	ND	ND	ND	ND	ND	ND
CU3-27	CU3-27/0927/01	09/27/90	10/09/90	ND	ND	ND	ND	ND	ND
CU3-27 DUP	CU3-27/0927/02	09/27/90	10/06/90	ND	ND	ND	ND	ND	ND
CU3-35	CU3-35/0927/01	09/27/90	10/06/90	ND	ND	ND	ND	ND	ND
CU3-77	CU3-77/0928/01	09/28/90	10/09/90	ND	ND	ND	ND	ND	ND
CU4-60	CU4-60/0921/01	09/21/90	09/27/90	ND	ND	ND	ND	ND	ND
CU4-85	CU4-85/0921/01	09/21/90	09/27/90	ND	ND	ND	ND	ND	ND
CU5-55	CU5-55/0926/01	09/26/90	10/06/90	ND	ND	ND	ND	ND	1.0 B
CU5-85	CU5-85/0926/01	09/26/90	10/06/90	ND	ND	ND	ND	ND	0.5 JB
CU6-77	CU6-77/0925/01	09/25/90	10/02/90	ND	ND	ND	ND	ND	ND
CU7-55	CU7-55/0925/01	09/25/90	10/02/90	ND	ND	ND	ND	ND	ND
CU7-100	CU7-100/0925/01	09/25/90	10/02/90	ND	ND	ND	ND	ND	ND
CU8-17	CU8-17/0924/01	09/24/90	09/30/90	ND	ND	ND	ND	ND	ND
UPAFB Production Wells									
P-1	P-1/0913/01	09/13/90	09/20/90	ND	ND	ND	ND	ND	ND
P-2	P-2/0913/01	09/13/90	09/20/90	ND	ND	ND	ND	ND	ND
P-5	P-5/0913/01	09/13/90	09/20/90	ND	ND	ND	ND	ND	ND
City of Dayton Monitoring Wells									
MR-109S	MR-109S/0919/01	09/19/90	09/25/90	ND	ND	ND	ND	ND	ND
MR-109S DUP	MR-109S/0919/02	09/19/90	09/21/90	ND	ND	ND	ND	ND	5.4
MR-110S	MR-110S/0920/01	09/20/90	09/27/90	ND	ND	ND	ND	ND	ND

TABLE 6.2. (cont.)

Well No. ^(a)	Sample ID	Date Sampled	Date Analyzed	Chemical Parameter ^(b) (µg/L)					
				Chloro- benzene D.L.=1	Styrene D.L.=1	1,2-Dichloro- ethane D.L.=1	Carbon tetrachloride D.L.=1	1,1-Dichloro- ethane D.L.=1	Vinyl chloride D.L.=1-2
MR-111S	MR-111S/0920/01	09/20/90	09/27/90	ND	ND	ND	ND	ND	ND
MR-112S	MR-112S/0919/01	09/19/90	09/25/90	ND	ND	ND	ND	ND	ND
MR-112D	MR-112D/0920/01	09/20/90	09/26/90	ND	ND	ND	ND	ND	ND
MR-113S	MR-113S/0920/01	09/20/90	09/27/90	ND	ND	ND	ND	ND	ND
HD-100	HD-100/0918/01	09/18/90	09/25/90	ND	ND	ND	ND	ND	ND
HD-11	HD-11/0918/01	09/18/90	09/26/90	ND	ND	ND	ND	ND	ND
HD-12S	HD-12S/0918/01	09/18/90	09/25/90	ND	ND	ND	ND	ND	ND
HD-12M	HD-12M/0918/01	09/18/90	09/25/90	ND	ND	ND	ND	ND	ND
HD-13S	HD-13S/0918/01	09/18/90	09/26/90	6.2	0.4 J	ND	ND	ND	ND
HD-13D	HD-13D/0918/01	09/18/90	09/21/90	ND	ND	4.4	ND	ND	ND
HD-14S	HD-14S/0919/01	09/19/90	09/25/90	ND	ND	ND	ND	ND	13.8 B
City of Dayton									
Production Wells									
P-11	P-11/1001/01	10/01/90	10/07/90	ND	ND	ND	ND	ND	ND
P-14	P-14/0924/01	09/24/90	09/27/90	ND	ND	ND	ND	ND	ND
P-14 DUP	P-14/0924/02	09/24/90	09/30/90	ND	ND	ND	ND	ND	ND
P-15	P-15/0926/01	09/26/90	10/08/90	ND	ND	ND	ND	ND	ND
P-19	P-19/0928/01	09/28/90	10/06/90	ND	ND	ND	ND	ND	ND
P-25	P-25/0928/01	09/28/90	10/06/90	ND	ND	ND	ND	ND	ND
P-37	P-37/0928/01	09/28/90	10/06/90	ND	ND	ND	ND	ND	ND
P-56	P-56/0926/01	09/26/90	10/04/90	ND	ND	ND	ND	ND	ND
P-57	P-57/0924/01	09/24/90	09/30/90	ND	ND	ND	ND	ND	ND
P-58	P-58/0926/01	09/26/90	10/04/90	ND	ND	ND	ND	ND	ND
MCD Monitoring Wells									
MR-10	MR-10/0921/01	09/21/90	09/27/90	ND	ND	1.3	ND	ND	ND
GR-50	GR-50/0918/01	09/18/90	09/25/90	ND	ND	ND	ND	ND	ND
DAP Monitoring Wells									
HU-2	HU-2/0914/01	09/14/90	09/25/90	ND	ND	ND	ND	ND	ND
HU-20	HU-20/0914/01	09/14/90	09/24/90	ND	ND	ND	ND	ND	ND
HU-19S	HU-19S/0914/01	09/14/90	09/24/90	ND	ND	ND	ND	ND	ND
HU-19D	HU-19D/0914/01	09/14/90	09/24/90	ND	ND	ND	ND	ND	ND

^(a) The following samples are not detected (ND) for all chemical parameters analyzed: 08-522-M, 08-526-M, 08-527-M, 18-561-M, CW1-121, CW2-90, CW7-148, CW7-55 DUP, CW8-55, CW8-85, CW8-110, CW8-150, P-30 and P-55.

^(b) A "J" code is used to indicate an estimated value; the compound was found to be present but the result is less than the specified detection limit. A "B" code is used to indicate that the analyte was found in the blank as well as the sample indicating possible blank contamination. N.D.=Not Detected; D.L.= Detection Limit

^(c) DUP= duplicate sample

^(d) Determined to be a laboratory contaminant during data validation. Reported concentration is less than 10 times the detection limit value.

TABLE 6.3. Summary of Trip Blank and Equipment Blank Results for Ground Water Samples

Date Prepared	Date Analyzed	Sample ID	Type of Blank ^(a)	Chemical Parameter ^{(b)(c)} (µg/L)									
				Methylene chloride D.L.=1	Acetone D.L.=2	Carbon disulfide D.L.=1	1,2-Dichloro-ethylene D.L.=1	Trichloro-ethylene D.L.=1	Chloroform D.L.=1				
09/10/90	09/12/90	09-530-N/0910/03	TB	3.1 B	MD	MD	MD	MD	MD				
09/10/90	09/12/90	HW-21/0910/04	EB	0.63 JB	0.76 J	9.9	MD	MD	MD				
09/11/90	09/13/90	08-525-N/0911/03	TB	0.9 JB	0.3 J	MD	MD	MD	MD				
09/11/90	09/13/90	08-525-N/0911/04	EB	0.5 JB	MD	34	MD	MD	MD				
09/12/90	09/13/90	18-559-N/0912/03	TB	0.8 JB	1.0 J	MD	MD	MD	MD				
09/12/90	09/13/90	18-561-N/0912/04	EB	1.3 B	1.6 J	MD	MD	MD	MD				
09/13/90	09/20/90	19-564-N/0913/04	EB	0.5 J	0.6 J	1.6	MD	MD	MD				
09/13/90	09/20/90	P-1/0913/03	TB	0.7 J	MD	MD	MD	MD	MD				
09/14/90	09/24/90	HW-2/0914/03	TB	9.3 B	MD	1.3	MD	MD	MD				
09/14/90	09/24/90	HW-190/0914/04	EB	2.9 B	MD	2.3	MD	MD	MD				
09/18/90	09/25/90	MD-100/0918/03	TB	8.9 B	3.6	MD	MD	MD	MD				
09/19/90	09/21/90	MD-14S/0919/03	TB	8.6	MD	1.9	MD	MD	MD				
09/20/90	09/27/90	MR-110S/0920/04	EB	6.4 B	3.4	MD	0.5 J	MD	MD				
09/20/90	09/26/90	MR-1120/0920/03	TB	18 B	MD	MD	MD	MD	MD				
09/21/90	09/27/90	MR-10/0921/03	TB	21.0 B	MD	MD	0.5 J	MD	MD				
09/21/90	09/27/90	HR-10/0921/04	EB	1.6 B	MD	MD	MD	MD	MD				
09/24/90	09/30/90	CM6-55/0924/04	EB	0.5 J	MD	MD	MD	MD	MD				
09/24/90	09/27/90	P-14/0924/03	TB	6.4 B	MD	MD	MD	MD	MD				
09/25/90	10/02/90	CM6-77/0925/04	EB	1.3 B	MD	10.3	MD	MD	MD				
09/25/90	10/02/90	CM7-100/0925/03	TB	6.1 B	MD	MD	MD	MD	MD				
09/26/90	10/04/90	CM5-55/0926/03	TB	0.8 J	3.1	MD	MD	MD	MD				
09/26/90	10/06/90	CM5-85/0926/04	EB	3.1 B	3.7	0.9 J	MD	MD	MD				
09/27/90	10/06/90	CM3-27/0927/03	TB	17 B	MD	MD	0.4 J	MD	MD				
09/27/90	10/06/90	CM3-35/0927/04	EB	9.1 B	MD	MD	MD	MD	MD				
09/28/90	10/06/90	CM3-77/0928/03	TB	13 B	MD	MD	MD	MD	MD				
09/28/90	10/06/90	CM3-77/0928/04	EB	5.6 B	5.6	2.4	MD	MD	MD				
09/29/90	10/08/90	CM2-35/0929/03	TB	4.2	MD	MD	MD	MD	MD				
09/29/90	10/09/90	CM1-277/0929/04	EB	6.8 B	MD	MD	MD	MD	MD				
09/30/90	10/07/90	CM1-121/0930/04	EB	1.0	MD	4.5	MD	MD	MD				
10/01/90	10/07/90	CM7-148/1001/03	TB	0.8 J	MD	MD	MD	MD	MD				
10/01/90	10/08/90	CM7-148/1001/04	EB	1.9	MD	MD	MD	MD	MD				

TABLE 6.4. Summary of Method Blank Results For Ground-Water Samples

Date Analyzed	Sample ID	Chemical Parameter ^{(a)(b)} (µg/L)						
		Methylene Chloride D.L.=1	Carbon Disulfide D.L.=1	1,2-Dichloro-ethylene D.L.=1	4-Methyl-2-pentanone D.L.=2	Total Xylenes C.L.=1	Chloroform D.L.=1	
09/12/90	VBLKE7	1.7	ND	ND	ND	ND	0.24 J	
09/13/90	VBLKE8	0.5 J	ND	ND	ND	ND	0.6 J	
09/13/90	VBLKE8	0.5 J	ND	ND	ND	ND	0.6 J	
09/20/90	VBLKF7	ND	ND	ND	ND	ND	0.3 J	
09/21/90	VBLKA9	ND	ND	ND	ND	ND	0.3 J	
09/21/90	VBLKA9	ND	ND	ND	ND	ND	0.3 J	
09/24/90	VBLKB1	4.0	ND	ND	ND	ND	ND	
09/24/90	VBLKB0	0.9 J	ND	ND	ND	ND	ND	
09/25/90	VBLKB1	4	0.2 J	ND	ND	ND	ND	
09/25/90	VBLKB1	4.0	ND	ND	ND	ND	ND	
09/26/90	VBLKB5	3	ND	ND	ND	ND	ND	
09/26/90	VBLKB5	3	ND	ND	ND	ND	ND	
09/26/90	VBLKB5	3	ND	ND	ND	ND	ND	
09/27/90	VBLKB6	4.1	0.3 J	0.5 J	ND	0.8 J	ND	
09/27/90	VBLKB6	4.1	0.3 J	0.5 J	ND	ND	ND	
09/30/90	VBLKH1	ND	ND	ND	0.5 J	ND	ND	
10/02/90	VBLKH5	0.32 J	ND	ND	ND	ND	ND	
10/06/90	VBLKD3	1	ND	ND	ND	ND	ND	
10/06/90	VBLKD3	1	ND	ND	ND	ND	ND	
10/06/90	VBLKD3	1	ND	ND	ND	ND	ND	
10/09/90	VBLKD8	0.7 J	ND	ND	ND	ND	ND	
10/09/90	VBLKD8	0.7 J	ND	ND	ND	ND	ND	
10/09/90	VBLKD8	0.7 J	ND	ND	ND	ND	ND	
10/09/90	VBLKD8	0.7 J	ND	ND	ND	ND	ND	

TABLE 6.3. (cont.)

Chemical Parameter ^{(a)(c)} (µg/L)															
Date Prepared	Date Analyzed	Sample ID	Type of Blank ^(a)	1,1,1-Trichloro-ethane		Toluene	Chloro-benzene	Styrene	2-Hexanone	Vinyl chloride					
				D.L.=1	D.L.=1					D.L.=1	D.L.=1-2	D.L.=2			
09/10/90	09/12/90	09-530-M/0910/03	TB	ND	ND	ND	ND	ND	ND	ND	0.28 J	ND			
09/10/90	09/12/90	MW-21/0910/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/11/90	09/13/90	08-525-M/0911/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/11/90	09/13/90	08-525-M/0911/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/12/90	09/13/90	18-559-M/0912/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/12/90	09/13/90	18-561-M/0912/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/13/90	09/20/90	19-564-M/0913/04	EB	ND	ND	ND	ND	ND	4.0	ND	ND	ND			
09/13/90	09/20/90	P-1/0913/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/14/90	09/24/90	MW-2/0914/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/14/90	09/24/90	MW-190/0914/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/18/90	09/25/90	MD-100/0918/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/19/90	09/21/90	MD-145/0919/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/20/90	09/27/90	MR-110S/0920/04	EB	0.2 J	ND	ND	ND	ND	ND	ND	ND	ND			
09/20/90	09/26/90	MR-112D/0920/03	TB	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND			
09/21/90	09/27/90	MR-10/0921/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/21/90	09/27/90	MR-10/0921/04	EB	ND	ND	0.1 J	ND	ND	ND	ND	ND	ND			
09/24/90	09/30/90	CU8-55/0924/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/24/90	09/27/90	P-14/0924/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/25/90	10/02/90	CU6-77/0925/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/25/90	10/02/90	CU7-100/0925/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/26/90	10/04/90	CU5-55/0926/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/26/90	10/06/90	CU5-85/0926/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/27/90	10/06/90	CU3-27/0927/03	TB	ND	ND	0.3 J	ND	0.2 J	ND	ND	ND	ND			
09/27/90	10/06/90	CU3-35/0927/04	EB	ND	ND	ND	0.4 J	ND	ND	ND	ND	5.4			
09/28/90	10/06/90	CU3-77/0928/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	2.7			
09/28/90	10/06/90	CU3-77/0928/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/29/90	10/08/90	CU2-35/0929/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/29/90	10/09/90	CU1-27/0929/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
09/30/90	10/07/90	CU1-121/0930/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
10/01/90	10/37/90	CU7-148/1001/03	TB	ND	ND	ND	ND	ND	ND	ND	ND	ND			
10/01/90	10/08/90	CU7-148/1001/04	EB	ND	ND	ND	ND	ND	ND	ND	ND	ND			

^(a) TB = trip blank; EB = equipment blank^(b) A "J" code is used to indicate an estimated value; the compound was found to be present but the result is less than the specified detection limit. A "B" code is used to indicate that the analyte was found in the blank as well as the sample indicating possible blank contamination. N.D. = Not Detected; D.L. = Detection Limit^(c) The following chemical parameters are not detected (ND) in the trip and equipment blanks listed above: perchloroethylene, dibromochloromethane, bromodichloromethane, benzene, 1,2-dichloroethane, carbon tetrachloride, 1,1-dichloroethane.

TABLE 6.4. (cont.)

Date Analyzed	Sample ID	Chemical Parameter ^{(a)(b)}						
		1,1,1-Trichloro-ethane	Benzene	1,2-Dichloro-Toluene	Styrene	1,2-Dichloro-ethane	2-Hexanone	Vinyl Chloride
		D.L.=1	D.L.=1	D.L.=1	D.L.=1	D.L.=1	D.L.=2	D.L.=1-2
09/12/90	VBLKE7	ND	ND	ND	ND	ND	ND	ND
09/13/90	VBLKE8	ND	ND	ND	ND	ND	ND	ND
09/13/90	VBLKE8	ND	ND	ND	ND	ND	ND	ND
09/20/90	VBLKF7	ND	ND	ND	ND	ND	ND	ND
09/21/90	VBLKA9	ND	ND	ND	ND	ND	ND	ND
09/21/90	VBLKA9	ND	ND	ND	ND	ND	ND	ND
09/24/90	VBLKB1	0.6 J	ND	ND	ND	ND	ND	ND
09/24/90	VBLKB0	ND	ND	ND	ND	ND	ND	ND
09/25/90	VBLKB1	0.6 J	ND	ND	ND	ND	ND	0.3 J
09/25/90	VBLKB1	0.6 J	ND	ND	ND	ND	ND	0.3 J
09/26/90	VBLKB5	ND	ND	ND	ND	ND	ND	ND
09/26/90	VBLKB5	ND	ND	ND	ND	ND	ND	ND
09/27/90	VBLKB6	0.3 J	0.2 J	0.5 J	0.6 J	ND	ND	ND
09/27/90	VBLKB6	0.3 J	ND	ND	0.6 J	ND	ND	ND
09/30/90	VBLKH1	ND	ND	ND	ND	ND	0.9 J	ND
10/02/90	VBLKH5	ND	ND	ND	ND	ND	ND	ND
10/06/90	VBLKD3	ND	ND	ND	ND	0.5 J	0.8 J	ND
10/06/90	VBLKD3	ND	ND	ND	ND	ND	0.8 J	0.5 J
10/06/90	VBLKD3	ND	ND	ND	ND	ND	0.8 J	0.5 J
10/09/90	VBLKD8	ND	ND	ND	ND	ND	ND	ND
10/09/90	VBLKD8	ND	ND	ND	ND	ND	ND	ND
10/09/90	VBLKD8	ND	ND	ND	ND	ND	ND	ND
10/09/90	VBLKD8	ND	ND	ND	ND	ND	ND	ND

(a) A "J" code is used to indicate an estimated value; the compound was found to be present but the result is less than the specified detection limit. A "B" code is used to indicate that the analyte was found in the blank as well as the sample indicating possible blank contamination. N.D.=Not Detected; D.L.= Detection Limit

(b) The following chemical parameters are not detected (ND) in the method blanks listed above: acetone, trichloroethylene, perchloroethylene, dibromochloromethane, bromodichloromethane, chlorobenzene, carbon tetrachloride and 1,1-dichloroethane.

criteria are denoted with an asterisk in Table 6.2. Concentrations and ranges for these common laboratory contaminants will not be discussed further.

The VOCs that were detected for this investigation represent five chemical groups: chlorinated solvents (e.g., trichloroethylene, tetrachloroethylene, 1,2-dichloroethylene, 1,1,1-trichloroethane, 1,1-dichloroethane, and 1,2-dichloroethane); trihalomethanes (e.g., dibromochloromethane, chloroform, and bromodichloromethane); aromatic hydrocarbons (e.g., benzene, toluene, chlorobenzene, and styrene); saturated hydrocarbons (e.g., carbon tetrachloride); unsaturated hydrocarbons (e.g., vinyl chloride).

VOCs were detected in ground water from 47 of the 71 wells sampled. Trichloroethylene was detected in 28 of 71 ground water samples. The compound 1,2-dichloroethylene was detected in 22 of 71 ground water samples. Carbon disulfide and 1,1,1-trichloroethane were each detected in 11 of 71 ground water samples. Perchloroethylene was detected in 9 of 71 ground water samples. Toluene, acetone, and vinyl chloride were each detected in four samples. Nine VOCs (dibromochloromethane, chloroform, bromodichloromethane, benzene, chlorobenzene, styrene, 1,1-dichloroethane, carbon tetrachloride, and 1,2-dichloroethane) were detected in three or fewer ground water samples.

The following paragraphs provide an overview of the range of ground water quality conditions by TCL VOC. Trichloroethylene was reported in 28 samples at concentrations ranging from 0.1 J to 770 $\mu\text{g/L}$. Six of these samples were flagged by the laboratory as estimated "J" concentrations. The highest concentrations of trichloroethylene were found in ground water samples collected from CW5-55 (550 $\mu\text{g/L}$), CW5-85 (770 $\mu\text{g/L}$), and HD-11 (600 $\mu\text{g/L}$).

The compound 1,2-dichloroethylene was reported in 22 samples at concentrations ranging from 0.2 J to 73 $\mu\text{g/L}$. The highest concentrations found in the ground water samples were collected from HD-13S (63 $\mu\text{g/L}$) and HD-14S (73 $\mu\text{g/L}$). The 1,2 dichloroethylene concentrations are reported as totals disregarding speciation, including cis-1,2-dichloroethylene and trans-1,2-dichloroethylene. Six of 22 samples in which 1,2-dichloroethylene was detected are "J"-flagged by the laboratory as estimated concentrations. The sample collected from well CW4-85 is flagged as having possible method blank contamination (8.9 B $\mu\text{g/L}$). The QA/QC data for this sample indicate that

1,2-dichloroethylene was detected at 0.5 $\mu\text{g/L}$ and 0.5 J $\mu\text{g/L}$ in method blanks associated with the date of analysis.

Perchloroethylene was reported in nine samples at concentrations ranging from 0.1 J to 62 $\mu\text{g/L}$; the highest concentration was found in the ground water sample collected from well HD-12S. Five of nine samples in which perchloroethylene was detected are flagged by the laboratory as estimated concentrations ("J" flag).

The concentrations of 1,1,1-trichloroethane reported in eleven samples ranged from 0.2 J to 2.8 $\mu\text{g/L}$; the highest concentration was found in the ground water sample collected from well HW-2D. Nine of eleven ground water samples were flagged by the laboratory as estimated concentrations ("J" flag). The sample from well HD-12S shows possible method blank contamination (0.3 JB $\mu\text{g/L}$); QA/QC data for this sample indicate that 1,1,1-trichloroethane was detected at 0.6 J $\mu\text{g/L}$ in two method blank samples for this date of analysis. Field blank contamination may be present in samples from wells MR-110S and MR-112D. Concentrations of 1,1,1-trichloroethane in the field blanks were 0.2 J $\mu\text{g/L}$ and 0.3 J $\mu\text{g/L}$, respectively, which nearly equal the concentrations found in the environmental samples (0.3 J $\mu\text{g/L}$ and 0.3 J $\mu\text{g/L}$, respectively).

Toluene was reported in four samples at concentrations ranging from 0.2 J to 0.5 J $\mu\text{g/L}$. All four samples are flagged by the laboratory as estimated concentrations ("J" flag). Trip blank contamination is possible for sample CW3-27; the toluene concentration of 0.3 J $\mu\text{g/L}$ in the blank was slightly above that found in the actual sample (0.2 J $\mu\text{g/L}$).

Vinyl chloride was reported in four samples at concentrations ranging from 0.5 JB to 12 $\mu\text{g/L}$. The highest concentration was found in the ground water sample collected from well MW-21. Three samples, one collected from well CW5-85, one from well CW5-55, and one from well HD-14S, show possible method blank contamination (0.5 JB $\mu\text{g/L}$, 1.0 B $\mu\text{g/L}$, and 13.8 B $\mu\text{g/L}$, respectively). The QA/QC data for the date of analysis associated with samples from CW5-55 and CW5-85 indicate that vinyl chloride was detected at 0.5 J $\mu\text{g/L}$ in two method blank samples.

Dibromochloromethane, chloroform, bromodichloromethane, benzene, chlorobenzene, styrene, 1,1-dichloroethane, carbon tetrachloride, and 1,2-dichloroethane were reported in three or fewer ground water samples at concentrations ranging from 0.1 J $\mu\text{g/L}$ to 6.2 $\mu\text{g/L}$. The chloroform analysis for the sample from well 18-559-M shows possible method blank contamination (1.6 B $\mu\text{g/L}$); chloroform in two method blank samples was reported at a concentration of 0.6 J $\mu\text{g/L}$ for the date of analysis. No trip blank or field contamination was determined for these nine VOCs in any sample.

No TPH (high or low boilers) was detected in any ground water samples or QA/QC blanks. Field personnel, however, detected a fuel odor during installation of wells CW-7 and CW-8. These wells also had documented PID detections during field screening, but the laboratory analyses for these samples did not identify the contaminant as TPH.

Due to the presence of odors in wells at CW-7 and CW-8 a computerized library search was made of the sample spectra to qualify the presence of organic compounds not included in the TCL-VOC list. Estimated concentrations of tentatively identified compounds (TIC's) are contained in Appendix L. Dichlorobenzene was identified in an equipment blank from CW7-148 at a concentration of 1 J $\mu\text{g/L}$. Unknown hydrocarbons were identified in a duplicate sample from CW7-100, actual samples from CW8-17 and CW8-55, and an equipment blank from CW8-55 at concentrations ranging from 4 J to 40 J $\mu\text{g/L}$.

6.1.3 QA/QC Results

In general, laboratory QA/QC results indicate that the accuracy and precision of the Laboratory Analytical Procedures during the Phase I, Task 4, Field Investigation were reliable and therefore, the data are acceptable. The MS/MSD recovery was within method acceptance limits for all samples analyzed. Surrogate recovery was outside of method acceptance limits for only six samples, as described in Subsection 4.2.2. Data for the seven duplicate samples that were collected indicate that the analytical results had excellent repeatability.

Method blank data indicate that methylene chloride, acetone, carbon disulfide, 1,2-dichloroethylene, 1,1,1-trichloroethane, and vinyl chloride may have been introduced to some samples as routine laboratory contamination.

Trip blank and equipment blank contamination may have occurred in some samples analyzed for carbon disulfide, 1,1,1-trichloroethane, toluene, and acetone. In general, the concentrations of VOCs detected in QA/QC blanks are less than or nearly equal to those found in the actual sample and are most likely attributable to field and/or laboratory operations.

6.2 GROUND WATER QUALITY TRENDS

Organic environmental data generated during the Phase I, Task 4, Field Investigation have been evaluated to determine if any ground water quality trends exist. Based on the frequency of occurrence of TCL VOCs in analytical results from the Phase I, Task 4, Field Investigation and on concerns about off-site migration of additional solvents, the environmental distribution of five compounds will be evaluated further in the following subsections. These compounds are trichloroethylene, 1,2-dichloroethylene, perchloroethylene, 1,1,1-trichloroethane, and vinyl chloride.

6.2.1 Occurrence of VOCs in Ground Water

Of the 71 production and monitoring wells sampled during this investigation, 39 (55 percent) produced water samples in which one or more of the VOCs (excluding laboratory contaminants) listed in Table 2.2 were detected. VOCs were detected in ground water samples collected from three production wells at WPAFB and in samples from two of eleven production wells at the MRWF. Of the 35 existing monitoring wells that were sampled in the area of investigation, all but eight contained detectable concentrations of VOCs. Samples from 13 of 22 newly installed CW-series monitoring wells had detectable concentrations of VOCs.

These Phase I, Task 4, data generally confirm previously available information on the presence or absence of VOCs in ground water at and near the WPAFB boundaries. The new data which represent a one-time sampling event, however, cannot be used to determine whether water quality is changing over time. These data indicate the volatiles are distributed both laterally and vertically through the Mad River Valley Aquifer in the area of investigation.

6.2.2 Designation of Water Quality Zones for Evaluation of Ground Water Data

The monitoring wells and production wells sampled during this investigation are screened at depths ranging from less than 20 feet to in excess of 150 feet below grade. A simple mapping of data, therefore, is not useful to represent either the lateral or vertical distribution of contaminants in the environment. Ideally, wells within a single hydrogeologic unit or flow regime should be grouped to best reflect water quality conditions within the various parts of the aquifer. The existing data base is not sufficient to identify whether different hydrogeologic units exist or what their lateral or vertical extent is. Therefore, to assist in the evaluation of ground water quality trends in light of the current limitations, the water quality data are presented for three zones (upper, middle, and lower) within the aquifer based on the depth of the screens of the new CW-series monitoring wells installed during the Phase I, Task 4, Field Investigation. Wells CW1-27, CW1-35, CW2-35, CW2-44, CW3-27, CW3-35 and CW8-17 were used to define the "upper" zone. Wells CW1-121, CW2-90, CW7-100, CW7-148, CW8-110, and CW8-150 were used to determine the "lower" zone. The remaining wells (CW3-77, CW4-60, CW4-85, CW5-55, CW5-85, CW6-77, CW7-55, CW8-55, and CW8-85) represent the "middle" zone.

Screen depths of all sampled wells were compared to those of the CW-series wells in order to determine the aquifer zone that they represent. Table 6.5 summarizes the wells representing each zone. It should be emphasized that designation of the upper, middle, and lower zone is based on relative screen depth; therefore, conclusions regarding contamination with respect to hydrostratigraphic unit cannot be made.

6.2.3 Study of VOCs as a Composite Concentration

Maps were prepared to show the total concentration of all detected non-laboratory attributable VOCs in wells for each of the three water quality zones in Areas B and C (Plates 6.1 through 6.6). These maps show all the wells (presented separately as upper, middle, and lower) from which ground water samples were collected during the Phase I, Task 4, Field Investigation. Preparation of the maps involved the mathematical addition of concentrations of all VOCs to determine a composite or total concentration. Estimated

TABLE 6.5. Designation of Wells by Aquifer Layers

Well No.	Zone
MW-20	Upper
MW-21	Upper
MW-22	Upper
MW-23	Upper
MR-110S	Upper
HD-12S	Upper
CW1-27	Upper
CW2-35	Upper
CW3-27	Upper
CW8-17	Upper
013-522-M	Upper
013-523-M	Upper
08-524-M	Upper
08-525-M	Upper
08-526-M	Upper
08-527-M	Upper
08-528-M	Upper
09-530-M	Upper
19-564-M	Upper
P-1	Middle
P-2	Middle
P-5	Middle
MR-109S	Middle
MR-111S	Middle
MR-112S	Middle
MR-113S	Middle
HD-10D	Middle
HD-12M	Middle
HD-13S	Upper
HD-14S	Upper
HR-10	Middle
GR-50	Upper
HW-2	Upper
HW-19S	Upper
CW1-35	Upper
CW2-44	Upper
CW3-35	Upper
CW4-60	Middle
CW5-55	Middle
CW7-55	Middle
CW8-55	Middle
CW8-85	Middle
18-559-M	Upper
18-560-M	Upper
18-561-M	Upper
MR-108D	Lower
MR-112D	Lower

TABLE 6.5. (cont.)

Well No.	Zone
HD-11	Middle
HD-13D	Lower
P-11	Middle
P-14	Middle
P-15	Middle
P-19	Middle
P-25	Middle
P-30	Lower
P-37	Middle
P-55	Lower
P-56	Lower
P-57	Middle
P-58	Lower
HW-2D	Middle
HW-19D	Middle
CW1-121	Lower
CW2-90	Lower
CW3-77	Middle
CW4-85	Middle
CW5-85	Middle
CW6-77	Middle
CW7-100	Lower
CW7-148	Lower
CW8-110	Lower
CW8-150	Lower

concentrations marked with a "JB" or "J" code were included in the total VOC concentration, while "ND" (Not Detected) concentrations were considered to be equal to zero. Reported concentrations of the common laboratory contaminants acetone, methylene chloride, and carbon disulfide which are less than 10 times the DL were treated as "ND" concentrations (see Table 6.2). All other "B"-coded concentrations were included in the total VOC calculation.

Of the 71 wells that were sampled for VOCs, 43 wells had non-detectable quantities of total VOC and 23 had total VOCs less than 5 $\mu\text{g/L}$. Nine wells (i.e., HR-10, MW-21, CW3-77, CW6-77, MR-109S, MR-110S, MR-111S, HD-12M, and HD-13D) yielded ground water samples with a total VOC concentration between 5 $\mu\text{g/L}$ and 50 $\mu\text{g/L}$. Two wells, HD-12S and HD-14S, yielded ground water samples with a total VOC concentration between 50 $\mu\text{g/L}$ and 100 $\mu\text{g/L}$, and four wells (CW5-55, CW5-85, HD-11, and HD-13S) yielded samples with VOC concentrations exceeding 100 $\mu\text{g/L}$.

Plates 6.2 and 6.4 show that the ground water samples with the highest total VOC concentration are restricted to a relatively small area just north and west of Twin Lakes in Area C. Ground water samples in this area with highest total VOCs were collected from wells CW5-55, CW5-85, and HD-11 which represent the middle water quality zone, and wells HD-13S and MW-21 which represent the upper water quality zone. Ground water samples from all four wells which comprise cluster CW-5 (MW-21, HD-11, CW5-55, and CW5-85) yielded samples with high total VOCs.

6.2.4 Study of VOCs as Specific Compounds

For all wells sampled during the Phase I, Task 4, Field Investigation, an evaluation was made to determine if trends in contamination with a particular VOC exist in ground water with respect to the relative depth in the aquifer (e.g., upper, middle, and lower water quality zones) in Areas B and C. This subsection includes the results of this evaluation for trichloroethylene, 1,2-dichloroethylene, perchloroethylene, 1,1,1-trichloroethane, and vinyl chloride. Of these five organic compounds, only trichloroethylene and 1,2-dichloroethylene were detected with enough frequency in ground water in the area of investigation to warrant constructing concentration maps for possible contaminant plume delineation. Therefore, six concentration maps, one

representing each of the upper, middle, and lower water quality zones in Area B and Area C separately, were prepared for both trichloroethylene and 1,2-dichloroethylene (Plates 6.7 through 6.18). By constructing the concentration maps for trichloroethylene and 1,2-dichloroethylene, contaminant trends that occur with aquifer depth in both Areas B and C should become apparent. Further ground water monitoring may confirm the presence of VOCs in other layers.

Plates 6.7 through 6.12 show the distribution of trichloroethylene in the upper, middle, and lower water quality zones in Areas B and C. Of the 28 wells in which trichloroethylene was detected in both areas, 14 are from the upper zone, 13 are from the middle zone, and one is from the lower zone. The highest concentrations of trichloroethylene were reported in ground water from wells CW5-85 (770 $\mu\text{g/L}$), HD-11 (600 $\mu\text{g/L}$), and CW5-55 (550 $\mu\text{g/L}$), which represent the middle water quality zone. These data confirm the presence of elevated concentrations of trichloroethylene occurring in ground water northwest of Twin Lakes in Area C.

Plates 6.13 through 6.18 show the distribution of 1,2-dichloroethylene in the upper, middle, and lower water quality zones in Areas B and C. Of the 22 samples in which 1,2-dichloroethylene was detected, seven were from the upper zone, 13 were from the middle zone, and two were from the lower zone. The highest concentrations of 1,2-dichloroethylene were found in samples from wells HD-14S (73 $\mu\text{g/L}$), HD-13S (63 $\mu\text{g/L}$), CW5-55 (41 $\mu\text{g/L}$) and CW5-85 (40 $\mu\text{g/L}$), which represent the upper and middle water quality zones. As with trichloroethylene, an area containing elevated concentrations of 1,2-dichloroethylene was identified to the north and west of Twin Lakes in Area C.

The distribution of perchloroethylene in the upper, middle, and lower water quality zones was evaluated. Of the nine samples in which perchloroethylene was detected, four were from the upper zone and five were from the middle zone. The highest concentration of perchloroethylene was found in a sample from well HD-12S (62 $\mu\text{g/L}$) located in Area C.

The distribution of 1,1,1-trichloroethane in the upper, middle, and lower water quality zones was evaluated. Of the eleven samples in which

1,1,1-trichloroethane was detected, four were from the upper zone, six were from the middle zone, and one was from the lower zone. The highest concentration of 1,1,1-trichloroethane was found in ground water from well HW-2D (2.8 $\mu\text{g/L}$) which is located in Area B.

The distribution of vinyl chloride in the upper, middle, and lower water quality zones was evaluated. Of the four samples in which vinyl chloride was detected, two were from the upper zone, and two were from the middle zone. The highest concentrations of vinyl chloride were found in ground water from wells HD-14S (13.8 $\mu\text{g/L}$) and MW-21 (12 $\mu\text{g/L}$) located in Area C.

6.2.5 VOC Concentrations in Ground Water Exceeding MCLs

Data from the Phase I, Task 4, Field Investigation were compared with Maximum Contaminant Levels (MCLs) set by the U.S. EPA to assure the safety of water delivered by public supply systems. Table 6.6 lists the applicable MCLs for the primary VOCs detected during this field investigation. Although laboratory procedures did not include analysis for cis- and trans-1,2-dichloroethylene as separate species, MCLs for these compounds are listed in Table 6.6. As a conservative approach, total 1,2-dichloroethylene concentrations in ground water samples were compared to the MCL for cis-1,2-dichloroethylene (70 $\mu\text{g/L}$), which is the lowest of the two MCLs. Plate 6.19 and 6.20 are maps showing concentrations of organic compounds in ground water samples collected during this investigation that exceed the MCLs.

Four VOCs were detected in ground water samples at concentrations exceeding the applicable MCLs. These were trichloroethylene, 1,2-dichloroethylene, perchloroethylene, and vinyl chloride. Twelve samples from ten wells collected during this investigation contained VOC concentrations exceeding ground water MCLs for one of these VOCs.

Trichloroethylene concentrations in ground water samples from eight wells, seven from Area C (MW-21, CW5-55, CW5-85, CW6-77, HD-11, HD-12M, HD-13S) and one from Area B (CW3-77) exceeded Table 6.6 guidelines. Concentrations of trichloroethylene in ground water samples from these wells range from 6.2 to 770 $\mu\text{g/L}$. Perchloroethylene concentrations in ground water samples from one well in Area C, HD-12S (62 $\mu\text{g/L}$), exceeded Table 6.6 guidelines.

TABLE 6.6. Maximum Contaminant Levels for Organic Compounds in Public Water Systems

Parameter	MCL ($\mu\text{g/L}$) ^(a)
Carbon tetrachloride	5
Chloroform	100
Cis-1,2-dichloroethylene	70 ^{(c)(b)}
Trans-1,2-dichloroethylene	100 ^{(c)(b)}
Perchloroethylene	5 ^{(c)(b)}
1,1,1-Trichloroethane	200
Trichloroethylene	5
Vinyl chloride	2

^(a) U.S. EPA, Office of Water, EPA document 570-9-89-005, June 1989.

^(b) Federal Register, Vol. 54, No. 97, May 22, 1989.

^(c) Proposed MCL.

Vinyl chloride concentrations in ground water samples from two wells in Area C, MW-21 and HD-14S, (12 and 13.8 B $\mu\text{g/L}$, respectively) exceeded Table 6.6 guidelines. The concentrations of total 1,2-dichloroethylene in the sample from HD-14S (73 $\mu\text{g/L}$) exceeded Table 6.6 guidelines. With the exception of well CW3-77, all wells which exceeded MCLs for one or more VOCs are located in a narrow area north and west of Twin Lakes in Area C.

6.2.6 Vertical Distribution of Selected VOCs

Cross sections illustrating the vertical distribution of selected VOCs were constructed with data from those wells installed at the Area C and Area B boundaries. These cross sections were constructed in an attempt to determine if VOC concentrations and type of geologic or aquifer material occur in vertical trends. The following discussion does not attempt to define the full extent of contamination in either Area B or Area C.

Plate 6.21 shows the vertical distribution for total VOCs. The north-south cross section through Area C indicates that the total VOC concentration was highest in two gravel zones in which wells CW5-55 and CW5-85 are screened. Total VOCs ranging in concentration from 0.33 to 7.5 $\mu\text{g/L}$ were found in wells CW8-17, CW4-60, and CW6-77. The east-west cross section through Area B indicates that total VOC concentration was highest in three sand and gravel zones in which wells CW1-27, CW1-35, CW2-35, CW2-44, CW3-35, and CW3-77 are screened. Minor occurrences of total VOCs ranging in concentration from 0.8 to 0.99 $\mu\text{g/L}$ were found in wells MR-112D and CW3-27.

Plate 6.22 shows the vertical distribution of trichloroethylene. The north-south cross section through Area C indicates that the trichloroethylene concentration was highest in two sand and gravel zones in which wells CW5-55 and CW5-85 are screened. Trichloroethylene was detected in well CW6-77 at a concentration of 6.2 $\mu\text{g/L}$. The east-west cross section through Area B indicates that the trichloroethylene concentration was highest in three sand and gravel zones in which wells CW1-27, CW1-35, CW2-35, CW2-44, and CW3-77 are screened. Trichloroethylene (ranging in concentrations from 0.75 to 1.0 $\mu\text{g/L}$) was detected in wells CW3-27 and CW3-35.

Plate 6.23 shows the vertical distribution of 1,2-dichloroethylene. The north-south cross section through Area C indicates that the 1,2-dichloro-

ethylene concentration was highest in two sand and gravel zones in which wells CW5-55 and CW5-85 are screened. The compound 1,2-dichloroethylene was detected in wells CW4-60, CW4-85, and CW6-77 at concentrations ranging from 0.3 $\mu\text{g/L}$ to 8.9 $\mu\text{g/L}$. The east-west cross section through Area B indicates that the 1,2-dichloroethylene concentration was highest in sand and gravel zones in which well CW3-77 is screened. A minor occurrence of 1,2-dichloroethylene (0.3 J $\mu\text{g/L}$) was detected in well CW3-35.

7.0 FINDINGS AND CONCLUSIONS

The purpose of this Phase I, Task 4, Field Investigation was to collect additional information regarding geology, hydrogeology, and water quality at the Area C and Springfield Pike boundaries of WPAFB. The work plan that governed completion of the investigation was specifically designed to address data gaps identified after an assessment of available hydrogeologic and water-quality data and to collect critical data needed to conduct an evaluation of removal alternatives in the area of investigation. Specific activities of the investigation were undertaken after the Ohio EPA's review and approval of the work plan.

Due to the urgency of designing and implementing a removal action, this effort involved a relatively limited program to collect new hydrogeologic and water-quality data in the immediate vicinity of the boundary lines of Areas B and C and to confirm conditions at locations away from these property lines. The set of potential ground water contaminants was selected to reflect the most probable constituents that might have the potential to migrate across the Base boundaries.

Data generated by this Phase I, Task 4, Field Investigation will be used to assist in the selection and evaluation of removal alternatives, if required. Hydrogeologic and water level data will be input into a computer model designed to test various ground water withdrawal schemes. The treatment design engineers will use the water-quality data in the design of hardware for treatment of the contaminated ground water. The information gained during this investigation will also be used to estimate the extent of ground water contamination requiring remediation in the immediate area of investigation only.

The field program was intended to provide new information or to confirm existing information of the following types:

- Hydrogeologic--including the type and extent of geologic materials present beneath the site.
- Hydraulic--including the approximate transmissivity of the aquifer and the configuration of flow regimes, if they exist.

- Chemical--including the presence or absence of volatile organic solvents and fuels in ground water.

This section summarizes the findings of this investigation relative to these three basic types of information. The findings, however, are not limited to the data collected; they expand upon, confirm, or modify earlier available information in these areas.

The primary finding of the Phase I, Task 4, Field Investigation is that, although the understanding of conditions at the boundaries of Areas B and C have been increased as a result of this study, the investigative effort actually confirmed what was already known about the study area. Hydrogeologically and chemically, the current data base confirms findings reported by earlier investigations.

7.1 HYDROGEOLOGY

The Mad River Valley Aquifer at the Areas B and C boundaries consists of glacially derived unconsolidated sediments overlying an eroded bedrock surface. Plate 5.1 presents geologic cross sections at the two Base boundaries that show the lateral distribution of these geologic materials. Although all material identified above the bedrock is glacially derived, the conditions represented in Areas B and C are quite different.

7.1.1 Hydrogeology of Area C

The Area C boundary is dominated by fluvial-glacial sand and gravel with minor amounts of silt and clay-sized particles. The type of material encountered in Area C is consistent with the reports of earlier researchers (Stout et al., 1943 and Norris and Spieker, 1966). The thickness of the deposits was not as expected. The design of the field investigation was based on the belief that the sediments were at least 150 feet thick at all points of study along the Area C boundary. Three of five boring locations (CW-4, CW-5, and CW-6), however, identified bedrock at depths of 104 feet or less below grade. At location CW-4, bedrock is directly overlain by clay derived from the bedrock; however, at locations CW-5 and CW-6 glacial till may overlie the bedrock. As a result, the thickness of the fluvial-glacial deposits at these three drilling locations is about half that expected.

At locations CW-7 and CW-8, bedrock or clay were not encountered to the maximum drilling depth of 150 feet. It is not known at this time whether the deposits reach 250 feet in thickness, as represented by other researchers (Norris and Spieker, 1966).

7.1.2 Hydrogeology of Area B

The Area B boundary is dominated by glacial till. The till is a heterogeneous mixture dominated by clay and silt sized particles with interspersed gravel. At least two layers or lenses of fluvial-glacial sand and gravel were identified within the till during this field investigation.

The dominance of glacial till in Area B was unexpected. Previously available data suggest that fluvial-glacial sand and gravel may be as thick as 70 feet at the surface immediately beneath Area B (Norris and Spieker, 1966). The till was previously reported to be up to 50 feet thick over a deeper fluvial-glacial unit. This field investigation identified 35 to 40 feet of predominantly fluvial-glacial gravel overlying as much as 120 feet of till.

At drilling location CW-3 bedrock was encountered at a depth of about 100 feet below grade without any sand and gravel being identified below the till. At location CW-2, sand and gravel were not identified at the maximum drilling depth of 150 feet. At location CW-1 drilling was terminated at 150 feet in sand. Because only 6 feet of such material was penetrated during drilling, whether this represents the deeper fluvial-glacial deposits or another lens within the till is not known.

The efforts of this investigation did not determine the full thickness of the unconsolidated sediments beneath the Springfield Pike boundary of Area B. The data for both Areas B and C continue to demonstrate that the glacial materials are deposited in preglacial troughs, one trending southwest from Area C toward the Rohrer's Island Well Field and the second trending north from Area B toward the Rohrer's Island Well Field.

7.2 GROUND WATER QUALITY

As part of the Task 4, Field Investigation, the quality of ground water crossing the southwest boundary of Area C and the Springfield Pike boundary of

Area B was determined. Water quality analysis was limited to TCL VOCs and TPH.

7.2.1. Area C Boundary

Fifteen wells (5 existing wells and 10 new wells) were used to identify the quality of ground water leaving the Base at the southwest boundary of Area C. Five of these wells (08-525-M, HD-13S, MW-20, MW-21, and CW8-17) reflect the quality of water at the water table, and the remaining wells reflect conditions at depth.

Trichloroethylene, perchloroethylene, 1,2-dichloroethylene, toluene, styrene, chlorobenzene, chloroform, 1,1,1-trichloroethane, bromodichloromethane, vinyl chloride, and benzene were detected in ground water samples from water table wells at the Area C boundary. Except for well 08-525-M, samples from each of the water table wells contained at least one of these compounds. Wells MW-21 and HD-13S contained the highest combined VOC values, but well HD-13S contained the highest reported individual compound concentrations. As expected, trichloroethylene, perchloroethylene, 1,2-dichloroethylene, and vinyl chloride are the principal contaminants identified in these wells. MCLs are exceeded in well MW-21 for trichloroethylene and vinyl chloride and in well HD-13S for trichloroethylene.

Ground water quality in the middle water quality zone of the aquifer was evaluated by using wells HD-11, HD-12M, CW4-60, CW4-85, CW5-55, CW5-85, CW6-77, CW7-55, and CW8-55. Trichloroethylene, 1,2-dichloroethylene, vinyl chloride, and toluene were detected in ground water samples from wells in the middle water-quality zone at the Area C boundary. Except for well CW8-55, samples from these wells contained at least one of these compounds; the sample from CW8-55 was reported as ND for all analyzed compounds. Well CW5-85 contained the highest total VOC and the highest reported individual compound concentrations. The MCL for trichloroethylene was exceeded in wells CW5-55 (550 $\mu\text{g/L}$), CW5-85 (770 $\mu\text{g/L}$), CW6-77 (6.2 $\mu\text{g/L}$), HD-11 (600 $\mu\text{g/L}$) and HD-12M (9.1 $\mu\text{g/L}$).

Ground water quality in the lower water quality zone of the aquifer was characterized by wells HD-13D, CW7-100, CW7-148, CW8-110, and CW8-150. The VOCs, 1,2-dichloroethylene, and 1,2-dichloroethane were detected in the sample

from HD-13D. Wells CW7-100, CW8-150, CW8-110, and CW7-148 yielded samples which were reported as ND for all analyzed compounds. The MCLs were not exceeded in any of these wells.

During installation of wells at CW-7 and CW-8, a petroleum odor was noticed, and PID screenings identified the presence of VOC vapors. Laboratory analyses did not quantify specific VOCs or fuel components (except for trace levels of toluene in CW8-17) or petroleum hydrocarbons. A library search of the mass spectra from these wells identified the presence of up to 50 µg/L of unknown hydrocarbons.

7.2.2 Area B Boundary

Nine new wells were installed to define the quality of water leaving the Base along Area B. Trichloroethylene, 1,2-dichloroethylene, and toluene were the only compounds detected in the water table wells (CW1-27, CW1-35, CW2-35, CW2-44, CW3-27, CW3-35). Trichloroethylene was reported in samples from five wells; only toluene was detected in CW3-27. The MCLs were not exceeded in any of these wells.

One well, CW3-77, was completed in the intermediate portion of the aquifer. Trichloroethylene, perchloroethylene, and 1,2-dichloroethylene were the only compounds detected in this well. Trichloroethylene was detected above the MCL (9.7 µg/L) in CW3-77.

VOCs were not detected in samples from wells completed in the lower portion of the aquifer (CW1-121 or CW2-90). The MCLs were not exceeded in either well.

7.2.3 Other Areas

Ground water sampling during Phase I, Task 4, confirmed previously identified ground water quality conditions. Widespread low-level concentrations of VOCs are present off the Base. Concentrations are below the MCLs for all detected organics except for vinyl chloride in HD-14S; trichloroethylene in HD-11, HD-12M, and HD-13S; perchloroethylene in HD-12S, and 1,2-dichloroethylene in HD-14S. MCLs were not exceeded in any well in the Rohrer's Island Well Field.

7.3 EXTENT OF CONTAMINATION

Data generated during this Phase I, Task 4, Field Investigation provide information on ground water quality conditions at the southwestern boundary of Area C and along the Springfield Pike boundary of Area B. It was a primary objective of this investigation to determine if ground water quality conditions pose a threat to human health requiring immediate removal actions. For the purposes of this investigation, ground water containing VOCs in excess of MCLs is assumed to pose an unacceptable threat to health.

In Area C, samples collected at cluster well locations CW-4, CW-5, and CW-6 contain trichloroethylene or vinyl chloride that exceed the applicable MCLs. All levels of the aquifer are affected, however, the highest concentrations are found in deeper portions of the aquifer. Plates 6.2, 6.4, 6.6, 6.10 and 6.12, present the quality of water for total VOCs and trichloroethylene at the Area C boundary.

Available water level data indicate that ground water is flowing off-Base at the Area C boundary. The contaminants identified at the boundary were also quantified in wells hydraulically downgradient from the Base. Concentrations in excess of applicable MCLs have been quantified.

Only one well (CW3-77) at the Springfield Pike boundary of Area B exceeds an applicable MCL. No wells hydraulically downgradient from this well contain ground water exceeding MCLs.

Data generated during this Phase I, Task 4 Field Investigation are insufficient to understand the hydraulic or water-quality conditions at the Area B boundary. At this time the data are sufficient to suggest that a removal action is not immediately necessary.

REFERENCES CITED

- Bloyd, R. M., Jr. 1974. Summary Appraisals of the Nation's Ground-Water Resources - Ohio Region. U. S. Geological Survey Professional Paper 813-A.
- City of Dayton. 1990. Ground water quality data for HD-10, HD-11, HD-12, HD-13, and HD-14.
- DeRoche, J. 1990. USGS--Water Resources Division. Personal Communication.
- Engineering-Science, Inc. 1989. Project Work Plan for Remedial Investigations and Feasibility Studies at Wright-Patterson Air Force Base, Ohio. Volumes 1 and 4. Prepared for Wright-Patterson Air Force Base.
- Federal Register. 1989. Vol. 54, No. 97.
- Fenneman, N. M. 1938. Physiography of the Eastern United States. McGraw-Hill. pp. 419-518.
- Geraghty & Miller, Inc. 1987. Mad River Well Field Assessment and Appendices. Prepared for the city of Dayton.
- Holtz, R. D. and W. D. Kovacs. 1981. An Introduction to Geotechnical Engineering, Prentice Hall. Englewood, N.J. p. 211.
- IT Corporation. 1990. Environmental Investigation of Ground-Water Contamination at Wright-Patterson Air Force Base, Ohio. Volume 2, Work Plan. Volume 3, Sampling and Analysis Plan (SAP). Volume 4, Health and Safety Plan (HSP).
- Martin Marietta Energy Systems, Inc. 1990. Project Work Plan for Remedial Investigations and Feasibility Studies at Wright-Patterson Air Force Base, Ohio, Volume 2 Quality Assurance Project Plan. Prepared for Wright-Patterson Air Force Base.
- National Oceanic and Atmospheric Administration (NOAA). 1988. Local Climatological Data: Annual Summary With Comparative Data. Dayton, Ohio.
- Norris, S. E. and A. M. Spieker. 1966. Ground Water Resources of the Dayton Area, Ohio. U. S. Geological Survey Water Resources Investigation. Water-Supply Paper 1808.
- Stout, Wilber et al. 1943. Geology of Water in Ohio. Ohio Division of Geologic Survey, Bulletin #44.
- U.S. Environmental Protection Agency. 1986. Test Methods For Evaluating Solid Waste, Volume 11: Field Manual. 3rd Edition EPA Office of Solid Waste and Emergency Response (SW-846).
- U.S. Environmental Protection Agency. 1986. RCRA Ground-Water Monitoring Technical Enforcement Guidance Document (TEGD). Document OSWER-9950.1.

U.S. Environmental Protection Agency. 1988. Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA, Interim Final.

U.S. Environmental Protection Agency. 1989. Office of Water. EPA Document 570-9-89-005.

Walton, William C. and Scudder, George D. 1960. Ground-Water Resources of The Valley Train Deposits in the Fairborn, Ohio Area. Ohio Division of Water, Technical Report No. 3.

Weston, Inc. 1989. Stage 2 Report-Volumes, I, II, and III, Technical Report and Appendices. Prepared for Wright-Patterson Air Force Base.

DISTRIBUTION

No. of
Copies

OFFSITE

- 2 DOE/Office of Scientific
and Technical Information
- 6 R. Lester
Office of Environmental
Management
Restoration Branch
2750 ABW/EMR
WPAFB, OH 45433-5000
- Air Force Logistics Command
Headquarters
Area A, Building 262
HQ AFLC/DEVR
WPAFB, OH 45433
- T. Ballard
United States Environmental
Protection Agency
Region V (5HS-11)
230 S. Dearborn St.
Chicago, IL 60604
- 2 B. Buthker
Ohio Environmental
Protection Agency
Southwest District Office
40 S. Main St.
Dayton, OH 45402-2086
- K. Davidson
Ohio Environmental
Protection Agency
1800 WaterMark Dr.
Columbus, OH 43266
- K. Dovantzis
PRC Environmental
Management Inc.
233 N. Michigan Ave.
Suite 1620
Chicago, IL 60601

No. of
Copies

OFFSITE (continued)

- 2 R. Eastmond
International Technology
Corporation
Richland Regional Office
1045 Jadwin Ave., Suite C
Richland, WA 99352
- 4 J. Register
International Technology
Corporation
Cincinnati Regional Office
11499 Chester Rd.
Cincinnati, OH 45246

ONSITE

- DOE Richland Operations Office
- J. Shadel
Federal Building
Room 514, Area 700
825 Jadwin Ave.
Richland, WA 99352
- 3 Environmental Management
Operations (EMO)
- T. Page
D. Reed
Records Management
723 The Parkway
Richland, WA 99352
- 6 Pacific Northwest Laboratory
- Publishing Coordinator
Technical Report Files (5)

END

**DATE
FILMED**

8 / 11 / 92