PERFORMANCE EVALUATION OF A CERAMIC CROSS-FLOW FILTER
ON A BENCH-SCALE COAL GASIFIER

Westinghouse Principal Investigators
D. F. Ciliberti and T. E. Lippert

Fifth Quarterly Report
October 1, 1985 - December 31, 1985

Contract Number DE-AC21-84MC21338

DOE Project Officer: Randall J. Dellefield
Department of Energy
Morgantown Energy Technology Center
P.O. Box 880
Collins Ferry Road
Morgantown, WV 26505

DISCLAIMER

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, mark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PATENT STATUS

This technical report is being transmitted in advance of DOE patent clearance and no further dissemination or publication shall be made of the report without prior approval of the DOE Patent Counsel.

TECHNICAL STATUS

This technical report is being transmitted in advance of DOE review and no further dissemination or publication shall be made of the report without prior approval of the DOE Project/Program Manager.

OVERALL PROGRAM OBJECTIVES

The Department of Energy is currently supporting a program that will aid in the development of cross flow filtration technology as applied to combined cycle power generation with coal gasification. The stated overall goal is to gain information on both the operational and economic feasibility of the implementation of cross flow filtration in various gasifier options. Westinghouse has prepared a comprehensive program that will lead directly to these program goals in an efficient manner.

The proposed program is composed of three major technical tasks. Task 1 is directed at the design and actual test of a cross flow filter at a DOE bench scale gasifier. Task 2 is composed of several smaller theoretical and experimental efforts that are intended to firm up areas where engineering and design principles are lacking or considered inadequate. The third task is intended to integrate the results of the first two tasks in a conceptual design and cost analysis such that proper economic perspective for the filter concept can be gained. A brief summary of the approach taken in the technical tasks is presented in the following discussion.

In the conduct of Task 1, we will design, fabricate, install, and operate a cross flow test system at the AGC. The actual test article will incorporate provisions for a scaled down cross flow element that will accommodate all of the gasifier flow. From this element, we will gain information on filtration parameters such as efficiency, pressure drop, and cleanability. The element will be instrumented with high speed differential pressure transducers that will allow us to quantify the pulse jet parameters that are required for successful blow back cleaning. These will subsequently serve as inputs to scaling models for full size module calculations.

In Task 2 we propose to conduct a series of independent tests. The efforts center on the following areas: 1) a task to develop a filter element with improved mounting and delamination properties, 2) a task to refine our model that describes the dynamics of pulse jet cleaning, 3) a task to quantify the dust cake properties of char and sulfur sorbent fines, and 4) a chemical stability test of the cross flow filter in a simulated gasifier environment.

The third technical task will involve the integration of new test data and model refinements into a sound conceptual design for at least three gasifier systems. Westinghouse personnel that have had past and current responsibility for commercial gasification systems design and cost analysis will assume the primary responsibility for this task. We are confident that the approach of coupling a sound scientific data base and scaling methodology with a broad systems understanding and capability will result in a sound conceptual design and costing basis.

PROJECT STATUS REPORT FOR OCTOBER THROUGH DECEMBER

During this quarter, virtually all of the effort expended on this project was directed at testing cross flow filters at METC. The entire test covers the period from 8/5 to 11/22. This report summarizes and documents the details of the entire METC test program even though the initial test period was reported in the previous quarterly report. We have chosen to include the earlier work so that the entire test program is reported in a single report.

SUMMARY OF METC/W CROSS FLOW FILTER PROGRAM

The following presents a very brief summary of the sequence of test events associated with the testing of the cross flow ceramic filter at the METC test facility. The period covered includes testing done from August through November 1985.

Test Segment I:

This test was carried out using the filter element WCXF2, one of the two original filters supplied to Westinghouse by Coors in this program. This filter element was flanged and had a very low resistance to flow, only about 1 in wg at a face velocity of 8 ft/min in its clean and unused state.

The goal of the first 50 hr test segment was to gently condition the filter by initiating testing at a low face velocity. The plan was to then gradually increase velocity to its nominal value of 5 ft/min over the first 25 hours of test and then hold constant for the final 25 hours.

8/5: The system was brought to 720°F at a pressure of 250 psig with a flow of 1000 scfh of N₂, in an attempt to preheat the system prior to bringing product gas on line. At these conditions the filter registered a 1.6 in wg pressure drop. Operating personnel experienced problems with the electric in line process gas heater and testing was stopped for repair of the heater. This consisted of seal welding an internal flange connection.

8/9: By 09:30 the system had been heated to 950°F and product gas was brought on line at a flow of 1250 scfh. Soon after start of the test the system began to lose temperature and it was determined that the process heater had blown three fuses. A decision was made to finish the day shift at the temperature that the line heaters would afford, which was about 520°F. During this 8 hour run the filter pressure drop reached 17.9 in wg at a velocity of about 3.6 ft/min. At this point the filter was pulse jet cleaned with a pulse from a 300 psig reservoir which generated a very gentle 3/4 psid cleaning pulse within the filter element. This was sufficient to reduce the base pressure drop to only 3 in wg, confirming our earlier conclusion that gasifier char should be relatively easy to clean from the filter. The first samples from the system indicated an overall efficiency of about 99.2%.

8/13-8/15: On 8/13 the system was restarted and brought to a flow of 1060 scfh which yielded a velocity of 2.6 ft/min at 250 psig and ~ 1000°F. These conditions were held for the first 16.5 hours test. During this time the filter worked well with cycles from 5 to 18 in wg taking from 1/2 to 1 hour with inlet concentrations that were typically 4000 ppm. After 16-1/2 hours the flow was increased to 1430 scfh and the system temperature settled out at 1400°F yielding a face velocity of 3.5 ft/min. At these conditions the filter cycled between 12 and 30 in wg roughly every half hour. Samples taken during this period indicated overall efficiencies of 99.9+%.

From test hour 25 to 50 the system was run at a flow of 1750 scfh and a face velocity of about 5 ft/min. The pressure drop cycle was maintained at about 14 to 30 in wg every 20 min. During this period DOE particulate samples indicated some very wide swings in particulate loadings ranging from 300 ppm to 1400 ppm.

Efficiencies remained high until about test hour 41 when a noticeable amount of penetration began to occur and efficiencies dropped to 98.5%. After the 50 hour segment was completed the element was removed for inspection. The main body of the filter was found to be in excellent condition, however, upon careful examination it was determined that the filter flange had cracked along the complete length of one side of the element, and was the apparent source of dust penetration.

In the period between 8/15 and 9/10 METC personnel fabricated a natural gas fired gas heater as a back up to the existing electric gas heater as it had continued to be an operational problem and was apparently unable to provide enough heating to provide desired filter inlet temperatures.

Also during this time we prepared a second filter element for test (WCXF4). This element had very much thicker and more rugged flanges than WCXF2, and its back face had been slip coated and fired in an attempt to provide insurance against delamination. In Coors opinion, however, this process had not significantly improved the strength of this particular part since the slip had not penetrated the surface of the filter very well. It was also noted that in the process of refiring the slip coating, the element had lost considerable permeability giving a pressure drop of 4.4 in wg at a face velocity of 7 ft/min.

Test Segment II:

The goal of this test segment was to operate the cross flow filter on gas that had been desulfurized in a fixed bed of zinc ferrite operated at 1200°F and 250 psig.

9/10: Testing was to begin this day but check out of the modified electrical heater and the new natural gas fired process gas heated consumed the entire day.

9/11: The initial period of testing was carried out at a flow of 1050 scfh at 930°F and 250 psig which yielded a filter velocity of 2.75 ft/min. At these conditions the baseline pressure drop was about 4 in wg and cycles to 15 in wg lasted for a period from 1/2 to 1 hour with inlet concentrations of 1000 to 2000 ppm. Overall efficiencies were measured at 99.5 to 99.8%. At test hour 24 the ignitor rod blew out of a Conax fitting and caused a shut down of the filter system and during this period the gasifier developed problems with a clinker shutting the entire test down for several days.

9/16-9/18: Test was restarted with the electrical process heater out of the system. The filter was preheated and brought as product gas at a flow of 1200 scfh at 1200°F early on 9/17. A leak developed in a flexible, inlet tube to the gas heater causing a 9 hour shut down. When the system was brought back on line the filter operated first at 2.6 ft/min and then at 3.7 ft/min for the duration of the test. The second half of the test went well with relatively stable cycles from 10 to 25 in wg over 1/2 to 1 hr periods and with inlet concentration of 300 to 800 ppm. During this time cleaning pulses of 300 to 350 psig were utilized and these generated internal filter pressure rises of 1.5 to 2 psid. Overall filter efficiencies were determined to be about 99.5% on average, which was somewhat lower than might have been expected, and which are typical of a minor flaw in the filter or its seals.

Test Segment III:

The goal of this test period was to gain experience operating at higher filter face velocities. We had originally planned to conduct several tests at 10 ft/min, however, as testing proceeded it became clear that the high velocities were not compatible with the higher resistance filter element.

9/18: Upon completion of the previous test the system was switched off desulfurized product gas and onto N₂ in preparation for a final switch back to undesulfurized gas. After some difficulties with plugging in lines the test was initiated at a flow of 1850 scfh at 1475°F which gave a face velocity of 10 ft/min. Over the first two hours the filter was cycled from 10 to 35 in wg five times in a steady fashion. At this point in time one of the sample lines became overheated, failed and caused an immediate shut down. At this time DOE operating personnel decided to make modifications to the gas fired heater and to rearrange the filter vessel and system piping in order to minimize heat loss in the system. Since the unit was to be down for a while, the filter was removed for inspection. It was determined that a delamination had occurred and was resulting in a small dust leak at the front face of the filter. A decision was made to patch this point with ceramic adhesive and to continue testing with this filter.

10/25: Testing was to resume with the modifications to the test facility completed, however, difficulties with the gas heater ignitor system prevented start up.

10/30 - 10/31: The system was preheated with nitrogen and brought on process gas at 1750 scfh at a temperature of 1520°F yielding a face velocity of 5.6 ft/min. The initial baseline pressure drop was measured at 12.3 in wg and the

unit settled into stable operation between 15-30 in wg every 15 to 20 minutes with a dust concentration of about 500 ppm. After about 8 hours dust feed was initiated. For the first four hours not much change was noticed in either filter behavior or inlet concentration. After about 4 hours of dust feed the system experienced 2 hour long periods of unstable operation during which the pressure drop would climb from 10 to 50 in wg in 4-5 min. During this time the filter operator increased the pulse pressure to 440 psig which gave pressure rises of 4-6 psid within the filter.

After these upsets passed, the system settled into stable operation for the remaining 40 hours of test. During this later period the filter cycled from about 12 to 20/30 in wg over 1/2 to 1 hour periods with inlet concentration of about 2200 ppm. The cleaning regimen was maintained at the 440 psig level throughout. It was noted that some significant penetration persisted with a measured overall efficiency of only 98.5%.

Test Segment IV:

The goal of the next test segment was to operate the filter both at high dust loadings and at high filter velocities on undesulfurized product gas.

11/1: At 22:15 on 11/1 the system was reset to operate at high velocities. Additionally a decision was made to operate at a lower system pressure of 150 psig in order to make more efficient use of the bottled methane being used to fire the combustor. The initial operating conditions were: flow of 2200 scfh at a temperature of 950°F and a pressure of 150 psig. The filter velocity was 10.7 ft/min and the initial baseline pressure drop was about 15 in wg. During the first 90 minutes of test the system temperature rose from 950 to 1410°F, and caused the baseline pressure drop to rise

accordingly. The filter operator attempted to maintain the baseline by increasing the pulse pressure from 250 to 350 psig. During this time the pressure drop cycled from 15 to 25 inches at roughly 1/2 hr intervals.

After 7 hours of operation a significant decrease in baseline pressure drop was noted and the subsequent rate of pressure drop increase was much lower than it had been previously. Outlet samples soon confirmed a serious problem with the filter as to efficiency dropped to only 86%. After 13 hours of operation the test was halted for inspection of the filter.

It was determined that the filter had delaminated at two additional planes and had, in fact, broken across to filter flats causing a major breach of the filtering barrier.

The only remaining filter element suitable for testing was prepared. This element (WCXF5) had been fired, coated with a slip and then high fired. The resultant coating appeared to be greatly superior to that of WCXF4. Additionally Westinghouse had ground the back side of the mounting flange so that it was parallel with the front sealing face. This process had not reduced the flange thickness significantly. This filter did have two potential flaws, however. In the process of firing a ripple had developed in the top two layers near the sealing face, and its effect on the units integrity was undetermined. Also, the high refire had reduced the permeability of the unit to an even greater extent than the previous filter, this unit having a pressure drop of 5.3 in wg at a filter face velocity of 7 ft/min.

11/5: Testing was to resume on 11/5 with a plan to gradually increase filter velocity up to the 10 ft/min value of the test plan. After heat up on N₂ attempts to start the combustor failed and it was determined that the ignitor itself had to be replaced and that the cast refractory in the combustor needed to be repaired.

11/6: At 22:45 on 11/6 the system was on gas at a flow of 1200 scfh and at 900°F and 150 psig. The flow was gradually increased over the next 3 hours to 2200 scfh and at a temperature of 1100°F the velocity was at 10 ft/min. The system operated with cycles from 30 to 40 in wg on 10 min cycles with inlet loadings at about 800 ppm, however after 9 hours the baseline pressure drop was still rising so a decision was made to lower the flow to 1725 scfh or 8.2 ft/min. Under these conditions the cycles were from 26-40 in wg on about 20-30 min periods. The system was fairly stable for a period of 8 hours, but then began an 8 hour period in which the baseline increase and cycle time shortened to a cycle of 40 to 48 in wg every 15-20 minutes. During this period the efficiency averaged about 98.5 - 99%.

At test hour 26 (22:00 on 11/7) the gasifier developed a problem and the test was shut down.

11/17: Testing resumed 11/17 at a flow of 1750 scfh, pressure of 150 psig and temperature of 1510°F. At 9 ft/min the initial cycles went from 30 to 35 in wg in a half hour. During the early part of the test it was determined that a steam heating line in the dust feeder had failed and water/steam was being injected into the system. This was repaired and the test continued.

Over the first 10 hours the baseline pressure gradually rose so that it was at 38 in wg and the cycle to 44 in wg took about 10 min. The filter did not appear to be cleaning well.

At 06:46 on 11/18 it was determined that the steam lines in the dust feeder were again leaking so the system was again shut down for repair. Late that day testing was resumed at a flow of 1750 scfh, however, the filter cycles were only 6 to 10 min. long to go from 40 to 45 in wg. In the subsequent 5 hours the flow was reduced two times (first to 7.4 ft/min and then to 6.4 ft/min) in an attempt to establish a stable operating cycle. During the last 5 or 6 hours of this 50 hr test segment, the cycles were from 44 to 48 in wg over 10 min periods and it also became apparent that something had gone wrong with the dust feeder as the last two inlet samples indicated loadings of only 22 and 40 ppm.

At the conclusion of this 50 hour test period the vessel was opened and the filter was found to be coated with a crusty or flaky deposit of char quite unlike the usual powdery deposits seen in previous testing. Additionally the inside of virtually all of the cross channels were plugged with the same deposit. Our speculation is that at some point the steam leaks in the dust feeder caused the dust on the filter to become wet and a difficult to remove deposit was formed on subsequent heat up. Water was found in the dust feed vessel and the filter instrument lines had to be drained. It was also determined that the motor rotation for the feeder was backward and had caused the auger to become detached.

The exterior of the filter was brushed clean and the channels scraped clean using pipe clearers and a vacuum. The filter was reinstalled and made ready for a repeat run of the previous test segment.

Test Segment V:

11/20: Testing was scheduled to resume on 11/20, however, problems arose with the gasifier during start up. A decision was made to carry out the remainder of the test using heated nitrogen and dust from the feeder. The system was brought to a flow of 1750 scfh at 150 psig and a temperature of 900°F yielding a velocity of 7.5 ft/min. This test ran without major incident throughout the next 38 hours, to a point in time where personnel scheduling dictated a shutdown. In the period the pressure drop cycles were quite steady starting at 40 minute cycles between 14 and 25 in wg and finishing at 40 min cycles from 17 to 27 in wg. Inlet loadings were typically 2800 ppm and typical filter efficiencies were 98.5%. Cleaning pulses over this period were set at 250 psig and gave filter internal pressure rises of 3-1/2 - 4 psid.

At the end of this test program the filter element was removed for inspection and found to be in excellent condition.

Cross Flow Filter Testing at METC

8/5:

On August 5th attempts were made to initiate the actual test program. At 9:00 a.m. the system flow was brought to a flow of 1000 scfh of N₂ at a system pressure of 250 psig and the system was gradually heated with the use of the electric process gas heater and the filter vessel heaters. The initial pressure drop of the filter (WCXF1) was about 1.6 in. wg. By about 5:00 p.m. the system had been heated to 720°F, however, some difficulty was being experienced with the process gas heater, so the test was shut down to inspect the heater.

In the next few days it was determined that an internal bolted and flanged connection of the heater had loosened, and caused leaking from the shell side of the heater to the heated process gas side. The solution was to seal weld this joint.

8/9:

The system was back in operating condition by August 9, and at 8:15 a.m. the system was brought to a flow 1250 scfh N₂ at a pressure of 250 psig and a temperature of 560°F. The initial filter pressure drop was about 3-4 in. wg. By 9:30 a.m. the system had been brought to a temperature of 830°F and the switch from N₂ to process gas was made. As can be seen in Figure 1, from 9:30 to 11:30 a.m. the pressure drop rose fairly constantly to a value of 10 in. wg. and the system temperature rose to 950°F. During this period DOE sample (8-9 0939-1053) indicated an inlet concentration of approximately 10.98 mg/scf or 410 ppm. At this time we began to lose temperature and it was discovered that the process heater had blown three fuses.

A decision was made to finish out that day shift with the temperature that the line heaters could provide. By about 2:30 p.m. the temperature had steadied at about 520°F. At this time the pressure drop had climbed to 17.9 in. wg. and the first pulse jet cleaning sequence was initiated. It consisted of a single 0.1 second pulse from a reservoir charged to 300 psig. During this initial pulse the system was placed in the bypass mode of operation. The internal pressure rise generated by the pulse was monitored (Figure 2) and it was found to be about 0.75 psi. Even with this very gentle pulse, the filter's pressure drop was decreased from 17.9 to 2.7 in. wg.

Figure 1 - Cross Flow Filter WCXF2 (8/9/85)

Cross flow filter WCXF-2 (8/14/85) $T = 1400^{\circ}\text{F}$, $P = 250 \text{ psig}$, $V_f = 4.89 \text{ ft/min.}$

Figure 1 - (continued)

Figure 2 - Pulse Trace of the Cleaning Pressure Differential Generated Inside Filter Plenum Relative to Dirty Side of Filter During a 0.1 sec Pulse from a 300 psig Reservoir to a 250 psig System

As can be seen in Figure 1, the remainder of the day consisted of a nearly 2 hr cycle to 10 in. wg. and a short cycle to 6.6 in. wg., each being punctuated by a successful pulse of 300 psig for 0.1 sec.

During the afternoon DOE samples were taken that indicated an inlet loading of 200 ppm and an outlet loading of between .09 to 4.28 mg/scf. The estimated filter efficiency was determined to be 99.18% which seemed a bit low, however, there was considerable variability in the outlet probe, and total outlet measurements, so there may be some question about the precision of the calculated efficiency.

In the period from 8/9 to 8/13 repairs were made on the process heater and a new test was initiated on August 13.

8/13-8/15:

At 8:00 a.m. 8/13 the filter system was at 655°F, 200 psig and had a pressure drop of 7.1 in. wg. at a flow of 960 scfh of N₂. By about 9:30 a.m. the system was switched to process gas at a flow of 1060 scfh and a temperature of 930°F and an initial pressure drop of 7.6 in. wg. The filter and system ran in a fairly steady fashion for the next 8-1/2 hours with nine cycles from 5 or 6 to 18 in. wg. and cycle times from 30 to 70 minutes. The flow was maintained at 1050 scfh, and at 1100°F and 250 psig; this gave rise to a filter face velocity of 2.6 ft/min. DOE inlet samples during this time indicated a typical inlet concentration of about 400 ppm during the first few hours. Later in this period the dust feeder was turned on and DOE sample (8-13 1320-1620) indicated an inlet loading of 100.5 mg/scf or 3700 ppm.

At about 6:00 p.m. (hr = 16.5 Fig. 1), the system flow was increased at a slow rate so that by 6:30 the system flow was at 1430 scfh. With a system temperature of 1100 to 1175°F the filter face velocity was approximately 3.5 ft/min. During the next 8-1/2 hr period (hr = 16.5 to hr 25) the system ran smoothly with measured efficiencies of 99.9+%, inlet concentrations from 3700 to 4100 ppm and cycle times of about 25 min for the pressure drop to rise from its base value of 12-15 in. wg. to the trigger pressure drop of 30 in. wg.

At 2:20 a.m. on 8/14 the system flow was again increased; this time from 1400 to 1750 scfh. In the subsequent several hours the temperature rose to about 1200°F giving a filter face velocity of 4.3 ft/min. This mode of operation was maintained constant over the next 25 hours of operation with the exception that the system temperature gradually worked its way up to a value of 1400°F giving face velocity of 4.9 ft/min. Cycle times during this period were typically 20-25 minutes to go from 14 to 30 in. wg. During this time DOE samples indicated a generally increasing inlet loading to the filter ranging from about 4500 ppm at the start of this period to values of about 18,000 ppm (hr 42-44) and then back to 2500 ppm near hour 48.

The measured overall efficiencies remained high at 99.9+% until about hour 42 (8/14) when the measured efficiency dropped to 98.45 and 98.45 again at hr 43. This drop can also be seen in Table I which shows the outlet loadings before 11:00 a.m. 8/14 were generally 0.1 - 0.5 mg/scf, but then increase to 1.1 to 4.1 mg/scf after that time. These higher outlet concentrations are typical of a flaw or failure in the filter element or its sealing.

Table 1 -PHYSICAL DATA FOR PARTICULATE SAMPLES TAKEN DURING HGC TEST 8/9 TO 8/15/85

SAMPLE	SAMPLING TIME (MIN)	PROBE POSITION	SAMPLE FLOW RATE (SCFM)	FLOW SAMPLED (SCF)	WEIGHT PARTICULATES (GRAMS)	MASS LOADING (MG/SCF)	MEAN :	
							MEAN VOLUME DIAMETER (MICRONS)	POPULATION DIAMETER (MICRONS)
8-9 0939-1053	61	INLET	0.240	18.960	0.2081	10.98	-	-
8-9 1250-1550	180	INLET	0.260	54.960	0.2986	5.43	1.92	0.87
8-9 1300-1640	220	OUTLET	1.04	260.960	1.1175	4.28	2.02	0.90
8-9 1401-1411	10	TOTAL OUTLET	17.50	223.432	0.0195	0.09	-	-
8-13 0941-1111	90	INLET	0.273	27.210	0.2990	10.99	-	-
8-13 1320-1620	180	INLET	0.273	57.780	5.8090	100.54	22.97	14.54
8-13 1024-1620	356	OUTLET	0.273	407.240	0.2498	0.61	5.62	2.15
8-13 1320-1620	180	TOTAL OUTLET	17.50	4022.160	0.2573	0.06	7.59	5.38
8-13 2005-2305	180	INLET	0.273	56.340	6.3204	112.18	17.45	10.59
8-13 2005-2305	180	OUTLET	1.09	222.696	0.0270	0.12	7.62	4.95
8-13 2000-2300	180	TOTAL OUTLET	23.33	4852.212	2.2505	0.46	15.87	10.32
8-14 0340-0633	173	INLET	0.456	90.888	11.0732	121.83	10.06	3.59
8-14 0340-0633	173	OUTLET	1.82	340.060	0.1593	0.47	8.51	5.62
8-14 0330-0631	181	TOTAL OUTLET	29.17	5629.635	0.7305	0.13	4.98	3.68
8-14 1100-1400	180	INLET	0.456	97.920	13.7332	140.25	32.51	17.43
8-14 1116-1416	180	TOTAL OUTLET	29.17	6031.692	6.6728	1.11	6.17	3.36
8-14 1623-1723	60	INLET	0.456	30.720	8.2418	268.29	20.61	14.65
8-14 1917-2017	60	INLET	0.456	32.160	15.5777	484.38	27.35	16.84
8-14 1733-2034	181	TOTAL OUTLET	29.17	6722.963	27.8902	4.15	23.73	16.02
8-14 2200-2300	60	INLET	0.456	30.240	6.3809	211.01	23.98	15.48
8-14 2153-2353	120	TOTAL OUTLET	29.17	4281.168	13.2095	3.09	6.38	3.65
8-15 0038-0138	60	INLET	0.456	31.440	2.0778	66.09	23.56	12.17
8-15 0207-0253	46	OUTLET	1.82	101.080	0.3435	3.40	4.34	2.44

At 3:00 a.m. on 8/15 the initial test period had been finished and the entire system was shut down.

In the following days the filter vessel was opened and the system was examined. It was determined that several of the heater wires had broken during the test. This had happened in the hottest section of wire nearest the liner, where the 12 awg nickel coated copper stranded wire had embrittled badly under the high partial pressure of CO, H₂, and H₂S. Another item that required corrective action was the outlet nozzle liner. It had shifted during installation of the vessel head and allowed hot gas to bypass this section and had caused a small hot spot (350°F) at the penetration of the outlet nozzle on the vessel head.

When the filter element itself was removed (Figure 3) it appeared to be in relatively good shape, although there was some accumulation of dust at the bottom of the filter, indicating that cleaning could have been somewhat more forceful. After the filter had been brushed off, the outer face looked to be in excellent condition (Figure 4) however, a close inspection of the inner face (closest to the clean gas plenum) revealed a fracture along the flanged surface of the filter. When the filter was removed from the mount, it was seen that the entire inner flange had broken (Figure 5) and had allowed some of the gasket material under that section to be blown out during pulse jet cleaning (Figure 6). This allowed the small amount of penetration that been observed to occur.

This type of filter failure was particularly unfortunate since it could have been avoided.. The flange on this filter (WCXF2) had started out at a thickness of 0.5 in, but was reduced to about 1/2 that value when the sealing face was ground

Figure 3 - Cross Flow Filter WCXF2 As Removed From METC Test Facility After Initial 50 hr Run

Figure 4 - Cross Flow Filter WCXF2 Brushed Off After Initial
50 Hour Exposure in METC Test Facility

Figure 5 - Photo Showing Failure of Flange on Cross Flow Filter
WCXF2 After 50 Hour Exposure in METC Test Facility

Figure 6 - Photo Showing How Gasketing Material Allowed Some Particulate Penetration After Flange Failure of Cross Flow Filter WCXF2

smooth for mounting. This element had been returned to Coors prior to use, so that back face and flange could be coated with a "slip" of the parent material and then refired at a high temperature for improved delamination resistance. After this process the front flanged sealing surface was again ground smooth and flat and reduced in thickness to the tested value of about 1/8 inch. It is our feeling that the flange probably was cracked during the mounting of the filter and it subsequently broke after about 65 pulses in the system.

The following steps were taken to remedy the problems observed in the filter vessel. 1) The outlet nozzle liner was repositioned to eliminate the hot spot, and this area was repainted with blue, temperature sensing paint. 2) The multistranded nickel coated copper wire was removed and single strand 12 awg nickel manganese wire was ordered to replace the damaged wire. 3) The Coors filter WCXF4 was prepared for mounting and subsequent test. This filter, shown in Figure 7, had been dipped in a slip and then high fired at 1530°C. The slip material was too thick, in Coors personnel's estimation, to have substantially infiltrated the surface of the filter, with the consequence that most of the coating resided at the surface of the filter where it was not of maximum benefit. It was felt, however, that the high firing should have improved bonding, and the flanges on this element remained at nearly the full 1/2 in thickness.

The new filter element was tested at ambient temperature to determine its virgin pressure drop/flow characteristics. Figure 8 presents this data, where it can be seen that the clean filter pressure drop is about 16 in. wg. at a face velocity of 11.7 ft/min. This is somewhat higher than previous Coors filters and probably is a result of some loss of pore size/porosity during the higher temperature firings.

Figure 7 - Second Cross Flow Filter (WCXF4) to be Tested at
METC HTHP Gasifier Test Facility

Figure 8 - Cross Flow Filter WCXF4 Pressure Drop vs Filter Face Velocity for Element Never Having Been Exposed to Dust

A decision had been made to install a natural gas fired combustor at the electric process heater outlet to act as a back up heater. The design, fabrication and installation of this device coupled with the Labor Day Weekend precluded any further testing during August.

Cross Flow Filter Testing During September:

On 9/9 the Westinghouse test engineer and technician returned to the METC test site and repaired the internal heater lead wires and proof tested the heater system. During this check out it was determined that the 3 phase power leads to the test vessel had not been properly installed with the result that only one phase had been available. Site electricians corrected the problem and the heaters checked out OK.

The new cross flow filter WCXF4 (shown in its mounting in Figure 9, was installed in the vessel and METC personnel replaced the top of the housing and torqued it down in preparation for pressure checking.

In the preceding week, METC personnel had completed the installation of a small natural gas fired combustor at the outlet of the electrical system process heater to provide additional temperature as required.

9/10 - 9/11

On 9/10 at 7:45 a.m. the system was begun to be heated on N₂ flow and the electrical process heater. Initial conditions were as follows:

Flow	447 scfh
Temp	400°F
Pressure	100 psig

Figure 9 - Cross Flow Filter WCXF4 in Mount Prior to
Test at METC

The resulting filter pressure drop was about 2.8 in wg at 1.8 ft/min. Some difficulty was experienced in subsequent efforts to boost the system gas temperature with the methane fired combustor because of difficulty in getting the methane heater lit. By about 2:15 p.m. the methane combustor was operating in a stable fashion and efforts proceeded with the heat up of the filter system up. At this time the system conditions were:

Flow	1150 scfh N ₂
Temp	350°F
Pressure	80 psig

The filter pressure drop at this point in time was measured at 5.3 in wg at a filter velocity of about 4.5 ft/min. The system was gradually heated to higher temperatures throughout the afternoon. At 5:30 p.m. the temperature was 920°F at a flow of 2280 scfh. From this point until 12:00 midnight the nitrogen flow was gradually reduced to the planned test flow of about 1050 scfh. At 12:00 midnight the process gas was brought on line at a flow of 1050 scfh at 250 psig with the temperature at 927°F which was as high as could be obtained. The initial pressure drop across the filter was about 4 in wg.

Figures 10 and 11 present the pressure drop data for the next 48 hours of operation. As can be seen, the first cycle was of a very long duration lasting 10-1/2 hours. During this time the filter pressure drop rose from 4 to 14.3 in wg. During this time the inlet samples indicated dust concentrations that ranged from 875 to 1900 ppm, and the filter velocity was 2.75 ft/min. The filter was pulse jet cleaned back to the baseline pressure drop of 4.0 in wg. As can be seen in Figure 11 subsequent cycles were somewhat shorter in duration, as is always the case with a new filter in the conditioning stages. Except for the initial sample, efficiencies were seen to remain fairly constant at about 99.5 - 99.8%.

- Cross flow WCXF-4 (9/11/85) T = 1200°F, P = 250 psig, V_f = 2.74 ft/min.

Figure 10 - Cross Flow WCXF4 (9/11/85)

Curve 750888-C

- Crossflow filter WCXF-4 (9/17-18/85) T=1200°F, P=250 psig

Figure 11 - Cross Flow Filter WCXF4 (9/17-18/85)

Testing continued in a smooth fashion throughout the remainder of 9/11 until 11:45 p.m. (hr 23.5) when the ignitor on the gas combustor blew out of its fitting, thereby forcing a system shutdown. By the time the system was ready to come back on line the gasifier developed a clinker and this period of test was shut down for the next several days.

9/16 - 9/17

By Monday 9/16 the required repairs to the system had been carried out and the system preheat was started. By 4:00 pm. the filter temperature was at 625°F with 1000 scfh of N₂ at 250 psig. The filter pressure drop was 3.5 in wg. The electrical process gas heater had been taken off line and all of the gas boost heating was being provided by the new gas direct fired heater. System temperature was gradually brought to about 1200°F by 5:30 a.m. on 9/17 at which time the process gas was brought on (Time = 24 in Figure 11). With process gas on and a typical inlet concentration of 450 ppm the pressure drop rose gradually from about 6 in wg to 10 in wg at 1:30 p.m. (hr 31). At this time one of the flexible hose connections in the process gas line failed at a flange weld, and the system was forced off line for a short period for repairs.

By 5:15 p.m. the N₂ flow was back on at 910 scfh and the temperature was 422°F with a system pressure of 110 psig and a filter differential pressure of 5.3 in wg. By 10:30 p.m. that evening the system was returned to process gas flow at 1150 scfh and as indicated by the trace at hour 31, Figure 11, the pressure drop cycle was continued at the point at which it was interrupted. At 2:45 a.m. 9/18 the ninth cleaning pulse to WCXF4 was administered as the pressure drop had risen to 15.1 in wg. At a flow of 1150 scfh the base line pressure drop was established at about 7.5 in wg. At this time the flow was brought to 1200 scfh or a velocity of about 3.2 ft/min.

Over the next seven hours testing proceeded smoothly with a pressure drop cycle of 8.5 to 16 in wg over roughly 90 min periods with inlet loadings of about 300 ppm. At 10:00 a.m. (hr 42.5) the system flow was increased to 1400 scfh (velocity of 3.7 ft/min). The baseline pressure drop was seen to increase proportionally to about 10 in wg. Over the next several hours and cycles testing generally went smoothly, however, there were several unexplained bumps in the pressure drop traces (hr 42.5, 44.7, 46, 47). The nature and cause of these spikes is not known. At 3:00 (hr 48) the filter was cleaned with a series of three pulses, the first being a standard 300 psig reservoir, which the second two were from a 350 psig reservoir. Some improvement in cleaning was realized with the higher pressure pulses as the baseline was driven down to 5.3 in wg.

At 4:00 p.m. on 9/18 the planned 50 hr run on desulfurizer gas was completed and the system was switched back to straight coal gas. In this process a plug occurred in the flow control valve and caused a short excursion in the system. At 7:40 p.m. the process gas was brought back on line and the filter experienced a sharp spike in pressure drop to 42 in wg (Figure 12). The filter was immediately pulse cleaned and the pressure drop returned to 12 in wg. With the system nominally at 1750 scfh, 1400°F and 250 psig the base differential pressure was approximately 12 in wg. Over the next 2-1/2 hours the filter operated between 12 and 30-32 in wg in a relatively stable fashion. At 10:00 p.m., however, the sampling system developed a problem as it became overheated and began to sag. This caused an immediate shut down for repair.

Since the system was down a decision was made to modify the combustor system so that it could provide all of the heating required to achieve a 1600°F filter temperature (previous runs could only reach 1400°F max.). It was also

Figure 12 - (9/18/85) 19:30 to 22:00 Hrs WCXF4

decided that the test vessel should be moved closer to the heater outlet in order to avoid some of the temperature drop previously experienced between the combustor outlet and filter inlet. These modifications precluded any further testing in the month of September.

Since the system was going to be down for a period of a few weeks, and since some constant penetration had been observed throughout the test, a decision was made to open the vessel and inspect the filter element.

The element "as removed" appeared to be in pretty good condition and is shown in Figure 13. After some cleaning, however, it was observed that a delamination had occurred with the crack crossing the back face of the filter as shown in Figure 14. Since such delaminations usually only cause leaks at the crack at the front sealing face, and since we did not have any clearly superior filters available, and since we wanted to accumulate significant test time on one element, we made a decision to plug the corrugation through which the leak was thought to be occurring and to proceed with the test using this element. Figure 15 presents a photo of the repaired element prior to installation in the vessel.

Testing at METC during October

After repairs had been made the filter was mounted and its flow/pressure drop characteristics were determined at ambient conditions. Figure 16 presents the results of this test and indicates the fact that the permeability of the filter had been reduced by about a factor of 2 in its 50 hour test exposure.

Figure 13 - Cross Flow Filter WCXF4 AS Removed from METC Test

Figure 14 - Cross Flow Filter WCXF4 Brushed Clean After METC
Test Shows Crack Through Back Wall

Figure 15 - Cross Flow Filter WCXF4 After METC Test Showing Patch at Clean Face Channel

Cross Flow WCXF4 New and After Test at METC

T=70 F, P=0 psig

Figure 16 - Flow vs Pressure Drop for Cross Flow Filter
Before and After 50 Hr Exposure to Dust

During the first three weeks of October major changes were carried out at the METC test facility. In these the electrical in-line process gas heater was replaced with a gas fired combustor heater and the W filter vessel was moved about 10 ft closer to the heater in an attempt to provide higher gas inlet temperature to the filter. On 10/22 Westinghouse technicians were at METC to rewire and replumb instrument lines to the vessel in its new position in preparation for restart of the test program.

10/25 - By Friday 10/25 the entire system was prepared for test. At 9:50 a.m. attempts to light off the new combustor were initiated. Unfortunately it proved impossible to sustain combustion for more than about 24 sec. After an entire day of work the trouble was determined to be a bad temperature transmitter. It was replaced and the next start-up was scheduled for Wednesday, October 30.

10/30 - 11/1 - At 9:15 a.m. on 10/30 the system was ready for restart. At this point in time the filter system flow was 744 scfh of N_2 at 250 psig with an inlet temperature of 1615°F. At these conditions the filter face velocity was about 2.5 ft/min and the pressure drop across the filter was 9 in wg. At this time it was noted that one of the three heater legs in the filter vessel was not operating correctly. Additionally, some confusion existed about the actual flow in the system because of a computer problem with the ADAC system. By early afternoon the flow problem had been resolved and the filter was brought on line with actual process gas.

The start of this portion of testing is shown in Figure 17 as Time = 0 in the top chart. At 13:30 the system flow was at 1750 scfh, the pressure at 250 psig and the inlet gas was at 1520°F. These conditions yielded a filter face velocity of 5.6 ft/min and a base pressure drop of 12.3 in wg. It should be noted that at these conditions

Curve 751291-C

Figure 17 —Crossflow filter WCXF-4 (10-30/10-31-85) $T = 1500^\circ\text{F}$, $P = 250$, $V_f = 5.49 \text{ ft/min}$.

Curve 751292-C

Figure 17 - Crossflow filter WCXF-4 (10-31/11-1-85) $T = 1500^\circ\text{F}$, $P = 250$, $V_f = 5.49$ ft/min.
(continued)

Figure 17 - Crossflow filter WCXF-4 (11-1-85) $T = 1500^{\circ}\text{F}$, $P = 250$, $V_f = 5.49 \text{ ft/min}$
(continued)

1166 scfh was coming from the combustor while only 578 scfh was actual process gas. A METC sample at the filter inlet indicated that over the first two hours the average dust concentration was of 417 ppm. During the next 4 hours, two additional samples indicated dust loadings of 770 and 357 ppm as shown in Figure 17. During this time the dust feeder was not on.

The first pressure drop cycle was relatively long, as is typical of a cleaned filter. It lasted about 2 hours, going from 12.3 to 24 in wg. At this time it was pulse jet cleaned with a single pulse that returned the base pressure drop to 12.1 in wg. The pulse was an 0.2 sec pulse from a 350 psig reservoir. The pulse produced a 2.4 psig pressure differential from the inside (clean side) of the filter to the dirty side, as determined by a high speed differential pressure transducer.

The first 6 hours proceeded in a typical fashion for a cleaned filter in an equilibrating period. Baseline pressure drops gradually rose a few inches to 14 or 15 in wg, with the trigger pressure drop set at about 30 in wg. During this time the operating technician chose to raise the pulse reservoir pressure to 380 psig, and to give 2 pulses per cleaning.

At 19:15 on 10/30 METC personnel initiated dust feed (time = 0 middle chart of Figure 17). Over the first three hours of dust feed there was very little difference in filter performance as indicated by the pressure drop traces. METC samples during this time indicated what seems to be an anomaly, in that the inlet loading remained essentially the same as the previous 6 hours with no dust feed. This was also consistent with the pressure drop behavior noted. These samples also indicated a very low efficiency of 88.7% which we find difficult to rationalize.

After about 3-1/2 hours of dust feed (right after a sample was completed) the filter system became quite unstable with the pressure drop rising from 10 to 50 in wg in a period of 4-5 minutes. This upset persisted for about one hour, abated for an hour (Time = 4.7-5.7) and then repeated again for an hour. During this period the operating technician raised the pulse pressure first to 400 psig and then to 440 psig, yielding a 4.4 psid cleaning pulse within the filter.

After these two upset episodes, the system settled into a stable operating mode with cycles between 10 and 40 in wg lasting about an hour.

We are not certain about the origin of the upsets but speculate that the dust feed into the system accumulated somewhere between the feeder and the filter for 3 to 4 hours and then broke loose during the pressure bump caused by the sampling system.

From time = 10 to 15 the operator gradually reduced the trigger pressure drop from 40 in wg to 20 in wg so that the operating cycles were from 10-20 in wg over roughly 30 min periods. In the steady period from time = 7 to 25 inlet concentration ranged from 1200 to 3600 ppm, and measured efficiencies ranging from 97 to 99.4% with an average of 98.1%. These efficiencies were evidence of some persistent flaw in the filter or its seals. From hour 25 to 26.5 the system experienced a minor upset which caused rapid pressure drop rises, however, the problem passed soon and the system was returned to stable conditions within an hour.

The remainder of this 50 hour test proceeded smoothly as indicated in Figure 17. Only one minor perturbation occurred at time = 45.8 (17:00 on 11/31) when the combustor was momentarily shut down in an unsuccessful attempt to install a six position manifold for the methane fuel tanks.

In summary Test #5 ran very well, demonstrating stable operation between 10 and 20 or 30 in wg at 5.5 ft/min with cycle time from 30 to 60 minutes and inlet loadings from 1000 to 4000 ppm. The filter also demonstrated its ability to survive upset conditions and return to stable operation. The single negative aspect of the test was the presence of a leak in the system as evidenced by the lower than expected efficiency of about 98.7%.

11/1 Test #6

At the end of the 50 hour test sequence number 5, the system was prepared for test sequence #6. This sequence called for operation at twice nominal filter velocity with straight, undesulfurized gas from the gasifier. A decision was made to operate the filter unit at 150 psig instead of the nominal 250 psig, in order to make better use of the bottled methane that had been used to fire the in-line process gas reheater. Accordingly, at 22:15 on 11/1/85 the system pressure was at 150 psig, the flow set to 2200 scfh of process gas with a filter inlet temperature of 1408°F. These conditions yielded a filter face velocity of 10.7 ft/min and a base pressure drop of 10 in wg. This point in time is shown as T = 0 in Figure 18. At 22:45 the system was switched off of process gas, and back to N₂ as there was a minor problem with operation of the gasifier. At 00:35 on 11/2, (T = 2.6) the system was back online with process gas.

During the next hour and a half, the system temperature gradually rose from about 960°F to the set point inlet temperature of 1600°F. During this period the filter was cycled twice first from 19 to 9.8 in wg and then from 22 to 16 in wg using a 250 psig pulse source which generated a 3.4 psid cleaning pulse within the filter. The cleaning pulse pressure had been reset to the lower value because of the new system operating pressure of 150 psig.

Curve 751289-B

Figure 18 - Crossflow filter WCXF-4 (11-1/2-85) T = 1400°F, P = 150 psi, V_f = 11.65 ft/min

From hour 4 to 6 (Figure 18) the system ran smoothly with roughly 30-40 minute cycles from 16 to 24 in wg. During this time the operator increased the pulse pressure from 250 to 300 psig which resulted in internal pulse pressures of 4.2 psid.

At 04:20 on 11/2 (Time = 6) dust feed to the filter was initiated at a rate of 0.35 Lbm/hr which was intended to give an inlet concentration of 2100 ppm. In fact, the initial 4 hours inlet sample indicated an initial loading of only 660 ppm. There may be some explanation for this reading in that the inlet sample valve was determined to have been set incorrectly at 06:00 (Time 1.9 bottom trace Figure 18). Resetting of the valve caused the spike shown in the pressure drop trace at this point.

The first pulse jet cleaning after dust feed was initiated occurred at 05:25 and was significant in that the filter pressure drop was reduced from the trigger of about 32 in wg to a base 9.7 in wg. This was considerably lower than the previously observed stable base of about 16 in wg. In addition, the rate of pressure drop rise was significantly lower after this cleaning sequence indicating the probability of a serious failure of the filter. Over the next 6 hours the pressure drop traces and outlet samples continued to indicate a serious problem with the filter, so at 11:30 on 11/3/85 a decision was made to stop testing and inspect the filter.

On 11/4 Westinghouse technicians opened the filter vessel and removed the filter element. A visual examination of the filter in its as removed condition revealed several failure sites as shown in Figure 19. At least three delaminations could be observed and at least one break across a filtering flat could be seen. Additionally a gasketing failure had occurred at one of the filter failure points as

Figure 19 - WCXF4 As Removed from METC Test 11/4/85
Shows Signs of Failure By Delamination and
Breaks Across Filter Flats

shown in Figure 20. When the element was brushed off it could be seen that the three delaminations had breached the back face of the filter as shown in Figure 21. It should be noted that the middle delamination had existed at the re-start of this test. When the filter was returned to Westinghouse and removed from the mount it was found to have delaminated along 3 surfaces and broken across the filter flats at two surfaces as shown in Figure 22. Figures 23 and 24 present photos that demonstrate the two failure types observed.

One curious observation made was that the dust in and on the filter was light brown rather than the usual black char like covering. We have no explanations for this, at this time.

In order to proceed with testing, another filter element (WCXF5) was prepared for installation. Additionally, it was determined that the power leads to the heaters had embrittled near the heater again, and new provisions were made in an attempt to avoid this problem.

Figure 20 - WCXF4 After Test at METC Showing Gasketing
Failure at Delamination

Figure 21 - WCXF4 After Test at METC Showing Delamination
Failures Across Back Face

Figure 22 - WCXF4 After Test and Disassembly from Mount
Showing Three Delamination Sites and Filter
Flat Breaks

Figure 23 - WCXF4 - Typical Failure by Delamination

Figure 24 - WCXF4 Failure by Break Across Filter Surface

PROJECT STATUS FOR NOVEMBER

TASK 1 - Testing at METC

Testing at the end of October had been halted at the beginning of test #6 because of a complete failure of filter element WCXF4, as described above. The only remaining filter element suitable for test was, therefore prepared for test. This element had been received in late August but had not been chosen for test because of a slight rippling that had occurred in the top two layers near the sealing face of the element. This element had been fired, dipped in a slip coat and then given a high temperature refire. The resultant back face appeared to be quite good with a glassy coating, however, the front face was suspect due to the rippling. In preparation for test the back side of the flanges had been ground smooth and parallel with the front sealing face, and several small areas on the side face of the element had been patched with ceramic adhesive as shown in Figure 25. One additional aspect of WCXF5 that had been noted was the fact that the repeated high firing had decreased the permeability significantly so that the resultant pressure drop at a given flow was somewhat higher than we would have desired as shown in Figure 26.

WCXF5 was installed in the test system in early November as the unit was prepared for restart. Additionally, the filter vessel heater wire connectors were replaced where they had embrittled in the previous test. As shown in Figure 27, only the bent and twisted ends nearest the electrical connection to the tube heaters had embrittled. In an attempt to remedy this problem, 3/8" inconel rod by 1-1/4 inch long was drilled and tapped for screwed connection to the heater. The other end was prepared to accept the power leads without bending or twisting, and was located as near the cool filter vessel wall as possible as indicated in the sketch of Figure 28.

Figure 25 - WCXF5 Prior to Test at METC

Clean Pressure Drop of Cross Flow Filters

ambient conditions, no exposure to dust

Figure 26 - Relative Pressure Drops of The Filters
Tested at METC

Figure 27 - Heater Power Leads Embrittled at Ends Near Heater

Figure 28 -

Inconel Rod Used To Connect Heater Power Leads To Heater Rods

11/6,7,8

During the evening of 11/5 the gasifier was brought on line, and attempts were made to start test #6 at 03:00 on 11/6. At this time the filter system was operating on heated N_2 at 2200 scfh at a pressure of 150 psig. In the hours between 03:00 and 07:30 problems were experienced with the ignition of the combustion. Eventually the filter system was shut down for inspection of the gas heater. When the combustor was opened the ignitor was found to be corroded badly and the ceramic casting in the combustor had cracked severely. The appropriate repairs were made by DOE personnel and by 21:45 of 11/6 the filter unit was back on hot N_2 . At 21:53 the flow was 2200 scfh and the temperature and pressure were 520°F and 150 psig. The pressure drop across the filter was noted to be 17.4 in wg. These conditions correspond to a filter face velocity of about 6.2 ft/min. At 22:45 the flow was reduced to 1200 scfh in preparation for going on product gas. At a flow of 1200 scfh and at a temperature and pressure of 890°F and 150 psig the filter pressure drop was 10.9 in wg. At 22:48 the process gas was brought on line. The low flow of 1200 scfh was intended to be the first of several steps of increasing flow during a conditioning period for the filter.

At 00:18 the flow was increased to 1600 scfh and the first pulse jet cleaning was administered. This is shown at Time = 4 in Figure 29. The filter pressure drop was reduced from 29.3 to 5 in wg by the 0.1 sec pulse from a 200 psig reservoir. At 00:35 a second pulse (from a 250 psig reservoir) reduced the pressure drop from 20.2 to 3.5 in wg. It was noted that this pulse generated a 2 psid cleaning pressure rise inside the filter element.

Curve 751293-C

Figure 29 - Cross flow filter WCXF-5 (11-7-85), $T = 1400^\circ\text{F}$, $P = 150$, $V_f = 9.0 \text{ ft/min}$

Figure 29 - Cross flow filter WCXF-5 (11-7/19-85), $T = 1400^\circ\text{F}$, $P = 150$
(continued)

Curve 751288-B

Figure 29 --Crossflow filter WCXF-5 (11-19-85) $T = 1400^{\circ}\text{F}$, $P = 150$ psi, $V_f = 6.43$ ft/min
(continued)

At 01:31 ($T = 5.3$) the flow was increased to 1600 scfh and the base pressure drop increased to about 6 in wg at the new face velocity of 6.2 ft/min. This flow was maintained for about 2 hours and three steady cycles from about 5 to 30 in wg were observed. At 03:30 the flow was increased to 2200 scfh or about 10.4 ft/min at 1100°F, and the gasifier gas flow was initiated. Over the next two hours the system operated in a steady fashion with 13 cycles between 30 and 39 in wg over 10 to 15 min periods. A sample taken during this period indicated an inlet loading of 817 ppm and an efficiency of 97.19%. Cleaning pulses during this period were at 300 psig and generated pressure rises of 3.5 to 4 psid. A decision was made to lower the gas flow in order to achieve slightly longer cycle times and a lower baseline. This was carried out in two steps from 2200 to 1900 scfh at 05:33 ($T = 9.2$) and then from 1900 to 1725 at 06:25 ($T = 10.2$).

At the flow of 1725 scfh the filter system temperature settled out at about 1200°F and gave a filter face velocity of about 8 ft/min. At these conditions the system began a fairly long steady period of operation in which the cycles between 25 and 40 in wg over a 15-20 min period, with an inlet dust concentration of 800 to 1750 ppm and typical filter efficiencies of about 98%. Over this period there was some gradual increase in baseline pressure drop as it rose to about 30 in wg. At 17:33 ($T = 21.2$) there was a 90 min disturbance in the filter behavior that was associated with the outlet sample being taken at this time. During this period pressure drop and its rate of increase decreased significantly as can be seen in Figure 29. After the outlet sample was finished, the pressure drop increased above its previous value as did the rate of increase. Pressure drop cycles shortened to 7-10 min to go from about 40 to 48 in wg. We have no explanation for this behavior, but it persisted for the next two hours until 22:00 ($T = 25.8$) (11/7/85) when the system was brought down because of gasifier operating problems.

11/17/85

The system was next started on 11/17/85. Flow through the filter began with hot N_2 at 14:30 with the following conditions: flow at 1750 scfh, at $910^{\circ}F$, with a pressure of 150 psig and a filter pressure drop of 35 in wg. A series of pulses reduced the pressure drop to 14 in wg, and during the three hour warm-up on N_2 the pressure drop gradually crept up to about 19 in wg. At 17:40 ($T = 25.8$) the produce gas flow was initiated with no dust feed. Inlet and outlet samples taken indicated an inlet loading of 388 ppm and an overall efficiency of 99.3%.

Soon after the start of product gas, ($T = 27.9$) a leak was discovered in the steam heating lines inside the dust feeder vessel. This leak resulted in wet dust and had an undetermined effect on the filter. By 21:20 ($T = 29.3$) the leak was repaired, fresh dust was loaded and the feeder set to deliver 0.25 lbm/hr of dust. Subsequent samples, however, only indicated loadings of 367 and 280 ppm when in fact they should have been in the neighborhood of 2000 ppm.

The next seven hours of operation ($T = 30$ to 37) were characterized by fairly short cycles of 5-10 min between pressure drops of 40 to 45 in wg. This cycle time and its shape (very steep initial rates of rise) were indicative of a poorly cleaned filter in which only a small fraction of the available area was being cleaned.

At 04:15 ($T = 36.8$) on 11/18 it was determined that the outlet sample line was leaking, and a decision was made to bring the system down for repair. During this time it was determined that the steam heating lines inside the dust feed vessel had failed again and were injecting large amounts of steam into the system. That large amounts of water had been thrown into the system was confirmed when the differential pressure lines for the filter had to be opened and drained.

By 18:20 on 11/18, repairs had been made and the system was back on hot N₂. By 19:30 the N₂ flow was up to 1750 scfh and the filter inlet temperature was 1160°F and the filter pressure drop was at 22 in wg. Over the next 2 hours there were a few problems with the bypass valve not functioning correctly, but by 21:41 process gas was brought to the system, at a flow of 1540 scfh (T = 36.8). Over the initial hour the pressure drop and its rate of rise were quite high and steadily increased. In order to get better control of the situation the system flow was lowered to 1400 scfh at 23:02 (T = 38.2). This yielded a filter velocity of 7.4 ft/min and reduced the baseline pressure drop from 40 to 35 in wg. Succeeding cycles gradually lost ground over the next 4 hours as the baseline slipped up to 43 in wg, and cycle times to 45 in wg were only 5-10 min with inlet loadings of only 300-500 ppm. At 02:45 (T = 42) on 11/19 the flow was again reduced, this time to 1225 scfh, or a filter face velocity of 6.4 ft/min. Accordingly, the base pressure drop decreased from 43 to 36 in wg, but it gradually increased over the next several hours to 44 in wg. During this time the trigger pressure was allowed to rise to 48 in wg, but even with the lower flow, the base line gradually rose over the next several hours until at 03:30 (11/9) (T = 47.8) the cycles were only 7 to 10 min to go from 44 to 48 in wg. It also appeared that something had gone wrong with the dust feed system as the sample taken from 06:17 to 07:15 only indicated an inlet loading of 22 ppm. As indicated in Figure 5 at T = 48-49 the filter appeared to be in serious trouble and a decision was made to shut down for inspection of the element at the end of the 50 hour test.

During the last several hours DOE personnel attempted to determine the problem with the dust feed, which again showed up as being very low with an inlet concentration of only 40 ppm.

At 14:00 the process was shut down and a forced cool down was initiated by maintaining an N₂ flow through the filter.

At approximately 21:00 on 11/19, the filter had cooled sufficiently to be removed from the system.

The filter was found to be encrusted with a relatively hard, flaky coating of char, which was quite different from the powdery dust deposits observed in previous tests. Figure 30 presents a photo of the filter in its "as removed" condition. Virtually all of the channels appeared to be plugged in large part by the same crusty deposit found on the outer surface. As mentioned earlier, the deposit could be scraped off in large chips and was quite unlike the powdery coating of dust observed earlier. Our current speculation is that this crusty deposit was formed during one of the times during which the steam lines in the dust feed vessel leaked and caused a physically wet mud to form on and in the filter.

The filter was brushed and vacuumed in order to remove the exterior deposits. The interior deposits were removed by running pipe cleaners through the channels and vacuuming out the dislodged flakes. Figure 31 shows the condition of the cleaned filter prior to its being installed in the system.

While the system was down METC personnel determined that the rotation of the dust feeder screw was incorrect and had caused it to detach itself from the motor drive shaft. Additionally, it was determined that considerable water had condensed within the vessel and caused the powder to become wet. These situations were corrected and the unit was made ready for continued test on 11/20/85.

Figure 30 - WCXF5 After Initial Testing at METC
Dust Deposit "Crusty" Unlike Usual Char Deposits

Figure 31 - WCXF5 After Deposits Removed Prior to Being
Reinstalled for Final Test Sequence

11/20 - 22/85

Throughout the day of 11/20 METC operating personnel experienced difficulties with the gasifier system. When it was determined that there would have to be a significant shutdown for maintenance on the system, a decision was made to carry out the last filter test segment using heated N₂ and injected char. Accordingly at 00:45 (T = 0 Figure 32) on 11/22 the system was at a flow of 1750 scfh with a temperature of 991°F at a pressure of 150 psig. Dust flow was initiated at a rate of 0.28 lbm/hr anticipating a loading of about 2000 ppm. At these conditions the filter face velocity was about 7.1 ft/min and the baseline pressure drop was 13 to 14 in wg.

As indicated in Figure 32, the resulting test sequence proceeded very well with stable pressure drop cycles between 14 and 25 in wg. These lasted about 40 to 50 minutes, depending on the inlet concentration which ranged from roughly 1500 to 4400 ppm over the established portion of the test and which averaged about 2800 ppm. Cleaning pulses throughout the duration of this test sequence consisted of a single 0.1 sec pulse from a 250 psig pressure reservoir. This constantly yielded a cleaning pressure rise in the range of 3.1 to 3.5 psid within the filter element.

During this test the measured filter efficiencies ranged from 98 to 99.6% and averaged 98.9%.

During the last several hours of the test the pressure drop cycles stretched out considerably as the dust concentration diminished as can be seen in Figure 32. At 15:00 on 11/22 the test system was shut down. This final test segment only included 38 hours, however, its end point

Curve 751287-8

Figure 32 -Cross flow filter WCXF-5 (11-21-85), $T = 1200^{\circ}F$, $P = 150$ PSIG, $V_f = 8.1$ ft/min

Figure 32 - Cross flow filter WCXF-5 (11-21/22-85) . $T = 1200^{\circ}\text{F}$. $P = 150$ PSIG. $V_f = 8.1$ ft/min
(continued)

was determined by previously scheduled vacation time for the majority of the operating personnel. An agreement between DOE project management personnel and Westinghouse test engineers was reached that agreed this was an appropriate point to conclude the cross flow filter testing.

On 11/25/85 Westinghouse test personnel returned to METC and removed the filter element from the unit for inspection. Figure 33 presents a photograph of the filter as removed. It can be seen that the element was in excellent condition and remarkably free from deposits. The element was easily vacuumed clean for inspection and no cracks or delaminations were detected. Figure 34 shows the cross flow filter WCXF5 after preliminary cleaning.

Figure 33 - WCXF5 As Removed From Filter System After Final Test Sequence

Figure 34 - WCXF5 After Final Test Sequence and Preliminary
Cleaning - No Delaminations or Cracks Observed

*mil's traces &
Rough removed,
cl*

END

**DATE
FILMED
8 / 19 / 92**