147
0-13-75
ANCR-1222

0171535

UC-13

IDAHO NATIONAL ENGINEERING LABORATORY

IDAHO GEOTHERMAL R&D
PROJECT REPORT FOR PERIOD
JANUARY 1, 1975 TO MARCH 31, 1975

J.F. Kunze

PREPARED FOR THE
ENERGY RESEARCH AND DEVELOPMENT ADMINISTRATION
IDAHO OPERATIONS OFFICE UNDER CONTRACT E (10-1)-1375

DATE PUBLISHED—JUNE 1975

1
Master
Aerojet Nuclear Company

IDAHO FALLS, IDAHO - 83401

DISTRIBUTION OF THIS DOCUMENT UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

Printed in the United States of America
Available from
National Technical Information Service
U. S. Department of Commerce
5285 Port Royal Road
Springfield, Virginia 22161
Price: Printed Copy \$5.45; Microfiche \$2.25

— LEGAL NOTICE —

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the Energy Research and Development Administration, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

Aerojet Nuclear Company

550 SECOND STREET
IDAHO FALLS, IDAHO 83401

July 31, 1975

To Recipients of Geothermal Progress Report

TRANSMITTAL OF JANUARY TO MARCH INEL GEOTHERMAL PROGRAM REPORT - Kun-439-75

Your continued interest in the Idaho National Engineering Laboratory's Geothermal Research and Development efforts is appreciated. We wish to apologize for the late mailing of the enclosed issue, a situation brought about in part by the moving of our printing facilities some 45 miles to the Central Facilities Area of the reactor testing station.

During the interim, the geothermal program has made significant progress. The April to June progress report has just been completed and submitted into the publication process. Since most of you will wish to receive information on the progress to date, the summary section from this second quarter report is attached to this letter.

It is our hope that the full second quarter progress report will be distributed in a more timely fashion. In the interim, if you have specific questions of concern, please feel free to contact me or one of our staff listed on the title page of the attached report.

Your understanding is appreciated.

Dr. J. F. Kunze, Manager
Geothermal Projects

Idaho National Engineering Laboratory

CS

PROGRESS REPORT SUMMARY FOR PERIOD APRIL 1 TO JUNE 30, 1975

(FULL REPORT TO BE DISTRIBUTED IN SEPTEMBER)

1.0 SUMMARY

Drilling on the first deep exploratory-production well was terminated on April 1, at a depth of 4987 ft, followed by logging and then flow testing to within the capacity of the reserve pit. Fluid temperatures within the production zone were 294°F (146°C) and artesian flow (with no back pressure at surface) was 600 gallons/minute (39 l/sec).

On March 18, the site for the second well (RRGE #2) was selected, 4000 ft northeast of the first. Site preparation began on April 11, and drilling on RRGE-2 commenced on April 26. A 15 in. diameter surface hole was drilled to 915 ft by April 27. Surface casing was installed and successfully cemented. Drilling of the second well using mud as the drilling fluid proceeded smoothly from below the surface casing to a depth of 4229 ft. The question of resource detection at that location remained an uncertainty (with mud in the hole). Coring at this depth showed some fractured and altered calcified sandstone. At that depth casing (13-3/8" diameter) was set and cemented.

Drilling below the casing proceeded using water as the drilling fluid. The well developed small spontaneous flow on May 27, while drilling just 20 ft below the bottom of the casing. Larger flows developed at about 4350 ft on May 28. At the 4350 to 4370 ft depth, a fractured zone was encountered, delivering approximately 400 gpm through the main flowlines. Drilling proceeded to 4807 ft, when a brief sustained flow test of 550 gpm was measured. Maximum downhole fluid temperature of 284°F was measured.

Drilling operations were terminated on June 26, 1975, at a depth of 5988 ft from ground level. Various strata of basement type quartzitic rock had been encountered from a depth of 4800 ft to the total depth of the well. Some indication of fracturing had been detected from the 5000 to 5200 ft region, but flow testing showed no substantial enhancement of the artesian flow from the well due to production from this depth. Flow testing and an extensive array of final logs on the well were run on June 27-29. Peak artesian flows from the well are of the order of 800 gpm, with temperatures from the 4300 ft depth to the total depth being 293 to 296°F. It appears that the bulk of the flow is occurring from the 4250 to 4800 ft region of the well.

With regard to effective economic utilization of ~300°F geothermal water, an examination of non-electric utilization of the electric plant outlet water was made. Various processes were examined for their potential for direct non-electric use. Heat balances of various industrial processes supplied by geothermal water appear viable both technically and economically, for a community similar to Raft River. A suitable balance between electric and non-electric utilization results in overall reduced energy costs and a mix of industrial user energy needs consistent with a remote area agricultural based economy.

For the Boise Space Heating Project, geochemical, geological, and geophysical studies continued and have been used in the selection of several shallow well drilling sites. The feasibility/conceptual design of heating and ventilation building modifications was completed. Cost estimates agree with earlier predictions of economic practicality of low temperature (107°F or 77°C) geothermal water to provide heat.

NOTICE
This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Energy Research and Development Administration, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

ANCR-1222

Nonnuclear Energy Sources and
Energy Conversion Devices
TID-4500

GEOTHERMAL R&D PROJECT REPORT FOR
PERIOD JANUARY 1, 1975 TO MARCH 31, 1975

Prepared by Idaho Geothermal Project

J. F. Kunze, Manager, INEL Geothermal Projects
L. G. Miller, Manager, Field Operations
J. F. Whitbeck, Manager, Energy Conversion Systems Design
A. S. Richardson, Manager, Non-Electric Applications
R. C. Stoker, Geological Engineer
S. G. Spencer, Environmental Engineer

Assisted by personnel in the Research and Engineering Departments of Aerojet Nuclear Company; C. R. Nichols, Boise State University; personnel of University of Utah and Allied Chemical Corp. (INEL)

SUBMITTED TO THE IDAHO OPERATIONS OFFICE AND THE DIVISION OF GEOTHERMAL RESEARCH
U.S. ENERGY RESEARCH AND DEVELOPMENT ADMINISTRATION

AEROJET NUCLEAR COMPANY

Date Published - June, 1975

PREPARED FOR THE U.S. ENERGY RESEARCH AND DEVELOPMENT ADMINISTRATION
IDAHO OPERATIONS OFFICE
UNDER CONTRACT NO. AT (10-1)-1375

Contract Technical Coordinator - J. L. Griffith

DISTRIBUTION OF THIS DOCUMENT UNLIMITED

ABSTRACT

The Idaho National Engineering Laboratory (INEL) Geothermal Research and Development Project was initially chartered by the Division of Applied Technology in December 1973. This report covers the period January 1, 1975, through March 31, 1975. A brief summary of the work, particularly of the Raft River Geothermal Exploratory Well No. 1 is given in Section 1.0, with more detail in subsequent sections.

TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	1
2.0 DEMONSTRATION MEDIUM TEMPERATURE GEOTHERMAL POWER PLANT PROGRAM	3
2.1 Background Information	3
2.2 Electrical Power Plant and Associated Studies	6
2.3 Environmental and Area Impact Considerations	11
2.4 Deep Drilling Program	15
2.5 Geology and Geophysics	18
2.6 Hydrology	25
3.0 ADVANCED HEAT EXCHANGER DEVELOPMENT	29
3.1 Direct Contact Heat Exchanger Development Studies....	29
3.2 Fluidized Bed Heat Exchanger Development Studies	35
4.0 NON-ELECTRIC USED OF GEOTHERMAL ENERGY	45
4.1 Introduction	45
4.2 Background Information	46
4.3 Progress During This Reporting Period	46
4.4 Boise Demonstration Geothermal Space Heating Project.	48
5.0 PLANS FOR SUBSEQUENT QUARTER	52

TABLE OF CONTENTS (Cont'd.)

Page

FIGURES

1.	Depth vs Void Fraction as a Function of Maximum CO ₂ Concentration in Liquid Phase.....	8
2.	RRGE-1.....	19
3.	RRGE-1 Geologic Cross Section.....	20
4.	RRGE-1 Profile.....	21
5.	Well Locations.....	24
6.	Drill Site and Vicinity.....	26
7.	Flow Loop Schematic.....	31
8.	Volume Model Boiler Schematic.....	32
9.	Surface Model Boiler Schematic.....	33
10.	Installed Boiler.....	34
11.	Installed Boiler.....	34
12.	Installed Boiler.....	34
13.	Fluid Sampling System.....	39
14.	Original Heat Exchanger Apparatus.....	40
15.	Present Heat Exchanger Apparatus.....	41
16.	Heat Exchanger Tank and Flow Distributor.....	42
17.	Heat Exchanger Tank and Distributor.....	43
18.	Heat Exchanger Tank and Flow Distributor.....	44

TABLES

I	Compositional Analysis of RRGE-1 Water Samples and Comparison with Other Wells in Area.....	12-14
---	---	-------

1.0 INTRODUCTION

Final preparations were completed prior to the actual deep drilling that began on January 4, 1975, at a selected site in Section 23, T15S, R26E, in the Raft River Valley of Southern Idaho. On February 1, a depth of 4632 ft was attained, and a routine logging operation was begun. Within 12 hours, spontaneous flow began to develop in the well. The well was allowed to flow freely until the completion of the logging operation, 14 hours later. At that time, bottom hole temperature was 280°F and the estimated flow at the surface was approximately 1400 gallons per minute. Because the exit 10-3/4 in. flow line no longer could carry the flow without boiling water reaching the drilling platform, the blowout preventors were closed. The well was later completed with 13-3/8 in. casing to a depth of 3624 ft, near the top of the inferred production zone. The well was then deepened to 4989 ft on March 31, primarily to gather more geologic information. The lower 500 ft was drilled through hard quartzitic-type rock from which no production appeared.

Conceptual design was initiated on a binary power plant with a double boiling subcooled cycle and a net power output of 10 MW. The conceptual design work will be completed in sufficient detail to provide a preliminary cost estimate early next quarter (April).

Design and fabrication has continued on the mobile test laboratories to be used at Raft River. The first units will be delivered to Raft River near the beginning of May, 1975. A small single tube heat exchanger has been fabricated and will be installed on well RRGE-1 to obtain initial fouling and performance data. A set of metallurgical samples installed three months ago in the Crank well have been removed for examination and analysis.

The design proceeded on the cooling ponds, the reinjection lines, and associated equipment necessary for conducting tests within the loop between the production and reinjection wells.

Additional archaeological surveys and biological surveys of the Raft River Valley are being planned with cooperation from area university staffs, in order to obtain baseline data prior to extensive flowing of either well.

With the break in winter weather, field geophysical work began on and around the Boise Front Fault, aimed at better interpretation and identification of the geothermal resource in that area. The existing heating systems in the Boise government buildings were surveyed in detail relative to their adaptability to geothermal heating. The design of conversion systems is progressing on the hot air systems.

Studies on possible short term but small scale demonstration of non-electrical uses of water from the Raft River well were initiated. Alternate methods of space heating, such as employed in areas of Klamath Falls, were being considered for future definitive studies.

2.0 DEMONSTRATION MEDIUM TEMPERATURE GEOTHERMAL POWER PLANT PROGRAM

2.1 Background Information

The area of Southern and Eastern Idaho is one of the most promising regions in the United States for near surface, economically recoverable geothermal energy. This portion of the state is divided between two physiographic regions. The Snake River Plain is typical of the volcanic rift regions of the U.S. where approximately 8% of the hot wells, geothermal springs and geysers in the Western U.S. are located. South of this is a physiographic region called The Basin and Range Province which covers Nevada, the Western half of Utah, the Southwestern half of Arizona, as well as parts of California, New Mexico, Colorado, and Montana, in addition to parts of Southern Idaho. In this Province are located more than a third of the known hot wells; geothermal springs, and geysers in the Western U.S. This region has experienced mountain thrusting in recent years and around its borders significant, recent volcanic activity is more common than within its interior.

In and surrounding this Snake River Plain portion of Idaho there are suspected to be an enormously large number of potentially valuable geothermal fields, such as the area just West of Yellowstone National Park, the Bruneau Area and the Owyhee County region. All of these are the subject of continuing studies (particularly by the USGS and the State of Idaho) to determine their geothermal potential. However, little geological data exists in most areas within 150 miles of the Idaho National Engineering Laboratory and Idaho Falls where the Energy Research and Development Administration's principal integrated contractor, Aerojet Nuclear Company, is located. One potential site, the Raft River Valley of Cassia County, Idaho, is an exception, where significant amounts of geothermal data were collected during the 1970 to 1972 period. As a typical site, representative of Basin and Range Province regions of the Western States, this area was selected in 1973 by AEC-ID, ANC, and USGS as a prime location for continuing geological, geophysical, and geothermal research, and for the possible establishment of a medium temperature, hot water, geothermal research and development power plant project. Through silica solution tests, this area has been determined to have a probable temperature for geothermal waters in the region of 150°C (300°F). These geothermal fluids are of lower temperature than those now considered to be economical for electric power generation and have been

classified by the AEC as medium temperature fluids. The huge quantities of such fluids available throughout the nation make them of enormous value for their total available energy. The area is, therefore, an appropriate location for a demonstration plant. Through the development of geothermal technology it is hoped that the economically competitive range of temperatures for electrical energy generation can be extended to lower values. The direct result being that the whole Basin and Range Province of the Western U.S. and its bordering areas would be demonstrated to be a commercially interesting geothermal field as well as resulting in a general increase in the potential value of all geothermal resource areas worldwide.

The occurrence of boiling water in the Raft River area near Malta, Idaho prompted the Raft River Rural Electric Cooperative to initiate, in 1971, preliminary geological investigations pertinent to the possibility of establishing a geothermal plant in the area for the production of electricity. Simultaneously the Cooperative management began to secure geothermal leases on the private land owned by its members. In 1973, Aerojet Nuclear Company began a preliminary engineering and feasibility study, gathering additional geophysical information from the Raft River Valley. The USGS had initiated a basic geological study of the area beginning in 1970, and substantially increased the effort in 1973, including gathering of geophysical data.

Unlike the anomalous Geysers geothermal steam field in Northern California where the enthalpy of the hot dry steam is high, the Raft River Valley is a medium temperature hot water field of comparatively low enthalpy representative of much of the identified geothermal potential resources in the Northwest. Hot water sources of approximately 300°F have an enthalpy of approximately 270 Btu/lb which is significantly lower than obtained from producing steam fields like the Geysers and Lardarello, where the exit fluid from the wells has 1100 Btu/lb. The hot water fields of Cerro Prieto, Mexico and Wairakei, New Zealand have well head fluids with about 500 Btu/lb. Hot water sources with about 270 Btu/lb are not currently attractive for commercial production of electric power. Neither the economics nor even the most economical power extraction techniques are yet unequivocally determined for these low enthalpy heat sources. However, the

large amount of energy stored in these vast reservoirs make their development very valuable. The higher enthalpy fields now currently attractive represent only about 5% of the known geothermal fields.

The Raft River area appears appropriate for demonstrating the extension of power production technology to the harnessing of the power producing potential in warm, not hot, water. With only 150°C (300°F) water anticipated, conventional steam turbine systems appear only marginal for normal applications. But, the Raft River Valley's near surface aquifer is quite cold, approximately 10°C (50°F). With such a cold temperature heat sink, 150°C water becomes quite attractive, from a Carnot efficiency viewpoint. A low boiling point organic fluid is a prime candidate for the working fluid, but the economics compared to steam has not as yet been established.

The demonstration power plant will contain a steam and/or a binary (organic fluid) cycle depending upon final temperatures and mineral content of the hot water. Initial operation of the plant is anticipated to be mid-1978. More details about the geology of the area, its apparent geothermal potential can be obtained from the report ANCR-1138, entitled, "A Low Temperature Demonstration Geothermal Power Plant in the Raft River Valley," dated February 1974.

The overall goals of the project are basically as follows:

1. To demonstrate the extraction of energy from a hydrothermal field utilizing full reinjection of the waste fluid. The reinjected fluid is to contribute to the fluid recharge of the hydrothermal field, with minimum degradation of the environment and the thermal heat source.
2. To demonstrate the design and operational characteristics of a geothermal electric power plant operating from a reservoir temperature well below the enthalpy limits now considered to be economically attractive for commercial development.
3. To consider the most efficient and effective utilization of the resource available, including non-electrical applications for the heat and/or the geothermal water itself.

2.2 Electrical Power Plant and Associated Studies

The work primarily associated with the power plant falls in the following major areas: flash steam power plant, binary power plant, water chemistry (including gas desorption and mineral deposition), test systems, and heat exchanger experiments. The progress in each of these categories is reported below.

2.2.1 Flash Steam Power Plant Studies

Analytical Studies

Analytical work continued on a computer model capable of handling a preflash and multiple power flashes. Detailed air-ejector models were completed and coupled to the flash. The model will handle both steam and non-condensables. A method of estimating dissolved gas release (three components, vapor and two gases) in each of the flasher/separation stages is also being incorporated in the flash steam model. This work will be completed during the next quarter. The program will have a general utility relative to flash steam plants (it is not restricted to Raft River conditions).

2.2.2 Binary Power Plant Studies

The dual boiling isobutane cycle has been studied for use with 300°F water. This cycle has proven to provide a high brine utilization factor and perhaps, more important, reduced sensitivity to inlet brine condition. Considering nominal inplant losses only, a brine utilization of about 5.5 MW/million pounds/hr of brine can be achieved. The superior performance and system flexibility appears achievable with a relatively small increase in heat transfer surface area. Presently, further optimization studies are being conducted. When brine supply and reinjection pumping requirements are significant and well flow rates are moderate (say about 1000 gpm) utilization becomes increasingly significant with respect to plant costs. Under these conditions and 300°F geothermal water, the binary system appears more favorable than the steam plant.

Conceptual design is underway for a power plant with a net power output (to the power grid) of 10 MW. The conceptual design work will be completed in sufficient detail to provide a preliminary cost estimate next quarter.

2.2.3 Test Systems

Design and fabrication has continued on the mobile test laboratories to be used at Raft River. The first units will be at Raft River near the end of April 1975. A small single tube heat exchanger has been fabricated and will be installed on well RRGE No. 1 to obtain fouling data as quickly as possible.

Design of cooling ponds, the reinjection lines, and associated equipment necessary for conducting tests is in progress. These tests will utilize significant flow rates from either well No. 1 or No. 2 (assuming number 2 is a successful producer), reinjection the water back into the other well.

2.2.4 Gas Desorption in the Well

The desorption of large quantities of gas from a geothermal liquid as it rises to the surface in a well can potentially cause two-phase flow conditions that would prevent or reduce well flow. The desorption is the result of the drop in hydrostatic pressure with elevation change (assuming initially saturated condition corresponding to some depth and temperature). The gas release is a function of the hydrostatic pressure, which is a function of the released gas. An analysis of this problem was made*. Typical results are shown in Figure 1 for various assumed concentrations of dissolved CO_2 . These results indicate that large void fraction may exist which would impede natural well flow. Additional work on actual flow regions will not be conducted until actual gas analyses of the Raft River water is available and the potential for substantial natural well flow is determined.

* Subcontract work performed by Energy Inc., Idaho Falls, Idaho

Fig. 1 Depth vs Void Fraction as a Function of Maximum CO₂ Concentration in Liquid Phase

2.2.5 Water Analysis Study

A water analysis of the RRGE No. 1 well was obtained after the well was cased. The casing prevents entry of water from various aquifer beds intersected by the drill hole and the following water analysis is considered to be representative of that which will be used for the RRGE geothermal plant. The figures listed in Table I are the selected average of several samples, appearing to be most representative. For comparison purposes, the analyses of two surrounding shallow hot wells (approximately 400 ft depth), Crank and BLM, and an irrigation well from approximately 12 miles northeast (Jack Pierce's well) are shown.

The dissolved N_2 and CO_2 in the geothermal water are higher than the values for these gases in water of equilibrium with air at 1 atmosphere and $20^\circ C$ (15.8 and 0.5 ppm, respectively).

The expected impact of the above geothermal water chemistry on a binary geothermal plant is described in terms of deposition, gas evolution, and corrosion-erosion, as follows:

1. Deposition

- a. The 46 ppm Si and 167 ppm $Si(OH)_4$ corresponds to 99 to 105 ppm SiO_2 . For the crystalline states of quartz or chalcedony, the likely equilibrium mineral product in the reservoir, the 105 ppm concentration in the geothermal fluid corresponds to an equilibrium temperature of $140^\circ C$. The minimum (condenser and first preheater) temperature envisioned within the binary plant are $55^\circ C$. The silica content there corresponds to super saturation of the crystalline phases but not of the amorphous phase*. Since the amorphous phase solubility is likely to control the deposition conditions, silica deposition is not expected to occur within the plant. In fact, the amorphous silica solubility curve, if it is indeed the controlling condition, would indicate that deposition would not occur even at lower temperatures to be encountered in the settling pond and the injection well. However, it should be noted that the equilibrium conditions between crystalline and amorphous silica are complex, depending, for

example, on pH condition of the water. Therefore, actual testing will be necessary before the above conclusion can be supported by fact. Concluding that silica (SiO_2) may not deposit within the plant relieves only part of the concern. Deposition of different silicates, perhaps related to corrosion products or other components of the geothermal field, requires additional investigation. However, the likelihood of a silicate problem appears small at this time.

- b. The 57 ppm Ca, 45 ppm HCO_3^- , and 8.8 ppm CO_3^{2-} correspond to supersaturated conditions (under certain assumptions) and CaCO_3 could deposit on surfaces particularly where dissolved gases are released, as for example upon discharge to settling ponds or upon entering rock at the injection site. Deposition on plant equipment (heat exchangers) can probably be avoided by maintaining gas pressure, but this strategy is not certain to work. The reason is that about 0.7 psig CO_2 partial pressure is required to maintain Ca and CO_3 in solution, but actual CO_2 content corresponds to only 0.3 psi.

In natural waters, Ca and CO_3 often remain soluble at considerable degrees of supersaturation (factors of 10 to 100) hence the supersaturated geothermal fluid may be benign in the plant.

At the point of reinjection however, one should not risk deposition of CaCO_3 even from slightly supersaturated solutions for fear of eventually restricting flow into the reinjection strata. Forced deposition of CaCO_3 from spent geothermal fluid should be achieved and the precipitate stripped from the solution before reinjection. Stripping will create a benign solid waste.

* See for instance, R. O. Fournier and J. J. Rowe, Estimation of Underground Temperatures from the Silica Content of Water from Hot Spring and Wet Steam Wells, American Journal of Science, Vol. 264, Nov. 1966, p. 685-697.

The reactivity of the geothermal fluid upon reinjection to the subsurface also depends on the oxygen content. The initially low O_2 content in the geothermal fluid should be preserved throughout all above ground operations. Particular design features may be needed where $CaCO_3$ is precipitated. Whether this concern is warranted depends on (1) how susceptible to oxidation the rocks are near the reinjection site and (2) how much the reinjected waters mingle with geothermal fluids that will be produced for power generation.

2.3 Environmental and Area Impact Considerations

Preliminary design criteria were established for an environmental monitoring system to be installed at the RRGE-1 site now that significant flows of geothermal water are available. To be included are hydrogen sulfide, radon, and CO_2 detectors, and a meteorology station, and a gauging station in the nearby Raft River. Procurement of the various system components is currently underway.

Work continued on identifying applicable federal and state environmental regulations for input to the test loop and power plant design efforts. A comparison of the relative merits of aquifer cooling vs cooling towers was made; with particular attention paid to the impact either system would have on the area. The results were coordinated with the engineering conceptual design studies.

An archeological clearance survey of the two proposed sites for RRGE-2 was conducted by the Curator of Archaeology at Idaho State University. Arrangements are being made for additional archaeological surveys and biological surveys of the valley to be performed by area university staffs.

TABLE 1
COMPOSITIONAL ANALYSIS OF RRGE-1 WATER SAMPLES
AND COMPARISON WITH OTHER WELLS IN AREA

Conditions: Cased hole, full flow and pressurized samples, 205°F (boiling temperature at elevation), samples taken after well allowed to flow freely.

	RRGE-1 ^a	Crank Well	BLM Well	Jack Pierce Well
pH	7.05-7.40	7.94	7.40	7.6
Conductivity (μmhos/cm)	2800.0	6080	3030	1720
Salinity (μg/ml or ppm)	1715.0	3360	1720	1204
Na absorption ratio †	19.5	26.8	18.3	- -
Metals: (All values in ppm)				
Ag	ND	- -	- -	- -
Al	m-t	- -	0.012 ppm	- -
B	0.2	0.25	0.15	- -
Ba	<0.4 ppm	ND	ND	- -
Be	<0.002 ppm	ND	ND	- -
Ca	57 ppm	125 ppm	52 ppm	157 ppm
Cd	ND	- -	- -	- -
Co	NO	- -	- -	- -
Cr	m-t	- -	- -	- -
Cu	t	0.02 ppm	0.02 ppm	- -
Fe	0.32 ^b	<0.02	<0.02	- -
K	26.7 ppm	32 ppm	21 ppm	16 ppm
Li	1.25 ppm	2.5 ppm	1.4 ppm	- -
Mg	0.76 ppm	0.3 ppm	0.2 ppm	18 ppm
Mn	0.07 ppm	0.02 ppm	0.02 ppm	- -
Na	400 ppm	1110 ppm	560 ppm	184 ppm
Ni	3.7 ppm	<0.05 ppm	<0.05 ppm	- -
Pb	t	<0.06 ppm	<0.06 ppm	- -
P	0.016 ppm	- -	- -	- -
Si	46 ± ppm	97 ppm	90 ppm	54 ppm
Sn	ND	- -	- -	- -
Sr	1.44 ppm	2.8 ppm	1.4 ppm	- -
Ti	t-m	- -	- -	- -

	<u>RRGE-1^a</u>	<u>Crank Well</u>	<u>BLM Well</u>	<u>Jack Pierce Well</u>
Metals:				
V	ND	- -	- -	- -
Zr	m	- -	- -	- -
Zr	ND	- -	- -	- -

Non-Metals (All values in ppm):

	<u>RRGE-1</u>	<u>Crank</u>	<u>BLM</u>
Cl ⁻	614 ^b	1900	880
Br ⁻	<2.5	3.1	1
I ⁻	0.036	0.06	0.02
F ⁻	5.4	5.7	6.9
PO ₄ ⁼	(0.05) ^c	0.04	0.08
SO ₄ ⁼	61	60	69
S ⁼	<0.2	- -	- -
NO ₃ ⁻	0.44	<0.5	<0.5
HCO ₃ ⁻	45.4 ^f	33.1	50.7
CO ₃ ⁼	8.8 ^g	16.8	25.5
SiO ₂	99 ^d -105 ^e	94	81
NH ₄ ⁻	1.99	1.4	0.3
Si(OH) ₄	167.2	- -	- -

c Calculated from total Phosphorus content

d Calculated from total Silicon Content

e Calculated from total Si(OH)₄ content

f Calculated from Ca(HCO₃)₂ content

g Calculated from CaCO₃ content

Dissolved Gases (RRGE-1)

Gas	RRGE-1		BLM
	(STP ml/liter H ₂ O)	Volume %	Volume %
Hydrogen	0.28	0.73	- -
Helium	0.02	0.051	- -
Nitrogen	50.50	87.5	95
Oxygen	0.06	0.19	5.0
Argon	0.82	1.60	
Carbon Dioxide	0.50	9.97	0.84
Methane	- -	- -	0.25
Total	56.7		

† Sodium Absorption Ratio Calculations

$$\text{Na Abs. Ratio} = \frac{\frac{(\text{Na ppm})}{\text{Mol. wt}} \times \text{ionic charge (1)}}{\frac{(\text{Ca ppm}) \times \text{ionic charge (2)}}{\text{mol. wt.}} + \frac{(\text{Mg ppm}) \times \text{ionic charge (2)}}{\text{mol. wt.}}}$$

where ppm = parts per million by weight in solution

$$\text{Na Abs. Ratio} = \frac{(0.0435) (\text{Na ppm})}{\frac{(0.0499) (\text{Ca ppm})}{2} + \frac{(0.0823) (\text{Mg ppm})}{2}}$$

- a RRGE-1 tested for many more metals and non-metals than the Crank, BLM, or fresh water wells. Figures based on average of up to 14 samples from RRGE-1.
- b Eliminated samples because of suggested contamination.

ND = none detected

M = major = - 5%; m = minor = <5% >0.1%; t = trace = <0.1%

2.4 Deep Drilling Program

2.4.1 Initial Drilling to 4632 ft)*

Drilling at the RRG-1 site began on January 4, 1975. Mud was selected as the drilling fluid for the 900 ft of surface hole. Drilling was routine and the depth of 900 ft was reached on January 9, 1975. A set of electric logs were obtained, followed by the placement and cementing of the 20 inch surface casing to 900 ft.

During the surface casing cementing operation, a normal maintenance inspection revealed that the high drum sprocket assembly bearing had been cracked. Further investigation disclosed that the shaft itself was cracked and could not be repaired. A total of seven days were required to locate and recondition a replacement shaft.

Drilling resumed again on January 20, 1975, using water as the drilling fluid. A depth of 4477 ft was reached on January 31, 1975, and a diamond core taken down to 4537 ft with 23 ft of rock core recovered from the upper portion of the 60 ft barrel section. Drilling was then resumed and continued until the bit was worn out at a depth of 4632 ft at which point well logging was initiated. Logs included caliper, temperature, sonic, gamma-gamma ray, natural gamma, self-potential, dual induction-laterolog and compensated neutron.

2.4.2 Well Logging - Spontaneous Flow

During the well logging operation on February 2, 1975, artesian flow began to develop approximately 12 hours after forced circulation had been stopped. Flow developed to approximately 800 gpm after ten hours. The flow reached a maximum of approximately 1400 gpm at 4:00 a.m. on February 3, 1975, before being shut in (14 hours after initial flow). Several flow tests, injection - coolant tests and wellbore temperature probes were conducted over the next several days. Bottom hole temperature at this time was 138°C (280°F).

*All depths are given with respect to ground level (4835 ft above sea level).

Base data recorded during the drilling operation was with respect to the Kelly bushings, 18 ft above ground level.

Additional temperature logging was conducted on February 10, 1975, in conjunction with selected injection and flow testing. The neutron, sonic, and temperature logs gave some indication of the likely region of hottest water production. Though by no means conclusive evidence existed, it was decided to leave the hole barefoot below the 3700 ft level where the hottest production zone appeared to begin.

In order to provide a base for the casing to be set and cemented to approximately the 3700 ft level, it was decided to backfill the hole to this depth with sand. The sand was inserted into the bottom of the hole through the drill stem. Two check valves were used at the bottom, and neither failed during the injection of the 1160 barrels of sand slurry. This amount filled the bottom of the hole with 880 ft of sand. A 7 ft layer of barite was placed on top of a sealant. Then a 120 ft thick layer of cement plug was emplaced in preparation for running and cementing the 13-3/8 inch production casing down to the 3624 ft depth. Prior to casing, this upper portion was flow tested, resulting in an average flow of only 125 gpm from the 3624 deep well.

2.4.3 Production Casing Collapse

During the cementing operation, the production casing parted at a joint near the 240 ft level. This suddenly released the 2100 psig pressure applied to the cement inside the casing (the cement had thickened prematurely, creating the need for such a pressure). The casing was successfully reconnected at the "popped" thread, and the cementing operation was completed from the top by pumping cement into the annulus between the surface casing and production casing.

The cement left in the casing (807 ft) was eventually drilled out after encountering considerable difficulty in milling through two collapsed casing areas between the 3312 ft to 3323 and 3567 to 3569 ft intervals. The exact cause of the collapsed casing is not known, though the two small isolated lengths of collapse lead to the conclusion that a buckling load and not excessive external pressure were responsible. The hole was then thoroughly cleared of all casing pieces, machinery chips and other drill test debris. Drilling then proceeded through the cement plug and into the sand. The original bottom of the hole was reached (4632 ft) on March 15, 1975. Extensive flow and injection tests were subsequently conducted on the well.

2.4.4 Final Drilling (to 4989 ft)

During the previous operations and as a result of the wet weather, the drilling rig was 33 inches out of vertical alignment. The rig was then leveled and preparations completed for deeper drilling. On March 31, 1975, total depth (TD) was reached at 4989 ft. Core samples were taken from 4668 to 4680 ft (9 ft recovered) and 4987 to 4989 ft. The entire lower 500 ft of hole consisted of hard quartzite "basement" type rocks. Three or four different lithologic strata were encountered in this distance. Figures 2 and 3.

Production was not increased by the additional drilling although the bottom hole temperature increased slightly to 146°C (294°F). The primary reason for deeper drilling was to gather geologic information on the deeper rock types. Basement rock (Pre-Cambrian Quartz Monzonite) was encountered at 4930 ft and drilling was halted at the 4989 ft level.

2.4.5 Completed Well Characteristics

The results of the flow and reinjection tests are as follows:

- 1) It is impossible to "kill" the well completely by pumping in cold water over a short period of time (up to 15 hours). When filled (presumably) with "cold" water, shutin pressure is still 60 psi.
- 2) Hot shutin pressure after flowing (with 280°F water in entire bore) is 160 - 170 psig.
- 3) The flow rate from the well is 650 gpm before development of back pressure from flashing occurs. This reduced flow (approximately 1400 gpm in the uncased hole) is a result of casing and sealing off some of the cooler production zones above the 3624 ft level.
- 4) Peak bottom hole (4989 ft) temperature, measured to date is 146°C (294°F).
- 5) The temperature of the geothermal water reaching the surface has reached 136°C (277°F) following a 2 hour flow test.

2.5 Geology and Geophysics

2.5.1 RRGE-1 Geology and Geophysics

The geological sequence of RRGE-1 is as depicted in Figure 2. It was anticipated that the Paleozoic section (limestone, quartzite and dolomite) would be encountered around the 4500 ft level, however the Pre-Cambrian phyllite, quartzite and quartz monzonite was found. This indicates that the movement along the Bridge Fault is much greater than originally estimated or that a major unconformity occurs directly above the Pre-Cambrian sequence. See Figure 3. Geophysical data supports the existence of the unconformity. If an unconformity exists, the Paleozoic section and possibly the upper units of the Pre-Cambrian section may not be present in this location. RRGE-2 drilling should confirm or refute the occurrence of the Paleozoic section in this area.

The interpretation by USGS personnel prior to the drilling (December 1974), of the resistivity and seismic data in the vicinity of RRGE-1 is presented in Figure 3.

2.5.2 Surface Measurement Program (USGS)

- 1) Surface geology - Interpretation of the surface geology of the Raft River Valley and Cotterell Mountains has been completed. Interpretation of the paleo-magnetic data is continuing.

Figure 2 RRGE-1

Figure 3

RRGE-1 Geologic
Cross Section

Fig. 4 RRGE-1 Profile

2) Geophysics - All surveys have been completed and consisted of the following.

- a) Active seismic
- b) Spontaneous electric potential
- c) Bipole - dipole
- d) Schlumberger deep resistivity
- e) Airborne infrared
- f) Gravity
- g) Residual Magnetic
- h) Audiomagnetotelluric

All relevant USGS survey information to date has recently been open-filed and will be available in report form in the near future.

2.5.3 Intermediate Depth Test Wells

A total of five wells have been drilled and completed. The first three wells have been described in the two previous quarterly reports. The fourth and fifth wells were completed this last quarter. See Figure 5 for the test well locations.

- 1) Test well #4 (252 ft deep) - the hole exhibited a temperature inversion at approximately 100 ft. The maximum temperature was 42°C (108°F) at 100 ft and decreased linearly to 38°C (100°F) at the bottom of the hole. Alluvium was encountered from the surface to 60 ft at which point an altered rhyolite occurred and continued to the bottom of the hole. The rhyolite was jointed and exhibited dense 5-10 ft sections from 170 to 220 ft.
- 2) Test well #5 (719 ft deep) - the hole encountered a basal cobble conglomerate between 665 and 680 ft and a granite below 680 ft. The granite was generally unexpected. The interpretation of the geophysical model for the area is being re-examined by USGS.

The well was completed with 2-inch casing installed and cemented down to the bottom and will be used as a heat flow measurement well.

Test well #3 (1423.5 ft deep) was also cased to 1100 ft and will be used as a heat flow and water level observation well.

There are no current plans for other intermediate depth test wells.

Figure 5

- 5 Intermediate Depth Test Wells
- ◆ 2 Pump Test Wells
- ▲ 2 Deep Exploratory Wells

2.5.4 RRGE-2 Well Site Selection

The Idaho National Engineering Laboratory in consultation with the USGS, ERDA, State of Idaho and other interested parties selected the site of the second well 3915 ft (3/4 mile) to the northeast of RRGE-1. See Figure 6. The site has good all-weather road accessibility and convenient utility connections.

In relation to RRGE-1 and the Bridge Fault, RRGE-2 is offset 650 ft from the down dipped side of the fault and approximately 3860 ft along the strike of the fault to the northeast from RRGE-1. Assume all lithological units and the fault attitude remain constant and that there are no other major faults occurring between the well sites. The RRGE-2 hole should intersect the Pre-Cambrian sequence at approximately 5060 ft and the fault zone from 5305 ft to 5700 ft.

2.6 Hydrology

2.6.1 USGS

Geologic structure, lithology, and physiographic history determine the surface-drainage pattern as well as the occurrence and movement of ground water. The principal water-bearing formations (older to younger) are the Salt Lake Formation of Pliocene (3-1/2 to 14 million years) age, consisting mainly of weakly consolidated sandy sediments and some layers of volcanic rock; the Raft Formation of Pleistocene (2.5 thousand to 3-1/2 million years) age consisting of sand and gravel, lake sediments, and thin beds of silt and clay; and alluvial deposits of Holocene (recent) age that form aquifers beneath the bottom lands of the valleys.

Ground water occurs in perched water tables, normal water tables, and under confined artesian conditions with the water bearing aquifer often located less than 40 ft below the land surface. Yields of irrigation wells in the area range from a few hundred to a few thousand gpm with average depths of from 200 to 400 ft.

Figure 6 Drill Site and Vicinity

Several wells yield warm to hot water. The hot water plumbing system is poorly understood however, geological and geophysical evidence suggests that the water rises from several thousand feet along fault zones and then moves laterally through permeable beds of the aquifer system. The five intermediate depth test wells core drilled by the USGS are being used to investigate the nature of the hot water and character of the rocks to depths of approximately 1000 ft (see discussion of wells under 2.5.2).

The cores and cutting from the intermediate wells were examined at the well site and presently are undergoing lab tests, petrographic examination, etc. Most of the material cored was claystone, siltstone, and sandstone, with several beds of conglomerate. These materials exhibit extensive alteration to clay due to low temperature percolating thermal waters. These wells have been sampled for chemical analysis. (See Section 2 for analysis of the RRGE #1 well and several surrounding wells). Preliminary indications are that the deeper water is somewhat salty (sodium chloride) with conductivities of 7000 to 10,000 micromhos/cm.

Additional geophysical borehole logs were run this quarter (flow meter, televiewer and etc.).

The water level in test well #1 is about 150 ft below the surface; in #2, it is about 70 ft below the surface; in #4, it is about 20 ft below the surface; and in #5, it was about 30 ft below the surface before it was cased in. Test well #3 flows about 60 gpm of 92°C water. Shutin pressure is 16 psig and is equipped with a shutoff valve.

The results of drilling generally reinforce the interpretation of the USGS geophysical data except for the granite member encountered in test well #5. The presence of this granite in the area of Sheep Mountain and Cedar Knoll will require a reevaluation of the data for this area. The granite shows a striking similarity to that occurring in the City of Rocks; an area located in the Sanctuary Mountains, one mountain range (16-3/4 miles) away to the west-southwest.

2.6.2 Pump Tests and Well Interaction Studies

Analysis was completed on the pumping tests (work performed under Subcontract by the Idaho Bureau of Mines and Geology). They were conducted on two privately owned irrigation wells (See Figure 5) in the immediate vicinity of the deep test hole location. Both wells are approximately 200 ft deep, 18 inches in diameter with perforated casing and have a free water surface (water table) located at a depth of 30 ft. One well was pumped at 1600 gpm and data were taken at 5 observation points. The other well was pumped at 1200 gpm and data were taken at two observation points. Both wells exhibited a drawdown of approximately 6 ft during pumping. The second test was aborted part way through by power failure.

The data were used in a two dimensional ground water computer code using the "Theis" equations and both transmissibility and reservoir storage coefficient were calculated. The equation is:

$$TV^2 h = S \frac{2h}{2t} + Q/A$$

Where T represents the transmissivity coefficient in $\frac{L^2}{t}$

S is storage coefficient, dimensionless

Q the well discharge (or reinjection rate in L^3/t)

h is the head above a given data plane

The solution for T gave values in the range of 2.2×10^5 gal/day/ft and for S approximately 1.7×10^{-3} .

3.0 ADVANCED HEAT EXCHANGER DEVELOPMENT

3.1 Direct Contact Heat Exchanger Development Studies

(Reported by R. F. Boehm and H. R. Jacobs, Department of Mechanical and Industrial Engineering, University of Utah)

During this reporting period scale models for determining the heat transfer characteristics of volumetric and surface boilers were constructed. In order to carry out the evaluation of the boiler characteristics a heat transfer loop was constructed. A basic schematic of the flow loop is shown in Figure 7.

The flow loop was designed so that both boilers could be installed at the same time; however, they must be operated separately as they use much of the same instrumentation. This design allows for modification of one boiler during testing of the other, thus reducing "down time." Figure 8 and 9 are schematics of the two boilers while Figures 10, 11 and 12 are photographs of the installed equipment.

In order to carry out meaningful evaluation of the performance of the scale model boilers, heat balances for the system had to be carried out. The analysis of heat loss to the environment required that the individual boilers be isolated from the environment. Figure 12 shows the insulated volume boiler.

Characterization of the direct contact boilers has been initiated utilizing Freon 113. The selection of this fluid was made based on its boiling point at atmospheric pressure and should not be construed to be a final selection as a working fluid. Testing with other working fluid including isobutane, propane, and other refrigerants will be carried out during the next quarter.

The basic working pressure for the prototype boilers has not been finalized. However, the pressure limit has been set at 300 psig. With this in mind the pressure vessels to be utilized were obtained. The vessels were acquired from a surplused demineralization unit at Ogden Supply Depot. Modification of these vessel will be initiated in the latter part of April 1975.

Analysis related to liquid-liquid preheaters to be utilized in a geothermal power plant utilizing direct contact processes has been initiated. These and other supplementary equipment requirements will be assessed in arriving at the selection of a working fluid for use at the Raft River site. System analysis for a 10 MW power plant will be utilized in selecting the final candidate working fluids.

Fig. 7

Figure 8 Volume Model Boiler Schematic

Fig. 9 Surface Model Boiler Schematic

Figure 10

Figure 11

Figure 12

3.2 Fluidized Bed Heat Exchanger Development Studies

(Reported by E. S. Grimmett, K. L. Smith, and D. C. Schmunk,
(Allied Chemical Corporation, Idaho National Engineering Laboratory)

3.2.1 Development of Sampling Techniques and Analytical Procedures

Chemical analysis of the gas and salt content in pressurized samples extracted from Raft River Geothermal Well provided information required for preliminary heat exchanger design. Surface sampling proved inadequate because of gas loss and precipitation loss and concentration changes due to steam loss. Reliable chemical analysis is dependent on the sampling techniques employed and results to date have proved the following to be imperative.

Sample collection vessels must be clean and evacuated or filled with an inert gas.

Prior to sampling, the well must run until it reaches steady-state temperature and pressure.

Samples should be collected at maximum well pressure to insure vessels contain a representative liquid.

Table I in Section 2.2.5 lists the major salts found in various samples collected from the cased well.

The liquid samples were filtered prior to emission, spectrochemical analysis and a large quantity of yellow-red residue was recovered. Quantitative analysis was not performed on the residue, but qualitative analysis showed iron oxides to be the only major components. It is suspected this precipitate resulted from attack of the geothermal water on the newly installed casing.

The high nitrogen concentration and N_2 -Argon ratios indicate most of the gas is dissolved air carried from the surface. The oxygen is apparently depleted by reaction. Carbon dioxide content is established by the carbonate-biocarbonate-carbon dioxide equilibrium system. Since helium is over 100 times greater in the water than in the air, the primary source must be radioactive alpha decay. The large hydrogen content is surprising but may arise from reaction of the fluid with the well casing.

3.2.2 Benchscale Heat Exchanger Studies

During the third quarter of fiscal 1975, the developmental work on the benchscaled model liquid fluidized bed heat exchanger has primarily been directed towards modification of the heat exchanger apparatus to improve data collection, fluidization, and heat transfer. Scale deposition experiments were started during this quarter, but equipment malfunctions prevented the completion of an entire 336 hour (14 day) run.

Several changes were made in the data collection equipment. Expanded records of the temperature variations throughout the heat exchanger system were provided by a larger capacity multipoint recorder. The recorder doubles the number of temperature points available for use in the apparatus and allows for quicker observation of temperature changes.

A system for collecting periodically, the filtered samples of circulating fluid during the heat exchanger experiments was developed also. (See Figure 13) The sampler consists of a 50 ml syringe with a stainless steel millipore filtering apparatus attached to the luer tip. The syringe allows for quick collection of samples with a minimum exposure to room air as the samples cool.

Heat exchanger experiments are conducted on a continuous 24 hour schedule with periodic monitoring of heat transfer data and sampling of the circulating fluid. Records of changes in temperature, secondary flow rate, and brine concentration will now be available throughout a heat exchanger run.

Modification of the system to improve fluidization were frequent during this quarter. Changes in the pump, the exchanger tank, the flow distributor, and the bed material were made (see Figures 14 and 15).

The 0.4 gpm pump used in the original system was replaced by a 2 gpm Materflex tubing pump. The increased flow allowed for more flexibility in distributor and bed material design.

The glass heat exchanger tank was modified several times as various distributor systems were tried. The original distributor consisted of a stainless steel screen and a layer of lead shot (Figure 16). This system distributed the flow well until sand and CaCO_3 collected on the unfluidized shot and screen. The next type of distributor was a coil of fine mesh stainless steel screen which was inserted in the tank inlet and covered with a layer of 0.079 inch stainless steel shot (see Figure 17). This distributor allowed the shot to vibrate slightly. Unfortunately the screen quickly became plugged and flow was decreased to the point that the shot became stationary and began to collect solids. This resulted in a build-up of back pressure which burst the pump tubing.

The current distributor arrangement consists of a mixed layer of 3/8" stainless steel grinding balls and 0.035 inch stainless steel shot (see Figure 18). This system distributes flow evenly and allows for very good fluidization. Since there is no screen to plug, and the entire distributor vibrates with the fluid flow, it is hoped that this system will not collect solids as the previous ones have done.

Although to date sand has been the only bed material utilized, a variety of sizes have been tried (0.300-0.714 mm) to obtain optimum fluidization and scrubbing action. Future plans include experimentation with various sizes of marble chips and amorphous silica for beds.

To improve the quality of the heat transfer data, the heating and secondary cooling systems were modified during this quarter. The four liter beaker previously used as a heating reservoir was replaced by a stainless steel tank containing four 1000 W immersion heaters (see Figures 14 and 15). This effectively doubled the amount of heat that was available in the system for transfer to the secondary cooling water.

The previously used copper cooling coil was replaced during this quarter by a coil made of 1/4" stainless steel tubing. The new coil will allow for more realistic heat transfer data to be collected in future heat exchanger experiments, and will be more resistant to the geothermal brines which will be circulated through the system.

Plans for the fourth quarter of fiscal 1975 include several scale deposition experiments using dissolved Raft River (Crank Well) scale. The present deposition study using dissolved Crank scale (NaCl and CaCO_3) with a mixed sand bed (.500-.714 mm) will be completed and evaluated. Following this, runs using marble chips and amorphous silica are scheduled. Finally, an extended (30 day) experiment is planned using the most promising equipment modifications and bed materials.

3.2.3 Pilot Plant Heat Exchanger

The design of the pilot plant equipment is about 60% complete and some drawings are already being reviewed. The heat exchanger will be constructed so that various types of heat exchanger tubing can be tested, as well as various bed support systems. Materials of construction are arriving and construction of the pilot module should start in June. The unit should be completed and operable by September.

Stainless Steel
Filtering Apparatus

WATMAN 540 Filter

50 ml Syringe

Figure 13
FLUID SAMPLING SYSTEM

Figure 14
ORIGINAL HEAT EXCHANGER APPARATUS

Figure 15
PRESENT HEAT EXCHANGER APPARATUS

Figure 16
HEAT EXCHANGER TANK AND FLOW DISTRIBUTOR

Figure 17

HEAT EXCHANGER TANK AND DISTRIBUTOR

Figure 18
HEAT EXCHANGER TANK AND FLOW DISTRIBUTOR

4.0 NON-ELECTRIC USES OF GEOTHERMAL ENERGY

4.1 Introduction

Current utilization of geothermal energy for non-electric uses appear to be confined to expedient means of satisfying specific needs. Until recently, no systematic technical evaluation and utilization investigation has been undertaken to find ways to maximize the use of this energy source. It has been estimated* that 98% of the more than 7×10^{20} Btu of recoverable heat from geothermal sources located under the United States could be utilized in non-electric applications. This quantity of heat is equivalent to 1.35×10^{14} barrels of oil.

ERDA, recognizing the need for a scientific evaluation of this potential energy source, requested that the Idaho National Engineering Laboratory coordinate the preparation of a National Non-Electric Utilization Program Concept Definition Study. This study was to delineate what the probable potential of such geothermal energy usage could be throughout the nation and also what research and development activities might effectively implement extensive such usage of the geothermal resource.

The postulated end result of this non-electric geothermal program definition study was to provide the nation with proven methods for the utilization of the enthalpy stored in the readily available geothermal fluids. This study was directed primarily toward the utilization of geothermal water in the moderate to low temperature range (300°F), since fluids at higher temperatures would more likely be utilized for electric power generation.

Preparation of a draft of the definition study was completed and copies were transmitted to ERDA Washington and the ERDA Geothermal Advisory Committee for their meeting which was held at ORNL last quarter. This report which is in the process of internal review and will be issued soon.

As a result of the Advisory Committee review of the Program Concept Definition Study, the ERDA initiated certain non-electric geothermal work to be performed at INEL during the remainder of FY-75. The work funded includes two basic areas of concern, namely, Non-Electric Geothermal Technical Development and a Demonstration Geothermal Space Heating Project of Government buildings.

* 3% of the intrinsic heat to a depth of 10 km.

4.2 Background Information

In the United States, the major research for development of geothermal energy in both the public and private sectors has been directed towards the electrical power generation aspects of the geothermal resource. But development has been slow due to a variety of geologic, economic, and political factors, not the least of which has been the rarity of the potent dry-steam type of geothermal system most suited to development for electrical generation.

Improved technology and rising energy costs will eventually allow the development of many intermediate (approximately 300°F or 150°C) and low-temperature (approximately 180°F or 82°C) geothermal systems for electrical generation. But, the majority of these low-temperature geothermal occurrences do not appear to be capable of producing either the temperatures or volumes of fluids necessary for even modest electrical generation. The logical approach would appear to be the utilization of the heat energy more directly for non-electric energy uses. The advantages to the nation's energy use inventory would be significant. For instance, each average American home has annual space heating energy consumption approximately equal to the energy consumed in operating the family automobile for a year. Savings in fossil fuel could represent a one to one increase in available resources for transportation.

In general, unless the hot water was already available, geothermal heating systems have seldom received serious consideration from city or subdivision planners. It is believed that direct, deliberate efforts to employ such energy for space heating could lead to its eventual widespread use. But, several pilot demonstration programs are believed necessary before the most feasible techniques are determined and the risks are better assessed in order to give the systems general acceptance as a viable alternative in community planning considerations in the U.S.

4.3 Progress During This Reporting Period

Work was initiated on the development of a decision modeling technique to aid in performing an evaluation of the long range benefits of the various

forms of non-electric geothermal energy utilization. It is anticipated that a number of existing computer programs, currently being examined, can be combined with manual techniques to assist in solving this problem. A preliminary report on this activity will be prepared during the next reporting period.

Cost analyses and comparisons of various space heating concepts with geothermal energy were initiated. Preliminary results indicate that the potential for geothermal heat, although limited to areas of resource availability is very attractive. A draft of the results of this study is under preparation.

During drilling operations of the first deep geothermal well at the Raft River site, it was deemed advisable to provide some heat to the atmosphere on and under the drilling platform since outdoor temperatures dropped to as low as -27°F . The heat was required not only for human comfort, but also to prevent freezing of water lines and tanks and severe stiffening of grease and oil on working parts. Under severe weather conditions drilling rig working platforms and cellars are normally heated with either electric space heaters or with fossil fuel generated hot water or steam space heaters. Water at 200°F from a nearby artesian geothermal well was piped to the drilling rig and connected directly to the existing space heating units to replace the normally used fossil fuel heated water. Effective tempering of the drilling rig operating floor and cellar temperatures was achieved. Although this application of geothermal space heating was relatively small in nature, it was a typical example of a new and novel approach to the savings of fossil fuel. A formal report on this activity is being prepared.

An analysis has been prepared relating to the steps necessary to incorporate the use of geothermal heat as a district heating system for a new city of from 6,000 to 20,000 population to be built in a known geothermal resource area. Cost comparisons with fossil fueled heating systems indicate that geothermal heating would be economically feasible. This is true partially because the location under consideration is a rather remote one where the cost of fossil fuel is abnormally high.

Plans are being formulated to embark on a program of pilot plant studies to assist in solving problems associated with the utilization of contaminated geothermal water. It is anticipated that such pilot plants will be located at an existing geothermal well site such as at the Raft River area.

Action is being initiated to develop plans for a series of semi-scale demonstration units of industrial-process heat applications of geothermal energy. Ultimately, one would anticipate such applications would be organized on a larger scale into an integrated industrial park at various geothermal sites. Industrial contacts will be made to solicit commercial interest participation in this activity.

4.4 Boise Demonstration Geothermal Space Heating Project

4.4.1 Background

A pilot demonstration project conceptual design effort has been initiated to be installed in the city of Boise, Idaho where a joint Federal-State effort will lead to the heating, by geothermal waters, the State Capitol, several State office buildings, the Veteran's Home, and part of the buildings of Boise State University.

The downtown area and the adjacent capitol complex are situated within one mile of the Foothills Fault. Many of the State buildings are located within 1/2 mile of reported thermal occurrences. (A well on the Capitol grounds produces warm water.) At a slightly greater distance is the campus of Boise State University. The aggregate annual expenditure for the present fossil fuel heating of these buildings is \$225,000. Based on 1975 fuel costs and an anticipated total project cost of approximately \$2-1/2 million, marginal economic feasibility based on amortization over a reasonable period is predicted. As the cost of the fuel has been constantly escalating and is expected to rise significantly in the future, the economic justification will become even stronger. In addition to this direct economic benefit, the replacement of fossil fuel-based heating with geothermal space heating will effect a significant long-term conservation

of fossil fuel which may be practical in many other localities. The present hot water wells serving the Boise Warm Springs residential area have been pumped without any appreciable decline in productivity for 83 years.

The planned research and development effort has the following principal objectives:

1. To determine if the proposed geothermal resource area is adequate.
2. To determine the costs and practicality of retrofitting existing heating systems for use with low temperature (probably less than 200°F or 93°C) geothermal water.
3. To design the distribution system, the H&V systems (new and conversions) and, in particular, the geothermal waste water discharge system.
4. To build and test the proposed system to demonstrate the actual costs of construction and operation and to identify the technical difficulties which may arise from long term operation.

In addition to the above detailed R&D effort, studies will be conducted to determine the feasibility of converting other public structures in Boise, Idaho to geothermal heating.

The objectives of the demonstration project will be accomplished in four stages. Phase I will be a study of the feasibility of converting the State buildings and other selected public buildings to geothermal heating. Phase II, which will proceed concurrently with Phase I, will be involved with geologic, geophysical, and geochemical investigations leading to site-selection as well as the initiation of the conceptual design and environmental analysis of the production, distribution, heating, and waste discharge systems. Phase III will be the drilling and testing of initial exploratory wells to confirm the distribution of the geothermal resource and subsequent production wells. This phase will include the completion of conceptual design of the system. Phase IV will proceed pending the successful results from the previous phases. It will represent the principal objective and expenditures centered on the construction of the distribution and discharge systems and installation of the heat exchange systems in the various heating plants. Much of this construction

phase is expected to be undertaken with non-federal construction funding except for the supplemental efforts relating specifically to research and development efforts. Environmental investigations centered on the impact of geothermal exploration and development in the urban environment will begin during Phase II and continue throughout the duration of the project.

4.4.2 Progress During This Reporting Period

Two Sprengnether MEQ-800 portable microseismic systems were received and checked out. Three days were spent in a field north of Boise monitoring microearthquake activity along the Cascade-Long Valley fault zone. Significant microseismic activity (approximately 30 events) was detected in spite of problems of snow depths of five feet. These preliminary results indicate the activity along this zone may provide a relatively high background level of seismic activity during monitoring in the Boise area.

A magnetometer survey of the Boise Foothills area was initiated because of snow conditions, measurements were restricted to traverses along the major access roads perpendicular to the Boise Front. Good data are being obtained and the survey is continuing.

Field mapping was begun during this reporting period. An area of hydrothermally silicified sandstone was located in the Colonial Hills Village area immediately north of the Boise State University lease.

Small computer programs have been written for geochemical thermometer calculations utilizing various mixing model by the U.S. Geological Survey. Equilibrium expressions for the fluoride concentrations in thermal water are being investigated. It is hoped that this work will help to explain the high fluoride concentrations encountered in the Boise and Raft River geothermal waters.

A thorough review of the existing heating systems installations of public buildings owned by the State of Idaho in Boise, Idaho was completed. Projected heating loads for present and future expansion to 1990 were determined. Preliminary layouts of the heating system, its costs and size were

underway. Engineering effort was directed toward the accumulation of design and operational data on the space heating systems that will be affected. Concurrently, effort has been applied to conceptual designs and the development of alternate overall design approaches that will satisfy environmental considerations.

An environmental analysis was prepared relative to the geophysical field measurements being conducted.

5.0 PLANS FOR SUBSEQUENT QUARTER

1. Complete the RRGE-2 (second well) drilling and initiate the testing program between RRGE-1 and 2.
2. Evaluate the geological data acquired from RRGE-2 and perform a further interpretation and correlation of the geophysical data in relation to this new data.
3. Select the drilling site for a possible third hole (RRGE-3) for exploratory and/or reinjection purposes.
4. Prepare reports on RRGE-1 site selection and well drilling.
5. Complete design and cost estimate of 10 MW dual boiling isobutane cycle operating from 300⁰F geothermal water.
6. Continue geological, geophysical, geochemical and hydrological studies of the Boise, Idaho Foothills area to establish the nature and extent of the geothermal resource and to determine its characteristics.
7. Continue feasibility and preliminary conceptual design work on the State buildings at Boise, Idaho. The engineering effort during this next quarter will be directed toward the completion of the design criteria and the initiation of the conceptual design.
8. Analyze residues from pipe samples obtained from long existing geothermal hot water systems in Boise. Metallographically examine pipe samples which have had long term exposure to Boise geothermal water to determine physical and chemical effects of this exposure.
9. Design and assemble test loops for installation in a geothermal water system in Boise.

DISTRIBUTION RECORD FOR ANCR-1222

External Distribution - Standard

In accordance with TID-4500, R62, under the category Nonnuclear Energy Sources & Energy Conversion Devices. (UC-13)

External Distribution - Unique

In accordance with the list provided by the author. (115)

Internal Distribution

In accordance with the list provided by the author. (38)

Technical Library (98)

Author (120)

J. L. Griffith, ID

C. W. Bills, ID

R. E. Wood, ID

Number of Copies

External Distribution - Standard	143
External Distribution - Unique	115
Internal Distribution - ANC	38
Internal Distribution - ID	3
Internal Distribution - Technical Library	98
Internal Distribution - Author	120

Total Copies Printed - - - - - 517