PNL--8121

DE92 016825

ELECTRIC LOAD MONITORING TO SUPPORT
A SHARED ENERGY SAVINGS PROCUREMENT
AT THE U.S. MARITIME ADMINISTRATION
MERCHANT MARINE ACADEMY

P. R. Armstrong
G. B. Parker

June 1992

Prepared for
the U.S. Department of Energy
Federal Energy Management Program
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Richland, Washington 99352

MASTER

20

PREFACE

The goal of the U.S. Department of Energy Federal Energy Management Program (DOE-FEMP) is to facilitate energy-efficiency improvements at federal facilities. This is accomplished by a balanced program of technology development, facility assessment, and use of cost-sharing procurement mechanisms. Technology development focuses upon the tools and procedures used to identify and evaluate energy-efficiency improvements, such as the ASEAM simulation model and the Federal Life Cycle Costing procedures. For facility assessment, DOE-FEMP provides metering equipment and trained analysts to federal agencies that exhibit a commitment to improve energy use efficiency. To assist in procurement of energy-efficiency measures, DOE-FEMP helps federal agencies devise and implement shared energy savings and utility demand-side management projects.

Pacific Northwest Laboratory (PNL)^(a) supports the DOE-FEMP mission as the lead laboratory for energy systems modernization. Under this charter, the Laboratory and its contractors work with federal facility energy managers to assess and implement energy-efficiency improvements at federal facilities nationwide.

(a) Pacific Northwest Laboratory is operated by Battelle Memorial Institute for the U.S. Department of Energy under Contract DE-AC06-76RLO 1830.

EXECUTIVE SUMMARY

Two monitoring projects were initiated at the U.S. Merchant Marine Academy (MMA), Long Island, New York, to support procurement of energy improvements through a Shared Energy Savings (SES) project. The first project involved boiler efficiency testing and initial (short-term) whole building electric demand testing. The results of these tests are given in this report.

The second project involved long-term monitoring of whole building electric demand for the period of March 17 through October 21, 1991. The purpose of long-term monitoring of the electric demand was to characterize three-phase power demand of three buildings that have large electrical loads: Bowditch Hall, Fulton-Gibbs Hall, and the Library. These data provide a baseline for recommending energy savings opportunities and, more importantly, for assessing energy savings resulting from future energy conservation measures to be implemented in the monitored buildings.

In addition, the monitoring provided detailed operational data that allow prospective SES contractors to recommend and assess alternative conservation measures more accurately and to propose measures that would be too risky to invest in without the data. The data also provide a baseline for estimating the savings generated by the energy improvements after they are in place. In the past, such estimates had been based on engineering calculations mutually agreed to by the facility and the contractor or third party investor. This approach normally eliminated any incentive on the part of the contractor to assure proper maintenance and operation of the energy improvements.

RESULTS

The three monitored buildings showed a baseload of about 210 kW and a daytime load of about 80 kW (23 avg kW) above the baseload during the heating season of the monitoring period. The baseload is *high* and the rise in daytime load is *low* compared with buildings of similar function. A significant fraction of the baseload probably consists of fans, lights, and office equipment that can be turned off at night and on weekends.

There is clearly a significant potential for savings in electric demand and consumption in the monitored buildings. Allowing a contractor to implement simple, hours-of-operation-reducing measures will lessen the contractor's incentive to look for longer payback energy conservation measures (ECMs) unless the implementation of such ECMs is specifically written into the contract. Also, a contractor may be less motivated to ensure that the longer payback ECMs are continuously maintained and properly operated. Such motivation is important because proper operations and maintenance (O&M) of efficiency measures is more difficult to contract, monitor, and enforce than their initial implementation.

RECOMMENDATIONS

The savings potential of O&M measures should be explored, and low-cost and no-cost O&M improvements should be implemented by MMA maintenance staff, where practicable, prior to selecting an SES contractor to install ECMs. This will force the contractor to focus on capital-intensive retrofits, which are the facility owner's primary concern and motivation for pursuing an SES arrangement in the first place.

The energy consumption on this campus is more variable than in typical office buildings. This poses difficulties in the calculation of energy savings that result from implementing SES retrofit measures. Based on the metering, a model that accounts for *variations in building occupancy* appears to be needed since the metered data were not well correlated to only ambient temperature. The occupancy data to drive the model could come from schedules of classes and other programs, or it could come from occupancy sensors that are part of the SES project and that can be monitored by an energy management and control system.

Lights and equipment that do not need to operate 24 hours per day should be controlled by occupancy sensors, photocells or time clocks. Demand lighting should be considered for the library stacks. High-efficiency lighting should be installed to replace older existing general, exterior, and security lighting fixtures. Selective delamping should be considered for hallways that are currently over-illuminated.

Based on these observations and a general knowledge of recent progress in lighting technology, the following retrofits should be considered:

- high-efficiency security lighting
- high-efficiency general (interior) lighting
- high-efficiency, photocell activated exterior lighting
- occupancy sensors for classrooms
- delamping and time-clocks or occupancy sensors for hall lights
- lighting on demand in the library stacks; the system should be designed to give 5-10 minutes of lighting in a single aisle initiated by a pushbutton at either end of the aisle.

Individual building metering and submetering of chillers and other large loads should be implemented where feasible. Electronic registers that record average power over each hour, day, week, or month and download data to a portable computer are recommended. This is the most cost-effective check of accuracy that can be applied to SES energy consumption models.

Based on observations at the site and recent progress in heating, ventilation and air conditioning (HVAC) technology and practice, the following HVAC retrofits should be considered:

- 2-speed or variable-speed fan motors, reduced airflow and operating hours
- 2-speed pump motors and impellers trimmed for actual flow and pressure
- high-efficiency motors for fans and pumps
- a plate heat exchanger to eliminate chiller operation in cool weather
- controls to modulate variable air volume (VAV) flow and static pressure by most needy zone
- time schedules and minimum load thresholds for fans, chillers and window units.

Steps should be taken to ensure that any retrofits designed to reduce electrical demand or consumption do not make phase imbalances any worse. The retrofits should be designed to improve existing phase imbalances if possible.

In addition, the servicing electric utility (Long Island Lighting Company) offers a variety of demand-side management incentives and up-front financing for energy modernization at federal facilities. These incentives could be combined with a program for site peak shaving through the use of existing diesel generators. A site peak shaving strategy will likely result in reduced or modified rates.

CONTENTS

PREFACE	iii
EXECUTIVE SUMMARY	v
1.0 INTRODUCTION	1.1
2.0 FACILITY DESCRIPTIONS	2.1
3.0 MONITORING DESCRIPTION	3.1
3.1 TEST DIAGRAM	3.2
4.0 RESULTS	4.1
4.1 MONTHLY DEMAND IN THE THREE MONITORED BUILDINGS	4.1
4.2 ANALYSIS OF FULTON-GIBBS HALL ELECTRIC LOADS	4.3
4.2.1 SE Circuit Demand Profiles	4.3
4.2.2 NW Circuit Demand Profiles	4.3
4.2.3 Relation Between Demand and Temperature	4.6
4.3 ANALYSIS OF BOWDITCH HALL ELECTRIC LOADS	4.9
4.3.1 Baseload	4.9
4.3.2 Chiller Power Demand	4.11
4.3.3 Relation Between Demand and Temperature	4.11
4.4 ANALYSIS OF LIBRARY ELECTRIC LOADS	4.14
4.4.1 Baseload	4.15
4.4.2 Variable Loads	4.15
4.4.3 Relation Between Demand and Temperature	4.15
5.0 RECOMMENDATIONS	5.1
6.0 ECONOMIC ANALYSIS	6.1
6.1 PAYBACK TIMES	6.1
6.2 INTERACTIONS	6.1

6.3 SHARED ENERGY SAVINGS	6.1
APPENDIX A - WHOLE BUILDING ELECTRIC DEMAND TESTS	A.1
APPENDIX B - BOILER EFFICIENCY TESTS	B.1
APPENDIX C - DEFINITION OF TERMS AND UNITS OF MEASURE	C.1

FIGURES

4.1	Average Weekday Profiles, Fulton-Gibbs Hall, SE Circuit	4.3
4.2	Average Weekend Profiles, Fulton-Gibbs Hall, SE Circuit	4.4
4.3	Average Weekday Profiles, Fulton-Gibbs Hall, NW Circuit	4.4
4.4	Average Weekend Profiles, Fulton-Gibbs Hall, NW Circuit	4.5
4.5	Average Weekday Profiles with 95% Confidence Region Shaded, Fulton-Gibbs Hall, NW Circuit	4.6
4.6	Fulton-Gibbs Hall Demand vs. Temperature (Daily Averages) . . .	4.8
4.7	Fulton-Gibbs Hall Demand vs. Temperature (Weekly Averages) . . .	4.8
4.8	Fulton-Gibbs Hall Demand vs. Temperature (Four-Week Averages) .	4.9
4.9	Average Weekday Profiles, Bowditch Hall, Not Including Old Panel and Chiller Loads	4.10
4.10	Average Weekend Profiles, Bowditch Hall, Not Including Old Panel and Chiller Loads	4.10
4.11	Bowditch Hall Demand, Not Including Old Panel Loads, vs. Temperature (Weekly Averages)	4.12
4.12	Bowditch Hall Demand, Not Including Old Panel Loads, vs. Temperature (Weekly Averages)	4.13
4.13	Bowditch Hall Demand, Not Including Old Panel Loads, vs. Temperature (Four-Week Averages)	4.13
4.14	Average Weekday Profiles, Library	4.14
4.15	Average Weekend Profiles, Library	4.15
4.16	Library Demand vs. Temperature (Daily Averages)	4.16
4.17	Library Demand vs. Temperature (Weekly Averages)	4.17
4.18	Library Demand vs. Temperature (Four-Week Averages)	4.17

TABLES

4.1	Monthly Loads Extrapolated from Monitored Load Profiles for March Through October 1991	4.2
4.2	Energy Use Intensities	4.2

1.0 INTRODUCTION

Equipment from the Mobile Energy Laboratory (MEL) testing and application program supported by the U.S. Department of Energy Federal Energy Management Program (DOE-FEMP) was applied to measure three-phase power demand of three large buildings at the U.S. Merchant Marine Academy (MMA) on Long Island, New York. The selected buildings were Bowditch Hall, Fulton-Gibbs Hall, and the Library. The MEL equipment was installed on March 17, 1991. Instruments to monitor the Bowditch Hall chiller as a separate load were added on June 2, 1991. MEL Test Procedure #1, *Building Energy Monitoring*, was followed in the installation and operation of the monitoring equipment.

The monitoring objectives were to 1) provide a baseline for assessing energy savings resulting from future energy conservation measures that are to be implemented in the monitored buildings, and 2) provide information for recommending cost-effective energy conservation opportunities.

Results of the long-term, whole building monitoring project at the MMA are presented in this report. Section 2 provides a brief description of the monitored facilities. Section 3 describes the monitoring hardware and application. Section 4 presents and interprets the monitored data. Section 5 makes recommendations regarding likely energy conservation opportunities, implementation of conservation measures by the MMA or an energy service company, and verification of the resultant savings. Section 6 provides the economic analysis.

Results of the initial project, which involved initial (short-term) whole building electric demand testing and boiler efficiency testing, are presented in Appendixes A and B, respectively. Appendix C is a listing of definitions of terms and units of measure used in this report.

2.0 FACILITY DESCRIPTIONS

Fulton-Gibbs Hall contains engineering classrooms and laboratories. It also contains the central boiler plant and steam laboratory. The gross floor area of Fulton-Gibbs Hall is 100,302 ft² and the net area is 96,598 ft². The engineering classrooms are cooled by central electrically driven air-conditioning. Fulton-Gibbs Hall is cooled by two 150-ton centrifugal chillers.

Bowditch Hall contains classrooms and a firing range. Gross and net floor areas are 61,390 and 58,725 ft², respectively. Bowditch Hall is cooled by a 200-ton centrifugal chiller.

The gross and net floor areas of the Library are 31,100 and 29,340 ft², respectively. The Library is cooled by two 60-ton reciprocating direct-expansion air-conditioning units.

3.0 MONITORING DESCRIPTION

Six three-phase power circuits were instrumented at two locations. A Synergistics Control Systems C180 data logger (serial number 00202) was installed in the Bowditch Hall electrical vault; this vault contains the service entrances to both the Library and Bowditch Hall. A potential brick was installed at an abandoned breaker served by transformer 5B. Three 1-amp in-line fuses were installed at the breaker terminals. Three AEMC 1000/2000:1 jaw-type current transformers (CTs), configured for the 1000:1 turn ratio, were initially installed on the bus bars to the 300- and 600-amp breakers that serve the old Bowditch Hall electrical panels. This circuit was monitored for five days. The CTs were then moved to the Library mains.

Three 1200:5, five-inch (inside dimension) window CTs were installed on the mains to the new Bowditch distribution panel, which includes the chiller circuit. The new panel is the only load on transformer 5A. A potential brick was installed at a spare breaker in the panel, and three 1-amp in-line fuses were installed at the breaker terminals. Six 400-amp CTs (two parallel CTs on the two conductors leaving each phase terminal of the breaker) were installed on the chiller circuit on June 2, 1991.

A second Synergistics Control Systems C180 (serial number 01223) was installed in Fulton-Gibbs Hall. Three 2500:5, eight-inch (inside dimension) window CTs were installed on the conductors that feed the NW switchgear cabinet. A potential brick was installed at an abandoned transfer switch, and three 1-amp in-line fuses were installed at the switch terminals. Three 3000:5, eight-inch (inside dimension) window CTs were installed on the conductors that feed the SE switchgear cabinet. A potential brick was installed at an abandoned transfer switch, and three 1-amp in-line fuses were installed at the switch terminals.

A 1/16-inch sheathed Type-K thermocouple was installed in the emergency generator cooling air louver, and a MEL Type-K thermocouple signal conditioner was installed in the C180 to measure outdoor air temperature.

3.1 TEST DIAGRAM

The six monitored circuits are all 120 volt, three-phase wye circuits. The instrumentation diagram for monitoring a typical circuit is shown below.

4.0 RESULTS

Continuous data from all data loggers were logged and remotely downloaded at PNL via phone lines and a modem for seven consecutive weeks, starting on March 18, 1991. Phone line problems in Bowditch Hall prevented remote uploading of data for that building during the periods of March 29 through April 1, 1991; June 16 through 20, 1991; June 29 through July 1, 1991; and August 19 through September 6, 1991. The loads observed during the monitoring period and the annual loads and energy use intensities (EUIs) extrapolated from the data are discussed in Sections 4.1 through 4.4.

4.1 MONTHLY DEMAND IN THE THREE MONITORED BUILDINGS

Demand for electrical power was measured in the months of March through October 1991, and extrapolated for the time period of November through February. In addition, four components of annual demand have been computed from each building's monthly profiles.

The monthly demand numbers are presented in Table 4.1. Note that some months' estimates are based on partial data. The number of full days is indicated by N, and each reported monthly demand value is based on the average kW on days with no missing data.

The EUIs for the four load components are presented in Table 4.2. The data in Tables 4.1 and 4.2 constitute an *electric energy baseline* for the monitored buildings. The baseline is useful for estimating the conservation potential of proposed lighting and air-conditioning energy conservation measures (ECMs) and evaluating the savings achieved by implemented ECMs. The baseline data are particularly important because a contractor's numbers are usually based on connected load and operating schedule surveys. Assumed operating schedules can err considerably on the high or low side.

The time-of-day, time-of-week, and weather-related behaviors of each building's loads are discussed in Sections 4.2 through 4.4.

TABLE 4.1. Monthly Loads (Average kW) Extrapolated from Monitored Load Profiles for March through October 1991

Period	Fulton-Gibbs		Library		Bowditch Hall		
WEEKDAYS	N	Total	N	Total	N	New	New+Old
March	10	112.62	4	10.75	7	43.33	98.33
April	21	136.16	22	41.46	22	38.18	93.18
May	23	197.83	20	28.86	20	94.88	149.88
June	18	227.61	15	16.39	15	118.48	173.48
July	22	198.98	22	93.07	22	145.05	200.05
August	22	217.63	12	139.81	12	143.17	198.17
September	21	210.61	16	73.97	16	104.70	159.70
October	15	143.03	15	36.22	15	44.64	99.64
WEEKENDS							
March	4	92.33	3	24.18	4	43.07	98.07
April	8	91.77	8	35.41	8	36.16	91.16
May	8	154.08	7	25.23	7	53.20	108.20
June	10	159.80	7	10.33	7	111.85	166.85
July	8	161.31	8	85.45	8	109.29	164.29
August	9	157.02	6	112.99	6	119.98	174.98
September	9	154.42	8	62.83	8	82.68	137.68
October	6	121.78	6	44.62	6	30.83	85.83
ALL DAYS							
March	14	106.82	7	14.59	11	43.26	98.26
April	29	123.48	30	39.73	30	37.61	92.61
May	31	185.33	27	27.82	27	82.97	137.97
June	28	208.24	22	14.66	22	116.58	171.58
July	30	188.22	30	90.89	30	134.84	189.84
August	31	200.31	18	132.15	18	136.55	191.55
September	30	194.56	24	70.79	24	98.41	153.41
October	21	136.96	21	38.62	21	40.70	95.70
Average kW		147.82		45.26		72.21	127.21
Annual MWh		1294.9		396.5		632.6	1114.4

TABLE 4.2. Energy Use Intensities (kWh/ft²-yr)

Load Category	Fulton-Gibbs	Library	Bowditch
Baseload	8.4	4.9	13.4
Intermittent Light & Plug	0.9	2.9	0.6
Added Summer Baseload	3.1	4.1	3.7
Intermittent Air Conditioning	0.5	0.8	0.4
Total	12.9	12.7	18.1

4.2 ANALYSIS OF FULTON-GIBBS HALL ELECTRIC LOADS

Two circuits, SE and NW, feed power to Fulton-Gibbs Hall; these were monitored in this study and are discussed below.

4.2.1 SE Circuit Demand Profiles

Average weekday demand profiles for the SE circuit are shown in Figure 4.1. Average weekend profiles are shown in Figure 4.2. The SE circuit's baseload is 18 kW. The average 15-minute peak load is about 30 kW. Note that the daytime loads are quite variable. There is little weekday daytime load in mid-July, for example, but exceptionally large weekend afternoon loads in late October. The variable part of the load averages 25 kWh per day on weekends and 50 kWh per day on weekdays and does not appear to be seasonal.

4.2.2 NW Circuit Demand Profiles

Average weekday demand profiles for the NW circuit are shown in Figure 4.3 and the corresponding weekend profiles are shown in Figure 4.4. The NW circuit's baseload is 100 kW on weekdays and 85 kW on weekends. The baseload

FIGURE 4.1. Average Weekday Profiles, Fulton-Gibbs Hall, SE Circuit

FIGURE 4.2. Average Weekend Profiles, Fulton-Gibbs Hall, SE Circuit

FIGURE 4.3. Average Weekday Profiles, Fulton-Gibbs Hall, NW Circuit

FIGURE 4.4. Average Weekend Profiles, Fulton-Gibbs Hall, NW Circuit

increases by 60 to 80 kW in summer. This increased demand may be due to condenser and chilled water pumps, chillers, or ventilation fans that run continuously in the summer. The intermittent daytime load adds 350 kWh per day to the winter baseload and about 1200 kWh per day to the summer baseload. These data imply that the intermittent air-conditioning load averages 850 kWh per day while the air-conditioning and ventilation equipment that operates continuously in summer uses 1700 kWh per day. There is little or no added daytime load on weekends.

Note that the NW weekday load profile for April 22 through May 8, 1991, is similar to the load profile for September 27 through Oct 21, 1991, and that the load profile for May 13 through June 8, 1991, is very similar to the profile for July 11 through September 26, 1991. The profiles are reproduced in Figure 4.5 with the addition of shaded confidence regions; the figure shows the extent to which the confidence regions of the similar profiles overlap. The general change in daily profile that develops during the spring and early

FIGURE 4.5. Average Weekday Profiles with 95% Confidence Region Shaded, Fulton-Gibbs Hall, NW Circuit

summer is retraced in the late summer and autumn. This is clear even with changes in operations, occupancy levels and weather that confound interpretation of individual daily profiles.

While the magnitude of the seasonal variation is much less in the weekend profiles, the symmetric character of the variation is still very clear. One drawback to this model is that changes in energy consumption due to changing building occupancy and operation cannot be distinguished from changes due to weather. Therefore, for evaluating future energy consumption for this building, an energy consumption model based on a seasonally varying daily profile appears to be feasible.

4.2.3 Relation Between Demand and Temperature

One fairly common feature of SES proposals and contracts is the use of a calibrated energy consumption model as the basis for calculating energy savings. These models generally assume that the non-air-conditioning demand component follows a weekly cycle and that weekly (or longer) average

whole building electric demand is well correlated with outside temperature. The accuracy of such models is always an important consideration in evaluating SES proposals.

The air-conditioning components of electric power demand are generally a function of internal loads, plant operation, and outside temperature, solar radiation and humidity. The following assumptions are usually made to arrive at a simple demand versus outside temperature model that is simple to calibrate and evaluate:

- Most of the building's internal load variation follows a weekly cycle; seasonal and other variable components of internal load that are difficult to model without detailed knowledge of building function and operation are assumed to be small.
- Plant operations do not involve frequent seasonal set-point and schedule adjustments.
- Solar gain and humidity effects are well enough correlated with outside temperature to be modeled as components of the outside temperature effect.

An analysis was performed to assess the adequacy of modeling energy consumption in Fulton-Gibbs Hall using such an outside temperature-based model. Figure 4.6 shows daily average demand as a function of daily average outside temperature. The expected trend of increasing demand with increasing temperature is apparent *but there is a great deal of scatter*. Some of this scatter is due to differences in weekday and weekend occupancy and operations.

Figure 4.7 shows weekly average demand as a function of weekly average temperature. Here the linear relation between demand and temperature is consistent between 10° and 20°C but the relation breaks down at higher temperatures. The air-conditioning system appears to reach its capacity at about 20°C. Figure 4.8 shows the relation between four-week average demand and outside temperature. The points are connected in order to show their time sequence. Note that the points above 20°C occur in June, July, and August. This observation leads to an alternative hypothesis for failure of the linear relationship. Lower energy use in June, July, and August could have resulted from reduced instructional activity (i.e., lower occupancy) in the summer months.

FIGURE 4.6. Fulton-Gibbs Hall Demand vs. Temperature (Daily Averages)

FIGURE 4.7. Fulton-Gibbs Hall Demand vs. Temperature (Weekly Averages)

FIGURE 4.8. Fulton-Gibbs Hall Demand vs. Temperature (Four-Week Averages)

4.3 ANALYSIS OF BOWDITCH HALL ELECTRIC LOADS

The main chiller circuit in Bowditch Hall was monitored between June 2 and October 22, 1991. The main feed was monitored between March 17 and October 22, 1991.

4.3.1 Baseload

Average weekday demand profiles for Bowditch Hall are shown in Figure 4.9 and weekend profiles are shown in Figure 4.10. The weekday baseload is 65 kW and the weekend baseload is 60 kW. There is no apparent seasonal variation in the baseload. The daytime light and plug load is about 80 kWh per day on weekdays and averages 10 kWh per day on weekends. Weekend daytime light and plug loads are more variable than weekday daytime light and plug loads due, presumably, to aperiodic weekend operations and to routine operations that differ from Saturday to Sunday (e.g., there is an increase in demand every Sunday night--perhaps due to a cleaning crew--that lasts for about 6 hours). However, the weekday and weekend profiles are flatter than

FIGURE 4.9. Average Weekday Profiles, Bowditch Hall,
Not Including Old Panel and Chiller Loads

FIGURE 4.10. Average Weekend Profiles, Bowditch Hall,
Not Including Old Panel and Chiller Loads

expected for the building's primary instructional function, due to high demand throughout the nights and weekends. This indicates that simple O&M changes, such as occupancy sensors, time-clocks, and interlocks, could result in significant energy savings.

4.3.2 Chiller Power Demand

Most or all of the air-conditioning at Bowditch Hall is provided by a single centrifugal chiller. During the monitoring period, the chiller operated 75 percent of the time on weekdays and a little over 50 percent of the time on weekends. The chiller draws a minimum of 60 kW. The resulting air-conditioning baseload is $770 + 205 = 975$ kWh per day. The variable air-conditioning load averages about 125 kWh per day on weekdays and 85 kWh per day on weekends; the difference is easily explained by the difference in light and plug baseload energy that must be removed to maintain a room temperature cooling setpoint.

The minimum kW demand is about what would be expected for a 200-ton centrifugal chiller with modulation provided by compressor inlet turning vanes. The maximum demand, however, is about half of what is expected. These observations lead to the conclusion that the chiller is oversized or that the distribution system (chilled water distribution, coils, and/or air distribution subsystems) is inadequate. If the chiller is oversized, it may be possible to retrofit the existing unit with a smaller compressor. This will result in a more efficient unit than replacement by a smaller unit, because retaining the large condenser and evaporator sections will result in closer approach temperatures and higher coefficient of performance (COP). Lower pressure drops through the water side passages of the condenser and evaporator sections will also result so that smaller chilled water and condenser water pumps may be used. If the distribution system is at fault, the inadequate portions should be upgraded.

4.3.3 Relation Between Demand and Temperature

The procedure for evaluating a temperature-based whole building demand model that was applied to the data from Fulton-Gibbs Hall monitoring was applied to Bowditch Hall. Figure 4.11 shows daily average demand as a

FIGURE 4.11. Bowditch Hall Demand, Not Including Old Panel Loads, vs. Temperature (Daily Averages)

function of daily average outside temperature. The expected trend of increasing demand with increasing temperature is apparent but there is as *much scatter here as in the Fulton-Gibbs data*. Some of this scatter is due to differences in weekday and weekend occupancy and operations. Figure 4.12 shows weekly average demand as a function of weekly average temperature. Here the correlation between demand and temperature is not much better than the correlation for daily average data. Note that the sensitivity of New Panel demand (BowNew) to temperature is primarily due to equipment associated with operation of the chiller (BowAC). Also note, however, that there are large loads on the other feeder (labeled NonAC) that are sensitive to outdoor temperature. This indicates that there are packaged air conditioners operating in the building or that there are other pumps and fans in the building whose operation is associated with chiller operation.

Figure 4.13 shows the relation between four-week average demand and outside temperature. The points are connected in order to show their time

FIGURE 4.12. Bowditch Hall Demand, Not Including Old Panel Loads, vs. Temperature (Weekly Averages)

FIGURE 4.13. Bowditch Hall Demand, Not Including Old Panel Loads, vs. Temperature (Four-Week Averages)

sequence. Note that the points for the four-week averaging periods ending May 14 through October 29 describe a near-linear relation for the chiller circuit (BowAC). The average New Panel demand (BowNew) for the four weeks ending September 3 is the most deviant in terms of a postulated linear demand-temperature relation. It (and, to a lesser extent, the point for the period ending July 9) can only be explained by reduced occupant activity or operational changes in the building.

Therefore, based on the metered data and analysis, the same caution should be exercised in accepting any proposed outside temperature-driven linear model for predicting energy usage in this building as was the case for Bowditch Hall.

4.4 ANALYSIS OF LIBRARY ELECTRIC LOADS

Average weekday demand profiles for the Library are shown in Figure 4.14, and the corresponding weekend profiles are shown in Figure 4.15.

FIGURE 4.14. Average Weekday Profiles, Library

FIGURE 4.15. Average Weekend Profiles, Library

4.4.1 Baseload

The baseload ranges from a low of 5 kW in May 1991 to a high of 120 kW in summer. Note that the baseload dropped in mid-May from about 20 kW to 5 kW. This may have been due to seasonal changeover of heating pumps and fans or to operational changes made in response to the high baseload observations reported in the earlier report (see Appendix A). However, note that the baseload had not dropped from 20 kW to below 5 kW as of October 20, 1991.

4.4.2 Variable Loads

The daytime light and plug load is about 120 kWh per day on weekends and 200 kWh per day on weekdays. The intermittent air-conditioning load is about 250 kWh per day on weekdays and 120 kWh per day on weekends. The increase in summer baseload appears to be too large to be attributed entirely to air-conditioning load and is of unknown origin.

4.4.3 Relation Between Demand and Temperature

The procedure for assessing temperature-based whole building demand models that was applied to Bowditch and Fulton-Gibbs Hall was also applied to

the Library. Figure 4.16 shows daily average demand as a function of daily average outside temperature. The expected trend of increasing demand with increasing temperature is near-linear with the upper side of the curve being particularly well defined. This indicates that there is a consistent level of occupant activity during days when the building is fully used. The scatter on the underside of the curve indicates days when the chiller was not operating, the Library was closed, occupant activity was low, or lights and equipment were shut off for a larger than usual fraction of the day.

Figure 4.17 shows weekly average demand as a function of weekly average outdoor temperature. Here the slight upward curve due to decrease in COP with increasing temperature is clear and the evidence of entire weeks of low occupant activity and low chiller operation in warm months is also apparent.

Figure 4.18 shows the relationship between four week average demand and outside temperature. The points are connected in order to show their time sequence. It is interesting to compare the low points in this sequence to

FIGURE 4.16. Library Demand vs. Temperature (Daily Averages)

FIGURE 4.17. Library Demand vs. Temperature (Weekly Averages)

FIGURE 4.18. Library Demand vs. Temperature (Four-Week Averages)

those in the corresponding plot of Bowditch Hall data (Figure 4.14). The Library data behave as expected (i.e., are near linear) for consistent occupancy and chiller operation except for the four-week averaging periods ending June 11, July 9, and August 6. Therefore, an energy use model based on outside temperature may be appropriate for this particular building. Bowditch Hall, on the other hand, appears to be actively occupied and air-conditioned through June, July, and early August but has low energy use during the four weeks ending September 3.

5.0 RECOMMENDATIONS

Total daytime load for the three buildings is about 35 kW above the baseload of about 285 kW. It is likely that 40 to 60 percent of the daytime load is due to lighting, 30 percent to intermittent air-conditioning, and the balance to computers, copiers and other office equipment (plug loads). The incremental daytime lighting EUI intensity is therefore only about 0.8 w/ft²-yr. This implies that the existing interior lighting is extremely efficient, that the buildings are significantly underlit or, most likely, that a substantial fraction of the lighting operates 24 hours per day. If this is the case, a substantial savings can be realized through lighting controls alone.

There is clearly a large potential for savings in electric demand and consumption in the monitored buildings. Letting an SES contractor implement simple, hours-of-operation-reducing measures will lessen the contractor's incentive to look for longer payback energy conservation measures unless the implementation of such ECMs is specifically written into the contract. Also, a contractor may be less motivated to ensure that the longer payback ECMs are continuously maintained and properly operated. Such motivation is important because proper O&M of conservation measures is more difficult to contract, monitor, and enforce than their initial implementation.

The savings potential of O&M measures should be explored and low-cost and no-cost O&M improvements should be implemented by MMA maintenance staff, where practicable, prior to retaining an SES contractor. This will force the contractor to focus on capital-intensive retrofits--which are the facility owner's motivation for pursuing an SES arrangement in the first place.

Energy consumption is more variable on a college campus than in a typical office building complex. This poses difficulties in the calculation of energy savings that result from implementation of SES measures. Based on the results of the monitoring and analysis, a model that accounts for *variations in building occupancy* appears to be needed. The occupancy data to drive the model could come from schedules of classes and other programs, or it could

come from occupancy sensors that are part of the SES project that can be monitored by an energy management and control system.

Individual building metering and submetering (end-use metering) of chillers and other large equipment loads should be undertaken where feasible in order to better characterize these significant loads. Electronic registers that record average power over each hour, day, week, or month that can be recovered and stored in a computer are recommended. This is the most cost-effective check of accuracy that can be applied to SES energy consumption models.

Based on these observations and a general knowledge of recent progress in lighting technology, the following cost-effective retrofits should be considered:

- high-efficiency security lighting
- high-efficiency general (interior) lighting
- high-efficiency, photocell activated exterior lighting
- occupancy sensors for classrooms
- delamping and time-clocks or occupancy sensors for hall lights
- lighting on demand in the library stacks; the system should be designed to give 5-10 minutes of lighting in a single aisle initiated by a pushbutton at either end of the aisle.

Based on observations at the site and recent progress in HVAC technology and practice, the following HVAC retrofits should be considered:

- 2-speed or variable-speed fan motors, reduced airflow and operating hours
- 2-speed pump motors and impellers trimmed for actual flow and pressure
- high-efficiency motors for fans and pumps
- a plate heat exchanger to eliminate chiller operation in cool weather
- controls to modulate variable air volume (VAV) flow and static pressure by most needy zone

- time schedules and minimum-load thresholds for fans, chillers and window units.

Steps should be taken to ensure that any retrofits designed to reduce electrical demand or consumption do not make phase imbalances any worse. The retrofits should be designed to improve existing phase imbalances if possible.

The servicing electric utility (Long Island Lighting Company) offers a variety of demand-side management incentives and up-front financing for energy modernization at federal facilities. These incentives are particularly attractive for peak limiting. Energy-efficiency improvements could be combined with a program for site peak shaving through the use of existing diesel generators. Implementation of such a peak shaving system by the MMA or its SES contractor should be explored.

6.0 ECONOMIC ANALYSIS

The primary purpose of this project was to provide a baseline of electrical consumption at the U.S. Merchant Marine Academy. The selection of energy conservation measures and the economic feasibility of selected measures are beyond the scope of the project and are the responsibility of an SES contractor. There are, however, some general economic considerations that should be understood before selecting a contractor.

6.1 PAYBACK TIMES

It is to a contractor's benefit to only implement conservation measures that have short payback times. This leaves the facility with only relatively unattractive paths to further energy conservation in the future. The contractor should be required to keep adding progressively longer payback conservation measures until the payback time for the whole package reaches some agreed-upon maximum. In order for the MMA to be in compliance with federal guidelines, the projects need to be evaluated based on minimum life-cycle cost criteria set forth in 10 CFR Part 436, *Federal Energy Management and Planning Programs*. In addition, the maximum payback must satisfy the risk clause in 10 CFR Part 436. Progressively longer payback measures and projects must be included in the package of recommended ECMs (including all reasonable uncertainties in operating costs, equipment life, loads, and performance of each measure) until the net present value (NPV) of the measure is zero.

6.2 INTERACTIONS

Lighting and HVAC conservation measures interact. When implementing both lighting and HVAC measures, their performance cannot be determined individually; the change in energy consumption and demand must be determined for the system as a whole.

6.3 SHARED ENERGY SAVINGS

It is important to establish who is responsible for cleaning, adjusting and maintaining the equipment and controls that are installed as part of a

shared energy savings contract. This is to ensure that the equipment operates at peak performance and yields the expected savings through the term of the contract and beyond. This could even include one group relamping of a lighting retrofit. It is recommended that the contractor assume this responsibility during the term of the contract and that MMA personnel receive training during this period in order to be able to take over these responsibilities at the end of the contract period.

APPENDIX A

WHOLE BUILDING ELECTRIC DEMAND TESTS

**U.S. Merchant Marine Academy
Whole Building Electric Demand Tests**

SUMMARY

PURPOSE: The purpose of this test was to measure three phase power demand at the Library, Bowditch Hall and Fulton-Gibbs Hall. The data will provide a baseline for assessing energy savings resulting from future energy conservation measures that are to be implemented in the monitored buildings.

RESULTS: The three monitored buildings have a baseload of about 320 kVA and a daytime load of about 200 kVA above the baseload during the heating season. The baseload is high and the rise in daytime load is low compared to buildings of similar function. A significant fraction of the baseload probably consists of fans, lights, and office equipment that can be turned off at night and on weekends.

RECOMMENDATIONS: Lights and equipment that do not need to operate 24 hours per day should be controlled from occupancy sensors, photocells or time clocks. Demand lighting should be considered for the library stacks. High-efficiency lighting should be installed to replace older existing general, exterior, and security lighting fixtures. Selective delamping should be considered for halls.

Monitoring should continue through December 1991 to characterize electrical consumption through the cooling season and beyond to the winter Solstice. This extension of the monitoring period will establish an accurate baseline that includes the effects of day length. Steps should be taken to ensure that any retrofits designed to reduce electrical demand or consumption do not make phase imbalances any worse. The retrofits should be designed to improve existing phase imbalances if possible.

TEST REPORT

1.0 MEL APPLICATION

This Mobile Energy Laboratory application was initiated to measure three-phase power demand of three large buildings at the U.S. Merchant Marine Academy. The selected buildings are the Library, Bowditch Hall and Fulton-Gibbs Hall. The MEL equipment was installed on 17 March 1991 and 23 March 1991. The data will provide a baseline for assessing energy savings resulting from future energy conservation measures that are to be implemented in the monitored buildings. The equipment will remain in place until 1 August 1991 or longer if continued monitoring is needed to verify the savings of energy conservation measures. MEL Test Procedure #7, Electrical Load Evaluation, was followed in the installation and operation of the monitoring equipment.

2.0 DEFINITIONS

CT: current transformer.

load: the power or apparent power required by a building or end-use.

baseload: the constant part of a time varying load.

Units of Measure:

A: ampere

V: Volt

kW: kilowatt

kVA: kilovolt-ampere

W/sf: Watts per square foot

3.0 PLANT DESCRIPTION

Fulton-Gibbs Hall contains engineering classrooms and laboratories. It also contains the central boiler plant and steam laboratory. The gross floor area of Fulton-Gibbs Hall is 100,302 square feet and the net area is 96,598 square feet. The engineering classrooms are cooled by central electrically driven air-conditioning.

Bowditch Hall contains classrooms and a rifle range. Gross and net floor areas are 61,390 and 58,725 square feet. Bowditch Hall is cooled by a 200-ton centrifugal chiller.

The gross and net floor area of the Library are 31,100 and 29,340 square feet. The Library is cooled by two 60-ton reciprocating direct-expansion air-conditioning units.

4.0 TEST INSTRUMENTS AND APPARATUS

Four 3-phase power circuits were instrumented at two locations.

A Synergistics C180, s/n 00202, power analyzer/logger was installed in the Bowditch Hall electrical vault; this vault contains the service entrances to both the Library and Bowditch Hall. Three AEMC 1000/2000:1 jaw type CTs, configured for the 1000:1 turn ratio, were installed on the Library mains. A potential brick was installed at an abandoned breaker served by the same transformer (5B) as the Library. Three 1-amp in-line fuses were installed at the breaker terminals. Three 1200:5, five-inch (i.d.) window CTs were installed on the mains to the new Bowditch distribution panel, which includes the chiller circuit. The new panel is the only load on transformer 5A. A potential brick was installed at a spare breaker in the panel and three 1-amp in-line fuses were installed at the breaker terminals.

A second Synergistics C180, s/n C1223, was installed in Fulton-Gibbs Hall. Three 2500:5, eight-inch (i.d.) window CTs were installed on the mains into

the NW switchgear cabinet. A potential brick was installed at an abandoned transfer switch and three 1-amp in-line fuses were installed at the switch terminals. Three 3000:5, eight-inch (i.d.) window CTs were installed on the mains into the SE switchgear cabinet. A potential brick was installed at an abandoned transfer switch and three 1-amp in-line fuses were installed at the switch terminals.

A 1/16-inch sheathed Type-K thermocouple was installed in the emergency generator cooling air louvre and a MEL Type-K thermocouple amplifier/reference finger card was installed in the C180 at Fulton-Gibbs to measure outdoor air temperature.

5.0 TEST DIAGRAM

The four monitored circuits are all 120 V, 3-phase wye circuits. The instrumentation diagram for monitoring one circuit is shown below.

6.0 TEST RESULTS

Continuous data have been logged for four weeks, starting on 18 March, with the exception of 29 March and 1 April when phone line problems prevented uploading of data to the MEL polling computer in Richland, WA. The demand profiles observed during this period are discussed below.

6.1 Fulton-Gibbs Hall

Electric demand was monitored at the two main switches located along the northwest and southeast sides of the service entrance switchgear room. The two circuits are designated NW Switch and SE Switch. The electric demands for Fulton-Gibbs Hall are plotted in Figure A.1. The NW Switch has a baseload of about 100 kVA. The daytime load ranges from 20 to almost 30 kVA higher than the base load. Note that demands are lowest during the week beginning 25 March. Also note the gradual decrease in baseload over the week beginning 18 March and the more abrupt return of the baseload on 10 April. These changes are not correlated with outside temperature.

The SE Switch has a baseload of about 20 kVA and daytime loads in the heating season range from 3 to 6 kVA above the baseload. The lowest baseload and daytime loads occur in the week beginning 25 March. During warm weekday afternoons (4/05, 4/03, 4/09 and 4/12), there are large demand peaks that result from air-conditioner operation. The relation between demand and temperature is not very consistent because cooling demands are relatively light at this time of year and are therefore affected as much by internal gains, set point changes and past operating conditions as by outside temperature.

6.2 Bowditch Hall and Library

The electrical demands of Bowditch Hall and the Library are shown in Figure A.2. There was insufficient time to schedule site electricians to instrument all three circuits that have to be monitored to segregate the loads properly. Therefore, data were taken on the circuits that feed the old distribution panel in Bowditch during the week beginning 18 March, and the current transformers were then moved to the circuit that feeds the Library on the morning of 24 March. From the week of monitoring the old distribution panel (Bowditch 5B), a baseload of 40 kVA and daytime loads that are about 45 kVA above the baseload are observed. The load on the new distribution panel (Bowditch 5A), on the other hand, is much more constant, with a baseload of 105 kVA and daytime loads of 2 to 12 kVA above baseload. The daytime loads are both lowest during the week beginning 25 March, but the reduction in baseload is almost imperceptible.

The Library baseload ranges from 45 to 60 kVA. The daytime load is 70 to 75 kVA above the baseload on weekdays. Daytime loads are only 40 to 45 kVA above the baseload, and of shorter duration, on the weekends of 23-24 March and 30-31 March. Note that the duration of weekday daytime loads is slightly less during the week beginning 25 March, but that demand magnitudes, except during daytime hours of 26 March, are unchanged.

7.0 RECOMMENDATIONS

Total daytime load for the three buildings is about 200 kVA above the baseload of about 320 kVA. It is likely that 70 to 85 percent of the daytime load is lighting and the balance is primarily computers, copiers and other office equipment. This translates to only about 1.0 W/sf. Properly designed security lighting should account for less than 10 percent of the baseload or 0.15 W/sf. Unless the existing lighting is extremely efficient, the buildings are either significantly underlit or a significant fraction of the lighting load is operating 24 hours per day.

Based on these observations and a general knowledge of recent progress in lighting technology, we recommend that the following retrofits be considered:

- high-efficiency security lighting
- high-efficiency general lighting
- high-efficiency, photocell activated exterior lighting
- occupancy sensors for classrooms
- delamping and time-clocks or occupancy sensors for hall lights
- lighting on demand in the Library stacks; the system should be designed to give 5-10 minutes of lighting in a single aisle initiated by a pushbutton at either end of the aisle.

For a more thorough characterization, a seasonal electric demand baseline should be established from the demand data that will be compiled between now and August 1991.

8.0 ECONOMIC ANALYSIS

The purpose of the test was to provide a baseline of electrical consumption. The selection of energy conservation measures and the economic feasibility of selected measures will be up to a shared-energy-savings contractor. There are, however, some general considerations that should be understood before selecting a contractor. These are discussed below.

Payback Times. It is to a contractor's benefit to only implement conservation measures that have short payback times. This leaves the site only relatively unattractive paths to further energy conservation in the future. The contractor should be required to keep adding progressively longer payback conservation measures until the payback time for the whole package exceeds some agreed-upon maximum.

Interactions. Lighting and HVAC conservation measures interact. When implementing both lighting and HVAC measures, their performance cannot be determined individually; the change in energy consumption and demand must be determined for the system as a whole.

Shared Energy Savings. It is important to establish who is responsible for cleaning, adjusting and maintaining the equipment and controls that are installed as part of a shared energy savings contract. It is logical that the contractor should have the responsibility during the term of the contract and that Merchant Marine Academy personnel should receive training during this period in order to be able to take over these responsibilities at the end of the contract period.

FIGURE A.1. Electrical Demand and Outside Temperature Measured at Fulton-Gibbs Hall

FIGURE A.2. Electrical Demand Measured at the Library and Bowditch Hall

APPENDIX B

BOILER EFFICIENCY TESTS

U.S. Merchant Marine Academy Boiler Efficiency Tests

SUMMARY

PURPOSE: The purpose of this test was to measure combustion and delivery efficiencies of the two boilers in the Academy's central steam plant and assess possible efficiency improvements.

RESULTS: The delivery efficiency of Boiler #1 ranged between 65 and 70%. The delivery efficiency of Boiler #2 ranged between 64 and 67%. The efficiency difference is almost certainly due to the limited retubing of Boiler #1 that was completed in 1988 or 1989. The fuel-air ratio controls of Boiler #1 appear to need repair.

RECOMMENDATIONS: The boiler efficiencies can be improved by improving combustion air and burner controls, preheating combustion air with a stack recovery heat exchanger, and by reducing steam pressure. The effect of a reduction in steam pressure can be achieved by installing a larger stack recovery heat exchanger.

Reductions in steam demand can be achieved by improving controls, repairing leaks and eliminating any non-return loads that exist.

An administrative effort will be needed to fund these projects because the justification for replacing old equipment is based partly on energy savings and partly on operations and maintenance (O&M) savings.

TEST REPORT

1.0 MEL APPLICATION

This Mobile Energy Laboratory application was initiated to measure boiler efficiencies at the central heating plant of the U.S. Merchant Marine Academy. Boiler #1 was monitored between 14 and 19 March 1991; Boiler #2 was monitored between 19 and 22 March 1991. MEL Test Procedure #8, Boiler Efficiency Evaluation, was used to conduct the tests.

2.0 DEFINITIONS

CO: carbon monoxide; usually refers to CO present in the stack.

Combustion air: air supplied to the firebox to support combustion.

Excess air: fraction of combustion air beyond what is theoretically needed.

O2: molecular oxygen; usually refers to O2 present in the stack.

Stack: boiler exhaust pipe or chimney.

Stack gas: combustion products, depleted air and unburned fuel.

Theoretical air: amount of combustion air required by reaction stoichiometry.

Units of Measure:

Btu: British thermal unit.

Btuh: Btu per hour.

Btu/s: Btu per second.

cfm: cubic feet per minute.

F: degrees Fahrenheit.

HHV: higher heating value (Btu/lbm or Btu/gallon)

MBtu: million Btu

MBH: million Btu per hour.

MCF: million cubic feet.

psf: pounds per square foot.

R: degrees Rankine.

3.0 PLANT DESCRIPTION

The two boilers are identical Babcock and Wilcox marine type water-tube boilers that have been in service since 1942. Each boiler is rated at 25MBH output at 250 psig steam pressure. One boiler is sufficient to meet peak steam demand. The lead boiler is alternated each year and the lag boiler is left on cold standby. The boilers are fired by #2 fuel oil from 1 December through 31 March and by natural gas during October, November, April and May. The steam is used to provide space heat and domestic hot water in all major buildings except for the Museum and the new facilities engineering and maintenance buildings.

4.0 TEST INSTRUMENTS AND APPARATUS

The boilers were tested in succession; the same instruments were therefore used to test both boilers.

A Neotronics Model PCO combustion analyzer was used for combustion efficiency measurements. A 1/16-inch-diameter sheathed Type-K thermocouple probe was used to measure combustion air temperature in the combustion air duct that runs under the boiler room floor at a point just upstream of the windbox inlet dampers.

An Engineering Measurements Company (EMCO) Model EMS-3270 (s/n C608053-G002) flow computer with rotor model 150-030-U-DEV (s/n 504008, rotor no. A004) was installed in the steam line of each boiler, at a point 4 feet downstream of the existing orifice meter. Temperature differences were measured by 1/16-inch-diameter sheathed Type-T special limits thermocouple probes connected as thermopiles. Temperature differences were measured from combustion air to feedwater, feedwater to steam, steam to flue gas, and flue gas to combustion air.

The water and steam probes were installed as pipe surface temperature probes; combustion side probes were inserted directly into the fluid streams. Thermopile voltages were amplified by MEL TP signal conditioner cards (#17, #18, #19, #20) configured for a gain of 201 ± 0.1 . System accuracy for temperature differences was $\pm(0.4F + 0.4\% \text{ of reading})$. Fuel oil flow was measured by the existing Neptune model VLF-20-90505-001 PD meter, accuracy $\pm 1.0\%$, repeatability $\pm 0.25\%$ at 390 gph. A reed contact was attached to the meter shaft at the magnetic coupling to obtain four contact closures per revolution. A divide-by-eight circuit was used to scale the pulse rate for the data logger. A Synergistics C180 data logger, s/n 1224, was used to record steam and fuel oil meter pulses, combustion air temperature, and the four temperature differences.

5.0 TEST DIAGRAM

Sampling points for the combustion efficiency test are indicated below.

Sampling points for the delivery efficiency test are indicated below.

6.0 TEST RESULTS

The results of the combustion efficiency tests and the delivery efficiency tests are consistent. The measured efficiencies are lower than the numbers assumed in the Burns and Roe (BRISC) report, *Heating Plant System Upgrade Feasibility Study for the USMMA*, March 1990. Boiler #1 is about 2 percentage points (3%) more efficient than Boiler #2. A difference of this magnitude is consistent with the fact that a partial retubing of Boiler #1 was recently completed. The efficiency test results are summarized below.

	<u>Average Measured Efficiencies</u>		<u>Difference</u>
	Combustion	Delivery	Combustion - Delivery
Boiler #1	77.1%	67.7%	9.4%
Boiler #2	72.8%	65.5%	7.3%

6.1 Combustion Efficiency Tests

Combustion efficiencies were sampled at random times and the number of samples is much smaller than the number of samples used to compute the average delivery efficiencies. The delivery efficiency data are therefore considered more reliable. The combustion efficiency data are plotted in Figure B.1.

6.2 Delivery Efficiency Tests

The average delivery efficiency is based on continuously sampled steam and fuel flow rates integrated over 5-minute intervals. Steam and feedwater enthalpies are based on temperatures sampled every 9 seconds and averaged over 5-minute intervals. The measured and calculated variables pertaining to delivery efficiency are plotted in Figure B.2 for Boiler #1 and in Figure B.3 for Boiler #2.

The difference between measured combustion and delivery efficiencies indicates that jacket losses, auxiliary steam and blowdown losses are significant, amounting to about 5% of fuel input.

6.3 Fuel-Air Ratio Controls

An evaluation of stack loss versus firing rate was made to assess the condition of boiler controls. A scatter plot of stack temperature (T_{stack}) minus steam temperature (T_{steam}) is shown for Boiler #2 in Figure B.4. There are three distinct operating curves. The response for each curve is consistent with theoretical boiler response, i.e. stack losses increase with firing rate. The difference between curves is likely due to discrete changes in operating parameters. Occasional adjustment of the combustion air blower's inlet vanes and changes in the number (or combination) of active burners are the most likely causes for the distinct response regimes that appear in the plot. Within each regime, however, it is clear that the fuel-air ratio is constant or a smoothly varying function of firing rate.

The corresponding data for Boiler #1 appear in Figure B.5. There appears to be little or no systematic relation between stack loss and firing rate. From these data it is apparent that the fuel-air ratio controls in Boiler #1 are not functioning properly.

7.0 RECOMMENDATIONS

The boiler energy conservation measures that should be considered include boiler retubing, combustion air preheat by stack heat recovery, improved burner controls, excess air trimming controls, and steam pressure reduction. Measures that should be considered on the load side are improved load controls and elimination of any existing non-return loads.

8.0 ECONOMIC ANALYSIS

Preliminary estimates of time-to-payback are made in this section for retrofitting a stack recovery/combustion air preheat heat exchanger and several other energy conservation measures. The results of this analysis indicate that a number of retrofits should be economically attractive to a shared-energy-savings (SES) contractor.

8.1 Cost of Fuel

The cost of #2 fuel oil for the MMA was \$386,464 for 535,091 gallons, or \$5.16/Mbtu(HHV), in FY90. The average cost of natural gas in April and May of 1989 was \$4.97/MBtu(HHV). The central boiler plant produces about 2/3 of its steam by burning #2 fuel oil and the other 1/3 by burning natural gas; this gives a weighted average fuel cost of about \$5.10/MBtu(HHV) in FY90. The average cost of electricity during the months of boiler operation currently is \$.0649/kWh from 00:00 to 07:00 daily and \$.0804/kWh + \$4.56/(peak monthly kW) from 07:00 to 24:00 daily.

8.2 Stack Recovery Equipment

Equipment Cost. Heat exchanger costs are customarily estimated on a per-unit-flow-rate basis. For stack recovery/combustion air preheat applications this can be readily translated to a per-unit-heating-capacity basis as follows. Combustion of 1 mole #2 fuel oil requires 99 mole of air (assuming 12% excess air and 0.003 lbm water/lbm dry air humidity) and produces 129 mole of flue gas. (Note that steam for atomization is a negligible fraction of the flue products.) Assuming a higher heating value for #2 fuel oil of 19,500 Btu/lbm and operation at sea level gives a combustion air flow rate of 159 cfm/MBH at 70F and a flue gas flow rate of 273 cfm/MBH at 250F. Pacific Gas & Electric Application Note 22 lists the initial equipment and installation cost at \$3.50 per cfm combustion air in 1990 dollars. RS Means, Mechanical Cost Data 1990, gives a cost of \$.60 per cfm, stack conditions, which corresponds to \$1.03 per cfm, combustion air inlet conditions, for a draft induction blower and motor (service to 600F). To this add \$0.50 per combustion air cfm for regulating dampers. Thus the heat exchanger will cost $\$5.03 \times 159 = \800 /MBH of input capacity.

Installation of the heat recovery equipment may entail replacing significant portions of the horizontal flue run. The replacement flue can be smaller because the induction fan will allow a higher pressure drop. A 36-inch-diameter insulated stainless steel flue will have an installed cost of about \$250/foot.

Recovery Fraction. The recovery fraction is limited by the acid dew point of the flue products, which determines the minimum flue gas discharge temperature from the flue gas side of the heat exchanger. The acid dew point is 180F for fuels containing less than 2% Sulfur. The discharge temperature can approach 180F if the flue is well insulated and the cold surfaces of the heat exchanger are corrosion resistant. If either condition cannot be met, a discharge temperature of 250F is the practical minimum. The recovery fraction is given by:

$$f_{\text{stack}} = \text{Eff}(T_{\text{netHXout}}) - \text{Eff}(T_{\text{netHXin}})$$

where

T_{netHXin} = 425F - 80F is the net stack temperature at the recovery heat exchanger inlet (after correcting the excess air problem),

T_{netHXout} = 250F - 80F is the net stack temperature at the recovery heat exchanger outlet, and

$\text{Eff}(T_{\text{net}})$ = combustion efficiency for a specified fuel and excess air fraction.

For excess air fractions of 7.5 to 12.5%, and the net stack temperatures given above, the recovery fraction is 3.9% for both natural gas and #2 fuel oil.

Energy Savings. The central plant consumes about 110,000 MBtu(HHV) of gas and oil in a heating season. The estimated annual savings produced by stack heat recovery is therefore $.039 \times 110,000 = 4,300$ Mbtu or \$22,000/year.

Cost of Operation. An annual cost to clean and maintain the stack recovery heat exchanger equal to 20% of installed first cost or \$160/MBH-year is assumed. The one other significant operating cost is electric power for the induced draft fan. With a pressure drop of 4 psf on the air side, 4 psf on the flue gas side, and 1 psf additional through the existing system (due to lost natural draft), and assuming an overall motor-fan efficiency of 0.7, the additional operating power will be 0.3 Watt per cfm or 0.08 kWh per MBtu boiler input. This corresponds to a cost of \$0.0061 per MBtu boiler input plus \$39/month (\$312/year) in demand charges. The annual cost of operation is therefore $0.2 \times \$800 \times 25 + 110,000 \times \$0.0061 + 8 \times \$39 = \$4,983/\text{year}$.

Time to Payback. The net savings is $\$22,000 - \$4,983 = \$17,000/\text{year}$. The initial cost of heat recovery equipment and installation is $25 \times \$800 = \$20,000$. An additional cost of \$25,000 will be required if the existing horizontal flue duct is replaced. The estimated payback time therefore ranges from 1.2 to 2.6 years.

8.3 Excess air trimming control. A closed loop controller can be used to continuously trim the excess air fraction based on stack O_2 and CO content.

The installed cost of a unit to serve both boilers will cost \$15,000. A combustion efficiency analyzer (needed to check and maintain the excess air controls) will cost an additional \$3000. Maintenance will cost an estimated \$2000 per year. It may also be necessary to replace the windbox assembly and burners to reap the full benefits of closed loop excess air control; this will cost \$45,000 for both boilers. The controller and new burners will allow excess air fraction to be reduced from 120% to 15% corresponding to an increase in boiler efficiency from 75% to 82.5%, for an annual savings of about \$30,000. The net annual savings will therefore be \$28,000 per year, giving a time-to-payback of about 2.3 years. A properly maintained mechanical fuel-air ratio modulator may yield nearly the same savings at lower first cost.

8.4 Steam Pressure Reduction. Reducing the steam pressure from 200 psig to 55 psig will reduce the stack temperature by about 80 R. This will increase boiler efficiency by about 2.5% (or 4.5% if the excess air problem is not first corrected) and result in an annual savings of about \$10,000. The cost of converting the atomizers to compressed air will be about \$10,000. There will also be about \$1000 per year in additional compressed air maintenance costs.

8.5 Interactions. Not installing the excess air-trimming controls will about double the size of the heat recovery equipment required. However, costs and savings both increase in proportion to heat stack flow rate, so the payback for heat recovery equipment is not significantly affected by the presence or absence of air-trimming controls.

A reduction in steam pressure will reduce the stack recovery fraction that can be achieved without condensation. An air washer should therefore be installed where the stack gases exit the recovery heat exchanger to remove corrosive gases. (The washer water can be circulated through a heat exchanger at the combustion air inlet of the main recovery heat exchanger to increase the recovery fraction, albeit at a higher incremental cost.) The extra cost of the washer will increase the time-to-payback for the stack recovery measure.

8.6 Complete Boiler Replacement. Complete boiler replacement options were analyzed in the BRISC study. It is important in pursuing any of the boiler replacement scenarios that the efficiency of new heating boilers be at least that which can be achieved by implementing all of the economically feasible improvements to the existing boilers that have been presented above, i.e., at least 88% for operation between 10MBH and 20MBH net output on #2 fuel oil with 40F combustion air.

8.7 Operations and Maintenance. It is important to establish who is responsible for cleaning, adjusting and maintaining the equipment and controls that are installed as part of a shared energy savings contract. It is logical that the contractor should have the responsibility during the term of the contract and that the MMA personnel should receive training during this period in order to be able to take over these responsibilities at the end of the contract period.

FIGURE B.1. Results of Boiler Combustion Efficiency Tests

FIGURE B.2. Results of Boiler #1 Delivery Efficiency Test

FIGURE B.3. Results of Boiler #2 Delivery Efficiency Test

FIGURE B.4. Boiler #2 Stack Loss: Approach Temperature vs. Firing Rate

FIGURE B.5. Boiler #1 Stack Loss: Approach Temperature vs. Firing Rate

APPENDIX C

DEFINITIONS OF TERMS AND UNITS OF MEASURES

APPENDIX C

DEFINITION OF TERMS AND UNITS OF MEASURE

TERMS

CT - current transformer

Load - the power or apparent power required by a building or end-use

Winter baseload - constant part of a time-varying heating season load

Summer baseload - constant part of a time-varying cooling season load

Added summer baseload - difference between summer and winter baseloads

Intermittent load - difference between total load and baseload

Energy use intensity (EUI) - annual energy consumption divided by gross floor area

End-use - a class of energy-using devices that serve a specified function

Group relamping - a maintenance program activity in which all bulbs are replaced at the same time

UNITS OF MEASURE

A - ampere (electric current)

V - Volt (electric potential)

kW - kilowatt (electric power)

kWh - kilowatt-hour (electric energy)

MWh - megawatt-hour (electric energy)

kVA - kilovolt-ampere (apparent electric power)

Btu - British thermal unit (thermal energy)

W/ft² - power density in watts per square foot of floor area

kWh/ft²-yr - average power density in kilowatt-hours per square foot per year

Ton - A unit of measure of cooling plant capacity equal to 12,000 Btu/hr

DISTRIBUTION

No. of
Copies

OFFSITE

12 DOE/Office of Scientific and
Technical Information

K. Dean Devine
Federal Energy Management
Program
U.S. Department of Energy
1000 Independence Avenue SW
CE-10.1
6A-034/FORS
Washington, DC 20585

T. Collins
Federal Energy Management
Program
U.S. Department of Energy
1000 Independence Avenue SW
CE-10.1
46A-034/FORS
Washington, DC 20585

2 J. White
MARAD
Department of Transportation
400 7th St. S.W.
Washington, DC 20590

No. of
Copies

2 K. Sendlein
U.S. Merchant Marine Academy
Kings Point, NY 11024-1699

ONSITE

DOE Richland Field Office

D. L. Segna

19 Pacific Northwest Laboratory

P. A. Armstrong
R. Bartlett
J. W. Currie
B. L. Mohler
G. B. Parker (2)
D. R. Payson
W. F. Sandusky
R. W. Reilly
J. L. Stoops
R. F. Szydlowski
Project File (2)
Publishing Coordination
Technical Report Files (5)

END

**DATE
FILMED**

8 / 12 / 92