468
4/14/80

Lh. 1540

SAN-1137-14

GEOTHERMAL LOOP EXPERIMENTAL FACILITY

Quarterly Report for the January—March 1979

By
G. Anastas
W. S. Bischoff
H. K. Bishop
J. L. Fe
C. H
W

U66 X

MASTER

Work Performed Under Contract No. EY-76-C-03-1137

San Diego Gas & Electric Company
San Diego, California

U. S. DEPARTMENT OF ENERGY

Geothermal Energy

REPRODUCTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

DISCLAIMER

"This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof."

This report has been reproduced directly from the best available copy.

Available from the National Technical Information Service, U. S. Department of Commerce, Springfield, Virginia 22161.

Price: Paper Copy \$13.00
Microfiche \$3.50

SDG&E - DOE
GEOTHERMAL LOOP EXPERIMENTAL FACILITY
QUARTERLY REPORT
FOR THE PERIOD
JANUARY - MARCH, 1979

G. Anastas
W. S. Bischoff
H. K. Bishop
J. L. Featherstone - Imperial Magma
C. H. Haas
W. H. Hanenburg
G. J. Hoaglin
W. O. Jacobson
J. P. Kozic
D. K. Mulliner - New Albion Resources Co.
D. G. Newell
R. J. Peirce
R. Quong - Lawrence Livermore Laboratory

APRIL, 1979

San Diego Gas & Electric Company
P.O. Box 1831
San Diego, California 92112

Prepared for the
Department of Energy
Under Contract No. EY-76-C-03-1137

REPRODUCTION OF THIS DOCUMENT IS UNLIMITED

TABLE OF CONTENTS

	<u>Page No.</u>
Abstract	1
Concise Description of the Niland GLEF	2
Quarterly Report	5
Introduction	5
1.0 Plant Operation	6
2.0 Reservoir Operation	12
2.1 Production Wells	12
2.2 Injection Wells	12
3.0 Testing	14
3.1 1976-1977 GLEF Test Program	14
3.2 1978-1979 GLEF Test Program	14
Test No. 1.0 Scale Removal	16
Test No. 2.0 Scale Properties	17
Test No. 3.0 Scale Control Additives	19
Test No. 4.0 Corrosion/Erosion	21
Test No. 5.0 Corrosion/Erosion Parameterization	23
Test No. 6.0 Plant Components and Instrumentation	24
Test No. 7.0 Brine Chemistry	25
Test No. 8.0 H ₂ S Abatement	26
Test No. 9.0 Steam Separation	27
Test No. 10.0 Injection Effluent Processing	28
Test No. 11.0 Makeup Water Injection Compatibility	29

	<u>Page No.</u>
Test No. 12.0 Well-Casing Materials	30
Test No. 13.0 Injection Studies	31
Test No. 15.0 Scale Control-Inhibitors	32
4.0 Systems Chemistry	33
4.1 Steam	34
4.2 Brine	36
4.3 Binary and Cooling Water	37
4.4 Scale	38
4.4.1 Scale From Magmamax No. 1 Utilizing B Train	39
4.4.2 Scale From Woolsey No. 1 Utilizing A Train Before Schedule Shutdown	39
4.4.3 Scale From Woolsey No. 1 Utilizing A Train After The Schedule Shutdown	40
4.5 Future Projects	41
5.0 Maintenance	42
5.1 Supply Lines	42
5.1.1 Woolsey No. 1 Supply Line	42
5.1.2 Magmamax No. 1 Supply Line	42

	<u>Page No.</u>
5.2 A Train	43
5.2.1 1st Stage Separator (V-1) and Drain Line	43
5.2.2 1st Stage Scrubber (V-8)	44
5.2.3 2nd Stage Separator (V-14) and Drain Line	46
5.2.4 2nd Stage Scrubber (V-10)	46
5.3 B Train	47
5.3.1 1st Stage Separator (V-4) and Drain Line	47
5.3.2 1st Stage Scrubber (V-8)	48
5.3.3 2nd Stage Separator (V-11) and Drain Line	48
5.3.4 2nd Stage Scrubber (V-12)	49
5.4 Valves	51
5.4.1 Pinch Valve (Red)	51
5.4.2 Pinch Valve (Galigher)	51
5.4.3 PCV 300	52
5.4.4 LCV 712	53
5.4.5 LCV 718A	53
5.4.6 PCV 301/LCV 714/Misc	55
5.5 Atmospheric Flash Vessel (V-15)/ P-2 Suction Piping	55
5.6 Injection Pump P-2/P-17	56
5.7 Injection Line	61
5.8 Heat Exchangers	64

	<u>Page No.</u>
5.8.1 1st Stage Heat Exchangers (E-2/E-3)	64
5.8.2 2nd Stage Heat Exchangers (E1B/E1C)	64
5.9 Cooling Water (C.W.) Condensers (E4A/E4B)	64
6.0 GLEF Reactor Clarifier/Media Filter Installation	66
6.1 Purpose	66
6.2 Description of Project Organization	66
6.3 Technical Description of Facility	66
6.4 Current Project Status	69
7.0 Other Activities	71
7.1 Feasibility Study	71
7.2 Direct Contact Heat Exchanger	71
7.3 Surge Study	72
7.4 Noncondensable Gas Content	73
7.5 Pilot Clarifier Testing	74
8.0 Summary	75

LIST OF TABLES

	<u>Page No.</u>
1-1 GLEF Availability by Months	6 a
1-2 Outages	6 c
1-3 Typical Operating Conditions for Woolsey No. 1	7 a
2-1 Chemical Composition IW-5	13 a
3-1 Scale Removal/Control Additives	16 a
3-2 Coupons - Test No. 4.0	22 a
3-3 General Atomic Coupons	22 d
3-4 Plant Components and Instrumentation	24 a

LIST OF FIGURES

	<u>Page No.</u>
0-1 Pictorial of the GLEF	2a
0-2 GLEF Typical Flow Diagram (Two Stage)	4a
1-1 GLEF Availability Months	6b
3-1 Coupons - Test No. 4.0 - 1st Stage, B Train (V-4)	22b
3-2 Coupons - Test No. 4.0 - 2nd Stage, B Train (V-11)	22c
5-1 Scale Locations, 1A Separator (V-1)	43a
5-2 Scale Locations, 2A Separator (V-14)	46a
5-3 Vortex Breaker Detail	49a
5-4 Ultrasonic Thickness Readings (V-12)	50a
6-1 GLEF Reactor Clarifier/Media Filter Process Flow Diagram	66a
6-2 Clarifier/Filter Installation Start-up Schedule	69a

APPENDICES

- A. Steam Constituents
- B. Brine Constituents
- C. Binary and Cooling Water Constituents
- D. Scale Constituents - Magmamax No. 1 Utilizing B Train
- E. Scale Constituents - Woolsey No. 1 Utilizing A Train
Before Shut-Down
- F. Scale Constituents - Woolsey No. 1 Utilizing A Train
After Shut-Down
- G. P-2 Pump Failure Investigation by Bechtel National, Inc.

ABSTRACT

Since the Geothermal Loop Experimental Facility (GLEF) Start-Up in May, 1976, a substantial amount of information has been obtained on the operation of the plant, components, brine and steam composition, production and injection wells, and the potential of the Niland Reservoir. The GLEF was modified in April, 1978, from a four stage flash/binary process to a two stage cycle for the extraction of energy from a high temperature, high salinity, liquid-dominated resource.

This Quarterly summarizes the general operations and accomplishments of the GLEF during the period from January 1, 1979 through March 31, 1979. The construction and installation of a reactor clarifier/media filter system to treat the effluent brine continued. Startup is expected during the next reporting period. Operations of the facility evaluated the two stage flash cycle characteristics of brines from the second production well (Woolsey No. 1). The results were similar to the characteristics of the first production well (Magmamax No. 1) that were reported previously. The 1979 test program has been initiated and preliminary results documented.

CONCISE HISTORY AND DESCRIPTION OF THE NILAND GLEF

Early in 1972, the concept of building a Geothermal Loop Experimental Facility (GLEF) at the Niland Known Geothermal Resource Area (KGRA) was originated. This area is located on the southern shore of the Salton Sea near Niland, California. SDG&E, in cooperation with Magma Power Company, drilled and flowed geothermal test wells to demonstrate the ability of the Niland Reservoir to produce a significant amount of hydrothermal fluid capable for the production of electric power.

In May, 1975, construction of the GLEF began and start-up of plant operations commenced on May 3, 1976. Figure 0-1 shows the general appearance of the GLEF. This size facility is the first of its kind for testing high temperature (in excess of 500°F downhole) and high salinity (over 200,000 ppm) geothermal resources.

Imperial Magma Company, jointly with the New Albion Resource Company (NARCO), supply geothermal fluid (brine) from two production wells, Magmamax No. 1 and Woolsey No. 1, located near the test facility. Magmamax No. 1 produces brine with a typical temperature and pressure at the wellhead of 440°F and 350 psig, respectively, with a capability of flowing approximately 400,000 lbs/hr. Woolsey No. 1 has produced brine with a typical temperature and pressure

- 2a -

FIGURE 0-1

**GEOHERMAL LOOP EXPERIMENTAL FACILITY
Niland, California**

at the wellhead of 380°F and 200 psig, respectively, with a capability of flowing approximately 300,000 lbs/hr. The plant has been designed to accept a two-well flowrate of approximately 800,000 lbs/hr. After the produced brine has flowed through the plant, it is then injected into the reservoir approximately one mile away through one of two injection wells, Magmamax No. 2 or No. 3. Since the performance decline of Magmamax No. 3, Magmamax No. 2 is now being used as the primary injection well. Based upon experience and data from these two injection wells, an effluent treatment system (the GLEF Clarifier/Filter Installation) is being constructed to minimize injection well performance declines. A new injection well (IW-5) was drilled and will be utilized to test the injection of treated brine from the Clarifier/Filter Installation.

In April 1978, the plant was shutdown for modification to a two stage flash cycle simulation. A feasibility study completed in early 1978 based on GLEF operating data, identified a two stage flash cycle as the optimum cycle for initial power plants at Niland. However, critical questions on brine handling needed to be resolved. Therefore, the plant was converted from the original four stage flash/binary system to a "simulation" of a two-stage flash/binary system (Figure 0-2). Critical portions of a two stage flash system with two parallel flash "trains" were simulated and a maximum

use of existing equipment was made to conserve funds. Each supply well has a separate set of flash vessels. The steam produced by the flashed brine passes through steam scrubbers to remove entrained brine containing salts and minerals. A turbine was not installed to conserve capital. The heat of the scrubbed steam is dissipated by four heat exchangers at a design rate of 200,000 lbs/hr, partially vaporizing the binary fluid. The condensed steam is primarily used for cooling water make-up, but can be recombined with the brine and injected into the reservoir for test purposes. The noncondensable gases separated in the heat exchangers are primarily carbon dioxide, with small amounts of other gases including hydrogen sulfide. These gases are exhausted to the atmosphere through a 130 foot high stack for dispersion.

In addition to testing the critical portions of the two stage flash process, evaluation of the reservoir is underway. Effects of injecting brine after clarification will also be evaluated. San Diego Gas & Electric Company (SDG&E) owns the facility and manages its testing. SDG&E and the United States Department of Energy (DOE) jointly fund the activities of the facility.

E-2 & 3
1ST STAGE EXCHANGERS

V-1
1ST STAGE BRINE FLASH DRUM
78"φ × 20'-0" T-T

V-4
1ST STAGE BRINE FLASH DRUM
66"φ × 20'-0" T-T

V-8
1ST STAGE STM. SCRUBBER
84"φ × 14'-0" T-T

V-6
VENT GAS SEPARATOR
36"φ × 10'-0" T-T

E-1B
2ND STAGE EXCHANGER

V-10
2ND STAGE STM. SCRUBBER
66"φ × 14'-0" T-T

V-14
2ND STAGE BRINE FLASH DRUM
78"φ × 20'-0" T-T

E-1C
2ND STAGE EXCHANGER

V-12
2ND STAGE STM. SCRUBBER
66"φ × 14'-0" T-T

V-11
2ND STAGE BRINE FLASH DRUM
90"φ × 30'-0" T-T

E-5
CONDENSATE COOLER

V-13
CONDENSATE TANK
42"φ × 12'-0" T-T

V-15
ATMOSPHERIC FLASH DRUM
84"φ × 28'-0" HIGH

E-4A & B
CONDENSERS

V-2
CONDENSATE ACCUMULATOR
114"φ × 30'-0" T-T

REFERENCE DRAWING	
DRAWING NO.	TITLE

	1 & 2	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
FLUID	TOTAL BRINE	BRINE	BRINE	STEAM	STEAM	BRINE	STEAM	STEAM	STEAM	STEAM	STEAM	BRINE	BRINE	STEAM	WATER	WATER	WATER	WATER	WATER	STEAM
M LBS/HR.	800	400	400	51.6	103.2	348.4	35.9	35.9	35.9	103.2	103.2	312.5	618	71.8	800	800	800	800	800	7.1
GPM	1266	633	633	51.6	103.2	633	35.9	35.9	35.9	206	206	565	1117	144	1600	1600	1600	1600	1445	7.1
STEAM M LBS/HR.	103.2	51.6	51.6	51.6	103.2	35.9	35.9	35.9	35.9	103.2	103.2	312.5	618	71.8	800	800	800	800	800	7.1
°F	363	363	363	363	363	363	232	212	212	340	110	242	228	212	90	121	165	206	228	228
PSIA	130	130	130	130	130	130	21	20	ATMOS.	125	115	20	ATMOS.	150					20	ATMOS.
MM BTU/HR.	3098	154.9	154.9	61.5	123.0	93.4	41.5	6.5	6.5	32.2	8.0	52.6	97.0	12.9	46.4	70.6	105.6	140.7	231.5	8.2

MARK	REVISION	DR.	CH	DATE
A	ISSUED FOR CUSTOMER APPROVAL	J.P.	FT	3-22-78
B	REDRAWN & ISSUED FOR APPROVAL	J.P.	FT	5-26-78
C	REVISED & REQUESTED FOR APPROVAL	J.P.	FT	5-26-78
D	ADDED CONDENSATE FLOW RATES AND PUMP, REVISED V-15 DIAMETER	RC	FT	7-15-78
E	REVISED STREAM DATA AS INDICATED	RC		

THE BEN HOLT CO.

TITLE: **GLEF TWO STAGE FLASH BINARY PROCESS FLOW DIAGRAM**

CUSTOMER: **SAN DIEGO GAS & ELECTRIC CO.**

DRAWN BY: **JOE POPE** SCALE: **CH** DRAWING NO.: **7429-09-D-3201** REV. **E**

APPROVED: *[Signature]* DATE: **3-22-78**

**GLEF TWO STAGE FLASH BINARY PROCESS FLOW DIAGRAM
FIGURE 0-2**

QUARTERLY REPORT

INTRODUCTION

This Quarterly Report covers the period from January 1, 1979 through March 31, 1979. Included are the general operations and accomplishments for this period.

The Plant Operations Section gives a chronological operating history of the plant during this quarter, and discusses plant availability, shutdowns, and start-ups. Reservoir assessment activities and the operation of production and injection wells are discussed in the Reservoir Operations Section. Results of tests that were accomplished are contained in the Testing Section. Laboratory data obtained for steam, brine, binary and cooling water, scale and future projects are given in the Systems Chemistry Section. Any equipment that required repairs or modifications are discussed in the Maintenance Section. The GLEF Clarifier/Filter Installation is discussed in Section 6.0. The "Other Activities" section discusses the status of the feasibility and surge studies, work on the direct contact heat exchanger, noncondensable gas content of the brine, and pilot clarifier testing.

1.0 PLANT OPERATION

W. S. Bischoff/R. J. Peirce

The plant operated for a total of 932 hours in this quarter giving a total of 10,814 hours since start-up. The plant availability based on total hours for the quarter was 43.1%. The availability since start-up was 42.5% based on total hours. Table 1-1 lists the monthly breakdown during 1979 and Figure 1-1 presents the availability since 1977. The reasons for this Quarter's outages are listed in Table 1-2.

This Quarter's unplanned outages account for 39% of all outages. Principle cause of unplanned outages continues to be the injection pump. On January 1, 1979, the GLEF was on stream at reduced flow due to limited capacity of the injection pump (P-2). The pump started to plug due to scale build-up. Flushing of the suction line or pump can did not rectify the situation. This was not unexpected (operation limited to 1000 hrs. prior to a major cleaning) and the GLEF was shutdown on January 2, 1979 for planned plant cleaning and overhaul (refer to Section 5.0, Maintenance for activities during shutdown). This completed a total of 1,103 hours of noncontinuous operation using the primary production well, Magmamax No. 1, since the October 10, 1978 plant overhaul (refer to 4th Quarter 1978). During the shutdown Magmamax No. 1 production line and flash trains were isolated from the Woolsey #1 train (2nd production well) by using

	FOR MONTH			SINCE START-UP		
	TOTAL GLEF OPERATING HOURS	TOTAL HOURS IN THE MONTH	% AVAILABILITY BASED ON TOTAL HOURS	CUMULATIVE TOTAL GLEF OPERATING HOURS	CUMULATIVE TOTAL MONTH HOURS	% AVAILABILITY BASED ON TOTAL MONTH HOURS
JANUARY	336	744	45.2	2799 ₁ 10218 ₂	5160 ₁ 24056 ₂	54.2 ₁ 42.5 ₂
FEBRUARY	379	672	56.4	3178 ₁ 10597 ₂	5832 ₁ 24728 ₂	54.5 ₁ 42.9 ₂
MARCH	217	744	29.2	3395 ₁ 10814 ₂	6576 ₁ 25472 ₂	51.6 ₁ 42.5 ₂
APRIL						
MAY						
JUNE						
JULY						
AUGUST						
SEPTEMBER						
OCTOBER						
NOVEMBER						
DECEMBER						

1. Since 2 Stage Modification
2. Since Plant Start-Up May 1976

1st OPERATION
MAY 3, 1976
@ 8:00

- AVAILABILITY = NO. OF HOURS OF PLANT OPERATION/TOTAL NO. OF HOURS IN THE MONTH.
- PLANT SHUTDOWN FOR MAJOR OVERHAUL.

NILAND GEOTHERMAL LOOP EXPERIMENTAL FACILITY
1977, 1978 & 1979 AVAILABILITY BY MONTHS
FIGURE 1-1

OUTAGES

<u>NUMBER</u>	<u>DATE</u>	<u>PLANNED OR UNPLANNED</u>	<u>CAUSE OF SHUTDOWN</u>	<u>OUTAGE TIME</u>	<u>CORRECTIVE ACTION TAKEN</u>
1	1-02-79	Planned	Routine Maintenance	392 Hrs.	
2	1-26-79	Unplanned	Hole in 1st stage brine inlet control valve (PCV-300)	5 Hrs.	Repaired Steam Leak
3	1-31-79	Unplanned	1st P-2 Failure	143 Hrs.	Replaced Broken Shaft
4	2-08-79	Unplanned	P-2 Seal Repair	5 Hrs.	Seal Replaced
5	2-09-79	Unplanned	2nd P-2 Failure	156 Hrs.	Replaced Broken Shaft
6	3-05-79	Planned	Partial Cleaning	54 Hrs.	
7	3-07-79	Unplanned	3rd P-2 Failure	170 Hrs.	Installed Spare Pump
8	3-19-79	Planned	Clarifier Interface/ Overhaul	303 Hrs.	
TOTAL				1228 Hrs.	

-6c-

TABLE 1-2

pancakes (blank flanges) at points of commonality. This was done in preparation for operation on Woolsey No. 1. Isolation allowed maintenance and operation to be accomplished concurrently.

On January 18, 1979 the plant was started up using Woolsey No. 1 as the production well. Baseline operation could not be met because of low wellhead pressure. This well had been reworked by Imperial Magma by adding a section of smaller diameter production casing to seal a leak in the original casing and a corrosion tubing string was inserted down into the well for testing corrosion rates. This tubing reduces the cross-sectional area of the well bore and may contribute to the less than design flow rates found. Flow rates were reduced to approximately 500 gpm in order to maintain design first stage flash pressures of 130 psia. Typical operating conditions during this period are shown in Table 1-3. Parts of the B Train were concurrently installed, including a spool piece on the second stage brine outlet, control valve, and a test spool on the supply line.

The plant was secured for five hours on January 26, 1979, to repair a leak in the A train at the first stage separator inlet elbow. This leak was caused by the high velocity flow impingement at this location which eroded the pipe wall. A fiberglass test spool was concurrently installed in the condensate supply line to the spray pond for Test No. 4.0 Corrosion/Erosion.

TYPICAL OPERATING CONDITIONS, 1/18/79 through 3/19/79

USING WOOLSEY #1 PRODUCTION WELL

<u>Location</u>	<u>Temperature °F</u>	<u>Pressure Psig</u>	<u>Flowrate</u>
Wellhead	NA	174	NA
Plant Boundary	366	151	NA
First Stage Flash - Brine Drain	338	117	-- ¹
First Stage Steam	347	113	22 lbs/h.
Second Stage Flash - Brine Drain	235	9	NA
Second Stage Steam	214	7	-- ¹
Atmospheric Flash - Brine	NA	NA	NA
Injection Line - Plant Boundary	217	NA	467 GPM
Injection Wellhead	NA	106	NA

¹ Instrument Not Functioning

-7a-

TABLE 1-3

Pigging of the injection line was being accomplished on a daily basis. On January 31, 1979, a pig was launched in the injection line. The injection pump (P-2) discharge pressure was about 500 psi. Within minutes the high level alarm on V-15 sounded, and it was discovered that P-2 had lost all discharge pressure. It was then determined that the shaft was broken. (Refer to Section 5.6 Injection Pump P-2). Temperature and pressure were maintained on the Woolsey No. 1 well by periodically blowing brine into the brine holding pond.

The repaired P-2 pump was received from the SDG&E Machine Shop and installed. The facility was put on stream on February 6, 1979, using Woolsey No. 1 production well in the "A" flash train. A pig was launched into the injection line soon after coming on line and was recovered in good shape. The failure of the injection pump P-2 does not appear to be directly caused by the previous pigging operation. However, the operation does induce pressure transients, which may have precipitated a failure of a pre-existing weakened condition. Leakage at the injection pump base caused a plant shutdown and the old gasket material was replaced by a string of Teflon packing and restarted. The shaft seal on P-2 was also leaking and on February 8, 1979, the plant was secured to replace the mechanical seal.

On February 9, 1979, the discharge pressure on P-2 injection pump was lost and motor current dropped to 20 amps. The pump shaft broke for a second time. Section 5.6, Injection Pump P-2, provides further details.

Injection pump was repaired by the SDG&E machine shop and installed on site. The plant was started on February 15, 1979 using the "A" train, with no significant problems. On the following day difficulties with daily pigging were observed. Four foam filled pigs, two wire "Power Brush" pigs and two "Polly Pigs" with carborandum straps were launched at ten minute intervals to try to clear the suspected partial obstruction. All were damaged beyond further use. An all metal articulated pig, except for the pressure cups, manufactured by T. D. Williamson was launched two times in a further attempt to clear the line. Although the line was cleared, the articulated pig was badly damaged. Subsequent operation indicated that the power brush pigs worked better and lasted longer than the Polly pigs, probably due to tougher construction.

During this run several measures were taken to reduce the scale build-up:

- . The P-2 injection pump can and suction lines were flushed once per shift with utility water.
- . Southwest Chemical periodically hydroblasted the P-2 first stage inlet by way of installed nozzles.
- . Control valves were cycled to prevent sticking caused by scale build-up.

The following are other items of interest during this run:

- . A test of H_2S removal using the pilot clarifier was accomplished.
- . Some control tubing was rerouted due to the clarifier installation.
- . The B train second stage steam flow indication was connected to the Data Acquisition System to allow permanent recording of the flows.
- . The atmospheric flash vessel (V-15) sight glass and level column became plugged and had to be rodded out.
- . The atmospheric flash vessel level control valve, located on the discharge of P-2 (718A), started sticking, causing discharge pressure to swing from 10 to 560 pounds. Manual control was instituted to reduce variation.

The plant was shutdown for a scheduled partial cleaning on March 5, 1979. The purpose of the partial cleaning was to obtain baseline conditions to test a scale inhibitor in the plant. Areas of heavy scaling were selected to evaluate the inhibitor. During the shutdown, a review of the H_2S data from the pilot clarifier indicated that a retest was required. The delay caused by the pump failure and need to retest the H_2S removal capability of the pilot clarifier lead to a decision to cancel the scale inhibitor testing. Woolsey No. 1 was periodically flowed to the brine

pond to maintain temperature and pressure. The P-2 injection pump was removed for exterior cleaning and the discharge and suction piping were also cleaned. The atmospheric flash vessel (V-15) was open and cleaned. Roto Rooter cleaned the pilot clarifier feed and overflow lines.

On March 7, 1979, the P-2 injection pump was set in place after the partial cleaning was finished. Plant warm-up was started in preparation for coming on stream but had to be halted due to the P-2 pump failure. The plant was down 170 hours while awaiting delivery of a spare pump (Refer to Section 5.6). The spare P-2 pump was received and installed on March 14, 1979, after being reassembled. Reduced flow baseline conditions were met on this date using Woolsey No. 1 production well on the A train.

On March 19, 1979, the plant was shutdown for plant modifications, clarifier/filter interfacing and plant cleaning.

2.0 RESERVOIR OPERATION

D. K. Mulliner

2.1 Production Wells

Woolsey No. 1 was used during the period for the production well. The pressure and temperature at the plant boundary ranged from 150 to 155 psig, 368°-370°F respectively. The flow averaged 500 GPM. The lower than expected flow could be partially due to the 6 5/8" production casing size, and to the restriction caused by hanging a 2" corrosion test casing string in the flowing well.

Magmamax #1

An analysis of a recent Caliper Log indicated corrosion from 900 feet down. Chemical analysis of the brine showed sulfates in larger amounts than would be expected from the Magmamax No. 1 formation. Therefore, a radioactive Spinner survey was conducted by Geotex to determine the condition of the well casing. The Logs indicate that there are no holes in the casing and all produced fluid is flowing through the slotted liner.

2.2 Injection Wells

Brine from the GLEF was injected directly into Magmamax No. 3 at a temperature of 200 - 210°F until February 1977. The injection pressure increased an average

of 1.7 psi per million gallons during this period. In February, 1977, settling tanks were installed to allow the suspended solids to settle out of the brine before it was injected. The residence time in the settling tanks was about 2-3 hours. With injection of the cleaner fluid the average injection pressure increased 0.26 psi per million gallons. As the injection pressure increased to the maximum of the pumps output, it was necessary to transfer the injection fluid to another well, Magmamax No. 2. The injection pressure during this quarter increased from 150-180 psig.

It was decided to drill a new injection well, IW-5, into a shallow zone below the caprock. The injection fluid would be the brine from the new clarifier and mixed media filter. This fluid will test the shallow injection formation and the injectivity of the clarified brine.

The new injection well (IW-5) was drilled to 1500 feet. The slotted liner extends from 1100 to 1500 feet. The well was flow tested to determine the chemical composition of the brine prior to using the well for injection (Refer to Table 2-1). A temperature log was run. The temperature gradient is typical of this area.

CHEMICAL COMPOSITION
INJECTION WELL IW-5

pH - 6.46 (dimensionless)

Density - 1.1030 (s/ml)

Conductivity - 247500 (uho/cm)

SO₄ - 181

NH₄-N - 201

Boron - 207

TDS - 170570

TSS - 460

Cl - 89800

HCO₃ - 152

CO₃ - 0

Total Alkalinity as CaCO₃ - 125

Al - 1.3

Mg - 367

Ba - 89

Mn - 335

Ca - 15600

Ni - 2.6

Cr - 0.44

K - 5750

Co - 2.50

*Si - 87

Cu - 0.37

Ag - 0.40

Fe - 113

Na - 32100

Pb - 7.0

Sr - 306

Li - 120

Sn - 32.7

Zn - 109

*Si - Analysis low probably due to sampling and analytical procedures.

Note #1 - The well was flowed at approximately 100 GPM, therefore, the analysis may not be indicative of full well flow conditions.

Note #2 - All values are in PPM unless otherwise indicated.

3.0 TESTING

3.1 1976-1977 GLEF Test Program

The original program of tests to be performed at the GLEF primarily addressed the performance of the major plant components associated with the binary cycle such as heat exchangers, steam scrubbers, and etc. However, Phase I of the Feasibility study (Refer to Quarterly Report, April 1978) has redefined the critical areas to be tested. A report of the results of the original program is being prepared by Bechtel National, Incorporated.

3.2 1978-1979 GLEF Test Program

A feasibility study completed by SDG&E, Bechtel National, Incorporated and The Ben Holt Company in late 1977 and early 1978 showed that a direct flash cycle power plant would be the best choice for the first geothermal power plant at the Niland reservoir. Critical areas of risk were identified. As a result, the GLEF was modified to simulate the critical areas of a two stage flash cycle.

The primary objective of the 1978-1979 GLEF Test Program is to reduce significant risks and costs of constructing and operating a dual flash-cycle power plant at Niland. This test program consists of several different tests that will be performed separately by SDG&E, Lawrence Livermore Laboratory and Imperial Magma under the overall

direction of SDG&E. The test program consists of fourteen tests numbered from 1.0 to 15.0 (test 14.0 has been deleted). The statement of objective and end of quarter status of each test is given below.

TEST NO. 1.0

D. G. Newell

Title: SCALE REMOVAL
Responsible Organization: SDG&E
Priority: 1

OBJECTIVES

The objective of this test is to quantitatively evaluate the cost effectiveness of various techniques (in terms of cost of power), for removing scale from brine piping and flash vessels so that the best may be selected for use in the proposed 50 MWe power plant at the reservoir. These techniques are:

1. Piping (on-line);
2. high-velocity water flush (on-line);
3. cavitation/hydroblast (on-line and off-line);
4. acidizing/hydroblast (off-line).

TEST DESCRIPTION

The cost effectiveness will be evaluated by establishing the cost per Kwhr of each technique (including capital and operating expenses and plant down-time required) for a nominal 50 MWe power plant. A qualitative judgment will also be made of the suitability of each technique for use in an operating power plant. (e.g. The ability of the method to clean effectively around elbows, through valves, etc., will be assessed.)

The type and amount of scale formed in the plant varies greatly throughout the plant, depending on the brine conditions. Each of the above techniques will be evaluated in some or all of the following locations in the GLEF:

1. Production line piping;
2. 1st to 2nd stage piping;
3. 2nd stage to atmospheric flash drum piping;
4. injection line piping;
5. flash vessels (cavitation/hydroblast only).

TEST STATUS

This test has not been formally initiated, but a substantial amount of data has been gathered. A shortage of manpower has limited the documentation, analysis and evaluation of the data. A summary of activities and results is given in Table 3-1. Section 5 provides more detail of the maintenance operation involved. A detailed evaluation is planned as time and manpower permits.

TABLE 3-1: SCALE REMOVAL/CONTROL ACTIVITIES 1/1/79 Through 3/31/79

<u>Location</u>	<u>On Or Off Line</u>	<u>Outage Number</u>	<u>Activity¹</u>	<u>Approx. Scale Thickness Inches</u>	<u>Results</u>	<u>Preliminary Conclusion</u>
Production line piping	—	8	None accomplished	1/16 - 1/8	—	—
First Stage Flash Vessel	Off	1	Hydroblast and shoveling	See Fig. 5-1	Successful	—
1st to 2nd Stage Piping	Off	1	Hydroblast	1/5 - 9/16	Successful	—
	On ²	-	Hydroblast (Daedalean Associates)	.065	Successful ²	Application probably limited
Second Stage Flash Vessel	Off	1	Hydroblast and shoveling	See Fig. 5-2	Successful	—
2nd to ATM. Flash Piping	Off	1	Hydroblast	1/2 - 2	Successful	—
ATM. Flash Vessel	Off	1	Hydroblast and shoveling		Successful	—
Injection Line Piping	Off	1	Routing (Roto Rooter) of Pump Discharge Section		Unsuccessful	Equipment not Sufficient study
	On	-	Pigging		Successful ³	—
Injection Pump	On	-	Flushing and Hydroblast		Unsuccessful	More frequent or more effective hydroblasting required.
Valves	Off	1	Removed, acid, soaked and flushed or Hydroblasted		Successful	Acid soak is a good technique where access is limited.

1 See Table 1-2 for outage description

2 Final cleaning of test section was off line

3 Some damage to pigs noted

TABLE 3-1: SCALE REMOVAL/CONTROL ACTIVITIES 1/1/79 Through 3/31/79 (Continued)

<u>Location</u>	<u>On Or Off Line</u>	<u>Outage Number</u>	<u>Activity</u>	<u>Approx. Scale Thickness Inches</u>	<u>Results</u>	<u>Remarks</u>
1st Stage Drain Test Section Values	On	—	Hydroblasting		Successful ⁴	Improved Nozzle Location & Coverage Required
Injection Line Section	Off	3	Hydroblasting		Successful	—
Atmospheric Flash Vessel	Off	3	Hydroblast and Shoveling		Successful	—
Block Valves	Off	3	Hydroblast		Successful	New Types Will Be Tried
Ball Control Valves	On Off	8	Cycling Acid Soak and Flush		Unsuccessful Successful	— —
Side Stream Pilot Clarifier Feed Lines	Off	6	Routing (Roto Rooter)		Successful	Applicable to Small Dia. Piping
Injection Lines and Pump	Off	6	Hydroblasting	1/2 - 2 7/8	Successful	—
Thermowell in 1st Stage Drain	On	—	Hydroblasting	1/16	Successful ⁵	Complete Scale Removal Not Required
1st Stage Scrubber	Off	1 & 8	Partial Scraping and Routing	Rust and Debris	Successful	—
2nd Stage Scrubber	Off	1 & 8	Scraping & Routing	0-2	Successful	—
Pinch Valves	On		Flexing of Diaphragm	—	Successful ⁶	Limited Life May Restrict Application
Inlet Control Valve	Off	8	Acid Soak and Flush	3/16	Successful	—
Atmos. Flash Drain	On	—	Hydroblast	—	Not Attempted	—
	Off	—	Hydroblast	2 1/2	Successful	—

4. Valves operated but some scale remained on sealing surfaces

5. Indicated correct temperature, but some scale remained

6. Valves functioned, but some scale remained

TEST NO. 2.0

R. Quong

Title: SCALE PROPERTIES
Responsible Organization: LLL
Priority: 1

OBJECTIVES

The objective of this test is to develop the ability to predict the amount of scale that forms in various sections of the plant and to predict the properties of that scale which affect the effort required to remove it. This information will be used to help size piping, vessels, etc., and to design a descaling system for the 50 MWe power plant proposed for the Niland reservoir.

TEST DESCRIPTION

Scaling rates will be determined at the approximate conditions present in each of the following area:

1. Production line piping;
2. 1st and 2nd stage piping
3. 2nd stage to atmospheric flash drum piping;
4. Atmospheric receiver drain line;
5. injection line piping.

Scale samples from each of these areas will be analyzed for chemical and mineralogical properties, as well as for mechanical properties such as hardness, adherence to wall etc. The effect of temperature, Reynolds Number, etc., on the scaling rate and the scale properties will also be investigated.

Various chemical solvents will be evaluated as a means of enhancing scale removal with possible on-line application.

TEST STATUS

Tests have been completed on effect of 8 candidate solvents on scale from 7 locations at the GLEF. Samples were collected in September-October, 1978, following Magma-max No. 1 operation. Contact times of 1 hr. at 23°C (73.4°F) and 80°C (176°F), and 24 hr. at 23°C (73.4°) were investigated. The solubility of the scales in the various solutions have been determined.

X-ray diffraction analysis of the Magmamax No. 1 scales have been completed. Mechanical properties were not measurable because of poor sample condition. Attempts will be made at the next opportunity at the GLEF. Instrument problems and backlog has delayed completion of x-ray fluorescence analysis of scale and scale liquor filtrates. Scale samples have been collected from 5 locations at the GLEF following Woolsey No. 1 operation for analysis and dissolution studies.

TEST NO. 3.0

R. Quong

Title: SCALE CONTROL ADDITIVES
Responsible Organization: LLL
Priority: 1

OBJECTIVES

The objective of this test is to determine the possibility of retarding or eliminating scale formation in a two-stage flash system through the addition of scale inhibiting chemicals or sludge particles to the brine. If these techniques are shown to have a beneficial effect, the cost per unit mass of brine treated will be estimated. This technique, if successful, may greatly reduce the cost of power from the 50 MWe power plant proposed for the reservoir.

TEST DESCRIPTION

After laboratory screening tests, the most promising additives will be tested at LLL's side stream facility, simulating power plant conditions. The consequences of successful scale inhibition on corrosion and erosion of plant components, effluent treatment, injection well lifetime, etc., will be addressed qualitatively through observations and analysis of the treated brine.

TEST STATUS

Eight proprietary additives (described in the 4th Quarterly Report, 1978) were tested (additives added to separated brine at 210°C, 410°F) for periods between 64 and 69 hours in the LLL dual train 2 stage system. A control test in each train was also carried out to establish baseline scaling rates. Effect of additives on rate of silica precipitation and solids formation has been determined. Based on pipe spool scaling, Southwest Specialty Chemicals SC-210 appeared to be the best of those tested. A factor of 4 reduction in pipe spool scaling rate at 125°C (257°F) was found. Chemical analysis of deposited scale is continuing. A 23-hour seeding test was completed. Sludge (20% by weight solids) was obtained from Magma and injected into high temperature brine in the LLL test system. Rate of injection corresponded to addition of .43% by weight solids or 4300 ppm to the brine. A greater amount of solids accumulation was found on coupons and pipe spools relative to controls. However, dissolved silica was reduced by the seeding. Preliminary results on additives has been reported (Lawrence Livermore Laboratory: UCID-18051, dated 2/1/79).

A 3-day scaling test of the Austral/Erwin process was completed. Chemical analysis of the scales and examination of the pipe spools are continuing, but it appears that 40 ppm of the oil-based additive had no beneficial effect on the low temperature scales ($<150^{\circ}\text{C}$, 302°F). There may have been a minor reduction of the 200°C , (392°F) scales.

TEST NO. 4.0

J. P. Kozic

Title: Corrosion/Erosion
Responsible Organization: SDG&E
Priority: 1

OBJECTIVES

The objective of this test is to measure the rates and types of corrosion/erosion of various materials of construction exposed to the brine and steam conditions that will be experienced in a 50 MWe power plant. This information will be used to determine the cost effectiveness of these materials of construction for a 50 MWe power plant with a 30 year design life. Metals, metal cladding, and corrosion-resistant coatings will be tested in the following environments:

1. Production line piping;
2. 1st stage flash vessel (liquid, vapor, and liquid/vapor interface regions);
3. 1st to 2nd stage piping;
4. 2nd stage flash vessel (liquid, vapor, and liquid/vapor interface regions);
5. Injection line piping;
6. Combined steam condensate.

Test Description

The test will consist of coupon exposure tests to vessels and observation of short pipe spools in the brine piping of the selected materials for qualitative information on the type and amount of corrosion/erosion experienced.

TEST STATUS

Test spools have been installed in order to examine corrosion/erosion. Refer to 4th Quarterly Report, 1978, for locations and materials tested. The following test spools will be installed during the clarifier/injection well test scheduled for May, 1979.

Injection Line (To IW-5)

Polymeric Concrete - Two formulations
Carbon Steel 1018
Miscellaneous metallic samples to be determined

To prevent electrolytic action, each pipe spool was isolated from adjacent pieces by insulating gaskets of Viton A fluorocarbon elastomer. All bolts passing through the flanges were insulated by Teflon FEP sleeves and washers.

Ultrasonic thickness measurements will be made to determine corrosion rates on pipe spools. Due to early problems with the operational reliability of the ultrasonic thickness meter, readings taken prior to January 1979 are suspect. The following are the corrosion rates for the Woolsey production line based on incomplete data:

<u>Material</u>	<u>Corrosion Rate (mils per year)</u> *
Hastelloy C-276	3.9
Inconel 625	3.9
Incoloy 825	9.7
Carbon Steel 1018	42.6

*80% on line factor = 7008 hours/year

More complete data will be collected during the run which will begin May 1979.

In addition to the pipe test spools, test coupons have been installed in the B train (refer to Table 3-2 and Figures 3-1 and 3-2). The sample from General Atomic consists of eighteen 1" x 3" coupons of various materials and coatings. These are detailed in Table 3-3. Prior to installation, each coupon was weighed to 0.1 gram and the thickness was determined to 0.0005 inches at 16 locations. Photographs were taken prior to installation and again as installed. It is anticipated that photos will also be taken at each shutdown to document scaling and corrosion tendencies.

COUPONS - TEST NO. 4.0

<u>1st Stage (V-4)</u>	<u>B Train</u>	<u>2nd Stage (V-11)</u>
Hastelloy C-276		Inconel 625
Hastelloy G		Indusco Ceramic
29 Cr/4 Mo		Carbon Steel
Ti-CP50		Epoxy Coated Carbon Steel
Carpenter 20 CB 3		Fluorocoat 1302 Carbon Steel
Inconel 625		
Incoloy 825		
Carbon Steel 1018/1020		
Indusco Ceramic		
Polyurethane		
Epoxy Coated Carbon Steel		
Fluorocoat 1302 On Carbon Steel		
General Atomic Panel

NOTES: 1. PANELS (1 THRU 8) ARE ~3" W $\times$ 12" L
 2. NUMBERS ON PANELS TO FACE BRINE & UP
 3. 1' INTERVAL BETWEEN PANELS

COUPONS - TEST NO. 4.0 B TRAIN 1ST STAGE (V-4)
 FIGURE 3-1

COUPONS - TEST NO. 4.0 B TRAIN 2ND STAGE (V-11)
FIGURE 3-2

SPECIMEN CODE #	MATERIAL (4) (5)	LOCATION ON FIXTURE (1)	STARTING SPECIMEN THICKNESSES (2) INCH		STARTING WEIGHT GM
			End		
			Numbered	Unnumbered	
14	Niobium Carbide coating over EVD (3) Niobium Coating.	1F	0.1168	0.1177	43.8307
16	Niobium carbide coating. Plasma spraying process.	2F	0.1282	0.1327	46.0934
10	Niobium coating. EVD Nb over thin layer of ion-plated Nb.	3F	0.1161	0.1164	44.4326
51	Niobium sheet (control specimen).	4F	0.1228	0.1234	42.9950
32	AISI 1018 Carbon steel (control specimen).	6F	0.1099	0.1095	41.9360
58	Nickel coating containing dispersion of fine SiC particles.	5F	0.1178	0.1176	45.0834
5	Niobium carbide coating over EVD Niobium coating.	7F	0.1112	0.1112	42.1050
29	Niobium carbide coating Plasma spraying process.	8F	0.1280	0.1246	45.4223
11	Niobium coating. EVD Nb over thin layer of ion-plated Nb.	9F	0.1125	0.1137	42.5253

(1) Locations 1F - 9F attached to Front Face and 10B - 18B are attached to Back Face.

(2) At 3/4" in from specimen ends on centerline. Overall dimensions are typically 1" X 3" X 1/8" thick.

(3) Physical vapor deposition of Nb.

(4) All coatings are on a substrate of AISI 1018 carbon steel.

(5) Coating thickness per side range from 0.001 - 0.003 inches except 16 which is 0.008 inch typically.

**GENERAL ATOMIC COUPONS - TEST MATERIALS AND DETAILS OF
SPECIMEN CONFIGURATION AND TEST LOCATION
TABLE 3-3**

SPECIMEN CODE #	MATERIAL (4) (5)	LOCATION ON FIXTURE (1)	STARTING SPECIMEN THICKNESSES (2) INCH		STARTING WEIGHT GM
			End		
			Numbered	Unnumbered	
55	Kynar 450 – polyvinylidene fluoride.	10B	0.1252	0.1248	5.2142
56	PFA Teflon – perfluoroalkoxy.	11B	0.1371	0.1363	9.5556
54	Ryton – PPS – 4 polyphenylene sulfide.	12B	0.1173	0.1181	9.2285
42	AISI 1018 Carbon steel (control specimen).	13B	0.1095	0.1096	41.7095
53	Radel R-5000 polyphenylsulfone.	14B	0.1204	0.1205	7.5062
57	Nickel coating containing dispersion of fine SiC particles.	15B	0.1188	0.1186	44.2811
23	Niobium carbide coating.	16B	0.1110	0.1112	41.9706
7	Niobium carbide coating over EVD Niobium coating.	17B	0.1158	0.1156	44.0224
20	Niobium coating. EVD Niobium over thin layer of ion-plated Niobium.	18B	0.1145	0.1145	43.5589

(1) Locations 1F – 9F attached to Front Face and 10B – 18B are attached to Back Face.

(2) At 3/4" in from specimen ends on centerline. Overall dimensions are typically 1" X 3" X 1/8" thick.

(3) Physical vapor deposition of Nb.

(4) All coatings are on a substrate of AISI 1018 carbon steel.

(5) Coating thickness per side range from 0.001 – 0.003 inches except 16 which is 0.008 inch typically.

**GENERAL ATOMIC COUPONS – TEST MATERIALS AND DETAILS OF
SPECIMEN CONFIGURATION AND TEST LOCATION
TABLE 3-3 CONT.**

TEST NO. 5.0

R. Quong

Title: CORROSION/EROSION PARAMETERIZATION
Responsible Organization: LLL
Priority: 2

OBJECTIVES

The objective of this test is to determine the expected lifetime of carbon steel and other alternate materials of construction in brine, steam and condensate as a function of pH, temperature, oxygen content and any other parameters that may vary within the reservoir or over the life of the wells.

TEST DESCRIPTION

This test will be primarily a paper study, utilizing existing data from the Bureau of Mines (as it becomes available) and LLL's data on corrosion rates on modified brine (low pH). The effects of standby oxygen corrosion during plant shutdown will also be evaluated in a test designed to simulate shutdown conditions.

TEST STATUS

The corrosion penetration rate and attack morphology of some 30 commercial metals and alloys in the completed 30 day test have been determined and reported in the Lawrence Livermore Laboratory report: ATHS/ISP-17, September 1978. Analysis of stress corrosion and weldment coupons is also complete. Report is in preparation.

Evaluation of coupons exposed in a Magmamax No. 1 downwell test during February, 1978 has been completed. Large differences in corrosion behavior, attributable to composition and microstructure differences were found. Severely corroded sections from a J55 string exposed in February, 1978 are currently being evaluated. Preliminary results were reported in the Lawrence Livermore Laboratory quarterly progress report, UCID-18074-79-1.

TEST NO. 6.0

W. S. Bischoff

Title: PLANT COMPONENTS AND INSTRUMENTATION
Responsible Organization: SDG&E
Priority: 1

OBJECTIVES

The objective of this test is to monitor the performance (operating life, failure history, etc.,) of plant components exposed to the brine and geothermal steam. This includes various types of control valves, line block valves, pumps, thermocouples, flow meters, etc.

TEST DESCRIPTION

The failure history of these components will be monitored using a "Failure Mode Analysis" program. The effectiveness of various types of equipment operating in the different brine and steam environments will be recorded and analyzed. Engineered changes will be implemented and their effects monitored to improve component performance and lifetime. This data will be used as a basis for selecting components and instrumentation for the 50 MWe flash cycle power plant to be built at the Niland reservoir.

Certain components that are required for safe operation of the plant and will also be evaluated for reliable performance. Relief valves, wellheads, shutoff valves, etc. are among the components to be so evaluated.

TEST STATUS

A substantial amount of operating history has been obtained for various plant components. This data is in the process of being evaluated adapted to meet the objectives of this test. Table 3-4 summarizes the significant operational history of components during this period.

PLANT COMPONENTS AND INSTRUMENTATION

<u>COMPONENT</u>	<u>PLANNED OR UNPLANNED MAINTENANCE</u>	<u>PROBLEMS</u>	<u>CORRECTIVE ACTIONS</u>
Injection Pump	Planned & Unplanned	Scale, excessive bearing wearing, shaft failure	Improved purge water and pump will be placed downstream of clarifier/filter.
Level Column Atmospheric flash tank	Planned	Scale, plugging	Purge water connections added.
Second Stage Separator	Planned	Brine carry over in steam	Lowered liquid level and baffle plate installed to reduce sloshing.
Second Stage Heat Exchanger	Planned	Poor performance	Vent added to prevent accumulation of noncondensable gas.
Flash vessel inlet piping	Unplanned	Erosion & leakage at elbows	Long radius or large dia. elbows planned.
Pigs	Planned & unplanned	damage	Cleaned, suspected partial blockage.
Injection pump	Unplanned	gasket leakage, pump base	New packing installed.
Ball type control valves	Planned	scale, sticking	Cycling.
Steam flow (turbine) meters	Unplanned	Turbine failure	Replace with pitot tube meter.

TEST NO. 7.0

C. H. Haas

Title: BRINE CHEMISTRY
Responsible Organization: SDG&E
Priority: 1

OBJECTIVES

The objective of this test is to completely characterize the chemistry of the Niland brine.

TEST DESCRIPTION

Analyses will be performed on samples of liquid brine, steam, condensate, and non-condensable gases under varying well flow conditions and a correlation drawn between well flow, plant operations, and fluid composition.

TEST STATUS

Sampling of GLEF fluids during this quarter and results are described in Section 4.0 Systems Chemistry. In general no major changes in chemistry were detected.

TEST NO. 8.0

R. Quong

Title: H₂S ABATEMENT
Responsible Organization: LLL
Priority: 2

OBJECTIVES

The objective of this test is to evaluate the technical feasibility and costs of stripping H₂S from GLEF non-condensable vent gas stream with brine effluent. In addition, the impact on the reactor-clarifier of this H₂S addition to the brine effluent will be considered.

TEST DESCRIPTION

Laboratory scale apparatus will be used to define the feasibility of this method. Technical advantages, disadvantages and costs of this technique will be compared with the Stretford process.

TEST STATUS

The first continuous scrubbing test using a small scale single stage unit was completed. Results show up to 82% of H₂S is removed (volumetric ratio of gas flow to brine flow was 20.6). A preliminary report of results are included in the Lawrence Livermore Laboratory first quarterly report, UCID-18074-79-1.

Since the issuance of this report, additional field tests were conducted during Woolsey No. 1 operation at the GLEF. In a single contact stage and in a countercurrent flow mode, H₂S removal efficiencies of >99% were attained at gas/liquid ratios corresponding to 0.2% noncondensable gas content in the brine. At higher gas/liquid ratios corresponding to 0.5 and 1% gas content, efficiencies dropped to 98% and 96%, respectively. Significant reduction in pH was measured in the brine effluent as a result of sulfide reaction precipitation. The effect of pH on scrubbing efficiency will be evaluated. Above test results were with 25°C (77°F) brine. The next test phase will utilize effluent at GLEF temperatures.

TEST NO. 9.0

W. O. Jacobson

Title: STEAM SEPARATION
Responsible Organization: SDG&E
Priority: TBD

OBJECTIVES

The objective of this test has not been finalized. A broad objective is to determine the effect of impurities in the steam on turbine performance and reliability.

TEST STATUS

This test has not been authorized. Bechtel National, Inc., submitted a proposed scope which was not accepted due to funding constraints. Bechtel National is preparing a proposal which is reduced in scope. The test will define the performance of the existing GLEF, steam scrubbers, and possibly evaluate an alternate method of steam separation/ scrubbing.

TEST NO. 10.0

J. L. Featherstone

Title: INJECTION EFFLUENT PROCESSING
Responsible Organization: Magma
Priority: 1

OBJECTIVES

The objective of the GLEF brine injection processing facility is to demonstrate the viability of a complete treatment system and evaluate the effect on injection well performance.

TEST DESCRIPTION

Detailed instrumentation is being incorporated into the clarifier/filter design. Instrumentation will allow evaluation of precipitation and clarification, filtration, sludge handling and dewatering, and sludge disposal.

TEST STATUS

No work on this test was accomplished during this quarter. Beginning operation is planned for the second quarter of 1979.

TEST NO. 11.0

J. L. Featherstone

Title: MAKEUP WATER INJECTION COMPATIBILITY
Responsible Organization: Magma
Priority: 1

OBJECTIVES

The objective of this test is to establish the technical and economic feasibility of mixing Salton Sea water with geothermal brine in the Eimco pilot plant reactor clarifier.

TEST STATUS

This test was completed by Imperial Magma. The 4th Quarterly Report, 1978, includes a summary of the findings.

TEST NO. 12.0

R. Quong

Title: WELL-CASING MATERIALS
Responsible Organization: LLL
Priority: 1

OBJECTIVES

The objective of this test is to assess the rates of corrosion and the types of corrosion with different standard well casing materials and to establish the expected service life of well casing materials.

TEST DESCRIPTION

Several strings of selected, small diameter tubing will be suspended in production wells. Strings will be removed after exposure and performance evaluated.

TEST STATUS

The 1800-ft. test string consisting of API steels J55, N80 and C75 was removed from Woolsey No. 1 well on March 26 after 2-1/2 months exposure. Exposure time was 1 month less than planned in order to be compatible with GLEF operations schedule. Reduced exposure time is not expected to compromise technical data. Sections of the different materials have been selected for metallographic analysis.

TEST NO. 13.0

R. Quong

Title: INJECTION STUDIES

Responsible Organization: LLL

Priority: 1

OBJECTIVES

The objective is to evaluate the use of Salton Sea fluids as a source makeup water.

TEST DESCRIPTION

Testing will: 1) study the technical and economic feasibility of using Salton Sea water mixed with brine for injection; 2) to determine what additives are necessary to reduce the sulfate concentration; 3) to establish by computer modeling, the effect on the reservoir of injection of Salton Sea water; 4) to determine by core flushing, the injectivity of clarifier effluent from brine and Salton Sea brine mixtures.

TEST STATUS

Chemical stability tests of clarified processed effluents from Magma's pilot facility, evaluation of core and membrane filter test data, and low pH brine adjustment tests have been completed and reported (LLL Geothermal ISP 1st Quarter Technical Progress Report for 1979, UCID-18074-79-1). Additional evaluation tests are dependent on 10 MW sized clarifier startup.

Results of brine/makeup water (Salton Sea, New River, and Alamo River) incubation tests with and without sludge contact at 90°C (194°F) for periods ranging from 15 minutes to 30 days have also been reported in the Lawrence Livermore Laboratory 1st quarterly report, UCID-18074-79-1.

TEST NO. 15.0

J. P. Kozic, F. Schoepflin

Title: Scale Control-Inhibitors
Responsible Organization: SDG&E

OBJECTIVES

The objective of this test was to determine if commercially available chemicals could be used to inhibit the precipitation of silica from Niland brine. This has been the major source of scale formation at the GLEF. If successful, both technically and economically, such a treatment may result in substantial cost savings in the 50 MW plant proposed for Niland.

TEST DESCRIPTION

Based on preliminary rapid field screening tests, one inhibitor will be tested at the GLEF. Effects on plant and pilot clarifier will be evaluated. Rapid field screening and GLEF testing are intended to complement the more comprehensive but smaller scale, testing being accomplished by LLL in Test No. 3.

TEST STATUS

NUS Corporation has completed the rapid field screening tests indicated that a reduction in precipitation rates may be realized by the use of chemical inhibitors but none of the products showed outstanding results. One such product (Betz Polysperse) had been purchased for a trial run prior to the plant shut down of March 19, 1979, however, due to operational problems with the P-2 injection pump and the need to gather more data on stripping H_2S from the vent gas (see status - Test No. 8.0), the inhibitor test has been postponed indefinitely.

4.0 SYSTEM CHEMISTRY

C. H. Haas

Magmamax No. 1 was the supply well used the first two days of this quarter before the plant was shut down for cleaning. No brine samples were taken during this period. A complete brine analysis for Magmamax No. 1 may be found in the previous quarterly report (Oct-Dec 1978). Scale samples were taken during the cleaning period and the analysis are presented in the scale section of this report.

The plant started up again on January 18, 1979 using Woolsey No. 1 as the supply well. Many problems were encountered in the plant during this quarter which led to numerous premature shut-downs. The following table lists the dates of start-ups, shut-downs and the reasons for these shut-downs.

<u>Date Start-up</u>	<u>Date Shut-down</u>	<u>Reason For Shut-down</u>
	1-2-79	Plant Cleaning
1-18-79	1-31-79	P-2 Failure
2-6-79	2-9-79	P-2 Seal Leak
2-16-79	3-5-79	Plant Cleaning
3-15-79	3-19-79	Clarifier Hook-up

Each plant shut-down had an adverse effect on the scale by allowing oxygen to enter the system causing possible oxidation of the existing scale. The oxidation of the metals produces a much harder scale.

The following four subsections: steam, brine, binary and cooling water, and scale, describe the sampling of the GLEF fluids during this quarter. Not all constituents listed are monitored because an accurate test procedure has not to date been set up.

4.1 Steam

Appendix A lists the daily and weekly monitored constituents of the GLEF steam. The steam sampling points remained unchanged during this quarter, that is, the steam samples entering the first and second stage scrubbers were grab samples and the steam samples exiting the first and second stage scrubbers were taken at the heat exchangers. The flushing lines for the steam sampling lines were discontinued due to contamination of the samples caused by leaking valves in the flushing water system.

The steam's physical characteristics in the first stage are considerably different than those previously reported using Magmamax No. 1 as the reference well. The pH entering the first stage scrubber ranged from a basic pH of 8.30 to an acid pH of 6.56. This is probably due to a combination of brine carry-over and a high concentration of the bicarbonate ion (HCO_3^-). This is indicated by concentrations of 389 ppm (HCO_3^-), 19.0 ppm (Na^+) and 8.14 ppm (Ca^{++}) at pH 8.30 and 1016 ppm (HCO_3^-), 25.6 ppm (Na^+), and 14.8 ppm (Ca^{++}) at pH 6.77. High concentrations of sodium and calcium are indicative of brine carry-over. The pH of the steam

from the first stage heat exchanger ranged from 6.12 to 5.81. This is not a drastic change, and increases in hydrogen sulfide (H_2S) and bicarbonate could account for the change in pH. For example, the values were 4.5 ppm H_2S , 961 ppm HCO_3^- at pH 6.12 and 6.0 ppm H_2S , 1042 ppm HCO_3^- at pH 5.81. The data in Appendix A indicates the effectiveness of the first stage scrubber in removing the major ions from the steam.

The steam entering the second stage scrubber was extremely impure due to large amounts of brine carry-over. The pH of the steam remained fairly constant, between 8.5 and 9.5, however, the concentrations of chlorides, sodium, calcium and potassium fluctuated considerably throughout this period. These fluctuations were attributed to the brine carry-over. The steam exiting the second stage scrubber showed considerable variation in regards to pH, chlorides, sodium, calcium and potassium. The pH varied from an acidic pH of 5.88 to a basic pH of 9.05. The concentrations of chlorides, sodium, calcium and potassium were generally higher than the concentrations of these same elements in the steam entering the second stage scrubber. This final steam sample was actually taken from the condensed steam leaving the second stage heat exchangers. The increased mineral content of this sample was attributed to solids deposited in the scrubber/heat exchanger system which were subsequently entrained in the condensed steam sample.

The characteristics of the combined condensate were relatively stable. There was good correlation for the values between the first and second stage scrubbers and the combined condensate, namely, the mass balance of the chemical species in the combined condensate were approximately equal to the combined mass leaving the first and second stage steam scrubbers.

4.2 Brine

Appendix B lists the daily and weekly monitored constituents of the geothermal brine through the two stage flash system. During the first week of plant operation, the concentrations of the elements followed the expected trend, that is, the concentrations increased as the brine flowed through the plant. However, this trend diminished after the first week. The concentrations of the elements for the injection sample were equal to or less than those for the second stage separator sample. This decrease may have been due to a scale build-up around the sample port in the injection line. Careful sampling and analysis is expected to evaluate this potential during the next report period. Toward the latter part of plant operations, the measured values in the Woolsey sample were higher than those for the first stage separator sample. These higher values occurred when scale pieces plugged the cooling coil requiring the Woolsey sample

to be taken directly from the supply line rather than passing through the cooling coil. In this sampling mode, part of the steam is flashed to the atmosphere producing a sample with a higher mineral content.

The concentrations of the elements taken from the Woolsey No. 1 supply line varied considerably during this test period. This variation may have been caused by not using the well for a long period of time. During this interim, the well casing had to be reworked because of holes, so in effect, Woolsey might be considered a new well. The following table illustrates the elements measured on the Atomic Absorption Spectrophotometer with the highest, lowest, and average concentrations:

<u>Element</u>	<u>High</u>	<u>Low</u>	<u>Average</u>
Na	54600	29600	42700
Ca	28300	16700	22900
K	14100	58300	10200
Ba	195	79	142
Fe	320	152	236
Li	197	122	162
Mn	903	498	718
Mg	116	67	87
Sr	472	292	382
Zn	313	172	256
Si	236	152	204
Pb	68	24	49

All measurements are in ppm

4.3 Binary and Cooling Water

Appendix C lists the daily and weekly monitored constituents of the binary and cooling water systems. These systems have been in operation since November 12, 1978.

The binary was monitored primarily for pH, conductivity, density, chlorides, calcium, iron and sodium. All measurements remained fairly constant.

The cooling water system was stable with respect to all measurements. The pH remained between 7.50 and 8.00 and the concentrations of the elements rose slightly due to the addition of the combined condensate.

The cooling water condensers remained stable as well. The dP (differential pressure) across the condensers rose slightly from a dP of 11 psi at the initial start up to a dP of 15 psi at the termination of this test period. The Betz water treatment chemicals continued to keep the condensers clean and keep the corrosion rate less than 1 mil per year.

4.4 Scale

This section of the report will be listed in three major categories: Scale from Magmamax No. 1 Utilizing "B" Train, Scale from Woolsey No. 1 Utilizing "A" Train before scheduled shut down, and Scale from Woolsey No. 1 Utilizing "A" Train after the scheduled shut down. The reader must remember the first stage heat exchanger, the P-2 injection pump, and the injection line are common to both trains. The samples for the second stage heat exchangers and for the cooling water condensers will be listed with the Woolsey scale samples even though one of them is a Magmamax heat exchanger.

4.4.1. Scale from Magmamax No. 1 Utilizing B Train

Appendix D lists the scale analyses for samples taken from the Magmamax Train. The major chemical species found in the scale are silica (SiO_2), iron sulfide or iron oxide (FeS or Fe_2O_3), lead sulfide or lead oxide (PbS or PbO) and calcium hydroxide ($\text{Ca}(\text{OH})_2$). The scale at the wellhead is primarily lead sulfide, iron sulfide, and silver sulfide (Ag_2S) with lesser amounts of silica and calcium hydroxide. As the brine flows through the plant, the scale deposition reverses, that is, the silica and calcium compounds become the predominant species and the lead, iron and silver become the lesser species. This same trend is noted in the previous quarterly report (Oct 1978 - Dec 1978).

4.4.2 Scale from Woolsey No. 1 Utilizing A Train before schedule shut-down

Appendix E lists the scale samples for the Woolsey Train before the March 19th shut-down. The samples still show an increase in silica concentration as the brine flows through the plant. The P-2 discharge samples are very similar in composition and both are relatively high in silica. Scale samples from a CorReco lined spool piece were taken at two different times. The first sample was taken February 16, 1979. The preliminary indication was that the liner was very effective in preventing scale build-up. However, when the spool piece was placed back into the injection line, the position of the liner was changed, so

that the liner was placed into the injection line, where the spool piece without the liner had been originally. This was done in order to determine if the flow of the brine had any effect on scaling.

On March 6, 1979, the spool piece was again removed from the injection line and scale samples were taken. The scale thickness on both sides of the spool were the same, as was the chemical composition. It appears that the major factor on any type of liner is the position of the spool piece with reference to flow. Any future tests involving spool pieces will be conducted with very careful consideration of the brine flow.

4.4.3 Scale from Woolsey No. 1 Utilizing A Train after the schedule shut-down

Appendix F lists the scale samples for the Woolsey No. 1 Train. The brine for the Woolsey No. 1 Train follows the same trend as that for the Magmamax No. 1 Train, that is, the silica concentration increases as the brine flows through the plant.

The scale samples from the steam scrubbers were mainly iron sulfide (FeS) and iron oxide (Fe_3O_4). The sample from the top of the 2A scrubber had a high concentration of calcium chloride (CaCl_2) and calcium carbonate (CaCO_3). This shows that the scrubber is not effective in eliminating

some of the elements from the steam and would also account for the high calcium scale in the heat exchanger. This may also have been the reason why the steam samples were so erratic throughout this last test period.

4.5 Future Projects

During the next test period the laboratory will be concentrating mainly on noncondensable gases and steam purity. These two factors are going to be playing a major role on future power plants, so it would be very beneficial to concentrate on these two areas. The brine analysis will still be done but to a lesser extent than it has been in the past.

5.0 MAINTENANCE

W. S. Bischoff/R. J. Peirce

5.1 Supply Lines

5.1.1 Woolsey No. 1 Supply Line (Outage #8)

On March 26, 1979 the test spools were removed on Woolsey supply line after 904 hours of operation. Scale thickness was 1/16". Samples were taken by the lab and the line was not cleaned but reassembled. The two double block valves located near the wellhead were removed due to scale build-up in them and replaced with two rebuilt ones. Scale thickness at the double block valves revealed about 1/16" of scale. The test tubing string was removed from within the well.

5.1.2 Magmamax No. 1 Supply Line

During the shutdown period prior to the July 10, 1978 startup, the brine supply line from Magmamax No. 1 well was opened at several locations for inspection and hydro-blasted clean. On January 11, 1979 after 2,580 hours of operation on Magmamax No. 1, a blank was removed to inspect the line for scale. About 1/8" of scale was found and a sample was sent to the lab. (Refer to Section 4.4.1)

NOTE: See Table 1-2 for description of outages.

5.2 A Train

5.2.1 1st Stage Separator (V-1) And Drain Line

On February 1, 1979 test spools were removed after 307 hours of operation to inspect scale thickness and determine results of Daedalean's cleaning method. There was .065" scale thickness on the spool piece that Daedalean cleaned while in operation. On another spool piece that had not been cleaned, there was .190" of scale. (Refer to Section 4.4.2 for lab analysis)

On March 21, 1979 after 904 hours of operation, this separator and drain line were opened for inspection and cleaning. Scale found in the separator is shown in Figure 5-1. The vessel was cleaned by Southwest Chemical by hydroblasting. The amount of scale removed was 1155 lbs. (Refer to Section 4.4.3 for lab analysis.)

The drain line revealed about 9/16" of scale in the section of line not cleaned by Daedalean's on-line cleaning method. The section of line that Daedalean cleaned while the system was in operation as well as once after operation was clean to bare metal. As previously mentioned, on February 1, 1979, this line was opened and inspected to determine Daedalean's success of cleaning. Since that time Daedalean had increased the operating pressure to their nozzle.

SCALE LOCATIONS 1A SEPARATOR (V-1)
FIGURE 5-1

The thermowell that was equipped with cleaning nozzles by Daedalean met with fair success. The thermowell had about 1/16" of scale on it but some sections were bare metal. This compared to about 9/16" of scale in the pipe. The two gate valves, with cleaning nozzles by Daedalean, installed in the "A" train were partially successful. One valve had enough scale on the seat that the valve could not be closed off completely. The other valve had some scale on the seat. On March 18th, the day before the plant was shutdown, the valves were closed and the test spool isolated successfully. Apparently seating was accomplished by embedding the gate into the scale.

5.2.2 1st Stage Scrubber (V-8)

On January 2, 1979 the plant was shut down to complete 1,103 hours of operation. The first stage steam scrubber was opened for inspection and cleaning. The interior inspection revealed normal scaling. Some loose scale at the bottom had accumulated and the bottom three trays had some scale and rust. The top two trays were cleaned as the other trays were relatively free of debris. The inside of the vessel was cleaned and the weir tubes were blown out to prevent blockage.

Ultrasonic thickness readings were taken on the top and bottom trays. Because this was the first time this was done, there were no other readings to compare it with.

The specification sheet shows the trays to be made of 3/8" (.375") steel. The readings were as follows:

<u>Bottom Tray</u> (in inches)	<u>Top Tray</u> (in inches)
1. .364	.370
2. .362	.372
3. .362	.370
4. .329 (under a drain pipe)	.370
5. .372	.385
6. .352	.390
7. .364	.348
8. .340 (under a drain pipe)	.389

Samples of scale were sent to the lab for analyses (Refer to Section 4.4.1). Upon completion of cleaning the vessel was closed.

A two foot long test spool was installed in the steam line between the 1st stage scrubber and the 1st stage heat exchanger. Ultrasonic thickness readings were taken and will be used to check for corrosion rates of steam piping.

On March 21, 1979 the 1st stage scrubber was opened for inspection. There had been 904 hours of operation since the last cleaning. The vessel was very clean compared to other times. The top two trays were clean of any scale. All weir tubes were clean. The bottom of the vessel had about 1" of debris covering a 9" circle. Most of the scale appeared to be rust. Scale samples were taken by the lab for analysis (Refer to Section 4.4.3). The vessel was cleaned and reassembled using a total of 37 man hours.

5.2.3 2nd Stage Separator (V-14) And Drain Line

On March 21, 1979 this separator and drain line were opened up for inspection and cleaning. Scale conditions found in the separator are shown in Figure 5-2. Southwest Chemical cleaned the separator by hydroblasting. The amount of scale removed from the separator was 2,340 lbs. Scale samples were taken by the lab (Refer to Section 4.4.3)

The drain line was inspected where the control valve (Galigher) was removed and 2" of soft scale was found at the inlet of the valve. A 2' section of the pipe was cut out on the outlet of the 2A separator and 1 1/2" of soft scale was found. This section of pipe was replaced by a spool piece lined by CorReco. The drain line was cleaned by Southwest Chemical Company.

5.2.4 2nd Stage Scrubber (V-10)

On March 21, 1979 the scrubber was opened for inspection. There has been 904 hours of operation since the last cleaning. A large amount of scale was found inside for such a short run. On the top tray there was up to 2" of loose scale built up on one side (south side). Two of the weir tubes were plugged up. On the second tray from the top there was up to 1" of scale piled up and again on the south

SCALE LOCATIONS 2A SEPARATOR (V-14)
FIGURE 5-2

side. All weir tubes were clean. On the 3rd and 4th trays from the top there was found about 1/2" of loose scale all over the tray. All weir tubes were open. On the bottom tray there were three weir tubes plugged up. On the bottom of the vessel there was about 1" of loose scale found. Scale samples were taken by the lab. (Refer to Section 4.4.3)

The vessel was cleaned of all loose scale and rust. A total of 28 man hours was spent cleaning the vessel.

5.3 B Train

5.3.1 1st Stage Separator (V-4) And Drain Line

On January 2, 1979, the plant was shutdown to complete 1,103 hours of operation. 1B separator and brine outlet lines were opened for inspection and cleaning.

On the brine outlet line the 1st removable 90° elbow and the test spools were removed for inspection. The scale thickness was between .200" and .300". This was about the same as on the last run but the scale formation was different. The time before there was a smooth layer of scale. This time there was a rippling layer of scale. Scale samples were taken and sent to the lab (Refer to Section 4.4.1). The test spools on the by-pass section were reinstalled without being cleaned. The gate valves were removed, cleaned and reinstalled. Southwest Chemical Company hydroblasted the drain line from the vessel to LCV 714.

The separator was inspected and 18" of loose scale was found in the bottom of the vessel. The inlet line coming into the vessel had an average of about 1" of scale. The top and sides above the waterline had about .100" thick scale. The drain pipe at the vortex breaker had about 3/4" of scale. Scale samples were taken and sent to lab (Refer to Section 4.4.1). The vessel was hydroblasted clean and 642 lbs of scale was removed by the Southwest Chemical Company.

5.3.2 1st Stage Scrubber (V-8)

This scrubber is used for the first stage in both A and B trains. Refer to Section 5.2.2 for detailed cleaning and maintenance.

5.3.3 2nd Stage Separator (V-11) and Drain Line

On January 2, 1979 the plant was shut-down to complete 1,103 hours of operation. The separator was opened and the spool piece in the brine outlet was removed for inspection.

The vessel was inspected and 3 feet of soft scale was found on the bottom of the vessel. On the side below the waterline there was between 3 1/2" to 4 1/2" of scale. On the top and side above the waterline there was about 1/8"

thick scale. The vessel was hydroblasted clean and scale was removed by Southwest Chemical Company. 4,527 lbs of scale was removed from the vessel. Refer to Section 4.4.1 for lab analysis.

The spool piece on the brine outlet line was removed and was replaced by a CorReco lined spool piece (12" x 33 11/16"). The inlet side to the spool piece had 3/4" of scale and the outlet side of spool piece had about 2" of scale. On the last run this line plugged up sufficiently to affect the operation of the plant and the line had to be flushed with cooling water to keep the plant in operation. The installation of long radius elbows on the last shutdown apparently did some good because there was no problem with operation on this run and no flushing was required.

The water column and sight glass were lowered 18" in order to maintain a normal water level in the separator, 30" instead of 42" as previously designed. This was done in an attempt to prevent the carryover of brine with the steam. This modification also required lowering the vortex breaker inside the vessel (See Figure 5-3). A baffle plate was also installed to retard "sloshing" of the brine. It is expected to reduce carryover, if the cause is "sloshing".

5.3.4 2nd Stage Scrubber (V-12)

On January 2, 1979 the plant was shut down to complete 1,103 hours of operation. The steam scrubber was opened up for inspection and cleaning.

VORTEX BREAKER DETAIL
FIGURE 5-3

Upon inspection the interior was found to contain a large amount of scale which indicated carryover from the separator. Heavy flinty scale was found on the side wall from 1/16" to 1/8" thick in the top chamber and tray. This was a hard scale that flaked off quite easily. The loose scale in the top tray was from 3/16" to 1/4" thick. The lower trays had an average of 3/16" scale on the walls and overhead with 1/4" to 3/8" loose scale in the bottom of the trays. The weir tubes showed a very heavy corrosion and pitting. By tapping on them some sounded quite thin. However, this thinning was not felt to be serious enough to warrant repair. The very bottom chamber had a soft sludge type scale up to the water line. Scale above the water line resembled that in the upper chambers.

Ultrasonic thickness readings were taken on the top and bottom trays to determine the amount of wear (See Figure 5-4). Scale samples were taken and sent to the lab (Refer to Section 4.4.1).

March 21, 1979 the scrubber was opened up for the inspection and cleaning. During a run of 904 hours this scrubber was used as a sump for condensate from the second stage Woolsey train heat exchanger only. The vessel required very little cleaning and was reassembled. A total of 31.5 man hours were expended in cleaning.

READINGS (IN INCHES)
ORIGINAL THICKNESS - 0.375 IN.

DATA POINT	TOP PLATE	BOTTOM PLATE
1	0.2920	0.2690
2	0.2890	0.2710
3	0.2950	0.2750
4	0.2980	0.2930
5	0.2920	0.2920
6	0.2980	0.2960

ULTRASONIC THICKNESS READINGS (V-12)
FIGURE 5-4

5.4 Valves

5.4.1 Pinch Valve (Red)

On January 2, 1979 the plant was shutdown to complete 1,103 hours of operation. At this time the valve was removed for inspection.

This valve is used as a control valve in the brine system between 2-B separator (V-11) and the atmospheric flash vessel (V-15). Prior to startup on November 9, 1978, the liner was replaced with one made of viton.

The results of the viton liner is very encouraging. Very little scale adhered to the inlet of the liner and was very soft. The outlet of the liner was clean. The inlet pipe to the Red Valve had about 2" of scale. Scale samples were taken from the inlet line to the Red Valve and from the Red Valve liner itself. Refer to Section 4.4.1 for scale analysis.

5.4.2 Pinch Valve (Galigher)

On March 20, 1979 the Galigher pinch valve was removed for inspection and repair. This concluded 904 hours of operation on the valve. Scale buildup of 2" was found in the inlet pipe and 1/4" was found in the outlet pipe. About 1/16" of scale had adhered to the liner although some bare spots on the liner were visible due to flexing. Refer

to Section 4.4.3 for lab analysis on scale. It was attempted to hydroblast the liner clean but this was not possible. The liner, made of butyl rubber, could have been used again but there was no guarantee on how long it would last. The company was called to see if it was possible to get a liner made of viton or another type of material. Viton was not possible and no other type of material was recommended by them. A new liner made of butyl rubber was used and the valve was reassembled and installed.

5.4.3 PCV 300

After 904 hours of operation PCV 300 was removed for inspection, cleaning, and repair on March 20, 1979. PCV 300 is the inlet valve to the 1st stage A separator. Some scale had accumulated on the ball of the valve, but the valve never did stick during operation. 3/16" of hard black scale was found on the inlet and outlet of the valve.

The valve was disassembled and sent to Southwest Chemical to be acid cleaned. Upon delivery from Southwest Chemical, the valve was reassembled and installed.

On January 26, 1979 a pin hole leak (caused by erosion by the high velocity flow at this point) developed on the outlet elbow from PCV 300 going into the 1st stage A separator. The plant was shut down and a patch was welded in place and the plant was started up again five hours later. Upon completion of this run the elbow was replaced.

5.4.4 LCV 712

After 904 hours of operation LCV 712 was removed for inspection, cleaning and repair on March 20, 1979. LCV 712 is the inlet valve to the 2A separator. Although 1/32" of scale formed on the valve ball, the valve remained free to open and close during this run. Hard black scale, 3/16" on the valve inlet and 1/32" on the valve outlet, was found upon inspection. Refer to Section 4.4.3 for lab analysis on the scale.

The valve was sent to Southwest Chemical to be acid cleaned. Upon delivery from Southwest Chemical the inside of the body was found to be badly damaged by erosion. The valve body was sent to the SDG&E Machine Shop to be built up with stellite. Upon return the valve was reassembled. The following new parts were purchased from Fisher Controls and installed: composition ball seal, backup ring, one new shim seal and grease fittings.

5.4.5 LCV 718 A

On January 2, 1979 the plant was shutdown to complete 1,103 hours of operation. LCV 718A was removed for inspection.

LCV 718A is the control valve on P-2 discharge controlling the level on the atmospheric flash vessel (V-15). The performance of the valve during this run was good. Upon

disassembly, the valve had a large amount of soft scale inside but this did not impair valve operation. The valve was sent to Southwest Chemical to be acid cleaned to free it of scale. Upon return, the valve was reassembled and installed.

After 904 hours of operation LCV 718A was removed for inspection, cleaning and repair on March 20, 1979. The valve remained fairly free to open and close during this run. At times the valve did stick on a full open or full closed position. Soft scale was found (as on previous inspections) in the valve upon disassembly.

After disassembly the valve was sent to Southwest Chemical to be acid cleaned. Upon delivery from Southwest Chemical the inside of the valve body was found to be badly pitted from erosion. The valve body was sent to SDG&E Machine Shop and built up with stellite. Upon return the valve was reassembled. The following new parts were purchased from Fisher Controls and installed: new ball seal, backup ring and two new shim seals.

Upon completion of the clarifier installation, this valve will not be used anymore. The brine will leave the Atmospheric Flash Vessel (V-15) via the feed pumps (P-16A and P-16B) to the clarifier. After clarifier installation, LCV 718A, will be used in the event that the plant is ever to be operated again without the clarifier.

5.4.6 PCV 301/LCV 714/Misc.

On January 2, 1979 the plant was shut down to complete 1,103 hours of operation. The pressure control valve to the 1B separator (PCV 301) and the level control valve to the 2B separator (LCV 714) were removed and disassembled for inspection.

These valves had performed well throughout the entire run. Prior to the run the valves had been acid cleaned, the ball coated with stainless steel, remachined to proper dimension and polished. Upon disassembly a layer of scale was found on the balls but the valves did not stick. The valves were sent to S. W. Chemical Company to be acid cleaned. Upon return the valves were reassembled and stored for spares.

Other valves were returned from E/M Lubricants, Inc., reassembled and installed. The balls had been remachined to design dimension, polished and sent to be coated with stainless steel. Through a special process Ecoalube 642, a solid film lubricant suspension in concentrated form containing molybdenum disulfide, was applied. This coating was being used in the hopes that it would prevent scale formation.

5.5 Atmospheric Flash Vessel (V-15)/P-2 Suction Piping

Following the shutdown on January 2, 1979 a modification was made on the suction line from V-15 to P-2. Elbows were removed and tees were installed with 12" valves

in order to insert a cleaning nozzle in the line. This will allow in-line cleaning of P-2 suction while in operation for testing.

On March 5, 1979 the plant was shut down to clean the atmospheric flash vessel (V-15) and P-2 suction piping. The purpose of this was to have a clean system to evaluate an inhibitor injection into the brine supply line. The suction piping had accumulated, after 485 hours of operation, 2 1/2" thick scale at the pump end and 2 1/4" thick scale at the V-15 end. Scale samples were sent to the lab for analysis (refer to Section 4.4.2). While the line and vessel were being cleaned, the decision was made not to inject the inhibitor due to the need to conduct higher priority tests.

5.6 Injection Pump P-2/P-17

Problems with the injection pump P-2 began late last quarter on December 30, 1979 when the discharge pressure started falling and problems were experienced on pumping out V-15. Up to this time Southwest Chemical hydro-blasted P-2 suction and flushed the can with cooling water. It was then necessary to flush the can two or three times daily to enable P-2 to pump out V-15. It was also necessary to use the pump discharge to flush out the can. On December 31st brine flow was reduced in order to keep the V-15 level at a normal level.

On January 2, 1979 the plant was shut down to complete 1,103 hours of operation. On January 3, 1979 the P-2 injection pump was removed from the can and sent to the SDG&E Machine Shop. The section between the pump and the can was about 90% plugged with scale. The pump suction line had approximately 2 7/8" of scale and the discharge line had approximately 2" of scale.

On January 4, 1979 the Machine Shop delivered the new pump head to the site. The head was set in place and the discharge flange tack welded in place. The old pump head was sent along with the pump back to the Machine Shop.

On January 15, 1979 the pump (original one) was sent to the site and installed. On January 16th, while attempting to install the coupling, it was discovered there was not enough clearance between the pump shaft and the motor shaft. The shaft was about 3/8" higher than normal. It was assumed to be due to the fact that the pump bowls were ground down enough to raise the pump shaft. On January 17th 3/8" was cut off from the top of the pump shaft to allow the coupling to fit in. The pump was installed and tested satisfactorily.

Southwest Chemical cleaned the discharge line from P-2 to LCV 718A. This completed the cleaning and startup began on January 18, 1979.

On January 31, 1979 the injection pump failed due to a broken shaft. The shaft broke just above the top impeller. The pump failed at about the same time a pig was

launched; this may or may not have a bearing on the failure. The pump was sent to SDG&E Machine Shop and disassembled. A new Hastelloy shaft was installed on the lower part and a stainless steel shaft on the upper part of the pump. On February 5, 1979 the pump was returned and installed.

On February 6, 1979 the pump base was found to be leaking. The whole pump was lifted and a piece of old gasket material was found lodged under the pump base. The old material was removed and a string of teflon packing was placed in the pump base. The plant was started up and after the pump was run for a period of about 30 minutes, all bolts on the base were again retightened. The pump was running smoothly. On this same day the mechanical seal that is supplied with purge water started leaking. The purge line could have been partially plugged or the supply valve might have inadvertently throttled down. To keep the seal cool, flow to the seal was increased. On February 8, 1979 the plant was secured to renew a shaft seal in P-2. The plant was started up in the early afternoon and brought up to baseline conditions.

On February 9, 1979, while in the process of cycling control valves and blowing down vessel water columns, P-2 failed. The pump lost discharge pressure, V-15 went high level and pump amps dropped from a normal of about 58 down to about 20. Indications were a broken pump shaft. This was the second occurrence on this run. The pump has 59

hours and 30 minutes of operating time since the pump was repaired after the shaft broke on January 31, 1979. Cycling valves and blowing down water columns are standard procedures done once a shift to keep the control valves from sticking and to keep the water columns clear from plugging. When doing this the flow of brine will change about 400 gallons per minute. Up to this time the pump was performing well. The last failure of the pump on January 31, 1979, occurred while launching a pig down the injection line. This procedure will also cause a change in flow through the pump. Bechtel National, Inc. was contracted to inspect the broken shaft and determine the cause of failure. Refer to Appendix G for details of the investigation.

The P-2 injection pump was removed on March 5, 1979 after 418 hours of operation for exterior cleaning. During this scheduled shutdown, the pump and can were cleaned. The P-2 discharge and suction piping were also cleaned.

On March 7, 1979, the P-2 injection pump was set in place after cleaning was finished. Plant warm-up was started in preparation for coming on stream but had to be halted because the P-2 pump would not turn. Acid water was purged to the bearings in hopes that if there was scale built-up it would correct the situation. It did not work. On March 8, 1979, the plant was still down due to the P-2 injection pump being frozen. The Woolsey supply line double block valves were closed to prevent a possible leak thru of

plant valves. Vessels were drained of accumulated brine and water. The P-2 pump was bumped electrically two times this date but remained frozen. Suction piping was removed from the P-2 pump in preparation for acid cleaning.

On March 9, 1979 acid was circulated thru the P-2 injection pump and pump can. This process was continued thru March 10. The following day the P-2 injection pump was left soaking in the acid solution and then neutralized.

On March 12, 1979, the P-2 pump was bumped twice electrically. The pump again failed to move and was then removed from the pump can. This pump was disassembled at the site. The second stage bowl bearings were found frozen. All of the other bearings and journals were scarred badly, but it was doubtful that the bearings were seized to the journals except in the 2nd stage. Most of the purge connections were blocked off due to the bearing shifting and covering the purge hole. This could have happened while the pump was in operation or when the bowls were being removed. It can not be determined whether the loss of purge water caused the bearing to seize and shift the bearing to block the purge line, whether the bearing shifted first and blocked the purge line causing loss of purge water, or when removing the bowls the bearings moved and covered the purge line during disassembly. However, corrective actions were taken to prevent the possibility of bearing shift in the future. The bearing was pressed out of the 2nd stage bowl and some scale was found in the purge line behind the bearing.

The bowls and impellers were sent to Southwest Chemical to be cleaned. After cleaning, the bowls, impellers, and shaft were sent to SDG&E Machine Shop for machining.

The spare P-2 injection pump had been at the shop where it was being reassembled. This pump was received on March 14, 1979 at which time it was installed.

On March 29, 1979 the original pump was returned from the SDG&E Machine Shop. The 9th stage (last stage) was left out of the pump and a spool piece was installed in its place. This was done due to a new application for the pump. All wearing ring clearances were between .040" and .045". The pump was reassembled and placed into a new can at the clarifier. The motor was sent to the shop to have new bearings installed and upon the return the motor was installed on the pump. This pump has been moved to a new location downstream of the Clarifier/Filter Installation and is now designated as P-17.

5.7 Injection line

On February 13th the injection line was hydro-blasted clean from the elbow above the A Train, first stage separator to the "CorReco"-lined spool piece. The last time this was cleaned was during plant modification prior to July 10, 1978 startup. There had been approximately 2,860 hours of operation on this line between cleaning. Through-

out the line there was about 1/2" of hard scale. The scale was completely removed from this section of line.

A problem occurred during cleaning while moving the cleaning nozzle through one of the elbows. It is suspected that a weld joint on the elbow may have caused the nozzle head to bind in the elbow. With difficulty, the nozzle was forced around the elbow and the line was cleaned.

On March 5, 1979 the plant was shut down to clean a section of the injection line. The purpose of this was to have a clean system to evaluate an inhibitor injection into the brine supply line, however this inhibitor injection test was later cancelled. Southwest Chemical cleaned about 16 feet of injection line from P-2 up to the 1st elbow. Scale of 1 1/4" in thickness had accumulated after 792 hours of operation. Refer to Section 4.4.2 for lab analysis of scale.

The "CorReco"-lined spool piece, located in the injection line, was removed and inspected on March 6, 1979, after 425 hours of operation. 3/8" of scale was found on the CorReco liner and 1/2" of scale on the unlined portion. The grey colored scale was soft, brittle and easily removed. Refer to Section 4.4.2 for lab analysis of scale.

After the plant was shutdown on March 19, 1979, the injection line was opened for inspection at various locations. The line was opened near the LLL injection point, just before going under the drainage ditch and just

before going under the road at the Magma site. Thickness of scale at all locations revealed about 5/8" of hard scale. Scale samples were sent to the lab for analysis (Refer to Section 4.4.3). Southwest Chemical company hydroblasted from the discharge of P-2 up to the inlet of LCV 718A.

The "CorReco"-lined spool piece was removed and turned over to SDG&E's Construction Department to be installed on the P-17 discharge line. A spool piece was made up and installed where the "CorReco" spool piece was removed. A loop was installed in the injection line within the plant boundary near the fence at the Bureau of Mines site. The purpose of this was to keep the line full of water so that the ultrasonic flow meter would operate. The ultrasonic flow meter was removed from the discharge of P-2 and installed on the loop.

The SDG&E Construction crew tied in the injection line from the new injection pump discharge location into the old injection line. Injection from P-17 can now go into the old injection wells (Magmamax No. 2 or No. 3) or into the new injection well (IW-5). The injection flow can also be split out so that clarified brine from P-17 can go to the injection well (IW-5) and P-13 discharge can go to either Magmamax No. 2 or No. 3 from the brine pond/Baker tank.

5.8 HEAT EXCHANGERS

5.8.1 1st Stage Heat Exchangers (E-2/E-3)

On March 14, 1979 the inspection ports were removed from the 1st stage heat exchangers (E-2 and E-3) to inspect the shell side of the exchangers. No scale was found in either heat exchanger.

5.8.2 2nd Stage Heat Exchangers (ElB/ElC)

On March 22, 1979 the heads on 2A and 2B heat exchangers (ElB and ElC) were removed to inspect the tubes and tube sheets. Both heat exchangers revealed scale deposits on the tube sheet. The lab took scale samples for analysis (Refer to Section 4.4.3).

The 2A heat exchanger (ElB) had been last inspected on April 26, 1977. At that time the tubes and tube sheet were found clean. The 2B heat exchanger (ElC) had last been opened for inspection on July 13, 1977 and large amounts of scale were found at that time. For prior information on scale deposits and cleaning, see September 1976 Bi-monthly report Appendix B.

5.9 Cooling Water Condensers (E4A/E4B)

The cooling water system had been in operation almost constantly from November 9, 1978 to March 22, 1979 when it was shut down for inspection and cleaning. This was

approximately 3,192 hours of operation on the C.W. system. During operation the pressure differential had increased slowly from 8 psi in November 1978 to 17 psi in March 1979. Prior to shutting down the C.W. system, all of the spray headers were opened and the pressure differential on the condensers was found to be 23 psi. It was found that each condenser could be successfully isolated at this time.

Upon removal of the condenser heads the tubes and tube sheet looked very clean. There was some debris on the tube sheet consisting mostly of grass type material and some scale build-up on the tubes (see Section 4.4.3 for lab analysis of scale). The Plasite coating previously applied on the water boxes held up very well, although, a few spots showed rust coming through. Southwest Chemical Company hydroblasted each tube in the E4A condenser. The E4B condenser was cleaned by on-site personnel with a small hydroblaster. The tube sheets were cleaned and each tube was flushed out with the hydroblaster. About seven tubes were plugged and these tubes were rodded out and flushed again. The bad spots on the Plasite coating were touched up and the C.W. inlet line was hydroblasted clean by Southwest Chemical. The condensers were hydro tested to check for leaking tubes and no tubes were found to be leaking. The heads were reinstalled and the C. W. System was placed back in operation. All spray headers were opened and the pressure differential was found to be 16 PSIG.

6.0 GLEF REACTOR CLARIFIER/MEDIA FILTER INSTALLATION

D. G. Newell

6.1 Purpose

The Reactor Clarifier/Media Filter Installation at the GLEF is intended to demonstrate that suspended solids in the brine can be removed prior to injection into the reservoir and that silica concentrations in the brine can be reduced to saturation values or below. The treated brine is expected to extend the useful life of the injection wells significantly.

6.2 Description of Project Organization

SDG&E and DOE are jointly funding engineering and construction of the facility. The Ben Holt Company is performing the detailed engineering. SDG&E is constructing and starting up the facility and Imperial Magma will operate and maintain the facility and monitor performance of the new injection well (IW-5) that has been drilled to accept the treated effluent.

6.3 Technical Description of Facility

A schematic of the system is shown in the process flow diagram (Figure 6-1). 625,000 lbs/hrs of brine is pumped from existing atmospheric flash drums by the clarifier feed pump, P-16, to the reactor clarifier, V-17. A flow

control valve is manipulated by the existing level controller on the atmospheric flash drum. The existing system maintains flow out of the flash drum in the same manner; consequently, this method of controlling flow to the system will not alter the operation of the existing plant.

The reactor clarifier, V-17, provides residence time for formation and settling of solids. The effluent brine flows by gravity to the sand and anthracite media filter, V-18B, and thence, to the brine surge tank, V-19, from where it is pumped by the injection pump to a pressure of approximately 500 psig for injection.

The 3,710 lbs/hr of sludge from the reactor clarifier, V-17, flows by gravity to the thickener, V-22, where the sludge is concentrated to 10 percent solids by weight. The sludge from the thickener is pumped to the plate and frame filter, F-1. A cake is produced at the rate of 257 lbs/hr (357 lbs/hr during V-20 drain). The filter is operated approximately every three hours for the necessary length of time and automatically shut down. The filter press is manually opened and the cake drops into transportable bins, V-21.

The effluent from the thickener, V-22, and the plate filter, F-1, both flow into the backwash holding tank, V-20.

The media filter, V-18B, must be backwashed once every 24 hours. To accomplish this without disrupting flow through the plant, three media filters are provided so

that one can be backwashed once each eight hours. The remaining two carry the full flow for the approximate 20 minute backwash operation.

The backwash tank, V-18A, is filled in four hours by 80 gpm of brine effluent from the media filter. This metering is accomplished by a flow oriface/splitter box which is part of the media filter system, V-18. The backwash operation consists of a seven minute drain, followed by an air blowdown then a 5-1/2 minute backwash time. The backwash fluid flows by gravity from the backwash tank (V-18A) up through the media filter (V-18B) to be backwashed, and thence, by gravity into the backwash holding tank, V-20. A rising level in V-20 activates the return pump, P-19, which pumps the backwash brine containing 1.14 weight percent suspended solids to the clarifier (V-17) influent line. This drains the holdup tank in four hours. Consequently, at this drain flow rate, the backwash cycle can be reduced to four hours. Furthermore, the pump, P-19, and associated lines are sized for 160 gpm so that the cycle time can be further reduced to two hours, if necessary, subject to maximum total flow rate of 1,600 plus five percent gpm into the reactor clarifier V-17.

During the four hour drain period, 56.7 lbs/hr of suspended solids are added to the clarifier by the backwash brine to the 204.3 lbs/hr suspended solids entering the clarifier in the effluent brine. Consequently, during the

four hours drain period, the cake produced contains 232 lbs/hr suspended solids, compared with 167 lbs/hr otherwise. That is, of the 204.3 (or 261 during V-20 drain) lbs/hr suspended solids entering the clarifier, 27.3 (or 29.3) lbs/hr leave in the effluent brine and 167 (or 232) lbs/hr leave in the sludge. The solids leaving in the clarifier effluent brine are removed in the media filter and subsequently backwashed to the holding tank, V-20, and then to the clarifier, V-17, during the drain period as described.¹

6.4 Current Project Status

The Clarifier/Filter Installation has been split into four systems (Injection, Clarification, Filtration, and Filter Press) to allow for an orderly, phased startup of the facility. The start-up schedule is attached as Figure 6-2.

As of March 30th, the project is on-schedule. All equipment is on-site except the clarifier feed pumps, two control valves and some non-essential instrumentation. Promised delivery dates for the critical equipment are not expected to cause a delay in the project. All vessels are erected, most major piping is complete and most electrical conduit has been installed. The first system to be started up (brine injection) is expected to be turned over to SDG&E's Start-up Section in April.

¹The Ben Holt Co., "GLEF Reactor Clarifier/Media Filter Installation, System Design Package", November 17, 1978, pp 1-4.

FIGURE 6-2

The GLEF is scheduled to begin to supply brine to the clarifier facility on April 27th. During the first two or three weeks of operation, the facility will operate at less than optimum conditions (during the sludge blanket build-up in the clarifier) and hence will not effectively remove suspended solids from the brine. During this time the brine will be injected into the original injection wells. Once the brine produced from the facility is clean enough (as established by Imperial Magma), the fluid will be directed into the new injection well (IW-5). This action is tentatively scheduled in May, 1979.

7.0 OTHER ACTIVITIES

7.1 Feasibility Study W. O. Jacobson

The initial phase of the Feasibility Study indicated that a dual entry steam turbine would be optimum. Industry data is being collected on dual entry steam turbine performance and maintenance. Initial responses do not indicate significant operational or maintenance problems. Data will be used in the next phase of the Feasibility Study, which is expected to be initiated during the next reporting period.

7.2 Direct Contact Heat Exchanger L. G. Van Wagenen

Based on the results of the Feasibility Study Addendum, Phase 1, a direct contact heat exchanger effort was initiated.

The goals of this project are to design, install and test a direct contact heat exchanger placed downstream of a first stage flash vessel at the GLEF. Working fluid is expected to be isopentane. Potential advantages of this arrangement include:

- . Minimum working fluid impurities due to removal of noncondensable gases in the first stage flash.
- . Ability to vary first stage flash conditions to simulate other reservoir conditions.
- . Elimination of binary fluid boiling in the direct contact heat exchanger simplifies design.
- . Prior removal of noncondensable gases simplifies recovery of entrained working fluid.

- . First stage flash generates a supply of condensate that can be used for cooling water makeup.
- . Scale control potential of the direct contact process will be evaluated.

The effort has been divided into two phases. Phase I includes the design and procurement activities. Phase II covers installation and testing, and will be initiated if funding is assured.

7.3 Surge Study W. O. Jacobson

A final surge study report was issued by The Ben Holt Co. The report concluded that observed facility surging was caused by two phase flow separations in the production line which could be corrected by installing a small surge tank upstream of the first stage flash vessels. Two surge tank approaches were defined. The first approach separated the two phases, allowing each phase to be separately controlled to the first flash vessel. The second approach was to remix (homogenize) the separated phases, allowing the mixture to be controlled to the first flash vessel.

Initial engineering was authorized to design a surge tank for each production line. Both design approaches (separation vs. remixing) are to be evaluated. If equipment can be installed within a short period, construction will be authorized.

7.4 Noncondensable Gas Content W. O. Jacobson

Noncondensable gas content of the brine is an important area where GLEF data has been collected. Measurements have utilized two methods. The first method records the flowrate of vapors coming from the first stage heat exchanger. This mass flowrate is corrected for water content and divided to brine flowrates to obtain noncondensable gas content. The second method collects bomb samples of wellhead brines and noncondensable gas content is measured in the laboratory.

Both methods are subject to errors. Composition of first stage heat exchanger vapors and lack of significant noncondensable gas content in second stage heat exchanger vapors is assumed in the first method. The second method assumes a representative sample can be drawn from a surging two phase flow line. Recent data has also shown inconsistent results.

A separate test has been planned to provide more reliable noncondensable gas content data. The objective of this test is to determine the quantity and constituents of the noncondensable gas being evolved at the GLEF. This information will be used in the 2nd phase of the Feasibility Study to evaluate the impact on flash power plant turbine, condenser and ejector systems. Gas flows will be measured at several locations. Gas samples will be taken at these locations, and constituents analyzed. Flowrates will be

measured using orifice meters and pitot tubes. Brines samples will be taken at the wellhead and flash vessels. New sample points will be installed. Tests are expected to be accomplished during the second quarter of 1979.

7.5 Pilot Clarifier Testing W. O. Jacobson

Imperial Magma is continuing to operate a pilot clarifier at the GLEF. During this reporting period, baseline operations were conducted using brine supplied from the second production well (Woolsey #1). No significant differences in performance operating with brine from the second production well was noted. In order to evaluate the effectiveness of the effluent brine as an H_2S scrubber, noncondensable gas was directed to the pilot clarifier. Schedule constraints did not allow time to build up a normal sludge bed, but preliminary data appears to be highly successful. More than 95% of the H_2S was apparently removed with no discernable effect on clarifier operation. Incorporation of this process into the GLEF clarifier is presently being evaluated.

Planned future testing of the pilot clarifier includes evaluation of a pilot crystalizer coupled to the plant clarifier. The crystalizer would replace the 2nd flash stage (on a pilot scale) and feed brine directly to the clarifier by passing the atmospheric flash vessel. Other testing which may be accomplished include cooling water blowdown addition and makeup water injection. These are low priority and will be accomplished as time and manpower permit.

8.0 SUMMARY

During this quarter the plant operated for a total of 932 hours. For the quarter, the plant availability was 43.1% and the availability since start-up was 42.5% based on a total of 10,814 hours of operation.

The plant was down for routine maintenance during the early part of the quarter after a total of 1,103 hours of noncontinuous operation. Following the start-up on January 18, 1979, the plant was shutdown on three occasions due to the injection pump (P-2) failure.

Woolsey No. 1 was used for the production well during this period and Magmamax No. 2 for the injection well. A new injection well (IW-5) was drilled to 1500 feet to accept the treated effluent at the GLEF.

The 1978-1979 GLEF Test Program, consisting of 14 different tests, is continuing. All but one of the tests have been defined by specific objectives, testing has been initiated, and preliminary results of several tests have been compiled. These findings are in the areas of Scale Properties (Test No. 2.0), Scale Control Additives (Test No. 3.0), Corrosion/Erosion Parameterization (Test No. 5.0), Brine Chemistry (Test No. 7.0), H₂S Abatement (Test No. 8.0)

and Injection Studies (Test No. 13.0). Steam Separation (Test No. 9.0) has not yet been authorized and Scale Control-Inhibitors (Test No. 15.0) has been postponed indefinitely. Makeup Water Injection Compatibility (Test No. 11.0) has been completed.

Data is being compiled on sampling of the GLEF fluids. The systems chemistry findings are separated into subsections in the areas of steam, brine, binary and cooling water, and scale. Sampling was affected by contamination of brine carry-over in the steam and by oxidation of the scale due to plant shutdowns.

Many of the plant components were inspected and cleaned during this quarter. Scale samples were removed and sent to the Chemistry Lab for analysis. Following the second plant shutdown, due to a broken shaft in the injection pump (P-2), Bechtel National, Inc. was contracted to determine the cause of the failures. Their report is included as Appendix G.

Construction is continuing on schedule on the GLEF Reactor Clarifier/Filter Installation to demonstrate that suspended solids in the brine can be removed prior to injection and that silica concentration can be reduced to saturation values or below. Construction completion is presently scheduled in April, 1979 and is expected to be fully operational by mid-May, 1979.

The initial phase of the Feasibility Study indicated that a dual entry steam turbine would be optimum. Data, collected from industry use, looks promising and will be used in the next phase of the Feasibility Study. Based on the results of the Feasibility Study Addendum, Phase 1, a direct contact heat exchanger effort was initiated with a definition of goals and potential advantages.

A final surge study report was issued concluding that observed facility surging was caused by two phase flow separations in the production line. Design approaches for correction are to be evaluated.

Measurements of noncondensable gas content of the GLEF brine utilizing two methods were evaluated as subject to errors. A more reliable test is planned for testing. Pilot clarifier testing in removing H_2S from noncondensable gas appears to be highly successful. Planned future testing of the pilot clarifier includes evaluation of a pilot crystalizer.

APPENDIX A

DATE 1-22-79	1ST STAGE STEAM IN	1ST STAGE STEAM OUT	2ND STAGE STEAM IN	2ND STAGE STEAM OUT	COMBINED CONDENSATE
pH	8.30	5.86	9.22	6.15	5.70
Density (g/ml)	0.995	0.995	0.995	0.999	0.995
TDS (mg/l)	216	36	176	556	576
Cond (μ mho/cm)	1240	1580	650	2390	2000
OH ⁻			12		
Cl ⁻	28	6.0	70	527	279
HCO ₃ ⁻	556	1071	0	515	779
CO ₃ ⁼	137	0	233	0	0
SO ₄ ⁼	27	N.D.	0.8	N.D.	N.D.
S ⁼	N.D.	1.5	0.1	0.3	1.0
NH ₄ -N	162	202	130	153	153
Total Alkalinity as CaCO ₃	456	878		422	638
Al	N.D.	N.D.	N.D.	N.D.	N.D.
B	7.0	5.7	2.4	3.5	4.6
Ba	N.D.	N.D.	N.D.	N.D.	N.D.
Ca	5.95	N.D.	12.5	77.4	59.5
Cr	N.D.	N.D.	N.D.	N.D.	N.D.
Co	N.D.	N.D.	N.D.	N.D.	N.D.
Cu	N.D.	N.D.	N.D.	N.D.	N.D.
Fe	0.86	0.08	0.48	1.59	1.16
Pb	N.D.	N.D.	N.D.	N.D.	N.D.
Li	0.03	N.D.	0.08	0.72	0.37
Mg	0.24	N.D.	0.56	0.36	0.16
Mn	N.D.	N.D.	N.D.	1.38	0.72
Ni	N.D.	N.D.	N.D.	N.D.	N.D.
K	2.76	N.D.	6.90	48.3	27.6
Ag	N.D.	N.D.	N.D.	N.D.	N.D.
Si	N.D.	N.D.	N.D.	N.D.	N.D.
Na	9.51	1.06	26.8	211	130
Sr	N.D.	N.D.	0.10	1.23	0.15
Sn					
Zn	18.7	N.D.	0.19	0.37	0.19

Note: All values are ppm unless otherwise indicated.

DATE	1ST STAGE	1ST STAGE	2ND STAGE	2ND STAGE	COMBINED
1-24-79	STEAM IN	STEAM OUT	STEAM IN	STEAM OUT	CONDENSATE
pH	8.30	6.05	9.36	9.05	6.00
Density (g/ml)					
TDS (mg/l)					
Cond (μ mho/cm)	1600	1560	850	1380	1580
OH ⁻					
Cl ⁻	51	13	148	284	153
HCO ₃ ⁻					
CO ₃ ⁼					
SO ₄ ⁼					
S ⁼	N.D.	3.5	0.2	0.1	3.0
NH ₄ -N					
Total Alkalinity as CaCO ₃					
Al					
B					
Ba					
Ca	9.0	N.D.	26	20	10
Cr					
Co					
Cu					
Fe	1.8	N.D.	N.D.	0.26	0.33
Pb					
Li					
Mg					
Mn					
Ni					
K	5.29	N.D.	12.4	23.5	10.6
Ag					
Si					
Na	22.0	0.80	64	121	71
Sr					
Sn					
Zn					

Note: All values are ppm unless otherwise indicated.

DATE	1ST STAGE	1ST STAGE	2ND STAGE	2ND STAGE	COMBINED
1-29-79	STEAM IN	STEAM OUT	STEAM IN	STEAM OUT	CONDENSATE
pH	7.15	5.94	9.38	8.96	5.90
Density (g/ml)	0.9990	1.0000	1.0000	0.9995	1.0000
TDS (mg/l)					
Cond (μmho/cm)	1700	1650	890	1150	1550
OH ⁻					
Cl ⁻	55	6.8	134	250	129
HCO ₃ ⁻	1029	1098	0	14	751
CO ₃ ⁼					
SO ₄ ⁼	25	N.D.	N.D.	N.D.	N.D.
S ⁼	0.2	3.0	0.2	1.0	0.3
NH ₄ -N	218	222	142	110	163
Total Alkalinity					
as CaCO ₃	844	901		11.4	616
Al					
B	7.3	4.6	3.0	4.0	4.1
Ba	N.D.	N.D.	N.D.	N.D.	N.D.
Ca	11.3	1.19	23.8	16.7	8.3
Cr					
Co					
Cu					
Fe	1.70	0.07	N.D.	0.13	0.46
Pb	N.D.	N.D.	N.D.	N.D.	N.D.
Li	0.04	N.D.	0.17	0.36	0.17
Mg	2.50	N.D.	0.21	0.17	0.08
Mn	0.07	N.D.	0.05	0.11	0.07
Ni					
K	3.33	N.D.	10.0	19.2	9.17
Ag					
Si	N.D.	N.D.	N.D.	N.D.	N.D.
Na	21.4	0.99	55.9	83.9	41.1
Sr	0.10	N.D.	0.30	0.40	0.20
Sn					
Zn	N.D.	N.D.	N.D.	N.D.	N.D.

Note: All values are ppm unless otherwise indicated.

DATE	1ST STAGE	1ST STAGE	2ND STAGE	2ND STAGE	COMBINED
1-31-79	STEAM IN	STEAM OUT	STEAM IN	STEAM OUT	CONDENSATE

pH	8.30	5.97	9.48	6.22	5.89
Density (g/ml)	1.0000	1.0000	1.0000	1.0000	1.0000
TDS (mg/l)					
Cond (umho/cm)	1300	1550	1150	1550	1550
OH ⁻			39		
Cl ⁻	46	10.7	231	245	119
HCO ₃ ⁻	542	1085	0	514	807
CO ₃ ⁼	150		137		
SO ₄ ⁼	12	N.D.	N.D.	N.D.	N.D.
S ⁼	N.D.	2.0	0.2	0.3	1.5
NH ₄ -N					
Total Alkalinity as CaCO ₃	445	889		422	661
Al					
B	7.8	4.9	3.3	3.4	4.1
Ba					
Ca	8.93	0.12	28.6	47.6	19.6
Cr					
Co					
Cu					
Fe	0.09	0.09	1.10	0.72	0.06
Pb					
Li					
Mg					
Mn					
Ni					
K					
Ag					
Si					
Na	15.8	2.21	77.2	84.6	40.4
Sr					
Sn					
Zn					

Note: All values are ppm unless otherwise indicated.

DATE	1ST STAGE	1ST STAGE	2ND STAGE	2ND STAGE	COMBINED
2-21-79	STEAM IN	STEAM OUT	STEAM IN	STEAM OUT	CONDENSATE
pH	8.30	5.95	9.02	5.98	5.84
Density (g/ml)	0.9990	0.9990	1.0000	9.9995	0.9990
TDS (mg/l)					
Cond (μ mho/cm)	1290	1700	1900	220	215
OH ⁻					
Cl ⁻	51	4.9	284	624	289
HCO ₃ ⁻	389	1085	236	431	779
CO ₃ ⁼	150		178	0	0
SO ₄ ⁼	22	15		N.D.	N.D.
S ⁼	N.D.	1.0	0.1	0.4	0.8
NH ₄ -N	174	364	141	110	168
Total Alkalinity as CaCO ₃	319	889	194	353	638
Al					
B	6.8	4.0	3.0	3.8	3.9
Ba	N.D.	N.D.	N.D.	N.D.	N.D.
Ca	8.14	0.12	52.3	93.0	29.1
Cr					
Co					
Cu					
Fe	1.00	0.09	1.38	1.68	0.82
Pb	N.D.	N.D.	N.D.	N.D.	N.D.
Li	N.D.	N.D.	0.22	0.86	0.39
Mg	1.42	N.D.	18.8	0.37	0.09
Mn	0.07	0.04	0.57	1.86	0.83
Ni					
K	4.85	N.D.	30.3	48.5	24.8
Ag					
Si	N.D.	N.D.	8.42	N.D.	N.D.
Na	19.0	1.27	199	272	139
Sr	N.D.	N.D.	0.80	1.93	0.85
Sn					
Zn	N.D.	N.D.	N.D.	0.30	N.D.

Note: All values are ppm unless otherwise indicated.

DATE	1ST STAGE STEAM IN	1ST STAGE STEAM OUT	2ND STAGE STEAM IN	2ND STAGE STEAM OUT	COMBINED CONDENSATE
2-23-79					
pH	6.56	6.05	9.50	6.17	5.85
Density (g/ml)	0.999	0.999	0.999	0.999	0.999
TDS (mg/l)					
Cond (μmho/cm)	1830	1700	661	2500	1900
OH ⁻					
Cl ⁻	50	94	92	556	206
HCO ₃ ⁻					
CO ₃ ⁼					
SO ₄ ⁼	5.8	N.D.	N.D.	N.D.	N.D.
S ⁼	0.2	4.0	0.4	0.8	3.5
NH ₄ -N					
Total Alkalinity as CaCO ₃					
Al					
B					
Ba					
Ca	7.78	N.D.	16.7	66.7	33.3
Cr					
Co					
Cu					
Fe	0.70	0.06	N.D.	1.04	0.66
Pb					
Li					
Mg					
Mn					
Ni					
K					
Ag					
Si					
Na	15.7	2.53	28.1	112	59.0
Sr					
Sn					
Zn					

Note: All values are ppm unless otherwise indicated.

DATE 2-26-79	1ST STAGE STEAM IN	1ST STAGE STEAM OUT	2ND STAGE STEAM IN	2ND STAGE STEAM OUT	COMBINED CONDENSATE
pH	7.00	5.96	8.95	6.23	5.89
Density (g/ml)	0.999	1.000	1.000	0.999	1.000
TDS (mg/l)					
Cond (μ mho/cm)	2400	1550	2830	1000	1350
OH ⁻					
Cl ⁻	57	12	600	12	66
HCO ₃ ⁻	1057	1043	417	556	834
CO ₃ ⁼					
SO ₄ ⁼	12	2		N.D.	N.D.
S ⁼	N.D.	N.D.	5.0	1.5	3.5
NH ₄ -N	218	216	154	116	168
Total Alkalinity as CaCO ₃	866	855	342	456	684
Al					
B	6.3	6.0	5.0	1.0	4.2
Ba	N.D.	N.D.	N.D.	N.D.	N.D.
Ca	10.6	0.76	106	15.2	22.7
Cr					
Co					
Cu					
Fe	0.78	N.D.	2.59	0.63	0.56
Pb	N.D.	N.D.	N.D.	N.D.	N.D.
Li	0.02	N.D.	0.40	N.D.	0.07
Mg	1.01	0.15	41.7	N.D.	N.D.
Mn	N.D.	N.D.	0.88	0.13	0.40
Ni					
K	5.0	N.D.	50.0	1.2	4.2
Ag					
Si	N.D.	N.D.	7.50	N.D.	N.D.
Na	20.1	0.49	304	5.4	19.6
Sr	N.D.	N.D.	1.39	N.D.	0.13
Sn					
Zn	N.D.	N.D.	N.D.	N.D.	N.D.

Note: All values are ppm unless otherwise indicated.

DATE 2-27-79	1ST STAGE STEAM IN	1ST STAGE STEAM OUT	2ND STAGE STEAM IN	2ND STAGE STEAM OUT	COMBINED CONDENSATE
pH	6.80	5.83	9.22	6.06	5.75
Density (g/ml)					
TDS (mg/l)					
Cond (μ mho/cm)					
OH ⁻					
Cl ⁻	59.3	18.5	168.0	269.1	129.2
HCO ₃ ⁻					
CO ₃ ⁼					
SO ₄ ⁼					
S ⁼					
NH ₄ -N					
Total Alkalinity as CaCO ₃					
Al					
B					
Ba					
Ca	6.14	0.34	32	38	18
Cr					
Co					
Cu					
Fe	0.45	0.06	N.D.	0.71	0.71
Pb					
Li					
Mg					
Mn					
Ni					
K					
Ag					
Si					
Na	14.6	0.43	53.0	87.0	42.0
Sr					
Sn					
Zn					

Note: All values are ppm unless otherwise indicated.

DATE	1ST STAGE	1ST STAGE	2ND STAGE	2ND STAGE	COMBINED
2-28-79	STEAM IN	STEAM OUT	STEAM IN	STEAM OUT	CONDENSATE
pH	7.19	5.88	8.98	6.08	5.75
Density (g/ml)	0.999	1.000	1.000	1.000	1.000
TDS (mg/l)					
Cond (μmho/cm)	2100	1600	3100	3500	2300
OH ⁻					
Cl ⁻	72.8	18.5	1100	1013	400
HCO ₃ ⁻					
CO ₃ ⁼					
SO ₄ ⁼					
S ⁼	N.D.	5.5	N.D.	0.5	4.0
NH ₄ -N					
Total Alkalinity as CaCO ₃					
Al					
B					
Ba					
Ca	8.1	N.D.	119	150	9.6
Cr					
Co					
Cu					
Fe	0.57	N.D.	0.31	1.60	0.88
Pb					
Li					
Mg					
Mn					
Ni					
K					
Ag					
Si					
Na	11.6	1.8	34	38	116
Sr					
Sn					
Zn					

Note: All values are ppm unless otherwise indicated.

DATE	1ST STAGE	1ST STAGE	2ND STAGE	2ND STAGE	COMBINED
3-1-79	STEAM IN	STEAM OUT	STEAM IN	STEAM OUT	CONDENSATE
pH	6.64	6.04	9.41	5.99	5.81
Density (g/ml)					
TDS (mg/l)					
Cond (umho/cm)	2500	1650	605	2125	1950
OH ⁻					
Cl ⁻	123	16.5	187	423	515
HCO ₃ ⁻					
CO ₃ ⁼					
SO ₄ ⁼					
S ⁼	N.D.	5.5	N.D.	1.5	4.5
NH ₄ -N					
Total Alkalinity as CaCO ₃					
Al					
B					
Ba					
Ca	5.3	0.1	8.6	68.8	38.0
Cr					
Co					
Cu					
Fe	0.60	0.03	0.05	0.82	0.62
Pb					
Li					
Mg					
Mn					
Ni					
K					
Ag					
Si					
Na	13.5	0.60	23.6	154	72
Sr					
Sn					
Zn					

Note: All values are ppm unless otherwise indicated.

DATE 3-2-79	1ST STAGE STEAM IN	1ST STAGE STEAM OUT	2ND STAGE STEAM IN	2ND STAGE STEAM OUT	COMBINED CONDENSATE
pH	6.77	5.95	9.32	6.11	5.87
Density (g/ml)	0.999	0.999		0.999	0.999
TDS (mg/l)					
Cond (umho/cm)	2350	1570	470	1600	1630
OH ⁻					
Cl ⁻	55.0	14.6	28.2	260	118
HCO ₃ ⁻	1016	1056	379	501	813
CO ₃ ⁼	0	0	200	0	0
SO ₄ ⁼					
S ⁼	N.D.	5.0	N.D.	0.5	3.5
NH ₄ -N	224	214	119	110	163
Total Alkalinity as CaCO ₃	833	866	311	411	666
Al					
B					
Ba					
Ca	14.8	0.23	7.39	44.3	19.9
Cr					
Co					
Cu					
Fe	0.51	0.05	N.D.	0.66	0.51
Pb					
Li					
Mg					
Mn					
Ni					
K					
Ag					
Si					
Na	25.6	1.60	10.3	51.3	46.8
Sr					
Sn					
Zn					

Note: All values are ppm unless otherwise indicated.

DATE 3-3-79	1ST STAGE STEAM IN	1ST STAGE STEAM OUT	2ND STAGE STEAM IN	2ND STAGE STEAM OUT	COMBINED CONDENSATE
pH	7.25	5.85	9.30	5.92	5.69
Density (g/ml)					
TDS (mg/l)					
Cond (umho/cm)					
OH ⁻					
Cl ⁻	39.8	10.7	82.6	1187	432
HCO ₃ ⁻					
CO ₃ ⁼					
SO ₄ ⁼					
S ⁼					
NH ₄ -N					
Total Alkalinity as CaCO ₃					
Al					
B					
Ba					
Ca	6.38	N.D.	5.11	191	85.1
Cr					
Co					
Cu					
Fe	0.87	N.D.	N.D.	1.63	1.05
Pb					
Li					
Mg					
Mn					
Ni					
K					
Ag					
Si					
Na	15.3	2.78	5.56	458	215
Sr					
Sn					
Zn					

Note: All values are ppm unless otherwise indicated.

DATE 3-5-79	1ST STAGE STEAM IN	1ST STAGE STEAM OUT	2ND STAGE STEAM IN	2ND STAGE STEAM OUT	COMBINED CONDENSATE
pH	7.65	5.90	9.38	5.88	5.75
Density (g/ml)	<1.0	<1.0		<1.0	<1.0
TDS (mg/l)					
Cond (μ mho/cm)	2000	1450	540	1650	1680
OH ⁻					
Cl ⁻	50.3	15.8	46.8	278	126
HCO ₃ ⁻	718	1192	0	460	840
CO ₃ ⁼	80	0	240	0	0
SO ₄ ⁼	N.D.	N.D.	N.D.	N.D.	N.D.
S ⁼	N.D.	6.0	N.D.	0.5	4.0
NH ₄ -N	194	216	137	106	167
Total Alkalinity as CaCO ₃	588	977		377	688
Al	N.D.	N.D.	N.D.	N.D.	N.D.
B	7.1	4.0	21.5	3.3	3.8
Ba	N.D.	N.D.	N.D.	N.D.	N.D.
Ca	7.9	0.24	4.8	47.6	23.8
Cr	N.D.	N.D.	N.D.	N.D.	N.D.
Co					
Cu	N.D.	N.D.	N.D.	N.D.	N.D.
Fe	0.28	N.D.	N.D.	0.64	0.50
Pb	N.D.	N.D.	N.D.	N.D.	N.D.
Li	0.06	N.D.	0.02	0.39	0.16
Mg	N.D.	N.D.	0.06	0.17	0.06
Mn	0.10	N.D.	0.03	0.78	0.36
Ni	N.D.	N.D.	N.D.	N.D.	N.D.
K	2.7	N.D.	1.60	8.50	3.75
Ag	N.D.	N.D.	N.D.	N.D.	N.D.
Si	N.D.	N.D.	N.D.	N.D.	N.D.
Na	14.7	0.63	11.1	101	50
Sr	N.D.	N.D.	0.09	0.77	0.30
Sn	N.D.	N.D.	N.D.	N.D.	N.D.
Zn					

Note: All values are ppm unless otherwise indicated.

DATE	1ST STAGE	1ST STAGE	2ND STAGE	2ND STAGE	COMBINED
3-16-79	STEAM IN	STEAM OUT	STEAM IN	STEAM OUT	CONDENSATE
pH	7.37	5.81	8.74	5.97	5.64
Density (g/ml)	<1.0	<1.0	1.0010	1.000	<1.0
TDS (mg/l)					
Cond (μmho/cm)	2300	1780	5800	2100	2050
OH ⁻					
Cl ⁻	97.6	14.8	2542	360	232
HCO ₃ ⁻	948	1042	352	460	745
CO ₃ ⁼	0	0	173	0	0
SO ₄ ⁼	N.D.	1.6	N.D.	N.D.	N.D.
S ⁼	N.D.	6.0	N.D.	0.5	3.5
NH ₄ -N	204	213	160	110	155
Total Alkalinity as CaCO ₃	777	855	289	377	611
Al					
B	7.9	5.1	8.0	4.1	4.6
Ba	N.D.	N.D.	1.50	N.D.	N.D.
Ca	16.1	0.33	444	57.8	40.0
Cr					
Co					
Cu					
Fe	0.30	0.04	0.97	0.76	1.14
Pb	N.D.	N.D.	N.D.	N.D.	N.D.
Li	0.11	N.D.	2.93	0.46	0.26
Mg	N.D.	N.D.	1.70	0.20	0.15
Mn	0.24	0.02	5.29	0.99	0.71
Ni					
K	8.15	0.30	37.0	17.8	18.5
Ag					
Si	N.D.	N.D.	1.60	N.D.	N.D.
Na	37.5	3.13	1422	100	50.0
Sr	0.24	N.D.	6.76	0.98	0.51
Sn					
Zn	N.D.	N.D.	0.13	N.D.	N.D.

Note: All values are ppm unless otherwise indicated.

DATE 3-19-79	1ST STAGE STEAM IN	1ST STAGE STEAM OUT	2ND STAGE STEAM IN	2ND STAGE STEAM OUT	COMBINED CONDENSATE
pH	7.29	6.12		6.36	5.85
Density (g/ml)	1.000	0.999		0.999	0.999
TDS (mg/l)					
Cond (umho/cm)	2300	1730		1830	1800
OH ⁻					
Cl ⁻	76	8.9		420	180
HCO ₃ ⁻	1239	961		460	758
CO ₃ ⁼	0	0		0	0
SO ₄ ⁼	N.D.	N.D.		N.D.	N.D.
S ⁼	N.D.	4.5		1.0	3.5
NH ₄ -N	216	225		113	163
Total Alkalinity as CaCO ₃	1016	788		377	622
Al					
B	7.4	5.1		2.5	2.8
Ba	N.D.	N.D.	N.D.	0.53	N.D.
Ca	13.6	0.65	29.9	76.1	32.6
Cr					
Co					
Cu					
Fe	0.38	0.06	0.09	0.94	0.85
Pb	N.D.	N.D.	N.D.	N.D.	N.D.
Li	0.11	N.D.	0.35	0.62	0.22
Mg	0.10	N.D.	0.34	0.29	0.15
Mn	0.23	0.03	0.16	1.43	0.61
Ni					
K	5.0	N.D.	17.5	38.3	13.3
Ag					
Si	N.D.	N.D.	N.D.	N.D.	N.D.
Na	23.9	2.50	78.6	168	80.4
Sr	0.16	N.D.	0.47	1.12	0.36
Sn					
Zn					

Note: All values are ppm unless otherwise indicated.

APPENDIX B

DATE 1-22-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	4.63	5.60	5.63	5.27
Density (g/ml)	1.1210	1.1360	1.1640	1.1630
TDS (mg/l)	202,920	252,560	278,780	272,100
Cond (μ mho/cm)	290,000	350,000	385,000	385,000
OH ⁻				
Cl ⁻	104,400	116,800	146,600	144,100
HCO ₃ ⁻	283	61	67	78
CO ₃ ⁼	0	0	0	0
SO ₄ ⁼	64	23	1	23
S ⁼				
NH ₄ -N	301	331	394	363
Total Alkalinity as CaCO ₃	233	50	55	64
Al	0.81	0.81	0.81	0.81
B	210	260	300	310
Ba	107	128	149	185
Ca	16,700	20,200	25,000	27,400
Cr	0.79	0.93	0.93	0.93
Co	1.31	2.30	2.50	2.38
Cu	0.58	1.36	1.38	1.36
Fe	152	212	247	265
Pb	24.7	54.5	61.0	59.7
Li	235	167	191	197
Mg	87.3	95.2	107	111
Mn	498	668	773	825
Ni	1.82	2.37	2.83	2.78
K	8,280	10,200	12,400	13,100
Ag	0.35	0.40	0.40	0.44
Si	163	217	253	247
Na	34,500	44,400	50,700	51,400
Sr	309	386	447	457
Sn				
Zn	196	252	299	304

Note: All values are ppm unless otherwise indicated.

DATE 1-24-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	4.97	5.67	5.71	5.34
Density (g/ml)				
TDS (mg/l)				
Cond (μmho/cm)	280,000	345,000	390,000	365,000
OH ⁻				
Cl ⁻	101,900	134,200	146,600	194,100
HCO ₃ ⁻				
CO ₃ ⁼				
SO ₄ ⁼				
S ⁼				
NH ₄ -N				
Total Alkalinity as CaCO ₃				
Al				
B				
Ba	93	131	140	187
Ca	18,000	22,000	26,000	26,000
Cr				
Co				
Cu				
Fe	164	208	223	215
Pb	32.8	54.0	60.7	62.3
Li	138	167	187	189
Mg	77	97	106	109
Mn	580	720	800	820
Ni				
K	7,890	10,500	13,200	11,600
Ag				
Si	167	220	226	220
Na	35,700	48,600	50,000	49,000
Sr	328	400	443	445
Sn				
Zn	216	276	310	306

Note: All values are ppm unless otherwise indicated.

DATE 1-29-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	4.83	5.66	6.02	5.75
Density (g/ml)	1.1010	1.1510	1.1460	1.1530
TDS (mg/l)				
Cond (μ mho/cm)	265,000	340,000	355,000	350,000
OH ⁻				
Cl ⁻	94,400	131,700	129,200	134,200
HCO ₃ ⁻	417	61	89	89
CO ₃ ⁼				
SO ₄ ⁼	50	28	43	53
S ⁼				
NH ₄ -N	286	315	305	325
Total Alkalinity as CaCO ₃	342	50	73	73
Al	1.44	1.80	2.16	2.16
B	287	351	399	383
Ba	78.5	151	177	183
Ca	17,900	21,400	25,000	23,800
Cr	0.27	0.41	0.41	0.36
Co	2.00	2.67	2.94	3.17
Cu	0.50	1.03	1.23	2.11
Fe	167	255	301	291
Pb	24.4	56.4	60.3	65.4
Li	122	184	204	179
Mg	66.7	100	108	104
Mn	544	789	895	877
Ni	2.13	2.50	2.82	2.98
K	5,830	9,170	11,700	10,000
Ag	0.21	0.32	0.33	0.33
Si	152	234	277	26.
Na	29,600	43,400	48,700	42,800
Sr	292	431	485	438
Sn	22.8	30.4	35.0	29.7
Zn	175	274	307	302

Note: All values are ppm unless otherwise indicated.

DATE 1-31-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	4.83	5.72	5.86	5.30
Density (g/ml)	1.1320	1.1480	1.1670	1.1670
TDS (mg/l)				
Cond (umho/cm)	300,000	345,000	380,000	380,000
OH ⁻				
Cl ⁻	110,200	126,900	141,300	141,300
HCO ₃ ⁻	255	61	89	100
CO ₃ ⁼				
SO ₄ ⁼	93	67	67	73
S ⁼				
NH ₄ -N				
Total Alkalinity as CaCO ₃	210	50	73	82
Al				
B	443	508	443	393
Ba	133	148	163	163
Ca	22,600	26,200	29,800	26,200
Cr				
Co				
Cu				
Fe	245	261	327	308
Pb	46.5	54.9	63.4	62.0
Li	159	171	206	187
Mg	87.5	95.8	121	117
Mn	694	774	952	903
Ni				
K	9,290	10,000	12,100	11,400
Ag				
Si	212	276	314	282
Na	40,400	46,300	51,500	47,100
Sr	371	398	480	457
Sn				
Zn	235	265	289	284

Note: All values are ppm unless otherwise indicated.

DATE 2-21-78	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	4.76	5.57	5.65	5.20
Density (g/ml)	1.1240	1.1490	1.1660	1.1660
TDS (mg/l)				
Cond (μmho/cm)	305,000	360,000	400,000	405,000
OH ⁻				
Cl ⁻	104,400	128,700	140,800	143,300
HCO ₃ ⁻	245	44.5	44.5	78.0
CO ₃ ⁼				
SO ₄ ⁼	73	73	87	80
S ⁼				
NH ₄ -N	319	336	354	358
Total Alkalinity as CaCO ₃	201	36.5	36.5	64
Al	1.04	1.04	2.78	N.D.
B	232	319	82	349
Ba	153	159	6.38	166
Ca	25,600	23,300	5,800	24,400
Cr	0.58	0.58	0.34	0.63
Co	2.89	3.02	0.73	3.10
Cu	0.65	1.22	0.22	1.24
Fe	247	285	144	315
Pb	48.4	56.8	7.37	61.1
Li	153	173	42.7	188
Mg	78.0	96.3	55.0	101
Mn	715	799	210	883
Ni	3.11	3.42	2.11	3.74
K	9,700	11,500	3,030	12,100
Ag	0.32	0.35	0.11	0.22
Si	211	222	30.9	227
Na	49,200	44,300	13,300	47,500
Sr	366	410	100	456
Sn	43.7	49.4	12.1	55.1
Zn	248	257	54.5	282

Note: All values are ppm unless otherwise indicated.

DATE 2-23-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH		5.58	5.77	5.22
Density (g/ml)		1.156	1.168	1.167
TDS (mg/l)	Sample Line Plugged			
Cond (μ mho/cm)		365,000	420,000	410,000
OH ⁻				
Cl ⁻		131,100	145,700	143,300
HCO ₃ ⁻				
CO ₃ ⁼				
SO ₄ ⁼		85	80	80
S ⁼				
NH ₄ -N				
Total Alkalinity as CaCO ₃				
Al				
B		341	389	566
Ba		152	170	189
Ca		23,300	27,800	24,400
Cr				
Co				
Cu				
Fe		278	335	313
Pb		58.6	64.3	62.9
Li		180	211	207
Mg		96.8	113	113
Mn		788	922	855
Ni				
K		10,700	12,900	12,900
Ag				
Si		242	264	258
Na		46,100	49,400	46,100
Sr		431	489	481
Sn				
Zn		280	306	328

Note: All values are ppm unless otherwise indicated.

DATE 2-26-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	5.20	5.72	5.84	5.80
Density (g/ml)	1.131	1.155	1.170	1.172
TDS (mg/l)				
Cond (μmho/cm)	283,000	340,000	365,000	360,000
OH ⁻				
Cl ⁻	111,700	133,600	143,300	143,300
HCO ₃ ⁻	267	56	78	78
CO ₃ ⁼				
SO ₄ ⁼	100	80	67	87
S ⁼				
NH ₄ -N	325	340	373	354
Total Alkalinity as CaCO ₃	219	46	64	64
Al	1.32	1.97	1.32	1.97
B	300	400	420	420
Ba	97.4	139	153	153
Ca	18,200	22,700	27,300	31,800
Cr	0.80	0.65	0.87	0.87
Co	3.21	4.03	4.63	4.33
Cu	0.56	1.27	1.34	1.41
Fe	213	263	288	288
Pb	54.8	5.48	58.1	58.1
Li	131	176	199	199
Mg	75.8	90.9	101	111
Mn	567	733	850	900
Ni	2.80	2.87	2.93	3.07
K	8,000	11,000	13,000	13,000
Ag	0.41	0.56	0.53	0.38
Si	158	225	250	250
Na	33,300	44,100	50,000	55,900
Sr	313	405	443	459
Sn	21.2	22.7	27.3	32.0
Zn	218	176	329	312

Note: All values are ppm unless otherwise indicated.

DATE 2-28-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	5.36	5.55	5.68	5.23
Density (g/ml)	1.1615	1.1525	1.1710	1.1720
TDS (mg/l)	276,650	256,040	315,000	340,000
Cond (μ mho/cm)				
OH ⁻				
Cl ⁻	145,700	138,400	155,400	143,300
HCO ₃ ⁻				
CO ₃ ⁼				
SO ₄ ⁼	86	79	71	77
S ⁼				
NH ₄ -N				
Total Alkalinity as CaCO ₃				
Al				
B				
Ba	167	161	167	189
Ca	28,300	23,200	29,300	21,200
Cr				
Co				
Cu				
Fe	320	309	356	314
Pb	57	54	60	57
Li	197	176	200	183
Mg	116	103	119	103
Mn	903	796	956	850
Ni				
K	14,100	11,900	14,600	12,400
Ag				
Si	211	211	234	203
Na	54,600	77,800	70,400	50,900
Sr	472	424	487	435
Sn				
Zn	295	288	330	313

Note: All values are ppm unless otherwise indicated.

DATE 3-2-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	5.55	5.58	5.75	5.35
Density (g/ml)	1.1550	1.1500	1.1700	1.1640
TDS (mg/l)				
Cond (μ mho/cm)	360,000	355,000	375,000	390,000
OH ⁻				
Cl ⁻	138,400	131,100	140,800	142,000
HCO ₃ ⁻	60	54	81	92
CO ₃ ⁼				
SO ₄ ⁼	93	88	88	97
S ⁼				
NH ₄ -N	325	329	347	354
Total Alkalinity as CaCO ₃	49	44	67	75
Al				
B				
Ba	178	153	147	165
Ca	26,100	23,900	27,300	28,400
Cr				
Co				
Cu				
Fe	281	291	327	342
Pb	61.3	60.0	56.3	66.3
Li	182	177	182	201
Mg	100	92.9	104	104
Mn	835	801	852	920
Ni				
K	12,700	11,300	13,300	14,700
Ag				
Si	256	250	220	262
Na	47,400	44,900	49,400	50,600
Sr	433	422	440	472
Sn				
Zn	310	301	306	324

Note: All values are ppm unless otherwise indicated.

DATE 3-5-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	5.53	5.62	5.70	5.37
Density (g/ml)	1.1555	1.1530	1.1725	1.1665
TDS (mg/l)				
Cond (μmho/cm)	340,000	342,500	365,000	375,000
OH ⁻				
Cl ⁻	145,700	138,400	150,600	155,400
HCO ₃ ⁻	87	43	49	70
CO ₃ ⁼				
SO ₄ ⁼	86	79	83	80
S ⁼				
NH ₄ -N	342	331	358	354
Total Alkalinity as CaCO ₃	71	36	40	58
Al	0.96	0.64	0.96	0.64
B	360	330	385	352
Ba	174	145	166	172
Ca	25,400	22,500	25,900	25,900
Cr	0.36	0.36	0.39	0.33
Co	7.0	6.0	6.0	6.0
Cu	0.86	1.52	1.52	1.44
Fe	257	255	305	294
Pb	67.7	54.2	64.6	64.6
Li	197	182	202	202
Mg	86.2	77.6	89.1	89.1
Mn	864	778	892	881
Ni	3.90	2.70	2.40	3.90
K	12,500	11,000	13,000	13,000
Ag	0.30	0.30	0.30	0.30
Si	238	226	250	237
Na	50,000	44,100	50,000	50,000
Sr	444	402	463	452
Sn	51.9	43.4	49.1	53.3
Zn	313	278	319	313

Note: All values are ppm unless otherwise indicated.

DATE 3-16-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	5.27	5.62	5.59	5.19
Density (g/ml)	1.1620	1.1555	1.1710	1.1650
TDS (mg/l)				
Cond (μmho/cm)	252,500	260,000	305,000	325,000
OH ⁻				
Cl ⁻	139,600	131,100	143,300	143,300
HCO ₃ ⁻	60	70	65	108
CO ₃ ⁼				
SO ₄ ⁼	94	88	84	101
S ⁼				
NH ₄ ^{-N}	351	336	351	306
Total Alkalinity as CaCO ₃	49	58	53	89
Al	0.93	0.93	0.93	0.62
B	425	410	475	460
Ba	195	180	195	195
Ca	25,600	23,300	27,800	31,100
Cr	0.38	0.44	0.55	0.49
Co	2.90	3.00	3.20	3.25
Cu	0.63	1.15	1.18	0.43
Fe	275	280	335	335
Pb	55.6	51.9	61.1	61.1
Li	186	174	200	200
Mg	95.0	90.0	100	100
Mn	882	838	916	926
Ni	3.10	3.04	2.78	304
K	11,900	11,100	13,300	13,300
Ag	0.44	0.56	0.47	0.40
Si	229	218	245	229
Na	51,900	46,300	50,700	50,000
Sr	453	432	490	486
Sn	50.0	45.2	42.9	46.4
Zn	299	279	312	325

Note: All values are ppm unless otherwise indicated.

DATE 3-19-79	WOOLSEY NO. 1	1A BRINE OUT	2A BRINE OUT	INJECTION
pH	5.65	5.67		5.22
Density (g/ml)	1.1655	1.1525		1.1625
TDS (mg/l)				
Cond (μmho/cm)	352,500	315,000		325,000
OH ⁻				
Cl ⁻	139,600	134,800		142,100
HCO ₃ ⁻	60	76		62
CO ₃ ⁼				
SO ₄ ⁼	80	82	88	79
S ⁼				
NH ₄ -N	333	329		349
Total Alkalinity as CaCO ₃	49	62		51
Al	1.17	1.17	1.56	1.17
B	250	250	260	230
Ba	184	158	158	171
Ca	27,200	27,200	28,300	29,300
Cr	0.91	0.91	0.86	0.91
Co	4.56	4.50	4.78	5.44
Cu	1.09	1.37	0.87	1.41
Fe	279	294	303	309
Pb	59.5	60.8	67.1	65.8
Li	181	185	199	192
Mg	88.2	83.3	98.0	103
Mn	814	843	929	900
Ni	3.51	3.31	3.27	3.81
K	11,700	10,000	11,700	12,500
Ag	0.62	0.62	0.51	0.31
Si	244	238	159	256
Na	45,700	45,000	46,400	48,600
Sr	422	422	448	433
Sn	68.2	61.2	70.6	64.7
Zn	309	281	320	309

Note: All values are ppm unless otherwise indicated.

APPENDIX C

DATE 1-22-79	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
pH	9.10	7.62	7.64
Density (g/ml)	1.000	1.002	1.002
TDS (mg/l)	200	1944	1922
Cond (μ mho/cm)	1460	3130	3200
OH ⁻			
Cl ⁻	26	682	673
HCO ₃ ⁻	334	150	278
CO ₃ ⁼	520		
SO ₄ ⁼	36	400	430
S ⁼	N.D.	N.D.	N.D.
NH ₄ -N	164	204	204
Total Alkalinity as CaCO ₃	274	205	228
Al	N.D.	N.D.	N.D.
B	0.4	5.4	5.2
Ba	N.D.	N.D.	N.D.
Ca	N.D.	119	119
Cr			
Co			
Cu			
Fe	0.08	4.75	4.80
Pb	N.D.	N.D.	N.D.
Li	N.D.	0.46	0.46
Mg	0.08	38.7	39.7
Mn	N.D.	1.00	1.00
Ni			
K	0.28	62.1	65.5
Ag			
Si	N.D.	36.1	36.1
Na	7.75	345	310
Sr	N.D.	0.97	0.99
Sn			
Zn	N.D.	0.28	0.28

Note: All values are ppm unless otherwise indicated.

DATE 1-24-79	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
pH	9.08	7.73	7.71
Density (g/ml)			
TDS (mg/l)			
Cond ($\mu\text{mho/cm}$)	1400	2800	2800
OH^-			
Cl^-	26	576	576
HCO_3^-			
$\text{CO}_3^{=}$			
$\text{SO}_4^{=}$			
$\text{S}^{=}$	N.D.	N.D.	N.D.
$\text{NH}_4\text{-N}$			
Total Alkalinity as CaCO_3			
Al			
B			
Ba			
Ca	0.6	120	120
Cr			
Co			
Cu			
Fe	0.15	4.4	4.4
Pb			
Li			
Mg			
Mn			
Ni			
K	N.D.	53.0	47.0
Ag			
Si			
Na	6.8	302	305
Sr			
Sn			
Zn			

Note: All values are ppm unless otherwise indicated.

DATE 1-29-79	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
pH	9.15	7.60	7.60
Density (g/ml)	1.0000	1.0005	1.0005
TDS (mg/l)			
Cond (μ mho/cm)	1450	2750	2800
OH ⁻			
Cl ⁻	26	590	595
HCO ₃ ⁻	445	278	278
CO ₃ ⁼	465		
SO ₄ ⁼	23	400	433
S ⁼	N.D.	N.D.	N.D.
NH ₄ -N		85.8	87.8
Total Alkalinity as CaCO ₃	365	228	228
Al			
B	0.6	5.1	5.3
Ba	N.D.	N.D.	N.D.
Ca	1.19	143	143
Cr			
Co			
Cu			
Fe	0.13	3.30	3.30
Pb	N.D.	N.D.	N.D.
Li	N.D.	0.42	0.42
Mg	0.13	40.6	40.6
Mn	N.D.	0.82	0.82
Ni			
K	N.D.	41.7	41.7
Ag			
Si	N.D.	19.6	19.6
Na	7.24	276	309
Sr	N.D.	1.26	1.29
Sn			
Zn	N.D.	0.19	0.09

Note: All values are ppm unless otherwise indicated.

DATE	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
1-31-79			
pH	9.18	7.67	7.67
Density (g/ml)	1.0000	1.0005	1.0005
TDS (mg/l)			
Cond (μ mho/cm)	1400	2900	2900
OH ⁻			
Cl ⁻	24	580	576
HCO ₃ ⁻	598	362	362
CO ₃ ⁼	397		
SO ₄ ⁼		400	400
S ⁼	N.D.	N.D.	N.D.
NH ₄ -N			
Total Alkalinity as CaCO ₃	490	296	296
Al			
B	0.3	5.1	5.2
Ba			
Ca	0.24	143	143
Cr			
Co			
Cu			
Fe	0.06	2.80	2.77
Pb			
Li			
Mg			
Mn			
Ni			
K			
Ag			
Si			
Na	5.88	257	257
Sr			
Sn			
Zn			

Note: All values are ppm unless otherwise indicated.

DATE 2-21-79	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
pH	8.80	7.72	7.66
Density (g/ml)	0.9990	1.0000	1.0000
TDS (mg/l)			
Cond (μmho/cm)	1320	3200	3200
OH ⁻			
Cl ⁻	26	605	600
HCO ₃ ⁻	946	348	306
CO ₃ ⁼	164		
SO ₄ ⁼	20	450	450
S ⁼	N.D.	N.D.	N.D.
NH ₄ -N		77	77
Total Alkalinity as CaCO ₃	775	285	281
Al			
B	0.8	4.3	4.3
Ba	N.D.	N.D.	N.D.
Ca	0.58	128	128
Cr			
Co			
Cu			
Fe	0.24	2.94	2.85
Pb	N.D.	N.D.	N.D.
Li	N.D.	0.39	0.39
Mg	N.D.	10.3	9.17
Mn	N.D.	0.98	0.97
Ni			
K	N.D.	12.1	12.1
Ag			
Si	N.D.	13.7	12.6
Na	5.06	323	316
Sr	N.D.	1.56	1.56
Sn			
Zn	N.D.	N.D.	N.D.

Note: All values are ppm unless otherwise indicated.

DATE
2-23-79

BINARY

COOLING WATER
FROM POND
TO CONDENSERS

COOLING WATER
FROM CONDENSERS
TO POND

pH	9.00	7.70	7.70
Density (g/ml)	0.9990	1.0000	1.0000
TDS (mg/l)			
Cond (μmho/cm)	1640	3250	3250
OH ⁻			
Cl ⁻	26	629	634
HCO ₃ ⁻			
CO ₃ ⁼			
SO ₄ ⁼	13	467	467
S ⁼	N.D.	N.D.	N.D.
NH ₄ -N			
Total Alkalinity as CaCO ₃			
Al			
B			
Ba			
Ca	0.22	122	122
Cr			
Co			
Cu			
Fe	0.28	3.39	3.32
Pb			
Li			
Mg			
Mn			
Ni			
K			
Ag			
Si			
Na	2.53	275	275
Sr			
Sn			
Zn			

Note: All values are ppm unless otherwise indicated.

DATE	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
2-26-79			
pH	8.90	7.81	7.76
Density (g/ml)	1.0100	1.0000	1.0000
TDS (mg/l)			
Cond (μ mho/cm)	1500	2900	3100
OH ⁻			
Cl ⁻	26	634	638
HCO ₃ ⁻	1071	375	389
CO ₃ ⁼	164		
SO ₄ ⁼	8.7	483	467
S ⁼	N.D.	N.D.	N.D.
NH ₄ -N		96.0	90.0
Total Alkalinity as CaCO ₃	877	308	319
Al			
B	0.5	5.5	5.5
Ba	N.D.	N.D.	N.D.
Ca	0.15	136	121
Cr			
Co			
Cu			
Fe	N.D.	2.84	2.84
Pb	N.D.	N.D.	N.D.
Li	N.D.	0.43	0.44
Mg	N.D.	41.7	40.4
Mn	N.D.	0.92	0.93
Ni			
K	0.4	50.0	50.0
Ag			
Si	N.D.	11.7	12.5
Na	1.47	304	314
Sr	N.D.	1.46	1.46
Sn			
Zn	N.D.	N.D.	N.D.

Note: All values are ppm unless otherwise indicated.

DATE 2-27-79	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
pH		7.67	7.68
Density (g/ml)			
TDS (mg/l)			
Cond ($\mu\text{mho/cm}$)			
OH^-			
Cl^-			
HCO_3^-			
$\text{CO}_3^{=}$			
$\text{SO}_4^{=}$		500	500
$\text{S}^{=}$			
$\text{NH}_4\text{-N}$			
Total Alkalinity as CaCO_3			
Al			
B			
Ba			
Ca		1.70	159
Cr			
Co			
Cu			
Fe		4.4	4.4
Pb			
Li			
Mg			
Mn			
Ni			
K			
Ag			
Si			
Na		323	323
Sr			
Sn			
Zn			

Note: All values are ppm unless otherwise indicated.

DATE	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
2-28-79			
pH	8.80	7.63	7.63
Density (g/ml)	1.0000	1.0100	1.0005
TDS (mg/l)			
Cond ($\mu\text{mho/cm}$)	1400	3000	2950
OH^-			
Cl^-	24.3	682	682
HCO_3^-			
$\text{CO}_3^{=}$			
$\text{SO}_4^{=}$		500	500
$\text{S}^{=}$			
$\text{NH}_4\text{-N}$			
Total Alkalinity as CaCO_3			
Al			
B			
Ba			
Ca	0.20	111	121
Cr			
Co			
Cu			
Fe	0.36	4.2	4.2
Pb			
Li			
Mg			
Mn			
Ni			
K			
Ag			
Si			
Na	2.10	300	305
Sr			
Sn			
Zn			

Note: All values are ppm unless otherwise indicated.

DATE
3-1-79

BINARY

COOLING WATER
FROM POND
TO CONDENSERS

COOLING WATER
FROM CONDENSERS
TO POND

pH	7.70	7.71
Density (g/ml)		
TDS (mg/l)		
Cond ($\mu\text{mho/cm}$)	3225	3050
OH^-		
Cl^-		
HCO_3^-		
$\text{CO}_3^{=}$		
$\text{SO}_4^{=}$	494	494
$\text{S}^{=}$		
$\text{NH}_4\text{-N}$		
Total Alkalinity as CaCO_3		
Al		
B		
Ba		
Ca	80	80
Cr		
Co		
Cu		
Fe	3.60	3.60
Pb		
Li		
Mg		
Mn		
Ni		
K		
Ag		
Si		
Na	288	288
Sr		
Sn		
Zn		

Note: All values are ppm unless otherwise indicated.

DATE	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
3-2-79			
pH	8.79	7.71	7.71
Density (g/ml)	1.0000	1.0000	1.0000
TDS (mg/l)			
Cond (μ mho/cm)	1520	3100	3150
OH ⁻			
Cl ⁻	30	706	697
HCO ₃ ⁻	961	406	392
CO ₃ ⁼	173		
SO ₄ ⁼		511	511
S ⁼	N.D.	N.D.	N.D.
NH ₄ -N		96.7	96.0
Total Alkalinity as CaCO ₃	788	333	321
Al			
B			
Ba			
Ca	0.34	148	148
Cr			
Co			
Cu			
Fe	0.15	3.37	3.47
Pb			
Li			
Mg			
Mn			
Ni			
K			
Ag			
Si			
Na	1.60	372	378
Sr			
Sn			
Zn			

Note: All values are ppm unless otherwise indicated.

DATE 3-5-79	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
pH	8.82	7.77	7.75
Density (g/ml)			
TDS (mg/l)			
Cond ($\mu\text{mho/cm}$)	1470	2820	3400
OH^-			
Cl^-	26.6	742	732
HCO_3^-			
$\text{CO}_3^{=}$			
$\text{SO}_4^{=}$	0.5	525	543
$\text{S}^{=}$	N.D.	N.D.	N.D.
$\text{NH}_4\text{-N}$		105	104
Total Alkalinity as CaCO_3			
Al		1.9	2.2
B	0.4	6.2	6.2
Ba	N.D.	N.D.	N.D.
Ca	0.3	111	111
Cr			
Co			
Cu			
Fe	0.14	3.55	3.60
Pb	N.D.	N.D.	N.D.
Li	N.D.	0.53	0.53
Mg	N.D.	44	44
Mn	N.D.	1.10	1.10
Ni			
K	N.D.	25	25
Ag			
Si			
Na	0.56	333	325
Sr	N.D.	1.80	1.80
Sn			
Zn	N.D.	0.14	0.14

Note: All values are ppm unless otherwise indicated.

DATE 3-16-79	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
pH	8.48	7.44	7.46
Density (g/ml)			
TDS (mg/l)			
Cond ($\mu\text{mho/cm}$)	1800	2550	2800
OH^-			
Cl^-	35	670	670
HCO_3^-	500	257	244
$\text{CO}_3^{=}$	173		
$\text{SO}_4^{=}$		563	563
$\text{S}^{=}$			
$\text{NH}_4\text{-N}$		63	61
Total Alkalinity as CaCO_3	410	211	200
Al			
B	1.3	6.2	6.2
Ba	N.D.	N.D.	N.D.
Ca	0.89	156	156
Cr			
Co			
Cu			
Fe	0.55	3.01	2.97
Pb	N.D.	N.D.	N.D.
Li	N.D.	0.40	0.40
Mg	N.D.	45.5	45.0
Mn	0.02	0.93	0.93
Ni			
K	1.04	48.1	48.1
Ag			
Si	N.D.	12.8	12.8
Na	11.9	375	375
Sr	N.D.	1.89	1.96
Sn			
Zn	N.D.	0.13	0.13

Note: All values are ppm unless otherwise indicated.

DATE 3-19-79	BINARY	COOLING WATER FROM POND TO CONDENSERS	COOLING WATER FROM CONDENSERS TO POND
pH	8.81	7.71	7.84
Density (g/ml)	1.0000	1.0000	1.0000
TDS (mg/l)			
Cond (μ mho/cm)	1500	2950	3000
OH ⁻			
Cl ⁻	28.9	729	707
HCO ₃ ⁻	975	284	285
CO ₃ ⁼	173		
SO ₄ ⁼	32	578	578
S ⁼	N.D.	N.D.	N.D.
NH ₄ -N		69	67
Total Alkalinity as CaCO ₃	799	233	233
Al			
B	1.0	6.2	6.2
Ba	N.D.	N.D.	N.D.
Ca	0.76	163	163
Cr			
Co			
Cu			
Fe	0.24	2.82	2.82
Pb	N.D.	N.D.	N.D.
Li	N.D.	0.49	0.49
Mg	0.10	45.3	45.3
Mn	N.D.	1.11	1.09
Ni			
K	N.D.	45.8	50.0
Ag			
Si	N.D.	12.2	12.2
Na	6.07	429	429
Sr	N.D.	1.84	1.84
Sn			
Zn	N.D.	0.22	0.22

Note: All values are ppm unless otherwise indicated.

APPENDIX D

PRODUCTION LINE AT "T" NEAR LLL 60 FT FROM WELLHEAD DATE: 1-19-79

Wt. %	% Fraction	% Total Scale
Al - 2.76	Water Soluble - 16.2	CaCl ₂ - 1.05
Ba - 0.00	CaCl ₂ - 6.5	FeCl ₂ - 0.26
Ca - 0.23	FeCl ₂ - 1.6	MgCl ₂ - 0.26
Cr - 0.01	MgCl ₂ - 1.6	MnCl ₂ - 0.26
Co - 0.01	MnCl ₂ - 1.6	KCl - 1.57
Cu - 0.02	KCl - 9.7	NaCl - 12.80
Fe - 3.11	NaCl - 79.0	Al ₂ S ₃ - 9.70
Pb - 32.33		Ca(OH) ₂ - 0.31
Li - 0.01		CuO - 0.06
Mg - 0.14		FeS - 5.83
Mn - 0.07	Acid Soluble - 61.4	PbS - 43.30
Ni - 0.02	Al ₂ S ₃ - 15.8	Li ₂ SiO ₃ - 0.06
K - 0.20	Ca(OH) ₂ - 0.5	Mg(OH) ₂ - 0.25
Si - 7.45	CuS - 0.1	Mn(OH) ₂ - 0.12
Ag - 0.40	FeS - 9.5	K ₂ SiO ₃ - 0.37
Na - 0.32	PbS - 70.5	AgCl - 0.74
Sr - 0.00	Li ₂ SiO ₃ - 0.1	Na ₂ SiO ₃ - 0.49
Sn - 0.18	Mg(OH) ₂ - 0.4	ZnS - 0.18
Zn - 0.16	Mn(OH) ₂ - 0.2	Al ₂ O ₃ - 0.54
	K ₂ SiO ₃ - 0.6	CaSiO ₃ - 0.25
	AgCl - 1.2	CrO - 0.02
	Na ₂ SiO ₃ - 0.8	CoS - 0.02
	ZnS - 0.3	CuO - 0.02
		Fe ₃ O ₄ - 0.16
		PbO - 7.66
		MgSiO ₃ - 0.09
	Acid Insoluble - 22.4	NiS - 0.02
	Al ₂ O ₃ - 2.4	SiO ₂ - 13.23
	CaSiO ₃ - 1.2	Ag ₂ S - 0.02
	CrO - 0.1	SnO - 0.25
	CaS - 0.1	ZnO - 0.11
	CuO - 0.1	
	Fe ₃ O ₄ - 0.7	
	PbO - 34.2	
	MgSiO ₃ - 0.4	
	NiS - 0.1	
	SiO ₂ - 59.0	
	Ag ₂ S - 0.1	
	SnO - 1.1	
	ZnO - 0.5	

1-B SEPARATOR

DATE: 1-12-79

Wt. %	% Fraction	% Total Scale
Al - 0.55	Water Soluble - 29.8	CaCl ₂ - 7.90
Ba - 0.00	CaCl ₂ - 26.5	PbCl ₂ - 0.06
Ca - 1.69	PbCl ₂ - 0.2	LiCl - 0.18
Cr - 0.00	LiCl - 0.6	MgCl ₂ - 0.30
Co - 0.00	MgCl ₂ - 1.0	MnCl ₂ - 0.63
Cu - 0.20	MnCl ₂ - 2.1	KCl - 1.52
Fe - 12.67	KCl - 5.1	NaCl - 19.10
Pb - 15.49	NaCl - 64.1	SrCl ₂ - 0.12
Li - 0.01	SrCl ₂ - 0.4	Al ₂ S ₃ - 0.19
Mg - 0.51		Ca(OH) ₂ - 0.04
Mn - 1.04		CuS - 0.26
Ni - 0.01		Fe ₂ O ₃ - 5.11
K - 0.37	Acid Soluble - 12.9	PbS - 6.31
Si - 11.75	Al ₂ S ₃ - 1.5	Mg(OH) ₂ - 0.25
Ag - 0.13	Ca(OH) ₂ - 0.3	Mn(OH) ₂ - 0.43
Na - 3.44	CuS - 2.0	NiO - 0.01
Sr - 0.03	Fe ₂ O ₃ - 39.6	Na ₂ SiO ₃ - 0.06
Sn - 0.10	PbS - 48.9	Ag ₂ O - 0.10
Zn - 0.26	Mg(OH) ₂ - 1.9	ZnS - 0.14
	Mn(OH) ₂ - 3.3	Al ₂ O ₃ - 0.92
	NiO - 0.1	CaSiO ₃ - 1.09
	Na ₂ SiO ₃ - 0.5	CuO - 0.11
	Ag ₂ O - 0.8	Fe ₃ O ₄ - 14.33
	ZnS - 1.1	PbO - 12.43
		MgSiO ₃ - 1.49
		MnSiO ₃ - 1.60
		SiO ₂ - 24.87
		Ag ₂ S - 0.11
		SnSO ₄ - 0.11
		ZnO - 0.23
	Acid Insoluble - 57.3	
	Al ₂ O ₃ - 1.6	
	CaSiO ₃ - 1.9	
	CuO - 0.2	
	Fe ₃ O ₄ - 25.0	
	PbO - 21.7	
	MgSiO ₃ - 2.6	
	MnSiO ₃ - 2.8	
	SiO ₂ - 43.4	
	Ag ₂ S - 0.2	
	SnSO ₄ - 0.2	
	ZnO - 0.4	

1-B SEPARATOR BRINE (OUT)

DATE: 1-8-79

Wt. %	% Fraction	% Total Scale
Al - 0.64	Water Soluble - 18.0	CaCl ₂ - 2.27
Ba - 0.00	CaCl ₂ - 12.6	CrCl ₂ - 0.04
Ca - 0.57	CrCl ₂ - 0.2	FeCl ₂ - 0.20
Cr - 0.01	FeCl ₂ - 1.1	LiCl - 0.14
Co - 0.02	LiCl - 0.8	MgCl ₂ - 0.52
Cu - 0.74	MgCl ₂ - 2.9	MnCl ₂ - 1.60
Fe - 13.82	MnCl ₂ - 8.9	KCl - 1.19
Pb - 21.62	KCl - 6.6	NaCl - 12.01
Li - 0.01	NaCl - 66.7	SrCl ₂ - 0.04
Mg - 0.34	SrCl ₂ - 0.2	Al ₂ S ₃ - 1.06
Mn - 1.04		Ca(OH) ₂ - 0.20
Ni - 0.02		CuS - 1.12
K - 0.26		Fe ₂ O ₃ - 11.62
Si - 11.57	Acid Soluble - 33.0	PbS - 17.32
Ag - 0.30	Al ₂ S ₃ - 3.2	Mg(OH) ₂ - 0.33
Na - 7.73	Ca(OH) ₂ - 0.6	Mn(OH) ₂ - 0.73
Sr - 0.01	CuS - 3.4	K ₂ SiO ₃ - 0.03
Sn - 0.00	Fe ₂ O ₃ - 35.2	Ag ₂ O - 0.23
Zn - 0.13	PbS - 52.5	Na ₂ SiO ₃ - 0.10
	Mg(OH) ₂ - 1.0	ZnS - 0.26
	Mn(OH) ₂ - 2.2	Al ₂ O ₃ - 0.64
	K ₂ SiO ₃ - 0.1	CaSiO ₃ - 0.49
	Ag ₂ O - 0.7	CoS - 0.05
	Na ₂ SiO ₃ - 0.3	CuO - 0.20
	ZnS - 0.8	Fe ₃ O ₄ - 10.24
		PbO - 14.40
		MgSiO ₃ - 0.49
		MnSiO ₃ - 0.83
		NiO - 0.05
		SiO ₂ - 21.45
		Ag ₂ S - 0.15
	Acid Insoluble - 49.0	
	Al ₂ O ₃ - 1.3	
	CaSiO ₃ - 1.0	
	CoS - 0.1	
	CuO - 0.4	
	Fe ₃ O ₄ - 20.9	
	PbO - 29.4	
	MgSiO ₃ - 1.0	
	MnSiO ₃ - 1.7	
	NiO - 0.1	
	SiO ₂ - 43.8	
	Ag ₂ S - 0.3	

2-B SEPARATOR (TOP)

DATE: 1-12-79

Wt. %	% Fraction	% Total Scale
Al - 0.04	Water Soluble - 11.1	CaCl ₂ - 1.42
Ba - 0.00	CaCl ₂ - 12.8	LiCl - 0.08
Ca - 0.67	LiCl - 0.7	MgCl ₂ - 0.08
Cr - 0.03	MgCl ₂ - 0.7	MnCl ₂ - 0.02
Co - 0.01	MnCl ₂ - 0.2	KCl - 0.53
Cu - 0.04	KCl - 4.8	NaCl - 8.95
Fe - 43.12	NaCl - 80.6	SrCl ₂ - 0.02
Pb - 0.75	SrCl ₂ - 0.2	CaCO ₃ - 0.56
Li - 0.01		CrS - 0.06
Mg - 0.11		CuS - 0.03
Mn - 1.68		FeS - 26.91
Ni - 0.02	Acid Soluble - 30.9	PbS - 0.74
K - 0.11	CaCO ₃ - 1.8	MgCO ₃ - 0.12
Si - 9.95	CrS - 0.2	MnCO ₃ - 1.73
Ag - 0.00	CuS - 0.1	NiCO ₃ - 0.03
Na - 1.37	FeS - 87.1	Na ₂ SiO ₃ - 0.09
Sr - 0.01	PbS - 2.4	ZnS - 0.62
Sn - 0.07	MgCO ₃ - 0.4	Al ₂ O ₃ - 0.06
Zn - 0.59	MnCO ₃ - 5.6	CaSiO ₃ - 0.35
	NiCO ₃ - 0.1	CrO - 0.06
	Na ₂ SiO ₃ - 0.3	Fe ₃ O ₄ - 35.79
	ZnS - 2.0	PbO - 0.12
		MgSiO ₃ - 0.12
		MnSiO ₃ - 1.10
		NiS - 0.06
		SiO ₂ - 20.12
		SnSO ₄ - 0.06
		ZnO - 0.17
	Acid Insoluble - 58.0	
	Al ₂ O ₃ - 0.1	
	CaSiO ₃ - 0.6	
	CrO - 0.1	
	Fe ₃ O ₄ - 61.7	
	PbO - 0.2	
	MgSiO ₃ - 0.2	
	MnSiO ₃ - 1.9	
	NiS - 0.1	
	SiO ₂ - 34.7	
	SnSO ₄ - 0.1	
	ZnO - 0.3	

2-B SEPARATOR (BOTTOM)

DATE: 1-12-79

Wt. %

% Fraction

% Total Scale

Al - 0.04
 Ba - 0.00
 Ca - 1.25
 Cr - 0.00
 Co - 0.00
 Cu - 0.10
 Fe - 0.90
 Pb - 0.84
 Li - 0.01
 Mg - 0.04
 Mn - 0.13
 Ni - 0.00
 K - 0.33
 Si - 32.73
 Ag - 0.02
 Na - 2.71
 Sr - 0.04
 Sn - 0.15
 Zn - 0.10

Water Soluble - 23.4
 CaCl₂ - 28.9
 LiCl - 0.8
 MgCl₂ - 0.3
 MnCl₂ - 1.4
 KCl - 5.6
 NaCl - 62.3
 SrCl₂ - 0.6
 ZnCl₂ - 0.1

Acid Soluble - 4.6
 Ca(OH)₂ - 1.8
 CuS - 5.5
 FeS - 40.4
 PbS - 36.7
 Mg(OH)₂ - 0.9
 Mn(OH)₂ - 3.7
 Na₂SiO₃ - 4.6
 ZnS - 6.4

Acid Insoluble - 72.0
 Al₂O₃ - 0.1
 CaSiO₃ - 0.3
 CuO - 0.1
 Fe₃O₄ - 1.1
 PbO - 0.7
 MgSiO₃ - 0.2
 MnSiO₃ - 0.1
 SiO₂ - 97.0
 Ag₂S - 0.1
 SnSO₄ - 0.2
 ZnO - 0.1

CaCl₂ - 6.76
 LiCl - 0.19
 MgCl₂ - 0.07
 MnCl₂ - 0.33
 KCl - 1.31
 NaCl - 14.59
 SrCl₂ - 0.14
 ZnCl₂ - 0.02
 Ca(OH)₂ - 0.08
 CuS - 0.25
 FeS - 1.87
 PbS - 1.69
 Mg(OH)₂ - 0.04
 Mn(OH)₂ - 0.17
 Na₂SiO₃ - 0.21
 ZnS - 0.29
 Al₂O₃ - 0.07
 CaSiO₃ - 0.22
 CuO - 0.07
 Fe₃O₄ - 0.79
 PbO - 0.50
 MgSiO₃ - 0.14
 MnSiO₃ - 0.07
 SiO₂ - 69.85
 Ag₂S - 0.07
 SnSO₄ - 0.14
 ZnO - 0.07

SCALE FROM LINE ENTERING RED VALVE
BETWEEN 2B SEPARATOR AND ATMOSPHERIC FLASH
DATE: 1-12-79

Wt. %	% Fraction	% Total Scale
Al - 0.05	Water Soluble - 25.5	CaCl ₂ - 7.22
Ba - 0.00	CaCl ₂ - 28.3	PbCl ₂ - 0.03
Ca - 0.61	PbCl ₂ - 0.1	LiCl - 0.18
Cr - 0.00	LiCl - 0.7	MgCl ₂ - 0.05
Co - 0.00	MgCl ₂ - 0.2	MnCl ₂ - 0.26
Cu - 0.20	MnCl ₂ - 1.0	KCl - 1.35
Fe - 0.21	KCl - 5.3	NaCl - 16.27
Pb - 0.14	NaCl - 63.8	SrCl ₂ - 0.13
Li - 0.02	SrCl ₂ - 0.5	ZnCl ₂ - 0.03
Mg - 0.03	ZnCl ₂ - 0.1	Ca(OH) ₂ - 0.15
Mn - 0.11		CuO - 0.51
Ni - 0.00		Fe ₂ O ₃ - 0.37
K - 0.36		PbO - 0.44
Si - 34.90	Acid Soluble - 2.0	Mn(OH) ₂ - 0.22
Ag - 0.00	Ca(OH) ₂ - 7.4	Na ₂ SiO ₃ - 0.37
Na - 3.22	CuO - 18.5	ZnO - 0.21
Sr - 0.03	Fe ₂ O ₃ - 18.5	Al ₂ O ₃ - 0.07
Sn - 0.15	PbO - 18.5	CaSiO ₃ - 0.22
Zn - 0.05	Mn(OH) ₂ - 11.2	Fe ₃ O ₄ - 0.22
	Na ₂ SiO ₃ - 18.5	MgSiO ₃ - 0.07
	ZnO - 7.4	MnSiO ₃ - 0.07
		SiO ₂ - 71.41
		SnSO ₄ - 0.15
	Acid Insoluble - 72.5	
	Al ₂ O ₃ - 0.1	
	CaSiO ₃ - 0.3	
	CuO - 0.2	
	Fe ₃ O ₄ - 0.3	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.1	
	SiO ₂ - 98.5	
	SnSO ₄ - 0.2	
	ZnO - 0.1	

RED VALVE LINER
BETWEEN 2B SEPARATOR AND ATMOSPHERIC FLASH
DATE: 1-12-79

Wt. %	% Fraction	% Total Scale
Al - 0.05	Water Soluble - 17.4	CaCl ₂ - 4.16
Ba - 0.00	CaCl ₂ - 23.9	PbCl ₂ - 0.12
Ca - 0.61	PbCl ₂ - 0.7	LiCl - 0.16
Cr - 0.00	LiCl - 0.9	MgCl ₂ - 0.03
Co - 0.00	MgCl ₂ - 0.2	MnCl ₂ - 0.17
Cu - 0.22	MnCl ₂ - 1.0	KCl - 0.94
Fe - 0.37	KCl - 5.4	NaCl - 11.73
Pb - 1.28	NaCl - 67.4	SrCl ₂ - 0.09
Li - 0.01	SrCl ₂ - 0.5	Ca(OH) ₂ - 0.08
Mg - 0.01		CuO - 0.41
Mn - 0.09		Fe ₂ O ₃ - 0.47
Ni - 0.00		PbO - 2.41
K - 0.17	Acid Soluble - 3.2	Mn(OH) ₂ - 0.11
Si - 41.00	Ca(OH) ₂ - 2.6	K ₂ SiO ₃ - 0.03
Ag - 0.20	CuO - 7.8	Ag ₂ O - 0.14
Na - 1.55	Fe ₂ O ₃ - 14.7	Na ₂ SiO ₃ - 0.19
Sr - 0.01	PbO - 57.7	ZnO - 0.16
Sn - 0.17	Mn(OH) ₂ - 3.4	Al ₂ O ₃ - 0.08
Zn - 0.07	K ₂ SiO ₃ - 0.9	CaSiO ₃ - 0.24
	Ag ₂ O - 4.3	Fe ₃ O ₄ - 0.32
	Na ₂ SiO ₃ - 6.0	MgSiO ₃ - 0.08
	ZnO - 2.6	MnSiO ₃ - 0.08
		SiO ₂ - 77.48
		AgCl - 0.16
		SrSO ₄ - 0.16
	Acid Insoluble - 79.4	
	Al ₂ O ₃ - 0.1	
	CaSiO ₃ - 0.3	
	CuO - 0.2	
	Fe ₃ O ₄ - 0.4	
	PbO - 0.7	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.1	
	SiO ₂ - 97.6	
	AgCl - 0.2	
	SnSO ₄ - 0.2	
	ZnO - 0.1	

V-15 (ATMOSPHERIC FLASH VESSEL) OUTLET
DATE: 1-8-79

Wt. %	% Fraction	% Total Scale
Al - 0.06	Water Soluble - 41.6	CaCl ₂ - 14.77
Ba - 0.02	CaCl ₂ - 35.5	CuCl ₂ - 0.04
Ca - 3.78	CuCl ₂ - 0.1	LiCl - 0.25
Cr - 0.00	LiCl - 0.6	MgCl ₂ - 0.08
Co - 0.00	MgCl ₂ - 0.2	MnCl ₂ - 0.29
Cu - 0.19	MnCl ₂ - 0.7	KCl - 2.70
Fe - 0.33	KCl - 6.5	NaCl - 23.20
Pb - 0.14	NaCl - 55.8	SrCl ₂ - 0.17
Li - 0.03	SrCl ₂ - 0.4	ZnCl ₂ - 0.08
Mg - 0.03	ZnCl ₂ - 0.2	Ca(OH) ₂ - 0.25
Mn - 0.12		CuO - 0.45
Ni - 0.02		Fe ₂ O ₃ - 0.62
K - 0.99		PbO - 0.25
Si - 30.70	Acid Soluble - 2.3	Mn(OH) ₂ - 0.08
Ag - 0.01	Ca(OH) ₂ - 10.7	Na ₂ SiO ₃ - 0.58
Na - 6.29	CuO - 19.6	ZnO - 0.08
Sr - 0.06	Fe ₂ O ₃ - 26.8	Al ₂ O ₃ - 0.11
Sn - 0.00	PbO - 10.7	BaSO ₄ - 0.06
Zn - 0.06	Mn(OH) ₂ - 3.6	CaSiO ₃ - 0.22
	Na ₂ SiO ₃ - 25.0	CuO - 0.06
	ZnO - 3.6	Fe ₃ O ₄ - 0.28
		PbO - 0.06
		MgSiO ₃ - 0.06
		MnSiO ₃ - 0.06
		SiO ₂ - 55.20
	Acid Insoluble - 56.1	
	Al ₂ O ₃ - 0.2	
	BaSO ₄ - 0.1	
	CaSiO ₃ - 0.4	
	CuO - 0.1	
	Fe ₃ O ₄ - 0.5	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.1	
	SiO ₂ - 98.4	

P-2 DISCHARGE
DATE: 1-2-79

Wt. %	% Fraction	% Total Scale
Al - 0.06	Water Soluble - 34.6	BaCl ₂ - 0.03
Ba - 0.02	BaCl ₂ - 0.1	CaCl ₂ - 9.45
Ca - 2.26	CaCl ₂ - 27.3	CuCl ₂ - 0.03
Cr - 0.00	CuCl ₂ - 0.1	PbCl ₂ - 0.35
Co - 0.01	PbCl ₂ - 1.0	LiCl - 0.17
Cu - 0.26	LiCl - 0.5	MgCl ₂ - 0.07
Fe - 0.41	MgCl ₂ - 0.2	MnCl ₂ - 0.28
Pb - 0.58	MnCl ₂ - 0.8	KCl - 2.11
Li - 0.02	KCl - 6.1	NaCl - 21.90
Mg - 0.03	NaCl - 63.3	SrCl ₂ - 0.14
Mn - 0.10	SrCl ₂ - 0.4	ZnCl ₂ - 0.07
Ni - 0.02	ZnCl ₂ - 0.2	Ca(OH) ₂ - 0.06
K - 0.73		CuO - 0.38
Si - 34.82		Fe ₂ O ₃ - 1.70
Ag - 0.01		PbO - 0.44
Na - 5.55	Acid Soluble - 3.0	Mn(OH) ₂ - 0.03
Sr - 0.04	Ca(OH) ₂ - 2.0	NiO - 0.03
Sn - 0.00	CuO - 12.6	K ₂ SiO ₃ - 0.06
Zn - 0.05	Fe ₂ O ₃ - 56.5	Na ₂ SiO ₃ - 0.26
	PbO - 14.6	AgCl - 0.02
	Mn(OH) ₂ - 1.0	ZnO - 0.03
	NiO - 1.0	Al ₂ O ₃ - 0.12
	K ₂ SiO ₃ - 2.0	CaSiO ₃ - 0.19
	Na ₂ SiO ₃ - 8.8	CuO - 0.06
	AgCl - 0.5	Fe ₃ O ₄ - 0.25
	ZnO - 1.0	PbO - 0.12
		MgSiO ₃ - 0.06
		SiO ₂ - 61.59
	Acid Insoluble - 62.4	
	Al ₂ O ₃ - 0.2	
	CaSiO ₃ - 0.3	
	CuO - 0.1	
	Fe ₃ O ₄ - 0.4	
	PbO - 0.2	
	MgSiO ₃ - 0.1	
	SiO ₂ - 98.7	

1-B SCRUBBER (BOTTOM)

DATE: 1-9-79

Wt. %	% Fraction	% Total Scale
Al - 0.04	Water Soluble - 3.8	CaCl ₂ - 2.98
Ba - 0.00	CaCl ₂ - 78.8	CrCl ₂ - 0.20
Ca - 0.17	CrCl ₂ - 5.3	MgCl ₂ - 0.20
Cr - 0.05	MgCl ₂ - 5.3	MnCl ₂ - 0.20
Co - 0.01	MnCl ₂ - 5.3	NaCl - 0.20
Cu - 0.03	NaCl - 5.3	Ca(OH) ₂ - 0.08
Fe - 49.99		CrO - 0.13
Pb - 0.31		CoO - 0.10
Li - 0.00		CuO - 0.10
Mg - 0.03	Acid Soluble - 27.9	Fe ₂ O ₃ - 25.72
Mn - 0.50	Ca(OH) ₂ - 0.3	PbO - 0.38
Ni - 0.04	CrO - 0.2	Mg(OH) ₂ - 0.03
K - 0.00	CoO - 0.1	Mn(OH) ₂ - 0.50
Si - 2.13	CuO - 0.1	NiO - 0.10
Ag - 0.00	Fe ₂ O ₃ - 92.2	Na ₂ SiO ₃ - 0.03
Na - 0.06	PbO - 1.1	ZnO - 1.09
Sr - 0.00	Mg(OH) ₂ - 0.1	Al ₂ O ₃ - 0.07
Sn - 0.00	Mn(OH) ₂ - 1.8	CaSiO ₃ - 0.14
Zn - 0.73	NiO - 0.1	Fe ₃ O ₄ - 61.74
	Na ₂ SiO ₃ - 0.1	MgSiO ₃ - 0.07
	ZnO - 3.9	MnSiO ₃ - 0.48
		SiO ₂ - 5.46
	Acid Insoluble - 68.3	
	Al ₂ O ₃ - 0.1	
	CaSiO ₃ - 0.2	
	CrO - 0.1	
	CoO - 0.1	
	CuO - 0.1	
	Fe ₃ O ₄ - 90.4	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.7	
	NiO - 0.1	
	SiO ₂ - 8.0	

1-B SCRUBBER (TOP)
DATE: 1-8-79

Wt. %	% Fraction	% Total Scale
Al - 0.03	Water Soluble - 0.4	MnCl ₂ - 0.20
Ba - 0.00	MnCl ₂ - 50.0	NaCl - 0.20
Ca - 0.04	NaCl - 50.0	CaCO ₃ - 0.02
Cr - 0.02		CrS - 0.02
Co - 0.01		CuS - 0.02
Cu - 0.01		Fe ₂ O ₃ - 15.96
Fe - 38.32	Acid Soluble - 17.1	PbS - 0.03
Pb - 0.05	CaCO ₃ - 0.1	MnCO ₃ - 0.36
Li - 0.00	CrS - 0.1	NiCO ₃ - 0.03
Mg - 0.01	CuS - 0.1	Na ₂ SiO ₃ - 0.02
Mn - 0.29	Fe ₂ O ₃ - 93.3	ZnS - 0.65
Ni - 0.05	PbS - 0.2	Al ₂ O ₃ - 0.08
K - 0.00	MnCO ₃ - 2.1	CaSiO ₃ - 0.25
Si - 1.21	NiCO ₃ - 0.2	CoS - 0.08
Ag - 0.00	Na ₂ SiO ₃ - 0.1	Fe ₃ O ₄ - 75.98
Na - 0.01	ZnS - 3.8	PbO - 0.08
Sr - 0.00		MgSiO ₃ - 0.08
Sn - 0.00		MnSiO ₃ - 0.58
Zn - 0.53		NiS - 0.08
	Acid Insoluble - 82.5	SiO ₂ - 5.28
	Al ₂ O ₃ - 0.1	
	CaSiO ₃ - 0.3	
	CoS - 0.1	
	Fe ₃ O ₄ - 92.1	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.7	
	NiS - 0.1	
	SiO ₂ - 6.4	

2-B SCRUBBER (BOTTOM)

DATE: 1-8-79

Wt. %	% Fraction	% Total Scale
Al - 0.03	Water Soluble - 16.4	CaCl ₂ - 9.35
Ba - 0.00	CaCl ₂ - 57.0	KCl - 0.54
Ca - 2.20	KCl - 3.3	NaCl - 6.51
Cr - 0.02	NaCl - 39.7	CaCO ₃ - 3.30
Co - 0.01		CrS - 0.06
Cu - 0.05		CoCO ₃ - 0.06
Fe - 32.57		CuS - 0.06
Pb - 1.08	Acid Soluble - 62.2	FeS - 43.43
Li - 0.00	CaCO ₃ - 5.3	PbS - 1.31
Mg - 0.04	CrS - 0.1	MgCO ₃ - 0.06
Mn - 3.98	CoCO ₃ - 0.1	MnCO ₃ - 6.41
Ni - 0.03	CuS - 0.1	NiCO ₃ - 0.06
K - 0.02	FeS - 69.8	Na ₂ SiO ₃ - 0.06
Si - 4.17	PbS - 2.1	ZnS - 7.40
Na - 0.22	MgCO ₃ - 0.1	Al ₂ O ₃ - 0.06
Ag - 0.00	MnCO ₃ - 10.3	CaSiO ₃ - 0.36
Sr - 0.01	NiCO ₃ - 0.1	CoS - 0.02
Sn - 0.00	Na ₂ SiO ₃ - 0.1	CuO - 0.02
Zn - 4.62	ZnS - 11.9	Fe ₃ O ₄ - 13.82
		PbO - 0.15
		MgSiO ₃ - 0.04
		MnSiO ₃ - 0.41
		NiS - 0.03
		SiO ₂ - 6.46
		ZnO - 0.02
	Acid Insoluble - 21.4	
	Al ₂ O ₃ - 0.3	
	CaSiO ₃ - 1.7	
	CoS - 0.1	
	CuO - 0.1	
	Fe ₃ O ₄ - 64.5	
	PbO - 0.7	
	MgSiO ₃ - 0.2	
	MnSiO ₃ - 1.9	
	NiS - 0.2	
	SiO ₂ - 30.2	
	ZnO - 0.1	

2-B SCRUBBER (CENTER)

DATE: 1-8-79

Wt. %

% Fraction

% Total Scale

Al - 0.03
Ba - 0.01
Ca - 0.28
Cr - 0.03
Co - 0.01
Cu - 0.03
Fe - 53.15
Pb - 0.22
Li - 0.00
Mg - 0.03
Mn - 1.04
Ni - 0.05
K - 0.02
Si - 3.80
Ag - 0.00
Na - 0.11
Sr - 0.00
Sn - 0.00
Zn - 1.58

Water Soluble - 4.5
CaCl₂ - 35.6
FeCl₂ - 2.4
MnCl₂ - 2.4
KCl - 4.8
NaCl - 54.8

Acid Soluble - 45.7
CaCO₃ - 0.6
CoCO₃ - 0.01
CuS - 0.1
FeS - 90.9
PbS - 0.4
MgCO₃ - 0.1
MnCO₃ - 2.8
NiCO₃ - 0.1
Na₂SiO₃ - 0.1
ZnS - 4.8

Acid Insoluble - 49.8
Al₂O₃ - 0.1
CaSiO₃ - 0.3
CrO - 0.1
Fe₃O₄ - 82.8
PbO - 0.1
MgSiO₃ - 0.1
MnSiO₃ - 0.7
NiS - 0.1
SiO₂ - 15.7

CaCl₂ - 1.60
FeCl₂ - 0.11
MnCl₂ - 0.11
KCl - 0.22
NaCl - 2.47
CaCO₃ - 0.27
CoCO₃ - 0.05
CuS - 0.05
FeS - 41.53
PbS - 0.18
MgCO₃ - 0.05
MnCO₃ - 1.28
NiCO₃ - 0.05
Na₂SiO₃ - 0.05
ZnS - 2.19
Al₂O₃ - 0.05
CaSiO₃ - 0.15
CrO - 0.05
Fe₃O₄ - 41.22
PbO - 0.05
MgSiO₃ - 0.05
MnSiO₃ - 0.35
NiS - 0.05
SiO₂ - 7.82

2-B SCRUBBER (UPPER WALLS)

DATE: 1-8-79

Wt. %	% Fraction	% Total Scale
Al - 0.02	Water Soluble - 11.9	CaCl ₂ - 2.11
Ba - 0.00	CaCl ₂ - 17.7	MgCl ₂ - 0.35
Ca - 3.05	MgCl ₂ - 2.9	MnCl ₂ - 0.35
Cr - 0.02	MnCl ₂ - 2.9	KCl - 0.70
Co - 0.01	KCl - 5.9	NaCl - 8.40
Cu - 0.05	NaCl - 70.6	CaCO ₃ - 4.51
Fe - 42.37		CrS - 0.15
Pb - 0.87		CuS - 0.07
Li - 0.00		FeS - 58.24
Mg - 0.04	Acid Soluble - 72.8	PbS - 1.02
Mn - 2.62	CaCO ₃ - 6.2	MgCO ₃ - 0.07
Ni - 0.24	CrS - 0.2	MnCO ₃ - 3.93
K - 0.01	CuS - 0.1	Na ₂ SiO ₃ - 0.07
Si - 3.56	FeS - 80.0	ZnS - 4.72
Ag - 0.00	PbS - 1.4	Al ₂ O ₃ - 0.03
Na - 0.11	MgCO ₃ - 0.1	CaSiO ₃ - 0.09
Sr - 0.01	MnCO ₃ - 5.4	CrO - 0.02
Sn - 0.00	Na ₂ SiO ₃ - 0.1	CoS - 0.02
Zn - 3.23	ZnS - 6.5	CuO - 0.02
		Fe ₃ O ₄ - 9.73
		PbO - 0.06
		MgSiO ₃ - 0.06
		MnSiO ₃ - 0.08
		NiS - 0.31
		SiO ₂ - 4.87
		ZnO - 0.02
	Acid Insoluble - 15.3	
	Al ₂ O ₃ - 0.2	
	CaSiO ₃ - 0.6	
	CrO - 0.1	
	CoS - 0.1	
	CuO - 0.1	
	Fe ₃ O ₄ - 63.6	
	PbO - 0.4	
	MgSiO ₃ - 0.4	
	MnSiO ₃ - 0.5	
	NiS - 2.0	
	SiO ₂ - 31.9	
	ZnO - 0.1	

2-B SCRUBBER (TOP)
DATE: 1-8-79

Wt. %	% Fraction	% Total Scale
Al - 0.04	Water Soluble - 23.7	CaCl ₂ - 15.64
Ba - 0.00	CaCl ₂ - 66.0	KCl - 0.45
Ca - 5.91	KCl - 1.9	NaCl - 7.61
Cr - 0.03	NaCl - 32.1	CaCO ₃ - 10.82
Co - 0.00		CrS - 0.07
Cu - 0.02		FeS - 50.06
Fe - 28.96		PbS - 0.20
Pb - 0.17	Acid Soluble - 67.2	MnCO ₃ - 3.43
Li - 0.00	CaCO ₃ - 16.1	NiCO ₃ - 0.07
Mg - 0.03	CrS - 0.1	Na ₂ SiO ₃ - 0.07
Mn - 0.20	FeS - 74.5	SrCO ₃ - 0.07
Ni - 0.03	PbS - 0.3	ZnS - 2.42
K - 0.00	MnCO ₃ - 5.1	Al ₂ O ₃ - 0.06
Si - 3.08	NiCO ₃ - 0.1	CaSiO ₃ - 0.62
Ag - 0.00	Na ₂ SiO ₃ - 0.1	CoS - 0.01
Na - 0.09	SrCO ₃ - 0.1	CrO - 0.01
Sr - 0.05	ZnS - 3.6	CuO - 0.01
Sn - 0.00		Fe ₃ O ₄ - 4.36
Zn - 1.41		PbO - 0.05
		MgSiO ₃ - 0.05
		MnSiO ₃ - 0.11
		NiS - 0.03
		SiO ₂ - 3.78
	Acid Insoluble - 9.1	
	Al ₂ O ₃ - 0.7	
	CaSiO ₃ - 6.8	
	CoS - 0.1	
	CrO - 0.1	
	CuO - 0.1	
	Fe ₃ O ₄ - 48.0	
	PbO - 0.5	
	MgSiO ₃ - 0.5	
	MnSiO ₃ - 1.2	
	NiS - 0.3	
	SiO ₂ - 41.7	

APPENDIX E

BRINE LINE BELOW 1-A SEPARATOR
DATE: 2-2-79

Wt. %	% Fraction	% Total Scale
Al - 0.90	Water Soluble - 19.9	CaCl ₂ - 3.20
Ba - 0.05	CaCl ₂ - 16.1	LiCl - 0.14
Ca - 0.95	LiCl - 0.7	MgCl ₂ - 0.32
Cr - 0.01	MgCl ₂ - 1.6	MnCl ₂ - 1.39
Co - 0.01	MnCl ₂ - 7.0	KCl - 1.13
Cu - 0.07	KCl - 5.7	NaCl - 13.67
Fe - 20.89	NaCl - 68.7	SrCl ₂ - 0.02
Pb - 1.38	SrCl ₂ - 0.1	ZnCl ₂ - 0.02
Li - 0.01	ZnCl ₂ - 0.1	Al ₂ S ₃ - 0.11
Mg - 0.43		CaO - 0.17
Mn - 1.72		CuS - 0.04
Ni - 0.01		Fe ₂ O ₃ - 19.18
K - 0.22	Acid Soluble - 21.1%	PbS - 0.15
Si - 20.23	Al ₂ S ₃ - 0.5	MgO - 0.27
Ag - 0.06	Ca(OH) ₂ - 0.8	MnO - 1.08
Na - 1.98	CuS - 0.2	Na ₂ SiO ₃ - 0.04
Sr - 0.01	Fe ₂ O ₃ - 90.9	AgCl - 0.02
Sn - 0.07	PbS - 0.7	ZnS - 0.04
Zn - 0.08	Mg(OH) ₂ - 1.3	Al ₂ O ₃ - 1.48
	Mn(OH) ₂ - 5.1	BaSO ₄ - 0.06
	Na ₂ SiO ₃ - 0.2	CaSiO ₃ - 1.12
	AgCl - 0.1	CrO - 0.06
	ZnS - 0.2	CoS - 0.06
		CuS - 0.06
		Fe ₃ O ₄ - 12.15
		PbO - 1.30
	Acid Insoluble - 59.0	MgSiO ₃ - 1.00
	Al ₂ O ₃ - 2.5	MnSiO ₃ - 1.77
	BaSO ₄ - 0.1	NiS - 0.06
	CaSiO ₃ - 1.9	SiO ₂ - 39.71
	CrO - 0.1	Ag ₂ S - 0.06
	CoS - 0.1	SnSO ₄ - 0.06
	CuS - 0.1	ZnO - 0.06
	Fe ₃ O ₄ - 20.6	
	PbO - 2.2	
	MgSiO ₃ - 1.7	
	MnSiO ₃ - 3.0	
	NiS - 0.1	
	SiO ₂ - 67.3	
	Ag ₂ S - 0.1	
	SnSO ₄ - 0.1	
	ZnO - 0.1	

BRINE LINE BETWEEN 1-A & 2-A SEPARATORS @ "T"

DATE: 2-2-79

Wt. %	% Fraction	% Total Scale
Al - 0.58	Water Soluble - 27.3	CaCl ₂ - 6.28
Ba - 0.04	CaCl ₂ - 23.0	LiCl - 0.19
Ca - 1.70	LiCl - 0.7	MgCl ₂ - 0.27
Cr - N.D.	MgCl ₂ - 1.0	MnCl ₂ - 0.27
Co - 0.01	MnCl ₂ - 4.8	KCl - 1.86
Cu - 0.06	KCl - 6.8	NaCl - 17.29
Fe - 18.92	NaCl - 63.3	SrCl ₂ - 0.08
Pb - 1.31	SrCl ₂ - 0.3	ZnCl ₂ - 0.03
Li - 0.02	ZnCl ₂ - 0.1	Al ₂ S ₃ - 0.07
Mg - 0.40		Ca(OH) ₂ - 0.16
Mn - 1.58		CuS - 0.04
Ni - 0.01		Fe ₂ O ₃ - 16.77
K - 0.47	Acid Soluble - 18.3	PbS - 0.11
Si - 17.45	Al ₂ S ₃ - 0.4	Mg(OH) ₂ - 0.22
Ag - 0.01	Ca(OH) ₂ - 0.9	Mn(OH) ₂ - 0.86
Na - 3.36	CuS - 0.2	Na ₂ SiO ₃ - 0.04
Sr - 0.02	Fe ₂ O ₃ - 91.6	ZnS - 0.04
Sn - 0.05	PbS - 0.6	Al ₂ O ₃ - 1.03
Zn - 0.07	Mg(OH) ₂ - 1.2	BaSO ₄ - 0.05
	Mn(OH) ₂ - 4.7	CaSiO ₃ - 1.41
	Na ₂ SiO ₃ - 0.2	CoS - 0.05
	ZnS - 0.2	Cu ₂ O - 0.05
		Fe ₃ O ₄ - 10.94
		PbO - 1.31
		MgSiO ₃ - 0.98
		MnSiO ₃ - 1.58
	Acid Insoluble - 54.4	NiS - 0.05
	Al ₂ O ₃ - 1.9	SiO ₂ - 36.78
	BaSO ₄ - 0.1	Ag ₂ S - 0.05
	CaSiO ₃ - 2.6	SnSO ₄ - 0.05
	CoS - 0.1	ZnO - 0.05
	Cu ₂ O - 0.1	
	Fe ₃ O ₄ - 20.1	
	PbO - 2.4	
	MgSiO ₃ - 1.8	
	MnSiO ₃ - 2.9	
	NiS - 0.1	
	SiO ₂ - 67.6	
	Ag ₂ S - 0.1	
	SnSO ₄ - 0.1	
	ZnO - 0.1	

V-15 DISCHARGE @ "T"
DATE: 2-2-79

Wt. %	% Fraction	% Total Scale
Al - 0.08	Water Soluble - 65.8	CaCl ₂ - 16.91
Ba - N.D.	CaCl ₂ - 25.7	CuCl ₂ - 0.07
Ca - 2.80	CuCl ₂ - 0.1	LiCl - 0.46
Cr - N.D.	LiCl - 0.7	MgCl ₂ - 0.13
Co - 0.01	MgCl ₂ - 0.2	MnCl ₂ - 0.92
Cu - 0.10	MnCl ₂ - 1.4	KCl - 6.45
Fe - 1.06	KCl - 9.8	NaCl - 40.20
Pb - 0.12	NaCl - 61.1	SrCl ₂ - 0.39
Li - 0.03	SrCl ₂ - 0.6	ZnCl ₂ - 0.26
Mg - 0.05	ZnCl ₂ - 0.4	Ca(OH) ₂ - 0.11
Mn - 0.22		Cu ₂ O - 0.14
Ni - 0.01		Fe ₂ O ₃ - 1.05
K - 1.47		PbO - 0.17
Si - 14.41	Acid Soluble - 1.6	Mg(OH) ₂ - 0.12
Ag - N.D.	Ca(OH) ₂ - 6.7	Mn(OH) ₂ - 0.05
Na - 6.85	Cu ₂ O - 6.7	Na ₂ SiO ₃ - 0.07
Sr - 0.09	Fe ₂ O ₃ - 65.6	ZnO - 0.05
Sn - 0.07	PbO - 4.4	Al ₂ O ₃ - 0.16
Zn - 0.14	Mg(OH) ₂ - 7.8	CaSiO ₃ - 0.33
	Mn(OH) ₂ - 3.3	CoO - 0.03
	Na ₂ SiO ₃ - 4.4	Fe ₃ O ₄ - 0.91
	ZnO - 1.1	MgSiO ₃ - 0.10
		MnSiO ₃ - 0.07
		NiO - 0.03
		SiO ₂ - 30.75
		SnSO ₄ - 0.07
	Acid Insoluble - 32.6	
	Al ₂ O ₃ - 0.5	
	CaSiO ₃ - 1.0	
	CoO - 0.1	
	Cu ₂ O - 0.1	
	Fe ₃ O ₄ - 2.8	
	PbO - 0.3	
	MgSiO ₃ - 0.3	
	MnSiO ₃ - 0.2	
	NiO - 0.1	
	SiO ₂ - 94.3	
	SnSO ₄ - 0.2	
	ZnO - 0.1	

P-2 PUMP BOWL
DATE: 2-2-79

Wt. %	% Fraction	% Total Scale
Al - 0.09	Water Soluble - 10.2	CaCl ₂ - 2.59
Ba - N.D.	CaCl ₂ - 25.4	CuCl ₂ - 0.06
Ca - 0.43	CuCl ₂ - 0.6	LiCl - 0.06
Cr - N.D.	LiCl - 0.6	MgCl ₂ - 0.03
Co - 0.01	MgCl ₂ - 0.3	MnCl ₂ - 0.11
Cu - 0.89	MnCl ₂ - 1.1	KCl - 0.82
Fe - 1.00	KCl - 8.0	NaCl - 6.47
Pb - 0.51	NaCl - 63.4	SrCl ₂ - 0.06
Li - N.D.	SrCl ₂ - 0.6	Al ₂ (SO ₄) ₃ - 0.48
Mg - 0.02		Ca(OH) ₂ - 0.12
Mn - 0.11		Cu ₂ O - 1.80
Ni - 0.02		Fe ₂ O ₃ - 1.71
K - 0.19	Acid Soluble - 6.1	PbO - 0.94
Si - 41.19	Al ₂ (SO ₄) ₃ - 7.8	Mg(OH) ₂ - 0.02
Ag - 0.05	Ca(OH) ₂ - 2.0	Mn(OH) ₂ - 0.18
Na - 0.97	Cu ₂ O - 26.7	NiO - 0.02
Sr - 0.01	Fe ₂ O ₃ - 28.1	K ₂ SiO ₃ - 0.18
Sn - 0.10	PbO - 14.0	Na ₂ SiO ₃ - 0.49
Zn - 0.14	Mg(OH) ₂ - 0.3	AgCl - 0.12
	Mn(OH) ₂ - 2.9	ZnO - 0.39
	NiO - 0.3	Al ₂ O ₃ - 0.08
	K ₂ SiO ₃ - 2.9	CaSiO ₃ - 0.17
	Na ₂ SiO ₃ - 8.1	CaO - 0.08
	AgCl - 2.0	Fe ₃ O ₄ - 0.50
	ZnO - 4.9	MgSiO ₃ - 0.08
		MnSiO ₃ - 0.08
		SiO ₂ - 82.28
		SnSO ₄ - 0.08
	Acid Insoluble - 83.7	
	Al ₂ O ₃ - 0.1	
	CaSiO ₃ - 0.2	
	CaO - 0.1	
	Cu ₂ O - 0.2	
	Fe ₃ O ₄ - 0.6	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.1	
	SiO ₂ - 98.3	
	SnSO ₄ - 0.1	
	ZnO - 0.1	

P-2 DISCHARGE
DATE: 2-2-79

Wt. %	% Fraction	% Total Scale
Al - 0.11	Water Soluble - 39.2	CaCl ₂ - 9.84
Ba - N.D.	CaCl ₂ - 25.1	CuCl ₂ - 0.04
Ca - 2.05	CuCl ₂ - 0.1	LiCl - 0.20
Cr - 0.01	LiCl - 0.5	MgCl ₂ - 0.08
Co - 0.01	MgCl ₂ - 0.2	MnCl ₂ - 0.43
Cu - 0.41	MnCl ₂ - 1.1	NiCl ₂ - 0.04
Fe - 0.88	NiCl ₂ - 0.1	KCl - 3.68
Pb - 0.14	KCl - 9.4	NaCl - 24.54
Li - 0.02	NaCl - 62.6	SrCl ₂ - 0.24
Mg - 0.03	SrCl ₂ - 0.6	ZnCl ₂ - 0.12
Mn - 0.16	ZnCl ₂ - 0.3	Ca(OH) ₂ - 0.22
Ni - 0.02		Cu ₂ O - 0.65
K - 1.02		Fe ₂ O ₃ - 1.23
Si - 28.49		PbO - 0.20
Ag - 0.01	Acid Soluble - 2.5	Mg(OH) ₂ - 0.02
Na - 5.06	Ca(OH) ₂ - 8.9	Mn(OH) ₂ - 0.09
Sr - 0.07	Cu ₂ O - 21.5	NiO - 0.02
Sn - 0.08	Fe ₂ O ₃ - 49.0	K ₂ SiO ₃ - 0.06
Zn - 0.05	PbO - 5.9	Na ₂ SiO ₃ - 0.17
	Mg(OH) ₂ - 0.7	ZnO - 0.02
	Mn(OH) ₂ - 3.7	Al ₂ O ₃ - 0.17
	NiO - 0.7	CaSiO ₃ - 0.29
	K ₂ SiO ₃ - 2.2	CrO - 0.06
	Na ₂ SiO ₃ - 6.7	CoO - 0.06
	ZnO - 0.7	Fe ₃ O ₄ - 0.52
		MgSiO ₃ - 0.06
		MnSiO ₃ - 0.06
		SiO ₂ - 56.77
		Ag ₂ O - 0.06
		SnSO ₄ - 0.06
	Acid Insoluble - 58.3	
	Al ₂ O ₃ - 0.3	
	CaSiO ₃ - 0.5	
	CrO - 0.1	
	CoO - 0.1	
	Cu ₂ O - 0.2	
	Fe ₃ O ₄ - 0.9	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.1	
	SiO ₂ - 97.4	
	Ag ₂ O - 0.1	
	SnSO ₄ - 0.1	

INJECTION LINE @ ELBOW ABOVE 1-A SEPARATOR

DATE: 2-2-79

Wt. %	% Fraction	% Total Scale
Al - 0.06	Water Soluble - 22.8	CaCl ₂ - 7.66
Ba - 0.13	CaCl ₂ - 33.6	PbCl ₂ - 0.07
Ca - 1.53	PbCl ₂ - 0.3	LiCl - 0.11
Cr - N.D.	LiCl - 0.5	MgCl ₂ - 0.05
Co - 0.01	MgCl ₂ - 0.2	MnCl ₂ - 0.32
Cu - 0.24	MnCl ₂ - 1.4	KCl - 1.57
Fe - 0.85	KCl - 6.9	NaCl - 12.81
Pb - 0.48	NaCl - 56.2	SrCl ₂ - 0.14
Li - 0.01	SrCl ₂ - 0.6	ZnCl ₂ - 0.07
Mg - 0.03	ZnCl ₂ - 0.3	Ca(OH) ₂ - 0.29
Mn - 0.11		Cu ₂ O - 0.59
Ni - 0.01		Fe ₂ O ₃ - 1.77
K - 0.41		PbO - 1.04
Si - 33.79	Acid Soluble - 4.2	Mg(OH) ₂ - 0.03
Ag - 0.01	Ca(OH) ₂ - 7.0	Mn(OH) ₂ - 0.13
Na - 2.48	Cu ₂ O - 14.1	K ₂ SiO ₃ - 0.10
Sr - 0.05	Fe ₂ O ₃ - 42.2	Na ₂ SiO ₃ - 0.29
Sn - 0.12	PbO - 21.1	SrO - 0.03
Zn - 0.04	Mg(OH) ₂ - 0.8	ZnO - 0.14
	Mn(OH) ₂ - 3.1	Al ₂ O ₃ - 0.15
	K ₂ SiO ₃ - 2.3	BaSO ₄ - 0.15
	Na ₂ SiO ₃ - 7.0	CaSiO ₃ - 0.29
	SrO - 0.8	CoO - 0.07
	ZnO - 1.6	CuO - 0.07
		Fe ₃ O ₄ - 0.59
		MgSiO ₃ - 0.07
		MnSiO ₃ - 0.07
	Acid Insoluble - 73.0	NiO - 0.07
	Al ₂ O ₃ - 0.2	SiO ₂ - 71.04
	BaSO ₄ - 0.2	Ag ₂ O - 0.07
	CaSiO ₃ - 0.4	SnSO ₄ - 0.15
	CoO - 0.1	
	Cu ₂ O - 0.1	
	Fe ₃ O ₄ - 0.8	
	PbO - 0.2	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.1	
	NiO - 0.1	
	SiO ₂ - 97.3	
	Ag ₂ O - 0.1	
	SnSO ₄ - 0.2	
	ZnO - 0.1	

DANIEL'S SPOOL PIECE (WITHOUT LINER)

DATE: FEBRUARY 1, 1979

Wt. %	% Fraction	% Total Scale
Al - 0.06	Water Soluble - 36.4	CaCl ₂ - 11.10
Ba - 0.56	CaCl ₂ - 30.5	KCl - 1.44
Ca - 11.34	KCl - 4.0	NaCl - 23.64
Cr - N.D.	NaCl - 65.0	SrCl ₂ - 0.17
Co - 0.01	SrCl ₂ - 0.5	Al ₂ (SO ₄) ₃ - 0.32
Cu - 0.15		Ba(OH) ₂ - 0.83
Fe - 4.46		Ca(OH) ₂ - 24.92
Pb - 0.41		Cu ₂ O - 0.45
Li - N.D.	Acid Soluble - 52.6	Fe ₂ O ₃ - 9.46
Mg - 0.06	Al ₂ (SO ₄) ₃ - 0.6	PbO - 0.47
Mn - 7.05	Ba(OH) ₂ - 1.6	Mg(OH) ₂ - 0.10
Ni - 0.01	Ca(OH) ₂ - 47.4	Mn(OH) ₂ - 14.96
K - 0.09	Cu ₂ O - 0.5	Ag ₂ O - 0.05
Si - 6.85	Fe ₂ O ₃ - 18.0	Na ₂ SiO ₃ - 0.10
Ag - 0.05	PbO - 0.5	SrO - 0.10
Na - 1.00	Mg(OH) ₂ - 0.2	ZnO - 1.27
Sr - 0.07	Mn(OH) ₂ - 28.5	Al ₂ O ₃ - 0.04
Sn - 0.11	Ag ₂ O - 0.1	BaSO ₄ - 0.16
Zn - 0.70	Na ₂ SiO ₃ - 0.2	CaSiO ₃ - 0.76
	SrO - 0.2	CoO - 0.01
	ZnO - 2.2	Fe ₃ O ₄ - 0.56
		MgSiO ₃ - 0.05
		MnSiO ₃ - 0.31
		NiO - 0.01
		SiO ₂ - 8.60
		AgCl - 0.03
		SnSO ₄ - 0.09
	Acid Insoluble - 11.0	
	Al ₂ O ₃ - 0.4	
	BaSO ₄ - 1.5	
	CaSiO ₃ - 7.0	
	CoO - 0.1	
	Cu ₂ O - 0.1	
	Fe ₃ O ₄ - 5.1	
	PbO - 2.0	
	MgSiO ₃ - 0.5	
	MnSiO ₃ - 2.8	
	NiO - 0.1	
	SiO ₂ - 78.2	
	AgCl - 0.3	
	SnSO ₄ - 0.8	
	ZnO - 1.1	

DANIEL'S SPOOL PIECE (WITH LINER)

DATE: FEBRUARY 1, 1979

Wt. %	% Fraction	% Total Scale
Al - 0.18	Water Soluble - 32.9	BaCl ₂ - 0.07
Ba - 0.98	BaCl ₂ - 0.2	CaCl ₂ - 10.40
Ca - 2.54	CaCl ₂ - 31.6	LiCl - 0.20
Cr - N.D.	LiCl - 0.6	MgCl ₂ - 0.07
Co - 0.01	MgCl ₂ - 0.2	MnCl ₂ - 0.30
Cu - 0.28	MnCl ₂ - 0.9	KCl - 2.27
Fe - 1.78	KCl - 6.9	NaCl - 19.41
Pb - 0.55	NaCl - 59.0	SrCl ₂ - 0.20
Li - 0.02	SrCl ₂ - 0.6	Ba(OH) ₂ - 2.36
Mg - 0.06		Ca(OH) ₂ - 1.13
Mn - 0.43		Cu ₂ O - 0.73
Ni - 0.01		Fe ₂ O ₃ - 3.95
K - 0.68	Acid Soluble - 11.1	PbO - 1.05
Si - 23.90	Ba(OH) ₂ - 21.3	Mg(OH) ₂ - 0.10
Ag - 0.01	Ca(OH) ₂ - 10.2	Mn(OH) ₂ - 0.94
Na - 4.33	Cu ₂ O - 5.6	K ₂ SiO ₃ - 0.13
Sr - 0.11	Fe ₂ O ₃ - 35.6	Na ₂ SiO ₃ - 0.87
Sn - 0.14	PbO - 5.3	SrO - 0.20
Zn - 0.11	Mg(OH) ₂ - 0.9	ZnO - 0.26
	Mn(OH) ₂ - 8.5	Al ₂ O ₃ - 0.39
	K ₂ SiO ₃ - 1.2	BaSO ₄ - 0.56
	Na ₂ SiO ₃ - 7.8	CaSiO ₃ - 0.62
	SrO - 1.8	CoO - 0.01
	ZnO - 1.8	Fe ₃ O ₄ - 0.06
		MgSiO ₃ - 0.17
		MnSiO ₃ - 0.34
		NiO - 0.01
		SiO ₂ - 53.03
		SnSO ₄ - 0.17
	Acid Insoluble - 56.0	
	Al ₂ O ₃ - 0.7	
	BaSO ₄ - 1.0	
	CaSiO ₃ - 1.1	
	CoO - <0.1	
	Cu ₂ O - 0.2	
	Fe ₃ O ₄ - 0.1	
	PbO - 0.8	
	MgSiO ₃ - 0.3	
	MgSiO ₃ - 0.6	
	NiO - <0.1	
	SiO ₂ - 94.7	
	SnSO ₄ - 0.3	
	ZnO - 0.1	

DANIEL'S SPOOL PIECE (WITHOUT LINER)
CHANGED SPOOL ALIGNMENT

DATE: MARCH 9, 1979

Wt. %	% Fraction	% Total Scale
Al - 0.11	Water Soluble - 44.1	BaCl ₂ - 0.09
B - 0.20	BaCl ₂ - 0.2	CaCl ₂ - 10.23
Ba - 0.18	CaCl ₂ - 23.2	CuCl - 0.04
Ca - 2.33	CuCl - 0.1	LiCl - 0.31
Cr - N.D.	LiCl - 0.7	MgCl ₂ - 0.09
Co - N.D.	MgCl ₂ - 0.2	MnCl ₂ - 0.53
Cu - 0.38	MnCl ₂ - 1.2	KCl - 4.37
Fe - 0.92	KCl - 9.9	NaCl - 28.14
Pb - 0.07	NaCl - 63.8	SrCl ₂ - 0.22
Li - 0.03	SrCl ₂ - 0.5	ZnCl ₂ - 0.09
Mg - 0.04	ZnCl ₂ - 0.2	Ba(OH) ₂ - 0.11
Mn - 0.19		Ca(OH) ₂ - 0.32
Ni - N.D.		Cu ₂ O - 0.86
K - 1.34		Fe ₃ O ₄ - 2.09
Si - 24.83	Acid Soluble - 3.9	PbO - 0.16
Ag - N.D.	Ba(OH) ₂ - 2.8	Mg(OH) ₂ - 0.03
Na - 6.37	Ca(OH) ₂ - 8.3	Mn(OH) ₂ - 0.11
Sr - 0.08	Cu ₂ O - 22.1	K ₂ SiO ₃ - 0.11
Sn - 0.29	Fe ₃ O ₄ - 53.5	Na ₂ SiO ₃ - 0.11
Zn - 0.03	PbO - 2.8	SrO - 0.03
	Mg(OH) ₂ - 0.7	ZnO - 0.03
	Mn(OH) ₂ - 2.8	Al ₂ O ₃ - 0.26
	K ₂ SiO ₃ - 2.8	BaSO ₄ - 0.16
	Na ₂ SiO ₃ - 2.8	CaSiO ₃ - 0.42
	SrO - 0.7	CuO - 0.10
	ZnO - 0.7	Fe ₃ O ₄ - 0.57
		MgSiO ₃ - 0.10
		MnSiO ₃ - 0.05
		SiO ₂ - 49.92
		SnSO ₄ - 0.35
	Acid Insoluble - 52.0	
	Al ₂ O ₃ - 0.5	
	BaSO ₄ - 0.3	
	CaSiO ₃ - 0.8	
	CuO - 0.2	
	Fe ₃ O ₄ - 1.1	
	PbO - 0.1	
	MgSiO ₂ - 0.2	
	MnSiO ₂ - 0.1	
	SiO ₂ - 96.0	
	SnSO ₄ - 0.7	

DANIEL'S SPOOL PIECE (WITH LINER)
CHANGED SPOOL ALIGNMENT
DATE: MARCH 9, 1979

Wt. %	% Fraction	% Total Scale
Al - 0.09	Water Soluble - 41.5	BaCl ₂ - 0.04
B - 0.41	BaCl ₂ - 0.1	CaCl ₂ - 9.88
Ba - 0.18	CaCl ₂ - 23.8	CuCl - 0.04
Ca - 2.34	CuCl - 0.1	LiCl - 0.29
Cr - N.D.	LiCl - 0.7	MgCl ₂ - 0.08
Co - N.D.	MgCl ₂ - 0.2	MnCl ₂ - 0.46
Cu - 0.38	MnCl ₂ - 1.1	KCl - 3.36
Fe - 1.02	KCl - 8.1	NaCl - 27.09
Pb - 0.12	NaCl - 65.3	SrCl ₂ - 0.21
Li - 0.03	SrCl ₂ - 0.5	ZnCl ₂ - 0.04
Mg - 0.03	ZnCl ₂ - 0.1	Ba(OH) ₂ - 0.08
Mn - 0.17		Ca(OH) ₂ - 0.21
Ni - N.D.		Cu ₂ O - 0.59
K - 1.08		Fe ₃ O ₄ - 1.65
Si - 28.08	Acid Soluble - 3.5	PbO - 0.18
Ag - N.D.	Ba(OH) ₂ - 2.2	Mg(OH) ₂ - 0.02
Na - 6.37	Ca(OH) ₂ - 6.0	Mn(OH) ₂ - 0.08
Sr - 0.08	Cu ₂ O - 16.9	K ₂ SiO ₃ - 0.08
Sn - 0.30	Fe ₃ O ₄ - 47.5	Na ₂ SiO ₃ - 0.08
Zn - 0.03	PbO - 3.8	SrO - 0.08
	Mg(OH) ₂ - 0.6	SnO - 0.50
	Mn(OH) ₂ - 2.2	ZnO - 0.08
	K ₂ SiO ₃ - 2.7	Al ₂ O ₃ - 0.16
	Na ₂ SiO ₃ - 2.7	BaSO ₄ - 0.16
	SrO - 0.6	CaSiO ₃ - 0.31
	SnO - 14.2	CuO - 0.11
	ZnO - 0.6	Fe ₃ O ₄ - 0.54
		MgSiO ₃ - 0.05
		SiO ₂ - 53.50
		SnSO ₄ - 0.05
	Acid Insoluble - 55.0	
	Al ₂ O ₃ - 0.3	
	BaSO ₄ - 0.3	
	CaSiO ₃ - 0.6	
	CuO - 0.2	
	Fe ₃ O ₄ - 1.0	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	SiO ₂ - 97.3	
	SnSO ₄ - 0.1	

P-2 TOP
DATE: 3-6-79

Wt. %	% Fraction	% Total Scale
Al - 0.08	Water Soluble - 41.4	BaCl ₂ - 0.11
B - 0.30	BaCl ₂ - 0.3	CaCl ₂ - 7.98
Ba - 0.04	CaCl ₂ - 19.3	LiCl - 0.29
Ca - 1.79	LiCl - 0.7	MgCl ₂ - 0.08
Cr - N.D.	MgCl ₂ - 0.2	MnCl ₂ - 0.70
Co - N.D.	MnCl ₂ - 1.7	KCl - 3.56
Cu - 0.32	KCl - 8.6	NaCl - 28.44
Fe - 1.34	NaCl - 68.7	SrCl ₂ - 0.17
Pb - 0.51	SrCl ₂ - 0.4	ZnCl ₂ - 0.04
Li - 0.03	ZnCl ₂ - 0.1	Ca(OH) ₂ - 0.12
Mg - 0.04		Cu ₂ O - 0.12
Mn - 0.25		Fe ₂ O ₃ - 1.77
Ni - 0.02		PbO - 0.78
K - 1.07	Acid Soluble - 3.4	Mg(OH) ₂ - 0.02
Si - 24.76	Ca(OH) ₂ - 3.5	Mn(OH) ₂ - 0.12
Ag - 0.03	Cu ₂ O - 3.5	NiO - 0.02
Na - 6.37	Fe ₂ O ₃ - 52.0	K ₂ SiO ₃ - 0.05
Sr - 0.06	PbO - 16.8	Ag ₂ O - 0.02
Sn - 0.20	Mg(OH) ₂ - 0.5	Na ₂ SiO ₃ - 0.08
Zn - 0.09	Mn(OH) ₂ - 3.5	SnO - 0.39
	NiO - 0.5	ZnO - 0.14
	K ₂ SiO ₃ - 1.4	Al ₂ O ₃ - 0.17
	Ag ₂ O - 0.5	CaSiO ₃ - 0.28
	Na ₂ SiO ₃ - 2.4	CuO - 0.06
	SnO - 11.4	Fe ₃ O ₄ - 0.88
	ZnO - 4.0	MgSiO ₃ - 0.11
		MnSiO ₃ - 0.06
		SiO ₂ - 53.38
		AgCl - 0.06
	Acid Insoluble - 55.2	
	Al ₂ O ₃ - 0.3	
	CaSiO ₃ - 0.5	
	CuO - 0.1	
	Fe ₃ O ₄ - 1.6	
	PbO - 0.4	
	MnSiO ₃ - 0.1	
	MgSiO ₃ - 0.2	
	SiO ₂ - 96.7	
	AgCl - 0.1	

P-2 SUCTION

DATE: 3-6-79

Wt. %	% Fraction	% Total Scale
Al - 0.08	Water Soluble - 49.1	BaCl ₂ - 0.10
B - 0.30	BaCl ₂ - 0.2	CaCl ₂ - 11.83
Ba - 0.03	CaCl ₂ - 24.1	CuCl - 0.05
Ca - 1.99	CuCl - 0.1	LiCl - 0.34
Cr - N.D.	LiCl - 0.7	MgCl ₂ - 0.10
Co - 0.01	MgCl ₂ - 0.2	MnCl ₂ - 0.78
Cu - 0.17	MnCl ₂ - 1.6	KCl - 4.57
Fe - 0.95	KCl - 9.3	NaCl - 31.04
Pb - 0.07	NaCl - 63.2	SrCl ₂ - 0.24
Li - 0.03	SrCl ₂ - 0.5	ZnCl ₂ - 0.05
Mg - 0.04	ZnCl ₂ - 0.1	Ca(OH) ₂ - 0.02
Mn - 0.22		CoO - 0.01
Ni - N.D.		Cu ₂ O - 0.06
K - 1.06		Fe ₂ O ₃ - 0.45
Si - 22.62	Acid Soluble - 0.8	PbO - 0.07
Ag - N.D.	Ca(OH) ₂ - 3.0	Mg(OH) ₂ - 0.01
Na - 5.35	CoO - 1.0	Mn(OH) ₂ - 0.03
Sr - 0.06	Cu ₂ O - 8.0	K ₂ SiO ₃ - 0.01
Sn - 0.22	Fe ₂ O ₃ - 57.0	Na ₂ SiO ₃ - 0.01
Zn - 0.04	PbO - 2.0	SnO - 0.16
	Mg(OH) ₂ - 1.0	ZnO - 0.02
	Mn(OH) ₂ - 4.0	Al ₂ O ₃ - 0.15
	K ₂ SiO ₃ - 1.0	CaSiO ₃ - 0.25
	Na ₂ SiO ₃ - 1.0	CuO - 0.10
	SnO - 20.0	Fe ₃ O ₄ - 0.80
	ZnO - 2.0	MgSiO ₃ - 0.10
		MnSiO ₃ - 0.05
		SiO ₂ - 48.55
		SnSO ₄ - 0.05
	Acid Insoluble - 50.1	
	Al ₂ O ₃ - 0.3	
	CaSiO ₃ - 0.5	
	CuO - 0.2	
	Fe ₂ O ₃ - 1.6	
	PbO - 0.1	
	MgSiO ₃ - 0.2	
	MnSiO ₃ - 0.1	
	SiO ₂ - 96.9	
	SnSO ₄ - 0.1	

P-2 DISCHARGE

DATE: 3-6-79

Wt. %	% Fraction	% Total Scale
Al - 0.13	Water Soluble - 33.5	BaCl ₂ - 0.07
B - 0.41	BaCl ₂ - 0.2	CaCl ₂ - 6.93
Ba - 0.02	CaCl ₂ - 20.7	CuCl - 0.13
Ca - 1.60	CuCl - 0.4	LiCl - 0.20
Cr - N.D.	LiCl - 0.6	MgCl ₂ - 0.07
Co - N.D.	MgCl ₂ - 0.2	MnCl ₂ - 0.40
Cu - 0.62	MnCl ₂ - 1.2	KCl - 3.28
Fe - 0.76	KCl - 9.8	NaCl - 22.21
Pb - 0.09	NaCl - 66.3	SrCl ₂ - 0.13
Li - 0.02	SrCl ₂ - 0.4	ZnCl ₂ - 0.07
Mg - 0.04	ZnCl ₂ - 0.2	Ca(OH) ₂ - 0.38
Mn - 0.14		CuO - 0.59
Ni - N.D.		Fe ₂ O ₃ - 1.69
K - 0.99		PbO - 0.20
Si - 31.60	Acid Soluble - 3.2	Mg(OH) ₂ - 0.04
Ag - N.D.	Ca(OH) ₂ - 11.8	Mn(OH) ₂ - 0.10
Na - 4.97	Cu ₂ O - 18.3	K ₂ SiO ₃ - 0.10
Sr - 0.05	Fe ₂ O ₃ - 52.7	Na ₂ SiO ₃ - 0.14
Sn - 0.14	PbO - 4.3	ZnO - 0.04
Zn - 0.03	Mg(OH) ₂ - 1.1	Al ₂ O ₃ - 0.25
	Mn(OH) ₂ - 3.2	CaSiO ₃ - 0.32
	K ₂ SiO ₃ - 3.2	CuO - 0.19
	Na ₂ SiO ₃ - 4.3	Fe ₃ O ₄ - 0.57
	ZnO - 1.1	MgSiO ₃ - 0.06
		SiO ₂ - 61.71
		SnSO ₄ - 0.13
	Acid Insoluble - 63.3	
	Al ₂ O ₃ - 0.4	
	CaSiO ₃ - 0.5	
	CuO - 0.3	
	Fe ₂ O ₃ - 0.9	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	SiO ₂ - 97.5	
	SnSO ₄ - 0.2	

APPENDIX F

1A SEPARATOR - BOTTOM
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.72	Water Soluble - 30.4	CaCl ₂ - 5.59
Ba - 0.02	CaCl ₂ - 18.4	LiCl - 0.27
Ca - 1.42	LiCl - 0.9	MgCl ₂ - 0.21
Cr - 0.02	MgCl ₂ - 0.7	MnCl ₂ - 0.67
Co - 0.01	MnCl ₂ - 2.2	KCl - 3.40
Cu - 0.14	KCl - 11.2	NaCl - 20.12
Fe - 18.46	NaCl - 66.2	SrCl ₂ - 0.12
Pb - 1.23	SrCl ₂ - 0.4	Al ₂ S ₃ - 0.06
Li - 0.02		Ca(OH) ₂ - 0.45
Mg - 0.33		CrO - 0.03
Mn - 1.03		CuO - 0.11
Ni - 0.03	Acid Soluble - 28.1	Fe ₂ S - 25.18
K - 0.81	Al ₂ S ₃ - 0.2	PbO - 0.70
Si - 16.31	Ca(OH) ₂ - 1.6	Mg(OH) ₂ - 0.34
Ag - 0.03	CrO - 0.1	Mn(OH) ₂ - 0.98
Na - 3.55	CuO - 0.4	K ₂ SiO ₃ - 0.06
Sr - 0.03	Fe ₂ S - 89.6	Na ₂ SiO ₃ - 0.06
Sn - N.D.	PbO - 2.5	ZnO - 0.14
Zn - 0.09	Mg(OH) ₂ - 1.2	Al ₂ O ₃ - 1.20
	Mn(OH) ₂ - 3.5	BaSO ₄ - 0.04
	K ₂ SiO ₃ - 0.2	CaSiO ₃ - 0.71
	Na ₂ SiO ₃ - 0.2	CoS - 0.04
	ZnO - 0.5	CuO - 0.08
		Fe ₃ O ₄ - 4.19
		PbO - 0.71
		MgSiO ₃ - 0.50
		MnSiO ₃ - 0.54
		NiO - 0.04
		SiO ₂ - 33.34
		Ag ₂ O - 0.04
		ZnO - 0.08
	Acid Insoluble - 41.5	
	Al ₂ O ₃ - 2.9	
	BaSO ₄ - 0.1	
	CaSiO ₃ - 1.7	
	CoS - 0.1	
	CuO - 0.2	
	Fe ₃ O ₄ - 10.1	
	PbO - 1.7	
	MgSiO ₃ - 1.2	
	MnSiO ₃ - 1.3	
	NiO - 0.1	
	SiO ₂ - 80.3	
	Ag ₂ O - 0.1	
	ZnO - 0.2	

1A SEPARATOR - TOP
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.62	Water Soluble - 8.2	CaCl ₂ - 0.32
Ba - N.D.	CaCl ₂ - 3.9	KCl - 0.97
Ca - 0.42	KCl - 11.8	NaCl - 6.51
Cr - 0.16	NaCl - 79.4	SrCl ₂ - 0.40
Co - N.D.	SrCl ₂ - 4.9	Al ₂ S ₃ - .35
Cu - 2.53		CaCO ₃ - 0.27
Fe - 19.34		CrS - 0.15
Pb - 13.00		CuS - 4.04
Li - 0.001	Acid Soluble - 38.5	FeS - 22.52
Mg - 0.29	Al ₂ S ₃ - 0.9	PbS - 8.20
Mn - 1.89	CaCO ₃ - 0.7	MnCO ₃ - 2.19
Ni - 0.11	CrS - 0.4	MgCO ₃ - 0.46
K - 0.08	CuS - 10.5	NiCO ₃ - 0.15
Si - 16.15	FeS - 58.5	Na ₂ SiO ₃ - 0.03
Ag - N.D.	PbS - 21.3	ZnS - 0.12
Na - 0.34	MnCO ₃ - 5.7	Al ₂ O ₃ - 0.91
Sr - N.D.	MgCO ₃ - 1.2	CaSiO ₃ - 0.69
Sn - 0.09	NiCO ₃ - 0.4	CrO - 0.11
Zn - 0.14	Na ₂ SiO ₃ - 0.1	CuO - 0.27
	ZnS - 0.3	Fe ₃ O ₄ - 8.26
		PbO - 7.62
		MgSiO ₃ - 0.27
		MnSiO ₃ - 1.01
	Acid Insoluble - 53.3	NiS - 0.05
	Al ₂ O ₃ - 1.7	SiO ₂ - 33.91
	CaSiO ₃ - 1.3	SnSO ₄ - 0.11
	CrO - 0.2	ZnO - 0.11
	CuO - 0.5	
	Fe ₃ O ₄ - 15.5	
	PbO - 14.3	
	MgSiO ₃ - 0.5	
	MnSiO ₃ - 1.9	
	NiS - 0.1	
	SiO ₂ - 63.6	
	SnSO ₄ - 0.2	
	ZnO - 0.2	

PRO. LINE BETWEEN 1A & 2A
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.58	Water Soluble - 24.1	CaCl ₂ - 5.35
Ba - 0.04	CaCl ₂ - 22.2	LiCl - 0.19
Ca - 1.70	LiCl - 0.8	MgCl ₂ - 0.27
Cr - 0.01	MgCl ₂ - 1.1	MnCl ₂ - 1.47
Co - 0.01	MnCl ₂ - 6.1	KCl - 2.12
Cu - 0.06	KCl - 8.8	NaCl - 14.70
Fe - 18.92	NaCl - 61.0	Al ₂ S ₃ - 0.13
Pb - 1.31		Ca(OH) ₂ - 0.30
Li - 0.02		CrS - 0.05
Mg - 0.40		CuS - 0.20
Mn - 1.58	Acid Soluble - 25.1	FeS - 22.4
Ni - 0.01	Al ₂ S ₃ - 0.5	PbS - 0.18
K - 0.47	Ca(OH) ₂ - 1.2	Mg(OH) ₂ - 0.35
Si - 17.45	CrS - 0.2	Mn(OH) ₂ - 1.36
Ag - 0.01	CuS - 0.8	NiO - 0.03
Na - 3.36	FeS - 89.3	Na ₂ SiO ₃ - 0.03
Sr - N.D.	PbS - 0.7	ZnS - 0.08
Sn - 0.05	Mg(OH) ₂ - 1.4	Al ₂ O ₃ - 0.97
Zn - 0.07	Mn(OH) ₂ - 5.4	BaSO ₄ - 0.05
	NiO - 0.1	CaSiO ₃ - 1.32
	Na ₂ SiO ₃ - 0.1	CoS - 0.05
	ZnS - 0.3	CuO - 0.05
		Fe ₃ O ₄ - 10.23
		PbO - 1.22
		MgSiO ₃ - 0.92
		MnSiO ₃ - 1.48
	Acid Insoluble - 50.9	NiS - 0.05
	Al ₂ O ₃ - 1.9	SiO ₂ - 34.30
	BaSO ₄ - 0.1	Ag ₂ S - 0.05
	CaSiO ₃ - 2.6	SnSO ₄ - 0.05
	CoS - 0.1	ZnO - 0.05
	CuO - 0.1	
	Fe ₃ O ₄ - 20.1	
	PbO - 2.4	
	MgSiO ₃ - 1.8	
	MnSiO ₃ - 2.9	
	NiS - 0.1	
	SiO ₂ - 67.6	
	Ag ₂ S - 0.1	
	SnSO ₄ - 0.1	
	ZnO - 0.1	

LCV - 712
CONTROL VALVE BETWEEN 1A & 2A SEPARATORS
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.71	Water Soluble - 15.2	CaCl ₂ - 1.85
B - N.D.	CaCl ₂ - 12.2	MgCl ₂ - 0.26
Ba - 0.01	MgCl ₂ - 1.7	MnCl ₂ - 0.70
Ca - 0.52	MnCl ₂ - 4.6	KCl - 1.40
Cr - N.D.	KCl - 9.2	NaCl - 10.99
Co - N.D.	NaCl - 72.3	Ca(OH) ₂ - 0.14
Cu - 3.35		CrO - 0.04
Fe - 15.05		CuO - 5.69
Pb - 6.13		Fe ₂ O ₃ - 22.26
Li - N.D.	Acid Soluble - 35.9	PbO - 7.67
Mg - 0.36	Ca(OH) ₂ - 0.4	Mg(OH) ₂ - 0.72
Mn - 2.08	CrO - 0.1	Mn(OH) ₂ - 3.27
Ni - N.D.	CuO - 15.3	K ₂ SiO ₃ - 0.04
K - 0.13	Fe ₂ O ₃ - 62.0	AgCl - 0.04
Si - 18.49	PbO - 10.8	ZnO - 0.09
Ag - 0.04	Mg(OH) ₂ - 2.0	Al ₂ O ₃ - 0.98
Na - 0.68	Mn(OH) ₂ - 9.1	CaSiO ₃ - 0.93
Sr - N.D.	K ₂ SiO ₃ - 0.1	Fe ₃ O ₄ - 6.41
Sn - N.D.	AgCl - 0.1	MgSiO ₃ - 0.24
Zn - 0.05	ZnO - 0.1	MnSiO ₃ - 0.88
		SiO ₂ - 35.4
	Acid Insoluble - 48.9	
	Al ₂ O ₃ - 2.0	
	CaSiO ₃ - 1.9	
	CuO - 0.4	
	Fe ₃ O ₄ - 13.1	
	PbO - 7.8	
	MgSiO ₃ - 0.5	
	MnSiO ₃ - 1.8	
	SiO ₂ - 72.4	
	ZnO - 0.1	

2A SEPARATOR INLET

DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.39	Water Soluble - 13.8	CaCl ₂ - 3.13
B - N.D.	CaCl ₂ - 22.7	CuCl - 0.08
Ba - N.D.	CuCl - 0.6	FeCl ₂ - 0.08
Ca - 0.05	FeCl ₂ - 0.6	MgCl ₂ - 0.73
Cr - 0.01	MgCl ₂ - 5.3	MnCl ₂ - 0.94
Co - 0.01	MnCl ₂ - 6.8	KCl - 1.05
Cu - 0.24	KCl - 7.6	NaCl - 7.58
Fe - 4.33	NaCl - 54.9	SrCl ₂ - 0.08
Pb - 0.05	SrCl ₂ - 0.6	ZnCl ₂ - 0.12
Li - N.D.	ZnCl ₂ - 0.9	Ca(OH) ₂ - 0.07
Mg - 0.10		CuO - 0.34
Mn - 0.28		CrO - 0.01
Ni - 0.01		Fe ₂ O ₃ - 6.17
K - 0.15	Acid Soluble - 6.8	PbO - 0.11
Si - 36.28	Ca(OH) ₂ - 1.1	Mn(OH) ₂ - 0.19
Ag - 0.01	CuO - 2.6	Mg(OH) ₂ - 0.03
Na - 0.78	CrO - 0.2	K ₂ SiO ₃ - 0.01
Sr - 0.01	Fe ₂ O ₃ - 90.8	Na ₂ SiO ₃ - 0.05
Sn - N.D.	PbO - 0.4	ZnO - 0.13
Zn - 0.10	Mn(OH) ₂ - 2.8	Al ₂ O ₃ - 0.71
	Mg(OH) ₂ - 0.4	CaSiO ₃ - 0.48
	K ₂ SiO ₃ - 0.2	Fe ₃ O ₄ - 1.51
	Na ₂ SiO ₃ - 0.7	SiO ₂ - 76.17
	ZnO - 0.8	MgSiO ₃ - 0.08
		MnSiO ₃ - 3.16
	Acid Insoluble - 79.4	
	Al ₂ O ₃ - 0.9	
	CaSiO ₃ - 0.6	
	CuO - 0.2	
	Fe ₃ O ₄ - 1.9	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.2	
	SiO ₂ - 95.9	
	ZnO - 0.1	

2A SEPARATOR - SIDE
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.21	Water Soluble - 25.5	BaCl ₂ - 0.08
Ba - 0.07	BaCl ₂ - 0.3	CaCl ₂ - 11.07
Ca - 2.05	CaCl ₂ - 43.4	LiCl - 0.20
Cr - 0.01	LiCl - 0.8	MgCl ₂ - 0.07
Co - 0.02	MgCl ₂ - 0.3	MnCl ₂ - 0.56
Cu - 0.07	MnCl ₂ - 2.2	KCl - 0.28
Fe - 2.42	KCl - 1.1	NaCl ₂ - 13.06
Pb - 0.14	NaCl ₂ - 51.2	SrCl ₂ - 0.15
Li - 0.02	SrCl ₂ - 0.6	ZnCl ₂ - 0.03
Mg - 0.09	ZnCl ₂ - 0.1	Ba(OH) ₂ - 0.05
Mn - 0.26		Ca(OH) ₂ - 0.23
Ni - 0.02		CrO - 0.02
K - 0.07		CuO - 0.12
Si - 30.90	Acid Soluble - 6.3	Fe ₂ O ₃ - 5.52
Ag - 0.01	Ba(OH) ₂ - 0.8	PbO - 0.19
Na - 2.33	Ca(OH) ₂ - 3.6	Mg(OH) ₂ - 0.05
Sr - 0.05	CrO - 0.3	Mn(OH) ₂ - 0.18
Sn - 0.12	CuO - 0.8	NiO - 0.03
Zn - 0.12	Fe ₂ O ₃ - 87.6	Na ₂ SiO ₃ - 0.03
	PbO - 0.8	ZnO - 0.16
	Mg(OH) ₂ - 0.8	Al ₂ O ₃ - 0.41
	Mn(OH) ₂ - 2.8	BaSO ₄ - 0.07
	NiO - 0.5	CaSiO ₃ - 0.41
	Na ₂ SiO ₃ - 0.5	MgSiO ₃ - 0.27
	ZnO - 1.5	MnSiO ₃ - 0.20
		SiO ₂ - 66.42
		SnSO ₄ - 0.14
	Acid Insoluble - 68.2	
	Al ₂ O ₃ - 0.6	
	BaSO ₄ - 0.1	
	CaSiO ₃ - 0.6	
	CuO - 0.1	
	PbO - 0.2	
	MgSiO ₃ - 0.4	
	MnSiO ₃ - 0.3	
	SiO ₂ - 97.4	
	SnSO ₄ - 0.2	
	ZnO - 0.1	

2A SEPARATOR - TOP
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.09	Water Soluble - 2.7	CaCl ₂ - 0.83
Ba - N.D.	CaCl ₂ - 30.9	MgCl ₂ - 0.04
Ca - 0.34	MgCl ₂ - 1.6	MnCl ₂ - 0.01
Cr - 0.08	MnCl ₂ - 0.8	KCl - 0.28
Co - 0.03	KCl - 10.6	NaCl - 1.51
Cu - 0.04	NaCl - 56.1	CaCO ₃ - 0.22
Fe - 58.18		CrS - 0.07
Pb - 0.16		CuS - 0.07
Li - N.D.		FeS - 70.42
Mg - 0.04	Acid Soluble - 72.7	PbS - 0.15
Mn - 0.80	CaCO ₃ - 0.3	MgCO ₃ - 0.07
Ni - 0.03	CrS - 0.1	MnCO ₃ - 1.10
K - 0.07	CuS - 0.1	Na ₂ SiO ₃ - 0.07
Si - 4.59	FeS - 96.9	ZnS - 0.51
Ag - N.D.	PsB - 0.2	Al ₂ O ₃ - 0.14
Na - 0.29	MgCO ₃ - 0.1	CaSiO ₃ - 0.12
Sr - N.D.	MnCO ₃ - 1.5	CrO - 0.02
Sn - 0.07	Na ₂ SiO ₃ - 0.1	CoS - 0.02
Zn - 0.37	ZnS - 0.7	Fe ₃ O ₄ - 16.01
		PbO - 0.02
		MgSiO ₃ - 0.02
		MgSiO ₃ - 0.05
		NiS - 0.02
		SiO ₂ - 8.07
		SnSO ₄ - 0.05
		ZnO - 0.02
	Acid Insoluble - 24.6	
	Al ₂ O ₃ - 0.6	
	CaSiO ₃ - 0.5	
	CrO - 0.1	
	CoS - 0.1	
	Fe ₃ O ₄ - 65.1	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.2	
	NiS - 0.1	
	SiO ₂ - 32.8	
	SnSO ₄ - 0.2	
	ZnO - 0.1	

2A SEPARATOR - BOTTOM OUTLET

DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.14	Water Soluble - 37.7	BaCl ₂ - 0.11
Ba - 0.06	BaCl ₂ - 0.3	CaCl ₂ - 14.29
Ca - 2.98	CaCl ₂ - 37.9	LiCl - 0.26
Cr - N.D.	LiCl - 0.7	MgCl ₂ - 0.08
Co - N.D.	MgCl ₂ - 0.2	MnCl ₂ - 0.30
Cu - 0.04	MnCl ₂ - 0.8	KCl - 3.69
Fe - 1.45	KCl - 9.8	NaCl - 18.77
Pb - 0.11	NaCl - 49.8	SrCl ₂ - 0.19
Li - 0.02	SrCl ₂ - 0.5	Ba(OH) ₂ - 0.04
Mg - 0.06		Ca(OH) ₂ - 0.21
Mn - 0.19		CuO - 0.10
Ni - 0.02		Fe ₂ O ₃ - 2.37
K - 1.05	Acid Soluble - 3.0	PbO - 0.16
Si - 25.58	Ba(OH) ₂ - 1.3	Mg(OH) ₂ - 0.18
Ag - N.D.	Ca(OH) ₂ - 7.0	Mn(OH) ₂ - 0.15
Na - 4.01	CuO - 1.3	Na ₂ SiO ₃ - 0.02
Sr - 0.01	Fe ₂ O ₃ - 79.0	ZnO - 0.11
Sn - 0.14	PbO - 1.3	Al ₂ O ₃ - 0.30
Zn - 0.09	Mg(OH) ₂ - 0.6	CaSiO ₃ - 0.36
	Mn(OH) ₂ - 5.1	Fe ₃ O ₄ - 0.83
	Na ₂ SiO ₃ - 0.6	MgSiO ₃ - 0.18
	ZnO - 3.8	MnSiO ₃ - 0.18
		NiO - 0.06
		SiO ₂ - 56.94
		SnSO ₄ - 0.12
	Acid Insoluble - 59.3	
	Al ₂ O ₃ - 0.5	
	CaSiO ₃ - 0.6	
	CuO - 0.1	
	Fe ₃ O ₄ - 1.4	
	PbO - 0.2	
	MgSiO ₃ - 0.3	
	MnSiO ₃ - 0.3	
	NiO - 0.1	
	SiO ₂ - 96.2	
	SnSO ₄ - 0.2	
	ZnO - 0.1	

2A SEPARATOR DISCHARGE NEAR GRAY VALVE
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.26	Water Soluble - 17.0	BaCl ₂ - 0.03
B - N.D.	BaCl ₂ - 0.2	CaCl ₂ - 4.91
Ba - 0.06	CaCl ₂ - 28.9	LiCl - 0.15
Ca - 0.71	LiCl - 0.9	MgCl ₂ - 0.03
Cr - N.D.	MgCl ₂ - 0.2	MnCl ₂ - 0.49
Co - N.D.	MnCl ₂ - 2.9	KCl - 1.56
Cu - 0.09	KCl - 9.2	NaCl - 9.74
Fe - 1.57	NaCl - 57.3	SrCl ₂ - 0.07
Pb - 0.26	SrCl ₂ - 0.4	Ba(OH) ₂ - 0.07
Li - 0.01		Ca(OH) ₂ - 0.20
Mg - 0.06		CuO - 0.17
Mn - 0.17		Fe ₂ O ₃ - 2.78
Ni - N.D.	Acid Soluble - 3.5	PbO - 0.13
K - 0.23	Ba(OH) ₂ - 1.9	Mg(OH) ₂ - 0.04
Si - 39.13	Ca(OH) ₂ - 5.6	Mn(OH) ₂ - 0.17
Ag - N.D.	CuO - 2.5	Na ₂ SiO ₃ - 0.02
Na - 1.08	Fe ₂ O ₃ - 79.4	SrO - 0.02
Sr - 0.02	PbO - 1.3	ZnO - 0.15
Sn - 0.10	Mg(OH) ₂ - 1.2	Al ₂ O ₃ - 0.48
Zn - 0.06	Mn(OH) ₂ - 5.0	BaSO ₄ - 0.08
	Na ₂ SiO ₃ - 0.6	CaSiO ₃ - 0.40
	SrO - 0.6	Fe ₃ O ₄ - 0.87
	ZnO - 1.9	MgSiO ₃ - 0.16
		MnSiO ₃ - 0.08
		SiO ₂ - 77.12
		SnSO ₄ - 0.08
	Acid Insoluble - 79.5	
	Al ₂ O ₃ - 0.6	
	BaSO ₄ - 0.1	
	CaSiO ₃ - 0.5	
	CuO - 0.1	
	Fe ₃ O ₄ - 1.1	
	PbO - 0.1	
	MgSiO ₃ - 0.2	
	MnSiO ₃ - 0.1	
	SiO ₂ - 97.0	
	SnSO ₄ - 0.1	
	ZnO - 0.1	

GRAY VALVE
BETWEEN 2A SEPARATOR AND ATMOSPHERIC FLASH

DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.17	Water Soluble - 12.3	CaCl ₂ - 0.32
B - N.D.	CaCl ₂ - 2.6	MnCl ₂ - 0.70
Ba - 0.08	MnCl ₂ - 5.7	KCl - 1.56
Ca - 0.24	KCl - 12.7	NaCl - 9.64
Cr - N.D.	NaCl - 78.4	ZnCl ₂ - 0.07
Co - N.D.	ZnCl ₂ - 0.6	Ba(OH) ₂ - 0.10
Cu - 0.12		Ca(OH) ₂ - .19
Fe - 1.77		CuO - .18
Pb - 0.29		Fe ₂ O ₃ - 3.26
Li - N.D.	Acid Soluble - 4.3	PbO - 0.14
Mg - 0.04	Ba(OH) ₂ - 2.4	Mg(OH) ₂ - 0.04
Mn - 0.23	Ca(OH) ₂ - 4.4	Mn(OH) ₂ - 0.35
Ni - N.D.	CuO - 2.4	K ₂ SiO ₃ - 0.02
K - 0.11	Fe ₂ O ₃ - 75.7	Na ₂ SiO ₃ - 0.04
Si - 38.92	PbO - 1.5	SiO - 0.02
Ag - N.D.	Mg(OH) ₂ - 1.0	ZnO - 0.18
Na - 0.49	Mn(OH) ₂ - 8.2	Al ₂ O ₃ - 0.03
Sr - 0.01	K ₂ SiO ₃ - 0.5	BaSO ₄ - 0.08
Sn - N.D.	Na ₂ SiO ₃ - 1.0	CaSiO ₃ - 0.50
Zn - 0.10	SrO - 0.5	Fe ₃ O ₄ - 0.92
	ZnO - 2.4	MgSiO ₃ - 0.08
		MnSiO ₃ - 0.17
		SiO ₂ - 81.41
	Acid Insoluble - 83.4	
	Al ₂ O ₃ - 0.4	
	BaSO ₄ - 0.1	
	CaSiO ₃ - 0.6	
	CuO - 0.1	
	Fe ₃ O ₄ - 1.1	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.2	
	SiO ₂ - 97.2	
	ZnO - 0.1	

SLUDGE FROM CLARIFIER
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.09	Water Soluble - 8.1	CaCl ₂ - 4.28
B - N.D.	CaCl ₂ - 52.8	MnCl ₂ - 0.23
Ba - 0.18	MnCl ₂ - 2.8	KCl - 0.67
Ca - 1.01	KCl - 8.3	NaCl - 2.70
Cr - N.D.	NaCl - 33.3	SrCl ₂ - 0.23
Co - N.D.	SrCl ₂ - 2.8	Ba(OH) ₂ - 0.32
Cu - 0.29		Ca(OH) ₂ - 2.32
Fe - 3.80		CuS - 0.41
Pb - 0.42		FeS - 6.47
Li - N.D.	Acid Soluble - 10.5	PbS - 0.43
Mg - 0.03	Ba(OH) ₂ - 3.0	Mn(OH) ₂ - 0.22
Mn - 0.13	Ca(OH) ₂ - 22.1	Mg(OH) ₂ - 0.02
Ni - 0.01	CuS - 3.9	K ₂ SiO ₃ - 0.05
K - 0.04	FeS - 61.6	Na ₂ SiO ₃ - 0.02
Si - 41.40	PbS - 4.1	SrO - 0.05
Ag - 0.01	Mn(OH) ₂ - 2.1	ZnS - 0.19
Na - 0.10	Mg(OH) ₂ - 0.2	Al ₂ O ₃ - 0.16
Sr - 0.03	K ₂ SiO ₃ - 0.5	BaSO ₄ - 0.08
Sn - N.D.	Na ₂ SiO ₃ - 0.2	CaSiO ₃ - 0.41
Zn - 0.11	SrO - 0.5	CuO - 0.16
	ZnS - 1.8	Fe ₃ O ₄ - 2.44
		PbO - 0.24
		MgSiO ₃ - 0.08
		MnSiO ₃ - 0.16
		SiO ₂ - 77.58
		ZnO - 0.08
	Acid Insoluble - 81.4	
	Al ₂ O ₃ - 0.2	
	BaSO ₄ - 0.1	
	CaSiO ₃ - 0.5	
	CuO - 0.2	
	Fe ₃ O ₄ - 3.0	
	PbO - 0.3	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.2	
	SiO ₂ - 95.3	
	ZnO - 0.1	

INJECTION LINE AT LLL

DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.08	Water Soluble - 35.4	BaCl ₂ - 0.07
B - N.D.	BaCl ₂ - 0.2	CaCl ₂ - 11.01
Ba - 0.72	CaCl ₂ - 31.1	LiCl - 0.18
Ca - 4.76	LiCl - 0.5	MgCl ₂ - 0.07
Cr - N.D.	MgCl ₂ - 0.2	MnCl ₂ - 0.35
Co - N.D.	MnCl ₂ - 1.0	KCl - 2.62
Cu - 0.02	KCl - 7.4	NaCl - 20.96
Fe - 2.25	NaCl - 59.2	SrCl ₂ - 0.14
Pb - 0.40	SrCl ₂ - 0.4	Al ₂ (SO ₄) ₃ - 0.07
Li - 0.02		Ba(OH) ₂ - 1.19
Mg - 0.40		Ca(OH) ₂ - 8.93
Mn - 1.71		CoO - 0.02
Ni - N.D.	Acid Soluble - 22.5	CuO - 0.44
K - 0.77	Al ₂ (SO ₄) ₃ - 0.3	Fe ₂ O ₃ - 4.86
Si - 23.09	Ba(OH) ₂ - 5.3	PbO - 0.85
Ag - 0.01	Ca(OH) ₂ - 39.7	Mn(OH) ₂ - 5.22
Na - 4.53	CoO - 0.1	Mg(OH) ₂ - 0.11
Sr - 0.08	CuO - 1.6	K ₂ SiO ₃ - 0.09
Sn - N.D.	Fe ₂ O ₃ - 21.6	Na ₂ SiO ₃ - 0.20
Zn - 0.25	PbO - 3.0	SrO - 0.14
	Mn(OH) ₂ - 23.2	ZnO - 0.71
	Mg(OH) ₂ - 0.5	Al ₂ O ₃ - 0.08
	K ₂ SiO ₃ - 0.4	BaSO ₄ - 0.38
	Na ₂ SiO ₃ - 0.9	CaSiO ₃ - 0.34
	SrO - 0.6	Fe ₃ O ₄ - 1.14
	ZnO - 2.8	MgSiO ₃ - 0.04
		MnSiO ₃ - 0.07
		SiO ₂ - 39.72
	Acid Insoluble - 42.1	
	Al ₂ O ₃ - 0.2	
	BaSO ₄ - 0.9	
	CaSiO ₃ - 0.8	
	CuO - 0.2	
	Fe ₃ O ₄ - 2.7	
	PbO - 0.4	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.4	
	SiO ₂ - 94.1	
	ZnO - 0.2	

INJECTION LINE BY BAKER TANKS
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.03	Water Soluble - 24.8	BaCl ₂ - 0.07
B - N.D.	BaCl ₂ - 0.3	CaCl ₂ - 8.53
Ba - 0.86	CaCl ₂ - 34.4	PbCl ₂ - 0.87
Ca - 2.68	PbCl ₂ - 3.5	LiCl - 0.12
Cr - N.D.	LiCl - 0.5	MnCl ₂ - 0.12
Co - N.D.	MnCl ₂ - 0.5	MgCl ₂ - 0.02
Cu - 0.09	MgCl ₂ - 0.1	KCl - 1.54
Fe - 0.48	KCl - 6.2	NaCl - 13.39
Pb - 5.35	NaCl - 54.0	SrCl ₂ - 0.10
Li - 0.01	SrCl ₂ - 0.4	ZnCl ₂ - 0.02
Mg - 0.02	ZnCl ₂ - 0.1	Ba(OH) ₂ - 1.49
Mn - 0.08		Ca(OH) ₂ - 2.07
Ni - N.D.		CuO - 0.15
K - 0.52		Fe ₂ O ₃ - 0.84
Si - 24.31	Acid Soluble - 15.9	PbO - 11.65
Ag - 0.01	Ba(OH) ₂ - 9.4	Mn(OH) ₂ - 1.10
Na - 3.31	Ca(OH) ₂ - 13.0	K ₂ SiO ₃ - 0.08
Sr - 0.10	CuO - 0.6	AgCl - 0.19
Sn - N.D.	Fe ₂ O ₃ - 5.3	Na ₂ SiO ₃ - 0.37
Zn - 0.04	PbO - 65.8	SrO - 0.17
	Mn(OH) ₂ - 0.6	ZnO - 0.03
	K ₂ SiO ₃ - 0.5	Al ₂ O ₃ - 0.06
	AgCl - 1.2	BaSO ₄ - 0.53
	Na ₂ SiO ₃ - 2.3	CaSiO ₃ - 0.59
	SrO - 1.1	Fe ₃ O ₄ - 0.36
	ZnO - 0.2	MgSiO ₃ - 0.06
		MnSiO ₃ - 0.06
		SiO ₂ - 56.36
		SrSO ₄ - 0.06
	Acid Insoluble - 59.3	
	Al ₂ O ₃ - 0.1	
	BaSO ₄ - 0.9	
	CaSiO ₃ - 1.0	
	CuO - 0.1	
	Fe ₃ O ₄ - 0.6	
	PbO - 2.0	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.1	
	SiO ₂ - 95.0	
	SrSO ₄ - 0.1	

1A SCRUBBER (BOTTOM)
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.05	Water Soluble - 0.3	CaCl ₂ - 0.11
B - N.D.	CaCl ₂ - 38.1	MnCl ₂ - 0.01
Ba - N.D.	MnCl ₂ - 1.6	KCl - 0.02
Ca - 0.26	KCl - 6.3	NaCl - 0.16
Cr - 0.09	NaCl - 52.4	ZnCl ₂ - 0.01
Co - N.D.	ZnCl ₂ - 1.6	CaCO ₃ - 0.07
Cu - 0.04		CrS - 0.07
Fe - 47.00		CuS - 0.07
Pb - 0.37		FeS - 32.34
Li - N.D.	Acid Soluble - 34.5	PbS - 0.41
Mg - 0.03	CaCO ₃ - 0.2	MgCO ₃ - 0.03
Mn - 0.39	CrS - 0.2	MnCO ₃ - 0.59
Ni - 0.04	CuS - 0.2	NiO - 0.03
K - 0.02	FeS - 93.8	ZnS - 0.86
Si - 2.64	PbS - 1.2	Al ₂ O ₃ - 0.13
Ag - N.D.	MgCO ₃ - 0.1	CaSiO ₃ - 0.52
Na - 0.14	MnCO ₃ - 1.7	CrO - 0.13
Sr - N.D.	NiO - 0.1	Fe ₃ O ₄ - 56.6
Sn - 0.08	ZnS - 2.5	PbO - 0.07
Zn - 0.54		MgSiO ₃ - 0.07
		MnSiO ₃ - 0.07
		NiS - 0.07
		SiO ₂ - 7.30
		SnSO ₄ - 0.13
		ZnO - 0.13
	Acid Insoluble - 65.2	
	Al ₂ O ₃ - 0.2	
	CaSiO ₃ - 0.8	
	CrO - 0.2	
	Fe ₃ O ₄ - 86.8	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.1	
	NiS - 0.1	
	SiO ₂ - 11.2	
	SnSO ₄ - 0.2	
	ZnO - 0.2	

1A SCRUBBER (2ND TRAY)
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.04	Water Soluble - 0.3	CaCl ₂ - 0.08
B - N.D.	CaCl ₂ - 25.0	PbCl ₂ - 0.03
Ba - N.D.	PbCl ₂ - 9.4	MnCl ₂ - 0.04
Ca - 0.10	MnCl ₂ - 12.5	NaCl - 0.05
Cr - 0.07	NaCl - 15.6	ZnCl ₂ - 0.11
Co - N.D.	ZnCl ₂ - 37.5	CrS - 0.04
Cu - 0.02		CuS - 0.04
Fe - 51.18		FeS - 34.75
Pb - 1.02		PbS - 0.14
Li - N.D.	Acid Soluble - 35.9	MnCO ₃ - 0.29
Mg - 0.02	CrS - 0.1	NiO - 0.04
Mn - 0.25	CuS - 0.1	ZnS - 0.61
Ni - 0.05	FeS - 96.8	Al ₂ O ₃ - 0.13
K - N.D.	PbS - 0.4	CaSiO ₃ - 0.26
Si - 2.47	MnCO ₃ - 0.8	CrO - 0.13
Ag - N.D.	NiO - 0.1	Fe ₃ O ₄ - 56.31
Na - 0.02	ZnS - 1.7	PbO - 0.06
Sr - N.D.		MgSiO ₃ - 0.06
Sn - 0.10		MnSiO ₃ - 0.19
Zn - 0.48		NiS - 0.06
	Acid Insoluble - 63.8	SiO ₂ - 6.32
	Al ₂ O ₃ - 0.2	SnSO ₄ - 0.13
	CaSiO ₃ - 0.4	ZnO - 0.13
	CrO - 0.2	
	Fe ₃ O ₄ - 88.3	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.3	
	NiS - 0.1	
	SiO ₂ - 9.9	
	SnSO ₄ - 0.2	
	ZnO - 0.2	

2A SCRUBBER (BOTTOM)
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.43	Water Soluble - 9.5	CaCl ₂ - 0.39
B - N.D.	CaCl ₂ - 4.1	MgCl ₂ - 0.08
Ba - 0.03	MgCl ₂ - 0.8	MnCl ₂ - 0.25
Ca - 0.24	MnCl ₂ - 2.6	KCl - 0.13
Cr - 0.09	KCl - 1.4	NaCl - 8.54
Co - N.D.	NaCl - 89.9	SrCl ₂ - 0.08
Cu - 0.04	SrCl ₂ - 0.8	ZnCl ₂ - 0.04
Fe - 46.74	ZnCl ₂ - 0.4	Al ₂ S ₃ - 0.12
Pb - 0.28		CaCO ₃ - 0.17
Li - N.D.		CrS - 0.12
Mg - 0.06		CuS - 0.06
Mn - 0.85	Acid Soluble - 57.8	FeS - 53.8
Ni - 0.05	Al ₂ S ₃ - 0.2	PbS - 0.17
K - 0.03	CaCO ₃ - 0.3	MgCO ₃ - 0.06
Si - 7.36	CrS - 0.2	MnCO ₃ - 1.04
Ag - N.D.	CuS - 0.1	NiO - 0.06
Na - 0.97	FeS - 95.7	Na ₂ SiO ₃ - 0.06
Sr - 0.01	PbS - 0.3	ZnS - 0.63
Sn - 0.10	MgCO ₃ - 0.1	Al ₂ O ₃ - 0.65
Zn - 0.47	MnCO ₃ - 1.8	BaSO ₄ - 0.33
	NiO - 0.1	CaSiO ₃ - 0.23
	Na ₂ SiO ₃ - 0.1	CrO - 0.03
	ZnS - 1.1	Fe ₂ O ₃ - 17.23
		PbO - 0.13
		MgSiO ₃ - 0.10
		MnSiO ₃ - 1.31
		NiS - 0.03
		SiO ₂ - 14.00
		SnSO ₄ - 0.07
		ZnO - 0.07
	Acid Insoluble - 32.7	
	Al ₂ O ₃ - 2.0	
	BaSO ₄ - 0.1	
	CaSiO ₃ - 0.7	
	CrO - 0.1	
	Fe ₂ O ₃ - 52.7	
	PbO - 0.4	
	MgSiO ₃ - 0.3	
	MnSiO ₃ - 0.4	
	NiS - 0.1	
	SiO ₂ - 42.8	
	SnSO ₄ - 0.2	
	ZnO - 0.2	

2A SCRUBBER (3RD TRAY)
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.06	Water Soluble - 9.2	CaCl ₂ - 0.36
B - N.D.	CaCl ₂ - 3.9	MgCl ₂ - 0.07
Ba - 0.02	MgCl ₂ - 0.8	MnCl ₂ - 0.53
Ca - 0.19	MnCl ₂ - 5.8	KCl - 0.10
Cr - 1.00	KCl - 1.1	NaCl - 8.06
Co - N.D.	NaCl - 87.6	SrCl ₂ - 0.04
Cu - N.D.	SrCl ₂ - 0.4	ZnCl ₂ - 0.04
Fe - 46.98	ZnCl ₂ - 0.4	CaCO ₃ - 0.15
Pb - 0.02		CrS - 0.10
Li - N.D.		FeS - 48.54
Mg - 0.04		PbS - 0.20
Mn - 0.75	Acid Soluble - 50.3	MnCO ₃ - 0.80
Ni - 0.04	CaCO ₃ - 0.3	Na ₂ SiO ₃ - 0.05
K - 0.02	CrS - 0.2	ZnS - 0.45
Si - 4.90	FeS - 96.5	Al ₂ O ₃ - 0.12
Ag - N.D.	PbS - 0.4	BaSO ₄ - 0.04
Na - 0.91	MnCO ₃ - 1.6	CaSiO ₃ - 0.20
Sr - 0.01	Na ₂ SiO ₃ - 0.1	CrO - 0.08
Sn - 0.13	ZnS - 0.9	Fe ₃ O ₄ - 28.09
Zn - 0.35		PbO - 0.04
		MgSiO ₃ - 0.08
		MnSiO ₃ - 0.24
		NiS - 0.04
		SiO ₂ - 11.34
		SnSO ₄ - 0.16
		ZnO - 0.08
	Acid Insoluble - 40.5	
	Al ₂ O ₃ - 0.3	
	BaSO ₄ - 0.1	
	CaSiO ₃ - 0.5	
	CrO - 0.2	
	Fe ₃ O ₄ - 69.3	
	PbO - 0.1	
	MgSiO ₃ - 0.2	
	MnSiO ₃ - 0.6	
	NiS - 0.1	
	SiO ₂ - 28.0	
	SnSO ₄ - 0.4	
	ZnO - 0.2	

2A SCRUBBER - TOP
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.02	Water Soluble - 26.2	CaCl ₂ - 9.72
Ba - N.D.	CaCl ₂ - 37.1	KCl - 2.38
Ca - 7.5	KCl - 9.1	NaCl - 14.10
Cr - 0.04	NaCl - 53.8	Al ₂ S ₃ - 0.07
Co - N.D.		CaCO ₃ - 15.35
Cu - 0.02		CrS - 0.07
Fe - 21.15		CuS - 0.07
Pb - 0.11	Acid Soluble - 73.8	FeS - 45.92
Li - N.D.	Al ₂ S ₃ - 0.1	PbS - 0.22
Mg - 0.02	CaCO ₃ - 20.8	MnCO ₃ - 9.08
Mn - 4.66	CrS - 0.1	Na ₂ SiO ₃ - 0.07
Ni - 0.01	CuS - 0.1	ZnS - 2.95
K - 0.09	FeS - 62.2	
Si - 0.49	PbS - 0.3	
Ag - N.D.	MnCO ₃ - 12.3	
Na - 0.44	Na ₂ SiO ₃ - 0.1	
Sr - 0.02	ZnS - 4.0	
Sn - N.D.		
Zn - 1.56		

2A HEAT EXCHANGER
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - N.D.	Water Soluble - 40.4	CaCl ₂ - 26.30
B - N.D.	CaCl ₂ - 65.1	KCl - 0.65
Ba - N.D.	KCl - 1.6	NaCl - 12.81
Ca - 16.32	NaCl - 31.7	ZnCl ₂ - 0.65
Cr - N.D.	ZnCl ₂ - 1.6	CaCO ₃ - 43.50
Co - N.D.		FeS - 5.18
Cu - N.D.		PbS - 0.06
Fe - 2.01		MgCO ₃ - 0.06
Pb - 0.02	Acid Soluble - 59.6	MnCO ₃ - 6.20
Li - N.D.	CaCO ₃ - 73.0	Na ₂ SiO ₃ - 0.06
Mg - 0.01	FeS - 8.7	SrCO ₃ - 0.24
Mn - 2.98	PbS - 0.1	ZnS - 4.29
Ni - N.D.	MgCO ₃ - 0.1	
K - 0.01	MnCO ₃ - 10.4	
Si - 0.16	Na ₂ SiO ₃ - 0.4	
Ag - N.D.	ZnS - 7.2	
Na - 0.10		
Sr - 0.11		
Sn - N.D.		
Zn - 1.75		

2B HEAT EXCHANGER
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - N.D.	Water Soluble - 43.8	CaCl ₂ - 35.74
B - N.D.	CaCl ₂ - 81.6	NaCl - 4.60
Ba - 0.01	NaCl - 10.5	SrCl ₂ - 2.32
Ca - 17.76	SrCl ₂ - 5.3	ZnCl ₂ - 1.14
Cr - N.D.	ZnCl ₂ - 2.6	CaCO ₃ - 51.25
Co - N.D.		FeS - 1.69
Cu - N.D.		MnCO ₃ - 2.02
Fe - 0.52		Na ₂ SiO ₃ - 0.12
Pb - N.D.	Acid Soluble - 56.2	SrCO ₃ - 0.73
Li - N.D.	CaCO ₃ - 91.2	ZnS - 0.39
Mg - N.D.	FeS - 3.0	
Mn - 0.74	MnCO ₃ - 3.6	
Ni - N.D.	Na ₂ SiO ₃ - 0.2	
K - N.D.	SrCO ₃ - 1.3	
Si - 0.07	ZnS - 0.7	
Ag - N.D.		
Na - 0.03		
Sr - 0.31		
Sn - N.D.		
Zn - 0.14		

EAST CONDENSER
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.27	Water Soluble - 17.0	CaCl ₂ - 5.42
Ba - N.D.	CaCl ₂ - 31.9	FeCl ₂ - 6.14
Ca - 0.15	FeCl ₂ - 36.1	MgCl ₂ - 1.41
Cr - 0.08	MgCl ₂ - 8.3	MnCl ₂ - 1.89
Co - 0.02	MnCl ₂ - 11.1	NaCl - 0.95
Cu - N.D.	NaCl - 5.6	SrCl ₂ - 0.24
Fe - 35.41	SrCl ₂ - 1.4	ZnCl ₂ - 0.95
Pb - 0.06	ZnCl ₂ - 5.6	CaCO ₃ - 0.07
Li - N.D.		CrO - 0.15
Mg - 0.09		Fe ₂ O ₃ - 69.78
Mn - 0.05		PbO - 0.13
Ni - 0.05	Acid Soluble - 70.5	MgCO ₃ - 0.14
K - 0.02	CaCO ₃ - 0.1	MnCO ₃ - 0.07
Si - 0.85	CrO - 0.2	NiCO ₃ - 0.07
Ag - N.D.	Fe ₂ O ₃ - 99.0	K ₂ SiO ₃ - 0.07
Na - 0.02	PbO - 0.1	ZnO - 0.10
Sr - 0.01	MgCO ₃ - 0.2	Al ₂ O ₃ - 0.71
Sn - 0.09	MnCO ₃ - 0.1	CaSiO ₃ - 0.18
Zn - 0.06	NiCO ₃ - 0.1	CoO - 0.03
	K ₂ SiO ₃ - 0.1	Fe ₃ O ₄ - 8.95
	ZnO - 0.1	MgSiO ₃ - 0.08
		NiO - 0.04
		SiO ₂ - 2.29
		SnSO ₄ - 0.14
	Acid Insoluble - 12.5	
	Al ₂ O ₃ - 5.7	
	CaSiO ₃ - 1.4	
	CrO - 0.1	
	CoO - 0.2	
	Fe ₃ O ₄ - 71.6	
	PbO - 0.5	
	MgSiO ₃ - 0.6	
	NiO - 0.3	
	SiO ₂ - 18.3	
	SnSO ₄ - 1.1	
	ZnO - 0.2	

WEST CONDENSER
DATE: 3-21-79

Wt. %	% Fraction	% Total Scale
Al - 0.31	Water Soluble - 17.0	CaCl ₂ - 6.12
B - N.D.	CaCl ₂ - 36.0	FeCl ₂ - 5.44
Ba - N.D.	FeCl ₂ - 32.0	PbCl ₂ - 0.22
Ca - 0.16	PbCl ₂ - 1.3	MgCl ₂ - 1.36
Cr - 0.02	MgCl ₂ - 8.0	MnCl ₂ - 1.58
Co - N.D.	MnCl ₂ - 9.3	KCl - 0.22
Cu - 0.01	KCl - 1.3	NaCl - 1.37
Fe - 39.12	NaCl - 8.1	ZnCl - 0.68
Pb - 0.04	ZnCl - 4.0	Ca(OH) ₂ - 0.07
Li - N.D.		Fe ₂ O ₃ - 65.78
Mg - 0.08		Mg(OH) ₂ - 0.13
Mn - 0.05		K ₂ SiO ₃ - 0.07
Ni - N.D.	Acid Soluble - 66.1	NaSiO ₃ - 0.07
K - 0.02	Ca(OH) ₂ - 0.1	Al ₂ O ₃ - 1.47
Si - 2.86	Fe ₂ O ₃ - 99.5	CaSiO ₃ - 0.22
Ag - N.D.	Mg(OH) ₂ - 0.2	CuO - 0.03
Na - 0.04	K ₂ SiO ₃ - 0.1	Fe ₃ O ₄ - 0.35
Sr - N.D.	Na ₂ SiO ₃ - 0.1	PbO - 0.08
Sn - N.D.		MgSiO ₃ - 0.10
Zn - 0.32		SiO ₂ - 14.64
	Acid Insoluble - 16.9	
	Al ₂ O ₃ - 8.7	
	CaSiO ₃ - 1.3	
	CuO - 0.2	
	Fe ₃ O ₄ - 2.1	
	PbO - 0.5	
	MgSiO ₃ - 0.6	
	SiO ₂ - 86.6	

APPENDIX G

Bechtel National, Inc.
Engineers—Constructors

Fifty Beale Street
San Francisco, California

Mail Address: P.O. Box 3965, San Francisco, CA 94119

RECEIVED
San Diego Gas & Electric Company

MAR 12 1979

GEOTHERMAL SECTION

March 8, 1979

Mr. W. O. Jacobson
San Diego Gas & Electric Company
P.O. Box 1831
San Diego, California 92112

Subject: Report on fractured pump shaft.
Contract GTF-00166
Bechtel Job No. 12094-001.

Dear Bill:

Complying with your instructions, the portion of the fractured P-2 pump shaft, which Chuck Madsen brought back from the GLEF, was delivered to Frank Locke, of George Tardiff's group at LLL.

Madsen's report, a copy of which is enclosed herewith, concludes that from visual inspection of the fracture area and from a consideration of the circumstances of the failure, the fracture appears to have occurred in a ductile torsional mode.

We are awaiting comments from LLL as to their conclusions.

Sincerely,

al

A. N. Rogers
Project Engineer

ANR:mw
cc. T.R. Fick
A.C. Madsen

Letter File No. ACM-029-15
Date: February 28, 1979

MATERIALS & QUALITY SERVICES

☒ **TRIP REPORT** ☐ **FAILURE ANALYSIS** ☐ **PROBLEMS** ☐ **OTHER:** _____

TO: T. R. Fick **FROM:** A. C. Madsen

COPIES TO: R. C. Bertossa _____
A. N. Rogers _____
G. R. Schmidt/J. E. Drennan _____
R. A. White _____
DCC (015151) _____
Distribution MC _____

PROJECT NO. 12094.001 **PROJECT NAME:** Niland Geothermal Test Facility

SPEC. NO. N/A **DATE OF TRIP:** 2-12-79 to 2-12-79

DESTINATION OF TRIP: San Diego Gas and Electric Co.'s machine shop
in San Diego, CA

COMPONENTS INVOLVED (INCLUDING MATERIALS): Hastelloy C pump shaft

PURPOSE OF TRIP (DESCRIPTION OF PROBLEM): On February 9, 1979, the Hastelloy C
shaft on the brine reinjection pump (P-2 pump) at Niland failed after 59 hours
of service. We were requested to inspect the broken shaft and to determine
the cause of failure.

Date: February 28, 1979

MATERIALS & QUALITY SERVICES

☒ TRIP REPORT ☐ FAILURE ANALYSIS ☐ PROBLEMS ☐ OTHER: _____
(CONTINUED)

PRESENT AT DISCUSSION:

**BECHTEL
REPRESENTATIVES**

A. C. Madsen

**OTHERS (INCLUDING
AFFILIATIONS & POSITIONS)**

W. O. Jacobsen, SDE&G

CONCLUSIONS AND RECOMMENDATIONS:

The shaft failure appears to be related to pump design problems. The bronze bearing adjacent to the fracture became "welded" to the shaft and the shaft then fractured in a ductile torsional mode. The "welding" of the shaft and bearing were caused by overheating of the bearing and shaft surfaces. The overheating was apparently caused by an insufficient amount of water flowing within the bearing-shaft annulus and/or leakage of scale into this annulus.

DETAILS OF INVESTIGATION (DISCUSSION OF OBSERVATIONS ACTION TAKEN AND OTHER PERTINENT DATA):

see page 3 ff

Trip Report
Letter File No. ACM-029-15
Date: February 28, 1979
Page 3

DETAILS OF INVESTIGATION (DISCUSSION OF OBSERVATIONS, ACTION TAKEN AND OTHER PERTINENT DATA):

The vertical brine reinjection pump at Niland has a history of shaft failures. The original K-Monel shaft failed just above the fourth impeller (from the suction end) after approximately three months service. The second failure on this shaft occurred at the ninth impeller in the shaft bearing approximately one week after the first failure.

The K-Monel shaft was replaced by a 17-4 PH stainless steel shaft (H 900 condition) which also experienced several failures. The cause of one failure was attributed to stress corrosion cracking. Therefore, a new shaft consisting of Hastelloy C in the impeller region (i.e., it extends to approximately one foot above the ninth or top impeller) was mechanically coupled to the upper portion of the old 17-4 PH shaft. (The Hastelloy C section of the shaft consisted of two Hastelloy C bars welded together.) After 59 hours and 30 minutes of operating time, the Hastelloy C section of shaft broke in half within the upper bearing near the ninth (i.e., the top) impeller. This is reportedly the same area where the old 17-4 PH shaft broke on January 31, 1979. A sketch and photographs of the break location and bearing system are shown in Figures 1 through 5. Photographs of the fracture surfaces are shown in Figures 2 and 3.

Inspection of the break area showed that the upper bearing adjacent to the break had fractured in two and that the upper half of this bearing had been "welded" to the shaft (see Figures 1 and 4). The lower part of this bearing and the lower bearing would still rotate freely on the shaft. However, each exhibited a degree of roughness on its inside diameter. The lower half of the fractured bearing was discolored (see Figure 4) while the lower bearing was still shiny and copper colored.

The design of the pump is such that water used for lubrication and cooling is injected between the upper and lower bearing (at each bearing location on the shaft). (The water inlets are shown in Figure 6.) The water is injected at a pressure 50 psi greater than the pump pressure. This pressure is reportedly monitored by flow meters and pressure gages. Theoretically, the water is supposed to flow within the 0.010 to 0.012 inch annulus between the shaft and both the upper and lower bearings.

Inspection of the shaft showed that most of the bearings were not adequately cooled and/or lubricated. The condition of the shaft at bearing locations varied from very minor surface roughness (lower end of shaft) to severely grooved. The shaft was severely grooved adjacent to the fracture in the Hastelloy C section (see Figure 3) and under the upper set of bearings in the 17-4 PH section of bearings were severely grooved (see Figure 8) which indicates this bearing seized the shaft and rotated within the housing.

Trip Report
Letter File No. ACM-029-15
Date: February 28, 1979
Page 4

DETAILS OF INVESTIGATION (continued):

As stated above, the upper bearing near the shaft fracture "froze" and fractured and was discolored. Therefore, it is apparent that most of the water injected there flowed by the lower bearing. It is probable that the lack of water to the upper bearing and/or the leakage of scale (sections of the shaft were heavily scaled as shown in Figures 3 and 7) into the shaft upper bearing annulus caused the shaft and bearing to overheat and to eventually become "welded" together. At this point the fracture occurred in a ductile torsional mode. The fracture occurred in the Hastelloy C section instead of in the 17-4 PH section where the bearing also became welded to the shaft because 17-4 PH is a much stronger alloy than Hastelloy C. A comparison of the tensile properties of each alloy is given in Table 1.

M&QS REPRESENTATIVE:

A. C. Madsen

Figure 2. Broken pump shaft. View from above top impeller.

Figure 3. Fracture face of broken Hastelloy C pump shaft. Photograph shows mechanical coupling (upper left) used to join the broken Hastelloy C section to the old 17-4 PH stainless steel section.

Figure 4. Fractured bearing. The shaft fracture occurred in this bearing.

Figure 5. View of shaft from below the final pump stage. The shaft structure within the upper bearing of this stage.

Figure 6. Vertical brine reinjection pump, P-2. Note inlet nozzles for bearing cooling water.

Figure 7. Photograph of 17-4 PH stainless steel section of the shaft. Note severe grooving at upper end (upper right).

Figure 8. Severely grooved section of 17-4 PH stainless steel shaft.

Figure 9. Photograph of bronze bearing that was used on the upper end of the 17-4 PH stainless steel section of shaft.

Table 1

Tensile Properties of Hastelloy C and 17-4 PH Stainless Steel

	<u>Hastelloy C</u> <u>(a)</u>	<u>17-4 PH Stainless Steel</u> <u>(b)</u>
Tensile strength, psi		
Room temperature	114,900	203,000
600°F	96,300	173,000
800°F	94,800	162,000
Yield strength, psi		
Room temperature	52,900	186,000
600°F	36,200	150,000
800°F	30,500	141,000

(a) Data obtained for 1 inch thick plate, heat treated at 2050°F and rapid quenched.

(b) H-900 condition.