LEGIBILITY NOTICE

A major purpose of the Technical Information Center is to provide the broadest dissemination possible of information contained in DOE's Research and Development Reports to business, industry, the academic community, and federal, state and local governments.

Although a small portion of this report is not reproducible, it is being made available to expedite the availability of information on the research discussed herein.

LA-UR--87-3950

DE88 003153

TITLE DEVELOPMENT OF AN INTEGRATED HEAT PIPE-THERMAL STORAGE SYSTEM FOR A SOLAR RECEIVER

AUTHORS Edward S. Kelly, J. Tom Sera and Michael A. Merrigan
Advanced Engineering Technology, MEE-13
Los Alamos, New Mexico 87545
Gary Weidenreich, Sundstrand Missile & Space Power Systems
Advanced Technology Group
Rockford, IL 61105-7000
Steve Johnson, NASA Lewis Research Center, NASA Cleveland
Cleveland, OH 44135

SUBMITTED TO Journal of Thermophysics and Heat Transfer
AIAA Journal
Thermophysics Conference
San Antonio, Tx
June 27-29, 1987

DISCLAIMER

THIS DOCUMENT CONTAINS INFORMATION OF A PRELIMINARY NATURE AND IS NOT TO BE USED FOR ANY OTHER PURPOSE WITHOUT THE EXPRESS WRITTEN PERMISSION OF THE LOS ALAMOS NATIONAL LABORATORY.

THIS DOCUMENT IS THE PROPERTY OF THE LOS ALAMOS NATIONAL LABORATORY AND IS LOANED TO YOUR ORGANIZATION. IT AND ITS CONTENTS ARE NOT TO BE DISTRIBUTED OUTSIDE YOUR ORGANIZATION.

Los Alamos Los Alamos National Laboratory
Los Alamos New Mexico 87545

MASTER

11/27/88 10:10 AM

TABLE OF CONTENTS

EXTENDED SUMMARY	1
------------------	---

LIST OF FIGURES

1	Rankine cycle receiver	1
2	Axial heat pipe with thermal storage units	3
3	Heat pipe element test setup	4
4	Insolation concentration versus cavity depth	5
5	Thermocouple locations	5
6	Calorimetry setup	6
7	TES canister fully charged at start of eclipse	7
8	Temperature versus time of one axial set of thermocouples during solid phase startup to peak input power	7

REFERENCES	8
------------	---

**DEVELOPMENT OF AN INTEGRATED HEAT PIPE-THERMAL
STORAGE SYSTEM FOR A SOLAR RECEIVER**

By

**Edward S. Keddy, J. Tom Sera, and Michael A. Merrigan
Advanced Engineering Technology, MEE-13
Los Alamos National Laboratory
Los Alamos, New Mexico 87545**

**Gary Weidenreich
Sundstrand Missile & Space Power Systems
Advanced Technology Group
4747 Harrison Avenue
Rockford, IL 61205-7002**

**Steve Johnson
NASA Lewis Research Center
NASA Cleveland
2100 Brinkpark Road
Cleveland, OH 44135**

The Organic Rankine Cycle (ORC) Solar Dynamic Power System (SDPS) is one of the candidates for Space Station prime power application. In the low earth orbit of the Space Station approximately 34% of the 91-minute orbital period is spent in eclipse with no solar energy input to the power system. During this period the SDPS will use thermal energy storage (TES) material to provide a constant power output. Sundstrand Corporation is developing a Rankine Cycle generator for the Space Station that uses cooled and preheated fluids such as the TES material. An integrated heat-pipe thermal storage and power system is being developed as part of the ORC-SDPS solar dynamic power system and operated as a closed heat pipe circuit to collect and transfer the solar energy within the receiver cavity. The receiver cavity is the TES storage within the pipes and can be filled with the TES material and cooled and preheated regions of the heat pipe circuit. The TES material is preheated by the solar energy to drive the heat pipe circuit.

Fig. 1. Rankine cycle receiver.

ORC-SOPS receiver cavity. The heat pipe transforms the non-uniform solar flux incident in the heat pipe surface within the receiver cavity to an essentially uniform flux at the potassium vapor condensation interface in the heat pipe. During solar insolation, part of the thermal energy is delivered to the heater tube and the balance is stored in the TES units. During the eclipse period of the orbit, the balance stored in the TES units is transferred by the potassium vapor to the toluene heater tube.

The solar receiver heat pipes are similar to conventional alkali metal heat pipes but they are unique in operational characteristics. The solar

radial flux is delivered to a semicylindrical surface section of the heat pipe and it varies in power density from end to end with a peak flux of about 7.5 W/cm^2 approximately 50 cm from one end. The operational temperature is limited to 775 K in the potassium vapor space under the maximum heat input to each pipe of 5.7 kW. During eclipse the heat pipe is required to continue to function in a transfer mode, using the latent heat of the LiOH as the heat source to provide the necessary heat to the toluene heater. The resulting heat pipe design, shown in Fig. 2, has been developed to meet these requirements.

Fig. 2 Axial heat pipe with thermal storage units

A developmental performance verification heat pipe was constructed from stainless steel tubing 100 cm in length with an outside diameter of 10.7 cm. The wick structure designed to provide liquid return for the verified heat transfer performance requirement consisted of three layers of fine mesh screen placed against the inner wall for circumferential distribution of the primary fluid. Similar layers of screen were placed around the thin wall section of the tube to provide a liquid path for the condensate during open flow. Axial flow distribution was provided by the insertion of a thin wall section of the boiler

and two between the heater tube and the circumferential distribution wick. Potassium was vacuum-distilled into the heat pipe and the heat pipe wet-in at 775 K to fill the screen wick and arteries. The heat pipe was tested in a vacuum chamber, Fig. 3, with simulated solar heat input being provided by a variable zoned rf induction coil (Fig. 4). This coil was separated into four distinct zones, each providing a different semi-cylindrical radial heat input flux into the heat pipe. Heat loss on the back half of the pipe was kept to minimum with radiation shielding. Thermocouples were used to monitor the temperature profile circumferentially and axially (Fig. 5).

Fig. 3. Heat pipe element test setup.

Tests were conducted to satisfy the conditions of 4.8 kW throughput for normal operation and 5.7 kW heat throughput for an upper limit. Heat throughputs were measured using a calorimetric flow system that simulated the toluene flow system, as shown in Fig. 6. Thermal charge and discharge of the internal thermal storage canisters was conducted to simulate an earth orbit cycle. The heat pipe was operated with a constant input orbit cycle. The heat pipe was operated with a constant input of 5.2 kW during the simulated insolation period. At 753 K, a power level of 3 kW was removed through the heater tube and the balance of the input power was stored in the TIS canisters. When the temperature of the heat pipe reached 775 K the eclipse cycle was started. The average

Fig. 4 Insolation concentration versus cavity depth

Fig. 5 Thermocouple locations

Fig. 6. Calorimetry setup.

power throughput remained approximately 3.0 kW during the test cycles (Fig. 7). The temperature swing was ± 25 K.

A test was conducted with the input flux varied axially to demonstrate the design-peak-heat flux capability of 15 watts/cm^2 . An rf coil was fabricated to provide greater than 5 kW heat input to the heat pipe over the area that received 15 watts/cm^2 or more in normal operation. The heat pipe was isothermal within 5 K at a temperature of 733 K with no hot spots or other abnormalities.

Heat pipe transient performance tests were conducted to determine the operating characteristics and power input limits of the heat pipe/thermal storage elements under conditions corresponding to reacquisition of the sun during emergence from the eclipse conditions and to initial start-up of the solar dynamic power system. During start-up of the system from the frozen state, the working fluid in the heat pipe must be melted and must be made available to the internal phase change cycle at a rate higher than that at which vapor from the evaporator is lost to the frozen regions of the heat pipe. Determination of the start-up limits was established by a series of tests conducted with decreasing times to full input power level for the heat pipe. The most rapid start-up time was 10 seconds. These tests were completed

without any evidence of malfunction of the heat pipe assembly. The temperature distribution through the heat pipe was symmetric and uniform through the start-up, even in the minimum time start (Fig. 8).

An integrated heat pipe/thermal storage element has been designed and developed that meets the functional requirements of (1) absorbing the solar energy in the receiver, (2) transporting the energy to the organic Rankine heater, (3) providing thermal storage for the eclipse phase, (4) allowing uniform discharge from the thermal storage to the heater. The heat pipe assembly has been operated at design input powers of 4.8 kW and 5.7 kW. Thermal cycle tests to simulate the insulation and eclipse periods have demonstrated the successful charge and discharge of the TES canisters. Axial flux levels to 15 watts/cm^2 have been demonstrated and transient tests have demonstrated that the heat pipe will successfully startup from the frozen condition with full power at the onset.

Fig. 7. TES canister fully charged at start of eclipse.

Fig. 8. Temperature versus time of one axial set of thermocouples during solid phase startup to peak input power.

REFERENCES

1. Heidenreich, G., Parekh, M. B., Sundstrand Corporation, "Thermal Energy Storage for Organic Rankine Cycle Solar Dynamic Space Power System," 21st IECEC, San Diego, California (August 1986).
2. Keddy, E., Sena, J. T., Woloshun, K., Merrigan, M. A., "An Integrated Heat Pipe-Thermal Storage Design for a Solar Receiver," 21st Intersociety Energy Conversion Engineering Conference (IECEC), San Diego, California (August 1986), Los Alamos National Laboratory report LA-UR-86-1840.
3. Keddy, E., Sena, J. T., Merrigan, M. A., Heidenreich, G., "Integrated Heat-Pipe Thermal Storage System Performance Evaluation," 22nd Intersociety Energy Conversion Engineering Conference (IECEC), Philadelphia, Pennsylvania (August 10-14, 1987), Los Alamos National Laboratory report LA-UR-87-1623.