**PRELIMINARY CHARACTERIZATION
OF THE F-AREA
RAILROAD CROSSTIE PILE
AT THE
SAVANNAH RIVER SITE**

**PREPARED FOR
WESTINGHOUSE SAVANNAH RIVER COMPANY
SAVANNAH RIVER SITE
AIKEN, SOUTH CAROLINA**

**PREPARED BY
SIRRINE ENVIRONMENTAL CONSULTANTS
AIKEN, SOUTH CAROLINA**

**SIRRINE PROJECT NUMBER
G1106**

OCTOBER 1991

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

for

TABLE OF CONTENTS

	<u>Page</u>
EXECUTIVE SUMMARY	ES-1
1.0 <u>PRELIMINARY UNIT EVALUATION</u>	1
1.1 Introduction	1
1.2 Existing Literature and Information	1
1.3 Waste Characteristics	2
2.0 <u>ENVIRONMENTAL SETTING</u>	3
2.1 Geologic Setting	6
2.2 Hydrostratigraphy	10
3.0 <u>SUMMARY REPORT OF FIELD OPERATIONS</u>	22
3.1 Field Activities Summary	22
3.2 Sample Collection, Handling, Packaging and Shipping	31
3.3 Quality Assurance/Quality Control	34
3.4 Project Field Files	35
4.0 <u>UNIT SCREENING RESULTS</u>	35
4.1 Data Development	35
4.2 Findings	36
4.2.1 Metals in Soil Samples	36
4.2.2 Organic Analytes in Soil Samples	36
4.2.3 Other Analytes in Soil Samples	37
4.2.4 Metals in TCLP Samples	37
4.2.5 Radionuclides in Soil Samples	37
4.2.6 Analytes Detected in Groundwater Samples	38

REFERENCES

REF-1

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

MASTER

FIGURES

<u>Number</u>	<u>Title</u>	<u>Page</u>
2-1	Site Location and Physiographic Setting	4
2-2	Physical Setting of the F-Area Railroad Crosstie Pile	5
2-3	General Stratigraphic Column for Coastal Plain Sediments	7
2-4	Stratigraphic Section Through SRS	8
2-5	General Hydrogeologic Units at SRS	11
2-6	Water Table Contour Map and Flow Direction for the F-Area Railroad Crosstie Pile Vicinity, (4th Quarter, 1987)	12
2-7	Layout Map for Well Clusters P-28 and FC-2	14
2-8	Hydraulic Heads in Groundwater at Well Cluster P-28/FC-2	15
2-9	Regional Potentiometric Surface Map, Aquifer Unit IIA	17
2-10	Areas of Upward and Downward Vertical Hydraulic Gradients Across SRS	18
2-11	Relationship Between Physiography and Hydrostratigraphy Near F- and H-Areas	21

TABLES

<u>Number</u>	<u>Title</u>	<u>Page</u>
3-1	F-Area Railroad Crosstie Site Chronological Field Activities Summary	24
3-2	Soil Sample Matrix, FRT-1HP	26
3-3	Soil Sample Matrix, FRT-5HP	27
3-4	Soil Sample Matrix, FRT-4HP	28
3-5	Soil Sample Matrix, FRT-3HP	29
3-6	Water Sample Matrix	30
3-7	Soil Sampling Intervals and Analyses	32
3-8	Groundwater Analyses	33
4-1	Metals Detected in F-Area Tie yard Soil Samples	39
4-2	Organic Analytes Detected in F-Area Tie Yard Soil Samples	40
4-3	Other Analytes Detected in F-Area Tie Yard Soil Samples	41
4-4	Metals Detected in F-Area Tie Yard TCLP Samples	42
4-5	Radionuclides Detected in F-Area Tie Yard Soil Samples	43
4-6	Soil Sample Radionuclide Summary, F-Area Railroad Crosstie Pile	44
4-7	Groundwater Analyses	45
4-8	Background Soil Concentrations, Blanton Soil Series	46
4-9	Background Soil Concentrations, Fuquay Soil Series	47
4-10	Background Soil Concentraions, Udorthent Soils	48
4-11	Drinking Water Standards	49

APPENDICES

Appendix A Analytes Not Found at the F-Area Railroad Crosstie Pile

Appendix B Groundwater Monitoring Data, FBP Wells

Appendix C Field Notes and Geologic Logs

Note: Laboratory Analytical Results are summarized in the body of the report and are available from Tom Gaughan, WSRC-ER; (404) 821-8016

EXECUTIVE SUMMARY

Historical information about the F-Area Railroad Crosstie Pile is limited. The unit is believed to have been a borrow area for earth fill that began receiving railroad crossties during the 1960s. The number of crossties at the unit began to increase significantly in 1984 when major repair of the SRS rail system was initiated. An estimated 100,000 used railroad crossties have accumulated at the unit since 1984.

In an effort to determine the impact of the railroad crossties on the environment, a total of 28 soil samples were collected from four test borings in March of 1991. Sample depths ranged from ground surface to 21.5 feet. Three of the borings were extended to the water table and groundwater samples were collected, one in an upgradient "background" area, and two downgradient from the unit.

Few analytes were reported above detection limits. Test results are summarized in Section 4.0 and analytes not detected are summarized in Appendix A to this report. In three soil samples collected from depths between 10 and 21.5 feet, copper occurred at levels slightly above background. These copper values were detected in the sidegradient test boring and in the two downgradient test borings. Three organic analytes, acetone, pyridine, and Toluene, were reported above detection limits but well below drinking water standards (DWS) in all test borings, including the upgradient boring.

Radionuclide activities were reported above background in both soil and water samples from all test borings (Tables 4-5 and 4-7). There do not appear to be any statistically significant trends in radionuclide activities with depth, or between upgradient or downgradient borings.

The organic analytes tetrachloroethylene and trichloroethylene were detected above DWS in the groundwater in one of the downgradient borings, and well above DWS in the upgradient boring along with carbon tetrachloride and trichlorofluoromethane. No organic analytes were detected in groundwater in the second downgradient test boring.

The analytes detected in the test borings downgradient from the unit cannot be attributed to the railroad crosstie pile as they are not significantly different than the values reported for the upgradient, background test boring.

PRELIMINARY CHARACTERIZATION OF THE F-AREA RAILROAD CROSSTIE PILE AT THE SAVANNAH RIVER SITE

1.0 PRELIMINARY UNIT EVALUATION

1.1 Introduction

A review of existing literature and information about the F-Area Railroad Crosstie Pile indicates that the history of the site is not fully documented. However, experienced personnel believe the site began receiving railroad crossties during the 1960s¹. The volume of used crossties stored at the site began to increase significantly in 1984 when the first major repair of the SRS rail system, and the construction of L-Lake were initiated¹. Since 1984, the F-Area Railroad Crosstie Pile has accumulated an estimated 100,000 railroad crossties from repair and replacement of onsite railroad tracks. In addition, the pile includes an unknown number of creosote treated utility poles from power line and telephone system repairs¹.

1.2. Existing Literature and Information

The following information specifically pertaining to the F-Area Railroad Crosstie Pile was reviewed:

Bignell, D.T., Railroad Crosstie Disposal Alternatives, January, 1991. Letter to Mr. Donald Gross, Jr.

AAR, 1988, Toxicity Characteristic Leaching Procedure Testing of Railroad Crossties (R-708), Association of American Railroads, Chicago, IL;

Olson, C., Wells Monitored by the Health Protection Department, HPR-88-001

Additional documents pertaining to general SRS waste management activities were also reviewed as necessary and are included in the list of references.

1.3 Waste Characteristics

The F-Area Railroad Crosstie Pile was used for the disposal or staging primarily of creosote-treated railroad crossties. In addition, the site has also received some creosote-treated utility poles, guardrail posts, fence posts, and other miscellaneous lumber¹. Creosote, a petroleum based wood preservative and insect repellent, may contain up to 200 various molecular weight organic compounds. Chemical components of, and additives to, creosote may include cresols, phenolic compounds such as pentachlorophenol, heterocyclic compounds, and various three-to-six carbon-chain volatile organic acids. Most of these compounds form the soluble, and hence leachable, phase of creosote. The soluble constituents/components of creosote are prone to natural degradation, which may yield many intermediate and end products. Degradation components of creosote include: phenol (primary intermediate compounds), various methylated phenols, methane, and carbon dioxide.

Waste railroad ties obviously meet the definition of a solid waste, but not necessarily a hazardous waste. A solid waste is classified as a hazardous waste if it exhibits the characteristics of ignitability, corrosivity, reactivity, or toxicity as defined in 40 CFR 261, Subpart C. Creosote contains cresol and pentachlorophenol compounds which fall into the category of regulated hazardous constituents. Representative samples were obtained from SRS ties of 1953, 1961, 1975, 1984, and 1990 vintage and were analyzed. The results from those TCLP tests, and the tests from eleven previous SRS samples (also past technical reports from the Association of American Railroads²) indicate that the ties are non-hazardous¹.

All used ties at the F-Area storage site were removed from a nonradioactive (clean) area, i.e., not from within a Radiologically Controlled Area (RCA). However, the possibility does exist that some ties may have been radioactively contaminated due to the possibility of a railroad car being contaminated¹. This potential for radiological contamination necessitates that radiological requirements be considered and evaluated when analyzing the alternatives for crosstie disposal (particularly those options involving transporting the ties offsite). While beta and gamma radiation can be readily monitored with existing instruments, alpha radiation is easily shielded making monitoring very difficult.

An alpha emitting contamination that is not on the surface of the wood may be difficult to impossible to detect with present SRS scanning instruments¹. The ties must be completely surveyed, internally and externally, for alpha and beta-gamma contamination before offsite shipments are allowed to any contractor, other than a contractor permitted by Federal and State regulatory agencies to dispose of radioactive wastes.

2.0 ENVIRONMENTAL SETTING

The Savannah River Site is located on the Upper Coastal Plain about 20 miles southeast of the Fall Line in west-central South Carolina. F-Area is located in the central portion of the Site, as shown on Figure 2-1. The F-Area Railroad Crosstie Pile is situated on a ridge in an area of varied vegetation which includes mature broad leaf and pine trees with sparse ground cover. The undergrowth has been cleared from the surrounding area by the U.S. Forest Service to provide a fire break. The crossties are positioned in an area that has been leveled by excavating into the west side of a low hill, previously a soil borrow area. A very steep erosional gully approximately 70 feet deep is immediately to the west of the site. The gully drains toward Upper Three Runs about 1300 feet to the northwest. The closed F-Area Burning/Rubble Pits and Scrap Lumber Pile were located in a cleared area about 300 feet to the south of the railroad crosstie pile. The physical setting of the Railroad Crosstie Pile is depicted on Figure 2-2.

The predominant soil series in the vicinity of the F-Area Railroad Crosstie pile are classified within the Blanton and Fuquay Series and as Udorthents³. Udorthent is a generic term for sites where the natural soil horizons have been disrupted, usually by construction activities.

FIGURE 2-1 SITE LOCATION AND PHYSIOGRAPHIC SETTING

Adapted from USGS 7.5 Minute Quadrangle: New Ellenton SW, Rev. 1981

FIGURE 2-2 PHYSICAL SETTING OF THE F-AREA RAILROAD CROSSTIE PILE

2.1 Geologic Setting

The subsurface geology that underlies the SRS includes crystalline basement rocks and Triassic sedimentary rocks which are overlain by Cretaceous and younger Coastal Plains sediments. At SRS the depth to bedrock ranges from approximately 750 feet at the northern boundary to more than 1400 feet to the south⁴. The crystalline basement rock is composed of chlorite-hornblende schist, hornblende gneiss, and lesser amounts of other types of crystalline rock. The Triassic sedimentary bedrock occurs in the southern portion of the Savannah River Site and consists of poorly sorted conglomerate, sandstone and mud-rock. These are generally dark red in color.

The stratigraphic units of the Coastal Plain, from oldest to youngest, are the Cape Fear Formation, the Lumbee Group, the Black Mingo Group, the Orangeburg Group, the Barnwell Group, and the Upland Unit, as depicted on Figure 2-3⁵. A stratigraphic section across SRS is depicted on Figure 2-4⁶. The lowermost of these units, the Cape Fear Formation, is composed of Lower Cretaceous, poorly sorted, silty to clayey quartz sands and interbedded clays which range in thickness from 30 feet at the northwest site boundary to more than 180 feet at the southeast site boundary.

The Lumbee Group (Upper Cretaceous) is subdivided into the Middendorf, the Black Creek, and the Pee Dee Formations. The lower contact between the Middendorf and the Cape Fear is a sharp erosional unconformity. In general, the Lumbee Group is composed of variably colored quartz sands and clays which range in thickness of 380 to more than 700 feet from the northwestern site boundary to the southeastern site boundary respectively.

The Black Mingo Group consists of the Rhems Formation (Early Paleocene), which includes the Ellenton Member, and the Williamsburg Formation (Late Paleocene). The Ellenton consists mostly of gray, poorly sorted, micaceous, lignitic, silty and clayey quartz sand interbedded with gray clays. The Ellenton is approximately 40 feet thick at the northwestern boundary of the SRS and thickens to approximately 100 feet at the southeastern boundary. The Williamsburg sediments are composed of silty quartz sand interbedded with

Modified from Price, et al.⁵

FIGURE 2-3 GENERAL STRATIGRAPHIC COLUMN FOR COASTAL PLAIN SEDIMENTS

SOURCE: Savannah River Site Environmental Report for 1988⁶

FIGURE 2-4 STRATIGRAPHIC SECTION THROUGH SRS

clays. The Williamsburg thickens from 30 feet at the northwestern boundary of SRS to 50 feet at the southeastern boundary.

The Orangeburg Group is subdivided into the lower Middle Eocene Congaree Formation and the Upper Middle Eocene Santee Limestone Formation. The Congaree is composed of well sorted, fine-to-coarse quartz sands with thin clay laminae throughout. The Congaree is approximately 60 feet thick at the northwestern boundary of the SRS and thickens to approximately 85 feet near the southeastern boundary. The Santee Limestone Formation is subdivided into the Warley Hill, the Caw Caw, and the McBean Members, and varies in lithology from carbonates and calcareous quartz sands to quartz and glauconitic sands and clays. The Warley Hill and the Caw Caw Members make up what has been referred to in many SRS reports as the "Green Clay". This unit is composed of glauconitic, silty and clayey quartz sands. The thickness of the formation ranges from 40 feet to more than 80 feet from the northwestern boundary of the SRS to the southeastern boundary.

The Barnwell Group (Late Eocene) is subdivided into the Clinchfield, the Dry Branch, and the Tobacco Road Formations. The Clinchfield is present at some locations at the SRS but it is not continuous enough to be correlated across the Site. The Dry Branch is composed of silty and clayey quartz sand with interbedded clays. The Dry Branch Formation ranges in thickness from 50 feet to 80 feet from the northwestern boundary of the SRS to the southeastern boundary. The Tobacco Road Formation consists of massive moderately to poorly sorted quartz sand with minor clay laminae. The Tobacco Road outcrops at the surface at many locations at the SRS and ranges in thickness from 20 to 30 feet.

The Upland Unit (previously mapped at SRS as the Hawthorn Formation) is composed of clays and poorly sorted, clayey, silty, pebbly, and cobbly quartz sands with extreme lateral and vertical variation.⁷ These sediments represent fluvial channel deposits. The Upland Unit is about 15 feet thick in this area.

2.2 Hydrostratigraphy

A multilayer hydrologic system exists in the Coastal Plain sediments at the Savannah River Site within which confining units are interspersed with more transmissive units. Aadland and Bledsoe⁴ have proposed a new hydrostratigraphic nomenclature system (Figure 2-5) which will be used in this report.

Aquifer Unit IIB is the shallow water table aquifer at the SRS, composed of sediments from the Tobacco Road, the Dry Branch, and the McBean Formations. The sediments of Aquifer Unit IIB exhibit a wide variation in lithologic composition both vertically and laterally. The position of the water table results more from unconfined aquifer conditions than from stratigraphic control.

Aadland and Bledsoe⁴ report a series of discontinuous thin clay lenses (informally referred to as the "Tan Clay") within the Dry Branch Formation in F- and H-Areas. This serves as a locally significant aquitard, designated Confining Zone IIB1-IIB2. This confining zone divides Aquifer Unit IIB into a lower aquifer zone, IIB1, and an upper aquifer zone, IIB2.

Based on water level data from wells and test borings near the F-Area Railroad Crosstie Pile, the depth to water in the area is about 100 feet below land surface. The groundwater flow direction of Aquifer Unit IIB (based on average measurements recorded for 1988) in the F-Area was shown to be to the west-northwest. Contours of the water table aquifer are depicted on Figure 2-6. Values reported for hydraulic conductivity of Aquifer Unit IIB range from 1×10^{-3} cm/sec to 1×10^{-6} cm/sec depending on the type of geologic material across which the wells are screened.

Aquifer Unit IIB is separated from Aquifer Unit IIA (Congaree) by Confining Unit IIA-IIB. This confining unit (described in previous SRS reports as the Green Clay or Caw Caw Clay Member) was identified at a depth of 152 feet below land surface in Well P-28 TA.

COMPARISON OF HYDROSTRATIGRAPHIC UNITS USED AT SRS					PROPOSED NOMENCLATURE AADLAND (1990)	
GEOLOGIC AGE	SRP BASELINE HYDROGEOLOGIC STUDY	GEOTRANS (1989)	PRICE (1988)	AQUIFER SYSTEM I/II		
UNKNOWN	UPLAND UNIT	AQUIFER 4	ZONE 8	AQUIFER SYSTEM II		
	TOBACCO RD FM		ZONE 7	AQUIFER ZONE II B, CONFINING ZONE II B, - IIB,		
	DRY BRANCH FM				AQUIFER ZONE IIB, CONFINING UNIT IIA - IIB	
	TERTIARY	BARNWELL GROUP	McBEAN FORMATION GREEN CLAY	ZONE 6	AQUIFER UNIT I/II C	SYSTEMS BOUNDARY
CONGAREE		AQUIFER UNIT II A				
WILLIAMSBURG FM		AQUITARD 2	ZONE 4	CONFINING UNIT I/II B	AQUIFER UNIT I B	
ELLENTON FORMATION						CONFINING UNIT I/IIA - I/II B
CRETACEOUS		PEEDEE FORMATION	AQUIFER 2	ZONE 3	AQUIFER UNIT I/IIA	AQUIFER UNIT IA
		BLACK CREEK FM				
	MIDDENDORF FM	AQUIFER 1	ZONE 2	CONFINING SYSTEM I		
	CAPE FEAR FM	BASE OF MODEL	ZONE 1			
TRIASSIC OR PALEOZOIC BASEMENT				PALEOZOIC - TRIASSIC BASEMENT HYDROLOGIC SYSTEM		

FIGURE 2-5 GENERAL HYDROGEOLOGIC UNITS AT SRS

Modified from HPR-88-001, 1988⁸

FIGURE 2-6 WATER TABLE CONTOUR MAP AND FLOW DIRECTION FOR THE F-AREA RAILROAD CROSSTIE PILE VICINITY, (4th Quarter, 1987)

The general hydrologic conditions in the vicinity of the F-Area can be observed from the P-28/FC-2 well cluster, located 4700 feet east of the railroad crosstie pile (see Figure 2-2). In all, a total of 12 wells are found at this location, approximately 110 feet east of the F-Area perimeter. Ground surface elevations range from 280 feet, to 286 feet. A detailed location map and individual well layout for both clusters can be found on Figure 2-7.

Profiles for the P-28 and FC-2 clusters are presented on Figure 2-8 along with the approximate locations of the major clay and clayey zones. All wells within the FC-2 cluster are completed in the Tertiary age formations of Aquifer System II above confining System I-II (Ellenton Formation). Wells in this cluster range in depth from approximately 80 feet for the water table well (FC-2F) to approximately 235 feet for the Aquifer Unit IIA well (FC-2A) which is completed in the lower Congaree. The six wells installed in the P-28 cluster are all completed in the Cretaceous age formations of Aquifer System I below Confining System I-II. Wells in this cluster range in depth from approximately 240 feet for the uppermost well screened in the first permeable sand unit below the Ellenton and upper Cretaceous clays (P-28A) to approximately 780 feet for the deepest well at the site, P-28TA, which is screened in Aquifer System I in the lower Middendorf formation.

The water table is found at a depth of about 70 feet below the ground surface (approximate elevation 217 feet) in well FC-2F. Below the water table, the water levels decrease from elevation 217 feet to approximately 209 feet in well FC-2D which is screened in Confining Unit IIA-IIB (the Santee Formation above the Caw Caw Clay unit). Across the Caw Caw Clay, there is a drop in head of approximately 65 feet between well FC-2D (elevation 209 feet) and well FC-2C (elevation 145 feet) which is completed in the upper Congaree Formation of Aquifer Unit IIA.

The downward hydraulic gradient during July 1987 was calculated to range from 0.07 to 0.33 from the water table aquifer (Aquifer Unit IIB) to the upper Congaree Formation (Aquifer Unit IIA). There is a slight head reversal (increase in head) of about 2 feet between Aquifer Unit IIA and the upper portion of Confining System I-II (Wells FC-2B and FC-2A, respectively). There is a significant head reversal of 26 feet between the upper and lower portions of

From DPST-88-627, E.I. du Pont de Nemours and Company, 1988⁹

FIGURE 2-7 LAYOUT MAP FOR WELL CLUSTERS P-28 AND FC-2

Modified from Bledsoe, 1988⁹

FIGURE 2-8 HYDRAULIC HEADS IN GROUNDWATER AT WELL CLUSTER
P-28/FC-2

Confining System I-II (Wells FC-2a and P-23A screened in the Williamsburg Formation and the upper Pee Dee Formation, respectively). Upward hydraulic gradients ranged from 0.04 to 0.24. Below the Pee Dee, the head decreases slightly with increasing depth within Aquifer System I down to the lower Middendorf Formation (Well P-28TA) where the piezometric surface is found at an elevation of about 171 feet.

As shown on Figure 2-9, Upper Three Runs Creek acts as a regional discharge area for groundwater within Aquifer Unit IIA. The characteristics of the potentiometric surface contours near Upper Three Runs Creek indicate that any hazardous constituents which reach Unit IIA would not go any deeper, but would instead be transported laterally to Upper Three Runs Creek within Unit IIA.

Hydraulic heads in Aquifer Units IA and IB are controlled by recharge and discharge regions to the northeast and southwest, respectively, of SRS⁵. Figure 2-10 shows the regional relationship between hydraulic heads in Units IB and IIA. In the northwest and east-central parts of SRS, hydraulic heads in Unit IIA are higher than heads in Unit IB. Elsewhere at SRS hydraulic heads in Unit IB are higher than hydraulic heads in Unit IIA. Comparisons of hydraulic heads in the various zones within Unit IA with the hydraulic head in Unit IIA yield similar results.

Because of the lack of control between well clusters, the exact location of the line separating the region of head reversal from that of no head reversal is uncertain. As shown on Figure 2-10, a head reversal is believed to exist at F-Area Railroad Crosstie Pile, preventing downward migration of contaminants from Unit IIA through Confining System I-II. However, if a head reversal does not exist at the unit, the rate of downward migration of groundwater from Unit IIA to Unit IB may be estimated from the parameter values applicable to Confining System I-II. Recently published data (April 1991¹⁰) suggests that vertical hydraulic conductivity for Confining System I-II ranged from 7.98×10^{-10} cm/sec to 2.27×10^{-8} cm/sec at Site B northeast of F-Area. This translates, conservatively, to 6.4×10^{-5} ft/day. The head change and hydraulic gradient across the confining system may be estimated from published data. A

Source: Adapted from Du Pont, 1983h

Legend

- C.K.R.L.P. Reactor Areas
- F.M. Separations Areas
- M. Fuel and Target Fabrication
- D. Steam and Power Plant
- Heavy Water Production
- A. Savannah River Laboratory and Administration Area
- CS. Central Shops
- RM. River Mile
- U. Heavy Water Control Test Facility

Road A = Highway 125

Contours indicate areas where head in Upper Cretaceous sediments is greater than head in Congaree. Contour interval equals 10 feet (10 foot = 3.048 meters)

Area of Downward Gradient

Observation Well Cluster

Scale (kilometers)

Source: Waste Management Activities for Ground Water Protection, Savannah River Plant, Aiken, South Carolina, Volume 2, DOE/EIS-0120, US Department of Energy, December 1987.

FIGURE 2-10 AREAS OF UPWARD AND DOWNWARD VERTICAL HYDRAULIC GRADIENTS ACROSS SRS¹³

maximum head change value of 12.5 feet, yielding a hydraulic gradient of 0.11 ft/ft, was reported by Bledsoe for Well Cluster P-179.

$$K_v = \text{vertical hydraulic conductivity} = 6.4 \times 10^{-5} \text{ ft/day}^{10}$$

$$n_e = \text{effective porosity (minimum, estimate)} = 0.07^{11}$$

Head change, Unit IIA to Unit IB (maximum) = 12.5 feet (well cluster P-179)

Saturated thickness of Confining System I-II (minimum, estimate) = 20 feet¹²

i = hydraulic gradient = 0.11 ft/ft

Using Darcy's Law:

$$V = K_v / n_e$$

A velocity of 1.04×10^{-4} ft/day is obtained for groundwater leaking downward through Confining System I-II. Assuming constant parameter values and continuity of the aquitard, it would require about 544 years for water to migrate from Aquifer Unit IIA through Confining System I-II into Aquifer Unit IB.

Based on the above information, it is unlikely that hazardous constituents that might be released from the F-Area Railroad Crosstie Pile would reach water-bearing strata (Units IB or IA) below Aquifer Unit IIA. Constituents entering the water table aquifer would instead be transported laterally at each clay layer within Aquifer IIB toward Upper Three Runs Creek, or would leak through Confining Unit IIA-IIB, and reach Upper Three Runs Creek through Aquifer Unit IIA.

In the general F-Area, the water table occurs within the Barnwell Group. Figure 2-3 shows this to be one of the younger (therefore, stratigraphically higher) units in the section. At higher topographic elevations in F-Area, these younger units exist and the water table occurs in them. At the lower elevations, the younger units are eroded and the water table resides in geologic units lower in the section. The deepest erosion (at Upper Three Runs Creek) exposes the Congaree Formation and, in this portion of F-Area, the water table occurs in this

formation. These are textbook geomorphic features which have been observed in field reconnaissance, and are depicted on Figure 2-11.

Hydraulic conductivity obtained from a Steady-State Model Calibration for the Barnwell Group was 0.2 - 1.1 m/day.¹² This value was determined from slug test data collected from nearby F- and H-Area wells. Total porosity of the sediments that compose the Barnwell Formation range approximately from 35% to 60%.¹⁴ Effective porosity has been estimated at a lower value of approximately 20%.¹²

The horizontal hydraulic gradient of the water table (Barnwell Group) in the area of the railroad crosstie pile (between the four monitoring wells) is approximately 0.024 (calculated from 4th quarter 1988 data). The horizontal hydraulic gradient in the underlying Congaree Formation in the general F-Area is approximately 0.006.¹² The Congaree aquifer flow is toward Upper Three Runs Creek.¹²

Modified from Druffield, et al., 1986¹²

FIGURE 2-11 RELATIONSHIP BETWEEN PHYSIOGRAPHY AND HYDROSTRATIGRAPHY NEAR F- AND H-AREAS

3.0 SUMMARY REPORT OF FIELD OPERATIONS

3.1 Field Activities Summary

Field activities for the Preliminary Characterization of the F-Area Railroad Crosstie site commenced March 12, 1991 and were completed March 22, 1991. Four soil borings, FRT-1HP, FRT-3HP, FRT-4HP and FRT-5HP were drilled and sampled initially to depths of 21.5 ft, for soil assessment purposes. Three of these borings, FRT-3HP, FRT-4HP, and FRT-5HP were then extended to the water table at a depth of about 100 ft for collection of groundwater samples with the new version of the Hydropunch™, designated Hydropunch™ II. FRT-5HP is located in a wooded area upgradient from the railroad crosstie pile, and FRT-3HP and -4HP were located downgradient. The borings were drilled at locations that had previously been staked and approved by DHEC. Boring locations are shown on Figure 2-6.

Drilling and sampling commenced March 12, 1991 at FRT-1HP and resumed after a one-day rain delay at the upgradient boring, FRT-5HP. The soil samples were collected from these two borings without incident. However, upon drilling FRT-5HP to the water table and driving the Hydropunch™ II into position for sampling at the phreatic surface, it was determined that groundwater samples could not be collected with the system, as configured. The Hydropunch™ II may be assembled in two different configurations; the standard configuration for sampling below the water table, and a new configuration for determining if low-density contaminants exist at the phreatic surface. The modified version of the Hydropunch™ simplifies disassembly, decontamination, and reassembly over previous versions. In addition, it is very rugged and is driven into position with a 140 lb hammer in the same manner as a split spoon. After the Hydropunch™ II is driven into sampling position, the driller retracts the body of the sampling device to expose a screen and allow groundwater to enter the sample chamber. In the standard configuration, water is retained in the sample chamber by a pair of check valves and the Hydropunch™ II is retrieved with a 200 ml sample inside. However, in the water-table configuration, a bailer is lowered into the sample chamber through the drill rods. Therefore, it is possible to collect larger samples in the modified configuration by means of multiple trips with the bailer.

Normal drilling rods are used in the standard configuration, with an AW adaptor in the drivehead. However, the system is designed to work with EW casing in the water-table configuration to enable passage of a 1-in diameter bailer into the sample chamber.

The EW casing was not yet available for use at the Railroad Crosstie site, so it was necessary to sample through NWJ rods which have a 1.065-in ID constriction at each 10 ft. interval joint. This makes it very difficult to insert or retrieve the 1-in. OD bailer. Also, since the top of the bailer is open, it is possible to introduce contamination into the bailer at each rod joint. In addition, the check valve in the bailer tends to unseat at each impact with a joint so that sample is lost in transit up the rods. This may not present a significant problem at a site where the water table is very shallow, but it does become significant where the water table is deeper. It may also be possible to use a small-diameter top-fill bailer if the water depth in the sample chamber is sufficient, but a suitable bailer was not available.

After consultation with WSRC staff and a teleconference with QED, Inc., developer of the Hydropunch™, it was determined that EW casing would be necessary for successful completion of sampling with the Hydropunch™ II, at this site. The Groundwater Monitoring Group of WSRC-EPD determined that it would not be feasible to procure EW casing within the project time frame. It was, therefore, necessary to either grout FRT-5HP or to use an alternative sampling procedure. The method selected by the Groundwater Monitoring Group of WSRC-EPD was to insert 2-in PVC casing and screen into each boring with a section of screen straddling the water table. A bailer was then used to collect a representative groundwater sample after the water level in each borehole stabilized.

A chronological summary of field activities is presented as Table 3-1, and soil sample data for each boring are presented as Tables 3-2 through 3-5. Sample data for groundwater samples from Borings FRT-3HP, 4HP, AND 5HP are presented as Table 3-6.

TABLE 3-1

**F-Area Railroad Crosstie Site
Chronological Field Activities Summary**

<u>DATE</u>	<u>REMARKS</u>
Monday 3/11/91	Prepare eqpt. - no sample containers available
3/12/91	FRT-1HP; Drill and collect 7 soil samples to 21.5 ft.
3/13/91	Rain - shut down, shipped samples
3/14/91	FRT-5HP; Drill and collect 7 soil samples to 21.5 ft. - augered to 95 ft. - no water - no more augers, shut down for the day.
Friday 3/15/91	Auger to 105 ft., Adaptor sub to couple Hydropunch™ to rods won't fit. Mtg. Well Bldg. Telecom Bergren, QED, determine Hydropunch™ II sub is EW <u>Casing</u> thread - not <u>rod</u> thread. No sub or EW casing available. Graves determines ID of NWJ rod couplings greater than 1 in., should allow passage of bailer. R. Hunter authorizes fabrication of NWJ box to EW casing pin adaptor. Telecom Tom Gaughan and Mary Flora. Elect to terminate drilling for the day rather than attempt to move to another boring. Grout FRT-1HP to surface.
Monday 3/18/91	New adaptor on site. Drive Hydropunch, trip in bailer with difficulty. Retrieve bailer with great difficulty and no sample - repeat 3 times. Sampling observed by Dan Wells, Dpt site - awaiting resolution.
3/19/91	Directed by J. Janssen to substitute 2 in. temporary piezometer for Hydropunch™ sampling in FRT-5HP, 3HP and 4HP. Auger to 110 ft. and install 2 in. PVC piezometer in FRT-5HP. FRT-4HP, drill and collect 7 soil samples to 21.5 ft., auger to 35 ft. Encountered large quartz cobbles during sampling requiring multiple sampling attempts at depths other than planned depths (see Table 4).
3/20/91	FRT-4HP (continued) Auger to 120 ft., set 2 in. PVC piezometer with 20 ft. screen.

- 3/20/91** FRT-3HP, drill and collect 7 soil samples to 21.5 ft., auger to 25 ft.
- 3/21/91** FRT-3HP (continued) Auger to 105 ft., set 2 in. PVC piezometer with 15 ft. screen.
- FRT -5HP - Collect water samples, 1145 to 1130.
- FRT-4HP - Collect water samples, 1440 to 1640
- FRT-3HP - Collect water samples, 1645 to 1840 including duplicate water sample labeled FRT-2HP.
- Note: one liter metals samples filtered through 0.45 micron filter, except for sample labeled FRT-2HP which was unfiltered.
- 3/22/91** Remove PVC temporary piezometers and grout borings FRT-3HP, 4HP and 5HP to surface.

TABLE 3-2**Soil Sample Matrix, FRT-1HP**

Date: 3/12/91

F-Area Railroad Crosstie Site

Technical Oversight: Charles B. Travis, PE, PG

Sampling Assistant: Sean W. Asquith

Company: Sirrine Environmental Consultants

Sampling Station: FRT-1HP, Soil boring, 3 in. diameter split spoon

Preliminary SRS Coordinates: N 79,777.44; E 50,408.41

Preliminary Elevation: 284.2 ft msl

Reference Point: Ground Surface

Station Established: 3/12/91

SAMPLE INFORMATION:

Sample ID	Depth	Date	Time	Sampler	Comments
FRT-1HP-1	0 - 1.5	3/12/91	1400	SWA	"O" ppm on OVA
FRT-1HP-2	1.5 - 3.0	3/12/91	1415	CBT	"O" ppm on OVA
FRT-1HP-3	3.0 - 4.5	3/12/91	1440	SWA	"O" ppm on OVA
FRT-1HP-4	4.5 - 6.0	3/12/91	1520	SWA	"O" ppm on OVA
FRT-1HP-5	10.0 - 11.5	3/12/91	1550	SWA	"O" ppm on OVA
FRT-1HP-6	15.0 - 16.5	3/12/91	1615	SWA	"O" ppm on OVA
FRT-1HP-7	20.0 - 21.5	3/12/91	1650	SWA	"O" ppm on OVA

TABLE 3-3**Soil Sample Matrix, FRT-5HP**

Date: 3/14/91

F-Area Railroad Crosstie Site

Technical Oversight: Charles B. Travis, PE, PG

Sampling Assistant: Sean W. Asquith

Company: Sirrine Environmental Consultants

Sampling Station: FRT-5HP, Soil Boring, 3 in. diameter split spoon;

Groundwater sampling station - see Table 6

Preliminary SRS Coordinates: N 79,823.00; E 50,701.78

Preliminary Elevation: 295.5 ft msl

Reference Point: Ground Surface

Station Established: 3/14/91

SAMPLE INFORMATION:

Sample ID	Depth	Date	Time	Sampler	Comments
FRT-5HP-1	0.0 - 1.5	3/14/91	0900	SWA	"O" ppm on HNu
FRT-5HP-2	1.5 - 3.0	3/14/91	0950	SWA	"O" ppm on HNu
FRT-5HP-3	3.0 - 4.5	3/14/91	1010	SWA	"O" ppm on HNu
FRT-5HP-4	4.5 - 6.0	3/14/91	1040	SWA	"O" ppm on HNu
FRT-5HP-5	10.0 - 11.5	3/14/91	1115	SWA	"O" ppm on HNu
FRT-5HP-6	15.0 - 16.5	3/14/91	1145	SWA	"O" ppm on HNu
FRT-5HP-7	20.0 - 21.5	3/14/91	1210	SWA	"O" ppm on HNu
FRT-5HP-TB		3/14/91	1245	SWA	Trip Blank (Prepared by Lab)

TABLE 3-4**Soil Sample Matrix, FRT-4HP**

Date: 3/19/91

F-Area Railroad Crosstie Site

Technical Oversight: Charles B. Travis, PE, PG

Sampling Assistant: Sean W. Asquith

Company: Sirrine Environmental Consultants

Sampling Station: FRT-4HP, Soil Boring, 3 in. diameter split spoon

Groundwater Sampling Station - see Table 6

Preliminary SRS Coordinates: N 80,181.91; E 50,419.81

Preliminary Elevation: 283.6 ft msl

Reference Point: Ground Surface

Station Established: 3/19/91

SAMPLE INFORMATION:

Sample ID	Depth	Date	Time	Sampler	Comments
FRT-4HP-1	0.0 - 1.25	3/19/91	1240	CBT	"0" ppm on HNu
FRT-4HP-2	1.5 - 2.5	3/19/91	1320	CBT	"0" ppm on HNu
FRT-4HP-3	3.0 - 4.0	3/19/91	1400	CBT	3 ppm top; "0" ppm at bit
FRT-4HP-4	4.5 - 6.0	3/19/91	1440	CBT	2 ppm on HNu
FRT-4HP-5	11.0 - 12.5	3/19/91	1530	CBT	2 ppm top; "0" ppm at bit
FRT-4HP-6	16.0 - 17.0	3/19/91	1605	CBT	"0" ppm
FRT-4HP-7	20.0 - 21.5	3/19/91	1635	CBT	2 ppm top; "0" ppm at bit

TABLE 3-5

Soil Sample Matrix, FRT-3HP

Date: 3/20/91

F-Area Railroad Crosstie Site

Technical Oversight: Charles B. Travis, PE, PG

Sampling Assistant: Sean W. Asquith

Company: Sirrine Environmental Consultants

Sampling Station: FRT-3HP, Soil Boring, 3 in. diameter split spoon;

Groundwater sampling station - see Table 6

Preliminary SRS Coordinates: N 79,872.19; E 50,387.93

Preliminary Elevation: 280.3 ft msl

Reference Point: Ground Surface

Station Established: 3/20/91

SAMPLE INFORMATION:

Sample ID	Depth	Date	Time	Sampler	Comments
FRT-3HP-1	0.0 - 1.5	3/20/91	1400	CBT	"4" ppm on HNu
FRT-3HP-2	1.5 - 3.0	3/20/91	1425	CBT	"2" ppm on HNu
FRT-3HP-3	3.0 - 4.5	3/20/91	1450	CBT	"3" ppm on HNu
FRT-3HP-4	4.5 - 6.0	3/20/91	1525	CBT	"2" ppm on HNu
FRT-3HP-5	10.0 - 11.5	3/20/91	1555	CBT	"2" ppm on HNu
FRT-3HP-6	15.0 - 16.5	3/20/91	1645	CBT	"4" ppm on HNu
FRT-3HP-7	20.0 - 21.5	3/20/91	1710	CBT	"2" ppm on HNu
FRT-3HP-R		3/20/91	1445	SWA	Rinsate Blank

TABLE 3-6**WATER SAMPLE MATRIX**

Date: 3/21/91 Water Samples
F-Area Railroad Crosstie Site
Technical Oversight: Charles B. Travis, PE, PG
Sampling Assistant: Sean W. Asquith
Company: Sirrine Environmental Consultants
Sampling Stations@Time: FRT-5HP @ 1145 to 1330
FRT-4HP @ 1535
FRT-3HP @ 1730

	FRT-5HP	FRT-4HP	FRT-3HP
Depth to Water	103.0 feet	97.4 feet	93.9 feet
Date	3/21/91	3/21/91	3/21/91
Time	1145 - 1330	1535	1730
Volume Purged	3 Bailers	3 Bailers	4 Bailers
pH	5.39	5.11	5.53
Specific Cond.	65.2 $\mu\text{s}/\text{cm}$	25.2 $\mu\text{s}/\text{cm}$	26.4 $\mu\text{s}/\text{cm}$
Temperature	19.0° C	18.5° C	18.5° C
Alkalinity (mg/l as CaCO_3)	4.4	2.2	2.2
			Collected Duplicate sample at time 1800 from FRT-3HP ID: FRT-2HP (did not filter metals sample)

3.2 Sample Collection, Handling, Packaging and Shipping

Samples were collected, handled, packaged and shipped in accordance with procedures specified in DPSOP 254¹⁵ and in the RFI/RI Program Plan¹⁶. Samples were shipped from SRS by commercial carrier (overnight delivery) to Roy F. Weston Laboratories in Pennsylvania, using proper Chain of Custody procedures.

Sampling intervals and analyses were specified in the Program Plan (Tables 3-7 & 3-8), and Weston provided sample containers and coolers for shipping. The initial plan was to collect soil samples with a standard split spoon (1.375-in ID). However, the large quantity of soil required for analysis, and the cobbles encountered in the uppermost geologic formation, the Upland Unit, made it necessary to use a 3-in ID stainless steel split spoon.

All sampling equipment was decontaminated prior to use and between samples in accordance with the protocol developed for the RFI/RI program. The basic steps in this protocol are: 1) washing with an approved laboratory detergent, 2) steam cleaning, 3) rinsing with reagent-grade Isopropanol, and 4) rinsing with dionized (DI) water. All personnel who handled samples or sampling equipment wore Pylox sampling gloves, which were changed frequently to avoid cross-contamination of samples.

The borings were excavated with a truck-mounted drill and 6.25-in OD hollow-stem augers to the specified depth, and the sampler lowered to the bottom of the augers on NWJ drill rods. A combination of hydraulic down pressure and a 140 pound hammer were then used to advance the sampler 24 inches, or to refusal. Upon recovery from the boring, the sampler was opened and the headspace monitored with an Organic Vapor Analyzer (OVA) or with an HNu photoionization detector (PID). The sample would then be split, and the entire length monitored with the HNu. The sampling assistant would immediately collect and seal a soil sample for volatile organic analysis (VOA), where specified. The remaining sample would then be blended in a stainless steel bowl, placed in sample containers provided by Weston, and packed on ice in coolers. The hydrogeologist used part of each sample to prepare a Field Geologic Log. A total of seven soil samples were collected from

TABLE 3-7

Soil Sampling Intervals and Analyses

Interval (ft)	Analyses*
0-1.5	1,2,3,6
1.5-3.0	1,2,3,6
3.0-4.5	1,4,5,6,7
4.5-6.0	1,4,5,6,7
10-11.5	1,4,5,6,7
15-16.5	1,4,5,6,7
20-21.5	1,4,5,6,7

4 QA/QC samples

* Specific analyses coded by group below.

Soil parameters

Group 1:	Soil pH
Group 1:	Specific conductance of soil
Group 1:	Volatile organic vapor or soil gas (field screening)
Group 1:	Total organic carbon (TOC)
Group 2:	TCLP
Group 3:	Appendix IX constituents
Group 4:	Volatile organic analyses
Group 5:	Semi-volatile organic compounds
Group 6:	Radionuclide scan - gross alpha, non-volatile beta, radium gamma PHA
Group 7:	Metals listed on Appendix IX

TABLE 3-8

Groundwater Analyses*
1,2,3,4,5,6

2 QA/QC samples

* Specific analyses coded by group below.

Field parameters

Group 1: pH
Group 1: Specific Conductance
Group 1: Temperature
Group 1: Field Alkalinity

Laboratory parameters

Group 2: pH
Group 2: Specific Conductance
Group 2: Temperature
Group 3: GC/MS scan (volatiles)
Group 4: Semi-volatile organic compounds
Group 5: Radionuclide scan:
gross alpha, non-volatile beta,
radium, gamma PHA
Group 6: Appendix IX metals

each test boring at specified intervals to a depth of 21.5 feet. Auger cuttings were logged below that depth to complete the Field Geologic Log. Therefore, the level of detail is significantly different in the segments of the logs above and below 21.5 ft. depth. The geologic logs are attached as Appendix C.

Groundwater samples were collected March 21, 1991 from FRT-3HP, -4HP and -5HP. Samples were collected with a Teflon bailer through the 2-in PVC casing previously placed in each of these borings. The groundwater samples were also placed in containers provided by Weston and packed on ice in coolers. Specific conductance, pH, temperature, and alkalinity were measured in the field and are recorded in Table 6. The samples designated for metals analysis were filtered in the field through 0.45 micron Nalgene disposable filter assemblies. A duplicate set of samples was collected from FRT-3HP and labeled as samples from FRT-2HP for QA/QC purposes. FRT-2HP is a fictitious boring number as FRT-2HP was not drilled. The duplicate metals sample was not filtered in the field. Borings FRT-3HP, -4HP and -5HP were grouted to the surface March 22, 1991, following completion of groundwater sampling. In general, samples were shipped within 24 hours after collection. Chain of custody forms were filed at the Well Building, (772-7B) at SRS.

3.3 Quality Assurance/Quality Control

Technical oversight of drilling activities was provided by Sirrine Environmental Consultants, Inc.. Two persons were available for most sampling and oversight activities, a hydrogeologist and a sampling assistant. The technical oversight personnel had extensive experience with this type of project and were very familiar with SRS procedures and protocols. Test equipment was calibrated daily in accordance with procedures specified by the manufacturers. Organic vapor screening was performed with a model HW101 HNu with a 10.2 electron volt (EV) probe. Field parameters for groundwater samples were determined with a HyDAC conductivity, temperature, pH Tester manufactured by Cambridge Scientific Industries. Groundwater temperature was verified with a Taylor Model 21424-1 thermometer with a range from -15° C to 105° C. Alkalinity was determined in the field with a Hach Digital Titrator, Model Number 6900-01.

QA/QC samples were included with shipments as specified in the Program Plan. These consisted mostly of trip blanks provided by Weston. Also, a complete set of duplicate ground water samples was collected from boring FRT-3HP and labeled with a fictitious boring number, FRT-2HP. The metals sample in the duplicate set was not filtered prior to shipment.

3.4 Project Field Files

Daily field activities were recorded in a bound journal as directed by the Groundwater Monitoring Group of WSRC-EPD. Photocopies of Daily Activity Reports and Field Geologic Logs are attached as Appendix C.

4.0 UNIT SCREENING RESULTS

4.1 Data Development

Laboratory analytical data from Weston arrived piecemeal over an extended period of time. The raw data was confusing and difficult to review. It was sent to Exploration Resources, Inc., a WSRC subcontractor in Athens, Georgia, for sorting and validation. Weston later sent the data to Exploration Resources on electronic media for sorting by computer. A printout of the test data, consisting of 295 single-spaced pages, was forwarded to Sirrine for review and incorporation into the report.

Review of the voluminous analytical data revealed that few analytes were reported above detection limits. Therefore, Exploration Resources used electronic sorting methods to produce tables that included only those analytes reported above detection limits. Summaries of soil sample analytical results are presented as Tables 4-1 through 4-6. Table 4-7 summarizes analytical data for the groundwater samples. A separate listing of analytes not detected was compiled in a Memo from Kathleen Gore to William Fay of Exploration Resources on August 23, 1991. That memo is included in this report as Appendix A.

4.2 Findings

Based on data available, it is concluded that no hazardous substances have been released to the soils by the crosstie pile. Constituent values were compared with background values reported by Looney, et. al.¹⁷ and with Drinking Water Standards (DWS). The soil series identified in the vicinity of the crosstie pile are the Blanton and Fuquay soil series and Udorthent soils. Udorthent is a generic term for sites where the natural soil horizons have been disrupted, usually by construction activities. The range of background soil values for each series is presented in Tables 4-8 through 4-10, along with the mean and standard deviation, where those can be calculated. In many instances, analytes were below detection limits, rendering mean and standard deviation calculations invalid.

4.2.1 Metals in Soil Samples

Constituent values for metals detected in soil samples at the unit are listed on Table 4-1. Metals are natural components of soils with widely varying concentrations. For example, a clean sand might have no detectables, while a clay or silt might be expected to have relatively high concentrations of various metals. The only metal detected at levels outside the range of background soil concentrations is copper. The range for copper in Blanton, Fuquay, and Udorthent soils is 0.36 to 11.1 mg/kg and three of the 28 values for copper exceeded this range. Those samples were: 11.7 mg/kg from a depth of 20 to 21.5 feet in FRT-1HP, 14.1 mg/kg from a depth of 10 to 11.5 feet in FRT-3HP, and 16.5 mg/kg from a depth of 15 to 16.5 feet in FRT-4HP. It is difficult to attribute these slightly elevated levels of copper to the railroad crosstie pile due to the depth at which they were encountered.

4.2.2 Organic Analytes in Soil Samples

Only three organic analytes were reported above detection limits in soil samples; acetone and pyridine from a depth 0.0 to 1.5 feet in FRT-3HP, and toluene in one or more samples in all borings. However, the acetone and pyridine were reported at the detection limit and toluene was reported at the detection limit of 6 mcg/kg in FRT-1HP and FRT-5HP. As shown on Table 4-2,

toluene was reported at levels ranging from 12 mcg/kg to 80 mcg/kg in FRT-3HP and FRT-4HP. These values are well above detection limits in two samples but well below the proposed DWS for toluene of 1,000 mcg/L.

4.2.3 Other Analytes in Soil Samples

All parameters for percent solids, cyanide, sulfide, pH, specific conductance, and total organic carbon (TOC) were reported within the range of anticipated and background values for soil, as shown on Table 4-3.

4.2.4 Metals in TCLP Samples

Barium was reported in TCLP test results from all test borings (see Table 4-4). The highest reported value was 684 mcg/l for the sample collected at a depth of 1.5 to 3.0 feet in the background soil boring, FRT-5HP. Cadmium was reported in the TCLP test result on the soil sample from 0.0 to 1.5 feet in FRT-5HP at a level of 5.2 mcg/l. That value is essentially at the detection limit of 5.0 mcg/l. These values are well below the allowable TCLP concentrations listed in 40 CFR 268.41, and also less than DWS of 1000 mcg/l and 10 mcg/l, respectively.

4.2.5 Radionuclides in Soil Samples

Radionuclide activities in soil samples are listed on Table 4-5 and summarized on Table 4-6. Background values reported by Looney, et.al.¹⁷ and Fay and Pickett¹⁸ are included on Table 4-6 for comparison. Activities for gross alpha, non-volatile beta, and total radium are well above background in all but five of the 28 soil samples. Gross alpha and non-volatile beta appear to be significantly higher in the background boring, FRT-5HP, and in the "side-gradient" boring, FRT-1HP, than in the two "down-gradient" borings, FRT-3HP and FRT-4HP. However, the reverse appears to be true for total radium values. There do not appear to be any statistically significant trends in constituent activities with respect to sample depth. The test values do not fit a normal distribution, and therefore, a larger sample population would be needed for Analysis of Variance and determination of statistical significance. It is not possible at this time to attribute elevated soil radionuclide activities to the F-Area Railroad Crosstie Pile.

4.2.6 Analytes Detected in Groundwater Samples

Groundwater samples were collected from three test borings, FRT-3HP, 4HP, and 5HP. In addition, a replicate sample was collected from FRT-3HP. The replicate metals sample was not filtered in the field. Groundwater sample data are presented on Table 4-7. Drinking Water Standards (DWS) are summarized in Table 4-11. Gross alpha activities ranged from 150 pCi/L in FRT-3HP to 830 pCi/L in FRT-5HP, well above DWS of 15 pCi/L. Similarly, non-volatile beta activities ranged from 85 pCi/L in the replicate sample from FRT-3HP to 280 pCi/L in FRT-4HP, again much higher than DWS of 50 pCi/L. In addition, these activities are much higher than in the nearby FBP well series. Groundwater sample data from the third quarter of 1984 to the first quarter of 1991 are summarized in Appendix B for the FBP wells. The radionuclides cesium-137 and total radium are well below DWS in all wells.

Reported values for specific conductance are about 100 times those measured in the field, and about 20 to 100 times those normally measured in the FBP wells. This indicates incorrect units of measurement may have been reported by the laboratory. Weston has not yet responded to inquiries on this issue.

Barium and chromium were reported above DWS in the unfiltered replicate sample from FRT-3HP, but below detection limits in the filtered sample.

The organic analytes tetrachloroethylene and trichloroethylene were detected above DWS in FRT-3HP and well above DWS in FRT-5HP along with carbon tetrachloride and trichlorofluoromethane. No organic analytes were detected in FRT-4HP. The values reported for FRT-5HP are in line with those reported for the FBP wells which are upgradient toward F-Area.

The analytes detected in the groundwater downgradient from the unit cannot be attributed to the railroad crosstie pile as they are not significantly different than the values reported for the upgradient, background test boring.

TABLE 4-1

Metals detected in F-Area Tie Yard soil samples

<u>Core #</u>	<u>Depth Interval</u> (feet)	<u>Chromium</u> mg/Kg	<u>Copper</u> mg/Kg	<u>Lead</u> mg/Kg	<u>Mercury</u> mg/Kg	<u>Vanadium</u> mg/Kg	<u>Zinc</u> mg/Kg
1	0.0-1.50	3.9	< 4.5	1.70	0.14	< 9.1	23.3
	1.5-3.00	9.8	< 4.8	2.60	< 0.11	< 9.6	10.4
	3.0-4.50	7.3	< 5.0	3.50	< 0.12	16.0	4.7
	4.5-6.00	8.5	< 4.8	1.20	< 0.11	16.1	7.4
	10.0-11.50	6.9	6.8	2.20	< 0.12	21.8	10.3
	15.0-16.50	6.5	< 4.6	1.30	< 0.12	18.2	6.7
	20.0-21.50	6.8	11.7	1.10	< 0.12	11.3	12.0
3	0.0-1.50	4.9	< 5.3	2.70	< 0.11	10.8	4.5
	1.5-3.00	3.6	< 5.1	0.88	< 0.12	< 10.2	< 4.1
	3.0-4.50	4.4	< 5.1	0.82	< 0.10	< 10.2	< 4.1
	4.5-6.00	7.0	< 5.0	4.30	0.16	12.9	20.1
	10.0-11.50	5.6	14.1	5.20	< 0.12	10.6	29.5
	15.0-16.50	3.2	< 4.7	1.5	< 0.12	< 9.4	5.3
	20.0-21.50	10.0	< 4.8	1.40	0.15	9.8	6.3
4	0.0-1.50	13.7	< 5.3	3.50	< 0.12	19.9	< 4.2
	1.5-3.00	8.5	< 3.9	4.30	< 0.11	14.9	3.6
	3.0-4.50	9.9	< 4.9	4.80	< 0.12	18.1	< 3.9
	4.5-6.00	4.7	5.6	1.10	< 0.11	< 11.0	6.1
	10.0-11.50	3.8	9.1	< 0.67	< 0.11	< 8.5	7.2
	15.0-16.50	3.1	16.5	0.88	< 0.11	< 8.2	13.0
	20.0-21.50	< 1.7	< 4.3	< 0.59	< 0.11	< 8.7	4.0
5	0.0-1.50	2.4	< 3.9	1.80	< 0.11	< 7.8	5.2
	1.5-3.00	2.2	< 3.8	0.75	< 0.10	< 7.7	5.3
	3.0-4.50	12.6	< 4.8	3.10	< 0.12	17.1	4.4
	4.5-6.00	5.8	< 4.6	1.20	< 0.12	11.3	8.9
	10.0-11.50	3.5	8.0	1.20	< 0.12	< 10.2	17.6
	15.0-16.50	< 2.1	< 5.3	0.85	< 0.12	< 10.6	9.9
	20.0-21.50	2.2	< 4.9	1.50	< 0.11	< 9.8	6.1

Note: Core 1 = FRT-1HP, Core 3 = FRT-3HP, Core 4 = FRT-4HP, and Core 5 = FRT-5HP

Compiled by Exploration Resources, Inc.

TABLE 4-2

Organic analytes detected in F-Area Tie Yard soil samples

<u>Core #</u>	<u>Depth Interval</u> (feet)	<u>Acetone</u> $\mu\text{g/Kg}$	<u>Pyridine</u> $\mu\text{g/Kg}$	<u>Toluene</u> $\mu\text{g/Kg}$
1	0.0-1.50	B 22	< 350	6
	1.5-3.00	B 130	< 370	< 6
	3.0-4.50	B 92	< 410	< 6
	4.5-6.00	B 95	< 380	< 6
	10.0-11.50	B 70	< 400	< 6
	15.0-16.50	B 100	< 400	< 6
	20.0-21.50	B 150	< 380	J 3
3	0.0-1.50	220	390, < 360	41
	1.5-3.00	B 56	< 440	80
	3.0-4.50	B 240	< 380	J 3
	4.5-6.00	B 340	< 390	J 5
	10.0-11.50	B 320	< 380	12
	15.0-16.50	B 400	< 350	J 18
	20.0-21.50	B 40	< 370	J 4
4	0.0-1.50	B 16	< 390	12
	1.5-3.00	B 3100	< 350	J 3
	3.0-4.50	B 110	< 390	J 2
	4.5-6.00	B 210	< 380	J 3
	10.0-11.50	B 130	< 370	< 6
	15.0-16.50	B 2800	< 360	J 5
	20.0-21.50	B 77	< 340	< 6
5	0.0-1.50	B 30	< 340	< 6
	1.5-3.00	B 5200	< 340	J 1
	3.0-4.50	B 5000	< 380	< 6
	4.5-6.00	B 220	< 380	J 3
	10.0-11.50	B 54	< 370	6
	15.0-16.50	B 56	< 380	J 2
	20.0-21.50	B 43	< 370	J 5

Note: Core 1 = FRT-1HP, Core 3 = FRT-3HP, Core 4 = FRT-4HP, and Core 5 = FRT-5HP
 "B" indicates analyte found in blank; "J" indicates estimated value below quantification level.

Compiled by Exploration Resources, Inc.

TABLE 4-3

Other analytes detected in F-Area Tie Yard soil samples

<u>Core #</u>	<u>Depth interval</u> (feet)	<u>Solids</u> %	<u>Cyanide</u> mg/Kg	<u>Sulfide</u> mg/kg	<u>pH</u>	<u>Spec. Cond.</u> μS/cm	<u>TOC</u> %
1	0.0-1.50	93.6	< 1.1	< 0.27	5.6	12.1	0.18
	1.5-3.00	87.7	< 1.1	< 0.28	5.3	8.6	0.96
	3.0-4.50	87.2			5.0	8.8	1.70
	4.5-6.0	87.8			4.9	9.0	1.30
	10.0-11.50	84.8			5.0	8.5	1.50
	15.0-16.50	85.4			5.0	9.6	1.60
	20.0-21.50	87.0			5.1	7.1	1.30
3	0.0-1.50	87.6	< 1.1	< 0.28	4.5	16.1	1.70
	1.5-3.00	86.0	< 1.2	< 0.29	4.9	15.8	1.20
	3.0-4.50	95.4			5.1	9.8	0.83
	4.5-6.0	81.8			5.1	7.8	1.80
	10.0-11.50	86.2			5.0	12.2	1.00
	15.0-16.50	86.8			5.0	10.2	1.10
	20.0-21.50	88.8			6.3	8.8	0.96
4	0.0-1.50	87.0	< 1.1	< 0.29	5.0	15.5	2.40
	1.5-3.00	91.6	< 1.1	< 0.27	5.3	13.7	0.85
	3.0-4.50	80.9			4.9	20.4	1.50
	4.5-6.0	90.9					
	10.0-11.50	88.8			5.2	8.9	0.99
	15.0-16.50	90.8			5.3	10.9	0.79
	20.0-21.50	93.3			5.2	12.5	0.23
5	0.0-1.50	94.4	< 1.1	< 0.26	5.0	11.8	0.30
	1.5-3.00	95.5	< 1.0	0.30	5.2	11.4	0.01
	3.0-4.50	80.6			5.2	11.3	1.50
	4.5-6.0	85.7			5.0	8.2	1.50
	10.0-11.50	86.5			5.1	13.4	1.10
	15.0-16.50	86.8			5.0	8.9	1.40
	20.0-21.50	87.6			5.2	10.1	1.20

Note: Core 1 = FRT-1HP, Core 3 = FRT-3HP, Core 4 = FRT-4HP, and Core 5 = FRT-5HP

Compiled by Exploration Resources, Inc.

TABLE 4-4

Metals detected in F-Area Tie Yard TCLP samples

<u>Core #</u>	<u>Depth Interval</u> (feet)	<u>Barium</u> $\mu\text{g/L}$	<u>Cadmium</u> $\mu\text{g/L}$
1	0.0-1.50	< 200	< 5.0
	1.5-3.00	382	< 5.0
3	0.0-1.50	281	< 5.0
	1.5-3.00	< 200	< 5.0
4	0.0-1.50	283	< 5.0
	1.5-3.00	< 200	< 5.0
5	0.0-1.50	< 200	5.2
	1.5-3.00	684	< 5.0

Note: Core 1 = FRT-1HP, Core 3 = FRT-3HP, Core 4 = FRT-4HP, and Core 5 = FRT-5HP
Compiled by Exploration Resources, Inc.

TABLE 4-5

Radionuclides detected in F-Area Tie Yard soil samples

<u>Core #</u>	<u>Depth Interval</u> (feet)	<u>Gross Alpha</u> pCi/g	<u>Nonvolatile Beta</u> pCi/g	<u>Cesium-137</u> pCi/g	<u>Thorium-232</u> pCi/g	<u>Total Radium</u> pCi/g
1	0.0-1.50	50.0±12.0	16.0±4.0		0.9±0.1	3.7±0.3
	1.5-3.00	44.0±13.0	20.0±4.0		1.5±0.3	3.9±0.3
	3.0-4.50	31.0±12.0	27.0±5.0		1.0±0.2	1.9±0.3
	4.5-6.00	58.0±15.0	11.0±4.0		1.1±0.2	2.2±0.3
	10.0-11.50	48.0±12.0	19.0±3.0		1.8±0.3	4.3±0.4
	15.0-16.50	22.0±9.0	20.0±5.0		0.8±0.4	3.7±0.4
	20.0-21.50	36.0±12.0	15.0±5.0		0.7±0.2	2.6±0.3
3	0.0-1.50	29.0±10.0	9.8±3.1	0.0±0.1	0.0±0.2	6.1±0.6
	1.5-3.00	26.0±9.0	13.0±3.0	0.0±0.1	0.5±0.2	5.4±0.5
	3.0-4.50	33.0±11.0	9.6±4.3	0.0±0.1	0.3±0.2	3.1±0.4
	4.5-6.00	22.0±8.0	16.0±4.0	0.0±0.0	1.1±0.3	7.4±1.3
	10.0-11.50	0.0±11.0	10.0±4.0	0.0±0.1	1.1±0.2	4.3±0.5
	15.0-16.50	20.0±9.0	12.0±4.0	0.0±0.2	1.3±0.2	6.0±0.5
	20.0-21.50	25.0±10.0	28.0±4.0	0.0±0.1	1.3±0.2	13.0±1.0
4	0.0-1.50	54.0±13.0	21.0±4.0	0.2±0.2	1.8±0.2	11.0±1.0
	1.5-3.00	52.0±14.0	20.0±4.0	0.0±0.1	1.4±0.2	7.5±0.6
	3.0-4.50	49.0±13.0	15.0±4.0	0.0±0.2	1.1±0.2	12.0±1.0
	4.5-6.00	23.0±11.0	16.0±4.0	0.0±0.2	1.3±0.3	6.3±0.6
	10.0-11.50	20.0±10.0	0.0±6.5	0.0±0.1	0.7±0.2	4.9±0.5
	15.0-16.50	9.8±8.0	13.0±4.0	0.0±0.1	1.0±0.2	5.7±0.5
	20.0-21.50	0.0±9.7	11.0±4.0	0.0±0.2	0.0±0.2	7.2±0.6
5	0.0-1.50	41.0±12.0	25.0±5.0		0.9±0.1	2.7±0.2
	1.5-3.00	46.0±14.0	23.0±4.0		1.0±0.2	2.7±0.2
	3.0-4.50	40±12	34.0±6.0		1.3±0.2	2.3±0.2
	4.5-6.00	34±11	11.0±4.0		1.0±0.3	1.1±0.2
	10.0-11.50	44±12	22.0±5.0		1.4±0.2	0.8±0.1
	15.0-16.50	45±13	34.0±5.0		1.5±0.3	2.2±0.2
	20.0-21.50	62±16	24.0±5.0		2.1±0.3	0.7±0.1

Note: Core 1 = FRT-1HP, Core 3 = FRT-3HP, Core 4 = FRT-4HP, and Core 5 = FRT-5HP

Compiled by Exploration Resources, Inc.

TABLE 4-6

Soil Sample Radionuclide Summary
F-Area Railroad Crosstie Pile

<u>Boring</u>	<u>Mean</u>	<u>S</u>	<u>Sample Size</u>
Gross Alpha, pCi/g			
Background ¹⁷	7.14	2.6	168
FRT-1HP	41.3	12.34	7
FRT-3HP	22.1	10.67	7
FRT-4HP	29.7	21.90	7
<u>FRT-5HP</u>	44.6	8.68	7
All Samples	34.4	16.32	28
Non-Volatile Beta, pCi/g			
Background ¹⁷	9.58	4.14	168
FRT-1HP	18.3	5.02	7
FRT-3HP	14.1	6.56	7
FRT-4HP	13.7	7.02	7
<u>FRT-5HP</u>	24.7	7.87	7
All Samples	17.7	7.76	28
Total Radium, pCi/gr			
Background ^{*18}	0.89	0.35	18
FRT-1HP	3.2	0.94	7
FRT-3HP	6.5	3.19	7
FRT-4HP	7.8	2.69	7
<u>FRT-5HP</u>	1.8	0.89	7
All Samples	4.8	3.21	28

*Radium 226 only

TABLE 4-7
GROUNDWATER ANALYSES

Radionuclides detected in F-Area Tie Yard water samples

<u>Analyte</u>	<u>Core 3</u>	<u>Core 3 Replicate</u>	<u>Core 4</u>	<u>Core 5</u>
Gross Alpha (pCi/L)	150±30	300±70	830±110	360±80
Nonvolatile Beta (pCi/L)	130±30	85±19	280±30	110±20
Cesium-137 (pCi/L)	0±18	0±30	0±15	16±14
Total Radium (pCi/L)	0.4±0.2	1.2±0.4	0.7±0.3	0.5±0.2

Other Analyses of F-Area Tie Yard water samples

<u>Analyte</u>	<u>Core 3</u>	<u>Core 3 Replicate</u>	<u>Core 4</u>	<u>Core 5</u>
Specific Conductance (µS/cm)	2220	2210	2010	5610
pH	5.2	5.1	5.3	5.9

Metals Analytes detected in F-Area Tie Yard water samples

<u>Analyte</u>	<u>Core 3 Filtered</u>	<u>Core 3 Replicate Unfiltered</u>	<u>Core 4 Filtered</u>	<u>Core 5 Filtered</u>
Barium (µg/L)	<200	3490	<200	<200
Beryllium (µg/L)	<5	17	<5	<5
Cobalt (µg/L)	<50	421	<50	<50
Chromium (µg/L)	<10	91.1	<10	<10
Copper (µg/L)	<25	150	<25	<25
Lead (µg/L)	<3	15	<3	<3
Mercury (µg/L)	<0.2	1.2	<0.2	<0.2
Nickel (µg/L)	<40	74.7	<40	<40
Silver (µg/L)	<10	27.9	<10	<10
Tin (µg/L)	<100	121	<100	<100
Vanadium (µg/L)	<50	219	<50	<50
Zinc (µg/L)	60.8	352	20.1	<20

Organic Analytes detected in F-Area Tie Yard water samples

<u>Analyte</u>	<u>Core 3</u>	<u>Core 3 Replicate</u>	<u>Core 4</u>	<u>Core 5</u>
Carbon Tetrachloride (µg/L)	J3	J3	<5	10
Tetrachloroethylene (µg/L)	10	10	<5	46
Trichloroethylene (µg/L)	11	15	<5	81
Trichlorofluoromethane (µg/L)	46	27	<5	49

Note: Core 1 = FRT-1HP, Core 3 = FRT-3HP, Core 4 = FRT-4HP, and Core 5 = FRT-5HP
"J" Indicates estimated value below quantification level.

Compiled by Exploration Resources, Inc.

TABLE 4-8
F-AREA RAILROAD CROSSTIE PILE VICINITY
RANGE OF BACKGROUND SOIL CONCENTRATIONS

Blanton Soil Series				
<u>Analyte</u>	<u>Unit</u>	<u>Range</u>	<u>Mean</u>	<u>Standard Deviation</u>
Al	(ug/g)	715-27,512	9061	7265
As	(ug/g)	<0.5-7.05	*	*
Ba	(ug/g)	2.4-31.6	12.2	8.08
Cd	(ug/g)	0.27-0.99	*	*
Cr	(ug/g)	1.7-35.2	12.7	9.92
Cu	(ug/g)	0.36-8.2	3.1	2.26
Fe	(ug/g)	1200-37,740	10,394	11,229
Pb	(ug/g)	0.68-7.84	3.9	2.07
Mg	(ug/g)	20.1-296.7	104.7	62.1
Mn	(ug/g)	<1.6-138.5	*	*
Hg	(ug/g)	<0.1-0.25	*	*
Ni	(ug/g)	0.11-9.6	*	*
K	(ug/g)	<40-<800	*	*
Se	(ug/g)	<0.2-<4.0	*	*
Ag	(ug/g)	0.24-<1.0	*	*
Na	(ug/g)	20.1-109.4	45.4	17.9
Zn	(ug/g)	3.0-24.6	9.2	4.53
Cl	(ug/g)	<1.25-11.2	*	*
Nitrate as Nitrogen	(ug/g)	<0.5-11.6	*	*
Sulfate	(ug/g)	<5-18.2	*	*
TOC	(ug/g)	270-8842	1845	2102
Gross Alpha	(PCI/g)	2.9-10.0	*	*
Nonvolatile	(PCI/g)	<5.0-16	*	*
Beta				
Uranium	(PCI/g)	<1-2.2	*	*

Derived from Looney, et al, 1990¹⁷

Soil Intervals Sampled

0-6 in, 7-61in, 61-76 in. and 98-121in

* Range includes values below detection limit. Mean and standard deviation calculations would not yield valid results.

TABLE 4-9
F-AREA RAILROAD CROSSTIE PILE VICINITY
RANGE OF BACKGROUND SOIL CONCENTRATIONS

<u>Analyte</u>	<u>Unit</u>	<u>Fuquay Soil Series</u>		
		<u>Range</u>	<u>Mean</u>	<u>Standard Deviation</u>
Al	(ug/g)	1974-31,640	12,502	10,380
As	(ug/g)	<0.5-15.2	*	*
Ba	(ug/g)	3.0-50.4	16.1	10.8
Cd	(ug/g)	<0.5-0.86	*	*
Cr	(ug/g)	2.28-105.1	20.86	20.92
Cu	(ug/g)	0.64-11.1	3.83	3.17
Fe	(ug/g)	885.9-79,600	16,160	19,401
Pb	(ug/g)	2.02-16.4	5.21	2.92
Mg	(ug/g)	40.53-436.1	152.8	114.4
Mn	(ug/g)	<1.6-92.7	*	*
Hg	(ug/g)	<0.1-0.89	*	*
Ni	(ug/g)	<2-17.9	*	*
K	(ug/g)	<40-326	*	*
Se	(ug/g)	<0.2-1.66	*	*
Ag	(ug/g)	<0.3-1.7	*	*
Na	(ug/g)	19.3-72.2	42.6	15.1
Zn	(ug/g)	2.2-19.6	9.2	4.54
Cl	(ug/g)	<1.25-10.7	*	*
Nitrate as Nitrogen	(ug/g)	<0.5-2.3	*	*
Sulfate	(ug/g)	<5-19.2	*	*
TOC	(ug/g)	121-13,146	1,970	3,035
Gross Alpha	(PCI/g)	<4-14	*	*
Nonvolatile	(PCI/g)	<6-16	*	*
Beta				
Uranium	(PCI/g)	<1-3.3	*	*

Derived from Looney, et al, 1990¹⁷

Soil Intervals Sampled

0-6 in, 7-40 in, 40-84 in. and 120-132 in

- * Range includes values below detection limit. Mean and standard deviation calculations would not yield valid results.

TABLE 4-10
F-AREA RAILROAD CROSSTIE PILE VICINITY
RANGE OF BACKGROUND SOIL CONCENTRATIONS

<u>Analyte</u>	<u>Unit</u>	<u>Udorthent Soils</u>		
		<u>Range</u>	<u>Mean</u>	<u>Standard Deviation</u>
Al	(ug/g)	2,899-43,320	11,577	9,384
As	(ug/g)	<2-5.99	*	*
Ba	(ug/g)	1.3-35.7	9.5	8.8
Cd	(ug/g)	<0.5-1.19	*	*
Cr	(ug/g)	7.3-34.2	19.6	7.99
Cu	(ug/g)	1.6-10.7	4.2	2.46
Fe	(ug/g)	3,637-35,400	15,525	9,486
Pb	(ug/g)	1-13.7	4.6	3.42
Mg	(ug/g)	24.4-255.4	93.3	63.2
Mn	(ug/g)	<1.6-27.9	*	*
Hg	(ug/g)	<0.1-0.15	*	*
Ni	(ug/g)	<2-8.5	*	*
K	(ug/g)	<40-259	*	*
Se	(ug/g)	<0.4-0.77	*	*
Ag	(ug/g)	<0.3-1.8	*	*
Na	(ug/g)	13.8-382	59.5	80.1
Zn	(ug/g)	1.8-30.1	10.6	7.22
Cl	(ug/g)	<1.25-19.7	4.95	4.01
Nitrate as Nitrogen	(ug/g)	<0.5-8.9	*	*
Sulfate	(ug/g)	<5-21.2	*	*
TOC	(ug/g)	32-5,260	572	1,033
Gross Alpha	(PCI/g)	<4-11	7.24	2.50
Nonvolatile	(PCI/g)	<7-23	10.1	3.38
Beta				
Uranium	(PCI/g)	<1-4.7	*	*

Derived from Looney, et al, 1990¹⁷

Soil Intervals Sampled

0-24 in, 24-48 in, and 48-72 in

- * Range includes values below detection limit. Mean and standard deviation calculations would not yield valid results.

Analyte	Level	Units	Status	Reference
Americium-241	4	pCi/L	proposed	EPA, 1986
Antimony-125	300	pCi/L	final	EPA, 1977
Arsenic	0.05	mg/L	final	CFR, 1987
Barium	1	mg/L	final	CFR, 1987
Barium-140	90	pCi/L	final	EPA, 1977
Benzene	0.005	mg/L	final	EPA, 1987
Beryllium-7	6,000	pCi/L	final	EPA, 1977
Cadmium	0.01	mg/L	final	CFR, 1987
Carbon-14	2,000	pCi/L	final	EPA, 1977
Carbon tetrachloride	0.005	mg/L	final	EPA, 1987
Cesium-134	20,000	pCi/L	final	EPA, 1977
Cesium-137	200	pCi/L	final	EPA, 1977
Chlordane	0.002	mg/L	proposed	EPA, 1989
Chloroethene (Vinyl chloride)	0.002	mg/L	final	EPA, 1987
Chloroform*	0.1	mg/L	final	CFR, 1987
Chromium	0.05	mg/L	final	CFR, 1987
Chromium-51	6,000	pCi/L	final	EPA, 1977
Cobalt-58	9,000	pCi/L	final	EPA, 1977
Cobalt-60	100	pCi/L	final	EPA, 1977
Dibromochloropropane	0.0002	mg/L	proposed	EPA, 1989
1,4-Dichlorobenzene (p-Dichlorobenzene)	0.075	mg/L	final	EPA, 1987
1,2-Dichloroethane	0.005	mg/L	final	EPA, 1987
trans-1,2-Dichloroethene	0.1	mg/L	proposed	EPA, 1989
1,1-Dichloroethylene	0.007	mg/L	final	EPA, 1987
2,4-Dichlorophenoxyacetic acid	0.1	mg/L	final	CFR, 1987
1,2-Dichloropropane	0.005	mg/L	proposed	EPA, 1989
Endrin	0.0002	mg/L	final	CFR, 1987
Ethylbenzene	0.7	mg/L	proposed	EPA, 1989
Fluoride	4	mg/L	final	CFR, 1986
Gross alpha	15	pCi/L	final	CFR, 1987
Heptachlor	0.0004	mg/L	proposed	EPA, 1989
Heptachlor epoxide	0.0002	mg/L	proposed	EPA, 1989
Iodine-129	1	pCi/L	final	EPA, 1977
Iodine-131	3	pCi/L	final	EPA, 1977
Iron-55	2,000	pCi/L	final	EPA, 1977
Iron-59	200	pCi/L	final	EPA, 1977
Lead	0.05	mg/L	final	CFR, 1987
Lindane	0.004	mg/L	final	CFR, 1987
Manganese-54	300	pCi/L	final	EPA, 1977
Mercury	0.002	mg/L	final	CFR, 1987
Methoxychlor	0.1	mg/L	final	CFR, 1987
Nickel-59	300	pCi/L	final	EPA, 1977

* The level for total trihalomethanes is set at 0.1 mg/L. Because bromated methanes are rarely detected in SRS groundwater, EHP presumes that most of the trihalomethanes present in site groundwater are chloroform.

TABLE 4-11 (cont'd)

Savannah River Site—Environmental Report for 1989

Analyte	Level	Units	Status	Reference
Nickel-63	50	pCi/L	final	EPA, 1977
Nitrate (as N)	10	mg/L	final	CFR, 1987
Nitrite (as N)	0.001	mg/L	proposed	EPA, 1989
Nonvolatile beta	50	pCi/L	proposed	EPA, 1986
PCBs	0.0005	mg/L	proposed	EPA, 1989
Pentachlorophenol	0.2	mg/L	proposed	EPA, 1989
Potassium-40	300	pCi/L	proposed	EPA, 1986
Radium-226	4	pCi/L	proposed	EPA, 1986
Radium-228	8	pCi/L	proposed	EPA, 1986
Ruthenium-103	200	pCi/L	final	EPA, 1977
Ruthenium-106	30	pCi/L	final	EPA, 1977
Selenium	0.01	mg/L	final	CFR, 1987
Silver	0.05	mg/L	final	CFR, 1987
Silvex	0.01	mg/L	final	CFR, 1987
Strontium-89	20 ^b	pCi/L	final	EPA, 1977
Strontium-90	8	pCi/L	final	EPA, 1977
Styrene	0.005	mg/L	proposed	EPA, 1989
Technetium-99	900	pCi/L	final	EPA, 1977
Tetrachloroethylene	0.005	mg/L	proposed	EPA, 1989
Tin-113	4,000	pCi/L	proposed	EPA, 1986
Toluene	2	mg/L	proposed	EPA, 1989
Total radium	5	pCi/L	final	CFR, 1987
Toxaphene	0.005	mg/L	final	CFR, 1987
1,1,1-Trichloroethane	0.2	mg/L	final	EPA, 1987
Trichloroethylene	0.005	mg/L	final	EPA, 1987
Tritium	20	pCi/mL	final	CFR, 1987
Uranium-234	28	pCi/L	proposed	EPA, 1986
Uranium-235	28	pCi/L	proposed	EPA, 1986
Uranium-238	28	pCi/L	proposed	EPA, 1986
Xylenes	10	mg/L	proposed	EPA, 1989
Zinc-65	300	pCi/L	final	EPA, 1977
Zirconium-95	200	pCi/L	final	EPA, 1977

^b This is the lower of two levels given for strontium-89.

References:

- CFR (Code of Federal Regulations), 1986. "National Primary Drinking Water Regulations," 40 CFR, Part 141, pp. 521-568, Washington, DC.
- CFR (Code of Federal Regulations), 1987. "National Primary Drinking Water Regulations," 40 CFR, Part 141, pp. 526-575, Washington, DC.
- EPA (U.S. Environmental Protection Agency), 1977. *National Interim Primary Drinking Water Regulations*, EPA-570/9-76-003, Washington, DC.
- EPA (U.S. Environmental Protection Agency), 1986. "Water Pollution Control; National Primary Drinking Water Regulations, Radionuclides (Proposed)," *Federal Register*, September 30, 1986, pp. 34836-34862, Washington, DC.
- EPA (U.S. Environmental Protection Agency), 1987. "National Primary Drinking Water Regulations; Synthetic Organic Chemicals; Monitoring for Unregulated Contaminants," *Federal Register*, July 8, 1987, pp. 25690-25717, Washington, DC.
- EPA (U.S. Environmental Protection Agency), 1989. "National Primary and Secondary Drinking Water Regulations (Proposed Rule)," *Federal Register*, May 22, 1989, pp. 22062-22160, Washington, DC.

REFERENCES

1. Bignell, D.T., WSRC, Railroad Crosstie Disposal Alternatives, Letter to Mr. Donald Gross, Jr, DOE.(January, 1991)
2. AAR, Toxicity Characteristic Leaching Procedure Testing of Railroad Crossties (R-708). Association of American Railroads, Chicago, IL (1988)
3. USDA, Soil Survey of Savannah River Plant Area. Parts of Aiken, Barnwell, And Allendale Counties, South Carolina. U. S. Department of Agriculture, Soil Conservation Service, (1990)
4. Aadland, R.K, and H.W. Bledsoe, Classification of Hydrostratigraphic Units at Savannah River Site, South Carolina. WSRC-RP-90-987, WSRC, Savannah River Laboratory, Aiken, SC (1990).
5. Price, V., "Subsurface Hydrogeology," in Stephenson, A.2., ed., Final Safety Analysis Report for DWPF (Draft). DPSTSA-200-10, E.I. du Pont de Nemours and Company, Savannah River Plant, Aiken, SC (1988).
6. WSRC, Savannah River Site Environmental Report for 1988. WSRC-RP-89-59, Westinghouse Savannah River Company for the U.S. Department of Energy, Aiken, SC (1988).
7. Fallaw, W.C., Subsurface Stratigraphy and Structure of the A- and M-Area at the Savannah River Site, Aiken, SC, WSRC (DRAFT, 1990);
8. Olson, C., Wells Monitored by the Health Protection Department. HPR-88-001, E.I. du Pont de Nemours and Company and Exploration Software, Savannah River Plant, Aiken, SC (1988).
9. Bledsoe, H.W., SRP Baseline Hydrogeologic Investigation - Phase III. DPST-88-627, E.I. du Pont de Nemours & Co., Savannah River Laboratory, Aiken, SC (1988)
10. WSRC, Site Hydrogeologic/Geotechnical Characterization Report for Site B, New Municipal Soil Waste Landfill, WSRC-RP-91-392, Westinghouse Savannah River Company for the U.S. Department of Energy, Aiken, SC (1991).
11. Huber, L.A. and H.W. Bledsoe, Environmental Information Document, Hydrofluoric Acid Spill Area. DPST-85-696, E.I. du Pont de Nemours and Company, Savannah River Laboratory, Aiken, SC (1987).
12. Duffield, G. M., D. R. Buss, R.W. Root, Jr., S.S. Hughes, and J.W. Mercer, Characterization of Groundwater Flow and Transport in the General Separations Areas, Savannah River Plant: Flow Model Refinement and Particle Tracking Analysis. CORR-86-0031, Geo Trans, Inc., for E.I. du Pont de Nemours and Company, Savannah River Laboratory, Aiken, SC (1986).

13. USDOE, Final Environmental Impact Statement: Waste Management Activities for Groundwater Protection, Savannah River Plant, Aiken, South Carolina. DOE/EIS-0120, U.S. Department of Energy, Savannah River Operations Office, Aiken, SC (1987).
14. Root, R.W., Jr. Groundwater Data from the H-Area, Savannah River Plant, South Carolina. DPST-80-601, E.I. du Pont de Nemours and Company, Savannah River Laboratory, Aiken, SC (1980)
15. WSRC, Hydrogeologic Data Collection Methods, Procedures and Specifications. DPSOP 254, adapted by WSRC from E.I. du Pont de Nemours and Company, Savannah River Site, Aiken, SC (1987 or latest version).
16. WSRC, RCRA Facility Investigation/Remedial Investigation (RFI/RI) Program Plan. WSRC-RP-89-994, Westinghouse Savannah River Company, Aiken, SC (1989)
17. Looney, B.B., C.A. Eddy, M. Ramdeen, J. Pickett, V. Rogers, M.T. Scott and P.A. Shirley, Geochemical and Physical Properties of Soils and Shallow Sediments at the Savannah River Site (u). WSRC-RP-90-1031, Westinghouse Savannah River Company, Aiken, SC (1990).
18. Fay, W. M., and J. B. Pickett, Documentation of 1982 Soil Analyses to Determine the Natural Background Radioactivity in SRP Surface Soils. DPST-87 260, E.I. du Pont de Nemours and Company, Savannah River Laboratory, Aiken, SC (1987).
19. WSRC, Savannah River Site Environmental Report for 1989. WSRC-IM-90-60, Westinghouse Savannah River Company for the U.S. Department of Energy, Aiken, SC (1989).

The following documents were reviewed as part of the Unit Literature Review, but not cited.

- * Bledsoe, H.W., SRP Baseline Hydrogeologic Investigation - Phase II. DPST-86-674, E.I. du Pont de Nemours & Co., Savannah River Laboratory, Aiken, SC (1987)
- * Christensen, E.I. and D.E. Gordon, Technical Summary of Groundwater Quality Protection Program at Savannah River Plant, Vol. 1: Site Geohydrology, and Solid and Hazardous Wastes. DPST-83-829, E.I. du Pont de Nemours and Company, Savannah River Laboratory, Aiken, SC (1983).
- * du Pont, Technical Summary, Ground Water Quality Impact of Waste Disposal at Savannah River Plant, an update of DPST 83-829* E. I. du Pont de Nemours and Company, Savannah River Plant, Aiken, SC (1987).

- * Gordon, D.E., W.E. Johnson, D.S. Kaback, B.B. Looney, R.L. Nichols, C.B. Shedrow, Characterization Recommendations for Waste Sites at the Savannah River Plant. DPST-87-667, E.I. du Pont de Nemours and Company, Savannah River Laboratory, Aiken, SC (1987).
- * King, C.M., W.L. Marter, B.B. Looney, and J.B. Pickett, Methodology and Parameters for Assessing Human Health Effects for Waste Sites at the Savannah River Plant. DPST-86-298, E.I. du Pont de Nemours and Company, Savannah River Laboratory, Aiken, SC (1987).
- * Looney, B.B., J.B. Pickett, C.M. King, W.G. Holmes, W.E. Johnson, and J.A. Smith, Selection of Chemical Constituents and Estimation of Inventories for Environmental Analysis of Savannah River Plant Waste Sites. DPST-86-291, (1987).
- * SAIC, Ecologic Assessment of Closure Options for Savannah River Plant Waste Sites. CORR-870116 Report to E.I. du Pont by Science Applications International Corporation, Oak Ridge, TN (1987).
- * Schalles, J.F., R.R. Sharitz, J.W. Gibbons, G.J. Leversee, and J.N. Knox, Carolina Bays of the Savannah River Plant. SRO-NERP-18, National Environmental Research Park Program, Savannah River Plant, Aiken, SC (1989).
- * Shields, J.D., N.D. Woody, A.S. Dicks, G.J. Hollod, J. Shalles, and G.J. Leversee, Locations and Areas of Ponds and Carolina Bays at the Savannah River Plant. DP-1525, E.I. du Pont de Nemours and Company, Savannah River Plant, Aiken, SC (1982).
- * USEPA, Test Methods for Evaluating Solid Waste. Volume 1. Methods for Analytes and Properties. Third Edition. EPA SW-846, Office of Solid Waste and Emergency Response, Washington, DC (1986).
- * USEPA, Data Quality Objectives for Remedial Response Activities. EPA 540/G-87/003, Washington, DC (1987).
- * USEPA, Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA. Interim Final. EPA/540/G-89/004 (1988);
- * WSRC, 5Q. Radiological Controls Manual. DPSOP 40, adapted by WSRC from E.I. du Pont de Nemours and Company, Savannah River Site, Aiken, SC (current version).
- * WSRC, Health Protection Department Radiation Survey Procedures. DPSOL 193, adapted by WSRC from E.I. du Pont de Nemours and Company, Savannah River Site, Aiken, SC (current version).

APPENDIX A
ANALYTES NOT FOUND
AT THE
F-AREA RAILROAD CROSSTIE PILE

Appendix A

FAX COVER SHEET

Date: 8/22/91

TO:

Name: Chuck TRAVIS

Address: SIRrine Environmental

City: Aiken State: SC

Regular Phone No.: 803-649-5175

FAX No. 803-649-5178

Note: Here is some material you can work with. I will call you on Monday

From: William FAY

EXPLORATION RESOURCES, INC.
425 NORTH LUMPKIN ST.
ATHENS, GA 30601

REGULAR PHONE NO.: (404) 353-7983
FAX NO.: (404) 546-8111

No. of pages including this cover sheet 6

MEMO

TO: William Fay

FROM: Kathleen Gore *Kg*

DATE: August 23, 1991

SUBJECT: Tieyard core analyses

Each of the four cores, FRT-1HP, FRT-3HP, FRT-4HP, and FRT-5HP, had 7 sediment samples. The analyses requested for each core were:

pH, specific conductance, TOC samples 1-7 (except sample 4 of FRT-4HP)

App. IX Inorganics:

 Cyanide, sulfide

 samples 1-2

 App. IX metals

 samples 1-7

App. IX Organics

 VOA

 samples 1-7

 BNA

 samples 1-7

 Pest/Herb

 samples 1-2

 Dioxins/Furans

 samples 1-2

 samples 1-7

Rads

 Gross alpha

 Nonvolatile beta

 Total radium

 Gamma PHA (only Th-232 for FRT-1 and -5; Cs-137 and Th-232 for FRT-3 and -4.)

The following analytes from the Appendix IX Inorganics suite, Metals narratives, were not detected in any samples:

Antimony

Nickel

Arsenic

Selenium

Barium

Silver

Beryllium

Thallium

Cadmium

Tin

Cobalt

The following analytes from the Appendix IX Organics suite, Dioxin/Furan subsuite, Dioxin narrative, were not detected in any samples:

PeCDD
PeCDF
Hexachlorodibenzo-p-dioxin isomers
Hexachlorodibenzo-p-furan isomers
Tetrachlorodibenzo-p-dioxin isomers
Tetrachlorodibenzo-p-furan isomers

The following analytes from the Appendix IX Organics suite, Herb/Pest subsuite, Organophosphorus pesticide narrative, were not detected in any samples:

Diazinon	Methyl parathion
Dimethoate	Phorate
Disulfoton	Sulfotepp
Famphur	Thionazin
Ethyl parathion	o,o,o-Triethyl phosphorothioate

The following analytes from the Appendix IX Organics suite, Herb/Pest subsuite, Pest/PCB narrative, were not detected in any samples:

Aldrin	Endrin aldehyde
alpha-Benzene hexachloride	Heptachlor
delta-Benzene hexachloride	Heptachlor epoxide
gamma-Benzene hexachloride (Lindane)	Isodrin
alpha-Chlordane	Kepone
gamma-Chlordane	Methoxychlor
4,4'-DDD	Aroclor-1016
4,4'-DDE	Aroclor-1221
4,4'-DDT	Aroclor-1232
Dieldrin	Aroclor-1242
Endosulfan I	Aroclor-1248
Endosulfan II	Aroclor-1254
Endosulfan sulfate	Aroclor-1260
Endrin	Toxaphene

The following analytes from the Appendix IX Organics suite, GC/MS Volatile narrative, were not detected in any samples:

2,4-Dichlorophenoxyacetic acid
2,4,5-TP (Silvex)
2,4,5-Trichlorophenoxyacetic acid

The following analytes from the Appendix IX Organics suite, GC/MS Volatile narrative, were not detected in any samples:

Acetonitrile	1,1-Dichloroethylene
Acrolein	Dichlorodifluoromethane
Acrylonitrile	Dichloromethane (Methylene chloride)
Benzene	1,2-Dichloropropane
Bromodichloromethane	cis-1,3-Dichloropropene
Bromoform	trans-1,3-Dichloropropene
Bromomethane (Methyl bromide)	Ethylbenzene
2-Butanone	2-Hexanone
Carbon disulfide	Iodomethane (Methyl iodide)
Carbon tetrachloride	Isobutyl alcohol
Chlorobenzene	Methacrylonitrile
2-Chloro-1,3-butadiene	4-Methyl-2-pentanone
Chloroethane	Propionitrile
Chloroethene (Vinyl chloride)	Styrene
Chloroform	1,1,1,2-Tetrachloroethane
Chloromethane (Methyl chloride)	1,1,2,2-Tetrachloroethane
3-Chloropropene	Tetrachloroethylene
Dibromochloromethane	1,1,1-Trichloroethane
1,2-Dibromo-3-chloropropane	1,1,2-Trichloroethane
1,2-Dibromoethane	Trichloroethylene
Dibromomethane	Trichlorofluoromethane
trans-1,4-Dichloro-2-butene	1,2,3-Trichloropropane
1,1-Dichloroethane	Vinyl acetate
1,2-Dichloroethane	Xylenes

The following analytes from the Appendix IX Organics suite, Semivolatiles narrative, were not detected in any samples:

Acenaphthene	Benzyl alcohol
Acetophenone	Bis(2-chloroethyl) ether
Acenaphthylene	Bis(2-chloroethoxy)methane
2-Acetylaminofluorene	Bis(2-chloroisopropyl) ether
4-Aminobiphenyl	Bis(2-ethylhexyl) phthalate
Aniline	4-Bromophenyl phenyl ether
Anthracene	Butylbenzyl phthalate
Aramite	2-sec-Butyl-4,6-dinitrophenol
Benzo[a]anthracene	4-Chloroaniline
Benzo[a]pyrene	Chlorobenzilate
Benzoic acid	2-Chloronaphthalene
Benzo[b]fluoranthene	2-Chlorophenol
Benzo[g,h,i]perylene	4-Chlorophenyl phenyl ether
Benzo[k]fluoranthene	Chrysene

m-Cresol (3-Methylphenol)
 o-Cresol (2-Methylphenol)
 p-Cresol (4-Methylphenol)
 Diallate
 Dibenz[a,h]anthracene
 Dibenzofuran
 Di-n-butyl phthalate
 1,2-Dichlorobenzene
 1,3-Dichlorobenzene
 1,4-Dichlorobenzene
 3,3'-Dichlorobenzidine
 2,4-Dichlorophenol
 2,6-Dichlorophenol
 Diethyl phthalate
 p-Dimethylaminoazobenzene
 7,12-Dimethylbenz[a]anthracene
 3,3'-Dimethylbenzidine
 a,a-Dimethylphenethylamine
 2,4-Dimethyl phenol
 Dimethyl phthalate
 1,3-Dinitrobenzene
 2,4-Dinitrophenol
 2,4-Dinitrotoluene
 2,6-Dinitrotoluene
 Di-n-octyl phthalate
 1,4-Dioxane
 Diphenylamine
 Ethyl methacrylate
 Ethyl methanesulfonate
 Fluoranthene
 Fluorene
 Hexachlorobenzene
 Hexachlorobutadiene
 Hexachlorocyclopentadiene
 Hexachloroethane
 Hexachlorophene
 Hexachloropropene
 Indeno[1,2,3-c,d]pyrene
 Isophorone
 Isosafrole
 Methapyrilene
 3-Methylcholanthrene
 3-Methyl-4-chlorophenol
 2-Methyl-4,6-Dinitrophenol
 Methyl methacrylate
 Methyl methanesulfonate

2-Methylnaphthalene
 Naphthalene
 1,4-Naphthoquinone
 1-Naphthylamine
 2-Naphthylamine
 2-Nitroaniline
 3-Nitroaniline
 4-Nitroaniline
 Nitrobenzene
 2-Nitrophenol
 4-Nitrophenol
 4-Nitroquinoline-1-oxide
 N-Nitrosodi-n-butylamine
 N-Nitrosodiethylamine
 N-Nitrosodimethylamine
 N-Nitrosodiphenylamine
 N-Nitrosodi-n-propylamine
 N-Nitrosomethylethylamine
 N-Nitrosomorpholine
 N-Nitrosopiperidine
 N-Nitrosopyrrolidine
 5-Nitro-o-toluidine
 Pentachlorobenzene
 Pentachloroethane
 Pentachloronitrobenzene
 Pentachlorophenol
 Phenacetin
 Phenanthrene
 Phenols
 p-Phenylenediamine
 2-Picoline
 Pronamide
 Pyrene
 Safrole
 1,2,4,5-Tetrachlorobenzene
 2,3,4,6-Tetrachlorophenol
 o-Toluidine
 1,2,4-Trichlorobenzene
 2,4,5-Trichlorophenol
 2,4,6-Trichlorophenol
 1,3,5-Trinitrobenzene

Analytes detected only with modifier (i.e., otherwise not detected at all):

beta-Benzene hexachloride (modifier B) (Pesticide/PCB narrative of Pest/Herb subsuite of App. IX Organics suite)

Dichloromethane (Methylene chloride) (modifier B) (GC/MS Volatiles narrative of App. IX Organic suite)

Cesium-137 (result: 0.2 ± 0.2) (Rads)

The following are the analytes that had results above detection limits.

Analytes detected:

Suite:

pH, spec. cond., TOC

pH, spec. cond., TOC; Inorganics narrative

Acetone

App. IX VOA; GC/MS Vol. narrative

Chromium

App. IX Inorganics; Metals narrative

Copper

App. IX Inorganics; Metals narrative

Cyanide

App. IX Inorganics; Inorganics narrative

Lead

App. IX Inorganics; Metals narrative

Mercury

App. IX Inorganics; Metals narrative

Pyridine

App. IX BNA; Semivolatile narrative

Sulfide

App. IX Inorganics; Inorganics narrative

TOC

App. IX Inorganics; Inorganics narrative

Toluene

App. IX VOA; GC/MS Volatiles narrative

Vanadium

App. IX Inorganics; Metals narrative

Zinc

App. IX Inorganics; Metals narrative

Rads

Rads from subcontracting laboratory (Eberline)

I wasn't able to find results for analyses of 1,2-Dichloroethene.

APPENDIX B
GROUNDWATER MONITORING DATA
FBP WELLS
Third Quarter 1984 to First Quarter 1991

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 1A	85Q4	-0.1	MGL	ACROLN	-0.1	1
FBP 2A	85Q4	-0.1	MGL	ACROLN	-0.1	1
FBP 3A	85Q4	-0.1	MGL	ACROLN	-0.1	1
FBP 4	85Q4	-0.1	MGL	ACROLN	-0.1	1
FBP 1A	85Q4	-0.1	MGL	ACRYLO	-0.1	1
FBP 2A	85Q4	-0.1	MGL	ACRYLO	-0.1	1
FBP 3A	85Q4	-0.1	MGL	ACRYLO	-0.1	1
FBP 4	85Q4	-0.1	MGL	ACRYLO	-0.1	1
FBP 1A	84Q3	-0.002	MGL	AG	-0.002	2
FBP 1A	84Q4	-0.002	MGL	AG	-0.002	1
FBP 1A	85Q1	-0.002	MGL	AG	-0.002	1
FBP 1A	87Q1	-0.002	MGL	AG	-0.002	1
FBP 1A	89Q2	-0.002	MGL	AG	-0.002	1
FBP 1A	91Q1	-0.002	MGL	AG	-0.002	2
FBP 2A	84Q3	-0.002	MGL	AG	-0.002	1
FBP 2A	84Q4	-0.002	MGL	AG	-0.002	1
FBP 2A	85Q1	-0.002	MGL	AG	-0.002	1
FBP 2A	87Q1	-0.002	MGL	AG	-0.002	1
FBP 2A	89Q2	-0.002	MGL	AG	-0.002	1
FBP 2A	91Q1	-0.002	MGL	AG	-0.002	1
FBP 3A	84Q3	-0.002	MGL	AG	-0.002	1
FBP 3A	84Q4	-0.002	MGL	AG	-0.002	1
FBP 3A	85Q1	-0.002	MGL	AG	-0.002	1
FBP 3A	87Q1	-0.002	MGL	AG	-0.002	1
FBP 3A	89Q2	-0.002	MGL	AG	-0.002	1
FBP 3A	91Q1	-0.002	MGL	AG	-0.002	1
FBP 4	85Q1	-0.002	MGL	AG	-0.002	1
FBP 4	85Q3	-0.002	MGL	AG	-0.002	1
FBP 4	85Q4	-0.00045	MGL	AG	-0.00045	2
FBP 4	86Q1	-0.002	MGL	AG	-0.002	1
FBP 4	87Q1	-0.002	MGL	AG	-0.002	1
FBP 4	89Q2	-0.002	MGL	AG	-0.002	1
FBP 4	91Q1	-0.002	MGL	AG	-0.002	1
FBP 1A	84Q3	-2	PCL	ALPHAG	-2	1
FBP 1A	84Q4	6	PCL	ALPHAG	6	1
FBP 1A	85Q1	4	PCL	ALPHAG	4	1
FBP 1A	86Q1	16	PCL	ALPHAG	16	1
FBP 1A	86Q2	4.57	PCL	ALPHAG	4.57	1
FBP 1A	86Q3	130	PCL	ALPHAG	68.13	2
FBP 1A	86Q4	34.9	PCL	ALPHAG	34.9	1
FBP 1A	87Q1	8.1	PCL	ALPHAG	8.1	1
FBP 1A	87Q2	-3	PCL	ALPHAG	-3	1
FBP 1A	87Q3	1.8	PCL	ALPHAG	1.46667	3
FBP 1A	87Q4	3.5	PCL	ALPHAG	3.5	1
FBP 1A	88Q1	2.6	PCL	ALPHAG	2.6	1
FBP 1A	88Q3	4.5	PCL	ALPHAG	4.5	1
FBP 1A	89Q1	2.76	PCL	ALPHAG	2.76	1
FBP 1A	89Q2	-3	PCL	ALPHAG	-3	1
FBP 1A	90Q1	12.5	PCL	ALPHAG	9.2	2
FBP 1A	91Q1	3.7	PCL	ALPHAG	3.5	2
FBP 2A	84Q3	-2	PCL	ALPHAG	-2	1
FBP 2A	84Q4	7	PCL	ALPHAG	7	1
FBP 2A	85Q1	5	PCL	ALPHAG	5	1
FBP 2A	86Q1	-2	PCL	ALPHAG	-2	1
FBP 2A	86Q2	2.28	PCL	ALPHAG	2.28	1
FBP 2A	86Q3	0.87	PCL	ALPHAG	1.185	2
FBP 2A	86Q4	1.9	PCL	ALPHAG	1.9	1
FBP 2A	87Q1	-3	PCL	ALPHAG	-3	1
FBP 2A	87Q2	1.8	PCL	ALPHAG	1.8	1
FBP 2A	87Q3	1.9	PCL	ALPHAG	1.9	1
FBP 2A	87Q4	2.9	PCL	ALPHAG	2.9	1
FBP 2A	88Q1	4.2	PCL	ALPHAG	4.2	1
FBP 2A	88Q3	2.48	PCL	ALPHAG	2.48	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	89Q1	0.7	PCL	ALPHAG	0.7	1
FBP 2A	89Q2	-3	PCL	ALPHAG	-3	1
FBP 2A	90Q1	-3	PCL	ALPHAG	-3	1
FBP 2A	91Q1	-2	PCL	ALPHAG	-2	1
FBP 3A	84Q3	-2	PCL	ALPHAG	-2	1
FBP 3A	84Q4	-2	PCL	ALPHAG	-2	1
FBP 3A	85Q1	-2	PCL	ALPHAG	-2	1
FBP 3A	86Q1	-2	PCL	ALPHAG	-2	1
FBP 3A	86Q2	2.83	PCL	ALPHAG	2.83	1
FBP 3A	86Q3	0.7	PCL	ALPHAG	1.1	2
FBP 3A	86Q4	-3	PCL	ALPHAG	-3	1
FBP 3A	87Q1	-3	PCL	ALPHAG	-3	1
FBP 3A	87Q2	1.7	PCL	ALPHAG	1.7	1
FBP 3A	87Q3	-3	PCL	ALPHAG	-3	1
FBP 3A	87Q4	-3	PCL	ALPHAG	-3	1
FBP 3A	88Q1	-3	PCL	ALPHAG	-3	1
FBP 3A	88Q3	-3	PCL	ALPHAG	-3	1
FBP 3A	89Q1	1.15	PCL	ALPHAG	0.975	2
FBP 3A	89Q2	-3	PCL	ALPHAG	-3	1
FBP 3A	90Q1	-3	PCL	ALPHAG	-3	1
FBP 3A	91Q1	-2	PCL	ALPHAG	-2	1
FBP 4	85Q1	41	PCL	ALPHAG	41	1
FBP 4	85Q3	-2	PCL	ALPHAG	-2	1
FBP 4	85Q4	17	PCL	ALPHAG	17	1
FBP 4	86Q1	38	PCL	ALPHAG	38	1
FBP 4	86Q2	1.96	PCL	ALPHAG	1.96	1
FBP 4	86Q3	6.8	PCL	ALPHAG	4.965	2
FBP 4	86Q4	3.9	PCL	ALPHAG	3.9	1
FBP 4	87Q1	4.1	PCL	ALPHAG	3.7	2
FBP 4	87Q2	6.3	PCL	ALPHAG	6.3	1
FBP 4	87Q3	3.6	PCL	ALPHAG	3.6	1
FBP 4	87Q4	6.3	PCL	ALPHAG	6.3	1
FBP 4	88Q1	-3	PCL	ALPHAG	-3	1
FBP 4	88Q3	11.2	PCL	ALPHAG	11.15	2
FBP 4	89Q1	4.77	PCL	ALPHAG	4.77	1
FBP 4	89Q2	3.6	PCL	ALPHAG	3.6	1
FBP 4	90Q1	-3	PCL	ALPHAG	-3	1
FBP 4	91Q1	-2	PCL	ALPHAG	-2	1
FBP 1A	84Q4	-0.001	MGL	AS	-0.001	1
FBP 1A	85Q1	-0.001	MGL	AS	-0.001	1
FBP 1A	87Q1	-0.002	MGL	AS	-0.002	1
FBP 1A	89Q2	-0.002	MGL	AS	-0.002	1
FBP 1A	91Q1	-0.002	MGL	AS	-0.002	2
FBP 2A	84Q4	-0.001	MGL	AS	-0.001	1
FBP 2A	85Q1	-0.001	MGL	AS	-0.001	1
FBP 2A	87Q1	-0.002	MGL	AS	-0.002	1
FBP 2A	89Q2	-0.002	MGL	AS	-0.002	1
FBP 2A	91Q1	-0.002	MGL	AS	-0.002	1
FBP 3A	84Q4	-0.001	MGL	AS	-0.001	1
FBP 3A	85Q1	-0.001	MGL	AS	-0.001	1
FBP 3A	87Q1	-0.002	MGL	AS	-0.002	2
FBP 3A	89Q2	-0.002	MGL	AS	-0.002	1
FBP 3A	91Q1	-0.002	MGL	AS	-0.002	1
FBP 4	85Q1	-0.001	MGL	AS	-0.001	1
FBP 4	85Q3	-0.002	MGL	AS	-0.002	1
FBP 4	85Q4	-0.002	MGL	AS	-0.002	2
FBP 4	86Q1	-0.002	MGL	AS	-0.002	1
FBP 4	87Q1	-0.002	MGL	AS	-0.002	1
FBP 4	89Q2	-0.002	MGL	AS	-0.002	1
FBP 4	91Q1	-0.002	MGL	AS	-0.002	1
FBP 1A	84Q3	0.008	MGL	BA	0.0075	2
FBP 1A	84Q4	0.008	MGL	BA	0.008	1
FBP 1A	85Q1	0.052	MGL	BA	0.052	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 1A	86Q2	0.069	MGL	BA	0.069	1
FBP 1A	87Q1	0.048	MGL	BA	0.048	1
FBP 1A	88Q1	0.017	MGL	BA	0.017	2
FBP 1A	89Q1	0.033	MGL	BA	0.033	2
FBP 1A	89Q2	0.0281	MGL	BA	0.0281	1
FBP 1A	90Q1	0.0216	MGL	BA	0.02145	2
FBP 1A	91Q1	0.024	MGL	BA	0.024	2
FBP 2A	84Q3	0.005	MGL	BA	0.005	1
FBP 2A	84Q4	0.007	MGL	BA	0.007	1
FBP 2A	85Q1	0.005	MGL	BA	0.005	1
FBP 2A	86Q2	0.004	MGL	BA	0.004	1
FBP 2A	87Q1	-0.004	MGL	BA	-0.004	1
FBP 2A	88Q1	0.009	MGL	BA	0.009	1
FBP 2A	89Q1	0.005	MGL	BA	0.005	1
FBP 2A	89Q2	0.00552	MGL	BA	0.00552	1
FBP 2A	90Q1	0.00585	MGL	BA	0.00585	1
FBP 2A	91Q1	0.0087	MGL	BA	0.0087	1
FBP 3A	84Q3	0.007	MGL	BA	0.007	1
FBP 3A	84Q4	0.008	MGL	BA	0.008	1
FBP 3A	85Q1	0.009	MGL	BA	0.009	1
FBP 3A	86Q2	0.012	MGL	BA	0.012	1
FBP 3A	87Q1	0.011	MGL	BA	0.011	1
FBP 3A	88Q1	0.01	MGL	BA	0.01	2
FBP 3A	89Q1	0.009	MGL	BA	0.009	1
FBP 3A	89Q2	0.0107	MGL	BA	0.0107	1
FBP 3A	90Q1	0.00822	MGL	BA	0.00822	1
FBP 3A	91Q1	0.011	MGL	BA	0.011	1
FBP 4	85Q1	-0.004	MGL	BA	-0.004	1
FBP 4	85Q3	-0.004	MGL	BA	-0.004	1
FBP 4	85Q4	-0.004	MGL	BA	-0.004	2
FBP 4	86Q1	-0.004	MGL	BA	-0.004	1
FBP 4	86Q2	-0.004	MGL	BA	-0.004	1
FBP 4	87Q1	-0.004	MGL	BA	-0.004	1
FBP 4	88Q1	-0.004	MGL	BA	-0.004	1
FBP 4	89Q1	-0.004	MGL	BA	-0.004	2
FBP 4	89Q2	-0.004	MGL	BA	-0.004	1
FBP 4	90Q1	-0.004	MGL	BA	-0.004	1
FBP 4	91Q1	0.0033	MGL	BA	0.0033	1
FBP 1A	84Q3	-0.002	MGL	BE	-0.002	2
FBP 1A	84Q4	-0.002	MGL	BE	-0.002	1
FBP 2A	84Q3	-0.002	MGL	BE	-0.002	1
FBP 2A	84Q4	-0.002	MGL	BE	-0.002	1
FBP 3A	84Q3	-0.002	MGL	BE	-0.002	1
FBP 3A	84Q4	-0.002	MGL	BE	-0.002	1
FBP 1A	84Q3	9	PCL	BETAG	9	1
FBP 1A	84Q4	8	PCL	BETAG	8	1
FBP 1A	85Q1	188	PCL	BETAG	188	1
FBP 1A	86Q1	167	PCL	BETAG	167	1
FBP 1A	86Q2	145.18	PCL	BETAG	145.18	1
FBP 1A	86Q3	213.5	PCL	BETAG	193.25	2
FBP 1A	86Q4	206	PCL	BETAG	206	1
FBP 1A	87Q1	98.2	PCL	BETAG	98.2	1
FBP 1A	87Q2	82.4	PCL	BETAG	82.4	1
FBP 1A	87Q3	61.8	PCL	BETAG	57.9	3
FBP 1A	87Q4	37.3	PCL	BETAG	37.3	1
FBP 1A	88Q1	50.6	PCL	BETAG	50.6	1
FBP 1A	88Q3	88.1	PCL	BETAG	88.1	1
FBP 1A	89Q1	72.56	PCL	BETAG	72.56	1
FBP 1A	89Q2	46.3	PCL	BETAG	46.3	1
FBP 1A	89Q3	60	PCL	BETAG	60	1
FBP 1A	90Q1	60.9	PCL	BETAG	58.5	2
FBP 1A	90Q3	49.8	PCL	BETAG	49.8	1
FBP 1A	91Q1	55.4	PCL	BETAG	53.55	2

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	84Q3	10	PCL	BETAG	10	1
FBP 2A	84Q4	16	PCL	BETAG	16	1
FBP 2A	85Q1	12	PCL	BETAG	12	1
FBP 2A	86Q1	4	PCL	BETAG	4	1
FBP 2A	86Q2	21.88	PCL	BETAG	21.88	1
FBP 2A	86Q3	7.44	PCL	BETAG	6.37	2
FBP 2A	86Q4	7.5	PCL	BETAG	7.5	1
FBP 2A	87Q1	7.6	PCL	BETAG	7.6	1
FBP 2A	87Q2	9.7	PCL	BETAG	9.7	1
FBP 2A	87Q3	9.9	PCL	BETAG	9.9	1
FBP 2A	87Q4	4.8	PCL	BETAG	4.8	1
FBP 2A	88Q1	3	PCL	BETAG	3	1
FBP 2A	88Q3	8.54	PCL	BETAG	8.54	1
FBP 2A	89Q1	5.94	PCL	BETAG	5.94	1
FBP 2A	89Q2	12.6	PCL	BETAG	12.6	1
FBP 2A	89Q3	6.1	PCL	BETAG	6.1	1
FBP 2A	90Q1	17.1	PCL	BETAG	17.1	1
FBP 2A	90Q3	7.2	PCL	BETAG	7.2	1
FBP 2A	91Q1	14.9	PCL	BETAG	14.9	1
FBP 3A	84Q3	-3	PCL	BETAG	-3	1
FBP 3A	84Q4	6	PCL	BETAG	6	1
FBP 3A	85Q1	9	PCL	BETAG	9	1
FBP 3A	86Q1	-3	PCL	BETAG	-3	1
FBP 3A	86Q2	13.42	PCL	BETAG	13.42	1
FBP 3A	86Q3	20.25	PCL	BETAG	11.025	2
FBP 3A	86Q4	-2	PCL	BETAG	-2	1
FBP 3A	87Q1	3.3	PCL	BETAG	3.3	1
FBP 3A	87Q2	3.1	PCL	BETAG	3.1	1
FBP 3A	87Q3	-2	PCL	BETAG	-2	1
FBP 3A	87Q4	-2	PCL	BETAG	-2	1
FBP 3A	88Q1	-2	PCL	BETAG	-2	1
FBP 3A	88Q3	1.16	PCL	BETAG	1.16	1
FBP 3A	89Q1	1.07	PCL	BETAG	1.02	2
FBP 3A	89Q2	3.22	PCL	BETAG	3.22	1
FBP 3A	89Q3	-2	PCL	BETAG	-2	2
FBP 3A	90Q1	3.8	PCL	BETAG	3.8	1
FBP 3A	90Q3	-2	PCL	BETAG	-2	1
FBP 3A	91Q1	-2	PCL	BETAG	-2	1
FBP 4	85Q1	34	PCL	BETAG	34	1
FBP 4	85Q3	-3	PCL	BETAG	-3	1
FBP 4	85Q4	7	PCL	BETAG	7	1
FBP 4	86Q1	49	PCL	BETAG	49	1
FBP 4	86Q2	5.11	PCL	BETAG	5.11	1
FBP 4	86Q3	20.01	PCL	BETAG	12.155	2
FBP 4	86Q4	2.5	PCL	BETAG	2.5	1
FBP 4	87Q1	5.7	PCL	BETAG	5.15	2
FBP 4	87Q2	4.3	PCL	BETAG	4.3	1
FBP 4	87Q3	5.3	PCL	BETAG	5.3	1
FBP 4	87Q4	4.6	PCL	BETAG	4.6	1
FBP 4	88Q1	-2	PCL	BETAG	-2	1
FBP 4	88Q3	7.28	PCL	BETAG	7.175	2
FBP 4	89Q1	3.44	PCL	BETAG	3.44	1
FBP 4	89Q2	3.89	PCL	BETAG	3.89	1
FBP 4	89Q3	-2	PCL	BETAG	-2	1
FBP 4	90Q1	4	PCL	BETAG	4	1
FBP 4	90Q3	-2	PCL	BETAG	-2	1
FBP 4	91Q1	-2	PCL	BETAG	-2	1
FBP 1A	85Q4	-0.005	MGL	BRDCLM	-0.005	1
FBP 1A	87Q3	-0.001	MGL	BRDCLM	-0.001	1
FBP 1A	89Q3	-0.001	MGL	BRDCLM	-0.001	1
FBP 1A	90Q1	-0.001	MGL	BRDCLM	-0.001	2
FBP 2A	85Q4	-0.005	MGL	BRDCLM	-0.005	1
FBP 2A	89Q3	-0.001	MGL	BRDCLM	-0.001	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	90Q1	-0.001	MGL	BRDCLM	-0.001	1
FBP 3A	85Q4	-0.005	MGL	BRDCLM	-0.005	1
FBP 3A	89Q3	-0.001	MGL	BRDCLM	-0.001	2
FBP 3A	90Q1	-0.001	MGL	BRDCLM	-0.001	1
FBP 4	85Q4	-0.005	MGL	BRDCLM	-0.005	1
FBP 4	89Q3	-0.001	MGL	BRDCLM	-0.001	1
FBP 4	90Q1	-0.001	MGL	BRDCLM	-0.001	1
FBP 1A	87Q1	13.9	MGL	CA	13.9	1
FBP 1A	88Q1	6.12	MGL	CA	6.09	2
FBP 1A	89Q1	10.8	MGL	CA	9.7	2
FBP 1A	89Q2	8.02	MGL	CA	8.02	1
FBP 1A	90Q1	6.75	MGL	CA	6.605	2
FBP 1A	91Q1	7	MGL	CA	6.95	2
FBP 2A	87Q1	1.23	MGL	CA	1.23	1
FBP 2A	88Q1	2.5	MGL	CA	2.5	1
FBP 2A	89Q1	2.79	MGL	CA	2.79	1
FBP 2A	89Q2	1.85	MGL	CA	1.85	1
FBP 2A	90Q1	2.2	MGL	CA	2.2	1
FBP 2A	91Q1	2.3	MGL	CA	2.3	1
FBP 3A	87Q1	4.1	MGL	CA	4.1	1
FBP 3A	88Q1	3.7	MGL	CA	3.585	2
FBP 3A	89Q1	3.9	MGL	CA	3.9	1
FBP 3A	89Q2	4.05	MGL	CA	4.05	1
FBP 3A	90Q1	3.53	MGL	CA	3.53	1
FBP 3A	91Q1	3.3	MGL	CA	3.3	1
FBP 4	87Q1	0.434	MGL	CA	0.434	1
FBP 4	88Q1	0.584	MGL	CA	0.584	1
FBP 4	89Q1	0.572	MGL	CA	0.53	2
FBP 4	89Q2	0.58	MGL	CA	0.58	1
FBP 4	90Q1	0.339	MGL	CA	0.339	1
FBP 4	91Q1	0.34	MGL	CA	0.34	1
FBP 1A	87Q3	-0.003	MGL	CCL2F2	-0.003	1
FBP 1A	85Q4	-0.005	MGL	CCL3F	-0.005	1
FBP 1A	87Q3	0.00833	MGL	CCL3F	0.00833	1
FBP 1A	89Q3	0.008	MGL	CCL3F	0.008	1
FBP 1A	90Q1	-0.001	MGL	CCL3F	-0.001	2
FBP 2A	85Q4	-0.005	MGL	CCL3F	-0.005	1
FBP 2A	89Q3	0.015	MGL	CCL3F	0.015	1
FBP 2A	90Q1	0.007	MGL	CCL3F	0.007	1
FBP 3A	85Q4	-0.005	MGL	CCL3F	-0.005	1
FBP 3A	89Q3	0.006	MGL	CCL3F	0.0055	2
FBP 3A	90Q1	0.001	MGL	CCL3F	0.001	1
FBP 4	85Q4	-0.005	MGL	CCL3F	-0.005	1
FBP 4	89Q3	-0.001	MGL	CCL3F	-0.001	1
FBP 4	90Q1	-0.001	MGL	CCL3F	-0.001	1
FBP 1A	85Q4	-0.005	MGL	CCL4	-0.005	1
FBP 1A	86Q3	-0.001	MGL	CCL4	-0.001	2
FBP 1A	87Q1	-0.001	MGL	CCL4	-0.001	1
FBP 1A	87Q2	-0.001	MGL	CCL4	-0.001	1
FBP 1A	87Q3	-0.001	MGL	CCL4	-0.001	3
FBP 1A	87Q4	-0.001	MGL	CCL4	-0.001	1
FBP 1A	88Q1	-0.001	MGL	CCL4	-0.001	1
FBP 1A	88Q3	-0.001	MGL	CCL4	-0.001	2
FBP 1A	89Q1	-0.001	MGL	CCL4	-0.001	1
FBP 1A	89Q3	-0.001	MGL	CCL4	-0.001	1
FBP 1A	90Q1	-0.001	MGL	CCL4	-0.001	2
FBP 1A	90Q3	-0.001	MGL	CCL4	-0.001	1
FBP 1A	91Q1	-0.001	MGL	CCL4	-0.001	2
FBP 2A	85Q4	0.017	MGL	CCL4	0.017	1
FBP 2A	86Q3	0.00734	MGL	CCL4	0.0072	2
FBP 2A	86Q4	0.00462	MGL	CCL4	0.00462	1
FBP 2A	87Q1	0.002	MGL	CCL4	0.002	1
FBP 2A	87Q2	0.00593	MGL	CCL4	0.00593	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	87Q3	-0.001	MGL	CCL4	-0.001	1
FBP 2A	87Q4	0.0148	MGL	CCL4	0.0148	1
FBP 2A	88Q1	0.0124	MGL	CCL4	0.0124	1
FBP 2A	88Q3	0.008	MGL	CCL4	0.008	1
FBP 2A	89Q1	0.00673	MGL	CCL4	0.00673	1
FBP 2A	89Q3	-0.001	MGL	CCL4	-0.001	1
FBP 2A	90Q1	0.007	MGL	CCL4	0.007	1
FBP 2A	90Q3	0.008	MGL	CCL4	0.008	1
FBP 2A	91Q1	0.004	MGL	CCL4	0.004	1
FBP 3A	85Q4	-0.005	MGL	CCL4	-0.005	1
FBP 3A	86Q3	0.00119	MGL	CCL4	0.00119	1
FBP 3A	87Q1	-0.001	MGL	CCL4	-0.001	1
FBP 3A	87Q2	-0.001	MGL	CCL4	-0.001	1
FBP 3A	87Q3	-0.001	MGL	CCL4	-0.001	1
FBP 3A	87Q4	-0.001	MGL	CCL4	-0.001	1
FBP 3A	88Q1	-0.001	MGL	CCL4	-0.001	1
FBP 3A	88Q3	-0.001	MGL	CCL4	-0.001	1
FBP 3A	89Q1	-0.001	MGL	CCL4	-0.001	1
FBP 3A	89Q3	-0.001	MGL	CCL4	-0.001	2
FBP 3A	90Q1	-0.001	MGL	CCL4	-0.001	1
FBP 3A	90Q3	-0.001	MGL	CCL4	-0.001	1
FBP 3A	91Q1	-0.001	MGL	CCL4	-0.001	1
FBP 4	85Q4	-0.005	MGL	CCL4	-0.005	1
FBP 4	86Q3	-0.001	MGL	CCL4	-0.001	1
FBP 4	87Q1	-0.001	MGL	CCL4	-0.001	1
FBP 4	87Q2	-0.001	MGL	CCL4	-0.001	1
FBP 4	87Q3	-0.001	MGL	CCL4	-0.001	1
FBP 4	87Q4	-0.001	MGL	CCL4	-0.001	2
FBP 4	88Q1	-0.001	MGL	CCL4	-0.001	2
FBP 4	88Q3	-0.001	MGL	CCL4	-0.001	1
FBP 4	89Q1	-0.001	MGL	CCL4	-0.001	1
FBP 4	89Q3	-0.001	MGL	CCL4	-0.001	1
FBP 4	90Q1	-0.001	MGL	CCL4	-0.001	1
FBP 4	90Q3	-0.001	MGL	CCL4	-0.001	1
FBP 4	91Q1	-0.001	MGL	CCL4	-0.001	1
FBP 1A	84Q3	-0.002	MGL	CD	-0.002	2
FBP 1A	84Q4	-0.002	MGL	CD	-0.002	1
FBP 1A	85Q1	-0.002	MGL	CD	-0.002	1
FBP 1A	86Q1	-0.001	MGL	CD	-0.001	1
FBP 1A	86Q3	-0.002	MGL	CD	-0.002	1
FBP 1A	87Q1	-0.002	MGL	CD	-0.002	1
FBP 1A	87Q2	-0.002	MGL	CD	-0.002	1
FBP 1A	87Q3	-0.002	MGL	CD	-0.003	4
FBP 1A	87Q4	-0.002	MGL	CD	-0.002	1
FBP 1A	88Q1	-0.002	MGL	CD	-0.002	2
FBP 1A	89Q2	-0.002	MGL	CD	-0.002	1
FBP 1A	91Q1	-0.002	MGL	CD	-0.002	2
FBP 2A	84Q3	-0.002	MGL	CD	-0.002	1
FBP 2A	84Q4	-0.002	MGL	CD	-0.002	1
FBP 2A	85Q1	-0.002	MGL	CD	-0.002	1
FBP 2A	86Q1	-0.001	MGL	CD	-0.001	1
FBP 2A	86Q3	-0.002	MGL	CD	-0.002	1
FBP 2A	87Q1	-0.002	MGL	CD	-0.002	1
FBP 2A	87Q2	-0.002	MGL	CD	-0.002	1
FBP 2A	87Q3	-0.002	MGL	CD	-0.002	1
FBP 2A	87Q4	-0.002	MGL	CD	-0.002	1
FBP 2A	88Q1	-0.002	MGL	CD	-0.002	1
FBP 2A	89Q2	-0.002	MGL	CD	-0.002	1
FBP 2A	91Q1	-0.002	MGL	CD	-0.002	1
FBP 3A	84Q3	0.046	MGL	CD	0.046	1
FBP 3A	84Q4	0.011	MGL	CD	0.011	1
FBP 3A	85Q1	-0.002	MGL	CD	-0.002	1
FBP 3A	86Q1	-0.001	MGL	CD	-0.001	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 3A	86Q3	-0.002	MGL	CD	-0.002	1
FBP 3A	87Q1	-0.002	MGL	CD	-0.002	1
FBP 3A	87Q2	0.002	MGL	CD	0.002	1
FBP 3A	87Q3	-0.002	MGL	CD	-0.002	1
FBP 3A	87Q4	-0.002	MGL	CD	-0.002	1
FBP 3A	88Q1	-0.002	MGL	CD	-0.002	2
FBP 3A	89Q2	-0.002	MGL	CD	-0.002	1
FBP 3A	91Q1	-0.002	MGL	CD	-0.002	1
FBP 4	85Q1	-0.002	MGL	CD	-0.002	1
FBP 4	85Q3	-0.002	MGL	CD	-0.002	1
FBP 4	85Q4	-0.002	MGL	CD	-0.002	2
FBP 4	86Q1	-0.001	MGL	CD	-0.001	1
FBP 4	86Q3	-0.002	MGL	CD	-0.002	1
FBP 4	87Q1	-0.002	MGL	CD	-0.002	1
FBP 4	87Q2	-0.002	MGL	CD	-0.002	1
FBP 4	87Q3	-0.002	MGL	CD	-0.002	1
FBP 4	87Q4	-0.002	MGL	CD	-0.002	1
FBP 4	88Q1	-0.002	MGL	CD	-0.002	1
FBP 4	89Q2	-0.002	MGL	CD	-0.002	1
FBP 4	91Q1	-0.002	MGL	CD	-0.002	1
FBP 1A	85Q4	-0.01	MGL	CHBR3	-0.01	1
FBP 1A	87Q3	-0.002	MGL	CHBR3	-0.002	1
FBP 1A	89Q3	-0.001	MGL	CHBR3	-0.001	1
FBP 1A	90Q1	-0.001	MGL	CHBR3	-0.001	2
FBP 2A	85Q4	-0.01	MGL	CHBR3	-0.01	1
FBP 2A	89Q3	-0.001	MGL	CHBR3	-0.001	1
FBP 2A	90Q1	-0.001	MGL	CHBR3	-0.001	1
FBP 3A	85Q4	-0.01	MGL	CHBR3	-0.01	1
FBP 3A	89Q3	-0.001	MGL	CHBR3	-0.001	2
FBP 3A	90Q1	-0.001	MGL	CHBR3	-0.001	1
FBP 4	85Q4	-0.01	MGL	CHBR3	-0.01	1
FBP 4	89Q3	-0.001	MGL	CHBR3	-0.001	1
FBP 4	90Q1	-0.001	MGL	CHBR3	-0.001	1
FBP 1A	85Q4	-0.005	MGL	CHCL3	-0.005	1
FBP 1A	86Q3	0.00243	MGL	CHCL3	0.00243	2
FBP 1A	86Q4	-0.001	MGL	CHCL3	-0.001	1
FBP 1A	87Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 1A	87Q2	-0.001	MGL	CHCL3	-0.001	1
FBP 1A	87Q3	-0.001	MGL	CHCL3	-0.001	3
FBP 1A	87Q4	-0.001	MGL	CHCL3	-0.001	1
FBP 1A	88Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 1A	88Q3	-0.001	MGL	CHCL3	-0.001	2
FBP 1A	89Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 1A	89Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 1A	90Q1	-0.001	MGL	CHCL3	-0.001	2
FBP 1A	90Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 1A	91Q1	0.001	MGL	CHCL3	0.001	2
FBP 2A	85Q4	-0.005	MGL	CHCL3	-0.005	1
FBP 2A	86Q3	-0.001	MGL	CHCL3	-0.001	2
FBP 2A	86Q4	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	87Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	87Q2	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	87Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	87Q4	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	88Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	88Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	89Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	89Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	90Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	90Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 2A	91Q1	0.002	MGL	CHCL3	0.002	1
FBP 3A	85Q4	-0.005	MGL	CHCL3	-0.005	1
FBP 3A	86Q3	-0.001	MGL	CHCL3	-0.001	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 3A	86Q4	-0.001	MGL	CHCL3	-0.001	1
FBP 3A	87Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 3A	87Q2	-0.001	MGL	CHCL3	-0.001	1
FBP 3A	87Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 3A	87Q4	-0.001	MGL	CHCL3	-0.001	1
FBP 3A	88Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 3A	88Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 3A	89Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 3A	89Q3	-0.001	MGL	CHCL3	-0.001	2
FBP 3A	90Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 3A	90Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 3A	91Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 4	85Q4	-0.005	MGL	CHCL3	-0.005	1
FBP 4	86Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 4	86Q4	-0.001	MGL	CHCL3	-0.001	1
FBP 4	87Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 4	87Q2	-0.001	MGL	CHCL3	-0.001	1
FBP 4	87Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 4	87Q4	-0.001	MGL	CHCL3	-0.001	2
FBP 4	88Q1	-0.001	MGL	CHCL3	-0.001	2
FBP 4	88Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 4	89Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 4	89Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 4	90Q1	-0.001	MGL	CHCL3	-0.001	1
FBP 4	90Q3	-0.001	MGL	CHCL3	-0.001	1
FBP 4	91Q1	0.001	MGL	CHCL3	0.001	1
FBP 1A	85Q4	-0.005	MGL	CH2CL2	-0.005	1
FBP 1A	89Q3	-0.001	MGL	CH2CL2	-0.001	1
FBP 1A	90Q1	-0.001	MGL	CH2CL2	-0.001	2
FBP 2A	85Q4	-0.005	MGL	CH2CL2	-0.005	1
FBP 2A	89Q3	-0.001	MGL	CH2CL2	-0.001	1
FBP 2A	90Q1	-0.001	MGL	CH2CL2	-0.001	1
FBP 3A	85Q4	-0.005	MGL	CH2CL2	-0.005	1
FBP 3A	89Q3	-0.001	MGL	CH2CL2	-0.001	2
FBP 3A	90Q1	-0.001	MGL	CH2CL2	-0.001	1
FBP 4	85Q4	-0.005	MGL	CH2CL2	-0.005	1
FBP 4	89Q3	-0.001	MGL	CH2CL2	-0.001	1
FBP 4	90Q1	-0.001	MGL	CH2CL2	-0.001	1
FBP 1A	85Q4	-0.01	MGL	CH3BR	-0.01	1
FBP 1A	87Q3	-0.002	MGL	CH3BR	-0.002	1
FBP 1A	89Q3	-0.001	MGL	CH3BR	-0.001	1
FBP 1A	90Q1	-0.001	MGL	CH3BR	-0.001	2
FBP 2A	85Q4	-0.01	MGL	CH3BR	-0.01	1
FBP 2A	89Q3	-0.001	MGL	CH3BR	-0.001	1
FBP 2A	90Q1	-0.001	MGL	CH3BR	-0.001	1
FBP 3A	85Q4	-0.01	MGL	CH3BR	-0.01	1
FBP 3A	89Q3	-0.001	MGL	CH3BR	-0.001	2
FBP 3A	90Q1	-0.001	MGL	CH3BR	-0.001	1
FBP 4	85Q4	-0.01	MGL	CH3BR	-0.01	1
FBP 4	89Q3	-0.001	MGL	CH3BR	-0.001	1
FBP 4	90Q1	-0.001	MGL	CH3BR	-0.001	1
FBP 1A	85Q4	-0.01	MGL	CH3CL	-0.01	1
FBP 1A	87Q3	-0.001	MGL	CH3CL	-0.001	1
FBP 1A	89Q3	-0.001	MGL	CH3CL	-0.001	1
FBP 1A	90Q1	-0.001	MGL	CH3CL	-0.001	2
FBP 2A	85Q4	-0.01	MGL	CH3CL	-0.01	1
FBP 2A	89Q3	-0.001	MGL	CH3CL	-0.001	1
FBP 2A	90Q1	-0.001	MGL	CH3CL	-0.001	1
FBP 3A	85Q4	-0.01	MGL	CH3CL	-0.01	1
FBP 3A	89Q3	-0.001	MGL	CH3CL	-0.001	2
FBP 3A	90Q1	-0.001	MGL	CH3CL	-0.001	1
FBP 4	85Q4	-0.01	MGL	CH3CL	-0.01	1
FBP 4	89Q3	-0.001	MGL	CH3CL	-0.001	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 4	90Q1	-0.001	MGL	CH3CL	-0.001	1
FBP 1A	84Q3	2.5	MGL	CL	2.5	1
FBP 1A	84Q4	2.5	MGL	CL	2.5	1
FBP 1A	85Q1	2.5	MGL	CL	2.5	1
FBP 1A	86Q1	5.2	MGL	CL	5.2	1
FBP 1A	87Q1	3.1	MGL	CL	3.1	1
FBP 1A	89Q2	3	MGL	CL	3	1
FBP 1A	91Q1	2.87	MGL	CL	2.835	2
FBP 2A	84Q3	4.5	MGL	CL	4.5	1
FBP 2A	84Q4	5	MGL	CL	5	1
FBP 2A	85Q1	5.5	MGL	CL	5	2
FBP 2A	86Q1	8.7	MGL	CL	8.7	1
FBP 2A	87Q1	3.1	MGL	CL	3.1	1
FBP 2A	89Q2	3.1	MGL	CL	3.1	1
FBP 2A	91Q1	5.52	MGL	CL	5.52	1
FBP 3A	84Q3	4	MGL	CL	4	1
FBP 3A	84Q4	4.6	MGL	CL	4.6	1
FBP 3A	85Q1	4	MGL	CL	4	1
FBP 3A	86Q1	6.9	MGL	CL	6.9	1
FBP 3A	87Q1	3.5	MGL	CL	3.5	1
FBP 3A	89Q2	3.5	MGL	CL	3.5	1
FBP 3A	91Q1	3.62	MGL	CL	3.62	1
FBP 4	85Q1	2.5	MGL	CL	2.5	1
FBP 4	85Q3	3.27	MGL	CL	3.11	2
FBP 4	85Q4	2.4	MGL	CL	2.4	1
FBP 4	86Q1	2.9	MGL	CL	2.9	2
FBP 4	87Q1	3.1	MGL	CL	3	2
FBP 4	89Q2	2.9	MGL	CL	2.9	1
FBP 4	91Q1	2.97	MGL	CL	2.97	1
FBP 1A	85Q4	-0.005	MGL	CLC6H5	-0.005	1
FBP 1A	89Q3	-0.001	MGL	CLC6H5	-0.001	1
FBP 1A	90Q1	-0.001	MGL	CLC6H5	-0.001	2
FBP 2A	85Q4	-0.005	MGL	CLC6H5	-0.005	1
FBP 2A	89Q3	-0.001	MGL	CLC6H5	-0.001	1
FBP 2A	90Q1	-0.001	MGL	CLC6H5	-0.001	1
FBP 3A	85Q4	-0.005	MGL	CLC6H5	-0.005	1
FBP 3A	89Q3	-0.001	MGL	CLC6H5	-0.001	2
FBP 3A	90Q1	-0.001	MGL	CLC6H5	-0.001	1
FBP 4	85Q4	-0.005	MGL	CLC6H5	-0.005	1
FBP 4	89Q3	-0.001	MGL	CLC6H5	-0.001	1
FBP 4	90Q1	-0.001	MGL	CLC6H5	-0.001	1
FBP 1A	84Q3	0	APC	COLOR	0	1
FBP 1A	84Q4	0	APC	COLOR	0	1
FBP 2A	84Q3	0	APC	COLOR	0	1
FBP 2A	84Q4	0	APC	COLOR	0	1
FBP 3A	84Q3	0	APC	COLOR	0	1
FBP 3A	84Q4	0	APC	COLOR	0	1
FBP 1A	84Q3	35.2	UMHC	COND	35.2	1
FBP 1A	84Q4	25	UMHC	COND	25	1
FBP 1A	85Q1	192.6	UMHC	COND	192.6	1
FBP 1A	85Q2	160.4	UMHC	COND	160.4	1
FBP 1A	85Q3	204.6	UMHC	COND	204.6	1
FBP 1A	85Q4	393	UMHC	COND	393	2
FBP 1A	86Q1	225	UMHC	COND	225	1
FBP 1A	86Q2	243	UMHC	COND	243	1
FBP 1A	86Q3	246	UMHC	COND	244.4	2
FBP 1A	86Q4	241	UMHC	COND	241	1
FBP 1A	87Q1	169	UMHC	COND	169	1
FBP 1A	87Q2	117	UMHC	COND	117	1
FBP 1A	87Q3	83.6	UMHC	COND	82.825	4
FBP 1A	87Q4	99.1	UMHC	COND	99.1	1
FBP 1A	88Q1	74.3	UMHC	COND	73.5	2
FBP 1A	89Q1	109	UMHC	COND	109	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 1A	89Q2	1200	UMHC	COND	1200	1
FBP 1A	90Q1	90	UMHC	COND	89	2
FBP 1A	91Q1	98	UMHC	COND	98	2
FBP 2A	84Q3	46.4	UMHC	COND	46.4	1
FBP 2A	84Q4	53.6	UMHC	COND	53.6	1
FBP 2A	85Q1	68.3	UMHC	COND	68.3	1
FBP 2A	85Q2	55	UMHC	COND	55	1
FBP 2A	85Q3	68.8	UMHC	COND	68.8	1
FBP 2A	85Q4	250	UMHC	COND	250	1
FBP 2A	86Q1	98.8	UMHC	COND	98.8	1
FBP 2A	86Q2	73.2	UMHC	COND	73.2	1
FBP 2A	86Q3	49	UMHC	COND	49	1
FBP 2A	86Q4	44.6	UMHC	COND	44.6	1
FBP 2A	87Q1	38.4	UMHC	COND	38.4	1
FBP 2A	87Q2	43.9	UMHC	COND	43.9	1
FBP 2A	87Q3	79.8	UMHC	COND	79.8	1
FBP 2A	87Q4	106	UMHC	COND	106	2
FBP 2A	88Q1	65	UMHC	COND	65	1
FBP 2A	89Q1	45.2	UMHC	COND	45.2	1
FBP 2A	89Q2	35	UMHC	COND	35	1
FBP 2A	90Q1	38	UMHC	COND	38	1
FBP 2A	91Q1	50	UMHC	COND	50	1
FBP 3A	84Q4	52.1	UMHC	COND	52.1	1
FBP 3A	85Q1	130.5	UMHC	COND	130.5	1
FBP 3A	85Q2	54.9	UMHC	COND	54.9	1
FBP 3A	85Q3	66.3	UMHC	COND	66.3	1
FBP 3A	85Q4	70	UMHC	COND	70	1
FBP 3A	86Q1	78.5	UMHC	COND	78.5	1
FBP 3A	86Q2	77.4	UMHC	COND	77.4	1
FBP 3A	86Q3	62.4	UMHC	COND	62.4	1
FBP 3A	86Q4	67.6	UMHC	COND	64.45	2
FBP 3A	87Q1	58.8	UMHC	COND	58.8	1
FBP 3A	87Q2	55.4	UMHC	COND	55.4	1
FBP 3A	87Q3	51.5	UMHC	COND	51.5	1
FBP 3A	88Q1	50	UMHC	COND	50	1
FBP 3A	89Q1	61.3	UMHC	COND	61.3	1
FBP 3A	89Q2	60	UMHC	COND	60	1
FBP 3A	90Q1	55	UMHC	COND	55	1
FBP 3A	91Q1	52	UMHC	COND	52	1
FBP 4	85Q1	30.3	UMHC	COND	30.3	1
FBP 4	85Q2	17.6	UMHC	COND	17.6	1
FBP 4	85Q3	18.6	UMHC	COND	18.6	1
FBP 4	85Q4	19	UMHC	COND	18.5	2
FBP 4	86Q1	19.82	UMHC	COND	19.82	1
FBP 4	86Q2	21.29	UMHC	COND	21.29	1
FBP 4	86Q3	18.3	UMHC	COND	18.3	1
FBP 4	86Q4	21.6	UMHC	COND	21.6	1
FBP 4	87Q1	20.7	UMHC	COND	20.7	1
FBP 4	87Q2	22.8	UMHC	COND	22.35	2
FBP 4	87Q3	22.4	UMHC	COND	22.4	1
FBP 4	87Q4	25.6	UMHC	COND	25.6	1
FBP 4	88Q1	20	UMHC	COND	20	1
FBP 4	89Q1	31.8	UMHC	COND	31.8	1
FBP 4	89Q2	20	UMHC	COND	20	1
FBP 4	90Q1	30	UMHC	COND	30	1
FBP 4	91Q1	22	UMHC	COND	22	1
FBP 1A	84Q4	0.0021	MMY	CORR	0.0021	1
FBP 2A	84Q4	0.0038	MMY	CORR	0.0038	1
FBP 3A	84Q4	0.0031	MMY	CORR	0.0031	1
FBP 1A	84Q3	-0.004	MGL	CR	-0.004	2
FBP 1A	84Q4	-0.004	MGL	CR	-0.004	1
FBP 1A	85Q1	-0.004	MGL	CR	-0.004	1
FBP 1A	87Q1	-0.004	MGL	CR	-0.004	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 1A	89Q2	-0.004	MGL	CR	-0.004	1
FBP 1A	90Q1	-0.004	MGL	CR	-0.004	2
FBP 1A	91Q1	0.0048	MGL	CR	0.0045	2
FBP 2A	84Q3	-0.004	MGL	CR	-0.004	1
FBP 2A	84Q4	-0.004	MGL	CR	-0.004	1
FBP 2A	85Q1	-0.004	MGL	CR	-0.004	1
FBP 2A	87Q1	-0.004	MGL	CR	-0.004	1
FBP 2A	89Q2	-0.004	MGL	CR	-0.004	1
FBP 2A	90Q1	-0.004	MGL	CR	-0.004	1
FBP 2A	91Q1	-0.004	MGL	CR	-0.004	1
FBP 3A	84Q3	-0.004	MGL	CR	-0.004	1
FBP 3A	84Q4	-0.004	MGL	CR	-0.004	1
FBP 3A	85Q1	-0.004	MGL	CR	-0.004	1
FBP 3A	87Q1	-0.004	MGL	CR	-0.004	1
FBP 3A	89Q2	-0.004	MGL	CR	-0.004	1
FBP 3A	90Q1	-0.004	MGL	CR	-0.004	1
FBP 3A	91Q1	0.0049	MGL	CR	0.0049	1
FBP 4	85Q1	-0.004	MGL	CR	-0.004	1
FBP 4	85Q3	-0.004	MGL	CR	-0.004	1
FBP 4	85Q4	-0.004	MGL	CR	-0.004	2
FBP 4	86Q1	-0.004	MGL	CR	-0.004	1
FBP 4	87Q1	-0.004	MGL	CR	-0.004	1
FBP 4	89Q2	0.0119	MGL	CR	0.0119	1
FBP 4	90Q1	-0.004	MGL	CR	-0.004	1
FBP 4	91Q1	-0.004	MGL	CR	-0.004	1
FBP 1A	84Q3	-0.004	MGL	CU	-0.004	2
FBP 1A	84Q4	-0.004	MGL	CU	-0.004	1
FBP 2A	84Q3	-0.004	MGL	CU	-0.004	1
FBP 2A	84Q4	0.007	MGL	CU	0.007	1
FBP 3A	84Q3	-0.004	MGL	CU	-0.004	1
FBP 3A	84Q4	0.009	MGL	CU	0.009	1
FBP 1A	84Q3	-0.005	MGL	CYN	-0.005	1
FBP 1A	84Q4	-0.005	MGL	CYN	-0.005	1
FBP 2A	84Q3	-0.005	MGL	CYN	-0.005	1
FBP 2A	84Q4	-0.005	MGL	CYN	-0.005	1
FBP 3A	84Q3	-0.005	MGL	CYN	-0.005	1
FBP 3A	84Q4	-0.005	MGL	CYN	-0.005	1
FBP 1A	87Q3	-0.001	MGL	C13DCP	-0.001	1
FBP 1A	85Q4	-0.01	MGL	C2H3CL	-0.01	1
FBP 1A	89Q3	-0.001	MGL	C2H3CL	-0.001	1
FBP 1A	90Q1	-0.001	MGL	C2H3CL	-0.001	2
FBP 2A	85Q4	-0.01	MGL	C2H3CL	-0.01	1
FBP 2A	89Q3	-0.001	MGL	C2H3CL	-0.001	1
FBP 2A	90Q1	-0.001	MGL	C2H3CL	-0.001	1
FBP 3A	85Q4	-0.01	MGL	C2H3CL	-0.01	1
FBP 3A	89Q3	-0.001	MGL	C2H3CL	-0.001	2
FBP 3A	90Q1	-0.001	MGL	C2H3CL	-0.001	1
FBP 4	85Q4	-0.01	MGL	C2H3CL	-0.01	1
FBP 4	89Q3	-0.001	MGL	C2H3CL	-0.001	1
FBP 4	90Q1	-0.001	MGL	C2H3CL	-0.001	1
FBP 1A	85Q4	-0.01	MGL	C2H5CL	-0.01	1
FBP 1A	87Q3	-0.001	MGL	C2H5CL	-0.001	1
FBP 1A	89Q3	-0.001	MGL	C2H5CL	-0.001	1
FBP 1A	90Q1	-0.001	MGL	C2H5CL	-0.001	2
FBP 2A	85Q4	-0.01	MGL	C2H5CL	-0.01	1
FBP 2A	89Q3	-0.001	MGL	C2H5CL	-0.001	1
FBP 2A	90Q1	-0.001	MGL	C2H5CL	-0.001	1
FBP 3A	85Q4	-0.01	MGL	C2H5CL	-0.01	1
FBP 3A	89Q3	-0.001	MGL	C2H5CL	-0.001	2
FBP 3A	90Q1	-0.001	MGL	C2H5CL	-0.001	1
FBP 4	85Q4	-0.01	MGL	C2H5CL	-0.01	1
FBP 4	89Q3	-0.001	MGL	C2H5CL	-0.001	1
FBP 4	90Q1	-0.001	MGL	C2H5CL	-0.001	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 1A	85Q4	-0.005	MGL	C6H6	-0.005	1
FBP 1A	89Q3	-0.001	MGL	C6H6	-0.001	1
FBP 1A	90Q1	-0.001	MGL	C6H6	-0.001	2
FBP 2A	85Q4	-0.005	MGL	C6H6	-0.005	1
FBP 2A	89Q3	-0.001	MGL	C6H6	-0.001	1
FBP 2A	90Q1	-0.001	MGL	C6H6	-0.001	1
FBP 3A	85Q4	-0.005	MGL	C6H6	-0.005	1
FBP 3A	89Q3	-0.001	MGL	C6H6	-0.001	2
FBP 3A	90Q1	-0.001	MGL	C6H6	-0.001	1
FBP 4	85Q4	-0.005	MGL	C6H6	-0.005	1
FBP 4	89Q3	-0.001	MGL	C6H6	-0.001	1
FBP 4	90Q1	-0.001	MGL	C6H6	-0.001	1
FBP 1A	85Q4	-0.005	MGL	DBRCLM	-0.005	1
FBP 1A	87Q3	-0.001	MGL	DBRCLM	-0.001	1
FBP 1A	89Q3	-0.001	MGL	DBRCLM	-0.001	1
FBP 1A	90Q1	-0.001	MGL	DBRCLM	-0.001	2
FBP 2A	85Q4	-0.005	MGL	DBRCLM	-0.005	1
FBP 2A	89Q3	-0.001	MGL	DBRCLM	-0.001	1
FBP 2A	90Q1	-0.001	MGL	DBRCLM	-0.001	1
FBP 3A	85Q4	-0.005	MGL	DBRCLM	-0.005	1
FBP 3A	89Q3	-0.001	MGL	DBRCLM	-0.001	2
FBP 3A	90Q1	-0.001	MGL	DBRCLM	-0.001	1
FBP 4	85Q4	-0.005	MGL	DBRCLM	-0.005	1
FBP 4	89Q3	-0.001	MGL	DBRCLM	-0.001	1
FBP 4	90Q1	-0.001	MGL	DBRCLM	-0.001	1
FBP 1A	84Q3	-5	MGL	DOC	-5	1
FBP 1A	84Q4	5.8	MGL	DOC	5.8	1
FBP 2A	84Q3	5	MGL	DOC	3.75	2
FBP 2A	84Q4	-5	MGL	DOC	-5	1
FBP 3A	84Q3	7	MGL	DOC	7	1
FBP 3A	84Q4	-5	MGL	DOC	-5	1
FBP 1A	84Q4	-0.00004	MGL	ENDRN	-0.00004	1
FBP 1A	85Q1	-0.00004	MGL	ENDRN	-0.00004	2
FBP 1A	91Q1	-0.00001	MGL	ENDRN	-0.00001	2
FBP 2A	84Q4	-0.00004	MGL	ENDRN	-0.00004	1
FBP 2A	85Q1	-0.00004	MGL	ENDRN	-0.00004	1
FBP 2A	91Q1	-0.00001	MGL	ENDRN	-0.00001	1
FBP 3A	84Q4	-0.00004	MGL	ENDRN	-0.00004	1
FBP 3A	85Q1	-0.00004	MGL	ENDRN	-0.00004	1
FBP 3A	91Q1	-0.00001	MGL	ENDRN	-0.00001	1
FBP 4	85Q1	-0.00004	MGL	ENDRN	-0.00004	1
FBP 4	85Q3	-0.00004	MGL	ENDRN	-0.00004	1
FBP 4	85Q4	-0.00004	MGL	ENDRN	-0.00004	2
FBP 4	86Q1	-0.00004	MGL	ENDRN	-0.00004	1
FBP 4	91Q1	-0.00001	MGL	ENDRN	-0.00001	1
FBP 1A	85Q4	-0.005	MGL	ETC6H5	-0.005	1
FBP 1A	89Q3	-0.001	MGL	ETC6H5	-0.001	1
FBP 1A	90Q1	-0.001	MGL	ETC6H5	-0.001	2
FBP 2A	85Q4	-0.005	MGL	ETC6H5	-0.005	1
FBP 2A	89Q3	-0.001	MGL	ETC6H5	-0.001	1
FBP 2A	90Q1	-0.001	MGL	ETC6H5	-0.001	1
FBP 3A	85Q4	-0.005	MGL	ETC6H5	-0.005	1
FBP 3A	89Q3	-0.001	MGL	ETC6H5	-0.001	2
FBP 3A	90Q1	-0.001	MGL	ETC6H5	-0.001	1
FBP 4	85Q4	-0.005	MGL	ETC6H5	-0.005	1
FBP 4	89Q3	-0.001	MGL	ETC6H5	-0.001	1
FBP 4	90Q1	-0.001	MGL	ETC6H5	-0.001	1
FBP 1A	84Q3	0.1	MGL	F	0.1	1
FBP 1A	84Q4	-0.1	MGL	F	-0.1	2
FBP 1A	85Q1	0.11	MGL	F	0.11	1
FBP 1A	87Q1	0.14	MGL	F	0.14	1
FBP 1A	89Q2	-0.1	MGL	F	-0.1	1
FBP 1A	91Q1	-0.1	MGL	F	-0.1	2

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	84Q3	0.11	MGL	F	0.11	1
FBP 2A	84Q4	-0.1	MGL	F	-0.1	1
FBP 2A	85Q1	-0.1	MGL	F	-0.1	1
FBP 2A	87Q1	0.15	MGL	F	0.145	2
FBP 2A	89Q2	-0.1	MGL	F	-0.1	1
FBP 2A	91Q1	-0.1	MGL	F	-0.1	1
FBP 3A	84Q3	0.34	MGL	F	0.34	1
FBP 3A	84Q4	0.13	MGL	F	0.13	1
FBP 3A	85Q1	-0.1	MGL	F	-0.1	1
FBP 3A	87Q1	0.14	MGL	F	0.14	1
FBP 3A	89Q2	-0.1	MGL	F	-0.1	1
FBP 3A	91Q1	-0.1	MGL	F	-0.1	1
FBP 4	85Q1	-0.1	MGL	F	-0.1	1
FBP 4	85Q3	0.22	MGL	F	0.22	1
FBP 4	85Q4	-0.1	MGL	F	-0.1	1
FBP 4	86Q1	0.12	MGL	F	0.115	2
FBP 4	87Q1	0.11	MGL	F	0.11	1
FBP 4	89Q2	-0.1	MGL	F	-0.1	1
FBP 4	91Q1	-0.1	MGL	F	-0.1	1
FBP 1A	84Q3	0.112	MGL	FE	0.09	2
FBP 1A	84Q4	0.007	MGL	FE	0.007	1
FBP 1A	85Q1	0.023	MGL	FE	0.023	1
FBP 1A	86Q1	0.036	MGL	FE	0.036	1
FBP 1A	87Q1	0.034	MGL	FE	0.034	1
FBP 1A	87Q2	0.072	MGL	FE	0.072	1
FBP 1A	87Q3	0.07	MGL	FE	0.04175	4
FBP 1A	87Q4	0.059	MGL	FE	0.059	1
FBP 1A	88Q1	0.046	MGL	FE	0.039	2
FBP 1A	89Q1	0.049	MGL	FE	0.042	2
FBP 1A	89Q2	0.142	MGL	FE	0.142	1
FBP 1A	91Q1	0.048	MGL	FE	0.0405	2
FBP 2A	84Q3	0.128	MGL	FE	0.128	1
FBP 2A	84Q4	0.1	MGL	FE	0.1	1
FBP 2A	85Q1	0.025	MGL	FE	0.025	1
FBP 2A	86Q1	0.019	MGL	FE	0.019	1
FBP 2A	87Q1	0.018	MGL	FE	0.018	1
FBP 2A	87Q2	0.062	MGL	FE	0.062	1
FBP 2A	87Q3	0.029	MGL	FE	0.029	1
FBP 2A	87Q4	0.084	MGL	FE	0.084	1
FBP 2A	88Q1	0.029	MGL	FE	0.029	1
FBP 2A	89Q1	-0.02	MGL	FE	-0.02	1
FBP 2A	89Q2	0.0613	MGL	FE	0.0613	1
FBP 2A	91Q1	0.027	MGL	FE	0.027	1
FBP 3A	84Q3	0.038	MGL	FE	0.038	1
FBP 3A	84Q4	0.323	MGL	FE	0.323	1
FBP 3A	85Q1	0.019	MGL	FE	0.019	1
FBP 3A	86Q1	0.042	MGL	FE	0.042	1
FBP 3A	87Q1	0.012	MGL	FE	0.012	1
FBP 3A	87Q2	0.134	MGL	FE	0.134	1
FBP 3A	87Q3	0.145	MGL	FE	0.145	1
FBP 3A	87Q4	0.02	MGL	FE	0.02	1
FBP 3A	88Q1	0.034	MGL	FE	0.0305	2
FBP 3A	89Q1	0.043	MGL	FE	0.043	1
FBP 3A	89Q2	0.0491	MGL	FE	0.0491	1
FBP 3A	91Q1	0.03	MGL	FE	0.03	1
FBP 4	85Q1	0.017	MGL	FE	0.017	1
FBP 4	85Q3	0.047	MGL	FE	0.047	1
FBP 4	85Q4	0.031	MGL	FE	0.0265	2
FBP 4	86Q1	0.014	MGL	FE	0.014	1
FBP 4	87Q1	0.01	MGL	FE	0.01	1
FBP 4	87Q2	0.032	MGL	FE	0.032	1
FBP 4	87Q3	0.151	MGL	FE	0.151	1
FBP 4	87Q4	0.017	MGL	FE	0.017	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 4	88Q1	0.036	MGL	FE	0.036	1
FBP 4	89Q1	0.05	MGL	FE	0.04	2
FBP 4	89Q2	0.0787	MGL	FE	0.0787	1
FBP 4	91Q1	0.031	MGL	FE	0.031	1
FBP 1A	84Q3	-0.04	MGL	GCSCN	-0.04	1
FBP 1A	84Q4	-0.04	MGL	GCSCN	-0.04	1
FBP 2A	84Q3	-0.04	MGL	GCSCN	-0.04	2
FBP 2A	84Q4	-0.04	MGL	GCSCN	-0.04	1
FBP 3A	84Q3	-0.04	MGL	GCSCN	-0.04	1
FBP 3A	84Q4	-0.04	MGL	GCSCN	-0.04	2
FBP 1A	84Q3	-0.0002	MGL	HG	-0.0002	1
FBP 1A	84Q4	-0.0002	MGL	HG	-0.0002	1
FBP 1A	85Q1	0.00023	MGL	HG	0.00023	1
FBP 1A	87Q1	-0.0002	MGL	HG	-0.0002	1
FBP 1A	89Q2	-0.0002	MGL	HG	-0.0002	1
FBP 1A	91Q1	-0.0002	MGL	HG	-0.0002	2
FBP 2A	84Q3	-0.0002	MGL	HG	-0.0002	1
FBP 2A	84Q4	-0.0002	MGL	HG	-0.0002	1
FBP 2A	85Q1	-0.0002	MGL	HG	-0.0002	1
FBP 2A	87Q1	-0.0002	MGL	HG	-0.0002	1
FBP 2A	89Q2	-0.0002	MGL	HG	-0.0002	1
FBP 2A	91Q1	-0.0002	MGL	HG	-0.0002	1
FBP 3A	84Q3	-0.0002	MGL	HG	-0.0002	1
FBP 3A	84Q4	-0.0002	MGL	HG	-0.0002	1
FBP 3A	85Q1	-0.0002	MGL	HG	-0.0002	1
FBP 3A	87Q1	-0.0002	MGL	HG	-0.0002	1
FBP 3A	89Q2	-0.0002	MGL	HG	-0.0002	1
FBP 3A	91Q1	-0.0002	MGL	HG	-0.0002	1
FBP 4	85Q1	-0.0002	MGL	HG	-0.0002	2
FBP 4	85Q3	-0.0002	MGL	HG	-0.0002	1
FBP 4	85Q4	-0.0002	MGL	HG	-0.0002	1
FBP 4	86Q1	-0.0002	MGL	HG	-0.0002	1
FBP 4	87Q1	-0.0002	MGL	HG	-0.0002	1
FBP 4	89Q2	-0.0002	MGL	HG	-0.0002	1
FBP 4	91Q1	-0.0002	MGL	HG	-0.0002	1
FBP 1A	87Q1	0.86	MGL	K	0.86	1
FBP 1A	88Q3	0.825	MGL	K	0.8235	2
FBP 1A	89Q2	0.56	MGL	K	0.56	1
FBP 1A	91Q1	0.62	MGL	K	0.6	2
FBP 2A	87Q1	0.42	MGL	K	0.42	1
FBP 2A	89Q2	-0.5	MGL	K	-0.5	1
FBP 2A	91Q1	-0.5	MGL	K	-0.5	1
FBP 3A	87Q1	0.54	MGL	K	0.54	1
FBP 3A	89Q2	-0.5	MGL	K	-0.5	1
FBP 3A	91Q1	-0.5	MGL	K	-0.5	1
FBP 4	87Q1	0.3	MGL	K	0.3	1
FBP 4	89Q2	-0.5	MGL	K	-0.5	1
FBP 4	91Q1	-0.5	MGL	K	-0.5	1
FBP 1A	84Q4	-0.001	MGL	LIN	-0.001	1
FBP 1A	85Q1	-0.001	MGL	LIN	-0.001	2
FBP 1A	91Q1	0	MGL	LIN	0	2
FBP 2A	84Q4	-0.001	MGL	LIN	-0.001	1
FBP 2A	85Q1	-0.001	MGL	LIN	-0.001	1
FBP 2A	91Q1	0	MGL	LIN	0	1
FBP 3A	84Q4	-0.001	MGL	LIN	-0.001	1
FBP 3A	85Q1	-0.001	MGL	LIN	-0.001	1
FBP 3A	91Q1	0	MGL	LIN	0	1
FBP 4	85Q1	-0.001	MGL	LIN	-0.001	1
FBP 4	85Q3	-0.001	MGL	LIN	-0.001	1
FBP 4	85Q4	-0.001	MGL	LIN	-0.001	2
FBP 4	86Q1	-0.001	MGL	LIN	-0.001	1
FBP 4	91Q1	0	MGL	LIN	0	1
FBP 1A	85Q4	0.046	MGL	MEC5D8	0.046	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	85Q4	0.047	MGL	MEC6D8	0.047	1
FBP 3A	85Q4	0.047	MGL	MEC6D8	0.047	1
FBP 4	85Q4	0.041	MGL	MEC6D8	0.041	1
FBP 1A	85Q4	-0.005	MGL	MEC6H5	-0.005	1
FBP 1A	89Q3	-0.001	MGL	MEC6H5	-0.001	1
FBP 1A	90Q1	-0.001	MGL	MEC6H5	-0.001	2
FBP 2A	85Q4	-0.005	MGL	MEC6H5	-0.005	1
FBP 2A	89Q3	-0.001	MGL	MEC6H5	-0.001	1
FBP 2A	90Q1	-0.001	MGL	MEC6H5	-0.001	1
FBP 3A	85Q4	-0.005	MGL	MEC6H5	-0.005	1
FBP 3A	89Q3	-0.001	MGL	MEC6H5	-0.001	2
FBP 3A	90Q1	-0.001	MGL	MEC6H5	-0.001	1
FBP 4	85Q4	-0.005	MGL	MEC6H5	-0.005	1
FBP 4	89Q3	-0.001	MGL	MEC6H5	-0.001	1
FBP 4	90Q1	-0.001	MGL	MEC6H5	-0.001	1
FBP 1A	84Q4	-0.02	MGL	MEXCLR	-0.02	1
FBP 1A	85Q1	-0.02	MGL	MEXCLR	-0.02	2
FBP 1A	91Q1	-0.0005	MGL	MEXCLR	-0.0005	2
FBP 2A	84Q4	-0.02	MGL	MEXCLR	-0.02	1
FBP 2A	85Q1	-0.02	MGL	MEXCLR	-0.02	1
FBP 2A	91Q1	-0.0005	MGL	MEXCLR	-0.0005	1
FBP 3A	84Q4	-0.02	MGL	MEXCLR	-0.02	1
FBP 3A	85Q1	-0.02	MGL	MEXCLR	-0.02	1
FBP 3A	91Q1	-0.0005	MGL	MEXCLR	-0.0005	1
FBP 4	85Q1	-0.02	MGL	MEXCLR	-0.02	1
FBP 4	85Q3	-0.02	MGL	MEXCLR	-0.02	1
FBP 4	85Q4	-0.02	MGL	MEXCLR	-0.02	2
FBP 4	86Q1	-0.02	MGL	MEXCLR	-0.02	1
FBP 4	91Q1	-0.0005	MGL	MEXCLR	-0.0005	1
FBP 1A	87Q1	4.57	MGL	MG	4.57	1
FBP 1A	89Q2	2.59	MGL	MG	2.59	1
FBP 1A	91Q1	2.1	MGL	MG	2.1	2
FBP 2A	87Q1	0.429	MGL	MG	0.429	1
FBP 2A	89Q2	0.574	MGL	MG	0.574	1
FBP 2A	91Q1	0.95	MGL	MG	0.95	1
FBP 3A	87Q1	0.693	MGL	MG	0.693	1
FBP 3A	89Q2	0.62	MGL	MG	0.62	1
FBP 3A	91Q1	0.57	MGL	MG	0.57	1
FBP 4	87Q1	0.288	MGL	MG	0.288	1
FBP 4	89Q2	0.263	MGL	MG	0.263	1
FBP 4	91Q1	0.26	MGL	MG	0.26	1
FBP 1A	84Q3	0.022	MGL	MN	0.022	2
FBP 1A	84Q4	0.019	MGL	MN	0.019	1
FBP 1A	85Q1	0.065	MGL	MN	0.065	1
FBP 1A	86Q1	0.083	MGL	MN	0.083	1
FBP 1A	86Q3	0.086	MGL	MN	0.086	1
FBP 1A	86Q4	0.087	MGL	MN	0.085	2
FBP 1A	87Q1	0.057	MGL	MN	0.057	1
FBP 1A	87Q2	0.033	MGL	MN	0.033	1
FBP 1A	87Q3	0.026	MGL	MN	0.0215	4
FBP 1A	87Q4	0.026	MGL	MN	0.026	1
FBP 1A	88Q1	0.025	MGL	MN	0.025	2
FBP 1A	88Q3	0.036	MGL	MN	0.036	1
FBP 1A	89Q1	0.042	MGL	MN	0.0415	2
FBP 1A	89Q2	0.0346	MGL	MN	0.0346	1
FBP 1A	90Q1	0.0252	MGL	MN	0.0251	2
FBP 1A	91Q1	0.029	MGL	MN	0.029	2
FBP 2A	84Q3	0.011	MGL	MN	0.011	1
FBP 2A	84Q4	0.015	MGL	MN	0.015	1
FBP 2A	85Q1	0.014	MGL	MN	0.014	1
FBP 2A	86Q1	0.02	MGL	MN	0.02	1
FBP 2A	86Q3	0.01	MGL	MN	0.01	1
FBP 2A	86Q4	0.009	MGL	MN	0.009	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	87Q1	0.009	MGL	MN	0.009	1
FBP 2A	87Q2	0.017	MGL	MN	0.017	1
FBP 2A	87Q3	0.021	MGL	MN	0.021	1
FBP 2A	87Q4	0.026	MGL	MN	0.026	1
FBP 2A	88Q1	0.025	MGL	MN	0.025	1
FBP 2A	88Q3	0.013	MGL	MN	0.013	1
FBP 2A	89Q1	0.012	MGL	MN	0.012	1
FBP 2A	89Q2	0.0118	MGL	MN	0.0118	1
FBP 2A	90Q1	0.0113	MGL	MN	0.0113	1
FBP 2A	91Q1	0.025	MGL	MN	0.025	1
FBP 3A	84Q3	0.012	MGL	MN	0.012	1
FBP 3A	84Q4	0.006	MGL	MN	0.006	1
FBP 3A	85Q1	0.007	MGL	MN	0.007	1
FBP 3A	86Q1	0.009	MGL	MN	0.009	1
FBP 3A	86Q3	0.023	MGL	MN	0.023	1
FBP 3A	86Q4	0.009	MGL	MN	0.009	1
FBP 3A	87Q1	0.007	MGL	MN	0.007	1
FBP 3A	87Q2	0.023	MGL	MN	0.023	1
FBP 3A	87Q3	0.009	MGL	MN	0.009	1
FBP 3A	87Q4	0.007	MGL	MN	0.007	1
FBP 3A	88Q1	0.006	MGL	MN	0.006	2
FBP 3A	88Q3	0.01	MGL	MN	0.01	1
FBP 3A	89Q1	0.007	MGL	MN	0.007	1
FBP 3A	89Q2	0.00688	MGL	MN	0.00688	1
FBP 3A	90Q1	0.0049	MGL	MN	0.0049	1
FBP 3A	91Q1	0.0054	MGL	MN	0.0054	1
FBP 4	85Q1	0.003	MGL	MN	0.003	1
FBP 4	85Q3	0.003	MGL	MN	0.003	1
FBP 4	85Q4	0.003	MGL	MN	0.003	2
FBP 4	86Q1	0.002	MGL	MN	0.002	1
FBP 4	86Q3	0.002	MGL	MN	0.002	1
FBP 4	86Q4	0.002	MGL	MN	0.002	1
FBP 4	87Q1	0.002	MGL	MN	0.002	1
FBP 4	87Q2	0.002	MGL	MN	0.002	1
FBP 4	87Q3	0.004	MGL	MN	0.004	1
FBP 4	87Q4	0.003	MGL	MN	0.003	1
FBP 4	88Q1	0.002	MGL	MN	0.002	1
FBP 4	88Q3	0.003	MGL	MN	0.003	1
FBP 4	89Q1	0.002	MGL	MN	0.002	2
FBP 4	89Q2	0.00285	MGL	MN	0.00285	1
FBP 4	90Q1	-0.002	MGL	MN	-0.002	1
FBP 4	91Q1	-0.002	MGL	MN	-0.002	1
FBP 1A	84Q3	3.13	MGL	NA	2.965	2
FBP 1A	84Q4	2.19	MGL	NA	2.19	1
FBP 1A	85Q1	4.17	MGL	NA	4.17	1
FBP 1A	86Q1	6.05	MGL	NA	6.05	1
FBP 1A	87Q1	4.91	MGL	NA	4.91	1
FBP 1A	88Q1	3.6	MGL	NA	3.585	2
FBP 1A	89Q1	4.47	MGL	NA	4.44	2
FBP 1A	89Q2	4.48	MGL	NA	4.48	1
FBP 1A	90Q1	3.89	MGL	NA	3.825	2
FBP 1A	91Q1	4.5	MGL	NA	4.4	2
FBP 2A	84Q3	6.84	MGL	NA	6.84	1
FBP 2A	84Q4	9.46	MGL	NA	9.46	1
FBP 2A	85Q1	7.49	MGL	NA	7.49	1
FBP 2A	86Q1	14.1	MGL	NA	14.1	1
FBP 2A	87Q1	4.27	MGL	NA	4.27	1
FBP 2A	88Q1	8.87	MGL	NA	8.87	1
FBP 2A	89Q1	3.06	MGL	NA	3.06	1
FBP 2A	89Q2	3.72	MGL	NA	3.72	1
FBP 2A	90Q1	3.71	MGL	NA	3.71	1
FBP 2A	91Q1	5.1	MGL	NA	5.1	1
FBP 3A	84Q3	4.63	MGL	NA	4.63	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 3A	84Q4	4.24	MGL	NA	4.24	1
FBP 3A	85Q1	4.41	MGL	NA	4.41	1
FBP 3A	86Q1	7.83	MGL	NA	7.83	1
FBP 3A	87Q1	4.9	MGL	NA	4.9	1
FBP 3A	88Q1	4.48	MGL	NA	4.365	2
FBP 3A	89Q1	4.51	MGL	NA	4.51	1
FBP 3A	89Q2	4.75	MGL	NA	4.75	1
FBP 3A	90Q1	3.99	MGL	NA	3.99	1
FBP 3A	91Q1	4.5	MGL	NA	4.5	1
FBP 4	85Q1	1.57	MGL	NA	1.57	1
FBP 4	85Q3	1.65	MGL	NA	1.65	1
FBP 4	85Q4	1.93	MGL	NA	1.9	2
FBP 4	86Q1	1.74	MGL	NA	1.74	1
FBP 4	87Q1	2.12	MGL	NA	2.12	1
FBP 4	88Q1	2.19	MGL	NA	2.19	1
FBP 4	89Q1	2.77	MGL	NA	2.695	2
FBP 4	89Q2	3.33	MGL	NA	3.33	1
FBP 4	90Q1	2.77	MGL	NA	2.77	1
FBP 4	91Q1	3.4	MGL	NA	3.4	1
FBP 1A	84Q3	-0.004	MGL	NI	-0.004	2
FBP 1A	84Q4	-0.004	MGL	NI	-0.004	1
FBP 1A	86Q2	0.012	MGL	NI	0.012	1
FBP 1A	87Q1	-0.004	MGL	NI	-0.004	1
FBP 1A	88Q1	-0.004	MGL	NI	-0.004	2
FBP 1A	89Q1	0.012	MGL	NI	0.0095	2
FBP 1A	90Q1	-0.004	MGL	NI	-0.004	2
FBP 2A	84Q3	-0.004	MGL	NI	-0.004	1
FBP 2A	84Q4	-0.004	MGL	NI	-0.004	1
FBP 2A	86Q2	-0.004	MGL	NI	-0.004	1
FBP 2A	87Q1	-0.004	MGL	NI	-0.004	1
FBP 2A	88Q1	0.005	MGL	NI	0.005	1
FBP 2A	89Q1	0.005	MGL	NI	0.005	1
FBP 2A	90Q1	-0.004	MGL	NI	-0.004	1
FBP 3A	84Q3	0.009	MGL	NI	0.009	1
FBP 3A	84Q4	0.008	MGL	NI	0.008	1
FBP 3A	86Q2	-0.004	MGL	NI	-0.004	1
FBP 3A	87Q1	-0.004	MGL	NI	-0.004	1
FBP 3A	88Q1	-0.004	MGL	NI	-0.004	2
FBP 3A	89Q1	-0.004	MGL	NI	-0.004	1
FBP 3A	90Q1	-0.004	MGL	NI	-0.004	1
FBP 4	86Q2	-0.004	MGL	NI	-0.004	1
FBP 4	87Q1	-0.004	MGL	NI	-0.004	1
FBP 4	88Q1	-0.004	MGL	NI	-0.004	1
FBP 4	89Q1	-0.004	MGL	NI	-0.004	2
FBP 4	90Q1	-0.004	MGL	NI	-0.004	1
FBP 1A	84Q3	-0.5	MGL	NO2	-0.5	1
FBP 1A	84Q4	-0.5	MGL	NO2	-0.5	1
FBP 2A	84Q3	-0.5	MGL	NO2	-0.5	1
FBP 2A	84Q4	-0.5	MGL	NO2	-0.5	1
FBP 3A	84Q3	-0.5	MGL	NO2	-0.5	1
FBP 3A	84Q4	-0.5	MGL	NO2	-0.5	1
FBP 1A	84Q3	2.25	MGL	NO3	2.25	1
FBP 1A	84Q4	1.85	MGL	NO3	1.85	1
FBP 1A	85Q1	18	MGL	NO3	18	2
FBP 1A	86Q2	22	MGL	NO3	22	2
FBP 1A	86Q3	24.55	MGL	NO3	24.55	1
FBP 1A	86Q4	23.7	MGL	NO3	23.65	2
FBP 1A	87Q1	16.9	MGL	NO3	16.9	1
FBP 1A	87Q2	12	MGL	NO3	12	2
FBP 1A	87Q3	8.21	MGL	NO3	7.71	3
FBP 1A	87Q4	12.8	MGL	NO3	12.8	1
FBP 1A	88Q1	5.68	MGL	NO3	5.68	1
FBP 1A	88Q3	9.72	MGL	NO3	9.72	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 1A	89Q1	9.01	MGL	NO3	9.01	1
FBP 1A	89Q2	9.8	MGL	NO3	9.8	1
FBP 1A	89Q3	0.38	MGL	NO3	0.38	1
FBP 1A	90Q1	8.06	MGL	NO3	8.03	2
FBP 1A	91Q1	6.95	MGL	NO3	6.4	2
FBP 2A	84Q3	2	MGL	NO3	2	1
FBP 2A	84Q4	1.73	MGL	NO3	1.73	1
FBP 2A	85Q1	1.8	MGL	NO3	1.775	2
FBP 2A	86Q2	1.58	MGL	NO3	1.58	1
FBP 2A	86Q3	1.29	MGL	NO3	1.29	1
FBP 2A	86Q4	1.44	MGL	NO3	1.44	1
FBP 2A	87Q1	1.27	MGL	NO3	1.27	1
FBP 2A	87Q2	1.5	MGL	NO3	1.5	1
FBP 2A	87Q3	10.2	MGL	NO3	10.2	1
FBP 2A	87Q4	3.18	MGL	NO3	3.165	2
FBP 2A	88Q1	2.19	MGL	NO3	2.19	1
FBP 2A	88Q3	1.81	MGL	NO3	1.81	1
FBP 2A	89Q1	1.51	MGL	NO3	1.51	1
FBP 2A	89Q2	1.2	MGL	NO3	1.2	1
FBP 2A	89Q3	0.78	MGL	NO3	0.78	1
FBP 2A	90Q1	1.49	MGL	NO3	1.49	1
FBP 2A	91Q1	2.27	MGL	NO3	2.27	1
FBP 3A	84Q3	-0.5	MGL	NO3	-0.5	1
FBP 3A	84Q4	-0.5	MGL	NO3	-0.5	1
FBP 3A	85Q1	0.5	MGL	NO3	0.5	1
FBP 3A	86Q2	0.54	MGL	NO3	0.54	1
FBP 3A	86Q3	1.08	MGL	NO3	1.08	1
FBP 3A	86Q4	0.4	MGL	NO3	0.4	1
FBP 3A	87Q1	0.31	MGL	NO3	0.31	1
FBP 3A	87Q2	0.3	MGL	NO3	0.3	1
FBP 3A	87Q3	0.67	MGL	NO3	0.67	1
FBP 3A	87Q4	0.58	MGL	NO3	0.58	1
FBP 3A	88Q1	0.5	MGL	NO3	0.5	1
FBP 3A	88Q3	0.44	MGL	NO3	0.44	1
FBP 3A	89Q1	0.291	MGL	NO3	0.291	1
FBP 3A	89Q2	0.34	MGL	NO3	0.34	1
FBP 3A	89Q3	0.29	MGL	NO3	0.28	2
FBP 3A	90Q1	0.18	MGL	NO3	0.18	1
FBP 3A	91Q1	0.26	MGL	NO3	0.26	1
FBP 4	85Q1	-0.5	MGL	NO3	-0.5	1
FBP 4	85Q3	-0.5	MGL	NO3	-0.5	1
FBP 4	85Q4	-0.5	MGL	NO3	-0.5	2
FBP 4	86Q1	0.62	MGL	NO3	0.62	1
FBP 4	86Q2	0.5	MGL	NO3	0.5	1
FBP 4	86Q3	0.3	MGL	NO3	0.3	1
FBP 4	86Q4	0.43	MGL	NO3	0.43	1
FBP 4	87Q1	0.44	MGL	NO3	0.44	1
FBP 4	87Q2	0.45	MGL	NO3	0.45	1
FBP 4	87Q3	0.76	MGL	NO3	0.76	1
FBP 4	87Q4	0.68	MGL	NO3	0.68	1
FBP 4	88Q1	0.58	MGL	NO3	0.58	1
FBP 4	88Q3	0.47	MGL	NO3	0.47	1
FBP 4	89Q1	0.377	MGL	NO3	0.377	1
FBP 4	89Q2	0.48	MGL	NO3	0.48	1
FBP 4	89Q3	0.43	MGL	NO3	0.43	1
FBP 4	90Q1	0.26	MGL	NO3	0.26	1
FBP 4	91Q1	0.31	MGL	NO3	0.31	1
FBP 1A	84Q3	4	THON	ODOR	4	1
FBP 1A	84Q4	0	THON	ODOR	0	1
FBP 2A	84Q3	4	THON	ODOR	4	1
FBP 2A	84Q4	0	THON	ODOR	0	1
FBP 3A	84Q3	2	THON	ODOR	2	1
FBP 3A	84Q4	0	THON	ODOR	0	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 1A	84Q3	0.005	MGL	PB	0.005	2
FBP 1A	84Q4	-0.004	MGL	PB	-0.004	1
FBP 1A	85Q1	0.038	MGL	PB	0.038	1
FBP 1A	86Q1	-0.01	MGL	PB	-0.01	1
FBP 1A	86Q3	0.025	MGL	PB	0.025	1
FBP 1A	86Q4	0.007	MGL	PB	0.007	2
FBP 1A	87Q1	-0.006	MGL	PB	-0.006	1
FBP 1A	87Q2	-0.006	MGL	PB	-0.006	1
FBP 1A	87Q3	0.02	MGL	PB	0.00725	4
FBP 1A	87Q4	-0.006	MGL	PB	-0.006	1
FBP 1A	88Q1	-0.006	MGL	PB	-0.006	2
FBP 1A	88Q3	-0.006	MGL	PB	-0.006	1
FBP 1A	89Q1	0.006	MGL	PB	0.0045	2
FBP 1A	89Q2	-0.006	MGL	PB	-0.006	1
FBP 1A	90Q1	-0.006	MGL	PB	-0.006	2
FBP 1A	91Q1	-0.003	MGL	PB	-0.003	2
FBP 2A	84Q3	0.005	MGL	PB	0.005	1
FBP 2A	84Q4	0.026	MGL	PB	0.026	1
FBP 2A	85Q1	-0.004	MGL	PB	-0.004	1
FBP 2A	86Q1	-0.01	MGL	PB	-0.01	1
FBP 2A	86Q3	-0.006	MGL	PB	-0.006	1
FBP 2A	86Q4	-0.005	MGL	PB	-0.005	1
FBP 2A	87Q1	-0.006	MGL	PB	-0.006	1
FBP 2A	87Q2	0.008	MGL	PB	0.008	1
FBP 2A	87Q3	-0.006	MGL	PB	-0.006	1
FBP 2A	87Q4	-0.006	MGL	PB	-0.006	1
FBP 2A	88Q1	0.006	MGL	PB	0.006	1
FBP 2A	88Q3	-0.006	MGL	PB	-0.006	1
FBP 2A	89Q1	0.007	MGL	PB	0.007	1
FBP 2A	89Q2	-0.006	MGL	PB	-0.006	1
FBP 2A	90Q1	-0.006	MGL	PB	-0.006	1
FBP 2A	91Q1	-0.003	MGL	PB	-0.003	1
FBP 3A	84Q3	-0.004	MGL	PB	-0.004	1
FBP 3A	84Q4	0.01	MGL	PB	0.01	1
FBP 3A	85Q1	-0.004	MGL	PB	-0.004	1
FBP 3A	86Q1	-0.01	MGL	PB	-0.01	1
FBP 3A	86Q3	-0.006	MGL	PB	-0.006	1
FBP 3A	86Q4	-0.005	MGL	PB	-0.005	1
FBP 3A	87Q1	-0.006	MGL	PB	-0.006	1
FBP 3A	87Q2	0.072	MGL	PB	0.072	1
FBP 3A	87Q3	-0.006	MGL	PB	-0.006	1
FBP 3A	87Q4	-0.006	MGL	PB	-0.006	1
FBP 3A	88Q1	-0.006	MGL	PB	-0.006	3
FBP 3A	88Q3	-0.006	MGL	PB	-0.006	1
FBP 3A	89Q1	-0.006	MGL	PB	-0.006	1
FBP 3A	89Q2	-0.006	MGL	PB	-0.006	1
FBP 3A	90Q1	-0.006	MGL	PB	-0.006	1
FBP 3A	91Q1	-0.003	MGL	PB	-0.003	1
FBP 4	85Q1	-0.004	MGL	PB	-0.004	1
FBP 4	85Q3	0.022	MGL	PB	0.022	1
FBP 4	85Q4	-0.005	MGL	PB	-0.005	2
FBP 4	86Q1	-0.01	MGL	PB	-0.01	1
FBP 4	86Q3	-0.006	MGL	PB	-0.006	1
FBP 4	86Q4	-0.005	MGL	PB	-0.005	1
FBP 4	87Q1	-0.006	MGL	PB	-0.006	1
FBP 4	87Q2	-0.006	MGL	PB	-0.006	1
FBP 4	87Q3	0.01	MGL	PB	0.01	1
FBP 4	87Q4	-0.006	MGL	PB	-0.006	1
FBP 4	88Q1	-0.006	MGL	PB	-0.006	1
FBP 4	88Q3	-0.006	MGL	PB	-0.006	1
FBP 4	89Q1	-0.006	MGL	PB	-0.006	2
FBP 4	89Q2	-0.006	MGL	PB	-0.006	1
FBP 4	90Q1	0.00875	MGL	PB	0.00875	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 4	91Q1	-0.003	MGL	PB	-0.003	1
FBP 1A	85Q4	0.051	MGL	PBFB	0.051	1
FBP 2A	85Q4	0.051	MGL	PBFB	0.051	1
FBP 3A	85Q4	0.055	MGL	PBFB	0.055	1
FBP 4	85Q4	0.05	MGL	PBFB	0.05	1
FBP 1A	84Q3	6.3	PH	PH	6.3	1
FBP 1A	84Q4	5.53	PH	PH	5.53	1
FBP 1A	85Q1	5.8	PH	PH	5.8	1
FBP 1A	85Q2	4.8	PH	PH	4.8	1
FBP 1A	85Q3	4.7	PH	PH	4.7	1
FBP 1A	85Q4	4.65	PH	PH	4.65	2
FBP 1A	86Q1	4.56	PH	PH	4.56	1
FBP 1A	86Q2	4.41	PH	PH	4.41	1
FBP 1A	86Q3	4.43	PH	PH	4.42	2
FBP 1A	86Q4	3.97	PH	PH	3.97	1
FBP 1A	87Q1	4.62	PH	PH	4.62	1
FBP 1A	87Q2	4.74	PH	PH	4.74	1
FBP 1A	87Q3	4.62	PH	PH	4.1625	4
FBP 1A	87Q4	4.63	PH	PH	4.63	1
FBP 1A	88Q1	5.04	PH	PH	5.04	2
FBP 1A	89Q1	4.7	PH	PH	4.7	1
FBP 1A	89Q2	4.65	PH	PH	4.65	1
FBP 1A	90Q1	4.75	PH	PH	4.75	2
FBP 1A	91Q1	5.07	PH	PH	5.07	2
FBP 2A	84Q3	6.1	PH	PH	6.1	1
FBP 2A	84Q4	6.05	PH	PH	6.05	1
FBP 2A	85Q1	6.9	PH	PH	6.9	1
FBP 2A	85Q2	5.4	PH	PH	5.4	1
FBP 2A	85Q3	5.2	PH	PH	5.2	1
FBP 2A	85Q4	5.05	PH	PH	5.05	1
FBP 2A	86Q1	5.17	PH	PH	5.17	1
FBP 2A	86Q2	5.01	PH	PH	5.01	1
FBP 2A	86Q3	6.2	PH	PH	6.2	1
FBP 2A	86Q4	4.36	PH	PH	4.36	1
FBP 2A	87Q1	5.36	PH	PH	5.36	1
FBP 2A	87Q2	5.18	PH	PH	5.18	1
FBP 2A	87Q3	5.3	PH	PH	5.3	1
FBP 2A	87Q4	5.22	PH	PH	5.21	2
FBP 2A	88Q1	5.32	PH	PH	5.32	1
FBP 2A	89Q1	5	PH	PH	5	1
FBP 2A	89Q2	5.18	PH	PH	5.18	1
FBP 2A	90Q1	5.2	PH	PH	5.2	1
FBP 2A	91Q1	5.46	PH	PH	5.46	1
FBP 3A	84Q3	6.2	PH	PH	6.2	1
FBP 3A	84Q4	5.86	PH	PH	5.86	1
FBP 3A	85Q1	7.2	PH	PH	7.2	1
FBP 3A	85Q2	5.5	PH	PH	5.5	1
FBP 3A	85Q3	5.4	PH	PH	5.4	1
FBP 3A	85Q4	3.55	PH	PH	3.55	1
FBP 3A	86Q1	5.3	PH	PH	5.3	1
FBP 3A	86Q2	5	PH	PH	5	1
FBP 3A	86Q3	5.45	PH	PH	5.45	1
FBP 3A	86Q4	4.85	PH	PH	4.85	2
FBP 3A	87Q1	5.34	PH	PH	5.34	1
FBP 3A	87Q2	5.32	PH	PH	5.32	1
FBP 3A	87Q3	5.43	PH	PH	5.43	1
FBP 3A	88Q1	5.54	PH	PH	5.54	1
FBP 3A	89Q1	5.37	PH	PH	5.37	1
FBP 3A	89Q2	5.3	PH	PH	5.3	1
FBP 3A	90Q1	5.23	PH	PH	5.23	1
FBP 3A	91Q1	5.53	PH	PH	5.53	1
FBP 4	85Q1	6.8	PH	PH	6.8	1
FBP 4	85Q2	5.3	PH	PH	5.3	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 4	85Q3	5.4	PH	PH	5.4	1
FBP 4	85Q4	5	PH	PH	5	2
FBP 4	86Q1	4.87	PH	PH	4.87	1
FBP 4	86Q2	4.76	PH	PH	4.76	1
FBP 4	86Q3	5.13	PH	PH	5.13	1
FBP 4	86Q4	4.36	PH	PH	4.36	1
FBP 4	87Q1	5	PH	PH	5	1
FBP 4	87Q2	4.885	PH	PH	4.885	2
FBP 4	87Q3	4.65	PH	PH	4.65	1
FBP 4	87Q4	4.87	PH	PH	4.87	1
FBP 4	88Q1	5.13	PH	PH	5.13	1
FBP 4	89Q1	4.96	PH	PH	4.96	1
FBP 4	89Q2	5.02	PH	PH	5.02	1
FBP 4	90Q1	4.99	PH	PH	4.99	1
FBP 4	91Q1	5.26	PH	PH	5.26	1
FBP 1A	84Q3	-0.01	MGL	PHENOL	-0.01	1
FBP 1A	84Q4	-0.002	MGL	PHENOL	-0.002	1
FBP 1A	85Q1	-0.002	MGL	PHENOL	-0.002	1
FBP 1A	86Q1	-0.002	MGL	PHENOL	-0.002	1
FBP 1A	87Q1	-0.002	MGL	PHENOL	-0.002	1
FBP 1A	89Q2	-0.005	MGL	PHENOL	-0.005	1
FBP 1A	91Q1	-0.005	MGL	PHENOL	-0.005	2
FBP 2A	84Q3	-0.01	MGL	PHENOL	-0.01	2
FBP 2A	84Q4	-0.002	MGL	PHENOL	-0.002	1
FBP 2A	85Q1	-0.002	MGL	PHENOL	-0.002	1
FBP 2A	86Q1	-0.002	MGL	PHENOL	-0.002	1
FBP 2A	87Q1	-0.002	MGL	PHENOL	-0.002	1
FBP 2A	89Q2	-0.005	MGL	PHENOL	-0.005	1
FBP 2A	91Q1	-0.005	MGL	PHENOL	-0.005	1
FBP 3A	84Q3	-0.01	MGL	PHENOL	-0.01	1
FBP 3A	84Q4	-0.002	MGL	PHENOL	-0.002	1
FBP 3A	85Q1	-0.002	MGL	PHENOL	-0.002	2
FBP 3A	86Q1	-0.002	MGL	PHENOL	-0.002	1
FBP 3A	87Q1	-0.002	MGL	PHENOL	-0.002	1
FBP 3A	89Q2	-0.005	MGL	PHENOL	-0.005	1
FBP 3A	91Q1	-0.005	MGL	PHENOL	-0.005	1
FBP 4	85Q1	-0.002	MGL	PHENOL	-0.002	1
FBP 4	85Q3	-0.002	MGL	PHENOL	-0.002	1
FBP 4	85Q4	-0.002	MGL	PHENOL	-0.002	1
FBP 4	86Q1	-0.002	MGL	PHENOL	-0.002	1
FBP 4	87Q1	-0.002	MGL	PHENOL	-0.002	2
FBP 4	89Q2	-0.005	MGL	PHENOL	-0.005	1
FBP 4	91Q1	-0.005	MGL	PHENOL	-0.005	1
FBP 1A	86Q3	1.51	PCL	PU	1.51	1
FBP 2A	86Q3	0.5	PCL	PU	0.5	1
FBP 3A	86Q3	0.5	PCL	PU	0.5	1
FBP 4	86Q3	1.01	PCL	PU	1.01	1
FBP 1A	89Q3	-0.2	PCL	PU238	-0.2	1
FBP 2A	89Q3	-0.2	PCL	PU238	-0.2	1
FBP 3A	89Q3	-0.1	PCL	PU238	-0.1	1
FBP 4	89Q3	-0.1	PCL	PU238	-0.1	1
FBP 1A	89Q3	1.3	PCL	PU242	1.3	1
FBP 2A	89Q3	0.63	PCL	PU242	0.63	1
FBP 3A	89Q3	-0.2	PCL	PU242	-0.2	1
FBP 4	89Q3	-0.1	PCL	PU242	-0.1	1
FBP 1A	89Q3	3	PCL	PU3940	3	1
FBP 2A	89Q3	-0.08	PCL	PU3940	-0.08	1
FBP 3A	89Q3	-0.1	PCL	PU3940	-0.1	1
FBP 4	89Q3	-0.1	PCL	PU3940	-0.1	1
FBP 1A	84Q3	-0.001	MGL	SE	-0.001	2
FBP 1A	84Q4	-0.001	MGL	SE	-0.001	1
FBP 1A	85Q1	-0.001	MGL	SE	-0.001	1
FBP 1A	87Q1	-0.002	MGL	SE	-0.002	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 1A	89Q2	-0.002	MGL	SE	-0.002	1
FBP 1A	91Q1	-0.002	MGL	SE	-0.002	2
FBP 2A	84Q3	-0.001	MGL	SE	-0.001	1
FBP 2A	84Q4	-0.001	MGL	SE	-0.001	1
FBP 2A	85Q1	-0.001	MGL	SE	-0.001	1
FBP 2A	87Q1	-0.002	MGL	SE	-0.002	1
FBP 2A	89Q2	-0.002	MGL	SE	-0.002	1
FBP 2A	91Q1	-0.002	MGL	SE	-0.002	1
FBP 3A	84Q3	-0.001	MGL	SE	-0.001	1
FBP 3A	84Q4	-0.001	MGL	SE	-0.001	1
FBP 3A	85Q1	-0.001	MGL	SE	-0.001	1
FBP 3A	87Q1	-0.002	MGL	SE	-0.002	2
FBP 3A	89Q2	-0.002	MGL	SE	-0.002	1
FBP 3A	91Q1	-0.002	MGL	SE	-0.002	1
FBP 4	85Q1	-0.001	MGL	SE	-0.001	1
FBP 4	85Q3	-0.002	MGL	SE	-0.002	1
FBP 4	85Q4	-0.002	MGL	SE	-0.002	2
FBP 4	86Q1	-0.002	MGL	SE	-0.002	1
FBP 4	87Q1	-0.002	MGL	SE	-0.002	1
FBP 4	89Q2	-0.002	MGL	SE	-0.002	1
FBP 4	91Q1	-0.002	MGL	SE	-0.002	1
FBP 1A	90Q1	7.38	MGL	SI	7.31	2
FBP 1A	91Q1	10	MGL	SI	9.95	2
FBP 2A	90Q1	6.82	MGL	SI	6.82	1
FBP 2A	91Q1	8.2	MGL	SI	8.2	1
FBP 3A	90Q1	7.8	MGL	SI	7.8	1
FBP 3A	91Q1	8.9	MGL	SI	8.9	1
FBP 4	90Q1	6.06	MGL	SI	6.06	1
FBP 4	91Q1	6.8	MGL	SI	6.8	1
FBP 1A	87Q1	4.44	MGL	SILICA	4.44	1
FBP 1A	89Q2	9.35	MGL	SILICA	9.35	1
FBP 2A	87Q1	3.58	MGL	SILICA	3.58	1
FBP 2A	89Q2	8.01	MGL	SILICA	8.01	1
FBP 3A	87Q1	4.34	MGL	SILICA	4.34	1
FBP 3A	89Q2	9.26	MGL	SILICA	9.26	1
FBP 4	87Q1	3.13	MGL	SILICA	3.13	1
FBP 4	89Q2	7.08	MGL	SILICA	7.08	1
FBP 1A	84Q4	-0.002	MGL	SILVEX	-0.002	1
FBP 1A	85Q1	-0.002	MGL	SILVEX	-0.002	1
FBP 1A	91Q1	-0.00009	MGL	SILVEX	-0.00009	2
FBP 2A	84Q4	-0.002	MGL	SILVEX	-0.002	1
FBP 2A	85Q1	-0.002	MGL	SILVEX	-0.002	1
FBP 2A	91Q1	-0.00009	MGL	SILVEX	-0.00009	1
FBP 3A	84Q4	-0.002	MGL	SILVEX	-0.002	2
FBP 3A	85Q1	-0.002	MGL	SILVEX	-0.002	1
FBP 3A	91Q1	-0.00009	MGL	SILVEX	-0.00009	1
FBP 4	85Q1	-0.002	MGL	SILVEX	-0.002	1
FBP 4	85Q3	-0.002	MGL	SILVEX	-0.002	1
FBP 4	85Q4	-0.002	MGL	SILVEX	-0.002	1
FBP 4	86Q1	-0.002	MGL	SILVEX	-0.002	1
FBP 4	91Q1	-0.00009	MGL	SILVEX	-0.00009	1
FBP 1A	84Q3	-10	MGL	SO4	-10	1
FBP 1A	84Q4	-5	MGL	SO4	-5	1
FBP 1A	85Q1	-5	MGL	SO4	-5	1
FBP 1A	87Q1	-5	MGL	SO4	-5	1
FBP 1A	88Q1	-5	MGL	SO4	-5	1
FBP 1A	89Q1	-5	MGL	SO4	-5	1
FBP 1A	89Q2	-5	MGL	SO4	-5	1
FBP 1A	90Q1	11.8	MGL	SO4	11.25	2
FBP 1A	91Q1	4.74	MGL	SO4	4.5	2
FBP 2A	84Q3	10	MGL	SO4	10	1
FBP 2A	84Q4	-5	MGL	SO4	-5	1
FBP 2A	85Q1	5	MGL	SO4	5	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	87Q1	-5	MGL	SO4	-5	1
FBP 2A	88Q1	7	MGL	SO4	7	1
FBP 2A	89Q1	-5	MGL	SO4	-5	1
FBP 2A	89Q2	-5	MGL	SO4	-5	1
FBP 2A	90Q1	-5	MGL	SO4	-5	1
FBP 2A	91Q1	2.09	MGL	SO4	2.09	1
FBP 3A	84Q3	10	MGL	SO4	10	1
FBP 3A	84Q4	-5	MGL	SO4	-5	1
FBP 3A	85Q1	12	MGL	SO4	12	1
FBP 3A	87Q1	10	MGL	SO4	10	1
FBP 3A	88Q1	10	MGL	SO4	10	1
FBP 3A	89Q1	12.1	MGL	SO4	12.1	1
FBP 3A	89Q2	13	MGL	SO4	13	1
FBP 3A	90Q1	13.4	MGL	SO4	13.4	1
FBP 3A	91Q1	11.9	MGL	SO4	11.9	1
FBP 4	85Q1	-5	MGL	SO4	-5	1
FBP 4	85Q3	-5	MGL	SO4	-5	1
FBP 4	85Q4	-5	MGL	SO4	-5	1
FBP 4	87Q1	-5	MGL	SO4	-5	1
FBP 4	88Q1	-5	MGL	SO4	-5	1
FBP 4	89Q1	-5	MGL	SO4	-5	2
FBP 4	89Q2	-5	MGL	SO4	-5	1
FBP 4	90Q1	8.9	MGL	SO4	8.9	1
FBP 4	91Q1	4.17	MGL	SO4	4.17	1
FBP 1A	86Q2	35.25	PCL	SR	35.25	1
FBP 4	86Q2	14.48	PCL	SR	14.48	1
FBP 1A	89Q3	-5	PCL	SR89	-5	1
FBP 2A	89Q3	-5	PCL	SR89	-5	1
FBP 3A	89Q3	-4	PCL	SR89	-4	1
FBP 4	89Q3	-4	PCL	SR89	-4	1
FBP 1A	89Q3	-1	PCL	SR90	-1	1
FBP 2A	89Q3	-1	PCL	SR90	-1	1
FBP 3A	89Q3	-1	PCL	SR90	-1	1
FBP 4	89Q3	-1	PCL	SR90	-1	1
FBP 1A	84Q3	-1	MGL	SULFID	-1	1
FBP 1A	84Q4	-1	MGL	SULFID	-1	1
FBP 2A	84Q3	-1	MGL	SULFID	-1	1
FBP 2A	84Q4	-1	MGL	SULFID	-1	1
FBP 3A	84Q3	-1	MGL	SULFID	-1	1
FBP 3A	84Q4	-1	MGL	SULFID	-1	1
FBP 1A	84Q3	0.017	MGL	SUR	0.015	2
FBP 1A	84Q4	-0.01	MGL	SUR	-0.01	1
FBP 2A	84Q3	-0.01	MGL	SUR	-0.01	1
FBP 2A	84Q4	-0.01	MGL	SUR	-0.01	1
FBP 3A	84Q3	-0.01	MGL	SUR	-0.01	1
FBP 3A	84Q4	-0.01	MGL	SUR	-0.01	1
FBP 1A	85Q4	-0.01	MGL	TCLEA	-0.01	1
FBP 1A	87Q3	-0.001	MGL	TCLEA	-0.001	1
FBP 1A	89Q3	-0.001	MGL	TCLEA	-0.001	1
FBP 1A	90Q1	-0.001	MGL	TCLEA	-0.001	2
FBP 2A	85Q4	-0.01	MGL	TCLEA	-0.01	1
FBP 2A	89Q3	-0.001	MGL	TCLEA	-0.001	1
FBP 2A	90Q1	-0.001	MGL	TCLEA	-0.001	1
FBP 3A	85Q4	-0.01	MGL	TCLEA	-0.01	1
FBP 3A	89Q3	-0.001	MGL	TCLEA	-0.001	2
FBP 3A	90Q1	-0.001	MGL	TCLEA	-0.001	1
FBP 4	85Q4	-0.01	MGL	TCLEA	-0.01	1
FBP 4	89Q3	-0.001	MGL	TCLEA	-0.001	1
FBP 4	90Q1	-0.001	MGL	TCLEA	-0.001	1
FBP 1A	85Q4	-0.005	MGL	TCLEE	-0.005	1
FBP 1A	86Q1	0.001	MGL	TCLEE	0.001	2
FBP 1A	86Q3	0.00395	MGL	TCLEE	0.00388	2
FBP 1A	86Q4	-0.001	MGL	TCLEE	-0.001	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 1A	87Q1	-0.001	MGL	TCLEE	-0.001	1
FBP 1A	87Q2	-0.001	MGL	TCLEE	-0.001	1
FBP 1A	87Q3	0.00137	MGL	TCLEE	0.00079	3
FBP 1A	87Q4	-0.001	MGL	TCLEE	-0.001	1
FBP 1A	88Q1	0.00456	MGL	TCLEE	0.00456	1
FBP 1A	88Q3	-0.001	MGL	TCLEE	-0.001	2
FBP 1A	89Q1	-0.001	MGL	TCLEE	-0.001	1
FBP 1A	89Q3	-0.001	MGL	TCLEE	-0.001	1
FBP 1A	90Q1	-0.001	MGL	TCLEE	-0.001	2
FBP 1A	90Q3	-0.001	MGL	TCLEE	-0.001	1
FBP 1A	91Q1	-0.001	MGL	TCLEE	-0.001	2
FBP 2A	85Q4	0.098	MGL	TCLEE	0.098	1
FBP 2A	86Q1	0.104	MGL	TCLEE	0.104	1
FBP 2A	86Q3	0.0291	MGL	TCLEE	0.02795	2
FBP 2A	86Q4	0.0233	MGL	TCLEE	0.0233	1
FBP 2A	87Q1	0.0172	MGL	TCLEE	0.0172	1
FBP 2A	87Q2	0.0399	MGL	TCLEE	0.0399	1
FBP 2A	87Q3	-0.001	MGL	TCLEE	-0.001	1
FBP 2A	87Q4	0.0688	MGL	TCLEE	0.0688	1
FBP 2A	88Q1	0.0602	MGL	TCLEE	0.0602	1
FBP 2A	88Q3	0.052	MGL	TCLEE	0.052	1
FBP 2A	89Q1	-0.001	MGL	TCLEE	-0.001	1
FBP 2A	89Q3	-0.001	MGL	TCLEE	-0.001	1
FBP 2A	90Q1	0.02	MGL	TCLEE	0.02	1
FBP 2A	90Q3	0.039	MGL	TCLEE	0.039	1
FBP 2A	91Q1	0.031	MGL	TCLEE	0.031	1
FBP 3A	85Q4	0.011	MGL	TCLEE	0.011	1
FBP 3A	86Q1	0.012	MGL	TCLEE	0.012	1
FBP 3A	86Q3	0.00783	MGL	TCLEE	0.00783	1
FBP 3A	86Q4	0.00617	MGL	TCLEE	0.00617	1
FBP 3A	87Q1	0.00297	MGL	TCLEE	0.00297	1
FBP 3A	87Q2	0.00325	MGL	TCLEE	0.00325	1
FBP 3A	87Q3	-0.001	MGL	TCLEE	-0.001	1
FBP 3A	87Q4	0.0035	MGL	TCLEE	0.0035	1
FBP 3A	88Q1	0.00762	MGL	TCLEE	0.00762	1
FBP 3A	88Q3	0.006	MGL	TCLEE	0.006	1
FBP 3A	89Q1	0.00516	MGL	TCLEE	0.00516	1
FBP 3A	89Q3	-0.001	MGL	TCLEE	-0.001	2
FBP 3A	90Q1	0.001	MGL	TCLEE	0.001	1
FBP 3A	90Q3	-0.001	MGL	TCLEE	-0.001	1
FBP 3A	91Q1	0.002	MGL	TCLEE	0.002	1
FBP 4	85Q4	-0.005	MGL	TCLEE	-0.005	1
FBP 4	86Q1	-0.001	MGL	TCLEE	-0.001	1
FBP 4	86Q3	0.00275	MGL	TCLEE	0.00275	1
FBP 4	86Q4	-0.001	MGL	TCLEE	-0.001	1
FBP 4	87Q1	-0.001	MGL	TCLEE	-0.001	1
FBP 4	87Q2	-0.001	MGL	TCLEE	-0.001	1
FBP 4	87Q3	-0.001	MGL	TCLEE	-0.001	1
FBP 4	87Q4	-0.001	MGL	TCLEE	-0.001	2
FBP 4	88Q1	-0.001	MGL	TCLEE	-0.001	2
FBP 4	88Q3	-0.001	MGL	TCLEE	-0.001	1
FBP 4	89Q1	-0.001	MGL	TCLEE	-0.001	1
FBP 4	89Q3	-0.001	MGL	TCLEE	-0.001	1
FBP 4	90Q1	-0.001	MGL	TCLEE	-0.001	1
FBP 4	90Q3	-0.001	MGL	TCLEE	-0.001	1
FBP 4	91Q1	-0.001	MGL	TCLEE	-0.001	1
FBP 4	86Q1	-1	MGL	TCOLI	-1	1
FBP 1A	84Q3	36	MGL	TDS	36	1
FBP 1A	84Q4	40	MGL	TDS	40	1
FBP 1A	87Q1	116	MGL	TDS	116	1
FBP 1A	89Q2	84	MGL	TDS	84	1
FBP 1A	91Q1	41	MGL	TDS	40.5	2
FBP 2A	84Q3	90	MGL	TDS	90	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	84Q4	68	MGL	TDS	68	1
FBP 2A	87Q1	14	MGL	TDS	14	1
FBP 2A	89Q2	24	MGL	TDS	24	1
FBP 2A	91Q1	24	MGL	TDS	24	1
FBP 3A	84Q3	46	MGL	TDS	46	1
FBP 3A	84Q4	62	MGL	TDS	62	1
FBP 3A	87Q1	36	MGL	TDS	32	2
FBP 3A	89Q2	42	MGL	TDS	42	1
FBP 3A	91Q1	9	MGL	TDS	9	1
FBP 4	87Q1	8	MGL	TDS	8	1
FBP 4	89Q2	15	MGL	TDS	15	1
FBP 4	91Q1	-1	MGL	TDS	-1	1
FBP 1A	84Q3	-5	MGL	TOC	-5	1
FBP 1A	84Q4	-5	MGL	TOC	-5	1
FBP 1A	85Q1	1.68	MGL	TOC	1.68	1
FBP 1A	85Q2	1.98	MGL	TOC	1.98	1
FBP 1A	85Q3	0.37	MGL	TOC	0.37	1
FBP 1A	85Q4	0.34	MGL	TOC	0.34	1
FBP 1A	86Q1	-1	MGL	TOC	-1	1
FBP 1A	86Q2	-1	MGL	TOC	-1	1
FBP 1A	86Q3	-1	MGL	TOC	-1	1
FBP 1A	86Q4	5.3	MGL	TOC	5.3	1
FBP 1A	87Q1	-1	MGL	TOC	-1	1
FBP 1A	87Q2	-1	MGL	TOC	-1	1
FBP 1A	87Q3	-1	MGL	TOC	-1	4
FBP 1A	87Q4	-1	MGL	TOC	-1	1
FBP 1A	88Q1	-1	MGL	TOC	-1	1
FBP 1A	89Q1	-1	MGL	TOC	-1	1
FBP 1A	89Q2	2	MGL	TOC	2	1
FBP 1A	90Q1	-1	MGL	TOC	-1	2
FBP 1A	91Q1	-1	MGL	TOC	-1	2
FBP 2A	84Q3	-5	MGL	TOC	-5	1
FBP 2A	84Q4	-5	MGL	TOC	-5	1
FBP 2A	85Q1	1.03	MGL	TOC	1.03	1
FBP 2A	85Q2	0.383	MGL	TOC	0.383	1
FBP 2A	85Q3	0.57	MGL	TOC	0.57	1
FBP 2A	85Q4	0.67	MGL	TOC	0.67	1
FBP 2A	86Q1	-1	MGL	TOC	-1	1
FBP 2A	86Q2	-1	MGL	TOC	-1	1
FBP 2A	86Q3	-1	MGL	TOC	-1	1
FBP 2A	86Q4	6	MGL	TOC	5.75	2
FBP 2A	87Q1	-1	MGL	TOC	-1	2
FBP 2A	87Q2	1	MGL	TOC	1	1
FBP 2A	87Q3	-1	MGL	TOC	-1	1
FBP 2A	87Q4	1.1	MGL	TOC	0.8	2
FBP 2A	88Q1	1	MGL	TOC	1	1
FBP 2A	89Q1	-1	MGL	TOC	-1	1
FBP 2A	89Q2	2	MGL	TOC	2	1
FBP 2A	90Q1	-1	MGL	TOC	-1	1
FBP 2A	91Q1	-1	MGL	TOC	-1	1
FBP 3A	84Q3	6	MGL	TOC	6	1
FBP 3A	84Q4	-5	MGL	TOC	-5	1
FBP 3A	85Q1	2	MGL	TOC	2	1
FBP 3A	85Q2	0.735	MGL	TOC	0.735	1
FBP 3A	85Q3	0.47	MGL	TOC	0.47	1
FBP 3A	85Q4	1.23	MGL	TOC	1.23	1
FBP 3A	86Q1	-1	MGL	TOC	-1	2
FBP 3A	86Q2	-1	MGL	TOC	-1	1
FBP 3A	86Q3	-1	MGL	TOC	-1	1
FBP 3A	86Q4	1.5	MGL	TOC	1.5	1
FBP 3A	87Q1	-1	MGL	TOC	-1	1
FBP 3A	87Q2	2	MGL	TOC	2	1
FBP 3A	87Q3	4	MGL	TOC	4	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 3A	87Q4	-1	MGL	TOC	-1	1
FBP 3A	88Q1	-1	MGL	TOC	-1	1
FBP 3A	89Q1	1.1	MGL	TOC	1.1	1
FBP 3A	89Q2	2	MGL	TOC	2	1
FBP 3A	90Q1	-1	MGL	TOC	-1	1
FBP 3A	91Q1	-1	MGL	TOC	-1	1
FBP 4	85Q1	1.65	MGL	TOC	1.65	1
FBP 4	85Q2	0.402	MGL	TOC	0.402	1
FBP 4	85Q3	0.9	MGL	TOC	0.9	1
FBP 4	85Q4	0.6	MGL	TOC	0.6	1
FBP 4	86Q1	-1	MGL	TOC	-1	1
FBP 4	86Q2	-1	MGL	TOC	-1	1
FBP 4	86Q3	-1	MGL	TOC	-1	1
FBP 4	86Q4	3.6	MGL	TOC	3.55	2
FBP 4	87Q1	-1	MGL	TOC	-1	1
FBP 4	87Q2	-1	MGL	TOC	-1	1
FBP 4	87Q3	2	MGL	TOC	2	1
FBP 4	87Q4	-1	MGL	TOC	-1	1
FBP 4	88Q1	-1	MGL	TOC	-1	1
FBP 4	89Q1	1.2	MGL	TOC	1.2	1
FBP 4	89Q2	2	MGL	TOC	2	1
FBP 4	90Q1	-1	MGL	TOC	-1	1
FBP 4	91Q1	-1	MGL	TOC	-1	1
FBP 1A	84Q3	1	PCL	TOTRAD	1	1
FBP 1A	84Q4	-1	PCL	TOTRAD	-1	1
FBP 1A	85Q1	4	PCL	TOTRAD	4	1
FBP 1A	86Q1	8	PCL	TOTRAD	8	1
FBP 1A	86Q3	5.8	PCL	TOTRAD	5.8	1
FBP 1A	86Q4	4.7	PCL	TOTRAD	4.7	1
FBP 1A	87Q1	3.2	PCL	TOTRAD	3.2	1
FBP 1A	87Q2	3.4	PCL	TOTRAD	3.4	1
FBP 1A	87Q3	1	PCL	TOTRAD	0.96667	3
FBP 1A	87Q4	1.1	PCL	TOTRAD	1.1	1
FBP 1A	88Q1	-1	PCL	TOTRAD	-1	1
FBP 1A	88Q3	1.16	PCL	TOTRAD	1.16	1
FBP 1A	89Q1	2.29	PCL	TOTRAD	2.29	1
FBP 1A	89Q2	1.7	PCL	TOTRAD	1.7	1
FBP 1A	89Q4	3.1	PCL	TOTRAD	3.1	1
FBP 1A	90Q1	3.6	PCL	TOTRAD	2.05	2
FBP 1A	90Q3	3.2	PCL	TOTRAD	3.2	1
FBP 1A	91Q1	1.1	PCL	TOTRAD	0.8	2
FBP 2A	84Q3	1.4	PCL	TOTRAD	1.4	1
FBP 2A	84Q4	-1	PCL	TOTRAD	-1	1
FBP 2A	85Q1	-1	PCL	TOTRAD	-1	1
FBP 2A	86Q1	-1	PCL	TOTRAD	-1	1
FBP 2A	86Q3	-1	PCL	TOTRAD	-1	1
FBP 2A	86Q4	-1	PCL	TOTRAD	-1	1
FBP 2A	87Q1	-1	PCL	TOTRAD	-1	1
FBP 2A	87Q2	0.8	PCL	TOTRAD	0.8	1
FBP 2A	87Q3	2.2	PCL	TOTRAD	2.2	1
FBP 2A	87Q4	1.4	PCL	TOTRAD	1.4	1
FBP 2A	88Q1	-1	PCL	TOTRAD	-1	1
FBP 2A	88Q3	-1	PCL	TOTRAD	-1	1
FBP 2A	89Q1	-1	PCL	TOTRAD	-1	1
FBP 2A	89Q2	6.05	PCL	TOTRAD	6.05	1
FBP 2A	89Q4	3.1	PCL	TOTRAD	3.1	1
FBP 2A	90Q1	20	PCL	TOTRAD	20	1
FBP 2A	90Q3	-1	PCL	TOTRAD	-1	1
FBP 2A	91Q1	-1	PCL	TOTRAD	-1	1
FBP 3A	84Q3	-1	PCL	TOTRAD	-1	1
FBP 3A	84Q4	-1	PCL	TOTRAD	-1	1
FBP 3A	85Q1	-1	PCL	TOTRAD	-1	1
FBP 3A	86Q1	2	PCL	TOTRAD	2	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 3A	86Q3	-1	PCL	TOTRAD	-1	1
FBP 3A	86Q4	-1	PCL	TOTRAD	-1	1
FBP 3A	87Q1	-1	PCL	TOTRAD	-1	1
FBP 3A	87Q2	0.6	PCL	TOTRAD	0.6	1
FBP 3A	87Q3	-1	PCL	TOTRAD	-1	1
FBP 3A	87Q4	-1	PCL	TOTRAD	-1	1
FBP 3A	88Q1	-1	PCL	TOTRAD	-1	2
FBP 3A	88Q3	-1	PCL	TOTRAD	-1	1
FBP 3A	89Q2	-1	PCL	TOTRAD	-1	1
FBP 3A	89Q4	2.1	PCL	TOTRAD	2.1	1
FBP 3A	90Q1	-1	PCL	TOTRAD	-1	1
FBP 3A	90Q3	1.3	PCL	TOTRAD	1.3	1
FBP 3A	91Q1	-1	PCL	TOTRAD	-1	1
FBP 4	85Q1	7	PCL	TOTRAD	7	1
FBP 4	85Q3	-1	PCL	TOTRAD	-1	1
FBP 4	85Q4	6	PCL	TOTRAD	6	1
FBP 4	86Q3	2.3	PCL	TOTRAD	2.3	1
FBP 4	86Q4	1.9	PCL	TOTRAD	1.9	1
FBP 4	87Q1	2.6	PCL	TOTRAD	2.4	2
FBP 4	87Q2	6.3	PCL	TOTRAD	6.3	1
FBP 4	87Q3	2.7	PCL	TOTRAD	2.7	1
FBP 4	87Q4	1.9	PCL	TOTRAD	1.9	1
FBP 4	88Q1	-1	PCL	TOTRAD	-1	1
FBP 4	88Q3	2.64	PCL	TOTRAD	2.625	2
FBP 4	89Q1	2.34	PCL	TOTRAD	2.34	1
FBP 4	89Q2	4.93	PCL	TOTRAD	4.93	1
FBP 4	89Q4	2.9	PCL	TOTRAD	2.9	1
FBP 4	90Q1	-1	PCL	TOTRAD	-1	1
FBP 4	90Q3	2.7	PCL	TOTRAD	2.7	1
FBP 4	91Q1	4.3	PCL	TOTRAD	4.3	1
FBP 1A	84Q3	0.068	MGL	TOX	0.068	1
FBP 1A	84Q4	0.011	MGL	TOX	0.011	1
FBP 1A	85Q1	0.0584	MGL	TOX	0.0584	1
FBP 1A	85Q2	0.0283	MGL	TOX	0.0283	1
FBP 1A	85Q3	0.034	MGL	TOX	0.034	1
FBP 1A	85Q4	0.036	MGL	TOX	0.036	1
FBP 1A	86Q1	0.036	MGL	TOX	0.0355	2
FBP 1A	86Q2	0.038	MGL	TOX	0.0375	2
FBP 1A	86Q3	0.035	MGL	TOX	0.0335	2
FBP 1A	86Q4	0.04	MGL	TOX	0.04	1
FBP 1A	87Q1	0.022	MGL	TOX	0.022	1
FBP 1A	87Q2	0.014	MGL	TOX	0.014	1
FBP 1A	87Q3	0.019	MGL	TOX	0.012	4
FBP 1A	87Q4	0.007	MGL	TOX	0.007	1
FBP 1A	88Q1	0.007	MGL	TOX	0.007	1
FBP 1A	88Q3	0.299	MGL	TOX	0.2915	2
FBP 1A	89Q1	0.0239	MGL	TOX	0.0239	1
FBP 1A	89Q2	-0.005	MGL	TOX	-0.005	1
FBP 1A	89Q3	0.029	MGL	TOX	0.029	1
FBP 1A	90Q1	0.01	MGL	TOX	0.009	2
FBP 1A	90Q3	0.009	MGL	TOX	0.009	1
FBP 1A	91Q1	-0.005	MGL	TOX	-0.005	2
FBP 2A	84Q3	0.071	MGL	TOX	0.071	1
FBP 2A	84Q4	0.065	MGL	TOX	0.065	1
FBP 2A	85Q1	0.2652	MGL	TOX	0.2652	1
FBP 2A	85Q2	0.33	MGL	TOX	0.312	2
FBP 2A	85Q3	0.254	MGL	TOX	0.254	1
FBP 2A	85Q4	0.241	MGL	TOX	0.241	1
FBP 2A	86Q1	0.237	MGL	TOX	0.237	1
FBP 2A	86Q2	0.168	MGL	TOX	0.1505	2
FBP 2A	86Q3	0.082	MGL	TOX	0.082	1
FBP 2A	86Q4	0.056	MGL	TOX	0.056	1
FBP 2A	87Q1	0.049	MGL	TOX	0.049	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	87Q2	0.078	MGL	TOX	0.078	1
FBP 2A	87Q3	0.185	MGL	TOX	0.1705	2
FBP 2A	87Q4	0.216	MGL	TOX	0.216	1
FBP 2A	88Q1	0.16	MGL	TOX	0.16	1
FBP 2A	88Q3	0.099	MGL	TOX	0.099	1
FBP 2A	89Q1	0.0787	MGL	TOX	0.0752	2
FBP 2A	89Q2	0.09	MGL	TOX	0.09	1
FBP 2A	89Q3	0.176	MGL	TOX	0.176	1
FBP 2A	90Q1	0.102	MGL	TOX	0.102	1
FBP 2A	90Q3	0.07	MGL	TOX	0.07	1
FBP 2A	91Q1	0.099	MGL	TOX	0.099	1
FBP 3A	84Q3	0.062	MGL	TOX	0.062	1
FBP 3A	84Q4	0.013	MGL	TOX	0.013	1
FBP 3A	85Q1	0.0118	MGL	TOX	0.0118	1
FBP 3A	85Q2	0.0158	MGL	TOX	0.0158	1
FBP 3A	85Q3	0.013	MGL	TOX	0.013	1
FBP 3A	85Q4	0.015	MGL	TOX	0.015	1
FBP 3A	86Q1	0.014	MGL	TOX	0.014	1
FBP 3A	86Q2	0.011	MGL	TOX	0.011	1
FBP 3A	86Q3	0.01	MGL	TOX	0.01	1
FBP 3A	86Q4	0.005	MGL	TOX	0.005	1
FBP 3A	87Q1	0.007	MGL	TOX	0.007	1
FBP 3A	87Q2	-0.005	MGL	TOX	-0.005	1
FBP 3A	87Q3	0.006	MGL	TOX	0.006	1
FBP 3A	87Q4	0.006	MGL	TOX	0.006	1
FBP 3A	88Q1	-0.005	MGL	TOX	-0.005	1
FBP 3A	88Q3	0.861	MGL	TOX	0.861	1
FBP 3A	89Q1	0.026	MGL	TOX	0.026	1
FBP 3A	89Q2	-0.005	MGL	TOX	-0.005	1
FBP 3A	89Q3	0.054	MGL	TOX	0.0505	2
FBP 3A	90Q1	0.01	MGL	TOX	0.01	1
FBP 3A	90Q3	0.005	MGL	TOX	0.005	1
FBP 3A	91Q1	0.011	MGL	TOX	0.011	1
FBP 4	85Q1	0.0057	MGL	TOX	0.0057	1
FBP 4	85Q2	-0.005	MGL	TOX	-0.005	1
FBP 4	85Q3	-0.005	MGL	TOX	-0.005	1
FBP 4	85Q4	0.006	MGL	TOX	0.006	1
FBP 4	86Q1	-0.005	MGL	TOX	-0.005	1
FBP 4	86Q2	0.84	MGL	TOX	0.4285	2
FBP 4	86Q3	-0.005	MGL	TOX	-0.005	1
FBP 4	86Q4	-0.005	MGL	TOX	-0.005	1
FBP 4	87Q1	-0.005	MGL	TOX	-0.005	2
FBP 4	87Q2	-0.005	MGL	TOX	-0.005	1
FBP 4	87Q3	-0.005	MGL	TOX	-0.005	1
FBP 4	87Q4	-0.005	MGL	TOX	-0.005	1
FBP 4	88Q1	-0.005	MGL	TOX	-0.005	1
FBP 4	88Q3	0.584	MGL	TOX	0.584	1
FBP 4	89Q1	-0.005	MGL	TOX	-0.005	1
FBP 4	89Q2	0.009	MGL	TOX	0.009	1
FBP 4	89Q3	0.047	MGL	TOX	0.047	1
FBP 4	90Q1	-0.005	MGL	TOX	-0.005	1
FBP 4	90Q3	-0.005	MGL	TOX	-0.005	1
FBP 4	91Q1	0.015	MGL	TOX	0.015	1
FBP 1A	89Q2	-0.05	MGL	TPHOS	-0.05	1
FBP 2A	89Q2	0.06	MGL	TPHOS	0.06	1
FBP 3A	89Q2	0.29	MGL	TPHOS	0.29	1
FBP 4	89Q2	0.22	MGL	TPHOS	0.22	1
FBP 1A	87Q1	-0.01	MGL	TPO4	-0.01	1
FBP 1A	90Q3	-0.05	MGL	TPO4	-0.05	1
FBP 1A	91Q1	-0.05	MGL	TPO4	-0.05	2
FBP 2A	87Q1	0.04	MGL	TPO4	0.04	1
FBP 2A	90Q3	-0.05	MGL	TPO4	-0.05	1
FBP 2A	91Q1	-0.05	MGL	TPO4	-0.05	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 3A	87Q1	0.03	MGL	TPO4	0.03	1
FBP 3A	90Q3	-0.05	MGL	TPO4	-0.05	1
FBP 3A	91Q1	-0.05	MGL	TPO4	-0.05	1
FBP 4	87Q1	0.02	MGL	TPO4	0.02	1
FBP 4	90Q3	-0.05	MGL	TPO4	-0.05	1
FBP 4	91Q1	-0.05	MGL	TPO4	-0.05	1
FBP 1A	85Q4	0.02	MGL	TRCLE	0.02	1
FBP 1A	86Q1	0.023	MGL	TRCLE	0.022	2
FBP 1A	86Q3	0.0224	MGL	TRCLE	0.02055	2
FBP 1A	86Q4	0.0292	MGL	TRCLE	0.0292	1
FBP 1A	87Q1	0.007	MGL	TRCLE	0.007	1
FBP 1A	87Q2	0.00735	MGL	TRCLE	0.00735	1
FBP 1A	87Q3	0.00611	MGL	TRCLE	0.00395	3
FBP 1A	87Q4	0.00501	MGL	TRCLE	0.00501	1
FBP 1A	88Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 1A	88Q3	0.009	MGL	TRCLE	0.0085	2
FBP 1A	89Q1	0.00942	MGL	TRCLE	0.00942	1
FBP 1A	89Q3	0.008	MGL	TRCLE	0.008	1
FBP 1A	90Q1	0.007	MGL	TRCLE	0.0065	2
FBP 1A	90Q3	0.008	MGL	TRCLE	0.008	1
FBP 1A	91Q1	0.006	MGL	TRCLE	0.006	2
FBP 2A	85Q4	0.098	MGL	TRCLE	0.098	1
FBP 2A	86Q1	0.105	MGL	TRCLE	0.105	1
FBP 2A	86Q3	0.0281	MGL	TRCLE	0.02625	2
FBP 2A	86Q4	0.0247	MGL	TRCLE	0.0247	1
FBP 2A	87Q1	0.0132	MGL	TRCLE	0.0132	1
FBP 2A	87Q2	0.0457	MGL	TRCLE	0.0457	1
FBP 2A	87Q3	-0.001	MGL	TRCLE	-0.001	1
FBP 2A	87Q4	0.0526	MGL	TRCLE	0.0526	1
FBP 2A	88Q1	0.0608	MGL	TRCLE	0.0608	1
FBP 2A	88Q3	0.076	MGL	TRCLE	0.076	1
FBP 2A	89Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 2A	89Q3	0.125	MGL	TRCLE	0.125	1
FBP 2A	90Q1	0.048	MGL	TRCLE	0.048	1
FBP 2A	90Q3	0.065	MGL	TRCLE	0.065	1
FBP 2A	91Q1	0.033	MGL	TRCLE	0.033	1
FBP 3A	85Q4	-0.005	MGL	TRCLE	-0.005	1
FBP 3A	86Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	86Q3	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	86Q4	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	87Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	87Q2	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	87Q3	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	87Q4	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	88Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	88Q3	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	89Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	89Q3	-0.001	MGL	TRCLE	-0.001	2
FBP 3A	90Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	90Q3	-0.001	MGL	TRCLE	-0.001	1
FBP 3A	91Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 4	85Q4	-0.005	MGL	TRCLE	-0.005	1
FBP 4	86Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 4	86Q3	-0.001	MGL	TRCLE	-0.001	1
FBP 4	86Q4	-0.001	MGL	TRCLE	-0.001	1
FBP 4	87Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 4	87Q2	-0.001	MGL	TRCLE	-0.001	1
FBP 4	87Q3	-0.001	MGL	TRCLE	-0.001	1
FBP 4	87Q4	-0.001	MGL	TRCLE	-0.001	2
FBP 4	88Q1	-0.001	MGL	TRCLE	-0.001	2
FBP 4	88Q3	-0.001	MGL	TRCLE	-0.001	1
FBP 4	89Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 4	89Q3	-0.001	MGL	TRCLE	-0.001	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 4	90Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 4	90Q3	-0.001	MGL	TRCLE	-0.001	1
FBP 4	91Q1	-0.001	MGL	TRCLE	-0.001	1
FBP 1A	86Q2	0.01678	PCML	TRITIU	0.01678	1
FBP 1A	87Q1	11.1	PCML	TRITIU	11.1	1
FBP 1A	87Q2	9.9	PCML	TRITIU	9.9	1
FBP 1A	87Q3	8.7	PCML	TRITIU	8.3	2
FBP 1A	87Q4	8	PCML	TRITIU	8	1
FBP 1A	88Q1	7.7	PCML	TRITIU	7.7	1
FBP 1A	89Q2	6.94	PCML	TRITIU	6.94	1
FBP 1A	91Q1	5.66	PCML	TRITIU	5.655	2
FBP 2A	86Q2	0.01052	PCML	TRITIU	0.01052	1
FBP 2A	87Q1	8.15	PCML	TRITIU	8.15	1
FBP 2A	87Q2	7.95	PCML	TRITIU	7.95	1
FBP 2A	87Q3	8	PCML	TRITIU	8	1
FBP 2A	87Q4	8.1	PCML	TRITIU	8.1	1
FBP 2A	88Q1	7.3	PCML	TRITIU	7.3	1
FBP 2A	89Q2	6.96	PCML	TRITIU	6.96	1
FBP 2A	91Q1	6.03	PCML	TRITIU	3.063	2
FBP 3A	86Q2	0.00637	PCML	TRITIU	0.00637	1
FBP 3A	87Q1	5.83	PCML	TRITIU	5.83	1
FBP 3A	87Q2	5.47	PCML	TRITIU	5.47	1
FBP 3A	87Q3	5.8	PCML	TRITIU	5.8	1
FBP 3A	87Q4	5.1	PCML	TRITIU	5.1	1
FBP 3A	88Q1	5.4	PCML	TRITIU	5.4	2
FBP 3A	89Q2	4.36	PCML	TRITIU	4.36	1
FBP 3A	91Q1	4.48	PCML	TRITIU	4.48	1
FBP 4	86Q2	0.00958	PCML	TRITIU	0.00958	1
FBP 4	87Q1	8.28	PCML	TRITIU	8.095	2
FBP 4	87Q2	9.26	PCML	TRITIU	9.26	1
FBP 4	87Q3	7.4	PCML	TRITIU	7.4	1
FBP 4	87Q4	7.3	PCML	TRITIU	7.3	1
FBP 4	88Q1	6.1	PCML	TRITIU	6.1	1
FBP 4	89Q2	5.01	PCML	TRITIU	5.01	1
FBP 4	91Q1	5.94	PCML	TRITIU	5.94	1
FBP 1A	84Q3	-1	TU	TUR	-1	1
FBP 1A	84Q4	5.6	TU	TUR	5.6	1
FBP 1A	85Q1	0.025	TU	TUR	0.025	1
FBP 2A	84Q3	0.82	TU	TUR	0.82	1
FBP 2A	84Q4	6.5	TU	TUR	6.5	1
FBP 2A	85Q1	23	TU	TUR	23	1
FBP 3A	84Q3	0.8	TU	TUR	0.8	1
FBP 3A	84Q4	11	TU	TUR	11	1
FBP 3A	85Q1	23.5	TU	TUR	23.5	1
FBP 4	85Q1	8.5	TU	TUR	8.5	1
FBP 4	85Q3	3.6	TU	TUR	3.6	1
FBP 4	85Q4	7.3	TU	TUR	6.95	2
FBP 4	86Q1	0.21	TU	TUR	0.21	1
FBP 1A	84Q4	-0.001	MGL	TXPHEN	-0.001	1
FBP 1A	85Q1	-0.001	MGL	TXPHEN	-0.001	2
FBP 1A	91Q1	-0.00024	MGL	TXPHEN	-0.00024	2
FBP 2A	84Q4	-0.001	MGL	TXPHEN	-0.001	1
FBP 2A	85Q1	-0.001	MGL	TXPHEN	-0.001	1
FBP 2A	91Q1	-0.00024	MGL	TXPHEN	-0.00024	1
FBP 3A	84Q4	-0.001	MGL	TXPHEN	-0.001	1
FBP 3A	85Q1	-0.001	MGL	TXPHEN	-0.001	1
FBP 3A	91Q1	-0.00024	MGL	TXPHEN	-0.00024	1
FBP 4	85Q1	-0.001	MGL	TXPHEN	-0.001	1
FBP 4	85Q3	-0.001	MGL	TXPHEN	-0.001	1
FBP 4	85Q4	-0.001	MGL	TXPHEN	-0.001	2
FBP 4	86Q1	-0.001	MGL	TXPHEN	-0.001	1
FBP 4	91Q1	-0.00024	MGL	TXPHEN	-0.00024	1
FBP 1A	85Q4	-0.005	MGL	T12DCE	-0.005	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 1A	87Q3	-0.001	MGL	T12DCE	-0.001	1
FBP 1A	89Q3	-0.001	MGL	T12DCE	-0.001	1
FBP 1A	90Q1	-0.001	MGL	T12DCE	-0.001	2
FBP 2A	85Q4	-0.005	MGL	T12DCE	-0.005	1
FBP 2A	89Q3	-0.001	MGL	T12DCE	-0.001	1
FBP 2A	90Q1	-0.001	MGL	T12DCE	-0.001	1
FBP 3A	85Q4	-0.005	MGL	T12DCE	-0.005	1
FBP 3A	89Q3	-0.001	MGL	T12DCE	-0.001	2
FBP 3A	90Q1	-0.001	MGL	T12DCE	-0.001	1
FBP 4	85Q4	-0.005	MGL	T12DCE	-0.005	1
FBP 4	89Q3	-0.001	MGL	T12DCE	-0.001	1
FBP 4	90Q1	-0.001	MGL	T12DCE	-0.001	1
FBP 1A	87Q3	-0.001	MGL	T13DCP	-0.001	1
FBP 1A	86Q3	3.28	PCL	U	3.28	1
FBP 1A	89Q3	-1	MGL	U	-1	1
FBP 1A	90Q1	-1	MGL	U	-1	2
FBP 2A	86Q3	2.46	PCL	U	2.46	1
FBP 2A	89Q3	-1	MGL	U	-1	1
FBP 2A	90Q1	-1	MGL	U	-1	1
FBP 3A	86Q3	2.46	PCL	U	2.46	1
FBP 3A	89Q3	-1	MGL	U	-1	2
FBP 3A	90Q1	-1	MGL	U	-1	1
FBP 4	86Q3	30.38	PCL	U	30.38	1
FBP 4	89Q3	-1	MGL	U	-1	1
FBP 4	90Q1	-1	MGL	U	-1	1
FBP 1A	86Q2	14.04	PCL	UPU	7.02	2
FBP 4	86Q2	206.32	PCL	UPU	115.91	2
FBP 1A	89Q3	-0.1	PCL	U235	-0.1	1
FBP 2A	89Q3	-0.05	PCL	U235	-0.05	1
FBP 3A	89Q3	-0.1	PCL	U235	-0.1	1
FBP 4	89Q3	-0.1	PCL	U235	-0.1	1
FBP 1A	89Q3	-0.1	PCL	U238	-0.1	1
FBP 2A	89Q3	-0.05	PCL	U238	-0.05	1
FBP 3A	89Q3	-0.1	PCL	U238	-0.1	1
FBP 4	89Q3	0.52	PCL	U238	0.52	1
FBP 1A	89Q3	-0.1	PCL	U3334	-0.1	1
FBP 2A	89Q3	-0.05	PCL	U3334	-0.05	1
FBP 3A	89Q3	-0.1	PCL	U3334	-0.1	1
FBP 4	89Q3	0.19	PCL	U3334	0.19	1
FBP 1A	84Q3	0.012	MGL	ZN	0.011	2
FBP 1A	84Q4	0.037	MGL	ZN	0.037	1
FBP 2A	84Q3	0.015	MGL	ZN	0.015	1
FBP 2A	84Q4	0.015	MGL	ZN	0.015	1
FBP 3A	84Q3	0.048	MGL	ZN	0.048	1
FBP 3A	84Q4	0.023	MGL	ZN	0.023	1
FBP 1A	85Q4	-0.005	MGL	11DCE	-0.005	1
FBP 1A	87Q3	-0.001	MGL	11DCE	-0.001	1
FBP 1A	89Q3	-0.001	MGL	11DCE	-0.001	1
FBP 1A	90Q1	-0.001	MGL	11DCE	-0.001	2
FBP 2A	85Q4	-0.005	MGL	11DCE	-0.005	1
FBP 2A	89Q3	-0.001	MGL	11DCE	-0.001	1
FBP 2A	90Q1	-0.001	MGL	11DCE	-0.001	1
FBP 3A	85Q4	-0.005	MGL	11DCE	-0.005	1
FBP 3A	89Q3	-0.001	MGL	11DCE	-0.001	2
FBP 3A	90Q1	-0.001	MGL	11DCE	-0.001	1
FBP 4	85Q4	-0.005	MGL	11DCE	-0.005	1
FBP 4	89Q3	-0.001	MGL	11DCE	-0.001	1
FBP 4	90Q1	-0.001	MGL	11DCE	-0.001	1
FBP 1A	85Q4	-0.005	MGL	11DCLE	-0.005	1
FBP 1A	87Q3	-0.001	MGL	11DCLE	-0.001	1
FBP 1A	89Q3	-0.001	MGL	11DCLE	-0.001	1
FBP 1A	90Q1	-0.001	MGL	11DCLE	-0.001	2
FBP 2A	85Q4	-0.005	MGL	11DCLE	-0.005	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 2A	89Q3	-0.001	MGL	11DCLE	-0.001	1
FBP 2A	90Q1	-0.001	MGL	11DCLE	-0.001	1
FBP 3A	85Q4	-0.005	MGL	11DCLE	-0.005	1
FBP 3A	89Q3	-0.001	MGL	11DCLE	-0.001	2
FBP 3A	90Q1	-0.001	MGL	11DCLE	-0.001	1
FBP 4	85Q4	-0.005	MGL	11DCLE	-0.005	1
FBP 4	89Q3	-0.001	MGL	11DCLE	-0.001	1
FBP 4	90Q1	-0.001	MGL	11DCLE	-0.001	1
FBP 1A	85Q4	-0.005	MGL	111TCE	-0.005	1
FBP 1A	86Q3	-0.001	MGL	111TCE	-0.001	2
FBP 1A	86Q4	-0.001	MGL	111TCE	-0.001	1
FBP 1A	87Q1	-0.001	MGL	111TCE	-0.001	1
FBP 1A	87Q2	-0.001	MGL	111TCE	-0.001	1
FBP 1A	87Q3	-0.001	MGL	111TCE	-0.001	3
FBP 1A	87Q4	-0.001	MGL	111TCE	-0.001	1
FBP 1A	88Q1	-0.001	MGL	111TCE	-0.001	1
FBP 1A	88Q3	-0.001	MGL	111TCE	-0.001	2
FBP 1A	89Q1	-0.001	MGL	111TCE	-0.001	1
FBP 1A	89Q3	-0.001	MGL	111TCE	-0.001	1
FBP 1A	90Q1	-0.001	MGL	111TCE	-0.001	2
FBP 1A	90Q3	-0.001	MGL	111TCE	-0.001	1
FBP 1A	91Q1	-0.001	MGL	111TCE	-0.001	2
FBP 2A	85Q4	-0.005	MGL	111TCE	-0.005	1
FBP 2A	86Q3	-0.001	MGL	111TCE	-0.001	2
FBP 2A	86Q4	-0.001	MGL	111TCE	-0.001	1
FBP 2A	87Q1	-0.001	MGL	111TCE	-0.001	1
FBP 2A	87Q2	-0.001	MGL	111TCE	-0.001	1
FBP 2A	87Q3	-0.001	MGL	111TCE	-0.001	1
FBP 2A	87Q4	-0.001	MGL	111TCE	-0.001	1
FBP 2A	88Q1	-0.001	MGL	111TCE	-0.001	1
FBP 2A	88Q3	-0.001	MGL	111TCE	-0.001	1
FBP 2A	89Q1	-0.001	MGL	111TCE	-0.001	1
FBP 2A	89Q3	-0.001	MGL	111TCE	-0.001	1
FBP 2A	90Q1	-0.001	MGL	111TCE	-0.001	1
FBP 2A	90Q3	-0.001	MGL	111TCE	-0.001	1
FBP 2A	91Q1	-0.001	MGL	111TCE	-0.001	1
FBP 3A	85Q4	-0.005	MGL	111TCE	-0.005	1
FBP 3A	86Q3	-0.001	MGL	111TCE	-0.001	1
FBP 3A	86Q4	-0.001	MGL	111TCE	-0.001	1
FBP 3A	87Q1	-0.001	MGL	111TCE	-0.001	1
FBP 3A	87Q2	-0.001	MGL	111TCE	-0.001	1
FBP 3A	87Q3	-0.001	MGL	111TCE	-0.001	1
FBP 3A	87Q4	-0.001	MGL	111TCE	-0.001	1
FBP 3A	88Q1	-0.001	MGL	111TCE	-0.001	1
FBP 3A	88Q3	-0.001	MGL	111TCE	-0.001	1
FBP 3A	89Q1	-0.001	MGL	111TCE	-0.001	1
FBP 3A	89Q3	-0.001	MGL	111TCE	-0.001	2
FBP 3A	90Q1	-0.001	MGL	111TCE	-0.001	1
FBP 3A	90Q3	-0.001	MGL	111TCE	-0.001	1
FBP 3A	91Q1	-0.001	MGL	111TCE	-0.001	1
FBP 4	85Q4	-0.005	MGL	111TCE	-0.005	1
FBP 4	86Q3	-0.001	MGL	111TCE	-0.001	1
FBP 4	86Q4	-0.001	MGL	111TCE	-0.001	1
FBP 4	87Q1	-0.001	MGL	111TCE	-0.001	1
FBP 4	87Q2	-0.001	MGL	111TCE	-0.001	1
FBP 4	87Q3	-0.001	MGL	111TCE	-0.001	1
FBP 4	87Q4	-0.001	MGL	111TCE	-0.001	2
FBP 4	88Q1	-0.001	MGL	111TCE	-0.001	2
FBP 4	88Q3	-0.001	MGL	111TCE	-0.001	1
FBP 4	89Q1	-0.001	MGL	111TCE	-0.001	1
FBP 4	89Q3	-0.001	MGL	111TCE	-0.001	1
FBP 4	90Q1	-0.001	MGL	111TCE	-0.001	1
FBP 4	90Q3	-0.001	MGL	111TCE	-0.001	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 4	91Q1	-0.001	MGL	111TCE	-0.001	1
FBP 1A	85Q1	-0.005	MGL	112TCE	-0.005	1
FBP 1A	87Q3	-0.001	MGL	112TCE	-0.001	1
FBP 1A	89Q3	-0.001	MGL	112TCE	-0.001	1
FBP 1A	90Q1	-0.001	MGL	112TCE	-0.001	2
FBP 2A	85Q4	-0.005	MGL	112TCE	-0.005	1
FBP 2A	89Q3	-0.001	MGL	112TCE	-0.001	1
FBP 2A	90Q1	-0.001	MGL	112TCE	-0.001	1
FBP 3A	85Q4	-0.005	MGL	112TCE	-0.005	1
FBP 3A	89Q3	-0.001	MGL	112TCE	-0.001	2
FBP 3A	90Q1	-0.001	MGL	112TCE	-0.001	1
FBP 4	85Q4	-0.005	MGL	112TCE	-0.005	1
FBP 4	89Q3	-0.001	MGL	112TCE	-0.001	1
FBP 4	90Q1	-0.001	MGL	112TCE	-0.001	1
FBP 1A	85Q4	0.045	MGL	12DCD4	0.045	1
FBP 2A	85Q4	0.051	MGL	12DCD4	0.051	1
FBP 3A	85Q4	0.05	MGL	12DCD4	0.05	1
FBP 4	85Q4	0.052	MGL	12DCD4	0.052	1
FBP 1A	85Q4	-0.001	MGL	12DCLE	-0.001	1
FBP 1A	87Q3	-0.001	MGL	12DCLE	-0.001	1
FBP 1A	89Q3	-0.001	MGL	12DCLE	-0.001	1
FBP 1A	90Q1	-0.001	MGL	12DCLE	-0.001	2
FBP 2A	85Q4	-0.001	MGL	12DCLE	-0.001	1
FBP 2A	89Q3	-0.001	MGL	12DCLE	-0.001	1
FBP 2A	90Q1	-0.001	MGL	12DCLE	-0.001	1
FBP 3A	85Q4	-0.001	MGL	12DCLE	-0.001	1
FBP 3A	89Q3	-0.001	MGL	12DCLE	-0.001	2
FBP 3A	90Q1	-0.001	MGL	12DCLE	-0.001	1
FBP 4	85Q4	-0.001	MGL	12DCLE	-0.001	1
FBP 4	89Q3	-0.001	MGL	12DCLE	-0.001	1
FBP 4	90Q1	-0.001	MGL	12DCLE	-0.001	1
FBP 1A	85Q4	-0.01	MGL	12DCLP	-0.01	1
FBP 1A	87Q3	-0.001	MGL	12DCLP	-0.001	1
FBP 1A	89Q3	-0.001	MGL	12DCLP	-0.001	1
FBP 1A	90Q1	-0.001	MGL	12DCLP	-0.001	2
FBP 2A	85Q4	-0.01	MGL	12DCLP	-0.01	1
FBP 2A	89Q3	-0.001	MGL	12DCLP	-0.001	1
FBP 2A	90Q1	-0.001	MGL	12DCLP	-0.001	1
FBP 3A	85Q4	-0.01	MGL	12DCLP	-0.01	1
FBP 3A	89Q3	-0.001	MGL	12DCLP	-0.001	2
FBP 3A	90Q1	-0.001	MGL	12DCLP	-0.001	1
FBP 4	85Q4	-0.01	MGL	12DCLP	-0.01	1
FBP 4	89Q3	-0.001	MGL	12DCLP	-0.001	1
FBP 4	90Q1	-0.001	MGL	12DCLP	-0.001	1
FBP 1A	85Q4	-0.005	MGL	13DCP	-0.005	1
FBP 2A	85Q4	-0.005	MGL	13DCP	-0.005	1
FBP 3A	85Q4	-0.005	MGL	13DCP	-0.005	1
FBP 4	85Q4	-0.005	MGL	13DCP	-0.005	1
FBP 1A	89Q3	-0.001	MGL	13DCPC	-0.001	1
FBP 1A	90Q1	-0.001	MGL	13DCPC	-0.001	2
FBP 2A	89Q3	-0.001	MGL	13DCPC	-0.001	1
FBP 2A	90Q1	-0.001	MGL	13DCPC	-0.001	1
FBP 3A	89Q3	-0.001	MGL	13DCPC	-0.001	2
FBP 3A	90Q1	-0.001	MGL	13DCPC	-0.001	1
FBP 4	89Q3	-0.001	MGL	13DCPC	-0.001	1
FBP 4	90Q1	-0.001	MGL	13DCPC	-0.001	1
FBP 1A	89Q3	-0.001	MGL	13DCPT	-0.001	1
FBP 1A	90Q1	-0.001	MGL	13DCPT	-0.001	2
FBP 2A	89Q3	-0.001	MGL	13DCPT	-0.001	1
FBP 2A	90Q1	-0.001	MGL	13DCPT	-0.001	1
FBP 3A	89Q3	-0.001	MGL	13DCPT	-0.001	2
FBP 3A	90Q1	-0.001	MGL	13DCPT	-0.001	1
FBP 4	89Q3	-0.001	MGL	13DCPT	-0.001	1

DATA RETRIEVED 7/2/91

WELL	QTR	MAXIMUM RESULT	UNITS	TESTNAME	MEAN RESULT	# OBS
FBP 4	90Q1	-0.001	MGL	13DCPT	-0.001	1
FBP 1A	85Q4	-0.01	MGL	2CLEVE	-0.01	1
FBP 1A	87Q3	-0.001	MGL	2CLEVE	-0.001	1
FBP 1A	89Q3	-0.001	MGL	2CLEVE	-0.001	1
FBP 1A	90Q1	-0.001	MGL	2CLEVE	-0.001	2
FBP 2A	85Q4	-0.01	MGL	2CLEVE	-0.01	1
FBP 2A	89Q3	-0.001	MGL	2CLEVE	-0.001	1
FBP 2A	90Q1	-0.001	MGL	2CLEVE	-0.001	1
FBP 3A	85Q4	-0.01	MGL	2CLEVE	-0.01	1
FBP 3A	89Q3	-0.001	MGL	2CLEVE	-0.001	2
FBP 3A	90Q1	-0.001	MGL	2CLEVE	-0.001	1
FBP 4	85Q4	-0.01	MGL	2CLEVE	-0.01	1
FBP 4	89Q3	-0.001	MGL	2CLEVE	-0.001	1
FBP 4	90Q1	-0.001	MGL	2CLEVE	-0.001	1
FBP 1A	84Q4	-0.02	MGL	24D	-0.02	1
FBP 1A	85Q1	-0.02	MGL	24D	-0.02	1
FBP 1A	91Q1	-0.0003	MGL	24D	-0.0003	2
FBP 2A	84Q4	-0.02	MGL	24D	-0.02	1
FBP 2A	85Q1	-0.02	MGL	24D	-0.02	1
FBP 2A	91Q1	-0.0003	MGL	24D	-0.0003	1
FBP 3A	84Q4	-0.02	MGL	24D	-0.02	2
FBP 3A	85Q1	-0.02	MGL	24D	-0.02	1
FBP 3A	91Q1	-0.0003	MGL	24D	-0.0003	1
FBP 4	85Q1	-0.02	MGL	24D	-0.02	1
FBP 4	85Q3	-0.02	MGL	24D	-0.02	1
FBP 4	85Q4	-0.02	MGL	24D	-0.02	1
FBP 4	86Q1	-0.02	MGL	24D	-0.02	1
FBP 4	91Q1	-0.0003	MGL	24D	-0.0003	1

APPENDIX C
FIELD NOTES
AND
GEOLOGIC LOGS

3/12/91

F-Area Railroad Crosstie Site

Technical Oversight: Charles B. Travis, PE, PG;

Sampling Assistant: Sean Asquith

Company: Sirrine Environmental Consultants

Sampling Station: FRT-1-HP, soil boring, split spoon
samples. SRS Coordinates: (Preliminary) -

N 79,777.44; E 50,408.41

Preliminary Elevation: 284.2

Reference Point: Ground Surface; Ditch/dirt road
Station Established 3/12/91

Sample Information:

Sample ID	Depth	Date	Time	Sampler	Comments	T _h
FRT-1HP-1	0-1.5	3/12/91	1400	SWA	0" ppm mOVA, 3" 5"	
FRT-1HP-2	1.5-3.0	3/12/91	1415	CBZ	0" ppm mOVA, 3"	
FRT-1HP-3	3.0-4.5	3/12/91	1440	SWA	0" ppm mOVA, 1 3/8"	1
FRT-1HP-4	4.5-6.0	3/12/91	1520	SWA	0" ppm mOVA, 3" 0"	
FRT-1HP-5	10.0-11.5	3/12/91	1550	SWA	0" ppm mOVA, 3"	
FRT-1HP-6	15.0-16.5	3/12/91	1615	SWA	0" ppm mOVA, 3"	
FRT-1HP-7	20.0-21.5	3/12/91	1650	SWA	0" ppm mOVA, 3"	
FRT-1HP-TB		3/13/91	1150	SWA	TRIP Blank (Prepared by Lab)	

3/12/91 Dai

0830 Received
available0900 Arrived
Driller;The ga
0930 Meeting
data an1030 Rig on
Boring
spoonSame ga
does not
radio1100 Steam
for auger1245 Sub not
about sub

Program

1310 Graves a
examined

1320 Mark

1335 Bruce r

spma the

* 1400 Began to
Screen
on OV;

1410 Mark

* 1415 Push s
background* 1440 Push to
at 144
inches

3/12/91 Daily Activities Report

- 0830 Received Telecom from Dan Wells that drill rig is available, proceed to site.
- 0900 Arrive Well Bldg, Begin assembling sampling gear, Driller, James Smith, steam cleaning augers outside the gate to F-Area Crisette site.
- 0930 Meeting with Janelle Janssen, re: format for sample data and Daily Activities, etc.
- 1030 Rig on location of first sampling station, soil Boring FRT-1-HP. We plan to use 3 inch split spoon for near-surface soil samples because of large quantity of sample required, but James does not have a sub to adapt to 3 inch spoon. I radio Dan Wells - he said Carl will bring one out.
- 1100 Steam cleaner on site, boom up, setting up "horses" for augers.
- 1245 Sub not yet on site; contacted Janelle Janssen by radio. Asked about substituting hand auger for 3 inch split spoon - not in Program Plan. She contacted Graves. Bruce Kristianson of Graves arrived site with sample catchers at 1310, examined the split spoon - dpt site to get sub.
- 1320 Mark Jones, WSRC, visits site 1320.
- 1335 Bruce returns site 1335 with sub for 3 inch split spoon had to file threads to get it to make up.
- * 1400 Begin to push 1st sample at 1400. Volat. & organic screening of sample at background - Appn on OVA, FRT-1HP-1, 0 to 1.5 ft.
- 1410 Mark Jones dpt site at 1410
- * 1415 Push second sample at 1415; OVA reading at background. Samples 1 & 2 with 3" split spoon.
- * 1440 Push third sample - with SPT - standard split spoon at 1440. Quartz cobble in bit - slightly less than 18 inches. Sample. Sample volume very small with

3/12/91

2 inch split span (1 7/8" ID); Unable to fill bottles from lab. Elected to use 3" split span on remaining samples. This is more time consuming, especially with only one drive head, and it requiring wrenches because of bad threads. Also used wrenches each time.

* 1520 Pushed Sample FRT-1HP-4 at 1520.

* 1550 Pushed Sample FRT-1HP-5; 10 to 11.5 ft at 1550.
Contact from sand to clay at ~11.0 ft.

* 1615 Push Sample FRT-1HP-6 at 1615, 15.0 to 16.5 ft

* 1650 Push Sample FRT-1HP-7 at 1650, 20.0 to 21.5 ft

Total depth of exploration: 21.5 ft; Collect 7 samples (6 @ 3" split span; 1 @ 2" split span)

Auger to 20 ft. Sean collected a replicate

Appendix IX BNA at Sample 4. Sean and I check samples, tape labels, repack samples, lock gate and

1800 depart for Well Bldg at 1800. We unload truck, lock

1830 samples in cage, dpt SR5 at 1830.

3/13/91 Daily Activities Report

0645 Meet Sean Asquith and C.B. Travis, at 0645 - proceed to site.

0700 Heavy rain at site, meet Dan Wells at Well Bldg 0730. Janelle Janssen notified by Graves Well Drilling that Graves prefers to not work in the rain. Janelle said it is Graves' call.

Janelle said Tom Gaughn is making shipping arrangements for samples. Telecom Tom Gaughn 0830. Discussed shipping arrangements.

0910 Tom called back 0910, he will bring shipping order to Well Bldg

0920 Talked to Traci Biecker and Janelle Janssen and concluded that I should take samples off-site and ship them

Fill bottles
on on
assuming,
requiring
15000

myself rather than
leave them at shipping
& receiving for them to
ship.

930 Sean prepare chain of
custody

955 Pack samples w/ bubble
wrap

1030 Telecom Tom Gaughn re: final arrangements for
shipping samples to Lab. He has a runner handcarrying
shipping documents around for signatures - will deliver to
Sean at Well Bldg.

1150 Finished packing samples.
Enclosed 140mL VOA
Trip Blank in the shipping
cooler. Wait for
Tom Gaughn to come
by with the shipping
order.

1200 Lunch

1215 Tom Gaughn brought
by the shipping order

1245 Lu Well Building

1250 Arr Shipping

Called HP Bobby Sims.
He said he would be here
in about 10 minutes

1335 Lu Shipping

1410 Arr office

Leave cooler with Melare
Davenportfield to ship.

1815 Shipped samples Fed-X

ft at 1550.

15.0 to 16.5 ft
0.2 to 1.5 ft

Collect
"split span")
silicate

and I check
gate and
load truck, lock

received to site
by 0730. Janelle
Graves prefers
Graves call.
arrangements for
shipping arrangements
to Well Bldg.

and
added
samples

3/14/91

F-Area Railroad Crosstie Site

Technical Oversight: Charles D. Travis, PE, PG

Sampling Assistant: Sean W. Asquith

Company: Sirrine Environmental Consultants

Sampling Station: FRT-5HP, Soil Boring - Split Spoon;
Ground water sampling station - Hydropunch

Preliminary SRS Coordinates: N 79, 82300, E 50, 701.78

Preliminary Elevation: 295.5

Reference Point: Ground Surface, wooded plateau

Station Established 3/14/91

SAMPLE INFORMATION:

Sample ID	Depth	Date	Time	Sampler	Comments
FRT-5HP-1	0.0 to 1.5	3/14/91	0920	SWA	0 ppm on HNU
FRT-5HP-2	1.5 to 3.0	3/14/91	0950	SWA	0 ppm on HNU
FRT-5HP-3	3.0 to 4.5	3/14/91	1010	SWA	0 ppm on HNU
FRT-5HP-4	4.5 to 6.0	3/14/91	1040	SWA	0 ppm on HNU
FRT-5HP-5	10.0 to 11.5	3/14/91	1115	SWA	0 ppm on HNU
FRT-5HP-6	15.0 to 16.5	3/14/91	1145	SWA	0 ppm on HNU
FRT-5HP-7	20.0 to 21.5	3/14/91	1210	SWA	0 ppm on HNU
FRT-5HP-TB		3/14/91	1245	SWA	TRAP Blank (Prepared by Lab)

3/14/91

0650 M.

0700 tr

160

Rai

0800 W.

27

ste

0900 vf

* 0920 f.

S.

* 0950 P.

C.

W.

* 1010 P.

P.

* 1040 P.

P.

* 1115 Avg

* 1145 Avg

* 1210 Avg

T.

1215 W.

C.

F.

d.

W.

27

m.

1315 S

t

v

1345 t

t

3/14/91 Daily Activities Report

- PG 0650 Meeting Sircine Office - CBT + SWA. Load equipment on
 0700 truck. Dpt for SR5 0700. Arrive Well Bldg 0735
 nts load remaining equipment, obtain Key for Gate to
 Railroad Crosstie Area. Fill containers with D.I. rinse
 split spoon; 0800 water, dpt for site at 0800. Arrive site 0810, set up
 punch at sampling station FRT-5HP. James and crew
 0800 steam clean augers, etc. at station FRT-1HP, set
 up rig at 5th FRT-5HP at 0800, ready to sample.
 plateau * 0920 Push first sample, FRT-5HP-1 at 0920. Decon
 Sampling eqpt., pack samples (SWA), prepare to sample
 * 0950 Push Sample FRT-5HP-2 at 0950. Large cobble
 (50mm) in bit, resulting in partial sample. However,
 with 3" split spoon, sample sufficient.
 * 1010 Push Sample FRT-5HP-3 at 1010, 3.0 to 4.5 ft. Again
 partial sample.
 * 1040 Push Sample FRT-5HP-4 at 1040, 4.5 to 6.0 ft.
 * 1115 Auger to 10.0 ft and push sample FRT-5HP-5, 10.0 to 11.5 ft
 * 1145 Auger to 15.0 ft and push sample FRT-5HP-6, 15.0 to 16.5 ft
 * 1210 Auger to 20.0 ft and push sample FRT-5HP-7, last soil sample
 this station, from 20.0 to 21.5 ft. James then
 1215 began augering to water table at 1215,
 CBT attempts to check water level in wells
 FBP-3A and 2A. Old style well with small
 diameter drop pipe; Water level indicator
 will not fit inside. CBT dpt for Well Bldg
 at 1245 for different water level indicator,
 more D.I. water, etc.
 1315 Sean got together bottles
 for water sampling. Cleaned
 up after soil sampling.
 1345 1245 Decon Hydro-punch and
 trailer.

3/14/91, (continued)

	C.B.T. review well data with Bob Hunter. Ascertain That wells FBP-2A and 3A may not be water table wells based on screen settings. Return to	1715 Dpt.
1350	site at 1350 with second water level indicator - James augering at 70 ft. Cuttings moist, but not saturated. Second water level indicator still too large to fit drop pipes on wells FBP-2A+3A. C.B.T. radio R. Hunter. Suggest augering until saturated cuttings noted, Then clean inside of augers with decontaminated 3" split spoon and checking for water inside the augers with the water level indicator. Noted color change in auger cuttings at ~82'. Cuttings progressively damper but not saturated. Hunter concurred. Noted drilling change at 85 ft, cuttings damp, and no more augers. Tripped in	0650 CB to 0730 We. 0730 dri 12, dee, beki Ora The Sea
1500	3" split spoon at 1500. Split spoon at bottom of	
1515	auger at 1515; perhaps 3" fill inside auger. Push 24", then Trip out.	0800 sa sc Lab
1520	Sean Calibrate pH meter with 7 and 4 buffers	cb, a CBT
1525	Tripped split spoon out at 1525, rods and sample dry. No reading on water level indicator. James contacts Graves via radio. Bruce advises James to pull out 40 ft of augers and dig it off until tomorrow. C.B.T.	Jan 0850 Avege 0900 bac dri
1535	advise Dan Wells via radio at 1535. SNA repacks hydropunch. Reload gear on Truck, reconcile Subcontractor expense record with driller, dpt site for Well Bldg at 1605. Off load Truck, pack samples, refill DI water containers, etc	0920 Add dri/ vnti to c at
1645	Sean fill-out chart - at - caseody -	Hy an
1710	Leave cooler of samples locked in cage at well building	pas to

no Ascentain
to water table.
turn to
indicator-

moist, but
icator still
OP-2A+3A.
until saturated
ors with
cking for
ter level

ger cuttings
riper but not
ig change at
Tripped in
bottom of
auger. Push

water
After S

1 sample dry.
nes contacts
to pull out
narrow. CBT
SWA repacks
subcontractor
Well Bldg at
DI Water

- at -

locked
no

with custody seal on cooler.
1715 Dpt SRS 1715

3/15/91 Daily Activities Report (FRT-SHP)

0650 CBT meet SWA 0650, load truck. Take two vehicles
to facilitate sample handling, etc. Meet James at
Well Bldg, 0730. Janelle Martin, Telecom Tom Saughan
0730 to discuss water level. Program Plan only calls for
drilling to 100 ft, but screens in FBQ-2A+3A are
122 ft below ground level. Tom said to drill as
deep as necessary. 1988 water levels about 101 ft
below ground level. Tom is preparing a shipping
Order for samples. He requests that Sean hand carry
The shipping order to Tracy Bittler for signature.
Sean contacts Tracy- she will not be available after noon
0800 so Sean dpt Well Bldg 0800 to meet Tom. CBT Telecom Western
Lab to confirm they receive samples on Saturday. They
cb, and will be expecting a FedEx shipment tomorrow.
CBT dpt Well Bldg, meet James at gate to site at 0825.
James waiting for arrival of 20 ft of additional auger.

0850 Augers arrive site 0850, James began tripping augers
0900 back down at 0900, hole clean and dry. Added augers,
drilled to 100 ft, cuttings still moist, not saturated.

0920 Added augers- 100-105 ft at 0920. James reports soft
drilling 102-105 ft. Continue cleaning hole ~ 1 min
until saturated cuttings return to surface. CBT attempt
to check with water level indicator but augers plugged
at 104 ft. CBT asked James for sub to connect
Hydropunch to rods. No EW sub available
and hole in AW sub too small for bailer to
pass through. CBT radio R. Hunter. Agrees
to bring parts in to Well Bldg for discussion

3/15/91 (continued)

3/15/91

SWA back at site with Shipping Order signatures. He will
 decan split spoon to knock soil plug out of auger. Meeting at
 1030 Well Bldg at 1030 - R. Hunter, Bruce Kristiansen, and CB Travis.
 The "EW" adaptor that came with the Hydropunch does not
 match the description in the charts. Telecom Chris Bennett
 1100 1100. For contact at QED, Telecom Brad Peake at QED
 at 1110. The thread is EW Casing thread, not EW
 rod thread. Bruce determined that an adaptor can
 be fabricated and shipped here by Tuesday. Telecom
 Mary Flora re: overall situation and the possibility
 of using a temporary 2" PVC piezometer. Mary
 will discuss with Bob Benson of DHEC - he is out
 to lunch - will call back. Bruce got an estimate
 of \$100 + tax and shipping with delivery Saturday.
 R. Hunter authorized the purchase. Further
 discussion about options. Discussed moving to
 one of the other borings and obtaining soil
 samples. Bruce points out that, by the time
 we can trip out of FRT-5HP, decan the augers,
 move and set up on another boring - we may
 obtain soil samples, but it will be too late
 to ship them. CBT Telecom Ben Shapiro
 at Weston Lab. If we sample today and
 ship Saturday, he will get delivery Monday -
 this will be OK but is pushing it. It would not
 be acceptable to sample today and ship Monday.
 1215 Radio discussion - CBT and Tom Gaughan at 1215 -
 Tom concurs with maintaining the Status Quo
 1230 until Monday. Telecom Mary Flora - 1230 - She
 concurs with not moving over, if we can proceed with
 Hydropunch Monday. SWA returns Hydropunch, etc to
 Well Bldg - locks in cage - dpts with samples for shipping.
 1245 at 1245. CBT return site 1255, James and Anthony

gr
1310WS
1340rai
1400TH
esS
CB

1445 14

3/

0645 CBT

pr
0830Bldg
Hebeg
2dwill
dec

0930 Av

ra
0945 MFlu
1000 in1040 S
sTea1045 55
-d

3/15/91 (continued)

ures. He will
Meeting at
, and CBT Travis.
dropunch does not
Chris Bennen
ake at QED
, not EW
adaptor can
day. Telecom
, the possibility
inter. Mary
EC - he is out
in estimate.

grouting FRT-1HP to surface. Begin tripping
1310 augers out of FRT-5HP at 1310 - after tripping
water at 102⁰⁰⁰ ft. in the hole. Complete tripping
1340 augers out at 1340. Sealed the hole against
rainwater infiltration with plastic and earth.
1400 and dpt site. Met Teresa Jordan at
the gate - gave her the key so she could
escort two other persons around the site.
She will return the key to Dan Wells.
CBT return to Well Bldg. Update files. Dpt site
1445 1445, SVA shipped (and checked) samples via FedEx at 1500.

3/18/91 Daily Activities Report FRT-5HP

Saturday.
Further
moving to
ning soil
by the time
in the augers,
ing - we may
be too late
on Shapiro
day and
Monday -
It would not
ship Monday.
ian at 1215 -
to vs Quo
230 - She
proceed with
dropunch, etc to
for shipping, d
os and Anthony

0645 CBT + SVA meet at Sirrine office at 0645. Sean has
prior sampling commitments, so CBT will provide Technical
Oversight and sample. Load sampling gear - drive to Well
0830 Bldg. Load remaining gear. Meet James at site at 0830
Hole cased at 835 ft, so no water here. James
begins tripping in augers at 0840 while CBT decon new
adaptor to remove machine oil, etc. Weather cool
with light drizzle. 69°F at 0900. Assembled &
deconned Hydropunch. Completed tripping in
0930 Augers at 0930. Steam cleaned inside of drill
rods one more time, ~~and~~ to begin tripping in. Tim
0945 McKinsey visited site 0945 to assist with hydropunch
Final rinse and assembly of Hydropunch - begin tripping
1000 in at 1000. Determined we needed an additional
1040 5 ft rod. Anthony drove to Buckner's site - rth 1040.
Steam cleaned & assembled. Drove sampler (Hydropunch)
1045 5 ft at 1045. The bailer hits each coupling
- at 10 ft intervals - on the way down, and

3/18/91 (continued)

on the way out. Retrieving the bailer is very difficult and time consuming, and each impact with a coupling unseats the checkball so that, by the time the bailer is at the surface, it is empty. After three attempts, asked James to call on Graves radio to have Janelle Janssen or Robert Hunter visit the site and observe the operation. Dan Wells arr site 1100,

1100 followed by Rick Frey. We again attempted to sample the Hydropunch, but concluded that it will be necessary to use EW flush joint casing. Tim, Dan, and Rick

1200 depart site 1200. Rick will have a 1 inch OD stainless steel bailer fabricated with no check valve, and rounded top and bottom so we can salvage this hole. Dan suggested Rick discuss the financial aspects of this with R. Hunter

1235 or Janelle Janssen. Sean Asgwith arrived site 1235. He depart site 1300 to obtain signatures for next outgoing shipment of samples. Still no word on fabricating bailer

1400 at 1400, so CBT returned to Well Bldg. to make calls & to discuss

1500 with Janelle Janssen. Telecom Bruce K. 1500, bailer not ready yet. Graves will call back ~ 1530. Telecom

1545 Clark at Graves at 1545. Bailer should be ready at sometime in the morning. CBT discussed with Janelle Janssen - she said "dog it off" for the day and don't come out in the morning until I confirm with Graves that the

1600 bailer is available. CBT return to site 1600, pack gear, reconcile hours with driller, return to Well Bldg

1630 dpt site 1630, after unloading gear. Note: The driller is concerned about getting augers stuck in hole, but Bruce K. said it shouldn't be a problem to leave them in overnight.

3/19/91

0815 Telecom obtained, piezomet. in place @ Graves that we

I asked it is equipment

0915 and fuel No one cooler, e.

1000 site 1000. augered from the plug = 0.4

1025 piezomet. apparent from Hyd tripping clean,

1055 hole at ~ 0.5 ft

1100 down on secured soil. V. and rods location. I set v

1200 To push fins to push 1st bit. Deco

3/19/91 FRT-5HP Daily Activities Report

1. The bailer is
 assuming, and each
 eats the checkball
 is at the surface,
 Temps, asked
 to have Janelle
 at the site and
 calls on site 1100,
 attempted to sample
 it will be necessary
 Tim, Dan, and Rick
 a 1 inch OD
 d with no check
 in so we can
 ted Rick discuss
 his with R. Hunter
 with arrived site 1235.
 for next outgoing
 on fabricating bailer
 to make calls & to discuss
 K. 1500, bailer not
 back ~ 1530, Telecom
 should be ready if
 used with Janelle Janssen -
 d don't come out
 with Graves that the
 to site 1000, pack
 return to Well Bldg
 ar. Note: The driller is
 but Bruce K. said
 in overnight.

0815 Telecom Janelle Janssen 0815. She has
 obtained permission to substitute 2" temporary
 piezometers in FRT-5HP, 3HP, and 4HP
 in place of Hydropunch sampling. She said
 Graves would gather 2" PVC and screen and
 that we should set them through the augers.
 I asked about filter pack - she indicated
 it is not necessary. I load sampling
 equipment, purchase ice for shipping samples
 and fuel for field vehicle; arrive Well Bldg 0915.
 No one at Well Bldg. I load remaining equipment
 cooler, etc, fill D.I. water bottle, arrive
 1000 site 1000. James has pulled Hydropunch and
 augered to 110 ft. He encountered no resistance
 from the Hydropunch point. Screen = 16 ft,
 plug = 0.44 ft, casing = 100.0 ft. Temporary
 1025 piezometer tripped in 1025, inside augers, so
 apparently went to the bottom with no interference
 from Hydropunch screen or point. Began
 tripping out augers at 1030. CBT disassemble,
 clean, and repack Hydropunch. Augers out of
 1055 hole at 1055. Temporary piezometer stickup
 ~ 0.5 ft, so went to bottom as expected. Boom
 1100 down on rig at 1100. Moved rig off hole,
 secured hole with plastic sheeting and
 soil. Used steam cleaner to decon rig, augers,
 and rods prior to moving onto next boring
 location. James moved rig over stake at 1130 while
 I set up sampling station. James has boom up, ready
 to push first sample at 1200. Sampling station setup, attempted
 to push 1st sample. Hit an obstruction at 0.6 ft. Cobble in
 bit. Deconned spoon, moved rig one foot west, pushed 1st

3/19/81 (continued)

3/19/81

* 1240 sample again. Pushed 1.25 ft, sufficient sample at 1240. Augered to 1.5 ft. Pushed FRT-4HP-2 at 1315 - unable to push due to large cobbles - Auger 6 inches - Push again at

F-Are.
Technics
Company

* 1320 1320 - to ~2.5 ft. Auger to 3.0 ft, Push Sample

* 1400 FRT-4HP-3 at 1400 - 3.0 to 4.0 ft, unable to push further. Upper portion of sample damp, lower portion dry. H₂N₂ yielded 3 ppm in upper head space, 0 ppm at bit. Augered to 4.5 ft, push

Samplin
Sci
Te

* 1440 FRT-4HP-4 at 1440, 4.5 ft to 6.0 ft. Sample damp - H₂N₂ registers 2 ppm in both upper and lower head space as split spoon drive head and bit removed. Augered to 10.0 ft. Push Sample FRT-4HP-5 ~ 1.5 ft - too hard. Nothing but auger cuttings in split spoon. Auger to 11.0 ft

Prelimin
Prelimi
Refer
Station

* 1530 push sample 11.0 to 12.5 ft at 1530. Auger to 15.0 ft, attempt to push FRT-4HP-6 at 1555; too hard ~ 0.1 ft penetration, auger to 16.0 ft; pushed sample to refusal at 17.0 ft

Sample

* 1605 at 1605. Augered to 20 ft, collected FRT-4HP-7 from

* 1635 20.0 to 21.5 ft at 1635 - in sand. James and Anthony

remaining augers from FRT-5HP to FRT-4HP while I

1650 log & package samples. Rtn 1650 with augers. I note sample jar is broken - FRT-4HP-4, pH sample. Other jars full, so should be sufficient sample. CBT completes packing samples, etc, while James drills to 35 ft. Reconcile

Sample ID	Depth
FRT-4HP-1	0.0 to 1.25
FRT-4HP-2	1.5 to 3.0
FRT-4HP-3	3.0 to 4.0
FRT-4HP-4	4.5 to 6.0
FRT-4HP-5	6.0 to 10.0
FRT-4HP-6	10.0 to 11.0
FRT-4HP-7	20.0 to 21.0
FRT-4HP-TB	

1745 paperwork with driller, dpt site and lock gate at 1745

Rtn to Well Bldg, unload gear, lock samples in

1815 cage, dpt Well Bldg at 1815.

inefficient sample at 1240
 P-2 at 1315 - Unable
 hes - Push again at
 5.0 ft. Push Sample
 unable to push
 ple damp, lower
 ppm in upper head
 1 to 4.5 ft, push
 to 6.0 ft. Sample
 upper and lower head
 bit removed. Augered
 5 ~ 1.5 ft - too hard.
 won. Auger to 11.0 ft
 2 Auger to 15.0 ft,
 5; too hard - at 1st
 ok to refusal at 17.0 ft
 lected FRT-4HP-7 from
 James and Anthony ^{6/1/91}
 FRT-4HP while I
 with augers. I note
 pH sample. Other jars
 completes packing
 35 ft. Reconcile
 in lock gate at 1745
 samples in

3/19/91
 F-Area Railroad Cross-tie Site
 Technical Oversight: Charles B. Travis
 Company: Sirmine Environmental Consultants

Sampling Station: FRT-4HP;
 Soil boring - Split spoon samples
 Temporary piezometer - bailed samples
 Preliminary SRS Coordinates: N 80, 181.21; E 50, 419.81
 Preliminary Elevation: 283.6
 Reference Point: Ground Surface, drainage swale
 Station Established 3/19/91

Sample Information

Sample ID	Depth	Date	Time	Sampler	Comments
FRT-4HP-1	0.0 to 1.5	3/19/91	1240	CB2	"0" ppm w/ HNu
FRT-4HP-2	1.5 to 3.0	3/19/91	1320	CB2	"0" ppm w/ HNu
FRT-4HP-3	3.0 to 4.0	3/19/91	1400	CB2	3 ppm upper, 0 ppm lower.
FRT-4HP-4	4.5 to 6.0	3/19/91	1440	CB2	2 ppm on HNu
FRT-4HP-5	6.0 to 7.5	3/19/91	1530	CB2	2 ppm top, 0 ppm at bit
FRT-4HP-6	7.5 to 10.0	3/19/91	1605	CB2	"0" ppm
FRT-4HP-7	20.0 to 21.5	3/19/91	1635	CB2	"0" ppm bit, 2 ppm top
FRT-4HP-TB		3/19/91	1705		Trip Blank

3/20/91 Daily Activities Report

3/20/91

0700 Load sampling equipment at Sirrine Office at 0700.
 0730 CBT to Well Bldg 0730, load remaining gear and cooler
 0800 of samples from cage. Mtg Janelle Janssen to discuss
 progress. Janelle suggested collecting samples of ground
 water from FRT-5HP today because it might rain tomorrow.
 0830 CBT fill DI water bottles, arrive site 0830; James
 augering at 65 ft on FRT-4HP. CBT packed samples from
 yesterday in Freshice. Teresa Jordan visits site 0915
 to 0930. Noted auger cuttings increasingly damp below
 25 ft, but not saturated. Saturated cuttings return
 ~110.5 ft - last auger 110-115 ft. Cuttings wet
 but not a slurry. CBT believes water table ~110 ft.
 James not sure. Radio via Graves radio - Bruce at
 Well Bldg. CBT requests permission to drill to
 120 ft and set 20 ft of screen to be sure
 screen straddles water table. Bruce relays
 permission at 1030. Drilled 115-120 ft by
 adding 5 ft rod on top of augers. Steam cleaned
 rods and pvc screen and casing (2") off station and
 1115 return 1115. Sean Asquith arrive site 1115, begins to
 wrap and prepare samples for shipment. Begin tripping 3"
 1125 split spoon inside augers at 1125 to make sure augers
 clear before inserting 2" PVC screen. Sean dpt for
 1130 Well Bldg 1130 to obtain more bubble wrap. Split spoon
 1135 to bottom of boring at 120 ft at 1135; began tripping
 out. Begin tripping in temporary piezometer screen at
 at 1145. Tally in order of insertion: paint plug - 0.45 ft,
 2" PVC ^{split} screen: 5.00, 5.02, 5.00, 5.02 ft, 2" PVC
 casing, 20.0, 20.0, 20.0, 20.0, 20.0, and 2.53 ft
 PVC pipe unusually heavy, but doesn't appear to be
 1155 schedule 80?? Sean rtn site 1155. PVC casing
 stop at 112 ft - no need to use 2.53 ft piece.

1205 Begin 1.
 1245 out aug
 1255 off sta
 To sedi
 set up:
 1340 Station
 boom v
 * 1400 at 1400
 Collec
 * 1450 at 144
 Unbale;
 ship too
 from F.
 * 1525 at 152
 * 1555 Note 11.5
 CB * 1555 push
 * 1645 at 164
 Killen,
 1630 at 1630, d
 * 1710 FRT-3
 Material
 sand. T
 have b.
 of 27
 25 ft.
 with dri
 1745 site 17
 sampling
 1800 FRT-4
 1810 and at
 1845 Samples

art

3/20/91 (continued)

Office at 0700.
 ining gear and cooler
 le Janssen to discuss
 ing samples of ground
 e it might rain tomorrow
 p site 0830; James
 CBT packed samples from
 Jordan visits site 0915
 reasingly damp below
 saturated cuttings return
 5 ft. Cuttings wet
 es water table ~110 ft.
 res radio - Bruce at
 mission to drill to
 screen to be sure
 ble. Bruce relays
 d 115-120 ft by
 gers. Steam cleaned
 2") off station and
 site 1115, begins to
 it. Begin tripping 3"
 To make sure augers
 screen. Sean dpt for
 wrap. Split spoon
 135; began tripping
 piezometer screen etc
 tion. Bint plug - 0.45 ft,
 1.5, 0.0 ft, 2" PVC
 20.0, and 2.53 ft.
 esn't appear to be
 5. PVC casing
 2.53 ft piece.

1205 Begin tripping out augers at 1205. Complete tripping
 1245 out augers at 1240, boom down at 1245, rig
 1255 off station FRT-4HP at 1255. Moved off station
 To steam clean augers, rods, etc. CBT & SWA
 set up sampling station FRT-3HP. Rig on
 1340 Station at 1340, plastic under rig and
 boom up at 1355. Push sample FRT-3HP-1
 * 1400 at 1400. Push sample FRT-3HP-2 at 1425.
 Collect rinseate sample, 2 @ 40 ml VOA vials
 * 1450 at 1445. Push FRT-3HP-3 at 1450
 Unable to complete sampling FRT-3HP in time to
 ship today, so Sean dpt site 1520 with samples
 from FRT-4HP for shipping. Push FRT-3HP-4
 * 1525 at 1525. Auger to 10 ft, push FRT-3HP-5 from
 * 1555 10 to 11.5 ft at 1555. Augered to 15 feet
 * ~~1555~~ push FRT-3HP-6 from 15.0 to 16.5 ft
 * 1645 at 1645. Jim Jordan, Natche Park, Terry
 Killen, and a gentleman from EPA visited site
 1630 at 1630, dpt 1645. Auger to 20.0 ft, push sample
 * 1710 FRT-3HP-7 from 20.0 to 21.5 ft at 1710.
 Material in the bit is fine, grayish red purple
 sand. This horizon has been demonstrated to
 have background levels of lead on the order
 of 27 ppm in M-Area. James augers to
 25 ft. Knock off at 1730. Reconcile paperwork
 with driller; he helps load samples, etc on truck, dpt
 1745 site 1745. CBT stay on site to complete log, load
 sampling gear, etc. Measured water level in
 1800 FRT-4HP at 97.3 ft below ground level at 1800
 1810 and at 103.0 ft in FRT-5HP at 1810. Deposit
 1845 samples, etc at well Bldg at 1830. Dpt SRs at 1845.

3/21/91 Daily Activities Report

0730 Meeting CBT + SWA at Sirrine Office at 0730. Agree Sean will us truck today, prepare FRT-3HP soil samples for shipment. CBT will use PDR, will oversee installation of temporary piezometer in FRT-3HP.

0800 CBT arrive site 0800. Anthony steam cleaning augers off station; James augering at 20 ft; having difficulty bringing cuttings/cobbles up with augers. CBT + James discuss water level - will drill FRT-3HP to 105 ft.

0830 CBT return to Well Bldg at 0830 to meet with J. Janssen - SWA with Janella wants all three piezometers sampled today so they can be grouted tomorrow. I point out that FRT-3HP isn't even installed yet, but we'll do what we can. CBT assist SWA in

1000 assembling sampling gear - return site 1000. James augering at 70 ft.

1010 Sean Arr. FRT-5HP. Set-up 40 collect groundwater sample. Decom tation bather

1045 Calibrate pH meter with 7 and 4 buffers.

Get together sample containers

James drills to 95 ft, cuttings damp. Stop drilling

1045 at 1045 to allow water level to equilibrate

1115 No water accumulates; drill to 100 ft at 1115 -

1145 allow to equilibrate - at 96 ft at 1145. James has 3 @ 5 ft sections of screen, so CBT directs to drill to 105 ft and set 15 ft of screen.

1230 Drill to 105 ft. Water at 96 ft at 1230. Begin tripping in temporary piezometer at 1240. (Note: The extra 5 ft of screen below the water table will allow collection of a cleaner, less disturbed sample with the bailer, because

3/20/91

F-Area R
Technical C
Sampling,
Company

Sampling

Preliminary
Preliminary
Reference
Station

Sample

Sample ID	Depth
FRT-3HP-1	0 to 1.5
FRT-3HP-2	1.5 to 3.0
FRT-3HP-3	3.0 to 4.5
FRT-3HP-4	4.5 to 6.0
FRT-3HP-5	10.0 to 11.5
FRT-3HP-6	15.0 to 16.5
FRT-3HP-7	20.0 to 21.5

FRT-3HP-R

3/20/91

F-Area Railroad Crossing Site

Technical Oversight: Charles B. Travis, PE, PG.

Sampling Assistant: Sean W. Asquith

Company: Sippine Environmental Consultants, Inc.

Sampling Station: FRT-3HP

Soil boring, 3" split spoon samples

Temporary piezometer - bailed samples

Preliminary SRS Coordinates: N 79,872.19; E 50,387.93

Preliminary elevation: 280.3

Reference Point: Ground Surface,

Station Established 3/20/91

Sample Information

Sample ID	Depth	Date	Time	Sampler	Comments
FRT-3HP-1	0.0 to 1.5	3/20/91	1400	CBT	4 ppm on HAN
FRT-3HP-2	1.5 to 3.0	3/20/91	1425	CBT	2 ppm
FRT-3HP-3	3.0 to 4.5	3/20/91	1450	CBT	3 ppm
FRT-3HP-4	4.5 to 6.0	3/20/91	1525	CBT	2 ppm
FRT-3HP-5	10.0 to 11.5	3/20/91	1555	CBT	2 ppm
FRT-3HP-6	15.0 to 16.5	3/20/91	1645	CBT	4 ppm
FRT-3HP-7	20.0 to 21.5	3/20/91	1710	CBT	2 ppm
FRT-3HP-R		3/20/91	1445	SWA	Rinsate Blank

Office at 0730.

re FRT-3HP soil

PDR, will oversee

in FRT-3HP.

cleaning augers off

having difficulty

augers, CBT + James.

T-3HP to 105 ft.

with J. Janssen

three piezometers

noted tomorrow,

even installed yet, "

ist SWA in

re 1000 James

set-up

4-er sample.

with

concretes

imp. stop drilling

to equilibrate

11 ft at 1115 -

at 1245, James

n, so CBT directs

15 ft to 5 screen.

ft to 1230. Begin

ter at 1240.

n below the water

cleaner, less

bailer, because

3/21/91 (continued)

3/21/91

F-Area,
Sampling,
Company:Sediment will settle to the bottom of the screen.
1250 Piezometer in place at 1250. James began

1315 Tripping out augers at 1315 hr.

SWA and CBT bail FRT-5HP beginning at 1145. Necessary to allow well to recover

about 5 minutes between bails with teflon bailer to minimize sediment. Filtered

metals sample - 1 liter - through 0.45 μ Nalgene filter apparatus. Complete filtration

at 1325. Complete filling 1/2 gallon Rad

1330 sample at 1330. Complete packing samples

1345 and move of sampling station at 1345

Note: Water level at 103.0 ft below ground surface prior to sampling.

1410 James completes tripping out augers - from

FRT-3HP - at 1410. Water level 98.5 ft TAC with 3.7 ft stick up is 94.8 ft below GS.

Sean setup on sampling station FRT-4HP at 1405, begins decontamination procedure. Water level at

1435 97.36' below GS at 1435. Begin tripping in

1440 first bailer at 1440. Complete bailing and

filtering sample at 1640. Setup on station FRT-3HP at 1645. Decon and bail. Complete

bailing and filtering sample at 1840.

Note: Collected duplicate sample at this station except metals sample not filtered.

Labeled duplicate sample: FRT-2HP

1850 SWA + CBT dpt site 1850, for Well Bldg.

Sampling

FRT-5H

Depth to Water 103.0

Date 3/21/91

Time 12:45

Vol. Purged 3 Ba

pH 5.3

sp Cond 65.2

Temp. 19.0

Alkalinity 4.4

(mg/L as CaCO₃)

p Alkalinity

3/21/91 Water Samples

F-Area Railroad Crosstie Site

Sampling: S.W. Asquith, C.B. Travis

Company: Sirrine Environmental Consultants

bottom of the screens

50. James began

15 hr.

- 5HP beginning a t
well to recoverbails with teflon
iment. Filteredr - through 0.45 μ

Complete Filtration

Using 1/2 gallon Rad

ite packing samples

station at 134.5'

below ground surface

not augers - from

iter level 98.5 ft TAC

24.8 ft below G.S.

ation FRT-4HP at 1405,

ire. Water level at

Begin Tripping in

mplete bailing and

0. Set up on station

econ and bail. Comple

mple at 1840.

id sample at this

s sample not filtered.

mple FRT-2HP

1850, for Well Bldg.

Sampling Stations: FRT-5HP; 1145 to 1330;
FRT-4HP;
FRT-3HP;

	FRT-5HP	FRT-4HP	FRT-3HP
Depth to Water	103.0	97.4'	93.9'
Date	3/21/91	3/21/91	3/21/91
Time	1200-1330	1535	1730
Vol. Purged	3 Bails	3 Bails	4 Bails
pH	5.38	5.11	5.53
sp Cond	65.2 μ S/cm	25.2 μ S/cm	26.4 μ S/cm
Temp.	19.0 $^{\circ}$ C	18.5	18.5
Alkalinity	4.4	2.2	2.2
(mg/L as CaCO_3 & Alkalinity)			
			Collected
			Duplicate sample
			at time 1800
			from FRT-3HP
			ID: FRT-2HP
			(did not filter
			metals sample)

3/22/91 Daily Activities Report

3/22/91 C

0730 Telecom Dan Wells To C.B. Travis confirming technical oversight for grouting FRT-3HP, 4HP and 5HP.

Purch
Shippi
grent to
1800 Road F.

0830 CBT on site. James has removed PVC from FRT-3HP and is tripping in Tremie. Begin mixing
0855 grout at 0855. Grout weight - with bentonite = 14.5 lb/gal.

0940 Good grout return at 0940, 21 sacks grout in FRT-3HP. Complete tripping out 105 ft Tremie at 0950. Flush grout from pump and Tremie and move onto

1015 FRT-4HP at 1015. Pull PVC + Trip out. Begin tripping in 126' Tremie (6' stickup) at 1035. Begin mixing

1130 grout at 1045. 14.3 lb/gal. Good grout return at 1130. Out 24 sacks of grout. Began tripping out Tremie. From FRT-4HP - Slushed grout from pump, hoses, Tremie.

1230 moved onto FRT-5HP at 1230. Tripped out PVC at 1245, began mixing grout at 1255 - pump 22 sacks grout at 14.3 lb/gal with return

1330 at 1330. Trip out 105 ft of Tremie, flush Tremie, pumps, hoses, etc. C.B.T. reconcile paperwork with driller, apt for well Bldg with split spools, logs, etc. Driller remains to load equipment and police site. FRT-3HP, 4HP and 5HP grout has dropped ~ 4 ft in each boring - will require tapping off.

CBT complete Soil Boring Installation Reports, update files, arrange shipping to Weston with Sean Asquith. Terry Killeen relayed instructions through Janelle Janssen to ship duplicate samples to lab (collected from FRT-3HP and labeled FRT-2HP). WSRC will relay analytical instructions to Weston.

1645 CBT dpt SRS 1645 with sample coolers.

part

3/22/91 (continued)

vis confirming
 1 RT-3HP, 4HP and

Purchase ice for coolers. Prepare
 shipping labels, turn coolers
 over to FedEx lady at 955 Millbrook
 1800 Road FedEx box at 1800.

1 red PVC from
 2. Begin mixing
 with bentonite = 14.5 gal.
 3. grout in FRF3HP.
 Tremie at 0950.
 4. and move onto
 5. p abt. Begin tripping
 6. 7. Begin mixing
 8. grout return at 1130.
 9. 10. out Tremie from
 11. imp, hoses, Tremie
 12. Tripped out PVC
 13. 12.55 - pump
 14. 15 gal with return
 15. 16. es flush Tremie.
 17. reconcile paperwork
 18. 19. with split spools,
 20. 21. load equipment and
 22. 23. p and 5 HP
 24. 25. in each boring-

Installation
 arrange shipping to
 1. 2. Killeen relayed
 3. Janssen to
 4. 5. (collected from
 6. 7. 2HP). WSRC
 8. 9. tons to Weston
 10. 11. simple coolers.

WESTINGHOUSE SAVANNAH RIVER COMPANY
SOIL BORING PROCEDURES
SRS SOIL BORING INSTALLATION REPORT

Manual: DPSOP 254
Chapter: 3 (Draft 1)
Page: 1 of 2
Effective Date: 8/1/89
Organization: Environmental
Protection Section

SRS SOIL BORING INSTALLATION REPORT

GENERAL INFORMATION

Boring number FRT-1HP Site F-Area Railroad Crosstie Pile
Boring purpose Soil Boring: fr
Project name Preliminary Characterization of the F-Area Railroad Crosstie Pile
Custodian T. Bittler Custodial Dept C S W E
SRS Coordinates: North 79,777.44 East 50,468.41
Or: Latitude _____ Longitude _____
Location description In a ditch/drainage swale/dirt road
Drilling contractor Graves Driller James Smith, #861
Oversight contractor Sirrine Environmental Oversight Charles R. Travis / Sean W. Asquith
Boring start date 3/12/91 Boring completion date 3/12/91

DRILLING INFORMATION

Note: Depths are measured from ground surface to the nearest 0.1 ft.

Type of drill rig used Gwik Drill
Depth to static water level N/A
Total depth of boring 21.5 ft
Ground surface elevation (mean sea level) 284.2

	Hole			
Drilling Method	Diameter	From (ft.)	To (ft.)	Footage
Auger	<u>6.7 1 1/4</u>	<u>0.0</u>	<u>21.5</u>	<u>21.5</u>
Hollowstem auger	<u>1 1/4</u>	<u>0.0</u>	<u>20.0</u>	<u>20.0</u>
Mud rotary				

Sample depths 0.0 to 1.5, 1.5 to 3.0, 3.0 to 4.5, 4.5 to 6.0, 11.0 to 11.5, 15.0 to 16.5
20.0 to 21.5

WESTINGHOUSE SAVANNAH RIVER COMPANY

SOIL BORING PROCEDURES

SRS SOIL BORING INSTALLATION REPORT

Manual:

Chapter:

Page:

Effective Date:

Organization:

DPSOP 254

3 (Draft 1)

2 of 2

8/1/89

Environmental
Protection Section

Split spoon:

Sample depths 0.0 to 1.5, 1.5 to 3.0, 3.0 to 4.5, 4.5 to 6.0, 6.0 to 7.5,
7.5 to 9.0, 9.0 to 10.5

Other (specify):

Sample depths

Disposition of samples Shipped to Weston Lab.

Tests conducted on samples pH, TCLP, App IX pig, App IX Inorg,
App IX VOA, RAD, App IX BVA, App IX metals (B2)

BORING ABANDONMENT

Material(s) used to abandon boring 3 sacks grout

Method of abandonment Tramie in 3 sack batch neat cement grout
with bentonite (with funnel)

Proper abandonment verified by Charles Tranta

Boring installation report prepared by Charles Tranta

Company S. Tranta

Date 3/1/89

COMMENTS

FIELD GEOLOGIC LOG

PROJECT F-Area Railroad Crosstie site				DATE 3/12/91	SHEET 1 of 2
Preliminary Characterization				DRILLING SUBCONTRACTOR GORES	
WELL NO. ERT-1-HIP		LOCATION N 79, 777.44, E 50, 469.41		DRILLER James Smith, # 861	
LOGS PREPARED BY Charles B. Janna		COMPANY Serrine		DRILLING METHOD 1 1/4" Hollow Stem Auger	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
1	0			SAND: fine to coarse, poorly sorted, moderate brown to moderate yellowish brown with roots.	3" split screen
2	1			Color grades moderate yellowish brown to moderate reddish brown	3" ss
3	2			CLAYEY SAND, with rtz cobbles to 1". yellowish brown to moderate reddish brown, rtz cobbles white.	2" ss
4	3			As above - grades with less clay, sand grains and pebbles mostly subangular.	3" ss
	4				
	5				
	6				
	7				
	8				
	9				
5	10			SAND, medium to coarse, moderate yellowish brown.	2" ss
	11			CLAY, light to moderate red with occasional white or moderate yellowish brown mottling, with sand (brown to red).	
	12				
	13				
	14				
6	15			CLAYEY SILTY SAND; 1/4" to 1/2" pale red purple to grayish red purple, mottled moderate yellowish brown.	3" ss
	16				
	17				
	18				
	19				
	20				

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Site</i>		DATE <i>3/12/91</i>	SHEET <i>2</i> OF <i>2</i>
WELL NO. <i>FRT-1HP</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY		LOCATION	DRILLER
COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
<i>7</i>	<i>20</i>			<i>CLAYEY SAND; v. fine to coarse, light brown to moderate reddish orange.</i>	
	<i>1</i>				
	<i>2</i>			<i>Total Depth of Exploration: 21.5 ft.</i>	
	<i>3</i>			<i>Completed 1700, 3/12/91</i>	
	<i>4</i>				
	<i>5</i>				
	<i>6</i>				
	<i>7</i>				
	<i>8</i>				
	<i>9</i>				
	<i>0</i>				
	<i>1</i>				
	<i>2</i>				
	<i>3</i>				
	<i>4</i>				
	<i>5</i>				
	<i>6</i>				
	<i>7</i>				
	<i>8</i>				
	<i>9</i>				
	<i>0</i>				

WESTINGHOUSE SAVANNAH RIVER COMPANY
SOIL BORING PROCEDURES
SRS SOIL BORING INSTALLATION REPORT

Manual: DPSOP 254
Chapter: 3 (Draft 1)
Page: 1 of 2
Effective Date: 8/1/89
Organization: Environmental Protection Section

SRS SOIL BORING INSTALLATION REPORT

GENERAL INFORMATION

Boring number FRT-54P Site F-Area Railroad Crosstie Pile
Boring purpose Soil boring with water table sample
Project name Preliminary Characterization of the F-Area Railroad Crosstie Pile
Custodian T. B. Miller Custodial Dept CSWE
SRS Coordinates: North 78,823.00 East 56,701.78
Or: Latitude _____ Longitude _____
Location description Wooded plateau above crossties
Drilling contractor Graves Driller James Smith, #861
Oversight contractor Sirrine Oversight C. B. Travis, S.W. Asquith
Boring start date 31/4/91 Boring completion date 31/5/91

DRILLING INFORMATION

Note: Depths are measured from ground surface to the nearest 0.1 ft.

Type of drill rig used Quik Drill
Depth to static water level 113.6 ft.
Total depth of boring 116.6 ft
Ground surface elevation (mean sea level) 225.5 ft

	Hole			
Drilling Method	Diameter	From (ft.)	To (ft.)	Footage
Auger				
Hollowstem auger	<u>6 1/4</u>	<u>0.0</u>	<u>116.6</u>	<u>116</u>
Mud rotary				

Sample depths _____

WESTINGHOUSE SAVANNAH RIVER COMPANY

SOIL BORING PROCEDURES

SRS SOIL BORING INSTALLATION REPORT

Manual:

Chapter:

Page:

Effective Date:

Organization:

DPSOP 254

3 (Draft 1)

2 of 2

8/1/89

Environmental
Protection Section

Split spoon:

Sample depths 0.0 to 1.5, 1.5 to 3.0, 3.0 to 4.5, 4.5 to 6.0, 6.0 to 11.5
15.0 to 16.5, 26.0 to 27.5

Other (specify): Water sample at water table

Sample depths ~ 16.3 ft

Disposition of samples shipped to Weston Lab

Tests conducted on samples pH, TCLP, App IX C1a, App IX Imrg,
App IX VOA (soil and water), RAD, App IX BNA, App IX, metals

BORING ABANDONMENT

Material(s) used to abandon boring Neat cement grout with Bentonite

Method of abandonment Pump grout through Tremie

Proper abandonment verified by Charles B. Fravia

Boring installation report prepared by Charles B. Fravia

Company Silline

Date 31 22 191

COMMENTS

FIELD GEOLOGIC LOG

G1106

PROJECT F-Area Railroad Crosstie site		DATE 3/14/91	SHEET 1 OF 2
Preliminary Characterization		DRILLING SUBCONTRACTOR Graves	
WELL NO. FRT-54P	LOCATION N 79,823.10, E 50, 701.78	DRILLER James Smith, # 861	
LOGS PREPARED BY Charles J. J. J.	COMPANY Serrine	DRILLING METHOD 6 1/4" Hollow Stem Auger	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
1	0			SAND medium to coarse, pale yellowish brown, occasional pebbles, subrounded to subangular.	3" split spinn.
	1			as above - with a cobble ~ 50 mm	
2	2				
	3				
3	4			color grades moderate yellowish brown and moderate reddish brown	
4	5			CLAYEY SAND v. fine to coarse, moderate reddish brown with stringers (2-3 mm) pale yellowish orange, occasional well rounded cobble.	very hard
	6				
	7				
	8				
	9				
5	10			As above	very hard
	11				
	12				
	13				
	14				
6	15			As above	
	16			SAND, v. fine to medium, mottled pale pink, grayish red purple, and very dark red, trace silt.	med dense to dense
	17				
	18				
	19				
	20				

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Site</i>		DATE <i>3/14/91</i>	SHEET <i>2</i> OF <i>25</i>
WELL NO. <i>FRT-5HP</i>		LOCATION	DRILLER
LOGS PREPARED BY <i>Charles B. Zuma</i>		COMPANY	DRILLING METHOD

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS	
<i>7</i>	<i>20</i>			<i>SAND, v. fine to medium, mottled pale pink, grayish red, purple, and very dark red, trace silt, color grades to moderate reddish orange and pale reddish brown.</i>	<i>Note: Logged suger cuttings from 21.5 ft to 25.0 ft.</i>	
	<i>1</i>					
	<i>2</i>					
	<i>3</i>					
	<i>4</i>					
	<i>25</i>			<i>As above</i>		
	<i>6</i>					
	<i>7</i>					
	<i>8</i>					
	<i>9</i>					
	<i>30</i>			<i>As above</i>		
	<i>1</i>					
	<i>2</i>					
	<i>3</i>					
	<i>4</i>					
	<i>35</i>			<i>As above, grades coarser, with trace clay (5-10%)</i>		
<i>6</i>						
<i>7</i>						
<i>8</i>						
<i>9</i>						
<i>40</i>						

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crossing Site</i>		DATE <i>3/14/81</i>	SHEET <i>3</i> of <i>6</i>
WELL NO. <i>FRT-5HP</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY <i>CB Franva</i>		LOCATION	DRILLER
COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	40			<i>SAND v. fine to coarse with 10-15% silt and clay, moderate reddish orange to pale reddish brown.</i>	<i>Logged From Auger cuttings</i>
	1				
	2				
	3				
	4				
	45			<i>As above</i>	
	6				
	7				
	8				
	9				
	50			<i>As above</i>	
	1				
	2				
	3				
	4				
	55			<i>As above</i>	
	6				
	7				
	8				
	9				
	60			<i>color grades with less red CB2</i>	

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Site</i>		DATE <i>3/14/91</i>	SHEET <i>4</i> OF <i>6</i>
WELL NO. <i>FRT-54P</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY <i>CB Travia</i>		DRILLER	DRILLING METHOD
LOCATION		COMPANY	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	6 0			<i>SAND, v. fine to coarse with 10 to 15% silt and clay, moderate reddish orange to pale reddish brown</i>	<i>Logged From Auger Cutting</i>
	1				
	2				
	3				
	4				
	6 5			<i>As Above</i>	
	6				
	7				
	8				
	9				
	7 0			<i>As above</i>	
	1				
	2				
	3				
	4				
	7 5			<i>As above</i>	
	6				
	7				
	8				
	9				
	8 0			<i>color grades with less red</i>	

FIELD GEOLOGIC LOG

PROJECT F-Area Railroad Crosstie Site		DATE 3/14/91	SHEET 5 of 6
WELL NO. ERT-5HP		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY CB Zornitz		LOCATION	DRILLER
COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	8 0			<u>SAND</u> v. fine to coarse with 10 to 15% silt and clay, fark yellowish orange to moderate yellowish brown.	Logged from auger cuttings
	1				
	2				
	3				
	4				
	8 5			As above	
	6				
	7				
	8				
	9				
	9 0			As above - cuttings moist	
	1				
	2				
	3				
	4				
65	9 5			<u>SAND</u> fine to coarse, 10 to 15% silt and clay, mottled moderate yellow and moderate red.	Logged from 3" split screen
	6				3/14/91
	7				3/15/91
	8				
	9				
	10 0				

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Site</i>		DATE <i>3/15/91</i>	SHEET <i>6</i> OF <i>6</i>
WELL NO. <i>FRT-5HP</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY <i>CB Tramm</i>		LOCATION	DRILLER
COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	10 0			<i>SAND, v. fine to coarse, 10 to 15% silt and clay, moist</i>	<i>Logged from auger cuttings</i>
	1				
	2			<i>Cuttings saturated</i>	<i>drilling water</i>
	3				
	4				
	10 5			<i>Bottom of boring at 105 ft</i>	
	6			<i>3/15/91 at 0930.</i>	
	7			<i>Prepared for Hydropunch.</i>	
	8			<i>Water at 102 ft - measured thru augers,</i>	
	9				
	11 0			<i>Note: Boring extended to 116 ft</i>	<i>3/19/91</i>
	1				
	2				
	3				
	4				
	5				
	6				
	7				
	8				
	9				
	0				

SRS SOIL BORING INSTALLATION REPORT

GENERAL INFORMATION

Boring number FRT-4 H1 Site F-Area Railroad Crosstie Pile
 Boring purpose Soil Boring with water Table sample
 Project name Preliminary characterization of the F-Area Railroad Crosstie pile
 Custodian T. Bitter Custodial Dept CSE
 SRS Coordinates: North 86,151.91 East 50,419.81
 Or: Latitude _____ Longitude _____
 Location description drainage swale adjacent to crossties
 Drilling contractor Graves Driller James Smith, #861
 Oversight contractor Sirrine Environmental Oversight C. B. Travis / Sean W. Asquith
 Boring start date 3/19/91 Boring completion date 3/20/91

DRILLING INFORMATION

Note: Depths are measured from ground surface to the nearest 0.1 ft.

Type of drill rig used Geik Drill
 Depth to static water level 97.4 ft
 Total depth of boring 120 ft
 Ground surface elevation (mean sea level) 253.6

Drilling Method	Hole		Footage
	Diameter	From (ft.)	
Auger			
Hollowstem auger	<u>6 1/4"</u>	<u>0.0</u>	<u>120.0</u>
Mud rotary			

Sample depths _____

WESTINGHOUSE SAVANNAH RIVER COMPANY
SOIL BORING PROCEDURES
SRS SOIL BORING INSTALLATION REPORT

Manual: DPSOP 254
Chapter: 3 (Draft 1)
Page: 2 of 2
Effective Date: 8/1/89
Organization: Environmental
Protection Section

Split spoon:

Sample depths 0.0 to 1.5, 1.5 to 2.5, 3.0 to 4.0, 4.5 to 6.0, 11.0 to 12.5
16.0 to 17.0, 21.0 to 22.5

Other (specify): Water sample at water table (~95 ft)

Sample depths

Disposition of samples Shipped to Weston Lab

Tests conducted on samples pH, TCLP, App IX Organic, App IX Inorg.
App IX VOA (soil and water), RAD, App IX BNA, App IX metals

BORING ABANDONMENT

Material(s) used to abandon boring West cement grout with Bentonite

Method of abandonment Pumped grout Through Tremie

Proper abandonment verified by Charles B. Jantz

Boring installation report prepared by Charles B. Jantz

Company Sirrine Date 3 122 191

COMMENTS

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Pile</i>		DATE <i>3/15/91</i>	SHEET <i>1</i> OF <i>6</i>
Preliminary Characterization		DRILLING SUBCONTRACTOR <i>Graves</i>	
WELL NO. <i>FRT-4HP</i>	LOCATION <i>N80.181.91; E 50.419.81</i>	DRILLER <i>James Smith, #861</i>	
LOGS PREPARED BY <i>CB Faria</i>	COMPANY <i>Sprine Environmental</i>	DRILLING METHOD <i>6 1/4" Hollow Stem Auger</i>	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
<i>1</i>	0	<i>Q. O. O.</i>		<i>3 Cabbles, qtz, white with silty sand</i>	
	1	<i>Q. O. O.</i>		<i>Cabbles well rounded,</i>	
<i>2</i>	2	<i>Q. O. O.</i>		<i>As above, sand is moderate reddish brown</i>	
	3	<i>Q. O. O.</i>		<i>SAND, white to v. coarse with pebbles, subangular / upper portion of</i>	
<i>3</i>	4	<i>Q. O. O.</i>		<i>to subrounded, moderate reddish brown</i>	<i>Sample damp.</i>
	5	<i>Q. O. O.</i>		<i>As above</i>	
<i>4</i>	6	<i>Q. O. O.</i>			
	7				
<i>5</i>	8				
	9				
<i>6</i>	10	<i>Q. O. O.</i>		<i>Cobble, white quartz</i>	
	11	<i>Q. O. O.</i>		<i>Sand, with pebbles, moderate</i>	
<i>7</i>	12	<i>Q. O. O.</i>		<i>reddish brown with pale yellowish</i>	
	13	<i>Q. O. O.</i>		<i>orange.</i>	
<i>8</i>	14				
	15				
<i>9</i>	16	<i>Q. O. O.</i>		<i>As above, moderate reddish brown</i>	
	17	<i>Q. O. O.</i>			
<i>10</i>	18				
	19				
<i>11</i>	20				
	21				

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Site</i>		DATE <i>3/19/91</i>	SHEET <i>2</i> OF <i>6</i>
WELL NO.		DRILLING SUBCONTRACTOR	
LOCATION		DRILLER	
LOGS PREPARED BY <i>CB Zuma</i>		COMPANY	
		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
<i>7</i>	<i>20</i>			<i>SAND with silt, moderate brown</i>	
	<i>1</i>			<i>SAND, med to coarse, well sorted, pale yellowish orange to dark yellowish orange</i>	
	<i>2</i>				
	<i>3</i>				<i>Note 1 logs below 21.5 ft based on auger cuttings</i>
	<i>4</i>				
	<i>25</i>			<i>SAND, fine to medium, moderate red to moderate reddish brown.</i>	
	<i>6</i>				
	<i>7</i>				
	<i>8</i>				
	<i>9</i>				
<i>3</i>	<i>30</i>			<i>As above</i>	
	<i>1</i>				
	<i>2</i>				
	<i>3</i>				
	<i>4</i>				
	<i>5</i>			<i>Color grades to dark yellowish orange</i>	<i>3/19/91</i> <i>3/26/91</i>
	<i>6</i>				
	<i>7</i>				
	<i>8</i>				
	<i>9</i>				
	<i>400</i>				

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Pile</i>		DATE <i>3/20/91</i>	SHEET <i>3</i> OF <i>6</i>
WELL NO. <i>FRT-4HP</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY <i>CB JANTA</i>		LOCATION	DRILLER
COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	4 0			<i>SAND, med to coarse, dark yellowish brown</i>	<i>Logged from</i>
	1			<i>well sorted, sub angular to sub rounded</i>	<i>auger cuttings</i>
	2			<i>with trace silt. Occasional pebbles</i>	
	3				
	4				
	4 5			<i>As above</i>	
	6				
	7				
	8				
	9				
	5 0			<i>As above</i>	
	1				
	2				
	3				
	4				
	5 5			<i>As above</i>	
	6				
	7				
	8				
	9				
	6 0			<i>As above</i>	

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie pile</i>		DATE <i>3/20/91</i>	SHEET <i>4</i> OF <i>6</i>
WELL NO. <i>FRT-4 HP</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY <i>CB Travis</i>		DRILLER	DRILLING METHOD

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	6 0			<i>SAND, med to coarse, dark yellowish orange, well sorted, subangular to subrounded with silt and occasional pebbles</i>	<i>Logged from auger cuttings</i>
	1				
	2				
	3				
	4				
	6 5			<i>As above, no pebbles</i>	<i>drilling easier</i>
	6				
	7				
	8				
	9				
	7 0			<i>As above, color grading to moderate reddish brown</i>	
	1				
	2				
	3				
	4				
	7 5			<i>grades with more silt</i>	<i>cuttings moist</i>
	6				
	7				
	8				
	9				
	8 0			<i>As above</i>	

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Pile</i>		DATE <i>3/20/91</i>	SHEET <i>5</i> OF <i>6</i>
WELL NO. <i>FRT-4 HP</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY <i>CB Travis</i>		DRILLER	
COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	8 0			<i>SAND, med to coarse, with silt and trace clay, sub angular to sub rounded moderate reddish brown</i>	<i>Loaded from auger cuttings</i>
	1				
	2				<i>cuttings damp</i>
	3				
	4				
	8 5			<i>As above</i>	
	6				
	7				
	8				
	9				
	9 0			<i>As above, color grading to pink to dark yellowish brown.</i>	
	1				
	2				
	3				
	4				
	9 5			<i>As above</i>	
	6				
	7				
	8				
	9				
	10 0			<i>As above</i>	<i>cuttings damp but not saturated.</i>

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie A'le</i>		DATE <i>3/20/91</i>	SHEET <i>6</i> OF <i>6</i>
WELL NO. <i>FRT-4HP</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY <i>CB Javira</i>		LOCATION	DRILLER
COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	100			<i>SAND, med to coarse, dark yellowish brown, ~15% silt and clay, damp</i>	<i>Logged from Auger cuttings</i>
	1				
	2				
	3				
	4				
	105			<i>As above</i>	
	6				
	7				
	8				
	9				
	110			<i>As above, cuttings more damp but not saturated</i>	
	1			<i>Cuttings saturated ~110.5-111 ft.</i>	
	2				
	3				
	4				
	115			<i>As above</i>	
	6				
	7				
	8				
	9				
	120			<i>As above</i>	
				<i>Boring complete at 120 ft at 1230, 3/20/91</i>	

WESTINGHOUSE SAVANNAH RIVER COMPANY
SOIL BORING PROCEDURES
SRS SOIL BORING INSTALLATION REPORT

Manual: DPSOP 254
Chapter: 3 (Draft 1)
Page: 1 of 2
Effective Date: 8/1/89
Organization: Environmental
Protection Section

SRS SOIL BORING INSTALLATION REPORT

GENERAL INFORMATION

Boring number FRT-3 HP Site E-Area Railroad Crosstie pile
Boring purpose Soil boring + water table sample
Project name Preliminary Characterization of the E-Area Railroad Crosstie pile
Custodian T. Bittler Custodial Dept CSWE
SRS Coordinates: North 79,872.19 East E 50,387.93
Or: Latitude _____ Longitude _____
Location description A recently bulldozed area adjacent to Crossties
Drilling contractor Graves Driller James Smith, # 861
Oversight contractor Sirrine Environmental Oversight C. B. Travis / Sean K. Asquith
Boring start date 31.20.91 Boring completion date 31.21.91

DRILLING INFORMATION

Note: Depths are measured from ground surface to the nearest 0.1 ft.

Type of drill rig used Swik Drill
Depth to static water level 93.9 ft
Total depth of boring 105 ft
Ground surface elevation (mean sea level) 280.3

	Hole			
Drilling Method	Diameter	From (ft.)	To (ft.)	Footage
Auger				
Hollowstem auger	<u>1.1</u>	<u>1.1</u>	<u>105.1</u>	<u>115</u>
Mud rotary				

Sample depths _____

WESTINGHOUSE SAVANNAH RIVER COMPANY

SOIL BORING PROCEDURES

SRS SOIL BORING INSTALLATION REPORT

Manual:

Chapter:

Page:

Effective Date:

Organization:

DPSOP 254

3 (Draft 1)

2 of 2

8/1/89

Environmental
Protection Section

Split spoon:

Sample depths 0.6 to 1.5, 1.5 to 3.0, 3.0 to 4.5, 4.5 to 6.0, 6.0 to 11.5,
15.0 to 16.5, 20.0 to 21.5

Other (specify): Water sample at ~ ^{CPT} 16.5 ft water surface

Sample depths

Disposition of samples Shipped to Weston Lab

Tests conducted on samples pH, TCLP, App IX Org, App IX Inorg
App IX VOA²⁰, RAD, App IX BVA, App IX metals

BORING ABANDONMENT

Material(s) used to abandon boring Neat cement grout with bentonite

Method of abandonment Pump Through Tremie

Proper abandonment verified by

Boring installation report prepared by

Company Sirrine

Date

31 22 191

COMMENTS

FIELD GEOLOGIC LOG

PROJECT F-Area Railroad Crosstie Site		DATE 3/20/91	SHEET 1 OF 6
Preliminary Characterization		DRILLING SUBCONTRACTOR Graves	
WELL NO. ERT-3HP	LOCATION N 79,872.19; E 50,387.93	DRILLER James Smith, #861	
LOGS PREPARED BY Charles J. Jara	COMPANY Sirrinc	DRILLING METHOD 6 1/4 inch H.S. Auger, 3" split spoon	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
1	0	Gravel with sand and clay - fill		Gravel with sand and clay - fill	
	1	Sand with cobbles, dark yellowish brown to moderate reddish brown		Sand with cobbles, dark yellowish brown to moderate reddish brown	
2	2				
	3				
3	4	Cobbles with sand, well rounded moderate reddish brown cobbles (white quartz)		Cobbles with sand, well rounded moderate reddish brown cobbles (white quartz)	
4	5	gravel with ~3" layer pale yellowish brown clay, then cobbles		gravel with ~3" layer pale yellowish brown clay, then cobbles	
	6				
	7				
	8				
	9				
5	10	SAND, med to coarse with cobbles and pebbles, yellowish brown, trace clay		SAND, med to coarse with cobbles and pebbles, yellowish brown, trace clay	
	11	upper portion of sample saturated, lower portion dry (perched water)		upper portion of sample saturated, lower portion dry (perched water)	
	12				
	13				
	14				
6	15	As above, some water trickling down from above.		As above, some water trickling down from above.	
	16				
	17				
	18				
	19				
	20				

FIELD GEOLOGIC LOG

PROJECT F-Area Railroad Crosstie Pile		DATE 3/20/91		SHEET 2 OF 6	
WELL NO. FRT-3HP		LOCATION		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY CB Zanna		COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
7	2 0	[Sketch of sand texture]		<u>SAND</u> med to coarse, moderate reddish brown grading to moderate red.	
	1			<u>SAND</u> is fine to fine, grayish red purple	
	2				
	3				
	4				
	2 5			As above, color moderate red to dusky red (blended by augers)	3/20/91 3/21/91
	6				
	7				
	8				
	9				
	3 0			As above	
	1				
	2				
	3				
	4				
	3 5			<u>Sand</u> fine to medium, dark yellowish orange, sub angular to sub rounded w/ 10-15% silt & clay	
	6				
	7				
	8				
	9				
	4 0			As above	

NOTE: Logged from auger cuttings below 21.5 ft

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Pile</i>		DATE <i>3/28/91</i>	SHEET <i>3</i> OF <i>6</i>
WELL NO. <i>FRT-3HP</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY <i>C.B. Travis</i>		DRILLER	
COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	40			<i>SAND med to coarse, dark yellowish orange, well sorted, sub angular to sub rounded with ~ 5% clay and silt, and occasional pebbles</i>	<i>Logged from 3' per cuttings</i>
	1				
	2				
	3				
	4				
	45			<i>As above</i>	
	6				
	7				
	8				
	9				
	50			<i>As above</i>	
	1				
	2				
	3				
	4				
	55			<i>As above</i>	
	6				
	7				
	8				
	9				
	60			<i>As above</i>	

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Pile</i>		DATE <i>3/27/91</i>	SHEET <i>4</i> OF <i>6</i>
WELL NO. <i>FRT-3HP</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY		DRILLER	DRILLING METHOD
LOCATION		COMPANY	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	6 0			<i>SAND, med to coarse, dark yellowish orange well sorted, subangular to sub rounded with ~16% clay and silt.</i>	<i>Logged from auger cuttings</i>
	1				
	2				
	3				
	4				
	6 5			<i>As above</i>	
	6				
	7			<i>color grading to moderate reddish brown</i>	
	8				
	9				
	7 0			<i>As above, cuttings moist grades with more silt</i>	
	1				
	2				
	3				
	4				
	7 5			<i>As above</i>	
	6				
	7				
	8				
	9				
	8 0			<i>As above</i>	

FIELD GEOLOGIC LOG

PROJECT F-Area Railroad Crosstie Pile		DATE 3/20/91	SHEET 5 of 6
WELL NO. FRT-3HP		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY CB Zarrin		LOCATION	DRILLER
COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	0			<u>Sand med to coarse, with silt</u>	<u>Logged from</u>
	1			<u>and clay (45%) moderate reddish</u>	<u>finger cuttings</u>
	2			<u>brown, sub angular to sub rounded</u>	
	3			<u>moist</u>	
	4				
	5			<u>As above</u>	
	6				
	7			<u>color grading to dark</u>	
	8			<u>yellowish brown</u>	
	9				
	10			<u>As above</u>	
	11				
	12				
	13				
	14				
	15			<u>As above, cuttings damp</u>	
	16				
	17				
	18				
	19				
	20			<u>As above, cuttings saturated</u>	

FIELD GEOLOGIC LOG

PROJECT <i>F-Area Railroad Crosstie Pile</i>		DATE <i>3/21/91</i>	SHEET <i>6</i> OF <i>6</i>
WELL NO. <i>FRT-3HP</i>		DRILLING SUBCONTRACTOR	
LOGS PREPARED BY <i>CB Juvia</i>		LOCATION	DRILLER
COMPANY		DRILLING METHOD	

RUN NUMBER	DEPTH BELOW GROUND SURFACE, FEET	LITHOLOGY	PERCENT RECOVERY	SAMPLE DESCRIPTION	DRILLING COMMENTS/REMARKS
	100			<i>SAND, med to coarse, dark yellowish orange brown, 10 to 15% silt and clay, wet</i>	<i>Logged from auger cuttings</i>
	1				
	2				
	3				
	4				
	5				
	6				
	7				
	8				
	9				
	10				
	11				
	12				
	13				
	14				
	15				
	16				
	17				
	18				
	19				
	20				
	21				
	22				
	23				
	24				
	25				
	26				
	27				
	28				
	29				
	30				
	31				
	32				
	33				
	34				
	35				
	36				
	37				
	38				
	39				
	40				
	41				
	42				
	43				
	44				
	45				
	46				
	47				
	48				
	49				
	50				
	51				
	52				
	53				
	54				
	55				
	56				
	57				
	58				
	59				
	60				
	61				
	62				
	63				
	64				
	65				
	66				
	67				
	68				
	69				
	70				
	71				
	72				
	73				
	74				
	75				
	76				
	77				
	78				
	79				
	80				
	81				
	82				
	83				
	84				
	85				
	86				
	87				
	88				
	89				
	90				
	91				
	92				
	93				
	94				
	95				
	96				
	97				
	98				
	99				
	100				

Boring complete at 105 ft at 1230, 3/21/91

END

**DATE
FILMED**

6 / 29 / 92