EPRI

**DOE/MC/23167-3056
(DE92001119)**

**ADVANCED COAL-FUELED GAS TURBINE SYSTEMS REFERENCE SYSTEM
DEFINITION UPDATE**

Topical Report

September 1991

Work Performed Under Contract No. AC21-86MC23167

**For
U.S. Department of Energy
Morgantown Energy Technology Center
Morgantown, West Virginia**

**By
Westinghouse Electric Corporation
Orlando, Florida**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

DOE/MC/23167--3056

DE92 001119

**Advanced Coal-Fueled Gas Turbine Systems
Reference System Definition Update**

Topical Report

Work Performed Under Contract No.: DE-AC21-86MC23167

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
Westinghouse Electric Corporation
Power Generation Business Unit
4400 Alafaya Trail
Orlando, Florida 32826-2399**

September 1991

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
BACKGROUND.....	vi
1 EXECUTIVE SUMMARY.....	1-1
2 PLANT PERFORMANCE.....	2-1
2.1 Assumptions.....	2-1
2.2 Performance.....	2-2
2.3 Emission Goals.....	2-18
3 ECONOMICS.....	3-1
3.1 Economic Assumptions.....	3-1
3.1.1 Criterion: Cost of Electricity.....	3-1
3.1.2 Power Plant Definition.....	3-1
3.1.3 Plant Financial Data.....	3-3
3.1.4 COE of Conventional Plants.....	3-4
3.2 Cost of Electricity Calculations.....	3-15
3.2.1 Total Plant Cost.....	3-15
3.2.2 Total Plant Investment.....	3-19
3.2.3 Total Capital Requirements.....	3-19
3.3 Operation and Maintenance Cost.....	3-21
3.3.1 Operating Costs.....	3-21
3.3.2 Maintenance Costs.....	3-22
3.3.3 Fixed and Variable Components.....	3-22
3.4 Fuel and Consumables.....	3-23
3.5 Cost of Electricity Estimate.....	3-24
3.6 COE of a Mature Plant.....	3-25
4 SLAGGING COMBUSTOR DESCRIPTION.....	4-1
4.1 Slagging Combustor Concept.....	4-1
4.2 Particulate Control.....	4-2
4.3 Sulfur Control.....	4-2
4.4 Nitrogen Oxide Control.....	4-3
4.5 Alkali Control.....	4-3
5 ECONOMIC SENSITIVITY STUDIES.....	5-1
5.1 Combustor Outlet Temperature.....	5-1
5.2 Slurry Chemical Expense.....	5-3
5.3 Sulfur Capture.....	5-3
5.4 Combustor Capital Cost.....	5-7
5.5 Turbine Reblading Interval.....	5-7
5.6 Combustor Pressure Loss.....	5-9
5.7 Combustor Heat Rejection.....	5-10
5.8 Natural Gas Prices.....	5-12
5.9 Coal Beneficiation.....	5-13

TABLE OF CONTENTS (Continued)

6	PLANT DESCRIPTION.....	6-1
6.1	Fuel Processing.....	6-1
6.2	Combustion Turbine Assembly.....	6-4
6.3	Steam Turbine Cycle.....	6-8
6.4	Slag Disposal System.....	6-9
APPENDIX A	LICADO Coal Cleaning Process.....	A-1
APPENDIX B	Other Coal Cleaning Processes.....	B-1

LIST OF TABLES

<u>Tables</u>	<u>Page</u>
1-1	1-2
1-2	1-3
2-1	2-1
2-2	2-9
2-3	2-12
2-4	2-15
2-5	2-15
2-6	2-17
2-7	2-18
3-1	3-2
3-2	3-2
3-3	3-3
3-4	3-3
3-5	3-4
3-6	3-4
3-7	3-5
3-8	3-6
3-9	3-6
3-10	3-8
3-11	3-9
3-12	3-11
3-13	3-12
3-14	3-13
3-15	3-14
3-16	3-17
3-17	3-17
3-18	3-18
3-19	3-18
3-20	3-20
3-21	3-21
3-22	3-22
3-23	3-23
3-24	3-24
3-25	3-25
3-26	3-25
5-1	5-1
5-2	5-2
5-3	5-3
5-4	5-5
5-5	5-5
5-6	5-6
5-7	5-7
5-8	5-8
5-9	5-9
5-10	5-10
5-11	5-10
5-12	5-11

LIST OF TABLES

<u>Tables</u>		<u>Page</u>
5-13	Comparative Rankings	5-14
5-14	Performance Comparisons	5-14
5-15	Capital Cost Comparisons	5-15
5-15	COE Comparisons	5-15
6-1	Fuel Processing Characteristics	6-1
6-2	Coal and CWM Characteristics	6-1
6-3	Combustion Turbine Performance Data	6-4
6-4	Combustion Turbine Stream Data	6-5
6-5	Turbine Performance with Natural Gas	6-6
6-6	Steam Turbine Performance Data	6-9
B-1	Key Cost and Design Parameters	B-3
B-2	Process Consumables	B-5

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
1-1	Comparison of COE for Conventional Power Plants and PC and CWM CFCTCC Reference Plants	1-3
2-1	Power System Arrangement	2-3
2-2	Block Flow Diagram - Direct Coal-Fueled Combined Cycle	2-4
2-3	Slagging Combustor Process Flow Diagram	2-5
2-4	Combustion Turbine Cycle	2-6
2-5	Heat Recovery Steam Generator	2-7
2-6	Steam Turbine Cycle	2-8
3-1	COE Calculation Model	3-16
5-1	COE Margin vs. Firing Temperature	5-2
5-2	COE Margin vs. Ca/S Ratio	5-4
5-3	COE Margin for Plant with FGD	5-4
5-4	COE Margin vs. Fe/S Ratios with FGD	5-6
5-5	COE Margin vs. Turbine Reblading Intervals	5-8
5-6	COE Margin vs. Combustor/Cyclone Pressure Drop	5-9
5-7	COE Margin vs. Combustor Cooling (Rejected Heat Used)	5-11
5-8	COE Margin vs. Combustion Cooling (Energy Lost from Cycle)	5-12
5-9	COE Margin Sensitivity to Natural Gas Prices	5-13
6-1	Direct Coal-Fired Combustion Turbine System	6-10
A-1	LICADO Flow Diagram	A-2

BACKGROUND

The objective of the Direct Coal-Fueled 80 MW Combustion Turbine Program is to establish the technology required for private sector use of an advanced coal-fueled combustion turbine power system. The system is to burn low-cost, utility-grade coal, and yet meet the EPA New Source Performance Standards for coal-fired steam generators. Plant thermal efficiency is to surpass competing coal-utilization cycles.

Under this program the technology for a direct coal-fueled 80 MW combustion turbine is to be developed. This unit would be an element in a 207 MW direct coal-fueled combustion turbine combined cycle which includes two combustion turbines, two heat recovery steam generators and a steam turbine.

Key to meeting the program objectives is the development of a successful high pressure slagging combustor that burns coal, while removing sulfur, particulates, and corrosive alkali matter from the combustion products. Westinghouse and Textron (formerly AVCO Research Laboratory/Textron) have designed and fabricated a subscale slagging combustor. This slagging combustor, under test since September 1988, has been yielding important experimental data, while having undergone several design iterations.

Therefore, it is the objective of this report to provide the current effort to evaluate the relative economic benefits of various design and process options for the direct coal-fueled combustion turbine combined cycle.

In particular the report discusses the following:

- 1) The assumptions, performance and emission goals of the two reference coal-fueled combustion turbine systems which burn either pulverized coal (PC) or coal-water mixture (CWM).
- 2) Plant economics; the assumptions made, cost of electricity calculations (COE), estimates for operation and maintenance, consumables and COE, and the COE of a mature plant.
- 3) Description of the slagging combustor which includes the concept and how particulates, sulfur, nitrogen oxide and alkali are controlled.
- 4) Economic sensitivity studies; an assessment of the influence of different parameters on the COE margin of the CWM-fueled plant.
- 5) Description of the coal-fueled gas turbine combined cycle power plant.

1 EXECUTIVE SUMMARY

Previous conceptual design studies indicated that a combustion turbine combined cycle fueled by utility-grade pulverized coal could operate with a cost of electricity (COE) lower than the COE of a conventional pulverized coal power plant. The key component of this direct-fired system is a slagging combustor that burns coal while removing sulfur, particulates, and corrosive alkali matter from the combustion products.

Subscale development testing of a unique slagging combustor design has been yielding important experimental data since September 1988, and it is now appropriate to update and expand the previous conceptual design studies.

This report contains the current effort to evaluate the relative economic benefits of various design and process options for the direct coal-fueled combustion turbine combined cycle. A power system computer model is used to compare the proposed design alternatives with a conventional coal-fired steam turbine power plant and conventional combustion turbine combined cycles in terms of performance, capital cost, and cost of electricity. All performance data is based on the higher heating value (HHV) of the fuel and all costs are in 1989 dollars.

The technical assumptions on which the current standard Westinghouse coal-fueled combustion turbine combined cycle (CFCTCC) is based includes: using Pittsburgh No. 8 coal (standard utility grade); ambient conditions of 14.7 psia, 59°F, and a relative humidity of 60%; NSPS emissions criteria; use of a slagging combustor whose rich/lean zone reduces NO_x formation; use of limestone as a sorbent to capture sulfur ($\text{Ca/S}=2$); use of slagging cyclone separators to reduce particulate matter and solid alkali; combustor outlet temperature of 1850°F; maximum turbine metal temperature of 1650°F; pressure drop of 7% through the slagging combustor system; and, partial recovery of an 8% combustor heat loss.

The economics and performance of the CFCTCC reference plant were compared to three conventional plants: a 220 MW conventional pulverized coal-fired steam turbine generator plant with flue gas desulfurizer (FGD) (This plant, PC-FGD, is fueled with Pittsburgh No. 8 coal), and two combustion turbine combined cycles (CTCC) plants, one fueled with distillate oil and the other plant fueled with natural gas. The sizes of the comparison plants were chosen to approximate the generating capacity of the CFCTCC reference systems.

The design values on which the costs were based reflect generic design conditions for the conventional plants. Table 1-1 summarizes the design conditions of each plant. Pittsburgh No. 8 coal was priced at \$1.80/MMBtu and gas and oil were priced at \$4.00/MMBtu delivered to the power plants studied. These prices are based on the HHV of the fuels.

Capital costs for the PC-FGD plant were developed consistent with the cost basis of the reference CFCTCC. The conceptual cost estimate for the PC-FGD plant is intended to cover a complete plant, including all equipment, materials, labor and construction support.

Table 1-1. Conventional Plants - Design Conditions

Plant Type	PC-FGD	CTCC, gas	CTCC, oil
Plant Output, MW	220	262	258
Fuel Type	Pgh. 8 Coal	Nat Gas	No. 2 Oil
Fuel HHV, Btu per	13,555/lb	1,035/SCF	138,690/gal
Plant Heat Rate, Btu/kWh	9,960	8,208	8,227
Boiler	Subcrit	Subcrit	Subcrit
Steam Turbine Generator [1]	TC/2F	TC/2F	TC/2F
Cooling Tower [2]	MD, Wet	MD, Wet	MD, Wet
Sulfur Control System	Limestone FGD	none	none
Fuel Cost, \$/MMBtu	\$1.80	\$4.00	\$4.00
Construction Time, yrs	3.5	2.0	2.0
Book Life, yrs	30	30	30
TPC Year	Dec 1989	Dec 1989	Dec 1989
TPI Year	Jan 1990	Jan 1990	Jan 1990
Capacity Factor	70%	70%	70%

[1] Tandem Compound, Double Flow

[2] Mechanical Draft, Wet

The costing bases for the two combined cycle plants are also consistent with the reference CFCTCC plants. Power is produced by two combustion turbines and one steam turbine with a combined output of around 260 MW.

The 30-year levelized costs of electricity (\$/MWh) for the three conventional plants and the two CFCTCC reference plants are: 94.4 (PC-FGD), 84.1 (CTCC, gas), 85.2 (CTCC, oil), 84.05 (CWM-CFCTCC), and 77.51 (PC-CFCTCC). The COEs of the CFCTCC are lower than the PC-FGD, by 11% and 17.9% for the CWM and PC plants, respectively and comparable to the gas and oil-fired combined cycles.

In Figure 1-1, the COE for the three conventional and two coal-fueled combined cycles studied is divided into the cost areas of capital and maintenance, consumables and fuel. Capital and maintenance costs dominate the PC-FGD COE, while the COE of the oil-and gas-fired combined cycles is set and controlled by the fuel costs.

As would be expected, the COE of the coal-fueled combined cycles has a large capital and maintenance cost and also a large consumable cost when compared to a gas-or oil-fired combined cycle plant. The CWM plant consumable costs are higher than for a PC combined cycle plant due to the costs associated with making the slurry.

The CFCTCC power plant performance is summarized in Table 1-2. The CWM plant generates 9.5 MWs more power than the PC plant, but has a plant cycle efficiency which is lower by 1.8 percentage points. Evaporation of the water contained in the CWM causes this phenomenon to occur.

Figure 1-1. Comparison of COE for Conventional Power Plants and PC and CWM CFCTCC Reference Plants

Table 1-2. Summary of CFCTCC Power Plant Performance

Plant Type	CWM	PC
Combustion Turbine Net Power (MW)	172.1	161.3
Steam Turbine Net Power (MW)	63.9	62.6
Fuel Processing & Auxiliary Power (MW)	(4.7)	(2.0)
Net Power Generation (MW)	231.3	221.8
Net Heat Rate (Btu/kWh)	8924.0	8536.0
Efficiency (Percent)	38.2	40.0

Sensitivity studies were also performed using the reference system computer model to assess the influence of certain parameters on the COE margin of the CWM and PC CFCTCC plants. Some of the parameters studied included: combustor outlet temperature, combustion turbine blading interval, Ca/S ratio and possible FGD installation, combustor pressure loss, combustor heat rejection, and slurry chemical expense and coal beneficiation. A detailed review of these and other parameters are contained in Chapter 5.

The coal beneficiation processes studied are discussed in Appendices A and B. Appendix A discusses the LICADO process which was developed by Westinghouse and the University of Pittsburgh, and funded by the Department of Energy and the Pennsylvania Energy Development Authority. Appendix B discusses three other physical coal cleaning and two chemical coal cleaning processes that were selected to represent alternatives to LICADO coal cleaning and no coal cleaning.

This report provides an update on the economics of a CFCTCC plant. Comparisons were made between combined cycle plants fueled with PC, CWM, natural gas and oil, and with a standard 220 MW PC-FGD plant. When compared against the PC-FGD plant, the economics today show COE margins for combined cycle plants fueled with PC, CWM, gas and oil of 17.9, 11.0, 10.9 and 9.7 percent, respectively. When coal prices are compared against a rising price in gas or oil, the economics immediately become more favorable to a coal-fueled based power process.

2 PLANT PERFORMANCE

There are two Reference System power plants -- one fueled by 60/40 coal-water mixture (CWM) and the other fueled by dry pulverized coal (PC). Each plant is a combustion turbine combined cycle, in which power is generated by two gas turbines, one steam turbine and two heat recovery steam generators (HRSGs). This configuration combines the low cost of domestic coal with the high efficiency of a gas turbine combined cycle plant.

The characteristics of the Reference Systems are summarized in Table 2-1 and described in more detail in later sections. Throughout this report, all heating values, heat rates, and efficiencies are calculated on the basis of higher heating value (HHV) of the fuel.

Table 2-1. Reference System Plant Performance

Turbine Fuel	PC	60/40 CWM	
Coal Feed Rate	139,702	152,289	lb/h
Limestone Feed Rate	27,543	30,025	lb/h
Coal HHV	13,555	13,555	Btu/lb
Plant Thermal Input (HHV)	1,894	2,064	MMBtu/h
Gas Turbine Net Power	161,304	172,136	kW
Steam Turbine Net Power	62,555	63,917	kW
Plant Auxiliary Power	(2,013)	(4,736)	kW
Net Power Generation	221,845	231,316	kW
Net Heat Rate (HHV)	8,536	8,924	Btu/kWh
Net Electric Efficiency (HHV)	40.0	38.2	%

Figure 2.1 is a schematic representation of the physical configuration of the Reference System. Some of the thermal subsystems, such as combustors, cyclones, and gas turbines, consist of multiple components arranged in parallel. In order to facilitate comparisons with other power systems, all performance and cost values in this report are the combined values for all parallel streams unless otherwise specified.

2.1 Assumptions

The technical assumptions on which the current standard Westinghouse CFCTCC is based include: using Pittsburgh No. 8 coal (standard utility grade); ambient conditions of 14.7 psia, 59°F, and a relative humidity of 60%; NSPS emissions criteria; use of a slagging combustor whose rich/lean zone reduces NO_x formation; use of limestone as a sorbent to capture sulfur (Ca/S=2); Use of slagging cyclone to reduce particulate matter and solid alkali; combustor outlet temperature of 1850°F; maximum turbine metal temperature of 1650°F; pressure drop of 7% through the slagging combustor system; and, partial recovery of the combustor heat loss of 8%.

It should be noted that the combustor outlet temperature (COT) is a convenient thermodynamic parameter for system analysis, but it is not the same as the turbine inlet temperature (TIT). The TIT is defined as the flow-weighted mean total temperature of the working fluid relative to a stationary plane immediately upstream of the first stage rotor blade. For cooled turbines, the COT is higher than the TIT.

2.2 Performance

Although the performance of the two Reference Systems are similar, as shown in Table 2-1, the Reference System fueled by coal-water mixture generates 4.3 percent more power at a 4.6-percent worse heat rate than the system fueled by dry coal. The increased power is due to the added turbine mass flow provided by the slurry water. But the evaporation of the water uses some of the thermal energy of the coal, resulting in reduced efficiency.

Figures 2-2 through 2-6 are the flowsheets for both Reference Systems. The numbered streams on the flowsheets correspond to the locations listed in Tables 2-2 and 2-3, which contain thermodynamic data for the streams for the CWM fueled reference system and dry coal-fueled Reference System, respectively. The arithmetic signs +/- of the flows in the data tables correspond to flow directions in the accompanying flow diagrams. The negative flow in stream 89 indicates that steam is extracted from the LP steam turbine, rather than inducted to it.

The electric power generation and use in both systems are compared in Table 2-4. Tables 2-5 and 2-6 are the energy and material balances for the two Reference Systems. The radiation losses listed in the energy balances represent 8.4% of the lower heating value energy of the coal fuel, and include all losses associated with the slagging combustor, slag disposal systems, connecting duct, and ancillary cleanup equipment.

Figure 2-1. Power System Arrangement

Figure 2-2. Block Flow Diagram - Direct Coal-Fueled Combined Cycle

Figure 2-3. Slagging Combustor Process Flow Diagram

Figure 2-4. Combustion Turbine Cycle

Figure 2-5. Heat Recovery Steam Generator

Figure 2-6. Steam Turbine Cycle

Table 2-2. CWM Coal-Fueled Combined Cycle Thermodynamic Data

LOC	DESCRIPTION	ENTHAL BTU/LB	PRESS PSIA	QUAL -	SPVOL CUFT/LB	TEMP F	WTFLO LB/H
1	Ambient Air	28.52	14.70	.00	13.13	59.00	0.
2	Ambient Water	19.56	14.70	.00	.02	51.46	0.
3	Dry Coal Feed	75.02	.00	.00	.00	59.00	152289.
4		.00	.00	.00	.00	.00	0.
5	CWM	75.02	.00	.00	.01	59.00	253815.
6		.00	.00	.00	.00	.00	0.
7		.00	.00	.00	.00	60.00	0.
8		.00	.00	.00	.00	.00	0.
9		.00	.00	.00	.00	.00	0.
10		.00	.00	.00	.00	.00	0.
11		.00	.00	.00	.00	.00	0.
12		.00	.00	.00	.00	.00	0.
13		.00	.00	.00	.00	.00	0.
14		.00	.00	.00	.00	.00	0.
15		.00	.00	.00	.00	.00	0.
16	Comp Proc Air Ex	.00	.00	.00	.00	.00	0.
17	Comprsr Air Inlt	28.52	14.70	.00	13.13	59.00	5395896.
18	LP Comp Air Inlt	28.52	14.55	.00	13.26	59.00	5395896.
19	LP Comp LP Coolg	137.98	105.30	.00	3.41	507.05	118845.
20	LP Comp HP Coolg	190.24	203.69	.00	2.14	714.06	393861.
21		.00	.00	.00	.00	.00	0.
22		.00	.00	.00	.00	.00	0.
23		.00	.00	.00	.00	.00	0.
24	LP Comp Air Exit	190.24	199.30	.00	2.14	714.06	4883190.
25	HP Comp Air Inlt	190.24	199.30	.00	2.14	714.06	4883190.
26	HP Comp LP Coolg	.00	.00	.00	.00	.00	0.
27	HP Comp HP Coolg	.00	.00	.00	.00	.00	0.
28	HP Comp Air Exit	190.24	199.30	.00	2.14	714.06	4883190.
29	HP Brnr Air Inlt	190.24	199.30	.00	2.14	714.06	4883190.
30	HP Brnr Gas Exit	.00	.00	.00	.00	.00	0.
31	HP Turb HP Coolg	.00	.00	.00	.00	.00	0.
32	HP Turb LP Coolg	.00	.00	.00	.00	.00	0.
33	HP Expander Exit	190.24	199.30	.00	2.14	714.06	4883190.
34	LP Brnr Gas Exit	517.65	185.35	.00	4.63	1850.00	5130836.
35	LP Turb HP Coolg	171.52	202.76	.00	2.14	640.50	393861.
36	LP Turb LP Coolg	137.98	103.24	.00	3.41	507.05	118845.
37		.00	.00	.00	.00	.00	0.
38		.00	.00	.00	.00	.00	0.
39		.00	.00	.00	.00	.00	0.
40	LP Expander Exit	195.11	15.13	.00	31.56	713.72	5643542.
41		.00	.00	.00	.00	.00	0.
42		.00	.00	.00	.00	.00	0.
43	Turbine Exhaust	195.11	15.13	.00	28.81	713.72	5643542.
44	Comprsr Spray In	.00	.00	.00	.00	.00	0.

Table 2-2. CWM Coal-Fueled Combined Cycle Thermodynamic Data
(Continued)

LOC	DESCRIPTION	ENTHAL BTU/LB	PRESS PSIA	QUAL -	SPVOL CUFT/LB	TEMP F	WTFLO LB/H
45	HP Brnr Fuel Inl	75.02	280.74	.00	.01	59.00	0.
46	HP Brnr H2O Injc	.00	.00	1.00	.00	.00	0.
47	LP Brnr Fuel Inl	75.02	280.74	.00	.01	59.00	253815.
48	LP Brnr H2O Injc	-1007.00	.00	1.00	.00	.00	0.
49	Gas Turbine Fuel	75.02	280.74	.00	.00	59.00	253815.
50	Intrclr Wtr Inlt	.00	14.70	.00	.00	59.00	0.
51	Intrclr Wtr Exit	.00	.00	.00	.00	.00	0.
52	Recuper LP Air I	.00	.00	.00	.00	.00	0.
53	Recuper LP Air O	.00	.00	.00	.00	.00	0.
54	Rec Cmp Air Inlt	.00	.00	.00	.00	.00	0.
55	Recuper HF Air I	.00	.00	.00	.00	.00	0.
56	Recuper Cwtr Inl	.00	.00	.00	.00	.00	0.
57	Recuper Cwtr Out	.00	.00	.00	.00	.00	0.
58	HRSO LP Stm Supp	19.56	14.70	1.00	.02	51.46	0.
59	HRSO IP Stm Supp	.00	100.97	1.00	.00	.00	0.
60	HRSO HP Stm Supp	.00	403.90	1.00	.00	.00	0.
61	HRSO Zone Gas In	195.11	15.13	.00	28.81	713.72	5643542.
62	HRSO Gas Inlt	195.11	15.13	.00	28.81	713.72	5643542.
63	Reheatr Gas Inlt	195.11	15.13	.00	28.81	713.72	2897509.
64	Reheatr Gas Exit	169.62	15.05	.00	26.56	616.58	2897509.
65	HP Suph Gas Inlt	195.11	15.13	.00	28.81	713.72	2746034.
66	HP Suph Gas Exit	169.62	15.05	.00	26.56	616.58	2746034.
67	HP Evap Gas Inlt	169.62	15.05	.00	24.61	616.58	5643542.
68	HP Evap Gas Exit	130.62	14.98	.00	22.95	465.54	5643542.
69	HP Econ Gas Inlt	130.62	14.98	.00	22.95	465.54	5643542.
70	HP Econ Gas Exit	120.36	14.91	.00	22.06	425.33	5643542.
71	IP Suph Gas Inlt	.00	.00	.00	.00	.00	0.
72	IP Suph Gas Exit	.00	.00	.00	.00	.00	0.
73	IP Evap Gas Inlt	120.36	14.91	.00	21.37	425.33	5643542.
74	IP Evap Gas Exit	107.80	14.83	.00	20.92	375.79	5643542.
75	IP Econ Gas Inlt	107.80	14.83	.00	20.92	375.79	5643542.
76	IP Econ Gas Exit	103.20	14.76	.00	20.56	357.61	5643542.
77	LP Suph Gas Inlt	.00	.00	.00	.00	.00	0.
78	LP Suph Gas Exit	.00	.00	.00	.00	.00	0.
79	LP Evap Gas Inlt	103.20	14.76	.00	19.75	357.61	5643542.
80	LP Evap Gas Exit	88.23	14.70	.00	19.15	289.06	5643542.
81	HRSO Gas Exit	88.23	14.70	.00	19.15	298.06	5643542.
82	Makeup Water	19.56	14.70	.00	.02	51.46	0.
83	HRSO LP Deaer In	60.98	30.00	.00	.02	92.86	543073.
84	LP Daer Wtr Exit	218.93	30.00	.00	.02	250.34	544420.
85	LP Evap Stm Drum	75.45	30.00	.00	.02	107.40	125294.
86	LP Evap Tube Inl	75.95	162.11	.00	.02	107.40	125294.
87	LP Evap Tube Out	750.03	30.00	.56	7.73	250.34	125294.

Table 2-2. CWM Coal-Fueled Combined Cycle Thermodynamic Data
(Continued)

LOC	DESCRIPTION	ENTHAL BTU/LB	PRESS PSIA	QUAL -	SPVOL CUFT/LB	TEMP F	WTFLO LB/H
88	LP Evap Stm Exit	1164.15	30.00	.00	13.74	250.34	-1348.
89	LP Suph Stm Exit	1164.15	30.00	.00	13.74	250.34	-1348.
90	IP Econ Wtr Inlt	220.63	488.72	.00	.00	251.08	544420.
91	IP Evap Wtr Inlt	268.25	100.97	.00	.00	298.53	544420.
92	IP Evap Stm Drum	273.52	100.97	.00	.02	303.65	92962.
93	IP Evap Tube Inl	274.21	269.88	.00	.02	303.65	92962.
94	IP Evap Tube Out	1036.41	100.97	.83	3.65	328.53	92962.
95	IP Evap Stm Exit	1187.34	100.97	.00	4.39	328.53	77163.
96	IP Suph Stm Exit	1187.34	100.97	.00	4.39	328.53	77163.
97	HP Econ Wtr Inlt	268.25	444.29	.00	.00	298.53	467257.
98	HP Evap Wtr Inlt	392.12	403.90	.00	.00	415.55	467257.
99	HP Evap Stm Drum	393.76	403.90	.00	.02	417.05	294762.
100	HP Evap Tube Inl	394.25	517.18	.00	.02	417.05	294762.
101	HP Evap Tube Out	1140.43	403.90	.92	1.06	445.55	294762.
102	HP Evap Stm Exit	1204.62	403.90	.00	1.15	445.55	467257.
103	Reheatr Stm Inlt	1231.89	100.97	1.00	5.04	422.90	535075.
104	Throttle Steam	1354.42	367.18	.00	1.77	680.00	467257.
105	Hot Rht Exit	1369.92	91.80	1.00	7.32	680.00	535075.
106	Stm Trb Stm Inlt	1354.42	367.18	1.00	1.77	680.00	457912.
107	Stm Trb HP Leak	1354.42	367.18	.00	1.77	680.00	9345.
108	HP Stm Trb Exit	1237.21	100.97	1.00	5.01	418.77	457912.
109	Stm Trb Lp Inlet	1265.14	30.00	1.00	18.05	456.74	543073.
110	Stm Trb Stm Exit	1053.22	.76	.95	410.19	92.86	543073.
111	Condnsr Stm Inlt	1053.22	.76	.95	410.19	92.86	543073.
112	Cndnsr Cnd Exit	60.87	.76	.00	.02	92.86	543073.
113	Clg Twr Air Inlt	28.52	14.75	.00	.00	59.00	3527057.
114	Clg Twr Air Exit	181.31	14.70	.00	.00	75.88	3527057.
115	HRSB AB Fuel Gas	.00	.00	.00	.00	.00	0.
116	Sorbent Inlet	.00	.00	.00	.00	59.00	30025.
117	Gas Midpoint	.00	.00	.00	.00	.00	0.
118	Slag Exit	551.93	.00	.00	.00	1850.00	36193.
119	Slg Clr Pump Inl	393.76	403.90	.00	.02	417.05	2857492.
120	Hot Cycl CW Inlt	394.88	660.28	.00	.02	417.85	2857492.
121	Slg Comb CW Inlt	394.88	660.28	.00	.02	417.85	2857492.
122	Slg Comb CW Exit	450.72	660.28	.00	.02	468.02	2857492.
123	Cold Gt Fuel Gas	75.02	.00	.00	.01	59.00	253815.

Water Dewpoint 97.1
Stack Exit Temp 300.2

Table 2-3. Dry Coal-Fueled Combined Cycle Thermodynamic Data

LOC	DESCRIPTION	ENTHAL BTU/LB	PRESS PSIA	QUAL -	SPVOL CUFT/LB	TEMP F	WTFLO LB/H
1	Ambient Air	28.52	14.70	.00	13.13	59.00	0.
2	Ambient Water	19.56	14.70	.00	.02	51.46	0.
3	Dry Coal Feed	46.08	.00	.00	.00	60.00	139702.
4		.00	.00	.00	.00	.00	0.
5	Coal Fuel Feed	46.08	.00	.00	.01	60.00	139702.
6		.00	.00	.00	.00	.00	0.
7		.00	.00	.00	.00	60.00	0.
8		.00	.00	.00	.00	.00	0.
9		.00	.00	.00	.00	.00	0.
10		.00	.00	.00	.00	.00	0.
11		.00	.00	.00	.00	.00	0.
12		.00	.00	.00	.00	.00	0.
13		.00	.00	.00	.00	.00	0.
14		.00	.00	.00	.00	.00	0.
15		.00	.00	.00	.00	.00	0.
16	Comp Proc Air Ex	.00	.00	.00	.00	.00	0.
17	Comprsr Air Inlt	28.52	14.70	.00	13.13	59.00	5395896.
18	LP Comp Air Inlt	28.52	14.55	.00	13.26	59.00	5395896.
19	LP Comp LP Coolg	137.98	105.30	.00	3.41	507.05	117232.
20	LP Comp HP Coolg	190.24	203.69	.00	2.14	714.06	388515.
21		.00	.00	.00	.00	.00	0.
22		.00	.00	.00	.00	.00	0.
23		.00	.00	.00	.00	.00	0.
24	LP Comp Air Exit	190.24	199.30	.00	2.14	714.06	4890149.
25	HP Comp Air Inlt	190.24	199.30	.00	2.14	714.06	4890149.
26	HP Comp LP Coolg	.00	.00	.00	.00	.00	0.
27	HP Comp HP Coolg	.00	.00	.00	.00	.00	0.
28	HP Comp Air Exit	190.24	199.30	.00	2.14	714.06	4890149.
29	HP Brnr Air Inlt	190.24	199.30	.00	2.14	714.06	4890149.
30	HP Brnr Gas Exit	.00	.00	.00	.00	.00	0.
31	HP Turb HP Coolg	.00	.00	.00	.00	.00	0.
32	HP Turb LP Coolg	.00	.00	.00	.00	.00	0.
33	HP Expander Exit	190.24	199.30	.00	2.14	714.06	4890149.
34	LP Brnr Gas Exit	510.00	185.35	.00	4.59	1850.00	5048972.
35	LP Turb HP Coolg	171.52	202.76	.00	2.14	540.50	388515.
36	LP Turb LP Coolg	137.98	103.24	.00	3.41	507.05	117232.
37		.00	.00	.00	.00	.00	0.
38		.00	.00	.00	.00	.00	0.
39		.00	.00	.00	.00	.00	0.
40	LP Expander Exit	192.73	15.13	.00	31.18	713.73	5554719.
41		.00	.00	.00	.00	.00	0.
42		.00	.00	.00	.00	.00	0.
43	Turbine Exhaust	192.73	15.13	.00	28.60	713.73	5554719.
44	Comprsr Spray In	.00	.00	.00	.00	.00	0.
45	HP Brnr Fuel Inl	46.08	280.74	.00	.01	60.00	0.

Table 2-3. Dry Coal-Fueled Combined Cycle Thermodynamic Data
(Continued)

LOC	DESCRIPTION	ENTHAL BTU/LB	PRESS PSIA	QUAL -	SPVOL CUFT/LB	TEMP F	WTFLO LB/H
46	HP Brnr H2O Injc	.00	.00	1.00	.02	.00	0.
47	LP Brnr Fuel Inl	46.08	280.74	.00	.01	60.00	139702.
48	LP Brnr H2O Injc	-31.68	280.74	1.00	.02	.00	24779.
49	Gas Turbine Fuel	46.08	280.74	.00	.01	60.00	139702.
50	Intrclr Wtr Inlt	.00	14.70	.00	.00	59.00	0.
51	Intrclr Wtr Exit	.00	.00	.00	.00	.00	0.
52	Recuper LP Air I	.00	.00	.00	.00	.00	0.
53	Recuper LP Air O	.00	.00	.00	.00	.00	0.
54	Rec Cmp Air Inlt	.00	.00	.00	.00	.00	0.
55	Recuper HP Air I	.00	.00	.00	.00	.00	0.
56	Recuper Cwtr Inl	.00	.00	.00	.00	.00	0.
57	Recuper Cwtr Out	.00	.00	.00	.00	.00	0.
58	HRSO LP Stm Supp	19.56	14.70	1.00	.02	51.46	-24779.
59	HRSO IP Stm Supp	.00	100.97	1.00	.00	.00	0.
60	HRSO HP Stm Supp	-31.68	403.90	1.00	.02	.00	24779.
61	HRSO Zone Gas In	192.73	15.13	.00	28.60	713.73	5554719.
62	HRSO Gas Inlt	192.73	15.13	.00	28.60	713.73	5554719.
63	Reheatr Gas Inlt	192.73	15.13	.00	28.60	713.73	2865183.
64	Reheatr Gas Exit	167.38	15.05	.00	26.35	615.87	2865183.
65	HP Suph Gas Inlt	192.73	15.13	.00	28.60	713.73	2689536.
66	HP Suph Gas Exit	167.38	15.05	.00	26.35	615.87	2689536.
67	HP Evap Gas Inlt	167.38	15.05	.00	24.61	615.87	5554719.
68	HP Evap Gas Exit	129.06	14.98	.00	22.78	465.54	5554719.
69	HP Econ Gas Inlt	129.06	14.98	.00	22.78	465.54	5554719.
70	HP Econ Gas Exit	118.36	14.91	.00	21.84	423.05	5554719.
71	IP Suph Gas Inlt	.00	.00	.00	.00	.00	0.
72	IP Suph Gas Exit	.00	.00	.00	.00	.00	0.
73	IP Evap Gas Inlt	118.36	14.91	.00	21.28	423.05	5554719.
74	IP Evap Gas Exit	105.30	14.83	.00	20.65	370.89	5554719.
75	IP Econ Gas Inlt	105.30	14.83	.00	20.65	370.89	5554719.
76	IP Econ Gas Exit	100.51	14.76	.00	20.26	351.68	5554719.
77	LP Suph Gas Inlt	.00	.00	.00	.00	.00	0.
78	LP Suph Gas Exit	.00	.00	.00	.00	.00	0.
79	LP Evap Gas Inlt	100.51	14.76	.00	19.55	351.68	5554719.
80	LP Evap Gas Exit	84.71	14.70	.00	18.76	288.01	5554719.
81	HRSO Gas Exit	84.71	14.70	.00	18.76	288.01	5554719.
82	Makeup Water	19.56	14.70	.00	.02	51.46	24779.
83	HRSO LP Deaer In	60.98	30.00	.00	.02	92.86	532607.
84	LP Daer Wtr Exit	218.93	30.00	.00	.02	250.34	558763.
85	LP Evap Stm Drum	75.58	30.00	.00	.02	107.53	127828.
86	LP Evap Tube Inl	76.11	172.22	.00	.02	107.53	127828.
87	LP Evap Tube Out	762.28	30.00	.57	7.91	250.34	127828.
88	LP Evap Stm Exit	1164.15	30.00	.00	13.74	250.34	-1377.

Table 2-3. Dry Coal-Fueled Combined Cycle Thermodynamic Data
(Continued)

LOC	DESCRIPTION	ENTHAL BTU/LB	PRESS PSIA	QUAL -	SPVOL CUFT/LB	TEMP F	WTFLO LB/H
89	LP Suph Stm Exit	1164.15	30.00	.00	13.74	250.34	-1377.
90	IP Econ Wtr Inlt	220.63	488.72	.00	.00	251.08	558763.
91	IP Evap Wtr Inlt	268.25	100.97	.00	.00	298.53	558763.
92	IP Evap Stm Drum	273.20	100.97	.00	.02	303.33	93921.
93	IP Evap Tube Inl	273.93	279.80	.00	.02	303.33	93921.
94	IP Evap Tube Out	1045.64	100.97	.84	3.69	328.53	93921.
95	IP Evap Stm Exit	1187.34	100.97	.00	4.39	328.53	78935.
96	IP Suph Stm Exit	1187.34	100.97	.00	4.39	328.53	78935.
97	HP Econ Wtr Inlt	268.25	444.29	.00	.00	298.53	479828.
98	HP Evap Wtr Inlt	392.12	403.90	.00	.00	415.55	479828.
99	HP Evap Stm Drum	393.67	403.90	.00	.02	416.97	285040.
100	HP Evap Tube Inl	394.16	517.42	.00	.02	416.97	285040.
101	HP Evap Tube Out	1140.43	403.90	.92	1.06	445.55	285040.
102	HP Evap Stm Exit	1204.62	403.90	.00	1.15	445.55	455049.
103	Reheatr Stm Inlt	1231.56	100.97	1.00	5.04	422.90	524883.
104	Throttle Steam	1354.42	367.18	.00	1.77	680.00	455049.
105	Hot Rht Exit	1369.92	91.80	1.00	7.32	680.00	524883.
106	Stm Trb Stm Inlt	1354.42	367.18	1.00	1.77	680.00	445948.
107	Stm Trb HP Leak	1354.42	367.18	.00	1.77	680.00	9101.
108	HP Stm Trb Exit	1237.21	100.97	1.00	5.01	418.77	445948.
109	Stm Trb LP Inlet	1265.14	30.00	1.00	18.05	456.74	532607.
110	Stm Trb Stm Exit	1053.21	.76	.95	410.19	92.86	532607.
111	Condnsr Stm Inlt	1053.21	.76	.95	410.19	92.86	532607.
112	Cndnsr Cnd Exit	60.87	.76	.00	.02	92.86	532607.
113	Clg Twr Air Inlt	28.52	14.75	.00	.00	59.00	3459085.
114	Clg Twr Air Exit	181.31	14.70	.00	.00	75.88	3459085.
115	Hrsg AB Fuel Gas	.00	.00	.00	.00	.00	0.
116	Sorbent Inlet	.00	.00	.00	.00	59.00	27543.
117	Gas Midpoint	.00	.00	.00	.00	.00	0.
118	Slag Exit	551.93	.00	.00	.00	1850.00	33202.
119	Slg Clr Pump Inl	393.67	403.90	.00	.02	416.97	2621524.
120	Hot Cycl CW Inlt	394.78	659.74	.00	.02	417.77	2621524.
121	Slg Comb CW Inlt	394.78	659.74	.00	.02	417.77	2621524.
122	Slg Comb CW Exit	450.62	659.74	.00	.02	467.94	2621524.
123	Cold Gt Fuel Gas	46.08	.00	.00	.01	60.00	139702.

Water Dewpoint 81.8
Acid Dewpoint 238.1

Table 2-4. Combined Cycle Power Summary

GAS TURBINE			
Turbine Fuel	Dry Coal	60/40 CWM	
Expander Power	419,829	430,883	kW
Compressor Power	(253,885)	(253,861)	kW
Auxiliary Power	(581)	(620)	kW
Losses	(4,059)	(4,267)	kW
Gas Turbine Net Power	161,304	172,136	kW
STEAM TURBINE			
HP Steam Turbine Power	15,310	15,721	kW
IP Steam Turbine Power	16,386	16,705	kW
LP Steam Turbine Power	33,060	33,710	kW
Auxiliary Power	(400)	(392)	kW
Losses	(1,802)	(1,826)	kW
Steam Turbine Net Power	62,555	63,917	kW
Fuel Processing	(1,155)	(3,798)	kW
Combustor Coolant Pump	(858)	(938)	kW
Total Plant Auxiliaries	(2,013)	(4,736)	kW
Net Power Generation	221,845	231,316	kW

Table 2-5. CWM Combined Cycle Energy Balance

ENERGY INPUTS	LBS/HR	TEMP F	ENTHALPY BTU/LB	MILLIONS BTU/HR	POWER kW
Slg Clg Wtr Pump				3.20	937.5 kW
Condensate Pump				.06	17.3 kW
Clg Twr Air Fan				.04	12.0 kW
Clg Twr Cir. Pump				.04	12.3 kW
Stm Trb Gen Loss				3.68	1079.2 kW
Stm Trb Mch Loss				2.26	661.4 kW
Stm Trb Aux Loss				.29	86.0 kW
Boiler Feed Pump				.93	271.0 kW
Boiler Circ Pump				.06	18.1 kW
Boiler Circ Pump				.06	18.6 kW
Boiler Circ Pump				.15	42.7 kW
GT Generatr Loss				8.52	2497.2 kW
Slurry Plant				12.96	3798.3 kW
G. Turb Aux Load				2.11	619.6 kW
G. Turb Mech Loss				6.04	1770.2 kW
LP Air Compressor				866.42	253860.6 kW
Ht Cycl Cooling				.00	
Clg Twr Air Inlt	3527057.	59.	28.52	100.57	
Makeup Water	0.	51.	19.56	.00	

Table 2-5. CWM Combined Cycle Energy Balance
(Continued)

ENERGY INPUTS	LBS/HR	TEMP F	ENTHALPY BTU/LB	MILLIONS BTU/HR	POWER kW
Fuel L.H.V. (Eff.)				1994.44	
Gas Turbine Fuel	253815.	59.	75.02	19.04	
Comprsr Air Inlt	5395896.	59.	28.52	153.87	
G. Turb HP Cooling				.00	
Slagger Reaction				7.89	
Sorbent Inlet	30025.	59.	.00	.00	
Total	9206793.			3182.64	

ENERGY INPUTS	LBS/HR	TEMP F	ENTHALPY BTU/LB	MILLIONS BTU/HR	POWER kW
LP Stm Turb				115.05	33719.1 kW
IP Stm Turb				57.01	16704.6 kW
HP Stm Turb				53.65	15720.8 kW
LP Gas Expander				1470.59	430883.2 kW
HRSG Gas Exit	5643542.	298.	88.23	497.91	
Clg Twr Air Exit	3527057.	76.	181.31	639.49	
Clg Twr Air Fan				.04	
Clg Twr Cir. Pump				.04	
Stm Trb Gen Loss				3.68	
Stm Trb Mch Loss				2.26	
Stm Trb Aux Loss				.29	
Gt Generatr Loss				8.52	
Slurry Plant				12.96	
G. Turb LP Cooling				7.37	
Radiation Losses				*167.99	
G. Turb Aux Load				2.11	
G. Turb Mech Loss				6.04	
Slagger Lat.Heat				119.41	
Slag Exit	36193.	1850.	551.93	19.98	
Total	9206793.			3184.41	

* Conservative value established under original project ground rules in 1983. Radiation losses include everything in the combustion zone which includes the slagging combustion process.

Table 2-6. Dry Coal-Fueled Combined Cycle Energy Balance

ENERGY INPUTS	LBS/HR	TEMP F	ENTHALPY BTU/LB	MILLIONS BTU/HR	POWER kW
Slg Clg Wtr Pump				2.93	858.3 kW
Condensate Pump				.06	17.0 kW
Clg Twr Air Fan				.04	11.8 kW
Clg Twr Cir. Pump				.04	12.1 kW
Stm Trb Gen Loss				3.65	1069.9 kW
Stm Trb Mch Loss				2.21	647.6 kW
Stm Trb Aux Loss				.29	84.2 kW
Boiler Feed Pump				.95	278.2 kW
Boiler Circ Pump				.07	19.9 kW
Boiler Circ Pump				.07	19.9 kW
Boiler Circ Pump				.14	41.4 kW
GT Generatr Loss				8.19	2399.8 kW
Coal Grinding				3.94	1154.9 kW
G. Turb Aux Load				1.98	580.8 kW
G. Turb Mech Loss				5.66	1659.4 kW
LP Air Compressr				866.50	253885.3 kW
HT Cycl Cooling				.00	
Clg Twr Air Inlt	3459085.	59.	28.52	98.64	
Makeup Water	24779.	51.	19.56	.48	
Fuel (LHV)				1829.61	
Gas Turbine Fuel	139702.	60.	46.08	6.44	
Comprsr Air Inlt	5395896.	59.	28.52	153.87	
G. Turb HP Cooling				.00	
Slagger Reaction				7.24	
Sorbent Inlet	27543.	59.	.00	.00	
Total	9047006.			2992.99	

ENERGY INPUTS	LBS/HR	TEMP F	ENTHALPY BTU/LB	MILLIONS BTU/HR	POWER kW
LP Stm Turb				112.83	33060.4 kW
IP Stm Turb				55.93	16386.4 kW
HP Stm Turb				52.25	15310.0 kW
LP Gas Expander				1432.86	419829.1 kW
HRSg Gas Exit	5554719.	288.	84.71	470.54	
Clg Twr Air Exit	3459085.	76.	181.31	627.17	
Clg Twr Air Fan				.04	
Clg Twr Cir. Pump				.04	
Stm Trb Gen Loss				3.65	
Stm Trb Mch Loss				2.21	
Stm Trb Aux Loss				.29	
Gt Generatr Loss				8.19	
Coal Grinding				3.94	

Table 2-6. Dry Coal-Fueled Combined Cycle Energy Balance
(Continued)

ENERGY INPUTS	LBS/HR	TEMP F	ENTHALPY BTU/LB	MILLIONS BTU/HR	POWER kW
H2O Ref Temp Chg				24.17	
Gas Turb LP Cooling				7.27	
Radiation Losses				154.10	
Gas Turb Aux Load				1.98	
Gas Turb Mech Loss				5.66	
Slagger Lat. Heat				13.61	
Slag Exit	33202.	1850.	551.93	18.32	
Total	9047006.			2995.07	

2.3 Emission Goals

New Source Performance Standards (NSPS) are assumed to be the emissions criteria. Stipulations of the Code of Federal Regulations, Volume 40, parts 53-60, July 1, 1989 are summarized in Table 2-7, as applied to electric utility boilers. The combined cycle plants burning coal-water slurry are treated as coal-in, electric-power-out plants, so the boiler rules are expected to apply.

Table 2-7. Emissions Goals

<u>Pollutant Species</u>	<u>Maximum Amount</u>
Particulates: Boiler Rule	0.03 lb/MMBtu
Opacity: Boiler Rule	20 percent
Sulfur: Boiler Rule	
Option 1:	1.2 lb/MMBtu, with 90% reduction in uncontrolled SO ₂
Option 2:	0.6 lb/MMBtu, with 70% reduction in uncontrolled SO ₂
Nitrogen Oxides: Boiler Rule	0.6 lb/MMBtu

3 ECONOMICS

3.1 Economic Assumptions

The assumptions underlying the economic assessment of the proposed power plant are described in this section. The same assumptions and methods are applied to assuring consistency in the comparisons.

The assumptions are divided into five sections:

- Section 3.1.1 explains the choice of COE as the criterion
- Section 3.1.2 describes the power plant that is being evaluated
- Section 3.1.3 outlines financial assumptions specific to the power plant
- Section 3.1.4 describes the COEs of the conventional plants to which the proposed plant are compared.

3.1.1 Criterion: Cost of Electricity

Cost of Electricity (COE) is the basis for financial comparison because it is a powerful tool for comparing the economic merits of competing systems. Although various financing assumptions are possible within the EPRI Technical Assessment Guide, and although resulting COE figures may not represent current utility cost structures, COE evaluates the trade-off between fuel cost (the largest contributor to the levelized COE) and utility capital requirements. COE is useful because it considers the total plant configuration in the comparative evaluations.

The COE, otherwise known as the levelized busbar cost of electricity, is the sum of six levelized components:

- Carrying Charges (a function of capital cost)
- Fixed Operating and Maintenance Expense
- Variable Operating and Maintenance Expense
- Cost of Consumables
- By-Product Credit (not used in study)
- Fuel Cost

The COE margin, which is the difference between the COE of a candidate system and the COE of a pulverized-coal plant with stack gas cleanup, is the financial indicator. Systems with COE margins above 10 percent could be of commercial interest, but systems with COE margins above 20 percent would definitely draw commercial interest.

The COE calculations are described in greater detail in Section 3.2.

3.1.2 Power Plant Definition

The direct coal-fired power plant, into which the low-emission cleanup system is integrated, is a combustion turbine combined cycle (CFCTCC) fueled with CWM or PC. The combined cycle plant consists of two gas turbines and one reheat steam turbine. The characteristics of the plant are shown in Table 3-1. This configuration combines the low cost of domestic coal with the high efficiency of a combustion turbine combined cycle plant.

Table 3-1. Reference System Plant Characteristics

Design/Construction Period:	3.0 yr (Combined Cycle Plant) 3.5 yr (Comparison PC-FGD Plant)		
Plant Location:	Northeast US (Western PA)		
Delivered Fuel:	Pittsburgh No. 8 Coal		
Levelized Capacity Factor:	70 percent		
THERMAL INPUT			
Turbine Fuel	Dry Coal	60/40 CWM	
Coal Feed Rate	139,702	152,289	lb/h
Coal HHV	13,555	13,555	Btu/lb
Plant Thermal Input (HHV)	1,894	2,064	MMBtu/h
ELECTRIC OUTPUT			
Gas Turbine Net Power	161,304	172,136	kW
Steam Turbine Net Power	62,555	63,917	kW
Plant Auxiliary Power	(2,013)	(4,736)	kW
Net Power Generation	221,845	231,316	kW
Net Heat Rate (HHV)	8,536	8,924	Btu/kWh
Net Electric Efficiency (HHV)	40.0	38.2	%

The delivered coal is Pittsburgh No. 8 coal whose ultimate analysis and heating value are given in Table 3-2. On-site fuel preparation consists of conventional grinding and CWM production for the CWM plant, and conventional grinding for the dry coal-fueled plant. There is no cleaning of the coal in either of these processes to remove ash or sulfur before it is burned in the slagging combustor.

Table 3-2. Fuel Characteristics

	60/40 CWM	Dry Coal	No.2 Oil	Natural Gas
WEIGHT (%)				
Carbon	44.67	74.45	86-66	69.26
Hydrogen	2.98	4.97	12-14	22.68
Nitrogen	0.91	1.51	<0.1	8.06
Oxygen	3.70	6.17	-	-
Sulfur	1.80	3.00	0.05-1.0	-
Moisture	41.51	2.51	-	-
Ash/Inert	4.43	7.39	-	-
CONSTITUENTS (%vol)				
CH ₄				90.0
C ₂ H ₆				5.0
N ₂				5.0

Table 3-2. Fuel Characteristics
(Continued)

	60/40 CWM	Dry Coal	No.2 Oil	Natural Gas
HEATING VALUE (Btu/lb)				
Higher HV	8,133	13,555	~19,500	21,799
Lower HV	7,858	13,096	~18,200	19,671

The compositions of the sorbents used in this study -- limestone and taconite -- are characterized in Table 3-3.

Table 3-3. Sorbent Constituents

	Limestone	Taconite
WEIGHT (%)		
Calcium Carbonate, CaCO ₃	95.00	-
Moisture, H ₂ O	5.00	-
Magnetite, Fe ₂ O ₃	-	35.74
Inert Material	-	64.26

3.1.3 Plant Financial Data

The financial assumptions used to compare the economic performance of the direct coal-fired combustion turbine plant with that of the reference pulverized coal plant are summarized here. The same assumptions apply to both plants. Table 3-4 lists the financial assumptions (economics, financing, and taxes) that affect the calculations of carrying charge rate and levelizing factors.

Table 3-4. Financial Assumptions

Capital Cost Year Dollars:	1989 (December)	
Project Book Life:	30 years	
Book Salvage Value:	-0-	
Project Tax Life:	20 years	
Tax Depreciation Method:	Reform	
Investment Tax Credit	0%	
Federal Income Tax Rate:	34.0%	
State Income Tax Rate:	4.0%	
Property Tax Rate:	1.0%	
Insurance Rate:	1.0%	
Capital Structure	<u>% of Total</u>	<u>Cost (%)</u>
Common Equity	35	15.2
Preferred Stock	15	11.5
Debt	50	11.0
Weighted Cost of Capital		12.5

**Table 3-4. Financial Assumptions
(Continued)**

Escalation Rates (Apparent)	
General Escalation	6.0% per year
Fuel Escalation	2.0% per year

Table 3-5. Operating Costs

ITEM	OPERATING COST
General Inflation	6.0 % per year
Interest during Construction	12.5 % per year
Operating Labor	\$21.70 /hr w/burden
Pittsburgh No. 8 Coal	\$ 1.80 /MMBtu
Limestone sorbent	\$17.20 /ton
Hematite (Fe ₂ O ₃) sorbent	\$ 380 /ton
Magnetite (Fe ₃ O ₄) sorbent	\$ 380 /ton
Taconite (Fe ₃ O ₄ w/inerts) sorbent	\$ 30 /ton
Nitrogen	\$96.86 /ton
Raw Water	\$ 0.70 /1000 gallons
Water treatment chemicals	\$ 0.12 /lb
CWM dispersant	\$ 0.24 /lb
CWM stabilizer	\$ 2.75 /lb
CWM pH modifier	\$0.167 /lb
Sludge disposal	\$10.60 /ton
Solid Waste Disposal	\$ 9.20 /ton

Table 3-5 shows the assumed values for process flow costs of the power plant.

3.1.4 COE of Conventional Plants

The cost of a conventional PC-FGD plant, and of a CTCC plant provides economic reference points for the evaluation of CFCTCC plants. For consistency in comparisons, the reference cost data was developed for 220 MWe PC-FGD plants. The design values on which the costs were based reflect generic design conditions. Table 3-6 summarizes the design conditions of the conventional plant designs.

Table 3-6. Conventional Plants - Design Conditions (HHV)

Plant Type	PC-FGD	CTCC, gas	CTCC, oil
Plant Output, MW	220	262	258
Fuel Type	Pgh. 8 Coal	Nat Gas	No. 2 Oil
Fuel HHV, Btu	13,555/lb	1,035/SCF	138,690/gal
Plant Heat Rate, Btu/kWh	9,960	8,208	8,227
Boiler	Subcrit	Subcrit	Subcrit
Steam Turbine Generator [1]	TC/2F	TC/2F	TC/2F
Cooling Tower [2]	MD, Wet	MD, Wet	MD, Wet

Table 3-6. Conventional Plants - Design Conditions
(Continued)

Sulfur Control System	Limestone FGD	none	none
Fuel Cost, \$/MMBtu	\$1.80	\$4.00	\$4.00
Construction Time, yrs	3.5	2.0	2.0
Book Life, yrs	30	30	30
TPC Year	Dec 1989	Dec 1989	Dec 1989
TPI Year	Jan 1990	Jan 1990	Jan 1990
Capacity Factor	70%	70%	70%

- [1] Tandem Compound, Double Flow
[2] Mechanical Draft, Wet

All costs for the PC-FGD and CTCC plants were developed with the same cost basis as for the CFCTCC plants. These cost items are discussed in greater detail in Section 3.2. The conventional cost estimates are for complete PC-FGD and CTCC plants, including all equipment, materials, labor, and construction support.

Tables 3-7 and 3-8 summarize the capital and operating costs, respectively, for the conventional power plants. The Total Plant Investment (TPI) includes allowances for funds used during construction, as explained in Section 3.2.2.

The levelized busbar COE of these plants, summarized in Table 3-9 are the reference values to which all other plants in this study are compared.

The COE is calculated by dividing the total annual capital and operating costs (levelized) by the total annual electric production. Calculation procedures are explained in Section 3.5.

The capital and O&M costs of the PC-FGD plant are about three times the cost of either combined cycle plant, and its capital and O&M charges are correspondingly higher. On the other hand, the annual fuel cost for coal is only about a third of the annual cost of either oil or natural gas. The net result of these differences is that combined cycle plants in base-loaded operation can produce electricity at a lower cost than can conventional pulverized coal plants.

Table 3-7. Conventional Plants - Capital Requirements

Plant Type	PC-FGD	CTCC, gas	CTCC, oil
CAPITAL INVESTMENT	(\$/kW)	(\$/kW)	(\$/kW)
Process Capital & Facilities	1255.2	444.0	454.4
Engrg & H.O. Fee	125.5	35.5	36.4
Process Contingency	-0-	-0-	-0-
Project Contingency	138.1	48.0	49.1
TOTAL PLANT COST (TPC)	1518.8	527.5	539.9
TOTAL PLANT INVESTMENT (TPI)	1665.4	543.7	556.5

Table 3-7. Conventional Plants - Capital Requirements
(Continued)

Royalty Allowance	-0-	-0-	-0-
Preproduction Costs	44.2	19.3	19.7
Inventory Capital	31.6	1.6	9.7
Initial Catalysts & Chemicals	-0-	-0-	-0-
Land Cost	<u>6.8</u>	<u>2.9</u>	<u>3.2</u>
TOTAL CAPITAL REQUIREMENT (TCR)	1748.0	567.4	589.0

Table 3-8. Conventional Plants - Operating Costs

Plant Type	PC-FGD	CTCC, gas	CTCC, oil
	(\$/kW-yr)	(\$/kW-yr)	(\$/kW-yr)
OPERATION & MAINTENANCE			
Operating Labor	18.9	8.7	9.6
Maintenance Labor	14.6	3.9	3.9
Maintenance Material	21.9	5.8	5.9
Admin & Support Labor	<u>10.0</u>	<u>3.8</u>	<u>4.0</u>
Total O&M (first year)	65.4	22.1	23.4
CONSUMABLE OPERATING COSTS	(\$/MWh)	(\$/MWh)	(\$/MWh)
Water	0.60	0.49	0.50
Chemicals	1.05	0.27	0.27
Other Consumables	-0-	-0-	-0-
Waste Disposal	<u>1.39</u>	<u>-0-</u>	<u>-0-</u>
Total Consumables (first year)	3.03	0.76	0.77
FUEL COST (first year)	17.93	32.83	32.91

Table 3-9. Conventional Plants - COE Summary

Plant Type	PC-FGD	CTCC, gas	CTCC, oil
Total Plant Cost, \$/kW	1518.8	527.5	539.9
Capital Charges, \$/MWh	49.3	16.0	16.6
Fixed Oper & Maint, \$/MWh	13.0	4.4	4.7
Variable Oper & Maint, \$/MWh	5.6	1.9	2.0
Consumables, \$/MWh	5.3	1.3	1.3
Fuel, \$/MWh	<u>21.2</u>	<u>60.5</u>	<u>60.6</u>
Levelized COE, \$/MWh	94.4	84.1	85.2

Conventional Pulverized Coal Power Plant with FGD

To provide the economic analysis of the direct coal fired combined cycle power plant with relevancy to current commercial technology, the costs of a conventional pulverized coal fired fossil plant were conceptually developed. For the purpose of consistency in comparisons, this cost data was developed for a nominal 220 MW PC-FGD plant.

In determining the capital costs (process capital and general facilities), several sources were utilized. The cost estimate is based on Gilbert/Commonwealth's (G/C) in-house reference fossil plant estimate and a recent project of a similar size. These costs include vendor quotations for major equipment supplemented by current literature, and pricing from several recently completed cost studies and estimates of 250 MW and 350 MW plants. In conjunction with these sources, scaling was done to allow for differences in equipment and system sizes. The site specific components, such as site development, coal handling system, ash handling and disposal, and cooling system, were estimated by adjusting the generic estimate. Based on the above approach, a direct capital cost (process capital and general facilities) of 276 million or 1,255 \$/kW was developed. This result was compared to other G/C in-house small PC-FGD plant data to verify that results were within the range of expected values under similar conditions.

Engineering and project contingency costs (no process contingency was required) were evaluated to yield a total plant cost value at \$366 million or 1,665 \$/kW. The total plant investment factor was slightly higher for the PC-FGD plant, due to the expected longer construction period (4 years vs. 3 years). The addition of preproduction costs, inventory capital, and land cost result in a Total Capital Requirement of \$384 million or 1,748 \$/kW.

The number of plant operators was reduced to 21, in contrast to 23 for the CFCTCC plant. Maintenance percent values were modified, where required, but kept consistent for similar systems or equipment. Similarly, consumable costs were developed, with the PC-FGD plant values being much higher than the CFCTCC plant values for water and water treating chemicals, and waste disposal (FGD sludge) costs. However, overall chemical costs for the PC-FGD plant are much lower than the costs for the CWM CFCTCC plant due to the lack of slurry chemicals.

The cost of fuel for the PC-FGD plant was developed in a similar approach as the slurry plants and, based on the PC-FGD plant heat rate of 9960 Btu/kWh, yielded a first year fuel cost of \$24 million.

The Levelized Busbar Cost of Power, as well as the levelized value of the busbar cost constituents, were determined on the same basis as were the costs for the CFCTCC plants. The COE for the PC-FGD plant was calculated to be 94.4 mills/kWh. This value, as well as the constituent values and all other capital and operating cost values, are summarized in Table 3-10. Table 3-11 summarizes the estimate basis and financial criteria used to arrive at the COE.

Table 3-10. PC-FGD Plant COE Summary
CAPITAL INVESTMENT & REVENUE REQUIREMENT SUMMARY

TITLE/DEFINITION

Case:	Conventional PC Fired Power Plant with FGD		
Plant Size:	220.0 (MW, net)	Heat Rate:	9,960 (Btu/kWh)
Fuel (type):	Pittsburgh #8	Cost:	1.80 (\$/MMBtu)
Design/Construction:	4 (years)	Book Life:	30 (years)
TPC (Plant Cost) Year:	1989 (Dec.)	TPI Year:	1990 (Jan.)
Capacity Factor	70 (%)		
CAPITAL INVESTMENT		\$x1000	\$/kW
Process Capital & Facilities		276,146	1255.2
Engineering (incl. C.M., H.O. & Fee)		27,615	125.5
Process Contingency			
Project Contingency		<u>30,376</u>	<u>138.1</u>
TOTAL PLANT COST (TPC)		\$334,137	1518.8
TOTAL CASH EXPENDED	\$306,822		
AFDC	\$59,555		
TOTAL PLANT INVESTMENT (TPI)		\$366,377	1665.4
Royalty Allowance			
Preproduction Costs		9,733	44.2
Inventory Capital		6,946	31.6
Initial Catalyst & Chemicals			
Land Cost		<u>1,500</u>	<u>6.8</u>
TOTAL CAPITAL REQUIREMENT (TCR)		\$384,556	1748.0
OPERATING & MAINTENANCE COSTS (First year)		\$x1000	\$/kW-yr
Operating Labor		4,147	18.9
Maintenance Labor		3,210	14.6
Maintenance Material		4,815	21.9
Administrative & Support Labor		<u>2,207</u>	<u>10.0</u>
TOTAL OPERATION & MAINTENANCE (1st yr.)		\$14,379	65.4
FIXED O & M (1st yr.)			45.75 \$/kW-yr
VARIABLE O & M (1st yr.)			3.20 mills/kWh
CONSUMABLE OPERATING COSTS (Less Fuel)		\$x1000	mills/kWh
Water		811	0.60
Chemicals		1,413	1.05
Other Consumables			
Waste Disposal		<u>1,868</u>	<u>1.39</u>
TOTAL CONSUMABLES (1st yr.-fuel)		\$4,093	3.03
BY-PRODUCT CREDITS (First year)			
FUEL COST (First Year)		\$24,186	17.93
LEVELIZED OPERATION & MAINTENANCE COSTS			
Fixed O & M			79.9 \$/kW-yr
Variable O & M			5.6 mills/kWh
Consumables			5.3 mills/kWh
By-Product Credit			mills/kWh
Fuel			21.2 mills/kWh
LEVELIZED BUS BAR COST OF POWER			94.4 mills/kWh
30 Year at a Capacity Factor of:	70%		

Table 3-11. PC-FGD Plant Financial Basis

ESTIMATE BASIS/FINANCIAL CRITERIA FOR REVENUE REQUIREMENT CALCULATIONS

GENERAL DATA/CHARACTERISTICS

Case Title:	Conventional PC Fired Power Plant with FGD	
Unit Size:/Plant Size:	220.0 MW, net	
Location:	N.E. USA	
Fuel:	Pittsburgh No. 8	
Plant Heat Rate-Full Load:/Avg.:	9,960 Btu/kWh	
Levelized Capacity Factor:	70%	
Capital Cost Year Dollars:	1989 (December)	
Delivered Cost of Coal:	1.80 \$/MMBtu (at start-up)	
Design/Construction Period:	4 years	
Plant Startup Date (year):	1990 (January)	
Land Area/Unit Cost	200 acre	\$7,500 /acre

FINANCIAL CRITERIA

Project Book Life:	30 years	
Book Salvage Value:	%	
Project Tax Life:	20 years	
Tax Depreciation Method:	Reform	
Property Tax Rate:	1.0 % per year	
Insurance Tax Rate:	1.0 % per year	
Federal Income Tax Rate:	34.0 %	
State Income Tax Rate:	4.0 %	
Investment Tax Credit/% Eligible	%	%
	% of Total	Cost (%)
Capital Structure	-----	-----
Common Equity	35	15.2
Preferred Stock	15	11.5
Debt	50	11.0
Weighted Cost of Capital:	12.5 %	
Escalation Rates (Apparent)		
General Escalation:	6.0 % per year	
Fuel Price Escalation:	2.0 % per year	

Conventional Gas-and Oil-Fired Gas Turbine Combined Cycle Power Plants

The power generating island is based on two current generation gas turbines, each equipped with its own hydrogen-cooled electric generator rated at 100,000 kVA. The gas turbine combustors are designed for dual fuel operation so that they can be started on natural gas or oil. The gas turbines used in combine cycle plants are assumed to have inlet and exhaust losses of 4 inches of water and 10 inches of water, respectively.

Overall, the gas turbine generator is approximately 70 feet long by 29 feet wide by 13 feet high. Each gas turbine exhaust is connected to a heat recovery steam generator (HRSG) which produces steam at two pressure levels (1622 psia and 312 psia). The HRSGs are approximately 40 feet wide by 50 feet long by 40 feet high, and exhaust to individual stacks approximately 125 feet tall. The HRSG is equipped with a duct burner that fires natural gas to heat the gas turbine exhaust to 1200°F.

NO_x control for the gas turbine will be achieved by water injection. For this conceptual design, a water to fuel mass flow ratio of 1:1 was assumed to reduce NO_x emission to 42 ppm(v) dry at 15% O₂ for gas and 65 ppm(v) at 15% O₂ for oil.

Upstream of the HRSG is an exhaust bypass stack that is approximately 75 feet tall. This stack, equipped with silencers, allows the gas turbine to operate in a simple cycle mode when the HRSG or steam cycle equipment is inoperative. This stack also allows the operator to divert some of the exhaust gas away from the HRSG during start-up to assist in bringing the steam cycle equipment on line.

The steam turbine used in the configuration is a current generation non-reheat type with 1450 psig/1000°F throttle condition, and a 2.5-in. HgA back pressure. The high pressure turbine element is housed in a single casing and exhausts to a separate low pressure turbine with a double flow exhaust and 26-in. last stage blades. The steam turbine has two extraction ports to provide steam to a low pressure feedwater heater and the deaerator. The steam turbine is attached to a dedicated, hydrogen-cooled electric generator rated at 138,000 kVA.

Steam cycle heat rejection is through a wet, mechanical draft cooling tower. The cooling tower is designed to achieve a 2.5-in. of mercury condenser pressure for a 75°F wet bulb, a 9°F approach, and a 19.7°F range. Maximum circulating water temperature is 103.7°F. A set of two 50% capacity pumps circulate water from the cooling tower to the condenser at a pressure of 80 feet of water.

Each gas turbine exhausts into a stack which is 75-feet tall. The stack is equipped with silencing material and is arranged so that future flue gas bypass dampers and HRSG addition can be easily accommodated for combined cycle conversion.

The capital cost, operating costs, and COE for gas-fueled and oil-fueled combined cycles are shown in Tables 3-12 and 3-13, respectively. The financial bases for these calculations are shown in Tables 3-14 and 3-15.

Table 3-12. Gas-Fueled Combined Cycle COE Summary

CAPITAL INVESTMENT & REVENUE REQUIREMENT SUMMARY

TITLE/DEFINITION

Case:	Natural Gas Combined Cycle Plant		
Plant Size:	261.8 (MW, net)	Heat Rate:	8,208 (Btu/kWh)
Fuel (type):	Natural Gas	Cost:	4.00 (\$/MMBtu)
Design/Construction:	2 (years)	Book Life:	30 (years)
TPC (Plant Cost) Year:	1989 (Dec.)	TP1 Year:	1990 (Jan.)
Capacity Factor	70 (%)		
CAPITAL INVESTMENT		\$x1000	\$/kW
Process Capital & Facilities		116,235	444.0
Engineering (incl. C.M., H.O. & Fee)		9,299	35.5
Process Contingency			
Project Contingency		12,553	48.0
TOTAL PLANT COST (TPC)		\$138,088	527.5
TOTAL CASH EXPENDED	\$134,179		
AFDC	\$8,171		
TOTAL PLANT INVESTMENT (TP1)		\$142,351	543.7
Royalty Allowance			
Preproduction Costs		5,043	19.3
Inventory Capital		407	1.6
Initial Catalyst & Chemicals			
Land Cost		750	2.9
TOTAL CAPITAL REQUIREMENT (TCR)		\$148,551	567.4
OPERATING & MAINTENANCE COSTS (First year)		\$x1000	\$/kW-yr
Operating Labor		2,271	8.7
Maintenance Labor		1,009	3.9
Maintenance Material		1,514	5.8
Administrative & Support Labor		984	3.8
TOTAL OPERATION & MAINTENANCE (1st yr.)		\$ 5,779	22.1
FIXED O & M (1st yr.)			15.45 \$/kW-yr
VARIABLE O & M (1st yr.)			1.08 mills/kWh
CONSUMABLE OPERATING COSTS (Less Fuel)		\$x1000	mills/kWh
Water		787	0.49
Chemicals		435	0.27
Other Consumables			
Waste Disposal			
TOTAL CONSUMABLES (1st yr.-fuel)		\$1,222	0.76
BY-PRODUCT CREDITS (First year)			
FUEL COST (First Year)		\$52,707	32.83
LEVELIZED OPERATION & MAINTENANCE COSTS			
Fixed O & M			27.0 \$/kW-yr
Variable O & M			1.9 mills/kWh
Consumables			1.3 mills/kWh
By-Product Credit			mills/kWh
Fuel			60.5 mills/kWh
LEVELIZED BUSBAR COST OF POWER			84.1 mills/kWh
30 Year at a Capacity Factor of:	70%		

Table 3-13. Oil-Fueled Combined Cycle COE Summary

CAPITAL INVESTMENT & REVENUE REQUIREMENT SUMMARY

TITLE/DEFINITION

Case:	Distillate Oil Combined Cycle Plant		
Plant Size:	258.4 (MW, net)	Heat Rate:	8,227 (Btu/kWh)
Fuel (type):	Distillate Oil	Cost:	4.00 (\$/MMBtu)
Design/Construction:	2 (years)	Book Life:	30 (years)
TPC (Plant Cost) Year:	1989 (Dec.)	TPI Year:	1990 (Jan.)
Capacity Factor	70 (%)		
CAPITAL INVESTMENT		\$x1000	\$/kW
Process Capital & Facilities		117,424	454.4
Engineering (incl. C.M., H.O. & Fee)		9,394	36.4
Process Contingency			
Project Contingency		<u>12,682</u>	<u>49.1</u>
TOTAL PLANT COST (TPC)		\$139,500	539.9
TOTAL CASH EXPENDED	\$135,552		
AFDC	\$8,255		
TOTAL PLANT INVESTMENT (TPI)		\$143,807	556.5
Royalty Allowance			
Preproduction Costs		5,078	19.7
Inventory Capital		2,498	9.7
Initial Catalyst & Chemicals			
Land Cost		<u>825</u>	<u>3.2</u>
TOTAL CAPITAL REQUIREMENT (TCR)		\$152,208	589.0
OPERATING & MAINTENANCE COSTS (First year)		\$x1000	\$/kW-yr
Operating Labor		2,469	9.6
Maintenance Labor		1,017	3.9
Maintenance Material		1,525	5.9
Administrative & Support Labor		<u>1,046</u>	<u>4.0</u>
TOTAL OPERATION & MAINTENANCE (1st yr.)		\$6,056	23.4
FIXED O & M (1st yr.)			16.41 \$/kW-yr
VARIABLE O & M (1st yr.)			1.15 mills/kWh
CONSUMABLE OPERATING COSTS (Less Fuel)		\$x1000	mills/kWh
Water		787	0.50
Chemicals		435	0.27
Other Consumables			
Waste Disposal			
TOTAL CONSUMABLES (1st yr.-fuel)		<u>\$1,222</u>	<u>0.77</u>
BY-PRODUCT CREDITS (First year)			
FUEL COST (First Year)		\$52,143	32.91
LEVELIZED OPERATION & MAINTENANCE COSTS			
Fixed O & M			28.6 \$/kW-yr
Variable O & M			2.0 mills/kWh
Consumables			1.3 mills/kWh
By-Product Credit			mills/kWh
Fuel			60.6 mills/kWh
LEVELIZED BUSBAR COST OF POWER			85.2 mills/kWh
30 Year at a Capacity Factor of:	70%		

Table 3-14. Gas-Fueled Combined Cycle Financial Basis

ESTIMATE BASIS/FINANCIAL CRITERIA for REVENUE REQUIREMENT CALCULATIONS

GENERAL DATA/CHARACTERISTICS

Case Title:	Natural Gas Combined Cycle Plant	
Unit Size:/Plant Size:	261.8 MW, net	
Location:	N.E. USA	
Fuel:	Natural Gas	
Plant Heat Rate-Full Load:/Avg.:	8,208 Btu/kWh	
Levelized Capacity Factor:	70%	
Capital Cost Year Dollars:	1989 (December)	
Delivered Cost of Natural Gas:	4.00 \$/MMBtu (at start-up)	
Design/Construction Period:	2 years	
Plant Startup Date (year):	1990 (January)	
Land Area/Unit Cost	100 acre	\$7,500 /acre

FINANCIAL CRITERIA

Project Book Life:	30 years	
Book Salvage Value:	%	
Project Tax Life:	20 years	
Tax Depreciation Method:	Reform	
Property Tax Rate:	1.0 % per year	
Insurance Tax Rate:	1.0 % per year	
Federal Income Tax Rate:	34.0 %	
State Income Tax Rate:	4.0 %	
Investment Tax Credit/% Eligible	%	%
	% of Total	Cost (%)
Capital Structure	-----	-----
Common Equity	35	15.2
Preferred Stock	15	11.5
Debt	50	11.0
Weighted Cost of Capital:	12.5 %	
Escalation Rates (Apparent)		
General Escalation:	6.0 % per year	
Fuel Price Escalation:	6.5 % per year	

Table 3-15. Oil-Fueled Combined Cycle Financial Basis

ESTIMATE BASIS/FINANCIAL CRITERIA for REVENUE REQUIREMENT CALCULATIONS

GENERAL DATA/CHARACTERISTICS

Case Title:	Distillate Oil Combined Cycle Plant	
Unit Size:/Plant Size:	258.4 MW, net	
Location:	N.E. USA	
Fuel:	Distillate Oil	
Plant Heat Rate-Full Load:/Avg.:	8,227 Btu/kWh	
Levelized Capacity Factor:	70%	
Capital Cost Year Dollars:	1989 (December)	
Delivered Cost of Oil:	4.00 \$/MMBtu (at start-up)	
Design/Construction Period:	2 years	
Plant Startup Date (year):	1990 (January)	
Land Area/Unit Cost	110 acre	\$7,500 /acre

FINANCIAL CRITERIA

Project Book Life:	30 years	
Book Salvage Value:	%	
Project Tax Life:	20 years	
Tax Depreciation Method:	Reform	
Property Tax Rate:	1.0 % per year	
Insurance Tax Rate:	1.0 % per year	
Federal Income Tax Rate:	34.0 %	
State Income Tax Rate:	4.0 %	
Investment Tax Credit/% Eligible	%	%
	% of Total	Cost (%)
Capital Structure	-----	-----
Common Equity	35	15.2
Preferred Stock	15	11.5
Debt	50	11.0
Weighted Cost of Capital:	12.5 %	
Escalation Rates (Apparent)		
General Escalation:	6.0 % per year	
Fuel Price Escalation:	6.5 % per year	

3.2 Cost of Electricity Calculations

Cost of electricity was chosen because it considers the total plant configuration. As a comprehensive evaluator, the COE calculation entails several sets of constituent calculations which are described in this section.

The revenue requirement method is used to compile the COE. This method is generally used by electric utilities to assess the economic consequences of alternatives. The overall COE calculation is displayed in Figure 3-1. The individual calculations shown in the figure are explained in greater detail in subsequent paragraphs:

- Section 3.2.1 describes the Total Plant Cost
- Section 3.2.2 converts the cost into Total Plant Investment
- Section 3.2.3 explains Total Capital Requirements
- Section 3.2.4 discusses Operation and Maintenance Costs
- Section 3.2.5 explains the use of leveling factors
- Section 3.2.6 lists the COE of the first plant
- Section 3.2.7 tabulates the COE of a mature plant

3.2.1 Total Plant Cost

The installed cost of all equipment and facilities of the power plant, including the cost of services related to installation, is the total plant cost (TPC). When the TPC is divided by the plant net power output, the resulting figure, in \$/kW, is a widely used evaluator of power systems. The total plant costs of the Reference System Plants are tabulated in Table 3-16 and Table 3-17.

The cost of each item in the power plant is the sum of four constituent costs:

- Process capital and general facilities
- Engineering and home office overhead charge
- Process contingency
- Project contingency

Process Capital and General Facilities

Process capital is the total constructed cost of all on-site processing and generating systems. Process capital includes equipment, direct labor, and indirect labor. General facilities, reported as structures and site work, is the constructed cost of all roads, yard facilities, office buildings, shops, laboratories, and storage systems for fuel, chemicals, and by-products.

Engineering and Home Office Overhead Charge

The engineering and home office overhead charge, which includes a cost allowance for construction management, is presented as a fraction of process capital and general facilities. A representative composite fraction of 10 percent was applied to each item in the cost estimate.

Process Contingency

The probability of functional success of each component is reflected in its process contingency. Continuing development of the newer components tends to increase their costs as problems are discovered and solved. The process contingency, expressed as a percent of the process capital cost, quantifies this development uncertainty in equipment design and performance in the form of a cost, process contingency factors generally follow the guidelines published by EPRI, as listed in Table 3-18.

Figure 3-1. COE Calculation Model

Table 3-16. PC CFCTCC Plant Costs (Thousand 1989 Dollars)

<u>PLANT SECTION</u>	<u>PROC. CAP. & GEN FAC.</u>	<u>CONTINGENCIES PROJECT</u>	<u>PROCESS</u>	<u>ENGRG +CONSTR MGT FEE</u>	<u>TOTAL PLANT COST</u>
Coal Processing	29604.	2960.	2960.	3256.	38781.
Slagging Combstr	19476.	1948.	3895.	2142.	27461.
Compressor Inlet	2124.	212.	0.	234.	2570.
Inlet Filter	536.	54.	0.	59.	649.
Main Compressor	8198.	820.	0.	902.	9920.
LP Expander	17028.	1703.	851.	1873.	21455.
Generator	10020.	1002.	0.	1102.	12124.
Steam Power Plant	33956.	3396.	0.	3735.	41087.
Stm Cyc Clg Twr	4680.	468.	0.	515.	5662.
Heat Exchangers	12849.	1285.	64.	1413.	15612.
Instr. + Controls	8460.	846.	0.	931.	10237.
Access. Electric	18504.	1850.	0.	2035.	22390.
Other BOP Equip.	14097.	1410.	0.	1551.	17057.
Structures	19939.	1994.	0.	2193.	24126.
Site Work	8128.	813.	0.	894.	9835.
Total (\$k)	207599.	20760.	7771.	22836.	258966.
Total (\$/kW)	935.8	93.6	35.0	102.9	1167.3

Table 3-17. CWM CFCTCC Plant Costs (Thousand 1989 Dollars)

<u>PLANT SECTION</u>	<u>PROC. CAP. & GEN FAC.</u>	<u>CONTINGENCIES PROJECT</u>	<u>PROCESS</u>	<u>ENGRG +CONSTR MGT FEE</u>	<u>TOTAL PLANT COST</u>
CWM Equipment	22118.	2212.	2212.	2433.	28974.
Slagging Combstr	21644.	2164.	4329.	2381.	30518.
Compressor Inlet	2124.	212.	0.	234.	2570.
Inlet Filter	536.	54.	0.	59.	649.
Main Compressor	8197.	820.	0.	902.	9918.
LP Expander	17636.	1764.	882.	1940.	22221.
Generator	10506.	1051.	0.	1156.	12712.
Steam Power Plant	34678.	3468.	0.	3815.	41961.
Stm Cyc Clg Twr	4753.	475.	0.	523.	5751.
Heat Exchangers	12716.	1272.	64.	1399.	15450.
Inst. + Controls	8857.	886.	0.	974.	10718.
Access. Electric	18504.	1850.	0.	2035.	22390.
Other BOP Equip.	14097.	1410.	0.	1551.	17057.
Structures	19939.	1994.	0.	2193.	24126.
Site Work	8128.	813.	0.	894.	9835.
Total (\$k)	204435.	20443.	7486.	22488.	254832.
Total (\$/kW)	883.8	88.4	32.4	97.2	1101.8

Table 3-18. Development Categories

<u>State of Technology Development</u>	<u>Process Contingency</u>
The process is used commercially	0 - 5 %
A full-sized module has been operated	5 - 10 %
Small pilot plant data is available	10 - 15 %
Concept with bench-scale data available	15 - 25 %
New concept with limited data	25 % and higher

The process contingency factors for the equipment items in the power plant are listed in Table 3-19. Process contingencies for advanced components are based on the judgements of the technical experts working on this study.

Table 3-19. Process Contingency Factors

<u>Equipment</u>	<u>Process Contingency Factor</u>
Coal Processing	10 %
CWM Plant Equipment	10 %
Combustor	40 %
Main Compressor	0 %
Expander	5 %
Generator (Expander)	0 %
Steam Power Plant	0 %
Cooling Tower (Circ. Matl)	0 %
Heat Exchangers	0 %
Instrumentation and Controls	0 %
Accessory Electric	0 %
Other BOP Equipment	0 %
Structures	0 %
Site Work	0 %

Project Contingency

Consistent with conventional power plant practice, a general project contingency was added to the total plant cost to cover the cost of any additional equipment that could result from a detailed design. The project contingency is intended to cover uncertainties in the cost estimate itself, whereas the process contingency covers uncertainties in the technical performance of the equipment. A nominal value of 10 percent project contingency was applied to each item in the cost estimate.

The total plant cost is estimated on the basis of instantaneous construction, and does not include any consideration of financing or construction time.

3.2.2 Total Plant Investment

The Total Plant Investment (TPI) at date of start-up includes consideration for escalation of construction costs and allowance for funds used during construction (AFDC, formerly called interest during construction) over the construction period. TPI is computed from the total plant cost where the TPC is expressed on an "overnight" or instantaneous construction basis. The calculation method for TPI is taken from the EPRI Technical Assessment Guide (TAG):

$$TPI = TPC \times AF_{tpi}$$

where:

$$AF_{tpi} = (Z^N - 1) / (Z - 1)N$$

$$Z = (1 + i) / (1 + ea)$$

i = Weighted cost of capital

ea = Apparent escalation rate for equipment

N = Construction period, years

The equation is based on a uniform expenditure rate over the construction period, with all expenditures taking place at the end of each year. The construction period for this purpose was established as three years. The apparent escalation rate for this calculation was 6 percent per year, while the discount rate was 12.5 percent.

3.2.3 Total Capital Requirements

The Total Capital Requirement (TCR) value includes all capital necessary to complete the entire project. The TCR is the sum of the TPI, prepaid royalties, preproduction (or start-up) costs, inventory capital, initial chemical and catalyst charge, and land cost.

Prepaid Royalties: The paid-up royalties allowance was estimated to be 0.5 percent of the associated process capital. Royalties were charged for cleanup devices, the compressor, the combustor, the expander and the slurry plant.

Preproduction Costs: The preproduction costs are intended to cover operator training, equipment checkout, major changes in plant equipment, extra maintenance, and inefficient use of fuel and other materials during plant start-up. The preproduction costs are estimated as follows:

- One month of fixed operating costs. Fixed operating costs are operating and maintenance labor, administrative and support labor, and maintenance materials.
- One month of variable operating costs at full capacity excluding fuel. These variable operating costs include chemicals, water, and other consumables and waste disposal charges.
- 25 percent of full capacity fuel cost for one month. This charge covers inefficient operation that occurs during the start-up period.

- 2 percent of total plant investment (TPI). This charge covers expected changes and modifications of equipment that will be needed to bring the plant up to full capacity.

Inventory Capital: The inventory capital is the value of inventories of fuel and other consumables. The inventory is estimated to be a 60-day supply of fuel and other consumables (excluding water) based on full capacity operation.

Initial Catalyst and Chemicals: The initial catalyst and chemical charge is the initial cost of any catalysts or chemicals that are contained in the process equipment (but not in storage, which is covered in inventory capital). No value is shown because charges are included in the component material capital cost.

Land Cost: The required land area was determined on the basis of similar plot plans to be 90 acres. The land cost was \$7,800 per acre.

The TCR of a plant is converted into an operating cost by expressing it as the levelized carrying charge, which is the revenue obligation needed to support the investment in the plant. The carrying charge is the sum of return of debt, return on equity, federal and state income tax liability, book depreciation, property taxes, and insurance. The values of these components are listed with other plant financial assumptions in Section 3.1.3, and levelization is discussed in Section 3.2.5.

The total capital requirements and levelized carrying charge for both Reference power plants are summarized in Table 3-20.

Table 3-20. First CFCTCC Plant Capital Requirements

Plant Type	Dry PC	CWM
	(\$/kW)	(\$/kW)
CAPITAL INVESTMENT		
Process Capital & Facilities	935.8	883.8
Engrg & H.O. Fee	102.9	97.2
Process Contingency	35.0	32.4
Project Contingency	93.6	88.4
TOTAL PLANT COST (TPC)	1167.3	1101.8
TOTAL PLANT INVESTMENT (TPI)	1240.4	1170.7
Royalty Allowance	2.0	1.8
Preproduction Costs	35.7	37.6
Inventory Capital	29.7	37.4
Initial Catalysts & Chemicals	-0-	-0-
Land Cost	3.3	3.2
TOTAL CAPITAL REQUIREMENT (TCR)	1311.0	1250.6

3.3 Operation and Maintenance Costs

The operating and related maintenance costs are combined under the following headings: Operating Labor, Maintenance Labor, Maintenance Material, and Administrative & Support Labor. Once determined, the sum of these values is re-apportioned into fixed (independent of plant power generation) and variable (directly proportional to the amount of power generated) components.

3.3.1 Operating Costs

The operating costs are estimated on a first year basis and given in December 1989 dollars. The "first year" costs assume normal operation and do not include the initial start-up costs, which are computed separately. The costs are subsequently presented on a 30-year levelized basis.

The cost of operating labor was estimated on the basis of the number of operating jobs (OJ) that are required to operate the plant. The operating labor charges (OLC) were then computed using the average labor rate as follows:

$$OLC = \frac{(OJ) \times (Labor\ Rate \times Labor\ Burden) \times (8766\ hr/yr)}{(\text{net capacity of plant at full load in KW})}$$

Table 3-21, CFCTCC Plant Operating Labor Requirements, indicates the number of operating jobs, the operating labor rate, and the operating labor burden that were used to determine the first year operating labor cost value. The operating labor requirements were determined on the basis of data provided by the United Coal Company for the slurry plant, supplemented by G/C data for combined cycle plants and subsequently adjusted for expected other labor requirements to arrive at total plant operating requirements.

Table 3-21. CFCTCC Plant Operating Labor Requirements

Operating Labor Rate (base):	\$16.10/hr
Operating Labor Burden:	35 percent of base
Labor Overhead Charge Rate:	30 percent of labor

Operating Labor Requirements (OJ) per shift:

<u>Category</u>	<u>1 Unit/Mod.</u>	<u>Total Plant</u>
Skilled Operator	3.0	3.0
Operator	16.0	16.0
Foreman	2.0	2.0
Lab Techs, etc.	2.0	2.0
TOTAL (OJs)	23.0	23.0

3.3.2 Maintenance Costs

Since the development of the maintenance labor and maintenance material costs are interrelated, these two costs are discussed together. Annual maintenance costs, especially for new technologies, are often estimated as a percentage of the installed capital cost of the facilities. The percentage varies widely depending on the nature of the processing conditions and the type of design.

Maintenance factors for the equipment in the power plant are listed in Table 3-22. A typical piece of equipment has an annual maintenance factor of 1.5 percent. Items that are expected to need more maintenance have higher maintenance factors, and items needing less maintenance have lower factors.

Table 3-22. CFCTCC Maintenance Factors

<u>Equipment</u>	<u>Factor</u>
Coal Processing	3.0 %
CWM Plant Equipment	3.0 %
Slagging Combustor	3.0 %
Main Compressor	3.0 %
Expander	3.0 %
Generator (Expander)	1.5 %
Steam Power Plant	1.5 %
Cooling Tower (Circ. Matl)	1.5 %
Heat Exchangers	2.0 %
Instrumentation and Controls	1.5 %
Accessory Electric	1.5 %
Other BOP Equipment	2.0 %
Structures	0.5 %
Site Work	1.5 %

Since the maintenance costs should be separately expressed as maintenance labor and maintenance materials, a maintenance labor/materials ratio of 40/60 was used for this breakdown. This ratio is consistent with EPRI guidelines.

The administrative and support labor cost is an O&M overhead charge for administrative and support labor. This charge taken as 30 percent of the operating and maintenance labor. General and administrative expenses are not included.

3.3.3 Fixed and Variable Components

The total of operating and maintenance costs are divided into fixed and variable O&M costs. The fixed costs are essentially independent of capacity factor, and are generally expressed as \$/kW-yr. The variable costs are directly proportional to the amount of power produced, and are generally expressed as \$/MWh.

Based on EPRI guideline and utility experience, base-loaded plants tend to have a relatively high fixed component of the operating cost, whereas peaking and intermediate plants have a relatively high variable component. It was

therefore assumed that the fixed portion of the operating cost is equal to the expected nominal capacity factor for the plant. The balance of the cost is then assumed to be variable. An example of the calculation is shown below.

Fixed O&M = Capacity Factor (CF) x Total O&M (\$/kW-yr)

Variable O&M = $\frac{[(1-CF) \times \text{Total O\&M} \times 1,000 \text{ mills/\$}]}{(CF \times 8,760 \text{ hrs/yr})}$

3.4 Fuel and Consumables

The fuel, feedstock, and disposal costs reported in this section pertain to the CWM-fired combined cycle power plant. In terms of a strict EPRI-TAG terminology these items are referred to as consumable operating costs, by-product credits, and fuel costs.

Consumable operating costs are developed on a first year basis and subsequently levelized over the 30-year life of the plant. The quantities and unit costs that were used to develop the corresponding cost values are included in Table 3-23.

The water component is the acquisition charge for water required for the plant steam cycle and slurry plant. The water treatment chemicals consist of the H₂SO₄ and caustic required to treat the associated water quantity.

Table 3-23. CFCTCC Fuel and Consumables

Turbine Fuel		60/40 CWM	Dry Coal
	Cost (\$/klb)	Flow (lb/h)	Flow (lb/h)
Coal - Pittsburgh No. 8		152,289	139,702
Water	0.08	479,309	369,830
Water Treatment	120.00	276	213
Dispersant	240.0	2,014	0
Stabilizer	2,750.00	426	0
pH Modifier	167.43	1,534	0
Sorbent - Limestone	8.57	30,025	27,543
Nitrogen	48.43	0	17,463
Solids Disposal	4.60	36,193	33,202

Waste disposal is the cost allowance for off-site disposal of plant solid wastes. The sludge is the dry-weight equivalent of the beneficiation plant tailings. The unit cost for disposal was based on the EPRI recommended value. The dry solids quantity is the composite of captured ash and spent sorbent. Again, the unit cost for disposal was based on the EPRI recommended value.

For the coal, as well as for all feedstock and disposal costs, the quantities represent the 100-percent capacity requirement, while all values in the COE tables are adjusted for the designated 70-percent power plant capacity factor.

The estimated operating costs for the first year of commercial operation are summarized in Table 3-24. These costs provide data that is used to calculate the levelized busbar COE.

Table 3-24. CFCTCC Reference System Operating Costs

Plant Type	CWM	Dry PC
	(\$/kW-yr)	(\$/kW-yr)
OPERATION & MAINTENANCE		
Operating Labor	16.43	17.14
Maintenance Labor	8.05	8.61
Maintenance Material	12.08	12.92
Admin & Support Labor	7.35	7.72
Total O&M (first year)	43.92	46.39
CONSUMABLE OPERATING COSTS	(\$/MWh)	(\$/MWh)
Water	0.17	0.14
Water Treatment	0.14	0.12
CWM Dispersant	2.09	-0-
CWM Stabilizer	5.07	-0-
pH Modifier	1.11	-0-
Sorbent	1.11	1.06
Nitrogen	-0-	3.81
Waste Disposal	0.72	0.69
Total Consumables (first year)	10.42	5.82
FUEL COST (first year)	16.06	15.36

Inflation will tend to increase the operating costs (in current dollars) over the life of the plant. In order to avoid the complication of varying each of the fixed and variable operation costs from year to year, a single "levelized" value is used.

The general 30-year levelizing factor, based on a 6-percent annual escalation and an 12.5-percent cost of capital, is 1.75. This general factor is used for all levelizing calculations except for fuel. The 30-year levelizing factor for fuel, based on 2.0-percent annual escalation and an 12.5-percent cost of capital is 1.18.

3.5 Cost of Electricity Estimate

The coal-pile-to-busbar cost of electricity is the conventional figure of merit used by utilities to compare power generation alternatives. The COE includes consideration of total capital requirements, represented by the levelized carrying charge (sometimes referred to as the fixed charge), levelized fixed and variable operation and maintenance costs, levelized consumable operating costs, and levelized fuel costs. The 30-year levelized COE for the first plant is summarized in Table 3-25.

Table 3-25. First CFCTCC Plant COE Summary

Plant Type	CWM	Dry PC
Total Plant Cost, \$/kW	1101.8	1167.3
Capital Charges, \$/MWh	35.28	36.99
Fixed Oper & Maint, \$/MWh	8.76	9.25
Variable Oper & Maint, \$/MWh	3.75	3.97
Consumables, \$/MWh	18.21	10.17
Fuel, \$/MWh	19.03	18.20
Levelized COE, \$/MWh	85.04	78.58

3.6 COE of a Mature Plant

By the time the fifth plant is built, it is assumed that design improvements to the relatively new components would reduce their cost by an amount equal to the process contingency in the first plant. Consequently, the fifth plant would have a lower capital cost than the first plant. The "Mature Plant" costs reflect this reduced capital cost, and provide a fair comparison to the cost of mature pulverized coal plant. The COE of the mature plant is itemized in Table 3-26.

Table 3-26. Mature CFCTCC Plant COE Summary

Plant Type	CWM	Dry PC
Total Plant Cost, \$/kW	1,069.4	1,132.3
Capital Charges, \$/MWh	34.29	35.92
Fixed Oper & Maint, \$/MWh	8.76	9.25
Variable Oper & Maint, \$/MWh	3.75	3.97
Consumables, \$/MWh	18.21	10.17
Fuel, \$/MWh	19.03	18.20
Levelized COE, \$/MWh	84.05	77.51
COE Margin (ref: \$94.4/MWh)	11.0%	17.9%

4 SLAGGING COMBUSTOR DESCRIPTION

In slagging combustion systems, coal is burned at a temperature high enough so that coal ash melts and turns to liquid. This liquid, which flows down the combustor walls, is collected and extracted from the combustor. Therefore, there are few solid ash particles to pass out of the chamber with the hot gases and damage the turbine. In addition, the sulfur found in most coals can also be removed at this point. Calcium compounds are introduced into the chamber where they combine with the sulfur. The resulting sorbent-captured sulfur melts and joins the slag. Also, because a slagging combustor operates fuel-rich in the primary zone and lean-burn in the secondary zone, it will suppress NO_x formation.

For slagging to occur, temperatures throughout the combustion chamber, and particularly at the walls, must not fall below approximately 2600°F, depending upon the type of coal. These temperatures are achieved by employing a proper air/fuel ratio, refractory walls, and adequate residence time for the reacting coal/air mixture. Refractory walls are used in the subscale combustor to reduce heat loss and promote slagging, during the relatively short duration development tests.

4.1 Slagging Combustor Concept

Slagging temperatures are attained in the first stage, where the primary combustion takes place. Larger ash and slag particles are inertially separated from the gas in a toroidal-vortex flow pattern. The fuel-rich conditions in this stage inhibit the conversion of fuel-bound nitrogen into NO_x . A sorbent, such as limestone, is injected into the combustor at the downstream end of the first stage where conditions are right to capture sulfur.

The second stage is an efficient impact separator that is closely coupled to the first stage. This stage collects the finer particles of slag, ash, and sorbent that are carried over from the first stage. Slag separation in the second stage takes place in three phases: the transport of molten particles from the gas stream to the wall; the flow of slag along the wall to the slag tap due to gravity; and the flow of the slag through the slag tap. Molten slag droplets separate from the gas stream by centrifugal force. The efficiency of separation depends on the velocity and the radius of turning. The thickness of the slag layer and its movement under the influence of gravitational, and gas-flow shear forces are influenced more by gas temperature and wall cooling than they are by combustor size. The slag can be prevented from freezing in the slag tap by letting a small flow of gases escape through the center of the slag tap.

Though the impact separator is very effective at removing ash/slag particles from the products of fuel-rich combustion, further particulate cleanup is required in order to meet both the turbine requirements and the NSPS requirements. In the current combustor configuration, a slagging cyclone separator has been incorporated into the fuel-rich zone of the combustor to further reduce particulate emissions. This is a novel application for cyclone separators: a literature search was performed and no evidence was found of any operating experience with a slagging cyclone separator (i.e., a cyclone separator operating at such a high temperature that the particulate matter to

be separated is molten and the separated slag forms a flowing layer on the walls of the cyclone). It was postulated that the relatively high gas temperature in the cyclone may enable a very high cyclone collection efficiency to be attained. Re-entrainment and turbulence effects are important considerations in cyclone performance and such effects are difficult to predict. At the high temperature in the combustor second stage, the ash particles to be separated are molten and sticky. Operation with liquid ash alleviates potential problems due to re-entrainment of separated slag and allows the use of higher than normal tangential inlet velocities, thereby generating high inertial separation forces and improved collection performance.

Combustion is completed in the fuel-lean third stage, where rapid quenching with secondary air reduces the gas temperature below the temperature at which thermal NO_x can form. The design of the third stage is based on conventional gas turbine combustor design practice. The combustor uses a rich-lean approach with quick quench to control nitrogen oxides. Thermal NO_x kinetics require quenching from rich to lean in a few milliseconds. This time requirement determines the number, geometry, placement, and orientation of the secondary air jets.

Integrated with the turbine, the external combustion assembly physically replaces a normal combustor. As a preliminary estimate, the external combustion assembly comprises two slagging combustor modules which are connected to the reference utility-sized combustion turbine.

4.2 Particulate Control

Particles and slag are removed in both the first stage and the separator stage. The toroidal-vortex flow field in the first stage separates ash particles by centrifugal collection. The separated ash particles combine with the liquid slag flowing down the combustor wall. The combustor dome design and injection arrangement result in a small toroidal-vortex radius that permits efficient separation without excessive pressure drop.

The inertial-impact separator stage collects the finer particles carried over from the first stage. Gases from the first stage are accelerated through a single nozzle and impinge on a plate. This design can efficiently remove particles of 5 microns and larger without excessive pressure drop. An acceptable pressure drop is needed to maintain the high efficiency of the power system.

4.3 Sulfur Control

Sulfur is captured by injecting dolomite or limestone into the fuel-rich first stage. Under normal combustor conditions, CaO in the sorbent reacts with SO_2 in the gas to form $\text{CaSO}_3 + \text{CaSO}_4$, which can be removed along with the slag. Formation of CaS by reactions between calcium (inherent in the coal ash or impregnated with the coal) and pyritic sulfur in the coal ash have also been reported. This supplemental reaction would enhance the overall sulfur capture.

Results of leaching and activity tests on sulfated dolomite (CaS) have shown that it is environmentally unacceptable for disposal. Several processes are available to convert it to environmentally acceptable forms for disposal. One

desirable process is the dry oxidation of CaS to CaSO_4 . Oxidizing the CaS in a fluidized-bed reactor at a proper temperature in excess air (32 moles of air per mole of CaS) prevents competing reactions that form SO_2 and CaO. It is important to remove CaS from the combustor before final oxidation in the third stage. At the fuel-lean condition, sulfur is partially or completely released, and its capture presents a formidable problem.

4.4 Nitrogen Oxide Control

The slagging combustor concept can control NO_x levels to far below those currently required by NSPS. The intense and rapid mixing of the reactants in the first stage promotes rapid volatilization of the coal and homogeneous combustion. The first stage is expected to operate with a fuel/air equivalence ratio between 1.2 and 1.4. Under these fuel-rich conditions, fuel-bound nitrogen is converted to N_2 instead of NO_x . Conditions in the first and second stages also minimize the carryover of fuel-bound nitrogen to the third stage. Additional air is added to this fuel-lean stage in such a manner that the gas is rapidly quenched to below the temperature at which thermal NO_x can form.

4.5 Alkali Control

The relatively volatile alkali compounds can cause corrosion and deposition in the expander. They can volatilize during combustion and subsequently condense at the cooler gas turbine operating temperature to form molten alkali sulfates, which are highly corrosive. In addition, condensed alkalies can provide a sticky surface on which ash particles accumulate. This deposition buildup on the blading results in performance degradation of the gas turbine.

Alkalies (sodium and potassium) can be controlled by controlling the thermochemistry of coal ash and by operating at conditions that inhibit the volatilization of alkalies during combustion. Because most of the coal is burned in a very short time the volatilization of alkalies is limited by reaction kinetics. Further, silicates in the fused ash are relatively stable at combustion temperatures, and they can serve as getters for controlling alkalies.

5 ECONOMIC SENSITIVITY STUDIES

Sensitivity studies were performed using the computer model to assess the influence of certain parameters on the COE margin of the CWM-fueled plant. Table 5-1 lists the parameters that were evaluated, along with the relative sensitivity of COE margin to each parameter.

Table 5-1. COE Sensitivities Summary

<u>Parameter</u>	<u>Reference Plant Value</u>	<u>Extreme Value</u>	<u>Change In Parameter</u>	<u>Possible COE Margin</u>	<u>Change In COE Margin</u>
Combustor Outlet Temperature, °F	1850	2150	16%	19.9%	82%
Slurry Chemical Expense, \$M	11.7	10.5	-10%	12.5%	14%
Sulfur Capture:					
Limestone Ca/S [1]	2.00	8.00	300%	-3.0%	-127%
Limestone Ca/S [2]	2.00	6.00	200%	-11.8%	-207%
Taconite Fe/S [2]	n/a	10.00	n/a	-53.4%	-587%
Combustor Capital Cost, \$M	26.2	39.3	50%	9.0%	-18%
Reblading Interval:					
over 5,000 hours	25,000	40,000	60%	11.2%	2%
under 5,000 hours	25,000	1,000	-96%	-34.6%	-416%
Combustor Pressure Drop, %	7%	9%	+29%	10.2%	-7%
Combustor Heat Rejection, %	8%	10%	+25%	10.8%	-1%

[1] Assuming 90% sulfur capture without FGD

[2] Assuming FGD required

The effects of these parameters are discussed in subsequent paragraphs.

This section also describes the effect of changing natural gas prices on the COE margin of a combined cycle fueled by coal, compared to a combined cycle fueled by natural gas.

5.1 Combustor Outlet Temperature

The reference system operates with a combustor outlet temperature of 1850°F, which is several hundred degrees lower than the firing temperature of commercial turbines fueled by oil or gas. Table 5-2 and Figure 5-1 show the dramatic improvement in COE margin resulting from increasing the firing

temperature to 2150°F. The improvement is due to the increased power and efficiency of the higher temperature cycle. The progressive improvement is tempered somewhat at higher temperatures by the requirement for increased turbine blade cooling, which reduces the cycle efficiency, and by the increased cost of the higher temperature turbine hot parts.

Table 5-2. COE Sensitivity to Firing Temperature (CWM-Fueled Plant, HHV)

<u>Firing Temperature (°F)</u>	<u>Net Power (MW)</u>	<u>Plant Efficiency (%)</u>	<u>Capital Cost (\$/kW)</u>	<u>COE Margin (%)</u>
1850 (base)	231.3	38.2	1,069	11.0
2000	267.3	39.4	967	16.9
2150	301.1	40.2	925	19.9

Figure 5-1. COE Margin vs. Firing Temperature

5.2 Slurry Chemical Expense

In the CWM-fueled reference plant, the first year cost of slurry chemicals (dispersant, stabilizer, and pH modifier) is estimated to be \$11.7 million, or 79.5 percent of the \$14.8-million total first year consumables cost. The complete consumable cost breakdown is listed in another section of this report.

For this same plant, consumables account for 21.7 percent of the total COE. A 10-percent reduction in chemicals cost, by reducing either the amount of chemicals used or their costs, would result in a reduction in COE of $0.100 \times 0.795 \times 0.217$, or 1.7 percent.

In the extreme case, if the slurry chemical cost were eliminated altogether, the COE would decrease by 17.2 percent from \$84.0/MWh to \$69.6/MWh, and the COE margin would improve from 11.0 percent to 26.3 percent.

5.3 Sulfur Capture

During the slagging combustor tests, over 90 percent of the sulfur was captured in the primary combustion zone, but much of it escaped from the slag in the slag separator zone, resulting in a net sulfur capture efficiency for the complete rig of only about 50 percent. In the test rig, the slag is retained in the separation zone for the duration of the test, allowing the sulfur time to escape. It is thought that sulfur escape will be significantly reduced when a slag removal system is added, resulting in overall sulfur capture efficiencies of at least 90 percent.

The addition of more sorbent results in increased feedstock costs, slightly decreased plant efficiency, and increased capital cost of the slag-handling equipment. Table 5-3 and Figure 5-2 project COE margins between -2.9 and +11.0 percent for CWM, and between 4.7 and 17.9 percent for dry pulverized coal, assuming that 90-percent of the sulfur can be captured using limestone with Ca/S ratios between 2.0 and 8.0. Each 1.0 increase in Ca/S ratio results in an approximate 2.3-percent decrease in COE margin.

Table 5-3. COE Sensitivity to Ca/S Ratio
(CWM-Fueled Plant with 90% Sulfur Capture, HHV)

<u>Limestone Ca/S Ratio (w/90% capture)</u>	<u>Net Power (MW)</u>	<u>Plant Efficiency (%)</u>	<u>Capital Cost (\$/kW)</u>	<u>COE Margin (%)</u>
2.0 (base)	231.3	38.2	1,069	+11.0
4.0	231.9	37.8	1,094	+ 6.3
6.0	232.4	37.4	1,116	+ 1.7
8.0	233.0	37.0	1,136	- 2.9

Figure 5-2. COE Margin vs. Ca/S Ratio

Figure 5-3. COE Margin for Plant with FGD

If the slagging combustor is unable to remove all 90 percent of the sulfur, a FGD could be added to the plant, but at the cost of a considerable erosion of COE margin. As shown in Table 5-4 and Figure 5-3, the COE margin for a plant with FGD ranges from 1 percent (for dry coal plant with a Ca/S of 2.0) to -11.8 percent (for a CWM-fueled plant with a Ca/S ratio of 6.0). The capital cost of the FGD depends mainly on gas volumetric flow rate, not sulfur removal ability. The change in COE margin with changing Ca/S ratio is due to changes in feedstock cost, plant efficiency, and slag-removal equipment cost, as described above. The case with Ca/S equal to 0.0 represents a plant in which all sulfur is captured by limestone in the FGD, and none is captured by the slagging combustor.

**Table 5-4. COE Sensitivity to Ca/S Ratio
(CWM-Fueled Plant with FGD, HHV)**

<u>Limestone Ca/S Ratio (w/FGD)</u>	<u>Net Power (MW)</u>	<u>Plant Efficiency (%)</u>	<u>Capital Cost (\$/kW)</u>	<u>COE Margin (%)</u>
0.0	226.4	37.7	1,205	-3.5
2.0	227.8	37.5	1,229	-6.1
4.0	229.0	37.3	1,247	-9.1
6.0	230.5	37.1	1,262	-11.8

Taconite, an iron-based sorbent, is a less reactive and less expensive alternative to limestone. The temperatures in the slagging combustor are much higher than the normal operating range of this sorbent, and operation with Fe/S ratios below 10 is expected to require a FGD to maintain the required 90-percent sulfur removal. Table 5-5 and Figure 5-4 show negative COE margins in all cases, due to the low sulfur capture efficiency of taconite and the increased capital cost of slag-removal equipment and of the FGD. The case with Fe/S equal to 0.0 represents a plant in which all sulfur is captured by limestone in the FGD, and none is captured by the slagging combustor.

**Table 5-5. COE Sensitivity to Taconite Fe/S Ratio
(CWM-Fueled Plant, HHV)**

<u>Taconite Fe/S Ratio (w/FGD)</u>	<u>Net Power (MW)</u>	<u>Plant Efficiency (%)</u>	<u>Capital Cost (\$/kW)</u>	<u>COE Margin (%)</u>
0.0	226.4	37.7	1,205	- 3.5
4.0	228.6	36.7	1,304	-27.0
6.0	229.2	36.2	1,347	-39.7
8.0	230.5	35.7	1,386	-52.4
10.0 (no FGD)	232.5	35.3	1,280	-53.4

For a CWM-fueled, taconite-assisted plant with an Fe/S ratio of 10.0, the first year taconite cost is estimated to be \$32 million, or about 58 percent of the \$55-million total first year consumables cost, as itemized in Table 5-6.

Figure 5-4. COE Margin vs. Fe/S Ratios with FGD

Table 5-6. Taconite and Other Consumable Costs

Stream	lb/h	\$/klb	k\$/yr
Water	487,292	0.08	250.80
Water Treatment	280	120.00	206.18
Taconite	346,334	15.00	31,855.77
Dispersant	2,192	240.00	3,225.57
Stabilizer	464	2750.00	7,822.14
PH Modifier	1,669	167.43	1,713.33
Solids Disposal	327,381	4.60	10,146.16
Total Consumables			55,219.95

For this same plant, consumables account for 46.8 percent of the total COE, as shown in Table 5-7. A 10-percent reduction in taconite cost, therefore, would result in a reduction in COE of $0.100 \times 0.58 \times 0.468$, or 2.7 percent.

Table 5-7. COE with Taconite for CFCTCC - CWM

Total Plant Cost, \$/kW	1,069.4
Capital Charges, \$/MWh	42.32
Fixed Oper & Maint, \$/MWh	9.90
Variable Oper & Maint, \$/MWh	4.24
Consumables, \$/MWh	67.72
Fuel, \$/MWh	20.61
Levelized COE, \$/MWh	<u>144.80</u>
COE Margin (ref: \$94.4/MWh)	-53.4%

In the extreme case, if the taconite cost were eliminated altogether, the COE would decrease by 27.1 percent from \$144.80/MWh to \$105.5/MWh, and the COE margin would improve from -53.4 percent to -11.8 percent, not enough to break even.

5.4 Combustor Capital Cost

The capital cost of the slagging combustor in a mature CWM-fueled plant is estimated to be \$26.2 million, or about 10.6 percent of the \$247-million total plant cost. (The capital cost breakdown is shown in another section of this report.) For this same plant, carrying charges based on these capital costs account for 40.8 percent of the total COE. The impact of a combustor cost reduction on COE is relatively minor.

A 10-percent reduction in slagging combustor cost, therefore, would result in a reduction in COE of $0.100 \times 0.106 \times 0.408$, or 0.44 percent.

In the extreme case, if the slagging combustor cost were eliminated altogether, the COE would decrease by 4.4 percent from \$84.0/MWh to \$80.3/MWh, and the COE margin would improve from 11.0 percent to 14.9 percent. If the cost of the slagging combustor doubled to \$52.4 million, the COE would increase to \$87.8/MWh.

5.5 Turbine Reblading Interval

A critical factor in the successful development of a CFCTCC is the delivery of a suitable clean gas to the turbine inlet that is compatible with turbine components. Potentially higher particulate loadings and alkali levels within a direct coal-fired combustion turbine indicates that an economic trade-off should be considered between hot gas cleanup and turbine reblading intervals. In this study only the reblading interval of the turbine was considered.

Periodic replacement of corroded or eroded turbine blades affect the COE by increasing maintenance cost and reducing the operating availability of the turbine. Since there is not enough data on the effects of corrosion and erosion on turbine blade life, the COE was calculated for the range of values listed in Table 5-8. For each case, including the base case, the COE includes the materials and labor cost of opening the turbine and replacing worn-out rows of vanes and blades.

Table 5-9 and Figure 5-5 show that reblading interval has little effect on COE margin as long as the shortest time between rebladings is at least 5,000 hours. At shorter reblading intervals, however, turbine down-time begins to reduce the capacity factor of the power plant. Blade lives of 2,000 and 1,000 hours reduce the nominal 70-percent availability to 58 percent and 46 percent, respectively, which severely reduces the COE margin of the coal-fueled combined cycle.

Table 5-8. Turbine Reblading Interval

<u>Reblading Schedule</u>	<u>Row 1 (hours)</u>	<u>Row 2 (hours)</u>	<u>Row 3 (hours)</u>	<u>Row 4 (hours)</u>
Schedule 1	40,000	60,000	60,000	100,000
Schedule 2 (base)	25,000	50,000	50,000	90,000
Schedule 3	10,000	20,000	20,000	50,000
Schedule 4	5,000	10,000	10,000	25,000
Schedule 5	2,000	4,000	4,000	10,000
Schedule 6	1,000	2,000	2,000	5,000

Figure 5-5. COE Margin vs. Turbine Reblading Intervals

Table 5-9. COE Sensitivity to Reblading Interval
(CWM-Fueled Plant, HHV)

Shortest Blade Life (hrs)	Net Power (MW)	Plant Efficiency (%)	Capital Cost (\$/kW)	COE Margin (%)
40,000	231.3	38.2	1,069	11.2
25,000 (base)	231.3	38.2	1,069	11.0
10,000	231.3	38.2	1,069	9.8
5,000	231.3	38.2	1,069	8.1
2,000	231.3	38.2	1,069	-8.5
1,000	231.3	38.2	1,069	-34.7

5.6 Combustor Pressure Loss

The pressure loss through the combustor-and-cyclone flow path affects the expansion pressure ratio of, and the power produced by, the gas turbine. Table 5-10 and Figure 5-6 show that a 1-percent increase in pressure drop results in a 0.3-percent reduction in COE margin. This effect is minor compared with the effects of other parameters such as combustor outlet temperature and sulfur capture effectiveness (discussed in other sections).

Figure 5-6. COE Margin vs. Combustor/Cyclone Pressure Drop

**Table 5-10. COE Sensitivity to Combustor Pressure Loss
(CWM-Fueled Plant, HHV)**

<u>Combustor Pressure Loss (%)</u>	<u>Net Power (MW)</u>	<u>Plant Efficiency (%)</u>	<u>Capital Cost (\$/kW)</u>	<u>COE Margin (%)</u>
2.0	234.7	38.8	1,054	12.3
5.0	232.6	38.5	1,064	11.4
7.0 (base)	231.2	38.2	1,069	11.0
9.0	229.5	37.9	1,080	10.2

5.7 Combustor Heat Rejection

In the proposed configuration, the high-temperature zones of the slagging combustor are cooled by circulating water from the HRSG high-pressure boiler, effectively removing energy from the gas turbine cycle and moving it directly to the steam turbine cycle. This shift in energy utilization increases the power produced by the plant while it reduces the overall plant thermal efficiency. These offsetting effects reduce the per-kilowatt capital cost but increase the per-kilowatt-hour operating cost. The net economic result is that a 10-percent increase in combustor cooling (based on LHV heat released) causes only a 0.2-percent decrease in COE margin. As long as the cooling energy is returned to the steam cycle, the COE margin is virtually insensitive to combustor heat rejection.

The effect of combustor cooling on COE margin is shown in Table 5-11 and Figure 5-7. For this set of data, all of the heat rejected by the combustor is used by the steam cycle.

**Table 5-11. COE Sensitivity to Combustor Cooling
(Rejected Heat Used By Steam Cycle, HHV)**

<u>Combustor Cooling (% of QLHV)</u>	<u>Net Power (MW)</u>	<u>Plant Efficiency (%)</u>	<u>Capital Cost (\$/kW)</u>	<u>COE Margin (%)</u>
0.0	216.7	39.6	1,071	11.9
6.0	227.3	38.6	1,069	11.2
8.0 (base)	231.3	38.2	1,069	11.0
10.0	235.6	37.9	1,067	10.8

Figure 5-7. COE Margin vs. Combustor Cooling
(CWM-Fueled Plant; Rejected Heat Used by Steam Cycle)

If, instead of being used by the steam turbine cycle, the energy from combustor cooling is rejected to the environment, the impact on COE is dramatically different. Table 5-12 and Figure 5-8 show COE margins between 5.8 and 8.4 percent resulting from unrecovered combustor cooling losses, compared with the 11-percent margin of the Reference Plant.

Table 5-12. COE Sensitivity to Combustor Cooling
(CWM-Fueled Plant; Energy Lost from Cycle, HHV)

Combustor Cooling (% of QLHV)	Net Power (MW)	Plant Efficiency (%)	Capital Cost (\$/kW)	COE Margin (%)
0.0	216.7	39.6	1,071	11.9
6.0	217.1	36.8	1,085	8.4
8.0	217.3	35.9	1,090	7.1
10.0	217.6	35.0	1,095	5.8
8.0 (Base,ref)	231.3	38.2	1,069	11.0

Figure 5-8. COE Margin vs. Combustor Cooling
(Energy Lost from Cycle)

5.8 Natural Gas Prices

In recent years natural gas prices have been more volatile than coal prices. Both the CWM and dry-coal plants have higher COEs than a combined cycle fueled by natural gas at a price of \$4.00/MMBtu, but a change in gas price could make the coal-fueled combined cycle less expensive to operate than its gas-fueled counterpart.

Figure 5-9 shows the strong relationship between natural gas price and COE margin for coal-fueled plants. Over a range of gas prices from \$2 to \$20/MMBtu (gas/coal costs of 1.1 to 11.1), the COE margins of dry-coal-fueled Reference Systems range from -44 percent to +76 percent. The corresponding values for the CWM-fueled plants are -56 percent and +74 percent. COE "break-even" values occur at Gas/Coal price ratios around 2.22 (\$3.99/MMBtu gas) for the CWM-fueled plant, and around 1.98 (\$3.56/MMBtu gas) for the dry-coal-fueled plant.

Figure 5-9. COE Margin Sensitivity to Natural Gas Prices

5.9 Coal Benefication

The effect of various types of coal cleaning on the thermal and economic performance of the PC-Fired Reference System was evaluated in a sensitivity study. Direct Coal-Fueled Reference Systems with no coal cleaning were compared to systems with four different types of physical coal cleaning (including the LICADO process) and two types of chemical coal cleaning. The LICADO coal cleaning process is described in Appendix A and brief descriptions of the other coal cleaning processes are given in Appendix B. The PC-Fueled Reference System without coal cleaning had the best efficiency, plant cost, and COE margin, as shown in the ranked comparisons in Table 5-13. In general, physical coal cleaning alternatives ranked better than the chemical cleaning alternatives. The conventional pulverized coal steam power plant with flue gas desulfurization (PC/FGD) placed last or second-last in all categories.

Table 5-13. Comparative Rankings (1=best, 9=worst)

	Plant Efficiency (Table 5-14)	Plant Cost (Table 5-15)	COE Margin (Table 5-16)
REFERENCE SYSTEMS:			
CWM-Fueled	3	5	5
PC-Fueled	1	1	1
COMPARISON PLANTS:			
PC/FGD	9	9	8
PC/LICADO	4	7	6
PC/PCC-1	5	2	2
PC/PCC-2	7	4	3
PC/PCC-3	6	3	4
PC/TRW	2	6	7
PC/Kennecott	8	8	9

The thermal performance of each of the plants is summarized in Table 5-14. The HHV efficiencies of both Reference Systems and the TRW chemical cleaning process are above 38 percent, and all of the direct coal-fueled gas turbine alternative plants have efficiencies above 36 percent. The relatively large auxiliary requirements of the Kennecott process reduces the net power output and the efficiency by about 4 percent, but this reduction is offset by the high energy recovery of the process.

Table 5-14. Performance Comparisons

	Gas Turb Power (MW)	Stm Turb Power (MW)	Auxil Power (MW)	Net Power (MW)	Coal Feed (lb/h)	HHV Eff. (%)
REFERENCE SYSTEMS:						
CWM-Fueled	172.1	63.9	-4.7	231.3	152,289	38.34%
PC-Fueled	161.3	62.6	-2.0	221.8	139,707	39.98%
COMPARISON PLANTS:						
PC/FGD	-	-	-	220.0	161,653	34.26%
PC/LICADO	161.2	63.2	-4.1	220.3	166,551	37.84%
PC/PCC-1	161.3	63.1	-2.3	222.1	151,220	36.97%
PC/PCC-2	161.3	63.2	-2.5	221.9	151,372	36.91%
PC/PCC-3	161.3	63.1	-2.3	222.1	151,239	36.96%
PC/TRW	161.3	64.2	-3.9	221.5	140,169	39.79%
PC/Kennecott	161.3	63.9	-12.1	213.1	146,875	36.53%

Reference Systems with no coal cleaning or with physical coal cleaning other than LICADO cleaning have total plant costs under \$1200/kW, as shown in Table 5-15. The LICADO process equipment adds about \$200/kW to the cost of the plant, making it cost about the same as a Reference System plant with chemical coal cleaning. The addition of coal cleaning equipment adds between \$21/kW and \$193/kW to the capital cost.

The total plant cost of the PC/FGD comparison plant is about \$400/kW more expensive than the Reference Systems without coal cleaning.

Table 5-15. Capital Cost Comparisons

	Coal Processing (\$/kW)	Total Plant (\$/kW)
REFERENCE SYSTEMS:		
CWM-Fueled	116	1,169
PC-Fueled	162	1,132
COMPARISON PLANTS:		
PC/FGD	-	1,519
PC/LICADO	333	1,300
PC/PCC-1	183	1,145
PC/PCC-2	198	1,159
PC/PCC-3	196	1,158
PC/TRW	290	1,246
PC/Kennecott	355	1,350

The most important comparison of the plants is that of their COE margins (compared to the PC/FGD plant), as shown in Table 5-16. In the table, operating and maintenance (O&M) costs are presented as a single value that includes both fixed and variable costs. The PC-Fueled Reference System plant without coal cleaning shows the most favorable COE margin, followed by conventional physical coal cleaning, the CWM-Fueled plant without coal cleaning, LICADO coal cleaning, and chemical coal cleaning. The case with the Kennecott process was estimated to have a higher COE than that of the PC/FGD plant.

Table 5-16. COE Comparisons

	Capital Charges (\$/MWh)	F&V O&M (\$/MWh)	Consum- ables (\$/MWh)	Fuel (\$/MWh)	Levelized COE (\$/MWh)	COE Margin (%)
REFERENCE SYSTEMS:						
CWM-Fueled	34.3	12.5	18.2	19.0	84.0	11.0%
PC-Fueled	35.9	13.2	10.2	18.2	77.5	17.9%
COMPARISON PLANTS:						
PC/FGD	49.3	18.6	5.3	21.2	94.4	-0-%
PC/LICADO	41.1	15.5	9.9	19.2	85.7	9.2%
PC/PCC-1	36.4	14.3	9.9	19.7	80.2	15.1%
PC/PCC-2	36.8	14.4	9.8	19.7	80.7	14.5%
PC/PCC-3	36.8	14.4	9.9	19.7	80.8	14.5%
PC/TRW	39.6	15.0	15.1	18.3	88.1	6.7%
PC/Kennecott	43.1	16.1	21.9	19.9	101.0	-7.0%

The results of this sensitivity study show that the PC-Fueled gas turbine combined cycle has the best thermal and economic performance when used without supplemental coal cleaning; the sulfur is most effectively removed by the slagging combustor, not by an upstream process.

6 PLANT DESCRIPTION

The coal-fueled gas turbine combined cycle power plant is described in the the following sections:

- Section 6.1 Fuel Processing
- Section 6.2 Combustion Turbine Assembly
- Section 6.3 Steam Turbine Cycle
- Section 6.4 Slag Disposal System

6.1 Fuel Processing

The fuel processing facility performs all the functions needed to convert coal as received into a slagging combustor fuel, whether it is a coal-water slurry or dry pulverized coal. Table 6-1 is a brief functional overview of the two fuel processing systems.

Table 6-1. Fuel Processing Characteristics

<u>Turbine Fuel</u>	<u>Dry Coal</u>	<u>60/40 CWM</u>
Receiving and Storage	X	X
Reclaim and Storage	X	X
Crushing, Drying and Storage	X	-
Pulverizing, Grinding	X	X
Slurry Production	-	X
Slurry Storage	-	X
Fuel Injection	X	X
Refuse Reclaim & Disposal	X	X
Site Work	X	X
Miscellaneous	X	X

Table 6-2 characterizes the two coal fuels. The delivered coal in both cases is Pittsburgh No. 8.

Table 6-2. Coal and CWM Characteristics

<u>Turbine Fuel</u>	<u>Dry Coal</u>	<u>60/40 CWM</u>	
Carbon	74.45	44.67	%(wt)
Hydrogen	4.97	2.98	%(wt)
Nitrogen	1.51	0.91	%(wt)
Oxygen	6.17	3.70	%(wt)
Sulfur	3.00	1.80	%(wt)
Moisture	2.51	41.51	%(wt)
Ash	7.39	4.43	%(wt)
Higher Heating Value	13,555	8,133	Btu/lb

The slurry processing facility and the dry coal processing facility are described below in greater detail.

Slurry Processing Facility

The coal slurry production facility supplies all the fuel for the 233 MW gas turbine combined cycle operating at 70-percent capacity factor. This facility is located at the power plant.

The fuel preparation facility converts Pittsburgh No. 8 lump coal into a coal-water fuel. The fuel processing consists of four major processes: coal receiving and storage, coal reclaim and storage, coal slurry production, and slurry storage and feed.

Receiving and Storage. Pittsburgh No. 8 coal, sized at 1-1/2" x 0", is received at the power plant from unit trains consisting of 60 or 70 100-ton capacity bottom-dump cars. The rail unloading system consists of a double track with unloading hoppers installed beneath the railroad siding. The cars can be thawed, if needed, by electrical infrared radiant heaters. Two car shakers are provided to assist in dumping the cars. Vibrating feeders beneath the track hoppers feed coal to an inclined belt conveyor, which delivers coal to the active storage pile. A telescopic chute provides minimized dusting as coal discharges to the pile.

Two coal piles are provided: active and inactive. The active pile, which contains enough coal for 72 hours of operation at rated capacity, is located at the conveyor delivery point. The adjacent inactive coal storage pile is designed to store enough coal for 60 days of normal operation.

Reclaim and Storage. The reclaim system transfers coal from the coal pile to the fuel processing area. Coal is conveyed from two reclaim hoppers, located under the active storage pile, to the inclined belt conveyor by two vibrating feeders. The belt conveyor discharges coal onto a double-deck screen that passes 1/4" x 0" coal to a transfer chute. A hammer mill reduces the rest of the coal to the same size. A 456-foot belt conveyor moves the coal from the screen and hammer mill to two 1,000-ton slurry feed bins.

CSM Production. The fuel production rate was calculated to be 470 gpm. The slurry facility is designed for a production rate of 550 gpm to allow for 24 hours of maintenance per week. Under normal conditions, the required 470 gpm is sent to the combustion turbine while 80 gpm goes to storage.

The major components of the slurry production facility are:

Ball Mill - The ball mill is a wet grinding device that converts 1/4" x 0" coal into coal particles less than 100 mesh (150 microns) in size. Oversize particles are recycled through the ball mill by a belt conveyor.

Sieve Bend - The ball mill discharge is diluted to 12 percent solids, then screened for oversize particles in two sieve bends before flowing to the centrifuge dryers.

Centrifuge Dryers - Ten high-speed centrifuges remove moisture to achieve a final dry coal flow with 6 percent moisture.

Slurry Preparation - Dried coal is discharged to the coal-water mixing tanks, where chemical additives and additional water are added to produce the required slurry composition. Demineralized water used to minimize any alkali and other trace metal contamination.

Refuse Reclaim and Disposal - The tailings from the drying mills are collected into a static thickener, from which processed water is pumped to the plant water holding tank for recirculation. A waste slurry containing 20 percent solids is pumped to two high-speed centrifuges, which dry the refuse to 6-percent moisture. This refuse is delivered to an off-site ash disposal facility.

CWM Storage and Feed. The slurry is collected in an agitated sump for distribution to either the temporary storage tank or the gas turbine combustor. The three-day supply of stored slurry is mixed with a stabilizer to assure the stability of the mixture during storage. Three pumps transport 550 gpm of slurry to the fuel tank so the combustor can be fueled at full load while the storage tank is being replenished at 80 gpm.

Dry Coal Processing Facility

The dry coal production facility supplies all the fuel for the 222 MW combustion turbine combined cycle operating at 70-percent capacity factor. This facility is located at the power plant.

The fuel preparation facility converts Pittsburgh No. 8 lump coal into a pulverized coal fuel. The fuel processing consists of four major processes: receiving and storage, reclaim and storage, crushing and storage, and coal injection.

Receiving and Storage. Pittsburgh No. 8 coal, sized at 1-1/2" x 0", is received at the power plant from unit trains consisting of 60 or 70 100-ton capacity bottom-dump cars. The rail unloading system consists of a double track with unloading hoppers installed beneath the railroad siding. The cars can be thawed, if needed, by electrical infrared radiant heaters. Two car shakers are provided to assist in dumping the cars. Vibrating feeders beneath the track hoppers feed coal to an inclined belt conveyor, which delivers coal to the active storage pile. A telescopic chute provides minimized dusting as coal discharges to the pile.

Two coal piles are provided: active and inactive. The active pile, which contains enough coal for 72 hours of operation at rated capacity, is located at the conveyor delivery point. The adjacent inactive coal storage pile is designed to store enough coal for 60 days of normal operation.

Reclaim and Storage. The reclaim system transfers coal from the coal pile to the fuel processing area. Coal is conveyed from two reclaim hoppers, located under the active storage pile, to the inclined belt conveyor by two vibrating feeders. The belt conveyor discharges coal onto a double-deck screen that

passes 1/4" x 0" coal to a transfer chute. A hammer mill reduces the rest of the coal to the same size. A 456-foot belt conveyor moves the coal from the screen and hammer mill to two 1,000-ton feed bins.

Crushing and Storage. The coal is conveyed from the feed bins to secondary crushers and dryers by vibrating feeders. The product coal is conveyed to surge bins, which feed three 50-percent pulverizers. The pulverizer system, which includes baghouse recovery, feeds the coal injection system through a set of lock hoppers.

Coal Injection. Pulverized coal is injected into the combustors by a Petrocarb-type lock hopper system. This 100-percent redundant system injects coal at a rate of 140,000 lb/hr.

6.2 Combustion Turbine Assembly

The combustion turbine assembly is a pedestal-mounted engine supported by two bearings on a single shaft. The assembly includes an axial flow compressor, an external combustor, a reaction turbine, and associated piping and wiring. The assembly is shipped with rotor in place. The rotor is supported by two tilting pad journal bearings and a double-acting, tilting pad thrust bearing. The engine uses cold-end drive with a rigid coupling at drive end. The turbine uses horizontal split case construction. The first row of vanes can be replaced through access ports, without lifting the cylinder covers.

The main components of the combustion turbine assembly are:

- Multi-stage axial flow compressor
- External combustion assembly
- Four-stage reaction type turbine

The combustion turbine assembly also includes a start-up fuel system with starting air atomizing; fire detection and protection of exhaust end bearing; inlet silencing to 59 dbA; an enclosure with ventilation and lighting; and, a Halon fire protection system.

Table 6-3 summarizes the thermal performance of both reference combustion turbines.

Table 6-3. Combustion Turbine Performance Data

<u>Turbine Fuel</u>	<u>Dry Coal</u>	<u>60/40 CWM</u>	
Turbines per Plant	2	2	
Cycle Pressure Ratio	14.0	14.0	atm
Firing Temperature	1850	1850	°F
Expander Power	419,829	430,883	kW
Compressor Power	(253,885)	(253,861)	kW
Auxiliary Power	(581)	(620)	kW
Losses	(4,059)	(4,267)	kW
Combustion Turbine Net Power	161,304	172,136	kW

The combustion turbine expander is cooled by two air streams from the compressor as shown in Figure 2-4. Water cooling of the slagging combustor is used to augment steam production in the HRSGs. Stream data for both the CWM-fueled and dry coal-fueled cases are tabulated in Table 6-4.

Table 6-4. Combustion Turbine Stream Data

CWM-FUELED SYSTEM Loc Description	Press psia	Temp °F	Flow lb/h
17 Compressor Air Inlet	14.7	59.0	5,395,896
19 Compressor LP Cooling Exit	105.3	507.1	118,845
20 Compressor HP Cooling Exit	203.7	714.1	393,861
24 Compressor Air Exit	199.3	714.1	4,883,190
34 Combustor Gas Exit	185.4	1850.0	5,130,836
35 Expander HP Cooling Inlet	202.8	640.5	393,861
36 Expander LP Cooling Inlet	103.2	507.1	118,845
40 Expander Exhaust	15.13	715.1	5,643,542
47 Combustor Fuel Inlet	280.7	59.0	253,815
120 Cooling Water Inlet	660.3	417.8	2,857,492
122 Cooling Water Exit	403.9	468.0	2,857,492
DRY COAL-FUELED SYSTEM Loc Description	Press psia	Temp °F	Flow lb/h
17 Compressor Air Inlet	14.7	59.0	5,395,896
19 Compressor LP Cooling Exit	105.3	507.1	117,232
20 Compressor HP Cooling Exit	203.7	714.1	388,515
24 Compressor Air Exit	199.3	714.1	4,890,149
34 Combustor Gas Exit	185.4	1850.0	5,048,972
35 Expander HP Cooling Inlet	202.8	640.5	388,515
36 Expander LP Cooling Inlet	103.2	507.1	117,232
40 Expander Exhaust	15.13	713.8	5,554,719
47 Combustor Fuel Inlet	280.7	59.0	139,702
120 Cooling Water Inlet	660.3	417.8	2,621,524
122 Cooling Water Exit	403.9	468.0	2,621,524

The turbomachinery for the Reference System is assumed to be designed for the operating conditions of the Reference System; this is not an existing turbine operating at Reference System conditions. The compressor and turbine efficiencies are the efficiencies of the W501B operating on natural gas. Operating with the flows and temperatures of the Reference System, however, an actual W501B would probably not match the performance of the Reference System turbine, because it would be operating at off-design conditions. The performance of the 501B-type turbine used for the Reference System, but fueled by natural gas, is shown in Table 6-5.

Table 6-5. Turbine Performance With Natural Gas

Compressor Pressure Ratio	14:1	14:1
Inlet Air Flow, lb/s	749	749
Combustor Exit Temperature, °F	1850	2000
Exhaust Temperature, °F	703	769
Exhaust Flow, lb/s	767	769
Generator output, kW	86,571	96,726
Natural Gas Energy, MBtu/h (HHV)	948	1,052
Natural Gas Energy, MBtu/h (LHV)	854	948
Heat Rate, Btu/kWh (HHV)	10,944	10,879
Heat Rate, Btu/kWh (LHV)	9,865	9,806

6.2.1 Compressor

The 19-stage axial compressor has variable-angle inlet guide vanes and tuned stainless steel blades. The stainless steel vanes are inner shrouded to provide a rugged diaphragm assembly, and coated with low temperature, aluminum-rich coating to prevent corrosion. Each stage is provided with stepped labyrinth seals. Vane assemblies can be removed without removing the rotor.

The compressor used is aerodynamically similar to the compressor of the Westinghouse W501B gas turbine. The compressor is assumed to have an infinitesimal stage (polytropic) efficiency of 0.9057, resulting in an isentropic efficiency of 0.86 when operated at the design pressure ratio.

6.2.2 Slagging Combustor

The slagging combustor, shown in Figure 6-1, is a modular unit with three principal stages. The first stage is the primary combustion zone or compartment. Coal and pre-heated compressed air, enter the primary zone coaxially through several, equally spaced injection nozzles. This coaxial injection promotes intense air and coal mixing and rapid particle heat-up and devolatilization, which minimize carbon burn-out time.

The incoming coal-air jets converge at the combustor center line and form one vertical jet which impacts the combustor dome. This forms a toroidal vortex which provides the mechanisms for flame stabilization and centrifugal separation of larger ash and slag particles. The separated ash and slag form a stable flowing layer on the combustor walls. The vertical geometry of this stage allows gravity to assist in the removal of the molten slag. Fuel-rich conditions in the primary combustion zone inhibit NO_x formation from fuel-bound nitrogen. They also provide the necessary reducing conditions for removal and capture of sulfur. The sulfur sorbent, limestone, dolomite, hematite or magnetite is counter-flow injected into the downstream end of the primary zone. The first stage is designed for a coal particle residence time of about 100 ms (for 75 micron sized particles).

For slagging to occur, temperatures throughout the combustion chamber, and particularly at the walls, must not fall below about 2,600°F depending upon the type of coal. These temperatures are achieved by employing a proper air to fuel ratio, by providing adequate design for refractory walls, and sufficient residence time for the reacting coal to air mixture.

The second stage of the direct coal-fired combustor is an efficient impact separator which is closely coupled to the first stage. The impact separator removes particulates carried over with the gas from the primary zone, whether they are sorbent or fine particles of ash.

A slagging cyclone separator has been incorporated into the current subscale combustor configuration. This slagging cyclone provides a further reduction in particulate emissions. The manner in which these particulates are removed represents a novel application of a cyclone separator. At the high temperatures in the combustor second stage, the ash particles to be separated are molten and sticky. Operation with liquid ash alleviates potential problems due to re-entrainment of separated slag and allows the use of higher than normal tangential inlet velocities, thereby generating high inertial separation forces and improved collection performance.

In the third stage of the slagging combustor, complete combustion is accomplished and the combustion gases are tempered to meet turbine inlet requirements. This stage preferably consists of a single module with a pressure shell as is found in the first two stages. Combustion and dilution air are introduced through two rows of injection tubes with approximately sixteen tubes per row circumferentially spaced.

6.2.3 Expander

The four-stage expander has variable reaction with a high temperature drop in the first stage vane. The blades are made of forged superalloy with extended necks. The first two stages are air-cooled and coated with precious metal aluminide. All blades are individually replaceable with the rotor in place.

The vanes are made of cast superalloy, with the first two stages air-cooled. The first stage vanes are replaceable without lifting the cover. The cylinder uses blade ring construction with rollout feature to permit the replacement of vane segments with the rotor in place. Minimum leakage, interstage labyrinth seals are concentrically located by radial keys for independent transient expansion.

The expander is similar to the expander of the Westinghouse W501B gas turbine. The expander is assumed to have an infinitesimal stage (polytropic) efficiency of 0.9159, resulting in an isentropic efficiency of 0.936 when operated at the design pressure ratio.

6.2.4 Generator-Exciter Assembly

The generator-exciter assembly is a direct-connected, hydrogen-cooled, 3600-rpm, non-salient pole unit rated at 0.9 power factor. Coils are insulated with Thermalastic for long life. A permanent magnet generator powers the voltage regulator, which controls the stationary field of a brushless exciter.

The two-pole, 3-phase, 60-Hertz synchronous generator is rated at 13,800 volts. The generator uses:

- Outdoor type construction
- Hydrogen cooling
- Class B insulation
- Temperature detectors in cooler outlet gas and in armature windings
- Lube oil system integral with combustion turbine system
- Seal oil system
- Current transformers
- Neutral grounding transformer and resistor

The exciter assembly is directly connected to generator. The brushless exciter consists of:

- Permanent magnet generator
- Alternating current exciter
- Rotating rectifier
- Space heaters
- Enclosure with lighting

6.2.5 Auxiliaries

The auxiliaries to the combustion turbine assembly consist of:

- Pipe rack assemblies
- Starting package
- Mechanical package
- Electrical/control package
- Coolers
- Inlet air system
- Exhaust Gas System
- Auxiliary transformers
- Isolated Phase Bus
- Fire protection system.

6.3 Steam Turbine Cycle

The components included in the steam turbine cycle are the heat recovery steam generator (HRSG), the reheat steam turbine, the generator, and the condenser. The steam bottoming cycle uses relatively low dual-pressure steam with reheat. There are no feedwater heating extractions above the deaerator. A single-chamber, double-pass condenser is connected to the low-pressure turbine. Part-load operation is conducted with sliding pressure under single-valve control.

The unfired dual-pressure boiler includes superheater, reheater, and HP and IP evaporators that provide motive steam, and an LP evaporator that provides steam for the deaerator. The heat exchanger surfaces are extended on the gas side, and the construction is modular to minimize field assembly.

The boilers use forced circulation. Feedwater treatment consists of chemical treatment, deaeration, and blowdown from the steam drums. The gas leaving the HRSG is 50°F hotter than the acid dewpoint of the products of combustion, so corrosion of the HRSG is not expected to be a problem.

The steam turbine uses full annulus admission for uniform thermal expansion, fast starting, and fast load change. The steam turbine is directly connected to a hydrogen-cooled, 3600-rpm, 60-Hz electric generator. Speed governing is provided to allow the steam turbine to be accelerated to and synchronized with the 60-Hz system. The performance characteristics of the reheat steam turbine cycles for both the CWM-fueled and the dry coal-fueled systems are tabulated in Table 6-6.

Table 6-6. Steam Turbine Performance Data

Reference System Fuel	60/40 CWM	Dry Coal	
<u>Combustor Cooling Water</u>			
Cooling Water Flow	2,857,492	2,621,524	lb/h
Temperature entering Combustor	417.8	417.8	°F
Temperature leaving Combustor	468.0	468.0	°F
Energy transferred to HRSG	159.6	146.4	MMBtu/h
<u>HP Turbine</u>			
Throttle Pressure	367	367	psia
Throttle Temperature	680	680	°F
HP Steam Turbine Power	15,721	15,310	kW
<u>IP Turbine</u>			
Reheat Pressure	92	92	psia
Reheat Temperature	680	680	°F
IP Steam Turbine Power	16,705	16,386	kW
<u>LP Turbine</u>			
Inlet Pressure	30	30	psia
Inlet Temperature	680	680	°F
LP Steam Turbine Power	33,710	33,060	kW
<u>Condenser</u>			
Inlet Pressure	1.5	1.5	in. Hg
Inlet Temperature	92.9	92.9	°F
<u>Losses</u>			
Auxiliary Power	(392)	(400)	kW
Losses	(1,826)	(1,802)	kW
Steam Turbine Net Power	63,917	62,555	kW

6.4 Slag Disposal System

Molten slag is drained from each of the two combustors into two corresponding quench areas, where the slag is cooled and fractured by a water spray as illustrated in Figure 6-1.

The molten slag is water-quenched by several nozzles in the quenching zone. This cools the slag until it is substantially solid pieces. These pieces drop into a water bath. A moving chain conveyer in the bottom of the water bath moves the chunks of slag to a series of roller crushers in the slurring/processing region. The crushed slag is slurried in water, preferably with an impeller and allowed to return to atmospheric pressure by passing out of the apparatus through a pressure let-down valve. Slurry exiting the pressure let-down valve is fed into a recycling zone. The slurry is preferably pumped into a settling tank. The settling tank separates out the water from the slag particles to enable the removal of slag tailings and the recirculation of water back to the system. The slag tailings can be removed in a road or rail vehicle, or equivalent conveyer or transportation means. The recycled water can be pumped either back into the slurring step or back into nozzles for quenching molten slag.

Figure 6-1. Direct Coal-Fired Combustion Turbine System

APPENDIX A - LICADO COAL CLEANING PROCESS

The LICADO (Liquid Carbon DiOxide) process is a novel, advanced coal cleaning method conceived and patented by the University of Pittsburgh. Liquid carbon dioxide at high pressure (about 850 psig) and room temperature is used to separate clean coal from an aqueous suspension, leaving the ash and pyrite constituents in the water phase. Since liquid CO_2 is immiscible in water, wets clean coal particles, and does not wet ash or pyrite particles, these properties result in the separation of clean coal from the water, ash, and pyrite at the liquid CO_2 -water interface. The effectiveness of this process has been demonstrated in bench-scale batch tests and in continuous tests up to 10 lb/hr at the University of Pittsburgh. These initial tests resulted in removal of up to 90% of the ash and pyritic sulfur.

PLANT DESCRIPTION

The following discussion of the plant refers to the components and their arrangement, as shown in Figure A-1.

Feed Coal Preparation

Feed coal preparation consists of a coal bin, crusher, weight indicator, wet grinder, slurry sump, coal/water slurry pumps, and the appropriate valves, cyclone classifier, feed storage, instrumentation, and controls. Here the coal is ground to 200 mesh for feed supply.

The coal/water slurry feed system employs pressurized recycle water. Maintaining the recycle water at high pressure reduces the substantial amount of absorbed CO_2 lost, if the water were decompressed.

Some elements of the pressurized water feed system require multiple components based on plant requirements of coal feed slurry concentration with 10% weight solids, 1000 psig pressure, and vessel fabrication constraints of keeping the wall thickness between 1 to 2 inches.

A bucket lift delivers the fine coal to the coal feed receiver, which is at atmospheric pressure. Coal passes into one of two lock hoppers through a pipe and ball valve. The lock hoppers feed coal to the slurry tanks, which hold the slurry supply at about 840 psig. The total capacity of the lock hoppers is an 80-minute supply of feed coal, and the total capacity of the slurry tanks is a 60-minute supply of slurry. Mechanical mixers keep the coal/water slurry homogeneous in the on-stream tank, while the slurry pump drains the tank and supplies the hydraulic mixer.

Figure A-1. LICADO Flow Diagram

Liquid CO₂ Processing

The liquid CO₂ processing loop pump circulates subcooled liquid CO₂ at approximately 860 psig and 70°F through the hydraulic mixer, CO₂/water separator, CO₂ clean coal filter, and CO₂ loop cooler. Insulation covering the subsystem in conjunction with the CO₂ cooler allows loop temperature control. A pressurizer maintains CO₂ saturation pressure at about 840 psig through a temperature control system.

In the hydraulic mixer, liquid CO₂ first contacts the coal/water slurry. Coal/water slurry enters along the axis of the mixer pipe while the liquid CO₂ is injected into the water slurry through a multiholed nozzle. The 73 one-eighth inch diameter streams degrade to droplets due to the drag created on the CO₂ stream by the difference in velocities of the coal/water and liquid CO₂. This mixture of coal/water/CO₂ droplets flows through a series of orifice disks which further promote turbulence and thoroughly mix the stream. Orifice plates are of two patterns and alternate along the length of the mixer.

The unit has four separation stages within one pressurized column. The separator column has a pressure shell of Schedule 40, 304 stainless steel pipe. The column bottom is a steep conical section with a center discharge to facilitate fluid flow with a high solids concentration.

The coal/CO₂ exits the column through two diametrically opposed pipes below the unit top. Water containing refuse and pyritic sulfur issues from the bottom. The raw coal/water/CO₂ feed nozzle is approximately one-third the distance up the column. The top of the column is closed by a 600-lb blind flange from which all of the column internals are supported or pass through. All of the internals are removed from the column when the top flange is raised.

Each separator stage consists of a conical flow tube through which the mixture of coal/water/CO₂ is accelerated by a propeller at the lower and larger diameter end. Also, attached to the lower or base end of the conical flow tube is a tubular ring with eight small holes directed toward the center of the cone and propeller. Either CO₂ or water may be injected through these holes to enhance coal/refuse separation. The mixer velocity, as it passes through the conical flow tube, will be increased and be discharged at 45° toward the column periphery. The heavier refuse/ water will travel further and concentrate near the column wall, while the lighter coal/CO₂ will remain nearer the center of the column. Stages are separated by a quiescent zone.

All mixing blades are positioned along a single central shaft driven from above through a magnetic coupling to the externally mounted motor.

Clean Coal Recovery

Cleaned coal and CO₂ exit the top of the separators (approximately 12 percent solids by weight). The coal/CO₂ slurry flows through a cyclone into the auger filters operating at saturated conditions. The feed slurry liquid level is maintained in the filter medium auger leg with saturated vapor above the liquid in the remaining auger leg and in the vertical coal receiver leg. The auger constantly turns at 1 to 3 RPM, stripping coal from inside the filter medium and delivering it to the top of the unit where it falls into the coal receiver leg. The coal in each filter is cyclically discharged into the product collection vessel (depressurizer tank), in which it is depressurized. The CO₂ goes to a CO₂ accumulator while the clean coal is pneumatically transported to large storage silos. Filtrate (liquid CO₂) from the filters is delivered to the CO₂ loop pressurizer.

Refuse Disposal

Refuse and water are constantly drawn from the bottom of the separator, at about 3-4% wt. solids concentration, through a level control valve and into a cyclone separator within the refuse letdown tank. Water with absorbed CO₂ vents from the top of the cyclone, while concentrated refuse is drained from the bottom. Expanded CO₂ vents to the recycle subsystem while the water is decanted from over the refuse and passes to the pressurized recycle water tank. While the first tank is filling, refuse settling, and water being decanted, the second tank is discharging refuse sludge from the bottom for disposal. Both the product and refuse tanks are duplicated to assure continuous plant operation by switching from Tank 1 after filling to Tank 2.

Gaseous CO₂ Recycle

Some CO₂ will accompany the refuse and product in the depressurizing operation. Economics and considerations require that this gaseous CO₂ be compressed and recycled to the liquid CO₂ loop. The gaseous CO₂ subsystem contains filters, accumulator, compressor, and after-cooler.

Plant Operation

Run of mine coal is loaded into the hopper outside the building and is fed onto a weight feeder inside the building. The feeder conveys the raw coal to a crusher where it is reduced to 1/4 inch and smaller. A ball mill wet grinds the 1/4 inch coal to a 200 mesh top size and discharges it into a sump from which a slurry pump delivers the coal fines to a wet cyclone classifier. The overflow from the cyclone carries the 200 mesh and smaller particles to feed storage, while the cyclone underflow returns oversized material to the ball mill.

From the feed storage, where the excess water drains back to the atmospheric recycle water tank, a bucket conveyer lifts the 200 mesh top size coal to the top of the building and deposits them into the feed receiver. The feed receiver supplies the lock hoppers, which have a combined capacity equal to an 80-minute supply. Ball valves isolate the feed receiver from the lock hoppers to allow pressurization of the lock hoppers with CO₂ saturated vapor. From this point, the slurry tank, refuse letdown tank, coal depressurizer, and recycle water tank are interconnected with a pressure equalization system, which is connected to the vapor space in the pressurizer and maintains these vessels at CO₂ saturation pressure of 840 psig at 70°F. However, each tank may be isolated from the equalization system, if desired.

The slurry tanks have a combined capacity equal to a 60-minute process feed supply. The number of tanks is a multiple of 3. While Tank 1 is on-stream, Tank 2 is mixing and Tank 3 is being filled. To fill a tank, water is first filled to a prescribed level, the stirrer turned on, and then the contents of a lock hopper is deposited into the slurry tank. The concentration may be changed by controlling the amount of coal added.

A slurry pump increases the feed pressure to approximately 900 psig to supply the hydraulic mixer. Liquid CO₂ is injected into the slurry within the mixer. The mixer has a series of eight orifice plates through which the coal/water/CO₂ mixture passes. Pressure drop through the mixer is calculated to be approximately 50 psig.

The mixture enters the separator which has four stages, each of which separate and concentrate the coal/CO₂ and water/refuse phases of the previous stage.

The coal/CO₂ phase concentrates near the center of the column and exits the unit at the top, while the heavier water/refuse phase accumulates at the column periphery and exits at the bottom of the column.

The slurry pump flow rate, plus the CO₂ flow rate equal the total separator inlet flow, while the outlet flow is balanced by control of the water/refuse stream exit rate through the bottom CO₂/water interface level indication. Thus, the remaining coal/CO₂ outlet flow is automatically established.

Water, refuse, and absorbed CO₂ are drawn from the bottom of the separation vessel and into the liquid cyclone within one of the two refuse letdown tanks. Concentrated solids exit from the bottom of the cyclone, while water and absorbed CO₂ vent from the top. Solids will concentrate in the tank bottom while water is decanted from over the refuse and returned to the pressurized recycle water tank. When a prescribed solids level is reached in the on-line tank, it will be isolated from the system; and flow will be diverted to the second tank. CO₂ will be vented to the accumulator from the first tank to reduce its pressure to about 25 psig. This pressure will be used to force the refuse sludge out of the vessel into disposal drums.

At some time during operation of the plant, runs will be made to investigate continuous venting of refuse sludge and recycle water from one tank only; thus, the second tank will be held in reserve.

The same product will be used for the coal depressurizing tanks.

The product stream (approximately 12 percent solids, coal/CO₂) from the top of the separator is concentrated in a cyclone to about 25-percent solids before it enters one of two auger filters. The second filter is a standby unit. Any coal fines in the overflow are recirculated to the separator with the CO₂ flow.

Coal cake is delivered by the auger to the receiver leg and flows through into the depressurizer tank. At a prescribed level in the depressurizer tank, it is isolated from the system; CO₂ is vented to the accumulator until the tank pressure is 10 psig. Then this pressure is used to discharge the product. Meanwhile, the coal filter cake continues to fill the receiver leg of the filter until the emptied receiving tank is put back into the system, at which time the cycle is repeated.

APPENDIX B - OTHER COAL CLEANING PROCESSES

Three physical coal cleaning (PCC) and two chemical coal cleaning (CCC) processes were selected to represent alternatives to LICADO coal cleaning and no coal cleaning. The processes are:

Physical Coal Cleaning

PCC I: (Dense-Medium (DM) Vessels, DM Cyclones, Froth Flotation)
PCC II: (DM Cyclones at Low and High Gravity, Froth Flotation)
PCC III: (DM Cyclones, Concentrating Tables)

Chemical Coal Cleaning

TRW: Gravichem (Ferric Sulfate Oxidation of Sulfur)
Kennecott: (Oxygen Oxidation of Sulfur)

PROCESS DESCRIPTIONS

The process descriptions are taken from Evaluation of Physical/Chemical Coal Cleaning and Flue Gas Desulfurization, Interagency Energy/Environment R&D Program Report, United States Environmental Protection Agency, EPA-600/7-79-250 (November 1979).

The three PCC processes represent widely used commercial technology; they were selected for study because they offer a relatively high degree of sulfur reduction compared with other PCC methods. The two CCC processes are not commercial processes, but have been developed to bench-scale or limited pilot-plant stages. Additional development could make significant changes in their technical, and thus economic, potential for sulfur reduction. The PCC processes are somewhat limited in their desulfurization application because they removed only pyritic sulfur. One of the CCC processes removes significant quantities of organic sulfur in addition to pyritic sulfur.

PCC I: Dense-Medium (DM) Vessels, DM Cyclones, Froth Flotation

In the PCC-I process, raw coal is crushed to three size fractions, each of which is processed separately. A DM vessel is used for the coarse coal, a DM cyclone for the intermediate-sized coal, and froth flotation for the fine coal. The process includes raw coal sizing, coarse coal cleaning, intermediate coal cleaning, and fine coal cleaning. An additional grinding step was added to the basic PCC-I process to pulverize the coal for the slagging combustor.

PCC II: DM Cyclones at Low and High Gravity, Froth Flotation

In the PCC-II process, the coal is crushed, then the coarse fraction is processed in DM cyclones operated at low specific gravity to produce a small overflow of highly cleaned coal. The bottoms from the low-gravity cyclones are pumped to high-gravity cyclones to produce "middling" (medium-quality coal) and refuse. The fine coal is recovered by froth flotation. The process includes raw coal sizing, low-gravity cleaning, normal-gravity cleaning, and fine coal cleaning. An additional grinding step was added to the basic PCC-II process to pulverize the coal for the slagging combustor.

PCC III: DM Cyclones, Concentrating Tables

In the PCC-III process, about two-thirds of the crushed coal is a coarse fraction treated in DM cyclones. A fine coal fraction, amounting to about one-third of the coal feed, is cleaned on concentrating tables. The remaining very fine coal fraction is thickened and filtered without cleaning and is added to the clean coal product. The process includes raw coal sizing, coarse coal cleaning, and fine coal cleaning. An additional grinding step was added to the basic PCC-III process to pulverize the coal for the slagging combustor.

TRW Gravichem: Ferric Sulfate Oxidation of Sulfur

TRW Defense and Space Systems Group developed the Gravichem coal desulfurization process and claims the process will remove 90 to 99 percent of the pyritic sulfur, but none of the organic sulfur. The process has been demonstrated in an 8-ton-per-day plant at a TRW test site. The process consists of a sink-float gravity separation, followed by selective oxidation of the pyrite in the sink fraction with ferric sulfate, followed by acetone leaching to recover elemental sulfur.

The basic process includes grinding to 28 mesh and briquetting the final product. To make the final product consistent with the other slagging combustor fuels, additional grinding was added to reduce the coal to 100 mesh, and the briquetting step was removed. The added cost of grinding and the reduced cost of briquetting were assumed to cancel each other.

Kennecott: Oxygen Oxidation of Sulfur

Kennecott Copper Corporation began development of this process in 1970 and continued work through 1975 when the process was demonstrated at a bench-scale level. The process consists of an oxidation system in which 85 to 95 percent of the pyritic sulfur and up to 30 percent of the organic sulfur in the coal are oxidized to soluble sulfates by sparging oxygen through the pulverized coal at a high temperature and pressure.

The basic process includes grinding to 28 mesh and pelletizing the final product. To make the final product consistent with the other slagging combustor fuels, additional grinding was added to reduce the coal to 100 mesh, and the pelletizing step was removed. The added cost of grinding and the reduced cost of pelletizing were assumed to cancel each other.

COST AND POWER ALGORITHMS

Each coal cleaning process was analyzed using four variations of coal with sulfur contents of 0.7%, 2.0%, 3.5%, and 5.0%. The 3.5-percent-sulfur cases were used as the bases for comparison because they were closest to the 3-percent sulfur content of the Pittsburgh No. 8 coal used for the slagging combustor.

The estimated total direct cost (TDC) of each complete process is assumed to be a function of the inlet coal feed rate and the degree of sulfur removal. The cost algorithm and tabulated constants below are based on the costs of plants that use 3.5-percent-sulfur as the feed coal.

$$\begin{aligned} \text{TDC} = & \text{Cref}(\text{Wc}/\text{Wref})^{0.7} (\text{Sr}/\text{Srref})^e \\ & + \text{PSref}(\text{Wc}/38.35)^{0.65} + \text{Clref}(\text{Wc}/38.35)^{0.75} \\ & + \text{MXref}(\text{Wc}/38.35)^{0.5} \end{aligned}$$

where:

TDC	=	Total Direct Cost, thousands of 1989 dollars
Clref	=	Coal Injection System reference cost, k\$(1989) [see Table B-1]
Cref	=	TDC of reference plant, k\$(1989) [see Table B-1]
e	=	Capacity ratio exponent, dimensionless [see Table B-1]
PSref	=	Pulverizer System reference cost, k\$(1989) [see Table-1]
MXref	=	Miscellaneous reference cost, k\$(1989) [see Table B-1]
Sr	=	Pyritic sulfur removal, decimal
Srref	=	Pyritic sulfur removal of reference plant, decimal [see Table B-1]
Wc	=	Coal feed rate, lb/s
Wref	=	Coal feed rate of reference plant, lb/s [see Table B-1]

Table B-1. Key Cost and Design Parameters

	PCC I	PCC II	PCC III	TRW	KENNECOTT
Cref, k\$(1989)	34,532	42,646	41,766	138,277	166,322
Clref, k\$(1989)	5,017	5,017	5,017	-0-	-0-
MXref, k\$(1989)	990	990	990	-0-	-0-
PSref, k\$(1989)	6,350	6,350	6,350	-0-	-0-
Ref. coal feed, t/yr	4,480,000	4,499,000	4,148,000	4,127,000	4,326,000
Wref, lb/s	414.82	416.57	416.11	382.13	400.56
Srref, decimal	0.5069	0.5285	0.4728	0.9786	0.8811
e	0.1	0.1	0.0	0.0	4.4

The auxiliary power and consumables requirements for each complete process are assumed to be a function of the inlet coal feed rate. The power and consumables algorithms and tabulated constants below are based on the costs of plants that use 3.5-percent-sulfur as the feed coal.

Power

$$Pwr = Wc * 3600 / 1000 (Cp + 10^x)$$

Pwr = Auxiliary power requirements, kW

Cp = Power Coefficient, kWh/lb [see Table B-2]

Wc = Coal feed rate, lb/s

x = Grinding exponent (PCC-I, II, and III only)

$$= 2.27 - 1.673(Ly) + 0.412(Ly^2) - 0.033(Ly^3)$$

Ly = Log of final grind size, microns, $\log_{10}(14859/\text{mesh})$

Process water

$$Wpw = Cpw * Wc * 3600 / 1000$$

Wpw = Process water requirement, lb/h

Cpw = Process water coefficient, lb/lb [see Table B-2]

Diesel Fuel

$$Wdf = Cdf * Wc * 3600 / 1000$$

Wdf = Diesel fuel requirement, lb/h

Cdf = Diesel fuel coefficient, lb/lb [see Table B-2]

Natural Gas

$$Wng = Cng * Wc * 3600 / 1000$$

Wng = Natural gas requirement, lb/h

Cng = Natural gas coefficient, lb/lb [see Table B-2]

Chemicals

$$Wch = Cch * Wc * 3600 / 1000$$

Wch = Chemical feed required, lb/h

Cch = Chemical feed coefficient, lb/lb [see Table B-2]

The "cost factor" in the table is the cost of all chemicals plus other operating costs -- analyses, operating labor, and process steam -- divided by the weight flow of chemicals. Annual maintenance expenses, representing 6 percent of the capital cost per year, were also based on the values in the report. The cost factors are higher for the physical coal cleaning processes than for the chemical coal cleaning processes because of maintenance costs (which are large compared to the costs of actual consumables), and because of consumable feed rates (which are lower than for the chemical processes).

Table B-2. Process Consumables (normalized per 1000 lb feed coal)

	PCC I	PCC II	PCC III	TRW	KENNECOTT
Cp, kWh/klb	1.60	2.92	1.43	22.06	76.312
Cpw, lb/klb	36.86	65.81	21.62	14665.1	8426.66
Cdf, lb/klb	0.09010	0.09194	0.08462	-0-	-0-
Cng, lb/klb	-0-	-0-	-0-	-0-	-0-
Cch, lb/klb	0.56919	0.60457	0.40498	47.97061	248.4061
Cost Factor, \$/klb	521.32	492.11	708.79	88.60	38.63

END DATE
6-1-92