1 OF 1

- Use of buried waste records for characterization—This method has been and will continue to be used in conjunction with the technology used. However, content and location records of buried waste at the RWMC are often not accurate or explicit enough to adequately judge the most effective treatment technology, or to know what will be found upon excavation.

- Ground-penetrating radar—This technology has been attempted with

2
EGG-WTD-9980
November 1991

**Idaho
National
Engineering
Laboratory**

*Managed
by the U.S.
Department
of Energy*

INFORMAL REPORT

**Identification of Buried Structures
(Aerial Surveillance and Analysis of
Buried Waste)
Long-Range Project Plan**

K. L. Williams

*Work performed under
DOE Contract
No. DE-AC07-76ID01570*

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights. References herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

EGG-WTD--9980

DE92 012216

**Identification of Buried Structures
(Aerial Surveillance and Analysis of Buried Waste)
Long-Range Project Plan**

K. L. Williams

Published November 1991

**Idaho National Engineering Laboratory
EG&G Idaho, Inc.
Idaho Falls, Idaho 83415**

**Prepared for the
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
Under DOE Field Office, Idaho
Contract DE-AC07-76ID01570**

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

IDENTIFICATION OF BURIED STRUCTURES
(Aerial Surveillance and Analysis of Buried Waste)

LONG RANGE PROJECT PLAN
November 1991
EGG-WTD-9980

Prepared by:

Karen L. Williams
Karen L. Williams, Engineering Specialist

11/15/91
Date

Reviewed by:

David E. Shropshire
David E. Shropshire,
Project Demonstration Unit Manager

11/15/91
Date

Reva A. Hyde
Reva A. Hyde, Sr. Engineer
Identification of Buried Structures (IBS)
Project Manager

11/15/91
Date

ABSTRACT

This long-range plan presents the plan (i.e., budget, schedule, justification, and plans for technology deployment) for implementation of the Identification of Buried Structures project. Two subcontractors will test and demonstrate their technologies at the Idaho National Engineering Laboratory during October and November 1991, and will analyze their data and submit final reports to EG&G Idaho, Inc., by the end of December 1991. By February 21, 1992, EG&G Idaho will present a final report to the Department of Energy, assessing the subcontractors' results and recommending further action.

SUMMARY

The objective of the Identification of Buried Structures (IBS) (also known as Aerial Surveillance and Analysis of Buried Waste) project is to investigate the use of airborne geophysical sensors to identify subsurface soil characteristics, and locate buried waste and ordnance at the Idaho National Engineering Laboratory (INEL). The project was initiated per the Department of Energy Headquarter's (DOE-HQ's) instructions via their Idaho Field Office (DOE-ID) to EG&G Idaho, Inc., to perform demonstrations and tests on aerial surveillance and analysis equipment systems during the fall of 1991. If the equipment operates successfully, it would significantly reduce costs and increase both speed and safety for site survey and characterization efforts at several key INEL locations. A Request for Proposal was issued in an attempt to identify possible technologies to accomplish this objective. From the responders, two helicopter-mounted technologies were identified for further investigation, and subcontracts were awarded to Martin Marietta Missile Systems of Orlando, FL, and to EBASCO Environmental Services, Inc., of Idaho Falls, ID.

The purpose of this long-range plan is to present the plan for implementation of the IBS project. The two subcontractors will test and demonstrate their technologies at the INEL during October and November 1991, and will analyze their data and submit final reports to EG&G Idaho by the end of December 1991. By February 21, 1992, EG&G Idaho will present a final report to DOE, assessing the subcontractors' capabilities and recommending further action.

The total cost for this project is estimated at \$1,105K, of which \$793K is for subcontract of the sensor systems. The possible cost savings if the systems are successful at identifying buried structures could be substantial to DOE by reducing safety risks and the time required for characterization of waste and ordnance sites at the INEL, and potentially at DOE sites across the nation. The mobilization and demobilization costs for a subcontractor to perform an aerial surveillance, based on the current IBS subcontracts, are about \$300K total. Therefore, a large area must be surveyed to make the

surveillance cost effective; the area will be estimated and reported in the IBS final report.

This document is based upon the best available information at the time of publishing, and will be revised as necessary, based upon changes in strategy, budget, and resources.

CONTENTS

ABSTRACT	iii
SUMMARY	v
ACRONYMS	ix
1. INTRODUCTION	1
1.1 Technological Need	1
1.2 Alternatives to Technology Development	2
1.3 Technological Application	4
2. OBJECTIVES AND PRINCIPLES	6
2.1 Project Objectives	6
2.2 Basic Scientific Principles	6
2.2.1 Martin Marietta System	7
2.2.2 EBASCO System	7
3. WORK BREAKDOWN STRUCTURE	9
4. WORK SCOPE	11
5. SCHEDULE	13
6. BUDGET	14
6.1 Project Life Cycle Costs	14
6.2 Annual WBS Budget Projections	14
6.3 Annual Funding Category Budget Projections	14
7. RESOURCE ALLOCATION	15
7.1 Annual Resource Projections	15
7.2 Estimated Annual Subcontract Costs	15
8. TECHNOLOGY DEPLOYMENT PLAN	16
8.1 Cooperative/Collaborative Agreements	16
8.2 Applicable Regulations and Requirements	16
8.3 Technology Deployment Strategy	17

8.4 Technology Transfer	18
9. POTENTIAL TECHNOLOGY DEVELOPMENT BENEFITS	20
9.1 Operational	20
9.2 Regulatory Compliance	21
9.3 Institutional	21
9.4 Cost Savings	22
10. CHANGE CONTROL	23
APPENDIX A—LOGIC DIAGRAM	A-1
APPENDIX B—COST ESTIMATE BASIS	B-1

FIGURES

1. Identification of Buried Structures (IBS) Work Breakdown Structure (WBS)	10
--	----

ACRONYMS

ARA II	Auxiliary Reactor Area II
BWID	Buried Waste Integrated Demonstration
CAP	Cost Account Plan (also called a Work Package)
CBD	<i>Commerce Business Daily</i>
COCA	Consent Order and Compliance Agreement
DOE	Department of Energy
DOE-ID	Department of Energy Field Office, Idaho
DOE-HQ	Department of Energy, Headquarters
EC	Environmental Checklist
EM	electromagnetic
EPA	Environmental Protection Agency
ERP	Environmental Restoration Program
IBS	Identification of Buried Structures project (also known as the Aerial Surveillance of Buried Waste project)
INEL	Idaho National Engineering Laboratory
MM	Martin Marietta
NEPA	National Environmental Protection Act
NODA	Naval Ordnance Disposal Area
NPR	New Production Reactor
ORNL	Oak Ridge National Laboratory
PNL	Pacific Northwest Laboratory
RWMC	Radioactive Waste Management Complex
SAR	Safety Analysis Report
SDA	Subsurface Disposal Area
SL-1	Stationary Low-Power Reactor-1
TSA	Transuranic Storage Area
TTP	Technical Task Plan
WBS	Work Breakdown Structure

IDENTIFICATION OF BURIED STRUCTURES (Aerial Surveillance and Analysis of Buried Wastes) LONG-RANGE PROJECT PLAN

1. INTRODUCTION

The Idaho National Engineering Laboratory (INEL) has been designated as the lead Department of Energy (DOE) laboratory for the Buried Waste Integrated Demonstration (BWID) program. In support of BWID and the INEL Environmental Restoration Program (ERP), waste and soil at the Radioactive Waste Management Complex (RWMC) Subsurface Disposal Area (SDA) will be excavated for testing and demonstration of several waste treatment technologies; other treatment technologies will be demonstrated in situ. Records of buried waste content and location at the RWMC are often not accurate or explicit enough to adequately judge the most effective treatment technology, or to know what will be found upon excavation. In addition to the buried waste at the RWMC, there is also buried waste which must be excavated or treated in situ at the Stationary Low-Power Reactor-1 (SL-1) site at Auxiliary Reactor Area II (ARA II). Intrusive methods of identifying buried wastes can spread contamination or generate more wastes which must be disposed of or treated. Some areas of the INEL are also scattered with old ordnance remaining from military tests conducted during the 1940s and 1950s, and some of that ordnance is still live. A nonintrusive method of identifying locations and sizes of ordnance and buried waste would significantly reduce costs and increase both speed and safety for site characterization and retrieval efforts at several key INEL locations.

1.1 Technological Need

Waste burial at the RWMC began in the 1940s and continues today. There is an estimated two million cubic feet of contaminated buried waste intermixed with six million cubic feet of dirt in pits and trenches at the SDA. Depending on the waste contents and the practice at the time, buried waste is contained in cardboard boxes, steel drums, and plywood boxes that are now deteriorating. Original records of what was buried and where it was buried

are often inaccurate or too general to be useful. Without in situ treatment or excavation of the wastes, contaminant migration from the containers will increase. However, treatment or excavation must be preceded by characterization to identify the waste location and types. The sooner and more accurately that identification takes place, the sooner the treatment or excavation work can commence and the more effective it will be. Accurate identification of pit and trench boundaries will minimize disturbance of adjacent contaminated areas and reduce the amount of clean side burden soils to be processed.

DOE sites across the nation have similar buried waste situations, although the extent of the problems vary. Some sites have inaccurate records of where their waste was buried, i.e., wastes are sometimes found unexpectedly in areas where no records indicate that any wastes were buried.

While the technology to detect buried waste is yet to be tested and demonstrated via the Identification of Buried Structures (IBS) project, the system's ability to detect ordnance has already been proven by the Department of Defence and could be useful at the INEL. During the 1940s and 1950s, military tests left many spent and some live ordnance scattered in several areas of the INEL. Construction on any new INEL site has always been preceded by a thorough search and removal of any live ordnance, now conducted in conjunction with the necessary archaeologic survey. The searches have been conducted by personnel surveying the area in question at close range, with the potential hazard of inadvertently exploding any live ordnance and causing injury to workers. Some projects which are currently under consideration for construction at the INEL include the New Production Reactor (NPR) and the Defense Weapons Reconfiguration Complex. Potential INEL sites for these or any other new facilities must be surveyed to find any live ordnance.

1.2 Alternatives to Technology Development

Alternatives to the IBS project's aerial surveillance technologies to identify ordnance and buried waste are:

- Use of buried waste records for characterization--This method has been and will continue to be used in conjunction with the technology used. However, content and location records of buried waste at the RWMC are often not accurate or explicit enough to adequately judge the most effective treatment technology, or to know what will be found upon excavation.
- Ground-penetrating radar--This technology has been attempted with little success at the RWMC, i.e., it was able to approximately locate some targets in the SDA Cold Pit and Pit 9, but was unable to provide accurate depth and target alignment information (letter from J. L. Landon to T. L. Rasmussen, February 6, 1989, "Ground-Penetrating Radar Final Report").
- Shallow seismic reflection--This technology has been used near the RWMC in an attempt to identify soil and geologic structures, with limited success due to the complex shape of the basalt flows (September 16, 1988, Report No. KGS-09/88, "Feasibility of Shallow Seismic Reflection Methods Near the RWMC at the INEL"). It has little potential for identification of ordnance since objects close to the surface do not effectively reflect, and buried waste objects offer even more complicated and noncontiguous underground shapes than the underlying basalt flows.
- Ground-contact magnetic/electromagnetic reconnaissance--This technology was used with some success at the INEL Acid Pit, Cold Test Pit, and Pit 9 of the SDA locating boundaries and collections of metallic objects within one to two meters, but was unable to distinguish the objects. It was not possible to determine pit geometries since reliable data could not be gathered through the approximately one-meter thick frozen top layer of soil. (May 1989, Report to DOE by J. C. Hasbrouck of UNC Geotech, Grand Junction Projects Office, "Geophysical Surveys at INEL/RWMC Cold Pit, Acid Pit, and Pit 9"). It is hoped that aerial surveys using this technology will provide a quicker and safer means of survey, and will be performed at a time when frozen soil should not be a factor.

- Core boring and sampling in the buried waste pits—This is a current method to help with characterization of the buried waste. While yielding valuable data for localized areas, it disturbs the waste, spreads contamination, potentially exposes personnel to radiological and hazardous contaminants, and generates waste (the sample materials) which must then be treated or disposed.
- Excavation of the buried materials—Many of the plans currently underway for remediation demonstration call for excavation of the materials prior to treatment, and information about the waste will then be gained in the process. However, the information will not be timely for making the excavation and the treatment faster and safer, nor for helping to judge whether an in situ treatment might have been preferable.
- Manual survey of ordnance sites with a metal detector—This method presents a potential explosives hazard to personnel. This is the method which has been used in the past, usually in conjunction with the archaeologic survey. It can achieve the objective of clearing unexploded ordnance from a construction site.
- No action, i.e., neither the IBS nor any of the above alternatives would be pursued—This is not a good alternative and, therefore, receives little or no consideration. In this case, no ordnance would be found, therefore no new construction could take place in areas which have not yet been surveyed and cleared. Also, buried waste would not be characterized; thus, planning for remediation would be a haphazard process and performance of the remediation would be inefficient and potentially hazardous.

1.3 Technological Application

If successful, the aerial surveillance technologies tested and demonstrated by this project will have two applications at the INEL as follows:

- BWID and ERP programs at the INEL can verify or modify their records of buried waste at the SDA, thereby allowing further evaluation of their plans for waste recovery, treatment, and remediation. RWMC operations can verify their data base of buried waste at the SDA, and verify the location of pits and trenches for future waste emplacement or excavation.
- The identification and location of ordnance will facilitate construction projects across the INEL by reducing the exposure of personnel to explosives hazards.

2. OBJECTIVES AND PRINCIPLES

2.1 Project Objectives

The objective of the IBS project is to investigate the use of airborne geophysical sensors to identify subsurface soil characteristics, and locate buried waste and ordnance on the INEL. If such equipment systems operate successfully, they would significantly reduce costs and increase both speed and safety for site characterization and retrieval efforts at several key INEL locations.

2.2 Basic Scientific Principles

Aerial surveillance of buried objects requires remote operating technologies that make use of inherent differences between the subject objects and the surrounding geology. Two helicopter-mounted technologies were identified for further investigation from the responders to the Request for Proposals. Subcontracts were awarded to Martin Marietta Missile Systems of Orlando, FL, and to EBASCO Environmental Services, Inc., of Idaho Falls, ID.

To demonstrate and test their systems, the two subcontractors will each fly over and survey four areas on the INEL, (a) the Naval Ordnance Disposal Area (NODA); (b) the Cold Test Pit just outside the SDA; (c) the western portion of the SDA, i.e., beyond a 1,000 foot radius of open pit no. 18 and the Transuranic Storage Area (TSA); and (d) the SL-1 burial ground at ARA-II. The subcontractors will be given sufficient data on the contents of those areas to calibrate their equipment and refine their data analysis algorithms. To determine accuracy of the surveillance techniques, the subcontractors' results on the contents of the areas will then be compared with additional data currently known on the areas.

If the systems tested during the IBS project show promise, further development may be desirable. For example, additional sensors, such as a multi-spectral infrared or radar, may be combined or added to existing instruments in the systems currently being tested. DOE will decide whether any extension of the project is warranted to pursue such development.

2.2.1 Martin Marietta System

Heat sources for buried objects or surrounding geologic structures include both the sun (a diurnal cycle) and the earth's own deep core heat generation. Surface or buried objects' temperatures can differ from the surrounding soil due to differences in heat transfer rates. Martin Marietta has combined electro-optics, image processing, target recognition software, and infrared imaging and thermography to develop a system which can locate land mines by detecting and evaluating their thermal signature. The system incorporates a proprietary advanced imaging technique coupled to a commercially available thermal imager. Capabilities demonstrated for shallow buried objects include the ability to detect small temperature differences, and feature extraction and classification. If these capabilities can be adapted for deeply buried objects (e.g., buried waste), the BWID and ERP programs could benefit, as could other DOE programs across the nation.

Martin Marietta calculates that if the depth of soil above a buried object is not larger than the object, a minimum 0.1°C difference in temperature between the soil above the object and the surrounding soil could exist and be detected by the Martin Marietta equipment. EG&G Idaho calculations show that this would probably not be the case and estimated that the system would only be effective in identifying waste buried to a depth of 1 ft. However, personnel from DOE's Office of Environmental Restoration and Waste Management observed a video tape of the system as demonstrated for the U.S. Army and, believing the system has potential, they directed EG&G Idaho to initiate the IBS Project to investigate the Martin Marietta system. Tests will focus on the sensitivity and accuracy of the equipment in identifying objects at various depths. Since any temperature differences would be sensitive to soil moisture content, and would be unreadable in case of snow cover, demonstration at the INEL must be performed before precluded by weather, i.e., during the fall of 1991.

2.2.2 EBASCO System

The EBASCO system offers potential for success in the complex geologic structure and vegetation cover of the INEL. The system is equipped with

magnetic and electromagnetic (EM) sensors which will be towed 100 ft beneath the helicopter while data is gathered on the specified INEL locations. Flight interval distance and altitude will affect the resolution of measurements, which are taken in both horizontal and vertical gradients.

A cesium magnetometer will passively measure the earth's naturally occurring magnetic field. The magnetic field may be locally altered or distorted by concentrations of ferrous material. Mapping the earth's magnetic field intensity highlights these local distortions or anomalies, indicating the location of buried ferrous objects. The depth at which an object can be detected is a function of the amount of ferrous material contained. Ideally, a single ferrous drum may be detected as deep as 10 ft, while a group of 100 ferrous drums may be detected as deep as 50 ft. Resolution of the horizontal and vertical gradient data are anticipated to be as follows: size of object within 0.1 lbs of ferrous material, depth within 1 ft, and lateral location within 2 ft. Magnetic anomalies caused by magnetic bedrock (such as basalt) and buried man-made ferrous objects are distinguished by the shape and magnitude of the anomaly. The vertical magnetic gradient is measured to enhance shallow targets and improve resolution of magnetic anomalies.

EM surveys detect contrasts in ground conductivity, usually caused by natural phenomena such as changes in lithology, porosity, and moisture content. Conductivity contrasts may also be caused by man-made phenomena, such as disturbed ground, buried waste, and contaminants in the soil and groundwater. EM instruments are based on the inductive coupling (i.e., no ground contact is necessary) of relatively high frequency electromagnetic waves into the ground's subsurface. The transmitter coil creates a time-varying magnetic field and associated eddy currents in the subsurface by emitting an alternating current. These eddy currents generate a secondary magnetic field which is measured and converted into units of conductivity, i.e., millisiemens per meter. Two different components of the EM field are measured, (a) the quadrature-phase which show conductivity changes related to excavation, subsurface disposal, soil contamination, and groundwater contamination and (b) the in-phase component, which is sensitive to buried conductors (such as metallic debris) and compares the primary and secondary magnetic fields.

3. WORK BREAKDOWN STRUCTURE

The Work Breakdown Structure (WBS) for the IBS project is shown in Figure 1.

11/12/91

Figure 1. Identification of Buried Structures (IBS) Work Breakdown Structure (WBS).

4. WORK SCOPE

Four main tasks have been identified for the IBS project as follows:

TASK 1: PLANS AND PROCUREMENT

The Plans and Procurement task included project management activities such as issuance of a notice to interested parties in the *Commerce Business Daily* and the Request for Proposals; writing the Technical Task Plan (TTP), the Cost Account Plan (CAP--also called a Work Package), the Environmental Checklist, and the Long-Range Plan; negotiating and awarding the subcontracts to Martin Marietta and EBASCO; obtaining the overflight and camera permits; and preparation of various presentations. All of these activities began in FY-91.

TASK 2: SYSTEM PREPARATION AND TEST PLANS

Many preparations were necessary before testing began. For example, during the week of September 23-27, 1991, the subcontractors visited the INEL to learn more about the test areas and to explain their technologies to IBS project and DOE personnel. Additional information on INEL Site, security, safety, and environmental regulations was later provided to the subcontractors. Their Test Descriptions and Test Plans were written, reviewed, and approved, and their hardware was adjusted and relocated to Idaho Falls. Quality assurance was and will be an integral consideration during all reviews.

TASK 3: SITE SURVEY AND CHARACTERIZATION

The actual data gathering is expected to take three to four weeks, weather permitting. Both subcontractors stationed their helicopters in cities near the INEL (Martin Marietta at Idaho Falls and EBASCO at Arco), and flew out to the test sites each day. Because Martin Marietta's technology had not been applied to buried waste sites, no specific procedures existed to ensure collection of the best data possible. Therefore, after the first week of flights, procedures were developed in

an attempt to optimize data quality. The Martin Marietta system incorporated real time data viewing and analysis, while EBASCO had a one-day turn around time, i.e., the data was reviewed and analyzed on each day following data gathering.

TASK 4: DATA REDUCTION AND ASSESSMENT

Data analysis began within two weeks after data gathering started. This allowed the data gathering process to be modified as necessary to further optimize for data quality. Each subcontractor will now analyze their data, determine whether their technology operated successfully at identifying the ordnance and buried waste, identify shortcomings and potential areas of improvement, and submit a final report for EG&G Idaho's review and approval. EG&G Idaho will then prepare a final report to DOE summarizing the testing program, commenting on the performance of each technology, and recommending any further action. This report will be submitted to DOE with the subcontractors' reports appended.

5. SCHEDULE

The IBS Project Schedule is shown in Appendix A. The primary driver for this short schedule is to accomplish the data gathering before snow, which would preclude Martin Marietta's data collection. Because the completion date is relatively soon, the schedule can be shown in considerable detail at this point, and there is no need for WBS Element Schedules separate from the Project Summary Schedule.

Major milestones (#) shown on the schedule are:

- award subcontracts (9/17/91)
- completion of the subcontractors' surveillance flights (11/22/91)

The key milestone (*) shown on the schedule is:

- submittal of EG&G Idaho's final report to DOE (2/21/92)

6. BUDGET

6.1 Project Life Cycle Costs

The total cost for the IBS Project is expected to be \$1,105K.

6.2 Annual WBS Budget Projections

Work on the IBS project started in FY-91 and will be completed by the end of February in FY-92. The cost breakdown by major task is:

Task 1:	Plans and Procurement	\$882K
	Subcontract to Martin Marietta	\$428K
	Subcontract to EBASCO	365K
	Total Subcontracts	793K
	Materials & Handling Fee	40K
	EBASCO on-site processing	44K
	Other	5K
Task 2:	System Preparation and Test Plans	29K
Task 3:	Site Survey and Characterization	106K
Task 4:	<u>Data Reduction and Assessment</u>	<u>88K</u>
	TOTAL	\$1105K

6.3 Annual Funding Category Budget Projections

The IBS project is financed entirely from FY-91 operating monies. Work performed during FY-92 will be financed by FY-91 carryover funds.

7. RESOURCE ALLOCATION

7.1 Annual Resource Projections

Appendix B is a summary table of identified resources for the life cycle of the project. It is taken from the Cost Account Plan (i.e., the Work Package).

7.2 Estimated Annual Subcontract Costs

Subcontracts awarded to Martin Marietta and to EBASCO will be completed in December 1991, with total payment due in January 1992, to be paid by FY-91 carryover funds.

8. TECHNOLOGY DEPLOYMENT PLAN

8.1 Cooperative/Collaborative Agreements

There are no cooperative or collaborative agreements in place at this time. Potential exists, however, to establish cooperative efforts with Lawrence Livermore National Laboratory, Los Alamos National Laboratory, and EG&G Nevada Tests and Measurements Group, where similar technology demonstrations are currently underway, and also Pacific Northwest Laboratory (PNL) and Oak Ridge National Laboratory (ORNL), where there are buried waste situations similar to those at the INEL. In addition, the Department of Defense (DOD) has been pursuing such technology and is another candidate for collaboration.

8.2 Applicable Regulations and Requirements

EG&G Idaho is responsible for all matters of compliance and permitting. Environmental Protection Agency (EPA) National Environmental Protection Act (NEPA) documentation, overflight permits, and camera permits are required for this project. Also, a Cost Account Plan, Technical Task Plan, and Long Range Plan are required. The project falls under the Waste Technology Development Department Quality Program Plan QPP-337. A separate Security Plan or Health and Safety Plan is not needed for this project since there are such plans in effect for each of the test areas, and this project shall abide by each of the appropriate plans while operating in the respective areas.

In compliance with NEPA requirements, an Environmental Checklist (EC) was prepared for this task. The EC was reviewed and approved by the DOE Technology Development and Integration Division. It was determined that the task falls under a Categorical Exclusion, and that no further NEPA documentation is required.

The proposed test flights were approved in advance by DOE-ID Safeguards and Security. The IBS project manager completed and submitted DOE-ID Form 5632.A1, "Request for INEL Overflight," to ID Security Operations Branch in advance of the proposed test flights. Camera permits were approved prior to

the start of flights. Martin Marietta and EBASCO personnel were informed and/or trained on all applicable INEL safety, security, and environmental procedures impacting their work.

The following regulations are applicable to INEL access control and will be adhered to:

DOE-ID Order 1200.A1, INEL Visitor Policies and Procedures

DOE Order 1240.2A, Unclassified Visits and Assignments by Foreign Nationals, DOE-ID Order 1240.2, Non-U.S. Citizen INEL Access Controls

DOE Order 5480.13, Aviation Safety

DOE Order 5632.3B, Operations Security

DOE and DOE-ID Order 5632.5, Physical Protection of Classified Matter

DOE-ID Order 5632.9, Issuance, Control, and Use of Badges, Passes, and Credentials

DOE and DOE-ID Order 5632.2A, Physical Protection of Special Nuclear Material and Vital Equipment

DOE and DOE-ID Order 5632.6, Physical Protection of DOE Property and Unclassified Facilities

8.3 Technology Deployment Strategy

To be deployable for ordnance identification, the IBS aerial surveillance technology must show the ordnance location and approximate size so that a ground team of personnel can later easily locate and detonate any ordnance. To be deployable for identification of buried structures, the technology must at least give a clear indication of a buried waste pit or trench boundary. Any clearer definition beyond this is desirable, but this is considered the threshold criterion to make the technologies worth deploying.

Commencing with the tests, a status report will be sent out every Friday until the conclusion of the project. The weekly status reports will include accomplishments, significant problems/issues and actions taken, upcoming meetings/visits, upcoming travel/visits, and internal data. Report copies will be sent to EG&G Idaho personnel working on closing the various ordnance areas at the INEL and NPR program personnel working on NPR site characterization.

At the conclusion of the tests, the subcontractors will have the responsibility for the preparation and issuance of final test reports. EG&G Idaho will then compare the results of the tests from the two systems and issue a formal report on the final technology evaluation. This report will be distributed to all parties as outlined in Section 8.4. Any further action to use or develop the technologies will be determined by DOE.

8.4 Technology Transfer

The INEL has been designated as the lead laboratory for integrating demonstrations for buried waste. Therefore, applications for the IBS technologies extend beyond the INEL and are potentially applicable to buried waste sites at DOE (and other federal agencies) locations across the nation.

Information on the technologies will be transferred to personnel working in the following organizations, projects, and tasks for their use in determining how the IBS technologies could best be used to meet their needs:

- Consent Order and Compliance Agreement (COCA) Management and Implementation at INEL Unit—location and identification of buried waste at various waste sites
- COCA Management and Implementation at INEL Waste Area Group 10 (Miscellaneous Areas) - Ordnance Interim Action Project—location and identification of ordnance at various INEL sites
- Buried Waste Integrated Demonstration Program—location and identification of buried waste

- EG&G Idaho Environmental Restoration Program--location and identification of buried waste
- EG&G Idaho Waste Management Operations Department--location and identification of buried waste
- EG&G Nevada Tests and Measurements Group--to compare to and augment their current technology investigations
- INEL Naval Ordnance Disposal Area--RCRA Closing Plan - location and identification of ordnance at the NODA site
- INEL New Production Reactor--Location Characterization - locations and identification of ordnance
- Lawrence Livermore National Laboratory--Aerial Surveillance Technology - to compare to and augment their current technology investigations
- Los Alamos National Laboratory--Aerial Surveillance Technology - to compare to and augment their current technology investigations.

If tests are successful, findings will be submitted to conferences, waste management magazines, environment journals, etc. Since these technologies are already known and will be demonstrated by commercial industries, no effort is needed or will be made to transfer the technology to the private sector.

9. POTENTIAL TECHNOLOGY DEVELOPMENT BENEFITS

9.1 Operational

The aerial surveillance technologies investigated by this project have been proven successful in identifying shallow buried metallic objects, i.e., land mines. This capability to identify and locate ordnance could facilitate construction projects across the INEL. Some areas of the INEL are scattered with old ordnance remaining from military tests conducted during the 1940s and 1950s, and some of that ordnance is still live. Construction on any new INEL site has always been preceded by a thorough search and removal of any live ordnance, in conjunction with the required archaeologic surveys. The searches have been conducted by personnel surveying the area in question at close range, with the potential hazard of inadvertently exploding any live ordnance and causing injury to workers. A nonintrusive method of identifying locations and sizes of ordnance would significantly increase the safety for site survey efforts at future INEL construction sites.

In addition, if the technologies operate successfully for buried waste identification, they could revolutionize the process by speeding it considerably, providing more accurate characterization of an entire waste field than is offered by core drilling or excavation at discrete points, and avoiding the resulting contamination spread or waste generation. Records of buried waste content and location at the RWMC are often not accurate or explicit enough to adequately judge the most effective treatment technology, or to know what will be found upon excavation. If the IBS aerial technologies are successful, BWID and ERP programs at the INEL could verify or modify their records of buried waste at the SDA, thereby allowing earlier and more effective waste recovery, treatment, and remediation. RWMC Operations could verify their data base of buried waste at the SDA, and verify the location of pits and trenches for future waste emplacement or excavation. Obviously, nonintrusive buried waste characterization, such as the IBS aerial technologies, would be highly advantageous.

9.2 Regulatory Compliance

Permission to excavate or core drill at the SDA is difficult to obtain due to the tangle of paperwork, compliance, and approvals required for environmental and safety regulatory compliance. By comparison, nonintrusive surveillance methods would simplify compliance with environmental and safety regulations while characterizing waste fields and potential construction sites. Because no soil would be disturbed by these processes, no waste would be generated or treated and no contamination would result. Therefore, the paperwork to comply with environmental or safety regulations would be sizably reduced. For example, the NEPA documentation to perform the IBS demonstration tests consisted simply of an environmental checklist, with a finding that the work falls under a Categorical Exclusion with no further NEPA documentation required. However, requirements for security compliance were increased, e.g., overflight permits and camera permits were required along with training of subcontract personnel.

Depending on the deploying location, use of these technologies may require more extensive efforts for compliance to regulations than was necessary at the INEL. For example, safety regulations may require possible revisions to Safety Analysis Reports (SARs), in addition to the usual Safe Work Permits and reviews by a Safety Engineer. Some DOE sites have restricted airspace and, at the least, overflight permits are necessary to ensure safety while flying over hazardous areas and potentially to limit proximity to structures or the ground. NEPA documentation may require addressing air emissions from helicopter operations. In total, however, it is expected that use of the aerial technologies would usually require less effort to comply with regulations than would conventional characterization methods.

9.3 Institutional

DOE sites across the nation (e.g., PNL and ORNL) have buried waste situations similar to the INEL, although the extent of the problems varies. A few sites even have inaccurate records of where their waste was buried, i.e., wastes are sometimes found unexpectedly in areas where no records indicate

that any wastes were buried. The IBS aerial technologies could be applicable to many of these sites, as well as sites of other federal agencies.

Also note that use of these private sector technologies would demonstrate DOE's commitment to supporting commercial activities in waste remediation programs.

9.4 Cost Savings

The possible cost savings if the IBS aerial surveillance systems are successful at identifying buried structures could be substantial to DOE by reducing safety risks and the time required for characterization of waste and ordnance sites at the INEL, and potentially at DOE and federal agencies across the nation. The mobilization and demobilization costs for a subcontractor to perform an aerial surveillance, based on the current IBS subcontracts, are about \$300K. Therefore, a large enough area must be surveyed to make it cost effective to address these costs; the area will be estimated and reported in the IBS final report. Any resulting cost savings is highly dependent on the amount of land to be surveyed, and could be from about one to five times the cost of using conventional methods (based on estimates for various potential work to be performed at the INEL).

10. CHANGE CONTROL

Changes to this document will be controlled in a manner consistent with the Waste Technology Development Department document control program. Changes to the Plan will require issuance of a controlled revision, and must be reviewed and approved by the same people (or their representatives) who approved the original. The original and all subsequent revisions will be retained by the IBS Cost Account Manager in the Project File.

APPENDIX A
LOGIC DIAGRAM

ISB Logic Diagram And Project Schedule

T91 0620/11-5

Plans and Procurement
 CBD Notice (Jan. 25, 1991)
 Request for Proposals
 Technical Task Plan
 Cost Account Plan
 Environmental Checklist
 Long Range Plan
 Overflight permits
 Camera permits
 Award MM and EBASCO contracts

System Prep and Test Plans
 Summary of INEL info on sites
 MM site visit (Sept 23 & 24)
 MM draft Test Plan/Definition
 Review & Finalize Test Plan/Definition
 MM prep helicopter & relocate
 EG&G arrange access for MM
 EG&G grid markings for MM
 EBASCO site visit (Sept 26 & 27)
 EBASCO draft Test Plan/Definition
 Review & Finalize Test Plan/Definition
 EBASCO prep helicopter & relocate
 EG&G arrange access for EBASCO
 EG&G grid markings for EBASCO

Site Survey and Characterization
 MM Flights
 EBASCO Flights
 MM remove & relocate helicopter
 EBASCO remove & relocate helicopter
 Data Reduction and Assessment
 MM reduce and assess data
 EBASCO reduce and assess data
 EG&G evaluate MM & EBASCO data
 and write final report

* Coordinate efforts for MM and EBASCO
 when/if possible

APPENDIX B
COST ESTIMATE BASIS

WORK PACKAGE DOCUMENTATION

Resource Summary

Date Prepared 10/25/91 Rev. No. 3 Fiscal Year 1991/1992 Work Package No. 3Y5110100

Performing Organization	Labor		Non-labor		Estimate Basis	Performing Organization Acknowledgment
	Hours	ST or CT	\$	Description		
E300	190				Planning/Procurement: 1 FTE for planning and initiating procurement.	
E300	450				System Prep/Test Plan: 4 FTEs for four weeks to coordinate subcontractor personnel, place grid markings needed to facilitate the helicopter surveys, provide data regarding knowledge of INEL buried wastes at specific locations, and review and approve the Test Plans. Also includes funds for RWMC personnel to aid in these tasks.	
E300	192				MM Site Survey/Characterization: One 3/4 TE for personnel to assist in the testing phase.	
8220	50				50 hrs to assist in meeting the data quality objectives.	
E320	132				Ebasco Site Survey/Characterization: One HTE for personnel to assist in the testing phase.	
8220	10				10 hrs to assist in meeting the data quality objectives.	
7110	60				RWMC Operations time to aid in placing the grid markers in the SDA and Cold Pit.	

Performing Organization	Labor		Non-labor		Estimate Basis	Performing Organization Acknowledgment
	Hours	ST or CT	\$	Description		
E300	172		6K	Travel	MM Data Reduction/Assessment/Report: One PTE (.4) to support a comparison of known data on INEL buried items to data obtained by the aerial surveillance system. Travel for two one-person trips to Martin-Marietta to discuss test results. One week to audit the results from the surveys. Travel for a one-person trip to Martin-Marietta to discuss test results.	
8220	40					
M8/M90			428K/ 21K	Subcontract	Martin Marietta subcontract for preparatory activities, performing tests, and data reduction and assessment.	
M8/M90			365K/ 18K	Subcontract	Ebasco Data Reduction/Assessment: EBASCO subcontract for preparatory activities, performing tests, and data reduction and assessment.	
E300	272		6K	Travel	One PTE (.7) to support a comparison of known data on INEL buried items to data obtained by the aerial surveillance system. Travel for three one-person trips to Ebasco to discuss test results.	
8220	30				30 hours to audit the results from the surveys. Travel for a one-person trip to Ebasco to discuss test results.	
F520	24				3 days to support audit the data analysis.	

Performing Organization	Labor		Non-labor		Estimate Basis	Performing Organization Acknowledgment
	Hours	ST or CT	\$	Description		
M8/M90					Final Report: EBASCO subcontract to provide on-site processing capability 1 FTE to support data analysis and preparation of the final report. 3 days to support statistical comparison of the technologies and 2 1/2 days to support data quality analysis. 1 1/2 weeks to support geophysical interpretation of the results. 1 week to support technical editing of the report. 3 days to support graphics for the report. 14 hrs to support printing the report.	
E300	592		40K/ 4K			
E200	44					
F520	60					
4620	40					
4650	24					
4660	14					

END

DATE
FILMED

6/10/92