DOE/BP--1437

DE91 000352

**OPERATIONS, MAINTENANCE, AND REPLACEMENT
BONNEVILLE POWER ADMINISTRATION**

**10-YEAR PLAN
1990 - 1999**

AUGUST 1990

MASTER

EB

**OPERATIONS, MAINTENANCE, AND REPLACEMENT
BONNEVILLE POWER ADMINISTRATION**

**10-YEAR PLAN
1990 - 1999**

Table of Contents

	<u>Page</u>
TABLE OF CONTENTS	i
FOREWORD	iii
1. WHY A 10-YEAR PLAN	1
2. THE OM&R PLAN	6
A. INTRODUCTION	6
B. MAJOR FINDINGS	6
C. ASSUMPTIONS	8
D. ISSUES NOT COVERED	8
E. RELIABILITY	9
F. SYSTEM OPERATIONS STRATEGY	9
G. MAINTENANCE/REPLACEMENT STRATEGIES	11
1. Maintenance Backlog Plan	11
2. Maintenance Strategy	17
3. Replacement Strategy	18
H. ENVIRONMENTAL STRATEGY	22
1. Background	22
2. The Plan	23
I. REPLACEMENT AND TRAINING OF SKILLED EMPLOYEES	24
J. PRODUCTIVITY	25
K. RESOURCE REQUIREMENTS	28
APPENDIX A: EXCERPTS FROM THE TECHNICAL REPORT	29
APPENDIX B: RELIABILITY CENTERED MAINTENANCE "THOUGHTS AND DISCUSSIONS"	36
APPENDIX C: ACRONYMS	38

SOMEONE YOU KNOW

Arms out, I turn. Wires in each hand,
I cross rivers, climb hills. When wind blows,
I tremble but hold. You glimpse me walking
in snowstorm, over the mountains. I'm from
Bonneville or upriver, some falls or other.
Please do not forget me. If I
fall down, cities will flash and go dark.

William Stafford

FOREWORD

In 1988 BPA began work on this Operations, Maintenance, and Replacement 10-Year Plan to develop a levelized program that would assure high system reliability. The development of this plan from 1988 through today involved the concerted work of many within BPA and its customers and interested public.

During the Programs in Perspective (PIP) meetings in the late summer and fall of 1988, many of the concerns to be addressed in an Operations, Maintenance, and Replacement Plan were identified.

Following these PIP meetings BPA established internal work groups. During the winter and spring of 1989, these work groups developed technical background and issue papers on topics that ranged from substation maintenance to environmental protection. In addition, a customer forum group was established and met on several occasions to review work on the plan, to offer ideas and points of view, and to assure that BPA understood customer concerns.

Based on recommendations from the work group reports and customer input, BPA's O&M Management Team developed the draft Operations, Maintenance, and Replacement 10-Year Plan that was released for public comment during the spring of 1990. During the public review period, BPA received a number of written comments from customers and the interested public. In addition, special meetings were held with interested customers.

This final Operations, Maintenance, and Replacement 10-Year Plan reflects BPA's response to customers and interested public on each topic discussed in the 10-Year Plan. The plan is a distillation of BPA's strategies to achieve a levelized program over 10 years. Should the reader wish more detail on a particular topic, 10 technical reports are available upon request. These reports are: Transmission Line Maintenance, Substation Maintenance, System Protection Maintenance, Power System Control, Environment, Non-Electric Plant, Substation Operations, PSC & Dispatching, Outage Data, and Utility Comparison.

1. WHY A 10-YEAR PLAN

BPA Mission Statement

BPA will work in a regional partnership to define and achieve the electric power, conservation, and fish and wildlife objectives of the Pacific Northwest. We will provide our customers a low-cost, reliable, and environmentally sound power supply and transmission system. We will do so in an open and businesslike way, responsive to citizens' concerns and to our obligations as a Federal agency. We will provide creative leadership and fulfill our responsibilities with professional excellence.

The BPA transmission system brings power to more than 150 customer utilities and direct service industries in a multi-state region. It has over 14,500 circuit miles of high-voltage and extra-high-voltage transmission lines and more than 400 substations. It has all kinds of facilities and equipment, ranging from a systemwide network of communications equipment to large 250-ton transformers to sophisticated electronic equipment. The system represents an investment of more than \$3.5 billion to the ratepayers of the Northwest. Replacement value of this system is estimated to exceed \$10 billion.

A. BACKGROUND

In 1974 BPA faced an imbalance between preventive maintenance workload and resources available to accomplish preventive maintenance. At that time, performance level guides (PLG's) that determine preventive maintenance were lengthened in an attempt to match workload to available resources. At the same time, BPA began to defer its capital replacement program. By the early 1980's, BPA was even deferring painting of electrical equipment.

Faced with a static workforce, increasing workload due to system growth, changing environmental regulations, and aging equipment, BPA failed to complete even the reduced level of preventive maintenance. BPA began to accumulate a backlog of undone preventive maintenance tasks.

By 1981, it was perceived that the region had excess transmission and generation capacity. Because excess transmission capacity provided a greater operating margin, BPA was able to save costs by taking advantage of the margin through operating and maintenance practices. BPA routinely:

1. Completed approximately 70 percent of planned preventive maintenance.
2. Deferred analysis of equipment failures, less significant outages, and outage rates.
3. Suspended annual system operations studies.
4. Deferred the painting of electrical equipment.

5. Deferred the replacement of power system equipment.
6. Reduced inventories of spare parts and spare equipment.

The preventive maintenance backlog continued to grow and equipment continued to age.

B. THE PROBLEM

By 1988-1989 it became increasingly obvious that the excess transmission capacity enjoyed by the region and BPA had largely disappeared. BPA, along with many other utilities, began to suffer the effects of transmission bottlenecks as well as the potential effects of voltage collapse. The reduction in transmission capacity margin was exacerbated by the effects of deferred maintenance and replacement of equipment.

In 1987, the U.S. Department of Energy Inspector General's (IG) Office audited BPA's substation maintenance program. They found a backlog of approximately 11,000 maintenance tasks--about 250 staff years. Backlogged maintenance tasks included diagnostic testing of equipment, maintenance of circuit breakers, and transformer overhauls. Approximately 40 percent of these tasks were at least 6 years overdue.

The IG report concluded that:

"Bonneville officials faced numerous economic, technical, environmental, community, and statutory considerations requiring compensating tradeoffs. Management rightly attempted to hold costs at the minimum necessary to accomplish agency objectives. However, the substation maintenance backlog threatens efforts to continue providing a safe, reliable, and cost effective system and should be reduced to a manageable level."

Events in 1988 and 1989 confirmed the IG's conclusions. BPA observed a trend toward increased equipment failures. More troubling, many of the failures involved the explosive failure of extra high voltage (EHV) equipment first placed into operation in the 1960's and the early 1970's. These failures posed serious potential safety problems. Further, the explosions sometimes damaged adjacent equipment resulting in additional cost and reduced reliability. The performance of the power system during the extreme cold weather conditions of February 1989 further confirmed the potential for reduced reliability.

In addition, BPA, like other utilities, began to be faced with new environmental awareness, issues, and regulations. Numerous Federal and State statutes such as the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), have been enacted to regulate the use and disposal of hazardous substances, wastes, and contaminants. As an outgrowth of these developments, BPA efforts to assure the agency not only complied with these laws, but took proactive steps to mitigate future liabilities, have significantly increased the resources necessary to meet these responsibilities.

C. BPA'S RESPONSE

BPA's response to the problem started in 1988. BPA began systematic corrective action by:

1. Developing emergency plans for 230-kV and 500-kV transformers.
2. Developing an emergency response plan for microwave failures.
3. Undertaking the development of an emergency response plan for transmission line failures.
4. Developing, through the Northwest Power Pool, a plan to restore the power system after a regionwide outage.
5. Procuring emergency transmission line structures and microwave structures.
6. Undertaking the comprehensive review of emergency spare parts inventories.
7. Procured four 500-kV emergency spare power circuit breakers.

In 1988, BPA also completed a top to bottom review of its performance level guides. These guides were established at a level based on the experience of other utilities, manufacturer's recommendations, and BPA experience. This review resulted in a net reduction in preventive maintenance workload. However, the review also assumed that once new maintenance intervals were established, BPA would accomplish all of the work scheduled.

BPA then established a ramp of 48 FTE (full time equivalent) over a 3-year period to provide the resources necessary to accomplish the scheduled workload. That ramp will be complete in 1991. Bonneville did not add permanent staff to reduce the backlog.

However, BPA committed temporary resources (FTE and dollars) to work off the backlog. This has been done on an "as available basis" in 1988 and 1989. By the end of 1989, the backlog had been reduced by approximately 20 percent. In addition, painting of electrical equipment was being accomplished with temporary FTE at a rate to support a 10 to 15 year painting program.

Lastly, in February 1988, BPA adopted a strategic objective as follows:

"We will maintain competitive and predictable rates by . . . enhancing the contributions of BPA's transmission system to revenues, and implementing a multi-year, levelized operations, maintenance, and replacement plan keyed to high system reliability."

The Operations, Maintenance and Replacement 10-Year Plan is BPA's implementation of the strategic objective to "implement a multi-year, levelized operations, maintenance, and replacement plan keyed to high system reliability."

D. THE 10-YEAR PLAN

The 10-Year Plan expands the planning horizon for operating, maintaining, and replacing the transmission system from 3 years to 10 years. The resulting plan provides for 10 years of systematic work to bring BPA's system operations, maintenance, and replacement efforts back to proper levels. The implementation of this plan will protect the existing system investment, replace worn-out and failing equipment, increase maintenance productivity, and maintain a safe and reliable supply of power to the people of the Pacific Northwest.

PROVIDING QUALITY CUSTOMER SERVICE THROUGH

SAFETY – PUBLIC AND EMPLOYEE

RELIABILITY

ECONOMY AND COST EFFECTIVENESS

ENVIRONMENTAL SENSITIVITY

UNDERSTANDING AND RESPONSIVENESS TO CUSTOMER NEEDS

COURTESY

2. THE OM&R PLAN

A. INTRODUCTION

In 1988, BPA undertook the development of a long-range, 10-year plan for the agency's Operations, Maintenance, and Replacement Programs. The goals of this plan include:

1. Assuring BPA ratepayers "best value" by providing reliable customer service, avoiding systemwide interruptions, and optimizing program costs.
2. Recognizing BPA's responsibility to provide a safe and environmentally acceptable power system.
3. Developing strategies that result in levelized resource requirements and meet both short-term objectives and long-term goals.
4. Achieving understanding and acceptance of the 10-Year Plan within BPA and with its customers.

The yearlong planning effort is now complete, and BPA believes that the 10-Year Plan itself will serve the agency and our customers as a blueprint into the next century.

B. MAJOR FINDINGS

1. The region's power system enjoyed excess capacity through much of the 1980's. The excess capacity in the transmission system is coming to an end. BPA is experiencing transmission bottlenecks, the effects of an aging system, increased time to restore the system, and increased complexity introduced through remedial action schemes necessary to correct transmission limitations. As a result, maintaining system reliability will be a high priority during the decade. During the draft plan's public review, BPA received several comments supporting our high priority choice to maintain system reliability. Commenters also expressed concern that adequate funds be provided to operate in a prudent utility manner and suggested that additional transmission be built to solve stability-related problems.
2. In order to prudently operate, maintain, and replace the system through 1999, without a significant increase in personnel, BPA must achieve productivity increases of 1.5 to 2.0 percent per year. Increased workload is expected in four areas:
 - a. The need to maintain an aging system through the middle of the decade,
 - b. Increased complexity of control, communications, and protection systems,
 - c. Increased BPA response to environmental regulation, and
 - d. Increased load growth.
3. Over the decade, BPA will face a scarcity of engineering, procurement and construction resources. These resources support Transmission System Development, Fish and Wildlife, and Conservation Programs in addition to the operations, maintenance, and replacement of the system.

4. BPA will experience significant loss of skilled technical and craft employees through the decade. Renewal of that workforce through training, recruitment, and strengthening of the apprentice programs is a high priority. Many commenters supported BPA's high priority choice for strengthening training and apprentice programs. Some suggested that BPA get started as soon as possible to avoid significant problems in the years ahead. Also suggested was that BPA explore a regional approach in partnership with our customers.
5. BPA must sustain the present level of employee proficiency to accomplish this plan.
- 6.1/ The preferred path between where BPA is now and should be at the end of the decade is to:
 - a. Establish a levelized preventive maintenance program that will accomplish approximately 100 percent of the required maintenance each year.
 - b. Accelerate the replacement program to a peak of approximately \$59 million in 1995, reducing to a levelized program of approximately \$50 million by 1999.
 - c. Further reduce backlogged maintenance through use of available temporary resources.

This path will reduce the backlogged maintenance to acceptable levels by the end of the decade. Accelerating the replacement program through the mid-1990's will:

- a. More effectively address public and employee safety concerns,
- b. Take advantage of inherent productivity gains of replacing aging equipment with state-of-the-art equipment, and
- c. Maintain system reliability.

BPA received several comments on the preferred path and strategies for its maintenance and replacement programs. In many cases, commenters questioned whether replacement rates and backlog reduction rates were enough and offered specific changes. As the plan is implemented over the next year, BPA will closely monitor the adequacy of these rates and levels.

7. BPA will be faced with increasing environmental workload during the next decade. BPA plans to:
 - a. Replace all PCB (polychlorinated biphenyls) capacitors on the system over a 16-year period,
 - b. Retrofit approximately five existing substations per year with oil containment,
 - c. Replace approximately 76 underground storage tanks by 1993,
 - d. Provide ongoing employee training on work processes, and
 - e. Provide for the cleanup of historic spills.
8. BPA will face an undetermined workload to investigate, assess, and take remedial actions for contamination resulting from past work practices.

1/ All references to costs in this report are in terms of 1990 dollars.

C. ASSUMPTIONS

The most important assumptions which underlie this plan are:

1. In the absence of information to the contrary, the future will be much like the present. The plan speaks to change, trends, and anticipated deviations from the known base.
2. Technology will develop to support reliability centered maintenance (RCM). Adoption of reliability centered maintenance may result in significant productivity improvements.
3. No other major technological, political, or economic developments will substantially affect the way we do our business.
4. Pressure will continue to reduce cost and staff. Pressures to reduce staff will frequently conflict with cost reduction objectives.
5. The requirement to respond to emergency system outages such as storm damage, vandalism, or premature failures of equipment will continue at historic levels.
6. The regulatory environment for toxic waste management, right-of-way management, and environmental restoration and pollution control and abatement will be relatively stable or become more stringent over the next 10 years. In either event, workload is expected to increase.

D. ISSUES NOT COVERED

Significant issues that are not included in this plan are:

1. Major replacement/refurbishment of the original portion of the Celilo Converter Station. A comprehensive review and analysis of the situation at Celilo is underway. The results and recommendations will be taken into account in next year's plan.
2. Replacement, refurbishment, or acquisition of the Eastern Control Center (ECC).
3. Resources required for remedial action of CERCLA sites, including the Ross Complex in Vancouver. Specific remedial actions that may be required are not yet known with enough certainty to include in the plan.
4. Major refurbishment or replacement of substations other than Longview. During the plan's draft review, BPA received customer comment supporting the inclusion of Longview and other badly deteriorating substations into its electrical replacement program plans. Since preliminary plans for refurbishing Longview were already underway, BPA decided to revise its draft plans to include Longview. Section G (replacement strategy) and Section K (resource requirements) reflect the inclusion of Longview in the plan.

E. RELIABILITY

The region has enjoyed excess transmission and generation capacity through much of the 1980's. Due to load growth, the age of equipment, and other factors, the transmission system's excess capacity is rapidly coming to an end.

For example, during the cold weather of February 1989 and the winter of 1990, BPA and the region were constrained by transmission bottlenecks that limited transmission capacity in critical situations. Most obvious of these were transmission to and in the Puget Sound area and east to west transmission from eastern Montana through Idaho. Similar problems have been experienced on the subtransmission system.

As the excess transmission capacity has been reduced, some of BPA's aging equipment is being stressed harder. BPA has experienced increased equipment failures and increased system restoration time. As transmission capacity margin approaches zero, equipment failures have greater impact on system reliability.

Failure of 345-kV and 500-kV substation equipment has been especially troublesome. Much of this equipment was placed in service in the 1960's and the early 1970's. Too often, these failures have been explosive and have presented potential safety problems. These failures frequently damage surrounding equipment. The resulting loss of breaker positions or transformers can temporarily reduce reliability to unacceptable levels.

Finally, BPA is reviewing recent catastrophic outages resulting from the earthquake in San Francisco and Hurricane Hugo. There is much to be learned from the successes and problems experienced by the utilities involved in these disasters. As a minimum, BPA will review and rewrite its "Emergency Plan" to reflect today's reality.

In addition, BPA's customers have made the point that quality of service is important. They have stressed that even momentary outages may be important given the growing numbers of high-tech industries, businesses that depend on computers, and the proliferation of consumer electronics. BPA must better understand its customers' standards of service and their perceptions of BPA's quality of service.

Continuation of the status quo will ultimately compromise system reliability. Reliability must be a driving force behind any long-range plan to operate, maintain, and replace the system. BPA believes that this plan will protect the region's investment in the Federal transmission system and will insure appropriate system reliability for the future.

As stated earlier, several of BPA's customers and interconnected utilities reiterated their concerns for system reliability and supported the actions proposed in the draft 10-Year Plan. All commenters encouraged BPA to continue maintaining or improving its service record.

F. SYSTEM OPERATIONS STRATEGY

BPA is facing several circumstances which will challenge the ability to provide adequate operational reliability over the next 10 years. Principle concerns are in the following areas:

- The reduction of transmission system capacity margin limits operational flexibility and increases the impact of failed equipment on system reliability.
- Solutions to capacity problems will require more and increasingly complex control and compensation schemes. Such measures increase both operating and dispatching difficulty.
- Aging, obsolete, and less dependable equipment will reduce operational flexibility and margins of safety and reliability.
- About 75 percent of dispatching and substation operations personnel will retire or move to higher level operating positions.

The Federal power system, operated by BPA, is one of the most automated in the world. This is both a strength and a weakness. By being highly automated, BPA achieves significant productivity savings. However, fewer field operations personnel are available to respond to system emergencies.

Extensive application of electronic communication and control technology has made it possible to safely and reliably operate the power system much closer to its limits. This has substantial economic benefit since BPA can deliver more power with a given physical plant. This increased capability can be achieved with control and compensation schemes requiring less capital than would additional transmission and generation capacity. However, as this strategy continues, system reliability depends more and more on the reliability of BPA's automation, communications, and control systems. At the same time, system operating flexibility in such matters as equipment isolation, line and bus sectionalizing, and immediate spare availability becomes critical. Reliable and redundant equipment become even more important.

System operations has become significantly more productive in terms of the number of employees needed for operations and dispatch. In 1973, BPA had 25 substations manned 24 hours a day and 52 manned at least 8 hours a day, 7 days a week. BPA began to install centralized supervisory control in 1975. In 1990, BPA has three substations manned 24 hours a day and 54 substations manned 8 hours or less a day, 5 days a week.

In order to address the staffing implications of the new technology, BPA adopted formal Substation Classification and Staffing Criteria in 1983. This is the standard by which we determine staffing requirements for substation operations. It is based on BPA reliability criteria and operations workload.

The combination of increasing automation and consistent application of the criteria has resulted in significant gains in productivity. In 1975, BPA had 239 operators and 25 chief operators organized in 25 districts to service 325 substations. Today, 141 operators and 18 chief operators organized in 19 districts service 407 substations.

Further staff reductions would compromise response times for contingencies and BPA would be unable to provide satisfactory reliability to its customers.

Because of the reduced number of substation operators, it will be difficult to meet all needs for new dispatchers from the ranks of BPA substation operators. This has been BPA's traditional source of dispatchers because experienced operators already have much of the knowledge required by dispatchers. Recruits from other sources would need significantly more training. This training would be required in addition to increased training necessary for all dispatchers due to the addition of new and more sophisticated equipment and control schemes previously discussed.

To address these problems BPA plans to:

- Complete the upgrade of control and dispatch facilities through addition of new Transmission Control and Dispatch System (TCDS) and Real Time Operations and Dispatch System (RODS). The Eastern Control Center will be developed as a full backup to Dittmer.
- Institute annual system operations studies to better identify potential operating and capacity problems.
- Increase analysis of outages, system failures, and equipment failures. This will include initiating a detailed and accurate compilation of outage data.
- Significantly upgrade the substation operators' training center.
- Energize a dispatcher training facility equipped with a system simulator by October 1992.
- Add three dispatchers so that training may be conducted while still having the minimum required staff available to dispatch the system.
- Increase the number of substation operator apprentices from 10 to 16.

All of these steps are important. The training must not be taken lightly. It is essential to maintain proficiency and avoid errors. Suboptimal performance in dispatch and operations is very costly and has the potential to compromise safety.

The System Operations Program is summarized by function in Figure 1. ^{2/}

G. MAINTENANCE/REPLACEMENT STRATEGIES

In the past decade, BPA has been faced with competing demands for its limited resources. That competition forced BPA to make hard decisions concerning its resources. In the course of those decisions, BPA acted prudently in deferring maintenance and replacement programs. However, it is now necessary to change course to provide necessary resources to maintain and replace the transmission system over the next decade.

1. MAINTENANCE BACKLOG PLAN

In 1988, BPA made a decision to reduce the backlog of deferred transmission system preventive maintenance. First, maintenance intervals

^{2/} Selected major functions only. Does not represent total budget.

FIGURE 1
LEVELIZED OPERATIONS PROGRAM
BY SELECTED MAJOR FUNCTION
CONSTANT 1990 DOLLARS (M)

FIGURE 2

LEVELIZED 10-YEAR MAINTENANCE PLAN

WITH 2%/YEAR PRODUCTIVITY GAINS

April 11, 1990

Data File: Backlog 5 - 4/11/90

FIGURE 3

LEVELIZED 10-YEAR MAINTENANCE PLAN

WITHOUT 2% PER YEAR PRODUCTIVITY GAINS

April 11, 1990

Data File: Backlog 5F - 4/11/90

were reviewed. Maintenance intervals on some equipment were lengthened while prudence dictated that intervals on other equipment be shortened. In general, a net reduction in preventive maintenance workload resulted.

Next, BPA identified the resources required to accomplish the maintenance workload including scheduled preventive maintenance. This required the addition of 48 FTE. These resources were phased in over the FY 1989 through 1991 period. This is called the maintenance ramp.

Further, the Administrator committed additional temporary resources on an as available basis to reduce the backlog. Special attention was directed to the most urgent problems such as breaker maintenance and diagnostic testing of transformers.

As a result of these actions, BPA has reduced the overall maintenance backlog by 20 percent.

BPA is also committed to implementing levelized, long-range, operation, maintenance, and replacement programs which address the maintenance backlog.

The 10-Year Plan emphasizes replacements during the early years to reduce maintenance required by older equipment. It reduces the backlog gradually, with completion in 1999. This reduction is accomplished by providing necessary resources to accomplish the annual work plan (scheduled preventive maintenance) while replacing obsolete, maintenance-intensive facilities. No new resources are added to reduce the backlogged maintenance. This approach is the most cost effective.

The plan results in the least overall risk (short of investing substantially greater resources). It results in the most stable and predictable use of resources (money, staff, and engineering, construction, and procurement capability). It is consistent with the present long-range transmission system development and construction plans. Finally, this strategy makes it possible to move from backlog reduction to levelized operation without a traumatic adjustment in permanent staff. This is the most cost effective plan. Figures 2 and 3 illustrate the relationship between maintenance backlog, staffing, workload, and productivity.

Figure 2 illustrates how the backlog will be eliminated by the end of the decade provided that the replacement program and productivity gains are achieved.

- The levelized staffing curve represents the FTE resources the agency will devote to the maintenance program in the next 10 years. The increase shown in 1989, 1990, and 1991 represents the 48 FTE maintenance ramp. The remaining increase in 1992 and 1993 reflects the implementation of the 10-Year Plan.
- The levelized workload curve represents the workload after implementing the replacement strategy and achieving productivity gains of 1.5 to 2.0 percent per year. The decrease in workload shown in 1988 reflects revised maintenance intervals.

FIGURE 4
LEVELIZED, EXPENSED MAINTENANCE PROGRAM
BY SELECTED MAJOR FUNCTION
CONSTANT 1990 DOLLARS (M)

- The difference between the workload and staffing is approximately 10 percent. Overtime will be used to accomplish half the difference, or 5 percent. Therefore, BPA is staffing to complete 95 percent of the workload. The remaining 5 percent will be addressed in the annual work plan through short term productivity improvements.
- With the staffing in balance with the workload, the backlog will be reduced as the work plans are accomplished. This is illustrated by the upper line of Figure 2. As scheduled, preventive maintenance is completed and as equipment with backlogged maintenance is replaced, the maintenance backlog is eliminated. By 1999, maintenance backlog will be eliminated.

Figure 3 illustrates what will happen if productivity gains are not achieved or the replacement program is deferred. The workload will steadily increase to approximately 950 FTE, nearly 120 FTE greater than the levelized program. The backlog will decrease in the first years of the plan. However, as the workload increases, the backlog will increase to nearly the level of 1989.

The plan eliminates the maintenance backlog by 1999 without adding resources. If temporary resources are available, BPA will utilize those resources on an ad hoc basis to accelerate the backlog reduction.

At least two of BPA's customers expressed doubts and concerns with the backlog reduction assumptions and plans included in the draft 10-Year Plan. These customers either (1) wondered if BPA should not devote more resources to this effort or (2) questioned what should be an acceptable level. BPA will carefully monitor its progress in this regard and suggest changes as warranted over time.

2. MAINTENANCE STRATEGY

Maintenance will continue to rely on a well-defined preventive maintenance program which is funded and staffed at a level to accomplish 95 percent of the defined program. However, in the next decade, BPA will move from a time based program to a reliability centered program. Moving to reliability centered maintenance will occur gradually as on-line monitors and diagnostic techniques are developed. (See Appendix B for more detail on reliability centered maintenance.) Automated testing techniques will allow faster and more complete maintenance on most components of the power system. Maintenance frequencies will be adjusted as industry practices change. Pilot projects will be developed to test new maintenance techniques for application on the entire system. Emphasis will be placed on specifying replacements and additions to the system which require minimal maintenance and capitalize on economies of scale.

During public review of the draft plan, commenters supported BPA's intent to employ reliability centered (predictive) maintenance and suggested that BPA extend existing preventive maintenance intervals wherever possible. BPA plans to expeditiously incorporate reliability centered maintenance as technology becomes available and will continue to adjust maintenance frequencies based on prudent utility practices. Customers also requested that BPA keep them informed regarding the implementation of the reliability centered maintenance technology. BPA will attempt to share the results of pilot projects and other technical reports.

BPA will restore spare parts and equipment inventories to levels that assure the availability of adequate materials to meet the needs of the system and restore service with minimum outage duration. This will require BPA to temporarily increase expenditures for spares in order to assure inventory levels adequate to provide safe, reliable service.

The System Maintenance Program is summarized by function in Figure 4. ^{3/}

The major emphasis in the coming decade for non-electric maintenance will be the maintenance of facilities which directly support the power system. These facilities require periodic maintenance which is normally carried out by contractors. The present level of effort will remain fairly constant. Emphasis will be placed on maintaining a safe work environment and providing environmentally acceptable site maintenance.

Transmission line maintenance will be faced with increasing numbers of transmission facilities which are nearly 50 years old. Aging tests on steel structures will be required. Aerial thermovision and increased line patrols in rural areas will be necessary to insure the integrity of transmission lines. A slight increase in expenditures will occur near the end of the decade.

The substation maintenance function will become more productive through a strategy that stresses: 1) expanded technical training of its skilled workforce and expansion of its apprenticeship program; 2) addition of equipment specialist and engineering staff; 3) application of state-of-the-art technology in instrumentation systems for equipment condition monitoring; and 4) upgrading of tools and test equipment. A major thrust will be to increase equipment reliability.

System protection maintenance is faced with a very diversified workload. This function will be called upon to maintain 30-year-old meters and, at the same time, modern state-of-the-art microprocessor based equipment. Training and employee development to assure a work force capable of maintaining this broad range of equipment is high priority. In addition, automated testing techniques will be developed to further streamline maintenance practices.

Power system control efforts will focus on development of maintenance techniques which allow efficient maintenance practices by capitalizing on the use of monitoring equipment to implement reliability centered maintenance. Development of additional automated testing and diagnostic aids will allow BPA to maintain communication and control equipment in the face of increasing numbers and complexity.

3. REPLACEMENT STRATEGY

The system replacement program provides for equipment and material to replace capitalized portions of BPA's transmission lines, substations, control centers, radio stations, and other general facilities. In the past, BPA deferred a portion of its planned replacement program. As a result, additional investments must now be made to replace aging and failing components on the power system. Replacement emphasis will be on obsolete and maintenance intensive equipment and on acquisition of spare equipment needed to respond to catastrophic failures.

^{3/} Selected major functions only. Does not represent total budget.

FIGURE 5
SYSTEM REPLACEMENT PROGRAM
BY SELECTED MAJOR CATEGORY
CONSTANT 1990 DOLLARS (M)

TABLE I
REPLACEMENT EQUIPMENT AND QUANTITIES

<u>Equipment Category</u>	<u>Annual Quantity to be Replaced</u>	<u>Total Quantity Installed on the System</u>
A. Substation		
Batteries	16	325
Chargers	22	440
Transformers and Reactors	6	1075
500-kV Breakers	6	193
230-kV and Below Breakers	40	1510
Disconnects	40	7970
Fuses	15	3230
Instrument Transformers	100	6880
Capacitors	600 MVA	11,800 MVAR
B. Transmission Line		
Wood Poles	450-575	77,000
C. Control & Protection		
Meters	60	600
Annunciators	12	114
SICS	2	13
Oscillographs	9	92
Distance Relays	63	1136
D. Power System Control		
MWTT	40	610
SCADA RTU	8-20	129
MW Multiplex	40	594
UHF Radios	12	173
Batteries and Chargers	10-36	215
Engine Generators	5	72
Tone Equipment	18	172
Fault Locators	10	80
E. Non-Electric Plant		
Major Maintenance Complexes	1	20
Other O&M Buildings	2-3	765
Radio Buildings	1-2	91
Roofs	5-8	940
HVAC Units	2-3	700
Oil Spill Containment	3-5	116
Road/Yard Renovation	8-10	15,000,000 sq ft

FIGURE 6
ENVIRONMENTAL BUDGET
BY SELECTED MAJOR ACTIVITY
CONSTANT 1990 DOLLARS (M)

The replacement strategy will focus on increased substation and control equipment replacements during the first few years of the plan. This will help reduce the maintenance backlog and increase the productivity of BPA's workforce. Funding levels are expected to increase to \$59 million by 1995 and then gradually decrease to \$50 million by 1999.

The system replacement program by major function is shown in Figure 5. ^{4/} Table 1 provides a breakdown of average annual replacements by equipment type. Additional detail can be found in Appendix A.

Some of BPA's customers expressed concern that wood pole and electronic equipment replacement rates identified in the draft 10-Year Plan may be too long. BPA has major studies underway to evaluate these specific equipment types and will revise replacement rates based on study results. If BPA were to increase the wood pole replacement program at this time, poles with useful life would be replaced. However, BPA will be especially vigilant to determine the point at which the wood pole replacement program must be increased.

H. ENVIRONMENTAL STRATEGY

BPA has recently adopted a vision to provide a common focus and direction for the agency. This vision was expressed in two statements. The second statement is "The most competitive and socially responsible power system in the nation." Nowhere does that vision statement apply more directly than to BPA's environmental strategy.

BPA recognizes its responsibility to be good stewards of the environment. BPA intends to make consistent and measurable progress toward meeting these responsibilities.

1. BACKGROUND

Two kinds of environmental activities are associated with operations, maintenance, and replacement programs. The first is the control, containment, removal, and disposal of hazardous substances associated with the operation of the power system. The second is the environmental restoration and remedial action of contamination which occurred as a result of our past practices.

Meeting environmental responsibilities in these arenas requires BPA to take into account and comply with a host of regulations. These regulations are expected to increase in the future. The major laws and regulations which have been addressed in the plan are:

- The Toxic Substances Control Act (TSCA),
- The Clean Water Act,
- Safe Drinking Water Act,
- The Resource Conservation and Recovery Act (RCRA),
- The Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), and
- Corresponding State Statutes.

^{4/} Selected major functions only. Does not represent total budget.

This plan lays out a well-defined program to address BPA's responsibilities. However, there are major uncertainties which are not addressed:

- Laws and regulations are changing rapidly.
- Requirements and costs under CERCLA and corresponding State statutes are not well defined and not predictable at this time.
- The outcome of a number of investigations and studies are unknown at this time.

2. THE PLAN

In order to be efficient and cost-effective, the plan contemplates combining environmental work with other replacement work when possible. However, necessary steps will be taken to work with and resolve issues with the regulatory agencies to assure compliance, regardless of coordination with replacement efforts. Expenditures by major activity are shown in Figure 6. ^{5/} The budget shown for CERCLA cleanup is based on incomplete data and is expected to increase.

Several significant actions command the largest share of our attention. PCB's were used in the electrical industry as a fire retardant. However, PCB's are no longer manufactured due to environmental consequences. Although no longer made, PCB's remain in use in equipment installed prior to its regulation. Capacitors represent nearly 98 percent of BPA's PCB equipment. These capacitors are shunt and series capacitors located in substations. They are properly fenced and marked. Nevertheless, they represent a continual maintenance problem. The plan replaces about 600 MVAR of PCB capacitors each year. All PCB capacitors will be replaced on the system in approximately 16 years.

The Clean Water Act requires Spill Prevention Control and Countermeasure (SPCC) plans and spill containment for facilities with certain amounts of oil in proximity to water. In order to minimize the risk of discharging oil offsite, five substations per year will be retrofitted with oil containment.

Underground fuel tanks represent an environmental concern because of the potential for leakage into soil and groundwater. The plan will remove or replace all underground storage tanks by 1994. One of BPA's customers suggested that BPA remove as many buried tanks as possible. BPA agrees and will implement a plan that accomplishes this goal.

Over the 50-year history of BPA's transmission system, there have been spills caused by equipment leaks and failures. These past spill sites have been identified and those which have not been cleaned up must be addressed. Funding is included in this plan to clean up known sites. New treatment and disposal technologies need to be explored. BPA will support developmental efforts through the Electric Power Research Institute (EPRI).

BPA has reported nine possible sites to the initial inventory of CERCLA. BPA will investigate, assess, and take appropriate action at all nine sites. Funding is included in this plan for known activities at these sites.

^{5/} Selected major activities only. Does not represent total budget.

BPA will continue to develop and implement a Waste Management and Minimization Program to reduce generated wastes.

Finally, and perhaps most importantly, BPA will continue to provide appropriate environmental training to employees along with an accompanying Pollution Prevention Awareness program. These efforts will increase the environmental awareness of employees and provide instruction on environmental processes and work procedures. This training is expected to increase significantly over the decade.

I. REPLACEMENT AND TRAINING OF SKILLED EMPLOYEES

BPA's ability to implement this long range plan depends on maintaining a well trained, motivated workforce. Examination of expected retirement rates of the technical and craft workforce and the increasing complexity of the power system and power system equipment leads BPA to the conclusion that a high priority must be placed on employee replacement and training.

As mentioned previously under Major Findings, many of BPA's customers and the public supported the plan's training and apprentice programs. In fact, many customers expressed interest in utilizing any excess capacity in BPA's training facilities. Many customers were interested in looking for opportunities to cooperate in the development of appropriate community college programs as feeders to apprenticeship programs. BPA agrees and intends to further explore these possibilities with our customers.

During the next 10 years, there will be a very high turnover in BPA's technical and skilled crafts workforce. This will be primarily due to a large percentage of that workforce becoming eligible for and electing retirement. For example, during this period BPA expects to lose:

- About 75 percent of its dispatchers (25 employees),
- About 70 percent of its substation operators and chief operators (109 employees),
- About 50 percent of its line foremen, linemen, and groundmen (84 employees), and
- About 32 percent of its electricians and foremen (84 employees).

BPA has established apprentice programs for the electrician, lineman, and substation operator crafts. The entry point for dispatchers is normally through the substation operator craft. Over the next 10 years, BPA plans to obtain approximately 50 percent of its journeyman craftpersons through apprentice programs. The rest will be recruited from outside BPA. In order to implement that plan, BPA will:

- Increase the number of power system dispatchers by three to allow for training while maintaining minimum staffing to dispatch the system.
- Increase the number of apprentice linemen from eight to 12. This level will produce approximately four journeyman linemen per year.

- Increase the number of apprentice electricians from eight to 16. This level will produce approximately four journeyman electricians per year.
- Increase the number of apprentice substation operators from 10 to 16. This level will produce approximately six journeyman substation operators per year.

Of necessity BPA will continue to acquire equipment of diverse manufacture and differing technologies. Operating schemes and hardware will continue to increase in technical complexity. Training provided by vendors as part of procurement contracts is limited in depth and availability. It is usually provided at time of delivery, often years before actual maintenance is required.

A well designed and executed technical training program is necessary to maintain employee proficiency in the face of the above problems. However, the benefits of an active technical training program extend beyond maintaining employee proficiency. A training program is also a method of developing standard work practices and disseminating those standards to the work force.

To meet BPA's training needs, it is necessary to:

- Increase the training of linemen in such areas as hotstick use, truck driving, rigging, and erecting emergency restoration structures. The existing training area will be expanded to include a classroom facility.
- Establish a classroom facility for training apprentice electricians. That facility will include a central training substation and a mobile classroom/laboratory. Continued training for the existing workforce is essential to develop skills and techniques which will be needed for new equipment and diagnostic testing.
- Establish a system protective maintenance (SPM) training facility at Ross, preferably in conjunction with an SPM test and repair center. Automated testing techniques will increase productivity for metering and relaying maintenance.
- Establish a dispatcher training facility equipped with a system simulator for dispatchers and operators. A formal on-site training program will be developed for dispatchers at all levels. Equipment in the substation operators' training center will be upgraded to maintain comparability with current power system equipment.

J. PRODUCTIVITY

In order to prudently operate, maintain, and replace the system through 1999, without a significant increase in personnel, BPA must achieve productivity increases of 1.5 to 2.0 percent per year. Failure to achieve productivity goals will result in a backlog that increases rather than being reduced.

Any successful productivity program must be based on sound planning. First, performance level guides are reviewed annually based on manufacturer's recommendations, the experience of other utilities, and BPA experience. This review establishes the level of maintenance that must be accomplished. Secondly, a schedule of equipment that requires preventive maintenance is developed annually based on the performance level guides. This information, together with expected corrective maintenance and scheduled construction, is the basis for the annual maintenance plan. This procedure provides an opportunity to annually review maintenance accomplishments in comparison to the annual plan. In this regard, one utility suggested that BPA work with them and others to develop a coordinated maintenance scheduling system. This system would aim to obtain productivity gains and reliability improvements by coordinating work on critical elements in the same geographic area. BPA Area offices will continue to pursue such agreements with our customers.

Accelerating the replacement program through the middle of the decade increases productivity. For example, replacing a power circuit breaker that requires maintenance every 5 years with one that requires maintenance every 12 years reduces the total maintenance required. The replacement also eliminates any backlogged maintenance against the breaker that was replaced. As equipment is replaced, every effort will be made to select equipment which lasts longer and requires less maintenance. This means life costs will be factored into replacement decisions.

Many of the specific productivity measures contained in the technical report involve improved tools, work equipment, and training. There are many opportunities to improve productivity. Examples range from computer aided testing of protective relays to bucket trucks for some transmission line crews. The result of the former is to drastically reduce the time it takes to maintain some protective relaying schemes. The latter lets line crews work more efficiently in smaller crews. Increased productivity depends upon providing employees with up-to-date tools, equipment, and training. Reliability centered rather than time based maintenance will be implemented wherever practical. Reliability centered maintenance offers a promise of significant productivity improvement. However, widespread adoption of reliability centered maintenance depends upon further development of technology, power equipment, and work practices. Pilot projects will be implemented wherever feasible. Development of new technology and equipment through EPRI and equipment manufacturers will be fostered where possible.

Most importantly, BPA must seek to motivate and empower employees at all levels. This requires providing employees with the best tools, equipment, and training to do the job. At the same time employees are challenged to define the job that has to be done and to find better ways of doing the job defined. To that end it is necessary to:

- Continue to strengthen the O&M Team. The O&M Team consists of the Area O&M Managers and the OM&C Division Directors and Program Manager together with their functional teams.
- Encourage the use of Pilot Projects to test new technologies, equipment and work practices. Successes will become standard practice.

SYSTEM OPERATIONS, MAINTENANCE AND REPLACEMENT PROGRAMS CONSTANT 1990 DOLLARS (M)

	OPERATIONS	REPLACEMENTS	MAINTENANCE	TOTAL
FY90	20.5	45.2	63.9	129.6
FY91	21.0	61.7	64.3	147.0
FY92	21.2	47.8	66.0	135.0
FY93	21.2	58.6	66.4	146.2
FY94	21.2	51.1	66.3	138.6
FY95	21.2	58.7	66.8	146.7
FY96	21.2	54.8	67.0	143.0
FY97	21.2	55.0	67.2	143.4
FY98	21.2	54.0	67.4	142.6
FY99	21.2	49.9	67.7	138.8

FIGURE 7

- Utilize Verteams (a vertical slice through the organization) to examine specific functional areas and find opportunities for improvement.
- Implement a strengthened suggestion program. The goal is to increase the number and improve the quality of employee suggestions.
- Finally, BPA will seek constant improvement and employee feedback.

K. RESOURCE REQUIREMENTS

In order to implement this plan necessary resources will be required. Detailed resource requirements for each of the functions have been developed to enable BPA to operate, maintain, and replace facilities on BPA's transmission system. A summary of these resources is shown in Figure 7. The dollars displayed are in constant 1990 dollars and do not include inflation for salaries nor escalation of material costs. Likewise, the displayed figures do not include any overheads. The Operations and Maintenance Programs are expensed. The Replacement Program is capitalized.

Operations: The Operations Program begins at a base of \$20.5 million and will increase by approximately 3 percent over the 10-year period. This increase is due to the increased operator apprentice program and additional dispatchers. It is anticipated all other program elements will remain constant.

Maintenance: The Maintenance Program will increase to \$67.7 million by the end of the decade, which is a 6 percent increase over the 10-year period. This increase is due to the increased apprentice programs for electricians and line crafts and the training contained in this plan. In addition the plan provides a small increase for technical support. Finally there is a \$2 million increase to deal with the aging transmission facilities and a \$.5 million increase for additional environmental activities identified in the plan.

Replacement: The Replacement Program begins at a base of \$45.2 and increases to \$58.7 million in 1995 and decreases to \$49.9 million by the end of the decade. This reflects BPA's emphasis on replacing aging equipment during the early years. The major expenditures are associated with the purchase of replacement equipment and environmental restoration of BPA's substations.

APPENDIX A**EXCERPTS FROM TECHNICAL REPORT**

EXCERPTS FROM TECHNICAL REPORT

A. MAINTENANCE BACKLOG

In 1974 BPA faced an imbalance between preventive maintenance workload and resources available to accomplish preventive maintenance. Performance level guides (PLG's) that determine preventive maintenance frequencies were lengthened to match workload to available resources. At the same time, BPA began to defer its capital replacement program. By the early 1980's, BPA was routinely deferring painting of electrical equipment.

Faced with a static workforce, increased workload due to system growth and changing environmental regulations, and an aging power system, BPA began to accumulate a backlog of undone preventive maintenance tasks.

In 1988 we began to address this issue. First, we reviewed our maintenance frequencies. That review was based on manufacturers' recommendations, the experience of other utilities, and BPA's own experience. Maintenance frequencies on some equipment were lengthened while prudence demanded that frequencies on other equipment be shortened. In general, we were able to effect a net reduction in preventive maintenance workload by lengthening some frequencies and by relying on additional diagnostics to determine need for maintenance.

Next we identified the need for additional resources necessary to complete the remaining levelized workload, excluding the backlog. We assumed 5 percent productivity gains and the use of 5 percent overtime. We identified the need for an additional 48 FTE.* These additional resources are being phased in to the work force over a 3-year period beginning in 1989 and scheduled to be completed in 1991.

Next, the Administrator committed additional resources to reducing the backlog. After careful analysis of the backlog, 26 temporary employees and \$1.65 million were directed at the backlog in 1988. These resources were temporary electricians and painters. Part of these resources were directed to the backlog associated with replacement program. The temporary electricians were deployed to the field to augment our experienced crews. This began in the spring and was concluded in the fall of 1988. This concerted effort reduced the backlog by nearly 10 percent. With the infusion of permanent resources the backlog has continued to be reduced, although at a slower pace. By the end of 1989 the backlog had been reduced by 16 percent.

*FTE, as used in this plan, is a calculation equal to one employee or contractor working full time for 1 year. The calculation excludes all holiday and overtime hours and average leave hours. FTE is used to calculate both staff expended and workload requirements. For example, 20 temporary painters working a total of 3 months expend the equivalent of 5 FTE ($20 \times 1/4\text{YR} = 5$); or, the summer painting program requires the equivalent of 5 FTE in order to be completed in 3 months.

Finally, the Administration committed itself to develop a long-range plan to create a levelized operation, maintenance and replacement program which will address the maintenance backlog as well as serve as a planning guide for the next decade. As we addressed the plan, we developed two alternatives to reduce the backlog to an acceptable level:

Accelerated 5-Year Program. Reduce the backlog in a 5-year program by applying 20 FTE and \$1.65 million per year between 1990 and 1994. This will require full integration of electricians into BPA work force. Additional work and test equipment would be required to equip this additional work force. Implementation of this program would be to develop specific crews to address the backlog of maintenance and painting. The advantage of this alternative is that by directing additional resources at the backlog, it allows the current work force to perform their existing tasks without altering existing plans. The disadvantage of this alternative is that it would reduce resources that could be applied to the Replacement Program. Thus, at the end of the 5-year program, we would have done very little to correct the fundamental problem of aging power system equipment.

Reduction with Existing Work Force. Allow existing work force, augmented by temporary employees as available, to reduce backlog over time by performing maintenance at its next scheduled maintenance interval. Once the maintenance ramp-up of human resources is complete in 1991 and if the workload stays in balance with maintenance staffing, the backlog will be automatically reduced. If each year the preventive maintenance program is completed, then past due maintenance is eliminated with the completion of the next scheduled service. In addition, as the Replacement Program replaces older equipment, the past due maintenance on the replaced equipment will be eliminated. In most cases, the new equipment can be expected to have lengthened maintenance frequencies. Thus, the increased productivity resulting from Replacement Program will be used to offset system growth and to further reduce the backlogged maintenance. It is estimated that the maintenance backlog will be reduced to an acceptable level by the year 2000.

BPA has decided to implement the second alternative to address the backlog issue. With the adoption of the actions identified in this 10-Year Plan, the need to bring additional full-time resources is not considered necessary for backlog reduction. However we will monitor the amount of backlog to determine the need to apply additional resources in the future. In addition, we will utilize any temporary FTE that the agency may have to apply each spring and to the backlog in the summer months.

B. REPLACEMENT PROGRAMS

1. BACKGROUND

BPA replaces components in its transmission system as a capital expenditure, funded through BPA's borrowing authority. The System Replacement Program provides for equipment, for materials, and for associated planning, design and construction work to replace the transmission line, substation, control and general facilities of the Federal Columbia River Power System (FCRPS). The

Program also includes tools and work equipment and the capital costs of power system environmental restoration.

The 10-year projections for this program have two objectives. First, replacement criteria must meet the requirement for a reliable and safe system. Second, they aim to improve efficiency and maintainability. The projections are based on forecasted needs for replacing critical portions of the power system which have a high risk of failure or which require excessive maintenance due to age and deterioration. Much of this equipment is 30 to 50 years old, is beyond useful life, and lacks spares and factory parts support. Under a Transmission System Development Program (TSDP), some replacements are also made when a portion of our system must be upgraded to meet new energy needs. The Offices of OM&C and Engineering, with the Areas, work closely together to anticipate future needs and to coordinate these two programs.

The following tables show the 10-Year Plan for the System Replacement Program. They includes the major items and the resources we anticipate committing for each fiscal year. Note that this data is highly summarized and intended only to provide a concise overview. Details supporting the level of planned replacements are provided in the individual work group reports.

PLANNED ANNUAL REPLACEMENT QUANTITIES AND RESOURCES										
RPA & EQUIPMENT CATEGORY	FISCAL YEAR									
	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999
Substation										
Station Batteries	16	16	16	16	16	16	16	16	16	16
Battery Chargers	22	22	22	22	22	22	22	22	22	22
Transformers & Reactors	6	6	6	6	6	6	6	6	6	6
500-kV Breakers	6	6	6	6	6	6	6	6	6	6
230-kV & Below Breakers	40	40	40	40	40	40	40	40	40	40
AC Disconnects	40	40	40	40	40	40	40	40	40	40
Fuses	15	15	15	15	15	15	15	15	15	15
Surge Arresters	20	20	20	20	20	20	20	20	20	20
Control Cable (1000 ft)	50	50	50	50	50	50	50	50	50	50
Instrument Transformers	100	100	100	100	100	100	100	100	100	100
Capacitors (MVAR) 16 year rate	623	209	418	1226	655	620	602	501	586	685
FY Obligations \$(M)	20.4	28.6	18.6	27.0	22.3	26.5	24.5	26.0	26.9	23.7
FY FTE	71.5	78.5	70.0	74.5	67.0	76.0	72.0	75.0	76.0	71.0
Transmission line										
Wood Poles	450	450	450	450	450	475	495	520	545	575
Tower Grounding Platforms	49	67								
FY Obligations \$(M)	2.0	2.0	2.0	2.0	2.0	2.1	2.2	2.3	2.4	2.6
FY FTE	20.0	16.0	16.0	16.0	16.0	16.8	17.6	18.5	19.5	24.4
System Protection										
Watthour Meters	20	60	60	60	60	60	60	60	60	60
Analog & Digital Telemetry	20	67	68	67	68					
Annunciators	4	12	12	12	12	12	12	12	12	12
SICS		1	1	1	1	1	2	2	2	2
Oscillographs	9	9	9	9	9	9	9	9	10	10
Temperature Recorders	7	8	7	8	7	8				
Distance Relays		63	63	64	63	63	64	63	63	64
FY Obligations \$(M)	3.5	3.5	2.8	2.8	2.8	2.8	2.8	2.8	2.8	2.8
FY FTE	16.0	19.0	16.0	16.0	16.0	16.0	16.0	16.0	16.0	16.0

NOTE: Annual amounts are averages used for levelizing purposes over 10 years. As shorter-range needs are more precisely determined, these amounts will vary from the numbers shown.

PLANNED ANNUAL REPLACEMENT QUANTITIES AND RESOURCES

RPA & EQUIPMENT CATEGORY	FISCAL YEAR									
	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999
Power System Control										
Microwave Transfer Trip	22	40	40	40	40	40	40	40	40	40
SCADA RTU		8	20	20	16	16	16	16	16	16
Microwave Multiplex	12	40	40	40	40	40	40	40	40	40
UHF Radios	4	12	12	12	12	12	12	12	12	12
DATS					4	4	4	4	4	4
Comm Batteries & Chargers		36	36	36	10	11	10	11	10	11
Engine Generators (Radio Bldgs)	1	5	5	5	5	5	5	5	5	5
Submultiplex (Tone) Equipment		18	18	18	18	18	18	18	18	18
Fault Locators		10	10	10	10	10	10	10	10	10
Antennas	21	6	6	6	6	6	6	6	6	6
FY Obligations \$(M)	4.9	4.9	4.9	5.4	5.7	5.7	5.5	5.6	4.6	4.6
FY FTE	30.4	30.4	30.4	34.7	35.7	35.7	34.2	36.1	26.6	26.6
Non-electric Plant										
Major Maintenance Complexes		1	1	1	1	1	1		1	1
Other O&M Buildings	3	2	2	1	2	2	2	2	2	2
Vehicle Equipment Buildings	1	2	1	2	1	2	1	2	1	2
Radio Station Buildings	1	1			1	2	1	2	1	2
Roof Replacements	7	5	7	8	8	8	8	8	7	7
HVAC Replacements	2	3	2	3	3	3	3	3	3	3
Oil Spill Containment	3	5	3	3	3	5	5	5	5	5
Underground Storage Tanks	35	25	13							
Road/Yard Renovation	9	10	6	9	8	8	8	8	8	8
FY Obligations \$(M)	4.9	8.6	6.3	6.7	5.2	6.7	6.7	5.2	4.7	3.7
FY FTE	27.0	27.0	27.0	27.0	27.0	27.0	27.0	27.0	27.0	27.0
Environmental Restoration										
Remedial Actions at 9 CERCLA Sites			TO BE DETERMINED							
FY Obligations \$(M)	.1	.1	.5	2.0	2.0	2.0	2.0	2.0	2.0	2.0
FY FTE	2.0	2.0	3.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0
Tools & Work Equipment										
Helicopters			2	2		2				
Boom Trucks		2	2	2	2	2	2	2		
FY Obligations \$(M)	4.9	9.4	8.2	8.2	6.6	8.4	6.6	6.6	6.1	6.
FY FTE	-	-	-	-	-	-	-	-	-	-

NOTE: Annual amounts are averages used for levelizing purposes over 10 years. As shorter-range needs are more precisely determined, these amounts will vary from the numbers shown.

PLANNED ANNUAL REPLACEMENT QUANTITIES AND RESOURCES

RPA & EQUIPMENT CATEGORY

Program Planning & Evaluation

FY Obligations \$(M)

FY FTE

	FISCAL YEAR									
	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999
FY Obligations \$(M)	4.4	4.6	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5
FY FTE	70.8	71.0	71.0	71.0	71.0	71.0	71.0	71.0	71.0	71.0

TOTAL REPLACEMENT PROGRAM

FY Obligations \$(M) *

FY FTE

FY Obligations \$(M) *	45.2	61.7	47.8	58.6	51.1	58.7	54.8	55.0	54.0	49.9
FY FTE	237.7	244.9	234.4	244.2	237.7	247.5	242.8	248.6	241.1	241.0

* Obligations are in direct constant FY 1990 dollars and exclude BPA overhead loadings.

NOTE: Annual amounts are averages used for levelizing purposes over 10 years. As shorter-range needs are more precisely determined, these amounts will vary from the numbers shown.

APPENDIX B**RELIABILITY CENTERED MAINTENANCE
"THOUGHTS AND DISCUSSIONS"**

RELIABILITY CENTERED MAINTENANCE "THOUGHTS AND DISCUSSIONS"

Reliability centered maintenance (RCM) is a concept whereby equipment operating parameters are evaluated in relation to the potential for failure before maintenance is performed on a piece of equipment. Vital operating parameters are measured and compared with predetermined values. When differences between measured values exceed user established limits, warnings are issued, and maintenance is done to assure continuation of reliable service. These parameters may include temperature, pressure, load, number of operations, alarms, failures, time since last maintenance, operating environment, etc.

In the application of RCM to the BPA power system, evaluation criteria are established for each piece of equipment. For a high-voltage transformer, the evaluation criteria may include parts per million (PPM) gas-in-oil, operating temperature profile, vibration, or time since last maintenance. The criteria represents a set of measurement parameters upon which weighting factors may be established. Periodically, these factors are evaluated and a total rating for the equipment is determined. If this value is greater than the predetermined RCM comparison value, then maintenance is done. If the value is less than the predetermined value, maintenance is deferred.

Because time is no longer the primary scheduling factor, it becomes necessary to predict when maintenance is due for scheduling purposes. There are potential ramifications from this such as maintenance coming due at the wrong time of the year as well as too much maintenance coming due at the same time.

As RCM is developed, BPA will move slowly from a time-based maintenance process to one which relies on operating conditions and experiences to schedule work. This process will be evolutionary since it will require sophisticated equipment to monitor the established parameters. BPA will move into RCM slowly to assure that the expense of the monitoring equipment is offset by the savings in maintenance.

APPENDIX C**ACRONYMS**

APPENDIX: ACRONYMS

Below are listed acronyms which appear in this report.

BPA	Bonneville Power Administration
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
ECC	Eastern Control Center
EHV	Extra High Voltage
FCRPS	Federal Columbia River Power System
FTE	Full Time Equivalent (staff)
FY	Fiscal Year
HVAC	Heating, Ventilating, and Air Conditioning
kV	Kilovolts
MVAR	Megavolt Ampere Reactive
MWTT	Microwave Transfer Trip
OM&C	Office of Operation, Maintenance, and Construction
OM&R	Operations, Maintenance, and Replacement
PCB's	Polychlorinated Biphenyls
PLG	Performance Level Guide
PSC	Power System Control
RCM	Reliability Centered Maintenance
RCRA	Resource Conservation and Recovery Act
RODS	Real Time Operations and Dispatch System
RTU	Remote Terminal Unit
SCADA	Supervisory Control and Data Acquisition
SPCC	Spill Prevention Control and Countermeasure (Plan)
SPM	System Protection Maintenance
TSCA	Toxic Substances Control Act
UHF	Ultra High Frequency (radio)

END

DATE FILMED

10 / 29 / 90