ORNL/ER--48

DE92 004460

DEC 27 1991

FUNCTIONAL REQUIREMENTS FOR THE
TUMULUS I AND II CAP
WASTE AREA GROUPING 6
OAK RIDGE NATIONAL LABORATORY

JUNE, 1991

FY 1992 ENVIRONMENTAL RESTORATION

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Prepared by the
Oak Ridge National Laboratory
Oak Ridge, Tennessee 37831
managed by
Martin Marietta Energy Systems, Inc.
for the
U. S. DEPARTMENT OF ENERGY
under Contract No. DE-AC05-84OR21400

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

402

ORNL/ER-48
JUNE, 1991

APPROVAL OF FUNCTIONAL REQUIREMENTS FOR
TUMULUS I AND II CAP
SWSA 6, ORNL

Prepared by:	<u> </u> L. C. Cox	<u>6/29/91</u> Date
Reviewed by:	<u> </u> M. W. Kohring	<u>6-26-91</u> Date
Reviewed by:	<u> </u> J. H. Swanks	<u>7/1/91</u> Date
Reviewed by:	<u> </u> L. E. McNeese	<u>7/3/91</u> Date
Reviewed by:	<u> </u> M. A. Woody	<u>7/11/91</u> Date
Approved by:	<u> </u> S. D. Van Hoesen	<u>7/15/91</u> Date
Approved by:	<u> </u> S. B. Garland	<u>7/15/91</u> Date

TABLE OF CONTENTS

	<u>PAGE NO.</u>
1.0 INTRODUCTION AND PURPOSE	1
1.1 BACKGROUND	1
1.2 PURPOSE	2
2.0 PROJECT DESCRIPTION	2
3.0 MISSION	2
4.0 REQUIREMENTS AND SPECIAL ISSUES	2
4.1 REQUIREMENTS AND SPECIAL CONSTRAINTS	2
4.1.1 GENERAL FUNCTIONAL REQUIREMENTS	2
4.1.2 PERFORMANCE REQUIREMENTS	3
4.2 UNCERTAINTIES	5
4.3 INTERFACES AND INTERFACE REQUIREMENTS	6
4.4 SPECIAL ANALYSIS	6
4.5 HUMAN FACTORS	6
4.6 MAINTENANCE ISSUES	6
4.7 CRITICAL SYSTEMS	6
4.8 TESTING REQUIREMENTS	6
5.0 CONFIGURATION CONTROL PLAN	7
6.0 DISTRIBUTION LIST	7
REFERENCES	8
FIGURES	9

1.0 INTRODUCTION AND PURPOSE

1.1 BACKGROUND

The tumulus method of solid low-level waste (LLW) disposal began in 1989 with the Tumulus Disposal Demonstration (TDD) project, conducted on Tumulus I. See Figure 1, Tumulus Disposal Technology conceptual sketch. LLW is contained in 4-ft x 4-ft x 6-ft boxes which are placed into precast concrete casks. The annular space around the box is grouted with a cementitious grout before the lid is installed. The LLW does not contain RCRA materials or liquids. The casks are then stacked two high on the concrete tumulus pad. Prior to filling Tumulus I to capacity Tumulus II was constructed. Tumulus II will be filled to capacity by the end of 1991 at which time the Interim Waste Management Facility (IWMF) will have been constructed and will provide approximately six years of LLW disposal capacity. See Figure 2, SWSA 6 Site Plan, for location of Tumulus I and II.

The under and above pad monitoring drain systems for both tumuli are connected to a common monitoring station. See Figure 3, Tumulus Drain System, for pad monitoring system and monitoring well locations.

1.2 PURPOSE

This project will provide interim closure of the Tumulus I and II by designing and constructing a multilayered cap, with monitoring capabilities, which will be consistent in purpose with the requirements of an Record of Decision (ROD) which will result from the Waste Area Group (WAG) 6 closure and remediation effort. Capping Tumulus I and II has been a part of the overall tumulus disposal plan since inception in the Low Level Waste Disposal, Development and Demonstration (LLWDDD) program strategy issued in 1988.

2.0 PROJECT DEFINITION

This project consists of the design and construction of a low permeability cap over the Tumulus I and II disposal units. The cap shall incorporate a drainage system and be maintainable. The monitoring systems now in place will be modified and be utilized for post-closure monitoring of the pads and groundwater. The capability for performance assessment monitoring will be included in the design.

3.0 MISSION

The mission of the project is to provide a low permeability cap that will minimize infiltration, reduce surface radiation dose levels, protect the cap components and concrete casks from freeze/thaw cycles, and assess the performance of the cap. The organization of the project team is provided in Fig. 4.

4.0 REQUIREMENTS AND SPECIAL ISSUES

4.1 REQUIREMENTS AND SPECIAL CONSTRAINTS

4.1.1 General Functional Requirements

The cap will cover both of the tumulus pads. The cap will provide the functional capability to minimize infiltration, reduce surface radiation dose levels, and

provide freeze/thaw protection for the cap components and concrete casks. The cap will be designed so that it's performance can be assessed.

4.1.1.1 Infiltration Control

Infiltration will be minimized by a low permeability composite barrier located directly above the waste vaults and extending a minimum of 8-ft beyond the perimeter of the pads. The composite barrier will be clay soil compacted to a hydraulic conductivity of no less than 1×10^{-7} cm/sec and no less than 2-ft in depth. A Flexible Membrane Liner (FML) of no less than 30-mil in thickness will lay directly over the compacted clay layer.

A drainage layer will be located directly above the infiltration barrier to permit water to be drained away from the waste stack. The drainage layer will be a geo-grid overlain with a filter fabric.

The alternatives to be considered for the top surface shall include a native soil vegetative layer no less than 18-in. thick, asphalt, rip-rap, or a combination of these or other materials.

4.1.1.2 Groundwater and Surface Water Control

The A-E will perform an analysis to determine the plausibility of the backfill surrounding the waste stacks acting as a "wick" and bringing groundwater up to a level which encompasses the vaults and presents a threat of leaching radioactivity from the vaults. Features for preventing this type of activity will be incorporated in the design.

The effects of storm water flows will be determined by analysis and control features designed into the system.

4.1.1.3 Radiation Control

The allowable radiation dose rate at the cap surface is 25 mrem/yr. The cap will be designed to yield a dose rate at the surface of <25 mrem/yr.

4.1.1.4 Inadvertent Intrusion Control

Inclusion of an intrusion barrier is not required in this project, however, the cap design should not preclude the construction of an intruder barrier on top of the low permeability layer at some time in the future. The issue of intrusion barriers is an overall WAG 6 closure concern.

4.1.1.5 Gas Accumulation

Gas is not likely to be generated from the tumulus waste since it is well contained and has been screened to eliminate gas producing substances such as RCRA materials and liquids.

4.1.1.6 Freeze Protection

Freeze protection for the cap components and concrete casks will be provided by the top layer configuration. The design will verify that all cap components and the concrete casks are protected from freeze/thaw cycles.

4.1.1.7 Structural Stability

The casks will be evaluated to ensure they are capable of supporting the loads imposed by the cap and the equipment required to construct the cap. The A-E shall determine from a structural analysis of the casks and pad whether additional structural support will be necessary for Tumulus I and II to ensure structural stability of the cap.

4.1.2 Performance Requirements

To determine if the functional requirements have been met the performance of the cap must be assessed. The performance assessment will consider design life, failure modes, maintenance, and monitoring.

4.1.2.1 Design Life

The design life of the interim cap is 100 years for institutional control purposes. The major cause of cap failure is subsidence and displacement of the components due to natural causes, such as floods and earthquakes. Since the underlying components of the cap are the concrete waste vaults and pad, subsidence is not a major threat. Floods could pose a threat because of the close proximity of the drainage ditch on the west side. Erosion control to mitigate a flood event which would damage the cap will be included in the design. Seismic events capable of damaging the cap, although possible, are not likely during the 100 year institutional control period.

4.1.2.2 Failure Modes

Upon defining a cap system, the A-E will perform a failure mode and effect analysis which considers the site climatic, geologic, and hydrologic conditions. The analysis shall identify those actions which will minimize the effects of the failure events.

4.1.2.3 Maintenance

Maintenance during the institutional control period would include mowing, tree/brush removal, ditch cleaning, seeding and mulching, and animal control. The cap would be inspected periodically for damage and repairs would be made as needed.

4.1.2.4 Monitoring

Monitoring is anticipated during the institutional control period only and will be the primary means of determining the functional worthiness of the cap.

Post-closure monitoring of the tumulus disposal units will consist of a pad monitoring system and a groundwater monitoring system. The pad monitoring system shall provide means to sample any liquids which may form on the surface of the pads. In addition, any water which may collect under the pads will be monitored. The groundwater monitoring system will consist of shallow monitoring wells located around the perimeter of the two pads.

Each pad shall be capable of being monitored separately. This will require modifications to the existing piping systems. In addition, the drain lines shall be modified to incorporate clean-outs which will allow access to all lines. The clean-outs shall not penetrate the low permeability portions of the multilayer barrier cap.

It may be necessary for one of the monitoring wells (#1259, See Fig. 2) to penetrate the barrier cap. If so, the well casing will have to be sealed at each cap layer to prevent water intrusion. All other monitoring wells lie outside the perimeter of the cap. Not all wells will be preserved and those which are abandoned will have to be done so in compliance with approved procedures. If new monitoring wells are to be drilled they shall be slant drilled such that the casings do not penetrate the multilayer cap.

The monitoring system must also provide a means of determining if the cap is performing as designed by providing the capability to verify the performance requirements. Performance assessment would be best demonstrated by collecting the data which would support the conduct of an accurate water balance study. A reliable means of measuring rainfall, surface run-off, evapotranspiration, infiltration and leaks is necessary. The design will include these capabilities.

The existing monitoring station will be evaluated as to condition and upgraded, or replaced, as necessary to meet the monitoring requirements.

Tumulus II has a network of strain sensors/gauges installed. The wiring and associated devices shall be extended to an accessible location at the surface of the cap without penetrating the cap.

4.2 UNCERTAINTIES

A National Environmental Policy Act (NEPA) determination is in place for this project in the form of a Action Description Memorandum (ADM 0280X dated March 7, 1988) for Tumulus I and a Activities Description Memorandum (AcDM 0700X dated April 6, 1989) for Tumulus II. Design is scheduled to start in the 4th quarter of FY 1991 so that construction may be initiated in the 3rd quarter of FY 1992 and be complete in the 1st quarter of FY 1994. Other activities will be necessary to support this project. A source of low permeability clay will have

to be identified to provide the clay soil for the infiltration barrier. The well plugging and abandonment project will need to be operational to properly plug and abandon those monitoring wells deemed unnecessary.

The length of the institutional control period is not clear at this time. This project will install an interim cap and will be designed for a 100 year institutional control period.

4.3 INTERFACES AND INTERFACE REQUIREMENTS

This project will have to interface with other WAG 6 closure construction projects in the immediate vicinity. There will be an interface with the ORNL Ground Water Program and ORNL Waste Operations groups since the buildings immediately to the east of the tumulus will be operational.

There are no requirements for electrical service or other utilities except at the monitoring station.

An interface with the Waste Operations Group will be required to provide capability to collect, store and transport contaminated liquids which may accumulate at the monitoring station during construction of the cap. The temporary covers which serve to reduce run-off will be removed when construction starts. The high pH (>9.0) run-off caused by the concrete casks cannot be discharged and will have to be collected, stored and transported for treatment.

4.4 SPECIAL ANALYSES

A special analyses is required to determine the structural capability of the vaults to support the cap and the equipment necessary to construct the cap. The analyses should consider horizontal loads as well as vertical loads.

A hydrological and hydraulic analysis is required to determine if groundwater upwelling around the tumulus is going to be a problem.

The designer will perform an analysis to determine the effect of the cap on the production of high pH stormwater run-off. It is suspected that the high pH is being caused by the reaction between constituents in the concrete casks and rainwater. The designer will show by analysis that the cap will sufficiently eliminate water contact with the casks so that high pH (>9.0) in the run-off water will not be a problem.

4.5 HUMAN FACTORS

The monitoring station shall be designed to allow safe ingress and egress. Electrical outlets shall be furnished with ground fault protection devices.

4.6 MAINTENANCE

The cap final slopes will not exceed 3-ft horizontal to 1-ft vertical except where surface protection features which minimize erosion, and do not require maintenance, will be incorporated.

4.7 CRITICAL SYSTEMS

There are no critical systems associated with this project.

4.8 TESTING REQUIREMENTS

All drain piping shall be tested to assure water-tightness prior to constructing the cap. Access to all piping via clean-outs shall be verified.

Permeability testing of the compacted soil infiltration barrier will be conducted using standard Proctor densities. A QA control of this testing shall be strictly enforced.

The flexible membrane liner (FML) will be non-destructively tested at the seams and repaired areas. Excess FML cut into narrow strips and seamed using the same method as on the liner will be shear and peel tested in accordance with National Science Foundation (NSF) procedure #54.

All performance assessment features will be tested to verify their function.

All test plans, testing, and test results will be documented and submitted to Environmental Restoration Division (ERD) for review. All problems and deficiencies encountered during testing will be resolved and corrective action taken in accordance with applicable QA procedures.

5.0 CONFIGURATION CONTROL PLAN

All changes to the approved design will be reviewed and approved by the Program Project Manager and ERD in accordance with the Configuration Control Plan for WAG 6.

6.0 DISTRIBUTION LIST

All organizations represented by the signatures to this document shall receive a copy of all revisions to same.

REFERENCES

Oak Ridge National Laboratory. 1988. Closure Plan for Solid Waste Storage Area 6 ORNL/RAP/Sub-87/99053/9TV1/R1 Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Oak Ridge National Laboratory. 1988. Health, Safety, and Environmental Protection Procedure for Excavating Operations. ORNL/M-116/R1. Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Mortimore, J. 1988. Groundwater Quality Monitoring Well Installation - WAG 6. ORNL/RAP-44. Oak Ridge National Laboratory, Oak Ridge, Tennessee.

FIGURES

Figure 1. SWSA 6 Site Plan

Figure 2. Tumulus Drain System

Figure 3. Project Team Organization

Fig. 1 Tumulus Disposal Technology

Figure 2 SWSA 6 Site Plan

- Monitoring Well
- - - Drainage Ditch
- Existing Building

Figure 3 Tumulus Drain System and Monitoring Wells

Figure 4. Project Team Organization for WAG 6 Closure

END

DATE
FILMED

4 / 30 / 92