DOE/PC/88879--T2

DE92 011014

ENGINEERING DEVELOPMENT OF SELECTIVE AGGLOMERATION

TASK 6 OPERATION OF THE COMPONENT DEVELOPMENT TEST FACILITY

SEPTEMBER 1991

**U.S. DEPARTMENT OF ENERGY
CONTRACT NO. DE-AC22-89PC88879**

**PREPARED BY:
SOUTHERN ELECTRIC INTERNATIONAL, INC.
WILSONVILLE, ALABAMA**

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, mark, manufacturer or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

TABLE OF CONTENTS

Section	Page
EXECUTIVE SUMMARY	-i-
1.0 INTRODUCTION	1-1
1.1 Objective of the Report	1-1
1.2 Scope of CDTF	1-1
2.0 CONSTRUCTION	2-1
2.1 Site Preparation	2-1
2.2 Concrete and Structural Steel	2-1
2.3 Equipment Installation	2-1
3.0 DESCRIPTION OF CDTF	3-1
4.0 COAL PROCUREMENT	4-1
5.0 CDTF OPERATION	5-1
5.1 Introduction	5-1
5.2 Startup and Shakedown of CDTF	5-1
5.2.1 Startup and Calibration of Ball Mills	
5.2.2 Startup and Calibration of Agglomeration Process	
5.2.3 Startup Tests	
5.3 Operating Parameters Optimization	5-17
5.3.1 Optimization with 28 Mesh Coal	
5.3.2 Optimization with 100 Mesh Coal	
5.4 Mechanical Dewatering Tests	5-30
5.4.1 Evaluation of Dewatering Equipment with Small Agglomerates	
5.4.2 Production of Product for Pelletization	
5.4.3 Evaluation of Dewatering Equipment with Large Agglomerates	
5.4.4 Refuse Dewatering Vendor Tests	
5.5 Experience and Knowledge Gained	5-52

TABLE OF CONTENTS
Continued

Section	Page
6.0 LABORATORY TEST WORK	6-1
6.1 Introduction and Summary	6-1
6.2 CDTF Operations Support	6-1
6.3 Batch Agglomeration Test Work	6-1
6.3.1 Binder Evaluation	
6.3.2 Heptane Process	
6.3.3 Evaluation of Precleaned Coals	
6.4 Vendor Testing	6-10
6.4.1 Vendor Drying Tests for Heptane Removal	
6.4.2 Vendor Pelletization and Drying Tests	
6.5 Product Characterization	6-17
6.5.1 CDTF Samples	
6.5.2 Vendor Samples	
APPENDIX A	CDTF Operations Test Data
APPENDIX B	Laboratory Procedures
APPENDIX C	CDTF Laboratory Test Data
APPENDIX D	Laboratory Binder Test Data
APPENDIX E	Vendor Test Report

LIST OF FIGURES

Figure	Page
1-1 Component Development Test Facility	1-2
2-1 Site Preparation	2-2
2-2 CDTF Plant Layout	2-4
3-1 CDTF Block Flow Diagram	3-2
5-1 Task 6 CDTF Schedule	5-2
5-2 Ball Mills	5-5
5-3 High Shear Vessel	5-12
5-4 Flotation Cells	5-13
5-5 Low Shear Mixers	5-19
5-6 Sieve Bend and Vibrating Screen	5-27
5-7 Plate and Frame Filter Press System	5-33
5-8 Screen Bowl Centrifuge	5-35
5-9 Horizontal Belt Vacuum Filter	5-41
5-10 Thickener	5-51
B-1 Block Diagram of MICROTRAC	B-2
B-2 Apparatus for Azeotropic Distillation of Water	B-7
B-3 Apparatus for Soxhlet Extraction of Heavy Oil	B-11
B-4 Apparatus for Vacuum Distillation of Diesel and Asphalt	B-15

LIST OF TABLES

Table	Page
4-1 Coal Information	4-2
5-1 Summary of Operating Runs 4 - 12	5-17
5-2 Mechanical Dewatering Tests with Small Agglomerates	5-31
5-3 Mechanical Dewatering Tests with Large Agglomerates	5-46
6-1 Residual Heptane Concentrations	6-15

**Engineering Development of Selective Agglomeration
DE-AC22-89PC88879**

OPERATION OF THE COMPONENT DEVELOPMENT TEST FACILITY

EXECUTIVE SUMMARY

The purpose of this report is to summarize the component development and laboratory binder test work at Wilsonville during Task 6. This Task included the construction and startup of the Component Development Test Facility (CDTF), coal procurement, evaluation of unit operation and dewatering performance, laboratory binder tests for diesel and heptane, product characterization, and vendor tests. Data evaluation, interpretation, and analysis will be discussed in the Task 7 report.

The Component Development Test Facility was constructed at Wilsonville, Alabama, to allow unit operations testing at the 3 t/h continuous scale. The objective of the CDTF unit was to provide pilot plant data difficult to generate on smaller scales, such as testing of unit operations, evaluation of various methods of dewatering both the agglomerate product and refuse, and optimization of operating parameters. The program was divided into several areas: startup and shakedown of the grinding system and agglomeration circuit, evaluation of operating parameters, and testing of mechanical dewatering of product agglomerates and refuse.

The Task 6 component development program was structured to provide verification of equipment operability prior to actual optimization and dewatering tests. The tests conducted during Task 6 used both 28 and 100 mesh coal slurries at various binder concentrations and compositions to achieve a range of products for characterization and dewatering tests. Two startup runs with diesel binder to low shear and one with asphalt/diesel binder to low shear were conducted to allow checks of the system equipment and gain operating experience.

Optimization of operating parameters was an important objective of CDTF operation. Five binder optimization test runs were conducted with 28 mesh grind coal with the addition of diesel in high shear and asphalt/diesel binder blends in low shear. These tests focused on the production of agglomerates of 1 - 3 mm in diameter. Binder concentrations tested ranged from 8 to 12 wt % in the two low shear mixers, which were operated both in series and individually. The binder composition was typically 60/40 wt % asphalt/diesel. Binders with higher asphalt compositions were tested, with no visible improvement in product size or strength. Two optimization runs with 100 mesh coal were completed. These runs used 12 - 15 wt % binder to low shear for production of 1 - 3 mm agglomerates. Once system operability and optimization were completed, the dewatering tests were performed.

Another objective of the component development test program was to produce agglomerates at the pilot plant scale for evaluation of dewatering techniques for both product and refuse. Testing of several types of equipment was conducted to provide sufficient information on the dewatering characteristics of the product agglomerates and refuse. The results of these tests provide the data required to select appropriate equipment for use in later phases of the project.

The laboratory at Wilsonville was used to conduct all analyses on CDTF samples. Samples from each of the CDTF operating and startup runs were analyzed to assist in targeting steady-state operation and in understanding the performance achieved by the various unit operations within the process. In addition, batch binder tests were conducted with diesel and heptane, various agglomerates were produced for vendor tests, and product characterization was performed. Precleaning tests also were conducted to determine the overall improvement in agglomeration process performance.

Tests were performed using laboratory-scale test units at dryer vendor laboratories to evaluate the removal of heptane from agglomerates produced in a heptane process. A vibrating fluidized bed dryer, a rotary tray dryer, and an indirect disc type dryer were

tested. The objectives of the dryer tests were to define the dryer conditions required to process the heptane agglomerates at acceptable levels of agglomerate degradation, estimate the rate of volatiles removal, and measure the trace heptane concentrations in the dried agglomerates. Product characterization tests were performed with the dryer test products to determine how well the product held up in the dryer units.

Size enlargement via disc pelletization was completed at Ferro-Tech facilities with product samples collected from the CDTF horizontal vacuum belt filter. The variables tested included binder type and concentration, method of disc feed preparation, and asphalt content. Pelletization product was dried and subjected to various tests.

Optimization of operating parameters was an important objective of CDTF operation. Five binder optimization test runs were conducted with 28 mesh grind coal with the addition of diesel in high shear and asphalt/diesel binder blends in low shear. These tests focused on the production of agglomerates of 1 - 3 mm in diameter. Binder concentrations tested ranged from 8 to 12 wt % in the two low shear mixers, which were operated both in series and individually. The binder composition was typically 60/40 wt % asphalt/diesel. Binders with higher asphalt compositions were tested, with no visible improvement in product size or strength. Two optimization runs with 100 mesh coal were completed. These runs used 12 - 15 wt % binder to low shear for production of 1 - 3 mm agglomerates. Once system operability and optimization were completed, the dewatering tests were performed.

Another objective of the component development test program was to produce agglomerates at the pilot plant scale for evaluation of dewatering techniques for both product and refuse. Testing of several types of equipment was conducted to provide sufficient information on the dewatering characteristics of the product agglomerates and refuse. The results of these tests provide the data required to select appropriate equipment for use in later phases of the project.

The laboratory at Wilsonville was used to conduct all analyses on CDTF samples. Samples from each of the CDTF operating and startup runs were analyzed to assist in targeting steady-state operation and in understanding the performance achieved by the various unit operations within the process. In addition, batch binder tests were conducted with diesel and heptane, various agglomerates were produced for vendor tests, and product characterization was performed. Precleaning tests also were conducted to determine the overall improvement in agglomeration process performance.

Tests were performed using laboratory-scale test units at dryer vendor laboratories to evaluate the removal of heptane from agglomerates produced in a heptane process. A vibrating fluidized bed dryer, a rotary tray dryer, and an indirect disc type dryer were

1.0 INTRODUCTION

1.1 Objective of the Report

The objective of this report is to summarize the component development and laboratory binder test work at Wilsonville during Task 6. This Task included the construction and startup of the Component Development Test Facility (CDTF), coal procurement, evaluation of unit operation and dewatering performance, laboratory binder tests for diesel and heptane, product characterization, and vendor tests. Data evaluation, interpretation, and analysis are not included in this report, but will be discussed in the Task 7 report.

1.2 Scope of CDTF

The Component Development Test Facility was constructed at Wilsonville, Alabama, to allow unit operations testing at the 3 t/h continuous scale. The objective of the CDTF unit was to provide pilot plant data difficult to generate on smaller scales, such as testing of unit operations, evaluation of various methods of dewatering both the agglomerate product and refuse, and optimization of operating parameters. The program was divided into several areas: startup and shakedown of the grinding system, startup of the agglomeration circuit, evaluation of operating parameters, and testing of mechanical dewatering of product agglomerates and refuse. The design of the 3 t/h CDTF was developed incorporating maximum flexibility for possible future modifications. Equipment procured for the facility is generic and based on proven technologies so that specific pieces of equipment can be used interchangeably regardless of the design of the agglomeration circuit. Most of the equipment can and will be used in the POC module. The Component Development Test Facility is shown in Figure 1-1.

Figure 1-1: Component Development Test Facility (CDTF)

2.0 CONSTRUCTION

2.1 Site Preparation

Site preparation began with the clearing of trees from the selected 14 acre site at the Clean Coal Research Center in Wilsonville, and removal of the stumps and refuse. The site was then graded to meet the requirements set forth in the project civil package. The grading required the removal and filling of significant amounts of soil to provide an area of suitable size for process pads and coal storage. The area was suitably compacted and drainage provided via sloping and ditches. A fence was installed around the site, with access from the existing liquefaction facility provided. The site is shown in Figure 2-1.

2.2 Concrete and Structural Steel

Concrete foundations for the conveyors, crusher tower, and ball mill pad were installed once the site preparation was complete. The yard drainage structure (coal storage runoff basin) and process pad were completed next. Structural steel for all areas was installed, including the crusher tower and conveyors, ball mill structure, and process structure. Finally, foundations for the binder oil storage tanks and thickener were provided. Figure 2-2 shows the CDTF plant layout.

2.3 Equipment Installation

A subcontractor began work on the mechanical and electrical portions of Task 6 construction in early September, 1990, and completed that scope of work in late February, 1991. Maintenance craftsmen with SEI completed some additional equipment installation and system modifications in the first two months of operation. All process equipment and piping were installed. The piping was installed so as to minimize plugging by using two 45 degree turns in place of a 90 degree turn. Bypass piping was installed around some of the equipment.

Figure 2-1: Site Preparation

Utility tie-ins were made to existing facilities at the site - firewater, process water, potable water, sanitary piping, and instrument air. All firewater systems were inspected and tested, and all deficiencies corrected. The insurance underwriters conducted a survey of the site to identify the potential for property loss and recommended action to correct deficiencies found. All action items were corrected.

Electrical power was supplied to all equipment and lighting provided. Control panels were provided for the ball mills, weigh belt feeder, filter press system, and dewatering equipment. An intercom system, tied into the existing liquefaction system, was installed.

Figure 2-2: CDTF Plant Layout

3.0 DESCRIPTION OF CDTF

The coal crushing and grinding system consists of a hammermill coal crusher, weigh belt feeder, two ball mills (primary and secondary), and necessary hoppers and conveyors. The mills are capable of providing coal over a range of grinds from a d_{50} of 125 to 25 microns.

A conceptual block diagram of the CDTF is shown in Figure 3-1. The agglomeration circuit consists of a high shear mixer, where diesel (1 - 1.5 wt % dry coal feed basis) is added to begin the formation of microagglomerates, followed by conventional flotation cells for microagglomerate recovery. The flotation cell product is pumped to low shear mixers (either individually or in series, depending on residence time requirements), where binder is added for agglomerate growth. The binder consists of emulsions of various concentrations and compositions of asphalt and diesel in water, depending on coal grind and target product size expectations. The binder emulsion is produced with a colloid mill, and is introduced to the flotation product either in the piping entering the low shear vessels or through a binder contact vessel upstream of the vessels. Low shear product is then sent to the dewatering equipment being tested. Dewatered product is conveyed into dumpsters for transporting of the material to the utility plant located next to the facility. Tailings from flotation cells and dewatering are processed through a thickener for solids removal and water clarification, from which the water is recycled to the process and the solids are concentrated and pumped to refuse dewatering. Plate and frame filter presses were used for refuse dewatering throughout Task 6.

Figure 3-1: CDTF Block Flow Diagram

4.0 COAL PROCUREMENT

The objective of the coal procurement activity was to provide the appropriate quantity and quality of base test coals for the project as needed. The three coals selected for the project were Upper Freeport, Pittsburgh No. 8, and Western Kentucky No. 9. Upper Freeport seam coal was selected for Task 6 CDTF operation based on batch data from the confirmatory test program.

Specific coal vendors were selected and coal sales agreements reached with regard to coal quality specifications, tonnages, shipping schedules and coal prices. About 40 tons of each project coal was received and processed into various samples:

- o A one ton lot was crushed to 1/4" and subdivided into 20 lb sub-samples. The sub-samples were individually packed in plastic bags, purged with nitrogen, and placed in 55 gallon drums. This lot was kept at Wilsonville for shipments for specific tests, as needed.
- o A two ton lot was crushed to 1/4" and subdivided into 20 lb sub-samples. The sub-samples were individually packed in plastic bags, purged with nitrogen, and placed in 55 gallon drums. This lot was shipped to Alberta Research Council, Alberta, Canada.
- o A one ton lot of as-received coal was placed in 55 gallon drums, inerted, and shipped to a commercial laboratory for size and washability analysis
- o A one ton lot of as-received coal was placed in 55 gallon drums, inerted, and stored at Wilsonville for possible future use
- o The remainder of each 40 ton shipment was placed in 55 gallon drums, inerted, and stored at Wilsonville

Prior to each shipment of coal to the CDTF, the mine was visited to ensure the coal was freshly mined and properly sized, the trucks were cleaned and covered, and that the coal was of suitable quality. The coal storage pad at Wilsonville was cleaned before the coal shipments were delivered. The quality of the three project coals is shown in Table 4-1.

The table also indicates the total tonnage of each coal purchased. About 60 - 80 tons of Upper Freeport coal was disposed of at Alabama Power Company's E. C. Gaston plant (located next to the CDTF) at the end of Task 6.

Table 4-1

COAL INFORMATION

	<u>Upper Freeport</u>	<u>Pittsburgh 8</u>	<u>Kentucky 9</u>
Btu, db	12,700	13,100	12,450
Ash, db	16	12	16
Sulfur, db	2	4	5
Moisture	4	6	6
Tonnage	501.0	45.1	46.2
Mine Shipments	5	1	1
Drums to ARC	178	59	40

5.0 CDTF OPERATION

5.1 Introduction

The CDTF was constructed to allow testing of unit operations, evaluation of mechanical dewatering equipment, and optimization of operating parameters. The Task 6 program was structured so as to allow verification of equipment operability prior to actual optimization and dewatering tests. Once this was completed unit performance tests were made.

The tests conducted during Task 6 used both 28 and 100 mesh coal slurries at various binder concentrations and compositions to achieve a range of products for characterization and dewatering tests. Binder additions of about 9 wt % to the low shear mixers were required with 28 mesh grind slurries for the formation of large agglomerates. With 100 mesh coal slurries about 12 wt % binder was required. Large agglomerates (≥ 1 mm) are those which can be recovered from the low shear product by continuous screen operations, while small agglomerates (≤ 1 mm) must be handled by more extensive dewatering equipment for adequate moisture removal. CDTF operating data are included in Appendix A. A schedule of the tests is shown in Figure 5-1.

Prior to construction and operation of the Selective Agglomeration plant, the site National Pollutant Discharge Elimination System (NPDES) permit was modified to allow discharge of coal pile runoff from the plant. Because this permit requires flow rate measurements of all exiting streams from the facility, a flowmeter was installed in the Yard Drainage Structure discharge piping to allow monitoring and reporting of that flow. The permit requires treatment of the runoff water, if necessary, to adjust the pH, total suspended solids (TSS), magnesium, and iron prior to discharge. The system was first used on May 8, 1991. All parameters were checked and found to be within NPDES permit limits. The basin was then drained to the permitted discharge point. No problems or violations were experienced with the coal pile runoff during Task 6 operation.

Figure 5-1: Selective Agglomeration Task 6 CDTF Schedule

5.2 Startup and Shakedown of CDTF

Shakedown of the CDTF began with operation of the coal crushing and grinding system in December of 1990. Once the crusher and conveyors were functioning properly, the primary and secondary ball mills were calibrated.

Two startup runs with diesel binder to low shear and one with asphalt/diesel binder to low shear were conducted to allow checks of the system equipment and gain operating experience.

Five binder optimization test runs were conducted with 28 mesh grind coal with the addition of diesel in high shear and asphalt/diesel binder blends in low shear. These tests focused on the production of agglomerates of 1 - 3 mm in diameter. Binder concentrations tested ranged from 8 to 12 wt % in the low shear mixers, which were operated both in series and individually. The binder composition was typically 60/40 wt % asphalt/diesel. Binder with higher asphalt compositions were tested, with no visible improvement in product size or strength.

Two optimization runs with 100 mesh coal were completed. These runs used 12 - 15 wt % binder to low shear for production of 1 - 3 mm agglomerates.

In general, the plant achieved steady state operation two hours after coal feed was begun, if the low shear vessels were started up empty. Any change in binder addition rate or composition took 1.5 hours to achieve steady state (only the low shear vessels were impacted by the changes). The run length varied depending on the test conditions of the day, but generally was six or seven hours. The product consistency determined the volume of dumpster capacity available for a given run.

5.2.1 Startup and Calibration of Ball Mills

The grinding circuit was checked and started up before construction of the remainder of the plant was completed to allow preparation of some of the project coals. The coal crusher was started and used to prepare 160 drums of Western Kentucky No. 9 coal. This coal had been selected as the third test coal, replacing Illinois No. 6. The coal was crushed to 99 wt % + 1/4" x 0, drummed, bagged and inerted with nitrogen.

Calibration of the weigh belt feeder then began. The feeder was found to be operating properly, but the controller would not change belt speeds. The manufacturer was contacted to resolve this problem. The weigh belt feeder was calibrated at a 3 t/h dry coal feed rate. The water flow to the primary mill was calibrated at 18 gpm, to provide 40 wt % coal in the mill slurry, per the manufacturer's recommendation.

The primary and secondary mills were operated empty to ensure the cylinders rotated freely, then balls were charged to the primary mill. The manufacturer had specified four tons of balls to the primary mill to achieve a product with a d_{50} of 60 microns. Only two tons were initially charged, until a measurement could be made of the grind at that charge. The ball mills are shown in Figure 5-2.

The first primary mill calibration test run took place at a 3 t/h feed rate with a 40 wt % slurry in the mill. The objective of the run was to determine particle size distribution (PSD), evaluate accuracy of water flow rate calibrations to the primary mill and secondary mill sump, and continue to shake down the filter presses. Samples were taken to determine performance of the mill. The discharge was fed to the filter presses for dewatering. The results of this calibration using 4000 lbs of ball charge indicated the grinding mill was operated at a slurry concentration of 40 wt %. The average weight percent passing 125 microns was 43 % (target 40 %), so additional balls were charged for the next calibration.

Figure 5-2: Ball Mills

Two primary ball mill calibrations were made with a ball charge of 5000 lbs. A calibration was first done at a 3 t/h feed rate at a 50 wt % slurry in the mill. The objective of the test was to determine the product PSD (target grind of 28 mesh topsize), continue evaluation of the water flow calibrations, and calibrate a Marcy pulp density meter. The slurry concentration was increased from 40 to 50 wt % to evaluate the mill performance at the higher concentration. The actual slurry concentration was 55 wt % during the test. The average weight percent passing 125 microns (target grind) was 44 % (target 40 %).

The second primary mill calibration with 5000 lbs charge was made at a 3 t/h coal feed rate at a 40 wt % slurry concentration. The concentration was changed back to 40 wt % to reduce the impact of minor water feed fluctuations on the slurry concentration. The weigh belt feeder would operate in manual only, resulting in variations in the slurry concentration during the test. The slurry ranged from 35 to 52 wt %, with an average passing 125 microns of 48 wt %.

A weigh belt feeder manufacturing representative visited the site to check out and calibrate the feeder controller. A broken capacitor was found on one of the boards. This was corrected and the feeder checked out in automatic. The feeder appeared to be operating properly.

The primary mill ball charge was increased to 5500 lbs and another calibration test was conducted. The grinding objectives were to determine the PSD of the mill, with a target of 28 mesh topsize, d_{50} of 125 microns, and a slurry concentration of 40 wt %. Another objective was to operate the weigh belt feeder in the automatic mode, which had not been possible up to that time. The feeder operated well on automatic, but controlled the feed at a rate (5900-6000 lb/hr) slightly lower than the set point (6400 lb/hr). A set point of 6800 lb/hr controlled the rate at about 6500 lb/hr. The slurry sample indicated the 40 wt % target was obtained, with a d_{50} of 129-130 microns.

After completion of the primary mill calibration, the secondary mill was calibrated. A total ball charge of 9500 - 10,000 lbs was provided in the secondary mill, based on the manufacturer's recommendation. The exact weight could not be determined due to the quantity of balls initially present in the mill (about 300 - 500 lbs). A calibration run with the secondary mill was conducted. Target for the calibration was 100 mesh topsize with a d_{50} of 65 microns. Coal feed to the mill was 6400 lb/hr, with a 40 wt % slurry in the mill. Samples were taken of the mill discharge and coal feed. Analysis of product indicated that the target calibration for the mill had been achieved.

5.2.2 Startup and Calibration of Agglomeration Process

Calibration of Valves and Pumps

The CDTF has numerous manual valves and variable speed drive pumps used for flow control throughout the system. Although there are flowmeters on several of the process streams, accurate calibration of these valves and pumps was critical to ensure steady state operation, achieve target flow rates for material balances, and provide reproducible data. Procedures were established to allow reliable calibration of the valves and pumps over the flow ranges expected during Task 6.

For manual valves, the calibration involved measuring flow rates at specific valve settings by diverting the flow to a drum for weighing. Efforts were made to measure these flows as near to the process stream entry point as possible with a minimum of piping additions to most accurately simulate the pressure drops of actual operation. Several measurements were made at each setting to ascertain reproducibility, and the settings were checked periodically throughout Task 6 in case valves were inadvertently repositioned during shutdowns, upsets, etc. The manual valves which were used for flow control are listed below:

- o Process water to ball mills

- o Process water to primary mill discharge tank
- o Process water to secondary mill discharge tank
- o Process water to flotation cells
- o Process water to microagglomerate recovery tank
- o Hot water to colloid mill

Calibrating the pumps with variable speed drives involved the measurement of pump discharge flows over a range of motor speeds. The pumps were either centrifugal pumps (a) or internal gear positive displacement pumps with a built-in pressure relief valve (b). The pumps are listed below:

- o Primary Mill Discharge Pump (a)
- o Secondary Mill Discharge Pump (a)
- o Microagglomerate Pump (a)
- o Product Slurry Pump (a)
- o Diesel Binder Metering Pump to High Shear (b)
- o Diesel Binder Metering Pump to Low Shear (b)
- o Asphalt Binder Metering Pump to Low Shear (b)

The metering pump flows were measured as near to the process stream entry point as possible to most accurately simulate the pressure drops of actual operation. The product slurry pump flows were measured at the inlet to the particular dewatering equipment being tested. The other pump flows were measured at the pump discharge. Several measurements were made at each setting over the range of flows expected during operation to ascertain reproducibility, and the settings were checked periodically.

Filter Press Startup

After installation of the filter press system, a number of mechanical problems were found and corrected. The programmable logic controller for one of the two banks was corroded and was replaced. The inlet 3-way ball valves were taken apart and rebuilt to stop leakage. All the rollers on the filter system plate shifters were replaced. The packing on the hydraulic pistons of both the feed pumps was replaced. Problems were encountered with the plate shifter drive, requiring repair of a faulty clutch and correction of some electrical malfunctions. Once the filters were put into good operating condition, both banks of filters were started up and personnel were trained in the operation of the filters. The filter presses were used throughout the ball mill calibration tests to dewater the mill product for disposal.

Water Balance

Steady state was investigated in two flow paths. In the first water balance test water was added to the primary mill discharge tank, from where it was pumped to the tailings tank through the secondary mill tank, high shear mixer, and flotation cells. A concurrent path introduced water to the microagglomerate recovery tank, from which it was pumped to the tailings tank through the large low shear mixer, static sieve bend, and vibrating screen. The tailings tank slurry was pumped to the thickener, from which the water was sent back to the water delivery system. The available head from the thickener overflow to the clarified water surge tank was low, causing water to back up into the thickener. This condition did not interfere with the water balance test, but was detrimental to proper thickener operation.

To provide proper thickener operation, modifications were made to the water surge tank system into which the clarified water from the thickener discharges. A 3000 gallon surge tank was installed next to and below the existing water surge tank to increase the head drop between the thickener overflow and surge tanks, preventing the backing up of water in the thickener overflow trough and piping. In addition, the water storage capacity was increased, allowing better control of water inventory. A second water balance test was

conducted after completion of the modifications, with startup of the thickener at a flocculant concentration of two ppm in the thickener feed stream. This balance provided experience in startup and operation of the entire unit, including the thickener. Water clarification was good, but problems were encountered with the thickener underflow pump. The pump suction was backflushed and cleaned of heavily settled solids and construction waste, after which it operated well. A steady state water balance was achieved.

Asphalt Startup

When asphalt was delivered to the site and unloaded, a small amount of boilover occurred due to the presence of several inches of water in the storage tank. All the asphalt was contained in the dike and cleaned up. The asphalt supply system was then checked out. The tank heater would not keep the temperature hot enough to provide sufficient flow of asphalt. The heater set point was set at 220° F, just above the temperature range of 190° F suggested by the asphalt supplier. However, the asphalt itself would not heat up to that temperature, resulting in a temperature in the bottom of the tank of about 90 - 100° F. Since the asphalt metering pump suction comes off the bottom of the tank, asphalt flow could not be achieved. Initial discussions with the heater manufacturer indicated that the problem could be an incorrect type of overtemperature controller - the device that prevents the heating of the tank contents too much. A new overtemperature controller was obtained and installed, but did not appear to solve the problem. The set point of the heater was then increased to 250° F to increase the temperature at the bottom of the tank. The tank was allowed to heat up for several days, but the asphalt at the tank bottom continued to be too viscous to flow. A hot tap was made on the side of the tank about 3.5 ft above the original suction location, where the tank contents were at 235° F, to allow delivery of less viscous asphalt from this region of the tank to the pump suction. Asphalt flowed from this tap freely.

5.2.3 Startup Tests

First Startup Run with Diesel (Run T1)

Due to the problems with asphalt supply, startup Run T1 was conducted using diesel only as the binder in both the high and low shear vessels. The purpose of this run was to identify equipment problems and gain experience operating the entire plant. Since the ball mills had previously been operated successfully, the run focused on the testing of flotation cell operation, particularly adequate level control.

Coal was fed to the primary ball mill (28 mesh topsize product) at a 6400 lbs/hr feed rate. The mill was operated with a slurry concentration of 40 wt %. Slurry concentration was further diluted to 15 wt % solids prior to the high shear vessel. Diesel addition to the high shear was at 1 wt %, on a dry coal feed basis. The slurry was then sent to the flotation cells, which were operated at a solids concentration of 12 wt %. A polyglycol-based frothing agent (BETZ® M150 Flotation Frother) was used in the flotation cell rougher and scavengers. Flotation product was sent to the 1200 gallon low shear vessel, with an additional 15 wt % (dry coal feed basis) diesel introduced as a binder to the low shear vessel. The agglomerate product from low shear was fed to a combination of static sieve bend/vibrating screen for product dewatering prior to disposal in a large dumpster. The sieve bend had a 0.5 mm screen size. This size was used for all 28 mesh runs. Flotation cell and dewatering tailings were sent to a thickener for solids removal and water clarification. An anionic polymer emulsion (BETZ® CM 224) was used as a flocculant in the thickener. The thickener solids were dewatered in a plate and frame filter press. Water from both the thickener overflow and the filter press filtrate was recycled to the process. The pH of the circulating water had to be increased from time to time. This was done with batchwise addition to the recirculating water. The high shear vessel and flotation cells are shown in Figures 5-3 and 5-4, respectively.

The coal feed rate to the mills via the weigh belt feeder fluctuated from 6400 to 7100 lbs/hr during the run in the automatic mode of feeder operation. The weigh belt feeder

Figure 5-3: High Shear Vessel

Figure 5-4: Flotation Cells

control was switched to manual after about one hour of operation, resulting in more stable feed (6500 to 6900 lbs/hr). Coal was fed to the plant for slightly over two hours, after which the plant was shut down due to two trips of the high shear mixer. The flotation cells operated well, with relatively good level control. A number of minor maintenance items were noted for correction. Samples were taken throughout the system for evaluation of unit performance and stability.

Second Startup Run with Diesel (Run T2)

A second startup Run (T2) was conducted using diesel only as the binder to low shear. A colloid mill had been installed prior to the run to allow the production of binder emulsions. This run provided a chance to start up and operate the colloid mill for the first time, and to become more comfortable with startup and operation of the entire plant.

Coal was fed to the primary mill at a 3 t/h feed rate. Primary mill product was sent to the high shear vessel, where 1 wt % diesel was added. The high shear discharge was sent to the flotation cells, which were operated at a solids concentration of 12 wt %. Flotation cell product was sent to the 1200 gallon low shear vessel, with 12 wt % binder added to the process slurry in the feed piping to the low shear vessel. The binder was a 50/50 wt % diesel/water emulsion. Low shear product was dewatered using the static sieve bend/vibrating screen combination. Flotation and dewatering tailings were sent to the thickener/filter press system for solids removal and water recovery.

Coal feed to the mills was maintained at 3 t/h for the entire run. The high shear mixer continued to trip out intermittently during the run due to overheating, caused by the power draw. The power draw of the mixer was about 110 amps, with the trip set at 89 amps. This indicated that the rpm of the mixer was too high. A new sheave was ordered to allow a reduction of the rpm from 1650 to 1186. Samples were taken of the process streams for evaluation of unit operation.

First Startup Run with Asphalt (Run T3)

This run was the first with asphalt in the low shear binder, made possible with the hot tap at the asphalt tank. Although the high shear mixer trips had not been eliminated, the run was made to allow evaluation of unit operation with various asphalt concentrations in the binder. Problems with the in-line binder mixers, colloid mill and other equipment could then be identified. Asphalt feed was initially targeted at 6 lb/hr (50/50 wt % asphalt/diesel in binder), with the plan to increase to 9 lb/hr (75/25 wt % asphalt/diesel binder) partway through the run to evaluate the change in agglomerate appearance and size.

Coal feed was sent to the primary mill at a 3 t/h rate. The mill product was sent through the high shear vessel, where 1 wt % diesel was added, to the flotation cells. The flotation cells were operated at 12 wt % solids. Product from the cells was sent to the 1200 gallon low shear vessel. Binder was introduced to the slurry in the low shear feed piping at 12 wt %. The binder consisted of a 50/50 wt % asphalt/diesel blend, fed to the colloid mill at a 50/50 wt % binder/water concentration. The low shear product was dewatered via the static sieve bend/vibrating screen combination. Flotation and dewatering tailings were sent to the thickener and filter presses for solids removal and recovery of water.

Coal feed was maintained at the 3 t/h nominal rate throughout the run. At startup, the asphalt flow was measured and found to be only 5 lb/hr. The metering pump could not supply the binder flow required. However, the run was started to allow checks of the system with asphalt at the rates that could be achieved. During the run, the colloid mill product emulsion and low shear product did not appear to contain much asphalt, indicating that even the original 5 lbs/min rate was probably not being obtained as the run progressed. Also, the high shear mixer packing was smoking badly and the mixer continued to trip out frequently due to high amps. The run was stopped after only two hours of operation to prevent damage to the mixer.

After Run T3, the sheave for the high shear mixer impeller shaft was changed to reduce the rpm of the impellers from 1650 to 1186 to eliminate the high amp trips. The new

sheave dropped the power draw from 110 to 60 amps. No high shear mixer trips occurred for the remainder of Task 6 operation. The top and bottom packing at the mixer were also replaced at this time.

Due to the inadequate asphalt flow seen in Run T3, a larger asphalt pump motor was installed to increase asphalt delivery to the system. However, at the maximum flow capability of the new motor, only about 9 lbs/min could be achieved. Laboratory viscosity determinations of asphalt were made to pinpoint the temperature range required for adequate asphalt flow. The tests indicated that asphalt temperatures of about 300 to 320° F were required to reduce the viscosity to about 100 cP. The asphalt storage tank temperature was then increased further - to about 320° F - to decrease asphalt viscosity, and the asphalt pump was moved inside the diked area around the asphalt tank to reduce pressure drop in the suction piping to the pump.

After these changes had been made, the asphalt pump would not deliver any flow when operations continued. A new asphalt pump (same model type, with a mechanical seal instead of packing) was installed and put into operation. An initial surge of asphalt was observed downstream of the in-line mixers, but stopped after several minutes when the pump coupling became loose on the shaft. An inspection revealed that metal shavings from the asphalt tank hot tap had entered the pump suction. The asphalt metering pump is an internal gear positive displacement pump with a built-in pressure relief valve. The shavings had lodged between the gears and stopped the rotation of the head. The pump was pulled, the asphalt line exiting the tank flushed, the pump head cleaned, and the pump started again. A very good asphalt flow rate was obtained through the mixers - a flow of over 14 lbs/min at a variable speed pump controller setting of 30 Hz, which is 50 % of the motor speed. The pump which had been replaced was also found to have metal shavings in the pump head. These modifications solved the problems with asphalt delivery.

The instrumentation technicians began checking and calibrating the flowmeters for the oil and binder addition. The flowmeters did not calibrate well. Readings of the binder meters were taken every run, but because these did not correspond with timed flow rate measurements, the data is not reported in the Appendices.

5.3 Optimization of Operating Parameters

Upon completion of startup a number of runs were conducted to target the operating conditions required to produce agglomerates of suitable size for testing of the dewatering equipment. A summary of these runs is provided in Table 5-1.

Table 5-1

SUMMARY OF OPERATING RUNS 4 - 12

<u>Run</u>	<u>Coal Mesh</u>	<u>Binder Concentration (wt % dry coal)</u>	<u>Binder Composition, wt% (asphalt/diesel)</u>	<u>Solids wt % To</u>	
				<u>Flotation Cells</u>	<u>Low Shear</u>
4	28	12	50/50, 75/25	12	15
5	28	10	60/40	12	20
6	28	8	60/40	9	20
7	28	10,8	60/40, 80/20	9	20
8	28	9	60/40	9	20
9	100	12-15	60/40	9	20
10	100	11-12	60/40	9	20

For all runs:

Coal feed at 3 TPH (dry coal basis)

All ball mill solids = 40 wt %

High shear solids = 15 wt %

Emulsion water/binder ratio = 50/50 wt %

Low shear residence time = 21 minutes

5.3.1 Optimization with 28 Mesh Coal

First Asphalt Binder Run with 28 Mesh Coal (Run T4)

Once the asphalt pumping problems had been solved, the asphalt pump was calibrated at 6 and 9 lb/min flow rates in preparation for Run T4. The run objective was to test plant operation with asphalt in the binder and to evaluate the impact on product characteristics using different binder concentrations.

The run was conducted with 28 mesh coal (primary ball mill) at a 3 t/h dry coal feed rate. The mill slurry concentration was 40 wt % solids, which was reduced to 15 wt % prior to the high shear vessel. Diesel was added to the high shear at a rate of 1 wt %. The high shear product was reduced from 15 to 12 wt % solids at the flotation cell inlet. Flotation cell product was sent to the 1200 gallon low shear mixer. Binder was added to the process stream upstream of the low shear mixer, at a 12 wt % rate (dry coal feed basis). The binder was an emulsion from the colloid mill, which was fed a 50/50 wt % mixture of binder and hot water. The binder initially consisted of a 50/50 wt % asphalt/diesel blend. Low shear agglomerates were sent to the static sieve bend/vibrating screen for dewatering of the product. The low shear mixers are shown in Figure 5-5. Tailings were sent to the thickener and filter press system for water recovery and solids removal.

Initial asphalt and diesel feed to the colloid mill (and hence to low shear) was 6 lbs/min each. The system began producing a reasonable product (2-4 mm diameter), but appeared to contain too much binder. At this time the asphalt addition was reduced from 6 to 4.6 lbs/min, and the diesel was reduced from 6 to 5.1 lbs/min (a 47/53 wt % asphalt/diesel blend to the colloid mill) to observe the effect on product size and appearance. The product became significantly more sticky and appeared to contain more moisture, with a product size of about 3 mm diameter. The asphalt and diesel rates were then returned to 6 lbs/min each, as at the beginning of the test. The product appeared to improve, with a more consistent size (about 2-3 mm diameter), and was more difficult to crush by hand than the first product.

Figure 5-5: Low Shear Mixtures

The binder addition was next changed to 9 lbs/min asphalt and 3 lbs/min diesel (75/25 wt % ratio). The product became larger, about 3-4 mm in size, and significantly stickier than any of the previous products. One hour later the binder was returned to the original addition of 6 lbs/min each of asphalt and diesel. Plant operation continued for another hour before shut down because the product and refuse dumpsters were full. The binder flow was measured just prior to shutdown to verify the rates achieved with the metering pumps. The flow rate was 13.7 lbs/min (target: 12 lbs/min), indicating that the addition of binder was fairly consistent throughout the test. Samples were taken of process streams to allow evaluation of unit operation and stability.

Asphalt Optimization Run with 28 Mesh Grind (Run T5)

The objective of the test was to produce an agglomerate somewhat smaller than that of Run T4. Water addition to the microagglomerate tank used in previous runs was eliminated for this test to increase the low shear slurry solids concentration from about 15 to 20 wt %. The results of Run T4 had indicated that the flotation product was consistently 20 wt %, which was the target concentration. Addition of water to the microagglomerate tank had diluted the low shear slurry to about 12-16 wt %.

The run conditions were 3 t/h coal feed with 40 wt % slurry in the primary mill, for a 28 mesh grind. Diesel addition to the high shear mixer was 1 wt %. The flotation cells were operated at a solids concentration of 12 wt %. Flotation cell product was sent to the 1200 gallon low shear vessel. Binder emulsion was added to the 1200 gallon low shear vessel feed. The asphalt and diesel rates to low shear were 6 and 4 lbs/min (60/40 wt %ratio), respectively, for a total oil addition of 10 wt % (dry coal feed basis). This was a reduction from the previous run where 12 wt % asphalt/diesel was used. In that run the asphalt appeared to blind the screen, reducing the dewatering efficiency of the screen. The product was dewatered with the static sieve bend/vibrating screen combination. Tailings were sent to the thickener and filter presses for processing.

About 40 minutes after coal feed began the water flow from the head tank stopped. Investigation revealed that the water inventory in the system had been depleted, and that the coal feed to the ball mill had plugged the feed chute. Coal feed was stopped to clear the chute, and the water level in the system had to be replenished. About one hour after coal feed was resumed, the product became a recognizable agglomerate of about 0.5 mm. After about 1.5 hours the product had obtained a size of about 0.5 to 1.0 mm. During the test, the flotation cell levels became difficult to control. The level controllers appeared to be leaking air at the tube that senses liquid level in the flotation cells. Adjustments were made to the levels throughout the test to correct for level fluctuations. In addition, the entire flotation cell feed was fed first to the right bank, then to the left bank in an attempt to line out flotation. Frother rates were reduced from those used in Run T4 due to the excessive buildup of floating material in the tailings system. As the test progressed, the vibrating screen product became larger and larger, and also became stickier. The asphalt and diesel rates were not changed. The product finally began to cluster. Representative samples were taken throughout the system. During the sampling, significant froth buildup was observed in the microagglomerate tank. This floating material was high in solids concentration. Solids had been building up in the microagglomerate tank since the beginning of the run, probably due to the lack of water addition to the tank. The test was ended at that time, and the system was shut down and purged.

First Run with Binder Contact Vessel, 28 Mesh Coal (Run T6)

Prior to Run T6, the flotation cell level controllers were checked for air tightness and repaired. Run T6 was the first run which used a binder contact vessel for the introduction of binder to the flotation cell product, with mixing prior to low shear. The total binder addition to low shear was reduced to evaluate the impact of lower asphalt levels in the product on the dewatering performance of the vibrating screen, which had been blinding in previous runs. This run was also the first which operated with both low shear vessels in series, with the 1200 gallon vessel upstream of the 800 gallon vessel.

Coal feed began at a 3 t/h rate at 28 mesh grind. Diesel addition to high shear was 1 wt %, with high shear solids at 15 wt %. Microagglomerate recovery was done via flotation, with a reduction in flotation solids concentration from the previous 12 wt % level to 9 wt %. Flotation cell product was pumped through the binder contact vessel to the low shear vessels. Binder addition to low shear was 8 wt %, on a dry coal feed basis, with a 60/40 wt % asphalt/diesel split to the colloid mill. About 70 % of the binder was added via the binder contact vessel, while the remaining 30 % was added directly to the line feeding the first (1200 gal) low shear vessel. Low shear product was sent to the static sieve bend and vibrating screen for dewatering. Tailings were processed via the thickener and filter presses.

No major problems occurred with operation of the low shear vessels in series. There was some leakage at the shaft of the first vessel, which has no shaft seal, but this did not affect steady state operation of the plant. The total residence time in low shear was about 40 minutes. During the run, operation of the flotation cell level controllers was good. Modifications had been made to two of the level controllers, two of the flotation cell bubble tubes were replaced with new tubes (left cells), and the response time of the right cells had been adjusted to allow better level control within the flotation cells. Flotation cell operation appeared to achieve steady state, with very little coal loss to tailings. The dewatering performance of the sieve bend was good, as in previous runs. The vibrating screen performance was much better at the lower binder concentrations, with no significant blinding of the screen. The product appeared to be approximately 1 mm topsize. Operating data and laboratory samples were taken throughout the run.

Prior to Run T7, several changes were made to the system piping to improve system operability. The tailings tank mixer was moved to the microagglomerate recovery tank to reduce the accumulation of froth. Previous runs had to be curtailed due to solids buildup at this point. The filter press filtrate pump discharge was rerouted directly to the clarified water surge tank, bypassing the thickener to reduce the flow to the thickener and recirculate water to the system quicker. The process sump pump was piped directly to

the filter feed tank, reducing the excessive amount of froth and solids fed to the tailings tank and thickener by allowing immediate removal of the solids.

Operation at Higher Binder Asphalt Content with 28 Mesh Coal (Run T7)

Run T7 was conducted with an 80/20 wt % asphalt/diesel blend in the binder to low shear. This would allow evaluation of agglomeration performance at higher asphalt concentrations, and provide longer, smoother operation due to the changes made prior to the run.

Coal feed was begun at a rate of 3 t/h to the primary ball mill (28 mesh grind). High shear operated at 15 wt % solids with a diesel addition of 1 wt %. Flotation solids was 9 wt %. No frother was added to the roughers, and the minimum frother addition possible with the frother metering pumps was made to the scavengers. Flotation cell product was sent to both low shear mixers operated in series, at 20 wt % solids. Binder addition to low shear was made in both the binder contact vessel (about 70 % of the binder flow) and the piping directly upstream of the first low shear vessel (about 30 % of the binder flow), the 1200 gallon vessel. The binder was added at an 8 wt % (dry coal basis) rate. The binder consisted of an 80/20 wt % split of asphalt/diesel. The colloid mill gap was set at 1/1000 inch, the gap used throughout the remainder of Task 6. Earlier runs had used gaps ranging from 4/1000 to 1/1000 inch, until it was determined that the mill would operate at those gaps with no difficulties. No operating problems occurred at 1/1000 inch, so that setting was chosen for subsequent runs because the narrower gap produced a finer emulsion. The static sieve bend deck size was 0.5 mm. Agglomerates were dewatered via the static sieve bend and vibrating screen. Tailings from flotation, the sieve bend, and the vibrating screen were processed through the thickener and filter press system.

The plant was operated for 1.5 hours at the initial binder concentration, after which it was changed to a 10 wt % binder addition with a 60/40 wt % asphalt/diesel blend. The run continued for another two hours, then was stopped due to the lack of space in the

product dumpsters. The product agglomerates were about 1 mm in size at the end of the run.

The mixer in the microagglomerate recovery tank helped reduce the accumulation of solids, but did not eliminate the problem. Froth buildup on top of the tank had to be sprayed periodically with water and the tank contents stirred manually to keep the solids in suspension so they would exit from the tank. The diverting of the sump to the filter press feed tank improved the operation of the thickener by reducing the loading of floating solids processed there, but resulted in the overloading of the filter press system filtrate pump. This pump recycles water to the water surge tanks, but the capacity could not keep up with the combined flow of the thickener and sump pumps, resulting in the overflow of the filtrate tank periodically as the water inventory surged through the process. This water flowed back to the sump across the pad. Although this did not interfere with plant operation or performance, it was a nuisance during operation when the sump backed up onto the pad from time to time. Also, the water was reprocessed over and over through the sump and filter press system, instead of being returned immediately to the water supply tanks, increasing the loading on those systems.

Final Binder Optimization Run with 28 Mesh Coal (Run T8)

Based on the knowledge and experience of the previous runs, a final 28 mesh run (Run T8) was made at a binder addition rate of 9 wt % to low shear. The objective was to operate as long as possible (limited by the capacity of the two product dumpsters) at steady state.

Coal feed was begun at 3 t/h to the primary mill, with high shear operated at 15 wt % solids and 1 wt % diesel addition. The flotation cells were operated at 9 wt % solids. Both low shear vessels were used, with the 1200 gallon vessel first in series. Low shear was operated at a 20 wt % solids concentration, directly from the flotation cell product. Binder was added to both the binder contact vessel (70 %) and the 1200 gallon low shear mixer (30 %), at the total target rate of 9 wt % of 60/40 wt % asphalt/diesel mixture.

Agglomerate product was dewatered via the static sieve bend and vibrating screen. All tailings were processed in the thickener and filter press system.

The run was interrupted after about 20 minutes of operation due to plugging in the coal feed chute. The water supply had temporarily dropped due to system surges. The coal feed was restarted in about 30 minutes. No further system upsets were experienced for the duration of the run, which continued another 4.5 hours. The ball mill and high shear mixer feed rates (6400 lbs/hr coal and 76 gpm slurry flow, respectively) were both near the run targets of 6520 lbs/hr and 77 gpm throughout the run, indicating good steady state conditions. The product agglomerate had a d_{50} of 0.5 mm and a topsize of about 1 mm. Binder addition was maintained at 9 wt % throughout the run.

This run provided steady state operation of the process with 28 mesh coal, and completed the optimization tests for 28 mesh grinds. The binder addition of 9 wt % (60/40 wt % asphalt/diesel) appeared to be the amount required for the production of agglomerates of about 0.5 to 1.0 mm diameter.

5.3.2 Optimization with 100 Mesh Coal

First Run with 100 Mesh Coal (Run T9)

Once the runs with 28 mesh coal had been completed, runs with 100 mesh grind coal were conducted to target the binder ranges needed for formation of agglomerates of suitable size for dewatering tests. The first 100 mesh grind run (T9) was made to evaluate flotation performance with the finer grind, quantify the binder addition required to produce agglomerates of suitable size for dewatering tests, and identify any differences in unit operation (tailings and thickener loading, vibrating screen performance, filter press operability).

Coal was fed to the secondary ball mill at a 3 t/h rate (dry coal basis) to produce a 40 wt % slurry of 100 mesh coal. Diesel was added to the high shear mixer at a rate of 1

wt %, with a 15 wt % slurry. The flotation cells were operated at a solids content of 9 wt %, with no frother in the roughers and the minimum allowed by the metering pumps in the scavengers. Product from the flotation cells, at a 20 wt % solids concentration, was sent to both low shear vessels, which were operated in series. Binder was added at a 15 wt % rate, with a 60/40 wt % asphalt/diesel blend. The binder flow was split between the binder contact vessel and the 1200 gallon low shear mixer at 70 and 30 %, respectively. The 1200 gallon vessel was first in series. Low shear product was dewatered via the static sieve bend and vibrating screen. The sieve bend and vibrating screen are shown in Figure 5-6. The sieve bend screen was changed from a 0.5 mm size to a 0.33 mm size for the 100 mesh run. Tailings from the process were pumped to the thickener and filter press system for solids removal.

About 1.25 hours after the run was started the coal feed chute plugged due to a momentary loss of water to the mill. Coal feed was resumed in about 20 minutes and remained constant at 6450 lbs/hr for the remainder of the run. While the unit was off feed the binder flows were not cut back or cut off, resulting in excessive binder dosages to low shear, particularly in the 1200 gallon low shear mixer -- in which a total of 15 wt % binder was being added. This resulted in a product of about 2-3 mm in size, which contained too much oil. The asphalt and diesel rates were cut to 43 % of the initial flow for forty minutes in order to assist the purging of these upset agglomerates from the system. The binder rates were then returned to target conditions after another hour of operation due to the dry appearance of the product agglomerates. The product oil content appeared to increase thereafter, resulting in a stickier product. At that time the binder was cut from 15 to 12 wt %. The agglomerate product continued to grow in size - to about 4-6 mm - but became dry again. The run was concluded one hour after the binder rate reduction due to the product quality and full dumpsters. The run duration was 4.5 hours, including the 20 minute outage caused by the coal feed chute pluggage.

The changes in binder additions made to obtain a consistent product appearance did not allow the unit to achieve true steady state, but did provide some baseline data from which

Figure 5-6: Sieve Bend and Vibrating Screen

to plan the subsequent 100 mesh runs. The 0.33 mm static sieve bend did not provide dewatering of the low shear product as well as the 0.5 mm screen. The finer coal resulted in an increase in solids in the tailings from the sieve bend and vibrating screen, creating a significant quantity of floating material in the thickener. These solids would not settle, and were very difficult to remove via the thickener scum trough. This trough allows removal of the floating scum via a rotating scraper, which pushes the floating material into the trough for blowdown. The solids loading in the thickener was so high that continual manual assistance had to be supplied throughout the run to keep the thickener clarified water quality at an acceptable level.

Final Binder Optimization Run with 100 Mesh Coal (Run T10)

The purpose of Run T10 was to achieve steady state operation while producing an agglomerate of about 2 mm in diameter. This product would then allow testing of the dewatering equipment.

The run began with a 3 t/h coal feed rate to the secondary mill at a 40 wt % slurry in the mill. Diesel addition to the high shear mixer was set at 2 wt %, on a dry coal feed basis, with a high shear feed of 15 wt % solids. The higher diesel addition was used due to the finer grind of the coal. Flotation cell feed was kept at 9 wt % solids. Both low shear mixers were operated in series, with the 1200 gallon vessel feeding the 800 gallon vessel. A binder of 60/40 wt % asphalt/diesel (50 wt % oil in the colloid mill) was added at an initial target rate of 12 wt % (dry coal basis). The binder was fed to the binder contact vessel and the 1200 gallon low shear mixer at a 70/30 % split. Low shear product dewatering was done via the static sieve bend and vibrating screen. The initial static sieve bend screen size was 0.33 mm. Tailings were fed to the thickener for settling of the solids, which were pumped to the plate and frame filter system, while the clarified water was recovered into the water surge tanks.

When the run began the coal in the 3 ton surge bin was too wet to feed onto the weigh belt feeder, requiring manual assistance via hammering on the side of the bin, as well as

rodding in the top of the bin. As a result, coal feed was erratic for the first couple of hours of the run, until the wet coal had been fed to the mills. An operator was stationed at the bin throughout the run to ensure coal feed was uninterrupted. The coal feed chute to the secondary ball mill plugged about 45 minutes after startup. This was caused by the high water content of the coal coming off the end of the weigh belt feeder. Coal feed to the secondary mill was interrupted for about 20 minutes. Asphalt and diesel feed rates to the low shear system were reduced from 7.2 and 4.8 lb/min each to 1.0 and 0.3 lb/min each during the loss of coal feed to prevent overdosing in the low shear vessels. These flows were returned to the target conditions after coal feed to the system was resumed.

Once the system had stabilized, it was observed that the 0.33 mm sieve screen in the static sieve bend was too small to provide adequate dewatering of the low shear product. The screen was switched on line from 0.33 to 0.5 mm by feeding the 800 gallon low shear vessel to the tailings tank for about 5 minutes. The screen change was beneficial to the product dewatering.

About an hour after the screen change, the filter press feed pumps became plugged due to the accumulation of solids in the pump casing over the previous runs. The filter feed tank filled, and recycle of system water from the filtrate return tank was delayed. This resulted in an unexpected loss in water flow at the head tank, and coal feed was interrupted for about 30 minutes due to loss of water flow.

The binder addition to low shear was reduced from 12 to 11 wt % (four hours after startup) because the product appeared to be too large. System disruptions had led to overdosing of the binder to low shear, producing agglomerates of about 2 - 3 mm in size. The run continued for two more hours, with the product becoming more consistent and no longer increasing in size. Coal feed to the system continued until the 3 ton surge bin was empty so a vibrator mount could be welded onto the side of the bin. This vibrator would help prevent plugging of coal in the bottom of the hopper. Samples were taken at the coal feed system, flotation cells, and low shear system per normal procedures. In

addition, low shear and vibrating screen product samples were taken regularly throughout the run to monitor changes in product appearance.

5.4 Mechanical Dewatering Tests

A major objective of the component development test program was to produce agglomerates at the pilot plant scale for evaluation of dewatering techniques for both product and refuse. Testing of several types of equipment was conducted to provide sufficient information on the dewatering characteristics of the product agglomerates and refuse. The results of these tests would provide the data required to select appropriate equipment for use in later phases of the project. The CDTF focused on the mechanical dewatering of products from the diesel process. The equipment selected for operation during component development were:

- o Product dewatering equipment
  - Sieve bend/vibrating screen
  - Screen bowl centrifuge
  - Horizontal belt vacuum filter
  - Plate and frame filter press
- o Refuse dewatering equipment
  - Plate and frame filter press
  - Pressure belt filter (vendor tests)

Prior to the beginning of the dewatering evaluation tests, a vibrator was installed on both the 24 ton and three ton coal hoppers, with appropriate controls mounted at the weigh belt feeder control station, to eliminate the plugging of coal from these vessels. Two flotation cell blower motors were pulled for replacement of the top and bottom bearings. A pipe was installed from the 1200 gallon low shear vessel to the agglomerate product

tank to allow feed of low shear slurry to the various dewatering equipment being tested. The primary mill tank mixer was moved to the agglomerate product tank.

5.4.1 Evaluation of Dewatering Equipment with Small Agglomerates

Test runs were conducted at both 3 and 6 wt % binder to low shear to evaluate the performance of each dewatering device with small agglomerates. A summary of these runs is given below in Table 5-2.

Table 5-2

MECHANICAL DEWATERING TESTS WITH SMALL AGGLOMERATES

<u>Run</u>	<u>Coal Mesh</u>	<u>Dewatering Equipment Tested</u>	<u>Binder Concentration (wt % dry coal)</u>
11	100	Filter	3, 6
12	100	Filter, Centrifuge	3
13	100	Centrifuge	3
14	100	Filter, Centrifuge	6
15	28	Filter, Centrifuge	6
16	28	Filter, Centrifuge, Belt	3
17	28	Belt	6
18	28	Belt	3, 6

For all runs:

Coal feed at 3 TPH (dry coal basis)

All ball mill solids = 40 wt %

High shear solids = 15 wt %

Flotation cell solids = 9 wt %

Binder composition = 60/40 wt % AC-5 asphalt/diesel

Emulsion water/binder ratio = 50/50 wt %

Low shear residence time = 21 minutes

Filter Press at 6 % Binder with 100 Mesh Coal (Run T11)

Run T11 was conducted utilizing 6 and 3 wt % binder to low shear at 100 mesh. The objective of the run was to evaluate the dewatering performance of the plate and frame

filter press at the above binder addition. The plate and frame filter press system is shown in Figure 5-7.

The secondary mill was operated at a 3 t/h feed rate with 45 wt % solids. The high shear vessel was fed at 15 wt % solids, with 1.5 wt % diesel. The flotation cells were fed 9 wt % solids. Only the 1200 gallon low shear vessel was used. An initial binder oil concentration of 6 wt % was added in the binder contact vessel, but no binder was added directly to the low shear vessel. The static sieve bend size used was 0.5 mm. The low shear solids feed target was set at 22 wt % solids. Low shear product flowed simultaneously to both the agglomerate product tank and the static sieve bend/vibrating screen. The entire process flow was too large for the product pump to handle.

Coal feed was smooth throughout the run, with no upsets or feed interruptions. There were some problems with coal plugging in the crusher inlet chute, but this did not affect the run performance. The coal feed rate averaged 6350 lbs/hr over the duration of the run, at a nominal 3 t/h dry coal target. The feed rate to high shear averaged 74.7 gpm, at a target of about 76.0 gpm. The microagglomerate pump averaged 64.9 gpm, at a target of about 43.8 gpm. It was uncertain if the large difference in microagglomerate flows was due to flowmeter errors or water addition to the microagglomerate tank for prevention of solids buildup.

The product contained a significant amount of water. The sieve bend and vibrating screen were not able to dewater the agglomerates well, resulting in a significant amount of water in the product dumpsters. The sieve bend tailings contained product, as was indicated by the black color of the tailings, and the extremely large amount of material floating in the thickener. The solids floating in the thickener had to be continually (and manually) purged from the thickener via the sludge blowdown trough in order to maintain water clarity. This was very manual intensive due to the thick nature of the solids. Also, the solids had to be shoveled out of the center thickener section (where the feed from the tailings tank enters) several times.

Figure 5-7: Plate and Frame Filter Press System

The product was capable of being handled by the portable belt conveyor. Once steady state conditions had been obtained with 6 wt % binder, the product was sent to the plate and frame filter press via the agglomerate product tank and pump. All normal flows to the filter feed tank had been stopped and the tank purged with product for about 15 minutes while feeding one bank of filter plates. Filter feed was then switched to the other bank of plates and the product dewatered. The pumps were allowed to pump for 20 minutes, before the filtrate flow from the bank had dropped to a very small rate. The filters were then cycled through normal dumping and five samples taken down the length of the plates to allow comparison of the cake through the bank to determine if additional "deadheading" of the pumps was necessary to achieve a cake of suitable moisture. (More time was not allowed during this test due to the volume of material in the sump and thickener which had to be filtered). The sample appearance indicated that the cake near the inlet to the bank, which had seen higher pressure for a longer time, was the driest. During the next test additional filtering time was allowed to obtain a dryer cake.

After the 6 wt % conditions were achieved, the binder was changed to a 3 wt % addition of 60/40 wt % asphalt/diesel. The product became more of a slurry. The goal was to send the 3 wt % product to the filter presses, but the run had to be stopped due to lack of product and filter dumpster capacity.

Centrifuge and Filter Press at 3 % Binder with 100 Mesh Coal (Run T12)

Run T12 was performed with 100 mesh grind coal at a binder concentration of 3 wt % in low shear. The run objectives were to achieve steady state operation with 3 wt % binder, then test the product dewatering performance of the screen bowl centrifuge and the plate and frame filter press. If time permitted, the binder would be changed to 6 wt % to allow dewatering tests with both the centrifuge and filter press. The screen bowl centrifuge is shown in Figure 5-8.

The secondary mill discharge was 40 wt % solids. Water was added to provide a high shear feed of 15 wt % solids, and 1.5 wt % diesel was added to high shear. The flotation

Figure 5-8: Screen Bowl Centrifuge

cells were fed at 9 wt % solids. Flotation cell product was pumped to the 1200 gallon low shear mixer through the binder contact vessel, where a 3 wt %, 60/40 wt % asphalt/diesel mixture was added, on a dry coal feed basis. No binder was added directly to low shear. Only the 1200 gallon low shear mixer was used.

Coal feed was maintained at a target of 6500 lbs/hr, with an actual feed throughout the run of about 6560 lbs/hr. There were no coal feed upsets or interruptions during the run. Low shear product was fed to both the static sieve bend and the agglomerate product tank throughout the run. This split was about 50/50. The static sieve bend size was 0.5 mm. The agglomerate tank material was pumped to the centrifuge as soon as a consistent slurry was available to test the operation of the centrifuge and minimize the water in the product dumpsters. Remaining low shear product was sent to the combination sieve bend and vibrating screen.

Once steady state was achieved at 3 wt %, flow rate measurements and samples were taken at the screen bowl centrifuge. After the centrifuge measurements and samples were taken, the agglomerate tank flow was switched to the filter feed tank to purge the tank for filter press tests. Once purging had been achieved, the slurry was pumped to a clean bank of plates for dewatering. After about 20 minutes the filtrate flow had dropped to a negligible amount, but the filter feed pumps were allowed to deadhead for an additional 35 - 40 minutes, at which time no water was exiting the filter, to ensure the driest cake possible with the system. Five samples of the cake were taken down the length of the bank to determine changes within the batch. Since the large bank of filters was used (compared to the small bank in Run T11), only the plates corresponding to a similar number as the small bank were sampled to allow comparison from bank to bank.

After the filter press was tested at 3 wt %, the binder was increased to 6 wt % and the unit allowed to achieve steady state. While this was occurring, cleanup of the thickener was continued, as was the filtering of the sump and thickener underflow material. Meanwhile, solids accumulated in the centrifuge discharge chute, backing up and causing

the centrifuge to trip off. The centrifuge was restarted, but smoke was visible in the unit control panel. The run was stopped to allow maintenance to investigate the problem, and allow cleanup of the pad, sump and thickener. Samples of both the centrifuge and filter press tests were taken to the laboratory for evaluation. In addition, routine samples were taken throughout the run.

Centrifuge at 3 % Binder with 100 Mesh Coal (Run T13)

The objective of Run T13 was to evaluate the dewatering performance of the screen bowl centrifuge with an agglomerate product produced from 100 mesh coal with 3 and 6 wt % binder to low shear. However, a system upset due to a power failure lengthened the duration of the 3 wt % tests, so that no time was available for testing the 6 wt % binder conditions.

Coal was fed to the secondary mill at a 3 t/h rate, with the mill operating at 40 wt % solids. The high shear mixer was operated at 15 wt % solids with a diesel addition of 1.5 wt %. The flotation cells were operated at a solids concentration of 9 wt %. Only the 1200 gallon low shear vessel was used. Binder was added via the binder contact vessel at a rate of 3 wt % (dry coal) 60/40 wt % asphalt/diesel. The low shear product was sent to both the product agglomerate tank and the sieve bend/vibrating screen.

A system upset occurred 30 minutes after coal feed was begun. The unit was started back up in about 30 minutes, and the system achieved steady state so as to allow testing of the centrifuge. The first tests were conducted with a screen weir depth of three out of four plugs installed. Three different centrifuge feed rates were tested, with a product pump speed of 60, 40, and 30 Hz, corresponding to flow rates of 400, 185, and 100 lbs per min, respectively of slurry (slurry solids concentration: 20 wt %). Flow rate measurements of all filtrates and the solids discharge were taken under each feed rate, as well as samples of each. The centrifuge was then shut down to allow the removal of two more plugs to allow testing with a lower bowl weir depth of one out of four plugs. A power failure occurred 3.75 hours after startup, which shut down all unit equipment and

upset steady state. The centrifuge tests at the first set of conditions had been completed. There were heavy thunderstorms for the latter part of the morning. Coal feed was restarted, and the unit allowed to obtain steady state once again. After steady state had been achieved, flow rate measurements and samples with the lower bowl depth were taken at 60, 40, and 30 Hz pump speeds, similar to the earlier tests during the run. The unit was shut down upon completion of the second set of centrifuge tests due to the full product and filter dumpsters, so testing of the centrifuge at 6 wt % binder was not possible. Routine samples of the coal feed and flotation cells were taken during the run.

Centrifuge and Filter Press at 6 % Binder with 100 Mesh Coal (Run T14)

Run T14 was conducted to evaluate the dewatering performance of the screen bowl centrifuge with 100 mesh small agglomerates produced with 6 wt % binder to low shear, and to repeat the plate and frame test at the same conditions.

Coal feed to the secondary ball mill was maintained at 3 t/h throughout the run. The high shear mixer was operated at 15 wt % solids, with 1.5 wt % diesel addition to high shear. The flotation cells were operated at 9 wt % solids. Only the 1200 gallon low shear vessel was used, with binder addition via the binder contact vessel. The binder was 6 wt % (dry coal) 60/40 wt % asphalt/diesel. The product from low shear was sent to both the product agglomerate tank and the sieve bend/vibrating screen.

There were no system upsets during the run. The tests began with 3 of 4 plugs installed in the bowl of the centrifuge. Three different feed rates to the centrifuge were tested: 60, 40, and 30 Hz (400, 185, and 100 lb/min). Flow rate measurements and samples were taken of filtrates and solid product. Upon completion of the first set of tests, one set of flow rates and samples were taken with one out of four plugs installed.

Low shear product was next diverted to the plate and frame filter press, where the filter feed pumps were allowed to deadhead for 30 minutes after filtrate was no longer visibly discharging from the filter. This allowed a repeat of the previous 100 mesh, 6 wt % binder

test with the plate and frame, where the pumps were not allowed to deadhead. Samples were taken of filter cake down the length of the bank. Routine coal feed and flotation cell samples were taken for evaluation of unit performance.

Centrifuge and Filter Press at 6 % Binder with 28 Mesh Coal (Run T15)

Run T15 was conducted at a 3 t/h feed rate with 28 mesh coal at a 6 wt % binder to low shear to allow evaluation of the centrifuge and filter press at those conditions.

The high shear mixer was operated at a 15 wt % solids concentration, with 1 wt % diesel addition. The flotation cell solids were operated at 9 wt %. Only the 1200 gallon low shear vessel was used. Binder was added to the 1200 gallon low shear vessel via the binder contact vessel at a 6 wt % (dry coal) 60/40 wt % asphalt/diesel ratio. The low shear product was sent to both the product agglomerate tank and the sieve bend/vibrating screen.

Coal feed was started and the unit allowed to achieve steady state. Tests were then made using the screen bowl centrifuge. The centrifuge used a weir depth of 3 of 4 plugs. Three feed rates to the centrifuge were tested: 60, 40, and 30 Hz pump speeds (400, 185 and 100 lbs/min). Flow rate measurements were taken of all filtrates and the solids discharge, and samples of these streams were obtained.

Upon completion of the centrifuge tests, the product was diverted to the plate and frame filter press. The filters were allowed to deadhead for about 30 minutes after no filtrate discharge was visible. The cake was then dumped and sampled down the length of the bank. The unit was then taken off feed and shutdown and cleanup began. In addition to the dewatering samples, routine coal feed and flotation cell samples were taken.

Centrifuge, Vacuum Belt, and Filter Press at 3 % Binder with 28 Mesh Coal (Run T16)

Run T16 was conducted at a 3 t/h coal feed rate with 28 mesh grind coal. The purpose of this run was to determine the dewatering performance of the screen bowl centrifuge,

horizontal belt vacuum filter, and the plate and frame filter press with 3 wt % binder to low shear. The horizontal belt vacuum filter is shown in Figure 5-9.

The high shear diesel addition was 1 wt %, with flotation cell solids concentration at 9 wt %. Only the 1200 gallon low shear vessel was used, with a binder addition of 3 wt % (60/40 wt % asphalt/diesel). All the binder was added via the binder contact vessel. The low shear product was sent to both the product tank and the sieve bend/vibrating screen.

The first dewatering test was made with the centrifuge. Three different flow rates were fed to the unit, which had three out of four plugs installed for weir level within the bowl. Flow rate measurements and samples were taken at each feed pump setting of 60, 40, and 30 Hz. Samples included one centrifuge feed sample, as well as centrate, screen wash no. 1 and 2, and product for all three feed rates. The centrifuge rpm was 2050.

After the centrifuge tests were complete, the horizontal belt vacuum filter was tested. Three different belt speeds were tested, with two feed rates at each belt speed. The cake thickness and filtrate flow rates were measured, and the feed pump speed (Hz) noted for material balance purposes. Samples were taken of the cake discharge, filtrate 1 (feed end of belt), and filtrate 2. Since the agglomeration system was at steady state, only one sample was taken of the low shear feed to the unit to represent all feed streams during the tests.

Upon completion of the horizontal belt vacuum tests, the product was sent to a cleaned bank of plate and frame filter presses. The filtrate flow dropped to about zero after about 30 minutes, and the filter pump was deadheaded for another 35 minutes to achieve as dry a cake as possible. No filtrate was flowing at this time. A filtrate sample was collected near the end of the visible flow, and five filter press cake samples were taken down the length of the bank. The driest cake was present at the feed end of the bank of plates.

Figure 5-9: Horizontal Belt Vacuum Filter

Vacuum Belt at 6 % Binder with 28 Mesh Coal (Run T17)

Run T17 was conducted with 28 mesh coal at a 6 wt % binder addition to low shear to test the dewatering performance of the horizontal belt vacuum filter under those conditions.

The unit was started up at a 3 t/h coal feed rate with 15 wt % solids to high shear, and a 1 wt % diesel addition to high shear. Flotation cell solids were 9 wt %. The 6 wt % binder was added to low shear at a 60/40 wt % asphalt/diesel ratio using the binder contact vessel. Only the 1200 gallon low shear vessel was used.

No coal feed upsets were experienced at any time during the run. After steady state was achieved the vacuum belt tests began. The product pump feeding the belt was maintained at 40 Hz throughout the run. Four belt speeds were used: 7.8, 12.0, 20.0, and 22.5 ft/min. Flow rate measurements of filtrates and solids product were made, with samples taken of each stream. Also, the product agglomerate pump was calibrated over a speed range from 30 to 60 Hz. Routine samples were taken of coal feed and flotation cells, and all samples taken to the laboratory for analyses. The run was concluded after all scheduled tests were completed, and the unit cleaned in preparation for the next run.

Vacuum Belt at 3 and 6 % Binder with 28 Mesh Coal (Run T18)

The objectives of Run T18 were to evaluate the dewatering performance of the horizontal belt vacuum filter with 100 mesh coal agglomerates prepared with both 3 and 6 wt % binder to low shear.

Coal feed was maintained at 3 t/h to the secondary ball mill. High shear feed contained 15 wt % solids, and 1.5 wt % diesel was added to high shear. Flotation cells were operated at a 9 wt % solids concentration. Binder was added via the binder contact vessel, at an initial rate of 6 wt %, 60/40 wt % asphalt/diesel. Only the 1200 gallon low shear vessel was used, discharging to both the product agglomerate tank and the sieve bend/vibrating screen. The product was pumped to the horizontal belt vacuum filter at

a pump speed of 40 Hz (about 185 lb/min slurry rate) throughout the run.

The unit was operated until steady state was obtained, and the first set of belt tests were performed. Four belt speeds were tested at the 6 wt % binder addition rate: 20.0, 13.8, 10.6, and 6.7 ft/min. Filtrate and solids product flow rates were measured, and samples taken of the product. The binder concentration was then changed from 6 to 3 wt %, and allowed to reach steady state under the new conditions. Various belt speeds were tested, also at a pump speed of 40 Hz: 25.7, 13.8, and 9.5 ft/min. Appropriate flow rate measurements and samples were taken. Routine coal feed and flotation cell samples were obtained. All the samples were taken to the laboratory for analysis. The unit was shut down due to the full product dumpsters.

Problems were encountered with the water supply to the belt system and solids buildup under the belt at the discharge end from time to time during the test. The solids were washed and the water supply check valve was knocked for a few seconds, and the unit lined back out. The solids buildup contributed to blinding of the cloth because the scraper would not perform properly, and was most likely caused by the accumulation of solids in the discharge chute (which was very manual intensive). The water supply problem resulted in inadequate spray at the nozzles at the belt for short periods of time.

The product appeared to contain more moisture with 100 mesh coal as compared to 28 mesh. Also, the 3 wt % binder product during Run T18 appeared to contain more moisture than the 6 wt % binder product.

5.4.2   Production of Product for Pelletization

Products with 100 Mesh Coal at Low Asphalt Content (Run T19)

The objectives of Run T19 were to produce a horizontal belt product with 100 mesh coal at both 1 and 3 wt % asphalt in low shear and collect 2 drums of each for pelletization tests. Upon completion, a test with 3 wt % diesel to low shear would be conducted to

evaluate the effect of diesel only on product moisture content.

Coal feed to the secondary mill was maintained at 3 t/h throughout the run. The high shear mixer was operated at 15 wt % solids, with a diesel addition rate of 1.5 wt % (dry coal). The flotation cells were operated at 9 wt % solids. Only the 1200 gallon low shear vessel was used. Binder was added to low shear via the binder contact vessel at an initial concentration of 1 wt % asphalt (no diesel). Low shear product was sent to the sieve bend/vibrating screen as much as possible during the run. When steady state was achieved, the product was also diverted to the product tank, and to the horizontal belt.

Steady state was achieved and the tests begun. Product was sent to the belt, and two 55 gal drums of dewatered product were collected. The material appeared to form a better cake than asphalt/diesel blends. Operation of the belt was not good. The product appeared to have smaller particles than that obtained with 3 and 6 wt %, 60/40 wt % asphalt/diesel blend, and appeared to blind the cloth more. Water ran off the back of the cloth, and the cloth slipped too much. (The rubber belt turned, but the filter cloth would turn slower). The vacuum breaker on the vacuum pump kept relieving. There were no system upsets or interruptions in feed of low shear product from the product agglomerate tank to the belt. All the problems were inherent to the belt itself. However, a representative cake was obtained.

Once product at 1 wt % asphalt had been collected, the asphalt rate was increased to 3 wt % to obtain product under those conditions. A few minutes later the coal feed chute plugged. Solids had built up under the weigh belt feeder from which coal is fed to the ball mills through the weeks of operation, and had finally created enough drag on the belt to break the chain on the feeder drive. A replacement chain link had to be found, and the coal cleaned out. This took about two hours. The unit was then shut down due to the excessive solids level in the system and cleanup begun. Routine samples were taken of coal feed and the flotation cells, and delivered to the laboratory for analyses.

Products with 100 Mesh Coal with No Binder (Run T20)

The objectives of Run T20 were to operate with 100 mesh coal and no binder in low shear to obtain product from the horizontal belt filter for vendor pelletization tests, then evaluate the dewatering performance of the horizontal belt filter and screen bowl centrifuge with a product from 3 wt % diesel in low shear.

The secondary mill was used to make a 40 wt % slurry of 100 mesh coal at a nominal 3 t/h coal feed rate. The high shear was operated with a solids concentration of 15 wt %, and a diesel addition of 1.5 wt %. The flotation cells were operated with 9 wt % solids. Only the 1200 gallon low shear vessel was used, with a low shear solids target of 22 wt %. Initially, no binder was added to low shear. Later, during the diesel portion of the run, 3 wt % diesel was added to low shear via the binder contact vessel as an emulsion. The product was diverted to both the product tank and the sieve bend/vibrating screen.

Coal feed was started and the system allowed to achieve steady state. Testing and sampling of the horizontal belt then began. Two 55 gallon drums of belt product were collected with no binder to low shear for use in vendor pelletization tests.

After collection of the pelletization samples, the binder to low shear was set at 3 wt % diesel to evaluate the product dewatering for comparison with asphalt/diesel blends at the same coal grind and dewatering equipment parameters. Samples and flow measurements were taken at the horizontal belt vacuum filter with a feed rate of about 185 lbs/hr (pump speed of 40 Hz).

The product was then switched to the screen bowl centrifuge, and samples and flow rate measurements taken at feed rates of 40 and 60 Hz (185 and 400 lbs/min, respectively). In addition, routine coal feed and flotation cell samples were obtained and taken to the laboratory for analyses.

5.4.3 Evaluation of Dewatering Equipment with Large Agglomerates

Several runs were conducted to evaluate the dewatering performance with larger agglomerates. These runs are summarized below in Table 5-3.

Table 5-3

MECHANICAL DEWATERING TESTS WITH LARGE AGGLOMERATES

<u>Run</u>	<u>Coal Mesh</u>	<u>Dewatering Equipment Tested</u>	<u>Binder Concentration (wt % dry coal)</u>
21	100	Filter, Centrifuge, Belt	11-13
22	100	Filter, Centrifuge, Belt	12-15
23	28	Centrifuge, Belt, Sieve Bend/Vibrating Screen	10-12

For all runs:

Coal feed at 3 TPH (dry coal basis)

All ball mill solids = 40 wt %

High shear solids = 15 wt %

Flotation cell solids = 9 wt %

Binder composition = 60/40 wt % AC-5 asphalt/diesel

Emulsion water/binder ratio = 50/50 wt %

Low shear residence time = 35 minutes

First Large Agglomerate Dewatering Run with 100 Mesh Coal (Run T21)

The objectives of Run T21 were to evaluate the dewatering performance of the screen bowl centrifuge, horizontal belt vacuum filter, and plate and frame filter press with large agglomerates (about 1 mm in diameter) produced with 100 mesh coal. Prior to the run, the sheave on the screen bowl centrifuge was changed from 2050 to 1750 rpm, and the horizontal belt vacuum filter cloth was changed to a larger mesh size, both at the recommendation of the manufacturer.

The secondary mill was used to make a 40 wt % slurry of 100 mesh coal at a nominal 3 t/h coal feed rate. The high shear was operated with a solids concentration of 15 wt %, and the low shear was operated with a solids concentration of 9 wt %.

and a diesel addition rate of 1.5 wt %. The flotation cells were operated with 9 wt % solids. Both the low shear vessels were used, with the 800 gallon vessel first in series. Low shear solids target was 22 wt %. An initial binder concentration of 11 wt %, 60/40 wt % asphalt/diesel ratio was used, with all the binder introduced into the binder contact vessel. The product was diverted to both the product tank and the sieve bend/vibrating screen. The material in the product tank was initially sent to the horizontal belt vacuum filter to dewater the product while the unit lined out.

The run was begun and the unit was allowed to achieve steady state. After two hours of operation the product had not yet formed agglomerates of significant size (<1 mm). Operation was continued for another hour. When there still was no change in vibrating screen product appearance, the binder rate was increased from 11 to 12 wt %. The 60/40 wt % asphalt/diesel ratio was maintained. Shortly thereafter the binder addition was split between the binder contact vessel and low shear, with 70 % of the binder entering the binder contact vessel and 30 % entering the 800 gallon low shear vessel feed piping. This was done because the product was not getting larger. During previous large agglomerate runs the binder addition had been split, so the change was made in an effort to increase product size. No significant change in product size was achieved after another 1.5 hours, so the binder addition was again increased, from 12 to 13 wt %. The hot water addition to the colloid mill appeared to be lower than desirable (about 35 to 40 wt % water in colloid mill product based on pump speeds), and was increased to about 60 wt %. The unit continued to operate for another hour, but there was no change in product size. The run objective of 1 mm agglomerates was not achieved. The unit was then shut down. There were no operating problems or upsets at any time during the run. Samples of the colloid mill product were taken before and after the water rate change for analysis of binder emulsion. The analyses showed no noticeable change in emulsions.

Second Large Agglomerate Dewatering Run with 100 Mesh Coal (Run T22)

The objectives of Run T22 were the same as Run T21: to evaluate the dewatering performance of the screen bowl centrifuge, horizontal belt vacuum filter, and plate and

frame filter press with large agglomerates (about 1 mm in diameter) produced with 100 mesh coal.

The secondary mill was used to make a 40 wt % slurry of 100 mesh coal at a nominal 3 t/h coal feed rate. The high shear was operated with a solids concentration of 15 wt %, and a diesel addition rate of 1.5 wt %. The flotation cells were operated with 9 wt % solids. Both the low shear vessels were used, with the 800 gallon vessel first in series. Low shear solids target was 22 wt %. An initial binder concentration of 12 wt %, 60/40 wt % asphalt/diesel ratio was used, with all the binder introduced into the binder contact vessel.

The run was started and allowed to achieve steady state. When the agglomerates did not reach the 1 mm size required, the binder rate was again increased from 12 to 13 wt %. The binder was increased at 30 minute intervals, first from 13 to 14 wt %, then from 14 to 15 wt %. Agglomerates of about 1 mm size were achieved about 4 hours after startup, and the dewatering tests were begun. Samples were taken of the vibrating screen product for analysis, and two 55 gal drums of vibrating screen product were taken.

The horizontal vacuum belt was tested at a 40 Hz feed rate (about 185 lbs/min) at a belt speed of 10.0 ft/min. Flow rates and product samples were taken. The screen bowl centrifuge was then tested, at feed rates of 40 and 60 Hz (about 185 and 400 lbs/min, respectively), both with a weir depth of three out of four plugs. Flow rates and product samples were taken. Tailings were diverted to the filter press for collection of solids for refuse vendor tests. Four five gallon buckets of solids were collected.

Large Agglomerate Dewatering Run with 28 Mesh Coal (Run T23)

The objectives of Run T23 were to evaluate the dewatering performance of the screen bowl centrifuge, horizontal belt vacuum filter, and sieve bend/vibrating screen on 1 mm agglomerates produced with 28 mesh grind coal.

The primary mill was used to make a 40 wt % slurry of 28 mesh coal at a nominal 3 t/h coal feed rate. The high shear was operated with a solids concentration of 15 wt %, and an initial diesel addition rate of 1 wt %. The flotation cells were operated with 9 wt % solids. Both low shear vessels were used, with the 800 gallon vessel first in series. The low shear solids target was 22 wt %. An initial binder concentration of 10 wt %, 60/40 wt % asphalt/diesel ratio was used, with all the binder introduced into the binder contact vessel.

The run was started and the unit was operated with changes in binder conditions until steady state production of a 1 mm agglomerated was achieved. The binder addition was changed from 10 to 11 wt % about 1.5 hours after startup, since the product was not 1 mm. The binder was again increased from 11 to 12 wt % after another 2.5 hours. The diesel addition to high shear was increased from 1 to 1.5 wt % at the same time because the flotation cells were not floating the product. Product size was only about 0.75 mm at this time. The unit was then shut down due to equipment failure. The bottom, interior screen of the vibrating screen had torn from the side of the body, and the rubber balls that bounce inside were discharged into the tailings tank, plugging the tailings pump suction. The dewatering equipment was not tested, and the desired product size was not obtained. The vibrating screen was then repaired in preparation for operation the next day.

Run T23 was continued after repairs had been made to the vibrating screen. The initial diesel addition rate to high shear was 1.5 wt %, and the initial binder rate to low shear was 13 wt %, 60/40 wt % asphalt/diesel mixture, with all the binder added via the binder contact vessel.

The unit was operated until steady state at a 1 mm product size was achieved. The diesel addition to high shear was changed from 1.5 to 1 wt % after 3 hours of operation because the flotation cells were floating too much. The binder addition was changed from 13 to 12 wt % after another hour due to the product agglomerates being slightly larger

than 1 mm in size. Steady state was achieved, and samples and flow rates taken at the horizontal belt vacuum filter and the screen bowl centrifuge. The samples were taken to the laboratory for analyses.

Dewatering Run with No Binder and 3 % Diesel Binder (Run T24)

The objective of Run T24 was to evaluate the dewatering performance of the horizontal belt vacuum filter and the screen bowl centrifuge with no binder to low shear, and 3 wt % diesel to low shear. Centrifuge tests were only done with 3 wt % diesel product. The rpm of the screen bowl centrifuge was increased to 2050, and the horizontal belt cloth was replaced with a finer mesh size, prior to the run. Piping was revised to allow operation with the 1200 gallon low shear vessel.

The unit was started and achieved steady state. Flow rates and samples were taken at the horizontal belt vacuum filter and the centrifuge, as well as routine coal feed and flotation samples.

The CDTF was then mothballed until startup in Phase II. All piping and vessels were drained and cleaned and the equipment prepared for long-term storage.

5.4.4 Refuse Dewatering Vendor Tests

Tests were conducted at Parkson Corporation to evaluate the dewatering of CDTF refuse from the thickener. A filter feed concentration of approximately 28 wt % solids results in a cake of 72 - 75 wt % solids. The laboratory test summary is included in Appendix E. The thickener is shown in Figure 5-10.

Figure 5-10: Thickener

5.5 Experience and Knowledge Gained

During operation of the CDTF valuable operating experience was gained, and a number of capital improvements or additions needed for Task 13 were identified. These items must be addressed to improve unit operability and steady state control and monitoring.

Operating Experience

- o Steady state can be achieved quicker when low shear is used if the low shear vessels are empty when flotation product is first fed to them.
- o Three operators were used during Task 6 operation. This was not enough manpower. A minimum of five operators will be needed for POC operation. One possible breakdown of this manpower is shown below.
  - Coal crushing and ball mill areas - operation and sampling
  - Agglomeration system, flotation cells - operation and sampling
  - Product dewatering - operation and sampling
  - Thickener and plate and frame filters - operation
  - Coal addition and product disposal

Modifications to CDTF for POC

- o The microagglomerate recovery tank and agglomerate product tank should be redesigned to allow improved mixing of the slurries to keep solids in suspension, eliminating floating solids buildup problems in these vessels. The design should include appropriate changes to mixer type and size.
- o Improved mixing is needed in both ball mill discharge tanks, the filter press feed tank, and the process area pad sump.
- o Flow control valves with flow indication should be purchased to replace the manual gate valves at water addition locations throughout

the plant. This would provide more accurate control and monitoring of these flows throughout each run.

- Water to ball mills
  - Water to primary mill discharge tank
  - Water to secondary mill discharge tank
  - Water to flotation cells
  - Water to microagglomerate recovery tank
  - Water to agglomerate product tank
  - Water to colloid mill
-
- o The binder metering pumps need to be resized. The existing range is too large for best control of flows.
  - o Install a product pad of sufficient size and appropriate design to accommodate several days' product. This will allow drainage of the product to the process area sump, and improve the disposal procedure for the product. With such a pad, a dump truck could be leased to allow POC personnel to load product and transport to Gaston's coal pile when needed, allowing longer runs and eliminating the uncertainty of scheduling associated with using a commercial transporter.
  - o Install permanent piping from the process area to the Liquefaction facility's waste water treatment system to allow the purging of excess water from the system.
  - o The filter press system filtrate pump capacity must be increased. This pump recycles all of the water which is fed from the thickener and sump to the filter feed tank, and was too small during Task 6.
  - o Install a continuous caustic addition system for pH control.
  - o Install larger ball mill discharge pumps and larger microagglomerate recovery pumps to allow a wider range of test conditions during POC operation.

- o The thickener scum blowdown system must be redesigned and improved. The existing system is too manual intensive, requiring continual attention from one operator throughout the run. Perhaps an automatic spray could be installed to push the floating material through the blowdown piping, designed to come on when the rake arm comes near the blowdown trough. The best place to route the blowdown must be determined - probably to the process area sump, so it can be pumped to the filter feed tank, although this would increase the loading on that sump.
- o Install a coal feed chute to each ball mill.
- o Obtain new metering pumps to provide better control of frother and flocculant addition at lower rates. The pumps used during Task 6 were too large.
- o Install a larger thickener underflow pump and enlarge the pump suction to allow better handling of solids.
- o Relocate the high pressure water pump suction to allow use of the pump.
- o Install guard rails on the sides of the reclaim hopper ramp, and a ladder on the hopper.
- o Install a plant air line to the crusher tower to clean the hammermill coal crusher.
- o For operation in winter months, freeze protection must be given serious consideration. How extensive should the protection be?
- o Install a permanent steam line from liquefaction for use in starting up asphalt flows, unplugging lines, etc.

6.0 LABORATORY TEST WORK AT WILSONVILLE

6.1 Introduction

The analytical laboratory at Wilsonville was used to conduct all analyses for evaluation of unit operation and dewatering performance at the CDTF. In addition, laboratory binder tests were conducted with diesel and heptane, various agglomerates were produced for vendor tests, and product characterization was performed. Evaluation, interpretation, and analysis of the data are not included in this report, but will be discussed in the Task 7 report.

6.2 CDTF Operations Support

Samples from each of the CDTF operating and startup runs were analyzed to target steady state operation and indicate the performance achieved by the various unit operations within the process. A description of the laboratory procedures used during Task 6 is included in Appendix B. Results from each run are summarized in Appendix C, CDTF Laboratory Database. A description of the sample locations is included at the beginning of Appendix C.

6.3 Batch Agglomeration Test Work

6.3.1 Binder Evaluation

A series of batch low shear agglomeration tests using Upper Freeport coal were conducted as a preliminary screening of binder types and to establish an approximate range of binder concentrations for pilot tests. Commercially prepared asphalt emulsions (cationically stabilized) and asphalt/diesel blends were found to be effective binding agents. The following is a list of all binders tested for use in the Component Development Test Facility:

- o No. 2 Fuel Oil (Diesel)
- o No. 5 Fuel Oil
- o No. 6 Fuel Oil
- o Commercial Asphalt Emulsion SS-1
- o Commercial Asphalt Emulsion RS-2

Bench scale testing began with the fuel oils listed above. Each of the binders were tested at various concentrations with 200 mesh grinds of Upper Freeport coal. Procedures, conditions, and results of the binder evaluation tests have been included in Appendix D. The final evaluation was based on the quantity of binder required to produce 1 mm sized agglomerates using a high shear and low shear step with screening as the means of recovery. During these batch tests, a 2 wt % addition of diesel became the standard high shear binder addition. This step was then followed by a series of small binder additions followed by high shear mixing until microagglomerates with sufficient size could be recovered by screening. The recovered microagglomerates were then treated with approximately 500 ml of rinse water before repulping for the low shear step. When the low shear step began, the binder was again added in stages until agglomerates of 1 mm in size were produced. The agglomerates were then dried and analyzed for ash and sulfur. Following is a step-by-step procedure of the actual test conditions:

1. Conditioning. Four minutes @ 2400 rpm with the Rushton impeller
2. Diesel addition (dry coal basis) until product was screenable.
3. High Shear four to six minutes @ 2400 rpm.
4. Screening of high shear product on 200 mesh screen.
5. Approximately 500 ml of rinse water to high shear product.
6. Repulp froth into a one liter vessel.
7. Change impeller to three blade turbine.

8. Binder addition with two minutes of high shear @ 2400 rpm.
9. Low shear 60 minutes @ 1800 rpm.
10. Binder addition with two minutes of high shear @ 2400 rpm.
11. Low shear 15 minutes @ 1800 rpm.
12. Repeat steps 10 and 11 until 1 mm agglomerates are produced.

This procedure was followed as close as possible throughout the initial binder evaluation testing. As research into the various binder types continued, a variety of AC-5 asphalt and fuel oil No. 2 blends were prepared representing a range of binders according to viscosity and used for binders during low shear.

Testing of the binders with 28 mesh Upper Freeport coal was then conducted, with asphalt and diesel blends again used as low shear binders. The procedure used for the 200 mesh tests were also used for the 28 mesh, however, the addition of diesel in high shear became 1 wt % due to the change in grind size. During this time the laboratory procedures were modified in an effort to better simulate the emerging heavy oil process being tested in Task 5 and to simplify the laboratory work. A Wemco-Gallagher flotation machine was utilized to recover microagglomerates immediately after high shear mixing. The recovered microagglomerates were again repulped and low shear agglomeration completed using a series of binder additions and mixing steps.

The 200 and 28 mesh grinds were then tested with the commercial asphalt emulsions. The two types tested were SS-1 and RS-2 (as designated by ASTM asphalt emulsion classification). These binder tests using emulsions followed the procedure previously described. This complete set of testing determined the agglomerate growth rate for Upper Freeport coal and each individual binder type.

Once the binder levels had been established, different impellers were compared by testing 28 and 200 mesh Upper Freeport coal in a 0.8 liter vessel. The impellers used included

the following: six-blade Rushton, three-blade Turbine, 45 degree four-blade turbine and axial three-blade A310 impellers. Comparison of agglomerate growth rate and binder consumption indicated no significant differences between the four impellers with the power draw varying between 1.8 to 9.0 in-oz of torque between the various types of impellers and impeller speed in the range of 1600 to 2400 rpm. Procedures and observations for the impeller comparisons can be found in Appendix D.

After impeller testing, the binders were evaluated for agglomerate growth and consumption by comparing staged and single staged additions of binder. This was done by completing the high shear step with diesel, then 1) adding the SS-1 emulsion binder in stages with low shear between the additions for agglomerate growth and 2) adding the total amount of binder in one step with one low shear time for agglomerate growth. The testing indicated that a small reduction in binder requirement may occur by series addition of the binder.

A few tests were performed to evaluate the performance of surfactants in reducing the binder requirements for agglomerate growth. The surfactants used were Paradimethylsiloxane, a hydrophobic based surfactant, and oleic acid, a fatty acid. Several surfactant tests indicated a reduction in overall binder requirement was achieved, however, the tests had poor reproducibility, making the results inconclusive.

6.3.2 Heptane Process

Production of Heptane Agglomerates and Heptane Agglomerant Tests

The objectives of the heptane testing were to:

- o Make a preliminary estimate of high shear conditions for a heptane-based process. This was to ensure that the microagglomerates used in the low shear test work would be similar to those expected from an optimized process.
- o Measure the kinetics of batch heptane agglomeration.

- o Determine the effects of different binder types and their concentrations on the formation of low shear product agglomerates.
- o Evaluate the effects of product agglomerate size and binder content on the rate of agglomerate drying.
- o Assess the physical properties of both "green" (low shear product) and dried agglomerates.
- o Assess the physical strength of heptane agglomerates during solvent removal by evaluation of product agglomerate strength during drying at an elevated temperature.

Early work at Wilsonville involving the first phase of low shear agglomeration testing showed that relatively strong agglomerates of 2 to 4 mm in size could be formed using very low quantities of asphalt (AC-5) suspended in heptane. AC-5 addition during high shear mixing resulted in the formation of larger microagglomerates with improved water drainage properties. Flotation tests conducted using heptane microagglomerates as feed resulted in good microagglomerate recovery, with ash and sulfur rejection comparable to screening.

The second phase of heptane test work was completed in three (3) series of tests, with the best results from each phase being used to establish conditions for the subsequent series of tests. The purpose of Series I was to assess the use of asphalt binder in high shear as a means of making microagglomerates larger and with improved recovery properties. Series II was used as a means of evaluating the effects of binder concentration in low shear on agglomeration kinetics. The purpose of Series III was to measure how agglomerate size and binder content influence the rate of drying at selected dryer temperatures. Results of these tests are shown in Appendix D.

The following test conditions were established based on previous laboratory data:

Coal type:	Upper Freeport
Coal particle size:	200 mesh with a d50 of 25 microns

High shear solids concentration:	15 wt %
High shear residence time:	Two minutes
High shear agglomerant addition:	Add total quantity of agglomerant at start of high shear mixing for a duration of ten seconds
Microagglomerate recovery:	Screen or flotation
Low shear solids concentration:	15 wt %
Low shear mixing intensity:	1800 rpm, turbine impeller
Low shear agglomerant addition:	Add total quantity of bridging liquid at start of low shear mixing, for a duration of 30 seconds

Series I Test Matrix

Binder concentration to high shear:	0, 0.1, 0.3, and 0.5 wt %
Binder type:	AC-5 asphalt
High shear heptane concentration:	10, 20, and 30 wt % for screening; 5, 7.5, 10, 20, and 30 wt % for flotation
Microagglomerate recovery:	Screen or flotation

Procedure

The 20 wt % heptane concentrations were tested first at 0 and 0.5 wt % binder (AC-5) concentrations. After high shear mixing the microagglomerates were screened on an 80 mesh screen for two minutes, using a mild rapping action to assist with water removal. The microagglomerates were then rinsed with 800 ml of water and screened for an additional two minutes to allow excess water to drain. The product was then dried at 105° C until no further volatiles were emitted. Ash and sulfur content were then determined. These tests conditions were continued until the optimum conditions of recovery and product quality were achieved. The best method indicated in Series I

testing was then carried over into Series II for subsequent low shear tests.

Series II Test Matrix

Binder concentration to low shear: 3, 4, and 5 wt % AC-5

Residence time: 4, 8, 16, 32 minutes

The amount of heptane used in low shear was selected by that amount that would produce an agglomerate of a 2-3 mm size after four minutes of low shear mixing. Phase I indicated that the total agglomerant requirement to achieve this growth rate was approximately 35 wt %.

Procedure

All of the Series I tests were conducted using a heptane concentration of 10 wt % in high shear. For each low shear test one of the three levels of asphalt was added to a sufficient amount of heptane such that the total amount of asphalt and heptane would equal 35 wt % of dry coal by weight. Keeping the total heptane and asphalt at a constant value helped to produce similar kinetics between asphalt levels with similar "green agglomerates" handleability. After low shear agglomeration, the product was split into three portions:

- o Half of the product agglomerates was used for determining total volatiles by drying at 105° C, screened for size consistency and then submitted to a drop shatter test from a 24 " height.
- o One fourth of the product agglomerates was split into two subsamples. One sample was dried at 105° C and analyzed for ash and sulfur. The other was saved for future analysis.
- o One fourth of the product agglomerates was used to determine water content of agglomerates by extraction with xylene.

Formation of 2 mm agglomerates was seen with all three levels of AC-5 binder. The 5 wt % binder level was discarded due to the stickiness of the heptane product. A 2 wt % AC-

5 binder level replaced the 5 wt % level to evaluate both high and low levels of AC-5. The total oil concentration (heptane plus AC-5) was also reduced from 35 to 33 wt % (dry feed coal basis) since the lower total agglomeration solution concentration improved the handleability of the product agglomerate while maintaining good agglomeration kinetics.

During this Series II testing, the one liter vessel originally used was replaced with a stainless steel vessel of the same dimensions. This was due to the low shear slurry adhering to the walls of the original vessel.

Series III Test Matrix

Binder concentration:	2, 3, and 4 wt %
Dryer temperature:	78, 110, and 140 ° C
Dryer retention time:	20, 40, and 80 minutes, and 16 hrs.

Procedure

The Series III tests were completed using the same procedure as in Series II, serving as repeats of previous tests. Three low shear tests for each binder concentration were conducted to produce test agglomerates for each dryer temperature. After low shear mixing and product agglomerate screening was completed, the agglomerates were split into four sub-samples. Each sub-sample was placed in a preheated oven for the designated retention time. After drying, the sample was weighed to determine total volatile loss and then the agglomerates were assessed for strength both before and after cooling. A sub-sample of each retention time sample was used for water and total oil extraction. Ash and total sulfur content were analyzed for the sub-samples with the 16 hour retention time.

6.3.3

Evaluation of Precleaned Coals

The objectives of the precleaning tests were to determine whether there is any improvement in overall agglomeration process performance as a result of precleaning the project coals and, if so, to quantify this improvement. Agglomeration tests were conducted on prepared samples of Upper Freeport and Kentucky No. 9 coals. The coal samples were prepared at Geochemical Testing by three different methods. The test preparation methods are described below. Results of the tests are included in Appendix D.

- o Raw coal sample: The sample was pulverized to 1-mm topsize and sent to Wilsonville and ARC for batch tests.
- o Heavy-liquid control sample: The sample was screened at 100 mesh and the 1/4" x 100-mesh fraction contacted with the precleaning liquid (1.65 specific gravity) for the time and amount of liquid generally required to conduct sink-float testing on the sample. All of the solids were then recovered by filtration, and the sample then pulverized to 1-mm topsize. The 100-mesh x 0 screened fraction was then recombined with the pulverized sample and homogenized. The combined sample was then cross-riffled and split into a number of 165 +/- 5 gram samples. These samples were then wet-ground further to the desired size at Wilsonville for agglomeration feed.
- o Precleaned sample: Processing of this sample involved screening at 100 mesh to separate the 100 mesh x 0 fraction. The 1/4" x 100 mesh fraction was subjected to float-sink testing using a liquid with a specific gravity of 1.65. The float products were pulverized to 1-mm topsize and recombined with the 100 mesh x 0 fraction from the earlier screening step. The combined sample was homogenized, cross-riffled, and split into a number of samples weighing about 165 +/- 5 grams. These samples were then wet-ground in a ball mill at Wilsonville to produce the agglomeration feed samples.

Batch agglomeration tests were then carried out on the three types of samples using diesel and heptane as the agglomerating liquid. A total of 41 Kentucky No. 9 coal and 34 Upper Freeport coal batch agglomeration tests were completed. The raw coal sample described above constituted the baseline sample for comparison of the effects of

precleaning. The heavy-liquid control sample provided information on whether or not the heavy liquid caused a change in the agglomeration properties of the coal (no effect was detected). The float 1.65 coal fraction represented the pre-cleaned coal sample.

The conditions for the agglomeration tests were:

Coal:	Kentucky No. 9 and Upper Freeport
Coal particle size:	28, 100 and 200 mesh
Coal samples:	Three samples (detailed earlier)
Agglomerating liquid:	Diesel and Heptane
Agglomerant dosage:	1 wt % for diesel and 20 to 25 wt % for heptane
High-Shear residence time:	One minute
Method of recovery:	Flotation for diesel, screening for heptane

The tests involved high shear mixing followed by microagglomerate recovery. Low shear agglomeration was not carried out. Clean coal product and refuse samples from the agglomeration tests were analyzed for ash, total sulfur, and pyritic sulfur (by outside lab) in addition to several randomly selected sample aliquots for feed coal analysis.

6.4 Vendor Testing

6.4.1 Heptane Removal Drying Tests

Tests were performed using laboratory-scale test units at dryer vendor laboratories to evaluate the removal of heptane from agglomerates produced in a heptane process. A vibrating fluidized bed dryer, a rotary tray dryer, and an indirect disc type dryer were

tested. The test conditions required to achieve high solids recovery and low product volatiles were identified, and selected samples of dryer products were collected at the end of the dryer tests for determination of trace heptane concentration and product characterization. Results of the dryer tests are discussed in the Task 7 report. The heptane agglomerates used in the tests were prepared at the Wilsonville laboratory. As part of this work, various methods of sample shipment were evaluated with respect to "green" agglomerate conditions.

The objectives of the dryer tests were to:

- o Define the dryer conditions required to process the heptane agglomerates at acceptable levels of agglomerate degradation
- o Estimate the rate of volatiles removal and the final volatiles content of the dried agglomerates
- o Measure the trace heptane concentrations in the dried agglomerates

6.4.1.1 Agglomerate Sample Preparation

Heptane agglomerates for vendor dryer tests were produced in the Wilsonville laboratory using minus 100 mesh Upper Freeport coal. The coal was ground in the secondary ball mill at the CDTF due to the large quantity required. Also, the laboratory vessel used in the earlier batch heptane agglomeration tests was too small to produce the significant quantities of product required, therefore, a larger mixing vessel was fabricated. A 12" diameter baffled vessel (volume of five gallons) with a variable speed mixer was used to produce the agglomerates. The vessel was first used with a preliminary test using 28 mesh Upper Freeport coal with diesel as the agglomerant and a commercial asphalt emulsion as binder. The test was strictly experimental with no set procedure, only to verify torque readings as well as the ability to work with such a large vessel. The test was successful, with a product agglomerate of 3/4 mm.

Using the large mixing vessel, heptane microagglomerates were produced in high shear

with 20 wt % heptane. A continuous screening method was established for microagglomerate recovery. The microagglomerates were drained from the vessel onto the continuous vibrating screen using a two inch diameter drainage hose attached to an opening on the side of the vessel near the bottom. The eight inch diameter, 48 mesh screen was set at an angle, with a 2.75" wide trough added across the center of the screen to divert material through an opening at the circumference. The opening had a 5 mm "lip" where the material discharged from the screen. The screen was mounted on a laboratory vibrator for a standard eight inch screen. After numerous adjustments to the screen, it was determined that at an angle of 40 degrees the microagglomerates would form a very thin cake of product on the lip of the screen, preventing flooding. The success of the vibrating screen relied on the buildup of an agglomerate cake on the screen which would slow down the incoming agglomerate slurry and prevent the feed slurry from flooding the screen deck. At a steady rate of flow, the agglomerate cake moved slowly down the screen being pushed by incoming product. This steady movement allowed all water to drain before the product exited the screen.

The procedure for producing the heptane agglomerates consisted of high shear mixing for three minutes followed by microagglomerate recovery by screening and low shear mixing for 10 - 15 minutes. Based on experimental data from the batch tests 18 wt % heptane was used in high shear. Inversion during high shear mixing was observed within 90 to 110 seconds after the addition of the heptane. This was visible by the formation of discrete microagglomerates. The high shear product was then screened using the vibrating screen apparatus previously described. At this point, the microagglomerates were returned to the mixing vessel, where water was added to bring the slurry level to 10 inches. Low shear binder with a content of 7 wt % heptane and 2 wt % AC-5 was then added. This total oil content of 27 wt % formed agglomerates 2-4 mm in size. The agglomerates were then drained on an 8 mesh screen. The agglomerates were slightly tumbled around on the screen to allow all free water to drain. The product was then shipped to dryer vendors for the first series of drying tests.

Shipment Method Evaluation

Two methods of sample shipment were evaluated to determine the best method of transporting "green" agglomerates to prevent clumping: placing the dewatered agglomerates in sealed cans, and shipping the agglomerates immersed in water. The samples immersed in water showed a greater tendency to clump together than the dewatered samples. Both methods were sensitive to the procedure used to prepare the agglomerates before they were packed in the sample containers. Some agglomerates were screen drained followed by 30-45 seconds of tumbling on the screen, while some were prepared with minimal drainage and no screen agitation. The agglomerates with better drainage were more free-flowing, containing 2-4% lower volatiles than those with minimal drainage. These lower-volatile samples did not clump during shipment, while those which were not tumbled coalesced more readily, especially when shipped immersed in water. The dewatered state was chosen for subsequent shipments.

6.4.1.2 Equipment Testing

First Series of Dryer Tests

Preliminary drying tests were conducted on site at each vendor's laboratory as described below, using nitrogen as the drying gas.

Vibrating Fluidized Bed Dryer A series of four drying tests was completed using a 0.5 ft² batch vibrating fluidized bed dryer and one gallon samples of agglomerates. Recovery of the agglomerates and heptane removal proved to be sensitive to drying conditions (gas velocity and temperature) and the final temperature of the agglomerate bed in the dryer.

Rotary Tray Dryer A series of five drying tests was conducted using a bench continuous tray dryer and 1000-1200 grams of agglomerates. The laboratory drying unit consisted of two trays operated to simulate transfer of product between rotating stages of a turbo dryer. The sample was loaded onto one tray and transferred to the second tray using a "tray wiper" at programmed intervals. The gas velocity, temperature, and tray cycle time were adjusted to simulate commercial dryer conditions. Periodic samples were extracted

from the dryer during operation to develop drying rate curves.

Analysis of the first series dryer products for trace heptane concentrations and testing of the comparative strength of samples dried at Wilsonville and samples produced by the dryer vendors was then conducted. Discussion of the drying results has been included in the Task 7 report. Drying rate data and volatile losses are included in Appendix D. This data provided the drying conditions and specifications necessary during the second series of dryer tests to achieve high removal of heptane with sufficient product agglomerate strength.

Second Series of Dryer Tests

Evaluation of the dried products from the first series of dryer tests indicated that the 2 wt % AC-5 content in low shear had not produced the strongest heptane agglomerate known to be possible. Therefore, another batch of heptane agglomerates were produced for a second series of dryer tests, using 3 wt % AC-5 in low shear. These were shipped to all dryer vendors for testing of heptane removal. In addition, disc-pelletized agglomerate samples were tested using the vibrating fluidized bed dryer and the rotary tray dryer. A summary of each test is given below.

Rotary Tray Dryer The rotary tray dryer used in the first series of tests was again used in the second series to evaluate drying of the heptane agglomerates produced with 3 wt % asphalt. Two dryer tests used nitrogen as the drying medium, while the other three tests used air.

Indirect Disc Dryer The tests with an indirect disc type dryer used microagglomerates from high shear only, using heptane as the agglomerating medium with no asphalt. An indirect disc type dryer was tested.

Vibrating Fluidized Bed Dryer Dryer tests were completed with a vibrating fluidized bed dryer for heptane agglomerates (3 wt % asphalt) and disc-pelletized agglomerates. Four

tests were conducted with the heptane pellets, and ten tests with the disc-pelletized (see Section 6.4.2.2). High solids recovery was observed during each of the tests, indicating that the fluidized bed dryer did not cause degradation of the sample during drying.

Hot Water Bath Tests Heptane removal via hot water bath stripping was tested at Wilsonville. A series of four tests were completed using a hot water bath temperature of 90° C and residence times of 30, 45, 60, and 120 minutes. Condensation of heptane was complete in approximately 25 minutes. No degradation of the final product was observed, but they were easily deformed after screen drainage. The final agglomerate moisture was approximately 15 wt %. Residual heptane analysis was conducted, with the following values:

Table 6-1

RESIDUAL HEPTANE CONCENTRATIONS

<u>Residence Time, min</u>	<u>Heptane Conc., ppm</u>	<u>Toluene Conc., ppm</u>
30	2400	1670
45	1540	1380
60	1500	1380
120	810	845

The toluene detected is believed to originate from the industrial-grade heptane used for the agglomeration tests, which was obtained from the coal liquefaction pilot plant also located in Wilsonville. The higher boiling point of the toluene (112° C) compared to water results in the concentration of toluene in the product. This phenomenon was also observed with refuse from the CDTF which was treated via hot water bath (350 and 280 ppm, respectively, for two samples), and can be eliminated by the use of fresh heptane dedicated to the process.

Product characterization tests were performed with the dryer test products to determine how well the product held up in the dryer units.

6.4.2 Pelletization and Drying Tests

6.4.2.1 Sample Preparation and Pelletization

Size enlargement via disc pelletization was completed at Ferro-Tech facilities with product samples collected from the CDTF horizontal vacuum belt filter. One product was produced during operation with the addition of 1 wt % AC-5 asphalt to low shear. The second product was produced with no binder to low shear. Both samples were generated from 100 mesh Upper Freeport coal with 1 wt % diesel addition to high shear. A total of 21 batch disc pelletization tests and 6 continuous tests were completed. The conditions and results of the tests are included in Appendix E. Those tests which included a capital "A" in the identification number were conducted with 1 wt % asphalt product.

The variables tested included:

- o Binder type: Wet milled food corn starch, dry milled corn flour
- o Binder concentration: 0.5 to 5 wt %
- o Method of disc feed preparation: dry mix binder, wet mix binder
- o Asphalt content: 0 to 2 wt %
(for weatherproofing)

Methods used to measure the initial pellet strength as part of the evaluation of pellet quality consisted of compression force breakage of mono-sized pellets (approximately 11 mm diameter), 18-inch drop tests of "green" and dried pellets, and six-foot drop tests of dried pellets.

6.4.2.2 Drying Tests

Pelletization product was dried and subjected to crush tests. A portion of the pelletization product was dried at Ferro-Tech in a convection oven, while additional product was sent

for dryer tests with a vibrating fluidized bed dryer. All the dried product was subjected to strength tests at Ferro-Tech.

The convection oven was operated at approximately 80° C. Some of the samples dried in the convection oven were removed from the oven at different time intervals as a means of determining the importance of moisture content on pellet strength. A summary of the Ferro-Tech drying results over time is also included in Appendix E.

Results of the strength tests of the vibrating fluidized bed dryer products are shown in Table 6-2. (Crush is the force in pounds required to crush a pellet of 1/2 to 7/16 inch diameter).

Table 6-2

PELLETIZED DRYER PRODUCT STRENGTH

<u>Test No.</u>	<u>Starch, wt %</u>	<u>AC-5 Asphalt</u>	<u>Moisture wt %</u>	<u>Average Crush</u>
C-1	1.5	0	2.29	3.2
	"	"	1.26	3.5
	"	"	0.68	5.4
	"	"	-	6.0
C-2	2	0	6.05	1.4
	"	"	2.40	2.5
	"	"	2.25	6.3
	"	"	-	8.8
C-3	4	0	7.80	1.7
	"	"	2.53	8.2
	"	"	-	6.7
C-5	2	2 wt%	7.27	1.0
	"	"	2.42	3.8
	"	"	1.76	5.1
	"	"	0.95	5.6
	"	"	0.66	5.0

The results of the Ferro-Tech convection timed samples suggest that moisture values of 5-6 wt % are required to achieve maximum strength. Observations made during the vibrating fluidized bed dryer tests suggest that a moisture content of 2-4 wt % is required for maximum strength. Regardless, the continuous pelletization tests successfully enlarged both CDTF-generated coal samples over the range of binder tested (1.5 to 4 % dry milled flour), and the pellet quality was as good as or exceeded that obtained from the batch tests.

6.5   Product Characterization

6.5.1   Laboratory and CDTF Samples

Numerous types of heavy binder agglomerates were produced in the laboratory and CDTF during Task 6. These products were made with different binder levels, different methods of binder additions, etc. Characterization tests conducted on these products allowed a comparison of strength and handleability. Evaluation of the product characteristics is discussed in the Task 7 report. The tests are shown below, with procedures for most of these tests included in Appendix B.

- o   Particle size distribution
- o   Tumbler test
- o   Drop shatter test
- o   Volatiles concentration
- o   Moisture
- o   Oil content
- o   Ash content
- o   Sulfur content

- o Angle of repose
- o Bulk density

Along with these characterizations of heavy binder agglomerated products, the heavy oil binders were characterized by viscosity and specific gravity.

6.5.2 Vendor Samples

Heptane Product Characterization

Product characterization tests were conducted on selected dryer vendor products returned to Wilsonville. Four types of samples were used:

- o Feed sample - a sample of the wet agglomerates taken just before the dryer tests were performed.
- o Bulk product sample - The agglomerates recovered from the test dryer after the completion of the dryer tests.
- o Timed sample - The agglomerates extracted from the dryer during the drying test.
- o Dust sample - The agglomerate fines that are removed from the dryer by entrainment in gas flows through the dryer. This represented product lost due to agglomerate degradation during the drying process.

The following tests were performed for each of the four samples listed above. The procedure for each is included in Appendix B.

- o Feed Sample
  - Total volatiles
  - Agglomerate particle size distribution
  - Drop shatter

- o Dryer Bulk Product Sample
  - Agglomerate particle size distribution
  - Drop shatter
  - Oil content if appropriate.
  - Total volatiles
  - Water content
  - Angle of repose
  - Tumbler test
  - Direct shear tests (outside laboratory)
- o Timed Sample
  - Total volatiles
  - Trace heptane analysis (outside laboratory)
- o Dust Sample (fines lost from dryer)
  - Particle size distribution

Along with the product characterization of all heptane agglomerates, product characterization was performed for the heptane/AC-5 binder and the heptane alone. These included GC analysis and specific gravity.

APPENDIX A
CDTF OPERATIONS TEST DATA

[illegible][illegible]

T2	3/28/91	0	6.27	7.5	46
		11			
		18	6.31	8.8	
		26	6.32	9.6	48
		32	6.40	10.8	
		41			52
		49	6.25	12.2	
		61			51
		63	6.52	13.6	
		76			53
		77	6.65	15.1	
		88	6.03	16.2	
		91			48

Page 2

Run	ID	Date	Time	Lbs/hr	TotLbs	PBM	%Sol	Feeding HS- gpm	Feeding LS- cum gal	Feeding HS- gpm	Feeding LS- cum gal	Water	Asphalt	Binder	Sump	Sump	Sump	Sump	Prod	HS	LS	LS	Froth	PBM	SBM	HS	BCV	LS1200	LS800	Power Draw
T2	12	3/28/91	101	5.79	17.5																									
			111	6.06	18.6																									
			116				46																							
			121	5.89	19.7																									
			131				46																							
			136	6.00	21.1																									
			146				44																							
			147	5.94	22.1																									
			156	5.90	23.0																									
			161				51																							
T3	13	4/02/91		6.51	25.0			87.9																						
	15					47																								
	25			6.23	26.2			86.6																						
	30					49																								
	35			6.31	27.4			88.3																						
	45			6.23	28.3	53		113.7																						
	55			6.35	29.4			87.3																						
	60					48		12.0																						
	65			6.16	30.5			86.7																						
	75			6.04	31.5	49		112.0																						
T4	85			6.27	32.6			81.7																						
	90					42		122.0																						
	95			6.14	33.4			88.2																						
	0	4/10/91		7.14	34.5	49		90.4																						
	10			6.05	35.7			82.5																						
	15																													
	20			6.36	36.8	41		80.6																						
	25																													
	30			6.55	37.7	42		70.6																						
	35																													
	40			6.34	38.9	45		84.2																						
	45																													
	60			6.01	41.0	47		81.9																						
	70																													
	75			6.01	42.6	40		71.4																						

COTF Operating Data

8/02/91

[illegible]

[illegible]

CDTF Operating Data

8/02/91

Run ID	Date	<--Coal Feed-->		<--Grinding-->		<-----Flowmeter Data----->				<--Temperature (F)-->				Pump Speed (Hz)				<--KW-->				Power Draw							
		Lbs/hr	TotLbs	PBM	SBM	-Feeding HS-	-Feeding LS-	gpm	cum gal	gpm	cum gal	Water	Asphalt	Binder	Sump	Sump	Sump	Micro Prod	HS	LS	LS	Froth	PBM	SBM	HS	BCV	LS1200	LS800	
T11	5/06/91	130	6.31	13.5	49	74.6	29418	73.0	55784																				
		145	6.41	15.0	45	75.7	30493	74.1	56673																				
		165	6.44	17.3		76.0	32093																						
		167						60.2	58069																				
		175	6.88	18.5	44	68.0	32944	42.1	68855																				
		190	6.72	19.9	48	72.1	33824	97.8	69625																				
		205	6.73	22.0	48	75.5	35276	51.0	60678																				
T12	5/09/91	40		4.2																									
		45	6.41	5.0	46	73.2		64.0																					
		60	6.45	6.7	49	73.8	808	69.0																					
		75	6.30	8.0	46	70.2	1736																						
		90	6.47	9.7	47	75.4	2921																						
		105	6.53	11.3	45	76.5	4016	70.5	2607																				
		120	6.59	12.9	42	77.4	5187	35.3	3564																				
		135	6.63	14.8	46	73.3	6418	45.1	4653																				
		150																											
		180	6.01	19.5	40	76.2	9699	70.1	7316																				
		195	6.31	21.2	48	73.5	10810	76.2	8202																				
		210	6.54	22.7	46	73.7	11872																						
		220																											
		225	6.46	24.3	44	75.6	12927																						
		245	6.42	25.6	44	73.9	14505	66.4	11184																				
		255	6.47	27.7		81.1	15277																						
		260																											
		270																											
T13	5/15/91	15	6.44	4.3	39	82.1	21103																						
		30	6.51	5.8	47	56.4	21890																						
		45																											
		60	6.55	9.3	47	56.9	24013																						
		75																											
		85	6.56	11.4	43	58.7	25207																						
		95																											
		105	6.62	13.9	43	62.4	26690																						
		130	6.32	16.4	48	67.9	28177																						
		135																											

60.0 28023

[illegible]

Run ID	Date	Time	←-Coal Feed→		←-Grinding→		←-Flowmeter Data→				←-Temperature (F)→				Pump Speed (Hz)				←-KW→				Power Draw			
			Lbs/hr Totlbs	PBM	SBM	XSol	gpm	cum gal	gpm	cum gal	gpm	cum gal	gpm	cum gal	gpm	cum gal	gpm	cum gal	gpm	cum gal	gpm	cum gal	gpm	cum gal		
T17	5/24/91	115	6.32	12.3	45		59.9	28052	47.1	29455	178	172	30	55	50	8.0	12.2	7.4	.10	30	60	28	62			
		140	6.49	14.4	47		65.2	29223	47.6	30550																
		190	6.51	20.2	48		59.2	32486	34.4	33490																
T18	5/29/91	35	6.59	4.3	44		39.4	1419	64.0	44327																
		50	6.50	6.0	47		35.4	1978	61.0	45377																
		65	6.25	7.3	43		37.1	2426	66.0	46427	90	124		54	50	8.0	12.2	7.4	.10	24	60	30	60			
		80	6.39	9.5	46		39.8	3193																		
		95	6.48	10.8	43		33.4	3634	65.0	48528																
		110							72.0	49338																
		115	6.64	12.8	39		26.3	4175																		
		125							86.0	50650	171	124		50	60	8.0	12.2	7.4	.10	24	58	31	62			
		140	6.67	15.3	49		32.8	4908	84.0	51671																
		170							39.0	54356																
T19	5/30/91	180	6.34	19.8	49		27.4	6294																		
		185							68.0	55267	156	124		51	60	8.0	4.5	3.7	.10	24	58	30	60			
		200	6.50	22.1	48		32.3	6964	88.0	56571																
		215							83.0	57695																
		225	6.62	24.8	48		31.3	7709																		
		245	6.49	26.6	50		39.3	8274	67.0	59715	165	124		51	50	8.0	4.5	3.7	.10	24	58	30	61			
		260							38.0	60654																
		265	6.34	29.2	48		40.7	9108																		
		280							64.0	62120																
		T19	5/30/91	45	6.33	4.7	40		33.8	11996	35.0	68365	161	114		54	50	8.0	0.0	2.1	.10	24	60	25	50	
60	6.51			6.8	48		42.4	12757	36.0	69119																
75	6.41			8.5	40		41.4	13433	61.0	69846																
90	6.30			9.6	40		41.9	13924	64.6	70421																
105	6.24			11.1	38		37.1	14501	46.2	71333	166	120		55	50	8.0	0.0	2.1	.10	24	58	25	50			
120	6.38			13.1	38		42.1	15232	49.1	72431																
145	6.42			15.4	46		46.8	16229	57.4	73733																
165	6.53			17.5	47		63.4	17423	55.0	74840	172	120		55	50	8.0	0.0	6.2	.10	24	58	27	50			
T20	6/03/91			15	6.35	3.1		62.1	1352																	
				20							52.0	81634														
		35	6.40	5.0	32		39.8	2539	50.0	82132																
		50	6.33	6.3	44		46.4	3083	56.0	82897																
		70	7.10	8.7			38.0	3932	59.0	83950																

[illegible]

[illegible]

APPENDIX B
LABORATORY PROCEDURES

PARTICLE SIZE DISTRIBUTION (PSD)

SCOPE:

This method is used to determine the PSD of 28, 100, and 200 mesh coal grinds produced in both the lab and the CDTF. PSD determination for agglomerated products is discussed in the footnote.

SUMMARY:

A representative sample of coal is wet screened at 170 mesh. The +170 and -170 samples are then dried at 105° C with the +170 mesh being dry screened and the -170 mesh sample analyzed with the Leeds & Northrup Particle Size Analyzer. The two size distributions are then combined to make up one complete size distribution.

APPARATUS:

Leeds & Northrup Particle Size Analyzer (Microtrac). See Figure B-1.

PROCEDURE:

1. Sample size should be approximately 100-150 grams.
2. Wet screen the entire sample at 170 mesh until no coal passes through the screen.
3. Dry both +170 and -170 mesh samples at 105° C and weigh. This will determine what percentage of the entire sample is +170 mesh and -170 mesh.
4. The +170 mesh PSD is then determined via dry screening using the appropriate sizes depending on coal topsize.
5. The -170 mesh is sampled and prepared in slurry form for PSD determination with the Microtrac.
6. The two size particle size distributions are then combined into one PSD representing the entire coal sample.

NOTE:

The PSD of agglomerated products is determined via dry screening with the appropriate size screens. Given the large size of these products and their oil content, the use of the Microtrac is neither necessary nor possible for fine particle size determination.

Figure B-1: Block Diagram of MICROTRAC

DETERMINATION OF ASH AND SULFUR CONTENT

SCOPE: Determination of ash and sulfur content of coal and agglomerated product samples.

APPARATUS: MAC-400, LECO SC-32, and LECO SC-132 instruments

PROCEDURE:

1. Riffle or cone and quarter the sample to be analyzed until the minimum representative sample of sufficient size for the desired analyses is obtained. The minimum amount of sample required for the subsample to be representative varies depending on the particle tosize, i.e., the coarser the particles the more sample required.

2. Pulverize the subsample to a size of 90 wt % passing 100 mesh.

3. Remove the required amount of material from subsample and load it into the required containers for analyses via the laboratory instruments.

4. The following results are then generated from these laboratory analyzers:

MAC-400 - wt % ash
wt % moisture
wt % fixed carbon

LECO SC-32/SC-132 - wt % total sulfur

PERCENT SOLIDS DETERMINATION

SCOPE:

To determine the percent solids of samples taken from the Component Development Testing Facility.

PROCEDURE:

Samples prepared for testing in the laboratory were contained in 16 oz. jars. The initial weight of the sample was determined by weighing the jar containing the sample.

1. Record the weight of the 16 oz. jar and sample.
2. Weigh one piece of appropriately sized filter paper.
3. Pour the sample onto the filter paper and allow to filter by vacuum.
4. Record the weight of the empty jar.
5. Once the sample has completely filtered, place the filter paper and sample into a 105° C oven to dry.
6. When the sample has dried, weigh the filter paper and dry sample.

CALCULATIONS:

$$\% \text{ Solids} = \frac{\text{Final Sample Weight}}{\text{Initial Sample Weight}} \times 100$$

where:

Initial Sample Weight = (Weight of jar + sample) - (Weight of jar)

Final Sample Weight = (Weight of filter paper) - (Weight of dry paper and product)

DETERMINATION OF VOLATILE LOSS

Scope: The following method is used to determine the total volatile loss (at 105° C) from agglomerates and to determine the moisture content of coal.

Summary: A representative sample of agglomerates/coal is dried at 105° C and by calculation, the volatile loss/moisture content is determined.

Procedure:

1. Sample size used should be 100-200 g of a representative sample of agglomerates/coal.
2. Determine the initial weight of the sample and place in a 105° C oven until a constant weight is achieved.
3. Determine the final weight of the agglomerates and perform the following calculation to determine percent volatile loss/moisture:

$$\% \text{ Volatile/Moisture} = \frac{\text{Initial Wt} - \text{Final Wt}}{\text{Initial Wt}} \times 100$$

DETERMINATION OF AGGLOMERATE WATER CONTENT BY AZEOTROPIC DISTILLATION

- Scope: This method determines the water content of agglomerates.
- Summary: The water is separated from agglomerates by azeotropic distillation with xylene. Condensed solvent and co-distilled water are continuously separated in a trap, the water being retained in the graduated section. The water content is determined by measuring the volume of water in the trap.
- Apparatus: Distillation set-up for water extraction. (See Figure B-2)
- Reagents: Xylene
- Procedure:
1. Sample size should be approximately 50 grams of a representative sample of agglomerates.
  2. Weigh the distillation flask to the nearest 0.001 gram. Add a few boiling stones, tare the flask, and add approximately 50 grams of agglomerate sample and weigh again to the nearest 0.001 gram.
  3. Add approximately 250 ml of xylene to the distillation flask. Assemble the distillation apparatus as in Figure B-2, ensuring all connections are vapor tight.
  4. Apply heat and continue distillation until the water level has remained constant for 15 minutes or until no sign of water dripping into separator. Discontinue heating and add three drops of isopropyl alcohol around the inside rim of the condenser to bring water droplets adhering to the glass surface of the condenser down into the trap.
  5. Allow the trap and contents to cool down to room temperature. Estimate the volume of water in the trap to the nearest 0.05 ml.
- Calculations: The moisture content of agglomerates is given by:

$$\% \text{ Moisture} = \frac{V}{W} \times 100$$

Figure B-2: Apparatus for Azeotropic Distillation of Water

where:

V = Volume of water retained in trap, ml.
(The density of water is assumed to be 1 kg/l)

W = Initial sample weight, grams.

DETERMINATION OF AGGLOMERATE HEAVY OIL CONTENT

- Scope: This procedure determines the bridging liquid content of agglomerates which have been previously dried to a constant weight at 105° C. The agglomerates are dried prior to this procedure since this soxhlet extraction procedure provides the amount of oil and water remaining present in the agglomerates.
- Summary: A dried agglomerate sample is separated into liquid and solids by refluxing with dichloromethane in a soxhlet extraction apparatus. The solvent recycles through the extraction thimble to dissolve oil and asphalt. The extractables are then determined gravimetrically by determining the solids retained in the extraction thimble and/or by evaporation of solvent from the dichloromethane solution of bridging liquid.
- Apparatus: Soxhlet extraction apparatus, rotovapor. Figure C-3.
- Reagents: Dichloromethane
- Procedure:
1. Sample should be approximately 15 grams of a representative sample of dried agglomerates.
  2. Prior to use, dry extraction thimble for one hour at 105° C and store in a desiccator for 15 minutes.
  3. Weigh the extraction thimble to the nearest 0.001 gram. Fill with the agglomerate sample and weigh again to the nearest 0.001 gram.
  4. Weigh the extraction flask to the nearest 0.001 gram and add approximately 300 ml dichloromethane to the flask. Place the thimble in the extractor and assemble the apparatus as in Figure C-1, ensuring all connections are vapor tight.
  5. Place a 1/2" piece of glass rod in the bottom of the Soxhlet reservoir. This will assure the solvent is not lost over the top of the thimble.
  6. Set the powerstat controller at 35 and turn the heat on. This assures a steady reflux, but not so vigorous that solvent escapes through the condenser (if this happens the level in the flask will decrease and the solvent may evaporate).

7. Let the extraction proceed until the dichloromethane wash in the extractor is clear. The extraction can go overnight as long as there's no danger of the solvent completely evaporating.
8. Turn the extraction off and let reflux stop. Carefully remove the thimble and allow any excess dichloromethane to drain.
9. Place the thimble in a small beaker and place in oven. Dry at least three hours at 105° C.
10. Remove dried sample to desiccator. Leave in desiccator for 15 minutes and weigh.

Calculations:

$$\% \text{ oil} = \frac{\text{initial sample wt} - \text{extracted sample wt}}{\text{initial sample wt}} \times 100$$

NOTES:

Fibrous thimbles absorb moisture rapidly (about 5 mg/minute). Therefore it is important to weigh samples consistently and as quickly as possible. Practice the same procedure for weighing clean thimbles and thimbles with extracted samples.

The dichloromethane in the extractor may be used three or four times assuming it is not to be used for recovering the oil it retains from the extraction.

Overnight extractions are common procedure but the extraction may be discontinued when the dichloromethane in the Soxhlet reservoir becomes clear indicating no more oil is being removed. This assumes the oil departs a noticeable color to the dichloromethane.

Do not allow the dichloromethane to overflow in the thimble as this may cause mechanical loss of sample. The glass rod in the extractor should raise the thimble such that the top of the thimble is slightly above the siphon tube. Thus its purpose is to prevent overflow.

Figure B-3: Apparatus for Soxhlet Extraction of Heavy Oil

AGGLOMERATE TOTAL OIL DETERMINATION CALCULATION

In order to determine the water and oil content of agglomerated products the combination of three different laboratory procedures is necessary.

First, a representative sample is obtained and the total volatiles evaporated at 105 degrees centigrade is determined. This total volatiles represents all of the water present in the sample along with some of the lighter fractions of hydrocarbons present in the agglomerating liquids.

Second, a similar representative sample is processed for water content determination. This water extraction procedure, while removing all the volatiles in the process, provides the amount of water only which is present in the sample.

Third, the product of the total volatiles determination is subjected to the Soxhlet extraction procedure which determines the amount of oil and water present in the sample. Since all of the water and some of the oil has already been removed during volatiles determination this provides percent oil remaining.

To determine the total oil in the original agglomerates the following equation can be used once all of the above results are calculated on the same basis:

$$\text{Total oil} = \% \text{ total volatiles} - \% \text{ water} + \% \text{ oil}$$

DETERMINATION OF DIESEL FUEL AND ASPHALT RATIO IN COLLOID MILL FEED

SCOPE:

This method determines the distillable oil content from mixtures of asphalt and No. 2 diesel fuel. The oil content is related directly to the amount of asphalt and diesel fuel in the mixture.

SUMMARY:

The sample is distilled under vacuum (0.10 mm Hg) until the distillation flask reaches 600° F. These conditions remove distillable components that boil to 1050° F, which includes all of the No. 2 fuel oil but only a small percentage of the asphalt. In order to get the asphalt and diesel fuel composition, the distillable oil content has to be calibrated using known mixtures of asphalt and No. 2 diesel fuel.

APPARATUS:

Distillation flask with thermowell, vacuum pump, vacuum gauge, and temperature controller. (See Figure B-4)

PROCEDURE:

1. The sample size should be 100 +/- 10.0 grams
2. Add about six boiling stones to a 500-ml round-bottom flask with thermowell.
3. Weigh the flask and add the sample.
4. Attach the flask to the distillation apparatus as shown in figure C-4. Insulate the flask with heating mantles.
5. Turn on the vacuum pump and close the vacuum valve. This may have to be done slowly or in increments depending on sample thickness (see note 1).
6. Set heat controllers (rheostats) at 75% and turn on. This will allow for a slow, controlled heat up.
7. Depending on the sample, distillable oils will immediately start coming over. Make sure these oils do not block the exit of the oils into the receiver (see note 2).
8. The controller is set to cycle on and off at 600° F. When it has reached this temperature make sure the vacuum has been achieved and that no more oil is distilling over.
9. Turn the heat off and slowly release the vacuum.

10. Remove the flask and weigh immediately.

CALCULATIONS:

$$\% \text{ Oil} = \frac{\text{Wt. flask} + \text{sample} - (\text{Wt. flask} + \text{sample after test})}{\text{Wt. flask} + \text{sample} - \text{Wt. flask}} \times 100$$

The oil value is then used to calculate the #2 diesel and asphalt content by using the following linear regression equation:

$$Y = 119.69 - 1.175X$$

where Y = wt % asphalt in the sample

where X = distillable oil in the sample

- Note 1. The vacuum regulation should be done slowly as not to allow the residue in the pot to bump over. This can easily happen and is indicated by a sudden burst of black residual into the claisen head.
- Note 2. Heavy oils tend to clog the distillation path. This will give a false vacuum reading. A heat gun can be used to clear the path.

Figure B-4: Apparatus for Vacuum Distillation of Diesel and Asphalt

AGGLOMERATE DROP SHATTER TEST

SCOPE:

This method of drop shatter test covers the determination of the relative size stability and its complement, the friability, of sized coal.

SUMMARY:

The agglomerates are poured through a two inch diameter tube and allowed to drop six feet. This procedure is repeated up to 10 times with an initial size distribution of the agglomerates to be compared with a final size distributions after two and ten drops.

APPARATUS:

Six feet of plastic tube of two inch diameter.

PROCEDURE:

1. Sample size should be at least 50 grams of a representative sample of agglomerates.
2. Determine PSD of initial sample.
3. Pour the recombined sample through the tube allowing the sample to collect in a container underneath the tube.
4. Repeat step 3.
5. Determine PSD of the sample after these two drops taking care to prevent further breakage of the agglomerates.
6. Repeat step 3 eight more times or until a total of ten drops have been completed.
7. Determine PSD again after these ten drops.

CALCULATIONS:

The effect of drop tests on the particle size distribution is quantified by comparison of the various PSD's determinations made before and after drop tests. In general, the change in the percentage of fine material (-1 mm) present is the basis used since this represents the fines generated during the drop test.

TUMBLE TEST FOR AGGLOMERATES

SCOPE:

This test is a measure of the resistance of the coal to breakage upon impact and abrasion as the coal rubs together and against the walls of a cylindrical tumbler vessel.

APPARATUS:

One iron cylindrical vessel of uniform dimension, 7 1/4" in diameter and 7 1/4" in depth inside measurements.

PROCEDURE:

A sample size of approximately 100 grams is prepared by screening on appropriate sized screens for an initial particle size distribution (PSD). The distributions are then recombined and placed in the cylindrical tumbler. The tumbler is then rotated at 40 RPM for 30 minutes at which time the sample is removed and the PSD again determined. The sample is then recombined and tumbled two more times as described above with PSD determinations made after each tumble.

CALCULATIONS:

The effect of tumbling on the particle size distribution is quantified by comparison of the various PSD determinations made before and after tumbling. In general, the change in the percentage of fine material (-1 mm) present is the basis used since this represents the fines generated during tumbling.

APPENDIX C
CDTF LABORATORY TEST DATA

SAMPLE IDENTIFICATION LEGEND

SAMPLE LOCATION ABBREVIATIONS	SAMPLE LOCATION DESCRIPTION
CF	COAL FEED
PBM	PRIMARY BALL MILL PRODUCT
SBM	SECONDARY BALL MILL PRODUCT
FFL	FLOTATION FEED (LEFT)
FFR	FLOTATION FEED (RIGHT)
FFC	FLOTATION FEED (COMPOSITE)
RUF	ROUGHER FLOTATION PRODUCT
SCVR	SCAVENGER FLOTATION PRODUCT
FT	FLOTATION TAILINGS
LS1P	1200 GALLON LOW SHEAR PRODUCT
LS1U	1200 GALLON LOW SHEAR UNDERFLOW
LS2P	800 GALLON LOW SHEAR PRODUCT
LS2U	800 GALLON LOW SHEAR UNDERFLOW
SBT	SIEVE BEND TAILINGS
SBP	SIEVE BEND PRODUCT / VIBRATING SCREEN FEED
VSP	VIBRATING SCREEN PRODUCT
VST	VIBRATING SCREEN TAILINGS
BP	BIRD SCREEN BOWL CENTRIFUGE PRODUCT
BE	BIRD SCREEN BOWL CENTRIFUGE SCREEN EFFLUENT
BC	BIRD SCREEN BOWL CENTRIFUGE CENTRATE
FPP	FILTER PRESS PRODUCT
FPPC	FILTER PRESS PRODUCT COMPOSITE
EP	EIMCO HORIZONTAL BELT VACUUM FILTER PRODUCT
EF	EIMCO HORIZONTAL BELT VACUUM FILTER FILTRATE
CW	CLARIFIED WATER
CMF	COLLOID MILL FEED (ASPHALT/DIESEL BLEND)
CMP	COLLOID MILL PRODUCT (ASPH/DIES/WATER BLEND)

NOTE: FOR BIRD PRODUCT (BP) - 3, 4, & 6 INDICATE FEED PUMP
SPEEDS OF 30, 40, & 60 HZ
- L & H INDICATE LOW AND HIGH WEIR
SETTINGS

Run ID	Sample ID	Sample Time	Flowrate lb/min	Volatiles Solid% at 105 C	Ash% TS%	O11% (dried)	O11% Total	Water%	Diesel%	Asphalt%	PH	Size Distribution		
												D20	D50	D80
T4	T4-VSP-3	180			4.80	1.17						3362	4166	4650
	T4-VST-4	180		.52	7.57	.98								
	T4-VSP-5	240		40.32	7.43	1.19						1073	1447	2317
T5	T5-VSP-1	85			19.62	8.54	1.56	14.74				1049	1309	1648
	T5-VSP-3	85			26.49	9.14	1.30	14.74				3409	4127	4552
	T5-CF-1	130			5.34	15.38	2.70					321	939	2134
	T5-CMF-1	130								62.10				
	T5-FFC-1	130		18.34										
	T5-FT-1	130		.38		66.37	6.24							
	T5-LS1P-1	130		22.97										
	T5-LS1U-1	130		22.86										
	T5-PBM-1	130		51.87								28	151	281
	T5-RUF-1	130		23.09		7.47	.91							
	T5-SBP-1	130		78.00										
	T5-SCVR-1	130		29.65		9.59	1.12							
	T5-VSP-1	130			19.62	8.54	1.56					1049	1309	1648
	T5-VSP-2	130			13.78	9.46	1.43					1810	2169	2392
	T5-VST-1	130		2.61										
	T5-VSP-3	175			26.49	9.14	1.30	14.14				3409	4127	4552
	T5-VSP-4	175			29.79	9.38	1.35	14.14				3385	4128	4571
	T5-CF-2	190			4.69							445	1311	2746
	T5-FFC-2	190		21.83										
	T5-FT-2	190		.88		51.73	1.14							
	T5-LS1P-2	190		25.15										
	T5-LS1U-2	190		31.55										
	T5-PBM-2	190		52.35								47	148	291
	T5-RUF-2	190		19.56										
	T5-SBP-2	190		73.00										
	T5-VSP-2	190			13.78	9.46	1.43					1810	2169	2392
	T5-VSP-4	190			29.79	9.38	1.35					3385	4128	4571
	T5-VST-2	190		4.41		23.48	1.99							
T6	T6-CF-1	135			4.86	12.64	1.52					401	1094	2308
	T6-FFC-1	135		14.44										
	T6-FT-1	135		.26		57.22	1.43							
	T6-PBM-1	135		49.28								33	135	278
	T6-RUF-1	135		22.32		6.67	1.12							
	T6-SCVR-1	135		17.19		16.82	1.79							
	T6-CF-2	180			4.91	10.10	1.81					583	1447	2914
	T6-CW-2	180								5.7				
	T6-FFC-2	180		14.29										
	T6-FT-2	180		.24		70.10	1.71							
	T6-LS1P-2	180		21.67		7.85	1.45					412	663	999
	T6-LS2P-2	180		20.79		7.76	1.39					511	678	902
	T6-PBM-2	180		50.20								29	131	280
	T6-RUF-2	180		21.72		7.33	1.05							
	T6-SBT-2	180		.11		26.10	1.35							
	T6-SCVR-2	180		18.02		17.39	1.69							
	T6-VSP-2	180			27.61	7.46	1.36	15.40				419	634	885
	T6-VST-2	180				23.28	1.99							
T7	T7-CF-1	240			4.65	10.59	1.93					772	1828	3752
	T7-CW-1	240									4.8			

Run ID	Sample ID	Sample Time	Flowrate lb/min	Volatiles Solid%	at 105 C	Ash% TSX	Oil% (dried)	Oil% Total	Water%	Diesel%	Asphalt%	PH	Size Distribution		
													D20	D50	D80
T7	T7-FFC-1	240			19.09										
	T7-FT-1	240			.51	41.71	1.06								
	T7-LS1P-1	240		23.44											
	T7-LS2P-1	240		21.93									451	606	799
	T7-PBM-1	240			51.81	7.51	1.17						27	142	290
	T7-RUF-1	240			22.40	7.67	.98								
	T7-SCVR-1	240			6.10	28.13	1.48								
	T7-VSP-1	240			30.76	7.85	1.14						411	575	778
T8	T8-LS2P-1	90		22.47									331	477	713
	T8-VSP-1	90			36.70								370	520	727
	T8-LS2P-2	120		21.98				12.80					424	606	838
	T8-VSP-2	120			36.17	7.93	1.43						423	608	837
	T8-CF-1	150			4.41	11.83	1.27						551	1541	3419
	T8-LS2P-3	150		22.54									495	694	955
	T8-PBM-1	150		43.83									20	135	299
	T8-VSP-4	180			28.68	7.93	1.37						558	786	1001
	T8-VSP-5	210			29.57								497	735	987
	T8-CF-2	240			6.11	10.55	1.81						335	750	1400
	T8-CW-1	240										4.6			
	T8-FFC-1	240		13.41											
	T8-FT-1	240		.99		49.98	1.48								
	T8-LS1P-1	240		23.61		9.09	1.49	10.44							
	T8-PBM-2	240		43.55									23	131	287
	T8-RUF-1	240		23.73		6.81	1.19								
	T8-SCVR-1	240		11.64		24.69	2.66								
	T8-VSP-6B	240			24.28	8.71	1.32								
	T8-CMF-2	270									69.50				
	T8-CMP-2	270							49.90						
	T8-LS2P-5	270		22.26									322	521	863
	T8-VSP-7	270			32.38								331	546	893
T9	T9-LS2P-1	90		16.69									566	749	1028
	T9-VSP-1A	90			31.32			13.86							
	T9-CF-1	150			6.16	15.31	2.24						394	787	1486
	T9-SBM-2	150		42.80									12	73	137
	T9-VSP-3A	150													
	T9-LS2P-3	180		19.14									241	319	445
	T9-VSP-4A	180			37.03										
	T9-VSP-7B	270													
	T9-CF-2	330			7.38	10.55	1.92						381	782	1482
	T9-CMF-2	330									53.90				
	T9-CMP-2	330							42.60						
	T9-CW-2	330										4.3			
	T9-FFC-1	330		16.89											
	T9-FT-1	330		.44		81.16	1.51								
	T9-LS2P-8	330		23.46									243	320	417
	T9-RUF-1	330		17.00		8.55	1.36								
	T9-SCVR-1	330		4.69		38.80	4.15								
	T9-VSP-9A	330			24.03	8.70	1.55								
T10	T10-VSP-5A	180				8.40	1.38								
	T10-CF-1	210			4.50								440	1191	2305
	T10-CW-1	210										4.5			

Run ID	Sample ID	Sample Time	Flowrate lb/min	Volatiles Solid% at 105 C	Ash% TSX	Oil% (dried)	Oil% Total	Water% Diesel% Asphalt%	PH	Size Distribution		
										D20	D50	D80
T10	T10-FFC-1	210		16.98								
	T10-FT-1	210		.11	78.24							
	T10-LS1P-1	210		16.34								
	T10-SBM-1	210		43.83	14.90	1.52				15	69	159
	T10-SCVR-1	210		6.58								
	T10-VSP-6A	210			9.34	1.45						
T11	T11-FFP1-1	115		46.97								
	T11-FFP2-1	115		42.86								
	T11-FFP3-1	115		46.49								
	T11-FFP4-1	115		46.03								
	T11-FFP5-1	115		35.76								
	T11-FFPC-1	115		40.82			2.97	5.77	38.02			
	T11-LS1P-1	160		18.46								
	T11-LS1P-2	190		18.37								
	T11-CF-1	220		7.17								
	T11-FFC-1	220		14.36	10.12	1.46						
	T11-FT-1	220		.59	63.56	2.43						
	T11-LS1P-3	220		17.41								
	T11-RUF-1	220		18.62	6.83	1.14						
	T11-SBM-1	220		46.34	10.16	1.50				13	58	154
	T11-SCVR-1	220		10.06	19.23	2.32						
T12	T12-BC-1	150	258.0	2.43	7.49	1.27						
	T12-BE-1	150	19.6	13.20								
	T12-BP-1	150	67.6		24.90		3.43	3.84	24.49		150	243
	T12-CF-1	150			7.19					235	629	1505
	T12-FPF-1	150		.01								
	T12-FPP1-1	150		23.62								
	T12-FPP2-1	150		29.63								
	T12-FPP3-1	150		31.52								
	T12-FPP4-1	150		33.43								
	T12-FPP5-1	150		36.24								
	T12-FPPC-1	150		32.92	8.58	1.33				115	377	
	T12-FT-1	150		.88	56.50	1.96						
	T12-LS2P-1	150		18.08								
	T12-SBM-1	150		44.99	10.76	1.36				12	66	159
T13	T13-BC6H-1	90	245.6	2.32								
	T13-BE6H-1	90	18.3	5.87								
	T13-BP6H-1	90	77.2		24.41							
	T13-LS2P-1	90		17.19								
	T13-BC4H-1	115	221.8	1.75								
	T13-BE4H-1	115	16.5	5.21								
	T13-BP4H-1	115	55.5		25.25							
	T13-BC3H-1	135	182.6	.78								
	T13-BE3H-1	135	15.5	6.42								
	T13-BP3H-1	135	32.9		27.46							
	T13-BC6L-1	255	367.6	2.69								
	T13-BE6L-1	255	9.9	11.02								
	T13-BP6L-1	255	52.7		19.49	8.95	1.28					
	T13-LS2P-2	255		15.32								
	T13-CF-1	270		5.82	10.25	1.67				375	1086	2245
	T13-FT-1	270		.38	77.29	2.84						

Page 5

[illegible]

Run ID	Sample ID	Sample Time	Flowrate lb/min	Volatiles			O11% (dried)		O11% Total			PH	Size Distribution		
				Solid% at 105 C	Ash% TS%			Water%	Diesel%	Asphalt%	D20		D50	D80	
T16	T16-FPP2-1	385		34.12											
	T16-FPP3-1	385		31.43											
	T16-FPP4-1	385		33.63											
	T16-FPP5-1	385		30.32											
	T16-FPPC-1	385		32.53	9.68	1.27	2.89	3.40	32.02						
T17	T17-EF-1	115	88.0	.01											
	T17-EP-1	125	41.4		21.17	8.67	1.43								
	T17-EF-2	135	177.3	.05											
	T17-EP-2	135	33.5		21.26	8.78	1.39								
	T17-EF-3	155	150.0	.04											
	T17-EP-3	160	49.6		21.76	8.46	1.33								
	T17-CF-1	170		4.63									561	1529	3007
	T17-FFC-1	170		14.40		10.22	1.20								
	T17-FT-1	170		.39		64.60	1.16								
	T17-LS1P-1	170		19.70				6.14					145	228	338
	T17-PBM-1	170		44.95		10.89	1.37						24	138	298
	T17-RUF-1	170		24.24		7.01	1.13								
	T17-SCVR-1	170		8.47		20.07	1.70								
	T17-EF-4	185	140.4	.03											
	T17-EP-4	190	44.1		20.77	8.72	1.37	5.59	7.30	19.06			120	254	353
T18	T18-CF-1	95		6.71									420	1022	2074
	T18-FFC-1	95		16.78		10.88	1.38								
	T18-FT-1	95		.34		78.51	1.29								
	T18-RUF-1	95		19.00		7.13	1.09								
	T18-SBM-1	95		43.52		10.38	1.35						9	51	149
	T18-SCVR-1	95		1.97		30.84	2.82								
	T18-EF-1	130	207.4												
	T18-EP-1	130	52.4		27.76	8.01	1.37	6.86							
	T18-EF-2	140	219.2												
	T18-EP-2	140	54.4		26.98										
	T18-EF-3	170	211.0												
	T18-EP-3	170	46.8		24.96										
	T18-EF-4	180	171.3												
	T18-EP-4	180	34.4		24.55			5.91	7.09	23.37			119	269	332
	T18-CMF-1	185									55.90	44.10			
	T18-CMP-1	185								34.40					
	T18-LS1P-1	185		13.99		8.57	1.06							143	269
	T18-EF-5	245	180.5												
	T18-EP-5	245	43.6		29.61	8.46	1.14								
	T18-CMF-2	260									53.90	46.10			
	T18-CMP-2	260								44.70					
	T18-EF-6	260	202.0												
	T18-EP-6	260			25.12			3.02	4.47	23.67			218	297	343
	T18-CW-1	265										4.5			
	T18-FFC-2	265		18.20		11.49	1.21								
T18-FT-2	265		.76		73.88	1.25									
T18-LS1P-2	265		14.91		8.65	1.13						90	151	232	
T18-RUF-2	265		19.70		7.73	.95									
T18-SCVR-2	265		2.76		29.03	1.75									
T18-EF-7	275	197.0													
T18-EP-7	275	44.6		25.54											

8/02/91

CDTF Sample Data

Page 8

Run ID	Sample ID	Sample Time	Flowrate lb/min	Volatiles Solid% at 105 C	Ash% TSX	Oil% (dried)	Oil% Total	Water%	Diesel%	Asphalt%	PH	Size Distribution		
												D20	D50	D80
T19	T19-EF-1	145	92.0											
	T19-EP-1	145	19.6	24.97	10.03	1.42	1.89	2.34	24.52					
	T19-FFC-1	145		15.72	11.17	1.24								
	T19-FT-1	145		.37	76.09	1.56								
	T19-LS1P-1	145		17.50	9.09	1.19							144	
	T19-RUF-1	145		19.68	7.34	1.11								
	T19-SCVR-1	145		9.45	23.36	2.62								
	T19-CMP-1	150												
T20	T20-EP-1	60	32.0	22.68	8.70	1.48	1.78	2.35	22.11				151	
	T20-EF-1	65	114.0											
	T20-LS1P-1	65		18.56	8.26	1.22								
	T20-CF-1	110		5.26								341	902	1922
	T20-FFC-1	110		17.87										
	T20-FT-1	110		.34	11.33	1.60								
	T20-RUF-1	110		19.51	7.29	1.22								
	T20-SBM-1	110		41.33	10.99	1.38						11	56	153
	T20-SCVR-1	110		9.06	21.31	2.19								
	T20-CMP-1	140						48.00						
	T20-LS1P-2	170		18.70	8.96	1.29								
	T20-EF-2	185	156.3											
	T20-EP-2	185	50.4	22.82	8.73	1.36	2.61	3.52	21.91			97	157	223
	T20-BC4H-1	190	153.0	1.11										
	T20-BP4H-1	190	44.2	18.86	8.99	1.29	2.58	5.45	15.99			202	268	327
	T20-BC6H-1	210	246.3	2.43										
	T20-BP6H-1	210	30.0	18.52	8.58	1.30						240	303	342
T21	T21-CMP-1	260							42.57					
	T21-CMP-2	290							49.65					
T22	T22-CMF-1	140								46.23	53.77			
	T22-CMP-1	140						36.90						
	T22-CF-1	180		4.49								245	737	1691
	T22-SBM-1	180		40.54	10.62	1.21						20	73	156
	T22-FFC-1	200		15.65	10.55	1.14								
	T22-FT-1	200		.43	75.27	1.34								
	T22-RUF-1	200		20.63	7.09	1.04								
	T22-SCVR-1	200		17.07	22.67	2.19								
	T22-LS2P-1	215		23.95	7.22	1.29								
	T22-SBT-1	215		.12	67.07									
	T22-VST-1	215		1.00	18.57	1.76								
	T22-VSP-1	230		26.43	7.39	1.30						630	781	945
	T22-VSP-1D	230		24.26			11.48	13.39	22.35					
	T22-EF-1	255	194.0											
	T22-EP-1	255	65.2	18.26	7.25	1.24	11.84	14.35	15.75			578	849	1077
	T22-CMF-2	270								49.64	50.36			
	T22-CMP-2	270						39.90						
	T22-BC4H-1	275	217.4	.05										
	T22-BP4H-1	275	54.5	16.22	7.44	1.24	12.59	14.80	14.01			140	304	774
	T22-BC6H-1	295	277.2	.11										
	T22-BP6H-1	295	49.9	16.56	7.32	1.21	12.52	15.96	13.12			145	305	689
T23	T23-CF-1	135		5.11										
	T23-FFC-1	135		17.02	10.00	1.04								

Run ID	Sample ID	Sample Time	Flowrate lb/min	Volatiles Solid% at 105 C	Ash% TSX	Oil% (dried)	Oil% Total	Water%	Diesel%	Asphalt%	PH	Size Distribution		
												D20	D50	D80
T23	T23-FT-1	135		.50	61.57	1.44								
	T23-PBM1-1	135		47.02	10.29	1.10								
	T23-RUF-1	135	356.0	25.19	6.68	.83								
	T23-SCVR-1	135	71.8	4.11	24.79	1.15								
	T23-FT-2	315	452.8	.73	48.73	1.15								
	T23-SBT-1	315		.23	34.14	1.19								
	T23-VST-1	315		.61	19.80	1.06								
	T23-EP-1	335	46.9		14.64	6.99	.91	9.22	10.40	13.46		569	813	1093
	T23-BC4H-1	345	241.2	.12										
	T23-BP4H-1	345	52.8		11.40	6.88	.94	8.41	9.80	10.01		171	328	660
	T23-CMF-1	345								1.20				
	T23-CMP-1	345								27.45				
	T23-LS2P-1	345		23.73		1.00								
	T23-VSP-1	345			26.08	7.08	.89	8.51	9.16	25.43		501	719	1150
	T23-VSP-1D	345			24.16			8.96	10.79	22.33				
	T23-BC6H-1	390	353.1	.22										
	T23-BP6H-1	390	114.0		12.17	6.97	.95	8.37	10.18	10.36		213	368	810
T24	T24-EF-1	115	62.4											
	T24-EP-1	115	21.2		26.33	8.41	.96	2.13	2.72	25.74			143	328
	T24-LS2P-1	115		19.41		7.98	.91							
	T24-CF-1	130			5.33							451	1290	2852
	T24-FFC-1	130		14.42		9.64	.94							
	T24-FT-1	130		.75	47.32	1.61								
	T24-PBM-1	130		44.65	10.79	1.13						35	141	305
	T24-RUF-1	130		24.25		6.05	.84							
	T24-SCVR-1	130		6.15	19.30	1.60								
	T24-EF-2	190	83.2											
	T24-EP-2	190	38.2		23.90	7.52	.92	3.34	5.27	21.97			142	313
	T24-LS2P-2	190		19.10		7.44	.87							
	T24-BC4H-1	240	173.8	.75										
	T24-BP4H-1	240	55.8		16.78	7.64	.91	2.53	4.11	15.20		185	262	340
	T24-CMP-1	250								49.51				
	T24-BC6H-1	265	227.4	.95										
	T24-BP6H-1	265	59.4		17.79	8.04	.94	2.13	3.28	16.64		186	243	335

APPENDIX D
LABORATORY BINDER TEST DATA

8/02/91

TEST PROCEDURES AND REPORTS

Page 1

Serial Number: 1
Sample Number: 1.3-3

Test Date: 10/09/90

Test Series: Binder Evaluation Tests

Feed Coal Seam: Ufp, weight 165.40 g, with a moisture content of %
Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	% Temp	Impeller	RPM Type	% Temp			
1	4	4	Conditioning					Rushton	1800 Low	15			
2	10	6	Oil Addition			Diesel	2	Rushton	2400 High	15		Flocs	
3	20	10	Oil Addition			FuelOil6	3	Rushton	2400 High	15		Flocs	
4	30	10	Oil Addition			FuelOil6	3	Rushton	2400 High	15		Flocs	
5	40	10	Oil Addition			FuelOil6	3	Rushton	2400 High	15		Flocs	
6	50	10	Oil Addition			FuelOil6	3	Rushton	2400 High	15		Inversion	
7			De-ash, 200M,					Rushton	2400 High	15		Screened	
8			Changed Impeller to 3 blade										
9	2	2	Oil Addition			FuelOil6	3	Turbine	2400 High	15		Flocs	
10	22	20	Low Shear					Turbine	1800 Low	15		Flocs	
11	24	2	Oil Addition			FuelOil6	3	Turbine	2400 High	15		Flocs	
12	44	20	Low Shear					Turbine	1800 Low	15		Flocs	
13	46	2	Oil Addition			FuelOil6	3	Turbine	2400 High	15		Flocs	
14	66	20	Low Shear					Turbine	1800 Low	15		Flocs	
15	68	2	Oil Addition			FuelOil6	3	Turbine	2400 High	15		Flocs	
16	88	20	Low Shear					Turbine	1800 Low	15		Flocs	
17	90	2	Oil Addition			FuelOil6	3	Turbine	2400 High	15		No Flocs, 1 mm Agglomerates	
18	110	20	Low Shear					Turbine	1800 Low	15		1 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 50 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 50 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 110 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 2

Serial Number: 2

Sample Number: 1.3-5

Test Series: Binder Evaluation Tests

Test Date: 10/09/90

Feed Coal Seam: Ufp, weight 163.10 g, with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step-1		Time, min-		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4	Conditioning						Rushton	2400	High	15	
2	10	6	Oil Addition			Diesel	2		Rushton	2400	High	15	Flocs
3	20	10	Oil Addition			FuelOil6	3		Rushton	2400	High	15	Flocs
4	30	10	Oil Addition			FuelOil6	3		Rushton	2400	High	15	Inversion
5			De-ash										
6			Changed Impeller to 3 blade						Turbine				
7	2	2	Oil Addition			FuelOil6	3		Turbine	2400	High	15	Flocs
8	22	20	Low Shear						Turbine	1800	Low	15	Flocs
9	24	4	Oil Addition			FuelOil6	3		Turbine	2400	High	15	Flocs
10	44	20	Low Shear						Turbine	1800	Low	15	Flocs
11	46	2	Oil Addition			FuelOil6	3		Turbine	2400	High	15	Flocs
12	66	20	Low Shear						Turbine	1800	Low	15	No Flocs
13	68	2	Oil Addition			FuelOil6	3		Turbine	2400	High	15	No Flocs
14	88	20	Low Shear						Turbine	1800	Low	15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 30 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 30 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 88 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 3

Serial Number: 3

Sample Number: 1.4-1

Test Series: Binder Evaluation Tests

Test Date: 10/16/90

Feed Coal Seam: Ufp, weight 157.56 g, with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step-Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res			Type	%	Temp	Impeller RPM	Type	%	Temp	
1	4	4	Conditioning				Rushton	2400	High	15	
2	10	6	Oil Addition	Diesel	2		Rushton	2400	High	15	
3	14	4	Oil Addition	FuelOil 15	13		Rushton	2400	High	15	Inversion
4			De-ash, 200M, 500ml water								
5			Repulp								
6	2	2	Oil Addition	FuelOil 15	5		Rushton	2400	High	15	
7	62	60	Changed Impeller to 3 blade				Turbine	1800	Low	15	Flocs
8	122	60	Low Shear				Turbine	1800	Low	15	Flocs
9	182	60	Low Shear				Turbine	1800	Low	15	No Flocs/No Growth
10	184	2	Oil Addition	FuelOil 15	6		Turbine	2400	High	15	
11	229	45					Turbine	1800	Low	15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 14 min
 Inversion Time: 14 min
 Residence Time in Low shear: 229 min

Moisture Content Air Dried: 41.60 %
 Moisture by Distillation: %
 Oil by Solvent Extraction: %

Strength Index:
 Abrasion Index:
 Consolidation Index:
 Product D-50 in mm:

Serial Number: 4
Sample Number: 1.4-2

Test Series: Binder Evaluation Tests

Test Date: 10/17/90

Feed Coal Seam: Ufp, weight 158.95 g, with a moisture content of %
Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	% Temp	Impeller RPM	Type	% Temp			
1	4	4	Conditioning					Rushton	2400 High	15		Flocs	
2	10	6	Oil Addition			Fueloil 6	2	Rushton	2400 High	15		Flocs	
3	14	4	Oil Addition			Fueloil 6	13	Rushton	2400 High	15		Flocs	
4			De-ash, 200ml water									Screened	
5			Repulp										
6	2	2	Oil Addition			Fueloil 6	6	Rushton	2400 High	15		Flocs	
7	62	60	Changed Impeller to 3 blade					Turbine	1800 Low	15		Flocs, Inversion in 15 minutes.	
8	64	2	Oil Addition			Fueloil 6	2	Turbine	2400 High	15		Microagglomerates	
9	79	15	Low Shear					Turbine	1800 Low	15		Microagglomerates	
10	81	2	Oil Addition			Fueloil 6	2	Turbine	2400 High	15		Microagglomerates	
11	96	15	Low Shear					Turbine	1800 Low	15		Microagglomerates	
12	98	2	Oil Addition			Fueloil 6	2	Turbine	2400 High	15		1/3 - 1/2 mm Agglomerates	
13	113	15	Low Shear					Turbine	1800 Low	15		1 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 14 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 62 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 113 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 5

Serial Number: 5

Sample Number: 1.4-3

Test Series: Binder Evaluation Tests

Test Date: 10/17/90

Feed Coal Seam: Ufp, weight 162.53 g, with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step- Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res			Type	% Temp	Impeller RPM	Type	% Temp			
1	4	4	Conditioning			Rushton	2400 High	15			
2	10	6	Oil Addition	Diesel	2	Rushton	2400 High	15		Flocs	
3	14	4	Oil Addition	A2.3D1	13	Rushton	2400 High	15		Flocs	
4			De-ash, 200M, 500ml water							Screened	
5			Repulp								
6	2	2	Oil Addition	A2.3D1	5	Rushton	2400 High	15		Flocs, Inversion	
7	62	60	Changed Impeller to 3 blade			Turbine	1800 Low	15		Flocs	
8	64	2	Oil Addition	A2.3D1	2	Turbine	2400 High	15		Microagglomerates	
9	79	15	Low Shear			Turbine	1800 Low	15		Microagglomerates	
10	81	2	Oil Addition	A2.3D1	2	Turbine	2400 High	15		Microagglomerates	
11	96	15	Low Shear			Turbine	1800 Low	15		1 to 3 1/2 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 14 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 16 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 96 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product (30 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 6

Serial Number: 6

Sample Number: 1.4-7

Test Series: Binder Evaluation Tests

Test Date: 10/17/90

Feed Coal Seam: Ufp, weight 160.00 g, with a moisture content of %
 Feed Coal Ground for 5 min to a topsize of 28 mesh, with a D-50 of mm

Step- Time, min-		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res			Type	% Temp	Impeller RPM	Type	% Temp			
1	4	4	Conditioning			Rushton	Low	15			
2	10	6	Oil Addition	Diesel	2	Rushton	High	15		Flocs	
3	20	10	Oil Addition	FuelOil6	3	Rushton	High	15		Inversion	
4			De-ash, 200M								
5			Repulp								
6			Changed Impeller to 3 blade								
7	2	2	Oil Addition	FuelOil6	3	Turbine	High	15		Microagglomerates	
8	12	10	Low Shear			Turbine	Low	15		Microagglomerates	
9	14	2	Oil Addition	FuelOil6	3	Turbine	High	15		1/2 mm Agglomerates	
10	24	10	Low Shear			Turbine	Low	15		1/2 mm Agglomerates	
11	26	2	Oil Addition	FuelOil6	3	Turbine	High	15		1/2 mm Agglomerates	
12	36	10	Low Shear			Turbine	Low	15		1 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 20 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 20 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 36 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 7

Serial Number: 7
 Sample Number: 1.4-5
 Test Series: Binder Evaluation Tests
 Test Date: 10/18/90

Feed Coal Seam: Ufp, weight 175.43 g, with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step- Time, min-		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res			Type	% Temp	Impeller RPM	Type	% Temp			
1	4	4	Conditioning			Rushton	2400 High	15			
2	10	6	Oil Addition	Diesel	2	Rushton	2400 High	15		Flocs	
3	14	4	Oil Addition	A1.801	13	Rushton	2400 High	15		Flocs	
4			De-ash, 200M, 500ml water							Screened	
5			Repulp								
6	2	2	Oil Addition	A1.801	5	Rushton	2400 High	15		Inversion	
7	62	60	Changed Impeller to 3 blade			Turbine	1800 Low	15		No Flocs, Small growth of agglomerates	
8	64	2	Oil Addition	A1.801	2	Turbine	2400 High	15		Approximately 10% 1 mm Agglomerates	
9	79	15	Low Shear			Turbine	1800 Low	15		Approximately 10% 1 mm Agglomerates	
10	81	2	Oil Addition	A1.801	2	Turbine	2400 High	15		Approximately 10% 1 mm Agglomerates	
11	96	15	Low Shear			Turbine	1800 Low	15		Approximately 10% 1 mm Agglomerates	
12	98	2	Oil Addition	A1.801	2	Turbine	2400 High	15		Approximately 10% 1 mm Agglomerates	
13	113	15	Low Shear			Turbine	1800 Low	15		1/2 mm Agglomerates; Ended test as comparison	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 14 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 16 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 113 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

Serial Number: 8
Sample Number: 1.4-6

Test Series: Binder Evaluation Tests

Test Date: 10/22/90

Feed Coal Seam: Ufp, weight 175.77 g, with a moisture content of %
Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

-Step-		-Time, min-		-----Procedure-----		---Oil Properties---		---Shear Conditions---		---Slurry---		---Observations---	
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4	Conditioning						Rushton	2400	High	15	
2	10	6	Oil Addition			Diesel	2		Rushton	2400	High	15	
3	14	4	Oil Addition			A2.801	13		Rushton	2400	High	15	
4			De-ash, 200M, 500ml water										
5			Repulp										
6	2	2	Oil Addition			A2.801	5		Rushton	2400	High	15	
7	62	60	Changed Impeller to 3 blade						Turbine	1800	Low	15	
8	64	2	Oil Addition			A2.801			Turbine	2400	High	15	
9	79	15	Low Shear						Turbine	1800	Low	15	
10	81	2	Oil Addition			A2.801			Turbine	2400	High	15	
11	96	15	Low Shear						Turbine	1800	Low	15	
12	98	2	Oil Addition			A2.801			Turbine	2400	High	15	
13	113	15	Low Shear						Turbine	1800	Low	15	
Average size of 1mm Agglomerates, odd shaped.													

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	14 min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	113 min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 9

Serial Number: 9

Sample Number: 1.4-8

Test Series: Binder Evaluation Tests

Test Date: 10/22/90

Feed Coal Seam: Ufp, weight 172.50 g, with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step- Time, min-		Procedure-----		Oil Properties-----		Shear Conditions-----		Slurry-----		Observations-----	
No	Cum Res			Type	%	Temp	Impeller RPM	Type	%	Temp	
1	4	4	Conditioning				Rushton	2400	High	15	
2	10	6	Oil Addition	Diesel	2		Rushton	2400	High	15	
3	14	4	Oil Addition	A3.2D1	13		Rushton	2400	High	15	Flocs
4			De-ash, 200M, 500ml water								Screened
5			Repulp								
6	2	2	Oil Addition	A3.2D1	5		Rushton	2400	High	15	Flocs
7	62	60	Changed Impeller to 3 blade				Turbine	1800	Low	15	Flocs
8	64	2	Oil Addition	A3.2D1	2		Turbine	2400	High	15	No Flocs, Inversion
9	79	15	Low Shear				Turbine	1800	Low	15	1/3 mm Agglomerates
10	81	2	Oil Addition	A3.2D1	2		Turbine	2400	High	15	1/3 mm Agglomerates
11	96	15	Low Shear				Turbine	1800	Low	15	1/3 mm Agglomerates
12	98	2	Oil Addition	A3.2D1	2		Turbine	2400	High	15	1/2 mm Agglomerates
13	113	15	Low Shear				Turbine	1800	Low	15	1/2 mm Agglomerates
14	115	2	Oil Addition	A3.2D1	2		Turbine	2400	High	15	1/2 mm Agglomerates
15	130	15	Low Shear				Turbine	1800	Low	15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 14 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 78 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 130 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 10

Serial Number: 10
Sample Number: 2.2-1

Test Series: Binder Evaluation: Tests

Test Date: 10/24/90

Feed Coal Seam: Ufp, weight 169.28 g, with a moisture content of %
Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	% Temp	Impeller	RPM	Type	% Temp		
1	4	4		Conditioning				Rushton	2400	High	15		
2	10	6		Oil Addition		Diesel	2	Rushton	2400	High	15		Flocs
3	14	4		Oil Addition		A2.801	13	Rushton	2400	High	15		Flocs
4				De-ash, 200M, 500ml water									Screened
5				Repulp									
6	2	2		Oil Addition		A2.801	5	Rushton	2400	High	15		Flocs
7	62	60		Low Shear				Rushton	1800	Low	15		1/4 mm Agglomerates
8	64	2		Oil Addition		A2.801	2	Rushton	2400	High	15		1/4 mm Agglomerates
9	79	15		Low Shear				Rushton	1800	Low	15		1/3 mm - 1/2 mm Agglomerates
10	81	2		Oil Addition		A2.001							

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 14 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 81 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

Serial Number: 11

Sample Number: 2.2-4

Test Series: Binder Evaluation Tests

Test Date: 10/25/90

Feed Coal Seam: Ufp, weight 169.28 g, with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4	Conditioning						Rushton	2400	High	15	
2	10	6	Oil Addition			Diesel	2		Rushton	2400	High	15	Flocs
3	14	4	Oil Addition			A2.801	13		Rushton	2400	High	15	Flocs
4			De-ash, 200M, 500ml water										Screened
5			Reulp										
6	2	2	Oil Addition			A2.801	5		Rushton	2400	High	15	Flocs
7	62	60	Changed Impeller to 3 blade						Turbine	1800	Low	15	1/3 mm Agglomerates
8	64	2	Oil Addition			A2.801	2		Turbine	2400	High	15	1/3 mm Agglomerates
9	79	15	Low Shear						Turbine	1800	Low	15	1/3 mm Agglomerates
10	81	2	Oil Addition			A2.801	2		Turbine	2400	High	15	1/2 mm Agglomerates
11	96	15	Low Shear						Turbine	1800	Low	15	1/2 mm Agglomerates
12	98	2	Oil Addition			A2.801	2		Turbine	2400	High	15	1/2 mm Agglomerates
13	113	15	Low Shear						Turbine	1800	Low	15	1/2 mm - 3 1/2 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 14 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 113 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 12

Serial Number: 12

Sample Number: 3.2-2

Test Series: Binder Evaluation Tests

Test Date: 10/26/90

Feed Coal Seam: Ufp, weight 160.00 g, with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step-1 Time, min			Procedure			Oil Properties			Shear Conditions			Slurry			Observations		
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp				
1	4	4	Conditioning						Rushton	2400	High	15					
2	8	4	Oil Addition			Diesel	1		Rushton	2400	High	15				Flocs	
3	10	2	Oil Addition			A2.3D1	14		Rushton	2400	High	15				Flocs	
4			De-ash, 200M, 500ml water													Screened	
5			Repulp														
6	2	2	Oil Addition			A2.3D1	7		Rushton	2400	High	15				Flocs	
7	32	30	Changed Impeller to 3 blade						Turbine	1800	Low	15				Microagglomerates	
8	34	2	Oil Addition			A2.3D1	2		Turbine	2400	High	15				1/3 mm Agglomerates	
9	49	15	Low Shear						Turbine	1800	Low	15				1/3 mm Agglomerates	
10	51	2	Oil Addition			A2.3D1	2		Turbine	2400	High	15				1/2 mm Agglomerates	
11	66	15	Low Shear						Turbine	1800	Low	15				1 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	10 min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	66 min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 13

Serial Number: 13
Sample Number: 3.2-4

Test Series: Binder Evaluation Tests

Test Date: 10/26/90

Feed Coal Seam: Ufp, weight 159.39 g, with a moisture content of %
Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4	Conditioning						Rushton	2400	High	15	
2	8	4	Oil Addition			Diesel	1		Rushton	2400	High	15	Flocs
3	10	2	Oil Addition			A2.801	14		Rushton	2400	High	15	Flocs
4			De-ash, 200M, 500ml water										Screened
5			Repulp										
6	2	2	Oil Addition			A2.801	7		Rushton	2400	High	15	Inversion
7	32	20	Changed Impeller to 3 blade						Turbine	1800	Low	15	Microagglomerates
8	34	2	Oil Addition			A2.801	2		Turbine	2400	High	15	Microagglomerates
9	49	15	Low Shear						Turbine	1800	Low	15	Microagglomerates
10	51	2	Oil Addition			A2.801	2		Turbine	2400	High	15	1/3 mm Agglomerates
11	66	15	Low Shear						Turbine	1800	Low	15	1/2 mm Agglomerates
12	68	2	Oil Addition			A2.801	2		Turbine	2400	High	15	1/2 mm Agglomerates
13	83	15	Low Shear						Turbine	1800	Low	15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	10 min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	12 min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	83 min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 14

Serial Number: 14

Sample Number: 3.2-6

Test Series: Binder Evaluation Tests

Test Date: 10/29/90

Feed Coal Seam: Ufp, weight 164.66 g, with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step--Time, min--		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res			Type	%	Temp	Impeller RPM	Type	%	Temp	
1	4	4	Conditioning				Rushton	2400	High	15	
2	8	4	Oil Addition	Diesel	1		Rushton	2400	High	15	Flocs
3	10	2	Oil Addition	A3.2D1	14		Rushton	2400	High	15	Flocs
4			De-ash, 200M, 500ml water								Screened
5			Repulp								
6	2	2	Oil Addition	A3.2D1	7		Rushton	2400	High	15	Flocs
7	32	30	Changed Impeller to 3 blad				Turbine	1800	Low	15	Inversion
8	34	2	Oil Addition	A3.2D1	2		Turbine	2400	High	15	Microagglomerates
9	49	15	Low Shear				Turbine	1800	Low	15	Microagglomerates
10	51	2	Oil Addition	A3.2D1	2		Turbine	2400	High	15	1/3 mm Agglomerates
11	66	15	Low Shear				Turbine	1800	Low	15	1/3 mm Agglomerates
12	68	2	Oil Addition	A3.2D1	2		Turbine	2400	High	15	1/3 mm Agglomerates
13	83	15	Low Shear				Turbine	1800	Low	15	1/2 mm Agglomerates
14	85	2	Oil Addition	A3.2D1	2		Turbine	2400	High	15	1/2 mm Agglomerates
15	100	15	Low Shear				Turbine	1800	Low	15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 10 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 44 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 100 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 15

Serial Number: 15

Sample Number: 3.2-7

Test Series: Binder Evaluation Tests

Test Date: 10/30/90

Feed Coal Seam: Ufp, weight 169.63 g, with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4	Conditioning						Rushton	2400	High	15	
2	8	4	Oil Addition			Diesel	1		Rushton	2400	High	15	
3	10	2	Oil Addition			FuelOil6	2		Rushton	2400	High	15	Flocs
4			De-ash, 200M, 500ml water										Inversion
5			Repulp										Screened
6	2	2	Oil Addition			FuelOil6	7		Rushton	2400	High	15	Microagglomerates
7	32	30	Changed Impeller to 3 blade						Turbine	1800	Low	15	Microagglomerates
8	34	2	Oil Addition			FuelOil6	2		Turbine	2400	High	15	Microagglomerates
9	49	15	Low Shear						Turbine	1800	Low	15	Microagglomerates
10	51	2	Oil Addition			FuelOil6	2		Turbine	2400	High	15	1/3 mm Agglomerates
11	66	15	Low Shear						Turbine	1800	Low	15	1/3 mm Agglomerates
12	68	2	Oil Addition			FuelOil6	2		Turbine	2400	High	15	1/2 mm Agglomerates
13	83	15	Low Shear						Turbine	1800	Low	15	1/2 mm Agglomerates
14	85	2	Oil Addition			FuelOil6	2		Turbine	2400	High	15	1/2 mm Agglomerates
15	100	15	Low Shear						Turbine	1800	Low	15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 10 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 10 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 100 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 16

Serial Number: 16

Sample Number: 4.1-1

Test Series: Binder Evaluation Tests

Test Date: 11/05/90

Feed Coal Seam: Ufp, weight 161.04 g, with a moisture content of %
 Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step- Time, min-		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res			Type	% Temp	Impeller RPM	Type	% Temp			
1	4	4	Conditioning			Rushton	2400 High	15			
2	8	4	Oil Addition	Diesel	1	Rushton	2400 High	15		Flocs	
3	12	4	Oil Addition	A2.3D1	7	Rushton	2400 High	15		Inversion	
4			De-ash, 200M, 500 ml water							Screened	
5			Repulp								
6	2	2	Oil Addition	A2.3D1	3	Rushton	2400 High	15		Microagglomerates	
7	32	30	Low Shear			Rushton	1800 Low	15		1/2 mm Agglomerates	
8	34	2	Oil Addition	A2.3D1	3	Rushton	2400 High	15		1/2 mm Agglomerates	
9	49	15	Low Shear			Rushton	1800 Low	15		1 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 12 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 12 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 49 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 17

Serial Number: 17

Sample Number: 4.1-2

Test Series: Binder Evaluation Tests

Test Date: 11/05/90

Feed Coal Seam: Ufp, weight 162.11 g, with a moisture content of %

Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

-Step-		Time, min-		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4		Conditioning					Rushton	2400	High	15	
2	8	4		Oil Addition		Diesel	1		Rushton	2400	High	15	Flocs
3	10	2		Oil Addition		A2.301	7		Rushton	2400	High	15	Inversion
4				De-ash, 200M, 500ml water									Screened
5				Repulp									
6	2	2		Oil Addition		A2.301	3		Rushton	2400	High	15	1/3 mm Agglomerates
7	32	30		Changed Impeller					Turbine	1800	Low	15	1/3 mm Agglomerates
8	34	2		Oil Addition		A2.301	3		Turbine	2400	High	15	1/2 mm Agglomerates
9	49	15		Low Shear					Turbine	1800	Low	15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	10 min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	10 min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	49 min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

Serial Number: 18
Sample Number: 4.1-3

Test Series: Binder Evaluation Tests

Test Date: 11/05/90

Feed Coal Seam: Ufp, weight 162.50 g, with a moisture content of %
Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations
No	Cum Res					Type	% Temp	Impeller RPM	Type	% Temp		
1	4	4	Conditioning					Rushton	2400 High	15		
2	8	4	Oil Addition			Diesel	1	Rushton	2400 High	15		Flocs
3	12	4	Oil Addition			A2.801	7	Rushton	2400 High	15		Inversion
4			De-ash, 200M, 500ml water									Screened
5			Repulp									
6	2	2	Oil Addition			A2.801	3	Rushton	2400 High	15		1/3 mm Agglomerates
7	32	30	Changed Impeller to 3 blade					Turbine	1800 Low	15		1/3 mm Agglomerates
8	34	2	Oil Addition			A2.801	3	Turbine	2400 High	15		1/3 mm Agglomerates
9	49	15	Low Shear					Turbine	1800 Low	15		1/2 mm Agglomerates
10	51	2	Oil Addition			A2.801	3	Turbine	2400 High	15		1/2 mm Agglomerates
11	66	15	Low Shear					Turbine	1800 Low	15		1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 12 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 12 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 66 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 19

Serial Number: 19

Sample Number: 4.1-5

Test Series: Binder Evaluation Tests

Test Date: 11/07/90

Feed Coal Seam: Ufp, weight 160.33 g, with a moisture content of %
 Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res					Type	% Temp	Impeller RPM	Type	% Temp			
1	4	4	Conditioning					Rushton	2400 High	15			
2	8	4	Oil Addition			Diesel	1	Rushton	2400 High	15		Flocs	
3	12	4	Oil Addition			A3.2D1	7	Rushton	2400 High	15		Inversion	
4			De-ash, 200M, 500ml water									Screened	
5			Repulp										
6	2	2	Oil Addition			A3.2D1	3	Rushton	2400 High	15		1/3 mm Agglomerates	
7	32	30	Changed Impeller to 3 blad					Turbine	1800 Low	15		1/3 mm Agglomerates	
8	34	2	Oil Addition			A3.2D1	3	Turbine	2400 High	15		1/3 mm Agglomerates	
9	49	15	Low Shear					Turbine	1800 Low	15		1/2 mm Agglomerates	
10	51	2	Oil Addition			A3.2D1	3	Turbine	2400 High	15		1/2 mm Agglomerates	
11	66	15	Low Shear					Turbine	1800 Low	15		1 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	12 min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	12 min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	66 min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 20

Serial Number: 20

Sample Number: 4.1-6

Test Series: Binder Evaluation Tests

Test Date: 11/12/90

Feed Coal Seam: Ufp, weight 158.49 g, with a moisture content of %
 Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step - Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res			Type	%	Temp	Impeller RPM	Type	%	Temp	
1	4	4	Conditioning				Rushton	2400	High	15	
2	10	6	Oil Addition	Diesel	2		Rushton	2400	High	15	Flocs
3	14	4	Oil Addition	A2.801	3		Rushton	2400	High	15	Inversion
4			De-ash, 200M, 500ml water								Screened
5			Repulp								
6	60		Low Shear				Rushton	1800	Low	15	Flocs
7	62	2	Oil Addition	A2.801	2		Rushton	2400	High	15	Flocs
8	77	15	Low Shear				Rushton	1800	Low	15	Microagglomerates
9	79	2	Oil Addition	A2.801	2		Rushton	2400	High	15	Microagglomerates
10	94	15	Low Shear				Rushton	1800	Low	15	Microagglomerates
11	96	2	Oil Addition	A2.801	2		Rushton	2400	High	15	Microagglomerates
12	111	15	Low Shear				Rushton	1800	Low	15	Microagglomerates
13	113	2	Oil Addition	A2.801	2		Rushton	2400	High	15	1/3 mm Agglomerates
14	128	15	Low Shear				Rushton	1800	Low	15	1/3 mm Agglomerates
15	130	2	Oil Addition	A2.801	2		Rushton	2400	High	15	1/2 mm Agglomerates
16	145	15	Low Shear				Rushton	1800	Low	15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 14 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 14 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 145 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 21

Serial Number: 21

Sample Number: 4.1-7

Test Series: Binder Evaluation Tests

Test Date: 11/12/90

Feed Coal Seam: Ufp, weight 164.00 g, with a moisture content of %
 Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties			Shear Conditions			Slurry		Observations
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp	
1	4	4		Conditioning					Rushton	2400	High		15	
2	8	4		Oil Addition		Diesel	1		Rushton	2400	High		15	Flocs
3				Flotation										Conditioned 2 minutes
4				Frother Addition										0.1 lb/ton Addition; Conditioned 2 minutes
5				Floated Until Barren										11 RPM
6				Repulp										
7	2	2		Oil Addition		A2.301	5		Rushton	2400	High		15	Inversion
8	32	30		Changed Impeller to 3 blade					Turbine	1800	Low		15	Flocs
9	34	2		Oil Addition		A2.301	2		Turbine	2400	High		15	Flocs
10	49	15		Low Shear					Turbine	1800	Low		15	Flocs
11	51	2		Oil Addition		A2.301	2		Turbine	2400	High		15	Flocs
12	66	15		Low Shear					Turbine	1800	Low		15	Microagglomerates
13	68	2		Oil Addition		A2.301	2		Turbine	2400	High		15	Microagglomerates
14	83	15		Low Shear					Turbine	1800	Low		15	Microagglomerates
15	85	2		Oil Addition		A2.301	2		Turbine	2400	High		15	1/3 mm Agglomerates
16	100	15		Low Shear					Turbine	1800	Low		15	1/2 mm Agglomerates
17	102	2		Oil Addition		A2.301	2		Turbine	2400	High		15	1/2 mm Agglomerates
18	117	15		Low Shear					Turbine	1800	Low		15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	8 min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	10 min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	117 min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

Serial Number: 22
Sample Number: 1.4-9

Test Series: Binder Evaluation Tests

Test Date: 11/14/90

Feed Coal Seam: Ufp, weight 172.80 g, with a moisture content of %
Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4	Conditioning						Rushton	2400	High	15	
2	8	4	Oil Addition			Diesel	1		Rushton	2400	High	15	
3			Flotation										Flocs
4			Frother Addition										Conditioned 2 minutes
5			Floated until Barren										Conditioned 2 minutes; 11 RPM; 0.1 lb/ton
6			Repulp										2 min. for majority; 2 min. for remaining coal
7	2	2	RS-2 Emulsion Addition				5		Rushton	2400	High	15	Inversion
8	32	30	Changed Impeller to 3 blade						Turbine	1800	Low	15	microagglomerates
9	34	2	RS-2 Emulsion Addition				2		Turbine	2400	High	15	microagglomerates
10	49	15	Low Shear						Turbine	1800	Low	15	microagglomerates
11	51	2	RS-2 Emulsion Addition				2		Turbine	2400	High	15	microagglomerates
12	66	15	Low Shear						Turbine	1800	Low	15	1/3 mm Agglomerates
13	68	2	RS-2 Emulsion Addition				2		Turbine	2400	High	15	1/3 mm Agglomerates
14	83	15	Low Shear						Turbine	1800	Low	15	1/2 mm Agglomerates
15	85	2	RS-2 Emulsion Addition				2		Turbine	2400	High	15	1/2 mm Agglomerates
16	100	15	Low Shear						Turbine	1800	Low	15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low Shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

TEST PROCEDURES AND REPORTS

8/02/91

Serial Number: 23
Sample Number: 4.1-8

Test Date: 11/16/90

Test Series: Solids Concentration Test

Feed Coal Seam: Ufp, weight 168.30 g, with a moisture content of %
Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4	Conditioning						Rushton	2400	High	15	
2	8	4	Oil Addition			Diesel	1		Rushton	2400	High	15	
3			Flotation										Flocs
4			Frother Addition										Conditioned 2 minutes
5			Floated until Barren										0.1 lb/ton Addition; Conditioned 2 minutes
6			Repuip Froth										11 RPM
7	2	2	Oil Addition			A3.201	5		Rushton	2400	High	15	Inversion
8	32	30	Changed Impeller to 3 blade						Turbine	1800	Low	15	Flocs
9	34	2	Oil Addition			A3.201	2		Turbine	2400	High	15	Flocs
10	49	15	Low Shear						Turbine	1800	Low	15	Flocs
11	51	2	Oil Addition			A3.201	2		Turbine	2400	High	15	Microagglomerates
12	66	15	Low Shear						Turbine	1800	Low	15	Microagglomerates
13	68	2	Oil Addition			A3.201	2		Turbine	2400	High	15	Microagglomerates
14	83	15	Low Shear						Turbine	1800	Low	15	1/3 mm Agglomerates
15	85	2	Oil Addition			A3.201	2		Turbine	2400	High	15	1/2 mm Agglomerates
16	100	15	Low Shear						Turbine	1800	Low	15	1 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear: 8 min	Moisture Content Air Dried: %	Strength Index:
Inversion Time: 10 min	Moisture by Distillation: %	Abrasion Index:
Residence Time in Low shear: 100 min	Oil by Solvent Extraction: %	Consolidation Index:
		Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 24

Serial Number: 24

Sample Number: 4.1-9

Test Series: Solids Concentration Test

Test Date: 11/15/90

Feed Coal Seam: Ufp, weight 168.32 g, with a moisture content of %
 Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res					Type	% Temp	Impeller	RPM Type	% Temp			
1	4	4	4	Conditioning				Rushton	2400 High	15			
2	8	4	4	Oil Addition		Diesel	1	Rushton	2400 High	15			
3				Floatation									
4				Frother Addition									
5				Floated Until Barren									
6	2	2	2	Oil Addition		A3.2D1	5	Rushton	2400 High	15			
7	32	30	30	Changed Impeller to 3 blade				Turbine	1800 Low	15			
8	34	2	2	Oil Addition		A3.2D1	2	Turbine	2400 High	15			
9	49	15	15	Low Shear				Turbine	1800 Low	15			
10	51	2	2	Oil Addition		A3.2D1	2	Turbine	2400 High	15			
11	66	15	15	Low Shear				Turbine	1800 Low	15			
12	68	2	2	Oil Addition		A3.2D1	2	Turbine	2400 High	15			
13	83	15	15	Low Shear				Turbine	1800 Low	15			
14	85	2	2	Oil Addition		A3.2D1	2	Turbine	2400 High	15			
15	100	15	15	Low Shear				Turbine	1800 Low	15			
16	102	2	2	Oil Addition		A3.2D1	2	Turbine	2400 High	15			
17	117	15	15	Low Shear				Turbine	1800 Low	15			

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low Shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 25

Serial Number: 25

Sample Number: 3.1-2

Test Series: Binder Evaluation Tests

Test Date: 11/16/90

Feed Coal Seam: Ufp, weight 161.30 g, with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step-Procedure		Oil Properties		Shear Conditions		Slurry		Observations
No	Time, min- Cum Res	Type	% Temp	Impeller	RPM	Type	% Temp	
1	4	4	Conditioning					
2	8	4	Oil Addition	Diesel	2	Rushton	2400 High	15
3			Floatation			Rushton	2400 High	15
4			Frother Addition					Flocs
5			Floated Until Barren					Conditioned 2 minutes
6			Reulp					Conditioned 2 minutes; 11 RPM; 0.1 lb/ton
7	2	2	Oil Addition	A3.201	5	Rushton	2400 High	15
8	32	30	Changed Impeller to 3 blade			Turbine	1800 Low	15
9	34	2	Oil Addition	A3.201	2	Turbine	2400 High	15
10	49	15	Low Shear			Turbine	1800 Low	15
11	51	2	Oil Addition	A3.201	2	Turbine	2400 High	15
12	66	15	Low Shear			Turbine	1800 Low	15
13	68	2	Oil Addition	A3.201	2	Turbine	2400 High	15
14	83	15	Low Shear			Turbine	1800 Low	15
15	85	2	Oil Addition	A3.201	2	Turbine	2400 High	15
16	100	15	Low Shear			Turbine	1800 Low	15

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 26

Serial Number: 26

Sample Number: 4.2-11

Test Series: Impeller Comparison Tests

Test Date: 11/19/90

Feed Coal Seam: Ufp, weight 159.61 g, with a moisture content of %
 Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res					Type	% Temp	Impeller RPM	Type	% Temp			
1	4	4	Conditioning					Rushton	2400 High	15			
2	8	4	Oil Addition			Diesel	1	Rushton	2400 High	15		Flocsw	
3			Floation									Conditioned 2 minutes	
4			Frother Addition									Conditioned 2 minutes; 11 RPM; 0.1 lb/ton	
5			Floated until Barren										
6			Repulp										
7	2	2	Oil Addition			A2.8D1	5	Rushton	2400 High	15		Inversion	
8	7	15	Oil Addition			A2.8D1	2	Rushton	2400 High	15		Microagglomerates	
9	32	15	Oil Addition			A2.8D1	2	Rushton	2400 High	15		Microagglomerates	
10	47	15	Oil Addition			A2.8D1	2	Rushton	2400 High	15		1/3 mm Agglomerates	
11	62	15	Oil Addition			A2.8D1	2	Rushton	2400 High	15		1 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content:	Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:		%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:		%	Consolidation Index:
					Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 27

Serial Number: 27

Sample Number: 3.3-1

Test Series: Binder Evaluation Tests

Test Date: 11/28/90

Feed Coal Seam: Ufp, weight 164.31 g. with a moisture content of %
 Feed Coal Ground for 45 min to a topsize of 200 mesh, with a D-50 of mm

Step- Time, min-		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res			Type	% Temp	Impeller	RPM Type	% Temp			
1	4	4	Conditioning			Rushton	2400 High	15			
2	8	4	Oil Addition	Diesel	2	Rushton	2400 High	15		flocs	
3			Flotation								
4			Frother Addition							0.1 lb/ton; 11 RPM	
5			Floated Until Barren							Floated 2 times	
6			Repulp								
7	2	2	Binder Addition		10	Rushton	2400 High	15		SS-1 Commercial Emulsion Binder	
8	37	35	Changed Impeller			Turbine	1800 Low	15		Flocs	
9	47	10	Oil Addition			Turbine	1800 Low	15		Few drops of Surfactant; Microagglomerates	
10	72	25	Oil Addition			Turbine	1800 Low	15		Few drops of Surfactant; Microagglomerates	
11	97	25	Low Shear			Turbine	1800 Low	15		1 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 28

Serial Number: 28
Sample Number: 4.3-2

Test Date: 11/28/90

Test Series: Binder Evaluation Tests

Feed Coal Seam: Ufp, weight 153.12 g, with a moisture content of %
Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step- Time, min-		Procedure-----		Oil Properties-----		Shear Conditions-----		Slurry-----		Observations-----	
No	Cum Res			Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4	Conditioning				Rushton	2400	High	15	
2	4	4	Oil Addition	Diesel	1		Rushton	2400	High	15	Flocs
3			Flotation								11 RPM
4			Frother Addition								0.1 lb/ton; 11 RPM
5			Floated Until Barren								Floated 2 times
6			Repulp								
7	4	4	Oil Addition	FuelOil6	7		Rushton	2400	High	15	Flocs
8	14	10	Changed Impeller				Turbine	1800	Low	15	Flocs
9	16	2	Oil Addition	FuelOil6	2		Turbine	2400	High	15	Flocs
10	31	15	Low Shear				Turbine	1800	Low	15	Large Flocs; No formation of agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Serial Number: 29
Sample Number: 4.3-3

Test Series: Binder Evaluation Tests

Test Date: 11/28/90

Feed Coal Seam: Ufp, weight 162.80 g, with a moisture content of %
Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	% Temp	Impeller	RPM	Type	% Temp		
1	4	4	Conditioning					Rushton	2400	High	15		
2	8	4	Oil Addition			Diesel	1	Rushton	2400	High	15	Flocs	
3			Flotation									11 RPM	
4			Frother Addition									0.1 lb/ton; 11 RPM	
5			Floated Until Barren									Floated 2 times	
6			Repulp										
7	2	2	Binder Addition				7	Rushton	2400	High	15	SS-1 Commercial Emulsion	
8			Changed Impeller					Turbine	1800	Low	15		
9	22	20	Low Shear					Turbine	1800	Low	15	Microagglomerates	
10	67	45	Binder Addition			Diesel		Turbine	1800	Low	15	Few drops of diesel; 1/2 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 30

Serial Number: 30

Sample Number: 4.3-4

Test Series: Binder Evaluation Tests

Test Date: 11/28/90

Feed Coal Seam: Ufp, weight 162.21 g, with a moisture content of %
 Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	% Temp	Impeller	RPM	Type	% Temp		
1	49	15		Binder Addition		Diesel		Turbine	1800	Low	15		Few drops Diesel; less than 1/2 mm Agglomerate
2	4	4		Conditioning				Rushton	2400	High	15		
3	8	4		Oil Addition		Diesel	1	Rushton	2400	High	15		Flocs
4				Flotation									11 RPM
5				Frother Addition									11 RPM; 0.1 lb/ton
6				Floated Until Barren									Floated 2 times
7				Repulp									
8	2	2		Surfactant Addition				Rushton	2400	High	15		Oleic Acid 0.3 %
9	4	2		Binder Addition				Rushton	2400	High	15		SS-1 Commercial Asphalt Emulsion; Agglomerates
10	34	30		Changed Impeller				Turbine	1800	Low	15		Microagglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 31

Serial Number: 31

Sample Number: 4.3-6

Test Series: Binder Evaluation Tests

Test Date: 11/29/90

Feed Coal Seam: Ufp, weight 160.00 g, with a moisture content of %
 Feed Coal Ground for 6 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	% Temp	Impeller	RPM Type	% Temp			
1	4	4	Conditioning					Rushton	2400 High	15			
2	8	4	Oil Addition			Diesel	1	Rushton	2400 High	15		Flocs	
3			Flotation									11 RPM	
4			Frother Addition									0.1 lb/ton; 11 RPM	
5			Floated Until Barren									Floated 2 times	
6	2	2	Surfactant Addition					Rushton	2400 High	15		Oleic Acid; Flocs	
7	4	2	Oil Addition			Fueloil6	7	Rushton	2400 High	15		Flocs	
8	19	15	Changed Impeller					Turbine	1800 Low	15		Agglomerates	
9	21	2	Oil Addition			Fueloil6	1	Turbine	2400 High	15		Agglomerates	
10	36	15	Low Shear					Turbine	1800 Low	15		Agglomerates	
11	38	2	Oil Addition			Fueloil6	1	Turbine	2400 High	15		Agglomerates	
12	53	15	Low Shear					Turbine	1800 Low	15		Agglomerates	
13	55	2	Oil Addition			Fueloil6	1	Turbine	2400 High	15		Agglomerates	
14	70	15	Low Shear					Turbine	1800 Low	15		1/3 mm Agglomerates	
15	72	2	Oil Addition			Fueloil6	1	Turbine	2400 High	15		1.2 mm Agglomerates	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

Serial Number: 32
Sample Number: 4.3-7

Test Series: Binder Evaluation Tests

Test Date: 11/29/90

Feed Coal Seam: Ufp, weight 167.93 g, with a moisture content of %
Feed Coal Ground for 6 min to a topsize of 28 mesh, with a D-50 of mm

Step - Time, min			Procedure		Oil Properties		Shear Conditions		Slurry		Observations
No	Cum	Res			Type	% Temp	Impeller	RPM	Type	% Temp	
1	4	4	Conditioning				Rushton	2400	High	15	
2	4	4	Oil Addition		Diesel	1	Rushton	2400	High	15	Flocs
3			Flotation								11 RPM
4			Flother Addition								0.1 lb/ton; 11 RPM
5			Floated Until Barren								Floated 2 times
6			Repulp								
7	2	2	Binder Addition			7	Rushton	2400	High	15	SS-1 Commercial Asphalt Emulsion
8	20	18	Changed Impeller				Turbine	1800	Low	15	No Formation of Agglomerates
9	35	15	Surfactant Addition				Turbine	1800	Low	15	1/2 ml Addition; No Formation of Agglomerates
10	37	2	CM-224 Addition				Turbine	2400	High	15	Inhibited Agglomerate growth; reduced S. Tensi
11	39	2	Binder Addition			1	Turbine	2400	High	15	No growth of Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 33

Serial Number: 33

Sample Number: 4.3-8

Test Series: Binder Evaluation Tests

Test Date: 11/29/90

Feed Coal Seam: Ufp, weight 151.28 g, with a moisture content of %
 Feed Coal Ground for 6 min to a topsize of 28 mesh, with a D-50 of mm

Step- No		Time, min	Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
		Cun	Res		Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4	4	Conditioning				Rushton	2400	High	15	
2	8	4	4	Oil Addition	Diesel	1		Rushton	2400	High	15	
3				Flotation								
4				Frother Addition								
5				Floated Until Barren								
6	2	2	2	Surfactant Addition				Rushton	2400	High	15	
7	4	2	2	Binder Addition		7		Rushton	2400	High	15	
8	44	4	4	Changed Impeller to 3 blade				Turbine	1800	Low	15	
9	46	2	2	Binder Addition		1		Turbine	2400	High	15	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content	Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:	
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:	
				Product D-50 in mm:	

8/02/91

TEST PROCEDURES AND REPORTS

Page 34

Serial Number: 34
Sample Number: 4.3-9

Test Series: Binder Evaluation Tests

Test Date: 11/29/90

Feed Coal Seam: Ufp, weight 170.26 g, with a moisture content of %
Feed Coal Ground for 6 min to a topsize of 28 mesh, with a D-50 of mm

Step		Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum	Res				Type	%	Temp	Impeller	RPM	Type	%	Temp
1	4	4	Conditioning						Rushton	2400	High	15	
2	8	4	Oil Addition			Diesel	1		Rushton	2400	High	15	
3			Flotation										
4			Frother Addition										
5			Floated Until Barren										
6	1	1	Surfactant Addition						Rushton	2400	High	15	
7	3	2	Oil Addition			A2.301	7		Rushton	2400	High	15	
8	33	30	Changed Impeller to 3 blade						Turbine	1800	Low	15	
9	35	2	Oil Addition			A2.301	1		Turbine	2400	High	15	
10	50	15	Low Shear						Turbine	1800	Low	15	
11	52	2	Oil Addition			A2.301	1		Turbine	2400	High	15	
12	67	15	Low Shear						Turbine	1800	Low	15	

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 35

Serial Number: 35

Sample Number: 4.3-10

Test Series: Binder Evaluation Tests

Test Date: 11/30/90

Feed Coal Seam: Ufp, weight 154.30 g, with a moisture content of %
 Feed Coal Ground for 7 min to a topsize of 28 mesh, with a D-50 of mm

Step-Time, min		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res			Type	%	Temp	Impeller RPM	Type	%	Temp	
1	4	4	Conditioning				Rushton	2400	High	15	
2	8	4	Oil Addition	Diesel	1		Rushton	2400	High	15	Flocs
3			Flotation								11 RPM
4			Frother Addition								0.1 lb/ton; 11 RPM
5			Floated Until Barren								Floated 2 times
6			Repulp								
7	2	2	Binder Addition		7		Rushton	2400	High	15	SS-1 Commercial Asphalt Emulsion; Flocs
8	32	30	Changed Impeller to 3 blade				Turbine	1800	Low	15	Flocs
9	34	2	Binder Addition		1		Turbine	2400	High	15	SS-1 Commercial Asphalt Emulsion; Microagglomerate
10	49	15	Low Shear				Turbine	1800	Low	15	Microagglomerates
11	51	2	Binder Addition		1		Turbine	2400	High	15	Microagglomerates
12	66	15	Low Shear				Turbine	1800	Low	15	Microagglomerates
13	68	2	Binder Addition		1		Turbine	2400	High	15	SS-1 Commercial Asphalt Emulsion; microagglomerate
14	83	15	Low Shear				Turbine	1800	Low	15	1/3 mm Agglomerates
15	100	15	Low Shear				Turbine	1800	Low	15	1/2 mm Agglomerates
16	102	2	Binder Addition		1		Turbine	2400	High	15	SS-1 Commercial Asphalt Emulsion; 1/2 mm Aggl.
17	117	15	Low Shear				Turbine	1800	Low	15	1.2 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

TEST PROCEDURES AND REPORTS

Page 36

Serial Number: 36
Sample Number: 4.3-11

Test Series: Binder Evaluation Tests

Test Date: 11/30/90

Feed Coal Seam: Ufp, weight 150.00 g, with a moisture content of %
Feed Coal Ground for 6 min to a topsize of 28 mesh, with a D-50 of mm

Step- Time, min-		Procedure		Oil Properties		Shear Conditions		Slurry		Observations	
No	Cum Res			Type	% Temp	Impeller RPM	Type	% Temp			
1	4	4	Conditioning			Rushton	2400 High	15			
2	8	4	Oil Addition	Diesel	1	Rushton	2400 High	15			Flocs
3			Flotation								11 RPM
4			Frother Addition								0.1 lb/ton; 11 RPM
5			Floated Until Barren								Floated 2 times
6			Repulp								
7	2	2	Binder Addition		7	Rushton	2400 High	15			SS-1 Commercial Asphalt Emulsion; Microaggl.
8	32	30	Changed Impeller to 3 blade			Turbine	1800 Low	15			Microagglomerates
9	34	2	Binder Addition		1	Turbine	2400 High	15			Microagglomerates
10	49	15	Low Shear			Turbine	1800 Low	15			Microagglomerates
11	51	2	Binder Addition		1	Turbine	2400 High	15			SS-1 Commercial Asphalt Emulsion; 1/3 mm Aggl.
12	66	15	Low Shear			Turbine	1800 Low	15			1/2 mm Agglomerates

PRODUCT AGGLOMERATE PROPERTIES

Residence Time in High Shear:	min	Moisture Content Air Dried:	%	Strength Index:
Inversion Time:	min	Moisture by Distillation:	%	Abrasion Index:
Residence Time in Low shear:	min	Oil by Solvent Extraction:	%	Consolidation Index:
				Product D-50 in mm:

8/02/91

Oil Data

Page 1

Oil Type	Oil Description	Viscosity, cp
A1.8D1	Asphalt Diesel Mixture (1.8:1)	1000
A2.3D1	Asphalt Diesel Mixture (2.3:1)	3000
A2.8D1	Asphalt Diesel Mixture (2.8:1)	6000
A3.2D1	Asphalt Diesel Mixture (3.2:1)	10000
Asphalt	Pure Asphalt	
Diesel	Pure Diesel	
FuelOil5	Pure Fuel Oil #5	
FuelOil6	Pure Fuel Oil #6	

WILSONVILLE BATCH DATA
LOW-SHEAR SERIES 1 TEST RESULTS - UPPER FREEPORT COAL (200 H)

Ser ID No.	Size	Oil Type	Oil Conc	Asphalt Type	Conc	Water	Rec	Tec	Screen	Product----->				<- Refuse ->				<- Performance Calculations -->								<- Calculations on Ash basis ->							
										Avg.	TS	Avg.	Btu/Lb	Avg.	Ash	TS	Avg.	Yield	8tu	Re	DMR	ARJ	TSR	Yield	8tu	Re	DMR	ARJ	TSR	Yield	8tu	Re	DMR
										gms																							
3	4.6-2	200M	Heptane	10	AC-5	0.00	800	Screen	80	12.0	1.55	13305	52.2	4.60	83.9	88.0	88.9	36.1	43.3	90.6	95.1	94.7	31.0	38.7	90.6	95.1	94.7	31.0	38.7				
4	5.6-2	200M	Heptane	10	AC-5	0.10	800	Screen	80	11.4	1.69	13410	70.6	3.18	86.3	91.2	92.0	37.9	36.4	92.5	97.8	97.4	33.4	31.8	92.5	97.8	97.4	33.4	31.8				
7	8.6-2	200M	Heptane	10	AC-5	0.30	800	Screen	80	12.9	2.00	13166	47.7	2.26	88.8	92.2	93.2	27.6	22.4	91.6	95.1	94.8	25.3	19.9	91.6	95.1	94.8	25.3	19.9				
2	3.6-2	200M	Heptane	20	AC-5	0.00	800	Screen	80	9.9	1.42	13654	0.0	0.00	86.1	92.7	93.4	46.2	46.6	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA				
5	6.6-2	200M	Heptane	20	AC-5	0.10	800	Screen	80	10.6	1.74	13540	75.3	4.79	90.4	96.5	97.3	39.5	31.5	91.9	98.1	97.5	38.5	30.3	91.9	98.1	97.5	38.5	30.3				
8	1.9-2	200M	Heptane	20	AC-5	0.30	800	Screen	80	11.4	2.26	13410	73.3	2.67	93.2	98.5	99.4	32.9	8.2	92.9	98.2	97.7	33.1	8.5	92.9	98.2	97.7	33.1	8.5				
24	5.8-3	200M	Heptane	20	AC-5	0.50	800	Screen	80	11.8	2.14	13341	76.5	2.51	92.4	97.2	98.1	31.0	13.6	93.8	98.7	98.3	29.9	12.3	93.8	98.7	98.3	29.9	12.3				
1	2.6-2	200M	Heptane	30	AC-5	0.00	800	Screen	80	9.7	1.54	13586	67.0	5.83	88.7	95.7	96.4	45.7	40.3	89.3	96.4	95.8	45.3	39.9	89.3	96.4	95.8	45.3	39.9				
6	7.6-2	200M	Heptane	30	AC-5	0.10	800	Screen	80	10.1	1.65	13613	73.9	4.86	87.9	94.3	95.1	43.7	36.6	91.1	97.8	97.2	41.6	34.3	91.1	97.8	97.2	41.6	34.3				
9	2.9-2	200M	Heptane	30	AC-5	0.30	800	Screen	80	10.0	1.97	13629	76.6	4.56	92.1	98.9	99.7	41.6	20.9	91.3	98.1	97.6	42.1	21.6	91.3	98.1	97.6	42.1	21.6				
25	6.8-3	200M	Heptane	30	AC-5	0.50	800	Screen	80	11.0	1.94	13470	75.1	3.69	90.6	96.2	97.0	36.9	23.3	92.5	98.3	97.8	35.5	21.7	92.5	98.3	97.8	35.5	21.7				
30	7.12-3200M	Heptane	20	AC-5	0.00	4000	Screen	80	9.1	1.54	13782	45.6	4.82	80.7	87.7	88.3	53.6	45.7	81.6	88.7	88.1	53.1	45.0	81.6	88.7	88.1	53.1	45.0					
31	8.12-3200M	Heptane	20	AC-5	0.00	4000	Screen	80	8.6	1.34	13857	56.7	5.75	85.9	93.9	94.5	53.2	49.8	85.1	93.0	92.3	53.7	50.2	85.1	93.0	92.3	53.7	50.2					
33	2.11-2200M	Heptane	30	AC-5	0.00	4000	Screen	80	7.7	1.15	13994	52.6	5.57	80.8	89.2	89.8	60.3	59.3	82.1	90.6	89.9	59.7	58.6	82.1	90.6	89.9	59.7	58.6					
32	1.11-2200M	Heptane	30	AC-5	0.00	4000	Screen	80	8.1	1.24	13930	47.3	5.05	75.9	83.4	83.9	60.9	58.8	80.5	88.4	87.8	58.5	56.4	80.5	88.4	87.8	58.5	56.4					
28	1.12-3200M	Heptane	30	AC-5	0.00	4000	Screen	80	9.6	1.64	13700	72.2	7.90	87.3	94.3	95.1	47.0	37.6	90.1	97.3	96.7	45.3	35.6	90.1	97.3	96.7	45.3	35.6					
20	1.8-3	200M	Heptane	30	AC-5	0.00	4000	Screen	80	8.3	1.37	13906	61.5	4.94	83.1	91.1	91.7	56.4	50.4	85.9	94.2	93.6	54.9	48.8	85.9	94.2	93.6	54.9	48.8				
26	7.8-3	200M	Heptane	30	AC-5	0.10	4000	Screen	80	11.2	1.74	13429	74.9	4.94	0.0	0.0	0.0	100.0	100.0	92.9	98.3	97.9	33.8	29.5	92.9	98.3	97.9	33.8	29.5				
35	4.11-2200M	Heptane	30	AC-5	0.10	4000	Screen	80	9.8	1.69	13657	61.2	5.39	85.3	91.8	92.6	46.8	37.1	88.4	95.2	94.7	44.9	34.8	88.4	95.2	94.7	44.9	34.8					
36	5.11-2200M	Heptane	30	AC-5	0.10	4000	Screen	80	10.4	1.68	13572	53.6	4.27	85.2	91.2	91.9	44.0	37.3	87.5	93.6	93.1	42.5	35.6	87.5	93.6	93.1	42.5	35.6					
23	4.8-3	200M	Heptane	30	AC-5	0.30	4000	Screen	80	9.8	1.71	13658	72.9	5.12	87.7	94.4	95.2	45.4	34.5	90.6	97.5	97.0	43.6	32.3	90.6	97.5	97.0	43.6	32.3				
29	3.12-3200M	Heptane	30	AC-5	0.30	4000	Screen	80	10.3	2.06	13583	74.2	4.65	88.2	94.4	95.2	42.5	20.6	91.4	97.9	97.4	40.4	17.7	91.4	97.9	97.4	40.4	17.7					
27	8.8-3	200M	Heptane	30	AC-5	0.50	4000	Screen	80	9.5	1.72	13706	72.8	5.03	88.5	95.6	96.3	46.6	33.5	90.1	97.4	96.8	45.6	32.2	90.1	97.4	96.8	45.6	32.2				
38	3.11-3200M	Heptane	5	AC-5	0.00	Flotation				6.6	1.13	14175	24.7	2.89	43.3	48.4	48.7	81.9	78.6	49.2	55.0	54.6	79.4	75.7	49.2	55.0	54.6	79.4	75.7				
40	6.11-3200M	Heptane	5	AC-5	0.00	Flotation				7.1	1.25	14090	23.3	2.31	57.1	63.5	63.9	74.2	68.9	46.6	51.7	51.4	78.9	74.6	46.6	51.7	51.4	78.9	74.6				
42	8.11-3200M	Heptane	5	AC-5	0.05	Flotation				7.6	1.41	14013	49.6	5.08	77.6	85.7	86.3	62.5	52.1	80.6	89.0	88.4	61.1	50.3	80.6	89.0	88.4	61.1	50.3				
39	5.11-3200M	Heptane	7.5	AC-5	0.00	Flotation				7.2	1.27	14085	45.0	5.45	68.0	75.5	76.0	69.1	62.3	77.2	85.8	85.1	64.9	57.2	77.2	85.8	85.1	64.9	57.2				
41	7.11-3200M	Heptane	7.5	AC-5	0.05	Flotation				7.5	1.35	14038	48.4	1.87	74.1	82.1	82.6	64.9	56.3	79.7	88.2	87.5	62.3	53.0	79.7	88.2	87.5	62.3	53.0				

WILSONVILLE BATCH DATA
LOW-SHEAR SERIES 1 TEST RESULTS - UPPER FREEPORT COAL (200 M)

Ser No.	ID	Size	Oil Type	Conc	Asphalt Conc	Microscreen	Product-----<-				Refuse ->				<- Performance Calculations -->								<- Calculations on Ash basis -->											
							Avg.	TS	Btu/lb	Avg.	Ash	TS	Avg.	TS	Yield	Btu	Re	CHR	ARJ	TSR	Yield	Btu	Re	CHR	ARJ	TSR	Yield	Btu	Re	CHR	ARJ	TSR		
							Ash	TS			Ash	TS	Yield	Btu	Re	CHR	ARJ	TSR			Yield	Btu	Re	CHR	ARJ	TSR			Yield	Btu	Re	CHR	ARJ	TSR
gms																																		
34	3.11-2200M	Heptane	10	AC-5	0.00	Flotation	7.0	1.16	14107	34.3	3.89	65.4	72.8	73.2	70.8	66.8	67.9	75.6	75.0	69.7	65.5													
37	2.11-3200M	Heptane	10	AC-5	0.00	Flotation	7.5	1.13	14034	35.5	4.78	63.4	70.1	70.5	69.9	68.8	70.4	77.9	77.3	66.6	65.3													
10	4.9-2 200M	Heptane	10	AC-5	0.00	Flotation	7.7	1.35	14004	50.6	1.97	80.8	89.3	89.8	60.7	52.5	81.1	89.6	88.9	60.5	52.3													
16	5.10-2200M	Heptane	10	AC-5	0.10	Flotation	8.6	1.58	13854	46.3	4.29	81.1	88.6	89.2	55.7	44.0	81.0	88.5	87.9	55.8	44.1													
11	5.9-2 200M	Heptane	10	AC-5	0.30	Flotation	9.9	1.97	13648	59.1	3.36	88.1	94.8	95.5	44.8	24.4	88.0	94.7	94.2	44.8	24.4													
19	8.10-2200M	Heptane	10	AC-5	0.50	Flotation	10.3	1.37	13581	59.7	4.31	85.5	91.6	92.3	44.1	49.0	88.9	95.2	94.7	41.9	47.0													
12	1.10-2200M	Heptane	20	AC-5	0.00	Flotation	9.9	1.69	13638	67.9	1.43	86.5	93.0	93.7	45.4	36.0	90.0	96.7	96.2	43.3	33.5													
17	6.10-2200M	Heptane	20	AC-5	0.10	Flotation	10.3	2.00	13576	68.9	4.50	90.0	96.4	97.2	41.0	21.4	90.7	97.1	96.6	40.6	20.8													
14	3.10-2200M	Heptane	20	AC-5	0.30	Flotation	10.7	1.81	13520	65.3	3.47	90.2	96.2	97.0	38.9	28.8	90.7	96.7	96.2	38.6	28.4													
15	4.10-2200M	Heptane	20	AC-5	0.50	Flotation	10.7	1.98	13515	59.7	2.17	91.1	97.0	97.9	38.2	21.1	89.7	95.5	95.1	39.1	22.3													
13	2.10-2200M	Heptane	30	AC-5	0.00	Flotation	9.8	1.43	13662	70.3	7.63	88.9	95.8	96.5	44.8	44.5	90.1	97.1	96.5	44.0	43.8													
18	7.10-2200M	Heptane	30	AC-5	0.10	Flotation	10.8	1.86	13508	70.6	5.30	91.5	97.4	98.2	37.6	25.7	91.6	97.6	97.1	37.5	25.5													
22	3.8-3 200M	Heptane	30	AC-5	0.30	Flotation	10.5	1.75	13545	71.0	4.21	90.0	96.1	96.9	39.9	31.1	91.3	97.5	97.0	39.1	30.1													
21	2.8-3 200M	Heptane	30	AC-5	0.50	Flotation	10.7	1.94	13510	65.3	4.31	89.4	95.3	96.1	39.1	24.3	90.8	96.7	96.2	38.2	23.1													
43	9.14-4 200M	PureHep	20	AC-5	0.0	Screen	45	7.3	NA	14057	34.4	NA	66.2	73.3	73.8	69.2	NA	68.8	76.3	75.7	68.0	NA												
44	1.14-1 200M	PureHep	20	AC-5	0.0	Screen	45	NA	NA	33.1	NA	NA	62.8	NA	NA	NA	NA	NA	NA	NA	NA	NA												
45	2.14-1 200M	PureHep	30	AC-5	0.0	Screen	45	7.9	1.12	13972	53.7	7.32	81.4	89.7	90.3	59.4	60.3	82.8	91.2	90.5	58.7	59.6												
46	3.14-1 200M	PureHep	30	AC-5	0.0	Screen	45	7.0	1.08	14114	49.9	6.92	76.3	84.9	85.4	66.2	64.2	79.5	88.5	87.8	64.8	62.7												
47	4.14-1 200M	PureHep	10	AC-5	0.0	Flotation		6.7	1.05	14167	47.2	5.82	68.7	76.8	77.2	71.0	68.4	77.5	86.5	85.9	67.3	64.3												
48	5.14-1 200M	PureHep	10	AC-5	0.0	Flotation		7.1	1.11	14092	50.2	6.10	77.4	86.0	86.6	65.0	62.4	79.9	88.8	88.1	63.9	61.2												

WILSONVILLE BATCH DATA
LOW-SHEAR SERIES 2 TEST RESULTS

Ser ID No. No.	Size (mesh)	HS Oil Conc (%)	LS Oil Conc. (%)	LS Res Time (mins)	Total Oil Conc. %	Asph Microagg Screen	-----Petroleum X-----				-----Heptane X-----				-----Asphalt X-----			
							Water	Wet prod	Dry prod	Feed	Water	Wet prod	Dry prod	Feed	Water	Wet prod	Dry prod	Feed
5	7(12-2)	200	10	21	16	31	2 Flot-2	12.76	33.68	52.18	38.88	32.42	24.15	2.68	2.06	3326	2436	
8	4(9-3)	200	10	21	32	31	2 Flot-2	11.62	24.03	32.55	23.19	16.81	11.98	2.81	2.06	5306	2734	
2	3(12-2)	200	10	21	32	31	2 Flot-2	2.27	28.34	40.77	27.25	37.51	25.07	2.99	2.06	3268	3150	
4	6(12-2)	200	10	20	16	30	3 Flot-2	12.17	29.86	44.38	32.63	26.30	19.34	4.08	3.13	3201	2438	
7	5(9-3)	200	10	20	32	30	3 Screen	12.61	46.92	91.89	72.79	67.19	53.22	3.79	3.12	4530	2199	
6	2(12-2)	200	10	20	32	30	3 Flot-2	8.61	20.68	27.17	20.04	15.85	11.70	4.07	3.13	2939	1711	
1	2(13-4)	200	10	19	16	29	4 Flot-2	17.16	29.26	43.62	33.73	18.04	13.95	5.17	4.22	4046	2511	
3	4(12-2)	200	10	19	32	29	4 Flot-2	8.76	41.71	75.74	54.75	59.83	43.25	5.53	4.23	3200	2909	
9	CDTF-1	100	10	15	32	25	1.5 Flot-2	0.00	31.00	45.94	30.99	45.94	30.99	2.22	1.53	1533	1000	
10	CDTF-3	100	10	20	32	30	1.5 Flot-2	10.40	22.51	29.69	20.56	15.98	11.07	2.17	1.53	3556	1134	
11	CDTF-4	100	10	19.5	32	29.5	2 Screen	45	9.48	21.89	28.76	22.54	16.30	2.55	2.05	2949	1472	
12	CDTF-5	100	18	7	32	25	2 Screen	45	NA	23.07	24.01	NA	NA	2.56	2.05	1755	1264	
13	CDTF-6	100	18	9	32	27	2 Screen	45	NA	22.43	29.69	22.78	NA	2.61	2.05	4000	2100	
14	CDTF-7	100	18	9	32	27	3 Screen	45	NA	23.33	31.64	24.65	NA	3.85	3.12	3900	3000	
15	1(14-4)	200	25	7	32	32	1 Flot-2	9.50	28.01	39.41	30.21	26.04	19.96	1.30	1.01	2571	600	
21	8(14-4)	200	20	10	20	30	1 Flot-2	12.54	21.68	28.07	20.31	11.83	8.56	1.38	1.01	1411	900	
18	5(14-4)	200	20	12	20	32	1 Flot-2	NA	14.35	16.99	12.41	NA	NA	1.37	1.01	2280	700	
22	9(9-3)	200	10	22	32	32	1 Flot-2	10.57	26.62	36.79	26.95	22.18	16.25	1.37	1.01	2482	450	
19	6(14-4)	200	20	11.5	20	31.5	1.5 Flot-2	9.12	23.82	31.94	22.67	19.71	13.99	2.11	1.53	2536	1418	
16	2(14-4)	200	25	6	32	31	2 Flot-2	13.26	28.48	40.91	30.48	21.86	16.28	2.68	2.06	3758	3000	
20	7(14-4)	200	20	11	20	31	2 Flot-2	8.96	23.78	32.09	23.35	20.00	14.56	2.75	2.06	2391	2017	
17	3(14-4)	200	25	5	32	30	3 Flot-2	10.03	24.35	33.49	25.67	19.70	15.10	3.91	3.12	3200	3000	

WILSONVILLE BATCH DATA
LOW-SHEAR SERIES 3 TEST RESULTS

Ser ID No.	---TARGET---				PROD				-----DRYING/EXTRACTION TESTS-----										AGGLOMERATE SIZE DISTRIBUTION						
	-COND	HS	LS	HEPT	-PRODUCT-		REFUSE		OVEN	DRYING		Dry/Wet		% Vols		% Water		% Hept		CUMULATIVE % PASSING					
					ASH	TS	ASH	TS		TEMP	PERIOD	Weight	%	Wet Prod	Basis	Wet Prod	Basis	Prod	Evap	1/4"	4 M	6 M	8 M	12 M	16 M
1	2(13-3)	2	24.2	8.6	43.4	500	7.095	1.289	53.06	5.913	79	20 MIN	80.45	19.55	9.29	12.09	100	99.48	83.45	49.7	32.9	24.65			
											79	40 MIN	79.34	20.66	1.08	19.80	99.72	98.93	82.73	44.08	25.3	16.9			
3	3(13-3)	2	23.5	8.29	42.3	450	7.33	1.195	51.6	5.927	79	80 MIN	71.18	28.82	0.31	28.60	100	96.02	66.78	37.5	27	20.67			
											79	16 HR	66.51	33.49	NA	NA	98.2	84.9	42.85	15.55	10.5	8.76			
2	4(13-3)	3	23.5	12.5	40	490	6.73	1.204	50.45	5.68	79	20 MIN	85.85	14.15	4.36	10.41	99.4	96.89	64.77	16.82	8.13	5.54			
											79	40 MIN	87.17	12.83	0.08	12.76	99.66	97.89	72.43	26.63	8.85	4.12			
5	5(13-3)	3	23.5	12.5	40	500	6.57	1.29	50.78	5.828	79	80 MIN	75.94	24.06	0.06	24.01	100	96.43	47.98	10.75	4.71	3.02			
											79	16 HR	69.31	30.69	NA	NA	98.93	96.06	57.18	25.55	15	1.68			
3	7(13-3)	2	24	8.48	45.5	500	6.49	1.143	53.26	6.774	111	20 MIN	71.39	28.61	0.00	28.61	100	98.15	80.24	44.14	28.9	19.93			
											111	40 MIN	70.81	29.19	0.00	29.19	100	100	72.53	26.98	11.6	5.63			
											111	80 MIN	71.56	28.44	0.00	28.44	100	98.01	72.85	27.68	14.7	6.62			
											111	16 HR	65.53	34.47	NA	NA	100	92.71	49.9	15.21	7.89	5.4			
4	8(13-3)	3	23.7	12.6	40.4	450	6.53	1.24	51.29	6.292	111	20 MIN	75.52	24.48	0.15	24.36	97.32	80.55	42.43	17.29	10.5	7.03			
											111	40 MIN	71.00	29.00	0.06	28.96	89.3	71.32	33.07	10.98	6.45	4.02			
9	9(13-3)	3	23.5	12.5	40	500	6.125	1.15	50.65	6.023	111	80 MIN	71.01	28.99	0.07	28.95	55.84	33.88	11.71	4.08	2.08	1.39			
											111	16 HR	65.67	34.33	NA	NA	96.2	83.49	58.36	34.66	25.5	20.83			
5	6(13-4)	3	24.2	12.8	41.1	400	6.44	1.183	53.82	5.708	141	20 MIN	69.76	30.24	0.03	30.22	100	95.87	71.69	23.81	10.1	6.95			
											141	40 MIN	70.11	29.89	0.02	29.87	99.55	97.88	70.05	27.09	12.8	7.92			
7	7(13-4)	3	23.4	12.4	39.8	450	6.36	1.133	55.5	6.122	141	80 MIN	70.22	29.78	0.03	29.75	100	99.62	85.1	44.07	23.4	15.68			
											141	16 HR	62.78	37.22		37.22	99.2	98.37	81.35	41.66	21.4	14.5			

TEST ID	1(9-3)	3(9-3)	6(9-3)	7(9-3)	8(9-3)	HEPTANE/AC-5	AC-5	AC-5	HEPT/AC-5	HEPTANE
Sample Wt. (g)	161.88	166.59	160.03	160.09	166	10.4	13.3	9.76	10.9	8.55
HEP(ml) HS	23.63	48.64	46.7	46.7	48	50 - 50	Commercial	AC-5 as delivered	3/25	Indus Grade
HS TIME	1	1	1	1	1	NA	NA	NA	NA	NA
MICRO REC	2-FLOT	2-FLOT	NONE	NONE	NONE	NA	NA	NA	NA	NA
HEP(ml) LS	40.18	17.04	16.1	16.3	16.8	NA	NA	NA	NA	NA
BIN SOL(50/50) LS	12.5	12.9	12.88	12.4	12.7	NA	NA	NA	NA	NA
LS TIME	32	32	32	32	32	NA	NA	NA	NA	NA
TAILINGS WT	28.13	30.7	NA	NA	NA	NA	NA	NA	NA	NA
TAILINGS ASH	52.86	45.27	NA	NA	NA	NA	NA	NA	NA	NA
OVEN TEMP	110	110	110	80	140	140	80	140	140	140
Ttl PROD WT (g)	129.25	131.72	158.74	75.98	101	NA	NA	NA	NA	NA
WT TO H2O EXTR	NA	NA	NA	61.55g	50.02g	NA	NA	NA	NA	NA
WT TO HEP EXTR	NA	NA	NA	61.13g	45.94g	NA	NA	NA	NA	NA

T = 110 C				T = 110 C				T = 80 C				T = 140 C				T = 80 C				T = 140 C				T = 140 C			
Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time	Time			
mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins	mins			
0	100.00	0	100.00	0	100.00	0	100.00	0	100.00	0	100.00	0	100.00	0	100.00	0	100.00	0	100.00	0	100.00	0	100.00	0	100.00		
10	79.02	10	75.51	10	74.21	10	66.38	10	72.42	30	80.27	30	65.90	30	99.70	30	99.49	10	51.69	10	51.69	10	51.69	10	51.69		
20	72.05	20	70.52	20	69.17	20	59.38	20	68.34	60	59.20	60	55.79	60	99.70	60	99.39	20	49.68	20	49.68	20	49.68	20	49.68		
40	67.36	40	68.95	30	67.59	30	57.99	30	68.25	90	59.10	90	55.30	90	99.70	90	99.18	30	49.68	30	49.68	30	49.68	30	49.68		
80	66.68	80	68.83	40	67.03	40	57.98	40	68.24	120	57.66	120	55.30	120	99.70	120	98.98	120	49.68	40	49.68	40	49.68	40	49.68		
140	66.68	140	68.83	50	66.85	50	57.98	50	68.23	150	57.38	150	55.30	150	99.70	150	98.87	150	49.68	50	49.68	50	49.68	50	49.68		
160	66.68	160	68.85	60	66.85	60	57.98	60	68.23	180	57.38	180	55.30	180	99.70	180	98.87	180	49.68	60	49.68	60	49.68	60	49.68		
200	66.68	200	68.85	70	66.78	70	57.98	70	68.23	210	57.28	210	55.30	210	99.70	210	98.87	210	49.68	70	49.68	70	49.68	70	49.68		
320	67.11	320	68.89	80	66.77	80	57.98	80	68.22	240	57.28	240	55.30	240	99.70	240	98.87	240	49.68	80	49.68	80	49.68	80	49.68		
380	67.16	380	68.93	90	66.77	90	57.98	90	68.22	270	57.09	270	55.30	270	99.70	270	98.87	270	49.68	90	49.68	90	49.68	90	49.68		
440	67.10	440	68.91	100	66.77	100	57.98	100	68.22	300	57.09	300	55.30	300	99.70	300	98.87	300	49.68	100	49.68	100	49.68	100	49.68		
500	67.13	500	68.94	130	66.77	200	57.98	200	68.22	330	57.09	330	55.30	330	99.70	330	98.87	330	49.68	130	49.68	130	49.68	130	49.68		
560	67.15	560	68.94	200	66.77	300	57.98	300	68.22	360	57.09	360	55.30	360	99.70	360	98.87	360	49.68	200	49.68	200	49.68	200	49.68		
620	67.15	620	69.03	230	66.77	360	57.98	360	68.22	390	56.99	390	55.30	390	99.70	390	98.87	390	49.68	230	49.6						

NOTE:
FOR 7(9-3):
131.04 g TO VOLATILE LOSS TEST
61.65 g TO HEP EXTRACTION TEST
61.13 g TO H2O EXTRACTION TEST

APPENDIX E
VENDOR TEST REPORTS

PARKSON CORPORATION

August 9, 1991

Southern Electrical International, Inc.
P.O. Box 1069
Wilsonville, AL 35186-1069

Attention: Mr. Darrell Moore

Reference: Laboratory Test Results

Dear Mr. Moore:

Thank you for the opportunity to test our equipment on your sludge sample. The test is complete and attached is the laboratory test summary.

The sample was tested at a concentration of 28.16 wt% and had a pH of 3.3. With the addition of Allied Colloids Percol 712 and Percol 778, 72-75 wt% was obtained in the final cake. Solids recovery of 95% was achieved. Expected capacity is 99 gpm/meter of press width. The above was tested using Parkson's Magnum® Press Series 3000 with its patented High Pressure Section.

Low pressure results can be found at the bottom of the summary. In short, using lower pressure Series 2000 allows increased hydraulic and solids capacity, but sacrifices cake dryness.

The recommended equipment for this application is two Magnum Press Series 3000 1.5 meter presses. Budget price for the equipment is \$280,000.00 plus freight and field service.

Please call if you have any questions or comments. Thank you for your interest.

Regards,

PARKSON CORPORATION

Matthew D. Rebmann
Sales Manager

MDR:mas

Enclosure:
As Noted

CC: Mr. Steve Hadley
Praxis Engineering
852 N. Hillview Drive
Milpitas, LA 95035

2727 N.W. 62ND STREET
FORT LAUDERDALE, FL 33309-1771

MAILING ADDRESS
P.O. Box 408399
FORT LAUDERDALE, FL 33340-8399

TELEPHONE
305 974-6610

TELECOPIER
305 974-6181

AN AXEL JOHNSON INC.
COMPANY

LABORATORY TEST SUMMARY (1)

MAGNUM® PRESS

Customer or

Consultant: Praxis Engineers for
Southern Electric International

Sample No.: 9090-0791

Plant or Project: Wilsonville, AL

Date Tested: 7/11/91

A. TEST RESULTS

Type of Sample

Upper Freeport Coal Tailings
(Coal refuse)

Sample As Received

67.02

Concentration Tested

28.16 (wt%) (4)

pH

3.3

Recommended Pretreatment

Polymer

1.2 + 1.3 lbs/ton dry solids
Allied Colloids Percol 712 @ \$1.15/lb
plus Percol 778 @ \$1.65/lb.

Estimated Chemical Cost(2)

\$3.53/ton dry solids

Unit Capacity

99 gpm/meter of press width

(1.0 meter 40")

7.5 tons dry solids/hr-meter
of press width (5)

Cake Solids

72-75 (wt%)

Solids Recovery

95 (%)

B. RECOMMENDED EQUIPMENT (3)

Anticipated Solids

Concentration

28.16 (wt%)

Number of Presses &

Series Number

Two (2) Series 3000-1.5 (6)

Total Capacity

297 gpm

22.6 tons dry solids/hr

Cake Solids

72-75 (Wt%)

Solids Recovery

95 (%)

(1) Tested on 0.25 meter press

(2) Cost is approximate and may change based on market conditions

(3) Assuming recommended pretreatment

(4) Specific Gravity ~ 1.08; % of solids passing 50 mesh = 82.51%;
100 mesh = 55.45%; 200 mesh = 36.64; 325 mesh = 28.34%

(5) Required capacity 20 tons per hour

(6) Series 2000-1.0 - 128 gpm/9.7 tons d.s. per hr; 66-69% cake
dry solids; 95% recovery

Date: 7/31/91

Approved

BJH

2727 N.W. 62nd Street
P.O. Box 408399
Fort Lauderdale, Florida 33340-8399
Telephone: 305 974-6610
FAX: 305 974-6182

▲ An Axel Johnson Inc. Company

END

**DATE
FILMED
5/08/92**