2
ORNL/M--1919

DE92 008113

Safety Assessment Document Gunite Tank Sludge Removal

R. D. Ehrlich
H. O. Weeren

Record copy

ENGINEERING LIBRARY
ORNL BLDG. 1000
EX. 4-6133

UNION
CARBIDE

NUCLEAR DIVISION
OXFORD, TENNESSEE

prepared for the U.S. DEPARTMENT OF ENERGY under
U.S. GOVERNMENT Contract W-7405 eng 26

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

NTIS price codes—Printed Copy: A10 Microfiche A01

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

X-OE-77

SAFETY ASSESSMENT DOCUMENT

GUNITE TANK SLUDGE REMOVAL

Prepared by

R. D. Ehrlich and H. O. Weeren
UCC-ND

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Issue Date: June, 1979

Document Number X-OE-77

SAFETY ASSESSMENT DOCUMENT

GUNITE TANK SLUDGE REMOVAL

Prepared by

R. D. Ehrlich and H. O. Weeren
UCC-ND

R. C. Robinson

Date: *1/23/79*

Recommended for Approval by UCC-ND (Operations Division Representative)

John H. Dwyer

Date: *4/2/79*

Recommended for Approval by UCC-ND Office of Operational Safety

H. Douglas MacNary

Date: *12/11/78*

Recommended for Approval by UCC-ND Engineering Division, Project Engineer

Richard D. Ehrlich

Date: *12/11/78*

Recommended for Approval by UCC-ND Engineering Division, Principal Engineer

C. C. Hawkins

Date: *6/7/79*

Approved by U.S. Department of Energy, Director, Engineering Division

R. J. Philippone for S. W. Ahrends

Date: *6/15/79*

Approved by U.S. Department of Energy, Director, Nuclear Research and Development Division

Prepared for the

UNITED STATES DEPARTMENT OF ENERGY
under U.S. Government Contract W-7405 eng 26

CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	1
2.0 DESCRIPTION	1
2.1 General Description	1
2.2 Gunite Tank Description	1
2.3 Sludge Description	3
2.4 Proposed Project Facilities	4
3.0 PROPOSED OPERATING PROCEDURE	6
4.0 SAFETY CRITERIA	11
5.0 PRINCIPAL SAFETY HAZARDS	13
5.1 Natural Phenomena	13
5.1.1 Seismic Effect	13
5.1.2 Winds and Tornadoes	14
5.1.3 Floods	15
5.2 Accidents and Failures	15
5.2.1 Criticality	15
5.2.2 Tank Dome Collapse	16
5.2.3 Tank Sidewall Leak	17
5.2.4 Fire	18
5.2.5 Failure of Services	19
5.2.6 Spills, Leaks, and Mechanical Failures	19
5.2.7 Operator Error	20

FIGURES

<u>Figure No.</u>	<u>Title</u>	<u>Page</u>
1	Gunite Tank Sludge Removal Location Plan	22
2	Gunite Tank Sludge Removal Topography and Subsurface Data	23
3	25' & 50' Dia. Gunite Tanks W-3 Thru W-10 Details	24
4	50' Gunite Tanks W-5 Thru W-10 Details	25
5	Cross-Sectional View of Typical Gunite Tank	26
6	Simplified Flow Sketch, Sluicing Operation with Recirculation	27
7	Simplified Flow Sketch, Slurry Transfer to Hydrofracture	28
8	Slurry Route from Tank Farm to Hydrofracture Site	29

GUNITE TANK SLUDGE REMOVAL

1.0 INTRODUCTION

This document presents the assessment and analysis of the safety hazards involved in the Gunitite Tank Sludge Removal Project. The six Gunitite tanks comprising the South Tank Farm were constructed in 1943. Since then, one or more of these tanks have been used continuously for the temporary storage of intermediate level radioactive wastes (ILW) before evaporation. Another tank has been used for the temporary storage of the concentrated ILW prior to its disposal. Upon completion of the new ILW System presently under construction, the six Gunitite tanks of the South Tank Farm will be removed from service. The purpose of this project is to remove the accumulated sludge from the Gunitite tanks and to transfer the sludge to the new Hydrofracture Facility. The ultimate disposal of the empty tanks is not included in this project.

2.0 DESCRIPTION

2.1 General Description

The South Tank Farm is located in Oak Ridge National Laboratory (ORNL) area 3507 approximately in the center of the ORNL facilities (Fig. 1). The 3507 area is about 120 x 180 ft and contains the six underground Gunitite tanks on a 60-ft center-to-center square matrix.* The waste disposal identification numbers for the three tanks in the north row, from west to east, are W-5, W-7, and W-9. The numbers for the tanks in the south row, from west to east, are W-6, W-8, and W-10. The south row of tanks is at a slightly lower elevation than the north row, conforming to the natural slope of the land surface. An enlarged layout of the 3507 area (Fig. 2) shows the dirt mounds above the Gunitite tanks and the conceptual locations of the footings to be installed for this project.

2.2 Gunitite Tank Description

"Very little information is available on the construction of the tanks."[†] The available information was obtained from the badly deteriorated construction drawings of the Clinton Engineer Works and the Cement Gun Company, Inc., in 1963 and used to prepare ORNL-TM-604* and new reference drawings E-56866 (Fig. 3) and D-56867 (Fig. 4). In some cases this information is:

* *An Analysis of the South Tank Farm and the Potential Hazards Associated with Continuous Use of the Tanks as Part of the Intermediate-Level Liquid Waste Disposal System*, F. R. Mynatt and C. C. Webster, ORNL-TM-604 (August 1963).

[†] Op. cit., F. R. Mynatt and C. C. Webster.

LEGEND

- NO. BORING
- NEW CONCRETE FOOTING FOR WORK PLATFORMS

SUBSURFACE DATA

FILE NO.	COORDINATES	SANDW. FLTH.	REF. ELEV.
NO. 1	1000.0 1000.0	0.0	700.0
NO. 2	1000.0 1000.0	0.0	700.0
NO. 3	1000.0 1000.0	0.0	700.0
NO. 4	1000.0 1000.0	0.0	700.0
NO. 5	1000.0 1000.0	0.0	700.0

REFERENCE INFORMATION:

- SJD-20539-0011
- SJD-20539-0012
- SJD-20539-0013
- SJD-20539-0014
- SJD-20539-0015

**FIGURE 2
CONCEPTUAL**

G. 3505

PROJECT: GUNITE TANK SLUDGE REMOVAL DRAWING: SITE TOPOGRAPHY AND SUBSURFACE DATA SCALE: 1" = 20'		SHEET: 1 OF 1 DATE: 10/1/77 BY: J. J. [illegible] CHECKED: [illegible]		GUNITE TANK SLUDGE REMOVAL SITE TOPOGRAPHY AND SUBSURFACE DATA GUNITE TANK SITE TOPO 10/1/77 1" = 20'	
--	--	---	--	---	--

PART SECTION OF 25' 1/2\"/>

NOTE:

ALL HOOP STEEL SHALL BE HIGH TENSILE STRENGTH WITH Y. & U. R. M. YIELD POINT OF 60,000 LBS PER SQ. IN. GUNITE SHALL HAVE MINIMUM COMPRESSIVE STRENGTH OF 8000 LBS PER SQ. IN. IN 28 DAYS. NOTES FOR INLET, OVERFLOW, VENT AND PURIFICATION TANK, ETC., TO BE SUPPLIED BY DU PONT AND INSTALLED BY CEMENT GUN COMPANY AT LOCATIONS DESIGNATED BY DU PONT. ALL EXCAVATION AND BACKFILLING BY DU PONT. SEE DU PONT DRAWINGS FOR LOCATION OF OPENINGS AND DIRECTION OF FLOOR SLOPE.

Sheet No.	Rev.	Date
57-A	1001	10/1/57
57-A	1002	10/1/57
57-A	1003	10/1/57
57-A	1004	10/1/57
57-A	1005	10/1/57
57-A	1006	10/1/57
57-A	1007	10/1/57
57-A	1008	10/1/57
57-A	1009	10/1/57
57-A	1010	10/1/57

FIGURE 3

Sheet No.	Rev.	Date
57-A	1001	10/1/57
57-A	1002	10/1/57
57-A	1003	10/1/57
57-A	1004	10/1/57
57-A	1005	10/1/57
57-A	1006	10/1/57
57-A	1007	10/1/57
57-A	1008	10/1/57
57-A	1009	10/1/57
57-A	1010	10/1/57

SECTION THRU DOME
Scale 1/8" = 1'-0"

NO.	REVISIONS				DATE	APPD	APPD
DRAWN	DATE	SUBMITTED	DATE	APPROVED	DATE		
DESIGNED	DATE	APPROVED	DATE	APPROVED	DATE		
CHECKED	DATE	APPROVED	DATE	APPROVED	DATE

[illegible]

SECRET

[illegible]

[Illegible handwritten notes]

THE FIVE NATIONAL ASSOCIATION
OF THE
JAPANESE NUCLEAR COMPANY
OF THE JAPANESE NUCLEAR COMPANY
OF THE JAPANESE NUCLEAR COMPANY

206 1 11-11-48 6836 65 13
 206 6

- a. Conflicting — for instance, the ORNL-TM-604 text reference on page 4 to the minimum concrete strength versus that given in the Cement Gun Company Drawing No. 679A appended. The appended Clinton Engineer Works drawing gives the same value as the ORNL-TM-604 text, but the reference drawing E-56866 gives the same value as the Cement Gun Company drawing.
- b. Wrong — for instance, the Cement Gun Company Drawing No. 679A and reference drawing E-56866 show a tank vent pipe of unspecified diameter at the top center of the tank dome. At the time the positive air sweep ventilation equipment was installed for Tank W-5 in September 1974, no sign of a vent pipe was found when the air sweep exhaust was installed at the top center of the dome.
- c. Or an ambiguous statement of fact based on an ambiguous reference — for instance, ORNL-TM-604 on pages 6 and 7 states that the interior surfaces of the ORNL Gunitite tanks "were painted with a bitumastic or asphaltic paint."* This statement is based on an ambiguous reference on Clinton Engineer Works Drawing No. W-68336.

Since (1) it is only physically possible at this time to inspect an insignificant portion of either the exterior or the interior of any one of the Gunitite tanks — and only with difficulty — and since (2) independent confirmation of the tank design information is not available, the information presented in the following paragraphs of Sect. 2.2 Gunitite tanks can only be given as data believed to be accurate and the best available. Additional data made available by the construction activities of the Gunitite Tank Sludge Removal project may contradict the information presented below.

Each of the Gunitite tanks in the 3507 area (Fig. 5) has an inside diameter of 50 ft, a vertical sidewall height of 12 ft referred to the tank floor at the center, a sidewall thickness of 6 in., and a nominal volume of 170,000 gal. The tank dome rises an additional 6 ft 3 in. at the center and has no internal supports. The tank dome is 10 in. thick except within 2 ft 6 in. of the vertical sidewall; within that area of the dome, the thickness increases (Figs. 3 and 4) as the dome edge is approached. This transition region provides for the proper transfer of stresses from the dome to the sidewall. The tank floor is 3 in. thick except for a thicker transition section starting about 4 ft from the sidewall.

Each tank was constructed of steel-reinforced Gunitite (a tradename for a mixture of portland cement, sand, and water sprayed in the form of a mortar from the nozzle of a cement gun against a form or a solid surface). The floor and dome were reinforced with wire mesh and reinforcing rod (rebar). The sidewall was reinforced with multiple layers of wire mesh, vertical rebar, and prestressed horizontal rebar hoops (Figs. 3 and 4).

* Op. cit., F. R. Mynatt and C. C. Webster.

FIGURE 5
CROSS-SECTION VIEW OF TYPICAL
GUNITE TANK

Table 1. Composition of sludge solids in three Gunite tanks^a (wt %)

	Tank		
	W-5 ^b	W-6	W-8
U	22.9	1.5	3.7
Th	6.4	0.8	14.2
Al	1.0	10.3	5.0
Ca	6.5	2.9	10.3
Fe	1.0	18.5	2.9
Pb	2.2	4.0	small
S	0.6	small	3.7
P	1.7	small	small
Cl	1.0	2.7	0.7
Na	small	small	small

^aThe analysis given for any tank does not add up to 100% because the analytical method used did not determine O, N, C, or H.

^bOf the six tanks, W-5 has the largest volume of sludge and the largest quantity of radionuclides.

2.4 Proposed Project Facilities

The project will provide the following facilities:

- A work platform with a grating-type deck to be installed above Tank W-10, which will be used as a surge tank, to support the concrete drill, the sluicer, pumps, and the television camera and light booms. The work platform support legs will straddle the tank; the tank will not bear any weight of the work platform or equipment. Removable lead shielding will be provided as required.
- Another work platform, similar to the one for Tank W-10, to be installed above the tank to be sluiced.
- A tank and mixing equipment to mix process water with bentonite and other suspension agents, as required, to form the initial sluicing mixture and transfer the bentonite-water mixture to Tank W-10.
- A hydraulic sluicing mechanism to be installed in the tank to be sluiced, supported from the work platform above the tank.
- A hydraulic sluicing mechanism as a spare or available to be installed in Tank W-10 if needed.

The following operator functions are identified as being critically necessary for safety:

- a. The shutdown of all operating process equipment such as pumps and sluicers, but not including the ventilation system for the Gunitite tanks.
- b. The capability to flush the slurry pipelines within the 3507 area with process water through the operation of appropriate valves.
- c. Although not completely operator-controlled, the ventilation for the Gunitite tanks.

3.0 PROPOSED OPERATING PROCEDURE

Construction of the proposed facilities will include the installation of the bentonite-water mixing equipment, the tank ventilation ducting for all six Gunitite tanks with dampers closed, as much of the piping around Tank W-10 as possible (with the work platform not in place), as much of the other piping as is reasonably possible, all support footings for both work platforms, the slurry pipeline from Tank W-10 to the existing valve pit near Tank W-6, the new piping inside the existing valve pit near Tank W-6, all of the new shielded containments for valves, instruments, and the grinder except those containments supported on or from the work platforms, the control room trailer, the high pressure hydraulic power unit, one work platform over Tank W-10, and the other work platform over the first tank to be sluiced (assumed to be Tank W-5 for discussion purposes in the remainder of this document). The vertical progressive cavity pumps, the sluicers, and the TV camera and light booms will be placed nearby but will not be placed on the work platforms; this will provide more working space for drilling the holes in the Gunitite domes. The holes will be drilled in the domes of Gunitite Tanks W-10 and W-5 by a special UCCND Plant and Equipment Division crew under the guidance of UCCND Engineering and with the assistance of UCCND Operations Division. The equipment installation in the drilled holes in these tanks will also be under the guidance of UCCND Engineering. The facilities will then be turned over to the Operations Division. The proposed operating procedure will be in five phases.

In phase one, the following procedure will be used at Tank W-10:

- a. If possible, the operator will add water to the tank to reduce to permissible levels (See Sec. 4.0, item 13) the radiation shine from material in the tank through the holes to be drilled in the tank dome. (The amount of water to be added will be field determined; each foot of water added will be about 14,700 gal.)
- b. The earth cover will then be carefully removed down to the bare Gunitite dome at each of the five locations where holes will be drilled, and nondestructive strength tests of the dome will be made at each location.

required on the work platform. The cover water from Step "a" will then either be disposed of as contaminated water or used in phase two.

In phase two, the following procedure will then be used at the tank to be sluiced first (Tank W-5 in this example):

- a. If possible, the operator will add sufficient water to the tank to reduce to permissible levels the radiation shine (from radioactive material in the tank) through the holes to be drilled in the tank dome. (The amount of water to be added will be field determined and may be either fresh water or water which has previously been used as cover water. Each foot of water added will be equivalent to about 14,700 gal.)
- b. The earth cover will then be carefully removed down to the bare Gunitite dome at each of the five locations (one location at a time) where holes will be drilled, and nondestructive strength tests of the dome will be made at each location. (For Tank W-5 only, the existing air sweep exhaust will be removed as necessary, and a temporary plug installed in the 12-in. hole.)
- c. A 34-in.-ID protective tube will be placed against the tank dome at the location of each hole to be drilled and will be grouted in place. Either the removed earth or clean fill dirt, as required, will then be backfilled around each tube to provide the maximum possible shielding against radiation.
- d. The pneumatically powered, modified existing core drill will be placed on the work platform; and the ventilation damper for the tank will be opened, providing a small negative pressure in the tank. Compressed air for the drill's air motor will be from a UCC-ND portable compressor via a temporary hose laid on the ground. A 24-in.-diam hole will be drilled at the top center dome location after three 4-in.-diam test cores are removed from the area of the large hole for strength tests. All reasonable efforts will be made to withdraw the 24-in.-diam concrete core from the tank.
- e. The second color TV camera and light boom will be inserted into the tank by crane via the new hole as quickly as possible and then sealed to the protective tube.
- f. The TV camera and light boom will be connected to remote controls, and turned on; the camera and lights will then be panned around the tank to examine the interior of the tank.
- g. In the absence of apparent tank interior irregularities, four additional 24-in.-diam holes will be drilled in the tank dome near the tank periphery, one at a time. Again, all reasonable efforts will be made to withdraw the 24-in.-diam concrete cores from the tank. (If a piece of equipment will not be immediately installed

FIGURE 6
SIMPLIFIED FLOW SKETCH,
SLUICING OPERATION
WITH RECIRCULATION

FIGURE 7
SIMPLIFIED FLOW SKETCH,
SLURRY TRANSFER
TO HYDROFRACTURE

- e. The TV camera and light boom with its winch assembly will then be transferred by a crane to its service platform nearby. A removable blind flange will be installed on the protective tube to seal the opening in the tank.
- f. Any other equipment suspended from the movable work platform into the tank just sluiced empty will be removed, and the hole sealed by a removable blind flange.
- g. The ventilation damper for the tank just cleaned will be closed.
- h. The work platform will then be detached from the footings and moved with a crane to the next tank to be sluiced.
- i. The water from the equipment rinsing will run into the tank and will either be transferred to another tank, using the existing intertank transfer pumps and piping, for use as cover water or be disposed of as contaminated water.
- j. The blind flanges on the protective tubes will be monitored, and shielding will be added as required (type and amount of shielding to be field determined).

Phases two through five of this proposed operating procedure will be repeated until all six tanks have been cleaned of sludge and are empty of slurry and liquid. (Note: It will be possible to add process water to Tank W-10 and then to transfer the water into any one of the other five tanks, using the facilities which will remain, in case Operations desires to do so to remove any possibility of tank floating or tank bottom failure during storm-caused flooding.)

4.0 SAFETY CRITERIA

The following safety criteria for the Gunitite tank sludge removal shall be applicable during the installation of the proposed facilities and the operation of the facilities for removing the sludge from the tanks, including the drilling of holes in the tank domes, the hydraulic sluicing of the sludge, the transfer of the resultant slurry to the hydrofracture facility, the periodic shifting of operations from one Gunitite tank to another as the tanks are emptied in sequence, and the ancillary operations of facility washup and equipment maintenance. These criteria shall not be construed to require secondary containment for the existing Gunitite tanks or other adjacent existing facilities of the waste systems and do not apply to existing facilities.

The following criteria have been used to guide the development of the conceptual design. When design details are available, a further evaluation of safety criteria compliance will be possible.

1. One level of redundancy shall be provided in the confinement of radwaste solution or slurry and may be provided by diverse means (example, doubly contained pipe).

elevation). These criteria do not apply to existing facilities, such as the Gunitite tanks or the ventilation exhaust stacks.

5.0 PRINCIPAL SAFETY HAZARDS

The Gunitite tanks in the 3507 area are about 35 years old and are not double contained. These tanks contain large quantities of fission products and significant quantities of other radwastes (Sect. 2.3). It is only physically possible at this time to inspect an insignificant portion of either the exterior or the interior of any one of the Gunitite tanks — and only with difficulty — so the structural integrity of the tanks is unknown. As these tanks continue to age, they represent an ever increasing safety hazard to ORNL personnel and to the environment due to the increasing risk of catastrophic failure of a tank — unless the sludge is removed from the tanks after the tanks are removed from service.

However, the safety hazards of the aging existing tanks and other existing facilities containing radioactive sludge will not be considered here; only those hazards presented by the proposed sludge removal effort will be addressed. Past work in the 3507 area includes (1) the successful sluicing out of Tank W-10 in the early 1950's by a similar procedure without adverse effects on personnel or the environment and (2) the core drilling of an 8-in.-diam hole and a 12-in.-diam hole in the dome of Tank W-5 with no known damage to the tank.

5.1 Natural Phenomena

5.1.1 Seismic Effects

No major additional hazard from seismic occurrence is foreseen. The radwaste slurry piping could be broken or otherwise damaged by a seismic event. Process equipment could also be damaged by such an event. However, of the process equipment which handles the radioactive slurry, the major part of each sluicer and the entire slurry handling part of each progressive cavity pump will be suspended down inside a Gunitite tank. The top parts of the sluicers, all other slurry processing equipment such as the the grinder, and all of the radwaste slurry piping on the discharge side of the pumps outside of the tanks will be double contained with leak detection instrumentation. (The slurry piping on the intake side of the progressive cavity pumps and the small portion of the discharge piping right next to the pumps will be single-wall pipe since it is entirely within a Gunitite tank; a failure of this single-wall pipe would create no hazard to personnel or the environment.) Since the slurry piping cannot be made self-draining except at unreasonably high cost and at an increased risk of jeopardizing the integrity of one or more Gunitite tanks, it will contain either radioactive slurry or contaminated

The additional hazard will be due to the possibility of a tornado passing over a work platform, causing an air flow reversal through the seals around the work-platform-mounted equipment and a consequent release of a small quantity of contaminated air to the environment. It is not possible at this time to estimate the magnitude or consequences of such a release.

5.1.3 Floods

No additional hazard is anticipated to be caused by the facilities to be installed for removing the sludge from the Gunite tanks. A recent analysis of a 100-year storm in the ORNL area has estimated that White Oak Creek and tributaries in the vicinity of the Gunite tanks in the 3507 area could back up to a water elevation of 786 ft.* All piping and equipment to be installed for this project will be above this elevation. Although the seals around equipment suspended into the Gunite tanks from the work platforms may not prevent the leakage of rainwater into the tanks, this would pose no hazard.

However, it should be noted that the bottoms of all six Gunite tanks are below the 786-ft elevation. Hence, there is an existing and continuing significant hazard from tank failure due to such a storm and flood and such possible failure mechanisms as tank bottom failure, tank sidewall failure, and tank flotation. The installation of the facilities provided by this project would not alter the hazard except that (1) as the sludge removal task goes on, more tanks will be empty and (2) the groundwater contamination resulting from a tank failure would be reduced by the fact that less radioactive material was present if the sludge had been removed before failure occurred. As indicated (Sect. 3.0), it will be possible to add process water to the empty tanks to prevent flooding-induced tank failure or tank flotation. However, any water added to the Gunite tanks for this purpose would have to be disposed of subsequently as contaminated water.

5.2 Accidents and Failures

5.2.1 Criticality

The present sample data available for the sludge in the Gunite tanks is unsatisfactory since each tank can be sampled at only one radial location with the existing facilities. Although the available data is almost certainly nonrepresentative of the sludge within the 50-ft-diam tanks, it is not possible to obtain any better samples with the existing sampling facilities. However, monitoring of the radiation spectrum in the tanks and of liquid and sludge temperatures in the tanks indicate that the only reaction occurring is the normal decay of fission products and transuranics present. Therefore, either the quantity of fissile material

* Private communication, R. O. Daugherty, April 3, 1978.

temporarily seal the opening as soon as possible with a layer of plastic, using care to avoid the radiation coming through the opening from the radioactive material in the tank, and would suspend operations. As soon as the size and shape of the opening have been determined, a better seal would be designed, fabricated, and installed. Operating personnel would then assess the feasibility of continuing operations on that tank with the proposed project facilities and proposed operating procedures. Any dirt from the dome earth cover falling into the tank with the portion of the dome would be treated as additional sludge. Any fallen part of the dome, even if it does not damage the tank floor when it hits, would interfere with the sluicing operation unless it fragments into small pieces.

The collapse of a major part of a dome or of an entire tank dome at any time would probably release approximately one curie of contaminated air to the plant environment. Such a failure after the installation of the proposed project facilities and when operations have started on that tank would have serious effects on the operations concerning that tank. The collapsed dome and earth cover might block the ventilation system. The earth cover dropped into the tank would provide shielding from the radiation hazard of the majority of the sludge, but the environment might be exposed to some surface contamination on the upper part of the tank sidewall, if the dome failed around the periphery. The natural circulation of air into the tank after such a collapse could entrain the surface contamination and quickly spread it outside the 3507 area. Upon such a collapse occurring, flow limitation (by design) in the exhaust line will preserve the vacuum in the remainder of the ventilation system. The escape of radioactively contaminated particles could be limited by temporarily covering the tank with an edge-weighted plastic sheet (emergency materials will be available on site before operations commence), using all possible precautions to limit exposure to the personnel involved. Further operations on the tank would require ground surface cleanup; the erection of a containment shell; the analysis of whether hydraulic sluicing or mechanical removal of earth cover, dome fragments, and sludge is now the more feasible; and the installation of suitable equipment.

5.2.3 Tank Sidewall Leak

Although the discharge pressure and, consequently, the force of the sluicing jet will vary up to 150 psig at the control of the operator by varying the operating characteristics of the sluice pump supplying the sluicer, the actual pressure to be used will be field determined. At whatever sluicer discharge pressure is used, there is a possibility that the impact of the sluicing jet on an unsuspected, particularly weak section of the tank sidewall may breach the wall or that the jet may uncover an existing hole in the wall which had been plugged until then with thick, immobile sludge. If either of these events were to occur, some slurry containing radioactive sludge particles would leak from the tank into the surrounding French drain and dry well system. The radioactivity associated with the leaking slurry would be detected by the dry well radiation monitors. Administrative procedures will require that

the tank, producing an air sweep across the tank from inleakage of air around equipment suspended in the tank and from air coming in through the existing "breather" vent. During all other times, the existing breather on the tank will be in service. Therefore, no significant accumulation of flammable gases is possible. Moreover, the sludge contains only trace amounts of organics and is nonflammable.

Although a fire in the trailer which will be provided for a control room is possible, the only effect would be to destroy operating instrumentation and controls. There would be no breach of containment of radioactive materials, and there would be no radiological hazard to the public. The storage of bulk quantities of flammable materials near the control room or the work platforms will not be permitted.

5.2.5 Failure of Services

The failure of services could involve any one or combination of: (1) process water to the 3507 area, (2) instrument air to the control room trailer, (3) electrical power to the hydraulic power unit and process equipment, (4) electrical power to the control room instrumentation, and (5) electrical power to the fans or mechanical fan failure at the 3039 Stack.

With the exception of the last of the possible failures, there would be no possible breach of containment of radioactive materials, and no hazard would result. However, in each of the five possible events, administrative procedures will require the operator to shut down all operations immediately (in case the event did not shut down all operations, per se) to protect the equipment. No emergency power or backup equipment is required for safe shutdown. In case of a lighting failure at night, flashlights will be used.

Since the fans at the 3039 Stack will be the source for the slight negative pressure to be maintained in Tank W-10 and in the tank being worked on, a failure of electrical power to these fans would create a hazard if (1) there were no backup power sources for the fans and (2) the failure were to occur at the time when holes were being drilled in a Gunitite tank dome. Specifically, the hazard would be possible outflow of contaminated air from the tank. However, the fan normally in service for this area is on the emergency power system in case normal power fails, and there is a steam-turbine-driven standby fan in case of mechanical fan failure or if normal power and emergency power both fail. Therefore, no hazard would result.

5.2.6 Spills, Leaks, and Mechanical Failures

Radioactive liquid or slurry leaks from the slurry piping and process equipment other than those caused by seismic effects (Section 5.1.1) are possible. However, (1) the slurry piping will be buried double-wall

It will be possible for the operator to inadvertently operate the sluicer under manual control with the sluicer nozzle motionless in one position or for the automatic nozzle controls to fail, keeping the nozzle in one position, at maximum discharge pressure for a long enough time to damage the tank sidewall. However, it is believed that it would take many hours, possibly days, for the sluicer jet to pound a hole in the tank wall. The consequences of such an event are assessed in Sect. 5.2.3. It is anticipated that the operator will be watching the sluicing operation in the TV monitor; presumably, the operator would realize that the jet is impinging constantly on one part of the tank wall before serious damage is done and would correct the operation of the sluicer mechanism. When the operator will be using the sluicer on manual control, it is assumed that he will avoid having the sluice jet hitting a single spot on the tank sidewall or bottom long enough to significantly damage the sidewall or bottom.

END

DATE
FILMED

4/10/92