DOE/MC/11076--3061

DE92 001142

**Results of Phase II Postburn Drilling, Coring, and Logging:
Rocky Mountain 1 Underground Coal Gasification Test
Hanna, Wyoming**

Topical Report

**R.L. Oliver
S.R. Lindblom
J.R. Covell**

APR 17 1992

February 1991

Work Performed Under Cooperative Agreement No.: DE-FC21-86MC11076

For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
Morgantown, West Virginia

By
Western Research Institute
Laramie, Wyoming

MASTER

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

**Results of Phase II Postburn Drilling, Coring, and Logging:
Rocky Mountain 1 Underground Coal Gasification Test
Hanna, Wyoming**

Topical Report

**R.L. Oliver
S.R. Lindblom
J.R. Covell**

Work Performed Under Cooperative Agreement No.: DE-FC21-86MC11076

For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880

By
Western Research Institute
P.O. Box 3395
University Station
Laramie, Wyoming 82071

February 1991

Blank

ii

TABLE OF CONTENTS

	<u>Page</u>
SUMMARY.....	iv
INTRODUCTION.....	1
Background.....	1
Objectives.....	2
INVESTIGATION METHODS.....	3
Phase II Plan.....	3
Phase II Drilling, Coring, and Logging Methods.....	3
RESULTS.....	6
ELW Module.....	6
CRIP Module.....	7
CONCLUSIONS.....	8
ACKNOWLEDGEMENT.....	9
DISCLAIMER.....	9
REFERENCES.....	10
APPENDIX A. Tables and Figures.....	11
APPENDIX B. Drilling Logs.....	29
APPENDIX C. Geophysical Logs.....	64
APPENDIX D. Operations Summary and Mass Balance Data.....	82

SUMMARY

The Rocky Mountain 1 (RM1) Underground Coal Gasification (UCG) site consisted of two different module configurations: the controlled retracting injection point (CRIP) and elongated linked well (ELW) configurations. The postburn coring of the RM1 UCG site was designed in two phases to fulfill seven objectives outlined in Western Research Institute's Annual Project Plan for 1989 (Western Research Institute 1989). The seven objectives were to (1) delineate the areal extent of the cavities, (2) identify the extent of roof collapse, (3) obtain samples of all major cavity rock types, (4) characterize outflow channels and cavity stratigraphy, (5) characterize the area near CRIP points and ignition points, (6) further define the structural geology of the site, and (7) identify the vertical positioning of the horizontal process wells within the coal seam. Phase I of the coring was completed during the summer of 1989 and served to partially accomplish all seven objectives. A detailed description of phase I results was presented in a separate report (Lindblom et al. 1990). Phase II, completed during the summer of 1990, was designed to complete the seven objectives; more specifically, to further define the areal extent and location of the cavities, to evaluate the outflow channels for both modules, and to further characterize the structural geology in the ELW module area.

The project objectives were met by drilling nineteen boreholes: eleven in the CRIP module and eight in the ELW module. Four of the eleven CRIP boreholes and two of the eight ELW boreholes were partially cored. In relation to the specific phase II objectives, the ELW cavity was symmetrical about the horizontal production well and extended west to the casing shoe. A structural deformation present in the ELW module area was located between EPBC-5 and VIW-1. It stepped down to the east and had a stratigraphic displacement of 6 to 8 ft. The CRIP cavity had a well-developed outflow channel and was symmetrical about the horizontal injection well, which was skewed slightly south from due east. An excellent core of the CRIP cavity roof transition zone from unaltered to highly altered material was recovered.

The phase II program, in conjunction with phase I results, effectively completed all seven objectives originally proposed for the postburn coring program.

INTRODUCTION

Background

The Rocky Mountain 1 (RM1) Underground Coal Gasification (UCG) test was conducted from November 16, 1987, through February 26, 1988 (United Engineers and Constructors 1989), at a site approximately one mile south of Hanna, Wyoming (Figure 1). The test consisted of dual module operation to evaluate the controlled retracting injection point (CRIP) technology, the extended linked well (ELW) technology, and the interaction of closely spaced modules operated simultaneously. The test caused two cavities to form in the Hanna No. 1 coal seam and associated overburden. The Hanna No. 1 coal seam was approximately 30 ft thick across the site and averaged a high-volatile C bituminous rank. The coal seam was overlain by sandstones, siltstones, and claystones deposited by various fluvial environments. The coal seam was considered an aquifer; however, it was separated from the nearest overlying water-bearing unit by a layer of strata of low permeability having a thickness greater than 100 ft. The coal seam contained several shaley zones. The upper extent of the lower shaley zone (approximately 5 ft from the base of the coal) defined the lower extent of the coal seam for the RM1 test. Details of the geology and hydrology are reported by Oliver (1987a) and Mason et al. (1987).

The ELW module consisted of two vertical injection wells (VIW-1 and VIW-2) intersecting horizontal production well PW-1 (Figure 2). The ELW module operated for 57 days and consumed approximately 4,430 tons of coal. The module produced 170 million scf of dry gas with an average heating value of 261 Btu/scf. Although the gas heating value was satisfactory, several problems were encountered with the module operation. Thermocouple data suggested that gasification occurred only in the upper part of the coal seam. The location of the horizontal borehole and injection point in the coal seam reduced resource use and gasification efficiency. In addition, the water content in the ELW product gas was excessive, being twice the average content of the CRIP product gas. The operation of this module was terminated early because excessive oxygen was detected in the product gas.

The CRIP module consisted of a vertical production well (CPW-2), a horizontal production well (CPW-1), and a horizontal injection well (CIW-1) (Figure 2). CIW-1 contained a 270-foot long ATSI 304 stainless steel liner inserted through the casing into the open borehole. The CRIP module operated for approximately 93 days consuming approximately 11,300 tons of coal. The module produced 447 million scf of dry gas with an average heating value of 287 Btu/scf. Initially, the coal was ignited at the end of the liner. Well CPW-2 was used for ignition of the coal and initial production. Once wells CIW-1 and CPW-1 became pneumatically linked, production was shifted from CPW-2 to CPW-1. Gasification continued in this configuration until the efficiency decreased to a preset point based on gas heating value. At this point, the ignitor-burner inside the liner was retracted approximately sixty ft from the end of the liner. The burner was used to burn off the liner to expose fresh coal to the UCG process and to reignite the coal to continue gasification. After reignition, the burner was retracted back

into the liner. This process was called a CRIP maneuver. Three such maneuvers were performed during the RM1 test. Each CRIP maneuver developed individual cavities, which eventually become interconnected as gasification progressed. In addition, shortly after the second CRIP maneuver, an unexplained 30-ft shortening of the liner occurred. This occurrence was termed the auto-CRIP. A summary of operations and mass balance data is presented in Appendix D.

Objectives

The postburn coring program provided critical data for determining the extent of cavity growth away from the process wells and aides in determining the efficiency and success of the UCG test. Inspection and evaluation of affected materials may show potential environmental problems and solutions. The geohydrologic structure of the coal and boundary strata served as the reactor vessel for the UCG process and was the major influence on the overall efficiency of the process.

Seven specific objectives were developed to guide the RM1 postburn coring program. The objectives were to (1) delineate the areal extent of the cavities, (2) identify the extent of roof collapse, (3) obtain samples of all major cavity rock types, (4) characterize the outflow channels and cavity stratigraphy, (5) characterize the area near CRIP points and ignition points, (6) further define the structural geology of the site, and (7) identify the vertical positioning of the horizontal process wells within the coal seam.

The postburn coring program was designed in two phases to meet these seven objectives. The first phase was to provide a general screening criteria for the data and meet as many of the objectives as possible. The second phase was to fill data gaps and provide refinements based on results of the first phase. Phase I of the project was completed during the summer of 1989. Detailed results are presented in a separate report (Lindblom et al. 1990). The results showed that (1) the ELW cavity extended farther west, and the CRIP cavity was located 5-10 ft farther south than anticipated; (2) roof collapse was contained within the overburden unit immediately above the coal in both modules; (3) samples of all major rock types were recovered; (4) insufficient data were obtained to characterize the outflow channels, but cavity stratigraphy was well defined; (5) boreholes near the CRIP points and ignition points did not exhibit characteristics significantly different from other boreholes in the cavities; (6) a fault zone was detected between VIW-1 and VIW-2 that stepped down to the east; and (7) PW-1 was only 7-12 ft below the top of the coal seam in the eastern part of the ELW module, and CIW-1 was located 18-20 ft below the top of the coal seam in the CRIP module.

Phase I fulfilled many of the objectives outlined for the project. However, some areas still needed to be defined or refined. These areas included (1) identifying the lateral and western extent of the ELW cavity, (2) identifying the southern and eastern extent of the CRIP cavity, (3) characterizing the outflow channels, (4) further refinement of the location and nature of the structural deformation present in the

ELW module area, and (5) recovery of samples of the roof transition zone from unaltered to altered material.

INVESTIGATION METHODS

Phase II Plan

Eighteen boreholes were proposed to meet the objectives of phase II investigations (Figure 2). Core samples were lacking from the outflow channels, from very near the CRIP and ignition points, and from the uppermost part of the roof transition zone. This caused six of the 18 boreholes to be proposed for partial coring. The remaining information required to address the objectives could be acquired by drilling.

Eight boreholes were proposed in the ELW module area (Figure 2): two holes to define the western extent of the cavity, two holes to define the northern extent of the cavity, and four holes to define the southern extent of the cavity. One of the boreholes in the western end of the cavity and one of the boreholes in the northern end were to be partially cored.

Ten boreholes were proposed in the CRIP module area (Figure 2): one hole partially cored near the initial injection point (CPW-2), two holes to define the eastern extent of the cavity, two holes (one partially cored) to define the outflow channel along CPW-1, one partially cored hole near the first CRIP point, and four holes (one partially cored) to define the southern extent of the cavity. It was acknowledged in the phase II drilling and coring plan (Covell and Mason 1990) that onsite developments, drilling and core results from boreholes finished early in the project, could affect later borehole locations.

In addition to drilling and coring, phase II boreholes were to be geophysically logged. Historically, downhole logging of postburn boreholes has been difficult because of the caving nature of cavity material. Consequently, the logging sondes rarely advanced beyond the initial upper void. In addition, hole conditions at the RM1 site further complicate the logging effort. A bentonitic zone was present at a depth of approximately 200 ft that closed off the hole almost immediately after removal of the drill string. It was hoped that the logging sonde could be advanced to the upper void in at least a few of the phase II boreholes. Regardless of these conditions, the deviation of the borehole to a depth of at least 200 ft could be obtained. After completion of the drilling and logging, the holes were to be plugged to the surface with a bentonite mixture.

Phase II Drilling, Coring, and Logging Methods

Activities presented in the phase II project plan were implemented at the RM1 site during September and early October of 1990. A total of 19 boreholes (one more than originally planned) were drilled, of which six were partially cored (Table 1). The boreholes were drilled and cored using air with mist and foam injection. Eleven of the boreholes were placed in the CRIP module and eight were placed in the ELW module

(Figure 3). Borehole names are consistent with the format and numerical sequence used in phase I. Cores were collected using conventional coring techniques with a Midway 1500 drilling rig, split core barrels, and diamond core bits. A geologic record of each borehole was kept as each hole was drilled (Appendix B). The actual activities conducted during phase II followed the original plan with only a few exceptions.

Drilling operations began by defining the lateral extent of the ELW module. Borehole EPBC-13 was drilled first to help locate EPBC-14, which was to be cored. EPBC-13 was placed farther north than specified in the plan because the presence of surface pipes blocked rig access. The hole was drilled through unaltered overburden, unaltered coal, and four feet into the understrata. Drilling operations were moved to the location of borehole EPBC-14, and it was drilled. EPBC-14 was not cored as specified in the plan because we were not certain if the location was within the cavity. Data collected during the drilling of EPBC-14 showed that this location was close to but still outside of the cavity wall. The hole was drilled 21 ft into unaltered coal. Borehole EPBC-15 was placed about 2 ft closer to the PW-1 line than EPBC-14 to obtain a core to replace EPBC-14. EPBC-15 was drilled to 332 ft into slightly altered overburden and then cored. Hole caving became a problem at 361 ft, and two core runs only advanced the core bit to 363 ft. Coring equipment was removed and drilling commenced. The hole was then drilled to a depth of 381 ft, eleven ft into unaltered coal.

The western extent of the ELW cavity was defined by boreholes EPBC-16 and EPBC-17. Borehole EPBC-16 was drilled at a location about 45 ft farther east than specified in the drilling plan to avoid drilling on the undisturbed hillside present at the specified location. The hole was located as far west as possible while still remaining on the topsoil stripped and leveled area. This hole was drilled before borehole EPBC-17 to better locate that hole for obtaining core. EPBC-16 was drilled to a depth of 377 ft where char was plugging the bit. Borehole EPBC-17 was then placed at a location about 10 ft east of EPBC-16 and was cored from about 5 ft above the altered roof to 1 ft into unaltered coal. The hole could not be advanced beyond 377 ft because char backfilled behind the bit.

The southern edge of the ELW cavity was defined by boreholes EPBC-18, EPBC-19, and EPBC-20. Borehole EPBC-18 was placed as specified in the drilling plan and was drilled into the understrata. It was drilled before EPBC-19 to ensure that EPBC-19 was located within the cavity. Borehole EPBC-19 was then drilled in cavity material and 12 ft into unaltered coal. Shortly after completion of this hole, the release of accumulated air pressure from the drilling operation caused water in the hole to rise to the surface in pulses, filling the hole with collapsed material. Borehole EPBC-20 was drilled at the specified location, but the drill bit could only be advanced to a depth of 357 ft because of extensive hole caving. However, the hole did penetrate altered material, which was the main objective of drilling at this location.

Activities in the CRIP module began with drilling and coring the eastern extent of the CRIP cavity. Borehole CPBC-10 was drilled to a depth of 282 ft. Coring was started at 282 ft to ensure recovery of

core samples from the roof transition zone. Borehole CPBC-12 was then drilled within the cavity and penetrated 10 ft into unaltered coal. Borehole CPBC-13 was drilled to 320 ft; it was only cored from 320 to 355 ft because of extensive hole caving problems. Borehole CPBC-14 was then drilled as specified outside the cavity.

Boreholes defining the southern edge of the CRIP cavity were finished next. Borehole CPBC-15 was drilled to a depth of 377 ft and served to better locate borehole CPBC-16 for obtaining core. Water blew out of CPBC-13 during the drilling of CPBC-15, backfilling CPBC-13 with collapsed material. Borehole CPBC-16 was drilled and cored next. It was located east of CPBC-15 because of the topography and highly altered nature of CPBC-15. When making the connection after the first core run at a depth of 317 ft, large volumes of water and cuttings were blown out of CPBC-15 to a height of about 40 ft. The hole was eventually backfilled with caved material. A total loss of air circulation through CPBC-15 made it impossible to continue coring CPBC-16. The hole was not a total loss, however, because the core obtained includes the upper section of strata that was not recovered from CPBC-13. Boreholes CPBC-17 and CPBC-18 were then placed as specified in the drilling plan. CPBC-17 was drilled outside the cavity, whereas CPBC-18 was apparently drilled through the southern wall of the CRIP cavity.

Boreholes CPBC-11 and CPBC-19 served to define the outflow channel for the CRIP module. Borehole CPBC-19 was drilled in the outflow channel approximately 190 ft from the initial production well (CPW-2) along the CPW-1 line. CPBC-11 was placed nearer the initial CRIP gasification zone, approximately 65 ft from CPW-2 along the CPW-1 line. CPBC-11 was cored from the initial void to a depth 12 ft into unaltered coal.

Questions were raised concerning the last CRIP cavity; and therefore, an additional hole (CPBC-20) was drilled in that area. The hole was only advanced to a depth of 362 ft because char plugged the bit.

Downhole geophysical logging was conducted on two separate occasions during the project: 9/18-19 and 9/28 (Table 1). Geophysical logging was performed to help identify changes in lithology, determine borehole deviation, and determine where the boreholes intersect void space. The logging sonde was advanced to the initial void or beyond in only four of the 19 wells: CPBC-11, 12, 19, and 20 (Table 1). These holes were logged immediately after drilling. Three boreholes were not logged because of caving to the surface. Caving was due either to hydrologic connection to a nearby hole being drilled or extremely high water flow during drilling. In the remaining 12 holes, the logging sonde was advanced to or just beyond the bentonitic zone present at about 190 to 200 ft. These deviation surveys were useful; some of the holes exhibited deviations greater than 10 ft. Figure 3 shows these deviations as dashed lines extending outward from the borehole location. Reduced copies of the geophysical logs are provided in Appendix C.

At the completion of drilling and logging operations, all holes were plugged to the surface with a bentonite mixture. The surface hole locations were then surveyed.

RESULTS

ELW Module

Two of the eight boreholes completed in the ELW module were drilled or cored outside the cavity, two holes intersected the cavity but did not penetrate to the cavity base, and four holes intersected the cavity to the cavity base (Table 2). Drilling logs for ELW and CRIP boreholes are presented in Appendix B. The results were used to construct a map showing the areal extent of the cavity (Figure 4) and cross sections through the ELW cavity (Figures 5-9).

An objective for phase II was defining the western and northern extent of the ELW cavity. Drill holes EPBC-16 and EPBC-17 suggest that the western extent of the cavity likely extends to the casing shoe. The northern extent is defined by EPBC-13 and EPBC-14, with borehole EPBC-14 apparently located very near the wall of the cavity. In addition, the southern wall is further defined by EPBC-18 and EPBC-15, with both boreholes apparently located very near the cavity wall. The width of the cavity varies from approximately 50 ft, in the general vicinity of VIW-1 (Figures 5 and 6), to 25 ft, in the area about 40 ft west of VIW-2 (Figure 7). VIW-1 was used as the injection point for the first 47 days of the 57-day test. VIW-2 was used as the injection point for the last 10 days. The cavity in the area around VIW-1 is more extensively developed because of the longer burn duration and greater coal consumption. The length of the cavity is 310 ft if alteration to the casing shoe is assumed (Figure 4). The thick sequence of char noted in EPBC-16 (Figure 8) suggests that the western 30 to 40 ft of the cavity may have outflow channel characteristics. In general, horizontal production well PW-1 is approximately 6 to 8 ft below the top of the coal to the east of the structural deformation shown in Figure 8. PW-1 is located lower in the coal seam toward the west. In the area near EPBC-16 and EPBC-17, PW-1 is about 22 to 24 ft below the top of the coal. These results are in general agreement with phase I results.

An objective of the phase II drilling in the ELW area was to further define the nature of the structural deformation present between VIW-1 and VIW-2. A refined structural cross section was constructed using the coal elevations obtained from EPBC-18 and with previous data obtained from CH-6, CH-7, CH-8, EPBC-5, VIW-1, and VIW-2 (Figure 9). These results suggest a continuous coal seam dip from CH-7 to EPBC-5 with an anomalous elevation change at VIW-1. This structural deformation steps down to the east with a stratigraphic displacement of 6 to 8 ft. This displacement was interpreted as a fault because of the degree of displacement over a short horizontal distance. It could also be a sharp fold or fault zone. Any of these interpretations reduce the thickness of coal above CPW-1 in the east end of the cavity. Previous UCG test evaluations show that little or no coal was consumed below the horizontal production well (Oliver 1987b). The anomaly apparently did not inhibit the westward migration of the burn, probably because its displacement was small relative to the total thickness of the coal seam (about 20 to 25%).

CRIP Module

Two of the eleven boreholes in the CRIP module area were drilled outside the cavity, three holes did not penetrate to the cavity base, and six holes were drilled or cored within the cavity to the cavity base (Table 2). This information was used to construct a map showing the areal extent of the cavity (Figure 10) and cross sections through the cavity (Figures 11 through 15).

An objective for phase II was defining the eastern and southern extent of the CRIP cavity. The eastern extent of the cavity is approximately five ft east of CPBC-12 defined by drill holes CPBC-12 and CPBC-14. The southern extent is defined by CPBC-15 through CPBC-18, with borehole CPBC-18 apparently intersecting the southern wall of the cavity. The width of the cavity varies from approximately 60 ft in the area of CPW-2 (Figure 11) and CCW-1 (Figure 12) to about 40 ft near the west end (Figure 13). CPW-2 was near the initial injection point, and CCW-1 was near the first CRIP maneuver. These two phases of the CRIP gasification lasted longer and consumed more coal than the final two phases, causing more extensive development of the cavity. It is apparent that CIW-1 is skewed slightly south of due east, assuming the symmetrical development of the cavity about this process well. The horizontal injection well in this configuration is farther to the south than we anticipated at the west end of the module, and it may extend farther to the north and east than we anticipated at the east end. The length of the cavity was at least 220-230 ft (Figure 14). The western extent is not known; however, we assume that its extent is limited by the approximate location of the last CRIP point. Phase I results suggest that CIW-1 is approximately 20 ft below the top of the coal.

An additional objective of phase II was to characterize the outflow channels. The outflow channel was defined by results from CPBC-11 and CPBC-19 (Figure 15). At the CPBC-11 location, the outflow channel exhibited cavity characteristics including extensive roof involvement. This location may have been transitional between the gasification cavity (flat bottom, vertical sides, and roof collapse) and the outflow channel (thick char zone, no roof collapse). At the CPBC-19 location, 14 ft of char suggests a more standard outflow channel characteristic. The char extends up to unaltered coal.

During the drilling of CPBC-16, extensive amounts of water were forced out of CPBC-15 before encountering altered material. This may be the result of induced air pressure in CPBC-16, which caused water to flow through radial fractures to CPBC-15. These fractures may have directly connected the two boreholes, or they may have indirectly connected them via the cavity (see drilling log CPBC-16, Appendix B).

CONCLUSIONS

The specific objectives of phase II drilling were accomplished. These objectives include (1) identifying the lateral and western extent of the ELW cavity, (2) identifying the southern and eastern extent of the CRIP cavity, (3) characterizing the outflow channels, (4) further refinement of the location and nature of the structural deformation present in the ELW module area, and (5) recovery of the roof transition zone from unaltered to altered.

Results show that the ELW cavity is symmetrical about the horizontal production well and extends west to the casing shoe. The structural deformation present in the ELW module area is located between EPBC-5 and VIW-1 and steps down to the east with a stratigraphic displacement of 6 to 8 ft. The CRIP cavity has a well developed outflow channel. The horizontal injection well appears to be skewed slightly south from due east. An excellent core of the CRIP cavity roof transition zone from unaltered to highly altered material was recovered.

The RM1 phase II postburn drilling, in combination with phase I results, successfully met all seven objectives originally proposed for the program.

ACKNOWLEDGEMENT

The authors express appreciation to the United States Department of Energy for funding of this work under Cooperative Agreement Number DE-FC21-86MC11076 and Grant Number DE-FG21-88MC25038.

DISCLAIMER

Mention of specific brand names or models of equipment is for information only and does not imply endorsement of any particular brand.

REFERENCES

- Covell, J.R., and G.M. Mason, 1990, Rocky Mountain 1 Postburn Coring-Phase II, Plans and Specifications. WRI report to DOE, Laramie, WY, WRI-90-R029.
- Lindblom, S.R., J.R. Covell, and R.L. Oliver, 1990, Results of Phase I Postburn Drilling and Coring, Rocky Mountain 1 Underground Coal Gasification Site, Hanna Basin, Wyoming. WRI report to DOE, Laramie, WY, WRI-90-R053.
- Mason, J.M., R.L. Oliver, J.D. Schrieber, C. Moody, P. Smith, and M.J. Healy, 1987, Volume 1: Geohydrology of the proposed Rocky Mountain 1 UCG Site, Hanna, Wyoming. WRI report to DOE and GRI, Laramie, WY, WRI-90-R056
- Oliver, R.L., 1987a, Geologic Evaluation of the Proposed Rocky Mountain 1 UCG Site, Hanna, Wyoming. WRI report to DOE, Laramie, WY, DOE report DOE/MC/11076-2312
- Oliver, R.L., 1987b, Results from the Controlled Excavation of the Tono I UCG Cavity, Centralia, Washington. Proceedings of the Thirteenth Annual UCG Symposium, Laramie, WY, 343-354.
- United Engineers and Constructors, Stearns-Roger Division, 1989, Rocky Mountain 1 Underground Coal Gasification Test, Hanna, Wyoming, Summary Report, Volume 1, Operations. Stearns-Roger Project Report.
- Western Research Institute, 1989, Annual Project Plan. Unpublished WRI report to DOE, Laramie, WY, WRI-89-R047.

APPENDIX A
Tables and Figures

Contents of Appendix A

<u>Table</u>	<u>Page</u>
1. Borehole Drilling, Coring, and Logging Depths.....	13
2. Borehole Results.....	13

<u>Figure</u>	
1. Site Location Map.....	14
2. Proposed Phase II Borehole Locations.....	15
3. RM1 Phase I and Phase II Borehole Locations.....	16
4. Location of Postburn Boreholes, Process Wells, and Approximate Cavity Boundaries for the RM1 ELW Module.....	17
5. ELW Cross Section A'-A.....	18
6. ELW Cross Section B'-B.....	19
7. ELW Cross Section C'-C.....	20
8. ELW Cross Section D'-D.....	21
9. Structural Cross Section Through ELW Module.....	22
10. Location of Postburn Boreholes, Process Wells, and Approximate Cavity Boundaries for the RM1 CRIP Module.....	23
11. CRIP Cross Section A'-A.....	24
12. CRIP Cross Section B'-B.....	25
13. CRIP Cross Section C'-C.....	26
14. CRIP Cross Section D-D'.....	27
15. CRIP Cross Section E-E'.....	28

Table 1. Borehole Drilling, Coring, and Logging Depths

Hole Number	Drilling Summary		Logging Summary		
	Date	Drilled	Cored	Date	Depth
CPBC-10	9/17	0-282	282-372	9/18	262
CPBC-11	19/18	0-342	342-372	9/18	341
CPBC-12	9/18-19	0-382	---	9/19	344
CPBC-13	9/24	0-320	320-355	Caved to	Surface
CPBC-14	9/25	0-362	---	9/28	192
CPBC-15	9/25	0-377	---	9/28	194
CPBC-16	9/26	0-302	302-317	9/28	252
CPBC-17	9/26-27	0-362	---	9/28	313
CPBC-18	9/27	0-382	---	9/28	136
CPBC-19	9/27-28	0-400	---	9/28	379
CPBC-20	9/28	0-362	---	9/28	317
EPBC-13	9/11	0-401	---	9/18	192
EPBC-14	9/11-12	0-381	---	Caved to	Surface
EPBC-15	9/12-13	0-332, 363-381	332-363	9/18	188
EPBC-16	9/14	0-377	---	9/18	188
EPBC-17	9/14-15	0-343	343-377	9/18	278
EPBC-18	9/15	0-395	---	9/18	249
EPBC-19	9/16	0-381	---	Cave to	Surface
EPBC-20	9/16	0-357	---	9/18	198

Table 2. Borehole Results

Hole Number	Coal Top	Cavity Top	Cavity Base	Affected Overburden	Coal Consumed	Coal Base
CPBC-10	354	334	371	20	17	?
CPBC-11	353	335	360	18	7	?
CPBC-12	351	336?	378	15	27	?
CPBC-13	352	313	?	39	?	?
CPBC-14	350	Unaltered	Unaltered	0	0	?
CPBC-15	354	326	373	28	19	?
CPBC-16	354	?	?	?	?	?
CPBC-17	354	Unaltered	Unaltered	0	0	?
CPBC-18	354	359	380	0	21	?
CPBC-19	354	356	370	0	14	385
CPBC-20	349	310	?	39	?	?
EPBC-13	368	Unaltered	Unaltered	0	0	398
EPBC-14	365	Unaltered	Unaltered	0	0	?
EPBC-15	361	332	370	33	9	?
EPBC-16	354	346	?	8	?	?
EPBC-17	355	348	376	7	21	?
EPBC-18	358	334?	358	24?	0	389
EPBC-19	359	325	369	34	10	?
EPBC-20	361	335	?	26	?	?

Figure 1. Site Location Map

Figure 2. Proposed Phase II Borehole Locations

Figure 3. RM1 Phase I and Phase II Borehole Locations

Figure 4. Location of Postburn Boreholes, Process Wells, and Approximate Cavity Boundaries for the RM1 EL1W Module

Figure 5. ELW Cross Section A'-A

Figure 6. ELW Cross Section B'-B

Figure 7. ELW Cross Section C'-C

Figure 8. ELW Cro

D'

Overburden

Iterated In-Place
Overburden

EPBC-5

EPBC-2

EPBC-8

EPBC-1

Rubble & Voids

Slag

Coal

Top of Coal

of Coal

Defined Base of Coal

is Section D-D'

Figure 9. Structural Cross Section Through ELM Module

Figure 10. Location of Postburn Boreholes, Process Wells, and Approximate Cavity Boundaries or the RM1 CRIP Module

Figure 11. CRIP Cross Section A'-A

Figure 12. CRIP Cross Section B'-B

Figure 13. CRIP Cross Section C'-C

Figure 14. CRIP Core

D'

Section D-D'

Figure 15. CRIP Cross

E'

Section E-E'

APPENDIX B
Drilling Logs

Contents of Appendix B
Geologic Log of Drill Hole

<u>Boring Number</u>	<u>Page</u>
EPBC-13.....	31
EPBC-14.....	32
EPBC-15.....	33
EPBC-16.....	36
EPBC-17.....	37
EPBC-18.....	40
EPBC-19.....	41
EPBC-20.....	42
CPBC-10.....	43
CPBC-11.....	49
CPBC-12.....	52
CPBC-13.....	53
CPBC-14.....	56
CPBC-15.....	57
CPBC-16.....	58
CPBC-17.....	60
CPBC-18.....	61
CPBC-19.....	62
CPBC-20.....	63

Page 1 of 1
Date 9/11/90

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase II) Project Number: 00131940
Boring Number: EPBC-13 Core Cut/Recovered: NA
Location: 20' North of EPBC-6 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 401' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					Drill 6" hole, 0-401'
		320	320-340, siltstone, dark gray		
		330			
		340	340-350, clayey siltstone, dark gray		
		350	350-370, siltstone, dark gray		
		360			
		370	368-397, coal, unaltered		
		380			
		390			
		400	397-400, siltstone, gray		
			401, T.D.

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase II) Project Number: 00131940
Boring Number: EPBC-14 Core Cut/Recovered: NA
Location: 15' S of EPBC-13, 25' N of V1W-1 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 381' Line Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					6" access hole 0-20 5 1/4" hole 20-380
		300	300-360, siltstone, dark gray, unaltered		
		310			
		320			
		330			
		340			
		350			
		360	360-362, coal, unaltered to slightly altered 362-365, slightly altered overburden 365-381, unaltered coal		
		370			
		380

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase II) Project Number: 00131930
Boring Number: EPBC-15 Core Cut/Recovered: 31.0/21.6
Location: 23' South of VW-1 Line on EPBC Field Geologist: R. Oliver/S. Lindblom
Total Depth: 380' 13, 14, 5, 6 line Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		330	332-348, slightly altered overburden, light and dark gray bands		9/12, drill with tri- cone (5¼") to core point 0-332'
		331			Tripped in core barrel tagged bottom at 332'
		332			9/13 Run 1 Cut 332-345=13.0 Rec. 332-345=13.0
		333			
		334			
		335			
		336			
		337			
		338			
		339			
		340			
		341			
		342

Geologic Log of Drill Hole EPBC-15 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		343			
		344			
		345			
		346	very crumbly		Run 2 Cut 345-361=16 Rec. 345-352.6=7.6 Q 352.6-361-8.4
		347			
		348	348-348.5, altered overburden, top 0.5' black and vesicular	3	
		349	348.5-349.6, altered overburden, red with black, no vesicles		
		350	349.6-351.0, altered overburden, gray with little red, some relict bedding		
		351	351.0-352.6, altered overburden, purplish- gray		
		352			
		353	352.6-357, lost core		
		354			Lots of water
		355			
		356			Return water warm
		357	357-359, void		Void 357-359
		358

Geologic Log of Drill Hole EPBC-15 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		359	359-361, lost core		
		360			
		361	361-362, altered overburden, purplish gray and altered overburden rubble, black and red from uphole		Run 3 Cut 361-363=1.0 Rec. 361-362=1.0
		362	returns indicate altered overburden, brown, altered claystone which overlies coal	4	Apparently coring hole slough @ 352'
		363			Run 4 Cut 362-363=1.0 Rec. -0-
		364			
		365			
		366	altered overburden with few small coal chips towards base (perhaps slag)		Lots of brown altered overburden in cutt- ings. Many problems coring.
		367			Switch to drill bit drill 363-381
		368			
		369			
		370	370-381, coal, unaltered		
		380	380, T.D.

Geologic Log of Drill Hole

Project Name: RMI Postburn Coring (Phase II) Project Number: 00131940
Boring Number: EPBC-16 Core Cut/Recovered: NA
Location: 60' East of PW1 Casing Shoe Field Geologist: R. Oliver/S. Lindblom
Total Depth: 377' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					Drill 4 3/4" 0-380
		300	300-346, clayey siltstone, dark gray, unaltered		
		310			
		320			
		330			
		340			
		350	346-347, void 347-359, altered overburden, purple gray rubble		Drilling very fast @ 347' Possible void ~1 @ top Definite void 354- 360 360-powdery coal (char?) in circu- lation water Void 361-370
		360	359-370, void char?		
		370	370-377, altered overburden, much of it brown and green with some similar to above (may have washed from uphole)		
		380	377, T.D. char on bit when tripped out! (place on sample bag)		
		390			
		400

Geologic Log of Drill Hole

Project Name: RMI Postburn Coring (Phase II) Project Number: 00131940
Boring Number: EPBC-17 Core Cut/Recovered: 34.0/14.5
Location: 70' East of PW1 Casing Shoe Field Geologist: R. Oliver/S. Lindblom
Total Depth: 377' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					Drill 6" hole to core point 0-340' 9/24 0-240 9/15 drill 240-343 core point
		343	343-347.5, siltstone, gray, unaltered		
		344		1	Run 1 Cut 343-359=16.0 Rec. 343-350.5=7.5 0 350.5-359=8.5
		345			
		346			
		347			
		348	347.5-349.5, slightly altered overburden, dark gray to black, locally rubble		
		349			
		350	349.5-350.5, altered overburden, dark gray to black		
		351	350.5-352, lost core		
		352	352-355, void		Drilled very fast 352-355, 356-358 void?
		353			
		354			
		355

Geologic Log of Drill Hole EFBC-17 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		355	355-356, lost core		
		356	356-358, void		
		357			
		358	358-360, lost core		
		359			
		360	360-361, void	2	Run 2 Cut 359-377=18.0 Rec. 370-377=7.0 Q 359-370=11.0
		361	361-370, lost core and small voids		360-361 void
		362			
		363			
		364			Drilling fast, quiet 364-377
		365			String lifted when kicked out pull down-char?
		366			
		367			
		368			
		369			
		370	370-372, altered overburden rubble, mostly purplish-gray		
		371

Geologic Log of Drill Hole EPBC-17 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		372	372-373.8, altered overburden, darker purplish-gray w/some greenish, more vesicular towards base		
		373			
		374	373.8-376.0, altered coal rubble		
		375			
		376	376-377, unaltered coal		Tight pulling out of bottom (probably char)
		377		T.D.	
		378			
		379			
		380			
		381			
		382			
		383			
		384			
		385			
		386			
		387

Page 1 of 1
Date 9/15/90

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase 11) Project Number: 00131940
Boring Number: EPBC-18 Core Cut/Recovered: NA
Location: 15' South of EPBC-10 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 395' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					Drill 4 3/4" to T.D.
		300	300-334, siltstone, gray, unaltered		
		310			
		320			
		330	334-358, siltstone, slightly altered?		Drilling faster from 334-340' 346-354' 356-360'
		340			Water stinks from 350' increased water Water warm
		350	fracturing below 350?		
		360	358-389, coal, unaltered		
		370			
		380			
		390	389-395, understrata		
			T.D.		
		400

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase II) Project Number: 00131940
Boring Number: EPBC-19 Core Cut/Recovered: NA
Location: 8' South of EPBC-10 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 381' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					Drill 4 3/4" hole to T.D. Air 0-130 Mist foam 130-381 Blade bit 0-160 Tri-cone 160-381
		300	300-325, siltstone, dark gray, unaltered		
		310			
		320			
			325-350, siltstone, slightly altered, gray		
		330			
		340			Lots of warm water coming out of hole (750 F)
		350	350-359, altered overburden rubble		Drilled fast 347-352 coal in returns
					Rubble or coal 354-357
		360	359-362, void		Drilled fast 359-361
			362-366, altered overburden rubble with small voids		Void 359-361
			366-369, void		Void 361-362
		370	369-380, coal, black, unaltered		Drill fast 362-366
					Void 366-369
		380	380-381, lower parting in coal		Not as much water 373'
			381 T.D.		Water flow increase 377'
		390			Out of coal at 380'

Page 1 of 1
Date 9/16/90

Geologic Log of Drill Hole

Project Name: RMI Postburn Coring (Phase II) Project Number: 00131940
Boring Number: EPBC-20 Core Cut/Recovered: NA
Location: 12' South of V1W1.2 line Field Geologist: R. Oliver/S. Lindblom
Total Depth: 357' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					Drill to 4 3/4" O-T.D. Blade 0-100 Tri-cone 100-T.D.
		300	300-335, clayey siltstone, dark gray, unaltered		
		310			
		320			
		330			Drilling fast 330-340 Acts rubbly drilling 337-340
		340	335-348, baked shale, altered siltstone		Drilling hard, slow 340-341
		350	348-350, void 350-357, altered overburden rubble		Drilling fast 346-348 Void 348-350 Drilling like rubble 350-355
		360	T.D., 357		Making lots of water 349
		370			Lost circulation 351 Drill fast 355-356 Then slow 356-357
		380			Trouble tripping back in hole
		390			
		400

Page 1 of 6
Date 9/17/90

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase 11) Project Number: 00131940
Boring Number: CPBC-10 Core Cut/Recovered: 90.0/73.3
Location: 5 Feet East of CPW-2 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 372' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		280			Drill 6" access hole 0-282
		281			Start 3" core 282'
		282	282-285.5, lost core	1	Run 1 Cut 282-297=15.0 Rec. 285.5-297=11.5 0 282-285.5=3.5
		283			
		284			
		285	285.5-334.5, siltstone, gray and dark gray, unaltered		
		286			
		287			
		288			
		289			
		290			
		291			
		292			
		293		2	
		294

Geologic Log of Drill Hole CPBC-10 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		295		2	
		296			
		297			
		298			Run 2 Cut 297-312=15.0 Rec. 297-311.7=14.7 Q 311.7-312=0.3
		299			
		300		3	
		301			
		302			
		303			
		304			
		305			
		306			
		307			
		308			
		309		4	
		310

Geologic Log of Drill Hole CPBC-10 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		311			
		312	311.7-312.0, Lost Core		
		313	Becoming finer grained		Run 3 Cut 312-326=14.0 Rec. 312-325.9=13.9 Q 325.9-326=0.1
		314			
		315			
		316		5	
		317			
		318			
		319			
		320			
		321			
		322			
		323			
		324			
		325		6	
		326	325.9-326.0, Lost Core

Geologic Log of Drill Hole CPBC-10 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		327			Run 4 Cut 326-340=14.0 Rec. 326-338.4=12.4 O 338.4-340=1.6
		328			
		329			
		330			
		331			
		332		7	
		333			
		334			Making lots of warm water from 334'. Drilling faster.
		335	334.5-338.4, slightly altered overburden, light and medium gray, some fracturing and rubbleization		
		336			
		337			
		338			
		339	338.4-340.0, lost core		
		340	340-345, slightly altered overburden, mostly rubble, light and medium gray	8	Run 5 Cut 340-354=14.0 Rec. 340-348.9=8.9 O 348.9-354=5.1
		341			
		342

Geologic Log of Drill Hole CPBC-10 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		343			Drilled fast 343-347
		344			
		345	345-348.9, altered overburden, black, mostly one piece, no vesicles, baked appearance		
		346			
		347		9	
		348			
		349	348.9-351.0, lost core		
		350			
		351	351-352, void		Void 351-352
		352	352-354, lost core		
		353			
		354	354-355, altered overburden rubble, dark gray		Run 6 Cut 354-362=8.0 Rec. 354-361.5=7.5 O 361.5-362=0.5
		355	355-361.5, altered overburden, lavender, black, greenish-gray banded, red @358.5, relict bedding, locally vesicular		Drilling slow
		356			
		357			
		358

Geologic Log of Drill Hole CPBC-10 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		359		10	
		360			
		361			
		361.5-362	lost core		
		362	362-363, altered overburden rubble, lavender, black and gray		
		363	363-363.5, altered overburden, black, vesicular		Run 7 Cut 362-372=10.0 Rec. 362-366.4-4.4 Q 366.4-372=5.6
		363.5-364	altered overburden, dark brown		
		364	364-366.2, altered overburden, red, black vesicular piece in middle		
		365			
		366	366.2-366.4, slag 366.4-372.0, lost core		
		367			Drilling fast 367-370
		368			
		369			
		370	370-371, void		Drilling very fast 370-371
		371	371-372, probably coal		
		372	T.D.		
		373			
		374

Geologic Log of Drill Hole

Project Name: RM1 Postburn C. ring (Phase II) Project Number: 00131940
Boring Number: CPBC-11 Core Cut/Recovered: 0.0/11.9
Location: On CPW-1 Line Field Geologist: R. Oliver/S. Lindblom
Total Depth: 372' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		335	335-336, void		Drill 6" access hole to 340'
		336			Start 3" core at 342'
		337			Possible void 335-336
		338			Drilled fast 336-340
		339			Drilled very fast
		340	340-342, void		340-342
		341			Lots of warm water from 336
		342	342-348.6, slightly altered overburden, light and medium gray		
		343		1	Run 1 Cut 342-357=15.0 Rec. 342-348.6=6.6 Q 348.6-357=8.4
		344			
		345			
		346			
		347			
		348			Drilling very fast
		349	348.6-351, void		Void 348-351

Geologic Log of Drill Hole CPBC-11 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		350			
		351	351-352, lost core		
		352	352-353, void		352-353, Drilling very fast (void?)
		353	353-357, lost core		
		354			354, Lost circulation
		355			354.5, Circulation back
		356			Drilling fast and smooth 355-357
		357	357-358.5, slightly altered overburden rubble		
		358	358.5-360, char	2	Run 2 Cut 357-372=15.0 Rec. 357-366.7=9.7 366.7-372=5.3 Coring smooth and fast 357-366
		359			
		360	360-366.7, coal, black, unaltered		
		361			
		362			
		363			
		364			
		365

Geologic Log of Drill Hole CPBC-11 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		366			
		367	366.7-372, lost core		Lost circulation 366.5
		368			
		369			Circulation back 369
		370			
		371			
		372	T.D.		
		373			
		374			
		375			
		376			
		377			
		378			
		379			
		380			
		381

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase II) Project Number: 00131940
Boring Number: CPBC-12 Core Cut/Recovered: NA
Location: 30' ENE of CPW-2 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 382' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					9/18 drill 4 1/4" to 82' 9/19 drill 4 1/4", 82- 382'
		300	300-342, claystone, dark gray, unaltered		
		310			
		320			
		330			
		340	342-356, void		
		350			Drilled very fast 347-356, probable void, lost circula- tion
		360	356-358, baked siltstone 358-361, void 361-378, altered overburden rubble		Some rubble, 356-358 Void 358-361 Making lots of water 361'
		370			Drilling like rubble 361-367, no circula- tion 361'
		380	378-393, coal, T.D.		Drill fast 367-368 (void?) Circulation back 371' Drilling like coal 378'
		390			
		400

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase 11) Project Number: 00131940
Boring Number: CPBC-13 Core Cut/Recovered: 35.0/7.2
Location: 4' North of TC-7 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 355' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		310	310-313, siltstone, gray, unaltered		Drill 6" hole to 320'
			313-322, baked overburden, dark gray to black		Start 3" core at 320'
		320			Lot of water @ 313
					Drilling faster 315
					Baked overburden chips on returns
		321			Top of altered zone about 313
					Run 1
					Cut 320-347=27.0
					Rec. 320-322=2.0
		322	322-324, lost core		0 322-347=25.0
					Lots of warm (90 F) water 321
		323			Drill fast 324-325, void
		324	324-325, void		
		325	325-327, lost core		
		326			
		327	327-335, void		327-335, drilled very fast, void
		328			
		329			
		330			
		331			
		332

Geologic Log of Drill Hole CPBC-13 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		333			
		334			
		335	335-339, lost core		
		336			
		337			
		338			
		339	339-340, void		Drill fast 339-340 void
		340	340-342, lost core		
		341			
		342	342-343, void		Drill fast 342-343
		343	343-344, lost core		
		344	344-347, void		Drill fast 344-347 void
		345			
		346			
		347	347-349.1, altered overburden rubble, dark gray to black		Run #2, 347-355=8.0 Rec. 347-352.2=5.2 0=2.8, Drill fast
		348			347-348

Geologic Log of Drill Hole CPBC-13 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		349	349.1-352.2, altered overburden, light and dark gray bands, relict bedding, few small vesicles	1	Drill fast 350-352
		350			
		351			
		352			
		353			
		352	352.2-355.0, lost core	2	Drill chattering at 353' like rubble Drilling very slow No chatter 354-355
		353			
		354			Hole repeatedly sloughing in. Unable to advance drill string beyond 331' despite repeated attempts.
		355	355 T.D.		
		356			
		357			
		358			
		359			
		360			
		361			
		362			
		363			
		364

Geologic Log of Drill Hole

Project Name: RMI Postburn Coring (Phase 11) Project Number: 00131940
Boring Number: CPBC-14 Core Cut/Recovered: NA
Location: 17' E of CPBC-12 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 362' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					Drill 4 1/4" 0-362
		300	300-350, siltstone, gray, unaltered		
		310			
		320			
		330			
		340			
		350	350-362, coal, unaltered		Drills like coal 350-362
		360	362 T.D.		
		370			
		380			
		390			
		400

Page 1 of 1
Date 9/25/90

Geologic Log of Drill Hole

Project Name: RMI Postburn Coring (Phase II) Project Number: 00131940
Boring Number: CPBC-15 Core Cut/Recovered: NA
Location: 23' S of TC-7 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 377' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					Drill 4 1/4" 0-377'
		300	300-326, siltstone, gray, unaltered		
		310			
		320			
		330	326-346, slightly altered overburden		Drilled fast 326--327, then lots of water, warm (not as voluminous as in the previous cavity wells) Drilled solid 327-340 Faster and chattery 340-346 Void? 346-348 Lost circulation Voids and soft rubble Drilled very fast 348-360 Hard 360-362 Fast, rubble 362-370 Very fast 370-373 Blowing water out of CPBC-13 Drilling like coal 373-377
		340			
		350	346-348, void 348-360, altered overburden rubble and small voids		
		360	360-362, altered overburden 362-370, altered overburden rubble		
		370	370-373, slag? 373-377, coal, unaltered		
		380	377 T.D.		
		390

Page 1 of 2
Date 9/26/90

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase 11) Project Number: 00131940
Boring Number: CPBC-16 Core Cut/Recovered: 15.2'/15/2'
Location: 5' ESE of CPBC-15 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 317' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		301			Drill 6" 0-302 Start 3" core at 302
		302	301.8-317, siltstone, gray, unaltered		Run 1 Cut 302-317=15' Rec. 301.8-317=15.2
		303		1	
		304			
		305			
		306			
		307			
		308			
		309			
		310		2	
		311			

Geologic Log of Drill Hole CPBC-16 (Cont.)

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		312			Blowing massive water out of CPBC-15, bubbling in CPBC-13.
		313			
		314			
		315			
		316			
		317	T.D. Note: Although material is still apparently unaltered at this depth, there are evidently fractures which extend from the cavity upwards to at least this depth.		Can't core T.D. hole. This core provides the upper unaltered section not retrieved from CPBC-13 to make a more complete core.
		318			
		319			
		320			
		321			
		322			
		323			
		324			
		325			
		326			
		327

Page 1 of 1
Date 9/26/90

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase II) Project Number: 00131940
Boring Number: CPBC-17 Core Cut/Recovered: NA
Location: 15' South of CPBC-15 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 362' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		300	300-330, siltstone, gray, unaltered		Drill 4 1/4" to T.D. 9/26/90 0-140 9/27/90 140-T.D.
		310			
		320			
		330	330-354, clayey siltstone, gray unaltered		
		340			
		350	354-362, coal, unaltered		354' drilling like coal
		360	362 T.D.		360' water flow in- creased, water warm (70°F) and sulfur order
		370			Apparently fairly close to cavity
		380			
		390			
		400

Geologic Log of Drill Hole

Project Name: RMI Postburn Coring (Phase II) Project Number: 00131940
Boring Number: CPBC-18 Core Cut/Recovered: NA
Location: 20' South of TC-9 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 382' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					Drill 4¼" to
		300	300-354, siltstone, gray, unaltered		
		310			
		320			
		330			
		340	(fractured below 340)		Increase in water @ 340'
		350	354-359, coal, black, unaltered		
		360	359-370, void		Lost circulation @ 362' Void 359-370 Hard 370-374
		370	370-374, altered overburden rubble 374-379, slag?		Circulation returned after tripped out to check bit and back in
		380	379-380, char 380, coal, black, unaltered 382, T.D.		Lots of water Drilled fast and chattery 374-380 Fast and quiet 380-382

Geologic Log of Drill Hole

Project Name: RM1 Postburn Coring (Phase II) Project Number: 00131940
 Boring Number: CPBC-19 Core Cut/Recovered: NA
 Location: 8' South of TC-2 Field Geologist: R. Oliver/S. Lindblom
 Total Depth: 400' Elevation: _____
 Drilling Method: Air rotary with mist/foam injection
 Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
		300	300-348, siltstone, gray, unaltered		9/27/90, drilled 0-80 9/28/90, 80-400
		310			
		320			
		330			
		340			
		350	348-349, coal? 349-354, siltstone, gray, unaltered, fractured		Void 348-349 Drilled fast from 349-352
		360	354-356, coal 356-363, char		Hard 352-354 Like coal 354-356 Lots of warm water @350
		370	363-370, void		Extremely fast 356-363
		380	370-385, coal, black, unaltered		Void 363-370
		390	385-400, understrata		
		400	400, T.D.		
			<div style="text-align: center;"> </div>

Geologic Log of Drill Hole

Project Name: RMI Postburn Coring (Phase II) Project Number: 00131940
Boring Number: CPBC-20 Core Cut/Recovered: NA
Location: North 50' West of TC-9 Field Geologist: R. Oliver/S. Lindblom
Total Depth: 362' Elevation: _____
Drilling Method: Air rotary with mist/foam injection
Contractor: NUCOR Driller: Bob Pickett Rig: Midway 1500

Formation/ Member	Lithologic Profile	Depth (ft)	Description	Core Box	Remarks (Core Cut/Recovered, Lost Circ., etc.)
					Drill 5 1/8" to T.D.
		300	300-310, siltstone, gray, unaltered		
		310	310-314, void		
			314-322, altered overburden		
		320	322-330, void		
		330	330-347, altered overburden rubble and small voids		Whole joint plus 5' drilled very fast 322-347
		340			
		350	347-362, altered overburden rubble and char		
		360	T.D. Presence of char (apparently several feet) indicates more of an outflow channel type geometry although there is extensive overburden involvement, and it is along injection line. Perhaps an immature cavity controlled by short duration of burn in this CRIP cavity.		Hard 356-359 Bit plugged, tripped out, tripped back in - bit plugged again with char - T.D. hole 362'
		370			
		380			

APPENDIX C
Geophysical Logs

Contents of Appendix C

Geophysical Logs

<u>Well</u>	<u>Page</u>
EPBC-13.....	66
EPBC-15.....	67
EPBC-16.....	68
EPBC-17.....	69
EPBC-18.....	70
EPBC-20.....	71
CPBC-10.....	72
CPBC-11.....	73
CPBC-12.....	74
CPBC-14.....	75
CPBC-15.....	76
CPBC-16.....	77
CPBC-17.....	78
CPBC-18.....	79
CPBC-19.....	80
CPBC-20.....	81

STRATA DATA INC. COMPENSATED DENSITY CALIPER / GAMMA RAY POINT RESISTANCE LOG	
FILE NO. 817 COMPANY: WESTERN RESEARCH INSTITUTE WELL: EPBC-13 FIELD: ROCKY MOUNTAIN 1 COUNTY: CARBON STATE: WYOMING LOCATION: SEC. 29 TWP. 14 N. RGE. 89 W. OTHER LOGS: DIRECTIONAL SURVEY	
PERMANENT DATUM: GROUND LEVEL ELEVATION: N/A LOG MEASURED FROM: GROUND LEVEL	
RUN NO.: ONE DATE: 08/18/90	
DRILLER: DEPTH OF BIT DIA.: 101 / 8" DEPTH OF BIT DIA.: CASING DP"/SIZE: NONE CASING DP"/SIZE:	
LOGGER: DEPTH: 184 CASING DEPTH: N/A BOT LOG INTERVAL: 182 TOP LOG INTERVAL: 0 TYPE FLUID IN HOLE: FORMATION WATER Bore of TEMP: N/A SAMPLE SOURCE: N/A FLUID LEVEL: 89 TIME SINCE CIRC: N/A RECORDED BY: McDONALD, WEFUM WITNESSED BY: MR. LINDOR, MR. B. VIER, MR. COVELL	

LOGGING DATA												
LOG FUNCTION	DATE	TIME	DEPTH (F)	DEPTH (M)	LOGGING RATE (F/HR)	DETECTISE TYPE	TEMP (F)	TEMP (C)	TEMP (F)	TEMP (C)	LOGGING INTERVAL	BY
G-O Density	08/18	21:00	200.3	100	10.0	20	Indet./Kd	14.70	0"	Ca 1.33	200	100
Caliper	08/18	21:00	200.3	10.0	20	Indet.	N/A	N/A	N/A	N/A	100	100
Caliper	08/18	21:00	200.3	10.0	20	N/A	N/A	N/A	N/A	N/A	100	100
Resistances	08/18	21:00	200.3	10.0	20	N/A	N/A	N/A	N/A	N/A	100	100

CALIBRATION FACTOR(S): Shop Calibration
 DIGITAL FILE NAME(S): 88113LOG
 REMARKS:

LOGGING DATA															
LOG Pulse/Time	Date Mo	LOG DATE		LOG TIME		SOLICIT TIME	W-ANAL		S-ANAL		COUNT INTERVAL				
		MM/DD	YY	HH	MM		1st-2nd PP/T	3rd-4th PP/T	1st-2nd PP/T	3rd-4th PP/T	FROM	TO	BY		
D-C Density	Chw	21	02	2:00.3	1:00	0.0	20	Stand./std	1.0 PP	0"	Ch 12	200 MC	100"	0	100"
Curvature	Chw	21	02	2:00.3	2:00	0.0	20	Index	N/A	N/A	N/A	N/A	170"	0	170"
Cell Spun	Chw	21	02	2:00.3	2:00	0.0	20	N/A	N/A	N/A	N/A	100"	0	100"	
Stand-off stress	Chw	21	02	2:00.3	2:00	0.0	20	N/A	N/A	N/A	N/A	100"	00	00	
CALIBRATION FACTOR(S): Ship Calib. data															
DIGITAL FILE NAME(S): 001181.06															
REMARKS:

LOGGING DATA													
1. FILE NAME(S)	2. RUN NO.	3. DATE	4. OPERATOR	5. TIME OF DAY	6. DATE	7. TIME	8. SECTION TYPE	9. 1st DEPTH	10. 2nd DEPTH	11. BORE TYPE	12. BORE CLASS	13. 1st DEPTH	14. 2nd DEPTH
O-C Drilling	One	21 02	2403	1.00	5.0	30	Under/hold	1.70"	0"	Co 12	280 MC	100"	0"
Drum	One	21 05	700	3.20	5.0	30	burst	N/A	N/A	N/A	N/A	170"	0"
Caliper	One	21 05	720	3.20	5.0	30	N/A	N/A	N/A	N/A	N/A	100"	0"
Resistivity	One	21 05	700	3.20	5.0	30	N/A	N/A	N/A	N/A	N/A	100"	0"

CALIBRATION FACTOR(S): Shop Calibration

DIGITAL FILE NAME(S): 00110100

REMARKS:

[illegible]

[illegible]

STRATA DATA INC.		COMPENSATED DENSITY CALIPER / GAMMA RAY POINT RESISTANCE LOG	
FILE NO. 973	COMPANY: WESTERN RESEARCH INSTITUTE		
	WELL: EPBC-20		
	FIELD: ROCKY MOUNTAIN 1		
	COUNTY: CARBON	STATE: WYOMING	
	LOCATION:		OTHER LOGS:
	SEC: 29 TWP: 14 N RGE: 89 W		DIRECTIONAL SURVEY
PERMANENT DATUM	GROUND LEVEL		
ELEVATION	N/A		
LOG MEASURED FROM	GROUND LEVEL		
RUN NO.	ONE		
DATE	08/18/82		
DRILLER:			
DEPTH OF BIT DIA.	157 / 8"		
DEPTH OF BIT DIA.			
CASING DPTH/SIZE	NONE		
CASING DPTH/SIZE			
LOGGERS:			
DEPTH	200'		
CASING DEPTH	N/A		
BCT LOG INTERVAL	100'		
TOP LOG INTERVAL	0'		
TYPE FLUID IN HOLE	FORMATION WATER		
Run of TEMP	N/A		
SAMPLE SOURCE	N/A		
FLUID LEVEL	110'		
TIME SINCE CORC	N/A		
RECORDED BY	MCDONALD, MEFUM		
WITNESSED BY	MR. LUDWIG, MR. BLIVER, MR. SCHELL		

LOGGING DATA													
LOG	DATE	TIME	DEPTH	TEMP	RES	GR	LOG	TIME	TEMP	RES	GR	LOG	TIME
Photo Probe													
Q-Q Density	08/21/82	10:00	100	100	100	100	100	100	100	100	100	100	100
Caliper	08/21/82	10:00	100	100	100	100	100	100	100	100	100	100	100
Resistivity	08/21/82	10:00	100	100	100	100	100	100	100	100	100	100	100

CALIBRATION FACTOR(S): Strip Calibration

QUALITY FILE NAME(S): 08210821

REMARKS:

STRATA		COMPENSATED DENSITY CALIPER / GAMMA RAY POINT RESISTANCE LOG	
FILE NO. 973		COMPANY: WESTERN RESEARCH INSTITUTE	
WELL: CPBC-10		FIELD: ROCKY MOUNTAIN 1	
COUNTY: CARBON		STATE: WYOMING	
LOCATION: SEC. 29 TWP. 14 N. RGE. 89 W.		OTHER LOGS: DIRECTIONAL SURVEY	
PERMANENT DATUM: GROUND LEVEL			
ELEVATION: N/A			
LOG MEASURED FROM: GROUND LEVEL			
RUN NO. ONE			
DATE: 06/18/90			
DRILLER:			
DEPTH at BIT DIA: 37 1/2"			
DEPTH at BIT DIA:			
CASING DEPTH / SIZE: NONE			
CASING DEPTH / SIZE:			
LOGGERS:			
DEPTH: 284'			
CASING DEPTH: N/A			
BOT LOG INTERVAL: 252'			
TOP LOG INTERVAL: 0'			
TYPE FLUID IN HOLE: FORMATION WATER			
Size at TOP: N/A			
SAMPLE SOURCE: N/A			
FLUID LOG: 1.33			
TIME SINCE OHC: N/A			
RECORDED BY: McDONALD, WENDY			
WITNESSED BY: MR. LEECH ON MR. SILVER, MR. COVELL			

LOGGING DATA											
LOG FUNCTION	DATE	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS
		LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS
		LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS	LOGGERS
C-O Density	06/21/90	284.3	1.00	0.0	20	16.70	0"	1.25	200	0"	287
Gamma	06/21/90	284.3	0.0	20	16.70	0"	1.25	200	0"	287	
Caliper	06/21/90	284.3	0.0	20	16.70	0"	1.25	200	0"	287	
Resistivity	06/21/90	284.3	0.0	20	16.70	0"	1.25	200	0"	287	

CALIBRATION FACTOR(S): Deep Cells ok

DIGITAL FILE NAME(S): 001161.00

REMARKS:

LOGGING DATA														
LOG PAGE(S)	DATE	LOCATION		CONTINENT		WAVE		SWATH		SPEED		OTHER DATA		
		AREA	POINT	DEPTH	DEPTH	TYPE	WAVE	SWATH	SWATH	SWATH	SWATH	SWATH	SWATH	
G-G Density	020	23 02	2403	100	0.0	20	1000/100	14.70'	8"	1/2 134	200 MC	241"	0	237
Recess	020	27 00	700	2.200	0.0	20	1000	N/A	N/A	N/A	N/A	237"	0	237
Cal spec	020	27 00	700	2.200	0.0	20	N/A	N/A	N/A	N/A	N/A	237"	0	237
Reference	020	27 00	700	2.200	0.0	20	N/A	N/A	N/A	N/A	N/A	237"	1.21'	21.0

CALIBRATION FACTOR(S): Ship Center offset

DIGITAL FILE NAME(S): 000112.00

REMARKS:

STRATA DATA INC.

**COMPENSATED DENSITY
CALIPER / GAMMA RAY
POINT RESISTANCE LOG**

FILE NO. 5173 COMPANY: WESTERN RESEARCH INSTITUTE

WELL: CPBC-12

FIELD: ROCKY MOUNTAIN 1

COUNTY: CARBON STATE: WYOMING

LOCATION: SEC. 29 TWP. 14 N. RGE. 89 W. DIRECTIONAL SURVEY

PERMANENT DATUM: GROUND LEVEL

ELEVATION: N/A

LOG MEASURED FROM: GROUND LEVEL

PLUT NO.: ONE

DATE: 06/18/80

DRIILLER:

DEPTH at BIT DIA. 367 / 8"

DEPTH at BIT DIA.

CASING OPTH/SIZE NONE

CASING OPTH/SIZE

LOGGED:

DEPTH 348

CASING DEPTH N/A

BIT LOG INTERVAL 348

TOP LOG INTERVAL 0

TYPE FLUID IN HOLE FORMATION WATER

Run at TEMP N/A

SAMPLE SOURCE N/A

FLUID LEVEL 130

TIME SINCE OHC N/A

RECORDED BY: McDONALD, WENDY

INTERPRETER: MR. LUBENOW, JR. OLIVER, MR. GOSSEL

LOGGING DATA													
LOG FUNCTION	DATE	TIME	DEPTH (FEET)	DEPTH (FEET)	DEPTH (FEET)	DEPTH (FEET)	DEPTH (FEET)	DEPTH (FEET)	DEPTH (FEET)	DEPTH (FEET)	DEPTH (FEET)	DEPTH (FEET)	DEPTH (FEET)
Si-D Density	06/18/80	1400	348	348	348	348	348	348	348	348	348	348	348
Survey	06/18/80	1400	348	348	348	348	348	348	348	348	348	348	348
Caliper	06/18/80	1400	348	348	348	348	348	348	348	348	348	348	348
Resistivity	06/18/80	1400	348	348	348	348	348	348	348	348	348	348	348

CALIBRATION FACTOR(S): 1.000

ORIGINAL FILE NAME(S): 5173.DAT

REMARKS:

COMPENSATED DENSITY CALIPER / GAMMA RAY POINT RESISTANCE LOG	
FILE NO. 913 COMPANY: WESTERN RESEARCH INSTITUTE			
WELL: CPBC-14			
FIELD: ROCKY MOUNTAIN 1			
COUNTY: CARBON		STATE: WYOMING	
LOCATION:		OTHER LOGS:	
SEC: 29 TWP: 14 N RGE: 89 W.		DIRECTIONAL SURVEY:	
PERMANENT DATUM: GROUND LEVEL		ELEVATION: N/A	
LOG MEASURED FROM: GROUND LEVEL		LOG NO.: 0116	
DATE: 08/28/90		CORRECTION: N/A	
DEPTH OF BIT DIA: 5 1/2"			
DEPTH OF BIT DIA: 5 1/2"			
CASING OPTM SIZE: NONE			
CASING OPTM SIZE: NONE			
LOGGERS:			
DEPTH: 194'			
CASING DEPTH: N/A			
BIT LOG INTERVAL: 192'			
TOP LOG INTERVAL: 0'			
TYPE FLUID IN HOLE: FORMATION WATER			
APP. TEMP: N/A			
SAMPLE SOURCE: N/A			
FLUID LEVEL: 118'			
TIME SINCE CURC: N/A			
RECORDED BY: MCDONALD, WED. J.			
WITNESSED BY: M. LINDGREN			

LOGGING DATA											
LOG FUNCTION	RAW DATA	LOGGED DATA	LOGGED DATA	LOGGED DATA	LOGGED DATA	LOGGED DATA	LOGGED DATA	LOGGED DATA	LOGGED DATA	LOGGED DATA	LOGGED DATA
G-M Density	1.00	2.182	2.182	1.00	2.182	2.182	1.00	2.182	2.182	1.00	2.182
Caliper	1.00	2.182	2.182	1.00	2.182	2.182	1.00	2.182	2.182	1.00	2.182
Caliper	1.00	2.182	2.182	1.00	2.182	2.182	1.00	2.182	2.182	1.00	2.182
Point Resistance	1.00	2.182	2.182	1.00	2.182	2.182	1.00	2.182	2.182	1.00	2.182

CALIBRATION FACTOR(S): Strip Calibration

DIGITAL FILE NAME(S): 9130-01-01-01

REMARKS:

COMPENSATED DENSITY CALIPER / GAMMA RAY POINT RESISTANCE LOG	
FILE NO. 373 COMPANY: WESTERN RESEARCH INSTITUTE			
WELL: CPBC-15			
FIELD: ROCKY MOUNTAIN 1			
COUNTY: CARBON		STATE: WYOMING	
LOCATION:			
SEC: 29 TWP: 14 N		RGE: B9 W.	
PERMANENT DATUM: GROUND LEVEL		OTHER LOGS:	
ELEVATION: N/A		DIRECT ORIAL SURVEY:	
LOG MEASURED FROM: GROUND LEVEL			
RUN TIME: ONE			
DATE: 08/28/90			
DRILLER:			
DEPTH OF BIT DIA: 377 / 8"			
DEPTH OF BIT DIA:			
CASING DEPTH/SIZE: NONE			
CASING DEPTH/SIZE:			
LOGGER:			
DEPTH: 100			
CASING DEPTH: N/A			
BOT LOG INTERVAL: 124			
TOP LOG INTERVAL: 0			
TYPE FLUID IN HOLE: FORMATION WATER			
RPT OF TEMP: N/A			
SAMPLE SOURCE: N/A			
FLUID LEVEL: 122			
TIME SINCE OPL: N/A			
RECORDED BY: McDONALD, DEFLUM			
WITNESSED BY: ME, JORDAN			

LOGGING DATA											
LOG FUNCTION	RUN NO.	MODEL	LOGGING UNIT	LOGGING UNIT	LOGGING UNIT	LOGGING UNIT	LOGGING UNIT	LOGGING UNIT	LOGGING UNIT	LOGGING UNIT	LOGGING UNIT
G-G Density	001	2100	2100	2100	2100	2100	2100	2100	2100	2100	2100
Gamma	001	2100	2100	2100	2100	2100	2100	2100	2100	2100	2100
Caliper	001	2100	2100	2100	2100	2100	2100	2100	2100	2100	2100
Point Resistance	001	2100	2100	2100	2100	2100	2100	2100	2100	2100	2100

CALIBRATION FACTORS: Stop Calibration
 DIGITAL FILE NAME(S) IN TO-CAL OUT
 REMARKS:

LOGGING DATA														
LOG FUNCTION	RAW NO.	LOGGING SET		LOGGING		LOG FILE		REMARKS		SUMMARY		LOGGING HISTORY		
		DATE	TIME	FILE	NO. OF PAGES	FILE	NO. OF PAGES	FILE	NO. OF PAGES	FILE	NO. OF PAGES	FILE	NO. OF PAGES	
G C Chemistry	One	21 02	1603	108	11.5	20	None/None	14 20	0"	C-1112	280 HC	11.2	0	300
Carriage	One	21 08	1611	230.3	11.0	20	None	N/A	N/A	N/A	N/A	204	0	304
Caliper	One	21 08	1611	120.3	11.0	20	N/A	N/A	N/A	N/A	N/A	300	0	300
Head drive	One	21 08	1611	230.3	11.0	21	N/A	N/A	N/A	N/A	N/A	300	124	190

CALIBRATION FACTOR(S): Ship Calibration

DIGITAL FILE NAME(S): 0170-C17A.06

REMARKS:

STRATA DATA INC.		COMPENSATED DENSITY CALIPER / GAMMA RAY POINT RESISTANCE LOG	
FILE NO. N73		COMPANY: WESTERN RESEARCH INSTITUTE	
		WELL: CPBC-1 B	
		FIELD: ROCKY MOUNTAIN I	
		COUNTY: CARBON STATE: WYOMING	
		LOCATION:	
SEC: 29 TWP: 14 N RGE: B3 W.		OTHER LOGS:	
PERMANENT DATUM:		GROUND LEVEL	
ELEVATION:		N/A	
LOG MEASURED FROM:		GROUND LEVEL	
POINT NO.:		ONE	
DATE:		09/28/00	
DRILLER:			
DEPTH OF BIT DIA:		5 1/2" 8"	
DEPTH OF BIT DIA:			
CASING OPTH / SIZE:		NONE	
CASING OPTH / SIZE:			
LOGGED:			
DEPTH:		130'	
CASING DEPTH:		N/A	
BIT LOG INTERVAL:		130'	
TOP LOG INTERVAL:		10'	
TYPE FLUID IN HOLE:		FORMATION WATER	
REV OF TEMP:		N/A	
SAMPLE SOURCE:		N/A	
FLUID LEVEL:		N/A	
TIME SINCE OAC:		N/A	
RECORDED BY:		W. DONALD MEDFORD	
REVISSED BY:		MR. LINDSEY	

LOGGING DATA													
LOG	DATE	TIME	DEPTH	LOG	TIME	DEPTH	LOG	TIME	DEPTH	LOG	TIME	DEPTH	LOG
G-G Density	09/28/00	21:00	2100	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Gamma	09/28/00	21:00	2100	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Caliper	09/28/00	21:00	2100	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

CALIBRATION FACTOR(S): Stop Calibration
 DIGITAL FILE NAME(S): IN PG-CELLAR
 REMARKS:
 Tool stuck in hole during logging.
 Fluid level below bottom logged interval, no Point Resistance Log.

<h1>COMPENSATED DENSITY CALIPER / GAMMA RAY POINT RESISTANCE LOG</h1>	
FILE NO. 5175		COMPANY: WESTERN RESEARCH INSTITUTE	
WELL: CPBC-19		FIELD: ROCKY MOUNTAIN 1	
COUNTY: CARBON		STATE: WYOMING	
LOCATION:		OTHER LOGS	
SEC: 29 TWP: 14 N		RANGE: 89 W	
PERMANENT DATUM ELEVATION LOG MEASURED FROM		GROUND LEVEL N/A GROUND LEVEL	
RUN NO.		CORE	
DATE		09-28-80	
DRILLER:		602 / 6	
DEPTH IN BIT DIA DEPT IN OF BIT DIA CASING OD IN / SIZE CASING ID IN / SIZE		NAME	
LOGGED		1301	
DEPTH CASING DEPT IN BOT LOG INTERVAL TOP LOG INTERVAL TYPE FLUID IN HOLE Boreal TEMP SAMPLE SOURCE FLUID LEVEL TIME SINCE ORG RECORDED BY INTERSECT BY		FORMATION WATER N/A N/A 110 N/A W-25-26-27-28-29 N/A

APPENDIX D

Operations Summary and Material Balance Data

Contents of Appendix D

<u>Table</u>	<u>Page</u>
Table D-1. Operations Summary, Rocky Mountain 1 UCG Project.....	84
Table D-2. Summary of Thermocouple Responses.....	85
Table D-3. Time Domain Reflectometry Data for the RM1 Project....	87
Calculation of Areal Extent of Cavities and Estimate of Geometry...	88

Table D-1. Operations Summary, Rocky Mountain 1 UCG Project

	Total Time, days	Operation Days	Coal Consumed, ton	Corrected Coal Consumed ^a , ton	Heat Loss In Situ &	Water Influx, gal/min	Average Gas Heating Value, Btu/scf
ELW Total	57.3	4.4-61.8	4,007	4,430	14.2	4.90	261
VIW-1	47.0	4.4-51.4	3,735	4,090	13.5	5.03	265 ^b
VIW-2	10.2	51.6-61.8	260	325	23.5	4.03	203
CRIP Total	93.0	9.7-102.7	9,877	11,277	9.6	3.16	287
1st Cavity	43.7	9.7-53.4	4,098	5,079	6.9	2.90	298
2nd Cavity	19.9	53.5-73.4	2,377	2,782	12.2	4.52	275
3rd Cavity	20.0	73.4-93.4	2,514	2,501	8.2	2.39	295 ^c
4th Cavity	9.3	93.4-102.7	880	856	18.8	3.03	247

^a Corrected for gas loss

^b Average includes initial air injection period, average for oxygen injection is 275 Btu/scf

^c Includes auto-CRIP

Table D-2. Summary of Thermocouple Responses

Well	Location	Initial Response	Failure	Notes
<u>ELW</u>				
VIW-2	tube tip	14.5	50.5	
	-10 ft	14.5	41.7	
	- 5 ft	14.5	51.9	
TC-11	-10 ft	27.0	27.0	TC below burnt off same time
	- 5 ft	21.0	27.0	
TC-12	-10 ft	42	NF	
	- 5 ft	60	NF	
	0	36	NF	
TC-13	-10 ft	10	10.5	TC below burnt off same time
	- 5 ft	6.8	11.1	
	0	5.5	11.5	
<u>CRIP</u>				
CIW-1	- 3 ft liner	8.6	11.0	
	- 25 ft liner	8.5	17.7	
	- 55 ft liner	8.6	17.7	
	- 85 ft liner	8.7	70.0	
	-115 ft liner	8.7	73.4	
	-145 ft liner	12.2	82	
	-175 ft liner	12.2	93.4	
	-205 ft liner	12.2	NF	
	ignitor tip	52.3	73.3	
	ignitor tube-13 ft	--	31.7	
CPW-2	dip tube	6.4	43.7	
	dip tube-26 ft	6.4	6.4	
TC-1	-20	69.8	69.9	
	-15	30.0	73.2	
	-10	30.0	76.7	
	- 5	35.0	58.2	
	0	35.0	77.8	
TC-2	-20	80.0	NF	Very minor responses
	-15	65.0	NF	
	- 0	50.0	NF	
TC-3	-15	38.3	38.4	
	-10	37.6	38.4	
	- 5	38.6	43.8	
	- 0	39.3	39.3	

Table D-2. Summary of Thermocouple Responses (continued)

Well	Location	Initial Response	Failure	Notes
TC-4	-20	45.0	59.0	
	-15	30.0	59.0	
	-10	25.0	65.4	
	- 5	30.0	66.0	
	- 0	30.0	69.7	
TC-7	-15	10.5	20.5	
	-10	16.5	20.6	
	- 5	20.3	59.2	
	- 0	20.8	59.2	
TC-9	-20	76.0	76.1	
	-15	22.0	76.1	
	-10	22.0	76.5	
	- 5	22.0	85.5	
	0	22.0	89.2	

Table D-3. Time Domain Reflectrometry Data for the RM1 Project

Time, Days	Length, ft	Rate, ft/day	Time, Days	Length, ft	Rate, ft/day
CRIP			VIW-1		
0.0	837.00		0.0	421.00	
24.000	833.00		24.000	423.00	
26.448	829.00		24.354	383.00	
28.125	823.00		28.604	379.00	
30.417	821.00		30.583	375.00	
32.563	265.00		32.542	248.00	
32.688	823.00		32.708	250.00	
33.417	826.00		33.458	244.00	
35.417	826.00		35.438	250.00	
52.313	816.00	0.4	52.323	239.00	
53.490	795.00		53.493	233.00	
57.333	795.00		57.354	228.00	
72.417	770.00	1.3	72.438	234.00	
73.438	735.00		78.438	234.00	
78.417	706.00		79.438	234.00	
79.417	704.00		93.587	231.00	
80.587	704.00		98.369	231.00	
81.438	704.00		99.500	231.00	
82.583	698.00		100.50	231.00	3.5
83.625	698.00				
84.719	702.00				
85.465	704.00				
86.354	698.00				
87.479	698.00				
91.375	694.00				
93.375	686.00	2.45			
93.396	660.00				
93.479	657.00				
94.354	659.00				
94.719	659.00				
95.719	661.00				
96.719	663.00				
98.368	655.00				
99.500	655.00				
100.50	655.00	0.7			

CALCULATION OF AREAL EXTENT OF CAVITIES AND ESTIMATE OF GEOMETRY

ELW

Total coal consumed = 4,430 tons (corrected for gas loss)

Assume average extent of vertical coal consumption = 12 ft

$$\rho_c = 86.7 \text{ lb/ft}^3$$

$$\text{Volume consumed} = \frac{4,430 \text{ ton} (2,000 \text{ lb/ton})}{86.7 \text{ lb/ft}^3} = 102,919 \text{ ft}^3$$

$$\text{Areal extent} = \frac{102,919 \text{ ft}^3}{12 \text{ ft}} = 8,516 \text{ ft}^2$$

Maximum lateral extent with approximate distance between EPBC-1 and EPBC-2 approximately 170 ft:

$$\frac{8,516 \text{ ft}^2}{170 \text{ ft}} = 50 \text{ ft}$$

V1W-1 Coal consumed = 4,090 tons

$$\text{Areal extent} = \frac{4,090 \text{ ton}}{4,430 \text{ ton}} (8,516 \text{ ft}^2) = 7,862 \text{ ft}^2$$

V1W-2 Coal consumed = 325 tons

$$\text{Areal extent} = \frac{325 \text{ ton}}{4,430 \text{ ton}} (8,516 \text{ ft}^2) = 625 \text{ ft}^2$$

V1W-1 Information

V1W-2 TC fails on approximately days 42 and 51

Coal consumed to day 42 is 2,852 tons

Coal consumed to day 51 is 3,762 tons

Areal extent on day 42:

$$\frac{2,852 \text{ ton}}{4,430 \text{ ton}} (8,516 \text{ ft}^2) = 5,482 \text{ ft}^2$$

Distance between EPBC-1 and V1W-2 = 115 ft

$$\text{Lateral extent on day 42} = \frac{5,482 \text{ ft}^2}{115 \text{ ft}} = 48 \text{ ft}$$

$$\text{Areal extent on day 51} = \frac{3,762 \text{ ton}}{4,430 \text{ ton}} (8,516 \text{ ft}^2) = 7,232 \text{ ft}^2$$

$$\text{Lateral extent on day 51} = \frac{7,232 \text{ ft}^2}{115 \text{ ft}} = 62 \text{ ft}$$

CRIP

Total coal consumed = 11,277 tons corrected for gas loss)

Assume average extent of vertical coal consumption = 18 ft

$$\rho_c = 86.7 \text{ lb/ft}^3$$

$$\text{Volume consumed} = \frac{11,277 \text{ ton} (2,000 \text{ lb/ton})}{86.7 \text{ lb/ft}^3} = 260,138 \text{ ft}^3$$

$$\text{Areal extent} = \frac{260,138 \text{ ft}^3}{18 \text{ ft}} = 14,452 \text{ ft}^2$$

1st Injection

Coal consumed = 5,079 tons

$$\text{Areal extent} = \frac{5,079 \text{ ton}}{11,277 \text{ ton}} (14,452 \text{ ft}^2) = 6,509 \text{ ft}^2$$

Assume circular cavity growth, find radius:

$$r = (A/\pi)^{1/2} = (6,509/\pi)^{1/2} = 45 \text{ ft}$$

2nd Injection

Coal consumed = 2,780 tons

$$\text{Areal extent} = \frac{2,780 \text{ ton}}{11,277 \text{ ton}} (14,452 \text{ ft}^2) = 3,563 \text{ ft}^2$$

Assume rectangle length of CRIP maneuver

$$\text{Sweep width} = 3,563 \text{ ft}^2 / 60 \text{ ft} = 52.72 \text{ ft}$$

3rd Injection

Coal consumed = 2,501 tons

$$\text{Areal extent} = \frac{2,501 \text{ ton}}{11,277 \text{ ton}} (14,452 \text{ ft}^2) = 3,205 \text{ ft}^2$$

Assume rectangle length of CRIP maneuver plus auto-CRIP

$$\text{Sweep width} = 3,205 \text{ ft}^2 / (60 \text{ ft} + 30 \text{ ft}) = 35 \text{ ft}$$

4th Injection

Coal consumed = 856 tons

$$\text{Areal extent} = \frac{856 \text{ ton}}{11,277 \text{ ton}} (14,452 \text{ ft}^2) = 1,097 \text{ ft}^2$$

Assume rectangle length of CRIP maneuver minus auto-CRIP

$$\text{Sweep width} = 1,097 \text{ ft}^2 / (60 \text{ ft} - 30 \text{ ft}) = 36 \text{ ft}$$

Day 37 when TC-3 showed strong response:

Coal consumed = 2,323 tons

$$\text{Areal extent (A)} = \frac{2,323 \text{ ton}}{11,277 \text{ ton}} (14,452 \text{ ft}^2) = 2,977 \text{ ft}^2$$

Assume circular growth, find radius:

$$r = \sqrt{\frac{A}{\pi}} = \sqrt{\frac{2,977}{\pi}} = 30 \text{ ft}$$

Assume elliptical shape where $\alpha = 20$ ft distance from well line to TC-3 where α = shortest radius of ellipse and β = longest radius of ellipse

$$\text{Areal extent} = \alpha\beta\pi$$

$$\frac{2,977 \text{ ft}^2}{\pi \cdot 20} = 47.4 \approx 47 \text{ ft}$$

The end of the cavity is 2β or 94 ft from the injection point.

END

**DATE
FILMED**

6 / 3 / 92