EGG-WTD-9993
January 1992

Received by OSTI
APR 27 1992

**Idaho
National
Engineering
Laboratory**

*Managed
by the U.S.
Department
of Energy*

Energy & Costs Scoping Study for Plasma Pyrolysis Thermal Processing System

**K. E. Sherick
J. E. Findley**

*Work performed under
DOE Contract
No. DE-AC07-76ID01570*

This document contains new concepts or the author(s) interpretation of new calculations and/or measurements; accordingly, EG&G Idaho, Inc. is required by the United States Government to include the following disclaimer:

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights. References herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

EGG-WTD--9993

DE92 012359

Energy & Costs Scoping Study for Plasma Pyrolysis Thermal Processing System

**K. E. Sherick
J. E. Findley**

January 1992

**Idaho National Engineering Laboratory
EG&G Idaho, Inc.
Idaho Falls, Idaho 83415**

**Prepared for
Office of Environmental Restoration and Waste Management
U.S. Department of Energy
Under DOE Idaho Field Office
Contract DE-AC07-76ID01570**

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

**Energy & Costs Scoping Study
for Plasma Pyrolysis Thermal
Processing System**

Prepared by:

J. E. Findley

1/23/92

Date

Approved by:

G. L. Anderson

1/23/92

Date

D. E. Shropshire

1/23/92

Date

ABSTRACT

The purpose of this study was to provide information in support of an investigation of thermal technologies as possible treatment process for buried wastes at the INEL. Material and energy balances and a cost estimate were generated for a representative plasma torch-based thermal waste treatment system operating in a pyrolysis mode. Two waste streams were selected which are representative of INEL buried wastes, large in volume, and difficult to treat by other technologies. These streams were a solidified nitrate sludge waste stream and a waste/soil mix of other buried waste components. The treatment scheme selected includes a main plasma chamber operating under pyrolyzing conditions; a plasma afterburner to provide additional residence time at high temperature to ensure complete destruction of hazardous organics; an off-gas treatment system; and an incinerator and stack to oxidize carbon monoxide to carbon dioxide and vent the clean, oxidized gases to atmosphere. The material balances generated provide materials flow and equipment duty information of sufficient accuracy to generate initial rough-order-of-magnitude (ROM) system capital and operating cost estimates for a representative plasma thermal processing system.

EXECUTIVE SUMMARY

The purpose of this study was to provide information in support of an investigation of thermal systems technology as a possible treatment process for buried wastes at the Idaho National Engineering Laboratory (INEL). Material and energy balances and a cost estimate were generated for a representative plasma torch-based thermal waste treatment system operating in a pyrolysis mode. These balances provide materials flow and equipment duty information of sufficient accuracy to generate initial ROM system capital and operating cost estimates for a representative plasma thermal processing system.

Although this study was based upon system conditions expected to be achieved in a plasma torch-based waste treatment system operating in a pyrolysis mode, the overall mass flows, and calculated energy requirements are expected to be ROM representative of any full-scale plasma (electric furnace) pyrolysis waste treatment system for the typical waste streams chosen. The chemical reactions, mass flows, and energy balances are largely determined by the composition of the waste streams chosen, which in turn drives the system component types, sizes, and costs.

For a given waste stream and throughput, the factors that would have the most significant influence on capital and operating costs for a plasma-based system are: operation of the main plasma chamber under oxidizing versus pyrolyzing conditions; use of oxygen versus air to oxidize organics; and the extent to which waste heat is recovered. Operation of the main plasma chamber under oxidizing conditions increases the volume of off-gas, and thus the size of the off-gas treatment equipment, but reduces the power input to the plasma torch due to the heat provided by combustion of the organics. Use of oxygen versus air to oxidize organics will also reduce off-gas volume at the expense of the costs to generate oxygen. Waste heat recovery will reduce operating costs, if the waste energy can be used, at the expense of capital cost.

The thermal processing scheme selected for this study was chosen based on the results of ongoing and previous thermal plasma processing system technology studies and on input from current vendors of plasma torch-based thermal processing equipment. The scheme selected includes a main plasma chamber operating under pyrolyzing conditions, a plasma afterburner to provide additional residence time at high temperature to ensure complete destruction of hazardous organics, an off-gas treatment system, and an incinerator and stack to oxidize carbon monoxide to carbon dioxide and vent the clean, oxidized gases to the atmosphere. The off-gas treatment subsystem configuration used in this study was patterned after the off-gas treatment subsystem utilized for in situ vitrification process systems as designed by Pacific Northwest Laboratories (PNL). Technical and economic trade-off studies to optimize the process were not included as part of this study. Additional work would be needed to determine the influence of variations in system components and key performance assumptions.

Two waste streams were selected that are representative of INEL buried wastes, large in volume, and difficult to treat by other technologies. These streams were a solidified nitrate sludge

waste stream and a waste/soil mix of other buried waste components. The wastes throughput (flow rate) used was based on the largest commercial design capacity for a plasma pyrolysis-based system for processing municipal solid waste. This system has not been built or operated.

A combination of manual calculations and commercial process simulation codes was used to generate the material and energy balances. The calculational approach and methods used in this study are focused upon determination of bulk mass and energy balances and are not sufficiently rigorous to determine the distribution of trace species [e.g. transuranic (TRU)] throughout the process. Bulk vapor and liquid phase temperatures expected to exist in the main plasma chamber were key assumptions and are based upon typical values obtained from experienced system vendors. The distribution of species between the vapor and liquid phases in the main chamber was determined based on the vapor pressure of each species at the vapor phase conditions (assumed temperature). It was further assumed that there were no chemical reactions between liquid phase species, that there was no entrainment of liquid or solids into the vapor phase, and that the vapor phase species were in chemical equilibrium at the vapor phase conditions (assumed temperature). Appendix D provides further explanation.

Resulting material and energy balances for the two waste streams selected for this study are discussed further in Section 5 and included in Appendix A. The ROM total estimated cost for the plasma system selected is \$21.8 (December 1991 dollars). The bases and key assumptions for this cost estimate are discussed in detail in Appendix C.

The focus of this study was upon providing a first cut scoping estimate of energy requirements and costs for a single representative plasma thermal processing system. There are numerous system and component variations possible within this system and other systems technology-based thermal processing systems that deserve further study. The approach and methods used in this study may be used to prepare material and energy balances and cost estimates for other thermal treatment systems and for other waste streams. Further studies of this type are required for comparing ROM capital costs, utility requirements, and operating costs of other likely thermal processing systems.

ACKNOWLEDGEMENTS

This report was prepared for the Waste Technology Development Department of EG&G Idaho, Inc., under contract to the U.S. Department of Energy Idaho Field Office, Office of Technology Development. Funding was provided under FY-91 Thermal Processing Technologies Technical Task Plans ID-0502-DT, 1991, and ID-040E-2D, 1992.

CONTENTS

ABSTRACT	iii
EXECUTIVE SUMMARY	v
ACKNOWLEDGEMENTS	vii
ACRONYMS	xi
1. INTRODUCTION	1
2. PLASMA TECHNOLOGY DESCRIPTION	3
3. FEED STREAMS	4
3.1 Stream Compositions	10
3.1.1 Series 743 Sludge	10
3.1.2 Estimate of Remaining Waste	10
4. PROCESS CONFIGURATION	14
4.1 Main Plasma Chamber	14
4.1.1 Inputs to the Reactor	14
4.1.2 Outputs	21
4.2 Plasma Afterburner	21
4.3 Off-gas System	22
4.3.1 Heat Recovery Boiler	22
4.3.2 Cooler	22
4.3.3 Wet Scrubber System	22
4.3.4 Condenser	23
4.3.5 Reheater and HEPA Filter Assembly	23
4.3.6 Blower	23
4.4 Incinerator	23
5. MASS AND ENERGY BALANCES	25
6. COST ESTIMATE	28
7. RESULTS SUMMARY	30
8. RECOMMENDATIONS	31

9. REFERENCES	32
APPENDIX A--MASS BALANCE TABLES	A-1
APPENDIX B--SUMMARY OF ENERGY BALANCE CALCULATIONS	B-1
APPENDIX C--COST ESTIMATE	C-1
APPENDIX D--DISCUSSION OF CALCULATION METHODS	D-1

FIGURES

1. Process Flow Diagram	15
2. Plasma Refuse Converter from Plasma Energy Corporation	17

TABLES

1. Estimated amounts of buried waste contributed by various sources	5
2. Compositional breakdown of Stream 1	11
3. Compositional breakdown of Stream 2	12
4. Compositional feed rates of Stream 1 into Plasma Reactor	18
5. Compositional Feed Rates of Stream 2 into Plasma Reactor	19
6. Mass and energy summary for treatment of Stream 1 (Sludges)	26
7. Mass and energy summary for treatment of Stream 2	26

ACRONYMS

ANL	Argonne National Laboratory
ARA	Auxillary Reactor Area
CFA	Central Facilities Area
DC	direct current
GCRE	gas-cooled reactor experiment
HEPA	high efficiency particulate air (filter)
ICPP	Idaho Chemical Processing Plant
INEL	Idaho National Engineering Laboratory
kgmoles/hr	kilogram-moles per hour
MW	megawatt
NASA	National Aeronautics and Space Administration
NEPA	National Environmental Policy Act
NRF	Naval Reactor Facility
OMRE	organic-moderated reactor experiment
PEC	Plasma Energy Corporation
PNL	Pacific Northwest Laboratory
PRC	plasma refuse converter
psi	pounds per square inch
psig	pounds per square inch (gauge)
RFP	Rocky Flats Plant
ROM	rough-order-of-magnitude
RWMC	Radioactive Waste Management Complex
SDA	Subsurface Disposal Area
SPERT	Special Power Excursion Reactor Test

TAN	Test Area North
TRA	Test Reactor Area
TRU	transuranic
WERF	Waste Experimental Reduction Facility
WIPP	Waste Isolation Pilot Plant

Energy & Costs Scoping Study for Plasma Pyrolysis Thermal Processing System

1. INTRODUCTION

The main purpose of this study was to provide information in support of an investigation of thermal processing systems technology as a possible treatment process for buried waste at the INEL. In particular, the scope of this project was to provide a ROM estimate of the energy requirements and costs for a representative plasma torch-based waste processing system. The estimate was to be based upon the results of the following tasks:

- Choose two appropriate waste streams for plasma processing. The streams should be representative of INEL buried waste, large in volume, difficult to treat by other technologies, and identified as hazardous and radioactive.
- Based upon review of ongoing and previous studies of thermal treatment technologies and input from appropriate commercial technology suppliers, select a plasma waste treatment scheme.
- Calculate material and energy balances for the selected plasma system, generate a conceptual process flow diagram, and prepare a scoping cost estimate.

The waste streams were chosen from the Plasma Candidate Waste Stream Survey.¹ Other hazardous constituents were added to obtain more representative data for mass and energy balances.⁸ The main plasma chamber and the plasma afterburner systems evaluated in this study are based on a 125 ton/day Plasma Refuse Converter design by Plasma Energy Corporation (PEC) and a plasma afterburner design by Scorpion Manufacturing respectively. These designs were chosen based upon each company's research and testing experience in plasma processes.

The off-gas system chosen for this study is similar to Pacific Northwest Laboratory's off-gas system utilized for in situ vitrification processing tests. It is an established system that can handle radionuclides, particulates, and acid gases. To minimize the size and cost of the off-gas system, it was assumed in this study that the final exhaust gases will be incinerated downstream of the off-gas system as necessary. The purpose of the final incineration step is to oxidize carbon monoxide to carbon dioxide. The stack gas effluent will consist of simple, nonhazardous molecules such as carbon dioxide,

nitrogen, and water. These gases will then be vented to the atmosphere. A crystalline slag is produced by the plasma furnace which upon cooling immobilizes radionuclides, heavy metals, and other inorganics into a essentially nonleachable ceramic form suitable for long-term storage or final disposal.

2. PLASMA TECHNOLOGY DESCRIPTION

Thermal plasma processing utilizes a plasma torch or arc to treat solid and liquid waste at very high temperatures to destroy the toxic organic materials and to stabilize the inorganics by forming a vitrified ceramic product that is essentially nonleachable. Thermal plasma processing technology is a promising technique for processing hazardous and mixed wastes and is being evaluated as a potential treatment process for INEL buried waste. It is anticipated that plasma torch or arc processing can successfully treat hazardous, low-level, transuranic, and mixed waste to meet final disposal requirements. The technology is considered excellent for radioactive alpha contamination control during processing, because of the potential for having a sealed reaction vessel.

A plasma is created when gas is ionized by heating it with a high-power dc electric arc strong enough to strip electrons from the gas molecules. When hazardous wastes are directly subjected to the high levels of energy delivered by the plasma, the molecular structure of the waste components are broken down into their atomic constituents. Only a small amount of gas is required to create this high-temperature plasma resulting in a smaller off-gas system compared to conventional incineration. When plasma is used to heat inert materials, such as soil to form a molten bath, a very uniform, high-temperature environment can be created. The temperature of the bath is high enough to ensure thermal destruction of the organic wastes even though the temperatures of the molten bath are far below the actual plasma temperatures. Heavy metal contaminants are dissolved in the molten slag/bath. Upon cooling, an essentially nonleachable solid results which requires no further treatment. If enough energy is supplied through the plasma torch, the process should be able to treat waste with any physical characteristic, including unopened waste-filled drums.² The resultant slag characteristics are currently being studied by several companies, one of which is MSE, Inc. in Butte, Montana, who is involved in the Plasma Arc Furnace Experiment (the Plasma Centrifugal Reactor configuration by Retech).

3. FEED STREAMS

The main criteria for selecting the candidate waste feed streams for this study was that the streams reflect the actual waste that may be treated by thermal plasma processing at the INEL. This could have been accomplished by selecting a "best" and "worst" case stream, or by selection of representative streams. However, bracketing the study with a best and worst case stream would have required the development of a set of criteria and a rigorous application of these criteria. Due to time limitations and limited information on actual waste characteristics, it was decided that representative streams would be more appropriate for this scoping study.

The initial step in the selection process was to concentrate efforts on only one of the four broad categories of waste found at the INEL. The four broad categories considered were stored waste, buried waste, mixed waste, and waste currently generated. Stored waste comprises a large volume of the waste at the INEL and is relatively well characterized. However, stored waste is scheduled for shipment to the Waste Isolation Pilot Plant (WIPP) and the need for processing the stored waste is not urgent. The mixed waste is a serious concern for regulatory reasons, but the small quantities of mixed waste currently at the Radioactive Mixed Waste Storage Facility (RMWSF) will not likely justify the design of a new process. Waste currently being generated amounts to relatively small quantities and much of it is treated at the Waste Experimental Reduction Facility (WERF). The buried waste is not well characterized and there are extremely large quantities of buried waste. Furthermore, there is a great deal of public concern about migration of radioactive and hazardous constituents from buried waste sites. For these reasons, it was decided that the representative waste streams would come from the buried waste.

Table 1 is a summary of buried waste streams contributed by various sources.¹ The first step in the selection process was to eliminate any streams with $< 1000 \text{ m}^3$ of waste. This is a somewhat arbitrary criteria, but the idea was to concentrate on the larger volume streams. The next step in the selection process was to eliminate any of the streams that did not have adequate available descriptions, or would not be considered hazardous waste. The remaining streams consisted primarily of the Rocky Flats Plant (RFP) sludges (excluding Series 744 Sludge) and various general waste streams ("general" means that the streams contained a variety of waste forms).

It was decided that a sludge would be a good candidate for treatment for several reasons. Most conventional technologies would only be marginally effective when applied to the cemented or solidified sludges. Furthermore, the 74X series sludges constitute a large portion of the RFP buried waste. It was decided to concentrate efforts on the Series 743 sludge since it has been characterized more extensively than some of the other sludges and has the highest percentage of hazardous organics.

Table 1. Estimated amounts of buried waste contributed by various sources.¹

Company/Laboratory	Description	Volume (m ³)
Rocky Flats Plant		
Series 741 sludge	First Stage Sludge: Obtained from treating aqueous process waste; precipitate of hydrated oxides of iron, magnesium, aluminum, silicon, plutonium, and americium is filtered to produce sludge that is 50-70% water by weight.	1983.87
Series 742 sludge	Second Stage Sludge: produced from the treatment of all other plant radioactive and/or chemical contaminated wastes and further treatment of 741 Sludge; may also contain mercury and lithium batteries and small amounts of contaminated mercury in pint bottles; filtered to produce a sludge 50-70% water by weight.	3280.33
Series 743 sludge	Organic Set-Ups: produced from treatment of liquid organic wastes; organic wastes were mixed with calcium silicate to form a paste-like material; consists mainly of trichloroethane, Texaco Regal Oil, and carbon tetrachloride, hydraulic oils; other organics include trichloroethylene, tetrachloroethylene, gearbox and spindle oils; also some unknown volume of oils containing PCB's.	2014.95
Series 744 sludge	Special Set-Ups: Resulted from processing liquid waste not compatible with the 741 and 742 processes because of their plutonium complexing nature; Includes alcohols, organic acids, EDTA. Solidified with Portland cement	338.78
Series 745 sludge	Evaporation Salts: originated from evaporation of liquid waste impounded in solar evaporation ponds; estimated to contain 60% sodium nitrate, 30% potassium nitrate, and 10% miscellaneous material.	1831.32

Table 1. (continued).

Company/Laboratory	Description	Volume (m ³)
Cemented liquids from 741 and 742 series		108.27
Trash drums		196.55
Empty bottles in drums from 744 series processing		92.65
74R	Effluent from 741 and 742 treatment process. 6N HNO ₃ neutralized with NaOH and mixed with Portland cement.	74.58
Empty oil drums		1238.99
Heavy oils/w calcium silicate		0.42
Fire waste	Gloveboxes, presses, lathes, furnaces, rolling mills, filters, piping, masonry brick ducting, and some structural components.	3413.94
Nitrate salts (a)		450.00
Estimate of remaining waste (b)	Gloveboxes, tanks of raschig rings, press, lathes, contaminated rags, ion exchange resins, copper molds, magnesium oxide crucibles, tantalum crucibles, and graphite molds.	38703.33
Rocky Flats Plant Estimated Total:		53724.98
INEL (c)		
NRF		12517.70 (442000 ft ³)
TRA		8779.38 (310000 ft ³)
ICPP		4672.90 (165000 ft ³)
TAN		3979.04 (140500 ft ³)
ANL		2378.93 (84000 ft ³)

Table 1. (continued).

Company/Laboratory	Description	Volume (m ³)
CFA		1146.98 (40500 ft ³)
OMRE		688.19 (24300 ft ³)
GCRE		688.19 (24300 ft ³)
SPERT		152.93 (5400 ft ³)
ARA		144.44 (5100 ft ³)
	INEL Estimated Total:	35148.68
Lawrence Radiation Laboratory	Contaminated paper and clothing; glassware, plastic, and laboratory equipment; solidified liquid waste; activated metals; gloveboxes; scintillation fluids in vials; HEPA filters; and animal carcasses. Some lithium compounds and beryllium oxide also included. Concrete used to solidify the waste.	2241.48
Rockwell International Atomic International Division	Sodium and sodium-potassium metal; small amounts of mercury; tritium contaminated glassware; samples of uranium and zirconium fuel; small quantities of terphenyls and diphenyls; beryllium; scrap metal; HEPA filters; fume hoods and ducting	1392.30
Nuclear Regulatory Commission (Formerly the Atomic Energy Commission)	Mainly dry waste solidified in concrete. A more detailed description is unavailable.	791.42
General Atomic Company	Paper, shoe covers, rubber gloves, lab coats, clothing and glassware, cemented liquids, scrap metal, piping, wood, glass, and HEPA filters; beryllium, uranium-zircaloy, hydride turnings, fines	714.82
Nuclear Engineering Co., Inc.		163.90

Table 1. (continued).

Company/Laboratory	Description	Volume (m ³)
Department of Health, Education, and Welfare		94.96
San Antonio Air Logistics Center		83.92
ICN (Formerly U.S. Nuclear Corporation)		79.96
PM-1 Nuclear Power Plant		47.15
IT Corporation (Formerly California Salvage Co.)		28.52
U.S. Army Chemical Center		25.88
University of Utah		20.11
U.S. Bureau of Mines		15.85
Babcock-Wilcox		15.63
U.S. Marine Corps		13.42
University of Washington		12.97
American Electronics, Inc.		10.42
U.S. Naval Radiation Defense Lab.		8.04
Oregon Metallurgical Corp.		7.33
Teledyne Wah Chang Corporation		4.53
University of California Lab. of Nuclear Medicine Rad. Biology		4.11
Thiokol Chemical Corporation		2.12
Washington State University		1.67
U.S. Army Chemical Center		1.05

Table 1. (continued).

Company/Laboratory	Description	Volume (m ³)
Colorado School of Mines Research Institute		0.42
U.S. Bureau of Mines		0.42
Chicago Bridge and Iron, Co. (Formerly Industrial X-Ray Engineers)		0.26
Memorial Hospital of Sheridan County		0.14
	Estimated Total of Other Generators:	5782.80
	Estimated Total Buried Waste:	94656.46

- a. Original information provided in kilograms. The value provided in cubic meters is an estimate.
- b. This is an estimated value for remaining volume not accounted for. It was based on stored Rocky Flats waste.
- c. The table that presented this information was stated as being in cubic meters. Those values are the ones in parentheses. These values were excessively high. If the data is actually cubic feet, they are approximately correct.

The other stream that was selected was the stream referred to as "Estimate of Remaining Waste." This stream contains essentially all of the RFP waste outside of sludges and fire waste. The mixture of metals, glass, plastics, cloth, paper, soil, and other miscellaneous items would present serious problems for most conventional processes unless extensive sorting was done prior to the processing. The selection of this stream was based on its large volume and representative nature.

3.1 Stream Compositions

The percentages of the various components in each stream were based primarily on work presented in previous Engineering Design Files (EDFs). In addition, certain components were added to each stream to ensure that the remaining waste streams were enveloped. The molecular composition of each of the individual components was obtained from a variety of sources.⁸⁻¹³

3.1.1 Series 743 Sludge

Table 2 lists the composition of the 743 Series Sludge. The basic volume percentages were obtained from an internal EG&G Idaho Engineering Design File.⁴ In addition, this volume was supplemented with small amounts of mercury, lithium, plutonium, and americium.

3.1.2 Estimate of Remaining Waste

Stream 2 is based loosely on the description given in Table 1 and the descriptions listed in *Content Code Assessment for INEL Contact-Handled Stored Transuranic Wastes*.⁸ In addition, soil, concrete, high-efficiency particulate air (HEPA) filters, plastics, lithium, and mercury have been added to represent the waste more completely. The volume percentages for the components were based on a report by James O. Low.⁵ Table 3 presents the composition of Stream 2. Fractions for waste types were determined based on 1971-1973 waste content code inventories developed from RFP were representative of the TRU waste buried at the Subsurface Disposal Area (SDA).

Table 2. Compositional breakdown of Stream 1.

Stream 1: Sludges (743)									
Component	Composition	Formula	Mol. wt (Mw)	Volume (gal) (V)	Density (g/cm ³) (D)	Mass (kg) (M=V*D)	Weight % (M/Tot M*100)	Kg-moles (kmol) (M/MW)	Mole % (X,*100)
Sludge 743	Texaco Regal Oil	C20H41	282.0	43400	0.9	1.48E+05	2.488	524.3	1.648
	CC14	CC14	153.8	27100	1.594	1.64E+05	2.752	1063.2	3.342
	1,1,1-trichloroethane	C2H3Cl3	133.4	5580	1.339	2.83E+04	0.476	212.1	0.667
	trichloroethylene	C2HCl3	131.3	4180	1.4642	2.32E+04	0.390	176.5	0.555
	perchloroethylene	C2Cl4	165.8	4180	1.6227	2.57E+04	0.432	154.9	0.487
	Used oil	C20H42	282.0	13900	0.9	4.74E+04	0.797	167.9	0.528
	PCB	C12H5Cl5	326.3	0.53	1.15	2.31E+00	0.000	0.0	0.000
	Inert (calcium silicate)	Ca2SiO4	172.2	130200	3.2	1.58E+06	26.543	9156.8	28.783
		Ca3SiO5	228.3	303800	3.2	3.68E+06	61.935	16119.4	50.669
	Mercury	Hg	200.6	540	13.534	2.77E+04	0.466	137.9	0.434
	Lithium	Li	6.9	540	0.534	1.09E+03	0.018	157.3	0.494
	Plutonium	Pu	244.0	0.03	19.84	2.90E+00	0.000	0.0	0.000
	Americium	Am	243.0	0.002	13.67	9.68E-02	0.000	0.0	0.000
	55 gal drum	Fe	55.8	7394.07	7.86	2.20E+05	3.703	3942.7	12.393
					Total:	5.94E+06	100.000	31812.9	100.000

Table 3. Compositional breakdown of Stream 2.

Category	Component	Composition	Molecular weight	Volume fraction category	Volume fraction total	Volume (ft ³)	Weight (kg)	Weight %	Kg-moles (kmole)	Mole %
Combustibles:	Paper/wood	C6H10O5 (84.81%) H2O (19 wt%)	Total:	0.5000	0.33000	454,497.615	5,607,844	26.976	29,358.1	7.7238
			162.0				4,756,012		46,732.0	12.2947
			18.0				841,177		41.6	0.0109
			256.0				10,655			
	Rags/clothing	C6H10O5 (85 wt%) H2O (15 wt%)	162.0	0.3000	0.19800	272,698.569	3,364,706	16.185	17,654.3	4.6447
			18.0				2,860,000		28,039.2	7.3768
							504,706			
		C7H14O7 (85 wt%) H2O (15 wt%)	210.0	0.2000	0.13200	181,799.046	2,243,137	10.790	9,079.4	2.3887
			18.0				1,916,667		18,692.8	4.9179
							336,471			
Metals: (gloveboxes, lathes, press, molds, and other scrap)	Carbon steel	Fe	55.8	1.0000	0.08000	110,181.240	2,039,216	9.809	36,545.1	9.6146
Soil, concrete:	Soil	SiO2 (65 wt%) Al2O3 (13%) Fe2O3 (5%) CaO (4%) K2O (3%) MgO (2%) H2O (8%)	Total:	0.5000	0.04500	61,976.948	1,529,412	7.357	16,546.6	4.3332
			60.1				994,118		1,951.2	0.5133
			101.9				198,824		479.1	0.1261
			159.6				76,471		1,090.5	0.2869
			56.1				61,176		487.1	0.1281
			94.2				45,880		759.0	0.1997
			40.3				30,588		4,797.4	1.7883
			18.0				122,353			
	Concrete	SiO2 (80 wt%) CaO (20%)	Total:	0.5000	0.04500	61,976.948	1,529,412	7.357	20,365.0	5.3378
			60.1				1,223,529		5,452.4	1.4345
			56.1				305,882			
Glass & raschig rings & filters & insulation:	Glass/rings/ Filters/ insulation	SiO2 (80 wt%) B2O3 (13 wt%) Na2O (4 wt%) Al2O3 (3 wt%)	Total:	0.9900	0.06930	95,444.499	1,265,971	6.090	16,857.1	4.4349
			60.1				1,012,777		2,364.6	0.6221
			69.6				164,576		814.8	0.2149
			62.0				50,639		372.7	0.0981
			101.9				37,979			
Crucibles		Al2O3SiO2 (50%) MgSiO3 (50 wt%)	Total:	0.0100	0.00070	964.086	20,341	0.098	62.8	0.0165
			162.0				10,171		101.3	0.0267
			100.4				10,171			

Table 3. (continued).

Category	Component	Composition	Molecular weight	Volume fraction category	Volume fraction total	Volume (ft ³)	Weight (kg)	Weight %	Kg-moles (kmole)	Mole %
Miscellaneous:	Plastics	(C ₂ H ₄) _x	28.0	0.3333	0.03333	45,904.259	1,324,165	6.370	47,291.6	12.4419
	Resins	(C ₈ H ₈) _x	104.0	0.3333	0.03333	45,904.259	1,123,277	5.403	10,800.7	2.8416
	Li	Li	6.9	0.0001	0.00001	13.773	208	0.001	30.2	0.0079
	Hg	Hg	200.6	0.0001	0.00001	13.773	5,268	0.025	26.3	0.0069
	Graphite	C	12.0	0.3333	0.03333	45,904.259	735,647	3.539	61,303.9	16.1284
Totals:					1.0000	1,377,279.273	20,788,603	100.000	280,098.8	100.0000

4. PROCESS CONFIGURATION

The basic configuration of the plasma pyrolysis system chosen consists of a main plasma chamber and a plasma afterburner followed by an off-gas treatment system. This project did not include optimization or trade-off studies for the system configuration.

The Plasma Pyrolysis Process Flow Diagram is shown in Figure 1. Stream numbers shown on the Process Flow Diagram correspond with those given in the mass and energy balance table in Appendix A.

4.1 Main Plasma Chamber

The main plasma chamber was patterned after the 125 ton/day Plasma Refuse Converter (PRC) design by PEC. PEC has conducted plasma waste conversion tests at the rate of 1 ton/hour, converting municipal solid waste into a fuel-rich gas and a vitrified inert solid. The results of these tests were used to design a 250 ton/day module called the Plasma Refuse Converter (Figure 2). The PRC consists of two 5 MW pyrolysis reactors each feeding 125 tons/day. Pyrolysis is the thermal decomposition of carbonaceous material in the absence of oxygen. After pyrolysis and vitrification, the volume reduction of the waste will be significant.^a

4.1.1 Inputs to the Reactor

Hazardous waste can be accepted in drum form to the main plasma reactor by a common walking floor mechanism. The walking floor permits the controlled handling of mixed waste. The feed is assumed to be comprised of the compositions given in Tables 4 and 5.

Air is used as the plasma gas for the PRC reactor and was assumed to be the plasma gas for this study. The plasma torch will require 150 scfm of air at 60-100 psig. It is important to note that the type of plasma gas used will have an impact on the amounts and types of products generated. Any gaseous medium is acceptable for use i.e., argon, helium, hydrogen, nitrogen, or, if appropriate, oxygen, carbon dioxide, water, etc.⁶ Trade-off and experimental studies would be beneficial in determining the best plasma gas for a particular system.

The plasma torch system will be equipped with a closed-loop cooling water system. Cooling water demand will be about 100 gallons/minute at a pressure of approximately 200 psig.

a. Personal correspondence (letter), Dr. Bud Camacho, Plasma Energy Corporation, Raleigh, North Carolina, November 1990.

Figure 1. Process Flow Diagram..

QTY. REQ'D	QVAL. LEVEL	PART OR IDENTIFYING NO.	DESCRIPTION/MATERIAL/SPECIFICATION	ITEM/ FIND
PARTS LIST				
DIMENSIONING AND SYMBOLS ARE AMERICAN NATIONAL STANDARD UNLESS OTHERWISE SPECIFIED SURFACE FINISHES DIMENSIONS AND TOLERANCES ARE IN INCHES TOLERANCES: J = ±.1 K = ±.01 L = ±.001 M = ±.0005 N = ±.0002 P = ±.0001 Q = ±.00005 R = ±.00002 S = ±.00001 T = ±.000005 U = ±.000002 V = ±.000001 W = ±.0000005 X = ±.0000002 Y = ±.0000001 Z = ±.00000005 DO NOT SCALE DRAWING			NEXT ASSISTANT CHIEF PROJECT NO. DATE DESIGN DATE CHECKED DATE DRAWN DATE RELEASE DATE	
EG&G Idaho, Inc. PLASMA PYROLYSIS PROCESS FLOW DIAGRAM			436942 SHEET 1 OF 1 TBA

Figure 2. Plasma Refuse Converter from Plasma Energy Corporation.

Table 4. Compositional feed rates of Stream 1 into Plasma Reactor.

Stream 1: Sludges (743)									
Component	Composition	Formula	Mol. wt.	Waste feed 125 tons/day basis (kg/hr)	Waste feed 125 tons/day basis (kg-mol/hr)	Plasma gas @ 150 scfm (kg-mol/hr)	Steam @ mole/mole C (kg-mol/hr)	Slag/ Molten metal (kg-mol/hr)	Offgas (nonequiv.) (kg-mol/hr)
Sludge 743	Texaco Regal Oil	C ₂₀ H ₄₂	282.0	117.587	0.417				0.417
	CCl ₄	CCl ₄	153.8	130.042	0.846				0.846
	1,1,1-trichloroethane	C ₂ H ₃ Cl ₃	133.4	22.493	0.169				0.169
	trichloroethylene	C ₂ HCl ₃	131.3	18.425	0.140				0.140
	perchloroethylene	C ₂ Cl ₄	165.8	20.419	0.123				0.123
	Used oil	C ₂₀ H ₄₂	282.0	37.660	0.134				0.134
	PCB	C ₁₂ H ₅ Cl ₅	326.3	0.002	0.000				0.000
	Inert (calcium silicate)	Ca ₂ SiO ₄	172.2	1254.257	7.282			7.282	
		Ca ₃ SiO ₅	228.3	2926.599	12.819			12.819	
	Mercury	Hg	200.6	22.001	0.110				0.110
	Lithium	Li	6.9	0.868	0.125				0.125
	Plutonium	Pu	244.0	0.002	0.000			0.000	
	Americium	Am	243.0	0.000	0.000			0.000	
	55 gal drum	Fe	55.8	174.957	3.135			3.135	
	Nitrogen	N ₂	28.013			8.498			8.498
	Oxygen	O ₂	31.999			2.259			2.259
	Steam	H ₂ O	18.015				12.720		12.720
				4725.312	25.300	10.757	12.720	23.237	25.540

Table 5. Compositional Feed Rates of Stream 2 into Plasma Reactor.

Category	Component	Composition	Molecular weight	Weight (kg)	Waste feed 125 tons/day basis (kg/hr)	Waste feed 125 tons/day basis (kg-mol/hr)	Plasma gas @150 scfm (kg-mol/hr)	Steam @ mole/mole C (kg-mol/hr)	Slag molten metal (kg-mol/hr)	Offgas (nonequil.) (kg-mol/hr)
Combustibles:	Paper/wood	Total:		5,607,844	1080.977	6.673				6.673
		C6H10o5 (84.81%)	162.0	4,756,012	191.188	10.622				10.622
		H ₂ O (.19 wt%)	18.0	841,177	2.422	0.009				0.009
	Rags/clothing	Total:		3,364,706	650.039	4.013				4.013
		C6H10O5 (85 wt%)	162.0	2,860,000	114.743	6.373				6.373
Metals: (gloveboxes, lathes, press, molds, and other scrap)	Carbon steel	H ₂ O (15 wt%)	18.0	504,706	433.360	2.064				2.064
		C7H14O7 (85 wt%)	210.0	1,906,667	76.45	4.249				4.249
		H ₂ O (15 wt%)	18.0	336,471						
	Fe	Total:		2,039,216	463.486	8.306			8.306	
			55.8							
Soil, concrete:	Soil	SiO ₂ (65 wt%)	60.1	1,539,412	225.950	3.761			3.761	
		Al ₂ O ₃ (13%)	101.9	994,118	45.190	0.443			0.443	
		Fe ₂ O ₃ (5%)	159.6	76,471	17.381	0.109			0.109	
	Concrete	CaO (4%)	56.1	61,176	13.905	0.248			0.248	
		K ₂ O (3%)	94.2	45,882	10.428	0.111			0.111	
Glass & Raschig Rings & filters & insulation:	Concrete	MgO (2%)	40.3	30,588	6.952	0.173			0.173	
		H ₂ O (8%)	18.0	122,353	27.809	1.545			1.545	
		Total:		1,529,412	278.092	4.629			4.629	
	Glass/rings/filters/insulation	SiO ₂ (80 wt%)	60.1	1,223,529	69.523	1.239			1.239	
		CaO (20%)	56.1	305,882						
Glass & Raschig Rings & filters & insulation:	Glass/rings/filters/insulation	Total:		1,265,971	230.190	3.831			3.831	
		SiO ₂ (80 wt%)	60.1	1,012,777	37.406	0.537			0.537	
		B ₂ O ₃ (13 wt%)	69.6	164,576	11.510	0.186			0.186	
	Soil	Na ₂ O (4 wt%)	62.0	50,639	8.632	0.085			0.085	
		Al ₂ O ₃ (3 wt%)	101.9	37,979						

Table 5. (continued).

Category	Component	Composition	Molecular weight	Weight (kg)	Waste feed		Waste feed 125 tons/day basis (kg-mol/hr)	Plasma gas @150 scfm (kg-mol/hr)	Steam @ mole/mole C (kg-mol/hr)	Slag molten metal (kg-mol/hr)	Offgas (nonequil.) (kg-mol/hr)
					125 tons/day basis (kg/hr)	125 tons/day basis (kg-mol/hr)					
Miscellaneous:	Crucibles		Total:	20,341							
		Al ₂ O ₃ SiO ₂ (50%)	162.0	10,171	2,312	0.014				0.014	
		MgSiO ₃ (50 st%)	100.4	10,171	2,312	0.023				0.023	
	Plastics Resins	(C ₂ H ₄) _x	28.0	1,324,165	300,956	10.749	10.749				10.749
		(C ₈ H ₈) _x	104.0	1,123,277	255,306	2.455	2.455				2.455
		Li	6.9	208	0.047	0.007	0.007				0.007
		Hg	200.6	5,268	1.197	0.006	0.006				0.006
		C	12.0	735,647	167,302	13.934	13.934			13.934	
	Nitrogen Oxygen Steam	N ₂	28.013					6.498			6.498
		O ₂	31.999					2.259			2.259
		H ₂ O	18.015						119.693		119.693
	Totals:				20,788,603	4724,969	86,934	10,757	110,693	37,628	179,213

To minimize soot formation, one mole of 250 psi steam/mole of carbon is injected into the reactor. Under pyrolyzing conditions, steam will react with soot (carbon) to form carbon monoxide and hydrogen.

The component weight percents, presented in Tables 2 and 3, were used to define the composition of the feed stream entering the plasma reactor at a rate of 125 tons/day. This rate was chosen based on the capacity of the Plasma Energy Corporation PRC design. Tables 4 and 5 give the compositional breakdown in kgmoles/hr for streams 1 and 2, respectively.

4.1.2 Outputs

The temperature of pyrolysis, the heating rate, and the composition of the carbonaceous feed material taken together determine the make-up of the byproducts of the pyrolysis process.⁶ The relative amounts of byproducts from the process are highly dependent upon the feed composition. The organic material in the feed will be volatilized and broken down into atomic constituents and reformed into simple byproducts such as carbon monoxide, hydrogen, hydrochloric acid, nitrogen, etc. The temperature of the off-gas leaving the plasma reactor is assumed to be 1000°C. The inorganic material will form a molten material (slag). The temperature of the molten bath is assumed to be 2000°C. It is further assumed that sufficient residence time is provided to ensure essentially complete thermal destruction of the organics. After exiting the furnace, the molten material is allowed to cool forming a crystalline, nonleachable slag.

In past studies exploring thermal melting operations for decontamination of TRU contaminated bulk metals, it was observed that the molten steel and slag form two distinct layers. The TRU contaminants are expected to be in an oxide form that will be dissolved into the slag. Any low melting temperature metals will melt and collect above or below the slag (depending upon density) and possibly allow for the bulk metal to be drawn off, separated, and reclassified as low level waste. The radioactive and hazardous heavy metals are also expected to remain dissolved within the slag. The resulting vitrified or ceramic product will retain these compounds following cooling such that the Environmental Protection Agency (EPA) Toxicity Characteristic tests for heavy metal leachability will consistently be met.⁷ Material process applications testing is needed to verify this expectation.

4.2 Plasma Afterburner

The main purpose of the afterburner is to ensure essentially complete decomposition of any hazardous organics that (not all organics escape) may have escaped from the main plasma pyrolysis reactor to achieve the required destruction and removal efficiencies. A plasma-type afterburner was chosen to be consistent with the goal of this study to evaluate plasma systems. A conventional combustion afterburner could also be used. The plasma torch in this scheme would use the influent

gas to strike an arc and therefore no additional plasma gas is needed. The opinion of PEC is that an afterburner is not needed. Further studies are required to verify this and to determine the optimum process scheme.

4.3 Off-gas System

The main purpose of the off-gas system is to cool, scrub, and filter the effluent gas from the plasma systems. The off-gas system configuration is similar to an off-gas system design by PNL. The PNL off-gas system is an established system which can handle radionuclides, particulates, and acid gases. The major components of the off-gas system include: a boiler, a gas cooler, a quench tower and tandem nozzle scrubber, two scrubber solution tanks, a condenser, a reheater, mist eliminators (vane separators), HEPA filter assemblies, and a blower. The off-gas system contains a sophisticated control system with critical and informational sensors located throughout the process to ensure safe operation. These include thermocouples, flowmeters, pressure elements, gas monitors, back-up equipment, etc.

4.3.1 Heat Recovery Boiler

The gas exiting the afterburner will be cooled to approximately 750°F in the heat recovery boiler by generating 250 psi steam. The main purpose of the boiler is to cool the gas stream and to recover waste heat by producing steam to be used in the process. Steam is injected into the main plasma chamber and used in the reheater downstream in the off-gas system. Because more steam is produced than is needed, the excess steam could potentially be used to evaporate water from the sludge generated in the off-gas system (reducing volume), or used in other energy recovery applications such as power generation.

4.3.2 Cooler

The gas cooler is a finned air-to-glycol heat exchanger and used to further cool the off-gases before they enter the quench tower.

4.3.3 Wet Scrubber System

The wet scrubber system consists of a quench tower, a tandem nozzle scrubber, and a vane separator. In the quench tower, the gas is contacted with the circulating scrubbing solution to reduce the temperature to approximately 150 °F by evaporation of water from the solution and to remove approximately 90% of any particulates and semivolatile radionuclides from the gas. The tandem nozzle scrubber is designed to remove an additional 90% of any remaining particulates that are greater than 0.5 μ in diameter. In addition, it provides further cooling of the gas and condenses the

remaining semivolatile components. Vane separator-type mist eliminators are used to remove all droplets greater than about 12 μ in diameter.

Scrubber solution is circulated to the quench tower and tandem nozzle scrubber. The solution from the quench tower and scrubber is cooled through two single-stage heat exchangers before being returned to the process. Fresh caustic solution is made-up to the circulating solution to neutralize any acids in the off-gas. Sludge is collected and concentrated by gravity settling in the sludge concentration tank and sent to the waste neutralization tank. Excess steam generated from the plasma pyrolysis process could be used to reduce the sludge volume by evaporation.

4.3.4 Condenser

Following the wet scrubber system, the gas flows through a condenser. The condenser provides additional decontamination of the off-gas by condensing and removing water. The second vane separator removes droplets ≥ 12 microns.

4.3.5 Reheater and HEPA Filter Assembly

After exiting the condenser, the gas is reheated using steam generated by the heat recovery boiler. This slightly superheats the gas to ensure that there is no entrained mist to clog the HEPA filters. The first stage of filtration consists of two HEPA filters in parallel. During operation, one filter is used and the other remains as a back-up in case the operating filter becomes clogged. The primary filter can then be changed out during operation. Final decontamination of the off-gas particulates is achieved in the two-stage HEPA filter assembly.

4.3.6 Blower

The off-gas is drawn through the system components by an induced-draft, single-stage centrifugal blower. A back-up blower rated at one-fourth the capacity of the primary blower is provided to maintain a negative pressure in the event of primary blower failure.

4.4 Incinerator

The effluent gas from the off-gas system contains carbon monoxide, carbon dioxide, water vapor, hydrogen, and nitrogen. For the process scheme selected for this study, the effluent gas is incinerated to oxidize the CO producing an effluent which primarily consists of carbon dioxide, water vapor, oxygen and nitrogen. The oxidized effluent gas is then vented to the atmosphere.

The combustion takes place downstream of the off-gas treatment system for two reasons. Because a large amount of air is needed to completely oxidize the gas, combustion upstream of the

off-gas system would significantly increase the gas volume through the system, and thus require larger, more expensive equipment. By incinerating the gas downstream, the size and costs of the equipment processing contaminated gases are reduced and a clean gas stream is oxidized in the incinerator producing simple nonhazardous products.

Secondly, the exit-gas from the plasma pyrolysis chamber contains a significant amount of unreacted carbon monoxide and hydrogen and at relatively high temperatures (2500°F). Completing combustion of this gas immediately following the pyrolysis step increases the gas temperature further due to the exothermic nature of the combustion reactions. Combusting the hot off-gas from the main plasma chamber would produce unattractive byproducts, increase the amount of cooling required upstream of the quench tower, and require more exotic combustion chamber construction materials because of high temperatures. Since the production of oxides of nitrogen is a function of temperature, this type of operation would be expected to result in higher effluent oxides of nitrogen concentrations.

The effluent gas from the off-gas system is combusted in a conventional gas incinerator. An assumption of 100% excess air was used to determine the gaseous effluent. The large amount of air reduces the combustion temperature and thus, will produce less oxides of nitrogen according to chemical equilibrium calculations. Because of the high heating value of incoming gas, minimal fuel is needed for the incinerator. To further reduce the oxides of nitrogen production, water could be injected into the incinerator. The off-gases are then exhausted to the stack, which is monitored continuously for radionuclides, oxides of nitrogen, and sulfur dioxide.

Because the heating value of the fuel-rich gas is simply lost if incinerated as shown, the gas could be used for other purposes such as producing steam to make electricity which could support the energy requirements for the torch. Again, trade off studies should be completed to determine superior and efficient energy benefits for this process.

5. MASS AND ENERGY BALANCES

Mass balances were generated for the two feed streams defined earlier in section three of this report and are identified as Stream 1 and Stream 2 throughout this section. A feed rate of 125 tons/waste/day was used to determine the mass balances around one reactor. This feed rate was based on the PEC Plasma Refuse Converter module design which has a capacity of 250 tons/waste/day using two 5 MW pyrolysis reactors. The process is assumed to run in a semi-continuous mode with the reactor being fed in batches of 20-30 tons/charge as recommended by PEC. A stream flow rate summary of the major process streams is presented in Tables 6 and 7 for Stream 1 and Stream 2, respectively. The fully detailed mass balance table for each stream can be found in Appendix A. The stream numbers given in the summary and detailed mass and energy balances correspond to the stream numbers on the Process Flow Diagram.

The following assumptions were made in determining the mass balances:

- The temperature in the main plasma chamber was assumed to be 2000°C in the slag (liquid phase) and 1000°C in the vapor phase based on discussions with PEC.
- One mole of steam per mole of carbon was used to determine the amount of steam required in the main plasma chamber as per the water shift reaction:

- Vapor phase chemical equilibrium is assumed to apply in the main plasma chamber, the afterburner, and the incinerator. Chemical equilibrium was determined using NASA's CEC computer program which considers dissociation and ionizing of constituents.
- Liquid and solid entrainment was neglected throughout the system.
- The ASPEN simulation program was used to model the off-gas system with the following assumptions:
 - Solid particulates were not modeled
 - Heat losses from the system were neglected
 - Henry's Law was used to determine the solubility of HCl in water
 - Vapor/liquid equilibrium was obtained at each equipment component.

The main plasma furnace will be the most significant energy consumer. A detailed energy balance around the main plasma chamber was calculated. The amount of energy required to melt

Table 6. Mass and energy summary for treatment of Stream 1 (sludges).

Stream number	1	2	3	5	6	20	21	22
Stream name	Feed	Plasma gas	Injected steam	Slag	Afterburner offgas	Incinerator air	Incinerator offgas to stack	To atm
Temperature (K)	298	298	478	2273	1644	298	1580	1580
Temperature (F)	77	77	401	3632	2500	77	2384	2384
Total Kgmol/hr	25.03	10.757	12.72	23.236	48.41	145.056	176.801	176.614
Total Kg/hr	4725	310	229	4355	909	4183	4957	4952
Total Lb/hr	10417	684	505	9601	2005	9223	10929	10917
Phase	S	G	G	S	G	G	G	G

Table 7. Mass and energy summary for treatment of Stream 2.

Stream number	1	2	3	5	6	20	21	22
Stream name	Feed	Plasma gas	Injected steam	Slag	Afterburner offgas	Incinerator air	Incinerator offgas to stack	To atm
Temperature (K)	298	298	478	2273	1644	298	1580	1580
Temperature (F)	77	77	401	3632	2500	77	2384	2384
Total Kgmol/hr	86.394	10.757	119.693	37.689	369.853	1267.468	1484.226	1481.895
Total Kg/hr	4725	310	2156	1596	5601	36554	42634	42567
Total Lb/hr	10417	684	4754	3519	12349	80587	93993	8893845
Phase	S	G	G	S	G	G	G	G

and vaporize the feed was calculated using heats of formation and heat capacities for each component (Appendix B).^{9,10} Assumptions used for heat losses in this study were based upon PEC experience. According to PEC, the plasma arc torch will suffer approximately 10- 15% water-cooling loss and the plasma reactor will suffer approximately a 100 kW to 150 kW loss through its refractory lining. Computational results show that a 5 MW torch will be required to treat Stream 1 and a 10 MW torch (or the two 5 MW reactor module) is required to treat Stream 2 under the assumed gas and slag temperature conditions. The difference is primarily due to the different organic content of each stream. Based on a 125 tons/day feed rate and assuming operation of 24 hr/day, the power requirement for the plasma pyrolysis process will be about 900 kW/hr/ton of Stream 1 and 1800 kW/hr/ton of Stream 2 (Appendix B).

6. COST ESTIMATE

A cost estimate was prepared for the plasma pyrolysis process described in this study. The cost identified in the estimate is based on December 1990 dollars. An escalation sheet is included with the detailed estimate in Appendix C for use if escalation is required. The ROM estimated total cost for the process is \$21 million. The total cost can be broken down as follows:

Summary of ROM Total Costs:

<u>Category</u>	<u>Cost (\$)</u>
Engineering, Design, Inspection . . .	2,500,000
Equipment	9,300,000
Construction Management	2,669,000
Project Administration	700,000
Contingency	<u>5,831,000</u>
Total	21,000,000

The ROM equipment costs can be broken down further as follows:

Summary of ROM Equipment Costs:

<u>Equipment</u>	<u>Cost (\$)</u>
Waste Feed System	85,800
Main Plasma Chamber	2,599,200
Transfer System	102,000
Plasma Afterburner	530,940
Transfer System	142,800
Heat Recovery Boiler	458,000
Off-Gas System	2,802,500
Incinerator	<u>2,570,400</u>
Total	9,291,640

In this ROM cost estimate, the building to house the Plasma Pyrolysis Process is assumed to contain heating and ventilation equipment sized to handle the process. Other items assumed to already exist include a crane, office rooms, water and sewer, fire and alarm systems, radiation and contamination control, etc. It is assumed that the majority of the National Environmental Protection Act (NEPA)/Environmental documentation will be included in this building cost.

The estimated total costs and equipment costs in December 1991 dollars are \$21.8 and \$9.6 million respectively. The assumptions used to prepare this estimate and additional details are given in Appendix C.

The estimate discussed above does not include feed pretreatment. A cost estimate for an auger/shredder feed pretreatment system is included as pages C-9 and C-10 in Appendix C. The estimated total costs and equipment costs for the pretreatment system in December 1991 dollars are \$1.2 and \$0.53 million dollars, respectively.

7. RESULTS SUMMARY

A scoping study was performed to evaluate the ROM energy requirement and equipment costs for a plasma pyrolysis thermal processing system as a possible waste treatment process for the INEL buried waste. Two representative INEL buried waste streams were identified for this study. Stream 1 is comprised of stabilized sludges and Stream 2 contains a assortment of mixed waste and soil. A feed rate of 125 tons/waste/day was used to calculate material and energy balances for the plasma pyrolysis treatment system.

The thermal processing waste treatment system chosen for evaluation consisted of a plasma pyrolysis reactor, a plasma afterburner, an off-gas treatment system with waste heat recovery, a final gas incinerator, and a stack. A conceptual flow sheet and cost estimate for this system were generated.

The power input requirement for the plasma pyrolysis reactor was calculated to be approximately 900 kW/hr/ton of Stream 1 waste input and 1800 kW/hr/ton of Stream 2 waste input. The ROM cost estimate for this total process system is \$21.8 million in December 1991 dollars.

8. RECOMMENDATIONS

The calculations performed in this study were intentionally very limited in scope. The purpose was to obtain a first cut ROM estimate for input energy requirements and system costs expected to be required to process the INEL buried wastes in a plasma torch-based pyrolysis system. A single process configuration was evaluated. Other thermal processing systems and component systems are possible and need to be evaluated in the same manner. Other waste streams and variations require consideration. Variations on key assumptions utilized in the study (e.g., gas and slag temperatures, heat losses, pyrolysis vs. combustion/oxidation, oxygen enrichment vs. air, plasma gas composition, extent of waste heat recovery, incineration of waste prior to plasma melting of noncombustibles, etc.) and other process variations need to be examined in similar analytical studies.

Optimization and trade-off studies are recommended to evaluate need for and type of afterburner; off-gas incineration versus utilization of off-gas containing CO and H₂; and cost effectiveness of energy recovery and utilization.

9. REFERENCES

1. S. Hailey, *Plasma Candidate Waste Stream Survey*, SMH-01-90, October 1, 1990.
2. L. J. Stalely, "Hazardous Waste Decontamination with Plasma Reactors," *Hazardous Materials Control*, March/April 1990, pp. 67-71.
3. H. M. Freeman, *Standard Handbook of Hazardous Waste Treatment and Disposal*, New York: McGraw-Hill Book Company, Inc., 1989, pp. 8.169-8.177.
4. E. C. Garcia and J. L. Knight, *Hazardous Organic Content of Pit 9*, EG&G Idaho, Inc., EDF BWP-ISV-002 Rev. 0, January 1989.
5. J. O. Low, *Annual Technology Assessment and Progress Report for the Buried Transuranic Waste Program at the Idaho National Engineering Laboratory*, EGG-2429, December 1985.
6. S. L. Camacho, "Plasma Pyrolysis of Medical Waste," *Plasma Symposium, Hyatt Richeys, Palo Alto, CA, March 7-9, 1990*.
7. R. Geimer, Science Applications International Corporation, "Plasma Arc Incineration of a Supercompacted Waste Form," *Plasma Applications to Waste Treatment Conference, Idaho National Engineering Laboratory, Idaho Falls, Idaho, January 16-17, 1991*.
8. T. L. Clements, Jr., *Content Code Assessments for INEL Contact-Handled Stored Transuranic Wastes*, WM-F1-82-021, EG&G Idaho, Inc., October 1982.
9. R. H. Perry and D. W. Green, *Perry's Chemical Engineers' Handbook*, 6th Edition, McGraw-Hill Book Company, Inc., New York, 1984.
10. R. C. Weast, *CRC Handbook of Chemistry and Physics*, 59th Edition, CRC Press, Boca Raton, Florida, 1974.
11. C. A. Wentz, *Hazardous Waste Management*, New York: McGraw-Hill Book Company, Inc., 1989.
12. L. Theodore and J. Reynolds, *Introduction to Hazardous Waste Incineration*, New York: John Wiley & Sons Publishing Co., 1987.
13. T. L. Clements, Jr. and D. E. Kudera, *TRU Waste Sampling Program: Vol. I-Waste Characterization*, EGG-WM-6503, September 1985.
14. Gordon and McBride, *Computer Program for Calculation of Complex Chemical Equilibrium Compositions, Rocket Performance, Incident and Reflected Shocks, and Chapman-Jouguet Detonations*, NASA SP-273, March 1976.

Appendix A

Mass Balance Tables

Mass Balance Table for Stream 1

STREAM ONE COMPONENTS	PROCESS STREAMS (Kgmol/hour)							
	Molecular Weight (g/mole)	Waste Feed 1	Pyrolysis Plasma Gas 2	250 psi Steam 3	Pyrolysis Offgas 4	Slag 5	After-Burner Offgas 6	Boiler Effluent 7
Texaco Regal Oil	282.0	0.417						
Carbon Tetrachloride	153.8	0.846						
1,1,1-trichloroethane	133.4	0.169						
trichloroethylene	131.3	0.140						
perchloroethylene	165.8	0.123						
Used Oil (C20.H42)	282.0	0.134						
PCB's	326.3	trace						
Calcium Silicate (Ca2SiO4)	172.2	7.282				7.282		
(Ca3SiO5)	228.3	12.819				12.819		
Mercury	200.6	0.110			0.11		0.110	0.110
Lithium	6.9	0.125						
Plutonium	244.0	trace				trace		
Americium	243.0	trace				trace		
Carbon Steel	55.8	3.135				3.135		
CO	28.0				11.528		11.9657	11.9657
CO2	44.0				1.214		0.762	0.762
H2O	18.0			12.72	3.3		3.7448	3.7448
HCl	36.4				4.683		4.6765	4.6765
H2	2.0				18.997		18.5292	18.5292
CH4	16.0				trace			
H	1.0						0.002	0.002
Oxygen	32.0		2.259					
Nitrogen	28.0		8.498		8.507		8.4957	8.4957
LiCl	42.4				0.107		0.124	0.124
Li2Cl2	84.8				0.009			
NH3	17.0				trace			
Cl	35.5						0.000	0.000
NO	30.0							
Total, (kgmoles/hour)		25.300	10.757	12.720	48.455	23.236	48.410	48.410
Total, (kg/hour)		4725.368	310.232	229.151	909.615	4355.136	909.437	909.437
Phase		M	V	V	V	S	V	V
Temperature (K)		298.15	298.15	473.67	1273.00	2273.00	1644.00	672.04
Pressure (Atm)		0.98	4.00	17.01	0.98	0.98		0.97

Mass Balance Table for Stream 1

STREAM ONE		PROCESS STREAMS (Kgmol/hour)						
COMPONENTS	Molecular Weight (g/mole)	Cooler Effluent	Quench Scrub Solution	Quencher Condensat	Scrubber/ Quencher Effluent	Tand. Noz Scrubber Solution	Tandem Nozzle Condensat	Tandem Nozzle Effluont
		8	9	10	11	12	13	14
Texaco Regal Oil	282.0							
Carbon Tetrachloride	153.8							
1,1,1-trichloroethane	133.4							
trichloroethylene	131.3							
perchloroethylene	165.8							
Used Oil (C20.H42)	282.0							
PCB's	326.3							
Calcium Silicate (Ca2SiO4)	172.2							
(Ca3SiO5)	228.3							
Mercury	200.6	0.110		0.110				
Lithium	6.9							
Plutonium	244.0							
Americium	243.0							
Carbon Steel	55.8							
CO	28.0	11.9657		0.006	11.9598		0.0257	11.934
CO2	44.0	0.762		0.0103	0.7516		0.0332	0.7183
H2O	18.0	3.7448	65.3173	50.9827	18.079	122.4699	129.9082	10.6407
HCl	36.4	4.6765		4.6765				
H2	2.0	18.5292			18.5293			18.5293
CH4	16.0							
H	1.0	0.002		0.002				
Oxygen	32.0							
Nitrogen	28.0	8.4957		0.0038	8.4919		0.016	8.4756
LiCl	42.4	0.124		0.124				
Li2Cl2	84.8							
NH3	17.0							
Cl	35.5							
NO	30.0							
Total, (kgmoles/hour)		48.410	65.317	55.915	57.812	122.470	129.983	50.298
Total, (kg/hour)		909.428	1176.691	1115.972	969.003	2206.295	2342.919	832.360
Phase		V	L	L	V	L	L	V
Temperature (K)		672.04	294.26	352.22	339.22	294.26	331.18	331.18
Pressure (Atm)		0.96	1.36		0.95	1.36		0.81

Mass Balance Table for Stream 1

STREAM ONE	PROCESS STREAMS (Kgmol/hour)							
	COMPONENTS	Molecular Weight (g/mole)	Condenser Condensate 15	Condenser Effluent 16	Reheater Effluent 17	HEPA Filter Effluent 18	Second Incinerator Feed 19	Air 20
								Second Incinerator Offgas 21
	Texaco Regal Oil	282.0						
	Carbon Tetrachloride	153.8						
	1,1,1-trichloroethane	133.4						
	trichloroethylene	131.3						
	perchloroethylene	165.8						
	Used Oil (C ₂₀ H ₄₂)	282.0						
	PCB's	326.3						
	Calcium Silicate (Ca ₂ SiO ₄)	172.2						
	(Ca ₃ SiO ₅)	228.3						
	Mercury	200.6						
	Lithium	6.9						
	Plutonium	244.0						
	Americium	243.0						
	Carbon Steel	55.8						
	CO	28.0	0.000798	11.9332	11.9332	11.9332	11.9332	
	CO ₂	44.0	0.0009	0.7174	0.7174	0.7174	0.7174	12.6506
	H ₂ O	18.0	3.3168	7.3238	7.3238	7.3238	7.3238	25.842
	HCl	36.4						
	H ₂	2.0		18.5293	18.5293	18.5293	18.5293	
	CH ₄	16.0						
	H	1.0						
	Oxygen	32.0						30.462
	Nitrogen	28.0	0.00049	8.4753	8.4753	8.4753	8.4753	114.594
	LiCl	42.4						
	Li ₂ Cl ₂	84.8						
	NH ₃	17.0						
	Cl	35.5						
	NO	30.0						0.187
	Total, (kgmoles/hour)		3.319	46.979	46.979	46.979	46.979	145.056
	Total, (kg/hour)		59.829	772.532	772.532	772.532	772.532	4183.416
	Phase		L	V	V	V	V	V
	Temperature (K)		324.82	324.82	352.59	352.59	353.68	298.15
	Pressure (Atm)			0.79	0.76	0.75	0.98	0.98

Mass Balance Table for Stream 1

STREAM ONE		PROCESS STREAMS (Kgmol/hour)					
COMPONENTS	Molecular Weight	Stack Gas	Waste Sludge	Boiler Feedwater	Steam 250psi to Reheater	Cooling 1 Medium Supply	Cooling 2 Medium Supply
	(g/mole)	22	23	24	25	26	27
Texaco Regal Oil	282.0						
Carbon Yetrachloride	153.8						
1,1,1-trichloroethane	133.4						
trichlorethylene	131.3						
perchloroethylene	169.8						
Used Oil (C20.H42)	282.0						
PCB's	326.3						
Calcium Silicate (Ca2Si1O4)	172.2						
(Ca3Si1O5)	228.3						
Mercury	200.6						
Lithium	6.9						
Plutonium	244.0						
Americium	243.0						
Carbon Steel	55.8						
CO	28.0						
CO2	44.0	12.6506					
H2O	18.0	25.842		34.0194	34.0194	1257	1257
HCl	36.4						
H2	2.0						
CH4	16.0						
H	1.0						
Oxygen	32.0	15.1316					
Nitrogen	28.0	122.99					
LiCl	42.4						
Li2Cl2	84.8						
NH3	17.0						
Cl	35.5						
NO	30.0						
Total, (kgmoles/hour)		176.614	Did Not	34.019	34.019	1257.000	1257.000
Total, (kg/hour)		4951.909	Calculate	612.859	612.859	22644.86	22644.86
Phase		V	S	L	V	L	L
Temperature (K)		1580.00		294.26	478.67	298.15	298.15
Pressure (Atm)		0.98		17.01	17.01	13.60	13.60

Mass Balance Table for Stream 2

STREAM 2		PROCESS STREAMS (Kgmol/hour)						
COMPONENTS	Molecular Weight (g/mole)	Waste Feed	Pyrolysis Plasma Gas	250 psi Steam	Pyrolysis Offgas	Slag	After-Burner Offgas	Boiler Effluent
		1	2	3	4	5	6	7
C6 H10 O5	162.0	10.686						
Sulfur	256.0	0.009						
C7 H14 O7	210.0	2.064						
Fe	55.8	8.306				8.306		
SiO2	60.1	12.221				12.221		
Al2 O3	101.9	0.528				0.528		
Fe2 O3	159.6	0.109				0.109		
CaO	56.1	1.487				1.487		
K2 O	94.2	0.111				0.171		
MgO	40.3	0.173				0.173		
NH3	17.0				0.0037		trace	trace
B2 O3	69.6	0.537				0.537		
Na2 O	62.0	0.186				0.186		
Al2 O3 Si O2	162.0	0.014				0.014		
Mg Si O3	100.4	0.023				0.023		
(C2 H4)x	28.0	10.749						
(C8 H8)x	104.0	2.455						
Lithium	6.9	0.007						
Mercury	200.6	0.006			0.0074		0.0074	0.0074
Graphite	12.0	13.934				13.934		
CH4	16.0				0.0074			
CO	28.0				95.534		103.7637	103.7637
CO2	44.0				24.137		15.9573	15.9573
H2	2.0				170.518		162.4042	162.4042
O2	32.0		2.259					
N2	28.0		8.498		8.4943		8.4957	8.4957
H2O	18.0	22.789		119.693	71.02		79.2244	79.2244
H2S	34.1				0.0702		trace	trace
LiOH	23.9				0.0074		trace	trace
NO	30.0							
Total, (kmoles/hour) -----		86.394	10.757	119.693	369.7994	37.689	369.8527	369.8527
Total, (kg/hour) -----		4725.32	310.232	2156.269	5598.499	1596.35	5601.419	5601.419
Phase -----		M	V	V	V	S	V	V
Temperature (K) -----		298.15	298.15	478.67	1273.15	2273.15	1644	672.04
Pressure (atm) -----		0.98	4.00	17.01	0.98	0.98		0.97

Mass Balance Table for Stream 2

STREAM 2								
COMPONENTS	Molecular Weight (g/mole)	PROCESS STREAMS (Kgmol/hour)						
		Cooler Effluent 8	Quench Scrub Solution 9	Quencher Condensat 10	Scrubber/ Quencher Effluent 11	Tand. Noz Scrubber Solution 12	Tandem Nozzle Condensat 13	Tandem Nozzle Effluent 14
C6 H10 O5	162.0							
Sulfur	256.0							
C7 H14 O7	210.0							
Fe	55.8							
SiO2	60.1							
Al2 O3	101.9							
Fe2 O3	159.6							
CaO	56.1							
K2 O	94.2							
MgO	40.3							
NH3	17.0	trace		trace				
B2 O3	69.6							
Na2 O	62.0							
Al2 O3 Si O2	162.0							
Mg Si O3	100.4							
(C2 H4)x	28.0							
(C8 H8)x	104.0							
Lithium	6.9							
Mercury	200.6	0.0074		0.0074				
Graphite	12.0							
CH4	16.0							
CO	28.0	103.7637			103.7637			103.7637
CO2	44.0	15.9573			15.9573			15.9573
H2	2.0	162.4042			162.4041			162.4041
O2	32.0							
N2	28.0	8.4957			8.4957			8.4957
H2O	18.0	79.2244	501.6731	459.3479	121.5618	940.7505	998.2602	64.0521
H2S	34.1	trace		trace				
LiOH	23.9	trace		trace				
NO	30.0							
Total, (kgmoles/hour) -----		0	501.6731	0	412.1826	940.7505	998.2602	354.6729
Total, (kg/hour) -----		0	9037.641	0	6364.017	16947.62	17983.66	5327.967
Phase -----		V	L	L	V	L	L	V
Temperature (K) -----		672.04	294.26	342.66	336.78	294.26	326.158	326.158
Pressure (atm) -----		0.96	1.36		0.95	1.36		0.81

Mass Balance Table for Stream 2

STREAM 2		PROCESS STREAMS (Kgmol/hour)						
COMPONENTS	Molecular Weight (g/mole)	Condenser Condensat 15	Condenser Effluent 16	Reheater Effluent 17	HEPA Filter Effluent 18	Second Incinerat Feed 19	Air 20	Second Inciner. Offgas 21
C6 H10 O5	162.0							
Sulfur	256.0							
C7 H14 O7	210.0							
Fe	55.8							
SiO2	60.1							
Al2 O3	101.9							
Fe2 O3	159.6							
CaO	56.1							
K2 O	94.2							
MgO	40.3							
NH3	17.0							
B2 O3	69.6							
Na2 O	62.0							
Al2 O3 Si O2	162.0							
Mg Si O3	100.4							
(C2 H4)x	28.0							
(C8 H8)x	104.0							
Lithium	6.9							
Mercury	200.6							
Graphite	12.0							
CH4	16.0							
CO	28.0		103.7637	103.7637	103.7637	103.7637		
CO2	44.0		15.9573	15.9573	15.9573	15.9573		119.714
H2	2.0		162.4041	162.4041	162.4041	162.4041		
O2	32.0						266.168	191.314
N2	28.0		8.4957	8.4957	8.4957	8.4957	1001.3	1008.62
H2O	18.0	4.5747	59.4774	59.4774	59.4774	59.4774		162.247
H2S	34.1							
LiOH	23.9							
NO	30.0							2.331
Total, (kgmoles/hour) -----		4.5747	350.0982	350.0982	350.0982	350.0982	1267.468	1484.226
Total, (kg/hour) -----		82.41322	5245.556	5245.556	5245.556	5245.556	36553.78	42634.39
Phase -----		L	V	V	V	V	V	V
Temperature (K) -----		324.82	324.82	352.59	352.59	353.67	298.15	1625.3
Pressure (atm) -----			0.79	0.76	0.75	0.98	0.98	0.98

Mass Balance Table for Stream 2

STREAM 2		P R O C E S S S T R E A M S (Kg/mol/hour)						
COMPONENTS	Molecular Weight (g/mole)	Stack Gas 22	Waste Sludge 23	Boiler Feedwater 24	Steam 250psi to Reheater 25	Cooling 1 Medium Supply 26	Cooling 2 Medium Supply 27	
C6 H10 O5	162.0							
Sulfur	256.0							
C7 H14 O7	210.0							
Fe	55.8							
SiO2	60.1							
Al2 O3	101.9							
Fe2 O3	159.6							
CaO	56.1							
K2 O	94.2							
MgO	40.3							
NH3	17.0							
B2 O3	69.6							
Na2 O	62.0							
Al2 O3 Si O2	162.0							
Mg Si O3	100.4							
(C2 H4)x	28.0							
(C8 H8)x	104.0							
Lithium	6.9							
Mercury	200.6							
Graphite	12.0							
CH4	16.0							
CO	28.0							
CO2	44.0	119.714						
H2	2.0							
O2	32.0	191.314						
N2	28.0	1008.62						
H2O	18.0	162.247		385.5535	265.8605	1257	1257	
H2S	34.1							
LiOH	23.9							
NO	30.0							
Total, (kgmoles/hour) -----		1481.895	Did Not Calculate	385.5535	265.8605	1257	1257	
Total, (kg/hour) -----		42567.43		6945.746	4789.477	22644.86	22644.86	
Phase -----		V	L	L	L/V	L	L	
Temperature (K) -----			326.15	294.26	480.81	298.15	298.15	
Pressure (atm) -----		0.98		17.01	17.01	13.60	13.60	

Appendix B

Summary of Energy Balance Calculations

HEAT BALANCE SUMMARY
FOR MAIN PLASMA CHAMBER FOR WASTE
STREAM 1, (DATUM 25°C)

$$\text{HEAT INPUT FROM TORCH} = \text{HEAT LOSSES FROM FURNACE} + \text{HEAT LOSSES TO COOLING MEDIUM} + \text{HEAT OF REACTION (ENDOTHERMIC)} + \text{ENTHALPY OF EFFLUENTS} - \text{ENTHALPY OF FEED}$$

The following tables were generated to solve the energy balance.

HEAT BALANCE SUMMARY FOR MAIN PLASMA CHAMBER FOR WASTE STREAM 2, (DATUM 25°C)

PLASMA ARC REACTOR HEAT AND MATERIAL BALANCE
GAS PHASE HEAT BALANCE - STREAM 1

	MOL WT (KG/KG-MOL)	HEAT OF FORMATION (KCAL/GM-MOL)	HEAT CAPACITY AT 512 DEG C (CAL/GM-DEG C)	STREAM 1 REACTANTS (KG-MOLS/HR)	STREAM 1 REACTANTS (KG/HR)	STREAM 1 PRODUCTS (KG-MOLS/HR)	STREAM 1 PRODUCTS (KG/HR)	HEAT OF FORMATION REACTANTS (KCAL/HR)	HEAT OF FORMATION PRODUCTS (KCAL/HR)	SENSIBLE HEAT OF PRODUCTS 25 - 1000 C (KCAL/HR)
C20H42	282	-133		0.551	155.38		0.00	-73283	0	0
CCl4	153.8	-33.3		0.846	130.11		0.00	-28172	0	0
C2H3Cl	133.4	-33.8		0.169	22.54		0.00	-5712	0	0
C2HCl3	131.3	-1.4		0.14	18.38		0.00	-196	0	0
C2Cl4	165.8	-3.4		0.123	20.39		0.00	-418	0	0
Hg	200.6	0	0.025	0.11	22.07	0.11	22.07	0	0	538
Li	6.9	0		0.125	0.86		0.00	0	0	0
O2	31.999	0		2.259	72.29		0.00	0	0	0
N2	28.013	0	0.266	8.498	238.05		0.00	0	0	61807
NH3	17.007	-10.96		12.72	0.00	8.5073	238.31	-735189	-190704	29615
H2O	18.015	-57.7979	0.511		229.15	0.0005	59.44	0	-2	1
CH4	16.042	-17.889	0.93		0.00	3.2995	0.00	0	-304529	84974
CO	28	-26.416	0.27		0.00	0.0001	322.79	0	-114217	14330
CO2	44.01	-94.052	0.275		0.00	1.2144	53.45	0	-103321	33240
HCl	36.4	-22.063	0.2		0.00	4.683	170.46	0	0	132248
H2	2	0	3.57		0.00	18.997	37.99	0	0	0
H2S	34.076	-4.815	0.296		0.00		0.00	0	0	0
LiOH	23.94	-116.58	0.25 *		0.00	0.1066	4.52	0	-10407	1102
LiCl	42.394	-97.63	0.25 *		0.00	0.0092	0.78	0	-1796	190
Li2Cl2	84.788	-195.26 *	0.25 *		0.00					
					909.24		909.82	-842970	-724982	358045

* ESTIMATED

PLASMA ARC REACTOR HEAT AND MATERIAL BALANCE
GAS PHASE HEAT BALANCE - STREAM 2

	MOL WT (KG/KG-MOL)	HEAT OF FORMATION (KCAL/GM-MOL)	HEAT CAPACITY AT 512 DEG C (CAL/GM-DEG C)	STREAM 2 REACTANTS (KG-MOLS/HR)	STREAM 2 REACTANTS (KG/HR)	STREAM 2 PRODUCTS (KG-MOLS/HR)	STREAM 2 PRODUCTS (KG/HR)	HEAT OF FORMATION REACTANTS (KCAL/HR)	HEAT OF FORMATION PRODUCTS (KCAL/HR)	SENSIBLE HEAT OF PRODUCTS 25 - 1000 C (KCAL/HR)
C6H10O5	162	-261.1 *		10.686	1731.13			-2790114.6	0	0
C7H14O7	210	-338.52 *		2.064	433.44			-698705.3	0	0
H2O (l)	18.015	-68.3174		22.789	410.54			-1556885.2	0	0
C2H4	28	12.496		10.749	300.97			134319.5	0	0
C8H8	104	35.32		2.455	255.32			86710.6	0	0
Hg	200.6	0	0.025	0.006	1.20	0.0074	1.48	0	0	36
Li	6.9	0		0.007	0.05			0	0	0
O2	31.999	0		2.259	72.29			0	0	0
N2	28.013	0	0.266	8.498	238.05	8.4943	237.95	0	-41	61713
NH3	17.007	-10.96				0.0037	0.06	0	-4104807	637442
H2O (g)	18.015	-57.7979	0.511	119.693	2156.27	71.02	1279.43	-6918004	-132	108
CH4	16.042	-17.889	0.93			0.0074	0.12	0	-2523629	704182
CO	28	-26.416	0.27			95.5341	2674.95	0	-2270114	284819
CO2	44.01	-94.052	0.275			24.1368	1062.26	0	0	1187061
H2	2	0	3.57			170.518	341.04	0	0	690
H2S	34.076	-4.815	0.296 *			0.0702	2.39	0	-338	43
LiOH	23.94	-116.58	0.25 *			0.0074	0.18	0	-863	2876093
				179.21	5599.27	369.80	5599.86	-11742679	-8899924	

* ESTIMATED

PLASMA ARC REACTOR
 STREAM 1 WASTE FEED (SLUDGES)
 CALCULATION OF CHANGE IN ENTHALPY OF SLAG/MOLTEN METAL IN REACTOR
 (SENSIBLE HEAT TO HEAT FROM 25 degC TO 2000 degC PLUS
 HEAT OF TRANSITION FOR PHASE CHANGES)

COMPONENT	MOL WT	SENSIBLE HEAT 298-2273K (Kcal/gmol)	HEAT OF TRANSITION (Kcal/gmol)	TOTAL ENTHALPY CHANGE 298-2273K (Kcal/gmol)	TOTAL ENTHALPY CHANGE 298-2273K (Kcal/kg)	SLAG/MOLTEN METAL	ENTHALPY (Kcal/hr)
						FLOW (Kgmol/hr)	FLOW (Kg/hr)
Ca2SiO4	172.24	59.53	13.4	72.93	627.8	7.282	1254
Ca3SiO5	228.32	59.53	13.4	72.93	627.8	12.819	2927
SiO2	60.08	33.78	2.19	35.97	598.6		
Al2O3	101.96	61.86	26	87.86	861.7		
Fe2O3	159.69	99.59	0.16	99.75	624.6		
CaO	56.08	31.91	18	49.91	890.0		
K2O	94.2	42.08	6.8	48.88	518.9		
MgO	40.3	24.24	18.5	42.74	1060.5		
B2O3	69.62	56.28	5.27	61.55	884.1		
Na2O	61.98	41.41	7.1	48.51	782.7		
MgSiO3	100.39	60.87	14.7	75.57	752.8		
C (Graphite)	12.01	10.44		10.44	869.0		
Fe	55.85	18.09	4.64	22.73	407.0	3.135	175
Pu	244	15.42	2.26	17.68	72.5	TR	TR
Am	243	16.51	2.4	18.91	77.8	TR	TR
Total:					Total:	23.236	4356
							2696312

PLASMA ARC REACTOR
 STREAM 2 WASTE FEED (COMPOSITE)
 CALCULATION OF CHANGE IN ENTHALPY OF SLAG/MOLTEN METAL IN REACTOR
 (SENSIBLE HEAT TO HEAT FROM 25 degC TO 2000 degC PLUS
 HEAT OF TRANSITION FOR PHASE CHANGES)

COMPONENT	MOL WT	SENSIBLE HEAT 298-2273K (Kcal/gmol)	HEAT OF TRANSITION (Kcal/gmol)	TOTAL ENTHALPY CHANGE 298-2273K (Kcal/gmol)	TOTAL ENTHALPY CHANGE 298-2273K (Kcal/Kg)	SLAG/MOLTEN METAL	ENTHALPY (Kcal/hr)
						FLOW (Kg/hr)	
						FLOW (kgmol/hr)	
Ca2SiO4	172.24	59.53	13.4	72.93	627.8		
Ca3SiO5	228.32	59.53	13.4	72.93	627.8	735	439792
SiO2	60.08	33.78	2.19	35.97	598.6	55	47004
Al2O3	101.96	61.86	26	87.86	861.7	17	10875
Fe2O3	159.69	99.59	0.16	99.75	624.6	83	74215
CaO	56.08	31.91	18	49.91	890.0	10	5426
K2O	94.2	42.08	6.8	48.88	518.9	7	7394
MgO	40.3	24.24	18.5	42.74	1060.5	37	33054
B2O3	69.62	56.28	5.27	61.55	884.1	12	9024
Na2O	61.98	41.41	7.1	48.51	782.7	2	1738
MgSiO3	100.39	60.87	14.7	75.57	752.8	167	145417
C (Graphite)	12.01	10.44		10.44	869.0	464	188782
Fe	55.85	18.09	4.64	22.73	407.0		
Pu	244	15.42	2.26	17.68	72.5		
Am	243	16.51	2.4	18.91	77.8		
Total:						37.629	962718
						1590	

Appendix C
Cost Estimate

"Providing research and development services to the government"

INTEROFFICE CORRESPONDENCE

Date: December 20, 1990

To: K. E. Sherick, MS 3422

From: A. R. Millward, MS 3508 *ARM*

Subject: STUDY ESTIMATE FOR THE PLASMA PYROLYSIS PROCESS - ARM-54-90

Cost Estimating has prepared the attached Study Cost Estimate. Attached are the cost estimate summary sheet, detailed cost estimate sheets, and a blank escalation sheet. As you requested, the costs identified in the estimate are based on December 1990 dollars. The blank escalation sheet is attached for your use if escalation is required.

The major assumptions and work scope which was not identified on your Flow Diagram but was included in our estimate is as follows:

The building that will house the Plasma Pyrolysis Process is existing or will be included in some other cost estimate. This building will have heating and ventilation equipment sized to handle the process, crane (if required), offices, rest rooms, lunch room, conference rooms, water and sewer, fire systems plus all building containment and alarm systems for radiation and contamination control, etc., necessary to handle this operation. It is assumed that the majority of the NEPA/Environmental documentation will be included in this building cost.

Included in our estimate is building modification for an operations control room with local and remote control devices (electrical and mechanical), and electrical power upgrades in the building and facility. Included are underground conduits and wire from an existing substation sized to feed 10 Megawatts of power to the building. Also included is power distribution equipment to handle the 10 Megawatts of power at the building. The upgrade of the facility power does not include upgrading of the power to the facility, modifications to the substations at the facility, or at the Scoville Substation.

Included in the Engineering Cost is extra time to perform studies of the possible emissions that could be emitted by the process. This is a major cost and is included with the assumption that this might have to be done prior to the building or facility NEPA documentation.

K. E. Sherick
December 20, 1990
ARM-54-90
Page 2

Attached is a detailed cost estimate sheet and a summary sheet labeled "Appendix A". These sheets are included to identify estimated costs of a pretreatment auger/shredder which can be added to the total estimated cost identified in the other attached cost estimate sheets if required.

If we can be of further assistance, please feel free to call me at 526-0944.

arm

Attachments:
As Stated

cc: Central Files, MS 1651
Project File #5147 *MRB*
A. R. Millward File

EG&G Idaho, Inc.

COST ESTIMATE SUMMARY

Type of Estimate : STUDY

File No.: 5147

Date: 12/20/90

Project : PLASMA PYROLYSIS PROCESS

Prepared By : A. R. Millward

Checked/Approved By: *ZMR*

	Unescalated	Escalation	Totals:
Engineering, Design and Inspection	(	21% of construction)	2,500,000
Performance Specification			
Title I & II Design	2,000,000		
Title III Inspection	500,000		
Construction Costs Subtotal			11,969,000
Direct/Indirect Costs		9,300,000	
4000 Improvement to Land			
5000 Buildings/ Structures			
6000 Utilities			
7000 Equipment	9,300,000		
8000 Demolition & Removal			
Indirect Costs	INCLUDED ABOVE		
Construction Management		2,669,000	
Field Engr and Const Mgmt	1,581,000		
Const Mgmt Reserve	1,088,000		
Government Furnished Material			
Purchased By CM			
Purchased By			
Procurement Fee			
Project Administration Costs			700,000
Project Management	255,000		
Project Support	445,000		
Subtotal			15,169,000
Contingency	38% of Subtotal		5,831,000
Escalation (included in above totals)			
Total Estimated Cost			21,000,000

Comments:

EG&G Idaho, Inc.

Date : 12/20/90
Page : 1 of 3

File No. 5147

Type of Est. STUDY

Project or Description

PIASMA PYROLYSIS PROCESS

SOURCE OF ESTIMATE
(E) Eng. Est.
(V) Vendor
(P) Pur. Order
(H) Handbook Ref.

Prepared By: A. R. Millward

Chk'd/Appr'd By :

(E) Eng. Est.
(V) Vendor
(P) Pur. Order
(H) Handbook R

THE

K. E. SHERICK

Acct. No.	Description	E.V, P,H	Mat'l Unit	Mat'l Ut. Cost	Unit Lab. Hrs.	Total Lab. Hrs.	Labor Rate	Labor Cost	Mat'l. Cost	LINE ITEM SUBTOTAL	Total Cost
	WASTE FEED SYSTEM										
	CONVEYOR/WALKING FLOOR	E/H	60 LF	500	8	480	35	16,800	30,000	\$46,800	
	ELECTRICAL	E/H	1 LOT	25000	400	400	35	14,000	25,000	\$39,000	
	SUBTOTAL										85,800
	MAIN PLASMA SYSTEM										
	PLASMA CHAMBER	E/V	1 LOT	2000000	1200	1,200	35	42,000	2,000,000	\$2,042,000	
	MECHANICAL PIPING/EQUIPMENT	E/H	1 LOT	500000	600	600	35	21,000	500,000	\$521,000	
	ELECTRICAL	E/H	1 LOT	25000	320	320	35	11,200	25,000	\$36,200	
	SUBTOTAL										2,599,200
	TRANSFER SYSTEM										
	PIPING (LINED & INS. TO ACCEPT HEAT)	E/H	50 LF	1200	24	1,200	35	42,000	60,000	\$102,000	
	SUBTOTAL										102,000
	PLASMA AFTERBURNER										
	AFTERBURNER	V/E	1 LOT	500000					500,000	\$500,000	
	MECHANICAL	E/H	1 LOT	2500	120	120	37	4,440	2,500	\$6,940	
	ELECTRICAL	E/H	1 LOT	10000	400	400	35	14,000	10,000	\$24,000	
	SUBTOTAL										530,940
	SUBTOTAL OF ALL COSTS										3,317,940

ASSUMPTIONS: THIS IS A ROM ESTIMATE, THE BUILDING EXISTS (W/H&V & CRANES), UTILITIES FOR ALARMS AND COMMUNICATIONS, POTABLE WATER, SEWER AND FIRE WATER EXIST, ELECTRICAL POWER WITHIN THE FACILITY WILL BE UPGRADED (THIS DOES NOT INCLUDE POWER UPGRADE TO THE FACILITY). EACH COST INCLUDES OVERHEAD AND PROFIT. THE SYSTEM IS FIXED PERMANENTLY INSIDE AN EXISTING BUILDING. THE OFFGAS SYSTEM COST WILL BE BASED ON THE COSTS IDENTIFIED IN OTHER ESTIMATES GENERATED BY THIS GROUP (BATTELLE REPORT OF MARCH 1987).

EG&G Idaho, Inc.

DETAILED COST ESTIMATE (CONT. SHEET)

Page 2

Project or
Description

PLASMA PYROLYSIS PROCESS

Type of Est. STUDY

File No. 5147

Date : 12/20/90

Page : 2 of 3

Acct. No.	Description	E.V. P.H.	Mat'l Unit	Mat'l Ut. Cost	Unit Lab. Hrs.	Total Lab. Hrs.	Labor Rate	Labor Cost	Mat'l. Cost	LINE ITEM SUBTOTAL	Total Cost
	TRANSFER SYSTEM										
	PIPING (LINED & INS. TO ACCEPT HEAT)	E/H	70 LF	1200	24	1,680	35	58,800	84,000	142,800	142,800
	SUBTOTAL										
	HEAT RECOVERY BOILER	E/V	1 EACH	250000	600	600	35	21,000	250,000	271,000	
	MECHANICAL	E/H	1 LOT	50000	2000	2,000	35	70,000	50,000	120,000	
	ELECTRICAL	E/H	1 LOT	25000	1200	1,200	35	42,000	25,000	67,000	
	SUBTOTAL										458,000
	OFF GAS SYSTEM	E/H	1 LOT	1500000	3500	3,500	35	122,500	1,500,000	1,622,500	
	MECHANICAL	E/H	1 LOT	750000	3000	3,000	35	105,000	750,000	855,000	
	ELECTRICAL	E/H	1 LOT	150000	5000	5,000	35	175,000	150,000	325,000	
	SUBTOTAL										2,802,500
	INCINERATOR	E/H	1 EACH	200000	1500	1,500	35	52,500	200,000	252,500	
	BLOCK STACK AND MONITORING SYSTEM	E/H	1 LOT	250000	1200	1,200	35	42,000	250,000	292,000	
	CONTROL ROOM	E/H	1 LOT	50000					50,000	50,000	
	EQUIPMENT	E/H	1 LOT	250000	1000	1,000	35	35,000	250,000	285,000	
	PRIMARY ELECTRICAL WITHIN THE FACILITY	E/H	1 LOT	1500000	4500	4,500	35	157,500	1,500,000	1,657,500	
	FACILITY BUILDING MODIFICATIONS	E/H	1 LOT	25000	240	240	35	8,400	25,000	33,400	
	SUBTOTAL										2,570,400
	SUBTOTAL OF ALL ABOVE COSTS										55,973,700
	SUBTOTAL FROM PAGE ONE										3,317,940
											USE \$9,300,000
	TOTAL OF ALL COSTS										\$9,291,640

[illegible]

EG&G Idaho, Inc.

COST ESTIMATE SUMMARY

Type of Estimate : STUDY

File No.: 5147

Date: 12/20/90

Project : PLASMA PYROLYSIS PROCESS - APPENDIX A

Prepared By : A. R. Millward

Checked/Approved By: *[Signature]*

	Unescalated	Escalation	Totals:
Engineering, Design and Inspection	(	21% of construction)	135,000
Performance Specification			
Title I & II Design	110,000		
Title III Inspection	25,000		
Construction Costs Subtotal			649,000
Direct/Indirect Costs		504,000	
4000 Improvement to Land			
5000 Buildings/ Structures			
6000 Utilities			
7000 Equipment	504,000		
8000 Demolition & Removal			
Indirect Costs	INCLUDED ABOVE		
Construction Management		145,000	
Field Engr and Const Mgmt	86,000		
Const Mgmt Reserve	59,000		
Government Furnished Material			
Purchased By CM			
Purchased By			
Procurement Fee			
Project Administration Costs			30,000
Project Management	20,000		
Project Support	10,000		
Subtotal			814,000
Contingency	35% of Subtotal		286,000
Escalation (included in above totals)			
Total Estimated Cost			1,100,000

Comments:

EG&G Idaho, Inc.

DETAILED COST ESTIMATE SHEET

Project or
Description

PLASMA PYROLYSIS PROCESS

Type of Est. STUDY

File No. 5147

Date : 12/20/90

APPENDIX A

SOURCE OF ESTIMATE
(E) Eng. Est.
(V) Vendor

Page : 1 of 1

Location

INEL

Prep. By : A. R. Millward

Requester

K. E. SHERICK

(P) Pur. Order
(H) Handbook Ref.

Chk'd/Appro'd By :

Acct. No.	Description	E.V. P.H.	Mat'l Unit	Mat'l Cost	Unit Lab. Hrs.	Total Lab. Hrs.	Labor Rate	Labor Cost	Mat'l. Cost	LINE ITEM SUBTOTAL	Total Cost
ASSUMPTIONS: THIS APPENDIX WILL BE USED IF THE PLASMA PYROLYSIS PROCESS REQUIRES PRETREATMENT OF THE FEED PRODUCT. THIS ASSURES THAT NO BUILDING MODIFICATION WILL BE DONE ON THIS ESTIMATE. IT IS ASSUMED THAT THIS WILL BE DONE BY A SHREDDER. IT SHOULD BE NOTED THAT THIS ESTIMATE WILL NOT COVER ANY MODIFICATION TO THE BUILDING TO CONTAIN DUSTS, CHEMICALS OR EXPLOSIVES											
	AUGER/SHREDDER		1 EACH	250000					250,000		\$250,000
	CONVEYOR SYSTEMS		2 EACH	65000					130,000		\$130,000
	MECHANICAL		1 LOT	25000	600	600	35	21,000	25,000		\$46,000
	ELECTRICAL		1 LOT	50000	800	800	35	28,000	50,000		\$78,000
	SUBTOTAL										504,000
ENGINEERING COSTS											
	DETAIL DRAWINGS										
	ENGINEERING COSTS		15 EACH		24	360	65	23,400			\$23,400
	DRAFTING COSTS		15 EACH	25	40	600	55	33,000	375		\$33,375
	PLAN DRAWINGS										
	ENGINEERING COSTS		5 EACH		40	200	65	13,000			\$13,000
	DRAFTING COSTS		5 EACH	25	80	400	55	22,000	125		\$22,125
	MEETINGS		1 LOT		80	80	65	5,200			\$5,200
	TRAVEL		1 LOT	3000	40	40	65	2,600	3,000		\$5,600
	SPECIFICATIONS (PROCUREMENT/CONSTRUCTION)		1 LOT	500	80	80	65	5,200	500		\$5,700
	Subtotal							\$104,400	\$4,000		\$108,400
											USE \$110,000
	SUBTOTAL OF ALL COSTS										

ESCALATION SHEET

Project or Description :
 Location : INEL
 Requested By :
 Date : 01/02/90
 Page : 1 of 1
 Prepare'd By : A. R. Millward
 Chk'd/appr'd By :

Fiscal Years	FY91	FY92	FY93	FY94	FY95	FY96	
Calendar Years	CY91	CY92	CY93	CY94	CY95	CY96	TOTAL
Escalated Months & Yearly Percentage	JFMAMJJASOND Months Yrs %	JFMAMJJASOND Months Yrs %	JFMAMJJASOND Months Yrs %	JFMAMJJASOND Months Yrs %	JFMAMJJASOND Months Yrs %	JFMAMJJASOND Months Yrs %	COM- POUNDED %
Title I, II							
Title III							
Labor							
Mat'l & Subcontracts							
Equipment							
Indirects							
PM							
CM							
FE							
Equipment	3.6	5.2	5.3	5.2	5.2	5.2	
Material	3.6	5.2	5.3	5.2	5.2	5.2	
Labor	4.0	5.0	5.6	5.6	5.6	5.6	
Indirects	4.2	5.0	5.4	5.4	5.4	5.4	
I. II	4.3	5.0	5.5	5.5	5.5	5.5	
III	4.3	5.0	5.5	5.5	5.5	5.5	
PM-CM-FE	4.3	5.0	5.5	5.5	5.5	5.5	
Composite	4.0	5.1	5.4	5.4	5.4	5.4	

Appendix D

Discussion of Calculation Methods

Discussion of Calculation Methods

The heat and material balances prepared for this study are based on both manual calculations and computer simulation. Determination of partitioning of species between the vapor and liquid phases in the main plasma chamber was based on the following assumptions:

- The liquid phase in the main chamber would be maintained at 2000°C and that this would result in a vapor phase temperature of 1000°C
- All hydrocarbon, chlorinated hydrocarbon, and metal species with a vapor pressure greater than one atmosphere at 2000°C would be in the vapor phase (this included lithium and mercury)
- All mineral and metal species with vapor pressure lower than one atmosphere at 2000°C would be in the liquid phase
- One mole of steam per mole of carbon atoms is added at the main plasma chamber to minimize carbon (soot) formation
- Air is used as the plasma gas
- No chemical reaction occurs between vapor and liquid species
- There is no entrainment of liquid or solid phases into the vapor phase.

Vapor phase chemical equilibrium at 1000°C and one atmosphere was calculated for the vapor species determined as described above using the NASA Lewis chemical equilibrium computer program, CEC76. This program determines chemical equilibrium based on a free-energy minimization technique when two thermodynamic states are defined. The program is described in detail in NASA document SP-273, *Computer Program for Calculation of Complex Chemical Equilibrium Compositions, Rocket Performance, Incident and Reflected Shocks, and Chapman-Jouguet Detonations*.¹⁴

An overall heat balance was calculated manually for the main plasma chamber. The heat of the pyrolysis reactions were determined from heats of formation(s) found in *Perry's Chemical Engineers' Handbook*⁹ and in the *CRC Handbook of Chemistry and Physics*.¹⁰ Sensible heat of the effluent vapor and liquid were determined from molar average heat capacity of each stream. Heat capacity for each molecular species as a function of temperature were found in the same references. The power input of the torch was determined from the heat balance based on the assumptions given above.

The plasma off-gas is then assumed to be heated to approximately 1370°C in a plasma torch-heated afterburner to ensure destruction of hazardous organic species in the off-gas. The afterburner temperature of 1370°C was selected as the highest practical temperature for which conventional refractories would be suitable. The CEC76 program was also used to determine the equilibrium composition of the afterburner off-gas. A heat balance was calculated for the afterburner in the same manner as the main chamber to determine the power input of the afterburner plasma torch.

An off-gas treatment system model previously developed for simulating in situ vitrification off-gas treatment was used to simulate the off-gas treatment material and energy balances for this study. This model was developed using ASPEN/SP, a commercial chemical process simulator available from Simulation Sciences Inc. The off-gas treatment unit operations simulated with ASPEN/SP included heat exchange, absorption, compression, mixing, and vapor/liquid flashing. ASPEN/SP has capability to use several equations of state to determine thermodynamic properties and vapor/liquid equilibrium. The Redlich-Kwong equation of state was used for the simulations performed for this study. Absorption of acid gases in the quench tower and scrubber, i.e., hydrochloric acid, were simulated using a Henry's Law model.

The treated effluent from the off-gas treatment will contain carbon monoxide which must be oxidized to carbon dioxide prior to being vented to the atmosphere. The heat balance and effluent composition of the off-gas incinerator were determined using the NASA CEC76 program described above.

END

**DATE
FILMED
6 10 8 192**