MARTIN MARIETTA

ORNL/ER-23

**ENVIRONMENTAL
RESTORATION
PROGRAM**

**Tracer-Level Radioactive Pilot-Scale
Test of In Situ Vitrification
Technology for the Stabilization of
Contaminated Soil Sites at ORNL**

G. K. Jacobs
B. P. Spalding

MANAGED BY
MARTIN MARIETTA ENERGY SYSTEMS, INC.
FOR THE UNITED STATES
DEPARTMENT OF ENERGY

UCN-17560 (6 7-91)

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

ENERGY SYSTEMS

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from 615-576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

Environmental Restoration Division
ORNL Environmental Restoration Program

Tracer-Level Radioactive Pilot-Scale Test of In Situ Vitrification Technology for the Stabilization of Contaminated Soil Sites at ORNL

G. K. Jacobs
B. P. Spalding

Manuscript Completed—June 1990
Date Issued—November 1991

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Prepared by
Environmental Sciences Division
Oak Ridge National Laboratory
ESD Publication 3806

Prepared for
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
under budget and reporting code EW 20

OAK RIDGE NATIONAL LABORATORY
Oak Ridge, Tennessee 37831-6285
managed by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U.S. DEPARTMENT OF ENERGY
under contract DE-AC05-84OR21400

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Author Affiliations

G. K. Jacobs and B. P. Spalding are members of the Environmental Sciences Division, Oak Ridge National Laboratory, Martin Marietta Energy Systems, Inc.

CONTENTS

EXECUTIVE SUMMARY	iv
BACKGROUND	1
OBJECTIVES	2
DESCRIPTION OF THE WORK	4
SITE SELECTION, CHARACTERIZATION, AND PREPARATION	4
TEST ACTIVITIES	5
POSTTEST ACTIVITIES	5
QUALITY ASSURANCE	7
TRAINING	8
DOCUMENTS AND PROCEDURES	9
SAFETY AND HEALTH: RISK ASSESSMENT/CONTINGENCY PLAN	10
REFERENCES	11

EXECUTIVE SUMMARY

This plan summarizes the activities to be performed during FY 1990 and FY 1991 for the tracer-level radioactive pilot-scale in situ vitrification (ISV) test. This test is the second step in evaluating ISV as a remedial action for the pits and trenches at Oak Ridge National Laboratory (ORNL). A previous test used nonradioactive tracers for cesium and strontium. This new test will again use a one-half-scale model of trench 7 and the pilot-scale ISV equipment of Pacific Northwest Laboratory (PNL). A small and precisely known amount of waste from a liquid waste disposal pit will be used for the test. An actually contaminated waste site cannot be used for this test because of the necessity to use an exactly known inventory of radionuclides so that a precise measurement of the volatilization of various constituents to the off-gas can be determined.

The test's four major objectives are these:

1. Demonstrate a reduction in ^{137}Cs accumulation in the off-gas processing trailer
2. Assess the radiological and operational performance factors associated with applying ISV to a radioactive site
3. Confirm the durability of an ISV waste form containing radioactive components
4. Evaluate seismic imaging and advanced thermometric methods for monitoring the progression of melting

PNL will deliver and operate its pilot-scale ISV equipment during the fall of 1990. ORNL will prepare the site and ready existing equipment (off-gas hood and electrodes) for PNL use. ORNL will sample and characterize waste from an available core from a liquid waste disposal pit and determine the chemical and radiological composition. On the basis of this information, the minimum amount of this waste (between 2 and 25 g) necessary to track the behavior of key radionuclides through the ISV system will be placed into the test trench. Samples of off-gas scrub solutions will be obtained during the test for analyses at ORNL. After the ISV mass solidifies and cools, samples will be collected and analyzed for their leachability and their chemical, radiological, and mineralogical composition.

BACKGROUND

In situ vitrification (ISV), developed and patented for the Department of Energy (DOE) by Pacific Northwest Laboratories (PNL), is one technology being considered for remedial action of contaminated sites at the Oak Ridge National Laboratory (ORNL). Specifically, evaluations of ISV have been conducted for its applicability to seven pits and trenches containing high levels of radioactivity. Jacobs et al. (1988) provide a description of the previous pilot-scale application at ORNL. Based on the results from a cold (no radioactivity) pilot-scale test of ISV (Spalding and Jacobs 1989), a recommendation was made to proceed to a tracer-level radioactive test at the pilot scale.

OBJECTIVES

1. Demonstrate Reduction in ^{137}Cs Accumulation in the Off-Gas Processing Trailer

The retention of cesium in the ISV material during the 1987 pilot-scale test was encouraging at a value of 99.88%. During application to an actual pit or trench, however, this factor could result in significant radiological hazard to personnel. Therefore, several engineered methods will be evaluated for their potential to minimize the accumulation of ^{137}Cs in the off-gas trailer during the tracer-level radioactive pilot-scale test. The methods to be evaluated include (1) real-time monitoring of the ^{137}Cs release using radiation monitors in the ISV off-gas processing system, with feedback to limit power input to the melt to induce cold-cap formation and to lower melt operating temperature; (2) direct monitoring of melt temperatures with feedback to power input to the melt; and (3) reducing ^{137}Cs accumulation in the off-gas trailer by inserting a high-efficiency particulate air filter on the off-gas hood during the interval of the run when the melted mass approaches the depth where the ^{137}Cs was placed or by incorporating a cesium-selective filter system within the off-gas system but external to the trailer.

2. Assess Radiological and Operational Activities of the ISV System

The tracer-level, pilot-scale ISV test will contain trace levels of actual waste so that all activities required during an application of ISV to a contaminated site can be performed and evaluated. Several operational problems occurred during the cold test, including breakup of the starter path, spurious radiation alarms, and malfunctions of the power delivery system. These problems, which are not significant for a cold test, are of great concern during the application of ISV to a site containing radioactivity. For the cold test, electrodes were placed in predrilled auger holes. For a contaminated site, it is advantageous to avoid drilling into contaminated zones. Therefore, during the tracer-level test, an automatic electrode feeding system that lowers the electrodes as melting proceeds will be used.

3. Confirm Durability of ISV Waste Form

All previous waste forms produced during ISV tests are extremely resistant to leaching with respect to short-lived radionuclides (e.g., half lives < 100 years). The presence of radionuclides and other sludge components likely to be encountered in the pits and trenches at ORNL is not anticipated to degrade this durability. However, leach tests will be performed on the resulting waste form to confirm these assumptions. In addition, a sample of actual waste from one of the pits will be analyzed and its leachability determined so that a direct comparison of the improved performance of the waste form can be made.

4. Evaluate Seismic Imaging and Advanced Thermometry for Monitoring Melt Progress

Direct monitoring of melt temperatures during field-scale applications of ISV has never been accomplished. To provide direct feedback to power input levels so that minimum melt temperatures (thus, minimum volatility of ^{137}Cs) can be maintained, direct monitoring is highly desirable. At the anticipated temperature of the melt (1300–2000°C), thermocouples tend to lose their calibration quickly. Optical thermometric methods are not susceptible to this problem. Therefore, in addition to thermocouples, optical pyrometers will be used.

For cold pilot-scale tests, the depth of melting can be established by using thermocouples placed into the test trench in a vertical array during its construction. Obviously, during application to an actual waste site, this method is not feasible because of the contamination present. Estimates of depth are usually based on computer models of energy input and the system's thermal properties. However, as was shown for ORNL sites during the cold pilot-scale test, the soil's heterogeneous nature makes this model somewhat inaccurate. Therefore, nondestructive geophysical monitoring using seismic imaging methods will be tested in order to identify the progression of melting. Seismic images will be obtained before, during, and after the melting and should be able to resolve the spatial configuration of the melt relative to the surrounding soil. On the basis of existing information, it is anticipated that the resolution of the seismic imaging will be on the order of 0.25 to 0.5 m, sufficient to see details within the vitrification zone.

DESCRIPTION OF THE WORK

The first phase of the work is to complete several tasks at PNL. First, a study of the effect of sodium additions to mixtures of soil and limestone on melt viscosity and electrical conductivity has recently been completed. Second, an engineering-scale test was conducted to examine (1) the effects of the addition of sodium and/or subsurface initiation of melting and (2) several advanced thermometry techniques. Third, an analysis of acceptable inventories of ^{137}Cs in the PNL off-gas processing trailer is being performed. The results of this calculation, combined with the analysis of some waste from an ORNL pit, will provide the basis for selecting an amount of waste to be placed into the pilot-scale test trench. The amount will probably be between 1 and 10 mCi of ^{137}Cs , which is equivalent to between 2 and 25 g of sludge from pit 2 or 3.

SITE SELECTION, CHARACTERIZATION, AND PREPARATION

The trench for the pilot-scale test will be about one-half the actual size of liquid low-level waste disposal trench 7. The trench will be located within Waste Area Grouping (WAG) 6, at a site to be chosen for its similarity in topographical, geological, and hydrological features to trench 7. WAG 6 was selected as an existing solid waste management unit for this test. Because WAG 6 is the approved disposal site for radioactive solid waste at ORNL, the radioactively contaminated glass block resulting from this test can be considered disposed of in place. The core and sludge samples taken by Lomenick et al. (1967) to be used in this test are currently stored in area 7811, west of WAG 4. These samples would be disposed of ultimately in a silo or tumulus in WAG 6 anyway. The trench will be filled with crushed limestone similar to that used for the cold test. Several thermocouple and optical thermometry devices will be placed in and around the trench to monitor the temperatures during and after the test.

Pretest characterization of the site includes measurements of soil moisture, bulk density, and a survey for unexpected contamination at the site. Geologic information will be collected on the host soil formation, especially stratigraphic and structural features, since these may provide avenues for off-gas and water movement from the trench. Cold test results indicated that no transport occurred in these features, but the characterization will be conducted to determine that no unique features are present at this new site. A seismic survey will also be done to provide background information for the imaging to be conducted during the test. The soil and crushed limestone will be analyzed for their mineralogical and chemical compositions.

During trench construction, a small amount of actual waste sealed in plastic bottles will be placed at the bottom of the crushed limestone layer. The amount to be added will be determined during early FY 1991. This determination will be based on several factors. First, PNL will calculate the maximum amount of ^{137}Cs that can be accommodated within the off-gas processing trailer. ORNL will collect and analyze a waste sample to determine both the chemical and radiological composition. Residual core material from the pits 2 and 3 characterization study of Lomenick et al. (1967) will be used as the source of waste. The concentration of ^{137}Cs and ^{90}Sr in the sludge samples ranges up to a maximum of 415 and 32 mCi/kg, respectively. It is anticipated that between 1 and 10 mCi of ^{137}Cs will be employed in the test, which would be equivalent to between 2.4 and 24 g of sludge at the highest

activity in the range of samples. The waste sludge is a mixture of calcium carbonate and illitic clay containing mostly ^{137}Cs and ^{90}Sr . Other radionuclides that may be present in small amounts may include ^{60}Co , uranium isotopes, and transuranic elements. It is not anticipated that the waste will contain hazardous materials, although the waste sample will be analyzed for total quantities of hazardous constituents as well as for the leachability of the hazardous metals (Extraction Procedure Toxicity Test). Considering that 25 g of the sludge will be incorporated homogeneously into ~20,000 kg of glass, the concentration of any hazardous component would be diluted approximately a millionfold.

TEST ACTIVITIES

During the planned ISV test, extensive thermal data will be collected on the spatial and temporal progress of the melt and its effects on the surrounding area. Thermal monitoring devices (thermocouple and optical sensors) will be placed within and around the trench and monitored continuously during the test.

Samples of off-gas scrub solutions will be collected every 2 h during the operation of the ISV pilot-scale system. Selective duplicate samples will be collected so that analyses can be conducted at PNL to provide a check on ORNL's results.

Seismic surveys of the site will be conducted several times (frequency to be determined) during the ISV operation. The source will be a "Betsy" seisgun (8-gauge shotgun) that delivers a lead slug into shallow, sand-lined holes in the soil that will allow for the complete removal of the lead. Geophones will be placed on the surface around the ISV hood, and vertical arrays of hydrophones will be placed in six boreholes (three on each side of the ISV hood).

POSTTEST ACTIVITIES

At the end of the ISV melting, the equipment will be shut down, dismantled, decontaminated, and prepared for shipment back to PNL. Details of these activities will be included in the ISV Test Plan. Wastes from the scrub solutions will be temporarily stored in appropriate containers and then treated at ORNL for disposal.

Thermal monitoring of the ISV mass will continue for several months to determine when the mass will be cool enough for core sampling. Several seismic surveys will be conducted to confirm the final spatial configuration of the mass and to attempt to identify the zone of crystallization that is anticipated based on the devitrification behavior from the previous test.

When the mass has cooled to near-ambient temperature (estimated time of 2 to 3 months), the site will be characterized for the degree of subsidence that occurred as a result of melting. Core samples will be obtained then also. Based on the degree of core recovery and the physical nature of the samples, a determination whether to partially excavate the mass will be made.

Off-gas scrub samples will be analyzed at ORNL (selective duplicates at PNL) for their chemical and radiological composition. This information, combined with the known quantities put into the trench, and chemical analyses of core samples will allow a determination of soil-to-off-gas retention factors. During the cold test, 99.88% of the cesium was contained within the ISV mass. It is anticipated that with the special attention to volatilization processes, this value can be greatly increased. The 0.12% of the cesium inventory, which was released to the process off-gas, was completely contained within the off-gas scrubbing and filtration system. No atmospheric releases of cesium were detected. No atmospheric releases of radioactivity will result from the off-gas processing system during this radioactive test.

Core samples will be analyzed for their chemical, radiological, and mineralogical composition. This information is necessary for the determination of retention factors for the radionuclides and as supporting information for interpreting leach tests. Samples of the ISV mass will be tested for their durability using such leach tests as Materials Characterization Center tests, the Environmental Protection Agency Toxicity Characteristic Leaching Procedure, and other standard geochemical tests.

QUALITY ASSURANCE

The work identified under this task plan will be performed in compliance with the applicable procedures of the ORNL Quality Assurance (QA) Manual that implements the QA requirements of DOE Order 5700.6. PNL will adhere to its own organizational QA procedures consistent with the same DOE order. A QA Plan has been completed and approved.

TRAINING

Staff involved in the ISV test need special training. PNL will provide trained operators of the pilot-scale ISV system. ORNL staff participating in the ISV test and the seismic surveys require instruction in the following areas:

- Use of respirators
- General radiation training
- OSHA hazardous waste training (40 h)

Prior to the start of the actual test, all workers will receive training for their specific tasks and be familiar with the overall working of the ISV equipment. An Operational Readiness Review will also be conducted prior to the start of the tests to ensure that all health, safety, and environmental concerns have been addressed.

DOCUMENTS AND PROCEDURES

Detailed procedures for the actual operation of the pilot-scale ISV system already exist. PNL has successfully completed many (>15) such pilot-scale tests. Existing PNL procedures, modified as necessary, will be used for this test. Details of these procedures will be included in the Run Plan and the Operational Readiness Plan.

Documents that are required for the test are listed and briefly explained below:

- Project Safety Summary: a general description of the activities to be completed and potential safety concerns; a high-level document that references to more detailed reports (e.g., Operational Readiness Plan, Test Plan) rather than contains all details
- QA Plan: a description of the QA procedures that apply to this project
- Waste Management Plan: a rundown of the storage and disposal procedures for anticipated wastes
- Test Plan: details of the activities that will be performed before, during, and after the ISV test; descriptions of the equipment to be used, anticipated results, and interfaces among ORNL and PNL staff
- Operational Readiness Plan: a detailed plan that addresses health, safety, and environmental concerns during the ISV test and contains a checklist to be used during the Operational Readiness Review and safety procedures to be followed during the test
- Run Plan: detailed procedures to be used during the operation of the PNL pilot-scale ISV system

SAFETY AND HEALTH: RISK ASSESSMENT/CONTINGENCY PLAN

Full details of safety and health procedures will be contained in the Project Safety Summary, Operational Readiness Plan, and Run Plan. The two main concerns are (1) release of and exposure to radiation from off-gases and (2) contact with high-voltage electricity. Risks will be minimized through the use of approved procedures, training of all personnel, and the use of backups for essential equipment.

Under normal operating conditions, all off-gases are contained within the off-gas trailer of the pilot-scale system. Although each trailer module is doubly contained, radiation monitors within the trailer will continuously check the air. If power should be lost to the system, an on-site backup generator is available. Should some unexpected event occur without an accompanying loss of power, power to the electrodes would be immediately shut down so that the release of off-gases would cease; the generator would allow the off-gas system to continue to operate effectively.

The test area will be marked as a controlled zone to prevent danger from contact with the high-voltage and thermally hot equipment. (It will also be a radiation control zone.) Such special equipment as electrically insulated boots and gloves will be required anytime personnel are within the controlled zone.

Although an uncontrolled release of radiation vent beyond the containment hoods is unlikely, plans are in place to deal with such a scenario. Radiation monitors will be placed around the equipment and the controlled zone. Personnel working within the radiation control zone may be required to wear respirators so they will be protected against unanticipated releases. Respirators will also be available within the processing trailer, although this zone will be continuously monitored for radiation also. At the first sign of unexpected releases, power to the electrodes would be discontinued, and the greatly reduced volume of resulting off-gases would continue to be processed.

REFERENCES

- Jacobs, G. K., Spalding, B. P., Carter, J. G., and Koegler, S. G. 1988. "In Situ Vitrification Demonstration for the Stabilization of Buried Wastes at the Oak Ridge National Laboratory," *Nucl. Chem. Waste Manage.* 8, 249.
- Lomenick, T. F., Jacobs, D. G., and Struxness, E. G. 1967. "The Behavior of Strontium-90 and Cesium-137 in Seepage Pits at ORNL," *Health Phys.* 13, 897.
- Spalding, B. P., and Jacobs, G. K. 1989. *Evaluation of an In Situ Vitrification Field Demonstration of a Simulated Radioactive Liquid Waste Disposal Trench*, Martin Marietta Energy Systems, Inc., ORNL/TM-10992, Oak Ridge Natl. Lab., Oak Ridge, Tenn.

DISTRIBUTION

1. L. V. Asplund/N. W. Durfee	21. G. E. Rymer
2. L. D. Bates	22. P. A. Schrandt
3. K. W. Cook	23. D. S. Shriner
4. J. H. Cushman	24-28. B. P. Spalding
5. M. P. Farrell	29. S. H. Stow
6. D. E. Fowler	30. D. W. Swindle
7. S. B. Garland II	31. R. I. Van Hook
8. C. W. Gehrs	32-36. ER Document Management Center
9. C. D. Goins	37. Central Research Library
10. J. A. Greene	38-42. ESD Library
11. S. G. Hildebrand	43. ORNL Y-12 Technical Library
12. L. D. Hyde	44. Laboratory Records Dept.
13-17. G. K. Jacobs	45. Laboratory Records, ORNL-RC
18-19. P. T. Owen	46. ORNL Patent Section
20. D. E. Reichle	
47. Office of Assistant Manager for Energy Research and Development, DOE Field Office, Oak Ridge, P.O. Box 2001, Oak Ridge, TN 37831-8500	
48. P. H. Edmonds, Radian Corporation, 120 South Jefferson Circle, Oak Ridge, TN 37830	
49. J. F. Franklin, Bloedel Professor of Ecosystem Analysis, College of Forest Resources, University of Washington, Anderson Hall (AR-10), Seattle, WA 98195	
50. G. M. Hornberger, Professor, Department of Environmental Sciences, University of Virginia, Charlottesville, VA 22903	
51. G. Y. Jordy, Director, Office of Program Analysis, Office of Energy Research, ER-30, G-226, U.S. Department of Energy, Washington, DC 20545	
52-55. W. E. Murphie, Department of Energy, Office of Environmental Restoration, Eastern Area D&D Branch, EM-423 (GTN), Washington, DC 20545	
56. R. H. Olsen, Vice President for Research, University of Michigan, 6643 Medical Science Building II, Ann Arbor, MI 48109-0620	
57. A. Patrinos, Acting Director, Environmental Sciences Division, Office of Health and Environmental Research, ER-74, U.S. Department of Energy, Washington, DC 20585	
58-59. S. S. Perkins, DOE Field Office, Oak Ridge, Information Resource Center, 105 Broadway, Oak Ridge, TN 37830	
60-61. S. P. Riddle, DOE Field Office, Oak Ridge, P.O. Box 2001, Oak Ridge, TN 37831-8541	
62-63. R. C. Sleeman, DOE Field Office, Oak Ridge, P.O. Box 2001, Oak Ridge, TN 37831-8541	
64. F. J. Wobber, Environmental Sciences Division, Office of Health and Environmental Research, Office of Energy Research, ER-74, U.S. Department of Energy, Washington, DC 20584	
65-66. Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831	

END

DATE
FILMED

6/11/92