225
3/17/80

DR. 865

DOE/ET/12057-5
(SAN/1189-5)

**BODCAU IN SITU COMBUSTION PROJECT
COMBUSTION TUBE TESTS**

Topical Report of January 1979

MASTER

Date Published—February 1980

Work Performed for the Department of Energy
Under Contract DE-AC03-76 ET12057
(formerly EY-76-C-03-1189)

Cities Service Company
Tulsa, Oklahoma

U. S. DEPARTMENT OF ENERGY

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

NOTICE

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States nor any agency thereof, nor any of their employees, makes any warranty, expressed or implied, or assumes any legal liability or responsibility for any third party's use or the results of such use of any information, apparatus, product or process disclosed in this report, or represents that its use by such third party would not infringe privately owned rights.

Printed in the United States of America
Available from
National Technical Information Service
U.S. Department of Commerce
5285 Port Royal Road
Springfield, VA 22161

NTIS price codes

Printed copy: \$7.25

Microfiche copy: \$3.00

10.5
5.0

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

**BODCAU IN SITU COMBUSTION PROJECT
COMBUSTION TUBE TESTS**

**Topical Report
January 1979**

By

W. H. Pusch

John W. Haggard
Principal Investigator
Cities Service Company
Tulsa, Oklahoma

Alan J. Leighton
Technical Project Officer
Fossil Energy Division
San Francisco Operations Office
Oakland, California

Work Performed for the Department of Energy
Under Contract DE-AC03-76ET12057
(formerly EY-76-C-03-1189)

Date Published—February 1980

U.S. DEPARTMENT OF ENERGY

DISCLAIMER
This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof nor any of their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

TABLE OF CONTENTS

	<u>PAGE</u>
LIST OF TABLES	iii
LIST OF FIGURES.	iv
SUMMARY.	1
INTRODUCTION	2
THEORY	6
PROCEDURE.	8
Combustion Tube Tests	8
Ignition Tests.	9
RESULTS.	11
Combustion Tube Tests	11
Ignition Tests.	12
DISCUSSION	13
Heat Losses	13
Alteration of Mineral Composition	14
Fluid Properties.	15
Simultaneous Water/Air Injection.	17
APPENDIX A	19
Tables.	19
Figures	27
APPENDIX B	29
Data.	29

LIST OF TABLES

<u>TABLE</u>		<u>PAGE</u>
1	Summary of Results	19
2	Ignition Test Results.	22
3	Semiquantitative X-Ray Diffraction Analysis of Core Material	23
4	Combustion Tube Oil Analyses	24
5	Oil Chromatographic Analyses	25
6	Produced Gas Analyses.	26

LIST OF FIGURES

<u>FIGURE</u>		<u>PAGE</u>
1	Schematic of the In-Situ Combustion Process	27
2	Schematic of Laboratory Combustion Tube	28

SUMMARY

A series of combustion tube tests were performed at the Cities Service Research Laboratory using Bellevue core samples and produced oil. The objectives of the study were to obtain information concerning the basic in-situ combustion process that would aid in understanding the performance of the Bellevue fireflood. Also investigated was the interaction of water with the burning process in order to determine the water/air injection ratio that should be used in field operations. Finally, the formation ignition temperature of the rock-oil system was approximated by means of laboratory oxidation tests.

The following conclusions were determined from the laboratory combustion tests:

1. Fuel deposit and air requirement of dry combustion were calculated by means of combustion tube tests to be 2 #/f³ and 17 MMSCF/A-f.
2. Injecting water increases the efficiency of the burning process by decreasing fuel deposit and air requirement.
3. Water rates as high as 500 B/MMSCF do not extinguish the combustion reaction in the laboratory system.
4. The ignition temperature of the Nacatoch formation is approximately 500°F.

INTRODUCTION

In 1971, Cities Service initiated a field test of the in-situ combustion process on the Bodcau Fee Lease in the Bellevue Field, Bossier Parish, Louisiana. This first test was similar to other firefloods using industry's early technology. Air was injected to burn a predetermined volume of the reservoir and then water was injected to utilize residual heat and increase overall oil recovery. This original test is still in the waterflood stage and it appears that 30-40 percent of the oil in place will be recovered. Utilizing information obtained from the original pilot and some laboratory tests, another field test was initiated using a new improved design. The second test applying simultaneous water/air injection indicated a greatly improved burning front profile and more rapid heat movement. The rapid advancement of the heat front reduced operating costs and improved project economics.

The current Cities Service-DOE project area uses the simultaneous water/air injection technique in all five patterns. Besides the handling of operational problems unique to fireflooding, project objectives include the determination of optimum water/air injection rates and optimum pattern volume that should be burned. Laboratory combustion tube tests were set up to investigate the interaction of water with the burning process and rates that may be used confidently in the field to improve both oil recovery and project economics.

Because of the highly complex nature of fireflooding, very few techniques are available for predicting behavior expected during field

application. Combustion tube tests have been successfully utilized to obtain approximations for the amount of oil that will be burned and the air required to sustain combustion. These variables, fuel deposit and air requirement, are controlled by the basic oxidation reactions and are not dependent on the configuration of the testing apparatus. As long as the porous medium and crude accurately represent those found in the reservoir, the chemical processes will be the same. Flow rates and fluid saturations will affect burning behavior, but the stoichiometry of the reaction is controlled by the temperature, pressure and characteristics of the reactants. Therefore, combustion tube tests have been accepted as a method of producing reliable data describing the in-situ combustion process.

On the other hand, combustion tube studies have little value in predicting bulk fluid movement. A primary consideration of any recovery process involving fluid injection is sweep efficiency. Although many theoretical models have been proposed to predict the mobility and movements of fluids within a reservoir, none have been completely successful in fire-flooding. Due to the extreme temperature gradients, constant changing of fluid phases and reaction kinetics, a rigorous prediction of flow properties has yet to be developed. Extrapolation of flow behavior in laboratory models to that in the field is unrealistic. Physical configuration vastly affects experimental simulations and prohibits scale up to reservoir conditions. Experience from field tests remains the best source of information for volumetric efficiencies.

Since one of the objectives of this study was to observe the effect of water injection on the combustion process, it must be resolved how indicative results of combustion tube tests are of field behavior. Three factors are associated with simultaneous air-water injection. The first is multi-

phase flow through the porous media. Questions concerning how the air and water will distribute within the burned zone and what conditions will exist when they reach the combustion front are not within the scope of laboratory tests. As mentioned previously, combustion tube tests contribute little toward predicting fluid movement and sweep efficiencies within the reservoir. Gravity segregation is an important consideration and its effect is eliminated by performing tests with the tube in the vertical position. Although the ratio of water and air are known at the injection well, their distributions while flowing through the reservoir and contacting the burning front are unknown and cannot be determined from laboratory studies.

The second factor associated with simultaneous air-water injection is heat transfer, the primary reason for injecting water. Although the heat losses from the combustion tube are considerably different from those of the reservoir, a direct analogy exists between the two systems. The reservoir is naturally insulated by overburden and underburden and heat losses are relatively small compared to the amount of heat generated. The laboratory tube has high heat losses due to its metal construction and limited amount of heat generated. To decrease heat losses and sustain a combustion front, strip heaters were placed around the tube. These heaters maintain an escalated isothermal condition which reduces the temperature gradient with tube surroundings and lowers heat losses. The heaters simply increase the overall energy level of the system, not interfering with process mechanisms. The heat transfer properties of the water and the subsequent temperature profiles are not distorted by the presence of the heating system. The flow of heat through the packed tube does represent what will happen in the reservoir with certain exceptions.

The entire concept of injecting water during fireflooding is to improve heat utilization. Likewise, interpreting the data for wet combustion is completely dependent on the heat transfer characteristics of the combustion tube. If heat losses from the tube are excessive and the combustion process is barely sustaining itself, little advantage is realized by scavenging heat behind the firefront. Injected water has a cooling effect on the combustion zone, lowering its temperature and possibly quenching the process. Conversely, if high temperatures are maintained by the strip heaters (insulating system), sufficient heat is available behind the firefront to vaporize all the water injected. In this case, the energy level in the combustion zone is insignificantly decreased by water and high burning temperatures exist. Large quantities of water passing through the combustion zone as steam have no adverse effect on the combustion reaction. Actual conditions in the reservoir will be somewhere between the two extremes. The conditions maintained on the combustion tube are believed to be representative of those that will prevail in the field. However, extrapolating water-air ratios from laboratory studies to field conditions might be misleading.

The final consideration for air-water injection is if large quantities of water passing through the combustion zone will affect burning efficiency. As previously discussed, combustion tube tests accurately represent the reaction mechanisms. Therefore, laboratory results will satisfactorily predict combustion zone behavior.

THEORY

The in-situ combustion process has been established as a viable oil recovery technique with both laboratory studies and field tests having been reported extensively in the literature. The exploitation of the process has been limited somewhat due to operational problems and costs associated with its application. Also, the complex nature of the process has created problems for accurately predicting reservoir performance using mathematical models. Figure 1 shows a schematic of the different zones present in the fireflood process. The combustion zone or firefront is the small zone where the oxidation of coke generates the large quantities of heat. The coke is the residue left behind by the reservoir crude after it has been vaporized and cracked by the high temperatures. The movement of the firefront and the distribution of the generated heat are factors which control oil displacement, ultimate recovery and successful application within a specific reservoir. These factors are not determined from laboratory tests and have to be obtained by field testing.

The oxidation reactions of the hydrocarbons have been accurately described by laboratory studies. Combustion tube tests are useful in determining amount of fuel deposition and air requirement. The fuel deposit which is controlled by rock properties, oil characteristics, temperature and pressure, is a measure of the amount of oil or coke consumed by oxidation. The air requirement is the amount of air required to consume the fuel deposited in one cubic foot of rock. These two variables are necessary in

the design or evaluation of a fireflood project because they are used to calculate burn volumes, oil displacement and compressor requirements.

There are many chemical reactions that occur during underground combustion. These include low temperature oxidation of oil, thermal cracking or pyrolysis and high temperature oxidation which is the primary reaction of interest. For analysis of combustion tube experiments the following stoichiometric equation is used to represent the process:

The data measured from a combustion tube test include composition and volume of produced gas. Knowing the composition of the injected gas (air), the chemical equation can be balanced to yield the quantity of hydrocarbons consumed and the amount of oxygen reacted. Other parameters that can be measured or calculated with combustion tube data are combustion temperature, oxygen utilization, air-oil ratio, oil produced and combustion zone velocity.

The injection of water together with the air results in a process known as wet combustion. The water acts as an efficient heat transfer media, recuperating the heat stored in the burned sand. The water moves through the burn front as steam and improves the heat flow characteristics of the process. Laboratory and field tests have reported that in addition to improved heat transfer, simultaneous air-water injection results in reduced fuel deposition and reduced air requirements. Thus, wet combustion decreases compressor requirements or project life and increases oil displacement.

TEST PROCEDURE

Combustion Tube Tests

A schematic of the combustion tube used in the study is shown in Figure 2. A mixture of sand, oil and water are packed in the 2.5" diameter stainless steel tube. A 0.25" diameter thermowell traverses the center of the sand pack enabling temperature measurements along the 73" length of the tube. Four 1250 watt strip heaters are strapped to the outside of the stainless steel tube and are controlled by an automatic power unit. The entire tube assembly is placed within an insulated 6" diameter steel jacket. Tests have been performed with the system in the vertical position. Air and water are injected at the top and production is taken off the bottom. The products pass through a water-cooled separator which condenses water vapor and hydrocarbons and maintains the gas at a constant temperature. Liquids are drained from the separator while gases pass through a wet test meter, sampling valve and are then vented to the atmosphere.

A run is performed by first packing the tube with either the unconsolidated, native Bellevue core or a mixture of burned Bellevue sand and produced oil and water. A portion of the mixture is sampled for oil and water determinations. The weight of mixture packed into the tube and the results from the fluid saturation measurements allow calculation of the porosity and volumetric saturations of each fluid phase. Nitrogen is flowed at 0.2 SCF/Min through the tube to establish a gas permeability and produce mobile fluids. The strip heaters are then activated raising the temperature of the system to the desired temperature. To initiate combustion, a heater

at the inlet face increases the sand pack to over 500°F. Nitrogen injection is replaced with air and ignition is usually observed immediately. The three thermocouples in the thermowell and the thermocouple attached to the ignition heater record significant increases in temperature upon ignition. Confirmation is also obtained with effluent gas compositions.

Data recorded during the run include air and water injection rates, injection pressure, produced oil, produced water and combustion gas volume. The gases produced are sampled and analyzed for oxygen, carbon dioxide and carbon monoxide using both an Orsat apparatus and a gas chromatograph. Oxygen is also monitored continuously with an oxygen analyzer. Thermocouples within the thermowell track the shape and movement of the combustion zone. Air flow rate is controlled using a rotometer and exit gases are monitored with a wet test meter. During simultaneous water/air injection the water rate is measured with a constant rate pump.

The air flow rate used in all runs was 0.2 SCF/Min or 435 SCF/f²-HR. The high air flux helped to reduce heat losses and decreased run time. The exit of the tube is vented to the atmosphere and no backpressure is held on the system. Therefore, the effective pressure at the combustion zone is controlled by the pressure drop through the sand pack which was quite low. The low pressure results in a low steam temperature and often the failure of a stabilized steam zone to form ahead of the front.

Ignition Tests

A series of small scale tests were performed to determine the ignition temperature of the formation. A small tube was packed with native Bellevue sand and placed in an oven. As air was flowed through the sample at different temperatures, the oxygen concentration of the effluent varied.

By correlating the concentration of oxygen with temperature, the ignition temperature of the crude could be predicted.

RESULTS

Combustion Tube Tests

The results of the combustion tube runs are summarized in Table 1. The parameters of primary interest, fuel deposit and air requirement, were determined to be 2 lb/f³ and 17 MMSCF/Ac-f for dry combustion. Increasing water/air ratios had a desirable effect on the process by decreasing both of the parameters. Fuel deposits of 1.5 lb/f³ and air requirements of 12 MMSCF were observed as the water rate was increased to 500 B/MMSCF. Water rates in excess of 500 B/MMSCF resulted in quenching of the combustion zone and difficulties in controlling laboratory test conditions.

Although the improved burning characteristics (reduced fuel deposit and air requirement) resulting from water injection are important in selecting the water/air ratio for field operations, the most important factor is the heat transfer properties of the entire system. The greatest heat transfer would occur at the highest water/air ratio in which no quenching was taking place. Therefore, the objective of the laboratory tests is to determine the maximum water rate without quenching. However, the selection of the optimum water/air ratio for the field requires a scale-up of laboratory conditions to those in the reservoir. Factors such as tube heat losses, formation heat losses, fluid flow behavior, heat transfer properties, sweep efficiencies and gravity segregation must be considered. These factors will allow a comparison of laboratory and field water rates. At this time it is thought that because of lower heat losses in the field, design water rates will be higher than equivalent laboratory rates. As the time elapses between

ignition and water injection, the burned volume increases and the effective water/air ratio in the field will be lower than that actually injected. Therefore, water should be started as soon as a stable combustion front has been established.

Ignition Tests

The small scale test to determine ignition temperature showed that oxidation became appreciable at 300°F. As the temperature of the sand pack was increased, the concentration of oxygen in the produced gas became lower. Finally, at 500°F all of the oxygen in the injected air was reacted indicating that the ignition temperature of the Bellevue field is less than 500°F. Table 2 presents a summary of the produced oxygen concentration versus the sand pack temperature for the experimental runs.

DISCUSSION

Heat Losses

The operational plan for the combustion tube was to use a high air flux and insulation to minimize the effect of heat loss. However, it was found that the heat capacity of the equipment and excessive heat losses created undesirable temperature gradients across the packed bed. Strip heaters were added to increase the overall heat level of the tube and its surroundings. There was no attempt to simulate adiabatic conditions. Strip heaters were controlled to maintain a minimum sand pack temperature which could be set by the operator. Temperatures of 200-300°F were used in this study because it was found that the rate of oxidation below 300°F was relatively low (see section on ignition tests). During the early stages of a run, heat flowed from the heaters to the sand pack increasing its temperature to the set point. As ignition and burning progressed through the tube, the heat level of the sand pack increased and the heat added by the heaters was correspondingly reduced. As the combustion front supplied sufficient heat to maintain temperatures in excess of the set point, the heaters were completely shut off by the automatic controller.

It is realized that the strip heater concept does not enable temperature profiles to be created analogous to those in the reservoir. However, as was mentioned in the introduction, the linear combustion tube model cannot simulate the three dimensional aspects of reservoir fluid flow. It is believed that the temperature and flow history of a unit volume in the

combustion tube does represent the behavior of a similar element in the reservoir. Therefore, the calculated parameters of interest will indeed be the same for both systems.

Results showed a distinctive correlation between heater temperature and oxygen utilization. Runs 1-8 utilized a set point of 300°F and over 80% of the oxygen was consumed by burning. Runs 18-25 maintained 200°F heater temperatures and oxygen efficiency ranged from 60-70%. These differences which are directly due to the thermal design of the laboratory equipment also caused a noticeable effect on the fuel deposit and air requirements. The 200°F runs burned less oil requiring less air than the high temperature runs. Indications of bypassed coke near the walls of the tube were observed. Again, the excessive heat losses produced lower temperatures resulting in incomplete combustion. The high temperature runs with very little produced oxygen showed no bypassed coke and more closely represent the processes occurring in the field.

Alteration of Mineral Composition

Combustion tube samples were analyzed before and after exposure to burning temperatures to determine changes that occurred in the mineral composition of the reservoir rock. Clay content is known to play an important role in laboratory combustion tests, affecting both fuel deposit and air requirement. Such a behavior is due to either the catalytic effect of certain minerals or the increased surface area due to the small clay particles. In either case, the mineral content should be known to extrapolate burning performance from one portion of the reservoir to another. Another reason for analyzing the minerals present before and after burning is to determine changes taking place at elevated temperatures. Alteration or decomposition

of certain clays occur at characteristic temperatures. Therefore, analysis of post-burn cores should allow the calculation of the maximum temperature to which each section of the core had been exposed. Calculation of temperature distributions from several cores can then be used to estimate areal and vertical movement of the combustion zone.

Results of X-ray diffraction analyses for samples from Run 25 are shown in Table 3. As can be seen the bulk material displayed very little change due to burning. However, the small particles (less than five microns) exhibited a disappearance of illite and kaolinite and corresponding increases in quartz and smectite. Slight increases in the concentrations of microcline, calcite and dolomite were also measured. The magnitude of the enthalpy changes due to the thermal alteration of the minerals is probably insignificant compared to the hydrocarbon reactions, but the presence or absence of the clays will have a catalytic contribution to the competing reactions. In other words, the presence of a particular clay might increase the rate constant of a thermal cracking reaction relative to an oxidation reaction. Such an effect would decrease the amount of oil burned and increase the efficiency of the combustion process. The distribution of these clays throughout the formation can then be used to explain differences in performance in various portions of the field. Attempts to quantify this type of behavior is the subject of future research studies.

Fluid Properties

Detailed analyses of Bellevue produced fluids are presented in the Bellevue-DOE Annual Reports and will also be the subject of a future topical report. In order to determine changes that might have occurred during laboratory combustion tube tests, several analyses were performed on fluids

produced from the laboratory runs. Tables 4 and 5 show the results of oil analyses from Runs 1-4 compared to original Bellevue oil. Runs 1 and 2 utilized native core material while native oil and burned Bellevue sand were mixed in Runs 3 and 4. Three samples were taken at three different stages during Run #1 and the results are very similar. A slight upgrading of oil gravity from 19.1 to 20.4 and a viscosity decrease from 261 to 58 cp were determined. The acid number did not change appreciably from the 5.3 mg KOH/g oil. Run 2 showed similar oil properties with a gravity of 20.4, viscosity of 76 cp and acid number of 5.4 mg KOH/mg oil. The oil from Runs 3 and 4 were significantly altered which could be due to the mixing of native oil and burned sand. Oil gravities increased to 22.9 and 23.6° API; viscosities at 100°F were decreased to 22 and 37 cp and the acid numbers were only 2.5 and 2.3 mg KOH/g oil. These drastically different oil properties were reflected in the low fuel deposit and air requirement calculated for the runs using mixed oil and sand.

In addition to the analysis of the crude oil, the composition of the produced water was determined. Because native core material used to pack the tube contained little or no water, all of the water produced during the tube runs should be either water formed by combustion or the fresh water injected during wet combustion runs. Results of analyses verified this fact. Specific gravities of water samples were approximately 1.0007 and the chloride content was 45 mg/l. Analysis did show the water was very acidic having a pH of 2.5. The acid nature of the water is probably due to the formation of acids during low temperature oxidation apparently present in most runs.

Three samples of produced gas were collected during combustion tube testing. The results shown in Table 6 indicate no nitrogen oxides generated

during the dry burn but hydrogen sulfide concentrations ranging from 8500-83100 ppm. These analyses imply that produced combustion gases in the field will contain significant amounts of H_2S .

Simultaneous Water/Air Injection

The injection of water and air simultaneously offers several possible advantages in fireflooding. First, the controlled injection of water in the upper portion of the pay interval and air in the lower tends to offset gravity override and poor vertical sweep inherent in all field applications. This behavior is very difficult to model in laboratory tests. The primary reason to inject water while burning is the ability of water to transport the generated heat to the cold oil zones. As was discussed in the introduction, the thermal design of the combustion tube creates problems in correlating between laboratory results and field behavior. Finally, it has been reported that the wet combustion process decreases both the amount of oil burned as fuel and the air required to burn a given volume of reservoir. It is this behavior that is being investigated in this study. The optimum water/air injection ratio (WAR) for field operations was one of the primary objectives of the combustion tube tests. The values obtained from the laboratory tests will be based only on burning front performance. Field WAR's will have to be calculated on three dimensional fluid flow and heat flow considerations. Only a very sophisticated mathematical model not presently available will allow such calculations.

Analysis of the results, Table 1, indicates a decrease of nearly 25% in the fuel deposit and air requirement when water was injected. However, a correlation between WAR and fuel deposit was not apparent so that no optimum WAR could be selected on the basis of these combustion tube tests.

A number of points were readily apparent from the tests. During dry combustion a very sharp temperature gradient appeared ahead of the flood front. Most of the generated heat remained behind the front and created a small zone of high heat content. Such conditions caused the strip heaters to supply additional heat to the system because the thermocouple sensed low temperatures. During wet combustion, temperatures ahead of the front rose very rapidly as the steam distributed the heat along the length of the tube. The external heaters would shut off and heat losses would increase. Therefore, the overall heat content of the system during dry combustion was much greater than during wet combustion. Temperature levels in the combustion zone were more stable in the dry runs and the burning was more evenly distributed radially. In some of the wet combustion runs, it appears as if low temperature oxidation competed with the primary reaction. Therefore, the results of the tests are somewhat clouded because of the various mechanisms occurring under the different tube conditions.

Results did verify that substantial amounts of water transformed to steam can move through the combustion zone without any loss in burning efficiency. However, if the temperature of the combustion zone was reduced sufficiently erratic combustion zone profiles were obtained. The process of quenched combustion could not be maintained under the conditions present in the laboratory equipment.

TABLE 1
SUMMARY OF COMBUSTION TUBE RESULTS

	<u>Run #1</u>	<u>Run #2</u>	<u>Run #3</u>	<u>Run #4</u>	<u>Run #7</u>	<u>Run #8</u>	<u>Run #9</u>
<u>Packing Conditions</u>							
Porosity, %	51.	48.	44.	43.	49.0	47.	51.
Oil Saturation, % PV	31.	36.	19.	21.	30.0	25.	22.
Sand Weight, grams	6267.	6624.	7068.	7187.	6493.0	6680.	6227.
Oil Weight, grams	693.	780.	372.	399.	663.0	534.	498.
Water Weight, grams	0.0	2.	0.0	399.	377.0	58.	54.
Native or mixed	N	N	M	M	N	N	N
<u>Operating Conditions</u>							
Combustion Temperature, °F	1053.	1116.	980.	936.	1531.	1022.	965.
Burning Efficiency, %	74.	80.	83.	90.	76.	89.	99.
Water/Air Ratio, B/MMSCF	0.0	0.0	0.0	125.	195.	336.	342.
<u>Results</u>							
Fuel Deposit, 16/ft. ³	2.79	1.94	1.31	1.50	1.76	1.55	1.90
Air Requirement, MMCF/A-F	19954.	12788.	9540.	11100.	13400.	12035.	15476.
Mole Weight of Fuel Unit	13.37	12.77	13.59	13.67	13.70	13.64	13.90
Air/Oil Ratio, MCF/B	19.95	13.69	23.61	28.32	17.15	21.10	101.

TABLE 1--CONTINUED
SUMMARY OF COMBUSTION TUBE RESULTS

	<u>Run #10</u>	<u>Run #11</u>	<u>Run #12</u>	<u>Run #13</u>	<u>Run #14</u>	<u>Run #15</u>	<u>Run #17</u>
<u>Packing Conditions</u>							
Porosity, %	50.	50.	52.	51.	49.	45.	41.
Oil Saturation, % PV	23.	28.	25.	18.	33.	25.	57.
Sand Weight, grams	6344.	6403.	6138.	6234.	6416.	6976.	7478.
Oil Weight, grams	506.	618.	574.	412.	738.	511.	1051.
Water Weight, grams	55.	14.	15.	13.	14.	22.	17.
Native or Mixed	N	N	N	N	N	N	M
<u>Operating Conditions</u>							
Combustion Temperature, °F	908.	1023.	919.	931.	823.	1031.	1094.
Burning Efficiency, %	87.	92.	86.	84.	82.	99.	98.
Water/Air Ratio, B/MMSCF	342.	352.	485.	503.	335.	0.0	0.0
<u>Results</u>							
Fuel Deposit, 16/ft. ³	1.77	1.76	1.45	1.49	2.24	1.86	2.55
Air Requirement MMCF/A-F	13201.	12510.	11060.	11052.	16444.	13907.	17666.
Mole Weight of Fuel Unit	13.58	13.17	13.80	13.65	13.52	13.54	13.11
Air/Oil Ratio, MCF/B	15.6	12.66	86.50	222.	19.43	20.79	13.0

TABLE 1--CONTINUED
SUMMARY OF COMBUSTION TUBE RESULTS

	<u>Run #18</u>	<u>Run #19</u>	<u>Run #20</u>	<u>Run #24</u>	<u>Run #24</u>	<u>Run #25</u>
<u>Packing Conditions</u>						
Porosity, %	47.	46.	52.	47.	48.	46.
Oil Saturation, % PV	34.	23.	21.	19.	18.	25.
Sand Weight, grams	6786.	6799.	6141.	6761.	6568.	6905.
Oil Weight, grams	712.	481.	479.	401.	390.	508.
Water Weight, grams	0.0	8.	8.	15.5	15.1	21.4
Native or Mixed	N	N	N	N	N	N
<u>Operating Conditions</u>						
Combustion Temperature, °F	941.	967.	976.	1048.	1199.	1361.
Burning Efficiency, %	98.	62.	74.	61.	58.	66.
Water/Air Ratio, B/MMSCF	0.0	0.0	225.	226.	188.	182.
<u>Results</u>						
Fuel Deposit, 16/ft. ³	2.78	1.57	1.65	1.33	1.57	2.04
Air Requirement, MMCF/A-F	19430.	10228.	10637.	8706.	10370.	12395.
Mole Weight of Fuel Unit	13.18	12.55	12.71	12.60	12.66	12.21
Air/Oil Ratio, MCF/B	22.59	24.17	15.87	26.18	26.92	43.66

TABLE 2
 BELLEVUE CORE SAMPLES
 IGNITION TEST RESULTS

OVEN TEMPERATURE VS % OXYGEN PRODUCED

<u>System Temperature, °F</u>	<u>Run 1 Flux=32 SCF/f²-HR</u>	<u>Run 2 35</u>	<u>Run 3 16</u>	<u>Run 4 16</u>	<u>Run 5 30</u>
200	21.0	--	--	--	--
250	21.0	--	21.0	21.0	21.0
300	19.8	--	19.6	19.1	21.0
350	17.0	16.5	15.0	14.3	17.5
400	10.5	8.9	5.3	6.9	9.4
450	7.2	1.5	0.5	1.0	3.3
500	0.0	0.0	0.0	0.0	0.0

Average pressure drop through tube ~ 4 psi.

TABLE 3
SEMIQUANTITATIVE X-RAY DIFFRACTION ANALYSIS OF CORE MATERIAL

	Bulk Material				Less Than Five Micron-Size			
	Sample 1	Sample 2	Sample 3	Sample 4	Sample 1	Sample 2	Sample 3	Sample 4
Illite	2	2	2	3	--	--	20	26
Smectite	--	--	--	--	12	11	8	7
Kaolinite	6	2	3	5	22	19	25	38
Chlorite	--	--	--	--	4	3	3	5
Quartz	76	77	78	74	44	48	35	19
Microcline	6	5	5	5	8	5	4	2
Orthoclase	3	2	2	2	--	--	--	--
Calcite	4	7	6	5	--	9	3	2
Dolomite	2	4	3	4	10	5	2	1
Siderite	1	1	1	--	--	--	--	--

Samples 1-3 burned sand from Run #25.

Sample 4 native sand used in Run #25.

TABLE 4
BELLEVUE COMBUSTION TUBE OIL ANALYSES

	<u>API Gravity @ 60°F</u>	<u>Viscosity, cps @ 100°F</u>	<u>Acid Number Mg KOH/g Oil</u>
Run #1			
A	20.5	58	5.5
B	20.3	59	6.7
C	20.4	56	7.7
Run #2	20.4	76	5.4
Run #3	22.9	22	2.5
Run #4	23.6	37	2.3
Original Oil	19.1	261	5.3

TABLE 5
BELLEVUE COMBUSTION TUBE OIL CHROMATOGRAPHIC ANALYSES

<u>Component</u>	<u>BP, °F</u>	<u>Run #1</u>			<u>Run #2</u>	<u>Run #3</u>	<u>Run #4</u>	<u>Original Oil</u>
		<u>A</u>	<u>B</u>	<u>C</u>				
C ₆	156	2.0	0.2	--	1.8	0.5	--	--
C ₇	209	0.8	0.6	0.1	0.7	0.2	--	0.1
C ₈	258	1.2	0.9	0.4	1.2	0.3	0.1	0.1
C ₉	303	2.4	1.8	1.0	1.9	0.9	0.4	0.4
C ₁₀	346	3.1	2.9	1.9	2.9	2.5	1.9	2.5
C ₁₁	384	5.1	4.1	2.8	3.8	6.7	4.7	4.6
C ₁₂	421	7.4	5.7	4.6	6.2	8.7	8.6	6.0
C ₁₃	470	9.3	8.5	5.3	7.2	9.3	10.1	8.1
C ₁₄	488	8.0	8.1	6.4	8.2	9.1	11.4	7.6
C ₁₅	518	8.6	7.8	7.3	8.0	9.2	9.0	6.6
C ₁₆	548	8.2	9.1	8.6	7.5	9.2	8.6	6.6
C ₁₇	577	4.5	4.3	5.7	5.5	5.8	7.1	6.1
C ₁₈	602	3.7	4.3	4.8	3.4	4.4	5.1	4.2
C ₁₉	627	3.0	3.3	5.0	3.5	3.9	4.3	3.7
C ₂₀	651	2.9	4.4	6.7	4.3	3.5	4.1	3.6

TABLE 6
LABORATORY COMBUSTION EXPERIMENT PRODUCED GAS ANALYSES

Note: All Values are Reported as Mole Percent

<u>Component</u>	<u>Sample 1</u>	<u>Sample 2</u>	<u>Sample 3</u>
a. Carbon Dioxide, CO ₂	9.6	8.6	11.2
a. Carbon Monoxide, CO	3.9	3.5	3.8
a. Oxygen, O ₂	5.9	6.1	4.4
b. Hydrogen Sulfide, H ₂ S	0.0085	0.0226	0.0831
c. Nitrogen Oxides, NO _x	0	0	trace
Nitrogen, N ₂ (by difference)	79.7	81.4	80.0
Methane, CH ₄	0.37	0.13	0.16
Ethane, C ₂ H ₆	0.20	0.05	0.04
Propane, C ₃ H ₈	0.03	0.05	0.04
Iso-butane, C ₄ H ₁₀	0.01	0.01	0
Normal-butane, C ₄ H ₁₀	0.09	0.02	0.02
Iso-pentane, C ₅ H ₁₂	0.01	0.01	0.01
Normal-pentane, C ₅ H ₁₂	0.03	0.01	0.01
Hexane plus	0.10	0.06	0.15
Specific Gravity	1.0431	1.0354	1.0529

- a. Carbon dioxide, carbon monoxide and oxygen were analyzed by the Orsat method.
- b. Hydrogen sulfide was analyzed by the Tutweiler method.
- c. Nitrogen oxides were analyzed by wet chemical procedures recommended by the Environmental Protection Agency.

FIGURE 1

TEMPERATURE DISTRIBUTION OF RESERVOIR

SCHEMATIC OF IN-SITU. COMBUSTION PROCESS

FIGURE 2

LABORATORY COMBUSTION TUBE SCHEMATIC

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOCH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 1
DATE: JULY 8, 1976
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	2.79
AIR REQUIRED	
SCF/CU FT	458.1
MSCF/A=F	19954.
OIL BURNED AS FUEL, B/A=F	365.
AIR-OIL RATIO, MSCF/B	12.93
AIR-FUEL RATIO, SCF/LB	164.
FRACTION OF OXYGEN UTILIZED	.74
MOLE WEIGHT OF FUEL UNIT	13.37
AVERAGE WATER-AIR RATIO, B/MMSCF	.00
FINAL WATER-AIR RATIO, B/MMSCF	.00
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	1053.
TUBE AIR-OIL RATIO, MSCF/B	19.95
% OIL-IN-PLACE RECOVERED	84.58

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	6267.00
OIL WEIGHT, GRAMS	693.00
WATER WEIGHT, GRAMS	.00
POROSITY, %	51.
OIL SATURATION, %PV	31.
WATER SATURATION, %PV	0.
GAS SATURATION, %PV	69.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	4.60	.00	.00	1.20	14.30	4.00	.00
.83	12.90	.00	.00	1.80	13.60	4.00	.00
1.47	20.00	.00	20.00	5.90	9.60	3.90	.00
2.42	31.40	.00	45.00	8.00	7.20	2.60	.00
3.38	44.10	135.00	70.00	6.10	8.60	3.50	.00
4.67	61.60	335.00	80.00	5.20	9.80	3.80	.00
5.50	75.50	542.00	90.00	4.40	11.20	3.80	.00
5.88	82.00	617.00	92.00	10.00	8.20	.60	.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1380.0000	4.6000
.8333	8.0000	1200.0000	12.9000
1.4667	16.0000	1100.0000	20.0000
2.4167	24.0000	920.0000	31.4000
3.3833	32.0000	970.0000	44.1000
4.6667	40.0000	1080.0000	61.6000
5.5000	48.0000	1120.0000	75.5000
5.8833	56.0000	960.0000	82.0000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOCH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 2
DATE: SEPT 23, 1976
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.94
AIR REQUIRED	
SCF/CU FT	293.6
MSCF/A=F	12788.
OIL BURNED AS FUEL, B/A=F	254.
AIR-OIL RATIO, MSCF/B	7.73
AIR-FUEL RATIO, SCF/LB	151.
FRACTION OF OXYGEN UTILIZED	.80
MOLE WEIGHT OF FUEL UNIT	12.77
AVERAGE WATER-AIR RATIO, B/MMSCF	.00
FINAL WATER-AIR RATIO, B/MMSCF	.00
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	1116.
TUBE AIR-OIL RATIO, MSCF/B	13.69
% OIL-IN-PLACE RECOVERED	75.56

* LABORATORY PACK CONDITIONS *

SAND WEIGHT,GRAMS	6623.70
OIL WEIGHT,GRAMS	779.50
WATER WEIGHT,GRAMS	1.50
POROSITY,%	48.
OIL SATURATION,%PV	36.
WATER SATURATION,%PV	0.
GAS SATURATION,%PV	63.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	.00	.00	.00	.00	14.00	3.00	.00
.38	6.40	.00	.00	3.40	12.00	3.80	.00
.67	11.00	.00	.00	2.70	10.10	4.20	.00
1.12	16.00	.00	.00	3.50	14.20	3.50	.00
1.48	25.00	.00	.00	4.50	13.50	4.10	.00
2.07	34.30	250.00	50.00	1.90	12.00	3.70	.00
2.55	42.00	415.00	60.00	3.70	14.20	4.60	.00
2.92	48.00	485.00	65.00	5.70	10.50	4.50	.00
3.28	54.40	620.00	80.00	10.00	8.00	2.60	.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	665.0000	1.0000
.3833	8.0000	1130.0000	6.4000
.6667	16.0000	1170.0000	11.0000
1.1167	24.0000	960.0000	16.0000
1.4833	32.0000	890.0000	25.0000
2.0667	40.0000	1195.0000	34.3000
2.5500	48.0000	1260.0000	42.0000
2.9167	56.0000	1290.0000	48.0000
3.2833	64.0000	990.0000	54.4000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOCH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 3
DATE: SEPT 29, 1976
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.31
AIR REQUIRED	
SCF/CU FT	219.0
MSCF/A=F	9540.
OIL BURNED AS FUEL, B/A=F	171.
AIR-OIL RATIO, MSCF/B	5.49
AIR-FUEL RATIO, SCF/LB	167.
FRACTION OF OXYGEN UTILIZED	.83
MOLE WEIGHT OF FUEL UNIT	13.59
AVERAGE WATER-AIR RATIO, B/MMSCF	.00
FINAL WATER-AIR RATIO, B/MMSCF	.00
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	980.
TUBE AIR-OIL RATIO, MSCF/B	23.61
% OIL-IN-PLACE RECOVERED	66.40

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	7068.00
OIL WEIGHT, GRAMS	372.00
WATER WEIGHT, GRAMS	.00
POROSITY, %	44.
OIL SATURATION, %PV	19.
WATER SATURATION, %PV	0.
GAS SATURATION, %PV	81.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	1.90	.00	.00	.50	12.70	4.60	.00
.23	5.60	.00	.00	.80	11.40	4.60	.00
.45	8.80	.00	.00	5.10	9.60	3.90	.00
.67	12.40	.00	.00	2.50	11.60	4.30	.00
.87	15.20	.00	.00	1.60	11.60	4.30	.00
1.07	18.60	.00	1.00	.70	11.70	4.60	.00
1.32	21.90	.00	3.00	.30	13.10	4.00	.00
1.47	24.60	.00	10.00	.20	13.80	5.20	.00
1.65	27.40	25.00	40.00	.30	13.30	5.20	.00
1.82	30.10	100.00	40.00	1.30	12.40	4.50	.00
2.10	34.40	195.00	40.00	6.90	8.30	3.10	.00
2.47	40.50	260.00	45.00	12.30	4.40	1.90	.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1200.0000	1.9000
.2333	6.0000	1040.0000	5.6000
.4500	12.0000	1020.0000	8.8000
.6667	18.0000	1030.0000	12.4000
.8667	24.0000	1020.0000	15.2000
1.0667	30.0000	960.0000	18.6000
1.3167	36.0000	960.0000	21.9000
1.4667	42.0000	1000.0000	24.6000
1.6500	48.0000	1040.0000	27.4000
1.8167	54.0000	980.0000	30.1000
2.1000	60.0000	960.0000	34.4000
2.4667	66.0000	870.0000	40.5000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 4
DATE: NOV. 3. 1976
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.50
AIR REQUIRED	
SCF/CU FT	254.8
MSCF/A-F	11100.
OIL BURNED AS FUEL, B/A-F	196.
AIR-OIL RATIO, MSCF/B	6.48
AIR-FUEL RATIO, SCF/LB	170.
FRACTION OF OXYGEN UTILIZED	.90
MOLE WEIGHT OF FUEL UNIT	13.67
AVERAGE WATER-AIR RATIO, B/MMSCF	.00
FINAL WATER-AIR RATIO, B/MMSCF	.00
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	936.
TUBE AIR-OIL RATIO, MSCF/B	28.32
% OIL-IN-PLACE RECOVERED	49.96

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	7187.40
OIL WEIGHT, GRAMS	399.30
WATER WEIGHT, GRAMS	399.30
POROSITY, %	43.
OIL SATURATION, %PV	21.
WATER SATURATION, %PV	20.
GAS SATURATION, %PV	60.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	1.40	.00	.00	.00	12.40	6.60	.00
.25	4.40	.00	.00	.30	12.80	4.30	.00
.55	8.20	.00	.00	1.40	11.60	3.80	.00
.83	12.10	.00	.00	.80	11.20	4.10	.00
1.12	15.70	.00	.00	.60	13.60	4.40	.00
1.40	19.30	.00	10.00	2.20	11.00	4.00	.00
1.70	23.20	70.00	40.00	1.50	12.20	4.30	.00
2.27	30.40	140.00	65.00	1.90	11.10	4.10	.00
2.93	38.80	210.00	65.00	5.10	9.90	3.20	.00

45

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1120.0000	1.4000
.2500	6.0000	1010.0000	4.4000
.5500	12.0000	940.0000	8.2000
.8333	18.0000	930.0000	12.1000
1.1167	24.0000	965.0000	15.7000
1.4000	30.0000	890.0000	19.3000
1.7000	36.0000	890.0000	23.2000
2.2667	48.0000	930.0000	30.4000
2.9333	60.0000	940.0000	38.8000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOCH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 7
DATE: JAN 5, 1977
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.76
AIR REQUIRED	
SCF/CU FT	307.6
MSCF/A=F	13400.
OIL BURNED AS FUEL, B/A=F	230.
AIR-OIL RATIO, MSCF/B	7.98
AIR-FUEL RATIO, SCF/LB	175.
FRACTION OF OXYGEN UTILIZED	.76
MOLE WEIGHT OF FUEL UNIT	13.70
AVERAGE WATER-AIR RATIO, B/MMSCF	125.18
FINAL WATER-AIR RATIO, B/MMSCF	146.74
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	1531.
TUBE AIR-OIL RATIO, MSCF/B	17.15
% OIL-IN-PLACE RECOVERED	63.76

* LABORATORY PACK CONDITIONS *

SAND WEIGHT,GRAMS	6493.00
OIL WEIGHT,GRAMS	663.00
WATER WEIGHT,GRAMS	377.00
POROSITY,%	49.
OIL SATURATION,%PV	30.
WATER SATURATION,%PV	16.
GAS SATURATION,%PV	53.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	14.50	.00	.00	8.40	6.20	2.50	.00
.67	22.20	.00	30.00	1.60	11.40	3.00	54.00
1.13	27.60	.00	130.00	.60	13.20	3.30	140.00
1.58	33.00	.00	220.00	1.60	12.50	3.00	250.00
1.97	37.50	.00	250.00	3.40	12.20	2.90	324.00
2.32	41.40	25.00	300.00	3.40	11.80	2.80	434.00
2.65	45.50	145.00	350.00	1.10	13.00	3.10	462.00
3.05	50.00	270.00	410.00	2.30	12.80	2.70	544.00
3.33	53.30	340.00	450.00	3.20	11.80	2.60	600.00
4.07	62.50	445.00	560.00	19.40	.40	.10	764.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	12.0000	1700.0000	14.5000
.6667	18.0000	1560.0000	22.2000
1.1333	24.0000	1680.0000	27.6000
1.5833	30.0000	1630.0000	33.0000
1.9667	36.0000	1720.0000	37.5000
2.3167	42.0000	1675.0000	41.4000
2.6500	48.0000	1950.0000	45.5000
3.0500	54.0000	1755.0000	50.0000
3.3333	60.0000	1820.0000	53.3000
4.0667	66.0000	760.0000	62.5000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOCCH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 8
DATE: JAN 10, 1977
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.55
AIR REQUIRED	
SCF/CU FT	276.3
MSCF/A-F	12095.
OIL BURNED AS FUEL, B/A-F	203.
AIR-OIL RATIO, MSCF/B	7.05
AIR-FUEL RATIO, SCF/LB	178.
FRACTION OF OXYGEN UTILIZED	.89
MOLE WEIGHT OF FUEL UNIT	13.64
AVERAGE WATER-AIR RATIO, B/MMSCF	195.81
FINAL WATER-AIR RATIO, B/MMSCF	298.91
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	1022.
TUBE AIR-OIL RATIO, MSCF/B	21.10
% OIL-IN-PLACE RECOVERED	48.92

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	6680.00
OIL WEIGHT, GRAMS	534.00
WATER WEIGHT, GRAMS	58.00
POROSITY, %	47.
OIL SATURATION, %PV	25.
WATER SATURATION, %PV	3.
GAS SATURATION, %PV	72.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O ₂ CONC	CO ₂ CONC	CO CONC	WATER INJECTED
.00	5.40	.00	.00	.20	16.00	1.60	.00
.55	10.90	.00	.00	.30	13.00	2.10	.00
1.00	16.10	.00	.00	1.20	12.70	2.10	.00
1.28	19.60	.00	60.00	2.70	13.10	1.90	136.00
1.57	22.90	.00	170.00	3.70	12.10	1.80	286.00
1.87	26.60	.00	250.00	4.00	11.60	1.80	436.00
2.20	30.30	.00	325.00	3.10	12.70	1.60	596.00
2.52	34.00	20.00	410.00	1.90	14.10	1.70	736.00
2.82	37.90	150.00	450.00	2.50	13.60	1.60	896.00
3.07	41.90	275.00	550.00	4.20	12.20	1.60	1066.00

55

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	6.0000	1420.0000	5.4000
.5500	12.0000	980.0000	10.9000
1.0000	18.0000	1015.0000	16.1000
1.2833	24.0000	1020.0000	19.6000
1.5667	30.0000	1030.0000	22.9000
1.8667	36.0000	1010.0000	26.6000
2.2000	42.0000	1030.0000	30.3000
2.5167	48.0000	1060.0000	34.0000
2.8167	54.0000	1050.0000	37.9000
3.0667	60.0000	1040.0000	41.9000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOCH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 9
DATE: JAN 17, 1977
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.90
AIR REQUIRED	
SCF/CU FT	355.3
MSCF/A-F	15476.
OIL BURNED AS FUEL, B/A-F	248.
AIR-OIL RATIO, MSCF/B	9.32
AIR-FUEL RATIO, SCF/LB	187.
FRACTION OF OXYGEN UTILIZED	.99
MOLE WEIGHT OF FUEL UNIT	13.90
AVERAGE WATER-AIR RATIO, B/MMSCF	336.69
FINAL WATER-AIR RATIO, B/MMSCF	491.95
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	965.
TUBE AIR-OIL RATIO, MSCF/B	101.31
% OIL-IN-PLACE RECOVERED	13.35

* LABORATORY PACK CONDITIONS *

SAND WEIGHT,GRAMS	6227.00
OIL WEIGHT,GRAMS	498.00
WATER WEIGHT,GRAMS	54.00
POROSITY,%	51.
OIL SATURATION,%PV	22.
WATER SATURATION,%PV	2.
GAS SATURATION,%PV	76.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	2.00	.00	.00	.10	12.30	.90	.00
.13	3.40	.00	.00	1.00	11.10	1.20	.00
.63	9.20	.00	.00	.10	14.40	1.20	.00
.93	13.80	.00	.00	.20	13.30	1.10	.00
1.38	18.20	30.00	40.00	.10	14.20	1.10	350.00
1.75	22.50	40.00	175.00	.10	15.70	1.20	660.00
2.08	26.40	45.00	250.00	.00	14.60	1.10	930.00
2.45	30.60	50.00	400.00	.30	14.50	1.20	1230.00
2.87	35.70	60.00	550.00	.00	14.80	.90	1570.00
3.35	41.20	65.00	675.00	.10	15.20	.80	1870.00
3.87	46.60	70.00	700.00	.00	14.20	.90	2290.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	2.0000	1060.0000	2.0000
.1333	6.0000	1090.0000	3.4000
.6333	12.0000	960.0000	9.2000
.9333	18.0000	1050.0000	13.8000
1.3833	24.0000	970.0000	18.2000
1.7500	30.0000	1050.0000	22.5000
2.0833	36.0000	1060.0000	26.4000
2.4500	42.0000	1050.0000	30.6000
2.8667	48.0000	950.0000	35.7000
3.3500	54.0000	865.0000	41.2000
3.8667	60.0000	810.0000	46.6000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOCH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 10
DATE: JAN 21, 1977
ANALYSTS: PB

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.77
AIR REQUIRED	
SCF/CU FT	303.0
MSCF/A-F	13201.
OIL BURNED AS FUEL, B/A-F	231.
AIR-OIL RATIO, MSCF/B	7.87
AIR-FUEL RATIO, SCF/LB	171.
FRACTION OF OXYGEN UTILIZED	.87
MOLE WEIGHT OF FUEL UNIT	13.58
AVERAGE WATER-AIR RATIO, B/MMSCF	342.01
FINAL WATER-AIR RATIO, B/MMSCF	604.65
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	908.
TUBE AIR-OIL RATIO, MSCF/B	15.60
% OIL-IN-PLACE RECOVERED	88.24

* LABORATORY PACK CONDITIONS *

SAND WEIGHT,GRAMS	6344.00
OIL WEIGHT,GRAMS	506.00
WATER WEIGHT,GRAMS	55.00
POROSITY,%	50.
OIL SATURATION,%PV	23.
WATER SATURATION,%PV	2.
GAS SATURATION,%PV	75.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	3.70	.00	.00	.50	10.80	6.10	.00
.08	4.70	.00	.00	.00	13.50	5.10	.00
.45	9.10	.00	.00	.30	12.30	4.20	.00
1.20	18.10	.00	20.00	1.00	12.30	3.70	.00
1.67	23.80	50.00	175.00	3.90	12.00	2.80	384.00
2.08	28.70	75.00	325.00	5.60	11.00	2.40	730.00
2.50	33.70	95.00	480.00	5.50	10.10	2.50	1086.00
2.77	37.00	100.00	600.00	2.90	11.70	3.00	1294.00
3.25	42.80	280.00	750.00	1.70	12.60	3.30	1694.00
3.52	45.90	250.00	795.00	2.00	12.20	3.10	1858.00
3.83	49.80	470.00	990.00	4.80	9.10	2.20	2184.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	950.0000	3.7000
.0833	6.0000	830.0000	4.7000
.4500	12.0000	1000.0000	9.1000
1.2000	18.0000	940.0000	18.1000
1.6667	24.0000	990.0000	23.8000
2.0833	30.0000	990.0000	28.7000
2.5000	36.0000	880.0000	33.7000
2.7667	42.0000	860.0000	37.0000
3.2500	48.0000	945.0000	42.8000
3.5167	54.0000	780.0000	45.9000
3.8333	60.0000	645.0000	49.8000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 11
DATE: JAN 27, 1977
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.76
AIR REQUIRED	
SCF/CU FT	287.2
MSCF/A=F	12510.
OIL BURNED AS FUEL, B/A=F	230.
AIR-OIL RATIO, MSCF/B	7.45
AIR-FUEL RATIO, SCF/LB	163.
FRACTION OF OXYGEN UTILIZED	.92
MOLE WEIGHT OF FUEL UNIT	13.17
AVERAGE WATER-AIR RATIO, B/MMSCF	352.20
FINAL WATER-AIR RATIO, B/MMSCF	517.59
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	1023.
TUBE AIR-OIL RATIO, MSCF/B	12.66
% OIL-IN-PLACE RECOVERED	80.70

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	6403.00
OIL WEIGHT, GRAMS	618.00
WATER WEIGHT, GRAMS	14.00
POROSITY, %	50.
OIL SATURATION, %PV	28.
WATER SATURATION, %PV	1.
GAS SATURATION, %PV	72.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	2.20	.00	.00	.80	13.00	4.50	.00
.27	5.60	.00	.00	.20	13.90	3.70	.00
.82	12.20	.00	.00	3.80	10.20	2.70	.00
1.27	17.70	.00	.00	1.50	12.00	3.70	.00
1.58	21.40	5.00	195.00	1.20	14.90	3.50	315.00
1.88	25.00	10.00	235.00	1.20	14.10	3.30	614.00
2.17	28.50	15.00	390.00	1.80	13.20	3.00	900.00
2.50	32.30	200.00	500.00	1.80	13.30	3.40	1218.00
2.85	36.40	300.00	590.00	1.10	14.90	3.60	1535.00
3.15	40.40	425.00	775.00	1.10	15.30	3.90	1870.00
3.43	44.00	525.00	875.00	2.50	14.40	3.30	2142.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1280.0000	2.2000
.2667	6.0000	1010.0000	5.6000
.8167	12.0000	1010.0000	12.2000
1.2667	18.0000	970.0000	17.7000
1.5833	24.0000	1025.0000	21.4000
1.8833	30.0000	990.0000	25.0000
2.1667	36.0000	980.0000	28.5000
2.5000	42.0000	1015.0000	32.3000
2.8500	48.0000	1070.0000	36.4000
3.1500	54.0000	1105.0000	40.4000
3.4333	60.0000	1090.0000	44.0000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOCCH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 12
DATE: FEB 15, 1977
ANALYSTS: PB

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.45
AIR REQUIRED	
SCF/CU FT	253.9
MSCF/A=F	11060.
OIL BURNED AS FUEL, B/A=F	190.
AIR-OIL RATIO, MSCF/B	6.43
AIR-FUEL RATIO, SCF/LB	175.
FRACTION OF OXYGEN UTILIZED	.86
MOLE WEIGHT OF FUEL UNIT	13.80
AVERAGE WATER-AIR RATIO, B/MMSCF	485.39
FINAL WATER-AIR RATIO, B/MMSCF	516.30
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	919.
TUBE AIR-OIL RATIO, MSCF/B	86.50
% OIL-IN-PLACE RECOVERED	8.28

* LABORATORY PACK CONDITIONS *

SAND WEIGHT,GRAMS	6138.00
OIL WEIGHT,GRAMS	574.00
WATER WEIGHT,GRAMS	15.00
POROSITY,%	52.
OIL SATURATION,%PV	25.
WATER SATURATION,%PV	1.
GAS SATURATION,%PV	75.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	1.50	.00	.00	.80	11.00	4.20	.00
.23	4.70	.00	.00	2.10	12.30	3.80	.00
.88	12.00	.00	.00	4.60	9.20	3.60	.00
1.18	15.80	.00	225.00	1.80	12.30	3.20	376.00
1.38	18.30	.00	375.00	2.10	11.90	3.10	660.00
1.75	22.40	10.00	540.00	3.40	10.70	2.90	1110.00
2.03	25.60	10.00	700.00	3.10	10.90	2.60	1448.00
2.28	28.70	50.00	850.00	2.30	11.40	3.00	1794.00
2.55	31.90	50.00	1050.00	2.60	11.80	3.20	2020.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.2333	6.0000	1020.0000	4.7000
.8833	12.0000	1050.0000	12.0000
1.1833	18.0000	910.0000	15.8000
1.3833	24.0000	880.0000	18.3000
1.7500	30.0000	905.0000	22.4000
2.0333	36.0000	860.0000	25.6000
2.2833	42.0000	805.0000	28.7000
2.5500	48.0000	740.0000	31.9000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOCCH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 13
DATE: FEB 22, 1977
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.49
AIR REQUIRED	
SCF/CU FT	253.7
MSCF/A=F	11052.
OIL BURNED AS FUEL, B/A=F	194.
AIR-OIL RATIO, MSCF/B	6.45
AIR-FUEL RATIO, SCF/LB	171.
FRACTION OF OXYGEN UTILIZED	.84
MOLE WEIGHT OF FUEL UNIT	13.65
AVERAGE WATER-AIR RATIO, B/MMSCF	503.68
FINAL WATER-AIR RATIO, B/MMSCF	688.66
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	931.
TUBE AIR-OIL RATIO, MSCF/B	221.80
% OIL-IN-PLACE RECOVERED	4.61

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	6234.00
OIL WEIGHT, GRAMS	412.00
WATER WEIGHT, GRAMS	13.00
POROSITY, %	51.
OIL SATURATION, %PV	18.
WATER SATURATION, %PV	1.
GAS SATURATION, %PV	81.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	8.50	.00	.00	1.30	12.20	4.90	.00
.52	14.90	.00	.00	2.60	11.60	4.00	.00
.88	19.10	.00	200.00	2.80	12.20	3.40	360.00
1.12	21.60	10.00	330.00	1.60	12.40	4.20	582.00
1.67	28.10	20.00	500.00	3.80	11.00	3.90	1036.00
2.02	32.50	20.00	750.00	4.70	8.90	2.50	1500.00
2.37	36.40	20.00	750.00	4.70	8.90	2.50	1860.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	6.0000	1010.0000	8.5000
.5167	12.0000	950.0000	14.9000
.8833	18.0000	910.0000	19.1000
1.1167	24.0000	940.0000	21.6000
1.6667	30.0000	1130.0000	28.1000
2.0167	36.0000	860.0000	32.5000
2.3667	48.0000	680.0000	36.4000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOKH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 14
DATE: MARCH 16, 1977
ANALYSTS: PB & BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	2.24
AIR REQUIRED	
SCF/CU FT	377.5
MSCF/A-F	16444.
OIL BURNED AS FUEL, B/A-F	293.
AIR-OIL RATIO, MSCF/B	10.17
AIR-FUEL RATIO, SCF/LB	169.
FRACTION OF OXYGEN UTILIZED	.82
MOLE WEIGHT OF FUEL UNIT	13.52
AVERAGE WATER-AIR RATIO, B/MMSCF	395.16
FINAL WATER-AIR RATIO, B/MMSCF	540.39
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	823.
TUBE AIR-OIL RATIO, MSCF/B	19.43
% OIL-IN-PLACE RECOVERED	64.36

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	6416.00
OIL WEIGHT, GRAMS	738.00
WATER WEIGHT, GRAMS	14.00
POROSITY, %	49.
OIL SATURATION, %PV	33.
WATER SATURATION, %PV	1.
GAS SATURATION, %PV	66.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	2.30	.00	.00	.10	11.20	7.40	.00
.47	7.80	.00	.00	1.50	12.60	4.20	.00
.87	12.80	.00	30.00	3.50	12.50	3.60	.00
1.52	20.40	.00	280.00	2.80	11.60	4.10	566.00
1.87	25.10	.00	400.00	4.40	10.80	3.20	900.00
2.43	33.20	30.00	670.00	6.80	7.80	2.40	1330.00
2.82	38.40	50.00	800.00	6.20	8.50	2.60	1330.00
3.32	45.50	100.00	900.00	3.90	10.20	3.10	1330.00
4.15	57.40	300.00	1050.00	3.10	12.00	3.40	2100.00
4.32	60.00	400.00	1125.00	3.30	11.10	3.00	2490.00
4.57	63.40	500.00	1225.00	3.90	11.20	2.70	2730.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1180.0000	2.3000
.4667	6.0000	1005.0000	7.8000
.8667	12.0000	1050.0000	12.8000
1.5167	18.0000	830.0000	20.4000
1.8667	24.0000	820.0000	25.1000
2.4333	30.0000	705.0000	33.2000
2.8167	36.0000	740.0000	38.4000
3.3167	42.0000	730.0000	45.5000
4.1500	48.0000	730.0000	57.4000
4.3167	54.0000	900.0000	60.0000
4.5667	60.0000	940.0000	63.4000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 15
DATE: APRIL 1, 1977
ANALYSTS: PB & BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.86
AIR REQUIRED	
SCF/CU FT	319.3
MSCF/A-F	13907.
OIL BURNED AS FUEL, B/A-F	243.
AIR-OIL RATIO, MSCF/B	8.35
AIR-FUEL RATIO, SCF/LB	172.
FRACTION OF OXYGEN UTILIZED	.99
MOLE WEIGHT OF FUEL UNIT	13.54
AVERAGE WATER-AIR RATIO, B/MMSCF	.00
FINAL WATER-AIR RATIO, B/MMSCF	.00
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	1031.
TUBE AIR-OIL RATIO, MSCF/B	20.79
% OIL-IN-PLACE RECOVERED	60.42

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	6976.00
OIL WEIGHT, GRAMS	511.00
WATER WEIGHT, GRAMS	22.00
POROSITY, %	45.
OIL SATURATION, %PV	25.
WATER SATURATION, %PV	1.
GAS SATURATION, %PV	74.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	3.30	.00	.00	1.01	13.00	3.00	.00
.23	6.40	.00	.00	.40	13.20	3.40	.00
.68	11.60	.00	.00	.50	13.40	3.20	.00
.97	15.30	.00	25.00	.40	13.20	3.30	.00
1.30	19.50	.00	35.00	.20	13.20	2.90	.00
1.63	23.80	.00	50.00	.00	13.60	3.60	.00
2.00	28.20	20.00	50.00	.20	13.00	3.40	.00
2.42	33.30	40.00	50.00	.00	14.20	3.00	.00
2.75	37.20	90.00	50.00	.00	14.60	3.40	.00
3.18	42.00	200.00	50.00	.00	14.60	3.60	.00
3.53	45.80	325.00	50.00	1.00	13.00	2.80	.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1060.0000	3.3000
.2333	6.0000	1085.0000	6.4000
.6833	12.0000	1080.0000	11.6000
.9667	18.0000	1025.0000	15.3000
1.3000	24.0000	1025.0000	19.5000
1.6333	30.0000	1020.0000	23.8000
2.0000	36.0000	1070.0000	28.2000
2.4167	42.0000	1025.0000	33.3000
2.7500	48.0000	970.0000	37.2000
3.1833	54.0000	1010.0000	42.0000
3.5333	60.0000	1005.0000	45.8000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAJ FEE B LEASE
FORMATION: NACATOH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 17
DATE: APRIL 27, 1977
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	2.55
AIR REQUIRED	
SCF/CU FT	405.5
MSCF/A-F	17666.
OIL BURNED AS FUEL, B/A-F	333.
AIR-OIL RATIO, MSCF/B	11.21
AIR-FUEL RATIO, SCF/LB	159.
FRACTION OF OXYGEN UTILIZED	.98
MOLE WEIGHT OF FUEL UNIT	13.11
AVERAGE WATER-AIR RATIO, B/MMSCF	.00
FINAL WATER-AIR RATIO, B/MMSCF	.00
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	1094.
TUBE AIR-OIL RATIO, MSCF/B	13.00
% OIL-IN-PLACE RECOVERED	70.05

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	7478.00
OIL WEIGHT, GRAMS	1051.00
WATER WEIGHT, GRAMS	17.00
POROSITY, %	41.
OIL SATURATION, %PV	57.
WATER SATURATION, %PV	1.
GAS SATURATION, %PV	42.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	3.50	.00	.00	.20	12.80	4.40	.00
.85	12.70	.00	.00	.00	15.70	4.10	.00
1.32	18.80	.00	.00	.00	14.40	4.40	.00
1.92	24.40	.00	.00	.00	14.40	4.40	.00
2.47	31.90	.00	.00	.00	14.60	4.30	.00
2.83	36.80	100.00	60.00	.00	12.20	5.00	.00
3.22	41.50	166.00	74.00	.00	13.70	4.70	.00
3.62	46.50	270.00	80.00	.10	13.70	4.60	.00
3.92	50.20	370.00	80.00	.00	13.60	5.00	.00
4.22	53.70	470.00	100.00	1.00	12.80	4.60	.00
4.67	59.10	680.00	100.00	4.10	10.40	4.30	.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1145.0000	3.5000
.8500	6.0000	1070.0000	12.7000
1.3167	12.0000	1210.0000	18.1000
1.9167	18.0000	1160.0000	24.4000
2.4667	24.0000	1145.0000	31.9000
2.8333	30.0000	1125.0000	36.8000
3.2167	36.0000	1075.0000	41.5000
3.6167	42.0000	1030.0000	46.5000
3.9167	48.0000	1060.0000	50.2000
4.2167	54.0000	1040.0000	53.7000
4.6667	60.0000	980.0000	59.1000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLEVUE - BODCAU FEE B LEASE
FORMATION: NACATOCCH SAND
LOCATION: BOSSIER PARISH, LOUISIANA

RUN NUMBER: 18
DATE: MAY 10, 1977
ANALYSTS: BP

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	2.78
AIR REQUIRED	
SCF/CU FT	446.0
MSCF/A=F	19430.
OIL BURNED AS FUEL, B/A=F	363.
AIR-OIL RATIO, MSCF/B	15.71
AIR-FUEL RATIO, SCF/LB	161.
FRACTION OF OXYGEN UTILIZED	.98
MOLE WEIGHT OF FUEL UNIT	13.18
AVERAGE WATER-AIR RATIO, B/MMSCF	.00
FINAL WATER-AIR RATIO, B/MMSCF	.00
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	941.
TUBE AIR-OIL RATIO, MSCF/B	22.59
% OIL-IN-PLACE RECOVERED	57.37

* LABORATORY PACK CONDITIONS *

SAND WEIGHT,GRAMS	6786.00
OIL WEIGHT,GRAMS	712.00
WATER WEIGHT,GRAMS	.00
POROSITY,%	47.
OIL SATURATION,%PV	34.
WATER SATURATION,%PV	0.
GAS SATURATION,%PV	66.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	1.80	.00	.00	2.60	9.00	4.50	.00
.13	4.00	.00	.00	.30	12.60	4.90	.00
.70	11.00	.00	.00	1.30	11.20	5.30	.00
1.03	14.80	.00	.00	.90	12.10	5.30	.00
2.20	22.50	7.00	11.00	.40	13.40	4.50	.00
3.05	30.30	48.00	12.00	.10	15.40	4.20	.00
3.55	35.30	66.00	14.00	.20	15.60	3.50	.00
5.35	43.10	172.00	20.00	.20	13.80	4.40	.00
6.45	50.30	235.00	37.00	.80	13.20	3.70	.00
6.95	56.80	370.00	40.00	.60	13.60	4.70	.00
7.42	62.90	430.00	40.00	1.10	13.40	5.10	.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1180.0000	1.8000
.1333	6.0000	1015.0000	4.0000
.7000	12.0000	1035.0000	11.0000
1.0333	18.0000	1040.0000	14.8000
2.2000	24.0000	1130.0000	22.0000
3.0500	30.0000	12.4000	30.3000
3.5500	36.0000	1060.0000	35.3000
5.3500	42.0000	995.0000	43.1000
6.4500	48.0000	1045.0000	50.3000
6.9500	54.0000	1170.0000	56.8000
7.4167	60.0000	1135.0000	62.9000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLVUE - ERDA-19
FORMATION:
LOCATION: *****ERDA-19*****

RUN NUMBER: 19
DATE: FEB 8, 1978
ANALYSTS:

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.57
AIR REQUIRED	
SCF/CU FT	234.8
MSCF/A=F	10228.
OIL BURNED AS FUEL, B/A=F	206.
AIR-OIL RATIO, MSCF/B	7.34
AIR-FUEL RATIO, SCF/LB	149.
FRACTION OF OXYGEN UTILIZED	.62
MOLE WEIGHT OF FUEL UNIT	12.55
AVERAGE WATER-AIR RATIO, B/MMSCF	.00
FINAL WATER-AIR RATIO, B/MMSCF	.00
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	967.
TUBE AIR-OIL RATIO, MSCF/B	24.17
% OIL-IN-PLACE RECOVERED	74.06

SAND WEIGHT,GRAMS
 OIL WEIGHT,GRAMS
 WATER WEIGHT,GRAMS
 POROSITY,%
 OIL SATURATION,%PV
 WATER SATURATION,%PV
 GAS SATURATION,%PV

6799.00
 481.00
 8.00
 46.
 23.
 0.
 76.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	1.10	.00	.00	1.85	14.16	2.74	.00
.35	4.70	.00	.00	4.28	12.03	2.79	.00
.73	8.70	.00	.00	6.28	10.73	2.70	.00
1.02	13.20	.00	.00	8.64	11.98	2.15	.00
1.38	18.40	.00	.00	6.39	10.53	3.53	.00
1.70	22.90	.00	.00	7.38	11.17	3.01	.00
1.98	26.90	.00	35.00	5.83	11.14	3.07	.00
2.32	31.40	.00	70.00	9.13	6.16	2.23	.00
2.82	39.10	50.00	70.00	12.30	7.52	1.72	.00
3.40	47.90	100.00	70.00	8.93	11.49	2.29	.00
3.78	53.50	200.00	70.00	8.02	9.63	2.45	.00
4.10	58.10	375.00	70.00	8.02	9.63	2.40	.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1050.0000	1.1000
.3500	6.0000	1045.0000	4.7000
.7333	12.0000	1040.0000	8.7000
1.0167	18.0000	960.0000	13.2000
1.3833	24.0000	960.0000	18.4000
1.7000	30.0000	960.0000	22.9000
1.9833	36.0000	965.0000	26.9000
2.3167	42.0000	970.0000	31.4000
2.8333	48.0000	880.0000	39.1000
3.4000	54.0000	950.0000	47.9000
3.7833	60.0000	985.0000	53.5000
4.1000	66.0000	960.0000	58.1000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLVUE   ERDA-20
FORMATION:
LOCATION: *****ERDA-20*****

RUN NUMBER: 20
DATE: MAR. 17, 1978
ANALYSTS:

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.65
AIR REQUIRED	
SCF/CU FT	244.2
MSCF/A=F	10637.
OIL BURNED AS FUEL, B/A=F	215.
AIR-OIL RATIO, MSCF/B	7.68
AIR-FUEL RATIO, SCF/LB	148.
FRACTION OF OXYGEN UTILIZED	.74
MOLE WEIGHT OF FUEL UNIT	12.71
AVERAGE WATER-AIR RATIO, B/MMSCF	225.39
FINAL WATER-AIR RATIO, B/MMSCF	287.78
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	976.
TUBE AIR-OIL RATIO, MSCF/B	15.87
% OIL-IN-PLACE RECOVERED	99.10

* LABORATORY PACK CONDITIONS *

SAND WEIGHT,GRAMS	6141.00
OIL WEIGHT,GRAMS	479.30
WATER WEIGHT,GRAMS	7.95
POROSITY,%	52.
OIL SATURATION,%PV	21.
WATER SATURATION,%PV	0.
GAS SATURATION,%PV	79.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	2.20	.00	.00	2.30	13.96	5.62	.00
.15	3.90	.00	.00	2.68	11.20	3.79	.00
.55	9.20	.00	.00	4.83	10.14	3.83	.00
.92	13.20	.00	.00	4.33	10.06	4.35	.00
1.42	19.30	.00	60.00	5.59	12.85	3.19	.00
1.78	23.50	10.00	125.00	5.01	11.29	4.34	340.00
2.07	27.40	20.00	200.00	2.36	14.28	5.36	530.00
2.33	31.90	50.00	225.00	1.87	14.37	6.19	640.00
2.68	35.50	175.00	250.00	4.42	14.11	4.41	755.00
3.05	40.00	225.00	400.00	3.95	11.95	6.48	910.00
3.40	44.20	300.00	625.00	6.14	11.06	2.91	1050.00
4.00	52.20	500.00	760.00	12.20	4.64	1.58	1320.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	930.0000	2.2000
.1500	6.0000	960.0000	3.9000
.5500	12.0000	910.0000	9.2000
.9167	18.0000	920.0000	13.2000
1.4167	24.0000	1050.0000	19.3000
1.7833	30.0000	920.0000	23.5000
2.0667	36.0000	980.0000	27.4000
2.3333	42.0000	1060.0000	31.9000
2.6833	48.0000	980.0000	35.5000
3.0500	54.0000	1000.0000	40.0000
3.4000	60.0000	1090.0000	44.2000
4.0000	66.0000	910.0000	52.1000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLVUE - ERDA-23
FORMATION:
LOCATION: *****ERDA-23*****

RUN NUMBER: 23
DATE: APRIL 14, 1978
ANALYSTS:

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.33
AIR REQUIRED	
SCF/CU FT	199.9
MSCF/A-F	8706.
OIL BURNED AS FUEL, B/A-F	174.
AIR-OIL RATIO, MSCF/B	6.11
AIR-FUEL RATIO, SCF/LB	150.
FRACTION OF OXYGEN UTILIZED	.61
MOLE WEIGHT OF FUEL UNIT	12.60
AVERAGE WATER-AIR RATIO, B/MMSCF	191.82
FINAL WATER-AIR RATIO, B/MMSCF	226.04
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	1048.
TUBE AIR-OIL RATIO, MSCF/B	26.18
% OIL-IN-PLACE RECOVERED	71.07

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	6761.00
OIL WEIGHT, GRAMS	401.00
WATER WEIGHT, GRAMS	15.50
POROSITY, %	47.
OIL SATURATION, %PV	19.
WATER SATURATION, %PV	1.
GAS SATURATION, %PV	80.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	1.90	.00	.00	2.48	13.79	3.87	.00
.38	4.70	.00	.00	7.94	9.90	3.11	.00
.75	9.30	.00	.00	9.03	7.16	2.29	.00
1.20	14.30	.00	.00	9.85	10.06	2.16	.00
1.63	19.30	.00	.00	9.74	7.07	1.97	50.00
2.12	25.40	.00	100.00	9.00	9.46	1.99	200.00
2.43	29.40	.00	125.00	8.47	11.98	2.30	330.00
2.75	33.90	.00	175.00	7.46	11.05	2.86	460.00
3.08	37.70	.00	300.00	7.07	10.77	3.03	575.00
3.43	41.70	75.00	375.00	6.91	11.23	2.70	670.00
3.83	45.60	200.00	450.00	7.16	9.42	2.63	825.00
4.25	51.30	300.00	550.00	7.10	10.50	3.10	950.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1260.0000	1.9000
.3833	6.0000	1140.0000	4.7000
.7500	12.0000	980.0000	9.3000
1.2000	18.0000	990.0000	14.3000
1.6333	24.0000	950.0000	19.3000
2.1167	30.0000	1020.0000	25.4000
2.4333	36.0000	1050.0000	29.4000
2.7500	42.0000	1140.0000	33.9000
3.0833	48.0000	1140.0000	37.7000
3.4333	54.0000	1060.0000	41.7000
3.8333	60.0000	1080.0000	45.6000
4.2500	66.0000	1030.0000	51.3000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLVUE - ERDA-24
FORMATION:
LOCATION: *****ERDA-24*****

RUN NUMBER: 24
DATE: APRIL 24, 1978
ANALYSTS:

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	1.57
AIR REQUIRED	
SCF/CU FT	238.1
MSCF/A-F	10370.
OIL BURNED AS FUEL, B/A-F	206.
AIR-OIL RATIO, MSCF/B	7.44
AIR-FUEL RATIO, SCF/LB	151.
FRACTION OF OXYGEN UTILIZED	.58
MOLE WEIGHT OF FUEL UNIT	12.66
AVERAGE WATER-AIR RATIO, B/MMSCF	187.67
FINAL WATER-AIR RATIO, B/MMSCF	.00
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	1199.
TUBE AIR-OIL RATIO, MSCF/B	26.92
% OIL-IN-PLACE RECOVERED	73.08

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	6567.50
OIL WEIGHT, GRAMS	390.00
WATER WEIGHT, GRAMS	15.10
POROSITY, %	48.
OIL SATURATION, %PV	18.
WATER SATURATION, %PV	1.
GAS SATURATION, %PV	81.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	13.80	.00	.00	9.40	9.50	2.10	.00
.17	15.70	.00	.00	8.30	11.80	4.10	.00
.82	23.60	.00	.00	10.50	11.00	3.60	.00
1.13	27.20	.00	.00	11.10	8.20	1.60	135.00
1.57	32.00	.00	180.00	10.00	8.80	2.10	270.00
1.98	36.50	.00	260.00	10.90	8.90	2.70	430.00
2.53	43.10	40.00	400.00	12.00	4.90	1.10	670.00
3.20	51.40	60.00	600.00	10.10	8.90	1.60	750.00
3.85	57.70	80.00	640.00	7.35	9.80	2.30	880.00
4.57	64.60	300.00	660.00	2.90	10.40	3.10	880.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	6.0000	1240.0000	13.8000
.1667	12.0000	1310.0000	15.7000
.8167	18.0000	1240.0000	23.6000
1.1333	24.0000	1045.0000	27.2000
1.5667	30.0000	1175.0000	32.0000
1.9833	36.0000	1130.0000	36.5000
2.5333	42.0000	1090.0000	43.1000
3.2000	48.0000	1500.0000	51.4000
3.8500	54.0000	1150.0000	57.7000
4.5667	60.0000	1105.0000	64.6000

CITIES SERVICE OIL COMPANY
E&P RESEARCH LABORATORY
TULSA, OKLAHOMA

COMBUSTION TUBE ANALYSIS

WELL NAME: BELLVUE - ERDA-25
FORMATION:
LOCATION: *****ERDA-25*****

RUN NUMBER: 25
DATE: MAY 8, 1978
ANALYSTS:

* SUMMARY OF RESULTS *

FUEL DEPOSIT, #/CU FT	2.04
AIR REQUIRED	
SCF/CU FT	284.6
MSCF/A-F	12395.
OIL BURNED AS FUEL, B/A-F	266.
AIR-OIL RATIO, MSCF/B	9.29
AIR-FUEL RATIO, SCF/LB	140.
FRACTION OF OXYGEN UTILIZED	.66
MOLE WEIGHT OF FUEL UNIT	12.21
AVERAGE WATER-AIR RATIO, B/MMSCF	182.09
FINAL WATER-AIR RATIO, B/MMSCF	30.73
AVERAGE COMBUSTION TEMPERATURE, DEGREES F	1361.
TUBE AIR-OIL RATIO, MSCF/B	43.66
% OIL-IN-PLACE RECOVERED	44.88

* LABORATORY PACK CONDITIONS *

SAND WEIGHT, GRAMS	6904.70
OIL WEIGHT, GRAMS	508.00
WATER WEIGHT, GRAMS	21.40
POROSITY, %	46.
OIL SATURATION, %PV	25.
WATER SATURATION, %PV	1.
GAS SATURATION, %PV	74.

* TEST DATA *

TIME	TOTAL GAS	TOTAL OIL	TOTAL WATER	O2 CONC	CO2 CONC	CO CONC	WATER INJECTED
.00	1.80	.00	.00	7.80	9.80	3.60	.00
.28	3.90	.00	.00	3.70	13.60	4.30	.00
1.00	12.80	.00	.00	6.40	10.50	3.20	.00
1.67	21.60	.00	.00	7.00	8.70	2.30	.00
2.13	26.60	.00	200.00	6.00	11.30	3.30	350.00
2.60	32.50	.00	300.00	6.90	11.10	3.50	460.00
3.03	37.80	.00	400.00	7.60	12.90	3.10	510.00
3.42	43.40	.00	525.00	4.70	17.70	3.60	590.00
3.88	48.90	.00	650.00	4.20	16.00	3.90	760.00
4.30	54.10	50.00	727.00	8.00	8.50	4.60	980.00
4.80	61.50	125.00	875.00	10.60	11.80	1.90	1200.00
5.18	67.70	240.00	1020.00	12.20	6.30	1.30	1220.00

* LOCATION OF COMBUSTION ZONE *

TIME	LOCATION	MAX TEMP	TOTAL GAS
.0000	.0000	1530.0000	1.8000
.2833	6.0000	1760.0000	3.9000
1.0000	12.0000	1290.0000	12.8000
1.6667	18.0000	1260.0000	21.6000
2.1333	24.0000	1370.0000	26.6000
2.6333	30.0000	1420.0000	32.5000
3.0333	36.0000	1400.0000	37.8000
3.4167	42.0000	1500.0000	43.4000
3.8833	48.0000	1390.0000	48.9000
4.3000	54.0000	1350.0000	54.1000
4.8000	60.0000	1340.0000	61.5000
5.3500	66.0000	1190.0000	67.7000

UNITED STATES DEPARTMENT OF ENERGY
BARTLESVILLE ENERGY TECHNOLOGY CENTER
P.O. BOX 1398
BARTLESVILLE, OKLAHOMA 74003

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE, \$300

POSTAGE AND FEES PAID
UNITED STATES
DEPARTMENT OF ENERGY

Return this sheet to above address, if you
do NOT wish to receive this material ☐
or if change of address is needed ☐ (indi-
cate change, including ZIP code).