NOTICE

**CERTAIN DATA
CONTAINED IN THIS
DOCUMENT MAY BE
DIFFICULT TO READ
IN MICROFICHE
PRODUCTS.**

Closure Plan for Solid Waste Storage Area 6

Volume 1: Closure Plan

August 1988

Oak Ridge National Laboratory
Remedial Investigation/Feasibility Study

U. S. Department of Energy
Oak Ridge Operations Office

Prepared by

Bechtel National, Inc.

CH2M Hill • EDGe • PEER

for

Oak Ridge National Laboratory

Operated by

Martin Marietta Energy Systems, Inc.

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

ORNL/RAP/Sub--87/99053/9-V1/R1

DE92 010426

CLOSURE PLAN
FOR
SOLID WASTE STORAGE AREA 6

VOLUME 1: CLOSURE PLAN

AUGUST 1988

OAK RIDGE NATIONAL LABORATORY
REMEDIAL INVESTIGATION/FEASIBILITY STUDY

Date Published - September 1988

Report Prepared by
Bechtel National, Inc.
P. O. Box 350
Oak Ridge, Tennessee 37830
under
Subcontract 30B-99053C

for

Oak Ridge National Laboratory
Oak Ridge, Tennessee 37831

Operated by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U.S. DEPARTMENT OF ENERGY
under Contract DE-AC05-84OR21400

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

TABLE OF CONTENTS

	<u>Page</u>
A. Introduction	A-1
A.1 Applicable U. S. Department of Energy Regulations	A-2
A.2 Applicable State and Federal Regulations	A-3
B. Facility Description	B-1
B.1 General Description	B-1
B.1.a Trenches	B-4
B.1.b Auger Holes	B-6
B.1.c Demolition Landfill	B-7
B.1.d Engineered Test Facility	B-7
B.1.e Engineered Control Structures	B-7
B.1.f Regulatory Actions	B-9
B.2 Location Information	B-13
B.2.a Topographic Map	B-13
B.2.b Seismic Considerations	B-13
B.2.c Floodplain Standard	B-13
B.3 Traffic Information	B-16
C. Waste Characteristics	C-1
C.1 General Description	C-1
C.2 Hazardous Characteristics	C-13
C.3 Analytical Results	C-14
C.4 Waste Analysis Plan	C-43
D. Closure Requirements	D-1
D.1 Introduction and Overview of Strategy	D-1
D.2 Corrective Action-Related Activities and Scheduling	D-4
E. Closure Plan	E-1
E.1 Closure Performance Standard	
40 CFR 265.111, TN Rule 1200-1-11-.05(7)(b)	E-1
E.2 Closure Activities	
40 CFR 265.112(b), TN Rule 1200-1-11-.05(7)(c)	E-2
E.3 Maximum Waste Inventory	
40 CFR 265.112(a)(2)	
TN Rule 1200-1-11-.05(7)(c)(2)(iii)	E-3
E.4 Inventory Removal; Disposal or Decontamination of Equipment	
40 CFR 265.112(a)(3), 40 CFR 265.114	
TN Rule 1200-1-11-.05(7)(c)(iv)	E-3
E.5 Closure of Disposal Areas	
40 CFR 265.310, 40 CFR 265.112	
TN Rule 1200-1-11-.05(7)(c)(2)	
TN Rule 1200-1-11-.05(14)(e)	E-5
E.5.a Interim Corrective Measure for RCRA-Regulated Areas	E-6
E.5.b RCRA Facility Investigation	E-9
E.5.c Supporting Projects	E-11
E.5.d RCRA Corrective Measure Study	E-14

TABLE OF CONTENTS (Continued)

	<u>Page</u>
E.5.e Record of Decision	E-15
E.5.f Final Closure and Corrective Actions	E-16
E.6 Other Activities Related to Closure	
40 CFR 265.112, TN Rule 1200-1-11-.05(7)(c)(2)(v)	E-17
E.7 Schedule for Closure	
40 CFR 265.112(a)(4)	
TN Rule 1200-1-11-.05(7)(c)(vi)	E-18
F. Groundwater Monitoring	
40 CFR 265.90, TN Rule 1200-1-11.05(7)(c)(2)(v)	F-1
F.1 Exemption from Groundwater Protection Requirements	F-1
F.2 Interim Status Period Groundwater Monitoring Data	F-1
F.3 Aquifer Identification	F-3
F.3.a Regional and Site Geologic Setting	F-3
F.3.b Regional and Site Groundwater Setting	F-8
F.4 Contaminant Plume Description	F-11
F.5 Detection Monitoring Program	F-13
F.5.a Indicator Parameters, Waste Constituents, Reaction Products to be Monitored	F-13
F.5.b Groundwater Monitoring Program	F-14
F.5.c Background Values	F-14
F.5.d Sampling, Analysis, and Statistical Procedures	F-14
F.5.e Compliance Monitoring Program	F-15
F.5.f Corrective Actions Program	F-16
G. Post-Closure Activities	G-1
G.1 Post-Closure Plan	G-1
G.1.a Inspection Plan	G-1
G.1.b Monitoring Plan	G-1
G.1.c Maintenance Plan	G-1
G.2 Notice to Local Land Authority	G-2
G.3 Notice in Deed to Property	G-2
G.4 Closure Cost Estimate	G-2
G.5 Financial Assurance Mechanism for Closure	G-2
G.6 Post-Closure Cost Estimate	G-2
G.7 Financial Assurance Mechanism for Post-Closure	G-3
G.8 Liability Requirements	G-3
G.9 State Financial Mechanism	G-3
H. Certification	H-1
References	R-1

LIST OF EXHIBITS

<u>Exhibit</u>	<u>Title</u>	<u>Page</u>
B.1a-B.1d	Trench and Auger Hole Locations	B-3
B.2	RCRA-Regulated Auger Holes and Trenches at SWSA 6	B-11
B.3	SWSA 6 100-Year Floodplain	B-14
B.4	1987 Annual Wind Rose at 30-m Level of Meteorological Tower 4	B-15
C.1	Location Map of SWSA 6 Indicating Trenches and Auger Holes Containing Lead, Xylene, and Toluene	C-2
C.2	Tenches Containing Scintillation Vials	C-3
C.3	Summary of Radioactive Waste Inventory for SWSA 6 Trenches and Auger Holes	C-4
C.4	Chemically Hazardous Waste Contaminants Detected in SWSA 6	C-15
C.5	Location Map of Documented HHMS, Piezometers, and Water Quality Wells at WAG 6	C-18
C.6	Location of Piezometers and Wells Sampled During 1986-1987 Characterization Effort at SWSA 6	C-20
C.7	Field Parameters for Leachate and Groundwater Samples	C-21
C.8	Inductively Coupled Plasma Spectrometric Analyses of Leachate and Groundwater Samples	C-23
C.9	Chemical, Ion Chromatographic, and Atomic Absorption Analyses of Leachate and Groundwater Samples	C-26
C.10	Priority Pollutants Found in Leachate and Groundwater Samples in SWSA 6	C-30
C.11	Radiochemical Analyses of Leachate and Groundwater Samples	C-33
C.12	Location of Surface Water Monitoring Points at WAG 6	C-38
C.13	Engineered Test Facility Surface Water Quality	C-39

LIST OF EXHIBITS
(Continued)

<u>Exhibit</u>	<u>Title</u>	<u>Page</u>
C.14	Results of Radiological Analyses of Surface Water at Selected Sites in SWSA 6	C-41
E.1	Overall Schedule for Closure of SWSA 6	E-20
E.2	Detailed Illustration of Activities for Closure of SWSA 6	E-21
F.1a&b	RCRA Well Locations	F-2
F.2	Generalized Geologic Map of the ORNL Study Area	F-5
F.3	Stratigraphic Column for Geologic Formations on the Base of the Copper Creek Thrust Sheet	F-6
F.4	Generalized Geologic Cross Section of Melton Valley	F-7

ACRONYMS

AEA	Atomic Energy Act
ACL	Alternate Concentration Limit
BNI	Bechtel National, Inc.
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
CMS	Corrective Measures Study
CY	Calendar Year
DO	Dissolved Oxygen
DOE	U.S. Department of Energy
EMC	Environmental Monitoring and Compliance
EPA	U.S. Environmental Protection Agency
ETF	Engineered Test Facility
EWB	Emergency Waste Basin
HDPE	High Density Polyethylene
HHMS	Hydrostatic Head Monitoring Station
HSWA	Hazardous Solid Waste Amendments
ICM	Interim Corrective Measure
IT	International Technology Corporation
LLW	Low-level Waste
NIPDWS	National Interim Primary Drinking Water Standards
NPDES	National Pollutant Discharge Elimination Standard
NRC	Nuclear Regulatory Commission
ORNL	Oak Ridge National Laboratory
ORR	Oak Ridge Reservation
PVC	Polyvinyl Chloride
RCRA	Resource Conservation and Recovery Act
RFA	RCRA Facility Assessment
RFI	RCRA Facilities Investigation
RI	Remedial Investigation
ROD	Record of Decision
SWMU	Solid Waste Management Unit
SWSA	Solid Waste Storage Area
TARA	Test Area for Remedial Actions
TCE	Trichloroethylene

ACRONYMS
(Continued)

TCL	Target Compound List
TDHE	Tennessee Department of Health and Environment
TDSWM	Tennessee Division of Solid Waste Management
TEGD	Technical Enforcement Guidance Document
TRU	Transuranic Waste
WAG	Waste Area Grouping
WOC	White Oak Creek

ABBREVIATIONS

Bq/L	Bequerels per liter
Ci	Curie
cm	centimeter
ft	feet
gal	gallon(s)
hr	hour(s)
in.	inch
lb	pound(s)
m/sec	meters per second
mg/L	milligrams per liter
mM	millimoles
mR/hr	milliroentgen per hour
ug/L	micrograms per liter
umhos/cm	micromhos per centimeter
ppm	parts per million
V	volt
yd ³	cubic yards
yr	year(s)

A. INTRODUCTION

This Closure Plan for Solid Waste Storage Area 6 (SWSA 6) of the U.S. Department of Energy (DOE) Oak Ridge National Laboratory (ORNL) describes how portions of SWSA 6 will be closed under Resource Conservation and Recovery Act (RCRA) Interim Status per 40 CFR 265 Subpart G [TN Rule 1200-1-11-.05(7)] and provides an overview of activities necessary for final closure and corrective measures for all of SWSA 6. Detailed information is provided in the appropriate sections of this closure plan.

During more than 40 yrs of production and research activities at ORNL, many radioactive, hazardous, and mixed (combination of hazardous and radioactive) wastes have been generated. These wastes have been disposed both on-site and off-site.

SWSA 6 was opened in 1969 as a shallow land burial site for low-level radioactive and nonradioactive wastes. Wastes were disposed in unlined trenches and auger holes until May 1986, at which time the site was closed by the DOE when it was found that RCRA-regulated wastes were being disposed there. The site, which was reopened in July 1986 following numerous changes in operations (including cessation of RCRA waste disposal), is the only currently operating disposal area for low-level radioactive waste at ORNL.

Until recently, the physical and chemical natures of the disposed wastes have been poorly documented, and packaging of wastes has been highly variable, ranging from no containerization to plastic bags to stainless steel drums. Through May 1986, approximately 29,000 m³ of low-level waste containing more than 200,000 Ci of radioactivity had been buried at SWSA 6. Records pertaining to nonradioactive wastes disposed there are minimal to nonexistent; however, it is estimated that about 25 percent of the acreage could have received some RCRA-regulated waste. A detailed description of SWSA 6 is provided in Section B.

Those areas that received hazardous and/or mixed wastes after November 8, 1980, are explicitly designated as RCRA "regulated units." By law, closure of regulated areas under 40 CFR 265 Subpart G must be initiated by November 8, 1988. This Closure Plan for SWSA 6 is being submitted in response to this requirement.

Covering the site with a RCRA cap is not a feasible alternative at this time because of trench subsidence, incompatibility with potential final closure options, and possible impence of the RCRA Facilities Investigation (RFI), which is essential to site characterization for final closure.

Installation of a high density polyethylene (HDPE) cover as an interim corrective measure for the RCRA-regulated areas in SWSA 6 will be initiated no later than November 8, 1988. Details of this installation are presented in the Interim Corrective Measure Design by Lockwood Greene (Volume 2 of this Closure Plan). The rationale, activities, and schedule for closure of all of SWSA 6 are discussed in detail in Sections D and E of this document.

A.1 APPLICABLE U.S. DEPARTMENT OF ENERGY REGULATIONS

The principle regulation governing management of mixed wastes at ORNL is DOE Order 5480.2, Hazardous and Radioactive Mixed Waste Management. These procedures follow, to the extent practicable, regulations issued by the U.S. Environmental Protection Agency (EPA) pursuant to RCRA. In addition, other DOE Orders have supplemental and related requirements. Assurance that hazardous waste is managed in an environmentally acceptable manner is part of the overall environmental protection, safety, and health protection program established by DOE Order 5480.1A. This order contains requirements to ensure that all DOE operations involving generation, transportation, treatment, storage, and/or disposal of all hazardous wastes are conducted in a manner that will protect public health and safety. Other relevant DOE orders include, but are not limited to:

DOE Order 1540.2 Hazardous Material Packaging for Transport
DOE Order 5484.2 Unusual Occurrence Reporting System
DOE Order 5700.6 Quality Assurance
DOE Order 5820.2 Radioactive Waste Management
DOE Order 5500.2 Emergency Planning, Preparedness, and Response
 and Operations

A.2 APPLICABLE STATE AND FEDERAL REGULATIONS

In addition to DOE orders, mixed wastes at ORNL are also regulated by the EPA and the Tennessee Department of Health and Environment (TDHE) as a result of Executive Order 12088, Federal Compliance with Pollution Control Standards, signed in October 1978. This mandated that all federal facilities comply with rules and regulations promulgated by the EPA and/or the state based upon applicable pollution control standards.

In the past, regulatory guidance for dealing with radioactive wastes and chemically hazardous wastes has generally been addressed in separate regulations. Under current federal law, mixed wastes are subject to regulation by the Nuclear Regulatory Commission (NRC) under the Atomic Energy Act (AEA) and by the EPA under the AEA and RCRA, as amended. Management and disposal of mixed waste must be conducted in compliance with NRC and EPA, and/or equivalent state regulations. NRC rules and licensing requirements currently have no direct impact on operations at ORNL or other DOE sites.

On May 1, 1987, DOE published a final interpretive rule to further clarify responsibility for mixed wastes under RCRA, effective June 1, 1987. The rule adopts a narrower interpretation of byproduct material, which is excluded from RCRA regulation under Section 11e(2) of the AEA. Only the actual radionuclides in DOE waste streams will be considered byproduct material. The nonradioactive components of those waste streams will now be subject to regulation under RCRA to the extent that they contain chemically hazardous components (10 CFR 962).

SWSA 6 became a RCRA-regulated unit in April 1986 when ORNL revised its Part A Application to reflect the hazardous waste disposed there (ORNL, 1986).

The RCRA-regulated areas in SWSA 6 will be closed in accordance with 40 CFR 265 Subpart G (265.111) [TN Rule 1200-1-11-.05(7)(b)], Closure and Post-Closure Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities. These rules require that facilities be closed in a manner that: 1) minimizes the need for further maintenance, and 2) controls, minimizes, or eliminates to the extent required to protect human health and the environment, post-closure escape of hazardous waste, hazardous constituents, leachate, contaminated runoff, or hazardous waste decomposition products to the environment.

In addition to the RCRA closure requirement, there are other regulations pertinent to SWSA 6. The Hazardous and Solid Waste Amendments (HSWA) to RCRA, passed by Congress on November 8, 1984, require any facility seeking a RCRA permit to conduct a corrective action program for releases of hazardous wastes or constituents from Solid Waste Management Units (SWMUs). Specifically relevant to SWSA 6 are: 1) RCRA Section 3004(u), requiring corrective action for releases of hazardous wastes or constituents from any SWMU, regardless of the time at which the waste was placed in the unit; and 2) RCRA Section 3004(v), requiring corrective action beyond the facility property boundary, where it is necessary to protect human health and the environment.

In addition to the closure/post-closure and corrective action programs implemented under RCRA, those waste management areas within SWSA 6 in which only radioactive wastes were disposed must be closed under separate regulatory programs. Because these radioactive waste management areas are interspersed with the hazardous waste management areas in SWSA 6, it is technically infeasible to close them individually.

In view of the physical and regulatory complexities involved at SWSA 6, the ORNL believes that a single, detailed, and comprehensive plan leading to closure and corrective actions for all of the disposal areas within SWSA 6 will result in the most effective, implementable, and timely action for long-term protection of human health and the environment.

B. FACILITY DESCRIPTION

B.1 GENERAL DESCRIPTION

The ORNL, which is located about 25 mi west of Knoxville, Tennessee, began operations in 1943 as a part of the Manhattan Project for atomic weapons research and development. The scope of operations at ORNL has changed over the years. Today the principal focus is on the development of civilian uses of nuclear technologies and the application of non-nuclear energy sources (National Research Council, 1985). The facility, which is currently operated by Martin Marietta Energy Systems, Inc. (Energy Systems), for the DOE is part of the Oak Ridge Reservation (ORR). The Oak Ridge Gaseous Diffusion Plant and the Y-12 Plant are the other major facilities within the ORR.

The street address of ORNL is:

Oak Ridge National Laboratory
Bethel Valley Road
Oak Ridge, Tennessee 37831

The mailing address is:

Oak Ridge National Laboratory
P. O. Box 2008
Oak Ridge, Tennessee 37831

Individuals responsible for the hazardous waste and mixed waste management activities are the Supervisor of Hazardous Waste Operations, telephone number (615) 576-1779, and the Supervisor of Solid Waste Operations, telephone number (615) 574-7150. The EPA HSWA facility number is TN1 890090003.

Normal operations at ORNL have generated radioactive, chemically hazardous, and mixed (both radioactive and chemically hazardous)

wastes. Many of these wastes, as well as some produced at locations other than Oak Ridge, have been disposed in shallow burial sites within the ORR (Shoun, 1987). SWSA 6 is the only currently operating disposal site at ORNL for radioactive waste.

SWSA 6 was opened for limited disposal in 1969 and began full-scale operations in 1973. The materials disposed there consist of a broad spectrum of wastes generated from virtually every operational and research activity conducted at ORNL since the inception of SWSA 6. The wastes included laboratory glassware and equipment, protective apparel, worn-out or obsolete mechanical equipment, construction materials, filter media and resins, radioactive wastes, animal remains, and contaminated earth. Until 1986 the physical and chemical characteristics of the wastes were poorly documented. Moreover, packaging was highly variable, ranging from plastic bags to stainless-steel drums to no containerization at all (IT, 1986).

Through May 1986, approximately 312,000 ft³ of low level waste containing more than 200,000 Ci of radioactivity were buried at SWSA 6. Records pertaining to chemically hazardous wastes disposed there are minimal to nonexistent; however, it is estimated that about 25 percent of the acreage used for waste disposal could have received some RCRA-regulated waste.

SWSA 6 contains more than 1000 trenches and auger holes (see Exhibits B.1.a - B.1.d). Trenches are assigned to one of the following categories depending upon the waste placed in them: 1) high activity, 2) low activity, 3) biological, 4) asbestos, 5) baled, 6) fissile, 7) high-activity concrete lined, and 8) low-activity concrete lined. Auger holes have been classified as one of three types, depending upon their waste content: 1) high-activity, 2) solvent, or 3) fissile (Davis and Solomon, 1987). Until May 1986, all trenches and most auger holes were unlined. Since that time, all disposal of radioactive waste has been in greater confinement disposal units, which isolate the waste from the hydrologic environment and, therefore, reduce the potential

wastes. Many of these wastes, as well as some produced at locations other than Oak Ridge, have been disposed in shallow burial sites within the ORR (Shoun, 1987). SWSA 6 is the only currently operating disposal site at ORNL for radioactive waste.

SWSA 6 was opened for limited disposal in 1969 and began full-scale operations in 1973. The materials disposed there consist of a broad spectrum of wastes generated from virtually every operational and research activity conducted at ORNL since the inception of SWSA 6. The wastes included laboratory glassware and equipment, protective apparel, worn-out or obsolete mechanical equipment, construction materials, filter media and resins, radioactive wastes, animal remains, and contaminated earth. Until 1986 the physical and chemical characteristics of the wastes were poorly documented. Moreover, packaging was highly variable, ranging from plastic bags to stainless-steel drums to no containerization at all (IT, 1986).

Through May 1986, approximately 312,000 ft³ of low level waste containing more than 200,000 Ci of radioactivity were buried at SWSA 6. Records pertaining to chemically hazardous wastes disposed there are minimal to nonexistent; however, it is estimated that about 25 percent of the acreage used for waste disposal could have received some RCRA-regulated waste.

SWSA 6 contains more than 1000 trenches and auger holes (see Exhibits B.1.a - B.1.d). Trenches are assigned to one of the following categories depending upon the waste placed in them: 1) high activity, 2) low activity, 3) biological, 4) asbestos, 5) baled, 6) fissile, 7) high-activity concrete lined, and 8) low-activity concrete lined. Auger holes have been classified as one of three types, depending upon their waste content: 1) high-activity, 2) solvent, or 3) fissile (Davis and Solomon, 1987). Until May 1986, all trenches and most auger holes were unlined. Since that time, all disposal of radioactive waste has been in greater confinement disposal units, which isolate the waste from the hydrologic environment and, therefore, reduce the potential

EXHIBITS B.1a - B.1d

Trench and Auger Hole Locations
(See Pockets, End of Document)

Drawing Numbers:

06-SK-07

06-SK-08

06-SK-09

06-SK-10

for waste leachate formation. No chemically hazardous wastes have been disposed in SWSA 6 since May 1986.

Suspect waste (no measurable contamination but not releasable to a sanitary landfill) is placed in a demolition landfill located within SWSA 6. The Engineered Test Facility (ETF), also located within SWSA 6, is currently used as a research and development area to investigate improved shallow land burial techniques.

B.1.a Trenches

Dimensions of trenches were highly variable depending on topography and trench type, but they generally were approximately 50 ft x 10 ft x 13-20 ft deep. Beginning in 1975, trench depth was limited to approximately 15 ft or less, with the floor of the trench being at least 2 ft above the documented high water table. Minimum spacing between trenches was 5 ft. When the waste level reached approximately 3 ft below the top, the trench was backfilled with soil from the excavation of the next trench. After a group of trenches was backfilled, the area was seeded to minimize erosion (ORNL, 1986).

High activity trenches are concentrated in two areas at the northern edge of the site where distance to the water table is greatest. They occupy about 2 acres, or 3 percent, of the total area of SWSA 6. High-activity trenches were used for disposal of waste with a reading on the surface of the container equal to or greater than 200 mR/h. This waste generally contained beta-gamma activity and/or nonfissile alpha activity. After being placed in the trench, the materials were covered with sufficient soil to lower the radiation reading at the trench surface to 100 mR/hr. Operating time for each high-activity trench was approximately 6 to 8 months. In addition to radioactive waste, at least two high-activity trenches (numbers 120 and 346) contain scintillation fluids composed primarily of xylene and toluene (ORNL, 1986).

Low-activity trenches occupy most of the area in SWSA 6 and are second in number only to biological trenches. Waste disposed there had radiation readings on the surface of the container of less than 200 mR/h and included metal, wood, construction debris, concrete, paper, plastics, apparel, and lead shielding (IT, 1986; ORNL, 1986). These trenches were usually operable for 6-8 weeks. Before June 1985, material was simply dumped into the trenches, but after that time most waste was packaged in plywood boxes or 55-gal steel drums and stacked in the trenches.

Asbestos trenches, which occupy about 0.7 acre, or 1 percent, of the total area, have received both radioactively contaminated and uncontaminated asbestos. Metal dividers were placed about 8 ft apart to conserve space and to prevent fill dirt from spilling into the unused portions of the trench. Disposal of asbestos occurred about once every three to four weeks, and the waste was covered with soil the same day (ORNL, 1986).

Soft waste that was not alpha radioactively contaminated, such as gloves, shoe covers, and blotter paper, was compacted about twice monthly and placed in the compacted-bale trenches. The volume reduction ratio was approximately 8 to 1, and the 10 ft³ bales weighed about 650 lb. Before compaction, the waste was checked to ensure that the radiation reading at contact was less than 200 mR/hr. Compacted bale trenches comprise about 0.15 acre, or 0.2 percent, of the area (ORNL, 1986).

Biological trenches received materials from biomedical laboratories and included carcasses of experimental animals, bedding, excreta, gloves, and shoe covers. Waste was disposed about once a week, and the trench was used for approximately 6 weeks. As in the asbestos trenches, metal dividers were used to conserve space and prevent fill dirt from spilling into unused portions of the trench.

Waste contained in the biological trenches is reported to be primarily low activity, low-level, non-alpha contaminated waste less than, or equal to, 200 mR/h, with most being approximately 5 mR/hr.

However, it is reported that the biological trenches contain the largest volume of scintillation fluids in SWSA 6. Records indicate that between 1972 and 1986 over 12,500 gal of scintillation fluids may have been disposed in 35 biological trenches (ORNL, 1986). The biological trenches comprise the largest group by number. They are distributed throughout four areas of the site, primarily in the central and southern portions, and account for about 3.2 acres, or about 5 percent, of the total area.

B.1.b Auger Holes

Unlined auger holes were used to dispose high-activity, low-level waste with radiation readings at the surface of the unshielded container being equal to, or greater than, 200 mR/hr. Auger holes are divided into three categories: fissile, high-activity, and solvent. These auger holes, which comprise about 1.2 acres, or 1.7 percent, of the total area, were placed in higher elevation areas and measured from about 1 to 4 ft in diameter and 20 ft in depth and were spaced about 3 ft apart. Any material containing uranium-235 is classified as fissile waste; other radionuclides such as cesium-137, uranium-238, or strontium-90 may be mixed with the uranium-235. High-activity auger holes also contain other low-level waste not classified as fissile such as cobalt and tritium. If high-activity waste could physically fit into an auger hole, it was placed there. Containers as large as 55-gal drums were buried there, and three or four disposals were routinely made in a single auger hole. After waste disposal, if the radiation reading was greater than 100 mR/hr, soil was backfilled until a reading of 100 mR/hr or less was observed. When the waste neared the surface of the hole, approximately 1 ft of soil was spread on top of the waste. The hole was then capped with 1 ft of concrete and brought to ground level with additional soil (ORNL, 1986).

Before 1980, solvent auger holes received a variety of chemical wastes, some of which were radioactively contaminated. Exact volumes

disposed are not known, but wastes included oils, cleaning solutions, alcohols, paint thinners, kerosene, jet fuel, acids, and sodium.

B.1.c Demolition Landfill

The low hazard ("suspect") waste demolition landfill is located in the northeastern portion of the site and covers approximately 5 acres. Waste is shredded to reduce its volume before being placed in the landfill and then covered with soil. Reportedly, about 5000 ft³/yr of suspect waste have been disposed here (ORNL, 1986). This waste has no measurable surficial radiological contamination but has been judged by the generator to be radioactively contaminated above ORNL "Health Physics Material Transfer Clearance Tag" (free of radiation or contamination hazards) limits or to be such that some areas (such as the inside of pipes) cannot be surveyed.

B.1.d Engineered Test Facility (ETF)

The ETF, which is located in the western part of SWSA 6, is a research and development area established by ORNL. Its purpose is to investigate improved shallow land burial technology for disposal of low-level waste (LLW) in humid environments. The ETF consists of trenches that contain low-activity baled waste with radiation readings of less than 200 mR/hr at the package surface. Investigations have focused on disposal techniques, methods for site characterization, and integration of site characterization data into site model development and application (ORNL, 1986).

B.1.e Engineered Control Structures

SWSA 6 does not presently have an engineered surface water runon and runoff control system (design for the runon/runoff control system for areas included in the interim corrective measure is shown in Volume 2 of this Closure Plan). However, the siting of individual burial areas with respect to topography and natural drainageways generally provides a degree of control of surface water runon. For

example, most areas either straddle, or are situated near, ridge tops, thus eliminating or minimizing the upgradient drainage area. The steepness of the slopes that dominate SWSA 6 generally provides for rapid runoff. Modifications to the natural drainage patterns include service roads and localized depressions resulting from trench subsidence. Localized depressions are backfilled and seeded to maintain a uniform grade as part of the routine maintenance of SWSA 6. Surface water runoff from the individual burial areas is generally to the natural drainageways which feed to White Oak Lake. White Oak Lake serves as a detention basin for the settlement of suspended sediments prior to discharge through a National Pollutant Discharge Emission System (NPDES) monitoring station at White Oak Dam to the Clinch River.

Historically, wind dispersal of materials disposed in SWSA 6 unlined trenches was controlled by the seeded soil cap placed over the solid waste in each trench as the trench surface was brought to the grade of the surrounding ground surface. The soil cap generally consisted of a minimum of 24 in. of natural soil, which was seeded for erosion protection. Control of wind dispersal of wastes disposed in unlined auger holes was also provided by a cap/plug. As described earlier, part of routine maintenance of SWSA 6 involves backfilling and reseeding depressions resulting from subsidence or collapse of trench covers; such maintenance assures that the potential for wind dispersal is minimized during operations at SWSA 6.

Wastes in SWSA 6 were primarily buried above the maximum permanent water table. However, records indicate that liquid wastes emplaced there were often poorly containerized. As containers degrade, liquids will enter the trenches and auger holes, enhancing the potential for contaminant migration. Circumstances that can contribute to liquid in landfills are discussed below (ORNL, 1986).

1. Rain or surface runoff from surrounding areas enters open waste-disposal trenches during the period that the trenches are receiving wastes. Berms are constructed around open trenches to divert runoff, so direct entry of runoff should occur only when diversion berms are breached.

2. Precipitation or runoff can infiltrate through the trench cap, particularly through subsidence cracks or depressions.
3. Some waste may come into direct contact with groundwater in waste disposal units that intersect a high water table.
4. Lateral inflow of subsurface stormflow may occur above the permanent water table (i.e., the surface below which all voids are saturated and at which water is under atmospheric pressure) when infiltrated precipitation becomes perched and moves downslope or downdip along fracture zones, soil "pans", bedding planes, or other macropore features.

Field observation suggests that all of these mechanisms contribute water to SWSA 6 waste trenches. Saturated conditions have been observed in the lower portions of many trenches (Webster, 1976), and water levels in trenches tend to be higher than the water table in surrounding wells (Davis and Stansfield, 1984). This may indicate that water infiltrates through trench caps (e.g., as a result of differential settlement of wastes and subsequent cracking of trench caps) as well as through adjoining soils where lateral inflows collect in the waste trenches in the aftermath of storm events. Groundwater analyses of trench leachate have been conducted from samples obtained in wells placed in trenches or in wells installed immediately adjacent to a trench or auger hole area. The leachate data have been used to provide information about waste constituents that have gone into solution when water has infiltrated a trench and directly contacted the waste.

B.1.f Regulatory Actions

In May 1986, SWSA 6 was temporarily closed to further burial operations by DOE, pending investigation of the potential disposal in some trenches of wastes regulated by the RCRA. Estimates from waste disposal records indicated that 25 percent of the disposal acreage might have received some RCRA-regulated wastes, which were thought to be principally lead, xylene, and toluene. After several changes in operating procedures, SWSA 6 was reopened for disposal of radiological waste in July 1986.

Designating SWSA 6 as a RCRA-regulated mixed waste site resulted in additional compliance needs to meet regulatory requirements. A Closure Plan (IT, 1986) was drafted in September 1986 to satisfy applicable EPA and TDHE regulations [40 CFR 265, Subpart G, and TDHE Rule 1200-1-11.05(7), "Rules Governing Hazardous Waste Management in Tennessee"].

As part of the original Closure Plan, preparation and implementation of a Remedial Investigation (RI) Plan was recommended to determine the need for remedial measures at the site, the extent of the remediation required, and the risk to health and environment from contaminants at the site. In December 1986, an RI Plan (ORNL, 1986) prepared by ORNL was submitted to the EPA and the TDHE for review and approval. During 1986-1987, ORNL conducted field investigations to characterize the site and to partially fulfill the data needs addressed in the RI Plan (Davis et al., 1987; Solomon et al., 1987).

A "Notice of Intent to Close a Hazardous Waste Management Unit" was made public by the TDHE, with comments from interested persons being due by October 30, 1987. The 1986 Closure Plan for SWSA 6 was reviewed by TDHE and deemed unacceptable (Ledford, 1988). Consequently, this Closure Plan is being prepared to fulfill EPA and TDHE directives requiring that closure of the RCRA-regulated areas within SWSA 6 be initiated by November 1988.

Exhibit B.2 lists the individual trenches and auger holes that are subject to regulation under RCRA (see Exhibits B.1a - B.1d for locations of these disposal sites). Those areas delineated in Exhibit B.2 may have received hazardous and/or mixed wastes between November 8, 1980, and May 1986, after which time no further RCRA-regulated wastes were disposed in SWSA 6.

While this document is intended to provide specific information regarding the proposed interim corrective measures for initiation of closure for the RCRA-regulated areas, an overall strategy and schedule is also presented that details a continuous closure effort

EXHIBIT B.2

RCRA-REGULATED AUGER HOLES AND TRENCHES
AT SWSA 6Auger Holes

W253	W254	W255	W256	W257	W258	W259
W260	W261	W262	W263	W264	W265	W266
W267	W273	W274	W275	W276	W277	W278
W279	W280	W281	W282	W283	W284	W285
W286	W287	W288	W289	W290	W291	W292
W293	W294	W295	W296	W297	W298	W299
W300	W301	W303	W304	W305	W306	W307
W308	W309	W310	W311	W312	W313	W314
W315	W316	W317	W318	W319	W320	W321
W322	W323	W324	W325	W326	W327	W328
W329	W330	W331	W332	W333	W334	W335
W336	W337	W339	W340	W341	W342	W343
W344	W345	W346	W347	W348	W349	W350
W351	W352	W353	W354	W355	W356	W357
W358	W359	W360	W361	W362	W363	W364
W365	W366	W367	W368	W369	W370	W371
W372	W373	W374	W375	W376	W377	W378
W379	W380	W381	W382	W383	W384	W385
W386	W387	W388	W389	W390	W391	W392
W393	W394	W395	W396	W397	W398	W399
W400	W401	W402	W403	W404	W405	W406
W407	W408	W409	W410	W411	W412	W413
W414	W415	W416	W417	W418	W419	W420
W421	W422	W423	W424	W425	W426	W427
W428	W429	W430	W431	W432	W433	W434
W435	W436	W437	W438	W439	W440	W441
W442	W443	W444	W445	W446	W447	W448
W449	W450	W451	W452	W453	W454	W455
W456	W457	W458	W459	W460	W461	W462
W463	W464	W465	W466	W467	W468	W469
W470	W471	W472	W473	W474	W475	W476
W477	W478	W479				

EXHIBIT B.2 (Continued)

<u>Trenches</u>						
120	307	309	310	311	312	313
314	316	317	318	319	320	321
322	323	324	326	327	328	329
330	331	332	333	343	345	346
347	348	352	353	355	356	357
358	359	360	361	362	363	365
366	367	368	369	370	371	373
374	375	376	377	378	379	380
381	383	384	385	386	387	388
389	390	391	392	396	397	398
400	401	402	403	404	405	406
407	408	409	416	417	418	419
420	422	423	424	427	428	429
431	433	434	435	436	437	438
439	440	441	442	443	444	445
446	447	448	449	450	451	452
453	454	456	458	459	460	462
463	464	465	466	468	470	471
472	473	474	476	477	478	479
480	481	482	483	484	485	486
489						

at SWSA 6 beginning with the preparation of this document and concluding with the final closure/corrective measures. Major activities included in this strategy, in addition to the interim corrective measures, are: an RFI; a groundwater treatment and extraction pilot plant study; full-scale testing of grouting, compaction, and capping of waste areas; a corrective measures study; and final remediation/closure of SWSA 6, including (if warranted) groundwater extraction/treatment, waste compaction/stabilization, and final capping of the site. This document is the first in a series of reports that will be prepared to provide the necessary information to complete these efforts. These will include RFI reports, technical memoranda, the CMS Report, work plans, and design plans.

B.2 LOCATION INFORMATION

B.2.a Topographic Map

Exhibits B.3 and B.4 are submitted to comply with the general requirements of the Tennessee Division of Solid Waste Management (TDSWM). Exhibit B.3 illustrates the floodplain and the location of facilities in accordance with TDSWM Rule 1200-1-11-.07(5)(a)(17). Exhibit B.4 is a wind rose in compliance with TDSWM Rule 1200-1-11-.07(5)(a)17(v).

B.2.b Seismic Considerations

All hazardous waste storage facilities in the State of Tennessee are excluded from regulation under the seismic standard per 40 CFR 264, Appendix VI.

B.2.c Floodplain Standard

The elevation at SWSA 6 ranges from approximately 742 ft to 860 ft above mean sea level, and the 100-yr, 24-hr flood elevation for the area is 754 ft. Examination of Exhibit B.3 shows that two small areas in the southern portion of SWSA 6 near White Oak Lake have

EXHIBIT B.3

**SWSA 6 100-Year Floodplain
(See Pocket, End of Document)**

Drawing Number:

06-SK-11

84.9% OF POSSIBLE DATA

SOURCE: Developed from ORNL DRAWING NO. 88-7361

EXHIBIT B.4 1987 ANNUAL WIND ROSE AT 30-METER LEVEL OF METEOROLOGICAL TOWER 4

elevations lower than the 100-yr flood range and, therefore, could become inundated.

The affected area includes only about 2 ft of trenches, fencing, culverts, and roads. SWSA 6 is the only SWMU within WAG 6 to fall within the 100-yr floodplain. The results of the RFI will be used to determine the most appropriate means of preventing flooding in those sections of SWSA 6 that are below the 100-yr flood elevation. It is anticipated that such corrective measures will be implemented as part of the closure of SWSA 6; however, if there is evidence of imminent risk to human health and the environment, corrective actions will be initiated before final closure of SWSA 6.

B.3 TRAFFIC INFORMATION

SWSA 6 can be reached via the SWSA 6 Access Road from Lagoon Road, which intersects State Highway 95. The entrance to SWSA 6 is controlled by a locked gate, and unauthorized personnel are not permitted entry.

C. WASTE CHARACTERISTICS

C.1 GENERAL DESCRIPTION

A variety of radioactive and chemically hazardous wastes has been disposed in SWSA 6. However, information available from the Waste Disposal Log on the identity and quantity of radionuclides disposed in SWSA 6 may be of limited usefulness (Davis and Solomon, 1987), and information on chemically hazardous waste is minimal. Assessing the potential for contaminant migration is further complicated by variation in types of containers. As the packaging disintegrates, contaminants will be released, but the quantity and rate of release are likely to be quite variable.

Despite the inherent problems, information that is available can be used to produce a general profile of the waste inventory in SWSA 6. The hazardous chemicals of principal interest are believed to be lead, xylene, and toluene. Both low-activity and high-activity trenches have received waste containing lead, which was used for containerization and/or shielding of radioactive waste to facilitate safe handling during research and disposal (see Exhibit C.1). It is estimated that approximately 150,000 lb of lead have been buried in SWSA 6 since early 1980 (IT, 1986). The biological trenches contain the largest volume of xylene and toluene, which are components of scintillation fluids; however, at least two high-activity trenches (120 and 346) are also listed as containing scintillation fluids. Those trenches listed in Exhibit C.2 are known to have received scintillation vials, but other trenches and auger holes may also have been recipients of RCRA-regulated wastes. Since 1972, it is estimated that more than 12,000 gal of scintillation fluids have been disposed in SWSA 6 (ORNL, 1986).

Examination of the Waste Disposal Log indicates that as of May 1986, more than 200,000 Ci had been emplaced in SWSA 6. Exhibit C.3 lists the estimated number of curies by trench and auger hole. Major radionuclides include cobalt-60, tritium, strontium-90, cesium-137, europium-152, europium-154, europium-155, and uranium-235; it is

LEGEND

- BUILDING 7842
- PAVED ROADS
- GRAVEL ROADS
- FENCE
- STREAM
- MARSHY AREA
- ASPHALT CAP
- AVAILABLE SPACE
- EXPERIMENTAL
- BIOLOGICAL
- LOW-ACTIVITY TRENCH
- HIGH-ACTIVITY TRENCH
- ASBESTOS
- AUGER HOLES
- BALED
- LANDFILL AREA
- HIGH-ACTIVITY CASKS

TRENCHES CONTAINING LEAD,
XYLENE, AND TOLUENE

- 1 LEAD
- 2 XYLENE, TOLUENE
- 3 LEAD, XYLENE,
TOLUENE

EXHIBIT C.1
LOCATION MAP OF SWSA 6
INDICATING TRENCHES AND
AUGER HOLES CONTAINING
LEAD, XYLENE, AND TOLUENE

EXHIBIT C.2

TRENCHES CONTAINING SCINTILLATION VIALS

<u>Trench No.</u>	<u>Trench Waste Category</u>
120	High-activity
310	Biological
311	Biological
314	Biological
317	Biological
318	Biological
320	Biological
321	Biological
324	Biological
326	Biological
328	Biological
329	Biological
331	Biological
332	Biological
345	Biological
346	High-activity
347	Biological
352	Biological
353	Biological
356	Biological
358	Biological
359	Biological
360	Biological
362	Biological
365	Biological
366	Biological
367	Biological
369	Biological
373	Biological
374	Biological
376	Biological
378	Biological
384	Biological
386	Biological
387	Biological
388	Biological
389	Biological

Source: ORNL, 1986

EXHIBIT C.3

SUMMARY OF RADIOACTIVE WASTE INVENTORY
FOR SWSA 6 TRENCHES AND AUGER HOLES

Number	Total Curies	Number	Total Curies	Number	Total Curies
<u>TRENCHES</u>					
1	<0.01	2	Unknown	3	Unknown
4	Unknown	5	Unknown	6	Unknown
7	Unknown	8	Unknown	9	Unknown
10	10.01	11	0.04	12	3.29
13	<0.01	14	Unknown	15	Unknown
16	0.03	17	Unknown	18	16.71
19	0.01	20	0.01	21	Unknown
22	8.01	23	Unknown	24	Unknown
25	Unknown	26	Unknown	27	Unknown
28	Unknown	29	Unknown	30	Unknown
31	Unknown	32	Unknown	33	Unknown
34	Unknown	35	Unknown	36	Unknown
37	Unknown	38	Unknown	39	Unknown
40	Unknown	41	Unknown	42	Unknown
43	Unknown	44	Unknown	45	Unknown
46	Unknown	47	Unknown	48	Unknown
49	Unknown	50	Unknown	51	Unknown
52	Unknown	53	Unknown	54	Unknown
55	Unknown	56	Unknown	57	Unknown
58	Unknown	59	Unknown	60	Unknown
61	Unknown	62	Unknown	63	Unknown
64	2.03	65	<0.01	66	27.67
67	6.51	68	0.40	69	13.80
70	7.02	71	3.32	72	236.26
73	5.50	74	3.69	75	7.01
76	3.36	77	58.32	78	Unknown
79	Unknown	80	4.87	81	5.01
82	6.00	83	9.01	84	13.77
85	4.01	86	8.02	87	50.66
88	6.01	89	Unknown	90	3.57
91	5.81	92	6.00	93	17.00
94	Unknown	95	8.38	96	4.03
97	14.01	98	6.00	99	6.71
100	8.01	101	<0.01	102	11.01
103	20.46	104	7.00	105	16.01
106	Unknown	107	<0.01	108	4.00
109	11.21	110	10.01	111	29.94
112	8.04	113	20.21	114	6.01
115	8.01	116	2.03	117	4.20
118	6.00	119	3.14	120	53.40
121	2.23	122	4.00	123	Unknown
124	Unknown	125	Unknown	126	Unknown
127	Unknown	128	Unknown	129	Unknown

EXHIBIT C.3 (Continued)

Number	Total Curies	Number	Total Curies	Number	Total Curies
130	Unknown	131	Unknown	132	Unknown
133	Unknown	134	Unknown	135	Unknown
136	Unknown	137	Unknown	138	Unknown
139	Unknown	140	Unknown	141	Unknown
142	<0.01	143	Unknown	144	Unknown
145	Unknown	146	Unknown	147	Unknown
148	Unknown	149	Unknown	150	Unknown
151	Unknown	152	Unknown	153	Unknown
154	Unknown	155	Unknown	156	Unknown
157	Unknown	158	Unknown	159	Unknown
160	Unknown	161	Unknown	162	Unknown
163	Unknown	164	Unknown	165	Unknown
166	Unknown	167	Unknown	168	Unknown
169	Unknown	170	Unknown	171	Unknown
172	Unknown	173	Unknown	174	Unknown
175	Unknown	176	Unknown	177	Unknown
178	Unknown	179	Unknown	180	Unknown
181	Unknown	182	Unknown	183	Unknown
184	Unknown	185	Unknown	186	Unknown
187	Unknown	188	Unknown	189	Unknown
190	Unknown	191	Unknown	192	Unknown
193	Unknown	194	Unknown	195	Unknown
196	Unknown	197	Unknown	198	Unknown
199	Unknown	200	Unknown	201	Unknown
202	Unknown	203	Unknown	204	Unknown
205	Unknown	206	Unknown	207	Unknown
208	Unknown	209	Unknown	210	Unknown
211	Unknown	212	Unknown	213	Unknown
214	Unknown	215	Unknown	216	Unknown
217	Unknown	218	Unknown	219	Unknown
220	Unknown	221	Unknown	222	<0.01
223	Unknown	224	Unknown	225	Unknown
226	Unknown	227	<0.01	228	85.08
229	Unknown	230	<0.01	231	Unknown
232	Unknown	233	<0.01	234	Unknown
235	4.20	236	1.01	237	1.68
238	380.03	239	50.05	240	2.14
241	2.02	242	3.02	243	2.63
244	1.01	245	3.16	246	26.70
247	2.93	248	1.24	249	3.03
250	9.06	251	12.62	252	3.02
253	1.05	254	1.01	255	0.03
256	6.01	257	3.03	258	1.11
259	8.00	260	10.03	261	1.04
262	2.00	263	6.00	264	12.00
265	1.17	266	32.64	267	8.05
268	9.01	269	13.29	270	8.33
271	72.13	272	4.62	273	8.03

EXHIBIT C.3 (Continued)

Number	Total Curies	Number	Total Curies	Number	Total Curies
274	11.75	275	6.00	276	12.03
277	1.17	278	3.07	279	12.02
280	8.01	281	9.50	282	22.11
283	1000.01	284	4.00	285	12.01
286	7.25	287	8.01	288	12.02
289	<0.01	290	3.12	291	6.39
292	7.01	293	121.70	294	8.02
295	0.04	296	10.32	297	0.03
298	<0.01	299	<0.01	300	<0.01
301	<0.01	302	0.01	303	8.03
304	293.19	305	4.00	306	1.26
307	29.30	308	4.00	309	1.15
310	5.51	311	2.82	312	31.52
313	3.26	314	7.31	315	Unknown
316	34.10	317	8.00	318	8.03
319	2.73	320	6.08	321	8.01
322	0.58	323	3.18	324	6.02
325	Unknown	326	6.02	327	5.04
328	14.43	329	6.00	330	7.43
331	8.01	332	5.54	333	20.71
334	0.52	335	0.18	336	0.01
337	0.02	338	0.03	339	0.50
340	0.56	341	0.13	342	<0.01
343	5.82	344	<0.01	345	6.00
346	15.60	347	4.02	348	2.85
349	Unknown	350	Unknown	351	Unknown
352	3.00	353	8.02	354	Unknown
355	Unknown	356	8.00	357	7.65
358	6.00	359	10.02	360	8.10
361	8.23	362	3.01	363	1.11
364	Unknown	365	8.02	366	8.03
367	8.04	368	2.67	369	10.02
370	2.00	371	4.29	372	Unknown
373	8.00	374	10.00	375	1.73
376	8.00	377	0.24	378	8.06
379	<0.01	380	0.03	381	0.50
382	<0.01	383	21.40	384	8.00
385	121.51	386	10.00	387	8.00
388	6.00	389	10.00	390	14.50
391	2217.16	392	1.90	393	Unknown
394	<0.01	395	Unknown	396	0.03
397	23.26	398	0.59	399	Unknown
400	54.55	401	12.03	402	10.00
403	1.01	404	8.03	405	50.00
406	2.88	407	<0.01	408	3.57
409	1.14	410	1001.20	411	<0.01
412	Unknown	413	<0.01	414	Unknown
415	Unknown	416	254.57	417	210.70

EXHIBIT C.3 (Continued)

Number	Total Curies	Number	Total Curies	Number	Total Curies
418	5.00	419	2.08	420	0.51
421	<0.01	422	4.00	423	23.12
424	4.13	425	Unknown	426	Unknown
427	3.00	428	6.00	429	7.00
430	0.55	431	236.24	432	0.01
433	<0.01	434	6.00	435	4.00
436	5100.23	437	1.42	438	<0.01
439	10.00	440	13.60	441	2.16
442	14.65	443	1.57	444	3510.20
445	0.17	446	1.54	447	4.93
448	4.00	449	1.43	450	10.00
451	12.00	452	10.01	453	14.00
454	12.00	455	Unknown	456	2.03
457	Unknown	458	0.88	459	500.67
460	5.72	461	Unknown	462	3.24
463	17.87	464	14.20	465	0.10
466	2.02	467	1.10	468	134.00
469	0.14	470	8.89	471	0.02
472	Unknown	473	Unknown	474	Unknown
475	Unknown	476	Unknown	477	Unknown
478	Unknown	479	Unknown	480	Unknown
481	Unknown	482	Unknown	483	Unknown
484	Unknown	485	Unknown	486	Unknown
487	Unknown	488	Unknown	489	Unknown
490	Unknown	491	Unknown	492	Unknown
493	Unknown	494	Unknown	495	Unknown
496	Unknown	497	Unknown	498	Unknown
499	Unknown	500	Unknown	501	Unknown
502	Unknown	503	Unknown	504	Unknown
505	Unknown	506	Unknown	507	Unknown
508	Unknown	509	Unknown	510	Unknown

TOTAL TRENCH INVENTORY

17,404.47

AUGER HOLES

1	0.75	2	Unknown	3	Unknown
4	Unknown	5	Unknown	6	Unknown
7	Unknown	8	Unknown	9	Unknown
10	Unknown	11	Unknown	12	Unknown
13	Unknown	14	Unknown	15	Unknown
16	Unknown	17	Unknown	18	Unknown
19	Unknown	20	Unknown	21	Unknown
22	Unknown	23	Unknown	24	Unknown
25	Unknown	26	Unknown	27	Unknown
28	Unknown	29	Unknown	30	Unknown
31	Unknown	32	Unknown	33	Unknown
34	Unknown	35	Unknown	36	Unknown

EXHIBIT C.3 (Continued)

Number	Total Curies	Number	Total Curies	Number	Total Curies
37	Unknown	38	Unknown	39	Unknown
40	Unknown	41	Unknown	42	Unknown
43	Unknown	44	Unknown	45	Unknown
46	Unknown	47	Unknown	48	Unknown
49	Unknown	50	Unknown	51	Unknown
52	Unknown	53	Unknown	54	Unknown
55	Unknown	56	Unknown	57	Unknown
58	Unknown	59	Unknown	60	Unknown
61	Unknown	62	Unknown	63	Unknown
64	Unknown	65	Unknown	66	Unknown
67	Unknown	68	Unknown	69	Unknown
70	Unknown	71	Unknown	72	Unknown
73	Unknown	74	Unknown	75	Unknown
76	Unknown	77	Unknown	78	Unknown
79	Unknown	80	Unknown	81	Unknown
82	Unknown	83	Unknown	84	Unknown
85	Unknown	86	Unknown	87	Unknown
88	Unknown	89	Unknown	90	Unknown
91	Unknown	92	Unknown	93	Unknown
94	Unknown	95	Unknown	96	Unknown
97	5.00	98	Unknown	99	Unknown
100	Unknown	101	Unknown	102	Unknown
103	Unknown	104	Unknown	105	Unknown
106	Unknown	107	Unknown	108	Unknown
109	Unknown	110	Unknown	111	Unknown
112	Unknown	113	Unknown	114	Unknown
115	Unknown	116	Unknown	117	Unknown
118	Unknown	119	Unknown	120	Unknown
121	Unknown	122	Unknown	123	Unknown
124	Unknown	125	Unknown	126	Unknown
127	Unknown	128	Unknown	129	Unknown
130	Unknown	131	Unknown	132	Unknown
133	Unknown	134	Unknown	135	Unknown
136	Unknown	137	Unknown	138	Unknown
139	Unknown	140	Unknown	141	Unknown
142	Unknown	143	Unknown	144	<0.01
145	Unknown	146	Unknown	147	Unknown
148	67.00	149	<0.01	150	10.35
151	20.55	152	0.02	153	0.10
154	118.15	155	1500.00	156	148.40
157	29.60	158	30.20	159	15.00
160	15.11	161	123.00	162	107.95
163	<0.01	164	<0.01	165	<0.01
166	1060.71	167	Unknown	168	16.60
169	Unknown	170	87.66	171	1.54
172	41.50	173	334.00	174	1320.00
175	<0.01	176	33.00	177	22.25
178	50.60	179	21.90	180	35.10

EXHIBIT C.3 (Continued)

Number	Total Curies	Number	Total Curies	Number	Total Curies
181	20.41	182	54.00	183	17.55
184	30.45	185	15.30	186	<0.01
187	9.50	188	6.40	189	10.20
190	<0.01	191	38.00	192	Unknown
193	Unknown	194	Unknown	195	Unknown
196	237.60	197	3500.00	198	128.00
199	150.72	200	34.00	201	50.10
202	23.50	203	20.70	204	30.20
205	5.25	206	1.60	207	10.85
208	7.25	209	4.20	210	1.50
211	1.51	212	5.82	213	4.02
214	12.01	215	24.50	216	<0.01
217	0.13	218	31.00	219	Unknown
220	Unknown	221	10.01	222	81.75
223	1.75	224	103.75	225	11.10
226	53.00	227	209.80	228	168.70
229	15.00	230	44.00	231	55.00
232	Unknown	233	10.10	234	10.20
235	5870.01	236	47080.00	237	15.02
238	31.00	239	30.10	240	55.01
241	55.04	242	2.04	243	800.40
244	0.57	245	165.00	246	2005.85
247	0.15	248	676.80	249	Unknown
250	Unknown	251	91.36	252	26.51
253	23.50	254	85.00	255	55.00
256	15.00	257	30.00	258	23.00
259	38.00	260	35.00	261	42.50
262	5.00	263	26.00	264	6.00
265	11.00	266	27.63	267	10.00
268	Unknown	269	5.00	270	219.00
271	203.00	272	96400.00	273	15.00
274	115.50	275	15000.00	276	27.00
277	276.00	278	869.00	279	6.50
280	27.00	281	39.19	282	36.00
283	142.75	284	36.00	285	5.68
286	19.00	287	1.50	288	14.00
289	12.50	290	1.00	291	133.55
292	2700.00	293	18.00	294	15.01
295	7.25	296	1003.51	297	1.58
298	6.52	299	4.50	300	605.02
301	2.10	302	4.00	303	14.10
304	17.00	305	14.50	306	160.00
307	1.00	308	45.00	309	600.00
310	0.51	311	200.12	312	-826.30
313	1430.00	314	0.12	315	0.04
316	6.02	317	0.05	318	8.50
319	9.25	320	2.00	321	3.25
322	6.00	323	Unknown	324	2.00

EXHIBIT C.3 (Continued)

Number	Total Curies	Number	Total Curies	Number	Total Curies
325	2.01	326	1001.50	327	630.54
328	1.00	329	92.00	330	3.00
331	5.00	332	102.00	333	5.51
334	10.66	335	1.61	336	37.05
337	2.06	338	122.70	339	0.10
340	121.50	341	1.08	342	13.21
343	2.50	344	8.00	345	6.10
346	2.50	347	31.00	348	6.00
349	5.00	350	11.20	351	29.10
352	103.00	353	233.00	354	Unknown
355	6.40	356	15.00	357	100.25
358	0.51	359	2.02	360	4.00
361	21.00	362	0.15	363	1.13
364	0.42	365	2.00	366	0.14
367	0.05	368	16.70	369	183.05
370	207.20	371	1.50	372	7.50
373	2.50	374	20.10	375	0.05
376	9.00	377	52.49	378	5.00
379	6.20	380	14.55	381	8.00
382	3.50	383	0.20	384	34.20
385	16.50	386	148.10	387	3.50
388	2.61	389	6.30	390	5.50
391	10.50	392	4.00	393	1.10
394	Unknown	395	3.01	396	3.03
397	1.30	398	1.50	399	3.50
400	21.90	401	3.00	402	<0.01
403	0.83	404	59.01	405	0.07
406	4.65	407	11.50	408	Unknown
409	809.00	410	6.00	411	Unknown
412	145.50	413	10.00	414	9.00
415	4.50	416	20.01	417	4.00
418	0.07	419	0.04	420	16.00
421	9.52	422	Unknown	423	1883.10
424	606.02	425	20.50	426	112.33
427	1678.45	428	86.23	429	18.07
430	10.77	431	Unknown	432	55.76
433	12.25	434	152.50	435	152.50
436	1.50	437	8.00	438	2.07
439	15.08	440	2.01	441	18.00
442	13.00	443	<0.01	444	21.97
445	10.00	446	0.10	447	321.00
448	6.00	449	3125.00	450	10.00
451	15.01	452	Unknown	453	Unknown
454	Unknown	456	Unknown	457	Unknown
458	Unknown	459	Unknown	460	Unknown
461	Unknown	462	Unknown	463	Unknown
464	Unknown	465	Unknown	466	Unknown
467	Unknown	468	Unknown	469	Unknown

EXHIBIT C.3 (Continued)

Number	Total Curies	Number	Total Curies	Number	Total Curies
470	Unknown	471	Unknown	472	Unknown
473	Unknown	474	Unknown	475	Unknown
476	Unknown	477	Unknown	478	Unknown
479	Unknown	480	Unknown	481	Unknown
482	Unknown	483	Unknown	484	Unknown
485	Unknown	486	Unknown	487	Unknown
488	Unknown	489	Unknown	490	Unknown
491	Unknown	492	Unknown	Unknown	Unknown
TOTAL AUGER HOLE INVENTORY					202148.42

Source: Davis and Solomon (1987).

estimated that these isotopes comprise about 80 percent of the total curies (Davis and Solomon, 1987).

If the Waste Disposal Log is correct for the date of trench or auger hole closure and for the number of curies disposed there, about 152,000 Ci remained in January 1987. This is a 31 percent decrease in activity from the radiation originally disposed in SWSA 6 and is primarily due to the decay of europium in auger holes 155, 197, 235, 236, and 272 (Davis et al., 1987). Davis and Solomon (1987) reported that 19 auger holes (272, 236, 275, 235, 490, 197, 449, 292, 480, 246, 423, 427, 155, 482, 313, 174, 166, 296, and 326) and 7 trenches (460, 436, 444, 391, 283, 482, and 410) contain 90 percent of the activity in SWSA 6.

SWSA 6 is the currently operating landfill for ORNL and, as such, is still receiving low-level radioactive waste. Records for the types and quantities of radionuclides disposed since 1986 are maintained by the Waste Management Operations Group.

The solvent auger holes received a variety of chemical wastes before 1980, both radioactively contaminated and noncontaminated (IT, 1986). Wastes disposed there included oils, cleaning solutions, alcohols, paint thinners, kerosene, jet fuel, acids (HCl , HNO_3), sodium, and miscellaneous solvents and other chemicals. Containerization ranged from small bottles and cans up to 55-gal drums, and the exact volume of wastes disposed in the solvent holes is unknown. A vapor sample from Monitoring Well 650, which is located near the auger holes, detected a number of organic compounds that included trichlorofluoro-methane, dichloroethylene, methyl ethyl ketone, carbon tetrachloride, benzene, trichloroethylene (TCE), and toluene. The primary constituents were TCE and toluene. (However, of these compounds, only benzene and toluene were present in limited groundwater and trench leachate sampling; see Exhibit C-10).

A retrievable cask, which has been used in other ORNL operations to dispose of TRU waste, is also reported to be buried at SWSA 6. Few details are available, but apparently the cask was placed there in

1969 and is located near the main entrance in the northern portion of the site, close to Trenches 25-28 (Gaddis, 1988). It is not known at this time whether TRU waste is contained in the cask. If a search of records indicates that retrievable TRU waste is buried there, this cask must be located and removed from SWSA 6 before final closure of the site.

The specific geophysical method for locating the cask has not been determined; however, options are likely to include ground penetrating radar (GPR), seismic refraction, magnetometer, and electromagnetic conductivity (EM). The EM may be effective in detection of lead shielding, and the magnetometer may sense reinforcing steel. When suspect targets have been detected, seismic refraction or GPR may identify near-surface concrete.

C.2 HAZARDOUS CHARACTERISTICS

Limited groundwater and trench leachate analyses indicate that the waste disposed in SWSA 6 may contain elemental metals and chemically hazardous constituents delineated in 40 CFR 264, Appendix IX. Despite the lack of detailed records on types and amounts of RCRA-regulated wastes buried in SWSA 6, known operations at ORNL during the time this landfill has been in use indicate that hazardous constituents are likely to have been disposed there.

Sampling of groundwater and trench leachate detected 21 EPA priority pollutants, with four of these exceeding Tennessee Superfund site guidelines. Site characterization is further complicated because the wastes are mixed and containerization varies.

Based on a review of waste disposal practices at SWSA 6, it is known that lead (D008) has been disposed in the landfill and that it may be the only elemental metal with the potential to exceed the maximum concentration for EP toxicity per 40 CFR 261 Subpart C. Lead sheeting, such as that typically used for radioactive shielding, failed the EP toxicity test. However, EP Toxicity Tests have not been conducted on the lead waste in SWSA 6, and there is no evidence

at this time that the waste would be considered hazardous. It is also known that scintillation fluids containing xylene (F003) and toluene (F005) were disposed in SWSA 6.

In addition to these constituents, limited groundwater and leachate sample analysis indicates that the following hazardous constituents are present at SWSA 6:

- Chloroethane
- Methylene chloride
- 1,1 - Dichloroethane
- Chloroform
- 1,2 - Dichloroethane
- 1,1,2,2 - Tetrachloroethane
- Trichloroethane
- 1,1,2 - Trichloroethane
- Benzene
- Cis - 1,3 - Dichloropropene
- Tetrachloroethene
- Ethylbenzene
- Styrene
- Phenol
- 2,4 - Dimethylphenol
- Naphthalene
- Bis (2 - Ethylhexyl) phthalate
- o-Cresol
- p-Cresol

All chemically hazardous constituents detected in SWSA 6 are listed in Exhibit C.4. More detailed information on site characterization is presented in Section C.3 "Analytical Results."

C.3 ANALYTICAL RESULTS

No soil sampling has been undertaken to date in SWSA 6. Sampling has been limited to trench leachate, groundwater, and surface water from interior locations and three sites near the SWSA 6 boundary.

EXHIBIT C.4

CHEMICALLY HAZARDOUS WASTE CONTAMINANTS DETECTED IN SWSA 6^(a)

Contaminant	App. IX(b)	App. VIII(c)	TCL(d)
Ag	X	X	X
Al			X
As	X	X	X
Asbestos			X
Ba	X	X	X
Be	X	X	X
Cd	X	X	X
CN	X	X	X
Co	X		X
Cr	X	X	X
Cu	X		X
F	X	X	X
Fe			X
Hf		X	
Hg	X	X	
K			X
Mg			X
Mn			X
Na			X
Ni	X	X	X
Pb	X	X	X
Sb	X	X	X
Se	X	X	X
V	X		
Zn	X		
ORGANIC COMPOUNDS:			
Benzene	X	X	X
Carbon tetrachloride(e)	X	X	X
Chloroethane	X		X
Chloroform	X	X	X
O-Cresol	X	X	
P-Cresol	X	X	
1,1-dichloroethane	X	X	X
1,2-dichloroethane	X		X
1,1-dichloroethane	X		X
1,2,-trans-dichloroethene	X	X	X
Cis-1,3-dichloropropene	X	X	X
2,4-dimethylphenol	X	X	X
Ethylbenzene	X		X

EXHIBIT C.4 (Continued)

Contaminant	App. IX(b)	App. VIII(c)	TCL(d)
ORGANIC COMPOUNDS (Cont'd):			
methylethyl ketone(e)	X	X	X
methylene chloride	X	X	X
4-methylophenol			X
Napthalene	X	X	X
Phenol	X	X	X
bis (2-ethylhexyl) phthalate	X	X	X
Styrene	X		X
1,1,2,2-tetrachloroethane	X	X	X
Toluene	X	X	X
1,1,2-trichloroethane	X	X	X
1,1,1.-trichloroethene	X		
Trichloroethene	X	X	X
Trichlorofluoro-methane(e)	X	X	X
Total xylenes	X		X
MIXTURE OF:			
phenol	X	X	X
benzoic acid			X
2-methylophenol			X
4-methylophenol			X
2,4,5-trichlorophenol	X	X	X

(a) Solomon et al. (1987), IT (1986), ORNL (1986).

(b) Appendix IX constituents, 40 CFR 264.

(c) Appendix VIII constituents, 40 CFR 261.

(d) Listed in the Target Compound List (TCL) under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA).

(e) Found in IT (1986) discussion, not in analytical results.

Groundwater data from the boundary compliance monitoring wells will be obtained during the second quarter of CY 1988.

Numerous wells have been installed throughout the operational history of WAG 6, many of which were used either for research purposes or to observe water levels inside trenches. Lack of information on installation and/or maintenance makes data from most of these wells questionable. However, the recently installed piezometers, water quality monitoring wells, and hydrostatic head monitoring stations (HHMS) can provide useful data for site characterization. Locations of these wells are shown in Exhibit C.5.

A series of 21 piezometers, which provides lithologic and water level data, was installed in the summer of 1986. These piezometers are constructed of polyvinyl chloride (PVC) with sandpacks, grout seals, and caps to prevent infiltration of surface water and rainfall. Water level data, which have been collected from these installations biweekly, have been used to generate preliminary groundwater maps. These maps aided in designing a network of 30 groundwater compliance wells.

The 30 groundwater quality monitoring wells were drilled and installed in early 1987 (Hyde, 1987). For compliance purposes, 21 of these wells are located along the boundary of SWSA 6, and the remainder are site characterization wells located within the burial site. Wells are constructed with stainless steel screens and casings and were drilled and installed according to strict RCRA protocol, as described in the RCRA Groundwater Monitoring Technical Enforcement Guidance Document (TEGD) (EPA, 1986).

Three sets of hydrostatic head well clusters, each consisting of three adjacent wells, are being installed to provide data to establish vertical hydraulic gradients between the initial saturated zone and the deeper consolidated bedrock. The wells in the clusters are placed at depths of approximately 80, 200, and 400 ft, respectively.

EXHIBIT C.5
LOCATION MAP OF DOCUMENTED HHMS, PIEZOMETERS,
AND WATER QUALITY WELLS AT WAG 6

Recent water quality sample testing has addressed both groundwater and trench leachate from a limited number of locations in WAG 6. Samples were collected only from wells; unsaturated zone sampling has so far not been feasible. Analysis parameters have included both standard water quality factors and contaminant concentrations (radionuclides, EPA- and State of Tennessee-listed organic and inorganic compounds, National Interim Primary Drinking Water Standards (NIPDWS)).

Exhibit C.6 shows the location of the 13 piezometers and wells sampled during the 1986-1987 characterization effort at SWSA 6. These provided limited data on the interior of SWSA 6 but did not provide any information about the compliance boundary. The location of the compliance boundary and the placement of the groundwater wells to determine whether contaminants are migrating were determined previously by ORNL and the regulatory agencies.

Field analyses of groundwater and trench leachate yielded similar results. Sample pH ranged from 5.7 to 8.0 with groundwater represented in the neutral to slightly basic range. Alkalinity was low and quite variable, ranging from 2.5 to 14.4 mM HCO_3^- . The temperature ranged from 10.5 to 25.5°C, typical values for very shallow groundwater. The samples generally showed mildly oxidizing redox conditions; however, both the Eh and dissolved oxygen (DO) values were quite variable. Dissolved oxygen (DO) ranged from 0.1 to 8.2 mg/L and Eh ranged from -0.071 to +0.490 V. Conductivity values ranged from 117 to 1,730 umhos/cm. Field analysis results are presented in Exhibit C.7 (Solomon et al., 1987).

As shown in Exhibits C.8 and C.9, analysis of major cations/anions yielded results typical of regional conditions. Calcium, magnesium, sodium, and iron were the major cations; and bicarbonate, sulfate, and chloride were the major anions (Solomon et al., 1987).

Samples from trench leachate and groundwater wells were analyzed for EPA priority pollutant organic compounds, and 21 of the compounds were detected (ORNL, 1986). Twelve were found in more than one

EXHIBIT C.6
LOCATION OF PIEZOMETERS AND WELLS SAMPLED
DURING 1986-1987 CHARACTERIZATION EFFORT AT SWSA 6

EXHIBIT C.7

FIELD PARAMETERS FOR LEACHATE AND GROUNDWATER SAMPLES

Well or Trench No. Date	pH	Temp. (°C)	O ₂ (ppm)	Conduct. (umhos/cm)	Eh (V)	Alkalinity (mM HCO ₃)	Remarks
T41 03/11/86	6.5	14.8	1.2	638	0.262	9.9	(a)
T41 12/04/86	6.2	16.5	NA	870	NA	10.5	
T41 3/10/87	5.7	11.7	2.6	117	NA	3.2	(a)
T92 04/22/86	7.0	17	1.8	545	0.180	2.9	
T92 12/04/86	6.2	16.3	0.8	1730	NA	14.4	
T92 03/10/87	7.0	12.6	3.0	442	NA	3.3	(a,c)
T135 04/13/87	6.4	14.7	0.3	930	0.009	7.7	(b)
T163 04/21/87	6.3	16.2	0.3	377	0.034	2.7	(a)
T219 01/21/87	6.6	10.5	3.2	938	NA	8.2	(a,c)
T257 12/05/86	6.4	14.5	1.0	320	NA	NA	
T257 01/21/87	5.8	14.1	1.5	468	NA	3.3	(a,c)
T257 03/10/87	7.8	12.8	4.2	283	NA	2.5	(b,c)
T260-2 04/13/87	5.8	13.2	0.4	1500	-0.071	3.6	(a)

EXHIBIT C.7 (Continued)

Well or Trench No. Date	pH	Temp. (°C)	O ₂ (ppm)	Conduct. (umhos/cm)	Eh (V)	Alkalinity (mM HCO ₃)	Remarks
T288 03/21/86	6.4	10.4	0.1	480	0.860	7.1	(b)
T288 12/05/86	6.6	15.8	0.6	840	NA	NA	
T288 (a,c) 03/10/87	7.2	10.4	4.0	745	NA	6.4	
S-11 03/17/86	7.0	17.0	1.8	545	0.490	8.9	(b)
647 07/10/86	7.0	25.5	4.2	720	0.445	7.7	
648 (b,c) 01/21/87	7.0	10.6	2.6	556	NA	5.2	
649 (a,c) 03/11/87	7.9	14.1	7.0	785	NA	8.4	
650 (b,c) 03/11/87	8.0	12.3	8.2	636	NA	5.9	

NA - Analysis not performed

- (a) - The unacidified filtered leachate sample was initially clear; on standing 2 hr a fine brown precipitate appeared.
- (b) - The filtered solution remained clear for at least 24 hr.
- (c) - The well was sampled on two consecutive days to get sufficient water for all analyses.

Source: Solomon et al. (1987).

EXHIBIT C.8

INDUCTIVELY COUPLED PLASMA SPECTROMETRIC ANALYSES
OF LEACHATE AND GROUNDWATER SAMPLES(a)

Element	Sampling Locations and Dates							
	T41 03/11/86	T41 12/04/86	T41 03/10/87	T92 04/22/86	T92 12/04/86	T92 03/10/87	T135 04/13/87	T163 04/21/87
Ag	<0.050	<0.050	<0.005	<0.050	<0.050	<0.005	<0.005	<0.005
Al	<0.200	<0.200	<0.020	<0.200	<0.200	<0.020	0.02	0.035
As	<0.330	<0.10	<0.010	<0.005	<0.10	<0.010	<0.010	<0.010
B	0.35	0.48	0.17	0.08	0.08	0.084	0.25	0.094
Ba	0.18	0.14	0.2	0.14	0.21	0.089	0.16	0.061
Be	<0.002	<0.002	<0.0002	<0.002	<0.0002	<0.0002	<0.0002	<0.0002
Ca	140	120	110	37	48	34	89	31
Cd	0.005	<0.005	0.0019	<0.005	<0.005	<0.0005	0.004	0.0016
Co	0.01	0.015	0.0068	<0.022	<0.010	0.013	0.008	0.0068
Cr	<0.040	<0.040	<0.0053	<0.040	>0.040	<0.0040	<0.0040	<0.0040
Cu	<0.020	<0.020	<0.002	<0.020	<0.020	<0.002	0.002	0.0025
Fe	23	37	34	7.1	23	6.2	50	<1.000
Ga	<0.300	<0.300	<0.030	<0.300	<0.300	<0.030	<0.030	<0.030
Li	<0.200	<0.200	<0.020	<0.200	<0.200	<0.020	<0.1900	<0.020
Mg	25	26	24	9.1	9.6	6.8	17	8.1
Mn	5	5.2	4.5	9.4	8	6.6	3.5	1.5
Mo	<0.040	<0.040	0.028	<0.040	<0.040	<0.004	<0.0040	<0.004
Na	42	28	27	7.1	23	9.8	7.1	1.8
Ni	0.08	0.27	0.034	0.06	<0.06	<0.006	<0.0120	<0.006
P	0.41	0.54	0.46	<0.300	2	0.12	1.8	0.79
Pb	<0.200	<0.200	<0.020	<0.010	<0.20	<0.020	<0.020	<0.020
Sb	<0.020	<0.20	<0.020	<0.200	<0.200	>0.020	<0.020	<0.020
Se	<0.020	<0.20	<0.020	<0.010	<0.20	<0.020	<0.020	<0.020
Si	3.9	3.6	3.3	4.7	6.2	3.8	1.9	1.1
Sn	<0.050	<0.050	<0.005	<0.050	<0.050	<0.005	<0.0050	<0.0050
Sr	0.14	0.23	0.2	0.11	0.13	0.074	0.15	0.042
Ti	<0.020	<0.020	<0.002	<0.020	<0.020	<0.002	0.002	0.0057
V	<0.010	<0.0010	0.001	<0.010	<0.0010	<0.001	0.001	0.001
Zn	0.041	0.083	0.0073	<0.020	<0.020	0.023	<0.0560	<0.0330
Zr	<0.020	<0.020	<0.002	<0.020	<0.020	<0.002	<0.0020	<0.002

EXHIBIT C.8 (Continued)

Element	Sampling Locations and Dates							
	T219 01/21/87	T257 12/05/86	T257 01/21/87	T257 03/10/87	T260-2 04/13/87	T288 03/21/86	T288 12/05/86	T288 03/10/87
Ag	0.030	<0.050	<0.005	<0.005	<0.005	<0.050	<0.050	<0.005
Al	<0.120	<0.200	0.03	<0.020	0.02	<0.200	<0.200	<0.020
As	<0.060	<0.10	<0.010	<0.010	<0.010	<0.005	<0.10	<0.010
B	<0.048	<0.08	0.022	<0.008	0.008	0.08	<0.08	<0.008
Ba	0.1	<0.099	0.12	0.068	0.13	0.2	0.28	0.18
Be	<0.0012	<0.002	<0.0002	<0.0002	<0.0002	<0.002	<0.002	<0.0002
Ca	150	31	36	32	38	47	72	52
Cd	<0.003	<0.005	0.0012	<0.0005	0.0033	<0.005	<0.005	0.0021
Co	0.014	<0.010	0.047	<0.001	0.019	<0.010	<0.016	0.0099
Cr	<0.024	<0.040	0.0049	<0.004	<0.0040	<0.040	<0.040	<0.004
Cu	<0.012	<0.020	<0.002	<0.002	0.002	<0.020	<0.020	<0.002
Fe	24	0.33	17	0.0087	40	50	69	45
Ga	<0.180	<0.300	<0.030	<0.030	<0.300	<0.300	<0.300	<0.030
Li	<0.120	<0.200	<0.020	<0.020	<0.0200	<0.200	<0.200	<0.020
Mg	22	4.6	11	3.7	13	13	18	12
Mn	5.7	0.35	7	0.00081	4.3	5.8	8.5	5.4
Mo	<0.024	<0.040	0.011	<0.004	<0.0040	<0.040	<0.040	0.014
Na	2.9	13	18	8.5	130	2.6	3.7	1.4
Ni	<0.036	<0.06	0.014	<0.006	<0.0060	0.06	<0.06	0.006
P	<0.180	0.62	0.12	0.13	0.1	0.63	0.84	0.64
Pb	<0.120	<0.20	<0.020	<0.020	<0.020	<0.010	<0.20	<0.020
Sb	<0.120	<0.20	<0.020	<0.020	<0.020	<0.020	<0.20	<0.020
Se	<0.120	<0.20	<0.020	<0.020	<0.020	<0.010	<0.20	<0.020
Si	0.53	2	0.14	2.1	1.3	4.3	5.4	3.3
Sn	<0.030	<0.050	<0.005	<0.005	<0.0050	<0.050	<0.050	0.005
Sr	0.17	0.061	0.072	0.05	0.075	0.092	0.13	0.078
Ti	<0.012	<0.020	0.0048	<0.002	0.0038	<0.020	<0.020	<0.002
V	0.0097	<0.001	<0.0010	0.0018	0.001	<0.010	<0.001	<0.001
Zn	<0.012	<0.020	0.44	0.006	<0.0190	<0.020	<0.020	0.0069
Zr	<0.012	<0.020	<0.002	<0.002	<0.0020	<0.020	<0.020	<0.002

EXHIBIT C.8 (Continued)

Element	Sampling Locations and Dates							
	S11 03/17/86	647 07/10/86	648 01/21/87	649 03/11/87	650 03/11/87	BLANK 12/04/86	BLANK 12/05/86	BLANK 04/21/87
Ag	<0.050	<0.050	<0.005	<0.050	<0.050	<0.050	<0.050	<0.005
Al	<0.200	<0.200	<0.020	<0.200	<0.200	<0.200	<0.200	<0.020
As	<0.100	<0.100	<0.010	<0.100	<0.100	<0.10	<0.10	<0.010
B	0.08	0.08	<0.008	0.32	0.11	<0.08	<0.08	<0.008
Ba	0.16	0.12	0.2	1.2	2	<0.020	<0.020	<0.014
Be	<0.002	<0.002	<0.0002	<0.0020	<0.002	<0.002	<0.002	<0.0002
Ca	140	63	90	1200	900	<5.0	1.2	0.25
Cd	<0.005	<0.005	<0.0005	<0.026	<0.0005	<0.005	<0.005	<0.0005
Co	<0.010	<0.010	0.0071	0.023	0.02	<0.010	<0.010	<0.0010
Cr	<0.040	<0.040	0.0052	<0.042	<0.045	<0.040	<0.040	<0.0040
Cu	<0.020	<0.020	<0.002	<0.020	<0.020	<0.020	<0.020	0.003
Fe	<0.030	<0.030	0.097	0.086	3.6	<0.030	<0.030	0.013
Ga	<0.300	<0.300	<0.030	<0.300	<0.300	<0.300	<0.300	<0.030
Li	<0.200	<0.200	<0.020	<0.200	<0.230	<0.200	<0.200	<0.020
Mg	24	10	6.5	78	110	0.14	0.39	0.0055
Mn	0.088	0.11	3.6	0.46	0.15	<0.0050	<0.0050	0.00056
Mo	<0.040	<0.040	<0.004	<0.040	<0.040	<0.040	<0.040	<0.004
Na	42	5.3	11	47	58	<0.50	<0.50	0.15
Ni	0.06	0.06	<0.006	<0.060	<0.060	<0.060	<0.060	<0.006
P	0.3	0.3	0.097	<0.300	<0.380	<0.300	<0.300	0.03
Pb	<0.200	<0.200	<0.020	<0.200	<0.200	<0.20	<0.20	<0.020
Sb	<0.200	<0.200	<0.020	<0.200	<0.200	<0.200	<0.200	<0.020
Se	<0.200	<0.200	<0.020	<0.200	<0.200	<0.20	<0.20	<0.020
Si	8.7	7.8	0.25	54	87	<0.20	<0.20	0.034
Sn	<0.050	<0.050	<0.0050	<0.050	<0.050	<0.050	<0.050	<0.0050
Sr	0.19	0.13	0.12	1.7	1.4	0.0065	0.0063	0.00068
Ti	<0.020	<0.020	0.0028	<0.020	<0.020	<0.020	<0.020	0.0044
V	<0.010	<0.010	0.0014	0.001	0.01	<0.0010	<0.0010	0.001
Zn	<0.020	<0.020	<0.002	<0.130	<0.096	0.03	0.022	<0.0250
Zr	<0.020	<0.020	<0.002	<0.020	<0.020	<0.020	<0.020	<0.002

(a) Values given in mg/L.

Source: Solomon et al. (1987).

EXHIBIT C.9

CHEMICAL, ION CHROMATOGRAPHIC, AND ATOMIC ABSORPTION
ANALYSES OF LEACHATE AND GROUNDWATER SAMPLES

	T41	T41	T41	T92	T92	T92	135	163
Analysis	03/11/87	12/04/86	03/10/87	04/22/86	12/04/86	03/10/87	04/13/87	04/21/87

CHEMICAL (Values in mg/L)

NH ₃	5.31	NA	NA	2.2	NA	NA	2.56	7.05
CYANIDE	NA	NA	<0.002	NA	NA	<0.002	<0.002	<0.002
TOTAL C	189	NA	NA	88	NA	NA	NA	NA
IOC	141	NA	NA	60	NA	NA	NA	NA
TOC	NA	NA	NA	NA	NA	NA	54	10

ION CHROMATOGRAPHIC (Values in ug/mL)

NO ₃ ⁻	<5	<1.0	3	<5.0	<1	<1.0	<5.0	<5.0
F ⁻	<10.0	1	<1.0	<1.0	4		<1.0	<1.0
SO ₄ ²⁺	132	150	9	6	6	<5.0	<5.0	<5.0
Cl ⁻	27	50	20	17	80	14	8.3	6.2
Br ⁻	<5.0	<5.0	<1.0	<5.0	<5.0	<1.0	<5.0	<5.0
PO ₄ ³⁻	<5.0	<1.0	<1.0	<5.0	<1	<1.0	<5.0	<5.0

ATOMIC ABSORPTION (Values in mg/L)

Hg	<0.0001	NA	NA	<0.0002	NA	NA	<0.0001	<0.0001
----	---------	----	----	---------	----	----	---------	---------

EXHIBIT C.9 (Continued)

	T219	T257	T257	T257	T260-2	T288	T288	T288
Analysis	01/21/87	12/05/86	01/21/87	03/10/87	04/13/86	03/21/86	12/05/86	03/10/87

CHEMICAL (Values in mg/L)

NH ₃	7.2	NA	0.64	NA	1.64	21.8	NA	NA
CYANIDE	<0.002	NA	<0.002	<0.002	<0.002	NA	NA	<0.002
TOTAL C	NA	NA	NA	NA	NA	148	NA	NA
IOC	NA	NA	NA	NA	NA	129	NA	NA
TOC	11	NA	4.4	NA	2.5	NA	NA	NA

ION CHROMATOGRAPHIC (Values in ug/mL)

NO ₃ ⁻	<1.0	<1.0	<1.0	4	<5.0	<5.0	<1	<1.0
F ⁻	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	4	<1.0
SO ₄ ²⁺	8	5	29	5	<5.0	<5.0	<1	<1.0
Cl ⁻	7	5	15	4	300	9.6	48	6
Br ⁻	<5.0	<5.0	<5.0	<1.0	<5.0	<5.0	<5.0	<1.0
PO ₄ ³⁻	<1.0	1	<1.0	1.5	<5.0	<5.0	<1.0	<1.0

ATOMIC ABSORPTION (Values in mg/L)

Hg	<0.0002	NA	<0.0002	NA	<0.0001	<0.0001	NA	NA
----	---------	----	---------	----	---------	---------	----	----

EXHIBIT C.9 (Continued)

Analysis	S11 03/17/86	647 07/10/86	648 01/21/87	649 03/11/87	650 03/11/87	Blank 04/21/87
CHEMICAL (Values in mg/L)						
NH ₃	0.18	0.24	0.11	NA	NA	0.13
CYANIDE	NA	<0.002	<0.002	<0.002	<0.002	<0.002
TOTAL C	119	NA	NA	NA	NA	NA
IOC	114	NA	NA	NA	NA	NA
TOC	NA	2.1	1.7	1.1	0.7	0.5
ION CHROMATOGRAPHIC (Values in ug/mL)						
NO ₃ ⁻	9.6	<5.0	<1.0	5	<1.0	<5.0
F ⁻	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
SO ₄ ²⁺	77	<5.0	5	20	21	<5.0
Cl ⁻	9.6	1	5	4	4	<1.0
Br ⁻	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
PO ₄ ³⁻	<5.0	<5.0	<1.0	<1.0	<1.0	<5.0
ATOMIC ABSORPTION (Values in mg/L)						
Hg	<0.0001	0.0007	<0.0002	<0.0001	<0.0002	<0.0001

NA = Analysis not performed
 TOC = Total Organic Carbon
 IOC = Inorganic Carbon

Source: Solomon et al. (1987).

sample: methylene chloride, 1,1-dichloroethane, chloroform, trichloroethene, benzene, tetrachloroethene, toluene, ethylbenzene, total xylenes, phenol, 4-methylphenol, and naphthalene (Exhibit C.10). High levels of xylenes and toluene were found in several samples, including both leachate and groundwater.

Trichloroethene, benzene, tetrachloroethene, toluene, and naphthalene had notable concentrations in some samples. Of the groundwater wells sampled, Well 648 had the highest concentrations of organics; this well is located near an area containing several solvent auger holes (Exhibit C.10). Trenches 219 and 288, both of which are biological trenches, showed the highest organic concentrations. Neither of these was listed as having received scintillation vials (IT, 1986); however, Trench 219 had 3696 ug/L of xylenes and Trench 288 had 1940 ug/L of toluene. This preliminary analysis suggests that organics may be widespread at SWSA 6. Additional sampling and analysis will be necessary to assess this concern.

Radiochemical analyses during the 1986-1987 characterization studies further illustrated the problems in remediating the mixed wastes disposed in SWSA 6. Gross-alpha activity for leachate samples collected from Trench 41 on March 11, 1986, and December 4, 1986, was 8.6 ± 5.3 Bq/L and 110 ± 45 Bq/L, respectively (Exhibit C.11). Tritium was present in all samples, exceeding 1000 Bq/L in 11 of the leachate samples and 2 groundwater samples. The highest strontium-90 concentration was 3600 Bq/L from Trench 41 on March 11, 1986. Strontium-90 and carbon-14 were present in appreciable concentrations in several trench leachate samples but were lower or absent in groundwater samples. Carbon-14 concentrations ranged from below detection to 2900 Bq/L in Trench 41 on March 10, 1987. Low levels of cobalt-60 and cesium-137 were detected. The highest concentration of cobalt-60 was observed in samples from Trench 257 and the highest concentration of cesium-137 was observed in samples from Trench 41.

EXHIBIT C.10

PRIORITY POLLUTANTS FOUND IN LEACHATE AND
GROUNDWATER SAMPLES IN SWSA 6

Compound(a)	Location			
	T92	T135	T163	T219
Chloroethane	<10	<10	49	<10
Methylene Chloride	<2.8	<5	<5	<5
1,1-Dichloroethene	<2.8	<5	<5	<5
1,1-Dichloroethane	<4.7	<5	626	<5
Chloroform	<1.6	<5	<5	<5
1,2-Dichloroethane	<2.8	<5	<5	<5
1,1,2,2-Tetrachloroethane	<6.9	<5	<5	<5
Trichloroethene	2	<5	<5	8
1,1,2-Trichloroethane	<5	<5	<5	<5
Benzene	4.4	<5	<5	929
Cis-1,3-Dichloropropene	<5	<5	<5	58
Tetrachloroethene	<4.1	<5	<5	1182
Toluene	<5	14	668	<5
Ethylbenzene	<5	<5	<5	67
Styrene	<5	<5	<5	7
Total Xylenes	<5	<5	<5	3696
Phenol	<10	<10	12	<10
4-Methylphenol	<10	<10	91	34
2,4-Dimethylphenol	<10	<10	<10	<10
Naphthalene	51	<10	<10	354
Bis(2-Ethylhexyl)phthalate	<10	<10	<10	<10
o-Cresol	<10	<10	<10	<10
p-Cresol	<10	<10	<10	<10

EXHIBIT C.10 (Continued)

Compound(a)	Location			S11
	T257	T260-2	T288	
Chloroethane	<10	<10	<10	<10
Methylene Chloride	<5	<5	<2.8	256
1,1-Dichloroethene	<5	<5	<2.8	<5
1,1-Dichloroethane	<5	<5	<2.8	<5
Chloroform	<5	<5	<1.6	87
1,2-Dichloroethane	<5	<5	<4.7	<5
1,1,2,2-Tetrachloroethane	<5	<5	<6.9	<5
Trichloroethene	<5	<5	<1.9	2
1,1,2-Trichloroethane	<5	<5	<5	<5
Benzene	<5	<5	13	<5
Cis-1,3-Dichloropropene	<5	<5	<5	<5
Tetrachloroethene	<5	<5	<4.1	<5
Toluene	35	<5	1940	<5
Ethylbenzene	<5	<5	720	<5
Styrene	<5	<5	<5	<5
Total Xylenes	11	<5	<5	<5
Phenol	<10	<10	13	<10
4-Methylphenol	<10	<10	<10	<10
2,4-Dimethylphenol	<10	<10	32	<10
Naphthalene	<10	<10	1704	<10
Bis(2-Ethylhexyl)phthalate	<10	<10	<10	13
o-Cresol	<10	<10	26	<10
p-Cresol	<10	<10	141	<10

EXHIBIT C.10 (Continued)

Compound (a)	Location			
	647	648	649	650
Chloroethane	<10	<10	<10	<10
Methylene Chloride	<5	<5	40	<5
1,1-Dichloroethene	<2.8	11	<5	<5
1,1-Dichloroethane	10	<5	<5	<5
Chloroform	<1.6	85	<5	<5
1,2-Dichloroethane	<2.8	23	<5	<5
1,1,2,2-Tetrachloroethane	<6.9	55	<5	<5
Trichloroethene	<1.9	2323	<5	<5
1,1,2-Trichloroethane	<5	22	<5	<5
Benzene	<4.4	70	<5	<5
Cis-1,3-Dichloropropene	<5	<5	<5	<5
Tetrachloroethene	<5	1973	<5	<5
Toluene	<5	10	<5	<5
Ethylbenzene	<5	<5	<5	<5
Styrene	<5	<5	<5	<5
Total Xylenes	<5	6	<5	<5
Phenol	<10	<10	<10	<10
4-Methylphenol	<10	<10	<10	<10
2,4-Dimethylphenol	<10	<10	<10	<10
Naphthalene	<10	<10	<10	<10
Bis(2-Ethylhexyl)phthalate	<10	<10	<10	<10
o-Cresol	<10	<10	<10	<10
p-Cresol	<10	<10	<10	<10

(a) Values in ug/L.

Source: ORNL (1986).

EXHIBIT C.11

RADIOCHEMICAL ANALYSES OF LEACHATE AND GROUNDWATER SAMPLES

Analysis(a)	EPA 40 CFR 191	T41 03/11/86	T41 12/04/86	T41 03/10/87	T92 04/22/86	T92 12/04/86
gross alpha		8.6±5.3	110±45	1.1±1.8	1.5±1.7	0.7±1.4
gross beta		(5.4±0.1)E3	(1.8±0.1)E4	(1.6±0.1)E4	150±10	16±4
gross gamma		<10	<10	<10	<10	<10
³ H	2.00 E+04	(2±0.1)E3	(3.4±0.1)E5	(1.8±0.1)E5	(2.2±0.1)E3	(2.6±0.1)E3
¹⁴ C	5.60 E+02	1.9	NA	(2.9±0.1)E3	42±18	NA
⁶⁰ Co	4.30 E+01	NA	<0.6	<0.6	0.22±0.08	<0.3
⁹⁰ Sr	8.10 E+00	(3.6±0.1)E3	(3.1±0.1)E3	NA	86±12	0.84±.20
⁹⁹ Tc	7.90 E+02	<100	<100	<100	<100	<100
¹³⁷ Cs	2.30 E+01	88±6	130±10	140±10	2.6±0.2	0.33±0.28
²²⁸ Th	1.50 E+00	0.17±0.2	NAL	NAL	NAL	NAL
²³⁰ Th	2.10 E+00	0.03±.01	NAL	NAL	NAL	NAL
²³⁴ U	4.10 E+00	0.63±0.07	NAL	NAL	NAL	NAL
²³⁵ U	4.30 E+00	0.11±0.03	NAL	NAL	NAL	NAL
²³⁸ U	4.50 E+00	0.36±0.05	NAL	NAL	NAL	NAL
Total Ra		0.47±0.18	NAL	NAL	<0.02	NAL

EXHIBIT C.11 (Continued)

Analysis(a)	T92 03/10/87	T135 04/13/87	T163 04/21/87	T219 01/21/87	T257 12/05/86	T257 01/21/87
gross alpha	1±1	0.6±1.0	1±1.7	<2	2.9±2.4	4.2±3
gross beta	9.4±3.4	(5.4±0.1)E3	26±5	20±5	9.4±3.7	(1.1±1)E3
gross gamma	<10	<10	<10	<10	<10	<10
³ H	(1.5±0.1)E3	(3.3±0.1)E4	620±50	380±40	(2.3±0.1)E4	(3.9±1)E3
¹⁴ C	<21	(2.6±0.1)E3	32±21	30±20	NA	410±30
⁶⁰ Co	<0.1	0.70±0.22	0.33±0.18	<2	<3	1.4±.4
⁹⁰ Sr	NAL	NA	NAL	NAL	0.26±0.13	NA
⁹⁹ Tc	<100	<100	<100	<100	<100	<100
¹³⁷ Cs	0.59±0.13	40±1	2.4±0.2	3±0.4	<0.3	2.1±0.4
²²⁸ Th	NAL	NAL	NAL	NAL	NAL	NAL
²³⁰ Th	NAL	NAL	NAL	NAL	NAL	NAL
²³⁴ U	NAL	NAL	NAL	NAL	NAL	NAL
²³⁵ U	NAL	NAL	NAL	NAL	NAL	NAL
²³⁸ U	NAL	NAL	NAL	NAL	NAL	NAL
Total Ra	NAL	NAL	NAL	0.11±0.05	NAL	<0.1

EXHIBIT C.11 (Continued)

Analysis(a)	T257 03/10/87	T260-2 04/13/87	T288 03/31/86	T288 12/05/86	T288 03/10/87	S11 03/17/86
gross alpha	2 $\pm$ 2.1	0.4 $\pm$ 1	1.9 $\pm$ 2	2.5 $\pm$ 2.3	1 $\pm$ 2	7.7 $\pm$ 2.7
gross beta	1 $\pm$ 2.4	3.9 $\pm$ 3	4.9 $\pm$ 2.9	52 $\pm$ 7	9.1 $\pm$ 3.4	4.7 $\pm$ 2.9
gross gamma	<10	<10	<10	<10	<10	<10
³ H	(1.2 $\pm$ 0.1)E4	310 $\pm$ 40	(4.8 $\pm$ 0.9)E2	(1.2 $\pm$ 0.1)E3	570 $\pm$ 50	(3.7 $\pm$ 0.2)E3
¹⁴ C	1 $\pm$ 20	19 $\pm$ 20	10 $\pm$ 35	NA	10 $\pm$ 20	48 $\pm$ 36
⁶⁰ Co	<0.2	<0.2	0.88 $\pm$ 0.26	0.43 $\pm$ 0.29	<0.2	0.87 $\pm$ 0.33
⁹⁰ Sr	NAL	NAL	NAL	12 $\pm$ 1	NAL	NAL
⁹⁹ Tc	<100	<100	<100	<100	<100	<100
¹³⁷ Cs	<0.2	<0.3	<0.1	1.2 $\pm$ 0.3	0.29 $\pm$ 0.3	<0.1
²⁸⁸ Th	NAL	NAL	NAL	NAL	NAL	NAL
²³⁰ Th	NAL	NAL	NAL	NAL	NAL	NAL
²³⁴ U	NAL	NAL	NAL	NAL	NAL	NAL
²³⁵ U	NAL	NAL	NAL	NAL	NAL	NAL
²³⁸ U	NAL	NAL	NAL	NAL	NAL	NAL
Total Ra	NAL	NAL	<0.02	NAL	NAL	<0.02

EXHIBIT C.11 (Continued)

Analysis(a)	647 07/10/86	648 01/21/87	649 03/11/87	650 03/11/87	Blank 04/21/87
gross alpha	1.6±2	<2	1±2	1±1	0.4±1.4
gross beta	5.3±3	<3	<2	2.6±2.6	0.7±2.3
gross gamma	<10	<10	<10	<10	<10
³ H	34±21	71±24	15±20	(2.6±0.1)E4	24±21
¹⁴ C	8±18	25±20	<20	13±14	6±20
⁶⁰ Co	<0.1	<3	<0.5	<0.1	<0.3
⁹⁰ Sr	NAL	NAL	NAL	NAL	NAL
⁹⁹ Tc	<100	<100	<100	<100	<100
¹³⁷ Cs	<0.1	<0.3	<0.4	<0.1	<0.3
²²⁸ Th	NAL	NAL	NAL	NAL	NAL
²³⁰ Th	NAL	NAL	NAL	NAL	NAL
²³⁴ U	NAL	NAL	NAL	NAL	NAL
²³⁵ U	NAL	NAL	NAL	NAL	NAL
²³⁸ U	NAL	NAL	NAL	NAL	NAL
Total Ra	0.025±0.012	.064±0.042	NAL	NAL	NAL

(a) All units are Bq/L except gross gamma, which is (counts min⁻¹ ml⁻¹).

NA = Analysis not performed

NAL = Analysis not performed because gross activity was low

Source: Solomon et al. (1987).

Surface water flow data have been collected at five monitoring stations within SWSA 6. Two are located within the ETF in the west central part of the site (SW4 and SW5), and three are at the major tributaries draining the site at points near their discharge to White Oak Lake (SW1, SW2, and SW3) (Exhibit C.12). Surface runoff measurements began in 1985, and data have shown that runoff is highly seasonal and characterized by four distinct periods: 1) low runoff during the summer months; 2) increasing runoff during the fall; 3) maximum runoff during the winter; and 4) decreasing runoff in the spring (Davis et al., 1987).

In addition to flow data, surface water quality sampling and analysis have been conducted at the ETF and at six other sites in SWSA 6 (Exhibit C.12). Samples from the ETF were analyzed for chemical and radiological parameters, whereas data from other sites involved only radionuclide analyses. Results are presented in Exhibits C.13 and C.14 (ORNL, 1986).

Tritium values from four of the sites exceeded the EPA standard (2×10^4 Bq/L), and one sample from the ETF had a tritium value of 13,667 Bq/L. The only other radionuclide to appear in significant amounts was strontium-90, which exceeded the EPA standard (8.1 Bq/L) in the 49 Trench Area West Creek Seep and at Gauging Station Three.

Cerling and Spalding (1981) surveyed streambed gravels from drainages in the White Oak Creek (WOC) watershed to determine concentrations of strontium-90, cobalt-60, and cesium-137. The tributary draining the east of SWSA 6 was estimated to contribute about 4 percent or less to the total discharge into WOC. However, another minor SWSA 6 contribution (2 percent) to the strontium-90 in WOC watershed was of special concern. This contamination originated as a groundwater seep emanating from the 49 Trench area, a recently used group of trenches containing low-activity waste. This rather rapid migration of strontium-90 with groundwater demonstrates the ready leachability of strontium-90 from solid waste disposal areas.

SW1
• SURFACE WATER MONITORING
POINT AND NUMBER

EXHIBIT C.12 LOCATION OF SURFACE WATER MONITORING POINTS AT WAG 6

EXHIBIT C.13

ENGINEERED TEST FACILITY SURFACE WATER QUALITY

Constituent	Unit	Number of Samples	Mean	Standard Deviation	Minimum Value	Maximum Value
<u>SW4</u>						
Al	mg/L	3	0.532	0.840	0.004	1.500
B ^(a)	mg/L	3	0.026	0.020	0.012	0.050
Br	mg/L	1	(b)			
Ca	mg/L	3	46	31	17	79
Cl	mg/L	3	2.4	2.0	0.9	4.6
F ^(a)	mg/L	3	0.2	0.2	0.1	0.4
Fe	mg/L	3	(b)			
I	mg/L	1	(b)			
K	mg/L	3	2.68	0.68	2.04	3.40
Mg ^(a)	mg/L	3	1.89	1.65	0.02	3.14
Mn ^(a)	mg/L	3	0.039	0.053	0.0003	0.100
Na	mg/L	3	2.29	0.95	1.20	2.88
NO ₃ -N	mg/L	3	1.4	2.4	0.001	4.2
P (total)	mg/L	2	0.012	0.010	0.005	0.019
SiO ₂	mg/L	3	8.50	1.25	7.50	9.90
SO ₄	mg/L	3	13.4	10.4	2.9	23.6
Sr	mg/L	3	(b)			
Total alkalinity	mg/L as CaCO ₃	3	120	75	40	188
Conductivity	S/cm	1	120			
pH	pH units	1	6.6			
TOC	mg/L	1	4.9			
Tritium ^(a)	Bq/L ^(c)	3	48	29	24	81
⁹⁰ Sr	Bq/L ^(c)	3	(b)			
Gross alpha	Bq/L ^(c)	3	0.74	0.46	0.28	1.20
¹³⁷ Cs	Bq/L ^(c)	3	(b)			
⁶⁰ Co	Bq/L ^(c)	3	(b)			

EXHIBIT C.13 (Continued)

Constituent	Unit	Number of Samples	Mean	Standard Deviation	Minimum Value	Maximum Value
<u>SW5</u>						
Al	mg/L	3	0.158	0.261	0.006	0.459
B ^(a)	mg/L	3	0.032	0.018	0.014	0.050
Br	mg/L	1	(b)			
Ca	mg/L	3	44	7	36	50
Cl	mg/L	3	8.7	5.2	4.6	14.6
F	mg/L	3	0.1	0.0	0.1	0.1
Fe	mg/L	3	(b)			
I	mg/L	1	(b)			
K	mg/L	3	2.60	0.51	2.01	2.90
Mg	mg/L	3	9.18	3.41	6.20	12.90
Mn ^(a)	mg/L	3	0.041	0.052	0.0004	0.100
Na	mg/L	3	4.25	0.51	3.70	4.70
NO ₃ -N ^a	mg/L	3	2.0	3.4	0.003	5.9
P (total)	mg/L	2	0.022	0.029	0.001	0.042
SiO ₂	mg/L	3	7.50	3.05	5.39	11.0
SO ₄	mg/L	3	23.9	12.7	13.0	37.8
Sr	mg/L	3	(b)			
Total alkalinity	mg/L as CaCO ₃	3	134	16	121	152
Conductivity	S/cm	1	320			
pH	pH units	1	6.9			
TOC	mg/L	1	3.3			
Tritium ^(a)	Bq/L ^(c)	3	13,667	1,527	12,000	15,000
⁹⁰ Sr	Bq/L ^(c)	3	(b)			
Gross alpha	Bq/L ^(c)	3	0.50	0.11	0.40	0.62
¹³⁷ Cs	Bq/L ^(c)	3	(b)			
⁶⁰ Co	Bq/L ^(c)	3	(b)			

(a) Majority of values above detection limits; therefore, mean = maximum mean.

(b) Majority of values below detection limit; therefore, no mean is reported.

(c) 3.7×10^{10} Bq = 1 Ci.

Source: Davis et al. (1984).

EXHIBIT C.14

RESULTS OF RADIOLOGICAL ANALYSES OF SURFACE WATER AT SELECTED SITES IN SWSA 6

Date	Radionuclide Concentration (Bq/L) (a)				Gross Alpha	Gross Beta
	^3H	^{90}Sr	^{137}Cs	^{60}Co		
			<u>SW6</u> (b)			
02/29/84	220 $\pm$ 50	1.9 $\pm$ 0.9	<0.6	<0.7	2.0 $\pm$ 1.0	---
			<u>SW7</u> (b)			
09/29/83	19,000 $\pm$ 1,000	0.54 $\pm$ 0.28	<0.5	<0.6	4.6 $\pm$ 3.6	---
02/29/84	27,000 $\pm$ 1,000	1.8 $\pm$ 0.9	<0.05	<0.07	<1	---
04/30/84	79,000 $\pm$ 1,000	0.29 $\pm$ 0.22	<0.1	<0.1	0.27 $\pm$ 0.8	---
05/17/85	330,000 $\pm$ 10,000	0.18 $\pm$ 0.17	<0.06	---	---	---
10/25/85	290,000 $\pm$ 10,000	0.16 $\pm$ 0.15	---	---	<2	---
01/14/86	330,000 $\pm$ 10,000	1.5 $\pm$ 0.3	---	---	2.9 $\pm$ 1.3	---
03/21/86	170,000 $\pm$ 10,000	0.42 $\pm$ 0.18	<0.05	---	---	---
			<u>SW8</u> (b)			
11/05/82	---	32 $\pm$ 1	<0.06	<0.07	2.8 $\pm$ 1.6	62 $\pm$ 7
07/25/83	120,000 $\pm$ 10,000	12 $\pm$ 1	<0.06	<0.06	0.7 $\pm$ 1.2	---
04/30/85	100,000 $\pm$ 10,000	9.4 $\pm$ 0.9	<0.06	<0.07	0.11 $\pm$ 0.72	---
10/25/85	26,000 $\pm$ 1,000	290 $\pm$ 10	---	---	<2	---
01/14/86	50,000 $\pm$ 1,000	3.1 $\pm$ 0.4	---	---	2.4 $\pm$ 1.2	---
03/21/86	95,000 $\pm$ 1,000	120 $\pm$ 10	0.12 $\pm$ 0.9	---	---	---
			<u>SW1</u> (b)			
05/17/85	11,000 $\pm$ 1,000	0.20 $\pm$ 0.17	<0.06	---	---	---
10/25/85	8,200 $\pm$ 200	0.21 $\pm$ 0.15	---	---	<2	---
01/14/86	19,000 $\pm$ 1,000	0.20 $\pm$ 0.14	---	---	1.7 $\pm$ 1.1	---
03/21/86	8,900 $\pm$ 300	0.61 $\pm$ 0.21	0.11 $\pm$ 0.10	---	---	---

EXHIBIT C.14 (Continued)

Date	Radionuclide Concentration (Bq/L)				Gross Alpha	Gross Beta
	^3H	^{90}Sr	^{137}Cs	^{60}Co		
			<u>SW2</u> ^(b)			
05/17/85	76,000 $\pm$ 1,000	0.23 $\pm$ 0.19	<0.05	---	---	---
10/25/85	66,000 $\pm$ 1,000	0.11 $\pm$ 0.14	---	---	<2	---
01/14/86	73,000 $\pm$ 1,000	0.77 $\pm$ 0.25	---	---	1.2 $\pm$ 1.0	---
03/21/86	77,000 $\pm$ 1,000	0.51 $\pm$ 0.23	<0.08	---	---	---
			<u>SW3</u> ^(b)			
05/17/85	75,000 $\pm$ 1,000	5.0 $\pm$ 0.6	<0.5	---	---	---
10/25/85	46,000 $\pm$ 1,000	4.8 $\pm$ 0.6	---	---	<2	---
01/14/86	140,000 $\pm$ 10,000	8.3 $\pm$ 0.7	---	---	<0.5	---
03/21/86	58,000 $\pm$ 1,000	5.7 $\pm$ 0.7	0.29 $\pm$.16	---	---	---

(a) $3.7 \times 10^{10} \text{ Bq} = 1 \text{ Ci}$

(b) See Exhibit C.12.

Source: IT (1986).

C.4 WASTE ANALYSIS PLAN

No further hazardous constituents are being disposed at SWSA 6. Historically, no waste analysis plan was prepared for SWSA 6 because, until May 1986, it was not considered a RCRA-regulated unit. After its status was changed, no waste was disposed there that constituted a regulated hazardous waste under RCRA. A Waste Analysis Plan will be addressed during the RFI.

Despite the lack of a waste management plan, ORNL has taken steps to ensure that no RCRA-regulated wastes are disposed in SWSA 6. Waste acceptance criteria have been established for landfill disposal and generators are required to certify waste contents in accordance with "Disposal Procedures for Hazardous Waste Materials" (ORNL, 1987).

D. CLOSURE REQUIREMENTS

This Closure Plan describes in detail the activities necessary for implementation of the interim corrective measures for the RCRA-regulated areas as well as providing a general description of those activities leading to final closure of SWSA 6, a SWMU encompassing areas in which both chemically hazardous and radioactive wastes have been disposed. This plan is submitted in response to RCRA, which provides for the regulation of those areas within the SWSA that received hazardous wastes between November 8, 1980, and May 1986, when disposal of hazardous wastes within SWSA 6 was discontinued. Because ORNL believes that a single comprehensive plan leading to final closure and corrective actions for all wastes disposed in SWSA 6 is the most effective strategy for long-term protection of human health and the environment, the Closure Plan for the RCRA-regulated areas is presented here in the context of overall closure of SWSA 6.

D.1 INTRODUCTION AND OVERVIEW OF STRATEGY

The strategy developed by ORNL is designed to conform with 40 CFR 265 Subpart G [(TN Rule 1200-1-11-.05(7))] and to satisfy the closure and corrective action requirements for all waste management areas at SWSA 6. The strategy is predicated primarily on closure in-place with corrective actions focused on groundwater quality. In-place closure of the majority of SWSA 6 is preferred due to the large volume of buried wastes, the exposures and possible environmental impacts that would occur during excavation/transport activities associated with clean-closure, and the lack of a permitted facility willing to receive the wastes. Corrective actions focus on groundwater because available data indicate that leaching is the most likely release mechanism for contaminants. Despite these assumptions, however, the strategy does not preclude clean-closure of selected areas within SWSA 6 nor does it preclude a broader scope of corrective actions.

The minimum technical requirement for in-place closure is construction of a low-permeability cap meeting performance standards

specified in 40 CFR 265 Subpart G [TN Rule 1200-1-11-.05(14)(e)]. A cap meeting these performance standards cannot immediately be constructed at SWSA 6 due to certainty that severe long-term subsidence of trenches will occur throughout the site.

Trench subsidence is a major problem in remediating shallow land disposal sites. Subsidence depressions not only create catchments for surface runoff and precipitation, but also channel water into contact with buried waste. Furthermore, surface stability is necessary for almost all infiltration and intrusion barriers. Subsidence has been observed repeatedly in SWSAs 4 and 5 (predecessors of SWSA 6) and is attributed to gradual decomposition and consolidation of wastes. Subsidence will result initially in ponding of water over the affected trenches, followed by eventual cap failure as mechanical properties are exceeded. Without measures to preclude trench settlement, cap integrity could only be assured with intensive maintenance, including frequent removal of selected portions of the cap for backfilling to maintain a grade adequate for surface water runoff.

The most effective and practical manner of minimizing long-term subsidence after closure is to minimize the volume of voids in the wastes at the time the cap is constructed. Because public health, environmental impacts, and technical difficulties will likely preclude excavating the wastes and treating them to reduce void space (e.g., shredding and/or incineration), in-place compaction and grouting are the most likely technologies for reducing void space.

The most common techniques for compaction and accelerated consolidation of solid wastes involve the use of standard vehicular compaction equipment (e.g., vibratory rollers, sheepfoot rollers) and surcharging the site with soil, respectively. Due to the geometry of the waste trenches, however, the use of these techniques is inappropriate. Standard compaction equipment does not generate the energy required to significantly compact wastes at depths greater than several feet. An alternate approach would be to bridge the trenches with precast concrete panels or other structural

components; however, all common structural materials are subject to degradation, and long-term cap subsidence would be unavoidable. Bridging would result in minimal transfer of surcharge stresses to depth within the trenches, resulting in minimal reduction in void space.

An alternate technique that does not suffer to the same degree from the above limitations is dynamic compaction, wherein a weight (e.g., 10 tons) is dropped by crane from a considerable height (e.g., 40 ft) onto the ground surface. ORNL has completed a limited field trial using dynamic compaction and believes that it, along with grouting, has the greatest potential for application to closure of SWSA 6.

Spalding (1986) conducted a demonstration in SWSA 6 to evaluate the degree of consolidation that could be achieved by dynamic compaction of a closed burial trench in a cohesive soil formation. Trench 271 in the northern portion of SWSA 6 was selected for this demonstration. Waste disposal records indicate that the trench was operational from March to June 1978, during which time about 880 ft³ of waste weighing about 8500 lbs were disposed there. The waste consisted primarily of contaminated equipment, demolition debris, and dry solids, with a small amount of biological waste. Packaging was variable. The inventory of radioisotopes, totaling about 80 Ci, included mostly strontium-90, with smaller amounts of cesium-137, samarium-151, thorium-232, uranium-238, technetium-99, cesium-134, ruthenium-106, cerium-144, iridium-192, cobalt-60, iron-59, manganese-54, californium-252, curium-244, and tin-121.

Water from the Emergency Waste Basin (EWB) just to the east of SWSA 6 was pumped into the trench to determine the void space, which measured 2790 ft³. Additional precompaction characterization included trench cap permeability (3×10^{-7} m/sec) and subsurface waste/backfill hydraulic conductivity (>0.01 m/sec). Compaction was accomplished by repeatedly dropping a 4-ton, steel-reinforced concrete cylinder from heights of 12 to 25 ft using the whipline of a 70-ton crane. The ground surface was depressed an average of

2.6 ft, with some areas depressed as much as 6.5 ft. The surveyed volumetric depression totaled 64 percent of the measured trench void space. Neither trench cap bulk density nor permeability was affected by compaction, indicating that the consolidation was primarily subsurface. Spalding (1986) concluded that dynamic compaction was an excellent and inexpensive way to collapse trench void space.

Concerns have been raised, however, about the potential for accelerated release of contaminants to groundwater if containers are ruptured by dynamic compaction. Consequently, the closure/corrective action program will include full-scale field trials within SWSA 6 to assess the effectiveness and implementability of dynamic compaction and grouting and to assess the potential impacts of dynamic compaction on groundwater quality. These studies are designated Test Area for Remedial Action (TARA) Phases I and II and are described in Section E.5, Closure of Disposal Areas.

The strategy for SWSA 6 closure and corrective action described in this plan assumes that the TARA program will affirm the feasibility of dynamic compaction (and grouting) for SWSA 6 and that some groundwater extraction and treatment will be required during dynamic compaction and for an extended period after closure. To allow expedited design and construction of a groundwater extraction and treatment system for final closure, the closure/corrective action strategy includes a groundwater treatment pilot study. This study will involve construction of a limited groundwater extraction system and a pilot treatment plant, which will be designed and scheduled to allow groundwater extraction and treatment in conjunction with TARA Phase II.

D.2 CORRECTIVE ACTION-RELATED ACTIVITIES AND SCHEDULING

The initial step of the RCRA Corrective Action process, a RCRA Facility Assessment (RFA), was completed for the entire ORNL facility in March 1987. For SWSA 6, the RFA identified the need for an RI to further characterize the nature, extent, and rate of

migration for releases of concern. The RI has since been changed to an RFI because of applicable RCRA regulations. It is expected that the RFI will in turn identify the need for a Corrective Measures Study (CMS), which will lead to selection of corrective measures, formalized in a Record of Decision (ROD). Following completion of the ROD process, the selected corrective measures will be implemented. As previously indicated, ORNL proposes to combine the RCRA Corrective Action Program with the closure process.

An overview of the schedule for final closure and corrective action is presented in Exhibit E-1. A detailed breakdown of the schedule is presented in Exhibit E-2 and Section E.7. Activities are interrelated and are scheduled to allow input of critical information from earlier activities to latter activities.

This Closure Plan primarily provides a procedural framework for achieving final closure and corrective action. ORNL will amend the Closure Plan following the development of information allowing a significant increase in the level of detail with which specific activities leading to final closure and corrective action are described.

In addition to amendments as described above, ORNL will amend the Closure Plan in accordance with 40 CFR 265 Subpart G [(TN Rule 1200-1-11-.05(7)(c)(3))] whenever it is affected by:

- o A change in SWSA 6 operations or design
- o An unexpected event during the closure period
- o An event that impacts the expected date of final closure

Moreover, TN Rule 1200-1-11-.05(7)(c)(4)(iv) allows the Commissioner of the TDHE to modify the Closure Plan to assure that it is consistent with appropriate regulations.

E. CLOSURE PLAN

E.1 CLOSURE PERFORMANCE STANDARD

40 CFR 265.111, TN Rule 1200-1-11-.05(7)(b)

Final closure of SWSA 6, as achieved through the activities described in the following sections, will be designed in accordance with 40 CFR 265 Subpart G [(TN Rule 1200-1-11-.05(7)(b))] to:

- o Minimize the need for further maintenance
- o Control, minimize, or eliminate, to the extent necessary to protect human health and the environment, post-closure escape of: 1) hazardous waste and hazardous waste constituents, 2) leachate and contaminated runoff, and 3) hazardous waste decomposition products to the ground, surface water, groundwater, or the atmosphere.

Final selection of technologies for closure and corrective action will result from the ROD process. In general, however, it is anticipated that these goals will be accomplished at final closure by the following measures:

- o A low permeability cap will be constructed over waste disposal areas to minimize surface water infiltration. Cap placement will be preceded by waste densification and/or grouting as required to minimize the long-term subsidence potential. The final cap design will meet or exceed RCRA cap performance standards in the RCRA-regulated areas. The cap surface will be stabilized to minimize erosion due to sheet flow runoff.
- o Surface water runoff and runoff controls will be constructed to minimize the potential for surface water infiltration into waste areas and to minimize the potential for erosion. Controls will include surface water diversion berms and ditches and energy dissipators.
- o A combination of vertical barriers (e.g., soil-bentonite slurry wall) and french drains will be constructed to lower the groundwater table below wastes, where feasible. Lowering the groundwater table below wastes (in combination with capping) will minimize leachate generation and, consequently, the migration of contaminants off-site.
- o If required, groundwater will be extracted and treated to reduce discharge of contaminants that may result from closure activities.

Section E.5, "Closure of Disposal Areas," describes all the steps in the proposed strategy leading to final closure and corrective action for SWSA 6.

E.2 CLOSURE ACTIVITIES

40 CFR 265.112, TN Rule 1200-1-11-.05(7)(c)

Implementation of final closure for the majority of SWSA 6, including all the RCRA-regulated areas, will be completed in one continuous operation. The overall closure strategy is based upon the interrelationship of various closure activities and requires a phased approach, wherein results from earlier activities provide input for the design of subsequent phases. ORNL believes that an iterative approach is necessary to achieve the closure performance standard as delineated in 40 CFR 265 Subpart G [(TN Rule 1200-1-11-.05(7)(b))]. Closure requirements and methods to meet these requirements are described in the following sections of this document.

(1)	265.111 [.05(7)(b)]	Closure Performance Standard:	E.1
(2)	265.113 [.05(7)(d)]	Closure; Time Allowed for Closure:	E.7
(3)	265.114 [.05(7)(e)]	Disposal or Decontamination of Equipment:	E.4
(4)	265.115 [.05(7)(f)]	Certification of Closure:	E.5
(5)	265.178	Closure of Containers:	Not Applicable
(6)	265.197 [.05(10)(e)]	Closure of Tanks:	Not Applicable
(7)	265.228 [.05(11)(g)]	Closure of Surface Impoundments:	Not Applicable
(8)	265.258 [.05(12)(h)]	Closure of Waste Piles:	Not Applicable
(9)	265.280 [.05(13)(g)]	Closure of Land Treatment Facility:	Not Applicable
(10)	265.310 [.05(14)(e)]	Closure of Landfills:	E.5
(11)	265.351 [.05(15)(e)]	Closure of Incinerators:	Not Applicable

Closure will commence with installation of interim corrective measures for the RCRA-regulated areas within SWSA 6. Concurrent with these activities will be the first phase of the RFI, which is shown in Exhibits E.1 and E.2 and discussed in more detail in Section E.5. Phase II RFI activities will target specific data gaps; thereafter, the RFI Report and public health and environmental assessment will be completed. Supporting projects, which will provide valuable input for the corrective measures implementation pursuant to final closure, include TARA Phase I, TARA Phase II, SWSA 6 Perimeter Groundwater Monitoring, and a Groundwater Treatment Pilot Study. These are shown on Exhibits E.1 and E.2 and discussed in Section E.5.

E.3 MAXIMUM WASTE INVENTORY

40 CFR 265.112(a)(2), TN Rule 1200-1-11-.05(7)(c)(2)(iii)

SWSA 6 consists of more than 1000 individual trenches and auger holes, about one-third of which have been designated as RCRA-regulated areas. The exact inventory of wastes disposed in SWSA 6 is unknown. Through May 1986 it is estimated that approximately 38,000 yd³ of low-level waste containing more than 200,000 Ci of radioactivity had been buried at the site (Davis et al., 1987; Boegly et al., 1985). At that time, estimates from waste records indicated that 25 percent of the disposal acreage might have been used for disposal of some RCRA-regulated wastes, which were thought to be principally lead, xylene, and toluene. A more detailed description of the waste in SWSA 6 is presented in Section C, "Waste Characteristics."

E.4 INVENTORY REMOVAL; DISPOSAL OR DECONTAMINATION OF EQUIPMENT

40 CFR 265.112(a)(3), 40 CFR 265.114,
TN Rule 1200-1-11-.05(7)(c)(iv)

As described in Section E.5, "Closure of Disposal Areas," the majority of all wastes disposed in SWSA 6--including wastes in RCRA-regulated areas--will be closed in place. Consequently, there should be no removal or off-site disposal of hazardous wastes at final closure. In addition, there are no tanks, vaults, or other equipment within SWSA 6 that were used to hold hazardous wastes

prior to disposal into the subsurface. Consequently there will be no decontamination of such equipment during closure.

Construction equipment employed during closure of SWSA 6--including the RCRA-regulated areas--will be decontaminated according to approved procedures in the Waste Management Plan being developed for this project. This plan will predict the quantities and types of wastes to be generated, describe how the wastes will be disposed, and establish a procedure for the decontamination of equipment. Bechtel National, Inc. (BNI), is performing a health and safety survey of the site. Part of this information will assist in predicting the probability of encountering contaminated soil and the resultant need for equipment decontamination and contaminated soil disposal. During the construction activities associated with the interim control measures, health physics and industrial hygiene personnel will be on site to monitor the personnel, the equipment, and the soil to determine if decontamination and/or contaminated waste disposal is necessary.

Any equipment that becomes contaminated during closure of SWSA will be decontaminated according to ORNL Procedure "Decontamination of Equipment and Release for Unrestricted Use;" this includes the following general procedures.

- o All equipment will be monitored periodically and at the end of the project to determine if it is contaminated. Release limits will be established for radiological contamination. If the monitoring indicates that the equipment exceeds the release limit, then decontamination will take place. Release limits will be established in the Waste Management Plan. If equipment comes into contact with known or suspected chemical contaminants, then decontamination will take place until it is free of visible contamination.
- o Bulk materials, such as mud, will be removed manually prior to other decontamination techniques being applied.
- o The decontamination technique or techniques, such as vacuum cleaning, water, steam, detergents, solvents, and sand blasting, to be used will be determined based upon the type of contamination present. Such guidelines will be provided in the Waste Management Plan. Simple methods will be selected first, and then progressively more severe methods will be selected if the simpler ones are unsuccessful.

- o The liquid runoff and solid residue remaining after decontamination activities will be contained, packaged, and disposed according to the Waste Management Plan.
- o If decontamination is unsuccessful in achieving the release limits by normal methods, then each such piece of equipment will be considered on a case-by-case basis and will not be released for unrestricted use until the release limits are met.
- o Records will be maintained on the release of equipment.

The contractor will have personnel trained by ORNL as waste packagers. If health physics and/or industrial hygiene monitoring indicates that a waste is contaminated, the trained waste packagers will prepare the waste for disposal by ORNL according to its existing procedures. If the waste is not contaminated, it will be disposed accordingly. The Waste Management Plan will be available by October 1, 1988.

E.5 CLOSURE OF DISPOSAL AREAS

40 CFR 265.310, 40 CFR 265.112, TN Rule 1200-1-11-.05(7)(c)(2)
TN Rule 1200-1-11-.05(14)(e)

ORNL has developed a single comprehensive plan leading to final closure and corrective actions for both radioactive and hazardous waste disposal areas within SWSA 6. An overview of the plan and the rationale were provided earlier in this Closure Plan.

Closure of SWSA 6 will take place in two phases:

- 1) Implementation of a RCRA Interim Corrective Measure (ICM)
 - o The schedule for the ICM is presented in Section E.7.
 - o Technical features of the ICM are described later in this section.
- 2) Implementation of a RCRA RFI and CMS, pilot and bench-scale studies, followed by final RCRA closure and corrective actions
 - o The schedule for these activities is presented in Section E.7.
 - o Technical features of these activities are described later in this section.

E.5.a Interim Corrective Measure for RCRA-Regulated Areas

While ORNL conducts the necessary programs required to resolve the technical problem of subsidence and other activities required for complete closure and corrective action, a temporary cap will be installed over the RCRA-regulated areas and maintained until final closure. Implementing the ICM as the first step in closure of SWSA 6 will meet the November 8, 1988, regulatory deadline for initiation of closure, yet permit completion of activities essential to providing long-term protection of human health and the environment.

A certified-for-construction design package for the ICM is included as Volume 2 of this Closure Plan. The design package includes: 1) construction specifications associated with the installation of the synthetic membrane liner, 2) a hydrologic drainage study of the impacts of the ICM on surface water runoff rates, and 3) design drawings showing cap and surface water control layouts for all of the RCRA-regulated areas. The scope of the ICM includes the following general items:

- o Placing a synthetic membrane cap over the affected areas to minimize infiltration of surface water
- o Constructing ditches and berms to collect and route surface water runoff and runoff to existing drainageways
- o Constructing surface water runoff energy dissipators to reduce the potential for erosion within the existing drainageways
- o Relocating existing facilities to accommodate capping of the RCRA areas
- o Inspection and maintenance

The synthetic membrane cap is 80-mil HDPE. HDPE is resistant to ultraviolet light and will provide adequate performance for the design life of the ICM, which is 5 years. The synthetic membrane will be anchored at regular intervals to reduce membrane response during high winds. Vents will be provided.

Surface water control measures will include: 1) perimeter runoff and runoff collection ditches/berms, 2) routing ditches to conduct collected surface water to the existing natural drainageways, and 3) energy dissipators to reduce the flow velocity (and hence the erosion potential) of surface water runoff entering the existing drainageways. Collection ditches will be lined with HDPE to reduce infiltration and with riprap to control flow velocities. Ditch cross-sections, grade, and riprap will be designed to accommodate the runoff from the 24-hr, 25-yr storm. To the extent feasible, collection and routing ditches will not traverse trenches or auger holes.

As indicated on the drawings in the design package, construction of the cap and associated surface water control measures will require elimination or relocation of existing fencing, service roads, wells, and other facilities. General site work and site disturbance will be minimized to the extent feasible. Upon completion of general site work, disturbed areas outside the capped areas will be graded and reseeded to minimize erosion.

ORNL will commit to a program of intensive inspection and maintenance to assure the continued effectiveness of the ICM. The program will be implemented upon construction of the ICM and will continue until final closure of SWSA 6. With frequent inspection and maintenance, it is expected that the performance of the ICM will be comparable to that of a RCRA cap. A Post Closure Surveillance and Maintenance Plan is being prepared to finalize the inspection items, frequencies, responsibilities, procedures, and checklists. This Plan will be available by October 1, 1988. It is planned that the basic inspection of the liner and drainage ditches will occur monthly and after significant rainfall events. It is expected that the following general procedures will be followed:

- o A log will be kept to document the inspection date and time, the condition of each of the areas inspected, any maintenance/repairs required, the date that the repairs are completed, and the personnel involved. Particular items of inspection will include the condition of the synthetic membrane liner (e.g., punctures, tears, abrasion, perimeter

anchorage), subsidence beneath the liner (e.g., as evidenced by ponding), displacement of riprap, and erosion problems. In addition, the ICM will be inspected periodically during storm events and once each quarter to verify that surface runoff and runoff provisions are adequate.

- o Maintenance will be performed immediately or as soon as weather permits by appropriately trained personnel. An adequate inventory of materials will be on-site for all routine maintenance (e.g., liner membrane and seaming supplies, riprap, backfill). Damage to the liner will be repaired specifically as recommended by the manufacturer. The Post-Closure Surveillance and Maintenance Plan, which will be available by October 1, 1988, will address these issues in detail.
- o Significant subsidence will be remedied by removing the liner from the affected area (either by rolling up the liner from the edge or by cutting out and hand compacting a section), backfilling the depression with clay and hand compacting, and replacing the liner (as a patch if necessary). Maintenance of riprap and erosion control will be performed so as to substantively restore conditions to those prevailing immediately following initial construction.
- o Following closure, ORNL will submit to the EPA Region IV Administrator and to the Commissioner of the TDHE certification that SWSA 6 has been closed in accordance with the plans and specifications provided herein or in amendments thereto. The certification must be prepared by an independent professional engineer registered in the State of Tennessee.
- o Sampling and analysis activities to be conducted during the design life of the ICM include those associated with the perimeter groundwater quality monitoring wells and those conducted as part of the RFI. Groundwater, surface water, and soils will be sampled and analyzed during the RFI. Specific sampling and analyses to be performed related to the ICM were identified in the RFI Work Plan, submitted to the DOE in July 1988. The results of ICM monitoring information will be used in the development of alternatives in the CMS. In conformance with RCRA, implementation of the ICM will commence no later than November 8, 1988, and will be completed within 180 days (i.e., by the end of April 1989), with an extension being possible for overriding technical reasons or adverse weather conditions. The ICM will significantly reduce or eliminate surface water infiltration in the affected areas, thereby reducing the rate at which contaminants are leached into groundwater. The ICM will remain in place until implementation of final closure and corrective actions (approximately 37 months). The ICM is essentially independent of other activities leading to final closure and corrective action; however, temporary modifications to the ICM may be required to allow completion of the RFI and pilot studies.

E.5.b RCRA Facility Investigation

The RFI is the field investigation portion of the RCRA corrective action program. The objectives of the RFI are to develop sufficient information to perform a public health and environmental assessment for SWSA 6 and to provide sufficient information to identify and evaluate remedial technologies that may be applicable for final closure and corrective actions.

The RFI process will involve the following major steps:

- o ORNL preparation of the RFI Work Plan
- o Agency review of the RFI Work Plan
- o ORNL response to agency comments
- o Phase I RFI field activities
- o Phase II RFI field activities
- o Public health and environmental assessment
- o Agency review of Phase II RFI Report
- o Response to agency comments

The RFI Work Plan both documents the development of a scope of work for the RFI and specifies field sampling activities and analyses to be performed (including locations, materials, and methods). This document was submitted to the DOE for subsequent submittal to regulatory agencies for review in July 1988 and will subsequently be modified as appropriate to reflect review comments. Upon resolution of agency comments, the Phase I RFI will be initiated. Based upon existing data regarding SWSA 6 and upon remedial investigation sampling activities identified for ORNL SWSAs 4 and 5, SWSA 6 Phase I RFI field activities are assumed to include:

- o Radiation walkover and dose rate surveys
- o Geophysical and civil surveys
- o Soil gas sampling

- o Soil and sediment sampling
- o Surface water and groundwater sampling
- o Surface water flow and groundwater elevation measurements

If, upon completion of the Phase I RFI, the data are insufficient to complete a public health and environmental assessment, a Phase II RFI will be performed. The Phase II RFI would target only specific data gaps. For example, Phase II RFI field activities might include: 1) sampling of media on a finer grid for increased precision of contaminant delineation, 2) sampling to determine physical and engineering characteristics of waste/soil/rock as required for evaluation of corrective action/closure technologies, and 3) repeat sampling for verification of unexpected Phase I results. As indicated in Exhibit E.1 (see end of Section E), it is assumed that a Phase II RFI will be required.

ORNL expects to begin the Phase I RFI no later than mid-October 1988 and to complete it mid-January 1990. The Phase II RFI, if required, will commence mid-January 1990 and continue to mid-August 1990. The specific field activities assumed to constitute the RFI are illustrated in Exhibit E.2 (see end of Section E).

The RFI will provide information inputs for other activities in the closure/corrective action process. These inputs are represented as arrows in Exhibit E.1, and are as follows:

- o The results of the initial groundwater quality characterization efforts, expected to be available in the second quarter of CY 1989, are required for the design of the pilot groundwater treatment plant.
- o The results of the Phase I RFI will be used in the design of TARA Phase II (selection of the trenches to be compacted, layout of groundwater monitoring and extraction wells). (Tara Phase II is described separately below.)

- o Early results of the Phase II RFI and the public health and environmental assessment will provide data to allow continued work on the CMS.
- o Upon completion of ORNL's response to agency comments on the RFI Report, expected to occur mid-November 1990, the final RFI will provide input to the CMS.

Following completion of Phase II RFI field sampling and analyses, ORNL will complete the public health and environmental assessment and RFI Report. The RFI Report will summarize the data collected during the RFI and will document the conclusions derived therefrom. The RFI Report will be submitted to the regulatory agencies for review. ORNL will subsequently modify the RFI Report, as appropriate, to reflect agency review comments.

E.5.c Supporting Projects

Although selection of technologies for final closure and corrective action cannot be made until completion of the CMS, it is anticipated that the following technologies will be among those selected: dynamic compaction and grouting of trenches, groundwater extraction and treatment, and capping. To provide sufficient data to adequately evaluate these technologies during the CMS and to effectively implement them during final closure and corrective action, pilot studies of these technologies will be performed during the closure period. Activities include TARA Phase I, TARA Phase II, SWSA 6 Perimeter Groundwater Monitoring, and a Groundwater Treatment Pilot Study. Each of these activities is described below.

As previously stated, the primary difficulty precluding immediate capping of the RCRA-regulated areas is the high probability of severe trench subsidence. TARA Phase I (and TARA Phase II, discussed below) are projects intended to investigate the effectiveness of dynamic compaction and trench grouting as techniques for minimizing long-term trench subsidence.

TARA Phase I will take place on an approximately one acre hillock containing 19 trenches in the northeastern portion of SWSA 6. This is an area believed to contain few buried containers of liquid hazardous or radioactive wastes. The program entails dynamic compaction of five of the trenches, grouting of a selected number of those compacted, then construction of instrumented low permeability caps over a specified areas. The effectiveness of dynamic compaction will be assessed using penetration testing and other appropriate techniques. Two types of caps will be constructed for comparison of performance: a "RCRA cap" conforming to EPA guidelines for hazardous wastes, and a "rad cap" conforming to applicable guidance for low-level radioactive wastes. The performance of the cap will be monitored regularly in addition to the normal post-closure inspection and maintenance activities.

The general goal of TARA Phase II is to assess the impacts of dynamic compaction on the release of contaminants to groundwater. TARA Phase II will involve dynamic compaction of a selected group of trenches in which there is a significant probability that containers of liquid hazardous wastes were disposed. During dynamic compaction, downgradient groundwater will be monitored and, if required, extracted and treated.

Secondary objectives of TARA Phase II will be to increase the amount of field experience with dynamic compaction and to supplement the database for evaluating the effectiveness of dynamic compaction.

Inputs to TARA Phase II include the experience gained in TARA Phase I, preliminary data from the RFI, completion of the pilot groundwater treatment plant, and preliminary results of pilot studies. It is planned to use the pilot treatment plant for any groundwater treatment that may be required in conjunction with TARA Phase II. Data from TARA Phase II will provide input to the CMS.

The TARA Phase II area has not yet been selected. Area selection criteria will stem from the need to construct an effective yet economical groundwater monitoring and extraction and treatment

system. A TARA Phase II Plan will be developed and delivered to the regulatory agencies for comment prior to commencing field activities.

It is possible that final closure and corrective action for SWSA 6 will involve groundwater extraction and treatment. To permit expedited design and construction of such a system, should it be selected, a Groundwater Treatment Pilot Study will be initiated in October 1988.

The groundwater treatment pilot study work plan will delineate the specific objectives of the study and the strategy for achieving the objectives. The work plan will specify tasks to be completed, schedule, and responsibilities. The work plan will be submitted for agency review when complete.

The study will involve an evaluation of available data (including results from the groundwater monitoring program described below), design and construction of a groundwater extraction system and a groundwater treatment pilot plant, followed by pilot studies. Upon completion of the pilot studies in mid-November 1989, the extraction system and treatment plant will be employed in the treatment of groundwater in conjunction with TARA Phase II. The results of the Groundwater Treatment Pilot Study will be used in the CMS and to optimize the design of any groundwater treatment system that may be required for final closure and corrective action.

To maintain a fast-track schedule, work will commence on evaluation of data and development of performance standards at the same time the plan is submitted for agency review. Design will commence upon receipt of agency review comments on the workplan. Following design and resolution of agency comments on the design, the system will be constructed. Pilot studies will follow start-up and shakedown of the plant. If the pilot studies indicate that the processes selected are not appropriate, the treatment concepts will be revised and the pilot treatment plant will be modified. Modifications would be followed by additional pilot studies. The schedules shown in

Exhibits E.1 and E.2 assume that the initial treatment concepts will not require revision.

Upon completion of the pilot studies in mid-November 1989, the extraction system and treatment plant will be employed in the treatment of groundwater in conjunction with TARA Phase II.

A network of compliance monitoring wells has been installed around the perimeter of SWSA 6. This network will be sampled periodically throughout the closure period in addition to the quarterly monitoring to be conducted for regulatory compliance. It is likely that the existing well system will be supplemented with additional wells during the RFI and that sampling of these new wells will be coordinated with sampling of the existing wells.

Results from perimeter groundwater monitoring will provide input to the design of the groundwater treatment pilot plant and provide "scoping information" to aid in the design of an effective assessment of groundwater quality within and beyond the boundary of SWSA 6 during the RFI.

The interior groundwater monitoring to be conducted for the RFI is identified as a supporting activity for closure; upon completion of final closure in 1993, however, this monitoring will continue as part of the post-closure activities.

E.5.d RCRA Corrective Measure Study

The third major component of the RCRA corrective action program (following the RFA and RFI) is completion of a CMS. The CMS will generally conform with "Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA," (EPA, 1988). The primary steps of the CMS process are:

- o Identification and screening of remedial technologies
- o Assembly and detailed development of alternatives

- o Analysis of alternatives (effectiveness, implementability, cost)
- o Preparation of CMS report
- o Agency and public reviews/ response to comments

The initial four steps are well described in the above referenced guidance document. To expedite the schedule, regulatory agency reviews and public reviews (final step) are scheduled simultaneously.

The CMS will develop and evaluate a range of alternatives for an integrated program of final closure and corrective action; the study will recommend one of the alternatives for implementation. The CMS will begin following completion of the Phase I RFI Report and will be submitted in draft form for agency review approximately one month following resolution of agency review comments on the Phase II RFI Report (mid-December 1990). In addition to the results of the RFI, the results of the TARA programs and the groundwater treatment pilot studies will also provide input to the CMS.

E.5.e Record of Decision

The ROD process will result in selection of a specific and detailed plan for implementation of final closure and corrective action. The general steps in the process are: 1) EPA/TDHE/DOE negotiations and selection of remedy/closure approach, 2) ROD public comment period, and 3) response to public comments. The process begins upon resolution of agency and public review comments on the CMS (expected to be mid-March 1991) and should be complete within 4 months (mid-July 1991). To maintain a fast-track schedule, conceptual and preliminary designs for final closure and corrective action will commence as soon as the selection of remedy/closure approach is made. As appropriate, the designs will be modified to reflect public comments.

This Closure Plan assumes that the ROD will specify the following combination of technologies for final closure and corrective action: 1) trench stabilization (e.g. dynamic compaction and/or

grouting), 2) vertical subsurface groundwater barriers and/or french collection drains, 3) groundwater extraction and treatment, 4) surface water runoff and runoff controls, and 5) capping (per RCRA and other regulatory guidance). Post-closure activities are assumed to include: 1) institutional control for a minimum of 100 years, 2) regular inspection and maintenance, and 3) groundwater monitoring.

If additional technologies are specified in the ROD (other than those incidental to the technologies listed above), the permit would be reopened and modified accordingly. ORNL proposes that such amendments to the permit be classified as minor modifications.

E.5.f Final Closure and Corrective Actions

Upon completion of the ROD process, which is estimated to take approximately 26 months to implement, closure for all of SWSA 6 can be undertaken. This is based on an assumed combination of technologies (dynamic compaction, subsurface barriers/drains, groundwater extraction and treatment, and capping). The completion date of October 1993 is also predicated on being able to initiate design following resolution of agency and public review comments on the CMS. It is anticipated that the primary technologies of the selected remedy will be apparent at this time. Design concepts will be modified as required by the ROD.

Selection of closure and corrective action technologies for SWSA 6 will be made during the ROD process following completion of the CMS. Consequently it is initially not possible to provide a significant level of technical detail regarding closure/post-closure provisions. This Closure Plan primarily provides a procedural framework for achieving final closure and corrective action. ORNL will amend the Closure Plan following the development of information allowing a significant increase in the level of detail with which specific activities leading to final closure and corrective action are described.

The strategy for implementation of final closure and corrective action would be as follows. Surface water controls and the groundwater extraction and treatment system would be constructed prior to dynamic compaction. Surface water controls would be designed to minimize or eliminate runoff to the areas to be compacted/grouted and capped. The measures would also control runoff to minimize infiltration and erosion. The groundwater extraction and treatment system would be designed to intercept potentially contaminated groundwaters resulting from trench stabilization by dynamic compaction. Groundwater would be extracted, treated, and discharged to White Oak Lake (as required). Trench grouting would be used in addition to dynamic compaction as appropriate. As each trench area is stabilized, a low permeability cap would be constructed over that area. The cap would work in conjunction with the vertical groundwater barriers and collection drains to lower the seasonally high groundwater table to below trench bottoms where feasible. The cap design would be determined through the ROD process, and would, therefore, meet the performance objectives stated in applicable regulations. Groundwater extraction and treatment would continue until monitoring indicated that the rate of release of contaminants had dropped to levels protective of public health and the environment.

The schedules shown in Exhibits E.1 and E.2 for implementation of final closure and corrective action are based on this assumed strategy. Agency reviews are included for key documents and design stages. Following closure, ORNL will submit to the EPA Region IV Administrator and to the Commissioner of the TDHE certification that SWSA 6 has been closed in accordance with the plans and specifications provided herein or in amendments thereto. The certification must be prepared by an independent professional engineer registered in the State of Tennessee.

E.6 OTHER ACTIVITIES RELATED TO CLOSURE

40 CFR 265.112, TN Rule 1200-1-11-.05(7)(c)(2)(v)

To ensure that SWSA 6 is closed in a manner meeting the closure performance standards specified in 40 CFR 265 Subpart G [TN Rule

1200-1-11-.05(7)(b)] additional monitoring activities will be necessary [TN Rule 1200-1-11-.05(7)(c)(2)(v)]. Groundwater monitoring, which is anticipated to be foremost among these additional activities, is discussed in detail in Section F. Provisions for runon/runoff control for the interim corrective measures are discussed in general in Section E.5.a and in detail in the certified-for-construction design package included under separate cover (Volume 2). Methods for runon/runoff control for final closure of SWSA 6 will be identified during the CMS and submitted for agency approval. If the RFI shows that trench leachate collection is necessary, means for implementing it will be addressed in the CMS. It is expected that a combination of vertical barriers and french drains will be constructed to lower the groundwater table below the wastes, hence minimizing leachate formation.

E.7 SCHEDULE FOR CLOSURE

40 CFR 265.112(a)(4), TN Rule 1200-1-11-.05(7)(c)(vi)

An overview of the schedule for all activities leading to final closure and corrective action is presented in Exhibit E.1. Activities are sequenced to allow input of critical information from earlier activities to latter activities. Key information inputs are illustrated as arrows in Exhibit E.1.

The schedule described in Exhibits E.1 and E.2 is based on assumptions regarding the nature and extent of contamination, the availability of resources, and which closure/corrective action technologies will be appropriate to the site and acceptable to regulatory agencies. As stated earlier, ORNL will amend the Closure Plan (including the schedule) as required during the closure period to reflect the best information available.

It is the intent of ORNL to adopt a "fast-track" approach to final closure and corrective action for SWSA 6. Techniques proposed to expedite implementation include:

- o Minimization of additional data gathering
- o Concurrent reviews by regulatory agencies
- o Value-engineering early in design phase
- o Early, focused reviews of critical parts of the design
- o Early and constant communication with regulatory officials to overcome institutional constraints pertaining to design/construction
- o Procurement of construction permits during design phase where feasible
- o Division of the bid package into components and release as soon as practical

EXHIBIT E.2
DETAILED ILLUSTRATION OF ACTIVITIES FOR CLOSURE OF SWSA 6

SUPPORTING PROJECTS

TARA PHASE I

TARA PHASE II PLAN

NOTES:

1. "A" CORRESPONDS TO SUBMITTAL OF PERMIT APPLICATION TO REGULATORY AGENCIES.
2. ADMINISTRATIVE PLANS INCLUDE PROJECT MANAGEMENT, QA, ES & H, DECONTAMINATION, AND WASTE MANAGEMENT PLANS.

KEY:

SHEET 2 OF 7

EXHIBIT E.2 (CONTINUED)

EXHIBIT E.2 (CONTINUED)

GROUNDWATER TREATMENT SYSTEM
SEE NOTE 1

1. SCHEDULE ASSUMES SINGLE PRIME DESIGN/CONSTRUCT CONTRACTOR.
2. ADMINISTRATIVE PLANS INCLUDE PROJECT MANAGEMENT, QA, ES & H, DECONTAMINATION, AND WASTE MANAGEMENT PLANS.

KEY:

2305 EBHS

EXHIBIT E.2 (CONTINUED)

FINAL CLOSURE/CONNECTIVE MEASURES - CONT'D

GROUNDWATER EXTRACTION SYSTEM (TRENCH DRAIN & WELLS)

NOTES:

- ADMINISTRATIVE PLANS INCLUDE PROJECT MANAGEMENT, LES, DECONTAMINATION, AND WASTE MANAGEMENT PLANS.

KEY:

SHEET 6 OF 7

EXHIBIT E.2 (CONTINUED)

F. GROUNDWATER MONITORING

40 CFR 265.90, TN Rule 1200-1-11-.05(7)(c)(2)(v)

F.1 EXEMPTION FROM GROUNDWATER PROTECTION REQUIREMENTS

ORNL does not seek a waiver from the groundwater monitoring requirements.

F.2 INTERIM STATUS PERIOD GROUNDWATER MONITORING DATA

Throughout the operational history of SWSA 6, numerous wells have been drilled for a variety of research and monitoring purposes. Data from some of these investigations are included in this Closure Plan. However, because of questions pertaining to their defensibility by EPA standards, they should be viewed only as scoping data to direct future studies during the RFI. Beginning in February 1987, a network of groundwater quality monitoring wells was installed. During well installation, all phases of the drilling, installation, and development were in adherence with the EPA RCRA Groundwater Monitoring Technical Enforcement Guidance Document (TEGD) (EPA, 1986). The wells were constructed in three basic configurations. The first was a standard soil/bedrock interface arrangement with stainless steel screen and casing. The second type was a stainless steel screen and casing string installed into the bedrock with the overlying regolith being isolated via a surface casing. The third configuration was also a bedrock well installation with an open interval drilled beneath a stainless steel riser casing with a surface casing isolating the regolith and weathered bedrock. Illustration of these types of wells, details of design and construction, and survey locations are found in Mortimore (1988).

The locations of the wells are shown in Exhibit F.1a and F.1b. As can be seen from the illustration, many of the wells were placed as compliance boundary wells to intersect possible plumes of contaminants. Locations of the new water quality monitoring wells were based on: 1) siting wells upgradient of the site to monitor

EXHIBIT F.1a and F.1b

**RCRA Well Locations
(See Pockets, End of Document)**

Drawing Numbers:

06-SK-12

06-SK-13

background water quality (Wells 846, 831, 832, 855, 856, 857, and 858), 2) siting wells downgradient from the site to monitor the quality of water being discharged to White Oak Lake (Wells 844, 843, 842, 841, 840, 838, 839, 859, 860, 834, 833, 835, 836, 837, and 945), and 3) siting wells downgradient of individual trench and auger hole areas (Wells 847, 845, 848, 849, 850, 851, 852, 853, and 854). The first samples were collected from SWSA 6 wells in the second quarter of CY 1988 by the ORNL Department of Environmental Monitoring and Compliance (EMC); thereafter, they will be sampled quarterly. Results from the first round of sampling will be available soon and will be used during the RFI.

Following sampling, the water quality at SWSA 6 will be assessed to determine:

- o Whether hazardous waste or hazardous waste constituents have entered the groundwater
- o The rate and extent of migration of hazardous waste or hazardous waste constituents in the groundwater
- o The concentrations of hazardous waste or hazardous waste constituents in the groundwater

F.3 AQUIFER IDENTIFICATION

F.3.a Regional and Site Geologic Setting

The geology of SWSA 6 is one of interbedded limestones and carbonate shales. These rocks are moderately dipping at the surface and exhibit many small-scale structural features such as folds, fractures, and joint sets. Also, the rocks have weathered to varying depths with the transition from soil/regolith to rock being gradational. As a result of this weathering characteristic, the soil or regolith has kept many of the structural features of the parent rock. Past work at the site indicates that the groundwater flow system may consist of two regimes--the near surface/regolith flow and the deeper bedrock flow.

Melton Valley, in which SWSA 6 is located, is geologically within the Copper Creek thrust block and is underlain by strata of the Middle to Late Cambrian Conasauga Group (Exhibit F.2). The Conasauga Group was deposited as part of a major marine transgression over a subsiding carbonate-rimmed tidal flat at what was then the eastern margin of the North American continent. In Melton Valley, the Conasauga Group is approximately 1850 ft thick and is lithologically very heterogeneous, consisting of alternating siltstones, silty limestones, calcareous shales, and mudstones. In the Oak Ridge vicinity, the Conasauga Group consists of six formations (Haase and Vaughan, 1981), which are, in ascending order: Pumpkin Valley Shale, Rutledge Limestone, Rogersville Shale, Maryville Limestone, Nolichucky Shale, and Maynardville Limestone (Exhibit F.3). SWSA 6 is thought to be underlain by the Maryville Limestone, which is typically composed of interbedded limestones, dark gray shales, and mudstones (Haase and Vaughan, 1981). Structural features of the Conasauga group are related to fault motion along the Copper Creek Fault, a regionally significant, low-angle thrust fault striking N50° E to N60° E and dipping to the southeast (Exhibit F.4). Thrust fault motion has developed much internal deformation throughout the Conasauga Group. Typical features observed are numerous secondary low-amplitude isoclinal folds, secondary bedding plane thrust faults, high-angle reverse faults, and joint sets (Sledz and Huff, 1981).

Lomenick and Wyrick (1965) briefly described the geology of SWSA 6 before the site was used for waste disposal. The Conasauga formation at the site consists of gray, green, and maroon-colored calcareous shales interbedded with gray-blue silty limestones. A few thin and relatively pure limestone lenses are present throughout the area and weather to thin seams of red to yellow clay. The shales usually weather to dull olive or brown color, while the silty limestone members weather to porous brown siltstone blocks. Both the weathered siltstones and shales have well developed joints that are open near the surface and are frequently stained reddish-brown to black. Weathering persists generally to depths of 5 ft or less in areas of low topography and to as much as 30 to 40 ft on the

SOURCE: Dreier et al. (1987).

EXHIBIT F.2 GENERALIZED GEOLOGIC MAP OF THE ORNL STUDY AREA

EXHIBIT F.3
STRATIGRAPHIC COLUMN FOR GEOLOGIC FORMATIONS
ON THE BASE OF THE COPPER CREEK THRUST SHEET

EXHIBIT F.4
GENERALIZED GEOLOGIC CROSS SECTION OF MELTON VALLEY

crests of the low hills (ORNL, 1986). Small faults and sharp folds are common throughout the area. Also the rocks have weathered to varying depths with the transition from soil/regolith to bedrock being gradational. As a result of this weathering feature, the soil/regolith layer has retained many of the structural features of the parent rock.

F.3.b Regional and Site Groundwater Setting

Previous groundwater investigations in SWSA 6 have been restricted to limited types of information, such as groundwater elevation, or to detailed investigations in limited areas, such as the ETF. Observations at previously used SWSAs sited over Conasauga Group bedrock suggest that the dominant pathway for transport of waste constituents in SWSA 6 is subsurface flow to surface streams (Cerling and Spalding, 1981). Although wastes were generally buried in trenches above the maximum permanent water table, observations indicate that, following storms, water is able to enter trenches and occur in a perched condition (above the permanent water table) for extended periods.

The near surface groundwater flow at SWSA 6 occurs through the overburden soil (regolith) and in the upper portions of the bedrock. Available data indicate that the shallow water table within the unconsolidated materials mimics the land surface. This is normal for this type of geological setting, with the shallow groundwater flowing from topographic highs to topographic lows. Groundwater flowing in the regolith and bedrock zones appears, from potentiometric data, to discharge into the White Oak Creek (WOC) drainage system.

Additional data are being developed by conducting shallow constant head tracer tests at SWSA 6 (Dreier, 1987). Preliminary reports indicate the presence of a strongly asymmetric tracer plume with preferred lateral flow direction different from that predicted by the gradient at the water table. A comparison of test results with fracture orientation suggests flow direction may be influenced by

the intersection of bedding-strike-parallel extension fractures with other fracture sets. Although the original bedrock material was impermeable, post-depositional folding and weathering have created a secondary fracture system which allows water movement through the bedrock and weathered unconsolidated zone (weathered bedrock). The unconsolidated zone ranges in depths from about 4 ft in low topographic areas to as much as 40 ft in high topographic regions. The fracture system seems to extend below the unconsolidated zone although it may decrease with depth.

Tests suggest that the water table aquifer may extend to depths of 200 ft or more below the ground surface (Davis et al., 1984). More recent data from a hydrostatic head monitoring well further suggest that the uppermost aquifer extends well into bedrock (Toran and Solomon, 1987). However, modeling analysis (Tucci, 1986) indicates that the deeper system, although hydrologically connected, may be essentially decoupled from the shallow system. Tucci estimated that nearly all groundwater flow is within the regolith with less than 3 percent of the flow occurring between the regolith and bedrock and less than 1 percent of the total groundwater flow discharging to the Clinch River through bedrock. Thus, the hydrologic role of bedrock is uncertain at this point. The modeling effort described by Tucci (1986) represents one limiting case in which deep recharge is assumed to be minimal.

Hydraulic conductivities for the unconsolidated zone of SWSA 6, based on slug tests, vary from less than 0.1 ft/day to 1.0 ft/day. The anisotropy is thought to range between 1:1 to 0.333:1 (strike normal/strike parallel) and is most likely a result of a preferred fracture orientation. It is thought that the anisotropy may vary with depth due to the changes in the fracture system; however, at this time, no data have been obtained to determine any vertical variation. The bedrock hydraulic conductivities are approximately an order of magnitude less than those of the unconsolidated zone. Currently, a series of well nests are being tested which will provide better information on the vertical variation of hydraulic conductivities (Davis et al., 1987).

Despite the studies that have been conducted at SWSA 6, there are not sufficient data to characterize the groundwater system of the site. Complex geologic structures and scarcity of characterization data make identification and accurate definition of the aquifer system difficult.

Further groundwater studies are presently being conducted. Additional sets of hydrostatic head wells are being installed within and around the SWSA 6 site. Moreover, the newly installed groundwater quality monitoring wells underwent their first round of sampling in the second quarter of CY 1988. The preliminary data from these installations will be available in the future and will be used during the RFI, closure, and post-closure activities.

During the RFI, borings will be collected in an attempt to identify the uppermost aquifer and any hydraulically interconnected underlying aquifers. This should determine likely subsurface flow paths for hazardous constituents that may leave SWSA 6. The hydrogeologic properties of the aquifers will be assessed, and the supporting data used in this assessment will be provided. A written report on the hydrogeologic characteristics of SWSA 6 will be submitted by a qualified hydrogeologist. This report, which will be submitted as an attachment to the RFI Report, will contain the drilling logs of on-site borings and wells in addition to a survey of available relevant literature. Site-specific data will include:

- o An analysis of topographic or geomorphic features that may influence the groundwater flow system
- o A classification and description of the hydrogeologic properties (e.g., hydraulic conductivity, porosity, texture, thickness) of all the hydrogeologic units found at the site
- o Isopach and structural contour maps and/or geologic cross sections placed on a topographic map to show the extent of the hydrologic units contained in the uppermost aquifer and any intervening aquitards or other units
- o A description of water level or fluid pressure monitoring including water level contour maps or vertical sections, well or piezometer hydrographs, and an interpretation of the

flow system, including the vertical and horizontal components of flow.

- o A description of the field methods used in the study and a summary of which data were collected by each method

F.4 CONTAMINANT PLUME DESCRIPTION

Information on the identity or quantity of radionuclides emplaced in SWSA 6 is available from the historic operational log but is limited. In addition to radionuclides, organic and metal contaminants are known to be present in SWSA 6. Waste containers varied from none to concrete boxes, glass bottles, or steel containers; again, historic documentation is not precise. The limited information available makes prediction of contaminant release rates problematic, if not impossible, from the existing inventory (Davis and Solomon, 1987). As would be expected, because SWSA 6 is a radioactive waste disposal site, a number of radionuclides was present in trench leachate (Solomon et al., 1987). Tritium was ubiquitous in SWSA 6 samples with concentrations as high as $340,000 \pm 100$ Bq/L. The EPA proposed drinking water standard for tritium is 3×10^3 Bq/L (51 FR 34836 ff). Low concentrations of cesium-137 were detected in a few trench leachate samples.

The tritium, cobalt-60, and strontium-90 concentrations in each trench leachate and groundwater sample were compared. No correlations were observed; i.e., one trench leachate might be high in tritium and low in strontium-90, while another leachate might have the reverse relationship. This result may be expected, considering the heterogeneous nature of the contaminants, wastes, and waste containerization in the trenches. This finding, however, suggests that, during the RFI of SWSA 6, examination of the groundwater should include a complete radiochemical analysis rather than attempting to rely on monitoring of indicator radionuclides (Davis et al., 1987).

During limited investigations of trench leachate and groundwater, several organics were present at concentrations of approximately

1 mg/L. Elevated concentrations of priority pollutants were found both in trench leachate and groundwater samples with benzene, naphthalene, tetrachloroethene, and toluene being present in multiple locations.

The presence of organic contaminants in SWSA 6 has several implications for groundwater monitoring plans. Based on the historic operational log, organic compounds have apparently been placed in both trenches and auger holes. Beta spectroscopy scintillation fluids and de-greasing compounds may represent the principle sources of organics present in trenches. Xylene and toluene are typical components of scintillation fluids, and these compounds have been observed in various water samples. Chlorohydrocarbons are frequently used in metal cleaning steps and have also been observed. Characterization information available for SWSA 6 can only be used as indicator data. Previous investigations have been too limited in scope, areal extent, and sampling frequency to properly characterize SWSA 6 for corrective measures or final closure. Too little is understood about conditions at the site to evaluate the risk to human health and the environment. Furthermore, existing characterization data cannot define the extent of the groundwater contamination.

During the RFI, detailed studies will focus on defining the extent of groundwater contamination, delineating any plumes that may exist, and determining the maximum concentration levels of the waste constituents.

During the RFI, the following information will be provided:

- o Details of the design and construction of any additional monitoring wells that may be required
- o Copies of the water analysis results for each well including groundwater surface elevation measurement and notifications of any significant change in water analysis parameters
- o A copy of the groundwater sampling and analysis plan that includes the procedure used and the protocols followed for:

- Sample collection
 - Sample preservation and shipment
 - Analytical procedures
 - Chain of custody control
- o Calculations of the initial background arithmetic mean and variance for each indicator parameter based on replicate measurements from upgradient wells during the first year
 - o A description of the statistical procedures used in processing the data submitted and results of statistical comparisons between upgradient and downgradient well sampling results and the first year background value for each indicator parameter
 - o If necessary, based on statistical comparison results, the specific plan for a groundwater quality assessment program in addition to the results of implementing such a plan. Specific indicator parameters will be determined during the RFI, and results of the groundwater quality assessment program will include:
 - Whether hazardous waste or hazardous waste constituents have entered the groundwater
 - The rate and extent of migration of hazardous waste or hazardous waste constituents in the groundwater
 - The concentrations of hazardous waste or hazardous waste constituents in the groundwater
 - o Results of the evaluations of annual elevation changes in groundwater and descriptions of the response to those evaluations

F.5 DETECTION MONITORING PROGRAM

Limited data from groundwater and trench leachate analyses indicate that hazardous waste constituents may be migrating. However, results from the first round of sampling of the perimeter monitoring wells are not yet available, and there is no information to confirm that contaminants are leaving SWSA 6.

F.5.a Indicator Parameters, Waste Constituents, Reaction Products to be Monitored

During the RFI, a list of indicator parameters, waste constituents, and reaction products will be determined that can provide reliable

indication of the presence of hazardous constituents in the groundwater.

F.5.b Groundwater Monitoring Program

SWSA 6 now has a newly-installed groundwater quality monitoring well network. Details of the well number, location, depth, and construction are provided in Mortimore (1988). These wells underwent the first round of sampling in the second quarter of CY 1988 by the ORNL EMC Department. Thereafter, wells will be sampled quarterly.

After results from sufficient sampling rounds are available, there will be an evaluation of the groundwater quality monitoring well network. If the present network is deemed insufficient or inappropriate, additional locations, parameters, or sampling methods will be provided. If other wells are deemed necessary, the installation specifications of those wells will conform with the current guidelines specified in the EPA TEGD (EPA, 1986).

F.5.c Background Values

Prior to the use of SWSA 6 for disposal, no sampling or analyses were conducted to provide background data for the groundwater quality at the site. Background wells were installed in the ETF prior to its use to provide some relevant background data. Several of the newly installed groundwater wells (notably Wells 846, 831, 832, 855, 856, 857, and 858) were located to provide some further background quality values. The ORNL EMC Department recently sampled these wells for the first time. When analyses of samples are available, the concentrations and coefficients of variation for each proposed monitoring parameter or constituent will be reported.

F.5.d Sampling, Analysis, and Statistical Procedures

Based on patterns of water in trenches, groundwater flow may constitute a significant pathway for migration of contaminants from

SWSA 6 to potential receptors off-site. ORNL has conducted preliminary investigations of groundwater flow and quality of SWSA 6 and has identified that the flow regime is complex and that there may be contaminants in the groundwater. An investigation of SWSA 6 hydrogeology will be conducted during the RFI to further define groundwater flow and quality. The general objectives of the RFI groundwater program are:

- o To characterize the movement of groundwater through and away from SWSA 6
- o To characterize groundwater quality in the vicinity of SWSA 6
- o To determine interaction between surface water (e.g., in seeps and streams) and groundwater

Samples will be collected at the site to investigate the types and concentrations of contaminants currently present in the groundwater. Water quality data will be used to assess the potential for migration of contaminants from SWSA 6 sources to potential receptors based on flow directions and rates, groundwater geochemistry, identified concentrations of contaminants, and mobility and toxicity of identified contaminants.

F.5.e Compliance Monitoring Program

If the presence of hazardous constituents is detected in the groundwater at the point of compliance, the following information will be submitted by the ORNL EMC Department:

- o Waste Description
 - Results of any direct sampling of the waste
 - A list of constituents reasonably expected to be in or derived from the waste
 - Identification of the dominant constituents found to be present and their relative abundance
- o Characterization of Contaminated Groundwater
- o Hazardous Constituents to be Monitored

- o Concentration Limits
- o Groundwater Monitoring System
- o Background Values
- o Sampling, Analyses, and Statistical Procedures

F.5.f Corrective Actions Program

If hazardous constituents that exceed the established alternate concentration limits (ACLs) are measured in the groundwater at the compliance boundary, ORNL will submit sufficient information, supporting data, and analyses to establish a corrective action program that meets the requirements of 40 CFR 264.100. The schedule for a risk-based demonstration of the ACLs will be established coincident with the latter portions of the RFI. The following information will be provided:

- o Characterization of Contaminated Groundwater
- o Concentration Limits
- o Corrective Action Plan
- o Groundwater Monitoring Program
- o Background Values
- o Sampling, Analysis, and Statistical Procedures

G. POST-CLOSURE ACTIVITIES

G.1 POST-CLOSURE PLAN

G.1.a Inspection Plan

Selection of technologies for final closure and corrective actions for SWSA 6 will be made during the ROD process. During design, a Post-Closure Inspection Plan will be developed and submitted to the regulatory agencies as a modification to the permit.

A plan for inspection of the ICM during the closure period is presented in general in Section E.5.a and will be discussed in detail in the Post-Closure Surveillance and Maintenance Plan to be submitted by October 1, 1988.

G.1.b Monitoring Plan

A network of groundwater quality monitoring wells has been installed at SWSA 6 as described in Section F, "Groundwater Monitoring." A Sampling and Analysis Plan for this well network has been prepared by the ORNL EMC Department and submitted to the regulatory agencies.

Selection of technologies for final closure and corrective actions will be made during the ROD process. Based on site information developed during the RFI and on the combination and arrangement of technologies selected, the Monitoring Plan (Sampling and Analysis Plan) will be revised and submitted to the regulatory agencies as a modification to the permit.

G.1.c Maintenance Plan

Selection of technologies for final closure and corrective actions for SWSA 6 will be made during the ROD process. During design, a Post-Closure Maintenance Plan will be developed and submitted to the regulatory agencies as a modification to the permit.

G.2 NOTICE TO LOCAL LAND AUTHORITY

Registered land surveyors employed by, or under contract to, ORNL will prepare a survey plat within 90 days after completion of the ICM indicating the location and dimensions of the capped disposal areas with respect to permanently surveyed benchmarks. ORNL will also provide an estimate of the type, location, and quantity of hazardous mixed wastes to be included as a part of this plat. This information and survey will be submitted to the local land use authority (for recording onto the deed), the EPA Region IV Administrator, and the Commissioner of the TDHE.

G.3 NOTICE IN DEED TO PROPERTY

In the event that the land on which ORNL and the disposal sites are located is released from Federal control, a notation on the deed to the facility property will be recorded that notifies any potential buyer that: 1) the land has been used to manage hazardous wastes, 2) use of the land is restricted to activities that will not disturb the integrity of the final cover or the monitoring system, and 3) a survey plat (as identified in Section H.3) has been submitted to the local zoning authority, the EPA Region IV Administrator, and the Commissioner of the TDHE.

G.4 CLOSURE COST ESTIMATE

Not applicable to Federal facilities.

G.5 FINANCIAL ASSURANCE MECHANISM FOR CLOSURE

Not applicable to Federal facilities.

G.6 POST-CLOSURE COST ESTIMATE

Not applicable to Federal facilities.

G.7 FINANCIAL ASSURANCE MECHANISM FOR POST-CLOSURE

Not applicable to Federal facilities.

G.8 LIABILITY REQUIREMENTS

Not applicable to Federal facilities.

G.9 STATE FINANCIAL MECHANISM

Not applicable to Federal facilities.

H. CERTIFICATION [40 CFR 270.11(a) and (d)]

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision, in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations.

Date:

8/19/88

Signature:

Joseph A. Lenhard
J. A. Lenhard, Assistant Manager
for Energy Research and Development
Department of Energy
Oak Ridge Operations

REFERENCES

- Boegly, W. J., et al. 1985. Characterization Plan for Solid Waste Storage Area 6. Environmental Sciences Division Publication No. 2638, ORNL/TM-9877. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Cerling, T. E., and B. P. Spalding. 1981. Areal Distribution of ^{60}Co , ^{137}Cs , and ^{90}Sr in Streambed Gravels of White Oak Creek Watershed, Oak Ridge, Tennessee. Environmental Sciences Division Publication No. 1488, ORNL/TM-7318. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Davis, E. C., and R. G. Stansfield. 1984. Design and Construction of a French Drain for Groundwater Diversion in Solid Waste Storage Area Six at the Oak Ridge National Laboratory. ORNL/TM-9014. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Davis, E. C., et al. 1984. Site Characterization Techniques Used at a Low-Level Waste Shallow Land Burial Field Demonstration Facility. ORNL/TM-1946. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Davis, E. C., et al. 1987. Summary of Environmental Characterization Activities at the Oak Ridge National Laboratory Solid Waste Storage Area Six FY 1986 Through 1987. ORNL/RAP/LTR-87/68. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Davis, E. C., and D. K. Solomon. 1987. A Summary of the ORNL SWSA-6 Waste Inventory: 1972 through 1986. ORNL/RAP/LTR-87/6. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Dreier, R. B. 1987. "Geology" in Davis et al.: Summary of Environmental Characterization Activities at the Oak Ridge National Laboratory Solid Waste Storage Area Six FY 1986 Through 1987. ORNL/RAP/LTR-87/68. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Dreier, R. B., et al. 1987. Summary of Geologic Data in the Vicinity of the Hydrofracture Facilities. ORNL/RAP/LTR-87/26. Oak Ridge, Tennessee.
- Gaddis, R. May 1988. Personal Communication to B. Skelton, BNI Team. Subject: "Location of TRU Cask in WAG 6."
- Haase, C. S., and N. D. Vaughan. 1981. "Stratigraphy and Lithology of the Conasauga Group in the Vicinity of Oak Ridge, Tennessee." Geological Society of America Abstracts with Programs, Vol. 13.
- Hyde, L. D. 1987. Water Quality Well Installation at ORNL. ORNL/RAP/LTR-87/10. Oak Ridge National Laboratory, Oak Ridge, Tennessee.

- International Technology Corporation. 1986. Draft Closure Plan for Solid Waste Storage Area (SWSA) 6. ORNL/Sub-86-72127/1. Oak Ridge, Tennessee.
- Ledford, L. K. January 27, 1988. Correspondence to J. A. Lenhard. Subject: "Notice of Deficiency, Closure Plan for SWSA 6, Oak Ridge National Laboratory."
- Lomenick, T. F., and H. J. Wyrick. 1965. Geohydrological Evaluation of Solid Waste Storage Area 6. ORNL/TM-1327. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Mortimore, J. 1988. Groundwater Quality Monitoring Well Installation - WAG 6. ORNL/RAP-44. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- National Research Council: 1985. The Management of Radioactive Waste at the Oak Ridge National Laboratory: A Technical Review. DOE/DP/48010/T-1. Washington, D.C.
- Oak Ridge National Laboratory. 1986. Draft Remedial Investigation Plan for Solid Waste Storage Area Six. ORNL/RAP-2. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Oak Ridge National Laboratory. 1987. Environmental Protection Manual. Environmental and Occupational Safety Division, Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Shoun, R. R. 1987. Environmental Data Package for ORNL Waste Area Grouping 5 (WAG 5), Solid Waste Storage Area 5 (SWSA 5). ORNL/RAP-19. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Sledz, J. J., and D. D. Huff. 1981. Computer Model for Determining Fracture Porosity and Permeability in the Conasauga Group. ORNL/TM-7695. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Solomon, D. K., R. C. Haase, T. V. Dinsmore, and A. D. Kelmars. 1987. Sampling and Analyses of SWSA-6 Trench Leachates and Groundwaters: III - Summary of FY 1986 and FY 1987 Activities. ORNL/RAP/LTR-87/37. Oak Ridge National Laboratory, Oak Ridge, Tennessee.
- Spalding, B. P. 1986. "Burial Trench Dynamic Compaction Demonstration at a Humid Site." Proceedings of the Seventh Annual Participants Information Meeting, DOE Low-Level Waste Management Program. Conf-8509121. EG&G Idaho, Inc.
- Toran, L., and D. K. Solomon. 1987. Hydrology and Geochemistry of the Hydraulic Head Monitoring Stations (Cluster Wells): Preliminary Interpretations. ORNL/RAP/LTR-87-76. Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Tucci, P. 1986. Groundwater Flow in Melton Valley, Oak Ridge Reservation, Roane County, Tennessee - Preliminary Model Analysis. WRI 85-4221. U.S. Geological Survey, Nashville, Tennessee.

U.S. Environmental Protection Agency. 1986. RCRA Groundwater Monitoring Technical Enforcement Guidance Document. Office of Solid Waste and Emergency Response, Washington, D.C.

U.S. Environmental Protection Agency. 1988. Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA. 68-01-7090. Office of Emergency and Remedial Response, Washington, D. C.

Webster, D. A. 1976. A Review of Hydrologic and Geologic Conditions Related to the Radioactive Solid-Waste Burial Grounds at Oak Ridge National Laboratory, Oak Ridge, Tennessee. Open-File Report 76-727. U.S. Geological Survey, Washington, D.C.

H

E 23,250

N 16,750

G

Δ C-02

● 858
● 857

Δ 3-01

N 16,500

830

F

17 18 19 20 21 22

3"
8

0 1 2 3 4 5 6 7 8 9 10 11 12 13

MATCH LINE - SEE SWSA NO. 6 (NORTH) SK

1" / 2

0

1

2

3

4

5

6

7

8

9

10

3" / 4

1 NO 06-SK-12

E 24,500

4 5 6

SIZE E

E 25,000

I

G

E

D

N 16,250

N 16,000

859

860

TENN.

STATE

770

27

△ CX 14

1MJO2

$$TVA \quad \overline{3T} \quad \overline{KV}A$$

473

484

468

458

780

POÁDS

A

B

C

WHITE OAK

OAK LAKE

REFERENCE DRAWINGS

TRENCH AND AUGER HOLE LOCATIONS (NORTH)
 TRENCH AND AUGER HOLE LOCATIONS (SOUTH)
 AUGER HOLE LOCATION INSETS (C,D,E, & H)
 AUGER HOLE LOCATION INSETS (A,B,F, & G)
 100-YEAR FLOODPLAIN
 GROUNDWATER QUALITY MONITORING

TAKEN FROM

6-SK-07
6-SK-08
6-SK-09
6-SK-10
6-SK-11
6-SK-12

N 17,500

E

N 17,250

D

FACILITY

WELLS

● 648

PIEZOMETERS

○ 831

WATER QUALITY
MONITORING WELLS

E

D

ROAD

SERVICE

37

800

750

750

650

645

649

127
126
125
124
123
122
121
120
119
118
117
116
115
114
113
112
111
110
109
108
107
106
105
104
103
102
101
100
99
98
97
96
95
94
93
92
91
90
89
88
87
86
85
84
83
82
81
80
79
78
77
76
75
74
73
72
71
70
69
68
67
66
65
64
63
62
61
60
59
58
57
56
55
54
53
52
51
50
49
48
47
46
45
44
43
42
41
40
39
38
37
36
35
34
33
32
31
30
29
28
27
26
25
24
23
22
21
20
19
18
17
16
15
14
13
12
11
10
9
8
7
6
5
4
3
2
1
0

17288

A

B

E 23,500

854

E 23,750

553

MATCH LINE - SEE SWSA NO. 6 (SOUTH) SHE

REFERENCE

TRENCH AND AUGER HOLE LOCA
 TRENCH AND AUGER HOLE LOCA
 AUGER HOLE LOCATION INSETS
 AUGER HOLE LOCATION INSETS
 100-YEAR FLOODPLAIN
 GROUNDWATER QUALITY MONITC

FORMATION SHOWN HAS BEEN TAKEN FROM
 TA ENERGY SYSTEMS DRAWING NO. C3E 21205 A035

△		
△		
△		
△		
△	4/22/88	ISSUED FOR L
NO.	DATE	REVISIONS
BECHTEL N OAK RIDGE		
OAK RIDGE NAT REMEDIAL IN FEASIBIL		
SWSA NO. GROUNDWATER QUALITY M.		
	JOB NO.	
	19118	

RENCE DRAWINGS

OLE LOCATIONS (NORTH)	06-SK-07
OLE LOCATIONS (SOUTH)	06-SK-08
IN INSETS (C,D,E, & H)	06-SK-09
IN INSETS (A,B,F, & G)	06-SK-10
IN	06-SK-11
Y MONITORING WELL LOCATIONS (SOUTH)	06-SK-13

B

A

△								
△								
△								
△								
△								
△	4/12/88	ISSUED FOR USE	BY	CHK	APPROVED			
NO.	DATE	REVISIONS	BY	CHK	APPROVED			
BECHTEL NATIONAL INC. OAK RIDGE, TENNESSEE								
OAK RIDGE NATIONAL LABORATORY REMEDIAL INVESTIGATION/ FEASIBILITY STUDY								
SWSA NO. 6 (NORTH) GROUNDWATER QUALITY MONITORING WELL LOCATIONS								
	JOB NO.	SKETCH NO.		REV.				
	19118	06-SK-12		A				

0 1 2 3 4 5 6 7 8 9 10 12 14 16 18 20 22 24 26 28 30 32

N18,000

N17,750

N17,500

E23, 250

E23, 500

E23, 750

E24, 000

850

800

34 35 36 38 40 42 44 46
4 3 2 1 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17

18 19 20 21 22 8 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14

NOTES

1. BACKGROUND INFORMAT
TAKEN FROM A MAP FL
CONTINENTAL AERIAL
TN.

SIZE E

NOTES

1. BACKGROUND INFORMATION SHOWN HAS BEEN TAKEN FROM A MAP FURNISHED BY CONTINENTAL AERIAL SURVEYS KNOXVILLE, TN.

H

G

N17,250

N17,000

N16,750

N16,500

N16,250

800+

LEGEND

ROAD

LAKE BORDER

ORNL GRID

100 YR. 24 HR. FLOOD ELEV.
(754 FT.)

REFERENCE DRAWINGS

TRENCH AND AUGER HOLE LOCATIONS
(NORTH)

06-SK-07

E

D

N16,000

N15,750

WHITE OAK LAKE

GROUNDWATER
WELL LOCATION
GROUNDWATER
WELL LOCATION

△		
△		
△		
△		
△		
△	4/22/00	

NO.	DATE
-----	------

SCALE 1" = 100'

BE

OAK RIDGE
RESEARCH

GRA-123,31 FLOOD DGN

GROUNDWATER QUALITY MONITORING
WELL LOCATIONS (NORTH)

06-SK-12

GROUNDWATER QUALITY MONITORING
WELL LOCATIONS (SOUTH)

06-SK-13

0 100 200

△								
△								
△								
△								
△	4/22/00	ISSUED FOR USE			X.N.	C.K.	J.D.	
NO.	DATE	REVISIONS			BY	CH'K	APPROVED	

SCALE 1" = 100'

BECHTEL NATIONAL INC.

OAK RIDGE, TENNESSEE

OAK RIDGE NATIONAL LABORATORY
REMEDIAL INVESTIGATION/
FEASIBILITY STUDY

SWSA NO. 6
100-YEAR FLOODPLAIN

JOB NO.

DRAWING NO.

REV.

19118

06-SK-11

A

COO
S

T521

T522

T517

SCALE 1" = 3'

COO03 DETAIL

T513

T510

T519

T509

T512

T514

T511

G

H

SCALING RULES

CO02 DETAIL
SCALE 1" = 3'

CO05 DETAIL
SCALE 1" = 3'

CO04 DETAIL

DETAIL

SCALE 1" = 3'

3 4 5 6

SIZE E

H

C511

C512

+

C556

C557

C513

C558

C514

C559

G

165

+

F

E

D

N17,250

N17,200

B

C505

C538

C506

INSET A

SCALE 1" = 10'

N16,950

E 24,550

204

202

194

188

149

E 24, 600

INSET B

SCALE 1"=10'

C

T519
T521 T520
T525 T524
T527
T526 T528
T529 T530

△ C12L

SS-1
△

E25,000

B

A

77501

INSET F
SCALE 1"=10'

BACKGROUND INFORMATION SHOWN HAS BEEN TAKEN FROM

INSET G

SCALE 1"=10'

REFERENCE DRAWINGS

TRENCH AND AUGER HOLE LOCATIONS (NORTH)
 TRENCH AND AUGER HOLE LOCATIONS (SOUTH)
 AUGER HOLE LOCATION INSETS (C,D,E, & H)
 100-YEAR FLOODPLAIN
 GROUNDWATER QUALITY MONITORING WELL LOCATIONS (NORTH)
 GROUNDWATER QUALITY MONITORING WELL LOCATIONS (SOUTH)

06-SK-07
 06-SK-08
 06-SK-09
 06-SK-11
 06-SK-12
 06-SK-13

△									
△									
△									
B	2/4/88	REVISED TO INDICATE RCRA - REGULATED AREAS	1 M.	JT'	CA	PA			
A	4/22/88	ISSUED FOR USE	1 M.	JT'	CA	PA			
NO.	DATE	REVISIONS	BY	CH'K	APPROVED				
BECHTEL NATIONAL INC. OAK RIDGE, TENNESSEE									
OAK RIDGE NATIONAL LABORATORY REMEDIAL INVESTIGATION/ FEASIBILITY STUDY									
SWSA NO. 6 AUGER HOLE LOCATION INSETS (A,B,F, & G)									
	JOB NO.		SKETCH NO.			REV.			
	19118		06-SK-10			B			

C

B

A

SCALING RULES

8

0 1 2 3 4 5 6 7 8 9 10 12 14 16 18 20 22 24 26 28 30 32 34 36

H

G

F

N 18,000

N 17,750

1" 4 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22

LEGEND

△ C-D4

SURVEY CONTROL POINT

PAVED ROADWAYS

GRAVEL ROADWAYS

ORNL GRID

SECURITY FENCE

OVERHEAD ELECTRIC LINES

POWER POLE

WATER (BASIN OR LAKE)

MARSHY AREA AROUND WHITE
JAK LAKE

TREES

TRENCHES

WELLS

ANIMAL

LOW-LEVEL WASTE

HIGH-LEVEL WASTE

ASBESTOS

COMPACTED BUNDLE

FISSILE WASTE

MONITORING (OBSERVATION)

FISSILE WASTE

HIGH-LEVEL WASTE

SOLVENT WASTE (TRANSURANIC)

LOW LEVEL CASK

SIZE E

H

G

SERVICE ROAD

ROAD

N

GRID NORTH

MERGENCY WASTE BASIN

A-17

A-16

M337

9

8

26

42

+ N17,250

D

+ N 2,500

E

QUADREX BOX

RCRA REGULATED UNITS

HIGH LEVEL WASTE

ETF EXPERIMENTAL WASTE

SER

HIGH LEVEL WASTE

ETP EXPERIMENTAL WELL

TVA 31 KVA S

SERVICE

M318 Δ

INSET "C"

GROUNDWATER
INTERCEPTOR
TRENCH

C

N 17,000

B

SERVICE

△ C-D3

INSET

334

33

N 16,750

E 23,500

A

77302

E 24,000

265
269

M284 222

E 24,000

MATCH LINE - SEE SWSA NO. 6 (SOUTH)

REFERENCE DRAW

TRENCH AND AUGER HOLE LOCATIONS (S)
 AUGER HOLE LOCATION INSETS (C,D,E,
 AUGER HOLE LOCATION INSETS (A,B,F,
 100-YEAR FLOODPLAIN
 GROUNDWATER QUALITY MONITORING WELL
 GROUNDWATER QUALITY MONITORING WELL

N SHOWN HAS BEEN TAKEN FROM
 Y SYSTEMS DRAWING NO. C3E 21205 A033

△				
△				
△				
△				
△	8/4/5	REVISED TO INDICATE RCRA - REGULATED AREAS	ST	CH
△	4/22/88	ISSUED FOR USE	SEN	CH
NO.	DATE	REVISIONS	BY	CHK APPR

BECHTEL NATIONAL INC.

OAK RIDGE, TENNESSEE

OAK RIDGE NATIONAL LABORATORY
REMEDIAL INVESTIGATION
FEASIBILITY STUDY

SWSA NO. 6 (NORTH)
TRENCH AND AUGER HOLE LOCATION

06-SK-08
06-SK-09
06-SK-10
~~06-SK-11~~
06-SK-12
06-SK-13

IONS (NORTH)
IONS (SOUTH)

102 NO.

SKETCH NO.

19118

06-SK-07

△									
△									
△									
B	8/4/5	REVISED TO INDICATE RCRA - REGULATED AREAS		ST	CH	AP			
A	4/26/88	ISSUED FOR USE		ST	CH	AP			
NO.	DATE	REVISIONS	BY	CH'K	APPROVED				

BECHTEL NATIONAL INC.

OAK RIDGE, TENNESSEE

OAK RIDGE NATIONAL LABORATORY
REMEDIAL INVESTIGATION/
FEASIBILITY STUDY

SWSA NO. 6 (NORTH)
TRENCH AND AUGER HOLE LOCATIONS

JOB NO.

SKETCH NO.

REV.

19118

06-SK-07

B

(TH) SKETCH NIO 06-5K-07

E 24,500

OM279

GROUNDWATER
INTERCEPTOR
TRENCH

O M356

7842

E 25,000

E 24,750

F

G

H

E 25,000

BACKGROUND INFORMATION SHOWN HAS
MARTIN MARIETTA ENERGY SYSTEMS D.

REFERENCE DRAWINGS

TRENCH AND AUGER HOLE LOCATIONS (NORTH)

AUGER HOLE LOCATION INSETS (C,D,E, & H)

AUGER HOLE LOCATION INSETS (A,B,F, & G)

100-YEAR FLOODPLAIN

GROUNDWATER QUALITY MONITORING WELL LOCATIONS (NORTH)

GROUNDWATER QUALITY MONITORING WELL LOCATIONS (SOUTH)

TAKEN FROM
G NO. CSE 21205 A034

FOR LEGEND SEE SKETCH NO 06-SK 07

△					
△					
△					
B	2/4/85	REVISED TO INDICATE RCRA - REGULATED AREAS		J'	CP
A	4/24/85	ISSUED FOR USE		TL	CA/R
NO.	DATE	REVISIONS	BY	CH'K	APPROV

BECHTEL NATIONAL INC.

OAK RIDGE, TENNESSEE

**OAK RIDGE NATIONAL LABORATORY
REMEDIAL INVESTIGATION/
FEASIBILITY STUDY**

**SWSA NO. 6 (SOUTH)
TRENCH AND AUGER HOLE LOCATIONS**

JOB NO.

SKETCH NO.

19118

06-SK-08

06-SK-07
06-SK-09
06-SK-10
06-SK-11
06-SK-12
06-SK-13

(NORTH)
(SOUTH)

C

FOR LEGEND SEE SKETCH NO 06-SK 07

B

△									
△									
△									
B	8/4/88	REVISED TO INDICATE RCRA - REGULATED AREAS		J	CP	CP			
A	4/24/88	ISSUED FOR USE		TU	CP	CP			
NO.	DATE	REVISIONS	BY	CHK	APPROVED				

BECHTEL NATIONAL INC.
OAK RIDGE, TENNESSEE

OAK RIDGE NATIONAL LABORATORY
REMEDIATION INVESTIGATION/
FEASIBILITY STUDY

SWSA NO. 6 (SOUTH)
TRENCH AND AUGER HOLE LOCATIONS

A

JOB NO.	SKETCH NO.	REV.
19118	06-SK-08	B

H

G

N17,400

+

H

2 0 1 2 3 4 5 6 7 8 9 10

TRENCH
38

N 17,200

W89

W83

W144

W145

W154

W147

TRENCH
37

N 17,150

W160

W157

W155

W151

W161

W158

W148

W159

SIZE E

H

G

C 493

C 492

C 491

C 540

C 541

C 534

C 542

C 533

C 560

C 532

C 561

C 516

C 562

C 517

C 563

+

C 490

98

D

E

N17,300

E25,000

INSET E
SCALE 1"=10'

E
1" = 10'

N

TRENCH

E

D

F43
F44

F45

F14

F15

F1

F46

F16

F2

F47

F3

F48

F35

F4

F18

F5

F19

537

INSET
SCALE

INSET H

SCALE 1" = 15'

179

REFER

TRENCH AND AUGER HOLE:
TRENCH AND AUGER HOLE:
AUGER HOLE LOCATION
100-YEAR FLOODPLAIN
GROUNDWATER QUALITY :
GROUNDWATER QUALITY :

INFORMATION SHOWN HAS BEEN TAKEN FROM
ETTA ENERGY SYSTEMS DRAWING NO. C3E 21205 A038

INSET D

SCALE 1"=10'

△		
△		
△		
△B	8/1/86	REVISED TO INDICATE RCRA - REGULATED
△A	4/1/86	ISSUED FOR L
NO.	DATE	REVISIONS
<p>BECHTEL N</p> <p>OAK RIDGE</p>		
<p>OAK RIDGE NATIONAL REMEDIAL INVESTIGATION FEASIBILITY STUDY</p>		
<p>SWSA</p> <p>AUGER HOLE LOCATION</p>		
		<p>JOB NO.</p> <p>19118</p>

REFERENCE DRAWINGS

- HOLE LOCATIONS (NORTH)
- HOLE LOCATIONS (SOUTH)
- ON INSETS (A, B, F, & G)
- IN
- TY MONITORING WELL LOCATIONS (NORTH)
- TY MONITORING WELL LOCATIONS (SOUTH)

- 06-SK-07
- 06-SK-08
- 06-SK-10
- 06-SK-11
- 06-SK-12
- 06-SK-13

T D
1" = 10'

△									
△									
△									
B	8/4/8	REVISED TO INDICATE RCRA - REGULATED AREAS							
A	4/1/8	ISSUED FOR USE							
NO.	DATE	REVISIONS	BY	CHK	APPROVED				

BECHTEL NATIONAL INC.
OAK RIDGE, TENNESSEE

OAK RIDGE NATIONAL LABORATORY
REMEDIAL INVESTIGATION/
FEASIBILITY STUDY

SWSA NO. 6
AUGER HOLE LOCATION INSETS (C,D,E, & H)

JOB NO.	SKETCH NO.	REV.
19118	06-SK-09	B

END

DATE
FILMED

5 / 18 / 92