12
4-13-92 9295①

PNL-8036
UC-600

**Preliminary Evaluation of the
Gaseous Effluent Sampling
and Monitoring Systems at
the 291-Z-1 and 296-Z-3 Stacks—
Plutonium Finishing Facility**

**L. C. Schwendiman
J. A. Glissmeyer**

April 1992

**Prepared for the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830**

**Pacific Northwest Laboratory
Operated for the U.S. Department of Energy
by Battelle Memorial Institute**

PNL-8036

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor Battelle Memorial Institute, nor any of their employees, makes **any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.** Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or Battelle Memorial Institute. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PACIFIC NORTHWEST LABORATORY
operated by
BATTELLE MEMORIAL INSTITUTE
for the
UNITED STATES DEPARTMENT OF ENERGY
under Contract DE-AC06-76RLO 1830

Printed in the United States of America

Available to DOE and DOE contractors from the
Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831;
prices available from (615) 576-8401. FTS 626-8401.

Available to the public from the National Technical Information Service,
U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

PNL--8036

DE92 010757

PRELIMINARY EVALUATION OF THE GASEOUS
EFFLUENT SAMPLING AND MONITORING
SYSTEMS AT THE 291-Z-1 AND 296-Z-3
STACKS--PLUTONIUM FINISHING FACILITY

L. C. Schwendiman
J. A. Glissmeyer

Prepared
April 1976

Published
April 1992

Prepared for
the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Richland, Washington 99352

MASTER

26
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

PREFACE

This report was written in 1976 to document work conducted during 1975 and 1976. The report was written for, and distributed to, the Atlantic Richfield Hanford Company, which, at that time, was the operating contractor responsible for the facilities studied. Because of this limited distribution, the report was never formally published or made publicly available. The current Hanford operating contractor, Westinghouse Hanford Company, has requested that the report be issued as a public document.

All efforts have been made to reproduce the document in its original format while remaining within the publishing guidelines established by the Pacific Northwest Laboratory (PNL). However, the report does contain references to internal operating procedures relevant to the operating contractor at the time the work was performed, which are no longer available, having been superseded over the intervening years. The report also contains numerous references to drawings in the Rockwell Hanford Operations Engineering Files. Copies of those drawings can be obtained by calling PNL Engineering Files (509) 376-0067.

TABLE OF CONTENTS

	<u>Page</u>
I. INTRODUCTION	1
II. 291-Z-1 STACK EFFLUENT SAMPLING SYSTEM	2
Description.	2
Sample Collection System.	2
Sample Monitoring System.	4
Preliminary Evaluation of Sample Collection System.	5
Sample Aliquot Selection.	5
Sampling System Performance	9
Sampling System Operation	13
Monitoring System.	14
Sensitivity and Range	14
Alarms.	15
Emergency Power	16
Calibrations.	16
Preliminary Recommendations.	16
Sample Collection System.	16
Sample Monitoring System.	18
III. 296-Z-3 STACK EFFLUENT SAMPLING SYSTEM	19
Description.	19
Preliminary Evaluation of Sample Collection System.	22
Sample Aliquot Selection.	22
Sampling System Performance	24
Sampling System Operation	26
Preliminary Recommendations.	27
IV. CONCLUSION	28
NOMENCLATURE	29
REFERENCES	31
APPENDIX	35

PRELIMINARY EVALUATION OF THE GASEOUS EFFLUENT
SAMPLING AND MONITORING SYSTEMS AT THE 291-Z-1
AND 296-Z-3 STACKS -- PLUTONIUM FINISHING FACILITY

I. INTRODUCTION

The 291-Z-1 and 296-Z-3 stack effluent particulate sampling and monitoring systems are being evaluated for compliance with Atlantic Richfield Hanford Company's Interim Criteria for such systems (Appendix). This evaluation is part of a study by Battelle-Northwest of gaseous effluent sampling systems in ARHCO facilities. This letter report presents a preliminary evaluation of the mentioned facilities and the indicated improvements needed to meet the Interim Criteria so that conceptual design work for improved systems can be initiated. There is currently underway a detailed study at the two stacks including a series of sampling experiments, the findings of which will not be included in this report.

The gaseous effluent sampling system at the 291-Z-1 and 296-Z-3 stacks are very dissimilar and will be treated in separate sections of this report. The discussions for each sampling system will include a brief description and a preliminary evaluation of the systems. At the close of each section recommendations will be made, which will aid in the design of improved systems that will comply with the interim criteria.

II. 291-Z-1 STACK EFFLUENT SAMPLING SYSTEM

Description

The 291-Z-1 stack exhausts process enclosure and room ventilation air from the 234-5Z, 236-Z and 232-Z buildings. The total exhaust flowrate has been found to be about 270,000 cfm. This airstream is sampled continuously and the collected sample is continuously monitored for alpha-emitting radio-nuclides. The sample collection and monitoring systems will be described in further detail separately.

Sample Collection System

Figure 1 is a diagram of the existing sample collection system. The sample airstream is withdrawn from a horizontal 16-foot square duct located just upstream from the stack base and just downstream of a duct expansion and the convergence of the 291-Z fan exhaust plenums. [9,10,11]

The sample airstream is withdrawn from the effluent through three 2-inch diameter intake nozzles spaced at four-foot intervals along a vertical 4-inch pipe which serves as a manifold. Since the sample airstream flowrate is only about 2 cfm, it can be assumed that most of the sample is withdrawn through the top nozzle. The sample airstream then passes through about 35 feet of piping and plastic tubing, including several joints and bends, to a Radeco Model 440 Alpha Monitor. In the monitor the particulates pass through an orifice purge flowmeter and are collected on a 47 mm diameter membrane filter (Gelman Acropor Model AN 3000, 3 μ m pore size). The orifice purge flowmeter is calibrated bimonthly, however the calibration conditions may be somewhat different from the conditions experienced in actual use.

PIPING SUMMARY

BENDS:

- a - 3/8 in. TYGON TUBING, 270° COMPOUND BEND, 4 IN. RADIUS
- b, c - 1-1/2 IN. SCH. 40 PIPE, 90° BEND, @ 2-1/2 IN. RADIUS

STRAIGHT PIPES:

- d - 1-1/2 IN. SCH. 40 PIPE
- f - 4 IN. SCH. 40 PIPE

NOZZLES:

- e - 2 IN. PIPE NIPPLES

FIGURE 1
291-Z-1 CONTINUOUS STACK SAMPLER [11]

The vacuum source for the sampler is the vacuum manifold that serves many of the buildings and air samplers at Z-Plant. The vacuum in the manifold is supplied by two pumps, Ingersol Rand type ES-1. A third pump is on automatic standby in the event of loss of vacuum. One of the three pumps is supplied by the emergency electrical power system, however a single pump does not supply sufficient vacuum to maintain the desired sample flowrate.

Sample Monitoring System

The collected sample of radioactive particles is continuously monitored by a 400 mm² diffused junction detector in the RADeCO Model 440 Alpha Monitor. The baseline for the detector is set at 5.15 MeV with a window setting of 0.5 MeV. These baseline and window settings allow a maximum counting efficiency for ²³⁹Pu while eliminating about 97% of the radon-thoron background.^[1] The monitor includes a count rate meter with the following scales: 0-50, 0-100, 0-500, 0-1000 and 0-5000 counts per minute. The scale normally used is 0-100 cpm. Coupled to the count-rate meter is a recorder where a full-scale reading corresponds to the maximum counting rate of the range the count rate meter is set on. An audible and visual alarm mounted on the monitor housing is activated at a reading of 40% on the recorder scale. The 40% reading also activates an audible alarm in the Radiation Monitoring office in 234-5Z.

On a weekly basis Radiation Monitoring conducts a source check of the monitor. A 500 dpm source is used to determine if the ²³⁹Pu counting efficiency is maintained within limits. Semiannually Radiation Monitoring performs a calibration of the monitor. An average alpha counting efficiency is determined by using 100 dpm, 200 dpm, 500 dpm, 1000 dpm and greater than 1000 dpm sources. The average efficiency is about

7-8%.^[2] Bimonthly checks of the count rate meter, baseline, window, gain, flowmeter and other items are performed by the Instrument Maintenance subsection in the 234-5Z building.

Preliminary Evaluation of Sample Collection System

This preliminary evaluation of the 291-Z-1 stack sample collection system will address the topics of sample aliquot selection, sampling system performance and sampling system operation.

Sample Aliquot Selection

A suitable sample aliquot will be large enough so that when a release of specified concentration and duration occurs, sufficient activity is collected to allow an accurate determination of the concentration. Also the sample aliquot must be withdrawn from a location where the activity concentration is representative* of the effluent.

Aliquot Size. The factors to be taken into account when evaluating the size of the sample aliquot are the analytical techniques to be used, the radioactive particle concentration that must be measurable, the duration of that concentration and the accuracy with which the measurement must be made.

Currently each sample filter is first analyzed at the 234-5Z laboratory and then at the 222-S counting room. Since this last analysis is the one relied on for an official

*A representative sample withdrawn from the bulk gas is one in which the particulate concentration equals the average particulate concentration in the effluent airstream. Also, the size distribution of particulates in a representative sample air-stream is the same as in the total effluent. Finally, a collected particulate sample is representative when the mass, divided by the amount of sample air from which it was collected, equals the average particulate concentration of the effluent. By collected we mean separated from the sample airstream (by a filter, usually) and held for observation. Since perfectly representative samples cannot be guaranteed, the interim criteria define allowable deviation from ideally representative.

analysis it is the one which will be of concern here. The current analytical technique has been outlined in detail elsewhere^[3,4]. The counting instrument used is the Beckman Wide Beta Analyzer. Each sample filter is counted twice (with a 5-hour minimum interval between counts) so that the effect of short-lived alpha emitters can be accounted for. The duration of each count is one minute. It is assumed that the long-lived alpha emitters are ²³⁹Pu. Usual background levels are 0.1-0.2 cpm measured during five 1-minute counts.

The equation for calculating the alpha-emitter concentration is:

$$\frac{\mu\text{Ci}}{\text{cc}} = \text{long-lived net cpm} \times \frac{\text{disintegrations}}{0.296^* \text{ counts}} \times \frac{\text{minute}}{\text{sample flowrate, ft}^3} \times \frac{\text{ft}^3}{28,317 \text{ cc}} \times \frac{1}{0.7^{**}} \times \frac{1}{1440 \text{ min.}^\dagger} \times \frac{\mu\text{Ci}}{2.22 (10^6) \text{ disintegrations/min}} \quad (1).$$

This equation can be used to calculate minimum sample flowrate once the concentration level to be measured and the measurement accuracy are decided upon.

The accuracy of a single counting of a radioactive material can be estimated by calculating the confidence intervals about the measured count. The following equation is frequently used to make such an estimation:

*The counting efficiency for ²³⁹Pu is 0.296 counts per disintegration.

**The collection efficiency of 0.7 is the value generally assumed for an HV-70 filter. However, because the filter used is a membrane filter with a pore size of 3 μm the collection efficiency should be much higher than 0.7.

†Here the sampling duration is one day.

$$\text{Interval limit} = 1.96 \sqrt{\frac{\text{net cpm} + \text{background cpm}}{\text{sample counting time}} + \frac{\text{background cpm}}{\text{background counting time}}} \quad (2).$$

The necessary net count rate for an analysis accuracy of $\pm 10\%$ is 380 cpm assuming a one minute counting time (the time currently used), a background of 0.2 cpm and a confidence level of 95%.

The 24-hour average alpha-emitter particulate concentration level that must be measurable is stated in the Interim Criteria - Sampling Criterion No. 1; i.e., the ERDA Manual Chapter Appendix 0524, Annex A, Table II, limit for ^{239}Pu ^[5] (6×10^{-14} $\mu\text{Ci/cc}$). Knowing the concentration level to be measured, the concentration duration or averaging time period, the current analytical technique and the aforementioned assumptions about accuracy, the minimum required sample flowrates can then be calculated. Equation No. 1 can be simplified and rearranged to allow calculation of the minimum sample flowrate:

$$\begin{aligned} \text{Sample flowrate, cfm} &= \frac{\text{net long-lived cpm}}{\text{concentration, } \mu\text{Ci/cc}} \\ &\times 5.33 (10^{-14}) \quad (3). \end{aligned}$$

Table I lists the calculated minimum flowrate required for measuring the concentration levels stated, with the stated accuracy and with the present analytical procedure.

TABLE I
Minimum Required Flowrates

Alpha-Emitter Concentration		For Measurements at
Source	$\mu\text{Ci/cc}$	95% Confidence Level, $\pm 10\%$ Accuracy, cfm*
Table II ^[5]	6.0×10^{-14}	338
Table I ^[5]	2.0×10^{-12}	10
Class I Emergency ^{[6]†}	9.1×10^{-12}	2.2
1/2-Class I Emergency ^{[6]†}	4.5×10^{-12}	4.5

*The calculated flowrates are considered to be at the same conditions as the air in the effluent, which is nearly at standard conditions.

†A stack flowrate of 270,000 cfm was assumed.

The table shows that sample flowrate of at least 338 cfm is required if the ERDA Manual Chapter Appendix Table II concentration limit, averaged over a 24-hour period, is to be measurable with $\pm 10\%$ accuracy (95% confidence level) with the current analytical procedure. One limiting factor for the sample flowrate is the airflow capacity of the filter media. The largest filter that can be counted with the existing procedure is 4 inches in diameter. The maximum flowrate through an Acropor filter of that size is probably less than 15 cfm; therefore, it is impractical to meet the minimum requirement of 338 cfm without changing the routine analytical procedure in some way.* With the present 2 cfm flowrate an alpha

*It is worth noting that if the sample counting time is longer than 1 minute, then the number of net counts (and sample flowrate) needed for a given accuracy is reduced. For example, if the counting time is 60 minutes, with an assumed background of 0.2 cpm, then a net count of 8 cpm is required for $\pm 10\%$ accuracy, 95% confidence level. The required flowrate to accumulate the necessary activity during a 24-hour average concentration of $6 \times 10^{-14} \mu\text{Ci/cc}$ is then reduced from 338 cfm to 7.1 cfm. This lower flowrate is more within the realm of practicability.

emitter 24-hour average concentration of 1.0×10^{-11} $\mu\text{Ci/cc}$ is measureable with a $\pm 10\%$ accuracy, 95% confidence level, with the current laboratory procedure.

It must be remembered that in all these calculations of sample flowrate (or sample size) we have accounted only for the accuracy of the counting statistics and have assumed an ideal collection of the sample. Because it is unlikely that ideal samples are collected, the calculated sample flowrates are minimums.

Sampling Location. The present sampling location is likely to be inadequate to allow obtaining a particulate sample which is representative of the effluent. In a 16-foot square horizontal duct, just a few feet from the convergence of two ducts, there is likely to be vertical stratification of the particulates and inadequate mixing.

Sampling System Performance

Having evaluated the choice of the current sample aliquot the effects of extraction and particulate delivery and collection on the representativeness of the collected samples will be addressed.

Extraction. The act of withdrawing the sample airstream from the effluent can cause a bias in the amount of particulates in the sample airstream. For the 291-Z-1 stack sample probe it can be shown that the current extraction of the sample aliquot results in a positive bias of large particles in the sample airstream. The chief cause of this bias is that the probe intake nozzles are greatly oversized for the 2 cfm sample flowrate.

It is reasonable to suspect that most of the air sample is extracted through the top nozzle. In that case the velocity of the sampled air at the nozzle orifice is 91.7 fpm versus 1050 fpm for the air in the effluent. The bias in the number of sampled particulates can be estimated as shown in Table II. The table shows that for 10 μ m AED particles, twice as many will be included in the sample airstream as would be representative for the aliquot.

TABLE II

Extraction Bias of 291-Z-1
Stack Sampler Probe

<u>Particle Size, μm AED*</u>	<u>Bias in Quantity of Extracted Particles</u>
0.5	1.00
1	1.01
2	1.05
5	1.32
8	1.77
10	2.17

*The AED, or aerodynamic equivalent diameter is defined as the diameter of a hypothetical particle of unit density (water) which has the same settling velocity as a given particle. AED is the most important parameter in describing the aerodynamic behavior of particles.

Particulate Sample Delivery and Collection. Also affecting the representativeness of the collected samples is the loss of particles during delivery to the collection filter and the penetration of particles through the filter.

The penetration of particles through the collection filter is expected to be of negligible consequence. The collection efficiency of the Acropor filter for particles of most sizes should be better than 95%.

The deposition of particles on pipe walls, valves, pipe joints and fittings is expected to be a major cause of inaccuracy of the current samples. Only the deposition of particles in smooth pipes can be accounted for by calculation. Table III shows an estimate of the fractional delivery of aerosols of various sized particles through the sampling system piping.

TABLE III
Percent Fractional Delivery of Monodispersed
Aerosols Through the Sample Delivery Lines

<u>Particle</u> <u>AED,</u> <u>μm</u>	<u>Vertical</u> <u>Lines</u>	<u>Horizontal</u> <u>Lines</u>	<u>Bends</u>	<u>Total</u> <u>System</u>
0.5	100	100	99	99
1	100	99	97	96
2	100	96	90	86
5	100	75	53	40
8	100	48	20	9
10	100	32	7	3

The table shows that for a 10 μm AED particle only about 3% of those entering the sampler piping would reach the filter, most of the losses occur in the bends and long horizontal lines. Because considerable additional particle losses are expected for the flowmeter, filter holder cavities, valves and pipe fittings, the estimates of penetration are high.

Combining the estimated extraction bias and penetration values yields an estimate of particle penetration through the sampling system as shown in the following table.

TABLE IV
Combined Estimate of Aliquot Particle
Penetration to the Collection Filter

<u>Particle Size,</u> <u>μm AED</u>	<u>Fractional</u> <u>Penetration</u>
0.5	.99
1	.97
2	.90
5	.53
8	.16
10	.07

The table shows that even though extra numbers of large particles are extracted, the total of particles larger than 2 μm AED reaching the filter is only a small fraction of those extracted in the sample. This system certainly does not meet Sampling Criterion No. 2, which requires that 90% of 10 μm AED particles in the sample aliquot must be collected on the filter.

Sampling System Operation

There are many elements of the operation of the sampling system which can affect the representativeness of the collected samples. These include the calibration of the flowmeter, the continuity of operation and the lack of an optimum inventory sample.

Inventory and Monitoring Sampling. The lack of a separate inventory sample is a major deficiency of the existing sampling system. Using the monitored sample, as presently obtained, for inventory purposes is not recommended because of the considerable qualification of the accuracy of the samples.

Flowrate Measurements. Accurate information about the flowrate (sample aliquot size) is necessary in the calculations of effluent release values. The present flowmeter is calibrated bimonthly in the laboratory against a standard rotameter. The applicability of the calibration to the operating conditions should be reviewed.

Continuity of Operation. The present sampling system is operated continuously; however, the vacuum supply is not engineered to operate under the emergency conditions as specified in the Interim Criteria. Since back-up steam driven fans for the 234-5Z ventilation system operate in the event of a power failure the 291-Z-1 stack sampler must also operate during a power failure. However, only one of the three supply vacuum pumps is connected to an emergency power source, but two pumps are needed to supply sufficient vacuum.

Monitoring System

Sensitivity and Range

The monitoring system is required to detect a release at least as low as one-half of a Class I Emergency (Monitoring Criterion 1). Also the instrumentation must have sufficient range to detect a release at least as great as one-hundred times a Class II Emergency (Monitoring Criterion 10). Both Class I and Class II Emergencies are concerned with measuring a total release of 1×10^{-4} curies of plutonium during a 24-hour period.^[6] Assuming a ventilation flowrate of 270,000 cfm, a counting efficiency of 0.08 and a sample flowrate of 2 cfm the count rate detected after a hypothetical one-half Class I Emergency release is calculated as follows*:

$$\begin{aligned} \text{detected count rate} &= 1/2 \times (10^{-4}) \text{ Ci} \times 0.08 \text{ c/d} \times \\ & \quad (1/2 \times \text{Class I}) \end{aligned}$$

$$\begin{aligned} & 2/270,000 \times 2.22 (10^{12}) \text{ d/Ci min} \\ & = 66 \text{ cpm} \end{aligned}$$

Similarly, for a hypothetical release of one-hundred times the Class II Emergency the detected count rate can be calculated as follows:

$$\begin{aligned} \text{detected count rate} &= 100 \times (10^{-4}) \text{ Ci} \times 0.08 \text{ c/d} \times \\ & \quad (100 \times \text{Class II}) \end{aligned}$$

$$\begin{aligned} & 2/270,000 \times 2.22 (10^{12}) \text{ d/min-Ci} \\ & = 13,160 \text{ cpm} \end{aligned}$$

*Again we have assumed that an ideal sample is collected.

The first calculation shows that the monitor has the required sensitivity, but the second calculation shows that the monitor does not have sufficient range. (The maximum range for the monitor is 5000 cpm.) If a release equivalent to one-hundred times a Class II Emergency occurred at a constant rate during one day the monitor's range would be exceeded in about 9 hours (the alarm would sound after about 5 minutes). However, during actual releases of the above levels the detector responses will be somewhat lower than the calculated responses. How much lower will depend mostly on the particle sizes during the release.

Alarms

The monitoring criteria require that the monitoring system alarm when a release level commensurate with a Class I Emergency is detected. During ideal sampling conditions the detected count rate can be calculated as:

$$\text{detected count rate} = 10^{-4} \text{ Ci} \times 2/270,000 \times 0.08 \text{ c/d} \times \\ (\text{Class I})$$

$$2.22 (10^{12}) \text{ d/min-Ci} \\ = 132 \text{ cpm.}$$

Presently the alarm actuates at 40 cpm, or about one-third the calculated alarm point. The 40-cpm alarm level may be satisfactory because it allows a margin for nonideal sampling while drawing attention to an abnormal release.

Triggering the alarm actuates a horn and a flashing light at the monitoring station and a horn in the Radiation Monitoring office, 234-5Z building, which is continuously occupied.

Most of the alarms required in the Monitoring Criteria are lacking in the 291-Z-1 stack monitoring system. There are no fail-safe alarms for instrument malfunction, loss of vacuum or loss of primary electrical power.

Emergency Power

One major deficiency of the 291-Z-1 stack monitor is the lack of an emergency power supply. In the event of a power outage the ventilation system shuts down except for two steam-turbine fans which provide a reduced flow of ventilation air. In this case the monitoring system will not function.

Calibrations

The existing program for calibrating and checking the monitoring instrumentation satisfies most of the requirements of the Monitoring Criteria; however, the frequency of counting rate calibration is only semiannual rather than quarterly.

Preliminary Recommendations

In light of the preceding evaluation of the 291-Z-1 stack sampling and monitoring systems there are several areas for improving the systems. The following preliminary recommendations should aid in the conceptual designs for systems that will comply with the Interim Criteria.

Sample Collection System

1. Collect at least two samples of the effluent; one for monitoring and one for inventory functions as specified in Sampling Criterion No. 5.

2. The sample delivery systems for both the inventory and monitored samples must be as short and simple as possible. If possible, the inventory sample collection medium should be placed directly behind a nozzle situated in the effluent stream. The sample collection filter for the monitored sample should be as short coupled as possible to the effluent stream, if not in the stream itself. Bends, long lengths of piping, flowmeters, valves, and pipe fittings upstream of the filter holder must be avoided. The thermostatic control of delivery and collection system temperature should be part of the conceptual design to insure against condensation upstream of the filter. Each new sampling system should be validated before installation and as the necessary techniques become available.
3. Improved filter holder designs must be used which avoid particle deposition.
4. Decide on the level of accuracy desired for measurements of a 24-hour average concentration equal to the ERDA Manual Table II limit for ^{239}Pu . Commensurate with this decision the following changes will need to be considered:
 - a. Use of a larger filter size, probably 4 inches in diameter.
 - b. Increasing the sample flowrate (sample size).
 - c. Lengthening the sample counting time.
5. Choose a location for sample withdrawal either in accordance with accepted standards ^[7] or which has been experimentally proven to contain an average particulate concentration of the effluent.

6. Provide sufficient emergency vacuum supply commensurate with Sampling Criterion 7.
7. Sample flow measurement should be accomplished downstream of the collection filter with either a mass flowmeter or other properly instrumented flowmeter which will allow flow measurements accounting for actual conditions of sample gas temperature and pressure.
8. Review the accuracy of present effluent flow measurements. Develop a new method if the accuracy is not within about $\pm 10\%$, 95% confidence level.
9. Provide a loss of vacuum alarm in a continuously occupied area.
10. Provide a procedure to adjust the sampler flowrate for occasions when the ventilation system is on emergency power.

Sample Monitoring System

1. Use a monitor with a count rate range of at least 20,000 cpm.
2. Calibrate the detector counting efficiency on a quarterly basis.
3. After the improved sample collection system has been built and validated consider adjusting the alarm point to comply more closely with Monitoring Criterion No. 7.
4. Add an emergency power supply for the monitoring and alarm instrumentation.
5. Add loss of power and instrument malfunction alarms. The alarms must be signalled in a continuously

occupied area. A zero-scale alarm may be sufficient for an instrument malfunction alarm.

III. 296-Z-3 STACK EFFLUENT SAMPLING SYSTEM

Description

The filtered exhaust from the 241-Z sump vessel and vessel cell ventilation systems are vented through the 296-Z-3 stack.^[16] The effluent is expected to be contaminated with small amounts of alpha-emitting particulates (generally assumed to be ²³⁹Pu). The effluent is continuously sampled for particulates, but the sample is not continuously monitored.

The 296-Z-3 stack is 15 feet tall and 14 inches in diameter. The flowrate has been recently measured to be 2500 cfm and the effluent air temperature was 149°F (yielding a corrected flowrate of about 2200 scfm @ 70°F, atmospheric pressure). The average air velocity in the stack is then 2360 feet per minute.

The effluent sample is withdrawn through a single nozzle probe located on the stack centerline about 4-1/2 feet (4 duct diameters) above the airflow entrances to the stack^[13,16] (Figure 2). The sample airstream passes through about 14 feet of piping, six-90° bends, a flowmeter, a valve and into a Hanford design^[12] in-line filter holder (Figure 3).^[13] Particulates are collected on a 4-inch diameter asbestos fiber (Hollingsworth and Vose, HV-70). The vacuum source is a vacuum pump mounted at the sampling station. The valve is adjusted so the flowmeter reads 1.5 scfm (@ 70°F, 14.7 psia).* The sampling piping is heat traced from the stack to the instrument enclosure;^[14] however, there is no thermostatic control.

*Because there is no flowrate correction made for the actual operating conditions it will be assumed that the sample flowrate is 1.5 scfm for some of the calculations that will follow.

FIGURE 2
296-Z-3 STACK [13,15,16]

PIPING SUMMARY

BENDS:

a - 3/8 IN. SCH. 40, 8 IN. RADIUS, 90° BEND

c - 3/8 IN. SCH. 40, 90° ELBOWS

STRAIGHT PIPE:

b - 3/8 IN. SCH. 40

d - 1 IN. SCH. 40

ALL PIPE IS 304 STAINLESS STEEL

FIGURE 3

296-Z-3 (241-Z) CONTINUOUS STACK SAMPLER [14,15,16]

Preliminary Evaluation of Sample Collection System

Sample Aliquot Selection

Sample Aliquot Size. As explained earlier (pages 8-11) the suitability of the sample aliquot size, depends upon the analytical procedure employed, the 24-hour average concentration of alpha-emitting particles that must be measured, and the desired accuracy of the measurement. The analytical procedure for the 296-Z-3 stack samples is the same as already described for the 291-Z-1 stack samples (page 9).

Sampling Criterion 1 requires that a 24-hour average concentration equal to the ERDA Manual Chapter, Table II,^[5] limit for ^{239}Pu ($6 \times 10^{-14} \mu\text{Ci/cc}$) must be measurable with an unspecified appropriate accuracy. For this preliminary evaluation an accuracy of $\pm 10\%$ at the 95% confidence level will be used as an illustration. As shown earlier (page 10) this accuracy requires a net long lived counting rate of 380 cpm. Equation 3 will be used to calculate the minimum required flowrate knowing the concentrations and accuracy levels desired. Table V shows the results of such calculations for various concentration levels. Also shown in the table is the measurable 24-hour average concentrations for the present sampling flowrate.

As the table shows, the required 24-hour average concentration is not measurable at the assumed accuracies using samples collected from the existing system. However, the lowest 24-hour average concentration shown is measurable with $\pm 10\%$ accuracy, 95% confidence level, if the sample flowrate (i.e., sample size) and the counting time are increased (see footnote on Page 8).

TABLE V

Minimum* Required Flowrates for Various Alpha-Emitter
Concentrations with a Duration of 24-Hours

Alpha-Emitter Concentration		For $\pm 10\%$ Accuracy at 95% Confidence Level,
Source	$\mu\text{Ci/cc}$	cfm
Table II ¹⁸¹	6×10^{-14}	338
Table I ¹⁸¹	2×10^{-12}	16
Class I Emergency [8]	$9.7 \times 10^{-11} \dagger$	.21
1/2 - Class I Emergency	$4.8 \times 10^{-11} \dagger$	.42
With Present Flowrate	1×10^{-11}	2

*These are minimum flowrates since it has been assumed here that the collected samples are representative.

†A stack flowrate of 2500 cfm is assumed.

Sampling Location. To obtain representative samples the particulate concentration at the point of withdrawal must be representative of the average particulate concentration of the effluent; however, that may not be the case for the existing sampling system. Because the present location is only about 4-duct diameters from the transitions into the stack and only 2-duct diameters from the stack top, the velocity profile at the sampling point will be highly irregular.* The airflows from the two stack inlets will not be well mixed at the sampling location. However, because of the size of the stack a better location could not have been chosen without expending a great deal of effort to obtain concentration profiles or installing a flow straightener below the sampling location.

*A recent velocity profile at the top of the stack shows channeling of much of the airflow to one side of the opening. However, the center of the opening was within the region of average velocity.

Sampling System Performance

Extraction. As described, the air sample is withdrawn at a flowrate of 1.5 cfm through a knife-edge probe (0.493-inch diameter) from the effluent which has a flowrate of 2500 cfm (14-inch duct diameter). Assuming that the nozzle is located in a region of average velocity the air velocity approaching the nozzle is 2300 fpm while the sample velocity through nozzle is only 1100 fpm. This difference in velocities will cause a bias in the particulate sample towards extra numbers of large particles. The estimated resulting biases for particles of various sizes are shown in Table VI.

TABLE VI

Extraction Bias of 296-Z-3 Stack Sampler Probe

<u>Particle Size, μm AED</u>	<u>Bias in Quantity of Extracted Particles</u>
0.5	1.00
1	1.01
2	1.04
5	1.23
8	1.44
10	1.56

The table shows that about one and one-half times as many 10 μm AED particles will be in the sample airstream than would be representative.

Particulate Sample Delivery and Collection. As explained previously the deposition of particulates in the sampling system and the filter collection efficiency also affect the representativeness of the sample.

The collection efficiency of the collection filter in use has been found to vary from filter to filter. In stack sample calculations ARHCO assumes that the filter collection efficiency is 70%; however, a collection efficiency as high as 97% has been measured [7] in one instance for similar face velocity conditions. The fact that the collection efficiency of the filter varies over a wide range lessens the accuracy of a sample.

Calculated values of percent fractional delivery of various sizes of monodispersed aerosols are shown in Table VII.

TABLE VIII
Percent Fractional Delivery of Monodispersed
Aerosols Through Sample Delivery Lines

<u>Particle Size</u> <u>μm, AED</u>	<u>Vertical</u> <u>Lines</u>	<u>Horizontal</u> <u>Lines</u>	<u>Bends</u>	<u>Total</u> <u>System</u>
0.5	100	100	100	100
1	100	100	98	98
2	100	100	94	93
5	98	98	66	63
8	94	96	34	31
10	90	93	19	16

As the table shows the 90° bends in the sample delivery system are a major cause of particulate sample losses prior to collection. It is suspected that other parts of the sample delivery system--rotameter, valve, pipefittings and walls of the filter holder--are also major contributors to the loss of particles; however, their effect cannot be calculated.

A likely additional error in the collected sample is the lack of a proper seal around the mounted filter paper. The existing filter holder was originally designed for an 8" x 10" filter paper to be laid over a screen.^[12] However, now a piece of plastic with an approximately 3-1/2 inch diameter cutout is taped over the screen and the filter paper is laid over the cutout. As the vacuum pressure pulls the filter down into the cutout the edges of the filter wrinkle. These wrinkles may allow the passage of sample air that has bypassed the collection filter.

Because of the significant losses of sampled particulates, as discussed above, the existing sample collection system does not meet the requirements of the Sampling Criteria. Even though additional large particles are extracted and are in the sample airstream initially, much less than 90% of a representative number of 10 μ m AED particles will ever be collected.

Sampling System Operation

Flowrate Measurement. An accurate knowledge of the sample flowrate (or sample aliquot size) is important for subsequent calculations of release levels. Because the effluent temperature is 149°F, rather than the 70°F for which the rotameter is calibrated, the indicated flowrate must be corrected. However, the flowmeter is not calibrated for the actual conditions, nor is there existing instrumentation to measure the airstream temperature and pressure at the flowmeter to allow correction of the indicated flow reading.

Continuity of Operation. The existing sampling system operates continuously as long as the 241-Z sump ventilation system operates. There is, however, no loss of vacuum alarm for the system. While there is no emergency power for the vacuum pump, there is no emergency power for the sump ventilation system either. Thus, the lack of emergency power is no real problem.

Preliminary Recommendations

The following preliminary recommendations should aid in the conceptual design of a sample collection system that will comply with the Interim Criteria. It would also be worthwhile to consider whether or not a monitored sample is needed for this stack.

1. The filter holder for the inventory sample should be placed just downstream of the extraction nozzle, either in the stack or short coupled to the stack exterior. The sample extraction should be accomplished with as little bias as possible.
2. Determine if the particulate concentration at the sampling location is representative of the effluent. It may be helpful to install a flow straightener just upstream of the nozzle to more evenly distribute the flow profile and mix the effluent.
3. Decide on the level of accuracy needed for measuring a 24-hour average concentration equal to the ERDA Manual Chapter, Table II limit for ^{239}Pu . In accordance with this decision, the sample flowrate and sample counting time will probably need to be increased.
4. Sample flow measurement must be accomplished with a properly instrumented and calibrated flowmeter which will account for the actual operating conditions.
5. Review the accuracy of present effluent flow measurements and increase the frequency of measurement. If the latter is not possible, install a flow measuring device (such as an annubar or other suitable device).
6. Install a loss of vacuum alarm in a continuously occupied area.

IV. CONCLUSION

In this preliminary evaluation of the gaseous effluent sampling and monitoring systems at the 291-Z-1 and 296-Z-3 stacks it was found that the sampling and monitoring are not accomplished in accordance with the Interim Criteria. The following are some of the major problem areas for the sampling systems.

- The sample delivery lines were too complex and lengthy to allow the adequate passage of particles as large as 10 μm AED. At both stacks there are flowmeters, valves, numerous 90° bends, pipe joints, and poorly designed filter holders which offer many sites for deposition of particles.
- The size of the sample aliquots were too small and the analysis counting time is too short to allow reasonable accurate measurement of a ^{239}Pu concentration as low as ERDA Manual Chapter 0524, Appendix, Table II values. This is true even if the samples collected were ideally representative.
- Because of the choice of sampling locations and the nonisokinetic extraction of the sample airstream there is good probability that the extracted samples are biased, and to unknown degrees.
- The size of the current sample aliquots are in doubt because of inadequate use of flowmeasuring devices.

Besides these four deficiencies common for both stacks, there are many others enumerated in the report. Several preliminary recommendations for corrective action are outlined herein. The incorporation of these recommendations into the design of improved sampling and monitoring systems will result in systems which better comply with the Interim Criteria.

NOMENCLATURE

AED	aerodynamic equivalent diameter
c	counts
cc	cubic centimeter
cfm	cubic feet per minute
Ci	Curie
cpm	counts per minute
d	disintegration
dpm	disintegrations per minute
fpm	feet per minute
ft ³	cubic feet
°F	degrees Fahrenheit
in.	inch
MeV	mega (million) electron volts
min	minute
mm	millimeter
scfm	standard cubic feet per minute (@ 70°F, atmospheric pressure)
μCi	micro (10 ⁻⁶) curie
μm	micro (10 ⁻⁶) meter (micron)

REFERENCES

1. Instrumentation Manual for RADeCO Model 440M, RADeCO Inc., 4161 Campus Point Court, San Diego, California, 92121. (a)
2. Calibration and Source Checks of Eberline and RADeCO Constant Alpha Air Monitors, Radiation Monitoring Manual of Standard Practices, Procedure No. 19.6, pages 5-10, ARHCO, (1976). (a)
3. Emergency and Holiday Coverage of 222-S Counting Room, Technical Services Section, Laboratory Operations Procedure No. ECOVCR-01A, ARHCO, (October, 1973). (a)
4. An Outline of Environmental Air Sample Analysis, ARH-869, ARHCO, (October, 1968). (a)
5. ERDA Manual Chapter 0524. Appendix, Annex A, (November, 1968).
6. Environmental Gaseous Discharges from 291-Z Stack, Z-Plant, ARHCO Emergency Procedure, ARH-222-3.2.12(1), (August, 1975). (a)
7. American National Standards - ANSI N13.1-1969, Guide to Sampling Airborne Radioactive Materials in Nuclear Facilities, American National Standards Institute, New York, New York, (1969).
8. Environmental Gaseous Discharges from 296-Z-3 Exhauster, Z-Plant, ARHCO Emergency Procedure ARH-222-3.2.12(2), (August, 1975). (a)

DRAWINGS - ARHCO Engineering Files

9. H-2-16015, 291-Z Exhaust Fan Tunnels and Stack Foundation. (b)
10. H-2-16016, 291-Z Sections and Details for Exhaust Fan Tunnels. (b)
11. H-2-16485, 291-Z Breathing Air System and Air Monitoring and Vacuum System. (b)
12. H-2-24543, In-Line Air Sampler Assembly and Details. (b)

(a) ARHCO internal procedure in place at time of work (1976).

(b) Copies can be obtained through Pacific Northwest Laboratory Engineering Files (509) 376-0067.

13. H-2-26135, 241-Z Sump Continuous Stack Sampler. (a)
14. H-2-26146, Electrical 241-Z Sump Continuous Stack Sampler. (a)
15. H-2-43549, Waste Sumps Facility Equipment and Piping Arrangement Plans. (a)
16. H-2-43552, Exhaust System 241-Z Sump Arrangement and Sections. (a)

(a) Copies can be obtained through Pacific Northwest Laboratory Engineering Files (509) 376-0067.

APPENDIX

INTERIM RADIOACTIVE GASEOUS EFFLUENT SAMPLING AND MONITORING
CRITERIA FOR ARHCO FACILITIES

Date: November 12, 1975
To: Distribution
From: B. J. McMurray *BJ McMurray*
Subject: INTERIM RADIOACTIVE GASEOUS EFFLUENT SAMPLING AND
MONITORING CRITERIA FOR ARHCO FACILITIES

In a continuing effort to report radioactive emissions to the environment as accurately as practicable, the performance of ARHCO's gaseous effluent sampling and monitoring systems is being studied by the Particulate and Gaseous Waste Research Section of Battelle-Northwest. This study has revealed several problems with our existing sampling systems.

In order to upgrade the performance of ARHCO's sampling and monitoring systems, positive goals must be set that will ensure that changes proceed in a direction that will result in improvements of the systems. The attached interim gaseous effluent sampling and monitoring criteria have been developed to aid those involved in the design, fabrication, and operation of these systems. It must be recognized that portions of the criteria are not easy to meet unless the sampling and monitoring systems are carefully planned and designed with these goals in mind.

The effectiveness of the attached interim criteria will be evaluated as improvements in existing systems are made, or as new systems are brought on line, to determine if changes in the criteria are necessary.

BJM:DJC:bac

Distribution

G. E. Backman/K. R. Price	J. Mishima - BNW
G. J. Bracken/D. M. Smith - ERDA-RL	G. C. Oberg
L. E. Bruns	R. G. Oliver
D. J. Carrell	B. J. Saueressig
J. L. Glissmeyer - BNW	L. C. Schwendiman - BNW
G. L. Hanson	H. P. Shaw
H. A. Lee	R. M. Smithers
C. W. Malody	A. T. White

INTERIM RADIOACTIVE
GASEOUS EFFLUENT SAMPLING AND MONITORING CRITERIA
FOR ATLANTIC RICHFIELD HANFORD COMPANY FACILITIES

INTRODUCTION

To ensure that gaseous radioactive releases to the environment are kept as low as practicable, it is necessary to sample all of the radioactive or potentially radioactive gaseous effluent streams in the 200 Areas. Specific gaseous effluent streams that have the potential for release of large quantities of radioactive materials must also be monitored by radiation detection instrumentation.

The criteria listed below are intended to be used as guidelines to aid in the design of new systems or the upgrading of existing systems. It is highly desirable that new or upgraded systems be able to meet or nearly approach as many of the following criteria as is practicable.

SAMPLING CRITERIA

The term "sampling" applies to the extraction, transport and collection of a sample of the radionuclides present in the gaseous effluent stream on a collection media suitable for subsequent laboratory analysis. Gaseous effluent sampling systems shall:

1. extract in a 24-hour period a representative fraction of the effluent stream such that an activity release at least as low as the concentration guides given in ERDA Appendix 0524, Annex A, Table II can be measured with appropriate accuracy upon subsequent laboratory analysis.*
 2. be designed, fabricated, and operated so that the particles extracted and transported to the collector will be representative to the degree that particles 10 micrometers and smaller in the sample collected will be at least 90 percent of the 10 micrometer and smaller particles in the same volume of a truly representative sample. At least 90 percent of the radioactive gases withdrawn shall be collected on the media selected or delivered to the activity sensing chamber in flow through monitors.
 3. operate in a continuous mode, except for short periods when the sample collection media is being changed, whenever the facility is exhausting to the atmosphere.
 4. extract samples of particles and gases that are a representative aliquot of the actual effluent stream.
- * If one half of the Class I Action Level in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility) is less than the Table II concentration guides, use one half of the Class I Action Level from the appropriate Emergency Procedure as the basis for this criterion.

5. collect at least two samples, one of which will be designated and used exclusively as an inventory sample.
6. shall provide particulate and gaseous samples that have not been adversely affected by condensation of moisture.
7. be equipped with a vacuum system for sample extraction that has the same number of back-up power systems as the exhaust fans of the facility. The vacuum system shall be provided with an alarm that is activated upon the loss of vacuum.
8. provide an inventory sample which is an accurate aliquot, within a factor of two, of the absolute radioactive materials of the effluent stream. (Note: This statement relates only to the sample extraction and delivery capability, not to the accuracy of detection and measurement.)
9. provide inventory samples with less than 25 percent variation from the mean of several similar samplings at the 95 percent confidence level.
10. have at least an annual check to ensure that variation in effluent characteristics (particle size, mass activity concentrations, etc.) have not changed significantly.

MONITORING CRITERIA

The term "monitoring" applies to the use of radiation detection instrumentation to measure the amount of radioactivity collected by the collection media. Gaseous effluent monitoring systems shall:

1. monitor the samples collected (except for the designated inventory sample) as detailed in items 1-10 under Sampling Criteria. The monitoring system shall be able to detect an activity release at least as low as one half that required for the Class I Action Level listed in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
2. detect the radiation from radionuclides in the effluent stream with appropriate sensitivity for the radiation emitted.
3. operate in a continuous mode, except for short periods while samples are being changed, whenever the facility is exhausting to the atmosphere.
4. be equipped with the same number of back-up power systems as the exhaust fans of the facility.
5. incorporate a permanent recorder to document the level of radioactivity measured by the radiation detection instrument.

6. be provided with a "fail-safe" system that alarms when a malfunction occurs in the radiation detection instrument or upon loss of vacuum.
7. alarm at a pre-set "trip" point that is consistent with a Class II Action Level as specified in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
8. be able to detect a Class II Action Level as specified in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility) in less than 24 hours.
9. alarm visually and audibly in a continuously occupied area for both the "fail-safe" alarm(s) and the emergency alarm(s).
10. be equipped with sufficient range to detect activity levels up to 100 times the Class II Action Level in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
11. have the radiation detection instrumentation calibrated on at least a quarterly basis.

DISTRIBUTION

No. of
Copies

No. of
Copies

OFFSITE

12 DOE/Office of Scientific
and Technical
Information

ONSITE

DOE Richland Field Office

J. E. Mecca A6-55

7 Westinghouse Hanford
Company

M. Haas T5-50
L. A. Garner (5) T5-54
E. C. Vogt T5-50

13 Pacific Northwest
Laboratory

J. A. Glissmeyer (5) K6-03
W. R. Gorst K6-86
J. V. Ramsdell K6-03
Publishing Coord. K1-06
Tech. Rpt. Files (5) P8-55

Routing

R. M. Ecker SEQUIM
J. W. Falco K6-78
M. J. Graham K6-80
R. L. Skaggs K6-77
P. C. Hays (last) K6-86

**DATE
FILMED
5/01/92**