TOP SECRET

**DOE/MC/25124-3014
(DE91002094)**

**CONCEPTUAL DESIGN OF COAL-FUELED DIESEL SYSTEM FOR STATIONARY
POWER APPLICATIONS**

Topical Report

May 1989

Work Performed Under Contract No. AC21-88MC25124

**For
U.S. Department of Energy
Morgantown Energy Technology Center
Morgantown, West Virginia**

**By
Arthur D. Little, Inc.
Cambridge, Massachusetts**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

**Conceptual Design of Coal-Fueled Diesel System
for Stationary Power Applications**

Topical Report

Work Performed Under Contract No.: DE-AC21-88MC25124

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
Arthur D. Little, Inc.
20 Acorn Park
Cambridge, Massachusetts 02140-2390**

May 1989

Table of Contents

	<u>Page</u>
List of Tables	v
List of Figures	viii
I. EXECUTIVE SUMMARY	1
A. Objectives of the Conceptual Design Study	1
B. Participants and Methodology	1
C. Summary of Results	2
II. OVERALL FACILITY DESIGN AND COAL-FUELED ENGINE	5
A. Plant Configuration and Major Subsystems	5
B. Recent Stationary Power Installations by Cooper-Bessemer	10
C. Diesel Engine Components Modified for Coal	11
D. Engine Component Cost Estimates	16
E. Overhaul Cost Estimates	17
III. STATIONARY POWER MARKETS TO BE SERVED	20
A. Selection of Applications and Plant Configurations	20
B. Cogeneration Prime Mover Requirements by Industry	22
C. Growth in Electric Power Capacity - Projected Need for Capacity Additions	22
D. Regions of Greatest Potential	25
E. Market Share for Coal Diesel Systems - Other Competing Technologies	28
F. Capacity-Growth Scenarios for Modular Coal Diesel Plants	30
IV. COAL PROCESSING AND TRANSPORTATION	33
A. Coal Processing Analysis Methods	33
B. CWS Specifications	34
C. Plant and Process Description	36
D. Description of Process Areas	36
E. Capital Cost Estimates	44
F. Operating Cost Estimates	46
G. Feedstock and Transportation	52
H. CWS Cost Summary	52
I. Cost Analysis Uncertainties and R&D Directions	58
J. Cost Modeling Runs	59
K. Cost Look-Up Table and Impact of Variables	61

Table of Contents (Continued)

	<u>Page</u>
V. EMISSION CONTROL SYSTEM DESIGN	67
A. Introduction and Emission Targets	67
B. Emission Control Technologies for Preliminary Conceptual Design	69
C. Selection of Integrated System Design Options	78
D. Cost Analysis Methodology and Assumptions	81
E. Discussion of Economic Analysis	96
F. Conclusions/Directions for Emissions R&D Program	112
VI. ANALYSIS OF ECONOMICS	115
A. Summary	115
B. Engine Component Cost Premiums Associated with Coal	115
C. Cost to Produce Engine-Grade Coal Fuels	117
D. Cost of Emission Control Systems	118
E. Projected Cost of Coal-Fueled Diesel Power	119
F. Parametric Sensitivity Analysis	119
VII. TECHNOLOGY GAPS AND HIGH PRIORITY R&D DIRECTIONS	125
VIII. COMMERCIALIZATION PLAN AND PROJECTED PENETRATION RATE	128
REFERENCES	R-1
Appendix A: CWS Plant Equipment Lists	A-1
Appendix B: CWS Process Cost Model	B-1
Appendix C: Sample CWS Cost Model Runs	C-1
Appendix D: Coal Feedstock Analyses	D-1
Appendix E: Alternative Designs for Higher Efficiency	E-1
Appendix F: Emission Control Technologies	F-1
Appendix G: Emission Control System Options - Process Diagrams	G-1
Appendix H: Cost Calculations for Emission Control System Options	H-1
Appendix I: Computer Model of Coal-Fueled Diesel System Economics	I-1

List of Tables

<u>Table No.</u>		<u>Page</u>
II-1	Cooper-Bessemer Model LSVB-20 Diesel Engine	5
II-2	Coal Engine Fuel System Components	13
II-3	Coal Engine Combustion System Components	13
II-4	Coal Engine Lube System Components	16
II-5	Coal Engine Intake/Exhaust System	16
II-6	Estimated Cost Premiums for Coal Diesel Engine Components	17
II-7	Engine Maintenance and Overhaul Costs	19
III-1	Coal Diesel Plant Configurations	22
III-2	Number of Existing Manufacturing Plants with Diesel Cogeneration Potential	23
III-3	Potential Demand for Diesel Engines for Cogeneration in Existing U.S. Manufacturing Plants	23
III-4	Fossil Fueled Power Plant Additions, 1991-2010 Forecast	24
III-5	Regions with Capacity Additions and Their Potential for CWS Diesel Plants	26
III-6	Actual vs. Forecast KWH Demand Growth (1983-1987)	28
III-7	Recent Trends in Stationary Engines (New Orders for North America)	29
III-8	Western Europe New Orders for Stationary Engines	30
III-9	Significant Potential Growth in Reciprocating Engine Power Plant Capacity, All Fuels	31
III-10	Scenario for Coal Diesel Market Penetration	32
IV-1	Engine-Grade CWS Specifications	35
IV-2	Typical Characteristics of Two CWS Fuels Produced by AMAX	37
IV-3	Process Plant Areas for 1.5% Ash CWS	40
IV-4	Process Plant Areas for 0.5% Ash CWS	40
IV-5	Capital Costs for CWS Processing Plant	45
IV-6	Processing and Operating Cost Factors for CWS Plant	46
IV-7	Labor Requirements	47
IV-8	Power Usage by Area	48
IV-9	Chemical Reagent/Additive Costs	50
IV-10	Operating Cost Summary for CWS Plant	51
IV-11	Coal Properties by Source (As Received Basis)	53
IV-12	Coal Transportation Cost Estimates	54

**List of Tables
(Continued)**

<u>Table No.</u>		<u>Page</u>
IV-13	Costing Assumptions	55
IV-14	CWS Plant Cost Summary - Physical Cleaning Plant	56
IV-15	CWS Plant Cost Summary - Chemical Cleaning Plant	57
IV-16	CWS Costing Uncertainties	60
IV-17	Assumptions for CWS Specifications Used in Cost Modeling Runs	62
IV-18	CWS Cost Look-Up Table	63
IV-19	Fuel Quality Scenarios	65
IV-20	Comparison of Costs for Eastern vs. Western Coals in Western Coal Plant	66
V-1	New Source Performance Standards for Stationary Sources	68
V-2	Assumed Engine Operating Conditions	70
V-3	Systems for Coal-Fueled Diesel Operation	71
V-4	Emission Control Subsystems	74
V-5	Probability of Technical Success for Emission Control Technologies	80
V-6	Emission Control System Options and Priorities for Research	82
V-7	Design and Cost Estimate Classifications	84
V-8	Methods Used to Estimate Subsystem Equipment Costs	86
V-9	Summary of SCR Cost Data	87
V-10	SCR Equipment and Catalyst Costs Used in Economic Analysis	90
V-11	Differential Costs of Coal-Fueled Engine Relative to Oil-Fueled Engine for Production of 125 psig Steam	92
V-12	Equipment Costs for Subsystems	94
V-13	Commodity Prices for Operating Cost Calculation	95
V-14	Coal-Fueled Diesel Emission Control System Capital and Operating Cost Summary for 1 LSB6 Engine (1.8 MW)	97
V-15	Coal-Fueled Diesel Emission Control System Capital and Operating Cost Summary for 4 LSB6 Engines (7.2 MW)	98
V-16	Coal-Fueled Diesel Emission Control System Capital and Operating Cost Summary for 2 LSVB20 Engines (12 MW)	99
V-17	Coal-Fueled Diesel Emission Control System Capital and Operating Cost Summary for 2 LSVB20 Engines (12 MW - No Cogeneration)	100

**List of Tables
(Continued)**

<u>Table No.</u>		<u>Page</u>
V-18	Coal-Fueled Diesel Emission Control System Capital and Operating Cost Summary for 4 LSVB20 Engines (24 MW)	101
V-19	Effect of Manifold Air Temperature on Process History	111
VI-1	Key Modifications to Economic Model	116
VI-2	Impact of Coal Fuel on Maintenance and Overhaul Practices	117
VI-3	Emissions Control Subsystem Costs	118
VI-4	Projected Cost of Power for Coal-Fueled Diesel Plant	119
VI-5	Cost of Power Depends on Source Coal and CWS Process	120
VI-6	Coal Transportation to Various Cities Affects Cost of Power by 5-10%	121
VI-7	Choice of Emission Control System Affects Cost of Power	122
VI-8	Increased Load Factor Can Lower Power Costs by About 5-10%	122
VI-9	Uncertainty Level	124
VIII-1	Cooper-Bessemer Commercialization Plan for Coal-Fueled Diesel	129

List of Figures

<u>Figure No.</u>		<u>Page</u>
II-1	Cooper-Bessemer LSVB Dual Fuel Engine Cross Section	6
II-2	Typical LSVB Engine Heat Balance	7
II-3	Plant Layout	8
II-4	Plant Layout	9
II-5	Injection System for CWS	12
II-6	Button Nozzle	14
II-7	Combustion Chamber Design	15
III-1	Regions for Potential Coal Diesel Applications	27
IV-1	Schematic of AMAX R&D Engine-Grade Coal Cleaning Process - 1.5% Ash Coal, Physical Cleaning Plant Configuration	38
IV-2	Schematic of AMAX R&D Engine-Grade Coal Cleaning Process - Ultra-Low Ash Configuration	39
V-1	Integration of Emission Control Subsystems with Engine Systems	72
V-1A	Example of Emission Control Design Configuration	79
V-2	Cost of SCR for Engine Emission Control	88
V-3	Capital Cost for Cogeneration System	103
V-4	Annual Operating Cost for Cogeneration System	104
V-5	Annual Operating Cost vs. Probability of Technical Success for 1.8 MW _e Cogeneration System	106
V-6	Annual Operating Cost vs. Probability of Technical Success for 7.2 MW _e Cogeneration System	
V-7	Annual Operating Cost vs. Probability of Technical Success for 12 MW _e Cogeneration System	108
V-8	Annual Operating Cost vs. Probability of Technical Success for 12 MW _e Power System	109
V-9	Annual Operating Cost vs. Probability of Technical Success for 24 MW _e Cogeneration System	110
V-10	Coal-Diesel NO _x Target Compared to Gas Turbines	114
VI-1	Emission Control Costs Appear Acceptable Above About 7 MW Plant Size	123
VII-1	Coal-Fueled Diesel R&D Priorities	126

I. EXECUTIVE SUMMARY

A. OBJECTIVES OF THE CONCEPTUAL DESIGN STUDY

The ADL/Cooper team prepared a preliminary conceptual design of a coal-fueled diesel system as part of a previous systems study, and this design concept was described in the 1986 Topical Report.⁽¹⁾ Since then, our team has accumulated extensive results from testing coal-water slurry on the 13-inch bore JS engine (400 rpm) in 1987 and 1988. These results provided new insights into preferred design concepts for engine components. One objective, therefore, was to revise the preliminary design to incorporate these preferred design concepts. In addition, there were certain areas where additional, more detailed analysis was required as a result of the previous conceptual design. Another objective, therefore, was to perform additional detailed design effort, as follows:

- Market applications and engine sizes: ADL prepared a more detailed regional analysis of modular power new capacity needs in the U.S. The results are reported in Chapter III.
- Coal-water slurry cleaning and grinding processes were re-examined in light of recent developments (AMAX). The results of this re-examination can be found in Chapter IV.
- Emission controls and hot gas contaminant controls were characterized in sufficient detail to allow cost estimates (PSI). Nine emission control system options were compared and of these four were selected as most promising. The results appear in Chapter V.
- Component durability: ADL and Cooper estimated the cost of wear resistant parts for the coal-fueled engine, including injection nozzle inserts, rings, liner, valves, valve seats, turbo-charger blades, crankcase bearings and the filtration system. The expected lifetime of components and the number of required replacements of these components during the total engine life were also estimated. Key results are reported in Chapter II.
- Costs and performance targets for each major subsystem component-by-component were analyzed. This provided more detail than the 1986 Systems Study which estimated only overall maintenance and capital cost premiums for the entire diesel system. See Chapter II, Sections D and E, for results.

Combining all this design information, ADL performed a computer-based economic analysis, including a parametric sensitivity analysis, which is reported in Chapter VI. Also, Cooper-Bessemer and ADL revised the commercialization plan (Chapter VII). Critical variables affecting market feasibility were flagged for attention. R&D priorities for the ongoing coal-fueled diesel program were reexamined (see Chapter VIII).

B. PARTICIPANTS AND METHODOLOGY

Cooper-Bessemer provided preliminary designs of coal diesel cogeneration and power plants, including parts lists, estimated costs, site drawings, and maintenance schedules. Cooper-

Bessemer and ADL also specified durable components (e.g., valves, rings, liners, turbocharger) including costs and replacement schedule based on existing knowledge (see Section II). Cooper-Bessemer also updated the commercialization plan (see Section VIII).

AMAX provided designs for two alternative engine grade CWS processes (physical and chemical cleaning), estimated costs for processing typical U.S. coals to meet specifications, specified the additive package, and designed the on-site fuel storage subsystem (see Section IV).

ADL reviewed the electric power and cogeneration trends in the US. for the next twenty years, including a region-by-region analysis of new capacity. Particular attention was given to modular capacity requirements below 100 MW plant size and below 15 MW engine size (see Section III).

PSI identified appropriate emission control technologies and designed integrated emission control packages (NO_x , SO_x , particulate) which will enable the coal diesel to meet future anticipated emission limits. Costs and development risks were included in their analysis (see Section V).

C. SUMMARY OF RESULTS

Five power plant design configurations were studied, ranging in size from the 1.8 MW plant based on a single 6-cylinder Cooper-Bessemer LSB-6 engine to the 24 MW plant which is based on four 20-cylinder LSVB-20 engines. Both cogeneration and power-only configurations were studied. Plant availability is known to be 90% for the LS series engine, and shaft efficiency is 40% on a higher heating value (HHV) basis. The engine has been designed so that these performance parameters should be the same for operation on coal water slurry as for standard operation on diesel fuel, and preliminary engine tests on CWS bear this out. Bottoming cycle options described in Appendix E can raise plant efficiency to approximately 46% (HHV), which is quite advantageous not only for lowering fuel consumption but also for reducing the greenhouse gas (CO_2) impact.

The engine is designed to burn physically cleaned "engine-grade" CWS with up to 1.5% ash on a dry coal basis; this is a major departure from earlier fuel specifications which called for relatively costly 0.5% ash chemically-cleaned CWS. The maximum particle size specification is in the 50 to 75 micron range. The slurry would be regionally produced in the same metropolitan area as the diesel plants and then delivered locally by tank truck, not unlike the practice for diesel oil today. The 180 ton/hr regional coal cleaning plant has been configured into a preliminary process design, and can be estimated to cost \$135 million installed. The processing cost for physical cleaning and slurry formulation is estimated at \$0.81/MMBtu, to which must be added the amortized capital cost of approximately \$0.55/MMBtu. A number of suitable coal feedstocks have been identified such as Kentucky Blue Gem and Elkhorn (see Table IV-11), using these coals it appears that clean CWS can be delivered to coal diesel power plants at a total cost of \$2.75 to \$3.50/MMBtu. Both Eastern and Western coals (e.g., Utah Castlegate) are attractive.

Special durable engine components have been specified to minimize erosive wear by coal and ash. Cooper has budgeted an extra \$1.7 million (50% additional) for the installed cost of a 6 MW engine to cover these modified and redesigned engine components, the most critical of which are:

- Piston rings and liners (100% assumed cost increase; 12000 hr life vs. 25000 hr std)
- Injection system (200% assumed cost increase; 500 hr life vs. 2000 hr std)
- Cylinder heads (50% assumed cost increase)
- Turbocharger (200% assumed cost increase; 25000 hr life vs. 100000 hr std)

The total overhaul and parts replacement for each 6 MW coal diesel engine is estimated at \$195,000 per year (vs. \$70,000 per year for conventional engine). This translates to 5.2 mills/kWh vs. 1.9 mills/kWh for the conventional diesel engine.

The coal diesel conceptual design is for a plant which has *lower* emissions than any state-of-the-art coal steam plant (0.6 and 1.2 lb/MMBtu for NO_x and SO_x, respectively). The emissions control subsystem is easy to distinguish from that of a conventional large stationary engine, in that it relies heavily on exhaust treatment modules, such as:

- Cyclone upstream of turbocharger to remove larger particles (over 5 micron size)
- Selective Catalytic Reduction (SCR) for NO_x control
- Spray dryer for SO₂ control
- Baghouse for particulate control and to capture sorbent

Preliminary cost estimates for this emissions subsystem indicate that for a 12 MW coal diesel plant the total cost will be about \$2.50/MMBtu (\$.0219/kWh), plus or minus 25% depending on the control options selected. This is significantly higher than our previous 1988 estimate, and reflects actual quotations for appropriate size components. It should be emphasized that the emission control cost estimates presented here are conservative and probably will be reduced in the course of developing actual components for the engine. Of the nine candidate emissions control systems analyzed in Chapter V, this system is the only one which relies on conventional technology for SO₂ and NO_x control. Three other systems based on "unconventional" technology also appear worthy of further R&D for the coal diesel system (see Chapter V).

Another finding from the emissions analysis was that coal diesel plants below about 7 MW appear to be prohibitively costly when fully equipped to control NO_x and SO_x emissions. This does not rule out all future sites for the 2-7 MW cogeneration market, however. This is proven by the recent active market in gas- and oil-fueled stationary reciprocating engines below 7 MW, most of which have NO_x emissions levels far in excess of the 0.6 lb/MMBtu target of the coal diesel design (with SCR) described in this report.

The overall cost of electricity is forecast to be between 6 and 7¢/kWh for the typical coal-diesel plant (12 MW capacity). This estimate is essentially unchanged from one 1986 study; whereas, emissions subsystem costs have been set at higher levels, this is compensated by coal slurry cleaning costs which have been revised downward based on physical cleaning (1.5% ash). The coal diesel technology would appear to become competitive as soon as the diesel fuel oil price

reaches about \$0.79/gallon (\$5.50/million Btu). The highest R&D priorities are now assigned to specific options for achieving lower cost coal processing methods, lower cost NO_x control, and durable injection nozzle tips and piston rings.

II. OVERALL FACILITY DESIGN AND COAL-FUELED ENGINE

A. PLANT CONFIGURATION AND MAJOR SUBSYSTEMS

The stationary coal diesel facility has a design configuration based on today's stationary diesel and dual-fuel engine power plants. The coal diesel power plant is intended for capacities from 1.8 MW output (one six-cylinder engine) up to 48 MW output (eight 20-cylinder engines). The Cooper-Bessemer Models LSB/LSVB engines, suitably modified for coal, will be used for these power plants. This engine series is nominally rated at 300 kW per cylinder and can be built as an in-line engine (6, 8, 10 cylinders; 1.8 to 3 MW) and as a vee-form (12, 16, 20 cylinders; 3.6 to 6 MW). Table II-1 shows the basic parameters of the LSB engine, and Figure II-1 shows the basic components in cross section. The brake mean effective pressure (bmep) at 200 psi is relatively conservative (about 2/3 that of locomotive engines), and this gives the Cooper LSB and LSBV Series engines the advantages of large combustion space in the cylinder, low overhaul and maintenance costs, and relatively high efficiency (see Figure II-2). Preliminary tests with the model JS engine indicate that the engine efficiency on coal fuel will be essentially the same as with diesel oil (about 40%). Also, bottoming cycle options exist which can raise the plant efficiency to about 46% (see Appendix E).

Table II-1
COOPER-BESSEMER MODEL LSBV-20 DIESEL ENGINE

No. of cylinders	20
Arrangement	Vee-form, turbocharged, intercooled
Output (nominal)	8385 bhp (6000 kW, 300 kW per cylinder)
Bore	15.5"
Stroke	22.0"
Speed (nominal)	400 rpm
Brake mean effective pressure (nominal)	200 psi
Specific fuel consumption	0.345 lb/bhp-hr (6300 Btu/hp-h)
Fuel spec	#2 diesel fuel/heavy diesel fuel
Lube oil consumption	15,000 bhp-h/gal

The engine will be designed to burn "engine-grade" coal water slurry (0.5 to 1.5% ash is the current range of ash specifications, on a dry coal basis) of 10 to 15 micron mean particle size, with 50 to 75 micron maximum size. This slurry would be regionally produced (see Section IV) and delivered by tank truck to the power plant, not unlike the practice for diesel oil today.

The overall plant configuration is shown in Figures II-3 and II-4 for a typical cogeneration configuration of two 20-cylinder engines (12 MW total output). The emissions control system is different than for a conventional stationary engine plant, and includes the following modules in the sequence seen by the exhaust gas:

FIGURE II-1. COOPER-BESSEMER LSVB DUAL FUEL ENGINE CROSS SECTION

FIGURE II-2.

Typical LSVB Engine Heat Balance (8550 BTU/kW-hr Input)

FUEL INPUT THAT CAN BE
RECOVERED AS USABLE ENERGY.
(TYPICALLY 85%)

FIGURE II-3. PLANT LAYOUT

FIGURE II-4. PLANT LAYOUT

The high availability and low maintenance of the Cooper-Bessemer engines was a critical decision for TDEC, because for district heating to be economical the engines must run constantly, as close to full load as possible. In the first 20 months of operation the engines ran almost continuously at a 92% load factor. Nearly all downtime was for scheduled preventive maintenance. No other engine we know of has been able to achieve performance like this for a cogeneration project of this size.

Another typical appreciation is the Indiana University project (four engines at 6430 kw). This cogeneration facility will produce not only enough steam and electricity to serve all campus buildings but also an excess of electricity which will be sold to the Pennsylvania Electric Company (PENELEC). Four natural gas-fired reciprocating engines will produce 24.3 megawatts of electricity. As the university requires approximately 4.3 MW, the remaining 20 MW can be marketed. At present, a coal-powered steam plant produces energy to heat and cool the majority of the buildings on campus. All but 2 to 3 percent of the university's requires electricity is purchased from PENELEC. The cogeneration facility would reduce IUP's annual estimated electricity and steam costs from \$2.7 million to \$506,000. The savings, added to the revenue produced by the sale of excess electricity, could total \$110 million over the next 20 years. This additional income could be used for augmenting academic programs and facilities and would become a major factor in long-range planning.

C. DIESEL ENGINE COMPONENTS MODIFIED FOR COAL

There are five engine subsystems where the Cooper-Bessemer engine will be impacted by coal water slurry:

- Fuel System
- Combustion Chamber
- Lube Oil System
- Air/Exhaust System
- Emissions Control System

Working with the team of subcontractors, Cooper has selected a preliminary design philosophy for each subsystem, and in most cases has selected a design concept which reflects that philosophy. As test data from this program becomes available, the design concepts will be modified accordingly. Cooper's current outlook is as follows for each engine subsystem:

(a) FUEL SYSTEM

Table II-2 lists the components of the fuel system for a coal engine.

The fuel injection system for coal water slurry, as currently configured, has minimal changes from the standard Diesel F.I. system. The preliminary design used in the JS tests is shown in Figure II-5. An isolating piston protects the pump and metering mechanism from the abrasive slurry. The components include:

FIGURE II-5. INJECTION SYSTEM FOR CWS

Table II-2
COAL ENGINE FUEL SYSTEM COMPONENTS

Item	C-B Fabricated or Bought	Modifications Required for CWS
Storage tank	B	Modified design for continuous agitation; design protects against settling and freezing; extra DF2 tank.
Transfer pump, piping valves, etc.	B	Moyno pump; common rail leading to F.I. pumps; dual system for DF2 and CWS.
Fuel injection pump	B	Larger pumps, operate on DF2; extra pump for DF2 pilot.
Injectors	B	Modified design (AMBAC); extra DF2 pilot injectors.

- Conventional cam driven jerk pump.
- Injectors which are designed to handle either CWS/DF2 or DF2: Figure II-6 shows one of the ceramic injector tip designs which are intended to prevent cavitation and withstand abrasion.
- Conventional control system.

Since DF2 or natural gas will be used as pilot fuel for ignition, two entire fuel systems are included in the design. For example, if a DF2 pilot is selected, the engine will have two fuel rails (one for CWS and one for DF2); two sets of fuel pumps, two sets of injectors, and two storage tanks.

(b) COMBUSTION SYSTEM

Table II-3
COAL ENGINE COMBUSTION SYSTEM COMPONENTS

Item	C-B Fabricated or Bought	Modifications Required for CWS
Cylinder heads (see Figure II-7)	C-B	Modified head design to allow gas torch or diesel pilot ignition
Air/exhaust valves	B	Special hard coatings to prevent erosion
Cylinder liners	C-B	Hard coatings to withstand abrasion
Pistons	C-B/B	Increased compression ratio to assist ignition; possible bowl in piston
Piston rings	B	Hard coatings and special profiles

FIGURE II-6. "BUTTON" NOZZLE

FIGURE II-7. COMBUSTION CHAMBER DESIGN

(c) LUBE OIL SYSTEM

Table II-4
COAL ENGINE LUBE SYSTEM COMPONENTS

Item	C-B Fabricated or Bought	Modifications Required for CWS
Lube oil	B	Special oil for enhanced ash removal
Lube oil pump, piping valves, etc.	B	Standard design
Lube oil injection design	C-B	Possible modification design to flush ring land area
Filters	B	Possible modification for higher ash loading (2-stage)
Bearings	B	Standard design

(d) INTAKE/EXHAUST SYSTEM

Table II-5
COAL ENGINE INTAKE/EXHAUST SYSTEM

Item	C-B Fabricated or Bought	Modifications Required for CWS
Intake manifold and aftercoders	C-B	Modified for higher pressure and possible air pre- heating after turbocharger
Intake filters manifolds, silencers, etc.	C-B/B	Standard design
Turbocharger	C-B	Modified design with hard coatings; turbocharger relocated to allow cyclone
Exhaust manifold	C-B	Entirely new design; greater length; accommo- dates emission control modules

(e) EMISSIONS CONTROL SYSTEM

Designs for the emission control system are described in Section V.

In summary, the major C-B manufactured components affected by CWS are as follows:

- Cylinder heads
- Cylinder liners
- Pistons
- Turbocharger
- Intake and exhaust manifolds

D. ENGINE COMPONENT COST ESTIMATES

The cost premiums associated with the critical engine parts are estimated in Table II-6. Note that the total premium is \$1.1 million ex-factory, and that the most expensive items, in terms of adapting the engine to coal fuel, are the turbocharger, the fuel pumps, the injectors and supply

system, and the instrumentation. Installation costs will carry a premium for the coal diesel as well, because of extra slurry pumps, tanks, and piping; the offset turbocharger and related exhaust manifolding; the extra instrumentation; the diesel pilot system, etc. Permits and compliance testing will also be more costly. This is accounted for in Table II-6 by applying 50% installation to the entire engine cost.

Table II-6
ESTIMATED COST PREMIUMS FOR COAL DIESEL ENGINE COMPONENTS
(20 cylinder, 6 MW engine)

Engine Components	Conventional Diesel ⁽¹⁾	Coal Diesel	Differential
Lube System	\$30,000	\$65,000	
Pistons and Piston Rings	50,000	70,000	
Cylinder Liners	100,000	200,000	
Cylinder Head(s)	200,000	300,000	
Valves/Seats	30,000	40,000	
Fuel Pumps, Injectors, Supply System	100,000	300,000	
Instruments	50,000	200,000	
Turbocharger	200,000	600,000	
Cam Shaft and Bearings	50,000	100,000	
Miscellany	<u>200,000</u>	<u>250,000</u>	
Subtotal Critical Parts	\$1,010,000	\$2,125,000	\$1,115,000
Non-Critical Parts	<u>1,350,000</u>	<u>1,350,000</u>	
Total Engine Cost	\$2,360,000	\$3,475,000	
Installation Costs (50%)	<u>1,180,000</u>	<u>1,737,500</u>	
Installed Engine Cost	\$3,540,000	\$5,212,500	\$1,672,500

⁽¹⁾Component costs for the conventional engine are nominal representative values based on C-B's broad experience, and do not necessarily correspond to prices of actual current engine parts of any specific C-B engine model.

E. OVERHAUL COST ESTIMATES

The overhaul and maintenance for a coal-fueled engine are significantly greater than for a conventional diesel. Not only are the parts replacement intervals shorter with coal, but the parts themselves are more costly. Four basic maintenance and overhaul service functions were considered:

- Injector tip inspection and replacement
- Inspection of filters, valve clearance, etc.
- "Top-end" overhaul (cylinder head rebuilds)
- "Bottom-end" overhaul (pistons, liners, crankcase bearings)

Table II-7 shows the intervals and cost estimates which we have prepared for the coal diesel versus the conventional engine. The period we analyzed was 20 years; this is sufficient to allow bottom-end overhaul costs to enter the calculation. The total overhaul costs for the coal diesel over 20 years amounts to \$3.9 million versus \$1.4 million for the conventional diesel. The injectors are a significant factor (over 25%) in this total; we have assumed \$3200 per set of twenty injector tips (\$160 per injector tip) and a 500 hour replacement interval. Each of these estimated numbers has a significant uncertainty at this stage of the program.

Table II-7
ENGINE MAINTENANCE AND OVERHAUL COSTS

Description	Unit of Measure	Coal Diesel	Conventional Diesel
MAINTENANCE INTERVALS			
Injectors	Hours/Cycle	500	2,000
Minor	Hours/Cycle	4,000	8,000
Top End	Hours/Cycle	12,000	25,000
Bottom End	Hours/Cycle	25,000	100,000
COST PER SERVICING			
Injectors	\$\$\$	\$3,200	negl.
Minor	\$\$\$	\$10,000	\$10,000
Top End	\$\$\$	\$60,000	\$90,000
Bottom End	\$\$\$	\$290,000	\$290,000
SERVICING THROUGH 1ST REBUILD			
Injectors	# of Cycles	50	N/A
Minor (excl. of injectors)	# of Cycles	6	13
Top End	# of Cycles	2	4
Bottom End	# of Cycles	1	1
COST THROUGH 1ST REBUILD			
Injectors	\$\$\$	\$160,000	negl.
Minor	\$\$\$	\$60,000 (for 6)	\$130,000 (for 13)
Top End	\$\$\$	\$120,000 (for 2)	\$360,000 (for 4)
Bottom End	\$\$\$	\$290,000	\$290,000
TOTAL THROUGH 1ST REBUILD	\$\$\$	\$630,000	\$789,000
ALLOCATED MAINTENANCE %			
Injectors	%	25.40%	
Minor	%	9.52%	16.67%
Top End	%	19.05%	46.15%
Bottom End	%	46.03%	37.18%
20-YR SERVICE CYCLES			
Injectors	# of Cycles	315	
Minor	# of Cycles	39	20
Top End	# of Cycles	13	7
Bottom End	# of Cycles	6	2
20 YEAR COST (SIX MAJOR REBUILDS)			
Injectors	\$\$\$ / 20 yr	\$1,008,000	
Minor	\$\$\$ / 20 yr	\$390,000	\$200,000
Top End	\$\$\$ / 20 yr	\$780,000	\$630,000
Bottom End	\$\$\$ / 20 yr	<u>\$1,740,000</u>	<u>\$580,000</u>
TOTAL MAINTENANCE COST (20 yr)		\$3,918,000	\$1,410,000
TOTAL MAINTENANCE COST (per kWh)		\$0.0052	\$0.0019

III. STATIONARY POWER MARKETS TO BE SERVED

A. SELECTION OF APPLICATIONS AND PLANT CONFIGURATIONS

In previous reports we reviewed a full range of stationary and marine engine applications and analyzed the potential suitability of coal fueled engines for each application. Of all the applications studied to date, there are three which appear very suitable for the coal fueled diesel system:

- Independent power generating plants, or "IPPs" (5-50 MW)
- Capacity addition for municipal utilities (10-50 MW)
- Industrial cogeneration plants (2-50 MW)

These applications typically involve multiple engines at a single plant where requirements are favorable for coal firing: high annual utilization, existing infrastructure, space for coal handling and emission controls, and constant load operation.

Trends in U.S. power requirements over the next 20 years or so appear to be highly favorable for the early adoption of these coal-fired diesel applications. The coal diesel stationary power plant is being developed at a time when there is an ongoing upheaval in the stationary power industry. This upheaval is in large part driven by the steady growth in U.S. power requirement, which continues to grow at 2.2 to 2.6% per year nationwide, and up to 6% per year in certain regions. For perspective, each extra 0.2% of growth nationwide represents 10,000 MW of new capacity on-line. Another driving force has been the major changes to the infrastructure such as PURPA and the rise of independent power plants (IPPs). Traditional procedures whereby utilities added stationary power capacity in the form of large central-station generators, in increments of 500 to 1300 MW, are gradually giving way to new procedures whereby modular plants are installed in the 50 to 400 MW size range, and many of these are non-utility owned generators (IPPs). At the present time, the fuels of choice for these modular plants are natural gas and oil, due to two factors:

- Gas and oil are currently priced at attractive levels (\$2 to \$4 per million Btu)
- There is no competitive coal-fueled modular power technology available with low emissions yet, particularly in the 2 to 50 MW range. Circulating fluid bed coal plants are now competitive but are somewhat larger in size and not as efficient as diesel plants would be.

However, these two factors may change by the late 1990s to early 2000, which is the period when the coal diesel will be in position to gain rapid market acceptance. This Topical Report provides a preliminary design of a competitive clean coal modular diesel power plant, with low emissions, suitable for 2 to 50 MW plant sizes, which is moving along the path to field demonstration in the mid-1990's. Continuing R&D efforts have resulted in steady progress toward demonstration of the prototype engine and emission control system on clean coal water slurry. As for gas and oil prices, many energy forecasts are including the scenario of a sawtooth climb of oil and gas prices to over \$30 per barrel (as a sustained price) during the 1990's. According to

our projections, when the industrial price of diesel fuel reaches about \$0.79/gallon (\$5.50/MMBtu), the coal-fueled diesel plant can offer a competitive cost of electricity. The current gas "bubble" in the U.S. is expected to be used up by the mid to late 1990's because of shrinking domestic gas production and increased gas demand. GRI forecasts (1988) show U.S. gas usage growing at a slow pace (0.5% through 2000 and 0.3% from 2000 to 2010), conventional gas supply declining, LNG and gas pipeline imports increasing, and gas prices increasing faster than coal prices (4.5% vs. 1.7% in real terms). These observations and scenarios leave a window of opportunity for clean coal slurry in the late 1990's and beyond, provided it can be produced at a delivered price of \$3 to \$3.50 per million Btu (current dollars).

As noted above, the coal diesel power plant is intended to serve three classes of applications:

- (a) IPPs: The coal diesel could capture an increasing portion of the non-utility modular power market now served by gas and oil fueled 5-50 MW engines (gas turbine and reciprocating engines).
- (b) Utility Incremental Added Power: The coal diesel could be considered by smaller utilities as an attractive alternative to other power plant types for adding up to 50 MW smaller increments of capacity (such as the circulating fluidized bed boiler or gas-fueled turbine). The coal diesel is generally considered to be the only technology with the potential to reach a 45-50% overall electric power efficiency below 50 MW with coal.
- (c) Industrial Cogeneration: Where the heat-to-power ratio requirement is appropriate (say, 1.0 to 1.4), the clean coal diesel could be an attractive alternative as an industrial cogeneration prime mover.

Pipeline compressors, mechanical drive and irrigation engines do not appear attractive for coal diesel because of either engine size, population, or natural gas availability.

Whereas applications (a) and (b) call for straight power generation, application (c) calls for both heat and power. Cogeneration units being built today are designed either to meet the power needs at the host industrial site or intended primarily for sale of power to the grid.

For the purposes of this preliminary design study, five plant configurations were considered, as shown in Table III-1.

These applications typically would be larger than 6 MW, the largest Cooper-Bessemer engine, and thus would involve multiple engines at a single plant. These applications also offer favorable characteristics for coal firing (high annual utilization, existing coal infrastructure, space for coal-handling and emission controls, constant load operation). The number of IPP and small utility plants is expected to expand significantly over the 1995-2010 period, as described in Sections B and C below, and this presents an important opportunity for small clean coal plants to establish viability.

Table III-1
COAL DIESEL PLANT CONFIGURATIONS

Function	Number and Output of Engines	Total Power	Cogen	IPP	Small Utility
Cogen	1 x 1.8 MW (6 cyl LSB)	1.8 MW	o	-	-
Cogen	4 x 1.8 MW (6 cyl LSB)	7.2 MW	o	-	-
Power	2 x 6 MW (20 cyl LSVB)	12 MW	-	o	o
Cogen	2 x 6 MW (20 cyl LSVB)	12 MW	o	o	-
Cogen	4 x 6 MW (20 cyl LSVB)	24 MW	o	o	-

B. COGENERATION PRIME MOVER REQUIREMENTS BY INDUSTRY

Table III-2 shows six industries which are expected to expand their cogeneration capacity. Table III-3 presents one scenario of how the diesel and gas reciprocating engines could fit into these expansion plans. This scenario shows the potential for over 1,500 new engines and 6400 MW of installed diesel capacity in cogeneration, about 55% of which is smaller engines of about 3 MW size. The coal diesel is not expected to be technologically ready to be offered before 1997 to 2000 (except for field demonstration purposes); however, it is targeted for future cogeneration installations after that time, assuming fuel prices are favorable. Therefore, Table III-3 portrays the potential future cogeneration market for the coal diesel, to the extent that comparable industrial cogeneration growth continues into the next two decades (see Section F for further discussion of scenarios).

As will be shown in Section V, a complete emission control package for the coal diesel, including 90% NO_x reduction, is expected to be cost effective only above about 8 MW plant size. If true, this would effectively exclude a large subset of cogeneration opportunities in the 1 to 8 MW size range. However the 520 engines shown in Table III-3 associated with plants 10 MW and up would still be an important market. Furthermore, certain cogeneration plants below 8 MW would be suitable for a lower cost emissions control package.

C. GROWTH IN ELECTRIC POWER CAPACITY - PROJECTED NEED FOR CAPACITY ADDITIONS

Modular electric utility plants are also a very promising application for the coal-fueled diesel. A significant shortfall in electric generating capacity is projected to occur beginning in the mid 1990's, according to our "most probable" scenario of 2.2%/year demand growth. Utilities have not yet announced their plans for new plants to satisfy this shortfall. Recent electric power surveys such as those by Mottley, Mycoff and Gumz⁽¹⁾ and the Energy Information Agency⁽²⁾, without exception point to a challenging time period between 1994 and 2000 when available U.S. generating capacity will start to be strained to meet projected demand. Before going into the detailed numbers, what this means is that there is an unprecedented opportunity (some would call it a likely requirement) for new modular power.

Table III-2
NUMBER OF EXISTING MANUFACTURING PLANTS WITH DIESEL
COGENERATION POTENTIAL

Industry	Cogeneration Plant Size		
	2.0-9.9 MW	10.0-19.9 MW	20.0 MW and Over
Food	450	48	84
Textile	199	9	6
Chemical	157	65	131
Petroleum Refining	39	8	91
Rubber	48	6	3
Metals	107	19	34
Other	<u>40</u>	<u>15</u>	<u>11</u>
Totals	1,040	170	360

Source: Department of Energy, 1984

Table III-3
POTENTIAL DEMAND FOR DIESEL ENGINES FOR COGENERATION IN EXISTING U.S. MANUFACTURING PLANTS

Plant Size	Potential Number of Plants Installing Cogeneration	Potential New Diesel Capacity				
		Assumed Percent Using Diesel ⁽¹⁾	Assumed No. and Size of Diesels per Plant	Number of Diesel Cogen Plants	Number of Engines	Added Capacity
2.0-9.9 MW	1,040	60%	2 x 3 MW	600	1200 @ 3 MW	3,600 MW
10.0-19.9 MW	170	50%	4 x 5 MW	85	340 @ 5 MW	1,700 MW
20.0 MW and over	360	10%	5 x 6 MW	36	180 @ 6 MW	1,100 MW
Totals	1,570	-	-	721	1,720	6400 MW

Source: Department of Energy, Arthur D. Little, Inc., estimates.

⁽¹⁾See Section E and Tables III-7 and III-8.

Of course, there is uncertainty in both the degree and timing of the upcoming potential shortfall, and in the mix of solutions which will actually be implemented, such as:

- Utility capacity additions*
- Independent power plants (IPPs)
- Repowering of utility power plants, including fluidized bed retrofits
- Life extension of existing units
- Imports (mainly from Canada) and more extensive wheeling
- Load management and conservation

Whatever mix eventually materializes, the first two solutions above (noted *) will be important elements, and these are two key potential future markets for the coal diesel power plant. A shortfall in new capacity additions by utilities should create greater demand for cogen and IPP plants, including modular plants under 100 MW. Coal-fueled heat engines, when developed and demonstrated, must compete against gas-fueled modular power and fluidized bed (coal) plants for share of this 4000-6000 MW per year market (see Section E for a discussion of market share).

Growth in gas cost (in \$/million Btu), coupled with lower growth in coal cost, should favor adoption of coal-fired technologies.

The projections for new fossil fueled capacity additions, including both utility and IPPs, are expected to be at a relatively high level in 1991-2010, as shown in Table III-4.

Table III-4
FOSSIL FUELED POWER PLANT ADDITIONS, 1991-2010 FORECAST

Power Plant Type	1991-1995 (MW)	1996-2000 (MW)	2001-2005 (MW)	2006-2010 (MW)
Utility coal steam turbine	7,500	19,000	54,700	73,100
Utility combined cycle (gas, oil, dual fuel)	6,300	30,600	7,600	8,600
Utility combustion turbine and reciprocating I.C. engine	10,800	15,500	7,400	7,600
IPP/Non-utility natural gas (gas turbine, diesel)	4,500	4,800	5,200	5,200
TOTALS	29,100 MW	69,900 MW	74,900 MW	94,500 MW

Source: EIA, Annual Energy Outlook 1990, Jan. 1990.

Note that a total 169,400 MW in projected new fossil-fueled capacity is expected to be installed over the ten year period 2001 to 2010, when the coal diesel will first become available. Of this, 159,000 MW will be required by utilities and another 10,400 MW is forecast for IPP (non-

utility). It should be noted that utilities do not have specific plans for most of the capacity needed after 1995. There is considerable flexibility to select new technologies which become proven.

The coal diesel is designed to compete for the smaller plant sizes in the 10-50 MW range, and will not be available until the late 1990s, except for demonstration. Therefore, the IPP and utility combustion turbine categories for 2001-2010 are the most likely targets for the 10-50 MW coal diesel plants (see shaded region in Table III-4). These two categories total 25,400 MW for this ten-year period. (It should be noted that utilities include stationary diesels in the "Combustion Turbine" category in the EIA and NERC database.) If the coal diesel earned even 10% market share of all size plants over this ten-year period, this would amount to 2540 MW or about 425 engines (over 40 engines per year), assuming 6 MW engine size.

For several reasons, utilities are showing interest in modular capacity expansion. There is an increasing problem in finding suitable sites for large central power plants near urban areas, and the capital requirement for each of these large plants is also a problem. Earlier expectations that nuclear plants would grow to relieve this shortfall are now less certain. Modular plants are easier to find sites for, can be put on-line with relatively short lead time, can follow load swings more efficiently, have a lower first cost per kW installed, and, in the case of large diesels, offer efficiencies of 40-45% vs. 34-37% for modern coal steam electric. Proven availability is 90% for large stationary reciprocating engine generator sets.

D. REGIONS OF GREATEST POTENTIAL

Ten specific regions where IPP capacity additions expected to be greatest are listed in Table III-5. The coal diesel plant is considered to be particularly appropriate to compete for future IPP sites because of the 5-50 MW size range and because of the flexibility exercised in plant design and fuel choice. Note that these ten regions are projected to account for 25,400 MW in new IPP capacity by 1997. Also, another 9164 MW in utility-owned new gas-fired and oil-fired units is forecast for these regions. Assuming these trends persist into the 2000-2010 period, some of these utilities may elect coal diesel (for smaller sub-50 MW plants) when the price of oil and gas increases. The ten regions shown in Table III-5 are the prime target market opportunities for modular power in the 10-200 MW range. Four of these regions in Table III-5 marked ("high") are judged particularly suitable for clean coal modular power (such as the coal diesel design).

These four regions are as follows:

- PA, NJ, MD ("MAAC")
- VA, NC, SC ("SERC-VAC")
- OH, WV, MI, IN, KY ("ECAR")
- FL ("SERC-FL")

Table III-5

REGIONS WITH CAPACITY ADDITIONS AND THEIR POTENTIAL FOR CWS DIESEL PLANTS

Region	States	Forecasted Capacity Additions* 1988-1997		Some Candidate CWS Metro Areas	Potential for 500 MW CWS Diesel Capacity
		IPP (MW)	Utility Gas and Oil (MW)		
WSCC/CNV	California	11,099	960	-	Low
MACC	Pennsylvania, NJ, Maryland	3,513	2,302	Pittsburgh, Philadelphia, Baltimore	High
SERC/VAC	Virginia, Carolinas	3,508	704	DC, Richmond, Raleigh-Durham	High
NPCC/NY	NY	2,459	238	New York	Medium
ECAR	Ohio, WY, Indiana, Kentucky, Michigan	1,510	1,035	Indianapolis, Detroit, Columbus	High
NPCC/ NE POOL	New England	1,452	117	New Haven, Portland, Providence, Boston	Medium
SERC/FL	Florida	902	3,000	Miami, Tampa, Jacksonville	High
SPP/WC	Oklahoma	500	410	Tulsa	Low
WSCC/RMP	Colorado	466	108	Denver	Low
SERC/SOU	Southern (GA, AL, MS)	--	290	Atlanta	Medium
TOTALS		25,409	9,164		

*Source: NERC, July 1989.

In these regions, there is not only a higher projected demand for new installations of modular power, but also a higher fuel price advantage for coal vis-a-vis natural gas. Also, each of these four regions offer several suitable barge terminals for coal delivery. These are also the regions where the actual electricity growth has exceeded utility forecasts by the greatest margins, as shown in Table III-6. What this means is that the utilities in these regions do not have new large central power stations being built to meet their demand growth, and they are most likely to turn instead to IPPs and modular power. These regions are shown on a U.S. map in Figure III-1, with the cross hatched areas representing significant potential for IPPs and modular power.

Note that the regions of greatest potential for the coal diesel essentially form a band about 800 miles wide down the Eastern U.S. If borne out by future trends, this would have a significant impact on the coal diesel commercialization plan and selection of source coals.

It should also be noted that environmental control considerations which evolve in each metropolitan area by 1995-2015 will play an important part in determining suitable regional markets for the coal diesel. That is, fuel choices for modular plants may be driven as much or more by local environmental considerations (and emission control costs) as by fuel cost (once coal slurry is in the competitive range).

FIGURE III-1 REGIONS FOR POTENTIAL COAL DIESEL APPLICATIONS

Table III-6

ACTUAL VS. FORECAST KWH DEMAND GROWTH (1983-1987)

Region	Forecast (%/Yr)	Actual (%/Yr)	Remarks
New England	3.0	4.2	Actively adding capacity
New York	0.6	2.8	Some problems
Mid-Atlantic	1.2	3.8	Actively adding capacity
Virginia-Carolina	3.2	5.2	Actively adding capacity; competitive bidding
Southern	1.8	5.2	Excess capacity
Florida	2.9	5.7	Adding cogen capacity

Source: EIA, 1988.

E. MARKET SHARE FOR COAL DIESEL SYSTEMS - OTHER COMPETING TECHNOLOGIES

The market share for coal diesels in the initial market period can be projected based on current trends in new orders for stationary reciprocating engines vis-a-vis gas turbines. That is, coal diesels would be expected to capture the same share of new stationary engine orders as diesels do now (once coal slurry is competitive with diesel oil and gas¹). It is clear from Table III-7 that diesels and natural-gas spark recips dominate the power market below 2,000 kW engine size (equivalent to plant sizes from 2 MW up to 12 MW, assuming 6 engines maximum per plant). Also, below 15,000 kW (15 to 90 MW plant size), diesels and gas recips currently take 58% of the market in North America.

When oil and gas prices rise in the U.S., diesels, because of their higher efficiency, will capture even greater market share. This can be seen from the current market trends in Western Europe, where gas and oil are more costly than in the U.S. (see Table III-8). Here, diesels command 60% of new engine orders below 15,000 kW engine size (15 to 90 MW plant size).

The data shown in Tables III-7 and III-8 include orders for 3501/5000 kW gas turbines for compression and pumping (including offshore platform) for the oil and gas industry. Such applications are presumably outside the intended future market for coal diesel. Excluding these orders, the current market share of diesel engines for stationary power (under 15 MW) is even greater; approximately 75% in North America and Europe.

¹ Our estimates of the cost-of-electricity (C.O.E.) suggest that clean coal slurry must be delivered to the site at a cost of \$1.00-1.50/mm Btu below gas or oil in order for the C.O.E. to be lower for the coal-fueled diesel than for a diesel with conventional fuel (depending on plant size, location, emission controls, and other factors).

Table III-7

RECENT TRENDS IN STATIONARY ENGINES (NEW ORDERS FOR NORTH AMERICA)
(Three-Year Period, June 86-May 89)

Output Range, kW	Diesel			Gas Turbine		
	Number of Engines	Total Power	% Continuous Duty	Number of Engines	Total Power	% Continuous Duty
1000/2000	384	576 MW	45%	8	12 MW	20%
2001/3500	36	99 MW	75%	65	179 MW	70%
3501/5000	18	77 MW	80%	63	267 MW	85%
5001/7500	13	81 MW	85%	8	50 MW	75%
7501/10000	2	18 MW	90%	14	123 MW	100%
10001/15000	6	75 MW	100%	3	38 MW	100%
TOTALS	459	925 MW (58 %)	-	161	669 MW (42 %)	-

Source: Diesel/Gas Turbine Worldwide, October 1987, 1988, 1989.

The earliest applications of coal diesels will probably be as dual fuel (gas-CWS) stationary reciprocating engines set up for field demonstration in the 1995 to 2000 period. At these early sites, the engines will be run on CWS part of the time (for demonstration) and on natural gas the rest of the year. During this period, relative fuel prices will dictate whether the coal diesel is competitive with the large gas-diesel engines running on natural gas and diesel fuel. In this period, commercial interest will depend upon how rapidly natural gas and oil prices rise and how soon the cost of producing clean CWS as engine fuel can be reduced to the competitive range of \$3.00 to \$3.50/MMBtu.

In the longer term, once high efficiency and reliability have been demonstrated, the coal diesel may become the preferred option for small, low-emission coal-fueled power (below 50MW plant size). In addition to merely displacing oil and gas stationary reciprocating engines, the coal diesel may begin to capture market share from gas turbines, depending on the commercial status of coal-fueled turbines in this size range.

Other advanced coal-power technologies will compete with the direct coal-fired diesel for these future opportunities. These include:

- Conventional steam turbine with fluid-bed coal combustor.
- Closed-cycle air turbine, indirect-fired, with fluid-bed combustor.
- Coal-fueled combined cycle gas turbine systems with pressurized combustor or gasifier, and hot-gas clean-up.

Table III-8
WESTERN EUROPE NEW ORDERS FOR STATIONARY ENGINES
(Three-year period, June 1986 - May 1989)

Size Range (kW)	Diesels		Gas Turbines	
	Number	Total Power	Number	Total Power
1000/2000	485	726 MW	31	47 MW
2001/3500	53	146 MW	12	32 MW
3501/5000	20	85 MW	73	311 MW
5001/7500	5	32 MW	38	238 MW
7501/10000	17	149 MW	9	79 MW
10001/15000	<u>7</u>	<u>88 MW</u>	<u>8</u>	<u>101 MW</u>
TOTALS	587	1226 MW (60%)	171	808 MW (40%)

Source: Diesel/Gas Turbine Worldwide, October 1987, 1988, 1989.

- Coal conversion to methanol or other liquid and gaseous fuels (e.g., "mild-gasification") to be used in conventional diesel and turbine engines.
- Stirling engine, indirectly fired with coal combustor.

The target coal-diesel applications were selected so as to exploit the anticipated competitive advantages of the diesel vis-a-vis these emerging technologies. For example, premium coal-derived fuels ("mild gasification") may be most competitive for smaller engines (below 2000 hp), for high engine RPM, for transportation applications, and for variable load-speed and for stringent emissions requirements. Coal-fueled gas turbines and steam turbines with fluid beds may be more competitive at 30 MW engine size and up (on a large enough scale to justify the hot gas clean-up and/or pressurized gasifier technology).

An in-depth critique of all five coal power technologies is beyond the intent of this section. It suffices to say that all five deserve continued intensive R&D efforts to prepare for future U.S. power requirements, including R&D on improved air pollution controls. Our assessment is that neither the steam turbine nor the two gas turbine options will be able to compete with the diesel below 10 MW unit engine size (say 20-50 MW plant size). Only the coal diesel, the mild-gasification reciprocating engine, and the Stirling engine are likely to be considered below 10 MW engine size. Of these, we assert that the coal diesel is an extremely attractive medium-risk/high reward technology.

F. CAPACITY-GROWTH SCENARIOS FOR MODULAR COAL DIESEL PLANTS

If the technology can be demonstrated, the future of stationary coal diesel plants is potentially bright indeed. The robust capacity growth for diesel cogeneration, small utility, and IPP power

for all fuels is expected to amount to approximately 900-1,200 MW per year during the next twenty years, as illustrated in Table III-9. This kind of engine production activity will revitalize engine production, which is now a mature low-growth industry, and this is expected to occur whether or not the coal diesel technology becomes available to participate in this market. The number of 2 to 6 MW engines produced per year for U.S. installation would grow to about 200-400 units.

Table III-9
SIGNIFICANT POTENTIAL GROWTH IN RECIPROCATING ENGINE POWER
PLANT CAPACITY, ALL FUELS

Potential Additions	1991-1995	1996-2000	2001-2005	2006-2010
Cogeneration ¹	1600 MW	1600 MW	1600 MW	1600 MW
Small Utility and IPP ²	3000 MW	4000 MW	2600 MW	2600 MW
Annual Added Capacity, Reciprocating Engines, All Fuels ³	920 MW/yr	1120 MW/yr	820 MW/yr	840 MW/yr
Planned Coal Diesel Status:	Proof of Concept	Field Demonstration	Commercial	Commercial

¹Based on Table III-3, assumes 25% of plants are converted to cogen in each five-year period.

²Assumes 20% new capacity is recip., not gas turbine.

³Sum of first two rows divided by five years.

Engine installations will be more prevalent in certain regions of the U.S. (see Section D above), where the growth in electricity demand is greatest and the available sites for large plants are dwindling. The coal diesel development effort is being planned so as to achieve a favorable position for the CWS fuel and the Cooper-Bessemer engine technology.

The development of coal diesel market share can be expected to proceed in five stages, as shown in Table III-10.

Table III-10
SCENARIO FOR COAL DIESEL MARKET PENETRATION

Stage	Scenario	Approx. Timeframe	Market Share and Annual Capacity Installed, Stationary Engines Below 15 MW			Number of Coal Diesel Engines Per Year
			Coal Recip	Gas/Oil Recip	Gas/Oil Gas Tur- bine	
1	Field demonstration as natural gas/CWS dual fuel engine	1995-2000	-	60% 600 MW	40% 400 MW	N/A
2	Coal diesel proven as competitive, captures say 1/5 of new orders for stationary recip engines as price of gas and oil begins to rise	2000-2005	10% 100 MW	50% 500 MW	40% 400 MW	~20
3	Gas and oil prices continue to rise; CWS stationary diesel captures half of new orders for stationary recip	2005-2010	30% 300 MW	30% 300 MW	40% 400 MW	~60
4	Gas and oil prices rise further so that clean CWS is now the preferred choice; gas turbines below 15 MW lose market share because of lower efficiency	2010-2015	55% 550 MW	20% 200 MW	25% 250 MW	~110
5	CWS diesel is preferred over gas turbines for CWS use below 15 MW	2015-2020	75% 750 MW	10% 100 MW	15% 150 MW	~150

Basis 1000 MW per year new orders for stationary engines below 15 MW (up to 90 MW plant size). Critical assumptions include (a) coal diesel cost of electricity demonstrated to be competitive, e.g., about 6.5¢/kWh in 1989 dollars (stage 2), (b) gas and oil prices rise 20% in stage 3 vs. stage 2 without concomitant source coal price increase, and (c) average size of CWS-engine assumed to be 4.8 MW (16 cylinder).

IV. COAL PROCESSING AND TRANSPORTATION

A. COAL PROCESSING ANALYSIS METHODS

This section describes the conceptual design and costing of an AMAX coal cleaning and processing plant that will produce engine-grade coal water slurries. This conceptual plant was sized to produce 2.4 million tons of CWS per year (180 tons/hour of clean, dry coal); this amount of slurry is ample to support 500 MW of coal-fired, diesel-engine power capacity.

In the analysis presented below, two coal cleaning plant configurations are described. One configuration will produce an ultra-low ash ($<0.5\%$)* slurry through the use of chemical cleaning. The other will produce a low-ash slurry ($<1.5\%$) by physically cleaning the coal. *Both these products are (potentially) engine-grade fuels.* The Cooper-Bessemer single cylinder research engine has run for more than 80 hours on ultra-low ash coal-fuel. This research engine has also run for a few hours on a 1.2% ash coal-fuel, with wear rates comparable to those of runs with the ultra-low ash coal. A third engine test on a coal with almost 4% ash proved unsuccessful; high wear rates and poor combustion limited the engine run to a few minutes. While a maximum ash level for the fuel has not been definitively set, our engine tests have indicated that 1.5% ash may be a safe upper limit for the engine-grade coal fuel.

The ultra-low ash slurry is prepared by subjecting the coal to physical cleaning, chemical cleaning and fine grinding. The 1.5% ash product is produced through fine grinding and physical cleaning only. A comparison of the two cleaning processes is presented because both fuels are candidates for engine use at this time. Each has advantages and disadvantages. The 1.5% ash slurry is very attractive economically, but its long term effect on engine wear is unknown. The ultra-low ash slurry has been found to be compatible with engine use, but its projected cost is significantly higher, according to current cost analysis.

This conceptual plant consists of a number of unit operation areas (e.g. grinding, physical cleaning, chemical cleaning etc.). The capital and operating costs of each operation area were estimated independently, making it possible to evaluate the cost impact of each coal processing step separately. A process plant cost model, based on the use of automated spread sheets, was developed to facilitate cost comparisons among various plant configurations.

The configuration of the plant (i.e. the sequence and inclusion of unit operation areas) depends on the desired characteristics of the CWS being produced. Because the necessary specifications of engine-grade CWS have not yet been finalized, we have structured our design and costing of the conceptual plant to allow flexibility in the specification of the CWS product. A cost/ benefit analysis of each additional degree of CWS refinement can now be assessed.

*All references to ash content are on a dry coal basis.

It should be noted that the plant design described in this chapter is quite preliminary. The basis of the plant design is the experience that AMAX R&D has gained while operating their 20 ton per day coal cleaning pilot plant and laboratory scale coal cleaning facilities. While these small scale facilities have provided valuable data, this information has to be extrapolated to predict performance of a full scale plant. In addition, only a few source coals have been cleaned and tested with the existing facilities. Because some coals are more cleanable than others, there will be some variability in plant output and efficiency. It must be remembered that the ash and sulfur specifications listed for each plant are targets. For example, future testing may show that the '1.5% ash coal' can be cleaned to 1% ash with a highly cleanable feedstock. Alternatively, with a less cleanable coal, tests may show that the coal process efficiency (Btu recovery) is lower in order to meet a given ash level specification.

Research work is currently being conducted to determine the economic and technical benefits of modifying various process steps. The costs presented in this chapter are a useful starting point for review and comparative purposes. These cost estimates can be expected to change as our understanding of the coal preparation process and the coal-engine requirements is improved.

B. CWS SPECIFICATIONS

The exact specifications of engine-grade CWS characteristics is the topic of ongoing research. These specifications are being developed on the basis of trade-offs between fuel price and engine performance. We have found that small changes in some specifications (e.g., ash content, particle size) can have large impacts on CWS cost. As would be expected, these changes may also have large impacts on engine performance (efficiency, component durability, and emissions system performance).

Some specifications are integrally linked. For instance, with physically cleaned coal the degree of ash removal achieved is tied directly to the degree the coal has been ground. The smaller the coal particle size, the more the ash that can be removed from the coal. For extremely low ash levels, some coals may have to be ground to a 10 micron top size. For ash levels of about 1.5%, the coal may be ground to a 30 micron top size. With chemically cleaned coals, the particle size and the clean-coal ash content are *not* linked. A 0.5% ash coal could have a top particle size of 75 - 100 microns, for example. Of course, if smaller particle sizes are desired, the coal can be ground finer, say to 30 microns, but this particle size reduction would not impact the coal cleaning steps.

The specifications of the two types of slurry that are applicable to a coal fired diesel engine are shown in Table IV-1. The ultra-low ash CWS has a 74 micron top size, and contains less than 0.5% ash and 0.7% sulfur (on a dry coal basis). The higher ash CWS has an ash content of about 1.5% and a sulfur content of less than 1% (dry coal basis). The top particle size will vary with coal type, but typically the top particle size will be between 20 and 44 microns. The higher ash slurry is prepared by physical cleaning; the ultra-low ash CWS is prepared by chemical cleaning. Both slurries are assumed to contain 52% solids and enough additives to maintain stability at viscosities of roughly 200 - 500 centipoise at low shear rates.

Table IV-1
ENGINE-GRADE CWS SPECIFICATIONS

	Ultra-Low Ash CWS	Low Ash CWS
Coal Type	High Volatile Bituminous	High Volatile Bituminous
Ash Content (wt. %, dry coal basis)	<0.5	<1.5
Sulfur Content (wt. %, dry coal basis)	<1.0	<1.0
Top Particle Size (microns)	74	30
Coal Loading (wt.%)	52%	52%
Low Shear Viscosity	200-300 cp	300-500 cp
Stability	Negligible settling after one week storage	Negligible settling after one week storage

Experience at AMAX R&D with their 20 ton/day plant indicates that the ultra-low ash CWS can be manufactured out of a wide range of bituminous coals. The higher ash slurry can be produced by a variety of coals, but some coal seams will not clean to as low an ash content as others. Typical CWS characteristics that AMAX R&D has produced using their pilot plant are shown in Table IV-2.

C. PLANT AND PROCESS DESCRIPTION

The coal cleaning and processing plant will include up to 13 operation areas. Block diagrams of two different plant configurations are shown in Figures IV-1 and IV-2. These configurations are: 1) a fine grinding and physical cleaning plant that will produce a coal product with less than 1.5% ash and a top particle size of about 30 microns; and 2) a chemical cleaning plant that will produce a clean coal with less than 0.5% ash and a top size of 74 microns.

Figure IV-1 shows the plant in a configuration to produce clean coal with less than 1.5% ash. In this configuration, the coal is unloaded, crushed, ground (in two stages: initial and fine grinding), physically cleaned, and formulated into slurry with water and additives.

Figure IV-2 shows a plant configuration that produces an ultra-clean coal water slurry from coal with less than 0.5% ash. In this configuration, three additional steps are included: a caustic leach, an acid leach and a hot water wash. The sequence of cleaning and slurrying is as follows: the coal is unloaded, crushed and initially ground to 74 microns top size. After initial grinding, the coal is physically cleaned. The coal does not have to be finely ground before physical cleaning because the coal will be cleaned to only 2 - 4% ash in this step. The coal is further cleaned in three chemical cleaning steps: caustic leach, acid leach and hot water wash. After chemical cleaning, the coal is formulated into CWS, no additional grinding is necessary.

The refinement in particle size and ash content that occurs as the coal is processed through each of these steps is shown in Tables IV-3 and IV-4.

D. DESCRIPTION OF PROCESS AREAS

Each of the areas in the CWS processing plant are described in some detail below. More detail can be found in Reference 1. For each area, an equipment list and capital cost information is listed in Appendix A. As described above, the sequence of these areas, and the inclusion or exclusion of some areas from the conceptual plant, will depend on the desired CWS specification. Areas 500-700 are included in the ultra-low ash processing plant only.

Area 100 Unloading and Storage

The raw coal will be delivered to the cleaning plant by unit trains with bottom dump capabilities. Area 100 includes a railroad siding (where the train is stored while it is being emptied) and a thaw shed (for unloading in winter). It is assumed that the trains are owned and operated by the rail company. A car scale is on the track to verify coal shipment weights. The coal is held in storage piles until it is used in the plant. The rest of this area includes conveyers, feeders and bulldozers to move the coal. A complete equipment list and estimated equipment costs are shown in Table A1 of Appendix A.

Table IV-2

TYPICAL CHARACTERISTICS OF TWO CWS FUELS PRODUCED BY AMAX

Slurry Characteristics	Ultra Low Ash (<0.5%)	Low-Ash (<1.5%)
Moisture (wt %)	47.2	47.4
Coal Content (wt %)	52	52.0
Additive Content (wt %)	0.8	0.6
Particle size (Microns)		
Top (98% passing)	74	44
Mean (50% passing)	10	8
(10% passing)	2	1
Viscosity (cp) @ 100 - 1000 sec ⁻¹	200	400
Heating Value (Btu/lb, slurry basis)	7,700	7,600
<u>Clean Coal Characteristics</u>		
Coal feedstock	Kentucky Splint	Kentucky Blue Gem
Proximate analysis (wt. % dry basis)		
Ash	0.4	1.5
Volatiles	37.0	34.5
Fixed carbon	62.6	64.0
Sulfur content (wt % dry basis)	0.7	0.5

Source: AMAX

**Figure IV-1. Schematic of AMAX R&D Engine-Grade Coal Cleaning Process
- 1.5% Ash Coal, Physical Cleaning Plant Configuration -**

Figure IV-2. Schematic of AMAX R&D Engine-Grade Coal Cleaning Process
- Ultra-Low Ash Configuration -

Table IV-3

PROCESS PLANT AREAS FOR 1.5% ASH CWS

Area #	Area Description	Typical Coal Top Size	Typical Coal Ash Content
100	Raw Coal Unloading and Storage	2 inches	10% (by wt., dry)
200	Crushing	0.25 inches	10%
300	Initial Grinding	100 microns	10%
800	Fine Grinding	30-70 microns	10%
400	Physical Cleaning	no change	1.5%
900	Slurry Preparation	no change	no change
1000	CWS Storage and Loading	n/a	n/a
1200	Waste Treatment and Disposal	n/a	n/a
1300	Utilities	n/a	n/a

Table IV-4

PROCESS PLANT AREAS FOR 0.5% ASH CWS

Area #	Area Description	Typical Coal Top Size	Typical Coal Ash Content
100	Raw Coal Unloading and Storage	2 inches	10% (by wt., dry)
200	Crushing	0.25 inches	10%
300	Initial Grinding	74 microns	10%
400	Physical Cleaning	no change	2-4%
500-700	Chemical Cleaning	no change	0.50%
900	Slurry Preparation	no change	no change
1000	CWS Storage and Loading	n/a	n/a
1100	Caustic Regeneration	n/a	n/a
1200	Waste Treatment and Disposal	n/a	n/a
1300	Utilities	n/a	n/a

Area 200 Crushing

The two-inch top size coal is moved through Area 100 on a conveyor to a storage bin in Area 200, where the coal will be crushed in a hammer mill to roughly one quarter of an inch in size (less than 6 mesh). The product coal is weighed and conveyed to a storage bin before it is ground. A complete equipment list and estimated equipment costs are shown in Table A2 of Appendix A.

Area 300 Initial Grinding

The coal is ground in this area with rod mills from a top size of six mesh to a top size of about 74 microns. The 74 micron product may contain some tramp oversize which is screened out with a 100 micron screen and fed back to the mill for regrinding. If the plant is configured for physical cleaning only (a coal product with 1.5% ash), the coal will be ground further (in Area 800) prior to physical cleaning. In a processing plant that includes chemical cleaning, the fine grinding is not necessary. The ground coal is stored in a feed tank for feeding to physical cleaning area of the plant.

A complete equipment list and estimated equipment costs for Area 300 is shown in Table A3 of Appendix A.

Area 400 Physical Cleaning

Physical cleaning of the coal can be done either by column flotation or by heavy media separation. AMAX currently utilizes heavy media separation in their pilot plant for CWS preparation. In this process the mineral matter is separated from the coal gravimetrically; denser particles, containing higher percentages of mineral matter sink, while coal particles with less mineral matter float in the heavy media (magnetite) separator.

An alternative physical cleaning method that shows some promise is column flotation. Column flotation utilizes the coal's hydrophobic surface characteristics to separate the coal minerals from the coal maceral. Bubbles of air are introduced to a column of water (and 'other') with ground coal. Particles of coal attach themselves to the air bubbles and are carried to the top of the column. Mineral matter particles sink to the bottom of the column. This process becomes more effective as the coal is ground finer (and therefore more mineral matter is liberated from the coal matrix).

Equipment lists and estimated equipment costs for both the heavy media separation plant and the column flotation system are presented in Tables A4 and A5 of Appendix A.

Area 500 Chemical Cleaning - Caustic Leach and Filtration

Chemical cleaning is required if the coal slurry ash specification is very low (<1.5%) or if the ash level specified cannot be attained by physical cleaning for a particular coal. Area 500, caustic leach and filtrating is the first step of the chemical cleaning process. Caustic leaching is done with a 4% solution of sodium hydroxide (NaOH) for 25 minutes at 230°C. This leaching step removes alumino-silicate materials (clays), quartz, and other metals such as iron, lead, magnesium etc that are bound to the clays. The sodium hydroxide binds strongly with the coal. Acid leaching and/or hot water washing ultimately removes the sodium precipitate from the coal.

An equipment list with estimated costs is shown in Table A6 of Appendix A.

Area 600 Chemical Cleaning - Acid Leach and Filtration

The acid leach step removes basic minerals, such as calcium or sodium compounds. It also helps remove some of the caustic that was introduced in Area 500. The acid leach is done with a 3% solution of HCl for 10 minutes at 80°C. An equipment list and estimated equipment costs for this area are shown in Table A7 of Appendix A.

Area 700 Chemical Cleaning - Hot Water Wash and Filtration

Hot water washing is conducted primarily to remove the NaOH and the HCl introduced in the caustic and acid leaching steps. The wash is conducted at 250°C for 30 minutes. In this step, ammonia is added to adjust the pH of the coal to 7.0. The coal is filtered for a final time and washed with water to remove as many of the undesirable ions as possible. An equipment list with estimated costs are shown below in Table A8 of Appendix A.

Areas 800 and 900 - Fine Grinding and CWS Formulation

If the coal is to be physically cleaned only, it is ground to about 20-44 micron top size in a stirred ball mill in this area. The stirred ball mill has the largest power requirement of any area in the plant.

If the coal is to be chemically cleaned, fine grinding and/or CWS formulation are done together in this area. If a small particle size is desired, water, dispersant and stabilizer are added upstream of the stirred ball mill. Dispersant dosages are about 0.75 lbs of dispersant per 100 lbs of coal. The stabilizer is added at a rate of approximately 0.05 pounds per 100 pounds of coal. Other additives, such as a biocide and an oil antiagglomerant (to make the CWS compatible with DF-2) may also be added in this area.

If the CWS has been physically cleaned only (and has therefore been finely ground prior to cleaning), the CWS is only formulated in this area. Also, if the coal has been chemically cleaned and a top size of 74 microns is acceptable, the CWS is only formulated in this area. Tanks with agitators are used to mix the additives into the CWS.

An equipment list and equipment costs for these areas are shown in Table A9 of Appendix A.

Area 1000 - Storage and Load Out

In this plant design, the CWS is stored in (10) one million gallon agitated tanks until it is loaded into fuel trucks for delivery to the power plant. The necessity of agitators in the holding tanks depends on the CWS formulation; if the slurry is highly stabilized, no agitators will be needed. The tank form is fitted with large load-out pumps to fill train cars for delivery to the customer. The equipment and estimated cost list is shown in Table A10.

Area 1100 - Caustic Recovery and Waste Neutralization

About one third of the total caustic feed to the caustic leach step can be recovered and recycled. NaOH is recovered by adding lime to the caustic filtrate which precipitates the dissolved silica and alumina and frees the NaOH into solution. This process is done at 70°C.

Recovery of HCl from the acid leach step would not be economical. However, the waste stream from the acid leach step will be neutralized by mixing it with the caustic waste stream, making salt water. The equipment needed for these processes is shown in Table A11 of Appendix A.

Area 1200 - Waste Treatment and Disposal

All waste streams from the cleaning and processing plant are treated and disposed of in tailing ponds. These ponds will serve to settle out the solids from the waste streams. The solids settled in these ponds include the mineral matter wastes from physical cleaning and chemical cleaning steps. Cooling water and any other process water will also be disposed of in these ponds. The cost for this area is accounted for in the cost of the land purchase for the plant. The cost of land is currently estimated to be 5 to 10 percent of the cost of the buildings that house the process plant but is sensitive to geographic location and industrial proximity.

Area 1300 - Utilities

A chemical cleaning plant will include a fluidized-bed cogeneration facility that will generate steam and electricity from the high ash wastes of the physical cleaning step. This is a modular facility, completely fabricated and installed by an outside vendor (e.g., Babcock and Wilcox). The FBC is specified to have a 30MW capacity and would generate enough steam for the chemical cleaning steps.

This cogeneration plant is estimated to cost \$48 million dollars and would only be economical in the case of a plant that includes chemical cleaning (and therefore has a steam requirement). A plant without a chemical cleaning steps will purchase power at local rates (assumed to be \$0.04/kWh) from the electricity grid. The plant will have smaller boilers for space and water heating.

Equipment lists and associated costs for this area are shown in Table A12 of Appendix A.

E. CAPITAL COST ESTIMATES

The equipment described in the previous section and the costs listed in Appendix A are, for the most part, bare equipment costs. There are additional capital costs for equipment installation, instrumentation, piping, electrical work, and paint and insulation. These additional plant costs are calculated on the basis of plant factors. These factors are taken from AMAX R&D experience with similar plants and were cross checked with the current literature on process plant costs. These cost factors are consistent with cost factor ranges used in general chemical engineering practice for process plants (Reference 2).

The factors used in the capital cost estimates are listed below. (Note: these cost factors are not applied to modular equipment that is delivered and installed as a package, such as the cogeneration plant.)

Capital Cost Factors (Expressed in Terms of % of Bare Equipment Cost)

Installation	24.8%
Instrumentation	25.5%
Piping	75.9%
Electrical	33.5%
Paint and Insulation	6.6%

In addition, there are costs associated with construction of buildings, purchase of land, site development, and rail and road facilities. Buildings and land cost is related to the square footage and height of the building installed. The type of structure is assumed to be a prefabricated steel building for basic protection from the elements. Cost includes labor, materials, and supplies for construction. Costs for plumbing, heating, lighting, ventilation and other services are part of this factor. The cost as a function of purchased equipment ranges from 45 to 70% in the literature. Land cost is estimated to be 5 to 10% of fixed equipment cost.

The total of these costs plus installed equipment costs constitutes the total field cost of the plant. This subtotal capital cost is subjected to additional engineering and construction fees. These cost factors are tabulated below.

Engineering and Construction Cost Factors (Expressed in Terms of % of Total Field Cost)

Engineering and Fees	13.8%
Indirect Costs	18.3%

Finally, there are cost factors applied to the final construction costs. These cost factors are listed below.

Working Capital Cost Factors
(Expressed in Terms of % of Total Construction Cost)

Contingency	20%
Working Capital	10%

The work-up of the capital costs of a 2.4 million ton per year CWS processing plant are shown in Table IV-5. Two possible plant configurations to make engine grade CWS are shown: Option 1, a physically cleaned coal with a top size of 30 microns, and Option 2, a chemically cleaned CWS with a top size of 74 microns. The capital cost of the physical cleaning plant is estimated to be \$135 million. The capital cost of the chemical cleaning plant is estimated to be \$287 million. Assuming a 12-year amortization period at 10% interest (a capital cost factor of 0.15), these capital costs correspond to annual operating costs of \$0.55/mmBtu and \$1.18/mmBtu, respectively.

Table IV-5
CAPITAL COSTS FOR CWS PROCESSING PLANT
 (Costs in \$1,000)

Capital Cost Item	CWS Specification Option (% ash in coal and top particle size, microns)			
	Option 1		Option 2	
	1.5% ash, 30um		0.5% ash, 74 um	
Delivered Equipment Cost (by Area)	Costs in Thousands (\$1,000)		Costs in Thousands (\$1,000)	
Unloading and Storage	\$1,333		\$1,333	
Crushing	\$389		\$ 389	
Initial grinding	\$2,019		\$2,019	
Physical Cleaning	\$1,325		\$1,325	
Chemical Cleaning				
Caustic Leach	\$0		\$11,242	
Acid Leach	\$0		\$6,322	
Hot Water Wash	\$0		\$8,312	
Fine Grinding	\$9062		\$0	
CWS Preparation	\$358		\$358	
Storage and Load Out	\$3,644		\$3,644	
Caustic Regeneration	\$0		\$2,917	
Waste Treatment	\$704		\$704	
Utilities	\$1,641		\$48,335	
A. Subtotal Equipment Cost		\$23,921		\$86,899
B. Installation Costs	\$39,781		\$64,132	
C. Building, Land, Rail and Roads	\$13,594		\$13,594	
D. Subtotal Field Costs (A+B+C+D)		\$77,296		\$164,625
E. Engineering, Fees and Indirect	\$24,812		\$52,845	
F. Subtotal Construction Cost		\$102,108		\$217,470
G. Contingency	\$20,421		\$43,494	
H. Total Capital Costs		\$122,529		\$260,964
I. Working Capital	\$12,253		\$26,096	
J. Final Total Capital Costs		\$134,782		\$287,060

F. OPERATING COST ESTIMATES

Operating costs of the coal cleaning and processing plant include labor, power, chemical reagents, and maintenance materials. (Raw coal costs and coal transportation are not included in the plant operating costs. Coal and transportation costs are detailed in the next section.) For either the highly or less refined CWS, the cost of reagents dominates the operating costs. These chemical reagents are used in slurry formulation and coal cleaning. In this section the costs associated with each operating cost component are discussed in turn. The processing and operating cost factors used to calculate plant operating costs are shown in Table IV-6.

Table IV-6
Processing and Operating Cost Factors for CWS Plant

Processing Factors	Operating Cost Factors
75% = Coal recovery factor (dry basis)	0.35 = \$/(ton of dry coal) for rod mill maintenance
52% = Coal loading	1.90 = \$/(Ton of Dry Coal) for stirred ball mill maintenance
	0.03 = Capital multiplier for maintenance other than mills
	2080 = Hr of work/yr @ standard wages
	0.04 = \$/kWh electricity purchased

Labor

Table IV-7 summarizes the estimated labor requirements for the conceptual coal cleaning and processing plant. The total labor cost for a physical cleaning plant producing a 'less refined' CWS product amounts to \$0.09/MMBtu of CWS produced at the plant. For a chemical cleaning plant with fine grinding, this labor cost increases to \$0.15/MMBtu. In general, labor costs are roughly 10% of the plant operating costs.

Power

Power usage and costs are summarized in Table IV-8. The plant area that uses the most power is fine grinding. In a physical cleaning plant, fine grinding constitutes 80% of the electrical energy usage of the plant. In a chemical cleaning plant, significant electricity users are the caustic leach area (22% of kWhrs used) and initial grinding (22% of kWhrs used).

In the case of the chemical cleaning plant there is also a large steam requirement. It is therefore assumed that an on site cogeneration facility will produce the power and steam required for the plant. This cogeneration plant is designed to be a 30MW fluidized bed boiler that burns coal refuse from the physical cleaning step. Total costs to run this cogeneration plant are estimated to be \$0.06/MMBtu of CWS produced (excluding labor, accounted for with the other labor costs). This cost does not include the amortized capital cost of the cogeneration facility.

Table IV-7. LABOR REQUIREMENTS

Area Description	Job Category	Total Labor Requirement (Number)		Wage	Yearly Cost (\$)	
		Physical Cleaning Plant	Chemical Cleaning Plant		Physical Cleaning Plant	Chemical Cleaning Plant
100 Unloading and Storage	Operators	4	4	\$17/hr	141,440	141,440
200 Crushing	Operators	4	4	\$17/hr	141,440	141,440
300 Initial Grinding	Operators	4	4	\$17/hr	141,440	141,440
400 Physical Cleaning	Operators	4	4	\$17/hr	141,400	141,440
500 Caustic Leach	Operators	-	8	\$17/hr	-	282,880
600 Acid Leach	Operators	-	4	\$17/hr	-	141,440
700 Hot Water Wash	Operators	-	8	\$17/hr	-	282,880
800 Fine Grinding	Operators	4	-	\$17/hr	141,440	-
900 CWS Preparation	Operators	-	4	\$17/hr	-	141,440
1000 Storage and Load Out	Operators	4	4	\$17/hr	141,440	141,440
1100 Caustic Regeneration	Operators	-	4	\$17/hr	-	141,440
1200 Waste Treatment	Operators	4	4	\$17/hr	141,440	141,440
1300 Utilities	Operators	4	36*	\$17/hr	141,440	1,273,960
General Plant	Shift Foreman	4	4	\$20/hr	166,400	166,400
General Plant	Mechanical Foreman	1	1	\$20/hr	41,600	41,600
General Plant	Mechanics	20	20	\$17/hr	707,200	707,200
General Plant	Electricians	12	12	\$17/hr	424,320	424,320
General Plant	Laboratory Technicians	5	5	\$15/hr	156,000	156,000
General Plant	Plant Manager	1	1	\$6,750/mo	81,000	81,000
General Plant	Plant Engineer	1	1	\$5,625/mo	67,500	67,500
General Plant	Process Engineer	2	2	\$5,200/mo	124,800	124,800
General Plant	Personnel Administrator	1	1	\$5,062/mo	60,744	60,744
General Plant	Safety/Environmental Officer	1	1	\$3,600/mo	43,200	43,200
General Plant	Purchasing Clerk	1	1	\$2,947/mo	35,364	35,364
General Plant	Warehouseman	1	1	\$2,947/mo	35,364	35,364
General Plant	Secretaries	2	2	\$2,947/mo	70,728	70,728
Total		84	145		\$3,145,740	\$5,126,900
				Cost per mm Btu of CWS:		0.15 \$/MMBtu

*Includes labor in cogeneration plant.

Table IV-8
POWER USAGE BY AREA

Area	Equipment	Installed Hp	Power Usage Per Year (kWh/yr)*	
			Physical Cleaning	Chemical Cleaning
Unloading and Storage	Scales, sampler, conveyor, feeder	60	250,000	250,000
Crushing	Feeders, screens, hammermill, conveyors, scale	190	794,000	794,000
Grinding	Feeders, Rodmill, Slurry sump	1,705	7,123,000	7,123,000
Physical Cleaning	Pumps, conveyors	260	1,086,000	1,086,000
Chemical Cleaning				
Caustic Leach	Agitators, pumps, conveyors	1,746	0	7,294,000
Acid Leach	Pumps, agitators, conveyors	291	0	1,216,000
Hot Water Wash	Pumps, agitators, conveyors	1,187	0	4,959,000
Final Grinding and Formulation	Stirred ball mill, pumps, sumps	16,403	68,525,000	0
Storage	Pumps	950	3,969,000	3,969,000
Chemical Regeneration	Feeders, agitators, pumps	975	0	4,073,000
	Total	23,767	82,747,000	30,764,000
	Total Cost in \$/mmBtu		\$0.09**	\$0.06***

*Assumes 80% capacity and 90% on stream usage (7884 hrs./year)

**Assumes \$0.04 /kWh electricity cost

***Assumes electricity supplied by on-site cogeneration plant

Power usage for the physical cleaning plant is more than for the chemical cleaning plant. Total electrical energy used in the physical cleaning plant is estimated to be about 80 million kWhrs/year. This energy usage corresponds to a cost of \$0.09/MMBtu of CWS produced. It is assumed that the electricity for this plant is purchased from the local grid, given the reduced steam usage as compared to the chemical cleaning plant.

Chemical Reagents

The costs of additives used to formulate the slurries are projected to cost \$0.41/MMBtu of CWS produced. This cost is independent of the degree of cleaning of the coal. The additive usage will vary slightly with coal grind.

The cost of reagents for the chemical cleaning steps are \$1.08/MMBtu. This includes caustic (assuming 30% is recycled), acid (assuming no recycle) ammonia (to balance the pH), lime and modifier for the caustic recovery. The cost of reagents for the physical cleaning plant are projected to be \$0.02/MMBtu. This cost includes frother and collector for the flotation column. A tabulation of the amounts and costs of chemicals used in the slurry plant are shown in Table IV-9.

Maintenance

Maintenance costs are estimated to be 3% of the capital cost of the plant plus the cost of mill liners and media for the grinding mills. For the finely ground coal, mill maintenance is projected to cost \$0.08/MMBtu. For coal with a 74 micron top size, the mill maintenance is projected to cost \$0.01/MMBtu.

Other

Additional operating costs are \$0.01/MMBtu for process and cooling water.

Total Operating Costs

A tabulation of the operating costs for the two CWS plant configurations is shown in Table IV-10. It can be seen that the cost of operating a chemical cleaning plant (@ \$1.93/MMBtu), even without fine grinding, is twice that of a physical cleaning plant (@ \$0.81/MMBtu). The added cost for the chemical cleaning plant is primarily in the cost of the reagents required for the caustic and acid leach steps of the cleaning process. For both plants, the cost breakdown is roughly: 10% labor; 5 - 10% utilities; 50 - 70% reagents and chemicals; and 10 - 20% maintenance.

Table IV-9
CHEMICAL REAGENT/ADDITIVE COSTS

	Unit Cost	Physical Cleaning Plant	Chemical Cleaning Plant
<u>Cleaning Reagents</u>		<u>\$/mm Btu CWS</u>	<u>\$/mm Btu CWS</u>
Collector	\$0.10/lb	<0.01	--
Frother	\$0.50/lb	0.02	--
Caustic	\$285/ton	--	0.56
Acid	\$155/ton	--	0.43
Ammonia	\$210/ton	--	0.06
Lime	\$40/ton	--	0.02
Modifier	\$90/ton	--	0.01
Subtotal		\$0.02	\$1.08
<u>CWS Additives</u>			
Dispersant	\$0.557/lb	0.30	0.30
Stabilizer	\$3.25/lb	0.09	0.09
Formaldehyde	\$0.25/lb	0.02	0.02
Subtotal		\$0.41	\$0.41
Total		\$0.43	\$1.49

Table IV-10
OPERATING COST SUMMARY FOR CWS PLANT

Item	Physical Cleaning Plant \$/MM Btu (HHV)	Chemical Cleaning Plant \$/MM Btu (HHV)
Labor		
Operation & Supervision, 17 & 20 \$/HR	0.04	0.06
Maintenance & Supervision, 17 & 20 \$/HR	0.04	0.04
Analytical	<0.01	<0.01
Other Assignable Labor	0.01	0.01
Cogeneration Plant Labor, 17 & 20 \$/HR	--	<u>0.03</u>
Subtotal	0.09	0.14
Utilities		
Electricity and Steam	0.09*	0.06**
Process and Cooling Water, 0.25 \$/1,000 gal	<u>0.01</u>	<u>0.01</u>
Subtotal	0.10	0.07
Reagents		
Caustic 285 \$/ton	--	0.56
Acid 155 \$/ton	--	0.43
Ammonia 210 \$/ton	--	0.06
Dispersant 0.557 \$/lb	0.30	0.30
Stabilize 3.25 \$/lb	0.09	0.09
Formaldehyde 0.25 \$/lb	0.02	0.02
Lime 40 \$/ton	--	0.02
Modifier 90 \$/ton	--	0.01
Collector 0.10 \$/lb	<0.01	--
Frother 0.50 \$/lb	<u>0.02</u>	<u>--</u>
Subtotal	0.43	1.49
Maintenance Materials		
Mill Liners and Media	0.08	0.01
General Maintenance 3% of Capital (excluding grinding equip.)	<u>0.11</u>	<u>0.22</u>
Subtotal	0.19	.23
Total Operating Cost	\$0.81	\$1.93

*Power purchased from main grid.

**Power and steam generated in cogeneration plant.

G. FEEDSTOCK AND TRANSPORTATION

Feedstocks

Table IV-11 lists a number of coal feedstocks that were used in the CWS costing estimates. The coals listed in this table fall under one of two sets of selection criteria. The first set of criteria is that the coals be highly cleanable so that it would be feasible to physically clean these coals to 1.5% ash and less than 1% sulfur. Two coals listed fall into this category: The Kentucky Blue Gem and the Kentucky Elkhorn. These coals have large mineral matter inclusions which are relatively easy to separate from the coal material. They also have low organic sulfur content. Appendix D gives detailed analyses of Elkhorn, Splint, and Hazard coals, before and after cleaning.

The second set of selection criteria is that the coals be inexpensive and local to the slurry plant (and the coal diesel engine plants). For the conceptual plant analysis, 6 - 8 sites were selected as hypothetical plant locations: Boston, Pittsburgh, Atlanta, Chicago, Phoenix and Salt Lake City.

Coals were selected on the basis of cost and close proximity to these locations. These coals may be inexpensive at minemouth but they must undergo more extensive cleaning to be processed into engine grade slurry. All these coals have low organic sulfur contents.

Transportation

Estimated shipping costs between coal seam location and slurry plant location are shown in Table IV-12. Costs are based on quotations obtained by AMAX from railroads and barges assuming large shipping orders and long-term contracts.

H. CWS COST SUMMARY

Table IV-13 summarizes the capital, operating and process cost assumptions used to calculate CWS cleaning and slurrying costs. All of these factors and/or assumptions have been described previously in this section; they are listed here again in summary form for convenience. A summary of CWS production costs are presented in Tables IV-14 and IV-15. These tables include annualized capital costs (based on a 10% cost of capital and 12-year recovery term), operation and maintenance costs, coal costs and transportation costs for two different CWS plant scenarios. The first scenario (Table IV-14) is a physical cleaning plant in Pittsburgh utilizing Kentucky Blue Gem coal. The second scenario (Table IV-15) is a chemical cleaning plant in Chicago utilizing Illinois #5 coal. These cost summaries are examples. Costs will vary with location, coal source, CWS specification, etc.

The summary tables show that the physically cleaned, finely ground coal slurry is expected to cost \$2.98/MMBtu (including coal, transportation, O&M, and capital costs). The chemically cleaned coal is expected to cost \$4.73/MMBtu.

Table IV-11

COAL PROPERTIES BY SOURCE (AS RECEIVED BASIS)

State	Seam	Moisture	Volatile Matter	Carbon (Fixed)	Ash	Total Sulfur	Organic Sulfur	Pyritic Sulfur	Btu/Lb (HHV)	Cost/Ton (Raw Coal)
Illinois	Illinois #5	8.00%	36.00%	48.00%	8.00%	1.00%	0.70%	0.30%	13,500	\$20.00
Illinois	Illinois #6	10.00%	38.00%	37.00%	10.00%	1.50%	1.00%	0.50%	13,500	\$25.00
Kentucky	Splint	4.00%	31.00%	47.00%	18.00%	0.50%	0.40%	0.10%	12,100	\$27.50
Kentucky*	Blue Gem	6.00%	38.00%	54.00%	2.00%	1.00%	0.30%	0.70%	14,000	\$30.00
Kentucky*	Elkhorn	2.00%	37.00%	58.00%	3.00%	0.70%	0.60%	0.10%	14,700	\$27.50
Kentucky	Hazard #4	1.00%	35.00%	59.00%	6.00%	0.85%	0.74%	0.10%	14,200	\$27.50
W. Virginia	Pittsburgh	6.00%	37.00%	53.00%	8.00%	2.00%	1.45%	0.55%	14,700	\$25.00
Utah	Castlegate	7.00%	39.00%	45.00%	9.00%	0.40%	0.40%	0.00%	12,500	\$20.00

Note: CWS properties and costs are based on AMAX profile data.

*Indicates coal can be physically cleaned to less than 1.5% ash by conventional methods.

Table IV-12
COAL TRANSPORTATION COST ESTIMATES

Market Area/ Coal Source	Coal	\$/ton Coal	\$/MMBtu (AMAX)
Pittsburgh/Knox Kentucky	Blue Gem	\$4/ton via barge	\$0.15
Pittsburgh/Perry Kentucky	Hazard	\$3/ton via barge	\$0.11
Pittsburgh/Marshal W. VA.	Pittsburgh	\$2/ton via barge	\$0.77
Boston/Knox Kentucky	Blue Gem	\$28/ton via rail	\$1.04
Boston/Hazard Kentucky	Hazard #4	\$24/ton via rail	\$0.89
Boston/Marshall W. VA.	Pittsburgh	\$17/ton via rail	\$0.63
Atlanta/Knox Kentucky	Blue Gem	\$7/ton via rail	\$0.26
Atlanta/Hazard Kentucky	Hazard #4	\$8/ton via rail	\$0.30
Atlanta/Marshal W. VA.	Pittsburgh	\$16/ton via rail	\$0.59
Chicago/Knox Kentucky	Blue Gem	\$10/ton via rail	\$0.37
Chicago/Hazard Kentucky	Hazard #4	\$11/ton via rail	\$0.41
Chicago/Marshal W. VA.	Pittsburgh	\$10/ton via rail	\$0.37
Chicago/Sullivan Illinois	Illinois #6	\$7/ton via rail	\$0.26
Salt Lake/Knox Kentucky	Illinois #5	\$23/ton via rail	\$0.85
Salt Lake/Carbon Utah	Castlegate	\$3/ton via rail	\$0.11
Phoenix/Knox Kentucky	Illinois #5	\$28/ton via rail	\$1.04
Phoenix/Carbon Utah	Castlegate	\$4/ton via rail	\$0.15

Table IV-13
COSTING ASSUMPTIONS

General = 7884 hr/yr equipment operation

Capital Cost Factors:

24.8%	=	Capital Installation Factor
25.5%	=	Capital Instrumentation Factor
75.9%	=	Capital Piping Factor
33.5%	=	Capital Electrical Factor
6.6%	=	Paint and Insulation Factor
13.8%	=	Capital Engineering and Fees Factor
18.3%	=	Capital Indirect Cost Factor
20.0%	=	Capital Contingency Factor
10.0%	=	Working Capital Factor

Processing Factors:

75%	=	Coal Recovery Factor (dry basis)
52%	=	Coal Loading

Operating Cost Factors:

0.35	=	\$(Ton of Dry Coal) for Rod Mill Maintenance
1.90	=	\$(Ton of Dry Coal) for Stirred Ball Maintenance
0.03	=	Capital Multiplier for Maintenance Other than Mills
2080	=	Hr/Yr Each Employee Works
0.04	=	\$/kWh Electricity Cost

Indirect Cost Factors:

0.027	=	Capital Multiplier for Taxes, Insurance, Supplies and Overhead
0.03	=	\$/Ton General Administration and Sales Cost
0.15	=	Capital Cost Factor

Table IV-14

CWS PLANT COST SUMMARY - PHYSICAL CLEANING PLANT

GENERAL ASSUMPTIONS

Plant Type	Physical cleaning/fine grinding
Plant Location	Pittsburgh
Plant Capacity	
(tons/year of clean coal)	1.25 million
(MMBtu/year of CWS)	36.5 million
Coal Type	Kentucky Blue Gem (High volatile bituminous)
CWS Specifications:	
Top coal size (micron)	30
% ash (wt%, dry basis)	1.5
% sulfur (wt%, dry basis)	1.6
CWS by heating value (Btu/lb)	7,600

<i>Item</i>	<i>Cost Summary Basis/Unit Cost</i>	<i>\$/MMBtu HHV</i>
A. Purchased coal used in slurry	\$30/ton raw coal	\$1.03
B. Unrecovered coal (25%)		0.34
C. Freight to CWS plant		0.15
D. Operation and maintenance (labor, utilities, reagents, maintenance)		0.81
E. Indirect costs (taxes, insurance, sup- plies, G&A)	2.7% of capital	0.10
F. Annualized capital	0.15 capital cost factor; \$135 million	0.55
	TOTAL	\$2.98

Table IV-15

CWS PLANT COST SUMMARY - CHEMICAL CLEANING PLANT

GENERAL ASSUMPTIONS

Plant Type	Chemical cleaning
Plant Location	Chicago
Plant Capacity	
(tons/year of clean coal)	1.25 million
(MMBtu/year of CWS)	36.5 million
Coal Type	Illinois #6
CWS Specifications:	
Top coal size (micron)	74
% ash (wt%, dry basis)	0.5
% sulfur (wt%, dry basis)	0.5
CWS by heating value (Btu/lb)	7,700

<i>Item</i>	<i>Cost Summary Basis/Unit Cost</i>	<i>\$/MMBtu HHV</i>
A. Purchased coal used in slurry	\$25/ton raw coal	\$0.85
B. Unrecovered coal (25%)		0.29
C. Freight to CWS plant		0.26
D. Operation and maintenance (labor, utilities, reagents, maintenance)		1.93
E. Indirect costs (taxes, insurance, sup- plies, G&A)	2.7% of capital	0.21
F. Annualized capital	0.15 capital cost factor; \$287 million	1.18
	TOTAL	\$4.73

I. COST ANALYSIS UNCERTAINTIES AND R&D DIRECTIONS

As noted at the beginning of this chapter, the plant design and costing described in the sections above is quite preliminary. There are uncertainties due to lack of experience with a full size plant and lack of experience with a number of coal feedstocks. In addition, a number of design decisions were not based on a comprehensive review of available technology, for instance grinding method. In this section, the uncertainties in our capital and operating cost estimates are outlined.

Grinding Costs

We have assumed that a stirred ball mill will be used to finely grind the coal. There are alternative methods that have not yet been completely evaluated, such as dry grinding or fluid energy milling. If alternative methods prove to provide overall cost reductions, the design of the fine grinding area would be modified. A change of design in this area would only serve to *reduce* the overall grinding costs since a least cost selection would ultimately be made.

One aspect of grinding that is uncertain is the maintenance cost of the ball mills. Estimates varying from \$2 to \$32/ton of coal processed for media and liner replacement have been quoted by people involved with ball mill designs. (References 3,4) The estimates presented in this chapter are on the low end of the spectrum, at \$2.00 per ton of coal processed. An increase in the cost of mill maintenance by 500% (to \$10/ton processed) would increase the cost of clean CWS by \$0.32/mmBtu.

Physical Cleaning

The costs of the flotation column for physical cleaning the coal are based on AMAX R&D experience with a 40 pound per day, laboratory scale column. The efficiency of the process (i.e. the Btu Recovery) is expected to vary widely with different coals. While the selection of appropriate coals will help to ensure that the plant maintains a high efficiency, it is possible that efficiencies will, at times, drop below estimated values.

In addition to performance, the costs of a full size column are uncertain. These costs are uncertain because they are based on the scale-up of a small facility. The design will undoubtedly become more complicated, and costly, as the process develops. A 50% increase in the cost of a physical cleaning step would increase the cost of CWS by about \$0.25/MMBtu.

Chemical Cleaning

The uncertainties in the cost of chemical cleaning step primarily from scaling issues. In addition, there is some uncertainty as to whether heat recovery potential exists which may reduce steam and utility needs.

Additive Package

Costs may go down as new formulations or mixing methods are developed. Also, depending on the storage and handling facilities of the engine plants, stabilizer may or may not be needed to be added to the slurry. The elimination of the stabilizer would *reduce* costs by about \$0.09/MMBtu.

One additive that is currently used in laboratory scale engine testing which is *not* included in CWS cost estimates is an oil-antiagglomerant. This additive is used currently because of the frequent transitions between diesel and CWS operation in the research engine. Such transitions would be infrequent during actual, full scale operation of a CWS-fired engine. The oil-antiagglomerant is also used currently because oil is used in the injector to lubricate moving parts that contact CWS. The necessity of using the oil-antiagglomerant to prevent clogging of the CWS in the engine is not certain. The cost of this additive corresponds to about \$0.39/MMBtu.

Waste Disposal/Caustic Regeneration

Uncertainties in the cost of waste disposal are due to uncertainties in the cost of land in the various target areas and uncertainties in the cost and availability of waste disposal sites, such as landfills. Some states may have more stringent regulations on solids disposal than others. We currently envision the use of a settling pond to separate solids from water. This separation is essential in order to conserve the water usage of the plant and in order to dispose of ash wastes as a solid instead of a liquid effluent. The size of these ponds has not been incorporated into the cost of the land required for the plant site. This issue needs to be clarified.

It is being assumed that 30% of the caustic used in the first chemical cleaning step can be regenerated. This number is fairly 'soft' and needs to be solidified by testing.

Utilities

The current cost estimates assume the need for a cogeneration facility for a chemical cleaning plant. Without a fine grinding step in the chemical cleaning plant, however, there is probably not enough power consumption to justify the large capital cost of a FBC cogeneration plant. Substituting the cost of a cogen plant with conventional steam boilers (and the purchase of electricity from the grid) could reduce utility cost estimates by \$0.20.

A summary of the cost uncertainties is presented in Table IV-16. The cost impact of each uncertainty is listed as the *approximate impact of a 50% cost change*. This shows the relative importance of each process in question to the total cost of CWS. *It must be kept in mind as more is learned and these uncertainties become resolved, the result may be either more or less than the 50% cost change indicated.*

J. COST MODELING RUNS

Cost information developed by AMAX R&D for the production of coal-water slurry has been converted into automated spreadsheets for use on personal computers. The automated spreadsheet format allows the user to evaluate the impact of various process options, coal feedstock characteristics, fuel characteristics, plant location sites, and plant sizes on the fuel cost. These spreadsheets constitute a process model that is very useful in the analysis and comparison of clean coal costs. The model flexibility reduces the time and labor required to determine the fuel costs and provides a basis to compare fuels manufactured by different processes.

Table IV-16
CWS COSTING UNCERTAINTIES

Potential Impact on CWS Cost	Item	Uncertain Factor	Approximate Impact of 50% Cost Change
Decrease	Coal Cost	• If plant run by coal company the profit would be on CWS only, not raw coal also.	\$0.25/MMBtu
Increase or Decrease	Grinding Methods	• Optimum grinding method not selected yet: dry grinding? Ball mill?	Under \$.10/MMBtu
Increase	Mill Maintenance	• Media replacement rates uncertain.	Under \$.10/MMBtu
Increase	Physical Cleaning	• Efficiency of froth flotation is not certain. • Cost of full-sized F.F. column not certain.	Under \$.25/MMBtu
Decrease	Chemical Cleaning	• Utility needs uncertain/heat recover potential uncertain.	\$.12/MMBtu
Decrease	Formulation of Additive Package	• Costs may go down as new formulations or mixing methods are developed.	\$.20/MMBtu
Increase	Caustic Regeneration	• Cost of chemicals, best process is being investigated.	\$.12/MMBtu
Increase	Waste Disposal	• Depends on location of coal cleaning facility. Some states may have more stringent regulations on solids disposal.	\$.01/MMBtu
Decrease	Cost of Power	• Cogeneration only appropriate in certain geographic sites and with both chemical cleaning and fine grinding together.	\$.15/MMBtu

The model requires input of specific information in order to complete the various cost calculations. The required information includes coal characteristics, plant flowsheet definition, plant size, and market location. Based upon these inputs, certain unit operations are selected for processing the coal. A total of 13 different unit operations are available for inclusion in the cost. Equipment size and cost is also a function of the required inputs. Output from the model includes a capital cost summary sheet and an operating cost summary sheet which provide a detailed breakdown of each cost and provide scenario background data.

A description of the unit operation area has been presented previously. Details of the equipment used in these areas is presented in Appendix A. Details of the model configuration, the spreadsheets used and the necessary inputs are presented in Appendix B. The results of runs made with this model are discussed below.

Cost Model Case Evaluations

Cost summaries were prepared using the automated spreadsheet model for the targeted market locations shown in Figure IV-3. A cost look-up table was prepared from the case runs to compare the sensitivity of plant location, plant size, fuel quality, and feedstock selection. A plant capital cost and operating cost summary sheet was prepared for each scenario. Sample summary sheets can be found in Appendix C.

The effect of "fuel quality" was evaluated by comparing the costs to produce three different slurries, each differing by their degree of beneficiation. The specifications of these three fuels are shown in Table IV-17. A minimally refined fuel is assumed to have 3% ash, 2% sulfur and a top particle size of 100 microns. A nominally refined slurry has an ash level of 1%, a sulfur content of 1%, and a top particle size of 74 microns. The highly refined CWS has less than 0.5% ash, less than 0.5% sulfur, and a top particle size less than 30 microns.

For the purposes of this comparative study, it was assumed that the minimally and nominally refined slurry were both physically cleaned while the highly refined slurry was chemically cleaned. *It must be noted that there are limited number of coals that can be physically cleaned to less than 1% ash with a top size of 74 microns. Most coals would have to be ground much finer to clean them to these levels with high energy recovery.* This scenario of varying degrees of CWS refinement was useful, however, for making cost comparisons.

K. COST LOOK-UP TABLE AND IMPACT OF VARIABLES

Results from the model runs are presented in Table IV-18, the CWS Cost Look-Up table. The following sections discuss the significance of the effects of three key variables:

- Plant size
- Fuel quality
- Plant location

Table IV-18, the CWS Cost Look-Up table, is set up to compare the results of the different case runs based upon the variable of interest. The following variables were analyzed:

FIGURE IV-3. MARKET LOCATIONS

Table IV-17

ASSUMPTIONS FOR CWS SPECIFICATIONS USED IN COST MODELING RUNS

CWS Quality	Minimally Refined	(Base Case) Nominally Refined	Highly Refined
Top particle size	100 microns	74	30
Ash content	3%	1%	0.5%
Sulfur content	2%	1%	0.5%
Viscosity (cp)	800	400	100
Potential coal feed-stocks	Lower grade coals, local to cleaning plant and CWS engine	High quality Kentucky coals (e.g., Blue Gem, Taggart, or Elkhorn seams)	Virtually any coal
Cleaning methods used	Physical cleaning	Physical cleaning	Chemical cleaning/ fine grinding

Table IV-18

CWS COST LOOK-UP TABLE

Parameter Studied	Market Location	Plant Size (Mt/yr)	Ash Content (wt%)	Particle Top Size (micron)	Capital Cost M \$	Plant Operating Cost ⁽¹⁾ \$/MMBtu	Coal Cost \$/MMBtu	Transportation Cost \$/MMBtu	Total CWS Cost \$/MMBtu
Plant Size	Pittsburgh	0.4	1.0	74	43.0	0.82	1.23	0.15	2.41
	Pittsburgh	1.25	1.0	74	78.4	0.56	1.23	0.15	2.32
	Pittsburgh	2.50	1.0	74	123.2	0.50	1.23	0.15	2.18
	Pittsburgh	3.50	1.0	74	146.8	0.47	1.23	0.15	2.11
Fuel Quality	Pittsburgh	1.25	1.0	74	78.4	0.56	1.23	0.15	2.32
	Pittsburgh	1.25	0.5	30	323.2	1.76	1.05	0.11	4.49
	Pittsburgh	1.25	3.0	100	78.4	0.54	1.00	0.07	1.99
	Atlanta	1.25	1.0	74	78.4	0.57	1.23	0.26	2.44
Location	Boston	1.25	1.0	74	78.4	0.57	1.23	1.04	3.22
	Chicago	1.25	1.0	74	80.8	0.56	1.23	0.37	2.55
	Phoenix	1.25	1.0	74	78.4	0.56	1.23	1.04	3.22
	Pittsburgh	1.25	1.0	74	78.4	0.56	1.23	0.15	2.33
	Salt Lake	1.25	1.0	74	80.8	0.55	1.23	0.85	3.04
	Atlanta	1.25	0.5	30	323.7	1.77	1.05	0.30	4.69
Fuel Quality and Location	Boston	1.25	0.5	30	323.7	1.77	1.05	0.89	5.28
	Chicago	1.25	0.5	30	323.7	1.94	0.87	0.41	4.79
	Phoenix	1.25	0.5	30	244.7	2.12	0.86	0.11	4.27
	Pittsburgh	1.25	0.5	30	323.2	1.76	1.05	0.11	4.49
	Salt Lake	1.25	0.5	30	244.7	2.12	0.86	0.11	4.27

*Includes coal, plant operation and maintenance, amortized capital, transportation and other indirect costs.

1. Plant Size

The base case is a 1.25 million ton per year (dry coal in the product slurry) plant. The plant site is near the Pittsburgh area and uses Blue gem seam coal from Kentucky. The coal is cleaned to 1.0% ash via column flotation and crushed to a top size of 74 micron in a rod mill. The comparative cases are for plants producing between 0.4 to 3.5 million tons per year of coal in the slurry.

Cost adjustments were made to the capital cost by factoring the cost of the equipment using the 0.6 tenths power rule or using step functions where more precise data were available. Certain site direct costs such as buildings and site improvements were adjusted on an individual case basis. Cost adjustments in the operating costs are based upon a unit of coal. Labor costs were adjusted on an individual case basis.

Plant operating costs increased as the plant size decreased, as expected. The economies of scale, however, were more apparent at the lower end of the range evaluated. The operating cost decreased from \$0.82 to \$0.56 when the plant size tripled from 0.4 Mt/yr to 1.25 Mt/yr. The operating costs decreased only 9 cents/MMBtu when the plant size was nearly tripled from 1.25 Mt/yr to 3.5 Mt/yr. The reduction in operating cost in the first plant size increase was a result of labor costs (21 cents/MMBtu) and utilities (4 cents/MMBtu) which are more efficiently utilized in a larger operation. After the plant reaches the 1.25 million ton per year size, the labor and utility costs are only 17 cents/MMBtu of the total operating cost. Savings in these areas will no longer show any significant improvement in the total operating cost.

The capital recovery cost for the plant also decreases (per unit of fuel produced) with increasing plant size. The annualized plant cost decreases from \$0.38/MMBtu for the 1.25 million T/yr plant to \$0.30/MMBtu and \$0.26/MMBtu for the 2.5 million T/yr and 3.5 million T/yr plant, respectively.

2. Fuel Quality

The base case scenario for fuel quality is shown in Table IV-19 along with the comparison scenarios:

Coal feedstock	Blue Gem Seam (Base) Kentucky 4A Seam (Low) Pittsburgh #8 Seam (High)
Plant Capacity	1.25 Mt/yr
Plant Location	Pittsburgh

(Feedstock analyses for the coals used in the model evaluations are presented in Appendix D.)

The greatest impacts to both the capital and operating costs were a result of utilizing chemical cleaning to reduce the ash content below 0.5%. The chemical cleaning circuit increased the Total Plant Capital Cost from \$78 million for the base case to \$324 million. The total CWS cost increased from \$2.32/MMBtu to \$4.49/MMBtu.

Table IV-19
FUEL QUALITY SCENARIOS

Fuel Quality	Ash Content (wt%) ¹	Sulfur Content (wt%) ¹	Particle Size (micron)	Viscosity (cp @ 100 sec ⁻¹)
Base Case	1.0	1.0	74	400
High	0.5	0.5	30	100
Low	3.0	2.0	100	800

¹Dry coal basis

Other assumptions standard for all scenarios were as follows:

The extra capital cost and operating cost is a result of chemical cleaning equipment and reagents required for processing, additional fine grinding equipment, and cogeneration installation. This equipment includes autoclaves, filters, heat exchangers, pumps, stirred ball mills, and a cogeneration plant to provide steam and electrical power. The increase in capital cost can be broken down as follows:

Chemical Cleaning	34%
Fine Grinding	11%
Cogeneration	55%

Cogeneration was used in all chemical cleaning scenarios except in the western cities where very low cost gas is available, making cogeneration less attractive.

Additional chemical cleaning costs include operating costs associated with chemical reagents, power costs, and extra labor.

Reducing the fuel quality further, as in the case shown for Pittsburgh scenario with 3% ash in the coal, reduces the cost from \$2.32/MMBtu to \$1.99/MMBtu, nearly 15%. The savings are realized by using a lower quality fuel, increasing recovery, and reducing grinding costs.

3. Plant Location

The trade-off between coal costs and transportation costs is the critical issue for plant location. Inexpensive local coals may reduce feedstock costs but may need to be chemically cleaned for sufficient beneficiation. Specialty coals that could be physically cleaned to adequate ash levels may be associated with high transportation costs. The most important comparison here is the use of western versus eastern coals for CWS plants located in the western part of the country. It was found, in fact, to be less expensive to ship a Kentucky coal to Salt Lake city based physical cleaning plant than to use a western coal in a chemical cleaning plant. (Few western coals can be physically cleaned to less than 1% ash.) The trade-offs for this analysis are shown in Table IV-20.

Table IV-20

COMPARISON OF COSTS FOR EASTERN VS. WESTERN COALS IN WESTERN COAL PLANT

Plant Location:	Salt Lake City, Utah
CWS Specifications:	
Top particle size	74 microns
Ash content	1%
Sulfur content	1%

<u>Coal Cleaning Method</u>	<u>Chemical</u>	<u>Physical</u>
Coal Used:	Utah Castlegate	Kentucky Blue Gem
Coal Cost:	\$0.86	\$1.37
Mine to Plant Transportation Cost	\$0.11	\$0.85
Plant Operating Cost	\$2.22	\$0.55
Indirect Costs		
G&A	\$0.21	\$0.10
Capital recovery	<u>\$1.01</u>	<u>\$0.33</u>
TOTAL	\$4.41	\$3.20

V. EMISSION CONTROL SYSTEM DESIGN

A. INTRODUCTION AND EMISSION TARGETS

The development of a low-cost emission control system for the coal-fueled diesel engine is necessary for its commercial success in small power generation systems. Because the coal-fueled diesel engine is a new technology, no emission limits have yet been imposed. Regulations are currently applied to all new coal-fired stationary sources larger than 250 MMBtu/hr fuel input, and we expect that regulations in some form will be extended to all new small coal-fired stationary power sources in the near future. When this occurs, the coal-fueled diesel system must be competitive with other technologies for power generation in terms of exhaust emissions. Competing technologies for power generation in the range below 100 MW_e include coal-fueled fluidized bed steam plants, as well as internal combustion engines and gas turbines designed to burn gas or oil. Coal-fired gas turbine plants below 100 MW_e are currently under development and may compete in the same timeframe as the Cooper Bessemer coal diesel.

Technical and economic criteria govern the design of an emission control system for the coal-fueled diesel engine. To be competitive, the coal-fueled diesel engine must be as environmentally sound as the other combustion technology alternatives. The current EPA New Source Performance Standards (NSPS) for coal-fired utility boilers can be met by the conventional combustion technologies, and for the purposes of this study, we have elected to design the emission control system to meet these standards. The current NSPS for the major pollutants, NO_x, SO₂, and particulate matter, are given in Table V-1. To reduce the major pollutants in the engine exhaust to meet the NSPS, one can choose among many technologies. However, pollution control technologies must meet two further criteria, one economic and the other technical. The cost of the emission control system has a powerful influence on the commercial feasibility of the coal-fueled diesel system. Both the capital and operating cost of the coal-fueled diesel system must be on par with that of other combustion sources. Technically, the control technologies chosen must be compatible with one another (for system integration) and must be compatible with the coal-fueled diesel engine operation.

The goal of this conceptual design study is to provide quantitative guidelines for selecting the emission control system for the coal-fueled diesel engine. For each of the three major pollutants, control technologies are identified that meet the preliminary technical and economic criteria discussed above. From these various technologies a number of integrated emission control system options are chosen for further study. The system options represent a spectrum of both anticipated cost and probability of technical success. We go on to formulate quantitative means to assess the cost and the probability of technical success for the system options. This allows intercomparison of the candidate options and prioritization of experimental work for the R&D program (Task 2 of Phase I).

Table V-1

NEW SOURCE PERFORMANCE STANDARDS FOR STATIONARY SOURCES

Pollutant	Required Emission Level Coal-Fired Utility Boilers (over 250 MMBtu/hr-input)	Proposed Levels for Small Industrial Boilers (30-75 MMBtu/hr-input)
NO _x	0.6 lb/MMBtu (150 ppm at 15% O ₂)*	1.0 lb/MMBtu
SO ₂	1.2 lb/MMBtu and 90% reduction, or 70% reduction if less than 0.6 lb/MMBtu is achieved	1.2 lb/MMBtu
Particulate	0.03 lb/MMBtu	0.05 lb/MMBtu

*The sum of NO plus NO₂ is converted from measured concentration to lb/MMBtu by using the molecular weight of NO₂ (as if all NO were converted to NO₂)

B. EMISSION CONTROL TECHNOLOGIES FOR PRELIMINARY CONCEPTUAL DESIGN

1. Engine Operating Parameters

Since the cost of the emission control system depends on the size of the overall system, several system sizes in the range of 2 to 50 MW power output have been chosen for study. The engine systems have been selected by Cooper-Bessemer as representative of future commercial opportunities. The engine (or engines) are assumed to be the LSB 6 or LSVB 20 design. These engines have a 15.5 inch bore and a 22 inch stroke. Table V-2 details the engine operating parameters that are independent of engine size such as the speed, compression ratio, and brake-specific fuel consumption. Also included in Table V-2 are the properties of the coal-water slurry and the expected emissions of the major pollutants. The NO_x emission is based on tests results from the JS-1 engine.⁽¹⁾ The SO_2 emission is calculated from a sulfur mass balance, assuming that all the fuel sulfur is converted to SO_2 . The particulate emission is calculated from the ash content of the coal and from an assumed burnout of 98 percent which is representative of JS-1 engine results.

Table V-2 presents the anticipated reduction required to meet NSPS for the three major pollutants. The SO_2 reduction required may be less than the 70 percent shown if a credit is allowed for the sulfur removed from the coal during the production of the coal-water slurry.

The cost of emission control equipment relative to the power output of the system (e.g., the cost per kilowatt of electricity generated) decreases as the size of system increases. In general, the relationship between cost and system capacity is not linear. Therefore, the cost calculations are performed for five systems that span the range of interest for small stationary engines. Table V-3 details the size-dependent operating parameters for the five systems of interest. Each system consists of one or more engine (either LSB 6 or LSVB 20 engine). Systems 1, 2, 3, and 5, labeled as cogeneration systems, include a waste heat boiler which makes 125 psig steam for process applications from the exhaust gas. System 4, a power generation system, does not have a waste heat boiler. In this configuration, no heat recovery from the exhaust gas takes place and a water quench unit is employed to reduce gas temperatures as required by pollution control equipment.

Currently, diesel-fueled stationary engines are not equipped with the kind of emission control technology that we have assumed will be needed to meet NSPS with the coal-fueled engine. The emission control devices will have to be integrated with the engine system components. A general schematic of the integrated system is illustrated in Figure V-1. Only one engine is shown; in this study, we have made the preliminary decision that emission control equipment downstream of the turbocharger will be common to all engines in the system, i.e., exhaust gases from all engines are combined after the turbocharger. Approximate temperatures are indicated in the figure, although the exact temperature will depend on the optimum temperature required for the individual emission control subsystems and on the engine exhaust conditions.

2. Selection Of Emission Control Technologies

The available technology for reducing exhaust gas pollutant levels has rarely been applied to small stationary engines. Most of the experience in removing the major pollutants comes from larger applications such as utility boilers. The emissions from the coal-fueled diesel engine are more closely similar to those from coal-fired utility boilers than to those from stationary engines

Table
V-2

ASSUMED ENGINE OPERATING CONDITIONS

Coal Properties

Ultimate Analysis: 81.2% C
5.53% H
10.07% O
1.83% N
0.91% S
0.38%
Ash

Lower Heating Value: 13,736 Btu/lb
Coal-Water Slurry Composition: 53 wt% coal (preliminary spec.)

Engine Operating Parameters

Compression Ratio: 10.8
BMEP: 200 psi
Power: 419 hp/cylinder
BSFC: 6300 Btu/hp-hr
Speed: 400 rpm

Combustion Conditions

Manifold Air Temperature: 250°F (preliminary)
Exhaust Gas Temperature: 880°F
Stoichiometry: 231% Theoretical Air

Pollutant Levels

	Expected Concentration: (preliminary)		lb/MMBtu	Assumed Reduction Required
	ppm	mg/l		
NO _x	900		2.8	79%
SO ₂	305		1.3	70% ⁽²⁾
Solids ⁽¹⁾		1.05	1.5	98%
Notes:				
(1) At 98% burnout				
(2) Reduction may be less than this if a credit for sulfur removal during production of coal-water slurry is allowed				

Table V-3
SYSTEMS FOR COAL-FUELED DIESEL OPERATION

Engine →	1 LSB 6	2 LSB 6	3 LSVB 20	4 LSVB 20	5 LSVB 20
Application	Co-gen	Co-gen	Co-gen	Power	Co-Gen
Number of Engines	1	4	2	2	4
Net Power Output (MW _e)	1.8	7.2	12	12	24
Total Horsepower	2,516	10,064	16,772	16,772	33,544
Coal Flow (lb/hr)	1,154	4,616	7,692	7,692	15,384
Heat Input (MMBtu/hr)	15.86	63.44	105.66	105.66	211.32
Exhaust Gas Flow (scfm) Single Engine	6,979	6,979	23,260	23,260	23,260
Total (all engines)	6,979	27,916	46,520	46,520	93,040
Exhaust Gas Flow (klb/hr) Single Engine	30.9	30.9	103.0	103.0	103.0
Total (all engines)	30.9	123.7	206.1	206.1	412.2
Emissions (lb/hr) SO ₂ (0.9% S in coal, 1.3 lb/MMBtu)	21	84	140	140	280
NO _x , as NO ₂ (900 ppm or 2.8 lb/MMBtu)	45	178	297	297	594
Solids (0.4% ash and 98% burnout)	27	110	183	183	365

A-9661

Figure V-1. Integration of Emission Control Subsystems with Engine Systems

fueled by natural gas and diesel fuel. The NO_x level from a coal-fueled diesel engine is much less than that from an existing engine burning natural gas or diesel fuel. However, the emissions of SO_2 and solids are greater than those of existing engines. Thus, the candidate technologies for removing the major pollutants are drawn from the experience in utility boilers and industrial process gases. Table V-4 summarizes the emission control technologies considered in this design study.

In this section, the individual emission control technologies are discussed. Appendix I contains process diagrams of each technology as applied to the coal-fueled diesel engine. The reader may wish to consult the appendix for further information on each technology.

2.1 NO_x Control Technologies

The most cost-effective means for NO_x control is to modify the engine combustion process through staged combustion, prechambers or other means. Although this will be attempted, the target of 85% NO_x reduction points to the probable need for exhaust gas NO_x treatment. The removal of NO_x from exhaust gas streams can be accomplished in two ways: reduction to N_2 or absorption. The former route is most commonly used on a commercial scale. In one class of processes, termed selective reduction, a nitrogen-containing compound (typically ammonia) is added to the exhaust gas stream where it reacts with the oxides of nitrogen to form N_2 . Depending on whether or not a catalyst is employed, the process is called either Selective Non-catalytic Reduction (SNR) or Selective Catalytic Reduction (SCR).

The SNR process occurs in a narrow temperature window, from about 1600 to 2000°F.⁽²⁾ This process has been applied on a commercial scale to utility boilers⁽³⁾ where the upper portion of the furnace provides the correct temperature range, and ammonia is utilized (Exxon "Denox" process). Recently, the minimum temperature for SNR has been lowered to about 1350°F by replacing ammonia with cyanuric acid in the presence of a large amount of CO .⁽⁴⁾ Under low CO conditions, the reaction window is still 1600 to 2000°F. This process will certainly be more expensive than ammonia injection due to the cost of the cyanuric acid. The maximum temperature expected in the coal-fueled diesel exhaust gas is 880°F (see Table V-2). The SNR process is not considered as a feasible NO_x removal technology for the coal-fueled diesel engine because the exhaust gas temperature is too low.

The SCR process employs a catalyst to lower the temperature window of the reduction process. SCR has been applied to boilers and process heaters in Japan and in Europe. There is extensive experience in Japan with the application of SCR to coal-fired boilers. Commercialization of SCR in the United States lags behind Japan and Europe, mainly because of the high cost and technical problems with coal ash found in the United States. Recently, tougher standards for NO_x reduction, especially in California, have dramatically increased the experience with SCR in the United States.

In commercial applications of SCR, the catalyst is typically a metal such as platinum or vanadium placed on a metal or ceramic substrate which is arranged as parallel plates or in a honeycomb. The process temperature range is 600 to 750°F and ammonia is used as an additive. The molar ratio of ammonia to NO_x is approximately unity. The amount of ammonia injected depends on the inlet NO_x concentration, the desired NO_x reduction, and the allowable ammonia

Table V-4

EMISSION CONTROL SUBSYSTEMS

NO_x Control

- Reburning
- SCR: Commercially available unit
- SCR: Ammonia injection over engine particulate catalyst at 450°F in baghouse
- SCR: Ammonia injection over CuO catalyst at 750°F in granular bed reactor (Shell/UOP) process
- Adsorption on engine particulate bed at 275°F in baghouse

Joint NO_x-SO₂ Control

- Ammonia injection over carbon catalyst at 450°F in reactor (Takeda process)

SO₂ Control

- Commercially available spray dryer
- Low Temperature (150 to 300°F) Sorbent Injection
- High Temperature (900 to 1000°F) Sorbent Injection
- Calcium Fuel Additive

Particle Control

- Baghouse
- Cyclone
- Granular Bed Filter
- Ceramic Cross Flow Filter

Auxiliary Equipment

- Induced Draft Fan
- Waste Heat Boiler: Differential Cost Relative to Diesel-fueled Baseline Case

slip (the amount of unreacted ammonia that exits the reactor). NO_x removal efficiencies of up to 90 percent can be obtained with SCR. The major operational problems with SCR are degradation of catalyst performance, ammonia slip, and ammonium sulfate formation. In application of SCR to conventional diesel engines, fouling of the catalyst by the diesel soot has been severe.⁽⁵⁾ However, the particulate emissions of the coal-fueled engine are different in character from those of a diesel-fueled engine. The experience in coal-fired boilers with SCR is more applicable to the coal-fueled engine. In coal-fired utility boilers, erosion of the catalyst support necessitates replacing the catalyst every one to five years and catalyst replacement cost is the major component of SCR operating costs. The main advantage to using the SCR process described above for the coal-fueled diesel engine is that the process is available commercially and has demonstrated the required NO_x reduction. Cost is the primary disadvantage; both capital and operating costs are expected to be relatively high.

In order to assess whether the NO_x reduction requirements of the emission control system can be met with a less expensive SCR process, two alternative technologies are considered. The first alternate SCR process involves using the carbon-containing particulate matter from the engine exhaust as a catalyst. The second involves a copper oxide catalyst supported on alumina pellets which incorporates a novel means for removing particles.

Recently, the catalytic activity of coke and carbon-containing particulate matter from utility boilers has been demonstrated on a laboratory scale^(6,7). Using coke activated with sulfuric acid, a 70 percent reduction of NO by ammonia at 300°F has been demonstrated.⁽⁶⁾ Particulate matter from industrial boilers containing 2 percent to 30 percent carbon by weight has been used as a catalyst for reduction of NO with ammonia.⁽⁷⁾ In the temperature range 570 to 750°F, NO reductions from 40 to 60 percent have been demonstrated. Because of the low ash content of the processed coal used in the engine, the particulate matter contains a very large amount of carbon. The carbon content of the ash is calculated to be 80 percent at 98 percent burnout and 67 percent at 99 percent burnout, based on a mass balance using 0.5 percent as the ash content. Thus, it may be possible to exploit the ash as a reduction catalyst. This process has not been applied on an industrial scale and is expected to have a low probability of technical success. However, the cost is very low, providing the impetus for choosing this technology for further study.

Universal Oil Products (UOP) has developed a process (based on the Shell CuO process) for removal of NO_x alone or for removal of NO_x and SO_2 .⁽⁸⁾ The reduction catalyst is CuO supported on alumina. In the presence of SO_2 , the CuO is converted to CuSO_4 which acts as a catalyst for NO_x reduction by ammonia. NO_x removal efficiencies of 90 percent or greater have been demonstrated on both oil and coal-fired utility boilers. SO_2 can be removed simultaneously if the catalyst is regenerated periodically using hydrogen and steam. The simultaneous NO_x - SO_2 process will not be considered here because of the cost and complexity of the regeneration step and the sulfur recovery plant.

Without simultaneous SO_2 removal, the Shell/UOP process is similar in cost to the commercial SCR processes discussed previously. However, if the catalyst is supported on alumina pellets, the pellets can be used as a filter medium for particulates. The technology for hot gas filtration has been developed for application to coal-fired gas turbines.^(9,10) In the granular bed filter process, a bed of alumina pellets removes particles from the gas stream. The filter media are continuously

withdrawn from the filtration vessel, cleaned, and returned to the vessel. The granular bed filtration process has been demonstrated on a pilot scale. Combination of the Shell/UOP process with granular bed filtration is relatively expensive, but will remove two of the three major pollutants in the exhaust gas stream and thus obviate the need for additional particle removal equipment.

A third kind of reduction process is called reburning. In this process, no chemical additives are used; instead, the exhaust gas passes through a secondary combustion zone. In typical applications the secondary fuel is natural gas and accounts for 10 to 20 percent of the total heat input to the system. The mixing rate of the exhaust gas and secondary fuel is designed to be slow enough so that fuel-rich regions are created. When NO_x in the fuel-lean gas diffuses into the fuel-rich zones, hydrocarbon radicals react with NO to produce nitrogen-containing species such as HCN and NH_3 which subsequently react with NO to form N_2 . Reburning has not been applied to reduce NO_x in diesel engines, but the process has been used extensively on combined-cycle gas turbine systems where NO_x reductions of up to 50 percent have been demonstrated.⁽¹¹⁾ The diesel operating conditions are different from those in boilers and furnaces in two important regards: the oxygen content of the exhaust gas is higher and the temperature is lower. These differences need to be explored on a laboratory scale to determine if reburning can be applied successfully to the coal-fueled diesel engine. It has been shown that under process conditions of high excess air for application to industrial process heaters⁽¹²⁾ reductions of up to 50 percent in NO_x can be achieved.

Reburning has several advantages that provide the impetus for further study in the coal-fueled engine application. First, the capital cost should be relatively low compared to other candidate NO_x removal technologies. The operating cost will consist solely of the cost of the secondary fuel. Second, the reburning process will increase the gas temperature and some of the added heat will be recovered in the waste heat boiler. The higher temperatures will increase the overall thermal efficiency of the process. Finally, the secondary combustion process will reduce the particulate loading in the exhaust gas through partial combustion of the carbon-containing particles in the engine exhaust gas.

In addition to chemical reduction, there are other methods for removing NO_x from exhaust gases. In the temperature range of 275 to 300°F, NO_x is adsorbed by activated carbon, as used in the Foster Wheeler-Bergbau-Forschung process.⁽⁸⁾ This process is not judged to be economical for systems below 50 MW. However, the carbon-containing particulate matter from the coal-fueled diesel exhaust might have the capability for removing NO_x via adsorption. Feasibility must be demonstrated under the engine exhaust operating conditions. The cost of such a system would be inconsequential. Even if adsorption does not produce the required NO_x reduction by itself, it could be combined with another NO_x reduction technique.

2.2 Joint NO_x - SO_2 Control Technologies

Many techniques have been proposed to simultaneously remove NO_x and SO_2 . As mentioned above, most of these are not suitable for small engine systems because they involve expensive regeneration and recovery plants which are not economical on a small scale. We consider one combined removal method which has a relatively inexpensive sulfur removal step. The Takeda process⁽⁸⁾ uses an activated carbon catalyst for reduction of NO_x with ammonia at 450°F and absorption of SO_2 . The NO_x removal efficiency for this process is 90 percent and that for SO_2 is

80 percent. The catalyst regeneration is accomplished by washing with water. The water is then mixed with lime and the resulting CaSO_4 is thrown away. This process has the advantage of removing two of the three major pollutants and has been demonstrated on a pilot scale in Japan. Major disadvantage are the cost and complexity of the process.

2.3 SO_2 Control Technologies

The most common method for the removal of SO_2 from exhaust gas streams is absorption. The techniques investigated as part of this study involve absorption of SO_2 followed by chemical reaction with an alkaline material. Large flue gas desulfurization systems that are used in applications such as power plants usually employ wet limestone scrubbers. Dry scrubbers or spray dryers are also commercially available and are cheaper than wet scrubbers, particularly on the scale of engine-based systems. However, the capital cost for spray dryers is high: \$150 to \$200/kW for large boiler systems. The cost per kilowatt will be substantially higher for the small systems in this study. Thus, spray dryers are commercially available, but the high cost provides incentive for examining alternate SO_2 removal techniques.

Direct injection of a sorbent material into a duct or into the furnace itself reduces the capital cost of SO_2 removal systems dramatically. The chemistry remains the same: a calcium or sodium compound (carbonate, hydroxide, or oxide) reacts with SO_2 in the gas to form a sulfate. A baghouse collects the spent sorbent, which may be recycled or thrown away. Sorbent injection has been demonstrated in three temperature regimes which in boilers correspond to one of the following locations, the upper furnace (1600 to 2200°F), the economizer (800 to 1200°F), and downstream of the air preheater (300°F). In the coal-fueled diesel engine, only the last two temperature regimes can be achieved. In the context of the engine, we refer to sorbent injection at either high (800 to 1200°F) or low (250 to 400°F) temperatures. In the former situation, the sorbent is injected upstream of the waste heat boiler. A duct burner may be required to raise the gas temperature to the optimum temperature. For low temperature injection, sorbent is injected upstream of a baghouse.

Both sodium and calcium sorbents have been used for direct injection processes. The former are more likely to be used in regenerable schemes, the latter in throw-away schemes. In this study, only throw-away schemes employing calcium-containing sorbents are considered. Calcium utilization (defined as the amount of calcium converted to CaSO_4) in the range of 35 to 40 percent has been demonstrated from the injection of calcium hydroxide at 800 to 1200°F.⁽¹³⁾ In other words, a molar calcium-to-sulfur ratio of two is required to remove 70 percent of the sulfur at these temperatures. Sodium sorbents give similar results in the high temperature regime⁽¹⁴⁾ and show higher utilizations at the low temperature regime.⁽¹⁵⁾

A slightly different approach to sorbent injection involves adding a calcium compound directly to the fuel. Thus the sorbent contacts SO_2 at the very high temperatures in the cylinder. Organic compounds such as calcium acetate would be readily compatible with the coal-water slurry. The calcium oxide aerosol that forms during combustion would consist of very small particles and might be very efficient at removing SO_2 . This process has not been demonstrated in an engine. The effect of the calcium oxide aerosol on the turbocharger and other engine components is also not known.

2.4 Particulate Control Technologies

For removal of particulates, a baghouse is the control technology of choice. Units are commercially available in the sizes required for the coal-fueled diesel engine with operating temperatures up to 450°F. However, since the baghouse would be located downstream of the turbocharger, a significant question concerns whether the turbocharger can tolerate the larger particles (say 5 to 50 microns) that may be present in the engine exhaust gas. Gas turbines cannot tolerate particles in excess of approximately 5 microns.⁽¹⁶⁾ Even though diesel turbochargers operate under much less severe temperature and density conditions than gas turbines, it is possible that the turbocharger will not be able to withstand particles larger than 5 microns without wear. In this case, a cyclone will be placed between the exhaust manifold and the turbocharger to remove larger particles.

Cyclones do not remove particles efficiently below 1 to 5 microns. However, if the loading of submicron particles is high, the turbocharger may be compromised even with the use of a cyclone. In the event that all particles have to be removed upstream of the turbocharger, a technique will have to be used that removes all particles at a temperature of 880°F. Baghouses are not made to withstand these temperatures, but several technologies are under development for coal-fired gas turbines that may be applicable to the engine system. Neither of the two technologies discussed here are available commercially, but both have undergone extensive testing at higher temperatures and pressures than found in the coal-fueled diesel engine system.

The granular bed filter has been discussed already. In brief, it consists of a moving bed of alumina pellets. The filter media are continuously withdrawn from the filtration vessel, cleaned, and returned to the vessel. The system has been operated successfully at 1600°F over a 1500 hr time period.⁽⁹⁾ An alternative to the granular bed filter is the ceramic cross flow filter.⁽¹⁰⁾ Dirty gas is forced through a porous ceramic material, trapping particles. High pressure air is backflushed through the filter to remove the particles which are subsequently collected. A filter element performed successfully at 1400 to 1450°F for over 250 hr, which included over 1000 cleaning cycles.

C. SELECTION OF INTEGRATED SYSTEM DESIGN OPTIONS

The various technologies for reducing the three major pollutants must be combined into a complete emission control system. Several system configurations were considered. The goal in the selection of system options is to provide emission control system designs that span a range of cost and probability of technical success. Some of the technologies that promise to be low in cost are not available on a commercial scale and thus pose a higher technical risk of development. Figure V-1A shows an example of one of many design configurations that were analyzed.

The probability of technical success of a technology can be derived from the state of its development. We have presented an overview of the individual technologies above. Table V-5 summarizes the progress toward commercialization for each of the candidate control technologies. Technologies that are commercially available for stationary diesel engines are given a probability of one for technical success. For non-commercial technologies, the size of the largest demonstration and its applicability to the coal-fueled diesel operating conditions determines the probability of technical success.

Table V-5

PROBABILITY OF TECHNICAL SUCCESS FOR EMISSION CONTROL TECHNOLOGIES

Subsystem Option	Probability of Success	Unit (20-100 MW)	Demo. (ca. 1 MW)	Pilot Demo	Bench Scale	Lab Demo
NOx Control:						
Reburning	0.75	No	No	Yes ⁽¹⁾	Yes	Yes
NH ₃ Injection in Baghouse at 450°F	0.25	No	No	No	No	Yes
Adsorption of NO _x at 275°F (Baghouse)	0.20	No	No	No	No	Yes
NH ₃ Injection in Granular Bed Filter (Shell/UOP)	0.50	NO	Yes ⁽²⁾	Yes	Yes	Yes
Commercial SCR	0.95	Yes ⁽³⁾	Yes	Yes	Yes	Yes
NOx-SO2 Control:						
NH ₃ Injection at 450°F (Takeda)	0.60	No	No	Yes	Yes	Yes
SO2 Control:						
Lime Injection (300°F)	0.85	No	Yes	Yes	Yes	Yes
Lime Injection (1000°F)	0.50	No	No	Yes	Yes	Yes
Ca Additive in Fuel	0.20	No	No	No	No	Yes
Commercial Spray Dryer	1.0	Yes	Yes	Yes	Yes	Yes
Particle Control:						
Cyclone	1.0	Yes	Yes	Yes	Yes	Yes
Baghouse	1.0	Yes	Yes	Yes	Yes	Yes
Ceramic Filter	0.70	No	No	Yes	Yes	Yes
Granular Bed Filter	0.65	No	No	Yes	Yes	Yes

Notes:

- (1) Not demonstrated under CFD operating conditions
 (2) Not demonstrated with granular bed filter
 (3) Limited work with diesel engines

The expected cost of each technology also affects the selection of integrated emission control system options. Without further information about the degree of particle removal required, it seems prudent to use a cyclone upstream of the turbocharger; in addition, a baghouse will be used at low temperatures (300 to 400°F). As additional information on turbocharger wear becomes available, the decision to use a cyclone may be re-examined.

Table V-6 contains a matrix of NO_x and SO₂ control technologies. Option A represents a combination of two commercially available technologies: SCR for NO_x control and a spray dryer for SO₂ control. Two alternative technologies, direct injection of sorbent and reburning are estimated to be inexpensive and to have a reasonable probability of technical success. They are combined with one another in Options B and C and paired with a commercially available technology in Options K and L. Option M consists of the Takeda process alone since it is a joint NO_x and SO₂ removal technique. Option N combines the spray dryer with NO_x absorption on a carbon bed. Option D combines the Shell/UOP process for NO_x removal with the addition of a calcium additive to the coal-water slurry. Direct injection of lime is also included in Option D in the event that only a limited amount of calcium compound can be added with the fuel. The cost of direct injection will be much less than the cost of the NO_x control unit or the calcium additive. In the economic analysis, the cost of equipment is calculated for each technology and then capital and operating costs are figured for each option. The basis for these calculations is discussed in the next section. Appendix G contains process diagrams corresponding to the system options discussed here.

D. COST ANALYSIS METHODOLOGY AND ASSUMPTIONS

1. Methodology

The method used to arrive at capital costs in this study is based on the methodology recommended by Electric Power Research Institute (EPRI)¹⁷. Appendix H provides the details of each calculation, by option and by system size. The reader may wish to refer to the appendix for an example of the format that is discussed here.

The Total Capital Investment (TCI) is one of the most important results of the economic analysis. The TCI represents the sum of the Total Plant Cost (TPC), royalties (where applicable), pre-production costs, inventory capital, and initial catalyst and chemical charge. The cost of land is not included here as it is in the EPRI Methodology. A royalty allowance equal to 0.5 percent of the process capital is used on proprietary processes. Process capital is defined as the total cost of each unit, including equipment and all installation costs (labor and materials). The pre-production costs consist of the following: one month of fixed operating costs, one month of variable operating costs at full capacity, and 2 percent of TPC. The last charge covers modification to the equipment needed at start-up. The inventory capital is equal to 60 days of variable operating costs, excluding power, steam, process water, and disposal costs. The initial supplies and materials cost accounts for supplies needed for start-up of the unit. In the case of processes requiring a catalyst, the equipment cost does not include the catalyst cost. Instead, the initial catalyst is accounted for in the start-up costs. For process chemicals, a fifteen day supply is assumed as an initial charge. The Total Plant Cost (TPC) is the sum of Process Capital, General Facilities Cost, Engineering and Home Office Fees, and Project Contingency Cost. The Process Contingency used in the EPRI Methodology accounts for the effect of the status of process

Table V-6

EMISSION CONTROL SYSTEM OPTIONS AND PRIORITIES FOR RESEARCH

High ← Research → Low
 Priority

NO _x Options	SO _x Options				
	Lime Injection @ 1000°F	Lime Injection @ 300°F	Adsorption on Activated Carbon at 450°F (Takeda Process)	Ca Additive in Fuel (~2000°F)	Spray Dryer
Reburning	Option C	Option B			Option L
NH ₃ Injection with Baghouse @ 450°F	Option J				
NO _x Absorption @ 275°F					Option N
NH ₃ Injection Using Activated Carbon Catalyst @ 450°F (Takeda Process)			Option M		
NH ₃ Injection Over CUO in Granular Bed @ 750°F (Shell/UOP)	Option D			Option D	
SCR @ 750°F		Option K			Option A

High

Research

Low

development on the design and cost of commercial-scale equipment. We do not apply a process contingency to the capital cost; instead we use the probability of technical success as a separate measure of the status of process development. In addition, the EPRI Methodology includes an allowance for escalation of construction costs over the construction period which is not used in this analysis because the construction period for small power plants is expected to be short. The General Facilities charge and the Engineering and Home Office Fees are assessed at 5 and 10 percent of the Process Capital, respectively. The Project Contingency Cost is computed as 20 percent of the sum of the Process Capital and General Facilities costs as appropriate for a preliminary design (as defined in Table V-7). The Process Capital (sometimes referred to as the installed equipment cost) is the total constructed cost of all equipment, including direct and indirect construction costs. Fees for freight and sales tax are included in the equipment cost. Direct installation costs account for the labor and materials costs of installation, including costs for site preparation and buildings. Indirect installation costs consist of the following: engineering and supervision labor, construction and field labor, any construction fees, and a small contingency fee. Reference 18 gives values for the direct and indirect installation cost components for most types of pollution control units.

The Operating and Maintenance Cost is the sum of operating labor, maintenance (labor and materials), and overhead labor. The annual maintenance costs are estimated as a percentage of the process capital cost. The EPRI methodology suggests maintenance cost factors for different technologies. The maintenance cost is broken down as 40 percent labor and 60 percent materials. The overhead charge is computed as 30 percent of the operating and maintenance labor and is a charge for administrative and support labor. Following the EPRI methodology, the Operating and Maintenance Cost is broken down into a fixed component and a variable component. The fixed Operating and Maintenance cost is the product of the capacity factor (or the utilization) and the annual Operating and Maintenance Costs; the balance of the cost is assumed to be variable. The Variable Operating cost has two components: consumables (power, chemicals, etc.) and operating and maintenance, as described above.

The total annual operating cost is the sum of the fixed Operating and Maintenance cost, the Variable Operating cost, and the cost of capital. The cost of capital is based on a 12 year allowable depreciation period for paying the debt at 10 percent interest. Accordingly, the yearly charge for the cost of capital is 15 percent of the total capital investment. The operating cost is expressed in millions of dollars per year or in mills/kWh. The latter unit is the annual operating cost (expressed as thousandths of a dollar) divided by the total hours that the equipment runs (at 65 percent utilization this is equal to 5694 hr) and the power output of the facility (in kW).

2. Cost Estimation For Individual Subsystems

The system capital and operating cost estimates depend on the actual cost of the equipment, being proportional to the equipment costs. In general, equipment costs are derived in two different ways. First, a study estimate is one based on previous cost data, but scaled for the particular system size (see Reference 19 for examples of scaling factors and Reference 18 for cost correlations for specific equipment); this type of estimate has probable accuracy of 30 to 50 percent. Second, a scope estimate is based on specific equipment costs, usually obtained in quote form from the manufacturer; this type of estimate has a probable accuracy of 10 to 20 percent.

Table V-7

DESIGN AND COST ESTIMATE CLASSIFICATIONS

Item	Design/Estimate Description	Project Contingency Range	Design Information Required	Cost Estimate Basis		
				Major Equipment	Other Materials	Labor
Class I	Simplified	30 to 50%	General site conditions, geographic location and plant layout.	By overall or section-by-section based on capacity/cost graphs, ratio methods, and comparison with similar work completed by the contractor, with material adjusted to current cost indices and labor adjusted to site conditions.		
		30 to 50%	Process flow/operation diagram.			
		30 to 50%	Product output capacities.			
Class II	Preliminary	15 to 30%	As for Type Class I plus engineering specifics, e.g.:	Recent purchase costs (including freight) adjusted to current cost index.	By ratio to major equipment costs on plant parameters.	Labor/material ratios for similar work adjusted for site conditions and using expected average labor rates.
		15 to 30%	Major equipment specifications.			
		15 to 30%	Preliminary P&I flow diagrams.			
Class III	Detailed	10 to 20%	Complete process design. Engineering design usually 20 to 40% complete. Project construction schedule. Contractual conditions and local labor conditions.	Firm quotations adjusted for possible price escalation with some critical items committed.	Firm unit cost quotes (or current billing costs) based on detailed quantity take-off.	Estimated manhour units (including assessment) using expected labor rate for each job classification.
		Pertinent taxes and freight included.				
Class IV	Finalized	5 to 10%	As for Class III, with engineering essentially completed.	As for Class III, with most items committed.	As for Class III, with material on approximately 100% firm basis.	As for Class III, some actual field labor productivity may be available.

Source: Ref. 17

Most cost data used in this study are based on conditions at some time in the past. Prices change with time and some method must be used to convert prices applicable at some time in the past to prices at some later time. For this study, the Chemical Engineering Index was used to convert all prices to March, 1988 prices. Prices are scaled by multiplying by the ratio of the March, 1988 index to the index at the original date of the price.

Table V-8 lists the methods used to calculate equipment costs for individual subsystems. Most of the study estimates are based on the methods in Reference 18, wherein specific correlations between cost, size, and operating parameters are provided for gas conditioning equipment such as baghouses, fans, and water quench units.

The cost for reburning is the sum of the cost of a duct burner and NO_x monitoring equipment. One duct burner is used per engine. For the LSB 6 engine, the burner must supply 4 MMBtu/hr of heat if the reburning process represents 20 percent of the total heat input. For the LSVB 20 engine, the burner must supply 13 MMBtu/hr. Three burner manufacturers were contacted; one quote was used for the duct burner costs because it was the most complete of the three.

For all SCR processes, a standard cost for the ammonia injection and storage system was used. This cost was drawn from the detailed cost breakdown of commercial SCR units. The sources of the commercial SCR costs are discussed below.

The cost for ammonia injection in the baghouse at 450°F is the sum of NO_x monitoring equipment and ammonia injection and storage equipment. In addition, the system option that incorporates this technology uses an insulated baghouse which is more expensive than the baghouses used for other systems. The insulated baghouse costs were estimated using correlations from Reference 18.

The cost for the Shell/UOP process is the sum of costs for an ammonia injection and storage system, NO_x monitoring equipment, and a granular bed filter unit sized by using a design value of the face velocity from Reference 20. The granular bed filtration unit equipment costs are discussed below.

In the case of the commercial SCR technology, cost data are available for engines in the range of 2000 to 60,000 hp. SCR costs are scaled by engine size using data on several engine sizes. The three data sets provide detailed equipment costs, but do not include complete capital cost information.^(21,22) An EPRI report⁽²³⁾ gives equipment and capital costs for a 80 MW utility boiler. The power boiler rating can be converted to an equivalent engine size by using the total exhaust flow through the SCR unit and a typical engine exhaust flow of 13 lb/hp-hr. The two estimates given in the EPRI report show a detailed breakdown of the capital costs. One (reference 24) gives SCR capital costs for a range of engine sizes. No detailed equipment costs are given.

The costs from all SCR data sets are given in March, 1988 dollars in Table V-9. The capital, equipment (excluding catalyst), and catalyst costs are displayed as a function of the system horsepower in Figure V-2. The capital costs fall on straight line with slope equal to 0.49. The equipment costs seem to be low for the smaller two systems by comparison with the capital cost data. A line with slope equal to 0.3 has been drawn through the equipment cost data. The rela-

Table V-8

METHODS USED TO ESTIMATE SUBSYSTEM EQUIPMENT COSTS

Subsystem Option	Estimation Method	References	Accuracy
<u>NO_x Control:</u>			
Reburning	Quotes from burner manufacturer		30%
NH ₃ Injection in Baghouse at 450°F	NH ₃ injection based on SCR cost; study estimate for baghouse	18	30%
Adsorption of NO _x at 275°F (Baghouse)	Based on estimate of differential disposal cost		20%
NH ₃ Injection in Granular Bed Filter (Shell/UOP)	NH ₃ injection based on SCR cost; study estimate scaled down	20	50%
Commercial SCR	Cost vs. engine size discussed in text	21, 22, 23	30%
<u>NO_x-SO₂ Control:</u>			
NH ₃ Injection at 450°F (Takeda)	Study estimate on cost of components	8, 18, 20	50%
<u>SO₂ Control:</u>			
Lime Injection (300°F)	Manufacturer quotes for small size; larger sizes scaled up	15, 18	30%
Lime Injection (1000°F)	Same as 300°F case		
Ca Additive in Fuel	Bulk price estimated from Aldrich catalog		50%
Commercial Spray Dryer	Budgetary estimate from manufacturer		20%
<u>Particle Control:</u>			
Cyclone	Quote from manufacturer		10%
Baghouse	Quote from manufacturer		10%
Ceramic Filter	Study estimate on cost of components	18, 25	50%
Granular Bed Filter	Study estimate on cost of components	18, 20	50%
<u>Auxiliary Equipment:</u>			
Induced Draft Fan	Study estimate	18	30%
Water Quench (for power system)	Study estimate	18	30%
Waste Heat Boiler	Scaled from LSVB 20 size	19	30%

Table V-9
SUMMARY OF SCR COST DATA

Reference	Horsepower	Cost in \$/hp ⁽¹⁾		
		Catalyst Cost	Equipment Cost ⁽²⁾	Capital Cost
24	1,072	-	-	746
21	2,000	25	52	-
21	5,500	25	27	-
22	9,600	29	26	-
24	11,796	-	-	172
24	28,150	-	-	145
23	65,210 ⁽³⁾	29	24	-
23	654,310 ⁽³⁾	35	26	111

Notes:

⁽¹⁾March 1988 \$

⁽²⁾Excluding catalyst cost

⁽³⁾Calculated from exhaust flow using 13 lb/hp-hr

A-9671

Figure V-2. Cost of SCR for Engine Emission Control

tive catalyst costs are almost constant with system horsepower and are taken to be \$29/hp. Based on these data, the equipment and catalyst costs for four coal-fueled diesel systems were determined from the graph (Table V-10).

Capital and operating costs for the Takeda process for one 33 MWe unit are given in Reference 8, but no details are given. The costs presented here are study estimates based on the process diagram; the costs of individual pieces of equipment are computed using estimation methods from References 18 and 19. Reference 18 gives a method for calculation of cost of a gas absorber consisting of a bed of activated carbon; the unit has two such absorbers. Reference 15 gives a detailed process diagram for a sorbent injection system from which the equipment list is derived for this estimate. Three manufacturers were contacted for quotes on a sorbent injection system for a single LSB 6 engine (approximately 100 lb/hr of sorbent). One quote was for a complete system and the other two included only the feeder itself. The cost of a sorbent feeding system for the smallest system is based on the cost of the feeder and auxiliary equipment (except duct work which is included in installation costs). Equipment costs for larger systems are computed by scaling the solid feed rate using an exponent of 0.6.

$$Cost_2 = Cost_1 \times \left(\frac{FeedRate_2}{FeedRate_1} \right)^{0.6}$$

Spray dryer equipment cost quotes were provided by one manufacturer for all four system sizes. Although several manufacturers of spray dryers were contacted, only one sold equipment in the size range of the engine systems.

Quotes were obtained from two manufacturers for cyclones. One manufacturer provided data for both the LSB 6 and LSVB 20 engine size. Both quotes agreed well with the calculation method given in Reference 18. Since the cyclone is upstream of the turbocharger, emission control systems have one cyclone per engine. Therefore the cost of cyclones is the number of engines multiplied by the single cyclone cost.

Reference 18 gives detailed methods for estimating the cost of baghouses. The cost is based on the gas flow rate, the gas face velocity (or air-to-cloth ratio), the type of baghouse (reverse air or pulsed jet), and the filter material. Costs for both pulsed jet and reverse air were calculated for all four system sizes. For this study, the reverse air baghouse was chosen because it was cheaper than the pulsed jet baghouse for the flow rates in question. A quote was also received from a manufacturer of pulsed jet baghouses detailing the cost for all four system sizes and the quoted costs were within about 5 percent of the calculated costs from Reference 18. The cost of insulated reverse air baghouse was also calculated for system Option J.

Equipment cost estimates for the ceramic cross flow filter units were assembled from the detailed component cost data in Reference 25. The principal sizing parameter utilized for calculating the total filter area and the vessel size is the filter face velocity, taken to be 10 ft/min as suggested in Reference 25. One cross flow filter unit is used for each engine.

Table V-10

SCR EQUIPMENT AND CATALYST COSTS USED IN ECONOMIC ANALYSIS

System Power [hp]	Equipment Cost [\$ /hp]	Catalyst Cost [\$ /hp]
2,516	66	29
10,064	43	29
16,772	38	29
33,544	31	29

Component cost data presented in Reference 20 are employed to determine equipment cost estimates for the granular bed filter. Sizing of the units was based on the recommended value for filter face velocity of 110 ft/min. The cost per filter element as well as typical costs for vessels and back end cleanup are provided in Reference 20. As with the cross-flow filter, total equipment costs for multiple-engine systems are calculated as the product of the cost per unit and the number of engines in the system.

3. Cost Of Auxiliary Equipment And System Integration

Auxiliary equipment is common to all systems, independent of which emission control subsystems are chosen. Because of the pressure drop through the various emission control modules, an induced draft fan will be needed to draw gas through the exhaust system. The cost of the fan is based on a static pressure of 10 inches of water. Using the methods outlined in Reference 18, the cost of a fan, motor, and starter are calculated for each system size.

In the case of the system for power generation only, there is no waste heat boiler to cool the exhaust gases down to approximately 350°F. A water quench unit can be used to lower the exhaust gas temperature for those components requiring a temperature less than that at the turbocharger exhaust. A correlation for the cost of water quench units (including a chamber, supports and controls) with gas flow is given in Reference 18. One manufacturer was contacted concerning water quench units and the quote was lower than the calculated costs. In order to be conservative for this cost estimate, the calculated cost was used.

The goal of the economic analysis is to compare the added cost of the coal-fueled diesel emission control system to the baseline diesel-fueled system. In cogeneration applications, the amount of steam generated and the size of the waste heat boiler depend on the temperature drop through the heat exchanger and the total gas flow. The exhaust gas temperatures at the inlet and outlet of the waste heat boiler vary depending on which subsystems are used. For example, if reburning is employed as the NO_x control method, the gas temperature at the boiler inlet is higher than that in the baseline case. In terms of cost, this means a higher steam credit (because more steam is generated) and a higher boiler cost (because more heat transfer surface is required).

In order to compare the system options to one another, a differential cost relative to the diesel-fueled baseline is calculated. Table V-11 shows the results of these calculations for all four cogeneration system sizes. The differential steam flow is expressed in terms of millions of dollars per year, using a steam price of \$5.64 per thousand pounds of 125 psig steam. The differential capital cost is based on an assumed boiler cost for the diesel-fueled baseline system. This baseline boiler cost is calculated from a cost of \$93,650 for a single LSVB 20 engine; the boiler cost was supplied by Cooper Bessemer and has been converted to March, 1988 dollars. A scaling exponent of 0.6 is used to obtain the costs for other system sizes. One waste heat boiler per system is assumed. The differential boiler cost (in millions of dollars) is calculated from the ratio of the heat exchange areas of the coal-fueled system relative to the diesel-fueled system and a scaling exponent of 0.6.

$$Cost_2 = Cost_1 \times \left(\frac{SurfaceArea_2}{SurfaceArea_1} \right)^{0.6}$$

Table V-11

DIFFERENTIAL COSTS OF COAL-FUELED ENGINE RELATIVE TO OIL-FUELED ENGINE FOR PRODUCTION OF 125 PSIG STEAM

Option	Temperature (F)		Ratio of Boiler Areas of Diesel	Differential Costs							
	In	Out		(mm\$/yr)		(mm\$)		(mm\$/yr)		(mm\$)	
				(mm\$/yr)	(mm\$)	(mm\$/yr)	(mm\$)	(mm\$/yr)	(mm\$)	(mm\$/yr)	(mm\$)
Diesel Fuel	850	420	1	0	0	0	0	0	0	0	0
A, D, K	750	360	2.04	0.009	0.026	0.034	0.060	0.057	0.082	0.114	0.125
B, C, L	1110	360	2.41	(0.094)	0.034	(0.377)	0.079	(0.628)	0.107	(1.257)	0.162
M	660	450	0.61	0.61	(0.013)	0.242	(0.029)	0.404	(0.040)	0.807	(0.060)
N	660	360	1.90	0.034	0.023	0.135	0.053	0.224	0.072	0.449	0.110
J	1000	450	1.03*	(0.036)	0.001	(0.142)	0.002	(0.160)	0.003	(0.319)	0.004

Assumptions:

- Saturation temperature is 350°F
- Latent heat of steam = 869 Btu/lb
- Baseline exchanger costs scales as the surface area using an exponent of 0.6 steam cost of 5.64 \$/klb
- One waste heat boiler per system is assumed

* Differential operating costs do not include the cost of natural gas to heat the exhaust gas; this is accounted for separately

4. Assembly Of System Costs

The installed equipment costs for individual subsystems have been calculated as discussed in the previous two sections. The results of these calculations (Table V-12) will be used to compute costs for the integrated emission control systems.

Several assumptions of significance are used in the system cost calculations. First, a decision has been made to combine the exhaust gases downstream of the turbocharger. Second, we have placed the duct burners upstream of the turbocharger to take advantage of the higher gas temperature there. Therefore one duct burner is required for each engine. The duct burner could be placed downstream of the turbocharger without changing the exhaust gas temperatures or pressures. Finally, all control equipment (except the cyclone and duct burner) and the waste heat boiler are common to all engines.

A distinction has been made between power and cogeneration systems. A cogeneration system has a waste heat boiler that produces 125 psig steam. The cost of the waste heat boiler is not included in the system, except if the cost is more (or less) than the diesel-fueled baseline case. The differential equipment cost of the boiler relative to the baseline is included in the equipment cost. Likewise, the cost of producing more (or less) steam than the baseline case is included as an operating cost.

The cost of operating labor is based on one half-time operator for the smallest (1.8 MW_e) system and one full-time operator for the others. Maintenance factors used to calculate maintenance labor and materials can be found in Appendix H.

Table V-13 lists the prices for consumables used to calculate variable operating costs. The steam cost is based on the replacement value for a utility boiler burning natural gas at \$3.50/1000 cubic feet. The prices for ammonia and activated carbon are from manufacturers. The calcium fuel additive is assumed to be calcium acetate and the cost is equal to one-tenth of the current price for kilogram quantities. Much uncertainty exists about the bulk price for this chemical since it is not intended for large-scale distribution currently. All other costs were taken from Reference 17.

The details of all the system cost calculations are given in Appendix H. This procedure will be illustrated with an example, Option A with one LSB 6 engine (1.8 MW_e).

The calculation begins with a list of equipment. Costs are taken from Tables V-11 and V-12. The installation cost is the sum of the installation costs for each unit. Each subsystem has an installation factor used to calculate the direct and indirect costs, equal to product of the equipment cost and the installation factor. This factor is based on the complexity of the equipment and on industry experience. Reference 18 suggests installation cost factors for some pollution control equipment. References 21 through 23 give installation costs for commercial SCR units. The Total Plant cost is computed as discussed above.

The installed equipment cost is used to calculate the Operating and Maintenance Cost (O&M) as discussed above. The O&M cost is divided into fixed and variable costs as a function of the utilization. A utilization of 65 percent is employed throughout. The variable operating cost due to consumable items (power, chemicals, disposal) is computed in terms of dollars per hr of operation. For processes employing a catalyst and for the baghouse, the cost of replacing the catalyst

Table V-12

EQUIPMENT COSTS FOR SUBSYSTEMS

Subsystem Option	Installation Multiplier ¹	Cost [\$/kW] as a function of system size:			
		1.8 MW	7.2 MW	12 MW	24 MW
<u>NO_x CONTROL:</u>					
Reburning ²	0.33	18	18	9	9
NH ₃ Injection in Baghouse at 450°F	0.40	47	12	8	5
Adsorption of NO _x at 275°F (Baghouse)	-	0	0	0	0
NH ₃ Injection in Granular Bed Filter (Shell/UOP)	0.70	164	110	105	102
Commercial SCR	0.37	92	60	53	43
<u>NO_x-SO₂ CONTROL:</u>					
NH ₃ Injection at 450°F (Takeda)	0.95	225	87	62	42
<u>SO₂ CONTROL:</u>					
Lime Injection (300°F)	0.37	17	9	6	5
Lime Injection (1000°F)	0.37	17	9	6	5
Ca Additive in Fuel	-	0	0	0	0
Commercial Spray Dryer	0.60	251	111	84	59
<u>PARTICLE CONTROL:</u>					
Cyclone ²	0.60	8	8	5	5
Baghouse	0.75	42	18	15	15
Ceramic Filter ²	0.69	69	69	50	50
Granular Bed Filter ²	0.70	132	132	102	102
<u>AUXILIARY EQUIPMENT:</u>					
Induced Draft Fan	0.40	3	2	2	2
Water Quench (for Power System)	0.38	-	-	9	-

NOTES: (1) To calculate installation cost, multiply equipment cost by the installation cost multiplier
 (2) Cost includes one unit for each engine

Table V-13
COMMODITY PRICES FOR OPERATING COST CALCULATION

Commodity	Value/Units
Operating Labor	\$21.55/hour
Natural Gas	\$3.50/1000 cu. ft.
Raw Water	\$0.60/1000 gallon
Cooling Water	\$0.15/1000 gallon
Steam (125 psig)	\$5.64/1000 lb
Power	\$0.05/kWh
Copper Oxide Catalyst	\$8000/ton
Activated Carbon	\$4000/ton
Ammonia	\$500/ton
Hydrated Lime	\$70/ton
Lime	\$65/ton
Calcium Acetate	\$4140/ton
Waste Disposal	
- Dry Solids	\$8.50/ton
- Fly Ash	\$6.50/ton
- Gypsum	\$6.50/ton
- Sludge	\$9.25/ton

or bags is included in the consumables. In Option A, the SCR catalyst is assumed to have a 2-year life; the hourly rate is the replacement cost divided by the number of hours of running time in two years. The bags (which are NOMEX cloth) have a one year life. Each calculation in Appendix H includes an itemized list of consumables.

The variable operating costs and fixed O&M costs are used to calculate the pre-production and inventory capital costs as described above. These costs and the initial supplies cost are added to the total plant cost to give the total capital cost. Finally, the cost of capital is computed as 15 percent per year of the total capital cost. The total operating cost is the sum of variable, fixed O&M, and capital costs. To facilitate comparisons among different systems, the total capital costs and operating costs are expressed on a cost per unit of electricity generated in Tables V-14 through V-18.

E. DISCUSSION OF ECONOMIC ANALYSIS

1. Cost Vs. System Size

The goal of this study, as stated earlier, was to quantify the cost and probability of success for the emission control system options. In this section, the analysis of the costs takes several forms. First, the cost of the equipment for the component technologies is presented. From these costs comparisons are made among the various technologies for controlling the three major pollutants. Second, the capital and operating costs for integrated emission control systems are presented as a function of system size. Finally, the probability of technical success for system options is introduced and combined with the operating costs for each system. The discussion of these results provides recommendations for the most favorable emission control options.

Table V-12 gives the cost of equipment for individual control technologies expressed on a per kilowatt basis. For the three major pollutants, several technologies are evaluated, providing a range of costs for controlling each pollutant. Of the NO_x control technologies, the Shell/UOP process is by far the most expensive. It must be noted, however, that this subsystem also includes removal of all particles as well as control of NO_x . Commercial SCR technology is 2 to 5 times more expensive than reburning or ammonia injection in the baghouse. The Takeda process, which removes both NO_x and SO_2 , is very expensive for the smallest system, but the capital cost is comparable to that of the commercial SCR for the 12 and 24 MWe systems. The commercial spray dryer for SO_2 control is 12 to 15 times more expensive than direct injection of sorbent into the duct.

Although the ceramic cross-flow filter and the granular bed filter are not included in any of the proposed systems, the costs are of interest in the event that the turbocharger needs more protection than offered by a cyclone. These technologies remove all particles upstream of the turbocharger and therefore the cost should be compared against the sum of the cyclone and baghouse costs. The ceramic cross-flow filter is 1.4 to 2.5 times more expensive than the cyclone/baghouse combination. The granular bed filter is 2.6 to 5 times more expensive than the commercially available option. If total particle removal is needed upstream of the turbocharger, the ceramic cross-flow filter is preferred due to the simplicity, relatively affordable cost, and near-commercial status of the technology.

COAL-FUELED DIESEL EMISSION CONTROL SYSTEM CAPITAL AND OPERATING COST SUMMARY FOR 1 LSB6 ENGINE (1.8 MW)

System Option	Capital Cost		Operating Cost			
	(MM\$)	(\$/kWh)	Variable (mills/kWh)	Fixed (mills/kWh)	Capital (mills/kWh)	Total (mills/kWh)
A	1.742	968	18	12	25	55
B	0.411	228	6	9	6	20
C	0.411	228	6	9	6	20
D	1.150	639	61	12	17	89
J	0.614	341	12	9	9	31
K	0.808	449	16	9	12	37
L	1.360	756	8	11	20	39
M	1.410	783	22	13	21	56
N	1.290	717	13	11	19	42

Notes: 65% utilization used to calculate variable operating costs; cost of capital is 15% per year.

**COAL-FUELED DIESEL EMISSION CONTROL SYSTEM CAPITAL AND OPERATING COST SUMMARY
FOR 4 LSB6 ENGINES (7.2 MW)**

System Option	Capital Cost		Operating Cost			Total (mills/kWh)
	(MM\$)	(\$/kWh)	Variable (mills/kWh)	Fixed (mills/kWh)	Capital (mills/kWh)	
A	3.649	507	13	6	13	33
B	0.987	137	3	4	4	11
C	0.987	137	3	4	4	11
D	3.415	474	58	6	12	77
J	1.292	159	10	4	5	19
K	1.957	279	13	5	7	25
L	2.662	370	4	6	10	19
M	2.494	346	18	6	9	33
N	2.404	334	9	5	9	23

Notes: 65% utilization used to calculate variable operating costs; cost of capital is 15% per year.

COAL-FUELED DIESEL EMISSION CONTROL SYSTEM CAPITAL AND OPERATING COST SUMMARY FOR 2 LSVB20 ENGINES (12 MW)

System Option	Capital Cost		Operating Cost			
	(MM\$)	(\$/kWh)	Variable (mills/kWh)	Fixed (mills/kWh)	Capital (mills/kWh)	Total (mills/kWh)
A	4.929	411	11	4	11	26
B	1.180	98	2	3	3	8
C	1.180	98	2	3	3	8
D	5.359	447	56	5	12	73
J	1.546	129	10	3	3	16
K	2.866	239	12	3	6	22
L	3.299	275	3	4	7	14
M	3.140	262	17	4	7	27
N	3.082	256	8	4	7	18

Notes: 65% utilization used to calculate variable operating costs; cost of capital is 15% per year.

**COAL-FUELED DIESEL EMISSION CONTROL SYSTEM CAPITAL AND OPERATING COST SUMMARY
FOR 2 LSVB20 ENGINES (12 MW - NO COGENERATION)**

System Option	Capital Cost		Operating Cost			
	(MM\$)	(\$/kWh)	Variable (mills/kWh)	Fixed (mills/kWh)	Capital (mills/kWh)	Total (mills/kWh)
A	5.053	421	12	4	11	27
B	1.335	111	12	3	3	17
C	1.335	111	12	3	3	17
D	5.440	453	55	5	12	72
J	1.772	148	13	3	4	19
K	2.947	246	12	3	6	21
L	3.453	288	12	4	8	23
M	3.340	278	11	4	7	22
N	3.151	262	9	5	9	23

Notes: 65% utilization used to calculate variable operating costs; cost of capital is 15% per year.

Table V-18

**COAL-FUELED DIESEL EMISSION CONTROL SYSTEM CAPITAL AND OPERATING COST SUMMARY
FOR 4 LSVB20 ENGINES (24 MW)**

System Option	Capital Cost		Operating Cost			
	(MM\$)	(\$/kWh)	Variable (mills/kWh)	Fixed (mills/kWh)	Capital (mills/kWh)	Total (mills/kWh)
A	8.052	336	12	2	9	23
B	2.176	91	2	2	2	5
C	2.176	91	2	2	2	5
D	10.301	429	55	2	11	69
J	2.853	119	9	2	3	14
K	5.114	213	12	2	6	19
L	5.133	214	2	2	6	10
M	4.965	207	16	2	6	23
N	4.729	197	7	2	5	14

Notes: 65% utilization used to calculate variable operating costs; cost of capital is 15% per year.

From the equipment cost of individual technologies, the discussion moves to the capital costs of complete emission control systems (Tables V-14 through V-18). Figure V-3 shows that the cost per kilowatt decreases by about a factor of two as the system size increases from 1.8 to 24 MW_e for the four cogeneration system options studied. The capital cost per kilowatt for the single LSB 6 system (1.8 MW_e) is almost twice as expensive as the cost of the next largest system (four LSB 6 engines or 7.2 MW_e). The cost per kilowatt continues to decrease as the system size increases to 12 and 24 MW_e, but the decline is more gradual. System options that include the spray dryer or the Takeda process unit show the strongest dependence of cost on system size.

In terms of capital cost per kilowatt, Options B, C, J, and K are favored for all system sizes. In addition, Options L, M, and N appear promising for the 12 and 24 MW_e systems.

The annual operating costs also decrease with increasing system size (Figure V-4). The operating costs for the smallest system (1.8 MW_e) are about three times higher than those for the largest system (24 MW_e). For the systems containing a commercial SCR unit, the cost of catalyst is the single largest operating cost. The cost of natural gas to raise the exhaust gas temperature to 750°F (the optimum SCR operating temperature) is also one of the major operating costs.

Options B, C, and L, which include the reburning technology, have low operating costs because of the credit for steam produced in excess of the diesel-fueled baseline case. The steam credit applies only to the four cogeneration systems; System 4, as defined in Table V-3, does not recover heat from the exhaust gas and no steam is produced. The appeal of these three options is diminished if the steam price goes down or if there is no steam production, as in the power generation system.

The high operating cost for Option D reflects the cost of the calcium acetate fuel additive. There is a high degree of uncertainty about what the bulk cost of a calcium fuel additive might be and these operating costs could be lower than indicated. As explained previously, we assume this reactant cost is 10 percent of the commodity chemical cost.

Option M has a favorable capital cost for the two largest systems, but the operating cost is significantly higher than most other systems. There are two reasons why the operating cost is so high. The primary factor is cost of steam; Option M produces less steam than the diesel-fueled baseline case because the temperature drop through the waste heat boiler is about half that of the baseline case. The replacement cost for the activated carbon is another important factor in the high operating cost.

In terms of total annual operating costs, Options B, C, and J are favored for all system sizes. In addition, Options K, L, and N appear promising for the 12 and 24 MW_e systems.

In the final set of figures, the annual operating costs are displayed with the probability of technical success for each system option. The probability of success is computed by multiplying the probabilities of the technologies for removal of the three major pollutants (Table V-5). In the case of a process that removes two pollutants simultaneously, the subsystem probability is squared.

A-9672

Figure V-3. Capital Cost for Cogeneration System

A-9673

Figure V-4. Annual Operating Cost for Cogeneration System

In Figures V-5 through V-9, the annual operating cost is plotted against the probability of technical success for all five systems. Options that have a probability of technical success greater than 50 percent are considered favorable. The cogeneration systems exhibit the same trends. Options C, D, J, and N have a probability less than 50 percent for the technical success of the emission control system. Of the options with a probability greater than 50 percent, Options A and M have the highest operating costs.

In the case of the power generation system, no heat is recovered from the exhaust gas and no steam is generated. The operating costs for systems including reburning (B, C, and L) increase because the steam credit taken in the case of cogeneration no longer offsets the cost of natural gas. On the other hand, the operating costs for Option M are lower in the power generation system than in the cogeneration system. The cost of additional steam (as compared to the diesel-fueled baseline) is not an operating cost in the power generation system.

In terms of the probability of technical success, Options B, K, and L are favored for cogeneration systems. For power generation systems, Option M is also favored in addition to the three systems listed for cogeneration applications.

2. Sensitivity Of Results

Since this study represents a preliminary design, with 20 to 30 percent uncertainty in the calculated costs, a formal sensitivity analysis is not performed. However, two aspects of the sensitivity of the economic calculations to input data are discussed. First, the engine operating parameters and system configuration may change as a result of the on-going JS-1 test program. Second, the process parameters for control technologies may change as a result of experiments performed as part of Task 2 and of more detailed discussions with manufacturers of commercially available technology.

Preliminary design decisions that have been made about the configuration of the integrated system are subject to change as engine development proceeds. Several elements of the preliminary design impact the cost and feasibility of the emission control system: manifold air temperature, assumed particle removal needed upstream of the turbocharger, placement of the reburning unit with respect to the turbocharger, and the decision to combine the gas streams from all engines for most of the emission control modules.

The manifold air temperature (MAT) has not been optimized as yet. The baseline MAT for these calculations is 250°F, but, as Table V-19 shows, variations in the manifold air temperature have an impact both on NO_x emissions and on the exhaust gas temperature. The variation of NO_x levels and exhaust gas temperatures with changes in MAT in the table are drawn from the JS-1 test results to date.

The required reduction of NO_x to meet NSPS varies from 63 to 84 percent as the MAT is varied from 150 to 300°F. Several elements of the cost of NO_x control technology depend on the required reduction: the reactor size, the amount of ammonia required for SCR-type processes, and the amount of reburning fuel used. For example, if a lower NO_x reduction is required than in the MAT baseline case, the residence time in the reactor (and hence the size of the reactor) can be reduced, resulting in lower capital costs. The operating costs also decrease because less

A-9656

Figure V-5. Annual Operating Cost vs. Probability of Technical Success for 1.8 MWe Cogeneration System

A-9657

Figure V-6. Annual Operating Cost vs. Probability of Technical Success for 7.2 MWe Cogeneration System

Figure V-7. Annual Operating Cost Vs. Probability of Technical Success for 12 MW_c Cogeneration System

A-9659

Figure V-8. Annual Operating Cost vs. Probability of Technical Success for 12 MW_e Power System

A-9660

Figure V-9. Annual Operating Cost vs. Probability of Technical Success for 24 MWe Cogeneration System

Table V-19

EFFECT OF MANIFOLD AIR TEMPERATURE ON PROCESS HISTORY

Point In Process	Process Parameter	Value	Units	Manifold Air Temp. (°F)			
				150	200	250	300
Cylinder Inlet	Engine Speed	400	rpm				
	BSFC	6300	Btu/hp-hr				
	Theoretical Air	231	%				
	Pressure		psig	21.4	24.3	27.3	30.2
Cylinder Exhaust	Pressure	12.4	psig				
	Temperature		F	780	830	880	930
	NO _x		ppm	525	675	900	1200
			lb/MMBtu	1.6	2.1	2.8	3.7
T.C. Outlet (1)	Temperature		F	560	610	660	710
T.C. Outlet (2)	Temperature		F	1010	1060	1110	1160
NO _x Control Unit	Required Reduction(3)			63%	71%	79%	84%
NOTES: (1) Without reburning (2) With duct burner upstream of turbocharger (20% of total heat input) (3) To meet 0.6 lb/MMBtu emission level							

ammonia is needed and the catalyst replacement costs are lower than in the baseline case. For the commercial SCR process (Options A and K) and the Takeda process (Option M), the cost of catalyst is a significant portion of the operating costs. The operating costs of the options employing reburning may be reduced if a lower NO_x reduction is required. Although the use of a steam credit in the cogeneration system calculations means that a decrease in natural gas costs is offset by a decrease in the amount of steam generated in excess of the diesel-fueled baseline. It should also be noted that the feasibility of reburning may become questionable if the required NO_x reduction becomes too high. Currently, the maximum reduction that can be achieved within the constraints of the coal-fueled diesel operating parameters is unknown.

The cost of particle removal equipment could increase by a factor of 2 if a cyclone is found to be insufficient to protect the turbocharger from erosion. In this case, the cyclone and the baghouse are replaced by a ceramic cross-flow filter located upstream of the turbocharger.

The reburning unit has been placed upstream of the turbocharger; if the duct burner must be placed downstream of the turbocharger, the inlet temperature for the reburning process would be lower than assumed here by approximately 200°F. This means that more reburning fuel would be required to achieve temperatures at which free radical formation and subsequent NO_x reduction could occur. Perhaps, in this case, the reburning process would not be feasible or cost-effective.

Finally, the systems are designed to combine the exhaust gas streams of all engines upstream of the waste heat boiler. If this is not possible, the systems with more than one engine would require more than one pollution control module (e.g., SCR, spray dryer, etc.). As an example, consider the SCR unit applied to System 2 (four LSB 6 engines). The cost of equipment for a single SCR unit is \$60/kW or \$432,000. If the exhaust gases from individual engines are not combined, four small SCR units are required at a cost of \$92/kW or \$662,400.

The goal of Task 2 is to assess the performance of specific control technologies under conditions of the coal-fueled diesel engine exhaust. The calcium-to-sulfur (Ca/S) ratio needed to achieve the desired SO₂ reduction by direct injection of sorbent may be revised. This would directly affect the operating costs of Options B, C, J, and D, although the impact is significant only to Options B and C. Since reburning has not been applied to the specific operating conditions of the coal-fueled diesel engine, it is difficult to predict the outcome of the experiments. If less reburning fuel than assumed here is required, the operating costs may decrease.

F. CONCLUSIONS/DIRECTIONS FOR EMISSIONS R&D PROGRAM

System Option A, which relies on conventional technology (SCR and spray dryer), is low risk, and this analysis shows the cost is high but not excessive. Therefore, until other options are demonstrated as feasible, Option A has been adopted as the nominal baseline emission control system in our plant design. However, it is not a "preferred" option in the real sense of the word because of relatively high cost. Based on the present economic analysis, the most attractive emission control system options in terms of cost and probability of success are Options P, K, and L. Options L and K combine a commercially available technology (SCR or spray dryer) with a technology that is less well-developed but inexpensive (reburning or sorbent injection). Option B uses reburning for NO_x control and sorbent injection for SO₂ control; this is the least expensive option, but it also has a lower probability of success than Options K or L. The capital costs for

these three emission control systems are in the range of \$750/kW to \$225/kW for the 1.8 MWe system, but decrease to \$250/kW to \$100/kW for the larger systems. The operating costs for these emission control systems are in the range of 20 to 40 mills/kWh for the 1.8 MWe system, but decrease to 5 to 20 mills/kWh for the larger systems.

Options J, D, N, and M should be eliminated as a result of the analysis. The first three have a probability of success less than 50 percent computed by the methods of this analysis and Option M is too expensive relative to its probability of technical success. A careful examination of Option C should be performed before proceeding further; the system is inexpensive, but the technology for sorbent injection at 900 to 1000°F is still under development. Recent work⁽¹³⁾ has shown that the degree of agglomeration of sorbent particles in the feeding system markedly affects the amount of SO₂ capture in the duct. If total particle removal is needed upstream of the turbocharger, the ceramic cross-flow filter is preferred. Using the ceramic cross-flow filter approximately doubles the cost of particle removal equipment.

On a per kilowatt basis, the cost of an emission control system for a single LSB-6 engine system (1.8 MW_e) is about twice the cost of larger systems. If the emission control system cost is so high that it threatens the commercial viability of the 1.8 MW_e system, the entire engine system should be closely examined with respect to reducing costs. There may be modifications in combustion conditions, fuel type, or engine design that, while increasing the cost of the engine or the fuel, result in a decrease in the cost of the emission control system. Thus, the overall system cost could be lowered to a level that would encourage commercialization.

Two commercially available pollution control technologies appear favorable but relatively expensive: SCR for NO_x and spray dryer for SO₂. These should be explored further with manufacturers to determine if the cost of systems specifically designed for the coal-fueled diesel engine can be reduced. SCR processes have undergone accelerated development recently as pollution regulations have gotten tougher, especially in Europe and Japan. The cost of an SCR process may decrease in the near term.

In summary, the conclusions of this design study are as follows:

Baseline Selected Option:	A (SCR and Spray Dryer)
Preferred but must be proven:	K (substitutes sorbent injection for SO ₂)
	L (substitutes reburning for NO _x)
	B (substitutes both the above technologies)
Judged not worth pursuing:	J (ammonia injection in baghouse for NO _x)
	D (calcium fuel-additive for SO ₂ ; shell/UOP process for NO _x)
	M (Takeda process for SO ₂ and NO _x)
	N (NO _x absorption plus spray dryer)
	C (same as Option B but injection at 1000°F)

The experimental program should focus on direct injection of sorbent and reburning. However, experiments with sorbent injection at 900 to 1000°F should be scaled back. Sorbent injection in this temperature range is not favored as a result of this analysis. The optimum temperature range cannot be attained in the coal-fueled diesel exhaust without reheating the gas. The system option featuring reburning and a waste heat boiler is the only cost-effective way to utilize sorbent injection at high temperatures for SO₂ removal. Reburning appears very attractive from a cost standpoint. However, this technology has not been demonstrated under coal-fueled diesel operating conditions. In particular, the experimental program should examine the temperature sensitivity and auxiliary fuel requirements of the process. Placement of the duct burner with respect to the turbocharger strongly affects the temperature in the reburning process (and the NO_x reduction). If the desired NO_x reduction is not achieved with reburning using up to 20 percent of the total heat input as reburning fuel, consideration should be given to combining reburning with another technique such as adsorption at 275°F or ammonia injection at 450°F in the baghouse. Both of these technologies, even when combined with reburning, are less expensive than a commercial SCR unit. Also, if the temperature proves to be too low for much reduction of NO_x by the actual reburning process, additives (such as urea or ammonia) might be used to increase the NO_x removal by non-catalytic reduction.

Finally, as shown in Figure V-10, the NO_x target for coal diesels if achieved, will still leave gas turbines at a considerable advantage with respect to NO_x.

Therefore, further NO_x methods should be explored, possibly including SNR and in-cylinder NO_x control.

Figure V-10. Coal-Diesel NO_x Target Compared To Gas Turbined

VI. ANALYSIS OF ECONOMICS

A. SUMMARY

The economics of the coal-fueled diesel plant has been continually re-evaluated as new information has come to light on coal fuels, emission control, engine component performance, and other factors. The analysis methodology includes the use of a sensitivity analysis to explore trade-offs between coal fuel price, emission control costs, maintenance costs, etc. The framework for the economic analysis originally was formulated in 1986, and the analysis was then repeated with revised assumptions in 1988 and again in 1989. Our analysis in 1986, including the complete methodology and framework, can be found in the Systems Study published as a METC report ("Coal Fueled Diesel Systems for Stationary Power Applications," Task 1 - Topical Report, Assessment of Merit," DOE/MC/22181-2242). Following that report, in 1988, the economics analysis was repeated after the JS engine test results on coal fuel enabled us to revise certain key assumptions in the economic model (e.g., engine efficiency and injector replacement intervals). Further changes since the 1988 analysis, reported here, resulted from two comprehensive reviews by subcontractors:

- AMAX revised their coal processing cost estimates (also, delivered and minemouth prices for likely source coals were updated) - see Section IV.
- Physical Sciences (PSI) prepared detailed estimates of emission control costs for specific configurations (SCR, spray dryer, etc.) - see Section V.

Table VI-1 summarizes the revised cost estimates. Our conclusions, as explained in more detail below, are that (1) the projected cost of coal diesel power is 6.45¢/kWh, which is virtually equal to the 6.54¢/kWh estimated in the 1988 analysis and 6.20¢/kWh in the original 1986 analysis, (2) economic viability hinges on the cost of CWS production (engine-grade slurry price must be kept below about \$3.50/million Btu), and (3) emission control costs have emerged as an equally important parameter; they could "make or break" the economic success. As shown in Table VI-1, the emissions control cost at \$2.50/MMBtu is converging toward the CWS fuel cost. The economic analysis gave a new perspective on the conditions under which the coal diesel could be cost competitive with oil or gas-fueled stationary engines. The complete revised model printout is included in this report as Appendix I.

B. ENGINE COMPONENT COST PREMIUMS ASSOCIATED WITH COAL

The use of beneficiated coal slurry will necessitate certain modifications to the standard large diesel engine, both in terms of special components and special maintenance practices. Although the precise nature of these modifications cannot be determined until the research and development is complete, it is still useful to project approximate cost premiums based on Cooper-Bessemer's best judgment at this time. Table II-6 above listed the engine components expected

to be affected by coal fuel; these are generally "moving parts" which are exposed to either the fuel or the products of combustion. The estimated cost premium associated with the modification of these components is \$1.67 million (the same assumption as in the 1988 analysis). That is, the standard 6 megawatt engine costs \$3.5 million, whereas the future coal-fueled version is projected to cost \$5.2 million, on an installed basis.

Table VI-1

KEY MODIFICATIONS TO ECONOMIC MODEL

Modification	1988 Estimate	1989 Estimate	Revisions Based on	Impact on Cost of Power
Revised emission control costs (PSI)	\$1.18/MMBtu	\$2.50/MMBtu	Detailed design of emission control system (see Chapter IV) This cost is for SCR and spray dryer configuration on 2x20 cyl engines	Higher by \$.0116/kWh
Revised coal water slurry costs (AMAX)	\$4.33/MMBtu	\$2.90/MMBtu	Detailed analysis of 1.8 million TPY processing plant This CWS cost is for physically-cleaned 1% ash product	Lower by \$.0125/kWh
Resulting cost of power after all other assumptions	\$.0654/kWh	\$.0645/kWh		Lower by \$.0009/kWh

On a per-kWh basis, this capital cost translates to 1.21 cents per kWh vs. 0.81 cents per kWh for the standard oil or gas engine, based on 20-year life and 80% load factor. This premium of $1.21 - 0.81 = 0.40$ cents per kWh is exclusive of emission control equipment costs, which are accounted for separately below.

The present maintenance practices for a 6 megawatt Cooper engine are compared to the expected coal diesel practices (as revised in view of JS test results) in Table VI-2.

The cost associated with this increased level of maintenance and overhaul is projected to be \$3.9 million over a 20-year period, vs. \$1.4 million for a standard 6 MW diesel, which translates to \$.0052/kWh for the coal engine vs. \$.0019/kWh for the standard. It is recognized that injector life would be limited on coal fuel (500 hr is the assumed injector life). The projected interval between major overhauls was also reduced to 25000 hr. See Table II-7 for detailed maintenance costs.

In summary, the total cost for purchasing, installing and maintaining a 6 megawatt Cooper-Bessemer coal diesel (exclusive of fuel and emissions control) is expected to be \$.0163/kWh, compared to \$.0100/kWh for an oil-fired diesel of comparable size, including both capital cost and maintenance. Since the standard busbar cost of producing power with diesel fuel or natural gas can range from about 5 to 7¢/kWh, depending on prevailing fuel prices, this premium of \$.0063/kWh for a coal-tolerant engine would represent about a 10% increase in power cost,

Table VI-2

IMPACT OF COAL FUEL ON MAINTENANCE AND OVERHAUL PRACTICES

Item	Standard 6 MW Diesel	Coal Diesel Projections	20-Year Overhaul Costs*
Injectors	2,000 hr.	500 hr.	\$1,008,000
Minor Maintenance Checks	8,000 hr.	4,000 hr.	390,000
Top-End Overhaul	25,000 hr.	12,000 hr.	780,000
Major Overhaul	100,000 hr.	25,000 hr.	1,740,000
Total	-	-	\$3,918,000

*1989 estimate for coal diesel

according to our analysis. This premium is by no means prohibitive. In fact, if emission control costs or fuel costs could be reduced significantly by the use of more expensive engine parts or more frequent maintenance, this could be easily justified according to the economics.

C. COST TO PRODUCE ENGINE-GRADE COAL FUELS

An essential ingredient in the future of coal-fueled diesels is the eventual emergence of a price advantage of the engine-grade coal fuel. Recognizing that (a) fuel oil and natural gas prices will almost certainly rise by 1995-2000, and (b) the extent and timing of the oil price increase is virtually unpredictable, we focussed our attention on the coal slurry fuel cost and how it might be reduced as much as possible. Our findings are based on detailed inputs from AMAX and other leading manufacturers of coal slurries. Key parameters were as follows:

- Physical cleaning (resulting in a 1.0-1.5% ash product) is now assumed to be sufficient for the CWS to be compatible with the Cooper-Bessemer engine. This eliminates expensive chemical cleaning steps.
- Dedicated engine-grade slurry facility; plant incorporates cogeneration using reject char and oversize coal.
- Plant capacity: 1.8 million tons per year (supports 100 engines at 5 MW, operating at 80% load factor)
- Capital cost of plant: \$78 million
- Typical coal price: \$1.81 per million Btu, delivered to slurry plant (includes \$.57/MMBtu for transportation cost (\$0.273/ton-mile for 590 miles) plus \$34.50/ton for minemouth coal).
- Electricity cost: \$0.04 kWh, 175 kWh/ton.
- Total operating cost of plant: \$0.57/MMBtu (excludes amortized capital cost)
- Capital recovery costs: 10% interest/12 year payback.

- Assume process development costs are already paid off, so that the plant costs are for the "nth plant." Here it is assumed that the R&D investment in coal cleaning technology by AMAX, Otisca, or other slurry suppliers will be fully recovered by the time the first two or three plants reach full capacity.

The results of this analysis indicate that engine grade slurry will cost about \$2.90 per million Btu (which is about \$1.10/MMBtu more than the source coal). "Low" and "high" estimates for the CWS cost are \$2.50 and \$3.70 per million Btu (these estimates correspond to 50% less and 100% greater overall coal cleaning cost).

There are two areas where further process developments could reduce the cost of engine-grade slurries: First, the additives and reagents which currently account for about 30% of the slurry cost have not been optimized. These additives and reagents are needed to keep the coal particles in suspension and to tailor viscosity. Second, further effort is needed to identify lower cost slurry formulations which are compatible with the engine.

D. COST OF EMISSION CONTROL SYSTEMS

Based on PSI's design and cost estimates reported in Section V, we selected four emission control design options for further study as part of the overall plant economics. Table VI-3 summarizes these designs and gives the basic capital and operating costs for each option.

Table VI-3
EMISSIONS CONTROL SUBSYSTEM COSTS

System			Plant Configuration				
			Cogen 1x6 Cyl 1.8 MW	Cogen 4x6 Cyl 7.2 MW	Cogen 2x20 Cyl 12 MW	Power 2x20 Cyl 12 MW	Cogen 4x20 Cyl 24 MW
A	SCR; spray dryer	Capital \$MM	1.742	3.649	4.949	5.053	8.052
		Oper. \$/kWh	0.030	0.019	0.015	0.016	0.014
		Total \$/kWh	0.053	0.031	0.025	0.026	0.022
B	Reburning; sorbent inj.	Capital \$MM	0.411	0.987	1.18	1.335	2.176
		Oper. \$/kWh	0.015	0.007	0.005	0.015	0.004
		Total \$/kWh	0.020	0.010	0.007	0.018	0.006
K	SCR; sorbent inj.	Capital \$MM	0.808	1.957	2.866	2.947	5.114
		Oper. \$/kWh	0.025	0.018	0.015	0.015	0.014
		Total \$/kWh	0.036	0.024	0.021	0.021	0.019
L	Reburning; spray dryer	Capital \$MM	1.36	2.662	3.299	3.453	5.133
		Oper. \$/kWh	0.019	0.010	0.007	0.016	0.004
		Total \$/kWh	0.037	0.019	0.014	0.023	0.009

E. PROJECTED COST OF COAL-FUELED DIESEL POWER

Based on the individual cost premiums for installing and operating a diesel engine designed for coal fuel, it is possible to project the total cost of power and determine the relative importance of each economic parameter. Our key findings from this analysis can be presented in the form of Table VI-4, which lists the elements which contribute to the cost of power. Note that the coal engine designer can afford to consider more expensive components if that results in an engine which tolerates lower cost coal fuel. Also note that the coal-fueled engine is projected to be competitive with the standard diesel at \$5.50/MMBtu fuel oil price.

Table VI-4

PROJECTED COST OF POWER FOR COAL-FUELED DIESEL PLANT

Cost Element	Coal Fueled		Gas or Oil Fueled	
	\$/kWh	Cost (6 MW Engine)	\$/kWh	Cost (6 MW Engine)
Engine capital cost (installed)	.0121	\$5.2 million	.0081	\$3.5 million
Maintenance and overhaul	.0052	\$3.9 million over 20 years	.0019	\$1.4 million over 20 years
Emissions control	.0219	\$2.50/MMBtu	.0032	\$0.37/MMBtu
Engine Fuel (delivered); including:	.0253	\$2.90/MMBtu; including	.0481	\$5.50/MMBtu for natural gas or fuel oil
- Slurry processing		\$0.80/MMBtu	-	
- Raw coal; transportation		\$1.81/MMBtu	-	
- Slurry transportation		\$0.29/MMBtu	-	
Total Cost of Power	.0645		.0613	

Key Assumptions: Heat rate 8,754 Btu/kWh, 80% load factor, and 90% availability. Future oil or natural gas price \$5.50/MMBtu.

It is clear from our analysis (see Table VI-4) that the most important parameters are the cost to clean the coal fuel and the emissions control, which essentially dominate the economics. If engine-grade slurry costs can be brought below \$2/million Btu above the source coal, then the coal diesel can probably be competitive with diesel fuel by the late 1990's, given long-range oil and natural gas price trends.

F. PARAMETRIC SENSITIVITY ANALYSIS

A series of runs using the economic model revealed which parameters were most sensitive in calculating the cost of power for a coal-fueled diesel plant. These runs also defined the circumstances under which the coal-diesel option would be most attractive economically. The following parameters were explored:

- Source coal and type of CWS process
- Distance from source coal to power plant
- Type of emission control system
- Size and type of power plant (12 MW, 24 MW power only or cogeneration, etc.)
- Load factor
- Natural gas and oil price

The effect of source coal on the economics is shown in Table VI-5. Note that the Blue Gem source coal can be physically cleaned and delivered at \$2.56/MMBtu for the Atlanta market. If shipped across the U.S. to Phoenix, the same Blue Gem based CWS would carry a price tag of \$4.11/MMBtu (because of the added transportation cost). The other three source coals in Table VI-5 must be chemically-cleaned to yield an engine grade slurry, and this is reflected in the higher prices. For example, if Kentucky Hazard coal is used in Atlanta, the slurry cost increases about 60% and the cost of power increases 25% (from \$.0604 to \$.0751/kWh).

Table VI-5
COST OF POWER DEPENDS ON SOURCE COAL AND CWS PROCESS

Source Coal	CWS Process		Phoenix		Atlanta	
			CWS Cost	Cost of Power	CWS Cost	Cost of Power
Blue Gem (KY)	Physically Cleaned	Delivered coal	\$3.30	\$0.0740/kWh	\$1.76	\$.0604/kWh
		Process cost	<u>0.82</u>		<u>.80</u>	
		Total	4.11		2.56	
Castlegate (Utah)	Chemically Cleaned	Delivered coal	1.27	\$0.0757/kWh	-	-
		Process cost	<u>2.96</u>			
		Total	4.23			
Illinois #5	Chemically Cleaned	Delivered coal	2.01	\$.0894/kWh	-	-
		Process cost	<u>3.01</u>			
		Total	5.82			
Hazard (KY)	Chemically Cleaned	Delivered coal	-	-	\$1.53	\$0.0751/kWh
		process cost			<u>2.70</u>	
		Total			4.23	

Basis: 12 MW cogen, Configuration K, \$5.50/MMBtu gas price

The effect of coal transportation has only a 5-10% impact on the cost of power, as shown in Table VI-6. For Blue Gem source coal, which is transported from Kentucky, the lowest power cost is for Chicago (\$.0627/kWh for the SCR/spray dryer plant design). This increases by \$.0081/kWh for the extreme case of transporting Kentucky coal to Phoenix, Arizona.

Table VI-6 also illustrates that the choice of emission control technology has a large impact on cost of power. Two extreme cases are compared, the most expensive, off-the-shelf emission technology (Option A) and the least expensive emission technology (Option B) which is actually still in the R&D phase. Note that the use of Option A raises the cost of power about 25% compared to Option B for all cities, for the 12 MW cogeneration plant. For straight power plants, where the use of reburning in Option B imposes a net fuel cost, the difference between Option A and Option B is only about 10%, as shown in Table VI-7. This is still a significant difference, and underscores the importance of further R&D on emission control system alternatives (particularly those which are less expensive than SCR for NO_x control and the spray dryer for SO_x control.

Note that the power costs in Tables VI-6 and VI-7 were given for 12 MW plants. This is because smaller plants (7.2 MW or 1.8 MW) are less attractive economically, because of the fixed expenses associated with emission control systems. In fact, PSI's analysis indicates that the emission control costs alone would be as high as \$.05/kWh for a 1.8 MW plant (one 6-cylinder coal diesel). Therefore, the emission control system would double the cost of power for a 1.8 MW plant; this would almost certainly be unacceptable. Figure VI-1 illustrates the effect of plant size on emission control costs. Effectively, this important conclusion eliminates many smaller cogeneration sites from future market consideration. However, other smaller cogeneration systems may not require the full 90% NO_x reduction built into this design package.

Table VI-6
COAL TRANSPORTATION TO VARIOUS CITIES AFFECTS COST OF POWER BY 5-10%

	Emission Control System	
	Baseline System - SCR/Spray Dryer (A)	Low Cost System - Reburn/ Sorbent (B)
Atlanta	\$.0632/kWh	\$.0489/kWh
Boston	.0678	.0535
Chicago	.0627	.0484
Phoenix	.0708	-
Salt Lake	.0682	.0539
Pittsburgh	.0605	.0461

Basis: Blue Gem, Physical Cleaning, 12 MW Cogen

Table VI-7

CHOICE OF EMISSION CONTROL SYSTEM AFFECTS COST OF POWER
(Reburning is particularly attractive for cogen plants)

Emissions Systems	12 MW Power	12 MW Cogen
SCR/Spray Dryer (A)	\$.0639/kWh	\$.0627/kWh
Reburn/350°F Sorbent (B)	.0586	.0484
SCR/350°F Sorbent (K)	.0605	.0604
Reburn/Spray Dryer (L)	.0620	.0529

Basis: Chicago, Blue Gem

The impact of load factor is significant, but not as important as other parameters such as slurry cost or emissions control. Table VI-8 illustrates that as load factor swings from 65% to 95%, the cost of power goes from \$.0684/kWh to \$.0592/kWh. While the total difference is about 15%, the variation around cost of power for the standard assumption of 80% load factor is only about $\pm 7\%$.

Table VI-8

INCREASED LOAD FACTOR CAN LOWER POWER COSTS BY ABOUT 5-10%

Load Factor	Coal Diesel with SCR/Spray Dryer (Config. A)
65%	\$.0684/kWh
80% (STD)	\$.0627/kWh
95%	\$.0592/kWh

Basis: Chicago, Blue Gem, 12 MW Cogen

Another important parameter is the engine efficiency associated with coal fuel. Based on the JS test results, our best estimate is that the coal engine efficiency will be 39%, identical to the standard Cooper engine. The penalty derived from slurry water evaporation (2-3%) appear to be compensated by faster heat release and other thermodynamic processes.

Table VI-9 shows the uncertainties assigned to each of seven key assumptions. For most assumptions, our uncertainty bounds are narrower (i.e., confidence level has increased) since 1988.

Figure VI-1. Emission Control Costs Appear Acceptable Above About 7 MW Plant Size

Table VI-9
UNCERTAINTY LEVEL

VII. TECHNOLOGY GAPS AND HIGH PRIORITY R&D DIRECTIONS

This preliminary design for a coal-fueled diesel engine power plant has revealed not only the most critical components or subsystems but also certain critical information about these components which is missing or poorly understood. Figure VII-1 summarizes our current priorities. In planning our R&D for the balance of Phase I and Phase II, we can focus on these critical "technology gaps":

Emissions Control

1. In-cylinder NO_x control: NO_x can be lowered by up to 50% by reduced air temperature, timing of injection, prechamber for staged combustion, or piston shape.
2. Low-cost SCR for NO_x control: the available SCR systems are very costly below 10 MW engine size; further R&D may correct this.
3. SNR for NO_x control at engine exhaust temperature (850°F): current SNR agents are not effective at this condition and further R&D is needed.
4. Small scale SO₂-capture and baghouse modules: exhaust treatment will certainly be needed for SO_x and particulate control. Appropriate exhaust treatment technologies exist for larger boiler plants, and the development strategy will require scaling these down to the 2-20 MW size of the engine.
5. Low-emission coals: emissions control R&D strategies must exploit the source coal selection and cleaning process as much as possible. For example, the specific clean coal formulation affects both NO_x and SO_x levels through fuel nitrogen and sulfur content.
6. The cost of emission control is also critical to the economic viability of this technology. Target costs are about one cent per kWh. An important remaining effort will be to design and develop the emissions control technology to accomplish the required emission reductions at reasonable projected installed and operating costs. Test results indicate that over 70% NO_x and SO_x reduction will probably be required along with over 99% particulate capture.

Durable Engine Components

1. Cost of critical parts: further development work will allow Cooper to better define the probable cost of coal tolerant parts. This system study suggests that there is room for increased parts cost if this results in either lower CWS cost or emission cost.
2. Injector tip replacement: the systems study showed a \$1.0 million cost of injector tips over 20 years of engine operation. Can the replacement interval be increased over 500 hours? Can the tip cost be reduced below \$160? The nozzle wear R&D strategy will involve not only hard materials for nozzle tips but also lower injection pressures and modified orifice geometry.
3. Turbocharger durability: the turbocharger has been given a premium of \$400,000 for hardened parts. Further R&D is needed to determine the actual severity of the wear problem.

Figure VII-1
Coal-Fueled Diesel R&D Priorities

4. Multi-cylinder fuel system: AMBAC must design and develop a dual-fuel injection system capable of either DF2 or coal-water slurry operation.
5. Ring and liner durability: further R&D is needed to define the overhaul interval (the current target is 25000 hr.) and the cost of hard rings and liners.

CWS Process R&D Priorities

- Engine tolerance for higher ash slurry: the AMAX cleaned engine-grade coal-water fuel up to 1.5 ash proved to be an excellent starting point, and gave us no significant problem during the JS engine tests. This leads us to the issue of whether the engine will accept a lower cost, lower grade coal slurry fuel formulation.
- AMAX cleaning process modifications: the actual process steps need more R&D to determine the efficiency and throughput rates that are feasible.
- Cleanability of source coals: to date, very few coals have been tested for cleanability in the AMAX process, with or without the chemical step. Further R&D is needed.
- Additives package: the cost of the additives is significant and there is room for fine tuning in this area.
- Power cost and merits of cogeneration: this is an area of uncertainty in the AMAX cost model.

VIII. COMMERCIALIZATION PLAN AND PROJECTED PENETRATION RATE

Table VIII-1 illustrates the commercialization plan and shows the ongoing program in this perspective. Following the 100-hour proof-of-concept test in 1992, Cooper-Bessemer will further develop the coal-fueled engine to meet more stringent targets (1000 hour maintenance interval on injection system, for example). Current technology allows diesel (noncoal) engines to operate at greater than 92% availability at full load operation. The key to achieving this level of availability is the development and implementation of a preventative maintenance program to maintain those parts with a lesser life at intervals that preclude unscheduled breakdown. This same philosophy of development would be applied to the coal engine. The multicylinder version will be designed and a prototype four-cylinder or six-cylinder will be built and tested. The first installation on a customer site is targeted for 1994. This will initiate field demonstration.

During the ten-year period, 1995-2005, Cooper will plan to introduce coal-fueled diesel systems into selected customers' sites, both new and retrofit installations. Basic development and integrated testing will occur in the R&D laboratory, however, the physical size of the medium speed engine precludes exhaustive testing in the laboratory environment. Therefore, the Cooper approach in the sale of initial models of new units and of conversion kits is to enlist the cooperation of customers and to establish an aggressive field follow-up support program to solve problems that are not evident in the laboratory in order to achieve the desired service life between maintenance intervals. We assume total sales of coal diesels will increase to the level of about 100 MW/year by the year 2005, based on the assumptions that cogeneration and IPP/small utility installations of reciprocating engines will occur as projected in Tables III-9 and III-10 for the period 1995-2005. The commercialization plan is designed so that the coal diesel will be proven and in position to capture a small share of these by the 2000-2010 timeframe. This will grow to approximately 110 engines per year by the year 2010-2015.

Other engine manufacturers will follow suit and, if necessary, license the technology from Cooper. Years 2005-2015 define the time period when the coal diesel system may become widely used both by utilities for modular power and by industries for cogeneration. Based on Cooper's dominant position in the U.S. large stationary engine market for the last 40 years, it is reasonable to assume that 40% of all coal diesel systems produced from year 2005 to 2015 will be produced by Cooper-Bessemer. This may represent 60-110 large stationary coal engine systems per year (see Table III-10).

Table VIII-1
Cooper-Bessemer Commercialization Plan for Coal Fueled Diesel

REFERENCES

Chapter III

1. Mottley, Mycoff, and Gumz, "U.S. Generation in the 1990's," Westinghouse, 1988.
2. Annual Energy Outlook, January 1990, pg. 46.

Chapter IV

1. Bhasin, A.K., Et al., "Chemical Coal Cleaning Process and Costs Refinement for CWS Manufacture," December 31, 1985 DOE Contract #DEAC21-83-MC20700, DOE Report #DOE/MC/20700.
2. Perry and Chilton, "Chemical Engineering Handbook," Fifth Edition.
3. Hagy, John, Personal Communication, Fort Pitt Machine Company.
4. Quotation from Dreyss Corporation.

Chapter V

1. Rao, A.K., Melcher, C.H., Wilson, R.P., Balles, E.N., Schaub, F.S., and Kimberly, J.A. (1988), "Operating Results of the Cooper-Bessemer JS-1 Engine on Coal-Water Slurry" presented at the Energy-Sources and Technology Conference, New Orleans, Louisiana.
2. Salimian, S. and Hanson, R.K. (1980), "A Kinetic Study of NO Removal from Combustion Gases by Injection of NHi-Containing Compounds", Comb.Sci.Tech. 23:225.
3. Markansi, J. (1988), "Reducing NOx Emissions", Power (September, 1988).
4. Caton, J.A. and Siebers, D.L. (1988), "Reduction of Nitrogen Oxides in Engine Exhaust Gases by the Addition of Cyanuric Acid", in Engine Emissions Technology for the 1990's (K.J. Springer ed.), American Society of Mechanical Engineers, New York.
5. Wasser, J.H. and Perry, R.B. (1987), "Diesel Engine NOx Control: Selective Catalytic Reduction and Methanol Emulsion", presented at 1987 Joint Symposium on Stationary Combustion NOx Control. New Orleans, Louisiana.
6. Mochida, I., Ogaki, M., Fujitsu, H., Yoshinobu, Y., and Ida, S. (1983), "Catalytic Activity of Coke Activated with Sulphuric Acid for the Reduction of Nitric Oxide", Fuel 62:867.
7. Davini, P. (1988), "Reduction of Nitrogen Oxides with Ammonia: the Activity of Certain Soots", Fuel 67:24.
8. Faucett, H.L., Maxwell, J.D., and Burnett, T.A. (1977), Technical Assessment of NOx Removal Processes for Utility Applications EPA-600/7-77-127.

9. Wilson, C., Cooper, J., and Placer, F. (1987), "Performance Evaluation of a Screenless (Counter-Current) Granular Bed Filter on a Subpilot-Scale PFBC" in Proceedings of the Seventh Annual Gasification and Gas Stream Cleanup Systems Contractors Review Meeting DOE/METC/-87/6079, Vol. I.
10. Meyer, J.H., Westervelt, D., and Anestis, T. (1987), "Evaluation of a Ceramic Cross-Flow Filter in a Bench-Scale Gasifier" in Proceedings of the Seventh Annual Gasification and Gas Stream Cleanup Systems Contractors Review Meeting DOE/METC/-87/6079, Vol. I.
11. McElroy, M.W. (1977), "Oklahoma Gas and Electric Full-Scale Demonstration of NO_x Destruction in Fuel-Rich Burners", EPRI Program RP-782, Palo Alto, California.
12. Yang, R.J., Arand, J.K., and Garcia, F.J. (1984), "Laboratory Evaluation of In-Furnace-NO_x-Reduction for Industrial Combustion Applications", ASME Paper 84-JPGC-FU-12, October.
13. Bortz, S.J., Roman, V., and Offen, G.R. (1988), "Hydrate and Process Parameters Controlling SO₂ Removal during Hydroxide Injection Near 1000°F", presented at First Combined FGD and Dry SO₂ Control Symposium, St. Louis, Missouri.
14. Simons, G.A., Ham, D.O., Parker, T.E., Morency, J.R., Moniz, G., and Boni, A.A. (1987), "Alternative SO₂ Sorbents", PSI Technical Report TR-744.
15. Muzio, L.J. and Sonnichsen (1983), "Dry SO₂-Particulate Removal for Coal-Fired Boilers, Volume 1: Demonstration of SO₂ Removal on a 22-MW Coal-Fired Utility Boiler by Dry Injection of Nahcolite", EPRI Report CS-2894, Volume 1.
16. LeCren, R.T., Hanson, A.M., and Hendrix, H.L. (1988), "Environmental Control Systems in Coal-Fueled Gas Turbines: Solar Turbines Technical Progress Report," presented at Annual Coal Fuel Heat Engines and Gas Stream Cleanup Systems Annual Contractors Review Meeting sponsored by DOE, Morgantown Energy Technology Center.
17. Electric Power Research Institute (1982), Technical Assessment Guide, EPRI Report No. P-2410-SR.
18. Vatauvuk, W.M. (1984), "Control Costs" in Handbook of Air Pollution Control Technology (S. Calvert and H.M. Englund, eds.), John Wiley and Sons, New York.
19. Peters, M.S. and Timmerhaus, K.D. (1980), Plant Design and Economics for Chemical Engineers, McGraw-Hill, Inc., New York.
20. Ciliberti, D.C., Smeltzer, E.E., Alvin, M.A., Keairs, D.L., and Bachovchin, D.M. (1983), Hot Gas Cleanup Using Ceramic Cross Flow Filters, Final Report, DOE/METC-85/6025.
21. Wilson, R.H. (1984) Arthur D. Little, Inc. and Southern California Gas, personal communication.

22. Wilson, R.H. (1987) Arthur D. Little, Inc., personal communication.
23. Swann, D.R. and Drissel, G.D. (1980), Feasibility of Retrofitting Catalytic Postcombustion NO_x Control on an 80-MW Coal-Fired Utility Boiler, EPRI Report No. CS-1372.
24. Wilson, R.H. (1987) NESCAUM Workshop on Cogeneration and Emission Control.
25. Rubow, L.N., Border, M., Buchanan, T.L., Cramp, J.A.C., Fischer, W.H., Klett, M.G., Maruvada, S.M., Nelson, E.T., Weinstein, R.E., and Zuharchuk, R. (1984), Technical and Economic Evaluation of Ten High-Temperature, High-Pressure Particulate Cleanup Systems for Pressurized Fluidized-Bed Combustion, DOE/MC/19196-1654. New Source Performance Standards for Stationary Sources

APPENDIX A
CWS PLANT EQUIPMENT LISTS

Table A1
EQUIPMENT LIST AREA 100 - UNLOADING & STORAGE

Item Description	Total Power Requirement (HP)	Total Cost (\$1,000)
Rail Siding	--	472
Thaw Shed	--	115
Load-Out Scale	2	39
Sampler	5	5
Storage Piles	--	-
Conveyors	50	67
Vibrating Feeder	3	133
Reclaim Pit	--	129
Dozers	--	300
Subtotal		<u>1,260</u>
Delivery & Taxes (@ 4%)		50
TOTALS	60	1,310

Table A2
EQUIPMENT LIST, AREA 200 - CRUSHING

Item Description	Total Power Requirement (HP)	Total Cost (\$1,000)
Storage Bin	--	24
Vibrating Feeder	3	10
Scalping Screen	25	21
Hammer Mill	150	144
Feed Conveyors	5	17
Product Conveyors	5	40
Conveyor Scale	2	16
Subtotal		272
Delivery & Taxes (@ 4%)		11
TOTALS	190	283

Table A3
EQUIPMENT LIST, AREA 300 - GRINDING

Item Description	Total Power Requirement (HP)	Total Cost \$ (\$1,000)
Mill Feed Bin	--	24
Apron Feeders	5	40
Rod Mill	--	870
Rod Mill Motor	1600	159
Rod Mill Starter	--	50
Rod Mill Charge	--	88
Slurry Sump	--	60
Subtotal	1605	1,291
Delivery & Taxes (@ 4%)		52
TOTALS	1605	1,343

Table A4
AREA 400 - PHYSICAL CLEANING (COLUMN FLOTATION)

Item Description	Total Power Requirement (HP)	Total Cost (\$1,000)
Frother Tank	--	25
Frother Pump	30	1
Collector Tank	--	19
Collector Pump	30	2
Conditioner	--	375
Conditioner Pump	50	3
Column Flot Cells	--	250
Blowers	--	70
Filters	--	--
Conveyors	50	--
Recycle Sump Pump	100	70
Thickener	--	--
Subtotal		815
Delivery & Taxes		33
TOTALS	260	848.

Table A5

EQUIPMENT LIST, AREA 400 - PHYSICAL CLEANING (HEAVY MEDIA)

Item Description	Total Power Requirements (HP)	Total Cost (\$1,000)
Heavy Media Plant	222	979.
Subtotal		<u>979</u>
Delivery & Taxes		39
TOTALS	222	1,018.

Table A6
Equipment List, Area 500, Caustic Leach and Filtration

Description	Number Required	Total HP	Total Cost (\$1,000)
Feed Slurry Mix Tank, 58,700 gal/each - CS	2	-	70
Feed Slurry Tank Agitator - CS	2	120	68
Recycle Caustic Tank, 42,300 gal - CS	1	-	34
Recycle Caustic Transfer Pump, 350 gpm - CS	1	15	4
Caustic Storage Tank, 476,000 gal - CS	1	-	89
Caustic Feed Pump - Piston, 45 pgm	1	30	75
High Pressure Feed Pump 1,530 gpm Total	2	1,200	760
Heat Exchanger - Stage 1, 2, 910 ft ² Total, Inconel Tubes - CS Shell	4	-	210
Heat Exchanger - Stage 2, 3,280 ft ² Total, Inconel Tubes - CS Shell	4	-	237
Heat Exchanger - Stage 3, 3,260 ft ² Total, Inconel Tubes - CS Shell	4	-	237
Autoclave, 12' ID x 78' long, Refractory Lined	1	-	930
Agitators, Autoclave, 5HP Inconel	6	30	346
1st Flash Vessel/Steam Separator - Inconel Clad	1	-	187
2nd Flash Vessel/Steam Separator - Inconel Clad	1	-	156
3rd Flash Vessel/Steam Separator - Inconel Clad	1	-	123
Slurry Cooler, 1,000 ft ² - CS	1	-	28
Filter Feed Tank, 32,000 gal - CS	1	-	30
Filter Feed Tank Agitator	1	30	17
Filter Feed Pump, 1,420 gpm, Centrifugal	1	150	16
Filter Presses, 76,460 ft ² , Polyprop	12	120	6,000
Cake Conveyors, 3' x 45'	12	36	422
Transfer Conveyors, 3' x 90'	2	10	95
Elevating Conveyor, 3' x 60'	1	5	48
Delivery and Taxes, 4%		—	407
Total		1,746	10,593

Table A7
Equipment List, Area 600, Acid Leach and Filtration

Description	Number Required	Total HP	Total Cost (\$1,000)
Acid Leach Tanks, 8,500 gal each	4	-	241
Leach Agitators	4	60	78
Filter Feed Pumps, 1,410 gpm - RL	2	100	32
Acid Storage Tank, 1,330,000 gal	1	-	382
Acid Pump, 135 gpm	1	5	3
Filter Presses, 57,340 ft ² , Polyprop	9	90	4,500
Cake Conveyors, 3' x 45'	9	21	316
Transfer Conveyor, 3' x 200'	1	10	122
Tripper Conveyor, 3' x 40'	1	5	54
Delivery and Taxes, 4%			<u>229</u>
Total		291	5,957

Table A8
Equipment List, Area 700, Hot Wash and Filtration

Description	Number Required	Total HP	Total Cost (\$1,000)
Mix Tanks, 62,000 gal/each - RLCS	2	-	224
Mix Tank Agitator - RL	2	100	76
High Press Slurry Pump, 1,540 gpm Total	2	800	805
Heat Exchanger - Stage 1, 2,910 ft ² Total, Ti-Gr 7 - GS Shell	4	-	210
Heat Exchanger - Stage 2, 3,280 ft ² Total, Ti-Gr 7 - CS Shell	4	-	237
Heat Exchanger - Stage 3, 3,260 ft ² Total, Ti-Gr 7 - CS Shell	4	-	237
Autoclave, 12' ID x 78' long, Refractory Lined	1	-	1,550
Autoclave Agitators, Ti-Gr 7, 5 HP each	6	30	378
1st Flash Vessel/Steam Separator	1	-	199
2nd Flash Vessel/Steam Separator	1	-	166
3rd Flash Vessel/Steam Separator	1	-	132
Slurry Cooler, 1,000 ft ² , Ti-Gr 7	1	-	72
Filter Feed Tank, 32,000 gal - RLCS	1	-	46
Filter Feed Tank Agitator, 30 HP	1	30	17
Filter Feed Pumps, 1,380 gpm - RL	2	100	32
Filter Presses, 57,340 ft ² , Polyprop	9	90	4,500
Cake Conveyors, 3' x 45'	9	27	316
Transfer Conveyor, 3' x 230'	1	10	141
Ammonia Storage Tank, 14' diameter x 75' - CS	1	-	120
Delivery and Taxes, 4%			378
Total		1,187	9,837

Table A9

EQUIPMENT LIST, AREAS 800 and 900 FOR GRINDING AND FORMULATION

Item Description	Total HP	Total Cost (\$1,000)
Mix Tanks	--	70
Mix Tank Agitator	120	68
Dispersant Storage Tank	--	70
Dispersant Feed Pump	7.5	1
Stirred Ball Mills with feed Pumps	16,000	8,000
Mix Tank Feed Pumps & Sumps	150	36
Stabilizer Mix Tanks	--	110
Stabilizer Mix Tank Agitators	120	68
Stabilizer Storage Tank	--	90
Stabilizer Feed Pump	5	2
Formaldehyde Storage Tank	--	7
Formaldehyde Feed Pump	1	2
Subtotal		<u>8,527</u>
Delivery and Taxes, 4%		349
Total	16,403.5	8,876

TABLE A10
EQUIPMENT LIST, AREA 1000, PRODUCT STORAGE AND LOAD-OUT

Item Description	Total HP	Total Cost (\$1,000)
Product Storage Tanks	--	1,845
Product Storage Tank Agitators	600	1,100
Product Delivery Pumps	750	142
Product Delivery Pumps	200	214
Subtotal		<u>3,301</u>
Delivery and Taxes, 4%		132
Total	1,550	3,433

Table A11

Equipment List, Area 1100, Caustic and Heat Recovery and Waste Neutralization

Description	Number Required	Total HP	Total Cost (\$1,000)
Modifier Hopper, 21,400 cu ft - CS	1	-	16
Modifier Feeder (Weigh)	1	1.25	12
Lime Hoppers, 25,000 cu ft Total - CS	2	-	105
Lime Feeders (Weigh)	2	2.5	24
Precipitation Tanks	4	-	89
Precipitation Tank Agitators	4	40	41
Milters, 5,310 ft ²	2	20	683
Discharge Conveyors, 3' x 45'	2	6	70
Caustic Evaporation System*	1	5	1,600
Neutralization Tanks, 173,000 gal/each - RL	3	-	318
Neutralization Tank Agitators - RL	3	600	285
Neutralization Waste Pump, 9,000 gpm Total - CS	3	300	35
Delivery and Taxes, 4%			
		974.75	3,412

*Installed cost

Table A12
Equipment List, Area 1300, Utilities

Description	Number Required	Total HP	Total Cost (\$1,000)
Compressors-Centrifugal, 1,000 HP	4	4,000	667
Recycle Water Tank, 30' diameter x 24' h	1	-	50
Recycle Water Pump, 2,500 gpm	1	200	17
Heat Recovery Exchangers, 13,500 ft ² Ti & CS	-	-	212
Heat Recovery Exchangers, 27,000 ft ² - CU & CS	-	-	447
Heat Recovery Pumps, 1,000 gpm each	8	370	90
Delivery and Taxes, 4%			62
Cogeneration Plant*		<u>2,000</u>	<u>44,000</u>
Total		6,570	45,545

*Installed included building

APPENDIX B
CWS PROCESS COST MODEL

COST MODEL CONFIGURATION

The cost model consists of a set of automated spread sheets. Each spread sheet contains information which is used to feed costs into the two output spread sheets, the capital and operating cost summaries. Figure 2 shows how the model uses various inputs and assumptions to carry out the calculations necessary for the capital and operating case summaries. By altering the input information, it is very easy to perform sensitivity analyses.

User Defined Variables

Each case evaluation requires input data from the user for use in the calculations. These variables are user defined variables, and they must be updated before each case is run. The variables are related to the fuel specification, production rate, and market location. A list of user defined variables are shown below:

<u>Requested Information</u>	<u>Typical Data Set</u>
Raw Coal :	
Coal Type	Seam Name
Coal Purchase Price	\$/Ton
Moisture in Coal	Wt%
Sulfur in Coal	Wt%
Ash in Coal	Wt%
Btu Value	HHV
Slurry Plant :	
Plant Location	City Name
Distance from :	
Mine	Miles
User Site	Miles
Capacity	Tons/yr
Chemical Cleaning	Yes/No
Final Grinding	Yes/No
Fuel Specification :	
Particle Top Size	um
Ash Content	Wt%
Sulfur Content	Wt%
Viscosity	cp @ 1000 sec ⁻¹

These inputs do not have defaults and must be updated for each case evaluation. Adjusting an input, such as plant capacity, will adjust the capital and operating costs of the plant and allow comparison with different size facilities producing the same fuel in different quantity. Similar variable evaluations can be performed with other inputs, making single variable impact sensitivity possible.

Figure 2. Model Operation Flow Sheet

The following section describes how the automated spread sheets work together to estimate the capital and operating costs for a slurry preparation plant.

Defined Model Assumptions

Certain calculations relating to capital, processing, operating, and indirect costs contain default assumptions. These assumptions are defined in the spread sheet and can be altered if desired. The assumptions are not part of the normal user inputs and must be accessed separately by the user. Most of the assumptions are factors which form the basis for the capital and operating costs. Equipment sizing and selection are not contained in the assumptions and are inflexible to user alteration. The assumptions are listed in Table 1.

Material balances and costs included for operation of the plant were based upon 7,884 hours of operation per year. This is derived by using a 90 percent on stream factor and 365 day-per-year, round-the-clock operation.

Capital cost factors are taken from AMAX experience with similar plants and cross checked with current construction estimation manuals. Building costs are based upon equipment-layout drawings and on internal AMAX cost files. Engineering fees and indirect costs are also based upon AMAX experience.

Processing factors are based upon pilot plant operation experience. The processing factors can be altered for different coals or processing unit applications if desired. A middling credit is included in case a credit is taken for the down grade material from the physical separation step. This credit is used mainly for heavy media separation rather than column flotation.

Operating cost factors include maintenance, freight, and utilities. The factors are derived from operating experience at AMAX processing plants and from specific transportation and utility rates for the market location. The values shown in Table 1 are examples of rates used for the Pittsburgh market area.

Indirect cost factors include cost of operation pertaining to overhead, profit, and administration. These cost factors are determined by the user and are very specific to the particular case being investigated. It is important to review the indirect cost factors before comparing fuel costs to ensure they are on the same basis.

Calculations

Capital and operating cost calculations are performed by the model, utilizing the inputs and assumptions described previously. Each of the thirteen areas of the plant have separate equipment capital and operating cost equations. The capital cost equations include a size factor or step functions depending upon the type of equipment and the size range. Operating cost equations utilize input information including labor rates, plant capacity, coal cost, transportation cost, and chemicals.

A review of the capital cost summary sheet and the operating cost summary sheet helps define the various calculations included in the cost model. These summary sheets are presented in Tables 3 and 4. The scenario which is presented in these tables represents the base case conditions for a plant in Pittsburgh Pennsylvania. The base case conditions are:

- Medium Quality Fuel
 - 1.0 % ash in the coal
 - 74 micron top size particles
 - 1.0 % sulfur
 - 400 cp at 100 sec⁻¹
- 1.25 million tons per year dry coal in slurry
- Coal feedstock which requires physical separation to achieve the desired fuel quality

Capital Cost Summary for CWS Fuel Plant

Plant Location: PITTSBURGH

Local Type: Blue Gem

Capacity: 1.25 Million T/Y (Coal in Fuel)

Raw Coal Characteristics:

6 Percent Moisture
2 Percent Ash
0.7 Percent Sulfur
14,042 HHV (Btu/lb)

Slurry Fuel Specifications:

74 um Top Size
1 Percent Ash
1 Percent Sulfur
MED Viscosity
35% Solids

*No Finish Grinding or Chemical Cleaning Required

<u>Item</u>	<u>Cost, \$ Million</u>
A. Subtotal Delivered Equipment Cost	13.971
Unloading & Storage	1.333
Crushing	0.389
Initial Grinding	2.019
Physical Cleaning	1.325
Caustic Leach & Filtration	0.000
Acid Leach & Filtration	0.000
Hot Water Wash & Filtration	0.000
Fine Grinding	0.000
Slurry Preparation	0.000
Storage & Load Out	3.644
Caustic Regeneration	2.917
Waste Treatment & Disposal	0.704
Utilities	1.641
B. Less Modularized Equipment Cost	<u>- 3.518</u>
C. Bare Delivered Equipment Subtotal (A-B)	10.453
D. Installation (24.8% of C)	2.592
E. Instrumentation (25.5% of C)	2.665
F. Piping (75.9% of C)	7.934
G. Electrical (33.5% of C)	3.502
H. Paint and Insulation (6.6% of C)	<u>0.690</u>
I. Subtotal (A+D+E+F+G+H)	31.354
J. Building	10.443
K. Land and Site Development	1.451
L. Rail and Road Facilities	<u>1.710</u>
M. Total Field Cost (I+J+K+L)	44.958
N. Engineering and Fees (13.8% of M)	6.204
O. Indirect Costs (18.3% of M)	8.227
P. Subtotal Construction Cost (M+N+O)	59.389
Q. Contingency (20% of P)	11.878
R. Total Capital Cost (P+Q)	71.267
S. Working Capital (10% of R)	7.127
T. Final Total Capital Cost (R+S)	78.894

Capital Cost Summary Sheet

Each of the costs found in the capital cost summary sheet are described below:

Item A

The total delivered equipment cost is presented for each of the areas included in the flowsheet. Equipment is first selected based upon fuel quality requirements and then sized based upon plant production rates. A cost is assigned to each piece of equipment based upon information taken from AMAX internal files or equipment costing information such as Richardson Process Plant Estimating Standards. A size cost adjustment is assigned to each piece of equipment based upon incremental size factors or step functions depending upon the type of equipment. In some cases the equipment cost includes installation costs. Equipment costs which are installed costs do not require adjustment for installing. Some unit operations do not have an equipment cost if they are not required for the specific scenario.

Item B

The costs for modular equipment, which is already installed, are summed for exclusion during installation costing.

Item C

Total equipment cost used for installation costing is equal to the total equipment cost (Item A) minus the modular equipment cost (Item B). This value is then used with the installation cost factors, Items D through H.

Item D

The Installation Cost Factor is multiplied times the bare delivered equipment cost. The cost includes installation of all delivered equipment including structural support, insulation, and paint. Installation factors are available for individual pieces of equipment. A general plant installation factor was used based upon the equipment type required for slurry manufacture. Based on AMAX experience, this factor is 24.8 percent.

Item E

Instrumentation and controls typically vary from 6 to 30 percent of the delivered equipment costs depending upon the amount of control and the complexity of the circuit. The slurry preparation plant would require a solid, liquid, and some gas control, as well as multiphase controls for the slurry streams. The cost includes the cost of the control equipment, installation, and auxiliary equipment and materials. AMAX experience suggests a factor of 25.5 percent for instrumentation.

Item F

Piping cost factors can range from 15 percent to 100 percent and may significantly impact the overall plant cost. The cost for piping covers labor, valves, fittings, pipe supports, and materials used in installing the process plant piping. Since the plant is heavily dependent upon piping for material handling, the factor used is on the high end of the range (75.9 percent).

Item G

Electrical installation costs include labor and materials for building power, transformers, lighting, and instruments. The electrical installation factor can range from 10 to 40 percent. Based on AMAX knowledge of plants of this general type, a factor of 33.5 percent was assumed for electrical.

Item H

Insulation and paint costs for the plant are affected by plant location. The cost is approximately 8 to 9 percent for chemical plants. The slurry production plant does not require the same insulation most chemical plants require, since outdoor containment is primarily for product storage and not piping intensive. Therefore, we assumed 6.6 percent for paint and insulation.

Item I

Item I is a summation of the equipment related installation factored costs (A, D, E, F, G, and H).

Item J

Buildings and Land cost is related to the square footage and height of the building. The type of structure is assumed to be a prefabricated steel building for basic protection from the elements. Cost includes labor, materials, and supplies for construction. Costs for plumbing, heating, lighting, ventilation, and other services are part of this factor. Land cost is not as production rate sensitive as other cost factors, since rail siding and coal storage is required regardless of the plant size, and is sensitive to geographic location and industrial proximity.

This cost, along with Items K and L, are step functions for which AMAX estimated the costs. The building and land cost do not have a direct relationship to the equipment cost or the subtotaled factored cost. Items J, K, and L relate to the equipment cost but not directly, since a plant with twice the equipment cost will not require twice as much rail trackage, roads, buildings, or land.

Item K

Land and site development includes grading, fencing, roads, sidewalks, landscaping, and auxiliary buildings such as change house, office, laboratory, warehouse, and shop. AMAX estimated land and site development costs.

Item L

Rail and road facilities include the cost of a rail switch, rail siding, and roads on site and from local access. Some of these costs are accounted for in the capital equipment cost of Area 100. Rail and road costs were estimated by AMAX and used as step functions as the plant output increased.

Item M

The total field cost is a summation of the equipment cost, equipment installation costs, plant erection, and site development costs. These are direct costs involved with building the plant (items I, J, K, and L).

Item N

The cost of design, engineering, drafting, purchasing, accounting, construction, travel, communications, on site office and home office expense, permitting and overhead are included in Engineering and Fees. This is an indirect cost that can range from 4 percent to 21 percent of the fixed capital cost. AMAX assumes a factor of 13.8 percent for engineering and fees.

Item O

Indirect Costs include field expenses such as contractors fee, construction tools, temporary assignments to the field office, construction payroll, travel and living expenses, taxes and insurance, and the other related overhead expenses. Based on plant experience, AMAX assumed a factor of 18.3 percent for indirect costs.

Item P

Total Construction cost includes the direct and indirect expenses.

Item Q

A contingency of 20 percent is included which is multiplied times the total Construction Cost. This could be reduced as the level of engineering increases and specific site related issues are more clearly defined. Figure 3, from Stearns Rogers, relates the level of engineering with the accuracy of the cost estimate. The figure shows that the level of engineering information known for this model reflects a confidence range of + or - 25 percent. For this reason, a higher than normal (10 percent) contingency factor is used.

Item R

The total capital cost is the sum of the direct, indirect, and contingency costs.

Item S

Working Capital is required for start up of the plant. It is used to purchase raw materials, stock the warehouse with spare parts and replacement equipment, and for changes required during start up. AMAX assumed 10 percent for working capital.

Item T

The Final Total Capital cost is the sum of the Total Capital Cost and the Working Capital.

Figure 3. Relationship of Engineering and Estimate Accuracy

Operating Cost Summary for CWS Fuel Plant

Plant Location: PITTSBURGH

Coal Type: Blue Gem

Capacity: 1.25 Million T/Y (Coal in Fuel)

Raw Coal Characteristics:

6 Percent Moisture
2 Percent Ash
0.7 Percent Sulfur
14,042 HHV (Btu/lb)

Slurry Fuel Specifications:

74 um Top Size
1 Percent Ash
1 Percent Sulfur
MED Viscosity
55% Solids

Distance in miles from:

Mine to Slurry Plant

Slurry Plant to User Site

0
20

27.8 MMBtu/ton (coal in fuel)

*No Finish Grinding or Chemical Cleaning Required

Item	Unit Cost		\$/Ton Dry Coal in Fuel	\$/MMBtu HHV
A. Purchased Coal	30.00	\$/ton raw	34.22	1.23
B. Freight to Slurry Plant	0.00	\$/ton raw	0.00	0.00
C. Subtotal Labor			2.46	0.09
Operation & Supervision	17 & 20	\$/hr	1.08	0.04
Maintenance & Supervision	17 & 20	\$/hr	0.99	0.04
Analytical	15	\$/hr	0.12	0.00
Other Assignable Labor			0.26	0.01
Cogeneration Plant Labor	17 & 20	\$/hr	0.00	0.00
D. Subtotal Utilities			2.32	0.08
Electrical and Steam			2.13	0.08
	0.25	\$/1,000 gal	0.19	0.01
E. Subtotal Reagents			8.86	0.32
Caustic	285	\$/ton	0.00	0.00
Acid	155	\$/ton	0.00	0.00
Ammonia	210	\$/ton	0.00	0.00
Dispersant	0.557	\$/lb	8.36	0.30
Formaldehyde	0.25	\$/lb	0.50	0.02
Lime	40	\$/ton	0.00	0.00
Modifier	90	\$/ton	0.00	0.00
F. Subtotal Maintenance Materials			1.86	0.07
Mill Liners and Media			0.35	0.01
General Maintenance	3% of Capital (excluding grinding equip.)		1.51	0.05
G. Freight to User Site	0.00	\$/ton fuel	0.00	0.00
H. Middling Coal Credit	0	\$/ton	0.00	0.00
I. Total Direct Costs (A+B+C+D+E+F+G+H)			49.72	1.79
J. Subtotal Indirect Costs			0.00	0.00
Taxes, Insurance, Supplies	0	% of Capital	0.00	0.00
General Admin. & Sales			0.00	0.00
Net Cash Flow	0.000	NCF Factor	0.00	0.00
K. Total Operating Cost (I+J)			49.72	1.79

Operating Cost Summary Sheet

The operating cost summary sheet is shown in Table 2. The itemized costs are described in further detail in this section.

Item A

Purchased coal cost is the cost of coal purchased from the mine identified in the header of the summary sheet. This is normally a quoted price based upon the tonnage required per year. The large amounts required for most of these plants results in some price reductions.

Item B

Freight to the slurry plant is the cost of moving the coal to the plant by rail or barge depending upon the location of the mine and the slurry plant. Freight costs were obtained from AMAX Coal Company or from FINAMAX Coal Company and were based on unit train loads of coal for the specific case scenarios. The train and the engine were assumed to be owned by the rail company.

Item C

The labor costs include the cost of wages for operators, foremen, mechanical and electrical support, laboratory technicians, safety and environmental, personnel, warehouse, purchasing, secretaries, engineers, and plant manager. Labor rates were taken from industry labor rates for 1988. More specific costs could be identified by plant location, but an average rate was used for the model regardless of the location. Certain fringe benefits and payroll costs were not included in these costs. The number of personnel and the estimated costs are shown in Table 4.

Item D

Utility costs were based upon the rates available from local utilities. Power and water costs were included in the utility costs. Industrial rates were quoted for power which are usually a function of the peak usage and a straight cost per kW/hr. Power consumption for the plant assumes 80% of the installed horse power is used during processing.

Item E

Reagent costs include reagents used in cleaning the coal and in formulating the final slurry. The costs and consumption rates are based upon actual operating experience at AMAX R&D Center. Certain reagents are not used in scenarios that have chemical cleaning excluded.

Table 4. Labor Requirements for the Base Case Scenario

<u>Area</u>	<u>Job Category</u>	<u>Number</u>		<u>Wage</u>	<u>\$/Yr</u>
	Operators:				
100	Unloading & storage	4	17	\$/hr	141,440
200	Crushing	2	17	\$/hr	70,720
300	Initial Grinding	4	17	\$/hr	141,440
400	Physical Cleaning	4	17	\$/hr	141,440
500	Caustic Leach & Filter	0	17	\$/hr	0
600	Acid leach & Filtration	0	17	\$/hr	0
700	Hot Water Wash & Filter	0	17	\$/hr	0
800	Fine Grinding	0	17	\$/hr	0
900	Slurry Preparation	0	17	\$/hr	0
1000	Storage & Load Out	4	17	\$/hr	141,440
1100	Caustic Regeneration	4	17	\$/hr	141,440
1200	Waste Treatment & Disposal	4	17	\$/hr	141,440
1300	Utilities	4	17	\$/hr	141,440
	Shift Foreman	4	20	\$/hr	166,400
	Mechanical Foreman	1	20	\$/hr	41,600
	Mechanics	20	17	\$/hr	707,200
	Electricians	12	17	\$/hr	424,320
	Laboratory Technicians	5	15	\$/hr	156,000
	Plant Manager	1	6,750	\$/hr	81,000
	Plant Engineer	1	5,625	\$/mo	67,500
	Process Engineer	2	5,200	\$/mo	124,800
	Personnel Administrator	1	5,062	\$/mo	60,744
	Safety/Environmental Officer	1	3,600	\$/mo	43,200
	Purchasing Clerk	1	2,947	\$/mo	35,364
	Warehouseman	1	2,947	\$/mo	35,364
	Secretaries	2	2,947	\$/mo	70,728
	Total \$/yr				3,075,020
	\$/Ton Dry Coal				2.46
	\$/MMBtu (HHV)				0.08

Item F

Maintenance materials is broken into two parts because a fairly large portion of the maintenance cost is related directly to grinding. The grinding mill maintenance costs for liners and media have been broken out separately. The remaining costs are covered under general maintenance.

Item G

Freight to the user's site includes the cost of transporting the slurry to the user's site. This cost was not included in the cost scenarios at the request of Arthur D. Little, Inc.

Item H

Middling coal credit is the credit for selling lower grade by product coal which is produced when heavy media separation is employed for physical cleaning. Heavy media separation was not used in any of the cost scenarios for Arthur D. Little, Inc.

Item I

Total Direct Costs are the sum of the itemized operating costs, Items A, B, C, D, E, and F.

Item J

Indirect costs include taxes, insurance, supplies, general administration, sales, and net cash flow. These costs were excluded at the request of Arthur D. Little, Inc., who included them separately.

Item K

The total operating cost is the same as the Total Direct Costs since Indirect Costs have been excluded.

APPENDIX C
SAMPLE CWS COST MODEL RUNS

Capital Cost Summary for CWS Fuel Plant

Plant Location: PITTSBURGH

Coal Type: Blue Gem

Capacity: 1.25 Million T/Y (Coal in Fuel)

Raw Coal Characteristics:

6 Percent Moisture
2 Percent Ash
0.7 Percent Sulfur
14,042 HHV (Btu/lb)

Slurry Fuel Specifications:

74 um Top Size
1 Percent Ash
1 Percent Sulfur
MED Viscosity
55% Solids

*No Finish Grinding of Chemical Cleaning Required

Item	Cost, \$ Million
A. Subtotal Delivered Equipment Cost	13.971
Unloading & Storage	1.333
Crushing	0.389
Initial Grinding	2.019
Physical Cleaning	1.325
Caustic Leach & Filtration	0.000
Acid Leach & Filtration	0.000
Hot Water Wash & Filtration	0.000
Fine Grinding	0.000
Slurry Preparation	0.000
Storage & Load Out	3.644
Caustic Regeneration	2.917
Waste Treatment & Disposal	0.704
Utilities	1.641
B. Less Modularized Equipment Cost	<u>- 3.518</u>
C. Bare Delivered Equipment Subtotal (A-B)	10.453
D. Installation (24.8% of C)	2.592
E. Instrumentation (25.5% of C)	2.665
F. Piping (75.9% of C)	7.934
G. Electrical	3.502
H. Paint and Insulation (6.6% of C)	<u>0.690</u>
I. Subtotal (A+D+E+F+G+H)	31.354
J. Buildings	10.443
K. Land and Site Development	1.451
L. Rail and Road Facilities	<u>1.710</u>
M. Total Field Cost (I+J+K+L)	44.958
N. Engineering and Fees (13.8% of M)	6.204
O. Indirect Costs (18.3% of M)	<u>8.227</u>
P. Subtotal Construction Cost (M+N+O)	59.389
Q. Contingency (20% of P)	<u>11.878</u>
R. Total Capital Cost (P+Q)	71.267
S. Working Capital (10% of R)	<u>7.127</u>
T. Final Total Capital Cost (R+S)	78.394

Capital Cost Summary for CWS Fuel Plant

Plant Location: PITTSBURGH

Coal Type: Blue Gem

Capacity: 1.25 Million T/Y (Coal in Fuel)

Raw Coal Characteristics:

6 Percent Moisture
2 Percent Ash
0.7 Percent Sulfur
14,042 HHV (Btu/lb)

Slurry Fuel Specifications:

74 um Top Size
1 Percent Ash
1 Percent Sulfur
MED Viscosity
55% Solids

Distance in miles from:

Mine to Slurry Plant: 0

Slurry Plant to User Site: 20

27.8 MM Btu/Ton

(Coal in Fuel)

*No Finish Grinding of Chemical Cleaning Required

Item	Unit Cost		\$/Ton Dry Coal In Fuel	\$/MM Btu HHV
A. Purchased Coal	30.00	\$/Ton Raw	34.22	1.23
B. Freight to Slurry Plant	0.00	\$/Ton Raw	0.00	0.00
C. Subtotal Labor			2.46	0.09
Operation & Supervision	17&20	\$/HR	1.08	0.04
Maintenance & Supervision	17&20	\$/HR	0.99	0.04
Analytical	15	\$/HR	0.12	0.00
Other Assignable Labor			0.26	0.01
Cogeneration Plant Labor	17&20	\$/HR	0.00	0.00
D. Subtotal Utilities			2.32	0.08
Electricity and Steam			2.13	0.08
Process and Cooling Water	0.25	\$/1,000 gal	0.19	0.01
E. Subtotal Reagents			8.86	0.32
Caustic	2.85	\$/ton	0.00	0.00
Acid	155	\$/ton	0.00	0.00
Ammonia	210	\$/ton	0.00	0.00
Dispersant	0.557	\$/lb	8.36	0.30
Formaldehyde	0.25	\$/lb	0.50	0.02
Lime	40	\$/ton	0.00	0.00
Modifier	90	\$/ton	0.00	0.00
F. Subtotal Maintenance Materials			1.86	0.07
Mill Liners and Media			0.35	0.01
General Maintenance		3% of Capital (excluding grinding equip.)	1.51	0.05
G. Freight to User Site	0.00	\$/ton fuel	0.00	0.00
H. Middling Coal Credit	0	\$/ton	<u>0.00</u>	<u>0.00</u>
I. Total Direct Costs (A+B+C+D+E+F+H)			49.72	1.79
J. Subtotal Indirect Costs			0.00	0.00
Taxes, Insurance, Supplies	0	% of capital	0.00	0.00
General Admin. & Sales			0.00	0.00
Net Cash Flow	0.000	NCF Factor	<u>0.00</u>	<u>0.00</u>
K. Total Operating Cost (I+J)	0.000		49.72	1.79

Capital Cost Summary for CWS Fuel Plant

Plant Location: CHICAGO Coal Type: ILLINOIS #5
 Capacity: 1.25 Million T/Y (Coal in Fuel)

<p>Raw Coal Characteristics:</p> <p style="padding-left: 40px;">8 Percent Moisture</p> <p style="padding-left: 40px;">8 Percent Ash</p> <p style="padding-left: 40px;">0.8 Percent Sulfur</p> <p style="padding-left: 40px;">13,500 HHV (Btu/lb)</p>	<p>Slurry Fuel Specifications:</p> <p style="padding-left: 40px;">30 um Top Size</p> <p style="padding-left: 40px;">0.5 Percent Ash</p> <p style="padding-left: 40px;">0.5 Percent Sulfur</p> <p style="padding-left: 40px;">LOW Viscosity</p> <p style="padding-left: 40px;">55 % Solids</p>
--	---

Item	Cost, \$ million
<hr/>	
A. Subtotal Delivered Equipment Cost	95.961
Unloading & Storage	1.333
Crushing	0.389
Initial Grinding	2.019
Physical Cleaning	1.325
Caustic Leach & Filtration	11.242
Acid Leach & Filtration	6.322
Hot Water Wash & Filtration	8.312
Fine Grinding	9.062
Slurry Preparation	0.358
Storage & Load Out	3.644
Caustic Regeneration	2.917
Waste Treatment & Disposal	0.704
Utilities	48.335
B. Less Modularized Equipment Cost	- 50.213
C. Bare Delivered Equipment Subtotal (A-B)	<hr/> 45.748
D. Installation (24.8% of C)	11.346
E. Instrumentation (25.5% of C)	11.666
F. Piping (75.9% of C)	34.723
G. Electrical (33.5% of C)	15.326
H. Paint and Insulation (6.6% of C)	3.019
I. Subtotal (A+D+E+F+G+H)	<hr/> 172.040
J. Buildings	10.443
K. Land and Site Development	1.451
L. Rail and Road Facilities	1.710
M. Total Field Cost (I+J+K+L)	<hr/> 185.644
N. Engineering and Fees (13.8% of M)	25.619
O. Indirect Costs (18.3% of M)	33.973
P. Subtotal Construction Cost (M+N+O)	<hr/> 245.236
Q. Contingency (20% of P)	49.047
R. Total Capital Cost (P+Q)	<hr/> 294.283
S. Working Capital (10% of R)	29.428
T. Final Total Capital Cost (R+S)	<hr/> 323.711

Operating Cost Summary for CWS Fuel Plant

Plant Location: CHICAGO

Coal Type: ILLINOIS #5

Capacity: 1.25 Million T/Y (Coal in Fuel)

Raw Coal Characteristics:

8 Percent Moisture
8 Percent Ash
0.8 Percent Sulfur
13,500 HHV (Btu/lb)

Slurry Fuel Specifications:

30 um Top Size
0.5 Percent Ash
0.5 Percent Sulfur
LOW Viscosity
55 % Solids

Distance in miles from:

Mine to Slurry Plant

Slurry Plant to User Site

0

20

26.8 MM Btu/Ton

(Coal in Fuel)

ITEM	UNIT COST		\$/TON DRY COAL IN FUEL	\$/MM BTU HHV
A. Purchased Coal	20.00	\$/TON RAW	23.31	0.87
B. Freight to Slurry Plant	0.00	\$/TON RAW	0.00	0.00
C. Subtotal Labor			4.18	0.16
Operation & Supervision	17 & 20	\$/HR	1.87	0.07
Maintenance & Supervision	17 & 20	\$/HR	0.99	0.04
Analytical	15	\$/HR	0.12	0.00
Other Assignable Labor			0.26	0.01
Cogeneration Plant Labor	17 & 20	\$/HR	0.93	0.03
D. Subtotal Utilities			1.93	0.07
Electricity and Steam			1.74	0.06
Process and Cooling Water	0.25	\$/1,000 gal	0.19	0.01
E. Subtotal Reagents			37.99	1.41
Caustic	285	\$/ton	15.11	0.56
Acid	155	\$/ton	11.55	0.43
Ammonia	210	\$/ton	1.58	0.06
Dispersant	0.557	\$/lb	8.36	0.31
Formaldehyde	0.25	\$/lb	0.50	0.02
Lime	40	\$/ton	0.62	0.02
Modifier	90	\$/ton	0.28	0.01
F. Subtotal Maintenance Materials			8.19	0.30
Mill Liners and Media			2.25	0.08
General Maintenance		3 % of Capital (excluding grinding equip.)	5.94	0.22
G. Freight to User Site	0.00	\$/TON FUEL	0.00	0.00
H. Middling Coal Credit	0	\$/TON	0.00	0.00
I. Total Direct Costs (A+B+C+D+E+F+G+H)			75.60	2.81
J. Subtotal Indirect Costs			0.00	0.00
Taxes, Insurance, Supplies	0	% of Capital	0.00	0.00
General Admin. & Sales			0.00	0.00
Net Cash Flow	0.000	NCF Factor	0.00	0.00
K. Total Operating Cost (I + J)			75.60	2.81

APPENDIX D
COAL FEEDSTOCK ANALYSES

COAL FEEDSTOCK DATA

COAL NAME - Hazard #4
 SEAM NAME - Hazard #4
 MINE NAME - Cumberland Collieries
 COAL RANK - High Volatile Bituminous
 CONTACT - Jim Lilly

		<u>AS RCVD</u>	<u>1.3 FLOT</u>	<u>CHEMICAL CLEAN</u>
Moisture	wt%	1.01	0.89	
Ash	wt%	5.59	2.53	
Volatiles	wt%	35.06	37.43	
Fixed Carbon	wt%	59.41	60.04	
HHV	wt%	14,203	14,724	
MAF HHV	wt%	15,044	15,106	
S.G. (dry basis)	wt%		1.269	
Moisture	wt%	0.00	0.00	
Ash	wt%	0.00	0.00	
Carbon	wt%	83.90	84.01	
Hydrogen	wt%	5.52	5.59	
Nitrogen	wt%	1.59	1.68	
Chlorine	wt%	NA	NA	
Sulfur	wt%	0.85	0.74	
Oxygen	wt%	8.14	7.98	
Pyritic Sulfur	wt%	0.101	0.005	
Organic Sulfur	wt%	0.74	0.90	
Total	wt%	0.84	0.91	

		<u>AS RCVD</u>	<u>1.3 FLOT</u>	<u>CHEMICAL CLEAN</u>
P ₂ O ₅	wt%	0.117	0.101	
SiO ₂	wt%	53.40	47.70	
Fe ₂ O ₃	wt%	5.72	4.84	
Al ₂ O ₃	wt%	31.80	36.80	
TiO ₂	wt%	1.91	1.97	
CaO	wt%	1.843	3.28	
MgO	wt%	0.610	0.715	
SO ₃	wt%	NA	NA	
K ₂ O	wt%	1.27	0.89	
Na ₂ O	wt%	0.48	0.81	
PbO	wt%	0.079	0.081	
NiO	wt%	0.015	0.051	

		<u>Oxidizing</u>	<u>Reducing</u>	<u>Oxidizing</u>	<u>Reducing</u>
Initial Deformation	*F	>2700	>2700	>2700	>2700
Softening (H+W)	*F				
Softening (H=Y ₂ W)	*F				
Fluid	*F				

Hardgrove Ind		
% Equil Moisture	2.92	
F.S.I.		

Btu Recovery, %	100.00	45.31
Wt. Recovery, %	100.00	45.12
Visc @ 65% Coal, cP		
Visc @ 60% Coal, cP		
Visc @ 80°C, 67% Coal		

Disp @ 65% Coal,	wt%	
Disp @ 60% Coal,	wt%	
Stability w/o		
Stabilizer,	wt%	
Stabilizer ROD		
for 1 mnth,	wt%	

COAL FEEDSTOCK DATA

COAL NAME - Splint (Standard)
 SEAM NAME - High Splint
 MINE NAME - Arch of Kentucky
 COAL RANK - High Volatile Bituminous
 CONTACT - Jim Lilly

		<u>AS RCVD</u>	<u>1.3 FLOT</u>	<u>CHEMICAL CLEAN</u>
Moisture	wt%	3.68	1.41	1.80
Ash	wt%	18.80	2.67	0.15
Volatiles	wt%	31.76	39.84	
Fixed Carbon	wt%	49.44	57.49	
HHV	wt%	12,120	14,579	
MAF HHV	wt%	14,937	14,979	
S.G. (dry basis)	wt%		1.264	
Moisture	wt%	0.00	0.00	0.00
Ash	wt%	0.00	0.00	0.18
Carbon	wt%	84.19	84.38	83.66
Hydrogen	wt%	5.71	5.72	5.47
Nitrogen	wt%	1.50	1.60	1.57
Sulfur	wt%	0.48	0.97	0.49
Oxygen	wt%	8.12	7.34	8.63
Pyritic Sulfur	wt%	0.31	0.05	0.005
Organic Sulfur	wt%	0.07	0.51	0.469
Total	wt%	0.38	0.52	0.479

	<u>AS RCVD</u>	<u>1.3 FLOT</u>	<u>CHEMICAL CLEAN</u>
P ₂ O ₅	wt% 0.150	0.189	0.355
SiO ₂	wt% 55.00	43.90	27.3
Fe ₂ O ₃	wt% 4.60	11.70	11.8
Al ₂ O ₃	wt% 21.10	27.10	9.35
TiO ₂	wt% 1.05	1.85	12.80
CaO	wt% 2.46	8.26	4.25
MgO	wt% 1.51	1.67	1.70
SO ₃	wt% NA	NA	--
K ₂ O	wt% 3.33	0.76	0.90
Na ₂ O	wt% 0.20	0.31	11.0
PbO	wt% <0.012	0.097	0.323
NiO	wt% 0.005	0.060	1.47

		<u>Oxidizing</u>	<u>Reducing</u>	<u>Oxidizing</u>	<u>Reducing</u>	
Initial Deformation °F	*F	2480	2450	2443	2342	2246 1830
Softening (H+W) °F	*F	2665	2555	2568	2442	2341 1885
Softening (H=Y ₂ W) °F	*F	>2700	2660	2595	2480	2359 1920
Fluid °F	*F		>2700	2615	2611	2389 1985

Hardgrove Ind
% Equil Moisture
F.S.I.

2.84

Btu Recovery, %
Wt. Recovery, %
Visc @ 65% Coal, cP
Visc @ 60% Coal, cP
Visc @ 80°C, 67% Coal

100.00 47.79
100.00 47.66

Disp @ 65% Coal, wt%
Disp @ 60% Coal, wt%
Stability w/o
Stabilizer, wt%
Stabilizer ROD
for 1 mnth, wt%

COAL FEEDSTOCK DATA

COAL NAME - Stenson
 SEAM NAME - Elkhorn #2
 MINE NAME - Stenson
 COAL RANK - High Volatile Bituminous
 CONTACT - Jim Lilly

		<u>AS RCVD</u>	<u>1.3 FLOT</u>	<u>CHEMICAL CLEAN</u>
Moisture	wt%	2.64	0.99	1.41
Ash	wt%	3.38	1.88	0.18
Volatiles	wt%	37.02	38.07	
Fixed Carbon	wt%	59.60	60.05	
HHV	wt%	14,695	14,908	
MAF HHV	wt%	15,209	15,194	
S.G. (dry basis)	wt%		1.301	
Moisture	wt%	0.00	0.00	0.00
Ash	wt%	0.00	0.00	0.20
Carbon	wt%	84.26	84.46	83.35
Hydrogen	wt%	5.71	5.90	5.67
Nitrogen	wt%	1.52	1.53	1.59
Chlorine	wt%	NA	NA	
Sulfur	wt%	1.00	1.51	0.70
Oxygen	wt%	7.51	6.60	8.49
Pyritic Sulfur	wt%	0.277	0.110	0.005
Organic Sulfur	wt%	0.69	0.71	0.690
Total	wt%	0.96	0.82	0.700

		<u>AS RCVD</u>	<u>1.3 FLOT</u>	<u>CHEMICAL CLEAN</u>
P ₂ O ₅	wt%	0.066	0.113	0.293
SiO ₂	wt%	34.80	30.10	15.9
Fe ₂ O ₃	wt%	21.30	15.80	18.3
Al ₂ O ₃	wt%	27.20	30.10	9.03
TiO ₂	wt%	1.16	1.34	5.50
CaO	wt%	5.60	7.59	3.45
MgO	wt%	1.23	1.63	0.97
SO ₃	wt%	NA	NA	--
K ₂ O	wt%	1.79	0.90	1.16
Na ₂ O	wt%	0.86	1.21	15.1
PbO	wt%	0.104	0.245	0.204
NiO	wt%	0.045	0.056	0.668

		<u>Oxidizing</u>	<u>Reducing</u>	<u>Oxidizing</u>	<u>Reducing</u>	
Initial Deformation	*F	2459	2367	2375	2375	2361 1990
Softening (H+W)	*F	2526	2442	2395	2395	2379 2081
Softening (H=Y ₂ W)	*F	2565	2480	2410	2410	2386 2105
Fluid	*F	2593	2582	2505	2505	2387 2125

Hardgrove Ind
 % Equil Moisture
 F.S.I.

3.06

Btu Recovery, %
 Wt. Recovery, %
 Visc @ 65% Coal, cP
 Visc @ 60% Coal, cP
 Visc @ 80°C, 67% Coal

100.00 43.81
 100.00 43.85

Disp @ 65% Coal, wt%
 Disp @ 60% Coal, wt%
 Stability w/o
 Stabilizer, wt%
 Stabilizer RQD
 for 1 mnth, wt%

APPENDIX E
ALTERNATIVE DESIGNS FOR HIGHER EFFICIENCY

1.0 RANKINE BOTTOMING CYCLE ANALYSIS

In this section a Rankine Bottoming Cycle (RBC) is considered in order to increase the power efficiency of the coal fueled diesel by recovering the heat rejected in the exhaust, water jacket cooling system, and the lube system. This analysis is intended to provide a first order estimate of the cycle efficiency benefits which could be obtained through the use of such a system. The result, as explained in Section 1.8, is that the use of RBC could increase the power plant efficiency from 39% to over 46%. Further analysis and optimization of the cycle would be required during the design of the system. The assumptions associated with each component in the system are presented at the appropriate point in the analysis.

Figure 1 presents a schematic representation of a simplified RBC. In this system, only heat from the diesel exhaust is recovered. The diesel exhaust is the heat source shown in Figure 1. For purposes of this analysis, steam was chosen as the working fluid of the cycle. Other working fluids could be used, such as toluene, to improve the cycle performance at the expense of toxicity and cost. The following section outlines the calculations performed on each component of the cycle.

1.1 Heat Source - Diesel Engine

The following performance data is based on 2 twenty cylinder turbo-charged Cooper Bessemer diesel engines.

Fuel Input:	105.66 x 10 ⁶ BTU/hr.
Electrical Output:	12 MW

Exhaust Gas Conditions after Turbocharger

Mass Flow:	206,000 lbs/hr.
Pressure:	10" H ₂ O
Temperature:	660 °F

In order to study the effect of higher exhaust temperatures on cycle efficiency, it was assumed that the exhaust gas temperature could be raised without changing the power output, which would require design modifications to the engine. In the analysis this was done by reducing the exhaust mass flow, so that the heat rejected in the exhaust gas remains constant. For simplicity in the analysis, it was assumed that the constant pressure specific heat of the exhaust gas is:

$$C_{p \text{ gas}} = 0.25 \frac{\text{BTU}}{\text{lb} \cdot ^\circ \text{R}}$$

FIGURE E-1:
SIMPLIFIED RANKINE BOTTOMING CYCLE (RBC) SCHEMATIC

The heat contained in the exhaust gas can then be calculated as follows:

$$Q_{\text{exh}} = \dot{m}_{\text{gas}} C_{p \text{ gas}} (T_{\text{gas}} - T_{\text{ambient}}) + Q_{\text{fg}}$$

in which the latter term in the equation is the latent heat of vaporization of water in the exhaust gas. The exhaust gas conditions for the four exhaust gas temperature cases are calculated using these assumptions.

Case	T_{gas} (°F)	Q_{fg} (10 ⁶ BTU/hr.)	$Q_{\text{Exh.}}$ (10 ⁶ BTU/hr.)	$\dot{m}_{\text{gas}}$ (lb./hr.)
1	660	8.5	37.34	206,000
2	750	8.5	37.34	177,477
3	850	8.5	37.34	153,813
4	1,110	8.5	60.50	206,000

Note that in Case 4 the assumption of constant exhaust heat is not maintained. This case is presented to simulate a burner in the diesel exhaust duct, which provides combustion of the unburned coal particles in the diesel exhaust for control of emissions.

1.2 Boiler Calculations

- Assumptions
- o Steam side boiler pressure of 250 psia
 - o Stack temperature of 330 °F to minimize H₂SO₄ corrosion
 - o Feedwater temperature of 220 °F
 - o Superheated steam leaves the boiler at ($T_{\text{gas}} - 100$ °F)
 - o 1 1/2% heat loss due to radiation

The equations for calculating performance of the boiler are:

$$Q_{\text{recov.}} = 0.985 \dot{m}_{\text{gas}} C_{p \text{ gas}} (T_{\text{gas}} - 330 \text{ °F.})$$

$$\dot{m}_{stm} = \frac{Q_{recov}}{h_{stm} - h_{fw}}$$

where:

Q_{recov} = heat recoverable from exhaust gas

$\dot{m}_{stm}$ = mass flow of steam produced

h_{stm} = enthalpy of steam leaving boiler

h_{fw} = enthalpy of feedwater entering boiler

Case	T_{gas} (°F)	T_{stm} (°F)	h_{stm} (BTU/lb.)	$\dot{m}_{gas}$ (lb./hr.)	Q_{recov} (10 ⁶ BTU/hr.)	h_{fw} (BTU/lb.)	$\dot{m}_{stm}$ (lb./hr.)
1	660	560	1,296.8	206,000	16.74	189.05	15,121
2	750	650	1,345.3	177,477	18.36	189.05	15,879
3	850	750	1,397.5	153,813	19.70	189.05	16,302
4	1,110	1,000	1,527.6	206,000	39.57	189.05	29,562

Steam enthalpy was obtained by using the 1967 ASME steam tables:

1.3 Turbine Calculations

- Assumptions:
- o Turbine efficiency of 80% including the generator
 - o Turbine exhaust pressure of 3" HgA

The equations for calculating the performance of the turbine are:

$$h_2 = h_1 - \eta_t(h_1 - h_{2i})$$

$$\text{Turbine Power Output} = \dot{m}_{stm}(h_1 - h_2)$$

where:

η_t = turbine efficiency

h_1 = enthalpy of steam at turbine inlet

h_{2i} = enthalpy at turbine exit assuming isentropic expansion from turbine inlet conditions to turbine exhaust pressure

Case	$\dot{m}_{stm}$ (lb./hr.)	h_1 (BTU/lb.)	h_{2i} (BTU/lb.)	h_2 (BTU/lb.)	Power (kW)
1	15,121	1,296.8	933	1,006	1,290
2	5,879	1,345.3	956	1,034	1,449
3	16,302	1,397.5	981	1,064	1,592
4	29,562	1,527.6	1,039	1,137	3,387

1.4 Condenser Calculations

- Assumptions: o Condenser Pressure, 3" HgA
o Condenser Temperature, 116 °F

The heat given up by the steam leaving the turbine during the condensation process must be rejected by the condenser by utilizing a source of cooler water such as a river, or through the use of a cooling tower. The equation to calculate this heat rejection is:

$$Q_{cond} = \dot{m}_{stm} (h_2 - h_3)$$

where:

Q_{cond} = heat rejected by the condenser

h_2 = enthalpy of steam entering the condenser

h_3 = enthalpy of water leaving the condenser

Case	$\dot{m}_{\text{stm}}$ (lb./hr.)	h_2 (BTU/lb.)	h_3 (BTU/lb.)	Q_{cond} (10^6 BTU/HR.)
1	15,121	1,006	81.9	13.97
2	15,879	1,034	81.9	15.12
3	16,302	1,064	81.9	16.01
4	29,562	1,137	81.9	31.19

1.5 Pump Calculations

- Assumptions:
- o Pump exit pressure is 25% higher than boiler pressure, to overcome losses in pipes
 - o Pump isentropic efficiency is 70%
 - o Pump drive efficiency is 95%

The equations for calculating the pump performance are as follows:

$$h_4 = h_3 + \frac{h_3 - h_{4i}}{\eta_p}$$

$$\text{Pump Power Input} = \dot{m}_{\text{fw}} \frac{(h_4 - h_3)}{\eta_d}$$

where:

h_3 = pump inlet enthalpy

h_4 = pump exit enthalpy

h_{4i} = pump exit enthalpy assuming isentropic pumping from inlet conditions to exit pressure

η_p = isentropic pump efficiency

η_d = pump drive efficiency

$\dot{m}_{fw}$ = feedwater mass flow rate

Case	h_3 (BTU/lb.)	h_{4i} (BTU/lb.)	h_4 (BTU/lb.)	$\dot{m}_{fw}$ (lb/hr)	Power kW
1	81.9	83.7	84.5	15,121	12.1
2	81.9	83.7	84.5	15,879	12.7
3	81.9	83.7	84.5	16,302	13.1
4	81.9	83.7	84.5	29,562	23.7

1.6 Oil Cooler

In the boiler calculation section it was assumed that the feedwater temperature entering the boiler was 220 °F. For this to be true, the feedwater must be heated by some means to this temperature. The assumption applied here is that the heat rejected by the oil cooler is sufficient to accomplish this heating. If it is assumed that 3% of the input heat to the diesel engine is rejected to the lube system, then there will be sufficient heat available for this feedwater heating, for all four cases. In a more rigorous analysis, all the heat available from the oil cooler would be used to heat the feedwater and a number of iterative cycle calculations would be performed, which when converged would yield a new feedwater temperature.

1.7 Water Jacket Heat Recovery

As can be seen from Figure 2, approximately 17% of the input fuel energy is rejected to the water jacket of the diesel engine. In order to recover this low temperature energy, a low pressure loop in the RBC is required. Figure 3 shows the water jacket fluid supplying heat to an evaporator. A more efficient method is to use ebullient cooling, in which saturated steam, generated by the boiling of water in the water jacket is admitted directly to a low pressure stage of the turbine. Calculations of the power output which can be gained by utilizing this rejected heat are outlined below:

FIGURE E-2: ENERGY DISTRIBUTION OF TYPICAL TURBO-CHARGED DIESEL ENGINE

SOURCE: "HEAT RECOVERY EQUIPMENT FOR ENGINES", C. L. SEGASER, ICES TECHNOLOGY EVALUATIONS
ANL/CES/TE 77-4

Figure E-3: RBC System with Low Pressure Water Jacket Recovery Loop

Assumptions: o Saturated steam conditions in water jacket

$$P_{stm} = 15 \text{ psig.}$$

$$T_{stm} = 250 \text{ }^{\circ}\text{F.}$$

$$h_{stm} = 1,164 \text{ Btu/lb.}$$

- o 17% of the diesel input energy is rejected to the water jacket.
- o 80% efficient turbine.

The following analysis of the water jacket heat recovery system is based on Case 3.

The heat rejected to the water jacket is calculated as follows:

$$\begin{aligned} Q_{WJ} &= Q_{INPUT}(0.17) \\ &= \left(105.66 \times 10^6 \frac{\text{Btu}}{\text{hr}} \right) (0.17) = 17.96 \times 10^6 \frac{\text{Btu}}{\text{hr}} \end{aligned}$$

The turbine output is then calculated using the same procedure as outlined in Section 1.3.

$$\begin{aligned} h_2 &= h_1 - \eta_T(h_1 - h_{2i}) \\ &= 1164 - 0.8(1164 - 989) = 1024 \frac{\text{Btu}}{\text{lb}} \end{aligned}$$

$$\begin{aligned} \text{Turbine Power Output} &= \dot{m}(h_1 - h_2) \\ &= \frac{18420 \text{ lb/hr} (1164 - 1024) \frac{\text{Btu}}{\text{lb}}}{3412.14 \frac{\text{Btu}}{\text{kWh}}} \\ &= 756 \text{ kW} \end{aligned}$$

This additional power output is then added to that of Case 3.

$$\text{kW}_{\text{turbine}} = 1592 + 756 = 2348$$

1.8 Summary and Conclusions

The following table summarizes the results of the earlier calculations.

Case	T _{gas} (°F)	Q _{gas} (10 ⁶ Btu/hr)	kW (diesel)	kW (turbine)	kW (pump)	kW (total)	η Total Cycle	%η improve- ment
base	660	37.34	12000	-	-	12000	0.388	-
1	660	37.34	12000	1290	-12	13278	0.429	10.6
2	750	37.34	12000	1449	-13	13436	0.434	11.9
3a	850	37.34	12000	1592	-13	13579	0.439	13.1
3b	850	37.34	12000	2348	-19	14329	0.463	19.3
4	1110	60.50	12000	3387	-23	15364	0.407	-

Case 3b is identical to Case 3a, with the addition of water jacket heat recovery.

Based on the above information, the following observations can be made:

- o The simplified RBC results in a 10.6% improvement in overall cycle efficiency. (42.9% efficiency instead of 38.8% for the unmodified coal diesel engine).
- o A 100°F increase in diesel exhaust temperature preheated air brings about an additional 1.2% increase in cycle efficiency (to 43.4%).
- o The addition of water jacket heat recovery to the RBC would increase overall cycle efficiency by 6.2% (to 46.3%).

The water jacket heat recovery provides an additional two-thirds of the heat recovery of the simplified RBC system, and is therefore a worthwhile addition to the cycle despite its additional complexity. The increases in exhaust temperature, also provide a significant cycle improvement, though not as dramatic. As stated earlier, this analysis is intended to provide a preliminary estimate of the magnitude of gains possible with RBC system. Optimization of boiler pressures, approach temperature differences, feedwater temperatures, etc. would allow fine tuning of the cycle. Overall cycle efficiencies beyond 46%, perhaps as high as 50% may be possible.

In Case 4, which uses a burner in the exhaust duct for control of emissions, the use of an RBC system becomes even more important. Additional fuel must be supplied to the burner, with no increase in power output. The RBC allows a substantial portion of this wasted heat to be recovered and converted to electrical output.

APPENDIX F
EMISSION CONTROL TECHNOLOGIES

REBURNING

A-8948A

EQUIPMENT

- DUCT BURNER
- COMBUSTION CHAMBER
- O₂ MONITOR (INLET & OUTLET)
- CH₄ SUPPLY PIPING
- CH₄ FLOW CONTROL SYSTEM
- VALVES AND PIPING

NH₃ INJECTION IN BAGHOUSE

A-8949A

EQUIPMENT

- NH₃ HANDLING SYSTEM:
 - LIQUID STORAGE TANK
 - VAPORIZER
 - VALVES AND PIPING
 - HOLDING TANK FOR NH₃/AIR MIXTURE
- NH₃ INJECTORS AND MIXING CHAMBER CONTROL SYSTEM
 - CONTROL VALVES
 - NO AND NH₃ MEASUREMENT EQUIPMENT
 - CONTROLLER
- BAGHOUSE INCLUDING ROTARY AIRLOCK AND ASH STORAGE (NOTE: THE BAGHOUSE MAY HAVE TO BE DESIGNED FOR TEMPERATURES > 400°F)
- INDUCED DRAFT FAN

GRANULAR BED FILTER FOR NO_x (AND PARTICLE) CONTROL

EQUIPMENT

- GRANULAR BED FILTER UNITS (4 EACH IN A PRESSURE VESSEL)
- PIPING FOR SOLID (FILTER MEDIA) TRANSPORT
- AIR BLOWER FOR SOLID (FILTER MEDIA) TRANSPORT
- FILTER MEDIA RESERVOIR
- DE-ENTRAINMENT VESSEL
- HEAT EXCHANGER
- BAGHOUSE
- PIPING AND VALVES FOR GAS HANDLING
- AMMONIA INJECTION SYSTEM
- GAS MONITORING SYSTEM

A-8952A

NH₃ INJECTION OVER ACTIVATED CARBON (TAKEDA PROCESS)

A-9093A

EQUIPMENT

- REACTOR VESSELS
- LIME FEEDER
- MIXING TANK, HOLDING TANK
- PUMPS
- NH₃ STORAGE TANK, MIXING VESSEL, AND INJECTOR
- VALVE AND PIPING
- GAS MONITORING INSTRUMENTATION

SELECTIVE CATALYTIC REDUCTION

A-8951A

EQUIPMENT

- NH₃ HANDLING SYSTEM:
 - LIQUID STORAGE TANK
 - VAPORIZER
 - VALVES AND PIPING
 - HOLDING TANK FOR NH₃ /AIR MIXTURE
- NH₃ INJECTORS AND MIXING CHAMBER CONTROL SYSTEM
 - CONTROL VALVES
 - NO_x AND NH₃ MEASUREMENT EQUIPMENT
 - CONTROLLER
- REACTION CHAMBER
- VALVES AND PIPING

SORBENT INJECTION

EQUIPMENT

- STORAGE SILO/HOPPER
- SCREW FEEDER
- EDUCTOR
- DUCT INJECTORS
- VALVES AND PIPING

SPRAY DRYER (HYDRATED LIME OPERATION)

A-8955A

- STORAGE SILO/HOPPER
- SCREW FEEDER
- SLURRY MIXING TANK
- SLURRY PUMP
- SPRAY CHAMBER
- VALVES AND PIPING

CYCLONE

A-8957A

EQUIPMENT

- CYCLONE (INCLUDING INLET AND OUTLET SCROLLS)
- ROTARY AIRLOCK
- ASH STORAGE BIN
- VALVES AND PIPING

BAGHOUSE

A-8956A

EQUIPMENT

- INSULATED BAGHOUSE (INCLUDING NOMEX BAGS)
- CONTROL SYSTEM
- INDUCED DRAFT FAN
- ROTARY AIRLOCK
- SCREW CONVEYER
- ASH STORAGE BIN
- VALVES AND PIPING

GRANULAR BED FILTER (FOR PARTICLE REMOVAL)

A-8959A

EQUIPMENT

- GRANULAR BED FILTER UNITS (2 EACH — 6 FT DIAMETER)
- PIPING FOR SOLID (FILTER MEDIA) TRANSPORT
- AIR BLOWER FOR SOLID (FILTER MEDIA) TRANSPORT
- FILTER MEDIA RESERVOIR
- DE-ENTRAINMENT VESSEL
- HEAT EXCHANGER
- BAGHOUSE
- PIPING AND VALVES FOR GAS HANDLING

CERAMIC CROSS FLOW FILTER

EQUIPMENT

- FILTER VESSEL (INCLUDING 12 x 12 x 4 in FILTER ELEMENTS)
- CONTROLLER, PRESSURE SENSOR, CONTROL VALVE
- 500 psig AIR HOLDING TANK
- AIR COMPRESSOR
- ROTARY AIRLOCK AND ASH STORAGE BIN
- VALVES AND PIPING
- HEATER FOR BLOWBACK AIR

APPENDIX G
EMISSION CONTROL SYSTEM OPTIONS - PROCESS DIAGRAMS

OPTION A

A 9462

OPTION B

A 9863

OPTION C

A 9664

OPTION D

• DUCT BURNER MAY BE REQUIRED AT THIS POINT TO RAISE EXHAUST GAS TEMPERATURE

A-9865

OPTION J

A 9666

OPTION K

A 9667

OPTION I

A 9658

OPTION M

A 9659

OPTION N

A-9670

APPENDIX H
COST CALCULATIONS FOR EMISSION CONTROL SYSTEM OPTIONS

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION A

System: 1 Engine (2 6 Cylinder)
1.8 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
SCR Unit	0.166	
Duct Burner	0.033	
Spray Dryer	0.451	
Cyclone	0.015	
Baghouse	0.075	
Induced Draft Fan	0.005	
Differential Boiler Cost	0.026	
Total Equipment	0.771	
Installation Costs:	0.409	
Total Installed Equipment Cost		1.180
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.425	
Total Plant Cost	1.605	
Royalties	0.001	
Preproduction Costs and Inventory Capital	0.063	
Initial Supplies and Materials	0.073	
Total Capital Cost		1.742

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 0.5		
Operating Labor (@ \$21.55/hour)	0.094	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.023	
Overhead Labor Cost	0.035	
Total Labor Cost	0.152	
Maintenance Supplies Cost	0.034	
Total Operating and Maintenance Cost	0.186	
Fixed Operating and Maintenance Cost		0.121
Variable Operating and Maintenance Cost	0.065	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu. ft.	2.90	
Ammonia @ \$0.25/lb	4.13	
Sorbent @ \$70 /ton	2.10	
Catalyst @ (2 yr life)	6.41	
Raw Water @ \$0.60/1000 gal	0.02	
Steam @ \$5.64/1000 lb	1.51	
Electricity @ \$0.05/KWh	1.92	
Disposal @ \$6.50/ton	0.29	
Bag @ (1 yr life)	1.49	
Total	20.76	0.118
Total Variable Operating Costs (@ 65% utilization)		0.183
Cost of Capital (15% per year)		0.261
Total Annual Operating Cost		0.365

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION B

System: 1 Engine (2 6 Cylinder)
1.8 Hhp power output

CAPITAL

Equipment:	Cost (MM \$)	
Reburning Unit	0.033	
Low Temperature Lime Injection	0.030	
Cyclone	0.015	
Baghouse	0.075	
Induced Draft Fan	0.005	
Differential Boiler Cost	0.034	
Total Equipment	0.192	
Installation Costs:	0.089	
Total Installed Equipment Cost		0.281
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.101	
Total Plant Cost	0.382	
Preproduction Costs and Inventory Capital	0.027	
Initial Supplies and Materials	0.001	
Total Capital Cost		0.411

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 0.5		
Operating Labor (@ \$21.55/hour)	0.094	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.004	
Overhead Labor Cost	0.030	
Total Labor Cost	0.128	
Maintenance Supplies Cost	0.007	
Total Operating and Maintenance Cost	0.135	
Fixed Operating and Maintenance Cost		0.088
Variable Operating and Maintenance Cost	0.047	
Variable Operating Cost:		
Natural Gas @ \$3.50/1000 cu.ft.	13.71	
Sorbent @ \$70 /ton	2.10	
Steam @ \$5.64/1000 lb	(16.55)	
Electricity @ \$0.05/KWh	1.04	
Disposal @ \$6.50/ton	0.29	
Bag @ (1 yr life)	1.49	
Total	2.08	0.012
Total Variable Operating Costs (@ 65% utilization)		0.059
Cost of Capital (15% per year)		0.062
Total Annual Operating Cost		0.208

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION C

System: 1 Engine (2 6 Cylinder)
1.8 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Reburning Unit	0.033	
High Temperature Lime Injection	0.030	
Cyclone	0.015	
Baghouse	0.075	
Induced Draft Fan	0.005	
Differential Boiler Cost	0.034	
Total Equipment	0.192	
Installation Costs:	0.089	
Total Installed Equipment Cost		0.281
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.101	
Total Plant Cost	0.382	
Preproduction Costs and Inventory Capital	0.027	
Initial Supplies and Materials	0.001	
Total Capital Cost		0.411

OPERATING COSTS

		Cost (MM \$/yr)
Operators/Shift: 0.5		
Operating Labor (@ \$21.55/hour)		0.094
Maintenance Factor: 0.04		
Maintenance Labor Cost		0.004
Overhead Labor Cost		0.030
Total Labor Cost		0.128
Maintenance Supplies Cost		0.007
Total Operating and Maintenance Cost		0.135
Fixed Operating and Maintenance Cost		0.088
Variable Operating and Maintenance Cost		0.047
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	13.71	
Sorbent @ \$70 /ton	2.10	
Steam @ \$5.64/1000 lb	(16.55)	
Electricity @ \$0.05/KWh	1.04	
Disposal @ \$6.50/ton	0.29	
Bag @ (1 yr life)	1.49	
Total	2.08	0.012
Total Variable Operating Costs (@ 65% utilization)		0.059
Cost of Capital (15% per year)		0.062
Total Annual Operating Cost		0.208

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION D

System: 1 Engine (2 6 Cylinder)
1.8 MWe power output

CAPITAL

Equipment:	Cost (MM \$)
Calcium Fuel Additive (Ca/S = 1)	0.000
Cyclone	0.015
High Temperature Lime Injection (Ca/S = 1)	0.030
Shell/UDP Unit with Granular Bed	0.296
Induced Draft Fan	0.005
Differential Boiler Cost	0.026
Total Equipment	0.372
Installation Costs:	0.229
Total Installed Equipment Cost	0.601
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.216
Total Plant Cost	0.817
Royalties	0.003
Preproduction Costs and Inventory Capital	0.242
Initial Supplies and Materials	0.087
Total Capital Cost	1.150

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 0.5		
Operating Labor (@ \$21.55/hour)	0.094	
Maintenance Factor: 0.09		
Maintenance Labor Cost	0.022	
Overhead Labor Cost	0.035	
Total Labor Cost	0.150	
Maintenance Supplies Cost	0.032	
Total Operating and Maintenance Cost	0.183	
Fixed Operating and Maintenance Cost		0.119
Variable Operating and Maintenance Cost	0.064	
Variable Operating Cost:	\$/hour	
Ammonia @ \$0.25/lb	4.13	
Fuel Additive @ \$2.07/lb	87.87	
Catalyst @ (2 yr life)	3.12	
Cooling Water @ \$0.15/1000 gal	0.20	
Steam @ \$5.64/1000 lb	1.51	
Electricity @ \$0.05/KWh	1.14	
Disposal @ \$6.50/ton	0.48	
Total	98.45	0.561
Total Variable Operating Costs (@ 65% utilization)		0.625
Cost of Capital (15% per year)		0.172
Total Annual Operating Cost		0.916

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION J

System: 1 Engine (2 6 Cylinder)
1.8 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----	
High Temperature Lime Injection	0.030	
Duct Burner	0.033	
Ammonia Injection in Baghouse (at 450 F)	0.084	
Cyclone	0.015	
Insulated Baghouse	0.101	
Induced Draft Fan	0.005	
Differential Boiler Cost	0.001	
Total Equipment	0.269	
Installation Costs:	0.142	
Total Installed Equipment Cost		0.411
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.148	
Total Plant Cost	0.539	
Preproduction Costs and Inventory Capital	0.054	
Initial Supplies and Materials	0.001	
Total Capital Cost		0.614

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 0.5		
Operating Labor (@ \$21.55/hour)	0.094	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.007	
Overhead Labor Cost	0.030	
Total Labor Cost	0.131	
Maintenance Supplies Cost	0.010	
Total Operating and Maintenance Cost	0.142	
Fixed Operating and Maintenance Cost		0.093
Variable Operating and Maintenance Cost	0.049	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu. ft.	11.10	
Ammonia @ \$0.25/lb	4.13	
Sorbent @ \$70 /ton	2.10	
Steam @ \$5.64/1000 lb	(6.24)	
Electricity @ \$0.05/KWh	1.04	
Disposal @ \$6.50/ton	0.29	
Bag @ (1 yr life)	1.49	
Total	13.91	0.079
Total Variable Operating Costs (@ 65% utilization)		0.128
Cost of Capital (15% per year)		0.092
Total Annual Operating Cost		0.313

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION K

System: 1 Engine (2 6 Cylinder)
1.8 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
SCR Unit	0.166	
Duct Burner	0.033	
Low Temperature Lime Injection	0.030	
Cyclone	0.015	
Baghouse	0.075	
Induced Draft Fan	0.005	
Differential Boiler Cost	0.026	
Total Equipment	0.350	
Installation Costs:	0.149	
Total Installed Equipment Cost		0.499
Engineering and Home Office Fees, General		
Facilities, 20% Contingency	0.180	
Total Plant Cost	0.679	
Royalties	0.001	
Preproduction Costs and Inventory Capital	0.055	
Initial Supplies and Materials	0.073	
Total Capital Cost		0.808

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 0.5		
Operating Labor (@ \$21.55/hour)	0.094	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.008	
Overhead Labor Cost	0.031	
Total Labor Cost	0.133	
Maintenance Supplies Cost	0.012	
Total Operating and Maintenance Cost	0.145	
Fixed Operating and Maintenance Cost		0.094
Variable Operating and Maintenance Cost	0.051	
Variable Operating Cost:		
Natural Gas @ \$3.50/1000 cu.ft.	2.90	
Ammonia @ \$0.25/lb	4.13	
Sorbent @ \$70 /ton	2.10	
Catalyst @ (2 yr life)	6.41	
Steam @ \$5.64/1000 lb	1.51	
Electricity @ \$0.05/KWh	1.04	
Disposal @ \$6.50/ton	0.29	
Bag @ (1 yr life)	1.49	
Total	19.87	0.113
Total Variable Operating Costs (@ 65% utilization)		0.164
Cost of Capital (15% per year)		0.121
Total Annual Operating Cost		0.379

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION L

System: 1 Engine (2 6 Cylinder)
1.8 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Reburning Unit	0.033	
Spray	0.451	
Cyclone	0.015	
Bag	0.075	
Induced Draft Fan	0.005	
Differential Boiler Cost	0.034	
Total Equipment	0.613	
Installation Costs:	0.349	
Total Installed Equipment Cost		0.962
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.346	
Total Plant Cost	1.308	
Preproduction Costs and Inventory Capital	0.051	
Initial Supplies and Materials	0.001	
Total Capital Cost		1.360

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 0.5		
Operating Labor (@ \$21.55/hour)	0.094	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.019	
Overhead Labor Cost	0.034	
Total Labor Cost	0.147	
Maintenance Supplies Cost	0.029	
Total Operating and Maintenance Cost	0.176	
Fixed Operating and Maintenance Cost		0.114
Variable Operating and Maintenance Cost	0.062	
Variable Operating Cost:		
Natural Gas @ \$3.50/1000 cu.ft.	13.71	
Sorbent @ \$70 /ton	2.10	
Raw Water @ \$0.60/1000 gal	0.02	
Steam @ \$5.64/1000 lb	(16.55)	
Electricity @ \$0.05/KWh	1.92	
Disposal @ \$6.50/ton	0.29	
Bag @ (1 yr life)	1.49	
Total	2.98	0.017
Total Variable Operating Costs (@ 65% utilization)		0.075
Cost of Capital (15% per year)		0.204
Total Annual Operating Cost		0.397

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION M

System: 1 Engine (2 6 Cylinder)
1.8 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Takeda Process Unit	0.405	
Cyclone	0.015	
Baghouse	0.075	
Induced Draft Fan	0.005	
Differential Boiler Cost	(0.012)	
Total Equipment	0.488	
Installation Costs:	0.452	
Total Installed Equipment Cost		0.940
Engineering and Home Office Fees, General		
Facilities: 20% Contingency	0.338	
Total Plant Cost	1.278	
Royalties	0.005	
Preproduction Costs and Inventory Capital	0.084	
Initial Supplies and Materials	0.042	
Total Capital Cost		1.410

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 0.5		
Operating Labor (@ \$21.55/hour)	0.094	
Maintenance Factor: 0.08		
Maintenance Labor Cost	0.030	
Overhead Labor Cost	0.037	
Total Labor Cost	0.161	
Maintenance Supplies Cost	0.045	
Total Operating and Maintenance Cost	0.206	
Fixed Operating and Maintenance Cost		0.134
Variable Operating and Maintenance Cost	0.072	
Variable Operating Cost:	\$/hour	
Ammonia @ \$0.25/lb	4.13	
Sorbent @ \$70 /ton	0.60	
Catalyst @ (2 yr life)	7.17	
Raw Water @ \$0.60/1000 gal	0.02	
Steam @ \$5.64/1000 lb	10.63	
Electricity @ \$0.05/KWh	0.94	
Disposal @ \$9.50/ton	1.66	
Bag @ (1 yr life)	1.49	
Total	26.65	0.152
Total Variable Operating Costs (@ 65% utilization)		0.224
Cost of Capital (15% per year)		0.211
Total Annual Operating Cost		0.570

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION N

System: 1 Engine (2 6 Cylinder)
1.8 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----
Spray Dryer	0.451
Cyclone	0.015
Baghouse (275 F)	0.075
Induced Draft Fan	0.005
Differential Boiler Cost	0.023
Total Equipment	0.569
Installation Costs:	0.338
Total Installed Equipment Cost	0.907
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.327
Total Plant Cost	1.234
Preproduction Costs and Inventory Capital	0.055
Initial Supplies and Materials	0.001
Total Capital Cost	1.290

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 0.5		
Operating Labor (@ \$21.55/hour)	0.094	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.018	
Overhead Labor Cost	0.034	
Total Labor Cost	0.146	
Maintenance Supplies Cost	0.027	
Total Operating and Maintenance Cost	0.173	
Fixed Operating and Maintenance Cost		0.112
Variable Operating and Maintenance Cost	0.061	
Variable Operating Cost:	\$/hour	
Sorbent @ \$70 /ton	2.10	
Raw Water @ \$0.60/1000 gal	0.02	
Steam @ \$3.64/1000 lb	3.91	
Electricity @ \$0.05/KWh	1.87	
Disposal @ \$20/ton	0.51	
Bag @ (1 yr life)	1.49	
Total	11.90	0.068
Total Variable Operating Costs (@ 65% utilization)		0.128
Cost of Capital (15% per year)		0.193
Total Annual Operating Cost		0.434

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION A

System: 4 Engines (2 6 Cylinder)
7.2 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----	
SCR Unit	0.433	
Duct Burner	0.033	
Spray Dryer	0.797	
Cyclone	0.059	
Baghouse	0.132	
Induced Draft Fan	0.014	
Differential Boiler Cost	0.060	
Total Equipment	1.528	
Installation Costs:	0.786	
Total Installed Equipment Cost		2.314
Engineering and Home Office Fees, General Facilities: 20% Contingency	0.833	
Total Plant Cost	3.147	
Royalties	0.003	
Preproduction Costs and Inventory Capital	0.201	
Initial Supplies and Materials	0.298	
Total Capital Cost		3.649

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.045	
Overhead Labor Cost	0.070	
Total Labor Cost	0.304	
Maintenance Supplies Cost	0.068	
Total Operating and Maintenance Cost	0.372	
Fixed Operating and Maintenance Cost		0.242
Variable Operating and Maintenance Cost	0.130	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	11.59	
Ammonia @ \$0.25/lb	16.32	
Sorbent @ \$70 /ton	8.40	
Catalyst @ (2 yr life)	25.62	
Raw Water @ \$0.60/1000 gal	0.09	
Steam @ \$5.64/1000 lb	6.04	
Electricity @ \$0.05/KWh	3.96	
Disposal @ \$6.50/ton	1.14	
Bag @ (1 yr life)	4.47	
Total	73.02	0.416
Total Variable Operating Costs (@ 65% utilization)		0.546
Cost of Capital (15% per year)		0.547
Total Annual Operating Cost		1.335

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION B

System: 4 Engines (2 6 Cylinder)
7.2 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----
Reburning Unit	0.134
Low Temperature Lime Injection	0.057
Cyclone	0.059
Baghouse	0.132
Induced Draft Fan	0.014
Differential Boiler Cost	0.079
Total Equipment	0.475
Installation Costs:	0.198
Total Installed Equipment Cost	0.673
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.242
Total Plant Cost	0.915
Preproduction Costs and Inventory Capital	0.063
Initial Supplies and Materials	0.009
Total Capital Cost	0.987

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.011	
Overhead Labor Cost	0.060	
Total Labor Cost	0.260	
Maintenance Supplies Cost	0.016	
Total Operating and Maintenance Cost	0.276	
Fixed Operating and Maintenance Cost		0.179
Variable Operating and Maintenance Cost	0.097	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	54.82	
Sorbent @ \$70 /ton	8.40	
Steam @ \$5.64/1000 lb	(66.21)	
Electricity @ \$0.05/KWh	3.83	
Disposal @ \$6.50/ton	1.14	
Bag @ (1 yr life)	4.47	
Total	6.45	0.037
Total Variable Operating Costs (@ 65% utilization)		0.134
Cost of Capital (15% per year)		0.148
Total Annual Operating Cost		0.461

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION C

System: 4 Engines (2 6 Cylinder)
7.2 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----	
Reburning Unit	0.134	
High Temperature Lime Injection	0.057	
Cyclone	0.059	
Daghouse	0.132	
Induced Draft Fan	0.014	
Differential Boiler Cost	0.079	
Total Equipment	0.475	
Installation Costs:	0.198	
Total Installed Equipment Cost		0.673
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.242	
Total Plant Cost	0.915	
Preproduction Costs and Inventory Capital	0.063	
Initial Supplies and Materials	0.009	
Total Capital Cost		0.987

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.011	
Overhead Labor Cost	0.060	
Total Labor Cost	0.260	
Maintenance Supplies Cost	0.016	
Total Operating and Maintenance Cost	0.276	
Fixed Operating and Maintenance Cost		0.179
Variable Operating and Maintenance Cost	0.097	
Variable Operating Cost:		
Natural Gas @ \$3.50/1000 cu. ft.	54.82	
Sorbent @ \$70 /ton	8.40	
Steam @ \$5.64/1000 lb	(66.21)	
Electricity @ \$0.05/KWh	3.83	
Disposal @ \$6.50/ton	1.14	
Bag @ (1 yr life)	4.47	
Total	6.45	0.037
Total Variable Operating Costs (@ 65% utilization)		0.134
Cost of Capital (15% per year)		0.148
Total Annual Operating Cost		0.461

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION D

System: 4 Engines (2 1/2 Cylinder)
7.2 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Calcium Fuel Additive (Ca/S = 1)	0.000	
Cyclone	0.059	
High Temperature Lime Injection (Ca/S = 1)	0.057	
Shell/UOP Unit with Granular Bed	0.795	
Induced Draft Fan	0.014	
Differential Boiler Cost	0.060	
Total Equipment	0.985	
Installation Costs:	0.616	
Total Installed Equipment Cost		1.601
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.576	
Total Plant Cost	2.177	
Royalties	0.009	
Preproduction Costs and Inventory Capital	0.909	
Initial Supplies and Materials	0.330	
Total Capital Cost		3.415

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.09		
Maintenance Labor Cost	0.058	
Overhead Labor Cost	0.074	
Total Labor Cost	0.321	
Maintenance Supplies Cost	0.086	
Total Operating and Maintenance Cost	0.407	
Fixed Operating and Maintenance Cost		0.265
Variable Operating and Maintenance Cost	0.142	
Variable Operating Cost:	\$/hour	
Ammonia @ \$0.25/lb	16.32	
Fuel Additive @ \$2.07/lb	351.50	
Catalyst @ (2 yr life)	10.88	
Cooling Water @ \$0.15/1000 gal	0.81	
Steam @ \$5.64/1000 lb	6.02	
Electricity @ \$0.05/KWh	3.82	
Disposal @ \$6.50/ton	1.90	
Total	391.25	2.228
Total Variable Operating Costs (@ 65% utilization)		2.370
Cost of Capital (15% per year)		0.512
Total Annual Operating Cost		3.147

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION J

System: 4 Engines (2 6 Cylinder)
7.2 MWe power output

CAPITAL

Equipment:	Cost (MM \$)
High Temperature Lime Injection	0.057
Duct Burner	0.134
Ammonia Injection in Baghouse (at 450 F)	0.084
Cyclone	0.059
Insulated Baghouse	0.176
Induced Draft Fan	0.014
Differential Boiler Cost	0.002
Total Equipment	0.526
Installation Costs:	0.265
Total Installed Equipment Cost	0.791
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.285
Total Plant Cost	1.076
Preproduction Costs and Inventory Capital	0.207
Initial Supplies and Materials	0.009
Total Capital Cost	1.292

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.013	
Overhead Labor Cost	0.060	
Total Labor Cost	0.262	
Maintenance Supplies Cost	0.019	
Total Operating and Maintenance Cost	0.281	
Fixed Operating and Maintenance Cost		0.183
Variable Operating and Maintenance Cost	0.098	
Variable Operating Cost:		
Natural Gas @ \$3.50/1000 cu. ft.	44.40	
Ammonia @ \$0.25/lb	16.32	
Sorbent @ \$70 /ton	8.40	
Steam @ \$5.64/1000 lb	(24.95)	
Electricity @ \$0.05/KWh	3.83	
Disposal @ \$6.50/ton	1.14	
Bag @ (1 yr life)	4.47	
Total	53.61	0.305
Total Variable Operating Costs (@ 65% utilization)		0.403
Cost of Capital (15% per year)		0.194
Total Annual Operating Cost		0.780

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION K

System: 4 Engines (@ 6 Cylinder)
7.2 MWe power output

CAPITAL

Equipment:	Cost (MM \$)
SCR Unit	0.433
Duct Burner	0.033
Low Temperature Lime Injection	0.057
Cyclone	0.059
Baghouse	0.132
Induced Draft Fan	0.014
Differential Boiler Cost	0.060
Total Equipment	0.788
Installation Costs:	0.328
Total Installed Equipment Cost	1.116
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.402
Total Plant Cost	1.518
Royalties	0.003
Preproduction Costs and Inventory Capital	0.187
Initial Supplies and Materials	0.298
Total Capital Cost	1.957

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.017	
Overhead Labor Cost	0.062	
Total Labor Cost	0.268	
Maintenance Supplies Cost	0.025	
Total Operating and Maintenance Cost	0.293	
Fixed Operating and Maintenance Cost		0.191
Variable Operating and Maintenance Cost	0.102	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	11.59	
Ammonia @ \$0.25/lb	16.32	
Sorbent @ \$70 /ton	8.40	
Catalyst @ (2 yr life)	25.62	
Steam @ \$5.64/1000 lb	6.02	
Electricity @ \$0.05/KWh	3.83	
Disposal @ \$6.50/ton	1.14	
Bag @ (1 yr life)	4.47	
Total	77.39	0.441
Total Variable Operating Costs (@ 65% utilization)		0.543
Cost of Capital (15% per year)		0.301
Total Annual Operating Cost		1.035

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION L

System: 4 Engines (2 6 Cylinder)
7.2 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Reburning Unit	0.134	
Spray Dryer	0.797	
Cyclone	0.059	
Baghouse	0.132	
Induced Draft Fan	0.014	
Differential Boiler Cost	0.079	
Total Equipment	1.215	
Installation Costs:	0.656	
Total Installed Equipment Cost		1.871
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.674	
Total Plant Cost	2.545	
Preproduction Costs and Inventory Capital	0.109	
Initial Supplies and Materials	0.009	
Total Capital Cost		2.662

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.037	
Overhead Labor Cost	0.068	
Total Labor Cost	0.294	
Maintenance Supplies Cost	0.056	
Total Operating and Maintenance Cost	0.350	
Fixed Operating and Maintenance Cost		0.228
Variable Operating and Maintenance Cost	0.122	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	54.82	
Sorbent @ \$70 /ton	8.40	
Raw Water @ \$0.60/1000 gal	0.09	
Steam @ \$5.64/1000 lb	(66.21)	
Electricity @ \$0.05/KWh	3.96	
Disposal @ \$6.50/ton	1.14	
Bag @ (1 yr life)	4.47	
Total	6.67	0.038
Total Variable Operating Costs (@ 65% utilization)		0.161
Cost of Capital (15% per year)		0.399
Total Annual Operating Cost		0.788

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION M

System: 4 Engines (2 6 Cylinder)
7.2 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----	
Takeda Process Unit	0.626	
Cyclone	0.059	
Baghouse	0.132	
Induced Draft Fan	0.014	
Differential Boiler Cost	(0.029)	
Total Equipment	0.802	
Installation Costs:	0.733	
Total Installed Equipment Cost		1.535
Engineering and Home Office Fees, General Facilities- 20% Contingency	0.553	
Total Plant Cost	2.088	
Royalties	0.008	
Preproduction Costs and Inventory Capital	0.230	
Initial Supplies and Materials	0.169	
Total Capital Cost		2.494

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.08		
Maintenance Labor Cost	0.049	
Overhead Labor Cost	0.071	
Total Labor Cost	0.310	
Maintenance Supplies Cost	0.074	
Total Operating and Maintenance Cost	0.383	
Fixed Operating and Maintenance Cost		0.249
Variable Operating and Maintenance Cost	0.134	
Variable Operating Cost:	\$/hour	
Ammonia @ \$0.25/lb	16.32	
Sorbent @ \$70 /ton	2.39	
Catalyst @ (2 yr life)	28.66	
Raw Water @ \$0.60/1000 gal	0.08	
Steam @ \$5.64/1000 lb	42.50	
Electricity @ \$0.05/KWh	3.41	
Disposal @ \$9.50/ton	6.64	
Bag @ (1 yr life)	4.47	
Total	104.47	0.595
Total Variable Operating Costs (@ 65% utilization)		0.729
Cost of Capital (15% per year)		0.374
Total Annual Operating Cost		1.352

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION N

System: 4 Engines (2 6 Cylinder)
7.2 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----
Spray Dryer	0.797
Cyclone	0.059
Baghouse (275 F)	0.132
Induced Draft Fan	0.014
Differential Boiler Cost	0.055
Total Equipment	1.057
Installation Costs:	0.616
Total Installed Equipment Cost	1.673
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.602
Total Plant Cost	2.276
Preproduction Costs and Inventory Capital	0.129
Initial Supplies and Materials	0.000
Total Capital Cost	2.404

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.033	
Overhead Labor Cost	0.067	
Total Labor Cost	0.289	
Maintenance Supplies Cost	0.050	
Total Operating and Maintenance Cost	0.339	
Fixed Operating and Maintenance Cost		0.221
Variable Operating and Maintenance Cost	0.118	
Variable Operating Cost:		
Sorbent @ \$70 /ton	8.40	
Raw Water @ \$0.60/1000 gal	0.09	
Steam @ \$5.64/1000 lb	23.62	
Electricity @ \$0.05/KWh	3.91	
Disposal @ \$20/ton	2.00	
Bag @ (1 yr life)	4.47	
Total	42.49	0.242
Total Variable Operating Costs (@ 65% utilization)		0.361
Cost of Capital (15% per year)		0.361
Total Annual Operating Cost		0.942

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION A

System: 2 Engines (2 20 Cylinder)
12 Mw power output

CAPITAL

Equipment:	-----Cost (MM \$)-----
SCR Unit	0.637
Duct Burner	0.033
Spray Dryer	1.013
Cyclone	0.059
Baghouse	0.181
Induced Draft Fan	0.024
Differential Boiler Cost	0.082
Total Equipment	2.029
Installation Costs:	1.032
Total Installed Equipment Cost	3.061
Engineering and Home Office Fees, General	
Facilities: 20% Contingency	1.102
Total Plant Cost	4.163
Royalties	0.003
Preproduction Costs and Inventory Capital	0.272
Initial Supplies and Materials	0.491
Total Capital Cost	4.929

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.060	
Overhead Labor Cost	0.075	
Total Labor Cost	0.323	
Maintenance Supplies Cost	0.091	
Total Operating and Maintenance Cost	0.414	
Fixed Operating and Maintenance Cost		0.269
Variable Operating and Maintenance Cost	0.145	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	19.32	
Ammonia @ \$0.25/lb	27.23	
Sorbent @ \$70 /ton	14.77	
Catalyst @ (2 yr life)	42.71	
Raw Water @ \$0.60/1000 gal	0.14	
Steam @ \$5.64/1000 lb	10.05	
Electricity @ \$0.05/KWh	5.71	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	105.84	0.603
Total Variable Operating Costs (@ 65% utilization)		0.748
Cost of Capital (15% per year)		0.739
Total Annual Operating Cost		1.756

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION B

System: 2 Engines (2 20 Cylinder)
12 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Reburning Unit	0.110	
Low Temperature Lime Injection	0.074	
Cyclone	0.059	
Baghouse	0.181	
Induced Draft Fan	0.024	
Differential Boiler Cost	0.107	
Total Equipment	0.555	
Installation Costs:	0.239	
Total Installed Equipment Cost		0.794
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.286	
Total Plant Cost	1.080	
Preproduction Costs and Inventory Capital	0.086	
Initial Supplies and Materials	0.015	
Total Capital Cost		1.180

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.013	
Overhead Labor Cost	0.061	
Total Labor Cost	0.262	
Maintenance Supplies Cost	0.019	
Total Operating and Maintenance Cost	0.281	
Fixed Operating and Maintenance Cost		0.183
Variable Operating and Maintenance Cost	0.098	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu. ft.	91.35	
Sorbent @ \$70 /ton	14.77	
Steam @ \$5.64/1000 lb	(110.36)	
Electricity @ \$0.05/KWh	5.58	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	7.35	0.053
Total Variable Operating Costs (@ 65% utilization)		0.152
Cost of Capital (15% per year)		0.177
Total Annual Operating Cost		0.512

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION C

System: 2 Engines (2 20 Cylinder)
12 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Reburning Unit	0.110	
High Temperature Lime Injection	0.074	
Cyclone	0.059	
Baghouse	0.181	
Induced Draft Fan	0.024	
Differential Boiler Cost	0.107	
Total Equipment	0.555	
Installation Costs:	0.239	
Total Installed Equipment Cost		0.794
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.286	
Total Plant Cost	1.080	
Preproduction Costs and Inventory Capital	0.086	
Initial Supplies and Materials	0.015	
Total Capital Cost		1.180

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.013	
Overhead Labor Cost	0.061	
Total Labor Cost	0.262	
Maintenance Supplies Cost	0.019	
Total Operating and Maintenance Cost	0.281	
Fixed Operating and Maintenance Cost		0.183
Variable Operating and Maintenance Cost	0.098	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	91.35	
Sorbent @ \$70 /ton	14.77	
Steam @ \$5.64/1000 lb	(110.36)	
Electricity @ \$0.05/KWh	5.58	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	9.35	0.053
Total Variable Operating Costs (@ 65% utilization)		0.152
Cost of Capital (15% per year)		0.177
Total Annual Operating Cost		0.512

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION D

System: 2 Engines (2 20 Cylinder)
12 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Calcium Fuel Additive (Ca/S = 1)	0.000	
Cyclone	0.059	
High Temperature Lime Injection (Ca/S = 1)	0.074	
Shell/UDF Unit with Granular Bed	1.255	
Induced Draft Fan	0.024	
Differential Boiler Cost	0.082	
Total Equipment	1.494	
Installation Costs:	0.947	
Total Installed Equipment Cost		2.441
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.879	
Total Plant Cost	3.320	
Royalties:	0.014	
Preproduction Costs and Inventory Capital	1.479	
Initial Supplies and Materials	0.546	
Total Capital Cost		5.359

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.09		
Maintenance Labor Cost	0.088	
Overhead Labor Cost	0.083	
Total Labor Cost	0.360	
Maintenance Supplies Cost	0.132	
Total Operating and Maintenance Cost	0.492	
Fixed Operating and Maintenance Cost		0.320
Variable Operating and Maintenance Cost	0.172	
Variable Operating Cost:	\$/hour	
Ammonia @ \$0.25/lb	27.23	
Fuel Additive @ \$2.07/lb	579.22	
Catalyst @ (2 yr life)	18.66	
Cooling Water @ \$0.15/1000 gal	1.34	
Steam @ \$5.64/1000 lb	10.05	
Electricity @ \$0.05/KWh	5.60	
Disposal @ \$6.50/ton	2.54	
Total	644.64	3.671
Total Variable Operating Costs (@ 65% utilization)		3.843
Cost of Capital (15% per year)		0.804
Total Annual Operating Cost		4.966

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION J

System: 2 Engines (2 20 Cylinder)
12 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----	
High Temperature Lime Injection	0.074	
Duct Burner	0.110	
Ammonia Injection in Baghouse (at 450 F)	0.093	
Cyclone	0.059	
Insulated Baghouse	0.244	
Induced Draft Fan	0.024	
Differential Boiler Cost	0.003	
Total Equipment	0.607	
Installation Costs:	0.323	
Total Installed Equipment Cost		0.930
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.335	
Total Plant Cost	1.265	
Preproduction Costs and Inventory Capital	0.266	
Initial Supplies and Materials	0.015	
Total Capital Cost		1.546

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.015	
Overhead Labor Cost	0.061	
Total Labor Cost	0.265	
Maintenance Supplies Cost	0.022	
Total Operating and Maintenance Cost	0.287	
Fixed Operating and Maintenance Cost		0.187
Variable Operating and Maintenance Cost	0.100	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	74.10	
Ammonia @ \$0.25/lb	27.23	
Sorbent @ \$70 /ton	14.77	
Steam @ \$5.64/1000 lb	(28.04)	
Electricity @ \$0.05/KWh	5.58	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	101.56	0.578
Total Variable Operating Costs (@ 65% utilization)		0.676
Cost of Capital (15% per year)		0.232
Total Annual Operating Cost		1.097

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION K

System: 2 Engines (@ 20 Cylinder)
12 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
SCR Unit	0.637	
Duct Burner	0.033	
Low Temperature Lime Injection	0.074	
Cyclone	0.059	
Baghouse	0.181	
Induced Draft Fan	0.024	
Differential Boiler Cost	0.082	
Total Equipment	1.090	
Installation Costs:	0.451	
Total Installed Equipment Cost		1.541
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.553	
Total Plant Cost	2.096	
Royalties	0.003	
Preproduction Costs and Inventory Capital	0.276	
Initial Supplies and Materials	0.491	
Total Capital Cost		2.866

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.024	
Overhead Labor Cost	0.064	
Total Labor Cost	0.276	
Maintenance Supplies Cost	0.036	
Total Operating and Maintenance Cost	0.313	
Fixed Operating and Maintenance Cost		0.203
Variable Operating and Maintenance Cost	0.110	
Variable Operating Cost:		
Natural Gas @ \$3.50/1000 cu.ft.	19.32	
Ammonia @ \$0.25/lb	27.23	
Sorbent @ \$70 /ton	14.77	
Catalyst @ (2 yr life)	42.71	
Steam @ \$5.64/1000 lb	10.05	
Electricity @ \$0.05/KWh	5.58	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	127.67	0.727
Total Variable Operating Costs (@ 65% utilization)		0.837
Cost of Capital (15% per year)		0.430
Total Annual Operating Cost		1.470

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION L

System: 2 Engines (@ 20 Cylinder)
12 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Reburning Unit	0.110	
Spray Dryer	1.013	
Cyclone	0.059	
Baghouse	0.181	
Induced Draft Fan	0.025	
Differential Boiler Cost	0.107	
Total Equipment	1.494	
Installation Costs:	0.820	
Total Installed Equipment Cost		2.314
Engineering and Home Office Fecs. General Facilities- 20% Contingency	0.833	
Total Plant Cost	3.147	
Preproduction Costs and Inventory Capital	0.137	
Initial Supplies and Materials	0.015	
Total Capital Cost		3.299

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.35/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.046	
Overhead Labor Cost	0.071	
Total Labor Cost	0.306	
Maintenance Supplies Cost	0.069	
Total Operating and Maintenance Cost	0.375	
Fixed Operating and Maintenance Cost		0.244
Variable Operating and Maintenance Cost	0.131	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	91.35	
Sorbent @ \$70 /ton	14.77	
Raw Water @ \$0.60/1000 gal	0.14	
Steam @ \$5.64/1000 lb (110.36)		
Electricity @ \$0.05/KWh	5.71	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	9.62	0.053
Total Variable Operating Costs (@ 65% utilization)		0.186
Cost of Capital (15% per year)		0.493
Total Annual Operating Cost		0.925

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION M

System: 2 Engines (@ 20 Cylinder)
12 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Takeda Process Unit	0.740	
Cyclone	0.059	
Baghouse	0.181	
Induced Draft Fan	0.024	
Differential Boiler Cost	(0.039)	
Total Equipment	0.965	
Installation Costs:	0.881	
Total Installed Equipment Cost		1.846
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.665	
Total Plant Cost	2.511	
Royalties	0.010	
Preproduction Costs and Inventory Capital	0.337	
Initial Supplies and Materials	0.282	
Total Capital Cost		3.140

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.08		
Maintenance Labor Cost	0.059	
Overhead Labor Cost	0.074	
Total Labor Cost	0.322	
Maintenance Supplies Cost	0.089	
Total Operating and Maintenance Cost	0.411	
Fixed Operating and Maintenance Cost		0.267
Variable Operating and Maintenance Cost	0.144	
Variable Operating Cost:		
Ammonia @ \$0.25/lb	27.23	
Sorbent @ \$70 /ton	3.98	
Catalyst @ (2 yr life)	47.77	
Raw Water @ \$0.60/1000 gal	0.14	
Steam @ \$5.64/1000 lb	70.88	
Electricity @ \$0.05/KWh	5.43	
Disposal @ \$9.50/ton	11.32	
Bag @ (1 yr life)	5.78	
Total	172.53	0.982
Total Variable Operating Costs (@ 65% utilization)		1.126
Cost of Capital (15% per year)		0.471
Total Annual Operating Cost		1.864

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION N

System: 2 Engines (2 20 Cylinder)
12 Mw power output

CAPITAL

Equipment:	-----Cost (MM \$)-----
Spray Dryer	1.013
Cyclone	0.059
Baghouse (275 F)	0.181
Induced Draft Fan	0.024
Differential Boiler Cost	0.072
Total Equipment	1.349
Installation Costs:	0.786
Total Installed Equipment Cost	2.135
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.769
Total Plant Cost	2.904
Preproduction Costs and Inventory Capital	0.174
Initial Supplies and Materials	0.005
Total Capital Cost	3.082

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.043	
Overhead Labor Cost	0.070	
Total Labor Cost	0.301	
Maintenance Supplies Cost	0.064	
Total Operating and Maintenance Cost	0.365	
Fixed Operating and Maintenance Cost		0.237
Variable Operating and Maintenance Cost	0.128	
Variable Operating Cost: \$/hour		
Sorbent @ \$70 /ton	14.77	
Raw Water @ \$0.60/1000 gal	0.14	
Steam @ \$5.64/1000 lb	39.40	
Electricity @ \$0.05/KWh	5.66	
Disposal @ \$20/ton	3.67	
Bag @ (1 yr life)	5.78	
Total	69.42	0.395
Total Variable Operating Costs (@ 25% utilization)		0.523
Cost of Capital (15% per year)		0.462
Total Annual Operating Cost		1.222

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION A

System: 2 Engines (2 20 Cylinder)
12 MWe power output (no cogeneration)

CAPITAL

Equipment:	-----Cost (MM \$)-----
SCR Unit	0.637
Duct Burner	0.033
Spray Dryer	1.013
Cyclone	0.059
Baghouse	0.181
Induced Draft Fan	0.024
Gas Cooler	0.104
Total Equipment	2.051
Installation Costs:	1.072
Total Installed Equipment Cost	3.123
Engineering and Home Office Fees, General Facilities, 20% Contingency	1.124
Total Plant Cost	4.247
Royalties	0.003
Preproduction Costs and Inventory Capital	0.312
Initial Supplies and Materials	0.491
Total Capital Cost	5.053

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.062	
Overhead Labor Cost	0.075	
Total Labor Cost	0.326	
Maintenance Supplies Cost	0.092	
Total Operating and Maintenance Cost	0.418	
Fixed Operating and Maintenance Cost		0.272
Variable Operating and Maintenance Cost	0.146	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	19.32	
Ammonia @ \$0.25/lb	27.23	
Sorbent @ \$70 /ton	14.77	
Catalyst @ (2 yr life)	42.71	
Raw Water @ \$0.60/1000 gal	1.90	
Electricity @ \$0.05/KWh	5.82	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	119.76	0.682
Total Variable Operating Costs (@ 65% utilization)		0.828
Cost of Capital (15% per year)		0.758
Total Annual Operating Cost		1.858

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION B

System: 2 Engines (2 20 Cylinder)
12 MWe power output (no cogeneration)

CAPITAL

Equipment:	Cost (MM \$)	
Reburning Unit	0.110	
Low Temperature Lime Injection	0.074	
Cyclone	0.059	
Baghouse	0.181	
Induced Draft Fan	0.024	
Gas Cooler	0.115	
Total Equipment	0.563	
Installation Costs:	0.283	
Total Installed Equipment Cost		0.846
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.305	
Total Plant Cost	1.151	
Preproduction Costs and Inventory Capital	0.170	
Initial Supplies and Materials	0.015	
Total Capital Cost		1.335

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.014	
Overhead Labor Cost	0.061	
Total Labor Cost	0.263	
Maintenance Supplies Cost	0.020	
Total Operating and Maintenance Cost	0.284	
Fixed Operating and Maintenance Cost		0.184
Variable Operating and Maintenance Cost	0.100	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu. ft.	91.35	
Sorbent @ \$70 /ton	14.77	
Raw Water @ \$0.60/1000 gal	3.46	
Electricity @ \$0.05/KWh	5.69	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	123.28	0.702
Total Variable Operating Costs (@ 65% utilization)		0.801
Cost of Capital (15% per year)		0.200
Total Annual Operating Cost		1.186

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION C

System: 2 Engines (2 20 Cylinder)
12 MWe power output (no cogeneration)

CAPITAL

Equipment:	Cost (MM \$)	
Reburning Unit	0.110	
High Temperature Lime Injection	0.074	
Cyclone	0.059	
Baghouse	0.181	
Induced Draft Fan	0.024	
Gas Cooler	0.115	
Total Equipment	0.563	
Installation Costs:	0.283	
Total Installed Equipment Cost		0.846
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.305	
Total Plant Cost	1.151	
Preproduction Costs and Inventory Capital	0.170	
Initial Supplies and Materials	0.013	
Total Capital Cost		1.335

OPERATING COSTS

Cost (MM \$/yr)		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.014	
Overhead Labor Cost	0.061	
Total Labor Cost	0.263	
Maintenance Supplies Cost	0.020	
Total Operating and Maintenance Cost	0.284	
Fixed Operating and Maintenance Cost	0.184	
Variable Operating and Maintenance Cost	0.100	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	91.35	
Sorbent @ \$70 /ton	14.77	
Raw Water @ \$0.60/1000 gal	3.46	
Electricity @ \$0.05/KWh	5.69	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	123.28	0.702
Total Variable Operating Costs (@ 65% utilization)	0.801	
Cost of Capital (15% per year)	0.200	
Total Annual Operating Cost	1.186	

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION D

System: 2 Engines (2 20 Cylinder)
12 MWe power output (no cogeneration)

CAPITAL

Equipment:	Cost (MM \$)	
Calcium Fuel Additive (Ca/S = 1)	0.000	
Cyclone	0.059	
High Temperature Lime Injection (Ca/S = 1)	0.074	
Shell/UDF Unit with Granular Bed	1.255	
Induced Draft Fan	0.024	
Gas Cooler	0.104	
Total Equipment	1.516	
Installation Costs:	0.987	
Total Installed Equipment Cost		2.503
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.901	
Total Plant Cost	3.404	
Royalties	0.014	
Preproduction Costs and Inventory Capital	1.475	
Initial Supplies and Materials	0.546	
Total Capital Cost		5.440

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.09		
Maintenance Labor Cost	0.090	
Overhead Labor Cost	0.084	
Total Labor Cost	0.363	
Maintenance Supplies Cost	0.135	
Total Operating and Maintenance Cost	0.498	
Fixed Operating and Maintenance Cost		0.324
Variable Operating and Maintenance Cost	0.174	
Variable Operating Cost:	\$/hour	
Ammonia @ \$0.25/lb	27.23	
Fuel Additive @ \$2.07/lb	579.22	
Catalyst @ (2 yr life)	18.66	
Raw Water @ \$0.60/1000 gal	1.76	
Cooling Water @ \$0.15/1000 gal	1.34	
Electricity @ \$0.05/KWh	5.71	
Disposal @ \$6.50/ton	2.54	
Total	636.46	3.624
Total Variable Operating Costs (@ 55% utilization)		3.798
Cost of Capital (15% per year)		0.816
Total Annual Operating Cost		4.938

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION J

System: 2 Engines (2 20 Cylinder)
12 MWe power output (no cogeneration)

CAPITAL

Equipment:	Cost (MM \$)	
High Temperature Lime Injection	0.074	
Duct Burner	0.110	
Ammonia Injection in Baghouse (at 450 F)	0.093	
Cyclone	0.059	
Insulated Baghouse	0.244	
Induced Draft Fan	0.024	
Gas Cooler	0.112	
Total Equipment	0.716	
Installation Costs:	0.366	
Total Installed Equipment Cost		1.082
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.390	
Total Plant Cost	1.472	
Preproduction Costs and Inventory Capital	0.285	
Initial Supplies and Materials	0.015	
Total Capital Cost		1.772

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.33/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.017	
Overhead Labor Cost	0.062	
Total Labor Cost	0.268	
Maintenance Supplies Cost	0.026	
Total Operating and Maintenance Cost	0.294	
Fixed Operating and Maintenance Cost		0.191
Variable Operating and Maintenance Cost	0.103	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	74.10	
Ammonia @ \$0.25/lb	27.23	
Sorbent @ \$70 /ton	14.77	
Raw Water @ \$0.60/1000 gal	2.45	
Electricity @ \$0.05/KWh	5.69	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	132.25	0.753
Total Variable Operating Costs (@ 65% utilization)		0.856
Cost of Capital (15% per year)		0.266
Total Annual Operating Cost		1.313

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION K

System: 2 Engines (2 20 Cylinder)
12 MWe power output (no cogeneration)

CAPITAL

Equipment:	Cost (MM \$)	
SCR Unit	0.637	
Duct Burner	0.033	
Low Temperature Lime Injection	0.074	
Cyclone	0.059	
Baghouse	0.181	
Induced Draft Fan	0.024	
Gas Cooler	0.104	
Total Equipment	1.112	
Installation Costs:	0.491	
Total Installed Equipment Cost		1.603
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.577	
Total Plant Cost	2.180	
Royalties	0.003	
Preproduction Costs and Inventory Capital	0.273	
Initial Supplies and Materials	0.491	
Total Capital Cost		2.947

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1	
Operating Labor (@ \$21.55/hour)	0.189
Maintenance Factor: 0.5	
Maintenance Labor Cost	0.025
Overhead Labor Cost	0.064
Total Labor Cost	0.278

Maintenance Supplies Cost	0.037
Total Operating and Maintenance Cost	0.315

Fixed Operating and Maintenance Cost	0.205
--------------------------------------	-------

Variable Operating and Maintenance Cost	0.110
---	-------

Variable Operating Cost:	\$/hour
Natural Gas @ \$3.50/1000 cu. ft.	19.32
Ammonia @ \$0.25/lb	27.23
Sorbent @ \$70 /ton	14.77
Catalyst @ (2 yr life)	42.71
Raw Water @ \$0.60/1000 gal	1.76
Electricity @ \$0.05/KWh	5.69
Disposal @ \$6.50/ton	2.23
Bag @ (1 yr life)	5.78

Total	115.49	0.680
-------	--------	-------

Total Variable Operating Costs (@ 65% utilization)	0.790
--	-------

Cost of Capital (15% per year)	0.442
--------------------------------	-------

Total Annual Operating Cost	1.437
-----------------------------	-------

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION L

System: 2 Engines (2 20 Cylinder)
12 MWe power output (no cogeneration)

CAPITAL

Equipment:	Cost (MM \$)
Reburning Unit	0.110
Spray Dryer	1.013
Cyclone	0.059
Baghouse	0.181
Induced Draft Fan	0.025
Gas Cooler	0.115
Total Equipment	1.502
Installation Costs:	0.864
Total Installed Equipment Cost	2.366
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.852
Total Plant Cost	3.218
Preproduction Costs and Inventory Capital	0.221
Initial Supplies and Materials	0.015
Total Capital Cost	3.453

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.047	
Overhead Labor Cost	0.071	
Total Labor Cost	0.307	
Maintenance Supplies Cost	0.071	
Total Operating and Maintenance Cost	0.378	
Fixed Operating and Maintenance Cost		0.246
Variable Operating and Maintenance Cost	0.132	
Variable Operating Cost:		
Natural Gas @ \$3.50/1000 cu.ft.	91.35	
Sorbent @ \$70 /ton	14.77	
Raw Water @ \$0.60/1000 gal	3.60	
Electricity @ \$0.05/KWh	5.82	
Disposal @ \$6.50/ton	2.23	
Bag @ (1 yr life)	5.78	
Total	123.55	0.703
Total Variable Operating Costs (@ 65% utilization)		0.836
Cost of Capital (15% per year)		0.518
Total Annual Operating Cost		1.600

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION M

System: 2 Engines (@ 20 Cylinder)
12 MWe power output (no cogeneration)

CAPITAL

Equipment:	Cost (MM \$)	
Takeda Process Unit	0.740	
Cyclone	0.059	
Daghouse	0.181	
Induced Draft Fan	0.024	
Gas Cooler	0.102	
Total Equipment	1.106	
Installation Costs:	0.920	
Total Installed Equipment Cost		2.026
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.729	
Total Plant Cost	2.755	
Royalties	0.010	
Preproduction Costs and Inventory Capital	0.293	
Initial Supplies and Materials	0.282	
Total Capital Cost		3.340

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.08		
Maintenance Labor Cost	0.065	
Overhead Labor Cost	0.076	
Total Labor Cost	0.330	
Maintenance Supplies Cost	0.097	
Total Operating and Maintenance Cost	0.427	
Fixed Operating and Maintenance Cost		0.278
Variable Operating and Maintenance Cost	0.149	
Variable Operating Cost:	\$/hour	
Ammonia @ \$0.25/lb	27.23	
Sorbent @ \$70 /ton	3.98	
Catalyst @ (2 yr life)	47.77	
Raw Water @ \$0.60/1000 gal	1.04	
Electricity @ \$0.05/KWh	5.54	
Disposal @ \$9.50/ton	11.32	
Bag @ (1 yr life)	5.78	
Total	102.66	0.585
Total Variable Operating Costs (@ 65% utilization)		0.734
Cost of Capital (15% per year)		0.501
Total Annual Operating Cost		1.513

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION N

System: 2 Engines (2 20 Cylinder)
12 MWe power output (no cogeneration)

CAPITAL

Equipment:	Cost (MM \$)
Spray Dryer	1.013
Cyclone	0.059
Baghouse (275 F)	0.181
Induced Draft Fan	0.024
Gas Cooler	0.102
Total Equipment	1.379
Installation Costs:	0.825
Total Installed Equipment Cost	2.204
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.793
Total Plant Cost	2.997
Preproduction Costs and Inventory Capital	0.149
Initial Supplies and Materials	0.005
Total Capital Cost	3.151

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.044	
Overhead Labor Cost	0.070	
Total Labor Cost	0.303	
Maintenance Supplies Cost	0.066	
Total Operating and Maintenance Cost	0.369	
Fixed Operating and Maintenance Cost		0.240
Variable Operating and Maintenance Cost	0.129	
Variable Operating Cost:		
Sorbent @ \$70 /ton	14.77	
Raw Water @ \$0.60/1000 gal	1.08	
Electricity @ \$0.05/KWh	5.77	
Disposal @ \$20/ton	3.67	
Bag @ (1 yr life)	5.78	
Total	31.07	0.177
Total Variable Operating Costs (@ 65% utilization)		0.306
Cost of Capital (15% per year)		0.473
Total Annual Operating Cost		1.019

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION A

System: 4 Engines (2 20 Cylinder)
24 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
SCR Unit	1.040	
Duct Burner	0.055	
Spray Dryer	1.416	
Cyclone	0.119	
Baghouse	0.363	
Induced Draft Fan	0.043	
Differential Boiler Cost	0.125	
Total Equipment	3.161	
Installation Costs:	1.608	
Total Installed Equipment Cost		4.769
Engineering and Home Office Fees, General Facilities: 20% Contingency	1.717	
Total Plant Cost	6.486	
Royalties	0.007	
Preproduction Costs and Inventory Capital	0.576	
Initial Supplies and Materials	0.983	
Total Capital Cost		8.052

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.03		
Maintenance Labor Cost	0.094	
Overhead Labor Cost	0.085	
Total Labor Cost	0.368	
Maintenance Supplies Cost	0.141	
Total Operating and Maintenance Cost	0.509	
Fixed Operating and Maintenance Cost		0.331
Variable Operating and Maintenance Cost	0.178	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	38.64	
Ammonia @ \$0.25/lb	54.45	
Sorbent @ \$70 /ton	29.58	
Catalyst @ (2 yr life)	85.41	
Raw Water @ \$0.60/1000 gal	0.29	
Steam @ \$5.64/1000 lb	20.10	
Electricity @ \$0.05/KWh	10.24	
Disposal @ \$6.50/ton	4.47	
Bag @ (1 yr life)	11.56	
Total	254.74	1.430
Total Variable Operating Costs (@ 65% utilization)		1.628
Cost of Capital (15% per year)		1.208
Total Annual Operating Cost		3.167

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION B

System: 4 Engines (2 20 Cylinder)
24 MWe power output

CAPITAL

Equipment:	Cost (MM \$)
Reburning Unit	0.220
Low Temperature Lime Injection	0.107
Cyclone	0.119
Baghouse	0.363
Induced Draft Fan	0.043
Differential Boiler Cost	0.162
Total Equipment	1.014
Installation Costs:	0.461
Total Installed Equipment Cost	1.475
Engineering and Home Office Fees, General	
Facilities- 20% Contingency	0.531
Total Plant Cost	2.006
Preproduction Costs and Inventory Capital	0.140
Initial Supplies and Materials	0.030
Total Capital Cost	2.176

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.024	
Overhead Labor Cost	0.064	
Total Labor Cost	0.277	
Maintenance Supplies Cost	0.035	
Total Operating and Maintenance Cost	0.312	
Fixed Operating and Maintenance Cost		0.203
Variable Operating and Maintenance Cost	0.109	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu.ft.	182.70	
Sorbent @ \$70 /ton	29.58	
Steam @ \$5.64/1000 lb	(220.73)	
Electricity @ \$0.05/KWh	11.11	
Disposal @ \$6.50/ton	4.47	
Bag @ (1 yr life)	11.56	
Total	18.69	0.106
Total Variable Operating Costs (@ 65% utilization)		0.215
Cost of Capital (15% per year)		0.326
Total Annual Operating Cost		0.744

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION C

System: 4 Engines (2 20 Cylinder)
24 MWe power output

Equipment:	-----Cost (MM \$)-----	
Reburning Unit	0.220	
High Temperature Lime Injection	0.107	
Cyclone	0.119	
Baghouse	0.363	
Induced Draft Fan	0.043	
Differential Boiler Cost	0.162	
Total Equipment	1.014	
Installation Costs:	0.461	
Total Installed Equipment Cost		1.475
Engineering and Home Office Fees, General Facilities, 20% Contingency	0.531	
Total Plant Cost	2.006	
Preproduction Costs and Inventory Capital	0.140	
Initial Supplies and Materials	0.030	
Total Capital Cost		2.176

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.024	
Overhead Labor Cost	0.064	
Total Labor Cost	0.277	
Maintenance Supplies Cost	0.035	
Total Operating and Maintenance Cost	0.312	
Fixed Operating and Maintenance Cost		0.203
Variable Operating and Maintenance Cost	0.109	
Variable Operating Cost:		
Natural Gas @ \$3.50/1000 cu. ft.	182.70	
Sorbent @ \$70 /ton	29.58	
Steam @ \$5.64/1000 lb	(220.73)	
Electricity @ \$0.05/KWh	11.11	
Disposal @ \$6.50/ton	4.47	
Bag @ (1 yr life)	11.56	
Total	18.69	0.106
Total Variable Operating Costs (@ 65% utilization)		0.215
Cost of Capital (15% per year)		0.326
Total Annual Operating Cost		0.744

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION D

System: 4 Engines (@ 20 Cylinder)
24 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
Calcium Fuel Additive (Ca/S = 1)	0.000	
Cyclone	0.119	
High Temperature Lime Injection (Ca/S = 1)	0.107	
Shell/UOP Unit with Granular Bed	2.447	
Induced Draft Fan	0.043	
Differential Boiler Cost	0.125	
Total Equipment	2.841	
Installation Costs:	1.836	
Total Installed Equipment Cost		4.677
Engineering and Home Office Fees, General Facilities, 20% Contingency	1.684	
Total Plant Cost	6.361	
Royalties	0.023	
Preproduction Costs and Inventory Capital	2.821	
Initial Supplies and Materials	1.091	
Total Capital Cost		10.301

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.09		
Maintenance Labor Cost	0.089	
Overhead Labor Cost	0.083	
Total Labor Cost	0.361	
Maintenance Supplies Cost	0.134	
Total Operating and Maintenance Cost	0.495	
Fixed Operating and Maintenance Cost		0.322
Variable Operating and Maintenance Cost	0.173	
Variable Operating Cost:		
Ammonia @ \$0.25/lb	54.45	
Fuel Additive @ \$2.07/lb	1159.44	
Catalyst @ (2 yr life)	37.32	
Cooling Water @ \$0.15/1000 gal	2.69	
Steam @ \$5.64/1000 lb	20.10	
Electricity @ \$0.05/KWh	11.20	
Disposal @ \$6.50/ton	5.09	
Total	1290.29	7.347
Total Variable Operating Costs (@ 65% utilization)		7.520
Cost of Capital (15% per year)		1.545
Total Annual Operating Cost		9.387

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION J

System: 4 Engines (3 20 Cylinder)

24 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----	
High Temperature Lime Injection	0.107	
Duct Burner	0.220	
Ammonia Injection in Baghouse (at 450 F)	0.120	
Cyclone	0.119	
Insulated Baghouse	0.487	
Induced Draft Fan	0.043	
Differential Boiler Cost	0.004	
Total Equipment	1.100	
Installation Costs:	0.602	
Total Installed Equipment Cost		1.702
Engineering and Home Office Fees, General Facilities: 20% Contingency	0.613	
Total Plant Cost	2.315	
Preproduction Costs and Inventory Capital	0.508	
Initial Supplies and Materials	0.030	
Total Capital Cost		2.853

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.027	
Overhead Labor Cost	0.065	
Total Labor Cost	0.281	
Maintenance Supplies Cost	0.041	
Total Operating and Maintenance Cost	0.322	
Fixed Operating and Maintenance Cost		0.209
Variable Operating and Maintenance Cost	0.113	
Variable Operating Cost: \$/hour		
Natural Gas @ \$3.50/1000 cu.ft.	148.20	
Ammonia @ \$0.25/lb	54.45	
Sorbent @ \$70 /ton	29.58	
Steam @ \$5.64/1000 lb	(56.08)	
Electricity @ \$0.05/KWh	11.11	
Disposal @ \$6.50/ton	4.47	
Bag @ (1 yr life)	11.56	
Total	203.29	1.158
Total Variable Operating Costs (@ 65% utilization)		1.271
Cost of Capital (15% per year)		0.428
Total Annual Operating Cost		1.908

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION K

System: 4 Engines (2 20 Cylinder)
24 MWe power output

CAPITAL

Equipment:	Cost (MM \$)	
SCR Unit	1.040	
Duct Burner	0.053	
Low Temperature Lime Injection	0.107	
Cyclone	0.119	
Baghouse	0.363	
Induced Draft Fan	0.043	
Differential Boiler Cost	0.125	
Total Equipment	1.852	
Installation Costs:	0.797	
Total Installed Equipment Cost		2.649
Engineering and Home Office Fees, General		
Facilities: 20% Contingency	0.954	
Total Plant Cost	3.603	
Royalties	0.007	
Preproduction Costs and Inventory Capital	0.521	
Initial Supplies and Materials	0.983	
Total Capital Cost		5.114

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.04		
Maintenance Labor Cost	0.041	
Overhead Labor Cost	0.069	
Total Labor Cost	0.299	
Maintenance Supplies Cost	0.062	
Total Operating and Maintenance Cost	0.361	
Fixed Operating and Maintenance Cost		0.235
Variable Operating and Maintenance Cost	0.126	
Variable Operating Cost:		
Natural Gas @ \$3.50/1000 cu.ft.	38.64	
Ammonia @ \$0.25/lb	54.45	
Sorbent @ \$70 /ton	29.58	
Catalyst @ (2 yr life)	85.41	
Steam @ \$5.64/1000 lb	20.10	
Electricity @ \$0.05/KWh	11.11	
Disposal @ \$6.50/ton	4.47	
Bag @ (1 yr life)	11.56	
Total.	255.32	1.454
Total Variable Operating Costs (@ 65% utilization)		1.580
Cost of Capital (15% per year)		0.767
Total Annual Operating Cost		2.582

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION L

System: 4 Engines (@ 20 Cylinder)
24 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----	
Reburning Unit	0.220	
Spray Dryer	1.416	
Cyclone	0.119	
Baghouse	0.363	
Induced Draft Fan	0.043	
Differential Boiler Cost	0.162	
Total Equipment	2.323	
Installation Costs:	1.272	
Total Installed Equipment Cost		3.595
Engineering and Home Office Fees, General Facilities, 20% Contingency	1.294	
Total Plant Cost	4.889	
Preproduction Costs and Inventory Capital	0.214	
Initial Supplies and Materials	0.030	
Total Capital Cost		5.133

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.072	
Overhead Labor Cost	0.078	
Total Labor Cost	0.339	
Maintenance Supplies Cost	0.108	
Total Operating and Maintenance Cost	0.447	
Fixed Operating and Maintenance Cost		0.291
Variable Operating and Maintenance Cost	0.156	
Variable Operating Cost:	\$/hour	
Natural Gas @ \$3.50/1000 cu. ft.	182.70	
Sorbent @ \$70 /ton	29.58	
Raw Water @ \$0.60/1000 gal	0.19	
Steam @ \$5.64/1000 lb (220.73)		
Electricity @ \$0.05/KWh	10.24	
Disposal @ \$6.50/ton	4.47	
Bag @ (1 yr life)	11.56	
Total	18.11	0.103
Total Variable Operating Costs (@ 65% utilization)		0.259
Cost of Capital (15% per year)		0.770
Total Annual Operating Cost		1.320

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION M

System: 4 Engines (2 20 Cylinder)
24 MWe power output

CAPITAL

Equipment:	-----Cost (MM \$)-----	
Takeda Process Unit	1.001	
Cyclone	0.119	
Baghouse	0.363	
Induced Draft Fan	0.043	
Differential Boiler Cost	(0.060)	
Total Equipment	1.466	
Installation Costs:	1.307	
Total Installed Equipment Cost		2.773
Engineering and Home Office Fees, General		
Facilities: 20% Contingency	0.998	
Total Plant Cost	3.771	
Royalties	0.013	
Preproduction Costs and Inventory Capital	0.616	
Initial Supplies and Materials	0.564	
Total Capital Cost		4.965

OPERATING COSTS

-----Cost (MM \$/yr)-----

Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.08		
Maintenance Labor Cost	0.089	
Overhead Labor Cost	0.083	
Total Labor Cost	0.361	
Maintenance Supplies Cost	0.133	
Total Operating and Maintenance Cost	0.494	
Fixed Operating and Maintenance Cost		0.321
Variable Operating and Maintenance Cost	0.173	
Variable Operating Cost:	\$/hour	
Ammonia @ \$0.25/lb	54.45	
Sorbent @ \$70 /ton	7.97	
Catalyst @ (2 yr life)	95.54	
Raw Water @ \$0.60/1000 gal	0.28	
Steam @ \$5.64/1000 lb	141.77	
Electricity @ \$0.05/KWh	10.71	
Disposal @ \$9.50/ton	22.63	
Bag @ (1 yr life)	11.56	
Total	344.91	1.964
Total Variable Operating Costs (@ 65% utilization)		2.137
Cost of Capital (15% per year)		0.745
Total Annual Operating Cost		3.203

Coal-Fueled Diesel Engine Emission Control Economics

Cost Summary for OPTION N

System: 4 Engines (2 20 Cylinder)
24 MWe power output

CAPITAL

Equipment:	Cost (MM \$)
Spray Dryer	1.416
Cyclone	0.119
Baghouse (275 F)	0.363
Induced Draft Fan	0.043
Differential Boiler Cost	0.110
Total Equipment	2.051
Installation Costs:	1.206
Total Installed Equipment Cost	3.257
Engineering and Home Office Fees, General Facilities, 20% Contingency	1.173
Total Plant Cost	4.430
Preproduction Costs and Inventory Capital	0.289
Initial Supplies and Materials	0.010
Total Capital Cost	4.729

OPERATING COSTS

-----Cost (MM \$/yr)-----		
Operators/Shift: 1		
Operating Labor (@ \$21.55/hour)	0.189	
Maintenance Factor: 0.05		
Maintenance Labor Cost	0.065	
Overhead Labor Cost	0.076	
Total Labor Cost	0.330	
Maintenance Supplies Cost	0.098	
Total Operating and Maintenance Cost	0.428	
Fixed Operating and Maintenance Cost		0.278
Variable Operating and Maintenance Cost	0.150	
Variable Operating Cost:		
Sorbent @ \$70 /ton	29.58	
Raw Water @ \$0.60/1000 gal	0.29	
Steam @ \$5.64/1000 lb	78.80	
Electricity @ \$0.05/KWh	10.19	
Disposal @ \$20/ton	7.35	
Bag @ (1 yr life)	11.56	
Total	137.77	0.784
Total Variable Operating Costs (@ 65% utilization)		0.934
Cost of Capital (15% per year)		0.709
Total Annual Operating Cost		1.922

APPENDIX I
COMPUTER MODEL OF COAL-FUELED DIESEL SYSTEMS

DESCRIPTION

PG 1	COVER
PP 2-3	MACROS USED TO MANIPULATE MODEL
PG 4-6	DIRECTORY OF RANGE NAMES USED IN MODEL
PP 7	KEY VALUES
PG 8	TREND INDICES
PG 9	COAL PROPERTIES BY SOURCE
PG 10	CHARACTERISTICS OF SELECTED FUELS BY REGION
PG 10	TRANSPORTATION COST INPUTS BY REGION
PG 11	SELECTED COAL CHARACTERISTICS
PG 11	FIXED AND VARIABLE TRANSPORTATION COST COMPONENTS
PG 11	COST OF TRANSPORTING COAL TO SLURRY PLANT
PG 12	COAL SLURRY PLANT CAPITAL COST
PG 13	COST OF COAL DELIVERED TO SLURRY PLANT
PG 14	SLURRY CHARACTERISTICS & PROCESS COSTS
PG 14	SLURRY COST SUMMARY
PG 14	COST OF TRANSPORTING SLURRY TO UTILITY PLANT
PG 15	COAL-FIRED DIESEL ENGINE CAPITAL COST (PER 6 MW ENGINE)
PG 15	FOOTNOTE TO PAGE ABOVE
PG 16	COAL-FIRED DIESEL ENGINE MAINTENANCE COSTS
PG 17	COAL-FIRED DIESEL ENGINE EFFICIENCY/CONVERSION VALUES
PG 17	COST PER kWh ATTRIBUTABLE TO FUEL FOR COAL-FIRED ENGINE
PG 18	PERFORMANCE STATISTICS
PG 19	COAL-FIRED DIESEL ENGINE EMISSIONS CONTROL COSTS
PG 19	COAL-FIRED DIESEL ENGINE CAPITAL & OPERATING COSTS
PG 20	COAL-FIRED DIESEL ENGINE FUEL TRANSPORT STATISTICS
PG 21	COST COMPARISON
PG 22	COAL PREMIUM (DISC'T) OVER GAS/OIL
PG 23	COSTS BASED ON ASSUMED FUEL OIL PRICES
PG 24	OIL-FIRED DIESEL ENGINE PLANT CAPITAL COST (PER 6 MW ENGINE)
PG 25	OIL-FIRED DIESEL ENGINE MAINTENANCE COSTS
PG 26	OIL-FIRED DIESEL ENGINE EFFICIENCY/CONVERSION VALUES
PG 26	COST PER kWh FOR FUEL USED BY OIL-FIRED ENGINE
PG 27	GAS/OIL-FIRED DIESEL ENGINE CAPITAL & OPERATING COSTS

WORKSHEET: MAIN
FILE NAME: TR10
DISK NAME: TOB-8701
DEVELOPER: TODD BURGER AND BOB RANCATORE
SUBCASE #: 61366-03
TODAY IS: 23-May-89 04:39:06 PM

*****VERSION ID*****

DATE: 29-Mar-86
TIME: 06:00:00 PM
DESCRIPTN: Transfer to 1-2-3 Plus addns

*****VERSION! AGE*****

DAYS: 26
MONTHS: 1
YEARS: 3

LOCATION OF MACROS: A24
RANGE NAME DIRECTORY: A200

KEY VALUES

DESCRIPTION OF KEY VALUES	NATURE OF VALUE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
COAL TYPE (EAST 1-9, WEST 10-12)	INPUT	6	6	6	6
COAL TYPE BASED ON TYPE #		BLUE GEM	BLUE GEM	BLUE GEM	BLUE GEM
SLURRY PLANT TYPE	INPUT	AMAX	AMAX	AMAX	AMAX
LOAD FACTOR	INPUT	80.00%	80.00%	80.00%	80.00%
POWER PLANT SITE	INPUT	ATLANTA	ATLANTA	ATLANTA	ATLANTA
EMISSIONS CONTROL CONFIGURATION	INPUT	A	A	A	B
PLANT CONFIGURATION	INPUT	12MWP	12MWC	24MWC	12MWC
ASH LEVEL (1-0.5%, 2-1% AND UP)	INPUT	2	2	2	2
COAL DIESEL EFFICIENCY	INPUT	39.00%	39.00%	39.00%	39.00%
FINANCING INTEREST RATE	INPUT	10.00%	10.00%	10.00%	10.00%
FINANCING TERMS (YEARS)	INPUT	12	12	12	12
FUEL OIL OR GAS COST \$/MMBTU	INPUT	\$5.50	\$5.50	\$5.50	\$5.50
DISTANCE - MINE TO SLURRY PLANT (MILES)	INPUT	590	590	590	590

COAL PROPERTIES BY SOURCE

CODE	STATE	TYPE/FIELD	MOISTURE	VOLATILE MATTER	CARBON (FIXED)	ASH	TOTAL SULFUR	ORGANIC SULFUR	PYRITIC SULPHUR	BTU/LB	COST/TON DRY COAL
1	ALABAMA	S. APPALACHIA	2.80%	28.00%	58.00%	10.00%	0.75%	0.34%	0.41%	12,500	\$36.50
2	ILLINOIS	QUALITY CIR.	8.00%	35.00%	47.00%	8.50%	2.50%	1.13%	1.38%	11,700	\$29.50
3	ILLINOIS	ILLINOIS #5	10.00%	36.00%	42.00%	12.00%	4.50%	0.70%	0.38%	11,900	\$20.00
4	ILLINOIS	ILLINOIS #6	14.00%	38.00%	37.00%	13.00%	3.50%	1.58%	1.93%	10,500	\$20.50
5	KENTUCKY	SPLINT	4.00%	31.00%	47.00%	18.00%	2.00%	0.80%	1.20%	14,100	\$27.50
6	KENTUCKY	BLUE GEM	6.00%	38.00%	54.00%	2.00%	0.70%	0.30%	0.40%	14,000	\$34.50
7	PENNSYLVANIA	ELMHORN	2.00%	37.00%	58.00%	3.00%	3.00%	1.20%	1.80%	14,100	\$27.50
8	KENTUCKY	HAZARD #4	1.00%	35.00%	59.00%	6.00%	0.85%	0.74%	0.10%	14,200	\$27.50
9	W. VIRGINIA	PITTSBURGH	6.00%	37.00%	53.00%	8.00%	1.00%	0.45%	0.55%	13,000	\$27.00
10	COLORADO	GREEN RIVER	8.00%	37.00%	46.00%	9.00%	0.50%	0.22%	0.28%	11,600	\$22.25
11	UTAH	CASTLEGATE	7.00%	0.00%	0.00%	5.00%	0.50%	0.20%	0.30%	13,500	\$23.00
12	UTAH	KAIPAROWITZ	10.00%	38.00%	41.00%	9.00%	0.60%	0.27%	0.33%	11,500	\$26.00

NOTE: Moisture, volatile matter, "C" and organic sulfur values are based on ADL profile data.

Ash, total sulfur, BTU/lb and price are based on "COAL WEEK" May 9, 1988.

Coal price is average of term price quotes, FOB mine.

SELECTED COAL CHARACTERISTICS

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
COAL REGION (EAST/WEST)?	REGION	EAST	EAST	EAST	EAST
COAL TYPE IN REGION	LOCATION	BLUE GEM	BLUE GEM	BLUE GEM	BLUE GEM
COAL SOURCE CHARACTERISTICS					
VOLUME	LBS/CU.FT.	59	59	59	59
ENERGY/WEIGHT	BTU/LB	14,000	14,000	14,000	14,000
ENERGY/VOLUME	BTU/CU.FT.	823,529	823,529	823,529	823,529
MOISTURE CONTENT	% BY WT	6.00%	6.00%	6.00%	6.00%
ASH CONTENT	% BY WT	2.00%	2.00%	2.00%	2.00%
ORGANIC SULFUR CONTENT	% BY WT	0.30%	0.30%	0.30%	0.30%
NITROGEN CONTENT	% BY WT				
COST AT MINEMOUTH	SHORT TON	\$34.50	\$34.50	\$34.50	\$34.50
COST AT MINEMOUTH	\$\$\$/MM BTU	\$1.23	\$1.23	\$1.23	\$1.23

FIXED AND VARIABLE TRANSPORTATION COST COMPONENTS

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
U.S. RAILROAD RATES					
FIXED HAUL COMPONENT	\$\$\$	\$3.2192	\$3.2192	\$3.2192	\$3.2192
VARIABLE HAUL COMPONENT	\$\$\$/1000 MI	\$21.8200	\$21.8200	\$21.8200	\$21.8200
U.S. TRUCK RATES					
FIXED HAUL COMPONENT	\$\$\$	\$0.9276	\$0.9276	\$0.9276	\$0.9276
VARIABLE HAUL COMPONENT	\$\$\$/1000 MI	\$82.6534	\$82.6534	\$82.6534	\$82.6534
RAIL PREFERRED OVER TRUCK					
AT WHAT DISTANCE:	MILES	38	38	38	38

COST OF TRANSPORTING COAL TO SLURRY PLANT

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
COAL REGION TO SLURRY PLANT	MILES	590	590	590	590
U.S. RAILROAD RATES					
DELIVERY PRICE	\$\$\$/TON	\$16.0930	\$16.0930	\$16.0930	\$16.0930
COST/DISTANCE	\$\$\$/TON MI	\$0.0273	\$0.0273	\$0.0273	\$0.0273
COST/ENERGY	\$\$\$/MM BTU	\$0.5748	\$0.5748	\$0.5748	\$0.5748
U.S. TRUCK RATES					
DELIVERY PRICE	\$\$\$/TON	\$49.6931	\$49.6931	\$49.6931	\$49.6931
COST/DISTANCE	\$\$\$/TON MI	\$0.0842	\$0.0842	\$0.0842	\$0.0842
COST/ENERGY	\$\$\$/MM BTU	\$1.7748	\$1.7748	\$1.7748	\$1.7748
MINIMUM COST TRANSPORTATION					
IS VIA TRUCK/RAIL	MODE	RAIL	RAIL	RAIL	RAIL
MINIMUM TRANSPORTATION RATE					
DELIVERY PRICE	\$\$\$/TON	\$16.0930	\$16.0930	\$16.0930	\$16.0930
COST/DISTANCE	\$\$\$/TON MI	\$0.0273	\$0.0273	\$0.0273	\$0.0273
COST/ENERGY	\$\$\$/MM BTU	\$0.5748	\$0.5748	\$0.5748	\$0.5748

COAL SLURRY PLANT CAPITAL COST

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
FINANCIAL TERMS					
COST OF CAPITAL	%	10.00%	10.00%	10.00%	10.00%
RECOVERY TERM	YEARS	12	12	12	12
CAPITAL COST COMPONENTS					
GRINDING, LEACHING, PROCESSING, AGGLOMERATION/FILTRATION, AND OTHER PHYSICAL PLANT. \$\$\$MM		\$78.00	\$78.00	\$78.00	\$78.00
ANNUAL CAPITAL CHARGE	\$\$\$MM/YR	\$11.448	\$11.448	\$11.448	\$11.448
CAPITAL CHARGE/INPUT	\$\$\$ /TON	\$6.360	\$6.360	\$6.360	\$6.360
CAPITAL CHARGE/OUTPUT	\$\$\$ /MM BTU	\$0.2271	\$0.2271	\$0.2271	\$0.2271

COST OF COAL DELIVERED TO SLURRY PLANT

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
COST INPUTS					
COAL COST/ENERGY					
AT MINEMOUTH	\$\$\$ /MM BTU	\$1.23	\$1.23	\$1.23	\$1.23
TRANSPORTATION	\$\$\$ /MM BTU	\$0.57	\$0.57	\$0.57	\$0.57
TOTAL AT SLURRY PLANT	\$\$\$ /MM BTU	\$1.81	\$1.81	\$1.81	\$1.81
COAL COST/WEIGHT					
AT MINEMOUTH	SHORT TONS	\$34.50	\$34.50	\$34.50	\$34.50
TRANSPORTATION	SHORT TONS	\$16.09	\$16.09	\$16.09	\$16.09
TOTAL	SHORT TONS	\$50.59	\$50.59	\$50.59	\$50.59
QUANTITY INPUTS					
ANNUAL COAL INPUT QTY	TONS/YEAR	1,800,000	1,800,000	1,800,000	1,800,000
TONS OF SLURRY OUTPUT	SHORT TONS	1,714,286	1,714,286	1,714,286	1,714,286

SLURRY CHARACTERISTICS & PROCESS COSTS

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
OPERATING COSTS					
POWER, REAGENTS, ADDITIVES, DISPOSAL, AND OTHER. (EXCL COAL)	\$\$\$/MM BTU	0.57	0.57	0.57	0.57

SLURRY COST SUMMARY

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
DELIVERED COAL PRICE	\$\$\$/MM BTU	\$1.81	\$1.81	\$1.81	\$1.81
TOTAL OPNS COST (EXCL COAL)	\$\$\$/MM BTU	\$0.57	\$0.57	\$0.57	\$0.57
CAPITAL RECOVERY/DEBT SVCE	\$\$\$/MM BTU	\$0.23	\$0.23	\$0.23	\$0.23
TOTAL SLURRY COST	\$\$\$/MM BTU	\$2.60	\$2.60	\$2.60	\$2.60

COST OF TRANSPORTING SLURRY TO UTILITY PLANT

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
SLURRY TO UTILITY PLANT	MILES	20	20	20	20
U.S. RAILROAD RATES					
DELIVERED PRICE	\$\$\$/TON	\$3.8166	\$3.8166	\$3.8166	\$3.8166
COST/DISTANCE	\$\$\$/TON MI	\$0.1908	\$0.1908	\$0.1908	\$0.1908
COST/ENERGY	\$\$\$/MM BTU	\$0.2870	\$0.2870	\$0.2870	\$0.2870
U.S. TRUCK RATES					
DELIVERED PRICE	\$\$\$/TON	\$2.6270	\$2.6270	\$2.6270	\$2.6270
COST/DISTANCE	\$\$\$/TON MI	\$0.1314	\$0.1314	\$0.1314	\$0.1314
COST/ENERGY	\$\$\$/MM BTU	\$0.1975	\$0.1975	\$0.1975	\$0.1975
MINIMUM COST TRANSPORTATION IS VIA TRUCK/RAIL	MODE	TRUCK	TRUCK	TRUCK	TRUCK
MINIMUM TRANSPORTATION RATE					
DELIVERED PRICE	\$\$\$/TON	\$3.8166	\$3.8166	\$3.8166	\$3.8166
COST/DISTANCE	\$\$\$/TON MI	\$0.1908	\$0.1908	\$0.1908	\$0.1908
COST/ENERGY	\$\$\$/MM BTU	\$0.2870	\$0.2870	\$0.2870	\$0.2870

COAL-FIRED DIESEL ENGINE CAPITAL COST (PER 6 MW ENGINE)

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
FINANCIAL STATISTICS					
COST OF CAPITAL	%	10.00%	10.00%	10.00%	10.00%
RECOVERY TERM	YEARS	12	12	12	12
OPERATING STATISTICS					
POWER RATING	MEGAWATTS	6	6	6	6
ANALYSIS PERIOD	YEARS	20	20	20	20
AVAILABILITY	%	90.00%	90.00%	90.00%	90.00%
LOAD FACTOR	%	80.00%	80.00%	80.00%	80.00%
OPERATING PERIOD	HRS PER YEAR	6307	6307	6307	6307
POWER GENERATED	MWH	760,000	760,000	760,000	760,000
CAPITAL COST COMPONENTS					
LUBE SYSTEM	\$\$\$	\$65,000	\$65,000	\$65,000	\$65,000
PISTONS & PISTON RINGS	\$\$\$	\$70,000	\$70,000	\$70,000	\$70,000
CYLINDER LINERS	\$\$\$	\$200,000	\$200,000	\$200,000	\$200,000
CYLINDER HEAD	\$\$\$	\$300,000	\$300,000	\$300,000	\$300,000
VALVES	\$\$\$	\$40,000	\$40,000	\$40,000	\$40,000
FUEL PUMP & INJECTOR	\$\$\$	\$300,000	\$300,000	\$300,000	\$300,000
INSTRUMENTS	\$\$\$	\$200,000	\$200,000	\$200,000	\$200,000
TURBOCHARGER	\$\$\$	\$600,000	\$600,000	\$600,000	\$600,000
CAM SHAFT & BEARINGS	\$\$\$	\$100,000	\$100,000	\$100,000	\$100,000
MISCELLANY	\$\$\$	\$250,000	\$250,000	\$250,000	\$250,000
SUBTOTAL CRITICAL PARTS	\$\$\$	\$2,125,000	\$2,125,000	\$2,125,000	\$2,125,000
NON-CRITICAL PARTS	\$\$\$	\$1,350,000	\$1,350,000	\$1,350,000	\$1,350,000
PRODUCTION ENGINE COST	\$\$\$	\$3,475,000	\$3,475,000	\$3,475,000	\$3,475,000
INSTALLATION COSTS	\$\$\$	\$1,737,500	\$1,737,500	\$1,737,500	\$1,737,500
INSTALLED ENGINE COST	\$\$\$	\$5,212,500	\$5,212,500	\$5,212,500	\$5,212,500
EMISSIONS EQUIPMENT	\$\$\$	\$2,526,500	\$2,464,500	\$2,013,000	\$590,000
TOTAL CAPITAL OUTLAY	\$\$\$	\$7,739,000	\$7,677,000	\$7,225,500	\$5,802,500
ANNUAL CAPITAL CHARGE	\$\$\$ / YEAR	\$1,135,801	\$1,126,702	\$1,060,438	\$851,594
CAPITAL CHARGE/OUTPUT					
PRINCIPAL COMPONENT	\$\$\$ / kWh	\$0.0102	\$0.0101	\$0.0095	\$0.0076
COST OF CAPITAL	\$\$\$ / kWh	\$0.0078	\$0.0077	\$0.0072	\$0.0058
TOTAL CHARGE/OUTPUT	\$\$\$ / kWh	\$0.0179	\$0.0178	\$0.0167	\$0.0134
PRINCIPAL & COST OF CAPITAL/OUTPUT					
ENGINE	\$\$\$ / kWh	\$0.0121	\$0.0121	\$0.0121	\$0.0121
EMISSIONS	\$\$\$ / kWh	\$0.0059	\$0.0057	\$0.0047	\$0.0014
NOTE AMOUNT (OVER) UNDER					
STANDARD ENGINE COST:					
PRODUCTION OF \$2.35M		(\$1,125,000)	(\$1,125,000)	(\$1,125,000)	(\$1,125,000)
INSTALLATION OF \$1.15M		(\$587,500)	(\$587,500)	(\$587,500)	(\$587,500)
EMISSIONS PREMIUM (\$.9M)		(\$1,626,500)	(\$1,564,500)	(\$1,113,000)	\$310,000
TOTAL PREMIUM		(\$3,339,000)	(\$3,277,000)	(\$2,825,500)	(\$1,402,500)

COAL-FIRED DIESEL ENGINE MAINTENANCE COSTS

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
MAINTENANCE INTERVALS					
INJECTORS	HOURS/CYCLE	500	500	500	500
MINOR	HOURS/CYCLE	4,000	4,000	4,000	4,000
TOP END	HOURS/CYCLE	12,000	12,000	12,000	12,000
BOTTOM END	HOURS/CYCLE	25,000	25,000	25,000	25,000
COST PER SERVICING					
INJECTORS	\$\$\$	\$3,200	\$3,200	\$3,200	\$3,200
MINOR	\$\$\$	\$10,000	\$10,000	\$10,000	\$10,000
TOP END	\$\$\$	\$60,000	\$60,000	\$60,000	\$60,000
BOTTOM END	\$\$\$	\$290,000	\$290,000	\$290,000	\$290,000
SERVICING THRU 1st REBUILD					
INJECTORS	# OF CYCLES	50	50	50	50
MINOR (excl. injectors)	# OF CYCLES	6	6	6	6
TOP END	# OF CYCLES	2	2	2	2
BOTTOM END	# OF CYCLES	1	1	1	1
COST THRU 1st REBUILD					
INJECTORS	\$\$\$	\$160,000	\$160,000	\$160,000	\$160,000
MINOR	\$\$\$	\$60,000	\$60,000	\$60,000	\$60,000
TOP END	\$\$\$	\$120,000	\$120,000	\$120,000	\$120,000
BOTTOM END	\$\$\$	\$290,000	\$290,000	\$290,000	\$290,000
TOTAL THRU #1 BOTTOM END	\$\$\$	\$630,000	\$630,000	\$630,000	\$630,000
ALLOCATED MAINTENANCE %					
INJECTORS	%	25.40%	25.40%	25.40%	25.40%
MINOR	%	9.52%	9.52%	9.52%	9.52%
TOP END	%	19.05%	19.05%	19.05%	19.05%
BOT M END	%	46.03%	46.03%	46.03%	46.03%
LIFE SERVICE CYCLES					
INJECTORS	# OF CYCLES	315	315	315	315
MINOR	# OF CYCLES	39	39	39	39
TOP END	# OF CYCLES	13	13	13	13
BOTTOM END	# OF CYCLES	6	6	6	6
20 YEAR COST (SIX MAJOR REBUILDS)					
INJECTORS	\$\$\$ / LIFE	\$1,008,000	\$1,008,000	\$1,008,000	\$1,008,000
MINOR	\$\$\$ / LIFE	\$390,000	\$390,000	\$390,000	\$390,000
TOP END	\$\$\$ / LIFE	\$780,000	\$780,000	\$780,000	\$780,000
BOTTOM END	\$\$\$ / LIFE	\$1,740,000	\$1,740,000	\$1,740,000	\$1,740,000
TOTAL MAINTENANCE COST	\$\$\$ / LIFE	\$3,918,000	\$3,918,000	\$3,918,000	\$3,918,000
TOTAL MAINTENANCE COST					
TOTAL MAINTENANCE COST	\$\$\$ / kWh	\$0.0052	\$0.0052	\$0.0052	\$0.0052

COAL-FIRED DIESEL ENGINE EFFICIENCY/CONVERSION VALUES

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
EFFICIENCY ADJUSTMENT					
DIESEL FUEL ENGINE					
STANDARD EFFICIENCY	%	39.00%	39.00%	39.00%	39.00%
SLURRY/POWDER DELIVERY AND INJECTION	%				
RADIATION LOSSES	%				
PUMPING LOSSES FOR AIR DELIVERY	%				
UNBURNED FUEL	%				
SLURRY WATER EVAP., NET	%				
FRICTION LOSSES	%				

EFFICIENCY PENALTY (NOT BY ADDITION)	%	0.00%	0.00%	0.00%	0.00%
ADJUSTED EFFICIENCY	%	39.00%	39.00%	39.00%	39.00%

HEAT RATE	BTU/kWh	8,749	8,749	8,749	8,749

COST PER kWh ATTRIBUTABLE TO FUEL FOR COAL-FIRED ENGINE

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3

SLURRY OPNS INCL COAL COST					
CAPITAL RECOVERY	\$\$\$ / kWh	\$0.0020	\$0.0020	\$0.0020	\$0.0020
OPNS COST (EXCL COAL)	\$\$\$ / kWh	\$0.0050	\$0.0050	\$0.0050	\$0.0050
DELIVERED COAL PRICE	\$\$\$ / kWh	\$0.0158	\$0.0158	\$0.0158	\$0.0158
TOTAL CAPITAL & OPNS	\$\$\$ / kWh	\$0.0228	\$0.0228	\$0.0228	\$0.0228

SLURRY TRANSPORTATION COST	\$\$\$ / kWh	\$0.0025	\$0.0025	\$0.0025	\$0.0025
TOTAL FUEL COMPONENT	\$\$\$ / kWh	\$0.0253	\$0.0253	\$0.0253	\$0.0253

COAL-FIRED DIESEL ENGINE FUEL TRANSPORT STATISTICS

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
SLURRY TRANSPORT					
POWER GENERATED/ENGINE	MWH/YEAR	38,000	38,000	38,000	38,000
NUMBER OF ENGINES	#	6	6	6	6
POWER GENERATED/CLUSTER	MWH/YEAR	228,000	228,000	228,000	228,000
HEAT RATE	BTU/kWh	8,749	8,749	8,749	8,749
ENERGY REQUIRED/YEAR	MMBTU	1,994,708	1,994,708	1,994,708	1,994,708
SLURRY ENERGY CONTENT	BTU/CUFT	245,066	245,066	245,066	245,066
SLURRY REQ'D FOR YEAR	CUFT	8,139,467	8,139,467	8,139,467	8,139,467
TANKCAR LOADS/YEAR (1)	#	2,035	2,035	2,035	2,035
TANKCAR LOADS/WEEK (1)	#	39	39	39	39
COAL TRANSPORT FROM MINEMOUTH					
ENERGY REQUIRED/YEAR	MMBTU	1,994,708	1,994,708	1,994,708	1,994,708
COAL ENERGY/VOLUME	BTU/CUFT	823,529	823,529	823,529	823,529
SLURRY/BYPRODUCT RATIO	%	50.00%	50.00%	50.00%	50.00%
COAL REQ'D FOR YEAR	CUFT	4,844,290	4,844,290	4,844,290	4,844,290
TRAIN CARLOADS/YEAR (2)	#	1,425	1,425	1,275	1,275
TRAIN CARLOADS/WEEK (2)	#	27	27	25	25

NOTE (1): ASSUMES 30,000 GALLON TANKCARS

COAL-FIRED DIESEL ENGINE EMISSIONS CONTROL COSTS

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
SYSTEM TYPE		A	A	A	B
OPERATING COMPONENTS	\$\$\$/MM BTU	\$1.829	\$1.715	\$1.600	\$0.572
CAPITAL COMPONENTS	\$\$\$/MM BTU	\$0.669	\$0.653	\$0.533	\$0.156
TOTAL		\$2.498	\$2.367	\$2.133	\$0.728

COAL-FIRED DIESEL ENGINE CAPITAL & OPERATING COSTS

DESCRIPTION	UNIT OF MEASURE	BASE CASE	ALTERNATE CASE 1	ALTERNATE CASE 2	ALTERNATE CASE 3
OPERATING (EXCL EMISSIONS)					
FUEL	\$\$\$ / kWh	\$0.0253	\$0.0253	\$0.0253	\$0.0253
MAINTENANCE	\$\$\$ / kWh	\$0.0052	\$0.0052	\$0.0052	\$0.0052
TOTAL OPERATING	\$\$\$ / kWh	\$0.0304	\$0.0304	\$0.0304	\$0.0304
CAPITAL (EXCL EMISSIONS)	\$\$\$ / kWh	\$0.0121	\$0.0121	\$0.0121	\$0.0121
EMISSIONS					
OPERATING	\$\$\$ / kWh	\$1.8288	\$1.7145	\$1.6002	\$0.5715
CAPITAL	\$\$\$ / kWh	\$0.0059	\$0.0057	\$0.0047	\$0.0014
TOTAL EMISSIONS	\$\$\$ / kWh	\$1.8347	\$1.7202	\$1.6049	\$0.5729
TOTAL COST	\$\$\$ / kWh	\$1.8772	\$1.7628	\$1.6474	\$0.6154

COST COMPARISON

DESCRIPTION	UNIT OF MEASURE	FOSSIL FUEL		NATURAL GAS/OIL	
		COAL DIESEL		OIL-FIRF, DIESEL	
		BASE CASE		BASE CASE	
FUEL					
MINEMOUTH/REFINERY COST	\$\$\$/kWh		\$0.0108		\$0.0481
COAL TRANSPORT COST	\$\$\$/kWh		\$0.0050		
SLURRY PLANT CAPITAL	\$\$\$/kWh		\$0.0020		
SLURRY PLANT OPERATIONS	\$\$\$/kWh		\$0.0050		
SLURRY/DIESEL TRANSP.	\$\$\$/kWh		\$0.0025		
TOTAL FUEL COST	\$\$\$/kWh		\$0.0253		\$0.0481
UTILITY OPERATING COST					
TOTAL FUEL COST	\$\$\$/kWh		\$0.0253		\$0.0481
UTILITY PLANT MAINT.	\$\$\$/kWh		\$0.0052		\$0.0019
UTILITY PLANT EMISSIONS	\$\$\$/kWh		\$0.0160		
TOTAL OPERATING COST	\$\$\$/kWh		\$0.0464		\$0.0500
UTILITY PLANT CAPITAL	\$\$\$/kWh		\$0.0121		\$0.0081
EMISSIONS CAPITAL	\$\$\$/KWH		\$0.0059		\$0.0032
TOTAL UTILITY COST	\$\$\$/kWh		\$0.0644		\$0.0613

COAL PREMIUM (DISC'T) OVER GAS/OIL	

COAL DIESEL	

DESCRIPTION	BASE CASE
-----	-----
FUEL	
MINEMOUTH/REFINERY COST	(\$0.0373)
COAL TRANSPORT COST	\$0.0050
SLURRY PLANT CAPITAL	\$0.0020
SLURRY PLANT OPERATIONS	\$0.0050
SLURRY/DIESEL TRANSP.	\$0.0025

TOTAL FUEL COST	(\$0.0228)
UTILITY OPERATING COST	
TOTAL FUEL COST	(\$0.0228)
UTILITY PLANT MAINT.	\$0.0033
UTILITY PLANT EMISSIONS	\$0.0160

TOTAL OPERATING COST	(\$0.0035)
UTILITY PLANT CAPITAL	\$0.0040
EMISSIONS CAPITAL	-----
	\$0.0031
TOTAL UTILITY COST	-----

OIL-FIRED DIESEL ENGINE PLANT CAPITAL COST (PER 6 MW ENGINE)

DESCRIPTION	UNIT OF MEASURE	BASE CASE
FINANCIAL STATISTICS		
COST OF CAPITAL	%	10.00%
RECOVERY TERM	YEARS	12
OPERATING STATISTICS		
POWER RATING	MEGAWATTS	6
LIFE	YEARS	20
AVAILABILITY	%	90.00%
LOAD FACTOR	%	80.00%
POWER GENERATED	MW HOURS	750,000
CAPITAL COST COMPONENTS		
STANDARD ENGINE COST	\$\$\$	\$2,350,000
%COST OF CRITICAL PARTS	%	44.00%
VALUE OF CRITICAL PARTS	\$\$\$	\$1,034,000
ADJ FOR CRITICAL PARTS	%	100.00%
ADJ COST-CRITICAL PARTS	\$\$\$	\$1,034,000
PRODUCTION ENGINE COST	\$\$\$	\$2,350,000
INSTALLATION COSTS	\$\$\$	\$1,150,000
TOTAL CAPITAL OUTLAY	\$\$\$	\$3,500,000
ANNUAL CAPITAL CHARGE	\$\$\$ / YEAR	\$513,672
CAPITAL CHARGE/OUTPUT		
PRINCIPAL COMPONENT	\$\$\$ / MM kWh	\$0.0046
COST OF CAPITAL	\$\$\$ / MM kWh	\$0.0035
TOTAL CHARGE/OUTPUT	\$\$\$ / MM kWh	\$0.0081

OIL-FIRED DIESEL ENGINE MAINTENANCE COSTS

DESCRIPTION	UNIT OF MEASURE	BASE CASE
MAINTENANCE INTERVALS		
MINOR	HOURS/CYCLE	8,000
TOP END	HOURS/CYCLE	25,000
BOTTOM END	HOURS/CYCLE	100,000
COST PER SERVICING		
MINOR	\$\$\$	\$10,000
TOP END	\$\$\$	\$90,000
BOTTOM END	\$\$\$	\$290,000
SERVICE CYCLES THRU 1st REBUILD		
MINOR	# OF CYCLES	13
TOP END	# OF CYCLES	4
BOTTOM END	# OF CYCLES	1
COST THRU 1st BOTTOM END REBUILD		
MINOR	\$\$\$	\$130,000
TOP END	\$\$\$	\$360,000
BOTTOM END	\$\$\$	\$290,000
TOTAL	\$\$\$	\$780,000
ALLOCATED MAINTENANCE %		
MINOR	%	16.67%
TOP END	%	46.15%
BOTTOM END	%	37.18%
LIFE SERVICE CYCLES		
MINOR	# OF CYCLES	20
TOP END	# OF CYCLES	7
BOTTOM END	# OF CYCLES	2
20 YEAR COST (TWO MAJOR REBUILDS)		
MINOR	\$\$\$ / LIFE	\$200,000
TOP END	\$\$\$ / LIFE	\$630,000
BOTTOM END	\$\$\$ / LIFE	\$580,000
TOTAL MAINTENANCE COST	\$\$\$ / LIFE	\$1,410,000
TOTAL MAINTENANCE COST	\$\$\$ / kWh	\$0.0019

GAS/OIL-FIRED DIESEL ENGINE CAPITAL & OPERATING COST

DESCRIPTION	UNIT OF MEASURE	BASE CASE
ENGINE PLANT CAPITAL	\$\$\$ / kWh	\$0.0081
EMISSIONS CAPITAL	\$\$\$ / kWh	\$0.0032
ENGINE PLANT MAINTENANCE	\$\$\$ / kWh	\$0.0019
FUEL	\$\$\$ / kWh	\$0.0481
TOTAL COST	\$\$\$ / kWh	\$0.0613

EMISSIONS CONTROL SUBSYSTEM COSTS

DEWSRIPTION				PLANT CONFIGURATION				
				COGEN 1X6 CYL 1.8 MW	COGEN 4X6 CYL 7.2 MW	COGEN 2X20 CYL 12 MW	POWER 2X20 CYL 12 MW	COGEN 4X20 CYL 24 MW
TYPE	NOX	SOX						
A1	SCR	SPRAY DRYER	CAPITAL \$MM	1.742	3.649	4.929	5.053	8.052
A2			OPER. \$/KWH	0.03	0.019	0.015	0.016	0.014
B1	REBURNING	350 DEGREE	CAPITAL \$MM	0.411	0.987	1.18	1.335	2.176
B2		SORBENT	OPER. \$/KWH	0.015	0.007	0.005	0.015	0.004
K1	SCR	350 DEGREE	CAPITAL \$MM	0.808	1.957	2.866	2.947	5.114
K2		SORBENT	OPER. \$/KWH	0.025	0.018	0.015	0.015	0.014
L1	REBURNING	SPRAY DRYER	CAPITAL \$MM	1.36	2.662	3.299	3.453	5.133
L2			OPER. \$/KWH	0.019	0.01	0.007	0.016	0.004

END

**DATE
FILMED**

2 / 19 / 92