MASTER

RECEIVED BY TIC JUN 22 1979

**EVALUATION OF THE FEASIBILITY,
ECONOMIC IMPACT,
AND EFFECTIVENESS
OF UNDERGROUND
NUCLEAR POWER PLANTS**

FINAL TECHNICAL REPORT

MAY 1978

prepared for
California Energy Commission

prepared by
THE AEROSPACE CORPORATION
Energy and Transportation Division

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

Aerospace Report No.
ATR-78(7652-14)-1

EVALUATION OF THE FEASIBILITY, ECONOMIC IMPACT,
AND EFFECTIVENESS OF UNDERGROUND NUCLEAR POWER PLANTS

Final Technical Report

May 1978

Prepared for
California Energy Commission

Prepared by
THE AEROSPACE CORPORATION
Energy and Transportation Division
2350 E. El Segundo Boulevard
El Segundo, California 90245

LEGAL NOTICE

This report was prepared as an account of work sponsored by the State of California Energy Resources Conservation and Development Commission, but does not necessarily represent the views of said Commission or any of its employees except to the extent if any that it has formally been approved by said Commission at a public meeting. For information regarding any such action, communicate directly with the said Commission at 1111 Howe Ave., Sacramento, CA 95825. Neither said Commission nor the State of California, nor any officer, employee, thereof or any of its contractors or subcontractors makes any warranty, express or implied, or assumes any legal liability whatsoever for the contents of this document. Nor does any party represent that use of the data contained herein would not infringe privately owned rights.

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

ACKNOWLEDGMENTS

This document represents a summary and evaluation of the integrated efforts of several teams of experts in specialized fields. Without their wholehearted support, the project could not have been accomplished. Special recognition should be given to the two architect/engineer firms who conducted the design and economic analyses for the underground concepts: S&L Engineers, who developed the Berm-Contained facility design, under the leadership of John E. Ward and Russell C. Brown; and Underground Design Consultants/Gibbs and Hill, who developed the Mined-Cavern facility design, under the direction of Larry E. Wilkinson of UDC, and Louis Giannuzzi of G&H. The excellence of their efforts in designing and estimating the costs of the facilities has provided the foundation for the success of the project. The efforts of the accident consequence analysts of the team of Advanced Research and Applications Corporation/Intermountain Technologies, Inc. must also be acknowledged. Their work was performed under the direction of Bryce W. Johnson, and Hong Lee of ARACOR, and Peter R. Davis and Don C. Slaughterbeck of ITI. The limits of the state-of-the-art of accident consequence analysis had to be extended substantially on this project to account for the long-term underground system response to Class-9 accident conditions.

This document was prepared under the combined efforts of F. C. Finlayson, W. A. Kammer, and J. Benveniste of The Aerospace Corporation. Support was received in the conduct of the Aerospace program from a number of technical and managerial specialists including: T. L. Alley, R. L. Beck, R. L. Crolus, W. A. Kelley, O. J. Mead, and W. W. Willis. Consultant support on geological and structural aspects of the program was provided by C. Smith. The Aerospace program was performed under the direction of M. B. Watson and F. C. Finlayson.

The work on this program was conducted for the California Energy Commission under the project management of H. Daniel Nix of the Commission Staff. His tireless support, astute direction of the project, and detailed technical review of the Aerospace document are gratefully acknowledged.

CONTENTS

	<u>Page</u>
ACKNOWLEDGMENTS.....	i
1.0 INTRODUCTION.....	1-1
1.1 Motivations for Underground Siting.....	1-3
1.2 Program Objectives and Scope.....	1-9
1.3 Program Structure.....	1-16
REFERENCES.....	1-19
2.0 UNDERGROUND NUCLEAR POWER PLANT CONCEPTS.....	2-1
2.1 Basis for Development of Concepts.....	2-1
2.2 Surface Plant Designs.....	2-6
2.2.1 Facility Design Specifications.....	2-7
2.2.2 UDC/G&H Surface Plant Features.....	2-8
2.2.3 S&L Surface Plant Features.....	2-10
2.2.4 Relationships Between Underground and Surface Plant Layouts.....	2-13
2.3 Baseline Berm-Contained Facilities.....	2-14
2.3.1 Berm-Contained Facility Features.....	2-16
2.3.2 Accident Mitigation Systems in Berm-Contained Facilities.....	2-19
2.3.3 Overview of Feasibility and Constructability.....	2-22
2.4 Baseline Mined-Cavern Facilities.....	2-22
2.4.1 Mined-Cavern Facility Features.....	2-23
2.4.2 Accident Mitigation Systems for Mined-Cavern Facilities.....	2-27
2.4.3 Overview of Feasibility and Constructability.....	2-29
REFERENCES.....	2-31
3.0 PUBLIC HEALTH IMPACTS.....	3-1
3.1 The Nature of Reactor Accident Risk.....	3-1
3.2 Accident Descriptions.....	3-9

3.3	Relative Health and Economic Consequences.....	3-14
3.3.1	Principal Factors Affecting Radiological Health Effects.....	3-16
3.3.2	Health Effect Results.....	3-19
3.3.3	Ground Water Contamination.....	3-27
3.3.4	Economic Impacts.....	3-29
3.4	Summary.....	3-32
REFERENCES.....		3-34
4.0	TECHNICAL FEASIBILITY OF UNDERGROUND CONCEPTS.....	4-1
4.1	Basis for Study Criteria	
4.1.1	Power Plant Characteristics.....	4-2
4.1.2	System/Component Locations.....	4-2
4.1.3	Site Material Property Specification.....	4-5
4.1.4	Containment and Accident Mitigation System Design Requirements.....	4-6
4.2	Functional Effectiveness of Accident Mitigation Systems..	4-26
4.2.1	Accident Results for Reference Surface Plants.....	4-27
4.2.2	Pressure and Temperature Response in the Berm- Contained Concept.....	4-27
4.2.3	Overall Results in Soil and Rock-Sited Facilities.....	4-35
4.2.4	Observations on Accident Mitigation System Effectiveness.....	4-38
4.3	Feasibility of Construction.....	4-39
4.3.1	Berm-Contained Structures.....	4-39
4.3.2	Mined-Cavern Structures.....	4-41
4.3.3	Observations on the Feasibility of Underground Construction Methods.....	4-53
4.4	Operating, Maintenance, and Operational Safety.....	4-54
4.5	Surface Plant Designs Incorporating Accident Mitigation System Concepts.....	4-57
REFERENCES.....		4-61

5.0	ECONOMIC IMPACTS OF UNDERGROUND CONSTRUCTION.....	5-1
5.1	Economic Assumptions and Guidelines.....	5-4
5.2	Comparative Reference Surface and Baseline	
	Underground Facilities Costs.....	5-9
5.2.1	Cost Analysis of Surface Plants.....	5-10
5.2.2	Cost Analysis of Underground Facilities.....	5-12
5.3	Impact of Construction Scheduling on Facility Costs.....	5-18
5.3.1	Construction Schedules.....	5-18
5.3.2	Cash Flow Requirements During Plant Construction..	5-22
5.4	Surface Plant Accident Mitigation System Cost	
	Sensitivity Studies.....	5-27
5.5	Parametric Cost Sensitivity Studies.....	5-28
5.5.1	Berm-Contained Facility Cost Sensitivity.....	5-31
5.5.2	Mined-Cavern Facility Cost Sensitivity.....	5-35
	REFERENCES.....	5-40
6.0	EVALUATION OF RELATED ISSUES.....	6-1
6.1	Seismic Impacts.....	6-1
6.1.1	Overview of Seismic Implications for California	
	Siting.....	6-2
6.1.2	Underground Seismic Environments.....	6-5
6.1.3	Berm-Contained Seismic Design.....	6-9
6.1.4	Mined-Cavern Seismic Design.....	6-14
6.1.5	Observations on Seismic Design.....	6-16
6.2	Siting in Proximity to Population Centers.....	6-17
6.2.1	Surface Plant Exclusion Criteria for Population	
	Centers.....	6-17
6.3	Facility Vulnerability to Natural and Man-Made Hazards...	6-25
6.3.1	Flooding, Falling Objects, and Other Natural	
	Hazards.....	6-25
6.3.2	Sabotage or Military Actions.....	6-31

6.4	Licensing/Regulatory Implications.....	6-32
6.4.1	Design Objectives with Respect to Plant Licensability.....	6-32
6.4.2	Comparison of Underground Plant Design with Current Licensing Requirements.....	6-33
6.4.3	Summary of Licensing Implications.....	6-39
6.5	General Availability of Siting Locations.....	6-40
6.5.1	Survey Approach and Data Analyzed.....	6-42
6.5.2	Representative Underground Siting Areas.....	6-51
6.6	Overall Evaluation of Underground Facility Issues.....	6-54
REFERENCES.....		6-57
APPENDIX I	FINAL SPECIFICATIONS AND DESIGN CRITERIA FOR BERM- CONTAINED AND MINED-CAVERN UNDERGROUND NUCLEAR POWER- PLANT DESIGN PROJECTS.....	AI-1

FIGURES

	<u>Page</u>
1-1. Study of Underground Siting of Nuclear Power Plants.....	1-17
2-1. Mined Cavern Concepts.....	2-2
2-2. Berm Contained Concepts.....	2-4
2-3. UDC/Gibbs & Hill Reference Surface Plant.....	2-9
2-4. S&L Engineers Reference Surface Plant.....	2-11
2-5. Berm-Contained Underground Plant.....	2-15
2-6. Cross-Sectional View of Berm-Contained Underground Structures.....	2-17
2-7. Schematic Diagram of Level-2 Accident Mitigation System for Berm-Contained Plant.....	2-20
2-8. Cutaway Sketch of Mined-Cavern Underground Plant Layout.....	2-24
2-9. Plan View of Mined-Cavern Underground Facility.....	2-25
2-10. Layout of Level-2 Accident Mitigation System for Mined- Cavern Facility.....	2-28
3-1. Frequency of Man-Caused Events Involving Fatalities (Annualized Basis for 100 Nuclear Power Plants).....	3-5
4-1. Possible LOCA Sequence with Massive LWR Core Melt.....	4-8
4-2. Containment Pressure-Time Histories (ECCS Inoperable).....	4-9
4-3. Principal Radionuclide Transport Mechanisms.....	4-11
4-4. Schematic Diagram of Components of PWR Cooling System.....	4-25
4-5. Containment Pressure Transient for the Degraded Loss-of- Electric Power Accident.....	4-28
4-6. Containment Temperature Transient for the Degraded Loss- of-Electric Power Accident.....	4-29
4-7. Containment Pressure Transient for the Degraded Loss-of- Electric Power Accident.....	4-30
4-8. Containment Temperature Transient for the Degraded Loss- of-Electric Power Accident.....	4-31
4-9. Late-Time Containment Temperature - Berm-Contained Concept....	4-33

4-10.	Schematic of Reactor Cavern Lining and Rock Bolt and Tendon Support Patterns.....	4-49
4-11.	Schematic of Details of Reactor Cavern Lining.....	4-50
4-12.	Surface Plant Modification for Level-3 Accident Mitigation Systems.....	4-58
5-1.	Plant Construction Schedule Summary.....	5-19
5-2.	Normalized Berm-Contained and Reference Surface Plant Cash Flow Curves.....	5-24
5-3.	Normalized Mined-Cavern and Reference Surface Plant Cash Flow Curves.....	5-25
6-1.	Earthquake Epicenter Locations.....	6-3
6-2.	Regions of Fault Zone and Volcanic Activity Relative to Population Screening Criterion.....	6-4
6-3.	Recommended Horizontal Seismic Response Spectra (Subsurface Depths Greater than 30 Meters, 0.5 g Peak Surface Acceleration).....	6-8
6-4.	S&L Reference Surface Plant Structural Dimensions.....	6-11
6-5.	Baseline Berm-Contained Plant Structural Dimensions.....	6-12
6-6.	Cumulative Population as a Function of Distance from Nuclear Plants.....	6-19
6-7.	Locations of Existing and Proposed Nuclear Power Plants.....	6-20
6-8.	Population-Related Geographic Screening Factors.....	6-21
6-9.	Areas with Potential for Floods and Dam-Failure Inundation.....	6-28
6-10.	Locations of Known Geothermal Resource Areas and Oil and Gas Fields.....	6-46
6-11.	Locations of Areas of Potential Ground Water.....	6-47
6-12.	Locations of Regions of Unconsolidated Soil Deposits.....	6-49
6-13.	Locations of Regions of Granitic Rocks.....	6-50
6-14.	Composite Identification of Areas of Technically Acceptable Unconsolidated Soil Deposits.....	6-52
6-15.	Composite Identification of Areas of Technically Acceptable Granitic Rocks.....	6-53

TABLES

	<u>Page</u>
1-1. Calculated Radioactivity of 1100 MWe PWR at Shutdown and as a Function of Decay Time.....	1-7
1-2. Reactor Facility Classification of Postulated Accidents and Occurrences.....	1-13
3-1. U.S. Accident Death Statistics 1969.....	3-2
3-2. Fission Product Release Characteristics.....	3-12
3-2. Radioactive Dose Conversions Factors for Health Effect.....	3-17
3-4. Short and Long-Term Fatalities (Weighted and Severe Results).....	3-20
3-5. Health Consequences (Weighted and Maximum Results).....	3-22
3-6. Economic Consequences (Weighted and Severe Results).....	3-30
4-1. Progression of Accident Initiated by Loss of Coolant in Underground Plants.....	4-14
4-2. Progression of Accident Initiated by Loss of Electric Power in Underground Plants:.....	4-24
4-3. Summary of Accident Calculations.....	4-36
4-4. Nominal Excavated Dimensions of Major Caverns for Baseline PWR & Alternative BWR Facilities.....	4-42
5-1. Basic Cost Estimate Assumptions.....	5-7
5-2. Nuclear Power Plant Cost Comparisons.....	5-11
5-3. Berm-Contained Concept Cost Sensitivity Analyses.....	5-29
5-4. Mined-Cavern Concept Cost Sensitivity Analyses.....	5-30
6-1. Proposed Depth Reduction Factors for Seismic Motions.....	6-6

EVALUATION OF THE FEASIBILITY, ECONOMIC IMPACT,
AND EFFECTIVENESS OF UNDERGROUND NUCLEAR POWER PLANTS

1.0 INTRODUCTION

In June 1976, California enacted three laws which will severely constrain the licensing of nuclear power plants within the State until the California Energy Commission (CEC) makes findings on three key issues related to nuclear power. Two of the statutes dealt with fuel reprocessing and waste disposal. The third required the CEC to conduct "... a study of the necessity for, and effectiveness and economic feasibility of, undergrounding and berm-containment of nuclear reactors ...". The work performed to establish an adequate technical basis for the evaluation required by the third law has been integrated and summarized in this document.

Results are presented of two studies (Refs 1-1, 1-2) conducted by highly qualified engineering organizations specializing in nuclear power plants in which conceptual designs were prepared for berm-contained facilities (near-surface underground concepts where the reactor and other plant systems with large inventories of radioactive materials are buried in soil within a relatively shallow excavation) and facilities constructed in underground mined-caverns in rock. The studies included preparation of cost estimates for subsurface and comparable surface nuclear power plants. All cost estimates were developed for conditions specifically related to California siting of such facilities. For example, the study specified, among many other items, the use of seismic design levels which were high (0.5g) compared to values appropriate to the Eastern United States (commonly about 0.25g); closed cycle cooling water systems; and labor costs based on typical California wage rates. Sensitivity studies were also conducted of a number of other construction related parameters which were expected to have the most significant impacts on costs.

A third study (Ref 1-3), summarized herein, was conducted to analyze and evaluate the relative consequences of very severe (and highly improbable) reactor accidents in surface and underground facilities. (The terminology "underground" is used in this report in a generic sense to refer to both berm-contained and mined-cavern concepts.) From these analyses, conclusions may be drawn with respect to the relative attractiveness of the concepts as alternatives to surface siting of nuclear power plants.

The California Division of Mines and Geology carefully examined the significant geophysical and major demographic factors relevant to underground siting. Maps were prepared to determine the general availability of technically acceptable areas for subsurface siting. Their findings (Ref 1-4) are also summarized in this report.

A study of the seismic implications for underground siting (Ref 1-5) was conducted to establish general design criteria and to evaluate whether or not subsurface siting offered major benefits in high-seismic environments. Such information is particularly relevant to earthquake-prone California. Other significant design criteria and study guidelines were developed in a preliminary investigation (Ref 1-6) of the general underground nuclear power plant subject areas of technical feasibility, cost, and effectiveness.

A number of other program efforts conducted as part of the overall CEC investigation have not been identified above or included in this summary. These efforts included an environmental analysis (Ref 1-7) undertaken to identify any major differential impacts between surface and subsurface nuclear facilities during construction and normal operation; decision analyses undertaken to establish a framework for weighing the merits and penalties of siting options (Ref 1-8); application of a probabilistic cost model to quantify the uncertainty in concept cost

estimates (Ref 1-9); and a general analysis of Federal regulations governing the siting and construction of underground nuclear power plants (Ref 1-10). The Reference list of Section 1 identifies individually available, program-sponsored reports. The interested reader is referred to those documents for details of particular investigations. They are available from the Publications Unit, California Energy Commission, 1111 Howe Avenue, Sacramento, California 95825 by mail, or by telephone: toll free (800-852-7516) in California; or (916-322-3725) outside California.

1.1 MOTIVATIONS FOR UNDERGROUND SITING

Underground siting of nuclear power plants has been recommended by its supporters for a variety of reasons. Historically, underground siting has most often been equated to siting in mined-rock caverns. Recently, however, the so-called berm-contained, or soil-covered, facilities have been included as "underground" concepts. The nation's first commercial electricity-generating power reactor at Shippingport, Pennsylvania, had the major plant systems containing radioactivity constructed below ground. The Humboldt Bay nuclear power plant near Eureka, California, also has its reactor located well below ground level. Although these facilities could not be considered to be "underground" or even "berm contained", as defined in this study, they do illustrate one motivation for below surface siting. For both of these plants, the surrounding soil was utilized as an effective radiation shield which reduced the need for, and expense of, constructing shielding such as concrete walls for the protection of workers in the facilities. A second reason suggested for underground siting has been protection of the plant from external hazards including wind-generated missiles, falling aircraft, industrial explosions, military acts, or sabotage.

A third motivation for recommending underground siting has been associated with the potential for gaining a structural benefit from the subsurface environment. For example, as will be discussed in detail

subsequently, an underground facility is not expected to be subjected to seismically induced loads as severe as those of a surface plant for an equivalent earthquake at a given site.

In the United States, however, perhaps the most frequently occurring argument for underground siting has stemmed from a feeling that subsurface siting might offer substantial public safety advantages, if certain improbable, but severe, reactor accidents should occur (those which result in massive melting of the reactor's nuclear core).

As background, it is the radioactivity which builds up in the nuclear core of the reactor which makes it a potential health hazard. The radioactivity of a reactor is not a constant, but increases and decreases over its operational lifetime. When a light-water reactor is first placed in operation, it is loaded with fresh, naturally radioactive uranium-oxide fuel with an aggregate activity averaging about several hundred curies. This fresh fuel is only slightly radioactive and can be handled with relative safety. During reactor fueling processes, the fresh fuel customarily is handled by workers using only thin cotton gloves for protective shielding. However, after extended periods of reactor operation for power production, the nuclear fission process which produces the energy for the power plant will also produce large amounts of additional, highly radioactive fission products within the fuel. For example, if a large reactor (of about 1000 megawatts of electrical power output) is operated at full power for about one year, the radioactivity contained within the fuel in the core of the reactor will increase to approximately 17 billion curies. Though the fission-product sources of the radioactivity are largely restricted to the fuel rods themselves, energetic gamma rays emitted by the radioactive fission products have great penetrating power. Consequently, heavy shielding is necessary for protection from the extremely hazardous radiation emitted by the fuel, after it is removed from the reactor (or if the radiation escapes by accidental means).

If the reactor is shut down, the buildup of fission products in the fuel ceases, and the level of radioactivity in the irradiated fuel decreases as time passes. A very rapid rate of decrease occurs initially in the fission product inventory due to a preponderance of short-lived fission products. The radioactively decaying fission products also produce a substantial quantity of energy ("decay heat"), which must be dissipated in order to prevent the fuel from overheating. Power reactors have been provided with heat removal systems for periods of reactor shutdown, such as the Emergency Core Cooling System, to remove the decay heat from the reactor fuel rods.

At the time of shutdown, the decay heat represents about 7 percent of the rated thermal power output of the plant. This amounts to approximately 225 MW of thermal power for a plant with an electrical capacity of 1100 MW, and a corresponding rated thermal output of about 3300 MW at full operational loads. Within 10 seconds after shutdown, the decay heat would decrease to about 5 percent of the rated thermal output, dropping to 2 percent after 10 minutes, and reaching 1 percent after 2.25 hours. Within 24 hours after shutdown, the decay heat would fall to about 0.5 percent of the rated thermal output of the plant. The rate of decay heat production decreases very slowly thereafter, due to long-lived fission products, reaching 0.1 percent of rated thermal power (or about 4 MW) about 30 days after shutdown.

At the end of a one-day period, the total radioactivity of the shutdown reactor has decreased from its initial shutdown inventory of 17 billion curies to about 4 billion curies. Within 30 days, the radioactivity will have decayed to about 1 billion curies. It will diminish to about two-thirds of a billion curies in two months; and slowly decay to about one-tenth of a billion curies over a period of a year after shutdown. In a similar manner, the same one-year shutdown period would reduce the rate of production of decay heat from its

original 225 MW of thermal power to a thermal output of less than 1 MW. Table 1-1 presents a summary of the radioactivity and thermal power output of an 1100 MW_e reactor as a function of time after shutdown.

The enormous quantities of hazardous radioactive fission products and the large thermal power output of the related decay heat are the primary properties which make reactor accidents of unique and special concern. If a reactor accident should occur, the fuel rods must be kept immersed in water to prevent overheating. If the water bath should be lost by some mechanism, the fuel rods would melt in a very brief period (in about an hour or less), releasing the gaseous and volatile portions of the fission products to the confines of the protective reactor containment structure. An existing (or subsequent) breach of the reactor's containment structure could then release the radioactive gases to the environment. The molten radioactive core of the reactor might also penetrate the foundation of the containment structure, furnishing another pathway for release of radioactivity to the external environment. More detailed descriptions of the events associated with a core meltdown accident are presented in subsequent sections of this report (e.g., Sections 4.1 and 4.2).

As a result of the reactor industry's and the U.S. Nuclear Regulatory Commission's (NRC) "Defense-in-Depth" approach to plant design and construction for assurance of public safety, such accidents are very unlikely to occur in a nuclear power plant. The Defense-in-Depth concept requires the application of high standards in plant and operational equipment design and construction; incorporation of specifically designed "Engineered Safety Features" into the plant to prevent accidents from reaching conditions where core-melt could occur; and inclusion in the plant of multiple, redundant and independent barriers against release of harmful amounts of radioactive fission products from the reactor. However, because operational reactors possess very large inventories of radioactive fission products of great potential lethality, the

Table 1-1. Calculated Radioactivity of 1100 MW_e PWR^a at Shutdown and as a Function of Decay Time^b

Decay Time, Days	Iodine and Bromine Isotopes	Radioactivity (Megacuries)				Total	Total Thermal Power kW
		Noble Gases	All Fission Products	Actinides	Activation Products		
0	1435	1240	13800	3450	10.6	17250	225000
1	265	221	2890	1330	9.19	4230	17400
5	101	105	1870	432	8.42	2310	9720
15	28.7	29.0	1280	39.7	7.50	1330	5600
30	6.74	4.77	947	9.35	6.40	963	4060
60	0.494	0.784	656	6.32	4.76	666	2350
120	0.00282	0.659	401	5.90	2.76	410	1740
210	0.00000309	0.648	244	5.56	1.36	250	1100
365	0.00000218	0.630	146	5.17	0.614	152	659
1097	0.00000218	0.553	47.3	4.45	0.324	52.0	204
3653	0.00000218	0.353	17.9	3.27	0.132	21.3	67

^aReactor is assumed to be shut down just before refueling after a sustained (293 day) period at a specific power of 37.5 MW/metric ton. The time average specific power over the previous 1100 days is 30 MW/metric ton. The reactor is fueled with 3.3% enriched uranium totaling 82 metric tons of enriched uranium fuel.

^bTable from Report WASH-1250

probability of incurring a serious accident in a nuclear power plant has been a subject of substantial investigation -- and controversy.

The most detailed study of the potential risks associated with such accidents (Ref 1-11) indicates that very serious accidents (where over 1000 people might be killed) are predicted to occur less frequently than once in every billion years of individual reactor operation. The calculations suggest that less serious accidents (inducing no more than one death, for example) should occur with frequencies of the order of once in every 10,000 to 100,000 years of operation per reactor. Vigorous debate has surrounded the accident frequency estimates associated with these predicted consequences. However, the highest published estimates of accident frequencies which have been proposed for the more severe accidents (estimates produced by skeptics of nuclear power) have been of the order of one in 10,000 reactor-years (Ref 1-12).

Though these estimates of accident rates for reactors are low compared to other accident rates which are accommodated by society with varying degrees of concern (e.g., automobile and aircraft accidents, major fires, dam failures, etc.), the acceptability of the risks of nuclear power reactor accidents to the general public has still been a subject of substantial controversy. It should be observed that many people find purely probabilistic treatments of very infrequent, but severe accidents an unsatisfactory basis for public risk assessments. Moreover, the lack of acceptance of such a probabilistic approach to assessment of such risks is not necessarily due to a lack of familiarity with the methodology of the subject matter or the results of its application. Thus, underground siting has been suggested as a means of eliminating the controversy over the likelihood and severity of a major reactor accident (Ref 1-13); as an element of a continuing program of safety augmentation techniques (Ref 1-14); as a necessary addition to the defense-in-depth concept; or simply, as a desirable siting concept (Ref 1-15).

On balance, some features of underground nuclear power plant construction have appeared to be potentially less attractive than they would be for a surface-sited facility. These have included concerns over space limitations in underground structures that might contribute to construction delays and/or increase problems with operations and maintenance for the facility after the plant was operational. Fire fighting has also been viewed as a potentially more difficult problem in the limited confines of an underground structure. In addition, several other problems have been considered to be especially serious for underground structures. These include such phenomena as cave-ins, rock falls, flooding, etc. There has also been some concern with respect to the availability of generally acceptable rock and soil sites for underground facilities within California.

These issues have been addressed in the course of the studies conducted for the CEC program. The results of the analyses have been summarized in this report.

1.2 PROGRAM OBJECTIVES AND SCOPE

The CEC program was developed and conducted in accordance with the following broad guidelines:

- a. Underground facilities were to be designed to protect against the effects of a severe reactor meltdown accident -- without first order regard for the improbability of the accident.
- b. Public safety (through prevention of catastrophic containment failure) was taken as the primary design goal for engineered Accident Mitigation Systems which were to be incorporated into the conceptual underground facilities for radioactive fission product control in case of severe reactor accidents.

- c. After consideration of public safety, a supportive design goal was established of achieving a facility design of reasonably low cost -- although trade-offs between operational convenience, maintainability, and in-plant safety were required to be considered.
- d. Accident Mitigation System designs were required to be developed with the recognition that they would be compared against a standard of total, passive protection to the public from the results of a broad range of postulated severe reactor accidents. Consequently, where possible, designs were sought for the Accident Mitigation Systems which would be demonstrably effective against nuclear power plant accidents which might otherwise be perceived by many as being catastrophic.
- e. Development of thoroughly credible facility designs and analyses of public consequences was required, based upon documented assumptions and well-defined engineering methods.

The desire for realistic designs, schedules, and cost estimates was another major factor influencing the direction of the program. Similarly, results of public consequence analyses were sought which would be reasonably representative of the demographic and geophysical conditions of California. To this end, the program was conducted with the broad objective of ensuring the development of both reasonable and conservative designs from which cost estimates could be derived which were neither excessively optimistic nor pessimistic. It was recognized that much of the uncertainty in cost estimates associated with conceptual designs has been contributed by schedule uncertainties. Consequently, designers were tasked with development of realistic schedules, together with definition of a representative range of reasonable upper and lower estimates of possible schedule perturbations. Demographic and siting

specifications were also developed on the basis of the premises relative to requirements for realism in the study.

In order to ensure systematic development of underground designs for consequence limitation in case of severe accidents, Specifications for Accident Mitigation Systems were defined which broadly outlined five concepts for augmented public safety. The five levels of safety augmentation were defined ranging from a Level-Zero concept, based simply on underground emplacement of a nuclear power plant with essentially the same design features as a surface facility, to a Level-4 concept which provided for complete isolation from the biosphere (within an essentially impenetrable, energy-absorbing containment structure) of any fission-products released during a meltdown accident. The basic outline for the Accident Management System Design Levels was as follows:

- Level-0 - Incorporation of only conventional Class-8 surface facility design features and methodology in an underground environment.
- Level-1 - Conventional surface facility Class-8 design with protective isolation devices on all tunnels, shafts and other penetrations to the surface.
- Level-2 - Elementary Class-9 Accident Mitigation System using a pressure relief mechanism (high-permeability tunnels, expansion volumes, etc) with a directed path to the earth medium surrounding the facility, in order to achieve pressure and fission product management through utilization of the natural external environment of the underground facility.
- Level-3 - Class-9 Accident Mitigation Systems with an added pressure management system incorporating a controlled, filtered venting system.

Level-4 - Class-9 accident control with complete fission product retention within underground containment using core catchers and long-term energy dissipating systems, as necessary.

The Accident Mitigation Systems presented above have been defined in terms of accident "Classes" developed by the NRC. The NRC has subjectively divided accidents which might occur in a nuclear power plant into 9 "Classes". Accidents in Classes 1 through 9 are categorized in ascending order of severity of consequences as shown in Table 1-2. Prior to NRC licensing, a reactor must be shown capable of controlling all categories of accidents up to, and including, a Class-8 accident (representing the most severe "Design Basis Accident") without substantial releases of radioactivity. A Class-8 accident can involve a partial meltdown of the core and substantial releases of radioactivity to the confines of the reactor containment building. However, before the NRC will approve a construction permit for a nuclear plant, the containment building housing the reactor must be shown to be capable of retaining its integrity under the Class-8 accident conditions. Class-9 accidents embody all those accidents which are more severe than Class-8; especially those postulated to result in substantial core meltdown together with a breach of the integrity of the containment structure for the reactor.

Historically, regulatory emphasis has been on accident prevention through the Defense-in-Depth concept mentioned previously. Under this philosophy, prior to licensing, each nuclear power plant is required to demonstrate the effectiveness of NRC specified "Engineered Safety Feature" (ESF) systems in preventing minor (up to Class-8) accidents from becoming severe (Class-9) accidents. Some critical ESF effectiveness demonstrations have only been made on the basis of paper engineering design studies, without the benefit of actually simulating Class-9 accidents in experimental demonstrations, for evident reasons.

Table 1-2

Reactor Facility

Classification of Postulated Accidents and Occurrences*

No. of Class	Description	Example(s)
1	Trivial Incidents	Small Spills Small Leaks Inside Containmentment
2	Misc. Small Releases Outside Containmentment	Spills Leaks and Pipe Breaks
3	Radwaste System Failures	Equipment Failure Serious Malfunction or Human Error
4	Events that Release Radioactivity into the Primary System	Fuel Defects During Normal Operation Transients Outside Expected Range of Variables
5	Events that Release Radioactivity into Secondary System	Class-4 and Heat Exchanger Leak
6	Refueling Accidents Inside Containmentment	Drop Fuel Element Drop Heavy Object Onto Fuel Mechanical Malfunction or Loss of Cooling in Transfer Tube
7	Accidents to Spent Fuel Outside Containmentment	Drop Fuel Element Drop Heavy Object Onto Fuel Drop Shielding Cask - Loss of Cooling to Cask, Transportation Incident on site
8	Accident Initiation Events Considered in Design-Basis Evaluation in the Safety Analysis Report	Reactivity Transient Rupture of Primary Piping Flow Decrease - Steamline Break
9	Hypothetical Sequences of Failures More Severe Than Class-8	Successive Failure of Multiple Barriers Normally Provided and Maintained

*Reproduced from Ref 1- 16

However, on the basis of these "demonstrated" ESF capabilities, a Class-9 accident could only occur if several of the ESF in a nuclear plant simultaneously failed to function. Statistical studies of the probability of simultaneous failure of several of the ESF have led to the low probability estimates for severe Class-9 accidents which were mentioned above. (Ref 1-11)

Recent changes in regulatory philosophy are detectable, due in part to risk analyses which have explicitly treated Class-9 accidents in the spectrum of acknowledged concerns. More attention is now being given to using the results of statistical investigations of a "complete" set of accidents with their corresponding probabilities and consequences to identify important areas where concentrated efforts could lead to significant improvements in nuclear power plant designs with potentially significant reductions in public risk. (Ref 1-17)

In the CEC study of underground nuclear power plants, a design philosophy was adopted which explicitly attempted to restrict design innovations which would substantially violate existing licensing requirements. Within this framework, engineers were given the goal of designing facilities which would accommodate licensing requirements, as nearly as possible, and incorporate all standard ESF systems. Thus, accident prevention was the main line of defense in the CEC sponsored designs as it is in more conventional surface-sited nuclear power plants. However, as a last barrier to surface release of fission products, accident mitigation systems which take full advantage of the underground environment have been integrated into the underground facilities. They have been designed to provide additional aid in the improbable event of multiple ESF system failures.

Only Level-2 and 3 Accident Mitigation Systems were designed and evaluated in any detail for the underground facilities of the CEC program (cf, Sections 2 and 3). Level-0 systems appeared to offer only minimal

advantages over surface plants. It was apparent that it would be difficult to assure the effectiveness of a Level-1 design, as was also shown in other studies (Ref 1-18). Level-4 design concepts were beyond the scope of the CEC Study due both to technological and time limitations. Accident Mitigation System concepts could be applied to surface facilities as well as underground plants. Consequently, a design was prepared and an evaluation conducted for a Level-3 concept applied to a surface plant (cf, Sections 3 and 4).

The scope of the study was restricted to light-water reactors (LWR) in order to concentrate on the more probable candidates for reactor licensing in California in the immediate future. This limitation should not be taken as a judgement in any form of the relative safety, feasibility or applicability of other reactor systems. Moreover, there are no obvious restrictions which would prevent other commercial power reactor concepts from being considered as candidates for underground emplacement, if this type of construction were to become a licensing requirement of the State of California.

Accident probabilities were not specifically determined for the underground facility design concepts of this study. As discussed in more detail in Section 3 below, the evaluation of accident risks requires the weighting of accident consequences for a given event by the probability of the occurrence of the event. Accident probabilities cannot be adequately determined in the absence of detailed final system designs. Designs of this type were beyond the financial constraints and time limitations of this program. Consequently, it was not possible to develop a complete set of accident scenarios from the conceptual designs of this study, nor to evaluate the specific sets of probabilities of system failures associated with such scenarios. Thus, explicit quantification of accident probabilities, such as those conducted for surface nuclear facilities in the Reactor Safety Study (Ref 1-11), was not performed for these studies. However, the results of Reference 1-11

were analyzed, evaluated and utilized (where applicable) in estimates of the relative likelihood of accident scenarios associated with underground and surface-sited facility designs.

1.3 PROGRAM STRUCTURE

The basic structure of the CEC program is outlined in Figure 1-1. As indicated, the program was conducted in two phases. A description of the results of the Preliminary Phase of the program is contained in Reference 1-6. Primary emphasis in this document has been placed upon the results of the second or Detailed Study Phase of the program, as shown in Figure 1-1. However, where appropriate, some of the significant results of the preliminary phase have also been summarized in this report.

The principal participants in the program included the California Division of Mines and Geology, who conducted Task 10 in which a preliminary assessment was made of the general availability of technically acceptable siting conditions for construction of underground facilities. Two highly qualified Architect/Engineer (A/E) firms conducted the design and costing efforts (Task 11). These included S&L Engineers, the California-based arm of Sargent and Lundy of Chicago, Illinois, who analyzed the berm-contained plant. S&L Engineers' experience included, in part, the preliminary design analyses for a similar underground cut-and-cover facility prepared for a Middle-Eastern country. The mined-cavern concept was developed by Underground Design Consultants (UDC) representing a joint venture including the firms of Foundations Sciences, Inc., of Portland, Oregon; Parsons, Brinckerhoff, Quade, and Douglas, Inc., of New York; and Vattenbyggnadsbyran of Stockholm, Sweden; supplemented by Gibbs and Hill, Inc. (the designers of the only operational commercial underground nuclear power plant in the world -- Chooz, France). UDC efforts were further strengthened, in BWR portions of the design, by consultant support from ASEA-ATOM of Sweden;

Figure 1-1. Study of Underground Siting of Nuclear Power Plants

and, in their geotechnical considerations by Woodward-Clyde Consultants, Inc., of California.

The consequence analysis portion of the study, Task 12, was conducted by the Advanced Research and Applications Corporation (ARACOR) of Sunnyvale, California, with major supplemental support from Intermountain Technologies, Inc., of Idaho Falls, Idaho, in the development and analysis of the thermodynamics and gas dynamics of accident sequences in the underground facilities.

Support to the CEC for technical program management and integration of the efforts of the several contractors was provided by The Aerospace Corporation. The CEC was also supported in the systems management of the program by the Jet Propulsion Laboratory, who analyzed certain regulatory, legal, and economic aspects of the study. The Jet Propulsion Laboratory efforts will be reported separately.

The material reviewed below represents the results of a one-year program for evaluation of the technical aspects of the overall CEC study, including both the Preliminary and Detailed Study phases. The second half, or Detailed Study phase of the program, was conducted in an intensive six-month effort culminating in the designs, economic analyses, and consequence analyses summarized below.

REFERENCES

- 1-1. S&L Engineers, "Conceptual Design and Estimated Cost of Buried 'Berm Contained' Nuclear Power Plants," January 1978.
- 1-2. Underground Design Consultants, "Conceptual Design and Estimated Cost of Nuclear Power Plants in Mined Caverns," December 1977.
- 1-3. Advanced Research and Applications Corporation, "Analysis of Public Consequences from Postulated Severe Accident Sequences in Underground Nuclear Power Plants," December 1977.
- 1-4. CEC, "Underground Siting of Nuclear Power Reactors: Determination of Site Characteristics and General Availability in California," January 1978.
- 1-5. Applied Nucleonics Co., Inc., "Seismic Assessment of Underground and Buried Nuclear Power Plants," Report No. 1226-1, September 1977. (Prepared under subcontract to The Aerospace Corporation. Also published under Aerospace Report No. ATR-78(7652-01)-2.)
- 1-6. The Aerospace Corporation, "Systems Management Support for ERCDC Study of Undergrounding and Berm Containment: Interim Report, Preliminary Program Assessment and Follow-on Program Development," ATR-77(7652-01)-1, August 1977.
- 1-7. Environmental Science Associates, Inc., "Environmental Impacts of Underground Nuclear Power Plants," Report No. ESA-EIA-3077 (Revised), 20 September 1977. (Prepared under subcontract for Advanced Research and Applications Corporation.)

- 1-8. Jet Propulsion Laboratory, "Decision Analysis Framework for the Underground Siting of Nuclear Power Plants," 5030-92, May 1977.
- 1-9. Jet Propulsion Laboratory, "Methodology for the Estimation of Cost of Underground Nuclear Power Plants," 5030-89, May 1977.
- 1-10. Jet Propulsion Laboratory, "Analysis of Federal Regulations Governing Siting and Construction of Nuclear Power Plants as Applied to Underground or Berm Containment," 5030-88, September 1977.
- 1-11. U.S. Nuclear Regulatory Commission, "Reactor Safety Study," WASH-1400 (NUREG-75/014), October 1975.
- 1-12. Union of Concerned Scientists/Sierra Club, Joint Review Committee, "Preliminary Review of the AEC Reactor Safety Study," November 1974.
- 1-13. Teller, Edward, "Hearings on Proposition 13, Volume III: Technological Concerns in Nuclear Reactor Safety, Part 1/ California State Assembly Committee on Resources, Land Use, and Energy, Sacramento, CA, October 1975".
- 1-14. American Physical Society, "Report to the APS by the Study Group on Light-Water Reactor Safety," Review of Modern Physics, Vol. 47, Suppl. No. 1, Summer 1975.
- 1-15. Carter, James Earl, Campaign Statement.
- 1-16. USAEC, "The Safety of Nuclear Power Reactors (Light Water-Cooled) and Related Facilities," WASH-1250, July 1973.

- 1-17. Personal Communication, Dr. Saul Levine, U.S. Nuclear Regulatory Commission, February 1978.
- 1-18. Allensworth, J.A., et al, "Underground Siting of Nuclear Power Plants: Potential Benefits and Penalties, SAND76-0412/NUREG-0255, Sandia Laboratories, Albuquerque, N.M., August 1977.

THIS PAGE
WAS INTENTIONALLY
LEFT BLANK

2.0 UNDERGROUND NUCLEAR POWER PLANT CONCEPTS

The design concepts for the underground nuclear power plants of this study were developed with due consideration for the technological background provided by previous studies and actual experience in design and construction of underground nuclear facilities. Underground plants have had many advocates and critics. Their concepts and evaluations influenced the CEC study structure objectives, and guidelines. However, a unique aspect of the CEC Study has been the explicit intent to develop facility design concepts which were integrated with the underground environment in order to utilize its native properties in a mitigation system for severe reactor accidents. This overriding consideration significantly influenced underground concept development in the program. Most previous studies have been conducted on the basis of a straightforward extrapolation of surface nuclear power plant designs into the underground environment. These extrapolated surface design concepts were found to be generally ineffective in reducing public risks from severe reactor accidents. However, in this CEC project, innovative accident mitigation systems were developed which could take full advantage of the underground properties of the earth. As a result, substantial reductions in radioactivity releases from postulated severe accidents were achieved in the CEC underground designs by utilization of the filtering and ionic demineralization properties of the earth. The concepts and results will be presented in more detail in subsequent sections of this report.

2.1 BASIS FOR DEVELOPMENT OF CONCEPTS

A substantial body of literature has been published on the subject of underground nuclear power plants. As a generalization of the published results, two fundamentally different concepts for underground facilities have been suggested. The majority of the earlier studies (cf, Refs 2-1 through 2-9) considered concepts such as those shown in Figure 2-1. In these studies, the nuclear plants were designed for construction

HORIZONTAL ENTRY

VERTICAL ENTRY

Figure 2-1. Mined Cavern Concepts

in caverns excavated in large, monolithic masses of high quality rock, such as those which can be found in the granite batholith of California's Sierra Nevada mountain ranges. A somewhat smaller set of studies have been conducted of nuclear plants of the second general type. These envisioned a nuclear plant similar to those shown in the sketches of Figure 2-2 where the facility would be buried in shallow soil excavations beneath the surface of the earth (or in a hillside), (cf, Refs 2-9 through 2-13). In addition to paper studies, four nuclear facilities have actually been constructed underground. These have all been built in Europe, all in mined-rock caverns, and all have been constructed in hillsides with essentially horizontal access tunnels between the entry portals for the plants and the principal underground structures (cf, Refs 2-14 through 2-18).

As indicated in the sketches of Figures 2-1 and 2-2, a wide variety of facility arrangements and access methods are possible within the framework of the two basic types of underground concepts considered. As examples, the facility may be entered (and constructed) through nearly horizontal tunnels, or by vertical shafts; various elements of the major plant systems, especially the turbine-generator related systems, may be located above or beneath the ground surface; plants may be constructed in hillsides or on flat terrain; or a number of other design variations may be considered. Each of the variations would be expected to impact the economic feasibility of the facility and perhaps its technological feasibility as well.

In conducting the CEC study of underground nuclear power plants, no a priori decisions were made with respect to the best underground design concepts. However, during the initial phases of the program decisions were made (Ref 1-6) with respect to selection of certain concepts as "baseline" designs to be developed during the study. These decisions were based upon preliminary analyses of concept effectiveness, feasibility, and economy. Parametric investigations involving many of the above mentioned alternative design variations were also conducted in

Figure 2-2. Berm Contained Concepts

the study. The results of these analyses will be discussed in subsequent sections. The baseline design concepts of the study are presented in this section of the report.

Motivations for construction (or study) of underground nuclear power plants have varied, but severe reactor accidents have rarely been explicitly included in such consideration. (In this discussion, severe reactor accidents are those which result in essentially complete meltdown of the highly radioactive core.) For example, a major consideration for the SENA, Chooz facility (an underground nuclear power plant actually constructed in France) was military security. The French nuclear regulatory authorities believe that surface-sited nuclear plants are adequately safe. Consequently, the concept of utilizing underground plant construction to limit public health effects from severe accidents was not the dominant motivation for the siting of the Chooz facility.

Similarly, most of the studies of underground nuclear power plants cited above have restricted their analyses to evaluation of facility effectiveness against a more limited set of accidents (NRC Class-8, or less), where only partial core meltdowns were considered. For such accidents, reactor containment structures for surface-sited nuclear facilities are designed to limit releases of radioactivity to the environment to essentially insignificant levels. Containment system designs for the majority of the previous underground facilities studied were functionally similar to those of surface-sited nuclear power plants. Therefore, when the evaluations were limited to consideration of Class-8 (or lower) accidents, the relative effectiveness of underground plants was not demonstrably greater than that of a surface facility.

Of the documents cited, only one (Ref 2-9) deals in any depth with the effects of the more severe category of reactor accidents (NRC Class-9) of concern to this study. (The nature of the accidents analyzed in this Study is defined in greater detail in Sections 3 and 4 of this document.) In the study (Ref 2-9), no specific attempt was made to

develop designs for underground facilities which would take significant advantage of the underground environment in order to reduce the potential for catastrophic releases of radioactivity to the public.

The CEC study, however, was conducted with the explicit goal of developing designs for underground nuclear power plants which utilized the earth as a direct means for controlling and mitigating fission product releases from severe reactor accidents so that unanticipated major releases of radioactivity could not occur. This was done by specifically recognizing the potential of the earth for (a) providing a heat-sink for the energy released in a severe accident; (b) providing a natural mechanism for relieving pressures from gases and vapors through the native permeability and bulk porosity of soil and rock; and (c) providing an effective filtering medium which could substantially reduce the quantities of fission products released in a severe reactor accident; and hence reduce the impacts of the most hazardous of the released radioisotopes. Specific systems for accident mitigation were developed in the study which were designed to take advantage of these features of the subsurface environment. These systems will be described below.

2.2 SURFACE PLANT DESIGNS

To permit internally consistent evaluations of estimates of cost differences between surface and underground facilities, specific designs were developed in the CEC study for both types of plant concepts. Two different organizations, with differing design philosophies and differing approaches for implementing the construction of the designs, were responsible for developing the two underground concepts and estimating their costs. Each of the organizations also prepared a reference surface plant design so that underground plant cost estimates could be compared against surface plant estimates which had been developed on a consistent basis.

2.2.1 Facility Design Specifications

The two reference surface plant designs developed for this study, one prepared by S&L Engineers, Inc. (S&L), and the other by Gibbs and Hill, Inc. (G&H) for UDC represent the application of the most recent experience of both firms in designing nuclear power plants. The design prepared by S&L Engineers incorporates the experience and knowledge accumulated on over 2 dozen large size nuclear plants constructed in the U.S. The Gibbs and Hill design is based on their standardized balance-of-plant design (GIBBSAR) recently submitted to the NRC for licensing approval. Both the S&L and G&H reference surface plant designs were required to meet a 0.5g seismic design criteria specified as the baseline for the study. This earthquake motion specification is higher than is customarily required for nuclear plants constructed outside of California; but it was selected as an appropriate value for a seismic criterion in view of California's high potential for seismic activity (cf, Section 6.1).

In accordance with program specifications, both S&L and G&H utilized a 3800 MW thermal power standardized Westinghouse RESAR 414 nuclear steam supply system (NSSS) in their surface plant designs. Other comparable NSSS which are made by Babcock and Wilcox, Combustion Engineering, and General Electric could have been utilized in the plant designs without significantly altering the conclusions of this study with respect to cost, constructability, or operability of the facilities. The Westinghouse reactor was selected on the basis of design maturity and the relative numbers of Westinghouse systems utilized throughout the nation in comparison with other NSSS suppliers. However, all of the NSSS designs considered in this study, irrespective of manufacturer, satisfy regulatory requirements currently in effect and incorporate provisions for implementation of additional requirements wherever they are currently under consideration. The RESAR 414 is representative of the current standard for the state-of-the-art in nuclear steam supply system design.

For consistency, the Westinghouse RESAR 414 was also used as the baseline NSSS for the underground facility designs. Sensitivity studies were conducted of the cost impact of utilizing the NSSS of the other major U.S. reactor vendors in the underground designs.

The Reference surface nuclear plants have been designed around the concept of a totally independent, self-contained electrical power producing facility. Each facility consists of a single nuclear steam supply system and all necessary balance-of-plant structures, systems, and components required to produce 1340 MW of electrical power. An independent, self-contained, power plant concept, is not necessarily the optimum economic choice for a large, multiunit nuclear power installation. The utilization of such units in this study was based upon observations of current utility practice in cases where standardized nuclear power plants are being considered, or adopted. A number of utilities are considering the use of self-contained, completely independent plants of this sort for multiunit sites. Plans call for these installations to use side-by-side, but separate, construction of the individual facilities. Under these circumstances, only administration buildings for the combined facilities would be shared. The self-contained concept was particularly useful for this study since it permitted consistent comparisons to be made between surface plants and similar self-contained underground plant concepts.

2.2.2 UDC/G&H Surface Plant Features

Figure 2-3 illustrates the external features of the GIBBSAR Reference surface plant. The cylindrical structure dominating the skyline of the figure is the cylindrical reactor containment building. The containment building functions as a final barrier to the spread of radioactive material that could be released from the reactor located within, if a serious accident should occur. This structure with its thick reinforced concrete walls and domed roof, also protects the reactor

Figure 2-3. UDC/Gibbs & Hill Reference Surface Plant

systems equipment from external threats of weather (hurricanes, tornadoes, etc.), flying objects (wind-launched, high-velocity debris, large airplanes, etc.), and provides security against unauthorized entry.

In the illustration of Figure 2-3, the containment structure is surrounded by a larger building of lower elevation, called the "auxiliary building". In this design approach for a surface plant, (called the "nuclear island" concept) the support systems for the reactor plant, including waste processing systems, are distributed around the perimeter of the containment building within the confines of the auxiliary building. This arrangement has advantages for aseismic design because most of the critical components of the plant are mounted on a common foundation slab. As a result, the equipment interconnections are not subject to the potentially large differential motions which might occur in an earthquake if the equipment were located in several separate buildings with independent foundations. The large building shown behind the containment structure houses the turbine-generator and related equipment for the facility. The steam produced by the reactor is carried in massive steel pipes from the containment structure to the turbine-generator where the thermal energy of the steam is converted into electrical energy.

2.2.3 S&L Surface Plant Features

Figure 2-4 shows an artist's rendering of the plant arrangement for the S&L Reference surface plant. As observed in the previous illustration, the cylindrical reactor containment is the dominant structure. The turbine-generator building is the large rectangular building extending to the left of the containment building. The S&L design differs from that of G&H with respect to the locations for auxiliary systems. In the S&L concept, the auxiliary systems are housed in several buildings separated from the turbine-generator and reactor structures, as shown in the foreground of Figure 2-4.

Figures 2-3 and 2-4 show the relative sizes, shapes, and arrangements of the nuclear plant structures and buildings. It is evident from comparison with familiar objects shown, that these structures are very large. For example, the reactor containment buildings for the Reference surface plants are about 240 feet high (about the height of a twenty story building) and about 150 feet in diameter.

In the surface plant designs, the reactor is located within the containment buildings shown in the preceding pictures and is isolated from the external environment by heavy closure doors and specially engineered wall penetration seals in locations where pipes and electrical circuits must be allowed to pass through the walls of the building. The design of the seals for the openings in the walls of the containment building depends on the predicted temperatures and pressures of the vapors and gases which might result from accidents occurring within the structure. The penetration seals must also be designed to accommodate pipe thermal expansions and movement in normal operation. For the surface plant, the containment structure's internal temperature and pressure can be significant as a result of severe reactor accidents. Thus accident-induced temperatures and pressures constitute design-basis conditions for the seals, as well as the containment structure.

The remaining buildings and structures would never be subject to as hostile an internal environment as the containment structure. None of the buildings, besides the containment structure, contain equipment with large enough inventories of fission products to provide the potential for catastrophic release of radioactive materials. Consequently most of these other buildings are not subject to the identical stringent NRC regulatory design standards that the containment structure is required to meet. It should be noted, however, that, high standards of quality control are required in the construction of all elements of the facility.

2.2.4 Relationships Between Underground and Surface Plant Layouts

In developing a rationale for determining which power plant components should be put underground, three factors were dominant. These included: (a) the potential for accidental release of radioactive fission products; (b) facility costs, and (c) operational performance. Those elements of the facility with the largest steady-state operational inventories of radioactive fission-products were the prime candidates for underground emplacement, in order to reduce the potential threat to the public from accidental releases of radioactivity. The reactor itself has by far the largest inventory of radioactive fission products of any of the systems in the facility. Thus, if decisions were made on the basis of minimum underground volume, or cost requirements alone, only the reactor and its associated containment structure might be placed underground. However, it appeared after analysis of the surface plant designs that the goal of minimizing changes in the design of plant equipment layouts and system interrelationships could not be achieved unless some other parts of the plant were placed underground with the reactor. In the final designs, the reactor, new and spent fuel, and waste-related equipment were all placed underground. On the basis of a preliminary economic analysis, the turbine-generator and related electrical equipment were also located underground in the baseline mined-cavern design concept. The economic significance of this decision was examined in an alternative mined-cavern concept with the turbine-generator located at the surface. In the baseline berm-contained facility, on the other hand, the turbine-generator was located above ground, since the lengthening of the steam lines from the NSSS did not appear to cause the design or performance of the plant to depart significantly from surface plant capabilities. In both baseline underground design concepts, the power plant control centers were located underground in order to assure similarity in control circuit relationships between underground and surface facilities.

Because the abbreviated schedule and cost constraints of this program permitted the development of only a limited level of design detail, it was necessary to utilize contemporary surface plant design technology and construction experience as much as possible. Therefore, a principal guideline was established which stipulated that currently available equipment and proven system layouts should be used whenever possible, even though some small cost penalties might be incurred for the underground plants from such requirements. This approach was considered to be better than attempting to redesign plant elements which have become more or less standardized (such as containment structure volumes) or estimating costs of major revisions in equipment design (especially for the reactor, or Nuclear Steam Supply System related elements) for which the NRC could require equipment manufacturers to perform expensive requalification and testing programs, if currently licensed designs were substantially altered.

2.3 BASELINE BERM-CONTAINED FACILITIES

After considering a number of alternative arrangements, a large dome-shaped structure enclosing a separate reactor containment building was selected for the baseline berm-contained facility design. This design is illustrated in the artist's rendering of Figure 2-5. The massive external structure was designed to be approximately half-buried within a shallow excavation. The protruding half would be covered with soil removed from the excavation (a construction method commonly referred to as "cut-and-cover"). The design is intended to minimize the expense of excavation and backfilling of the soil cover. It also provided a structurally efficient plant design which was consistent with the goals of (1) incorporating the identical equipment of the surface facility into relatively similar spatial relationships for systems within the underground facility; and (2) providing maintenance space approximately equivalent to that of the Reference surface plant. The configuration of the buried external structure with its cylindrical cross-section and hemispherical dome was selected on the basis of its efficiency in

Figure 2-5. Berm-Contained Underground Plant

carrying the heavy static load of the soil cover, while simultaneously resisting the large seismic forces associated with 0.5g peak surface accelerations. To reduce the possibility of structural differential displacements, overturning, sliding, and soil pressure design requirements from seismic excitation, a common-mat foundation structure was used for both the internal containment and the external structures. The free-standing containment structure is entirely enclosed within the dome-shaped auxiliary building.

2.3.1 Berm-Contained Facility Features

The dimensions of the domed exterior structure, shown in Figure 2-6, were selected to allow all equipment normally included within the auxiliary buildings for a surface-sited facility (including such systems as new and spent fuel handling and storage, rad-waste systems, etc.) to be located inside the exterior structure but outside the spatial envelope required for the freestanding reactor containment structure. Sufficient space was also provided within the external auxiliary structure to house the plant control center and related cable spreading and electrical equipment rooms. This permitted equipment and control circuitry to be arranged with relatively short vital cabling lengths and avoided the necessity of routing critical safety related circuits outside of the underground auxiliary structure. In the berm-contained design, with the turbine-generator located at the surface, the steam line length between the reactor and the turbine-generator is increased by about 100 ft over the equivalent line length for the Reference surface plant. This relatively small increment in steam line length is not expected to have a significant effect on plant performance (Ref 2-19).

Piping, cabling, and ventilation interfaces between surface and underground structures have been provided through tunnels connecting the external auxiliary structure with the turbine-generator building. Penetrations and doors for the tunnels would be constructed with seals to prevent the leakage of radioactive gases out of the external, secondary

Figure 2-6. Cross-Sectional View of Berm-Contained Underground Structures

containment structure in case the integrity of the reactor containment building was violated in the event of a severe accident. Normally, the main tunnel doors between the surface and the underground auxiliary structure would remain open during routine plant operation for ventilation purposes. If an accident should occur requiring isolation of the underground auxiliary structure from the external environment, the interconnecting tunnel doors would be manually closed and locked in position by plant personnel. Because the reactor containment structure would be hermetically sealed whenever the facility was operational, the tunnel seal doors between the underground auxiliary structure and the surface would only have to be closed if the reactor containment integrity were threatened as a result of a severe accident. Adequate time would be available for plant personnel to detect and respond to such a situation, as will be shown in more detail in Section 4.1. A fuel handling and storage facility for both fresh and spent fuel is located within the underground auxiliary structure. External access has been provided for fuel shipments via a short tunnel under the berm, which exits from the auxiliary building at a point nearly opposite the turbine-generator building interface and leads directly to the surface.

By analysis of the combined static loads and seismically induced dynamic ground motion forces, the required reinforced concrete thicknesses for the cylindrical wall of the superdome were shown to be 16 feet at the base, gradually tapering to 6 feet at the apex of the dome. The foundation mat is about 16 feet thick on the average. The interior of the superdome structure is about 230 feet high and 306 feet in diameter at the base. It's internal height is adequate to accommodate the reactor containment building (of essentially the same height as that of a surface plant) as a free standing structure.

No fundamental modifications are required for the reactor containment structure from those of a similar surface plant structure. However, a modest reduction in seismic loads, due mostly to the stiffness of the massive foundation mat for the underground structures, permitted

Figure 2-7. Schematic Diagram of Level-2 Accident Mitigation System for Berm-Contained Plant

The relatively simple hardware components for this Level-2 Accident Mitigation System are shown in Figures 2-6 and 2-7. The 24 pipes (1 ft in diameter) leading to the rock filter bed are routed through the massive concrete base mat of the auxiliary structure from the lower levels of the reactor containment. During normal operations, and relatively minor accidents, three parallel-connected, pressure and temperature sensitive valves (burst disks) isolate the reactor containment building from each of the ducts leading to the rock bed. During severe reactor accidents, pressures or temperatures within the reactor containment building would increase to levels (far above those of minor accidents) where the burst disks would be designed to rupture, with a resultant blow-down of released gases and vapors to the rock-bed heat-sink/expansion zone of the system.

The accident mitigation system serves two primary functional purposes. The first, and perhaps most important function is to prevent excessive build-up of pressures and temperatures within the containment structure which might result in uncontrollable, potentially catastrophic, failure of the structural shell. Failure could result in direct releases of radioactive fission product gases and vapors to the surface environment. The second major function of the accident mitigation system is to provide a controlled release path for the radioactive gases and vapors leading from the containment structure to the engineered expansion volume/heat-sink/filter zone outside the facility. Here the gases would be cooled and vapors condensed. Thereafter, the native properties of the soil would be utilized to mitigate the further release of radioactivity to the surface environment.

The Level-3 Accident Mitigation System, shown schematically in Figure 2-5, uses many components which are identical to those of the Level-2 system. However, in the Level-3 design, the 24 pipes from the containment structure are connected to a concrete header structure completely encircling the outside of the auxiliary structure. The header entirely encompasses the rock-bed filter/heat-sink in the Level-3 system

the underground containment structure to be designed with slightly thinner walls (cf, Section 6.1). As designed, it appears that the underground reactor containment could satisfy most current criteria for NRC licensing without significant problems. Though some licensing difficulties and/or delays would be expected with any novel design, no insurmountable problems are anticipated with this design approach for an underground facility (cf, Section 6.4).

2.3.2 Accident Mitigation Systems in Berm-Contained Facilities

The Accident Mitigation Systems (defined in general terms in Section 1.2) for Class-9 accidents have been incorporated as integral parts of all the underground designs of this project. The Level-2 concept, outlined schematically in Figure 2-7, utilizes the natural properties of the berm covering over the plant for pressure mitigation and radioactivity filtering and retention. The Level-2 system was specified for incorporation into the baseline design of the berm-contained facility. An expansion volume for gases and vapors released in the accident, consisting of an especially selected and prepared rock heat-sink/filter medium (gravel and stone), would be backfilled around the lower part of the igloo during the construction process. This rock bed provides the termination point for 24 large ducts leading from the containment building (also shown in Figure 2-6). When covered by the backfilled berm, the rock in the expansion volume/heat-sink zone is buried beneath about 150 feet of native (or, if required, specifically selected) soil which provides the ultimate filtering properties of the Level-2 system for radioactive fission products. In operation, the slowly expanding gases released in the postulated severe accidents would be forced to travel long distances as they percolated through the rock bed and soil before reaching the surface. The effectiveness of the long travel path as a filter of radioactive fission products will be described in more detail in Section 3.3.

design. A vent stack containing additional especially selected filtering media connects the underground rock-bed filled header to the surface. In the Level-3 concept, the permeability and porosity of the engineered filter bed and heat-sink system can be tailored to match design requirements for pressure-relief more optimally than would generally be possible with a Level-2 concept. However, the functional objectives of the Level-2 and 3 accident mitigation systems are identical.

2.3.3 Overview of Feasibility and Constructability

The principal conclusions derived from the study of the berm-contained plant conceptual design are described in more detail in subsequent sections. However, no major technological or analytical problems were discovered that would cause significant difficulties in construction or the functional effectiveness of the facility. It appears that the berm-contained design could be implemented with current construction practices without expectation of encountering significant surprises in the design or constructability of the facility.

2.4 BASELINE MINED-CAVERN FACILITIES

In the mined-cavern conceptual designs developed by the Underground Design Consultants' (UDC) team for the study, the nuclear reactor would be housed in an excavated structure within a very-large, monolithic rock mass. The plant concept utilizes the strength (as well as other physical properties) of the native rock in the design of the structure to house the facility. The feasibility of mined-cavern construction is dependent upon the existence of large very high-quality rock masses which can satisfy the structural design requirements for the excavation of tunnels and caverns within the rock. The caverns would provide the requisite space in which the plant equipment would be installed. Unfortunately, the geologic processes of nature do not produce the perfect rock materials, free of joints and flaws, that are customarily dealt with in the laboratory. It was therefore necessary to

develop the rock material property specifications used in this design study from previous siting studies conducted in California and experience in rock drilling and mining (cf, Section 4.1). Though the earlier siting studies were conducted for purposes other than power plant siting, the high quality rock incorporated in the specifications is believed to be representative of potential sites for California mined-cavern facilities.

2.4.1 Mined-Cavern Facility Features

In the design of mined-cavern facilities, it was determined that it was not practical to attempt to excavate a single large cavern within which the entire plant would be housed. The excavation of several smaller caverns (with interconnecting tunnels) in which to house the facility was found to be a more feasible approach. Consequently, the designs prepared for this project use a multiple cavern layout of this type.

The overall general arrangement of caverns, tunnels, and associated surface facilities for the baseline mined-cavern design is shown in Figures 2-8 and 2-9. The UDC plant was designed around four large caverns oriented parallel to a postulated tectonic stress field within the rock, which accounts for the angular orientation of the underground structures with respect to those constructed outside of the hill. Each of the large caverns is separated from its neighbors by a distance about equal to the largest adjacent cavity span, or about 100 ft, in most cases. Both small and large tunnels have been utilized in the design for routing of cables and piping between caverns, as well as for equipment access and personnel passages between the various parts of the plant.

The baseline plant was designed for a hillside site with a specified surface slope of about 40 percent. A flat site was also considered as an alternative design case. However, the hillside location allowed a preferred horizontal access tunnel to the caverns which was

Figure 2-8. Cutaway Sketch of Mined-Cavern Underground Plant Layout

Figure 2-10. Layout of Level-2 Accident Mitigation System for Mined-Cavern Facility

found to be the least expensive method of providing access to the caverns. In the baseline design, the reactor cavern would be located a distance of about 800 feet inside the hillside with the operating floor at about the same level as the external grade at the portal entry. At this distance inside the hillside, the reactor cavern would be under about 300 feet of cover, 100 feet of which would be weathered rock. The remaining 200 feet of solid competent rock would be more than adequate to permit the excavation of the freestanding (but heavily rock bolted) arched roof structure of the reactor cavern.

In its finished configuration (cf, Section 4.3), the reactor cavern would be lined with 3 ft of concrete, topped by steel plates. In the event of an accident, the reactor cavern would function as the primary containment structure for controlling radioactive materials which might be released from the reactor. The massive construction of this portion of the facility is required to satisfy the functional design requirements of the containment structure for licensing purposes.

In the baseline design, the auxiliary systems, turbine-generator, and transformer caverns are located on either side of the reactor cavern. The turbine-generator and transformer caverns are located nearer the outside entrance to the facility, relative to the reactor cavern, in order to reduce the length of condenser cooling water lines and underground electrical power cabling going to the cooling towers and switch yard located at the surface. Steam and feedwater piping, and electric power circuits would be routed through separate tunnels between the reactor and turbine-generator caverns. Located at one end of the long turbine-generator cavern are the steam generator feedwater heaters and associated piping. The plant control center and health physics areas are located at the other end. The feedwater heaters, which are typically located on both sides of the turbine, as in the Reference surface plant, were repositioned in the underground facility. In order to reduce the cavern span requirements, the feedwater heaters were grouped into a linear extension of the turbine-generator cavern.

The underground location of the plant control center in the other end of the turbine-generator cavern was chosen in order to retain control and monitoring circuit lengths which are comparable to those of a surface plant. With the underground control center location, cable routing can be similar to the circuitry of the reference surface plant, thereby maintaining the potential for similar levels of circuit reliability.

The alternative of locating the turbine-generator at the surface was examined as a mined-cavern concept sensitivity study. This concept increases the length of the steam and feedwater piping by about 700 feet. As will be discussed in more detail in Section 5, the surface turbine-generator configuration is somewhat less expensive than the equivalent underground design. On the other hand, the surface turbine-generator concept would be expected to have some slight plant performance penalties because of efficiency losses resulting from the lengthened steam lines. However, the incremental plant performance penalties would be insignificant when compared to the other intrinsic parasitic power losses associated with plant operation.

In the baseline mined-cavern design, the auxiliary cavern houses the rad-waste processing equipment, new and spent fuel storage facilities, and reactor coolant fluid chemical control equipment. This cavern would be positioned lower in elevation than the reactor cavern to ensure that the fluid heads for the Engineered Safety System circulating pumps would be the same as those of a surface plant.

2.4.2 Accident Mitigation Systems for Mined-Cavern Facilities

Extending to the right side of the reactor cavern, in the diagrams of Figures 2-8 and 2-9, are two tunnels which have been provided for the Level-2/Level-3 rock heat-sink/expansion volumes. These tunnels, shown in greater detail in Figure 2-10, are partly filled with

crushed-rock from the excavation. The tunnels are connected to the main reactor cavern through pressure and temperature sensitive valves similar to the rupture disks of the berm-containment-concepts. These devices would rupture (for both the Level-2 and Level-3 concepts), if either pressure or temperature within the containment cavern exceeded the design limits for the mitigation system. Once the valves opened, the hot gases would be released and flow over the crushed rock surfaces, thereby, cooling the gases and condensing the vapors, with a consequent reduction in the reactor containment cavern pressure. When the accident management system was called into operation, the Level-2 system would allow slow leakage of the expanded and cooled gases into the low-permeability, surrounding rock. Under these circumstances, the surface area of the unlined, rock-filled expansion/condensation zone tunnels would act as a long term heat-sink and ultimate filter medium for released radioactive gases and vapors in the baseline Level-2 systems.

The Level-3 accident mitigation system for the mined-cavern concept uses the same basic rock heat-sink and expansion zone tunnels as the Level-2 system, but connects them to a vertical shaft topped by a tall stack. Noncondensable gases would be vented through the stack after the gases had been cooled and filtered by percolation through the crushed rock within the tunnel.

2.4.3 Overview of Feasibility and Constructability

The proposed mined-cavern design requires a total horizontal cross-sectional area of about 250,000 sq ft for all of the underground caverns and tunnels. Based upon cavern-to-cavern, and complex-to-surface space requirements, a site with a rock mass of from five to ten times that cross-sectional area would be required for construction of the facility, i.e., about 25 to 50 acres. The size of the individual caverns would be dependent upon the size of the equipment to be installed (cf, Section 4.3). Using the Westinghouse RESAR 414 NSSS, the reactor cavern has been designed with a finished span of about 95 feet, the largest span

width required for any cavern in the facility. Based upon UDC/G&H sensitivity studies, reactor systems of equivalent power manufactured by Combustion Engineering and Babcock and Wilcox would require only slightly larger spans for construction of the containment cavern. However, reactor cavern span requirements for boiling-water reactors were found to be much larger (with a span of about 150 ft) than the equivalent spans needed for a PWR.

On the basis of the conceptual engineering design developed in this program and the current experience in underground hard rock construction, the proposed baseline mined-cavern concept appears feasible. However, caverns with spans of about 100 feet are considered very large by current standards, since only a few excavations of this size have ever been constructed. If the baseline mined-cavern concept were to be constructed, its magnitude would approach those of the largest known or currently planned underground mined-rock cavern projects in the world (either nuclear or hydroelectric) in excavated volume, and reinforced concrete emplaced. Though the excavations would be very large, the principal technological construction problems appear to be within the state-of-the-art for underground construction, at least for the baseline PWR design. Hence, subject to the availability of sites with adequate quantities of high quality rock, mined-cavern concepts of this type appear to be technologically feasible for underground nuclear power plant construction. The technological feasibility of the design, construction, and operability of mined-cavern facilities are discussed in greater detail in Sections 4 and 6 of this report.

REFERENCES

- 2-1. Franklyn C. Roger, "Underground Siting of Nuclear Power Plants: Environmental and Economic," Harza Engineering Company, Nuclear News, May 1971.
- 2-2. E. Jamne, "Underground Siting of Nuclear Plants in Norway," Institutt for Atomenergi, Kjeller, Norway. Fourth United Nations International Conference on the Peaceful Uses of Atomic Energy, Geneva, Switzerland, September 6-16, 1971
- 2-3. VBB (Vattenbyggnadsbyran), "Siting of Nuclear Power Plants with Respect to Protection Against Aerial Attack," Sweden, June 1974.
- 2-4. J. H. Crowley, P. L. Doan and D. R. McCreath, "Underground Nuclear Plant Siting: A Technical and Safety Assessment." Nuclear Safety, Vol. 15, No. 5, September - October 1974.
- 2-5. M. B. Watson, et al., "Underground Nuclear Power Plant Siting," The Aerospace Corporation, 1972.
- 2-6. M. B. Watson and W. A. Kammer, "Underground Nuclear Power Plants with Surface Turbine Generators," The Aerospace Corporation, 1973.
- 2-7. T. L. Brekke and C. E. Glass, "Some Considerations Related to Underground Siting of Nuclear Power Plants in Rock," University of California, 1973.
- 2-8. Centrala Draftledningen (CDL), (Swedish Power Producers) "Rock Siting of Nuclear Power Plants From a Reactor Safety Standpoint," Final Report, November 1975.

- 2-9. James Allensworth, et al., "Underground Siting of Nuclear Power Plants: Potential Benefits and Penalties," SAND76-0412 Sandia Laboratories, New Mexico, August 1977.
- 2-10. Norwegian State Power Board, "Assessment of Hypothetical Maximum Accidents in an Underground PWR Plant."
- 2-11. D. J. Fogarty, et al., "Design Concept for an Underground Nuclear Generating Station at a Coastal Site." Paper presented at 35th Annual Meeting American Power Conference, Chicago, Illinois, May 1974.
- 2-12. V. N. Karpenko and C. E. Walter, "Underground Siting of Nuclear Power Reactors," Lawrence Livermore Laboratory, University of California, Livermore, California, Siting of Nuclear Facilities. Proceedings of a Symposium Jointly Organized by the International Atomic Energy Agency and the OECD Nuclear Energy Agency, Vienna, Austria, December 9-13, 1974.
- 2-13. W. Kroger, et al., "Underground Siting of Nuclear Power Plants with Emphasis on the 'Cut and Cover' Technique."
- 2-14. "Fourth Annual Report, Halden Reactor Project," European Nuclear Energy Agency (ENEA), 1962.
- 2-15. B. McHugh, "The Agesta Nuclear Power Station," A. B. Atomenergi, Stockholm, 1964.
- 2-16. The Agesta Power Station Description, Personal Communication, 1972.
- 2-17. "Lucens: Switzerland's Experimental Pressure Tube Reactor," Nuclear Engineering, November 1962.

- 2-18. E. Ginggeli, P. Verstraete, and A. Sutter, "The Underground Containment of the Lucens Experimental Nuclear Power Plant." Fourth United Nations International Conference on the Peaceful Uses of Atomic Energy, Geneva, Switzerland, September 6-16, 1971.
- 2-19. S&L Engineers, "Conceptual Design and Estimated Cost of Buried 'Berm Contained' Nuclear Power Plants," Draft Final Report, p. IV-65, January 31, 1978.

3.0 PUBLIC HEALTH IMPACTS

In the past several years, the safety of light-water nuclear reactors has received a great deal of attention. Among the strong forces motivating such attention is the public perception of the risk associated with potentially catastrophic accidents which have been postulated to occur in nuclear reactors. The concept of risk, to be discussed in more detail below, encompasses both the likelihood of an event, expressed as a frequency -- or probability, and the associated severity -- or consequences -- of the event. For reasons which will be discussed below, this study did not address risks of reactor accidents in underground facilities specifically, but instead concentrated on attempting to quantify the relative consequences of postulated serious accidents occurring under similar conditions in both surface and underground plants. Accident probabilities, the other half of the reactor risk relationship, were considered in a qualitative fashion and some general observations with respect to the relative risk of reactor accidents in underground plants have been made in this section of the report.

3.1 THE NATURE OF REACTOR ACCIDENT RISK

Risk is defined as the product of the frequency (probability of occurrence) and the consequences of an event. This definition serves as the basis for the quantitative assessment of risks from all manner of activities. Risk may be expressed in two fundamental forms: either as an effect to society, or as an effect to an individual. For example, in 1971 there were about 15 million automobile accidents in the U.S. of which 1 in 300 resulted in a death. Thus, the societal risk of death from auto accidents was

$$R_s = 15,000,000 \times \frac{1}{300} = 50,000 \text{ deaths/year}$$

and, for a society consisting of approximately 200 million people, the average individual risk was

$$r = \frac{5 \times 10^4}{2 \times 10^8} = 2.5 \times 10^{-4} \text{ , deaths/person-year}$$

Expressed in an equivalent way, each individual in the U.S. (including men, women, and children) has about one chance in 4000 of being killed in an automobile accident over a period of a year. Other examples of accident risks are presented in Table 3-1 (based upon data from Ref 3-1).

Table 3-1

U. S. Accident Death Statistics 1969

Accident	Total Deaths 1969	Probability of Death Per Person Per Year 1969
Motor Vehicle	55,800	3×10^{-4}
Falls	17,800	9×10^{-5}
Fires, Burns	7,500	4×10^{-5}
Drowning	6,200	3×10^{-5}
Poisoning	4,500	2×10^{-5}
Firearms	2,300	1×10^{-5}
Air Travel	1,800	9×10^{-6}
Electrocution	1,150	6×10^{-6}
Lightning	160	8×10^{-7}

It is important to note that the deaths and individual risks of Table 3-1 are based upon historical records of fatal accidents. Moreover, in most instances identified in the table, the accidents or events leading to the tabulated deaths preceded the resulting deaths by

relatively short periods. (Although, direct information on the periods between accidents and resulting deaths is not determinable from the annual statistical tabulations.) The reader is cautioned that the nature and characteristics of reactor risks are sufficiently different from most of the entries in Table 3-1 so that decisions with respect to risk acceptability of reactors should be made with care.

No accidental deaths, attributable to reactors, have occurred in U.S. commercial nuclear power plants. Moreover, as described briefly in Section 1.1, the probability of a major reactor accident -- one in which more than 10 people are killed -- has been calculated to be very small (e.g., of the order of 10^{-5} per reactor-year). Numerical estimates of reactor accident risks, such as those provided by the Reactor Safety Study (RSS) (Ref 3-1), have been based on detailed analyses of failure probabilities for the relevant system components involved in the accident sequences evaluated. Such an analysis attempts to predict the frequency of the occurrence of serious accidents (and their consequences) on the basis of historical data on failure rates for discrete components of the system. Critics of the RSS have pointed out two significant weaknesses (from among a number of others identified): (a) All of the possible failure modes leading to a severe accident for a nuclear power plant (especially those involving human frailties) could not have been included; and (b) construction features of nuclear power plants in general may be substantially different from the two specific (one PWR and one BWR) plant designs evaluated in the study. This latter observation is particularly significant since the two plant designs utilized in the Reactor Safety Study were relatively early versions of large reactors. For this study, which utilized much more recent facility/reactor designs, improvements had already been incorporated to eliminate some potential sources of accidents. Thus a tendency toward lower failure probabilities for critical systems would undoubtedly be associated with the more current designs of facilities, as time went by.

Nevertheless, the weaknesses suggested by the first of the two above factors, and diverse others as well, will lead to the potential for increased failure probabilities for nuclear power plants when compared to the RSS estimates. Predicting frequencies of very low probability events is a very difficult problem. Perhaps the magnitude of the problem is best summarized by a conclusion from the American Physical Society's report on reactor safety:

"....we recognize that the event-tree and fault-tree approach can have merit in highlighting relative strengths and weaknesses of reactor systems, particularly through comparison of different sequences of reactor behavior. However, based on our experience with problems of this nature involving very low probabilities, we do not now have confidence in the presently calculated (RSS) absolute values of the probabilities of the various branches (or events)." (Ref 3-2) (Paranetical notations added by editor.)

An important finding of the RSS was that public health consequences due to reactor accidents were dominated by potentially very severe, but infrequent, accidents. Figure 3-1 presents several estimates for consequence/probability relationships which have been calculated for reactor accidents. The basic figure, including the man-caused events and the two lower curves of reactor accident consequences, has been reproduced from the Reactor Safety Study (Ref 3-1); while the upper curve represents a more pessimistic estimate developed by critics of nuclear power (Ref 3-3). The differences between the estimates represent, in part, the diversity which exists within the technical community with respect to public health effects which might result from reactor accidents. The diversity is caused, for the most part, by the sparseness of experimental information on the biological effects of radiation on humans at low doses and dose rates. However, in spite of the divided opinions, there appears to be general agreement that, under the worst circumstances, tens to hundreds of thousands of casualties could result

Figure 3-1. Frequency of Man-Caused Events Involving Fatalities.
(Annualized Basis for 100 Nuclear Power Plants)*

* (Base figure reproduced from RSS--Ref. 3-1)

from a single very severe accident (a substantial fraction of these would be spread out rather uniformly over a period of about 30 years, or more). The probabilities of such serious accidents have been estimated to be very small. Thus, when they are taken together with the large expected consequences, the product of these two factors yields risks which fall in the range which society has accepted for a number of its other activities. For comparison with the results of Table 3-1, assuming 100 operational reactors in the year 1985, the Reactor Safety Study analysis of the relationships of Figure 3-1 indicates that when risks are taken on an annualized average basis, less than one person per year would die from accidents attributable to the nuclear power plants. The individual risk to all people living in the general vicinity of the plants (projected to be about 15,000,000 people) was estimated to be 2×10^{-10} deaths per year. Even the more pessimistic estimates (Ref 3-3) give societal risks of less than 100 deaths per year from the 100 reactors, or individual risks of about 7×10^{-6} , or about the same relative annual risk as that of accidental death by electrocution. It should be noted however, that the fatality results of Figure 3-1 have all been presented on an annualized basis for purposes of consistency. If expressed in terms of ultimate total fatalities, the latent fatality values for nuclear accidents from Figure 3-1 would have to be increased by about a factor of 30, to account for the delayed distribution of latent deaths over a period of about 30 years. The annualized fatality basis for Figure 3-1 was utilized in order to provide a consistent basis for comparisons with the man-caused events and the early fatality curves of the figure.

It must be noted however, that society seems to be less willing to accept equivalent risks from high consequence -- low probability events, than from low consequence -- but more frequently experienced events. This is admittedly a somewhat simplified observation of a complex phenomenon. However, the observation is sufficiently valid to indicate that psychological elements must be factored into an evaluation

of nuclear risks in order to bring nuclear power plant accidents into perspective with other types of more familiar accidents.

An example of the public's apprehension with respect to high consequence, low probability events can be seen in the experiences with dam and levee failures, which have resulted in a total of about 2900 deaths from eight major events in the period from 1889 to 1972. Known deaths from these eight events have ranged from a high of 2000 to a low of 5. Thus societal risks of about 35 deaths per year, on the average, are implied by the indicated fatalities (with corresponding individual risks of about 2×10^{-5} per year). The current recognition of the potential for high consequence results from dam failures, arising from events such as the 125 deaths associated with the failure of the Buffalo Creek Dam in W. Virginia (in 1972), has resulted in significant public interest in reducing risks from these sources. Moreover, the recent failure of the Teton Dam has led to questions concerning the adequacy of the designs of other dam projects currently under construction. It seems probable that increased attention will be paid in the future to detailed siting investigations and inspection of dams on a regular basis. Thus dam failures provide an example where societal and individual risks were relatively low (about the same level as those of death by poisoning); but public concern over large consequence events has caused an effort to be made to reduce dam failure probabilities and hence, public risks to even lower levels than currently exist.

The preceding example of social response to the risks of dam failure illustrates another significant factor. Even though a given risk may be acceptable when averaged over society at large, occasionally potential risks exist only at specified locations, and may consequently be unacceptably large to a smaller sector of the public. For example, dam failures occur only at dam sites and reactor accidents occur only at reactor locations. While this observation may seem obvious, it suggests another method for risk reduction: prudent siting policy. Thus,

proposals to construct major dams immediately upstream of large population centers may be deemed imprudent in spite of low estimates of the probability for dam failure at the site. A similar comment could apply to reactor siting. Thus, it may be possible to achieve reduced risks, through improvements in safety system reliability, through prudent siting, or by combinations of each approach.

As previously noted, no serious accidents resulting in public health consequences due explicitly to reactor accidents have occurred in nuclear power plants. Thus the historical data for reactor accident-induced-fatalities is so sparse that the issue of public risks could remain debatable for a long time. Moreover, trade-offs between the cost of consequence reduction in nuclear power plants and the perceived benefits of the resulting risk reduction are debated by strongly polarized groups in society. The potential for substantially reducing the public health impacts of severe accidents by underground construction of nuclear power plants will be discussed in this section. However, the issue of whether such reductions in consequences are necessary has not been addressed directly in this document. The issue of "How safe is safe enough?" has not been examined in this report; nor was this issue intended to be resolved by the engineering studies reported herein.

As a result of the manifold problems with evaluation of societal and individual risk of nuclear power plants, posed primarily by the difficulty of determining the probability or frequency of accidents in the facilities, risk evaluation, per se, was not performed in this study. To perform a credible risk analysis, a complete set of accident scenarios must be determined for the concept being investigated -- together with the individual probabilities of the occurrence of each accident in the set and the corresponding set of associated consequences for each accident. Thus if a comparative risk analysis between underground and surface nuclear plants had been attempted, it would have been necessary to have complete sets of accidents, probabilities, and

consequences for both underground and surface plants. The completeness of the accident spectrum for surface plants embodied in the RSS, the most thorough study of the subject currently available, has been the subject of continuing debate, as previously observed.

The design efforts conducted under this study were restricted to conceptual levels by the time and budgetary constraints of the program. Conceptual designs of nuclear power plants do not (by definition and intent) provide sufficient detail to permit determination of a complete set of accidents. Thus conducting a risk analysis for this study was clearly beyond the scope of the project. Instead, the study concentrated on evaluating comparative public health and economic consequences for underground and surface-sited nuclear power plants. To do this, it was necessary to assume that a significant set of accidents could be selected which would be similar in characteristics and credibility for both types of plants; and envelop the range of significant consequences for both types of plants. By making this assumption, the process of accident analysis was reduced to more manageable scope for the study. The effort for accident scenario selection, though significant and extensive, was limited to choosing an enveloping set of accidents which would provide both the design requirements for accident mitigation systems for the facilities and would envelop the significant events for comparative consequence analyses. The details of the accident analysis pertaining to specification of accident mitigation system design requirements are discussed in Section 4.1.

3.2 ACCIDENT DESCRIPTIONS

It must be reemphasized that present day nuclear plant safety systems are designed to prevent the occurrence of Class-9 accidents such as those considered in this study, rather than mitigate the consequences of the occurrence. As noted earlier, Design Basis Accidents considered in the normal licensing process range from those with trivial

consequences (Class-1) through relatively severe events (Class-8). In order to evaluate licensing impacts, the underground plants were designed against the same set of currently specified Design Basis Accidents that are now the basis for licensing evaluation of surface facilities. However, the Accident Mitigation Systems (defined in Section 1.2) which were incorporated into the underground plant conceptual designs have been considered as supplementary safety systems, not as an integral part of the NRC specified Engineered Safety Systems. Thus, the accident control capabilities of the Reference surface plant would be significantly different from those developed for the underground plants of this study; even though it was intended that the licensability of both concepts should be judged against the same set of standards. The underground concepts which evolved during the course of this work were intended to mitigate the consequences of Class-9 accidents and yet to be no more prone to incur such an accident than a conventional surface plant would be. To supplement comparisons of consequences for underground and surface-sited plants, a sensitivity study was conducted of adding a Level-3 Accident Mitigation System to a surface-sited facility. (Details of this design are discussed in Section 4.5. Results of cost estimates are discussed in Section 5 of this report.)

The selection of appropriate design requirements for the Accident Mitigation Systems as well as accident sequences for the comparative evaluation of surface and underground facility consequences was an important part of the CEC program. The NRC Reactor Safety Study (Ref 3-1), examined in detail thousands of hypothetical accident sequences and found 78 which resulted in varying degrees of core melting to dominate the consequence spectrum for the pressurized water reactors (used as the baseline reactor systems for this study). Similarly, 63 dominant boiling water reactor accident sequences were found.

As previously indicated, developing a complete set of accident sequences for underground nuclear power plant risk assessment was beyond

the scope of this study. However, a set of accident sequences was selected to use in determining the effectiveness of underground siting. The sequences were developed by modifying several of the more significant Reactor Safety Study sequences, and synthesizing, and adapting them to envelop the critical parameters for design of the underground accident mitigation systems of this study. The sequences were selected to present limiting design cases for rates of energy delivery to the underground facility systems, peak pressure development within the reactor containment -- in the absence of accident mitigation systems, peak flow rates for mixtures of gases and vapors in mitigation system ductwork, and peak external heat-sink power handling requirements for absorbing the released energy of the reactor decay heat.

For the purpose of calculating accident consequences, the sequences utilized for accident mitigation system design were found to fit within the enveloping description of accident results called PWR-2 in the Reactor Safety Study (RSS) (Ref 3-1). Thus, the collective PWR-2 categorization of surface plant accident scenarios was adopted and slightly modified to fit the enveloping concept described above for the range of severe accidents considered in this study. This severe collective accident category, associated with a large atmospheric release of radioactivity for a surface plant, envelops fifteen of the more significant accident scenarios considered in the RSS. Of the fifteen, the sequence initiated by loss of off-site power, followed by the loss of on-site emergency power and failure of the emergency feedwater system, was computed to have the highest probability of occurrence. This accident sequence (with some modifications) was also selected as one of the more significant potential scenarios for the underground facilities. More details of the selected underground accident scenarios are presented in Section 4.1. Table 3-2 presents a comparison of the PWR-2 accident category of the Reactor Safety Study with the selected categorization of accident fission product release characteristics for this study.

The principal difference between the collective release categorizations for the PWR-2 and CEC underground facility study occur in the sixth group of radionuclides (Ru, Mo, Rh, Tc, Co) where the estimated

Table 3-2

Fission Product Release Characteristics

<u>Radionuclides</u>	<u>Release Fractions</u>	
	<u>PWR-2</u>	<u>CEC Study</u>
1) Xe, Kr	0.9	0.8
2) I	0.7	0.7
2a) Org. I	0.007	0.007
3) Cs, Rb	0.5	0.4
4) Te, Sb	0.3	0.3
5) Ba, Sr	0.06	0.05
6) Ru, Mo, Rh, Tc, Co	0.02	0.4
7) La, Nd, Y, Ce, Pr, Nb, Am, Cm, Pu, Np, Zr	0.004	0.002

releases for the CEC study were a factor of 20 higher than the PWR-2 estimates. A rapid interaction of the core melt with the coolant from the Emergency Core Cooling System (resulting in essentially the same energy release as a steam explosion) was assumed to occur in the underground environment in order to characterize peak rates of energy delivery for the containment structures and accident mitigation systems. The radionuclides in the sixth group are more susceptible to release under these quasi-steam-explosion conditions than they would be under the conditions of the collective category of accident sequences contained in PWR-2 of the Reactor Safety Study.

For comparative purposes, the CEC study used the same collective categorization of release fractions in the analysis of both underground and surface-sited facilities. For analyses of surface accidents, releases were characterized as "puff"-like in duration and predicted to occur at essentially ground-level as a result of an excess-pressurization failure mode for the containment structure. This containment failure mode is the same as the basic PWR-2 failure mode used in the RSS. The time of release from the reactor containment structures of both the surface and underground facilities was prescribed to occur at about 3.5 hrs. This time corresponds to approximately the time when the large energy release from the molten core-coolant interaction was expected to occur. For the underground facilities, the radioisotopes of Table 3-2 were assumed to be released at this time to the rock bed expansion/condensation zone of the Level-2 or 3 Accident Mitigation Systems. Atmospheric releases resulting from the migration of radionuclides through the soil and rock covering the underground facilities were calculated by two-dimensional numerical transport analyses. Results were dependent upon the permeability, porosity, and filtering characteristics of the soils (or other filter media) through which the gases and vapors slowly percolated during their transport process to the surface of the earth.

As will be shown in detail subsequently, underground design concepts were evaluated against this enveloping set of critical parameters and were proved effective. Since the enveloping accident sequences generated extremes of pressure, temperature, and rates of energy delivery, it is presumed, therefore, that underground siting could be shown to be effective for most other specific accident sequences (such as those described in the Reactor Safety Study).

3.3 RELATIVE HEALTH AND ECONOMIC CONSEQUENCES

Based upon the categorized radioactive releases described above, the potential consequences of melt-down accidents of this collective type have been calculated for surface and underground plants. The elements of the calculation include (1) the radioactive inventory available for release to the external environment, (2) atmospheric transport of the radioactive cloud; (3) removal of radioactive particles from the cloud and their resultant deposition upon the ground, (4) for the underground case, transport of radioactive fission products through the overburden, and (5) determination of the related health and economic impacts. Each of these parts contributes to calculational uncertainties associated with the complexity of the phenomena and the paucity of experimental data.

Once the fission product effluent is released to the atmosphere, the resultant radioactive cloud is transported by the wind in a given direction. The XOODOQ computer code was used to calculate the average concentration of radioactive effluent in the air ($\bar{X}/Q$) and the average deposition per unit area of radioactivity on the ground ($\bar{D}/Q$) as a function of distance from the reactor site (Ref 3-4). The code models the effluent released in the cloud as though it were evenly distributed across a 22.5 degree sector downwind from the release point. The model allows for the cloud plume to rise as a function of the release elevation at the reactor site and terrain topography.

To provide for realism in consequence evaluations, four geographical regions were chosen as being representative of potential nuclear plant locations within the State. Three of the sites evaluated were considered to be typical of different portions of California's Central Valley (sites designated hereafter as A, B, and C) and the fourth site (D) was considered to be representative of the South-eastern desert

regions (bordering on Nevada and Arizona). Meteorology and demography typical of these regions were used in the consequence analyses. The meteorological data for the four postulated plant sites were derived from several sources (e.g., Refs. 3-5, 3-6). Meteorological data was also obtained and integrated from proposed and existing nuclear reactor sites in California.

For each of the postulated sites and each of the four seasons, a most probable wind direction was utilized for calculation of the consequences of an accidental release. The concentration of radioactivity in the cloud and the average-deposition on the ground were calculated as weighted averages over six wind speed classes and seven stability categories. In addition, a similar calculation was performed for the case where the winds were blowing in the direction of the maximum population concentration within 50 miles of the designated site. This result was taken to represent a "severe" condition for an accident.

Though the XOQDOQ code is reasonably sophisticated in its mathematical treatment of the consequence analysis problems, it is doubtful that XOQDOQ (or any other currently available computer codes or techniques) can provide reliable estimates of the "true" consequences for an accident (Ref 3-7). If the codes were capable of accepting more realistic meteorological input data, and if the data were available, more reliable results could be produced. For example, the assumption of constant wind conditions extending to distances in excess of 150 miles from the reactor is an obvious weakness in both the analysis methods and availability of data. In addition, rather large variations have been observed in the measured values of deposition velocity of radioactive particles, since these depend sensitively on meteorological conditions and terrain. Because the deposition velocity prescribes how quickly, and thus where, the radioactivity will settle, the value selected for this parameter markedly influences the number of people exposed to protracted doses and the land area subject to evacuation and eventual reclamation.

Both of these factors are major contributors to the total health and cost impacts of a Class-9 accident. However, by restricting the investigation to the differences between the consequences of releases from surface and underground plants, much of the uncertainty resulting from the weaknesses in the available calculational tools has been reduced.

3.3.1 Principal Factors Affecting Radiological Health Effects

Since the basic goal of the study was analysis of the effectiveness of underground siting, and not the determination of absolute values of surface plant accident consequences, several factors which can affect accident consequences were examined parametrically. Four different evacuation models were evaluated and found to have generally insignificant effects on consequences. The effect of assuming various relationships for dose effectiveness factors was evaluated, as well as the change in public health and economic costs for different interdiction criteria. These results are discussed in greater detail below.

The indices selected for quantification of the impact of large releases of radioactive material on the population are shown in Table 3-3. A risk factor, which converts a given radiation dose to a health effect, is associated with each index. These risk factors were assigned after conservative evaluation of the current literature in the field. When, as was sometimes the case, the available experimental evidence seemed too sparse to provide firm support for a position taken by some investigators, a more conservative estimate (larger risk factor) was adopted for this study. It may be noted that as a result, the risk factors appearing in Table 3-3 are the same as, or more conservative than, those appearing in the Reactor Safety Study (Ref 3-1).

3.3.1.1 Latent and Plateau Periods

After reviewing the evidence for a latent period and a plateau period for cancer induction by ionizing radiation, it was judged that the latent periods given in the RSS should be accepted as appropriate criteria for the present study. On the other hand, the plateau periods (taken as 25 or 30 years in the RSS) were judged to be less well founded. For this study, they were extended to the end of normal life expectancy of the irradiated individuals. Adopting this more conservative criterion increased the expected number of cancer deaths for a given radiation dose by a factor of 1.6 over that of the RSS.

Table 3-3

Radioactive Dose Conversions Factors For Health Effect

1.	Early Fatalities (Assuming Supportive Treatment)	Bone Marrow: LD ₅₀ = 430 rem, Lung Dose: LD ₅₀ = 19,000 rem
2.	Early Illnesses	Various
3.	Latent Cancer Deaths	194/10 ⁶ man rem
4.	Latent Thyroid Cancers	134/10 ⁶ man rem
5.	Latent Thyroid Nodules	197/10 ⁶ man rem
6.	Genetic Disorders	132/10 ⁶ man rem
7.	Genetic Spontaneous Abortions	42/10 ⁶ man rem
8.	Prenatal Deaths	LD ₅₀ = 80 rem (1st trimester) LD ₅₀ = 340 (2nd & 3rd trimester)
9.	Temporary Sterility	S ₅₀ = 250 rem (ovaries) S ₅₀ = 80 rem (testes)

3.3.1.2 Dose Rate Effects

In line with this generally conservative approach, it was assumed for this study that the incidence of tumors and other radiation effects was governed by a linear integrated function of total dose to the entire population irradiated, irrespective of the magnitude of the dose to the individual members of the group. (This assumption was also used as a baseline for the RSS consequence calculations.) The evidence for departure from this "linear hypothesis" was considered to be too inconclusive to warrant utilization of any modification to the concept in the baseline for this study. However, there seems to be general agreement within the technical community concerning the existence of dose rate effects. For the examination of these effects, the data of Yuhas (Ref 3-8), and Upton, et al, (Ref 3-9) were used to derive dose rate effectiveness factors (D.R.E.F.) defined as

$$\text{D.R.E.F.} = \frac{\text{tumor incidence at given dose rate}}{\text{tumor incidence at maximum dose rate}}$$

When plotted against dose rate and adjusted for the different susceptibilities of mice and men, the function

$$\text{D.R.E.F.} = 1 - e^{-0.133 (\text{dose rate})}$$

was adopted as the best representation of the dose rate effect. Although dose rate effectiveness factors smaller than 0.1 are implied by this expression, (e.g., D.R.E.F. = 0.1 at less than 0.8 rem/day) the smallest D.R.E.F. used in this study to calculate health effects was 0.2.

3.3.2 Health Effect Results

The results of the calculations for the number of fatalities associated with short and long-term effects from major releases from surface and underground plants are presented in Table 3-4. The results calculated for each of the four sites have been represented as a range of values in the tables. Though the results are presented as a range, they were derived from the discrete calculations for the four sites, each with its own demographic model; and for a variety of meteorological conditions. Thus the results should not be interpreted as a description of calculational uncertainties, but as an indication of limiting results for all cases considered. Two pairs of numbers appear in each space. The pair in parentheses represents the range of "severe" consequences derived by performing calculations with the appropriate wind characteristics applied in the direction of the maximum population concentration in the vicinity of the site at the time of the release. The other values are weighted effects derived by averaging consequences associated with the most probable wind directions in each of the four seasons of the year together with the severe consequence estimates. The consequence numbers result from the application of a linear dose-effect relation (i.e., dose-rate effects were not utilized in the development of the results). The corresponding consequences for the underground facility are shown in the right-hand column of the Table 3-4.

The main contributors to early fatalities (occurring within 60 days) are bone-marrow depletion and lung damage due to inhalation of radionuclides from the passing cloud. Of the radionuclides in the cloud, the largest contributors to these early effects are Ru-103 and Ru-105, Te-132, and I-131, and I-135. In addition, Cs-134, Ce-144, and Mo-99

ne

Table 3-4

Short and Long-Term Fatalities
Weighted and (Severe)* Results

<u>Contributors</u>	<u>Fatality Range</u>	
	<u>Surface Sites</u>	<u>Underground Sites</u>
Early Deaths	17-450	0
	(210-1900)*	(0)*
Latent Cancer Deaths	3900-6300	0
	(4300-7200)*	(1)*

*Exposure of the maximum population density sector within 50 miles of site.

also contribute importantly. The late effects (occurring after latent periods of from 0 to 15 years, and extending over the life expectancy of the irradiated individual) are produced, for the most part, by the whole body dose delivered by radionuclides deposited on the ground and from the (relatively small) external dose from the passing cloud. The ground deposition contribution is dominated by I-131, Ru-103 and Ru-106, and Cs-134 and Cs-137. Inhalation and residence time within the body also contribute to the late effects. The radionuclides most responsible in this instance are Te-132, Ru-103, Ba-140, Sr-89, and Cs-134. Thyroid and gastrointestinal exposures are not expected to contribute additional early fatalities. Supportive medical treatment was assumed to be available for irradiated individuals. The cost of medical treatment was included in this assessment.

In contrast, Table 3-5 presents the calculated results for nonfatal health consequences of the accidents investigated. It must be noted that, by definition, none of the listed effects resulted in

fatalities to the individuals exposed to the radiation. For example, early illnesses are dominated by cases of respiratory impairment (which may result in either regressive or permanent, but not lethal, health impairment depending upon the condition of the lungs before exposure and radiation doses received) and temporary (nonrecurring) discomfort from vomiting. Thyroid nodules may be either benign or malignant. If they were believed to be malignant, they would usually be surgically removed, or treated with therapeutic doses of I-131. In any case, the majority of thyroid cancers would be well-differentiated, relatively slow growing, and relatively amenable to therapy. Consequently, their mortality rate would be much lower than that of other cancers (American Cancer Society, 1974). For this reason, both the thyroid cancers and nodules listed in Table 3-5 represent those which were medically treatable and did not result in fatalities.

Prenatal deaths result from exposure of the fetus to the radiation from the accident. The total number of deaths from this source is small, since: (a) relatively large radioactive doses to the fetus are required to cause its death; and (b) the number of deaths is also proportional to the relative number of pregnancies in the exposed population. Spontaneous abortions are differentiated from prenatal deaths because the abortions occur as a result of irradiation-induced genetic aberrations in fertilized eggs which would result in early death and consequent rejection of developing embryos. These effects have been

Table 3-5
Health Consequences
 Weighted and (Maximum)* Results

<u>Health Effects</u>	<u>Range of Effects</u>	
	<u>Surface Sites</u>	<u>Underground Sites</u>
Early Illnesses	160-7700	0
	(2000-62000)	(0)
Thyroid Cancers	3300-17000	<1-3
	(6300-130,000)	(<1-27)
Thyroid Nodules	4600-17000	<1-5
	(7000-130,000)	(<1-40)
Prenatal Deaths	1-18	0
	(5-130)	(0)
Genetic Disorders	2600-4300	~0
	(2900-4900)	(<1)
Spontaneous Abortions	840-1400	~0
	(920-1600)	(<1)
Temporary Sterility	340-12000	0
	(2000-100,000)	(0)

*Exposure of the maximum population density sector within 50 miles of site.

estimated to occur over periods lasting as long as 20 to 40 years after the accident. Spontaneous abortions are directly related to the genetic disorders, also shown in Table 3-5.

Changes in the body's genetic material are called mutations. Mutations can occur spontaneously, from unknown causes, or can be induced by a variety of physical or chemical agents, one of which is ionizing radiation. The effects of mutations can be very obvious (e.g., albinism) or they can be so slight as to be detectable only by laboratory tests (e.g., protein variants). The health consequences of mutation can range from significant functional and structural abnormalities (generally with appreciable life shortening) to small and trivial effects that are neither disfiguring nor incapacitating. The results presented in Table 3-5 belong to the category of significant disorders.

Ionizing radiation (irrespective of source) received by members of the public increases the frequency of mutations. Living things are continually exposed to natural background irradiation from radioactive elements in the body, the earth's crust, and from cosmic rays. Natural background radiation doses to the U.S. population exceed 20 million man-rem per year (based upon average individual doses of 130 mrem per year). This radiation may account for some fraction of the naturally occurring mutations in man. Radiation received as a result of accidents in nuclear power plants is essentially similar to natural background irradiation. Accident-induced radiation would not, therefore, be expected to induce mutations that produce new kinds of effects. There is no reason to believe that genetic disorders that would arise from such radiation-induced mutations would differ from those that occur naturally.

It should be recognized that the genetic disorders of Table 3-5 are expected to occur over a very long time period. Fully one-half of the total (about 1000 to 2000) would occur after a 140 year period

following the accident (Ref 3-10). Assuming a stable California population of about 20 million and a birth rate of about 14 per 1000 population per year, 39 million births would occur during the 140 year period. Of this number, about 1% (400,000) would be expected to have genetic disorders occurring from natural causes (Ref 3-10). Thus the genetic disorders caused by the postulated reactor accident would represent an increment of less than 0.5 percent to the total natural genetic disorders produced during the same period.

The temporary sterility results presented in Table 3-5 would be dominated by effects in the male population. The temporary disorder would be manifest as a decrease (or absence) of sperm beginning at least 6 to 7 weeks after exposure to the damaging radiation at the levels of Table 3-3, and continuing for a period of from a few months to the order of a year. Recovery would follow; and libido and potency would most likely not be affected during the period. Radiation effects on the female ovary differ from those of the male testes since, unlike the testes, the ovaries develop their entire supply of germ cells (or oocytes) early in life and lack the capacity for replacement of lost cells. Thus radiation damage to the oocytes irreversibly reduces the reproductive potential of the woman exposed to the radiation of the accident. Prolonged or permanent suppression of menstruation would be expected for about 50% of the women exposed to a 250 rem dose (cf, Table 3-3). However, based upon the fatality-dose factors of Table 3-3, few cases of permanent sterility would be expected among female survivors to the postulated accident. Since most individuals conceive children intermittently over a period of generally less than 35 years, it is unlikely that the majority of those experiencing temporary sterility (i.e., damage to only a portion of the oocytes) would be aware of the condition.

For all effects but early deaths and illnesses, the values shown in Tables 3-4 and 3-5 are composed of the sum of two contributions, the

effects of an early, "prompt" (or acute) exposure and a protracted exposure. The former originates from short-term direct irradiation and inhalation of radionuclides from the passing cloud; the latter from long term, whole body irradiation from fall-out which has been deposited upon the surface of the earth. For this study, these two contributions were kept separate until a late stage of the calculations in order to permit consideration of low-dose, threshold, and dose-rate effects on consequence results.

In a parametric study, a dose-rate effectiveness factor of 0.2 was applied to the protracted exposure portion of the consequence calculations in order to evaluate the effects of low dose-rates. Where the protracted exposure was an important contributor, health effects were reduced by factors of 1/2 to 1/5 upon application of the effectiveness factor. For surface facilities, where protracted exposures were particularly significant contributors to latent cancer deaths, the "weighted" estimates of fatalities were reduced by a factor of almost 0.2 by application of the dose-rate effectiveness factors at all sites and "severe" values were reduced by a factor of about 0.3. Similarly, spontaneous abortions and genetic disorders were reduced by almost identical factors of 0.2 for "weighted" results and 0.3 for "severe cases, upon consideration of dose-rate effects. Conversely, thyroid cancers and nodules, prenatal deaths, and temporary sterility cases are almost all the result of acute radiation exposures occurring during passage of the radioactive cloud; hence these categories of health effects were not substantially altered by consideration of dose-rate effects.

Health effects from accidents in underground facilities, if at all detectable, would be the result of protracted exposures, at very low dose rates. This is partially the result of an implicit assumption of the study that the accident mitigation systems functioned effectively under the Class-9 accident conditions for which they were designed. As a

result, no "puff" release of radiation would occur from the underground facility. Only slow filtered seepage of gaseous fission products would be expected from the system under these assumptions. The validity of this assumption will be discussed in more detail in Section 4 of this report. However, it should be noted that, if it were necessary, or desirable, accident mitigation system reliability for the underground plants could be increased (essentially without limit) because of the simple, passive, redundant design of the concepts.

However, assuming successful operation of the accident mitigation systems, application of the parametric dose-rate effectiveness factor (0.2) to results of reactor accidents in underground plants reduced impacts (which were already essentially negligible) to even lower values. All types of illnesses with measurable effects were found to be reduced by about a factor of 1/5, as might be expected.

The underground plant health effects in the right-hand columns of Tables 3-4 and 3-5 are associated with the consequence estimates for the baseline berm-contained (Level-2 Accident Mitigation System) facility. It is apparent, that in comparison to the surface plant results, fatalities and all types of health consequences have been reduced to essentially negligible levels for the underground facilities. Results of the analyses conducted for the CEC project indicate that for Class-9 accidents occurring in the underground plants, the population would only be exposed to the portion of the released noble gases and methyl iodide which could diffuse through the soil to the surface. Radioactive methyl iodide has a more significant health impact than any of the noble gases. Although effects of radioactive decay of methyl iodide were included in the calculations, no chemical interaction with the soil was permitted in the analyses of its fission product transport to the surface. Thus the contribution of methyl iodide has been conservatively estimated. The rock of the mined-cavern concepts was much less permeable than soil; and depths of cover were much larger in the

rock facility designs than in the berm-contained concepts. Consequently, diffusion to the atmosphere of radioisotopes other than noble gases was insignificant for the mined-cavern concepts. Thus, the resulting consequences for the baseline mined-cavern concepts would also be essentially zero. The same negligible consequences would be expected for Level-3 accident mitigation system concepts, (cf, Section 2.3 for design description) for all underground and surface-sited facilities thus equipped. The incorporation of a filter into the Level-3 designs to delay and trap all radionuclides, except for a fraction of the noble gases assured the resultant low-consequence results.

3.3.3 Ground Water Contamination

Radioactive materials could be released into the ground following a Class-9 accident, migrate into ground water systems, and eventually find their way into the biosphere. Once the radioactivity entered the ground water system, the speed with which it traveled to a withdrawal point would depend upon the velocity of the water in the aquifer (a function of the permeability and porosity of the aquifer and its hydraulic gradient) and a retention factor associated with the chemical activity of the radionuclide in the aquifer medium. The transport time to a withdrawal point is given by the distance from the injection point at the site of the accident divided by the travel speed of the radionuclide. Clearly, the time interval between accident and entry into the biosphere is entirely site dependent.

In the absence of site-specific aquifer characteristics, calculations were performed parametrically for the ground water contamination estimates of this study, with water flow velocity ranging from 10^{-3} feet per day to 2 feet per day, and retention factors varying over a factor of 300. From these calculations, radionuclide travel times were derived which ranged from 7 years per mile to 4 million years per mile. By implication, for ground water discharge distances on the order

of a mile or more, migration times would generally be long, compared to the half-lives of most radioisotopes. Except for the longest lived radionuclides, the radioactivity would be well below maximum permitted levels before extraction from the aquifers could take place for wells beyond a one-mile radius. The possible exceptions are Sr-90 and Cs-137. Calculations of the concentrations of these two radionuclides at a discharge point one mile away from a given release point show that, for combinations of high water flow velocity (2 ft/day) and low retention factors, their maximum permissible concentrations could be greatly exceeded in the aquifer. However, under these conditions, it might take from 30 to over 200 years for the Sr-90, or Cs-137 respectively, to travel the one-mile distance. However, for equally credible values of lower aquifer flow velocities and higher radionuclide retention factors for soils, concentrations of these radioisotopes could fall within permissible values. The significant observation from these results is that the migration of long-lived radioactivity is strongly dependent upon site-conditions. These critical siting factors would have to be considered during site selection processes. Aquifer flow rates, in particular, would effect not only ground water considerations, but construction processes as well.

The Level-2 accident mitigation systems for the underground plants of this study utilize the soil outside of the boundaries of the underground structures as an integral part of the radioactivity filtering system for the plant. Consequently, a larger amount of the soluble fission product inventory released in a Class-9 accident would probably find its way into the ground water from an underground facility than might be the case for a similar accident in a surface plant. However, careful attention to site geology in the course of site selection procedures could reduce the prospects of contaminating ground water in the unlikely event of a core melt penetrating the foundation mat of the containment structure. In addition, the range of radionuclide migration rates estimated above shows that time would be available for implementing

remedial actions for an accident in an underground plant to forestall unacceptable contamination of the biosphere, if the need should arise. Some of the remedies which have been proposed include: (a) pumping water out of wells drilled downstream of the site into decontamination facilities, (b) installation of an underground "dam" around the reactor to divert the flow of ground water, and (c) injecting materials into the ground around the reactor site to decrease the permeability and porosity of the ground. It is concluded, therefore, that ground water contamination resulting from a Class-9 accident may be controlled (after-the-fact, if necessary). Thus, ground water contamination does not appear to be a significant potential source of public health consequences for either underground or surface facilities.

3.3.4 Economic Impacts

Estimates of the economic consequences of a Class-9 accident must include the costs associated with the evacuation and relocation of the threatened population, health care for exposed persons, and the interdiction of productive land and property to meet imposed exposure-dose constraints. Constraints on dose limitations to the exposed population were set at relatively low levels for the study, i.e., any area for which the population would receive a dose of more than 25 rem in 30 years was evacuated and agricultural lands within the region were taken out of production (i.e., "interdicted").

Table 3-6 shows the range of total economic costs calculated to result from a Class-9 accident at the four postulated sites. The weighted average totals (determined in the same way that weighted consequences were evaluated) range from 0.34 to 8.6 billion dollars. Estimates for the severe case (in parentheses) range from 0.64 to 35 billion dollars.

The results of the economic analyses, shown in Table 3-6, indicate that the major economic impact resulted from the need to relocate people for extended periods of time as a consequence of this criterion. The next largest economic impact was associated with the cost of taking agricultural land out of production until the radiation levels

Table 3-6
Economic Consequences
 Weighted & (Severe)* Results

<u>Source</u>	<u>Range of Costs</u>	
	<u>Surface Sites</u> (\$Billions)	<u>Underground Sites</u> (\$thousands)
Evacuation & Relocation	0.13 - 7.2 (.23 - 34)	0 (0)
Farmland	.13 - 1.3 (.31 - 1.6)	0 (0)
Medical Treatment	.079 - .12 (0.1 - 0.6)	1 - 16 (1 - 140)
Total	.34 - 8.6 (.64 - 35)	1 - 16 (1 - 140)

*Exposure of the maximum population density sector within 50 miles of site.

from the accident had subsided. However, actual crop and livestock losses were relatively small, contributing less than 1% to the total economic impact of the postulated accidents. The costs of hospitalization and treatment of the radiation victims seldom exceeded half the costs of evacuation and relocation, or removal of agricultural lands from production.

There was practically no change in these values if a dose-rate effectiveness factor of 0.2 was applied with respect to the protracted exposure cases without changing the baseline interdiction criteria. This is because only the costs of health care are affected under these circumstances (the evacuation and land interdiction levels were maintained at 25 rem for 30 years in both cases). However, the health care was a relatively minor part of the total costs (as indicated by Table 3-6). On the other hand, if the evacuation and land interdiction criteria were changed rather substantially (e.g., from permissible radiation dose levels of 25 rem/year to 100 rem/year) total economic costs could be substantially reduced. Some sample cases evaluated indicated total cost reductions by factors averaging about 17% of baseline costs (with a range of cost reductions from 5% to 67% of baseline costs) for the higher permissible dose level case. Cost reductions were achieved at the expense of increased latent cancer deaths. Death increases averaged about 1.7 times baseline values (with a range of 1.6 to 2.3 times baseline values). Estimates of the value of human life were not included in the calculations of total economic costs. It is apparent, however, that economic cost estimates and long-term fatalities are sensitive to the choice of interdiction parameters for accidents in surface-sited facilities.

The right-hand column of Table 3-6 presents the economic consequences of an equivalent Class-9 accident in an underground plant. It shows the comparative costs were trivial in the underground case, and

that neither evacuation of population nor interdiction of lands was required. The medical treatment costs have also been drastically reduced. Note that they are now measured in the thousands of dollars rather than billions. Using a dose-effectiveness factor of 0.2 reduces medical treatment costs by an additional factor of about 1/5.

3.4 SUMMARY

It should be observed that the consequence calculations performed for this study represent state-of-the-art analyses of the effects of severe accidents in nuclear power plants. The complexity of developing numerical models of the physical laws of meteorology and determining adequate models of radiological health effects places truly accurate numerical modeling of reactor accident results beyond the state-of-the-art, at this time. Thus, the available numerical methods are quite idealized; but they are adequate for the state-of-the-art of the input meteorological and health effects data upon which they are based. Therefore, uncertainty in the calculated accident consequence results is a fact-of-life. The site characteristic idealizations which had to be made to conduct the study; the basic numerical models for transport of the radioactive cloud; rates of radioisotope deposition upon the ground; the applicability of the "linear hypothesis" for radiological dose determination vs. the validity of threshold models which suggest that until some minimum dose is received the body is able to counteract the effects of irradiation; the accuracy of estimates of latent and plateau periods for cancer induction following irradiation; all of these issues (and many others unmentioned) make lengthy debates over fine-tuning of any one of the parameters unwarranted. Thus, more confidence can be placed in the relative relationships between the underground and surface plant consequence results than in the absolute values for either one of the analyses.

A corollary observation can be made with respect to accident scenario selection. The conceptual design detail developed in this study was incapable of supporting the development of a complete set of accident scenarios for underground plants. Thus it was inappropriate to attempt to perform a risk analysis for the study for which a complete set of accident scenarios would have been essential. A smaller subset of accidents was developed which provided an envelope of "important" accident

scenarios for both system design and accident consequence analysis. The enveloping approach to accident scenario development was intended to provide a set of accidents which were significant for both underground and surface-sited plants.

Therefore accident probabilities were not specifically evaluated for the underground concepts of this study. However, consequences for the representative categorization of enveloped severe accidents were compared on a relative basis for both surface and underground facilities. Results (cf, Tables 3-4 and 3-5) indicated that the underground facilities have the capacity to reduce consequences by factors of several thousand or more relative to the postulated accident results in surface plants. Economic impacts were similarly reduced for the underground facilities when compared with results of similar reactor accidents in surface nuclear power plants. Thus, it appears that almost irrespective of accident probabilities in the two types of facilities, substantial reductions in risks of reactor accidents could be achieved by underground emplacement. The resolution of the question of whether such reductions in risk are necessary (or, "How safe is safe-enough?") was not within the scope of this study.

REFERENCES

- 3-1. U.S. Nuclear Regulatory Commission, "Reactor Safety Study," WASH-1400 (NUREG-75/014), October 1975.
- 3-2. APS Study Group, "Report to the American Physical Society by the Study Group on Light-Water Reactor Safety," Rev. of Mod. Physics, Vol. 47, Supplement 1, Summer 1975.
- 3-3. Union of Concerned Scientists, "The Risks of Nuclear Power Reactors, A Review of the NRC Reactor Safety Study WASH-1400 (NUREG-75/014)," Cambridge, Mass., August 1977.
- 3-4. J. F. Sagendorf and J. T. Goll, "Program for the Meteorological Evaluation of Routine Effluent Releases at Nuclear Power Stations," USNRC (Draft) 1976.
- 3-5. NOAA, "Climates of the States, Vol. II -- Western States Including Alaska and Hawaii," Water Information Center, Port Washington, New York, 1974.
- 3-6. U.S. Naval Weather Service, "World Wide Airfield Summaries, Vol. VIII, Part 1 -- U.S.A. (West Coast, Western Mountains and Great Basin)," AD688472, NTIS, Springfield, Ca. 1969.
- 3-7. The Aerospace Corporation, "Systems Management Support for ERCDC Study of Undergrounding and Berm Containment," ATR-77(7652-01)-1, Appendix III, August 1977.

- 3-8. J. M. Yuhas, "Recovery from Radiation-Carcenogenic Injury to the Mouse Ovary," Radiation Research, 60, 321, 1974.
- 3-9. A. C. Upton, M. L. Randolph, and J. W. Conklin, "Late Effects of Fast Neutrons and Gamma Rays in Mice as Influenced by the Dose Rate of Irradiation," Radiation Research, 41, 467, 1970.
- 3-10. ARACOR, "Analysis of Public Consequences from Postulated Severe Accident Sequences in Underground Nuclear Power Plants," December 1977, App. D, p. 24.

4.0 TECHNICAL FEASIBILITY OF UNDERGROUND CONCEPTS

Two recurring questions are often posed in connection with underground nuclear power plant concepts. In brief, they are: "Could a facility be built which would be functionally and operationally adequate within the physical and spatial constraints associated with underground construction?"; and, "Could such a facility cope with the problems associated with a postulated severe core-meltdown accident?" This section reviews the principal technological factors associated with the issue of whether an underground plant, which was designed to mitigate an accident it would probably never experience, could also be designed to avoid (a) compromises with plant-safety and (b) complications to maintenance and major and minor repair tasks. The goals and basis for selection of the design criteria and critical parameters of the CEC program are described below. A review is provided of the functional effectiveness of accident mitigation systems in coping with the severe conditions of the postulated Class-9 accidents. Descriptions are presented of the designed capabilities of the facilities in terms of constructability, as well as the long-term stability and durability of underground structures. The relative capabilities of underground facilities are compared to equivalent surface plants in the areas of operations, maintenance, and plant safety. An application of the underground technology for accident mitigation systems to surface plants is also described. The surface plant application is presented in terms of a concept developed in a sensitivity study incorporating a Level-3 Accident Mitigation System (defined in Section 1.2; and described briefly in Section 2.3) into a surface facility.

4.1 BASIS FOR STUDY CRITERIA

The final specifications and criteria for the Architect/Engineer (A/E) design studies are presented in full in Appendix I. A detailed

description of the basis for selection of the preliminary design criteria for the CEC project is presented in The Aerospace Corporation Interim Report which describes the preliminary phase of the CEC program (Ref 4-1). The criteria were developed in preliminary form by The Aerospace Corporation and the CEC staff and reviewed in detail by the A/Es. The final criteria which were adopted for the program were chosen to reflect the greatest possible realism for the design parameters of significance to the project.

4.1.1 Power Plant Characteristics

The baseline reactor (a Westinghouse RESAR 414 of 3800 MW thermal capacity) and plant characteristics (a single, independent, self-contained power producing facility with a net electrical capacity of 1300 MW, utilizing a closed-cycle cooling system with mechanical, evaporative cooling towers, etc.) were selected to reflect the state-of-the-art in standardized reactor design and balance-of-plant design technology. The 3800 MWt units are the largest currently available. They were selected for use in the program because they were representative of the size of reactors being currently considered for use in California; and also because they represent an upper limit for the dimensional capacity of the designs. That is, smaller reactors could be accommodated within the concepts of the study with relative ease.

4.1.2 System/Component Locations

The decisions with respect to locating particular elements of plant systems above or underground were primarily based upon evaluations of individual system radioactivity hazards. Secondary consideration was given to limitations on underground space requirements for the facilities. High priority operational and/or plant safety requirements occasionally required compromises to these basic decision criteria to be made.

Decision making relative to underground structural configurations and equipment locations involved several explicit goals of the study. The first and foremost objective was to produce a plant design which would be capable of utilizing the underground environment to mitigate severe core-meltdown accidents, considering several different accident mitigation systems which were specified in broad general terms (cf, Section 1.2).

The second goal was to provide a design which incorporated the Class-9 accident mitigation capabilities and yet had minimal conflicts with current federal and state licensing requirements for nuclear power plants. That is, existing licensing design-basis requirements were to be followed, as far as reasonably possible, in the underground design. The "Design Basis Accidents" for the facility were to remain as defined in current NRC regulatory standards. Thus, for licensing purposes, Design Basis Accidents were limited to NRC Class-8 events, or less. Under these conditions, the maximum licensing design basis accidents involve only partial core meltdown, although the accident is assumed to release large amounts of radioactivity within the containment structure. During the licensing process, the NRC specified "Engineered Safety Feature" systems of the plant must be shown (generally by design calculations) to be capable of preventing a complete meltdown of the core. Under these circumstances, the NRC's Defense-in-Depth design philosophy holds that releases of the radioactivity from the containment structure to the external environment (and hence to the public) would be expected to be minor.

For the CEC underground nuclear power plant program, the Class-9 accident mitigation systems incorporated into the plant designs were considered to be supplementary safety systems, and thus not directly subject to the NRC regulations for "Engineered Safety Feature" systems. For example, except where the Class-9 accident mitigation systems

interfaced directly with the containment structure itself, they were not considered to be required to be designed to NRC Category I seismic design standards. The NRC standards for Category I systems impose significant requirements for testing, demonstration of capability to meet seismic qualification standards, and inspectability on equipment over the lifetime of the plant. The Category I standards have been developed to ensure that the active ESF systems will function reliably upon demand. Since the demand may result from seismically induced problems in the facility, exceptionally high standards of performance are required for such systems. The simple, passive elements of the Class-9 Accident Mitigation System of this study were designed with great redundancy. Reliable performance would be expected from such systems, with high standards of engineering and common construction practices.

The effectiveness of the standard Engineered Safety Features required by the NRC was not an issue in the CEC underground plant design study. All of the equipment of this type that would be found in a surface plant was also included in the underground plant designs. The CEC study of underground facilities, however, postulated the occurrence of Class-9 accidents, which required an assumed failure of several of the Engineered Safety Features Systems (an improbable event). This was the basis for a third design goal, embracing the philosophy that accident mitigation system concepts which were developed in the program, should be designed to reduce the consequences of the postulated Class-9 accidents without increasing the likelihood of their occurrence.

A fourth goal recommended that plant designers attempt (1) to provide equipment layouts which took operational conditions into account so that plant safety would not be diminished; and (2) to ensure that operations and maintenance procedures were not made more complex or expensive to perform. This objective imposed constraints on equipment spacing, accessibility to and dimensions of aisleways for personnel and equipment movement; as well as constraints on the overall underground

volume of the berm-contained and mined-cavern facilities. It also placed special requirements on ventilation systems, etc. in order to meet the equivalent standards of surface facilities.

All of these goals were considered within the broad objective of cost-consciousness. In order to provide an objective evaluation of the economics of underground nuclear power plants, it was necessary to maintain a constant recognition that superfluous technological features in the designs were not desirable. The ultimate goal was to produce a facility design which could meet the requirements of the goals specified above, and yet was as reasonably low in cost as was possible within the constraints of the time and budget of the CEC program. Thus, although it was beyond the scope of the programs to optimize the underground designs on the basis of economics, designers were always conscious of the need to exercise fiscal restraint in the design processes.

4.1.3 Site Material Property Specification

Siting specifications were selected with the goal of realism and design conservatism in mind. Objectivity in design development was a major goal of the study. Selection of the physical parameters characterizing the site was made with the intent of providing design criteria which neither penalized nor rewarded the development of underground design concepts. The technological feasibility, economics, and constructability of plants are functions of the physical properties of the soil and rock at prospective plant construction sites. Consequently, a substantial effort was made during the preliminary portions of the programs to ensure that the baseline soil and rock specifications were representative of conditions which could be found within the State: and provided realistic physical properties for plant construction (Ref. 4-1). Thus baseline soil and rock models were prepared by idealizing and generalizing results of physical property measurements from actual, but representative, studies of siting

conditions within California (Refs 4-1, 4-2). Under the idealization of the results, the site properties specified are reasonably appropriate for the Central Valley portions of the State, (from which the basic data originated) as well as for the Eastern Mojave Desert regions. Alternative soil and rock models were evaluated as a part of the design efforts of the program in order to assess the range of costs which might be incurred for an associated range of realistic siting conditions.

Seismic criteria were of particular importance to the project. California characteristically has more severe seismic problems for nuclear power plant design than most other parts of the U.S. In order to develop realistic subsurface seismic design criteria, a specific effort was made in the preliminary portion of the CEC program to investigate this problem area (Refs 4-3, 4-4). Free-field seismic motions were evaluated in terms of subsurface soil and rock influence factors for modifications to standard NRC spectral distribution curves for free-field response to earthquakes at the surface of the earth (cf, Section 6.1). A peak earthquake acceleration of 0.5 g at the earth surface of the construction site was specified as a nominal value for baseline seismic design. The 0.5 g peak seismic accelerations at the surface were judged to be reasonably conservative estimates of seismic design requirements for the regions of interest within the State and the design concepts of the CEC study. Sensitivity studies were made of the economic impact of higher (and lower) seismic design requirements.

4.1.4 Containment and Accident Mitigation System Design Requirements

Specific design requirements for containment structures and accident mitigation systems were developed in detail during the course of the final half of the CEC program based on analyses of the fluid dynamic and thermodynamic conditions sustained within the plants during postulated Class-9 accidents (Ref 4-5). The accident-induced design conditions were developed in accordance with two broad technological guidelines described below.

4.1.4.1 The "Pressure-Cooker Effect"

The first guideline was based upon observations that Class-9 accident environments would exceed the pressure-design capacity of surface-plant containment structures (Refs. 4-6, 4-7). Figure 4-1 presents a simplified example of the sequence of events occurring in a severe Class-9 core-meltdown accident initiated by a loss-of-coolant accident (LOCA) from a pipeline rupture in the NSSS. The three principal methods for loss of containment integrity in a surface-sited plant are shown in the figure. Of the three mechanisms indicated, the public risks for surface nuclear power plants are dominated by the containment overpressurization failure mode. Overpressurization failure occurs as a result of release of enormous quantities of energy in a Class-9 accident within the otherwise leak-tight boundary of the containment structure. Some early estimates of containment pressure development as a function of time are shown in Figure 4-2, reproduced from Ref 4-6. Without an engineered system for pressure relief from the containment, the radioactive decay heat of the reactor core would be transferred to the trapped mixture of steam and vaporized fission products until the pressures and temperatures within the containment structure rose beyond the pressure resistant capabilities of the structure. Overpressurization failure is perceived as resulting in a sudden rupturing of the containment structure with a consequent rapid "puff" release of radioactive vapors and gases. The overpressure failure scenario has been referred to as the "pressure-cooker effect" due to the similarity between the effects of the decay heat released within the fixed volume of the containment and the results of overheating an unattended common kitchen pressure cooker.

In an underground facility, a containment structure could be designed to utilize the weight of the overlying soil or rock to resist internal pressures, and thus, to increase the leak-tight design pressure

Figure 4-1. Possible LOCA Sequence with Massive LWR Core Melt

NOTE: TYPICAL SURFACE CONTAINMENTS DESIGNED FOR 50-60 psig

Figure 4-2. Containment Pressure-Time Histories (ECCS Inoperable)

capability of the facility. However, the immense amounts of energy associated with the decay heat of the molten reactor core, together with the pressure-cooker effect, would still be expected to cause overpressure failure of a containment structure which was designed to be leak-tight. Moreover, to maintain the integrity of the containment, the natural pressure resisting ability of the soil and rock would have to be equalled by all the penetrations for pipes and cables, and closures for equipment passageways through the walls of the structure. Unless the penetrations were designed to the equivalent capabilities of the walls, they would remain a weak link for pressure-cooker effects.

Without the aid of the accident mitigation systems prescribed for the study, failure of the underground structure might be delayed for longer periods than those of surface plants (where failure could occur in a manner of hours after the accident). Ultimately, however, overpressure failure -- with a probable puff release to the atmosphere -- would also be an expected failure mode for underground containment structures, unless they were provided with a mechanism for pressure relief. The several release paths associated with containment failure under such conditions in an underground environment are depicted in Figure 4-3. Note, that pressure relief might be achieved by the process of the molten-core of the reactor melting through the concrete foundation mat of the containment structure, if excess overpressure failure of the structure had not already occurred. This process provides a natural, uncontrolled pressure relief system somewhat similar in concept to the engineered accident mitigation systems of this study.

To prevent the occurrence of containment failure via the pressure-cooker effect, accident sequences were selected, and their results evaluated, to serve as a basis for design requirements for the accident mitigation systems and containment buildings of the underground facilities. Sequences were selected with the intent of developing a system which could cope with the Class-9 accident conditions.

ATMOSPHERIC RELEASE AND SUBSEQUENT DISPERSION

Figure 4-3. Principal Radionuclide Transport Mechanisms

4.1.4.2 The Envelope Concept of Accident Sequence Selection

In accordance with a second guideline, accident sequences were selected which enveloped the probable limiting design conditions for the two associated elements of the underground facilities (containment structures and accident mitigation systems). Accident sequences were selected with the goal of establishing a significant set of scenarios which would include the physical extremes of operational conditions for the containment and accident mitigation systems. By this means, it was implicitly assumed that system effectiveness could be shown for other accidents by demonstrating that they fell within the envelope of the selected sequences.

Sequences were selected to establish requirements in two general time domains: (1) short-term, very rapid response requirements (with periods of less than one hour); and (2) intermediate and long-term system requirements for coping with releases of large amounts of energy (at low rates of energy delivery, but over time periods of the order of days, weeks or months). The accident sequences of the NRC "Reactor Safety Study" (Ref 4-8) were analyzed and modified sequences from it were utilized in accordance with the requirements of the enveloping concept.

Portions (and combined elements) of three principal accident scenarios were selected which provided the desired envelope for the time domains and pressure and temperature requirements for design of the two major plant elements. As previously noted, the LOCA provides the Class-8 Design Basis Accident for the pressure design requirements of surface structures. In accordance with the licensing goals set for the underground facility, described in Section 4.1.2 above, the design pressure for the underground containment, and the operational conditions for all the NRC required Engineered Safety Feature systems, were prescribed on the basis of the Design Basis Accident specifications for surface-sited facilities..

4.1.4.3 Loss-of-Coolant Accident Without Effective Core Cooling

Of the several conceivable accident scenarios capable of initiating a Class-9 accident, the LOCA sequence of events is the most widely considered in the literature. The LOCA is depicted in Figure 4-1, and will be described here in some detail to provide background on typical accident processes. The sequence begins with a large, double-ended, "guillotine" break in the primary loop piping of the nuclear reactor steam supply system. Water and steam are expelled from the reactor pressure vessel and depressurization ("blowdown") is complete in a matter of seconds. The resultant loss of the water moderator within the reactor's nuclear core stops the fission chain reaction; but considerable energy remains in the fuel in the form of the decay heat of the radioactive fission products (cf, Table 1-1). As blowdown proceeds, the generated steam and gas pressurize the containment, and the engineered safety features (ESF's), such as the emergency core cooling system (ECCS), are activated. At this point, if the ESF's perform as intended, the accident sequence is stopped and meltdown of the core is prevented. This is termed a "Class-8 accident." On the other hand, in the unlikely event that the ESF's malfunction, the sequence can escalate to a Class-9 accident.

The probable sequence of events occurring during a large LOCA without effective emergency core cooling is shown in Table 4-1. The sequence can be divided into seven periods (Ref 4-9). It should be kept in mind, however, that the following description is uncertain in many respects for the physical processes involved in a LOCA are not thoroughly understood. Thus, at many points in what follows, plausible estimates of prevailing conditions have been given.

Table 4-1*

PROGRESSION OF ACCIDENT INITIATED BY LOSS OF COOLANT
IN UNDERGROUND PLANTS

Time	Event	Comments
0	Primary system pipe rupture, loss of electric power	
0-30 sec	Blowdown	Core power shutdown occurs from scram or core voiding
30 sec-1.0 hr	Core heatup and melting, Zircaloy-water reaction	Hydrogen burns in containment
1.0 - 2.0 hr	Reactor vessel meltthrough	
2.1 - 7.3 hr	Erosion of concrete base mat	
7.3 - indefinite	Interaction between melt and soil/rock beneath the base mat	

*Reproduced from Ref 4-5

Period 1: Blowdown

The double-ended rupture of a large primary system pipe produces the violent expulsion of most of the water in the reactor pressure vessel into the containment where a large fraction of it would be vaporized to steam. This event is termed "blowdown." Three features of the blowdown influence subsequent core behavior. These are the (a) blowdown forces, (b) fuel element cooling during blowdown, and (c) rate of escape from, and the quantity of water remaining in the reactor pressure vessel after blowdown.

Current estimates presume that (a) the blowdown forces will not seriously disrupt the core, (b) the fuel element cooling during blowdown would result in removal of about one-half of the stored thermal energy in the fuel rods, and (c) about 10 percent of the water originally in the reactor vessel would remain after blowdown. At the completion of blowdown, which takes at least 5 to 10 sec for the largest breaks, core temperatures may range from about 600F (320C) to about 1500F (810C) at the hottest section of the core. However, these estimates are quite uncertain, as discussed in the following paragraphs.

Period 2: Core Heatup - Decay Heating Only

Core temperatures begin to rise after blowdown, because of decay heat, at rates of approximately 20F/sec (11C/sec) for PWR's and 12F/sec (6.7C/sec) for BWR's at the hottest portion of the core. If they start from 1500F (920C), local core regions could reach temperatures greater than 2000F (1100C) within 30 to 50 sec. Then an exothermic Zircaloy-steam reaction between the Zircaloy fuel rod material in the steam-filled pressure vessel would begin to become a significant energy source. If substantial damage to the core is to be prevented, it is important that the ECCS operates successfully before this critical

juncture. Delayed application of the ECCS coolant would be considerably less effective in the presence of a substantial Zircaloy-steam reaction; in fact, it could tend to exacerbate the situation.

Period 3: Core Heatup - Decay Heating Plus Chemical Heating

If portions of the core should reach temperatures greater than 2000F (1100C), the Zircaloy-steam reaction would become increasingly significant. The rate of this reaction would initially increase parabolically with time (i.e., doubling the reaction time increases the reaction rate by a factor of 4). As cladding temperatures increase, the pressure vessel may tend to dry out, with a consequent decrease in the reaction rate, as the reaction rate is dependent upon the availability of steam.

22

The time required to reach the melting point of the cladding, 3360F (1850C) at the hottest portion of the reactor in the absence of effective cooling, could be approximately 1 minute. However, the beginning of localized clad melting may not mark the effective beginning of core collapse. Fuel rods would have to reach temperatures greater than 3360F (1850C) before substantial clad dripping or fuel rod slumping could occur.

Period 4: Core Collapse and Collection as a "Heap" in the Reactor Vessel

The time from pipe rupture to the collection of the core as a molten heap in the bottom of the reactor vessel is not known precisely. The calculation is highly dependent upon the model chosen for core meltdown and the process chosen to describe the weakening or melting of the internal core structural grid plate. Two outcomes have been considered. Gradual melting of the fuel could result in the slow deposition of the core in the lower portion of the pressure vessel, while an abrupt failure of a core support grid could result in sudden dumping of a major portion of the molten core to the bottom of the pressure vessel.

A time range from 10 to 60 min from pipe break to collection of the core melt as a heap in the bottom of the pressure vessel appears to cover the uncertainties in the models. The lower limit derives from a heat accumulation consideration. With extensive metal-water reaction (50 percent of cladding) and the assumption that all accumulated decay heat goes into heating the fuel, there is sufficient energy to bring the entire core to the melting point of UO_2 within 10 min.

The actual process of a core collapse and collection in the bottom of the reactor vessel is likely to be a much more complicated matter than the description given above. It involves (a) combination of metals in the melt, with substantially altered melting characteristics from the formation of eutectics; (b) dripping molten flow, and resolidification; (c) blockages of flow, steam production, chemical reactions, and (d) many other effects.

Period 5: Pressure Vessel Meltthrough

The nature of a meltthrough at the bottom of the pressure vessel is somewhat uncertain. As noted above, it is not known whether the fuel would dribble through the grid plate slowly as the fuel melted, or if it would form puddles and melt through suddenly in a series of delayed action falls.

From 50 to 80 percent of the molten fuel might reasonably be expected to fall into the pressure vessel bottom. However, this percentage of the fuel would include that portion of the core having the greatest energy for decay heating.

The first effect of the core materials falling into the vessel bottom would be to evaporate rapidly any water remaining in the vessel. A rapid production of steam might affect the flow of core material

through the grid plate, but steam explosions (resulting from sudden, hyperintensive interactions of water with the molten core) could blow molten core material up and out of the pressure vessel. Steam explosions of sufficient energy could conceivably cause failure of a large section of the pressure vessel head. As indicated in the fourth sketch of Figure 4-1, missiles from steam explosion driven heads have been perceived as potential mechanisms for containment failure, in a surface-sited facility.

However, when the molten core material has collected in the bottom of the pressure vessel, radioactive decay and possibly some further metal-water reactions would result in continued heating of both the fuel and the pressure vessel bottom.

A conservative estimate of the weight of core material plus vessel internals, about 250 tons, would produce forces in the vessel of only a few percent of those due to normal operating pressures; hence, the vessel bottom would not be apt to fail until its melting point were approached.

The equilibrium temperature of the melt is somewhat ill-defined due to the uncertainty in the composition of constituent materials. However, temperatures of the order of 4700 to 4900F (2000 to 2200C) are probable. Under these circumstances, a meltthrough of the pressure vessel could be expected to occur from 20 to 60 min after core collapse (30 to 120 min after pipe rupture), if there were no external cooling for the vessel.

Period 6: Pressure Vessel Meltthrough to Collection of the Core in a Heap at Bottom of the Containment

As indicated, pressure vessel meltthrough might be expected in 30 to 120 min after the pipe rupture. Most of the core, with the melted portion of the vessel bottom, would break through very quickly. A major

uncertainty is associated with the interaction of the molten stream of metal with a water pool, which could be found at the bottom of the containment vessel as a result of ECCS operation during the LOCA.

The molten core material could cause steam explosions if it falls into a water pool. The predictive capability for estimating the probability and effects of steam explosions is very limited (Ref 4-10). About all that can be stated with confidence is that explosions yielding localized pressures on the order of 3000 psi (200 atm) might occur.

The direct damaging effects of localized explosions in the sump area of the containment building are probably minor, because of the size and strength of the structures in the lower regions of these massive structures. The most serious effect of such explosions might be the overall incremental containment pressure associated with the explosions, and the tendency to scatter molten core materials to high sections of the containment walls, where localized structural damage might occur.

Another serious effect of such localized explosions could be the promotion of subdivision of the molten core material with a resultant increase in the overall rate of the reaction of water with the metallic constituents of the molten core material. The resulting increased production of non-condensable hydrogen could be of serious concern, it might lead to containment failure by overpressurization, in spite of successful operation of containment sprays or suppression pools, which are designed to reduce containment pressures by condensation of steam and other condensable fission products.

Period 7: Behavior of Molten Core Mass at the Bottom of the Containment

Upon failure of the pressure vessel bottom, it is estimated that as much as 45 to 75 percent of the core would fall into the containment

vessel and that the self-heating of this material (after a total elapsed time of from 1 to 2 hrs) would be of the order of 0.5 to 0.6 percent of the rated reactor power, or 15 to 20 MW (assuming that about 65 percent of the total decay heat is associated with the molten core materials). (Ref 4-11)

The core material, with the molten vessel material, grid plate, etc., could weigh between 100 and 300 tons depending upon the mechanics of the melting process. If there were no steam explosion, the combined melted material would displace any water into which it fell and commence to heat the concrete, steel, etc., of the foundation base mat of the containment vessel. The rapid boiling of any water into which the molten core fell might scatter the molten core. The precise nature of the molten core and its flow behavior are uncertain, as discussed previously. Whether the core would rapidly spread out into a thin layer, remain more in a heap, or be broadcast by steam explosions is uncertain.

However, if one assumed the collection of the material on the floor as either a thin layer or heap, the concrete would spall and disintegrate as it was heated by the molten core. Since the molten fuel-steel mix is heavier than the concrete ingredients, the concrete residue could either mix with the core or float on the top. Currently preferred models for the core-concrete interaction postulate a turbulent interaction which thoroughly mixes and agitates the combined materials, resulting in expulsion of semi-volatile fission product isotopes from the molten material (Ref. 4-8).

Ordinary dry concrete has a density of about 145 to 155 lb/ft³ (specific gravity of 2.32 to 2.48) and contains about 2 percent by weight of water chemically bound to its molecular structure. Its thermal conductivity is about 1.2 to 1.0 Btu/hr ft F (or 0.005 to 0.008 cal/g C), which is comparable to the thermal conductivity and specific heat of the melt. The concrete virtually disintegrates at about 900F (500C).

The average thickness of concrete in the foundation for the containment vessel is commonly about 10 ft. On the basis of such thicknesses, disintegration of from 100 to 400 tons of concrete might be required for the molten fuel to breach the containment vessel and enter the soil or rock beneath the structure.

It is estimated that the molten core might reach and penetrate the foundation of the containment structure in from 2 to 7 hrs after the beginning of the accident sequence.

If there is no water at the bottom of the containment, or if the water is boiled away from that region and condensed elsewhere, then the dry mass of molten core and concrete would be expected to vaporize at a significant rate. Condensation of vaporized fuel and fission products could occur throughout the volume of the containment.

4.1.4.4 LOCA Underground System Design Requirements

The LOCA sequence described above, represents a bounding case for short term response of the system to rapid increases of pressure. In a LOCA with effective ECCS operation, an almost instantaneous rise in pressure occurs at the instant of the pipe rupture. Pressures in the containment approach the licensing design basis pressures during this rapid pressure increase. To meet standard licensing requirements, the pressure-relief elements of the Class-9 accident mitigation system must be normally-closed, and remain closed under Class-8 accident pressurization conditions. Thus the LOCA represents an important point on the time-pressure envelope for accident mitigation system design requirements.

If the LOCA is compounded with loss of on-site and off-site power to the facility, an accident sequence results which includes the

failure of the following ESF: the loss of long-term heat removal systems; emergency core cooling systems (ECCS); and containment spray systems. The accident scenario, as depicted in Table 4-1, also results in a rapid rise in temperature, extending over long periods of time. Only a small amount of ECCS water would be added within the containment in this scenario. The mitigation systems have to be capable of responding to the increasing pressures and temperatures of this concept. The scenario provided a basis for selection of activation pressures for rupture disks which were connected to tunnels providing access to a large expansion volume for the gases and vapors. The expansion volume was filled with a porous rock bed heat-sink for condensing the steam and vaporized fission products released in the accident.

In the extended LOCA scenario, activation of the rupture disks of the accident mitigation system causes steam to be quickly expelled to the expansion volume/heat-sink zones of the Level 2 or Level-3 systems. After the gases and vapors have been expelled, the containment atmosphere would be left relatively dry at low pressures and at early times. Under these circumstances, as the energy of the core continues to be released as radioactive decay heat, the temperature of the gases and vapors remaining within the structure would rise until equilibrium or structural failure occurred -- whichever occurred first. These high temperatures also represent an important element of the envelope of design requirements. The effectiveness of the system against this potential long-term, high-temperature design requirement will be discussed in more detail in Section 4.2.

4.1.4.5 Transient-Induced Loss of Off-Site and On-Site Power

This accident sequence, the second of the principal scenarios, produced results which appeared to bound energy release rates for system design. The thermodynamic requirements imposed by this accident upon the

facility structures, as described in Table 4-2, produce pressures and temperatures which initially rise relatively slowly (compared with a LOCA). The principal effects of the energy release rates are experienced when core meltdown occurs after about 3 hours. The system components involved in the accident sequence outlined in Table 4-2 are schematically depicted in Figure 4-4. When meltthrough of the pressure vessel occurs, the molten core falls to the floor of the keyway beneath the reactor; the water from the ECCS accumulators is dumped upon it; and a rapid release of energy occurs. Approximately 100 million BTUs (B) of thermal energy are released in a period of the order of 1 minute, an energy release rate of about $5.5 \times 10^9 \text{ B/hr.}$ (equivalent to a sudden pulse of short duration of nearly 2000 MW of thermal power released to the gases and vapors of the containment). This extremely large rate of energy input to the system would induce correspondingly high rates of increasing pressure and temperature for short periods. This scenario appeared to represent the limiting conditions for the rate of energy delivery to the facility systems. Consequently, it was used to establish system design requirements for pressure and mass-flow rates in the ductwork of the accident mitigation systems.

4.1.4.6 Loss-of-Coolant Accident With Diminished ECCS Capacity

The third of the principal accident scenarios included in enveloping the design criteria for accident mitigation systems consisted of a LOCA resulting in a meltdown followed by a partial restoration of ECCS capacity for the plant. In this scenario, a restricted flow of coolant from the ECCS is drawn from the refueling water storage tank by the motor driven pumps of the ECCS and delivered to the molten reactor core. The rate of delivery was approximately equal to the maximum rate for decay heat production of steam. This process would develop the highest pressure at long times in a sealed containment. For a plant equipped with a Level-2 or Level-3 accident mitigation system the scenario would establish the size of the heat-sink (in the expansion volume) needed to reduce the system pressure by condensation.

Table 4-2*

PROGRESSION OF ACCIDENT INITIATED BY LOSS OF ELECTRIC POWER
IN UNDERGROUND PLANTS

Time (hr)	Event	Comment
0	Loss of off-site electric power. Scram occurs.	Failure of on-site power and auxiliary feedwater assumed.
0-1.0	Secondary heatup and boiloff through safety relief valves	Discharge to surface
1-1.2	Primary system heatup to pressurizer relief valve setting	2485 psia
1.25	Pressurizer surge tank rupture disks open, discharge to containment	
1.25-2.2	Primary system boiloff through pressurizer relief valves to containment	
2.2-3.1	Heatup of core with metal-water reaction, core melts through vessel	System remains at 2485 psia until vessel meltthrough
3.1	Accumulator water discharge into molten fuel. Melt freezes and cools	Accumulator water flashes to steam and goes to containment.
3.1-5.1	Core reheats and melts	
5.1-10.4	Erosion of containment base mat	
10.4-Indefinite	Interaction with soil and rock beneath the base mat	

*Reproduced from Ref 4-5

Figure 4-4. Schematic Diagram of Components of PWR Cooling System*

*Reproduced from Ref 4-5

ne

In various combinations, these three accident scenarios were used to establish an envelope of short, intermediate, and long term conditions to size the flow capacity of passageways from the containment to the expansion volume/heat-sink zone; to determine the reaction times for rupture disks, and their appropriate activation temperatures and pressures; and to establish the requirements for heat-sink capacities and expansion volumes, in order to ensure that acceptable pressure limits were achieved in the system. Pressure limits in the expansion volume/heat-sink zone must be limited in order to prevent development of large fissures in the earthen berm or rock overburden. If excessive pressures were developed in the expansion volume, new pressure-venting pathways could be developed for direct release of radioactive gases to the atmosphere (cf, Figure 4-3). Analysis of the accident scenarios also led to evaluation of pressures, temperatures, and energy transferred within the containment which might damage or destroy the integrity of seals for penetrations through the containment structure, or result in structural damage to the containment itself.

4.2 FUNCTIONAL EFFECTIVENESS OF ACCIDENT MITIGATION SYSTEMS

The effectiveness of the Level-1, 2, and 3 accident mitigation systems (defined in Section 1.2 and described in Sections 2.3.2 and 2.4.2) in coping with the effects of severe accident conditions, was investigated by comparing calculated responses of underground and surface plants with and without accident mitigation systems respectively. This section describes the pressures and temperatures occurring within the containment as a result of the accident scenarios investigated for the study. The physical implications for release of radioactivity associated with the results of the postulated extreme accidents are also discussed.

4.2.1 Accident Results for Reference Surface Plants

Pressure and temperature histories are shown in Figures 4-5 and 4-6, respectively, for the Reference surface containment building response to the utility electrical system transient - induced loss-of-electric-power accident described in Section 4.1.4.4, that was used to investigate limiting rates of energy delivery to the system. The characteristic elements of the event, corresponding to those listed in Table 4-2, are noted on the figures. The large pressure spike, at point (4), occurs as the energy is released from the rapid interaction of the ECCS fluid with the core after pressure vessel meltthrough. Containment integrity would be lost from overpressurization during this pressure pulse (peaking at 88 psig) since the induced pressure substantially exceeds the nominal Class-8 design pressure for the structure (60 psig) (Ref 4-5). Even if the containment and penetrations could stand this pressure pulse, it would almost certainly fail after about 10 hours, when predicted pressures in excess of 100 psig would occur. Similar predictions of containment failure for surface facilities under these pressures were made in the RSS, e.g., Ref 4.12.

4.2.2 Pressure and Temperature Response in the Berm-Contained Concept

The effect of an accident mitigation system is shown in Figures 4-7 and 4-8 for the same accident scenario occurring in an underground plant equipped with a Level-3 system, with respect to pressure and temperature response histories respectively. The dramatic decrease in pressure in the containment associated with system activation is evident. The rupture disks would be activated by high pressures associated with reactor pressure vessel meltthrough, which would occur at point (4), about 3.1 hours into the accident sequence.

1. Boiloff of primary inventory through pressurizer relief valves
2. Hydrogen burn from 50% Zr-H₂O
3. Reactor vessel meltthrough, accumulator discharge
4. Core quenched, 50% Zr-H₂O
5. Core remelts
6. Containment base mat meltthrough

*Figure 4-5. Containment Pressure Transient for the Degraded
Loss-of-Electric Power Accident
Site: Surface
Design Level: Reference

*Reproduced from Ref 4-5

THIS PAGE
WAS INTENTIONALLY
LEFT BLANK

1. Boiloff of primary inventory through pressurizer relief valves
2. Hydrogen burn from 50% Zr-H₂O
3. Reactor vessel meltthrough accumulator discharge
4. Core quenched, 50% Zr-H₂O
5. Core remelts
6. Containment base mat meltthrough

*Figure 4-6. Containment Temperature Transient for the Degraded
 Loss-of-Electric Power Accident
 Site: Surface
 Design Level: Reference
 *Reproduced from Ref 4-5

1. Boiloff of primary inventory through pressurizer relief valves
2. Hydrogen burn from 50% Zr-H₂O
3. Reactor vessel meltthrough
4. Core quenched, 50% Zr-H₂O, expansion volume opens
5. Containment and expansion volume depressurized

*Figure 4-7. Containment Pressure Transient for the Degraded
Loss-of-Electric Power Accident
Site: Berm
Design Level: 3

*Reproduced from Ref 4-5

1. Boiloff of primary inventory through pressurizer relief valves
2. Hydrogen burn from 50% Zr-H₂O
3. Reactor vessel meltthrough
4. Core quenched, 50% Zr-H₂O, expansion volume opens
5. Containment and expansion volume depressurized
6. Base mat meltthrough
7. Metal-water reactions complete

*Figure 4-8, Containment Temperature Transient for the Degraded
Loss-of-Electric Power Accident
Site: Berm
Design Level: 3
*Reproduced from Ref 4-5

Temperatures within the containment structure are not dramatically decreased by accident mitigation system activation, however. Though the systems are shown in Figure 4-7 to be quite effective in reducing pressures--as they were designed to be -- the study calculations showed that long-term heat transfer to the external heat-sink became relatively ineffective when the initial blowdown of the containment gases and vapors to the expansion volume/heat-sink zone was completed. After this, heat transfer from the decay heat of the reactor occurred primarily by conduction to the containment equipment and structural elements. The effects of the elements of the containment structure as conductive heat-sinks, together with natural convective heat transfer from the outside of the containment structure, dominate the thermal response of the system after the containment depressurizes (i.e., when the rupture disks are activated). Figure 4-8 shows the thermal history calculated for the containment on the basis of a very conservative model for transferring heat away from the containment structure.

Results of an independent analysis of long-term heat transfer effects conducted at The Aerospace Corporation are shown in Figure 4-9. The figure shows the results of application of a model for heat loss mechanisms for two different parametric rates of dissipation of decay heat from the reactor core into the ground. In the analysis, energy dissipation occurs as the molten core penetrates the foundation of the containment building, and sinks progressively into the earth (and hence out of direct visual and thermal contact with the containment structure). As the core melts its way into the earth beneath the structure, more heat is absorbed by the earth and less is available to heat the structure. In the analysis shown, the heat transmitted to the containment is transferred by conduction into all heat-sinks inside the containment structure: but primarily it is absorbed by conduction in the massive walls of the structure. In the berm-contained concept, the

Figure 4-9. Late-Time Containment Temperature - Berm-Contained Concept

reactor containment structure has been designed as a free-standing, concrete cylinder, which would be completely enclosed within the dome-shaped auxiliary building. Consequently, a nominal rate of free-convective heat transfer was included in the calculation of Figure 4-9 to account for heat carried away from the hot walls of the containment structure to the cooler regions of the auxiliary building, as a result of localized circulation of the air within the domed external auxiliary structure. Compared to the heat capacity of the walls of the containment structure, the auxiliary building provides an enormous heat-sink. Thus, changes in the temperature of the air in the auxiliary building have been assumed to be negligible in the examples shown.

The results indicate that for either of the two parametrically selected decay heat dissipation rates, peak temperatures in the interior of the structure, and at the inside wall surface of the containment structure reach about 700F after periods on the order of one week to 10 days after the accident. It can be shown that the temperature gradient within the walls reverses soon after the peak temperatures are reached. Thereafter, the temperatures in the wall and the atmosphere of the containment are reduced as the convective losses from the exterior of the containment structure exceed the input from the radioactive decay heat additions.

Though the containment structure may survive temperatures of the order of 700F, conventional penetration seals are not designed to tolerate such high temperatures. Consequently, seal breakdown would be expected to occur at temperatures of approximately 400F (Ref 4-5). However, pressure reductions achieved with the Level-2 or Level-3 Accident Mitigation Systems would reduce leakage through the seals into the secondary containment structures (e.g., the underground auxiliary buildings of the berm-contained facilities) to nominal levels. However, if high pressures existed, together with the high temperatures, some leakage to the auxiliary building would occur through this mechanism.

Note that high pressures would only occur if the accident mitigation systems failed to function properly, an unlikely possibility considering the passive design and redundancy of the systems. Figure 4-7 shows that essentially all the driving pressure for leakage is eliminated before temperatures become high enough for concern. In addition, the relative volume of the underground auxiliary structure would limit pressure buildup in the secondary containment to levels where leakage to the external environment would not be expected to exceed current NRC standards for leak-tight reactor containments. Seals in the primary containment could probably be designed to cope with temperatures on the order of 700F. However, development of such high-temperature resistant seal designs was beyond the scope of this study.

4.2.3 Overall Results in Soil and Rock-Sited Facilities

Table 4-3 presents an overview of the calculations of the effectiveness of the major design concepts developed in this program for coping with extreme accidents. For the berm-contained design cases, the most pertinent results for evaluation of accident mitigation system effectiveness are those shown for the Level-3 systems. The Level-2 calculations of Table 4-3 were made on the basis of an assumed impermeable pressure boundary condition at the interface between the expansion volume zone and the overburden soil or rock. Calculations with more realistic pressure boundary conditions in the expansion volume/heat-sink zone were conducted subsequently, by another program participant (Ref 4-13). Under the more realistic boundary permeability and porosity conditions, pressures in the Level-2 berm-contained plant fell to very low levels shortly after depressurization of the containment, i.e., when the rupture disks were activated. Results of the calculations with the more realistic boundary conditions indicate that the effectiveness of Level-2 and Level-3 systems would be expected to be approximately identical.

Table 4-3*
SUMMARY OF ACCIDENT CALCULATIONS

Case No.	Fig. No.	Plant	Design Level	Accident ^a	Maximum Temperature and Pressure in Containment				Time to Attain 400°F Temperature After Base Mat Penetration (hours)
					Before Base Mat Penetration		at 300 hours		
					Temp. (°F)	Press. (psig)	Temp. (°F)	Press. (psig)	
1	4,5	Surface	--	LOEP-AF	390	100	--	--	--
2	2,3	Surface	--	LOCA-EP	400 (at 3.6 hr ^b)	32 (at 3.6 hr ^b)	--	--	--
3	12,13	Berm	1	LOEP-AF	280	100	--	--	--
4	14,15	Berm	2	LOEP-AF	410	91	635	38	65
5	16,17	Berm	3	LOEP-AF	375	91	590	~ 0	95
6	6,7	Berm	1	LOCA-EP	400 (at 3.6 hr ^b)	33 (at 3.6 hr ^b)	--	--	--
7	8,9	Berm	2	LOCA-EP	385	30	605	26	82
8	10,11	Berm	3	LOCA-EP	385	30	595	~ 0	85
9	18,19	Berm	2	LOCA-RWST	280 (at 9 hr)	60 (at 9 hr)	--	--	--
10	26,27	Rock	1	LOEP-AF	380	96	--	--	--
11	28,29	Rock	2	LOEP-AF	380	94	570	84	78
12	30,31	Rock	3	LOEP-AF	380	94	520	~ 0	100
13	20,21	Rock	1	LOCA-EP	400 (at 3.6 hr ^b)	34 (at 3.6 hr ^b)	--	--	--
14	22,23	Rock	2	LOCA-EP	400	34	666	36	72
15	24,25	Rock	3	LOCA-EP	400	34	500	~ 0	115

^a LOEP-AF refers to the postulated loss-of-electric power accident with loss of auxiliary feedwater.
LOCA-EP refers to the postulated loss-of-coolant accident with loss of electrical power.
LOCA-RWST refers to the postulated loss-of-coolant accident with boiloff of water in the refueling water storage tank.

^b Calculation terminated at 3.6 hours.

*Reproduced from Ref 4-5

The Level-2 system expansion volume/heat-sink tunnels of the mined-cavern facility are smaller than the equivalent zone of the berm-contained systems, and the rock overburden is of lower permeability than the soil overburden. Consequently Level-2 system pressures in the mined-caverns would fall more slowly than in the berm-contained cases. Nonetheless, the results shown in Table 4-3 for Level-2 systems in the mined-cavern facilities also represent the limiting cases of an assumed impermeable pressure boundary for the systems. At the 300 hour time shown in the table, the pressures would be expected to be substantially lower than those indicated, if realistic values of rock permeabilities had been used.

In any case, the pressures (even assuming impermeable boundaries at the soil and rock interface with the expansion volume/heat-sink zones) are relatively low -- less than 40 psig for the berm-contained facilities and about 80 psig for the rock-based mined-cavern cases. During the consequence analysis program, it was shown that major new pathways for venting in the soil and rock overburden (cf, Figure 4-3) would not be created as long as the pressure in the expansion volume/heat-sink zones was less than the lithostatic soil load at the expansion zone/overburden interface (Ref 4-13). A reasonable rule of thumb for estimation of the lithostatic load suggests that it increases at the rate of about one psi per lineal foot of overburden depth beneath the earth's surface. Thus lithostatic loads would be about 80 psi (or more) for the berm-contained facility and about 200 psi for the mined-cavern plants. Consequently the pressures in the expansion volume are (under the most conservative possible estimates) far lower than would be required to open up new vent paths for direct, nonfiltered releases of radioactive gases from the underground facilities to the atmosphere--and hence to the public.

4.2.4 Observations on Accident Mitigation System Effectiveness

In general, the accident mitigation systems have been shown to provide a very effective mechanism for limiting the pressures in the containment systems to manageable levels. Assuming successful operation of the system, even the most pessimistic estimates of steady-state pressures indicate that values are within pressure design tolerance limits for surface containment structures. In the rock reactor containment cavern, where the highest long-term pressures were calculated to exist, the pressure-resistant capacity of the cavern structure could substantially exceed the strength of equivalent surface-sited structures, as a result of the support from the rock mass in which the cavern was constructed. Thus the probability of overpressurization failure of underground containment structures appears to have been practically eliminated by the utilization of the accident mitigation systems.

The high-temperature phenomenon observed during this study could present a threat to both seal and structure design. However, if the ultimate long-term temperatures in the containment are limited to values on the order of 700F, or less, structural failure is unlikely. Seals of current design would be expected to lose their integrity at temperatures in excess of 400F. Seals with higher temperature capacities could probably be designed and fabricated without posing substantial technological problems or adding greatly to facility costs. However, it should be reiterated that, though seal failure in the reactor containment structure penetrations is undesirable, it is not catastrophic in an underground facility. That is, since the containment building pressures are reduced to essentially atmospheric levels by successful operation of the accident mitigation systems, fission-product leakage would be negligible, even if seal integrity were lost. If, on the other hand, pressures remained fairly high -- as they might in the baseline mined-cavern concept -- some leakage to the secondary containment

structures (auxiliary caverns, or buildings) could occur. However, low-level leakage into the much larger volumes of these auxiliary underground structures would not be expected to produce high pressures within them. Consequently, limiting fission-product leakage from the secondary containment structures to the external environment to within current NRC criteria for leak-tightness (commonly leakage of no more than 0.1% per day) should be relatively simple to do compared to the problems of ensuring these limits are not exceeded for surface-sited facilities.

Therefore, as a general observation, the analyses of the accident mitigation system designs prepared in the study show them to be capable of performing their intended functions -- i.e., limiting the pressures and temperatures within the containment structure to levels where its uncontrolled, catastrophic failure can be prevented.

22

4.3 FEASIBILITY OF CONSTRUCTION

An important consideration in the evaluation of underground nuclear power plants is the feasibility of construction for the concepts. This section will address the technological problems associated with construction of the two concepts considered in the CEC program: berm-contained, and mined-cavern facilities.

4.3.1 Berm-Contained Structures

The berm-contained concept developed for the underground plant designs of this study uses a large dome-shaped structure of reinforced concrete as a housing for all the subsurface portions of the plant. (cf, Figure 2-5) The domed auxiliary structure functions as a support for the soil covering (berm) which is backfilled over the plant after construction is completed. The large domed structure is the principal feature of the berm design concept. (With an inside diameter of 306 ft, the structure is comparable in size and shape to the Houston Astrodome.)

Another notable feature of the domed structure is its massive wall (16 ft thick at the base). Nevertheless, the dome, while considerably larger in scale than the containment building housing the reactor and other portions of the NSSS, is not expected to require any extraordinarily unusual fabrication techniques, or to present intractable construction problems.

Closure of the dome can be deferred until the construction of the reactor containment building is completed. Construction of the external walls of the domed auxiliary building would be sequenced with placement of backfill and major internal equipment installation in order to minimize the need for underground structural fabrication, which (if required) would further increase the construction schedule. Late closure would also decrease the potential for inconvenient equipment installation processes.

22

As with any major construction project, there are certain minimum technical site requirements which must be met to ensure that facility constructability standards can also be met. For the berm concept, these are primarily associated with the site geology, which must provide an adequate foundation material. The presence of excessive groundwater must also be avoided. Excessive groundwater could complicate construction and subsequent plant operation. Problems of ground water intrusion would be a concern for any type of surface or subsurface construction project. However, the excavation and berm backfill requirements are satisfied by a wide range of soil and rock materials. This feature permits considerable flexibility in site selection for the berm concept. Thus, the problems and additional expenses associated with water intrusion can be limited by selecting sites which do not have excessively high water tables, accompanied by high flow velocities for the subsurface water. Thus, geological requirements for a berm site are not substantially more restrictive than those for conventional surface facilities. Geological requirements would not be expected to significantly restrict siting opportunities.

There are, as will be shown subsequently in Section 6.5, extensive areas within the State which would be technically suitable for berm-contained plant siting. In spite of the very diverse geological characteristics that would probably be found within these areas, locating geologically acceptable sites for berm-contained plants should not be particularly difficult.

4.3.2 Mined-Cavern Structures

The mined-cavern underground concepts use excavations in massive, monolithic rock formations to house the principal plant systems. These caverns, interconnected by access tunnels, are situated about 200 feet below ground level (on the average) in competent rock. Rock qualifies for the designation of "competent" if its mechanical properties and geological characteristics make it capable of sustaining underground excavations without the aid of any direct structural support, except that provided by unmined rock in the form of pillars and sidewalls.

The heights, widths and lengths of the principal caverns required for the baseline PWR and major alternative BWR configurations are listed in Table 4-4, and are shown in the baseline PWR plant layout drawings in Section 2.4 (e.g., Figures 2-8 and 2-9). The required dimensions were determined from detailed equipment layouts. The volume of the caverns, as designed, includes explicit allowances for installation, operation, in-service inspection and maintenance, and replacement of equipment (Ref 4-14).

The NSSS for a PWR can be arranged to fit within a cavern with a maximum span of the order of 100 feet. However, the design for the BWR plant would require spans of the order of 150 feet for the reactor cavern and 120 feet for the turbine/generator cavern. With more time and a

major BWR-NSSS reconfiguration, (primarily involving the suppression pool) a span of about 100 feet might also be possible for a mined-cavern BWR concept. Underground excavations with spans in excess of 100 ft have not been made in sufficient numbers to be considered as state-of-the-art structures. Thus the BWR cavern dimensions pose problems which will be discussed in more detail subsequently.

As indicated in Table 4-4, the required cavern heights range up to 212 feet. As a general rule, structural stability of underground excavations is more dependent on cavern span (the width of the excavation) than on the height or length of the excavation. The arched roof of the cavern poses the central problem of underground excavation

Table 4-4

Nominal Excavated Dimensions of Major Caverns for
Baseline PWR & Alternative BWR Facilities

PWR w/Subsurface Turbine (Baseline Case)

(Total Excavation Volume 1.04×10^6 Cu. Yd)

	<u>Height</u>	<u>Width</u>	<u>Length</u>
Reactor	212 ft.	101 ft.	190 ft.
Turbine-Generator	170 "	91 "	630 "
Auxiliary	186 "	91 "	460 "
Transformer & Diesel	76 "	90 "	420 "
Electrical	80 "	90 "	450 "

BWR w/Subsurface Turbine (Major Alternative)

(Total Excavation Volume 1.13×10^6 Cu. Yd.)

Reactor	206 ft.	148 ft.	233 ft.
Turbine-Generator	176 "	120 "	510 "
Radwaste	110 "	120 "	450 "
Fuel Bldg.	121 "	80 "	160 "
Electrical	60 "	80 "	1080 "

design. Stable roof structures depend primarily upon the quality of the rock of the excavation (about which more will be said later) and the cavern span dimension. Given a stable roof structure, the height and length of the cavern can be extended essentially without limits in good rock, with standard excavation procedures.

The required spacing between adjacent caverns and the minimum required depth of sound rock cover over the cavern roofs depend on both the site geology and the tectonic stress intensity and orientation within the rock mass. For the rock specified in this study, both the minimum spacing between caverns and the minimum rock cover above the caverns were required to be (at least) equal to the largest adjacent cavern span. This design rule is reasonably conservative and based upon underground hydroelectric plant experience for excavation in good quality rock. Tunnels for construction and operational access between caverns range up to 30 feet wide by 50 feet high.

4.3.2.1 The Relationship of Rock Quality to Cavern Constructability

Though rock in a large granite excavation may give the appearance of massive uniformity and solidity, it is actually made up of closely-packed, regularly-shaped, nearly rectangular blocks of varying size. The so-called Rock Quality Designation (RQD) index is used to provide an engineering description of large in situ rock masses. In the RQD system, a rock mass with large, tightly-packed blocks is given higher valued ratings than one with smaller, loosely-packed rocks. The highest quality rating for rock masses in the RQD indexing system is a value of 100. Based upon actual field investigations in Central California (e.g., Ref 4-2) the baseline rock for this study was specified to have an RQD of

97; hence, it must be considered a very fine, high-quality rock. Rock of this quality would be expected to be very closely knit with lineal dimensions of blocks averaging on the order of 1.5 feet on each side.

Though smaller cavern excavations could be made in such high quality material without resorting to any rock reinforcement methods at all, the large excavations of this study must be reinforced with rock bolts and cable tendons. These reinforcements are placed in the rock to "knit" it together and increase the overall strength of the in situ mass of rock. Since each rock block is generally only weakly cemented to its neighbors and is otherwise essentially independent of them, the local strength of the in situ rock system depends primarily on the overall overburden load imposed upon (or local stresses within) the bulk rock mass. The individual strength of intact rock blocks, which may be very high, is largely independent of the in situ strength of the rock mass, which has practically no more strength than any large collection of heavy, but essentially loosely assembled blocks.

Thus, the maximum practical width and height of rock caverns are generally limited more by the size, spacing, regularity and continuity of rock joints than by the individual strength of an intact block of the rock material. At depths of interest (several hundred feet), the in situ compressive stresses in the natural rock mass of the baseline facility site were estimated to be as high as one to two thousand psi. Stress concentrations from excavation processes may increase these stresses locally to the order of 5,000 psi (Ref 4-14). By comparison, the unconfined compressive strengths of intact granite specimen range from 20,000 to 40,000 psi. However, as observed above, the bulk strength of the rock is governed by the in situ stress and not the strength of intact

laboratory specimen. The opening of the cavern, during the excavation process, not only develops compressive stress concentration points, but also causes localized tensile stresses to be developed in the cavern walls. These pose particularly severe problems because where tensile stresses exist, individual blocks are restrained only by local cementation and block-to-block obstructions.

Thus as the excavation proceeds, span limits of underground openings (which have not been stabilized with tendons and bolts) are generally a function of shearing movements which may occur along rock joints or shear zones which may open as the blocks of rock in the walls are loosened locally by the excavation process. The tightness, continuity, and irregularity of the joints and the nature of any infilling materials determine the susceptibility to shearing failure. The design and construction of rock openings in an excavation is, therefore, concerned with limiting movement of blocks and wedges of rock along joint planes through installation of rock bolts and cable tendons.

The upper bound on maximum feasible rock cavern span is likely to be determined more by the spacing between major geologic defects in overall rock mass than by internal defects within an individual block. Natural rock caverns, such as the 600-foot span of the Carlsbad Caverns in New Mexico, provide evidence that, in the absence of major defects, stable rock roofs can be maintained by natural arch action.

Since the mined-cavern structures of this study have been designed for construction in naturally jointed granitic rock masses, their large size requires that they be reinforced with many rock bolts. Because the caverns are designed to house a nuclear power plant, the stability of the cavern design must be demonstrated in a very conservative fashion. Consequently, substantial additional rock reinforcement above nominally calculated values must be provided for the excavated caverns, as discussed below.

Rock bolting is designed to stabilize excavated openings by "knitting" together a zone of rock adjacent to the free surface of the excavation, causing the rock to act as a homogeneous mass rather than as an assemblage of loose blocks. This rock reinforcement is accomplished by introducing bolts or tendons extending through the zone to be reinforced. These rock bolts and/or tendons would be installed and tensioned as the excavation proceeds. By this means, the rock would be placed and kept under compressive loads and shearing resistance across joints would be improved, thus inhibiting the start of shearing movements.

In the baseline design for the reactor cavern, the ceiling is supported by 30 ft long, 1 3/8 inch diameter, rock bolts spaced on a 6 ft x 6 ft rectangular grid; supplemented by 50 ft cable tendons on a 12 ft square grid. Rock bolts would be post-tensioned to 74,000 lbs and cable tendons to 300,000 lbs. The cavern walls would be strengthened by 20 ft rock bolts located on a 6 ft grid. Based upon this rock bolt and cable tendon pattern, a nominal compressive stress of 13 to 15 psi would be imparted to the ceiling and walls of the cavern.

Early installation of additional internal structural support, such as concrete and steel linings, would also be used to confine the smaller, near-surface rock blocks, which might not have been thoroughly "knitted" together by the rock bolting. The use of such supplemental linings enhances the caverns overall stability.

Perhaps as many as 10 representative caverns of the sizes considered in this study (i.e., with spans of approximately 100 feet) have been excavated. Thus spans of this order are generally recognized as being within the "state-of-the-art" for current underground construction practices. Only a few larger openings have been excavated. Experience is, therefore, limited for spans in excess of 100 ft.

Thus the 150 ft span designed for the BWR reactor cavern exceeds the state-of-the-art for construction in granitic rocks, even when the rock mass is of the high quality specified for this study. No recognized theoretical limits exist to application of the art of rock bolt and cable tendon strengthening of the rock mass of the walls and roof of the excavation. However, good practice would indicate that some experimental evidence would be needed to demonstrate the feasibility of such large spans, especially for underground nuclear power plant structures. If serious consideration were given to cavern excavations with spans as large as 150 ft, then a prototype experimental program should be conducted to demonstrate the feasibility of the concept.

In the absence of empirically demonstrated feasibility, the BWR cavern spans must currently be considered to be beyond the state-of-the-art in underground rock cavern construction. As previously noted, it might be possible to redesign the NSSS for a 1300 MW_e BWR to fit within a cavern with a span of the order of 100 ft. However, such a redesign would probably require extensive relicensing programs for elements of the BWR-NSSS. A redesign effort of this magnitude was beyond the scope of the CEC project for investigation of the designs of underground nuclear power plants.

Construction of large spans of the sizes required in this study in lower quality rock than the baseline specifications could require a progressive excavation and construction approach similar to one used for construction of a 100 foot diameter cylinder in volcanic tuff and scoria in Hawaii. In this case, a hemispherical domed roof was first constructed by driving a circular pilot tunnel around the perimeter of the base of the dome. Working from this tunnel, a series of 5 ft thick spherical segments ("orange peel" sections) were excavated upward toward the ultimate apex of the cavern. As the roof was exposed, it was supported with posts using the unexcavated core as a base. By this means, the entire domed roof was opened up without ever exposing the rock

to an unsupported span greater than five feet wide. The excavated shell was then pumped full of concrete to form a structural support for the cavern roof. The balance of the cavern excavation was subsequently finished in complete safety under the protection of the concrete-reinforced dome (Ref 4-15).

4.3.2.2 Cavern and Tunnel Linings

Concrete linings are to be provided for the major caverns of the facility. The linings are primarily intended as a structural support for zones between rock bolt anchors to provide protection against minor rock falls, and also to serve a function in the groundwater control system. The details of the method to be used for cavern lining depend on the analysis of migrating groundwater, initial rock stresses, etc.

For the baseline PWR reactor cavern, a 3 ft thick concrete lining has been designed which is to be emplaced between a welded steel lining and the excavated rock walls. The steel linings would form the interior walls of the caverns as in the SENA plant in France in order to meet the NRC leak-tightness criteria for Class-8 accident design. (cf., Section 6.4) The proposed reactor cavern lining detail is presented in Figures 4-10 and 4-11. The detail shows steel ties which would be supplemented with steel mesh in some areas of highly fractured rock to provide additional support against dislocation of small surface rocks. Relatively simple embedded drains would be placed at the rock-concrete interface to collect groundwater seepage.

Basic control of groundwater migrating within the rock is provided through a system of four relatively small (10 ft x 10 ft) supplemental drainage tunnels and galleries, excavated below and parallel to the principal caverns. These tunnels would be connected at 10 ft intervals to drainage holes extending to the vicinity of the caverns to collect general groundwater seepage through the rock as well as that collected from the vicinity of the caverns.

Figure 4-10. Schematic of Reactor Cavern Lining and Rock Bolt and Tendon Support Patterns

Figure 4-11. Schematic of Details of Reactor Cavern Lining

For the major caverns other than the reactor cavern, the lining approach is slightly different. The major caverns with a span of 75 feet or more would be provided with a concrete roof lining 3 feet thick and the walls would be shotcreted (i.e., coated with a thick covering of mortar blown on the walls under high pressure over a steel mesh liner). The shotcreted wall surfaces would serve as the interior building walls.

Tunnels and minor caverns are all shotcreted or lined with concrete. Only those containing seismic Category I (safety-related) equipment would be provided with rock bolted structural supports and lined with structural concrete as well. Thus, the tunnel which would be used for access to the control room and would contain safety related instrument cables and the piping to the ultimate heat-sink, would be rockbolted for dynamic reinforcement of the walls and roof. In addition, this tunnel roof arch would be constructed with a structurally reinforced concrete lining.

4.3.2.3 Static Cavern Stability

The static stability of the rock caverns is customarily evaluated on the basis of semi-empirical methods for stress analysis of the rock arch of the cavern. Both the natural rock arch action and the strengthening effects of rock bolts and tendons are considered. Due consideration is also taken of in situ bulk rock stresses and stress concentrations resulting from cavern excavation. Finite element analyses of the effects of imposing gravity loads and in situ tectonic stresses on multiple cavern configurations are qualitatively informative. However, such calculations are necessarily inexact, in that they are commonly based on assumptions of perfect elasticity and homogeneity of the rock, and are sensitive to variations in size and direction of the tectonic stresses. Nonetheless, finite element studies are useful in indicating the general pattern of rock mass stresses; although they are otherwise of limited value for conceptual design development purposes.

Correlations between the theoretical analysis and prototype performance for rock caverns have been shown to be inexact. Consequently, final stability evaluation of major underground openings is generally based on field observation and instrumentation measurements to detect incipient structural motion. It has become standard practice in construction of large rock caverns for hydroelectric plants to verify the static integrity of the excavated opening in the rock through such a program of field instrumentation and observation. Before cavern excavation begins, pilot tunnels are constructed above and parallel to the major cavern locations. (These galleries also serve such other purposes as geologic exploration, drainage galleries, and as access for grouting and pre-reinforcement of the rock, if required.) From these tunnels, extensometers and other types of rock mechanics instrumentation are installed in key places in the crown of the cavern in order to observe movements in the rock face as the excavation takes place.

The general experience from other major underground facilities is that the cavern faces stabilize within a few months after the completion of excavation. If observation of the instrumentation indicates continuing movement at any location, additional rock bolts or cable tendons would be installed until an adequate record of stability was established. No mechanical plant equipment would be installed until the entire excavation had been demonstrated to be completely stabilized. The pilot tunnels and field instrumentation remain accessible for continuous inspection, observation and re-verification of cavern stability throughout the operating life of the plant.

The dynamic stability of mined-cavern and berm-contained facilities will be reviewed in Section 6.1.

4.3.3 Observations on the Feasibility of Underground Construction Methods

Conventional construction techniques have been utilized in the designs of both the berm-contained and mined-cavern facilities. Though the basic structures supporting the soil and rock overburden for both facilities are very large, the techniques for construction are sufficiently common to provide high confidence that construction of the domed auxiliary building for the berm-contained plant and baseline PWR mined-caverns are within the state-of-the-art of conventional construction technology.

If cave-ins of the underground structures should occur, they clearly would be formidable problems for either type of facility. The adequacy of the construction of the structures would almost certainly be a subject of detailed examination during licensing processes, if underground concepts were to be carried forward to the facility licensing stage. (Discussed in more detail in Section 6.4.) Though the examination would be intensive, and perhaps require some minor design changes before a construction permit would be awarded, there is no reason to believe that major conceptual changes would be required in the structural designs of either type of underground facility.

No technological restrictions are apparent for construction of the baseline structures for either the berm-contained or mined-cavern facilities.

However, if the 150 ft spans required for the BWR mined-cavern designs were seriously considered, some additional research and development would probably have to be conducted to demonstrate the constructability and long-term stability of such large caverns. Nevertheless, even in this case, there are no theoretical constraints

which are evident to construction of even these large caverns. Though first-of-a-kind mined-cavern BWR facilities would evidently take substantially longer to receive licensing approval than the equivalent PWR facility, there is no apparent reason to believe that BWR plants could not also be constructed. Moreover, no similar dimensional constraints were applicable to utilization of BWRs in berm-contained concepts. No substantial design changes were required to adapt the baseline berm-contained concept to BWR utilization.

4.4 OPERATING, MAINTENANCE, AND OPERATIONAL SAFETY

Skeptics of underground power plant construction have suggested that an increased potential for industrial accidents exists in subsurface facilities which would result in diminished plant availability factors. The allegation has been made that greater postulated confinement within the quarters of the underground plant would compound difficulties with maintenance and operation activities. The alleged potential spatial constraints have also been suggested to be a contributor to increases in consequences for fires, explosions and other similar types of industrial accidents.

Plant operational safety concerns in underground facilities were anticipated at the outset of the CEC program. Therefore, careful attention was given to incorporating generous amounts of space for equipment into facility design layouts so that operations and maintenance would be no more constrained and, if possible, generally less than in a surface-sited facility. Special attention was given to the design and locations of aisles, passageways, corridors and exits and entrances to allow for free flow of personnel and equipment under normal and emergency conditions within the facilities.

There is no obvious reason why spatial constraints must inherently be more severe in underground plants than they are in surface plants. Once inside the enclosed buildings of a surface-sited nuclear power plant, workers have no visual evidence that they are either above or below ground during the plant construction period, or when it is in operation. Careful attention to equipment layout in plant design and quality control during construction are the keys to avoiding complications from spatial constraints in either surface or underground facilities.

Designers in the CEC study made a conscious effort to ensure that the underground facilities had equipment accessibility for inspection, maintenance, and repair purposes that was at least equivalent to the customary spatial provisions for such activities in surface-sited nuclear plants. The A/Es who designed the underground structures have substantial experience in the design and construction of both surface and underground nuclear and non-nuclear facilities. The extensive experience of the A/Es gives credibility to their claim that operations and maintenance activities would be at least as easy to conduct in the underground facilities as these activities would be in a surface plant. Consequently spatial constraints should not increase problems in operations or plant safety for the underground plants of the CEC program designs.

Fire resistant barriers and doors, automatic sprinklers, and carbon-dioxide fire extinguishing systems were included in the underground designs in the same way and according to the same criteria as for a surface-sited facility. Special attention has been given to personnel protection and control of accidents in high hazard areas (those containing flammable fuels, coolants, etc.) to at least the same extent as in a surface plant. The necessity to use the tunnel passage ways as part of the ventilation systems for the underground plants also required

the development of special ventilation system designs that would ensure plant security and personnel safety in the event of an industrial accident such as fire. Physical separation of vital (safety related) equipment is required by the NRC for surface plants. The philosophy of physical separation of vital equipment was rigorously followed in the underground plants of this study. Thus, the consequences for industrial and plant operational accidents involving fire do not appear to be any greater for the underground plant designs of this study than they would be for a well-designed surface facility.

As indicated in Section 4.3, accidents arising from structural failure of the plant such as roof or ceiling collapse of the domed auxiliary building of the berm-contained concept or rock cavern containment structures would be very unlikely. Generally, in surface facilities, major structural failures are guarded against by proper attention to inspection and protection of structural elements as a part of general maintenance procedures. Any unusual signs that suggest weakening of the structure, such as corrosion, or evidence of cracking, etc., would be investigated and corrected before problems became serious. Similar techniques can be extended to the underground plants. Provisions have been included in the underground designs for access, test and inspection space requirements for interior structures. Also, instrumentation of the structure has been provided in the mined-cavern designs that will detect unusual changes in the structural loading, or signs of changes in strains in the walls themselves, and provide early warning of possible hazards in time for corrective action to be taken. Such provisions are relatively easily incorporated into the designs of both of the underground concepts and should essentially eliminate the potential for a possible serious cave-in accident.

4.5 SURFACE PLANT DESIGNS INCORPORATING ACCIDENT MITIGATION SYSTEM CONCEPTS

During the planning phase of the underground nuclear power plant study project, it became evident that certain features being investigated for the underground plant, such as the Level-3 accident mitigation systems, could also be engineered into a surface plant with the potential of providing similar levels of accident consequence mitigation (Ref 4-1). Thus a conceptual design was prepared for a modification of this type to a surface plant, so that an estimate of the incremental plant cost and the potential for reduction of public consequences could be made for comparison with the underground configurations of the study. The sketch shown in Figure 4-12, as prepared by S&L Engineers, illustrates how a Level-3² accident mitigation system might be added to a surface plant. The sketch shows a conventional PWR containment structure enclosing the baseline Westinghouse RESAR 414 NSSS. As in the berm-contained concept, pressure and temperature-sensitive burst disks located in the containment building would connect the building through large pipes to a large, buried, ring-shaped header pipe which in turn would be connected to the pressure relief volume/heat-sink zone. By this means, a controlled vent path has been provided through an engineered filter/heat-sink to the external environment. With the controlled-filtered venting system, only the least harmful of the radioactive gases would be released during the postulated meltdown accident. Releases of radioactivity through this pathway would be essentially the same for the surface Level-3 system as they would be for an underground accident-mitigation system of the same type.

The pressure relief volume, adjacent to the containment building, would be filled with crushed rock and gravel housed within a structural enclosure to provide a heat-sink for condensing both the steam and vaporized fission products produced by the decay heat of the

Figure 4-12. Surface Plant Modification for Level-3 Accident Mitigation Systems

reactor. The entire crushed-rock heat-sink and associated filter beds, would be located below grade. The pressure relief volume would be connected to the external environment through a tall vent stack.

It appears that incorporation of a Level-3 Accident Mitigation System into a surface plant would require only minor changes to the containment and foundation structures of a surface-sited nuclear power plant. The resulting layout of buildings and equipment would not be expected to be meaningfully different from those of the Reference surface plant. No technological problems are apparent for modifying a surface facility with a controlled filtered-venting system of the type proposed here.

It must be noted, however, that the modified surface plant of Figure 4-12 is not entirely equivalent to the underground facilities of this study in safety features. The underground plants provide a secondary containment in addition to the primary reactor containment structure as an additional barrier to possible fission-product releases. In the berm-contained plant (cf, Figure 2-5), the domed auxiliary building provides secondary protection against loss of primary containment integrity. In the mined-cavern concept (cf, Figure 2-6), the remainder of the cavern and tunnel complex provides this secondary support in case leakage of radioactive fission products should occur.

The high temperature conditions associated with long-term thermal response of the coupled reactor containment building and accident mitigation systems (cf, Figures 4-8 and 4-9) suggest that the secondary containments of the underground structures may play an important role in limiting fission product releases to the external environment. If the seals of the primary containment structures should fail under high temperatures, then the secondary containments could provide an important barrier against further leakage of fission products.

In summary, the secondary containment feature provided by the underground facilities is a nontrivial safety feature. The modified surface plant of Figure 4-12, without a secondary containment structure, cannot be considered directly equivalent to the underground facilities of this study. Nevertheless, incorporation of an accident mitigation system into a surface facility can reduce the likelihood of overpressure failure of the reactor containment. Of equal importance, the accident mitigation system would reduce the release of fission products from an associated puff release to essentially only a delayed release of noble gases, insofar as primary containment integrity was maintained. Thus, the modification of surface facilities to incorporate controlled, filtered-venting systems of the type proposed here appears worthy of further consideration and evaluation.

REFERENCES

- 4-1. The Aerospace Corporation, "Systems Management Support for ERCDC Study of Undergrounding and Berm Containment: Interim Report; Preliminary Program Assessment and Follow-on Program Development," ATR-77(7652-01)-1, August 1977, Section 6.
- 4-2. K. O'Brien & Associates, "Siting Concepts and Investigations," Limited Distribution Reports for the Air Force Space & Missile Systems Organization, San Bernardino, California, 1965 to 1967.
- 4-3. The Aerospace Corporation, op cit, Ref 4-1, Section 3.3.
- 4-4. Applied Nucleonics Co., Inc., "Seismic Assessment of Underground and Buried Nuclear Power Plants," Report No. 1226-1, September 1977. (Also published under Aerospace Report No. ATR-78(7652-01)-2).
- 4-5. ARACOR, "Analyses of Public Consequences from Postulated Severe Accident Sequences in Underground Nuclear Power Plants," December 1977, (Sections II and IV).
- 4-6. The Aerospace Corporation, op cit., Ref 4-1, Section 3.1.
- 4-7. Beck, R. L. and Watson, M.B., "Safety Analysis of an Underground Nuclear Power Plant with an Inoperable ECCS," Aerospace Report No. ATR-73(7278)-3, (Draft) March 1973, Unpublished.
- 4-8. USNRC, "Reactor Safety Study," WASH-1400 (NUREG-75/014), October 1975.

- 4-9. W. K. Ergen, et al., "Emergency Core Cooling: Report of the Advisory Task Force Committee on Power Reactor Emergency Cooling," U.S. Atomic Energy Commission, October 1967..
- 4-10. Sandia Laboratories, Albuquerque, New Mexico "Core Meltdown Experimental Review," SAND74-0382, August 1975.
- 4-11. ARACOR, op cit, Ref 4-5, Appendix A, p. 4-21.
- 4-12. USNRC, op cit, Ref 4-8, Main Report, pp. 64, 78, 79.
- 4-13. ARACOR, op cit, Ref 4-5, (Appendix E).
- 4-14. Underground Design Consultants, "Conceptual Design and Estimates Cost of Nuclear Power Plants in Mined Caverns," December 1977, (Section 9).
- 4-15. Ibid, Section 9.2.

5.0 ECONOMIC IMPACTS OF UNDERGROUND CONSTRUCTION

The economic feasibility of underground nuclear power plants was one of the principal areas of investigation of the CEC project. One of the more complex issues requiring careful consideration before responsible cost comparisons can be made, is the requirement for providing a common economic basis for comparison of the designs of surface and underground facilities. The problem is particularly difficult because each of the two power plant concepts is associated with a substantially different level of development toward commercial application. To provide a common basis for making cost comparisons, the decision was made to assume the existence of a "mature industry" as a common level of commercial development for both surface and underground plants. The implications of this assumption will be discussed in more detail below.

Economic optimization of the underground designs of this project was beyond the scope of the program. Nevertheless, considerable effort was made to develop relatively economical design concepts. Prior to development of the final design concepts of the project, a variety of preliminary alternative concepts were considered and evaluated on a semi-quantitative basis relative to economics and technology. For example, alternative berm-contained underground designs were analyzed which were based upon multiple underground structures of several shapes and sizes, housing various elements of the major plant systems. Technical and economic parameters were evaluated for the alternate berm-contained concepts before the final unitary, domed auxiliary structure (completely enclosing the primary reactor containment building) was selected for more detailed design development. Similarly, the multiple cavern layout of the mined-cavern concept was selected over a single linear cavity, primarily for technological reasons. More complete descriptions of the selection processes by which the final design concepts of this project were developed are contained in the individual contractor reports on their respective designs and cost analyses (cf, Refs 1-1 and 1-2).

There are several essential steps in development of a cost estimate for a nuclear power plant; each must be developed with equal precision if the overall estimate is to be accurate. First, the basic construction cost of the plant must be determined, which includes the costs of labor expended, and the purchase costs of construction material and equipment. Second, the indirect costs must also be determined. The indirect costs include, among other things, the cost of engineering, management and licensing. Total construction costs for the facility are given by the sum of the direct and indirect construction costs. To estimate plant grand total costs, the escalation in the prices of labor, materials, and equipment over the period of plant construction, as well as estimates of the allowable interest costs from indebtedness accruing during the construction period must be added to the total construction costs. Escalation and interest costs must be derived from the cash ²² flow requirements of the construction and equipment installation schedule. Thus, calculation of the "grand total project cost" requires not only detailed knowledge of the current cost of materials and labor, and future interest and escalation rates, but of the schedule for construction as well.

Estimates of plant construction costs are generally prepared by Architect/Engineering (A/E) firms on the basis of detailed specifications and drawings. The quality of the cost estimate, i.e., its accuracy in predicting actual costs of construction, is directly dependent upon several factors. Perhaps foremost is the ability and experience of the cost estimators. They of course, depend on complete and accurate plant engineering information. Critical items are the selected value for future escalation and interest rates which are needed for determination of grand total project costs. Since the construction cost estimates to which these predictions will be applied must be extrapolated over long periods into the future (frequently more than 10 years), the selected values of escalation and interest rates can have a very significant

impact on the ultimate costs of the project. Thus the insight of the cost estimator in selecting the proper escalation and interest rates is very important in the development of accurate cost estimates. The values of escalation and interest rates utilized in this study will be discussed subsequently.

Project cost estimates for nuclear power plants have historically been troubled by inaccuracies, even when detailed designs were used as the basis for initial estimates. (Commonly the estimates have been found to be too low.) The experience to date indicates that inaccurate estimates have been attributable to a combination of items such as incomplete engineering descriptions; incorrect and/or incomplete equipment and material lists; inadequate estimates of labor requirements; changes in facility design after project initiation; underestimates of construction time requirements resulting from incorrect scheduling (sometimes due to changes in licensing requirements, labor strikes, or intervenor induced delays); and incorrect assumptions for cost escalation rates and interest rates for borrowing money.

As indicated, the minimization of inaccuracies in cost estimates requires that highly qualified designers and cost estimators be used in their preparation. For this project, A&E design firms with extensive experience as estimators of project costs for both surface and underground facilities were utilized in conducting the CEC program. However, the design detail which could be developed in this study was constrained to conceptual levels by financial and performance period limitations. Nevertheless, the designs prepared in the course of this study are believed to be the most detailed of their kind yet prepared in the United States. This level of design detail, while sufficient in most instances to produce a credible preliminary cost estimate, is, however, only adequate for an initial estimate of costs. For new and complex designs, such as those of an underground nuclear power plant, a considerable degree of uncertainty can be present in the estimates.

Estimates of total plant costs were prepared for both surface and underground plants using, wherever possible, the same equipment designs, sizes, and cost assumptions in each of the estimates. However, it was determined early in the project that the relative change in cost (i.e., differential cost) of underground plants in comparison to surface facilities would be a more accurate representation of the economic impact of underground nuclear power plants than the absolute estimates of the total cost would be. Therefore, the total individual plant costs were developed for the principal purpose of preparing differential cost estimates for the surface and underground plants. The grand total cost figures should not, necessarily, be considered as statements of the absolute cost of nuclear power plant construction. As a result, comparisons of grand total project cost estimates with estimates from other studies are not recommended.

The results of the cost estimating activities, including the definitions of the assumptions and guidelines used in preparation of the estimates of this study, together with plant licensing and construction schedules, are presented in the following sections. It should be noted that results presented in this section represent an extensive abridgement of the original cost data developed by the A/Es in performance of their efforts. The cost data was prepared in accordance with the NRC code of Accounts (cf, Ref 5-1) and analyzed to the 6 and 7 digit level of detailed component breakdowns. The final results have been too voluminous for general distribution. They are available for review at the CEC Library.

5.1 ECONOMIC ASSUMPTIONS AND GUIDELINES

As stated previously, the estimates of required amounts of material, equipment, and construction labor for the nuclear plant designs prepared on this project have been based upon the assumption of a mature

industry, i.e., an industry where a number of plants of commercial status (of both surface and underground type) have been successfully constructed, licensed, and operated. This assumption was adopted in order to put both surface and underground plant cost estimates on a reasonable and equitable common basis and to avoid the extreme number of judgements required for estimates for first-of-a-kind plants. Even though the technology for underground nuclear plant construction appears to be in hand, first-of-a-kind plant cost estimates cannot be prepared without additional detailed design and some indication of regulatory impacts on final plant designs and construction schedules. It is difficult to develop reliable cost scaling relationships for estimation of first-of-a-kind plant costs. Experience and cost data accumulated in nuclear power plant construction for individual plants of current vintage have been evaluated for such relationships. Experience has shown that in many instances, preliminary estimates of the cost of construction for early commercial power plants (for which the nuclear technology was thought to be mature enough to permit reasonable estimates to be made by the commercial utility industry) were found to be inaccurate when the facility was ultimately completed. (In some cases, estimates were low by as much as a factor of two, Ref 5-2.) Other statistical studies of more standardized construction projects have been extrapolated for application to underground nuclear plants. These suggest that total direct construction costs for first-of-a-kind plants may be about 15% higher than would be predicted based upon estimates for a "mature" industry, where at least five plants had been previously constructed (Ref 5-3).

Likewise, the limited number of underground facilities built to date are an insufficient base, by themselves, for development of confirmatory plant cost estimates. Only one underground nuclear plant of commercial status has been constructed and operated to date. It is a mined-cavern design, considerably smaller in size (305 MW) than the current large (1300 MW) nuclear plants of interest to this study. The plant is located in a foreign country (Chooz, France). So far, final

plant construction cost data are not available, so it is not possible to determine precisely the plant's cost relative to a surface facility. However, it is worthwhile observing that the plant is currently operational and appears to have a good operating record in comparison to surface nuclear facilities of similar nuclear design. This, however, is more significant to operational costs of underground facilities, than to construction costs.

In summary, neither confirmatory evidence for the cost estimates prepared, nor absolute cost estimates for prototype plants could be developed in this study. Large variance could occur in actual ultimate grand total project costs for prototype underground plants with respect to the estimates given in this study. Nevertheless, the cost estimates developed are believed to be the most accurate estimates of large-scale underground nuclear power plant costs which have been developed to date. For purposes of estimating costs of underground plants relative to those of equivalent surface-sited facilities, the cost estimates should be wholly adequate to meet the CEC's decision-making needs.

The basic economic assumptions and guidelines used in the preparation of the underground and surface plant cost estimates are summarized in Table 5-1. Fresno, California, area labor rates and efficiency factors were utilized based upon that community's central location in the San Joaquin Valley, an area which was believed to be representative of technically feasible locations for either surface, berm-contained, or mined-cavern nuclear power plants. Other locations, such as the eastern Mojave desert regions of California, were also examined. The desert area labor rates were expected to be somewhat higher (10%) than those assumed for Fresno, and work efficiency was also expected to be somewhat reduced (10%) as a result of the probable remoteness of desert sites. Sensitivity analyses were conducted of these factors in connection with estimates of construction costs at remote sites of this type.

Table 5-1

Basic Cost Estimate Assumptions*

1. Construction labor costs are based on labor rates in the Fresno, California area as of 1 July 1977 including fringe benefits, and work efficiency ratings for workers in similar work areas.
2. Current prices (1 July 1977) were used for equipment and materials. Under these ground rules, cost estimates of major equipment items were used uniformly throughout all cost estimates made for the CEC programs, i.e., NSSS - \$77,827,000;
Turbine-generator - \$62,500,00.
3. Baseline cost estimates were made assuming a standard 40 hour work week of 5-8 hour days.
4. Escalation rates for materials, labor and equipment and indirect expenses were assumed to be 9% compounded annually. Allowances for funds using a simple interest rate of 10% per year and applied to the total estimated construction cost after applying escalation and taxes, if applicable.
5. All baseline cost estimates were made in terms of 1 July 1977 dollars with plant commercial operations to begin on 1 April 1990.

*Parametric analyses of cost impacts were made which varied the basic cost assumptions as follows:

- 1) Remote siting: Labor costs (+10%), reduced labor efficiency (+10%).
- 2) Accelerated construction schedules: Use of premium time factors for labor costs associated with extended work weeks and multiple shifts (as required).
- 3) Variations in commercial operation dates (beyond concept only): Accelerated construction schedule modification (1 October 1989); delayed schedule modification (1 November 1991).

Because the bidding practices normally used by utilities in selecting the vendor for large pieces of equipment often result in small percentage (but significant dollar) variations in the prices of large pieces of equipment, it was decided to adopt a uniform value of NSSS and turbine-generator cost for use by estimators of both underground concepts. The values shown in the Table 5-1 were the prices established for these major equipment items on the basis of current estimates (not firm quotations) from vendors. For purposes of this study, costs for the NSSS of both PWRs and BWRs were assumed to be identical.

As shown in Table 5-1, a 9% escalation rate (compounded annually) and a 10% per year simple interest rate for allowances for funds used during construction (AFDC) were selected for use in this study. As used in the CEC study, the escalation rate was applied to both direct and indirect costs for labor, materials, and equipment. Effects of parametric variations in the escalation rates have been investigated by another contractor, and will be reported in another document.

The escalation rate is related to the general inflation rate associated with the value of goods and commodities in the market place. The construction industry in general, and the nuclear power plant construction industry in particular, have recently experienced inflation rates which are substantially higher than those of the overall consumer price index (which has recently been increasing at an average rate of about 7% per year). The 9% escalation rate (used in producing the estimates for the grand total project costs for both the surface and underground nuclear facilities) is representative of recent, near-term high general inflation rates, as well as the longer term higher average rates for the construction industry. Extrapolation of the 9% escalation rate over the 13 year period between the present and the assumed plant start-up date (1977-1990) had a substantial impact on the grand total project costs, as will be shown and discussed subsequently.

It should be noted, that the 10% annual simple interest rate used for AFDC estimates is close to the maximum rates allowed by the Public Utilities Commission in California for incorporation of incremental construction costs for power plants into the rate base of a utility. The 10% AFDC also reflects current interest rates for utility bond issues.

5.2 COMPARATIVE REFERENCE SURFACE AND BASELINE UNDERGROUND FACILITIES COSTS

Previous estimates of costs of underground nuclear plants have varied over a wide range; from incremental factors above surface plants of less than 10% to factors of almost 2 (cf, Ref 5-3). The majority of these earlier estimates were based on design studies of very limited scope and design detail. Some had different objectives and purposes for constructing the facilities underground than those which were adopted by the CEC study. No previously published studies included provisions in their designs for mitigation of accident conditions for severe core melt (Class-9) accidents. In view of these circumstances, considerable skepticism has existed with respect to the reasonableness of these earlier estimates of the cost of underground nuclear power plant construction. This lack of confidence in earlier cost estimates prompted the extensive effort to develop meaningful cost estimates directly relevant to the State of California.

Accurate estimates of the costs of large complex, and correspondingly expensive projects such as a nuclear power plant require an incredibly large number of considerations. In this study, the selection and preparation of the ingredients of accurate cost estimates were given a great deal of emphasis. This resulted in the preparation of detailed construction schedules, work force requirement tables, labor rates, and accurate identification of requisite engineering materials and equipment.

5.2.1 Cost Analysis of Surface Plants

The cost impacts of underground nuclear plant construction were obtained by comparing the estimated costs of surface plants of similar electrical capacity to those calculated for an underground plant. The total estimated construction cost calculated for the Reference surface plants is shown in Table 5-2 as ranging from \$637/kW to \$708/kW. The range does not represent a probabilistic statement of uncertainty in power plant cost estimates; but is the result of two discrete contractor approaches to plant design and construction.

A major difference in the cost estimates of the two contractors is due to the design approaches used for the Reference surface plants. The UDC facility design is based upon the Gibbs and Hill's GIBBSAR standardized plant design package which was briefly described in Section 2.2. A standardized approach to design would be expected to benefit from minimized contingency requirements and some potential for distribution of engineering costs over several units. Standardized nuclear power plant design packages have received favorable attention among some utilities recently, primarily on the basis of a presumed improvement in licensing processes for such plants.

The S&L Reference surface plant design, on the other hand, is based upon a continuation of design experience from one facility to another, utilizing as much replication of system elements from previous designs as possible. In this concept, attempts are made to minimize costs by carrying over as much direct experience from plant-to-plant as possible. Some utilities may prefer the S&L approach to design because it has the inherent flexibility to incorporate utility design preferences.

The point of the preceding discussion is not to endorse a particular design philosophy, but rather to note that design philosophy can impact estimated costs.

COST ITEM		PLANT COSTS (M\$)				
● Direct Construction		Surface			Subsurface	
NRC Acc. No.	Item	UDC	S&L	Lvl. -3 Mod	Berm	Mined Caverns
20	Land	(a)	(a)	(a)	(a)	(a)
21	Structures	196	193	196	252	182
22	Reactor	150	171	171	173	153
23	Turbine-Generator	133	199	200	207	150
24	Electrical	37	50	50	58	49
25	Miscellaneous	14	20	19	20	19
27	Excavation & Backfill	(c)	2	4	15	75
28	Accident Mitigation	-	-	4	5	3
35	Substation	3	4	4	4	4
91	Construction Services	(d)	8	8	10	(d)
-	Contingency, Total	45	(b)	(b)	(b)	101
Total		578	647	657	744	736
● Indirect		343	181	181	206	432
Total Construction Cost		921	828	842	950	1168
\$/KW		708	637	647	731	898
● Escalation, 9% (Compounded Annually)		1100	1033	1049	1105	1233
● AFDC 10% (Simple Interest)		722	618	632	763	1029
Grand Total Project Cost		2743	2479	2519	2818	3430
Percent Differential		-	-	1.6	13.6	25

- Notes: (a) - Land and transmission costs not included in estimates
 (b) - Contingency cost included as part of individual direct cost item
 (c) - Not specifically known, estimated at about 2 million dollars
 (d) - Included in indirect cost subtotal

Table 5-2. Nuclear Power Plant Cost Comparisons

The "total construction costs" of Table 5-2 do not include the charges for interest and escalation. When these cost items are included, the corresponding grand total surface plant project costs are about 2.5 and 2.7 billion dollars, (about 3 times the total construction costs) for the two independent contractor estimates conducted by UDC and S&L respectively.

Nuclear power plant costs have been independently investigated for the NRC (in 1977) by United Engineers and Constructors (UE&C) (Ref 5-4). UE&C cost estimates were made at approximately the same level of detail as those of this study. They estimated the construction cost of an 1100 MW PWR plant at \$499/kW in June 1976 prices. This estimate can be shown to be within approximately 10% of the construction cost estimates for this project when adjusted for plant size and extrapolated to 1977 dollars using the escalation rate of this study. However, the UE&C cost estimates were not based upon the high seismic design criteria specified for this study (0.25g vs. 0.5g). Extrapolating results to account for this design difference would bring cost estimates into closer correlation.

5.2.2 Cost Analysis of Underground Facilities

The estimated total construction cost of the baseline berm-contained plant is \$731/kW, and \$898/kW for the mined-cavern plant, as shown in Table 5-2. When escalation and AFDC have been included, the percentage cost increases over the Reference surface plant estimates are approximately 14% for the berm-contained plant and 25% for the mined-cavern plant.

5.2.2.1 Baseline Berm-contained Plant Cost Factors

The cost estimate summaries of Table 5-2 present the breakdown of the principal elements of the construction costs for the Reference and Baseline underground plants (a similar estimate for a modified Level 3 surface plant is also included -- and will be discussed subsequently). Cost increases of subsurface over surface construction are evident for nearly all itemized accounts with the greatest dollar increases occurring in the Structures category (Acct. 21). For berm-contained plants, the cost increase in Acct. 21, the Structures line item, is 31% above the equivalent line item for a surface structure, and represents 61% of the overall subsurface cost increases.

More detailed analyses of the berm-contained plant cost estimates indicate that the Acct. 21 cost increase is dominated by the labor and material requirements for the concrete and steel work of the massive domed auxiliary building structure of the berm-contained concept. This item alone represents a cost increment of over \$37 million or about 62% of the total cost increase for the Structures line item (Acct. 21). It can also be shown that cost increases for the reactor containment building and the turbine-generator building represent about 22% and 12% of the total increase in Acct. 21, respectively. Incremental costs for the increased requirements for heating, ventilating, and air conditioning in the underground structures represent an additional increment of about 4% (\$2.1 million) of the total increase in Acct. 21.

Of the total \$97 million increase in direct construction costs for the baseline berm-contained facility over the Reference surface plant, the data of Table 5-2 indicates that excavation and backfill costs represent an increment of about 15%. Similarly, the direct costs attributable to incorporation of the Level-2 accident mitigation system represent about 5% of the increase in the cost of the underground plant

over the cost of the surface facility. Thus the incremental cost of providing the massive domed structure, required primarily to support the static load of the berm backfill, is the dominant factor in the direct cost increment (about 38%) for the berm-contained facility. The costs of the accident mitigation systems are a relatively small component of the basic cost of berm-contained plants.

5.2.2.2 Baseline Mined-Cavern Plant Cost Factors

For the mined-cavern plants, the structural costs of Acct. 21 can be reduced by about 7% below those of surface plants. However, if the additional costs of tunnel and cavern excavation were included in the Structures category, the resulting composite of subsurface structural costs would be increased by about 31% above those for a surface plant. Tunnel and cavern excavation costs represent about 47% of the increase in the direct cost of mined-cavern facility construction, as compared to the equivalent direct costs of the Reference surface facility.

However uncertainties in the estimates of the underground facility costs, as reflected in the Contingency line item, represent a substantial fraction (about 64%) of the increment in total direct costs for the mined-cavern facility. If the contingencies were spread back against individual line items in the direct costs, about 15% would be charged against the excavation and backfill accounts; about 37% against uncertainties in the overall cost of direct labor for construction of the facility; with the remainder (48%) charged against overall uncertainties in the direct costs of materials and equipment.

Costs for the addition of the accident mitigation system for the subsurface plant represent about 2% of the total incremental direct cost for the facility.

5.2.2.3 Accident Mitigation System Cost Increments

A 60% difference exists between the berm-contained and mined-cavern accident mitigation system designs (\$5 Million vs. \$3 Million, respectively), with the berm-contained concept having the higher cost. For this account item most of the additional cost for the mined-cavern design is in the expense of mining the expansion volume/heat-sink chambers; whereas in the berm-contained design most of the additional expense is in ducts, and piping required between the reactor containment building and the external heat-sink/expansion volume. The excavation for the berm-contained concept domed auxiliary building is large enough to accommodate the heat-sink/expansion volume with no additional earth moving required.

5.2.3 Explanation of Differences in Line-item Costs of Baseline Plants

With the exception of Acct. 27, excavation and backfill, and the contingency line item, the individual item-by-item cost of the berm-contained design is observed to be higher than the rock cavern design. Item 23, the turbine generator account will serve as focus for further evaluation of this interesting relationship. A \$57 million difference (\$207 vs. \$150 million) exists in the cost estimate for Acct. 23 between the berm-contained and mined-cavern designs. In view of the similarity of the equipment for the two designs, it might be expected that there would be a smaller difference in the cost estimates developed for this account. (Note that the major cost differences would be associated with the facilities and not with the equipment items. Facility cost differences would be expected to appear in the Structural design account (Acct. 21). The Turbine-generator account (Acct. 23) is heavily hardware oriented.)

Most of the differences between the cost estimates for this account are the result of the different methods utilized by the two contractors in analyzing the performance of the line-item tasks in terms of their respective views of construction management. With respect to construction management, S&L categorizes their role as supervisory; while the other engineering firm, G&H, viewed themselves in the broader role of constructor. In the construction supervisory role, the S&L management team would plan on subcontracting all phases of the program. Consequently their direct construction line item costs are based upon estimates of the subcontracted cost of labor and materials for each element of the line-item tasks. As a result, the individual line items include estimates of the subcontractor's charges for labor, materials, an estimate of his overhead, and subcontract fees. On the other hand, the UDC cost estimates reflect a constructor's view of direct hiring of their own labor (from union hiring halls), and direct purchase of their own materials. Thus, at the account level of individual direct construction cost line items the UDC cost estimates do not include overhead and fees on either labor or materials. In the UDC estimates, overhead and fee appear as indirect charges, and are therefore itemized below the total direct construction cost line. The difference between the two contractor's indirect cost estimates of \$226 million (\$432-\$206 million) may be assumed to be largely a reflection of the contractor differences in approaches to construction management. If the difference in indirect costs were distributed in an appropriate fashion among the several UDC accounts, the differences between individual line item accounts for the two underground concepts would be significantly decreased.

Also, as previously noted, the itemized estimates of direct costs for the berm-contained design include contingency costs as integral elements of the individual line item costs. However, in the mined-cavern cost estimates, contingency costs have been broken out as a separate line item to be added to the total direct cost. If, as discussed above, the

contingency cost for the mined-cavern design were distributed among the individual item accounts, (or conversely, if the berm-contained contingency estimates had been segregated) the accounts would be more comparable.

Some additional direct cost line item differences are attributable to variations in accounting procedures. For example, the cost of the turbine pedestal (about \$4 million) has been included in Acct. 23 in the UDC cost estimate; while the same item, with approximately the same costs, has been placed in Acct. 21 in the S&L cost estimate. This is typical of a number of similar accounting practice differences between the two contractors, which contribute to the overall differentials in line-item costs; and prohibit direct, quantitative comparison of the cost estimates on a line-by-line basis.

It is significant to note that it is impractical to make quantitative discriminations in plant costs at the individual line-item level of the 2-digit NRC cost accounting data shown in Table 5-2. More important comparisons can be made at the total construction cost, and grand total project cost levels. Only at these levels will the differences in construction management approaches and cost accounting procedures be reasonably well integrated for the two facility cost estimates. The more detailed 2-digit line-item accounting breakdown is most useful in establishing qualitative relationships for the relative significance of individual contributions within the overall costs of each facility.

It should be reiterated that actual cost estimates performed for this study were conducted at much more detailed levels than the 2-digit accounting format shown in Table 5-2. Costs of labor and materials were estimated at the level of individual hardware items or construction tasks. The detailed cost estimates represent volumes of hundreds of pages each. They are available for review at the CEC offices as appendices to References 1-1, and 1-2.

5.3 IMPACT OF CONSTRUCTION SCHEDULING ON FACILITY COSTS

A surface nuclear power plant takes about 10 years to complete from the time a utility makes the decision to build, until the plant is ready for commercial operation. Abridged versions of the Reference surface plant licensing and construction schedules developed in this study are shown in Figure 5-1 (Refs 1-1, 1-2).

5.3.1 Construction Schedules

The schedules for construction of the 1300 MW (electric) Reference surface nuclear plants were prepared independently by the S&L and UDC design teams to be used as a basis for comparisons with underground plant construction schedules. The surface plant schedules produced by these two teams differ somewhat in overall length (16 months) because of differences in licensing time assumptions and estimates of containment and reactor vessel support structure construction times.

About one-half (nearly 5 years) of the total construction time for the S&L surface-sited plant is consumed in the plant licensing approval cycle, about 6 years is required for actual construction and 6 months for fuel loading and power testing. The licensing time assumed by S&L reflects a typical licensing time period for a modified version of an existing plan (other than a standardized plant design). The assumed licensing time requirements of the UDC team are substantially shorter than those of S&L and reflect a schedule appropriate for an NRC approved standardized plant design (the UDC estimate is based upon utilization of the Gibbs & Hill, Inc. standardized GIBBSAR design).

The differences in the S&L and UDC surface plant construction schedule lengths represent objective attempts on the part of both designers to estimate surface plant construction time requirements for a

mature nuclear industry based upon two somewhat dissimilar (but not uncommon) approaches to surface plant design and construction.

5.3.1.1 Reasons for Schedule Increases for Underground Construction

Schedules for both of the underground subsurface plant designs are also included in Figure 5-1. It is apparent that overall schedules for subsurface plant completion are substantially longer than surface plant schedules (by about 19 and 22 months for mined-cavern and berm-contained nuclear plants respectively).

The increased time for construction of the berm-contained design is largely the result of extensive soil excavation requirements for the domed auxiliary structure and the time needed for subsequent replacement of the soil over the structures. The berm-contained plant schedule is also lengthened by labor productivity losses associated with the limited accessibility, additional time required for equipment and material handling, and associated complications and delays in equipment installation processes caused by the closure of the dome and subsequent construction; together with the additional work requirements for construction of the dome; and finally, the assumed time losses associated with the hazards of constructing structures in large, deep excavations.

In the mined-cavern design, excavation, rock bolting and fabrication of the lining of the caverns for the several major plant systems are the principle contributors to schedule increases. However, other factors also contribute to schedule lengthening, including the reduced accessibility of the underground caverns of the plant for equipment and structural material installation; some restrictions in construction work spaces; and longer, more restricted, hauling routes and difficult handling requirements for transporting equipment from material storage areas to work areas.

5.3.1.2 The Impact of Reactor Pressure Vessel Placement

A key milestone in the construction schedule of a nuclear power plant is the placement of the reactor pressure vessel (RPV). Placement of the RPV signifies essential completion of the major structural work on the reactor containment building. Subsequent to RPV placement, the construction work emphasis shifts from structural work (concrete, rebar and steel emplacement) to equipment installation and hookup (piping, conduits and cables). After the RPV is in place, the large construction openings needed for passage of the RPV and the steam generators into the reactor containment building can be closed, isolating the reactor systems from the external environment. Controlled environmental conditions can then be maintained within the structure that will be favorable for the completion of sensitive piping, equipment, and electrical and control circuit installations. For that reason, most contractors would prefer an early date for RPV placement.

However the convenience of favorable working conditions for equipment installation and hookup must be traded off against the economic disbenefits of early purchase and delivery of the NSSS. As indicated qualitatively by Acct. 22, the reactor represents a substantial portion (approximately 26% for surface plants) of the direct costs of the facility. Although the NSSS alone represents only one portion of the total Acct. 22 cost, it is the major contributor (about one-half) to this line-item. Since essentially all costs must be paid to the NSSS manufacturer before delivery, utility managers and economists would prefer to defer acceptance of this major capital equipment item as long as possible to minimize interest charges for indebtedness on the purchased equipment. Thus, an important economic trade-off exists between early or deferred purchase and installation of this equipment, as well as the other major capital equipment items in the facility.

For the mined-cavern design, the underground tunnels and caverns provide considerable protection from the external environment and an early closure of the reactor cavity is not as important as it is for surface and berm-contained plants. The rock cavern schedule reflects this feature by delaying the RPV installation as long as possible.

In the berm-contained design, the RPV is installed within the reactor containment before the walls and dome of the auxiliary building are completed. Of course, final backfill of the soil covering for the berm-contained design cannot be completed until the domed structure is finished. Thus, RPV installation for the berm-contained plant cannot be deferred for as long a time, as shown in the schedule, as it can be in the Reference surface plant (or the mined-cavern facility).

5.3.2 Cash Flow Requirements During Plant Construction

While a nuclear plant is in the planning and construction phase, money is spent to pay for the various services, equipment and construction activities as the costs are incurred. The rate of expenditure of money is, of course, dependent upon the level of manpower effort, together with the amount and type of equipment and materials involved in the plant construction at any given time. These factors vary significantly throughout the construction period of the project. The fund expenditure rate for a nuclear plant typically begins low; reaches a maximum about midway in the schedule; and then gradually tapers off toward completion of the facility. When the expenditure rate is integrated over time, the result is the classical "S"-shaped cumulative cash flow curve. The specific shape and magnitude of the cash flow curve are dependent upon several factors, including: the labor and capital elements of the Total Construction Cost for the facility; the construction schedule; and the values assumed for interest and escalation rates. To permit comparison between the several above and below ground

designs the cash flow curves for construction of each of the principal facilities of this study are shown in Figures 5-2 and 5-3. Each figure shows two cash flow curves, one for the Reference surface plant and the other for the corresponding underground plant. The curves have been normalized for convenience in comparisons; but it must be remembered that the two curves shown on each figure represent plants with significantly different absolute costs.

The approximate dates of occurrence of five significant milestones in the construction processes of the plants have been identified on each cash flow curve. These milestones are the dates when: (a) the limited work authorization (LWA) was issued; (b) the construction permit (CP) was issued; (c) the reactor pressure vessel (RPV) was set into place; (d) the turbine-generator was delivered; and (e) the fuel was loaded. The date of commercial operation (CO) marks the official plant start-up date and the common end point for all construction cost curves (in accordance with the CEC project specifications). Issuance of the LWA marks the beginning of actual physical work at the construction site. In the period between the issuing of the LWA and the issuing of the CP, work at the site is limited primarily to site preparation, including excavation for foundations (which would require substantial movement of soil or rock for the underground plants). Formal beginning of the remainder of the construction activity cannot be consummated until the CP is issued. The RPV set dates and T-G delivery dates represent the times when expenditures for these two major pieces of capital equipment have been substantially completed.

As indicated by the dates shown in Figures 5-2 and 5-3 for these activities, a cost strategy was followed by each designer/cost-estimating team of developing a cash flow for each concept that would constrain (so far as possible) the total amount of the expenditures resulting from escalation and interest charges when applied to the basic construction

Figure 5-2. Normalized Berm-Contained and Reference Surface Plant Cash Flow Curves

Figure 5-3. Normalized Mined-Cavern and Reference Surface Plant Cash Flow Curves

cost (see Table 5-2) of the plant. With the interest (AFDC) rates (10%) and escalation rates (9%) utilized in this study, a cost savings strategy in construction scheduling would be to delay (for, as long as possible) the delivery of major capital equipment items until they were absolutely essential for installation in the plant. This strategy trades off escalation of the cost of equipment at the 9% rate against the alternative of paying the higher (10%) interest rates for longer times. The strategy would be particularly effective in holding down plant costs related to the more expensive equipment items such as the NSSS and turbine-generator, shown in Accts. 22 and 23 of Table 5-2. Since cash outlays for purchase of major components are typically contractually required to be essentially complete at the time of delivery, delay of delivery minimizes interest charges.

This strategy can be observed in the relative timing of the RPV installation date and turbine-generator systems (T-G) delivery for both the berm-contained and mined-cavern designs. The mined-cavern design can best take advantage of this delivery-delaying tactic. That is, the berm-contained plant, with its domed structure surrounding the reactor containment building, demands a relatively early date for setting of the RPV because of other conflicting construction activities. (As previously noted, sufficient time must be allowed for completion of dome construction and subsequent backfill of the berm.) Therefore, in the berm-contained design, the RPV delivery and installation must occur earlier in the schedule sequence than is required for the surface plants, or the mined-cavern facility.

Of course, changes in the relative magnitudes of the values chosen for the interest and escalation rates might induce minor changes in the scheduling of events for equipment delivery and installation, if full advantage were to be taken of this strategy for reducing overall plant costs. If the difference between interest and escalation were even greater than the 1% used herein, the strategy of delaying acceptance of

major equipment items would be even more favorable for overall cost minimization. Parametric investigations of the impacts of various interest and escalation rates were not performed as part of the A&E cost estimating activities. However, such investigations are being conducted by other participants in the CEC project and will be reported in a separate document.

5.4 SURFACE PLANT ACCIDENT MITIGATION SYSTEM COST SENSITIVITY STUDIES

Table 5-2 presents a column showing the relative costs for augmenting the safety features of an otherwise conventional surface-sited nuclear power plant with a modified Level-3 accident mitigation system (similar to the underground Level-3 system designs). The results of the design and cost trade-off analysis (performed by S&L) indicate that in comparison to the Reference³² surface plant, the system could be added with only modest cost increases. Direct construction costs are increased by \$14 million (about 2%). The cost increment for the accident mitigation system itself accounts for about 29% of the increased costs. Additional structural requirements, including a modest amount of additional excavation to house an underground rock-filled heat-sink/expansion volume, contribute about another 64% of the total additional costs.

Caution should be exercised when making economic comparisons between the modified surface facility and the underground berm-contained facility. The equivalent berm-contained facility, equipped with a Level-3 accident mitigation system, has an extra barrier to release of radioactive fission products from a Class-9 accident that is not found in the surface plant modification. The domed auxiliary building of the berm-contained facility represents an extremely effective second-containment structure which would be available as a backup to prevent fission product release to the environment, if failure of the primary reactor containment structure should occur for any reason. Though such a failure seems unlikely, as discussed in Section 4.2, the

existence of the second containment structure would nevertheless substantially reduce the likelihood of uncontrolled fission product release to the external environment from a Class-9 accident -- and hence also imply substantially reduced comparative risks for the underground facility with respect to the modified surface facility.

In any event, the relatively nominal percentage cost increase associated with the modified surface facility seems to make it an attractive concept for further investigation.

5.5 PARAMETRIC COST SENSITIVITY STUDIES

Several other economic and design-related variables were evaluated. In these analyses, an effort was made to vary the parameters individually, without altering the other design parameters of the concepts. However, in some cases such as the variation in which a GE 3800 MWt GESSAR Boiling-water Reactor (BWR) was substituted for the baseline Westinghouse 3800 MWt RESAR 414 PWR, it was necessary to prepare additional design drawings (cf., Refs 1-1, 1-2) in order to adequately evaluate the cost impacts of the changes. As a general approach to evaluation of the effect of each parameter change, critical design elements impacted by the change in the variables were identified; the required design changes were determined for the major elements of the facilities; and the resulting changes in facility costs were calculated. As shown in Tables 5-3 and 5-4, the variables selected for cost sensitivity analyses included: (a) reactor types (principally BWR) and underground and surface turbine-generator locations; (b) accident mitigation systems; (c) site characteristics which could impact facility construction and/or operation; (d) seismic input motion levels; (e) depths of cover over the facilities; and (f) construction schedule variations.

Table 5-3. Berm-Contained Concept Cost Sensitivity Analyses

Variables	<u>Costs</u>		Cost Increment (vs. Baseline)	
	<u>Total Construction</u> (\$ million)	<u>Grand Total Project</u> (\$ million)	<u>(\$ million)</u>	<u>(%)</u>
I. <u>Baseline</u>	950	2818	- -	- -
II. <u>Reactor (PWR)*</u>				
1) BWR	934	2765	-53	-1.9
III. <u>Accident Mitigation System</u>				
<u>Design (Level 2)</u>				
1) Level 1	949	2817	-1	negligible
2) Level 3	961	2841	+23	+0.8
IV. <u>Site Characteristics (B/L)</u>				
1) Soil Model 2	945	2805	-13	-0.5
2) Rock Model 1	954	2831	+13	+0.5
3) Dry Soil	949	2818	- -	negligible
4) High Water Table	969	2875	+57	+2.0
5) Dry Climate	951	2828	+10	+0.4
6) Remote Desert	1027	3050	+232	+8.2
V. <u>Seismic Input (0.5g)</u>				
1) 0.67g	975	2895	+77	+2.7
VI. <u>Minimum Overburden (50 ft)</u>				
1) 25 ft	929	2757	-61	-2.2
2) 100 ft	982	2912	+94	+3.3
VII. <u>Construction Schedule (142 mo)</u>				
a) Common Commercial Operation Date				
1) Accel. (136 mo)	990	2943	+125	+4.4
2) Extended (161 mo)	949	2782	-36	-1.3
b) Common Project Initiation				
1) Accel. (136 mo)	990	2819	+1	negligible
2) Extended (161 mo)	949	3314	+496	+17.6

* Data in parenthesis represent baseline (B/L) conditions for variables cited.

Table 5-4. Mined-Cavern Concept Cost Sensitivity Analyses

<u>Costs</u>				
	<u>Variables</u>	<u>Total Construction</u> (\$ million)	<u>Grand Total Project</u> (\$ million)	<u>Percent Change</u> <u>(vs. Baseline)</u>
I.	<u>Baseline (PWR)**</u>	1168	3430	- -
II.	<u>Reactor/Turbine-Generator (B/L)</u>			
	1) BWR	1177	- -	+0.8
	2) Surface T-G	1126	3311	-3.4*
III.	<u>Accident Mitigation System</u> <u>Design (Level 2)</u>			
	1) Level 1	1165	- -	-0.3
	2) Level 3	1166	- -	-0.2
IV.	<u>Site Characteristics (B/L)</u>			
	1) Better rock	1167	- -	-0.1
	2) Poorer rock	1172	- -	+0.3
	3) High Water inflow	1174	- -	+0.5
	4) Dry Climate	1170	- -	+0.2
	5) Flat Terrain	1191	- -	+2.0
	6) Remote Desert	1168	- -	negligible
V.	<u>Seismic Input (0.5g)</u>			
	1) 0.67g	1181	- -	+1.1
	2) 0.3g	1159	- -	-0.8
VI.	<u>Depth of Cover (200 ft)</u>			
	1) 1000 ft	1260	- -	+7.9
VII.	<u>Construction Schedule (123 mo)</u>			
	1) Accel. (104 mo)	1192	3560	+3.8*
	2) Extended (141 mo)	- -	3526	+2.8*

* Percent changes calculated with respect to Grand Total Project Cost. All other variations were calculated with respect to Total Construction Cost.

** Data in parenthesis represent baseline (B/L) conditions for variables cited.

5.5.1 Berm-Contained Facility Cost Sensitivity

Costs of berm-contained facilities were found to be sensitive to the following factors, in the approximate order of their significance.

5.5.1.1 Construction Schedule Variations

Construction schedule variations were analyzed in two different ways in the berm-contained concept cost sensitivity studies. In both cases the effects of an extended schedule were examined (a 19 month increase for a total duration of 161 months) in comparison with the baseline schedule (142 months total). If common plant start-up dates for commercial operation (April 1990) were assumed as the basis for cost estimates (as assumed for all other variables except the schedule variations), then the 161 month extended schedule duration implied that the project initiation (i.e., the initiation of the first elements of plant studies and licensing procedures) had to occur by 1 November 1976, nearly 8 months prior to the date (1 July 1977) for fixing price estimates. This artificial project initiation date required some portions of the cost estimates of the program to be "deescalated" from 1 July 1977 to the November 1976 project initiation date. Thus, the assumption of a common date for commercial operation resulted in somewhat unrealistic cost estimates for the extended schedule case; since the deescalation process for costs led to an apparent reduction in grand total projects costs for the concept.

In order to resolve this problem, a second analysis was conducted of the cost impact of schedule variations, based upon the assumption of common dates for project initiation with those of the baseline program (i.e., 1 June 1978). Using the same extended schedule duration of 161 months total, the grand total project costs were increased in this analysis by about 18 percent, or nearly \$500 million.

The analysis of an accelerated schedule (136 months), based upon similar assumptions, (i.e., the common 1 June 1978 date for project initiation), provided results indicating that the grand total project costs were increased by only negligible amounts (about \$1 million). However, total construction costs (in terms of constant, 1 July 1997 dollars) were increased by about \$40 million (or 4.2%). Under these assumptions, in spite of increased total construction costs, the accelerated schedule resulted in compensating reductions in both escalation and interest, with the net result that negligible changes occurred in the grand total project costs.

The nominal case for the accelerated schedule (assuming common start-up dates of 1 April 1990 for commercial operation of the plant) yielded a project initiation date of 1 December 1978. The increased construction costs, due primarily to higher labor rates for premium time charges and extended work weeks, and the artificial 6 month delay in project initiation (required in order to delay commercial operation until the common 1990 date) resulted in higher escalation costs -- which further resulted in higher AFDC (interest) charges. The net cost impact for the accelerated schedule was an \$125 million increase (or about 4%), of which about two-thirds was attributable to higher costs from escalation and AFDC.

Thus construction schedule changes have the potential for producing a major cost impact on the berm-contained facilities. Extended schedules were shown to increase costs by as much as about 18% (or about \$500 million). Accelerated schedules may not reduce project costs. In some cases, it may even increase them. Depending upon assumptions with respect to project initiation, accelerated schedules resulted in cost increases of as much as about 4% (or \$125 million) for several cases examined in the CEC study.

5.5.1.2 Remote Site Locations

Construction in a relatively remote (Eastern Mojave Desert) area of California was shown to result in an increase in cost of about 8% (\$232 million). Note that this number is exclusive of transmission line costs. The cost increase resulted primarily from assumed decreases in productivity of labor at the site; lost time in traveling to and from the site; and a need to offer higher wages to attract workers to the remote location. These factors were accounted for in the sensitivity analysis by increasing both man-hours and labor rates by 10% each.

5.5.1.3 Overburden Depth

Increasing the depth of back-filled cover over the berm-contained facility by 50 ft (from depths of 50 ft minimum to 100 ft minimum) resulted in an increase in the grand total project cost of about 3% (or \$94 million). Similarly, decreasing the overburden by 25 ft from the baseline (50 ft) depth resulted in cost savings of about 2% (or a cost decrease of \$61 million). Thus berm-contained facility costs are sensitive to depths of cover, primarily as a result of the impact of the static load from the massive berm cover on the required thickness of the domed structure. Baseline overburden depths were prescribed on the basis of estimated requirements for delay and filtering effectiveness with respect to fission products released from the Level-2 Accident Mitigation Systems. With careful design of the berm, including selection of material properties for fission product transport characteristics -- as well as their construction properties, reduced thicknesses of overburden could probably be used. Optimization of overburden thicknesses would be a subject for detailed design studies. Such an effort was beyond the scope of this program.

5.5.1.4 Seismic Design Criteria

Increasing the seismic design criteria from peak surface accelerations of 0.5g to 0.67g increased grand total project costs by about 3% (\$77 million). The increased seismic loads on the structure resulted in increases of about 30% in the wall thicknesses for both the domed auxiliary building and containment structures; and an increase of about 20% in the foundation mat thickness. Underground construction was found to reduce seismic requirements for equipment design. However, no cost benefits were taken for reduced equipment requirements in the development of the underground designs

5.5.1.5 Groundwater Table Level

When the plant construction site was assumed to have a groundwater table which reached to approximately the surface grade level, grand total project costs were increased by about 2% (or \$57 million). The costs were increased as a result of seismic design requirements for resolving soil liquefaction problems. An expensive, permanent, Category I (seismically qualified) pumping system was also required for steady-state dewatering of the site in this sensitivity analysis. Thus, high-water table effects could have a detectable (but modest) impact on berm-contained plant costs.

5.5.1.6 Accident Mitigation System Design

On a comparative basis, the choice of an accident mitigation system for use with the berm-contained concepts did not have a large impact on grand total project costs. If only Level-1 requirements were met, costs were essentially unchanged from baseline costs. (The Level-1 System design does not require an expansion volume/heat-sink zone. The only significant system requirement is for leak-tight closures on the

tunnel, pipe, and cable penetrations from the domed auxiliary building to the external environment). Similarly, if a Level-3 system were provided (with an engineered, controlled and filtered release system for gaseous fission products), the grand total project costs increased by less than 1% (\$23 million). Thus the selection and incorporation of alternative accident mitigations systems in the berm-contained facilities does not seem to have a particularly significant impact on plant costs.

5.5.1.7 Reactor Types

22 The design detail permitted within the scope of the study was not sufficient to make distinctions between the several available NSSS on the basis of cost estimates prepared in this study. For all practical purposes, it appears that the berm-contained concepts would be equally applicable to any of the presently available power reactors. At this time, there is no reason to believe other reactor types, such as High Temperature Gas Cooled Reactors, could not also be adopted for a berm-contained installation.

5.5.1.8 Other Site Characteristics

The costs of berm-contained facilities appear to be insensitive to changes in the other principal construction properties associated with site locations (i.e., soil properties and climatic conditions) that were investigated. No substantial impact would be expected from these variables on sites within the State of California.

5.5.2 Mined-Cavern Facility Cost Sensitivity

Table 5-4 indicates that the following variables have major impacts on mined-cavern facilities.

5.5.2.1 Depth of Cover

If the caverns are located at greater distances into the hillside in order to obtain depths of cover of 1000 ft over the reactor cavern, instead of the 200 ft of the baseline case, total construction costs are increased by about 8%. Principal design features causing the cost increase are: (a) increased excavation costs for longer tunnels (about 1700 ft added to each of the two main tunnels) and ventilation shafts; (b) increased ventilation costs; (c) increased line lengths and pump capacities (hence costs) for condenser cooling water and service water requirements; (d) decreased labor productivity as a result of longer transit times from tunnel portal entrances to underground work points; and (e) greater logistical problems with material and equipment during construction.

5.5.2.2 Construction Schedules

Both extended and accelerated construction schedules were shown to adversely effect costs when compared with nominal baseline schedules. All mined-cavern schedule variations were based upon assumed common start-up dates for commercial operation of the plants (April 1990). The acceleration in the schedule was accomplished by use of premium time and extended work weeks during the equipment installation and set-up portion of the schedule. These factors increased the total construction costs for the facility (in constant 1977 dollars) by over 2%; making this variation the second most expensive concept investigated. A gross increase in the grand total project cost of about 4% (\$230 million) resulted when the additional impact of increased escalation resulting from the delay in project initiation (the accelerated project was initiated 1 July 1981 -- compared to 1 January 1980 for the baseline project initiation) was included in the cost estimates. The extended schedule sensitivity analysis indicated costs would be increased by about 3% (\$194 million) as a result of an 18 month slip in the construction schedule.

5.5.2.3 Surface Location For Turbine-Generator Systems

Total facility construction costs were shown to decrease by about 3% when the turbine-generator and related supporting systems were located at the surface of the hillside, rather than in an excavated cavern. Though costs were increased for longer main steam and feedwater lines from the reactor to the turbine (and back), they were more than offset by the reduced costs of cavern excavation, elimination of underground condenser coolant lines, reduced ventilation requirements, and shorter electrical connections for the main generator.

5.5.2.4 Site Terrain Characteristics

22 If the plant were constructed beneath flat terrain, instead of within a hillside, total construction costs for the plant would be expected to increase by about 2%. Though the basic plant layout remained unchanged in this sensitivity analysis, access tunnel lengths were substantially increased by the necessity of spiraling down the 200 ft in depth to the plant working level beneath the surface. For example, a 5% tunnel grade would increase the required access tunnel lengths by over 3000 ft. Assuming the turbine-generator systems were located underground and the cooling water supply to the turbine condenser was located at the surface, condenser design requirements (or coolant lift requirements) could also be substantially impacted. Thus it appears that hillside sites would be both economically and technologically preferable to siting beneath flat terrain.

5.5.2.5 Seismic Design Criteria

Sensitivity studies were made of the impacts of both increased and decreased seismic motions for mined-cavern facilities. Increases of representative seismic inputs from 0.5g to 0.67g increased facility total

construction costs by about 1%. Similarly decreases in seismic levels from 0.5g to 0.3g decreased total construction costs by about 1%. The cost impacts were the result of changes in requirements for rock bolts, concrete, and steel for supporting the underground cavern and tunnel excavations in the two parametric cases

5.5.2.6 Accident Mitigation System Designs

Changing the facility design to incorporate either Level-1 or Level-3 Accident Mitigation Systems instead of the baseline Level-2 system, resulted in insignificant cost changes for the facilities. Costs were apparently decreased, but the changes were too small to permit realistic differentiation between concepts on the basis of economics.

5.5.2.7 Alternative Reactor Types

As with the berm-contained concepts, there does not appear to be a sufficient basis for distinction between any of the currently available NSSS, on the basis of economics. However, the technological problems with the proposed large cavern spans (about 150 ft in width) for the 1300 MWe BWR concepts provide a basis for concern about the practicality of the proposed design for the BWR concept. It is possible that reactor cavern span requirements for BWRs could be reduced to about the same values as those of the baseline PWR reactor cavern (a span of about 100 ft.). However, the NSSS redesign requirements to achieve this goal were beyond the scope of the CEC project. Therefore, it is appropriate to note that the decision for underground mine-cavern reactor selection cannot be reasonably based upon economic merits, at this time. However, for a given thermal power output, technological considerations indicate that the physical dimensions of a PWR-NSSS (regardless of manufacturer) are preferable to those of a BWR for mined-cavern siting.

5.5.2.8 Other Site-Related Characteristics

Neither geological, nor meteorological properties of sites, nor site remoteness appears to have a significant impact on mined-cavern facility costs. A foothill location was assumed for construction of the baseline facility. This site was considered to be sufficiently distant from urban centers, that the remote siting cost effects on labor productivity and higher wages were introduced for the baseline cost estimates--and all other sensitivity studies as well. Thus, cost perturbations due to the above-mentioned site-related features were found to be too small for discrimination against the background of other cost uncertainties for the facilities.

REFERENCES

- 5-1. United Engineers and Constructors, Inc., "1000-MWE Central Station Power Plants, Investment Cost Study," Vol I, Pressurized Water Reactor Plant, USAEC Report No. WASH-1230 (Vol 1), June 1972.
- 5-2. Rand Corporation Report, "Development and Commercialization of the Light Water Reactor," 1946-1976; June 1977.
- 5-3. Aerospace Corporation Report, "System Management Support for ERCDC Study of Underground and Berm Containment," August 1977.
- 5-4. United Engineers and Constructors, Inc., "Capitol Cost; Pressurized Water Reactor Plant," NUREG-0241(Vol 1 of 2), June 1977.

6.0 EVALUATION OF RELATED ISSUES

A variety of issues associated with underground siting of nuclear power plants, including both advantages and disadvantages, have been raised by advocates and opponents of the concept. Advocates have suggested that benefits might be derived from such sources as (a) reductions in seismic requirements for underground facilities; (b) potential reductions on restrictions against close-in siting of nuclear power plants to population centers; (c) possible reductions in plant vulnerability to natural hazards (e.g., falling objects or severe meteorological events, such as tornadoes, etc.) or man-made hazards (e.g., aircraft impacts or potential military or sabotage threats). Opponents have suggested that (a) there might be more severe licensing and regulatory requirements with resulting lengthened construction periods and associated increased costs for underground plants; (b) that flooding problems might be more severe; and (c) that there might not be sufficient site locations within California to make underground concepts worthy of consideration. These issues will be addressed in this section. Maps used in this section to illustrate some specific aspects of these issues have been derived from an investigation of geophysical and population-related features of California performed by the State Division of Mines and Geology in support of the CEC underground nuclear power plant project (Ref 1-4).

6.1 SEISMIC IMPACTS

As noted above, advocates of underground nuclear power plants have suggested that even shallow burial of a power plant could reduce the intensity of ground motion sufficiently below that experienced at the ground surface of the site to make underground siting economically attractive. An early project study (Ref 1-5) provided evidentiary support for this anticipated benefit. As a consequence, specific efforts were subsequently made to examine the effects of the underground seismic

environment on facility designs and costs (cf, Section 5.5 for an evaluation of the economic impacts of seismicity on underground facilities).

6.1.1 Overview of Seismic Implications for California Siting

California is a very seismically active area. Figure 6-1 displays historical data (1900 to 1974) for earthquake epicenters of events with Richter magnitude of 4.0 or greater, (or modified Mercalli Intensity of 5.0 or more) within the State. The figure provides a dramatic display of seismic activity. About one-half of the recorded earthquakes of significance in the 48 contiguous States of the U.S. have occurred in the State of California (Ref 6.1)

In California, and other areas as well, earthquake activity can generally be associated with identified fractures or faults in the Earth's crust. Consequently, earthquake hazard relationships based upon proximity to known fault locations have been adopted (along with other measures) as a mechanism for evaluation of nuclear power plant sites with respect to seismicity. For example, criteria for determining seismic implications for potential plant sites are contained in the NRC's Regulatory Guide 4.7, "General Site Suitability Criteria for Nuclear Power Stations." The principal limits of Regulatory Guide 4.7 may be summarized as (a) an absolute restriction against siting in the presence of a "capable" fault, based upon the present inability of structural design to accommodate the severe ground motion environments (including the potential for ground rupture) experienceable at such a site; and (b) an implied extension of the above observations generally excluding the location of plant sites within five miles of a "capable" surface fault greater than 1000 ft. in length. "Capable" faults are defined as those which have displayed movement (irrespective of magnitude) at or near the ground surface at least once within the past 35,000 years or movement of a recurring nature within the past 500,000 years. Figure 6-2 presents an

Figure 6-1. Earthquake Epicenter Locations

Figure 6-2. Regions of Fault Zone and Volcanic Activity Relative to Population Screening Criterion

application (and extension) of similar criteria to those stated above to identified faults of relatively recent origin in California. Quaternary faults, those which have exhibited movement within about the last 2 million years, with lengths of 1000 ft. or more have been shown in the figure, with a band of 5 mi. width (10 mi. total) marked along each side of the fault. Although the criteria upon which Figure 6-2 was based are not identical to those of the NRC, the identified fault zone areas are quite likely to include the "capable" faults within them. Thus, proposed sites within the indicated fault zone regions would most likely require extensive geotechnical evaluation, and positive proof of fault ages, before they would be found acceptable.

From a comparison of Figures 6-1 and 6-2, the relationship between earthquake epicenters and crustal faulting of the earth can be readily observed. The few earthquake epicenters which are not specifically associated with known faults probably would be, if further investigations were conducted.

6.1.2 Underground Seismic Environments

In the initial phase of the CEC program, a preliminary assessment was made of seismic implications for underground facilities. (Refs 1-5, 1-6) Estimates were made of seismic motions and an analysis conducted of structure-medium interactions for subsurface facilities based upon empirical data and theoretical grounds. The investigation also included an evaluation of the applicability of current seismic design methods for surface nuclear facilities to underground designs.

Pertinent empirical evidence available on underground measurements of seismic motions was reviewed and evaluated. It was concluded that the data supported the inference of decreasing levels of motion with increasing depth beneath the surface. However, most of the direct measurements had been obtained in relatively weak earthquakes.

Moreover, peak accelerations recorded at the surface of the earth were generally substantially less than 0.1 g. Such acceleration levels are well below those of significance to nuclear power plant design in California. To supplement the empirical results, finite-element analyses were performed for a "typical" Central Valley site on the basis of an assumed 0.5 g seismic acceleration input.

Based upon the combined results of both theoretical analyses and empirical data, reduction factors for peak values of free-field acceleration, velocity, and displacement were defined for preliminary design purposes. The results, as shown in Table 6-1, specified that peak accelerations at depths of 30 m (or greater) should be reduced by a factor of 0.5 in soils and 0.67 in rock sites (Ref 6.2). Peak values of velocity and displacement were also reduced; although, no reduction in displacement was recommended for rock sites. The values listed in Table 6-1 were developed for preliminary design guidance for the study. They did not comprise the final seismic design basis for the plants sited in either soil or rock.

Table 6-1

Proposed Depth Reduction Factors
for Seismic Motions
(Depth >30m)

	Peak <u>Acceleration</u>	Peak <u>Velocity</u>	Peak <u>Displacement</u>
Soil	1/2.0	1/1.5	1/1.2
Rock	1/1.5	1/1.2	1/1.0

The recommended reduction factors of Table 6-1 allow distinction between soil and rock sites and are independent of depth, at depths below 30 m. For depths of less than 30 m, it was recommended that a linear transition be made between a factor of unity appropriate for the surface motions and the reduction factors of Table 6-1. For example, an acceleration reduction factor, $R_A(20)$, for a soil site at a depth of 20 m would be given by:

$$R_A(y) = 1 - \frac{y}{30} (1 - R_A),$$

$$\text{e.g.; } R_A(20) = 1 - \frac{20}{30} (1 - \frac{1}{2}) = \frac{2}{3}$$

where y is the depth in meters. Similar relationships would be applicable for reduction factors for peak velocity and displacement at intermediate depths.

The preliminary seismic design relationships were also developed in a spectral form in terms of motions as a function of frequency of response for a damped, single degree-of-freedom oscillator, as shown in Figure 6-3 (Ref 6-3).

The preliminary analyses also demonstrated reduced structural motions for underground structures as compared with surface plants. The lower calculated values for free-field and structural motions for the underground environment suggested that less steel and concrete would be needed to resist dynamic forces in underground structures when compared to surface facilities at the same site location. The potential for reduced motions also suggested that more "standardized" equipment might be used within the underground facilities, i.e., equipment designed for the more benign seismic environments of the midwest and eastern portions of the United States.

The preliminary evaluation of Ref 1-5 also suggested that seismic structural design methods of current practice would probably be

Figure 6-3. Recommended Horizontal Seismic Response Spectra
(Subsurface Depths Greater than 30 Meters, 0.5 g Peak Surface Acceleration)

adequate for preliminary analysis of underground structures, as well as surface structures. An evident need was observed for improvements in the physical basis for seismic analysis methods. More realistic, nonlinear soil stress-strain relationships should be incorporated into the computational methodology for both surface and underground plant designs. Nevertheless, current analytical methods have had reasonably good success in post-incident "predictions" of the results of earthquake interactions with existing semi-buried structures, in the limited number of serendipitous cases where such structures have been exposed to earthquakes. The general adequacy of these calculations lends credibility to the conclusion that the seismic design methods currently utilized are probably adequate for at least preliminary design of underground facilities.

6.1.3 Berm-Contained Seismic Design

On the basis of these findings, current seismic design methods were used by S&L Engineers, Inc. to reevaluate the seismic loads and structural response for the berm-contained facilities. Because the external dome-shaped structure for the auxiliary building of the berm-contained concept is only partially located beneath the surface grade level within its excavation, with a large portion of the backfilled berm located above grade level, seismic loads on the facility were found to be substantial. This is largely a result of the large shear forces which the domed auxiliary structure must resist to prevent horizontal sliding of the massive earthen backfill. Deeper burial might have reduced these shear loads, but only at substantial expense due to the corresponding requirements for increased excavation.

When the state-of-the-art seismic design methods were applied to both the Reference surface and Baseline berm-contained facility designs for the study, it was found that input seismic motions to the two structures were not substantially different. This observation was

somewhat surprising based upon the earlier results of the program, discussed above. However, the similarity in seismic motions was at least partially the result of differences in the site geological models applied in the design of the two plants. The foundations for both the surface and underground structures were laid within the first adequate layer of rock provided in the specifications for the baseline site geological model. Though the sites for the two facilities were considered to be similar, the depth of overlying unconsolidated soil materials was allowed to be a variable for the two designs. (Variability in soil layer thickness is common at most real sites.) As a consequence, the relative depth to bed-rock was similar for both surface and underground facilities. With current seismic design methods, the distance from structure foundation to bed-rock is the controlling feature for seismic motions for similar site geological models. The unanticipated result of this design simplification was that (from the point of view of a spectral analysis of the seismic motions) there was little difference between the input seismic conditions at the foundations for the surface and underground structures.

Structural dimensions for the facilities are based upon combinations of static soil loads as well as dynamic seismic loads. In the berm-contained plant, the dead-weight load of the soil backfill of the berm dominates all other loads on the external superdome structure. The dominant static meridional membrane forces are from 2 to 5 times greater than the equivalent seismic forces for the domed shell of the auxiliary building. Based upon the results of static and dynamic analyses, the final structural dimensions of the Reference surface and Baseline berm-contained plants are as shown in Figures 6-4 and 6-5 respectively.

It should be noted that, while the soil cover imposed very large static and dynamic loads on the exterior elements, modest reductions were achieved in the seismic loads on the internal structures of the

Figure 6-4. S&L Reference Surface Plant Structural Dimensions

6-12

Figure 6-5. Baseline Berm-Contained Plant Structural Dimensions

underground plant when compared with those of the surface facility. This can be seen in the smaller size of the walls in the containment structure in the underground plant. It was also shown that the response spectra on the higher floors within the containment and auxiliary buildings in the underground plant were not amplified as much as they were in the surface plant. This would result in smaller seismic loads on the equipment which would be located on the higher floors. Thus, even though the underground seismic environment did contribute significantly to the required external dimensions of the domed auxiliary structure, reduced seismic requirements for equipment would permit some economic benefits for the underground facility. As indicated in Section 5.5, increasing the seismic design requirements to 0.67 g induced a modest (2.7%) increase in the grand total cost of the underground facility. This increase was almost exclusively due to added requirements for concrete and steel for heavier structures. Equipment costs, due in part to the beneficial effects of the underground environment, were essentially unchanged for the higher seismic design conditions.

The structural analysis and design of the berm-contained facility led to the following conclusions:

- The depth of the soil cover should be kept to the minimum possible consistent with design objectives (e.g., accident mitigation) so that the cost of the structure supporting this overburden is not unduly penalized.
- The soil cover imposes very large static and dynamic loads on the exterior elements. However, as a result of the stiffness of the massive auxiliary building mat, the seismic loads on those internal structures connected to the external structures only by the foundation mat are smaller than those of a surface facility.

- ne
- The structural requirements for an underground plant are dominated by the large static loads imposed by the soil cover and the configurational constraints placed upon the building to support those loads more efficiently. Nevertheless, the dynamic seismic loads make a significant contribution to design requirements for an underground plant. The burial depth for the berm-contained plant was not optimized for seismic purposes. In a final design exercise, seismic requirements should be included in the determination of the optimum burial depth.

6.1.4 Mined-Cavern Seismic Design

According to a recent evaluation of seismic damage to underground rock excavations, structures in rock are much safer than aboveground structures for given Modified-Mercalli (MM) intensities of shaking (Ref 6-4). Only minor damage was observed to underground rock excavations in MM-VIII to IX earthquake intensity levels. Considerable damage would be experienced by aboveground structures at the same MM intensities. In the survey, total collapse of underground rock tunnels was only observed when associated with movement of an intersecting fault, irrespective of earthquake intensity. Moreover, up to surface acceleration levels of 0.5 g, no damage was observed to pressure-grouted, concrete-lined underground rock excavations due to seismic shaking alone.

The mined cavern structures of this study have been designed on the basis of state-of-the-art construction practices. Rock bolts and tendons have been utilized to strengthen the excavated surfaces. In addition, concrete and steel linings would be applied to all critical safety-related caverns; or pressure-grouted concrete liners would be utilized for non-critical tunnels. In this type of construction, virtually no free response of the structural lining is possible with respect to the surrounding rock mass (Ref 6.5).

Moreover, structure-medium interactions between seismic waves and underground excavations which result in significant amplifications to free-field motions would occur only if earthquake wavelengths are equivalent to (or at most, four times larger than) the dimensions of the excavations (Ref 6.6). Most of the significant energy of earthquakes in rock is developed at frequencies between 0.4 Hz and 10 Hz. For the rock materials of interest to this study, wavelengths of from 1000 ft. to 30,000 ft. would be associated with these frequencies. These wavelengths are about a factor of 10 (or more) larger than the critical dimensions of excavations in the mined-cavern concepts. Consequently, the caverns, and structures braced to the walls, within them, would tend to move with essentially the same motion as the free-field rock mass. Little or no distortion would be expected across the spans of the caverns and pseudo-static design analysis methods would be adequate for them. The maximum strains experienced in long tunnels would be essentially equivalent to the earthquake free-field strains (or about 10^{-4} in/in for the 0.5 g earthquake prescribed for this study). Under these conditions, earthquake-induced maximum shear stresses in the rock in the vicinity of the tunnels would be less than 200 psi which should be well within the strength of the reinforced structures designed for this study

Because the mined-cavern structures would respond with essentially the same motion as the input, free-field motion of the earthquake, they would obtain another benefit from underground construction. The containment building of a surface-sited plant responds to an input earthquake motion at its base like a pendulous cantilevered structure; that is, the motion of the upper floors of the structure is greatly amplified in comparison with the base motion. Since the underground cavern structure would be supported on all sides by surrounding rock with the upper floors braced against the cavern walls, the pendulous motion of the structure, hence the amplification of the higher floors, would be essentially eliminated.

6.1.5 Observations on Seismic Design

Some seismic benefits are achievable with underground construction. However, the partially-buried design of the berm-contained structure results in large external seismic loads due to the shear forces associated with the massive backfilled earth berm of the structure. Nevertheless, seismic loads are less than the static loads of the weight of the berm, which dominate the structural sizing for the walls of the external superdome structure. Moreover, the massive stiff structure of the unitary base-mat for the domed auxiliary and internal containment building, reduces the pendulous containment response somewhat compared to the response of the Reference surface structure. Similarly, the inertia of the massive earth berm reduces the pendulous motion of the upper floors of the domed auxiliary structure below that of the equivalent surface structures, resulting in reductions in accelerations at critical frequencies for equipment. Hence, equipment requirements for the underground structure would be somewhat less substantial than would be the case for a surface-sited structure. This results in some benefits with respect to equipment requirements for the underground facility.

Subsurface motions are not expected to be reduced as dramatically with depth in rock as they would be in soil. However, the mined-cavern facilities benefit substantially from being totally contained within the surrounding rock. As a result, cavern motions are constrained to essentially those of the free-field in the rock mass. Hence, amplification of seismically induced motions for the structures would be substantially reduced. Here again, and perhaps more than in the case of the berm-contained facility, some substantial benefits in seismic design requirements for equipment would be expected. Underground seismic design requirements were relatively small compared with static design load support requirements for the mined-cavern structures, as was also the case for the berm-contained facilities.

6.2 SITING IN PROXIMITY TO POPULATION CENTERS

An often-cited benefit for subsurface siting is that it might permit locating power reactors closer to population centers, the presumed centers-of-demand for electrical power. If this were possible, then the additional expense of underground siting might be offset by savings from shorter electrical transmission line distances from power plants to customers. Advocates have held that if underground siting were proven effective in mitigating the consequences of severe reactor accidents, opportunities for urban underground site locations might evolve which would otherwise be unavailable to surface-sited nuclear power plants. The validity of these assumptions will be discussed below. The reader is cautioned that the following discussion is directed specifically to the State of California and conclusions reached may not apply to other locales.

6.2.1 Surface Plant Exclusion Criteria for Population Centers

One of the important factors influencing siting decisions for conventional surface sited nuclear power plants is the proximity of the facility to population centers. An examination of past siting decisions has indicated that there has been much diversity with respect to population distributions about individual nuclear power plants. Some plants are located quite close to large population centers; while others are relatively far from any cities of substantial size.

No definitive NRC criteria are currently available upon which to base a regional population screening effort for evaluating site remoteness requirements for the entire State of California. Some informal guidelines have been adopted by the NRC; but they have been left as policy statements, and have not been formulated into specific regulatory criteria. In 1973, the AEC produced a report evaluating

population distributions at all approved reactor sites as well as those for which application for licensing had been made at any time. (WASH-1308; Ref 6-7). As an informal guideline, the report suggested that sites would not be considered acceptable for licensing purposes if they had population densities which exceeded the gross definition provided by an envelope of the cumulative population distributions for three significant plants: (1) Zion (an operating facility in the vicinity of Chicago, Ill.); (2) Newbold Island (a proposed site, not actively under consideration, in the vicinity of Philadelphia, Pa.); and (3) Indian Point (an operating facility in the vicinity of New York City, N.Y.). On the basis of the WASH-1308 population analysis, the AEC further recommended that sites with cumulative populations greater than 30,000 within 5 miles of the reactor; 500,000 within 20 miles, and 2 million within 40 miles should be analyzed carefully and consideration be given to alternative locations. These constraining cumulative population distribution curves have been plotted as Figure 6-6, along with the current cumulative population distributions for existing and proposed nuclear power plant sites within the State of California. Figure 6-7 presents the locations of these existing and proposed nuclear power plants in California: (Following a recent local election, utility planners have indicated that the request for approval of the San Joaquin plant site will be withdrawn.) It is interesting to observe that California's sites generally fit within the spirit (and usually the letter) of the WASH-1308 recommended guidelines.

The WASH-1308 guidelines were transposed into Statewide screening criteria by converting them to integrated population vs. radial distance demarcation criteria. The AEC's quantitative recommendations for population limits, as noted above, (extended by limiting population to an average of no more than 500 people/sq. mi beyond the 40 mile limit) have been applied to California population centers as shown in Figures 6-2 and 6-8. (The application of the population screening criteria has been combined with maps of (a) volcanic/fault zone activity criteria and

Figure 6-6. Cumulative Population As A Function of Distance From Nuclear Plants

Figure 6-7. Locations of Existing and Proposed Nuclear Power Plants

Figure 6-8. Population-Related Geographic Screening Factors

(b) other population-related geographic factors of National Parks, Monuments, Indian Reservation, and State Parks; and wilderness and wild-river areas, respectively in the two figures.) The major population centers associated with metropolitan San Francisco, Los Angeles and San Diego are clearly visible on the maps. According to the latest census figures, over three-fourths of the total population of California are located within the designated areas of these population centers; with about one-half of the total population located in the greater Los Angeles area. Population centers in the Central Valley are also clearly evident. The five largest population centers of the Central Valley (Sacramento, Fresno, Bakersfield, Stockton, and Modesto) constitute about an additional 10% of the total population of the State.

If the map showing existing or proposed locations for nuclear plants (Figure 6-7) were superimposed on the maps of Figures 6-2 or 6-8, it would be observed that (with the exception of the Humboldt Bay facility), all such plant sites lie outside of the indicated demarcation zones for the population centers noted. The Humboldt Bay nuclear facility is a small (63 MWe), prototypical BWR with operating and safety characteristics which differ substantially from the large (1300 MWe) plants of interest to this program. The Humboldt Bay site is near the town of Eureka, California (population: 24,337, in 1970). The license for this facility is under review by the NRC at this time. Concern has been expressed with regard to the plant's seismic capabilities. Whether the Humboldt Bay nuclear power plant will be allowed to operate again is uncertain.

By observation, it is clear that the bulk of California's population is concentrated near the Pacific Ocean. Figure 6-2 shows that it is also concentrated in areas of high seismic potential. The criteria used to define potential seismic hazard areas were described in Section 6.1. Although often referred to as seismic exclusion areas, the indicated hazard zones are more properly "prudence" areas. An applicant

ne proposing a nuclear plant site within the mapped seismic hazard areas could anticipate an extensive period of geotechnical studies as a part of his licensing process.

Certainly the coupling between population centers and areas of high seismic potential is not entirely intentional. However, it is also apparent that the public's perception of individual risks from seismic events is not sufficient to discourage population concentration in the regions of highest seismicity in the State. This is particularly apparent in the greater Los Angeles area where over half of the State's population is centered; and where some of the most severe earthquakes have been experienced.

Though this observation is somewhat peripheral to the issue of siting of nuclear power plants in the vicinity of population centers, the relationship of population centers to the seismic demarcation zones of this study is very important to plant siting. The criteria for seismic demarcation zones are associated with proximity to capable faults and not directly identifiable with intensity of ground shaking. Thus the indicated seismic demarcation zones of Figure 6-2 would be equally applicable to both underground and surface-sited facilities.

The extensive overlap of population and hazardous seismic regions shown in Figure 6-2 indicates that there is little reason to believe that any significant benefit can be obtained from attempts to site underground plants closer to the major population centers in California. However, not all of the areas within the population demarcation zones are covered by overlapping seismic hazard areas. Consequently, there might be a limited number of sites which could be considered in the vicinity of the three most heavily populated regions in the State. It should be noted, however, that such sites would be required to satisfy a variety of other criteria as well as those associated with public risks from accidental releases of radioactivity.

These include the availability of suitable soil or rock for construction purposes; turbine condenser cooling water availability; terrain characteristics; accessibility; and all other standard siting criteria. Obtaining an adequate cooling water supply could be an especially difficult problem for sites in heavily populated areas, particularly, if coastline sites were excluded. (Seismic hazards would apparently foreclose most of the coastline.) The availability of technically acceptable soil and rock conditions for siting will be discussed in more detail in Section 6.5. However, finding acceptable sites in proximity to the principal population centers of the State would appear to be a difficult problem. These observations may not be equally applicable elsewhere, since the circumstances upon which the observations are based are practically unique to California. Nevertheless, it is apparent that siting of underground nuclear plants in proximity to population centers in California does not appear to be a readily accomplishable task. The siting investigations of this study were not sufficiently specific, or detailed enough, to permit a complete dismissal of the concept; but the results are adequate enough to indicate that it would be difficult to find acceptable sites in proximity to California's population centers.

Some consideration might be given to plant locations which fell within the boundaries of the population demarcation zones in the Central Valley of the State. However, with the possible exception of Sacramento, these cities are too small and/or too broadly dispersed to represent significant centers of electrical loads for a large nuclear power plant of the type considered in this study. Thus, from the standpoint of reducing power transmission distances to significant centers of electrical loads, there is no compelling reason to consider the Central Valley for proximity siting purposes.

6.3 FACILITY VULNERABILITY TO NATURAL AND MAN-MADE HAZARDS

Arguments, both pro and con, have been given with respect to the relative vulnerability of underground nuclear power facilities to natural and man-made hazards. The relative safety of underground plants with respect to flooding, falling objects, and other natural hazards such as fires, tornadoes, hurricanes, seiches, etc., as well as such man-made problems as sabotage or military actions will be reviewed in this portion of the report.

6.3.1 Flooding, Falling Objects, and Other Natural Hazards

All conventional, surface-sited, nuclear plants must be designed to withstand the effects of natural phenomena such as earthquakes, tornadoes, hurricanes, floods, tsunami and seiches without loss of capability to perform their essential safety functions. (10 CFR 50, Appendix A) The design basis for these events must reflect (a) consideration of the "most severe" of the natural phenomena that have been historically reported for the site and surrounding area with sufficient margin for the limited accuracy, quantity, and period of time in which the historical data have been accumulated; and (b) appropriate combinations of these phenomena.

6.3.1.1 Tsunamies and Seiches

Because the technically feasible sites in California for underground facilities are most likely to be found in inland areas, (to be discussed in more detail in Section 6.5 below), tsunamies and seiches are of little concern to this study. However, in any case, there is no apparent reason why underground facilities should be any more vulnerable to such events than surface plants. All modern nuclear plants generally have foundation levels well below grade. Similar design approaches to

mitigation of the effects of tsunamies and seiches (such as dikes and levees) would be used for both surface and underground facilities, as required

6.3.1.2 Tornadoes and Hurricanes

Similarly, tornadoes and hurricanes are events which must be considered for both surface and underground facilities. There is no reason to believe that surface facilities are particularly susceptible to damage from such events, if they have been designed with careful and conservative consideration of the design requirements of 10 CRF 50, Appendix A. Nevertheless, the heavy berm covering or deep rock overburden above the mined-caverns of the underground facilities of this study would make them even less sensitive to tornado and hurricane damage.

6.3.1.3 Missiles and Falling Objects

Similarly, the depths of overburden for the berm-contained and mined-cavern facilities would make them almost insensitive to hazards of high energy missiles or falling objects, either man-made or natural. Substantial effort has been expended by the NRC and utilities in attempts to demonstrate that surface plant containment structures are capable of resisting damage from missiles and/or falling objects such as aircraft; tornado-driven missiles such as high-velocity telephone poles, etc.; turbine blade missiles which might be emitted from a turbine-overspeed accidents, or other objects impacting with high energy. Analyses and experiments have been conducted which indicate that conventionally designed containment vessels are practically invulnerable to such accidents. (For examples, see Ref 6-8, which provides reports on tests and analyses for plant design against external hazards of several kinds, including turbine and tornado-generated missiles, aircraft impacts, etc.) Underground facilities would be no more susceptible to such accidents than surface plants, and probably much less.

6.3.1.4 Flooding

Flooding is a topic which must be considered for both surface and underground facilities, depending upon site selection. Foundation levels are located well below normal surface grades for both berm-contained and surface-sited plants: about 150 ft, for berm-contained plants; and about 50 ft for the Reference surface plant. Careful site selection would be needed for these facilities if expensive flood prevention measures (dikes, levees, etc.) were to be avoided. It should be noted, however, that the principal underground structures in the mined-cavern concept would be located at approximately the same grade level as the external surface of the plant. Moreover, the mined-cavern facilities would probably be located in the foothill areas of the State where flooding would probably not be as great a problem as it might be for a berm-contained plant if it were sited (for example) in the flat lowlands of the Central Valley.

Since facility flooding was a potential area of concern, the State Division of Mines and Geology (DMG) investigated this problem in their geographical/geophysical survey of the State (Ref 6-9). Areas which might be flooded due to both natural causes and to failures, are shown in the composite map of Figure 6-9, which was prepared on the basis of DMG results. Except for the Central Valley region, flooding and inundation can be seen to have only localized impacts.

Again, it should be noted that the indicated areas of Figure 6-9 do not represent absolute exclusionary restrictions. Engineering solutions, such as dikes, levees, pumping, and dewatering systems, etc. are possible which could make specific sites within the indicated areas acceptable. Moreover, the flooding demarcation zones of the figure would apply to surface sited facilities as well as underground structures.

G 8448

Figure 6-9. Areas with Potential for Floods and Dam-Failure Inundation

Other sources of consideration with respect to flooding are (1) groundwater which might infuse into the plant, (2) failure of in-plant water systems, and (3) failure of plant dewatering systems. For the underground facilities, dewatering systems were generally provided for cases of in-plant water system failure or, where groundwater might be a problem. Though these systems added to the expense of the underground facilities, they were designed at fairly nominal cost to handle reasonable volumes of water. If inflow during excavation for the facility were found to be excessive, it might be necessary to abandon a site and seek another location. This could be an important concern for the mined-cavern facilities, where detection of hidden sources of groundwater during site geological surveys is more difficult than it is for the berm-contained plants.

Optimization of dewatering system designs for reliability was beyond the scope of this program. However, in a final design effort, reliability criteria would need to be developed for the designers. Imposition of such criteria would not be expected to impact the economic results of the program substantially. Reliable dewatering systems would essentially eliminate groundwater seepage and in-plant water system failure as a source of concern for either underground or surface facilities.

It is clear, however, that site selection would be a very important factor in reducing plant vulnerability to flooding. With careful selection, there is no evident reason for underground plant vulnerability to this source of problems to be significantly higher than it would be for a surface plant.

6.3.1.5 Fires

The probability of fires is no greater for an underground plant than it would be for a surface facility (Ref 6-10). The extent of damage

resulting from fires is, however, highly dependent on the quality of plant design. Careful attention to fire safety criteria with emphasis on redundancy and separation of critical electrical and control system circuitry, adequate space for fire control activities considering critical equipment items, etc., is required for a facility design which minimizes opportunities for damage from fires.

It has been argued that an underground plant could suffer more damage than a surface facility (from comparable fires) for two reasons: First, if the plant were inadequately designed, it could be somewhat more difficult to use fire suppression equipment from sources outside of the plant; second, underground plants might tend to have more compact layouts than surface plants, which could increase equipment damage from fires. For reasons set forth below, this study concluded that not only the probability, but also the consequence of fires would be similar for both surface and underground plants.

This conclusion is based upon several observations from the CEC program results. First, a conscious effort was made to provide adequate space for fire control activities in equipment layouts for the underground plants. Moreover, redundant fire suppression systems for vital systems contained within the plant are currently required for surface plants and were required for the underground plants of this study as well. Also, the plant designs developed for this study reflect adherence to regulatory requirements for physical separation of vital (safety related) equipment and its related redundant electrical and control circuitry. Thus, it is judged that the consequences of fires within the underground plants of this study would pose no significant additional risks in excess of those associated with fires in surface plants.

6.3.2 Sabotage or Military Actions

Analysis of the susceptibility of a facility to sabotage is extremely complex and often depends on assumptions and judgements for which quantitative support is difficult to provide. A variety of qualitative arguments have been made with respect to the susceptibility of underground plants to sabotage. For example, added protection against sabotage, and terrorist (or other paramilitary) action has been suggested as a benefit for underground siting because access to the underground plant is more readily controlled due to fewer and more consolidated personnel access paths. It has also been suggested that access to critical portions of the underground facility could be more readily denied because of these factors together with the long passageways of the mined-cavern concepts. It has been countered, however, that sabotage would most likely be attempted by employees normally working within the plant. In this case, the benefits claimed for reduced sabotage potential in underground plants could work in reverse; that is, efforts by officials to gain access to the plant for the purpose of terminating or mitigating internal sabotage efforts could be more readily thwarted.

A definitive assessment of the potential for sabotage or terrorist actions against surface or underground plants would be difficult to make. Moreover, it was not possible to quantitatively assess the benefit from underground siting with respect to acts of terrorism and war. Such acts are closely tied to national and international political climates, which can (and do) change frequently. Thus, quantifying the potential risk reduction resulting from underground siting, based on additional protection against acts of terrorism and war, was beyond the scope of this study.

Underground siting, however, offers a unique benefit relative to these types of problems. It is possible to effectively isolate an

underground plant from the external environment if saboteurs or terrorists should gain entrance and control of it. The ability to effectively isolate the radioactive elements of an underground plant from the public should make the facility a less attractive target for saboteurs or terrorists. The underground plant could not be used to hold a large population hostage by threatening to destroy the facility. The psychological terror of such an act would be removed, along with the diminished opportunity for severe consequences. Likewise, if the motivation for such activities were financial blackmail based upon the economic value of the facilities, there would probably be targets which would also be more attractive (and accessible) than an underground nuclear power plant. Thus, the probability and consequences of sabotage or terrorist attacks against underground facilities can be argued to be lower than they would be for comparable surface facilities, even though precise numerical estimates of risk reduction were not made.

6.4 LICENSING/REGULATORY IMPLICATIONS

The NRC, as the principal regulatory agency dealing with the safety of nuclear power plants, has established its basic criteria for judging the licensability of a plant in the Code of Federal Regulations, Title 10, Part 50, Appendix A (10 CFR 50, Appendix A). These regulations are contained in 55 specific criteria, collected under 6 main topical categories. The licensing and regulatory implications of underground nuclear power plants will be discussed below within the framework of potential points of departure from the criteria of 10 CFR 50, Appendix A.

6.4.1 Design Objectives with Respect to Plant Licensability

An explicit goal for the underground facility designs of the CEC program was to develop plant concepts which would, insofar as possible, meet current licensing specifications. Designers were given the goal of preparing a plant with as few departures from the basic guidelines of the

current NRC licensing criteria as possible. That is, the NRC Class-8 Design Basis Accidents (such as the Loss-of-Coolant Accident) were specified as the basis for licensing design considerations for the underground facility. As discussed in Section 4, the Class-9 accident mitigation systems were to be included in the facility design as supplementary systems for the NRC required Engineered Safety Feature systems designed for accident control (such as the Emergency Core Cooling Systems; SCRAM, or reactor-trip systems; etc.). Thus the Class-9 accident mitigation systems were intended to provide an additional safety barrier in the unlikely event of a severe core meltdown accident. A design objective was to develop simple, passive systems which would increase public safety without increasing the probability of Class-9 accidents (by exacerbating an accident, which might have been constrained within Class-8 accident limits in a conventional nuclear power plant, into a more serious core-meltdown (Class-9) accident in the underground plant).

6.4.2 Comparison of Underground Plant Design with Current Licensing Requirements

The 55 licensing criteria of 10 CFR 50, Appendix A have been analyzed below in terms of the six principal categorical groupings for the criteria.

6.4.2.1 Category I - Overall Requirements

Under the general heading of Overall Requirements, 5 criteria have been specified, in 10 CFR 50, Appendix A, which deal with (a) quality control standards; (b) design bases for protection against natural phenomena; (c) fire protection; (d) environmental and missile design requirements (for protection against accident-induced missiles, pipe whipping, impinging fluid-jets, etc.); and (e) inter-facility sharing of structures, systems, and components. In analyzing the

application of these criteria to underground facilities, quality control standards for underground facilities would be unchanged from those of surface plants. Moreover, in this project, design studies were conducted on the basis of single, independent underground power plants. Thus there would be no problems with inter-facility sharing of structures, systems, or components. The criteria covered under (b), (c), and (d) above were discussed in Section 6.3 and conditions in underground plants were shown to be either essentially similar to those of surface nuclear plants, or in some cases somewhat more likely to satisfy the NRC design criteria than a surface plant.

6.4.2.2 Category II - Protection by Multiple Fission Product Barriers

Under this second NRC category, 10 criteria have been specified dealing with maintenance of the prescribed barriers which must be provided in a nuclear power plant against accidental release of radioactivity to the public and plant personnel. These specifications include requirements for: (a) the nuclear design of the reactor; (b) instrumentation and control circuitry for steady state operation of the reactor as well as identification of system conditions in case of accidents; (c) the coolant system of the reactor and the integrity of the coolant pressure boundary, including pipes, pumps, vessels, etc. which must operate under the pressures of the reactor coolant; (d) containment building design; (e) on-site and off-site power sources for plant and safety systems; and (f) control room design for operator safety and plant emergency shutdown.

With the possible exception of the containment building design criterion, essentially all other aspects of the underground facility design requirements included with this second category are identical to those of surface plants. However, the containment building criterion requires that:

"Reactor containment and associated systems shall be provided to establish an essentially leak-tight barrier against the uncontrolled release of radioactivity to the environment and to assure that the containment design conditions important to safety are not exceeded for as long as postulated accident conditions require."
(Criterion 16, 10 CFR 50, Appendix A)

The use of rupture disks as pressure relief valves in the Level-2 and Level-3 accident mitigation systems for the underground facilities may complicate conformance with this criterion. Malfunctioning of a rupture disk under Class-8 accident conditions could be a source of regulatory agency concern. Moreover, the capability of the rupture disks to provide a leak-tight barrier for the long periods of time (on the order of days) which have been predicted to be required for control of Class-8 accidents could also be challenged by regulatory personnel. At the conceptual design level of this study, the reliability of the rupture disks could not be quantified. Some research and development work in this area would almost certainly be necessary during licensing procedures for early underground plants to provide adequately quantified reliability estimates for the rupture disks. However, if problems were identified in the course of such R&D efforts, system reliability could be increased by introducing redundant disks in series into the connecting pipes which penetrate the containment building boundary. Moreover, it is possible that incorporation of the Class-9 accident mitigation systems in the underground facilities might permit some relaxation in Criterion 16, since the stated restriction is against uncontrolled release of radioactivity. The case for relaxation of the criterion would be based upon the fission-product filtering capability of the systems, which would not represent completely uncontrolled release of radioactivity. The probability of significant radioactivity releases to the public from a Class-8 accident in an underground facility would be low, even if the rupture disks were to open unexpectedly during an accident.

Irrespective of conjecture over limitations on the uncontrolled release aspects of Criterion 16, the requirement for long-term leak-tight integrity of the containment structural boundary could be a subject for significant licensing review with underground power plants. With careful attention to system design, it may be possible to limit leakage problems with respect to rupture disk seals on the blowdown pipes penetrating the containment; but a demonstration program with respect to system leak-tightness would almost certainly be required. A research and development program in this area could be required during the licensing procedures for an initial underground facility.

6.4.2.3 Category III - Protection and Reactivity Control Systems

Ten criteria have been incorporated under this category by the NRC. They include design requirements for (a) automatic functioning of protection systems, including requirements for independence, reliability, and testability; (b) physical separation of redundant protection and control systems; and (c) reactivity control system capability, redundancy, and independence. Under the program guidelines of using standardized reactor NSS systems, all systems included under this category for underground nuclear power plants would be expected to be identical to those of surface power plants. No licensability impact is expected from the criteria of this category.

6.4.2.4 Category IV - Fluid Systems

This category includes 17 criteria which deal with: (a) quality, inspectability, and fracture prevention for all the elements of the reactor coolant pressure boundary; (b) provisions for reactor coolant make-up for losses from small leaks in pipes or other elements of the coolant boundary; (c) residual heat removal requirements to prevent overheating of the core from fission-product decay heat following normal

(or accidental) reactor shutdown; (d) emergency core cooling system design and testing; (e) containment heat removal system design, inspection, and testability to prevent excessive buildup of temperature and pressure within the containment structure following a loss-of-coolant-accident (LOCA); (f) containment atmosphere cleanup system design inspectability, and testability to assure that the concentration and radioactivity levels of released fission products from a LOCA can be effectively reduced within the containment boundary.

All of the criteria of this Category IV are related to the nuclear steam supply system for the power plant. In the CEC underground plant study, designers were required to avoid making changes in these systems or in elements of the underground plant boundaries which might impact the applicability of current designs to meet these criteria. As an example, containment volumes were adopted without any substantial changes from the standardized prescriptions of the reactor vendors. Thus, operating characteristics of systems included under Category IV would be expected to remain unchanged in the underground environment. Hence, no licensing problems are expected in connection with the criteria of this category.

6.4.2.5 Category V - Reactor Containment

The eight criteria under this category govern the design and testing procedures for the containment structure, its pressure boundary, and all types of piping systems which penetrate the containment. Overall leakage from the containment structure through its pressure boundaries and any penetrating pipes or lines is typically restricted to no more than 0.1% (by volume) per day for a surface-sited reactor. The criteria of Category V outline the design requirements for the containment and isolation systems for piping penetrations through the containment. They also establish a requirement that the overall system must have its ability to meet the leakage requirements demonstrated on the basis of

tests which would be conducted in the completed structure at the LOCA containment design pressure.

As discussed in connection with the requirements of Criterion 16 of Category II, the containment system in an underground facility would be required to pass a leakage test that included Class-9 accident mitigation system penetrations as well as all other penetrations through the containment boundary. Rupture disk activation was set for pressures and temperatures at least 50% above the LOCA design conditions for the containment building. Testing at the Class-8 accident design pressure should not activate (or compromise the operation of) the rupture disks. However, as suggested in connection with Criterion 16 of Category II, maintaining very low leakage rates for the overall containment system may be more difficult as a result of the large, multiply redundant pipes used in the Class-9 system for pressure control. Leakage to the underground expansion volume/heat-sink regions of the Level-2 and Level-3 systems could not be equated to direct leakage to the atmosphere which could result from penetration leakage in the containment building of a surface plant. Considering the filtering characteristics of the soil and/or rock and the delay times (on the order of days to months for soil and rock respectively) associated with transport of radioactive gases to the ground surface for release to the atmosphere, it is not clear that it would be necessary to prescribe identical standards of leak tightness for the reactor containment structures of surface and underground facilities. Nevertheless, if the leakage criteria of this category were not reexamined by the NRC with the view of considering possible relaxation of the standards for gas leakage in Class-8 accidents in underground plants, then leak-tightness requirements could be a potential area of concern for underground facilities.

6.4.2.6 Category VI - Fuel and Radioactivity Control

The five criteria of this category deal with (a) control of released radioactive materials resulting from normal and off-normal operations; (b) the storage and handling of spent fuel and other radioactive wastes; and (c) requirements for monitoring releases of radioactive materials, if they should occur.

In most respects, procedures and systems for dealing with spent fuel and radioactive waste products from normal plant operations would be substantially the same for both surface and underground facilities. However, in both the berm-contained and mined-cavern facilities spent fuel is stored underground within the auxiliary system structures for the facilities. The secondary containments provided by the underground facility designs, would reduce public risks from accidents included under this category, in comparison with the results of the same scenarios in a surface facility.

6.4.3 Summary of Licensing Implications

Experience has shown that introduction of any new or innovative design concept will result in licensing delays, as the concept is reviewed by the licensing agencies (both state and federal). This observation has been confirmed on innumerable occasions in the history of the development of nuclear power. Thus it is almost inevitable that regulatory impacts would occur during the processes of licensing early underground nuclear power plants.

Some potential areas which might be subjected to regulatory review are the structural integrity of underground caverns, and the domed auxiliary structure of the berm-contained plants; the effect of the Class-9 accident mitigating systems on the integrity of the leak-tight

boundary of the containment structure of the underground facilities; and the testability (if this should be required) of the Class-9 accident design capabilities of the rupture disks for the accident mitigation systems.

As previously discussed (cf Section 4.3), the structural integrity of the underground facilities can probably be demonstrated to the satisfaction of the regulatory agencies, although it may require some time and additional analysis to convince them. The acceptability of rupture disks in the large pipes penetrating the reactor containment for the Class-9 accident mitigation systems may represent another potential regulatory problem. If this were the case, it might be necessary to develop a program to demonstrate the strength and reliability of the rupture disks with respect to the performance of their function. To resolve potential concern over reliability problems for rupture disks, it might be necessary to include more than one disk, in series, in the pipe openings. It might also be necessary to use the backup argument of the effectiveness of soil and rock as filters, in the event of unforeseen release of radioactive gases during a Class-8 accident as a basis for review of the applicability of these criteria to underground facilities.

Therefore, though some licensing issues are almost inevitable, none are recognized as representing insurmountable obstacles to construction and operation of the underground nuclear power plant concepts developed in the course of this study.

6.5 GENERAL AVAILABILITY OF SITING LOCATIONS

One of the expressed concerns about underground nuclear power plant construction in California deals with the adequacy and availability of sites with suitable engineering, geophysical, and population-related characteristics to accommodate a reasonable number of plants. Previous studies of the feasibility of underground nuclear power plants, which had

considered the applicability of the concept within the entire U.S., had concluded that few, if any, suitable siting areas were available in California (e.g., Refs 6-11, 6-12). Other reports, (e.g., Refs 6-13, 6-14) drew conclusions which were in direct contradiction to the above underground nuclear power plant studies. This second pair of reports identified areas of geological interest and suitable engineering material properties at several locations within the State. Thus it was deemed prudent to reexamine the State as part of the CEC program in order to evaluate the general availability and engineering characteristics of areas in the State of California relative to their technical suitability for the siting of underground nuclear power plants.

It was apparent that the rock-sited, mined-cavern concepts placed substantial requirements on the quantity and quality of rock for acceptable siting for several reasons. First, the mined-cavern concept occupies a cross-sectional area of about one-quarter million square feet. In order to accommodate structural and radiological requirements, cavern-to-cavern and cavern-to-surface lineal relationships must be considered in evaluating total underground space requirements. These suggest that a monolithic rock mass, generally free of major cracks and faults, of from 5 to 10 times the facility cross-sectional area, i.e., of the order of 25 to 50 acres, would be needed to adequately accommodate the facility. Secondly, high quality rock must be available to support the excavation and ensure the static and dynamic stability of the large cavern spans (with widths of the order of 100 ft) which are required to accommodate a reactor of the size considered in this study, i.e., 3800 MW of thermal power (1300 MWe). Finally, construction costs are influenced by the physical characteristics of the material being removed in the excavation process.

The berm-contained concepts considered have somewhat less restrictive requirements for site characteristics than those imposed by the mined-cavern concepts. Soil, or soft-rock sites which were underlain

with hard rock at reasonably shallow depths would be preferred for berm-contained facilities. The underlying rock would be used to provide a base for structural foundations.

A survey was conducted by the California Division of Mines and Geology (DMG) to identify the general existence of such siting locations within the State (Ref 6-9). Results of the survey are summarized in this section of the report.

6.5.1 Survey Approach and Data Analyzed

A set of 15 maps, each covering a single parameter of interest, was prepared by the DMG at a large scale (1:1,000,000) based upon the most recent available data. Even at this large scale of map production, one-tenth of an inch is approximately equivalent to one mile. Thus it was impossible to screen exhaustively and examine in detail an area as large as the State of California. At the scale of examination, it would undoubtedly be possible to find good sites in specific locations within areas which were tentatively and generally described as undesirable regions for site considerations. Conversely, bad sites might exist in areas which were generally identified as technically acceptable. The survey conducted was not intended to be a detailed review of specific site locations, nor would a study of this type have been appropriate for this CEC project.

In addition, many factors significant to a final siting decision were not considered in this survey. This includes such elements as proximity to existing transmission facilities suitable topography, or adequate access to siting areas for reasonable construction functions. These factors were considered to be appropriate to a regional siting process, rather than a general evaluation of the entire State.

Siting factors of the type which involved personal value judgements or questions of economics were also excluded. To the greatest extent possible, an attempt was made to utilize straightforward criteria in the DMG survey, which could be evaluated on a technological basis without the requirement of balancing social goals against site impacts, or the cost of construction.

The mapped parameters, which are presented throughout Section 6, were prepared along the lines of general categories of: (a) engineering and geophysical variables (which included natural hazards); and (b) population related factors (including not only population distribution, but also those geographic areas within the State which have been specifically set aside for public use). Though each parameter investigated was mapped individually by the DMG, various combinations of the individual maps have been assembled in this review to delineate composite parametric presentations of particular interest. Thirteen factors were considered by the DMG under two major categories. The first category, associated with Engineering and Geophysical factors, included:

- (a) Quaternary Seismic Fault Zones (cf, Section 6.1);
- (b) Quaternary Volcanic Activity (cf, Section 6.1);
- (c) Flood Potential (cf, Section 6.3);
- (d) Dam Failure Inundation Areas (cf, Section 6.3);
- (e) Known Geothermal Resource Areas;
- (f) Oil and Gas Fields;
- (g) Quaternary and Pliocene Unconsolidated Deposits;
- (h) Mesozoic Granitic Rock;
- (i) Presence of Water;
- (j) Ground Water;
- (k) Earthquake Epicenters: (Significant events occurring over the historical period, 1900-1974; cf, Section 6.1).

The second category was associated with selected population related factors, including (cf, Section 6.2):

- (a) Population;
- (b) National Parks, National Monuments, Indian Reservations, and State Parks;
- (c) Wilderness and Wild River Areas.

Several composite maps derived from the DMG study have been presented in earlier portions of this section of the report. For example, Figure 6-2 presented a combined display of the study's population screening parameter overlain with identified zones of Quaternary volcanic activity and seismic faulting. The significance of demarcation zones for seismic faulting as hazardous regions within the State and their relationship to population was discussed in Sections 6.1 and 6.2 of this report. Zones of known volcanic activity have also been regarded as equivalently hazardous regions on essentially the same basis as fault zones.

Section 6.2 presented the problems associated with siting in proximity to population centers. Criteria for identifying regions with generally high population densities, where nuclear power plant siting might be restricted, were developed for the DMG study. The results of applying this criteria were presented in Figure 6-8, and discussed in detail in Section 6.2. Also included on Figure 6-8 are the other population related factors investigated for the study: a) National parks, National monuments, Indian Reservations and State parks; and b) State and Nationally dedicated wilderness and wild river areas. Because these areas have been dedicated to specific public purposes, they have been treated as restricted regions for nuclear power plant siting in general. In actual site selection processes, these criteria might not be absolutely restrictive. Specific sites would have to be evaluated on their individual merits.

Problems associated with flooding and other natural hazards were reviewed in Section 6.3. Under this topic, Figure 6-9 presented the results of the survey of potential dam-failure inundation areas, and also identified those regions adjacent to rivers with potential for flooding. The Central Valley region was the most significantly affected area of the State in this regard. Although engineering solutions are available for mitigating problems in the geographical areas identified, the regions where flooding or inundation might occur have been considered potential problem areas. Consequently, regions where flooding or inundation might occur have been highlighted as requiring detailed engineering evaluations during site selection processes.

Figure 6-10 presents the combined data on Known Geothermal Resource Areas (KGRA) and oil and gas fields. KGRA's represent regions of potential value as sources of energy supplies. They are also frequently associated with areas of seismic activity. The association of KGRA's with seismic activity would make them relatively unattractive areas for surface or underground power plant siting.

Withdrawal of oil and gas fluids could cause large-scale subsidence problems in fields of this type. This could make demonstration of site acceptability in oil and gas fields difficult for either surface or underground plants. Consequently, KGRA's and oil and gas fields are not considered to be desirable siting areas. Figure 6-10 shows that exclusion of these areas would have an insignificant impact on general site availability within the State.

Regions of California with probable groundwater are shown in Figure 6-11. The potential for groundwater contamination in an underground nuclear power plant in the event of a severe core-meltdown accident was discussed in Section 3.3.3. It was noted that post-accident radionuclide migration rates in groundwater, assuming penetration of the

Figure 6-10. Locations of Known Geothermal Resource Areas and Oil and Gas Fields

Figure 6-11. Locations of Areas of Potential Ground Water

molten core into groundwater bearing strata, are dependent on site specific soil properties and groundwater flow rates. Consequently, whether such contamination would be a problem could only be evaluated on a site specific basis.

However, groundwater could be a problem during plant construction. Berm-contained plants require deep excavations, approximately 100 to 200 ft in depth. The bottom of the excavation would be approximately 400 ft in diameter. If heavy groundwater intrusion occurred during excavation, it could complicate construction procedures greatly and add substantially to the expense of the facility (cf, Section 4.3.1).

For these reasons, areas with groundwater were mapped in Figure 6-11. The map, however, does not necessarily reflect the depth to, nor the quantity or quality of, groundwater. In fact, the areas shown correspond very closely to those shown in Figure 6-12 of Quaternary and Pliocene unconsolidated deposits. Thus the mapped areas are not necessarily regions of exclusion for underground siting. The results have been shown primarily to identify the areas with potential groundwater and not to suggest that all such areas would have serious contamination or construction problems. Decisions with respect to the magnitude of groundwater problems would have to be made on a site-by-site basis.

The total areas of (a) Quaternary and Pliocene unconsolidated deposits, and (b) Mesozoic granitic rocks within the State are presented in Figures 6-12 and 6-13, respectively. The unconsolidated materials can be readily excavated with modern earth moving equipment and would be preferred for berm-contained plant excavations. The mapped regions of Figure 6-12 include alluvium, lake playa, and some sandstone, shale, and gravel deposits. Thus, the regions of Figure 6-12 are generally indicative of suitable conditions for berm-contained siting. The population demarcation zone data has been superimposed on the map to aid

Figure 6-12. Locations of Regions of Unconsolidated Soil Deposits

Figure 6-13. Locations of Regions of Granitic Rocks

the reader in making geographical correlations of the materials with respect to recognizable population centers. From the results presented, it is evident that large areas of unconsolidated deposits are found throughout the State. Thus technically suitable materials for berm-contained facility siting appear to be widely available in California.

The Mesozoic granitic rocks of Figure 6-13 were considered to be the most readily identifiable material of uniform quality for siting the very large underground tunnel and cavern complexes of the mined-cavern concepts. Some areas with other rocks such as the harder limestones, gneiss, dolomite, etc., might also be found to be suitable in extent and quality for construction of mined-cavern facilities. However, since most rocks of these types show greater variation in quality from site-to-site than is common in Mesozoic granitic deposits, the availability and quality of such sites would have to be evaluated on a site-by-site basis. The results shown in Figure 6-13 indicate that most of the more interesting areas of technically acceptable rock lie in the Sierra-Nevadas.

6.5.2 Representative Underground Siting Areas

The combined results of applying the principal engineering, geophysical, and population related factors are presented in Figures 6-14 and 6-15. The nonrestricted areas which show potential for siting of berm-contained facilities are shown in white on Figure 6-14. That is, the regions of Quaternary and Pliocene unconsolidated deposits have been shown in white, while other parameters associated with restrictions on siting activity in particular geographic areas have been shown in hues of gray and black. The remaining white areas, which have not been overlain by one, or more, of the restricted siting regions, represent potential areas for consideration of berm-contained facility sites. It is apparent that most of the technically acceptable areas for berm-contained siting are in the Central Valley and parts of the Eastern Mojave Desert.

Figure 6-14. Composite Identification of Areas of Technically Acceptable Unconsolidated Soil Deposits

Figure 6-15. Composite Identification of Areas of Technically Acceptable Granitic Rocks

Figure 6-14 shows that a substantial unexcluded area is available for consideration. However, based upon consideration of the potential areas of flooding and inundation shown in Figure 6-9, a substantial fraction of the remaining zones of unconsolidated deposits in the Central Valley would have to be specifically evaluated with regard to this feature. Nevertheless, there are substantial areas remaining in which specific searches for site locations could be conducted; especially in the Central Valley and Eastern Desert regions.

Figure 6-15 presents a similar overview of areas of interest for Mesozoic granitic rocks. The granitic rock areas have been shown in white with siting restriction factors presented in various shades of gray and black. Figure 6-15 shows the predominant remaining area to be the foothills of the Sierra-Nevadas -- with some limited areas of potential in the Eastern Mojave Desert. A significant consideration (not explicitly identified in Figure 6-15) is that the identified region of favorable rock conditions contains many high mountains. High mountain areas would be unattractive from the standpoint of accessibility, water availability, construction, and climate. On the other hand, sites in the foothills would be attractive for specific investigations.

Although this review indicates that the area for rock siting may be somewhat less extensive than the regions favorable for berm-contained facilities in soil, the combined regions of potential interest for underground siting are more extensive than some previous investigators had suggested (Refs 6-11, 6-12).

6.6. OVERALL EVALUATION OF UNDERGROUND FACILITY ISSUES

In summary, though underground siting poses more stringent geographical constraints (especially for mined-cavern facilities) than siting for surface nuclear power plants, a substantial area within the

State has been identified as technically feasible for underground siting. Perhaps the most restrictive criterion for excluding land areas in the State is the existence of capable seismic faults. California's coastline is especially notable for seismic faulting influences. Though much of the coastline area would be excluded for surface facilities on the basis of population restrictions, these areas are also generally areas of substantial seismic activity. Considering seismic effects on nuclear power plants, the improved seismic environment offered by underground siting does not appear to be substantial enough to result in a net decrease in plant costs. Savings associated with lessened seismic loads are more than offset by the cost of underground construction.

The two variables of population and seismicity are not independently exclusive within the State. When important siting variables are considered such as the proximity of population centers to seismic hazard zones, availability of adequate supplies of cooling water, accessibility to acceptable soil or rock materials for underground facility construction, the concept of siting underground nuclear power plants in proximity to population centers does not appear to be readily adaptable to conditions in California.

It should be noted, however, that the population densities associated with California's existing nuclear power plants are generally well below the high density demarcation criteria of this study, as shown in Figure 6-6. The concentration of population about Los Angeles, San Francisco, and San Diego will probably continue to dominate the population patterns for the State for many years. Thus, siting locations which are relatively remote in comparison to available sites in many areas of the U.S. are likely to be available within the State now (and in the future). Sites with such low cumulative population densities could be attractive for either surface or underground nuclear power plants. This factor should be recognized when evaluating the relative desirability of underground plant construction concepts.

If good design practices are followed, there is no inherent reason for underground nuclear power plants to be more susceptible to natural or man-made hazards than surface-sited nuclear plants. In fact, the heavy earth cover over the underground structures makes them less susceptible to accidents due to impacts from objects with high velocities and large momentum, hurricanes, tornadoes, etc. Moreover, the reduced potential for high public consequences resulting from releases of radioactivity should make underground plants less attractive targets for saboteurs and terrorists. Hence incentives for sabotage and terrorism should be reduced by siting nuclear power plants underground. Therefore, in general, underground nuclear plants appear to have the potential for an overall reduction in the hazards of natural or man-made events.

From a licensing point of view, the few, but necessary, design innovations required for an underground nuclear power plant would almost certainly lengthen the regulatory process for the earliest plants of this type. The most serious issues would probably be associated with demonstration of the integrity of underground structures and the stability of mined-caverns; and satisfaction of criteria for reactor containment building leak-tightness requirements, under Class-8 accident conditions. No insurmountable technological problems have been identified which would preclude conformance with licensing requirements. However, some specific research and development could be needed prior to licensing of the first underground plants; and some modifications to licensing criteria for specific application to underground plants of the types considered in this study would be desirable.

Finally, contrary to some earlier published opinions, there appear to be substantial areas within the State which could be technically adequate for either berm-contained or mined-cavern facility siting.

REFERENCES

- 6-1. Coffman, J.L. and von Hake, C.A., "United States Earthquakes; 1970," NOAA, Environmental Data Service, Silver Springs, Md., 1972.
- 6-2. The Aerospace Corporation, "Systems Management Support for ERCDC Study of Undergrounding and Berm Containment: Interim Report, Preliminary Program Assessment and Follow-on Program Development," ATR-77(7652-02)-1, August 1977, p. 3-62.
- 6-3. Ibid, p. 3-74.
- 6-4. Dowding, C.H. and Rozen, A., "Damage to Rock Tunnels from Earthquake Shaking," Journal of the Geotechnical Engineering Division, Proceedings of the American Society of Civil Engineers, Vol. 104, No. GTZ, February 1978, p. 184.
- 6-5. Ibid, p. 177.
- 6-6. Ibid, p. 181.
- 6-7. USAEC, "Population Distribution Around Nuclear Plant Sites," WASH-1308, April 1973.
- 6-8. American Nuclear Society, "Proceedings of Topical Meeting on Thermal Reactor Safety," July 31-August 4, 1977, Sun Valley, Idaho, 3 Volumes, pp. 3-441 to 3-544.
- 6-9. California Energy Commission, "Underground Siting of Nuclear Power Reactors: Determination of Site Characteristics and General Availability in California," Preliminary Draft, January 1978.

- 6-10. ARACOR, "Analysis of Public Consequences from Postulated Severe Accident Sequences in Underground Nuclear Power Plants," December 1977, p. 9.
- 6-11. USAEC, "Review of Underground Siting of Nuclear Power Plants," UEC-AEC-740107, January 1974.
- 6-12. Allensworth, V.A., et al, "Underground Siting of Nuclear Power Plants: Potential Benefits and Penalties," Sandia Laboratories (Albuquerque), SAND76-0412/NUREG-0255, 1977.
- 6-13. Ken O'Brien and Associates, "Siting Concepts and Investigations: Task 8, Final Technical Report," Headquarters, Space and Missile Systems Organization, Norton Air Force Base, California, 27 February 1970.
- 6-14. Kammer, W.A. and Watson, M.B., "Locating Underground Nuclear Power Plant Sites in California," The Aerospace Corporation Report No. ATR-73(7278)-2, Volumes I & II, February 1973.

Appendix I

22

Final Specifications and Design Criteria for Berm-Contained and
Mined-Cavern Underground Nuclear Power Plant Design Projects

Appendix IA

Berm-Contained Concept Specifications
(Abstracted from S&L Engineers Final Report)

TABLE A-1 SPECIFICATIONS FOR A STUDY OF BURIED, BERM CONTAINMENT
DESIGN CONCEPTS FOR UNDERGROUND NUCLEAR POWER PLANTS.

	Baseline	Sensitivity
<u>I. Power Plant Characteristics</u>		
Reactor and Thermal Capacity		
Westinghouse RESAR 41 (3800 MW)	X	
General Electric GESSAR (3800 MW)		X
Babcock & Wilcox Standard 241 (3800 MW)		NA
Combustion Engineering CESSAR (3800 MW)		NA
Plant Electrical Capacity, 1300 MW Net	X	NA
Cooling Water Supply Concept - Forced Convection	X	NA
Number of Units Sharing Common Facility	Single	NA
Nuclear Steam Supply Configuration		
o Standard Vendor Configuration	RESAR 414	GESSAR
o Alternative NSS Configuration to Accommodate Dimensional Constraints of Buried Containmentment	NA	NA
<u>II. System/Component Locations</u>		
Nuclear Steam Supply System	Subsurface	NA
Waste Processing and Storage	Subsurface	NA
Turbine Generator	Surface	NA
Main Power Transformer, Auxiliary Transformer, Substation	Surface	NA
Spent and New Fuel Storage and Handling	Subsurface	NA
Control Center	Subsurface	NA
Emergency Diesel Generators	Subsurface	NA

	Baseline	Sensitivity
III. <u>Siting Data</u>		
Soil Description		
Variation with Depth	Soil Model 1	a) Soil Model 2
Soil Moisture	Moist	Dry
Groundwater Specification		
Facility Location with Respect to Water Table	Facility Totally Above Water Table	Water Table at Ground Level
Siesmic Criteria - Surface Peak ²² Acceleration	0.5 g	a) 0.67 g
Rock Characteristics	NA	a) Rock Model 1
Site Remoteness	Central Valley Rural	East Desert Remote
Meteorological Conditions	Humid ⁽¹⁾	Dry ⁽¹⁾
IV. <u>Fission Product Containment Requirements</u>		
Pressure-Time Relationships	B/L*	B/L
Energy-Time Relationships	B/L	B/L
Pressure Management Design Concepts	Level 2	a) Level 1 b) Level 3
Minimum Depth of Containment Cover	50 ft.	a) 25 ft. b) 100 ft.
Surface/Underground Structure Interface Relationships		
Allowable Leakage Rates	By Others	B/L

EXHIBIT IV-1
(CONT.)

	Baseline	Sensitivity
V. <u>Schedule Variations - B/L Plant</u>	Nominal	a) Short (minus 6 mos) b) Long (plus 19 mos)
VI. <u>Reference Surface Power Plant Characteristics</u>		
Power Plant Characteristics	B/L (or equivalent)	NA
System/Component Locations	Standard or Replicated Surface Facility B/L	NA
Siting Data	B/L	NA
Fission Product Containment	Class-8 (DBA)	Level 3

(1) See Page IV-2 for meteorological assumptions

*B/L = Baseline

SOIL AND ROCK SITE DYNAMIC MATERIAL PROPERTIES - BERM CONTAINMENT STUDY

Soil Model No. 1 (Dynamic Properties)

Depth (ft)	Material	Seismic Velocities (ft/sec)		Large Strain Reduction Factors	Moduli (psi)		Poisson's Ratio	Density (lbs/ft ³)
		Longitudinal	Shear		Young's	Shear		
					Seismic/Reduced	Seismic/Reduced		
0-100	Sands, Silts, and Clays	2000	900	.375	5.4 E4/2.0 E4	2.0 E4/0.75 E4	0.37	110
100-200	Weakly Cemented Sandstone	4000	1800	0.6	2.5 E5/1.5 E5	9.2 E4/5.5 E4	0.37	130
200 +	Weakly Cemented Sandstone	5000	2500	0.8	4.9 E5/4.0 E5	1.8 E5/1.5 E5	0.33	135

Soil Model No. 2 (Dynamic Properties)

Depth (ft)	Material	Seismic Velocities (ft/sec)		Large Strain Reduction Factors	Moduli (psi)		Poisson's Ratio	Density (lbs/ft ³)
		Longitudinal	Shear		Young's	Shear		
					Seismic/Reduced	Seismic/Reduced		
0-25	Sand	2400	950	0.4	6.0 E4/2.4 E4	2.1 E4/0.84 E4	.405	108
25-85	Clay	5200	2100	0.2	3.1 E5/6.2 E4	1.1 E5/2.2 E4	.405	120
85-175	Sand	5100	1900	0.45	2.8 E5/1.3 E5	1.0 E5/0.45 E5	.42	128
175 +	Gravel	5600	2100	0.45	3.7 E5/1.7 E5	1.3 E5/0.57 E5	.42	134

SOIL AND ROCK SITE DYNAMIC MATERIAL PROPERTIES - BERM CONTAINMENT STUDY

Rock Model No. 1

Depth (ft)	Material	Seismic Velocities (ft/sec)		Large Strain Reduction Factors	Moduli (psi)		Poisson's Ratio	Density (lbs/ft ³)
		Longitudinal	Shear		Young's	Shear		
					Seismic/Reduced	Seismic/Reduced		
0-10	Sands, Silts, and Clays	2000	900	.375	5.4 E4/2.0 E4	2.0 E4/0.75 E4	0.37	110
10-50	Shale	5500	3200	1	8.0 E5/8.0 E5	3.2 E5/3.2 E5	0.25	145
50 +	Shale	7100	4100	1	14.0 E5/14.0 E5	5.6 E5/5.6 E5	0.25	155

**SOIL AND ROCK SITE STATIC AND DYNAMIC
MATERIAL PROPERTIES – UNDERGROUND NUCLEAR PLANT
STUDY – SOIL MODEL NO. 1**

Depth (ft)	Material	Seismic Velocities (ft/sec)		Large Strain Modulus Reduction Factors	Poisson's Ratio	Dry Density (lb/ft ³)	Other Static Properties	Other Dynamic Properties
		Longitudinal	Shear					
0-100	Sands, Silt, and Clays	2000	900	.375	0.37	110	$k_o = 0.5$ $\phi = 34^\circ$ $w(1) = 8\%$ $w(2) = 15\%$ $k = 10^{-3}$ cm/sec $SG = 2.67$ $n = 0.34$ $KTH(1) = 1.0$ $KTH(2) = 1.2$	$G = 1000 k_2 \sqrt{\sigma'_m}$ $k_{2max(1)} = 47$ $k_{2max(2)} = 69$ $\lambda = \lambda_{average} \left(\frac{2500}{\sigma'_v} \right)^{0.2}$ λ from Seed & Idriss * average curves at 0.07% shear strain
100-200	Weakly Cemented Sandstone	4000	1800	0.6	0.37	130	$k_o = 0.5$ $\phi = 38^\circ$ $w(1) = 5\%$ $w(2) = 8\%$ $k = 10^{-4}$ cm/sec $SG = 2.65$ $n = 0.2$ $KTH(1) = 1.5$ $KTH(2) = 1.7$	$G = 1000 k_2 \sqrt{\sigma'_m}$ $k_{2max(1)} = 123$ $k_{2max(2)} = 170$ $\lambda = \lambda_{average} \left(\frac{2500}{\sigma'_v} \right)^{0.2}$ λ from Seed & Idriss average curves at 0.02% shear strain
200-360	Weakly Cemented Sandstone	5000	2500	0.8	0.33	135	$k_o = 0.5$ $\phi = 41^\circ$ $w(1) = 5\%$ $w(2) = 8\%$ $k = 10^{-4}$ cm/sec $SG = 2.65$ $n = 0.18$ $KTH(1) = 1.65$ $KTH(2) = 1.90$	$G = 1000 k_2 \sqrt{\sigma'_m}$ $k_{2max(1)} = 172$ $k_{2max(2)} = 235$ $\lambda = \lambda_{average} \left(\frac{2500}{\sigma'_v} \right)^{0.2}$ λ from Seed & Idriss average curves at 0.007% shear strain

* Seed, H.B. and I.M. Idriss, "Soil Moduli and Damping Factors for Dynamic Response Analyses" Earthquake Engineering Research Center Report No. EERC 70-70, 1970.

See Exhibit IV-6 for Notes and Identification of Symbols.

**SOIL AND ROCK SITE STATIC AND DYNAMIC
MATERIAL PROPERTIES – UNDERGROUND NUCLEAR PLANT
STUDY – SOIL MODEL NO. 2**

Depth (ft)	Material	Seismic Velocities (ft/sec)		Large Strain Modulus Reduction Factors	Poisson's Ratio	Dry Density (lb/ft ³)	Other Static Properties	Other Dynamic Properties
		Longitudinal	Shear					
0-100	Sand	2400	950	0.4	.405	108	$k_o = 0.5$ $\phi = 38^\circ$ $w_{(1)} = 8\%$ $w_{(2)} = 15\%$ $k = 10^{-3}$ cm/sec $SG = 2.65$ $n = 0.35$	$G = 1000 k_2 \sqrt{\sigma'_m}$ $k_{2max(1)} = 105$ $k_{2max(2)} = 153$ $\lambda = \lambda_{average} \left(\frac{2500}{\sigma'_v} \right)^{0.2}$ $\lambda_{average}$ from Seed & Idriss curves at 0.06% shear strain
25-85	Clay	5200	2100	0.2	.405	120	$k_o = 0.5$ $S_u = 6600$ psf $C_u = 6600$ psf $\phi_u = 0^\circ$ $w_{(1)} = 20\%$ $w_{(2)} = 25\%$ $L.L. = 35\%$ $P.L. = 25\%$ $k = 10^{-7}$ cm/sec $SG = 2.70$ $n = 0.29$	$\frac{G}{S_u \max(1)} = 2988$ $\frac{G}{S_u \max(2)} = 3113$ λ from Seed & Idriss curves at 0.2%

See Exhibit IV-6 for Notes and Identification of Symbols

* See Reference, bottom of Exhibit IV-4.

EXHIBIT IV-5

**SOIL AND ROCK SITE STATIC AND DYNAMIC
MATERIAL PROPERTIES – UNDERGROUND NUCLEAR PLANT
STUDY – SOIL MODEL NO. 2 (CONT.)**

Depth (ft)	Material	Seismic Velocities (ft/sec)		Large Strain Modulus Reduction Factors	Poisson's Ratio	Dry Density (lb/ft ³)	Other Static Properties	Other Dynamic Properties
		Longitudinal	Shear					
85-175	Sand	5100	1900	0.45	.42	128	$k_o = 0.5$ $\phi = 42^\circ$ $v_{(1)} = 5\%$ $v_{(2)} = 12\%$ $k = 10^{-3}$ cm/sec $SG = 2.65$ $n = 0.23$	$G = 1000 k_2 \sqrt{\sigma'_m}$ $k_{2max(1)} = 139$ $k_{2max(2)} = 193$ $\lambda = \lambda_{average} \left(\frac{2500}{\sigma_v} \right)^{0.2}$ $\lambda_{average}$ from Seed & Idriss curves at 0.05% shear strain
175-360	Gravel	5600	2100	0.45	.42	134	$k_o = 0.5$ $\phi = 45^\circ$ $v_{(1)} = 5\%$ $v_{(2)} = 10\%$ $k = 10^{-1}$ cm/sec $SG = 2.65$ $n = 0.19$	$G = 1000 k_2 \sqrt{\sigma'_m}$ $k_{2max(1)} = 123$ $k_{2max(2)} = 167$ $\lambda = \lambda_{average} \left(\frac{2500}{\sigma_v} \right)^{0.2}$ $\lambda_{average}$ from Seed & Idriss curves at 0.05% shear strain

See Exhibit IV-6 for notes and identification of symbols

SOIL AND ROCK SITE STATIC AND DYNAMIC MATERIAL PROPERTIES - UNDERGROUND NUCLEAR PLANT STUDY

ROCK MODEL NO. 1

Depth (ft)	Material	Seismic Velocities (ft/sec)		Large Strain Modulus Reduction Factors	Poisson's Ratio	Dry Density (lb/ft ³)	Other Static Properties	Other Dynamic Properties
		Longitudinal	Shear					
0-10	Sands, Silts, and Clays	2000	900	.375	0.37	110	$k_o = 0.5$ $\phi = 34^\circ$ $w(1) = 8\%$ $w(2) = 15\%$ $k = 10^{-3}$ cm/sec $SG = 2.67$ $n = 0.34$	$G = 1000 k_2 \sqrt{\sigma'_m}$ $k_{2max(1)} = 47$ $k_{2max(2)} = 69$ $\lambda = \lambda_{average} \left(\frac{2500}{\lambda_v} \right)^{0.2}$ $\lambda_{average}$ from Seed & Idriss curves at 0.07% shear strain
10-50	Shale	5500	3200	1	0.25	145	$SG = 2.60$ $n = 0.11$	$G = \rho V_s^2$ $\lambda = 0.04$
50 +	Shale	7100	4100	1	0.25	155	$SG = 2.60$ $n = 0.05$	$G = \rho V_s^2$ $\lambda = 0.03$

*See Reference, bottom of EXHIBIT IV-4

SOIL AND ROCK SITE STATIC AND DYNAMIC MATERIAL PROPERTIES

UNDERGROUND NUCLEAR PLANT STUDY

SOIL MODEL NO.'s 1 and 2 - ROCK MODEL NO. 1

Notes and Symbols

k_o	= coefficient of earthpressure at rest
ϕ	= angle of internal friction
$w(1)$	= water content, percent (water table at 360 ft)
$w(2)$	= water content, percent (water table at surface)
k	= coefficient of permeability, cm/sec
SG	= specific gravity
n	= porosity
G	= shear modulus, psf
V_s	= shear wave velocity ft/sec
σ'_m	= effective mean pressure, psf
λ	= damping
ρ	= mass density
σ'_v	= effective overburden pressure, psf
$k_{2max}(1)$	= value of k_2 at very low strain (water table at 360 ft)
$k_{2max}(2)$	= value of k_2 at very low strain (water table at surface)
L.L.	= liquid limit, percent
P.L.	= plastic limit, percent
S_u	= undrained shear strength, psf
C	= cohesion, psf
$(G/S_u)_{max}(1)$	= maximum (G/S_u) for water table at 360 ft.
$(G/S_u)_{max}(2)$	= maximum (G/S_u) for water table at surface

Static and dynamic properties given for material between the depth 0 to 100 ft. in Soil Model No. 1 were determined assuming the layer consisted predominately of sands and silty sands.

$KTH(1)$	= coefficient of thermal conductivity, BTU/hr/ft ² /°F/ft (water table at 360 ft)
$KTH(2)$	= coefficient of thermal conductivity, BTU/hr/ft ² /°F/ft (water table at surface)

Variation of Shear Modulus with Shear Strain for Sands and Gravel

This data from Seed, H.B. and I.M. Idriss, "Soil Moduli and Damping Factors for Dynamic Response Analyses", Earthquake Engineering Research Center Report No. EERC 70-70, 1970.

Damping Ratios (Sands and Gravel)

See Reference, Exhibit IV-7

Shear Modulus at Shear Strain γ
Shear Modulus for $\gamma \approx 3 \times 10^{-4}$ percent

Typical Reduction of Shear Modulus with Shear Strain (Clays)

See Reference, Exhibit IV-7

Damping Ratios (Clays)

See Reference, Exhibit IV-7

COMPACTED BACKFILL PROPERTIES AND REQUIREMENTS

UNDERGROUND NUCLEAR PLANT STUDY

Granular Zone	Cohesive Zone	Gravel Zone	Clay and Clay Shale Zone
$\gamma_d = 122 \text{ pcf}$ $\phi = 42^\circ$ $W(1) = 10\%$ $W(2) = 16\%$ $k_o = 0.4$ $k = 10^{-4} \text{ cm/sec}$ $k_{2\max(1)} = 63$ $k_{2\max(2)} = 87$ $\frac{\lambda(\text{average})}{\lambda(\text{compacted})} = 1.1$ $Dr \geq 85\% \text{ ASTM D2049}$ $Cr \geq 95\% \text{ ASTM D1557}$	$\gamma_d = 115 \text{ pcf}$ $S_u = 4500 \text{ psf}$ $C_u = 4500 \text{ psf}$ $\phi_u = 0^\circ$ $W(1) = 15\%$ $W(2) = 18\%$ $k_o = 0.6$ $k = 10^{-7} \text{ cm/sec}$ $LL = 35\%$ $PL = 25\%$ $(G/S_u)_{\max(1)} = (G/S_u)_{\max(2)} = 3000$ $Cr \geq 95\% \text{ ASTM D1557}$	$\gamma_d = 128 \text{ pcf}$ $\phi = 44^\circ$ $W(1) = 7\%$ $W(2) = 10\%$ $k_o = 0.3$ $k = 10^{-1} \text{ cm/sec}$ $k_{2\max(1)} = 125$ $k_{2\max(2)} = 170$ $\frac{\lambda(\text{average})}{\lambda(\text{compacted})} = 1.1$ $Dr \geq 85\% \text{ ASTM D2049}$ $Cr \geq 95\% \text{ ASTM D1557}$	$\gamma_d = 125 \text{ pcf}$ $\phi_u = 20^\circ$ $S_u = 4500 \text{ psf}$ $C_u = 3000 \text{ psf}$ $W(1) = 10\%$ $W(2) = 15\%$ $k_o = 0.5$ $k = 10^{-6} \text{ cm/sec}$ $(G/S_u)_{\max(1)} = (G/S_u)_{\max(2)} = 3000$ $Cr \geq 95\% \text{ ASTM D1557}$

Notes and Symbols

γ_d = dry density, psf
 ϕ = angle of internal friction
 ϕ_u = undrained angle of internal friction
 k_o = coefficient of earth pressure
 k = coefficient of permeability, cm/sec
 LL = liquid limit, percent
 PL = plastic limit, percent
 C_u = cohesion, psf
 S_u = undrained shear strength, psf

G = shear modulus, psf
 $W(1)$ = water content, percent, for water table at 360 ft. depth
 $W(2)$ = water content, percent, for water table at ground surface
 $k_{2\max(1)}$ = maximum k_2 for water table at 360 ft. depth
 $k_{2\max(2)}$ = maximum k_2 for water table at ground surface
 $(G/S_u)_{\max(1)}$ = maximum (G/S_u) for water table at 360 ft. depth
 $(G/S_u)_{\max(2)}$ = maximum (G/S_u) for water table at ground surface
 Dr = relative density
 Cr = degree of compaction

ne

Appendix IB

Mined-Cavern Concept Specifications
(Abstracted from UDC Final Report)

TABLE 3-1

FINAL SUMMARY OF PROJECT SPECIFICATIONS

	<u>Baseline</u>	<u>Sensitivity</u>
<u>I. Power Plant Characteristics</u>		
Reactor and Thermal Capacity		
Westinghouse RESAR 414 (3800 MW)	X	
General Electric GESSAR (3800 MW)		(1)
Babcock and Wilcox Standard 241 (3800 MW)		(2)
Combustion Engineering CESSAR (3800 MW)		(2)
Plant Electrical Capacity, 1300 MW Net	X	NA
Cooling Water Supply Concept-Mechanical Evaporative	X	NA
Number of Units Sharing Common Facility	Single	NA
Nuclear Steam Supply Configuration		
°Standard Vendor Configuration	RESAR 414	(1) GESSAR
°Alternative PWR Configuration to Accommodate Constraints Underground Containment	NA	YES
<u>II. System/Component Locations</u>		
Nuclear Steam Supply System	Subsurface	NA
Waste Processing and Storage	Subsurface	NA
Turbine Generator and Main Transformer	Subsurface	Surface
Spent and New Fuel Storage and Handling	Subsurface	NA
Control Center	Subsurface	NA
Emergency Diesel Generators	Subsurface	NA
<u>III. Siting Data</u>		
Rock Description	Rock Model 1 (3)	(a) Rock Model 2 (3) (b) Rock Model 3 (3)
Groundwater Specifications	Dry	Dewater
Seismic Criteria - Surface Peak Acceleration (4)	0.5g	(a) 0.3g (b) 0.67g
Topography	Hillside (40% slope)	Flat

	<u>Baseline</u>	<u>Sensitivity</u>
Site Remoteness	Rural Area- Central Valley	Remote Area - East Desert
Meteorological Conditions	Central Valley (Table 3-4)	East Desert (Table 3-4)
<u>IV. Fission Product Containment Requirements</u>		
Pressure-Time Relationships	(6)	NA
Energy-Time Relationships	(6)	NA
Accident Management Design Concepts	Design Level 2	(a) Design Level 1 (b) Design Level 3 (c) BWR Design Level 3
Minimum Depth of Containment Cover	50 ft. (7)	1000 ft.
Surface/Underground Structure Interface Relationships		
Allowable Leakage Rates	0.1% per day	NA
<u>V. Schedule Variations</u>		
	Nominal	(a) Short (b) Long
<u>VI. Reference Surface Plant (PWR)</u>		
Power Plant Characteristics	Baseline (or Equivalent)	NA
System/Component Locations	Standard or Replicated Surface Facility	NA
Siting Data	(8)	NA
Fission Product Containment	Class 8 (DBA)	NA
Lifetime	40 years	NA
Condenser Pressure	3.5 inches Hg	NA

(1) BWR concept is a major design alternative for which plant layout must be prepared.

(2) No plant layouts are required.

(3) See Rock Models in Table 3-3.

(4) Subsurface seismic criteria specified in Appendix V.

(5) See meteorological conditions in Table 3-4.

(6) Determined in course of study by another contractor.

(7) Use optimal construction depth if greater than 50 ft.

(8) Site Geology: Baseline-Soil, Soil Model 1 (Table 3-5)

Seismic: 0.5g

Meteorological: Table 3-4

Groundwater: NA
Remoteness: Central Valley
Rural

TABLE 3-3

ROCK MODEL SPECIFICATIONS

<u>Rock Model No. 1</u>													
<u>Overburden:</u>	38' deep and consists of decomposed granodiorite.												
<u>Rock Mass:</u>	Coring to 1,000' revealed the following: Hard, dense, coarse grained, light gray granodiorite. The rock mass has been cut by two small diatase dikes and five very small aplite dikes. They are not zones of weakness. Seismic survey shows 1,100/22,000 ft./sec. Interface at 65' which correlates with the depth of granodiorite weathering.												
<u>Material Properties:</u>	The rock properties from 65' to the total depth are relatively uniform and yield the following average properties:												
	<table> <tr><td>Specific Gravity</td><td>2.77</td></tr> <tr><td>Percent Porosity</td><td>0.73</td></tr> <tr><td>Schmidt Rebound No.</td><td>48.5</td></tr> <tr><td>Compressive Strength, psi</td><td>22,470</td></tr> <tr><td>Young's Modulus, psi x 10⁶</td><td>6.5</td></tr> <tr><td>Tensile Strength, psi</td><td>1,030</td></tr> </table>	Specific Gravity	2.77	Percent Porosity	0.73	Schmidt Rebound No.	48.5	Compressive Strength, psi	22,470	Young's Modulus, psi x 10 ⁶	6.5	Tensile Strength, psi	1,030
Specific Gravity	2.77												
Percent Porosity	0.73												
Schmidt Rebound No.	48.5												
Compressive Strength, psi	22,470												
Young's Modulus, psi x 10 ⁶	6.5												
Tensile Strength, psi	1,030												
<u>Fracture Frequency:</u>	38'-65' highly fractured, weathered, FF=4" at 38' grading to 12" at 65' RQD = 52 65'-91' moderately fractured, FF=18" RQD=75; 91'-1,000' moderately fractured, FF=30" avg RQD = 97.												
<u>Tectonic Stress Field:</u>	38'-91', average horizontal stress is 70% of the vertical stress. 91'-1,000', average horizontal stress is 120% of the vertical stress.												

<u>Rock Model No. 2</u>	
	13' deep and consists of well-graded sand, gravel, and occasional rocks of boulder size.
	Coring to 1,000' revealed the following: Hard, dense, fine to medium grained, medium gray diabase gabbro.
	The uphole seismic survey shows 1,200/16,500 ft./sec. Interface at 21' deep which corresponds to the depth of gabbro weathering.

The rock properties from 21' to 1,000' are comparatively uniform and yield the following average properties:

Specific Gravity	3.010
Percent Porosity	0.30
Schmidt Rebound No.	42
Compressive Strength, psi	< 47,500
Young's Modulus, psi x 10 ⁶	8.6
Tensile Strength, psi	2,170

21'-111' moderately fractured, FF=6" RQD = 06;
111'-1,000' relatively intact, FF=30" RQD=100.

21'-111', average horizontal stress is 60% of the vertical stress.

111'-1,000', average horizontal stress is about 150% vertical stress.

Rock Model No. 3

63' of silts, sandy gravels, and boulders;
occasional outcrops of base material throughout area.

Fine crystalline salmon red granite. The rock mass is highly fractured and evidence of weathering and alteration exists to a depth of 145'.

Uphole seismic velocity surveys show 1,200 /9,000 ft./sec. Interface at 63' and 9,000/14,400 ft./sec. Interface at 145' which corresponds to the overburden and weathering depths described above.

The rock properties determined for the rock mass to the total depth of 1,000' average as follows:

	63'-145'	145'-498'	498'-1,000'
Specific Gravity	2.637	2.648	2.665
Percent Porosity	1.45	0.87	0.45
Schmidt Rebound No.	48.3	---	56.8
Compressive Strength, psi	7,600	11,700	26,600
Young's Modulus, psi x 10 ⁶	7.3	8.0	10.0
Tensile Strength, psi	640	870	1,230

63'-145', highly fractured and weathered, fracture frequency grades from ~3" to ~6" at 145', RQD = 58%.

145'-1,000' - average fracture frequency = 6", RQD = 71%.

63'-145', average horizontal stress is 40% of the vertical stress.

145'-498', average horizontal stress is about 60% of the vertical stress.

498'-1,000', average horizontal stress is about 110% of the vertical stress.

TABLE 3-4
SITE METEOROLOGICAL CONDITIONS

	<u>Central Valley</u>	<u>East Desert</u>
A. <u>Normal Operation</u>		
1) Dry Bulb Temp., F	100	110
2) Wet Bulb Temp., F	70	75
3) Relative Humidity, %	22	19
B. <u>Emergency Operation (Ultimate Heat Sink)</u>		
1) Dry Bulb Temp., F	105	115
2) Wet Bulb Temp., F	75	78
3) Relative Humidity, %	22	19

TABLE 3-5
STATIC AND DYNAMIC PROPERTIES – SOIL MODEL NO. 1*

Depth (ft)	Material	Seismic Velocities (ft/sec)		Large Strain Modulus Reduction Factors	Poisson's Ratio	Dry Density (lb/ft ³)	Other Static Properties	Other Dynamic Properties
		Longitudinal	Shear					
0-100	Sands, Silts, and Clays	2000	900	0.375	0.37	110	$k_o = 0.5$ $\phi = 34^\circ$ $w_{(1)} = 8\%$ $w_{(2)} = 15\%$ $k = 10^{-3}$ cm/sec $SG = 2.67$ $n = 0.34$	$G = 1000 k_2 \sqrt{\sigma'_m}$ $k_{2max(1)} = 47$ $k_{2max(2)} = 69$ $\lambda = \lambda_{average} \left(\frac{2500}{\sigma'_v} \right)^{0.2}$ $\lambda_{average}$ curves at 0.07% shear strain
100-200	Weakly Cemented Sandstone	4000	1800	0.6	0.37	130	$k_o = 0.5$ $\phi = 38^\circ$ $w_{(1)} = 5\%$ $w_{(2)} = 8\%$ $k = 10^{-4}$ cm/sec $SG = 2.65$ $n = 0.2$	$G = 1000 k_2 \sqrt{\sigma'_m}$ $k_{2max(1)} = 123$ $k_{2max(2)} = 170$ $\lambda = \lambda_{average} \left(\frac{2500}{\sigma'_v} \right)^{0.2}$ $\lambda_{average}$ curves at 0.02% shear strain
200-360	Weakly Cemented Sandstone	5000	2500	0.8	0.33	135	$k_o = 0.5$ $\phi = 41^\circ$ $w_{(1)} = 5\%$ $w_{(2)} = 8\%$ $k = 10^{-4}$ cm/sec $SG = 2.65$ $n = 0.18$	$G = 1000 k_2 \sqrt{\sigma'_m}$ $k_{2max(1)} = 172$ $k_{2max(2)} = 235$ $\lambda = \lambda_{average} \left(\frac{2500}{\sigma'_v} \right)^{0.2}$ $\lambda_{average}$ curves at 0.007% shear strain

Symbols:

- k_o = coefficient of earthpressure at rest
- ϕ = angle of internal friction
- $w_{(1)}$ = water content, percent (water table at 360 ft)
- $w_{(2)}$ = water content, percent (water table at surface)
- k = coefficient of permeability, cm/sec
- SG = specific gravity
- n = porosity
- G = shear modulus, psf
- σ'_m = effective mean pressure, psf
- λ = damping
- σ'_v = effective overburden pressure, psf
- $k_{2max(1)}$ = value of k_2 at very low strain (water table at 360 ft)
- $k_{2max(2)}$ = value of k_2 at very low strain (water table at surface)

* Adapted from Reference (1).