12
2/24/92 Jm ①

PNL-7991
UC-500

A Report for Westinghouse Hanford Company

**Analysis and Decision
Document in Support of
Acquisition of Steam Supply
for the Hanford 200 Area**

February 1992

Prepared for the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Operated for the U.S. Department of Energy
by Battelle Memorial Institute

PNL-7991

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor Battelle Memorial Institute, nor any of their employees, makes **any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.** Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or Battelle Memorial Institute. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PACIFIC NORTHWEST LABORATORY
operated by
BATTELLE MEMORIAL INSTITUTE
for the
UNITED STATES DEPARTMENT OF ENERGY
under Contract DE-AC06-76RLO 1830

Printed in the United States of America

Available to DOE and DOE contractors from the
Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831;
prices available from (615) 576-8401. FTS 626-8401.

Available to the public from the National Technical Information Service,
U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

ANALYSIS AND DECISION DOCUMENT IN SUPPORT
OF ACQUISITION OF STEAM SUPPLY FOR THE
HANFORD 200 AREA

D. R. Brown	R. W. Reilly
K. K. Daellenbach	D. L. Shankle
T. F. Grant ^(a)	S. A. Smith
P. L. Hendrickson	S. A. Weakley
D. C. Kavanaugh	T. A. Williams

February 1992

Prepared for
the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Richland, Washington 99352

(a) Human Affairs Research Center
Seattle, Washington

MASTER

JP
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

EXECUTIVE SUMMARY

The U.S. Department of Energy (DOE) is now evaluating its facility requirements in support of its cleanup mission at Hanford. One of the early findings is that the 200-Area steam plants, constructed in 1943, will not meet future space heating and process needs. Because the 200 Area will serve as the primary area for waste treatment and long-term storage, a reliable steam supply is a critical element of Hanford operations.

This Analysis and Decision Document (ADD) is a preliminary review of the steam supply options available to the DOE. The ADD contains a comprehensive evaluation of the two major acquisition options: line-item versus privatization. It addresses the life-cycle costs associated with each alternative, as well as factors such as contracting requirements and the impact of market, safety, security, and regulatory issues.

Specifically, this ADD documents current and future steam requirements for the 200 Area, describes alternatives available to DOE for meeting these requirements, and compares the alternatives across a number of decision criteria, including life-cycle cost.

DOE has currently limited the ADD evaluation alternatives to replacing central steam plants rather than expanding the study to include alternative heat sources, such as a distributed network of boilers or heat pumps. Thirteen project alternatives were analyzed in the ADD. One of the alternatives was the rehabilitation of the existing 200-East coal-fired facility. The other twelve alternatives are combinations of 1) coal- or gas-fueled plants, 2) steam-only or cogeneration facilities, 3) primary or secondary cogeneration of electricity, and 4) public or private ownership.

Major conclusions developed as the result of this analysis are as follows:

- DOE construction of a gas-fired, steam-only plant may be more cost-effective than rehabilitation of the 200-East coal-fired facility (L-017).
- Privatization of a steam-only plant does not appear to be in the best interests of DOE from an economic standpoint.
- Government-build cogeneration does not appear economically feasible unless a special power sales arrangement can be worked with the Bonneville Power Administration (BPA).
- A privately-owned and operated cogeneration plant onsite has the potential to provide DOE with steam at a cost substantially below the life-cycle cost of steam provided through rehabilitation of the 200-East plant.

- The best electricity market for Hanford-cogenerated electricity appears to be in the Pacific Southwest rather than in the Pacific Northwest.
- If a privatized cogeneration facility is developed at Hanford, it is likely to be gas-fired.
- DOE's existing contracting authority appears adequate for development of a privatized cogeneration facility.

CONTENTS

EXECUTIVE SUMMARY	iii
1.0 INTRODUCTION	1.1
1.1 PURPOSE OF THE DOCUMENT	1.1
1.2 STRUCTURE OF THE REPORT	1.2
2.0 STEAM REQUIREMENTS	2.1
2.1 PEAK DEMAND	2.2
2.2 MONTHLY STEAM DEMAND	2.3
2.3 ANNUAL ENERGY REQUIREMENTS	2.3
2.4 STEAM CHARACTERISTICS	2.4
2.5 SYSTEM RELIABILITY	2.4
2.6 CONDENSATE RETURN	2.5
3.0 STEAM PLANT ALTERNATIVES	3.1
3.1 ACQUISITION OPTIONS	3.1
3.1.1 Government-Build	3.1
3.1.2 Privatization	3.2
3.1.3 Existing Steam Sources	3.2
3.2 TECHNICAL OPTIONS	3.3
3.2.1 Fuel Type	3.3
3.2.2 Steam-Only Versus Cogeneration	3.3
3.2.3 Electrical Plant Size	3.3
3.3 PROJECT ALTERNATIVES	3.4
4.0 NON-COST ASPECTS OF THE ACQUISITION PROCESS	4.1
4.1 CONTRACTING AUTHORITY	4.1
4.1.1 The Private Sector's Likely Contract Needs	4.1

4.1.2	DOE's Authority to Meet a Bidder's Contract Needs	4.3
4.1.3	Summary of Contracting Issues	4.3
4.2	REAL ESTATE AND EASEMENTS	4.5
4.2.1	DOE's Long-Term Leasing Authority	4.5
4.2.2	Easement Requirements	4.6
4.3	ENVIRONMENTAL AND PERMITTING REQUIREMENTS	4.6
4.3.1	NEPA Requirements	4.7
4.3.2	Environmental Permit Requirements	4.7
4.3.3	Impact of the Tri-Party Agreement	4.8
4.4	SECURITY REQUIREMENTS	4.8
4.5	BUILDING AND SAFETY CODES	4.9
4.6	MARKET FACTORS	4.9
4.6.1	Fuel Costs and Supply	4.10
4.6.2	Market for Power from a Cogeneration Facility	4.11
4.6.3	Power Transmission Costs	4.14
4.6.4	PURPA Requirements	4.14
5.0	LIFE-CYCLE COST ANALYSIS	5.1
5.1	SPECIFIC OBJECTIVES FOR THE STEAM PLANT LIFE-CYCLE COST ANALYSIS	5.1
5.2	DESCRIPTION OF THE ANALYTIC APPROACH	5.2
5.2.1	Life-Cycle Cost Methodology	5.2
5.2.2	Cost and Performance Estimates	5.2
5.2.3	Key Assumptions and Inputs	5.2
5.3	200-AREA REHABILITATION VERSUS GOVERNMENT NEW CONSTRUCTION	5.4
5.4	GOVERNMENT-BUILD COGENERATION OPTIONS	5.5

5.5	PRIVATE STEAM-ONLY OPTIONS	5.6
5.6	PRIVATELY-OWNED-AND-OPERATED COGENERATION PLANTS	5.7
5.7	LIFE-CYCLE COST SENSITIVITY ANALYSIS	5.8
5.7.1	Electricity Prices and Escalation Rates	5.9
5.7.2	Natural Gas Prices and Escalation Rates	5.10
5.7.3	Private and Government Discount Rates	5.12
5.7.4	Change in Contract Length	5.12
5.8	LIFE-CYCLE COST SUMMARY	5.14
6.0	CONCLUSIONS	6.1
7.0	REFERENCES	7.1
APPENDIX A	- DISCUSSION OF THE LEGAL CONTEXT OF THE ACQUISITION OF A STEAM SUPPLY FOR THE HANFORD 200 AREA	A.1
APPENDIX B	- DOE'S LONG-TERM LEASING AUTHORITY	B.1
APPENDIX C	- PERMIT REQUIREMENTS	C.1
APPENDIX D	- FUEL PRICE AND AVAILABILITY	D.1
APPENDIX E	- MARKET AND PRICES FOR ELECTRIC POWER	E.1
APPENDIX F	- PUBLIC UTILITIES REGULATORY POLICIES ACT OF 1978 (PURPA)	F.1
APPENDIX G	- LIFE-CYCLE COST ANALYSIS	G.1

FIGURES

4.1	Power Sales Options for Cogenerator on the Hanford Site	4.12
5.1	Government-Build Steam-Only Options	5.4
5.2	Government-Build Cogeneration Options	5.6
5.3	Private Steam Plant Options	5.7
5.4	Private-Build, Coal-Fired Cogeneration Options	5.8
5.5	Private-Build, Gas-Fired Cogeneration Options	5.9
5.6	Levelized Costs for Privately-Owned, Gas-Fired Primary Cogeneration as a Function of Initial Price and Long-Term Price Escalation	5.10
5.7	Levelized Costs for Privately-Owned, Gas-Fired Secondary Cogeneration as a Function of Initial Price and Long-Term Price Escalation	5.11

TABLES

2.1	Peak Steam Demand	2.2
2.2	Projected Peak Steam Demand by Month	2.3
2.3	Annual Steam Production Requirements	2.4
3.1	Description of Project Alternatives	3.5
4.1	Permit Requirements for Steam Supply Project	4.8
4.2	Expected Fuel Cost and Escalation	4.11
5.1	Economic Assumptions	5.3
5.2	Alternative Natural Gas Price Results for Privately-Owned Plants	5.11
5.3	Alternative Natural Gas Price Results for Government-Owned Steam Plant	5.12
5.4	Alternative Discount Rate Results	5.13
5.5	Costs of Three 10-Year Contract Periods	5.13

1.0 INTRODUCTION

After almost 50 years of defense-related production of nuclear materials, the mission at Hanford has changed to site restoration. The U.S. Department of Energy, Richland Field Office (DOE-RL) estimates that 30-plus years will be required to decontaminate site facilities and remediate environmental damage.

DOE is now evaluating its facility requirements in support of the cleanup mission. One of the early findings is that the 200 Area steam plants, constructed in 1943 and partially upgraded in 1952, will not meet future needs. Because the 200 Area will serve as the primary area for waste treatment and long-term storage, a reliable 200-Area steam supply is a critical element of Hanford operations.

DOE is currently analyzing alternative approaches for securing the steam supply. One alternative is to rehabilitate the existing steam plant. The other alternative is to purchase steam from a private vendor. Because the 200 Area is in the center of the large, remote Hanford Site, importing the steam from an external private vendor is not feasible. The steam-generating facility would necessarily be constructed on the Site.

Given this requirement, any arrangement with the private sector would involve some form of "privatization" or public/private partnership. Under this approach, DOE would offer a long-term lease of land, an agreement to supply necessary services (water, emergency services, road and rail access, etc.), and a steam procurement agreement. In return, the private vendor would construct, own, operate, and maintain the plant within the 200 Area, selling the steam to DOE.

1.1 PURPOSE OF THE DOCUMENT

This Analysis and Decision Document (ADD) is a preliminary review of the steam supply options available to DOE. The ADD contains a comprehensive evaluation of the two major acquisition options, line-item versus privatization. It addresses the life-cycle costs associated with each alternative, as well as factors such as contracting requirements, the impact of market factors, safety, security, and business risk.

Specifically, the ADD will

- document current and future steam requirements for the 200 Area
- describe the alternatives available to DOE for meeting these requirements
- compare the alternatives across a number of decision criteria including life-cycle cost

- provide background materials that will be useful in preparing the "privatization" Request for Proposals (RFP) and in evaluating the responses to it.

The ADD is a preliminary document intended to support the DOE decision process. As the project matures, DOE will select an acquisition approach and develop additional data for specific needs. Over time, the validity of assumptions made here may change. It may be useful to maintain the ADD as a "living document" throughout the project, upgrading it as necessary to serve as a primary resource for explaining and defending the project within DOE and in discussions with the Office of Management and Budget (OMB). It could also serve as a critical element of the formal project proposal that will likely be required by DOE under its proposed approach to privatization implementation.

Because the ADD is designed as a decision aid for DOE, the information and analysis are presented from the federal perspective. Aspects of privatization that are important to a prospective private sector bidder but which have no impact on the government decision are sometimes noted in the discussions, but they are not evaluated.

The document was prepared by Pacific Northwest Laboratory (PNL) for the Westinghouse Hanford Company (WHC). The requirements were defined and most of the site-related data were developed through a cooperative effort on the part of PNL, WHC, Kaiser Engineers Hanford (KEH), and DOE-RL. DOE-RL provided overall direction and oversight.

1.2 STRUCTURE OF THE REPORT

This report contains two major elements. The body of the report presents a concise, comprehensive evaluation of the steam acquisition options. It is supported by a larger body of appendices that describe the basis for the information employed in the evaluation.

Section 2 of the ADD describes the current situation and documents steam requirements of the 200 Area. Section 3 describes the steam acquisition options available to DOE and the alternative configurations that must be analyzed to evaluate those options. Section 4 discusses non-cost issues related to the DOE decision. Section 5 reports on the life-cycle costs of 13 acquisition and configuration alternatives, as well as several sensitivity studies developed to understand the impact of important economic inputs that cannot be firmly determined. Section 6 integrates the findings of Sections 4 and 5 and provides a series of conclusions.

The appendices include more detailed discussions of the following: contracting authorities (Appendix A); real estate leasing authority (Appendix B); environmental and permitting requirements (Appendix C); fuel cost and supply (Appendix D); market and prices for electric power (Appendix E); information on the potential impact of the Public Utilities Regulatory Policies Act (PURPA) on the project (Appendix F); and life-cycle cost documentation (Appendix G).

As noted previously, DOE is evaluating only two acquisition alternatives: the line-item (L-017) for major rehabilitation of the existing plant and the "privatization" option. The evaluation conducted here, however, includes a matrix of procedural and technical options in order to provide DOE with a reasonably reliable estimate of privatization economics. These options are described in Section 3.1 and 3.2. There are two drivers for this larger analysis:

- OMB Circular A-104 requires that DOE analyze the life-cycle cost of government construction of the same plant configurations considered under privatization. This will ensure that the privatization option is more cost-effective than government implementation of the same plant configuration. Hence, the ADD includes government new-construction scenarios, even though the DOE government option will be L-017 rather than construction of an entirely new plant. An A-104 analysis will be required at a later stage of the privatization process. The ADD is only a preliminary cost-benefit analysis to examine a range of possible alternatives and to determine project feasibility.
- In constructing a steam plant on the Hanford Site, the private sector has a number of options, including generation of steam only, or cogeneration of steam and electricity. Other technical options include fuel type and plant size. A range of these options is covered to understand what approach is likely to be most cost-effective for the private sector and, subsequently, what the government life-cycle cost of purchased steam is likely to be. This approach will help DOE understand whether a steam-only or a cogeneration facility is likely to be more attractive to prospective bidders and what the facility primary fuel is likely to be. This information will help DOE design the acquisition activity and prepare environmental documentation.

2.0 STEAM REQUIREMENTS

The DOE cleanup mission at Hanford will likely continue for at least the next 30 years, with waste treatment and storage activities centered in the 200 Area. The schedule of major milestones is documented in the Hanford Federal Facility Agreement and Consent Order (commonly known as the Tri-Party Agreement), which is a negotiated cleanup settlement between DOE, the U.S. Environmental Protection Agency (EPA), and the Washington State Department of Ecology. A reliable steam supply is a necessary resource if DOE is to meet its milestones under the Tri-Party Agreement (the Hanford Federal Facility Agreement and Consent Order).

There are currently two steam generating plants in the 200 Area, one in the 200-West Area and the other in the 200-East Area. Both of these plants were constructed in 1943. Two additional boilers were added to the 200-East Area plant in 1952. The plants are connected by a steam tie-line, completed in 1990, that allows steam to be transported in either direction.

The 200-East and -West plants currently supply steam to existing 200 Area administrative buildings and some process activities through an above-ground distribution system. Process uses include the 200-East Area evaporator and process steam in B-Plant. Another important use of the steam is to drive back-up turbine motors for exhaust fans in some of the existing 200 Area process facilities.

Several new waste treatment facilities are currently planned for construction in the 200 Area. Because these facilities will treat nuclear wastes, DOE plans to include steam (or other heating) plants in each one to eliminate potential health and environmental problems of recovering steam condensate or waste water from nuclear facilities. Hence, the new steam plant will likely serve only existing facilities and any new non-nuclear facilities that are constructed. The future configuration of the 200 Area is not finalized, however, and the new steam facility must be designed to facilitate possible expansion in future years.

DOE has currently limited the evaluation alternatives to replacement steam plants rather than expanding the study to include alternative heat sources such as a distributed network of heat pumps. This decision was reached for two reasons:

- the need to have steam available for the back-up exhaust fans and other process activities
- the desire to use the fly ash from the (coal-fired) steam plant as a raw material for grout for radioactive waste storage activities.

DOE is now re-evaluating that decision, making a preliminary assessment of the cost of retrofitting exhaust fans and other process functions to other back-up

drives. The results of that analysis will not be available in time for consideration in this ADD and, therefore, must be compared later against the economic results provided here.

The use of fly ash for grout could also be a substantial benefit provided by the new or retrofit steam plant. The ash specifications have not yet been defined, however, and it is not certain that the ash will be suitable for grout. Also, the fly ash produced from a coal-fired steam plant of the sizes considered in this study provides only 20-40% of the amount that will be needed onsite. It is likely that the grout operation will require a single source of fly ash to keep the quality of ash consistent in this critical application. Hence, the LCC analysis provided in Section 5 and Appendix G contains no economic benefit for ash utilization.

2.1 PEAK DEMAND

Estimates of future steam requirements are based upon historical records of boiler generation in the 200 Area. (These data were documented in the RFP associated with the May 25, 1990, Commerce Business Daily notification of DOE's intent to procure steam.) For analysis in this ADD, these historical data were modified to accommodate 1) steam losses and uses internal to the existing steam plant and 2) load reductions due to various 200-Area processes that are scheduled to be terminated. Buildings housing those process activities will still need to be heated, however, until they are decontaminated and decommissioned, which is likely to be many years in the future. Hence, future steam use is expected to remain the same for space heating, with only minimal steam use expected for process use. Table 2.1 provides a profile of estimated future steam requirements on a normal winter day and an extreme winter day.

TABLE 2.1. Peak Steam Demand

Area	Normal Winter Day Peak (1,000 lbm/hr)	Extreme Winter Day Peak (1,000 lbm/hr)
200 West, Heating	85	110
200 East, Heating	85	110
200 East, Processing	63	0
Total	233	220

Source: U.S. Department of Energy, 1990.

These requirements are net delivery into the steam tie-line and do not consider internal plant utilization and plant losses. Note that the peak demand on a normal winter day can actually be greater than the peak demand on an extreme winter day. The reason for this is that, on extreme winter days, processing activities can be curtailed to ensure adequate steam for space heating.

This approach minimizes the capacity requirements for the plant. The normal winter peak demand would be met by using a multi-boiler plant capable of meeting the extreme winter peak demand with even one boiler unit out of service. The curtailment of process steam would only be needed during an unplanned winter outage of one of the boiler units.

Rehabilitation of the 200-East steam plant will provide adequate capacity to meet the 220,000 lbm/hr demand as a design maximum. In order to ensure comparability between alternative plant configurations, steam and cogeneration plants analyzed in this ADD were also configured to that same capacity.

2.2 MONTHLY STEAM DEMAND

An indication of the likely monthly variation in peak steam demand is presented in Table 2.2. Although little heating is required in the summer months, the steam lines are kept charged to minimize corrosion; to power the back-up exhaust fans (if needed); and for processing, service water, and ancillary building needs.

TABLE 2.2. Projected Peak Steam Demand by Month

<u>Month</u>	<u>Peak Steam Demand (1,000 lbm/hr)</u>
January	233
February	224
March	199
April	190
May	123
June	114
July	106
August	106
September	118
October	148
November	199
December	233

Source: U.S. Department of Energy, 1990.

2.3 ANNUAL ENERGY REQUIREMENTS

The amount of steam delivered annually will vary based upon weather variations (the demand is largely driven by space heat requirements) and by the changing process uses within the 200 Area.

Over the life of the plant, steam supply requirements are expected to change to reflect changes in the facilities that use steam. Under a low-use scenario, older administrative and other facilities are assumed to be decom-

missioned and replaced by new, more efficient ones. In addition, it is assumed that steam will not be required for some process uses (back-up exhaust fans). Under a high-use scenario, few facilities are decommissioned, and steam continues to be required in older buildings.

The range of expected gross annual steam demand is 500-1300 million pounds per year. Because the low-use scenario depends on acquisition of future construction funds, which are difficult to obtain in today's federal budgeting environment, future steam requirements will likely be closer to the high-use scenario. Therefore, the economic analyses conducted in this ADD assume 1100 million pounds per year gross steam demand.

The best estimate for high- and low-use scenarios is presented in Table 2.3.

TABLE 2.3. Annual Steam Production Requirements

<u>Area</u>	<u>Low</u> <u>(1,000,000 lbm/yr)</u>	<u>High</u> <u>(1,000,000 lbm/yr)</u>
200 West	254	423
200 East	<u>338</u>	<u>676</u>
Total	592	1099

Source: U.S. Department of Energy, 1990

2.4 STEAM CHARACTERISTICS

Steam delivered to the steam tie-line is required to be 225 psig at a temperature of 456°F (approximately 60°F superheat). Variations of $\pm 5\%$ in pressure and temperature are allowed for periods not to exceed one hour. Temperature and pressure must be within $\pm 1\%$ of specifications at all other times.

2.5 SYSTEM RELIABILITY

DOE will require substantial reliability, probably provided through redundant systems. The reliability specifications have not yet been defined. For the purposes of this analysis, the plant (all configurations) is assumed to be a multi-boiler plant capable of supplying extreme winter peak demand with one boiler system inoperative as described in Section 2.1 above.

DOE will also require assurance that fuel curtailment will not render the steam plant inoperative. In this analysis, this assurance is provided by assuming a 60-day onsite coal reserve for coal-fired plants and a 30-day onsite fuel oil supply for gas-fired plants.

2.6 CONDENSATE RETURN

The 200-Area distribution systems currently return no condensate to the steam plants, but rather send the condensate to the wastewater systems. This approach results in substantial energy loss (lost enthalpy in the condensate) as well as a substantial cost for treatment of make-up water. The reason for this approach is that most of the buildings are involved in nuclear processes, and the added cost of protective isolation systems and continuous monitoring renders condensate return to the steam plant economically infeasible. For this same reason, all alternatives considered in the ADD do not have condensate return systems. Make-up water will need to be provided for all of the steam used in the 200-Area distribution system because there will be no recycled water or condensate return.

3.0 STEAM PLANT ALTERNATIVES

The 200-East Area facility contains 5 coal-fired stoker boilers and 1 oil-fired boiler (for back-up), with a total rated capacity of 390,000 lbm/hr (WHC 1990). The 200-West Area facility contains 4 coal-fired stoker boilers, with a total rated capacity of 260,000 lbm/hr. These boilers provide steam for production processes, for building heat, and to power back-up exhaust fans in processing facilities.

In 1983, a comprehensive study of the 200 Area was conducted to evaluate the existing steam-generating facilities. This study concluded that the steam-generating facilities, which have operated continuously since being placed into service in 1943, have deteriorated and are no longer reliable. The study also concluded that rehabilitating the existing system is more cost-effective than developing a new steam-generating facility.

The coal-fired boilers have deteriorated to such an extent that they can now each be operated at a maximum capacity of 65,000 lbm/hr, compared with their design capacity of 80,000 lbm/hr. Maintenance outages have been increasing in length and severity, with some outages lasting more than one month.

It is clear that retaining the existing steam-generating system results in unacceptable reliability levels and very high maintenance costs. Therefore, the 30-year DOE cleanup mission requires a rehabilitated or new steam-generating facility.

3.1 ACQUISITION OPTIONS

Two realistic steam supply options are open to DOE: government-build and privatization. A third option, use of steam from other Hanford sources, has been eliminated from consideration. All three options are briefly described below.

3.1.1 Government-Build

In 1983, DOE initiated a capital upgrade program to rehabilitate and upgrade the existing 200 Area heating system by constructing a steam tie-line between 200-East and 200-West, making safety improvements to the 200-East and 200-West plants, constructing new boilers in the 200-East Area, and overhauling the existing 200-East boilers. The next phase of the program is to construct new boilers in the 200-East Area, then overhaul the existing plant. This approach would result in the operation of boilers with a total steam-generating capacity of 202,000 lbm/hr (net). Under this option, the 200-West steam plant would be closed. Note that for the balance of this document, "L-017" will be employed to represent the full series of future 200-East steam plant rehabilitation line items.

A second government-build alternative is to construct an entirely new steam plant. This option has already been evaluated and rejected in favor of L-017.

The new-construction option is being analyzed here, however, to provide consistent treatment of all possible options under more recent assumptions. This treatment is also consistent with the approach specified in OMB Circular A-104.

Under both government-build options, the site Operating and Engineering Contractor (OEC) would prepare all preliminary studies and designs. Specifications and final design would be prepared by the site Engineer-Constructor, and the construction would be bid to a private contractor. Once completed, the plant would be operated and maintained by the site OEC.

3.1.2 Privatization

The use of private capital to build steam-generating facilities is the other option open to DOE. Potentially there are two approaches here: Shared Energy Savings (SES) legislation and classic "privatization."

The SES legislation allows the federal government to contract with a private vendor to improve the efficiency of an existing government-owned facility, using the vendor's capital. Under this scenario, the vendor is paid back using a portion (hence, the "shared" in Shared Energy Savings) of the energy purchase funds that are saved through the improved efficiency of the facility. The SES legislation has been reviewed with respect to a privatized Hanford steam supply and may not be applicable because the facility that results would not be government-owned. The evaluation of the SES option is summarized in Appendix A of this ADD.

Under the classic privatization approach, DOE could issue a request for proposal (RFP) for purchase of steam from a private vendor, offering a companion long-term lease for federal land upon which to build the plant. The private contractor would then construct, own, operate, and maintain the steam plant, selling steam to the federal government through a long-term contract or on an annual appropriation basis.

State and local governments have used privatization for many years. Over the last decade the federal government's use of privatization has increased dramatically--primarily within the Department of Defense, which has been granted substantial enabling legislation. DOE is now beginning to recognize the benefits of privatization and is considering various privatized projects across its many installations.

3.1.3 Existing Steam Sources

There are currently two major possible sources for steam on the Hanford Site besides the dedicated steam plants. These sources are 1) WNP-2, a nuclear power plant operated by the Washington Public Power Supply System (WPPSS) to generate electricity, and 2) the Fast Flux Test Facility (FFTF), a nuclear reactor designed to test reactor fuels. Both of these have been eliminated from consideration for the following engineering and economic reasons. WNP-2 is subject to maintenance and other outages and cannot provide the continuous steam required. The FFTF (which currently does not produce steam but could be

so modified) operates intermittently and its future operation is doubtful. In addition, both of these potential sources are located substantial distances from the 200 Area, making steam delivery impractical.

3.2 TECHNICAL OPTIONS

This section describes the steam plant configurations that are being analyzed. As described earlier, the immediate DOE choices are whether to rehabilitate the 200-East steam plant or to purchase steam from a private vendor who constructs a plant in the 200 Area through a "privatization" arrangement. The evaluation of the private sector approach requires consideration of a number of private configuration options, including fuel type, steam-only versus cogeneration of steam and electricity, and electrical plant size. The development of these alternatives is described below. All of the options are configured to meet the steam requirements outlined in Section 2.

3.2.1 Fuel Type

One of the major determinants of feasibility and cost is fuel type. Coal and natural gas are the fuels most likely to provide the quantity and quality of steam required in a cost-effective manner. Oil-fired and electric boilers are not considered because they have higher operating costs than natural gas or coal, making them extremely unlikely to result in the most cost-effective private alternative. Other fuels, such as agricultural or municipal wastes, are not considered here because of their supply uncertainty and high capital cost.

3.2.2 Steam-Only Versus Cogeneration

If DOE were to issue an RFP for steam production, two rather different sets of proposals could likely result. One set would propose to produce only steam for sale to DOE; the other set would propose to cogenerate both steam for delivery to DOE and electrical power for sale to BPA or utilities over the power grid. Both of these possibilities need to be analyzed to determine the likely price of steam from a private facility.

3.2.3 Electrical Plant Size

In a steam-only situation, plant size would probably correspond closely to DOE's peak steam demand. In the cogeneration situation, however, a range of plant sizes is feasible. The facility could be designed and operated to meet the steam demand as its primary goal, with only limited cogeneration of electricity (hereafter called "secondary cogeneration"). Alternatively, the facility could be designed and operated as an electrical generating plant, with steam produced only as a by-product (hereafter called "primary cogeneration"). In the latter case, the plant could be significantly larger than in the former. Again, a range of electrical plant sizes needs to be analyzed to understand the economics of power production and the likely price of steam offered to the government.

3.3 PROJECT ALTERNATIVES

Because the realistic options open to DOE are either L-017 or steam purchase, the analysis conducted here needs to provide only information to help choose between the two. Hence, the suite of alternatives under consideration need not cover the range of possible alternatives (which is infinite), but only a reasonable range of alternatives likely to cover steam prices DOE might be offered. Likewise, all potentially applicable specific technologies (e.g., pulverized coal versus stoker-fed) need not all be evaluated; only those configurations a private contractor is likely to employ in supplying steam to the government.

A thorough evaluation of technical and acquisition options results in 13 combinations, presented in Table 3.1. The first alternative is L-017 as described in Section 3.1.1. The other twelve alternatives are combinations of 1) coal- or gas-fueled plants, 2) steam or cogeneration facilities, 3) primary or secondary generation of electricity, and 4) public or private ownership.

To meet reliability specifications, three independent units are specified for each plant, with each unit capable of producing 110,000 lbm/hr (net) to the distribution system. A facility with this capacity could deliver the extreme winter day peak demand with one unit out of service. For all the boiler units, water-tube boilers with economizers are employed. Coal-fired steam generation is based on a stoker combustion system with flue gas desulfurization. Coal-fired cogeneration is based on a steam Rankine cycle with an extraction/condensing turbine. Combined-cycle technology (Brayton topping cycle with steam Rankine extraction/condensing turbine bottoming cycle) is employed for gas-fired cogeneration systems. Secondary cogeneration systems are configured for one cogeneration unit and two boiler units. Primary cogeneration systems are configured with two cogeneration units and one boiler unit.

These alternatives represent various combinations of four basic 110,000 lbm/hr (net) units: coal-fired stoker boiler, gas-fired boiler, coal-fired steam Rankine cogeneration, and gas-fired combined-cycle cogeneration. These are likely, but not the only, technologies that could be employed by the 13 alternatives presented here.

Electricity output varies across cogeneration options. For analysis purposes, coal-fired cogeneration plants are configured to generate 15MW (secondary cogeneration) and 30MW (primary cogeneration). Gas-fired cogeneration plants are configured to generate 48.7MW and 97.4MW, respectively. These electricity production levels are design ratings, assuming no steam extraction. In actual operation, steam extracted for Hanford use would reduce plant output below these levels.

The secondary cogeneration options shown in Table 3.1 are the minimum cogeneration options, given the constraints of reliability and steam demand discussed above. A multitude of primary options are available where the power-to-steam ratio is greater than that of the secondary options. The logical one chosen here is to leave two cogeneration units and a spare steam unit. If it is cost effective under the primary options to cogenerate power, then the

TABLE 3.1. Description of Project Alternatives

1. Upgrade current 200-East steam plant (L-017, L-094, L-009 and L-020)
two new 101,000 lbm/hr (net) coal-fired stokers
(existing boilers as backup)
2. Coal-fired steam plant with private ownership
three 110,000 lbm/hr (net) coal-fired stokers
3. Coal-fired steam plant with government ownership
three 110,000 lbm/hr (net) coal-fired stokers
4. Coal-fired secondary cogeneration plant with private ownership (15MW_e)^(a)
one 110,000 lbm/hr (net) coal-fired steam Rankine cogeneration unit^(b)
two 110,000 lbm/hr (net) coal-fired stokers
5. Coal-fired primary cogeneration plant with private ownership (30MW_e)^(a)
two 110,000 lbm/hr (net) coal-fired steam Rankine cogeneration units^(b)
one 110,000 lbm/hr (net) coal-fired stoker
6. Coal-fired secondary cogeneration plant with government ownership (15MW_e)^(a)
one 110,000 lbm/hr (net) coal-fired steam Rankine cogeneration unit^(b)
two 110,000 lbm/hr (net) coal-fired stokers
7. Coal-fired primary cogeneration plant with government ownership (30MW_e)^(a)
two 110,000 lbm/hr (net) coal-fired steam Rankine cogeneration units^(b)
one 110,000 lbm/hr (net) coal-fired stoker
8. Gas-fired steam plant with private ownership
three 110,000 lbm/hr (net) gas-fired boilers
9. Gas-fired steam plant with government ownership
three 110,000 lbm/hr (net) gas-fired boilers
10. Gas-fired secondary cogeneration plant with private ownership (48.7MW_e)^(a)
one 110,000 lbm/hr (net) gas-fired combined-cycle cogeneration unit^(b)
two 110,000 lbm/hr (net) gas-fired boilers
11. Gas-fired primary cogeneration plant with private ownership (97.4MW_e)^(a)
two 110,000 lbm/hr (net) gas-fired combined-cycle cogeneration units^(b)
one 110,000 lbm/hr (net) gas-fired boiler
12. Gas-fired secondary cogeneration plant, government ownership (48.7MW_e)^(a)
two 110,000 lbm/hr (net) gas-fired combined-cycle cogeneration units^(b)
two 110,000 lbm/hr (net) gas-fired boilers
13. Gas-fired primary cogeneration plant with government ownership (97.4MW_e)^(a)
two 110,000 lbm/hr (net) gas-fired combined-cycle cogeneration units^(b)
one 110,000 lbm/hr (net) gas-fired boiler

(a) Electrical output is maximum capacity, net of internal uses, assuming no steam extracted for delivery to DOE. Actual output would necessarily be less.

(b) 110,000 lbm/hr (net) at full extraction.

market constraints of electric revenue rates, demand for power, capital availability, etc. will limit the size of the cogeneration facility. It is our intent to show that the primary cogeneration option is economically feasible under certain conditions in comparison to the L-017 alternative, not to define the optimal size of the cogeneration facility.

4.0 NON-COST ASPECTS OF THE ACQUISITION PROCESS

The purpose of this document is to describe the two steam acquisition approaches available to DOE, and identify and evaluate the important differences between them. In general, life-cycle cost will be the determinant for the decision unless there are significant other differences that override the cost advantage.

This section provides an evaluation of the non-cost aspects of the acquisition process. Specific inputs are established for determining the life-cycle cost of each alternative. Overriding "other" differences, if any, are identified.

In general, the government-build approach is well practiced and understood, and there are no real procedural concerns. Most of the discussion, then, will be concerned with how privatization would be implemented.

In the following sections each of the alternatives is evaluated across a number of perspectives. These perspectives include the following:

- contracting authority
- real estate leases and easements
- environmental and permitting requirements
- security
- building and safety codes
- market factors.

4.1 CONTRACTING AUTHORITY

Privatization is a new activity for DOE, and it cannot be assumed that DOE currently has the authority to enter into the kind of agreements necessary for a successful privatization project. Two facets of contracting authority may be important: DOE's authority to enter into long-term contracts and to accept contingent liability. Without these authorities, privatization projects (especially steam-only configurations) may fail to attract private-sector partners, or the contract terms offered by private-sector bidders may be too costly to the government. DOE's contracting authority is summarized in this subsection and discussed at length in Appendix A.

4.1.1 The Private Sector's Likely Contract Needs

Private-sector contractors (as well as their third-party funding source, if they have one) will require substantial evidence that they can recover their investment in a reasonable payback period. DOE is relying on its long history at Hanford, documentation of the 30-year cleanup mission, and its willingness

to offer the prospective bidder a "sole source" guarantee for steam demand in the 200 Area as such evidence. These are soft guarantees, however, and provide the contractor no legal recourse if the Site were to close or if the 200-Area steam demand disappeared for some unforeseen reason.

Two likely private-sector bid configurations in this project are the following:

- The bidder may propose to build a facility whose sole purpose is to generate steam for DOE, with revenues coming only from DOE. The bidder will likely seek a guaranteed long-term contract and will charge a steam price that will recoup his investment over the term of the contract. Even if contract renewals are expected by all parties, the payback will need to occur over the period of the first contract because no follow-on contracts can be guaranteed. Thus, the initial price DOE is expected to pay for steam will likely vary inversely with the term of the initial contract.
- The bidder may propose to build a cogeneration facility with steam sales to DOE and electricity sales to BPA or a utility. In this case, only part (probably a small part) of the bidder's revenue will come from DOE. A long-term contract for steam purchase may, thus, not be necessary. However, continued operation of the plant outside the period for which DOE requires steam depends upon an available water supply, road and rail access, emergency services, and/or other DOE-provided support activities for which the cogenerator will expect an enforceable guarantee. This guarantee may be part of the steam purchase contract or part of the real estate lease (see Section 4.2). In the former case, the cogenerator would need to recover his entire investment within the contract period, since continued operation of the cogeneration facility beyond contract expiration cannot be guaranteed. In the latter case, it probably will not be important to the contractor to recover his investment over the life of his steam purchase contract with DOE.

Another element that may be required by bidders as part of a long-term contract is a termination clause--a guarantee that the contractor would recover his unamortized capital costs from the government (the portion of the total capital cost attributable to meeting the DOE steam need) in the event that DOE terminates the contract before the contractor has fully recovered his capital investment. Providing such a guarantee is a "contingent liability" for DOE--a liability contingent upon the occurrence of some action, which in this case is elimination of steam demand in the 200 Area. Some bidders may discount the likelihood of a DOE termination and not require the termination clause; others may require such a clause. Even if the termination clause is not required, a risk premium will undoubtedly be assigned to such a contract, and the cost of steam to DOE will rise accordingly. Again, in the case of a cogeneration facility, where a long-term contract may not be required, the termination clause will likely be less critical than it will for a steam-only plant developed for the purpose of selling steam to DOE.

4.1.2 DOE's Authority to Meet a Bidder's Contract Needs

The Anti-Deficiency Act generally prohibits any federal agency from entering a long-term contract to pay for goods or services unless the agency obligates enough funds in that contract year to cover the total government obligation for the life of the contract. Having to meet this requirement, of course, would negate one of the primary reasons for DOE to use privatization--payments that coincide with the realization of benefits.

Through Section 161(u)(2) of the Atomic Energy Act (AEA) of 1954, however, DOE has overriding authority to enter into multi-year contracts for the purchase of services or supplies without first-year obligation of the entire contract amount. DOE's Office of General Counsel has interpreted Section 161(u)(2) to authorize DOE to enter into contracts for up to 10 years of product or service purchases with subsequent renewal options for reasonable periods of time.

Review of this legislation and related Congressional hearings appears to suggest, however, that the authorized contract term may actually be limited to only 5 years of purchases of the supplies or services, beginning with the initial delivery from the contractor, and 10 years overall (with the additional 5 years to be available for plant construction and related activities if needed). This discrepancy needs to be resolved before the privatization RFP is issued. The contract may be renewed multiple times, although it is not clear whether this renewal period has a ceiling of 5 or 10 years. The extension period should also be resolved before the RFP is issued.

DOE's current statutory authority to enter into long-term contracts could be augmented by new legislation. A bill that was considered by Congress during 1991 and will likely be reconsidered in 1992 would authorize DOE to enter into contracts for the procurement of products and services that are necessary to support waste cleanup and modernization activities at DOE facilities. The initial term of such contracts would be for a maximum period of 30 years and could include options for two 10-year extensions. It appears that steam would be among the types of products and services that this bill would authorize DOE to purchase by means of long-term contract.

The AEA also gives DOE the authority to incur a contingent liability through agreement to a termination clause in its contract.

4.1.3 Summary of Contracting Issues

The contracting issues are different for prospective steam-only and cogeneration bidders.

Steam-Only Contract Issues

Since the steam-only bidder depends entirely upon revenues from DOE, he/she will initially seek a contract length that is at least as long as the economic life of the proposed steam plant (30 to 40 years). The bidder will also seek a contractual guarantee, that if the government chooses to terminate for its convenience, he/she will be recompensed for the unamortized capital investment. As these desirable contract attributes are eroded, the bidder will

increase the premium charged for added risk, increasing the price of steam to DOE. At some point the risk becomes too great, and the bidder will refuse to bid on the government RFP.

It is not clear when that no-go point is reached. The prospective bidder's decision process has many other inputs, including alternative investment opportunities. While it is possible that the contractor will rely upon soft guarantees, it is more likely that he will require that his investment be recouped during the term of the contract and that the contract contain a termination clause guaranteeing repayment of capital.

If the initial contract length is constrained to the first 5 or 10 years following initial delivery of services, the contractor will likely require that all capital costs be recovered during those 5 or 10 years. As a result, the cost of steam will be very high in the first 5 or 10 years with, presumably, a lower cost of steam for contract extensions after the capital has been recovered. What happens after that initial 5 or 10 years is very much dependent upon how the renegotiation is structured, and DOE should give considerable thought to structuring that process in the initial negotiation period. The likely economics of a 10-year payback period is presented in Section 5 of this report.

It is also important to note that any prospective bidder will need to develop long-term fuel contracts. The longer he/she can guarantee being in operation, the longer the term of the fuel-purchase contract, which in turn will likely result in a lower fuel price. And, if the fuel is gas, a pipeline needs to be constructed to the site. The gas company is likely to require a long-term contract with take-or-pay provisions before it will agree to construct such a pipeline unless it has additional reasons for pipeline extension (see Appendix D).

It may be possible to privatize a steam-only facility under the 5-year contracting authority produced by one interpretation of the AEA, but it would almost certainly cause a heavy risk penalty to be built into the steam charges proposed by any bidder. A 10-year delivery contract that would be possible under the other interpretation of the AEA would be better, but still shorter than the industry norm for a situation such as this. If this is the approach of choice, it is in DOE's best interest to continue pursuing new legislative authority for longer-term (30 to 40 years) contract authority. If new legislation passes quickly, it might be available to DOE by the time contract negotiations begin, putting DOE in a better position to extract a better price from the winning contractor.

DOE can also offer to incur a contingent liability in order to buy down the risk premium and the cost of steam. The contractor's position is likely to be that "if the future of steam consumption is so certain, DOE is taking no risk and is incurring no cost in assuming contingent liability, and so why doesn't DOE put it into the contract?"

Cogeneration Contract Issues

Since the cogeneration bidder's revenues will be primarily based upon electricity sales, his major concern is not a long-term steam sales contract to DOE, but rather the acquisition of a stable site with guaranteed access and support services for the expected life of the cogeneration facility. Indeed, any utility will require proof of such a condition before it enters into a long-term electricity purchase contract. DOE intends to provide this guarantee through a long-term land lease (discussed in Section 4.2). The ability to contract for long-term steam sales to DOE may be an issue, but probably not a project-killing issue for a cogeneration bidder. A bidder will likely require only a long-term lease that provides for guaranteed services coupled to a Companion Operating Agreement (COA) that provides for purchase of steam based upon annual appropriations.

The bottom line with respect to contracting authority is that DOE's ability to contract for supplies and services is severely hindered by the AEA's current 5-year or 10-year limit. It may be possible to acquire a cogeneration-based steam supply with existing legislation, but if DOE is going to acquire future waste-related supplies or services through privatization, it needs more powerful long-term contracting authority.

4.2 REAL ESTATE LEASES AND EASEMENTS

This section discusses DOE's statutory authority to enter into long-term leases of government land and the long-term easements private vendors may need to acquire to construct and operate a steam plant on the Hanford Site.

4.2.1 DOE's Long-Term Leasing Authority

In order for privatization to be feasible, the land lease the contractor negotiates for the steam plant site must last (at least) as long as the economic life of the plant. If the plant is a steam plant with sales only to DOE, a lease term that allows for construction, an operation to serve DOE needs, and subsequent decommissioning and site remediation may be the extent of time needed. If the plant is designed as a cogeneration facility, the lease term should be at least 40 years to enable construction, full-life use of the cogeneration facility, and decommissioning and site remediation.

The AEA gives DOE the authority to enter into long-term leases of land in support of its nuclear mission. Based on past use of this authority at Hanford (there is currently a 99-year lease to the State of Washington), such leases can be for periods that will be quite sufficient for the purposes of the steam contract. There are conflicting authorities (the DOE Organization Act, for instance), however, that may restrict the term of the lease to 5 years.

Because the ability to enter into a long-term lease of Hanford land is critical to the success of the steam plant project, DOE's long-term leasing authority needs to be confirmed before substantial resources are invested in

the project. DOE should also continue to pursue passage of legislation in Congress that would grant DOE clear long-term leasing authority for privatization project purposes.

The following two leasing issues need to be confirmed:

1. Long-term leases are permitted in support of the Hanford mission. It appears extremely likely that the current Hanford cleanup mission, which the steam plant will support, falls under this umbrella. Any cogeneration plant constructed onsite, however, would have as its main purpose the generation of electricity for sale outside the Hanford Site. The question that needs to be resolved is: "Is the (secondary) generation of steam for Hanford waste cleanup adequate to allow the long-term leasing authority to be applied to the cogeneration site?".
2. DOE also intends to include services such as water supply, road and rail access, and emergency services as part of the lease. Linking these services to a long-term lease will be a substantial commitment for DOE to make--especially if the lease is for 30 to 40 years. If DOE were to close the Site before the lease had expired, it would have an expensive ongoing obligation to provide these services. Can this contingent liability be accepted under the leasing authorization? The willingness and authority of DOE to make such a commitment needs to be formally approved as part of preparing for privatization.

4.2.2 Easement Requirements

If the proposed new steam plant is fueled with natural gas, a new pipeline across DOE lands will be required to serve the facility, because there is no existing natural gas service to the 200 Area. A new trunk line from a neighboring community will need to be constructed (see Appendix D). It is expected that either a pipeline company or a natural gas distributor will construct the new line and obtain the needed easements from property owners along the route. If the pipeline company continues to own the portion of the pipeline within DOE boundaries, then it will need an easement from DOE. If DOE owns and constructs the portion of the pipeline on the Hanford Site, no easement for that portion of the route would be needed. The granting of a site easement does not seem to be a problem--there are precedents for other utility corridor easements on the Hanford Site.

4.3 ENVIRONMENTAL AND PERMITTING REQUIREMENTS

This subsection reviews the impact of the National Environmental Policy Act of 1969 (NEPA) and various permit requirements on the acquisition process. The impact of the Tri-Party Agreement is also discussed.

Compliance with NEPA will be required and will be an important element in project scheduling regardless of whether the government-build or the

privatization approach is pursued. Certain permits (principally environmental permits) will also be needed; this process will impact project schedule and costs.

4.3.1 NEPA Requirements

NEPA implements a national policy to encourage the productive and enjoyable harmony between man and his environment and to prevent or eliminate damage to the environment and biosphere. A critical component of NEPA is the requirement to evaluate the environmental effects of federal actions. The environmental evaluation typically produces an environmental assessment (EA) that results in either a "finding of no significant impact" (FONSI) or the determination that there is a potential for significant impact and the need for an environmental impact statement (EIS). Under NEPA, federal agencies have the ability to go directly to an EIS for "major federal actions significantly affecting the quality of the human environment."

The L-017 upgrades are anticipated to have no significant environmental impacts. Whether a new plant would have no significant impact (an EA resulting in a FONSI) or have the potential for significant impact (requiring an EIS) will be determined through the separate environmental planning now under way as a parallel activity to development of the ADD. As the government is required to satisfy NEPA requirements before committing to an irreversible action, DOE needs to make the NEPA decision as early in the project as possible.

Under the current approach, DOE intends to facilitate the schedule by developing broad NEPA documentation (EA or EIS) as early as possible. A schedule risk associated with this approach is that supplemental documentation may be required if the private-sector firm selected for the project proposes a plant configuration that has not been covered by the original NEPA documentation.

In summary, then, an EA should be sufficient to provide coverage for L-017, whereas an EIS may be required for any new construction. Proposals for plants whose configuration lies outside DOE's NEPA documentation may require supplementary documentation with attendant cost and schedule impacts.

4.3.2 Environmental Permit Requirements

The likely environmental permit requirements for the steam plant project are shown in Table 4.1 and are discussed in detail in Appendix C.

The major permit discriminator between the alternatives considered in the ADD concerns the prevention of significant deterioration (PSD) permit under the Clean Air Act (CAA). Section D.2 of Appendix D discusses the PSD permit in detail. Conclusions based on that discussion are

- All of the privately-owned plant options will require acquisition of a PSD permit because each option would constitute a "major stationary source" (i.e., a new stationary source because it would not be under DOE control).

TABLE 4.1. Permit Requirements for Steam Supply Project

Permit	Federal Ownership				Private Ownership			
	Coal		Natural Gas		Coal		Natural Gas	
	Cogeneration	Steam Only ^(a)	Cogeneration	Steam Only	Cogeneration	Steam Only	Cogeneration	Steam Only
New Source Emission	Y	Y	Y	Y	Y	Y	Y	Y
Prevention of Significant Deterioration (PSD)	Y	P	Y	P	Y	Y	Y	Y
Air Emission Operating	Y	Y	Y	Y	Y	Y	Y	Y
Dangerous Waste TSD	P	P	N	N	P	P	N	N
Solid Waste Disposal Facility	N	N	N	N	N	N	N	N
NPDES	N	N	N	N	N	N	N	N
Water Appropriation	N	N	N	N	P	P	P	P
Miscellaneous	N	N	N	N	Y	Y	Y	Y

Key: Y = Probably yes; N = Probably Not; P = Possibly.

(a) Includes Project L-017.

- Any new federally-owned facility that results in a net "significant" emission increase would also require a PSD permit. It is likely that any cogeneration plant, especially coal-fired, would result in "significant" emissions above current levels. On the other hand, a steam-only facility, especially natural gas-fired, may not result in "significant" emissions above current levels if sufficient existing boilers in the 200 Area are permanently closed.

4.3.3 Impact of the Tri-Party Agreement

The Hanford Federal Facility Agreement and Consent Order (commonly known as the Tri-Party Agreement) is an agreement between DOE, EPA, and the Washington State Department of Ecology covering environmental cleanup activities on the Hanford Site. Assuming all permit requirements identified in Section 4.3.2 are met, the Tri-Party Agreement and the conditions of the proposed steam plant are not expected to conflict.

4.4 SECURITY REQUIREMENTS

The level of security required during construction and operation of a facility will vary, depending on the location of the facility. Under all options, access requires passage through either the WYE Barricade on Route 4S or the Yakima Barricade on Route 11A.

The L-017 option will require stricter security requirements if the facility is located inside the 200 Limited Area. In this case, to gain access to the

facility, construction personnel will be required to have badges with a "O" clearance and special construction notation (which takes approximately 30 days to acquire) or else a "O" badge without the special notation, but with an escort. The escorted "O" badge can be acquired in less than one day.

If a new plant is to be constructed, it will be located along the steam tie-line in the 600 Area. The 600 Area has lower security requirements than the 200 Area. DOE will furnish contractors with badges for access to the 600 Areas at no additional cost. Should the contractor require or request a security clearance for access to the 200 Limited Areas, then the cost of obtaining the necessary investigations would be borne by the contractor.

According to Hanford Security officials, contractors will be held liable for all costs related to securing the appropriate clearances for individuals involved in constructing and operating any facility.

4.5 BUILDING AND SAFETY CODES

Safety and other codes and standards applicable to construction of a steam plant are likely to be similar for federal or private ownership. For federal ownership, the general design criteria in DOE Order 6430.1A are applicable. The policy statement in Section 7 of the Order states that while DOE "is not required to comply with state and local building codes, laws, and ordinances, the planning, design, and construction processes should accommodate them to the extent consistent with the accomplishment of the Department's mission." This policy suggests that the actual construction of a federally-owned versus a privately-owned plant would not differ substantially.

The Hanford Plant Standards would apply to a federally-owned steam plant, but presumably not to a privately-owned plant. These Standards apply to contractors and subcontractors performing work for DOE-RL at Hanford. The Standards are defined in DOE-RL Order RL 6430.1C as comprising design criteria, drawings, and specifications used for construction projects unique to Hanford. The Standards consist of Standard Design Criteria, Standard Details, and Standard Specifications. The Standard Design Criteria are statements of minimum requirements for work at Hanford.

A privately-owned steam plant would be subject to the Washington State Building Code and any supplemental requirements imposed by Benton County. The state building code consists of uniform codes, statutory provisions, and rules and regulations defined and adopted by reference in Revised Code of Washington (RCW) RCW 19.27.031 and RCW 19.27A.010. These include the Uniform Building, Mechanical, Fire, and Plumbing Codes. In addition, the National Electric Code and the National Electrical Safety Code are endorsed in RCW 19.28.010.

4.6 MARKET FACTORS

This section examines fuel cost and availability, markets and prices for power generated at a cogeneration facility, and transmission/distribution issues.

In addition, the Public Utilities Regulatory Policies Act of 1978 (PURPA) status of a cogeneration facility and the implications of that status are discussed. All prices are expressed in 1991 dollars.

4.6.1 Fuel Costs and Supply

Two fuel types are being considered for the steam-generating facility: coal and natural gas. Power system planners have traditionally found it difficult to predict future fuel prices. Planners have found that economic analyses are extremely sensitive to the assumptions made regarding future prices. Therefore, care must be taken in interpreting and using the prices and escalation rates presented in this section. Unforeseen market or political factors could significantly alter these rates. The impact of this uncertainty can be measured through sensitivity analysis in the life-cycle cost studies. These recommendations are discussed more thoroughly in Appendix D.

Coal Prices

Coal currently fuels the 200 Area steam boilers. Under the current 5-year contract, coal is purchased from Colorado and arrives at the 1100 Area at an average cost of \$2.55/MMBTU. The following coal price assumptions are recommended, depending on the acquisition option:

- federal ownership and operation: \$2.55/MMBTU and 1.0%/yr real escalation
- private ownership and operation: \$2.25/MMBTU and 1.0%/yr real escalation.

Natural Gas Prices

The natural gas industry has been criticized in the past for high prices and lack of competition; however, it has become more competitive in recent years. Natural gas is generally abundant in the United States and Canada and is generally priced at about \$2 to \$4/MMBTU as discussed in Appendix D.

A recommended average price of natural gas for planning purposes was ≈\$3.05/MMBTU. The real escalation rate estimates for natural gas ranged from 2.0 to 4.0%. A 3.0% real escalation rate is recommended for planning purposes.

Current pipeline capacity is generally inadequate to meet future transport needs in the Pacific Northwest. Major expansions of two interstate pipelines are under way and are expected to be completed in 1993 or 1994, in plenty of time to serve the proposed steam plant. In general, interviews with natural gas suppliers indicate that they would be willing to develop and operate a pipeline to the Hanford steam plant site (or at least to the Hanford Site boundary) for a small incremental cost (approximately \$0.20/MMBTU) if the plant operator were to sign a long-term contract for gas purchase.

The following natural gas price assumption is recommended:

- Under either the federal or privatization acquisition option, natural gas delivered to the Site will cost about \$3.25 (\$3.05 + \$0.20)/MMBTU and will escalate at a real rate of 3.0%/yr (see Table 4.2). This cost includes construction and operation of a feeder pipeline to the steam plant site from a nearby major interstate pipeline.

4.6.2 Market for Power from a Cogeneration Facility

The price that a prospective cogenerator can negotiate for sale of electricity is by far the most important variable in determining the viability of any cogeneration project. Unfortunately, it is impossible to predict price levels in advance of direct utility negotiations. The major reason is that most independent power producers sell to utilities through formal competitive procurements initiated by individual utilities. A market study was done to characterize likely ranges of electrical sales prices on a regional basis based upon 1) federal versus private ownership considerations, and 2) discussions with utility managers in those regions.

The following section discusses the type of market opportunities likely to be available under federal and private ownership (see Figure 4.1). The ability of a prospective site cogenerator to wheel power over BPA and other transmission lines is also discussed, but, again, it is impossible to guarantee capacity availability or wheeling cost in advance of actual negotiations. A more detailed discussion of these issues is provided in Appendix E.

Power Sales Under Federal Cogeneration Scenarios

The long-term power sales agreement between BPA and DOE-RL governs the disposition of all electrical power provided on the Hanford Site. Under Section 5 of the power sales agreement, DOE-RL must use its "best efforts" to either 1) serve its own load with firm resources, or 2) make the resources available for acquisition by BPA. Firm resources include firm power purchased on contract from a third party, as well as self-generation, both on an independent or jointly-owned basis.

Under the first option, the onsite generation is used simply to replace power that would have been purchased from BPA. The "price paid" for this power is simply the price that BPA charges the site for power under the effective

TABLE 4.2. Expected Fuel Cost and Escalation

	Expected Price (1991\$/MMBTU)		Real Escalation Rate (%/year)	
	<u>Coal</u>	<u>Natural Gas</u>	<u>Coal</u>	<u>Natural Gas</u>
Federal	2.55	3.25	1.0	3.0
Private	2.25	3.25	1.0	3.0

Pacific Northwest Markets

FIGURE 4.1. Power Sales Options for Cogenerator on the Hanford Site

Priority Firm-Rate (PF-Rate). For 1991, the melded rate for the Hanford Site was 22.7 mill/kWh. BPA's "official forecast" of the PF-Rate over the next 20 years reflects no real escalation.

Under the latter option, where the resource is made available for acquisition by BPA, the sale will take place under a "mutually agreeable contract at appropriate compensation." Under the provisions of the Northwest Power Planning and Conservation Act, BPA may only acquire such resources as demand-side measures, customer system efficiency improvements, or generation (conventional or renewable), if the resource does not cost BPA (in the form of a credit on a customer's bill) more than an alternative resource.

Under this latter option, BPA has implemented two generation-resource acquisition programs. Depending upon the characteristics (performance and environmental) of the resources, the likely price ranges between 28 and 38 mills/kWh. The mid-point of 33 mills/kWh is the best point of departure for planning purposes.

It is clearly to Hanford's advantage to pursue the second option of sale to BPA rather than "turning back the meter" on BPA sales to the Site. Under this approach, for a plant initiating operation in 1998, a price of 33 mill/kWh rate with zero expected escalation is an appropriate value to use in evaluating the worth of an alternative resource.

Power Sales Under Private Cogeneration Scenarios

Several power sales options are potentially available to a private cogenerator on the Hanford Site. These options include power sales both within and outside the Pacific Northwest.

Potential markets within the Pacific Northwest (PNW) include investor-owned utilities (IOUs), public utilities, and regional power brokers. The best opportunity to market the power appears to lie in the IOU competitive bid process.

Regional IOUs, including Puget Sound Power and Light, Washington Water Power, and Pacific Power and Light, are encouraged by the Washington Utility and Transportation Commission to engage in competitive bid resource acquisition. The intent is to acquire power at less than the utility's avoided cost. Informal discussions with utility representatives indicate that they expect to receive bids at 86-95% of avoided cost, which would produce the following purchase prices. (These rates are not expected to escalate above the general inflation rate.)

- Puget Sound Power and Light - 36 mill/kWh in 1996
- Washington Water Power - 35 mill/kWh in 1995.

The recommended value for evaluating sale of Hanford-generated electricity to the PNW region is 36 mill/kWh with zero escalation. This acquisition price is consistent with the expected payment levels in BPA's resource acquisition programs as discussed above.

Sales to public utilities in the PNW would be negotiated at a price that falls somewhere in between BPA's PF-Rate (23.1 mills/kWh) and the IOU's rates (36 mills/kWh). Most likely, because most public utilities are full-requirements customers of BPA, the negotiated price would be in the range of 23 to 24 mills/kWh. Another potential regional market lies with the brokering of power marketing subsidiaries of some of the region's IOUs. These transactions are typically short term (less than 5 years) and the payment value is less than the IOU would pay for the same resource (≈35 mills/kWh).

A survey of publicly- and privately-owned electric systems in California provides a look at the purchase prices outside the PNW. A study for the California Energy Commission in 1989 examined the avoided energy cost and capacity cost of fourteen major municipal and utility districts in the state. These systems included the Los Angeles Department of Water and Power; the Sacramento Metropolitan Utility District; and the cities of Anaheim, Burbank, Glendale, Palo Alto, Pasadena, Riverside, and Santa Clara, as well as several

smaller systems. Most of these systems have been familiar participants in inter-regional sales with PNW utilities, and they likely represent the best power sales opportunities outside the PNW. Two large investor-owned electric systems were also examined.

The average, melded avoided cost for this group is on the order of 40 to 60 mill/kWh, for 1999 delivery expressed in 1991 dollars. A smaller sample of systems that reflects a more contemporaneous view of current costs and load/resource balancing suggests a range of 41 to 58 mills/kWh. Capacity is valued substantially higher than in the PNW, with an approximate value of 10 to 20 mill/kWh at a 0.55 load factor. Expectations for long-run real escalation appear to be on the order of 3.0% for some utilities to as low as 0% for others.

In the increasingly competitive bulk power market, experiences in the PNW and elsewhere indicate that purchase prices are not likely to be as high as full avoided cost levels. Utilities regularly get bid responses that total 10 to 20 times their needed capacity. For a generic purchase price from outside the region, the more recent data indicates an average of 46 mill/kWh for a first-year payment in 1999 and escalation at 2.0% in constant dollars appear reasonable for planning purposes.

At the present time, and for the foreseeable future, the Desert Southwest market has surplus capacity. This is primarily due to new resources coming on-line and the effect of the economic downturn in the region.

4.6.3 Power Transmission Costs

Much of the electrical load at the Hanford Site is served by the DOE 230-kV grid. This system has sufficient capacity available to permit access to the Federal Columbia River Transmission System (FCRTS) that BPA owns and operates. The cost of wheeling electricity over the FCRTS is about 2 mill/kWh.

Inter-regional power transmission is facilitated by the Pacific Intertie. A new rate proposal for the use of the FCRTS and the Intertie for exports to the Pacific Southwest market went into effect October 1991. This raises transmission rates to 4 to 5 mill/kWh, with cost increases expected to match general inflation.

4.6.4 PURPA Requirements

PURPA was enacted by Congress to encourage the development of alternative sources of energy. Its approach was to impose conditions to promote non-utility generation of electricity, effectively reducing the monopoly power of regulated electrical utilities.

After PURPA passed, utilities were essentially forced by their state utility commissions to purchase power from "Qualified Facilities" (QFs) whenever it was offered, creating a burgeoning "PURPA industry." All needed capacity was

essentially being provided by QFs, leaving non-QF facilities without a market. (See Appendix F for a definition of a QF and a generalized discussion of PURPA.)

PURPA's impact, however, has decreased significantly over the past several years. Utilities can effectively avoid buying power directly from individual QFs by forcing them into an open bidding process in which they must compete with other QFs and non-QFs on a price (and other) basis. Utilities are encouraged by state commissions to take this approach as a way to attract low-cost power. Hence, the value of qualifying for QF status has significantly deteriorated from earlier years. PURPA qualification is not likely to play a role in development of any site cogeneration facility.

5.0 LIFE-CYCLE COST ANALYSIS

The life-cycle cost (LCC) analysis is an integral part of the ADD analysis. Its purpose is to

- compare, on a parametric level, the economic performance of a broad range of technical and procedural options
- eliminate options that are clearly not economic
- identify the most viable options, prioritizing where possible
- identify areas of economic uncertainty that cloud the decision process and perform sensitivity analyses to aid in resolving those uncertainties.

The LCC conducted within an ADD is a screening tool that may be inadequate to support a final decision, since the uncertainty band may be too great to judge between options that are nearly equal in economic performance. If two or more options are found to be nearly equal and the decision cannot be made on non-economic grounds, then a more detailed comparative analysis should be conducted before a final implementation decision is made.

5.1 SPECIFIC OBJECTIVES FOR THE STEAM PLANT LIFE-CYCLE COST ANALYSIS

The overall goal of this LCC analysis is to identify the likely least-cost option(s) for providing steam for space heating and process use in the 200 Area. The general approach is to evaluate a reasonable representation of several proposed project configurations. The analysis is intended to answer the following key questions:

1. Is it more economical for DOE to rehabilitate the 200-East plant (hereinafter referred to as L-017) or to construct a new central steam plant?
2. Is a government-build cogeneration plant economically feasible?
3. Do coal-fueled or gas-fueled plants make more economic sense given conditions onsite?
4. Does a privately-owned steam plant provide a lower cost of steam than government options?
5. Does a privately-owned cogeneration plant with sale of electricity off the Hanford Site appear to be economically feasible?
6. Given the alternatives, which are most promising and should be pursued further, and which can be eliminated at this time?

5.2 DESCRIPTION OF THE ANALYTIC APPROACH

The analytic approach is described in the following sections.

5.2.1 Life-Cycle Cost Methodology

The economic evaluation was conducted by calculating and comparing the levelized cost of providing steam to the 200 Area via 13 technology and ownership combinations. Levelized cost analysis combines initial cost, annually recurring cost, and system performance characteristics into a single figure of merit (the levelized steam cost in \$/1,000 lb) that is a commonly accepted metric for comparing the projected steam costs of alternative acquisition approaches. The specific economic methodology employed was that defined in Brown et al. (1987).

5.2.2 Cost and Performance Estimates

In developing the LCC, emphasis was placed upon determining relative economic performance through using consistent parametric design and costing approaches and by employing identical unit cost assumptions for common elements of alternative configurations. Detailed engineering designs were not prepared, and no bottom-up cost estimates were prepared. The approach used was to estimate costs at an aggregated level by using simple cost estimating relationships and scaling factors based on the overall size (e.g., lb/hr of steam and/or kWe) of the plant or major equipment elements. Similarly, performance was evaluated on an annual average basis.

Cost estimates prepared in this manner are typically described as "order of magnitude" and are expected to be accurate within plus 50% and minus 30% on an absolute basis (American Association of Cost Engineers 1990). However, the use of common cost and performance assumptions for common elements of a technology configuration reduces the level of uncertainty when viewed on a comparative basis. This allows conclusions to be developed about the relative merits of alternative technology configurations even when the absolute costs could differ by as much as 30 to 50%.

Appendix H presents a detailed discussion of how cost and performance estimates were developed for each of the analyses presented here.

5.2.3 Key Assumptions and Inputs

Economic inputs used to calculate the levelized steam cost are discussed in Appendix G and summarized in Table 5.1 for both government and private ownership.

The baseline economic life was set at 30 years for both government and private ownership. This lifetime is based on standards prescribed by the Electric Power Research Institute (EPRI) for facilities similar to the steam and cogeneration plants being considered and on guidelines prescribed by law (EPRI 1989; Van Knapp et al. 1989). The federal government does not pay any property taxes on Hanford facilities and is assumed to self-insure. The property

TABLE 5.1. Economic Assumptions

<u>Economic Factor</u>	<u>Government</u>	<u>Private</u>
Economic Life	30 years	30 years
Property Tax Rate	0%	1.5%
Insurance Rate	0%	0.5%
B&O Tax Rate	0%	1.5% of steam revenue 3.852% of out-of-state electricity revenue
Income Tax Rate	0%	34%
Discount Rate	4.7% real	7% real, after tax
General Inflation	5%	5%
Depreciation Period	N/A	20 years
Price Year	1991	1991
Net Salvage Value	\$0	\$0

tax rate for private ownership was established by consulting with the Benton County Assessor's Office. The private ownership insurance rate was established based on data from EPRI's Technical Assessment Guide (EPRI 1989).

Business and occupation (B&O) tax rates were established by consulting with the Washington State Department of Revenue. B&O taxes do not apply to either electricity or steam generated for self-consumption. Therefore, B&O taxes on steam would only apply for a privately-owned plant selling steam to the government. B&O taxes on electricity apply to sales for immediate consumption or sales outside the state of Washington. Sales within the state of Washington to public or private utilities for resale within the state of Washington are not subject to B&O taxes. Therefore, government sales of cogenerated power (to BPA) are not subject to the tax, nor are private sales to Washington utilities. B&O taxes would be assessed on private sales to California utilities, however.

The federal government does not pay income tax; the private income tax rate was presumed to be 34%, the top marginal rate for corporations (Van Knapp et al. 1989).

The federal government has recently established new discount rates for evaluating energy projects based on treasury security rates (Lippiatt and Ruegg 1990). Dean Devine, DOE-HQ Federal Energy Management Program, advised the project team to use the newly prescribed rate--4.7% real; this rate applies to the evaluation of central energy plant facilities, including boilers and cogeneration equipment, in addition to energy conservation and renewable energy investments. Three different sources were used to establish an appropriate private discount rate of 7% real (after tax).

The general inflation rate was set at 5%/yr based on consistent assumptions offered by EPRI (EPRI 1989) and the Northwest Power Planning Council (1989). Even though the levelized steam cost is calculated in real 1991 dollars, an inflation rate assumption is required to deflate future depreciation credits

that are established in nominal terms. In accordance with current tax laws identified in Van Knapp et al. (1989), depreciation under private ownership follows the 20-year modified accelerated cost recovery system (MACRS). The inflation rate assumption has no impact on the real levelized cost of steam for federal ownership scenarios.

5.3 200-AREA REHABILITATION VERSUS GOVERNMENT NEW CONSTRUCTION

One of the important early decisions that DOE needs to make is what the government "base case" should be, so that there is a government-levelized cost of steam against which all alternatives can be compared. The de facto base case for this analysis has been rehabilitation of the 200-East Area steam plant (referred to as Line Item L-017). Two government new construction alternatives should be compared against L-017: new coal-fired and gas-fired steam plants. The results of this analysis are presented in Figure 5.1.

The levelized cost of steam from L-017 over its 30-year life has been estimated to be \$13.96/1,000 lb. This cost reflects about 25% capital investment, 42% operations and maintenance (O&M), and 33% fuel over the life of the plant. The costs of new government coal-fired and gas-fired plants, respectively, are \$15.29 and \$13.68. A new coal-fired plant will be more expensive than rehabilitating the existing plant, as documented here. A gas-fired steam plant, however, appears to provide an equivalent levelized cost to L-017 for the assumptions modeled here.

S9112080.1

FIGURE 5.1. Government-Build Steam-Only Options

There are several key input factors whose relationships need to be understood. First, the capital cost for a gas-fired steam plant is about 40% of an equivalent coal-fired plant--hence, the levelized capital fraction is substantially less. Second, O&M for a coal-fired plant is substantially higher than for a comparable gas-fired plant. The higher O&M occurs because coal is a more complex and dirtier plant that requires fuel preparation and mechanical transport to the boilers, combustion gas cleanup, ash disposal, and other activities minimized in a gas plant. In this analysis, these two gas-fired advantages are compensated for by the greater fuel cost for the gas-fired plant, giving essentially equal LCCs between L-017 and the gas-fired steam plant for energy delivered to the site.

Natural gas is relatively inexpensive at present, but its price is expected to escalate above inflation at about 3% each year (as opposed to coal prices which are expected to escalate at only 1%), providing high fuel prices in the future. The predicted escalation rate for gas is perhaps the most critical assumption in this analysis. A sensitivity analysis on the effect of changes in natural gas prices and the escalation rate of natural gas was performed, and the results are presented in Section 5.7.2.

In evaluating this result, load assumptions should be reviewed. The analysis conducted here assumed that gross steam demand would be 1100 million lb/yr, at the upper end of the bracketed range of 700-1300 million lb/yr, based upon guidance received from Westinghouse Hanford. The assumption of a high-end demand tends to tilt the results towards a configuration with lower variable costs (fuel + variable O&M)--in this case, coal. However, future 200-Area loads appear to be highly uncertain. If, once the plant size is fixed by current demands, future loads decline precipitously, then variable costs become a significantly smaller component of total LCC. If this were the case in the 200 Area, the gas-fired steam plant would be more cost-effective than L-017 because of its substantially lower capital and fixed operating costs.

There is another design and operational approach that might make the gas plant significantly more attractive than the results provided here. DOE might opt to employ an interruptible gas supply to fuel the plant, taking advantage of the significant price reductions available (see Table D.1 in Appendix D). This approach would probably require expanded oil-fired, back-up at additional capital costs, but there would be net benefits. The U.S. Army is currently evaluating this option for many of its installations, and it expects to save considerable money through this approach.

5.4 GOVERNMENT-BUILD COGENERATION OPTIONS

If DOE were to develop cogeneration facilities to supply steam for the Site, the electrical power generated would need to be either 1) used to displace power purchased from BPA, or 2) sold to BPA directly. Under the former case, the "price" for electricity "sold" would equal the price currently paid for electricity, 23.1 mill/kWh; under the latter, the price would be 33 mills/kWh. Neither rate is expected to escalate over the general inflation rate.

Assuming the higher 33 mill/kWh price, the LCC results of potential DOE cogeneration facilities are as shown in Figure 5.2.

It is evident from these results that government-build cogeneration options are not cost-effective at Hanford. Primary cogeneration plants are less cost-effective than secondary plants--clearly, selling electricity at 33 mill/kWh is a money-losing proposition.

5.5 PRIVATE STEAM-ONLY OPTIONS

The LCC of prospective private-sector, coal-fired and gas-fired steam plants was compared with rehabilitation of the 200-East plant (L-017). Figure 5.3 presents the results of LCC analysis for a private coal- and natural gas-fired steam plant as compared to L-017. Both these options appear to be more expensive to DOE than L-017, although given the parametric nature of this analysis, it is impossible to rule out the gas-fired steam plant, especially if steam loads decrease significantly in the future. Comparing Figure 5.3 with Figure 5.1, the government-build steam options, clearly shows that for steam-only plants, government-build is more cost-effective than private-build, chiefly reflecting the lower cost of capital to the government. The sensitivity of steam costs to changes in the discount rates was examined and the results are presented in Section 5.7.3.

FIGURE 5.2. Government-Build Cogeneration Options

S9112080.3

FIGURE 5.3. Private Steam Plant Options

5.6 PRIVATELY-OWNED-AND-OPERATED COGENERATION PLANTS

The cost of steam from a private-sector cogeneration facility onsite is difficult to estimate. The primary reason is that there is a wide range of possible electrical prices and price escalation rates, and it is impossible to predict what prices and rates a Hanford contractor might be able to negotiate. The price and escalation rate for electricity sales is the most important factor in determining the economic performance of a prospective cogeneration facility.

For the reference cases presented in Appendix G, the PNW sales of electricity were assumed to be at 34 mills/kWh (net) with no real escalation and the PSW sales to be at 41.5 mills/kWh at a 2%/yr real escalation rate. For coal-cogeneration plants, the resulting levelized steam costs to DOE ranged from \$18.89 to \$22.74 as shown in Figure 5.4. These costs were much higher than L-017 and all of the steam-only plants (Figures 5.1 and 5.3). For natural-gas cogeneration plants, the steam costs ranged from \$11.68 to \$27.11 as shown in Figure 5.5. This range includes the best reference case (\$11.68) and the worst reference case (\$27.11). Because of this variability in the results, a sensitivity analysis of steam costs, the result of varying electricity prices and escalation rates, was performed. Results of this sensitivity analysis are discussed in the following section.

FIGURE 5.4. Private-Build, Coal-Fired Cogeneration Options

5.7 LIFE-CYCLE COST SENSITIVITY ANALYSIS

The sensitivity of the levelized cost of steam to DOE was examined by varying four sets of input variables:

- the net price received for electricity and the price escalation rate
- the price for natural gas and the price escalation rate
- both the government and private discount rates
- the effect of changing the contract length from 30 years to three 10-year contracts.

Possible markets and ranges of prices and escalation rates are presented in Section 4.6.2 and Appendix E. Rather than predict which of these markets is most probable, this analysis presents the levelized cost of steam to DOE based upon two factors: net price received for electricity (in \$1991), and price escalation rate. The net price received for electricity is calculated by taking the gross price received from the utility and subtracting wheeling costs and B&O taxes (if sold out of state).

FIGURE 5.5. Private-Build, Gas-Fired Cogeneration Options

5.7.1 Electricity Prices and Escalation Rates

Individual cogeneration contracts are likely to provide for sale of electricity to a utility at a fixed price (relative to inflation), with the contractor being able to pass through all increased costs from fuel price escalation. Gas is expected to escalate at 3% per year and is likely to constitute about 70% of the total LCC of a gas-fired cogeneration plant. Hence, the cogenerator may expect to capture about 2% of overall price escalation (above inflation).

Figure 5.6 presents the levelized cost of steam for a privately-owned, gas-fired primary cogeneration plant as a function of initial price and long-term price escalation. As a comparison, the levelized cost of steam from L-017 is presented as the horizontal line.

The range of cost-effective electricity price/escalation combinations ranges from roughly 35 mill/kWh at 2.4% real escalation to 45 mill/kWh at 1.0% real escalation. It would seem possible, given the market information developed here, to negotiate an electrical sales contract that could allow DOE to obtain steam at a significantly lower cost than L-017. Sales within the Pacific Northwest, expected to be at a net price of 34 mill/kWh, would be unlikely to yield a steam cost lower than provided by L-017.

FIGURE 5.6. Levelized Costs for Privately-Owned, Gas-Fired Primary Cogeneration as a Function of Initial Price and Long-Term Price Escalation

Figure 5.7 shows the same information for a privately-owned, gas-fired sec-
ondary cogeneration facility. Even at this lower level of electricity prod-
uction, it appears that steam production could be less expensive than L-017.
If the levelized cost of steam is below the L-017 steam cost (\$13.96) for the
plant sizes used in Figure 5.6 and 5.7, then it appears that the greater the
ratio of electrical to steam sales from a privatized steam plant, the better
the price of steam to the government is likely to be. If market conditions
are favorable, a private-sector cogenerator may propose to build even a larger
plant onsite than that envisioned in the primary-cogeneration scenario.

5.7.2 Natural Gas Prices and Escalation Rates

To determine the sensitivity of the levelized cost of steam to a change in the
price of natural gas or its real escalation rate, a series of LCC runs were
performed on three of the gas-fired options: 1) the privately-owned, primary
cogeneration option with electricity sales to the PSW; 2) the privately-owned,
secondary cogeneration option with electricity sales to the PSW; and 3) the
government-owned steam plant.

As shown in Tables 5.2 and 5.3, the levelized steam cost for the primary-
cogeneration option can change by more than \$29/1,000 lb steam from the lowest
price/escalation rate (\$2.50/MMBTU and 2%) to the highest price/escalation
rate (\$4.00/MMBTU and 4%). Similarly, for the same high and low prices/
escalation rates, the cost of steam for the secondary cogeneration option

FIGURE 5.7. Levelized Costs for Privately-Owned, Gas-Fired Secondary Cogeneration as a Function of Initial Price and Long-Term Price Escalation

TABLE 5.2. Alternative Natural Gas Price Results for Privately-Owned Plants

Primary Cogeneration Levelized Steam Cost
1991\$/1000-lb Steam

Initial Gas Price, \$/MMBTU	Real Annual Price Rate Escalation		
	2.00%	3.00%	4.00%
2.50	(1.86)	2.71	8.32
3.00	2.69	8.17	14.91
3.50	7.23	13.63	21.49
4.00	11.78	19.09	28.07

Secondary Cogeneration Levelized Steam Cost
1991\$/1000-lb Steam

Initial Gas Price, \$/MMBTU	Real Annual Price Rate Escalation		
	2.00%	3.00%	4.00%
2.50	5.42	7.93	11.03
3.00	7.92	10.94	14.65
3.50	10.43	13.95	18.28
4.00	12.93	16.96	21.91

TABLE 5.3. Alternative Natural Gas Price Results for Government-Owned Steam Plant

Initial Gas Price, \$/MMBTU	Real Annual Price Rate Escalation		
	2.00%	3.00%	4.00%
2.50	10.53	11.64	13.02
3.00	11.56	12.89	14.54
3.50	12.58	14.13	16.06
4.00	13.60	15.37	17.58

changes by \$16/1,000 lb of steam and for the steam plant by \$7/1,000 lb of steam. Thus, the primary cogeneration option is much more sensitive to a change in the price or escalation rate of natural gas than any of the other options.

Because of this sensitivity to natural gas prices and escalation rates, the levelized steam cost of the primary cogeneration options becomes greater than L-017 when the gas price/escalation rate is greater than about \$3.50/MMBTU and 3%, or \$3.00/MMBTU and 4%. This result highlights the importance of gas prices and escalation rates on the final cost of steam to the government. Given the wide range of prices and escalation rates discussed in Appendix D, it is important for all parties (private and government) to try and obtain the lowest-priced gas now and for the future.

5.7.3 Private and Government Discount Rates

The effect on the levelized steam cost of varying the private and government discount rates were examined in Section G.13.3. The government rates examined were 3%, 4%, and 5% and the private rates were 6%, 7%, and 8%. The privately-owned, primary cogeneration option with electricity sales to the PSW and the 200-East plant upgrade (L-017) were the cases examined with varying discount rates. Results of this analysis are shown in Table 5.4.

For the primary cogeneration option, the levelized steam costs only varied by less than \$0.50/1,000 lb of steam over the entire range of private and government discount rates. For L-017 the costs varied by \$0.85/1,000 lb of steam. Thus, the cost of steam is much less sensitive to changes in discount rates as compared to changes in the other variables (electricity prices and escalation rates, and natural gas prices and escalation rates) examined as part of the sensitivity analyses.

5.7.4 Change in Contract Length

The sensitivity of steam cost to a change in contract lengths from the reference case of 30 years to a series of three 10-year contracts was examined. Two options were analyzed for the effect of contract length changes, the gas-fired and coal-fired steam plants. In developing the economic model for a 10-year contract term, the assumption was that the contractor would require DOE to repay the entire capital investment over the term of the first 10-year

TABLE 5.4. Alternative Discount Rate Results

Primary Gas-Fired Cogeneration with Private Ownership
and Electricity Sales to the Pacific Southwest
Levelized Steam Cost, 1991\$/1000-lb Steam

<u>Private After-Tax Real Annual Discount Rate, %</u>	<u>Government Real Annual Discount Rate</u>		
	<u>3.0%</u>	<u>4.0%</u>	<u>5.0%</u>
6.0	11.34	11.51	11.70
7.0	11.35	11.53	11.72
8.0	11.45	11.63	11.82

200-East Plant Upgrade (L-017)
Levelized Steam Cost, 1991\$/1000-lb Steam

<u>Government Real Annual Discount Rate</u>		
<u>3.0%</u>	<u>4.0%</u>	<u>5.0%</u>
13.25	13.66	14.10

contract. During the two 10-year renewals, the contractor was assumed to recover fuel and O&M expenses, a fair rate of return on working capital, and a \$100,000 per year management fee. The analysis was structured so that the sum of discounted cash flows from the series of 10-year contracts was equal to that from a 30-year contract, using the contractor's discount rate.

From the compilation of results in Appendix G, and as shown in Table 5.5, the coal-fired steam plant had an overall cost of \$17.69/1,000 lb of steam while the gas-fired steam plant had an overall cost of \$15.86/1,000-lb steam. Compared to the reference cases, these costs are less than \$0.90/1,000-lb steam higher for the coal-fired plant and \$1.30/1,000 lb of steam higher for the gas-fired plant. The effect on the gas plant was larger because of its higher fuel escalation rate compared to the coal-fired plant.

TABLE 5.5. Costs of Three 10-Year Contract Periods

<u>Levelized Costs for Privately-Owned Steam Plant</u>		
<u>Period</u>	<u>Coal-Fired (\$/1,000 lb Steam)</u>	<u>Gas-Fired (\$/1,000 lb Steam)</u>
Year 1-10	22.91	16.36
Year 11-20	12.58	14.20
Year 21-30	12.69	17.24
Overall	17.69	15.86

Under the 10-year contract scenario, as shown in Table 5.5, separate LCCs are calculated for each contract period and then combined to develop a total LCC. The first period LCC is quite high, especially for the coal plant, reflecting total repayment of the capital plant plus fuel, O&M, and management fees. It is followed by two periods of low LCC, which reflect payment only for fuel, O&M, and management fees. The LCC in the last period (year 21-30) for the gas-fired plant is higher due to the large real escalation rate (3%) on fuel. When these three discounted cash flows are combined, the overall LCC is slightly higher than that for a 30-year contract, the reference case contract length.

Though the contract length has only a slight impact on the overall levelized cost of steam to the government, there are other reasons why a longer-term contract is more desirable:

- Attracting bidders and contract negotiations will be facilitated by a contract term that meets the industry norm.
- There is no guarantee that the contract will be renewed by the contractor at the end of 10 years. If the steam plant were to cease operation at the end of the first contract period, the government would have paid a LCC throughout the period substantially higher than L-017.
- The analysis conducted here assumes that the contractor will have been totally recompensed for his capital investment at the end of 10 years. The contractor will still own the plant. Given this bargaining position, the contract may be able to negotiate a better financial arrangement than recovery of costs plus the management fee (the assumption made here). This new arrangement would bring the total levelized cost of a series of three 10-year contracts even further above the levelized cost for a conventional 30-year contract.

5.8 LIFE-CYCLE COST SUMMARY

The LCC results presented above seem to suggest that DOE has three economic alternatives:

- L-017 - Rehabilitation of the 200-East Area coal-fired steam plant appears to be more cost-effective than any other alternative except the two summarized below. Because the line item is already in the approval chain, this plant can come on-line more quickly than any other configuration.
- New Government Gas-Fired Steam Plant - Development of a new government gas-fired steam plant appears to provide steam at about the same cost as L-017. Because this approach requires development and approval of a new line item, this plant would not come on-line for two years after L-017. It should be given serious consideration,

however, under a scenario where 200-Area steam consumption is expected to drop significantly over the next decades. Under this lower-use scenario, the gas-fired plant could be significantly more cost-effective than L-017.

- Privately Owned, Gas-Fired Cogeneration Plant - It may be possible to enlist a private-sector contractor to build a cogeneration facility onsite in order to sell electricity to the PSW. A range of possible electric prices and escalation rates could result in very inexpensive steam prices to DOE. Success of this approach is highly dependent upon the market and price of electricity and natural gas. Both markets are highly competitive and fluid.

6.0 CONCLUSIONS

The major conclusions developed in this ADD are presented below, each followed by a brief rationale for the conclusion.

Conclusion #1

DOE construction of a gas-fired, steam-only plant may be more cost-effective than rehabilitation of the 200-East coal-fired facility (L-017).

The projected LCCs of the rehabilitation project and a new government-build, gas-fired steam plant are very close. This evaluation was made with steam demand loads modeled towards the high side of the possible demand range. Three scenarios could make the gas-fired plant significantly more economic.

First, once the plant size is fixed by today's steam requirements, if the load trend continues to move downward (below the high-load scenario modeled in this analysis), then the gas plant would provide a lower LCC. If load decline can be accurately predicted, it would make the gas alternative more attractive.

Second, an alternative design and operational approach might make the gas plant significantly more attractive than the plant modeled here. DOE might opt to employ an interruptible gas supply to fuel the plant, taking advantage of the price reductions that result. This approach would probably require expanded oil-fired backup at additional capital cost, but there would likely be net economic benefits.

Third, rehabilitation of the existing 200-East plant to gas-fired boilers would undoubtedly be the least capital-intensive alternative and more cost-effective than coal-fired rehabilitation. This option was not evaluated as it was outside the scope of the project.

The feasibility of a gas plant onsite is, however, dependent upon an adequate fuel supply, and there is no gas supply onsite. Industry sources have informally indicated a willingness to extend a pipeline to Hanford for a long-term agreement to supply a cogeneration facility. It is unclear, however, whether the gas consumption of a 200-Area steam-only plant (plus other prospective markets) would be adequate incentive for pipeline extension. Also, the gas company will likely require a long-term, take-or-pay gas purchase contract to ensure payback of its investment. In such a situation, DOE may have problems with contract term limitations and contingent liability problems as discussed earlier in this document. Gas companies may be willing to commit to pipeline development without such contractual protection, however, if they perceive a future long-term market as a primary fuel for the many new facilities planned for the Hanford Site.

Conclusion #2

Privatization of a steam-only plant does not appear to be in the best interests of DOE from an economic standpoint.

The role of privatization is to enable government to capture some of the economic advantages that the private sector may enjoy for providing certain products or services, thereby providing the products/services more cheaply than government can provide them for its own consumption. From the analyses in Section 5, it is apparent that the private sector, because of its greater cost of capital, cannot construct, own, operate, and maintain any steam-only plant more cheaply than DOE can. Hence, privatization of a steam-only plant is economically disadvantageous for DOE.

Conclusion #3

Government-build cogeneration does not appear economically feasible unless a special arrangement can be worked with BPA.

As documented in Section 5, DOE cannot cogenerate power at an economic rate within the existing constraint that it must sell its power to BPA under a price ceiling of 36 mill/kWh. It may be appropriate, however, for DOE to develop a special arrangement with BPA (as a federal or DOE site) to transfer power at an economically viable price.

Conclusion #4

A privately-owned and operated cogeneration plant onsite has the potential for providing DOE with steam at a cost substantially below the LCC of steam provided by rehabilitating the 200-East plant.

The analysis provided in Section 5 demonstrates that, given an appropriate electricity sales agreement, a privatized cogeneration facility at Hanford could provide steam at a levelized cost well below the \$13.96/1,000-lb steam projected for rehabilitation of the existing plant. Privatization is possible and desirable because the private sector has access to lucrative power sales markets to which DOE has no access.

Conclusion #5

The best electricity market for Hanford-cogenerated electricity appears to be in the Pacific Southwest, rather than in the Pacific Northwest.

As demonstrated in Section 5, current and projected Pacific Northwest (PNW) utility electricity prices appear to be too low to support a viable privatized cogeneration plant at Hanford. Additionally, PNW sources generally project no escalation (over general inflation) in utility power acquisition prices over the next 20 years. Given that coal prices are expected to escalate at 1% and gas prices at 3% over the long term, it appears that combustion technologies are at a severe disadvantage for meeting future PNW power needs.

The electricity price structure in California, which is roughly 5 to 15 mill/kWh higher than comparable rates in the PNW, appears to support such development. In addition, several major Pacific Southwest (PSW) utilities expect their power acquisition prices to escalate at up to 2.0%/yr in real terms. This escalation factor is adequate to cover electricity generation cost growth due to fuel price escalation.

Conclusion #6

If a privatized cogeneration facility is developed at Hanford, it is likely to be gas-fired.

The economics of coal-fired cogeneration is substantially inferior to gas-fired cogeneration. This is due to the higher capital costs for coal-fired cogeneration plants. Thus, it is likely that any proposals to DOE will be for a gas-fired plant. There is no adequate gas supply close to Hanford, and so the feasibility of such a proposal will rest upon the gas industry's willingness to extend a pipeline onto the Hanford Site.

Conclusion #7

DOE's existing contracting authority appears adequate for development of a privatized cogeneration facility.

Any privatized cogeneration facility onsite will likely be developed primarily to sell electrical power at a profit. Sale of steam to DOE will be a secondary revenue stream to the owner. Under this scenario, the contractor will likely agree to a companion operating agreement that provides for steam sale to DOE on an annual basis, provided DOE grants a long-term lease for the cogeneration site that guarantees long-term delivery of services essential to plant operation.

7.0 REFERENCES

American Association of Cost Engineers. 1990. AACE Recommended Practices and Standards, Standard Cost Engineering Terminology. AACE Standard No. 10S-90, American Association of Cost Engineers, Morgantown, West Virginia.

Brown, D. R., et al. 1987. An Assessment Methodology for Thermal Energy Storage Evaluation. PNL-6372, Pacific Northwest Laboratory, Richland, Washington.

Electric Power Research Institute (EPRI). 1989. Technical Assessment Guide, Electricity Supply-1989. EPRI P-6587-L, Electric Power Research Institute, Palo Alto, California.

Kaiser Engineers Hanford Company (KEH). 1990. Conceptual Design Report Steam: System Rehabilitation, Phase II. Prepared for Westinghouse Hanford Company, Richland, Washington.

Lippiatt, B. C., and R. T. Ruegg. 1990. Energy Prices and Discount Factors for Life-Cycle Cost Analysis. NISTIR 85-3273-5, U.S. Department of Commerce, Washington, D.C.

Northwest Power Planning Council. 1989. Financial and Economic Assumptions 89-21. Northwest Power Planning Council, Portland, Oregon.

U.S. Department of Energy (DOE). 1990. "Request for Proposal Number DE-RP06-91RL 11905." DOE Richland Field Office, Richland, Washington.

Van Knapp, D. P., et al. 1989. American Jurisprudence, Second Edition. The Lawyers Co-operative Publishing Company, Rochester, New York, and Bancroft-Whitney Company, San Francisco.

Washington Department of Ecology, U.S. Environmental Protection Agency, U.S. Department of Energy. March 1990. Hanford Federal Facility Agreement and Consent Order (Tri-Party Agreement).

Westinghouse Hanford Company. 1990. Conceptual Design Report Steam System Rehabilitation, Phase II L-017 Project. WHC-SDL017-CDR-001 Rev. 0, Westinghouse Hanford Company, Richland, Washington.

APPENDIX A

DISCUSSION OF THE LEGAL CONTEXT OF THE ACQUISITION OF A STEAM SUPPLY FOR THE HANFORD 200 AREA

APPENDIX A

DISCUSSION OF THE LEGAL CONTEXT OF THE ACQUISITION OF A STEAM SUPPLY FOR THE HANFORD 200 AREA

This appendix discusses four DOE statutory authorities and their relation to using a private entity to provide steam for the Hanford Site's 200 Area. These authorities deal with the Department's authority 1) to enter into long-term contracts, 2) to accept contingent liabilities, 3) to indemnify its contractors, and 4) to use Shared Energy Savings legislative authority.

A.1 LONG-TERM CONTRACTING AUTHORITY

For purposes of this discussion, it is assumed that DOE desires to contract with a private contractor for the sale of steam to the Department for its use at the 200 Area. The steam-generating facility would be located on land leased to the private contractor in or near the 200 Area and would be financed, owned, and operated by the private contractor.

One of the purposes of Hanford's Private Sector Participation (PSP) Initiative is to reduce DOE's near-term costs in the acquisition of products and services. Thus, it is assumed that DOE would prefer a multi-year contract that calls for fairly equal unit costs for steam over the life of the contract. Likewise, the Department would prefer not to be required to obligate the entire amount to be paid for steam over the life of the contract in the fiscal year in which the contract is signed. Instead, it is assumed that DOE would want to be able to obligate annually only the amount needed to pay for steam purchases in that particular year.

Further, a prospective private contractor is assumed to prefer a relatively long-term contractual commitment from DOE in order to mitigate the business risk he incurs in using his own capital funds to construct a steam generation facility. The question addressed in this section is whether DOE has the statutory authority to enter into such a multi-year contract to purchase steam.

A.1.1 Anti-Deficiency Act

Examination of DOE's multi-year contracting authority starts with consideration of the Anti-Deficiency Act.^(a) This Act embodies certain federal governmental fiscal principles that influence DOE's ability to enter into contracts under the various specific statutes by which Congress has given the Department and its predecessors contracting authority. The Anti-Deficiency Act provides in relevant part:

(a) 31 U.S.C.A. §1341. United States Code Annotated (U.S.C.A.). 1983. West Publishing Company, St. Paul, Minnesota.

- (a)(1) An officer or employee of the United States government or of the District of Columbia government may not --
 - (A) make or authorize an expenditure or obligation exceeding an amount available in an appropriation or fund for the expenditure or obligation; or
 - (B) involve either government in a contract or obligation for the payment of money before an appropriation is made unless authorized by law.

In general, this Act prohibits a government agency official from making payments--or committing the government to make payments at a future time--for goods and services unless there is enough money in an agency appropriation available at the time of the commitment to cover the entire costs under the contract.^(a) That is, the Act generally prohibits an agency from committing through a long-term contract to pay for goods or services provided to the government over the life of the contract unless the agency obligates enough money in its appropriation for the year in which the contract is signed to cover all the payments for the goods or services over the entire life of the contract.

The Anti-Deficiency Act contains an exception to this general rule. The Act's subsection (a)(1)(B) states that no agency may involve the government in a contract or other obligation for the payment of money in advance of or in excess of appropriations made for that purpose "unless authorized by law." The U.S. General Accounting Office (GAO) has stated that the contracting authority referred to here is statutory authority which specifically authorizes an agency to enter into a long-term contract or other obligation prior to enactment of the applicable appropriation.^(b)

To constitute an exception to the Anti-Deficiency Act, such contract authority must be specific authority to incur a contractual obligation in excess or advance of appropriation, not merely the general authority any agency has to enter into contracts to carry out its functions. This kind of contract authority is generally stated by statute in clear and unmistakable terms.^(c)

The Anti-Deficiency Act restrictions appear to be reflected in various ways in the several statutory contracting authorities under which DOE enters into contracts. Three of those authorities have some relevance to DOE's options for

-
- (a) Principles of Federal Appropriations Law; U.S. General Accounting Office, Office of General Counsel; First Edition, June 1982, Washington, D.C.; p. 5-8.
 - (b) Principles of Federal Appropriations Law; U.S. General Accounting Office, Office of General Counsel; First Edition, June 1982, Washington, D.C.; p. 5-23.
 - (c) St. Elizabeth's Hospital, B-203984, 61 Comp. Gen. 661, September 30, 1982.

purchasing steam for the 200 Area: Section 646 of the DOE Organization Act, Section 161(u)(1) of the Atomic Energy Act of 1954 (AEA), and Section 161(u)(2) of the AEA.

A.1.2 Section 646 of the DOE Organization Act

Section 646 of the DOE Organization Act^(a) is an example of the general contracting authority any Federal agency has to enter into contracts. This section provides that

- (a) The Secretary is authorized to enter into and perform such contracts, leases, cooperative agreements, or other similar transactions with public agencies and private organizations and persons, and to make such payments (in lump sum or installments, and by way of advance or reimbursement) as he may deem to be necessary or appropriate to carry out functions now or hereafter vested in the Secretary.
- (b) Notwithstanding any other provision of this subchapter, no authority to enter into contracts or to make payments under this subchapter shall be effective except to such extent or in such amounts as are provided in advance in appropriation Acts.

Because the purchase of steam to serve the 200 Area's needs would presumably be deemed "necessary or appropriate to carry out functions now or hereafter vested in the Secretary," this section seems to give the Department the authority to contract with a private company for the purchase of steam. Because this section mentions no specific time limit on the term of contracts entered into using this authority, DOE could rely on this section to enter into a multi-year contract that would be of sufficient duration both to meet the Department's steam needs in the 200 Area and to give a private contractor sufficient assurance to be willing to risk capital funds to build a steam-generating facility on the Hanford Site.

This section does, however, contain the limitation in subsection (b) that would require the Department to have in its appropriation for the year in which it signs the contract sufficient funds to cover all the payments for steam contemplated under the contract. Thus, it appears that this contracting authority would not be useful for purposes of contracting for steam in the PSP context because DOE would have to obligate the entire amount of the contract payments from its appropriation in the year of the contract. Doing so would defeat one of the main purposes of the PSP Initiative, which is to allow the Department to spread the capital and operating costs associated with the procurement of services over the life of the contract rather than having to obligate funds to cover all or most of such expenses in the first year of the contract term.

(a) 42 U.S.C.A. §7256 (West 1983).

A.1.3 Section 161(u)(1) of the Atomic Energy Act of 1954

DOE apparently has two specific authorities that allow multi-year contracting as an exception to the Anti-Deficiency Act's general rule. Both appear in section 161(u) of the AEA. The first of these, subsection 161(u)(1),^(a) authorizes the Department to enter into contracts "for the purchase or acquisition of reactor services or services related to or required by the operation of reactors." Contracts entered into under this specific authority may be for periods "not to exceed five years from the date of execution of the contract."

This authority appears to be inappropriate to use for a Hanford steam contract because of the relatively short contract term that this subsection authorizes. Under any contracting scenario, approximately the first three years of the contract term are likely to be devoted to constructing the steam generation facility. Steam would then be delivered during the remainder of the contract term. Using the 5-year contracting authority of subsection 161(u)(1) would, therefore, allow only about two years of steam deliveries. A 5-year contract, or a series of separate 5-year contracts under this authority, may not provide sufficient assurance to a prospective contractor that his capital investment could be recovered through payments under the contract(s).

It is also questionable whether the purchase of steam could be considered to be "reactor services or services related to or required by the operation of reactors," given the purposes for which the steam will be used in the 200 Area. If the purchase of steam is not included within the purpose of this subsection, DOE could not use this authority to purchase steam.

A.1.4 Section 161(u)(2) of the Atomic Energy Act of 1954

Subsection 161(u)(2) of the AEA^(b) appears to provide the Department with sufficient authority to enter into a multi-year contract for the purchase of steam for the 200 Area. Subsection 161(u)(2) provides in relevant part that DOE may

(u)(2)(A) enter into contracts for such periods of time as the (Department) may deem necessary or desirable for the purchase or acquisition of any supplies, equipment, materials, or services required by the (Department). . . . Such contracts shall be entered into for periods not to exceed five years each from the date of initial delivery of such supplies, equipment, materials, or services or ten years from the date of execution of the contracts excluding periods of renewal under option.

(a) 42 U.S.C.A. §2201(u)(1). United States Code Annotated (U.S.C.A.). 1973. West Publishing Company, St. Paul, Minnesota.

(b) 42 U.S.C.A. §2201(u)(2) (West 1973).

It is likely that steam needed at Hanford's 200 Area would come within the meaning of "supplies, equipment, materials, or services required by the (Department)."

Though it is not entirely clear, an argument can be made that this subsection 161(u)(2) contracting authority is the kind of specific authority that fits within the Anti-Deficiency Act's "unless authorized by law" exception, that is, the authority to incur a contractual obligation in excess or advance of appropriation. In Principles of Federal Appropriations Law, the GAO cites 10 U.S.C.A. §2306(g)(1) as an example of specific statutory authority for multi-year contracting with annual funds that fits within the Anti-Deficiency Act exception.^(a) That statute authorizes the Department of Defense to award contracts for up to 5-year periods when procuring certain types of services or related supplies in overseas locations.

The legislative history of this DOD statute indicates that it was Congress' intention in passing this law to give DOD the same funding arrangements that it had already given to the Atomic Energy Commission, DOE's predecessor agency, when it had previously passed subsection 161(u)(2) of the AEA.^(b) It can, therefore, be argued that subsection 161(u)(2) gives DOE the same authority for multi-year contracting with annual funds that the GAO acknowledges 10 U.S.C.A. §2306(g)(1) gives to the Department of Defense.

The wording cited above regarding contract terms of either 5 years or 10 years leaves somewhat ambiguous the period for which DOE can contract for services under this subsection. The legislative history of this subsection, however, indicates that it was Congress' intent that DOE be able to use this authority to enter into a contract for a period of 10 years from the date of the contract's execution, although no more than 5 of those 10 years can be used for the actual delivery of services.^(c) The remainder of the total contract period, a period of up to five years, is to cover the time that the contractor may need to construct the special facilities needed to produce and deliver the services. That is, if DOE and its new contractor agree the contract should cover the period during which the contractor would construct the steam generation facility--3 years, for example--the original contract period could be set for a total of 8 years. This would include the 3 years for construction and the maximum 5 years of steam deliveries allowed by this subsection. If it was found to be unnecessary to provide for the facility construction period in the original contract, this subsection would allow DOE to enter into a steam

-
- (a) Principles of Federal Appropriations Law; U.S. General Accounting Office, Office of General Counsel; First Edition, June 1982, Washington, D.C.; p. 4-22.
 - (b) 1968 U.S. Code Congressional and Administrative News; 90th Congress, 2nd Session; Legislative History; p. 2485.
 - (c) 1958 U.S. Code Congressional and Administrative News; 85th Congress, 2nd Session; Legislative History; p. 3604-5. See also, Hearings on the AEC "Omnibus" Bill, H.R. 13120, Before the Subcommittee on Legislation of the Joint Committee on Atomic Energy, 85th Congress, 2nd Session (July 10, 17, 18, 1958), pp. 30-38.

contract for a maximum of 5 years for the first contract period. In either case, subsection 161(u)(2) authorizes DOE to contract for no more than 5 years of steam deliveries in the initial contract period.

This subsection also authorizes DOE to enter into options for additional contract periods and puts no limit on the number of such option periods. Like the initial contract period, each optional period of steam deliveries would be limited to 5 years. This limitation seems evident based on the subsection stating that contracts can be for ". . . *periods not to exceed five years each* . . ." Under, this statutory authority, therefore, DOE can commit to a series of 5-year contract periods for the delivery of steam. The first of these periods could be part of a longer contractual commitment, for up to 10 years, the additional period being devoted to the construction of the steam generation facility.

It should be noted that this somewhat ambiguous contracting authority may have been given a different interpretation by DOE's Office of General Counsel. In a memorandum^(a) addressing this subject, John Herrick, Senior Finance Counsel, states that subsection 161(u)(2) provides for a term of 10 years, with option periods, for the type of contract at issue here. This memo, however, does not explicitly express an opinion as to whether or not there is a 5-year limitation on DOE's receipt of services under such contracts. In the absence of new contracting authority that may be provided by currently pending legislation, this issue of whether subsection 161(u)(2) authorizes contracts for five or ten years of delivery of services needs formal clarification from DOE Headquarters.

If DOE chooses to use this authority to purchase steam, it appears that the Department would be required to obligate in each year against its then-current operating expense appropriation only enough funds needed to cover the value of the steam expected to be delivered during that year. It would not be necessary to obligate or set aside in each year an amount that would also cover the total termination charges that the Department would be required to pay in the event it chose to terminate the contract in that particular year.^(b) (Termination charges are discussed below in the section dealing with contingent liabilities.) This issue should, however, receive further review by the DOE Office of General Counsel and DOE procurement and contracting staff.

If DOE decides to use this authority, a part of subsection 161(u)(2)(A) (not explicitly cited above) requires DOE to make four determinations regarding the nature of the services being acquired:

-
- (a) Memorandum re: Private Sector Participation in Financing and Construction of the Transuranic Waste Interim Storage Facility, from John Herrick; Senior Finance Counsel, Office of General Counsel; February 12, 1991.
 - (b) 1958 U.S. Code Congressional and Administrative News; 85th Congress, 2nd Session; Legislative History; p. 3606.

1. It is advantageous to the government to purchase steam from a commercial source rather than producing steam from government-owned facilities. Depending on its results, the life-cycle cost (LCC) analysis being prepared for this project would probably be the major element of such a determination.
2. The furnishing of the steam would require the contractor to construct or acquire special facilities. The term "special facilities" is defined as "any land and any depreciable buildings, structures, utilities, machinery, equipment, and fixtures necessary for the production or furnishing of such. . . material, or services and not available to the vendors or suppliers for the performance of the contract."^(a)
3. The amortization of the contractor's capital costs chargeable to DOE constitutes an appreciable portion of the cost of contract performance, excluding cost of materials.
4. The contract is more advantageous to the government than a similar contract not executed under this particular contracting authority.

The purpose of these determinations is to require the Department to explore the use of government-owned facilities, and other means of short-term contracting, before committing to long-term contracts in which the government pays the amortization for all or part of the privately owned facilities.^(b)

Subsection 161(u)(2)(B) further requires that DOE be guided by three principles when entering into contracts under this authority. Those three principles are directed generally toward ensuring that the Department adheres to principles of good contracting. None of these principles should prove to be an obstacle to the use of this statutory contracting authority to procure steam.

A.1.5 Pending Legislation

DOE's current statutory authority to enter into long-term contracts could be augmented by new legislation. A bill that was considered by Congress during 1991 and will likely be reconsidered in 1992 would authorize DOE to enter into contracts for the procurement of products and services that are necessary to support waste cleanup and modernization activities at DOE facilities. The initial term of such contracts would be for a maximum period of 30 years and could include options for two 10-year extensions. It appears that steam would be among the types of products and services that this bill would authorize the Department to purchase by means of long-term contract.

(a) 42 U.S.C.A. §2201(u)(3) (West 1973).

(b) 1958 U.S. Code Congressional and Administrative News; 85th Congress, 2nd Session; Legislative History; p. 3605.

A.1.6 Federal Acquisition Regulations and DOE Acquisition Regulations

The Federal Acquisition Regulations (FAR), contained in Title 48 of the Code of Federal Regulations (C.F.R.), establish rules that apply to federal procurement actions generally. At least two FARs may have an impact on DOE's authority to enter into long-term contracts. The first of these, 48 C.F.R. 37.106, provides that

When contracts for services are funded by annual appropriations, the term of contracts so funded shall not extend beyond the end of the fiscal year of the appropriation except when authorized by law. . . .

A similar potential obstacle is raised by 48 C.F.R. 32.703-3:

A contract that is funded by annual appropriations may not cross fiscal years, except in accordance with statutory authorization. . . .

Each of these regulations appears to be predicated upon the Anti-Deficiency Act prohibitions discussed above and raises essentially the same question that must be answered in relation to subsection 161(u)(2) of the AEA: Does that statutory authority to enter into long-term contracts constitute sufficient authorization to fit within the Anti-Deficiency Act (and FAR) "unless authorized by law" exception? The answer to this question as it pertains to subsection 161(u)(2) will also likely apply to these FAR requirements.

It should also be noted that 48 C.F.R. 37.106 may not even apply to the procurement of steam for the Hanford 200 Area because a contract to buy steam may not be considered a contract for services governed by that section. The FARs define "service contract" as "a contract that directly engages the time and effort of a contractor whose primary purpose is to perform an identifiable task rather than to furnish an end item of supply."^(a) Steam could arguably be considered "an end item of supply" rather than the services of contractor personnel to perform an identifiable task.

The DOE Acquisition Regulation (DEAR) supplements the FARs and applies specifically to DOE procurements. A review of the DEARs indicated no requirements that would bear on the Department's authority to enter into a long-term contract to purchase steam.

A.1.7 DOE Order 4200.3B

DOE Order 4200.3B provides the policy, procedures, and responsibilities for the management of support service contracts within the Department.^(b) It is, first of all, questionable whether a contract to procure steam would have

(a) 48 C.F.R. §37.101 (1988).

(b) DOE Order 4200.3B, "Management of Support Services Contract Activity," Office of Organization and Management Systems, October 3, 1985.

to be reviewed under this Order. The order defines "support services" as "...all services and activities required by the Government to support the development and execution of assigned functions and programs."^(a) The examples of such services and activities provided in the Order include personal services that could be provided by DOE or contractor staff members. None of the examples include provision of a commodity or "an end item of supply" (see above discussion of the FAR), such as steam. It could thus be argued that this Order applies only to personal services contracts and not to contracts for the provision of a physical commodity such as steam.

If a steam contract would have to be reviewed under this Order, it may have an important bearing on whether the Department could enter into a long-term contract. The Order's section 5(e) specifies that the basic contract may be for a period of 3 years unless there is a valid justification for a longer period of performance. The contract can be extended for a maximum period of 5 years by exercising two successive 1-year options as allowed by the Order. These limitations seem to be in conflict with the contract periods authorized by subsection 161(u)(2) of the AEA discussed above. Clarification should, therefore, be sought from DOE Headquarters as to whether this Order would apply to a Hanford steam contract and, if so, how this apparent conflict can be resolved in favor of allowing a contract term of up to 10 years with 5-year option periods.

A.1.8 Summary and Conclusions

Subsection 161(u)(2) of the AEA appears to authorize DOE to enter into a long-term contract for the purchase of steam for Hanford's 200 Area. The question of whether this section would authorize DOE to contract for 5-year or 10-year periods of steam deliveries needs formal clarification from DOE's Office of General Counsel. DOE's authority under this statute to obligate in each year against its annual operating expense appropriation only enough funds to pay for that year's steam needs should also be confirmed. Having to obligate sufficient funds to cover all the payments for steam contemplated for the entire term of the contract from the appropriation for the year in which it signs the contract would obviously negate some of the expected benefits of privatization.

Even this contracting authority may, however, not be optimal for DOE's purposes. Prospective private contractors may prefer to enter into a 30- or 40-year contract to supply steam rather than a contract for 5 or 10 years of steam deliveries with options for additional 5- or 10-year periods. The longer contract periods would probably provide the private contractor with more assurance that DOE would purchase steam for at least most of the steam plant's useful life. This is particularly true if the contractor did not intend to build a cogeneration facility that could be used to supply electricity to non-DOE customers. Because of the reduction in business risk that the longer contract (e.g., a 30-year contract rather than a series of 5- or 10-year contracts) would provide, a contractor might be willing to recover

(a) DOE Order 4200.3B, Section 4b.

capital costs through the price it charges for steam over a longer period. If the contractor could accept a longer time to amortize capital costs, he would be more likely to agree to lower steam charges in the first years of the contract period than he would if he wanted to recover all capital costs in, for instance, the first 5 years of the contract.

While the preferences of a future steam supplier cannot be fully known at this time, it is suggested that DOE continue to pursue enactment of legislation that would authorize contracts with periods longer than 10 years. The authority to contract for a period of up to 30 years, with options for two 10-year extensions, would give DOE the negotiating flexibility that could result in lower costs for steam over the life of the long-term contract.

A.2 AUTHORITY TO ACCEPT CONTINGENT LIABILITIES

A "contingent liability" is a potential liability that may become an actual liability if some particular event happens or does not happen. In the particular situation at issue here, it is assumed that a private contractor would be unwilling to invest in capital facilities on the Hanford Site without some contractual guarantee that DOE would cover any unamortized capital costs if DOE terminated the contract before the contractor had fully recovered his capital investment through the charges for steam delivered to the Department. A contractual clause by which DOE could provide such a guarantee, and in so doing incur a contingent liability, is referred to as a termination clause.

The general rule governing contractual treatment of contingent liabilities is that, absent express statutory authority to the contrary, the government may not incur a contractual contingent liability where the amount of the government's liability is indefinite, indeterminate, or potentially unlimited.^(a) Such an agreement would violate the Anti-Deficiency Act.^(b)

A.2.1 Subsection 161(u)(3) of the Atomic Energy Act of 1954

Subsection 161(u)(3) of the AEA apparently provides the Department with express statutory authority to provide for contingent liabilities in a steam contract as long as the contract is formed using the long-term contracting authority of the Act's subsections 161(u)(1) or (u)(2). This express authority apparently fits within the "unless authorized by law" exception of the Anti-Deficiency Act and, therefore, would give the Department more latitude in incurring contingent liabilities than would be allowed by the general rule. Subsection 161(u)(3) authorizes DOE to include in contracts made under this subsection provisions which limit the obligation of funds to estimated annual deliveries and services and the unamortized balance of such amounts due for special facilities as the parties shall agree is chargeable to the performance

(a) Principles of Federal Appropriations Law; U.S. General Accounting Office, Office of General Counsel; First Edition, June 1982, Washington, D.C.; p. 6-41.

(b) 31 U.S.C.A. §1341 (West 1983).

of the contract. Any appropriation available at the time of termination or thereafter made available to the Department for operating expenses shall be available for payment of such costs which may arise from termination as the contract may provide.

To comply with this section, DOE could negotiate an agreed-upon means of calculating the remaining unamortized amount of the contractor's capital costs attributable to the contract for each year of the contract period. The contract should include a termination clause expressly stating that, if the contract is terminated at the Department's convenience, the DOE's obligation to the contractor will be limited to an amount equal to the cost of estimated steam deliveries for the year of termination plus the remaining unamortized balance of the contractor's capital costs as of that year, as determined through the agreed-upon calculation.

Such contractual language would appear to meet the requirements both of the AEA's subsection 161(u)(3) and of the Anti-Deficiency Act. In the event of termination, DOE could pay such costs from any appropriation for operating expenses available at the time of termination or thereafter made available to the Department. As stated above, it would not be necessary for DOE to obligate or set aside the total termination charges at the time of entering into the contract.^(a)

A.2.2 General Authority to Incur Contingent Liabilities

If DOE enters into a steam contract using statutory contracting authority other than subsection 161(u)(2), this subsection 161(u)(3) authority to enter into contingent liabilities could not be used. The Department could, however, still seek to enter into an incrementally funded steam contract that provides for contingent liabilities. Various Comptroller General's decisions indicate that contracts committing the government to pay for termination charges do not violate the Anti-Deficiency Act as long as they contain a provision that obligates the government only to the extent of funds allotted to the contract and stipulates that the government will not have any further monetary obligation to the contractor in the event that no additional funds become available.^(b)

DOE could, therefore, accept a contingent liability, if it so chooses, even if it does not use subsection 161(u)(2) contracting authority. DOE could include in the contract a termination clause stating that the government's liability will be no more than the funds allotted to the contract for the year in which termination takes place. It would also be advisable to try to include in the contract a clause similar to that described above which expressly limits DOE's liability upon termination to an amount equal to the estimated cost of steam

(a) 1958 U.S. Code Congressional and Administrative News; 85th Congress, 2nd Session; Legislative History; p. 3606.

(b) Honeywell Inc., B-192988, July 11, 1979, 79-2 CPD 23; Raytheon Co., B-198257, June 12, 1980, 80-1 CPD 414; Hughes Aircraft Corp., ASBCA No. 24601, 83-1 BCA 16,396.

needs for that year plus the remaining unamortized balance of the contractor's capital costs attributable to the contract according to an agreed-upon calculation.

Such a clause would provide the definition of and limitation on liability that are needed to comply with the Anti-Deficiency Act. In this case, however, DOE would probably have to obligate in each year of the contract sufficient funds to cover the total termination charges that would have to be paid to the contractor in the event that the Department terminated the contract in that particular year. Having to do so may decrease the benefits of undertaking the project through privatization.

A.2.3 Pending Legislation

The private sector participation bill that Congress may consider during 1992 would allow the Department to include a termination provision that obligates DOE to pay for the unamortized balance of any special facilities acquired or constructed by the private contractor, if such acquisition or construction constitutes a significant portion of the investment by the private contractor under the contract. The bill does not indicate how a "significant portion of the investment" would be determined. The bill would further allow DOE to use any appropriations that are available to the Department for operating expenses for the fiscal year of the termination or for any fiscal year after such fiscal year pay such unamortized balance and any other costs resulting from termination. This latter provision would seem to relieve the Department from having to obligate or set aside an amount to cover the total termination charges in each year of the contract.

A.2.4 Summary and Conclusions

DOE's ability to assure a prospective private contractor that he would be able to recover the unamortized portion of his capital costs in the event that DOE terminated the contract prior to completion of the contract period is essential to achieving the full benefits of PSP contracting. If DOE can offer such a termination clause, the contractor would probably be more likely to agree to a relatively level price for steam throughout the contract period. If DOE cannot offer to incur such a contingent liability, the contractor would be likely to want to recover all or most of the capital costs in the first few years of the contract.

A.3 AUTHORITY TO INDEMNIFY ITS CONTRACTORS

The Department of Energy does have the authority to agree to indemnify its contractors under various circumstances. In the steam contract context, this means that DOE can agree to pay the liabilities its steam contractor could possibly incur because of damages to the general public from the contractor's DOE-related activities. This authority stems both from the Price-Anderson Act, as amended, and from general contracting authority granted to the Department by the AEA and the DOE Organization Act.

A.3.1 Price-Anderson Act Authority

When a DOE contractor's activities involve the risk of public liability for a nuclear incident, the AEA, as amended by the original Price-Anderson Act^(a) and subsequently by the Price-Anderson Amendments Act of 1988,^(b) requires that DOE must indemnify its contractor.^(c) The Act defines public liability to mean "...any legal liability arising out of or resulting from a nuclear incident,..."^(d) A nuclear incident is an occurrence that results in death, bodily injury, or loss of property from the radioactive, toxic, explosive, or other hazardous properties of source, special nuclear, or byproduct materials.^(e) The Act sets the dollar limit for DOE aggregate liability and contractual indemnity coverage for a single nuclear incident at approximately \$7 billion.^(f) These and other provisions of the Act create indemnity responsibilities for DOE that are quite broad in terms of what contractors and what kinds of contractor activities are to be indemnified.

Given the apparent non-nuclear nature of the various steam procurement options, however, it appears at this time unlikely that DOE would be required, or even have the authority, to indemnify its steam contractor under the Price-Anderson Act. The ultimate resolution of this question, however, will depend on what form the steam production facility actually takes and what relation it has to other site activities. Given the breadth of DOE's Price-Anderson indemnity coverage responsibilities, it is conceivable that the steam contractor's activities on the Hanford Site may be covered by the Act. The issue of whether indemnification of the steam contractor is required by the Price-Anderson Act should, therefore, be revisited in the future as the actual physical parameters of the steam production facility take more definite shape.

A.3.2 General Contract Indemnification Authority

Even if the steam contractor cannot be covered by Price-Anderson, DOE does have the alternate authority to enter into an indemnification agreement under its general contracting authority. This authority is confirmed and explained at 48 C.F.R. §950.7011, which is one of the Code of Federal Regulations sections that makes up the Department of Energy Acquisition Regulation (DEAR).

(a) Act of September 2, 1957, P.L. 85-256, 71 Stat. 576.

(b) Act of August 20, 1988, P.L. 100-408, 102 Stat. 1066. This Act amends various provisions of the Atomic Energy Act of 1954, codified at 42 U.S.C.A. §§2011-2282, with the major amendments being made to section 170 of the Atomic Energy Act of 1954.

(c) 42 U.S.C.A. §2210(d)(1)(A). United States Code Annotated (U.S.C.A.). 1990 Supplement. West Publishing Company, St. Paul, Minnesota.

(d) 42 U.S.C.A. §2014(w) (West Supp. 1990).

(e) 42 U.S.C.A. §2014(q) (West Supp. 1990).

(f) McNett, John F., Nuclear Indemnity for Government Contractors Under the Price-Anderson Act; 1988 Amendments, Public Contract Law Journal, Fall 1989.

That section states that it is normally DOE policy to require its contractors to obtain insurance coverage against public liability for non-nuclear risks. There may, however, be circumstances in which a contractual indemnity may be warranted to protect a DOE contractor against liability for uninsured non-nuclear risks. (This DEAR section does not give examples of such circumstances.) When such circumstances do arise, the heads of contracting activities are responsible for submitting to the Secretary or his designer for review and decision all pertinent information concerning the need for, or desirability of, providing a general authority indemnity to a DOE contractor.

The maximum amount of general authority indemnity extended to a fixed-price contractor who incurs non-nuclear risk should normally be equivalent to the amount of insurance that the contractor usually carries to cover such risks in other commercial operations. If the risk involved in the contract with DOE is dissimilar to those normally encountered by the contractor, DOE's indemnification would be for the amount that the contractor otherwise would have reasonably carried to insure his contract risk. In the case of cost-reimbursement contracts, the DEAR section does not restrict or affect DOE's normal policy of paying its contractors for the allowable cost of losses and expenses incurred in the performance of the contract work, within the maximum amount of the contract obligation.

If DOE does choose to indemnify the steam contractor, the contractual identification agreement must contain two elements in order to comply with the Anti-Deficiency Act.^(a) First, it must expressly limit the government's liability to the Department's appropriations available at the time the liability comes due.^(b) This limitation must contain no implication that Congress will appropriate money to meet any deficiency. Second, the government's liability must be limited and determinable. In other words, the indemnification agreement must specifically state the dollar limits of the potential liability that DOE is assuming, as well as the method of calculating the liability that DOE and the contractor will use if the Department actually has to assume the contractor's liability in the future.

A.3.3 FAR 52.228-7 Insurance--Liability to Third Persons

Another means of providing a quasi-indemnity to contractors is contained in FAR 52.228-7 Insurance--Liability to Third Persons.^(c) Under this authority, DOE can require the contractor to carry a minimum amount of insurance to cover public liability claims and then agree to reimburse the contractor for liabilities above and not compensated by that insurance. The granting of this coverage must make clear that the government's liability is subject to the availability of appropriated funds at the time the contingent event occurs and that extension of this coverage should not be construed as implying that the Congress will appropriate funds sufficient to meet deficiencies.

(a) 31 U.S.C.A. §1341 (West 1983).

(b) 48 C.F.R. §950.7001(a).

(c) 48 C.F.R. §52.228-7.

A.3.4 Summary and Conclusions

DOE does have the authority to indemnify its contractors for potential liabilities for damage to the general public that the contractors may incur through contracted-for activities. If, as the steam plant project takes shape, it appears that the steam plant contractor is under risk of public liability for a nuclear incident as defined by the AEA, as amended, DOE would have to agree to indemnify that contractor.

Given the nature of the options being considered in this ADD, however, it appears at this time unlikely that DOE would be required to extend identification for nuclear risks to the steam contractor. If there are no nuclear risks associated with the steam plant activities, DOE would still have the option of granting indemnification to its contractor. This could be done using the Department's general contract authority for indemnifying risks assumed by its non-nuclear contractors.

DOE would also have the option of covering its contractor's liabilities above and not compensated by insurance held by the contractor under FAR 52.228-7 Insurance--Liability to Third Persons. DOE can consider extending this coverage in light of the potential risks to the public involved in the steam plant venture, as well as whether such coverage would provide a useful incentive to interest prospective contractors in this project.

A.4 APPLICABILITY OF SHARED ENERGY SAVINGS AUTHORITY

The Shared Energy Savings (SES) legislation^(a) authorizes all federal agencies to enter into contracts of up to 25 years' duration for the purpose of achieving energy savings. As the legislative history^(b) of this authority makes clear, Congress intended that federal agencies implement this authority by using a particular kind of business arrangement to achieve energy savings. That arrangement is a shared energy savings contract with a private energy service company (ESCO).

Under a shared energy savings contract, the ESCO contracts with the building owner to determine how energy usage within the building can be reduced and to install appropriate energy conservation equipment in the building to achieve those reductions. The capital costs of installing the energy conservation equipment are paid entirely by the private energy service company. The ESCO recovers its costs and receives a return on its investment by sharing in the energy savings that accrue after the equipment has been installed. The owner of the building also benefits by sharing in the energy savings, as mutually agreed in the contract.

(a) 42 U.S.C.A. §§8287-8287(c) (West Supp. 1990).

(b) 1986 U.S. Code Congressional and Administrative News; 99th Congress, 2nd Session; Vol. 4; p. 1018.

Buildings in which the energy savings are to be achieved under the SES authority must be owned by the federal government. The legislation defines "energy savings" as "a reduction in the cost of energy. . .utilized in an existing federally owned building or buildings or other federally owned facilities. . . ."Such savings can be achieved in two ways: by "the lease or purchase of operating equipment, improvements, altered operation and maintenance, or technical services" or "the increased efficient use of existing energy sources by cogeneration or heat recovery, excluding any cogeneration process for other than a federally owned building or buildings or other federally owned facilities."^(a)

A.4.1 Summary and Conclusions

Because this SES authority extends only to situations in which a private company installs new equipment or otherwise adjusts the energy usage in federally owned buildings, it appears that none of the options that include private ownership of a new steam generation facility, including a privately owned cogeneration facility, can take advantage of this SES contracting authority. It would appear to stretch the authority granted by this legislation to argue that SES allows DOE to contract with a private company to build, operate, and own a new steam-generating facility because such an arrangement would reduce or eliminate the energy costs associated with the old DOE-owned 200 Area steam plants.

Such an argument would, in effect, entail using this authority to contract for an entirely new, privately owned facility, rather than for privately owned equipment or other improvements to be installed in an existing DOE-owned building. Undertaking the former project does not appear to be within the authority granted by the SES legislation. In the Hanford 200 Area steam plant context, it appears that this authority could properly be used only to contract with a private company to install energy saving equipment in the existing 200 Area steam plants.

It should be noted, however, that staff of DOE's Inhouse Energy Management group at DOE Headquarters may have expressed the opinion that the SES authority can indeed be used to acquire steam from a privately owned steam plant. This issue should, therefore, be formally reviewed and clarified by DOE Headquarters.

(a) 42 U.S.C.A. §8287(c) (West Supp. 1990).

APPENDIX B

DOE'S LONG-TERM LEASING AUTHORITY

APPENDIX B

DOE'S LONG-TERM LEASING AUTHORITY

Three separate statute sections grant DOE the authority to lease government land to private parties: Subsection 161(g) of the Atomic Energy Act of 1954;^(a) Subsection 649(b) of the DOE Organization Act;^(b) and Section 120 of the Atomic Energy Community Act of 1955.^(c) DOE Order 4300.1B also governs the Department's ability to lease land.

The authority granted by the Atomic Energy Community Act appears to be inapplicable to the Hanford steam plant project. To use this authority, DOE would have to determine that the lease of land would serve to prevent or reduce the adverse economic impact of actual or anticipated reductions in DOE's Hanford programs. Because it appears that a lease of Hanford land to facilitate the steam plant project would be unlikely to fit the purposes of this Act, this authority will not be addressed further. Draft legislation that may soon be reintroduced in Congress to augment DOE's contracting and leasing authority is also discussed below.

B.1 SUBSECTION 161(g) OF THE ATOMIC ENERGY ACT

Subsection 161(g) of the Atomic Energy Act^(d) provides that

[In the performance of its functions the (Department) is authorized to]

- (g) acquire, purchase, lease, and hold real and personal property, including patents, as agent of and on behalf of the United States, subject to the provisions of section 2224 of this title,^(e) and to sell, lease, grant, and dispose of such real and personal property as provided in this chapter.

Because steam has been used in the past at the 200 Area and is needed in the future to contribute to DOE's waste clean-up activities at that Area, a lease of Hanford land to facilitate the building of a facility that would supply that steam would seem indisputably to be part of the Department's functions authorized by the Act and, therefore, within the authority granted by this section. Subsection 161(g) contains no limitation on the time period for leases entered into under its authority nor does it contain any required minimum amount that DOE must charge the party leasing government land. This

(a) 42 U.S.C.A. §2201(g) (West 1973).

(b) 42 U.S.C.A. §7259(b) (West 1983).

(c) 42 U.S.C.A. §2349 (West 1973).

(d) 42 U.S.C.A. §2201(g) (West 1983).

(e) 42 U.S.C.A. §2224 is of no relevance to the issue being examined here.

Atomic Energy Act authority has been used in the past to enter into long-term leases of Hanford land. In 1964, the Atomic Energy Agency, DOE's predecessor, used this authority to lease 1000 acres for a term of 99 years to the State of Washington for nuclear-related purposes. In the mid-1970s, the Energy Research and Development Administration, also a DOE predecessor, leased approximately 1000 acres to the Washington Public Power Supply System for nuclear-related purposes. It should be noted, however, that both these long-term leases were entered into before the enactment of Subsection 649(b) of the DOE Organization Act (discussed below) which contains a 5-year limitation on the length of land leases. Therefore, the fact that DOE's predecessor agencies were able to use Subsection 161(g) in the past is not necessarily strong evidence that this authority can be used to lease Hanford land now. Because the ability to enter into a long-term lease of Hanford land is essential to the success of the steam plant project, DOE's current leasing authority should be clarified as soon as possible.

B.2 SUBSECTION 649(b) OF THE DOE ORGANIZATION ACT

Subsection 649(b) of the DOE Organization Act, in relevant part, states that

- (b) In carrying out his functions, the Secretary, under such terms, at such rates, and for such periods not exceeding five years, as he may deem to be in the public interest, is authorized to permit the use by public and private agencies, corporations, associations, or other organizations or by individuals of any real property. . . under the custody of the Secretary for Department purposes.

As for the leasing authority granted by the Atomic Energy Act, Subsection 649(b) would appear to authorize a lease of Hanford land to facilitate the acquisition of steam for DOE activities in that such a lease would be a means of "carrying out (DOE) functions" and "for Department purposes." This leasing authority also contains no minimum amount that DOE must charge the party leasing government land. Instead, it allows the Department to lease land "at such rates. . . as the Secretary may deem in the public interest." Unlike the Atomic Energy Act authority, however, Subsection 649(b) allows leases for periods of no longer than five years. Also, because this subsection does not mention the authority to grant lease extensions, DOE apparently cannot grant extensions to leases beyond the original 5-year period allowed by this authority.

The 5-year limitation of leases established by Subsection 649(b) should, however, not prove to be an obstacle to DOE leasing land at Hanford for a substantially longer period. The Department can lease land either under the authority of the Atomic Energy Act of 1954 or of the DOE Organization Act. Because the Atomic Energy Act contains no limitation on the terms of leases, this authority appears to be the one most useful for the steam project.

B.3 DOE ORDER 4300.1B

DOE Order 4300.1B, issued July 1, 1987, establishes Department-wide policies and procedures for DOE's development, use, and disposal of land under its control. Chapter IV of this order bears upon DOE's authority to dispose of full or partial interests in land when it uses the leasing authority of the DOE Organization Act to do so. This Chapter reiterates authority to lease land as well as the five-year limitation on such leases.

Specifically, Section c(1) of Chapter IV provides that

- (1) Temporarily underutilized DOE-controlled property may be out-granted by lease; however, terms of such leases shall be for not more than 5 years as provided in Public Law 95-91 (91 Stat. 565) (the DOE Organization Act as discussed above) and leases may not be renewed.

Before granting a lease, this section directs DOE to obtain an appraisal of the land to be leased. Payment received from the lessee must be no less than the appraised fair market rental value except in cases where it is clearly in the best interest of the government to accept less. A justification for such leases must be submitted to the Director of Real Property and Facilities Management at DOE Headquarters. The limitations of this section apparently do not apply to land leases granted under authority of the Atomic Energy Act.

B.4 Pending Legislation

DOE's current statutory authority to enter into long-term leases of government land could be expanded by new legislation. A bill that was considered by Congress during 1991 and will likely be reconsidered in 1992 would authorize DOE to enter into leases of government land at DOE facilities in order to facilitate the construction of privately owned facilities that would provide waste cleanup- and modernization-related products or services to the Department under long-term contract. The term of such leases would be for the lesser of the expected useful life of the contractor's facilities or the period of the contract.

B.5 SUMMARY AND CONCLUSIONS

The Atomic Energy Act of 1954 gives the Department the authority to enter into long-term leases of land. Based on past use of this authority at Hanford, such leases can be for periods that will be quite sufficient for the steam contract. Because the ability to enter into a long-term lease of Hanford land is essential to the success of the steam plant project, DOE's leasing authority should be clarified as soon as possible. This is particularly true because of the differences in the length of leases allowed by the three authorities discussed above.

APPENDIX C

PERMIT REQUIREMENTS

APPENDIX C

PERMIT REQUIREMENTS

This appendix reviews the permits that may be required for the steam plant construction project and discusses any differences resulting from federal versus private ownership. The likely permit requirements were summarized in Table 4.1. Obtaining required permits is the responsibility of the owner of the facility, i.e., the U.S. Department of Energy (DOE) if the plant is federally owned and the successful bidder is under the privatization option. There are currently no environmental permits covering the existing steam plant operations.

C.1 EMISSION PERMITS

The new steam plant will likely need to be registered with the Benton-Franklin-Walla Walla Air Pollution Control Authority and have a notice of construction approved by the Authority before construction begins. The approval will be needed because the plant is a facility to which a federal standard of performance applies and because it is a major source emitting 100 tons per year (tpy) or more of a regulated pollutant.^(a) Such registration and approval will be needed whether the new steam plant is considered a new source of emissions or a modification to an existing source.^(b)

The federal standard of performance for steam-generating units appears at 40 CFR 60, Subpart (D)(b). It applies to all new, modified, or reconstructed steam-generating units with a heat input capacity greater than 29 MW (100 million Btu/hr) constructed after June 1986.^(c) All of the plant options under consideration would exceed this designated heat input capacity. The federal performance standard includes emission limits for particulates, nitrogen oxides, and sulfur dioxide; compliance and performance test methods; monitoring requirements; and reporting and record-keeping requirements.

The emission permit (i.e., approval of the notice of construction) issued by the Authority will require 1) compliance with the federal performance standard, 2) the application of best available control technology for emissions control, 3) a showing that allowable emissions will not delay the attainment date for an area not in attainment, and 4) a showing that the source will not cause a violation of any ambient air quality standard.^(d)

-
- (a) General Regulation 80-7 of the Benton-Franklin-Walla Walla Counties Air Pollution Control Authority, sections 400-100 and 400-110. WAC 173-400-100(28),(30); 173-400-110; and 173-403-030(30).
 - (b) WAC 173-403-030(29), (34).
 - (c) 52 Federal Register 47826, December 16, 1987.
 - (d) WAC 173-403-050(4).

The Washington State Department of Ecology (Ecology) has public involvement requirements applicable to the new source review process for sources with a "significant" net emission increase for a regulated pollutant.^(a) The definition of "significant" includes a NO_x emission rate of 40 tpy or more.^(b)

An emission permit will be required regardless of whether the plant is federally or privately owned. Federal facilities are subject to all federal, state, and local air pollution control requirements.^(c)

C.2 PREVENTION OF SIGNIFICANT DETERIORATION [PSD] PERMIT

The prevention of significant deterioration (PSD) permit program applies in geographic areas meeting ambient air standards or areas that cannot be classified. The PSD program is designed to prevent deterioration of air quality in these areas.

South Central Washington Intrastate Air Quality Control Region 230, which includes the Hanford Site, has ambient air quality that is either better than national standards or cannot be classified for particulates, SO₂, ozone, CO, and NO₂.^(d) Under the PSD program, major new stationary emission sources and major modifications to existing sources must obtain a PSD permit.^(e)

The term "major stationary source" is defined to include fossil fuel boilers (or combinations thereof) totaling more than 250 million Btu/hr input with the potential to emit 100 tpy or more of any pollutant subject to regulation under the Clean Air Act.^(f) The term also includes 1) any stationary source with the potential to emit 250 tpy or more of any pollutant subject to regulation under the Act and 2) any physical change at a stationary source not otherwise qualifying as a "major stationary source" if the change would constitute a major stationary source by itself.^(g) A "major modification" is defined to be any change in the method of operating a major stationary source that would result in a significant net emissions increase of any pollutant subject to regulation under the Clean Air Act.^(h) Emission rates which equal or exceed the following are "significant": CO (100 tpy), NO_x (40 tpy), SO₂ (40 tpy), and particulates (25 tpy).⁽ⁱ⁾

An existing PSD permit (No. PSD-X80-14) was issued by the U.S. Environmental Protection Agency (EPA) Region 10 Office to DOE in 1980. The permit covers NO_x emissions from the plutonium uranium extraction (PUREX) facility in the

-
- (a) WAC 173-403-110(1)(a).
 - (b) WAC 173-403-030(47).
 - (c) 42 U.S.C. 7418(a).
 - (d) 40 CFR 81.348.
 - (e) 42 U.S.C. 7475, 40 CFR 51.166(i).
 - (f) 40 CFR 51.166(b)(1)(i)(a).
 - (g) 40 CFR 51.166(b)(1)(i)(b,c).
 - (h) 40 CFR 51.166(b)(2)(i).
 - (i) 40 CFR 51.166(b)(23).

200-East Area and the UO_3 plant in the 200-West Area. The existing steam plant operations in the 200 Areas are not included within the scope of the permit.

The definition of the term "stationary source" is relevant to determining whether the L-017 project or the alternative plants under consideration will require a new PSD permit or modification of the existing permit. This term is defined as any "building, structure, facility, or installation" which emits or may emit an air pollutant subject to regulation under the Clean Air Act.^(a) The term "building, structure, facility, or installation" is defined as all pollutant-emitting activities which 1) belong to the same major group (have the same two-digit code) in the OMB's *Standard Industrial Classification Manual*, 2) are located on one or more contiguous or adjacent properties, and 3) are under the control of the same person.^(b) A steam plant and a cogeneration plant would both be in major group 49. It is not clear what major group other 200-Area activities are in,^(c) but it is not likely to be group 49.

Taken together, the definitions suggest that 1) the existing steam generation facilities in the 200 Area will be considered as the same stationary source as replacement or supplemental federally-owned steam/cogeneration facilities, 2) a privately-owned steam/cogeneration plant will be a new stationary source because it would not be under DOE control, and 3) other 200-Area activities are separate stationary sources for PSD purposes.

All of the new plants under consideration will likely have the potential to emit more than 100 tpy of a pollutant regulated under the Clean Air Act. Assuming an average annual steam demand of 1100 million pounds (lbs), 1038 Btu/lb steam, 85% boiler efficiency, and the estimated emission rates for the L-017 project,^(d) the emissions for a coal-fired plant will be roughly 335 tpy of NO_x ,^(e) 140 tpy of CO , 87 tpy of SO_2 , and 20 tpy of particulates. The NO_x emissions for a natural-gas-fired plant under similar assumptions will be roughly 124 tpy because allowable NO_x emission rates are less for gas-fired, steam-generating units than for coal-fired units.^(f)

Applying the preceding discussion of PSD requirements to the plant options under consideration suggests the following conclusions:

-
- (a) 40 CFR 51.166(b)(5).
 - (b) 40 CFR 51.166(b)(6).
 - (c) Possible groups are: 96 - Administration of Economic Programs, 97 - National Security and International Affairs, and 99 - Nonclassifiable Establishments.
 - (d) E. M. Koellermeier. April 1990. *Conceptual Design Report Steam System Rehabilitation, Phase II*. Prepared by Kaiser Engineers Hanford Company for Westinghouse Hanford Company, Richland, Washington, p. 31.
 - (e) This level of emissions would subject the plant to PSD review even if the total boiler capacity was kept less than 250 million Btu/hr [40 CFR 52.21(b)(1)(i)(b)].
 - (f) 40 CFR 60.44b(a).

- All of the privately-owned plant options under consideration will require acquisition of a PSD permit because each option would constitute a major stationary source (greater than 250 million Btu/hr heat input with the potential to emit 100 tpy or more of a regulated pollutant).
- The key to determining the need for a PSD permit for a federally-owned steam plant addition or cogeneration facility is whether such an addition results in a net "significant" emission increase, and hence, constitutes a "major modification." To avoid being a major modification, sufficient existing boilers in the 284-West Area must be permanently closed concurrently with construction of the new facilities so that net emissions are kept below the levels constituting significant emissions. The L-017 project description^(a) indicates that the 284-West boilers are to be closed at a later date, in which case the L-017 project would likely create a major modification requiring a PSD permit.

A PSD permit for the Hanford Site would be issued by Ecology or the EPA Region 10 Office and would be based on EPA regulations at 40 CFR 52.21 and 51.166. For the most part, the regulations at 40 CFR 52.21 have been incorporated by reference into the Washington Administrative Code (WAC 173-403-080).

The regulations have numerous requirements. A permit applicant must demonstrate under Section 165 of the Clean Air Act that the new source will not cause or contribute to a violation of national ambient air quality standards or of allowable increments of air quality degradation. To make this demonstration, the applicant must generally have or conduct one year of preapplication air quality monitoring and conduct a modeling analysis of impacts on ambient air quality.^(b) Although NO₂ concentration is monitored at Hanford,^(c) SO₂ and CO are not.^(d) PSD permit applicants must provide an analysis of the estimated impairment to visibility, soils, and vegetation resulting from the new source.^(e) PSD permits will require application of best available control technology (BACT) to all regulated pollutants which the source has the potential to emit in "significant" amounts.^(f) BACT is defined as the maximum degree of emission reduction that the regulatory agency determines is achievable after taking into account energy, environmental, and economic impacts and other costs.^(g)

(a) Koellermeier 1990, p. 2.

(b) 40 CFR 51.166(m)(1) and 51.166(l).

(c) R. E. Jaquish and R. W. Bryce, eds. 1990. *Hanford Site Environmental Report for Calendar Year 1989*. PNL-7346, Pacific Northwest Laboratory, Richland, Washington, p. 4.3.

(d) Jaquish and Bryce (1990), p. G.4, include estimates of total emissions (kgs) of particulates, SO₂, and CO.

(e) 40 CFR 51.166(o).

(f) 40 CFR 52.166(j)(2).

(g) 40 CFR 51.166(b)(12).

Ecology is to provide an opportunity for a public hearing on a PSD permit request.^(a) A final determination is made within one year of receipt of a complete permit application.^(b) Once issued, a PSD permit becomes invalid if construction does not commence within 18 months, if construction is discontinued for 18 months or more, or if construction is not completed within a reasonable time.^(c)

C.3 AIR EMISSION OPERATING PERMIT

The 1990 amendments to the Clean Air Act added Sections 502-505 which provide for an operating permit system for all large and many small sources of air pollution. Major sources emitting more than 100 tpy of a regulated pollutant and facilities subject to new source performance standards will be required to obtain a permit. The new steam plant will be within this coverage requirement, although the question of whether the plant will need its own permit or if it can be joined with other 200 Area facilities probably cannot be answered until specific regulatory requirements are issued. Operating permits are to be issued for 5-year terms and will include emission limits; a compliance schedule; and related activities such as monitoring, record keeping, and reporting requirements.

EPA is to have established minimum requirements for state permit programs by November 15, 1991. States are to submit an operating permit program to EPA for approval by November 1993. EPA has one year to approve or disapprove a plan. Owners of individual facilities must submit permit applications within one year after approval of a state program. Although it is too early to know how the operating permit program might affect the steam plant project, one possible impact might be the need for additional emission controls on the existing 284-East boilers.

C.4 SOLID WASTE DISPOSAL

If the steam plant is fired by coal, solid wastes from fly ash, scrubber by-products, and boiler bottom ash will be generated. Plans call for temporary storage at the plant location with later burial on the Hanford Site.^(d) The ash is currently buried at a designated site near the steam plant.^(e)

Fly ash, bottom ash, slag, and flue gas emission control wastes generated primarily from the combustion of coal or other fossil fuels are not considered to be hazardous wastes under the Resource, Conservation, and Recovery Act

(a) 40 CFR 51.166(q). WAC 173-403-100(1)(b).

(b) 40 CFR 51.166(q).

(c) 40 CFR 52.21(r)(2).

(d) Koellermeier 1990, p. 32.

(e) Jaquish and Bryce, 1990, p. 4.49.

(RCRA),^(a) and therefore are not subject to the permit requirements under RCRA at 40 CFR Part 270 for treatment, storage, and disposal facilities.

Such wastes are not, however, excluded under the Washington Hazardous Waste Management Act.^(b) Consequently, the solid wastes generated by steam plant operations need to be tested under Ecology's Dangerous Waste Regulations (WAC 173-303) to determine if they are dangerous wastes, extremely dangerous wastes, or special wastes. If the wastes fall into one of these categories, the requirements covering generation, transportation, and disposal must be met. Owners of facilities which transfer, treat, store, dispose (TSD) or recycle dangerous wastes need a permit from Ecology.^(c)

If the solid waste products from the steam plant are found not to be wastes subject to regulation under the Washington Hazardous Waste Management Act, they are to be disposed of in accordance with Ecology's Minimum Functional Standards for Solid Waste Handling at WAC 173-304. A permit for a solid waste disposal facility is needed from the local health department.^(d) Permit applications are reviewed by Ecology.^(e)

As Table 4.1 indicated, no solid waste disposal facility permit will be needed specifically for the steam plant. However, this notation is made with the understanding that the solid waste disposal facility selected for future ash disposal will meet the requirements of Ecology and the Benton-Franklin Health Department. The existing central solid waste landfill at Hanford does not have a permit from the Health Department.

All solid waste, hazardous waste, and dangerous waste requirements will apply regardless of whether the steam plant is federally or privately owned. Federal facilities are to comply with state and local solid waste requirements.^(f)

C.5 NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT

The proposed facility will generate liquid wastes from blowdown, water softener regeneration, and cooling.^(g) The discharges are planned to be collected for direct discharge to the Columbia River after treatment, or treatment and discharge by other means, by a project addressing the entire 200-Area waste discharge system. This system may be available to the private plant depending on availability of handling systems.

-
- (a) 40 CFR 261.4(b)(4).
 - (b) WAC 173-303-071.
 - (c) WAC 173-303-800.
 - (d) RCW 70.95.170. WAC 173-304-600.
 - (e) RCW 70.95.185.
 - (f) 42 U.S.C. 6961.
 - (g) Koellermeier 1990, p. 33.

Discharges to surface water bodies require a national pollution discharge elimination system (NPDES) permit under the Clean Water Act. Under the Clean Water Act, federal facilities are subject to the same water pollution control requirements as privately-owned facilities.^(a) The Hanford Site has an existing NPDES permit issued by the EPA Region 10 Office.^(b) Since the discharge of liquid wastes from the new steam plant are to be handled in conjunction with the broader 200 Area waste treatment plans, an NPDES permit will not be needed for the steam plant project (refer to Table 4.1).

Different permit requirements would be applicable if it is determined at some point to discharge the liquid wastes from steam plant operations to a drain field or an artificial water body on the Hanford Site instead of to the Columbia River via the 200-Area waste treatment system. An operator of a privately-owned steam plant would likely need a permit from Ecology under the Washington State Waste Discharge Program.^(c) If the steam plant is federally owned, the need for a waste discharge permit would depend on whether federal supremacy and sovereign immunity have been waived for this type of discharge under the Clean Water Act and, if not, whether compliance as a matter of policy or comity would be undertaken. In addition, it would also need to be determined if the liquid wastes are hazardous materials regulated under RCRA or dangerous wastes regulated under the Washington Hazardous Waste Management Act. If the answer is found to be "yes" for either Act, the requirements described in Section C.4 would need to be met whether the plant is federally or privately owned.

C.6 WATER ACQUISITION

Water for the proposed steam plant will be acquired from the existing raw water reservoir in the 200 Area.^(d) DOE has asserted a federally reserved water right for Hanford's atomic-energy-related activities. Accordingly, DOE does not have a permit from Ecology for the appropriation of Columbia River water for operations in the 200 Area.

If the new steam plant is federally owned, its water needs would seem to clearly fall within the reserved water right. Water for a federally-owned cogeneration facility would also seem to be within the reserved water right, with the possible exception of a plant with electricity output that exceeds DOE's electricity demand for Hanford activities. No such plants are considered in this document.

Water under DOE's reserved water right may be able to be supplied by DOE to the operator of a privately-owned steam or cogeneration plant. Such water supply would not increase total water use for Hanford-related operations.

(a) 33 U.S.C. 1323.

(b) Jaquish and Bryce 1990, pp. 2.12, B.7.

(c) WAC 173.216.

(d) Koellermeier 1990, p. 21.

There is precedent allowing temporary transfer of reserved water rights on Indian reservations.^(a)

If needed, a water right for the steam/cogeneration plant can likely be obtained since there is no shortage of Columbia River water available for appropriation. Permits are obtained from Ecology by following the procedures in RCW 90.03.250-.340 and WAC 508-12.

C.7 MISCELLANEOUS PERMITS

A private firm constructing and operating the steam plant will likely be subject to certain permit requirements that would not apply to a federally-owned plant under the Supremacy Clause of the U.S. Constitution. Federal facilities are subject to state and local requirements only when the federal government's sovereign immunity has been waived. Sovereign immunity has been waived in certain statutes, e.g., the Clean Air Act, the Clean Water Act, and RCRA, but has not been waived in other potentially applicable areas. Examples of permits and licenses that could apply to a privately-owned plant but that probably would not apply to a federally-owned plant include 1) a business license, 2) building and occupancy permits, 3) septic tank permit, and 4) transportation-related permits for public roads (e.g., for oversized loads).

C.8 COMPARISON OF OWNERSHIP AND FUEL OPTIONS

As suggested by Table 4.1, the option with the simplest permit requirements is a federally-owned, natural-gas-fired plant. This option avoids the need for 1) permit(s) related to disposal of solid waste products and 2) the miscellaneous permits. The need for a PSD permit can also be avoided if net emissions are kept below the "significant" level. Privately-owned, coal-fired plants have the greatest potential permit requirements. The other ownership and fuel options would present other possible permit requirements as shown in Table 4.1.

The time and cost to obtain permits is very difficult to estimate. Many factors can influence the process including 1) the diligence and aggressiveness of the permit applicant; 2) whether baseline environmental data already exist in a satisfactory format; 3) the workload of the issuing agency; 4) whether the requested permits affect other existing Hanford permits, permit requests, or permit-related negotiations between DOE and Ecology; and 5) the extent of public interest and/or opposition (if any) to the permit requests. One article states that obtaining air quality permits can take 12-24 months if

(a) A. D. Tarlock, 1990. *Law of Water Rights and Resources*, Clark Boardman Co., New York, Section 9.07[4].

pre-application monitoring data must be collected.^(a) An ownership/fuel structure that requires more permits than the federal ownership/natural gas option will not necessarily have a longer permit acquisition process because permits can be pursued concurrently.

(a) Hanson, B. R., and S. Bush. 1987. "Precious Metals Mine and Processing: Facility Permitting." Natural Resources and Environment, 2(3):45.

APPENDIX D

FUEL PRICE AND AVAILABILITY

APPENDIX D

FUEL PRICE AND AVAILABILITY

D.1 NATURAL GAS PRICES

A review of a number of "end-user" assessments of gas price and escalation is summarized in the table below. These are generic burnertip prices which include acquisition, interstate transmission, and local distribution costs, without any significant facility expansion. The references cited for these assessments are contained in Section D.5 of this appendix.

TABLE D.1. Natural Gas Price Expectations

	Price/MMBTU (in 1990\$)			Escalation (%)		
	Firm	Int ^(a)	Composite	Firm	Int ^(a)	Composite
NPPC (1990)	4.30	2.90	3.40	1.4	2.5	2.1
BPA (1989)	--	--	2.70	--	--	2.3
PP&L (1989)	3.50	2.60	3.10	--	--	3.3
PGE (1990)	--	--	2.50	--	--	4.0
Cascade Natural Gas ^(b) (Retail, market-based)	--	--	2.40	--	--	0.0
GRI (1989a)						
Industry-PNW	--	--	2.90	--	--	4.0
Utilities-PNW	--	--	3.65	--	--	2.8
EPRI (1989)	--	--	2.60	--	--	4.0
EIA (1990)	--	--	3.32	--	--	3.7

(a) Denotes under interruptible transportation.

(b) No date available.

The range of \$2.50 to about \$3.65 per MMBTU appears to bound current burnertip prices. The first six sources have a Pacific Northwest (PNW) focus, while the latter two are highly aggregate, being at the national level. The average from all the former is \$2.95. A reasonable value for planning purposes would be represented by the approximate midpoint of the range: \$3.00 per MMBTU. Updating this price to 1991, using the gross national product (GNP) implicit

price deflator, results in a value of \$3.05/MMBTU. All but one forecast of escalation in gas prices show rates in excess of general inflation. Given the slight disparities across the non-zero forecasts for the PNW, a 3.0% real escalation would be reasonable for use in planning.

Given the increasingly competitive nature of the industrial gas market, a more aggressive gas acquisition and transportation strategy may produce lower gas cost in the near term than the averages derived above. It is very probable that such a strategy would have to incorporate a substantially higher escalation rate for planning. This is demonstrated, for example, in the Gas Research Institute (GRI) forecast for real escalation for industrial gas use in the PNW, shown in the table above as "Ind-PNW," where a low price is coupled to a high escalation rate.

For usual planning purposes, the above cost would be sufficient for determining fuel cost for a gas-fired project. However, the remote site location for the steam facilities at Hanford presents a special problem of connecting to a high pressure/high volume gas delivery system, a problem not typically encountered at other host sites.

Because of the distances involved and the possible security considerations, recognition of additional costs for gas delivery is essential. Two basic options seem feasible at this stage: connecting with the local distribution company or connecting directly with an interstate pipeline.

Connecting with the local distribution company (LDC), Cascade Natural Gas (CNG), would require a high pressure line off the CNG's system in north Pasco and a river-crossing over the Columbia. Very rough indications are for a line of approximately 35 miles. The LDC indicates that with the large volume of gas potentially involved, it could justify the investment in such a pipeline. LDC would design, install, own, and maintain the line up to the 200 Area, if the appropriate utility easements and permits could be obtained. Instead of the traditional upfront payment ("contribution in aid of construction") by the owner of the plant, CNG claims it could serve the load under a take-or-pay arrangement. Under normal deliveries, the cost is estimated by Cascade to be "nominal," in the neighborhood of \$.20-\$.25/MMBTU. In the event of declined delivery, CNG indicated that a payment tied to CNG's margin would be needed. This margin-based recovery would be on the order of \$1.00/MMBTU for contract volumes.

The second option would involve bypassing the LDC's system and connecting directly with an interstate pipeline. Two possibilities present themselves here.

Pacific Gas Transmission (PGT) has large, interstate facilities passing through the mid-Columbia region to serve LDC loads and to ultimately serve its California direct and wholesale customers. PGT indicates that an investment of 30-35 miles of line (probably 12-inch) would just be feasible for a large load such as a cogeneration facility. A Columbia River crossing would also be necessary here. PGT would design, install, own, and maintain the line and recover its investment and costs via a tariffed service approved by the

Federal Energy Regulatory Commission (FERC), at an incremental rate of approximately \$.20 per MMBTU. This is based on recent, comparable experience from other transportation activities.

Another option of this variety surfaces off the Northwest Pipeline (NWP) system from the Sunnyside/Grandview area, and NWP would be interested in transporting directly a high-volume load such as this. Two routes are possible. One goes directly north, paralleling State Highways 241 and 24, converging at Highway 240 and the Yakima Barricade. The route would then proceed due east on Road 24 and then south to the 200 Area. This route represents a distance of about 35 miles and is probably the easiest route on the Hanford Site for purposes of gaining utility easements. Like PGT, NWP would seek to recover its costs through a FERC-approved rate, but would try to price the service on a rolled-in basis in the range of \$.10-.20 per MMBTU. There is some question, however, about NWP's ability to provide this type of tariffed service. The other possible route with the NWP pipeline could conceivably be east to Benton City and north to the 200 Area, a distance of about 45 miles. While this route is longer, the greater market potential to the Tri-Cities area could influence the transporter in favor of this option.

Regardless of which company transports gas to the 200 Area, \$.20/MMBTU would seem to reflect a reasonable adder to be combined with the generic planning numbers above, at 0.0% real escalation. This applies if the project developer does not need to be involved in pipeline ownership. Thus, the total gas cost per MMBTU would be \$3.25 and the adder would have only a very slight impact on the expected real escalation rate; so, it is reasonable to retain a 3.0% rate.

In the event that the project developer would have to incur the capital expenditures for pipeline installation and ownership, the sizing and cost data shown in Table D.2 can be applied for planning purposes.

These data are a composite of inputs from the Northwest Natural Gas least cost utility plan (LCUP) filing in Oregon, from the Engineering Services Group at Cascade Natural Gas, and from PGT. Fixed operating and maintenance (O&M) costs are negligible: one percent of the annual capacity cost is a rule of thumb.

Total installed costs of the two most probable pipeline lengths from the above specifications are shown in Table D.3.

The shorter-distance installation represents traversing the Hanford Site (east or west, roughly), and, therefore, the \$.20 adder to connect with a delivery system must still be recognized. The 35-mile pipeline would represent direct connection with either interstate pipeline company.

TABLE D.2. Pipeline Sizing and Cost Data

<u>Pipe Size</u>	<u>MCF/Day Capacity</u>	<u>\$/ft (1990\$)</u>
20-in.	60 - 108,000	88
16-in.	30 - 60,000	67
12-in.	19 - 30,000	52
10-in.	11 - 19,000	44
8-in.	up to 11,000	36

TABLE D.3. Installed Cost (\$K)

<u>Pipe Size</u>	<u>10 miles</u>	<u>35 miles</u>
20-in.	\$4,700	\$16,350
16-in.	3,500	12,350
12-in.	2,700	9,500
10-in.	2,200	7,600
8-in.	1,900	6,500

D.2 INTERSTATE PIPELINE CAPACITY

All existing, firm interstate capacity is taken. Both PGT and NWP have substantial capacity expansion plans at various stages of development. PGT has a submission before the FERC for significant expansion of its system to transport gas from Western Canada to its California market. About 20% of the expansion is targeted for PNW-delivery capability, but this is fully subscribed (Cascade Natural Gas is one of the subscribers). PGI expects certification from the California Public Utilities Commission (CPUC) in January 1991 and from the FERC by the end of the first quarter of 1991.

NWP indicates a general willingness to expand capacity for long-term, firm arrangements. In fact, at the end of December 1990, NWP filed an application for expansion; approval and construction are expected to be completed by the end of 1992. NWP indicated the necessity of a cogenerator having firm gas transportation as part of the planning process, rather than assuming that it can be available spontaneously.

D.3 COAL PRICES

A survey of coal prices and expected real escalation is summarized in Table D.4. Again, the Energy Information Administration (EIA) numbers are aggregates; so, the first six assessments offer a more regional focus. However, within the region, the PP&L and PGE entries reflect a coal variety with lower heat content, and BPA's assumption is an extraordinarily generic one. The average of the three remaining estimates for the PNW is \$2.18/MMBTU and an average, expected escalation rate of 0.9% over the 20-year horizon.

Updating the price to 1991 and using the GNP implicit price deflator, a coal price of \$2.25/MMBTU and a real escalation rate of 1.0% are reasonable assumptions for planning purposes. If the government owns and operates the steam plant/ cogeneration facility, the coal procurement restriction suggests that \$2.55/ MMBTU be used as a base, after updating to 1991 dollars, and a 1.0% real escalation rate be adopted under the assumption that the qualified suppliers exhibit nearly the same cost and productivity trends as the industry in general.

TABLE D.4. Expected Coal Prices

	<u>Price in MMBTU</u> <u>(in 1990\$)</u>	<u>Escalation (%)</u>
NPPC (1990)	2.40	0.8
BPA (1989)	1.65	1.3
PP&L (1989)	1.25	~1
PGE (1990)	1.55	1.2
GRI (1989b)	2.05	1.4
EPRI (1989) Low Sulphur Central Rockies to Pacific NW	2.10	0.5
EIA (1990)	1.28	0.8
DOE-RL	2.45	annual spot adjustment

D.4 COAL AVAILABILITY

Unlike natural gas supply, no special, new facilities appear to be required for increased volumes of coal transport and handling. Additional railroad crews may be necessary to move increased volumes.

D.5 REFERENCES

Bonneville Power Administration (BPA). December 1989. Draft 1990 Resource Program, BPA, Portland, Oregon.

Cascade Natural Gas. (No date available.) Industrial Marketing Department, Seattle, Washington.

Electric Power Research Institute (EPRI). September 1989. TAG, Technical Assessment Guide, Vol. I. EPRI P-6587-L, EPRI, Palo Alto, California.

Energy Information Administration (EIA). 1990. 1990 Annual Energy Outlook, Long-Term Projections. DOE/EIA-0383(90), U.S. Department of Energy, Energy Information Administration, Washington, D.C.

Gas Research Institute (GRI). 1989a. Baseline Projection Data Book, 1989 GRI Baseline of U.S. Energy Supply and Demand to 2010 GRI, Washington, D.C.

Gas Research Institute (GRI). 1989b. 1989 GRI Baseline Projection of U.S. Energy Supply and Demand to 2010 GRI Research Insights, Chicago, Illinois.

Northwest Power Planning Council (NPPC). February 1990. "New Resources: Supply Curves and Environmental Effects." Staff Issue Paper, No. 90-4, Portland, Oregon.

Pacific Power & Light (PP&L). November 1989. Planning for Stable Growth, Resource and Market Planning Program before the Oregon Public Utility Commission, Docket No. LC-1.

Portland General Electric (PGE). December 1990. The 1990 Integrated Resource Plan, A Least Cost Approach Appendix 3, pursuant to Oregon Public Utility Commission Order 89-507.

APPENDIX E

MARKET AND PRICES FOR ELECTRIC POWER

APPENDIX E

MARKET AND PRICES FOR ELECTRIC POWER

The price that a prospective cogenerator can negotiate for sale of electricity is by far the most important variable in determining the viability of any cogeneration proposal. Unfortunately, it is impossible to predict price levels in advance of direct utility negotiations. The major reason is that most independent power producers sell to utilities through formal competitive procurements initiated by individual utilities. The best that can be done is to characterize likely ranges of prices on a regional basis based upon 1) federal vs. private ownership considerations, and 2) informal discussions with utility managers in those regions.

The following section discusses the type of market opportunities likely to be available under federal and private ownership. The ability of a prospective site cogenerator to wheel power over BPA and other transmission lines is also discussed, but again, it is impossible to guarantee capacity availability or wheeling cost in advance of actual negotiations.

E.1 POWER SALES UNDER FEDERAL COGENERATION SCENARIOS

The long-term power sales agreement between BPA and DOE-RL governs the disposition of all electrical power provided on the Hanford Site. This agreement expires on June 30, 2001. There may be a BPA initiative to renegotiate Hanford rates and conditions before expiration, since BPA has started to renegotiate other long-term power sales agreements.

Under Section 5 of the power sales agreement, DOE-RL must use its "best efforts" to either 1) serve its own load with firm resources, or 2) make the resources available for acquisition by BPA. Firm resources include firm power purchased on contract from a third party, as well as self-generation both on an independent or jointly-owned basis. As part of this agreement, DOE-RL must submit an annual forecast of electricity requirements and resource availability.

Under the first option, the onsite generation is used simply to replace power that would have been purchased from BPA. The "price paid" for this power is simply the price that BPA charges the site for power under the effective PF-Rate. The energy component of the PF-Rate is seasonally differentiated (18.7 mill/kWh winter and 14.7 mill/kWh summer) and \$3.60/kW/month of billing demand for capacity. For 1991, the melded rate for the Hanford Site was 22.7 mill/kWh. BPA's "official forecast" of the PF-Rate over the next 20 years reflects no real escalation.

Under the latter option, where the resource is made available for acquisition by BPA, the sale will take place under a "mutually agreeable contract at

appropriate compensation." Hence, there is substantial uncertainty as to what the appropriate price would be. BPA's resource acquisition strategy is complex and is still being developed. The process is complicated by the Northwest Power Planning and Conservation Act of 1980, as BPA has not yet acquired resources under the Act. BPA is currently initiating several acquisition programs to prepare for an expected energy deficit forecast for 1992-1993.

To initiate its resource acquisition program, BPA is formulating a solicited, competitive bidding program, which may be an option for a Hanford cogeneration bidder. Other mechanisms include a Billing Credit Solicitation, for which the initial round of bid submissions was received in mid-October 1990. This resource acquisition mechanism provides a glimpse of the type of BPA "market opportunities" that are likely to be available. Under the provisions of the Northwest Power Planning and Conservation Act, BPA may only acquire such resources as demand-side measures, customer system efficiency improvements, or generation (conventional or renewable), if the resource does not cost BPA (in the form of a credit on a customer's bill) more than an alternative resource. There is no one single alternative resource, and there are slight adjustments to account for different characteristics of generation units.

According to this Billing Credit Solicitation, BPA's ceiling is 36.2 mill/kWh for a resource coming on-line in 1992, and 35.8 mill/kWh for a resource coming on-line in 1996. BPA expects that these rates will not escalate above the general inflation rate. The rates include capacity payment, which is not of substantial worth in a hydro-dominated system, at the equivalent of about 1 mill/kWh. These values are ceilings for a cogeneration resource, so credits will probably be somewhat less.

BPA's other resource acquisition program was initiated in the spring of 1991 with an RFP for 300 MW of generation and conservation resources, up from 100 MW initially. The alternative resource construct is prominent in this solicitation, as are credits/debts for resource characteristics not tied to strict performance and availability features such as location and environmental externalities. With the array of different alternative resource types and credits/debts, a range of 28-38 mill/kWh appears to bound likely payments for a proposed thermal facility. This range should, for all intents and purposes, encompass less than full avoided cost payments because of competitive pressures emanating from the bid process.

It is clearly to Hanford's advantage to pursue the second option of sale to BPA rather than "turning back the meter" on BPA sales to the Site. Under this preferred approach, a price of 33 mill/kWh (1991 \$) rate with zero expected escalation is an appropriate value to use in evaluating the worth of an alternative resource for a plant coming on-line in 1999. This represents the mid-point of the range discussed above.

E.2 POWER SALES UNDER PRIVATIZATION COGENERATION SCENARIOS

Several power sales options are potentially available to a private cogenerator on the Hanford Site. These options are described below.

E.2.1 Pacific Northwest Sales

Investor-Owned Utilities (IOUs)

Should a private project developer satisfy requirements as a Qualifying Facility (QF) under the Public Utilities Regulatory Policies Act of 1978 (PURPA), it would be eligible, in principle, for full avoided cost payments from the mandatory purchase by utilities that are regulated by the Washington Utility and Transportation Commission. (See Appendix F for an explanation of PURPA.) These regulated utilities are the IOUs: Puget Sound Power and Light, Washington Water Power, and Pacific Power and Light. Non-investor-owned utilities are not regulated by the WUTC, nor are they compelled by law to acquire QF production. In general, this duality has resulted in attention being focused on IOUs. In addition, IOUs are typically the best market for a QF in terms of having higher avoided costs on which to base payments. Only about 50 MW of non-utility generation appears to have occurred in the early 1980s in Washington under this type of arrangement. This situation was largely the result of the energy surplus in the Pacific Northwest (PNW) during much of the 1980s.

With the near-term prospects of a regional supply deficit, resource acquisition activities are accelerating. However, the WUTC and the Federal Energy Regulatory Commission (FERC) are now fostering an even more competitive generation environment than represented by the policies in the early days of PURPA. The end result is that utilities are now encouraged to engage in competitive bid resource acquisition in the hope that non-utility resources can be brought on-line at less than the utility's avoided cost. The utility's avoided cost is the ceiling to acceptable bids (similar to the BPA approach described earlier). Puget has completed one such bidding process, a solicitation for 100 MW and is in the early stage of another for approximately 150-200 MW for acquisition in 1996. Puget's first solicitation resulted in bids for nearly 1,200 MW. Puget found the bids to fall into a range of 86% to 95% of its avoided cost. Washington Water Power is completing its first competitive acquisition process for 30 MW.

The following are likely results of the IOU competitive bid process, based on unofficial discussions with utility representatives. These prices are based on 95% of avoided cost expressed in 1991 dollars and are not expected to escalate above the general inflation rate.

- Puget Sound P&L 36 mill/kWh in 1999
- Wash. Water Power 35 mill/kWh in 1999
- Pacific P&L 28 mill/kWh in 1999.

Percent deviations from each system's avoided cost are likely to get smaller over time as the least expensive resource opportunities are exhausted.

PacifiCorp's electric utility unit, Pacific Power and Light (PP&L), released a competitive bid resource solicitation for 50 MW in October 1991. As shown, its avoided costs are considerably below those of the other IOUs in the region, and in fact, are at the lower end of the range likely from purchase by BPA. This is largely a result of PP&L's very diverse system (both in its hydro-thermal mix and geographically) as an outgrowth of its merger with Utah Power and Light in 1988 and its continued expansion outside the PNW. Combined with transmission elements, this potential purchaser of Hanford Site cogenerated power is inferior to even sales to BPA for near-term planning purposes, and is consequently dropped from further consideration.

Averaging Puget's and Washington Water Power's projected payments, and rounding off, produces 36 mill/kWh (1991 \$) for sales from the Hanford Site commencing in 1999. Coupled with this, no price escalation above general inflation is anticipated.

These acquisition prices are consistent with the expected payment levels in BPA's resource acquisition programs discussed above.

PNW Public Utilities

Another opportunity for Hanford power sales lies with the large number of PNW public utilities, which include municipal systems and public utility districts. Most of these are full-requirements customers of BPA, but some--and usually the larger systems--have their own generating capability and place only partial requirements on BPA.

For full-requirements utilities, system-avoided costs are proxied or reflected in the PF-Rate under which they take service from BPA. This is the same as the current 23-24 mill/kWh identified above. Even the larger, partial requirements public utilities use the PF-Rate as their avoided cost for resource planning purposes. Higher avoided cost and, hence, higher payments would seem to be possible if the utility attached substantial value to diversity of resources and to the flexibility of not having to depend totally on BPA to meet new load growth over the long-run. In general, however, sales to PNW public utilities would be negotiated at a price that falls somewhere in between BPA's PF-Rate and IOU's avoided costs.

PNW Power Brokers

Another potential regional market lies with the brokering or power marketing subsidiaries of some of the region's IOUs. Portland General Electric, Puget, and Idaho Power all have subsidiaries that act as intermediaries in marketing power. However, these transactions are typically short term (less than 5 years) and pose a payment value somewhere between BPA and IOU payments for competitive resource acquisition.

Because bids are evaluated on multiple criteria, a precise price estimate cannot be made. For instance, most of the region's immediate needs occur west of the Cascades. Because trans-mountain high voltage transmission capacity is constrained, a bid from an east side power source is unlikely to score as high as one from the west side.

Evaluation of these three alternative markets for privately-generated electricity indicates that the highest expected price is about 36 mill/kWh (for 1999 delivery to an IOU in 1991 \$) with a zero real escalation rate.

E.2.2 Sales Outside of the Pacific Northwest

A survey of publicly-owned electric systems in California provides a look at the purchase prices outside the region. A study for the California Energy Commission (CEC) in 1989 examined the avoided energy cost and capacity cost of fourteen major municipal and utility districts in the state. These systems included the Los Angeles Department of Water and Power; the Sacramento Metropolitan Utility District; and the cities of Anaheim, Burbank, Glendale, Palo Alto, Pasadena, Riverside, and Santa Clara, as well as several smaller systems. Most of those surveyed have been familiar participants in interregional sales with PNW utilities, and they likely represent the best power sales opportunities outside the PNW.

The average, melded avoided cost for this group is on the order of 55-60 mill/kWh, for 1991 delivery expressed in 1991 dollars. Capacity is valued substantially higher than in the PNW, with an approximate price of 10-20 mill/kWh at a 0.55 load factor. Expectations for long-run real escalation appear to be as high as 3.0%. Some Pacific Southwest (PSW) utilities, however, forecast 0% escalation over the long term.

In the increasingly competitive bulk power market, experiences in the PNW and elsewhere indicate that purchase prices are not likely to be as high as full avoided cost levels. Utilities regularly get bid responses that total 10-20 times their needed capacity. Avoided capacity costs are stable, but energy costs are more variable. Using a range of 85% to 95% of avoided cost as an expected result of the competitive process provides a likely price of 50-55 mill/kWh.

The CEC survey of publicly-owned systems in the PSW was also augmented with a more recent examination of avoided cost payments by San Diego Gas and Electric, and Pacific Gas and Electric (both large IOUs); and a marginal cost study by the Sacramento Municipal Utility District. The range for a long-term contract payment, commencing in 1999, is 39 to 58 mill/kWh (melded) with the simple weighted average at 46 mill/kWh. Real escalation was estimated to be 2.0% on average for these utilities.

For a generic purchase price from outside the region, 46 mill/kWh for a first-year payment beginning in 1999 and escalation at 2.0% in constant dollars appear reasonable for planning purposes.

E.3 WHEELING CAPACITY FOR HANFORD-GENERATED ELECTRICITY

Wheeling capacity for Hanford-generated electricity on the Hanford Site, within the Hanford region, and outside the region is explained in the following sections.

E.3.1 On the Hanford Site

With the high-voltage grid requirements associated with existing facilities at the Hanford Site and especially those from the Washington Public Power Supply System (WPPSS) nuclear program, sizing of the current system and interconnection with the BPA substation at Midway appears to require no significant transmission expansion. DOE-RL's 230-kV loop is rated at a MW capacity of 300 MW for north/south flows. Site non-coincident peak demand for the 100, 200, 300, and 400 Areas is on the order of 70 MW and, according to the most recent forecast from BPA, is expected to grow to about 100 MW by 2010 [without the Hanford Waste Vitrification Plant (HWVP), which is not contemplated as a baseload activity].

The loop will continue to have substantial excess capacity, nearly 200 MW for the 20-year forecast. BPA also owns a number of other high-voltage lines as part of the main and secondary grid of the FCRTS. There are 115-, 230- and 500-kV lines with interconnects at the Hanford and Ashe substations, but these apparently do not currently interconnect with the DOE-owned 230-kV grid.

Washington Water Power has a 115-kV line that interconnects with BPA facilities at Edna, east of the 200 Area.

E.3.2 Within the Region

Once energy arrives at the Midway station over the DOE-RL grid, it will be connected to the main grid of the FCRTS. Transmission capability from the east to the west side of the region (where the largest and fastest load growth is occurring) has received widespread concern from planners in the region. A popular misconception is that there are transmission bottlenecks or no extra, firm capacity for east-to-west flows. However, BPA's concern centers predominantly on First-Level Contingency events rather than on normal conditions in winter or otherwise.

Under normal conditions, even in the winter period of November through April, indications are that adequate firm capacity over which to move large blocks of energy is available. In a First-Level Contingency under extreme, abnormal winter conditions, there is a significant possibility of a trans-mountain high-voltage line going down, with a voltage collapse and ensuing blackout. Expansion of the system over the Cascades is one option under consideration and, if selected, would be expected to be completed in 1995-1996. This upgrade will most likely be undertaken solely by BPA.

Transmission service over the main and secondary grid of the FCRTS is tariffed by the FERC at the IR-91 rate. Currently, the rate is \$0.312/kW-month for demand and 0.91 mill/kWh. The melded rates at the following load factors are

illustrative of the total, kWh-equivalent cost: At a 100% load factor, it is 1.4 mill/kWh, and at 50%, it is 1.8 mill/kWh. The escalation rate above general inflation is expected to be modest: about 0.3%. (Losses on the FCRTS are estimated at 1.6% and are implicit in BPA's rates, inasmuch as losses have to be represented in contract demand quantities.)

For sales involving transmission on the FCRTS, 2 mill/kWh and a real escalation rate of 0.3% appear reasonable for planning purposes.

E.3.3 Outside the Region

The most likely access to the PSW market is via the Pacific Intertie. Access on PacifiCorp's system to the Desert Southwest (DSW) and PSW connection appears far more restrictive on both price and, especially, on non-price terms.

Coupled with the service under FERC's IR-87 Schedule, service to get to the California-Oregon border (the "COB") is tariffed under BPA's IS-91 rate regulated by the FERC. Depending on the load factor, current cost would be in the 1.6-2.3 mill/kWh range. Real escalation is indicated to be modest at 0.3%.

The availability of capacity over the Intertie appears to be far less of a problem than the east-west capability of the FCRTS. This is primarily true for the federal portion (currently about 5,200 MW, not counting loop losses, of about 6,300 MW total). The two private PNW utilities (PGE and Pacific) tend to covet their portion for their own transactions, but PGE may present some limited opportunity for loads of the size expected for a cogeneration project.

The capacity outlook is made more sanguine with the proposed Third AC expansion of the Intertie (1,600 MW of 50/50 federal/non-federal participation). It is generally acknowledged, as well, that the region's adoption of a combustion turbine-based strategy to firm secondary hydro energy would free up even more capacity over the north-south portions of the Intertie. This surplus would most likely be mitigated by PSW transactions with British Columbia Hydro. The net result from these transactions is, nevertheless, subject to considerable speculation.

BPA's Long-Term Intertie Access Policy governs power transmission over the federal portion of the northern half of the Pacific Intertie. BPA will generally wheel for any public/private utility on any legitimate requests for transmission. However, the policy does require the utility to be a scheduling utility within automatic generation control areas. In instances where the selling system is of a non-utility or non-scheduling variety, BPA requires the buyer to arrange and negotiate delivery over the tie-line and main grid.

For sales involving transmission on the FCRTS and over the Pacific Intertie to the COB, a reasonable cost for planning purposes would be in the range of 4.1 to 4.5 mill/kWh in 1991 dollars and an associated real escalation rate of 0.3%.

APPENDIX F

PUBLIC UTILITIES REGULATORY POLICIES ACT OF 1978 (PURPA)

APPENDIX F

PUBLIC UTILITIES REGULATORY POLICIES ACT OF 1978 (PURPA)

The Public Utilities Regulatory Policies Act of 1978 (PURPA) was enacted by Congress to encourage the development of alternative sources of energy. Its approach was to impose conditions to promote non-utility generation, effectively reducing the monopoly power of regulated electrical utilities. This was achieved by requiring state commissions to develop compliance regulations for electric utility capacity acquisition:

1. Utilities must acquire capacity and energy offered by Qualifying Facilities (QFs) when offered.
2. QFs would receive a price equal to the purchasing utility's total avoided capacity and energy costs, and the utility might also be required to pay front-end loading of capacity payments.
3. The utility would provide for interconnection and wheeling, if necessary.
4. The utilities would provide backup or standby capacity for the QF at fair and reasonable rates.
5. The QF would be exempt from regulation as a public utility and from the provisions of the National Fuel Use Act.

Other incentives emerged from income tax laws, including the federal 10% investment tax credit and accelerated depreciation. Both of these incentives have since been eliminated with the passage of the Tax Reform Act of 1986.

In the early years after PURPA, possessing QF status was a key requirement for obtaining project financing. Serious financial backing required a power sales contract, and states were forcing private utilities to purchase the output of QF facilities. Independent, non-QF generators were essentially foreclosed from project development by virtue of this constraint, as well as lacking regulatory status as an independent power producer.

With the passage of PURPA, non-utility generators could qualify as a QF by being either a cogenerator or a small power producer. The PURPA treatment of small power producers and of cogenerators can be easily confused. Both are given below with the understanding that it is only the PURPA requirements on cogeneration which may be germane to this project.

F.1 QUALIFICATION FOR PURPA

To qualify as a QF, a cogenerator must meet the following standards:

1. The operating standard is that the balance of usable thermal energy to total energy (thermal plus electric) can go no lower than 5%.
2. Oil or gas topping-cycle technologies must meet the following efficiency test:
 - If useful thermal output is greater than 15%, the plant efficiency (as calculated using total electric power output plus one-half of thermal output) must be at least 42.5% on a calendar year basis.
 - If useful thermal output is between 5% and 15%, then the efficiency test pivots on 45%.
3. Regulated electric utilities must have less than 50% equity in the project.

To qualify for QF status as a small power producer, the following conditions must be satisfied:

1. Must have maximum power capacity of 80 MW per facility.
2. Must use biomass, wastes, or a renewable resource technology for at least 50% of the total energy input.
3. Regulated electric utilities must have less than 50% equity in the project.

F.2 CURRENT IMPACT OF PURPA

PURPA's impact has declined significantly over the past several years. Utilities can effectively avoid buying power directly from individual QFs by forcing them into an open bidding process in which they must compete with other QFs and non-QFs on a price (and other) basis. Utilities are encouraged by state commissions to take this approach as a way to attract low cost power. Hence, the advantages of qualifying for QF status have significantly deteriorated from a decade ago.

Recently, the FERC has proposed a clarification on the status of a QF in competitive resource bidding situations, which are becoming prevalent and are being encouraged by federal and state regulators. Despite the FERC's indefinite deferral of its proposed rulemaking in competitive bidding, there are two elements which could have potential relevance here:

- In any bidding program, a QF shall receive a higher preference than a non-QF bidder, all else equal.
- A winning QF bidder shall be exempt from the efficiency standard pertaining to cogeneration.

The FERC has streamlined regulations governing nontraditional power suppliers [independent power producers (IPPs)] under the Federal Power Act. These changes cover

- rate authorization via bidding or negotiation
- rate schedule filings without exhaustive cost support
- exemption from cost accounting requirements
- streamlined corporate and financial regulation
- adoption of accelerated certification procedures.

APPENDIX G

LIFE-CYCLE COST ANALYSIS

APPENDIX G

LIFE-CYCLE COST ANALYSIS

G.1 INTRODUCTION

The life-cycle cost (LCC) analysis is an integral part of the ADD analysis. It is intended to

- compare, on a parametric level, the economic performance of a broad range of technical and procedural options
- eliminate options that are clearly not economic
- identify the most viable options, prioritizing where possible
- identify areas of economic uncertainty that cloud the decision process and perform sensitivity analyses to aid in resolving those uncertainties.

The LCC conducted within an ADD is a screening tool that may be inadequate to support a final decision, since the uncertainty band may be too great to judge between options that are nearly equal in economic performance. If two or more options are found to be nearly equal and the decision cannot be made on non-economic grounds, then a more detailed comparative analysis should be conducted before a final implementation decision is made.

G.1.1 Goals for the Steam Plant Life-Cycle Cost Analysis

The overall objective of this LCC analysis is to identify the likely least-cost option(s) for providing steam for space heating and process use in the 200 Area. The general approach is to evaluate a reasonable representative of several proposed project configurations. The analysis is intended to answer the following key questions:

1. Is it more economical for DOE to rehabilitate the 200-East plant (hereafter referred to as L-017) or to construct a new central steam plant?
2. Is a government-build cogeneration plant economically feasible?
3. Do coal-fired or gas-fired plants make more economic sense given conditions onsite?
4. Does a privately-owned steam plant provide a lower cost of steam than government options?

5. Does a privately-owned cogeneration plant with sale of electricity off the Hanford Site appear to be economically feasible?
6. Given the alternatives, which are most promising and should be pursued further, and which can be eliminated at this time?

G.1.2 Nature of the Analysis

In developing the LCC, emphasis was placed upon determining relative economic performance through use of consistent parametric design and costing approaches and by employing identical unit cost assumptions for common elements of alternative configurations. Detailed engineering designs were not prepared, and no bottom-up cost estimates were prepared. The approach used was to estimate costs at an aggregated level by using simple cost-estimating relationships and scaling factors based on the overall size (e.g., lb/hr of steam and/or kWe) of the plant or major equipment elements. Similarly, performance was evaluated on an overall annual average basis. Diurnal and seasonal effects were not explicitly simulated.

Cost estimates prepared in this manner are typically described as "order of magnitude" and are expected to be accurate within plus 50% and minus 30% on an absolute basis (American Association of Cost Engineers 1990). However, the use of common cost and performance assumptions for common elements of a technology configuration reduces the level of uncertainty when viewed on a comparative basis. This allows conclusions to be developed about the relative merits of alternative technology configurations even when the absolute costs could differ by as much as 30-50%.

G.2 SYSTEM DESCRIPTIONS

Boiler and cogeneration technologies and individual units are described in the following sections.

G.2.1 Boiler Technologies

Fundamental steam generation (boiler) options are presented in Table G.1. Fire-tube boilers are most commonly applied for low capacity systems, generally lower than 25,000 lb of steam/hr. The individual boiler capacity required for the 200-Area steam plant is a little greater than 100,000 lb/hr. Therefore, a water-tube boiler is required.

Economizers are used to preheat boiler feedwater rather than exhaust combustion products once the exhaust is too cool to transfer additional heat effectively in the evaporator section. In most industrial applications, economizers are a cost-effective means of improving boiler plant efficiency and were assumed to be included.

Gas-fired combustion is a relatively simple process that requires no further specification for a preliminary feasibility study. As indicated in Table G.1, several combustion system options exist for a coal-fired boiler. Stoker

TABLE G.1. Steam Generation Options

- Water-tube or fire-tube
- With or without economizer
- Fuel type/combustion system
 - gas
 - coal
 - stoker
 - pulverized coal
 - atmospheric fluidized bed
 - bubbling
 - circulating
 - pressurized fluidized bed
 - bubbling
 - circulating

systems are generally applicable to smaller-sized boilers producing less than 100,000 lb/hr of steam. For systems greater than 100,000 lb/hr of steam, pulverized coal combustion is generally more cost-effective. Fluidized bed combustion systems are also generally cost-effective for steam production rates of 100,000 lb/hr or more, and are especially attractive for burning high-sulfur coal.

Pressurized fluidized bed combustion was eliminated from consideration because it is still in the demonstration phase of development. Atmospheric fluidized bed combustion was not considered because prospective coals are low in sulfur. At an individual unit capacity of about 100,000 lb/hr, the choice between stoker and pulverized coal technology is a toss-up. Stoker combustion and spray dryer flue gas desulfurization (FGD) technology was selected as the basis for coal-fired combustion to be consistent with the analysis already completed for upgrading the 200-East steam plant (Westinghouse Hanford 1990). The characteristics of the selected boiler technologies are summarized in Table G.2.

G.2.2 Cogeneration Technologies

Fundamental cogeneration options are presented in Table G.3. Many of these can be quickly eliminated.

Reciprocating engine systems are generally applicable at power levels of 1 MW or less and produce hot water or very low-pressure/temperature steam. This

TABLE G.2. Reference Boiler Technologies

- Gas-fired water-tube boiler with economizer
- Stoker(coal)-fired water-tube boiler with economizer and spray dryer FGD

TABLE G.3. Cogeneration Options

<u>Topping Cycles</u>	
<ul style="list-style-type: none"> • Steam Rankine Extraction Backpressure constant variable • Reciprocating Engines Steam Internal combustion Diesel Stirling • Fuel Cells 	<ul style="list-style-type: none"> • Brayton Open WHR^(a)/process steam WHR/steam Rankine WHR/Kalina WHR/Cheng Closed WHR/process steam WHR/steam Rankine WHR/Kalina • Kalina
<u>Bottoming Cycles</u>	
<ul style="list-style-type: none"> • Steam Rankine 	<ul style="list-style-type: none"> • Organic Rankine

(a) Waste heat recovery.

system size is too small and the steam pressure/temperature too low to be applicable for the 200-Area steam plant. In addition, Stirling engine systems are not mature technology.

Fuel cells have good load-following capabilities and can be constructed in modular units to meet any power requirement, but even the most advanced concept (phosphoric acid) is still in the demonstration phase. In addition, about half of the waste heat produced must be recovered in the form of hot water.

Bottoming cycles use lower temperature process waste heat sources to produce electricity. The general concept of a bottoming cycle is to produce electricity from waste heat recoverable from process operations when little if any demand for hot water or low-temperature steam exists. Neither of these two conditions exist in the 200 Area, so bottoming cycles are inappropriate technology.

In open (Brayton) cycle systems, the products of combustion flow directly through the turbine. This requires the use of relatively clean burning fuels, such as natural gas. Closed (Brayton) cycle systems have a recirculating working fluid that is externally heated in a separate heat exchanger. This allows the use of essentially any type of fuel, including coal. However, closed cycle systems are significantly more expensive and are currently only in the developmental phase.

The Kalina cycle offers interesting opportunities for increasing cogeneration system efficiencies, but is still in the developmental stage. Thus, it was eliminated from consideration as either a stand-alone option or an option to be used in conjunction with a Brayton cycle and WHR.

Through the process of elimination described above, the viable cogeneration options that remain are steam Rankine and open Brayton cycle (gas turbine) with waste heat recovery.

For a coal-fired system, the only reasonable option is steam Rankine. Coal combustion products are too dirty to run directly through an open Brayton cycle. Constant backpressure steam turbines are ideal for situations with steady process steam requirements, but they cannot be easily or efficiently operated at less than full-load conditions. Therefore, this type of steam turbine is not a good candidate for the 200 Area. Variable backpressure turbines do allow adjustment in the power/steam output ratio, but are not commonly available. Extraction condensing turbines, however, also allow variable power/steam ratios and are commonly employed. Thus, the coal-fired cogeneration system was based on an extraction condensing steam Rankine turbine.

A gas-fired cogeneration system could possibly use either steam Rankine or an open Brayton cycle with WHR. In general, a steam Rankine system would not be chosen because it is more expensive to install than any of the Brayton systems and offers no other advantages for a gas-firing situation. Generating low pressure process steam directly from the gas turbine exhaust gases requires the lowest investment of the WHR options, but is energetically inferior.

Two options for generating additional power from steam generated by the gas turbine exhaust gases are the Cheng and combined cycles. In the former, steam not used for process purposes is injected into a modified gas turbine. In most cases, the steam injection rate would be well in excess of steam injection normally employed to control NO_x emissions. In the combined-cycle, steam generated by the gas turbine exhaust gases is expanded through a Rankine steam turbine; process steam is extracted at the required pressure, while the balance is fully expanded and condensed. Either the Cheng cycle (also called steam-injected gas turbine or STIG) or combined (Brayton/Rankine) cycle technologies are viable options for a gas-fired cogeneration system. Combined-cycle technology was selected as the basis for evaluation because of its significant historical use and theoretical energy efficiency advantage.

Recommended reference cogeneration systems are identified in Table G.4.

TABLE G.4. Reference Cogeneration Technologies

- Coal-fired steam Rankine
- Gas-fired combined Brayton/steam Rankine cycle

G.2.3 Size and Number of Units

The number and capacity of individual units that make up the power plant have direct impact on system cost, performance, and reliability. A single unit offers the lowest initial plant cost, but would likely suffer from poor part-load efficiency and would not allow for planned or unplanned outage. Multiple parallel units offer better operating flexibility and reliability at increased cost. A fundamental ground rule of the LCC analysis was that a new power plant, whether cogeneration or steam generation, will have adequate steam production capacity to meet the peak space heating load in the 200 Area with one unit down. The peak space heating load during an extreme winter day requires 220,000 lb of steam/hr. Three half-sized units, each capable of producing 110,000 lb of steam/hr, were assumed. Design steam conditions are 225 psig and 456°F.

For the steam plants, each of the three units employs the same boiler technology, either gas-fired or coal-fired. Three identical units are not employed in a cogeneration plant, however. It would make little sense for a cogeneration train to be constructed for all three units. In a (steam) load-following mode, the third unit would be used too infrequently to justify the economic investment in cogeneration capacity. The third unit could be operated to produce electric power only. Without the efficiency advantages inherent with cogeneration, however, it is unlikely that a unit of this size could produce electric power at a competitive cost. Similar arguments can be made regarding the relative economic viability of having one or two cogeneration units with (correspondingly) two or one boiler units, but an a priori conclusion cannot be reached for these two scenarios. Therefore, both "primary" and "secondary" plant configurations were considered for each cogeneration technology. A primary cogeneration plant has two cogeneration units and one boiler unit, while the secondary cogeneration plant has one cogeneration unit and two boiler units.

The seven configuration options evaluated are outlined in Table G.5. Each of these (except upgrading the existing plant) was analyzed under both government and private ownership conditions, resulting in 13 base-case analyses.

TABLE G.5. Life-Cycle Cost Technology Options

Upgrade 200-East Steam Plant (1)
New Construction
Coal-Fired
Steam Plant (2)
Secondary Cogeneration Plant (3)
Primary Cogeneration Plant (4)
Gas-Fired
Steam Plant (5)
Secondary Cogeneration Plant (6)
Primary Cogeneration Plant (7)

G.3 ECONOMIC METHODOLOGY

The economic evaluation was conducted by calculating and comparing the levelized cost of providing steam to the 200 Area via the 13 technology and ownership combinations described above. Levelized cost analysis combines initial cost, annually recurring cost, and system performance characteristics into a single figure of merit (the levelized steam cost in \$/1000 lb) that is a commonly accepted metric for comparing the projected steam costs of alternative acquisition approaches. The specific economic methodology employed was that defined in Brown et al. (1987).

Economic inputs used to calculate the levelized steam cost are summarized in Table G.6 for both government and private ownership. There are some government costs for private ownership cases. These include preconstruction costs, construction, and maintenance of connecting facilities such as the water line, and maintenance of the Hanford rail system.

The baseline economic life was set at 30 years for both government and private ownership based on standards prescribed by the Electric Power Research Institute (EPRI) for facilities similar to the steam and cogeneration plants being considered and guidelines prescribed by law (EPRI 1989; Van Knapp et al. 1989). Due to potential contracting limitations, capital recovery for private investment was also evaluated for a 10-year period. The federal government does not pay any property taxes on Hanford facilities and is assumed to self-insure. The property tax rate for private ownership was established by consulting with the Benton County Assessor's Office. The private ownership insurance rate was established based on data from EPRI's Technical Assessment Guide (EPRI 1989).

Business and occupation (B&O) tax rates were established by consulting with the Washington State Department of Revenue. B&O taxes do not apply to either electricity or steam generated for self-consumption. Therefore, B&O taxes on steam would only apply for a privately-owned plant selling steam to the

TABLE G.6. Economic Assumptions

<u>Economic Factor</u>	<u>Government</u>	<u>Private</u>
Economic Life	30 years	30 years
Property Tax Rate	0%	1.5%
Insurance Rate	0%	0.5%
Business and Occupation Tax Rate	0%	1.5% of steam revenue; 3.852% of out-of-state electricity revenue
Income Tax Rate	0%	34%
Discount Rate	4.7% real	7% real, after tax
General Inflation	5%	5%
Depreciation Period	N/A	20 years
Price Year	1991	1991
Net Salvage Value	\$0	\$0

government. B&O taxes on electricity apply to sales for immediate consumption or sales outside the state of Washington. Sales within the state of Washington to public or private utilities for resale within the state of Washington are not subject to B&O taxes. Therefore, government sales of cogenerated power (to BPA) are not subject to the tax, nor are private sales to Washington utilities. Private sales to California utilities would be assessed B&O taxes, however.

The federal government does not pay income tax; the private income tax rate was presumed to be 34%, the top marginal rate for corporations (Van Knapp et al. 1989).

Establishing an appropriate discount rate is always a subjective, speculative matter for private ownership. Surprisingly, some speculation exists for government ownership as well. Historically, OMB's Circular A-94, Revised, prescribed a 10% real (i.e., after the effects of inflation are removed) discount rate for evaluating time-distributed costs and benefits for most federal economic analyses. Subsequently, OMB Circular A-104 established a nominal (i.e., the effects of inflation are included) discount rate equal to the current interest rate on new issue of U.S. Treasury securities with maturities most nearly equal to the term of the lease for federal economic analyses evaluating leases of capital assets. Strictly speaking, however, DOE would be purchasing steam from a private owner, not leasing the steam plant from a private owner, so it is not clear whether A-104 would apply. More recently, the federal government has established new discount rates for evaluating energy projects based on recent treasury security rates (Lippiatt and Ruegg 1990). Dean Devine of DOE-HQ (Federal Energy Management Program) advised that the newly prescribed rate (4.7% real) applies to the evaluation of central energy plant facilities, including boilers and cogeneration equipment, in addition to energy conservation and renewable energy investments. Therefore, a 4.7% real discount rate was assumed for the baseline federal discount rate.

Three different sources were used to establish an appropriate private discount rate. Data presented in Brown et al. (1987) and data provided by cogeneration financing consultants, Hansen and McQuat, indicated that a 6% real after-tax discount rate was reasonable. The former was based on long-run historical rates of return on corporate debt and common stock and historical debt and equity fractions. The latter was based on current debt and equity rates and fractions for private financing of a cogeneration plant serving U.S. Department of Defense (DoD) facilities. Although individual assumptions for debt and equity rates and fractions differed between the two sources, the overall real after-tax rates were essentially the same. The third source was provided by the Northwest Power Planning Council (1989). They suggested a nominal before-tax rate equivalent to about 8% real on an after-tax basis for private investments in cogeneration systems. Based on the three sources of information, a 7% real after-tax discount rate was assumed for the baseline private discount rate.

The general inflation rate was set at 5%/yr based on consistent assumptions offered by EPRI (EPRI 1989) and the Northwest Power Planning Council (1989). Even though the levelized steam cost is calculated in real 1991 dollars, an

inflation rate assumption is required to deflate future depreciation credits that are established in nominal terms. Per current tax laws identified in Van Knapp et al. (1989), depreciation under private ownership follows the 20-year modified accelerated cost recovery system (MACRS). The inflation rate assumption has no impact on the real levelized cost of steam for federal ownership scenarios.

G.4 PRECONSTRUCTION COSTS

Preconstruction includes all activities that occur prior to final design and construction. For the government ownership scenario, this includes an initial engineering study, preparation of functional design criteria, a conceptual design report, evaluation of best available control technology, and preparation of an environmental assessment (EA) or environmental impact statement (EIS). For the private ownership scenario, government preconstruction activities are reduced to preparation of the request for proposal (RFP), preparation of NEPA documentation, and activities associated with conducting a bidder's conference, reviewing proposals, selecting a winner, and negotiating a contract. Costs incurred by the private party, prior to contract award, were assumed to be borne by the private party as non-reimbursable expenses.

Preconstruction costs were separately estimated for three generic options: 1) upgrading of the current 200-East steam plant, 2) construction of a new government-owned facility, and 3) construction of a new privately-owned facility.

Preconstruction activities required for upgrading the current 200-East steam plant have either already been completed or are currently in progress and nearly finished. Expenditures already incurred or committed are "sunk costs" and were excluded from the LCC analysis. No additional preconstruction costs are required for upgrading the 200-East steam plant.

Preconstruction costs other than an EIS or EA were estimated by Westinghouse Hanford to be \$244K plus 1% of the estimated plant final design and construction cost for government ownership. An EIS should cost no more than \$1038K and could be as little as \$519K, according to PNL personnel experienced in EIS preparation. A figure of \$779K was used for estimating purposes. For a privately-built plant, preconstruction costs were estimated by Westinghouse Hanford to be about \$311K (plus \$779K for an EIS). The preconstruction period for all new government-build and private-build options was estimated at 3 years, beginning in January 1992.

Preconstruction costs in 1991 dollars are summarized in Table G.7.

G.5 PLANT BOUNDARY CONSTRUCTION COSTS

In general, plant boundary costs include all equipment and facilities to be constructed within the immediate boundaries of the proposed new plant construction site, whether the plant is owned by the government or a private

TABLE G.7. Preconstruction Costs

200-East Steam Plant Upgrade	\$0
Government Ownership	\$1023K + 1% of govt. design/const. cost
Private Ownership	\$1090K + 1% of govt. design/const. cost ^(a)

(a) For example, government-constructed connecting facilities.

company. The boundaries correspond to the specific plot that would be leased to a private owner. Connecting facilities excluded from the plant boundary estimate are specifically identified in the following section. All design and construction costs associated with upgrading the 200-East steam plant are designated "plant boundary" costs.

All cost estimates have been prepared on an "overnight construction" basis (without escalation or interest during construction, which is included in the financial methodology) in mid-1991\$. Raw cost data were updated to mid-1991\$ using cost indices pertinent to the object being evaluated. The Chemical Engineering Plant Cost Indices, Marshall and Swift Equipment Cost Indices, and gross national product (GNP) implicit price deflator were all employed when appropriate.

The construction period for L-017 was estimated to be four years, beginning in January 1993. The construction period for all new government-build and private-build options was estimated to be four years, beginning in January 1995. Thus, L-017 was estimated to start up in January 1997, and all other options to start up in January 1999.

G.5.1 Government/Private Construction Cost Differential

Kaiser Engineers Hanford (KEH) completed a preliminary analysis of the expected difference between government and private construction costs. Direct material and labor costs (typically representing about 50% of total Hanford project costs) are expected to be drawn from the same sources and would be the same for either ownership scenario. Indirect construction costs were estimated to be approximately 13% lower, however, with private ownership. Therefore, the total construction cost was assumed to be 6.5% less for private ownership. About two-thirds of the savings were attributed to the design activity, where previous related design experience and less-detailed design specifications should lower costs on the private side. Smaller savings were also projected in quality control, construction management, and client management.

G.5.2 200-East Steam Plant Upgrade

The reference case for comparison with all new plant construction alternatives is the 200-East steam plant upgrade. The upgrade consists of two completely new 101,000 lb/hr (net) stoker units and a general overhaul of current plant facilities. The combined upgrade is to be accomplished in a series of projects designated as L-017, L-094, L-009, and L-020. Costs for project L-017 were taken directly from the conceptual design report (Westinghouse Hanford 1990). Costs for the other three projects were obtained from Westinghouse Hanford personnel.

The total costs estimated for each of the four projects included escalation to the midpoint of construction. Escalation during construction was subtracted, resulting in "overnight" construction cost estimates in 1991 dollars, the same basis as used for preparing the new construction plant estimates. Escalation during construction is implicitly included in the economic methodology used for calculating the levelized steam cost. A summary of the overnight construction cost estimates for each of the four 200-East steam plant upgrade projects is shown in Table G.8.

G.5.3 Coal-Fired Steam Plant

Construction costs for a new coal-fired steam plant were derived from estimates presented in the conceptual design report for Project L-017 prepared by KEH for Westinghouse Hanford. Project L-017 costs associated with upgrading the current facility (e.g., a new dewatering system for the current ash-handling equipment) were subtracted from the L-017 estimate, and costs for incremental equipment required by a new plant (e.g., coal-handling system) were added. A list of cost elements deleted from and added to the "L-017" basis is presented in Table G.9.

Data presented by Coffin (1981) describing the costs of stoker-fired steam plants as a function of overall capacity and the number of units was used to scale the residual "L-017" estimate from two units at 101,000 lb/hr capacity (net) each to three units with a 110,000 lb/hr capacity (net) each. Site preparation (including clearing, rough grade, fine grade, soil stabilization, graveling, and paving) costs were estimated based on unit cost data presented in Building Construction Cost Data 1986 (Means 1986a). Site acreage was based

TABLE G.8. 200-East Steam Plant Upgrade Costs

Project	Overnight Construction Cost (in 1991\$)
L-017	30,277K
L-094	12,599K
L-009	1,015K
L-020	1,015K
Total	44,907K

TABLE G.9. Cost Basis Deletions/Additions

<u>Deletions</u>	<u>Additions</u>
Asbestos removal	Site preparation
Miscellaneous site work	Warehouse
Utility relocations	Waste water treatment
Power wiring in existing building	Auxiliary start-up boiler
Demolition of old brine pit	Coal-handling system
Piping in existing building	
Dewatering system	

on land requirements indicated in Boulay et al. (1986) for a plant with similar capacity. The cost for a new warehouse was estimated based on the warehouse size at the 200-East steam plant and unit cost data presented in Means (1986a). Waste water treatment and auxiliary boiler costs were estimated based on cost data presented in Esposito (1989) for these elements in similarly sized plants. Coal-handling system costs were estimated based on data presented in Boulay et al. (1986) that were scaled to the peak coal-handling rate required by the new steam plant. Plant boundary costs for a new privately-built, coal-fired steam plant are summarized in Table G.10. Total plant boundary cost for a new government-build, coal-fired steam plant would be \$52,376K.

G.5.4 Gas-Fired Steam Plant

The cost of the gas-fired steam plant was estimated from the coal-fired steam plant cost by multiplying the latter by the expected ratio of gas-fired steam plant cost to coal-fired steam plant cost. This ratio was established by consulting a dozen sources that compared stoker- and gas-fired steam plant costs for plants with the same number of units and capacity. Gas-fired boiler units were assumed to be shop-fabricated, while stoker-fired units were assumed to be field-erected. The results of the survey are shown in Table G.11. The expected ratio ranged from 0.25 to 0.65 and averaged 0.40.

TABLE G.10. Coal-Fired Steam Plant Cost Summary

<u>Element</u>	<u>Private Ownership Cost (in 1991\$)</u>
"L-017" Scale-up	42,139K
Site preparation	675K
Warehouse	104K
Waste water treatment	343K
Auxiliary start-up boiler	415K
Coal-handling system	5,295K
Total	48,970K

TABLE G.11. Gas/Coal Steam Plant Relative Costs

<u>Source</u>	<u>Gas/Coal Cost Ratio</u>
Coffin (1981)	0.30
Mallik (1982)	0.40
Brown et al. (1986)	0.45
Blazek et al. (1979)	0.40
CRS Sirrine (1989)	0.38
Kaiser Engineers	0.65
McQuat	0.55
Asea Brown Boveri	0.40
Babcock and Wilcox (Ohio)	0.42
Babcock and Wilcox (Portland)	0.30
Powerhouse Equipment	0.25
Riley Stoker	0.33
Average	0.40

Using the average ratio, the estimated gas-fired steam plant cost was \$19,590K for private construction. An oil storage system, with 30-day capacity, was presumed to be a special requirement resulting in an additional cost. A cost of \$860K was estimated based on oil storage system costs presented in Boulay et al. (1986) and storage system cost-scaling factors presented in Peters and Timmerhaus (1980). Thus, the total plant boundary construction cost for private ownership was estimated to be \$20,450K; the corresponding government ownership estimate is \$21,870K.

G.5.5 Gas-Fired Cogeneration Plant

Both secondary and primary gas-fired cogeneration plants were evaluated. The secondary plant consists of one cogeneration unit and two boilers; the primary plant consists of two cogeneration units and one boiler. All units in both plants are gas-fired.

The principal source of cost information for the gas-fired cogeneration plant was a quote received from General Electric (GE) for a "turn-key" combined-cycle cogeneration plant. The GE estimate was scaled down slightly to match the 110,000 lb/hr steam requirement at full extraction. Review of the GE estimate identified one item to be deleted and several items that needed to be added to complete the plant. Generic substation costs included in the GE estimate were subtracted because this item was specifically evaluated separately (see Section G.6, Connecting Facilities Costs). Additional items required to complete the estimate were a plant air system, auxiliary startup boiler, site preparation, 30-day oil storage and supply, water treatment, and waste treatment. Plant air, auxiliary boiler, and waste water treatment costs were based on estimates presented in Esposito (1989), which evaluated a gas-fired combined-cycle plant nearly identical to the system quoted by GE. Site preparation (including clearing, rough grade, fine grade, soil stabilization, graveling, and paving) costs were estimated based on unit cost data presented

in Means (1986a). Site acreage was based on land requirements indicated in Boulay et al. (1986) for a plant with similar capacity. The cost of an oil storage system with a 30-day capacity was estimated based on oil storage system costs presented in Boulay et al. (1986) and storage system cost scaling factors presented in Peters and Timmerhaus (1980). Water treatment costs were based on unit cost data presented in the "L-017" project report.

Secondary and primary cogeneration plant cost estimates were developed by combining the adjusted GE estimate for a single combined-cycle unit with cost data presented in Esposito (1989), which presented a detailed comparative evaluation of single- and multiple-unit, combined-cycle power plants. The adjusted GE estimate was segregated into items that scale linearly with the number of units (e.g., gas turbine, heat recovery steam generator, steam turbine, etc.) and items with strong economies-of-scale (e.g., balance-of-plant equipment such as plant air system, fire protection, piping, miscellaneous buildings, etc). Based on the data presented in Esposito (1989), balance-of-plant (BOP) estimates were first estimated for one-, two-, and three-unit, combined-cycle plants. BOP costs for the primary cogeneration plant (two cogeneration units and one boiler unit) were assumed to be less than for three cogeneration units, but more than for two cogeneration units; the average of the two figures was used. Similarly, BOP costs for the secondary cogeneration plant were assumed to be less than for the primary cogeneration plant, but more than for a single cogeneration unit; again, the average of the two figures was used for the estimate. Individual gas-fired boilers were assumed to cost 40% of the cost for an individual coal-fired boiler. Secondary and primary gas-fired cogeneration plant costs are summarized in Table G.12 for the private ownership scenario. The total estimated costs for secondary and primary cogeneration plants with government ownership are \$53,435K and \$76,823K, respectively.

TABLE G.12. Gas-Fired Cogeneration Plant Cost Summary

Element	Private Ownership Costs (in 1991\$)	
	Secondary Cogeneration	Primary Cogeneration
Combined-cycle unit(s)	23,411K	46,821K
Boiler units	9,344K	4,672K
Cooling system	1,339K	1,962K
General facilities	13,268K	15,147K
Site preparation	260K	260K
Oil storage	1,318K	1,568K
Water treatment	675K	779K
Waste treatment	343K	343K
Total	49,957K	71,551K

G.5.6 Coal-Fired Cogeneration Plant

The principal data source used to establish costs for the coal-fired cogeneration plants was a report by Boulay et al. (1986) that evaluated a 50-MW coal-fired steam Rankine power plant. Coal-handling system costs were scaled to the peak coal-handling rates required by the cogeneration plants. Steam generation (boiler) costs were scaled to the design steam rate and pressure, and adjusted to a stoker design basis based on relative cost data presented in Coffin (1981). The resultant cost is consistent with the boiler cost estimated for a new steam plant; the higher cost for the cogeneration plant steam boiler is due to its higher steam flow rate and pressure. Power production costs were scaled down based on cost data for systems of different size presented in Esposito (1989). Again, power production costs estimated for the coal-fired cogeneration plants are consistent with that estimated for the steam Rankine portion of the gas-fired cogeneration plants. The higher cost of the former is attributable to its higher inlet steam flow and use of multiple feedwater heating stages.

Boiler house costs were estimated directly from the boiler house estimate presented in the "L-017" project documentation. Turbine building and turbine crane costs were estimated based on the costs presented in Esposito (1989). Balance-of-plant (general facilities) costs presented in Boulay et al. (1986) were scaled down to a single cogeneration unit size based on relative BOP cost data presented in Esposito (1989). After subtracting the separately estimated boiler house, turbine building, and turbine crane costs, BOP costs for secondary and primary coal-fired cogeneration plants were estimated based on the same relative costs previously estimated for single-unit, secondary-plant, and primary-plant gas-fired cogeneration. The costs for individual coal-fired boiler units were derived from the estimates prepared for the "L-017" project, with a slight adjustment for the difference in steam-generating capacity. Water treatment and waste treatment costs were set equal to that estimated for gas-fired cogeneration plants.

Secondary and primary coal-fired cogeneration plant costs are summarized in Table G.13 for the private ownership scenario. The total estimated costs for secondary and primary coal-fired cogeneration plants with government ownership are \$73,492K and \$89,137K, respectively.

G.6 CONNECTING FACILITIES COSTS

Connecting facilities are required to integrate a new steam or cogeneration plant into the current infrastructure at Hanford. Connecting facilities include steam and filtered water lines for all plants, low-voltage power for steam plants, high-voltage power for cogeneration plants, and a rail spur upgrade for coal-fired plants. A new gas-delivery pipeline would be required for gas-fired plants, but the analysis assumes (see Appendix D) that a natural gas company would construct the pipeline and recover cost through gas sales.

The proposed site for a new steam or cogeneration plant is located just to the northwest of the intersection of Route 3 connecting 200-West and 200-East and

TABLE G.13. Coal-Fired Cogeneration Plant Cost Summary

<u>Element</u>	<u>Private Ownership Costs (in 1991\$)</u>	
	<u>Secondary Cogeneration</u>	<u>Primary Cogeneration</u>
Coal handling	5,845K	6,374K
Steam generation	35,485K	37,343K
Power generation	11,005K	20,971K
General facilities	15,365K	17,535K
Water treatment	675K	779K
Waste treatment	343K	343K
Total	68,715K	83,344K

Route 4 North. The specific location is identified as "Site B."^(a) Approximately 20 acres would be required for a coal-fired plant and 8 acres for a gas-fired plant. For the purposes of calculating the length of connecting facilities, the 8-acre, gas-fired site was assumed to sit in the southeast corner of the 20-acre, coal-fired site and all connecting distances were measured to the center of the 8-acre site.

The current steam line connecting 200-East and 200-West Areas runs along the north side of Route 3 near the southern edge of the proposed site. The connecting distance was estimated to be 550 ft. The cost for 550 ft of 24-in.-diameter pipe (same diameter as the steam tie-line connecting 200 East and 200 West), including fittings, valves, insulation, casing, and ground supports, was estimated to be \$311,450.

Filtered make-up water will come from the current filter plant in the 200-East Area. The pipeline was assumed to run north from the filter plant to the current steam tie-line and then follow its right-of-way over to the new site. The total length of the new pipe was estimated to be 7320 ft. The peak make-up water requirement (250,000 lb/hr) is approximately the same for all plants, even though the cogeneration plants consume more water on an annual basis. The sum of make-up water required to replace extracted process steam and cooling tower consumption is nearly constant. The cost for 7320 ft of 6-in.-diameter pipe (design velocity = 5 ft/sec at peak flow), including fittings, valves, insulation, casing, and ground supports, was estimated to be \$570,992.

A 2.4-kV power line runs alongside the steam tie-line connecting the 200-East and 200-West Areas; hence, the low-voltage power connecting distance was also estimated to be 550 ft. Low voltage tie-in costs were estimated based on providing 1 MVA service with 550 ft of cabling and ducting and an isolation transformer. The total cost was estimated to be \$51,908.

(a) Memo from Doug Mills to Chuck Hatch (both of Westinghouse Hanford), dated January 10, 1991.

Each of the cogeneration plants would have to be connected to the 230-kV power grid at Hanford in order to export power from the site. Currently, the nearest 230-kV line is located approximately 2 miles north of the proposed site. However, plans for the Hanford Waste Vitrification Plant (HWVP) would reroute the 230-kV line to a new substation about 1/2 mile northeast of the proposed power plant site.

Discussions were held with the Waste Tank Safety Operations/Remediation staff, Westinghouse Hanford's HWVP office, to determine how a cogeneration plant could be integrated into the plans for a new HWVP substation. According to Westinghouse Hanford, system stability concerns would not permit two independent substations in such proximity. Therefore, he developed rudimentary designs that identified the incremental equipment requirements for each of the four cogeneration options. The substation designs developed have two parallel transformers with protective equipment that would allow primary service of HWVP and the cogeneration plant, even with a failure in one of the transformers or one of the incoming 230-kV lines. Incremental equipment requirements for each of the four cogeneration options are shown in Table G.14, along with the estimated cost. Cost data were provided by Westinghouse Hanford staff and supplemented by data from EPRI's Technical Assessment Guide (1989) and Means Electrical Cost Data 1986 (Means 1986b).

TABLE G.14. Incremental Substation Requirements and Costs

<u>Secondary Coal Cogeneration (15 MW)</u>	<u>Primary Coal Cogeneration (30 MW)</u>
2-1200 A breakers	3-1200 A breakers
2-13.8 kV, 1200 A bus	2-13.8 kV, 2000 A bus
57,600 ft of cable	Upgrade 2-1200 A breakers to 2000 A
6,400 ft of cable duct	Upgrade 2-25/33/42 MVA transformers
	to 30/40/50 MVA
Total cost = \$763K	57,600 ft of cable
	6,400 ft of cable duct
	Total cost = \$1126K
<u>Secondary Gas Cogeneration (49 MW)</u>	<u>Primary Gas Cogeneration (97 MW)</u>
1-1200 A breaker	2-1200 A breakers
2-2000 A breaker	2-2000 A breakers
2-13.8 kV, 3000 A bus	1-3000 A breaker
Upgrade 2-1200 A breakers to 3000 A	2-13.8 kV, 5000 A bus
Upgrade 2-25/33/42 MVA transformers	Upgrade 2-1200 A breakers to 5000 A
to 40/50/60 MVA	Upgrade 2-25/33/42 MVA transformers
57,600 ft of cable	to 80/100/120 MVA
6,400 ft of cable duct	57,600 ft of cable
Total cost = \$1552K	6,400 ft of cable duct
	Total cost = \$3291K

The coal-fired plants will require an upgrade to a current rail spur that would serve the new plant site. The length of the spur is approximately 6900 ft. Recent estimates for rail upgrades are about \$93-102/linear ft, according to the Operations Support Services Department, Westinghouse Hanford. Based on an average expected cost of \$98/ft, the total cost for upgrading the rail spur was estimated to be \$674,809.

G.7 STARTUP AND WORKING CAPITAL COSTS

Startup and working capital costs were estimated using assumptions established in EPRI (1989). Startup or preproduction costs are defined by EPRI to include operator training, equipment checkout, changes in equipment, extra maintenance, and inefficient use of fuels and other materials during startup. Working capital includes an initial inventory of fuel, consumables, and spare parts plus adequate funding to cover two months of operating expenses. The specific assumptions used for estimating startup and working capital costs are summarized in Table G.15.

G.8 OPERATION AND MAINTENANCE COSTS

Operation and maintenance (O&M) costs include labor, maintenance materials, and consumable supplies. Fuel costs are addressed separately in the following section. The O&M estimate is limited to costs that are incurred within the plant boundary. "Home office" expenses were not included because they were presumed to be the same for either government or private ownership. However, the private operator is allowed \$103,817/yr of profit as an incentive for being in business, in addition to the profit required to provide a reasonable rate of return on capital investment.^(a)

TABLE G.15. Startup and Working Capital Estimating Assumptions

Startup

One month O&M at full capacity +
one week fuel at full capacity +
2% of total plant investment

Working Capital

Four months fuel at full capacity +
two months O&M at full capacity +
two months consumables at full capacity +
0.5% of total plant investment

(a) Telephone communication with McOuat, 1991.

Labor costs were estimated by first establishing the requirements for operating, maintenance, and overhead labor. The sum of these three labor requirements was then split into exempt and nonexempt portions and multiplied by the respective labor rate for these latter two categories. Labor requirements and rates were established by reviewing Westinghouse Hanford O&M estimates for an upgraded 200-East steam plant and O&M data presented in Boulay et al. (1986) and Esposito (1989), which evaluated several small coal- and gas-fired power plants. Strong agreement was found between the estimates prepared by Westinghouse Hanford and those found in Boulay et al. (1986) and Esposito (1989) for similarly sized plants. This confirmed the initial presumption that no significant O&M cost differences would exist between government and private ownership. Labor requirements and costs are summarized in Table G.16. Annual charges of \$52,000 and \$78,000 were allowed for nonexempt and exempt staff, respectively, which covers direct wages and benefits.

Maintenance material costs were estimated based on a fraction of total installed capital cost, including indirect costs and contingency. Data presented in the literature (Boulay et al. 1986; Esposito 1989; Mallik 1982; EPRI 1989) indicated that a narrow range around 2% was reasonable, with coal-fired systems having a higher fraction than gas-fired systems. Annual maintenance material cost fractions of 1.7% and 2.2% were established for gas-fired and coal-fired systems, respectively, based on estimating data presented in EPRI (1989).

Consumable supplies include filtered makeup water, boiler feedwater chemicals, cooling water chemicals (cogeneration systems only), flue gas desulfurization lime (coal-fired systems only), ash disposal (coal-fired systems only), and electricity (boiler units only; cogeneration unit parasitic electricity consumption subtracted from gross electricity power output).

An allowance for the cost of filtered makeup water supplied by the 200-Area water plant (\$1/1000 gal) was established from data presented in Peters and Timmerhaus (1980) and Boulay et al. (1986). Makeup water is required to replace exported steam (none of which is returned to the steam or cogeneration plant); steam-cycle blowdown; steam injection for NO_x control in gas turbines; and cooling system consumption (evaporation, drift, and blowdown) for the cogeneration plants. Replacement of exported steam and cooling system consumption represents over 90% of the makeup water requirement. The sum of cooling

TABLE G.16. Labor Requirements and Costs (full-time staff)

Plant	Operation	Maintenance	Overhead	Total	Nonexempt	Exempt	Annual Cost
200-East Upgrade	28	14	8	50	38	12	\$2,907K
Coal Steam	28	14	8	50	38	12	\$2,907K
Gas Steam	14	7	4	25	19	6	\$1,453K
Primary Coal Cogeneration	38	19	10	67	51	16	\$3,893K
Primary Gas Cogeneration	24	12	6	42	32	10	\$2,440K
Secondary Coal Cogeneration	33	17	9	59	45	14	\$3,426K
Secondary Gas Cogeneration	19	9	5	33	25	8	\$1,921K

system consumption and replacement of exported steam is approximately constant. Therefore, peak makeup water requirements are approximately the same for steam and cogeneration systems, even though annual makeup water requirements are higher for cogeneration systems. Makeup water requirements and costs are summarized in Table G.17.

Boiler-feedwater and cooling-water treatment consumes chemicals to control hardness, pH, total dissolved solids, and oxygen concentration. Cost data presented in Boulay et al. (1986) and Esposito (1989) were used to establish a rate of \$52/million lb of makeup boiler feedwater and \$26/million lb of makeup cooling water. Annual boiler feedwater and cooling water chemical treatment costs are summarized in Table G.18.

Lime is consumed in the flue gas desulfurization process which is required for all coal-fired plants. The lime required per MMBTU of coal combusted was established based on data presented in the conceptual design report for project L-017, upgrade of the current steam plant (Westinghouse Hanford 1990). The cost of lime was set at \$57/ton based on data in Esposito (1989) and EPRI (1989). The resultant lime charge was \$0.035/MMBTU of coal.

TABLE G.17. Makeup Water Requirements and Costs

Plant	Peak Demand (10 ³ lb/hr)	Annual Demand (10 ⁶ lb/yr)	Annual Cost (1990\$)
200-East Upgrade	230	970	120K
Coal Steam	230	970	120K
Gas Steam	230	970	120K
Primary Coal Cogeneration	249	1870	233K
Primary Gas Cogeneration	256	2030	233K
Secondary Coal Cogeneration	240	1200	149K
Secondary Gas Cogeneration	243	1250	156K

TABLE G.18. Chemical Treatment Costs

Plant	Boiler Feedwater Treatment Costs (1991\$/yr)	Cooling Water Treatment Costs (1991\$/yr)
200-East Upgrade	51K	N/A
Coal Steam	51K	N/A
Gas Steam	51K	N/A
Primary Coal Cogeneration	55K	23K
Primary Gas Cogeneration	56K	26K
Secondary Coal Cogeneration	53K	6K
Secondary Gas Cogeneration	53K	6K

Solid wastes (fly ash, calcium sulfite, calcium sulfate, unreacted lime) resulting from coal-fired flue gas cleanup will need to be properly disposed. Various options are possible, including backfill at the coal mine; offsite disposal at a certified hazardous waste site such as Arlington, Oregon; or disposal at Hanford at a certified site to be developed. No assumptions were made regarding the specific scenario that is most likely to occur. Rather, based on EPRI (1989), a nominal disposal charge of \$10/ton was assumed for preliminary planning purposes to help differentiate between gas-fired and coal-fired cases. The amount of solid waste generated per MMBTU of coal combusted was also established based on data presented in the conceptual design report for project L-017 (Westinghouse Hanford 1990). The resultant solid waste disposal charge was \$0.032/MMBTU of coal.

Boiler unit electric power consumption was estimated [from data presented in Coffin (1981)] to be 0.0025 kWh/lb steam and 0.0030 kWh/lb steam for gas-fired and coal-fired boilers, respectively. Electricity was assumed to be priced at the current effective (demand and energy charges melded together) BPA rate of \$0.0231/kWh. As noted above, plant electric power consumption associated with the cogeneration units was subtracted from the gross cogeneration unit output. The resultant annual electricity charges for each plant type are shown in Table G.19.

G.9 FUEL COSTS

Fuel cost assumptions were addressed in detail in Appendix D and are summarized in Table G.20. The government premium for "delivered" coal is due to special purchasing regulations that inhibit securing the best possible rate. Government coal is presumed to be delivered by an outside railroad to the 1100 Area and subsequently delivered to the coal-fired plant by the Hanford railroad. The \$1,038,000 annual Hanford railroad charge for government ownership represents the estimated marginal cost of operating and maintaining the Hanford rail system, a cost that could be avoided if no coal was handled by the Hanford railroad. Private coal is presumed to be delivered by an outside railroad directly to the new coal-fired plant. The \$519,000 annual Hanford railroad charge for private ownership represents the estimated marginal cost of maintaining the Hanford rail system, i.e., \$519,000 in Hanford railroad

TABLE G.19. Boiler Unit Electricity Costs

<u>Plant</u>	<u>Annual Cost (1991\$/yr)</u>
200-East Upgrade	69K
Coal Steam	69K
Gas Steam	58K
Primary Coal Cogen	1K
Primary Gas Cogen	1K
Secondary Coal Cogen	20K
Secondary Gas Cogen	15K

TABLE G.20. Reference Fuel Cost Assumptions

<u>Cost Element</u>	<u>Government</u>	<u>Private</u>
"Delivered" Coal Price (in 1991\$)	2.55/MMBTU	2.25/MMBTU
Annual Hanford Railroad Charge (in 1991\$)	1038K	519K
Real Annual Coal Escalation Rate	1%/yr	1%/yr
"Delivered" Gas Price (in 1991\$)	3.25/MMBTU	3.25/MMBTU
Annual Hanford Railroad Charge	0	0
Real Annual Gas Escalation Rate	3%/yr	3%/yr

operating charges are saved in this scenario. Within the range of annual coal deliveries required for the alternative plants considered, the Hanford railroad charges were assumed to be fixed.

The delivered gas price of \$3.25/MMBTU includes the gas company's amortized cost for installing a gas pipeline to serve the new plant location. Annual charges of \$519,000 and \$1,038,000 for Hanford railroad charges are saved relative to government and private coal-fired plant scenarios.

G.10 ELECTRIC POWER REVENUES

Electric power revenue rate assumptions were addressed in detail in Appendix E and are summarized in Table G.21. A government-owned cogeneration plant would likely sell its power to BPA at an estimated rate of 33 mill/kWh (1990\$) with zero real escalation. A privately-owned cogeneration plant would have more flexibility in marketing its power. Prospective sales to Pacific Northwest (PNW) utilities might be expected to yield 36 mill/kWh (1990\$), less 2 mill/kWh for transmission with zero escalation. Sales to Pacific Southwest (PSW) utilities could yield substantially higher revenues, perhaps 46 mill/kWh (1990\$), less 4.5 mill/kWh for transmission, but with 2.0%/yr real escalation. Washington State B&O taxes equal to 3.852% of electricity revenues would be levied against sales outside of Washington.

TABLE G.21. Reference Electricity Revenue Rates

<u>Ownership/Customer</u>	<u>Basic Rate</u>	<u>Transmission Charge</u>	<u>Escalation Rate</u>
Government/BPA	33 mill/kWh	N/A	0%/yr real
Private/PNW utility	36 mill/kWh	2 mill/kWh	0%/yr real
Private/PSW utility	46 mill/kWh	4.5 mill/kWh	2.0%/yr real

G.11 PLANT PERFORMANCE

Plant performance and operating strategy determine the annual fuel consumption and (for cogeneration plants) electric power output, and subsequently, annual fuel costs and electric power revenues. Although each of the seven plant configurations provides the same peak and annual steam demand, each has unique performance characteristics resulting in different fuel consumption and power output (for cogeneration systems).

G.11.1 Steam Production

The reference annual net steam demand (exported from the plant boundary) for the 200 Area is 930 million lb/yr. The preliminary Westinghouse Hanford RFP established a prospective range of 700-1300 million lb/yr of gross steam demand. A single reference figure of 1100 million lb/yr of gross steam demand was selected based on advice received from Chuck Hatch of Westinghouse Hanford. The conversion from gross to net steam demand was calculated based on the net/gross ratio defined in the conceptual design report for project "L-017" (Westinghouse Hanford 1990).

A single annual steam demand figure is adequate for evaluating the annual performance and fuel consumption of either coal-fired or gas-fired boiler plants, where all three units are identical. A more complicated situation exists for the cogeneration plants, which include either one boiler unit and two cogeneration units, or two boiler units and one cogeneration unit. Because of differences in fuel efficiency and power output between the boiler and cogeneration units, the amount of steam generated via each technology type must be estimated for each cogeneration plant. This requires definition of the expected steam demand distribution, unit availability, and unit operating strategy.

Detailed steam demand distribution data were not available at the time this study was conducted. The only indication of steam demand distribution was a series of estimates of the gross peak demand for each month presented in Westinghouse Hanford's draft RFP. These data were used to prorate the total annual demand into monthly totals, i.e., total monthly demand was assumed to be proportional to monthly peak demand. The average hourly demand was then calculated directly by dividing the monthly total by the number of hours in the month. The minimum hourly demand was estimated by assuming that the difference between the average hourly and minimum hourly demands was equal to the difference between the peak hourly and average hourly demands. Finally, the steam demand was assumed to be evenly distributed over time, resulting in a cumulative demand distribution curve for each month as shown in Figure G.1. The resultant monthly steam demand characteristics based on these assumptions are shown in Table G.22.

For the secondary cogeneration plant, the single cogeneration unit was presumed to operate all the time, except for planned and unplanned outages. One or both of the boiler units would operate during the cogeneration unit outage period or when the net steam demand exceeded 110,000 lb/hr. The amount of monthly steam demand potentially provided by the cogeneration unit (i.e.,

S9103009.1

FIGURE G.1. Monthly Steam Demand Distribution

TABLE G.22. Monthly Steam Demand Characteristics

Month	Total Monthly Demand, 10^6 lb	Max. Hourly Demand, 1000 lb	Ave. Hourly Demand, 1000 lb	Min. Hourly Demand, 1000 lb
January	108.4	232	148.5	65.0
February	104.7	224	143.4	62.8
March	93.0	199	127.4	55.8
April	88.8	190	121.6	53.2
May	57.5	123	78.8	34.6
June	53.3	114	73.0	32.0
July	49.5	106	67.8	29.6
August	49.5	106	67.8	29.6
September	55.1	118	75.5	33.0
October	69.2	148	94.8	41.6
November	93.0	199	127.4	55.8
December	108.4	232	148.5	65.0

unadjusted for planned and unplanned outages) was calculated as illustrated in Figure G.2. The month was split into two time periods at the point representing the peak steam capacity (110,000 lb/hr) of the cogeneration unit. The total monthly steam demand provided by the cogeneration unit and boiler units is depicted in Figure G.2. Mathematically, the monthly cogeneration unit steam output is equal to the average hourly steam rate below 110,000 lb/hr multiplied by the number of hours when steam production is less than or equal to 110,000 lb/hr plus 110,000 lb/hr multiplied by the balance of hours in the month. The resultant monthly cogeneration unit and boiler unit steam demand for secondary cogeneration plants (unadjusted for availability) is shown in Table G.23.

For a secondary cogeneration plant with a single cogeneration unit, the planned outage was assumed to occur in the summer, when steam demand was lowest. The lowest monthly cogeneration steam output shown in Table G.23 was reduced by the fraction of planned downtime expected to occur that month. The unplanned outage could occur any time. Therefore, the estimated total annual cogenerated steam output shown in Table G.23 was reduced by the fraction of unplanned downtime expected to occur in a year. Reductions in the potential

S9103009.2

FIGURE G.2. January Steam Output from Cogeneration and Boiler Units

TABLE G.23. Cogeneration and Boiler Unit Steam Production for Secondary Cogeneration Plants^(a)

<u>Month</u>	<u>Monthly Cogeneration Output (10⁶ lb)</u>	<u>Monthly Boiler Output (10⁶ lb)</u>
January	75.9	32.5
February	75.3	29.4
March	72.8	20.2
April	71.7	17.1
May	56.8	0.7
June	53.2	0.1
July	49.5	0.0
August	49.5	0.0
September	54.8	0.3
October	64.3	4.9
November	72.8	20.2
December	75.9	32.5
Annual Total	772.5	157.9

(a) Unadjusted for availability.

cogeneration-unit, annual steam output, due to planned and unplanned outage, were subtracted from the annual total shown in Table G.23 to determine the actual expected annual total.

For a primary cogeneration plant with two cogeneration units, the planned outage for both was assumed to occur consecutively in the summer, when steam demand was lowest. Therefore, planned outage does not reduce the amount of steam that could be provided by a cogeneration unit. An unplanned outage would reduce the amount of steam that could be provided by the cogeneration units any time the hourly steam demand exceeds the single unit capacity of 110,000 lb/hr. If one cogeneration unit was always down, the annual steam demand provided by the backup boiler would be the same as calculated above for a secondary cogeneration plant. With two cogeneration units, the annual steam load provided by the backup boiler is equal to the amount of steam provided by the backup boilers for the secondary cogeneration plant multiplied by the cogeneration unit unplanned outage rate.

The annual availability for a gas-fired cogeneration unit was assumed to be 0.90, based on data presented in EPRI (1989). The annual availability for a coal-fired cogeneration unit was assumed to be 0.85 based on data presented in EPRI (1989) and Coffin (1981). In both cases, the annual downtime was assumed to be split half and half between planned and unplanned outages. The resultant annual steam output provided by cogeneration and boiler units for each of the four cogeneration plants is shown in Table G.24.

TABLE G.24. Annual Cogeneration and Boiler Unit Steam Production

<u>Plant</u>	<u>Cogeneration Unit Steam (10^6 lb/yr)</u>	<u>Boiler Unit Steam (10^6 lb/yr)</u>
Secondary Gas Cogeneration	704.2	226.2
Secondary Coal Cogeneration	670.0	260.4
Primary Gas Cogeneration	922.5	7.9
Primary Coal Cogeneration	918.6	11.8

G.11.2 Boilers

Boiler plant performance is captured in two factors: 1) the fraction of the combusted fuel's higher heating value (HHV) energy that is transferred to the water/steam passing through the boiler unit (the boiler efficiency), and 2) the ratio of net steam exported from the plant to gross steam exiting the boiler units. The latter factor accounts for internal (parasitic) plant steam consumed by deaeration, blowdown, and steam turbines driving the forced and induced draft fans. The ratio of net to gross steam production was assumed to be the same for all low-pressure boilers and was set equal to the ratio (0.845) defined in the conceptual design report for project L-017. The boiler efficiency differs slightly between gas-fired and coal-fired stoker units, however. Based on information presented in Payne (1986), the boiler efficiencies were set at 0.82 and 0.81 for coal-fired stoker and gas-fired boiler units, respectively, based on the HHV of each fuel.

G.11.3 Combined Cycle Cogeneration

Performance characteristics for the gas-fired cogeneration unit were based on specifications obtained directly from GE. GE data for a system designed to produce 125,000 lb/hr at maximum extraction in the steam turbine were linearly scaled down to the design steam production rate of 110,000 lb/hr. Plant performance data were provided at ISO conditions, i.e., at one atmosphere pressure and 59°F. The actual output of the combined-cycle unit will vary with atmospheric conditions. Power output will be greater during the winter and less during the summer. However, ISO conditions are fairly close to the annual average conditions experienced at Hanford. An annual hour-by-hour simulation of plant power production would produce a more accurate prediction of expected performance, but this level of detail was beyond the scope of a LCC analysis.

Power production and fuel consumption data are summarized in Table G.25 for the gas-fired, combined-cycle unit. The fuel consumption rate, gas turbine power output, and auxiliary power consumption remain constant while the steam turbine power output varies inversely with the steam extraction rate in a relationship that is approximately linear. The unit heat rate at full condensation (no steam extracted) is about 8700 Btu/kWh.

TABLE G.25. Gas-Fired Combined-Cycle Performance Summary

Gas Turbine Output	35.4 MW
Steam Turbine Output	14.1 MW at 0 lb/hr extraction 9.1 MW at 55,000 lb/hr extraction 4.2 MW at 110,000 lb/hr extraction
Auxiliary Power	0.8 MW
Net Power at 0 Extraction	48.7 MW
Net Power at Full Extraction	38.8 MW
Net Power Output (MW) =	$48.7 - 0.09(\text{klb/hr extracted})$
Fuel Consumption	423.5 MMBTU/hr

G.11.4 Steam Rankine Cogeneration

The coal-fired steam, Rankine cogeneration unit employs the same throttle (turbine inlet) and condensing temperatures and pressures as the steam turbine for the gas-fired, combined-cycle unit. The throttle steam flow is higher for the coal-fired system, however, because additional steam is extracted for feedwater heating and deaerating purposes. Extraction conditions for feedwater heating and deaerating were established based on conditions assumed in Boulay et al. (1986), which evaluated a similar coal-fired steam Rankine plant. The gross power output for the unit was calculated via an energy balance around the turbine, assuming the same turbine efficiency as for the gas-fired cogeneration unit steam turbine. The reduction in power output that is due to extraction of process steam at 225 psig is also the same as for the gas-fired cogeneration unit steam turbine. Parasitic power consumption was assumed to be the same on a percentage basis as that described in Boulay et al. (1986).

Fuel consumption was calculated via an energy balance around the boiler. Parasitic steam consumption within the coal-fired cogeneration boiler unit is limited to blowdown; turbine extraction steam is used for deaeration; and all fan and pump drives are assumed to be driven by electric motors per Boulay et al. (1986). The boiler efficiency was set at 0.82, the same as for the low-pressure, coal-fired boiler units.

Power production and fuel consumption data are summarized in Table G.26 for the coal-fired steam Rankine unit. The fuel consumption rate and auxiliary power consumption remain constant while the steam turbine power output varies inversely with the steam extraction rate in a relationship that is approximately linear. The unit heat rate at full condensation (no process steam extracted) is about 14,400 Btu/kWh, considerably poorer than for the gas-fired combined-cycle unit.

G.11.5 System Fuel Consumption and Power Production

Annual fuel consumption and power production statistics are summarized in Table G.27 for each of the six steam or cogeneration plants evaluated. The annual steam production of 930 million lb is the same for all of the plants. Fuel consumption is the least for the boiler plants; slightly more fuel is

TABLE G.26. Coal-Fired Steam Rankine Performance Summary

Steam Turbine Output	16.3 MW at 0 lb/hr extraction 11.4 MW at 55,000 lb/hr extraction 6.4 MW at 110,000 lb/hr extraction
Auxiliary Power	1.3 MW
Net Power at 0 Extraction	15.0 MW
Net Power at Full Extraction	5.1 MW
Net Power Output (MW) = 15.0 - 0.09(1,000 lb/hr extracted)	
Fuel Consumption	215.6 MMBTU

TABLE G.27. Annual Fuel Consumption and Power Production Summary

<u>Plant</u>	<u>Fuel Consumption (10¹² Btu)</u>	<u>Power Output (GWh)</u>
Coal-Fired Boilers	1.41	0
Gas-Fired Boilers	1.42	0
Secondary Coal Cogeneration	2.00	51
Secondary Gas Cogeneration	3.69	321
Primary Coal Cogeneration	3.23	141
Primary Gas Cogeneration	6.69	685

consumed in the gas-fired boiler plant because of its lower boiler efficiency (based on HHV). Fuel consumption is greater for the cogeneration plants, of course, because electricity is produced in addition to steam. Power output for the gas-fired cogeneration plants is significantly higher than for coal-fired cogeneration plants because of the inclusion of a gas turbine in the former; the steam turbine is about the same size in both plants. Fuel consumption for the gas-fired cogeneration plants, although higher than for the corresponding coal-fired plants, is not as high as the relative power output might suggest because of the significant efficiency advantage of combined-cycle technology compared to steam Rankine.

G.12 LEVELIZED STEAM COSTS

The levelized cost of steam over a 30-year period was calculated for each plant and ownership scenario by combining the cost, performance, and economic characteristics described above and employing the economic methodology defined in Brown et al. (1987). The key inputs and results for each case evaluated are presented in the following subsections.

G.12.1 Levelized Cost Analysis Input Summary

Initial capital costs, annual O&M costs, and annual fuel costs are summarized for each plant option in Tables G.28 through G.34. Annual electricity and steam production were summarized in Section G.10 and are not repeated here.

TABLE G.28. 200-East Plant Upgrade Costs

<u>Item</u>	<u>Government</u>	<u>Private Ownership</u>	
	<u>Ownership</u>	<u>Government</u>	<u>Private</u>
Preconstruction (1991\$K)	0		N/A
Construction (1991\$K)	44,907		N/A
Startup (1991\$K)	1,586		N/A
Inventory/Working Capital (1991\$K)	3,645		N/A
Operation and Maintenance (1991\$K/yr)	4,394		N/A
Fuel (1991\$K/yr)	3,579		N/A
Hanford Train (1991\$K/yr)	1,038		N/A

TABLE G.29. Coal-Fired Steam Plant Costs

<u>Item</u>	<u>Government</u>	<u>Private Ownership</u>	
	<u>Ownership</u>	<u>Government</u>	<u>Private</u>
Preconstruction (1991\$K)	1,562	1,107	0
Construction (1991\$K)	53,986	1,609	48,972
Startup (1991\$K)	1,622	35	1,484
Inventory/Working Capital (1991\$K)	3,659	13	3,313
Operation and Maintenance (1991\$K/yr)	4,429	35	4,319
Fuel (1991\$K/yr)	3,579	0	3,140
Hanford Train (1991\$K/yr)	1,038	519	0

TABLE G.30. Gas-Fired Steam Plant Costs

<u>Item</u>	<u>Government</u>	<u>Private Ownership</u>	
	<u>Ownership</u>	<u>Government</u>	<u>Private</u>
Preconstruction (1991\$K)	1,251	1,099	0
Construction (1991\$K)	22,809	934	20,452
Startup (1991\$K)	838	20	787
Inventory/Working Capital (1991\$K)	3,852	7	3,833
Operation and Maintenance (1991\$K/yr)	2,070	16	2,031
Fuel (1991\$K/yr)	4,731	0	4,731
Hanford Train (1991\$K/yr)	0	0	0

TABLE G.31. Secondary Coal-Fired Cogeneration Plant Costs

<u>Item</u>	<u>Government Ownership</u>	<u>Private Ownership</u>	
		<u>Government</u>	<u>Private</u>
Preconstruction (1991\$K)	1,780	1,113	0
Construction (1991\$K)	75,813	2,320	68,716
Startup (1991\$K)	2,154	51	1,980
Inventory/Working Capital (1991\$K)	4,261	20	3,853
Operation and Maintenance (1991\$K/yr)	5,458	51	5,301
Fuel (1991\$K/yr)	5,087	0	4,464
Hanford Train (1991\$K/yr)	1,038	519	0

TABLE G.32. Primary Coal-Fired Cogeneration Plant Costs

<u>Item</u>	<u>Government Ownership</u>	<u>Private Ownership</u>	
		<u>Government</u>	<u>Private</u>
Preconstruction (1991\$K)	1,940	1,117	0
Construction (1991\$K)	91,822	2,684	83,344
Startup (1991\$K)	2,565	58	2,358
Inventory/Working Capital (1991\$K)	4,858	23	4,391
Operation and Maintenance (1991\$K/yr)	6,443	59	6,256
Fuel (1991\$K/yr)	8,216	0	7,210
Hanford Train (1991\$K/yr)	1,038	519	0

TABLE G.33. Secondary Gas-Fired Cogeneration Plant Costs

<u>Item</u>	<u>Government Ownership</u>	<u>Private Ownership</u>	
		<u>Government</u>	<u>Private</u>
Preconstruction (1991\$K)	1,581	1,114	0
Construction (1991\$K)	55,864	2,435	49,957
Startup (1991\$K)	1,716	52	1,589
Inventory/Working Capital (1991\$K)	6,646	19	6,600
Operation and Maintenance (1991\$K/yr)	3,100	42	2,999
Fuel (1991\$K/yr)	12,242	0	12,242
Hanford Train (1991\$K/yr)	0	0	0

TABLE G.34. Primary Gas-Fired Cogeneration Plant Costs

Item	Government Ownership	Private Ownership	
		Government	Private
Preconstruction (1991\$K)	1,829	1,132	0
Construction (1991\$K)	80,698	4,173	71,551
Startup (1991\$K)	2,436	84	2,239
Inventory/Working Capital (1991\$K)	9,377	32	9,305
Operation and Maintenance (1991\$K/yr)	4,147	71	3,993
Fuel (1991\$K/yr)	22,225	0	22,225
Hanford Train (1991\$K/yr)	0	0	0

G.12.2 Reference Levelized Cost Results

Levelized cost results are presented in Table G.35 for each of the plant type and ownership combinations evaluated in this study. Reference cost, performance, and economic assumptions described earlier in this Appendix are used. Although it appears likely that the actual contracting period for a private

TABLE G.35. Thirty-Year Capital Recovery Period Results

Case Description	Levelized Costs (1991\$/1000-lb Steam)				
	Capital	Fuel	O&M	Revenue	Steam
200-East Upgrade	3.54	4.58	5.84	0	13.96
Govt. Coal Steam	4.09	4.73	6.47	0	15.29
Priv. Coal Steam	6.94	4.07	5.82	0	16.83
Govt. Gas Steam	1.89	8.76	3.04	0	13.68
Priv. Gas Steam	3.29	8.22	3.05	0	14.56
Govt. Second. Coal Cogen.	5.66	6.52	7.48	1.81	17.84
Priv. Second. Coal Cogen./PNW	9.58	5.56	6.75	1.84	20.05
Priv. Second. Coal Cogen./PSW	9.58	5.56	6.75	3.00	18.89
Govt. Prim. Coal Cogen.	6.82	10.22	8.44	5.00	20.48
Priv. Prim. Coal Cogen./PNW	11.54	8.66	7.66	5.12	22.74
Priv. Prim. Coal Cogen./PSW	11.54	8.66	7.66	8.32	19.54
Govt. Second. Gas Cogen.	4.36	21.87	4.05	11.39	18.89
Priv. Second. Gas Cogen./PNW	7.48	20.32	3.98	11.68	20.10
Priv. Second. Gas Cogen./PSW	7.48	20.32	3.98	18.90	12.88
Govt. Prim. Gas Cogen.	6.25	39.29	5.08	24.31	26.31
Priv. Prim. Gas Cogen./PNW	10.68	36.41	4.94	24.93	27.11
Priv. Prim. Gas Cogen./PSW	10.69	36.41	4.94	40.36	11.68

owner could be less than 30 years, the results presented in Table G.35 are based on a 30-year capital recovery period in order to first address cost differences stemming from other factors. The effect of multiple 10-year contracting periods is addressed separately below.

As would be expected, the cost of steam from a new government-owned, coal-fired steam plant is greater than for upgrading the 200-East plant. This higher cost is because of greater capital expenditure for a new plant and the higher O&M associated with continuing to operate the current plant for two years longer than if the 200-East boiler plant was upgraded.

A new privately-owned, coal-fired steam plant was projected to produce higher cost steam than a new government-owned plant of the same type. Lower construction costs, O&M costs, and coal costs for the privately-owned plant do not make up for the private owner's higher cost of capital (discount rate). These relationships hold for other cases, as well. The levelized cost of capital is always lower for government ownership, while the levelized cost of fuel for coal-fired plants is always lower for private ownership.

Gas-fired steam plants were predicted to produce lower cost steam than new coal-fired steam plants for the reference cost and performance assumptions. In fact, the cost of steam predicted for a new government-owned, gas-fired plant is less than for upgrading the 200-East plant. Capital and O&M costs are greater for the coal-fired plants, but fuel costs are much higher for the gas-fired plants. The cost of steam for a gas-fired plant is especially sensitive to the expected future price of natural gas. The reference gas price escalation rate is 3%/yr in real terms, i.e., 3%/yr in excess of general inflation. The sensitivity of levelized steam costs to natural gas prices and escalation rates is examined below.

Neither secondary nor primary coal-fired cogeneration plants are superior to coal-fired steam plants. Even for the relatively optimistic PSW electric revenue rate assumption, the high unit capital cost (\$/kWe) and heat rate (Btu/kWh) of the coal-fired cogeneration plant results in higher steam costs.

G.13 SENSITIVITY ANALYSIS

The cost of steam to the government is affected by many input variables to varying degrees. Four of these input variables--the electric revenue rate and escalation rate, the price of natural gas and its escalation rate, the government and private discount rate, and the length of the contract between the private firm and the government--are examined to determine how sensitive the final steam cost is to each of these variables. In all of these sensitivity analyses, only a few of the reference cases shown in Table G.35 will be used. Also, only the affected input variables will be changed; all other input values will be the same as used in the reference cases.

G.13.1 Alternative Electricity Revenue Rates

As noted above, privately-owned, gas-fired cogeneration plants could possibly provide steam to the government at costs that are significantly less than could be provided via an upgrade of the 200-East plant or any other plant evaluated in this study. The cost of steam from any of the gas-fired cogeneration plants is more sensitive to the electricity revenue rate than the coal-fired cogeneration plants because gas-fired cogeneration plants have a higher power-to-steam ratio on an annual basis (see Table G.27). The sensitivity of the cost of steam from secondary and primary gas-fired cogeneration plants is shown in Table G.36 for various combinations of initial revenue rate and future real annual percentage escalation. Note that the initial revenue rate is net of transmission charges and B&O taxes, if any. The steam costs projected in Table G.36 show that significant savings relative to the 200-East plant upgrade are possible for a high initial revenue rate and/or high future escalation rate.

Current, as well as future, electricity revenue rates are extremely speculative. If the private owner's contract with the utility allows future fuel price increases to be "passed through" to the utility, the electricity revenue escalation rate is likely to be something less than that for the price of gas, which represents about 70% of the levelized cost of a primary gas-fired cogeneration plant. The reference real gas escalation rate for Table G.36 is 3%/yr. Thus, based on the above contracting scenario, an overall revenue escalation rate of 2%/yr might be a reasonably consistent assumption.

The steam costs shown in Table G.36 were calculated based on the minimum total revenues (from electricity and steam sales) required to allow the minimum acceptable rate of return on capital. Higher electricity revenues lower the

TABLE G.36. Alternative Electric Revenue Rate Results

Initial Revenue Rate (\$/kWh)	Real Annual Revenue Rate Escalation			
	0.00%	1.00%	2.00%	3.00%
Primary Gas-Fired Cogeneration - Private Ownership Levelized Steam Cost (1991\$/1000-lb Steam)				
0.030	30.10	26.33	21.80	16.34
0.035	26.36	21.96	16.68	10.31
0.040	22.62	17.60	11.56	(4.28)
0.045	18.88	13.23	6.44	(1.75)
Secondary Gas-Fired Cogeneration - Private Ownership Levelized Steam Cost (1991\$/1000-lb Steam)				
0.030	21.50	19.74	17.62	15.06
0.035	19.75	17.69	15.22	12.23
0.040	18.00	15.65	12.82	9.41
0.045	16.25	13.60	10.42	6.58

required steam revenues, hence, the charge for steam to the government. As indicated in Table G.36, if electricity rates are high enough, the private owner could pay the government for the steam it provides to the government and still achieve the minimum acceptable return on capital. Such ridiculously low steam charges could only occur if steam cogeneration was required to qualify for the electricity revenue rate (for example, to qualify under PURPA). This scenario is unlikely with the advent of independent power producers (IPP) and bidding for resources by utilities. An independent power producer would not likely be willing to sell steam for less than the value of forgone electricity revenues caused by extracting steam from the turbine unless such sale was required to acquire the contract. Table G.37 shows the value of steam for an IPP as a function of the initial price of electricity and future real annual percentage escalation. Note that the data presented in Tables G.36 and G.37 indicate the existence of an optimum future electricity price that will minimize the cost of steam to the government.

G.13.2 Alternative Natural Gas Prices

As stated in Section G.12, the cost of steam for a gas-fired plant is very sensitive to the price of natural gas and its real escalation rate. The sensitivity of the cost of steam from privately-owned, secondary and primary gas-fired cogeneration plants is shown in Table G.38 for various combinations of initial gas price and future real annual percentage escalation. Similarly, Table G.39 shows the change in steam cost from varying the same inputs for the government-owned, gas-fired steam plant.

In comparing the two tables, one can see that the steam costs of cogeneration plants are much more sensitive to the price and escalation rate than the steam cost from the steam plant. This is, of course, due to the use of much more natural gas by the cogeneration plant. Also, note that for any combination of price and escalation rate, that the steam cost of the secondary cogeneration plant lies between the primary cogeneration plant and the steam plant. Thus, the secondary-cogeneration plant is never the best choice among the three shown.

The primary cogeneration plant has the lowest cost steam at any of the shown prices at a 2.00% real escalation rate. At higher initial prices of natural

TABLE G.37. Value of Steam (1991\$/1000-lb Steam)

Initial Price of Electricity (\$/kWh)	Real Annual Revenue Rate Escalation			
	0.00%	1.00%	2.00%	3.00%
Cogeneration - Private Ownership				
0.030	2.70	3.22	3.85	4.62
0.035	3.15	3.75	4.49	5.39
0.040	3.60	4.29	5.13	6.15
0.045	4.05	4.83	5.77	6.93

TABLE G.38. Alternative Natural Gas Price Results for Privately-Owned Plants

Primary Cogeneration Levelized Steam Cost (1991\$/1000-lb Steam)

Initial Gas Price (\$/MMBTU)	Real Annual Price Rate Escalation		
	2.00%	3.00%	4.00%
2.50	(1.86)	2.71	8.32
3.00	2.69	8.17	14.91
3.50	7.23	13.63	21.49
4.00	11.78	19.09	28.07

Secondary Cogeneration Levelized Steam Cost (1991\$/1000-lb Steam)

Initial Gas Price, \$/MMBTU	Real Annual Price Rate Escalation		
	2.00%	3.00%	4.00%
2.50	5.42	7.93	11.03
3.00	7.92	10.94	14.65
3.50	10.43	13.95	18.28
4.00	12.93	16.96	21.91

TABLE G.39. Alternative Natural Gas Price Results for Government-Owned Steam Plant

Levelized Steam Cost (1991\$/1000-lb Steam)

Initial Gas Price (\$/MMBTU)	Real Annual Price Rate Escalation		
	2.00%	3.00%	4.00%
2.50	10.53	11.64	13.02
3.00	11.56	12.89	14.54
3.50	12.58	14.13	16.06
4.00	13.60	15.37	17.58

gas at a 3.00% or 4.00% real escalation rate, the government-owned steam plant has cheaper steam. The primary cogeneration plant has lower steam costs than the 200-East upgrade option (L-017), which has a levelized steam cost of \$13.96/1000 lb (from Table G.35), for low initial prices of gas and low escalation rates. At a 3.00% escalation rate and an initial price of \$4.00/MMBTU at a 4.00% escalation rate and prices of \$3.00/MMBTU and above, L-017 is the better option.

G.13.3 Alternative Discount Rate Results

The sensitivity of the levelized steam cost to a change in the government's and the private firm's discount rate was examined. The primary, gas-fired cogeneration plant with private ownership and sales of electricity in the PSW

and the 200-East upgrade (L-017) were the cases used to investigate the sensitivity of steam costs to discount rates. The results of the sensitivity analysis are in Table G.40. The reference discount rates used in the analysis were a private after-tax, discount rate of 7% and a government discount rate of 4.7%, all real rates.

For the primary cogeneration case in Table G.40, the levelized steam is very insensitive to changes in the government or private discount rates. The difference between the steam cost at the low end of the table (3% government rate, 6% private rate) and the high end of the table (5% government rate, 8% private rate) is only \$0.48/1000-lb steam. The sensitivity of L-017 to a change in the government discount rate is a little higher, an increase of \$0.85/1000-lb steam when the rate rises from 3% to 5%. On the whole, then, the discount rate has very little effect on the final steam cost of either option examined.

G.13.4 Alternative Contracting Periods

As noted earlier, a private plant owner may likely be limited to a contract length significantly less than the expected duration of the steam demand in the 200 Area and the typical economic life of a new steam plant (both approximately 30 years). A shorter contracting period may have a significant impact on a steam-only plant; a cogeneration plant could possibly switch to pure power production if no subsequent steam contract were negotiated, thus reducing the private owner's risk in that situation.

The levelized cost of steam from a privately-owned, coal-fired, and gas-fired steam plant was calculated for three consecutive 10-year contracts. The private owner was assumed to charge a price for steam in each period that would result in the minimum acceptable rate of return in that period, under the initial presumption that the plant would not operate for more than the

TABLE G.40. Alternative Discount Rate Results

Primary Gas-Fired Cogeneration with Private Ownership
and Electricity Sales to the Pacific Southwest
Levelized Steam Cost (1991\$/1000-lb Steam)

Private After-Tax Real Annual Discount Rate, %	Government Real Annual Discount Rate		
	3.0%	4.0%	5.0%
6.0	11.34	11.51	11.70
7.0	11.35	11.53	11.72
8.0	11.45	11.63	11.82

200-East Plant Upgrade (L-017)
Levelized Steam Cost (1991\$/1000-lb Steam)

NA	13.25	13.66	14.10
----	-------	-------	-------

allowed for recovery of construction capital, including return on investment. The three levelized steam costs were combined into a single overall levelized cost from the government's perspective by applying the government's discount rate to the prospective charges during the three periods. The results of this analysis, summarized in Table G.41, show that three 10-year contracts results in a slightly higher effective levelized steam cost to the government over a 30-year period.

The effect of the assumptions outlined above is that the present value of revenues collected by the private owner for the sum of the three 10-year contracting periods is the same as for a 30-year contract. Thus, the private owner is indifferent as to the contract length. The government is not indifferent to the changes in the charging structure and will end up paying a slightly higher amount for steam in the long run. The sensitivity of the cost of steam is less than \$0.90/1000-lb steam for the coal-fired plant and \$1.30/1000-lb steam for the gas-fired plant.

It is critical to understand a key assumption in this analysis that will be restated. This analysis presumes the government can negotiate a steam charge for each period based on achieving a minimum acceptable rate of return to the private owner over a 30-year period. The rate charged during the first 10-year period is significantly higher than would be charged in a 30-year contract. There is some risk with the 10-year contract that the government could pay the higher initial charge and never see the benefit of reduced charges in later years.

TABLE G.41. Contracting Period Impact on Private Steam Costs

Levelized Costs for Coal-Fired Steam Plant

<u>Period</u>	<u>10-yr Contract (\$/1000 lb steam)</u>	<u>30-yr Contract (\$/1000 lb steam)</u>
Year 1-10	22.91	16.83
Year 11-20	12.58	16.83
Year 21-30	12.69	16.83
Overall	17.69	16.83

Levelized Costs for Gas-Fired Steam Plant

Year 1-10	16.36	14.56
Year 11-20	14.20	14.56
Year 21-30	17.24	14.56
Overall	15.86	14.56

G.14 REFERENCES

American Association of Cost Engineers. 1990. AACE Recommended Practices and Standards, Standard Cost Engineering Terminology. AACE Standard No. 10S-90, American Association of Cost Engineers, Morgantown, West Virginia.

Blazek, C. F., N. R. Baker, and R. R. Tison. 1979. Central Heating - Fossil-Fired Boilers. ANL/CES/TE 79-4, prepared by the Institute of Gas Technology for Argonne National Laboratory, Argonne, Illinois.

Boulay, R. B., et al. 1986. Competitiveness of Small Power Plants Using Ambient Pressure, Air-Blown Gasifiers. EPRI AP-4454, prepared by Gilbert/Commonwealth, Inc. for the Electric Power Research Institute, Palo Alto, California.

Brown, D. R., et al. 1987. An Assessment Methodology for Thermal Energy Storage Evaluation. PNL-6372, Pacific Northwest Laboratory, Richland, Washington.

Brown, D. R., L. L. Fassbender, and A. D. Chockie. 1986. The Value of Solar Thermal Industrial Process Heat. PNL-5629, Pacific Northwest Laboratory, Richland, Washington.

Coffin, B. D. 1981. "Estimating Capital and Operating Costs for Industrial Steam Plants." 7th Energy Systems Guidebook, pp. 122-125. McGraw-Hill Publishing Company, New York.

CRS Sirrine, Inc. 1989. Utilities Study, Twin Cities Campuses. CRS Sirrine, Greenville, South Carolina.

Electric Power Research Institute (EPRI). 1989. Technical Assessment Guide, Electricity Supply-1989. EPRI P-6587-L, Electric Power Research Institute. Palo Alto, California.

Esposito, N.T. 1989. A Comparison of Steam-Injected Gas Turbine and Combined-Cycle Power Plants: Technology Assessment. EPRI GS-6415, prepared by Jersey Central Power and Light Company for the Electric Power Research Institute, Palo Alto, California.

Lippiatt, B. C., and R. T. Ruegg. 1990. Energy Prices and Discount Factors for Life-Cycle Cost Analysis. NISTIR 85-3273-5, U.S. Department of Commerce. Washington, D.C.

Mallik, A. K. 1982. "Computerized Cost Comparison of Industrial Boilers." Cost Engineering 24(5).

Means Company, Inc. 1986a. Building Construction Cost Data 1986. R.S. Means Company, Inc., Kingston, Massachusetts.

Means Company, Inc. 1986b. Means Electrical Cost Data 1986. R.S. Means Company, Inc., Kingston, Massachusetts.

Northwest Power Planning Council. 1989. Financial and Economic Assumptions. 89-21, Northwest Power Planning Council, Portland, Oregon.

Payne, F. W. 1986. Efficient Boiler Operations Sourcebook. The Fairmont Press, Atlanta, Georgia.

Peters, M. S., and K. D. Timmerhaus. 1980. Plant Design and Economics for Chemical Engineers. McGraw-Hill Book Company, New York.

Van Knapp, D. P., et al. 1989. American Jurisprudence, Second Edition. The Lawyers Co-operative Publishing Company, Rochester, New York, and Bancroft-Whitney Company, San Francisco.

Westinghouse Hanford Company. 1990. Conceptual Design Report, Steam System Rehabilitation, Phase II. WHC-SD-L017-CDR-001, prepared by Kaiser Engineers Hanford Company for Westinghouse Hanford Company, Richland, Washington.

DISTRIBUTION

No. of
Copies

No. of
Copies

OFFSITE

12 DOE/Office of Scientific and
Technical Information

J. D. White
Science Applications Int'l
Corp.
1845 Terminal Dr., Suite 202
Richland, WA 99352

T. F. Grant
Human Affairs Research Center
4000 N.E. 41st
Seattle, WA 98105-5428

ONSITE

DOE Richland Field Office

D. L. Sours (10)

21 Westinghouse Hanford Company

R. A. Dutton
C. H. Eccleston
R. H. Engelmann
J. K. Fish (10)
A. D. Gadeken (3)
J. R. Kirkendall
E. M. Koellermeier
R. J. Meyer
G. E. Miller
M. W. Young

23 Pacific Northwest Laboratory

D. R. Brown
K. K. Daellenbach
P. L. Hendrickson
D. C. Kavanaugh
R. W. Reilly
D. L. Shankle
S. A. Smith
S. A. Weakley (10)
Publishing Coordination
Technical Report Files (5)

END

END

**DATE
FILMED**

4 / 02 / 92