DOE/ID/01816--1

AMERICAN ELECTRIC POWER SERVICE CORPORATION

MASTER

FEASIBILITY STUDY

for

UPGRADING THE BYLLESBY & BUCK HYDROELECTRIC PLANTS

NOTICE
PORTIONS OF THIS REPORT ARE ILLEGIBLE. IT
HAS BEEN REDUCED FROM THE BEST AVAILABLE
COPY TO PERMIT THE BROADEST POSSIBLE AVAIL-
ABILITY.

DISCLAIMER

This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

COOPERATIVE AGREEMENT NO.DE-FC07-78ID01816

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

BOFORS
NOHAB

FEASIBILITY STUDY OF UPGRADING BYLLESBY
AND BUCK POWER PLANTS ON THE NEW RIVER
IN THE COMMONWEALTH OF VIRGINIA

CONTRACT NO. C 4772

AMERICAN ELECTRIC POWER SERVICE CORPORATION
2 BROADWAY, NEW YORK, N.Y. 10004

BOFORS-NOHAB
ONE WORLD TRADE CENTER
SUITE 10225, NEW YORK
NEW YORK 10048

NEW YORK
MAY 1979

TABLE OF CONTENTS

<u>CHAPTER</u>	<u>PAGE NO.</u>
S <u>MANAGEMENT ABSTRACT</u>	
1 <u>INTRODUCTION</u>	1
1.1 <u>EXISTING FACILITIES</u>	3
1. DESCRIPTION OF FACILITIES	3
(1) The Byllesby Development	3
(2) The Buck Development	4
(3) Project Operation	5
2. APPRAISAL OF CONDITION	7
(1) The Byllesby Development	7
1. Forebay	7
2. The Dam	8
3. Spillway	8
4. Powerhouse and Generating Equipment	9
(2) The Buck Development	10
1. Forebay	10
2. The Dam	10
3. Spillway	10
4. Powerhouse and Generating Equipment	11

<u>EXHIBITS</u>	<u>EXHIBIT</u>
STATE OF VIRGINIA, LOCATION MAP	A-1
MAP OF BYLLESBY AND BUCK PROJECT	A-2
BYLLESBY, GENERAL PLAN	A-3
BUCK, GENERAL PLAN	A-4

111	<u>PROJECT POWER AND POTENTIAL UPGRADING ALTERNATIVES</u>	13
1.	SUMMARY FIELD TEST AND DEVELOPMENT OF BASE LINE DATA FOR UPGRADING ALTERNATIVES	13
	(1) Datum and Elevations	13
	(2) Water Elevations versus Load	14
	(3) Tailwater	15
	(4) Existing Turbine Efficiency	15
2.	UPGRADING ALTERNATIVES	17
	(1) Replacement of Existing Runners by New Runners of More Efficient Design	17
	(2) Raise the Forebay Elevation at Buck by Three Feet	19
	(3) Install Small Scale Hydropower Unit, Buck Powerhouse	21
	(4) Replace Timber Flashboards at Byllesby and Buck by Gates	25
	(5) New Power Stations with Bulb Turbine Units	27

EXHIBITS

EXHIBIT

MAP OF FIELD TEST LOCATIONS, BYLLESBY	B-1
MAP OF FIELD TEST LOCATIONS, BUCK	B-2
BYLLESBY, OVERALL EFFICIENCY, EXISTING UNITS	B-3
BUCK, OVERALL EFFICIENCY, EXISTING UNITS	B-4
LAYOUT NEW RUNNER	B-5
TURBINE EFFICIENCY WITH NEW RUNNER, BYLLESBY	B-6
OVERALL EFFICIENCY WITH NEW RUNNER, BYLLESBY	B-7
TURBINE EFFICIENCY WITH NEW RUNNER, BUCK	B-8
OVERALL EFFICIENCY WITH NEW RUNNER, BUCK	B-9

EXHIBIT

PERFORMANCE CURVES, BYLLESBY HEAD 40 FEET	B-10
PERFORMANCE CURVES, BYLLESBY HEAD 44 FEET	B-11
PERFORMANCE CURVES, BYLLESBY HEAD 48 FEET	B-12
PERFORMANCE CURVES, BYLLESBY HEAD 52 FEET	B-13
PERFORMANCE CURVES, BYLLESBY HEAD 54 FEET	B-14
PERFORMANCE CURVES, BYLLESBY HEAD 56 FFET	B-15
PERFORMANCE CURVES, BUCK HEAD 30 FEET	B-16
PERFORMANCE CURVES, BUCK HEAD 36 FEET	B-11
PERFORMANCE CURVES, BUCK HEAD 40 FEET	B-18
PERFORMANCE CURVES, BUCK HEAD 42.5 FEET	B-19
PERFORMANCE CURVES, BUCK HEAD 45 FEET	B-20
LAYOUT SMALL SCALE HYDRO POWER UNIT	B-21
FLOW DURATION CURVE	B-22
LAYOUT PELICAN GATES, BUCK	B-23
LAYOUT PELICAN GATES, ALTERNATIVE, BUCK	B-24
LAYOUT PELICAN GATES, BYLLESBY	B-25
PROFILE MODEL RUNNERS	B-26
HILL DIAGRAM STANDARD TURBINE MODEL	B-27
EFFICIENCY RESULTS TEST RUNNER	B-28

TABLES

New River - Duration Table of Daily Discharges, Period 1931-1973	1
New River - Average Flow Duration Statistics, Period 1931-1973	2
New River - Annual Maximum Peak Stages and Discharges	3
Summary Feasibility Analysis	4 p. 39

PAGE NO.IV INITIAL ANALYSIS OF SAFETY FACTORS CONCERNING
PERTINENT UPGRADING ALTERNATIVES

1. STABILITY ANALYSIS	26
(1) Description	28
(2) Analysis	29
(3) Results and Recommendations	31
2. <u>HYDRAULIC EFFECTS ON THE SPILLWAY</u>	32
(1) Analysis	33
(2) Results and Recommendations	34

EXHIBITSEXHIBIT

STABILITY ANALYSIS SPILLWAY SECTION, BUCK	C-1
FORCES AND EQUATIONS, ANALYSIS	C-2
SIX HOUR RUN OFF HYDROGRAPH - NEW RIVER	C-3
HYDROGRAPH COMPUTATION	C-4
PRESENT OPERATION BUCK SPILLWAY, 1/2 PMF	C-5
OPERATION BUCK SPILLWAY (RAISED 3 FEET)	C-6
FLOOD FREQUENCY COMPUTATIONS	C-7
FLOOD FREQUENCY CURVE	C-8

PAGE NO.V ECONOMIC FEASIBILITY ANALYSIS AND RECOMMENDED
ALTERNATIVES

1. ALTERNATIVES SELECTED FOR ANALYSIS	36
(1) Byllesby	37
(2) Buck	37
2. ANALYSIS	40
(1) Capital Cost per Installed KW	42

	<u>PAGE NO.</u>
(2) Cost per Installed KWH	42
(3) Return on Investment	43
3. RECOMMENDED ALTERNATIVES	44
VI <u>NECESSARY REGULATORY REQUIREMENTS</u>	47
VII <u>INITIAL ASSESSMENT OF ENVIRONMENTAL IMPACT AND SOCIO ECONOMIC FACTORS</u>	50

APPENDICES

- A. NEW POWER STATIONS WITH BULB UNITS
- B. UPGRADING ALTERNATIVES AND COST ESTIMATES FOR BASIC ALTERNATIVES
- C. FEASIBILITY ANALYSIS COMPUTATION AND COMPUTER PRINT-OUTS

MANAGEMENT ABSTRACT

MANAGEMENT ABSTRACT

This study was performed to investigate and determine the feasibility of upgrading alternatives of the Byllesby and Buck hydroelectric developments located on the New River in the State of Virginia. Both plants are run of the river operations, 66 years old and generate an average annual energy of 111,5 GWH.

- The plants are well maintained and upgrading is possible and feasible according to the assumptions defined in this report. At the time of the proposal for this study, it was assumed that the present equipment should be replaced by Bofors-Nohab standard small scale hydro generating units. Subsequent investigations and studies, however, indicated that from an economic-engineering point of view, the plants could be upgraded, by modernizing the hydraulic and generating equipment and by reducing head loss conditions.
- These considerations led to the recommendations to replace the existing runners at Byllesby and Buck, by new runners of more efficient hydraulic design, draft tube and wicket gate modifications and rewinding of the generators to increase both the plant capacity and annual power generation.
 - Capacity increase total 3.8 MW
 - Annual generation increase 20,201,000 KWH

- Additional potential for capacity and generation increase exists by installing a standard small scale hydro unit at Buck. This potential should be reviewed, the recommendations reflect this point of view.
- According to the assumptions that the present plant could continue to generate the average annual KWH for 15 years and that the modifications would extend the life of the project by 40 years; the capital cost of the recommended improvements to install the new runners, modify the equipment and carry out the required civil engineering work and the associated benefit-cost ratios would be:
 - Capital cost \$6.1 million
 - Benefit cost ratio 2.32
- The upgrading alternatives could be carried out in less than two years, as indicated by the recommended engineering and construction schedule, contained in Chapter V of this report.

Numerous other alternatives were investigated during the course of this study, including to replace the present plants by completely new plants and dams, powered by bulb turbine units. Feasibility analysis in terms of economic and improved power generation, and appraisal of present condition indicated that these alternatives could not be recommended.

The implementation of the recommended alternatives could be carried out with a minimum of production losses, by having the new runners

and gates ready for installation during the low water season and installing the modified installations in sequence.

CHAPTER I
INTRODUCTION

CHAPTER I

INTRODUCTION

The purpose of this document is to report on the feasibility assessment study performed for American Electric Power Service Corporation, Contract No. C-4772, concerning the upgrading potential of the Byllesby and Buck hydropower plants which are located in the State of Virginia. This study was proposed in March, 1978 to participate in the PRDA ET-78-D-07-1706 program. Bofors-Nohab served as general consultant to AEP for this study.

The study concerned the upgrading potential of two developments, Byllesby and Buck, which are located on the New River and are run of the river operations. They are managed by Appalachian Power Company, who, from an operating point of view consider the two developments one project. The developments date from 1913, the equipment has in general operated reliably over the past, however, opportunity for improvements exist.

This report has been prepared as a joint effort by Bofors-Nohab and American Electric Power Service Corporation. The report has been organized as follows:

Chapter I - is this introduction.

Chapter II - describes the existing facilities and contains an appraisal of the hydroelectric equipment, dam, powerhouse and spillway.

Chapter III

- deals with the project power, identification of potential upgrading and the underlying engineering considerations.

Chapter IV

- represents an initial assessment of safety factors of critical alternatives and their engineering considerations.

Chapter V

- summarizes the possible alternatives; it contains an analysis of these alternatives and recommends a potentially feasible combination of upgrading activities.

Chapter VI and VII

- outline various regulatory requirements and environmental issues, respectively.

Bofors-Nohab acknowledges the excellent cooperation and assistance provided by personnel from American Electric Power Service Corporation and the Appalachian Power Company for its part in this challenging assignment.

CHAPTER II
EXISTING FACILITIES

CHAPTER II

EXISTING FACILITIES

This chapter describes the existing hydroelectric facilities of the Byllesby and Buck project which are covered by major license No. 2514, issued by FERC on April 3, 1978. The facilities were constructed in 1912 by the New River Power Company and sold in 1924 to the New River Development Company. Appalachian Power Company of Roanoke, Virginia acquired the project in 1926.

The descriptions and evaluations summarized in this chapter are based on information obtained from American Electric Power Service Corporation, the Appalachian Power Company, special studies, observations and on-site visits.

1. DESCRIPTION OF FACILITIES

The project is located on the New River in the vicinity of Galax and Austinville, Carroll County, Virginia. The location is shown on Exhibits A-1 and A-2. The project consists of two separate hydroelectric developments. The Byllesby development is located about four miles upstream from the Buck development, which in turn is located about five miles upstream from the U.S. Ivanhoe Gaging Station No. 03165500.

(1) The Byllesby Development

The Byllesby development is shown on Exhibit A-3. It includes a concrete dam with an integral powerhouse, a spillway and a reservoir.

The main dam, 528 feet, consists of six spans equipped with six spans of Tainter gates and nine spans of flashboards. Two trash sluices separate the dam from the non-overflow section which contains the powerhouse and the intakes.

The powerhouse contains the following main equipment.

- . Four Turbines - I.P. Morris 1913, 6000 HP units, 116 EPM, design head 49 feet.
- . Four Generators - General Electric Company 1913, 5,400 kw, Type ATB.
- . Various auxiliary equipment including two Francis turbine driven excitation units.

The spillway extends about 180 feet across a channel which discharges into the river below the powerhouse. The spillway consists of six spans of flashboards.

The reservoir has a surface area of about 260 acres and a volume of approximately 2,060 acre-feet. The drainage area at the site is 1,310 square miles.

(2) The Buck Development

The Buck development is shown on Exhibit A-4. It includes a concrete dam with an integral powerhouse, a separate spillway and reservoir.

The main dam located in the channel north of Mountain Island, consists of a 352 foot long non-overflow concrete gravity abutment section containing trash sluices and the powerhouse with intakes.

The powerhouse contains the following main equipment.

- . Three turbines - I.P. Morris 1913, 3500 HP 97 RPM, design head 34 feet.
- . Three Generators - General Electric Company 1913 2,835 kw. Type ATB.
- . Various auxiliary equipment including one Francis driven excitation unit and one motor-generator excitation unit, which operates from the grid.

The spillway is located upstream from the main dam, upstream at the entrance to the south channel. It consists of six tainter gates and twenty-one flashboard sections.

The reservoir covers approximately 70 acres and has a volume of about 640 acre-feet. The drainage area at the site is 1,320 square miles.

(3) Project Operation

Appalachian Power Company operates the project mainly by remote control, by means of a supervisory system, from Roanoke, Virginia. The project produces peaking power, which is fed into the inter-connected power system of the company and its affiliated companies. The project is operated at or near its full capacity to fit the

system load curve.

Since the Byllesby and Buck Developments are located close together and because the Buck reservoir is small and depends on the discharge of Byllesby, the project is considered as a single plant from a loading and operation procedure point of view. As a result of peaking operations there are rapid fluctuations of the power pool levels. The Buck development currently discharges a minimum flow of 310 cfs at all times to satisfy downstream requirements. The Byllesby flow may, as required, be completely stopped to allow the Buck reservoir to fill.

The average production in kilowatt hours per year has been based upon operating reports, from 1967 to and including 1976.

<u>YEAR</u>	BYLLESBY	BUCK
	<u>MWH</u>	<u>MWH</u>
1967	59045	38883
1968	55136	36347
1969	58592	37939
1970	50864	36357
1971	72986	47500
1972	74464	51217
1973	60291	52420
1974	82248	56232
1975	78384	52917
1976	66460	45608
<u>Arithmetic mean</u>	65847	45573
<u>kwh per year</u>	65,900,000	45,600,000

The kwh production tabulated above has been influenced by two main factors; wet years and the installation of solid state excitation, operated from the grid, at Byllesby. The latter reduced downtime due to clogging of the exciter intakes.

For the purpose of this study the average calculated values for annual kilowatt hour production have been assumed to be representative for base line data.

2. APPRAISAL OF CONDITION

Each development, Byllesby and Buck, is appraised separately in this section and covers the forebay, dam, spillway, and powerhouse generating equipment. In addition, an overall view of the total project is dealt with.

(1) The Byllesby Development

1. Forebay

The forebay at Byllesby has for some years been subjected to considerable silting in front of the spillway and extending several miles upstream the river. The resulting loss of pondage has been noticeable. It was expected that the configuration of the silt with respect to the intakes would result in head losses which would negatively influence turbine performance. A special field study was undertaken by the Appalachian Power Company to ascertain the effects of this condition. The results of this study did not indicate conclusively that appreciable head losses were caused by the silt.

The natural flow of the river is towards the dam, in which the tainter gates are situated. When flow conditions require that the tainter gates be opened and the flashboards are still in place on the spillway, eddies and lower speed of the water will cause sediment to settle in front of the spillway. If this situation continues over a longer period of time, the silting will affect the hydraulic conditions of the intakes and further reduce reservoir pondage.

2. The Dam

Some erosion and spalling is in evidence on the abutments of the dam. A program has been initiated by AEP to correct this situation, as part of their normal maintenance procedures. Recent studies conducted by AEP indicate that the dam and structure are sound.

3. Spillway

Spilling at Byllesby can take place over the main dam and through the spillway. At maximum pool elevation of 2082.5 feet the spilling capacity is 93800 cfs. The limit of spilling capacity is about 120,000 cfs with all tainter gates open and all timber flashboards removed. Spilling in excess of 130,000 cfs would overtop the powerhouse deck, which elevation is 2085.0 feet. From the Log Pearson type III computations the probability of exceeding the maximum discharge capacity has a recurrence interval more than 200 years.

Flashboards are removed at flows in excess of 24000 cfs.

When the flow returns to normal the forebay level stays at

the low level where the flashboards were removed. During this period of time, until the flashboards are replaced, the turbines are operated at a considerably lower head. The next chapter will deal in more detail with these conditions, with respect to energy losses.

4. Powerhouse and Generating Equipment

The powerhouse and generating equipment, although old, are in general in good state of repair and the generating equipment operates reliably.

Two Francis turbine generator units were used until recently for excitation. These units are now out of operation.

The equipment was damaged during the 1940 flood when the river discharge was in excess of 150,000 cfs. Since then the plant has been rehabilitated and the generators rewound.

The turbine units at Byllesby operate at a normal head of 54 feet. A special field test reported on December 18, 1978 indicated that Byllesby's turbine units yield 3.53 kw per cfs, which is less than the manufacturer's curve information, which shows a yield of 3.83 per cfs. This condition is attributed to the age and type of the equipment.

Since Byllesby is operated in conjunction with Buck, and Byllesby has four turbine units and Buck has three identical turbine units, Byllesby discharges more water than Buck can handle. To obtain a relative balance, Byllesby's turbines are operated at a maximum gate opening of 85 per cent.

(2) The Buck Development

1. Forebay

The forebay at Buck has a normal pool elevation of 2002 feet. The average tailwater elevation at Byllesby is 2024.5 feet. Development of the remaining 20 feet of head is not considered feasible because it would require relocation of the Norfolk and Western Railroad. There is, however, some potential for increasing the head. This issue is covered in Chapter III.

2. The Dam

The dam at Buck is classified according to the Corps of Engineers "Recommended Guidelines for Safety Inspection of Dams" as small in size and significant in hazard potential. AEP has undertaken a study to evaluate the condition of the dam, with the purpose to improve its condition. This study is in progress and will be carried out during 1979.

3. The Spillway

Spilling at Buck takes place entirely through the spillway. The twenty-four sections of the spillway have a spilling capacity of 101,300 cfs at a maximum pool level of 2004.5 feet. The limit of spilling capacity with all Tainter Gates open and all flashboards removed is about 150,000 cfs. Spilling in excess of 150,000 cfs would overtop the powerhouse

deck, which elevation is 2007 feet. The probability of exceeding the maximum discharge has been computed to have a recurrence interval of 200 years.

As at Byllesby, Buck's flashboards are removed at flows in excess of 24000 cfs. The next chapter will also deal with the energy losses, related to this condition.

4. Powerhouse and Generating Equipment

The powerhouse at Buck has been subjected to considerable damage during the 1940 flood. Substantial repairs were made after the flooding. The present condition of the powerhouse will also be evaluated in the before mentioned AEP study of the dam.

The three turbine generating units are, in general, in good state of repair and operate reliably. The units operate at a normal operating head of 41 feet. The same test was reported for Buck as at Byllesby in December, 1978. Results of this test indicated that Buck's unit yield 2.60 kw per cfs rather than the 2.80 kw per cfs which was expected from the manufacturer's curve. This condition is also attributed to the age and type of equipment. Buck's turbines are operated at 100 per cent gate opening.

There were two Francis turbine generator excitation units. One is still in place, the other was partially dismantled and concrete was cast over this unit after the 1940 flood. The remaining unit is not operated; excitation current is obtained from a motor generator set.

* * * *

In general, the Byllesby and Buck project is in good condition and can probably continue to operate as at present for some time to come. However, upgrading potential is available, as will be demonstrated in the next chapters.

CHAPTER II
EXHIBITS

STATE OF VIRGINIA
LOCATION MAP

LOCATION OF BYLLESBY AND DUCK
DAMSITES ENCIRCLED

EXHIBIT A-2

IVANHOE GAGING STATION

BUCK POWER STATION

BYLLESBY POWER STATION

NATIONAL
FOREST

FEASIBILITY ASSESSMENT STUDY FOR THE
BULLSBY HYDRO PROJECT
GENERAL PLAN, DAM AND DAMS

B. BORSON

[illegible]

CHAPTER III
PROJECT POWER AND
UPGRADING ALTERNATIVES

CHAPTER III

PROJECT POWER AND POTENTIAL UPGRADING ALTERNATIVES

This chapter deals with the power and energy that can be generated at the Byllesby and Buck project under a number of upgrading alternatives.

Basic Data

The following basic data were used in evaluating the power potential at the project.

- Normal operating pool levels of each development.
- New River - Duration table of daily discharges over the period from 1931 to and including 1973. (Table 1)
- New River - Average flow statistics. (Table 2)
- New River - Annual maximum peak stages and discharges. (Table 3)
- Summary and comments of field tests, performed by APCO and reported in 1978. (Section 1)

1. SUMMARY FIELD TEST AND DEVELOPMENT OF BASE LINE DATA FOR UPGRADING ALTERNATIVES

(1) Datum and Elevations

The field test indicated that the datum used by APCO was eight feet higher than the USGS datum. All elevations were subsequently adjusted to the "Test Datum", which is APCO's datum minus eight feet for each plant. The "Test datum" should now be the same as the USGS datum. The accuracy is assumed to be within 2 feet. At the field tests the runner centerline elevations (distributor CL) and main structural elevations as well as the elevation of railroad tracks at Byllesby and Buck were determined. All readings were

tied to the USGS datum. The result can be found in the tabulation below:

Runner Centerline	Byllesby	Buck
Concrete surface of powerhouse	2085.00	2007.00
Spillway crest - average	2070.76	1994.78
Plant floor - average	2047.82	1986.38
Nominal full pool (Max. limit at the tests)	2079.10	2003.40
Railroad track	2087.27	2011.54
Top of rail		

(2) Water Elevations Versus Load

The tests were directed to study the variations of forebay and tail water elevations as a function of load. It was expected that the effect at Byllesby's forebay was considerable due to the large deposit of silt in front of the turbine intakes.

In order to study the entire forebay a large number of measuring points were selected on the forebay of Byllesby as well as of Buck.

The forebay elevation readings at different turbine loads showed, at Byllesby as well as at Buck, a relatively slight variation of the forebay from one measuring point to another. This is to some extent surprising, especially at Byllesby, where the above mentioned silt bank, was assumed to have caused local flow velocity peaks with a significant head losses. As no large variations were observed as far as the flow conditions were

concerned, it was concluded that the flow passages upstream of the turbine intakes, at both Byllesby and Buck, have sufficient dimensions for their respective discharges.

(3) Tailwater

The readings of the tailwater showed an increasing tailwater elevation with increasing discharge. The specific increase appeared to be approximately the same at Byllesby as well as at Buck, one foot increase per turbine unit at full load. Maps of field test locations are shown on Exhibits B-1 and B-2.

(4) Existing Turbine Efficiency

The efficiency diagrams of the existing francis turbine units (shown on Exhibits B-3 and B-4) were computed from the manufacturers curves. A field test performed by APCO, during the period 1972 through 1977, to check the manufacturers curves, indicated that a difference existed. The test was performed by means of continuous discharge readings at the Ivanhoe Gaging station and corresponding readings of the generator outputs of Byllesby and Buck.

The manufacturers curves show as an average:

Byllesby 3,82 KW per cfs

Buck 2,80 KW per cfs

Twelve check reading periods from 1972 through 1977 show as an average:

Byllesby 3,53 KW per cfs

Buck 2,60 KW per cfs

Coefficients used to correct the efficiencies were for:

$$\text{Byllesby} \quad \frac{3.53}{3.82} = .924$$

$$\text{Buck} \quad \frac{2.60}{2.80} = .929$$

The hill diagrams shown on Exhibits B-3 and B-4 were computed as follows:

$$\eta \% = \frac{P \cdot 100}{g.H.0,3048.Q (0,3048)^3}$$

where

η = percent overall efficiency

P = output in KW (KW is a metric unit)

g = gravity coefficient (9,815 m/s²)

H = head, in feet

0,3048 = conversion of feet to meter

Q = discharge in cfs

(0,3048)³ = conversion of cfs to m³/s

$$\text{thus; } \eta \% = \frac{100 P}{g.H. (0,3048)^4} \quad (Q = \text{one cfs})$$

For a number of equally distributed KW-values first the efficiency (%) and then the discharge (cfs) was calculated at each of the specified heads. For each head the efficiency

was plotted versus discharge. Before plotting the efficiencies were multiplied by the correction coefficients mentioned above.

- From the efficiency/discharge diagrams, numerically equal efficiencies were plotted on the hill curves head versus discharge.
- The 100 per cent gate opening curve indicated in the diagrams was plotted from empirical data supplied by APCO. The information developed was used as base line data for developing the following alternatives.

2. UPGRADING ALTERNATIVES

(1) Replacement of Existing Runners by New Runners of More Efficient Design

In considering this alternative, it is intended to keep the existing shafts, speedrings, distributors, head covers, draft tubes, etc. However, in order to increase the wicket gate opening the wicket gate trailing edge will need to be cut off. A layout of the new runner is shown on Exhibit B-5.

Due to a smaller discharge diameter of the new runner, it will be necessary to install a plate cone immediately downstream from the runner band.

The turbine efficiency characteristic of the new runner is shown on Exhibits B-6, B-7, B-8, and B-9. The generator efficiency was estimated at 96 per cent.

Performance curves at various heads are shown on Exhibits B-10 through B-20.

$$Q_{11} = \frac{Q_m}{(D_m)^2 \sqrt{H_m}} m^3 / s$$

$$n_{11} = n_m \frac{D_m}{\sqrt{H_m}} \text{ rpm}$$

where the prefix m refers to model test data and the prefix 11 to model test data converted to one meter runner diameter and one meter head.

The hill diagram of the new runner is designed on basis of data of the above mentioned model hill diagram. For each of the even heads of Byllesby and Buck a unit speed in the n_{11} - system can be calculated as follows:

$$\text{Byllesby: } n_{11} = 116,1 \frac{2,700}{\sqrt{H}} \text{ rpm}$$

$$\text{Buck: } n_{11} = 97,3 \frac{2,700}{\sqrt{H}} \text{ rpm}$$

where - 116,1 and 97,3 are the synchronous speeds of Byllesby and Buck respectively.

- 2,700 is the runner throat diameter in meters.

- H is the head in meter.

The prototype turbine efficiency is higher than that of the model due to reduced friction losses caused by the increased head and increased runner diameter. The efficiency scale effect follows the rates between the function of Reynolds numbers of the model and of the prototype.

$$\frac{1 - \eta_p}{1 - \eta_m} = 0,3 + 0,7 \left[\frac{D_m \nu_p}{D_p \nu_m} \sqrt{\frac{H_m}{H_p}} \right]^{1/5}$$

ν_p and ν_m = kinematic viscosity of the prototype and the model discharge respectively

where the prefix m refers to model and the prefix p to prototype.

The efficiency increment is calculated at the peak efficiency of each model curve and then added as a constant amount to all other points on the curve.

The discharge Q_{11} of the model hill diagram can be converted to prototype discharge Q_p as follows:

$$Q_p = Q_{11} (2,7000)^2 \sqrt{H_p}$$

where 2,700 m is the runner diameter and H is the head.

The diagrams comparing at constant head the efficiency characteristics of the "new and the old turbines" are extractions from the hill diagrams.

(2) Raise the Forebay Elevation at Buck by Three Feet

With consideration to the elevation of the railroad tracks, running close to forebay, it is possible to raise the maximum forebay elevation three feet and thus obtain a valuable increase of the head. The new normal pool elevation will be about 2006 feet. As the top of the rail is located on 2011,54' there will be difference in height of approximately 5 feet.

The normal maximum head would be increased from 40 feet to 43 feet. Considering 100% gate opening it is possible to calculate a new maximum output of the unit. Two cases are possible, either with the existing turbine or with a turbine upgraded by means of a new runner.

The following tabulation shows data and results.

	Turbine	Head feet	Gate %	Overall eff. %	Discharge cfs	Output kw
1	Existing	40	100	74,5	1170	2952
2	Existing	43	100	74,5	1215	3295
3	New	40	100	84,8	1170	3360
4	New	43	100	84,0	1215	3715

As can be seen the biggest increase in output is achieved with a new runner at 43 feet head. Compared with the existing turbine at 40 feet the increase in generator output amounts to $3715 - 2952 = 763$ KW per unit.

An increase of the head results in a corresponding increase of the discharge. An increase of the turbine discharge in Buck reduces to some extent the present unbalance between Byllesby and Buck.

A three feet increase of the head improves the production of kilowatthours per year. The improvement factor is the relationship between the previous maximum output at 40 feet head and the new maximum output at 43 feet head. Two cases are possible either with existing runners or with new runners.

In both cases the percentual change should be based on output of existing runner at 40 feet head.

1. Existing runner:

$$\text{factor K} = \frac{3295}{2952} = 1.116$$

2. New runner:

$$\text{factor K} = \frac{3715}{2952} = 1.258$$

Normal average KWh-production amounts to 45.6000.000 kilowatt-hours per year. The probable production at 43 feet head should amount to:

Existing runner:

$$E = 1.116 \cdot 45,6000,000 = 50,890,000 \text{ KWh per year}$$

New runner:

$$E = 1.258 \cdot 45,6000,000 = 57,360,000 \text{ KWh per year}$$

A three feet elevated forebay requires a corresponding vertical extension of powerhouse intake deck as well as of all dam constructions and spillway crests.

(3) Install Small Scale Hydropower Unit, Buck Powerhouse

In Byllesby and Buck power plants are together seven identical turbines installed. There are four units in Byllesby at 56 feet rated head and three units in Buck at 40 feet rated head. The total discharge capacity of the turbines in Byllesby is probably 20 to 30% larger than that of the turbines in Buck. At normal head conditions 80 to 85% gate in Byllesby corresponds to 100%

gate in Buck. Thus, 100% gate in Byllesby means spilling water in Buck.

To improve the flow balance a small scale hydro power unit could be installed. It could be situated in place of the unused exciter turbine.

Exhibit B-21 shows the proposed arrangement of the small scale hydro unit in the exciter turbine pit. As big a unit as possible should be chosen. The proposed turbine has a runner diameter of 1700 mm. The discharge comes to the turbine through a penstock having a diameter of 2400 mm and a length of approximately 15 m (50 feet) between the turbine and the forebay side of the powerhouse. The existing exciter turbine penstock cannot be used because it is too small diameter, a new penstock should be arranged.

Technical features and data of the proposed unit are:

- Unit with a fixed blade turbine runner and a fixed vane distributor.
- The unit is intended for on-off operation at approximately constant output.
- The electrical equipment is of induction type taking its excitation from the grid.
- The unit does not have a speed governor but the speed of the unit is kept constant by means of the frequency of the network.
- Start and stop of the unit is automatically controlled by means of a float or a transmitter on the forebay acting on the butterfly valve, i.e. the elevation of the forebay governs the operation of the unit.

- The unit would operate when the other turbines operate at full load. The tail water will raise about 3 feet. The average head of the unit would be 38 feet.

Turbine runner diameter = 1700 mm

Generator speed, asynchronous = 734 rpm

Turbine speed = 327 rpm

Gearbox ratio = 1:2,24

Discharge at 38 feet head = $14,8 \text{ m}^3 / \text{s} = 523 \text{ cfs}$

Overall efficiency, i.e. turbine, gearbox and generator = 84%

Generator output at 38 feet head = 1410 KW

The minimum number of hours per year there is discharge enough for operation of the small scale hydro unit can be estimated by means of the flow duration curve of the New River which is shown on Exhibit B-22. The three units in Buck have together an average discharge of 3000 cfs. The flow duration curve shows that more discharge than 3000 cfs is available 16% of the time.

$$.16 \times 8760 = 1400 \text{ hours}$$

The minimum number of kilowatthours per year is:

$$1410 \cdot 1400 = \underline{1,974,000} \text{ KWh/year}$$

The calculation of the technical data for the proposed small scale hydro unit is based on the model test hill diagram 51 87225 (Exhibit B-28). The fixed on-off operational point can be plotted in the hill diagram after calculation of the n_{11} and the Q_{11} , i.e. the one meter speed and discharge.

$$n_{11} = 327 \frac{1.700}{\sqrt{38 \cdot 0.3048}} = 163.3 \text{ rpm}$$

$$Q_{11} = \frac{14.8}{1.7^2 \sqrt{38 \cdot 0.3048}} = 1.50 \text{ m}^3/\text{s}$$

where 327 is the turbine speed

1.70 is the runner diameter

38 is the head in feet

0.3048 is the factor for conversion from feet to meter

14.8 is the discharge in m^3/s

The plotted point shows a cavitation number of 0.77. The cavitation number is defined according to Thoma,

$$\sigma = \frac{H_B - H_w - H_s}{H}$$

where σ = cavitation coefficient

H_B = barometric pressure expressed in meter water column

H_w = water vapor pressure in meters

H_s = turbine draft head in meters

H = effective head in meters

$H_B - H_w$ can be assumed to 9.8 meter

$$\text{thus } \sigma = \frac{9.8 - H_s}{H}$$

$$\text{and } H_s = 9.8 - \sigma \cdot H$$

With $\sigma = 0.77$ and $H = 38$ feet (11.58 m) the required H_s amounts to 0.88 m. As shown on Exhibit B-22 the setting

of the turbine runner is chosen to 0.8 m above TWL, i.e. there is a slight safety margin of $0.88 - 0.80 = 0.08$ m against cavitation.

(4) Replace Timber Flashboards at Byllesby and Buck by Gates

The flashboards are used at extremely high flows to pass water in excess of plant discharge capacity. Normally this situation occurs only at flows of 24000 cfs and more. The boards are knocked out and released from the dam. Once the flow returns to normal the forebay elevation stays at the low level where the boards were knocked. During the period of time until the boards are restored the turbines are operated at a considerably reduced head which means a loss of kilowatthours.

A probable average loss of kilowatthours per year is calculated as follows:

A six-years period, 1973 - 1978, has been evaluated (APCO-report). During the period the flashboards have been knocked:

Byllesby - 4 times

Buck - 8 times

The following tabulation specifies what has happened to the flashboards in Byllesby and Buck during the six-years period as well as a calculated figure for the KWh-loss at each occasion.

	<u>Byllesby</u>	<u>Buck</u>
1973 March/April	Boards out 25 days Loss during period 4,645,000 KWh	Boards out 10 days Loss during period 500,000 KWh
1973	Boards out 12 days Loss during period 1,698,000 KWh	Boards out 9 days Loss during period 720,000 KWh
1974 April	No boards knocked - -	Boards out 5 days Loss during period 136,000 KWh
1975 March/April	No boards knocked - -	Boards out 17 days Loss during period 385,000 KWh
1975 Oct/Nov	No boards knocked	Boards out 4 days
1976 June/July	No boards knocked - -	Boards out 13 days Loss during period 936,000 KWh
1977 Nov/Dec	Boards out 40 days Loss during period 2,4000,000 KWh	Boards out 55 days Loss during period 5,000,000 KWh
1978 Jan/March	Boards out 55 days Loss during period 7.760.000	Boards out 55 days Loss during period 3.6000.000 KWh

The total loss in kilowatthours during the six-years period is:

Byllesby: 16,503,000 KWh

Buck : 7,957,000 KWh

Average loss per year:

Byllesby: $16,503,000/6 = \underline{2.750.000 \text{ KWh}}$

Buck : $7,957,000/6 = \underline{1.326.000 \text{ KWh}}$

If movable gates were installed instead of the flashboards the KWh-loss could be considerably decreased. The period of time with reduced head could be kept at a minimum when gates are raised as soon as the excess water has passed the dam.

Exhibits B-23, B-24 and B-25 represent a layout for pelican gate application.

(5) New Power Stations with Bulb Turbine Units

In order to cover the whole spectrum of alternatives, completely new power stations were looked into to replace the existing Byllesby and Buck Project. Since this alternative is not considered feasible at this time it is not further covered in this chapter. For the sake of completeness, however, it is summarized in Appendix A.

CHAPTER III
EXHIBITS

[illegible]

TOLLHATTEN SWEDEN

BOFORS
NOHAB

BYLESBY POWER STATION
OVERALL EFFICIENCY OF EXISTING UNITS

5407-0200

FEBR. 1979

She

POSSIBLE HEAD INCREASE BY 5 FEET
EXISTING HEAD RANGE

100% GATE OPENING.

EXHIBIT B-4

OVERALL EFFICIENCY PERCENT

BOFORS
NOHAB

BUCK POWER STATION
OVERALL EFFICIENCY OF EXISTING UNITS

5407 - 0200
FEBR. 1939

Project Name	Assessment	Revision	Material	Unapproved	Notes
RELIABILITY ASSESSMENT STUDY	1.2	1			
300000 AND DUCK HYDRO PLANT					
FRANCIS RUNNER OF NEW DESIGN					
DATE: 10/1/79					
BY: J. B. BOFORS					
37. 87396

EXHIBIT B-6

100% GATE
OPENING

DISCHARGE cfs

BOFORS

OVERALL EFFICIENCY WITH NEW RUNNER
FEASIBILITY STUDY
BY LESBY HYDRO PLANT

5407 - 0200

Shu

FEBR. 1979

EXHIBIT B-8

BOFORS
NORAB
TROLLHATTAN SWEDEN

BUCK HYDRO PLANT
FEASIBILITY STUDY
TURBINE EFFICIENCY WITH NEW RUNNER

5407-0209
JMS
FEBR. 1979

BOFORS
NOHAB

BUCK HYDRO PLANT
FEASIBILITY STUDY
OVERALL EFFICIENCY WITH NEW RUNNER

5407-0200
5/2/5
FEAR. 1979

TROLLHATTAN SWEDEN

EXHIBIT B-10

P = PROPOSED NEW TURBINE RUNNER
E = EXISTING INSTALLATION

EFFICIENCY PERCENT

OUTPUT KILOWATTS

90

80

70

60

50

0

500

1000

1500

6000

5000

4000

3000

2000

1000

0

100% GATE

TURBINE EFFICIENCY (P)
OVERALL EFFICIENCY (P)

GENERATOR OUTPUT (P)
GENERATOR OUTPUT (E)

OVERALL EFFICIENCY (E)

DISCHARGE CFS

BYLLESBY HYDRO PLANT
FEASIBILITY STUDY
HEAD = 40 FEET SPEED 116.1 RPM
PERFORMANCE CURVES

5407-0200
FEBR 1979
ST. 87381

EXHIBIT B-11

P = PROPOSED NEW TURBINE RUNNER
E = EXISTING INSTALLATION

EFFICIENCY PERCENT

OUTPUT KILOWATTS

70

60

50

0

500

1000

1500

6000

5000

4000

3000

2000

1000

0

OVERALL EFFICIENCY (E)

GENERATOR OUTPUT (E)

GENERATOR OUTPUT (P)

OVERALL EFFICIENCY (P)

TURBINE EFFICIENCY (P)

100% GATE

DISCHARGE CFS

BYLLESBY HYDRO PLANT
FEASIBILITY STUDY
HEAD 44 FEET SPEED 116.1 RPM
PERFORMANCE CURVES

5407-0200
FEBR. 1979
ST. 87382

BYLLESBY HYDRO PLANT
FEASIBILITY STUDY
HEAD 48 FEET SPEED 116.1 RPM
PERFORMANCE CURVES

5407-0200
FEBR. 1979
ST. 87383

BYLLESBY HYDRO PLANT
FEASIBILITY STUDY
HEAD = 52 FEET SPEED 116.1 RPM.
PERFORMANCE CURVES

5407-0200
FEBR 1979
ST. 87384

BYLLESBY HYDRO PLANT
FEASIBILITY STUDY
HEAD = 54 FEET SPEED = 116.1 RPM.
PERFORMANCE CURVES

5407-0200
FEBR. 1979
ST. 87385

BYLLESBY HYDRO PLANT
FEASIBILITY STUDY
HEAD = 56 FEET SPEED 116.1 RPM.
PERFORMANCE CURVES

5407-0200
5/11
FEBR. 1979
ST 87386

BUCK HYDRO PLANT
FEASIBILITY STUDY
HEAD = 30 FEET SPEED 97.3 RPM.
PERFORMANCE CURVES

5407-0200
5th
FEBR. 1979
ST. 87390

BUCK HYDRO PLANT
 FEASIBILITY STUDY
 HEAD 36 FEET SPEED = 97.3 RPM.
 PERFORMANCE CURVES

5407-0200
 FEBR. 1979
 ST. 87391

BUCK HYDRO PLANT
FEASIBILITY STUDY
HEAD = 40 FEET SPEED = 97.3 RPM.
PERFORMANCE CURVES

5407-0200
FEBR. 1979
ST. 87392

NOHAB
TROLLHÄTTAN
SWEDEN

DUCK HYDRO PLANT
FEASIBILITY STUDY
HEAD = 42.5 FEET SPEED = 97.3 RPM
PERFORMANCE CURVES

5407-0200
5th
FEBR. 1979
ST. 87393

BUCK HYDRO PLANT
FEASIBILITY STUDY
HEAD = 45 FEET SPEED = 97.3 RPM.
PERFORMANCE CURVES

5407-0200
9th
FEBR. 1979
ST. 87394

EXHIBIT B21

EXHIBIT B-22

TROLLHATTAN
SWEDEN

NEW RIVER VIRGINIA
FLOW DURATION AT IVANHOE
GAGING STATION
DAILY DATA DURING PERIOD 1931-1973

5407-0200
FEB. 1979
GT 83345

Change	Zone	Description of Change	Date	Original
△				

EXHIBIT B-23

SECTION E-E
REF. DRAW. NO.

Drawing No. Order No.		Revision Date		Title Description		Material Material		Location Location		Date Date		Sheet Sheet	
Drawing No. Order No.		Revision Date		Title Description		Material Material		Location Location		Date Date		Sheet Sheet	
Drawing No. Order No.		Revision Date		Title Description		Material Material		Location Location		Date Date		Sheet Sheet	
Drawing No. Order No.		Revision Date		Title Description		Material Material		Location Location		Date Date		Sheet Sheet	

FEASIBILITY ASSESSMENT STUDY
BUCK HYDRO PLANT
FLASHBOARDS REPLACED BY PELICAN GATES

BOFORS
HOWAB

47. 87376

Change	Year	Description of change	Date	Sign.
△				

EXHIBIT B-24

ALTERNATIVE
THE FLASHBOARDS
REPLACED BY
12' PELICAN GATES

SECTION E-E

REF. DRAW. NO.

Artikelnr. Article number	Beskrivning Description	Material Material	Upplysningar Basic data
12' Pelican Gates	REASONABILITY ASSESSMENT STUDY BUCK HYDRO PLANT FLASHBOARDS REPLACED BY PELICAN GATES		Feb. 1979 J. H. J.
Order No.	Quantity	Unit	Price
B. BOFORS NOMAB		Form: A2 Size: 420x594 Blad: 1 Sheet: 1 4T. 87377

[illegible]

INLOPERENTEN SURVEILS EFTER MALL 4T. 410392

EXHIBIT B-26

4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392	
4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392	
4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392		4T. 410392 4T. 410392 4T. 410392

EXHIBIT B28-A

BOFORS
NONAB
TROLLHÄTTAN SWEDEN

F346 G/14-31-526
MUSSELDIAGRAM
NETTOFALLHÖJD $L_v = 10^\circ \text{C}$
SAMMANSTÄLLNING 3T-5453

PV-11874
76.11.15 *lee*
GT.903 939

EXHIBIT B 28-B

B OFORS
 NOHAB
 TROLLHÄTTAN SWEDEN
 F346 G/14-31-526
 MUSSELDIAGRAM
 NETTOFALLHÖJD $L_f = 10^\circ C$
 SAMMANSTÄLLNING 3T-5453
 PV-11874
 76.11.15
 GT.903 999

New River

Duration table of daily discharge for
year ending September 30.

Gaging Station at Ivanhoe, Virginia

Source: Commonwealth of Virginia State Water Control Board

Class	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	
Year	Number of days in class																																		CFS-Days	
1931			2	5	10	10	14	26	38	28	53	33	31	33	20	21	9	5	6	11	4	3	2		1										524410.0	
1932	1	7	11	7	12	26	38	25	21	31	18	22	22	33	32	25	13	8	5	4	1	3	1												540610.0	
1933	1			2	1	6	10	16	21	29	20	24	19	43	50	40	27	22	12	9	6	3			2	1	1								810243.0	
1934				2	10	26	48	48	50	44	36	25	20	14	14	6	4	4	4	2	1	4	2						1						469091.0	
1935							1		10	18	37	31	32	48	62	30	24	23	16	9	7	5	1	2	1	4	1	2	1						973377.0	
1936					1	2	4	19	33	45	32	32	24	22	38	28	20	8	8	9	10	12	9	4	4	2									894903.0	
1937						8	10	26	46	34	36	35	51	27	26	19	16	13	3	4	6		2	1	2										751513.0	
1938					1	5	8	19	34	42	37	60	77	22	19	11	7	6	4	4	4	1	2	1	1										819950.0	
1939					7	12	25	29	44	34	47	31	43	29	9	11	18	8	8	5	3	1						1							662846.0	
1940				5	27	43	31	17	20	40	39	20	32	26	13	17	11	3	4	5	3	1			2			1	1			1	1	1	1	768072.0
1941				2	6	5	22	34	35	50	71	50	37	16	11	7	4	6	1	3	2	2	1													577650.0
1942					12	16	23	25	39	42	43	27	31	33	22	16	6	5	8	7	3	3	2	1	1										692934.0	
1943				3	4	10	16	14	19	23	36	54	73	35	20	19	14	12	3	4	3			1	2										850398.0	
1944				4	28	50	45	36	29	23	20	25	32	19	17	13	4	8	7	1	3			1	1										642983.0	
1945						8	15	41	26	36	65	64	29	32	18	5	7	4	4	4	4	1	1	2	1						1			1		912730.0
1946						1	4	19	12	26	28	22	50	54	55	32	26	13	5	7	3	3	1		2	1					1				915519.0	
1947					1	3	12	32	55	53	49	35	29	33	17	19	11	7	3	1	3			1											640298.0	
1948					1	6	19	25	27	34	39	52	48	24	30	14	18	13	5	5	1	1	2	2											862158.0	
1949						2	8	13	10	11	18	33	74	60	46	32	13	16	6	7	5	2	4	3	1							1			1099145.0	
1950						2	4	9	15	35	106	89	30	26	19	13	9	4	3					1												861742.0
1951							5	18	15	26	35	40	27	53	53	35	18	10	13	7	3	2		1	2	1							1			780551.0
1952						7	13	18	28	33	40	24	17	28	48	42	18	14	11	9	5	5		1	3		2								668288.0	
1953			1	2	8	22	41	18	20	23	34	22	23	29	39	18	24	19	8	5	2	3			2	1	1								671096.0	
1954		1	6	19	27	36	45	27	23	22	18	18	19	31	33	11	9	4	5	4	1			1	3		1	1							515075.0	
1955		1	1	8	12	6	15	20	37	39	37	31	30	36	24	17	17	8	9	4	1	4	3	1	1	1	1	2							664358.0	
1956		3	3	3	5	22	39	48	50	38	21	14	20	25	29	13	10	5	7	2	3	1	2	1		1	1								535504.0	
1957				1		10	13	17	26	25	22	28	40	63	32	33	8	8	11	8	6	4	4	2	1	1					1	1			925781.0	
1958						1	1	7	10	11	15	31	31	36	45	34	40	20	36	18	15	5	3	3	3										1028606.0	
1959				2	3	6	17	28	54	43	49	38	24	26	18	22	11	6	5	5		2	2	2							2				607999.0	
1960							1	11	28	32	35	31	52	49	45	33	20	5	7	2	2	2	3	3	1	3	1				1		2			1068056.0
1961					4		8	27	52	30	35	35	33	33	33	22	12	13	10	7	7	1		1	1							1			798615.0	
1962					1	4	13	24	38	23	17	28	32	45	31	30	21	21	16	4	7	3	3	2		2									905562.0	
1963				5	6	6	23	18	41	35	27	40	26	37	39	20	12	6	5	4	5	3	2		3	1							1		672495.0	
1964		1	3	20	13	30	37	33	32	31	14	18	19	28	20	20	19	8	6	4	2	4	1		3										561813.0	
1965			1		3	7	19	12	39	39	39	38	38	37	28	22	14	12	6	3	1	1	3	1						1	1				754948.0	
1966				1	3	11	32	48	59	46	28	26	20	30	15	8	11	6	3	3	3	4	2	3	1					1			1		590905.0	
1967					4	8	10	15	19	32	33	32	70	48	41	20	12	9	2	4	2	2	2												740785.0	
1968		1	2	3	3	3	4	7	10	19	33	33	40	38	35	32	33	20	17	12	8	10	1	1					1					735971.0		
1969			1	1	1	3	2	7	8	35	33	41	40	40	50	37	17	14	6	13	6	5	1	1	2	1									680247.0	
1970		1	2	1	3	4	10	9	16	24	25	33	33	43	47	44	28	10	10	6	2	7		3		1	1			1	1				705654.0	
1971						1	9	9	17	28	38	32	33	55	42	31	17	23	10	11	4	4	1												758500.0	
1972							3	10	14	16	19	23	48	76	45	38	29	13	11	9	2	3	2	1	1					1	2				991976.0	
1973						1	1		4	19	30	19	21	45	45	50	36	38	28	7	7	2	1	3					4	1	1		1	1		1080386.0

Table 2

New River

Average flow duration statistics for
the years 1931-1973.

Gaging Station at Ivanhoe, Virginia

Source: Commonwealth of Virginia State Water Control Board

Class	CFS	Total	Accum	Perct	Class	CFS	Total	Accum	Perct	Class	CFS	Total	Accum	Perct	Class	CFS	Total	Accum	Perct
0	0.00	0	15706	100.0	9	670.00	748	14519	92.4	18	2800.0	896	2901	18.5	27	12000	37	94	.5
1	184.00	0	15706	100.0	10	780.00	1030	13771	87.7	19	3300.0	615	2005	12.8	28	14000	24	57	.3
2	220.00	4	15706	100.0	11	920.00	1288	12741	81.1	20	3900.0	456	1390	8.9	29	17000	8	33	.2
3	250.00	20	15702	100.0	12	1100.00	1294	11453	72.9	21	4600.0	296	934	5.9	30	19000	12	25	.1
4	300.00	35	15682	99.8	13	1300.00	1308	10159	64.7	22	5400.0	208	638	4.1	31	23000	8	13	.0
5	350.00	90	15647	99.6	14	1500.00	1252	8851	56.4	23	6300.0	143	430	2.7	32	27000	1	5	.0
6	410.00	135	15557	99.1	15	1700.00	1751	7599	48.4	24	7400.0	83	287	1.8	33	31000	3	4	.0
7	480.00	317	15422	98.2	16	2000.00	1803	5948	37.2	25	8700.0	59	204	1.3	34	37000	1	1	
8	570.00	586	15105	96.2	17	2400.00	1144	4045	25.8	26	10000.0	51	145	0.9					

New River

Annual maximum peak stages and discharges.

Gaging Station at Ivanhoe, Virginia

Drainage Area 1.340 mi²

Gage date 1943, 09 ft above mean sea level

Source: US Geological Survey, Open-File report 77-720

Water year	Date	Gage height (feet)	Discharge (cfs)	Water year	Date	Gage height (feet)	Discharge (cfs)
1878	Sept. 1878	a) 30	100,000	1952	Mar. 11, 1952	11.46	21,300
1913	May 24, 1913	-	b) 16,000	1953	Mar. 24, 1953	10.83	19,500
1916	July 16, 1916	c) 34.8	132,000	1954	Mar. 1, 1954	10.80	19,500
1931	Aug. 22, 1931	8.25	13,200	1955	Apr. 14, 1955	12.92	25,000
1932	Jan. 1, 1932	7.22	10,500	1956	Apr. 16, 1956	11.06	20,300
1933	Oct. 17, 1932	12.44	23,100	1957	Apr. 5, 1957	15.90	34,200
1934	Mar. 28, 1934	10.32	19,200	1958	Jan. 14, 1958	12.02	22,700
1935	Sept. 6, 1935	13.22	25,200	1959	Sept. 30, 1959	17.88	42,100
1936	Nov. 13, 1935	12.32	22,800	1960	Mar. 31, 1960	13.24	25,900
1937	Oct. 17, 1936	10.27	17,700	1961	May 12, 1961	14.39	29,200
1938	Oct. 19, 1937	12.16	22,600	1962	Dec. 12, 1961	11.00	20,000
1939	Aug. 19, 1939	12.29	22,800	1963	Mar. 13, 1963	15.50	32,800
1940	Aug. 14, 1940	38.1	155,000	1964	Aug. 31, 1964	10.18	17,900
1941	Dec. 28, 1940	8.67	13,800	1965	Oct. 17, 1964	12.40	23,600
1942	Sept. 6, 1942	10.26	17,700	1966	Feb. 14, 1966	14.95	31,000
1943	Dec. 30, 1942	10.22	17,400	1967	Mar. 7, 1967	9.01	14,900
1944	Feb. 18, 1944	10.44	18,000	1968	Mar. 13, 1968	8.35	13,200
1945	Sept. 18, 1945	17.3	39,700	1969	Oct. 19, 1968	9.56	16,300
1946	Jan. 8, 1946	12.3	22,800	1970	Aug. 10, 1970	13.48	26,600
1947	Jan. 20, 1947	10.63	18,400	1971	Oct. 31, 1970	6.74	9,470
1948	Oct. 18, 1947	12.02	22,000	1972	June 21, 1972	16.01	34,500
1949	Aug. 29, 1949	14.51	29,200	1973	May 28, 1973	18.52	44,600
1950	Nov. 2, 1949	8.56	13,500	1974	Apr. 5, 1974	13.18	25,800
1951	Dec. 8, 1950	16.97	38,500	1975	Mar. 14, 1975	13.70	27,300
				1976	Oct. 18, 1975	15.57	33,000

- a) Approximate stage, highest known during period 1840 to 1916.
- b) Maximum daily discharge, from records of Appalachian Power Co.
- c) From floodmarks, present datum.

CHAPTER IV

INITIAL ANALYSIS OF
SAFETY FACTORS CONCERNING
PERTINENT UPGRADING
ALTERNATIVES

CHAPTER IV

INITIAL ANALYSIS OF SAFETY FACTORS
CONCERNING PERTINENT UPGRADING ALTERNATIVES

Each of the proposed upgrading alternatives was examined for adverse safety conditions that might be introduced with its implementation.

The identification of any such safety hazards led to either a recommendation of measures to alleviate the problem or a recommendation of dropping the alternative as a proposal for upgrading the hydro plants. Either of the recommendations was made from a preliminary analysis with emphasis towards establishing a related cost so that the comparative economic evaluations could be conducted for the selected upgrading alternatives. In the case where an upgrading alternative with an associated safety condition would prove economically feasible, a more detailed analysis and design would precede the development of the alternative.

At both the Byllesby and Buck dams, all but one of the proposed alternatives involved equipment changes or modifications. These equipment modifications would produce no change in the present safety condition of the dams. The proposed alternative of raising the head three feet at Buck, however, would alter the present hydraulic and stability conditions at the site. The hydraulic and stability situations were evaluated for the Buck hydro plant operating with the head increase.

1. STABILITY ANALYSIS(1) Description

Buck is a gravity type dam relying on its mass to resist overturning and sliding. The critical sections of the powerhouse side of the dam and the spillway were investigated for stability. The

critical section of the retaining dam is shown on Exhibit A-4, Section C-C; the critical section of the spillway is shown on the same exhibit Section E-E. Exhibit C-1 shows the forces as applied to the spillway section and Exhibit C-2 defines the forces and equations used in the analysis. Two cases were considered when analyzing the dam for stability. One case, the earthquake loading, applied all forces from Exhibit B except the ice load. The other case, ice loading, applied all forces from Exhibit B except the earthquake forces. The evaluation of stability considered the most critical case, either ice or earthquake loadings.

(2) Analysis

With the normal pool at Buck raised three feet to elevation 2006.5, the most critical case at the retaining dam section was earthquake loading at a maximum head of forty feet. Applying the equations from Exhibit C-2, the factors of safety associated with this section were:

1. Factor of safety against overturning FS_o 1.16
2. Factor of safety against sliding FS_s 3.6
3. Pressure at the toe P_t 34 psi
3. Pressure at the heel P_h -13 psi

The spillway section was taken at the flashboards as shown in Exhibit C-1. Since the spillway joins the piers at 33 foot intervals, the stability analysis included one pier and half the spillway on each side of the pier as a composite section. With the normal pool increased three feet, the most critical case was ice loading at a maximum head of 32.5 feet. Applying the

equation from Exhibit C-2, the factors of safety associated with this situation were:

- . Factor of safety against overturning FS_o 0.89
- . Factor of safety against sliding FS_s 3.0

Because the factor of safety against overturning is less than unity, the resultant force on the base of the dam (R_v) falls outside the toe, signifying failure by overturning. Since some of the parameters used for the stability analysis, such as uplift, were not verifiable at this time, the appropriate factor of safety against overturning was taken from analysis of the spillway's present situation. The spillway has withstood critical conditions of ice loading at a head of 29.5 feet, which corresponds to the three foot differential between the present and proposed operation. Applying equation 1, the factor of safety against overturning FS_o is 1.1. In order to increase the factor of safety FS_o from 0.89 to 1.1 with the head increased, stabilizing forces are required in both the piers and the spillway. For the net effects on the piers and the spillway under an increased head to remain similar to the net effects currently experienced at the spillway, a resisting moment of 2901 kip-feet is required in each pier and a resisting moment of 3617 kip-feet is required in each spillway section.

With the addition of these resisting moments to the piers and spillway, the factors of safety from the equations on Exhibit B become:

1. Factor of safety against overturning FS_o 1.1
2. Factor of safety against sliding FS_s 3.2

3. Pressure on the toe P_t 33 psi
3. Pressure on the heel P_h -13.7 psi

(3) Results and Recommendations

For both the retaining dam and the spillway sections, the factors of safety against sliding exceed the allowable factor of 2.0, and the factors of safety against overturning are lower than the usual allowable factor of 1.5. The sections are stable from overturning since the factors of safety are greater than unity. These lower factors of safety, however, indicate the stress distribution on the base of the dam, and it appears that under critical loading conditions the heel of the dam will be in tension. The stresses, however, are very small because of the relatively low head. The concrete, therefore, should be able to resist even the tensile stress, as it demonstrated to have done in the past under critical loading conditions. A detailed stress analysis of the critical sections would precede any development.

To obtain the desired moments to stabilize the spillway at a raised head, a dead load of 125 Kips is required in each pier and a force of 275 Kips is required in each spillway section. The existing bridge over the piers could be replaced with heavier precast concrete sections and covered with a twelve inch concrete slab. This would transmit the desired load to each pier and also serve to widen the access road to the powerhouse. The spillway would be rock anchored to the foundation at various intervals to supply the desired stabilizing force. Tests must be performed on the spillway concrete and the rock foundation before the

detailed designs can be established. For the economic evaluation, however, conceptual designs were used to arrive at cost estimates for insuring the stability of Buck with the head increased.

2. HYDRAULIC EFFECTS ON THE SPILLWAY

Another consideration of raising the head at Buck would be its effect on the spillway's ability to discharge a given flood. The spillway at Buck consists of twenty-four flashboard sections as shown on Exhibit A-4 Section E-E and six tainter gate sections as shown on the same exhibit, Section D-D. The tainter gates are used to regulate the flows at the dam, while the flashboards are removed during flooding periods when the capacity of the gates is exceeded. At the present normal pool elevation of 2003.5, the reservoir covers approximately 70 acres. With the head raised the reservoir would operate at a normal pool elevation of 2006.5.

For evaluating the required flood capacity of the spillway the Corps of Engineers' "Recommended Guidelines for Safety Inspection of Dams" was used to classify the Buck dam. Following the Corps' guidelines, the dam would be classified as small in size and significant in hazard potential. Under this classification the recommended spillway design flood would range from the 100 yr. flood to the 1/2 PMF (Probable Maximum Flood). The 1/2 PMF was used in evaluating the performance of the spillway. A flood hydrograph shown in Exhibit C-3 was supplied by the Corps of Engineers for the Ivanhoe drainage basin just below Buck dam. Exhibit D shows the derivation of the 1/2 PMF hydrograph.

(1) Analysis

A computer program was utilized to determine the change in reservoir elevation from the spillway operation during the 1/2 PMF.

The principal equation used in the program to calculate the elevation changes was:

$$Z = (I - O) / A \times DT$$

Z = change in reservoir elevation

I = flood inflow

O = outflow or spillway discharge

A = available storage area at a specific elevation

DT = specified time increment

A few simplifications were used in running the program because of the timing difficulty involved with the flashboard removal. These simplifications would not affect the maximum reservoir elevation attained during the flood. No change in reservoir level was recorded until the inflow from the flood exceeded the discharge potential of the six tainter gates at normal pool. This is observed in the initial part of the program run. The six tainter gates were assumed to control the inflow until a maximum elevation was reached. At this elevation the remaining twenty-four flashboard sections were assumed to be released instantaneously. This is shown at the sudden drop in the reservoir during the program run. From this point on, the entire spillway functions as a weir with the flows uncontrolled and the reservoir rise following the equation previously defined. In actual practice, one flashboard section at a time would be

removed until all the sections were removed, which would occur before the maximum elevation used in the program is reached. Exhibit C-5 shows the present operation of the Buck spillway during the 1/2 PMF, and Exhibit C-6 shows operation of the spillway with the head increased three feet.

(2) Results and Recommendations

It was initially suspected that the reservoir rise would be greatest with the head increase because of the lost storage capacity between the present normal pool and the raised normal pool. This was not the case as shown in the computer printouts for the existing and raised head situations. In both cases the reservoir reached a maximum elevation of 2010' during the twenty-fourth hour of the flood. This is attributed to the fact that the magnitudes of the flood inflows and spillway discharges are much greater than the storage capacity of the reservoir at various elevations. In effect, there is no storage available for these large discharges and the height of the reservoir depends solely on the magnitude of the flood inflows and the discharge characteristics of the spillway at Buck.

While there are no disadvantages hydraulically to raising the head at Buck there are some advantages. As shown in the program, at an increased head the tainter gates can control a greater discharge before the flashboards must be removed. This greater flood control will increase the energy gains at the plant as demonstrated in a previous upgrading proposal. Also, the dam will be overtopped during the 1/2 PMF at its present elevation of 2007 feet. If the head at the dam were increased three feet,

the elevation of the dam would also be increased to 2010'. It would, therefore, be safe from overtopping during the 1/2 PMF. The spillway discharge capacity of 150,000 cfs at elevation 2007' is between the 100 yr. and 1/2 PMF peak discharge values, of 100,700 cfs and 203,000 cfs respectively; therefore, if the 100 yr. flood, Exhibit C-7 and C-8, was used in the hydraulic analysis, the existing dam would be safe from overtopping.

* * * * *

The next chapter will deal with the alternatives from an economic feasibility point of view.

CHAPTER IV
EXHIBITS

STABILITY ANALYSIS SPILLWAY SECTION OF BUCK DAM

SECTION A-A
SCALE 1/8" = 1'-0"

PLAN VIEW
SCALE 3/32" = 1'-0"

EXHIBIT C-1

STABILITY ANALYSIS
A. Definition of Forces

$$F_I = \text{ice force} = 5000 h_I$$

$$F_{qw} = \text{earthquake force due to acceleration of water} = \frac{5}{9} \gamma_w H^2 \cdot \frac{1}{10}$$

$$F_w = \text{hydrostatic force} = \frac{1}{2} \gamma_w H^2$$

$$F_s = \text{silt force} = \frac{1}{2} \gamma_s h^2$$

$$F_u = \text{uplift force} = \frac{1}{2} \gamma_w H_B$$

$$W_s = \text{weight of spillway}$$

$$F_{qs} = \text{earthquake force on spillway} = 0.13 W_s$$

$$W_p = \text{weight of pier}$$

$$F_{qp} = \text{earthquake force on pier} = 0.13 W_p$$

$$R_v = \text{resultant of bearing pressures} = W_p + W_s - F_u - F_{qp} - F_{qv} - F_{qs}$$

$$R_h = \text{resultant of horizontal forces} = F_w + F_I = F_{qw} + F_{qph} + F_{qsh}$$

B. Equations

(1) Factor safety against sliding

$$FS_s = \frac{R_v \times C_f + A_s S_s}{R_h}$$

$$C_f = \text{coefficient of friction} = .65$$

$$A_s = \text{area of key}$$

$$S_s = \text{shear strength of key} = 250 \text{ psi}$$

(2) Factor safety against overturning

$$FS_o = \frac{W_s a + W_p b}{(W_s a + W_p b) - R_v \bar{x}}$$

a & b & x are moment arms from toe

(3) Pressure in heel and toe

$$P_t = \frac{R_v}{B} \left(1 + \frac{6e}{B} \right)$$

$$P_h = \frac{R_v}{B} \left(1 - \frac{6e}{B} \right)$$

HYDROGRAPH COMPUTATION

Time Hr.	Flood (cfs) Hydrograph	Unit (cfs) Hydrograph	Inflow, Runoff Excess (in)				1/2 PMF Inflow (cfs) Hydrograph
			.12	6.98	.4	.12	
0	900	769	92				92
6	7,300	6,240	649	5,367			6,116
12	28,300	24,192	2,903	43,555	308		52,882
18	31,800	27,184	3,262	168,860	2,496	92	174,710
24	25,300	21,627	2,595	189,744	9,677	749	<u>202,765</u>
30	17,600	15,045	1,805	150,956	10,874	2,963	166,538
36	11,900	10,172	1,220	105,014	8,650	3,262	118,146
42	8,700	7,437	892	71,000	6,015	2,595	80,502
48	6,750	5,770	692	51,910	4,069	1,805	58,476
54	5,300	4,331	544	40,275	2,975	1,220	45,014
60	4,200	3,590	431	31,626	2,308	892	35,257
66	3,300	2,821	339	25,058	1,812	692	27,902
72	2,600	2,223	267	19,670	1,436	544	21,937
78	2,200	1,880	226	15,517	1,128	431	17,302
84	1,900	1,624		13,122	889	339	
90	1,700	1,453			752	267	
96	1,500	1,282				226	
102	1,300	1,111					
108	1,150	983					
114	1,000	855					
120	900	769					
126	800	684					
132	700	598					
138	600	513					
144	500	427					
150	400	342					

168,000 cfs - 6 hr.

$$\text{Depth of runoff} = \frac{168,600 \text{ cfs} \cdot 6 \text{ hr.} \times 21,600 \frac{\text{sec}}{6 \text{ hr}} \times \frac{12 \text{ in}}{\text{ft}}}{1340 \text{ m}^2 \times (5280 \frac{\text{ft}}{\text{mi}})^2} = 1.17 \text{ in}$$

EXISTING BUCK RES. HALF PMF
FLOOD ROUTING THROUGH A SPILLWAY
SPILLWAY LENGTH = 934.00 FT. LONG
SPILLWAY CREST = 1995.00 FT. HEIGHT

Exhibit C-5

TIME	ELEVATION	INFLOW	OUTFLOW
.500	2003.500	509.500	509.500
1.000	2003.500	1018.999	1018.999
1.500	2003.500	1528.962	1528.962
2.000	2003.500	2038.925	2038.925
2.500	2003.500	2548.388	2548.388
3.000	2003.500	3057.851	3057.851
3.500	2003.500	3567.314	3567.314
4.000	2003.500	4076.777	4076.777
4.500	2003.500	4586.738	4586.738
5.000	2003.500	5096.703	5096.703
5.500	2003.500	5606.164	5606.164
6.000	2003.500	6115.629	6115.629
6.500	2003.500	10009.883	10009.883
7.000	2003.500	13906.602	13906.602
7.500	2003.583	17803.320	16923.609
7.999	2004.481	21700.035	19611.148
8.499	2005.594	25597.254	23165.395
8.999	1999.151	29494.473	29239.496
9.499	1999.502	33391.187	33089.297
9.999	1999.854	37287.900	36959.132
10.499	2000.190	41184.625	40864.844
10.999	2000.509	45081.340	44741.754
11.499	2000.828	48978.559	48619.129
11.999	2001.137	52875.777	52527.121
12.499	2001.864	63017.055	62009.344
12.999	2002.586	73168.312	72121.437
13.499	2003.280	83320.062	82227.688
13.999	2003.944	93471.812	92262.875
14.499	2004.581	103623.562	102387.250
14.999	2005.204	113775.375	112513.562
15.499	2005.804	123926.625	122590.750
15.999	2006.389	134077.875	132718.875
16.499	2006.961	144224.375	142779.000
16.998	2007.516	154370.812	152919.062
17.498	2008.066	164517.750	163037.375
17.998	2008.597	174664.687	173155.687
18.498	2008.774	177035.500	176681.062
18.997	2008.897	179372.187	179015.875
19.497	2009.019	181708.937	181357.625
19.997	2009.137	184045.625	183695.562
20.496	2009.256	186382.375	186028.812
20.996	2009.374	188719.062	188362.125
21.496	2009.492	191055.750	190695.437
21.996	2009.610	193392.500	193028.687
22.495	2009.729	195729.187	195362.062
22.995	2009.847	198065.937	197695.375
23.495	2009.965	200402.125	200028.250
23.995	2010.081	202738.375	202373.375
24.494	2009.971	199780.687	200259.187
24.994	2009.818	196764.375	197243.250
25.494	2009.665	193747.000	194220.375
25.993	2009.512	190729.687	191197.312
26.493	2009.359	187712.312	188174.250
26.993	2009.206	184695.000	185151.125
27.493	2009.053	181678.125	182128.500
27.992	2008.897	178661.312	179122.500
28.492	2008.738	175644.000	176100.562
28.992	2008.579	172626.625	173078.312
29.492	2008.421	169609.312	170056.062
29.991	2008.262	166591.937	167033.812
30.491	2008.058	162579.937	163161.937
30.991	2007.841	158550.125	159145.750
31.490	2007.620	154519.375	155105.875
31.990	2007.400	150488.625	151065.625
32.490	2007.179	146458.312	147025.812
32.990	2006.958	142428.000	143002.687
33.489	2006.729	138397.750	138965.500
33.989	2006.498	134367.437	134921.125
34.489	2006.268	130336.687	130876.250
34.988	2006.038	126305.875	126831.375
35.488	2005.801	122275.625	122812.312
35.988	2005.560	118245.312	118769.562
36.488	2005.366	115088.437	115488.062
36.987	2005.178	111953.125	112345.125
37.487	2004.991	108817.875	109206.062
37.987	2004.795	105682.562	106078.500
38.487	2004.599	102547.312	102934.812
38.986	2004.402	99412.063	99791.187

◆STOP◆

RAISED BUCK RES. HALF PMF
 FLOOD ROUTING THROUGH A SPILLWAY
 SPILLWAY LENGTH = 934.00 FT. LONG
 SPILLWAY CREST = 1995.00 FT. HEIGHT

Exhibit C-6

TIME	ELEVATION	INFLOW	OUTFLOW
.500	2006.500	509.500	509.500
1.000	2006.500	1018.999	1018.999
1.500	2006.500	1528.962	1528.962
2.000	2006.500	2038.925	2038.925
2.500	2006.500	2548.388	2548.388
3.000	2006.500	3057.851	3057.851
3.500	2006.500	3567.314	3567.314
4.000	2006.500	4076.777	4076.777
4.500	2006.500	4586.738	4586.738
5.000	2006.500	5096.703	5096.703
5.500	2006.500	5606.164	5606.164
6.000	2006.500	6115.629	6115.629
6.500	2006.500	10009.883	10009.883
7.000	2006.500	13906.602	13906.602
7.500	2006.500	17803.320	17803.320
7.999	2006.500	21700.035	21700.035
8.499	2006.500	25597.254	25597.254
8.999	2006.891	29494.473	27568.199
9.499	2007.795	33391.187	30761.715
9.999	2008.758	37287.906	34415.289
10.499	2000.190	41184.625	40878.371
10.999	2000.509	45081.340	44741.754
11.499	2000.828	48978.559	48619.129
11.999	2001.137	52875.777	52527.121
12.499	2001.864	63017.055	62009.344
12.999	2002.586	73168.312	72121.437
13.499	2003.280	83320.062	82227.688
13.999	2003.944	93471.812	92262.875
14.499	2004.581	103623.562	102387.250
14.999	2005.204	113775.375	112513.562
15.499	2005.804	123926.625	122590.750
15.999	2006.389	134077.875	132718.875
16.499	2006.961	144228.375	142779.000
16.998	2007.516	154370.812	152919.062
17.498	2008.066	164517.750	163037.375
17.998	2008.597	174664.687	173155.687
18.498	2008.774	177035.500	176681.062
18.997	2008.897	179372.187	179015.875
19.497	2009.019	181708.937	181357.625
19.997	2009.137	184045.625	183695.562
20.496	2009.256	186382.375	186028.812
20.996	2009.374	188719.062	188362.125
21.496	2009.492	191055.750	190695.437
21.996	2009.610	193392.500	193028.687
22.495	2009.729	195729.187	195362.062
22.995	2009.847	198065.937	197695.375
23.495	2009.965	200402.125	200028.250
23.995	2010.081	202738.375	202373.375
24.494	2009.971	199780.687	200259.187
24.994	2009.818	196764.375	197243.250
25.494	2009.665	193747.000	194220.375
25.993	2009.512	190729.687	191197.312
26.493	2009.359	187712.312	188174.250
26.993	2009.206	184695.000	185151.125
27.493	2009.053	181678.125	182128.500
27.992	2008.897	178661.312	179122.500
28.492	2008.738	175644.000	176100.562
28.992	2008.579	172626.625	173078.312
29.492	2008.421	169609.312	170056.062
29.991	2008.262	166591.937	167033.812
30.491	2008.058	162579.937	163161.937
30.991	2007.841	158550.125	159145.750
31.490	2007.620	154519.375	155105.875
31.990	2007.400	150488.625	151065.625
32.490	2007.179	146458.312	147025.812
32.990	2006.958	142428.000	143002.687
33.489	2006.729	138397.750	138965.500
33.989	2006.498	134367.437	134921.125
34.489	2006.268	130336.687	130876.250
34.988	2006.038	126305.875	126831.375
35.488	2005.801	122275.625	122812.312
35.988	2005.500	118245.312	118769.562
36.488	2005.366	115088.437	115488.062
36.987	2005.178	111953.125	112345.125
37.487	2004.991	108817.875	109206.062
37.987	2004.795	105682.562	106078.500
38.487	2004.599	102547.312	102934.812
38.986	2004.402	99412.063	99791.187

◆STOP◆

FLOOD FREQUENCY COMPUTATIONS

Log Pearson Tye III Calculations

$\overline{\log x}$	Mean	4.36
$\sigma \log x$	Standard Deviation	0.196
g	Skewness	1.40
(equation)	$\overline{\log x} = \log x + K \sigma \log x$	

<u>Probability</u>	<u>Recurrence Interval (yrs)</u>	<u>K Value</u>	<u>Discharge Nearest 100 cfs</u>
0.99	1.01	1.318	12,700
0.80	1.25	0.832	15,800
0.50	2	0.225	20,800
0.20	5	0.705	31,600
0.10	10	1.337	42,000
0.04	25	2.128	60,100
0.02	50	2.706	78,000
0.01	100	3.271	100,700
0.005	200	3.828	129,400

NEW RIVER IVANHOE, VIRGINIA
FLOOD FREQUENCY CURVE

EXHIBIT C-8

CHAPTER V
ECONOMIC FEASIBILITY
ANALYSIS AND RECOMMENDED
ALTERNATIVES

CHAPTER V

ECONOMIC FEASIBILITY ANALYSIS AND RECOMMENDED ALTERNATIVES

Economic feasibility of various alternatives were computed by AEP. This was done on the basis of information developed during the course of this study and by utilizing AEP's in-house "Hydro Project Economic Feasibility Analysis Procedures." The latter basically compares the cost and benefit associated with a hydroelectric project with an equivalent steam powered project. Cost estimates for the basic alternatives are shown in APPENDIX B. APPENDIX C contains computer print-outs of selected alternatives and an example of a derivation of a print-out.

In our analysis we have made the following assumptions:

- . The existing project could generate for a further 15 years approximately the present average annual KWH production.
 - Byllesby 65,900,000 KWH
 - Buck 45,600,000 KWH
- . The upgrading of the project, including its hydro turbine and electric generating equipment would extend the life of the project by at least 40 years from the point in time the upgrading would be implemented.

1. ALTERNATIVES SELECTED FOR ANALYSIS

From the basic alternatives mentioned in the previous chapter various combinations are possible. Some combinations were obviously less attractive than others. They were excluded from the analysis at the time this became apparent. Alternatives selected for analysis were:

(1) BYLLESBY

Alternative 1: Continue with existing equipment as is.

(Project life 15 years)

Alternative 2: Install 4 new runners, modify draft tubes and wicket gates and rewind and upgrade 4 generators.

(Project life 40 years)

Alternative 3: Replace flashboards by Pelican gates. (The life of the project would not be extended, however, the new gates' life would be in excess of 40 years.)

(2) BUCK

Alternative 1: Continue with existing equipment as is (Project life 15 years)

Alternative 2: Install 3 new runners, modify draft tubes and wicket gates and rewind 3 generators. (Project life 40 years)

Alternative 3: Replace flashboards by Pelican gates. (The life of the project would not be extended, however the gates' life would be in excess of 40 years.)

Alternative 4: Raise the forebay of Buck by 3 feet. (No extension of project life)

Alternative 4: Raise the forebay of Buck by 3 feet. (No extension or project life)

Alternative 5: Add small scale hydro unit in remaining exciter pit. (No extention of project life except for the SSHU, which would be 40 years.)

Alternative 6: Install 3 new runners, modify draft tubes and wicket gates, rewind 3 generators and replace flashboards with gates. (Project life 40 years)

Alternative 7: Install 3 new runners, modify draft tubes and wicket gates, rewind 3 generators and add a standard small scale hydropower unit in the existing exciter pit. (Project life 40 years)

Alternative 8: Install 3 new runners, modify draft tubes and wicket gates, rewind 3 generators and add a standard small scale hydropower unit and replace flashboards by gates. (Project life 40 years)

Alternative 9: Install 3 new runners, modify draft tubes and wicket gates, rewind three generators, add a standard small scale hydropower unit, replace flashboards by gates and raise the forebay elevation of Buck by three feet. (Project life 40 years)

Table 4, on the next page, represents a summary economic feasibility analysis of the above mentioned alternatives 2 through 9.

TABLE 4

SUMMARY FEASIBILITY ANALYSISBYLLESBY

No.	Alternative	Annual Cap. Increase		Required Investment \$ X 10 ³	Incremental Annual Level-ized Benefit \$ X 10 ³	Supportable Investment at 18% CC*	Benefit Cost Ratio
		MWH	MW				
2	Upgrade hydro equipment	9,500	2.7	2,852	1,380	7,667	2.69
3	Gates	3,060	-	527	130	722	1.37
2&3	Upgraded equipment and gates	12,912	2.7	3,379	1,564	8,689	2.57

BUCK

2	Upgrade hydro equipment	6,050	1.1	2,024	927	5,150	2.54
3	Gates	1,339	.1	820	55	306	.37
4	Raise forebay 3 feet	6,630	-	3,302	272	1,511	.46
5	Addition small scale hydro unit	1,974	1.4	1,894	106	589	.31
6	Upgrade equipment and gates	7,389	1.1	2,703	991	5,516	2.04
7	Upgrade equipment and new unit	8,024	2.5	3,762	1,029	5,717	1.52
8	Upgrade equipment, gates and new unit	9,363	2.5	4,441	1,107	6,150	1.39
9	Upgrade equipment, gates, new unit, and forebay raise 3 feet	15,072	2.5	7,743	1,199	6,661	.86

* CC - Carrying Charges

2. ANALYSIS

From an economic point of view the choice of alternative in order of priority would be as follows:

<u>Priority</u>	<u>Alternatives</u>		<u>Capt. Cost</u> <u>\$ x 10⁶</u>	<u>Combined</u> <u>B/C Ratio</u>
	<u>Byllesby</u>	<u>Buck</u>		
1	(2)	+ (2)	4.9	2.63
2	(2&3)	+ (6)	6.1	2.32
3	(2&3)	+ (7)	7.1	2.02
4	(2&3)	+ (8)	7.8	1.90

However, from an increased power potential point of view the choice of alternatives would be in order of priority.

<u>Priority</u>	<u>Annual Cap. Increase</u>		<u>Alternatives</u>		<u>Combined</u> <u>B/C Ratio</u>
	<u>MWH</u>	<u>MW</u>	<u>Byllesby</u>	<u>Buck</u>	
1	22,175	5.2	(2&3)	+ (8)	1.90
2	20,836	5.2	(2&3)	+ (7)	2.02
3	20,201	3.8	(2&3)	+ (6)	2.32
4	15,550	3.8	(2&3)	+ (2)	2.63

Combinations of alternatives having a benefit cost ratio of less than unity were eliminated from consideration.

* * * * *

The assumptions made for this type analysis are sensitive in terms of existing plant life. For instance, if it would be assumed that the existing plant life could be extended 40 years with the same benefits as experienced today, the BC ratios would be for the following alternatives (as computed by AEP).

. <u>Byllesby</u>		<u>B/C</u>
- Upgrade hydro equipment		.99
- Replace flashboards by gates		1.79
- Upgrade equipment and gates		1.14
. <u>Buck</u>		B/C
- Upgrade hydro equipment		.89
- Replace flashboards by gates		.49
- Upgrade equipment and gates		.80

The plants, however, are 66 years old. The assumption that the plants can operate for another 40 years without major upgrading or refurbishing does not appear to be realistic.

The assumption made that the plant could operate under existing conditions without upgrading or refurbishing, is to some extent also arbitrary, however, experience has shown that most hydro plants have a useful life in the range of 70 - 80 years. In the light of this experience and the appraisals made at the site of the equipment at Byllesby and Buck, the assumption of 15 years extended life of the existing equipment was chosen.

We therefore feel that the B.C. ratios shown according to the assumption 15 years extended life for the existing equipment

and 40 years life for upgraded equipment is more realistic.

(1) Capital Cost per installed KW

As was shown in the previous chapter the power studies indicated a difference from name plate data and installed capacity. Field tests were performed to arrive at the installed capacity values. From the records of AEP it was established that:

- . The present value of installed cost per KW for the existing plant was \$138 per KW.
- . After upgrading this value would be according to the following alternatives:

	<u>\$ per KW</u>	Increase in <u>\$ per KW</u>
(2&3) + (8)	349	211
(2&3) + (7)	329	191
(2&3) + (6)	311	173
(2) + (2)	273	185

(2) Cost per Installed KWH

The average output of the project over the past 10 years was 1,11.5 million KWH. It was established from information obtained from AEP that:

- . The installed cost divided by annual generated KWH was \$.035.

. After upgrading this value would be according to the following alternatives:

	<u>\$ per KWH</u>	Increase in <u>\$ per KW</u>
(2&3) + (8)	.088	.053
(2&3) + (7)	.084	.049
(2&3) + (6)	.076	.041
(2) + (2)	.069	.034

The values tabulated above are relative with respect that the values per KW and per KWH are compared to an assumed value of the present Byllesby and Buck project.

(3) Rate of Return on Investment

AEP is a "regulated" company. Decisions to invest in additional energy supply sources are mainly based on need and benefit-cost criteria. Current analytical procedures are based on this concept.

Efforts were made by AEP to compute the ROI of the alternatives at various project life intervals. Since these computations were a comparative analysis not based on cash-flow, they could be open to misunderstanding. For this reason, they have not been included in this report.

* * * * *

Primary financial criteria for selection of upgrading alternatives have been the benefit cost ratios.

3. RECOMMENDED ALTERNATIVES

Main criteria for selecting potential viable alternatives for upgrading the project have been increased energy production and increased capacity for both Byllesby and Buck. The recommended alternatives evolved have a benefit cost ratio of more than two.

The following is recommended:

- . Develop and install alternatives (2 & 3) and (6). New Runners modified draft tubes and wicket gates and in addition replacement of flashboards by hydraulic gates for Byllesby and Buck.
- . Review the methods and cost estimates for the civil engineering and installation costs for alternative (5), installing a small scale hydropower unit at Buck, with the objectives to simplify and reduce the costs of these activities. Prepare a new economic analysis of this alternative and re-evaluate this issue.

The engineering considerations have been dealt with in the previous chapter, cost information has been included in APPENDIX B, and benefit cost summaries have been shown on Table 4. An outline of the recommended engineering and production schedule is presented on the next page.

* * * * *

The choice of upgrading alternatives makes it possible to install the new runners and rewind generators in sequence. Hence, energy production losses during the installation period can be kept at 14% of maximum production.

BYLLESBY and BUCK

UPGRADING FEASIBILITY STUDY

RECOMMENDED ENGINEERING AND CONSTRUCTION SCHEDULE

Item	Project		Years
•Detailed Review of Feasibility Study	██████████		
•Preparation of Contract Documents	██████████		
•Contract Awards Mechanical and Electrical Equipment	██		
•Detailed Design of Construction Contracts	██████████		
•Award of Construction Contract	██		
•Preparation of Construction Drawings	████████████████████		
•Fabrication and Delivery of Hardware	██		
•Construction Mobilization	██████████		
•Construction Modifications, Powerhouse Dams and Spillways	██		
•Installation Byllesby		██████████	
•Installation Buck		██████████	
•Testing and Start-Up		██████████	

54

10
20
30
40
50
60
70
80
90
100
110
120
130
140
150
160
170
180
190
200
210
220
230
240
250
260
270
280
290
300
310
320
330
340
350
360
370
380
390
400
410
420
430
440
450
460
470
480
490
500
510
520
530
540
550
560
570
580
590
600
610
620
630
640
650
660
670
680
690
700
710
720
730
740
750
760
770
780
790
800
810
820
830
840
850
860
870
880
890
900
910
920
930
940
950
960
970
980
990
1000

The engineering, cost and benefit parameters chosen in this study have on purpose been conservative. When the project would be mobilized, both equipment manufacturers and civil engineering contractors could gain cost savings from volume, continuity and having tooling on site. These potential savings have not been estimated in this study. However, in case of implementation of the project these savings should be passed on to the client.

CHAPTER VI
REGULATORY REQUIREMENTS

CHAPTER VI

NECESSARY REGULATORY REQUIREMENTS

On April 3, 1978, The Federal Energy Regulatory Commission issued a license to Appalachian Power Company (for a period effective April 1, 1962 through December 31, 1993) for the continued operation and maintenance of Byllesby and Buck, Project No. 2514. The license was issued in acceptance of the required exhibits of the plants that were submitted to the FERC from 1965 through 1967. The license was also issued subject to Form L-3 entitled "Terms and Conditions of License for Constructed Major Projects Affecting Navigable Waters of the United States," designated by Articles 1 through 28, and special conditions designated by additional Articles 29 through 38. The necessary regulatory requirements affecting the proposals for upgrading Byllesby and Buck are addressed in these Articles. The following is a summary of the various agencies required approvals, as stated in the Articles, prior to any upgrading alternative implementation.

ARTICLE 2

The revised or additional exhibits covering the changes in the present license must be submitted to the FERC for approval.

The exhibits affected by the upgrading alternatives are:

Exhibit E - Nature, extent and ownership of water rights (only applicable for raising the head at Buck)

Exhibit H - Proposed operation; comprehensiveness of development; spillway capacity (only applicable for raising the head of Buck)

Exhibit I - Estimate of dependable capacity and energy output (all proposals)

Exhibit J & K - Map of location, project area and boundary (only applicable for raising the head at Buck)

Exhibit L - General design drawings (only applicable for raising the head at Buck)

Exhibit M - General description of equipment (all proposals)

Exhibit N - Estimate of cost (all proposals)

Exhibit R - Recreational use of project (only applicable for raising the head at Buck)

ARTICLE 4

The Regional Engineer, Federal Energy Regulatory Commission, will inspect and approve any addition or alteration authorized by the FERC.

ARTICLE 21

Any dredging and filling required at the project, upon approval of the FERC, shall be done to the satisfaction of the District Engineer, Department of Army, in charge of the locality.

ARTICLE 32

Any changes to recreational development proposed at the project requires the approval of the Virginia Commission of Outdoor Recreation and the U.S. Department of the Interior. The changes would be filed for Commission approval in revised Exhibits K and R of the license.

ARTICLE 33

Any changes to the project requires the approval of Federal, State and local environmental protection agencies.

These agencies would include: United States Environmental Protection Agency, the Virginia State Water Control Board, and the Virginia Commission of Game and Inland Fisheries.

ARTICLE 35

Prior to construction or development at the project consultation with the State Historical Preservation Officer is required.

This agency is the Virginia Historic Landmarks Commission.

CHAPTER VII

INITIAL ASSESSMENT OF ENVIRONMENTAL AND SOCIO ECONOMIC FACTORS

CHAPTER VII

INITIAL ASSESSMENT OF ENVIRONMENTAL IMPACT AND SOCIOECONOMICAL FACTORS

The "Order Issuing License," dated April 3, 1978, from the Federal Energy Regulatory Commission, summarized the environmental and socioeconomical aspects for the Byllesby and Buck hydroelectric plants. The following outlines the summaries on Recreation, Fish and Wildlife, and Environment Considerations.

1. RECREATION

The U.S. Department of Interior stated that because of the rugged terrain which restricts access to the project waters, the project's potential for recreational development is limited. The Department also said that there is limited demand for recreation development because of the low population density. In license Exhibit R, however, forty acres of land was reserved for future recreational development. This future development site was acceptable to the Virginia Commission of Game and Inland Fisheries while the Virginia Commission of Outdoor Recreation suggested the narrow shorelines also be included in the recreational development scheme. The FERC therefore concluded that "the proposed recreational development for the project appears to be consistent with the objectives and priorities in the Virginia Outdoor Plan."

2. FISH AND WILDLIFE

The following points were drawn from the Department of Interior and the Virginia Commission of Game and Inland Fisheries comments on

Byllesby and Buck. The minimum flow of 310 cfs from Buck was sufficient to protect the downstream fishery resources. No migratory species of fish were in this part of the New River, so fish passages were not necessary. Fishermen and hunters appear to use the river and areas around the facilities moderately. The FERC finally concluded that "the project as operated does not affect wildlife resources."

3. ENVIRONMENTAL CONSIDERATIONS

The FERC stated that the railroad and utilities distract from one of the most scenic areas on the New River, which includes spectacular cliffs, fast white water, and a rugged wilderness setting in general. There were no historic sites affected by the project and there was no adverse impact on the quality of the human environment imposed by the operation of the project. The FERC also noted that the Virginia State Water Control Board issued a Water Quality Certificate for the project for compliance with the water quality standards. Therefore, the FERC concluded "that the preparation and circulation of an environmental impact statement is not necessary."

The implementation of any of the proposed upgrading alternatives for Byllesby and Buck would not alter the present, and previously stated, assessment of the environmental and socioeconomic aspects of the two sites. Therefore, the environmental impacts associated with upgrading the two hydroplants could be considered neutral, neither improving nor deteriorating the existing situation. As part of the FERC licensing procedure, the various environmental

agencies (Article 33 Regulatory Requirements) would be contacted for their comments and approval prior to the development of any alternative.

APPENDIXES

NEW POWER STATIONS
WITH BULB UNITS ALTERNATIVE

NEW POWER STATIONS WITH BULB TURBINE UNITS

The best location of new damsites would be immediately downstream of the existing dams. The existing dams can most likely serve as coffer dams during the construction period. The location of the dams and the power houses should be chosen so that the old stations can be kept in operation as much as possible of the construction time.

A horizontal bulb turbine of conventional design is a suitable turbine installation in each one of the two new power houses. The turbine has a propeller runner with movable blades and distributor with movable vanes.

For equal discharge the two units should have different dimensions. The lower head at Buck requires a somewhat larger turbine dimension than the higher head at Byllesby. However, in order to simplify the design and the manufacturing of turbines and electrical equipment the two units are proposed to be made identical.

Technical data are as follows:

	<u>Byllesby</u>	<u>Buck</u>
1. Rated full load discharge	5300 cfs	5300 cfs
2. Rated head	56 feet	43 feet
3. Turbine runner diameter	4500 mm	
	14,76 feet	14,76 feet
4. Synchronous speed	138,5 rpm	128,6 rpm
5. Submergence of runner	24 feet	18 feet
	below TWL	below TWB

6. Generator output at 5300 cfs and rated head	22740 kW	17250 kW
7. Possible production of kWh/year. New River flow duration curve	77 million	62 million
8. Cross section drawing	3T 87399	3T 87401
9. General arrangement drawing	4T 87398	3T 87400
10. Performance diagram	5T 87404	5T 87405

Purchase prices for the turbine and electrical equipment are estimated as follows:

Price per turbine \$ 2.060.000

Price per generator and accessory
equipment \$ 1.260.000

The above prices do not include erection.

Required erection time estimated as follows:

Turbine hours 12000

Generator and accessory
electrical equipment hours 8000

The outline of the proposed new bulb turbine units is based on model tests performed in Anstalt fuer Stroemungs-maschinen in Graz, Austria (ASTROE) for BOFORS-NOHAB participation in the Altenwoerth project.

The hill diagram 5T 803191 shows the model test result.

The full load discharge is chosen to 5300 cfs which corresponds to a 5% of time flow in New River. At lower discharges the unit will be operated at part load.

The runner diameter 4500 mm is selected on the basis of a suitable specific loading of the turbine.

The synchronous speed is chosen to an RPM which, converted to n_{11} leads to an optimum speed in the model hill diagram.

The n_{11} speed at rated heads amounts to:

Byllesby:

Buck:

$$n_{11} = 138,5 \frac{4,500}{\sqrt{17,07}} = 150,9 \text{ rpm}$$

$$n_{11} = 128,6 \frac{4,500}{\sqrt{13,11}} = 159,8 \text{ rpm}$$

The prototype efficiency curves 5T 87404 and 5T 87405 are designed on the basis of the above mentioned hill diagram 5T 803191.

1. The discharge conversion follows the expression:

$$Q = Q_{11} \cdot (D)^2 \sqrt{H} \text{ i.e. } Q = Q_{11} \cdot (4,50) \sqrt{56.0,3048}$$

2. The efficiency step-up is made according to Huttons formula

i.e.

$$\frac{1 - \eta_p}{1 - \eta_m} = 0,25 + 0,75 \left[\frac{D_m}{D_p} \frac{\nu_p}{\nu_m} \sqrt{\frac{H_m}{H_p}} \right]^{1/5}$$

where prefix m refers to the model data and prefix p to the prototype.

ν is the kinematic viscosity, i.e., a function of the water temperature.

3. The calculation of the required draft head, in this case the submergence of the runner, follow the empirical formula:

$$\sigma = 0,12 (n_{11})^2 \cdot 10^{-4} + 0,20 \cdot (Q_{11})^2$$

where

σ = Cavitation number according to Thoma

n_{11} and Q_{11} according to previous definition

4. The calculation of the possible production of kilowatt hours per year is based on the New River flow duration curve No. 5T 87395.

Drwg 3T 87399, Byllesby, Turbine cross section

Drwg 3T 87401, Buck, Turbine cross section

Drwg 4T 87398, Byllesby, Arrangement drawing

Drwg 4T 87400, Buck, Arrangement drawing

Drwg 5T 87404, Byllesby, Performance diagram

Drwg 5T 87405, Buck, Performance diagram

Drwg 5T 803191, Byllesby and Buck Model Test Hill Diagrams

4T87398

DATE	7/02/21	PROJECT	FEASIBILITY ASSESSMENT STUDY
BY	CEL	PROJECT	BYLESBY HYDRO PLANT
APPROVED	[Signature]	PROJECT	POWERSTATION WITH SINGLE BULB TURBINE
SCALE	1:200	PROJECT	
THE DESIGN ACCORDING TO THIS DRAWING IS THE PROPERTY OF NADCOYST & HOLDING AND MUST NOT BE REPRODUCED OR USED IN ANY MANNER WITHOUT THE WRITTEN CONSENT OF NADCOYST & HOLDING. ANY INFRINGEMENT WILL BE PROSECUTED.		NOTES:	

[illegible]

PROJECT	DATE	NAME OF PARTY	MATERIAL FED. TAX ID NO.	PLANT SYMBOL MOUNTING	D. BY	NOTES
	7/20/21	CELE	FEAS 3 LITY ASSESSMENT STUDY			
		BUCK HYDRO PLANT				
	APPROVED	POWER STATION WITH SINGLE BULB TURBINE				
	DATE	7/20/21				

BUCK POWER STATION
BULB TURBINE UNIT
HEAD = 43 FEET

R 332 K/4-39.33-340
RÖRTURBIN ALTENWÖRTH
PROVFALLHÖJD: 6.3 → 12.7 M
MUSSELDIAGRAM

ASTRÖ
17.10.72 *Ln*
ST. 803191

BYLLESBY POWER STATION
BULB TURBINE UNIT
HEAD = 56 FEET

R 332 K/4-39.33-340
RÖRTURBIN ALTENWÖRTH
PROVFALLHÖJD = 6.3 → 12.7 M
MUSSELDIAGRAM

ASTRÖ
17.10.72 *Ln*
ST. 803191

79.02.21	79.02.21	1:25	
FEASIBILITY ASSESSMENT STUDY - BUCK HYDRO PLANT			
POWERSTATION WITH SINGLE BULB TURBINE - CROSS SECTION.			
BOFORS <small>HYDRO</small>			
3T87401			

100
95
90
85
80
EFFICIENCY PERCENT

75.000
20.000
15.000
10.000
OUTPUT KILOWATTS

50

100

150

TURBINE DISCHARGE m^3/s

TURBINE EFFICIENCY

OVERALL EFFICIENCY

TURBINE OUTPUT

GENERATOR OUTPUT

BYLLESBY HYDRO PLANT
POWER STATION WITH BULD TURBINE
HEAD = 56 FEET SPEED = 138.5 RPM
PERFORMANCE DIAGRAM

5407-0200
87
FEBR 1979
ST. 87404

TROLLHÄTTAN
SWEDEN

BUCK HYDRO PLANT
POWER STATION WITH BULO TURBINE
HEAD = 43 FEET SPEED = 128.6 RPM
PERFORMANCE DIAGRAM

5407-0200
FEBR. 1979
5T. 87405

BOFORS
NONAB

APPENDIX B

UPGRADING ALTERNATIVES

AND COST ESTIMATES

UPGRADING ALTERNATIVES AND COST ESTIMATES

 I. BYLLESBY

<u>Alternative</u>	<u>Description</u>	<u>Annual Energy Increase KWH</u>
I	New runners	9,500,000
II	Replace flashboards by gates (1)	2,133,751
III	Replace flashboards by gates (2)	3,062,751

Alternative I

<u>Item</u>	<u>Units</u>	<u>Qty</u>	<u>Unit Costs \$</u>	<u>Total Costs \$</u>
Runners		4	230,000	920,000
Installation	mnhrs	10,200	15	153,000
Contingency 10%				107,300
Road preparation			L.S.	1,000
Slide fill	cu yds	200	2.75	550
Slide excavation	cu yds	300	4.--	1,200
Access bridge			L.S.	250,000
Contingency 15%				37,912
Generator rewinding and modification		4	200,000	800,000
Contingency 10%				80,000
Sub total				2,350,962
Engineering and administration fees 15%				352,644
Sub total				2,703,606
Allowance for funds during construction (includes interest) AFDC 5.5%				148,698
TOTAL				2,852,304

Alternative 11

<u>Item</u>	<u>Units</u>	<u>Qty</u>	<u>Unit Costs \$</u>	<u>Total Costs \$</u>
Pelican gates and controls	10'X 31.33	1	L.S.	203,000
Contingency 10%				20,300
Mobilization			L.S.	5,000
Removal spillway (crane)	day	30	400.-	12,000
Labor	mnhr	960	10	9,600
Concrete modification	cu yd	6	250.-	1,500
Contingency 15%				4,215
		Sub total		255,617
Engineering and administration fees 15%				38,342
		Sub total		293,957
Add AFDC 5.5%				16,168
		TOTAL		310,125

Alternative III

<u>Item</u>	<u>Units</u>	<u>Qty</u>	<u>Unit Costs \$</u>	<u>Total Costs \$</u>	
Pelican gates and controls	10'X	31.33	2	L.S.	362,000
Contingency 10%					36,200
Mobilization					5,000
Removal spillway bridge (crane)	day	30	400.-		12,000
Labor	mnhr	1,120	10.-		11,200
Concrete modification	cu yd	12	250.-		3,000
Contingency 15%					4,680
			Sub total		434,080
Engineering and administration fees	15%				65,112
			Sub total		499,192
AFDC 5.5%					27,455
			TOTAL		526,647

2. BUCK

<u>Alternative</u>	<u>Description</u>	<u>Annual Energy Increase KWH</u>
I	New runners	6,050,000
II	Addition of one small scale hydro power unit	1,974,000
III	Flashboard replacement	1,338,838
IV	Three feet head increase	6,628,838

Alternative I

<u>Item</u>	<u>Units</u>	<u>Qty</u>	<u>Unit Costs \$</u>	<u>Total Costs \$</u>
Runners		3	230,000	690,000
Installation	mnhrs	7,650	15	114,750
Contingency 10%				80,475
Reinforce access bridge	lbs	60,000	.60	36,000
Temporary supports		8,880	.20	1,776
Mobilization			L.S.	5,000
Crane rental (2)	day	30	800	24,000
Labor	mnhrs	2,400	10	24,000
Barge mobilization			L.S.	10,000
Contingency 15%				16,067
Modification generators		3	200,000	600,000
Contingency 10%				60,000
Sub total				1,668,404
Engineering and administration fees 15%				250,261
Sub total				1,918,665
Allowance for funds during construction (includes Interest AFDC 5.5%)				105,526
TOTAL				2,024,191

Alternative 11

<u>Item</u>	<u>Units</u>	<u>Qty</u>	<u>Unit Costs \$</u>	<u>Total Costs \$</u>
Small scale hydro unit, including gearbox butterfly valve, generator, transformer, controls.		1	L.S.	390,000
Penstock	meters	15	3,000	45,000
Erection penstock	mnhrs	900	15	13,500
Solid state excitation			L.S.	90,000
Installation of excitation			L.S.	60,000
Contingency 10%				59,850
Existing turbine removal	cu yds	210	250	52,500
Penstock concrete rem.	cu yds	200	250	50,000
Penstock concrete rem.	cu yds	45	1,000	25,000
Miscellaneous concrete		50	500	25,000
Forebay cofferdam			L.S.	250,000
Removal cofferdam			L.S.	62,500
Tailrace cofferdam			L.S.	100,000
Removal tailrace cofferdam			L.S.	25,000
Stoplogs & guides			L.S.	18,000
Access bridge			L.S.	107,112
Contingency 15%				110,227
Sub total				1,503,729
Engineering and administration fees				225,559
Sub total				1,729,288
AFDC 9.5%				164,282
TOTAL				1,893,570

Alternative III

<u>Item</u>	<u>Units</u>	<u>Qty</u>	<u>Unit Costs \$</u>	<u>Total Costs \$</u>
Pelican gates and controls	9'X 31.33'	3	L.S.	486,000
Contingency 10%				48,600
Access bridge				107,112
Concrete work	cu yds	18	250	4,500
Labor	mnhrs	960	10	9,600
Extra barge work	days	15	128	1,920
Crane	days	15	400	6,000
Contingency 15%				19,370
		Sub total		683,102
Engineering and administration fees	15%			102,465
		Sub total		785,567
AFDC 5.5%				43,206
		TOTAL		828,773

Alternative IV

<u>Item</u>	<u>Units</u>	<u>Qty</u>	<u>Unit Costs \$</u>	<u>Total Costs \$</u>
Pelican gates, controls 12'X 30.33'		6	L.S.	1,046,000
Contingency 10%				104,600
Mobilization				60,000
Crane rental	day	30	800	24,000
Barge rental	month	1	L.S.	6,336
Labor, bridge	mnhrs	3,000	10	30,000
Precast bridge sections	cu yd	210	200	42,000
Placement	cu yd	660	200	132,000
Cranes for gates	day	45	400	18,000
Barge	day	45	128	5,760
Concrete work	cu yd	36	250	9,000
Labor gates	mnhrs	1,440	10	14,400
Spillway anchoring	ft	6,000	30	180,000
Flashboard replacement			L.S.	62,500
Miscellaneous			L.S.	10,000
Clearing			L.S.	900
Grading	cu yd	1,000	3	3,000
Fill material	cu yd	3,340	6	20,040
Stone surface roads	ton	778	5	3,890
Material removal	cu yd	1,058	3	3,150
Concrete work	cu yd	11	150	1,650
Gate and fence			L.S.	1,000
Grouting			L.S.	7,000
Powerhouse concrete	cu yd	400	250	100,000
Flash rack mod.	lbs	15,480	.89	14,098
Miscellaneous			L.S.	2,000
Contingency 15%				105,859
Generator upgrading		3	200,000	600,000
Contingency 10%				60,000
Sub total				2,622,183
Engineering and administration fees 15%				393,327
Sub total				3,015,510
AFDC 9.5%				286,473
TOTAL				3,301,983

BOFORS
NOHAS

APPENDIX C

COMPUTER PRINT-OUTS

HYDRO FEASIBILITY

ANALYSIS. (AEP)

APPENDIX CINTRODUCTION

The computer program, HYD, calculates the levelized annual benefits of hydroelectric plants. Benefits include two main components, capacity benefits, or value of the investment in coal-fired steam plants that is pre-empted by the operation of a hydroelectric plant, and generation benefits, or value of production costs for a coal-fired steam plant that is pre-empted by the operation of a hydroelectric plant. The HYD program is capable of evaluating baseload and peaking components of hydro capacity, but since the Byllesby/Buck project operates essentially on a run of river basis, all capacity is considered base load capacity in the evaluations. Similarly, the value of generation can be determined by applying off-peak rates to the off-peak portion of generation, and peaking rates to the peak period portion of generation. However, since Byllesby/Buck generation is entirely evaluated at the rate for base-load generation, both components of generation are arbitrarily combined into the off-peak category.

INPUT DATA

Hydro project characteristics:

- . Baseload capacity rating - MW (Average hourly output for run of river operation)
- . Peaking capacity rating - MW (Not used)
- . Off-peak generation - MWH (Total annual generation)
- . Peak-period generation (Not used)

Economic parameters:

- . Life of project - years (40 years for reconditioned plant.
Examined 15 and 40 years for existing plant)
- . Discount rate = .11

Base-load generating capacity investment parameters:

- . Base-load availability adjustment = 1.15
(Accounts for the higher availability of the hydro project as compared to an alternative steam plant)
- . Base-load capacity cost = \$600/KW (1979 dollars)
- . Base-load capacity carrying charge rate = .18
- . Transmission equip. cost for base-load gen. cap. = \$100/KW (1979 dollars)
- . Transmission equip. carrying charge rate = .19
- . Fractional transmission loss = .03

Off-peak generation cost parameters:

- . Off-peak fuel cost = \$13./MWH (1979 dollars)
- . Off-peak fuel cost escalation rate = .08
- . Off-peak O&M cost = \$1./MWH (1979 dollars)
- . Off-peak O&M cost escalation rate = .08

DESCRIPTION OF PROGRAM CALCULATIONS

(Sample calculation evaluates addition of new runners at Byllesby)

ANNUAL BENEFITS OF HYDROELECTRIC PROJECT:

Base-load capacity benefit = \$1,321,472

= carrying charges on capacity investment (A)

+ carrying charges on transmission equip. investment (B)

+ carrying charges on coal stock investment (C)

+ 3% to cover transmission loss related investment (D)

Peaking capacity benefit - not used

Levelized off-peak generation benefit = \$2,695,748.

= levelized annual fuel costs (E)

+ levelized annual operation & maintenance costs (F)

+ 3% to cover energy lost in transmission (G)

Levelized peak period generation benefit - not used

Total Annual Benefit = \$4,017,220

CAPACITY BENEFIT CALCULATION:

Base load:

Generating Capacity (carrying charges) = \$1,068,119 (A)

= Capacity rating X avail. adj. X installed cost X 1000 KW/MW X C.C. rate

= 8.60 MW X 1.15 X \$600/KW X 1000 KW/MW X .18

Transmission Equipment (carrying charges) = \$187,910 (B)

= Capacity rating X avail. adj. X installed cost X 1000 KW/MW X C.C. rate

= 8.60 MW X 1.15 X \$100/KW X 1000 KW/MW X .19

Peaking:

Generating Capabity (carrying charges) - not used

Transmission Equipment (carrying charges) - not used

Operation & Maintenance Cost Benefit + \$186,945 (F)
 = Generation off peak + O&M cost X levelization factor
 + 75,400 MWH X \$1/MWH X 2.479

Peaking:

Fuel Cost Benefit - not used

Operation & Maintenance Cost Benefit - not used

Other:

Off-Peak Energy Related Transmission Loss = \$78,516 (G)
 = (off peak fuel cost benefit + O&M Benefit) X fractional transmission loss
 = (E + F) X .03
 + (\$2,430,287 + \$186,945) X .03

Peaking Energy Related Transmission Loss - not used

Total Other = \$ 78,516

Total Annual Generation Benefit = \$2,695,748

= E + F + G

Total Annual Benefit = \$4,017,220

Total Annual Capacity Benefit 1,321,472

+ Total Annual Generation Benefit 2,695,748

Other:

Base-load Fuel Stock Invest. (car.chg.) = \$26,955 (C)

= 1/4 years X off peak fuel cost X off peak generation X cost of money

= .25 yr. X \$14/MWH X 75,400 MWH/Yr. X .11

Peaking Fuel Stock Invest. (Car.Chg.) - not used

Base-load capacity - Related Transmission Loss Costs = \$38,489. (D)

= (Capacity carrying charges + transmission carrying charges

+ fuel stock carrying charges) X fractional transmission loss

= (A + B + C) X .03

= (\$1,068,119 + \$187,910 + \$26,955) X .03

Peaking Capacity - Related Transmission Loss Cost - not used

Total Other = C + D = \$ 65,445

Total Annual Capacity Benefit = \$ 1,321,472

= A + B + C + D

GENERATION BENEFIT CALCULATION:

Values are levelized annual costs, that is, the cost during the initial year multiplied by a levelization factor. d = discount rate, e = escalation rate, and $r = (1+d)/(1+e)-1$.

$$\text{Levelization factor} = \frac{\left[1 + \frac{\{(1+r)^n - 1\}}{r(1+r)^n} \right]}{\left[1 + \frac{\{(1+d)^n - 1\}}{d(1+d)^n} \right]}$$

Off Peak:

Fuel Cost Benefit = \$ 2,430,287 (E)

= Generation off peak X fuel cost X leveliz. factor

= 75,400 MWH X \$13/MWH X 2.479

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT

BYLLESBY
EXISTING PLANT

BASE LOAD CAPACITY BENEFIT	\$	1152500.
PEAKING CAPACITY BENEFIT	\$	0.
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	1484513.
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.
TOTAL BENEFIT	\$	2637013.

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	7.50	1.15	600.00	.180	931499.3
TRANSMISSION	7.50	1.15	100.00	.190	163874.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS.LOSS & COAL STOCK INV.)	--	--	--	--	57127.2
TOT.ANN.CAPACITY BENEFIT	--	--	--	--	1152501.0

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	65900.0	13.00	.080	1.562	1338327.0
OPER & MAINT COST	65900.0	1.00	.080	1.562	102948.3
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	1.562	.0
OPER & MAINT COST	.0	1.00	.080	1.562	.0
OTHER:					
TRANS.LOSS	--	--	--	--	43238.3
TOT.ANN.ENERGY BENEFIT	--	--	--	--	1484513.0
TOTAL ANNUAL BENEFIT					2637013.0

NOTE: (1) BASED ON 15 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

BYLLESBY

NEW RUNNERS

BASE LOAD CAPACITY BENEFIT	\$	1321472.	MODIFIED DRAFT TUBES AND WICKET GATES AND UPGRADED GENERATORS
PEAKING CAPACITY BENEFIT	\$	0.	
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	2695748.	
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.	
TOTAL BENEFIT	\$	4017220.	

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	8.60	1.15	600.00	.180	1068119.0
TRANSMISSION	8.60	1.15	100.00	.190	187909.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS.LOSS & COAL STOCK INV.)	--	--	--	--	65445.0
TOT.ANN.CAPACITY BENEFIT	--	--	--	--	1321472.0

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	75400.0	13.00	.080	2.479	2430287.0
OPER & MAINT COST	75400.0	1.00	.080	2.479	186945.1
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	2.479	.0
OPER & MAINT COST	.0	1.00	.080	2.479	.0
OTHER:					
TRANS.LOSS	--	--	--	--	78516.9
TOT.ANN.ENERGY BENEFIT	--	--	--	--	2695748.0

TOTAL ANNUAL BENEFIT 4017220.0

NOTE: (1) BASED ON 40 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

BUCK

REPLACE FLASHBOARDS
BY PELICAN GATES

BASE LOAD CAPACITY BENEFIT	\$	823596.
PEAKING CAPACITY BENEFIT	\$	0.
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	1057383.
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.
TOTAL BENEFIT	\$	1880979.

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	5.36	1.15	600.00	.180	665711.4
TRANSMISSION	5.36	1.15	100.00	.190	117115.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS. LOSS & COAL STOCK INV.)	--	--	--	--	40768.9
TOT. ANN. CAPACITY BENEFIT	--	--	--	--	823596.1

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	46939.0	13.00	.080	1.562	953258.7
OPER & MAINT COST	46939.0	1.00	.080	1.562	73327.6
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	1.562	.0
OPER & MAINT COST	.0	1.00	.080	1.562	.0
OTHER:					
TRANS. LOSS	--	--	--	--	30797.6
TOT. ANN. ENERGY BENEFIT	--	--	--	--	1057383.0

TOTAL ANNUAL BENEFIT

1880979.0

NOTE: (1) BASED ON 15 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

BUCK

MODIFIED EQUIPMENT
ADDITION SMALL SCALE
UNIT AND FOREBAY
ELEVATION

BASE LOAD CAPACITY BENEFIT	\$	1060317.
PEAKING CAPACITY BENEFIT	\$	0.
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	2169183.
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.
TOTAL BENEFIT	\$	3229500.

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	6.90	1.15	600.00	.180	856979.2
TRANSMISSION	6.90	1.15	100.00	.190	150764.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS.LOSS & COAL STOCK INV.)	--	--	--	--	52573.3
TOT.ANN.CAPACITY BENEFIT	--	--	--	--	1060317.0

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	60672.0	13.00	.080	2.479	1955575.0
OPER & MAINT COST	60672.0	1.00	.080	2.479	150428.8
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	2.479	.0
OPER & MAINT COST	.0	1.00	.080	2.479	.0
OTHER:					
TRANS.LOSS	--	--	--	--	63180.1
TOT.ANN.ENERGY BENEFIT	--	--	--	--	2169183.0
TOTAL ANNUAL BENEFIT					3229500.0

NOTE: (1) BASED ON 40 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

BYLLESBY
FLASHBOARDS

BASE LOAD CAPACITY BENEFIT	\$	1213801.	REPLACED BY GATES
PEAKING CAPACITY BENEFIT	\$	0.	
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	1553512.	
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.	
TOTAL BENEFIT	\$	2767313.	

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	7.90	1.15	600.00	.180	981179.2
TRANSMISSION	7.90	1.15	100.00	.190	172614.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS.LOSS & COAL STOCK INV.)	--	--	--	--	60007.7
TOT.ANN.CAPACITY BENEFIT	--	--	--	--	1213801.0

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	68963.0	13.00	.080	1.562	1400532.0
OPER & MAINT COST	68963.0	1.00	.080	1.562	107733.2
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	1.562	.0
OPER & MAINT COST	.0	1.00	.080	1.562	.0
OTHER:					
TRANS.LOSS	--	--	--	--	45247.9
TOT.ANN.ENERGY BENEFIT	--	--	--	--	1553512.0

TOTAL ANNUAL BENEFIT 2767313.0

NOTE: (1) BASED ON 15 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

BUCK

MODIFIED EQUIPMENT
ADDITION SMALL SCALE
UNIT AND GATES

BASE LOAD CAPACITY BENEFIT	\$	967956.
PEAKING CAPACITY BENEFIT	\$	0.
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	1965072.
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.
TOTAL BENEFIT	\$	2933028.

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	6.30	1.15	600.00	.180	782459.2
TRANSMISSION	6.30	1.15	100.00	.190	137654.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS. LOSS & COAL STOCK INV.)	--	--	--	--	47842.2
TOT. ANN. CAPACITY BENEFIT	--	--	--	--	967956.2

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	54963.0	13.00	.080	2.479	1771563.0
OPER & MAINT COST	54963.0	1.00	.080	2.479	136274.1
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	2.479	.0
OPER & MAINT COST	.0	1.00	.080	2.479	.0
OTHER:					
TRANS. LOSS	--	--	--	--	57235.1
TOT. ANN. ENERGY BENEFIT	--	--	--	--	1965072.0

TOTAL ANNUAL BENEFIT

2933028.0

NOTE: (1) BASED ON 40 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

BUCK

EXISTING PLANT

BASE LOAD CAPACITY BENEFIT	\$	799034.
PEAKING CAPACITY BENEFIT	\$	0.
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	1027221.
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.
TOTAL BENEFIT	\$	1826254.

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	5.20	1.15	600.00	.180	645839.6
TRANSMISSION	5.20	1.15	100.00	.180	113619.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.180	.0
OTHER (TRANS. LOSS & COAL STOCK INV.)	--	--	--	--	39574.8
TOT. ANN. CAPACITY BENEFIT	--	--	--	--	799034.3

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	45600.0	13.00	.080	1.562	926065.7
OPER & MAINT COST	45600.0	1.00	.080	1.562	71235.8
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	1.562	.0
OPER & MAINT COST	.0	1.00	.080	1.562	.0
OTHER:					
TRANS. LOSS	--	--	--	--	29919.0
TOT. ANN. ENERGY BENEFIT	--	--	--	--	1027220.5
TOTAL ANNUAL BENEFIT					1826254.0

NOTE: (1) BASED ON 15 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

		<u>BUCK</u>	
		NEW RUNNERS	
		MODIFIED DRAFT TUBES	
		AND WICKET GATES AND	
		UPGRADED GENERATORS	
BASE LOAD CAPACITY BENEFIT	\$	906564.	
PEAKING CAPACITY BENEFIT	\$	0.	
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	1846622.	
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.	
TOTAL BENEFIT	\$	2753186.	

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	5.90	1.15	600.00	.180	732779.5
TRANSMISSION	5.90	1.15	100.00	.190	128914.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS.LOSS & COAL STOCK INV.)	--	--	--	--	44869.7
TOT.ANN.CAPACITY BENEFIT	--	--	--	--	906564.0

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	51650.0	13.00	.080	2.479	1664778.0
OPER & MAINT COST	51650.0	1.00	.080	2.479	128059.9
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	2.479	.0
OPER & MAINT COST	.0	1.00	.080	2.479	.0
OTHER:					
TRANS.LOSS	--	--	--	--	53785.1
TOT.ANN.ENERGY BENEFIT	--	--	--	--	1846622.0

TOTAL ANNUAL BENEFIT 2753186.0

NOTE: (1) BASED ON 40 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

BUCK

INSTALL SMALL SCALE

BASE LOAD CAPACITY BENEFIT	\$	834361.	HYDRO POWER UNIT
PEAKING CAPACITY BENEFIT	\$	0.	
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	1700894.	
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.	
TOTAL BENEFIT	\$	2535254.	

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	5.43	1.15	600.00	.180	674405.8
TRANSMISSION	5.43	1.15	100.00	.190	118645.4
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS. LOSS & COAL STOCK INV.)	--	--	--	--	41309.5
TOT. ANN. CAPACITY BENEFIT	--	--	--	--	834360.6

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	47574.0	13.00	.080	2.479	1533401.0
OPER & MAINT COST	47574.0	1.00	.080	2.479	117953.9
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	2.479	.0
OPER & MAINT COST	.0	1.00	.080	2.479	.0
OTHER:					
TRANS. LOSS	--	--	--	--	49540.6
TOT. ANN. ENERGY BENEFIT	--	--	--	--	1700894.0
TOTAL ANNUAL BENEFIT					2535254.0

NOTE: (1) BASED ON 40 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

BUCK

BASE LOAD CAPACITY BENEFIT	\$	937377.	MODIFIED HYDRO EQUIPMENT AND ADDITION OF SMALL SCALE HYDRO UNIT
PEAKING CAPACITY BENEFIT	\$	0.	
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	1917198.	
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.	
TOTAL BENEFIT	\$	2854574.	

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	6.10	1.15	600.00	.180	757619.1
TRANSMISSION	6.10	1.15	100.00	.190	133284.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS.LOSS & COAL STOCK INV.)	--	--	--	--	46472.8
TOT.ANN.CAPACITY BENEFIT	--	--	--	--	937376.8

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	53624.0	13.00	.080	2.479	1728404.0
OPER & MAINT COST	53624.0	1.00	.080	2.479	132954.2
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	2.479	.0
OPER & MAINT COST	.0	1.00	.080	2.479	.0
OTHER:					
TRANS.LOSS	--	--	--	--	55840.7
TOT.ANN.ENERGY BENEFIT	--	--	--	--	1917198.0

TOTAL ANNUAL BENEFIT 2854574.0

NOTE: (1) BASED ON 40 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

BUCK

MODIFIED EQUIPMENT
AND FLASHBOARDS
REPLACED BY GATES

BASE LOAD CAPACITY BENEFIT	\$	922100.
PEAKING CAPACITY BENEFIT	\$	0.
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	1894495.
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.
TOTAL BENEFIT	\$	2816594.

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	6.00	1.15	600.00	.180	745199.2
TRANSMISSION	6.00	1.15	100.00	.190	131099.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS. LOSS & COAL STOCK INV.)	--	--	--	--	45800.8
TOT. ANN. CAPACITY BENEFIT	--	--	--	--	922099.9

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	52989.0	13.00	.080	2.479	1707937.0
OPER & MAINT COST	52989.0	1.00	.080	2.479	131379.8
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	2.479	.0
OPER & MAINT COST	.0	1.00	.080	2.479	.0
OTHER:					
TRANS. LOSS	--	--	--	--	55179.5
TOT. ANN. ENERGY BENEFIT	--	--	--	--	1894495.0
TOTAL ANNUAL BENEFIT					2816594.0

NOTE: (1) BASED ON 40 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * *

BUCK

MODIFIED EQUIPMENT

AND FOREBAY EL. INCR.

BY 3 FEET

BASE LOAD CAPACITY BENEFIT	\$	1029504.
PEAKING CAPACITY BENEFIT	\$	0.
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	2098643.
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.
TOTAL BENEFIT	\$	3128147.

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE-LOAD:					
GENERATING CAPABILITY	6.70	1.15	600.00	.180	832139.1
TRANSMISSION	6.70	1.15	100.00	.190	146394.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS. LOSS & COAL STOCK INV.)	--	--	--	--	50970.5
TOT. ANN. CAPACITY BENEFIT	--	--	--	--	1029504.4

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	58699.0	13.00	.080	2.479	1891981.0
OPER & MAINT COST	58699.0	1.00	.080	2.479	145537.0
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	2.479	.0
OPER & MAINT COST	.0	1.00	.080	2.479	.0
OTHER:					
TRANS. LOSS	--	--	--	--	61125.5
TOT. ANN. ENERGY BENEFIT	--	--	--	--	2098643.0

TOTAL ANNUAL BENEFIT

3128147.0

NOTE: (1) BASED ON 40 YEAR LIFE AND 11.0% DISCOUNT RATE

* * ANNUAL BENEFITS OF HYDROELECTRIC PROJECT * 4

BUCK

FOREBAY ELEVATION
INCREASED 3 FEET

BASE LOAD CAPACITY BENEFIT	\$	921820.
PEAKING CAPACITY BENEFIT	\$	0.
LEVELIZED OFF-PEAK GENERATION BENEFIT	\$	1176549.
LEVELIZED PEAK PERIOD GENERATION BENEFIT	\$	0.
TOTAL BENEFIT	\$	2098369.

CAPACITY BENEFIT CALCULATION

	CAPACITY RATING MW	AVAIL ADJ	INSTALLED COST \$/KW	CARRYING CHARGE RATE	ANNUAL CAPACITY BENEFIT \$
BASE LOAD:					
GENERATING CAPABILITY	6.00	1.15	600.00	.180	745199.2
TRANSMISSION	6.00	1.15	100.00	.190	131099.9
PEAKING:					
GENERATING CAPABILITY	.00	1.15	600.00	.180	.0
TRANSMISSION	.00	1.15	100.00	.190	.0
OTHER (TRANS. LOSS & COAL STOCK INV.)	--	--	--	--	45521.0
TOT. ANN. CAPACITY BENEFIT	--	--	--	--	921820.1

GENERATION BENEFIT CALCULATION(1)

	GENERATION MWH	INITIAL VALUE \$/MWH	ESCA- LATION RATE	LEVEL- IZATION FACTOR	ANNUAL GENERATION BENEFIT \$
OFF PEAK:					
ENERGY (FUEL) COST	52229.0	13.00	.080	1.562	1060690.0
OPER & MAINT COST	52229.0	1.00	.080	1.562	81591.4
PEAKING:					
ENERGY (FUEL) COST	.0	13.00	.080	1.562	.0
OPER & MAINT COST	.0	1.00	.080	1.562	.0
OTHER:					
TRANS. LOSS	--	--	--	--	34268.4
TOT. ANN. ENERGY BENEFIT	--	--	--	--	1176549.0

TOTAL ANNUAL BENEFIT

2098369.0

NOTE: (1) BASED ON 15 YEAR LIFE AND 11.0% DISCOUNT RATE