DOE/ER/53276--4

DE92 008647

Technical Progress Report

Colorado School of Mines Fusion Gamma Ray Diagnostic Project

DE-FG02-88ER53276

Principal investigator

F. Edward Cecil

Professor of Physics

Colorado School of Mines

February 14, 1992

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

SUMMARY

This report summarizes the 1991 calendar year activities of the fusion gamma ray diagnostics project in the physics department at the Colorado School of Mines. This project is supported by the U. S. Department of Energy through research grant #DE-87ER-53276. In addition, the experimental work being carried out at TFTR is supported in part by DOE Contract # DE-AC02-76CH03073, and relies heavily upon our on-going collaboration with Dr. Sid Medley of the TFTR team.

Considerable progress has been realized in the fusion gamma ray diagnostic project in the last year. Specifically we have achieved the two major goals of the project as outlined in last year's proposed work statement to the Office of Applied Plasma Physics in the DOE Division of Magnetic Fusion Energy. The two major goals were:

- i. Solution of the severe interference problem encountered during the operation of the gamma ray spectrometer concurrent with high power levels of the neutral beam injectors (NBI) and the ICRH antennae.
- ii. Experimental determination of the absolute detection efficiency of the gamma ray spectrometer. This detection efficiency will allow the measured yields of the gamma rays to be converted to a total reaction rate.

In addition to these two major accomplishments, we have continued, as permitted by the TFTR operating schedule, the observation of high energy gamma rays from the ${}^3\text{He}(\text{D},\gamma){}^5\text{Li}$ reaction during deuterium NBI heating of ${}^3\text{He}$ plasmas.

1. Solution to the ICRH interference problem

As noted in previous progress reports for our project, the operation of the fusion gamma ray detector on TFTR was severely compromised during ICRH heating in conjunction with NBI heating. The severity of this problem is illustrated in Fig. 1. This behavior is representative of the response of the detector in this environment as the detector was initially configured. The indicated TFTR shot #51787, August 3, 1990, compares the total neutron rate with the total ICRH injected antenna power and one channel of the gamma ray spectrometer, DEG-SCALER[3], giving the counts per 0.5 msec as a function of time into the shot. The gamma ray signal should approximately track the neutron signal since the main source of gamma rays during deuterium NBI into primarily deuterium plasmas will be neutron capture gamma rays in the environment of the spectrometer. The extent of the interference induced by the ICRH is clear as the gamma ray spectrometer is rendered totally useless during the 500 msec time period during which the ICRH power was being injected into the plasma. The severity of the problem is emphasized by the fact that the maximum RF power is relatively low, about 1.8 MW. By tracing along the cable path from the gamma ray spectrometer to the equipment rack in the TFTR basement using a low-power, hand held RF generator, the pick-up was simulated. An additional level of cable shielding was installed and the interference problem appears to have been totally eliminated. Witness TFTR Shot#61964 in Fig. 2. The same digraphs are presented as were given in Fig. 1. In the case of the latter shot, this time with an ICRH power level at 5 MW, the gamma ray count rate approximately tracks that of the neutron production rate as expected with no observable interference or degradation during the 500 msec interval from 3.5 to 4.0 sec into the shot when the ICRH power was being injected into the plasma. We will continue to monitor the response of the gamma ray spectrometer in the presence of increasing ICRH power levels, confident that the present demonstrated level of isolation will remain adequate.

$\times 10^{16}$

ANT61964 01/28/92 16:50

CUPLOT 01/29/92

$\times 10^{16}$

N
E
U
T
R
O
N
S

NEUTRON RATE. SCALER= 4 EFF= $9.600\text{E-}12$ YLD= $8.565\text{E+}15$

M
E
G
A
W
A
T
T

Total Injected Antenna Power

C
O
U
N
T
S

DEG-SCALER[03] Raw Data

Time (Seconds)

2. Measurement of absolute detection efficiency of gamma ray spectrometer

The application of the TFTR fusion gamma ray spectrometer to quantitative analysis of fusion plasma reaction rates requires a knowledge of the absolute detection efficiency of the spectrometer. The absolute detection efficiency will be a product of several factors, some of them dependent on the energy of the gamma ray. These factors are:

1. Effective solid angle;
2. Detection efficiency for a gamma ray entering the scintillator;
3. Attenuation in the port cover;
4. Attenuation in the neutron absorber at the aperture to the detector;
5. Fraction of total plasma volume observed by the detector.

The product of factors 1 and 2 was measured for a gamma ray energy of 4.44 MeV by locating a 1 Curie PuBe source yielding 1.4×10^6 4.44 MeV gamma rays per second at a series of points along a chord tangent to the toroidal axis of the vacuum vessel at the center of bay K and along a vertical axis through the center of the port. The location of the spectrometer relative to this port is indicated in Figure 3. The count rates along these horizontal and vertical scans are shown in Figures 4 and 5. Typical spectra measured with the source in full view of the detector, partially obscured and fully obscured are given in Figure 6. The peak yields plotted in Figures 4 and 5 were extracted from the spectra by taking the total number of counts in the peak region (channels 100 to 130) and subtracting the number of counts in the background immediately adjacent to the peak region (channels 130 to 160).

These measurements were made with the port cover removed. The attenuation of the gamma rays in the port cover, factor 3 in the above list, was determined by measuring the transmission of the 4.44 MeV gamma ray at characteristic locations over the surface of the port. The net attenuation was determined from the individual transmission measurements

FIG. 6

Scan of TFTR Bay K with 4.44 MeV PuBe source

Scan of TFTR Bay K with 4.44 MeV PuBe source

by modelling with a Monte Carlo code which assumed a radial source distribution:

$$[1 - (R/A)^2]^n; \text{ with } A = 70 - 90 \text{ cm. and } n = 6 - 8.$$

For nominal values of the parameters $A = 80$ cm. and $n = 7$, the modelled transmission through the port cover was 0.58. The dependence of the modelled transmission on the parameters A and n away from the minimal values is given in Figures 7 and 8. The transmission varies by no more than a few percent as the parameters A and n vary between 70 - 90 cm. and 6 - 8 respectively.

The attenuation due to the neutron absorber at the entrance to the spectrometer, factor 4, was measured by locating the PuBe source at the front aperture to the spectrometer and comparing the count rates with and without the absorber. A transmission of 0.32 was measured for the absorber at a gamma ray energy of 4.44 MeV.

The fraction of plasma volume observed, factor 5, was determined from the observed length of the toroidal center line (Figure 4) and the known major radius of the torus.

By combining factors 1-5 and assuming that the source gamma rays are uniformly distributed over the azimuth of the torus, a net efficiency of $(8.5 \pm 0.3) \times 10^{-9}$ peak counts per source gamma ray was determined for a gamma ray energy of 4.44 MeV. The uncertainty in the efficiency represents the combined uncertainty due to the statistical uncertainties in the Monte Carlo calculations and the calibration measurements. The actual uncertainty in the efficiency will be somewhat higher, probably at the 10% level by virtue of the uncertainties in the peak definition and background subtraction procedures.

Using the known energy dependence of the mass attenuation coefficients of gamma rays in the port cover, neutron absorber and scintillator materials, the absolute detection efficiency may be extended to higher energies. The efficiencies thus determined are plotted in Figure 9. The fact that the absolute efficiency is only weakly dependent on the gamma ray energy in the range from 4 to 25 MeV is a reflection of the fact that the mass

Monte Carlo Calculation of Port Cover Transmission

Port cover transmission

Monte Carlo Calculation of Port Cover Transmission

Ndet = Ntotal * (abs eff)
Ndet is peak counts in detector
Ntotal is total number of gammas in entire torus
abs eff is plotted quantity

attenuation coefficients go through a broad minimum in this energy range and that what dependence remains tends to cancel in first order since a greater attenuation in the port cover and neutron absorber will tend to be offset by a greater probability of conversion in the scintillator.

The absolute detection efficiency plotted in Figure 9 may be used to estimate the gamma ray peaks counts during plasma operation. If we assume a gamma ray to charged particle branching ratio of 5×10^{-5} for the d-t and d- ^3He reactions, then we would expect a 17 MeV full energy peak count rate of 5000 counts per second at a total reaction rate of 1×10^{16} reactions per second.

3. Spectrometry of gamma rays during d- ^3He operation on TFTR.

During the most recent run period on TFTR, a series of shots were devoted to neutral deuterium beam injection into ^3He plasmas. The fusion gamma ray spectrometer was operational during these shots and spectra were recorded indicating the detection of high energy capture gamma rays from the d- ^3He reaction. There were six ^3He shots and three ^4He shots as controls. The two-dimensional histograms generated with the CENA utility TEXAS for the ^3He and ^4He shots are indicated in Figures 10 and 11. The presence of the high energy gamma rays for the ^3He shots is noted. We are continuing to analyze these data. Results of this analysis and that of comparable shots expected in the next TFTR run period will be presented in future reports.

BOOK IETR GAMMA-RAY DATA

TEXAS 7.3 (11-JAN488AN-907:54FEC_GAMMA REEC

PAGE 200e 3GR: 3D plot of count rate versus energy and time

VERSION 1.0000-LOW 35.0000-RI 0.0000-AL 6.7E-09 FILE 9000:BIAS 7.7E-03 ECRT 30.00
RTF_LO 6.7E-09 F_HI 0.0000 F_AL 6.7E-09 FILE 9000:BIAS 7.7E-03 ECRT 30.00

SHOT LIST

GM: 61581
61584
61585
61587
61614
61615

SET: 5.02

VERSION 1.000000-100 30.000000-100 0.000000-100 30.000000-100 0.000000-100
 G1F_L03.9E+09F-10 0.000000-100 3.9E+09F-10 9000:01AS7.7E-03ECRIT 30.00

SHOT LIST

GM: 61572
 61573
 61574

SET: 4.82

END

DATE
FILMED

4 / 01 / 92

I