10
11/29/92 Am ①

ORNL/CON-334

**OAK RIDGE
NATIONAL
LABORATORY**

**EVALUATION OF THE UTILITIES ENERGY
MONITORING AND CONTROL SYSTEM INSTALLED
AT THE U.S. ARMY, EUROPE, PIRMASENS AND
97TH BASE SUPPORT BATTALION, GERMANY**

Martin A. Broders and Benjamin W. McConnell
Energy Division

January 1992

Prepared by the
OAK RIDGE NATIONAL LABORATORY
Oak Ridge, Tennessee 37831-6285
managed by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U. S. DEPARTMENT OF ENERGY
under Contract No. DE-AC05-84OR21400

**MANAGED BY
MARTIN MARIETTA ENERGY SYSTEMS, INC.
FOR THE UNITED STATES
DEPARTMENT OF ENERGY**

THIS DOCUMENT CONTAINS NEITHER RECOMMENDATIONS NOR
CONCLUSIONS OF THE U.S. GOVERNMENT. IT IS THE PROPERTY OF THE
U.S. GOVERNMENT AND IS LOANED TO YOUR ORGANIZATION; IT AND ITS
CONTENTS ARE NOT TO BE DISTRIBUTED OUTSIDE YOUR ORGANIZATION.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

ORNL/CON--334

DE92 006664

**Evaluation of the Utilities Energy Monitoring and
Control System Installed at the U.S. Army, Europe,
Pirmasens and 97th Base Support Battalion, Germany**

**Martin A. Broders and Benjamin W. McConnell
Energy Division**

January 1992

Prepared for the

**Headquarters, U.S. Army, Europe
Office of the Deputy Chief of Staff, Engineer
Facilities Engineering Division, Utilities and Energy Branch
Heidelberg, Germany**

**Prepared by the
OAK RIDGE NATIONAL LABORATORY
Oak Ridge, Tennessee 37831-6285
managed by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U. S. DEPARTMENT OF ENERGY
under Contract No. DE-AC05-84OR21400**

MASTER

rb

CONTENTS

LIST OF FIGURES	v
LIST OF TABLES	vii
ACKNOWLEDGMENTS	ix
EXECUTIVE SUMMARY	xi
ABSTRACT	xvii
1. INTRODUCTION	1
1.1 BACKGROUND	1
1.2 SCOPE (STATEMENT OF WORK)	1
2. PROJECT DESCRIPTION	3
2.1 GENERAL DESCRIPTION	3
2.1.1 Samsomatic Thermal Energy (District Heating) Monitoring and Control System	3
2.1.2 Landis and Gyr Electric Demand Limiting Ripple Control System	7
2.1.3 Siemens Electrical Energy Monitoring System	7
2.2 SYSTEM PLANNING	7
3. EVALUATION OF PROJECT DOCUMENTATION	11
4. ASSESSMENT OF SITE AND PHYSICAL CONDITIONS	13
4.1 BUNKER HILL VILLAGE	13
4.2 HUSTERHOEH KASERNE (GENERAL)	14
4.3 MUENCHWEILER HOSPITAL COMPLEX	17
5. ANALYSIS OF ENERGY AND COST SAVINGS	19
5.1 ENERGY CONSUMPTION AND SAVINGS TRENDS AT PIRMASENS	19
5.2 BUNKER HILL VILLAGE ENERGY CONSUMPTION AND SAVINGS TRENDS	27
5.3 ELECTRICAL ENERGY CONSUMPTION AND SAVINGS ATTRIBUTED TO UEMCS OPERATIONS	32
5.4 COST SAVINGS ATTRIBUTED TO UEMCS OPERATION	35
6. GENERAL ASSESSMENT OF BENEFITS AND OF MAINTENANCE AND TRAINING	37
6.1 BENEFITS	37
6.2 MAINTENANCE AND TRAINING	37
7. CONCLUSIONS	39

8. RECOMMENDATIONS	41
9. REFERENCES	43

LIST OF FIGURES

Fig. 1.	Samsomatic UEMCS central control console located in Building 4656	4
Fig. 2.	Typical district heating system setup located in Bunker Hill Village family housing unit. (Building 4508)	4
Fig. 3.	Schematic diagram of typical district heating system in Bunker Hill Village . .	5
Fig. 4.	Landis and Gyr ripple control system central control station located in Building 4656	8
Fig. 5.	Typical vehicle storage warehouse dehumidification system setup in Warehouse 4734G	8
Fig. 6.	Control cabinet of dehumidification system with integrated ripple control in Warehouse 4734G	9
Fig. 7.	Siemens electrical energy monitoring system central control station located in Building 4656	9
Fig. 8.	Pirmasens total energy consumption by building, ft ²	21
Fig. 9.	Pirmasens total energy consumption by fuel and energy type	22
Fig. 10.	Pirmasens total energy consumption by major facility	24
Fig. 11.	Pirmasens thermal energy consumption by major facility	26
Fig. 12.	Pirmasens FY 1990 annual energy consumption by major facility and by fuel and energy type	29
Fig. 13.	Pirmasens Bunker Hill Village thermal energy consumption	31
Fig. 14.	Pirmasens electrical power peaks during 1990	33
Fig. 15.	Pirmasens Husterhoeh Kaserne September 1990 daily electrical consumption	34

LIST OF TABLES

Table 1. Pirmasens total energy consumption by fuel and energy type, MBtu/year . . .	20
Table 2. Pirmasens total energy (thermal and electrical) consumption by major facility	23
Table 3. Pirmasens thermal energy consumption by major facility	25
Table 4. Pirmasens FY 1990 energy consumption by major facility and by fuel and energy type, MBtu	28
Table 5. Pirmasens Bunker Hill Village thermal energy consumption	30

ACKNOWLEDGMENTS

The authors would like to acknowledge the help and support of Rudi Hartlieb and Roman Tretter of the Pirmasens and 97th Base Support Battalion in Pirmasens, Germany, and of Jeff Mitchell at Headquarters, U.S. Army Europe in Heidelberg, Germany. We would also like to acknowledge the aid and logistical support provided by Gary Briggs of the Martin Marietta Energy Systems, Inc., European Office, and by Charles Doty of the Martin Marietta Energy Systems, Inc., Data Systems Research Division. The clerical and secretarial support of Donna Penland also was critical to the success of the project. Finally, the document review and technical comments of Mike Gettings and Randy Barnes are deeply appreciated.

EXECUTIVE SUMMARY

Under the provisions of Interagency Agreement DOE No. 1938-B090-A1 between the U.S. Department of Energy (DOE) and the United States Army in Europe (USAREUR), Martin Marietta Energy Systems, Inc., (MMES) is evaluating the overall performance and energy efficiency of the utilities energy monitoring and control systems (UEMCSs) located at U.S. Army installations in Heidelberg, Goeppingen, Pirmasens, and Baumholder, Germany. These evaluations rely upon existing data and information and do not involve introducing metering and instrumentation for measuring installation energy use. This report was prepared by the Oak Ridge National Laboratory (ORNL) and specifically presents the results of the evaluation of the UEMCS installed at USAREUR, 21st Theater Army Area Command (TAACOM), Pirmasens and 97th Base Support Battalion, Pirmasens, Germany.

The U.S. Army military installation at Pirmasens, Germany, consists of a large number of separate installations. The major thrusts of this report are the Husterhoeh Kaserne and the Muenchweiler Hospital Complex, which are the primary installations currently monitored and controlled by existing UEMCSs. Future systems expansion also is planned for these primary installations. The UEMCS currently serving Pirmasens is comprised of three distinctively different and separate systems that are described below.

The first UEMCS is a Samsomatic system and is the principal system installed at Pirmasens. It was not justified, procured, or installed in the classic sense, using a Military Construction Project Data Sheet (Form DD-1391). Neither was it funded as an Energy Conservation Investment Program (ECIP) project. As such, a formal Life Cycle Cost Analysis (LCCA) was not prepared to justify and secure funding for this project. Instead, USAREUR, 21st TAACOM, Pirmasens entered into a contract with Stadtwerke Pirmasens, a local utility, to install at no initial cost to the U.S. Government a hot water district heating (DH) system and an associated Samsomatic UEMCS (DH/UEMCS) for Bunker Hill Village, Husterhoeh Kaserne. The DH/UEMCS will be owned, operated, and maintained by Stadtwerke Pirmasens for a period of 10 years, during which time the U.S. Army will pay for these systems incrementally along with its monthly energy bill. Based on a monthly system payback base rate of 31,430 DM (\$15,332),* the overall cost of these systems after a 10-year payoff period will be 3,771,600 DM (\$1,840,000). The cost of the Samsomatic UEMCS is included in the overall cost of the hot water DH system. At the end of 10 years, ownership of these systems will be transferred to the U.S. Army, which then will be responsible for system operations and maintenance.

The oldest UEMCS at Pirmasens is a Landis and Gyr ripple control system that was installed in 1983. This system serves a demand-limiting function by controlling 100 and 200 kW blocks of dehumidifier load in the vehicle storage area. The system is owned and directly controlled by the electric company, Pfaltzwerke AG; and it consists of a single ripple control receiver in Building 4152, the electrical substation serving the vehicle storage area. The ripple control system activates two contacts at the receiver that, via 24-V control wiring, open

* During FY 1989 and FY 1990, the average rate of exchange was 1 US\$ = 2.05 DM.

a set of relays in the humidity sensors of the dehumidifier control circuits. A total of 722 kW of load is connected in 14 vehicle storage warehouses.

Finally, a Siemens S5-150-U Simatic PG675 monitoring system, which uses twisted pair wire for communications, was installed in 1985. The system monitors kWh at all 25 substations and at an additional 25 key electric consumption points. The system also monitors kW demand and switch status at the Muenchweiler facilities. The Siemens system is the only UEMCS at Pirmasens that was purchased using ECIP funding. No documentation of the LCCA is available.

Pirmasens maintains monthly records of fuel and energy consumption for each of its major installations. While electrical energy consumption essentially has remained constant during the last 5 years, thermal energy use has declined steadily. An overall reduction in total energy consumption (MBtu/year) of over 11% has been achieved during this time period. This steady decrease in thermal energy consumption can be attributed to a combination of energy conservation retrofit measures—including building envelope retrofits and boiler/fuel conversions—and more recently to the installation of the hot water DH/UEMCS in Bunker Hill Village.

Further evaluation of the energy consumption and conservation trends at Pirmasens requires a closer examination of energy use by each major facility or area. Some very interesting trends in comparative energy performance (MBtu/1000 ft²) among the major facilities were observed. First and foremost, the energy performance of Bunker Hill Village is far superior to that of the other comparable facilities, endorsing the benefits derived from building envelope retrofits and DH/UEMCS installation. This illustration also confirms the wisdom of Pirmasens Directorate of Housing and Engineering (DEH) personnel to proceed methodically with future plans to expand DH/UEMCS utilization in both the Kaserne and Muenchweiler areas. Using Bunker Hill Village as a point of reference, energy efficiency (9.29 Btu/HDD^{*}/ft²) during FY 1990 was approximately 39% superior to that of another military family housing community, Saratoga Village (15.35 Btu/HDD/ft²). When compared with the Muenchweiler Hospital Complex (20.26 Btu/HDD/ft²), the energy efficiency of Bunker Hill Village was over 50% superior. It should be noted that the Muenchweiler Hospital Complex area, which is used predominantly for barracks and family housing, is currently undergoing building envelope retrofits and conversion to a hot water DH/UEMCS system.

The major UEMCS installed at Pirmasens is the Samsomatic UEMCS that operates in concert with the hot water DH system that began operation in Bunker Hill Village at the end of FY 1988. A steady decrease in thermal energy consumption has occurred during the time period FY 1985 through FY 1990. This improvement occurred in two distinct phases. First, most of the buildings in Bunker Hill Village (27 of 36 buildings) underwent comprehensive building envelope energy conservation retrofits (e.g., external insulation, multi-pane windows, ceiling insulation) between July 1984 and October 1988. Reduced thermal energy consumption and the resultant energy savings during FY 1985 through FY 1988 can be attributed in major part to this retrofit program. Second, the Bunker Hill Village hot water

* Heating degree-day

DH/UEMCS began operation during September 1988. Therefore, reduced thermal energy consumption and the resultant energy savings that occurred during FY 1989 and FY 1990 can be attributed in major part to combined hot water DH and UEMCS operation in Bunker Hill Village.

In terms of energy efficiency, DEH personnel at Pirmasens can be proud of the fact that they have reduced thermal energy consumption in Bunker Hill Village from 14.66 Btu/HDD/ft² during FY 1985 to 9.29 Btu/HDD/ft² during FY 1990. This is approximately a 37% reduction in thermal energy consumption in just 5 years. Indeed, by comparing FY 1989 and FY 1990, an estimate of the energy savings attributable to the UEMCS operation alone reveals a saving of 10% in energy.

Unlike the earlier UEMCS evaluation at Heidelberg,¹ this evaluation indicates that the potential for saving electrical energy is considerably lower than for saving thermal energy. The facilities at Pirmasens do not present just the relatively heavy electrical load in administrative and support areas. The present system has a winter peak load of about 5500 kW (6000 kW contracted peak), which occurs on weekday mornings. The relatively flat electric load demand during weekdays indicates little opportunity for peak shifting.

The major electric loads at the Husterhoeh Kaserne, and the Muenchweiler Complex are the water plant and pumps, the warehouses and repair shops, the military vehicle storage area, the Autodin, and other communications sites. The key elements of these loads are estimated to be pumps, compressor drives, and other electric motors. However, not all of these elements are associated with space heating, air handling, and air conditioning; since electric load is relatively constant throughout the year. Hence, the opportunity to control these loads in conjunction with the heating, ventilation, and air conditioning (HVAC) systems does not seem reasonable.

Cost savings can be calculated from estimates of savings from night setback of thermostats, night setback of water heater set points, reduced electrical demand, reduced lighting and circulation pump operation, and improved operation and maintenance. Most of these functions, however, are controlled directly either by the local utility (demand reduction) or by local process controllers. Therefore, direct estimates of savings from the UEMCS operation are based on improvements to the system by the UEMCS, which include not only energy savings but also improved monitoring and maintenance.

It is generally understood that energy savings achieved at Bunker Hill Village during FY 1989 and FY 1990 can be attributed in major part to the UEMCS operation in concert with the new hot water DH system. Using the energy savings in FY 1990 for those buildings under DH/UEMCS, the 6-year average of 6490 HDD/year and the 2-year average of 32.4 DM/MBtu for DH cost, an average cost savings of 197,640 DM/year is estimated. For the cost of the UEMCS as presently configured (500,000 DM), a simple payback of about 2.5 years is indicated.

Based on the results of the evaluation of the UEMCS installed at Pirmasens, the following conclusions have been reached:

- The UEMCS operations at Pirmasens are managed and operated by a very knowledgeable and dedicated DEH Utilities Division staff. This staff has done a commendable job in their attempts to reduce energy consumption in Bunker Hill Village with UEMCS equipment that has minimum monitoring and control capabilities and that is not primarily under U.S. Army control.
- Significant reductions in thermal energy consumption have been achieved in Bunker Hill Village as a result of building envelope energy conservation retrofits and of the replacement of coal-fired building heating systems with a UEMCS-controlled hot water DH system. In terms of energy efficiency (Btu/HDD/ft²), thermal energy consumption in Bunker Hill Village has been reduced approximately 37% over a 5-year period.
- The success achieved in Bunker Hill Village clearly demonstrates the potential to save energy at other Pirmasens installations. For example, based on FY 1990 thermal energy consumption data, the energy performance (Btu/HDD/ft²) of Bunker Hill Village is 39% superior to that of Saratoga Village and is over 50% superior to that of the Muenchweiler area.
- In contrast to electrical energy consumption, thermal energy consumption offers the greater potential for overall energy and cost savings for most of the major Pirmasens facilities. Perhaps the most evident candidate for potential energy and cost savings is the Muenchweiler Hospital Complex, where the annual thermal energy consumption during FY 1990 represented about 90% of the total energy consumed by this facility. Building envelope energy conservation retrofits are currently under way, and the installation of a UEMCS-controlled hot water DH system should result in a significant reduction in thermal energy consumption in the Muenchweiler Hospital Complex, if the positive results achieved at Bunker Hill Village are to serve as an indicator.
- The local temperature regulators serving individual or groups of buildings in the Husterhoch Kaserne area, and used primarily for temperature setback, were found to be operating in less than an optimal manner. This undesirable condition can be rectified to a great extent by a planned future UEMCS that will enable thermal energy systems in individual buildings to be monitored and controlled on a continual basis from a central remote location.
- Approximately 37% of the energy savings and 22% of the cost savings attributed to the UEMCS operations at the military community at Heidelberg can be attributed to reduced thermal energy consumption for domestic hot water heating.¹ Heidelberg practices temperature setback and maintains a maximum domestic hot water temperature at the faucets of 105° F (40.6° C). Pirmasens, on the other hand, maintains the domestic hot water temperature at 140° F (60° C). Significant energy savings can be achieved by reducing the domestic hot water set temperature.
- The Autodin and other communications facilities at Pirmasens represent a sizable electrical load. In addition to the electric load required to meet the communications equipment demand, a relatively large air conditioning load of 366 kW is present. Discussion with the Autodin personnel revealed that the system is not presently configured for enthalpy control, is oversized for present requirements, and is

experiencing some major problems with the air handling system. The air conditioning system at Autodin and other communications facilities could be greatly improved in efficiency by the use of enthalpy control.

- The use of a UEMCS does result in both energy savings and cost savings. Improved operation and maintenance can be expected to contribute to the overall cost savings but are difficult to quantify. The simple payback period is estimated to be 2.5 years for the Samsomatic system installed at Pirmasens.

ABSTRACT

Under the provisions of Interagency Agreement DOE No. 1938-B090-A1 between the U.S. Department of Energy (DOE) and the United States Army in Europe (USAREUR), Martin Marietta Energy Systems, Inc., (MMES) through the Oak Ridge National Laboratory, (ORNL) is evaluating the utilities energy monitoring and control systems (UEMCSs) installed at USAREUR, 21st Theater Army Area Command (TAACOM), Pirmasens and 97th Base Support Battalion, Pirmasens, Germany. This evaluation relies upon existing data and information to take an in-depth look at the overall performance and effectiveness of these UEMCSs in order to determine, where possible, if they are achieving their operational objectives and are meeting projected energy and cost savings. The major thrusts of this report are the Husterhoeh Kaserne and the Muenchweiler Hospital Complex, which are the primary installations currently monitored and controlled by existing UEMCSs. UEMCS operations at Pirmasens are managed and operated by a very knowledgeable and dedicated Directorate of Engineering and Housing (DEH) Utilities Division staff. Significant reductions in thermal energy consumption have been achieved in Bunker Hill Village as a result of building envelope energy conservation retrofits and of the replacement of coal-fired building heating systems with a UEMCS-controlled hot water district heating (DH) system (DH/UEMCS). In terms of energy efficiency (Btu/HDD/ft²) thermal energy consumption in Bunker Hill Village has been reduced approximately 37% over a 5-year period. The success achieved in Bunker Hill Village clearly demonstrates the potential to save energy at other Pirmasens installations. In contrast to electrical energy consumption, thermal energy consumption offers the greater potential for overall energy and cost savings for most of the major Pirmasens facilities. In comparison, approximately 37% of the energy savings and 22% of the cost savings attributed to the UEMCS operations at the military community at Heidelberg can be attributed to reduced thermal energy consumption for domestic hot water heating.¹ Heidelberg practices temperature setback and maintains a maximum domestic hot water temperature at the faucets of 105° F (40.6° C). Pirmasens, on the other hand, maintains the domestic hot water temperature at 140° F (60° C). Significant energy savings can be achieved by reducing the domestic hot water set temperature. The Autodin and other communications facilities at Pirmasens represent a sizable electrical load. In addition to the electric load required to meet the communications equipment demand, a relatively large air conditioning load of 366 kW is present. The air conditioning system is not presently configured for enthalpy control, is oversized for present requirements, and is experiencing some major problems. The air conditioning system at the Autodin and other communications facilities could greatly improve in efficiency by the use of enthalpy control. Simple payback for the UEMCS operating in concert with the Bunker Hill Village DH system is estimated to be about 2.5 years. This report discusses and graphs the details of the evaluation conducted. Overall, Pirmasens has done a commendable job in its attempts to reduce energy consumption in Bunker Hill Village with UEMCS equipment that has minimum monitoring and control capabilities and that is not primarily under U.S. Army control.

1. INTRODUCTION

1.1 BACKGROUND

Under the provisions of Interagency Agreement DOE No. 1938-B090-A1 between the U.S. Department of Energy (DOE) and the United States Army in Europe (USAREUR), Martin Marietta Energy Systems, Inc., (MMES) is providing research and development support and technical assistance in the areas of computer science, information engineering, energy studies, engineering, and systems development. One of the initial projects authorized under this interagency agreement calls for the evaluation of the utilities energy monitoring and control systems (UEMCSs) operating at selected U.S. Army installations in Europe. Evaluation of the overall performance and energy efficiency of UEMCSs utilized at U.S. Army installations in Heidelberg, Goeppingen, Pirmasens, and Baumholder, Germany, is nearing completion. This report specifically presents the results of the evaluation of the UEMCS installed at USAREUR, 21st Theater Army Area Command (TAACOM), Pirmasens and 97th Base Support Battalion, which is operated by the Directorate of Engineering and Housing (DEH) Utilities Division.

1.2 SCOPE (STATEMENT OF WORK)

The Oak Ridge National Laboratory (ORNL) was selected by Headquarters, USAREUR, Facilities Engineering Division, Utilities and Energy Branch in Heidelberg to evaluate the overall effectiveness and energy efficiency of UEMCSs at four U.S. Army installations in Germany. The third of these systems to be evaluated, which is the scope of this report, is the UEMCS installed at Pirmasens. This evaluation relies upon existing data and information and does not involve introducing metering and instrumentation for the purpose of measuring installation energy use.

The primary purpose of this evaluation is to take an in-depth look at the overall performance and effectiveness of the UEMCS installed at Pirmasens to see if it is achieving its operational objectives by resulting in energy and cost savings. Available UEMCS project documentation is reviewed and evaluated in terms of completeness, accuracy, and reasonableness. Energy and cost saving derived from actual system operating experience is compared with any available energy and cost savings projections or life cycle cost analyses (LCCAs) made for this project. An assessment of site and physical conditions is performed based on visits to the various Pirmasens installations, facilities, and buildings served by the UEMCS. An in-depth analysis of projected energy and cost savings endeavors to highlight the most effective energy conservation measures currently monitored and controlled by the UEMCS and to identify additional measures that can be implemented in the future to improve the overall performance of this system. Finally, this evaluation focuses on a general assessment of UEMCS benefits that are not necessarily related to tangible energy and cost savings. This assessment is based, in part, on interviews with DEH Utilities Division management and operation personnel addressing such issues as system operation and maintenance and such human factors as system end-user acceptance and comfort.

2. PROJECT DESCRIPTION

2.1 GENERAL DESCRIPTION

The U.S. Army military installation at Pirmasens, Germany, consists of a large number of separate installations in addition to the primary Husterhoeh Kaserne at Pirmasens and the Muenchweiler Hospital Complex in Muenchweiler, Germany. Some of these installations, which include ammunition areas, warehouses, and storage facilities, already have been turned over to the German government. More of these installations will be turned over to the German government or deactivated in the future. Accordingly, this report will focus on the Husterhoeh Kaserne and the Muenchweiler Hospital Complex, which are the primary installations currently monitored and controlled by existing UEMCSs, and for which future systems expansion is planned. The UEMCS currently serving Pirmasens is comprised of three distinctively different and separate systems, each of which is described briefly in this section.

2.1.1 Samsomatic Thermal Energy (District Heating) Monitoring and Control System

Bunker Hill Village is a military family housing complex located in the Husterhoeh Kaserne that consists of 36 multi-family units, 32 of which are currently connected to a central district heating (DH) system that began operation during September 1988. This DH system and its associated Samsomatic UEMCS (DH/UEMCS) were installed by Stadtwerke Pirmasens, a local public utility, at no initial expense to the U.S. Government. Figure 1 is a view of the Samsomatic UEMCS central control console located in DEH Utilities Division Building 4656. Figure 2 is a typical DH system (space and hot water heating) setup in the basement of a Bunker Hill Village family housing unit. Stadtwerke Pirmasens will own, operate, and maintain this DH/UEMCS for a period of 10 years, at which time ownership, operation, and maintenance responsibility for these systems will be transferred to the U.S. Army at Pirmasens. In the meantime, the U.S. Army is paying for these systems over this 10-year period as an integral part of its monthly thermal energy bill from Stadtwerke Pirmasens.

Stadtwerke Pirmasens has a central cogeneration facility that generates electrical energy and that uses the cogenerated thermal energy to supply a local DH system, including 200-mm (7.87-in.) diameter hot water supply and return transmission lines to Bunker Hill Village. Hot water supply to Bunker Hill Village is maintained at 120°C (248°F) and 3.3 bar (48.4 psi) maximum during the winter heating season and at 80°C (176°F) and 3.3 bar (48.4 psi) minimum during the summer season. The return line temperature is controlled at a maximum of 60°C (140°F) and 1.86 bar (26.5 psi). During the actual site visit (May 28 and 29) the actual hot water return temperature was observed to be about 50°C (122°F).

The Samsomatic UEMCS that was installed by Stadtwerke Pirmasens to operate in concert with the Bunker Hill Village DH system (Fig. 3) has the following thermal energy monitoring and control capabilities for building space heating:

- *Night Setback Temperature Control:* During the heating season building operating temperatures are reduced from 21°C (70°F) to 15°C (60°F) from 10 to 11 p.m. until 5 to 6 a.m. $\Delta T = 6^\circ\text{C}$ (10°F).

ORNL-PHOTO 11729-91

Fig. 1. Samsomatic UEMCS central control console located in Building 4656.

ORNL-PHOTO 11730-91

Fig. 2. Typical district heating system setup located in Bunker Hill Village family housing unit (Building 4508).

Fig. 3. Schematic diagram of typical district heating system in Bunker Hill Village.

- *DH System Hot Water Supply Temperature Control:* Primary DH system hot water supply temperature is a function of four outside air temperature conditions (-20°C, -10°C, 15°C, and 20°C) that can be set remotely at the UEMCS central control.
- *DH System Hot Water Supply Flow Control:* The main control valve in the primary DH system hot water supply line can be regulated remotely at the UEMCS central control. This is the primary means for building space heating control, including night setback.
- *Secondary Heating System Circulation Pump Control:* During the winter heating season the pumps that circulate hot water through the building secondary heating system (radiators) run continuously. During the summer they are run approximately 2 minutes per day as a preventative maintenance measure.
- *Primary DH System Hot Water Temperature Monitoring:* The temperature of the hot water leaving the space heating heat exchanger is monitored.
- *Secondary Heating System Hot Water Temperature Monitoring:* The temperature of the hot water supplied to the building secondary heating system at the point of discharge from the space heating heat exchangers is monitored as well.
- *Building Outside Air Temperature Monitoring:* The outside air temperature is monitored and is used in conjunction with the established set points used to control DH system hot water supply temperature.

The Samsomatic UEMCS also has the following capabilities for monitoring and controlling building domestic hot water:

- *Domestic Hot Water Heating System Circulating Pump Control:* The pump that circulates potable water through the domestic hot water pre-heater and primary hot water heater en route to the hot water storage tanks is alternately turned on and shut off to maintain a 60°C (140°F) domestic hot water temperature in the hot water storage tanks.
- *Building Domestic Hot Water Supply Circulation Pump Control:* The pump that circulates potable hot water used by the military occupants of Bunker Hill Village housing units is controlled remotely at the UEMCS central control. As a conservation measure these pumps are shut off between 10 p.m. and 5 a.m.
- *Hot Water Storage Tank Temperature Monitoring:* The hot water storage tank temperature is monitored and is supplied to the domestic hot water temperature control algorithm.

General Note: In 10 of the 32 buildings under UEMCS control, the visual display on the monitor at the UEMCS central control indicates that DH system pumps and valves are either on or off (open or closed).

2.1.2 Landis and Gyr Electric Demand Limiting Ripple Control System

The Landis and Gyr ripple control system (Fig. 4) is a low frequency power line carrier system that was installed in 1983. This system serves a demand-limiting function by controlling 100 and 300 kW blocks of dehumidifier load in the vehicle storage area, and it is owned and directly controlled by the electric company, Pfaltzwerke AG. Pfaltzwerke AG also controls street lighting in 3 steps (off, 1/2-on and on) in its service area, which includes the Pirmasens military community.

The Landis and Gyr system consists of a single ripple control receiver in Building 4152, the electrical substation serving the vehicle storage area. The ripple control system activates two contacts at the receiver that, via 24-volt control wiring, open a set of relays in the humidity sensors of the dehumidifier control circuits. A total of 722 kW of load is connected in 14 vehicle storage warehouses. Figures 5 and 6 depict typical setups in Warehouse 4734G.

2.1.3 Siemens Electrical Energy Monitoring System

A Siemens S5-150-U Simatic PG675 monitoring system, which uses twisted pair wire for communications, was installed in 1985. This system monitors kWh at all 25 substations and at an additional 25 key electric consumption points. The system also monitors kW demand and switch status at the Muenchweiler facilities. The Siemens system is the only UEMCS at Pirmasens that was purchased using Energy Conservation Investment Program (ECIP) funding. During the initial site visit no documentation of the LCCA was readily available.

While no central control capability of electric distribution operations currently exists, the central station located in Building 4656 (Fig. 7) is capable of such control actions with software and hardware modifications. This central station presently is configured with a dot-matrix alarm printer, a color cathode-ray tube (CRT) display, and a keyboard. A small, portable computer with a floppy disk drive is available for program modifications and maintenance.

2.2 SYSTEM PLANNING

Future plans for DH/UEMCS system expansion focus on the Husterhoeh Kaserne at Pirmasens and the Muenchweiler Hospital Complex in Muenchweiler, Germany. The Husterhoeh Kaserne, which is the largest and principal installation at Pirmasens, is comprised of six distinct service areas:

Area	Function
Bunker Hill Village	Housing: Military family
Saratoga Village	Housing: Officer family
Kaserne area	Administrative: Offices, barracks, general
Labor Services area	Industrial: Maintenance, services
Medical Depot area	Industrial: Equipment repair, warehouses
Vehicle Warehouse area	Industrial: Vehicle warehouse, Autodin

ORNL-PHOTO 11733-91

Fig. 4. Landis and Gyr ripple control system central control station located in Building 4656.

ORNL-PHOTO 11734-91

Fig. 5. Typical vehicle storage warehouse dehumidification system setup in Warehouse 4734G.

ORNL-PHOTO 11731-81

Fig. 6. Control cabinet of dehumidification system with integrated ripple control in Warehouse 4734G.

ORNL-PHOTO 11732-81

Fig. 7. Siemens electrical energy monitoring system central control station located in Building 4656.

With the exception of the military vehicle warehouse area, these service areas have individual central heating plants supplemented by smaller boiler plants that serve one or more buildings. Thermal energy generated by these plants usually is distributed in the form of hot water and/or steam to the individual service areas from central DH systems. This thermal energy, in turn, is used in the various buildings and facilities for space heating, hot water heating, and industrial processes. Thermal energy in these service areas currently is not monitored and controlled from a central UEMCS. Instead, many individual buildings and facilities have installed Centra-Burke "Centratherm" (or equivalent) remote temperature regulation controllers. The above general description, for the most part, also applies to the Muenchweiler Hospital Complex. The future project plans of Pirmasens for the expansion of both DH/UEMCS systems are summarized below in order of priority:

1. *Kaserne area:* There are currently five satellite oil-fired boiler plants supplying thermal energy to designated buildings and facilities in the Kaserne area. A future project will eliminate these boiler plants and will connect the existing building secondary space and hot water heating systems to an existing hot water DH system that serves the Kaserne area. The existing Building 4644 central heating plant will supply thermal energy to the aforementioned hot water DH system. At the same time, a new UEMCS will be installed to monitor and control space and hot water heating operations in the Kaserne area, similar to UEMCS operations at Bunker Hill Village. Approximately 80% of the direct cabling for this new UEMCS already is installed in the Kaserne area.
2. *Medical Depot area:* This future project is very similar to the Kaserne area project described above. Nine existing satellite oil-fired boiler plants will be eliminated, and the existing building and facility space and hot water heating systems will be connected to an existing hot water DH system that serves the Medical Depot area. The existing Building 4111 central heating plant will supply thermal energy to this hot water DH system. Again, a new UEMCS will be installed concurrently with DH system improvements that will monitor and control space and hot water heating operations in the Medical Depot area. Much of the direct cabling for this UEMCS is already installed. The new UEMCS could be operated either separately or centrally in concert with the new Kaserne area UEMCS.
3. *Muenchweiler Hospital Complex:* The Building 4325 central heating plant that serves the Muenchweiler Hospital Complex already has been converted from coal to oil-firing. In addition, a new hot water DH system distribution network has been installed to serve this complex. Future plans call for existing buildings to be disconnected from an old steam system and connected to the new hot water DH system. ESSO, a private company, will own and operate the Building 4325 central heating plant and associated hot water DH system for a period of 10 years. After 10 years, during which time the U.S. Army will make incremental payments, the hot water DH system will become the property and responsibility of Pirmasens. In addition, as an integral part of this project, a new UEMCS will be installed to monitor and control space and hot water heating operations in the Muenchweiler Hospital Complex. Approximately 15% of the direct cabling for this new UEMCS is already installed. Existing communication lines between the Muenchweiler Hospital Complex and the Husterhoeh Kaserne would allow this new UEMCS to be connected directly to any central UEMCS located in the Husterhoeh Kaserne area.

3. EVALUATION OF PROJECT DOCUMENTATION

On March 26, 1991, a letter was sent to Headquarters USAREUR requesting that copies of selected UEMCS project documentation and other pertinent records be made available for review by ORNL personnel during their scheduled visit to Pirmasens.² Some of the requested information was sent to ORNL prior to the scheduled site visit, and additional information was assembled at the UEMCS operations center in Building 4656 for use by ORNL personnel during their 2-week site visit to evaluate the overall effectiveness and energy efficiency of this system. During the course of the 2-week site visit at Pirmasens, the ORNL principal investigators posed many questions and requested pertinent supplemental data and information. All questions were answered in a forthright and open manner. Whenever supplemental information was available, it was provided to the ORNL principal investigators in a timely manner. Overall, the quality of project documentation was satisfactory, and the cooperation afforded ORNL principal investigators by Pirmasens UEMCS management and operations personnel was excellent.

Upon returning to ORNL, the principal investigators commenced their analysis and evaluation of the UEMCS at Pirmasens and identified additional information and data that were not immediately available during the 2-week site visit but that were necessary to complete the analysis and evaluation of this UEMCS. On June 14, 1991, a letter was sent to Headquarters USAREUR requesting the information and data needed,³ and most of these were received by ORNL on August 26, 1991, by letter of transmittal from Pirmasens.⁴

The UEMCS currently serving Pirmasens is comprised of three distinctively different and separate systems. Each of these UEMCSs was funded, was installed, and is operated under very different circumstances than the others; and the documentation associated with these systems is equally diverse, as is evident in the following brief descriptions:

- *Samsomatic Thermal Energy (DH) Monitoring and Control System.* The Samsomatic UEMCS is the principal UEMCS installed at Pirmasens. This system was not justified, procured, or installed in the classic sense, using a Military Construction Project Data Sheet (Form DD-1391); nor was it funded as an ECIP project. As such, a formal LCCA was not prepared to justify and secure funding for this project. Instead, USAREUR, 21st TAACOM, Pirmasens entered into a contract with Stadtwerke Pirmasens, a local utility, to install at no initial cost to the U.S. Government the hot water DH/UEMCS for Bunker Hill Village, Husterhoeh Kaserne. The DH/UEMCS will be owned, operated, and maintained by Stadtwerke Pirmasens for a period of 10 years, during which time the U.S. Army will pay for these systems incrementally along with their monthly energy bill. Based on a monthly system payback base rate of 31,430 DM (\$15,332),* the overall cost of these systems after a 10-year payoff period will be 3,771,600 DM (\$1,840,000). The cost of the Samsomatic UEMCS is included in the overall cost of the hot water DH system. At the end of 10 years, ownership of these systems will be transferred to the U.S. Army, which then will be responsible for system

* During FY 1989 and FY 1990, the average rate of exchange was 1 US\$ = 2.05 DM.

operations and maintenance. Construction of the Bunker Hill Village hot water DH/UEMCS started during April 1987 and was completed during April 1988; operation of these systems commenced during September 1988. Monthly records of energy consumption by fuel and energy type are maintained by Pirmasens Utilities Division personnel. These records were used extensively by the ORNL principal investigators to prepare the tables and charts found in Section 5 of this report to support the analysis of energy and cost savings.

- *Landis and Gyr Electric Demand Limiting Ripple Control System.* As indicated in Section 2.1.2, the Landis and Gyr system is owned and directly controlled by the electric company, Pfaltzwerke AG. There is no documentation on system costs.
- *Siemens Electrical Energy Monitoring System.* The Siemens system is the only UEMCS at Pirmasens that was purchased using ECIP funding; however, during the initial site visit no documentation of the LCCA was readily available. At the Pirmasens Husterhoeh Kaserne, the system monitors a ring-configured 20-kV to 380/220-V electric distribution system with three feed points. The Muenchweiler Hospital Complex is a single feed point, ring configuration. As indicated in Section 2.1.3, the system only monitors the kWh at substation points (plus kW and switch status at Muenchweiler). While hard copy printouts of consumption are available, the system has no magnetic data storage, and all data analysis must be done by hand.

4. ASSESSMENT OF SITE AND PHYSICAL CONDITIONS

Pirmasens consists of two primary installations: the Husterhoeh Kaserne at Pirmasens and the Muenchweiler Hospital Complex in Muenchweiler, Germany. Bunker Hill Village is a military multi-family housing complex in the Husterhoeh Kaserne. During the 2-week site visit to evaluate the overall performance and energy efficiency of the UEMCS serving Pirmasens, many individual buildings and facilities were visited. In general, the utility areas of most of these buildings and facilities were found to be clean and well maintained. One reason for this finding is the fact that many coal-fired boilers have been converted to oil and/or gas firing or have been replaced by DH. The advent of DH installations in Bunker Hill Village and in the Muenchweiler Hospital Complex has contributed to the improved operation and maintenance of building and facility space and of hot water heating systems. The resultant cleaner and uncluttered utility room environments should contribute to lower maintenance and increased life of UEMCS equipment in these utility areas. Summarized below are additional observations and pertinent comments resulting from visits to specific buildings and facilities in the Husterhoeh Kaserne and the Muenchweiler Hospital Complex.

4.1 BUNKER HILL VILLAGE

Since the primary UEMCS serving Pirmasens is the one that monitors and controls the operation of the hot water DH system in Bunker Hill Village, the initial focus of the ORNL principal investigators was on buildings and facilities associated with this system. A small, unnumbered utility building was erected by Stadtwerke Pirmasens at the point of entry to the Bunker Hill Village main hot water DH system supply and return lines. This utility building houses three circulation pumps that distribute hot water to the various military family housing units in Bunker Hill Village for space and hot water heating. Stadtwerke Pirmasens currently owns all of the DH/UEMCS equipment in this utility building, and systems operation and maintenance are totally under their control. DEH Utility Division personnel can monitor the overall performance of this system only from the Samsomatic central control console in Building 4656. System operational parameters monitored are hot water supply and return temperature and pressure, flow rate, and thermal energy consumption (MWh). Building 4523, which houses the transformer station that supplies electrical energy to Bunker Hill Village, also was visited.

The utility room in Building 4514, a typical Bunker Hill Village multi-family housing unit, was visited next. The recently installed hot water DH system and its interconnection with building secondary space and hot water heating systems was observed. The UEMCS remote control unit (RCU) that operates in concert with this DH system can be programmed manually in the building as well as monitored and controlled remotely from the Building 4656 Samsomatic UEMCS central control console. RCU settings facilitate night temperature setback on a day-by-day basis, which means that special setback operations can be programmed on weekends, when appropriate. Section 2.1.1 of this report provides a detailed description of the thermal energy monitoring and control capabilities of this UEMCS for building space and hot water heating. Potable hot water circulated through the secondary hot water systems of Bunker Hill Village buildings generally is maintained at 60°C (140°F), which is considered excessive. Thermal energy consumption in Bunker Hill Village multi-family

housing units can decrease further if this set temperature is reduced to 45°C (113°F), which apparently is the intended system design temperature. Finally, it was observed that there is no meter to measure electrical energy consumption in Building 4514, which is typical of most Bunker Hill Village buildings.

4.2 HUSTERHOEH KASERNE (GENERAL)

The Kaserne area in the Husterhoeh Kaserne contains office and administrative facilities, troop barracks, and other general support facilities. It is one of the most important areas within the Husterhoeh Kaserne and will receive priority consideration for upgrade and expansion of hot water DH/UEMCS. These future plans are discussed in more detail in Section 2.2 of this report. Since this area currently does not have a UEMCS that monitors and controls thermal energy for building space and hot water heating, many individual buildings and facilities in the Kaserne area have installed Centra-Burke "Centratherm" (or equivalent) local temperature regulation controllers, which in many cases are over 10 years old. Some of these controllers regulate night set back temperature only (i.e., setback 6°C from 21°C to 15°C). Other controllers are more sophisticated and allow night setback temperatures to be programmed for each day of the week. This allows, for example, operating temperatures in specific buildings to be set back for an entire weekend. Summarized below are observations and pertinent comments related to visits to specific buildings in the Kaserne area.

- *Building 4644* is the Central Heating Plant for the Kaserne area. It consists of three, dual, fueled hot water boilers that burn gas (primary) or No. 2 fuel oil (secondary) to produce hot water at 180°C (356°F) and 10 bar (150 psi). This hot water is distributed throughout the Kaserne area to secondary hot water distribution loops that serve several buildings.

It should be noted that there are also two other Central Heating Plants that operate in the Husterhoeh Kaserne: Building 4410, that serves the Labor Services area, and Building 4111, that serves the Medical Depot area. These Central Heating Plants differ from the Building 4644 Central Heating Plant in that they generate steam. Steam then is supplied to a steam-to-hot-water heat exchanger that produces 180°C (356°F) and 10 bar (150 psi) hot water, which is distributed to buildings and facilities within these service areas for space and hot water heating. Steam also is distributed directly to some buildings that use steam/air blowers for heating and for industrial processes that require the use of steam.

- *Building 4606* is a typical troop barracks in the Kaserne area. The utility room in this building has three oil-fired boilers that produce 110°C (230°F) and 0.5 bar (7.5 psi) steam, which supplies steam to a hot water heat exchanger. Hot water from the secondary side of this heat exchanger is circulated through Buildings 4606, 4607, 4608, and 4609 for space heating. Steam also is supplied to four hot water heaters that dispense domestic hot water to these buildings.

The boilers in this utility room will be deactivated, and the secondary space and hot water heating systems serving this group of buildings will be connected to the hot water

DH system serving the Kaserne area as part of the future plans for DH/UEMCS systems expansion discussed in Section 2.2. A typical local temperature regulator was installed in the Building 4606 utility room and was set for a 6°C ΔT night setback between 11 p.m. and 4 a.m., 7 days a week, which was appropriate for the current occupancy pattern in these troop barracks.

- *Building 4617* is a typical administrative building in the Kaserne area. There are two utility rooms in this building with a total of five oil-fired boilers that produce thermal energy for space and hot water heating of Buildings 4613, 4616, 4617, 4618, and 4619. The boilers and the heating systems serving these buildings are essentially the same as those described in the above paragraph. In like manner, future plans call for these boiler plants to be deactivated and the secondary space and hot water heating systems serving this group of buildings to be connected to the hot water DH system serving the Kaserne area. The local temperature regulator in the Building 4617 utility room has more capability than the temperature regulator installed in Building 4606 and permits different temperature setback scenarios to be programmed for each day of the week. This would allow, for example, total temperature setback during an entire weekend. This controller actually was set for a 6°C ΔT night setback between 9 p.m. and 5 a.m., 7 days a week. It was generally agreed that this temperature regulator was not being operated in an optimal manner. Temperature setback during the workweek probably could have been set between 5 p.m. and 5 a.m., and total temperature setback during the weekend also might have been appropriate.
- *Building 4624* is the Pirmasens Community Support Center located in the Kaserne area. The oil-fired boiler and the associated space and hot water heating systems serving this building are similar to those described above. Because no local temperature regulator served Building 4624, thermal energy savings resulting from temperature setback could not be realized.

The buildings and their associated thermal energy systems described above are a small but typical sample of other buildings and facilities in the Kaserne area. In terms of energy conservation being practiced in this area, we found a reliance on the use of local temperature regulators serving one or more buildings. In one building we found a regulator operating in an optimal manner. In another building we found a regulator with a capability that was not being fully utilized and operating under a night temperature setback scenario that was not producing optimal energy savings. In the Community Support Center we found no local temperature regulator at all. In general, the situation described here is typical of what one might expect to find throughout the Kaserne area. Looking at the positive side, this situation provides additional justification and support for Pirmasens' future plans to install a UEMCS to operate in concert with the Kaserne area hot water DH system. With increased U.S. Army monetary "belt tightening," the ability of Utilities Division personnel to operate and maintain energy systems in an optimal manner on a continuing basis becomes more and more difficult. Accordingly, such equipment as the local temperature regulators described above are not checked by qualified personnel on a frequent enough basis to ensure their optimum operation. A new UEMCS will enable the thermal energy systems in each building to be monitored and controlled on a continuing basis from a central remote location. Furthermore, systems that are not operating in a correct and optimal manner will be identified immediately for prompt and appropriate corrective action. As a bonus, the UEMCS will also be available

in these buildings and facilities to monitor and control electrical energy use as well as to perform other utility functions, such as leak detection.

The Medical Depot area in the Husterhoeh Kaserne consists of warehouses and repair/maintenance shops. As Section 2.2 indicates, this area also is scheduled for upgrade to a DH system, which will be installed in the existing Building 4111 central heating plant. This upgrade will eliminate nine smaller boiler plants and will include a new UEMCS. Communications cables are currently being installed. Since the area is not presently under UEMCS control, individual buildings utilize Centra-Burke "Centratherm" (or equivalent) local temperature monitoring and control systems. Buildings 4109, 4175, 4172, and 4000 were visited in this area. Observations and pertinent comments are summarized below.

- *Building 4109* is a maintenance and repair shop for portable medical shelters. The facility is heated by the central steam boiler in Building 4111 using a steam and air heat exchanger with blowers and hot water radiators in offices. Only local controllers are presently in use for controlling and monitoring the system. The building has a relatively large number of fans, but the motors driving these fans are not large (< 5hp). Several paint drying booths also were observed.
- *Building 4175* is one of the transformer stations serving the area. The station consists of two transformers, one 375 kVa and one 250 kVa, and is typical of the electrical substations serving the maintenance area.
- *Building 4172* is a medical storage warehouse and shipping facility. It is heated by a large oil-fired hot air system, with a local controller. Night setback is activated from 2300 to 0600 hours. This facility would be upgraded to DH/UEMCS in the planned facilities upgrade.
- *Building 4000* is a new electronic maintenance facility that uses a hot water to air heating system. The hot water is supplied from the Medical Depot area central plant in Building 4111. All wiring and some data transmission equipment for UEMCS have been installed, and an elaborate local control system already is installed and operating. The local control system regulates temperature by controlling pump speeds and valves in the heated water supply to the hot water to air heat exchanger. The facility is a single shift operation, and setback is practiced from 1500 to 0530 hours and on weekends. This facility can be included easily in any upgrades to the present Samsomatic UEMCS.

The Vehicle Warehouse area consists of some 14 warehouses that are used to store battle-ready equipment under controlled climatic conditions. The dehumidifiers represent a relatively large electric load. As Section 2.1.2 indicates, this load is under direct control by the local electric utility, Pfaltzwerke AG, via the Landis and Gyr Ripple control system. Each building has two 23.5-kW dehumidifiers and two 2.3-kW fan motors. The ripple control receiver is located in Building 4152, the electric substation serving the area, and the contacts of the ripple control receiver are attached to a set of relays in each dehumidifier controller.

Buildings 4155 and 4156 house the Autodin Communications facility, which represents a sizable electrical load. In addition to the electric load required to meet the communications

equipment demand, a relatively large air conditioning load of 366 kW is present. This load is not controlled in any way other than through the building thermostat. Discussion with the Autodin personnel revealed that the system currently is not configured for enthalpy control and is experiencing some major problems with the air handling system. The system also appears to be oversized for the present communication and computer equipment. The air conditioning system at Autodin could greatly improve in efficiency by using a local process controller. Some demand reduction and load shedding also could be achieved in the Autodin and in the additional communication facilities at the Husterhoch Kaserne. Careful evaluation of critical loads and enthalpy control should be considered and portions of the non-critical load placed under UEMCS.

4.3 MUENCHWEILER HOSPITAL COMPLEX

The Muenchweiler Hospital Complex is the other major area in the Pirmasens Military Community. The facilities include family housing, schools, bachelor officer and noncommissioned officer (NCO) quarters, a motor pool, a mess hall, and troop barracks. The mess hall is located in a portion of what used to be the hospital facility. At present, the Siemens UEMCS at the Husterhoch Kaserne monitors the ring-configured electrical distribution network for kWh, kW, and switch status. No direct control is possible in the present UEMCS configuration. Only one major air conditioning load is present at Muenchweiler, and this is a relatively small 7.5-hp unit at the hospital (Building 4341). Buildings 4313, 4325, and 4337 were visited; and key observations from these visits are summarized below.

- *Building 4313* is a partially occupied troop barracks that currently uses a local steam heating system. The system is being modified to accept hot water from the upgraded central heating plant. Local temperature regulators are used for night setback.
- *Building 4325* is the central heating plant for the Muenchweiler area. The plants are old steam plants that currently are being renovated to an oil-fired steam-hot water system. The system presently is being run and modified by the ESSO company, and a new UEMCS is planned as a part of the system renovation.
- *Building 4337* is a representative family housing unit that is monitored and controlled from a local temperature regulator. Night setback is used, and it is possible to network these local units into the communications system of the present Siemens electric distribution system UEMCS.

5. ANALYSIS OF ENERGY AND COST SAVINGS

5.1 ENERGY CONSUMPTION AND SAVINGS TRENDS AT PIRMASENS

Pirmasens maintains monthly records of fuel and energy consumption for each of its major installations. Table 1 summarizes energy consumption by fuel and energy type during the time period, FY 1985 through FY 1990. While electrical energy consumption essentially has remained constant during this time period, thermal energy use has declined steadily, as shown in Fig. 8. An overall reduction in total energy consumption (MBtu/year) of over 11% has been achieved during this time period. The steady decrease in thermal energy consumption can be attributed to a combination of energy conservation retrofit measures—including building envelope retrofits and boiler/fuel conversions—and more recently to the installation of the hot water DH/UEMCS in Bunker Hill Village. Figure 9 plots the overall energy consumption trend for Pirmasens by fuel and energy type. This illustration confirms a steady electrical energy usage and a gradual decrease in thermal energy consumption. The steady decline in the use of fuel oil and coal as a thermal energy source is noteworthy, as is the marked increase in the use of natural gas and DH during FY 1989 and FY 1990.

Further evaluation of the energy consumption and conservation trends at Pirmasens requires a closer examination of energy use by major facility or area. Table 2 summarizes the total energy (thermal and electrical) consumed by each of the major facilities during FY 1988 through FY 1990. This is the time period when the Husterhoeh Kaserne area building envelope retrofits and other conservation measures were being completed (FY 1988) and when the Bunker Hill Village DH/UEMCS began operations (FY 1989 through FY 1990). Figure 10 shows some very interesting trends in terms of comparative energy performance (MBtu/1000 ft²) among the major facilities. First and foremost, the energy performance of Bunker Hill Village is far superior to that of the other comparable facilities, endorsing the benefits derived from building envelope retrofits and DH/UEMCS installation. This illustration thus confirms the wisdom of Pirmasens DEH personnel to proceed methodically with future plans to expand DH/UEMCS installation in both the Kaserne and Muenchweiler areas.

Since electrical energy consumption is relatively steady, Table 3 and its companion illustration, Fig. 11, take a closer look at just the thermal energy consumption trends of the various Pirmasens major facilities. Using Bunker Hill Village as a point of reference, energy efficiency during FY 1990 (9.29 Btu/HDD/ft²) is approximately 39% superior to that of a comparable military family housing community, Saratoga Village (15.35 Btu/HDD/ft²). When compared with that of the Muenchweiler Hospital Complex area, the energy efficiency of Bunker Hill Village is over 50% superior (20.26 Btu/HDD/ft²). It should be noted that the Muenchweiler Hospital Complex area, which is used predominantly for barracks and family housing, currently is undergoing building envelope retrofits and conversion to a hot water DH/UEMCS system. Following these modifications, the Muenchweiler area should achieve energy efficiencies approaching those of Bunker Hill Village. In real terms these energy efficiency comparisons provide a general idea of the energy conservation potential of these other facilities that have not yet undergone such conservation measures as building envelope retrofits and DH/UEMCS operations expansion.

Table 1. Pirmasens total energy consumption by fuel and energy type, MBtu/year

Fuel/energy type	FY 1985	FY 1986	FY 1987	FY 1988	FY 1989	FY 1990
No. 2 fuel oil	194,030	188,260	185,992	162,531	158,477	159,744
No. 6 fuel oil	127,096	132,134	117,083	104,158	87,949	^a
Anthracite coal	93,754	88,047	77,365	58,669	^b	^b
Bituminous coal	93,019	103,602	88,784	98,961	94,280	98,396
District heating	--	--	--	--	55,387	53,541
Natural gas	14,369	12,967	15,408	16,568	39,259	133,010
Thermal energy (Subtotal)	522,268	525,010	484,632	440,887	435,352	444,691
Electrical energy	138,953	145,322	145,116	145,649	143,481	143,541
Total energy consumption	661,221	670,332	629,748	586,536	578,833	588,232
Other factors						
Building ft ²	7,212,000	7,118,000	7,469,000	7,461,000	7,463,000	7,587,000
Heating degree day (HDD)	6890	7040	6837	5895	5989	6286
Total MBtu/1000 ft ²	91.68	94.17	84.31	78.61	77.56	77.53
Thermal Btu/HDD/ft ²	10.51	10.48	9.49	10.02	9.74	9.32

^a Three central heating plants converted from No. 6 fuel oil to gas.

^b Bunker Hill Village converted from coal-fired boilers to district heating.

Fig. 8. Pirmasens total energy consumption by building, ft².

Fig. 9. Pirmasens total energy consumption by fuel and energy type.

Table 2. Pirmasens total energy (thermal and electrical) consumption by major facility

	FY 1988				FY 1989			FY 1990		
	Building ft ²	Total consumption, MBtu	MBtu 1000 ft ²		Building ft ²	Total consumption, MBtu	MBtu 1000 ft ²	Building ft ²	Total consumption, MBtu	MBtu 1000 ft ²
Husterhoeh Kaserne area										
• Kaserne area (KA)	639,635	93,920	146.83		639,635	95,427	149.19	763,635	96,187	125.96
• Labor Service area (LS)	190,017	22,217	116.92		190,017	23,069	121.41	190,017	22,616	119.02
• Medical Depot area (MD)	1,666,104	72,134	43.30		1,666,104	76,925	46.17	1,666,104	87,560	52.55
• Vehicle Warehouse area (VW)	523,932	3,127	5.97		523,932	2,090	3.99	523,932	2,202	4.20
• Saratoga Village (SV)	196,581	22,541	114.67		196,581	21,809	110.44	196,581	21,243	108.06
• Bunker Hill Village (BHV)	1,139,152	92,021	80.78		1,139,152	88,665	77.83	1,139,152	86,320	75.78
Subtotal	4,355,421	305,960	---		4,355,421	307,985	---	4,479,421	316,128	---
Muenchweiler area (MH)	772,662	109,790	142.09		772,662	105,769	136.89	772,662	109,784	142.09
Other facilities	2,332,917	170,786	73.21		2,344,917	165,079	70.40	2,334,917	162,320	69.52
Total	7,461,000	586,536	78.61		7,463,000	578,833	77.56	7,587,000	588,232	77.53

Fig. 10. Pirmasens total energy consumption by major facility.

Table 3. Pirmasens thermal energy consumption by major facility

	FY 1988				FY 1989				FY 1990			
	Building ft ²	Total thermal energy, MBtu	Btu/ HDD/ ft ²		Building ft ²	Total thermal energy, MBtu	Btu/ HDD/ ft ²		Building ft ²	Total thermal energy, MBtu	Btu/ HDD/ ft ²	
Husterhoeh Kaserne area												
- Kaserne area	639,635	75,898	20.13		639,635	76,141	19.88		763,635	73,334	15.28	
- Labor Service area	190,017	15,778	14.09		190,017	16,887	14.84		190,017	15,387	12.88	
- Medical Depot area	1,666,104	54,824	5.58		1,666,104	59,233	5.94		1,666,104	70,885	6.77	
- Vehicle Warehouse area	523,932	--	--		523,932	--	--		523,932	--	--	
- Saratoga Village	196,581	20,089	17.34		196,581	19,718	16.75		196,581	18,970	15.35	
- Bunker Hill Village	1,139,152	74,447	11.09		1,139,152	69,246	10.15		1,139,152	66,563	9.29	
Subtotal	4,355,421	241,036	--		4,355,421	241,225	--		4,479,421	245,139	--	
Muenchweiler area	772,662	98,961	21.73		772,662	94,280	20.37		772,662	98,396	20.26	
Other facilities	2,332,917	100,890	7.34		2,344,917	99,847	7.11		2,334,917	101,156	6.89	
Total	7,461,000	440,887	10.02		7,463,000	435,352	9.74		7,587,000	444,691	9.32	

Note: FY 1988 HDD = 5895
FY 1989 HDD = 5989
FY 1990 HDD = 6286 .

Fig. 11. Pimasens thermal energy consumption by major facility.

Finally, Table 4 and its companion illustration, Fig. 12, compare energy consumption during FY 1990 for each major facility by fuel and energy type. No outstanding conclusions are evident from these data other than the fact that thermal energy consumption, in contrast to electrical energy consumption, offers the greater potential for overall energy and cost savings for most of the major Pirmasens facilities. Perhaps the most evident candidate for potential energy and cost savings is the Muenchweiler Hospital Complex, where annual thermal energy consumption during FY 1990 represented about 90% of the total energy consumed by this facility. As stated above, current energy conservation efforts under way in the Muenchweiler area could produce remarkable results.

Aside from the military housing facilities discussed above, the remaining facilities at Pirmasens primarily consist of administrative, maintenance, and storage facilities in the Husterhoeh Kaserne area (Kaserne area, Labor Services area, Medical Depot area, and Vehicle Warehouse area). Future plans for hot water DH/UEMCS system expansion focus on the Husterhoeh Kaserne, as is discussed in Section 2.2. These future plans include not only the elimination of individual building boilers, but also the installation of individual building temperature regulators (process controllers) that will be controlled remotely from the newly installed UEMCS. Benefits to be derived from this installation could be significant, since many of the present local controllers located in individual buildings were observed to be operating in a less than optimal manner. Central monitoring by newly installed UEMCS undoubtedly will enhance overall operational performance.

5.2 BUNKER HILL VILLAGE ENERGY CONSUMPTION AND SAVINGS TRENDS

The major UEMCS utilized at Pirmasens is the Samsomatic system that operates in concert with the hot water DH system that began operation in Bunker Hill Village at the end of FY 1988. Table 5 and its companion illustration, Fig. 13, plot thermal energy consumption specifically for Bunker Hill Village during the time period, FY 1985 through FY 1990. As Fig. 13 illustrates, a steady decrease in thermal energy consumption occurred during this time period, an improvement that occurred in two distinct phases. First, most of the buildings in Bunker Hill Village (27 of 36 buildings) underwent comprehensive building envelope energy conservation retrofits (e.g., external insulation, multi-pane windows, ceiling insulation) between July 1984 and October 1988. Reduced thermal energy consumption and the resultant energy savings during FY 1985 through FY 1988 can be attributed in major part to this retrofit program. Second, the Bunker Hill Village hot water DH/UEMCS began operation during September 1988. Therefore, reduced thermal energy consumption and the resultant energy savings that occurred during FY 1989 and FY 1990 can be attributed in major part to combined hot water DH/UEMCS operation in Bunker Hill Village.

In terms of energy efficiency, DEH personnel at Pirmasens can be proud of the fact that they have reduced thermal energy consumption in Bunker Hill Village from 14.66 Btu/HDD/ft² during FY 1985 to 9.29 Btu/HDD/ft² during FY 1990. This is approximately a 37% reduction in thermal energy consumption in just 5 years. Personnel must not become complacent, however, since the military community in Heidelberg achieved a 7.72 Btu/HDD/ft² energy efficiency during FY 1990.¹

Table 4. Pirmasens FY 1990 energy consumption by major facility and by fuel and energy type, MBtu

	Building ft ²	Fuel oil	Coal	Gas	District heating	Total thermal energy	Electrical energy	Total consumption
Husterhoeh Kaserne area								
• Kaserne area	763,635	51,342	—	21,992	—	73,334	22,853	96,187
• Labor Service area	190,017	288	—	15,099	—	15,387	7,229	22,616
• Medical Depot area	1,666,104	12,170	—	58,715	—	70,885	16,675	87,560
• Vehicle Warehouse area	523,932	—	—	—	—	—	2,202	2,202
• Saratoga Village	196,581	236	—	18,734	—	18,970	2,273	21,243
• Bunker Hill Village	1,139,152	13,022	—	—	53,541	66,563	19,757	86,320
Subtotal	4,479,421	77,058	—	114,540	53,541	245,139	70,989	316,128
Muenchweiler area	772,662	—	98,396	—	—	98,376	11,388	109,784
Other facilities	2,334,917	82,686	—	18,470	—	101,156	61,164	162,320
Total	7,587,000	159,744	98,396	133,010	53,541	444,691	143,541	588,232

Fig. 12. Pirnasens FY 1990 annual energy consumption by major facility and by fuel and energy type.

Table 5. Pirmasens Bunker Hill Village thermal energy consumption

Bunker Hill Village: Total facility (36 buildings in 1990)

Fuel/energy type	FY 1985	FY 1986	FY 1987	FY 1988	FY 1989	FY 1990
Anthracite coal, MBtu/year	93,754	88,047	77,365	58,669	<i>a</i>	---
Fuel oil, MBtu/year	21,284	19,860	20,868	15,778	13,859	13,022
District heating (DH), MBtu/year	---	---	---	<i>a</i>	55,387	53,541
Total thermal energy, MBtu/year	115,038	107,907	98,233	74,447	69,246	66,563
Heating degree day (HDD)	6890	7040	6837	5895	5989	6286
MBtu/HDD (total facility)	16.70	15.33	14.37	12.63	11.56	10.59
Btu/HDD/ft ² (total facility) ^b	14.66	13.46	12.61	11.09	10.15	9.29

Bunker Hill Village: Buildings under UEMCS only (32 buildings in FY 1990)

Floor area, ft ² (under UEMCS)	919,276	919,276	919,276	919,276	919,276	939,896
MBtu/HDD (UEMCS buildings)	13.61	12.51	11.32	9.95	9.25	8.52
Btu/HDD/ft ² (UEMCS buildings)	14.80	13.60	12.31	10.83	10.06	9.06

^a Bunker Hill Village converted from coal-fired boilers to DH/UEMCS.

^b Bunker Hill Village total floor area = 1,139,152 ft² (36 buildings total).

Fig. 13. Pirmasens Bunker Hill Village thermal energy consumption.

5.3 ELECTRICAL ENERGY CONSUMPTION AND SAVINGS ATTRIBUTED TO UEMCS OPERATIONS

Unlike the earlier UEMCS evaluation at Heidelberg,¹ this evaluation indicates that the potential for saving electrical energy at Pirmasens is considerably lower than for saving thermal energy. The facilities at Pirmasens do not present just the relatively heavy electrical load in administrative and support areas. The electrical distribution system consists of three feed points at the Husterhoeh Kaserne and a single feed point at the Muenchweiler Hospital Complex. The primary distribution voltage is 20 kV, 50 Hz, 3-phase; and distribution is accomplished via a ring distribution configuration. There are 21 transformer stations at the Husterhoeh Kaserne and 4 at Muenchweiler. The secondary distribution voltage is 400/230 V (208/110 V for the hospital at Muenchweiler).

As shown in Fig. 14, the present system has a winter peak load of about 5500 kW (6000 kW contracted peak); and as shown in Fig. 15, the peak load occurs on weekend evenings and on weekday mornings. The relatively flat electrical load during weekdays indicates little opportunity for peak shifting. In addition, the system has a 0.94–0.96 power factor (<0.9 for penalty under contract) and consumes about 3900 MWh of electric energy per year. The overall consumption also has been relatively flat for the last 5 years; however, family housing electric consumption has increased from 17 to 47 MWh over the same period. This increase in family housing electric consumption can be attributed to the electric modernization of the Bunker Hill Village family housing area. However, the relatively flat total consumption indicates a slight reduction in electric consumption for the balance of plant.

The major electric loads at the Husterhoeh Kaserne and the Muenchweiler Hospital Complex are the water plant and pumps, the warehouses and repair shops, the military vehicle storage area, the Autodin, and the other communications sites. The key elements of these loads are estimated to be pumps, compressor drives, and other electric motors. However, not all of these are associated with space heating, air handling, and air conditioning; since electric load is relatively constant throughout the year. Hence, the opportunity to control this load in conjunction with the HVAC system does not seem reasonable.

The Siemens UEMCS that monitors the electrical system is the only UEMCS at Pirmasens that was purchased using ECIP funding; however, the documentation of the LCCA was not available during the initial visit and was not provided following the request for additional information.³ As mentioned earlier, the UEMCS systems for Pirmasens are not in direct control of any electric load. The demand from dehumidifiers (100 and 300 kW of diversified demand in 722 kW of connected load) is controlled directly by the electric supply company (Pfaltzwerke AG) using the Landis and Gyr ripple control system. Outside lighting also is controlled by the electric supplier.

The local Siemens UEMCS for the electric distribution system monitors kWh at the Husterhoeh Kaserne and kWh, kW, and switch status at the Muenchweiler Hospital Complex. The system is capable of control with modification of both hardware and software. As a result, the analysis of energy conservation and associated cost savings attributed to this UEMCS will not include a comparison with earlier projected savings. Since energy savings are essentially zero for UEMCS monitoring, the cost to benefit ratio is undefined for the Siemens UEMCS

Fig. 14. Pimasens electrical power peaks during 1990.

Fig. 15. Pirmasens Husterhoeh Kaserne September 1990 daily electrical consumption.

at Pirmasens. Careful analysis might justify savings as a result of operating this UEMCS, but most benefits will remain difficult to quantify.

Of the three UEMCS systems at the Pirmasens facilities, only the energy savings of the Samsomatic system used on the Bunker Hill Village DH system can be quantified. The electric distribution system is monitored only by the Siemens UEMCS, and hence no energy savings are possible. The Landis and Gyr system operated and controlled by the electric power supplier (Pfaltzwerke AG) is primarily a demand limiting system, and electric energy is shifted in time but not saved. The control of street lights at night does constitute energy savings, but no data on savings from the reduction in street lighting are readily available.

5.4 COST SAVINGS ATTRIBUTED TO UEMCS OPERATION

Cost savings can be calculated from estimates of savings from night setback of thermostats, reduced electrical demand, night setback of water heater set points, reduced lighting and circulation pump operation, and improved operation and maintenance. However, most of these functions at Pirmasens are controlled directly either by the local utility (demand reduction) or by local temperature controllers. Therefore, the direct estimates of savings from UEMCS operation reported below are based on the improved operation of the DH system in concert with UEMCS and include not only energy savings but also the indirect benefits of improved monitoring and maintenance.

It is generally understood that energy savings achieved at Bunker Hill Village during FY 1989 and FY 1990 can be attributed in major part to UEMCS operations in concert with the new hot water DH system. Using the data in Table 5 (lower section), the following calculations reveal the energy and cost savings resulting from the DH/UEMCS:

$$\begin{aligned}\text{FY 1989 MBtu Savings} &= (10.83-10.06) \text{ Btu/HDD/ft}^2 \times 919,276 \text{ ft}^2 \times 5989 \text{ HDD/year} \\ &= 4239 \text{ MBtu/year,}\end{aligned}$$

$$\begin{aligned}\text{FY 1990 MBtu Savings} &= (10.06-9.06) \text{ Btu/HDD/ft}^2 \times 939,896 \text{ ft}^2 \times 6246 \text{ HDD/year} \\ &= 5871 \text{ MBtu/year,}\end{aligned}$$

$$\text{FY 1989 Cost Savings} = 4239 \text{ MBtu/year} \times 31.56 \text{ DM/MBtu} = 133,783 \text{ DM/year,}$$

$$\text{FY 1989 Cost Savings} = 5871 \text{ MBtu/year} \times 33.25 \text{ DM/MBtu} = 195,211 \text{ DM/year,}$$

$$\text{Average Cost Saving} = 164,497 \text{ DM/year } (\$80,242/\text{year}).$$

While the Samsomatic UEMCS is capable of monitoring about 750 points, only 421 points presently are connected (8 analog and 5 digital per remote per building plus 5 analog points at the DH substation). An estimate of the cost to attach a single UEMCS remote to the DH system can be made. Assuming a cost per digital point of 600 DM and 5 digital points per remote and a cost per analog point of 1400 DM and 8 points per remote, each installed remote would cost 14,200 DM. The cost to connect all 32 buildings under UEMCS at Bunker Hill Village thus would be about 500,000 DM, including the central control computer and interface. This results in a simple payback period of 3.0 years on the plus side.

This estimate of savings does not include operation and maintenance (O&M) savings from reduced outage time nor improved maintenance, which would further reduce the payback period. On the minus side, a certain portion of annual energy savings must be attributed to improved system performance resulting from the operation of the new DH system.

However, if the difference in thermal energy savings for FY 1989 and FY 1990 is totally attributed to improved UEMCS operation of the DH system, the following equation provides an estimate of the average annual energy savings for the UEMCS using the 6-year average for HDD/year: Average Energy Savings = $(10.06 - 9.06) \text{ Btu/HDD/ft}^2 \times 939,896 \text{ ft}^2 \times 6490 \text{ HDD/year} = 6100 \text{ MBtu/year}$. Assuming the 2-year average DH cost of 32.4 DM/MBtu results in an average annual cost savings of 197,640 DM and a simple payback period of 2.53 years. Hence, it is safe to say that the Pirmasens UEMCS has a payback period of 2-3 years.

6. GENERAL ASSESSMENT OF BENEFITS AND OF MAINTENANCE AND TRAINING

6.1 BENEFITS

Beyond the readily apparent energy and cost savings, other benefits are known to exist for UEMCS. While some of these benefits can be quantified in terms of energy and cost savings, many can only be assessed subjectively. Because no energy coordinators currently serve Pirmasens, it was not possible to determine the effects of the UEMCS at the user level. A few (about 3-5) users were asked questions at random when the opportunity presented itself. In general, the answers to these questions revealed that buildings were adequately heated and that hot water was available when requested. Building occupants in Bunker Hill Village indicated that they felt that the hot water temperatures were too high, but there were no other indications of displeasure from any of the few users contacted.

Electrical energy consumption in family housing currently is not controlled. This is primarily because the peak demand for electricity in family housing is not coincident with the community peak. Therefore, attempts to control the peak would result in no real electrical energy or cost savings. The major system thermal energy conservation presently is accomplished via control of building temperature and thermal energy use and via night setback of DH and hot water temperatures. The few complaints received about present control strategies seem to indicate that the occupants seem pleased. While daytime setback probably is not practical in family housing, it may be prudent in bachelor officer's quarters (BOQ), bachelor enlisted quarters (BEQ), or other single soldier barracks during working hours.

6.2 MAINTENANCE AND TRAINING

The training of Pirmasens UEMCS personnel is accomplished in several ways, with on-the-job training as the primary method. Beyond on-the-job training, UEMCS equipment manufacturers conduct training programs that personnel attend, and some vendors also conduct on-site training. The U.S. Army, Huntsville, conducts training about every 2 years in Europe. The training received by the operators at Pirmasens appeared to be thorough.

It was observed that reduction in maintenance and operating personnel without increased use of UEMCS will result in decreased system efficiency. This observation is based on the finding of inoperative or improperly set local process controllers. Again, the enhanced use of UEMCS to provide feedback on system status reduces outage time and keeps the thermal and, potentially, the electrical utility system in peak operating condition, thereby reducing energy consumption and improving availability.

7. CONCLUSIONS

Based on the results of the evaluation of the UEMCS installed at Pirmasens, the following conclusions have been reached:

- The UEMCS operations at Pirmasens are managed and operated by a very knowledgeable and dedicated DEH Utilities Division staff. This staff has done a commendable job in their attempts to reduce energy consumption in Bunker Hill Village with UEMCS equipment that has minimum monitoring and control capabilities and that is not primarily under U.S. Army control.
- Significant reductions in thermal energy consumption have been achieved in Bunker Hill Village as a result of building envelope energy conservation retrofits and of the replacement of coal-fired building heating systems with a UEMCS-controlled hot water DH system. In terms of energy efficiency (Btu/HDD/ft²), thermal energy consumption in Bunker Hill Village has been reduced approximately 37% over a 5-year period.
- The success achieved in Bunker Hill Village clearly demonstrates the potential to save energy at other Pirmasens installations. For example, based on FY 1990 thermal energy consumption data, the energy performance (Btu/HDD/ft²) of Bunker Hill Village is 39% superior to that of Saratoga Village and is over 50% superior to that of the Muenchweiler area.
- In contrast to electrical energy consumption, thermal energy consumption offers the greater potential for overall energy and cost savings for most of the major Pirmasens facilities. Perhaps the most evident candidate for potential energy and cost savings is the Muenchweiler Hospital Complex, where the annual thermal energy consumption during FY 1990 represented about 90% of the total energy consumed by this facility. Building envelope energy conservation retrofits are currently under way, and the installation of a UEMCS-controlled hot water DH system should result in a significant reduction in thermal energy consumption in the Muenchweiler Hospital Complex, if the positive results achieved at Bunker Hill Village are to serve as an indicator.
- The local temperature regulators serving individual or groups of buildings in the Husterhoch Kaserne area, and used primarily for temperature setback, were found to be operating in less than an optimal manner. This undesirable condition can be rectified to a great extent by a planned future UEMCS that will enable thermal energy systems in individual buildings to be monitored and controlled on a continual basis from a central remote location.
- Approximately 37% of the energy savings and 22% of the cost savings attributed to the UEMCS operations at the military community at Heidelberg can be attributed to reduced thermal energy consumption for domestic hot water heating.¹ Heidelberg practices temperature setback and maintains a maximum domestic hot water temperature at the faucets of 105° F (40.6° C). Pirmasens, on the other hand, maintains the domestic hot water temperature at 140° F (60° C). Significant energy savings can be achieved by reducing the domestic hot water set temperature.

- The Autodin and other communications facilities at Pirmasens represent a sizable electrical load. In addition to the electric load required to meet the communications equipment demand, a relatively large air conditioning load of 366 kW is present. Discussion with the Autodin personnel revealed that the system is not presently configured for enthalpy control, is oversized for present requirements, and is experiencing some major problems with the air handling system. The air conditioning system at Autodin and other communications facilities could be greatly improved in efficiency by the use of enthalpy control.
- The use of a UEMCS does result in both energy savings and cost savings. Improved operation and maintenance can be expected to contribute to the overall cost savings but are difficult to quantify. The simple payback period is estimated to be 2.5 years for the Samsomatic system installed at Pirmasens.

8. RECOMMENDATIONS

Based on the results of the evaluation of the UEMCS utilized at Pirmasens, the following recommendations are made:

- Pirmasens should proceed with its plans to incorporate UEMCS with its planned expansion of hot water DH in both the Husterhoeh Kaserne and Muenchweiler Hospital Complex areas.
- As plans to expand the UEMCS operations at Pirmasens materialize, serious consideration should be given to centralizing all UEMCS operations.
- Control of domestic hot water systems by UEMCS can result in significant energy and cost savings. Consideration should be given to reducing the domestic hot water set temperature from its current setting of 140° F (60° C) to at least 120° F (49° C).
- Pirmasens currently does not have a formal network of energy coordinators assigned to its major facilities that could promote energy awareness and good conservation practices among the major facility and building end-users (energy consumers). The importance of and emphasis given to these activities cannot be overstressed. No conservation measure or energy system such as a UEMCS can achieve its full potential unless building occupants consider energy conservation worthwhile. A modest energy coordinator program should be given serious consideration by Pirmasens.
- Some demand reduction and load shedding could be achieved in the Autodin and other communication facilities at the Husterhoeh Kaserne. Careful evaluation of critical loads and enthalpy control should be considered and portions of the non-critical load placed under UEMCS.

9. REFERENCES

1. Broders, M. A., and B. W. McConnell, *Evaluation of the Computerized Utilities Monitor and Control System Installed at the U.S. Army, Europe, 26th Support Group at Heidelberg, Germany*, ORNL/CON-320, Martin Marietta Energy Systems, Inc., Oak Ridge Natl Lab., May 1991.
2. Broders, M. A., and B. W. McConnell, letter to J. Mitchell, March 26, 1991.
3. Broders, M. A., letter to J. Mitchell, June 14, 1991.
4. Drott, E. A., letter to M. A. Broders, July 29, 1991 (endorsed August 1, 1991).

INTERNAL DISTRIBUTION

1-10.	M. A. Broders	28.	M. W. Rosenthal
11.	R. S. Carlsmith	29.	M. P. Ross
12.	G. E. Courville	30.	R. B. Shelton
13.	G. A. Dailey	31.	J. N. Stone
14.	S. J. Dale	32.	T. A. Stone
15.	C. D. Doty	33.	A. W. Trivelpiece
16.	W. Fulkerson	34.	T. J. Wilbanks
17.	M. B. Gettings	35-36.	Laboratory Records Dept.
18.	C. R. Kerley	37.	Laboratory Records - RC
19.	M. A. Kuliasha	38.	Laboratory Protection Division
20-24.	B. W. McConnell	39.	ORNL Patent Office
25.	W. R. Mixon	40.	ORNL Public Relations Office
26.	S. L. Purucker	41.	ORNL Foreign Travel
27.	D. E. Reichle		

EXTERNAL DISTRIBUTION

- 42. Juergen Baller, Chief of Utilities, HQ USAREUR, 26th Support Group, DEH Heidelberg, Utilities Division, Heidelberg, GERMANY
- 43. R. H. Brewer, Director, Utility Systems Division, Department of Energy, CE-141, 5F-064/FORSTAL, 1000 Independence Avenue, SW, Washington, DC 20585
- 44. K. Gary Briggs, Jr., Program Manager, European Office, Martin Marietta Energy Systems, Inc., Rathausstrasse 15, D-6906 Leimen, GERMANY
- 45. B. G. Buchanan, Computer Science Department, University of Pittsburgh, 206 Mineral Industries Building, Pittsburgh, PA 15260
- 46. H. Frank Carlen, Chief of Electronic Technology Branch, U.S. Army Corp of Engineers, HNDED-ME, P.O. Box 1600, Huntsville, AL 35807
- 47. Millard Carr, Assistant for Energy Policy, Office of the Secretary of Defense, DASO(L)EP, Washington, DC 20301-8000
- 48. J. W. Cooke, DOE-OR
- 49. R. L. Egli, DOE-OR
- 50-51. Rudi Hartlieb, Chief of Utilities, DEH Utilities Division, Building 4656, Husterhoch Kaserne, Pirmasens, APO, New York 09819-3878
- 52. A. Hirsch, Vice President, Environmental Sciences and Director, Washington Operations, Midwest Research Institute, 5109 Leesburg Pike, Suite 414, Falls Church, VA 22041
- 53. R. O. Hultgren, Deputy Assistant Manager, Energy Research and Development, DOE-OR, ORNL, Building 4500N, MS 6269
- 54. H. M. Ingram, Director, Udall Center for Studies in Public Policy, The University of Arizona, 803/811 East First Street, Tucson, AZ 85719

- 55. Richard Karney, U.S. Army Engineering and Housing Support Center, Attn: CEHSE-FU-M, Ft. Belvoir, VA 22060-5580
- 56-57. Wolfgang Lind, U.S. Army, Europe, 21st TAACOM, Kaiserslautern, AEHER-FU-E, APO, New York 09325-3730
- 58. C. D. MacCracken, President, Calmac Manufacturing Corporation, 101 West Sheffield Avenue, P. O. Box 710, Englewood, NJ 07631
- 59-73. Jeff Mitchell, Electronics Engineer, HQ, U.S. Army, Europe, AEAEN-FE-U, APO, New York 09403-0108
- 74. J. W. Nehls, Sr., DOE-OR
- 75-84. Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831
- 85. W. G. Phelps, Director, Safeguards and Security Division, DOE-OR
- 86. J. B. Shrago, Director, Office of Technology Transfer, 405 Kirkland Hall, Vanderbilt University, Nashville, TN 37240
- 87. P. S. Siska, Chief, Utilities and Energy, HQ, U.S. Army, Europe, AEAEN-FE-U, APO, New York 09403-0108
- 88. R. Q. Spradlen, DOE-OR
- 89. W. F. Taylor, Head, Utilities Engineering Branch, Naval Facilities Engineering Command, 200 Stovall Street, Alexandria, VA 22332-2300
- 90-94. Roman Tretter, Engineering Technician, DEH Utilities Division, Building 4656, Husterhoeh Kaserne, Pirmasens, APO, New York 09819-3878
- 95. M. Williams, Professor, Department of Economics, Northern Illinois University, DeKalb, IL 60115

END

**DATE
FILMED**

2 / 25 / 92