MASTER

ARGONNE NATIONAL LABORATORY

**ENERGY AND ENVIRONMENTAL SYSTEMS
DIVISION**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

The facilities of Argonne National Laboratory are owned by the United States Government. Under the terms of a contract (W-31-109-Eng-38) between the U. S. Department of Energy, Argonne Universities Association and The University of Chicago, the University employs the staff and operates the Laboratory in accordance with policies and programs formulated, approved and reviewed by the Association.

MEMBERS OF ARGONNE UNIVERSITIES ASSOCIATION

The University of Arizona
Carnegie-Mellon University
Case Western Reserve University
The University of Chicago
University of Cincinnati
Illinois Institute of Technology
University of Illinois
Indiana University
Iowa State University
The University of Iowa

Kansas State University
The University of Kansas
Loyola University
Marquette University
Michigan State University
The University of Michigan
University of Minnesota
University of Missouri
Northwestern University
University of Notre Dame

The Ohio State University
Ohio University
The Pennsylvania State University
Purdue University
Saint Louis University
Southern Illinois University
The University of Texas at Austin
Washington University
Wayne State University
The University of Wisconsin

NOTICE

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately-owned rights. Mention of commercial products, their manufacturers, or their suppliers in this publication does not imply or connote approval or disapproval of the product by Argonne National Laboratory or the U. S. Department of Energy.

ARGONNE NATIONAL LABORATORY
9700 South Cass Avenue
Argonne, Illinois 60439

CASE STUDY OF TOTAL ENERGY PLANT AT THE
KANSAS CITY TWA OVERHAUL BASE

MASTER

prepared by

Jack Faucett Associates, Inc.
5454 Wisconsin Avenue, Suite 1150
Chevy Chase, Maryland 20015

for

Energy and Environmental Systems Division
Argonne National Laboratory
under Argonne Contract 31-109-38-4016

December 30, 1977

DISCLAIMER

This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Work sponsored by

U.S. Department of Energy
Assistant Secretary for Conservation and Solar Applications
Buildings and Community Systems Division

This informal report presents preliminary results of ongoing work or work that is more limited in scope and depth than that described in formal reports issued by the Energy and Environmental Systems Division.

Available from
National Technical Information Service
5285 Port Royal Road
Springfield, Virginia 22161

TABLE OF CONTENTS

	<u>Page</u>
ABSTRACT	<i>vii</i>
1 INTRODUCTION-CONCLUSIONS	1
2 BACKGROUND EVENTS LEADING TO CONSTRUCTION OF THE TWA TOTAL ENERGY PLANT	3
2.1 TWA EXPANSION PLANS	3
2.2 MISSOURI PUBLIC SERVICE RATE INCREASE	4
2.3 SALES EFFORT IN BEHALF OF TOTAL ENERGY	4
2.4 DECISION FOR TOTAL ENERGY	5
2.5 TOTAL ENERGY PLANT CONSTRUCTION	8
3 ENERGY FACILITIES AND SYSTEM CONTROL	9
3.1 TOTAL ENERGY SYSTEM	9
3.2 OTHER ENERGY FACILITIES	14
3.3 POWER DISTRIBUTION SYSTEM	16
3.4 CONCLUSION	18
4 HISTORY OF OPERATION	20
4.1 PLANT PRODUCTION	20
4.2 FUEL SUPPLY	23
4.3 OPERATIONAL LABOR	25
4.4 PLANT MAINTENANCE	26
5 ECONOMIC AND ENERGY EFFICIENCY EVALUATION OF TWA TOTAL ENERGY PLANT	29
5.1 ECONOMIC-FINANCIAL EVALUATION	30
5.2 ENERGY EFFICIENCY EVALUATION	34
5.3 REASONS FOR TWA'S TOTAL ENERGY FAILURE	35
6 ALTERNATE (WHAT IF) SCENARIOS AND FUTURE PROSPECTS FOR THE TWA/MPS TOTAL ENERGY PLANT	42
6.1 SCENARIO I: WHAT IF THE TWA COMPLEX HAD RELIED ON MISSOURI PUBLIC SERVICE UTILITY CONNECTIONS FOR BACKUP IN CASE OF TOTAL ENERGY OUTAGE	42
6.2 SCENARIO II: WHAT IF TWA HAD BEEN ABLE TO BUY AND SELL POWER TO MISSOURI PUBLIC SERVICE SYSTEM	45
6.3 SCENARIO III: WHAT IF MPS HAD OWNED THE TWA TOTAL ENERGY PLANT FROM THE BEGINNING	46
6.4 CONCLUSION	46
ACKNOWLEDGMENTS.	47
APPENDIX A: DATA ASSEMBLY	48

LIST OF FIGURES

<u>No.</u>	<u>Title</u>	<u>Page</u>
3.1	TWA Complex Site System	10
3.2	Total Energy Plant Schematic	12
3.3	Steam Interconnection	15
3.4	Power Distribution System	17
4.1	Weekly Electric Power Demand Profile, 1972	21
4.2	Weekly Electric Power Demand Profile, July 1975	22
4.3	Heat Rate for Total Energy Gas Turbine Generators	22
4.4	TWA Overhaul Base Steam Usage, 1976-1977	24
5.1	Waste-Heat-Recovery Boiler Production Rates	37

LIST OF TABLES

<u>No.</u>	<u>Title</u>	<u>Page</u>
2.1	Energy Consultant's Estimates of Total Energy vs Purchased Power Costs, 1970-1975 (dollars)	6
2.2	Comparison of Load Studies	7
3.1	List of Total Energy Plant and Related Utility Building Equipment	11
3.2	List of Emergency Power Generators	18
4.1	Total Energy Plant Blackouts Due to Equipment Malfunction . .	24
4.2	Fuel Usage by Total Hours on Both Units, 1975	25
5.1	Yearly Summary of Energy Costs (thousands of dollars)	30
5.2	Purchased Power Alternative - Cost Trends (thousands of dollars)	32
5.3	Total Energy Average Cost Trends (thousands of dollars) . . .	33
5.4	Total Energy Marginal Cost Trends (thousands of dollars) . . .	34
5.5	Fuel Consumption - Energy Production Total Energy Plant . . .	35
5.6	Fuel Consumption - Energy Production Purchased Power Alternative	35
5.7	Kansas City, Missouri, Monthly Normal Air Temperature Data . .	38
6.1	Missouri Public Service Company Monthly Peak and Output . . .	44
A.1.a	Total Energy Plant Fuel Consumption - Energy Production Uncorrected Data, 1973	56
A.1.b	Total Energy Plant Fuel Consumption - Energy Production Uncorrected Data, 1974	57
A.1.c	Total Energy Plant Fuel Consumption - Energy Production Uncorrected Data, 1975	58
A.1.d	Total Energy Plant Fuel Consumption - Energy Production Uncorrected Data, 1976	59
A.2	Total Energy Plant Fuel Consumption - Energy Production, 1975	60
A.3.a	Total Energy Plant Fuel Consumption - Adjusted Data, 1973 . .	61
A.3.b	Total Energy Plant Fuel Consumption - Adjusted Data, 1974 . .	61
A.3.c	Total Energy Plant Fuel Consumption - Adjusted Data, 1975 . .	62
A.3.d	Total Energy Plant Fuel Consumption - Adjusted Data, 1976 . .	62
A.3.e	Total Energy Plant Fuel Consumption - Adjusted Data, 1977 . .	63
A.4.a(1)	Total Energy Plant Average Monthly Cost, 1973 (dollars) . . .	64
A.4.b(1)	Total Energy Plant Marginal Monthly Cost, 1973 (dollars) . . .	64
A.4.a(2)	Total Energy Plant Average Monthly Cost, 1974 (dollars) . . .	65

LIST OF TABLES (cont'd)

<u>No.</u>	<u>Title</u>	<u>Page</u>
A.4.b(2)	Total Energy Plant Marginal Monthly Cost, 1974 (dollars) . . .	65
A.4.a(3)	Total Energy Plant Average Monthly Cost, 1975 (dollars) . . .	66
A.4.b(3)	Total Energy Plant Marginal Monthly Cost, 1975 (dollars) . . .	66
A.4.a(4)	Total Energy Plant Average Monthly Cost, 1976 (dollars) . . .	67
A.4.b(4)	Total Energy Plant Marginal Monthly Cost, 1976 (dollars) . . .	67
A.4.a(5)	Total Energy Plant Average Monthly Cost, 1977 (dollars) . . .	68
A.4.b(5)	Total Energy Plant Marginal Monthly Cost, 1977 (dollars) . . .	68
A.5.a	Total Energy Plant Monthly Fuel Costs, 1973	69
A.5.b	Total Energy Plant Monthly Fuel Costs, 1974	69
A.5.c	Total Energy Plant Monthly Fuel Costs, 1975	70
A.5.d	Total Energy Plant Monthly Fuel Costs, 1976	70
A.5.e	Total Energy Plant Monthly Fuel Costs, 1977	71
A.6	Total Energy Plant Operating and Maintenance Costs, 1975 (dollars)	72
A.7	Total Energy Plant Capital Costs: Average and Marginal, 1975 (dollars)	73
A.8.a	Purchased Power Alternative Monthly Cost, 1973 (dollars) . . .	74
A.8.b	Purchased Power Alternative Monthly Cost, 1974 (dollars) . . .	75
A.8.c	Purchased Power Alternative Monthly Cost, 1975 (dollars) . . .	76
A.8.d	Purchased Power Alternative Monthly Cost, 1976 (dollars) . . .	77
A.8.e	Purchased Power Alternative Monthly Cost, 1977 (dollars) . . .	78
A.9	Purchased Power Alternative Electricity Costs, 1975 (dollars)	79
A.10	Purchased Power Alternative Steam Production Fuel Costs, 1975 (dollars)	80
A.11	Purchased Power Alternative Steam Production Costs, 1975 (dollars)	81

ABSTRACT

This case study evaluates the reasons for TWA's 1969 decision to build a total energy plant at its Kansas City overhaul base. Total energy was bought on the basis that it would reduce energy costs and, at the same time, provide more reliable and higher quality electric power. Reasons why these expectations did not materialize are analyzed, along with operational statistics, and total energy versus purchased power costs, forming a record that can aid the Department of Energy in determining the energy conservation potential of such nonindustrial applications of total energy in the United States. TWA's present status at the overhaul base is that of buying electric power from the Missouri Public Service Company. Steam produced under the total energy format by waste-heat recovery, is again being produced through the use of the previously existing combustion boiler capacity.

1 INTRODUCTION-CONCLUSIONS

The case study reported here concerns the Trans World Airlines (TWA) Missouri Public Service Company (MPS) total energy plant in Kansas City. As part of a Department of Energy/Argonne National Laboratory program, it is one of several case studies made to determine the energy conservation potential of such nonindustrial applications in the United States. Knowledge gained from these case studies will be used by the Department to develop strategies for continuing programs in energy conservation and in research and development. Of particular interest in the TWA/MPS study is the fact that it was made on a large, award-winning, total energy plant that has recently been sold to an electric utility and converted to a peak-load generator (without byproduct heat recovery) in the utility's system.

TWA's present status, after the plant sale, is that of buying electric power from the MPS system. And steam, formerly produced by waste-heat recovery, is being produced through the use of the combustion boiler capacity that existed at the TWA overhaul base before the total energy system was installed. Missouri Public Service Company, the plant's new owner, is using the former total energy plant as a peak-load generator. Because the plant no longer will be operated as a total energy plant, the heat recovery equipment is being removed. As a peaking unit in the MPS system, the electric generators most likely will be used only during those relatively few hours in July and August when the load on the Missouri Public Service system is near its installed generating capacity.

TWA's decision to build the total energy plant was made at a time (1969) when its Kansas City complex was doubling in size and the MPS electric rates were increasing between 20 and 25%. Total energy was bought on the basis that it would reduce TWA energy costs and, at the same time, provide more reliable and higher quality electric power.

Technically, the TWA total energy plant performed well in that it did provide high-quality electric power with reasonable reliability. (This level of performance was attained even though the two electric generators designed into the plant proved insufficient to guarantee reliability; the plant should have been designed to contain more and smaller generating units.) However, the plant consumed far more fuel than originally was estimated for TWA's needs, and required far more maintenance and operating labor than had been anticipated initially. The original engineering analyses performed on the total energy plant did not include details simulating TWA's energy (electric and steam) needs nor how these needs would be supplied, using the actual hardware planned for installation. Such a simulation would have quickly shown that the assumed plant energy efficiencies were unrealistic.

Operating and maintenance expenses beyond those anticipated probably resulted from TWA's use of converted aircraft jet engines for stationary use. The sum of their experience with aircraft engine conversions for electric generator use was insufficient to warrant the optimistic assumptions made about engine and plant maintenance expenses and automatic operation capability of the plant. Moreover, in planning for major maintenance on the power turbines and electric generators, it was apparently presumed that additional generator capacity would be available before such maintenance would be needed.

A spare jet engine and procedures for rapid engine replacement were provided for performance of nonroutine engine maintenance, but no provisions were made for these times when major generator maintenance would be required. Thus, TWA's power needs could not be supplied in the event of having one generator down for extensive repairs without adding additional power generation capacity or adding an interconnection with the MPS electric utility system -- and both of these options were very expensive.

The TWA total energy plant failed not only economically but also as an energy conserver. Energy efficiency was less than half of the 70% anticipated. Consequently, the purchased power alternative (with TWA combustion-boiler, space-conditioning steam generation) to total energy was more energy efficient (45%) than total energy (35%). On the other hand, if TWA had been purchasing power between 1973 and 1977, 180,000 tons of electric utility coal would have replaced 5 million MCF of natural gas and 15 million gal of jet fuel consumed by TWA's total energy plant. (About 95% of MPS fuel is coal.)

Cost and energy comparisons of total energy with the purchased power alternative are so unfavorable to total energy that the following two alternate total energy scenarios would not have altered the conclusions that oil- and gas-fired gas-turbine-powered total energy cannot compete in Kansas City with coal-generated, purchased electricity and gas-generated steam:

1. The total energy plant having electric utility backup rather than onsite reserve capacity for backup, and
2. Electric utility ownership of the total energy plant with sales of steam and electricity to TWA.

Furthermore, as the price of gas rises relative to coal, any fuel cost advantage that gas- and petroleum-fueled total energy might once have had has disappeared.

Finally, the case study reported here shows that had TWA known in 1969 what it knows now, it would not have purchased the total energy plant; had it known in 1971-72 about the incremental costs of total energy plant operation, it would have liquidated its total energy investment as quickly as possible; and had it shut down the total energy plant and moved to purchased power at the beginning of 1973 rather than in 1977, it would have saved more than \$4 million in month-by-month costs.

2 BACKGROUND EVENTS LEADING TO CONSTRUCTION OF THE TWA TOTAL ENERGY PLANT

In 1969, several contributing circumstances motivated TWA to build a total energy plant at its overhaul base in Kansas City. After the total energy plant was built, the TWA complex was separated from the electric grid, and the total energy plant provided all electrical needs and most thermal energy needs of the overhaul base, nearby administration center, and pilot training facility. Among the events that caused this shift from purchased power to total energy were:

1. TWA's plans to expand its airport-located facilities to provide an additional aircraft overhaul plant, a new corporate administration center, and pilot training establishment,
2. A proposal by the electric utility, Missouri Public Service Company (MPS), serving TWA to raise prices for electric power by 20-25%, and
3. A sales effort by an Illinois-based energy engineering firm to interest the TWA headquarters staff in the potential of total energy (onsite power generation with waste-heat recovery) for the TWA Kansas City airport complex.

In addition to this combination of events, the utility substation at the TWA base would have to undergo costly upgrading to meet the needs of the new facilities. Hence, it became necessary to TWA quickly to evaluate these factors and decide on whether to provide onsite electric generation.

2.1 TWA EXPANSION PLANS

In the late 1960s the airline industry was in a boom period. Business was expanding rapidly and the industry was looking forward to sustained growth. In response to this business outlook, TWA planned major expansions of its centralized aircraft overhaul facilities in Kansas City.* The TWA expansion plan had two parts. In 1969 the first part was in the process of being constructed and was scheduled for completion by the summer of 1970. The second part was to have been slightly smaller and was to have been started later and completed in 1975. In 1969 TWA had about 1.1 million sq ft of airport located facilities. The first expansion was adding about 1.0 million sq ft and the second, was expected to add about another 0.9 million sq ft. Completion of Part I construction was delayed about a year and a half by construction trades labor disputes. Part II expansions were scrapped, due to

*TWA has its headquarters in New York City. It planned to consolidate its long-standing Kansas City airport operation, both aircraft maintenance and administration. The consolidation plan, however, did not involve services and functions related to scheduled TWA passenger and freight service; its overhaul, administrative, and pilot training facilities are at a remote part of the airport, completely separate from the passenger terminal.

shortfalls in airline industry growth. Consequently, the present TWA Kansas City Airport complex comprises about 2.1 million sq ft.

2.2 MISSOURI PUBLIC SERVICE RATE INCREASE

A rate increase was proposed by MPS in 1969 to the Missouri Public Utilities Commission that would increase electric power charges to TWA between 20 and 25%. In approximate figures, the new rate would have meant an increase of \$85,000 in yearly electric power costs, from \$357,000 to \$442,000. By 1975, this difference could have grown to about \$307,200 if the rate remained unchanged. Moreover, power outage experience (13 outages from May 1968-May 1969) and resultant overhaul-base downtime was considered excessive by New York TWA officials. Consequently, TWA officials were disturbed by the MPS rate increase and sought ways to counter its effect.

2.3 SALES EFFORT IN BEHALF OF TOTAL ENERGY

Early in 1969 an energy consulting company, Tri-Energy Corporation (specialists in total energy and electric generation), met with members of the New York-based corporate level staff responsible for all TWA facilities. Material was provided to TWA concerning the energy consulting capabilities of Tri-Energy Corporation and the potential of total energy.

Shortly after the initial contact with the consultants, TWA was informed of the impending electric rate increase requested by Missouri Public Service Company. Tri-Energy then was retained by TWA to provide analysis assistance to contest the increase and to develop alternative strategies in response to it. As part of this program, Tri-Energy was commissioned in April 1969, to prepare an analysis to total energy for application to the Kansas City Airport complex. A preliminary report on total energy was completed in May and the final one, in July. These reports provided projections and estimates of:

- Current and future electric and thermal energy needs at the Kansas City Airport complex,
- How dual-fueled, gas-turbine-powered electric generators with waste-heat recovery could meet the electric and thermal energy needs of the complex, and
- Cost of total energy vs purchased power and the current and long-term cost advantages that Tri-Energy expected from total energy in a TWA application.

The projection and estimates in the preliminary report were based on installation of multiple 2080 kW generators, powered by dual-fuel-capability Allison gas turbines.*

Later, during June, the larger JT3 jet engines, of which TWA had a surplus stock, were briefly evaluated for total energy electric generation use, but were rejected because they could not readily be converted to dual-fuel capability. At this time the large JT4 jet (as converted to the GG4 industrial configuration),** an engine used to power early Boeing 707 aircraft, was also evaluated for total energy use and was found suitable by Tri-Energy and TWA (New York headquarters staff).

Although the converted JT4 was considered suitable for TWA onsite electric generation, smaller prime movers (and more of them) would clearly have been preferable. The fact that TWA had surplus JT4 engines and an onsite engine servicing facility at the overhaul base were central factors in the decision that JT4 engines would work out. In addition, TWA may have been anticipating that a demonstrably successful total energy facility powered by the converted JT4 jets might stimulate a market demand for their surplus JT4 engines.

In their May 1969 report, based on using multiple Allison prime movers, Tri-Energy estimated total energy cost, purchased power costs, and savings for the 1970 to 1975 time period, as shown in Table 2.1. In their July report, based on using JT4 jet engines, they estimated savings from total energy at \$522,711-\$698,295 per year, depending on how much the TWA facilities were expanded.

2.4 DECISION FOR TOTAL ENERGY

The TWA corporate level staff in charge of facilities became persuaded (June 1969) of the superiority of total energy over the purchased power alternative. This decision began the corporate process that led to the ultimate approval of the Board of Directors in early 1970 to build the total energy plant. However, in the interim before the Board's approval, analyses of alternate energy arrangements were made by:

1. The TWA facilities engineering staff of the Kansas City overhaul base;

* Dual fuel capability was necessary in order to take advantage of the very low price of natural gas when it was provided on an interruptible basis. During natural gas interruptions (259 hours during 1969 in Kansas City), the alternate fueling system, using liquid jet fuel, would be put into operation. The back-up liquid jet fuel capability also contributed to plant reliability. If problems develop in the primary fueling system, a back-up system becomes available for immediate use in a dual-fuel prime mover under dual-fuel capability.

**A design package existed for converting the JT4 aircraft jet to the GG4 dual-fueled, industrial gas-turbine engine.

Table 2.1 Energy Consultant's Estimates of Total Energy vs Purchased Power Costs, 1970-1975 (dollars)^a

Year	Total Energy	Purchased Power	Savings
1970	\$ 688 572	\$ 961 722	\$273 150
1971	860 935	1 246 209	385 274
1972	908 859	1 343 560	434 701
1974	1 011 120	1 482 134	471 014
1975	1 091 266	1 601 464	510 198

^aImplicit in these estimates was an assumption that total energy is more than 70% energy efficient.

Source: Tri-Energy Corporation, *TWA Preliminary Report-Feasibility of Total Energy*, Mid-Continental International Airport, Overhaul Base Facilities, Kansas City, Missouri, May, 1969.

2. The consulting engineering firm of Burns and McDonnell (which traditionally does most of TWA's Kansas City engineering work); and
3. Sargent and Lundy, of Chicago, Illinois, at the request of MPS.

These analyses were the basis of much controversy.

The TWA facilities engineering staff in Kansas City contested the electric load demand projections generated by Tri-Energy and Burns and McDonnell as being too high (see Table 2.2) and suggested that the wide variance in the kW demand among the three analyses should be resolved before reliable estimates of the economic advantages of total energy could be determined.

In addition, the TWA Kansas City facility engineers observed that TWA had no experience with stationary-gas-turbine engines. Moreover, they asserted that the following unsupported assumptions were made in the Tri-Energy analyses:*

1. "... suitable modifications can be made to a 'flying' jet aircraft engine to convert it to a reliable, dual-fuel-industrial gas turbine having an efficient generating capacity of approximately 20,000 kW and a repeatable service life between overhauls of at least 10,000 hours,

*Facilities Engineering Staff, TWA Kansas City Overhaul Base, *Review of Three Total Energy Studies*, 1969.

Table 2.2 Comparison of Load Studies

	<u>1968</u>	<u>1970</u>	<u>1972</u>	<u>1975</u>
	kW	kW	kW	kW
Burns & McDonnell	7 650	24 067	25 187	31 947
Tri-Energy	6 000	14 700	15 900	28 720
TWA (Kansas City)	5 650	12 355	16 895	20 600

Source: TWA Kansas City, Overhaul Base, Facilities Engineering Staff Report, *Review of Three Total Energy Studies*, 1969.

2. "... the gas turbines will be capable of operating relatively efficiently at partial loads,
3. "all total energy plant equipment will be completely controlled and monitored by fully automatic equipment, [and]
4. "the quality of the current and the reliability of plant equipment will be equal or better than [those of] any available public utility source";

and that *until* these assumptions were backed up by operational histories of actual energy plants, economic analyses of total energy for the overhaul base would be inconclusive.

On the total energy issue, a gulf existed between the staff officials of the New York City TWA facilities and the staff engineers of the Kansas City Overhaul base who felt strongly that purchased power was superior. In addition to the maneuvering within TWA over total energy, there was maneuvering between TWA and Missouri Public Service Company. The TWA facility was one of the service company's larger customers whose business they did not want to lose.

In August 1969, MPS commissioned Sargent and Lundy Engineers of Chicago, Illinois, to evaluate purchased power vs total energy at the TWA Kansas City complex. The study was completed in three weeks and drew mainly on:

- Sargent and Lundy's experience and judgment in power generation rather than detailed site-specific engineering analysis, and
- Information provided by MPS, including electric and gas rate information, and a copy of Tri-Energy's July 1969 analysis of total energy for TWA.

The Sargent and Lundy analysis came to very different conclusions about total energy. They estimated a yearly cost advantage of \$580,409 for pur-

chased power over total energy -- a difference of nearly \$1.2 million compared to the Tri-Energy estimates.

After this study, MPS vigorously urged TWA to back away from total energy. This effort included contacts between the President of MPS and the President of TWA. The attempt to reverse the tide toward total energy failed and in October, 1969, engineering design and procurement for construction of the total energy plant began on a tentative basis. Official approval of the TWA Board of Directors came in early 1970.

2.5 TOTAL ENERGY PLANT CONSTRUCTION

TWA management's tentative approval to go ahead with total energy was required in October 1969 so that total energy plant construction would be completed when TWA's other new facilities (administration center, super hangar, and pilot training center) were to be finished in the fall of 1970. The tentative October 1969 go-ahead authorized procurement action on long lead time components and advanced engineering design work. In order to meet the fall 1970 deadline for plant startup, actual construction of onsite facilities was scheduled to begin early in 1970.

Ultimate completion of the total energy (electric generation plus steam generation) plant construction was delayed about two and a half years. Electric generation capability was delayed about 10 months (to the summer of 1971), and waste heat steam generation capability was delayed until early 1973. These delays were primarily the result of construction labor strikes during the prime summer construction months of 1970 and 1971 and problems with the total energy steam generation controls. However, since these strikes also delayed the other TWA expansion projects, the total energy plant delays did not delay use of the other newly constructed TWA facilities. The electric generation part of the total energy plant was available for use by the time TWA electric demand increased beyond the capacity of the existing MPS substation. In fact, for the first few months of total energy plant operation, the total energy plant was run in parallel and integrated with the MPS system to which it provided power. The quality of the TWA-produced power was very high and the interconnection continued until an equipment malfunction at the TWA substation caused the total energy plant to disconnect from the MPS system. From that time in 1971 until April 1977 when MPS assumed ownership of the total energy plant and TWA reconnected to the MPS system, the TWA Kansas City complex was isolated from outside electric power sources.

3 ENERGY FACILITIES AND SYSTEM CONTROL

The major equipment components of the total energy plant, such as the turbine-generators, are housed in the total energy building. Other energy equipment, including combustion boilers, steam driven chillers, and emergency diesel generators, is housed in the utility building and Bldg. 2 power house. Electric heating and cooling equipment provided space conditioning for the pilot training building and electric chillers, and oil heated hot water provided space conditioning for the administration center. As shown by the site plan in Fig. 3.1, the total energy plant, utility building, and Bldgs. 1 and 2 (including the super hangar) are all situated in one area, whereas the centers for administration and pilot training are geographically separated. As a result, only electricity was provided to these two centers by the total energy plant and cooling was provided by onsite equipment.

In this chapter, the physical aspects and operations of the different total energy components are discussed in relation to the overall system. The operations of the overall control system and the power distribution system are also discussed to show how electric power backup operated.

3.1 TOTAL ENERGY SYSTEM

The total energy system comprised mainly the turbine-generators in the total energy plant and the auxilliary equipment in the utility building. The total energy plant served the electrical needs of all the facilities at the TWA complex as well as all the steam needs of the super hangar (part of Bldg. 1) and most of the steam needs of Bldg. 2 and the rest of Bldg. 1. Table 3.1 lists all the system's major components and Fig. 3.2 shows how total energy plant components were connected. Emergency power was provided by separate emergency generators, the discussion of which is presented later in the section on power distribution. The following sections describe how the equipment operated.

3.1.1 Gas Generators

The two jet engines (gas generators) were TWA surplus flight engines that were retrofitted for dual-fuel operation. Natural gas was the primary fuel and liquid jet fuel, the alternate. In addition to two operating engines, a third was stored nearby to serve as a rapid replacement in the event that an operating engine malfunctioned. All operating modes of the engines could be automatically controlled and they included the following:

1. Fuel: natural gas or jet fuel,
2. Starting mode: manual or automatic,
3. Load schedule: base, peak, or max peak,
4. Adjust governor: regulate fuel in response to gas generator speed and exhaust temperature, and power turbine speed and output.

Fig. 3.1 TWA Complex Site System

Table 3.1 List of Total Energy Plant and Related Utility Building Equipment

A. Total Energy Plant	
<u>Equipment</u>	<u>Specifications</u>
1. Gas generators (2 units)	Pratt & Whitney JT4 flight engines modified to GG4A-7DF configuration
2. Power turbines (2 units)	Worthington EA214 two-stage, gas turbines
3. Electric generators (2 units)	Westinghouse: 20,150 kVA, 12,500 V, 60 Hz, 3 phase
4. Heat recovery boilers (2 units)	General Electric 100,000 lb/hr, 250 psig dry and saturated steam
5. Gas booster compressors	Worthington: CUB H-2, two-cylinder, single stage, double-acting; 100 psig suction, 300 psig discharge
6. Cooling towers (2 units)	Marley: Model 8605, Series NC, double-flow
B. Utility Building	
<u>Equipment</u>	<u>Specifications</u>
1. Steam boilers (3 units)	Murray; 110,000 lb/hr, 250 psig
2. Air conditioning unit (1 unit)	Carrier-Elliott turbine; 3,500 ton centrifugal, 250 psig steam input

A load-sharing, time-error frequency controller was used to balance loading between turbine-generator units when two units were operating. It also maintained a constant average frequency by comparing the actual frequency with a crystal oscillator time standard and correcting the accumulated frequency deviations.

3.1.2 Turbine-Generator Units

The hot exhaust gases from each jet engine were delivered into a power turbine that then drove a 20,150 kVA water-cooled electric generator. Each turbine-generator unit was provided with two lubricating systems: one system for the gas generator and one, for the power turbine and electric generator. The lube oil, supplied from a lube console (one for each generator), was cooled by two coolers mounted next to the console. The oil coolers were oil-to-water heat exchangers using cooling water from the cooling tower system.

Fig. 3.2 Total Energy Plant Schematic

3.1.3 Heat Recovery Boilers

Exhaust gases from each power turbine were fed into a General Electric heat recovery boiler to produce steam. Each boiler was capable of producing 100,000 lb/hr saturated steam at 250 psig. The amount of steam that could be produced depended upon the turbine exhaust temperature and the gas flow; exhaust temperature ranged from 600-950°F. The turbine exhaust temperature depended in turn upon the generator output. To produce steam from the waste heat, the feedwater was pumped into the boilers and circulated through horizontal tubes to enable heat exchange to take place. The feedwater entered at a temperature of 220°F and the output was 250 psig saturated steam.

The important controls provided for each boiler included: (1) a waste heat bypass damper, (2) a steam dump system, and (3) a two-element feedwater control system. The waste heat bypass damper served to regulate the input of waste heat into the boiler. Whenever there was an increase in steam pressure, an indication of low steam demand, the damper valve would open automatically to divert the waste heat to the atmosphere. An increase in demand would reverse the procedure. The steam dump system served to relieve excess steam when the total steam demand was lower than the minimum steam production. Even when the damper was fully open, some exhaust gas would still flow to the boilers. This steam dump system consisted of a pneumatically operated back pressure valve that discharged excess steam into the bypass stack immediately below the exhaust silencer. The back pressure valve was set at 260 psig, 10 psig higher than the operating pressure of 250 psig. The feedwater control system regulated water flow in response to both drum water level and steam flow from the boiler. In addition to these major controls, there were also other minor control systems, such as the continuous blowdown control system.

3.1.4 Gas Booster Compressors

The two gas compressors were Worthington 500-hp reciprocating units. Each unit was capable of providing compressed gas needed for one turbine-generator under full electric load. The compressors were needed because the jet engines required 300 psig gas, whereas the line gas was supplied by the Gas Service Company at a pressure of only 100 psig. The gas booster compressor system consisted of two packaged booster compressors; two glycol cooling systems, one for each compressor; a receiver for the high pressure gas; and a gas pressure regulative valve. Each compressor was controlled by a five-step-cylinder-unloader capacity control, acting in response to gas pressure in the receiver.

Early in the life of the total energy plant, problems were experienced with the fuel gas compressors. The problems arose because the compressors typically were required to operate for long periods of time at only a small fraction of their rated capacity. The constant low level operation subjected the compressor parts to abnormal stress, fatigue, and excessive wear, which caused compressor failure. Modifications were then made to the compressors that allowed them to operate satisfactorily at the low output levels required by the total energy plant.

3.1.5 Cooling Towers

Each oil cooling tower system was housed outdoors and provided cooling water to one of the generator units. The two towers were interconnected so that, in an emergency, cooling water could be supplied to both generator units and their lube oil systems. The overall operation control was such that whenever the generator units were started, the cooling tower pumps and fans would start, running from low speed to high. Whenever the water temperature dropped, the fan would automatically shift from high speed to low, and then to stop if the temperature was low enough. On a turbine-generator unit shutdown, the pump and fan would continue to run for 10 minutes and then stop. The pump and fan starters could be controlled manually as well, whenever necessary.

3.1.6 Steam Boilers

There were three gas-fired back-up steam boilers in the utility building. These boilers were fired whenever the steam produced from waste heat boilers was not enough to meet the total steam demand of the super hangar and during waste heat boiler outages. The firing of these boilers was automatically controlled in response to the pressure in the steam line.

The steam produced by the waste heat boilers and auxilliary boilers was supplied mainly to the super hangar (part of Bldg. 1) for heating. Any excess waste heat boiler steam was supplied to the rest of Bldg. 1 and to Bldg. 2 through an interconnection. The five boilers in Bldg. 2 supplied a 125-psig steam system, as explained below, that served the needs of Bldg. 2 and part of Bldg. 1. That system was connected with the total energy and utility building steam system (250-psig) through a pressure reducing valve (see Fig. 3.3) to allow excess 250-psig steam to supplement the 125-psig system, thus reducing the quantity of steam to be generated by the combustion boilers in Bldg. 2 and saving fuel costs. The primary fuel for these utility building auxilliary boilers was natural gas, with jet fuel as standby.

3.1.7 Air Conditioning Unit

A 3,500-ton air conditioning unit in the utility building was powered by the 250-psig steam produced by the waste heat boilers. It supplied chilled water to the super hangar for space cooling in the summer. Any excess steam that was not needed for this air conditioning unit was supplied through the steam lines to Bldg. 2, where there were three steam driven air conditioning units to serve the needs of Bldgs. 1 and 2. (See below.)

3.2 OTHER ENERGY FACILITIES

In addition to the equipment used for the total energy system, there were other energy facilities in various buildings at the TWA complex. Some of these facilities, such as those in Bldg. 2, were installed when the TWA complex was supplied by purchased power prior to 1971. After the total energy plant began operation, these facilities still remained in use but at a lower level. Altogether there were five steam boilers and three air conditioning

Fig. 3.3 Steam Interconnection

units, in Bldg. 2. Additional heating and cooling equipment was also installed in the administration center and the pilot training center.

3.2.1 Building 2 (Old Power House)

The old power house in Bldg. 2 contained the following energy facilities:

1. Steam boilers
 - a. 3 units Keeler; 60,000 lb/hr, 125 psig saturated
 - b. 2 units Union Iron Works; 30,000 lb/hr, 125 psig saturated
2. Air conditioning units
 - a. 2 units Carrier-Murray turbines; 850 tons
 - b. 1 unit Carrier-Murray turbine; 1,270 tons

As mentioned, the five steam generating units in Bldg. 2 supplied 125 psig steam to all the facilities in Bldg. 2 and part of Bldg. 1. Any excess steam from the total energy plant not needed by the super hangar was to be used first and the remaining steam demand was to be met by firing these boilers. The primary fuel was natural gas with #6 fuel oil as the standby fuel. In the summer, the steam was used to power the three air conditioning units that produced chilled water to cool the buildings.

3.2.2 Administration Center and Pilot Training Center

Due to the distance separating the total energy plant from the administration and the pilot training centers, and the fact that most of the administration center's electric air conditioning chillers were purchased before the decision to go to total energy, only electricity was supplied to these facilities. The heating and cooling needs in the administration center were met by separate oil-fired, hot-water-heating units and electric air conditioners. The pilot training center was electrically heated and cooled.

3.3 POWER DISTRIBUTION SYSTEM

The total energy plant supplied electricity to all the facilities in the TWA complex. The power was distributed via a 12,500-volt distribution system that fed two electrical buses, Bus A and Bus B, located in the utility building (see Fig. 3.4). The power from Bus A was distributed to general facilities. Bus B was connected only to the critical loads. To supply essential power when the total energy plant shut down, there were a total of three 1-MW emergency generators located in the utility building and Bldg. 2. In addition, there were five 0.8-MW emergency generators and an uninterrupt-

Fig. 3.4 Power Distribution System

ible power supply (UPS) system* in the administration center. The locations and capacity of these emergency generators are listed in Table 3.2. It should be noted, however, that the emergency power system in the administration center was separate from the rest of the emergency power system. During a power outage, the emergency generators in the administration center supplied only the center itself, and the UPS system supplied only the critical reservations computer located in the administration center. This system was necessary because, in the event of power failure, it would take approximately 70 seconds before the emergency generators could be brought on line and this time lapse could cause loss of the computer memory banks. The overall emergency power system operated as follows.

When a power outage occurred, generator No. 2 in Bldg. 2 (see Fig. 3.4), one of three emergency generators available, would start up first and feed only Bus B, which fed in turn only essential loads at each facility, except the administration center. Emergency generator No. 1 would start up next and pick up more of the essential loads that were fed by Bus B. As Bus B was energized, it was fed by the now operating emergency generator No. 3, located in the utility building. As soon as the generator units in the total energy plant were brought back on line, the three emergency generators would be shut down and normal power would be restored. There was a time lapse, however, between emergency power and the return of normal power, since the emergency generators and main turbine generators could not be run in parallel. It should be noted from Fig. 3.4 that a tie existed between the emergency power system in the administration center and Bus B. The tie was implemented so that in the event that Bus B was not able to carry all the critical loads, the emergency power in the administration center could be tapped temporarily.

3.4 CONCLUSION

The total energy facilities were well designed in that there were few operational problems. However, most of the facilities had excess capacity. For example, one 18-MW turbine-generator could have handled the entire load of the TWA complex most of the time. As a result of this underutilization, some

Table 3.2 List of Emergency Power Generators

No. of Units	Capacity	Location
1	1 000 kW/each	Utility Building
2	1 000 kW/each	Bldg. 2
5	800 kW/each	Admin. Ctr.

*An uninterruptible power supply (UPS) system is essentially a group of storage batteries that are constantly charged by the normal power supply and emit power instantaneously when the normal power supply is interrupted. In this particular system, there are four 1-MW batteries that together can supply continuous power for 15 minutes.

of the components were not operating efficiently and problems developed. The gas compressors, for example, often overheated. Furthermore, although the entire system was equipped with an automatic control system, some of the operations had to be performed manually, adding extra operating costs. These operational aspects are discussed in the next chapter.

4. HISTORY OF OPERATION

When the total energy plant began supplying electricity in the late summer of 1971, only one of the two turbine-generators was in operation and only electricity was supplied. In the fall of 1971, the other generator began to operate, but it was not until 1973 that the waste-heat-recovery boilers began supplying steam. From then to 1975 both generating units were on line most of the time. From mid-1975 to April 1977, when the total energy plant was sold to the Missouri Public Service Company, only one unit usually operated. During this entire period of operation, the total electric demand of the TWA complex did not increase as much as expected and the electric generators initially installed had more than sufficient capacity to handle all the loads. This chapter discusses the historical operation of the total energy plant and some of the problems the total energy plant experienced.

4.1 PLANT PRODUCTION

In 1971, one of the two turbine-generator units installed in the total energy plant was used to supply electricity to the entire TWA complex. Later in the year, the other unit was put into operation and from then on both were used to carry the entire load. During these early months the total energy plant was still connected to the Missouri Public Service Company (MPS) system. However, an explosion occurred in the MPS substation at the TWA complex and disrupted the interconnection in late 1971. From then until spring 1977, the connection was never remade and all the electrical needs of the TWA complex were met by the total energy plant until April 1977 when the plant was sold to MPS.

In the beginning of the total energy plant operation, both of the 18-MW generators were run all the time despite the fact that the total load was usually below 12 MW. This dual operation was put into effect to provide the spinning reserve that TWA felt was necessary to maintain a reliable power source for some essential loads (particularly the reservation's computer). As shown by one of the earlier (1972) weekly electrical demand profiles (Fig. 4.1), one unit could easily have carried the entire load of 12 MW. But both units were on line most of the time until the uninterruptible power supply (UPS) system was installed in 1975. The UPS system provided the necessary emergency power to the critical TWA airline reservations computer from mid-1975 on, so spinning reserve was no longer needed. Over the period from 1972 to 1977, the electricity demand of the base increased only slightly. A typical weekly demand profile for July 1975 is shown in Fig. 4.2. (It should be noted that due to the lack of data only the outputs during the first two shifts of a day are shown.) From Mondays through Fridays, the demand was fairly constant as there were no peaks. On Saturdays and Sundays, very little power was needed and only one generator usually operated. The average demand in the whole period was about 11 MW and the average monthly output was about 8000 kWh. During the entire period of operation, no major problems occurred although the engines ran very inefficiently. As shown by the engine turbine performance curves in Fig. 4.3, the most efficient generator output was at a load of about 18 MW; but since the output per generator was always much less, a higher heat input per kWh was needed.

Fig. 4.1 Weekly Electric Power Demand Profile, 1972

Fig. 4.2 Weekly Electric Power Demand Profile, July 1975

Fig. 4.3 Heat Rate for Total Energy Gas Turbine Generators

During the whole period when the total energy plant was operating, 21 complete power outages occurred, averaging to about four per year, and comparing favorably with the MPS outage history before 1971. From April 16, 1968, to April 28, 1969, MPS had 14 power outages. The dates and durations of total energy plant blackouts are listed in Table 4.1. There were no blackouts in 1973 and 1975.

In addition to electricity for the whole TWA complex (including overhaul base, administration center, and pilot training center), the total energy plant provided steam for most of the space conditioning and process heat needs of the overhaul base. Steam needed in excess of that produced by the total energy plant was generated in combustion boilers in the Bldg. 2 power house.

Since total energy plant output was governed by electric demand, steam output paralleled electric output. Most of the time a steam deficit existed between total energy steam production and steam demand, but during those few times when steam production, or production capability, exceeded demand, either exhaust gas from the turbine generators was dumped before entering the waste heat boilers or unneeded steam was dumped from the boilers.

TWA steam demand was greatest in the summer and winter when steam is used for air conditioning and heating. Since 80-90% of TWA overhaul base steam is needed for space conditioning, steam needs in the spring and fall, when the weather is temperate, are relatively low. Figure 4.4 shows the overhaul-base steam usage for 1976-1977.

4.2 FUEL SUPPLY

Natural gas was the primary fuel for the total energy plant, since it was the least expensive fuel available. However, since gas was supplied on an interruptible basis, alternate standby fueling was required for periods when the gas supply was curtailed. The TWA overhaul base was classified as a large industrial user of natural gas while it operated as a total energy plant. Before that it had been classified as a large commercial user and is so classified now.

Based on TWA's gas consumption of 3,000-10,000 MCF per day, the overhaul base was classified in such a way that the gas supply could be cut 100% whenever curtailment was in effect. Hence, there were days in the winter months (December, January, February, and March) during which no gas was available and the standby jet fuel had to be used instead. From the fuel usage data shown in Table 4.2, it can be seen that in the winter months, gas and jet fuel usage was about the same, but in the summer months, very little jet fuel was used. The switching from one fuel to another could be accomplished while the units were on line. Upon activation of the fuel select switch, the fuel change would take place automatically.

Table 4.1 Total Energy Plant Blackouts Due to Equipment Malfunction

	Date	Duration
1.	1-30-72	5 hr
2.	5-4-72	25 min
3.	5-4-72	15 min
4.	6-19-72	5 hr 17 min
5.	6-20-72	2 hr
6.	12-4-72	1 hr 43 min
7.	8-22-74	2 hr 26 min
8.	1-8-76	5 hr 20 min
9.	1-8-76	6 hr
10.	5-5-76	3 hr 34 min
11.	9-8-76	2 hr 59 min
12.	9-23-76	57 min
13.	11-15-76	38 min
14.	11-15-76	30 min
15.	11-18-76	27 min
16.	11-23-76	31 min
17.	12-23-76	38 min
18.	3-29-77	16 hr 8 min
19.	3-30-77	29 min
20.	3-30-77	1 hr 20 min
21.	3-30-77	31 min

Fig. 4.4 TWA Overhaul Base Steam Usage, 1976-1977

Table 4.2 Fuel Usage by Total Hours on Both Units, 1975

Month	Generator Unit Hours on Natural Gas	Generator Unit Hours on Jet Fuel	Percent on Natural Gas	Percent on Jet Fuel
January	607 ^a	851 ^a	42%	58%
February	268	1 217	18	82
March	558	766	42	58
April	947	532	64	36
May	700	700	50	50
June	843	638	57	43
July	1 056	80	93	7
August	854	16	98	2
September	758	8	99	1
October	714	55	93	7
November	738	96	88	12
December	463	263	64	36

^aHours add to more than 720 or 744 per month because two units were frequently operating at one time.

The gas was supplied at 100 psig and was compressed to 300 psig by two gas booster compressors, one for each engine. The jet fuel was delivered to the engines by a liquid fuel pumping system from two 30,000-gal underground storage tanks. The average fuel consumption per hour was about 200 MCF of gas or 1000 gallons of jet fuel. One of the most serious problems with the total energy plant occurred with the gas compressors. The compressors were designed for high gas flow, but, as discussed earlier, the output of each generator was usually very low. At low gas usage levels the compressors were subject to stress and usage for which they were not designed. Consequently, the compressors failed and had to be modified to meet TWA's needs.

4.3 OPERATIONAL LABOR

The total energy plant was designed to operate fully automatically, without full-time operating personnel. However, the automatic controls installed were designed for intermittent use with remotely controlled, peaking power plants rather than constantly running grid-isolated power plants. As such, the controls were designed primarily to protect the generating equipment rather than for reliability of power plant operation. Consequently, it was found that reliance on the automatic controls led to unwarranted power plant shutdowns, plant outages, and blackouts. Human operators were found to be superior to the automatic controls, and since the expense to the overhaul base of an unplanned blackout was so large, TWA stationed human operators in the

plant 24 hours a day, adding a significant expense to total energy plant operations.

4.4 PLANT MAINTENANCE

Originally, total energy plant maintenance was expected to be about a \$100,000/yr operation. This estimate, however, proved to be far below the actual level of total energy plant maintenance, which was over \$300,000 per year.

TWA maintenance on the total energy plant fell into three categories:

1. Routine, and periodic repair and maintenance,
2. Special maintenance and repair, and
3. Engine maintenance and repair done in TWA's engine overhaul shops.

4.4.1 Routine and Periodic Maintenance

This category included all the housekeeping activities needed to keep the plant running smoothly. Among these operations were:

Periodic equipment lubrication,
Equipment cleaning,
Instrument calibration,
Fuel nozzle change, and
Electrical relay cleaning and replacement.

4.4.2 Special Maintenance Modification and Repair

This category included the more major repair and maintenance jobs done on the total energy plant. Equipment sent out for work under contract with other organizations is also included, but engine repairs done in TWA shops are not. Repairs and modifications in this category covered:

Replacement of generator exciter brushes,
Alignments of generator exciter,
A gas compressor modification required for compressor operation at low output levels,
Replacement of power turbine bearings,
Fuel nozzle replacement, and
Repairs in turbine exhaust stock expansion points.

4.4.3 Shop Repairs of Jet Engines

When engine maintenance on installed jet engines could not be performed quickly, they were removed and sent to TWA's aircraft engine repair shop. A standby engine was then installed in order to return the power generator to operation or standby readiness.

It was anticipated originally that the converted aircraft jet engines powering the total energy plant would operate 10,000 hr in service between visits to the repair shop. TWA shop repair records show that the engines were in the shop three times the expected rate or about once out of every 3,300 hr of operation. In addition, TWA total energy plant operating supervisors stated that the engines visited the shops about 8 more times than the 24 the shop repair records show. The additional work was probably minor (yet, even minor work is expensive in an aircraft engine repair shop) and apparently was not recorded in shop records.

A number of not so firmly held impressions and conclusions emerge from discussions with a number of TWA personnel about total energy plant engine repairs. Among these are:

- Not all engine repair work done by TWA engine repair facility staff was charged.
- Engine repair costs in TWA shops were probably higher than if such work was done in shops that specialized on industrial gas turbines. Higher costs would result from two conditions:
 1. An aircraft engine repair shop is apt to be more expensive to operate because its work is done to much more exacting standards than those applicable to work on industrial engines.
 2. It would not be as skilled in diagnosing and repairing industrial gas turbine failures as would a shop that specialized in industrial engine repair.
- Engine repair costs did not appear to be carefully monitored because the repairs were done by TWA. The impression emerged that engine repair costs were not followed nearly as closely as they would have been if they had been out-of-pocket expense items. Discussions with engine repair facility supervisory staff indicated that the quantity of engine repair work done for each repair was determined by the engine repair mechanic without consultation with supervisors or the customer (the TWA facilities engineering staff). A different relationship existed between the TWA engine repair staff and the management staff than would probably have existed between the TWA total energy plant staff and an outside engine repair contractor. This difference may have resulted in more work being done on the total energy engines than was economical.

4.4.4 Future Maintenance Work

Relatively little of the total energy plant maintenance and repair work has been done on nonengine equipment. Because the equipment was new and generally in the first five years of a projected 25-year life, little major maintenance would be expected. However, as the plant equipment continues to age, much more maintenance can be expected to be required. The level of such future maintenance is unknown but it would surely be much higher than in the past. Consequently, future nonengine maintenance of the total energy plant would be expected to be much greater than in the past. Hence, unless some way might be found to diminish the engine maintenance, future total energy maintenance costs would be greater.

5 ECONOMIC AND ENERGY EFFICIENCY EVALUATION OF TWA TOTAL ENERGY PLANT

The total energy plant serving the Kansas City TWA complex was not a successful venture. TWA has sold the electric generating part of the plant to Missouri Public Service Company for use as a peaking generator in their system. It retains ownership of the steam generating portions of the plant, but is in the process of selling whatever equipment can be salvaged (primarily the two waste-heat boilers).

This chapter evaluates the economic and energy efficiency characteristics of the total energy plant and its operation. The data developed for the evaluation is identified and discussed in the Appendix. The next section evaluates the economic and financial viability of the total energy venture. The third section looks at the total energy facility in terms of energy efficiency and shows how the total energy plant used energy as compared to energy use under the hypothetical "purchased power" alternative. The fourth section discusses some of the reasons why the expectations of the TWA total energy plant advocates were not realized and compares the way the total energy plant actually operated with how it was planned to operate.

The analysis of this chapter shows that the total energy plant was never a paying venture on either an average cost or marginal (incremental) cost bases. Economically speaking, had TWA known in 1969 what they know now they would not have built the plant. Accordingly, when the plant was completed in 1971-1972, it would have been in TWA's interest to sell it immediately. Money was lost for every month that the plant was used in comparison to costs under the purchased power alternative. This situation was true even when "sunk" costs (but not salvage value) were eliminated from "owning" costs.

In terms of energy efficiency, the total energy plant did not conserve energy. All the years it operated it consumed more fuel Btu than the comparable purchased power alternative would have consumed. Furthermore, the total energy plant used only liquid and gas fuels, while more than half the fuel used under the purchased power alternative would have been coal.

It is the conclusion of this project that there are some conditions under which the plant could have been operated that would have improved the economics and fuel efficiency, but that nothing could have been done to make it cost effective. The plant never paid its way either on a full cost or on an incremental cost basis. Although these conclusions economically condemn the total energy facility evaluated by this project, they should not be viewed as a condemnation of the total energy concept. Rather, the TWA application of the total energy concept shows that realization of its potential requires very careful and realistic analyses of the specific circumstances in which it is to be applied. The ex post facto analysis of this project was simple compared to its prospective analysis. It is therefore difficult to say to what extent the first evaluation of the TWA plant should have projected what actually happened. Nevertheless, so many questionable elements exist in the original supportive analysis that biased the results in favor of total energy that had a thorough analysis by an objective party been done in TWA's behalf, the venture could have been avoided and millions of dollars could have been saved.

5.1 ECONOMIC-FINANCIAL EVALUATION

To understand the economics of the TWA total energy venture a retrospective analysis was done to compare the costs of the output of the total energy plant to the costs TWA would have incurred in purchasing the electricity and making the steam in their two large existing steam plants. The comparisons made and discussed here are:

- Between purchased power and the average (fully allocated) costs of total energy, and
- Between purchased power and the marginal (incremental) costs of total energy.

The comparison between purchased power costs and average costs of total energy shows whether the total energy venture was profitable as conceived prior to purchase. If the average cost comparison shows that the venture did not pay, the comparison between purchased power costs and marginal costs of total energy shows how bad a venture it was and when the investment should have been liquidated and a return to purchased power made. (The difference between total energy average cost and total energy marginal cost is in the capital component of the two costs. The marginal cost figure ignores the sunk portion of the capital costs, while the average cost figure includes them.)

Table 5.1 is a yearly summary of the purchased power costs, total energy average costs, and total energy marginal costs. The development of the data for this table is discussed in the Appendix. As can be seen, both average cost and marginal cost of total energy are larger than the purchased power alternative costs for the years from 1973 through 1976 (the years for which fairly complete data on the total energy plant operation were available.) The months in 1971 and 1972 for which data was not available would be even less favorable to total energy than the later periods, because little or no waste-heat recovery was taking place during the earlier period. (The lack of waste-heat recovery was due to problems with the waste-heat steam generator system that did not get resolved until January 1973).

The magnitude of the difference between total energy costs (average and marginal) and purchased power costs are so large as to leave little doubt about the conclusions they suggest:

Table 5.1 Yearly Summary of Energy Costs (thousands of dollars)

Year	Purchased Power	Total Energy	
		Average Cost	Marginal Cost
1973	1,381.7	2,523.1	1,889.8
1974	1,637.1	3,221.6	2,608.0
1975	1,906.0	4,132.8	3,529.8
1976	<u>2,162.1</u>	<u>3,678.2</u>	<u>3,103.8</u>
Total	7,086.9	13,555.7	11,131.4

- TWA's total energy venture was a poor investment. From 1973 through 1976 the plant lost \$6.4 million (difference between purchased power and total energy average cost).
- The total energy plant was so expensive to operate that TWA's interest would have been served by shutting the plant down as soon as alternate purchased power could have been provided and selling the plant at salvage prices.
- A salvage value of the plant of \$1.2 million or more was all that was necessary to justify not operating the plant after 1972.
- The longer the plant operated the more money it lost. The costs to TWA of waiting until 1976 to shut down the total energy plant and return to purchased power are estimated to be about \$4 million.
- From 1974-1976 the operating costs (fuel, operating, and maintenance), alone, were larger than alternative purchased power costs would have been.

All of the foregoing conclusions ignore the tax advantages of an early loss write-off. Including tax considerations in the analysis reinforces further the conclusion that TWA would have been well served by selling off its total energy investment as early as possible.

5.1.1 Sensitivity Analysis of Cost Trends

Tables 5.2-5.4 show a time series of the fuel and other cost elements that make up purchased power, total energy average, and total energy marginal costs. This subsection explores the sensitivity of the different costs to changes in their component parts and discusses implications for the future.

Purchased Power

Purchased power costs (Table 5.2) are dominated by electricity costs; however, that dominance is declining slowly due to natural gas price rises, as can be seen by the growing percentage of the costs of steam. The slowly growing importance of steam costs will continue as natural gas (the historical fuel for TWA combustion-boiler steam generation) prices rapidly rise to parity with oil prices, and as utility coal prices rise as well, although much more slowly.

Utility (MPS)-produced electricity prices will rise faster in the future than they have in the past as old, low cost, coal purchase contracts expire and are renegotiated to reflect higher current coal prices. In fact, some recent (September 1977) coal purchases by MPS are showing a 50-100% price increase for coal over average prices of \$0.47/million Btu paid in 1976 and early 1977. This expected trend in faster rising electricity prices is foreshadowed by a current rate increase request that the MPS Company now has before the Missouri Public Service Commission. Prices to TWA would increase by about 25% under the proposed price schedule. The slowly rising price of coal, as compared to prices of liquid and gas fuels, and the size dominance of the relatively stable non-fuel electricity costs of the purchased power

Table 5.2 Purchased Power Alternative - Cost Trends (thousands of dollars)

		Electricity			Steam			
		Fuel (96% Coal)	Other	Subtotal	Fuel	Other	Subtotal	Total
1973	Total	324	794	1119	194	73	268	1381
1973	%	23.5	57.5	81.0	14.1	5.3	19.4	100
1973	Mo. Avg.	27	66	93	16	61	21	137
1974	Total	392	918	1311	246	79	325	1637
1974	%	24	56.1	80.1	15.1	4.8	19.9	100
1974	Mo. Avg.	32	76	109	20	6	27	163
1975	Total	501	1006	1509	318	78	397	1905
1975	%	26.3	52.8	79.2	16.7	4.1	20.8	100
1975	Mo. Avg.	41	83	125	26	6	33	191
1976	Total	566	1108	1674	395	92	487	2162
1976	%	26.2	51.2	77.4	18.3	4.3	22.6	100
1976	Mo. Avg.	47	92	139	32	7	40	220
1977	Total	n/a	n/a	432	139	242	163	596
1977	%	n/a	n/a	72.6	23.4	4.1	27.4	100
1977	Mo. Avg.	n/a	n/a	144	46	81	54	199

alternative, together, suggest that costs under the purchased power alternative will rise slowly relative to rising gas prices.

Total Energy Average Cost

Total energy average costs (Table 5.3) start out being dominated by fuel and capital charges about equally, but as time goes on the dominance of fuel costs increases rapidly (for the first three months of this year more than 2/3 of total energy average costs were fuel costs). Even so, the average price of total energy fuel during the first quarter of 1977 is only \$1.72/million Btu.

Since it is inevitable that total energy plant fuel prices will rise to parity with jet fuel prices, about \$2.60/million Btu, a substantial increment (the difference between \$1.72 and \$2.60) is yet available for total energy fuel prices to rise even further (half again above the level of early 1977). Since fuel prices are by far the dominant component of total energy average costs, future total energy average costs could be expected to rise nearly as fast as fuel prices.

Total Energy Marginal Cost

Because capital costs are a smaller component of total energy *marginal* cost than they are of total energy *average* cost, the dominance of the fuel

Table 5.3 Total Energy Average Cost Trends (thousands of dollars)

Year	Costs	Fuel Cost			Operating and Maintenance Cost	Capital Cost	Total
		Natural Gas	Jet Fuel	Sub- Total			
1973	Total	629	325	955	600	967	2523
1973	%	25.0	12.9	38.9	23.8	38.3	100
1973	Mo. Avg.	52	27	79	50	80	210
1974	Total	830	818	1649	635	937	3221
1974	%	25.8	25.4	51.2	19.7	29.1	100
1974	Mo. Avg.	69	68	137	52	78	268
1975	Total	969	1530	2500	716	907	4123
1975	%	23.5	37.1	60.6	17.4	22.0	100
1975	Mo. Avg.	80	127	208	59	75	343
1976	Total	1301	768	2069	731	877	3678
1976	%	35.4	20.9	56.3	19.9	23.8	100
1976	Mo. Avg.	108	64	172	60	73	306
1977	Total	315	586	902	180	214	1297
	(3 mos.)						
1977	%	24.3	45.2	69.5	13.9	16.5	100
1977	Mo. Avg.	105	195	301	60	71	432

component of the marginal cost is ever greater (see Table 5.4). Therefore, total energy marginal cost will follow fuel cost increases even closer than will total energy average costs, which means that as total energy fuel prices rise total energy marginal costs will be the fastest growing of the three costs computed. Thus, the gap between purchased power costs and total energy marginal costs would have grown wider in the future.

Conclusions of Sensitivity Analysis -- Implications for the Future

Total energy average cost and total energy marginal cost are likely to rise even faster in the future relative to purchased power costs than they have in the past. Additionally, while operating and maintenance costs and capital costs were important determinants in the early unfavorable cost comparisons of total energy with purchased power, the importance of fuel costs now completely overshadows the other costs. In short, recent cost trends are not expected to reverse, but to accelerate with rising gas and liquid fuel prices and the continuation of these trends would reinforce the economic advantage of the purchased power alternative.

Table 5.4 Total Energy Marginal Cost Trends (thousands of dollars)

Year	Costs	Fuel Cost			Operating and Maintenance Cost	Capital Cost	Total
		Natural Gas	Jet Fuel	Sub- Total			
1973	Total	629	325	955	600	333	1889
1973	%	25.0	12.9	38.9	31.8	17.7	100
1973	Mo. Avg.	52	27	79	50	27	157
1974	Total	830	818	1649	635	323	2608
1974	%	25.8	25.4	51.2	24.4	12.4	100
1974	Mo. Avg.	69	68	137	52	769	217
1975	Total	969	1530	2500	716	313	3529
1975	%	23.5	37.1	60.6	20.3	8.9	100
1975	Mo. Avg.	80	127	208	59	26	294
1976	Total	1301	768	2069	731	302	3103
1976	%	35.4	20.9	56.3	23.6	9.8	100
1976	Mo. Avg.	108	64	172	60	75	258
1977	Total (3 mos.)	315	586	902	180	74	1157
1977	%	24.3	45.2	69.5	16.	6.4	100
1977	Mo. Avg.	105	195	301	60	25	386

5.2 ENERGY EFFICIENCY EVALUATION

Table 5.5 shows the yearly total energy plant fuel consumption and useful energy production. Table 5.6 shows the fuel consumption that would have occurred under the purchased power alternative. As these tables indicate, the purchased power alternative would have resulted in significantly less fuel consumption (1/3 less per year) than under total energy. Moreover, two-thirds of the fuel (in Btu) consumed under the purchased power alternative would have come from coal, whereas all the fuel consumed in the total energy plant was liquid and gas. Consequently, the total energy plant performed unfavorably in two respects:

1. More Btu was consumed than would have been the case under purchased power, and
2. Liquid and gas fuels were consumed heavily, whereas the purchased power alternative would have required less than one-third the quantity of these fuels.

Had the TWA complex been on purchased power from January 1973 through March 1977, more than 181,000 tons of coal would have replaced 5 MCF of natural gas and 15.6 million gal of jet fuel consumed to supply TWA's energy needs.

Table 5.5 Fuel Consumption - Energy Production Total Energy Plant

Year	Fuel Consumed			Useful Energy Produced				Energy Efficiency	
	Natural Gas	Jet Fuel	Total	Electricity		Steam		Total	%
	10 ⁹ Btu	10 ⁹ Btu	10 ⁹ Btu	10 ³ kWh	10 ⁹ Btu	10 ³ lb	10 ⁹ Btu	10 ⁹ Btu	
1977 (3 mo)	272.0	215.6	487.6	22,089	75.4	96,921	98.2	173.0	35.6
1976	1,694.7	288.6	1,983.3	92,119	314.3	392,071	397.2	711.5	35.9
1975	1,469.7	706.7	2,176.4	92,949	317.0	399,340	404.5	721.7	33.2
1974	1,865.7	467.1	2,332.8	90,256	308.0	393,204	398.3	706.3	30.3
1973	1,893.0	288.1	2,181.1	85,827	292.8	402,421	407.7	700.5	32.0
Total 1973-77	7,195.1	1,966.1	9,161.2	383,240	1,307.5	1,683,957	1,705.9	3,013.0	32.9

Table 5.6 Fuel Consumption - Energy Production Purchased Power Alternative

Year	Fuel Consumed				Useful Energy Produced				Energy Efficiency	
	Coal	Fuel Oil	Natural Gas	Total	Electricity		Steam		Total	%
	10 ⁹ Btu	10 ⁹ Btu	10 ⁹ Btu	10 ⁹ Btu	10 ³ kWh	10 ⁹ Btu	10 ³ lb	10 ⁹ Btu	10 ⁹ Btu	
1977 (3 mo)	249.6	1.6	134.7	385.9	22,089	75.4	96,921	98.2	173.0	45.0
1976	1,048.2	6.9	546.0	1,605.8	92,119	314.3	392,071	397.2	711.5	44.3
1975	1,063.1	3.7	554.3	1,621.1	92,949	317.0	399,340	404.5	721.7	44.5
1974	1,027.4	.3	553.2	1,578.0	90,256	308.0	393,204	398.3	706.3	44.8
1973	939.2	0.0	537.4	1,476.6	85,827	292.8	402,421	407.7	700.5	47.4
Total 1973-77	4,327.5	12.5	2,325.6	6,667.4	383,240	1,307.5	1,683,957	1,705.9	3,011.0	45.2

5.3 REASONS FOR TWA'S TOTAL ENERGY FAILURE

As documented in the two prior sections of this chapter, the TWA total energy plant was an economic and energy saving failure. Among the reasons for this failure are those discussed in the following subsections.

5.3.1 Energy Savings in Original Analyses Were Assumed Rather Than Determined through Engineering Analysis

The projected 70% energy efficiency of the TWA total energy plant was *assumed* in the 1969 engineering analysis prepared in support of total energy for TWA's Kansas City complex. At some point before a final decision was made to use total energy, a detailed engineering analysis should have been done on the final detailed energy plant design to verify that the assumed energy savings were realistically attainable. Such an analysis would have shown that the planned TWA application of total energy would not achieve energy efficiencies even approaching 70%. Simple calculations using:

- Engine turbine heat rate values (Fig. 4.3) for the TWA generator unit engines,
- Waste-heat steam generator heat-recovery rates (Fig. 5.2), plus
- Kansas City air temperature data (Table 5.7),

immediately reveal the fallacy of the 70% efficiency assumption.

5.3.2 The Two Prime Movers Were Too Large for the TWA Total Energy Application

More, smaller prime movers (generating engines) should have been provided for a facility such as the TWA Kansas City complex, for the following two reasons:

1. A single prime mover operating by itself cannot provide a highly reliable power supply (particularly to essential loads), since a single equipment of operational failure causes a blackout. The more prime movers providing power, the more reliability a generating plant has.
2. If a more reliable power supply is needed than can be provided by a single large unit, then the back-up unit as well as the primary unit must be operated to provide it. Thus, TWA had to operate continuously two 20-MW generators to reliably serve a 7.5-13.0-MW average load, at which output level the generator engines operate at very low efficiencies.

After the basic design of the TWA total energy plant was finalized, TWA decided to shift its airline reservations computer facilities from New Jersey to the new administration center at the Kansas City complex. The importance of uninterrupted power for the reservation computers created a need for extreme reliability. In response to this need, TWA operated with both generators on line most of the time (90% for most months in 1974 and early 1975). After a special uninterruptible power supply was installed in 1975 in the administration center for the computers, TWA changed its operating practice and from mid-1975 through March 1977 only one generator was normally in operation at any one time.

During those years, however, when two units were on line to service a total load of 7.5-13.0 MW, each generator operated in the 3.75-6.50-MW range. As shown by the heat-rate curves of Fig. 4.3 for the TWA gas turbine units, the efficiency of the turbines is very low -- 18,000 Btu/kWh to 23,000 Btu/kWh -- at these low output levels. Consequently, the total energy plant operated very inefficiently and expensively in order to ensure the desired power supply reliability. A better total energy plant design, with vastly improved reliability, would have called for more prime movers that could have operated more closely to their point of maximum efficiency.

Fig. 5.1 Waste-Heat-Recovery Boiler Production Rates

Table 5.7 Kansas City, Missouri, Monthly Normal Air Temperature Data

Month	Temperatures °F							Normal Degree Days Base 65°F	
	Normal			Extremes				Heating	Cooling
	Daily Maximum	Daily Minimum	Monthly	Record Highest	Year	Record Lowest	Year		
(a)				4		4			
J	36.2	19.3	27.8	61	1973	-13	1974	1153	0
F	41.9	24.2	33.1	74	1976	-4	1973	893	0
M	50.5	31.8	41.2	82	1974	-1	1973	745	7
A	64.8	45.1	55.0	85	1975	12	1975	314	14
M	74.3	55.7	65.0	91	1975	30	1976	111	111
J	82.6	65.2	73.9	98	1974	47	1973	12	279
J	88.0	69.6	78.8	107	1974	52	1973	0	428
A	86.7	68.1	77.4	104	1976	50	1973	0	388
S	78.8	58.8	68.8	98	1975	39	1975	42	156
O	68.9	48.3	58.6	92	1976	25	1976	235	37
N	52.7	34.5	43.6	78	1976	1	1976	642	0
D	40.4	24.1	32.3	67	1973	-11	1976	1014	0
yr	63.7	45.3	54.5	107	Jul 1974	-13	Jan 1974	5161	1420

Source: National Oceanic and Atmospheric Administration, *Local Climatological Data - Annual Summary With Comparative Data - 1976 - Kansas City, Missouri*, National Climatic Center, Asheville, North Carolina.

5.3.3 The TWA Kansas City Complex Did Not Grow as Large as Anticipated

Originally, the TWA Kansas City airport complex was expected to triple in size by 1975 relative to 1969. In fact, the facility only doubled in size, since the further expansion was not warranted due to declining business conditions in the airline industry. Yet, this further growth was expected by the original designers of the total energy plant, and the installation of a third gas turbine generator similar to the other two was anticipated. A third unit would have greatly increased the reliability of the plant, and if electric demand had increased as expected, the plant's three generators could have operated with much improved efficiency over the two-unit plant. At the same time, the addition of a third generator would not have changed the fact that the generating units were too large for a load as small as that of the TWA complex.

Looking forward to the time when one of the generators was to undergo a major overhaul (after 7-10 yr) and would be shut down for an extended period raises an important question -- What was to be done during such an overhaul to ensure reliability of power supply? Electric load by that time would probably exceed the capacity of one generator, so both of the remaining units would have to be on line with no back-up reserve if one of them went down. This

situation would have entailed great risk, jeopardizing plant reliability and degrading plant efficiency due to improperly sized prime movers.

Among the reasons in support of TWA's sale of the total energy plant was the problem of how to effect a major generator overhaul. With just *two* units on hand and one of them in overhaul, any easement of the problem would have required some form of drastic action. More than 5000 people are employed at the Kansas City complex and TWA could not risk closing down such a large operation because of electric supply problems. No practical option existed but to return to purchased power or to negotiate a standby agreement with MPS.

5.3.4 Unanticipated Fuel Price Increases and Natural Gas Supply Restrictions

In 1969, when the TWA total energy plant was conceived, very few observers of the energy scene were anticipating huge price increases for fuels, particularly for liquid and gas fuels. In that year the gas industry was beginning to anticipate supply restrictions, but the Gas Service Company of Kansas City, which supplied the TWA plant, gave no hint of the coming curtailments. In fact, the Gas Service Company planned to install a new gas main to serve the increased demand for gas in the Kansas City Airport region of its service area. Indeed, the analyses supporting total energy for the complex anticipated that prices would rise generally, and explicitly stated that energy prices would rise relatively. Consequently, no separate analysis of fuel and electricity price inflation was provided.

Since 1969, many things have happened in the fuel market. All fuel prices have risen much faster than the general price level and liquid and gas fuel prices have risen much faster than coal prices. Between 1972 and 1977, the period of greatest fuel price advance, natural gas and jet fuel prices for fuel delivered to TWA in Kansas City have increased more than 300%, whereas utility coal delivered to Missouri Public Service has not yet doubled. (Part of the reason for relatively low coal price increases are long-term coal supply contracts entered into prior to 1973-1974.)

Even more damaging for TWA's total energy plant was the declining of supply of available natural gas. Declining natural gas supply meant that the TWA plant had to use more and more jet fuel. Jet fuel and natural gas prices increased at about the same rate (300%); natural gas supply curtailment had the effect of further increasing the cost of fuel to the TWA plant because on a heat content basis natural gas is still much less expensive than jet fuel. A 100% curtailment of natural gas would have meant a fuel cost increase to the TWA plant of another 400-500% above the original natural gas price. In other words, a shift from 100% natural gas fuel in 1972 to 100% jet fuel in 1977 would have meant a price increase in current dollars from less than \$0.30/million Btu in 1972 to about \$2.60/million Btu in 1977, a more than an eightfold increase. Of course, 100% curtailment of natural gas has not come yet, but it is coming and the effect on gas- and liquid-fueled total energy plants will be devastating in places where the purchased power alternative is comparatively low cost coal fueling. Coal is experiencing large price increases, but these increases are much less severe than the price rises that total energy plants, originally conceived to be fueled with natural gas, are and will experience as natural gas prices rise to parity with oil, and natural

gas curtailments force fuel shifts from relatively cheap gas to expensive liquid fuels.

5.3.5 Larger Than Expected Non-Fuel Operational Costs and Maintenance Costs

Operating Expenses

The TWA total energy plant was designed to operate without personnel continuously on duty. It was supposed to require only occasional monitoring and periodic equipment status checks, instrument readings, and recordings. In practice the plant operated fairly automatically, but power reliability requirements and the lack of back-up generating units when both existing units were operating persuaded TWA to man the plant full time. Problems occasionally occurred that required rapid action, and dispatching personnel from remote locations in other buildings took too long. Furthermore, there was the risk that with remote plant monitoring, developing crises might be overlooked.

In consequence, one man was assigned to the total energy plant 24 hours a day, 365 days per year. Additionally, another man was on 1/3 time standby for work at the plant to assist in special operations such as engine startups and fuel switching. One and a third men per shift around the clock amounts to four man shifts per day and nearly six man-years of operating labor per year. Six man-years of labor is a considerable unanticipated expense in light of the fact that operating labor expense was originally estimated to be only \$20,000 per year.

Maintenance Expenses

Plant operating labor expense was not the only unanticipated increase in operational expenses. Maintenance expenses were also far greater than expected. Routine and special maintenance as well as jet engine maintenance were also much costlier than expected. The routine and special maintenance requirements were raised by a number of special problems that occurred periodically. Principal among these was a problem with the natural gas fuel nozzles in the jet engines. Natural gas liquids in the purchased gas fuel, plus gas compressor lubricating oil injected into the fuel gas during compression, did not burn completely in the engine. This deficiency caused carbon buildup on the gas fuel nozzles in the engine combustion chamber. The carbon buildup, in turn, frequently caused improper gas dispersion in the combustion chamber and resultant overheating and burning of engine parts. Needed repairs of the damage and fuel nozzle cleaning could usually be made without removal of the engine but it was expensive and raised routine repair costs significantly.

A separate category of maintenance that was much more costly than expected was engine maintenance that required engine removal and work in the TWA engine overhaul facility. In the original total energy analyses, it was anticipated that engines would operate 10,000 hr between repairs requiring removal and shop work. In practice, engine overhaul records show that the engines averaged only 3,200 hr between visits to the shop -- three times the repair rate originally estimated. In the future, nonengine maintenance and

repair costs on the total energy plant could be expected to increase substantially inasmuch as very little major equipment maintenance was needed during the first five years of plant life when all the equipment was new. As the total energy plant equipment ages, maintenance requirements can be expected to increase accordingly.

Operating costs and maintenance costs were expected to amount to only about \$120,000 per year. They may have amounted in fact to \$600,000 per year.

5.3.6 Larger Than Expected Capital Costs

It is unclear in the original reports made in support of total energy exactly how capital costs were calculated. However, the costs estimated in the report (\$354,000 and \$475,000, depending on the method of financing) are much less than the \$800,000+/year capital costs estimated in this study (see App. A). Part of the reason for the higher than expected capital costs was a cost overrun in plant construction of more than \$1 million. Most of the remaining higher capital costs arise from the interest rate charged for the capital that TWA invested in the total energy plant. The original estimate of interest costs to be paid was 6%. This rate is low in light of the fact that TWA was borrowing money via a bond issue in late 1969 at an interest rate of 10%. Since the decision to invest in total energy and the 10% bond issue were made at the same time, this study had assigned a 10% interest cost to money invested in the total energy plant. Depreciating the total energy plant at 4% per year (25-yr, straight-line) and interest charges on the unamortized portion of the total energy investment result in capital charges of slightly more than \$840,000 for the first year, declining thereafter over the 25-year life of the plant to a final charge in the 25th year of about \$240,000.

6 ALTERNATE (WHAT IF) SCENARIOS AND FUTURE PROSPECTS FOR THE TWA/MPS TOTAL ENERGY PLANT

This chapter briefly discusses alternate "what if" scenarios under which the TWA total energy facility might have operated and could operate in the future if its heat-recovery capability were maintained. The scenarios discussed typically are thought to enhance the economic viability of total energy. Yet, although different ways of operating the plant would improve its efficiency relative to the past, the magnitude of improvement under different scenarios would not be large enough to justify continued operation as a total energy plant. Missouri Public Service Company's plan to use the plant as a peaking unit in their system, while not evaluated by this study, is probably the most economical use of the facility now.

6.1 SCENARIO 1: WHAT IF THE TWA COMPLEX HAD RELIED ON MISSOURI PUBLIC SERVICE UTILITY CONNECTIONS FOR BACKUP IN CASE OF TOTAL ENERGY OUTAGE

Having a utility grid connection for emergency backup allows a total energy plant to be built and operated without built-in backup for coverage of unplanned shutdowns. Such back-up protection makes it possible to build onsite power generation plants with less reserve capacity. In the case of the TWA plant, about 100% of reserve generating capacity was provided. Power backup from an electric grid connection would have allowed the TWA plant to be constructed with about half the capacity with which it was actually built. Therefore, a considerable savings in investment capital would have been achieved if the TWA plant had been able to use connections to the MPS system for emergency backup.

Capital costs, on the other hand, would not have been the only source of savings -- operating cost savings would also have resulted if the TWA complex had been able to rely on MPS for back-up power. Because of the need for very high reliability in power supply to serve the worldwide TWA reservations system located in the administration center, TWA operated the total energy plant until 1975 with both 20-MW generators operating essentially all the time. Continuous operation meant that each generator often operated at about 25% of its rated capacity. At this low output level the gas generator (jet engine) and power turbine operated at a very low level of energy efficiency. Heat rate on the turbine at the 25% average power level was about 22,000 Btu/kWh. Had TWA been able to have MPS for backup in case of an outage, one of the total energy generators could have operated instead of two and the one unit could have operated at higher power and better efficiency at 18,000 Btu/kWh average heat rate.

While having MPS provide backup to the TWA total energy plant would have been advantageous to the economics of the total energy operation, such a backup arrangement had drawbacks, as far as Missouri Public Service Company was concerned. For example:

- Providing backup to TWA would require an added increment of costly peak-load generating capacity from MPS. (Assuming MPS normally would not have excess peak capacity beyond that needed to back up

their other load, the needed additional peak capacity could be provided directly by adding generating capacity or through inter-connection arrangements with other power providers.)

- Providing backup to TWA would improve the economics of the total energy plant, but insofar as it made the difference between total energy's being economically viable and not viable, the MPS backup would work to erode its own market by removing the TWA facility from the purchased power.

Since an MPS back-up connection with TWA would have been for emergency use only, very little energy normally would have been provided to TWA. The MPS role then would not be that of an electric energy provider, but one of providing insurance, or outage protection, to TWA. The question then arises -- Why not have the total energy plant provide its own "insurance" by including added onsite outage protection built into the total energy plant?

The answer lies in the fact that MPS with many customers and large energy production would not need to provide as large an increment of added capacity for TWA backup as TWA would have to provide itself. A utility can "play the averages" and assume that not every customer will be drawing energy at peak levels at the same time. On the other hand, a single isolated facility cannot do so and TWA had to cover itself. The way that TWA chose to provide the protection needed was to:

- Install two generating units, each of which could carry the full load of the TWA complex by itself, and
- Run both generating units most of the time in order to have instantaneously available backup in the form of spinning reserve.

This type of protection is very expensive in both capital and operating terms and would, in general, be much less costly if provided by a utility.* Pricing such protection could be very complex because utility rates are generally not marginal-cost priced, and marginal-cost pricing techniques would need to be used to determine a cost-based demand charge for the backup.

Using the TWA-Missouri Public Service situation as an example illustrates some of the economic factors that contribute to the advantage utilities have for providing backup over TWA's providing its own onsite generator for that purpose. Table 6.1 shows the monthly peak demands on the MPS electric system that would have backed up the TWA facility during the time the total energy plant operated. As can be seen the months of peak demand are usually July and August. Other months have levels of peak demand that are lower by 20% (110 MW) or more. While July and August of 1972 had periods of peak demand of between 550 and 575 MW, eight other months of 1976 have maximum demands of 351 MW, and two months (June and September) have peak demands of less than 450 MW. As this data shows, MPS used its peak generating capacity in 1976 only two months out of the year. For all of the other months more

*Another option, not discussed here, entails using a utility grid for power wheeling among onsite power generators. If wheeling were available, inter-connections could be made among different nonutility power providers who could supply back-up protection to each other.

Table 6.1 Missouri Public Service Company Monthly Peak and Output

Month	Year	Kilowatts	Day of Week	Day of Month	Hour	Monthly Output KWH (000's)	Month	Year	Kilowatts	Day of Week	Day of Month	Hour	Monthly Output KWH (000's)
January	1976	337 900	Wednesday	7	6:00 PM	199,462	January	1973	294 900	Tuesday	9	7:00 PM	244,619
February	1976	323 000	Wednesday	4	7:00 PM	209,491	February	1973	275 100	Wednesday	7	7:00 PM	202,266
March	1976	294 700	Monday	15	8:00 PM	186,527	March	1973	252 100	Monday	19	7:00 PM	186,568
April	1976	271 000	Friday	23	2:00 PM	206,452	April	1973	249 900	Monday	9	8:00 PM	159,923
May	1976	296 800	Friday	21	4:00 PM	145,996	May	1973	277 800	Monday	21	3:00 PM	187,765
June	1976	402 207	Monday	14	5:00 PM	177,490	June	1973	400 400	Monday	25	5:00 PM	210,966
July	1976	571 970	Tuesday	27	5:00 PM	215,245	July	1973	442 300	Monday	9	5:00 PM	221,941
August	1976	552 770	Tuesday	10	5:00 PM	254,430	August	1973	466 800	Monday	27	6:00 PM	233,570
September	1976	442 000	Friday	3	6:00 PM	234,293	September	1973	344 800	Saturday	1	1:00 PM	182,453
October	1976	332 500	Saturday	2	5:00 PM	210,984	October	1973	312 900	Monday	8	6:00 PM	155,608
November	1976	331 200	Monday	29	6:00 PM	204,256	November	1973	264 100	Tuesday	6	6:00 PM	135,458
December	1976	350 700	Thursday	30	6:00 PM	194,322	December	1973	296 000	Thursday	20	7:00 PM	150,551
						2,438,948							2,271,688
January	1975	294 700	Monday	13	7:00 PM	166,227	January	1972	250 500	Wednesday	5	7:00 PM	210,486
February	1975	301 600	Wednesday	5	7:00 PM	173,988	February	1972	245 900	Thursday	3	7:00 PM	244,672
March	1975	261 400	Monday	3	11:00 AM	150,069	March	1972	229 300	Wednesday	1	7:00 PM	163,458
April	1975	272 100	Wednesday	2	12:00 AM	164,487	April	1972	231 900	Monday	12	8:00 PM	161,746
May	1975	378 900	Thursday	22	4:00 PM	178,459	May	1972	287 700	Monday	22	6:00 PM	220,018
June	1975	483 000	Monday	30	4:00 PM	180,108	June	1972	369 970	Thursday	8	6:00 PM	178,800
July	1975	538 900	Monday	28	5:00 PM	240,501	July	1972	391 400	Friday	14	3:00 PM	191,052
August	1975	536 900	Tuesday	12	6:00 PM	239,826	August	1972	426 000	Friday	18	5:00 PM	210,962
September	1975	534 370	Wednesday	3	5:00 PM	182,759	September	1972	434 400	Monday	18	5:00 PM	187,318
October	1975	304 100	Monday	13	4:00 PM	170,076	October	1972	265 100	Wednesday	11	8:00 PM	188,853
November	1975	314 900	Monday	24	6:00 PM	150,372	November	1972	268 600	Friday	17	7:00 PM	130,619
December	1975	327 900	Wednesday	17	7:00 PM	161,978	December	1972	295 600	Monday	11	6:00 PM	217,577
						2,158,850							2,305,564
January	1974	284 800	Thursday	3	7:00 PM	266,331	January	1971	223 900	Tuesday	26	7:00 PM	220,011
February	1974	265 400	Friday	8	11:00 AM	245,855	February	1971	224 800	Monday	8	12:00 AM	217,213
March	1974	253 300	Monday	18	12:00 AM	213,172	March	1971	213 800	Tuesday	9	7:00 PM	215,188
April	1974	247 100	Thursday	4	11:00 AM	220,437	April	1971	203 000	Monday	5	5:00 PM	221,632
May	1974	376 300	Thursday	30	5:00 PM	161,081	May	1971	218 600	Monday	17	4:00 PM	153,757
June	1974	450 000	Thursday	20	6:00 PM	210,541	June	1971	357 100	Monday	28	5:00 PM	158,150
July	1974	511 000	Friday	19	5:00 PM	254,327	July	1971	373 800	Tuesday	13	3:00 PM	147,452
August	1974	469 500	Wednesday	21	5:00 PM	205,294	August	1971	394 670	Tuesday	24	5:00 PM	157,982
September	1974	323 100	Tuesday	10	6:00 PM	169,124	September	1971	389 800	Wednesday	8	5:00 PM	164,157
October	1974	275 100	Wednesday	30	7:00 PM	154,135	October	1971	266 100	Friday	1	6:00 PM	197,596
November	1974	281 600	Wednesday	13	6:00 PM	164,106	November	1971	241 300	Tuesday	30	6:00 PM	174,213
December	1974	292 000	Monday	16	6:00 PM	167,049	December	1971	245 700	Tuesday	14	6:00 PM	201,136
						2,431,452							2,228,487

Source: Annual Reports of Missouri Public Service System to the Federal Power Commission for the years 1971-1976, inclusive.

than 100 MW of generating capacity were idle all the time; and more than 200 MW were idle for eight of those months.

From this data it is clear that only during July and August would a significant burden have been imposed on MPS for backing up the TWA power plant. This study did not determine what that burden would have been; although it is likely that any peaking MPS could not have carried with its own generating facilities, could easily have been covered through interconnections with other wholesale or retail power providers at less cost than that incurred by TWA in providing its own backup.

6.2 SCENARIO II: WHAT IF TWA HAD BEEN ABLE TO BUY AND SELL POWER TO MISSOURI PUBLIC SERVICE SYSTEM

This scenario goes a step beyond Scenario I in that it provides for a facility such as TWA's to buy and sell power as well as use the utility system for backup. Enabling a total energy plant to buy and sell power according to its needs suggests that the total energy plant can select its point of operation independently of the fluctuations in power demand it must serve.

The maximum thermodynamic efficiency of total energy results when the entropy of the thermodynamic process providing power and by-product heat is minimized. This point of maximum thermodynamic efficiency would typically occur with prime mover/heat recovery systems having low heat rates but high heat recovery or energy efficiency.

With respect to the TWA/MPS situation, maximum thermodynamic efficiency would prevail when TWA could buy and sell power (presumably at marginal cost) and would choose to expand power production at least to the point where all its steam needs would be served by total energy with no combustion boilers operating to make steam. Operating in this mode suggests that during temperate climate periods (spring and fall) when space conditioning energy needs were minimized the total energy plant would operate just about as it has, during these slack steam periods.

6.2.1 TWA Sales to MPS

The total energy plant usually has provided most of TWA's total steam needs. During periods of maximum steam demand in midwinter and midsummer, the total energy plant would probably increase its kWh output to the level where waste heat steam would be serving all steam needs.

In the summer months of peak steam demand, TWA might have sold power to the MPS grid. These sales would have served the interests of MPS well, since the utility's general service demands also peak in summer. Furthermore, TWA's peak steam demands were often likely to occur when the MPS system was peaking on seasonal air conditioning loads.

As shown in Table 6.1 the MPS system peaks only two months of the year. All the rest of the time MPS can easily pull its load with its large Sibley coal plant. Therefore, at the other times of the year, particularly in winter when TWA steam needs would require the generation of extra electricity

in order to obtain the needed steam, MPS would not wish to buy power. In the past when natural gas was available and comparable in price to coal (1971-73), it is possible in theory (but unlikely in practice) that the TWA total energy plant could have produced electricity at lower cost than MPS. Lower cost production might have been possible then if the TWA plant had been thermally loaded, since a big thermal load would have allowed generator operation closer to the maximum energy efficiency point of their gas turbines. However, now and in the future with gas curtailment and higher gas prices relative to coal, it is unlikely that TWA could ever produce winter power competitively with the MPS Sibley coal generating plant.

6.2.2 TWA Purchases from MPS

It is unlikely TWA would ever have wanted to purchase power from the MPS system for the TWA complex did not have enough load for its total energy plant. The only time that TWA would have wished to purchase power from MPS would have been during periods of emergency when the total energy power generating system failed.

While the foregoing discussion of Scenario II identified one area where the TWA and MPS interests converged, it is very unlikely that a buy-sell arrangement would have had a significant effect on the basic economics of the TWA total energy plant.

6.3 SCENARIO III: WHAT IF MPS HAD OWNED THE TWA TOTAL ENERGY PLANT FROM THE BEGINNING

Under this scenario the total energy plant is grid integrated and MPS sells power and steam as owner of the total energy plant. This scenario is exactly similar to Scenario II except that it removes the need to coerce one party, MPS, into buying power from another party, TWA. Under this scenario the interests of MPS and TWA are merged. The historical outcome of this scenario would have depended on utility plant capacity having been duplicated by the capability of the total energy plant. This scenario conceivably could have worked during the early years of the total energy plant when natural gas was plentiful and cheap and if the total energy plant had been sized more accurately for steam load (1 unit rather than 2).

However, any success would have been short lived, since rising total energy fuel prices eventually would have driven the unit into the simple peaking that is its present status.

6.4 CONCLUSION

Other scenarios for operating the TWA/MPS total energy plant more advantageously have been considered but rejected. The economics of fueling the total energy plant make the TWA/MPS facility unworkable no matter how efficiently it be operated. The gap between fuel prices for the total energy plant and coal prices paid to fuel 95% of the Missouri Public Service Company energy generation is just too large to make the TWA/MPS total energy plant economical.

ACKNOWLEDGMENTS

This project was conducted by James H. McElroy; Nathaniel Ng contributed to the entire study in general and to Chapters 3 and 4 in particular; Nirmal Kotamraju was responsible for the data development of the Appendix; and Ginger Clark handled report production -- all of Jack Faucett Associates, Inc.

Robert Aulbach of RoBach, Incorporated, provided invaluable technical consultation to the project.

Special thanks go to the people of TWA and Missouri Public Service Company for providing the plant information on which the analysis of this study was based and for reviewing a draft of this report. Without the cooperation of these individuals the study could not have been conducted.

APPENDIX A.

DATA ASSEMBLY

This appendix describes:

- The derivation of the fuel consumption for the total energy plant,
- Total energy plant costs, and
- Purchased power alternative costs.

Numerous consistency checks on the fuel consumption data provided by TWA revealed that the fuel meters gave incorrect readings. A gas company meter calibration check in 1975 showed that natural gas consumption of the total energy plant was then understated by 27.3%. Other checks performed on the natural gas fuel consumption data revealed that the meters were not consistently in error by this factor. Data checks on the liquid jet fuel meter readings showed that they were even more in error and more erratic than those of the natural gas meters. Since TWA did not consistently correct their fuel consumption and since there was no other direct way to check total energy plant fuel consumption, Jack Faucett Associates devised a methodology to correct the monthly fuel consumption data.

The cost of the total energy venture is explained in terms of the average and marginal costs to TWA of actual useful steam and electricity generated. The average costs are the fully allocated costs and the marginal costs are the incremental costs incurred in order to continue the total energy plant operation after the plant was built.

The purchased power alternative is the cost to TWA that would have occurred if TWA had *purchased the electricity* and *made the steam* that came from the total energy plant.

The basic total energy plant data, which was the foundation of the data development outlined here, was provided by TWA. A variety of additional information also was obtained for data development and analysis. The additional information, as well as the source from which it was obtained, is listed below:

- Natural gas industrial and commercial prices for the 1971-1977 period (Gas Service Company of Kansas City);
- Low heat rate and high heat rate of the natural gas provided to TWA (Gas Service Company);
- The heat rate of the jet fuel provided to TWA (Mobil Oil Refinery of Augusta, Kansas);
- The electricity prices (1971-1977) that would have been applicable to TWA under the purchased power alternative (Missouri Public Service Commission);

- The monthly fuel adjustment correction to Missouri Public Service electric rates (Missouri Public Service Commission and Missouri Public Service Company); and
- Missouri Public Service Company coal costs, fuel usage patterns, periods of peak electric output, electric generation heat rates (MPS Co. reports on file with the Federal Energy Regulatory Commission.

A.1 DERIVATION OF FUEL CONSUMPTION DATA

The method of generating fuel consumption data takes into account the difference in heat rates (Btu/kWh) between one- and two-generator operation of the total energy plant. Energy consumption was determined for each of these modes of operation and total fuel consumption was then distributed between the two fuels, liquid jet and natural gas, in proportion to the hours of operation on each fuel. Because the errors on TWA gas meters are known for 1975, the corrected meter readings of gas consumption for 1975 are assumed accurate and heat rates were developed from these data for one- and two-generator operation.

In the month of April 1975 the plant was almost exclusively on two-generator operation. A heat rate was developed for this mode of operation by dividing the total energy consumption (in Btu) by the kWh output of the plant during that month. A similar heat rate was developed for one-generator operation using data for the month of November 1975. The heat rates* thus derived were assumed to be the heat rates for one- and two-generator operation for the entire period that the plant was in operation.

The one- and two-generator kWh outputs were determined by distributing the total kWh output of the plant in proportion to the number of hours they were operated. Initially, the respective kWh outputs were determined for each month. The heat rates determined were then applied to the appropriate kWh outputs to yield the quantity of fuel (in Btu) consumed in each mode of operation. These results were then aggregated to obtain the total fuel consumption.

Total energy consumption was then distributed proportionately between natural gas and jet fuel used by the plant in operation. Individual energy consumption was then converted to physical units, using Btu conversion factors of 855 Btu/CF** for natural gas and 125,000 Btu/gal[†] for jet fuel.

* The heat rates derived were 18,014 Btu/kWh for one-generator operation and 23,496 Btu/kWh for two-generator operation.

**The Btu conversion factor is for the low-heat value of natural gas, since the heat rate curves for the generators are for this low-heat value.

† The conversion factor for jet fuel was obtained from the Mobil Oil Refinery in Augusta, Kansas, which supplies the jet fuel.

Table A.1* shows the uncorrected fuel consumption data along with hourly operating data plus kWh and steam production for generator one and generator two. Table A.2 summarizes hourly data for 1975 from Table A.1 into one- and two-generator total hours of operation. Hourly data similar to that in Table A.2 was also developed for the other years from 1973-1977. Table A.3 shows the corrected month-by-month total energy plant fuel consumption for 1973-1977.

A.2 TOTAL ENERGY PLANT COSTS

This section presents the methodology for the derivation of:

- Total energy average and marginal costs.

A.2.1 Total Energy Average and Marginal Costs

Average and marginal costs have three components:

- Fuel costs,
- Operating (nonfuel) costs** and maintenance costs, and
- Capital costs.

Fuel costs are identical for both average and marginal costs. Operating and maintenance costs are also the same for total energy average and marginal costs.

The capital costs component in total energy average cost are based upon the construction costs of the total energy plant. The capital costs component of total energy marginal cost is based upon the salvage value of the total energy plant once it was constructed. Sunk costs, the difference between total energy plant construction costs and total energy plant salvage value, are not included in the capital cost component of total energy marginal cost.

Table A.4 presents a summary of costs for the total energy plant for the years 1973-1977.

Fuel Costs

The fuel consumption data that were derived for natural gas and jet fuel were simply multiplied by the unit cost of each of these fuels to yield costs of the total energy plant, presented for the years 1973-1977 in Table A.5.

* For more convenient reference, Tables A.1-A.11 appear consecutively at the end of Appendix A.

**Hereafter referred to as operating costs.

Unit price data on natural gas was obtained from TWA for all the years under consideration. An average annual unit price of jet fuel was obtained for 1973 and 1974 and was assumed to be constant for each of the months within those years. Unit price data for the months of 1975, 1976, and 1977 were obtained directly from TWA data.

Operating Costs and Maintenance Costs

Operating costs and maintenance costs are composed of the following:

- Operating costs
 - Labor costs
 - Material costs (1% of labor costs)
- Maintenance costs
 - Routine maintenance costs
 - Labor costs
 - Material costs (50% of labor costs)
 - Jet engine repair costs
- Miscellaneous costs
 - #6 fuel oil adjustment
 - Inventory costs.

Table A.6 presents a detailed breakdown of the operating and maintenance costs for 1975.

Operating Costs. From information provided by TWA, the total energy plant was determined to require 1.33 man-hours of labor per hour of operating time. This data, along with TWA's average hourly wage rate and an adjustment for overhead costs, was used to determine the monthly labor costs incurred. Material costs (1% of labor costs) were then calculated and added to labor cost to yield the total operating costs for the total energy plant.

Maintenance Costs. Maintenance costs consist of:

- Routine maintenance costs
 - Labor costs
 - Material costs (50% of labor costs)
- Jet engine repair costs.

Routine maintenance costs were derived from information obtained in interviews with supervisors at the total energy plant. It was established that routine maintenance required 0.64 man-hr of labor per hour of operating time, and costs were then calculated from labor and material components in a manner similar to the one used for operating cost.

Jet engine repair costs for work done in the TWA engine repair shops were made up of two components.

- Engine changeout costs (80 man-hr) needed to remove and replace an engine, and
- Shop repair costs assigned to labor and material expenses in TWA's shops for each of 24 recorded engine repairs. These costs were adjusted to include labor and material overhead. Labor overhead was assumed to be 140% of direct labor costs and material overhead for stocking and handling changes was assumed to be 17% of material costs. Overhead on outside contract work was assigned a 25% overhead rate.

The total shop engine maintenance cost was then spread over the 66 months between September 1971 and April 1977, assuming costs to have escalated 8% each year in January.

Miscellaneous Costs. Miscellaneous costs consist of:

- #6 fuel oil adjustment,
- Inventory cost, and
- Land rent (\$300 year).

TWA was forced to substitute #6 fuel oil for natural gas in steam generation during periods of natural gas curtailment because of the total energy plant requirements. The cost differential on a Btu basis between the relatively expensive #6 fuel oil and the less expensive natural gas that otherwise would have been used was assigned as a total energy cost. The extra cost involved in using #6 fuel oil in the boilers is the difference in cost between the amounts of fuel oil and natural gas consumed in order to generate an equal amount of steam. Fuel costs were calculated by applying unit price data to the quantity of fuel oil consumed for each of the months in which it was used. An equivalent natural gas cost was calculated by computing the cost of an equivalent amount (in terms of energy produced) of natural gas. The difference between the two costs is the fuel oil adjustment cost.

Inventory costs were calculated in the following manner. Discussion with the staff of TWA revealed that a spare parts inventory of about \$170,000 was maintained for plant equipment. Inventory costs are assumed to be 15% of the inventory and include interest and stocking costs.

Land rent is self explanatory at \$300 per year.

Capital Costs

Average and marginal costs are identical for each of the previous components of total cost. However, average capital costs and marginal capital costs differ significantly. Table A.7 presents the average and marginal capital costs for the year 1975.

Average Capital Cost. The total capital invested in the total energy plant was determined in the manner presented below.

Construction costs (from TWA)	\$5,853,832
Fees for engineering services	450,000
Subtotal	\$6,303,832
Interest payments during construction*	520,066
Total capital costs.	\$6,823,898

The rate of interest assigned to the borrowing of money for the construction of the total energy plant was 10% due to the fact that TWA borrowed money via a bond issue at an interest rate of 10% at the time the decision to construct the facility was made. This interest rate coupled with an insurance rate of 1% yielded a capital charge (not including depreciation) of 11%.

The total capital was then depreciated monthly (straight-line depreciation at an annual rate of 4%) for the 25-yr life of the plant. The monthly capital payments on the depreciated value were computed at an annual rate of 11%. Therefore, the monthly capital charges incurred in the operation of the total energy plant are the sum of the monthly depreciation capital cost and the monthly interest paid on the unamortized capital costs.

Marginal Capital Cost. To determine the salvage value of the total energy plant when electric generation began in the fall of 1971, the April 1977 salvage value of \$1,837,860 was appreciated to an October 1971 level by adding 5.13%** of \$1,837,860 for each year the plant had operated (5 1/2 years). Using this approach a salvage value of \$2.356 million in October 1971 was assigned to the total energy plant. A procedure similar to the one used for average monthly capital charges was then used to compute the marginal monthly capital charges for the total energy plant.

A.3 THE COST OF THE PURCHASED POWER ALTERNATIVE

The cost of the purchased power alternative is the total cost to TWA that would have occurred if TWA had purchased electric power from the Missouri Public Service Company and made the steam that came from the total energy plant waste-heat boilers. Table A.8 presents the total cost of the purchased power alternative for the years 1973-1977.

A.3.1 The Cost of Purchased Electricity

The cost of the purchased electricity is simply the cost of purchasing the useful electricity that was generated by the total energy plant. The procedure followed for determining the cost is illustrated in Table A.9.

* The interest payments were computed for a 9-month period at an annual interest rate of 11%.

**The 5.13% depreciation rate is the straight-line rate necessary to completely depreciate the \$1,837,860 salvage value over the remaining 19 1/2 years of plant life.

An average cost per unit of electricity* was applied to the total kWh output to yield power charges. A fuel adjustment charge was then made to the kWh output and added to the power charges to yield total charges. A franchise tax was then applied to the total charges to yield the unadjusted cost of the purchased electricity.

Since a small fraction** of the total kWh output is used for auxiliary machinery an adjustment must be made to the total cost. In addition, the cost*** to TWA for the construction of a substation was incorporated into the total cost of the electricity.

A.3.2 The Cost of the Steam

The costs of generating the steam are:

- Fuel costs, and
- Labor and maintenance costs.

The fuel cost incurred (capital costs were ignored since unused boiler capacity was available) is the cost of the natural gas that would have been required for the combustion boilers in lieu of the total energy plant. The method employed to determine the fuel cost is shown in Table A.10.

First, the amount of steam generated was obtained from total energy plant data. The amount was then converted to Btu using a conversion factor of 1013 Btu/lb[†] steam. Assuming an efficiency of 80% the input (in Btu) to the boilers was determined. The Btu input was then converted to MCF of natural gas by a conversion factor of 945 Btu/CF. This calculation yields the natural gas consumption of the combustion boilers. The cost of the natural gas was then determined by applying a unit cost^{††} to the quantity of natural gas consumed.

* The average cost per unit of electricity consumed was obtained by taking a typical monthly demand and consumption profile and calculating the total electric bill based on the MPS industrial electric rate schedule that was effective at the time, which consisted of charges based on both demand and actual usage. The demand charges were based on the maximum rate of power flow (i.e., maximum draw on the line) at any time, while the actual usage charges were based on the total consumption (kWh) of energy.

** The unadjusted cost of purchased electricity was adjusted downwards by 3.5% to compensate for auxiliary machinery power consumption.

***The annual cost of the substation was determined to be \$50,000 (10% of the \$500,000 TWA paid for substation construction).

[†] Obtained from steam tables.

^{††} The unit cost has been adjusted for the increase in fuel rates that are due to the reclassification of the facility from an industrial user of natural gas to a commercial user of natural gas. The rates applied were the Gas Service Company rates that were actually applicable each month.

Labor costs were calculated in a manner similar to that used for the total energy plant. TWA stated that the operation of the combustion boilers would have required 0.5 man-hr of labor per hour of operating time. This information, along with an average hourly wage rate (which was adjusted for overhead costs) was used to determine the monthly labor cost of the generation of steam. In addition to the labor cost, needed maintenance of the combustion boilers under these hypothetical circumstances was estimated by TWA to cost \$5000 per year.

The fuel costs and labor and maintenance costs were then summed to give the total cost for the generation of steam. The total cost is presented in Table A.11.

Table A.1.a Total Energy Plant Fuel Consumption-Energy Production
Uncorrected Data, 1973

	JANUARY		FEBRUARY		MARCH		APRIL		MAY		JUNE	
	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2
FUEL CONSUMPTION												
Natural Gas (MCF)	45,900	41,885	39,909	45,684	68,387	66,085	70,634	63,453	76,183	61,063	77,826	63,300
Hours on Natural Gas	398	401	333	411	610	621	634	635	661	652	355	688
Jet Fuel (Gallons)	231,480	226,248	316,920	326,064	37,872	103,776	93,792	192,288	45,408	92,778	22,416	35,232
Hours on Jet Fuel	327	319	369	327	41	39	100	100	46	48	21	33
ENERGY PRODUCTION												
Electricity (MWII)	3,450	3,710	3,380	4,050	3,290	3,580	3,700	3,790	3,830	3,670	3,930	4,000
Steam (Thousands of Pounds)			22,133	27,621	17,952	18,049	22,276	21,053	17,620	18,149	18,325	12,132

56

	JULY		AUGUST		SEPTEMBER		OCTOBER		NOVEMBER		DECEMBER	
	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2
FUEL CONSUMPTION												
Natural Gas (MCF)	67,505	69,877	79,616	43,587	68,874	58,527	70,495	89,106	52,903	46,778	20,613	56,972
Hours on Natural Gas	569	700	644	428	658	704	683	695	630	672	183	482
Jet Fuel (Gallons)	13,392	1,920	7,020	181,176	21,216	8,524	37,200	52,080	61,584	7,488	96,792	97,800
Hours on Jet Fuel	21	3	8	183	65	33	5	7	74	9	97	98
ENERGY PRODUCTION												
Electricity (MWII)	3,440	4,420	4,430	3,940	4,090	4,310	4,030	4,000	3,400	3,150	1,630	3,690
Steam (Thousands of Pounds)	15,727	20,822	21,454	17,581	16,044	18,299	15,037	19,093	13,606	16,468	10,924	22,056

Table A.1.b Total Energy Plant Fuel Consumption-Energy Production
Uncorrected Data, 1974

	JANUARY		FEBRUARY		MARCH		APRIL		MAY		JUNE	
	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2
FUEL CONSUMPTION												
Natural Gas (MCF)	18,077	46,387	36,500	42,968	55,028	71,571	70,166	59,087	61,082	79,762	54,538	73,592
Hours on Natural Gas	201	368	350	430	584	647	643	605	609	708	546	712
Jet Fuel (Gallons)	513,096	342,984	459,456	461,448	44,256	18,336	66,360	23,904	12,240	4,080	190,440	12,456
Hours on Jet Fuel	540	385	361	451	14	18	75	27	6	2	168	11
ENERGY PRODUCTION												
Electricity (MWH)	3,420	3,870	4,380	3,140	3,050	4,120	4,320	3,320	3,210	4,590	3,870	4,070
Steam (Thousands of Pounds)	16,763	22,490	12,573	11,692	1,777	17,029	21,682	20,274	11,584	22,475	12,102	12,123

57

	JULY		AUGUST		SEPTEMBER		OCTOBER		NOVEMBER		DECEMBER	
	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2
FUEL CONSUMPTION												
Natural Gas (MCF)	59,391	49,059	42,203	77,526	61,466	62,500	50,270	67,948	59,109	39,100	44,264	27,937
Hours on Natural Gas	605	492	339	727	608	648	490	691	583	389	402	274
Jet Fuel (Gallons)	141,144	217,824	352,542	41,928	46,528	105,264	129,192	32,232	160,704	350,520	280,128	389,112
Hours on Jet Fuel	99	218	299	14	183	90	31	7	162	356	277	379
ENERGY PRODUCTION												
Electricity (MWH)	3,880	3,950	3,930	4,480	3,860	4,230	3,500	4,320	4,030	4,130	3,950	3,840
Steam (Thousands of Pounds)	19,714	18,445	17,480	18,709	15,877	6,809	17,085	16,723	21,185	19,961	18,709	19,844

Table A.1.c Total Energy Plant Fuel Consumption-Energy Production
Uncorrected Data, 1975

	JANUARY		FEBRUARY		MARCH		APRIL		MAY		JUNE	
	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2
FUEL CONSUMPTION												
Natural Gas (MCF)	21,243	40,688	23,347	16,163	31,622	35,385	55,793	58,454	57,943	45,695	59,398	24,313
Hours on Natural Gas	222	385	135	133	269	289	474	473	336	364	635	208
Jet Fuel (Gallons)	505,056	345,888	660,744	553,416	466,800	353,976	266,088	249,840	371,736	314,424	93,048	488,904
Hours on Jet Fuel	496	355	608	609	384	382	268	264	354	346	102	536
ENERGY PRODUCTION												
Electricity (MWII)	3,790	4,190	4,080	3,960	3,620	3,780	4,140	4,120	4,050	4,090	4,160	4,290
Steam (Thousands of Pounds)	17,876	20,634	16,282	18,898	14,748	16,411	15,540	16,014	17,611	14,743	17,646	13,897

58

	JULY		AUGUST		SEPTEMBER		OCTOBER		NOVEMBER		DECEMBER	
	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2
FUEL CONSUMPTION												
Natural Gas (MCF)	49,900	75,106	69,771	56,752	8,989	34,127	39,993	76,381	46,669	69,339	58,571	22,256
Hours on Natural Gas	465	591	468	386	165	593	261	453	303	435	334	129
Jet Fuel (Gallons)	54,192	54,192	508	395	333	116	2,750	337	4,009	1,379	13,463	1,298
Hours on Jet Fuel	40	40	9	7	3	5	49	6	72	24	251	12
ENERGY PRODUCTION												
Electricity (MWII)	3,410	4,770	4,750	3,600	1,650	6,310	3,020	4,830	3,550	4,500	6,250	1,420
Steam (Thousands of Pounds)	15,047	17,816	19,888	16,442	4,425	25,432	117,648	183,369	26,434	42,007	24,176	5,372

Table A.1.d Total Energy Plant Fuel Consumption-Energy Production
Uncorrected Data, 1976

	JANUARY		FEBRUARY		MARCH		APRIL		MAY		JUNE	
	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2
FUEL CONSUMPTION												
Natural Gas (MCF)	32,695	13,370	29,796	56,196	61,854	51,390	7,210	109,002	37,654	45,310	76,439	33,408
Hours on Natural Gas	204	81	266	342	405	304	65	719	278	523	513	334
Jet Fuel (Gallons)	570,384	150,600	161,376	297,240	136,992	35,472	93,360	20,904	37,128	30,024	43,824	21,840
Hours on Jet Fuel	405	113	48	227	43	18	4	1	14	16	16	3
ENERGY PRODUCTION												
Electricity (MWH)	5,960	1,640	2,110	5,680	4,270	3,320	480	7,790	2,710	5,090	5,170	2,870
Steam (Thousands of Pounds)	24,687	5,066	9,953	25,186	18,912	13,512	1,882	31,626	12,772	14,645	107,594	134,063

	JULY		AUGUST		SEPTEMBER		OCTOBER		NOVEMBER		DECEMBER	
	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2	Unit 1	Unit 2
FUEL CONSUMPTION												
Natural Gas (MCF)	58,556	58,919	54,519	68,578	46,921	74,580	57,707	60,045	65,514	30,960	39,737	41,289
Hours on Natural Gas	473	479	414	536	361	542	397	361	442	192	448	158
Jet Fuel (Gallons)	38,688	23,064	6,312	4,970	10,824	6,336	35,976	29,448	217,608	83,832	160,848	308,043
Hours on Jet Fuel	12	5	31	7	11	3	12	15	164	72	130	350
ENERGY PRODUCTION												
Electricity (MWH)	3,990	4,060	3,670	4,770	3,220	5,020	4,090	3,830	5,990	1,980	3,940	3,810
Steam (Thousands of Pounds)		12,221	10,846	1,451	14,102	130						

Table A.2 Total Energy Plant Fuel Consumption-
Energy Production, 1975

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER
<u>HOURS OF OPERATION</u>												
Single Unit	30	3	20	9	40	7	304	618	722	671	654	714
Double Unit	714	741	652	735	680	737	416	126	22	49	90	6
TOTAL	744	744	672	744	720	744	720	744	744	720	744	720
<u>ENERGY PRODUCTION (MWH)</u>												
Single Unit	322	32	220	100	452	80	3454	6936	7725	7316	7076	7606
Double Unit	7658	8008	7180	8160	7688	8370	4726	1414	235	534	974	64
TOTAL	7980	8040	7400	8260	8140	8450	8180	8350	7960	7850	8050	7670
<u>HOURS ON FUEL TYPE</u>												
Natural Gas	607	268	558	947	700	843	1056	854	758	714	738	463
Jet Fuel	851	1217	766	532	700	638	80	16	8	55	96	263
TOTAL	1458	1485	1324	1479	1400	1481	1136	870	766	769	834	726
<u>FUEL CONSUMPTION^a</u>												
Natural Gas (MCF)	90,415	39,826	85,087	144,893	110,368	131,852	188,327	181,543	167,407	156,702	155,567	103,293
Jet Fuel (Gallons)	867,269	1,237,358	799,153	556,904	755,113	682,734	97,613	23,271	12,088	82,586	138,453	401,434

^aThe data for fuel consumption have been adjusted.

Table A.3.a Total Energy Plant Fuel Consumption-Adjusted Data, 1973

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER
FUEL CONSUMPTION												
Natural Gas (MCF)	107,302	103,879	175,195	176,701	190,229	181,741	201,838	181,406	213,396	215,968	163,703	91,777
Hours on Natural Gas	799	744	1,231	1,269	1,313	1,043	1,269	1,072	1,362	1,378	1,302	665
Jet Fuel (Gallons)	593,561	664,863	77,897	190,537	93,177	64,377	26,117	221,137	105,052	12,867	71,399	184,126
Hours on Jet Fuel	646	696	80	200	94	54	24	191	98	12	83	195
ENERGY PRODUCTION												
Electricity (MWII)	7,160	7,430	6,870	7,490	7,500	7,430	7,860	8,370	8,400	8,060	6,550	5,320
Steam (Thousands of Pounds)		49,754	36,001	43,320	35,769	30,457	36,549	39,036	34,342	34,130	30,074	32,980

Table A.3.b Total Energy Plant Fuel Consumption-Adjusted Data, 1974

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER
FUEL CONSUMPTION												
Natural Gas (MCF)		117,061	186,594	187,342	211,355	187,913	165,485	181,640	191,375	193,229		104,815
Hours on Natural Gas	569	780	1,231	1,248	1,407	1,258	1,097	1,166	1,256	1,181	972	676
Jet Fuel (Gallons)		525,726	33,186	104,759	8,222	182,936	327,176	333,602	185,561	42,540		695,904
Hours on Jet Fuel	925	512	32	102	8	179	317	313	178	38	518	656
ENERGY PRODUCTION												
Electricity (MWII)	7,290	7,520	7,170	7,710	7,800	7,940	7,830	8,410	8,090	7,820	8,160	7,790
Steam (Thousands of Pounds)	39,252	24,365	18,806	41,956	34,058	24,225	38,159	36,189	22,686	33,809	41,146	38,553

Table A.3.c Total Energy Plant Fuel Consumption-Adjusted Data, 1975

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER
FUEL CONSUMPTION												
Natural Gas (MCF)	90,415	39,826	85,087	144,893	110,368	131,652	188,327	181,543	167,407	156,702	155,567	103,293
Hours on Natural Gas	607	268	558	947	700	843	1,096	854	758	714	738	463
Jet Fuel (Gallons)	867,269	1,237,358	799,153	556,904	755,113	682,734	97,613	23,271	12,088	82,586	138,453	401,434
Hours on Jet Fuel	851	1,217	766	532	700	638	80	18	8	55	96	263
ENERGY PRODUCTION												
Electricity (MWH)	7,980	8,040	7,400	8,260	8,140	8,450	8,180	8,350	7,960	7,850	8,050	7,670
Steam (Thousands of Pounds)	38,510	35,180	31,159	31,554	32,354	31,544	32,463	36,330	29,857	35,220	35,221	29,548

62

Table A.3.d Total Energy Plant Fuel Consumption-Adjusted Data, 1976

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER
FUEL CONSUMPTION												
Natural Gas (MCF)	58,187	112,787	151,969	176,277	165,794	173,900	184,118	187,998	183,007	165,510	128,642	105,182
Hours on Natural Gas	285	548	709	784	801	847	952	950	903	758	634	606
Jet Fuel (Gallons)	723,576	387,242	89,456	7,692	42,484	26,690	22,495	51,450	19,412	40,336	327,624	570,008
Hours on Jet Fuel	518	275	61	5	30	19	17	38	14	27	236	480
ENERGY PRODUCTION												
Electricity (MWH)	7,600	7,790	7,590	8,270	7,800	8,040	8,050	8,440	8,240	7,920	7,970	7,750
Steam (Thousands of Pounds)	29,753	35,138	32,425	33,508	31,003	30,013	32,341	36,722	30,907	35,534	34,871	29,856

Table A.3.e Total Energy Plant Fuel Consumption-Adjusted Data, 1977

	JANUARY	FEBRUARY	MARCH	APRIL	DECEMBER
FUEL CONSUMPTION					
Natural Gas (MCF)	51,382	85,307	151,131		
Hours on Natural Gas	332	477	681		
Jet Fuel (Gallons)	999,582	695,000	30,367		
Hours on Jet Fuel	944	568	20		
ENERGY PRODUCTION					
Electricity (MWH)	7,700	7,900	7,290		
Steam (Thousands of Pounds)	30,144	35,634	31,143		

Table A.4.a(1) Total Energy Plant Average Monthly Cost, 1973 (dollars)

1973	FUEL COST			Operating and Maintenance Costs	Capital Costs	Total
	Natural Gas	Jet Fuel	Subtotal			
January	31,815	83,751	115,566	45,934	28,229	189,729
February	30,946	93,812	124,758	45,934	28,157	198,849
March	54,065	10,991	65,056	43,333	28,085	136,474
April	55,572	26,885	82,457	45,934	28,013	156,404
May	59,656	13,147	72,803	45,064	27,941	145,808
June	56,849	9,084	65,933	45,934	27,869	139,736
July	62,973	3,685	66,658	45,064	27,797	139,519
August	56,762	31,202	87,964	45,934	27,725	161,623
September	68,457	14,823	83,280	45,934	27,653	156,867
October	69,434	1,816	71,250	45,064	27,581	143,895
November	52,745	10,074	62,819	45,934	27,509	136,262
December	30,644	25,980	56,624	45,064	27,437	129,125
Total	629,918	325,250	955,168	545,127 (Fuel oil adjustment) <u>54,872</u> Total 599,999	333,996 (Fuel oil adj.) <u>54,872</u> Total 1,889,163	1,834,291

Table A.4.b(1) Total Energy Plant Marginal Monthly Cost, 1973 (dollars)

1973	FUEL COST			Operating and Maintenance Costs	Capital Costs	Total
	Natural Gas	Jet Fuel	Subtotal			
January	31,815	83,751	115,566	45,934	81,754	243,254
February	30,946	93,812	124,758	45,934	81,546	252,238
March	54,065	10,991	65,056	43,333	81,337	189,726
April	55,572	26,885	82,457	45,934	81,129	209,520
May	59,656	13,147	72,803	45,064	80,920	198,787
June	56,849	9,084	65,933	45,934	80,712	192,579
July	62,973	3,685	66,658	45,064	80,503	192,225
August	56,762	31,202	87,964	45,934	80,295	214,193
September	68,457	14,823	83,280	45,934	80,086	209,300
October	69,434	1,816	71,250	45,064	79,878	196,192
November	52,745	10,074	62,819	45,934	79,669	188,422
December	30,644	25,980	56,624	45,064	79,461	181,149
Total	629,918	325,250	955,168	545,127 (Fuel oil adjustment) <u>54,872</u> Total 599,999	967,290 (Fuel oil adj.) <u>54,872</u> Total 2,522,457	2,467,585

Table A.4.a(2) Total Energy Plant Average Monthly Cost, 1974 (dollars)

1974	FUEL COST			Operating and Maintenance Costs	Capital Costs	Total
	Natural Gas	Jet Fuel	Subtotal			
January	27,581	184,763	212,344	62,385	27,365	302,094
February	45,490	115,134	160,624	60,522	27,293	248,439
March	72,828	7,268	80,096	47,420	27,221	154,737
April	72,333	22,942	95,275	49,456	27,149	171,880
May	81,498	1,801	83,299	48,516	27,077	158,892
June	75,034	40,063	115,097	49,456	27,005	191,558
July	67,849	71,652	139,501	49,516	26,933	215,950
August	79,449	73,059	152,508	49,456	26,861	228,825
September	86,674	40,638	127,312	49,456	26,789	203,557
October	90,257	9,316	99,573	51,158	26,717	177,448
November	80,604	99,347	179,951	55,039	26,645	261,635
December	51,302	152,403	203,605	63,820	26,573	293,998
Total	830,799	818,386	1,649,185	636,200	323,628	2,609,013

Table A.4.b(2) Total Energy Plant Marginal Monthly Cost, 1974 (dollars)

1974	FUEL COST			Operating and Maintenance Costs	Capital Costs	Total
	Natural Gas	Jet Fuel	Subtotal			
January	27,581	184,763	212,344	62,385	79,252	353,981
February	45,490	115,134	160,624	60,522	79,043	300,189
March	72,828	7,268	80,096	47,420	78,835	206,351
April	72,333	22,942	95,275	49,456	78,626	223,357
May	81,498	1,801	83,299	48,516	78,418	210,233
June	75,034	40,063	115,097	49,456	78,209	242,762
July	67,849	71,652	139,501	49,516	78,001	267,018
August	79,449	73,059	152,508	49,456	77,792	279,756
September	86,674	40,638	127,312	49,456	77,584	254,352
October	90,257	9,316	99,573	51,158	77,375	228,106
November	80,604	99,347	179,951	55,039	77,167	312,157
December	51,302	152,403	203,605	63,820	76,958	344,383
Total	830,799	818,386	1,649,185	636,200	937,260	3,222,645

Table A.4.a(3) Total Energy Plant Average Monthly Cost, 1975 (dollars)

1975	FUEL COST			Operating and Maintenance Costs	Capital Costs	Total
	Natural Gas	Jet Fuel	Subtotal			
January	44,168	228,525	272,693	71,936	76,750	421,379
February	19,455	326,044	345,499	73,049	76,541	495,089
March	46,168	212,655	258,823	63,785	76,333	398,941
April	78,315	147,969	226,284	61,534	76,124	363,942
May	69,863	212,413	282,276	58,138	75,916	416,330
June	77,147	189,595	266,742	58,882	75,707	401,331
July	109,738	26,356	136,094	49,667	75,499	261,260
August	98,414	6,300	104,714	50,600	75,290	230,604
September	90,751	3,272	94,023	50,600	75,082	219,705
October	84,838	23,653	108,491	53,009	74,665	236,373
November	192,700	38,448	231,148	57,852	74,665	363,665
December	58,412	114,971	173,383	69,085	74,456	316,924
Total	969,969	1,530,201	2,500,170	718,137	907,236	4,125,543

Table A.4.b(3) Total Energy Plant Marginal Monthly Cost, 1975 (dollars)

1975	FUEL COST			Operating and Maintenance Costs	Capital Costs	Total
	Natural Gas	Jet Fuel	Subtotal			
January	44,168	228,525	272,693	71,936	26,501	371,130
February	19,455	326,044	345,499	73,049	26,429	444,977
March	46,168	212,655	258,823	63,785	26,357	348,965
April	78,315	147,969	226,284	61,534	26,285	314,103
May	69,863	212,413	282,276	58,138	26,213	366,627
June	77,147	189,595	266,742	58,882	26,141	351,765
July	109,738	26,356	136,094	49,667	26,069	211,830
August	98,414	6,300	104,714	50,600	25,997	181,311
September	90,751	3,272	94,023	50,600	25,929	170,548
October	84,838	23,653	108,491	53,009	25,853	187,353
November	192,700	38,448	231,148	57,852	25,781	314,781
December	58,412	114,971	173,383	69,085	25,709	268,177
Total	969,969	1,530,201	2,500,170	718,137	313,260	3,531,567

Table A.4.a(4)---Total Energy Plant Average Monthly Cost, 1976 (dollars)

1976	FUEL COST			Operating and Maintenance Costs	Capital Costs	Total
	Natural Gas	Jet Fuel	Subtotal			
January	33,737	225,539	259,276	79,505	25,637	364,418
February	68,597	131,353	199,950	63,495	25,565	289,010
March	92,382	30,343	122,725	56,398	25,443	204,566
April	128,101	2,609	130,710	57,274	25,421	213,405
May	120,449	14,411	134,860	56,156	25,349	216,365
June	129,486	9,053	138,539	57,274	25,277	221,090
July	137,039	7,156	144,195	56,156	25,205	225,556
August	147,560	16,366	163,926	57,274	25,133	246,333
September	144,722	6,167	150,889	57,274	25,061	233,224
October	131,614	13,392	145,006	56,156	24,989	226,151
November	102,862	114,013	216,875	62,631	24,917	304,423
December	64,529	198,363	262,892	71,648	24,045	359,385
Total	1,301,078	768,765	2,069,843	731,241	302,842	3,103,926

Table A.4.b(4) Total Energy Plant Marginal Monthly Cost, 1976 (dollars)

1976	FUEL COST			Operating and Maintenance Costs	Capital Costs	Total
	Natural Gas	Jet Fuel	Subtotal			
January	33,737	225,539	259,276	79,505	74,248	413,029
February	68,597	131,353	199,950	63,495	74,039	337,484
March	92,382	30,343	122,725	56,398	73,831	252,954
April	128,101	2,609	130,710	57,274	73,622	261,606
May	120,449	14,411	134,860	56,156	73,414	264,430
June	129,486	9,053	138,539	57,274	73,205	269,018
July	137,039	7,156	144,195	56,156	72,997	273,348
August	147,560	16,366	163,926	57,274	72,778	293,978
September	144,722	6,167	150,889	57,274	72,580	280,743
October	131,614	13,392	145,006	56,156	72,371	273,533
November	102,862	114,013	216,875	62,631	72,163	351,669
December	64,529	198,363	262,892	71,648	71,954	406,494

Table A.4.a(5) Total Energy Plant Average Monthly Cost, 1977 (dollars)

1977	FUEL COST			Operating and Maintenance Costs	Capital Costs	Total
	Natural Gas	Jet Fuel	Subtotal			
January	49,466	339,858	389,344	61,447	24,773	475,564
February	95,612	236,300	331,912	61,447	24,701	418,061
March	170,838	10,325	181,163	57,895	24,629	263,687
April						
May						
June						
July						
August						
September						
October						
November						
December						
Total	314,936	586,483	902,419	180,789	741,103	1,157,311

Table A.4.b(5) Total Energy Plant Marginal Monthly Cost, 1977 (dollars)

1977	FUEL COST			Operating and Maintenance Costs	Capital Costs	Total
	Natural Gas	Jet Fuel	Subtotal			
January	49,486	339,858	389,344	61,447	71,746	522,537
February	95,612	236,300	331,912	61,447	71,537	464,896
March	170,838	10,325	181,163	57,895	71,329	310,387
April						
May						
June						
July						
August						
September						
October						
November						
December						
Total	314,936	586,483	902,419	180,789	214,612	1,297,820

Table A.5.a Total Energy Plant Monthly Fuel Costs, 1973

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER	TOTAL
FUELS CONSUMED													
Natural Gas (MCF)	107,305	103,879	175,195	176,701	190,229	181,741	201,838	181,406	213,396	215,968	163,703	91,777	2,003,135
Jet Fuel (Gallons)	593,561	664,863	77,897	190,537	93,177	64,377	26,117	221,137	105,052	12,867	71,399	184,126	2,305,170
UNIT COST													
Natural Gas \$/MCF	.2965	.2979	.3086	.3145	.3136	.3128	.3120	.3129	.3208	.3215	.3222	.3339	
Jet Fuel \$/Gallons	.1411	.1411	.1411	.1411	.1411	.1411	.1411	.1411	.1411	.1411	.1411	.1411	.1411
TOTAL COST (Dollars)													
Natural Gas \$	31,815	30,946	54,065	55,572	59,656	56,849	62,973	56,762	68,457	69,434	52,745	30,644	629,916
Jet Fuel \$	83,751	93,812	10,991	26,885	13,147	9,084	3,685	31,202	14,823	1,816	10,074	25,980	325,250
TOTAL	115,566	124,758	65,056	82,457	72,803	65,932	66,658	87,964	83,280	71,250	62,819	56,624	955,166

Table A.5.b Total Energy Plant Monthly Fuel Costs, 1974

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER	TOTAL
FUELS CONSUMED													
Natural Gas (MCF)	82,063	117,061	186,594	187,342	211,355	187,913	165,485	181,640	191,375	193,229	165,410	104,815	1,974,282
Jet Fuel (Gallons)	843,666	525,726	33,186	104,759	8,222	182,936	327,176	333,602	185,581	42,540	453,638	695,904	3,736,916
UNIT COST													
Natural Gas \$/MCF	.3361	.3886	.3903	.3861	.3856	.3993	.4100	.4374	.4529	.4671	.4873	.4885	
Jet Fuel \$/Gallons	.2190	.2190	.2190	.2190	.2190	.2190	.2190	.2190	.2190	.2190	.2190	.2190	.2190
TOTAL COST (Dollars)													
Natural Gas \$	27,561	45,490	72,828	72,333	81,498	75,034	67,849	79,449	86,674	90,257	80,604	51,202	830,799
Jet Fuel \$	184,763	115,134	7,268	22,942	1,801	40,063	71,652	73,059	40,638	9,316	99,347	152,403	818,386
TOTAL	212,344	160,624	80,096	95,275	83,299	115,097	139,501	152,508	127,312	99,573	179,951	203,605	1,649,185

Table A.5.c Total Energy Plant Monthly Fuel Costs, 1975

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER	TOTAL
FUELS CONSUMED													
Natural Gas (MCF)	90,415	39,826	85,087	144,893	110,368	131,852	188,327	181,543	167,407	156,702	155,567	103,293	1,555,280
Jet Fuel (Gallons)	867,269	1,237,358	799,153	556,904	755,113	682,734	97,613	23,271	12,088	82,586	138,453	401,434	5,653,976
UNIT COST													
Natural Gas \$/MCF	.4885	.4885	.5426	.5405	.6330	.5851	.5827	.5421	.5421	.5414	.5413	.5655	
Jet Fuel \$/Gallons	.2635	.2635	.2661	.2657	.2813	.2777	.2700	.2707	.2707	.2864	.2777	.2864	
TOTAL COST (Dollars)													
Natural Gas \$	44,168	19,455	46,168	78,315	69,863	77,147	109,738	98,414	90,751	84,838	192,700	58,412	969,969
Jet Fuel \$	228,525	362,044	212,655	147,969	212,413	189,595	26,356	6,300	3,272	23,653	38,448	114,971	1,530,201
TOTAL	272,693	345,499	258,823	226,284	201,276	266,742	136,094	104,714	94,023	108,481	231,148	171,383	2,500,170

70

Table A.5.d Total Energy Plant Monthly Fuel Costs, 1976

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER	TOTAL
FUELS CONSUMED													
Natural Gas (MCF)	58,187	112,787	151,969	176,277	165,794	173,900	184,118	187,998	183,007	165,510	128,642	105,182	1,793,371
Jet Fuel (Gallons)	723,576	387,242	89,456	7,692	42,484	26,690	12,495	51,450	19,412	90,336	327,624	570,008	2,308,467
UNIT COST													
Natural Gas \$/MCF	.5798	.6082	.6079	.7267	.7265	.7446	.7443	.7849	.7908	.7952	.7936	.6135	
Jet Fuel \$/Gallons	.3117	.3392	.3392	.3392	.3392	.3392	.3181	.3181	.3177	.3320	.3480	.3480	
TOTAL COST (Dollars)													
Natural Gas \$	33,737	68,597	92,382	128,101	120,449	129,486	137,039	147,560	144,722	131,614	102,862	64,529	1,301,078
Jet Fuel \$	225,539	131,353	30,343	2,609	14,411	9,053	7,156	16,366	6,167	13,392	114,013	198,363	768,765
TOTAL	259,276	199,950	122,725	130,710	134,860	138,539	144,195	163,926	150,889	145,006	216,875	262,892	2,069,843

Table A.5.e Total Energy Plant Monthly Fuel Costs, 1977

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	TOTAL
<u>FUELS CONSUMED</u>							
Natural Gas (MCF)	51,382	85,307	151,131				287,820
Jet Fuel (Gallons)	999,582	695,000	30,367				1,724,949
<u>UNIT COST</u>							
Natural Gas \$/MCF	.9631	1.1208	1.1304				
Jet Fuel \$/Gallons	.3400	.3400	.3400				
<u>TOTAL COST (Dollars)</u>							
Natural Gas \$	49,486	95,612	170,838				315,936
Jet Fuel \$	339,858	236,300	10,325				586,483
TOTAL	389,344	331,912	181,163				902,419

Table A.6 Total Energy Plant Operating and Maintenance Costs, 1975 (dollars)

	JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTODER	NOVEMBER	DECEMBER	TOTAL
<u>NON-FUEL OPERATING COSTS</u>													
Hours in Month	744	744	672	744	720	744	720	744	744	720	744	720	8,760
Adjusted Wage Rate	22.40	22.40	22.40	22.40	22.40	22.40	22.40	22.40	22.40	22.40	22.40	22.40	22.40
Labor Costs \$	16,666	16,666	15,053	16,666	16,128	16,666	16,128	16,666	16,666	16,128	16,666	16,128	196,224
Material Cost (1% of labor costs)	167	167	151	167	161	167	161	167	167	161	167	161	196
Total Operating costs \$	16,833	16,833	15,204	16,833	16,289	16,833	16,289	16,833	16,833	16,289	16,833	16,289	196,420
<u>MAINTENANCE COSTS</u>													
Non-engine Maintenance													
Hours in Month	744	744	672	744	720	744	720	744	744	720	744	720	8,760
Adjusted Wage Rate	10.80	10.80	10.80	10.80	10.80	10.80	10.80	10.80	10.80	10.80	10.80	10.80	10.80
Labor Costs \$	8,035	8,035	7,258	8,035	7,776	8,035	7,776	8,035	8,035	7,776	8,035	7,776	94,608
Material Costs (50% of labor costs)	4,018	4,018	3,629	4,018	3,888	4,018	3,888	4,018	4,018	3,888	4,018	3,888	47,304
Total Costs \$	12,053	12,053	10,887	12,053	11,664	12,053	11,664	12,053	12,053	11,664	12,053	11,664	141,912
Engine Maintenance \$	18,284	18,284	18,284	18,284	18,284	18,284	18,284	18,284	18,284	18,284	18,284	18,284	219,408
Total Maintenance Cost \$	30,337	30,337	29,171	30,337	29,948	30,337	29,948	30,337	30,337	29,948	30,337	29,948	361,320
<u>MISCELLANEOUS COSTS</u>													
Fuel oil Adj. \$	21,336	22,445	15,980	10,934	8,471	8,282				3,342	7,252	19,418	117,464
Inventory Costs \$	3,430	3,430	3,430	3,430	3,430	3,430	3,430	3,430	3,430	3,430	3,430	3,430	41,160
Total Misc. \$	24,766	25,879	19,410	14,364	11,901	11,712	3,430	3,430	3,430	6,772	10,682	22,848	158,624
<u>TOTAL COSTS</u> \$	71,936	73,049	63,785	61,534	58,138	58,882	49,667	50,600	50,600	53,009	57,852	69,085	718,137

Table A.7 Total Energy Plant Capital Costs:
Average and Marginal, 1975 (dollars)

	Average	Marginal
January	\$ 76,750	\$ 26,501
February	76,541	26,429
March	76,333	26,357
April	76,124	26,285
May	75,916	26,213
June	75,707	26,141
July	75,499	26,069
August	75,290	25,997
September	75,082	25,925
October	74,873	25,853
November	74,665	25,781
December	74,456	25,709
Total	\$ 907,236	\$ 313,260

Table A.8.a Purchased Power Alternative Monthly Cost, 1973 (dollars)

1973	Electricity	Steam	Total
January	90,276		90,276
February	93,523	29,200	122,723
March	86,788	22,803	109,591
April	94,245	27,197	121,442
May	94,364	23,306	117,670
June	99,536	20,896	120,432
July	98,694	23,605	122,299
August	104,828	25,035	129,863
September	105,189	23,180	128,369
October	101,099	22,876	123,975
November	82,940	21,090	104,030
December	68,147	22,857	91,004
Total	1,119,629	262,045	1,381,674

Table A.8.b Purchased Power Alternative Monthly Cost, 1974 (dollars)

1974	Electricity	Steam	Total
January	103,623	26,902	130,525
February	106,762	20,959	127,721
March	101,987	17,142	119,129
April	104,590	31,104	135,694
May	106,727	26,287	133,014
June	114,863	21,224	136,087
July	108,733	29,916	138,649
August	117,778	30,239	148,017
September	114,705	21,931	136,636
October	108,761	29,834	138,595
November	113,140	36,213	149,353
December	109,483	34,213	143,696
Total	1,311,152	325,964	1,637,116

Table A.8.c Purchased Power Alternative Monthly Cost, 1975 (dollars)

1975	Electricity	Steam	Total
January	118,131	34,341	152,472
February	121,058	31,948	153,006
March	109,391	30,712	140,103
April	117,708	31,541	149,249
May	116,004	35,979	151,983
June	119,971	33,418	153,389
July	131,685	34,229	165,914
August	136,054	35,383	171,437
September	133,583	30,267	163,850
October	136,886	34,271	171,157
November	139,024	34,469	173,493
December	129,183	30,747	159,930
Total	1,508,678	397,305	1,905,983

Table A.8.d Purchased Power Alternative Monthly Cost, 1976 (dollars)

1976	Electricity	Steam	Total
January	125,617	32,813	158,430
February	125,765	38,078	163,843
March	127,723	35,805	163,528
April	140,922	42,566	183,488
May	133,391	39,720	173,111
June	133,310	39,659	172,969
July	146,733	41,880	188,613
August	180,927	48,765	229,692
September	153,152	42,522	195,674
October	138,967	47,692	186,659
November	139,161	43,387	182,548
December	128,573	34,410	162,983
Total	1,674,241	487,297	2,161,538

Table A.8.e Purchased Power Alternative Monthly Cost, 1977 (dollars)

1977	Electricity	Steam	Total
January	170,979	50,210	221,189
February	142,775	49,590	192,365
March	118,936	63,861	182,797
April			
May			
June			
July			
August			
September			
October			
November			
December			
Total (3 months)	432,690	163,661	596,351

Table A.9 Purchased Power Alternative Electricity Costs, 1975 (dollars)

1975	Energy Produced	Rate	Energy Charge	Fuel Adjustment Factor	Fuel Adjustment Charge	Total Charges	Franchise Tax Rate	Franchise Tax	Cost of Purchased Electricity	Cost of Purchased Electricity (Adjusted)
	(MWH)	\$/KWH	Dollars	\$/KWH	Dollars	Dollars	Fraction	Dollars	Dollars	Dollars
January	7,980	.0125	99,750	.00137	10,933	110,683	.067	7,416	118,098	118,131
February	8,040	.0125	100,500	.00162	13,025	113,525	.067	7,606	121,131	121,058
March	7,400	.0125	92,500	.00131	9,694	102,194	.067	6,847	109,041	109,391
April	8,260	.0125	103,250	.00085	7,021	110,271	.067	7,388	117,659	117,708
May	8,130	.0125	101,625	.00086	6,992	108,617	.067	7,277	115,894	116,004
June	8,450	.0125	105,625	.00081	6,845	112,470	.067	7,535	120,005	119,971
July	8,180	.0140	114,520	.00114	9,325	123,845	.067	8,298	132,143	131,685
August	8,350	.0140	116,900	.00134	11,189	128,089	.067	8,582	136,671	136,054
September	7,960	.0140	111,440	.00179	14,248	125,688	.067	8,421	134,110	133,583
October	7,850	.0140	109,900	.00242	18,997	128,897	.067	8,636	137,533	136,886
November	8,050	.0140	112,700	.00227	18,274	130,974	.067	8,775	139,749	139,024
December	7,670	.0140	107,380	.00183	14,036	121,416	.067	8,135	129,551	129,183
Total	96,320		1,276,090		140,579	1,416,669		94,916	1,511,585	1,508,680

Table A.10 Purchased Power Alternative Steam Production
Fuel Costs, 1975 (dollars)

	Steam Generated	Input Natural Gas	Unit Cost	Total Cost
	(thousands of dollars)	MCF	\$/MCF	Dollars
January	38,510	51,601	.5363	27,674
February	35,180	47,139	.5363	25,281
March	31,159	41,751	.5904	24,650
April	31,554	42,281	.5883	24,874
May	32,354	43,353	.6808	29,514
June	31,544	42,267	.0329	26,751
July	32,863	44,035	.6305	27,764
August	36,330	48,680	.5899	28,716
September	29,857	40,007	.5899	23,600
October	35,220	47,193	.5892	27,806
November	35,221	47,194	.5891	27,802
December	29,548	39,593	.6133	24,282
Total	399,340	535,094		318,714

Table A.11 Purchased Power Alternative Steam Production
Costs, 1975 (dollars)

1975	Labor Costs	Maintenance Costs	Fuel Costs	Total Cost
Month	Dollars	Dollars	Dollars	Dollars
January	6,250	417	27,674	34,341
February	6,250	417	25,281	31,948
March	5,645	417	24,650	30,712
April	6,250	417	24,874	31,541
May	6,048	417	29,514	35,979
June	6,250	417	26,751	33,418
July	6,048	417	27,764	34,229
August	6,250	417	28,716	35,383
September	6,250	417	23,600	30,267
October	6,048	417	27,806	34,271
November	6,250	417	27,802	34,469
December	6,048	417	24,282	30,747
Total	73,587	5004	318,714	397,305