✓
DOE/PC/90300--T 4

DOE/PC/90300--T4

DE92 005202

TECHNICAL PROGRESS REPORT

CONTRACT TITLE: Rapid Pressure Swing Absorption Cleanup of Post-Shift
Reactor Synthesis Gas

CONTRACT NUMBER: DE-FG22-90PC90300

CONTRACT PERIOD: 9/7/90 - 8/31/93

CONTRACTOR'S NAME: Center for Membranes and Separation Technologies
Department of Chemistry and Chemical Engineering
Stevens Institute of Technology
Castle Point, Hoboken, NJ 07030

INVESTIGATORS: Dr. K. K. Sirkar
Dr. S. Majumdar
Mr. S. Bhaumik

REPORT NUMBER: 4

REPORT PERIOD: 6/1/91 - 9/31/91

REPORTING DATE: October 31, 1991

PREVIOUS REPORT DATE: June 28, 1991

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Overview of Progress

Two experimental problems were identified in Technical Progress No. 3. The first problem was related to the difficulty in building up high pressure in the fiber lumen; the large void space in the module before the hollow fiber entrance and after the fiber exit was the source of the second problem. We have made significant progress toward eliminating these problems. A few experiments have also been carried out using a $\text{CO}_2\text{-N}_2$ feed gas mixture and water as an absorbent liquid. Two hollow fiber modules have been used in these experiments. The details of the modules are given in Table 1.

Modifications of Experimental Setup

It is necessary to raise the feed gas pressure in a relatively short period of time to increase the rate of gas absorption in the stagnant liquid. To build up higher feed gas pressure in the fiber lumen, a few changes have been incorporated in the experimental setup. So far only one electronic timer had been used to control two solenoid valves; the 2-way solenoid valve at the permeator exit end and the 3-way solenoid valve at the permeator inlet end. Therefore, both the valves would open and close simultaneously; this prevented a large pressure build up in the lumen since there was very little flow pressure drop in the hollow fiber lumen. If the 2-way valve at the exit end can be kept closed for an extra amount of time (note that the entrance valve would still be open during this time), it would then be possible to build up a certain pressure within a short time. Next, the 2-way valve may be opened with simultaneous closing of the 3-way valve at the feed end and the purified gas may be taken out to the surge drum. Finally, the 2-way valve may be closed and the other opening of the 3-way entrance valve directly opened to the vacuum line to carry out desorption.

To achieve the above goals, an independent but synchronous control of the two solenoid valves are required. A new timer was built for that purpose. The timer was made in our laboratory with the following components: time delay relay (Part No. TDML120AL, SSAC Inc., New York, NY), general purpose relay (Type KRP11AY-120, Newark Electronics, Newark, NJ) and some other items such as switch, relay sockets, fuse, etc., (all from Newark Electronics). The new timer enabled us to decouple the two sets of solenoid valves and we have been able to reach a pressure level of at least 40 psig. It appears that higher pressure can also be attained by changing the delay time.

The second problem concerns the void space in the gas entry fittings as well as the exit end and the tubes in both ends of the permeator. The void space has been reduced somewhat by filling it with packing materials such as polyethylene beads. The beads are approximately 2 mm in diameter.

As the experiments were going on, it was found that a few solenoid valves were not working well possibly because of overheating. Additional 2-way and 3-way solenoid

valves have been procured to replace the older ones.

For further operational flexibility (such as to provide an additional delay during absorption), a third solenoid valve was introduced in the setup. The valves were rearranged to get a desired time sequence. Currently, we have a 2-way solenoid valve (normally closed type) in the vacuum line and a 2-way solenoid valve (normally closed type) in the feed entrance line. At the exit end of the permeator a 3-way solenoid valve is installed one of whose ends is permanently closed. This experimental setup is illustrated in Figure 1. The apparatus was operated under two modes of operation.

Mode 1: Feed was allowed to enter for a certain time through valve 1 (refer to Figure 2) until the required pressure has been attained, keeping both valves 2 and 3 closed. Then valve 1 was also closed like the other valves, i.e., the whole module was isolated for a brief period of time to give an artificial delay for absorption. After that, the valve 3 was opened momentarily to take out the purified gas. Finally, valve 3 was allowed to close and simultaneously valve 2 was opened for desorption. This completed one whole cycle of operation.

Mode 2: Feed was allowed to enter for a certain time through valve 1 until the required pressure has been reached with both valves 2 and 3 being closed. After that valve 1 was closed and simultaneously valve 3 was opened for a short time just to take out the purified front of the mixture of gases. Then it was closed and simultaneously valve 2 was opened for desorption. This completed one whole cycle of operation.

A Typical Experiment

A typical experimental run is described below. The time sequence here refers to the experiment 4-8 in Table 2.

Inlet metering valve was set for a volumetric gas flow rate of 30 cc/min. Under such a condition, feed mixture (CO_2 - N_2) was allowed to enter the permeator through valve 1 for 1 second; during this time valves 2 and 3 were closed. Then valve 1 was closed and simultaneously valve 3 was opened for 9.2 seconds and feed gas mixture was allowed to go all the way to the exit end for absorption and the purified front of it was taken out from the exit and collected in the surge drum. After that, valve 3 was closed and simultaneously valve 2 was opened for 40 seconds for desorption. This constituted one complete cycle of 51.2 seconds. Such cycles were repeated continuously for 3 hours. After 2 hours, purified gas sample from the surge drum was injected into the GC for analysis. The flow rate was controlled by the metering valve after the surge drum. A typical flow rate of 5-10 cc/min was maintained. Gas sample was periodically injected into the GC at an interval of about 5 minutes. The experiment was stopped when no change in gas composition was noticed in five consecutive sample analysis.

Results

As stated earlier, two hollow fiber modules have been used for gas absorption experiments. The characteristics of each modules are listed in Table 1. Both modules became available from a different project.

The time setup for the solenoid valves, the corresponding feed pressure and the mode of operation for different experimental runs have been identified in Table 2. The purification results of each run are also available in Table 3. All experiments were made with a feed gas mixture of 10.12 % CO_2 and balance N_2 , either at 20 or 40 psig feed pressure. The absorbent liquid was pure water. Studies were made to determine the time cycle which would lead to a higher absorption rate and a higher quality product gas. The CO_2 composition in the purified gas varied from 2 - 5% in these studies.

A few observations can be made from these experimental runs. For identical cycle times in a given mode of operation (Expts 4-2 and 4-3), higher feed pressure would result in a lower product quality. A shorter cycle is probably preferable at higher pressure. A very short absorption time (Expts. 4-6 and 4-8) yielded product streams with higher levels of purification.

Note that in all of the above experiments, the desorption time remained constant (40 sec). In the next series of runs, the desorption time will also be varied (reduced). Further experiments will be carried out with CO_2 - water system to determine an optimum cycle time and optimum cycle rate before we proceed to a reactive absorption solution such as aqueous diethanolamine. A product stream of much greater purity should be obtained when such a solution is used.

Table 1: Characteristics of Hollow Fiber Modules

	Module 2	Module 3
Effective Length	39.5 cm	160 cm
No. of Fibers	6000	600*
Fiber ID	100 μm	100 μm
Fiber OD	150 μm	150 μm
Surface Area	11168 cm^2	2262 cm^2
Void Fraction	62.8%	66.5%

* Two identical sets of 300 fibers are available in this permeator in a well mixed condition. Only one set of 300 fibers was used for the experiment.

Table 2: Time Setup for Solenoid Valves

Experiment No.	Module No.	Mode of Operation	Pressure in fiber lumen (psig)	Valve # 1		Valve # 3		Valve # 2	
				Open	Close	Close	Open	Close	Open
4-1	2	1	40	7	74	37	4	41	40
4-2	3	1	40	7	75	37	5	42	40
4-3	3	1	20	7	75	37	5	42	40
4-4	3	2	40	2	44	2	4	6	40
4-5	3	2	40	2	43.6	2	3.6	5.6	40
4-6	3	2	40	1	43.6	1	3.6	4.6	40
4-7	3	2	20	2	49.0	2	9	11	40
4-8	3	2	20	1	49.2	1	9.2	11.2	40

The number under open and close columns referred to time scale in seconds

Table 3: Experimental Results

Experiment No.	Module No.	Mode of Operation	Feed Pressure (psig)	Feed Gas Composition	Purified Gas Composition
4-1	2	1	40	CO ₂ : 10.12% N ₂ : Balance	CO ₂ : 5.00% N ₂ : Balance
4-2	3	1	40	CO ₂ : 10.12% N ₂ : Balance	CO ₂ : 4.50% N ₂ : Balance
4-3	3	1	20	CO ₂ : 10.12% N ₂ : Balance	CO ₂ : 3.50% N ₂ : Balance
4-4	3	2	40	CO ₂ : 10.12% N ₂ : Balance	CO ₂ : 3.52% N ₂ : Balance
4-5	3	2	40	CO ₂ : 10.12% N ₂ : Balance	CO ₂ : 3.20% N ₂ : Balance
4-6	3	2	40	CO ₂ : 10.12% N ₂ : Balance	CO ₂ : 2.22% N ₂ : Balance
4-7	3	2	20	CO ₂ : 10.12% N ₂ : Balance	CO ₂ : 2.69% N ₂ : Balance
4-8	3	2	20	CO ₂ : 10.12% N ₂ : Balance	CO ₂ : 1.99% N ₂ : Balance

Figure 1: Setup for RAPSAB Experiment

Figure 2: Solenoid Valve Locations in RAPSAB Apparatus

END

DATE
FILMED
2 120192

I