210
9.6.83 gme (1) I-11008

Dr. 1726-4
GEND
034

GEND

General Public Utilities • Electric Power Research Institute • U.S. Nuclear Regulatory Commission • U.S. Department of Energy

Gross Decontamination Experiment Report

R. Mason
K. Kinney
J. Dettorre
V. Gilbert

July 1983

Prepared for the
U.S. Department of Energy
Three Mile Island Operations Office
Under DOE Contract No. DE-AC07-76ID01570

DO NOT MICROFILM
THIS PAGE

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

Printed in the United States of America

Available from
National Technical Information Service
U.S. Department of Commerce
5285 Port Royal Road
Springfield, VA 22161
NTIS Price Codes: Printed Copy A99
Microfiche A01

DO NOT MICROFILM
THIS PAGE

DISCLAIMER

This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights. References herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

GEND 034
Distribution Category UC-78
TMI Supplement

GEND--034

DE83 017046

GROSS DECONTAMINATION EXPERIMENT REPORT

R. Mason
K. Kinney
J. Dettorre
V. Gilbert

Published July 1983

Bechtel National, Inc.
Oak Ridge, Tennessee

NOTICE
PORTIONS OF THIS REPORT ARE ILLEGIBLE.
It has been reproduced from the best
available copy to permit the broadest
possible availability.

Prepared for EG&G Idaho, Inc.
and the U.S. Department of Energy
Three Mile Island Operations Office
Under DOE Contract No. DE-AC07-78ID01570

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

ABSTRACT

A Gross Decontamination Experiment was conducted on various levels and surfaces of the TMI - Unit 2 reactor building in March 1982. The polar crane, D-rings, missile shields, refueling canals, refueling bridges, equipment, and elevations 305' and 347'-6" were flushed with low pressure water. Additionally, floor surfaces on elevation 305' and floor surfaces and major pieces of equipment on elevation 347'-6" were sprayed with high pressure water. Selective surfaces were decontaminated with a mechanical scrubber and chemicals. Strippable coating was tested and evaluated on equipment and floor surfaces.

The objectives of the experiment were to evaluate several decontamination techniques and to decontaminate the reactor building surfaces. Both objectives were only partially successful since the objectives were not compatible. The effectiveness, efficiency, and safety of several decontamination techniques were established for the large, complex decontamination effort. Various decontamination equipment was evaluated and its effectiveness was documented. Decontamination training and procedures were documented and evaluated, as were the support systems and organization for the experiment. Information was obtained to facilitate generic decontamination planning, in addition to planning for TMI - Unit 2. Optimum techniques were selected on the basis of the tests for various types of surfaces.

The results of the experiment showed that the gross decontamination of the reactor building, with the proper techniques and water, could obtain the smearable contamination goal. Other techniques with strip-pable coating or with the mechanical scrubber and chemicals would result in smearable contamination levels well below the goal. Radiation dose rates in the best test areas were successfully reduced below the target for practical work area, and for head lift and defueling. Recontamination, other sources, storage, trash, and ineffective tests kept area dose rates in some areas from being reduced by the amount that had been forecasted. The surface deposition boring results indicate that the activity is generally limited to the paint. Airborne particulate activity was reduced during the experiment to the point where the results showed that additional decontamination would reduce the requirement for respirators. Further decontamination activity would reduce the area dose rates if the storage, trash, and waste are removed from the reactor building.

The major recommendations are to continue the decontamination effort in preparation for head lift and defueling, and to make improvements that will increase the effectiveness and efficiency of the decontamination effort.

CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	
Purpose	1-1
Objectives	1-2
Scope of the Experiment	1-2
Experimental Design	1-6
Limitations	1-12
Data Analysis Approach	1-14
2.0 SUMMARY OF RESULTS	
Low Pressure Activity	2-1
General Summary of Low Pressure Flush of Elevation 305'	2-1
General Summary of Low Pressure Flush of the Polar Crane	2-8
General Summary of Low Pressure Flush of the D-Rings, Missile Shields, Canals, Reactor Head Service Structure, and Refueling Bridges	2-14
General Summary of Low Pressure Flush of Elevation 347'-6"	2-23
High Pressure Flush Activity	2-29
General Summary of High Pressure Flush of Elevation 347'-6"	2-29
General Summary of High Pressure Flush of Elevation 305'	2-40
Reflushing of Elevation 305'	2-47
General Summary of Reflushing of Elevation 305'	2-47
Strippable Coating Test	2-49
General Summary of Results	2-49
Mechanical Scrubber Test	2-57
General Summary of the Task	2-57

CONTENTS (Continued)

	<u>Page</u>
Combinations of Decontamination Techniques	2-63
General Summary of Combinations of Decontamination Techniques	2-63
Summary	2-68
Decontamination Technique Summary	2-68
General Summary of Low Pressure Technique	2-68
General Summary of High Pressure Technique	2-68
Mechanical Scrubber	2-69
Strippable Coatings	2-69
Summary	2-70
Decontamination Training Program	2-70
Relationship of Training to Entry Planning	2-70
Training Criteria and Effectiveness	2-72
Summary of Training and Safety	2-74
Contamination Control and Recontamination	2-78
Contamination Control	2-78
Recontamination	2-80
Summary of the Problems	2-82
Organizations and Special Support Systems	2-83
Organizations	2-83
Special Support Systems and Equipment	2-85
Reactor Building Radiation Levels and Environment	2-88
Intensity Maps	2-88
Comparison of Gamma Spectrometer Results with Radiological Results	2-88
Reactor Building Environment: Analysis of Water Quality, Biological Activity, and Airborne Activity	2-90
Surface Deposition	2-96
Loose Particulate Contamination	2-98

CONTENTS (Continued)

	<u>Page</u>
3.0 CONCLUSIONS	
Decontamination Experiment Effectiveness	3-1
Decontamination Effectiveness	3-2
Decontamination Techniques	3-5
Decontamination Control and Surveillance	3-6
Support Systems and Organization	3-8
Decontamination Training	3-11
Decontamination Criteria	3-13
Gross Decontamination Goals and Criteria	3-13
Conclusion Summary	3-17
4.0 RECOMMENDATIONS	
Additional Testing	4-1
Decontamination Techniques	4-2
Other Recommendations	4-2
Additional Decontamination	4-2
5.0 REFERENCES	5-1

APPENDICES

A	SURFACE DEPOSITION
B	EQUIPMENT
C	RAW DATA
D	TRAINING AND SAFETY
E	ORGANIZATION AND SUPPORT
F	PHOTOGRAPHS AND VIDEOTAPE RECORDINGS OF THE DECONTAMINATION EXPERIMENT
G	VIDEOTAPE AND WORK PACKAGE LISTING
H	EXPERIMENTAL DESIGN AND METHODOLOGY
I	GAMMA SPECTROMETER RESULTS

TABLES

2-1	Elevation 305' Low Pressure Flush - Summary of Worker Radiation Exposure
2-2	Summary of Results of Low Pressure Flush of Elevation 305'
2-3	Elevation 305' Low Pressure Flush

TABLES (Continued)

2-4	Polar Crane Low Pressure Flush - Summary of Worker Exposure
2-5	Summary of Low Pressure Flushing of Polar Crane
2-6	Water Use for Polar Crane and Dome
2-7	Contamination Levels of D-Rings, Refueling Canal, and Fuel Handling Bridge
2-8	D-Rings, Refueling Canal, Missile Shields, and Fuel Handling Bridge Water Rates
2-9	D-Rings, Missile Shields, and Refueling Equipment - Summary of Worker Exposure
2-10	Summary of Results of D-Ring Walls, Canals, and Fuel Handling Bridge
2-11	Median Contact Radiation Reduction (differences in pre-test and post-test values)
2-12	Elevation 347'-6" Low Pressure Flush - Summary of Worker Exposure
2-13	Elevation 347'-6" Low Pressure Flush
2-14	Contamination Levels of Elevation 347'-6"
2-15	Elevation 347'-6" High Pressure Flush Water Use
2-16	Elevation 347'-6" Equipment High Pressure Flush Water Use
2-17	Elevation 347'-6" High Pressure Flush - Summary of Worker Exposure
2-18	Summary of Results of Elevation 347'-6" Floor High Pressure Flush
2-19	Summary of Results of Elevation 347'-6" Equipment High Pressure Flush
2-20	Elevation 305' High Pressure Flush Water Use
2-21	Summary of Results of Elevation 305' High Pressure Flush
2-22	Summary of Reflushing Radiation and Contamination Data of Elevation 305'
2-23	Strippable Coating Test - Elevation 305' Floor and Elevation 347'-6" Head Storage Stand
2-24	Elevation 305' Area ISC and Elevation 347'-6" Equipment - Strippable Coating Test Parameters
2-25	Summary of Results of Elevation 305' Area ISC
2-26	Mechanical Scrubber Test - Elevation 347'-6"
2-27	Summary of Results of Mechanical Scrubber Test
2-28	Summary of Results - Elevation 305' Low Pressure, High Pressure, and Strip Coating Tests
2-29	Summary of Results - Elevation 347'-6" Low and High Pressure Flush of Concrete Floors and Diamond Plate
2-30	Summary of Results - Elevation 347'-6" Low and High Pressure Flush on Concrete Floors

TABLES (Continued)

2-31	Summary of Various Test Results
2-32	Man-Hour and Material Costs for Support
2-33	Gross Decontamination Test Water Quality
2-34	Radionuclide Concentrations in Decontamination Water
2-35	Airborne Data Summary

FIGURES

1-1	Data Acquisition Program for Gross Decontamination Experiment
1-2	Gross Decontamination Data Acquisition Tasks
1-3	Gross Decontamination Experiment Summary
2-1	Elevation 305' Low Pressure Flush - Planned
2-2	Elevation 305' Low Pressure Flush - Actual
2-3	Data Acquisition Survey Locations - Elevation 305' Low Pressure, High Pressure, and Strippable Coating Tests
2-4	Low Pressure Flush of Polar Crane
2-5	Diagram of Dome Area/Polar Crane - Data Acquisition Locations
2-6	Diagram of Polar Crane - Data Acquisition Locations
2-7	Data Acquisition Locations - Elevation 347'-6" D-Rings and Missile Shield Areas
2-8	Data Acquisition Locations - Refueling Canal and Service Structure
2-9	Data Acquisition Locations - Fuel Handling Bridge
2-10	Elevation 347'-6" Low Pressure Flush - Planned
2-11	Elevation 347'-6" Low Pressure Flush - Actual
2-12	Elevation 347'-6" Planned Data Acquisition Locations - Low Pressure and High Pressure Flush
2-13	Elevation 347'-6" High Pressure Flush - Planned
2-14	Elevation 347'-6" High Pressure Flush - Actual
2-15	Elevation 305' High Pressure Flush - Planned
2-16	Elevation 305' High Pressure Flush - Actual
2-17	Mechanical Floor Scrubber Area - Elevation 347'-6"
2-18	Plot of Total Man-Hours per Hour in Containment Versus Time
2-19	Plot of Man-Hours Expended Versus Time
2-20	Elevation 305' Radiation Intensity Map
2-21	Elevation 347'-6" Radiation Intensity Map
3-1	Plot of Decontamination Factor (based on contact measurements) Versus Water Rate
3-2	Decontamination Logic Diagram

DO NOT MICROFILM
THIS PAGE

GROSS DECONTAMINATION EXPERIMENT REPORT

1.0 INTRODUCTION

The Department of Energy (DOE) proposed in July 1981 that a Gross Decontamination Experiment should be performed within the reactor building of TMI - Unit 2. The proposed scope of work was modified over the next several months, and an agreement was reached with General Public Utilities (GPU) on the content of the experiment in October 1981, with a proposed start date in November 1981.

Nuclear Regulatory Commission (NRC) approval of the experiment, which was expected in November, was delayed while GPU prepared responses to questions posed by the NRC. Also, engineering and installation of support equipment needed for the experiment were not completed within the scheduled November-December time frame. As a result, the experiment was rescheduled in late January 1982, with low pressure flushing of the reactor building to begin in early March 1982.

Although some minor deviations were encountered early in the course of the experiment, it was successfully completed in March 1982.

Purpose

The purpose of the Gross Decontamination Experiment was to provide the nuclear industry with the fullest possible access to applicable engineering and operational experience that can be gained from decontamination of the reactor building of TMI - Unit 2, and to document the following activities:

- o Gross decontamination effectiveness
- o Decontamination criteria

- o Decontamination techniques and equipment.
- o Decontamination training and procedures
- o Radiation monitoring and mapping
- o Support systems and organization.

Objectives

The objectives of the Gross Decontamination Experiment were to:

- o Evaluate the safety, effectiveness, and efficiency of various methods and equipment for performing gross decontamination of large, complex, contaminated surfaces within the reactor building. Support systems and organization for such a large decontamination effort were also to be evaluated.
- o Reduce the contamination present on selected surfaces within the reactor building in a manner consistent with ALARA (as low as is reasonably achievable) principles for personnel radiation exposure management.

During the course of the experiment, a later objective increased the importance of the decontamination aspect. However, during final preparation for and actual conduct of the experiment, decontamination became the focus of the work.

Scope of the Experiment

The scope of the Gross Decontamination Experiment changed several times during the planning and execution phases. During the planning phase, some decontamination test areas were deleted from the scope due to budgetary and

time constraints. After the experiment was begun, several of the deleted test areas were reinstated, and some data acquisitions tasks were deleted.

In the final planning phase, the scope of work included testing various decontamination techniques on major equipment, stairs, floor surfaces on elevations 305' and 347'-6", polar crane, refueling canal, bridges, D-rings, and missile shields. The sample (data acquisition) and work packages were structured to provide data on decontamination techniques, and to provide information necessary to evaluate the systems and organizational aspects of the effort.

Other work performed in support of the experiment included:

- o Installation of a polar crane access system ("Spider shafter" system) on elevation 305' with provisions to off-load personnel and equipment at elevation 347'-6".
- o Installation of additional services: decontamination water (rated at 10,000 psig) and 480 V ac power (100 psi service air is currently available through R 561).
- o Acquisition of data associated with the experiment - radiological surveys, including use of a gamma spectrometer, pictures, videotapes, etc.
- o Decontamination of the enclosed stairwell, using low pressure and high pressure water, if access to elevation 347'-6" via the Spider shafter is not accomplished.
- o Use of strippable coatings on the elevation 305' floor and equipment on elevation 347'-6", regardless of Spider status. The test area is approximately 700 square feet.

The relationship between the Gross Decontamination Experiment and the Gross Decontamination Technical Plan (TPO/TMI-007) is that the experiment encompassed the first 13 steps of the plan, with the exception of:

- o Installing the enclosure from personnel air lock No. 2 to enclosed stairwell No. 2
- o Installing an enclosure area around the stairwell No. 2 door and elevation 347'-6"
- o Sealing off elevation 347'-6"
- o Sealing off elevation 305'

Figure 1-1 shows the planned and actual sequence of steps for the experiment. The steps deleted from the Gross Decontamination Technical Plan were not performed because they were judged to be man-hour and man-rem intensive and because they would not contribute to general area dose reduction. No attempts, other than sequencing considerations and operational precautions, were made to prevent recontamination during the experiment. In addition, chemicals were used in small areas where they could be controlled and removed as separate waste. This prevented any impact of the chemicals on the submerged demineralizer system (SDS), which processes the water out of elevation 282'-6".

Prior to the experiment, various necessary equipment and items were installed in the reactor building. Processed water with a flow rate of up to 25 gallons per minute (gpm) and up to 180 F was provided to the building. Electrical power was provided for the spider and for elevation 305', because most of the circuits for that level were on elevation 282'-6", which had been under water.

A Spider lift access platform was installed on elevation 347'-6" and on the polar crane; to provide access to the crane. A new radio system was

installed with new antennas, a duplex base station, throat microphones, and stethoscope-type earphones.

The equipment that was brought into the containment consisted of:

- o High reach platform - Model S15E
- o Forklift
- o Lifting device to move heavy items between elevations 305' and 347'-6".

Decontamination techniques used during the Decontamination Experiment were demonstrated in either the auxiliary building or the reactor building, with the exception of the high pressure water floor scrubber. The basic technique was a water flush at pressures varying from 60 psig to 6000 psig, and at temperatures ranging from ambient to 140 F at the output of the penetration. The floor rates varied from 5 to 25 gpm. The major techniques tested were:

- o High pressure (HP) flush - Water lances directed manually were used to apply water at pressures between 2000 and 6000 psig. The actual pressure was the maximum that can be used without destroying the integrity of protective coatings. The water temperature did vary; however, the maximum at the pump was based on the design of the pump seals. The temperature was expected to be a maximum of 140 F. The actual application temperature did vary with heat losses through hoses.
- o Low pressure (LP) flush - Water lances directed manually were to be used to apply water at temperatures between ambient and 140 F at the inlet to the pump, at flow rates of approximately 25 gpm. Actual temperatures and pressures were to be dependent on line losses from the pump to the nozzle.

- o Spin jet - High pressure water was to be applied through a series of rotating nozzles. Application consists of pushing this device across the floor, which had the advantages of consistent application and a faster decontamination rate. The water floor scrubber required 230 V ac power. Pressures from 2000 to 6000 psig and flow rates from 5 to 25 gpm were to be used.
- o Strippable coatings - Strippable coatings were to be used to decontaminate the exposed concrete surfaces in the enclosed stairwell. The test area was to be approximately 350 square feet.
- o A mechanical scrubbing device was to be used on a small test area (150 square feet).
- o Wet vacuums were to be used to reduce squeegee operations and problems.
- o Evaluation of other equipment will continue throughout the test, and some substitution of equipment may occur.

Experimental Design

In planning for the execution of this experiment, a systematic approach was taken to selection of sampling locations, data collection standards, and test sequences. Details of the experimental design are contained in Appendix H.

Sampling locations were selected to provide a minimally representative data base for evaluation of the results produced by various decontamination techniques. Additionally, sufficient redundancy was included to permit evaluation of data precision, biases, reproducibility, etc.

Data collection standards were established to provide consistency in instrument usage or swipe (smears) collection. In all cases, sample points were permanently marked to ensure accurate relocation of data acquisition points.

The data collection and work sequence (see Figure 1-2) was established to provide an orderly and systematic approach to obtaining comprehensive results without recontamination or loss of data. The sequence was:

- o Task No. 1 - Elevation 305'

- Initial data collection and misting

- Low pressure flush of overheads

- Low pressure flush of major equipment

- Low pressure flush of wall and floor surfaces

- o Task No. 2

- Stairwell shielding

- Flush stairwell No. 2 concrete block wall

- o Task No. 3 - Polar Crane

- Data collection and misting

- Low pressure flush of polar crane and dome area

- High pressure spray of polar crane and dome area

o Task No. 4

Initial data collection

Mist and flush top of D-rings, missile shields, and open stairwell

Initial data collection - elevation 347'-6"

Mist elevation 347'-6"

Low pressure flush of elevation 347'-6" major equipment

Low pressure flush of elevation 347'-6" wall and floor surfaces

High pressure spray of elevation 347'-6" major equipment

High pressure spray of elevation 347'-6" major surfaces

Strippable coating test on reactor vessel head storage stand

Mechanical floor scrubber test on elevation 347'-6"

Wet abrasive spray on wall and floor surfaces on elevation 347'-6"

o Task No. 5

Initial data collection and mist of refueling canal area and equipment

Low pressure flush of major equipment over refueling canal and reactor head service structure

Low pressure flush of refueling canal wall and floor surfaces

- o Task No. 6

Data collection and mist of elevation 305' prior to high pressure spray

High pressure spray of elevation 305' major surfaces

Strippable coating test on elevation 305' floor surfaces

The initial changes to the scope of the experiment deleted the following items:

- o Task No. 1 - Flush of walls, overheads, and major equipment
- o Task No. 2 - Entire task
- o Task No. 3 - Low pressure spray of dome; high pressure spray of polar crane and dome
- o Task No. 4 - Low pressure flush of elevation 347'-6" wall surfaces; wet abrasive spray of wall and floor surfaces.
- o Task No. 5 - No change
- o Task No. 6 - High pressure spray of elevation 305' walls and equipment surfaces

Based on the approved scope of work, work packages were developed to implement the tasks and data acquisition packages contained within the tasks. This resulted in the following breakdown and sequence of tasks and work packages for the experiment:

- o Work Package 47^a (Task 1)

- All initial data acquisition for Work Packages 47, 53, 49, and 50

- Mist elevation 305'

- Low pressure flush of elevation 305'

- Post-low pressure flush data acquisition

- o Work Package 53 (Task 3)

- Mist of polar crane

- Low pressure flush of polar crane

- Post-low pressure flush data acquisition

- Data acquisition on elevation 347'-6" D-rings, missile shields, refueling canal, and reactor service structure

- o Work Package 49 (Tasks 4 and 5)

- Low pressure mist and flush missile shields, D-rings, reactor head service structure, refueling bridges, and refueling canal

- Post-low pressure flush data acquisition

a. The work package numbers do not have a numerical sequence significance but are representative of the task, i.e., Work Package 50 - low pressure flush of elevation 347'-6".

- o Work Package 50 (Task 4)

- Low pressure mist and flush of elevation 347'-6"

- Post-low pressure flush data acquisition

- o Work Package 51 (Task 4)

- High pressure flush of elevation 347'-6" major equipment and floor

- Post-high pressure flush data acquisition

- o Work Package 52 (Task 6)

- High pressure mist and flush of elevation 305'

- Post-high pressure flush data acquisition

- o Work Package 54 (Task 4)

- Strippable coating test on elevation 347'-6"

- o Work Package 81 (Task 6)

- Strippable coating test on elevation 305'

- o Work Package 80 (Task 4)

- Mechanical scrubber test on elevation 347'-6"

After the experiment was in progress, the following items previously deleted from the scope of work were reinstated:

- o Overheads, walls, and major equipment on elevation 305'
- o Mechanical scrubber test - chemicals
- o Low pressure flush of the dome

The following items were deleted:

- o Post-low pressure data acquisition of the polar crane flush on elevation 347'-6", missile shields, canals, and bridges
- o Post-low pressure flush data acquisition on elevation 347'-6"
- o Proper sequence of low pressure flush on elevation 305'

Figure 1-3 reflects the sequence and work package accomplishment for the experiment.

Limitations

The deletion of the interim data bases, which had been established to provide separate data on low and high pressure flushing, limited the ability to determine the effectiveness of some of the low, high, and combination pressure flush tests.

After the initial radiation readings and samples were collected on the lower elevations, canals, missile shields, and refueling bridges, additional debris and contamination were deposited from the polar crane flushing on these areas. The low pressure test of these areas, then, did not have valid pre-test data.

On elevation 305', the floor was flushed first, post-test data were taken, and then the overheads, walls, and floor were flushed. The change in sequence did not provide a good baseline for determining elevation 305' high pressure spraying effectiveness. However, based on data acquisition from other test areas on elevation 305', some estimates of technique effectiveness can be made.

Video recordings of the experiment allowed examination of the data acquisition techniques and the low pressure, high pressure, and combination tests. As a result, the recordings allowed the tests to be reviewed and a determination to be made on the success, failure, recontamination, and problems that did affect the results of the experiment.

Where operational circumstances invalidated some test data readings, the invalid data were removed prior to the evaluation of the various decontamination techniques.

The low pressure flushing of the enclosed stairwell was designed to provide information on:

- o Changes in airborne activity due to flushing operations
- o Effectiveness of decontaminating concrete block wall surfaces
- o Contamination control resulting from application of a coating to the open concrete block
- o The effectiveness in dose reduction and ease of installation of several different coatings.

This task was deleted from the scope of work. As a result, information was not provided during the experiment or in other tasks on decontamination of concrete block wall surfaces, contamination control with several different coatings, and water bladder shielding.

Data Analysis Approach

Analysis of the data acquired from the Gross Decontamination Experiment could be performed only by employing a "valid data" selection process. This approach employed a careful evaluation of the impact of operational parameters upon the validity of the data. As an example, a study of the videotapes of operations revealed that water control operators directed water over areas already decontaminated, or a worker walked through loose debris and tracked it to areas already cleaned. Sample points affected by such events were not used in results, since their validity was lost or questionable. Clearly, this reduced the data available for analysis, but served to eliminate many of the inconsistencies produced by inclusion of all data acquired.

After removal of invalid data, the analyses were done for each planned area within the reactor building and technique used (either singly or in combination). Pre- and post-test results were evaluated for each valid sampling point in a pair-wise fashion. The net result of this approach was a significant reduction in sample variances within groups, which provides the opportunity for more straightforward analyses of the data sets.

To analyze the data, the following scheme was employed:

- o Area gamma dose rate reductions were calculated by obtaining the difference between pre-test and post-test gamma radiation measurements.
- o Decontamination factors were calculated from contact gamma and beta results. To do this, the difference between pre-test and post-test contact gamma values was obtained. This was connected to micro-curries/cm² ($\mu\text{Ci}/\text{cm}^2$) by using the rationale contained in Reference 2.

Similarly, post-test beta values were converted to $\mu\text{Ci}/\text{cm}^2$ by the rationale contained in Reference 2. This provided an estimate of the areal density of the contaminants remaining on the surface after

treatment. The decontamination factor (DF) was then calculated from the following equation:

$$DF = \frac{Ci(P) + Ci(F)}{Ci(F)}$$

where $Ci(P) = \mu Ci/cm^2$ calculated from pre-test contact gamma measurement

$Ci(F) = \mu Ci/cm^2$ calculated from post-test contact beta values.

This method was used to analyze data obtained from the Large-Scale Decontamination Test conducted in 1981 (Reference 3). Although valid issues can be raised regarding this calculational method, it does provide a basis for comparison of results. It does not, however, provide absolute values for areal concentrations of contaminants. Gamma spectroscopy, deposition sample analyses, and the experiment data permit an evaluation of the relationship between areal concentrations, as used here, and the actual number of $\mu Ci/cm^2$ as determined by quantitative analyses. In addition, the decontamination factors may be compared between the different technique analyses.

- o To determine decontamination factors from swipe data merely requires a calculation of the ratio of pre-test to post-test swipe results. In these analyses, total cesium ratios were used. Thus:

$$DF = \frac{\text{Pre-test dpm/100 cm}^2 \text{ (Cs)}}{\text{Post-test dpm/100 cm}^2 \text{ (Cs)}}$$

- o To establish other parameters, e.g., gallons/square feet, square feet/min, etc., required a careful analysis of the videotapes to establish times for specific operations and areas involved. Derived parameters were then obtained from observed variables such as water flow rate (gpm), total water usage, and pump power cycles, in appropriate combination with data obtained from videotapes.

Figure 1-1. Data acquisition program for gross decontamination experiment.

Task No. 1

Data Collected

- A Airborne activity monitoring
- RC Radiation surveys (contact)
- RA Radiation surveys (area)
- S Swipe samples
- G Gamma spectrometer survey
- P Photographs
- V Videotape
- X Not accomplished

Figure 1-2. Gross decontamination data acquisition tasks.

Task No. 2

Figure 1-2. (Continued)

Task No. 3 . .

Figure 1-2. (Continued)

Task No. 4

(Contingency)

Figure 1-2. (Continued)

Task No. 5

Figure 1-2. (Continued)

Task No. 6

Figure 1-2. (Continued)

Figure 1-3. Gross decontamination experiment summary.

DO NOT MICROFILM
THIS PAGE.

2.0 SUMMARY OF RESULTS

Low Pressure Activity

General Summary of Low Pressure Flush of Elevation 305'

Technique Description. The low pressure flush of elevation 305' was designed to:

- o Conduct a second decontamination test on the surfaces that were previously decontaminated during the large-scale decontamination test.
- o Determine the effectiveness of decontaminating overhead surfaces, the equipment required for overhead decontamination, and flushing at different angles.
- o Determine the airborne activity created by this type of flushing and determine worker clothing requirements.
- o Determine the effectiveness of hot water flushing using various application techniques.
- o Decontaminate various types of surfaces found within the building, i.e., floors, walls, piping, cables, cable trays, and platforms.
- o Determine the advantage of misting surfaces prior to flushing.
- o Evaluate the sequence of operations, i.e., mist, flush overheads, flush major equipment, flush walls, and flush floors.

The low pressure flush was conducted in stages on elevation 305' because the scope of work was changed during the experiment. As a result, the work sequence was:

- o Mist
- o Floor
- o Overheads
- o Major equipment
- o Walls
- o Floor
- o Reflush floor.

Smearable Contamination Levels. The amount of contamination at the beginning of the low pressure flush of elevation 305' ranged from mid- 10^6 dpm/100 cm² to mid- 10^7 dpm/100 cm² of Cs-137. The pre-test average was 1.1×10^7 dpm/100 cm² of Cs-137. After the experiment, the readings ranged from 10^5 dpm/100 cm² to 10^6 dpm/100 cm², and averaged 4.1×10^6 dpm/100 cm² of Cs-137. The average reduction in smearable contamination was 63 percent. The Cs-137 to Sr-90 ratio remained constant during the test.

Degree of Uncertainty - Decontamination Effectiveness. Before and after misting and the first flush of the floor, data were acquired on floor and piping surfaces. Data were not taken on overheads or vertical surfaces, so no determination of technique effectiveness could be made for these areas. Visual observation of the experiment indicated that a significant amount of dirt and debris was flushed from the overheads and major equipment surfaces.

Hot water was tested during some flush operations on elevation 305' although the intended temperature was not reached because of problems with the heater. For a short time, a high temperature of 155 F was recorded, but throughout most of the experiment the water temperature averaged 112 F.

Decontaminating the overheads, equipment, and wall surfaces created some recontamination during the experiment because water and debris dripped onto the clean floor surfaces.

Waste Volume. The volume of waste generated during the test was less than had been expected because the worker rate was higher than projected and the water rate was lower. The total volume of water used for the experiment was 3300 gallons.

Results - Expected Versus Actual. The low pressure flushing results for areas of higher contamination were as expected or exceeded expectations. It appeared that area gamma radiation could be reduced by 50 percent, and the decontamination factor (DF) was greater than 10 for smearable contamination. For areas with lower radiation and contamination, a different technique than was used in the experiment may be appropriate because these areas were not as affected by the low pressure flush.

Equipment and Techniques. New techniques and equipment were developed for the test. In general, equipment provided by the manufacturer was not as rugged, reliable, or effective as desired for the harsh environment of the experiment. See Appendix B for equipment problems.

Worker Radiation Exposure. The worker exposure during the low pressure flush test, including data acquisition, misting, and flushing, was 9.813 man-rem. Table 2-1 shows the worker exposure for each task.

TABLE 2-1. ELEVATION 305' LOW PRESSURE FLUSH - SUMMARY OF
WORKER RADIATION EXPOSURE

<u>Task</u>	<u>Man-hours</u>	<u>Man-rem</u>
Pre-test data acquisition	3.19	1.016
Floor	4.55	3.005
Overheads, walls, floor	5.0	2.633
Stairs	1.05	1.831
Reflush	0.55	0.852
Post-test data acquisition	1.34	0.431

Safety. Safety was stressed during all phases of the low pressure flush activity, and no significant safety problems occurred during the test.

Worker Productivity. Worker productivity was hampered during the experiment by protective clothing requirements. Clothing included two sets of protective coveralls, full wet suits with hoods, and several sets of glasses and boots. Heat stress, rather than dose rate, was the limiting factor for time spent in-containment. The use of ice vests under the protective clothing (PC) increased the amount of time; the in-containment time limit was established at a maximum of 2½ hours, or 1 hour after the ice melted.

During training, each individual was tested to determine how long he could correctly operate the lance used for flushing at various pressures. Because of limited physical endurance exhibited by many of the workers, the time that they could flush was short. As a result, an optimum time limit was established for each crew that would not excessively tire the workers.

Summary of Specific Results. In general, the results of the low pressure flush test showed that contamination was reduced in all areas.

Low Pressure Flush Parameters--The results of the low pressure flush test on elevation 305' are shown in Table 2-2. Three crews of three members each misted and flushed for a total of 91 minutes (11 minutes misting, 80 minutes flushing). Approximately 1100 gallons of water were used during the test; 4405 square feet were covered per hour. The planned and actual test parameters and the data sample points are shown in Figures 2-1, 2-2, and 2.3.

Visual Results--The visual observations of the low pressure flush on elevation 305' showed that a great amount of dirt and debris was moved with the water. Flush crews reported that hot water produced better visual results; however, the data did not indicate more contamination reduction. The flush nozzle produced striping on the floor and diamond plate in heavy dirt (see Photograph 1). The low pressure flush did not move this "semi-fixed" debris observed on the diamond plate and other sections of the floor. Photograph 2 illustrates the high effectiveness of the flushing activities for removing dirt and debris from the stainless steel surfaces.

Radiation Changes--The low pressure flush produced area dose reductions ranging from 14 percent to 37 percent, as shown in Table 2-2.

Relative decontamination factors (RDFs) based on contact readings varied from 6.9 to 75.6 for floors, and to 124 for stainless steel. Area radiation readings showed dose reductions. However, Area II LP appeared to have some other sources (air coolers, core flood tank piping, stairwells) contributing to the area dose rate, since the contamination reduction should have produced a larger dose rate reduction.

TABLE 2-2. SUMMARY OF RESULTS OF LOW PRESSURE FLUSH OF ELEVATION 305'

Low Pressure Area	Surface	Area Dose Reduction ^a	RDF (contact)	Swipes Total Cesium (dpm/100 cm ²)		Water Use (gal/ft ²)
				Final	DF	
I 20 gpm Ambient ~70 F	Floor Stainless steel	37% -	75.6 124	4.62 x 10 ⁶ 4.17 x 10 ⁵	1.1 -	0.24
II 23 gpm 118 F	Floor Stainless steel	14% -	6.9 -	4.71 x 10 ⁵ 3.35 x 10 ⁵	42.0 18.9	0.144
III 23 gpm 96 F	Floor	33%	65.5	6.09 x 10 ⁶	2.8	0.22
IV 17 gpm 110 F	Floor	27%	28.0	8.19 x 10 ⁶	2.4	0.20

a. Area dose reduction = $\frac{\text{average pre-test area gamma} - \text{average post-test area gamma}}{\text{average pre-test area gamma}}$

Contamination and Recontamination--The contamination on the various test areas on elevation 305' was reduced and results varied in swipe DFs from 1.1 to 42 for floor surfaces. The best results recorded in total cesium were in Area II LP, with 4.7×10^5 dpm/100 cm². Recontamination of sample point 23 occurred when crews walked over the spot continuously during entering and leaving the air lock to change air samples and shifts. Recontamination was also observed during the flushing effort when the lance water stream splattered from spraying angle iron support braces and equipment stands at close range.

Effectiveness of the Different Low Pressure Flush Techniques--The effectiveness between 17 and 22 gpm did not appear to change during the test. If the water volume was too large for wet vacuum, the lower end of the flow rate range would be satisfactory.

Efficiency of the Low Pressure Techniques--The largest water use per square foot produced the highest contact DFs in the test areas. See Tables 2-2 and 2-3 for the specific results.

TABLE 2-3. ELEVATION 305' LOW PRESSURE FLUSH

<u>Test Area</u>	<u>Area (ft²)</u>	<u>Water Used (gal)</u>	<u>Water Use (gal/ft²)</u>
I	944	229	0.24
II	4427	652	0.14
III	532	120	0.23
IV	469	96	0.20
Overheads	23,174	1442	0.06

General Summary of Low Pressure Flush of the Polar Crane

Technique Description. The low pressure flush of the polar crane was designed to:

- o Determine airborne activity level changes as a result of misting the polar crane, dome area, LOCA ducts, and horizontal crane surfaces.
- o Determine the decontamination effectiveness of low pressure flushing on crane equipment and surfaces with various pressures and water temperatures.
- o Decontaminate the polar crane, dome area, crane rails, girders, surface, and equipment.
- o Determine the efficiency of the polar crane decontamination tests.

The polar crane low pressure flush was conducted during several entries. Not all of the pre-test data were acquired during the specified entry due to entry operational problems, and another entry had to be rescheduled. During the second entry, about 80 percent of the data collection requirements were completed. Flushing and misting of the crane were accomplished during two entries. The first entry occurred late in the day after the elevation 305' low pressure flush. As a result, misting of the crane and some flushing of the dome were accomplished before the end of the workday. During the second entry the crane was flushed, completing the low pressure test. The post-test data acquisition task was attempted during three entries that started approximately 3 weeks after the crane flush. The post-test data acquisition requirements were not completed, and recontamination of several of the crane surfaces occurred during crane recovery tasks before partial (50 percent) post-test data acquisition was accomplished. See Figures 2-4, 2-5, and 2-6 for diagrams of the polar crane and dome area test parameters and data acquisition locations.

Smearable Contamination Levels. The degree of smearable contamination at the beginning of the task varied from 1.1×10^7 dpm/100 cm² to 2.9×10^4 dpm/100 cm² of Cs-137 on horizontal surfaces, and from 6.2×10^6 dpm/100 cm² to 2.7×10^4 dpm/100 cm² of Cs-137 on vertical surfaces. Post-test results, where available, showed decontamination on vertical surfaces but recontamination on horizontal surfaces. Post-test horizontal surface contamination was in the same range as the pre-test data, and post-test vertical surfaces indicated swipe DFs from 2.55 to 1.72. See Appendix C for the raw data.

Degree of Uncertainty - Decontamination Effectiveness. Assessment of the decontamination effectiveness is uncertain for two reasons: (a) the data acquisition was insufficient and not timely to accurately record the results; (b) the crane surfaces were recontaminated by personnel traffic on the surfaces and by operational problems during the decontamination effort.

Waste Volume. Several problems with the rate of application and pressure for flushing activity on the crane reduced the amount of waste expected. The flush teams had problems with footing, flush pressure, and items to secure to; thereby reducing flush time from the total time available for the task.

Results - Expected Versus Actual. The test did not achieve the test objectives. The main reasons the task was not successfully completed were as follows:

- o The task did not have sufficient reserve manpower qualified for crane work.
- o The task was hurried to try to accomplish the test within a time frame that was imposed by remote reporter work schedules at TMI.
- o Decontamination and other tasks were given priority over data acquisition and test parameters.

The crew members that attempted the task were the best trained of all the decontamination crews. However, they were not allowed to function to their capacity due to safety restrictions on their stay time on the crane (i.e., heat stress and safety line hookup rules).

Equipment and Techniques. The polar crane was decontaminated by standard low pressure flushing with a hydrolance. No new techniques were used or developed for the task.

Worker Radiation Exposure. The worker exposure for the low pressure flushing of the crane was high compared to the surface area and task performed. Multiple entries to accomplish this task resulted in higher exposures. The breakdown for the task is shown in Table 2-4. The actual man-rem associated with misting and flushing time averaged 310 mrem per individual.

TABLE 2-4. POLAR CRANE LOW PRESSURE FLUSH - SUMMARY OF WORKER EXPOSURE

<u>Task</u>	<u>Man-hours</u>	<u>Man-rem</u>
Pre-test data	11.56	1.350
Misting - flushing	16.69	2.027
Post-test data	<u>10.37</u>	<u>1.202</u>
Total	38.62	4.779

Safety. Safety considerations were a major reason that this task required a much longer time than expected from training. Conservatism in safety rules applied to the crane task limited the time available for the work, and added

personnel requirements and equipment. The task was accomplished safely; however, the results were impacted where the safety requirements increased the work time beyond that which was available for the task. There did not appear to be a method to moderate the safety versus risk assessment of the task until a later time in the experiment.

Worker Productivity. Three more entries were required for this task than had been planned. The worker productivity for this task was limited by the concern for heat stress, which had occurred during previous crane tasks. This limited individuals' total work time. Equipment problems and insufficient reserve manpower for the task did not allow efficient rotation of personnel throughout the task. During planning for data acquisition, the total task time required for pre- and post-test data acquisition was underestimated. Data acquisition needs contributed to the need for additional entries as much as personnel factors. GPU linemen, rad-con technicians, and contractor electricians were used for this task. The GPU linemen were the best trained and appeared to be in the best physical condition of all the personnel in the experiment. However, other GPU commitments did not allow them to return for additional entries. Since GPU personnel could not be teamed with contractor personnel due to union rules, the task was limited to available personnel.

Summary of Specific Results. The decontamination results of the low pressure flushing task of the polar crane were disappointing and not indicative of what can be accomplished by low pressure flushing on equipment and surfaces. However, the results were also revealing concerning safe, effective, and efficient decontamination of a large, complex reactor building.

Low Pressure Flush Parameters--The results of the polar crane task are shown in Tables 2-5 and 2-6. Two crews of four (three flush crew members and a rad-con technician) were used in the misting and flushing operations.

TABLE 2-5. SUMMARY OF LOW PRESSURE FLUSHING OF POLAR CRANE

<u>Area</u>	<u>RDF</u> <u>(contact)</u>	<u>Swipes</u> <u>Total Cesium</u> <u>(dpm/100 cm²)</u>		<u>Water</u> <u>Use</u> <u>(gal/ft²)</u>
		<u>Final</u>	<u>DF</u>	
Polar Crane	<1 ^a	4.34 x 10 ⁶	1.95	0.092

a. Indicates activity was added.

TABLE 2-6. WATER USE FOR POLAR CRANE AND DOME

<u>Area</u>	<u>Water Used</u> <u>in Gallons</u>	<u>Water Use</u> <u>(gal/ft²)</u>
Polar Crane:		
11,614 sq. ft.	1071.3	0.09
Dome: 15,816 sq. ft.		
(estimated)	<u>~300</u>	<u>--</u>
Total	1371.3	

During the 1 hour and 27 minutes required for the task, 1375 gallons of water were used to mist and flush the dome and polar crane. The dome and crane area was approximately 27,000 square feet; for comparison, the elevation 305' area is approximately 25 percent of that area. Similarly, the amount of water and time per square foot was vastly different between the elevation 305' and crane areas, as the results indicate.

Visual Results--Visual results observed by the flush crews were that the flushing did a good job of removing dirt and debris from the crane and dome areas. Observation from the closed circuit televisions (CCTV) revealed considerable dirt, debris, and paint chips from the dome falling to the lower levels. However, actual flushing operations could not be observed because of the location of the TV cameras. Photographs 3 through 7 show the pre-test conditions of the crane and the work areas for the crews. Post-test photographs were not taken, as these were part of the deleted data acquisition tasks.

Radiation Changes--Area pre- and post-test radiation measurements were not made at the same locations, so area dose rate reductions could not be calculated. Post-test area measurements along the walkways and girder A indicated approximately 100 mrem gamma. At the top of the rails, the measurement was 150 mrem. Where contact gamma was reduced, it was reduced by 300 mrem (median). Contact beta reductions varied from 103 to 6700 mrem. Several locations indicated that both contact gamma and beta radiation readings increased.

Contamination and Recontamination--It appeared from CCTV results that the polar crane was recontaminated prior to the post-test measurements. Several crew members crossed contaminated areas to the polar crane and then went across most of the walkways, girders, etc., before the post-test data acquisition was conducted. During debriefing, crew members indicated that there were a few surfaces of the crane that had not been flushed since the crew could not "see" or reach them with the lance.

Effectiveness of the Technique--The results of the crane low pressure flush are not indicative of the efficiency of low pressure flushing. There was not as much dirt and rubble on the surface of the polar crane as on the elevation 305' or 347'-6" floors. There was oil, grease, and considerable corrosion and the crane does have a large percentage of vertical and angled surfaces. Debriefing results, visual observations, and radiation results indicate that a different technique should be used to decontaminate the polar

crane. Appropriate spray nozzles, pressures, and flow rates should be selected to remove the oil, grease, and dirt on the various surfaces of the dome and crane. A variety of nozzles and pressures would be required because of the large variance in distances and surfaces present in the crane area.

Efficiency of the Low Pressure Flush Technique--The water rate per square foot for this task was extremely low for the total area. Insufficient water was placed on the dome and crane to remove the contamination.

General Summary of Low Pressure Flush of the D-Rings, Missile Shields, Canals, Reactor Head Service Structure, and Refueling Bridges

Technique Description. The low pressure flush of these areas was designed to accomplish the following:

- o Determine the effectiveness of decontaminating the refueling equipment, canals, and service structures, with low pressure flushing at various temperatures.
- o Decontaminate various surfaces and materials, including walkways, stairs, ladders, bridges, and walls.
- o Determine the advantages of misting the surfaces prior to flushing.
- o Determine the radiation reduction as a result of the flushing operation.

The low pressure flush of this area was conducted over a 2-day period, starting late in the afternoon after the low pressure flush of the polar crane. The pre-test data were taken before the low pressure flush of the polar crane. During the polar crane flush, debris was deposited on the surfaces of the missile shields, D-rings, and refueling canals, and had to be removed along with the debris and contamination already in place. The first flush effort for this task was on the top of the D-ring, and the rest of the task was completed 2 days later. The D-rings were flushed on top and down into the interior from

elevation 367'. The refueling bridge, reactor head service structure (RHSS), and the shallow and deep refueling canals, were flushed from elevation 347'-6" and the walkways along the refueling bridge. No flushing was accomplished physically down in the canals. Post-test decontamination data were taken the day after the completion of this task and the low pressure flush of elevation 347'-6". Deleted from the task in the scope change were the data points on the elevation 347'-6" floor associated with the D-ring task to determine recontamination, overspray, and deposited debris from the crane. Photographs 8, 9, 10, and 11 show the refueling bridge and walkways, the underside of the missile shields and D-ring walkway, the shallow end of the refueling canal, and the deep end of the refueling canal and RHSS, respectively. Figures 2-7, 2-8, and 2-9 show the data acquisition locations for the D-rings, missile shields, refueling canals, RHSS, and refueling bridges.

Smearable Contamination Levels. The levels of smearable contaminants associated with the task are shown in Table 2-7. The D-rings had contamination reductions of 68 percent in Cs-137 and 96 percent in Sr-90. In the refueling canals, the deep end contained more contamination both before and after flushing than the shallow end. There was no reduction in Cs-137 in the deep end, and a 70 percent reduction in Cs-137 and a 57 percent reduction in Sr-90 in the shallow end of the canal. The fuel handling bridge had an increase of 23 percent in Cs-137 during the flushing operation.

Degree of Uncertainty - Decontamination Effectiveness. The decontamination effectiveness of this task is uncertain because of the contamination and water deposited on the surfaces after the polar crane flush and the timing of the pre-test data acquisition task. The equipment provided "shadows" on some of the surfaces which required angle changes to obtain flushing of the entire surfaces. It is apparent that some areas were not flushed effectively because of equipment obstructions.

TABLE 2-7. CONTAMINATION LEVELS OF D-RINGS, REFUELING CANAL, AND FUEL HANDLING BRIDGE

<u>Areas</u>	<u>Pre-test</u> <u>(dpm/100 cm² x 10⁶)</u>		<u>Post-test</u> <u>(dpm/100 cm² x 10⁶)</u>	
	<u>Cs-137</u>	<u>Sr-90</u>	<u>Cs-137</u>	<u>Sr-90</u>
D-rings	7.1	4.6	2.3	0.17
Refueling canal (shallow end)	3.3	0.28	1.0	0.12
Refueling canal (deep end)	6.7	0.063	6.6	0.2
Fuel handling bridge	1.3	0.07	1.6	0.024

Waste Volume. Waste volume for this task was low compared to the total square footage of the area. Since this area contained a large percentage of vertical surfaces and run-down from spraying occurred, helping the decontamination, it is understandable why the DFs were obtained with a low amount of water. Table 2-8 shows the results.

TABLE 2-8. D-RINGS, REFUELING CANAL, MISSILE SHIELDS, AND FUEL HANDLING
BRIDGE WATER RATES

Test Area	Area (ft ²)	Water Used (gal)	Water Use (gal/ft ²)
Top of D-rings	1169	294	0.25
D-ring walls	13,100	316	0.024
Refueling canal (shallow end)	4801	283	0.059
Refueling canal (deep end)	3244	142	0.04
Fuel handling bridge	1300	39	0.03
Missile shields	1867	304	0.16

Results - Expected Versus Actual. The results of the refueling canal produced the expected 50 percent reduction in dose rate in those areas where it was believed that the major source term was from the contamination. On top of the D-rings and areas associated with the top part of the RHSS, the reduction in dose rate was not as large because of other source terms. Contamination results were expected to have a higher amount removed and a lower amount remaining on the surface than was achieved. The amount remaining would have been lower if the water and debris had been picked up with a vacuum or if the flushing had occurred at the refueling canal floor level, which would have allowed the debris to be flushed into the drain rather than dry on the floor. Because debris was loosened from the surface but not effectively moved to the drain, higher floor contamination levels remained.

Equipment and Techniques. The basic low pressure flush technique was used for the task.

Worker Radiation Exposure. The man-hours associated with the entire task are given in Table 2-9.

TABLE 2-9. D-RINGS, MISSILE SHIELDS, AND REFUELING EQUIPMENT - SUMMARY OF WORKER EXPOSURE

	<u>Man-hours</u>	<u>Man-rem</u>
Pre-test data acquisition	4.75	0.919
Post-test data acquisition	4.91	0.980
Experiment operations	15.56	2.353

Safety. Safety planning for the task had several areas of concern. Special centerline lock harnesses were used by data acquisition personnel to climb in and out of the canals on the vertical ladders over 20 feet high. Keeping track of contaminated harnesses in the reactor building and their limited number caused some delay when equipment had to be swapped inside the reactor building. Heat stress, associated with the climbing and data taking task, aborted two tasks before the crews completed their assignments. Additional personnel and task time was spent completing the data requirements. Physical condition was important in the task, and the personnel were rotated to avoid similar incidents in the post-test data taking activities. The top of the walkways was slippery when wet, and when coupled with hydrolance operations, care had to be exercised on the operating pressure of the lance. A safety harness should be worn by flush operators working on the walkways where they can connect the harness to the railing.

Worker Productivity. The flushing of the task area was conducted from the walkways, the top of the D-rings, and elevation 347'-6". Minimal climbing was required except for data acquisition, which required descents into the refueling canals. Worker rates for the canals, RHSS, and D-rings were as projected. The clothing requirements were the same as all other low pressure flushing tasks. This task could not be simulated or a mock-up built because of the variety and complexity of the equipment and areas; therefore, photographs and cutaways of the reactor building had been used for planning. Covering the area properly with water was a problem, and adjustments had to be made repeatedly from the command center. The task used remote reporters and a rad-con technician. The capabilities of these people were acceptable although the lack of physical endurance of some of the personnel caused some task delay.

Summary of Specific Results. The task demonstrated that the refueling canals, equipment, and surface areas could be successfully flushed to produce acceptable results. It showed vividly what large RDFs could be obtained from surfaces that had not been walked on and had debris ground into them. The task shows the different source terms, dose rate reductions, and type of surfaces that impact on decontamination results.

Low Pressure Flush Parameters--The results of the low pressure flush test on the D-rings, refueling canals, RHSS, and refueling bridges are shown in Table 2-10. The flushing task was conducted during two entries. The first part of the task was conducted late in the day and consisted of approximately 35 minutes of actual flushing of the top of the D-rings. The task was completed during the second entry, for a total of 2 hours and 12 minutes of flushing with 1378 gallons of water. The actual amount of man-rem for flushing was 2.125.

TABLE 2-10. SUMMARY OF RESULTS OF D-RING WALLS, CANALS, AND FUEL HANDLING BRIDGE

Area	Area Dose Reduction ^a	RDF (Contact)	Swipes Total Cesium (dpm/100 cm ²)		Water Use (gal/ft ²)
			Final	DF	
Top of D-ring wall	21%	7.8	1.02x10 ⁶	4.3	0.25
Refueling canal					
Horizontal	51%	31.3	4.51x10 ⁶	3.5	
Vertical	NA	110.0	3.31x10 ⁴	1.7	0.07
Service Structure	NA	417	2.46x10 ⁵	<1	
Deep end					
Horizontal	65%	31.5	1.49x10 ⁷	1.2	0.04
Vertical	NA	67.5	3.47x10 ⁶	<1	
Fuel handling bridge					
Horizontal	32%	3.2	3.18x10 ⁶	<1	0.03
Vertical	NA	107.4	1.30x10 ⁵	<1	
Areas on top of D-ring walls					
Missile shield	33%	20.5	6.43x10 ⁶	1.5	0.16
walkway	-	6.7	1.35x10 ⁸	<1	

a. Area dose reduction = $\frac{\text{average pre-test area gamma} - \text{average post-test area gamma}}{\text{average pre-test area gamma}}$

Visual Results--Visual results were limited by the CCTV location; only the walkways and top of the D-rings could be observed. The walkways, missile shields, top of the D-rings, and bridge were not as dirty as the elevation 347'-6" floor, but they did have surface debris from the crane task. Visual observations by the flush crews indicated that dirt and debris were not visible on the walls or canal floor, except for crud piles and some dirt near the drains.

Radiation Changes--The low pressure flushing produced radiation changes in area dose rates; the largest reduction was in the deep end of the refueling canal, at 65 percent. The lowest area reduction was on top of the D-rings at 21 percent. This was anticipated because other sources, such as the B D-ring, had internal readings varying from 5 to 30 rem gamma, and the A D-ring had lower readings. The median reductions are given in Table 2-11. Follow-on tasks in the refueling canal areas showed approximately a 50 percent or larger reduction in man-rem for comparable tasks and time. Had the refueling canals been flushed from the floor, the area dose rate reduction would have been much greater.

TABLE 2-11. MEDIAN CONTACT RADIATION REDUCTION
(differences in pre-test and post-test values)

<u>Area</u>	<u>Contact Gamma (mrem)</u>	<u>Contact Beta (mrem)</u>
D-ring	70	2250
Refueling canal (shallow end)	110	1774
Refueling canal (deep end)	58	1054
Fuel handling bridge	35	724

Contamination and Recontamination--The post-test contamination revealed low DFs for swipe samples. It appeared that the contamination was moved from the large vertical surfaces to the horizontal surfaces; however, the flushing was not as successful in moving the debris to the drains because of the long distance from the floor to the flush teams. Thus, the contamination was left on the floor and between equipment sections. Had the crews flushed from the lower sections and the floor, the debris would have been moved to the drains.

Effectiveness of the Techniques--The low pressure flushing of stainless steel will produce excellent RDF's for contact readings on vertical surfaces and substantial area dose reduction. For low pressure flushing on horizontal surfaces, it is possible to obtain the same contamination levels (10^4 dpm/100 cm^2 of Cs-137) as the vertical surfaces when the flush is properly executed and the floors are flushed to move contamination and dirt to the drains. If the surfaces can be flushed before traffic is allowed on the surface, the decontamination of surfaces should be effective and easily obtained. Flush pressure of 500 to 1000 psi at 20 to 25 gpm appears to be optimum from the analysis and visual results.

Efficiency of the Techniques--The low pressure flush of the refueling equipment used both hot and ambient water at 22 gpm, except for a few brief periods of reduced flow and pressure on the deep end of the canal. Some flush crew members were not large enough in stature to control the lance adequately at the pressure and flow rates required. As a result of this and the observed lack of physical endurance of the crew members, the pressure and flow rates were reduced. As a result, excessive rotation of the flush operator position took place, which increased the flush time and reduced the effectiveness of the task. In addition, when crew members switched to the lance operator position, they lost track of what had been flushed, what had to be reflushed, and what remained to be cleaned. Warmer water appeared to produce better visual and data results in the shallow end of the canal.

General Summary of Low Pressure Flush of Elevation 347'-6"

Technique Description. The low pressure flushing of elevation 347'-6" was designed to:

- o Determine the effectiveness of various combinations of flow rates and temperatures on floor, walls, equipment, and other surfaces
- o Determine the efficiencies of the low pressure flush combinations
- o Determine airborne activity changes due to flushing activity
- o Determine the quantity of waste generated
- o Determine the radiation reductions as a result of the flushing operation
- o Decontaminate the elevation 347'-6" area
- o Evaluate the sequence of decontamination for the vertical, horizontal, and overhead surfaces

The low pressure flushing of the elevation 347'-6" floor and equipment took place in conjunction with and continued after the low pressure flushing of the D-rings, missile shields, refueling canal, RHSS, and refueling bridge. Figures 2-10 and 2-11 show the planned and actual test areas and parameters for the low pressure flushing of the elevation floor and equipment. The flushing removed a great deal of construction dirt and debris, and some of this dirt had to be shoveled into bags for waste removal. Spraying vertical surfaces, such as the liner and outside D-ring walls, 10 feet above the floor was removed from the scope of work and was not accomplished.

Smearable Contamination Levels. The pre-test contamination levels averaged 7.1×10^6 dpm/100 cm² of Cs-137. No post-test low-pressure flushing smearable contamination levels were measured except in the area of the mechanical scrubber test, where one 8 x 20 foot area was not high pressure sprayed. The average smearable contamination reading was 1.5×10^5 dpm/100 cm² in that area. The RHSS was also low pressure flushed only because the strippable coating was to be applied to its surface instead of its being high pressure sprayed. The average smearable contamination on the RHSS after low pressure flushing was 7.1×10^4 dpm/100 cm² for Cs-137. However, after the high pressure spray on the elevation 347'-6" floor but before the application of the strippable coating, the readings were 2.44×10^6 dpm/100 cm². This indicates a high level of recontamination from high pressure activities on the floor near the equipment.

Degree of Uncertainty - Decontamination Effectiveness. The data acquisition for the low pressure flushing of elevation 347'-6" was made during entry 43, along with the data acquisition task for the rest of the elevations. The polar crane had been flushed with the dome, and contamination, water, and debris were deposited on elevation 347'-6" after the initial elevation 347'-6" pre-test data were taken for low pressure flushing. Both the part of the post-test data acquisition task for the polar crane which had sample points on the elevation 347'-6" surface, and the post-test data acquisition for the low pressure flushing, were deleted from the scope of work so more decontamination tasks could be accomplished. As a result, the amount of contamination deposited on the elevation 347'-6" floor from the crane could not be determined, and only some isolated points in one test area were available for analysis of low pressure flushing.

Waste Volume. The low pressure flushing task used 14/5 gallons of water during its sequences. Besides flushing liquid waste, crews had to shovel dirt and debris into bags and bring them out as solid waste. In confined spaces, the water was unable to move the dirt to the drains. As a result, the low pressure flushing had to be suspended while large dirt piles were removed and

placed into bags with snow shovels. Elevation 347'-6" did not have the openings, floor penetrations, or other areas to dispose of the debris into the sump or basement level as were common on elevation 305'. The amount of water used was within 5 percent of what had been estimated for the task in the waste management plan.

Results - Expected versus Actual. The low pressure results were not measured after the task was completed. Some reduction in man-rem for later tasks was observed on elevation 347'-6".

Equipment and Techniques. The standard low pressure flushing techniques were used for the task. New equipment included:

- o Plastic snow shovels
- o Plastic children's sand shovels
- o Denim laundry bags and holders
- o Stainless steel meter sticks for 1-meter measurements.

The laundry bags were filled with dirt and debris and placed over drains. Water was sprayed into the bags to bring the dose rate down below a requirement of a 2-rem contact reading for each bag.

Worker Radiation Exposure. The worker exposure during the low pressure flushing test was 1.764 man-rem. Table 2-12 shows the exposure for each part of the task.

TABLE 2-12. ELEVATION 347'-6" LOW PRESSURE FLUSH - SUMMARY OF
WORKER EXPOSURE

<u>Task</u>	<u>Man-hours</u>	<u>Man-rem</u>
Pre-test data acquisition	4.47	0.813
Low pressure flushing of elevation 347'-6"	6.15	0.951

Safety. There were no specific comments on safety-related items for this task.

Worker Productivity. Worker productivity was hampered by the protective clothing requirements for the task. Heat stress and fatigue were the major limiting task length factors, rather than dose rate, on elevation 347'-6". The long hydrolance used was designed to prevent an operator from "shooting" himself with it. Safety, however, required foot and shin guards for operators using the hydrolance. It appeared at times that these guards were more of a tripping hazard than a protection. The rate of application of the low pressure flushing was not uniform during the task. It was evident in the videotapes that some lance operators did an outstanding job in the flushing task but others did not. The problem appeared to be a deficiency in the training for the operators. In one case, however, an attempt was made to hurry the crews to finish the task and leave the reactor building. Apprehension was very noticeable during data acquisition for elevation 347'-6". Some of the samples had to be retaken because of worker fear of high radiation exposure, which caused inattention to readings and procedures. Remote reporters and rad-con technicians were both used for this task.

Summary of Specific Results.

Low Pressure Flush Parameters--The low pressure flushing test on elevation 347'-6" used 1475 gallons of water in 2 hours and 3 minutes of flushing. Three crews of three men each were used for the flushing task. A total of 19 man-hours and 3.197 man-rem was charged to this task. The data acquisition sample points are shown in Figure 2-12.

Visual Results--The visual results of elevation 347'-6" showed that dirt and debris were moved by the water. There was some striping of the floor by the low pressure water, but it was minimal compared to the striping of elevation 305'. The storage, equipment areas, and floors were washed and the water ran out from under the storage onto the floors after the teams had flushed them.

Radiation Changes--A post-test data survey was not conducted after the low pressure flushing. The only indications of radiation changes were the periodic digital dosimeter readings for the crew members during subsequent tasks on elevation 347'-6". From these readings, dose rates appeared to have decreased since the flushing operations.

Contamination and Recontamination--The contamination control for this task consisted of controlling the sequence and direction of the flushing. Problems were caused as the rad-con technicians were going from the air lock to and from the flushing areas to change the air sampler during the task. They walked from highly contaminated areas through the decontamination operations area to "cleaned" areas to obtain air samples and then returned over the same route. As a result, contamination control was ineffective. Recontamination was evident in this tracking of people, both on videotape and when evaluating the areas where there had been traffic.

Effectiveness of the Different Low Pressure Flushing Techniques--Data were not taken to evaluate the differences among the techniques used during the low pressure flushing on elevation 347'-6".

Efficiency of the Low Pressure Flush Techniques--There was a difference in the efficiency of the personnel who flushed elevation 347'-6", but the efficiency among the techniques could not be evaluated. Table 2-13 shows the flush rate in gallons per square foot. In the experiment, it was apparent that a water rate below 0.10 gallon per square foot was ineffective in decontamination except for vertical surfaces.

TABLE 2-13. ELEVATION 347'-6" LOW PRESSURE FLUSH

<u>Test Area</u>	<u>Area (ft²)</u>	<u>Water Used (gal)</u>	<u>Water Use (gal/ft²)</u>
V	1282	208	0.16
IV	5507	777	0.14
VII	464	221	0.48
VIII	1143	269	0.24

High Pressure Flush Activity

General Summary of High Pressure Flush of Elevation 347'-6"

Technique Description. The high pressure flush of elevation 347'-6" was designed to:

- o Determine the effectiveness and efficiency of high pressure water spraying of major equipment of different types, material composition, and coatings.
- o Determine the effectiveness of various high pressures, temperatures, and flow rates on horizontal and vertical surfaces as well as on all types of equipment.
- o Decontaminate the elevation 347'-6" floor and major equipment.
- o Determine the airborne concentrations associated with high pressure spraying.
- o Determine the radiation reductions from high pressure spraying.
- o Determine recontamination resulting from further decontamination operations.

The high pressure flushing on elevation 347'-6" started during entry 47 with high pressure spraying of the equipment. The following day, during entry 48, high pressure spin jet cleaning of the floor was completed. Post-test data acquisition for the flushing activity occurred 3 days later during entry 49. Some adjustments were made in the test areas due to operational considerations.

High pressure spray consisted of spraying with a hydrolance at approximately 2600 to 3200 psi and at 7.5 gpm on the following equipment:

- o Stairwell No. 1
- o Seal ring
- o Reactor coolant pump motor stand
- o Reactor coolant pump motor alignment stand
- o Internals indexing fixture
- o East and west LOCA ducts
- o Cable tray rack in Area I HP.

The high pressure water scrub of the floor on elevation 347'-6" consisted of operating the water scrubber at various pressures, temperatures, and flow rates on concrete floors, diamond plate, and grating. This was followed by a low pressure flush to move into the drain system the debris loosened from the floor by the water scrubber. The wall areas 2 to 4 feet above the floors were flushed to remove splatter by the scrubber. See Figures 2-13 and 2-14 for the planned and actual test areas and parameters. Figure 2-12 shows data acquisition sample points.

Smearable Contamination Levels. The average levels of contamination (dpm/100 cm² of Cs-137) for elevation 347'-6" are shown in Table 2-14.

TABLE 2-14. CONTAMINATION LEVELS OF ELEVATION 347'-6"

<u>Surface</u>	<u>Pre-test Cs-137 (dpm/100 cm²)</u>	<u>Post-test Cs-137 (dpm/100 cm²)</u>	<u>Tests^a</u>
Concrete floor	7.1×10^6	4.2×10^5	LP/HP
Diamond plate	3.85×10^6	3.21×10^5	LP/HP
<u>Equipment</u>			
Index fixture	1.57×10^5	2.44×10^4	LP/HP
LOCA ducts	3.09×10^5	9.2×10^4	LP/HP
Cable trays	1.73×10^7	2.39×10^4	LP/HP
RC pump motor stand	6.61×10^6	5.02×10^5	LP/HP
RC pump alignment stand	6.34×10^6	6.32×10^6	LP/HP
RHSS	1.11×10^5	8.08×10^4	LP only
RHSS	1.25×10^6	2.36×10^4	LP and strip coat

a. LP = Low pressure flushing, HP = High pressure flushing.

During the low pressure/high pressure effort on elevation 347'-6", Cs-137 was reduced 94 percent and Sr-90 was reduced 92 percent. Data representing all test points and areas show no discernable differences in the cesium/strontium ratios before and after the test.

Degree of Uncertainty - Decontamination Effectiveness. It was concluded from an examination of the videotapes, photographs, and data taken before the low pressure test and after the high pressure test that high pressure flushing alone of the surfaces on elevation 347'-6" would have produced the post-test high pressure readings. Surfaces of special test areas that were high pressure sprayed only produced test results equal to or greater than the low pressure flush. After examining the videotapes and debriefings and determining that the high pressure spraying had marked visual results on the floor surface,

it was reaffirmed that the high pressure flushing alone on the surfaces would produce the results attained by both the low and high pressure spray. Sample points were removed from the analysis of the high pressure test in various areas where the water scrubber could not be operated. (Area IX HP was the exception since only the lance was used for that area. See Photograph 12 for Area IX.) As a result, the 4000 psi, 15 gpm test results in Area IX for the water floor scrubber were not determined, even though they were considered critical to the test data. Visual observations of the test noted recontamination of sample points by personnel traffic; this was taken into consideration in the results of individual tests.

Waste Volume. Tables 2-15 and 2-16 reflect the specifics for the amount of liquid waste generated during the high pressure spray of the equipment and the water floor scrubber cleaning of the floor surfaces. The 2157.1 gallons were within a small percentage of what had been estimated for the task.

Results - Expected Versus Actual. The results of the high pressure spraying on the equipment on elevation 347'-6" showed which tests were effective and which tests were not appropriate or would cause problems. Initially, some of the high pressure test results were disappointing; however, with an understanding of what really took place (recontamination, contributing radiation sources, ineffective procedures, or inappropriate techniques), the test results indicate which high pressure techniques were effective. The best technique produced the expected decontamination results; recontamination by technique and personnel traffic was not expected to be as large as it was in total dpm/100 cm² for some of the tests.

Equipment and Techniques. The equipment used during the tests included:

- o The water floor scrubber with four rotating nozzles and equipped with three sets of various flushing nozzles. (0-, 15-, and 725-degree nozzles are available.)

TABLE 2-15. ELEVATION 347'-6" HIGH PRESSURE FLUSH WATER USE

<u>Test Area</u>	<u>Area (ft²)</u>	<u>Water Used (gal)</u>	<u>Water Use (gal/ft²)</u>
I	646	182.3	0.28
II	337	104.1	0.31
III	299	164.3	0.55
IV	1167	121.3	0.10
V	2251	519.2	0.23
VI	839	355.1	0.42
VII	465	121.3	0.26
VIII	296	190.6	0.64
IX	618	<u>130.5</u>	0.21
Total =		1889.0	

TABLE 2-16. ELEVATION 347'-6" EQUIPMENT HIGH PRESSURE FLUSH WATER USE

<u>Test Area</u>	<u>Area (ft²)</u>	<u>Water Used (gal)</u>	<u>Water Use (gal/ft²)</u>
Stairwell No. 1	204	31	0.15
Seal ring	153	62	0.41
Pump stand, internals index fixture, & LOCA duct	1222	87	0.07
Cable trays	380	<u>88</u>	0.23
Total =		268	

- o The hydrolance with a high pressure spray tip for cleaning the debris removed by the spin jet.

The standard technique was used for high pressure spraying. The water floor scrubber had adapters placed on the nozzle holders to facilitate removal, and the lance was modified to allow quick changing of the various nozzles used during the tests. The test results showed that the 25-degree nozzle was not optimum for the scrubber and was removed from further testing because it produced more overspray and did not cut into the paint as well as the 15-degree nozzle. The 0-degree nozzle at 6000 psi would remove the paint from the concrete; therefore, it was not used in the reactor building. (The 15-degree nozzle was substituted for the 25-degree nozzle during the elevation 305' high pressure test.) The procedure for flushing after the water scrubber operation was inadequate for some of the test areas because of insufficient test pressure and application techniques. As a result, material loosened from the floor surface by the water floor scrubber was not moved by the flush water into the drains, but remained in small crud piles or as a film on the test area.

Worker Radiation Exposure. The worker exposure for the high pressure spray of elevation 347'-6" is shown in Table 2-17.

TABLE 2-17. ELEVATION 347'-6" HIGH PRESSURE FLUSH - SUMMARY OF WORKER EXPOSURE

<u>Task</u>	<u>Man-hours</u>	<u>Man-rem</u>
Pre-test data acquisition	12.96	2.318
High pressure spray	30.16	4.413
Post-test data acquisition	6.19	0.898

Safety. A safety "hold" occurred during the entry for high pressure spraying. A procedural problem on personnel restraints near the open grating had not been discussed prior to the entry, and several man-hours were lost during the entry to resolve the issue. This inflated the total hours for the experiment.

Worker Productivity. The worker productivity varied from 600 square feet per hour, for a surface with a lot of equipment and floor obstructions, to over 1600 square feet per hour. It was concluded that approximately 1000 square feet per hour should be used for planning purposes for successful high pressure spin jet operations. Productivity improved as water floor scrubber experience was gained in the reactor building. Personnel who were small in stature and those not physically fit had problems with maneuvering the 250-pound water floor scrubber and tired quickly.

Summary of Specific Results.

High Pressure Flush Parameters--High pressure flush of the equipment on elevation 347'-6" used 268 gallons of water in 43 minutes of actual flushing. It had been planned that several pressures, temperatures, and flow rates were to be used on the hydrolance operations. The temperature was varied, but the flush crews could not control the hydrolance at pressures higher than 3000 psi. When the pressure was reduced, it was not effective because the distance was too far from the nozzle tip to the equipment surface. The pressure was increased slightly during the test on the equipment, but the 4000 and 6000 psi tests with the hydrolance were not accomplished. The test could have been completed and all parameters could have been tested had sufficient personnel been available to allow persons of large stature (>250 pounds) to be selected for the task. In addition to low pressures, the horizontal and vertical surfaces above head height were not satisfactorily sprayed because necessary high reach equipment was unavailable. Post-test data samples were taken on horizontal surfaces that had not been adequately sprayed (see Photograph 13). Because the drain by the east LOCA duct plugged, the test on that duct was discontinued, and the duct was not effectively sprayed. The cable trays and

vertical surfaces, which were exceptions to the equipment spray task, were sprayed effectively with 3000 to 3200 psi (see Photograph 14 for vertical surfaces).. The water floor scrubber task used 1889 gallons in 3 hours and 37 minutes. Pressures of 2000, 4000, and 6000 psi were used at 5, 15, and 25 gpm at ambient and hot water (101 F average). Approximately 50 percent of the task was not observed on the CCTV because of camera problems. The crews failed to notify the command center when they finished the Area IV HP, and did not change the nozzles on the water scrubber to obtain 25 gpm for Area V. As a result, Area V scrubbing had to be repeated. Several sample points were not considered during analysis because the water scrubber would not fit in the area or was not used on the surface. Photographs 15 and 16 show highly congested areas where the scrubber could not be used. The floor area that was decontaminated the most effectively had the most gallons used per square foot of surface area. (See Tables 2-15 and 2-18).

Visual Results--Visual results of the color changes of the floor surfaces indicated that the water floor scrubber was more effective at higher pressures than lower pressures (see Photograph 17). At high pressures and high flow rates, a vapor cloud was observed around the machine. It was also noticed during the operation that flushing after the scrubber did not spray high enough on the walls and equipment to effectively remove the debris and contamination from the floor cleaning operations. Recontamination of the equipment on elevation 347'-6" was evident during the operation. Poor flushing techniques and test pressures too low for flushing the debris loosened from the floor by the scrubber were observed in some of the locations on elevation 347'-6". The smearable results went below 10^5 dpm/100 cm² of cesium only where concentrated effort was made to clean and prevent recontamination after the water floor scrubber operation.

TABLE 2-18. SUMMARY OF RESULTS OF ELEVATION 347'-6" FLOOR HIGH PRESSURE FLUSH

Area	Area Dose Reduction ^a	RDF (contact)	Swipes Total Cesium (dpm/100 cm ²)		Water Use (gal/ft ²)
			Final	DF	
I-HP 15 gpm 120 F/2000 psi	10%	15.9	1.27x10 ⁵	119.5	0.44
II-HP 5 gpm 94 F/4000 psi ^b	7.5%	19.0	4.03x10 ⁵	19.1	0.47
III-HP 5 gpm 110 F/2000 psi	22%	8.5	4.35x10 ⁵	10.1	0.69
IV-HP 7.5 gpm 88 F/6000 psi	16%	9.0	1.44x10 ⁵	37.4	0.25
V-HP 25 gpm 80 F/6000 psi	25%	23.1	8.7x10 ⁴	44.9	0.37
VI-HP 23.5 gpm 72 F/4000 psi	16%	30.5	3.44x10 ⁵	37.6	0.49
VII-HP 18 gpm 120 F/2000 psi	15%	29.6	7.28x10 ⁵	19.8	0.74
VIII-HP 18 gpm 95 F/6000 psi	23%	29.8	8.37x10 ⁴	69.9	0.88
IX-HP 14 gpm 89 F/2500 psi	34%	20.2	1.48x10 ⁵	9.4	0.45

a. Area dose reduction = $\frac{\text{average pre-test area gamma} - \text{average post-test area gamma}}{\text{average pre-test area gamma}}$

b. After the storage was moved from Areas II and III, the area dose rates were measured prior to the mechanical scrubber test. These readings indicated that a 47 percent area dose rate reduction had occurred after low and high pressure spraying of Area II and during removal of the storage and trash. The remaining dose rate was approximately 35 mrem/hour gamma.

Radiation Changes--The radiation changes in the area where the technique was judged most effective and optimum were:

Area gamma	20 mrem	(an average of 50 mrem remaining)
Contact gamma	130 mrem	
Contact beta	2086.5 mrem	

The cable trays had the largest changes in contact readings for the equipment decontamination. See Table 2-19 for the results.

Contamination and Recontamination--Contamination was evident in the high pressure and high flow rate tests. The established flush procedures did not do the job in minimizing the recontamination. There was insufficient detail in the procedures for the crews to recognize recontamination and inadequate guidance to increase the flush area where necessary. Contamination was not removed in several locations because the test pressure, water rate, or application rate was insufficient to be effective. In addition, personnel changing air samples traveled to the test areas several times through highly contaminated areas during the cleaning post-test data acquisition operations.

Effectiveness of the Techniques--In the combination of low pressure and high pressure flush, where it was assumed that the high pressure was the major technique, 6000 psi at 18 gpm gave the best results (see Table 2-18).

Efficiency of the Techniques--The higher pressure with the optimum flow rate of 18 gpm appeared to give the best DF with the least amount of waste and recontamination. The operation was most efficient when the pressure could be increased, the flow rate reduced, and the application rate decreased.

TABLE 2-19. SUMMARY OF RESULTS OF ELEVATION 347'-6" EQUIPMENT HIGH PRESSURE FLUSH

<u>Area</u>	<u>RDF</u> <u>(contact)</u>	<u>Swipes</u> <u>Total Cesium</u> <u>(dpm/100 cm²)</u>		<u>Water</u> <u>Use</u> <u>(gal/ft²)</u>
		<u>Final</u>	<u>DF</u>	
Stairwell No. 1	199	1.38x10 ⁶	3.9	0.15
Seal ring				
RC pump motor stand	28.3	3.76x10 ⁵	12.9	0.07
RC pump align stand	1.6	6.94x10 ⁶	<1	
Internals index fixture	12.4	2.0x10 ⁴	10.3	
West LOCA duct	16.5	1.15x10 ⁵	1.2	
Head storage stand	9.7	8.3x10 ⁴	1.6	Strip coat
Cable trays	81.6	2.6x10 ⁴	726	0.23

General Summary of High Pressure Flush of Elevation 305'

Technique Description. The high pressure flush of elevation 305' was designed to:

- o Determine the effectiveness of high pressure spin jet operations at various pressures, flow rates, and temperatures on the elevation 305' floor and wall surfaces
- o Determine the effectiveness of the various decontamination techniques
- o Determine the airborne activity changes as a result of operations
- o Determine the effectiveness of high pressure spraying on surfaces previously decontaminated during the large-scale decontamination test conducted in 1981
- o Determine man-rem, productivity of workers, safety of operations, and waste generated during the test.

The high pressure spraying on elevation 305' occurred during entry 50. During this entry, a storage area on elevation 347'-6", the open stairwell connecting elevation 347'-6" with elevation 305', and elevation 305' were decontaminated.

The low pressure flushing of the stairwell, which had taken place a few minutes before the high pressure water floor scrubber operations on elevation 305', dumped the water, contamination, and debris from the stairwell onto elevation 305' Areas XII and ISC. The operations plan on elevation 305' was to spray Areas X, XI, and XII, in that order. However, since the hoses were already in Area XII, the operational decision was made to start in Area XII and flush counterclockwise. Figures 2-15 and 2-16 show the planned and actual test parameters. Refer to Figure 2-3 for data acquisition sample points.

Smearable Contamination Levels. The average levels of smearable contamination (dpm/100 cm² of Cs-137) for the elevation 305' floor were 9.7×10^6 (pre-test) and 6.1×10^5 (post-test). The reductions in smearable contamination were 83 percent for Cs-137 and 90 percent for Sr-90 from the low pressure flush.

Degree of Uncertainty - Decontamination Effectiveness. The level of contamination on the floor after the low pressure flush is known, but the level of floor contamination at the start of the high pressure test is not known. After the post-test data acquisition had been conducted for the low pressure elevation 305' flushing, the flushing of the elevation 305' walls and overheads, elevation 347'-6" floor (debris came down through the floor grating), and the open stairwell deposited debris on the elevation 305' floor. As a result, after the high pressure test, radiation readings and contamination of some areas exceeded the values from the post-test low pressure flushing. The flushing to move the debris, loosened from the floor, by the water floor scrubber was unsatisfactory because the wrong nozzle and flow rate for the test were used. Thus, the test was not considered representative of the technique.

Waste Volumes. Table 2-20 shows the waste volume for the high pressure test on elevation 305'.

TABLE 2-20. ELEVATION 305' HIGH PRESSURE FLUSH WATER USE

<u>High Pres- sure Area</u>	<u>Area (ft)</u>	<u>Water Used (gal)</u>	<u>Water Use (gal/ft²)</u>
X	547	216.2	0.39
XI	552	132.5	0.24
XII	3468	1197.7	0.35

Results - Expected Versus Actual. The results of the high pressure spraying operation illustrated the impact of recontamination due to debris deposited on the surfaces from above and, in some cases, due to ineffective operational procedures. As a result, the high pressure spray did not produce the expected results. The tests, however, did show the techniques and the necessary procedures to produce the effectiveness desired. Area radiation results, which are dependent on the source term, proper contamination control techniques, and good decontamination procedures, did not reach the desired reductions on this elevation. It had been expected that contamination levels could be reduced below 10^5 dpm/100 cm² of Cs-137 for elevation 305'. It was apparent that the water floor scrubber loosened the semi-fixed debris from the surface of the floor, but the debris did not remain in solution and was not transported down the drains. As a result, much of the debris that was loosened from the surface dried on the floor or other surfaces.

Equipment and Techniques. The equipment used during the tests included the spin jet with four 15-degree nozzles, and the hydrolance with a 0050 nozzle for flushing. The equipment was the same as in the Equipment and Techniques section for the high pressure flushing of elevation 347'-6", with the exception of the flush nozzle. The techniques used involved water floor scrubbing the floor surface and then flushing the debris down the drain. A squeegee was used to control excess water and keep it in the floor contours to the drain system.

Worker Radiation Exposure. Worker radiation exposure for the high pressure test on elevation 305' was 5.75 man-hours and 2.525 man-rem. It must be noted that the elevation 305' high pressure spray task did not include Area ISC, which was only low pressure flushed (strippable coating was placed on Area ISC for testing after it had been low pressure flushed). The high pressure exposure was less than the low pressure exposure because the low pressure tests consisted of three separate activities (low pressure test on walls, overheads, and floor, and on the elevation 305' floor, and low pressure reflush).

Safety. The task did not have any problems during high pressure spraying, except that a crew member entered the reactor building with only one shin guard and was prohibited from assuming the lance operator position during the task.

Worker Productivity. The worker productivity varied from 1500 to 4600 square feet per hour. The rate of application was hurried in an attempt to complete the task in one entry, and the coverage of the area was incomplete. In the areas where there are considerable equipment and protrusions from the wall and floor surfaces, an estimate of the application rate cannot be projected. The water scrubber operators were told several times to slow their rate of application and movement with the machine. In the Area X HP, which had a pressure of 2000 psi and the lowest square foot per hour of application rate, considerable debris was left on the floor. See Photograph 18 for the debris, wheel marks, and flush marks on the floor. The results of high pressure water floor scrubber operations support the conclusion that 1000 square feet per hour at the proper pressure and flow rate will produce acceptable results.

Summary of Specific Results.

High Pressure Flush Parameters--High pressure flushing of the elevation 305' floor used 1546 gallons of water for 1 hour and 47 minutes of actual flushing time. Pressures of 2000 and 6000 psi were used at 24, 20.5, and 14 gallons per minute. Both ambient and hot water (120 F) were used at 2000 psi, and ambient was used at 6000 psi. Only the floor surfaces were high pressure sprayed. The flush after the water floor scrubber operation covered the floor and edge of the wall surface near the floor. Results of the high pressure flush are summarized in Table 2-21. During the task it was apparent that:

- o The 6000 psi and 25 gpm water floor scrubber operation used too much water and resulted in a large vapor cloud during and following the operation.
- o The wrong flush nozzle was used for Area XII, and the debris loosened from the floor by the scrubber was not moved effectively into the drains.

TABLE 2-21. SUMMARY OF RESULTS OF ELEVATION 305' HIGH PRESSURE FLUSH

High Pressure Area	Surface	Area Dose Reduction ^a	RDF (contact)	Swipes Total Cesium (dpm/100 cm ²)		Water Use (gal/ft ²)
				Final	DF	
X-14 gpm 2000 psi Ambient	Floor Stainless steel	0% -	30.6 1	1.89x10 ⁵ 4.6x10 ⁵	24.4 0.91	0.39
XI-20.5 gpm 2000 psi 120 F	Floor	5%	26.7	9.2x10 ⁴	39.6	0.24
XII-24 gpm 6000 psi Ambient	Floor Stainless steel	0% No post- test data recorded	30.8	1.42x10 ⁶	3.7	0.35

a. $\text{Area dose reduction} = \frac{\text{average pre-test area gamma} - \text{average post-test area gamma}}{\text{average pre-test area gamma}}$

Note: Area dose reductions did not occur, although the RDFs and DFs indicate that considerable activity and contamination were removed.

- o Debris was squeegeed back onto clean surfaces in Areas X and XII.
- o The application rate by the water scrubber operator was greater than used in training, and was too rapid to clean the amount of debris on the floor surface in Areas X and XII.
- o Post-test water scrubber flush operations with the lance did not cover the walls high enough to remove contamination caused by the machine operations at 6000 psi and 25 gpm.
- o The 15-degree nozzle on the water floor scrubber at 6000 psi and 25 gpm removed the dirt and some paint. This is shown in Photograph 19 and can be compared to results of 2000 psi at 14 gpm in Photograph 18. Water rates were not sufficient to produce good results at 14 gpm.

Visual Results--Visual results are shown in the photographs of Areas X, XI, and XII. Area XII had significant results at 6000 psi (Photograph 19) compared to 2000 psi (Photograph 18). The floor surface in Photograph 20 looked like that in Photograph 18 (wheel marks, etc.). The rate of application was so fast, even with the high pressure, that the surface was not being cleaned. After the crew repeated the task in Area VII, better results were achieved and are shown in Photograph 20, although some of the wheel marks are still visible on the floor surface. The diamond plate is visible in the top right area of Photograph 20. Photograph 21 shows the cleaned floor at 6000 psi and shows where a bucket had been on the floor surface during the accident and was later removed. Photograph 22 illustrates a surface cleaned at 6000 psi compared to a 2000 psi water floor scrubbed area in Photograph 23. In Photograph 24, the wheel marks of the machine are visible in the debris on the floor. The 2000 psi test and flush did not move the debris off the floor and down the drains, but the wheels of the machine did pick up contamination as did rubber boots worn by the decontamination crews, who tracked debris over the cleaned floor surfaces--a major source of recontamination.

Radiation Changes--The radiation changes in the area dose rate for Areas X HP and XII HP were actual increases over the pre-decontamination experiment values. Initially, low pressure flushing reductions were achieved, but recontamination and the inability of the post-test high pressure water floor scrubber flush to move the debris down the drains left the area with a 200 percent increase over the low pressure pre-test values. Failure to wash the wall surfaces and the floor effectively (and other sources) contributed to the high area radiation readings. The only area that showed a reduction in radiation readings was Area XI HP where a 13 percent reduction was achieved over low pressure flushing results. Contact radiation readings were reduced in all areas with the highest RDF of 30.6.

Contamination and Recontamination--Contamination of the other surfaces was evident in the videotapes of tests in which the high flow rates and high pressures were used (6000 psi and 24 gpm). Recontamination was evident as personnel changed air samples, moved wastewater with squeegees, and performed cleanup tasks. Swipe samples had DFs in the 20 to 25 range for 2000 psi and a DF of 3 for 6000 psi. The smearable contamination level averaged 10^5 dpm/100 cm² for cesium. During the flush of the stairwell prior to the high pressure spraying of elevation 305', a large quantity of dirt and contamination was deposited on the elevation 305' floor in Area XII HP.

Effectiveness of the Different High Pressure Techniques--The effectiveness of the techniques used during this test showed that 2000 psi was an insufficient pressure to use at any flow rate with the water floor scrubber to remove contamination. The recontamination of other surfaces and the inability to flush the loosened debris into the drains demonstrated that 6000 psi at 24 gpm was too much water to control at high pressure.

Efficiency of the High Pressure Techniques--The test showed that these techniques were not efficient. In addition, the task was not completed, required additional effort to remove contamination, and in some instances led to recontamination of clean surfaces. This series of tests showed the parameters where the techniques did not remove enough debris and where the removal of a lot of debris was inefficient and recontamination occurred.

Reflushing of Elevation 305'

General Summary of Reflushing of Elevation 305'

Technique Description. At the completion of the high pressure flushing, data acquisition and a review of the task indicated that large amounts of contamination and high dose rates remained in Area XII HP. Since this area provided major access to higher elevations and to the polar crane, an attempt was made to reflush this area before debris was tracked throughout the building. Unfortunately, the reflush was not scheduled until the second entry following the high pressure spraying of elevation 305'. Therefore, some contamination had been tracked to other levels and areas. The task was established to conduct a low pressure flushing from the area around the open stairwell through high pressure Area XII into Area XI to the entrance of the No. 2 air lock. During the last portion of the flushing operations, the air lock door developed a problem. As a result, most of the flushing continued unsupervised while the command center developed a procedure to enable personnel to exit the reactor building. As a result, the flushing task was not completed as planned.

Smearable Contamination Levels. Table 2-22 shows the pre- and post-test smearable contamination levels for this reflushing operation. The contamination levels were not effectively reduced during the reflush of the area because not all the recontaminated areas were flushed and the crew failed to move the debris down the drains.

Degree of Uncertainty - Decontamination Effectiveness. The data acquisition of the reflushing of elevation 305' was accomplished during a later entry. Some personnel traffic did occur in the area prior to the measurements.

Waste Volume. The liquid waste generated during the 32 minutes of flushing was 781.3 gallons of water, which was directed down the drains and the open stairwell to elevation 282'-6".

TABLE 2-22. SUMMARY OF REFRESHING RADIATION AND CONTAMINATION DATA OF ELEVATION 305'

LP Area	Location	Surface	Area				Contact								Swipes			
			Pre-Test Gamma	Post-Test First LF Gamma	Post-Test HE Gamma	Post-Test Reflush Gamma	Pre-Test Contact Gamma	Post-Test LP Gamma	Post-Test HP Gamma	Post-Test Reflush LP Gamma	Pre-Test Beta	Post-Test LP Beta	Post-Test HP Beta	Post-Test Reflush LP Beta	Pre-Test Cs-137	Post-Test LP Cs-137	Post-Test HP Cs-137	Post-Test Reflush LP Cs-137
	53-1	Floor			1300	1200				3800			9360	12,800				
	53-2	Floor			1100	1300				1800			1170	2000				
III	53-3	Floor	800	500	1200	1300	1000	900	1800	1900	4560	2660	780	1200	4.8x10 ⁶	1.7x10 ⁶	7.5x10 ⁶	6.2x10 ⁵
	53-4	Floor			1100	900				1600			3900	800				
	53-5	Floor			900	900				1200			780	6400				
	61	Floor	1000	500		400	3400	1000	900	1000	17,480	8360	8190	10,000		9.3x10 ⁶		9.5x10 ⁶

Results - Expected Versus Actual. The results of the reflush demonstrated that:

- o The area must be flushed properly, including the walls and recontaminated surfaces, to reduce area readings
- o Contamination levels achievable with water spraying are limited without some assistance of mechanical or chemical agents to remove the debris or keep debris suspended until it is flushed down the drains
- o Squeegee operations must keep the debris moving ahead of the lance operator
- o Contamination control and decontamination sequencing must be used together in order to minimize recontamination.

The results were expected to exceed the decontamination factors achieved as a result of low pressure reflushing.

Strippable Coating Test

General Summary of Results

Technique Description. The strippable coating test was designed to provide information to:

- o Determine the effectiveness, safety, and efficiency of the strippable coating as a means of decontaminating major equipment items on elevation 347'-6" and floor surfaces on elevation 305'.
- o Determine the man-rem, man-hours, solid waste generated, worker productivity, and radiation changes during the test.
- o Determine the effectiveness of using cheesecloth beneath the coating to add strength on irregular surfaces.

- o Determine the amount of activity removed by the coating and its effectiveness on surfaces of complex geometry.

The strippable coating was tested on equipment on elevation 347'-6" and on the elevation 305' floor surface. Water in the bottom of the center tank on the reactor head storage stand prevented it from being coated. As a result, the outer support flange horizontal and vertical surfaces on the storage stand were stripcoated with Imperial ALARA DECON 1146 and 1148 (self-strippable coating). Photograph 25 shows the support flange.

The elevation 305' floor Area ISC was coated with ALARA DECON 1146. All the coatings were allowed to dry for at least 24 hours before being removed. The material was cut with a carpet knife into strips several feet long and placed in plastic bags as compactable trash. The bags were loaded to less than 2 R gamma (contact) and were tied with long cords so the bags could be dragged. The coating on the elevation 305' floor is shown in Photographs 26 and 27.

Smearable Contamination Levels. The smearable contamination levels for Area ISC were 10^6 to 10^7 dpm/100 cm² of Cs-137 at the start of the test and were 10^4 dpm/100 cm² of Cs-137 after the material was removed from the floor. On elevation 347'-6", the vertical surfaces were 10^4 dpm/100 cm² and the horizontal surfaces were 10^6 dpm/100 cm² of Cs-137 at the start of the test. Post-test results showed 10^4 dpm/100 cm² of Cs-137 on horizontal equipment surfaces and floors. Vertical surfaces had post-test smearable results in the 10^3 dpm/100 cm² range for Cs-137. Table 2-23 presents the contamination results.

TABLE 2-23. STRIPPABLE COATING TEST - ELEVATION 305' FLOOR AND ELEVATION 347'-6" HEAD STORAGE STAND

LP/HP Area	Location	Surface	Pre-Test Area	Post-Test Area	Pre-Test Contact	Post-Test Contact	Pre-Test Contact	Post-Test Contact	Pre-Test Swipes-dpm/100 cm ²			Post-Test Swipes-dpm/100 cm ²		
			Gamma	Gamma'	Gamma	Gamma	Beta	Beta	Cs-137	Cs-134	Sr/Y-90	Cs-137	Cs-134	Sr/Y-90
Elevation 305' Floor														
	65		-	-	300	300	2240	2400	1.35 x 10 ⁶	1.33 x 10 ⁵	4.22 x 10 ⁴	5.99 x 10 ⁴	5.55 x 10 ³	7.77 x 10 ³
	70		-	-	290	200	672	880	1.27 x 10 ⁷	1.62 x 10 ⁵	4.22 x 10 ⁴	5.77 x 10 ⁴	5.99 x 10 ³	3.11 x 10 ³
	76		-	-	500	200	5440	3600	1.07 x 10 ⁷	1.02 x 10 ⁶	3.11 x 10 ⁵	1.95 x 10 ⁵	1.91 x 10 ⁴	1.86 x 10 ⁴
	77		-	-	700	800	1280	1000	2.02 x 10 ⁶	2.0 x 10 ⁵	3.55 x 10 ⁴	7.55 x 10 ⁴	8.44 x 10 ³	8.66 x 10 ³
Elevation 346'-6" Head Storage Stand														
	50		-	-	90	110	96	40	7.10 x 10 ⁴	5.99 x 10 ³	1.82 x 10 ³	2.89 x 10 ³	LLD	3.33 x 10 ³
	51		-	-	60	150	4928	3800	2.44 x 10 ⁶	2.44 x 10 ⁵	4.66 x 10 ⁵	4.44 x 10 ⁴	4.22 x 10 ³	3.11 x 10 ⁴
	52		-	-	140	100	4672	4400	1.24 x 10 ⁶	1.22 x 10 ³	1.73 x 10 ⁵	5.11 x 10 ⁴	4.22 x 10 ³	1.53 x 10 ⁴
	150		-	-	140	110	4672	4560	3.77 x 10 ⁶	3.77 x 10 ⁵	5.55 x 10 ⁵	-	-	-
	151		-	-	60	80	128	100	4.44 x 10 ⁴	3.77 x 10 ³	3.55 x 10 ³	-	-	-
	159		-	-	100	-	128	-	6.66 x 10 ⁴	6.22 x 10 ³	1.51 x 10 ⁹	-	-	-
	160		-	-	120	-	64	-	5.33 x 10 ⁴	5.77 x 10 ³	2.13 x 10 ³	-	-	-
	162		-	-	140	140	5312	5440	5.55 x 10 ⁶	5.33 x 10 ³	6.88 x 10 ⁵	7.55 x 10 ⁴	7.99 x 10 ³	4.44 x 10 ⁴
	163		-	-	80	100	224	200	5.11 x 10 ⁴	4.0 x 10 ³	5.77 x 10 ³	2.44 x 10 ³	LLD	4.0 x 10 ²
Intermediate Readings with Strip Coating on Elevation 305'														
			Contact Gamma		Contact Beta									
	65		300		800									
	70		280		400									
	76		600		2000									
	77		600		800									
Head Storage Stand														
	50		120		NDB									
	51		150		3000									
	52		150		3000									
	150		120		2920									
	151		80		120									
	159		-		-									
	160		-		-									
	162		125		4300									
	163		110		40									
A 750 mg sample of self-strippable coating after removal contained:												9.32 x 10 ⁶	9.10 x 10 ⁵	2.18 x 10 ⁵

Intermediate-level samples were taken while the coating was on the surfaces and indicated levels of activity comparable with the post-test contamination levels after the coating was removed. There appeared to be some cross-contamination of the samples and surface recontamination during data acquisition.

The self-strippable coating sample analyzed after removal from the reactor building showed 9.3×10^6 dpm/100 cm². This analysis and the photographs of the coating removals (Photographs 28 and 29) show that the coating removed considerable debris from the floor surface.

Degree of Uncertainty - Decontamination Effectiveness. Data were acquired on two occasions before the floor and equipment were strip-coated. Post-test data taken for two separate tasks confirmed the levels and readings. Area radiation readings were not taken, however, while the coating was on the floor; therefore, it was not possible to determine the coating's effectiveness in area radiation reduction.

Waste Volume. Both solid and compactable waste were generated by removal of the strippable coating. The trash consisted of the containers for the strippable coating and the coating after it was removed from the floor. The trash was placed in plastic bags and removed from the reactor building. The total volume of waste was 4.5 cubic feet (which should be compactable to approximately 3 cubic feet). Preliminary calculations indicate that a 55-gallon drum filled with the used ALARA 1146 strippable coating from an area of comparable contamination levels will show contact gamma readings of less than 5 rem. One drum will hold the refuse from 2000 to 2500 square feet of coated surface.

Results - Expected Versus Actual. The strippable coating test showed better decontamination effectiveness than expected. More debris was removed using the coating as a decontamination medium after low pressure flushing than had been demonstrated during any previous test in containment. Previous tests, using another manufacturer's product, had shown that the coating might be

difficult to remove from the floor. The Imperial ALARA DECON 1146 product was easy to apply and easy to remove. However, the self-strippable coating (1148) was not easy to remove and it is not recommended for use in the reactor building.

A section was also tested with cheesecloth as a base to evaluate the removal qualities with and without cheesecloth. The results showed that the cheesecloth was unnecessary and that the coating could be removed easily without it. However, if positive removal of the organic coating is required to ensure quality control criteria, consideration should be given to using the cheesecloth as a base for the coating.

Equipment and Techniques. The strippable coating was sprayed on the equipment and floor surfaces with an airless pump sprayer. The pump was set in a 5-gallon can of the coating and had a standard service air inlet of 90 psi and an outlet line of 2200 psi to the spray gun. A "mil stick" was used to periodically check the depth of the coating thickness and keep the coverage depth at 30 to 50 mils.

Worker Radiation Exposure. The worker exposure for the total task was 2.603 man-rem. The man-hours associated with the task were 10.65. Table 2-24 shows the individual man-rem and times for spraying and removing the coatings.

Safety. There were no safety problems with the strippable coating task, and normal precautions for any spraying of coatings were observed.

Worker Productivity. The test demonstrated that a floor surface could be strip coated at the rate of approximately 1000 square feet per hour. Removal of the floor coating was slightly less, at 750 to 800 square feet per hour.

The equipment test had an 800 square foot per hour rate of coverage, and included some surfaces with complex geometry. The removal rate was approximately half of the coverage rate for equipment. The crew consisted of three

TABLE 2-24. ELEVATION 305' AREA ISC AND ELEVATION 347'-6" EQUIPMENT - STRIPPABLE COATING TEST PARAMETERS

Test Area	Test		Area (ft ²)	Dosimeter - Worker				Activity	Rate- Coverage/ Removal	Time (min)	Remarks
	Start	Stop		No. 1	No. 2	No. 3	No. 4				
El. 305' ISC	1540	1613	533	Start	260	195	197	Spraying strip coat	969 ft/ hr	33	One worker rotated in and out of air lock to reduce man- ren.
				Stop	587	511	417				
				Dose	327	316	220				
El. 305' ISC	1507	1549		Start	107	97	99	Strip coat removal	761 ft/ hr	42	
				Stop	323	261	257				
				Dose	216	164	158				
El. 347'-6" Equipment	1507	1520	174	Start	123	124	119	Spraying strip coat	790 ft/ hr	13	Only flange of head storage stand was strip coated.
				Stop	197	195	192				
				Dose	74	71	73				
El. 347'-6" Equipment	1431	1456		Dose	83	73	75	Strip coat removal	414 ft/ hr	25	

people. However, one individual was rotated in and out of the air lock to assist as required, thereby keeping the dose rate lower for the crew.

Three people were required for setup; two people for spraying, and three people for cleanup and removal of the material.

Summary of Specific Results. The results of the strippable coating test on elevation 305' are shown in Table 2-25. The results are presented as a separate test and as a combination test after low pressure flushing. The final smearable contamination levels and the DFs for the strippable coating test indicate that it produced 10^4 dpm/100 cm² of cesium, with DFs in the hundreds for floor surfaces. The rate of application is comparable to that of high pressure flushing with vacuuming to pick up water. The application/removal time for the strippable coating is also comparable to the high pressure flush with vacuuming. Exposure reduction factors (ERFs) for area dose rate reductions are not available because no measurements were taken. The low pressure flushing plus strip coating did produce substantial reductions and DFs in area readings, contact readings, and smearable contamination results.

The test on the equipment showed that both vertical and horizontal surfaces could be reduced by a DF of approximately 50 for comparable surfaces and levels of smearable contamination. It appeared that 10^4 dpm/100 cm² of cesium was the best result that could be achieved on equipment. From the photographs of the equipment horizontal surfaces, it is apparent that more aggressive techniques are required to remove corrosion and reduce smearable contamination to obtain 10^3 dpm/100 cm² for total cesium.

The values in Table 2-23 show that the coating will reduce surface contamination. The coating is waterproof except under direct, high pressure spraying conditions, and is fairly durable. It should not be used in areas where the temperature will approach 120 F.

TABLE 2-25. SUMMARY OF RESULTS OF ELEVATION 305' AREA ISC

<u>Test Area</u>	<u>Contact RDF</u>	<u>Swipe DF</u>	<u>Final Swipe Total Cesium (dpm/100 cm²)</u>
Elevation 305' ISC	8.8	111.1	6.45×10^4
Elevation 305' Area IV LP/ISC	35.9	302.3	6.45×10^4

The self-stripping coating could not be removed easily and is not recommended for use in TMI at the present time. It appeared that too much effort would be spent removing the coating. The strippable coating is easy to remove and would be suitable.

Visual Results--The photographs show the coating on the surfaces, removal of the coating, and the surfaces after the coating has been removed (see Photographs 30 and 31). The debris captured by the coating can be observed on the underside of the coating.

Radiation Levels--The coating reduced the beta radiation levels; as expected, however, the contact gamma radiation levels did not change. The residual contact gamma radiation indicates that the source level was fairly constant throughout the test.

Contamination and Recontamination-- The intermediate readings on the strippable coating, shown in Table 2-23, show essentially the same level of contamination on top of the coating as under the surface after the coating was removed. This appears to be the result of cross-contamination by personnel walking on the area prior to sample collection.

Technique Effectiveness--The technique results showed that the use of strippable coatings is an effective technique to reduce smearable contamination to approximately 10^4 dpm/100 cm² of cesium for the contamination levels observed on elevation 305'. If used following a water spray, the technique would "fix" loose debris to the coating for removal. The coating protects against recontamination while it is on the surface. The removal rate of the technique is approximately 800 square feet per hour. If a heavy traffic area is to be decontaminated using a strippable coating, consideration should be given to using a cheesecloth base and plastic "egg crate" support walkway on top.

Technique Efficiency--The results produced were the most effective on elevation 305'. On elevation 305' the task used approximately 100 mrem per 100 square feet of coverage and approximately the same for removal. The volume of waste was less from this technique than from the water spray. When working larger surface areas, the efficiency will improve since the mobilization and set-up time would be less of a consideration.

Mechanical Scrubber Test

General Summary of the Task

Technical Description. A mechanical scrubber test was conducted on elevation 347'-6". The purpose of this test was to:

- o Determine the effectiveness of decontaminating with an acid and with a detergent solution
- o Determine the decontamination rates for the chemical solutions and the
 - Quantity of waste generated
 - Productivity of the workers
 - Radiation level reduction
 - Man-hours and man-rem associated with the test

- o Determine the safety and the efficiency of the chemical solutions and the test.

The test was conducted in a different area from the one originally selected. The size of the actual test area was so small that an additional area further to the north also had to be designated as part of the new test area. Figure 2-17 shows the areas actually used for the mechanical scrubber test.

The original plan had an area set aside in the mechanical scrubber test area that would not be tested with the high pressure water floor scrubber. This would allow testing of both solutions on an area that had been flushed with low pressure, as well as a combination of low and high pressure. When the test area was moved, a portion of each test was conducted over low pressure flushed areas and both low and high pressure flushed areas. However, these sections were not well defined.

During the cleanup operation, prior to the start of the experiment, trash and waste were consolidated in a few locations on elevation 347'-6" and elevation 305'. The trash/waste storage area was located in one-half of the mechanical scrubber area. After the high pressure flushing was completed and prior to the mechanical scrubber test, the storage area and trash were relocated away from the test area. During the scrubber test, the solutions were dispensed on the floor, scrubbed, rinsed with a small amount of water, and wet vacuumed into a 55-gallon waste drum. Data acquisition was accomplished prior to and after the test.

Smearable Contamination Levels. The pre- and post-test smearable contamination levels are shown in Table 2-26. The average pre-test smearable level of Cs-137 was 2×10^5 dpm/100 cm². Post-test results averaged 5×10^3 dpm/100 cm².

Recontamination of the test area occurred after the high pressure test. The squeegee operator was observed moving debris and water back into the area after it had been high pressure flushed. When the trash was moved, the area under the storage and trash that had not previously been decontaminated was

TABLE 2-26. MECHANICAL SCRUBBER TEST - ELEVATION 347'6"

LP/H ² Area	Location	Surface	Pre-Test	Post-Test	Pre-Test	Post-Test	Pre-Test	Post-Test	Pre-Test Swipes-dpm/100 cm ²			Post-Test Swipes-dpm/100 cm ²		
			Area Gamma	Area Gamma	Contact Gamma	Contact Gamma	Contact Beta	Contact Beta	Cs-137	Cs-134	Sr/Y-90	Cs-137	Cs-134	SR/Y-90
AREA II MS (acid)	153	Concrete	-	-	110	120	160	64	2.89×10^5	2.89×10^4	1.44×10^4	2.22×10^3	LLD	LLD
	156	Floor	-	-	50	50	320	224	1.29×10^5	1.31×10^4	7.1×10^3	3.11×10^4	3.55×10^3	1.22×10^3
	93	↓	38	39	60	60	320	256	1.07×10^5	1.07×10^4	9.1×10^3	3.33×10^3	LLD	LLD
	96		39	40	80	80	256	288	1.42×10^5	1.22×10^4	1.13×10^4	2.66×10^3	LLD	LLD
	157		-	-	60	49	288	227	1.22×10^5	1.11×10^4	8.21×10^3	2.66×10^3	LLD	LLD
	152		60	60	50	46	160	109	1.6×10^5	1.44×10^4	1.44×10^4	1.78×10^3	LLD	LLD
AREA I MS (detergent)	99	Concrete	35	34	34	30	131	96	7.10×10^4	7.10×10^3	6.44×10^3	3.11×10^3	LLD	LLD
	155	Floor	-	-	32	29	154	99	7.77×10^4	7.55×10^3	8.88×10^3	2.44×10^3	LLD	LLD
	112	↓	-	-	50	44	224	51	5.77×10^5	5.55×10^4	3.11×10^4	4.22×10^3	LLD	1.33×10^2
	110		31	30	38	34	262	147	3.11×10^5	3.11×10^4	2.02×10^4	3.77×10^3	LLD	1.55×10^2
	154		-	-	60	60	352	256	1.98×10^5	1.93×10^4	1.18×10^4	2.2×10^3	LLD	2.64×10^4
	98		36	36	60	60	320	224	2.22×10^5	2.06×10^4	1.35×10^4	3.11×10^3	LLD	3.55×10^2

flushed with low pressure. As a result, the average post-test contamination for low/high pressure testing prior to the mechanical scrubber test was higher than the pre-test contamination levels for the mechanical scrubber test in the same area.

Degree of Uncertainty - Decontamination Effectiveness. Data acquisition was conducted before and after the test. Swipe samples were damp during post-test data acquisition; therefore, the results may not be totally comparable. The exact location of the boundary where low pressure flushing stopped and high pressure flushing began is not known. However, examination of the data negates the importance of knowing the exact boundary point because the final results are the same for the entire area in terms of contamination levels.

Waste Volume. The volume of waste generated during the test was governed partially by local requirements. Because the waste drum could contain only 35 gallons total prior to transfer to the radwaste section, only 33 gallons of water could be used during the test in both test areas.

One gallon of acid was used for test Area II MS and one gallon of detergent solution was used in Area I MS. To prevent excessive detergent foaming, the vacuum was spiked with a defoamer prior to the entry. The waste drum was also spiked with a neutralizer prior to the entry to ensure that the waste would be in an acceptable form when removed. Approximately 0.2 gallon of water per square foot of test area was used to rinse the chemicals from the floor surface to the vacuum.

Results - Expected Versus Actual. The results of the chemicals used in the mechanical scrubber were as expected. However, the DF was sufficiently large that it is questionable whether water used with the scrubber would have produced the same result as chemicals. The acid test produced the best visual and decontamination results.

The area dose rate was expected to decrease below the post-high pressure test results of 61 mrem gamma for Area II HP and 76 mrem gamma for Area III HP. When the pre-test mechanical scrubber test area readings were examined, however, they were approximately 35 to 40 mrem gamma, well below the previous survey. Because the trash and waste had been moved between the tests, it was concluded that the trash and waste storage area was a factor in the area reading source terms. The area readings for the post-mechanical scrubber test were the lowest observed on elevation 347'-6" and only slightly higher than those in the deep end of the refueling canal.

Equipment and Techniques. The mechanical scrubber test was conducted with a 20-inch Clark industrial scrubber with an automatic liquids dispenser. The detergent and acid solutions were premixed and used on the surface with a medium coarse buffer pad (no abrasives). The residue was flushed with <100 psi and vacuumed into a waste container. The pad was not changed between tests, although requirements dictated that it should have been changed (the spare pads were misplaced in the reactor building during the staging task). The residence time for the acid was significantly less than was recommended by the manufacturer.

Worker Radiation Exposure. The work exposure for the task was 5.45 man-hours and 0.424 man-rem. This was the lowest exposure rate for any of the elevation 347'-6" tasks. To accomplish the task, workers had to travel through elevation 305' and the open stairwell to reach elevation 347'-6". Even with travel through these high dose rate areas, the per hour dose rate for the task was 78 mrem gamma.

Safety. There were no safety problems associated with this task. The phosphoric acid was neutralized in the waste container, and no waste entered the drains as they were sealed and covered.

Worker Productivity. The rate of application with the mechanical scrubber was approximately 600 square feet per hour. This included cleaning and vacuuming the waste. Three crew members were required to operate the scrubber, lance, and vacuum. All equipment could operate simultaneously.

Summary of Specific Results. The results of the mechanical scrubber test are shown in Table 2-27. The results of the acid test reflect higher DFs in area, contact, and swipe data. The contamination was reduced to 10^3 dpm/100 cm^2 of cesium. Area readings in the range of 30 to 40 mrem gamma could be obtained if trash and waste storage is removed and the areas properly cleaned.

TABLE 2-27. SUMMARY OF RESULTS OF MECHANICAL SCRUBBER TEST

<u>Area</u>	<u>Area Dose Reduction</u>	<u>RDF (contact)</u>	<u>Swipes Total Cesium (dpm/100 cm^2)</u>	
			<u>Final</u>	<u>DF</u>
I MS	0%	2.2	7.9×10^3	21.9
II MS	2%	6.5	3.1×10^3	84.8

Visual Results--Photograph 32 shows the visual difference between the acid and the detergent solutions tests. Photograph 33 shows the difference between areas that were not scrubbed (Areas I MS and II MS). Photograph 34 shows the differences between Area II HP and II MS.

Contamination and Recontamination--Specific instructions were given and followed to keep recontamination to a minimum. The floor was not walked on prior to the post-data acquisition, and decontamination was sequenced to leave a clean floor that would not be recontaminated from an area of higher contamination.

Technique Effectiveness--It was established that the mechanical scrubber would produce 10^3 dpm/100 cm^2 after low pressure or high pressure flushing. What effect the detergent, acid, mechanical scrubber, and vacuum had on the overall effectiveness could not be computed or estimated.

Technique Efficiency--The technique efficiency would be improved if the same results could be produced without chemicals. The waste volume can be controlled using this technique so the total liquid waste volume is less than that of either low or high pressure flushing of surface areas.

Combinations of Decontamination Techniques

General Summary of Combinations of Decontamination Techniques

The Decontamination Experiment was designed to test various decontamination techniques and to test multiple techniques in sequence on different types of surfaces. The test sequence was designed to increase in severity as the techniques were applied. For example, low pressure flush with water was the first test conducted, and phosphoric acid applied with a mechanical scrubber was the final test in the sequence. The results were as expected; the more aggressive the technique, the higher the decontamination factor.

Specific Results.

Elevation 305'--Table 2-28 shows the results of the low and high pressure water flushing and strip coating on the horizontal surfaces. Each of the low and high pressure tests had various parameters of flow rate, pressure, and temperature. The strip coating was applied after low pressure flushing. The strip coating test in Area IV LP had the lowest smearable contamination measurements at 6.45×10^4 dpm/100 cm² of cesium. The less than optimum results for the tests of the high pressure flush of elevation 305' and other radiation sources distort the area reductions shown in the table.

TABLE 2-23. SUMMARY OF RESULTS - ELEVATION 305' LOW PRESSURE, HIGH PRESSURE, AND STRIP COATING TESTS
(Based on representative data points^a)

Area	Pressure (psi - est.)	Temperature (F)	gpm (actual/planned)	Area Exposure Reduction Factor/ % of reduction	Contact RDF	Swipe DF	Final Swipe (total cesium dpm/100 cm ²)
I LP	~500	Ambient	20/15	1.58/37	75.6	1.1	4.62 x 10 ⁶
IV LP	~400	110	17/15	1.37/27	28.0	2.4	8.19 x 10 ⁶
II LP	~900	118	23/25	1.16/14	6.9	42.0	4.71 x 10 ⁵
III LP	~900	96	23/25	1.33/25	65.5	2.8	6.09 x 10 ⁶
X HP	2000	Ambient	14/15	0.89/0 ^b	30.6	24.4	1.89 x 10 ⁵
XI HP	2000	120	20.5/25	1.05/5 ^b	26.7	39.6	9.2 x 10 ⁴
XII HP	6000	Ambient	24/25	0.85/0 ^b	30.8	3.7	1.42 x 10 ⁶
XII HP	6000	Hot	24/25	1.05/5 ^b	10.8 ^c	15.9	8.25 x 10 ⁵
Strip Coat	-	-	-	N/A	8.8	111.1	6.45 x 10 ⁴
I LP/X HP				1.42/29	238.9	26.9	1.89 x 10 ⁵
II LP/XII HP (Ambient)				1.05/5	40.2	18.9	1.42 x 10 ⁶
II LP/XII HP (Hot)				1.0/0	40.1	33.7	1.67 x 10 ⁵
IV LP/Strip				1.37/27 (from LP only)	35.9	302.3	6.45 x 10 ⁴

a. Due to location or observed procedure, certain data points are more representative of the technique used. These values are determined using the representative data only.

b. Because pre-test data are not believed to be indicative of actual contamination prior to flush, and other radiation sources are masking the decontamination results, these reduction factors are not representative of the technique used.

c. Wrong nozzle was used

Elevation 347'-6"--The results of low and high pressure flushing of the concrete floors and diamond plate on elevation 347'-6" are shown in Table 2-29. On the concrete floor, the best decontamination results were achieved using 6000 psi at 18 gpm. Diamond plate did not have decontamination levels comparable to concrete floor levels, suggesting that higher pressure may be necessary on diamond plate to produce the same results. Recontamination was evident at the higher flow rates and pressure, both in the data and in videotapes of the operation. Table 2-30 shows the data on various pressures used for elevation 347'-6".

Strippable Coating Tests--Strippable coating tests were accomplished on low pressure flushed areas, although they could have been conducted over areas that had been high pressure flushed as well. The strippable tests revealed that the coating removed considerable amounts of loose contamination. Because all the loose contamination was not flushed down the drains in the high pressure flush, the strippable coating would have been a good technique to reduce this residue. Also, as indicated in the high pressure tests, more semi-fixed contamination was removed from the surface than in the low pressure tests. The use of strippable coating after high pressure flushing would be appropriate to fix the contamination and produce lower contamination levels.

As for equipment, high pressure spray can produce excellent results if the technique is applied properly. As an alternative for some equipment and surfaces, however, strippable coating can be an excellent decontamination technique and a protective cover against recontamination.

TABLE 2-29. SUMMARY OF RESULTS - ELEVATION 347'-6" LOW AND HIGH PRESSURE
FLUSH OF CONCRETE FLOORS AND DIAMOND PLATE

Area HP	Pressure (psi)	Area Exposure Reduction Factor/ % of reduction	Contact RDF (representative) ^a	Swipe DF	Representative Data ^a	
					DF	Final Swipe
<u>5 gpm</u>						
III	2000	1.15/13	8.5	7.7	10.1	4.35 x 10 ⁵
II	4000	1.08/7.5	19.0	19.1	19.1	4.03 x 10 ⁵
IV	6000	1.27/21	9.0	37.0	37.4	1.44 x 10 ⁵
	Area IV diamond plate			4.6	4.6	4.49 x 10 ⁵
<u>15 gpm</u>						
I	2000	1.11/10	15.9	119.5	119.5	1.27 x 10 ⁵
	Area I diamond plate			10.7	10.7	5.69 x 10 ⁵
IX	4000	1.40/29	20.2	1.7	9.3	1.48 x 10 ⁵
VIII	6000	1.29/23	29.8	69.9	69.9	8.37 x 10 ⁴
<u>25 gpm</u>						
VII	2000	1.13/15	29.6	20.9	19.8	7.28 x 10 ⁵
VI	4000	1.32/24	30.5	18.0	37.6	3.44 x 10 ⁵
V	6000	1.23/19	23.1	44.9	44.9	8.70 x 10 ⁴
	Area V diamond plate			6.2	21.4	2.85 x 10 ⁵

a. Due to location or observed procedure, certain data points are more ideally representative of the technique used. Therefore, separate values have been determined based on these points only.

TABLE 2-30. SUMMARY OF RESULTS - ELEVATION 347'-6" LOW AND HIGH PRESSURE
FLUSH ON CONCRETE FLOORS

Area HP	gpm (actual/ planned)	Area Exposure Reduction Factor/ % of reduction	Contact RDF (representative ^a)	Swipe DF (representative ^a)	Temperature (F)	LP Flush (gpm/temp.)
<u>2000 psi</u>						
III	5/5	1.15/13	8.5	10.1	110	22.5/81
I	15/15	1.11/10	15.9	119.5	120	14/Amb.
VII	18/25	1.18/15	28.7	20.9	120	19/74
<u>4000 psi</u>						
II	5/5	1.08/7.5	19.0	19.1	94	14/Amb.
IX	14/15	1.40/29	20.2	9.3	89	13/92
VI	23.5/25	1.32/24	30.5	37.6	72	22.5/81
<u>6000 psi</u>						
IV	7.5/5	1.27/21	9.0	37.4	88	22.5/81
VIII	18/15	1.29/23	29.8	69.9	95	13/92
V	25/25	1.23/19	23.1	44.9	80	22.5/81

a. Due to location or observed procedure, certain data points are more ideally representative of the techniques used. Therefore, these RDFs have been determined using these points only.

Summary

The combination of techniques produced sufficient data to select the most effective and most efficient techniques, in combination or singularly, to decontaminate various types of surfaces.

Decontamination Technique Summary

General Summary of Low Pressure Technique

The results of the various tests in the low pressure flushing technique do not show any change in decontamination effectiveness due to water temperature changes. It should be noted, however, that the higher water temperatures desired were not reached during the test. The water pressure varied from 400 to 900 psi because the prime constraint was to hold the gallons per minute constant. The flow rate that yielded the best results was approximately 20 to 25 gpm with a nozzle that would allow approximately 60 feet of spray. This assumed that the spray would be used at some distance from the operator. The best low pressure DFs were on stainless steel surfaces. The DFs were large for low pressure flushing where there was a large amount of contamination and debris at the beginning of the test.

General Summary of High Pressure Technique

Lance Spraying. High pressure spraying with the lance produced excellent results on the cable trays. Reductions on the other types of equipment should result if the procedure is accomplished properly. Indications from the tests show that the higher the pressure, the greater the effectiveness. At 3000 psi, the pressure was not high enough to produce the same cleanliness that was produced at 6000 psi in training on various surfaces. To use the lance safely at high pressures, it must be handled by persons of large stature who can use their size and weight to resist the high forces. The pressure over 3000 psi at 7 to 12 gpm appeared to be the most effective.

Water Floor Scrubber. Operation of the water floor scrubber indicated considerable recontamination on surfaces that were not flushed after the machine was used. The optimum parameters for horizontal surfaces appear to be 6000 psi and 15 to 18 gpm. The nozzle size in the scrubber can change the results visually on the surface. The 15-degree nozzle appeared to be optimum for decontaminating the floor without removing the paint.

Mechanical Scrubber

The mechanical scrubber produced excellent results on painted concrete surfaces. Its use with high pressure or low pressure produced the same results, and it could be used after each technique and produce the same results. The mechanical scrubber used with acid produced the best decontamination results, while the mechanical scrubber used with detergent reduced contamination levels almost as much as the acid. To obtain the results shown in the mechanical scrubber tests, flushing and wet vacuuming to remove the residue are required. The 20-inch-diameter brush or pad at less than 200 rpm appears to be an optimum combination for the floor surfaces in the reactor building to prevent splatter.

The pad texture used in the test influenced the visual results in training. As a result, the medium coarse nylon pad was selected as the most appropriate. Abrasive pads removed a few mils of the paint surface in tests outside the reactor building; however, abrasive pads were not tested in the reactor building.

Strippable Coatings

The strippable coating test proved that it was a decontamination technique that could be used after a high or low pressure flush. The results showed generally lower contamination levels for the technique than high pressure spraying alone.

On equipment, strippable coating is approximately the same as high pressure spray at the pressures tested. Spraying 30 to 50 mils of ALARA 1146 at 2200 psi at 4 to 6 inches appeared to produce the best results. The self-strippable coating was not effective, as it was difficult to remove.

Summary

Table 2-31 shows the best results of the various tests on surfaces.

Decontamination Training Program

(Refer to Appendix D, Training and Safety, for details.)

Relationship of Training to Entry Planning

Training is the term applied to the portion of the entry planning process that occurs between the drafting of individual work packages and their performance in-containment.

The process of transition between the completion of training and actual work package execution is a smooth one, provided that:

- o Work techniques are developed prior to completion of a work package.
- o Work packages are written well in advance to allow adequate review.
- o Personnel are prescreened for training prerequisites prior to scheduling their training.
- o Training feedback to work package content is encouraged; this may require rescheduling of the work item if negative feedback is significant.
- o Adequate training time is set aside.

TABLE 2-31. SUMMARY OF VARIOUS TEST RESULTS

	<u>Waste (total gal/ft²)</u>	<u>Area % Reduction</u>	<u>Contact RDF</u>	<u>Swipe DF</u>	<u>Pre-test level (dpm/100 cm²)</u>	<u>Post-test results (dpm/100 cm²)</u>
Low Pressure (Area III LP - Elevation 305')	120/0.22	33	65.5	2.8	5.39×10^6	1.92×10^6
High Pressure						
Spin Jet (Area VII - Elevation 347'-6")	190.6/0.64	23	29.8	69.9	5.85×10^6	8.37×10^4
Lance (Cable Trays)	88/0.23	--	81.6	726	1.89×10^7	2.6×10^4
Mechanical Scrubber (MS 1I - Acid)	13/0.2	2	6.5	84.8	2.66×10^5	3.14×10^3
Strip Coat						
Floor (ISC - Elevation 305')	3.4 ft ³ (solid waste)	--	11.5	66.2	7.07×10^6	1.07×10^5
Equipment (Head Storage Stand - Elevation 347'-6")	1.1 ft ³ (solid waste)	--	9.7	1.6		8.3×10^4

Entry planning is enhanced and costs are minimized if the goals of the training program are achieved. The effectiveness of a training program is primarily judged in subjective terms. It relies heavily on the feedback from workers and supervisors during the debriefing process. If work is being accomplished on schedule and the problems listed previously do not occur frequently, then the program is a success. A follow-up system is necessary to identify and correct known deficiencies.

In order to maintain confidence and enthusiasm for the entry program, workers need to feel that their contributions toward policy changes are being incorporated.

Training Criteria and Effectiveness

The criteria for the completion of training were to:

- o Locate and adequately screen and qualify personnel for entry
- o Allow workers to safely execute each work package with minimal outside direction
- o Convey overall knowledge of containment conditions
- o Convey nonroutine exit criteria for job termination
- o Provide training for worker action in the event of an emergency
- o Train adequate backup personnel.

These criteria were achieved through a training engineer's control of the training program. The training program for the Gross Decontamination Experiment established standards for student knowledge with respect to:

- o Prerequisite qualifications

- o General knowledge of containment and procedures
- o Specific instructions for each work package
- o Specific training in site, radiological, and safety requirements
- o Worker feedback after job completion.

The program also established standards for instructors and command center task supervisors to enhance effectiveness. The program was administered by a training engineer, who performed an independent review of each work package. During training, the adequacy and clarity of work instructions were validated as workers practiced for the planned entries. During the Decontamination Experiment, the following types of problems occurred, and influenced establishment of the optimum training policy:

- o Underutilization of assigned decontamination personnel due to lack of approved procedures, work packages, and associated software
- o Underutilization of personnel due to restraints imposed by the remote reporter system (initially a 2-week limit)
- o Significant loss of training time to correct prerequisite qualifications or to complete decontamination personnel administrative requirements
- o Lost training time due to lack of equipment.
- o Retraining or training time extensions to complete the development of techniques
- o Frequent rescheduling of entry tasks due to shortcomings in the planning process

- o Failure to train enough individuals to provide backup personnel for specific tasks
- o Failure to train enough individuals in a variety of decontamination tasks such that maximum scheduling could be achieved
- o Repetition of work packages due to lack of generic packages to cover repeat tasks such as trash removal.

Summary of Training and Safety

Training. The purpose of training was to provide skilled manpower for the Decontamination Experiment who could perform specific tasks efficiently and safely. The methodology used for initiating the appropriate training program was to:

- o Define the scope of activities and assumptions
- o Determine the specific task list
- o Develop an hour estimate by task
- o Determine skills needed by task
- o Estimate doses for tasks
- o Estimate out-of-containment support hours
- o Develop a preliminary schedule for task execution
- o Determine total worker job-hours
- o Determine numbers of personnel required and make up a schedule
- o Plan for backup personnel and make up a schedule.

It should be emphasized that the vulnerability of a tightly scheduled, sequential set of procedures is the availability of trained personnel. The necessity of training backup personnel became apparent due to illness, changed tasks, and/or differences in planned and actual worker hours required for task performance.

There were several sources of manpower that were used to support the Decontamination Experiment:

- o Rad-con technicians
- o Maintenance department personnel
- o Building trades crafts
- o Utility employees from remote locations
- o Subcontracted technicians and engineers
- o Volunteers from the utility.

Personnel from these sources were screened to identify those who qualified for containment entry and work. Prerequisites for training and containment entry included:

- o Valid radiological work permit training
- o Valid whole body exposure records on file
- o Valid whole body count
- o Valid respiratory physical examination
- o Satisfactory respirator fit test

- o Valid thermoluminescent dosimeter reading
- o Valid security badge for access to work areas.

Only the remote reporters did not rely upon their parent department for supervision and personnel support functions. The remote reporters were assigned to a foreman, who fulfilled supervisory and administrative duties. The use of remote reporters allowed the operations to be conducted within the required time frame, although they imposed logistics problems. It was difficult to develop operations and training schedules based on the rotating labor pool arrangements (see Appendix D for a discussion of these problems).

Training was based on a training work package which is described in Appendix D. The training work package served as the written instructions for completion of a task. The packages had specific formats and could be revised by executing the revision procedure.

Training for the specific Decontamination Experiment tasks involved the following phases:

- o Technique development phase - techniques for specific tasks were developed, evaluated, and refined for training and operations.
- o Classroom phase - personnel were acquainted with work packages, areas of work, and safety procedures.
- o Walk-through phase - personnel were practiced in actual tasks to be conducted without protective clothing and in similar, but not identical, work areas.
- o Mockup phase - personnel were in simulated work conditions and conducted dress rehearsals of their assignments.

Briefings preceded and followed each training phase. The final training briefing preceded entry and execution of assigned work. Debriefing served as a method of determining accomplished work, evaluating techniques, and providing a feedback mechanism to the training program. Details of training equipment and aids are given in Appendix D. These descriptions include specific training aids, equipment, qualification programs, and procedures for operation/coordination throughout the training phases.

The training engineer was responsible for the administration of the training program through the use of approved standards. The efficiency of the Decontamination Experiment was reduced because of the use of more than one training engineer and the lack of a complete training program from the beginning. Although the quality of most in-containment work was high, the cost and program consistency could have been improved significantly by more thorough preliminary planning. The continuation and completion of training program development is a recommended high priority which will ensure a higher degree of success in the future.

Safety. The administration of the safety program was the responsibility of the GPU site safety supervisor, who was supported in a technical capacity by the GPU corporate industrial hygienist. During the Decontamination Experiment, several safety issues arose which required the issuance of new safety policies regarding work instructions, equipment, or training. Implementation of these policies was the responsibility of BNoC Project Construction. Relevant safety issues affecting the experiment included:

- o Heat stress of workers
- o Protection from falls
- o Access to remote work areas, including the polar crane
- o Personnel and equipment protection measures
- o Confined space requirements

- o Equipment lifting and handling
- o Fire protection

For a detailed description of safety issues, refer to Appendix D. For detailed organizational responsibilities, refer to Appendix E.

Contamination Control and Recontamination

Contamination Control

Contamination control for the experiment was limited to the sequencing of the decontamination activities from the highest point in the reactor building descending down to the lowest elevation involved in the experiment. During the original schedule, this would have resulted in the following sequence:

- o Polar crane - low pressure
- o D-rings, missile shields, refueling canals, RHSS, and refueling bridges - low pressure flush
- o Elevation 347'-6" - low pressure and high pressure flush
- o Open stairwell
- o Elevation 305' low pressure and high pressure flush
- o Mechanical scrubber test
- o Strippable coating tests

The actual sequence of the operation was:

- o Elevation 305' low pressure flush floor only

- o Polar crane - low pressure flush
- o D-rings, missile shields, etc. - low pressure flush all surfaces
- o Elevation 347'-6" - low pressure, high pressure flush floor, and equipment
- o Elevation 305' walls, overheads, and floors - low pressure flush
- o Open stairwell connecting elevations 305' and 347'-6" - low pressure flush
- o Elevation 305' - high pressure flush
- o Elevation 305' - low pressure reflush

The planned sequence appeared to be adequate, and it was expected that minimal controls would be required between some areas such as a bootie or "sticky pads" change.

However, when the actual sequence occurred, contamination problems were evident. The main problem was that there were no controls to isolate clean areas from contaminated areas. As a result, personnel moved to and from the air lock across clean to contaminated areas (stairs and upper levels) to accomplish decontamination. During the sequence where the upper elevations were being decontaminated to levels of contamination lower than elevation 305' and the open stairwell, personnel moved across the areas changing air samples, water hose lengths, and crews.

Debris and contamination from overhead decontamination operations occurred several times: (a) when the polar crane was flushed, contamination dripped onto elevation 347'-6" and the missile shields, refueling canals, etc., (b) when the low and high pressure activity took place on elevation 347'-6", debris came down through the floor grating onto elevation 305', (c) after the elevation 305'

overheads, walls, and floors were low pressure flushed, debris and water dripped for several hours, and (d) when the open stairwell connecting elevation 347'-6" with 305' was flushed, debris and water contacted walls, floors, and overhead surfaces on elevation 305'.

Because the walls (D-rings, outside surfaces, and liner) on elevation 347'-6" were outside the scope of work, contamination that was deposited on the walls (and what was already there) was not flushed. Contamination from the polar crane was deposited on the top of the D-rings, missile shield, refueling canal, and bridges; however, it was flushed because all these surfaces were flushed in this task.

Similarly during the open stairwell and elevation 347'-6" flushing, debris came down through the grating onto elevation 305'. In some cases, the amount of dirt and debris on the floor was so great that footprints could be seen in it. This contamination was tracked into areas that had been decontaminated to significantly lower levels.

The change in the sequence of decontamination work and lack of protection between areas to prevent the tracking of contamination caused extensive recontamination and increased contamination levels on the floor surfaces. In some cases, post-test data acquisition was accomplished prior to recontamination of the surfaces. In other instances, the recontamination took place during the operation or, as in the case of the polar crane, over a few weeks and during three distinct recovery operations tasks on the crane and equipment. Where visual records show personnel traffic on sample points prior to post-test data acquisition, the sample points were removed from the analysis. Where this could not be determined exactly, the sample point data was used in the analysis.

Recontamination:

All of the techniques caused some recontamination; however, the results varied greatly in how much of an affect the recontamination had on the data. Where recontamination was recognized by the decontamination crew and the area

where it was deposited was included in the scope of work, the recontamination was cleaned. Where recontamination was recognized by the crew in an area outside the scope of work (walls and equipment), it was not cleaned. Some recontamination was seen from the command center and corrected immediately. Personnel traffic was not rerouted but the problem was recognized and condoned. Some procedures did not allow for deviations in the work sequence or additions to the work scope; some controlling individuals or entry supervisors did permit deviations during the experiment and decontamination procedures while others did not. In some cases, the system did not have timely control procedures to rectify recontamination or to change the sequence of minor activities to prevent recontamination. The CCTV outages had an impact on some of the decontamination activity as the work could not be viewed in several areas (polar crane, refueling canals, bridges, and some areas of elevation 347'-6").

Low pressure recontamination resulted from water hitting angle iron braces, equipment, and protrusions with 25 gpm at 900 psi at close range (5 to 10 feet). The water and debris splashed and in some cases recontaminated areas that had previously been cleaned. Flushing from a distance worked well except from above the refueling canals where the dirt could not be directed to the drains and therefore dried on the floor surface.

High pressure spraying and water floor scrubber operations required additional flushing with low pressure to move the debris removed from the floor surface into the drains. Where the debris caused vertical or higher level surface contamination, flushing was required to remove it. In several cases this was not accomplished and contamination and radiation readings at the end of the test indicated activity added during the decontamination effort. Where overspray from high pressure lance operations contacted the floor or other equipment (especially dirty or corroded items), the debris had to be removed by low pressure flushing.

The strippable coating caused some recontamination when the waste was not handled properly. For instance, the cut strips had to be rolled up the correct way to keep contamination from falling on a "clean" surface. Coating that was

not removed from the floor would track on shoes and remain as hot spots. It became necessary to ensure all coating material was removed from the surface.

The mechanical scrubber had some splatter from brush or pad rotation that migrated to the walls. Flushing took care of this problem readily as it was easily recognizable.

Summary of the Problems

Contamination control is necessary in any decontamination activity. The sequence of the operations will not control recontamination; personnel and work procedures have to be established that will prevent recontamination of areas being decontaminated. Moving equipment and large tools through contaminated areas to support decontamination efforts at higher elevations has to be protected, or the equipment must be cleaned prior to placing it on clean surfaces. This is especially true if the hoist area is in an area where a great quantity of debris has been dumped or flushed and not cleaned.

Surface contamination spread to other areas and surfaces from the decontamination operations, if not cleaned, will add significantly to the area dose rate. This was apparent on elevations 305' and 347'-6", and on the polar crane. Readings were taken in several areas to try to determine what contribution this made to the area dose rate increase. Where significant contamination was removed from the floor (visual and data records) and the area dose rates increased, recontamination was evident on other surfaces.

Where data indicated recontamination, an effort was made in each case to determine the cause. These investigations showed that factors were involved such as:

- o Insufficient detail in procedures
- o Training identification of recontamination
- o Inappropriate equipment for the task

- o Technique parameters - over optimum pressure and flow rate
- o Inattention to the task
- o Supervision of the task

Gross decontamination of a reactor building requires attention to potential recontamination, stringent personnel control, and stringent controls on equipment usage and work areas to minimize the negative impact on decontamination efforts.

Organizations and Special Support Systems

Various organizations and special support systems not directly related to the decontamination experiment were, nonetheless, key elements necessary to its successful completion. Several organizations were responsible for the approval, planning, and funding requirements of the experiment. In addition, various onsite departments provided support operations essential to the execution of the various decontamination tasks.

Organizations

Organizational Responsibilities. Several organizations were responsible for the approval, planning, and execution of the decontamination experiment. The client, GPU, reviewed and approved all work scope, funding, and milestone schedules and all procedures, as well as controlling various safety and support operations. The Department of Energy (DOE) contractor, EG&G, was responsible for the proposal of research tasks and funding of the tasks approved. The technical planning and guidance organization, Bechtel National, Inc. (BNI), defined the data acquisition and program tasks and issued the Decontamination Tasks and Sequence Plan. The prime engineering contractor for recovery, Bechtel Northern (BNoC), provided the engineering for required support systems and technical guidance to the project construction group (within BNoC), who

executed the decontamination plan, including service and support systems. For a detailed breakdown of organizational responsibilities, approval and planning methods, and procedures for support operations, see Appendix E.

Organization Interfaces. With several organizations contributing to the decontamination experiment, the interactions between groups became complicated and, in some instances, slowed progress. During implementation of the decontamination efforts, some of the problems were recognized and adjustments made to correct the situation.

The funding and approval situation was awkward due to the imbalance of control. EG&G, as agent for DOE, had essentially unlimited federal resources for tests and experiments, while GPU had minimal resources for testing or recovery efforts.

BNI designed the tests and parameters and wrote the sample packages to define the functional criteria. Using these criteria, BNoC, in turn, procured and trained the personnel and executed the experiment. The flow through GPU from BNI to BNoC and back resulted in some administrative delays of weeks for even minor issues or changes. During the implementation of the experiment, a procedure was adopted by which verbal permission of both respective Bechtel supervisors sufficed to document concurrence to change the packages during actual operations.

All procedures were routed through the NRC. While the NRC requested that several changes be made in some work packages, it was essentially supportive of recovery work and decontamination efforts.

DOE was involved primarily from a generic, lesson-learned point of interest. Its responsibility was to provide input to a national energy policy. In general, items to be developed for DOE include:

- o Standards for prevention of additional accidents like TMI-2
- o Equipment standards evaluation and modification

- o Evaluation of design basis accident scenario credibility
- o Evaluation of existing radiation monitoring instrumentation capabilities
- o Development of better field monitoring instruments.

GPU departments were established for plant operations. As a result, during the recovery operations and experiment, nine departments, each having veto authority, were required to approve each work task procedure before it could be executed. Multiple review cycles occurred when revisions were made and had to be approved. The 20 Decontamination Experiment procedures and 8 Engineering Change Modifications (ECMs) required excessive time for review under this organizational structure. In addition, the structure of the procedures was not in the optimum configuration for easy review (i.e., the work packages contained too much detail). The result was a review process which consumed more man-hours than the task or the training. A large recovery operation, as demonstrated during the experiment, reflected the requirement for a different organizational structure than the one that currently exists, in order to be efficient during decontamination and recovery.

Special Support Systems and Equipment

Equipment. Several pieces of special equipment were brought into or installed in the containment as part of the support operations for the decontamination experiment. These items included:

- o Spider work platform
- o New radio system (partial)
- o High reach scissors lift work platform

- o Forklifts
- o Elevation 347'-6" lifting device

For detailed descriptions of these support items and their applications, see Appendix E.

Radiological Controls Department Support. The radiological controls department was responsible for compliance with regulations regarding radiation protection. Various groups within the department had responsibilities related to the decontamination activities. Radiological engineering was responsible for ensuring that exposure resulting from work done in radiation areas was as low as reasonably achievable (ALARA). Radiological field operations, through the use of rad-con technicians, were responsible for identifying radiological conditions throughout the plant and for providing radiological coverage when required by the RWP. Dosimetry was responsible for issuing and reading thermoluminescent dosimeters, tracking exposure history, and recording bioassay and whole body count results. Respiratory training standards were issued and respiratory devices were supplied and decontaminated by the respiratory protection group.

Unit II Operations and Maintenance Department Support. Operations and maintenance technicians and supervisors were provided on a per-task basis by a group coordinator for the Decontamination Experiment. The operations department, among other duties, operated the plant systems, controlled the issue of plant keys and procedures, and provided plant operators for the decontamination water and service air special operating procedures. Among the duties of the maintenance department were repairing or replacing plant system components, maintaining and improving the closed-circuit television system, and providing radwaste interim storage and disposal support.

Industrial Safety and Health Department Support. The safety department was responsible or assumed the duties for several safety requirements for the decontamination experiment. Among these duties were:

- o Screening incoming personnel for respiratory qualifications
- o Specifying safety requirements to support work packages
- o Administering the Heat Stress Control Program contained in Appendix D - Training and Safety, Attachment D-6
- o Publishing training standards and lesson plans for safety issues; providing or qualifying instructors to teach safety items
- o Supplying industrial hygiene equipment such as oxygen/combustible gas monitors
- o Providing paramedic upon request.

Support Costs: Equipment and Man-hours. The support operations costs for the decontamination experiment were broken down into material and labor costs. The man-hour and material costs were separated into actual and prorated amounts for the period September 1981 to April 1982. Actual costs are those that can be directly related to a given item. Hours and dollars spent toward training, clothing, dressing, data acquisition, lights, and trash removal cannot be related to a single item and therefore were prorated for each item. In some cases (the "Blue Goose" water pump for example), the client already owned the equipment, and the only material cost incurred involved repair and maintenance. Table 2-32 shows the breakdown of man-hours and labor and material costs for major support items. Figure 2-18 shows the ratio of nonmanual support man-hours to each hour of manual labor inside the containment versus the time for the duration of the experiment. It is important to note that heavy engineering support was needed up front but decreased as the experiment progressed. GPU,

HP, and operations support remained proportional to the number of hours of in-containment work through the course of the experiments. The figure emphasizes the expenditure of 5,660 man-hours in the period October 26 to December 18, 1981, in which no flushing was accomplished due to approvals not being received as scheduled. The figure also reflects the improved efficiency as more entries were made and less preparation work was required.

Figure 2-19 shows the man-hours, both manual and nonmanual, expended during the course of the experiment.

Reactor Building Radiation Levels and Environment

Intensity Maps

The two maps of elevations 305' and 347'-6" (Figures 2-20 and 2-21) show the post-decontamination radiation dose for various locations throughout the areas. These maps characterize the major areas involved in the experiment and help to identify high-level contamination spots. The rates are based on the survey taken on March 26, 1982, supplemented, in some cases, by data collected on May 13, 1982. Appendix C provides a more detailed reference of data points.

Comparison of Gamma Spectrometer Results with Radiological Results

Introduction. The SAI collimated gamma-ray detector scanned surfaces of the TMI-2 containment building floors and walls both before and after the decontamination experiment. The surface contamination at 10 locations (5 each) on elevations 305' and 347'-6" were measured in the scans. The pre-decontamination measurements were made on December 16, 1981, and February 16, 1982, respectively, for elevations 305' and 347'-6"; the post-decontamination measurements were made on March 25 and March 26, 1982. Most of the measurements showed contamination levels for Cs-137 that were less than $1 \mu\text{Ci}/\text{cm}^2$. A few areas showed levels that were below the minimum detectable limits. In some cases, the level of activity after decontamination was above that measured before decontamination.

TABLE 2-32. MAN-HOUR AND MATERIAL COSTS FOR SUPPORT

<u>Item</u>	<u>Man-Hours</u> <u>Actual/</u> <u>Prorated</u>	<u>Labor (\$)</u> <u>Actual/</u> <u>Prorated</u>	<u>Material (\$)</u> <u>Actual/</u> <u>Prorated</u>	<u>Total (\$)</u> <u>Actual/</u> <u>Prorated</u>
Spider	11,421/8,425	221,436/ 122,476	50,437/9,505	271,873/ 131,981
Decontamination water system (incl. orange duck water pump)	3,957/5,055	72,370/73,485	88,971/5,885	161,341/79,370
Water pump (blue goose)	873/460	15,793/6,680	870/513	16,663/7,193
Anteroom	1,593/1,072	25,366/15,588	12,224/1,197	37,590/16,785
Equipment and small tools			3,841	3,841
Wet/dry vacuum and cleaning unit			73,331	73,331
Gamma spectrometer	335/306	6,307/4,452		6,307/4,452
Total	18,179/15,318	341,272/ 222,681	229,674/17,100	570,946/ 239,781
Grand total	33,497	\$563,953	\$246,774	\$810,727

Summary. A great deal of difficulty was encountered when an attempt was made to correlate gamma-spectroscopic methods with other measurements, such as swipe and contact radiation data. For most of the points at which gamma-spectroscopic measurements were made, other types of data were not collected.

Several of the points analyzed by gamma spectroscopy were located in high traffic areas or in areas that would have become recontaminated during decontamination of surrounding surfaces, e.g., overspray from spin-jet operations. However, without other measurements at the same locations, the validity of gamma spectroscopic results cannot be substantiated or refuted. From the pre-decontamination survey, it can be established that the ratio of the areal activity distribution as measured by gamma spectroscopy to that estimated by contact measurements was 0.08. Analysis of the post-decontamination point (SAI designation 34) using the above ratio yields a projected contact reading of approximately 1650 mrem/hr, which is within the observed range of 1000 to 3800 mrem/hr. However, this is the only point where a rough comparison can be made, and general conclusions cannot be based on one point.

Clearly, the gamma-spectroscopic results are derived from a very small sampling within a large area having a great deal of heterogeneity. Therefore, it should not be surprising if unrepresentative results were obtained. Some of the apparent inconsistencies may be explainable when gamma-spectroscopic results and surface deposition analyses can be compared. The analytical results from deposition sampling reflect agreement with the RDFs obtained during the experiment for comparable points. At this point, there has not been an analysis of the gamma-spectroscopic and surface deposition results.

Reactor Building Environment: Analysis of Water Quality, Biological Activity, and Airborne Activity

Water Quality. The quality of the water used for decontamination of the reactor building surfaces during the experiment was acceptable compared to maximum permissible concentrations (mpc). Table 2-33 details both the concentration limits and the actual measured values in the decontamination water.

Boron concentrations in the water were at 87 percent of the maximum permissible. The boron concentrations were kept at a relatively high level in the event that significant concentration of fuel fines occurred due to the decontamination operations.

Chloride ion-concentration was one-half of mpc values. Tritium was approximately 77 percent of mpc value and was closely monitored in air and by bioassay to ensure that tritium mpc hours were strictly observed in the decontamination work force. The pH of the water used was acidic, approximately pH 5.

Specific radionuclide concentrations were generally a factor of 1000 less than mpc values. Table 2-34 lists specific isotope concentrations in the water plus those concentrations specifically regulated in the mpcs.

TABLE.2-33. GROSS DECONTAMINATION TEST WATER QUALITY

<u>Parameter</u>	<u>Concentration</u>	
	<u>Max. Allowance</u>	<u>Actual</u>
Boron	2000 ppm	1731 ppm
Chloride ion	2 ppm	1 ppm
Tritium	1.0 $\mu\text{Ci/ml}$	0.77 $\mu\text{Ci/ml}$
pH	≥ 7.5	4.83

TABLE 2-34. RADIONUCLIDE CONCENTRATIONS IN DECONTAMINATION WATER

<u>Radionuclide</u> ^a	<u>Concentration</u>	
	<u>Max. Allowance</u>	<u>Actual</u>
Cs-134	$1.0 \times 10^{-3} \text{ } \mu\text{Ci/ml}$	$2.3 \times 10^{-6} \text{ } \mu\text{Ci/ml}$
Cs-137	$1.6 \times 10^{-3} \text{ } \mu\text{Ci/ml}$	$2.6 \times 10^{-5} \text{ } \mu\text{Ci/ml}$
Sr-89	$8.0 \times 10^{-4} \text{ } \mu\text{Ci/ml}$	
Sr-90	$2.7 \times 10^{-5} \text{ } \mu\text{Ci/ml}$	$3.0 \times 10^{-5} \text{ } \mu\text{Ci/ml}$
Ce-58		$1.0 \times 10^{-7} \text{ } \mu\text{Ci/ml}$
Ce-60		$3.6 \times 10^{-7} \text{ } \mu\text{Ci/ml}$
Ce-144		$2.7 \times 10^{-6} \text{ } \mu\text{Ci/ml}$
Rv-106		$1.2 \times 10^{-6} \text{ } \mu\text{Ci/ml}$
Mn-54		$1.5 \times 10^{-7} \text{ } \mu\text{Ci/ml}$
Sb-125		$1.0 \times 1.0^{-6} \text{ } \mu\text{Ci/ml}$

a. With total activity not to exceed $3.5 \times 10^{-3} \text{ } \mu\text{Ci/ml}$.

In summary, the water quality was good. Only the concentration of tritium required specific monitoring in air and by bioassay during decontamination operations.

Biological Activity. No biological activity measurements were made in the reactor building during or following the decontamination experiment. Prior to draining the reactor building sump, a preliminary analysis was made of the biological activity in air and sump water.

The pre-decontamination biological activity data allowed several conclusions to be reached. First, there was significant microbiological activity in air, on reactor building surfaces, and in sump water. Second, microbiological activity was not dissimilar to that found in the natural environment, specifically river water. Opportunistic pathogens were identified but were not of concern as long as respiratory protection was used in the building. Waterborne microorganisms could potentially reduce the efficiency of the SDS, especially by chelating or metabolizing Se-90.

The biological activity in air and resuspendable from building surfaces will need to be reevaluated before respiratory protection is discontinued. It is possible that some surface decontamination procedures, especially those using inorganic chemicals, would reduce biotic titer on surfaces and, therefore, reduce the potential inhalation hazard from microorganisms in the building.

Airborne Activity Results. Table 2-35 summarizes air concentrations of Cs-136 (average BZA samples), tritium, and average dose during operations. Detailed information by day and hour is given in Appendix C.

Cs-137 was unchanged or slightly reduced by decontamination operations. There was no indication that Cs-137 levels in air were elevated during operations or that there was any significant difference in airborne Cs-137 activity among the various decontamination techniques. The average airborne Cs-137 value following the experiment was 4×10^{-8} $\mu\text{Ci/cc}$.

TABLE 2-35. AIRBORNE DATA SUMMARY

Data Acquisition Task	Surface Description	Technique	Task Description	Average BZA Cs-137 ($\mu\text{Ci/cc}$)	Average Tritium ($\mu\text{Ci/cc}$)	Average Dose (mrem/hr)	Average TLD
1	El. 305' floor	LP flush	Pre-decon	3.15 E-7	a	239.2	282.5
			Decon operation	3.27 E-8	3.4 E-6	472.9	396.7
			Post-decon	a	a	321.0	170
3	Polar crane	LP flush	Pre-decon	1.34 E-7	a	117.1	190
			Decon operation	8.04 E-8	8.28 E-7	130.9	a
			Post-decon	5.47 E-8	a	165.3	133.3
4	A & B D-rings, missile shields & refueling canal	LP flush	Pre-decon	3.05 E-7	4.5 E-8	246.7	293.3
			Decon operation	7.33 E-8	4.0 E-6	162.6	a
			Post-decon	1.82 E-8	5.4 E-7	166.0	a
	El. 347'-6" floor	LP flush	Pre-decon	2.66 E-7	a	196.9	226.8
			Decon operation	2.27 E-8	3.4 E-6	196.7	a
			Post-decon	1.31 E-7	3.0 E-7	148.6	172.5
	Equipment flush	HP spray	Pre-decon	1.82 E-8	5.4 E-7	166.0	a
			Decon operation	4.67 E-8	7.1 E-7	199.4	186.7
			Post-decon	2.57 E-8	6.1 E-7	201.6	a
	El. 347'-6" floor & equipment	HP spray	Pre-decon	2.57 E-8	6.1 E-7	201.6	a
			Decon				
			Areas 1,2,3	1.53 E-8	5.05 E-7	98.8	130
			Areas 4,5	2.63 E-8	1.95 E-6	156.2	a
			Areas 6,7	1.73 E-8	2.8 E-6	143.1	a
			Areas 8,9	2.11 E-8	2.3 E-6	135.1	153.5
			Post-decon	1.05 E-8	8.0 E-7	144.3	140
6	El. 305' floor	HP spray	Pre-decon	1.65 E-8	2.36 E-6	372.0	110
			Decon operation	3.74 E-8	2.7 E-6	372.8	350
			Post-decon	1.22 E-8	a	346.5	274
4	El. 347'-6" floor	Floor scrub	Pre-decon	6.5 E-9	a	320.6	122.5
			Decon operation	1.63 E-8	a	77.5	116.7
			Post-decon	9.65 E-9	a	163.1	a
5	El. 305' floor	Strip coat	Pre-decon	6.5 E-9	a	320.6	122.5
			Decon operation	8.8 E-9	a	236.7	380
			Post-decon	7.35 E-9	a	224.8	250
1	El. 305' Floor	LP re-flush	Pre-decon	1.31 E-7	a	148.6	175
			Decon operation	7.8 E-8	4.47 E-6	408.8	381.7
			Post-decon	1.65 E-8	2.36 E-6	372.0	110

a. Not available.

Tritium in air was increased by a factor of 10 or less during decontamination operations. This was due primarily to the concentration of tritium in the water used for operations. The higher tritium values made it necessary to keep track of mpc hours for workers during flushing operations in order to ensure regulatory compliance. Following flushing operations, tritium returned to the pre-experiment levels, averaging approximately 10^{-6} $\mu\text{Ci/cc}$.

In summary, decontamination operations reduced airborne particulate activity and increased tritium only temporarily. It could be expected that the reduced airborne particulates would be sustained through time. Tritium levels could be reduced as airborne water and vapor are reduced following the termination of the experiment.

Surface Deposition

The purpose of this task was to obtain surface and subsurface samples of floor, wall, and equipment areas inside the reactor building before and after decontamination tasks. Samples were taken at varying depths and analysed in order to determine the extent and characterization of contamination inside the containment for evaluating the effectiveness of the decontamination efforts. Samples were collected with the surface deposition sampler shown in Appendix A. The sampler is a drill with an enclosed housing and attached vacuum unit. With this device, core samples can be obtained at various depths determined by the adjustment controls provided on the unit. Sampling locations are shown in Appendix A.

The data on surface deposition from the Gross Decontamination Experiment are included as Appendix A.

The results of the surface deposition DFs are shown where comparable test points are located with test points for the Gross Decontamination Experiment low/high pressure flush tests.

<u>Area</u>	<u>Surface Deposition DF</u>	<u>Experiment RDF</u>
Elevation 347'-6"		
II	13	19
V ₁	20	23
V ₂	9	10
VII	16	29
VIII	29	30
Elevation 305'		
IV	15	36

From Tables A-1 and A-2 in Appendix A, it is observed that surface activity for those locations where bore holes were made at various depths is relatively constant. Since the depth of the hole does not affect the activity, the activity must be within the initial layer. Most bore holes were at least 40 mils, which indicates that the majority of the contamination is within this 40-mil layer. Additionally, the agreement between DFs for surface deposition and contact is very good. The computation of these factors implies little or no self shielding of the beta. Hence, if the contaminate was not near the surface, these DFs would vary widely.

The DF data in Tables A-15 through A-17 for horizontal surfaces indicate an average DF of 6 to 25. This agrees well with the direct comparison data of 9 to 36. It seems reasonable to conclude that, generally, a DF of 10 or more was demonstrated.

Loose Particulate Contamination

Elevation 305' (44 samples)

<u>DFs</u>	<u>Vertical Surface</u>	<u>Horizontal Surface</u>
Low	0.07	0.7
High	26.0	80.0
Average	4.3	25.0
Medium	1.7	29.0

Elevation 347'-6" (34 samples)

<u>DFs</u>	<u>Vertical Surface</u>	<u>Horizontal Surface</u>
Low	0.4	4.0
High	1.6	29.0
Average	0.8	13.8
Medium	0.8	16.1

Elevation 367' (8 samples)

<u>DFs</u>	<u>Vertical Surface</u>	<u>Horizontal Surface</u>
Low		1.0
High	(One measured point)	15.0
Average	2.0	6.3
Medium	---	2.0

The overall results reflect that the radioactive activity is located in the paint and does not penetrate below approximately 40 mils. In addition, the remaining amount of debris on the surfaces, as determined by the surface deposition and the experiment, are relatively the same.

Figure 2-1. Elevation 305' low pressure flush — planned.

Figure 2-2. Elevation 305' low pressure flush — actual.

Figure 2-3. Data acquisition survey locations – elevation 305' low pressure, high pressure, and strippable coating tests.

Figure 2-4. Low pressure flush of polar crane.

Figure 2-5. Diagram of dome area/polar crane — data acquisition locations.

Key:

- * Area reading
- A** Air sample reading
- T** Teletector reading

Plan El. 426'-0"

Figure 2-6. Diagram of polar crane - data acquisition locations.

Figure 2-7. Data acquisition locations — elevation 347'-6" D-rings and missile shield areas.

Key:

* Area survey

□ Horizontal surfaces

○ Vertical surfaces

A Air samples

Plan El. 347'-6"

Figure 2-8. Data acquisition locations — refueling canal and service structure.

Figure 2-9. Data acquisition locations — fuel handling bridge.

Figure 2-10. Elevation 347'-6" low pressure flush - planned.

Figure 2-11. Elevation 347'-6" low pressure flush - actual.

Figure 2-12. Elevation 347'-6'' planned data acquisition locations — low pressure and high pressure flush.

Figure 2-13. Elevation 347'-6" high pressure flush - planned.

Figure 2-14. Elevation 347'-6" high pressure flush - actual.

Figure 2-15. Elevation 305' high pressure flush – actual.

Figure 2-16. Elevat on 305' high pressure flush — planned.

Figure 2-17. Mechanical floor scrubber area — elevation 347'-6".

Figure 2-18. Plot of total man-hours per hour in containment versus time.

Figure 2-19. Plot of man-hours expended versus time.

PHOTOGRAPH 1

PHOTOGRAPH 2

ENTRY 12 1-8

PHOTOGRAPH 3

ENTRY 12 1-21

PHOTOGRAPH 4

ENTRY 12 1-30

PHOTOGRAPH 5

ENTRY 12 1-5

PHOTOGRAPH 6

PHOTOGRAPH 7

PHOTOGRAPH 8

PHOTOGRAPH 9

PHOTOGRAPH 10

ENTRY 56 AREA 9-21

PHOTOGRAPH 12

ENTRY 56 AREA 7A-2

PHOTOGRAPH 13

ENTRY 56 AREA 7A-1

PHOTOGRAPH 14

ENTRY 56 AREA 7A-14

PHOTOGRAPH 15

ENTRY 56 AREA 7B-4

PHOTOGRAPH 16

PHOTOGRAPH 17

ENTRY 56 AREA 12C-5

PHOTOGRAPH 18

ENTRY 56 AREA 12A-5

PHOTOGRAPH 19

PHOTOGRAPH 20

ENTRY 56 AREA 12A-28

PHOTOGRAPH 21

PHOTOGRAPH 22

ENTRY 56 AREA 12C-2

PHOTOGRAPH 23

ENTRY 56 AREA 12C-3

PHOTOGRAPH 24

ENTRY 55 STRIPPABLE COATING TEST - 1

ENTRY 55 STRIPPABLE COATING TEST - 17

PHOTOGRAPH 26

ENTRY 55 STRIPPABLE COATING TEST - 30

PHOTOGRAPH 27

ENTRY 55 STRIPPABLE COATING TEST - 40

PHOTOGRAPH 28

ENTRY 55 STRIPPABLE COATING TEST - 43

PHOTOGRAPH 29

ENTRY 56 AREA 7A-7

PHOTOGRAPH 30

ENTRY 55 STRIPPABLE COATING TEST - 39

PHOTOGRAPH 31

ENTRY 56 AREA 7C-11

PHOTOGRAPH 32

ENTRY 56 AREA 7B-2

PHOTOGRAPH 33

ENTRY 56 AREA 7B-1

PHOTOGRAPH 34

DO NOT MICROFILM
THIS PAGE

ANNEX

3.0 CONCLUSIONS

Decontamination Experiment Effectiveness

The effectiveness of the Decontamination Experiment with regard to the objectives established during planning is summarized below:

- o The effectiveness of several decontamination techniques was established, and optimum techniques and technique parameters were selected for various surfaces and circumstances.
- o The efficiency of the decontamination technique was established.
- o Decontamination training and procedures were documented and evaluated.
- o Various decontamination equipment was evaluated and its effectiveness documented.
- o Support systems and organization for the experiment were documented and evaluated.
- o The safety of the experiment equipment techniques and plan was documented.
- o The contamination levels were reduced in some locations during the experiment, but some areas were recontaminated because of technique or procedure.
- o Radiation from other sources on both elevations masked the contamination reductions achieved during decontamination of several test areas.

- o The area dose rates were not reduced 70 to 150 mrem in the test areas in the reactor building, as was planned.
- o Information was obtained to facilitate generic decontamination planning, in addition to planning for TMI - Unit 2.
- o Radiation monitoring results and mapping of the area were partially accomplished for the experiment.
- o Sufficient data were generated by the experiment to provide the basis for several follow-on studies of subportions of the experiment.
- o The effectiveness of the Decontamination Experiment was decreased by the changes in work scope and basic criteria in contamination control.
- o A continuing decontamination effort will reduce the area dose rates in the reactor building.

Decontamination Effectiveness

In general, the decontamination factor (DF) was dependent upon the water volume applied per unit area, the type and orientation of the surface, and the nature of the existing contaminants.

Figure 3.1 shows a graph of DF versus the water volume per unit area (gal/ft²) for floor surfaces on elevations 305' and 347'-6". Rationale for the results shown are discussed below.

Most of the debris on elevation 305' was contaminated dirt. Low pressure flushing was effective in removing this loose material. Therefore, the DF, as calculated, is influenced by removal of the dirt as well as contaminants on the surface. From the graph it is clear that after sufficient water has been applied to cover the surface, the DF rises very rapidly and becomes almost

independent of the quantity of water applied per unit area. This result is expected because once there is sufficient water to move loosely adhering material, the necessity for excess water diminishes. Furthermore, too much water is operationally difficult to control and can result in recontamination of treated surfaces.

The intermediate curve represents the effect of high pressure flushing on floor surfaces that have been successfully treated with low pressure flushing. It is seen that the effect of increasing water volume per surface area decreases substantially, but is still greater than observed on elevation 347'-6". This probably arises from the fact that the low pressure flush on elevation 305' was not totally effective in removing the large quantities of debris, so that further removal was achieved by high pressure flush. The intermediate curve and the lower curves indicate that an optimum value exists for the volume of water applied per unit surface area.

The lower curve represents the effect of combined low pressure/high pressure flushing on the floor surfaces of elevation 347'-6". Note that DFs are lower than those of elevation 305'. Since these data were obtained after a combined low pressure/high pressure treatment and, presumably, the loose debris on elevation 347'-6" was considerably less than that on elevation 305', the removal rate appears to become controlled by dissolution rates and probability of removal of embedded material by the water stream rather than by gross removal of loosely adherent debris. It is seen that for conditions existing on elevation 347'-6", DFs greater than 30 were not achieved by the techniques used.

DFs are less dependent upon pressure and flow when considered separately. It was clear that low flow rates at any pressure were less effective than higher flow rates, simply due to the lack of sufficient water volume to remove contamination from the surfaces. Conversely, high flow rates with high pressures caused problems on horizontal surfaces because of the inability of operators to properly direct the water to drains and the attendant mist that

recontaminated cleaned surfaces. It appears that 15 gallons per minute at 6000 psi is the optimum flow rate that can be accommodated on horizontal surfaces.

No significant effect of water temperature can be established from this experiment. Cesium compounds are very soluble, and increased water temperature would be expected to increase their dissolution rates. Because of operational characteristics of the in-line water heating system, the actual hot water temperatures were difficult to maintain at constant values. This problem, coupled with the inherent large solubility of cesium, made it impossible to conclusively establish the need for hot water.

All data used in preparing Figure 3-1 resulted from tests in which the water was removed from the area by using squeegees to direct the wastewater to floor drains. Potentially different results would have been achieved if the excess water had been removed by a wet vacuum system. Such an approach would have at least minimized the problem of recontamination due to misdirection of water.

It can be concluded that the decontamination of vertical surfaces proceeds somewhat differently from that of horizontal surfaces. Vertical surfaces, of course, do not generally have debris embedded in their surfaces as do floors. Beyond that, DFs observed on vertical surfaces were also higher than those observed on some horizontal surfaces. The toe of the curves shown in Figure 3-1 is anticipated to be very short, since the water volume per unit area required for run off is considerably less than that for horizontal surfaces. Additionally, as a vertical surface is flushed from top to bottom, the buildup of water flowing down the surface increases the volume per surface area and is effective in the elution of solubles and transport of particulates. Such elution and transport are not so readily achieved on horizontal surfaces.

It was found that stainless steel surfaces exhibited much higher DFs than concrete and carbon steel surfaces, which were about the same. Such results are expected based upon the relative porosity of the various surfaces. Even in

the case of stainless steel, however, much larger DFs were observed on vertical surfaces than on horizontal ones, e.g., 110 versus 31 on the walls and floor, respectively, of the shallow end of the refueling canal.

Decontamination Techniques

Mechanical scrubbing techniques are effective in reducing smearable contaminant levels. The use of chemicals (detergent and phosphoric acid) on a limited scale posed no difficulty in their collection for subsequent waste management activities.

Wet-vacuum collection of the liquids may also have been partially responsible for the success of this technique, but this point remains to be evaluated.

Strippable coatings yielded large DFs (approximately 300), based upon smear sampling results.

When dealing with floor surfaces, it appears that low pressure flushing is not a prerequisite to high pressure cleaning unless a great deal of loose debris has to be removed.

From the data obtained, there is no apparent correlation between RDFs determined by contact readings and those DFs obtained from swipe data. This indicates that the removal of loose contaminants from a surface may or may not influence the amount removable in a swipe sampling process. However, there was a correlation between the RDFs determined by contact readings and surface deposition DFs.

The conclusions regarding decontamination effectiveness and efficiency are summarized in the decontamination logic diagram (Figure 3-2).

The abrasive technique shown in the logic sequence for stainless steel surfaces is necessary to remove contamination from the surface milling marks,

where it is not sufficiently reduced by low pressure flushing. It has been concluded that another technique, such as chemicals or abrasive blasting, would be required to obtain the same decrease in level of contamination that were obtained by the mechanical scrubber on the horizontal surfaces.

Decontamination Control and Surveillance

The results of the Decontamination Experiment indicated that:

- o Sequencing of decontamination activities to take into consideration gravity flow and location did not prevent recontamination.
- o Planning and implementation of control of personnel, equipment, and work areas are necessary to prevent recontamination, even during gross decontamination activities.
- o Step-off pads, sticky pads, and barriers are required in a contamination control program.
- o Testing various parameters of the basic decontamination techniques produced a large amount of recontamination of surfaces. Where pressures and flow rates were above the optimum range for the technique, adjacent or additional surfaces were contaminated or recontaminated by overspray or inadequate flushing.
- o Surveillance of the area and surfaces being decontaminated during and after the effort is necessary to determine the effectiveness of the decontamination effort. If there is a problem in effectiveness detected that can be readily rectified by changing the decontamination technique, procedure, or equipment, the change should be accomplished as soon as possible.

The detection method, authority to change generic procedures, and the team of required specialists should be available to coordinate the change. Some of this can be accomplished in preplanning the effort by including decision points and optional techniques, but during the activity some mechanism must exist to accomplish minor changes.

- o Personnel traffic from the air lock to various areas of the reactor building caused recontamination of surfaces where there was a significant difference in contamination levels between areas traveled.
- o High pressure spray activity with the lance and water floor scrubber caused contamination of other surfaces. Procedures should contain provisions for an adequate flush after high pressure activity, and the pressures should be constrained sufficiently to reduce contamination overspray and debris splatter.
- o An insufficient amount of time was spent with the decontamination crews in training on the recontamination problem, i.e., how to recognize it and the corrective actions to be taken during decontamination activities.
- o Equipment different from that required by the procedures was used during some of the tests, which resulted in recontamination.
- o Where an effective contamination control program was outside the scope of the experiment, its absence had a direct impact on post-test data. In some cases, it could not be determined if the lack of success of a test was due to recontamination or to an inadequate technique whose parameters were inadequate to remove contamination.
- o Contamination control of personnel leaving the containment and the areas outside the reactor building was excellent. Only three or four

cases of small area surface contamination occurred on individuals, and these were due to glove punctures or small items contacting the skin during undressing. The low incidence of personnel contamination can be attributed to the procedures and dedicated dressing and undressing assistance.

- o Sampling locations and procedures to locate hot spots during surveillance operation should follow PNL-SA-10433 TRANSTAT series publications as a guide to ensure adequate sampling of the areas.
- o CCTV in the command center allowed the work to be closely monitored in the reactor building. However, the poor radio communication and limited number of radios did not allow effective redirection of work when problems were observed in the decontamination work. Only the simplest of problems that required only a few words over the radio were resolved.

Support Systems and Organization

Operational problems with radios (e.g., too few radios, inoperative equipment, poor transmission quality) caused a significant increase in the number of man-hours spent in the containment and decreased the effectiveness of the decontamination tasks and data acquisition.

The amount of radwaste in the reactor building made it difficult to reduce radiation dose levels. Since solid waste cannot be effectively cleaned within the reactor building and it significantly increases dose rates, it should be removed from the containment. Improvements should be made in removing the radwaste to reduce the dose rates and allow decontamination of the areas around the storage, waste, and trash in the building.

Decontamination equipment and facilities outside the reactor building did not support the test effectively. For example, without a small tool decontamination capability additional tools were needed, which increased expenses, added waste volume, and created storage problems within the reactor building.

During a major decontamination task, personnel assigned solely to the task are required to support the organization controlling the entries and operations. Operational procedures require interfacing several disciplines and crafts. Therefore, it proved cost-effective to dedicate a group of workers who could respond quickly to specific operational requirements and to short-notice changes. The group of laborers who formed this support for the controlling organization accomplished the following tasks:

- o Provided general and specialized training on hoists, forklifts, and high lift/reach equipment items
- o Moved material among staging areas, anteroom, and the reactor building
- o Decontaminated the anteroom and air lock on a frequent basis
- o Prepared equipment for the entries
- o Functioned as a quick-response rescue team
- o Provided dress in/out support for the decontamination crews
- o Participated in the entry program within their quarterly and yearly dose limitations.

The lack of timeliness in the installation of some support systems caused lost work effort. As a result, work that had been scheduled but which could not be performed had to be accomplished at a later time, thereby causing additional training and support costs.

The site organization was not the optimum for performing recovery operations. The forced rotation of key personnel, especially remote reporters, during the experiment caused loss of continuity and reduced worker productivity. There was some redundancy in procedures that resulted in excessive coordination and some administrative delays, which impacted the entries. A large number of procedures were required to be understood by all personnel involved in the experiment. These could be reduced to a manageable number with a streamlined organization focused on recovery.

Except for the radios, test equipment functioned adequately.

Preventive maintenance is required on decontamination equipment such as water floor scrubbers, lances, wet vacuum systems, and high pressure pumps for efficient utilization on a routine basis.

Equipment purchased from commercial vendors may not be suitable for efficient or reliable operation in the harsh reactor building environment without modifications. Therefore, these items should be evaluated and modified in a timely manner.

The personnel dosimetry system must be responsive to operational activities. If a simple entry plan requires little change, the dosimetry system need not be on a real-time basis. As the dose limitations for workers are approached, it is imperative that a real-time dosimetry system is available. This ensures full worker utilization without excessive dose commitment. Delays in personnel dosimetry system response and procedures resulted in delaying the start of entries, in crew changes at the last minute, and in substitution of personnel between high- and low-dose-rate tasks. The dosimetry system was not responsive to the entry program and limited the frequency of entries. Quality control of a computerized system used for dosimetry is a necessity. Errors in records did occur and one individual had to be dedicated to quality control of dosimetry at the operations area.

Radiation work permits (RWPs) were not processed sufficiently in advance of entries, and the required approval cycle resulted in entry delays.

Distribution of data acquisition information included organizations that did not need the data and omitted some that required it. As a result, data management changes occurred in order to improve the efficiency and effectiveness of the system. The experiment required a dedicated individual to obtain the data and ensure the accuracy and coordination of organizations providing data and analysis.

An insufficient number of equipment items such as radios, MSA masks, ice vests, and safety harnesses reduced the efficiency and flexibility of activities during the experiment. The correct support requirements must be forecast in order to have sufficient numbers of equipment available. Training, decontamination, and in-containment requirements must be considered at one focal point.

Decontamination Training

Training must be completed to rigorous standards.

Some training deficiencies occurred due to equipment shortages for training and poor instruction. During a few of the later entries, training occurred just prior to the scheduled entry. As a result, there was no time for a review of training effectiveness. This schedule left the discovery of deficiencies to the task supervisor during the actual entry.

An insufficient number of backup personnel were trained; as a result, considerable scheduling flexibility was lost. The number of crew changes for sickness, absenteeism, accidents, and other incidents for each entry was underestimated. One backup for every four crew members (laborers and crafts) performing decontamination work was shown to be optimal.

The following tasks have to be accomplished before engaging personnel in training and decontamination operations:

- o All training equipment should be available and operationally ready, and a suitable work area should be dedicated for training.
- o Techniques and procedures should be proven and equipment tested before any training occurs.
- o All work packages must be reviewed and approved by training personnel, radiological staff, and crafts supervisors.
- o An adequate training staff must be provided.

Lesson plans for training can consist of work packages operation and qualification packages.

Work packages should be in an approved format and contain at a minimum:

- o Prerequisites for the task
- o Work instructions
- o Signoff instructions for completion
- o Equipment required
- o Work techniques required.

Work packages contained too many administrative and procedural items not associated with the actual work procedures. Fluctuation of these items caused excessive time spent in administrative approval channels, and many time delays that could have been avoided resulted from minor changes in techniques or

technical equipment. Items such as man-rem estimates, radiological characterization information, technique sheets, RWPs, and 4045s should be appended to work packages as references, not included within them.

One individual should be responsible for training and should have a support staff to conduct the training, document the training completed, and provide verification of certification for those individuals who will enter and work in the reactor building.

Decontamination Criteria

Gross Decontamination Goals and Criteria

The goal of gross decontamination is to remove the bulk of relatively loose and readily soluble contaminants, thereby reducing radiation levels and resuspension of contaminants. The reduction in the smearable contamination level was expected to be to 10^5 dpm/100 cm² of Cs-137, and work area dose rates would be reduced by 70 to 150 mrem gamma. Attainment of these levels would reduce the inhalation hazard as well as reduce overall exposures for work within the reactor containment building.

To accomplish the goal of gross decontamination, several criteria and restrictions are imposed on the activity:

- o Water will be the main decontaminating agent used.
- o The techniques must have been previously demonstrated in tests in the reactor, auxiliary, or turbine building.
- o The techniques will not impair or jeopardize the capability of the facility, component, or structure to perform its operations and safety function.

- o Techniques and reagents should be compatible with NSSS component materials to avoid excessive degradation of such components.
- o The use of chemicals will be prohibited where the effluent may impair operation of the submerged demineralizer system (SDS).
- o The sequence of activity will be based on the first 13 steps of the Gross Decontamination Plan (Reference 1).
- o Sequencing of the decontamination activity will employ gravity flow as the primary method of contamination control.
- o Extensive man-hour and man-rem associated activities which do not contribute to general area dose rate reductions will be avoided.

The level of 10^5 dpm/100 cm² of Cs-137 for gross decontamination is obtainable by the optimum techniques demonstrated during the Gross Decontamination Experiment. During the experiment, contamination equal to or lower than 10^5 dpm/100 cm² of Cs-137 was achieved on some floor and vertical surfaces, equipment, and cable trays.

Not all equipment and surfaces reached the desired level, because of recontamination or ineffective technique parameters used during the test.

Recontamination was a major problem, and the gravity flow principle and sequencing of the effort should be augmented by stringent controls on the movement of people and equipment through areas of varying contamination levels. Insufficient controls prevented several areas from maintaining the desired goal.

The sequencing of decontamination activities was changed from that in the plan, which established a logical approach to decontamination. By not following the established sequence, and without stringent controls on personnel movement and work areas, recontamination occurred. This will necessitate

duplication of effort and extensive reaccomplishment of some decontamination activities, such as on the polar crane and the elevation 305' floor and wall surfaces.

Reduction of area dose rate by 70 to 150 mrem gamma is possible in a gross decontamination effort; however, it was not generally attained during the experiment for the following reasons:

- o The scope of work did not include decontaminating adjacent surfaces or equipment, which contributed to the final area dose rate.
- o Storage areas, trash, and waste stored within the building contributed to the area dose rate. When one storage area was moved during the experiment, the area dose rate decreased approximately 50 percent below post-decontamination data acquisition values (30 mrem decrease). Rusted and corroded defueling tools, chains, gang boxes, and equipment not decontaminated to the levels of the floor surfaces added significantly to the area dose rate. The reactor building dose rate can be reduced by removing the trash and waste from the reactor building.
- o Areas under equipment, protrusions, or congested areas were not decontaminated to the same level as the floor surfaces during application of high pressure spraying with the water floor or mechanical scrubber. As a result, there are a number of areas under equipment that exceed the contamination and contact radiation levels reached during the decontamination of the floor surfaces. This contributed to the area dose rate and impacted the anticipated decontamination results.

- o Other source terms which contribute to area dose rates and affect the decontamination results in terms of area dose rate reductions are:

- The dome area
- LOCA ducts
- Inside area of the D-ring
- Reactor head service structure
- Reactor coolant system associated piping
- Elevation 282'-6"
- Enclosed stairwell and elevation shaft areas
- Incore instrument seal table.

Eventually, some of these sources can be shielded, decontaminated, or removed from the reactor building. The contribution of these sources to the area dose rate is not known and is not within the scope of this report.

The lowest area dose rates achieved in the Decontamination Experiment were: (a) 30 to 40 mrem gamma on elevation 347'-6", which resulted in a total of 75 to 80 mrem hours for work activity on that elevation, including transiting elevation 305' and the open stairwell, and (b) 18 to 25 mrem gamma in the refueling canal deep end. The refueling canal is stainless steel and isolated from the reactor and elevation 282'-6". Without the influence of other source terms, area readings of at least 18 to 25 mrem can be obtained during gross decontamination. However, the decontamination activity must include the walls, overheads, and floors.

Surface deposition sampling data are provided in Appendix A. An analysis of some of the surface deposition samples indicates:

- o The activity is limited to a thin surface layer
- o The surface layer is no thicker than 40 mils

- o The paint layer is approximately 20 to 30 mils (specification called for 28 mils)
- o Correlation with the contact radiation reading derived RDFs.

The Gross Decontamination Experiment showed that decontamination could be accomplished safely and not impact the operations or safety functions of the facility, components, or structure.

It will be necessary to use chemicals in areas where flushing or abrasive techniques cannot be used. Chemicals were used safely and it was possible to control the waste.

Conclusion Summary

- o The most effective decontamination technique reduced the gamma dose rates below the target for practical work area for head lift and defueling.
- o The mechanical scrubber and strippable coating technique can produce smearable contamination levels of 10^3 to 10^4 dpm/100 cm² of cesium, area radiation dose rates of 30 to 40 mrem/hour gamma on painted concrete surfaces, and 20 to 25 mrem/hour gamma on stainless steel surfaces.
- o The surface deposition boring results indicate that decontamination of the painted concrete surfaces can be accomplished by surface washing and scrubbing with water and chemicals.
- o The Decontamination Experiment results showed that the particulate activity could be reduced to the point where respirator protection is not required. Further decontamination efforts will eliminate the requirement for respirators.

- o DF is dependent upon the type and orientation of the surface, the nature of the contaminants, and the volume of water applied per unit surface area.
- o The water temperature did not appear to be a significant parameter in these tests.
- o High pressure and high flow rates caused problems.
- o Stainless steel exhibited higher DFs than both concrete and carbon steel.
- o Mechanical scrubbing is very effective. The need for detergent or other chemicals should be further evaluated.
- o Strip coating appears to be effective on floor surfaces. High DFs were observed.
- o Combination of low and high pressure flushing may be necessary on floors only if the surface is covered by large amounts of loose debris. Otherwise, high pressure flushing is just as effective as the combination - particularly if mechanical scrubbing is to be used.
- o Lack of correlation between RDFs by contact readings and DFs from smears indicates that the smearable fraction may be relatively independent of total loose contaminant/cm² at the levels involved in the reactor building.
- o High DFs are achievable on vertical surfaces with low pressure flushing alone. High pressure (over 2000 psi) is probably unnecessary. If further reduction is required, abrasive blasting, chemicals, or mechanical scrubbing could be used.

- o A vacuum system would be a beneficial addition to the water floor scrubber. It would avoid problems of recontamination due to an inability to properly handle water, and, DFs might be increased, since contaminated water would be removed rather than redistributed.
- o Smearable contamination levels of 10^5 dpm/100 cm² of Cs-137 are attainable using low pressure and/or high pressure flushing alone, if proper matching of technique to surface and contamination type is effected.
- o Hydrolance operations were limited to 3000 psi because of the inability of workers to maintain their footing while spraying. However, large workmen (in the 250 to 270 pound range) could satisfactorily spray with 6000 to 7000 psi.

Key:

△ LP Elevation 305'

□ HP Elevation 305' & LP/HP Elevation 305'

○ LP/HP Elevation 347'-6''

Figure 3-1. Plot of decontamination factor (based on contact measurements) versus water rate.

Figure 3-2. Decontamination logic diagram

DO NOT MICROFILM
THIS PAGE

4.0 RECOMMENDATIONS

Additional Testing

Additional testing should be accomplished and the following techniques should be evaluated:

- o Mechanical scrubbing with abrasive pads using water rather than chemicals.
- o Abrasive blasting techniques. Conventional methods or methods involving zeolites in water should be tested to assess their effectiveness on vertical and horizontal surfaces of various types. The success of mechanical scrubbing techniques indicates that a related technique, such as abrasive blasting, may be equally successful. Additional abrasive techniques should be tested for use in confined areas, which would possibly avoid recontamination problems encountered with the overspray associated with high pressure flushing.
- o Vertical surface cleaning with a mechanical scrubber using water alone and using chemical solutions.
- o Vacuum pickup systems for collection of water from the water floor scrubber. If wet-vacuum collection increases the DFs, a design effort will be required to achieve ease of vacuum use by decontamination teams.
- o Core and paint samples should be obtained from several surface deposition sampling locations and analyzed to determine: the thickness of the paint in those locations, and the activity contained in the paint, primer, and filler. This information should be obtained in small depth increments to 50 mils to determine how much material needs to be removed to effectively eliminate the contaminants.

Decontamination Techniques

Strippable coatings should be considered for decontamination of surfaces possessing a high fraction of smearable contamination. Such coatings should also be used for contamination control after an area is decontaminated since they are waterproof and, by the use of "egg crating," can be employed for contamination control on personnel traffic lanes.

An addendum to the Gross Decontamination Plan should be published to incorporate the results of this experiment.

Other Recommendations

- o Improve the reactor building radio communications between the crews and the command center.
- o Improve the system of approving entry tasks to provide adequate, but not excessive, review.
- o Review site procedures to remove redundancy, duplication, and overlapping responsibility.
- o Implement a program to establish source terms and effect dose reductions.
- o A method should be established to provide some flexibility during and after decontamination work. This is necessary in order to take full advantage of what has been learned by current progress to have a cost effective, efficient, and safe decontamination work activity.

Additional Decontamination

It is recommended that decontamination efforts continue. From the results of the experiment, area dose rates were obtained that are below the target

levels of 50 mrem for defueling activity -- 30 to 40 mrem on the elevation 347'-6" concrete floor, and 18 to 25 mrem in the deep end of the refueling canal. The recommended decontamination sequence is:

- o Remove all the storage, trash, and waste.
- o Decontaminate the vertical and overhead surfaces, especially those surfaces that have not been decontaminated previously.
- o Decontaminate the floor surfaces.
- o Locate the hot spots and shield, clean, or remove the source.
- o Additional decontamination is recommended because it will eliminate the requirement for respirator protection and should increase the efficiency of the reactor building work crews.

DO NOT MICROFILM
THIS PAGE

5.0 REFERENCES

1. Bechtel National, Inc., Technical Plan for Reactor Building Gross Decontamination, TPO/TMI-009, November 1981.
2. GPU Services, Radiological Measurements of Environment Above 347' Elevation Utilizing Penetration R-626, TDR 068, December 1980.
3. Reactor Building Large-Scale Decontamination Test, Technical Data Book, Volume 2, Decontamination Technology, TPO/TMI-009, June 1981.
4. Bechtel Northern Corporation, Decontamination Experiment Post Execution Analysis, June 1982.
5. Bechtel National, Inc., Waste Volume Estimates for Reactor Building Gross Decontamination - Predicted and Observed, May 1982.
6. Battelle Memorial Institute, TRAN-STAT, Statistics for Environmental Studies (Prepared for the U. S. Department of Energy, Office of Health and Environmental Research, Office of the Environment).

DO NOT MICROFILM
THIS PAGE.

APPENDIX A

SURFACE DEPOSITION

CONTENTS

INTRODUCTION

SECTION I	SURFACE DEPOSITION DATA
SECTION II	TLD AND RO-2A DATA
SECTION III	AIRBORNE DATA
SECTION IV	DECONTAMINATION FACTORS
SECTION V	RO-2A AND TLD COMPARISONS

TABLES

A-1	Surface and Subsurface Gross Decontamination Experiment Results of Elevation 305'
A-2	Surface and Subsurface Gross Decontamination Experiment Results of Elevation 347' and 367'
A-3	Pre-Gross Decontamination Experiment RO-2A Data
A-4	Post-Gross Decontamination Experiment RO-2A Data
A-5	Pre-Elevation 305' Gross Decontamination Experiment TLD Data
A-6	Pre-Elevations 347' and 367' Gross Decontamination Experiment TLD Data
A-7	Post-Elevation 305' Gross Decontamination Experiment TLD Data
A-8	Post-Elevation 347' Gross Decontamination Experiment TLD Data
A-9	Post-Elevation 367' Gross Decontamination Experiment TLD Data
A-10	Pre-Gross Decontamination Experiment TLD Beta and Gamma Measurements of the Dome Monitor and its Environment
A-11	Pre-Gross Decontamination Experiment RO-2A Dome Monitor Measurements
A-12	Pre-Gross Decontamination Experiment RO-2A Measurements
A-13	Post-Gross Decontamination Experiment RO-2A Measurements

CONTENTS (Continued)

TABLES (Continued)

- A-14 Gross Decontamination Experiment Airborne Concentrations of I-129, Cs-134, and Cs-137
- A-15 Elevation 305' Decontamination Factors for the Gross Decontamination Experiment
- A-16 Elevation 347' Decontamination Factors for the Gross Decontamination Experiment
- A-17 Elevation 367' Decontamination Factors for the Gross Decontamination Experiment
- A-18 Elevation 305' Gross Decontamination Experiment Decontamination or Contamination Factors Based Upon the TLD Measurements
- A-19 Elevations 347' and 367' Gross Decontamination Experiment Decontamination Factors Based Upon the TLD Measurements
- A-20 Pre-Gross Decontamination Experiment RO-2A and TLD Comparisons

FIGURES

- A-1 Elevation 305' Surface Deposition Sample and RO-2A Measurement Locations
- A-2 Elevation 347' Surface Deposition Sample and RO-2A Measurement Locations
- A-3 Drill Vacuum System for Surface Deposition
- A-4 Pre-Gross Decontamination Experiment TLD and RO-2A Measurement Locations (Elevation 305')
- A-5 Pre-Gross Decontamination Experiment TLD and RO-2A Measurement Locations (Elevation 347'-6")
- A-6 Post-Gross Decontamination Experiment TLD and RO-2A Measurement Locations (Elevation 305')
- A-7 Post-Gross Decontamination Experiment TLD and RO-2A Measurement Locations (Elevation 347'-6")

CONTENTS (Continued)

FIGURES (Continued)

- A-8 Pre-HPR-214 Gross Decontamination Experiment TLD
Measurement Locations
- A-9 Floor Plan of TMI-2 Reactor Building Elevation 305'
Showing Sampler Locations
- A-10 Floor Plan of TMI-2 Reactor Building Elevation 347'
Showing Sampler Location

APPENDIX A - SURFACE DEPOSITION

INTRODUCTION

The raw data on the following pages are the most current information available on the surface deposition task. The data are still considered in the preliminary category and should be used with caution until the final report on this subject is issued by EG&G, Idaho. Inquiries on the data may be directed to Mr. Dave Hetzer, EG&G/TIO, Three Mile Island Nuclear Power Plant, Middletown, Pennsylvania 17057.

The purposes of this task were to quantify surface deposition on the walls, floors, and equipment, and to establish the effectiveness of the decontamination procedures.

In order to measure the effectiveness of the Gross Decontamination Experiment (principally a water spray technique) performed in the TMI-2 reactor building, the Technical Information and Examination Program's Radiation and Environment Program obtained atmospheric and surface deposition measurements and general area radiation measurements within the reactor building before and after the experiment.

Contamination levels at vertical and horizontal metal and concrete surface locations were measured before and after the experiment. Surface deposition samples, and thermoluminescent dosimeter (TLD), RO-2A, and gamma spectrometry measurements were the methods used to measure the contamination levels. Three types of measurements were performed at several predetermined sampling locations to distinguish between radiation and contamination. In addition, the I-129, Cs-134, and Cs-137 airborne concentrations were measured at three elevations.

Section I gives the data for the surface deposition samples and RO-2A measurements at specific locations. Section II contains the TLD and RO-2A measurements for general areas. Section III presents airborne data (I-129, Cs-134, and Cs-137) for the containment building. Section IV tabulates decontamination factors for the Gross Decontamination Experiment. Section V provides a pre-Gross Decontamination Experiment comparison of RO-2A and TLD measurements.

SECTION I

SURFACE DEPOSITION DATA

Section I contains the data from surface deposition samples and RO-2A measurements at locations shown in Figures A-1 and A-2. The associated tables reflect the pre-Decontamination Experiment measurements, post-Decontamination Experiment measurements, and the surface sample results.

A drill-vacuum system (see Figure A-3) was developed by EG&G to collect the surface deposition samples. The sample sequence consisted of (a) setting up the drill-vacuum system at the sample location, (b) vacuuming an area approximately 40 cm^2 (1.4-inch diameter) into a filter, and (c) changing the filter and boring a 1/2-inch-diameter hole with a flat nose bit while continually vacuuming all debris from the bored hole. The drill-vacuum equipment was then moved a short distance away and the sequence was repeated for the deeper hole. Several samples of varying depth were collected at each location to aid in determining the extent of contamination. RO-2 measurements were made at the same locations (with some exceptions) as the surface samples.

The surface deposition sampling technique provided 70 vacuum samples of the loose particulate matter and 111 subsurface samples, varying in depth from approximately 2×10^{-2} to 3×10^{-1} cm. (125 mills corresponds to 3×10^{-1} cm). The vacuum and subsurface samples were obtained by collecting the loose particulate, paint, and concrete or metal material on a high efficiency particulate filter. Vertical samples were a composite of the loose particulate material on the surface, and the subsurface material. Horizontal samples consisted of a vacuum sample of the surface and a subsurface sample from the same sampling point. The $\mu\text{Ci}/\text{cm}^2$ result given in the following tables was determined by dividing the total activity of the samples from the

same location by the surface area of the drill bit (1.27 cm^2) for a subsurface sample. For a vacuum sample (loose particulate), the total activity was divided by the vacuumed surface area (39.02 cm^2).

FIGURE A-2
ELEVATION 347' SURFACE DEPOSITION SAMPLE AND RO-2A MEASUREMENT LOCATIONS

⊙ : 120 Volt Power Recepticals

Figure A-3. Drill vacuum system for surface deposition.

TABLE A-1

SURFACE AND SUBSURFACE GROSS DECONTAMINATION EXPERIMENT RESULTS OF ELEVATION 305'

Area	Surface	Sample #	Sample Depth (mil)	GAMMA RESULTS								ADDITIONAL DATA OR NOTES
				Pre $\mu\text{Ci}/\text{cm}^2$				Post $\mu\text{Ci}/\text{cm}^2$				
				Cs - 134	Cs - 137	Sb - 125	Co-60	Cs - 134	Cs - 137	Sb-125	Co-60	
I	Vertical	B4-2	50	$7 \pm 3 \text{ E-2}$	$7 \pm 3 \text{ E-1}$			$8 \pm 4 \text{ E-3}$	$8 \pm 4 \text{ E-2}$			
		11 W	50	$1.3 \pm 0.3 \text{ E-2}$	$1.3 \pm 0.3 \text{ E-1}$	$1.1 \pm 0.8 \text{ E-3}$		$4 \pm 1 \text{ E-4}$	$5 \pm 1 \text{ E-3}$			
				$8 \pm 2 \text{ E-4}$	$7 \pm 2 \text{ E-3}$							
		Y2			< 0.2				0.5 ± 0.2			
	Horizontal	H7-1	Vacuum	$1.78 \pm 0.08 \text{ E-3}$	$4.75 \pm 0.01 \text{ E-2}$			$1.6 \pm 0.3 \text{ E-5}$	$1.49 \pm 0.09 \text{ E-4}$			
								$3.0 \pm 0.4 \text{ E-5}$	$2.8 \pm 0.1 \text{ E-4}$			
		H7-2	10	$3.4 \pm 0.7 \text{ E-1}$	$3.4 \pm 0.7 \text{ E0}$			$7 \pm 2 \text{ E-3}$	$7 \pm 1 \text{ E-2}$			
								$9 \pm 2 \text{ E-3}$	$9 \pm 2 \text{ E-2}$			
		H7-3	Vacuum	$2.56 \pm 0.02 \text{ E-2}$	$2.54 \pm 0.01 \text{ E-1}$		$5 \pm 2 \text{ E-6}$	$2.4 \pm 0.4 \text{ E-5}$	$2.1 \pm 0.1 \text{ E-4}$			
								$1.4 \pm 0.3 \text{ E-5}$	$1.5 \pm 0.1 \text{ E-4}$			
		H7-4	50	$1.4 \pm 0.3 \text{ E-1}$	$1.4 \pm 0.3 \text{ E0}$		$4 \pm 3 \text{ E-3}$	$2.5 \pm 0.5 \text{ E-2}$	$2.4 \pm 0.5 \text{ E-1}$			
								$1.3 \pm 0.3 \text{ E-2}$	$1.3 \pm 0.3 \text{ E-1}$			
		H7-5	Vacuum	$3.50 \pm 0.08 \text{ E-3}$	$3.47 \pm 0.03 \text{ E-2}$		$1.7 \pm 0.8 \text{ E-6}$	$4.8 \pm 0.5 \text{ E-5}$	$5.1 \pm 0.2 \text{ E-4}$			
								$6.2 \pm 0.6 \text{ E-5}$	$6.2 \pm 0.2 \text{ E-4}$			
		H7-6	125	$1.8 \pm 0.4 \text{ E0}$	$1.8 \pm 0.4 \text{ E-1}$	$3 \pm 2 \text{ E-2}$		$1.6 \pm 0.3 \text{ E-2}$	$1.6 \pm 0.3 \text{ E-1}$			
								$7 \pm 2 \text{ E-3}$	$7 \pm 1 \text{ E-2}$			
		Y1			0.95 ± 0.10				0.4 ± 0.2			

TABLE A-1 (Continued)

Area	Surface	Sample #	Sample Depth (mil)	Gamma Results								ADDITIONAL DATA OR NOTES
				Pre $\mu\text{Ci}/\text{cm}^2$				Post $\mu\text{Ci}/\text{cm}^2$				
				Cs - 134	Cs -137	Sb-125	Co-60	Cs - 134	Cs-137	Sb-125	Co 60	
II	Vertical	V9	50	1.7+0.4 E-3	1.7 $\pm$ 0.4 E-2		3 $\pm$ 2 E-5	3.3+0.8 E-3	3.2+0.7 E-2			
		V8	50	8 $\pm$ 4 E-3	8 $\pm$ 4 E-2			3 $\pm$ 1 E-3	3 $\pm$ 1 E-2			
		V7	50	5 $\pm$ 2 E-3	5 $\pm$ 2 E-2			7 $\pm$ 3 E-2	7 $\pm$ 3 E-1			
		V6	50	1.4+0.7 E-2	1.4 $\pm$ 0.6 E-1			1.4 $\pm$ 0.6 E-2	1.4 +0.6 E-1			
		46H	50	1.4+0.4 E-3	1.4 $\pm$ 0.3 E-2			3.0 $\pm$ 7 E-3	3.0 $\pm$ 3.7 E-2			
		B3-2	50	4 $\pm$ 2 E-3	4 $\pm$ 2 E-2			3 $\pm$ 2 E-2	3 $\pm$ 2 E-1			
		Y3			0.5 $\pm$ 0.3				<0.6			
		Y4	Coils	0.5 $\pm$ 0.3 CI	5.9 $\pm$ 1.0 CI							
			Drip Pan	0.012 $\pm$ 0.006CI	0.07 $\pm$ 0.03 CI							
		Y5	Coils	0.2 $\pm$ 0.1 CI	1.6 +0.4 CI							
			Drip Pan		0.02+ 0.01 CI							
		Y6	Coils		0.8 + 0.4 CI							
			Drip Pan		0.03 +0.03 CI							
	Horizontal	34F1	Vacuum	1.01 +0.01 E-2	1.01 $\pm$ 0.01 E-1			1.9+0.4 E-5	1.8 $\pm$ 0.1 E-4			
		34F2	10	3.8 $\pm$ 0.8 E-1	3.8 $\pm$ 0.8 E0	8 + 5 E-3	1.2+0.6 E-4	4.2 $\pm$ 0.9 E-3	4.4 $\pm$ 0.9 E-2	4 $\pm$ 2 E-6		
		34F3	Vacuum	1.93 +0.02 E-2	1.92 $\pm$ 0.01 E-1			1.10+0.08 E-4	1.09+0.03 E-3			
		34F4	50	4.1 +0.9 E-1	4.1 $\pm$ 0.9 E0		3 $\pm$ 2 E-4	6 $\pm$ 1 E-3	6 $\pm$ 1 E-2			
		34F5	Vacuum	1.66+0.02 E-2	1.66+0.01 E-1			1.56+0.09 E-4	1.53+0.03 E-3			
		34F6	125	8 $\pm$ 2 E-1	8 $\pm$ 2 E0			9 $\pm$ 2 E-3	8 $\pm$ 2 E-2			

TABLE A-1 (Continued)

Area	Surface	Sample #	Sample Depth (inl.)	Gamma Results								Additional Data or Notes
				Pre $\mu\text{Ci}/\text{cm}^2$				Post $\mu\text{Ci}/\text{cm}^2$				
				Cs-134	Cs-137	Sb-125	Co-60	Cs-134	Cs-137	Sb-125	Co-60	
II	HORIZONTAL	50F1	Vacuum	4.34 $\pm$ 0.08E-3	4.25 $\pm$ 0.03E-2	1.6 $\pm$ 0.9E-4		1.8 $\pm$ 0.3E-5	1.8 $\pm$ 0.1E-4			
		50F2	10	1.9 $\pm$ 0.4E-1	1.9 $\pm$ 0.4E0			2.3 $\pm$ 0.5E-2	2.3 $\pm$ 0.5 E-1			
		50F3	Vacuum	3.23 $\pm$ 0.06E-3	3.19 $\pm$ 0.03E-2			6.4 $\pm$ 0.6E-5	6.5 $\pm$ 0.2E-4	1.5 $\pm$ 0.9E-5		
		50F4	50	1.2 $\pm$ 0.3E-1	1.2 $\pm$ 0.3E0	4 $\pm$ 2 E-3		6 $\pm$ 1 E-3	6 $\pm$ 1 E-2			
		50F5	Vacuum	6.8 $\pm$ 0.1E-3	6.63 $\pm$ 0.03E-2			4.6 $\pm$ 0.5E-5	4.1 $\pm$ 0.2E-4			
		50F6	125	2.6 $\pm$ 0.6E-1	2.6 $\pm$ 0.6E0	4 $\pm$ 3E-3	4 $\pm$ 2 E-4	1.9 $\pm$ 0.4E-1	1.9 $\pm$ 0.4E0			
		H3V	Vacuum	1.41 $\pm$ 0.05E-3	1.39 $\pm$ 0.02E-2	1.3 $\pm$ 0.6E-4		5.7 $\pm$ 0.2E-4	5.66 $\pm$ 0.06E-3			
		H3C	125	1.9 $\pm$ 0.4E-1	1.8 $\pm$ 0.4E0	1.1 $\pm$ 0.4E-2	5 $\pm$ 2E-4	3.5 $\pm$ 0.8E-2	3.4 $\pm$ 0.7E-1			
		γ 7			0.9 $\pm$ 0.2				5.3 $\pm$ 0.4			
		γ 8			<0.3							
		γ 9		2.7 $\pm$ 0.3	28 $\pm$ 2							
III	HORIZONTAL	H2V		2.30 $\pm$ 0.05E-3	2.23 $\pm$ 0.01E-2	1.8 $\pm$ 0.5E-4	4 $\pm$ 1 E-6	1.8 $\pm$ 0.3E-5	2.2 $\pm$ 0.1E-4			
		H2C		2.1 $\pm$ 0.05E-1	2.1 $\pm$ 0.5E0	3.5 $\pm$ 0.8E-2	5 $\pm$ 2 E-4	3.1 $\pm$ 0.7E-1	3.0 $\pm$ 0.6E0	9 $\pm$ 3 E-3	2.1 $\pm$ 0.8E-4	55F1 & 55F2 pre $\mu\text{Ci}/\text{cm}^2$ giver below:
		55F1		8.9 $\pm$ 0.1E-3	8.67 $\pm$ 0.03E-2	7.4 $\pm$ 0.2E-3	1.5 $\pm$ 0.2E-4	6.7 $\pm$ 0.2E-4	6.54 $\pm$ 0.05E-3	1.1 $\pm$ 0.3E-4		Ce-144 Ag-110m 1.0 $\pm$ 0.2E-3 9 $\pm$ 2E-5
		55F2		2.3 $\pm$ 0.5E-1	2.3 $\pm$ 0.5E0	2.0 $\pm$ 0.4E-1	5 $\pm$ 1E-3	2.6 $\pm$ 0.6E-2	2.5 $\pm$ 0.5E-1	1.4 $\pm$ 0.3 E-2	1.4 $\pm$ 0.5E-4	Ce-144 Ag-110m RuD-136 2.7 $\pm$ 0.7E-2 2.1 $\pm$ 0.7E-3 2.8 $\pm$ 0.9E-2
IV	VERTICAL	67W		2.7 $\pm$ 0.7E-3	2.7 $\pm$ 0.6E-2			1.6 $\pm$ 0.4 E-3	1.7 $\pm$ 0.4E-2			
	HORIZONTAL	70F1		1.28 $\pm$ 0.01E-2	1.26 $\pm$ 0.01E-1			6.2 $\pm$ 0.6E-5	5.6 $\pm$ 0.2E-4	4 $\pm$ 1E-5		
		70F2		4.1 $\pm$ 0.9E-1	4.1 $\pm$ 0.9E0			2.8 $\pm$ 0.6E-2	2.8 $\pm$ 0.6E-1			

TABLE A-2

SURFACE AND SUBSURFACE GROSS DECONTAMINATION EXPERIMENT RESULTS OF ELEVATIONS 347' AND 367'

AREA	SURFACE	SAMPLE #	SAMPLE DEPTH (in.)	GAMMA RESULTS								ADDITIONAL DATA OR NOTES
				Pre $\mu\text{Ci}/\text{cm}^2$				Post $\mu\text{Ci}/\text{cm}^2$				
				Cs-134	Cs-137	Sb-125	Co-60	Cs-134	Cs-137	Sb-125	Co-60	
II	HORIZONTAL	33F1	Vacuum	2.5 $\pm$ 0.1E-4	2.34 $\pm$ 0.05E-3		1.2 $\pm$ 0.4E-6	7.5 $\pm$ 0.7E-5	7.2 $\pm$ 0.2E-4			
		33F2	125	8 $\pm$ 2E-2	8 $\pm$ 2 E-1		6 $\pm$ 3E-5	7 $\pm$ 2E-3	7 $\pm$ 2E-2			
		91F1	Vacuum	3.4 $\pm$ 0.3E-4	3.47 $\pm$ 0.06E-3			2.5 $\pm$ 0.1E-4	2.53 $\pm$ 0.04E-3			
		91F2	10	7 $\pm$ 2E-2	7 $\pm$ 2E-1			2.6 $\pm$ 0.6E-3	2.5 $\pm$ 0.5E-2			
		91F5	Vacuum	1.3 $\pm$ 0.1E-4	1.22 $\pm$ 0.03E-3			1.9 $\pm$ 0.1E-4	1.99 $\pm$ 0.04E-3			
		91F6	50	5 $\pm$ 1E-2	5 $\pm$ 1E-1	2 $\pm$ 1E-3		4.1 $\pm$ 0.9E-3	4.0 $\pm$ 0.9E-2			
		91F3	Vacuum	2.4 $\pm$ 0.2E-4	2.09 $\pm$ 0.06E-3			7.1 $\pm$ 0.7E-5	7.7 $\pm$ 0.2E-4			
		91F4	125	2.2 $\pm$ 0.5E-2	2.2 $\pm$ 0.5E-1			6 $\pm$ 1E-3	6 $\pm$ 1E-2			
		γ 10			<0.14				1.1 $\pm$ 0.2			
III	VERTICAL	31W	50	5 $\pm$ 2E-4	5 $\pm$ 1E-3			1.2 $\pm$ 0.3E-3	1.2 $\pm$ 0.3E-2			
		34W	50	9 $\pm$ 2E-4	1.0 $\pm$ 0.2E-2			1.8 $\pm$ 0.4E-3	1.7 $\pm$ 0.4E-2			
IV	VERTICAL	36W	50	2.0 $\pm$ 5E-3	1.8 $\pm$ 0.4E-2			2.4 $\pm$ 0.6E-3	2.3 $\pm$ 0.5E-2			
		V4	50	2.9 $\pm$ 0.7E-3	2.8 $\pm$ 0.6E-2			2.8 $\pm$ 0.7E-3	2.9 $\pm$ 0.7E-2			
		γ 11			<0.20				<0.3			
	HORIZONTAL	HB-1	Vacuum	4.2 $\pm$ 0.3E-4	4.08 $\pm$ 0.08E-3							
		HB-2	125	3.0 $\pm$ 0.6E-2	3.0 $\pm$ 0.7E-1	2 $\pm$ 1E-3	1.3 $\pm$ 0.6E-4					
		γ 12			0.96 $\pm$ 0.15							

TABLE A-2 (Continued)

AREA	SURFACE	SAMPLE #	SAMPLE DEPTH (mil.)	Gamma Results								ADDITIONAL DATA OR NOTES
				pre $\mu\text{Ci}/\text{cm}^2$				Post $\mu\text{Ci}/\text{cm}^2$				
				Cs-134	Cs-137	Sb-125	Co-160	Cs-134	Cs-137	Sb-125	Co-60	
V	VERTICAL	B2-2	50	1.2 $\pm$ 0.5E-2	1.1 $\pm$ 0.5E-2			1.2 $\pm$ 0.6E-2	1.2 $\pm$ 0.5E-1			
	HORIZONTAL	A0F1	Vacuum	1.28 $\pm$ 0.05E-3	1.25 $\pm$ 0.02E-2			1.8 $\pm$ 0.1E-4	1.77 $\pm$ 0.03E-3			
		A0F2	50	3 $\pm$ 1 E-1	3 $\pm$ 1E0		5 $\pm$ 3E-5	3 $\pm$ 1E-2	3 $\pm$ 1 E-1	6 $\pm$ 2E-4		
		H10-1	Vacuum	1.89 $\pm$ 0.05E-3	1.87 $\pm$ 0.02E-2			3.5 $\pm$ 0.4E-5	3.3 $\pm$ 0.1E-4			
		H10-2	10	5 $\pm$ 1E-1	5 $\pm$ 1E0		5 $\pm$ 3E-5	4 $\pm$ 1 E-2	4 $\pm$ 1E-1			
		H10-3	Vacuum	1.65 $\pm$ 0.05E-3	1.63 $\pm$ 0.02E-2			5.1 $\pm$ 0.5E-5	5.1 $\pm$ 0.2E-4			
		H10-4	50	2.8 $\pm$ 0.6E-1	2.8 $\pm$ 0.6E0	9 $\pm$ 5E-3	1.6 $\pm$ 0.7E-4	1.2 $\pm$ 0.3E-2	1.2 $\pm$ 0.2 E-1			
		H10-5	Vacuum	7.0 $\pm$ 0.3E-4	7.02 $\pm$ 0.08E-3			8.7 $\pm$ 0.7E-5	8.8 $\pm$ 0.2E-4			
		H10-6	125	1.3 $\pm$ 0.3E-1	1.3 $\pm$ 0.3E0			2.0 $\pm$ 0.4E-2	2.0 $\pm$ 0.4E-1			
		Y 13			0.5 $\pm$ 0.16				0.8 $\pm$ 0.2			

TABLE A-2 (Continued)

AREA	SURFACE	SAMPLE	SAMPLE DEPTH (mil.)	Gamma Results								ADDITIONAL DATA OR NOTES
				Pre $\mu\text{Ci}/\text{cm}^2$				Post $\mu\text{Ci}/\text{cm}^2$				
				Cs-134	Cs-137	Sb-125	Co-60	Cs-134	Cs-137	Sb-125	Co-60	
VI	VERTICAL	V2	50	$1.4 \pm 0.4 \text{E-3}$	$1.4 \pm 0.3 \text{E-2}$			$4.0 \pm 0.9 \text{E-3}$	$4.0 \pm 0.3 \text{E-2}$			
		50W	50	$2 \pm 1 \text{E-3}$	$3 \pm 1 \text{E-2}$			$1.1 \pm 0.5 \text{E-3}$	$1.2 \pm 0.5 \text{E-2}$			
	HORIZONTAL	149F1	Vacuum	$1.53 \pm 0.02 \text{E-2}$	$1.53 \pm 0.01 \text{E-2}$		$4 \pm 2 \text{E-4}$	$4.3 \pm 0.1 \text{E-4}$	$4.24 \pm 0.05 \text{E-3}$			
								$2.1 \pm 0.1 \text{E-4}$	$2.03 \pm 0.03 \text{E-3}$			
		149F2	10					$7 \pm 1 \text{E-2}$	$7 \pm 1 \text{E-1}$		$9 \pm 5 \text{E-6}$	
								$6 \pm 1 \text{E-2}$	$5 \pm 1 \text{E-1}$			
		149F3	Vacuum					$5.3 \pm 0.5 \text{E-5}$	$5.1 \pm 0.2 \text{E-4}$			
								$2.1 \pm 0.1 \text{E-4}$	$2.03 \pm 0.03 \text{E-3}$			
		149F4	125	$6 \pm 1 \text{E-1}$	$6 \pm 1 \text{E0}$			$7 \pm 1 \text{E-2}$	$7 \pm 1 \text{E-1}$			
								$1.8 \pm 0.4 \text{E-1}$	$1.7 \pm 0.4 \text{E0}$			
		V10-1	Vacuum	$3.09 \pm 0.08 \text{E-3}$	$3.05 \pm 0.03 \text{E-2}$			$5.3 \pm 0.5 \text{E-5}$	$4.8 \pm 0.2 \text{E-4}$			
		V10-2	125	$3.3 \pm 0.7 \text{E-1}$	$3.3 \pm 0.7 \text{E0}$			$8 \pm 2 \text{E-2}$	$8 \pm 2 \text{E-1}$			
Y14			0.97 ± 0.17				2.0 ± 0.1					

TABLE A-2 (Continued)

Area	Surface	Sample #	Sample Depth (m11)	Gamma Results								ADDITIONAL DATA OR NOTES
				Pre $\mu\text{Ci}/\text{cm}^2$				Post $\mu\text{Ci}/\text{cm}^2$				
				Cs-134	Cs-137	Sb-125	Co-60	Cs-134	Cs-137	Sb-125	Co-60	
VII	Vertical	R1-2	50	1.6 $\pm$ 0.7 E-3	1.6 $\pm$ 0.7 E-2			4 $\pm$ 2 E-3	5 $\pm$ 2 E-2			
								1.6 $\pm$ 0.7 E-2	1.5 $\pm$ 0.7 E-1			
	Horizontal	54F1	Vacuum	1.15 $\pm$ 0.01 E-2	1.14 $\pm$ 0.01 E-1			2.7 $\pm$ 0.1 E-4	2.70 $\pm$ 0.04 E-3			
		54F2	10	2.8 $\pm$ 0.6 E-1	2.8 $\pm$ 0.6 E0			2.3 $\pm$ 0.5 E-2	2.2 $\pm$ 0.5 E-1		4 $\pm$ 2 E-5	
		54F3	Vacuum	1.47 $\pm$ 0.02 E-2	1.46 $\pm$ 0.01 E-1			1.6 $\pm$ 0.1 E-4	1.55 $\pm$ 0.03 E-3			
								1.8 $\pm$ 0.1 E-4	1.77 $\pm$ 0.03 E-3			
		54F4	50	3.7 $\pm$ 0.8 E-1	3.7 $\pm$ 0.8 E0			1.7 $\pm$ 0.4 E-2	1.7 $\pm$ 0.4 E-1			
								1.4 $\pm$ 0.3 E-2	1.4 $\pm$ 0.3 E-1			
		54F5	Vacuum	1.82 $\pm$ 0.02 E-2	1.81 $\pm$ 0.01 E-1			6.7 $\pm$ 0.6E-5	7.0 $\pm$ 0.2 E-4			
		54F6	125	1.4 $\pm$ 0.3 E-1	1.4 $\pm$ 0.3 E0			1.4 $\pm$ 0.3 E-2	1.4 $\pm$ 0.3 E-1			
		H9-1	Vacuum	1.05 $\pm$ 0.01 E-2	1.06 $\pm$ 0.01 E-1			7.6 $\pm$ 0.7 E-5	7.4 $\pm$ 0.2 E-4			
		H9-2	125	9 $\pm$ 2 E-2	9 $\pm$ 2 E-1			7 $\pm$ 2 E-3	7 $\pm$ 1 E-2			
		Y15			0.85 $\pm$ 0.17							
VIII	Horizontal	115F1	Vacuum	2.26 $\pm$ 0.06E-3	2.27 $\pm$ 0.02 E-2		5 $\pm$ 2 E-6	7.4 $\pm$ 0.7 E-5	7.2 $\pm$ 0.2 E-4			
		115F2	125	1.2 $\pm$ 0.2 E-1	1.1 $\pm$ 0.2 E-0			3.9 $\pm$ 0.9 E-3	3.7 $\pm$ 0.8 E-2			
	Vertical	16W	50	1.2 $\pm$ 0.3 E-2	1.3 $\pm$ 0.3 E-1			8 $\pm$ 2 E-3	8 $\pm$ 2 E-2			

TABLE A-2 (Continued)

Area	Surface	Sample #	Sample Depth (mil)	Gamma Results								ADDITIONAL DATA OR NOTES
				Pre $\mu\text{Ci}/\text{cm}^2$				Post $\mu\text{Ci}/\text{cm}^2$				
				Cs - 134	Cs - 137	Sb - 125	Co-60	Cs - 134	Cs - 137	Sb - 125	Co-60	
X	Horizontal	26F1	Vacuum	5.9 $\pm$ 0.3 E-4	5.7 $\pm$ 0.1 E-3			1.28 $\pm$ 0.01 E-	1.27 $\pm$ 0.01 E-2			
		26F2	125	3.9 $\pm$ 0.9 E-2	3.9 $\pm$ 0.9 E-1			5 $\pm$ 1 E-2	4 $\pm$ 1 E-1			
		HIV	Vacuum	4.51 $\pm$ 0.08 E-3	4.47 $\pm$ 0.03 E-2			2.15 $\pm$ 0.03 E-3	2.13 $\pm$ 0.01 E-2			
		HIC	125	2.5 $\pm$ 0.5 E-1	2.5 $\pm$ 0.5 E 0			9 $\pm$ 2 E-2	9 $\pm$ 2 E-1			
		221B	50	3 $\pm$ 2 E-3	4 $\pm$ 2 E-2			2 $\pm$ 1 E-3	2.0 $\pm$ 0.9 E-2			
		I-1	Vacuum	1.49 $\pm$ 0.05 E-3	1.50 $\pm$ 0.02E-2			5.5 $\pm$ 0.2 E-4	5.35 $\pm$ 0.05 E-3			
		I-2	50	9 $\pm$ 4 E-2	9 $\pm$ 4 E-1			2.1 $\pm$ 0.9 E-3	2.1 $\pm$ 0.9 E-2			
								6 $\pm$ 2 E-3	5 $\pm$ 2 E-2	1.3 $\pm$ 0.7 E-3		

NOTES:

1. All gamma results decay corrected to 3/26/82 @ 12:00
2. All gamma result uncertainties are 1 sigma
3. γ_4 , γ_5 , and γ_6 Cs-137 results are the total curies measured

TABLE A-3

PRE-GROSS DECONTAMINATION EXPERIMENT RO-2A DATA

ELEVATION	DATA POINT	VERTICAL OR HORIZONTAL	RO2A - READINGS		MEASUREMENT DATE	RO - 2A INFORMATION			DOSE RATES		COMMENTS
			OPEN WINDOW mR/hr.	CLOSED WINDOW mR/hr.		SERIAL #	CALIBRATION DATE	BETA FACTOR	γ mR/hr.	β mR/hr.	
305'	B4-2	Vertical	1,000	1,000	12/17/81	306	3/15/82	3.7	1,000	≤8akd.	4th beam north of air lock #2, facing O-ring wall, 4' above floor
	11W	Vertical	900	900	12/17/81	306	3/15/82	3.7	900	≤8akd.	4' above floor
	H7	Horizontal	400	250	12/17/81	306	3/15/82	3.7	250	560	
	34F	Horizontal	2,400	500	12/17/81	306	3/15/82	3.7	500	7,000	
	50F	Horizontal	1,300	400	12/17/81	306	3/15/82	3.7	400	3,300	
	H3	Horizontal	2,000	1,000	12/17/81	306	3/15/82	3.7	1,000	3,700	
	55F	Horizontal	2,000	1,500	12/17/81	306	3/15/82	3.7	1,500	1,900	
	6/W	Vertical	290	280	12/17/81	306	3/15/82	3.7	280	37	4' above floor
	70F	Horizontal	900	360	12/17/81	306	3/15/82	3.7	360	2,000	
347'	31W	Vertical	55	35	12/15/81	715	2/22/82	3.5	35	70	4' above floor
	33P	Horizontal	400	200	12/15/81	715	2/22/82	3.5	200	700	
	91F	Horizontal	700	300	12/15/81	715	2/22/82	3.5	300	1,400	
	34W	Vertical	75	65	12/15/81	715	2/22/82	3.5	65	35	4' above floor
	V4	Vertical	95	75	12/15/81	715	2/22/82	3.5	75	70	4' above floor
	36W	Vertical	85	75	12/15/81	715	2/22/82	3.5	75	35	4' above floor
	B2-2	Vertical	270	120	12/15/81	715	2/22/82	3.5	120	525	Front of JB
	40F	Horizontal	2,650	500	12/15/81	715	2/22/82	3.5	500	7,530	

TABLE A-3 (Continued)

[illegible]

TABLE A-4

POST-GROSS DECONTAMINATION EXPERIMENT RO-2A DATA

ELEVATION	DATA POINT	VERTICAL OR HORIZONTAL	RO-2A READINGS		MEASUREMENT DATE	RO-2A INFORMATION			DOSE RATES		COMMENTS
			OPEN WINDOW mR/hr.	CLOSED WINDOW mR/hr.		SERIAL #	CALIBRATION DATE	BETA FACTOR	Y mR/hr.	B mR/hr.	
305'	B4-2	Vertical	400	300	3/25/82	A001	2/24/82	4.0	300	400	4th I-beam north of airlock #2, facing D-ring wall, 4' above floor
	11W	Vertical	200	300	3/25/82	A001	2/24/82	4.0	300	≤ Bakd.	4' above floor
	H7	Horizontal	300	80	3/26/82	205	2/24/82	3.9	80	858	
	V9	Vertical	350	250	3/25/82	A001	2/24/82	4.0	250	400	4' above floor
	V8	Vertical	400	375	3/25/82	A001	2/24/82	4.0	375	100	4' above floor
	V7	Vertical	500	400	3/25/82	A001	2/24/82	4.0	400	400	4' above floor
	V6	Vertical	806	600	3/25/82	A001	2/24/82	4.0	600	824	4' above floor
	46W	Vertical	350	200	3/25/82	A001	2/24/82	4.0	200	600	4' above floor
	34F	Horizontal	380	250	3/26/82	205	2/24/82	3.9	250	507	
	50F	Horizontal	150	150	3/26/82	205	2/24/82	3.9	150	≤ Bakd.	
	H3	Horizontal	1000	1000	3/26/82	205	2/24/82	3.9	1000	≤ Bakd.	
	H2	Horizontal	4700	2500	3/26/82	205	2/24/82	3.9	2500	8580	
	55F	Horizontal	1500	500	3/26/82	205	2/24/82	3.9	500	3900	4' above floor
	67W	Vertical	600	600	3/25/82	A001	2/24/82	4.0	600	≤ Bakd.	
	70F	Horizontal	500	500	3/26/82	205	2/24/82	3.9	500	≤ Bakd.	
347'	31W	Vertical	48	36	3/25/82	A001	2/24/82	4.0	36	48	4' above floor
	33F	Horizontal	140	60	3/25/82	205	2/24/82	3.9	60	312	

1

~~XXXXXXXXXXXX~~

SECTION II

TLD AND RO-2A DATA

Gamma and beta measurement locations and values are given in Figures A-4 through A-8 and associated tables. The TLD measurements were made using a multichip system. Each TLD system contained 24 or 48 chips oriented such that 12 or 24 chips faced the front and 12 or 24 chips faced the back. The chips were clustered in groups of three under four or eight different thicknesses of shields. The dosimeters were placed directly on a surface to measure the beta activity level of the contact surface as well as the beta background and general area gamma activity levels detected by the opposite side of the TLD.

The RO-2A instrument (ion chamber type) provided beta and gamma readings for a specific sample location. RO-2A measurements were taken during the surface deposition sampling, HPR-214 (dome monitor) inspection work, and the TLD placements. The RO-2A instrument was held at a 2.54 cm fixed distance from the surface for the surface deposition sampling work. For the TLD placement work, the RO-2A instrument was held approximately 0.64 to 3.1 cm from the surface. The RO-2A instrument was held approximately 2.54 cm and 1.2 meters from the surface for the HPR-214 inspection work.

The gamma spectrometer measurements were performed using a portable, collimated gamma ray spectrometer to determine the surface area concentration of gamma ray emitting nuclides for each level at five vertical and five horizontal locations before and after the Decontamination Experiment. The spectrometer system consisted of a hyperpure germanium detector in conjunction with a multichannel analyzer that was calibrated to measure the surface area concentration of sources.

FIGURE A-4
PRE-GROSS DECONTAMINATION EXPERIMENT TLD AND RO-2A MEASUREMENT LOCATIONS

FIGURE A-5
PRE-GROSS DECONTAMINATION EXPERIMENT TLD AND RO-2A MEASUREMENT LOCATIONS

PLAN EL. 347' - 6"

Location Number	X	Y
1	10/114	10/114
2	10/114	10/114
3	10/114	10/114
4	10/114	10/114

Vertical Measurement	X	Y
1	10/114	10/114
2	10/114	10/114
3	10/114	10/114
4	10/114	10/114

Horizontal Measurement	X	Y
1	10/114	10/114
2	10/114	10/114
3	10/114	10/114
4	10/114	10/114

FIGURE A-6

POST-GROSS DECONTAMINATION EXPERIMENT TLD AND RO-2A MEASUREMENT LOCATIONS

32

8	10	12
14	16	18
20	22	24

34

8	10	12
14	16	18
20	22	24

36

8	10	12
14	16	18
20	22	24

38

8	10	12
14	16	18
20	22	24

40

8	10	12
14	16	18
20	22	24

42

8	10	12
14	16	18
20	22	24

44

8	10	12
14	16	18
20	22	24

46

8	10	12
14	16	18
20	22	24

48

8	10	12
14	16	18
20	22	24

50

8	10	12
14	16	18
20	22	24

52

8	10	12
14	16	18
20	22	24

54

8	10	12
14	16	18
20	22	24

56

8	10	12
14	16	18
20	22	24

58

8	10	12
14	16	18
20	22	24

60

8	10	12
14	16	18
20	22	24

62

8	10	12
14	16	18
20	22	24

64

8	10	12
14	16	18
20	22	24

66

8	10	12
14	16	18
20	22	24

68

8	10	12
14	16	18
20	22	24

70

8	10	12
14	16	18
20	22	24

72

8	10	12
14	16	18
20	22	24

74

8	10	12
14	16	18
20	22	24

76

8	10	12
14	16	18
20	22	24

78

8	10	12
14	16	18
20	22	24

80

8	10	12
14	16	18
20	22	24

82

8	10	12
14	16	18
20	22	24

84

8	10	12
14	16	18
20	22	24

86

8	10	12
14	16	18
20	22	24

88

8	10	12
14	16	18
20	22	24

90

8	10	12
14	16	18
20	22	24

92

8	10	12
14	16	18
20	22	24

94

8	10	12
14	16	18
20	22	24

96

8	10	12
14	16	18
20	22	24

98

8	10	12
14	16	18
20	22	24

100

8	10	12
14	16	18
20	22	24

102

8	10	12
14	16	18
20	22	24

104

8	10	12
14	16	18
20	22	24

106

8	10	12
14	16	18
20	22	24

108

8	10	12
14	16	18
20	22	24

110

8	10	12
14	16	18
20	22	24

112

8	10	12
14	16	18
20	22	24

114

8	10	12
14	16	18
20	22	24

116

Location Number	
S. side/N.P.	N. side/S.P.
Conglomerate	Conglomerate
Surface	Conglomerate

Vertical Corral Measurements:

Vertical Measurement:

TABLE A-5

PRE-ELEVATION 305' GROSS DECONTAMINATION EXPERIMENT TLD DATA

ID	LOCATION NUMBER	LOCATION DESCRIPTION	VERTICAL OR HORIZONTAL	TOTAL EXPOSURE				DATE & TIME OF EXPOSURE		EXPOSURE TIME HRS.	EXPOSURE RATE				COMMENTS
				B		Y		IN	OUT		B		Y		
				Front RAD	Back RAD	Front RAD	Back RAD				Front mR/hr.	Back mR/hr.	Front mR/hr.	Back mR/hr.	
11	13	Taped to liner approximately 4 feet above the floor, NE area Rx Bldg.	Vertical	NA	NA	92.70	98.66	12/9/81 1427	12/15/81 1838	148.2	NA	NA	623	664	
12	H7	Taped to the floor, NE area of Rx Bldg., SE area under CF-T-1A	Horizontal	23.79	136.74	63.37	69.67	12/9/81 1427	12/15/81 1838	148.2	158	920	426	468	
13	B4	Taped to the underside of the junction box, NE area of Rx Bldg.	Vertical	70.60	20.02	23.42	23.75	12/9/81 1427	12/15/81 1838	148.2	474	133	156	158	
14	V9	Taped to D-ring wall approximately 4 feet above floor, SE area Rx Bldg.	Vertical	36.53	5.70	84.90	82.26	12/9/81 1427	12/15/81 1838	148.2	244	36	571	553	
15	H6	Taped to West area of hatch cover, SE area of Rx Bldg.	Horizontal	1020.31	2203.82	332.53	390.86	12/9/81 1427	12/15/81 1838	148.2	6802	14.9R/hr.	2242	2635	
16	V8	Taped to front side of aircooler B approx. 4' above floor, SE area of Rx Bldg.	Vertical	16.73	22.07	85.83	85.23	12/9/81 1427	12/15/81 1838	148.2	110	146	577	573	
18	H5	Taped to the floor, SW area of Rx Bldg., NE area under CF-T-1B.	Horizontal	94.08	406.94	138.81	133.34	12/9/81 1427	12/15/81 1838	148.2	632	2743	935	898	
27	67W	Taped to D-ring wall approx. 4 feet above floor, NW area Rx Bldg.	Vertical	NA	NA	42.79	39.37	12/9/81 1427	12/15/81 1838	148.2	NA	NA	287	267	
26	66	Taped to liner approx. 4 feet above the floor NW area of Rx Bldg.	Vertical	202.81	39.51	42.27	45.19	12/9/81 1427	12/15/81 1838	148.2	1367	265	283	303	
25	63	Taped to D-ring wall approx. 4 feet above floor, W area of Rx Bldg.	Vertical	24.02	82.39	214.80	196.37	12/9/81 1427	12/15/81 1838	148.2	174	554	1448	1323	
23	H3	Taped to floor, West area of Rx Bldg.	Horizontal	NA	1155.24	767.44	809.81	12/9/81 1427	12/15/81 1838	148.2	NA	7794	5177	5462	
19	B3	Taped to underside of junction box approx. 8 feet off the floor.	Vertical	100.63	88.68	NA	57.50	12/9/81 1427	12/15/81 1838	148.2	677	597	NA	386	
21	50F	Taped to floor, SW area of Rx Bldg.	Horizontal	45.15	742.74	61.13	60.78	12/9/81 1427	12/15/81 1838	148.2	303	5010	411	408	

TABLE A-6

PRE-ELEVATIONS 347' and 367' GROSS DECONTAMINATION EXPERIMENT TLD DATA

LOCATION NUMBER	LOCATION DESCRIPTION	VERTICAL OR HORIZONTAL	TOTAL EXPOSURE				DATE & TIME OF EXPOSURE		EXPOSURE TIME HRS.	EXPOSURE RATE				COMMENTS
			B		Y		IN	OUT		B		Y		
			Front RAD	Back RAD	Front RAD	Back RAD				Front mR/hr.	Back mR/hr.	Front mR/hr.	Back mR/hr.	
30	Taped to liner approx. 4 feet above floor by hatch cover, NE area Rx Bldg.	Vertical	14.89	3.60	38.69	38.61	12/9/81 1507	12/15/81 1838	147.52	70	25	92	86	
31W	Taped to D-ring wall approx. 4 feet above floor, NE area Rx Bldg.	Vertical	32.41	10.03	14.12	13.83	12/9/81 1507	12/15/81 1838	147.52	215	64	93	91	
V3	Taped to liner behind enclosed stairwell approx. 4 feet above floor.	Vertical	11.68	3.47	10.04	8.45	12/9/81 1507	12/15/81 1838	147.52	75	19	66	47	
V4	Taped to outside enclosed stairwell wall approx. 4 feet above floor.	Vertical	9.40	9.10	13.30	13.17	12/9/81 1507	12/15/81 1838	147.52	60	57	88	87	
36W	Taped to D-ring wall approx. 4 feet above floor SE area Rx Bldg.	Vertical	19.06	2.72	17.84	17.93	12/9/81 1507	12/15/81 1838	147.52	125	14	118	119	
H10	Taped to floor near SW corner of hatch cover, South area of Rx Bldg.	Horizontal	33.52	568.94	35.87	39.32	12/9/81 1507	12/15/82 1838	147.52	223	3852	241	264	
50W	Taped to East side of head stand, SW area of Rx Bldg.	Vertical	55.22	22.58	19.83	18.24	12/9/81 1507	12/15/81 1838	147.52	368	147	132	121	
52	Taped to top of head stand, SW area of Rx Bldg.	Horizontal	51.91	246.62	22.21	21.52	12/9/81 1507	12/15/81 1838	147.52	345	1655	148	141	
V2	Taped to D-ring wall approx. 4 feet above floor West area Rx Bldg.	Vertical	21.10	4.85	18.62	18.32	12/9/81 1507	12/15/82 1838	147.52	137	26	124	122	
B1	Placed on the floor below junction box, West area Rx Bldg.	Horizontal	92.94	1645.79	67.93	67.25	12/9/81 1507	12/15/81 1838	147.52	624	11.2R/hr	458	453	
H9	Taped to floor approx. 4 feet south of open stairwell, West area of Rx Bldg.	Horizontal	77.90	927.68	41.64	39.35	12/9/81 1507	12/15/81 1838	147.52	522	6282	280	264	
56	Taped to liner approx. 4 feet above floor, West area of Rx Bldg.	Vertical	10.17	5.74	12.20	11.97	12/9/81 1507	12/15/81 1838	147.52	63	32	80	79	
63	West axis of the in core instrumentation area.	Horizontal	7423.62	36.0E3	1159.49	899.03	12/9/81 1507	12/15/81 1838	147.52	50.3R/hr	250 R/hr	7857	6092	
13	367' El., Top D-ring wall, East area of Rx Bldg.	Horizontal	60.66	172.42	49.08	55.30	12/9/81 1507	12/15/81 1838	147.52	407	7943	330	372	
V11	367' El., Taped to inside D-ring wall, East area Rx Bldg.	Vertical	26.85	85.20	112.98	109.65	12/9/81 1507	12/15/81 1838	147.52	178	573	763	741	

TABLE A-7

POST-ELEVATION 305' GROSS DECONTAMINATION EXPERIMENT TLD DATA

TLD #	LOCATION NUMBER	LOCATION DESCRIPTION	VERTICAL OR HORIZONTAL	TOTAL EXPOSURE				DATE & TIME OF EXPOSURE		EXPOSURE TIME HRS.	EXPOSURE RATE				COMMENTS
				X		Y		IN	OUT		X		Y		
				Front RAD	Back RAD	Front RAD	Back RAD				Front mR/hr.	Back mR/hr.	Front mR/hr.	Back mR/hr.	
1	13	Taped to liner approximately 4 feet above the floor, NE area Rx Building.	Vertical	10.16	5.14	135.13	135.65	3/25/82 1500	4/22/82 1057	668	15	8	202	203	
2	H7	Taped to the floor, NE area of Rx Building SE area under CF-T-1A	Horizontal	153.49	81.81	152.31	160.79	3/25/82 1500	4/22/82 1057	668	230	122	228	240	
3	B4	Placed on top of junction box, NE area of Rx Building	Horizontal	4357.49	49.93	258.50	225.84	3/25/82 1500	4/22/82 1057	668	6523	75	387	338	
4	V9	Taped to D-ring wall approximately 4 feet above floor, SE area Rx Building.	Vertical	88.60	NA	236.16	226.99	3/25/82 1500	4/22/82 1057	668	133	NA	353	340	
5	H6	Taped to west area of hatch cover, SE area of Rx Building	Horizontal	NA	467.23	1955.25	1846.07	3/25/82 1500	4/22/82 1057	668	NA	699	2927	2763	
6	V8	Taped to front side of aircooler B approximately 4' above floor, SE area of Rx Building	Vertical	61.13	166.03	222.10	219.22	3/25/82 1500	4/22/82 1057	668	91	240	332	328	
58	34F	Taped to floor, south area of Rx Building	Horizontal	16.56	79.36	186.66	182.27	3/25/82 1500	4/22/82 1057	668	25	119	279	273	
8	67W	Taped to D-ring wall approximately 4 feet above floor, NW area Rx Building	Vertical	58.59	23.87	103.70	100.15	3/25/82 1500	4/22/82 1057	668	9	4	155	149	
61	63	Taped to D-ring wall approximately 4 feet above floor, W area of Rx Building	Vertical	31.46	129.04	517.74	478.83	3/25/82 1500	4/22/82 1057	668	47	198	775	716	
63	V5	Taped to south equipment hatch wall approximately 4 feet above floor	Vertical	135.48	210.36	79.23	73.33	3/25/82 1500	4/22/82 1057	668	203	315	118	109	
7	H3	Taped to floor, West area of Rx Building	Horizontal	153.65	2455.26	357.63	349.62	3/25/82 1500	4/22/82 1057	668	230	3675	535	523	
64	55P	Taped to D-ring wall approximately 4 feet above floor, SW area of Rx Building	Vertical	30.05	11.16	130.27	120.94	3/25/82 1500	4/22/82 1057	668	45	17	195	193	
65	B3	Taped to underside of junction box approx. 8 feet off the floor	Vertical	214.26	154.39	175.19	183.76	3/25/82 1500	4/22/82 1057	668	321	234	262	275	
66	50F	Taped to floor, SW area of Rx Building	Horizontal	238.42	339.60	183.98	168.00	3/25/82 1500	4/22/82 1057	668	357	508	275	251	

TABLE A-8

POST-ELEVATION 347' GROSS DECONTAMINATION EXPERIMENT TLD DATA

LOCATION NUMBER	LOCATION DESCRIPTION	VERTICAL OR HORIZONTAL	TOTAL EXPOSURE				DATE & TIME OF EXPOSURE		EXPOSURE TIME HRS.	EXPOSURE RATE				COMMENTS
			X		Y		IN	OUT		X		Y		
			Front RAD	Back RAD	Front RAD	Back RAD				Front mR/hr	Back mR/hr	Front mR/hr	Back mR/hr	
30	Taped to liner approx. 4 feet above floor by hatch cover, NE area Rx Bldg.	Vertical	14.89	3.60	38.69	38.61	3/26/82 1328	4/22/82 1057	645.5	22	4	59	59	
31W	Taped to D-ring wall approx. 4 feet above floor, NE area Rx Bldg.	Vertical	94.43	17.27	42.34	39.56	3/26/82 1328	4/22/82 1057	645.5	145	25	65	60	
32	Taped to liner approx. 4 feet above floor, NE area Rx Bldg.	Vertical	5.11	12.62	22.04	20.99	3/26/82 1328	4/22/82 1057	645.5	7	18	33	32	
34W	Taped to D-ring wall approx. 4 feet above floor, East area Rx Bldg.	Vertical	48.23	15.23	32.69	28.99	3/26/82 1328	4/22/82 1057	645.5	73	22	50	44	
V3	Taped to liner behind enclosed stairwell approx. 4 feet above floor.	Vertical	7.30	NA	30.41	30.73	3/26/82 1328	4/22/82 1057	645.5	10	NA	46	47	
V4	Taped to outside enclosed stairwell wall approx. 4 feet above floor.	Vertical	33.42	24.81	42.25	41.00	3/26/82 1328	4/22/82 1057	645.5	51	37	65	63	
36W	Taped to D-ring wall approx. 4 feet above floor SE area Rx Bldg.	Vertical	16.29	3.50	36.48	33.95	3/26/82 1328	4/22/82 1057	645.5	24	4	56	52	
B2	Placed on top junction box, SE area of Rx Bldg.	Horizontal	39.57	211.89	60.94	56.97	3/26/82 1328	4/22/82 1057	645.5	60	327	94	87	
H10	Taped to floor near SW corner of hatch cover, South area of Rx Bldg.	Horizontal	68.14	1042.62	109.49	138.92	3/26/82 1328	4/22/82 1057	645.5	104	1614	167	214	
50W	Taped to East Side of head stand, SW area of Rx Bldg.	Vertical	82.38	5.81	69.76	70.19	3/26/82 1328	4/22/82 1057	645.5	127	9	107	108	
149F	Taped to floor by D-ring wall, SW area Rx Bldg.	Horizontal	NA	159.82	365.1	213.75	3/26/82 1328	4/22/82 1057	645.5	NA	247	565	330	
52	Taped to top of head stand, SW area of Rx Bldg.	Horizontal	73.08	358.95	45.62	45.55	3/26/82 1328	4/22/82 1057	645.5	113	556	70	70	
49	Taped to liner approx. 4 feet above floor, SW area of Rx Bldg.	Vertical	22.46	2.12	45.05	45.41	3/26/82 1328	4/22/82 1057	645.5	34	3	69	70	
V2	Taped to D-ring wall approx. 4 feet above floor, West Area Rx Bldg.	Vertical	28.79	7.09	49.23	49.90	3/26/82 1328	4/22/82 1057	645.5	44	10	76	77	
B1	Placed on top of junction box, West area of Rx Bldg.	Horizontal	27.15	16.92	70.07	63.01	3/26/82 1328	4/22/82 1057	645.5	42	26	108	97	
H9	Taped to floor approx. 4 feet South of open stairwell, West area of Rx Bldg.	Horizontal	59.91	505.63	82.34	88.56	3/26/82 1328	4/22/82 1057	645.5	92	783	127	136	
56	Taped to liner approx. 4 feet above floor, West area of Rx Bldg.	Vertical	15.23	9.49	32.46	32.65	3/26/82 1328	4/22/82 1057	645.5	23	14	50	50	

TABLE A-9

POST-ELEVATION 367' GROSS DECONTAMINATION EXPERIMENT TLD DATA

TLD #	LOCATION NUMBER	LOCATION DESCRIPTION	VERTICAL OR HORIZONTAL	TOTAL EXPOSURE				DATE & TIME OF EXPOSURE		EXPOSURE TIME HRS.	EXPOSURE RATE				COMMENTS
				X		Y		IN	OUT		X		Y		
				Front RAD	Back RAD	Front RAD	Back RAD				Front mR/hr	Back mR/hr	Front mR/hr	Back mR/hr	
71	13	367' El., Top D-ring wall, East area of Rx Building.	Horizontal	83.06	946.60	132.39	149.45	3/26/82 1328	4/22/82 1057	645.5	127	3014	204	231	
72	V11	367' El., Taped to Inside D-ring wall, East area Rx Building	Vertical	47.52	213.44	345.81	368.56	3/26/82 1328	4/22/82 1057	645.5	72	329	535	570	

FIGURE A-8

PRE-HPR-214 GROSS DECONTAMINATION EXPERIMENT
TLD MEASUREMENT LOCATIONS

Top of Elevator Shaft - 372' 7" Elevation

TABLE A-10

PRE-GROSS DECONTAMINATION EXPERIMENT TLD BETA AND GAMMA MEASUREMENTS OF THE DOME MONITOR AND ITS ENVIRONMENT

Type of Surface	TLD #	Location #	TLD F Exposure		TLD Y Exposure		LOCATION DESCRIPTION	TLD Back Exposure		Date & Time Exposure		Exposure Time (hrs)	B-Exposure Rate		Y - Exposure Rate		
			Front (RAD)	Back (RAD)	Front (RAD)	Back (RAD)		B (RAD)	Y (RAD)	IN	OUT		Front (mR/hr)	Back (mR/hr)	Front (mR/hr)	Back (mR/hr)	
Vertical Surface of Dome Monitor	1	H8-1	10.65	37.67	14.07	13.64	Horizontal surface, Top of Monitor	0.05	0.22	12/3/81 12:00	12/15/81 12:00	288	37	131	48	67	
	2	H8-2	32.67	548.79	159.01	174.47	Vertical Surface, Side of Monitor	0.05	0.22	12/3/81 12:00	12/15/81 12:00	288	113	1905	551	605	TLD had fallen and found on floor by monitor
	3	H8-3	238.05	<Bahd.	44.87	47.58	Vertical Surface, Side of Monitor	0.05	0.22	12/3/81 12:00	12/15/81 12:00	288	826	<Bahd.	155	166	
	4	H8-4	417.6	<Bahd.	32.69	39.14	Vertical Surface, Side of Monitor	0.05	0.22	12/3/81 12:00	12/15/81 12:00	288	1450	<Bahd.	113	137	
	5	H8-5	148.65	9.50	39.81	44.13	Vertical Surface, Side of Monitor	0.05	0.22	12/3/81 12:00	12/15/81 12:00	288	516	33	137	155	
Elevator Shaft Roof (Horizontal Surface)	6	H8-6	95.85	1073.03	112.61	124.42	Facing stairs and in front of hatch, TLD on immediate right	0.05	0.22	12/3/81 12:00	12/15/81 12:00	288	333	3725	390	1431	
	7	H8-7	37.89	926.13	114.50	123.37	Facing stairs and in front of hatch, TLD on immediate left	0.05	0.22	12/3/81 12:00	12/15/81 12:00	288	131	3215	397	428	
	8	H8-8	31.70	1229.50	109.25	126.58	Facing monitor and back to stairs, TLD on left corner of roof.	0.05	0.22	12/3/81 12:00	12/15/81 12:00	288	110	4269	379	439	
	9	H8-9	29.57	3362.59	183.90	224.37	Facing monitor and back to stairs, TLD on right corner of roof.	0.05	0.22	12/3/81 12:00	12/15/81 12:00	288	103	1228/hr.	638	778	
Control	10	H8-10	0.05	0.05	0.22	0.22	Carried to roof and brought out after placement of TLD's.	0.05	0.22	12/3/81 12:00	12/3/81 12:00	1	50	50	200	200	

Notes:

1. HPR-214

Horizontal and vertical measurements- front side of TLD system against monitor surface.

2. Elevator Roof Measurement

Horizontal Measurements- back side of TLD system against roof surface.

TABLE A-11

PRE-GROSS DECONTAMINATION EXPERIMENT RO-2A DOME MONITOR MEASUREMENTS

DATA POINT	VERTICAL OR HORIZONTAL	MEASUREMENT DESCRIPTION	RO-2A READINGS		DATE MEASUREMENT TAKEN	RO-2A INFORMATION			DOSE RATES		COMMENTS
			OPEN WINDOW mR/hr.	Closed Window mR/hr.		SERIAL #	CALIBRATION DUE DATE	BETA FACTOR	Y mR/hr.	B mR/hr.	
H8-1	Horizontal	Taken approx. 1" from outside surface of bucket.	100	100	12/15/81	681	1/22/82	4.3	100	≤ Bakd.	Plastic bucket over monitor, Dose readings through plastic bucket.
H8-2	Vertical	Taken approx. 1" from outside surface of bucket.	200	50	12/15/81	681	1/22/82	4.3	50	645	Plastic bucket over monitor, Dose reading through plastic bucket.
H8-3	Vertical	Taken approx. 1" from outside surface of bucket.	150	150	12/15/81	681	1/22/82	4.3	150	≤ Bakd.	Plastic bucket over monitor, Dose reading through plastic bucket.
H8-4	Vertical	Taken approx. 1" from outside surface of bucket.	200	100	12/15/81	681	1/22/82	4.3	100	430	Plastic bucket over monitor, Dose reading through plastic bucket.
H8-5	Vertical	Taken approx. 1" from outside surface of bucket.	NA	150	12/15/81	681	1/22/82	4.3	150	NA	Plastic bucket over monitor, Dose reading through plastic bucket.
H8-6	Horizontal	Instrument held approx. 1" from surface.	1000	150	12/15/81	681	1/22/82	4.3	150	3655	
		Instrument held approx. 3' from surface.	150	150	12/15/81	681	1/22/82	4.3	150	≤ Bakd.	
H8-7	Horizontal	Instrument held approx. 1" from surface.	1000	200	12/15/81	681	1/22/82	4.3	200	3440	
		Instrument held approx. 3' from surface.	100	50	12/15/81	681	1/22/82	4.3	50	170	
H8-8	Horizontal	Instrument held approx. 1" from surface.	600	100	12/15/81	681	1/22/82	4.3	100	2150	
		Instrument held approx. 3' from surface.	100	100	12/15/81	681	1/22/82	4.3	100	≤ Bakd.	
H8-9	Horizontal	Instrument held approx. 1" from surface.	1200	400	12/15/81	681	1/22/82	4.3	400	3440	
		Instrument held approx. 3' from surface.	200	150	12/15/81	681	1/22/82	4.3	150	215	

TABLE A-12

PRE-GROSS DECONTAMINATION EXPERIMENT RO-2A MEASUREMENTS

DATA POINT	VERTICAL OR HORIZONTAL	MEASUREMENT DESCRIPTION	RO-2A READINGS		DATE MEASUREMENT TAKEN	RO-2A INFORMATION			DOSE RATES		COMMENTS
			OPEN WINDOW mR/hr.	CLOSED WINDOW mR/hr.		SERIAL #	CALIBRATION DATE	BETA FACTOR	Y mR/hr.	B mR/hr.	
I3	Vertical	1"-1 1/2" from surface, 4' above floor	340	350	12/9/81	734	NA	3.5	350	< Bakd.	
II7	Horizontal	1"-1 1/2" from surface	300	400	12/9/81	734	NA	3.5	400	1400	
B4	Vertical	1"-1 1/2" from surface, Top of JB	250	220	12/9/81	734	NA	3.5	220	105	
V9	Vertical	1"-1 1/2" from surface, 4' above floor	500	400	12/9/81	734	NA	3.5	400	350	
H6	Horizontal	1" - 1 1/2" from surface	3.0 R/hr	3.0 R/hr	12/9/81	734	NA	3.5	3.0 R/hr	< Bakd.	
V8	Vertical	1"-1 1/2" from surface, 4' above floor	900	500	12/9/81	734	NA	3.5	500	1400	
H5	Horizontal	1" - 1 1/2" from surface	2.0 R/hr	800	12/9/81	734	NA	3.5	800	4200	
V5	Vertical	1/4" from surface, 4' above floor	175	150	12/9/81	705	10/26/81	4.1	150	103	
H3	Horizontal	1/4" from surface	2.0 R/hr	1.5 R/hr	12/9/81	705	10/26/81	4.1	1.5 R/hr	2050	
B3	Vertical	2"-4" from D-ring wall, 4" below JB	450	375	12/9/81	705	10/26/81	4.1	375	308	
V3	Vertical	1/4"-1/2" from surface, 4' above floor	50	50	12/9/81	681	1/22/82 DUE	4.3	50	< Bakd.	
V4	Vertical	1/4"-1/2" from surface, 4' above floor	100	75	12/9/81	681	1/22/82 DUE	4.3	75	108	
B2	Horizontal	1/4"-1/2" from surface, Top of JB	1.3 R/hr	150	12/9/81	681	1/22/82 DUE	4.3	150	4945	
H10	Horizontal	1/4"-1/2" from surface	950	250	12/9/81	681	1/22/82 DUE	4.3	250	3010	
50W	Vertical	1"-1 1/2" from surface	140	120	12/9/81	681	1/22/82 DUE	4.3	120	86	
I49	Horizontal	1"-1 1/2" from surface	10R/hr.	200	12/9/81	681	1/22/82 DUE	4.3	200	42.1R/hr.	
52	Horizontal	1"-1 1/2" from surface	500	200	12/9/81	681	1/22/82 DUE	4.3	200	1290	
V2	Vertical	1"-1 1/2" from surface, 4' above floor	140	120	12/9/81	681	1/22/82 DUE	4.3	120	86	
B1	Horizontal	1" - 1 1/2" from floor below JB	3.0R/hr.	600	12/9/81	681	1/22/82 DUE	4.3	600	10.3R/hr.	
H9	Horizontal	1"-1 1/2" from surface	1.3R/hr.	300	12/9/81	681	1/22/82 DUE	4.3	300	4.3R/hr.	
54	Horizontal	1"-1 1/2" from surface	250	130	12/9/81	681	1/22/82 DUE	4.3	130	516	
56	Vertical	1" - 1 1/2" from surface, 4' above floor	100	30	12/9/81	681	1/22/82 DUE	4.3	30	301	
63	Horizontal	1" - 1 1/2" from surface	25R/hr.	10R/hr.	12/9/81	681	1/22/82 DUE	4.3	25 R/hr	64.5R/hr.	
VII	Vertical	Taken perpendicular to surface	1.2 R/hr.	650	12/9/81	681	1/22/82 DUE	4.3	650	2365	

POST-GROSS DECONTAMINATION EXPERIMENT RO-2A MEASUREMENTS

E L E V A T I O N	DATA POINT	VERTICAL OR HORIZONTAL	MEASUREMENT DESCRIPTION	RO-2A READINGS		DATE MEASUREMENT TAKEN	RO-2A INFORMATION			DOSE RATE		COMMENTS
				OPEN WINDOW	CLOSED WINDOW		SERIAL #	CALIBRATION DATE	BETA FACTOR	Y mR/hr.	Z mR/hr.	
				mR/hr.	mR/hr.							
305'	H7	Horizontal	1" - 1 1/2" from surface	< Bakd.	250	3/25/82	A001	5/24/82 DUE	4.0	250	< Bakd.	
	B4	Horizontal	1" - 1 1/2" from surface, Top of JB	200	180	3/25/82	A001	5/24/82 DUE	4.0	180	80	
	V9	Vertical	1" - 1 1/2" from surface, 4' above surface	340	340	3/25/82	A001	5/24/82 DUE	4.0	340	< Bakd.	
	H6	Horizontal	1" - 1 1/2" from surface	3.8 R/hr	2.8R/hr	3/25/82	A001	5/24/82 DUE	4.0	2.8 R/hr	4000	
	V8	Vertical	1" - 1 1/2" from surface, 4' above floor	450	320	3/25/82	A001	5/24/82 DUE	4.0	320	520	
	70	Vertical	1" - 1 1/2" from surface, 4' above floor	190	190	3/25/82	731	4/10/82 DUE	3.8	190	< Bakd.	
	67W	Vertical	1" - 1 1/2" from surface, 4' above floor	210	190	3/25/82	731	4/10/82 DUE	3.8	190	76	
	66	Vertical	1" - 1 1/2" from surface, 4' above floor	200	200	3/25/82	731	4/10/82 DUE	3.8	200	< Bakd.	
	63	Vertical	1" - 1 1/2" from surface, 4' above floor	1000	900	3/25/82	731	4/10/82 DUE	3.8	900	380	
	52	Vertical	1" - 1 1/2" from surface, 4' above floor	1100	800	3/25/82	731	4/10/82 DUE	3.8	800	1140	
	V5	Vertical	1" - 1 1/2" from surface, 4' above floor	150	100	3/25/82	731	4/10/82 DUE	3.8	100	190	
	H3	Horizontal	1" - 1 1/2" from surface	900	800	3/25/82	731	4/10/82 DUE	3.8	800	380	
	55	Vertical	1" - 1 1/2" from surface, 4' above floor	300	270	3/25/82	731	4/10/82 DUE	3.8	270	114	
	83	Vertical	1" - 1 1/2" from surface, Front of JB	500	500	3/25/82	731	4/10/82 DUE	3.8	500	< Bakd.	
	50F	Horizontal	1" - 1 1/2" from surface	480	270	3/25/82	731	4/10/82 DUE	3.8	270	798	
347'	V3	Vertical	1" - 1 1/2" from surface, 4' above floor	80	60	3/26/82	579	3/26/82	4.0	60	80	
	V4	Vertical	1" - 1 1/2" from surface, 4' above floor	90	60	3/26/82	579	3/26/82	4.0	60	120	
	B2	Horizontal	1" - 1 1/2" from surface, Top of JB	160	90	3/26/82	579	3/26/82	4.0	90	280	
	H10	Horizontal	1" - 1 1/2" from surface	900	190	3/26/82	579	3/26/82	4.0	190	2040	
	V2	Vertical	1" - 1 1/2" from surface, 4' above floor	100	80	3/26/82	A001	2/24/82	4.0	80	80	
	B1	Horizontal	1/4" from surface, Top of JB	120	100	3/26/82	A001	2/24/82	4.0	100	80	
	H9	Horizontal	1/4" from surface	320	150	3/26/82	A001	2/24/82	4.0	150	680	
367'	V11	Vertical	Taken perpendicular to surface	1.2 R/hr	600	3/26/82	579	3/24/82	4.0	600	2400	

SECTION III

AIRBORNE DATA

Sampler locations for airborne concentration measurements are shown in Figures A-9 and A-10.

The airborne I-129, Cs-134, and Cs-137 concentrations were measured with a radioiodine molecular species sampler. The radioiodine sampler consisted of a particulate filter, a CdI_2 media cartridge, an IPH media cartridge, and two charcoal cartridges in series. As the air was pulled through the sampler, the components selectively absorbed, respectively, particulate I-129, Cs-134, and Cs-137; elemental I-129 and HOI-129; and the organic forms of I-129. During the stated sampling periods for the reactor building basement environment and elevations 305' and 347', the deposition and absorption rates of the radio-nuclides were assumed to be constant.

FIGURE A-9

FLOOR PLAN OF TMI-2 REACTOR BUILDING ELEVATION 305'
SHOWING SAMPLER LOCATIONS

PLAN EL 305'-6"

FIGURE A-10

FLOOR PLAN OF TMI-2 REACTOR BUILDING ELEVATION 347'
SHOWING SAMPLER LOCATION

TABLE A-14

GROSS DECONTAMINATION EXPERIMENT AIRBORNE CONCENTRATIONS OF I-129, Cs-134, and Cs-137

Elevation	Sampling Period	Sampling Time (Hours)	Total Volume Sampled (cc)	¹³⁴ Cs Concentration (μCi/cc)	¹³⁷ Cs Concentration (μCi/cc)	¹²⁹ I Concentration (μCi/cc)	¹²⁹ I Species (%)			Comments
							I ₂	HOI	Organic	
281' (Basement Environment)	12/10/81_12/12/81 0830_1045	50.25	5.91 x 10 ⁷	5.4±0.2 (-10)	5.5±0.02 (-09)	6.9±0.9 (-12)	<2	2	98	Location Uncertain
	12/12/81_12/13/81 1045_1730	30.75	3.03 x 10 ⁷	1.6±0.1 (-11)	1.7±0.1 (+10)	8.9±0.8 (-12)	<5	11	89	
	12/13/81_12/15/81 1730_1500	45.50	5.18 x 10 ⁷	3.9±0.2 (-11)	3.9±0.2 (-10)	8.3±0.8 (-12)	<5	7	93	
	12/18/81_12/23/81 1230_1035	118.00	1.39 x 10 ⁸	1.1±0.1 (-11)	1.2±0.1 (-10)	2.0±0.2 (-12)	6	10	84	
	12/23/81_12/29/81 1035_0950	143.50	1.36 x 10 ⁸	4.0±0.2 (-10)	4.2±0.01 (-9)	1.5±0.2 (-11)	<5	5	95	
	12/29/81_1/4/82 0950_0900	143.00	1.63 x 10 ⁸	3.9±0.1 (-11)	4.0±0.04 (-10)	1.6±0.2 (-11)	2	2	96	Location Uncertain
305'	12/10/81_12/12/81 0830_1045	50.25	5.55 x 10 ⁷	4.1±0.1 (-11)	4.4±0.05 (-10)	3.2±0.4 (-11)	1	3	96	
	12/12/81_12/13/81 1045_1730	30.25	3.81 x 10 ⁷	4.0±0.2 (-11)	4.0±0.1 (-10)	1.2±0.1 (-11)	<2	<2	100	
	12/13/81_12/15/81 1730_1500	45.50	5.10 x 10 ⁷	8.0±0.1 (-11)	8.6±0.2 (-10)	7.6±0.6 (-12)	<4	9	92	
	12/18/81_12/23/81 1230_1035	118.00	1.30 x 10 ⁸	9.2±0.1 (-11)	9.7±0.2 (-10)	4.1±0.4 (-12)	<5	7	93	
	12/23/81_12/29/81 1035_0950	143.50	1.78 x 10 ⁸	6.9±0.2 (-12)	7.1±0.2 (-11)	1.2±0.1 (-11)	<2	2	98	
	12/29/81_1/4/82 0950_0900	143.00	1.60 x 10 ⁸	1.9±0.2 (-11)	2.0±0.1 (-10)	2.3±0.2 (-11)	1	2	97	
347'	12/10/81_12/12/81 0830_1045	50.25	1.01 x 10 ⁸	2.1±0.2 (-10)	2.2±0.1 (-09)	6.3±0.6 (-12)	<3	7	93	
	12/12/81_12/13/81 1045_1730	30.75	7.00 x 10 ⁷	3.9±0.4 (-10)	4.0±0.2 (-09)	1.6±0.2 (-11)	<3	4	96	
	12/13/81_12/15/81 1730_1500	45.50	9.74 x 10 ⁷	3.7±0.4 (-10)	4.1±0.2 (-09)	5.4±0.5 (-11)	2	2	96	
	12/18/81_12/23/81 1230_1035	118.00	2.36 x 10 ⁸	4.5±0.1 (-12)	4.8±0.08 (-11)	1.0±0.1 (-11)	1	2	97	Location Uncertain
	12/23/81_12/29/81 1035_0950	143.50	3.27 x 10 ⁸	1.1±0.05 (-10)	1.1±0.06 (-09)	2.4±0.2 (-11)	1	1	98	Location Uncertain
	12/29/81_1/4/82 0950_1500	143.00	3.06 x 10 ⁸	3.4±0.2 (-11)	3.5±0.1 (-10)	1.9±0.2 (-12)	5	7	87	

SECTION IV

DECONTAMINATION FACTORS

The calculated decontamination factors based upon the surface deposition samples and TLD measurements are given in Section IV. For each surface deposition sample location, the decontamination factor was determined by dividing the pre-mean cesium concentration by the post-mean cesium concentration at the same location. The TLD-measured beta and gamma decontamination factors were determined by dividing the pre-experiment front or back dose rates by the post-gross front or back dose rates, respectively.

TABLE A-15
ELEVATION 305' DECONTAMINATION FACTORS FOR THE GROSS
DECONTAMINATION EXPERIMENT

Surface	Sample Location	Location Description	Decontamination Factors	
			Cs-134	Cs-137
VERTICAL	B4	Surface facing D-ring of 4th I-beam north of airlock #2, about 4' above the floor.	$9 \pm 6E0$	$9 \pm 6E0$
	11W	'B' D-ring wall about 4' above the floor, NE location.	$3 \pm 1E1$	$2.6 \pm 0.8E1$
			$2.0 \pm 0.7E0$	$1.4 \pm 0.5E0$
	V9	'B' D-ring wall about 4' above the floor, south side.	$5 \pm 2E-1$	$5 \pm 2E-1$
	V8	North wall of aircooler 'B' about 4' above the floor.	$3 \pm 2E0$	$3 \pm 2E0$
	V7	North wall of aircooler 'C' about 4' above the floor.	$7 \pm 4E-2$	$7 \pm 4E-2$
	V6	North wall of aircooler 'D' about 4' above the floor.	$1.0 \pm 0.7E0$	$1.0 \pm 0.6E0$
	46W	'A' D-ring wall about 4' above floor west of CFT 'B'.	$5 \pm 2E-1$	$5 \pm 1E-1$
	B3	Metal plate on 'A' D-ring wall west of CFT 'B'.	$1 \pm 1E-1$	$1 \pm 1E-1$
HORIZONTAL	67W	'A' D-Ring wall about 4' above floor, NW location.	$1.7 \pm 0.6E0$	$1.6 \pm 0.5E0$
	H7	Floor below NE corner of CFT 'A' support structure.	$6 \pm 8E1$	$6 \pm 8E1$
	34F	Floor in front of aircooler 'C', 6' from shield wall.	$8 \pm 4E1$	$8 \pm 4E1$
	50F	Floor in front of equipment hatch.	$3 \pm 4E0$	$5 \pm 2E0$
	H3	Floor near drain by the open stairwell.	$5 \pm 2E0$	$5 \pm 2E0$
	H2	Floor near the open stairwell entrance under welder.	$7 \pm 2E-1$	$7 \pm 2E-1$
	55F	Floor near the open stairwell entrance by the containment wall	$9 \pm 3E0$	$9 \pm 3E0$
	70F	Floor, NW sector.	$1.5 \pm 0.5E1$	$1.5 \pm 0.5E1$

TABLE A-16
ELEVATION 347' DECONTAMINATION FACTORS FOR THE GROSS
DECONTAMINATION EXPERIMENT

Surface	Sample Location	Location Description	Decontamination Factors	
			Cs-134	Cs-137
VERTICAL	31W	'B' D-ring wall about 4' above floor, ESE location.	$4 \pm 2E-1$	$4 \pm 1E-1$
	34W	'B' D-ring wall about 4' above floor, ESE location.	$5 \pm 2E-1$	$6 \pm 2E-1$
	V4	NW wall of enclosed stairwell about 4' above floor	$1.0 \pm 0.4E0$	$1.0 \pm 0.3E0$
	36W	'B' D-ring wall about 4' above floor, south side	$8 \pm 3 E-1$	$8 \pm 2 E-1$
	B2	Face of junction box on the south wall of 'B' D-ring.	$1.0 \pm 0.7E0$	$9 \pm 6 E-1$
	V2	'A' D-ring wall about 4' above floor, near head storage stand.	$4 \pm 1E-1$	$4 \pm 1E-1$
	50W	East vertical surface of head storage stand	$4 \pm 1E-1$	$4 \pm 1E-1$
	16W	'A' D-ring wall about 4' above floor, NW side.	$1.5 \pm 0.5E0$	$1.6 \pm 0.6E0$
HORIZONTAL	33F	Floor, NE sector	$1.1 \pm 0.4E2$	$1.1 \pm 0.4E1$
	91F	Floor, NE sector	$1.3 \pm 0.8E1$	$1.3 \pm 0.8E1$
	40F	Covered hatch diamond plate	$1.0 \pm 0.5E1$	$1.0 \pm 0.5E1$
	H10	Floor, SE of coolant pump and motor alignment stand	$2 \pm 1E1$	$2 \pm 1E1$
	149F	Floor, near south wall of 'A' D-ring.	$6 \pm 4E0$	$7 \pm 4E0$
	V10	Floor, east of head storage stand	$4 \pm 1E0$	$4 \pm 1E0$
	54F	Floor, near open stairwell, SW of its entrance.	$1.6 \pm 0.8E1$	$1.6 \pm 0.8E1$
	H9	Floor, south of open stairwell.	$1.4 \pm 0.5E1$	$1.4 \pm 0.4E1$
	115F	Floor, near floor drain in NW sector.	$3.0 \pm 0.8E1$	$2.9 \pm 0.8E1$

TABLE A-17
ELEVATION 367' DECONTAMINATION FACTORS FOR THE GROSS
DECONTAMINATION EXPERIMENT

Surface	Sample Location	Location Description	Decontamination Factors	
			Cs-134	Cs-137
Vertical	22IB	South surface of RC-P-2A support I-beam (2nd beam from south)	$2 \pm 1E0$	$2 \pm 1E0$
HORIZONTAL	26F	Walkway on top of 'A' D-ring wall, NW location	$8 \pm 2E-1$	$1.0 \pm 0.3E0$
	HI	Walkway on top of 'A' D-ring wall, SW location.	$2.8 \pm 0.8E0$	$2.8 \pm 0.8E0$
	I	RC-P-2A support I-beams, top surface (2nd beam from south).	$1.3 \pm 0.7E1$	$1.5 \pm 0.8E1$

TABLE A-18

ELEVATION 305' GROSS DECONTAMINATION EXPERIMENT DECONTAMINATION OR CONTAMINATION FACTORS
BASED UPON THE TLD MEASUREMENTS

Sample Location	Vertical or Horizontal	Pre Dose Rates				Post Dose Rates				Decontamination or Contamination Factors				Comments
		β		γ		β		γ		α		γ		
		Front mR/hr.	Back mR/hr.	Front mR/hr.	Back mR/hr.	Front mR/hr.	Back mR/hr.	Front mR/hr.	Back mR/hr.	Front	Back	Front	Back	
13	Vertical	NA	NA	623	664	15	8	202	203	NA	NA	DF 3.08	DF 3.27	
H7	Horizontal	158	920	426	468	230	122	228	240	CF 1.46	DF 7.54	DF 1.87	DF 1.95	
B4	Vertical	474	133	156	158	6523	75	387	338	CF 13.76	DF 1.77	CF 2.48	CF 2.14	
V9	Vertical	244	36	571	553	133	NA	353	340	DF 1.83	NA	DF 1.62	DF 1.63	
H6	Horizontal	6882	14.9 R/hr	2242	2635	NA	699	2927	2763	NA	DF 21.32	CF 1.31	CF 1.06	
V8	Vertical	110	146	577	573	91	249	332	328	DF 1.21	CF 1.71	DF 1.74	DF 1.75	
67W	Vertical	NA	NA	287	267	9	4	155	149	NA	NA	DF 1.85	DF 1.79	
63	Vertical	174	554	1448	1323	47	193	775	716	DF 3.70	DF 2.87	DF 1.87	DF 1.85	
H3	Horizontal	NA	7794	5177	5462	230	3675	535	523	NA	DF 2.12	DF 9.68	DF 10.44	
B3	Vertical	677	597	NA	386	321	231	262	275	DF 2.11	DF 2.58	NA	DF 1.40	
50F	Horizontal	303	5010	411	408	357	508	275	251	CF 0.85	DF 9.86	DF 1.49	DF 1.63	

TABLE A-19

ELEVATIONS 347' AND 367' GROSS DECONTAMINATION EXPERIMENT DECONTAMINATION FACTORS
BASED UPON THE TLD MEASUREMENTS

Elevation	Sample Location	Vertical or Horizontal	Pre Dose Rates				Post Dose Rates				Decontamination Factors				Comments
			β		γ		β		γ		β		γ		
			Front mR/hr.	Back mR/hr.	Front mR/hr.	Back mR/hr.	Front mR/hr.	Back mR/hr.	Front mR/hr.	Back mR/hr.	Front	Back	Front	Back	
347'	30	Vertical	70	25	52	86	22	4	55	59	3.18	6.25	1.56	1.46	
	31W	Vertical	215	64	53	91	145	25	65	60	1.48	2.56	1.43	1.52	
	V3	Vertical	75	19	66	47	10	NA	46	47	7.50	NA	1.43	1.00	
	V4	Vertical	60	57	88	87	51	37	65	63	1.18	1.54	1.35	1.38	
	36W	Vertical	125	14	110	119	24	4	56	52	5.21	3.50	2.11	2.29	
	H10	Horizontal	223	3852	244	264	104	1614	167	124	2.14	2.39	1.44	2.13	
	50W	Vertical	368	147	132	121	127	9	107	108	2.90	16.33	1.23	1.12	
	52	Horizontal	345	1665	143	141	113	556	70	70	15	2.99	2.11	2.01	
	V2	Vertical	137	26	121	122	44	10	76	77	3.11	2.60	1.63	1.58	
	B1	Horizontal	624	11.2 R/hr	458	453	42	26	108	97	14.86	430.77	4.24	4.67	
	H9	Horizontal	522	6202	200	264	92	763	127	136	5.67	8.02	2.20	1.94	
56	Vertical	63	32	80	79	23	14	50	50	2.74	2.29	1.60	1.50		
367'	13	Horizontal	407	7943	330	372	127	3014	204	231	3.20	2.64	1.62	1.61	
	V11	Vertical	178	573	763	741	72	329	535	570	2.47	1.74	1.43	1.30	

SECTION V

RO-2A AND TLD COMPARISONS

Table A-20 compares the contamination measurements of the RO-2A and TLD methods.

TABLE A-20

PRE-GROSS DECONTAMINATION EXPERIMENT RO-2A AND TLD COMPARISONS

ELEVATION	DATA POINT	RO-2A ¹		RO-2A ²		TLD			TLD vs. RO-2A ¹		TLD vs. RO-2A ²		RO-2A ¹ vs. RO-2A ²		COMMENTS
		β mR/hr.	γ mR/hr.	β mR/hr.	γ mR/hr.	β Back mR/hr.	γ		β	γ	β	γ	β	γ	
							Front mR/hr.	Back mR/hr.							
305A	H7	560	250	1,400	400	920	426	468	1.64	1.79	0.66	1.12	0.40	0.63	
	11W	≤ Bakd.	900	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	B4-2	≤ Bakd.	1,000	105	220	133	156	158	--	0.16	1.27	0.71	--	4.55	
	13	NA	NA	≤ Bakd.	350	NA	623	664	--	--	--	1.84	--	--	
	V9	NA	NA	350	400	36	571	553	--	--	0.10	1.41	--	--	
	H6	NA	NA	≤ Bakd.	3,000	14,900	2,242	2,635	--	--	--	0.81	--	--	
	V8	NA	NA	1,400	500	146	577	573	--	--	.10	1.15	--	--	
	34F	7,000	500	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	H5	NA	NA	4,200	800	2,743	935	898	--	--	0.65	1.15	--	--	
	B3	NA	NA	308	375	597	NA	386	--	--	1.94	1.03	--	--	
	50F	3,300	400	NA	NA	5010	411	408	1.52	1.03	--	--	--	--	
	V5	NA	NA	103	150	NA	NA	NA	--	--	--	--	--	--	
	H3	3,700	1,000	2,050	1,500	7,794	5,177	5,402	2.11	5.32	3.80	3.55	1.80	0.67	
	55F	1,900	1,500	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	63	NA	NA	NA	NA	554	1,448	1,323	--	--	--	--	--	--	
	66	NA	NA	NA	NA	265	283	303	--	--	--	--	--	--	
67W	37	280	NA	NA	NA	287	267	--	0.99	--	--	--	--		
70F	2,000	360	NA	NA	NA	NA	NA	--	--	--	--	--	--		
347	30W	NA	NA	NA	NA	25	92	86	--	--	--	--	--	--	

TABLE A-20 (Continued)

PRE-GROSS DECONTAMINATION EXPERIMENT RO-2A AND TLD COMPARISONS

ELEVATION	DATA POINT	RO-2A ¹		RO-2A ²		TLD			TLD vs. RO-2A ¹		TLD vs. RO-2A ²		RO-2A ¹ vs. RO-2A ²		COMMENTS
		B mR/hr.	Y mR/hr.	B mR/hr.	Y mR/hr.	R	Y		B	Y	R	Y	B	Y	
						Back mR/hr.	Front mR/hr.	Back mR/hr.							
347*	31W	70	35	NA	NA	64	93	91	0.91	2.63	--	--	--	--	
	33F	700	200	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	91F	1,400	300	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	34W	35	65	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	V4	70	75	108	75	57	88	87	0.81	1.17	0.53	1.17	0.65	1.00	
	V3	NA	NA	≤ Backd.	50	19	66	47	--	--	--	1.13	--	--	
	36W	35	75	NA	NA	14	118	119	0.40	1.58	--	--	--	--	
	B2-2	525	120	4945	150	NA	NA	NA	--	--	--	--	0.11	0.80	
	40F	7,530	500	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	H10	3,150	300	3010	250	3,852	241	264	1.22	0.84	1.27	1.01	1.05	1.20	
	V2	35	110	86	120	26	124	122	0.74	1.12	0.30	1.03	0.41	0.92	
	50W	210	165	86	120	147	132	121	0.70	0.77	1.71	1.05	2.44	1.38	
	52	NA	NA	1290	200	1665	148	141	--	--	1.29	0.72	--	--	
	149F	4,380	750	42.1R/hr.	200	NA	NA	NA	--	--	--	--	.10	3.75	
	V10	6,130	500	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	B1-2	105	150	10.3R/hr.	600	11.2R/hr.	458	453	106.67	3.04	1.09	0.76	0.01	0.25	
	54F	5,200	310	516	130	NA	NA	NA	--	--	--	--	10.08	2.38	
H9	3,500	390	4.3R/hr.	300	6282	280	264	1.79	0.70	1.46	0.91	0.81	1.30		
115F	1,000	90	NA	NA	NA	NA	NA	--	--	--	--	--	--		

TABLE A-20 (Continued)

PRE-GROSS DECONTAMINATION EXPERIMENT RO-2A AND TLD COMPARISONS

ELEVATION	DATA POINT	RO-2A ¹		RO-2A ²		TLD			TLD vs. RO-2A ¹		TLD vs. RO-2A ²		RO-2A ¹ vs. RO-2A ²		COMMENTS
		B mR/hr.	Y mR/hr.	B mR/hr.	Y mR/hr.	3 Back mR/hr.	Front mR/hr.	Back mR/hr.	B	Y	B	Y	B	Y	
347 ^h	56	NA	NA	301	30	32	80	79	--	--	0.11	2.65	--	--	
	16W	123	45	NA	NA	NA	NA	NA	--	--	3.88	0.70	--	--	
	63	NA	NA	64.5R/hr.	10R/hr.	250R/hr.	7857	6092	--	--	--	0.28	--	--	
367 ^h	13	NA	NA	NA	NA	7343	330	372	--	--	--	--	--	--	
	V11	NA	NA	2365	650	573	763	741	--	--	0.24	1.16	--	--	
	26F	770	280	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	III	2,000	290	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	I	4,300	270	NA	NA	NA	NA	NA	--	--	--	--	--	--	
	221B	158	325	NA	NA	NA	NA	NA	--	--	--	--	--	--	
372 ^h	H8-1	NA	NA	≤ Backd.	100	131	48	67	--	--	--	0.56	--	--	RO-2A ² measurements done for DOME Monitor Work, 1" from surface
	H8-2	NA	NA	645	50	1305	551	605	--	--	2.95	11.56	--	--	RO-2A ² readings done for DOME Monitor Work, 1" from surface
	H8-3	NA	NA	≤ Backd.	150	NA	155	166	--	--	--	1.07	--	--	RO-2A ² readings done for DOME Monitor Work, 1" from surface
	H8-4	NA	NA	430	100	NA	113	137	--	--	--	1.25	--	--	RO-2A ² readings done for DOME Monitor Work, 1" from surface
	H8-5	NA	NA	NA	150	33	137	155	--	--	--	0.97	--	--	RO-2A ² readings done for DOME Monitor Work, 1" from surface
	H8-6	2,500	400	3555	150	3726	390	431	1.49	1.03	1.02	2.74	0.68	2.67	RO-2A ² readings done for DOME Monitor Work, 1" from surface, RO-2A ¹ not same location TLD & RO-2A ²
	H8-7	2,500	400	3400	200	3216	397	428	1.29	1.03	0.93	2.06	0.73	2.00	RO-2A ² reading done for DOME Monitor Work, 1" from surface, RO-2A ¹ not same location TLD & RO-2A ²
	H8-8	NA	NA	2150	100	4265	379	439	--	--	1.99	4.09	--	--	RO-2A ² reading done for DOME Monitor Work, 1" from surface
	H8-9	NA	NA	3440	400	12R/hr	638	778	--	--	3.49	1.77	--	--	RO-2A ² readings done for DOME Monitor Work, 1" from surface

TABLE A-20 (Continued)

POST-GROSS DECONTAMINATION EXPERIMENT RO-2A AND TLD COMPARISONS

Elevation	Data Point	RO-2A ¹		RO-2A ²		TLD			TLD vs. RO-2A ¹		TLD vs. RO-2A ²		RO-2A ¹ vs. RO-2A ²		Comments
		β mR/hr.	γ mR/hr.	β mR/hr.	γ mR/hr.	β Back mR/hr.	γ	Back mR/hr.	β	γ	β	γ	β	γ	
305'	H7	858	80	<Bahd.	250	122	228	240	0.14	2.93	-	0.94	-	0.32	
	B4-2	400	300	80	180	75	387	338	0.19	1.21	0.94	2.01	5.00	1.67	
	V9	400	250	<Bahd.	340	-	353	340	-	1.39	-	1.02	-	0.74	
	H6	-	-	4000	2.8 R/hr	699	2927	2763	-	-	0.17	1.02	-	-	
	V8	100	375	520	320	249	332	328	2.49	0.88	0.48	1.03	0.19	0.17	
	34F	507	250	-	-	119	279	273	0.23	1.10	-	-	-	-	
	67W	<Bahd.	600	<Bahd.	190	4	155	149	-	0.25	-	0.80	-	3.16	
	63	-	-	380	900	193	775	716	-	-	0.51	0.83	-	-	
	V5	-	-	190	100	315	118	109	-	-	1.66	1.14	-	-	
	H3	<Bahd.	1000	380	800	3675	535	523	-	0.53	9.67	0.66	-	1.25	
	55F	3900	500	114	270	17	195	193	0.004	0.39	0.15	0.72	34.21	1.85	
	B3	-	-	<Bahd.	500	231	262	275	-	-	-	0.54	-	-	
50F	<Bahd.	150	798	270	508	275	251	-	1.75	0.64	0.97	-	0.56		
347'	31W	48	36	-	-	25	65	60	0.52	1.74	-	-	-	-	
	34W	40	50	-	-	22	50	44	0.55	0.94	-	-	-	-	
	V3	-	-	80	60	-	46	47	-	-	-	0.78	-	-	
	V4	80	80	120	60	37	65	63	0.46	0.80	0.31	1.07	0.67	1.33	
	36W	40	50	-	-	4	56	52	0.10	1.08	-	-	-	-	
	B2	480	100	280	90	327	94	87	0.68	0.91	1.17	1.01	1.71	1.11	

TABLE A-20 (Continued)

POST-GROSS DECONTAMINATION EXPERIMENT RO-2A AND TLD COMPARISONS

Elevation	Data Point	RO-2A ¹		RO-2A ²		TLD			TLD vs. RO-2A ¹		TLD vs. RO-2A ²		RO-2A ¹ vs. RO-2A ²		Comments
		β mR/hr.	γ mR/hr.	β mR/hr.	γ mR/hr.	β Back mR/hr.	γ		β	γ	β	γ	β	γ	
							Front mR/hr.	Back mR/hr.							
347'	H10	1287	150	2840	190	1614	167	214	1.25	1.27	0.57	1.00	0.45	0.79	
	50W	80	100	-	-	9	107	108	0.11	1.08	-	-	-	-	
	V2	40	70	80	80	10	76	77	0.25	1.09	0.13	0.96	0.50	0.88	
	B1	160	100	80	100	26	108	97	0.16	1.03	0.33	1.03	2.00	1.00	
	H9	-	-	680	150	783	127	106	-	-	1.15	0.88	-	-	
367'	V11	-	-	2400	600	329	535	520	-	-	0.14	0.92	-	-	

DO NOT MICROFILM
THIS PAGE

APPENDIX B
EQUIPMENT

CONTENTS

EQUIPMENT PROCUREMENT	B-1
MAJOR EQUIPMENT OPERATIONS	B-4
EQUIPMENT SPECIFICATIONS	B-8
PHOTOGRAPHS	

TABLES

B-1	Elevation 305' Low Pressure Flush	B-10
B-2	Polar Crane Low Pressure Flush	B-11
B-3	D-Rings, Missile Shields, Refueling Canal, and Service Structure Low Pressure Flush	B-12
B-4	Elevation 347'-6" Low Pressure Flush	B-13
B-5	Elevation 347'-6" High Pressure Flush	B-14
B-6	Elevation 305' High Pressure Flush	B-15
B-7	Pressure, Flow, and Temperature Adjustment	B-16

APPENDIX B - EQUIPMENT

EQUIPMENT PROCUREMENT

The purpose of this section is to describe the administrative system used to identify, procure, and track equipment during the decontamination experiment, to list problems encountered during the experiment, and to describe the planned and implemented improvements made to the procurement system since the end of the decontamination experiment.

Equipment Procurement System

The procurement system used during the decontamination experiment was fairly simple. The engineers identified equipment items necessary to perform specific work tasks and gave equipment requirements to the equipment engineer along with a need date for each item. The equipment engineer then had three options for procuring the items: (a) draw the item from stock on site, (b) fabricate the item on site, or (c) purchase the item from an offsite vendor. Either the equipment engineer or the equipment expeditor, provided by Catalytic, would then complete the appropriate form, depending on the chosen procurement option (material requisition, work authorization, or purchase requisition form). Once an item arrived on site, it was delivered to a location specified by the requesting engineer for use.

The equipment tracking system used was also fairly simple. A chronological log of equipment items ordered (from on site or off site) was kept, which listed for each item: description of item, number ordered, number received of total requested, and number still on order. This system was later modified to include the purchase order number for each piece of equipment.

Most of the problems encountered with this system were associated with the administrative tracking of orders or the physical tracing of equipment.

- o Equipment items were not tracked in logical major groups, such as National Liquid Blasting Company (NLB) pump and associated equipment, spin jet and hydrolance and associated equipment, air and water hoses, etc. This made it difficult to trace exactly which items had been procured and to identify the purpose of some items. The procurement list eventually became long and unwieldy, which also made the tracing of equipment difficult and occasionally led to the duplication of orders. Tracking by major groups would have eased this problem.
- o The equipment engineer did not keep a file of purchase orders and corresponding material received forms. This led to an equipment accountability problem. It was also difficult to assess the status of orders without a complete file of purchase orders indicating what was ordered, when it was ordered, and when it was expected.
- o The lack of either a central equipment storage area or an equipment storage location log led to accountability problems as well as operational problems. Often, the equipment that could not be traced through the existing paperwork tracking system could not be physically located. This resulted in duplicate orders and made it difficult to find equipment on short notice. Searching for equipment not only kept valuable workers busy, but frequently delayed training and entries.
- o The equipment tracking system did not track the equipment used for entries. This meant that no records were kept as to what equipment went into and out of the containment or where used equipment was stored, sent for decontamination, or sent for repair. This led to the duplication of many small tool items.

- o Failure of minor or major parts of major equipment, such as the NLB pump, spin jet, and hydrolances, was not anticipated early in the program. Thus, replacement parts were occasionally required on an emergency basis. This delayed training activities and entries.

Planned Improvements

Most of the equipment tracking problems experienced during the decontamination experiment could be solved by implementing additional administrative control, as follows:

- o Place group equipment orders into logical categories. Record on the order log the following information:
 - Purchase order number
 - Item description/quantity
 - Purchase order issuance date
 - Material received date
- o Keep each purchase order and material received form in a file.
- o Notify the equipment engineer of equipment needs as early as possible.
- o Keep a master storage log as to where each piece of equipment is stored. This should be grouped into logical categories as above.
- o Collect and store all equipment items required for each work package together for use during mock-up training and during the entry. This requires a dedicated staging area.

- o Purchase each piece of major equipment with a complete set of manufacturer's recommended replacement parts.

MAJOR EQUIPMENT OPERATIONS

This section describes major pieces of equipment used in the decontamination experiment, and some of the specific mechanical problems encountered in operation. The major equipment used was the NLB high pressure pump, water heater, spin jet, and hydrolance.

NLB 10150 Liquid Blasting Pump and Instantaneous Water Heater

The NLB high pressure water pump system consisted of a water supply source to the NLB pump, the instantaneous hot water heater and NLB pump, recirculation and drain lines from the NLB pump back to the water supply source, and supply lines from the NLB pump to containment penetration R-501 and into the containment (see Figures B-1 and B-2). The system is intended to supply a reliable source of pressurized, processed water to the liquid blaster equipment inside the containment building. The water will range in flow rate from 5 to 25 gpm, in temperature between 70 and 180 F, and in pressure between 1,000 and 10,000 psig. Water from the containment processed through the submerged demineralizer system (SDS) and the EPICOR system (process water) was used for the decontamination experiment. However, the process water contained tritium and therefore was treated as a radioactive liquid. Figure B-3 shows the decontamination experiment water system circulation.

This system was, on the whole, very dependable throughout the decontamination experiment. However, several problems were encountered.

- o Rupture Disk

As the pump system used contaminated process water, the rupture disk was a potential source of radioactive water release, and therefore

needed to be connected to a drain line and routed to a contaminated drain.

The rupture disk was located in an inconvenient spot on the pump, and a 6-inch extension pipe was needed to connect a drain line around the rupture disk. The installation of the 6-inch pipe, however, led to the rupture disk blowing at 5000 to 6000 psig below its rated value. It was determined that this was due to harmonic oscillations produced in the pipe by the water flowing past the pipe (see figure below).

This problem was solved by replacing the 6-inch pipe with a 50-foot rubber hose that damped the oscillations before they reached the rupture disk.

It should be noted that the need for providing a contained drainage path for the rupture disk was identified at a late date in the experimental planning.

o Pulsation Dampener

A weld between the pulsation dampener and the NLB pump discharge began to leak. The pulsation dampener was removed and replaced with a straight pipe until a new unit could be supplied by the vendor. Before the new dampener arrived, an administrative limit of 4000 psig was placed on the pump operation.

o Leaks

Several points in the pump system developed leaks:

- Solenoid operated damp valve - The solenoid was removed after causing some electrical problems, and the valve was made manual.

Manual damp valve - developed packing leaks

- Relief valve - developed packing leaks
- Flowmeters in the supply and drain lines - developed gas jet leaks

o Hot Water Heater

The hot water heater was designed to produce water up to 140 F at 25 gpm. System temperatures, as measured at the heater, averaged about 120 F, temperatures as measured at the pump storage tank averaged about 110 F, and temperatures at the hydrolance or spin jet averaged about 100 F. The desired temperature of 140 F at the spin jet or hydrolance was never reached.

Spin Jet and Hydrolance

Spin Jet

- o The water seal on the rotating nozzles developed leaks and needed replacement. The leaks were probably caused by operation of the nozzle rotational motor without water flow provided to the seal.
- o The hand-operated water supply trigger assembly on both spin jet units failed after use during training and had to be replaced. In both these cases, the loss of the spin jet units delayed personnel training activities.

Hydrolance

- o The trigger assemblies on several lances failed and were stuck partially open both during training and in-containment. Water was shut off using the manual safety valve on the lance.
- o The lances, as shipped from NLB, were deemed too short by site safety personnel because of the potential for the lance operator to shoot his foot during high pressure flushing. To accommodate the safety department's request, the short tip lances were replaced with longer tips, thus minimizing the accident potential.

In addition to the equipment for major operations of the experiment, a mechanical scrubber and wet vacuum system were tested in a small area. The mechanical scrubber was a 20-inch-diameter Clark industrial buffer with a 3-gallon-capacity liquid dispenser. The rotor was operated at less than 200 rpm to prevent excessive splatter.

The wet vacuum system consisted of three drums, pickup, and air hoses. A particulate filter was in the intake drum, and one drum contained a high efficiency particulate adsorber (HEPA) filter. The waste drum was modified to dump directly into a drain to keep the radiation levels at a minimum.

Command Center

The command center contained the control functions for entry into the reactor building with positions for safety, radiological engineering, operations, entry coordinator, and command center management. The center had provisions for videotaping, audio recording, communication, video cameras, and direct lines with the personnel, facilities, and functions necessary to control an entry.

EQUIPMENT SPECIFICATIONS

The equipment used in the decontamination experiment was specified by the engineers associated with each task. The technical data pertaining to the equipment are summarized below.

NLB High Pressure Pump and Instantaneous Water Heater

- o Model No. 10150E
- o 460-volt, 3-phase power
- o 0 to 25 gpm flow rate
- o 70 to 180 F water temperature
- o Up to 10,000 psig pressure
- o Purchase cost - \$59,485

NLB High Pressure Spin Jet

- o Spin Jet Floor Cleaner
 - Model No. 1100E-24
 - 110-volt, single phase power
 - Flow rate dependent upon nozzle
 - Up to 10,000 psig
 - Purchase cost - \$54,185

- o Hydrolance

- Model No. NCG-300-1 by NLB
- Flow rate dependent upon nozzle
- Up to 10,000 psig
- Purchase cost - \$7475

- o High pressure hose

- Model No. WP4 by NLB
- Inside diameter - 0.5 inch
- Outside diameter - 1.10 inches
- 40,000 psi burst pressure rating
- Purchase cost - \$6500 for 1200 feet

Losses due to hoses, lances, and nozzles for each area were determined for varying flow rates in order to find the required pump pressure to deliver desired pressure at the nozzle. These flow rates and pressures are summarized by area in Tables B-1 through B-6. During each operation, pump pressures, water temperatures, and water flow rates were monitored and recorded on a log sheet (see Table B-7) by the pump operator. Readings were taken every 15 minutes or whenever the pump started and stopped.

TABLE B-1. ELEVATION 305' LOW PRESSURE FLUSH

<u>Area</u>	<u>Temperature</u>	<u>Flow Rate</u>	<u>Pressure</u>		<u>Nozzle</u>
			<u>No Flow</u>	<u>Flow</u>	
<u>Misting</u>					
I LP	Ambient	20 gpm	5100 psig	4900 psig	0020
II LP	Ambient	20 gpm	5400 psig	5200 psig	0020
III LP	Ambient	20 gpm	5400 psig	5200 psig	0020
IV LP	Ambient	20 gpm	5600 psig	5400 psig	0020
<u>Flushing</u>					
I LP	Ambient	15 gpm	1800 psig	1600 psig	0050
II LP	140 F	25 gpm	4200 psig	4000 psig	0050
III LP	Ambient	25 gpm	4200 psig	4000 psig	0050
IV LP	140 F	15 gpm	2100 psig	1900 psig	0050

TABLE B-2. POLAR CRANE LOW PRESSURE FLUSH

<u>Area</u>	<u>Temperature</u>	<u>Flow Rate</u>	<u>Pressure</u>		<u>Nozzle</u>
			<u>No Flow</u>	<u>Flow</u>	
Misting	Ambient	20 gpm	7000 psig	6800 psig	0020
I PCL	Ambient	25 gpm	5700 psig	5500 psig	0050
II PCL	140 F	25 gpm	5700 psig	5500 psig	0050

TABLE B-3. D-RINGS, MISSILE SHIELDS, REFUELING CANAL, AND SERVICE
STRUCTURE LOW PRESSURE FLUSH

<u>Area</u>	<u>Temperature</u>	<u>Flow Rate</u>	<u>Pressure</u>		<u>Nozzle</u>
			<u>No Flow</u>	<u>Flow</u>	
Misting	Ambient	20 gpm	6500 psig	6300 psig	0020
Flushing	Ambient	25 gpm	5000 psig	4800 psig	0050

TABLE B-4. ELEVATION 347'-6" LOW PRESSURE FLUSH

<u>Area</u>	<u>Temperature</u>	<u>Flow Rate</u>	<u>Pressure</u>		<u>Nozzle</u>
			<u>No Flow</u>	<u>Flow</u>	
<u>Misting</u>					
V LP	Ambient	20 gpm	5400 psig	5200 psig	0020
VI LP	Ambient	20 gpm	5800 psig	5600 psig	0020
VII LP	Ambient	20 gpm	5800 psig	5600 psig	0020
VIII LP	Ambient	20 gpm	6100 psig	5900 psig	0020
<u>Flushing</u>					
V LP	Ambient	15 gpm	2000 psig	1800 psig	0050
VI LP	140 F	25 gpm	4700 psig	4500 psig	0050
VII LP	Ambient	25 gpm	4700 psig	4500 psig	0050
VIII LP	140 F	15 gpm	2400 psig	2200 psig	0050

TABLE B-5. ELEVATION 347'-6" HIGH PRESSURE FLUSH

Area	Temperature	Flow Rate	Pressure		Nozzle
			No Flow	Flow	
I HP					
Spin Jet	140 F	15 gpm	3300 psig	3100 psig	(4) #2506
Hydrolance	Ambient	10 gpm	2600 psig	2400 psig	#2510
II HP					
Spin Jet	Ambient	5 gpm	4600 psig	4400 psig	(4) #2502
Hydrolance	Ambient	10 gpm	2600 psig	2400 psig	#2510
III HP					
Spin Jet	140 F	5 gpm	2600 psig	2400 psig	(4) #2502
Hydrolance	Ambient	10 gpm	2600 psig	2400 psig	#2510
IV HP					
Spin Jet	Ambient	5 gpm	6600 psig	6400 psig	(4) #2502
Hydrolance	Ambient	10 gpm	2600 psig	2400 psig	#2510
V HP					
Spin Jet	Ambient	25 gpm	8210 psig	8000 psig	(4) #2506
Hydrolance	Ambient	10 gpm	2600 psig	2400 psig	#2510
VI HP					
Spin Jet	Ambient	25 gpm	6500 psig	6300 psig	(4) #2506
Hydrolance	Ambient	10 gpm	2700 psig	2500 psig	#2510
VII HP					
Spin Jet	140 F	25 gpm	4500 psig	4300 psig	(4) #2510
Hydrolance	Ambient	10 gpm	2700 psig	2500 psig	#2510
VIII HP					
Spin Jet	Ambient	15 gpm	7400 psig	7200 psig	(4) #2504
Hydrolance	Ambient	10 gpm	2700 psig	2500 psig	#2510
IX HP					
Spin Jet	Ambient	15 gpm	5500 psig	5300 psig	(4) #2504
Hydrolance	Ambient	10 gpm	2800 psig	2600 psig	#2510

TABLE B-6. ELEVATION 305' HIGH PRESSURE FLUSH

<u>Area</u>	<u>Temperature</u>	<u>Flow Rate</u>	<u>Pressure</u>		<u>Nozzle</u>
			<u>No Flow</u>	<u>Flow</u>	
X HP					
Spin Jet	140 F	15 gpm	2900 psig	2700 psig	(4) #2506
Hydrolance	Ambient	10 gpm	2500 psig	2300 psig	#2510
XI HP					
Spin Jet	140 F	15 gpm	3500 psig	3300 psig	(4) #2510
Hydrolance	Ambient	10 gpm	2500 psig	2300 psig	#2510
XII HP					
Spin Jet	Ambient	15 gpm	8000 psig	7800 psig	(4) #2506
Hydrolance	Ambient	10 gpm	2600 psig	2400 psig	#2510

TABLE B-7. PRESSURE, FLOW, AND TEMPERATURE ADJUSTMENT

Date: _____										
Time	P In	P Out	Temp. Reservoir	Temp. (Inlet)	Flow Rate			Pump Hr.	Table Ref.	P (No Flow)
:00										
:15										
:30										
:45										
:00										
:15										
:30										
:45										
:00										
:15										
:30										
:45										
:00										
:15										
:30										
:45										
:00										
:15										
:30										
:45										

Operator _____

Figure B-1. Pump equipment layout.

Figure B-2. Pump equipment layout.

NOTES

1. Penetration R-561 modified per ECM-963

2. Nonstandard symbols

□ — Coupler & shield for high pressure hose

⊕ — Pulsation dampener

⊕_s — Snubber

⊐ — Rupture disc

3. Bottle to collect oil-water mixture from casing drain

Figure B-3. Decontamination experiment water system.

SPIN-JET FOR FLOOR DECON

Figure B-4. Spin jet.

Figure B-5. Spin jet nozzles.

Figure B-6. Hydrolance.

Figure B-7. Wet-vacuum system.

Figure B-8. Command center.

DO NOT MICROFILM
THIS PAGE

APPENDIX C

APPENDIX C

RAW DATA

CONTENTS

HIGH PRESSURE FLUSH - ELEVATION 305'
LOW PRESSURE FLUSH - ELEVATION 305'
STRIPPABLE COATING TEST - ELEVATION 305' and HEAD STORAGE STAND
- ELEVATION 347'-6"
LOW PRESSURE AND HIGH PRESSURE FLUSH - ELEVATION 347'-6"
MECHANICAL SCRUBBER TEST - ELEVATION 347'-6"
LOW PRESSURE FLUSH - D-RINGS, REACTOR SERVICE STRUCTURE, MISSILE
SHIELDS, REFUELING CANALS, AND BRIDGES
LOW PRESSURE FLUSH - POLAR CRANE
REACTOR BUILDING AIR SAMPLE DATA - FEBRUARY 26 THROUGH MARCH 26, 1982
OPERATIONAL PARAMETERS - ELEVATION 305' LOW PRESSURE FLUSH
OPERATIONAL PARAMETERS - ELEVATION 305' HIGH PRESSURE FLUSH
OPERATIONAL PARAMETERS - ELEVATION 305' OVERHEAD, WALLS, ETC. HIGH
PRESSURE FLUSH
OPERATIONAL PARAMETERS - ELEVATION 347'-6" LOW PRESSURE FLUSH
OPERATIONAL PARAMETERS - ELEVATION 347'-6" HIGH PRESSURE FLUSH
OPERATIONAL PARAMETERS - POLAR CRANE
OPERATIONAL PARAMETERS - MISSILE SHIELDS, D-RINGS, CANALS
LOW PRESSURE REFLUSH AFTER HIGH PRESSURE FLUSH - ELEVATION 305'

HIGH PRESSURE FLUSH - ELEVATION 305'

HP Area	Location	Surface	Pre-Test Area Gamma (mrem)	Post-Test Area Gamma (mrem)	Pre-Test Contact Gamma (mrem)	Post-Test Contact Gamma (mrem)	Pre-Test Contact Beta (mrem)	Post-Test Contact Beta (mrem)	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
									Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90
X	12-1	Floor	100	120	150	130	608	190						
X	12-2	Floor	100	100	150	120	722	304						
X	12-3	Floor	108	120	130	120	494	114	4.22x10 ⁶	4.0x10 ⁵	1.42x10 ⁵	1.7x10 ⁵	1.9x10 ⁴	6.88x10 ³
X	12-4	Floor	120	140	160	150	190	76						
X	12-5	Floor	110	120	140	110	684	266						
X	15	CFT A Pipe	NA	170	100	100	228	152	3.77x10 ⁵	4.0x10 ⁴	2.66x10 ⁴	4.2x10 ⁵	3.96x10 ⁴	2.88x10 ⁴
XI	1	Floor	220	180	290	250	1930	1330	4.88x10 ⁶	4.88x10 ⁵	1.22x10 ⁵	3.33x10 ⁵	3.3x10 ⁴	7.77x10 ³
XI	21	Floor by #9	210	200	250	240	608	114	3.33x10 ⁶	3.11x10 ⁵	5.77x10 ⁴	8.86x10 ⁴	7.99x10 ³	3.1x10 ³
XII	23	Floor by #12	350	350	420	380	684	456	2.15x10 ⁵	2.44x10 ⁴	4.66x10 ³	1.11x10 ⁶	1.08x10 ⁵	2.89x10 ⁴
XII	29	Floor by #19	800	1000	1900	1400	9880	4290	1.22x10 ⁶	1.22x10 ⁵	2.89x10 ⁴	1.64x10 ⁶	1.58x10 ⁵	1.42x10 ⁴
XII	34	Floor	330	330	280	280	1590	507	8.44x10 ⁶	8.44x10 ⁵	1.09x10 ⁵	9.55x10 ⁵	9.32x10 ⁴	2.2x10 ⁴
XII	42	CFT B Pipe	NA	NA	3700	NA	1140	NA	1.15x10 ⁶	1.15x10 ⁵	2.2x10 ⁵			
XII	50	Floor	420	400	340	300	2120	1170	2.44x10 ⁶	2.22x10 ⁵	8.66x10 ⁴	1.53x10 ⁵	1.42x10 ⁴	5.1x10 ³
XII	53-3	Floor	600	1200	900	1800	2660	780	1.75x10 ⁶	1.78x10 ⁵	1.35x10 ⁵	7.5x10 ⁵	7.54x10 ⁴	2.66x10 ⁴
XII	53-1	Floor		1300		3600		9360						
XII	53-2	Floor		1100		1500		1170						
XII	53-4	Floor		1100		1600		3900						
XII	53-5	Floor		900		1200		780						

LCW PRESSURE FLUSH - ELEVATION 305'

HIP Area	Location	Surface	Pre-Test Area Gamma (mrem)	Post-Test Area Gamma (mrem)	Pre-Test Contact Gamma (mrem)	Post-Test Contact Gamma (mrem)	Pre-Test Contact Beta (mrem)	Post-Test Contact Beta (mrem)	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
									Cs-137	Cs-134	Si-90/Y-90	Cs-137	Cs-134	Si-90/Y-90
I	1	Floor	240	220	320	290	106C	1930	4.66x10 ⁶	2.66x10 ⁵	1.06x10 ⁵	4.88x10 ⁶	4.88x10 ⁵	1.22x10 ⁵
I	12-1	Floor	160	100	300	150	266C	608						
I	12-2	Floor	150	100	260	150	129G	722						
I	12-3	Floor	160	108	250	130	950	494	4.66x10 ⁶	4.44x10 ⁵	1.75x10 ⁵	4.22x10 ⁶	4.00x10 ⁵	1.42x10 ⁵
I	12-4	Floor	180	120	230	160	2730	190						
I	12-5	Floor	200	110	340	140	2500	684						
I	15	CFT A Pipe	200		200	100	380	228				3.77x10 ⁵	4.00x10 ⁴	2.66x10 ⁵
II	21	Floor by #9	200	210	260	250	912	608	1.7x10 ⁶	1.66x10 ⁵	4.44x10 ⁴	3.33x10 ⁶	3.11x10 ⁵	5.77x10 ⁴
II	23	Floor by #12	400	350	450	420	570	684	8.2x10 ⁶	7.99x10 ⁵	1.7x10 ⁵	2.15x10 ⁵	2.44x10 ⁴	4.66x10 ⁵
II	29	Floor by #19	1000	800	2000	900	15200	9880	2.22x10 ⁷	2.22x10 ⁵	4.88x10 ⁵	1.22x10 ⁶	1.22x10 ⁵	2.89x10 ⁴
II	34	Floor	400	330	340	280	4780	1500	2.66x10 ⁷	2.66x10 ⁵	1.93x10 ⁴	8.44x10 ⁶	8.44x10 ⁵	1.09x10 ⁵
II	42	CFT B Pipe	NA	NA	3200	1700	Not Taken	1140	5.77x10 ⁶	5.77x10 ⁵	2.88x10 ⁵	1.15x10 ⁶	1.15x10 ⁵	2.20x10 ⁵
II	50	Floor	400	420	460	340	2810	2120	5.1x10 ⁶	5.32x10 ⁵	1.3x10 ⁵	2.44x10 ⁶	2.22x10 ⁵	8.66x10 ⁴
III	53-3	Floor	800	600	1000	900	4560	2650	4.88x10 ⁶	5.1x10 ⁵	2.44x10 ⁵	1.75x10 ⁶	1.78x10 ⁵	1.35x10 ⁵
III	61	Floor	1000	600	3400	1000	17480	8350				9.32x10 ⁶	9.32x10 ⁵	3.55x10 ⁵
IV	65-1	Floor	300	180	600	340	6080	2120						
IV	65-2	Floor	280	200	400	270	10640	2770						
IV	65-3	Floor	300	200	600	300	14400	2650	2.88x10 ⁷	2.88x10 ⁵	5.55x10 ⁵	5.55x10 ⁵	5.77x10 ⁵	1.69x10 ⁵
IV	65-4	Floor	360	230	400	380	21280	2350						
IV	65-5	Floor	340	240	800	420	9120	2950						
IV	70	Floor	220	180	340	210	4780	1100	6.6x10 ⁶	6.88x10 ⁵	1.62x10 ⁵	9.32x10 ⁶	9.32x10 ⁵	2.44x10 ⁵

C-2

STRIPPABLE COATING TEST - ELEVATION 305' AND HEAD STORAGE STAND - ELEVATION 347'-6"

LP/ HP	Area	Location	Surface	Pre-Test	Post-Test	Pre-Test	Post-Test	Pre-Test	Post-Test	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²			Intermediate	Intermediate
				Area Gamma (mrem)	Area Gamma (mrem)	Contact Gamma (mrem)	Contact Gamma (mrem)	Contact Beta (mrem)	Contact Beta (mrem)	Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90	Contact Gamma	Contact Beta
		65		-	-	300	300	2240	2400	1.35×10^6	1.33×10^5	4.22×10^4	5.99×10^4	5.55×10^3	7.77×10^3	300	800
		70		-	-	290	200	672	880	1.27×10^7	1.62×10^5	4.22×10^4	5.77×10^4	5.99×10^3	3.11×10^3	280	400
		76		-	-	500	200	5440	3600	1.07×10^7	1.02×10^6	3.11×10^5	1.95×10^5	1.91×10^4	1.86×10^4	600	2000
		77		-	-	700	800	1280	1000	2.02×10^6	2.0×10^5	3.55×10^4	7.55×10^4	8.44×10^3	8.66×10^3	600	800
		50		-	-	90	110	96	40	7.10×10^4	5.99×10^3	1.82×10^3	2.89×10^3	LLD	3.33×10^2	120	NDB
		51		-	-	60	150	4928	3800	2.44×10^6	2.44×10^5	4.66×10^5	4.44×10^4	4.44×10^3	3.11×10^4	150	3000
		52		-	-	140	100	4672	4400	1.24×10^6	1.22×10^5	1.73×10^5	5.11×10^4	4.22×10^3	1.53×10^4	150	3000
		150		-	-	140	110	4672	4560	3.77×10^6	3.77×10^5	5.55×10^5	-	-	-	120	3920
		151		-	-	60	80	128	100	4.44×10^4	3.77×10^3	3.55×10^3	-	-	-	80	120
		159		-	-	100	-	128	-	6.66×10^4	6.22×10^3	1.51×10^9	-	-	-	-	-
		160		-	-	120	-	64	-	5.33×10^4	5.77×10^3	2.13×10^3	-	-	-	-	-
		162		-	-	140	140	5312	5440	5.55×10^6	5.33×10^5	6.88×10^5	7.55×10^4	7.99×10^3	4.44×10^4	125	4300
		163		-	-	80	100	224	200	5.11×10^4	4.0×10^3	5.77×10^3	2.44×10^3	LLD	4.0×10^2	110	40

Intermediate Test Results
(before stripping)

65	7.55×10^4	1.86×10^4	1.31×10^4
70	4.0×10^4	4.22×10^3	2.44×10^3
76	2.22×10^5	2.22×10^4	6.44×10^3
77	1.67×10^4	2.44×10^3	1.20×10^3
50	6.66×10^2	LLD	2.44×10^2
51	3.33×10^4	3.11×10^3	4.0×10^3

LOW PRESSURE AND HIGH PRESSURE FLUSH - ELEVATION 347'-6"

C-5

LP/HP Area	Location	Surface	Pre-Test Area Gamma (mrem)	Post-Test Area Gamma (mrem)	Pre-Test Contact Gamma (mrem)	Post-Test Contact Gamma (mrem)	Pre-Test Contact Beta (mrem)	Post-Test Contact Beta (mrem)	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
									Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90
V I	27	Diamond Plate	180	90	320	150	7520	370	7.1x10 ⁶	7.1x10 ⁵	1.55x10 ⁵	5.32x10 ⁵	4.88x10 ⁴	4.66x10 ³
V I	28	Diamond Plate	110	100	210	100	6360	851	4.0x10 ⁶	3.77x10 ⁵	7.99x10 ⁴	5.11x10 ⁵	4.66x10 ⁴	1.63x10 ⁴
V I	29-1	Concrete Floor	100	100	160	140	1760	333						
V I	29-2	↓	80	90	100	60	480	185						
V I	29-3		100	90	160	100	1760	296	1.53x10 ⁷	1.53x10 ⁶	7.39x10 ⁵	4.44x10 ⁴	4.22x10 ³	3.11x10 ³
V I	29-4		120	80	160	100	2560	222						
V I	29-5		100	90	180	100	2480	148						
V I	87		100	90	260	180	4560	2294	1.24x10 ⁷	1.24x10 ⁶	4.88x10 ⁵	1.53x10 ⁵	1.46x10 ⁴	6.44x10 ³
V I	129	Cable Tray	NA	NA	300	180	2000	518	2.13x10 ⁷	2.11x10 ⁶	8.88x10 ⁵	3.11x10 ⁴	2.66x10 ³	1.75x10 ³
V I	130	Cable Tray	NA	NA	300	180	6000	333	1.33x10 ⁷	1.33x10 ⁶	5.11x10 ⁵	1.65x10 ⁴	1.86x10 ³	4.22x10 ²
V II	89-1	Concrete Floor	60	80	160	110	1760	703						
V II	89-2	↓	60	70	120	120	2720	666						
V II	89-3		80	65	160	80	2560	777	1.35x10 ⁷	1.35x10 ⁶	5.55x10 ⁵	5.77x10 ⁵	5.99x10 ⁴	1.46x10 ⁴
V II	89-4		100	60	240	130	7040	1147						
V II	89-5		80	70	120	60	1920	333						
V II	91-1		50	60	50	40	440	333						
V II	91-2		50	50	60	48	480	341						
V II	91-3		60	55	80	60	560	407	5.33x10 ⁵	5.11x10 ⁴	3.11x10 ⁴	1.53x10 ⁵	1.53x10 ⁴	5.11x10 ³
V II	91-4		60	50	80	70	720	333						
V II	91-5		60	50	180	130	2480	1258						

LOW PRESSURE AND HIGH PRESSURE FLUSH - ELEVATION 347' - 6"

LP/HP Area: Location	Surface	Pre-Test Area Gamma (mrem)	Post-Test Area Gamma (mrem)	Pre-Test Contact Gamma (mrem)	Post-Test Contact Gamma (mrem)	Pre-Test Contact Beta (mrem)	Post-Test Contact Beta (mrem)	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
								Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90
VIII VIII 60-5		60	50	250	150	4875	2535						
VIII VIII 111	D-Ring Wall	NA	50	160	-	2496	-						
VIII VIII 112	Concrete Floor	70	60	160	90	2496	468	6.88x10 ⁶	6.66x10 ⁵	3.89x10 ⁵	7.55x10 ⁴	5.99x10 ³	4.88x10 ³
VIII IX 62-1	Concrete Floor	140	100	140	100	838	741						
VIII IX 62-2	Incore Instrument Seal Table	200	100	140	110	468	468						
VIII IX 62-3		180	140	110	80	663	234	4.88x10 ⁵	5.11x10 ⁴	1.55x10 ⁴	6.44x10 ⁴	5.55x10 ³	5.55x10 ³
VIII IX 62-4		140	150	110	80	545	390						
VIII IX 62-5		200	120	130	150	1638	1170						
VIII IX 63		500	-	-	120	-	234	-	-	-	8.2x10 ⁴	9.99x10 ³	9.10x10 ³
VIII IX 64	Concrete Floor	-	-	-	180	-	468	-	-	-	1.69x10 ⁵	1.58x10 ⁴	1.42x10 ⁴
VIII IX 86		160	130	220	180	3042	2028	3.33x10 ⁶	3.33x10 ⁵	1.2x10 ⁵	3.11x10 ⁶	3.11x10 ⁵	1.06x10 ⁵
VIII IX 1158	Floor-Concrete	100	70	120	80	702	468	1.62x10 ⁶	1.57x10 ⁵	8.44x10 ⁴	2.06x10 ⁵	2.06x10 ⁴	5.33x10 ³
V I 79	Liner Wall										3.77x10 ⁴	4.88x10 ³	1.49x10 ³

C-6

LOW PRESSURE AND HIGH PRESSURE FLUSH - ELEVATION 347'-6"

LP/HIP Area	Location	Surface	Pre-Test Area	Post-Test Area	Pre-Test Contact	Post-Test Contact	Pre-Test Contact	Post-Test Contact	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
			Gamma (mrem)	Gamma (mrem)	Gamma (mrem)	Gamma (mrem)	Beta (mrem)	Beta (mrem)	Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90
VI IV	133	Index Fix-Vert.	NA	180	120	120	80	111	9.1x10 ⁴	8.44x10 ³	LLD	2.44x10 ⁴	2.09x10 ³	5.11x10 ²
VI IV	134	Index Fix	NA	160	80	90	80	111	2.22x10 ⁵	2.44x10 ⁴	2.44x10 ³	2.44x10 ⁴	1.44x10 ³	5.11x10 ²
VI IV	145	Concrete Floor	80	150	140	160	660	-	2.44x10 ⁶	2.44x10 ⁵	1.38x10 ⁵			
VI IV	147	Concrete Floor	-		-	-								
VI V	37	Diamond Plate	310	260	460	200	8560	666	5.33x10 ⁶	5.33x10 ⁵	1.51x10 ⁵	2.13x10 ⁵	1.89x10 ⁴	5.99x10 ³
VI V	39-1	Concrete Floor	80	80	150	120	1400	1776						
VI V	39-2	↓	100	80	150	140	1400	888						
VI V	39-3		100	100	180	125	2480	685				9.77x10 ⁵	8.88x10 ⁴	5.33x10 ⁴
VI V	39-4		100	90	250	180	3800	1554						
VI V	39-5		100	90	250	200	3000	925						
VI V	40	Diamond Plate	300	200	260	150	5360	1147	5.77x10 ⁶	5.55x10 ⁵	1.31x10 ⁵	3.11x10 ⁵	2.66x10 ⁴	1.02x10 ⁴
VI V	41	Diamond Plate	200	130	200	100	2340	370	3.55x10 ⁵	3.55x10 ⁴	1.06x10 ⁴	1.42x10 ⁵	1.33x10 ⁴	3.77x10 ³
VI V	42	Diamond Plate	180	140	220	110	2262	185	6.66x10 ⁵	6.44x10 ⁴	1.89x10 ⁴	4.66x10 ⁴	4.88x10 ³	2.89x10 ³
VI V	44	RCPS-Hor.	NA	NA	200	240	312	4662	1.46x10 ⁷	1.46x10 ⁶	2.89x10 ⁵	1.69x10 ⁷	1.65x10 ⁶	3.55x10 ⁵
VI V	45	RCPS-Vert.	NA	NA	100	80	195	259	1.24x10 ⁵	1.24x10 ⁴	7.77x10 ³	1.89x10 ⁵	1.95x10 ⁴	4.22x10 ³
VI V	46	RCPS-Hor.	NA	NA	200	200	1950	5920	1.06x10 ⁷	1.06x10 ⁶	3.55x10 ⁵	7.99x10 ⁶	7.77x10 ⁵	1.82x10 ⁵
VI V	47	RCPS-Vert.	NA	NA	140	105	78	370	3.33x10 ⁴	3.55x10 ³	2.22x10 ³	1.98x10 ⁵	1.99x10 ⁴	3.77x10 ³

C-7

LOW PRESSURE AND HIGH PRESSURE FLUSH - ELEVATION 347'-6"

LP/HIP Area	Location	Surface	Pre-Test Area Gamma (mrem)	Post-Test Area Gamma (mrem)	Pre-Test Contact Gamma (mrem)	Post-Test Contact Gamma (mrem)	Pre-Test Contact Beta (mrem)	Post-Test Contact Beta (mrem)	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
									Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90
VI V	107	Concrete Floor	160	120	160	100	1360	777	3.55x10 ⁶	3.55x10 ⁵	2.04x10 ⁵	7.99x10 ⁴	6.88x10 ³	3.11x10 ³
VI V	114	Index Fixture Vert.	NA	NA	100	60	160	56	1.98x10 ⁵	1.95x10 ⁴	1.28x10 ³	2.07x10 ⁴	2.02x10 ³	7.54x10 ²
VI V	115A	Index Fixture Vert.	NA	NA	80	50	660	93	2.66x10 ⁵	2.66x10 ⁴	9.99x10 ³	5.11x10 ³	LLD	4.66x10 ²
VI V	127	LOCA-Duct	NA	NA	600	480	780	1924	2.44x10 ⁵	1.22x10 ⁴	1.13x10 ⁵	1.66x10 ⁵	1.53x10 ⁴	9.55x10 ³
VI V	128	LOCA-Duct	NA	NA	590	395	78	185	5.55x10 ³	LLD	LLD	4.66x10 ⁴	3.77x10 ³	1.06x10 ³
VI VI	48-1	Concrete Floor ↓	120	120	400	140	2340	1287						
VI VI	48-2		140	100	320	130	3042	1404						
VI VI	48-3		140	130	250	140	5265	1794	1.18x10 ⁷	1.15x10 ⁶	3.11x10 ⁵	3.11x10 ⁵	3.33x10 ⁴	1.38x10 ⁴
VI VI	48-4		140	110	210	200	2691	624						
VI VI	48-5		140	110	260	120	3665	819						
VI VI	50	RHSS-Vert.	NA	NA	190	140	117	156	1.49x10 ⁵	1.31x10 ⁴	1.31x10 ⁴	4.66x10 ⁴	4.93x10 ³	2.89x10 ³
VI VI	51	RHSS-Vert.	NA	70	110	50	351	2028	1.51x10 ⁵	1.51x10 ⁴	8.66x10 ⁴	1.18x10 ⁵	1.12x10 ⁴	2.89x10 ⁴
VI VI	52	RHSS-Hor.	-	-	-	140	-	624				7.1x10 ⁴	5.99x10 ³	4.0x10 ³
VI VI	53	RHSS-Vert.	NA		130				3.33x10 ⁴	3.55x10 ⁴	2.22x10 ³	7.77x10 ⁴	6.66x10 ³	4.66x10 ³
VI VI	108	Concrete Floor	200	140	450	700	1365	1665	1.8x10 ⁶	1.8x10 ⁵	7.99x10 ⁴	4.4x10 ⁵	3.99x10 ⁴	1.71x10 ⁴
VI VI	123	RCPMS-Hor.	NA	NA	150	140	590	241	1.86x10 ⁷	1.84x10 ⁶		1.66x10 ⁵	1.8x10 ⁴	7.77x10 ³
VI VI	124	RCPMS-Hor.	NA	NA	180	60	117	333	3.55x10 ⁶	3.33x10 ⁵	1.38x10 ⁶	2.89x10 ⁵	2.89x10 ⁴	5.77x10 ⁴
VI VI	125	RCMS-Vert.	NA	NA	200	140	78	148	2.44x10 ⁴	3.33x10 ³	2.66x10 ³	2.2x10 ³	1.22x10 ³	7.77x10 ²

C-8

LOW PRESSURE AND HIGH PRESSURE FLUSH - ELEVATION 347'-6"

LP/HIP Area	Location	Surface	Pre-Test Area Gamma (mrem)	Post-Test Area Gamma (mrem)	Pre-Test Contact Gamma (mrem)	Post-Test Contact Gamma (mrem)	Pre-Test Contact Beta (mrem)	Post-Test Contact Beta (mrem)	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
									Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90
VI III	33-1	Concrete Floor	100	70	120	90	1920	296						
VI III	33-2	↓	100	65	100	100	720	666						
VI III	33-3		100	80	140	90	1040	777	4.0x10 ⁶	4.0x10 ⁵	1.62x10 ⁵	4.0x10 ⁵	3.55x10 ⁴	1.04x10 ⁴
VI III	33-4		80	70	140	100	160	555						
VI III	33-5		80	75	80	140	400	74						
VI III	96	Concrete	60	60	50	60	120	185	2.44x10 ⁵	2.22x10 ⁴	2.11x10 ⁴	1.58x10 ⁵	1.60x10 ⁴	5.99x10 ³
VI III	98	Concrete	-	100	-	-	-	-						
VI III	146	Concrete Floor	-	90	-	-	-	-						
VI IV	35-1	Concrete Floor	150	120	260	190	1360	370						
VI IV	35-2	↓	150	120	240	200	3040	5180						
VI IV	35-3		150	130	240	170	2240	1110	4.88x10 ⁶	5.1x10 ⁵	1.58x10 ⁵	1.31x10 ⁵	1.26x10 ⁴	4.66x10 ³
VI IV	35-4		140	120	320	260	1920	888						
VI IV	35-5		140	120	300	250	2800	2775						
VI IV	99	Concrete	-	80	-	-	-	-						
VI IV	102	Diamond Plate	200	145	300	500	8400	1258	3.77x10 ⁶	3.77x10 ⁵	8.21x10 ⁴	1.95x10 ⁵	1.84x10 ⁴	2.66x10 ³
VI IV	103	Diamond Plate	220	180	360	360	5760	777	3.77x10 ⁶	3.55x10 ⁵	1.24x10 ⁵	6.22x10 ⁵	6.44x10 ⁴	9.1x10 ³
VI IV	105	LOCA Duct	NA	310	300	320	11600	No beta	1.35x10 ⁴	6.44x10 ²	LID	6.22x10 ⁴	5.11x10 ³	1.09x10 ³
VI IV	106	LOCA Duct	NA	390	360	700	960	851	4.22x10 ⁵	4.0x10 ⁴	5.11x10 ⁴	9.32x10 ⁴	8.44x10 ³	2.66x10 ³

LOW PRESSURE AND HIGH PRESSURE FLUSH - ELEVATION 347'-6"

C-10

LP/HP Area	Location	Surface	Pre-Test Area Gamma (mrem)	Post-Test Area Gamma (mrem)	Pre-Test Contact Gamma (mrem)	Post-Test Contact Gamma (mrem)	Pre-Test Contact Beta (mrem)	Post-Test Contact Beta (mrem)	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
			Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90						
VI VI	126	RCMS-Vert.	NA	NA	220	170	78	185	8.89x10 ³	8.89x10 ²	3.11x10 ³	4.66x10 ⁴	4.66x10 ³	1.78x10 ³
VI VI	131	RCMS-Hor.	NA	NA	1000	350	35100	1665	3.1x10 ⁶	3.1x10 ⁵	1.49x10 ⁵	9.99x10 ⁵	9.77x10 ⁴	1.35x10 ⁴
VI VI	132	RCMS-Hor.	NA	NA	500	320	7800	7696	1.18x10 ⁶	1.15x10 ⁵	7.77x10 ⁴	5.55x10 ⁵	4.88x10 ⁴	2.22x10 ⁴
VII VII	54-1	Concrete Floor ↓	150	130	500	140	5850	1794						
VII VII	54-2		180	120	190	170	5109	2067						
VII VII	54-3		170	200	350	200	5265	1170	3.77x10 ⁷	3.77x10 ⁶	8.66x10 ⁵	1.82x10 ⁶	1.78x10 ⁵	1.27x10 ⁵
VII VII	54-4		160	150	280	170	3588	1131						
VII VII	54-5		240	145	340	180	4134	1014						
VII VII	56	Liner Wall	NA	70	60	50	78	39	5.33x10 ⁴	5.33x10 ³	1.33x10 ³	3.77x10 ⁴	4.0x10 ³	2.04x10 ³
VII VII	57	Concrete Floor	80	70	100	60	897	624	1.22x10 ⁶	1.22x10 ⁵	4.0x10 ⁴	4.88x10 ⁴	4.88x10 ³	2.2x10 ³
VII VII	135	Stair-Hor.	NA	300	1000	600	35,100	9360	1.71x10 ⁷	1.71x10 ⁵	2.13x10 ⁵	1.24x10 ⁶	1.24x10 ⁵	5.11x10 ⁴
VII VII	136	Stair-Hor.	NA	300	900	600	7410	8580	5.55x10 ⁶	5.55x10 ⁵	2.44x10 ⁵	1.27x10 ⁶	1.18x10 ⁵	4.0x10 ⁴
VII VII	143	Concrete Floor	70	60	140	90	1014	429	4.22x10 ⁶	4.22x10 ⁵	1.46x10 ⁵	1.22x10 ⁵	1.15x10 ⁴	1.15x10 ⁴
VII VII	144	Liner Wall	-	-	-	-	-	-						
VIII VIII	60-1	Concrete Floor ↓	120	50	80	60	585	156						
VIII VIII	60-2		60	50	100	40	2730	507						
VIII VIII	60-3		60	50	80	43	468	301	3.77x10 ⁶	3.77x10 ⁵	1.58x10 ⁵	7.77x10 ⁴	8.21x10 ³	5.33x10 ³
VIII VIII	60-4		60	50	130	60	2613	468						

MECHANICAL SCRUBBER TEST - ELEVATION 347'-6"

LP/ HIP Area	Location	Surface	Pre-Test	Post-Test	Pre-Test	Post-Test	Pre-Test	Post-Test	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²			Chemical Solution
			Area Gamma (mrem)	Area Gamma (mrem)	Contact Gamma (mrem)	Contact Gamma (mrem)	Contact Beta (mrem)	Contact Beta (mrem)	Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90	
AREA	153	Concrete Floor	-	-	110	120	160	64	2.89x10 ⁵	2.89x10 ⁴	1.44x10 ⁴	2.22x10 ³	LLD	LLD	
IHS	156	↓	-	-	50	50	320	224	1.29x10 ⁵	1.31x10 ⁴	7.1x10 ³	3.11x10 ⁴	3.55x10 ³	1.22x10 ³	
	93		38	39	60	60	320	256	1.07x10 ⁵	1.07x10 ⁴	9.1x10 ³	3.33x10 ³	LLD	LLD	
	96		39	40	80	80	256	288	1.42x10 ⁵	1.22x10 ⁴	1.13x10 ⁴	2.66x10 ³	LLD	LLD	1
	157		-	-	60	49	288	227	1.22x10 ⁵	1.11x10 ⁴	8.21x10 ³	2.66x10 ³	LLD	LLD	
	152		60	60	50	46	160	109	1.6x10 ⁵	1.44x10 ⁴	1.44x10 ⁴	1.78x10 ³	LLD	LLD	
AREA	99	Concrete Floor	35	34	34	30	131	96	7.10x10 ⁴	7.10x10 ³	6.44x10 ³	3.11x10 ³	LLD	LLD	
IHS	155	↓	-	-	32	29	154	99	7.77x10 ⁴	7.55x10 ³	8.88x10 ³	2.44x10 ³	LLD	LLD	
	112		-	-	50	44	224	51	5.77x10 ⁵	5.55x10 ⁴	3.11x10 ⁴	4.22x10 ³	LLD	1.33x10 ²	2
	110		31	30	38	34	262	147	3.11x10 ⁵	3.11x10 ⁴	2.02x10 ⁴	3.77x10 ³	LLD	1.55x10 ²	
	154		-	-	60	60	352	256	1.98x10 ⁵	1.93x10 ⁴	1.18x10 ⁴	2.2x10 ³	LLD	2.64x10 ⁴	
	98		36	36	60	60	320	224	2.22x10 ⁵	2.06x10 ⁴	1.35x10 ⁴	3.11x10 ³	LLD	3.55x10 ²	

LOW PRESSURE FLUSH - D-RINGS, REACTOR SERVICE STRUCTURE, MISSILE SHIELDS, REFUELING CANALS, AND BRIDGES

Location	Pre-Test Area Gamma (mrem)	Post-Test Area Gamma (mrem)	Pre-Test Contact Gamma (mrem)	Post-Test Contact Gamma (mrem)	Pre-Test Contact Beta (mrem)	Post-Test Contact Beta (mrem)	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
							Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90
D-Ring												
1	450	300	290	210	5.2 rem	3.1 rem						
2	180	150	250	200	3.4 rem	2.3 rem						
3	180	170	250	250	5.8 rem	2.3 rem						
4	130	100	230	250	4.9 rem	2.3 rem						
5	130	100	280	200	4.5 rem	2.1 rem						
6	140	120	150	250	3.0 rem	975 mrem						
7	180	140	300	215	8.0 rem	1.1 rem						
8	160	130	300	260	4.4 rem	2.9 rem						
9	120	100	320	250	5.9 rem	2.9 rem						
10	120	110	400	175	3.6 rem	2.4 rem						
11	NA	NA	320	250	5.5 rem	3.3 rem	4.44 E4	4.00 E3	3.33 E4	1.38 E6	1.26 E5	6.48 E4
12	140	130	210	290	4.0 rem	3.2 rem	1.18 E7	1.18 E5	4.86 E5	7.33 E5	6.66 E4	1.0 E5
13	150	140	250	225	5.8 rem	4.6 rem	9.99 E6	9.78 E5	6.22 E5	2.44 E6	2.22 E5	4.84 E5
14	NA	NA	270	200	3.7 rem	1.2 rem	3.55 E6	3.55 E5	8.21 E5	4.88 E5	4.22 E4	5.11 E4
15	NA	NA	160	100	3.4 rem	1.2 rem				5.33 E5	5.11 E4	1.64 E3
16	NA	NA	350	250	5.0 rem	2.0 rem				2.66 E6	2.44 E5	1.06 E5
17	150	100	330	150	6.9 rem	1.4 rem	9.32 E6	9.24 E5	3.55 E5	2.89 E6	2.66 E5	4.08 E5
18	NA	NA	320	350	6.3 rem	3.5 rem	1.33 E5	1.35 E5	1.38 E5	1.24 E6	1.11 E5	5.24 E4
19	NA	NA	190	110	4.4 rem	3.9 rem				3.77 E5	3.77 E4	3.46 E4
20	180	120	500	250	9.8 rem	4.9 rem	8.21 E6	7.99 E5	2.13 E5	8.88 E6	8.21 E5	2.14 E5
21	NA	NA	230	175	3.0 rem	2.2 rem				9.10 E5	8.58 E4	1.97 E4
22	220	190	200	275	4.0 rem	2.8 rem			8.2 E5	1.38 E6	1.31 E5	4.26 E4
23	110	90	260	175	6.2 rem	3.6 rem				7.10 E5	6.82 E4	2.02 E4
24	NA	NA	130	125	480 mrem	683 mrem	1.35 E7	1.35 E5	1.02 E6	7.10 E5	6.44 E4	1.32 E4
25	140	120	250	190	7.4 rem	5.1 rem			2.02 E6	4.44 E5	4.22 E4	1.10 E5
26	NA	NA	190	175	840 mrem	1.3 rem				1.82 E6	1.69 E5	7.86 E4

LOW PRESSURE FLUSH - D-RINGS, REACTOR SERVICE STRUCTURE, MISSILE SHIELDS, REFUELING CANALS, AND BRIDGES

Location	Pre-Test Area Gamma (mrem)	Post-Test Area Gamma (mrem)	Pre-Test Contact Gamma (mrem)	Post-Test Contact Gamma (mrem)	Pre-Test Contact Beta (mrem)	Post-Test Contact Beta (mrem)	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
							Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90
Refueling Canal												
65	210	110	360	180	7.4 rem	3.9 rem			9.77 E5	3.55 E7	3.55 E6	3.55 E6
66	NA	NA	60	42	80 mrem	68 mrem			2.89 E3	1.09 E5	1.24 E4	4.88 E3
67	NA	NA	60	44	80 mrem	35 mrem	1.64 E4	1.58 E3	LLD	5.11 E4	4.22 E3	1.02 E3
68	340	120	600	200	10.4 rem	3.8 rem	2.44 E7	2.44 E6	1.49 E6			
69	NA	NA	460	380	560 mrem	Neg.	2.13 E5	2.15 E4	4.88 E3	8.66 E4	8.88 E3	5.77 E3
70	NA	NA	600	460	Neg.	96 mrem	2.44 E5	2.44 E4	7.10 E3	3.62 E5	3.80 E4	1.69 E4
71	NA	NA	100	90	80 mrem	32 mrem	3.55 E4	3.55 E3	2.66 E3	2.44 E4	2.42 E3	1.46 E3
72	140	80	300	60	6.0 rem	832 mrem	1.13 E7	1.09 E6	5.99 E5	5.33 E6	5.11 E5	4.84 E5
73	100	80	220	60	5.5 rem	704 mrem	1.75 E7	1.73 E6	1.62 E6	2.89 E6	2.89 E5	5.11 E5
74	NA	NA	110	90	80 mrem	32 mrem	6.66 E4	6.22 E3	4.44 E3	3.55 E4	4.00 E3	7.10 E3
75	NA	NA	600	410	Neg.	32 mrem	9.10 E4	8.66 E3	5.99 E3	6.44 E4	7.55 E3	5.33 E3
76	NA	NA	650	600	600 mrem	Neg.	4.22 E5	4.00 E4	1.95 E4	3.77 E5	4.00 E4	4.44 E4
Fuel Handling Bridge												
78	190	110	220	180	62 rem	4.5 rem	1.4x10 ⁶	1.4x10 ⁵	1.64x10 ⁵	1.04 E6	9.55 E4	1.29 E3
79	NA	NA	180	130	245 mrem	96 mrem	6.44 E4	6.44 E3	3.33 E3	1.75 E5	1.66 E4	9.46 E3
80	NA	NA	140	100	140 mrem	32 mrem	4.66 E4	4.66 E3	4.00 E3	9.32 E4	3.55 E3	5.31 E3
81	180	100	230	175	7.9 rem	4.2 rem	355 E6	3.77 E5	2.66 E5	2.22 E6	2.18 E5	2.24 E5
82	NA	NA	160	140	245 mrem	160 mrem	6.66 E4	7.10 E3	6.66 E3	9.32 E4	9.10 E3	4.79 E3
83	160	140	250	220	8.6 rem	7.3 rem	3.33 E6	3.11 E5	1.69 E5	5.55 E6	5.11 E5	7.57 E4
84	NA	NA	120	105	70 mrem	48 mrem				7.77 E4	6.66 E3	8.06 E3
85	250	180	230	210	3.7 rem	2.4 rem	7.99 E5	7.99 E4	7.33 E4	LLD	LLD	LLD

LOW PRESSURE FLUSH - D-RINGS, REACTOR SERVICE STRUCTURE, MISSILE SHIELDS, REFUELING CANALS, AND BRIDGES

Location	Pre-Test Area Gamma (mrem)	Post-Test Area Gamma (mrem)	Pre-Test Contact Gamma (mrem)	Post-Test Contact Gamma (mrem)	Pre-Test Contact Beta (mrem)	Post-Test Contact Beta (mrem)	Pre-Test Swipe - dpm/100 cm ²			Post-Test Swipe - dpm/100 cm ²		
							Cs-137	Cs-134	Sr-90/Y-90	Cs-137	Cs-134	Sr-90/Y-90
Refueling Canal Deep End												
117	NA	NA	40	18	140 mrem	32 mrem	4.66 E4	4.88 E3		3.11 E4	3.33 E3	2.53 E3
118	NA	NA	35	19	158 mrem	131 mrem	8.66 E4	8.21 E3	4.00 E3	2.89 E5	2.66 E4	1.13 E4
119	50	28	200	60	4.6 rem	448 mrem	3.77 E6	3.77 E5	2.89 E5	6.44 E6	6.94 E5	6.44 E5
120	80	18	150	60	3.7 rem	1.7 rem	2.89 E7	2.89 E6	1.18 E6	2.06 E7	2.04 E6	2.78 E7
121	NA	NA	120	22	105 mrem	250 mrem	8.66 E4	8.44 E3	2.69 E3	2.89 E5	2.89 E4	2.26 E4
122	NA	NA	60	34	595 mrem	602 mrem	7.10 E6	6.88 E5	2.22 E5	1.20 E7	1.22 E6	5.39 E5

LOW PRESSURE FLUSH - POLAR CRANE
ENTRIES 43 AND 45

Location	Surface	Pre-Test	Post-Test	Pre-Test	Post-Test	Pre-Test	Post-Test	dpm/100 cm ²						Area Gamma *
		Area Gamma (mrem)	Area Gamma (mrem)	Contact Gamma (mrem)	Contact Gamma (mrem)	Contact Beta (mrem)	Contact Beta (mrem)	Pre-Test Cs-137	Post-Test Cs-137	Pre-Test Cs-134	Post-Test Cs-134	Pre-Test Sr-90/Y-90	Post-Test Sr-90/Y-90	
1	Walkway	118		300	20	3230	228	2.89x10 ⁴	2.4x10 ⁶	2.0x10 ³	2.2x10 ⁵	1.2x10 ³	1.1x10 ⁵	150 mrem
2	Walkway		100	275		5415		5.6x10 ⁶		5.6x10 ⁵		3.3x10 ⁵		160 mrem
3	Walkway		100	300		6460		6.9x10 ⁴		8.2x10 ³		2.9x10 ³		160 mrem
4	Dr. Mech-Top	50		120	100	1824	380		1.6x10 ⁶		1.6x10 ⁵		7.8x10 ⁵	
5	Dr. Mech-Top			250		6650		9.8x10 ⁴		9.1x10 ³		4.2x10 ³		
6	Girder A-H		100	90	120	5358	3724	1.1x10 ⁷	1.5x10 ⁷	1.1x10 ⁶	1.5x10 ⁶	4.7x10 ⁵	7.8x10 ⁵	
7	Girder A-H			80		7296		1.2x10 ⁵		1.1x10 ⁴		4.4x10 ³		
8	Cross Beam	85		33	45	236	133		4.4x10 ⁴		3.7x10 ³		2.7x10 ³	165 mrem
8 ^{1/2}	Cross Beam	50												
9 ^{1/2}	Cross Beam	40												
9	Cross Beam	90		250		6650		4.0x10 ⁴		4.4x10 ³		1.4x10 ³		170 mrem
10	Platform	100		190	200	4978	3040	9.3x10 ⁶	8.2x10 ⁶	9.3x10 ⁵	8.0x10 ⁵	8.2x10 ⁵	4.9x10 ⁵	155 mrem
11	Tool Box			180	80	6916	152					2.1x10 ⁵		
12	Crane Rail	120		120	120	304	5244		2.2x10 ⁵		2.2x10 ⁴	1.6x10 ⁵	2.9x10 ⁴	
13	Crane Rail			120	115	4104	4123		6.4x10 ⁶		6.4x10 ⁵	1.2x10 ⁶	3.8x10 ⁵	
14	Cab Floor	80		30		646						2.1x10 ⁵		140 mrem
15	Girder-V			80		114			2.1x10 ⁵		1.9x10 ⁴	1.7x10 ⁴	4.2x10 ³	145 mrem
16	Girder-V			75		57						1.9x10 ⁵		
17	Girder A-V			80		2546		9.1x10 ⁴		9.3x10 ³		1.5x10 ³		
18	Girder B-V			180	200	5776	5320		1.2x10 ⁶		1.1x10 ⁵	2.0x10 ⁵	3.0x10 ⁴	
19	LOCA Duct											1.6x10 ⁴		
20	LOCA Duct													
21	Inside-Girder A				75		171		6.4x10 ⁵		6.2x10 ⁴	6.9x10 ⁴	3.3x10 ⁴	
22	Trolley-V													
23	Trolley-V											6.0x10 ⁴		
24	Trolley-H	100		150	200	3990	3040		1.2x10 ⁷		1.2x10 ⁶	1.8x10 ⁴	6.4x10 ⁵	
25	Trolley-H			180	380	6916	4256		7.5x10 ⁶		7.3x10 ⁵		2.4x10 ⁵	
26	Cab Floor			450		5890		1.7x10 ⁵		1.6x10 ⁴		8.9x10 ³		

LOW PRESSURE FLUSH - POLAR CRANE
ENTRIES 43 AND 45

Location	Surface	Pre-Test Area	Post-Test Area	Pre-Test Contact	Post-Test Contact	Pre-Test Contact	Post-Test Contact	dpm/100 cm ²						Area Gamma *
		Gamma (mrem)	Gamma (mrem)	Gamma (mrem)	Gamma (mrem)	Beta (mrem)	Beta (mrem)	Pre-Test Cs-137	Post-Test Cs-137	Pre-Test Cs-134	Post-Test Cs-134	Pre-Test Sr-90/Y-90	Post-Test Sr-90/Y-90	
27	Cab-Vert.			200		380		3.6x10 ⁵		3.8x10 ³		1.7x10 ⁴		
28	Cab-Vert.			150		190		1.2x10 ⁵		1.1x10 ³		6.4x10 ³		
29	Inside Girder-A			100	60	NDB	209	3.1x10 ⁵	1.2x10 ⁵	2.9x10 ³	1.3x10 ⁴	1.8x10 ⁴	5.6x10 ³	
30	Liner Wall	60		60	70	209	266	5.8x10 ⁵	2.4x10 ⁵	5.6x10 ³	2.7x10 ⁴	4.0x10 ⁴	1.4x10 ⁴	
31	Liner Wall	50		20	55	38	57		9.8x10 ⁴		9.1x10 ³		3.1x10 ³	
32	Dome				50		76	9.3x10 ⁴	6.9x10 ⁴	8.2x10 ³	6.9x10 ⁴	3.6x10 ³	2.4x10 ³	
33	Dome				50		114	1.1x10 ⁵	6.2x10 ⁴	1.1x10 ³	6.2x10 ³	3.6x10 ³	1.5x10 ³	
34	Liner Wall			50		95								
35	Liner Wall			130		1026		1.4x10 ⁶		1.4x10 ⁵		2.7x10 ⁴		
36	Dome							2.7x10 ⁴		2.7x10 ³		1.8x10 ³		
37	Dome													
38	Platform Floor			35	200	50	3040		1.7x10 ⁶		1.7x10 ⁵		5.8x10 ⁴	
39	Girder B-Vert.			110	200	4142	3040	6.2x10 ⁶	3.6x10 ⁶	6.2x10 ⁵	3.6x10 ⁵	2.7x10 ⁵	1.1x10 ⁵	
40	Rail Top			200		190		2.9x10 ⁶		2.9x10 ⁵		1.4x10 ⁵		
41	Rail Top		150	180		8436		4.7x10 ⁵		4.7x10 ⁴		5.1x10 ⁴		

*Readings taken May 11, 1982

**25 @ 10'
60 @ 3' post-test area gamma (teletector instrument)

H = horizontal, V = vertical

REACTOR BUILDING AIR SAMPLE DATA
February 26, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					H-3	$\mu\text{Ci/ml}$	BZA In $\mu\text{Ci/cc}$				
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90		H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
2/26/82															
10:00															
	10:46	12:30	HP survey	1.36×10^{-11}	2.37×10^{-9}	1.6×10^{-9}	1.4×10^{-10}	2.45×10^{-10}	4.5×10^{-8}		$< 1.19 \times 10^{-12}$	1.15×10^{-7}	1.2×10^{-7}	1.1×10^{-8}	1.8×10^{-9}
11:00	11:00	12:00	Polar crane Protection								$< 2.57 \times 10^{-12}$	2.28×10^{-7}	1.2×10^{-6}	1.1×10^{-7}	1.1×10^{-8}
			Installation of 110 V extension								$< 2.37 \times 10^{-12}$	5.57×10^{-8}	1.7×10^{-7}	1.5×10^{-8}	2.6×10^{-9}
	11:30	16:00	Pre-decon test data acquisition								1.5×10^{-12}	8.47×10^{-8}	2.1×10^{-7}	1.9×10^{-8}	2.5×10^{-9}
											1.92×10^{-12}	1.41×10^{-7}	3.2×10^{-7}	2.8×10^{-8}	3.7×10^{-9}
											$< 9.08 \times 10^{-13}$	4.15×10^{-8}	2.3×10^{-7}	9.9×10^{-9}	9.7×10^{-10}
12:00											$< 8.82 \times 10^{-13}$	3.62×10^{-8}	6.3×10^{-8}	5.6×10^{-9}	1.2×10^{-9}
	12:30	14:00	Protect CCTV								4.0×10^{-12}	3.03×10^{-7}	4.4×10^{-7}	3.9×10^{-8}	4.0×10^{-9}
			Relocate CCTV								$< 1.62 \times 10^{-12}$	1.68×10^{-7}	2.3×10^{-7}	2.0×10^{-8}	2.8×10^{-9}
											$< 1.62 \times 10^{-12}$	3.11×10^{-7}	4.5×10^{-7}	4.1×10^{-8}	3.6×10^{-9}

REACTOR BUILDING AIR SAMPLE DATA
February 26, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					$\mu\text{Ci/ml}$	BZA in $\mu\text{Ci/cc}$					
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
13:00			Install additional lighting at refueling canal								$<1.5 \times 10^{-12}$	5.14×10^{-8}	1.1×10^{-7}	9.4×10^{-9}	1.6×10^{-9}
14:00											2.01×10^{-12}	5.61×10^{-8}	1.1×10^{-7}	1.0×10^{-8}	3.0×10^{-9}
										7.0×10^{-5}	$<1.21 \times 10^{-12}$	1.29×10^{-8}	2.4×10^{-8}	2.0×10^{-9}	6.6×10^{-10}
											1.78×10^{-12}	2.08×10^{-8}	3.9×10^{-8}	3.7×10^{-9}	7.0×10^{-10}
15:00											$<5.3 \times 10^{-14}$	1.75×10^{-8}	2.3×10^{-8}	2.3×10^{-9}	6.3×10^{-10}
											1.34×10^{-12}	1.91×10^{-8}	3.5×10^{-8}	2.9×10^{-9}	1.0×10^{-9}
										1.4×10^{-5}	$<1.84 \times 10^{-12}$	1.87×10^{-7}	3.1×10^{-7}	2.8×10^{-8}	3.0×10^{-9}
16:00										2.7×10^{-5}	3.23×10^{-12}	2.35×10^{-7}	3.2×10^{-7}	2.8×10^{-8}	7.1×10^{-9}
											3.11×10^{-12}	8.7×10^{-8}	1.2×10^{-7}	1.1×10^{-8}	2.6×10^{-9}
											$<2.3 \times 10^{-12}$	2.7×10^{-8}	4.2×10^{-8}	3.9×10^{-9}	9.8×10^{-10}
17:00															

REACTOR BUILDING AIR SAMPLE DATA
March 3, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					H-3	$\mu\text{Ci/ml}$	BZA in $\mu\text{Ci/cc}$				
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90		H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
3/3/82															
09:00	09:17	10:00	HP survey	$<1.75 \times 10^{-13}$	6.63×10^{-9}										
	10:00														
	11:00														
	12:00														
	13:00														
	14:00														
	15:00														
	16:00														

REACTOR BUILDING AIR SAMPLE DATA
March 4, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					$\mu\text{Ci/ml}$		BZA in $\mu\text{Ci/cc}$				
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	iCs-137	Cs-134	Sr-90/Y-90
3/4/82															
09:00	09:14	09:29		(72 hr) $<3.6 \times 10^{-15}$						1.8×10^{-7}					
											6.6×10^{-5}				
10:00	10:15	11:16	LP-El. 305'	$<9.6 \times 10^{-12}$	1.2×10^{-7}	1.5×10^{-7}	1.2×10^{-8}	3.6×10^{-9}	9.3×10^{-7}						
	10:19	11:16	11:00 Mist						$<7.6 \times 10^{-9}$						
11:00	11:16	12:04	11:06							1.4×10^{-4}					
	11:16	12:04	Flushing and Misting	$<1.2 \times 10^{-11}$	1.8×10^{-7}	2.2×10^{-7}	1.9×10^{-8}	9.2×10^{-9}	2.9×10^{-6}	7.7×10^{-5}					
	11:27	12:04							2.5×10^{-7}	1.2×10^{-4}					
12:00	12:04	12:37							$<1.2 \times 10^{-8}$						
	12:37	13:10			$<1.8 \times 10^{-11}$	4.2×10^{-8}	4.4×10^{-8}	3.9×10^{-7}	$<2.5 \times 10^{-9}$	4.7×10^{-6}	1.7×10^{-4}				
										1.4×10^{-4}					
13:00	13:10	14:11	13:08	2.4×10^{-11}	1.5×10^{-7}	1.9×10^{-7}	1.7×10^{-8}	5.4×10^{-9}	2.1×10^{-6}	6.8×10^{-5}					
			El. 305' Flush	(72 hr) $<1.3 \times 10^{-11}$											
14:00		14:09								1.1×10^{-4}	(72 hr.)				
										7.7×10^{-5}	$<3.0 \times 10^{-12}$				
										9.0×10^{-5}	(72 hr.)				
											$<2.95 \times 10^{-12}$				

REACTOR BUILDING AIR SAMPLE DATA
March 4, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					$\mu\text{Ci/ml}$		BZA in $\mu\text{Ci/cc}$				
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
15:00	14:52	15:32	El. 305' data acquisition							4.6×10^{-5} 5.6×10^{-5}					
16:00	16:32	17:04	Polar crane misting	$<1.9 \times 10^{-11}$	3.6×10^{-7}	4.8×10^{-7}	4.9×10^{-8}	$<2.6 \times 10^{-9}$		1.5×10^{-4}	(72 hr.) $<1.87 \times 10^{-12}$				
17:00	17:04	22:40	↓						2.1×10^{-6}	1.4×10^{-4}	(72 hr.) $<1.87 \times 10^{-12}$				
	17:07	17:30		$<2.5 \times 10^{-11}$	5.0×10^{-7}	6.1×10^{-7}	5.2×10^{-8}	4.7×10^{-9}		1.8×10^{-4}					
	17:30	22:40							3.0×10^{-7}	1.2×10^{-4}					
18:00															

REACTOR BUILDING AIR SAMPLE DATA
March 5, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$						$\mu\text{Ci/ml}$	HZA in $\mu\text{Ci/cc}$				
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	4-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
3/5/82															
09:00	09:20	09:35	HTO and high volume sample												
10:00															
11:00	11:06	12:06	Polar crane flush												
				$<1.39 \times 10^{-11}$	3.92×10^{-7}	5.9×10^{-7}	5.0×10^{-8}	1.9×10^{-8}			6.2×10^{-7}	9.1×10^{-7}			

Entry aborted - high pressure spray pump leak - no flushing accomplished

REACTOR BUILDING AIR SAMPLE DATA
March 8, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					$\mu\text{Ci/ml}$	BZA in $\mu\text{Ci/cc}$					
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
3/8/82															
09:00	09:29	09:44	High volume and HTO samples						2.1×10^{-7}	7.4×10^{-5}	$< 1.97 \times 10^{-12}$	7.4×10^{-8}	1.1×10^{-7}	1.2×10^{-8}	4.2×10^{-9}
10:00	10:15	10:32	Collect 2 HTO's								$< 9.0 \times 10^{-12}$	2.0×10^{-8}	2.6×10^{-8}	2.7×10^{-9}	$< 7.2 \times 10^{-10}$
			Polar crane flush								$< 1.12 \times 10^{-12}$	6.3×10^{-8}	6.6×10^{-8}	5.7×10^{-9}	1.6×10^{-8}
	10:39	12:19									$< 1.14 \times 10^{-12}$	1.0×10^{-7}	1.4×10^{-7}	1.4×10^{-8}	9.6×10^{-9}
											$< 1.1 \times 10^{-12}$	6.13×10^{-8}	8.0×10^{-8}	8.6×10^{-9}	7.5×10^{-9}
11:00															
12:00															
13:00															
14:00															
15:00	15:22	16:33	HTO samples						3.0×10^{-6}						
	15:42	16:41	Flush B D-ring, Missile shields							3.2×10^{-4}	$< 2.46 \times 10^{-12}$	1.2×10^{-7}	2.0×10^{-7}	2.1×10^{-8}	1.9×10^{-8}
										1.6×10^{-4}	$< 1.6 \times 10^{-12}$	3.2×10^{-8}	4.0×10^{-8}	3.5×10^{-9}	4.1×10^{-8}
										1.7×10^{-4}	$< 1.69 \times 10^{-12}$	9.2×10^{-8}	1.2×10^{-7}	1.1×10^{-8}	1.2×10^{-8}
16:00															
17:00															
18:00															

FEACTOR BUILDING AIR SAMPLE DATA
March 10, 1982

Date	Time	Time	Activity	μCi/cc					μCi/ml	BZA in μCi/cc					
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90+Y-90
3/10/82															
08:00	08:44	08:59	Prelim. (HP) sampling						3.7x10 ⁻⁷	9.2x10 ⁻⁵	2.05x10 ⁻¹²	2.1x10 ⁻⁸	2.4x10 ⁻⁸	2.1x10 ⁻⁹	2.2x10 ⁻⁹
09:00										1.7x10 ⁻⁴ 1.9x10 ⁻⁴	6.45x10 ⁻¹² <1.46x10 ⁻¹²	2.05x10 ⁻⁸ 5.1x10 ⁻⁹	2.6x10 ⁻⁸ 6.0x10 ⁻⁹	2.2x10 ⁻⁹ 4.8x10 ⁻¹⁰	1.6x10 ⁻⁹ 5.9x10 ⁻¹⁰
10:00	09:55	10:24	Flush B D-ring	3.64x10 ⁻¹¹	8.1x10 ⁻⁸	7.6x10 ⁻⁸	8.6x10 ⁻⁹	<7.17x10 ⁻⁹	2.0x10 ⁻⁶	2.0x10 ⁻⁴ 6.4x10 ⁻⁵	<8.9x10 ⁻¹³ <1.38x10 ⁻¹²	6.5x10 ⁻⁸ 7.4x10 ⁻⁸	8.6x10 ⁻⁸ 9.1x10 ⁻⁸	7.4x10 ⁻⁹ 7.5x10 ⁻⁹	7.1x10 ⁻⁹ 8.4x10 ⁻⁹
	10:24	10:50	Flush A D-ring	<2.45x10 ⁻¹¹	2.06x10 ⁻⁷	2.9x10 ⁻⁷	2.8x10 ⁻⁸	<8.27x10 ⁻⁹	2.8x10 ⁻⁶	3.3x10 ⁻⁵					
11:00	10:50	11:21	Missile shields	2.73x10 ⁻¹¹	6.23x10 ⁻⁸	5.9x10 ⁻⁸	4.5x10 ⁻⁹	<7.17x10 ⁻⁹	4.7x10 ⁻⁶						
12:00	11:46	12:06		<3.18x10 ⁻¹¹	2.41x10 ⁻⁸	2.6x10 ⁻⁸	2.2x10 ⁻⁹	<1.08x10 ⁻⁸	3.9x10 ⁻⁶	1.7x10 ⁻⁴	<1.13x10 ⁻¹²	2.3x10 ⁻⁸	2.5x10 ⁻⁸	2.0x10 ⁻⁹	2.9x10 ⁻⁹
	12:06	12:39		<1.87x10 ⁻¹¹	3.54x10 ⁻⁸	3.6x10 ⁻⁸	3.0x10 ⁻⁹	<6.33x10 ⁻⁹	5.7x10 ⁻⁶	6.2x10 ⁻⁴ 2.5x10 ⁻⁴	2.04x10 ⁻¹² <1.15x10 ⁻¹²	3.91x10 ⁻⁸ 3.93x10 ⁻⁸	4.7x10 ⁻⁸ 4.8x10 ⁻⁸	4.1x10 ⁻⁹ 4.3x10 ⁻⁹	3.2x10 ⁻⁹ 2.2x10 ⁻⁹
13:00	12:39	13:45		1.45x10 ⁻¹¹	2.45x10 ⁻⁸	2.0x10 ⁻⁸	1.5x10 ⁻⁹	<3.26x10 ⁻⁹	5.9x10 ⁻⁶						
14:00	13:45	14:13	LP 347' -6"	<2.27x10 ⁻¹¹	1.07x10 ⁻⁷	1.2x10 ⁻⁷	8.7x10 ⁻⁹	7.7x10 ⁻⁹	3.3x10 ⁻⁶	5.1x10 ⁻⁴	<1.54x10 ⁻¹²	1.55x10 ⁻⁸	1.7x10 ⁻⁸	1.4x10 ⁻⁹	1.6x10 ⁻⁹
	14:13	14:54	Flush	<1.55x10 ⁻¹¹	3.65x10 ⁻⁸	4.1x10 ⁻⁸	3.0x10 ⁻⁹	<2.0x10 ⁻⁹	3.5x10 ⁻⁶	1.9x10 ⁻⁴	<1.74x10 ⁻¹²	2.71x10 ⁻⁸	3.4x10 ⁻⁸	2.9x10 ⁻⁹	1.1x10 ⁻⁹
15:00			Deep end canals							1.8x10 ⁻⁴	<1.51x10 ⁻¹²	1.43x10 ⁻⁸	1.7x10 ⁻⁸	1.6x10 ⁻⁹	7.4x10 ⁻¹⁰

C-24

REACTOR BUILDING AIR SAMPLE DATA
March 11, 1982

Date	Time	Time	Activity	μCi/cc						μCi/ml	BZA in μCi/cc					
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90	
3/11/82																
09:00		09:23	09:38	HP survey						5.4x10 ⁻⁷	1.6x10 ⁻⁴					
10:00		10:05	10:58	Data acquisition							5.1x10 ⁻⁴					
		10:21	11:24	Refueling canals, D-rings							3.5x10 ⁻⁵	2.9x10 ⁻¹²	7.19x10 ⁻⁹	8.7x10 ⁻⁹	8.7x10 ⁻¹⁰	1.6x10 ⁻⁹
11:00																
12:00																
13:00	12:53	14:19	Flushing equipment on El. 347' -6"							2.3x10 ⁻⁴	2.9x10 ⁻¹²	7.5x10 ⁻⁹	8.8x10 ⁻⁹	8.9x10 ⁻¹⁰	6.7x10 ⁻¹⁰	
	13:04	13:59		2.38x10 ⁻¹¹	1.24x10 ⁻⁸	1.8x10 ⁻⁸	1.7x10 ⁻⁹	<4.5x10 ⁻⁹	8.2x10 ⁻⁷	3.2x10 ⁻⁵						
14:00	13:59	14:13		<4.28x10 ⁻¹¹	1.26x10 ⁻⁸	3.3x10 ⁻⁸	1.5x10 ⁻⁹	<1.75x10 ⁻⁸	5.9x10 ⁻⁷		2.1x10 ⁻¹²	3.5x10 ⁻⁸	4.5x10 ⁻⁸	4.4x10 ⁻⁹	2.4x10 ⁻⁹	
											<1.2x10 ⁻¹²	6.8x10 ⁻⁸	6.1x10 ⁻⁸	5.4x10 ⁻⁹	1.2x10 ⁻⁹	
15:00												2.15x10 ⁻¹²	2.93x10 ⁻⁸	3.4x10 ⁻⁸	2.9x10 ⁻⁹	8.8x10 ⁻¹⁰
	15:18	16:09									3.1x10 ⁻⁴	<2.3x10 ⁻¹²	8.8x10 ⁻⁹	1.2x10 ⁻⁸	8.6x10 ⁻¹⁰	7.3x10 ⁻¹⁰
16:00	15:49	16:15									3.6x10 ⁻⁵	<2.1x10 ⁻¹²	3.4x10 ⁻⁸	4.1x10 ⁻⁸	3.4x10 ⁻⁹	2.7x10 ⁻⁹
				<2.48x10 ⁻¹¹	2.9x10 ⁻⁸	3.7x10 ⁻⁸	3.9x10 ⁻⁹	4.4x10 ⁻⁹	6.1x10 ⁻⁷	8.9x10 ⁻⁴	3.2x10 ⁻¹²	2.2x10 ⁻⁸	2.4x10 ⁻⁸	2.2x10 ⁻⁹	1.5x10 ⁻⁹	
17:00																
18:00																

C-25

REACTOR BUILDING AIR SAMPLE DATA
March 12, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$						$\mu\text{Ci/ml}$	BZA in $\mu\text{Ci/cc}$				
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
3/12/82															
09:00	09:04	09:19	HP samples						3.9×10^{-7}						
10:00	10:02	10:39	Flush 347' -6" HP spin jet and lance ↓ Stair-well						9.1×10^{-7}		$<8.36 \times 10^{-13}$	1.49×10^{-8}	2.0×10^{-8}	1.9×10^{-9}	$<1.4 \times 10^{-10}$
11:00	10:39	11:10							1.0×10^{-7}		1.78×10^{-12}	1.38×10^{-8}	1.9×10^{-8}	1.4×10^{-9}	8.3×10^{-10}
											2.5×10^{-12}	9.8×10^{-9}	7.0×10^{-9}	6.5×10^{-10}	7.8×10^{-10}
	11:10	12:13			$<9.6 \times 10^{-12}$	9.1×10^{-9}	6.6×10^{-9}	4.9×10^{-10}	$<1.1 \times 10^{-9}$	1.5×10^{-6}		$<1.47 \times 10^{-12}$	1.49×10^{-8}	1.8×10^{-8}	1.4×10^{-9}
12:00	12:13	12:40		$<2.4 \times 10^{-11}$	1.7×10^{-8}	1.6×10^{-8}	1.1×10^{-9}	$<2.6 \times 10^{-9}$	1.5×10^{-6}		$<1.0 \times 10^{-12}$	9.0×10^{-9}	9.6×10^{-9}	8.6×10^{-10}	1.7×10^{-12}
13:00	12:40	13:03		$<2.8 \times 10^{-11}$	2.2×10^{-8}	1.98×10^{-8}	1.6×10^{-9}	$<3.1 \times 10^{-9}$	2.4×10^{-6}						
	13:03	13:42							1.9×10^{-6}		$<1.82 \times 10^{-12}$	9.99×10^{-9}	1.5×10^{-8}	1.4×10^{-9}	8.0×10^{-10}
14:00	13:42	14:27		$<1.3 \times 10^{-11}$	3.4×10^{-7}	4.5×10^{-7}	3.6×10^{-8}	7.2×10^{-9}	3.7×10^{-6}		$<1.9 \times 10^{-12}$	1.5×10^{-8}	1.8×10^{-8}	1.5×10^{-9}	1.3×10^{-9}
15:00	15:11	15:50		$<1.6 \times 10^{-11}$	3.3×10^{-8}	4.4×10^{-8}	3.9×10^{-9}	$<1.8 \times 10^{-9}$	1.6×10^{-6}	1.9×10^{-4}	2.84×10^{-12}	1.38×10^{-8}	1.5×10^{-8}	1.3×10^{-9}	9.7×10^{-10}
16:00	15:50	16:26		$<1.7 \times 10^{-11}$	2.4×10^{-8}	3.3×10^{-8}	3.3×10^{-9}	$<1.9 \times 10^{-9}$	3.0×10^{-6}		$<2.2 \times 10^{-12}$	3.5×10^{-8}	4.6×10^{-8}	4.5×10^{-9}	2.5×10^{-9}
											$<1.5 \times 10^{-12}$	3.2×10^{-8}	4.2×10^{-8}	3.9×10^{-9}	1.8×10^{-9}
17:00															
18:00															

C-26

REACTOR BUILDING AIR SAMPLE DATA
March 15, 1982

Date	Time	Time	Activity	μCi/cc					μCi/ml	BZA in μCi/cc					
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90, Y-90
3/15/82															
09:00															
	09:26	09:41	HP samples and data acquisition						8.0x10 ⁻⁷						
10:00	09:58	11:00	El. 347'-6"								<1.71x10 ⁻¹²	9.57x10 ⁻⁹	1.5x10 ⁻⁸	1.07x10 ⁻⁸	4.04x10 ⁻¹⁰
			↓								<1.71x10 ⁻¹²	6.74x10 ⁻⁹	8.98x10 ⁻⁹	7.44x10 ⁻¹⁰	3.58x10 ⁻¹⁰
11:00	11:14	12:44	Staging task								<1.2x10 ⁻¹²	2.8x10 ⁻⁸	3.3x10 ⁻⁸	3.0x10 ⁻⁹	4.3x10 ⁻⁹
	11:37	12:44	↓								2.7x10 ⁻¹²	1.69x10 ⁻⁷	2.3x10 ⁻⁷	1.9x10 ⁻⁸	1.7x10 ⁻⁸
			Started flush								<1.5x10 ⁻¹²	1.05x10 ⁻⁷	1.3x10 ⁻⁷	1.1x10 ⁻⁸	8.3x10 ⁻⁹
12:00															
	12:37	14:00									<1.4x10 ⁻¹²	7.95x10 ⁻⁹	1.1x10 ⁻⁸	1.1x10 ⁻⁹	9.4x10 ⁻¹⁰
13:00															
14:00	13:58	14:30	LP El. 305'	<6.4x10 ⁻⁸	4.3x10 ⁻⁷	6.2x10 ⁻⁷	5.3x10 ⁻⁸	4.4x10 ⁻⁹	4.9x10 ⁻⁶		<1.5x10 ⁻¹²	9.67x10 ⁻⁹	1.1x10 ⁻⁸	1.1x10 ⁻⁹	6.2x10 ⁻¹⁰
	14:30	14:58	Overheads,	<2.2x10 ⁻¹¹	5.6x10 ⁻⁶	1.1x10 ⁻⁵	9.4x10 ⁻⁷	6.6x10 ⁻⁸	5.2x10 ⁻⁶						
15:00	14:58	15:16	verticals, and floor	<3.4x10 ⁻¹¹	2.9x10 ⁻⁷	3.1x10 ⁻⁷	3.3x10 ⁻⁸	2.9x10 ⁻⁹	1.9x10 ⁻⁶						
16:00	16:03	16:47		<1.4x10 ⁻¹¹	1.0x10 ⁻⁷	1.1x10 ⁻⁷	1.0x10 ⁻⁸	4.4x10 ⁻⁹	6.3x10 ⁻⁶						
17:00															
18:00															

REACTOR BUILDING AIR SAMPLE DATA
March 17, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					$\mu\text{Ci/ml}$	BZA in $\mu\text{Ci/cc}$					
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
3/17/82															
09:00	09:10	09:25							1.4×10^{-6}						
10:00											$<1.7 \times 10^{-14}$	6.43×10^{-8}	6.7×10^{-8}	5.7×10^{-9}	2.9×10^{-9}
											$<1.6 \times 10^{-12}$	5.26×10^{-8}	5.5×10^{-8}	4.8×10^{-9}	2.1×10^{-9}
	10:46	11:29	LP flush open stair- well (10:45)	$<1.4 \times 10^{-11}$	-	2.0×10^{-8}	1.4×10^{-9}	2.23×10^{-9}	2.1×10^{-6}		7.0×10^{-12}	5.7×10^{-8}	2.0×10^{-9}	1.8×10^{-10}	3.35×10^{-9}
11:00															
	11:38	12:07	HP flush open stair- well (11:15)	$<2.06 \times 10^{-11}$	1.43×10^{-7}	2.2×10^{-8}	1.8×10^{-8}	2.25×10^{-8}	4.8×10^{-6}		1.89×10^{-12}	4.55×10^{-8}	5.3×10^{-8}	4.4×10^{-9}	3.0×10^{-9}
											$<1.75 \times 10^{-12}$	8.36×10^{-8}	7.9×10^{-8}	6.6×10^{-9}	5.5×10^{-9}
12:00	12:08	12:48	Spin jet flush (12:04) Lance flush (12:42)						4.9×10^{-7}		$<1.75 \times 10^{-12}$	5.49×10^{-8}	5.8×10^{-8}	5.3×10^{-9}	4.0×10^{-9}
											$<1.75 \times 10^{-12}$	8.48×10^{-8}	8.7×10^{-8}	7.1×10^{-9}	6.0×10^{-9}
13:00															
14:00															
15:00	14:59	15:34	Area 10 ambient spin jet (15:13)						3.0×10^{-6}						

C-28

REACTOR BUILDING AIR SAMPLE DATA
March 17, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$						$\mu\text{Ci/ml}$	BZA in $\mu\text{Ci/cc}$				
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
			Area 10 ambient lance (15:16)												
			Area 11 flush (15:32)												

16:00

REACTOR BUILDING AIR SAMPLE DATA
March 18, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					$\mu\text{Ci/ml}$	RZA in $\mu\text{Ci/cc}$					
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
3/18/82															
	12:00														
		12:30	14:00	HP survey coverage											
	13:00	13:00	14:00	Trash removal							$<1.82 \times 10^{-12}$	7.1×10^{-9}	1.0×10^{-8}	1.1×10^{-9}	3.0×10^{-10}
											$<1.93 \times 10^{-12}$	6.7×10^{-9}	9.3×10^{-9}	9.1×10^{-10}	2.4×10^{-10}
											$<2.05 \times 10^{-12}$	1.9×10^{-8}	2.8×10^{-8}	2.2×10^{-9}	1.3×10^{-9}
											$<2.2 \times 10^{-12}$	1.2×10^{-8}	1.6×10^{-8}	1.5×10^{-9}	8.1×10^{-10}
	14:00														
	15:00														

REACTOR BUILDING AIR SAMPLE DATA
March 19, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					$\mu\text{Ci/ml}$	BZA in $\mu\text{Ci/cc}$					
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
3/19/82															
09:00	09:36			$<1.8 \times 10^{-11}$	-	7.8×10^{-8}	7.3×10^{-9}	1.1×10^{-8}	2.3×10^{-6}		$<1.1 \times 10^{-12}$	1.5×10^{-8}	1.4×10^{-8}	1.1×10^{-9}	2.5×10^{-9}
10:00	10:06	11:30	LP flush El. 305'	$<1.67 \times 10^{-12}$	-	1.8×10^{-8}	$<4.0 \times 10^{-9}$	$<4.7 \times 10^{-9}$	2.1×10^{-6}		$<1.8 \times 10^{-12}$	3.0×10^{-8}	2.7×10^{-8}	2.5×10^{-9}	4.1×10^{-9}
											$<1.8 \times 10^{-12}$	1.8×10^{-8}	1.4×10^{-8}	1.1×10^{-9}	2.5×10^{-9}
											$<1.8 \times 10^{-12}$	6.2×10^{-8}	6.9×10^{-8}	5.7×10^{-9}	7.8×10^{-9}
11:00															
12:00															

REACTOR BUILDING AIR SAMPLE DATA
March 25, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					$\mu\text{Ci/ml}$	BZA in $\mu\text{Ci/cc}$				
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	I-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134
3/25/82														
09:00	9:30	10:00	HP survey								$<2.1 \times 10^{-12}$	6.8×10^{-9}		
10:00	10:00	10:50	Incore photos											
	10:00	12:30	HP surveys											
	10:00	13:50	Surface deposition											
11:00	11:00	14:30	Video-taping											
12:00														
13:00														
14:00	14:00	16:20	Gamma spectrometer El. 305'											
15:00														
16:00														
17:00														

REACTOR BUILDING AIR SAMPLE DATA
March 26, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$					$\mu\text{Ci/ml}$	BZA in $\mu\text{Ci/cc}$					
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs- 37	Cs-134	Sr-90/Y-90
3/26/82															
09:00															
	09:30	10:00	HP survey								3.09×10^{-12}	1.8×10^{-8}	1.9×10^{-8}	1.6×10^{-9}	2.3×10^{-9}
10:00	10:00	13:00	Surface deposition samples								$<4.02 \times 10^{-13}$	2.2×10^{-10}	1.2×10^{-9}	$<1.6 \times 10^{-10}$	$<2.9 \times 10^{-10}$
	10:30	12:30	Polar crane survey and photos								3.2×10^{-12}	4.1×10^{-8}	5.3×10^{-8}	4.2×10^{-9}	2.7×10^{-9}
11:00											4.29×10^{-12}	5.97×10^{-9}	4.4×10^{-8}	3.5×10^{-9}	2.2×10^{-9}
											6.95×10^{-12}	5.27×10^{-8}	6.7×10^{-8}	5.4×10^{-9}	2.3×10^{-9}
12:00															
	12:30	12:50	Rig gamma spectrometer/equipment								2.8×10^{-12}	5.8×10^{-9}	5.4×10^{-9}	4.2×10^{-10}	4.2×10^{-10}
											3.2×10^{-12}	7.2×10^{-9}	8.5×10^{-9}	8.5×10^{-10}	8.7×10^{-10}
											$<2.14 \times 10^{-12}$	1.63×10^{-8}	2.6×10^{-8}	1.8×10^{-9}	1.4×10^{-9}
13:00															
	13:30	15:00	Gamma spectrometer measurement												
14:00	14:00	17:00	Strip-pable coating test El. 347'-6" and 305'												

REACTOR BUILDING AIR SAMPLE DATA
March 26, 1982

Date	Time	Time	Activity	$\mu\text{Ci/cc}$						$\mu\text{Ci/ml}$	BZA in $\mu\text{Ci/cc}$				
				Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90	H-3	H-3 Bioassay	Gross Alpha	Gross Beta	Cs-137	Cs-134	Sr-90/Y-90
15:00	15:30	16:00	Video-taping												
16:00	16:00	16:30	Rig out gamma spectrometer												
17:00															

OPERATIONAL PARAMETERS - ELEVATION 305'
LOW PRESSURE FLUSH
ENTRY 43

Test Area	Start	Stop	Water Temp-F	Water Temp-Final	Pump Water Pressure (dynamic)	Dose Received During Task Based on Dosimeter Readings (mrem)			Activity	Gal/Min	Water Used (gal)	Time (min)
						Worker #1	Worker #2	Worker #3				
Elevation 305'	11:00	11:04		Amb	5700				Mist only			
I LP	11:06	11:14		Amb	1800				Flush			
	11:18	11:25		Amb		173	170	172	Mist	20	229	19
II LP	11:37	11:57	110		4000	138	136	137	Mist and Flush }	23	652	54
	12:10	12:33	125		4900	617	613	566				
	12:43	12:54		155		755	749	703				
III LP	13:03	13:08	100	-	4400	10	12	9	Flush	23	120	10
	13:55	14:00	92	-		17	16	13				
						27	28	22				
IV LP	14:02	14:10	100	120	2100 1700	77	70	59	Flush	17.5/15.5	97	8
Total											~1098	91

OPERATIONAL PARAMETERS - ELEVATION 305'
HIGH PRESSURE FLUSH

Test Area	Start	Stop	Water Temp-F	Water Temp-Final	Pump Water Pressure ^a (dynamic)	Dose Received During Task Based on Dosimeter Readings (mrem)			Activity	Gal/min	Time (min)	Water Used (gal)	Remarks
						Worker #1	Worker #2	Worker #3					
Open Stairwell	10:18	10:23	86	86	3000				Flush	18.4	5	92.5	
	10:25	10:45			3000	265	344	326	Flush	21	20	420	
												512.5	Total gallons for open stairwell
El. 305' Area XII HP	10:58	11:12	104	80	7400	316	295	285	Spin jet	24	14	246.5	
	11:12	11:24	Amb	70	7400				Spin jet	24	12	211.2	
	11:38	12:05	Amb	70	7400	178	152	209	Spin jet	24	27	475.3	
	12:20	12:45	Amb	68	3300				Lance-flush	15	25	264.7	(did not use #2510 nozzle)
					Total for area	494	447	494					
X HP	14:55	15:14	Amb	Amb	3000				Spin jet	14	19	201.2	
	15:15	15:18	Amb	Amb	2300	82	80	70	Lance	5	3	15	
XI HP	15:22	15:27	120	120	3300				Spin jet	20.5	5	102.5	
	15:30	15:32	120	Amb	2800	43	42	37	Lance	15	2	30	
Total												2058.9	o Pump hours 1 hr 54 min o Water used on el. 305' 1546.3
77 min spin jet on el. 305' 30 min lance on el. 305' 25 min lance on stairwell 132 min = 2 hrs 12 min													

a. HP flush pump pressures required to provide test pressure of 2000, 4000, or 6000 psi at lance or spin jet.

OPERATIONAL PARAMETERS - ELEVATION 305' OVERHEAD, WALLS, ETC.
HIGH PRESSURE FLUSH
ENTRY 49

Test Area	Start	Stop	Water Temp-F	Water Temp-Final	Pump Water Pressure (Static)	Dosimeter Readings (mrem)			Activity	(Gal/min)	Time (min)	Time on Walls & Overhead (min)	Water Used (gal)	Estimated Water Used on Walls & Overhead
						Worker #1	Worker #2	Worker #3						
El. 305'	14:06	14:20	108	~112	3500				305' LP flush	22	14	10	300	240
	14:31	14:55	116	118	3000	375	495	395	305' LP flush	20.5	24	18	513	460
	15:00	15:14	118	Not available	2500				305' LP flush	17	14	10	142	113
	16:05	16:20	104	104	2500				305' LP flush	17.5	15	10	152	122
	16:23	16:45	90	82	2500	451	466	450	305' LP flush	15.5/17.5	22	16	223	178
	16:50	17:01	90	90	2500				305' LP flush	17.5	11	8	112	90
				Total for Task		826	961	846			1 hr 40 min	1 hr 12 min	1442	1203
El. 347'-6" Area III & IV Storage Area	12:30	12:38	84	90	3500				El. 347'-6" LP storage area	~14	8		112	
													Total	1554

Total pump hours
1 hr 42 min

OPERATIONAL PARAMETERS - ELEVATION 347'-6"
LOW PRESSURE FLUSH

Test Area	Start	Stop	Water Temp-F	Water Temp-Final	Water Pressure	Dose Received During Task Based on Dosimeter Readings (mrem)			Activity	Gal/m:n	Water Used (gal)	Time (min)
						Worker #1	Worker #2	Worker #3				
LP Area												
V	11:48	12:11	70	Amb	2000	50	50	45	Flush	14	208	23
VI	12:12	12:35	117	74	4200				Flush	22.5	334	23
	13:05	13:29	90	96	4700	102	103	91	Flush	22.5	348	24
	13:47	13:52	103	74	4200	16	16	16	Flush	19	95	5
					Total for Area	118	119	107				
VII	13:52	14:10	103	74	4200	56	58	59	Flush	19	221	13
VIII	14:10	14:28	102	88	2200				Flush	14.5	168	13
	14:46	14:58	105	92	4200	94	97	98	Flush	13	101	12
										Total	1475	123

OPERATIONAL PARAMETERS - ELEVATION 347'-6"
HIGH PRESSURE FLUSH
ENTRY 48

Test Area	Start	Stop	Water Temp-F	Water Temp-Final	Water Pressure ^a	Dose Received During Task Based on Dosimeter Readings (mrem)			Activity	Water Used (gal)	Time (min)	Gal/Min	Remarks	
						Worker #1	Worker #2	Worker #3						
3/12/82														
I	10:05	10:12	140	120	3100(D)	21	19	22	Spin jet	60.47	7	15	Confined area - pipes, protrusions	
	10:13	10:27			4400(D) Lance				Lance	121.83	14			
II	10:28	10:33	109	94	4400(D)	9	8	9	Spin jet	43.19	5	5	Confined area - pipes, cabinets, etc.	
	10:33	10:40			2400(D)				Lance	60.9	7			
III	10:42	10:58	110	110	2400(D)	31	28	32	Spin jet	138.23	16	5	Confined area - pipes, cabinets	
	11:00	11:03			2400(D)				Lance	26.1	3			
IV	11:18	11:26	88	88	6400(D)	16	15	14	Spin jet	69.1	8	7.5	Storage in 50% of area Cabinets blocking spin jet area	
	11:39	11:45			2400(D)	16	15	16	Lance	52.2	6			
V	11:49	12:35	92	80	6600(D)	32	30	30	Spin jet	397.4	46	5	Did the area twice (30 min. the first time) - tools on the floor.	
	12:43	12:57			821(D) 2600(D)				Lance	121.8	14			
VI	13:18	13:35	72	72	6500(S)	106	99	96	Spin jet	233.26	27	23.5		
	13:46	14:00			6300(D) 3500(S) 3300(D)				Lance	121.8	14			
VII	14:19	14:26	110	120	4500(S)	18	16	16	Spin jet	60.4	7	18	Confined area - small floor space	
	15:20	15:27			4300 3500(S) 3300(D)				Lance	60.9	7			
VIII	15:35	15:48	102	95	7400(S)	53	54	42	Spin jet	112.3	13	18		
	15:51	16:00			7200(D) 3500(S) 3300(D)				Lance	78.3	9			
IX	16:00	16:15	89	89	3500(S)	36	37	29	Lance only	130.5	15	14	Spin jet would not fit in area	
					3300(S)									
Total										1889.0	3 hrs 37 min			
											Pump hours 3 hrs 6 min			
											774.5 gal - lance			
											1114.5 gal - spin jet			

a. D = dynamic, S = static.

OPERATIONAL PARAMETERS - ELEVATION 347'-6" EQUIPMENT
HIGH PRESSURE FLUSH
ELEVATION 347'-6"

Test Area	Start	Stop	Water Temp-F	Water Temp-Final	Water Pressure	Dose Received During Task Based on Dosimeter Readings (mrem)			Activity	Gal/min	Water Used (gal)	Time (min)	
						Worker #1	Worker #2	Worker #3					
3/11/82													
Stairwell No. 1	13:05	13:30	88	88	3200	78	76	73	HP spray (lance) ↓	7.5	31	5 - stopped for 20 min (net 5 min)	
Seal Ring	13:30	13:40	88	100	3200					7.5	62	10	
RC Pump Motor Stand	13:41		100		3200					7.5			
RC Pump Alignment Stand						92	109	79					
Internals Index Fix		13:54		110		Although these tasks were monitored, doses could not be broken down for each task.				7.5	81	13	
West LOCA Duct	13:55	13:56	Drain plugged		3400	55	63	53	Did not complete because of plugged drain	7.5	6	1	
Cable Tray	14:00	14:11	100	86	3400					7.5	69	11	
	15:53	15:56	86	86	3800	87	101	186*	HP spray	19.75	19	3	
*Other tasks on El. 305'										Total	258.1	43	Total pump time .7 hr 42 min

C-40

OPERATIONAL PARAMETERS - POLAR CRANE
ELEVATIONS 426' TO 447'-6"

Test Area	Start	Stop	Water Temp-F	Water Temp-Final	Water Pressure ^a	Dose Received During Task Based on Dosimeter Readings (mrem)			Activity	Gal/min	Time (min)	Water Used (gal)	Remarks
						Worker #1	Worker #2	Worker #3					
3/4/82													
Polar Crane	16:52	17:04	100	95	6400(D) 7000(S)				Mist crane	20	12	138	1 hr 13 min of task for polar crane
Crane/ Dome	17:10	17:24	95	109	6800(D) 7000(S)	141	125	141	Mist dome and crane	20	<u>14</u> 26	<u>162</u> 300	
3/8/82													
General Area - Walkway	10:39	10:52	80	81	5700(D)				Flush	24	13		
	10:59	11:05	81	81	5200(S) 5000(D)	44	43	32		24	6		
Area 2	11:07	11:13	65	80	5700(D)				Flush	24	6		
Cab	11:13	11:17	80	80	5200(S) 5000(D)	18	16	15		24	4		
Trolley	11:22	11:36	90	110	5200(D)				Flush	24	14		
Girders	11:36	11:54	120	120	5400(D)	40	26	40		24	<u>18</u> 61	1071.6	
Total										1 hr 27 min		1371.6 gal	

a. D = dynamic, S = static.

OPERATIONAL PARAMETERS - MISSILE SHIELDS, D-RINGS, CANALS

Test Area	Start	Stop	Water Temp-F	Water Temp-Final	Water Pressure ^a	Dose Received During Task Based on Dosimeter Readings (mrem)			Activity	Gal/Min	Water Used (gal)	Time (min)
						Worker #1	Worker #2	Worker #3				
3/8/82												
D-Rings B Top	15:50	16:03	80	80	5000(S) 4500(D)	66	77	76	Flush	24	116	13
A Top	16:05	16:40	80	80	4500(D) 4200(S)	204	251	220	Flush	24	178	20
B Inside	09:57	10:06	83	70	4600(D) 4200(S)	Not Available				22	98	9
A Inside	10:06	10:26	70	70	4000(S)	Not Available			Flush	22	218	20
Missile Shield/RSS	10:26	10:40	67	67	4000(S)				Flush	22	152	14
	11:03	11:17	70	70	4600(S)	276	323	329			152	14
Refueling Canal					4200(D)							
	12:35	13:01	120	120	4000(S)	52	52	46	Flush	22	283	26
Refueling Canal (deep end)					4200(S)							
	14:28	14:41	83	93	4200(S) 4500(D)	41	42	42	Flush	18.5	142	13
Fuel Bridge	14:43	14:46	92	105	4200(S) 4000(D)	9	10	10	Flush	13	39	3
Total											1378	132 min

a. D = dynamic, S = static.

LOW PRESSURE REFLUSH AFTER HIGH PRESSURE FLUSH
ELEVATION 305'
ENTRY 52

HP Area	Location	Surface	Pre-Gamma Test (mrem)	Post-Gamma First LP (mrem)	Pre-HP (mrem)	Post-HP (mrem)	Pre-Contact Gamma (mrem)	Post-LP Gamma (mrem)	Post-HP Gamma (mrem)	Post-Reflush LP Gamma (mrem)	Pre-Test Beta (mrem)	Post-LP Beta (mrem)	Post-HP Beta (mrem)	Post-Reflush LP Beta (mrem)	Pre-Test Cs-137	Post-LP Cs-137	Post-HP Cs-137	Post-Reflush LP Cs-137	Pre-Strip Coat Cs-137	Inter-mediate Strip Coat Cs-137	Post-Strip Coat Cs-137
III	53-1	Floor			1300	1200				3800			9360	12,800							
	53-2	Floor			1100	1300				1800			1170	2000							
	53-3	Floor	800	600	1200	1300	1000	900	1800	1900	4560	2660	780	1200	4.8x10 ⁶	1.7x10 ⁶	7.5x10 ⁵	6.2x10 ⁵			
	53-4	Floor			1100	900				1600			3900	800							
	53-5	Floor			900	900				1200			780	6400							
	61	Floor	1000	600		400	3400	1000	900	1000	17,480	8360	8190	10,000		9.3x10 ⁶		9.5x10 ⁶			
Area ISC - no high pressure flush - strip coat + Post-LP and LP Walls and Overheads																					
IV	65-1	Floor	300	180	No HP		600	340	300		6080	2120	1950								
	65-2	Floor	280	200	flush of this area		400	270	260		10,640	2770	2496								
	65-3	Floor	300	200			600	500	300		14,400	2660	2730		2.9x10 ⁷	5.5x10 ⁶			1.3x10 ⁶	7.5x10 ⁴	5.9x10 ⁴
	65-4	Floor	360	230			400	380	370		21,280	2350	2067								
	65-5	Floor	340	240			800	420	420		9120	2960	2652								
	70	Floor	220	180			340	210	200		4780	1100	1014		6.6x10 ⁶	9.3x10 ⁶			1.2x10 ⁷	4.0x10 ⁴	5.7x10 ⁴

DO NOT MICROFILM
THIS PAGE

APPENDIX D
TRAINING AND SAFETY

CONTENTS

SELECTION AND CONTROL OF PERSONNEL FOR TRAINING	D-1
TRAINING PROGRAM METHODS	D-4
TRAINING EQUIPMENT	D-9
TRAINING ADMINISTRATION	D-16
FINAL MOCK-UP METHODS	D-20
DATA TAKING	D-24
TRAINING EFFECTIVENESS	D-26
TRAINING EFFICIENCY	D-28
SAFETY ISSUES AFFECTING THE DECONTAMINATION EXPERIMENT	D-29

ATTACHMENTS

D-1	SAMPLE WORK PACKAGE
D-2	TECHNIQUE SHEETS
D-3	GENERAL ENTRY TRAINING
D-4	PRE-JOB BRIEFING OUTLINE
D-5	POST-JOB DEBRIEFING OUTLINE
D-6	HEAT STRESS PROGRAM
D-7	TRAINING PROGRAM EFFECTIVENESS EVALUATION
D-8	TRAINING HOURS ESTIMATE BY MANPOWER SOURCE

APPENDIX D - TRAINING AND SAFETY

SELECTION AND CONTROL OF PERSONNEL FOR TRAINING

During the planning of the Decontamination Experiment, a scope of work was defined in order to make estimates of manpower requirements for training. These estimates were based upon specific task lists, man-hour estimates by task, skills requirements for each task, dose estimates for tasks, and allowances for backup personnel.

Sources of Manpower

Several sources of manpower with a wide range of skills and talents were utilized during the experiment.

Health Physics Technicians

Health physics (HP) technicians were either supplied or subcontracted by the licensee to perform radiological surveys and otherwise support the experiment. These personnel already possessed a high level of training and were the easiest to assimilate into the program. Approximately 1 HP man-hour was required in containment per 20 man-hours of experimental work.

Client Maintenance Department

Instrument and control technicians, electricians, and mechanics were supplied by the client utility on a limited basis. Their duties consisted of repairs to operating plant systems required during the experiment, including the CCTV system used to monitor containment activity.

Building Trades Crafts

Building trades crafts personnel, supplied by Catalytic, Inc., represented the following trades: ironworker, pipe fitter, electrician, carpenter, and laborer. They were utilized for installation of most of the support systems, such as decontamination water, electric power, and the spider work platform. In addition, the laborers gave general support both in and out of containment, did radwaste removal, and performed some data collection.

Remote Reporters

Individuals employed by the client in other job locations not related to power plants were periodically assigned to decontamination work at the site. This permitted the dose to be spread more evenly among the available employees. These workers performed all of the experimental decontamination tasks and most of the data collecting. Remote reporters were requested by the client to report on a specified day, for a predetermined time, to work exclusively on the experiment.

Subcontracted Technicians and Engineers

Subcontracted technicians and engineers were required when the needed expertise was not available from the other sources already discussed. Requirements in this category included photography and data collection (Bechtel National, Inc.), gamma spectrometer survey (SAI), surface deposition tests (EG&G), and decontamination techniques (Vikem). This work accounted for about 10 percent of the total time expended.

Volunteers

A small number of personnel, usually engineers, were also available from the client under certain conditions as part of a volunteer program. During the Decontamination Experiment, however, this resource was supplanted for the most part by the remote reporters.

Supervision and Coordination

The remote reporters were assigned to a foreman who assumed supervisory and administrative responsibilities not specifically related to the experiment. Additionally, the foreman assisted the instructors in determining the training status and performance of each individual and made recommendations for efficient utilization of the manpower resource. All other personnel were supervised by their parent departments. Working foremen were designated for the building tradesmen to supervise and help perform work.

Union regulations and rotating work shifts complicated scheduling. Better coordination resulted when a single individual scheduled all training and the parent department retained a dedicated coordinator to assist in scheduling and supplying manpower. Ultimately, the coordination was broken down by health physics support (GPU), building trades (Bechtel), and site maintenance (GPU).

Prescreening

All individuals who entered the training program were screened to ensure that prerequisites were met. These prerequisites consisted of radiological requirements that were not under the control of the implementation group, Bechtel Northern, and included:

- o Valid radiological work permit training
- o Valid whole body exposure record on file
- o Valid whole body count
- o Valid respirator physical
- o Satisfactory respirator fit test

- o Valid thermoluminescent dosimeter
- o Security badge for access to required plant areas.

The individuals who did not satisfy all of the requirements were returned to their respective organizations for reassignment.

TRAINING PROGRAM METHODS

Training Work Package

The training work package consisted of detailed written instructions for completion of each task. Some task descriptions were specific and were used only once; others were generic and were used several times. An example of a generic work package is removal of trash from the containment. The content of the training work package and the standards for instruction provided the starting base for the training program.

In addition to the instructions for the task, the work package contained sketches, photographs, equipment lists, and other attachments to enhance the overall comprehension of the work requirements. (See Attachment D-1 for examples of typical work package contents.)

Lessons learned in this area were:

- o Use one format for work packages.
- o Establish methods and the status for revisions to work packages.
- o Establish responsive review procedures for training quality and responsibility for training records and policies.

Technique Development Phase

Before a work package was undertaken, an initial training phase was completed to determine the optimum way of accomplishing each task. This is known as technique development. It is an optimization process giving the highest probability for success. An example is to determine the assembly process for a heavy piece of equipment, which would consider the difficulty of performing each assembly step and determine which steps are sequence dependent. In addition, endurance issues must be settled, such as what size subassemblies can be prepared outside containment and carried in, or whether all parts have to be carried in separately.

Decontamination methods are also classified as techniques. Examples of technique descriptions for flushing are contained in Attachment D-2.

Lessons learned during this phase were:

- o Ensure that work packages are fully developed prior to training people on the package.
- o Prepare a work package structure that can accommodate revisions quickly and that contains the items that are appropriate for the task.

Classroom Phase

In the classroom phase, the decontamination workers and an instructor reviewed the work package as well as routine procedures for working in radiologically controlled areas. (Topics in general entry training and typical procedure handouts are contained in Attachment D-3.) Some of the procedures and subjects especially highlighted during training include dress-out procedure, contamination control, heat stress, and fire protection.

During the classroom sessions the job was discussed, and training aides such as photographs, videotapes, and models were used to develop better understanding of the procedures. At the end of the sessions, all participants should have felt satisfied with the level of knowledge attained and ready to proceed to the next phase of training.

Lessons learned during this phase were:

- o Establish rigid instructor classroom standards.
- o Ensure that only finalized work packages and procedures are used for instruction.

Walk-through Phase

A walk-through is a timed execution of the work package involving all participants and feasible equipment. During the walk-through, personnel were not required to dress in protective clothing or use respirators. However, during tasks requiring manual dexterity, protective gloves and work gloves, if applicable, had to be worn. The walk-through was preceded by a briefing describing the work situation and any simulations in effect. A walk-through was considered successful when the job was performed efficiently and without coaching.

Lessons learned during this phase were:

- o Written standards are required for the walk-through phase of training.
- o Provide equipment for those parts of the task that require some protection in handling; e.g., gloves for rigging tasks.

- o Ensure that the walk-through conforms exactly with the work package.
- o Document the training at the time it is accomplished.

Mock-up Phase

This phase of training consisted of dress rehearsals for the tasks, creating working conditions as realistically as possible. In some cases this required constructing full-size replicas of plant equipment or areas. For the final mock-up of a work package, protective clothing was worn to demonstrate endurance requirements. The purpose of this phase was to identify problems or areas that needed special attention before actual entry, so that exposure time could be minimized and tasks accomplished as efficiently as possible.

Lessons learned during the mock-up phase were:

- o Written standards are required for the conduct of mock-up training.
- o Ensure that the mock-up is as representative as possible of the actual work to be accomplished.
- o The persons performing the task should wear the protective clothing that will be required in the reactor building.
- o All equipment for the task should be used during the mock-up.
- o Ensure that a sufficient number of spare or reserve personnel are trained on the mock-ups to allow for sickness or task slippages which may require substitutions.
- o The trainer should be in the command center and should direct that task during the entry, if possible.

Final Briefing

Prior to each decontamination entry, each worker team received a final briefing, done in compliance with 10 CFR 19 for instructions to workers in radiologically controlled areas. The briefing also served to reinforce previous training and allowed an opportunity for final questions. Items covered included:

- o Job sequence
- o Information regarding coordination with other groups
- o Dose estimate
- o Reading and acknowledgement of RWP
- o Criteria for termination of job
- o Schedule for the day.

Attachment D-4 is a complete pre-job briefing outline of items discussed.

Lessons learned during the final briefing phase were:

- o Written standards for the briefing are effective.
- o One organization and procedure should be responsible for and should provide the guidelines for the briefings.
- o Ensure that interfacing entry teams are briefed together.

Post-entry Debriefing

An important phase of the training program was the post-entry debriefing. Through this session, descriptions of conditions within the containment building were reported, and some evaluations of procedures could be made. Also, adequacy of planning, equipment, and training was determined. Therefore, the debriefing was a vital tool in judging the training and determining improvements for future operations. Attachment D-5 is an example of the guidelines used during the debriefing and illustrates the thoroughness of topics covered.

Lessons learned during this phase were:

- o Written standards for the debriefing are effective and are required. These should include:
 - Debriefing time and location
 - The person responsible to conduct the debriefing
 - The materials to be provided at the debriefing, such as records, tapes, RWPs, etc.

TRAINING EQUIPMENT

The use of proper equipment helps ensure high training quality. For work done in radiation areas, workers needed to understand and be able to demonstrate that they could perform all details of the assigned task.

Training Aids

Aids were used in the training program to make a given objective more understandable.

Lesson Plans

The most basic training aid was the lesson plan. It identified the training objective, guided the instructor in the use of all required teaching materials, and described the methods for conducting the lesson. Elements included a list of student handouts, training aid summary, support services required, and the lesson discussion outline.

A lesson plan was prepared in advance by the training administrator and was kept on file until needed.

Work Package. When the lesson plan used was a work package, a cover sheet was attached to document any additional training information. In most cases, the work package could stand by itself as a lesson plan.

Special Equipment. For each piece of equipment requiring training, a lesson plan was prepared to describe the principles and methods of operation.

General Entry Training. This was an indoctrination course administered to all personnel who trained for reactor building entry. The course lesson plan is given in Attachment D-6. Refresher training was also required at 90-day intervals or as often as necessary when policy or procedure changes required a more frequent update.

Photographs

Photographs were an invaluable training aid for work done in radiation areas and were particularly important when students were not familiar with the work area. Photographs could be used to verify installation details, define access routes and methods, and assist in proper tool selection and construction of mock-ups.

Closed-Circuit Television System and Videotape

Training at TMI-2 was enhanced by the use of a CCTV system installed in the containment. Eight cameras were installed in locations that permitted a large percentage of the containment to be seen from the command center, where work was monitored. The cameras could be remotely panned, tilted, zoomed, and focused. This system was used in the following ways:

- o All personnel received a containment familiarization as part of general entry training by viewing the containment from the command center.
- o Work done was recorded on videotape for historical, debriefing, and subsequent training purposes.
- o Specific training tapes could be made with input from the installed cameras or filmed elsewhere with a portable camera.
- o Portable cameras could also be used in the reactor building to film areas that would not otherwise be in view by the main system of cameras.

Videotape provided information similar to that provided by photographs, but required no processing time. Still photography was usually preferable to portable videotaping because it required fewer personnel and no support services for electric power and signal path out of containment.

Plant Model

A plant scale model was available as a training aid. Although it was not highly detailed, it could be used for worker orientation, distance measurements, and job planning. Its best applications were to show students the access paths to remote work areas and to brief personnel who would be working at different locations at the same time. A job walk-through in this situation improved coordination of the separate groups and improved overall understanding of the task.

Mock-up

A mock-up is the physical representation of a work area for training purposes. This full-scale training aid may be as small as a single piece of equipment or as large as a major component of the reactor plant. In addition to training benefits, mock-ups also demonstrate the feasibility and function of special tooling and verify proposed operating procedures and worker techniques.

The following mock-ups were required for TMI-2 decontamination:

- o Personnel air lock and loading ramps
- o Spider work platform supports
- o Spider work platform operating area
- o Elevation 347'-6" lifting rig (1500 pounds)
- o Polar crane lifting system (300 pounds)

- o Contamination control corridor
- o Gamma spectrometer (size and weight only)
- o Decontamination surface mock-ups
 - Stairwell
 - Vertical surface
 - Horizontal surface
 - Polar crane (turbine building crane used)
- o Decontamination equipment checkout
 - High pressure pump (for decontamination)
 - High pressure pump (for training)
 - Spin jet
 - Wet vacuum system

- Strippable coat pump
 - Hydrolance fittings
 - Decontamination services penetration
- o. Special equipment checkout
- High reach work platform
 - Forklift
 - Spider work platform
 - Elevation 305' to elevation 347'-6" lifting system
 - Elevation 347'-6" to elevation 426' lifting system
 - Surface deposition samplers.

Most of the mock-ups were located together in a centralized training area; some with special size requirements were located outside the area, and others already existed elsewhere in the plant.

Operating Systems

Since all system valve operations took place outside containment, the actual plant systems were used as training aids during final systems checkout. However, a training system was also constructed to allow training and decontamination at the same time.

Qualification Program

Each piece of training equipment described had to be operated by a qualified individual. Decontamination techniques were consolidated into a series of classes to help qualify an individual to operate all equipment. For special equipment, qualifications were met either through a separate course or as part of the work package that installed the equipment.

Supply of and Repairs to Training Equipment

Training equipment had to be available in sufficient quantities to support the program and to meet requirements for inspections and repairs. When only one item going into containment was purchased because of exceptional expense, a reservoir of qualified personnel had to be established before installation. In other cases, one of each training item was required if the task was to be performed on a one-time basis. When a piece of equipment was to be used repeatedly, a special training unit had to be allotted or a realistic mock-up constructed in order to meet training objectives. When the cost of an item was not prohibitive, if its use was critical to the program, or if its reliability was questioned, more than two units might be required.

Most large pieces of equipment were delivered with a list of recommended parts, and stocking of these parts was recommended.

Use of Procedures and Work Instructions

A procedure is a client-approved document, usually involving operation of plant systems, which requires verbatim compliance. Work instructions, on the other hand, are less strictly controlled and may be used to accomplish a variety of tasks. Validation of these documents through training is essential for a successful program. Any item that cannot be completed as written should be brought to the attention of the instructor.

Simulations and other differences between the training system and the actual system had to be understood by all students. Operational communications needed to provide a system procedure, such as special telephone circuits, also had to be set up in training. Checkout of the actual communications network was a prerequisite to the real work proceeding. When more than one procedure was to be in use at the same time, coordination procedures were often required. Supervisory personnel had to be trained in these coordination procedures.

TRAINING ADMINISTRATION

Training Engineer

The training engineer is responsible for the administration of the training program. He performs the following functions:

- o Review work packages for training impact
- o Select personnel from available resources
- o Screen individuals for prerequisite requirements
- o Specify training requirements
- o Schedule and monitor training activities

- o Notify scheduling group when training is complete
- o Debrief entry team members, recommending follow-up action within the area of responsibility
- o Maintain all lesson plans and individual records of training.

The preceding policies and methods resulted from the following problems experienced during the decontamination test:

- o More than one training engineer was involved in the same program.
- o The training engineer was not a dedicated individual with no other duties.

Instructor

The instructor is the individual assigned by the training engineer to teach an individual lesson plan. Instructors for work packages were either the cognizant engineer (writer of the work package) or the craft supervisor responsible for completion of the work package. For other lesson plans, the best qualified individual, or one qualified in an instruction program, was used, including client personnel when required (e.g., in lesson plans for safety training).

Instructor responsibilities are:

- o Teach and document training in accordance with the lesson plan
- o Ensure that scheduled personnel are present
- o Make recommended changes to the lesson plan
- o Inform the training engineer of problems.

The preceding policies and methods resulted from the following problems experienced during the decontamination test:

- o No written standards existed for establishing instructor performance.
- o Cognizant engineers were not sufficiently involved in training and in feedback from training.

Task Supervisor

The task supervisor is the individual responsible for direction of the task from the command center. Normally, he is either the cognizant engineer or the craft supervisor. For decontamination work, he may be a specifically assigned operation engineer. The duties of the task supervisor are:

- o Attest to the readiness for final mock-up training
- o Conduct and document walk-through and mock-up training
- o Attest to the adequacy of all work instruction and procedures
- o Conduct and document pre-job briefings
- o Thoroughly understand command center operations
- o Attend debriefings.

A qualification program is recommended for task supervisors.

The preceding policies and methods resulted from the following problems experienced during the decontamination test:

- o No written standards existed for task supervisors with respect to training responsibilities.

- o Mock-up performance was inadequately documented.
- o Mock-ups were scheduled prior to issuance and accountability procedures of final work packages.
- o Some task supervisors were unfamiliar with command center equipment and procedures.

Documentation

The use of training documentation helps ensure that training is being carried out in accordance with prescribed standards. The following records are maintained:

- o Prescreening reports for validation of prerequisite training
- o Master lesson plan file
 - Individual work package file
 - Special equipment file
 - Safety training file
 - General entry training file
 - Radiological instruments and data file
 - Decontamination techniques file
- o Debriefing file
- o Individual qualification record file

- o Schedules file
- o Certification records.

The preceding policies and methods resulted from the following problems experienced during the decontamination test:

- o More than one set of training records was in use.
- o No written standards existed for recordkeeping.

Qualification and Certification

Qualification is the process whereby the training engineer acknowledges that a student has satisfactorily completed a particular lesson plan. Certification is a two-step process whereby the training engineer specifies all requirements before an individual can enter the containment, and the health physics engineer attests that these requirements have been completed.

FINAL MOCK-UP METHODS

Final mock-up refers to the last practice session for any given work package. Final mock-up may encompass one or more of the following:

- o Walk-through
- o Full mock-up
- o Prove out shown by heat stress test and walk-through.

The factors considered for determining the requirements were:

- o Previous worker experience

- o Number of available personnel and scheduling flexibility
- o Radiation dose field in work area
- o Previous job results with similar work packages
- o Status and validity of existing job-time estimates.

Work Package Walk-through

This is a timed execution of the work package involving all participants and either actual equipment or mock-up equipment. Actual equipment should be used if feasible, but individuals do not have to wear protective clothing or use respirators. Tasks involving manual dexterity do require the wearing of protective gloves and work gloves, if applicable. The instructor for these sessions will normally be the task supervisor. Walk-throughs always precede a full mock-up, if it is required.

Walk-throughs as final training are limited to:

- o Repeat jobs or highly experienced individuals
- o Uncomplicated new work done by craft personnel or health physics technicians within their normal scope of work.

Work Package Full Mock-up/Prove Out

In a full mock-up, a dress rehearsal is completed by all workers in the protective clothing expected for the in-containment work. In other respects, it is identical to the requirements of a walk-through previously described. The instructor is normally the task supervisor. A prove out is a specialized form of full mock-up designed to obtain all approvals for performance of the package (time, dose estimate, adequacy of techniques, etc.). The individuals

doing the prove out do not, however, have to be the ones to actually perform the package, and the package may be done several times with additional personnel. In either case, following an acceptable prove out, a walk-through and heat stress test may be substituted for all follow-on personnel.

Full mock-ups are done for new work packages, for jobs done in high radiation dose fields, and when worker endurance may be a controlling factor. This places the highest level of control possible on the work package and increases its chances for success.

When using remote reporters or any other dedicated group to accomplish a wide range of work packages in a specific interval of time, the prove-out method is most effective. Each work package is validated with one crew. Walk-throughs and heat stress tests for follow-on personnel save time and allow the training engineer to form an availability matrix of personnel and jobs for which they are qualified. Time constraints prohibited full mock-ups in this situation for all personnel for all work packages, and experience has shown that trying to match selected individuals to each decontamination work package caused work stoppages because of absence, repetition of work, or changes to the decontamination sequence schedule. The matrix provides qualified alternates and sufficient flexibility to place manpower where it is most needed.

Heat Stress Test

The heat stress test is a physiological test performed by the GPUN safety department to determine an individual's suitability for working in protective clothing. Requirements for completion of this test are contained in Appendix D, Attachment D-6. Prior to an initial entrance into containment, all individuals must complete one of the following:

- o Heat stress test and walk-through
- o Full mock-up for estimated work time.

At the end of the heat stress test, physiological monitoring is performed for pulse and body temperature. This monitoring must also be performed for any individual wearing a full wet suit, regardless of the other training requirements. Once passed, a heat stress test is good for 90 days.

Standard Mock-up Techniques

Before a final mock-up is carried out, the individual conducting the mock-up must do the following:

- o Conduct a briefing, noting simulations in effect, communication methods, and the role of support personnel and equipment.
- o Ensure that the job is performed within the space allowed in-containment; if no mock-up exists, place tape on the floor or otherwise mark the work area.
- o Ensure that lighting conditions simulate actual containment conditions as closely as possible.
- o Begin and end training at the air lock mock-up, using all required equipment, and ensure that each individual understands the transportation requirements.
- o Allow the students to work without coaching.
- o If climbing or other physical exertion is part of the job, insert an equivalent amount in the training session.
- o If data are being recorded as part of the work package, ensure that individual assignments are understood, including delivery of the data to an assigned individual.
- o Hold a debriefing session.

The preceding policies and methods resulted from the following problems experienced during the decontamination test:

- o No written performance standards existed.
- o First mock-ups were not complete in time to secure final approvals without use of overtime.
- o Either final mock-ups were not fully representative of actual work or time estimates were questionable because of coaching of the workers.
- o Workers were in poor physical condition, showing lack of endurance and physical stamina.

DATA TAKING

Data Types

All containment work requires one or more of the following types of data:

- o Work package step signoffs
- o Radiological surveys
- o Air samples
- o Smears or scrapes
- o Data tables
- o Sketches and measurements

- o Physical samples
- o Other subjective evaluations and observations.

All workers, task supervisors, and support personnel need to be trained in the proper techniques for data handling.

Data Taking Training Program

Non-health physics personnel required to take radiological data must be qualified in accordance with the lesson plan for radiological instruments and data. All other requirements for data collection are specified by the cognizant engineer in the appropriate work package.

The role of support personnel in data handling logistics is defined through briefings. The task supervisor must ensure that all data coming out of containment are properly recorded or otherwise processed. All work package signoffs must be made on the official work copy for permanent retention, and omission of data collection must be noted at the work package debriefing.

The preceding policies and methods resulted from the following problems experienced during the decontamination test:

- o Logistics of data handling were not understood by team members, support personnel, and supervisors.
- o Data were lost in processing.
- o Data sheets were incorrectly or incompletely filled out.

- o Radiological data were obtained by remote reporters at a much slower pace than by health physics technicians.
- o Because of difficulty in following the work package, some work package signoffs were not made, and physical parameters were not recorded in the command center.

TRAINING EFFECTIVENESS

Self-Evaluation

Attachment D-7 contains a list of questions that can be used as a guide for evaluating the effectiveness of the training program. The evaluation compares various aspects of worker productivity and administrator effectiveness to the prescribed standards. Although some items on the list can be put into quantitative form, the majority of the judgements are subjective.

Debriefing Policy

The majority of the feedback for determining training effectiveness comes from debriefing. Workers must be aware of their responsibility to report problems freely, and the training engineer must create an environment and an administrative system by which these problems can be tracked and corrected.

Attendees at debriefings include:

- o Debriefing chairman (represents training engineer)
- o Task supervisor
- o Cognizant engineer
- o Entry team members

- o Entry team foreman (union employees only)
- o Site liaison engineer
- o Client radiological engineer (ALARA) (optional).

Records of the debriefing include:

- o Summary sheet
 - Entry data
 - Team members
 - Craft
 - Work package number
 - Individual job-hours and job-rems
 - Total job-hours and job-rems
 - Clock hours of entry
- o Team record (for each team)
 - Team member comments
 - Command center log sheets
 - Radiation work permit
 - Radiation surveys, if taken.

These records are assembled the day following the entry and reviewed for action items by the training engineer and the containment access group supervisor.

The preceding policies and methods resulted from the following problems experienced during the decontamination test:

- o No written standards of performance existed for the training program.
- o Effectiveness evaluations were not conducted.

TRAINING EFFICIENCY

For budgetary reasons, it is desirable to train entry personnel in as short a time as possible, as long as appropriate standards are maintained. Attachment D-8 gives approximate training times on a per work package basis for the type of personnel listed in "Selection and Control of Personnel for Training." It should be recognized that the training times for more complex jobs may vary considerably from those shown in Attachment D-8, which are only intended to be typical values. Attachment D-8 gives no time for prerequisite activities, such as RWP, respirator training, physicals and qualification, fit tests, and whole body counts. These activities should be completed prior to scheduling containment entry training. The table in Attachment D-8 further assumes that no retraining is required and that the required training can be scheduled in blocks that result in full use of each work day, including the part of the day when training is not scheduled.

The following conclusions can be drawn from the table:

- o It is more cost-effective from a training standpoint to use health physics technicians to gather radiological data than to train other personnel.

- o Cost savings are realized in training when all personnel make several entries.
- o It takes at least 2 full weeks to adequately train entry support technicians.
- o Remote reporter training requirements drop off significantly after the initial indoctrination program. This allows the personnel to make effective use of their available quarterly dose in about 3 weeks, given current radiological conditions.
- o Polar crane workers require an additional 9 hours of safety training.

SAFETY ISSUES AFFECTING THE DECONTAMINATION EXPERIMENT

Heat Stress

Preventing heat stress is a primary concern of the containment entry program. A complete description of this subject and policies, as promulgated by the client, is contained in Attachment D-6. It was prepared by GPU's corporate industrial hygienist and the site safety supervisor over a period of months during which the problems incurred during past containment entries were evaluated. The resulting policies acknowledge that:

- o Extended work times cause heat stress.
- o When impermeable clothing (plastic wet suits) is worn, some type of body cooling is necessary.
- o The best form of body cooling is the ice vest.
- o Proper training and physiological screening reduce the chances of heat stress.

Fall Protection and Working at Heights

When required, several types of fall protection are available to workers. These requirements are specified by the safety department to comply with federal regulations. Some of these measures include:

- o Use of safety belts
- o Use of center rail ladder belts
- o Proper use of ladders and erected platforms
- o Use of mobile work platform (high reach scissors lift)
- o Polar crane fall protection system (use of retractable lifelines and rescue equipment)
- o Use of polar crane access work platform (spider).

Belts, Ladders, and Scaffolding

Safety requirements for belts, ladders, and scaffolding are specified in each work package requiring their use. Safety belts are required when personnel must work outside constructed work platform handrails or when grating from the floor has been removed. Center rail belts are used in conjunction with climbing center rail ladders. These ladders are required to be installed in areas where the vertical ascent exceeds 20 feet. The amount and type of scaffolding constructed depends on its application, available space, and the length of time it is required. Constructed scaffolding, including access ladders, must be securely fastened and inspected before its use.

Mobile Work Platform

A mobile work platform was purchased for use in the Decontamination Experiment. It is a battery-operated, self-propelled scissors lift, capable of working at heights between 6 and 20.5 feet. It is limited to a capacity of 750 pounds on the main platform (usually two men, tools, and equipment). A 2.5-foot overreach platform, which also has a capacity of 250 pounds, allows access to most wall penetrations. The device was used only on elevation 305'. Built-in safety features prevented overloading the platform or tipping the unit and allowed several means of emergency shutdown. The principal advantage of this device is the job-rem and time savings it affords when less scaffolding is built.

Polar Crane Safety

One of the most challenging problems encountered was to establish a method for access to the polar crane, which, at the time of the accident, was positioned away from the parked position. This meant that the normal access ladder did not line up properly with the crane, made the climb much more difficult, and required the use of fall protection equipment. The following key steps were taken to establish an acceptable access route:

- o Climbing and rescue procedures were written.
- o The safety department performed the initial climb and installed a system of fall prevention equipment and rescue devices.
- o Subsequent climbs received a safety department escort until a method of instruction could be developed for regular training of polar crane workers.
- o Several inspections of the crane were conducted, including taking the measurements needed to install a work platform.

- o An acceptable work platform, capable of lifting four men from elevation 347'-6" to the polar crane walkway, was procured and engineered for installation.
- o Concurrent with the work platform procurement, application was made by GPU for minor variances from OSHA regulations.
- o Lifting systems were installed on elevation 347'-6" and on the polar crane.
- o The work platform was installed and tested; this included support installation, electric power, and platform assembly.
- o The current training program was established, requiring all personnel to learn the climbing technique, use of safety equipment, and operation of the work platform.

The time frame for developing crane access routes resulted from the desire for early inspection of the polar crane and its decontamination in the proper sequence for the Decontamination Experiment.

Protective Devices for Decontamination

Use of high pressure cleaning systems required the use of foot and skin protective devices as well as hearing protection.

Aluminum foot and skin guards were used. These devices were acceptable even though they were awkward to walk in, particularly on stairs. For this reason, they were put on and removed at the reactor building work area.

Standard industrial ear plugs were used for hearing protection. Unfortunately, these plugs were not truly compatible with the radio earpieces used, and a better solution would have been to use a radio headset that also sealed

out background noise. Although a system of this type was tested, it was not implemented because of reception problems with the radio. If headsets had been used, modification of the type of protective hood worn would have been required, since the hood used was not large enough to accommodate a headset.

Worker safety was also enhanced by direct radio communications between the command center and the entry teams, and by telephone headset communications between the command center and the high pressure pump. Almost all decontamination work was also visible on closed-circuit television as well. Equipment requiring protection from high pressure spray mist was covered with plastic.

Confined Space Requirements

If unventilated for a period greater than 7 days, a reactor building is considered a "confined space." This requires monitoring the atmosphere for sufficient oxygen levels (19.5 to 21 percent) and for the presence of combustible gases (less than 20 percent of the lower explosive limit). These measurements are performed by the first individual entering the air lock and containment. If measurements cannot be taken or if their results are either unsatisfactory or in question, subsequent entries are performed using self-contained breathing air only. Several instances of questionable readings have occurred in the past. The following factors have been determined to cause erroneous readings:

- o Transmissions from the radio system
- o Fluctuations in reactor building pressure and air lock pressure
- o Lower-than-recommended shelf life of the oxygen cell portion of the detector. (The actual acceptable replacement interval is about 2 months; the vendor-recommended shelf life is 6 months.)

Equipment Movement

Lifting and handling heavy equipment have the potential for causing personnel injury. Detailed rehearsals for these work items are required to ensure that the techniques employed are safe and efficient. This is particularly true when lifting devices and heavy equipment (forklift, winch, etc.) are involved. When equipment is to be carried, rehearsals must include instructions on prevention of back injury and controls that limit individual loads to about 50 pounds. Worker endurance must also be validated in mock-up training.

Fire Protection

A full fire protection capability was restored to the accessible areas of the containment building by implementation of the following measures:

- o Replacement and test of fire hoses on elevations 305' and 367'
- o Installation of portable fire extinguishers in the anteroom and on elevations 305' and 347'-6"
- o Maintenance of a log of transient combustibles by the command center; use of fire-resistant materials where possible
- o Training of entry personnel on casualty procedures and use of fire extinguishers
- o Training of fire brigades on containment conditions
- o Welding, cutting, burning, and soldering controlled per site procedure 1410-Y-26, with fire watches in radio contact with the command center
- o Monitoring of containment with CCTV following entry.

ATTACHMENT D-1
SAMPLE WORK PACKAGE

TMI-II RECOVERY WORK PACKAGE

Work Package No.: 53 Charge No.: _____

Revision No.: Original

TITLE: Gross Decontamination Test: Low Pressure Flush of Polar Crane

ORIGINATOR: J. R. Kannard

ESTIMATED WORKER REQUIREMENTS:

1. Manhours in Containment 30.5
2. Manrem 4.37
3. Entry Hours 6

APPROVAL:

- ° Decon Superintendent _____ Date _____
- ° CAG/Decon ALARA Review _____ Date _____
- ° Decon Operations Review *[Signature]* Date 12-22-81
- ° Cognizant Engineer *[Signature]* Date 12/14/81
- ° Training Review *[Signature]* Date 12/17/81

DISTRIBUTION: D. M. Lake (1)
T. E. Morris (3)
J. P. Pope (1)
W. H. Shirey (1)
P. R. Bengel (6)
J. Renshaw (1)
R. E. Walker (1)
R. L. Rider (1)
R. W. Jackson (1)
J. Schork (1)

1.0 PURPOSE AND SCOPE

The purpose of this experiment is to mist and low pressure water flush, the polar crane (and dome) area. A flow rate of 25 gpm will be used at both ambient temperature and 140°F. All surfaces except the underside of the polar crane will be flushed.

2.0 LIST OF REFERENCES

- 2.1 TMI Unit No. 2 Operating Procedure 2104-4.55, Reactor Building Entry and Pre-Decon (Rev. 5).
- 2.2 Data Acquisition Sample Package for Task No. 3.
 - Part 3.1 - Initial Data Collection and Misting of the Polar Crane.
 - Part 3.2 - LP Flushing of Polar Crane and Dome Area.
- 2.3 Work Package 41; Hose Installation and Test.
- 2.4 Work Package 47; Low Pressure Misting and Flushing of 305' Elevation.
- 2.5 Work Package 5; Equipment Protection
- 2.6 Work Package 48.2; Flushing of Stairwell No. 2.
- 2.7 Procedure for Ascent To and Descent from the Unit 2 Polar Crane, 2104.9-1.

3.0 LIST OF ATTACHMENTS

- 3.1 Equipment List
- 3.2 Manpower Assignments
- 3.3 Pre-Job Briefing Outline
- 3.4 Post-Job De-Briefing Outline
- 3.5 Prerequisite Verification Sheet
- 3.6 Technique Sheet - Data Collection
- 3.7 Data Collection Sheets

3.8 Figures

3.9 Technique Sheet - Hydrolance Operations for Misting and Flushing.

3.10 Representative Schedule

4.0 PREREQUISITES - (to be verified on Attachment 3.5 for each entry this Work Package is used).

4.1 The Spider Access System is installed and operational.

4.2 The following Work Packages are complete:

- #41: Hose Installation & Test (Applicable Sections)
- #47: Elevation 305 LP Flush
- #5: Equipment Protection

4.3 No other work may be in progress in the building during the execution of this work package.

4.4 The Decontamination Experiment Water (DEW) System has been installed, operationally tested and is functional and standing by for operation.

4.5 See Misting and Flushing Caution #5.

4.6 Equipment Protection has been accomplished on the Polar Crane.

4.7 Operation of the Reactor Building Purge system must be in compliance with GPU and NRC Directives for flushing activities.

5.0 GENERAL REQUIREMENTS

5.1 The equipment required for performance of this Work Package is listed on Attachment 3.1. The amount of this equipment required for each team entering the Containment Building will be determined on a case basis by the Decon Operations Supervisor and staged in the anteroom. No equipment staged for an entry shall be left behind in the anteroom.

- 5.2 Crew members shall be designated "A," "B," "C," and "D," for purposes of this Work Package, and they shall have this designation marked distinctively on the outside of their Anti-C's for monitoring purposes.
- 5.3 Work specified by this Work Package is under the direction of the Decontamination Operations Supervisor located in the Command Center. If work cannot proceed in accordance with the Work Package instructions, personnel should request further direction from the Command Center.
- 5.4 In order to reduce exposure, personnel within the containment shall remain in the lowest radiation fields practicable and consistent with performance of the work. These areas will be identified during training and may be marked with signs within the Containment Building.
- 5.5 The sequence of work presented in this document is the preferred sequence. Only the Decontamination Operations Supervisor may direct that the work proceed in alternate sequences.
- 5.6 Specific equipment will be sealed in poly bags prior to staging. The purpose is to maintain this equipment in a non-contaminated state until use. Routine opening of poly bags within the containment can be accomplished using large hand shears. Caution should be taken not to cut Anti-C clothing or the contents of the bag. If a bagged item of equipment is not used during performance of this Work Package, it will be removed to the Anteroom. Poly bags from which equipment has been removed shall be disposed of in the appropriate waste bag.

- 5.7 Operations specified by this Work Package shall be videotaped to the maximum extent practicable using hand held and/or existing, installed TV cameras.
- 5.8 For the purpose of evaluation and documentation of the effectiveness of each technique, the following data will be recorded in the Command Center during the task operations on Data Sheets 3-H or 3-P (Attachment 3.7) as applicable.
- o Time task initiated and concluded.
 - o Time elapsed for operations on each equipment item or area.
 - o Flow meter readings in order to determine approximate volume of water used for each technique on this designated equipment item or area.
 - o Efficiency of application method including number of personnel used; support services; access; safety hazard and effectiveness of equipment used (redundance, ease of moving from tops to side, etc.)
- 5.9 Collection of pre-test data on the polar crane and 347'6" elevation shall have been completed per Section 6.2 of this Work Package before proceeding with Section 6.3.
- 5.10 Workers will follow safety procedures as outlined in reference 2.7.
- 5.11 Verbal notification shall be given to Command Center before initiating decon of each work area.

5.12 Those items marked "Reserved" are steps which are not currently planned as a normal part of the operation. These steps may be selected for completion by the Decontamination Operations Supervisor prior to the planned entry provided the workers have been trained in the specific operation.

5.13 Instructions within individual steps which are bracketed, (), are "Reserved" in the same manner as indicated for steps in Item 5.13 above.

6.0 WORK INSTRUCTIONS

6.1 Access to Work Station (Typical)

6.1.1 Enter the anteroom and check the availability of equipment required for this Work Package.

6.1.2 When directed open the airlock door.

6.1.3 Transfer staged equipment to the airlock.
Enter the airlock.

6.1.4 Close the outer airlock door.

6.1.5 Open inner airlock door.

6.1.6 Transfer equipment out of airlock and stage equipment.

6.1.7 If staged equipment remains in the anteroom, return to airlock and repeat the loading sequence.

6.1.8 Close the inner airlock door.

6.1.9 Transfer equipment to elevation 347' by use of spider lift, "gooseneck hoist" or, if unavailable, by carrying up open stairwell.

6.1.10 Stage equipment for use on elevation 347' or polar crane as applicable. Any equipment to be

lifted from 347' elevation to the polar crane should be staged adjacent to the pick up point for the "gooseneck" hoist or spider lift.

- 6.1.11 If basic equipment and hoses have not been previously staged on/to the polar crane, perform applicable sections of reference 2.3 at this time with three team members in lieu of going to the polar crane. Team member "D" will remain on elevation 347' until all hoses are properly staged and operational.

6.2 Pre-Misting Data Acquisition

- 6.2.1 Take airborne samples per Attachment 3.6 at the locations identified on Figures 3-C and 3-H (Attachment 3.8). Initial Data Collection Sheet 3.7.1 upon completion at each point. Report completion to the Command Center.

NOTES FOR MISTING & FLUSHING OPERATIONS

1. Hose tender should assist squeegee operator whenever possible. In addition, the squeegee operator should assist the hose tender when necessary.
2. Prior to initiating work in each area, ensure that sufficient slack hose is available. Additional hose may be added as required per Reference 2.3.

CAUTIONS FOR MISTING AND FLUSHING OPERATIONS

1. Prior to use, the lance operator will inspect the connection of the lance with the water hose per Technique Sheet (Attachment 3.9) to verify a positive connection. A non-positive connection could result in a personnel injury upon pressurization.
2. Care should be taken to ensure that hose does not bind or rub against any sharp or cornered objects. This is the hose tender's responsibility, and he should move the hose as required.
3. Personnel should avoid getting wet to the maximum extent practicable. This may best be accomplished by staying behind the lance operator.
4. Depressurize hose and lance during any climbing operations. In addition, the lance should never be pointed at personnel. Inadvertent operation of the pressurized lance could result in personnel injury.
5. Insure that TMI #2 plant operations has identified energized circuits and that non-energized circuits have been tagged out. Energized circuits equipment can represent an electrical hazard to misting/flushing personnel and direct misting/flushing on these should be avoided.

6.3 Test Operations (Misting)

- 6.3.1 Connect the high pressure spray wand to the supply hose if not previously accomplished. Insure that a 0° nozzle is installed on wand (Nozzle #20).
- 6.3.2 Notify the Command Center, "Ready to Mist."
- 6.3.3 Command Center will notify pump operator, "Supply Water for Misting of the Polar Crane."
Pump operator will notify Command Center, "Pressure _____ psig, Temperature _____ °F, Flow Rate _____."
- 6.3.4 Command Center will notify the Entry Team, "Commence Misting."
- 6.3.5 Mist all accessible surfaces of Area I PC/L The (dome area around the crane and the) crane rails should also be misted.
- 6.3.6 Upon completion notify Command Center, "area I PC/L Misting Complete."
- 6.3.7 Command Center will notify the pump operator, "Secure the pump."
- 6.3.8 The pump operator will notify the Command Center, "Pump is secured." Command Center will notify the Entry Team, "Pump secured."
- 6.3.9 Pressure should be released at the spray wand.
Do not disconnect the wand from the supply hose.

6.4 Test Operations (LP Flush)

6.4.1 Release pressure at the spray wand and disconnect the nozzle to be *used* for low pressure flush (if applicable).

6.4.2 Notify the Command Center, "Ready to flush Area I PC."

6.4.3 Command Center will notify pump operator, "Supply Ambient temperature water for low pressure flushing of the polar crane."

Pump operator will notify Command Center, "Pressure _____ psi, Temperature _____ °F, Flow Rate _____."

6.4.4 Command Center will notify the entry team, "Commence flushing of Area I PC."

6.4.5 Flush all accessible surfaces of the polar crane in Area I PCL (Figure 3-A, Attachment 3.8). (This should be sequenced first by flushing the dome area over the polar crane). The crossbeam and girder "B" should be flushed. Girder "A" and walkway should then be flushed. At completion repeat steps 6.3.6 through 6.3.9.

6.4.6 Squeegee the crane surfaces where practicable.

6.4.7 Repeat Step 6.2.1.

6.4.8 Repeat steps 6.3.1 through 6.4.6 for Area II PCL (Figure 3-A, Attachment 3.8) except using water at 140°F for flushing. (The dome area should be flushed first. Special attention should be given to flushing of the area above the LOCA duct opening and the south dome area.) Next flush the polar crane trolley, girder "A", walkway, crossbeam girder "B," crane rails and last the polar crane cab. At completion repeat steps 6.3.6 through 6.3.9.

6.4.9 Repeat step 6.2.1.

6.4.10 Disconnect equipment and stage for lowering to the top of the D-Rings.

6.5 Post Flushing Data Acquisition

6.5.1 Perform a general area beta and gamma survey per Attachment 3.6 at 1 meter from the floor at the locations identified on Data Collection Sheet 3.7.2 (Attachment 3.7).

6.5.2 After surfaces have dried, perform a contact gamma, beta, and swipe survey per Attachment 3.6 at the locations specified on Data Collection 3.7.2 (Attachment 3.7). The survey includes points on the polar crane, D-Ring area, 347'6" floor elevation, and refueling canal areas.

(6.5.3 Take teletector measurements of the dome area. This measurement will be taken by placing the teletector above the points marked in Figure 3-C (Attachment 3.8) at 1 meter from the marked surface. The teletector probe should extend perpendicular to the polar crane. These measurements should be recorded on Data Collection Sheet 3.7.7 (Attachment 3.7).)

6.5.4 Take photographs of the polar crane locations and in directions specified on Figure 3-F. (Attachment 3.8).

6.6 Exit from Work Station

6.6.1 Lower equipment and hoses from the polar crane to the top of the D-rings using the "gooseneck" hoist or the spider lift.

6.6.2 Exit from the polar crane.

6.6.3 Proceed from elevation 347' to elevation 305' via the open stairwell (#1). Proceed to vicinity of personnel airlock.

6.6.4 Upon concurrence from the Command Center, equalize pressure between Containment Building and airlock, and unlatch and open inner airlock door. (See Reference 2.1 for details on airlock operation).

6.6.5 One team member should enter the airlock (while shedding one pair of booties). Team members should transfer items into airlock as they are bagged by team member in airlock.

- 6.6.6 After items are transferred into airlock, other team members should enter airlock (while sheeding one pair of booties each).
- 6.6.7 Close inner airlock door and equalize pressure between airlock and anteroom.
- 6.6.8 Unlatch and open outer airlock door.
- 6.6.9 Exit airlock and undress per instruction of anteroom attendants. Equipment in airlock will be removed by anteroom attendants after work crew is processed.
- 6.6.10 After having been processed by Radiological Control personnel and taking a shower, report to the Decon Operations Supervisor for de-briefing. De-briefing will be conducted per Attachment 3.4.

ATTACHMENT 3.1: EQUIPMENT LIST

QUANTITY	ITEM	INITIAL	
		STAGED	TO AIRLOCK
1	Hydrolance w/long lance adapted for LP misting (15°, 10 gpm nozzle)		
1	Squeegee		
3	High pressure hose seg- ments - 50 ft. w/quick disconnect couplings		
2	High pressure hose seg- ments - 50 ft. w/ quick disconnect couplings, adapted for suspension from polar crane		
3	Underwater high intensity Lamps - portable		
2	RO-2A		
50	Rad swipes and 8" X 9" poly bags		
2	Templates		
2	Air sampler units		
2	Swipe holders		
4	Felt tip marking pens		
50	Petri dishes, plastic millipore, 47 mm		
1	Meter stick		
1	Teletector		

ATTACHMENT D-2
TECHNIQUE SHEETS

TECHNIQUE SHEET

1.0 FLUSH TEAM OPERATION

A flush team consists of three personnel, a liquid blaster lance operator, a hose tender, and squeegee operator. To maintain all personnel in good physical condition for continued flush operation, the team members will rotate among the three position at about 15 minute intervals or as directed by Command Center.

1.1 Blaster Operator - Team Leader, operates the blaster lance of the spin-jet and is responsible for assuring safe operation of the liquid blaster or spin-jet. He is responsible that other team members are alerted prior to pressurizing the system and are in a safe locations prior to depressing the operating handle, activating the system.

1.2 Hose Tender - Provides assistance to the Blaster Operator. Prevents hose from snagging on obstructions and keeps hose clear of areas being cleaned. Positions himself directly behind the Blaster Operator at a safe distance (10-20 feet) and maintains slack for smooth lance operations. Assists with squeegee operation during spin-jet operations.

1.3 Squeegee Operator - Positions himself behind and to one side of the Blaster Operator. Directs floor run-off with his squeegee to floor drains. Prevents run-off from recontaminating areas already flushed. May be positioned in alternate locations by procedure or by instruction from the Command Center.

2.0 GENERAL INSTRUCTIONS

To begin liquid blasting the following guidelines should be followed:

2.1 All equipment is staged and nozzle is installed on lance with nozzle fan angle properly set.

2.2 Visually inspect all lines and connections.

2.3 Place the blaster shoulder piece firmly against right shoulder.

2.4 Grasp side handle firmly with left hand.

- 2.5 Establish a firm footing with one foot in front of the other by several inches to absorb the backwards force of the lance.
- 2.6 Open safety valve on the side of the lance.
- 2.7 Point the nozzle toward the starting point of the area to be cleaned.
- 2.8 Notify Command Center to pressurize the lance. (Be prepared for a sudden Jerk upon pressurization).
- 2.9 Disengage the safety latch.
- 2.10 Begin blasting by fully depressing the operating handle. (Maintain operating handle in full operating position of in full off position).
- 2.11 Whenever possible, flush from low dose areas. Avoid walking within 5 feet of floor drains.

3.0 SAFETY

- 3.1 Hoses are rated at 30,000 psi.
- 3.2 Operating pressure shall not exceed 10,000 psi.
- 3.3 All personnel will wear safety equipment as designated, this will normally include anti-contamination clothing, full face respirators, rain suits, shin guards, hard-hats, and ear protection.
- 3.4 The blaster lance system shall never be left unattended when pressurized.
- 3.5 Only trained personnel will be permitted to operate the Liquid Blaster or Spin-Jet.
- 3.6 Equipment safety features will be maintained in an operable condition.
- 3.7 The system must be depressurized and isolation valve closed on lance prior to performing any maintenance and prior to changing nozzles.
- 3.8 The Blaster Lance Operator will avoid direct flushing or blasting of area identified for equipment protection between yellow arrows taped on walls or covered with yellow herculite.

4.0 LIQUID BLAST MISTING

- 4.1 The misting nozzle (0020) is installed in lance note! While misting the squeegee operator will remain in low dose area.
- 4.2 The Liquid Blast Lance Operator will spray all overheads, walls and floor within flushing area.
- 4.3 At end of misting the Liquid Blast Lance Operator will notify the Command Center to shut down the pump. As the hose tender and Lance Operator move back to the starting point the lance operator will depressurize system close safety valve on lance and install the flushing nozzle.

5.0 LIQUID BLASTING OPERATION ON HORIZONTAL SURFACES

5.1 Low Pressure Flushing

NOTE: Misting will be performed prior to all flushing operations.

(Refer to Section 4.0).

- 5.1.1 The liquid blaster nozzle is held at least 2 feet away from the surface to be flushed and as far away from the surface to be flushed as the effective range of the flush stream.
- 5.1.2 The blaster lance should be held at no more than a 30° angle from the floor surface.
- 5.1.3 Flushing is accomplished with a side to side motion maintain flushing such that runoff flow back toward the operator is minimized.

5.2 High Pressure Liquid Blasting Of Horizontal Areas.

- 5.2.1 The nozzle or blaster discharge is held approximately six to ten inches above the surface being cleaned.
- 5.2.2 The blaster lance is held at an angle to the surface between 30° and 60° (Typically 45°).
- 5.2.3 The blaster is moved from side to side covering a path approximately 4 feet wide. Each pass will overlap the previous pass in order to assure full coverage of the surface being cleaned.

5.2.4 The fan nozzle is installed in the Blaster Lance such that the fan is parallel to the operating handle and perpendicular to the side to side motion of the lance.

5.2.5 The operator performs the side to side motion while moving slowly forward approximately 8 feet. The operator then backs up to a new starting point parallel to his previous path and begins liquid blasting a second path that will overlap his previous path on one side.

NOTE: When approaching a drain, stop blasting the floor approximately 5 feet from the drain. Place the nozzle 6" from the drain cover and blast into drain slots from two directions in order to minimize dose. Blasting should NOT be towards support personnel.

NOTE: While blasting areas with insulation, such as cable insulation that could be damaged, that could be damaged, the lance operator should blast at a minimum distance of approximately 2 feet in order to reduce the force applied on such materials.

6.0 LIQUID BLASTER OPERATION ON VERTICAL SURFACES

6.1 Low Pressure Flushing

6.1.1 The nozzle or blaster discharge is held at least 2 feet from surface to be flushed and as far away from the surface to be flushed the effective range of the flush stream.

6.1.2 The lance operator will angle the blast stream in such a way as to direct the water deflected from the surface being flushed toward areas not yet flushed. This will minimize recontamination and flushed surfaces.

6.1.3 Flushing is accomplished with a up and down sweeping motion.

6.1.4 Particular care should be employed while flushing corners. Water should not be impacted directly into corners.

6.2 High Pressure Liquid Blasting

6.2.1 The lance operator will angle the blast stream in such a way as to direct the water deflected from the surface being flushed toward areas not yet flushed. This will minimize recontamination of flushed surfaces.

6.2.2 Fan tip will be installed or positioned parallel to floor.

6.2.3 The operator moves the blasting lance in a vertical motions with the nozzle remaining 6 - 10 inches from the surface. In one continuous motion the operator should cover an area beginning at the top and blasting down to the bottom of the vertical surface.

6.2.4 Corners will be blasted side to side and from top to bottom. This Technique requires rinsing areas of the vertical surfaces already completed which may have become recontaminated due to splatter from blasting the corner. Rinse by backing up to the last area completed and blading with the nozzle at least 2 feet away from the vertical surface.

7.0 HIGH PRESSURE LIQUID BLASTING OF STAIRWELLS.

7.1 The starting point is at top level of the stairwell and initiates with misting operations.

7.2 Blast the entry to the stairwell with a fan tip nozzle.

7.3 At the platform of the stairwell, blast from the furthest point from the stairs toward the downward stairs. Blast surfaces beginning with the walls, (from top to bottom) then the railings and then the platform over to first descending step.

- 7.4 The runoff is directed by the operator across the platform and down the stairwell using the lance.
- 7.5 Begin blasting the descending stairs.
- 7.6 Order of Stairwell Liquid Blasting
- 7.6.1 Blast overheads, then walls (From top to bottom) and the railings.
- 7.6.2 Blast stair streads, descending steps are sequentially blasted.
- 7.6.3 After stepping down on third completed step repeat the steps for blasting of overheads, walls, railings, and steps for next step areas (7.6.1 and 7.6.2).
- 7.6.4 This process continuous until next lower platcorm is reached. Then at section 7.3 to repeat blasting of overheads, wall, railings, and steps for next flight of stairs. (7.6.1 - 7.6.4).

NOTE: Avoid direct blasting of lighting fixtures, recpeitcals and other electrical equipment.

8.0 LIQUID BLASTING OF OVERHEADS

- 8.1 Overhead Flushing will be accomplished using a 25 gpm open nozzle. This will direct a stream of water with sufficient force to reach 10 feet above the level of the overheads.
- 8.2 The lance operator moves the lance in a side to side motion at approximately 45° angle to the floor into the area being flushed.
- 8.3 Flush overheads as far forward of the operator as the effective water stream will allow.
- NOTE: Do not spray items marked for equipment protections by on either side of the area yellow herculite arrows.
- 8.4 The blaster lance operator after flushing all reachable overheads then begins flushing the walls and vertical surfaces, and then the horizontal areas including floors.
- 8.5 The lance operator will continue to flush overheads as he moves forward to next starting point.

9.0 H.P. SPIN-JET OPERATION

- 9.1 Visually check all the connections for leaks.
- 9.2 Operator moves spin-jet to starting area.
- 9.3 Starting area will be to either extreme side of floor (next to either the liner wall of D-Ring wall).
- 9.4 After notification from the command center that high pressure water is available, the operator depresses the operating handle of the spin-jet. After flow water starts, he will switch the spin jet motor on.
- 9.5 The spin - jet operator completes one pass to end of work area.
- 9.6 At end of the pass the operator will move the spin jet into position to blast an area parallel and overlapping back to the earlier pass, then completes the next pass back toward the starting point.
- 9.7 Continue overlapping passes up to the floor drain in middle of the work area.
- 9.8 The spin-jet operator then moves the spin jet into position to begin passes on the extreme opposite side of work area and proceeds (9.4-9.7) making parallel passes and continuing up to the floor drain.

10.0 LIQUID BLASTING SUPPORT PERSONNEL

- 10.1 The hose tender is positioned behind the operator at a safe distance, and will assist the operator by maintaining a sufficient slack in the hose in order to assure blaster operator mobility.
 - 10.1.1 Prevent the hose from rubbing against sharp corners.
 - 10.1.2 Keep the hose from impeding water runoff into drains.
 - 10.1.3 Inspect the hose and connections for leaks.
- 10.2 The squeegee operator is positioned behind and to the side of the operator with a squeegee in order to push water runoff towards floor drains.
 - 10.2.1 Keep the water runoff from recontaminating previous by completed areas.
 - 10.2.2 Assist the hose tender.

ATTACHMENT D-3
GENERAL ENTRY TRAINING

GENERAL ENTRY TRAINING

SECTION

1. Organization Chart and Telephone Numbers
2. Entry Team Requirements and Training
3. Reactor Building Exit Criteria
4. Conditions Inside the Reactor Building w/Elevation Maps
5. Personnel Airlock Drawings and Operation Description
6. Equipment
7. RWP Requirements/Minimum Protective Clothing and Dosimetry/
Whole Body Count/Bioassay Requirements
8. Dress Out Procedure/Checklists
9. Communication with Command Center
10. Contamination Control/RIR Lessons/Skin Contaminations
11. Undress Procedure
12. Ante-Room Layout/Support Personnel/Conditions
13. Safety Work Practices (Heat Stress Exposure/Confined Spaces)
14. Casualty Procedure for High Radiation In Containment
15. Casualty Procedure for Fire In Containment
16. Casualty Procedure for Personnel Injury or Sickness In
Containment
17. Fire Protection
18. Debriefing
19. Typical Entry Day Summary
20. Typical Entry Day Schedule

2.0 ENTRY REQUIREMENTS

Current RWP Training

Current Whole Body Count

Current Respirator Physical

Current MSA Fit Test - if the MSA purifier is used, otherwise current Scott fit is acceptable. (Glasses must be obtained if required)

MSA Purifier Training - only if MSA purifier is used, one time qualification; may be completed during week of training.

Reactor Building Training includes:

1. General Entry Training or GET refresher, as applicable.
2. Work Package Training
3. Airlock door training
4. Walkthru (may be omitted in some cases)
5. Final mockup (may be full dress/partial dress or heat stress test)

NOTE: Entry team members must sign training sheet for each phase of training.

Personal Requirements/Suggestions:

- a. Protection of valuables - each person is responsible for his own valuables.
- b. Tennis shoes - it is suggested that you wear an old pair of tennis shoes during your entry to prevent possible loss of good shoes via contamination.
- c. Change of under clothes, towel, soap, shampoo and comb - for use after your mock-up or entry.
- d. Bring this outline to training and mockup sessions for your use and notes.

3.0 REACTOR BUILDING EXIT CRITERIA

- A. Sickness and/or fatigue - affected individual to be escorted to the airlock as quickly as possible. All team members do not have to exit unless individual who is exiting cannot be readily replaced and is required to perform team tasks.

All team members are responsible for informing the Command Center of any feeling of sickness or heat stress. In addition, team members are responsible for monitoring the well being of other entry personnel and informing the Command Center of suspected illness or fatigue.
USE THE BUDDY SYSTEM WHILE IN THE CONTAINMENT!

- B. Dose Pull Point - as specified by the daily entry schedule. Each individual is responsible for monitoring the dosimeter and exiting at the specified pull point.
- C. Communication - Total loss of communication with team. If team member can hear the Command Center and make himself understood via CCTV, activities may continue. If team members try to contact the Command Center and do not get any response, they should stay in sight of a CCTV camera as much as possible, pick up their equipment and exit the Reactor Building.
- D. Radiation Detection Gear - loss of radiation dose rate instrumentation to the degree that personnel dose rate levels cannot be determined. Each team member will have a digital dosimeter and a pencil dosimeter with which to monitor his dose. In the event of failure of the digital dosimeter: 1) read pencil dosimeter; 2) call Command Center; 3) ask if exit is required.
- E. Respirator - failure of respirator to perform properly. Removal of the respirator while in the reactor building is acceptable in case of failure of the unit or sickness.
- F. As ordered by the Command Center.
- G. Failure of building lighting.
- H. Use of Ice Vests - ice vests will be used for tasks involving extreme physical exertion or of long duration. In order to avoid over stressing individuals involved in these types of tasks, a 60 minute time limit has been set from the time the individual notifies the Command Center that all the ice in his vest has melted until the time he exits from the Reactor Building.

For all exits, the prime criterion is the safety of the individuals. All other team members do not have to exit if they are in sight of another entry team member and/or a CCTV camera so that the Command Center can be made aware of their locations.

If an emergency arises, notify the Command Center and wait for instructions.

4.0 CONDITIONS INSIDE THE REACTOR BUILDING

<u>Radiation Dose Rates</u>	60 mRem/hr	- 28 Rem/hr
	100 mRad/hr	- 200 Rad/hr

Refer to dose rate maps (Make special note of dose rates and hot spots in your work area).

Typical hot spots include but are not limited to:

Elevation 305'

Enclosed Stairwell and elevator
Open Stairwell
Holes in Floor
Drains
Air Coolers
Hatches

ELEVATION 347'

Incore Instrumentation Table

Highlight low dose areas and highlight high dose or exclusion areas on maps.

Stay times for entry team members varies from 30 minutes to 3.5 hours.

Airborne Activity (After Purge)

<u>TYPE</u>		<u>AVERAGE CONCENTRATION</u>	<u>MPC</u>
Particulate	Cs ¹³⁷	4.7E-8	1 E-8
	Cs ¹³⁴	3.7E-9	1 E-8
	Sr ⁹⁰	1.4E-10	1 E-9
Inert Gas	K ⁸⁵	Less than 1E-6	1 E-5
Tritium	H ³	1.4E-8 - 6.3 E-6	5 E-6

MPC = ^{MINIMUM}~~Maximum~~ permissible concentration per 10 CFR 20

If isotope being measured is not yet known, 1 E-9 is MPC (assumed to be most restrictive, i.e. Strontium 90) and appropriate respiratory protection should be worn.

Purge remains on during the reactor building entry under most conditions.

Respirator must be working in reactor building and in anteroom in accordance with RWP. Respirator may be removed from exiting entry personnel during approved undress sequence even if air is greater than MPC.

Protection Factor

- MSA Purifier 1000
- Particulate Mask 50
- For tritium, any device other than self contained air = 1.0

Loose Surface Contamination

Levels vary from 10^5 dpm/100 cm² to 7.5×10^6 dpm/100 cm²

Noise

Noise level on E1. 305' is substantial (approximately 85-90 db) due to air coolers. Noise level on E1. 347' is relatively low in comparison.

Lighting

An area of poor lighting exists on E1. 305' northeast quadrant by CFT "A" (see page 6).

Step-Off Pads

1. Prior to entering airlock from reactor building, place boots and any extra external gloves in trash drum near ramp.
2. Prior to entering ante room from airlock; place 1 pair of boots in bag in airlock.
3. After exiting the ante room - final pair of boots and gloves at control point.

General Arrangements and Equipment Locations

(See Attached Maps)

PHOTOGRAPHS

See previous entry photographs (Make special note of photographs of your work area). Photographs are kept in Trailer 105 Room and may be reviewed upon request.

Camera Locations

(See Attached Maps)

Enclosed Stairwell Lighting

The lights in the enclosed stairwell are temporary lights which have been strung down from E1. 347' between the handrails. The on/off switch is tie-wrapped to the handrail in the center of the stairs. Since access to E1. 347' is via the open stairwell and access to the elevator machinery room or polar crane ladder is via the enclosed stairwell, these lights have been left on and should NOT be turned on/off unless ordered by Command Center.

(NOTE: Area at E1. 305' inside enclosed stairwell is 28 r/hr gamma).

This area is now roped off to traffic between E1. 305' and E1. 347'. The light bulbs are burnt out and will not be replaced until dose rates can be reduced in this area.

5.0 AIRLOCK

To be operated by operations department and other authorized (trained) personnel only.

Both doors are locked when not in use.

Unlocking of inner door requires stationing of security at both exits.

Inner and outer doors are interlocked to prevent the opening of both doors at once.

Interlock may be defeated by mechanical means in airlock (see figure).

Doors swing (1) into airlock and (2) into reactor building.

Do not allow door to swing open by itself; hold it as it opens to avoid "banging".

Be careful not to step or bump the airlock door seal surface.

When closing doors, make sure handwheel is turned to stop in "open" direction.

Always wipe door seal down with "spot check" prior to last closing operation.

Door Operation. (per 2104.-4.55)

To open:

1. rotate handwheel 3/4 turn to crack open equalizing valve; handwheel directions are specified above the handwheel.
2. allow pressure to equalize; note differential pressure by placing hand near air outlet pipe above handwheel.
3. rotate handwheel a second 3/4 turn until the mechanical stop is felt*
4. hold door and push open slowly until it is completely open.

To close:

1. swing door to near closed
2. insure door latch rollers are fully retracted; do so by turning handwheel in open direction until mechanical stop is felt
3. close door and turn handwheel in shut direction until mechanical stop is felt.

*NOTE: Inner Door requires more rotations of handwheel to open/close door.

REACTOR BUILDING AIRLOCK INTERLOCK OPERATION

Restoring Airlock.

1. Obtain seal to seal interlock cabinet.
2. Enter airlock per section 5.5
3. Insure both doors are closed.

NOTE: Reference Figures 1 and 2 for detailed drawing of interlock system.

4. Remove clamp knob (#48) and open cover (#52).
5. Press down on camyoke (#49) until it is parallel with shaft as in Figure 1 and interlock disks are together.
6. Close cover (#52) screw in clamp knob (#48) and apply seal.
7. Notify Shift Foreman that interlock is in force and seal is applied.

Violating the interlock system.

1. Obtain Shift Supervisor/Foreman approval prior to violating interlock.

Enter airlock per section 5.5:

NOTE: See Figures 1 and 2 for detailed drawing of interlock system.

2. Break seal and remove clamp knob (#48).
3. Open hinged cover (#52) and remove tape from camyoke, if present. Pull or push on camyoke (#49) until yoke is perpendicular to the shaft. Upper interlocking disk (#50) should slide toward camyoke violating interlock as in Figure 2.
4. Close cover and start clamp knob (#48) into hole. Do not turn in fully and do not apply seal.
5. Notify Shift Supervisor/Foreman that interlock is violated.

6.0 EQUIPMENT

CAG Equipment

Radio/Microphone/Earphones*
Small Lights
Spotlights
Digital dosimeters
Cameras*
Data Sheets/Clipboards/Maps/etc.

HP FOREMAN

RO-2A*
E-530*
RO-7*
Teletector*
Dosimeters
BZA personal air sampler

RAD ENGINEERING

TLD's and dosimetry placement

EQUIPMENT FOR ENTRY TASKS

Tools	Rope
Meters	Ramps
Buckets	Carts
Well Wheels	Ladders
	Grease Guns

Others as needed

SPECIALIZED EQUIPMENT*

Safety Equipment
High Reach Scissors Lift
Raymond Forklift
Spider Lift Platform
Tugger)
Chainfall) On Lifting Rig

*Special training required prior to use.

7.0 Minimum RWP Requirements

1. Two sets of cloth PC's with corresponding number of gloves and hooties. Wet suits or other additional protective clothing determined by team member activities.
2. Rubber boots/personal shoes.
3. Battery powered MSA Air Purifier Masks, Air Hoods, or Particulate Face Mask. (MSA Air Purifier unless otherwise specified).
4. TLD's - See following sheets.
5. Self-Reading Dosimetry - each man will carry one pencil dosimeter outside the PC's and two pencil dosimeters inside the PC's. Digital dosimeters will also be utilized by all entry personnel.

It is very important that you know the scale and millirem/division of the pencil dosimeters that you are assigned as you may be asked to give the Command Center a reading from your wrist dosimeter while in the Reactor Building (See attached page).

Protective Clothing Dress Out Sequence
(With Ice Vest)

1. Underwear and socks
2. TLD's: Finger rings and wrist TLD's (if required), facing palm side of hand.
3. Personal shoes
4. Ankle TLD's (if required)
5. One pair plastic booties over personal shoes - taped around ankles loosely
6. One pair cloth PC's with chest and thigh TLD attached - taped over first booties, pulled up to waist only.
7. Second pair of plastic booties taped to first PC's.
9. Two self-readers (low range and high range) taped to chest area on first PC's.
10. One pair cotton gloves.
11. Rubber boots, fastened, and taped to outer PC's.
12. Four sets of non-skid booties; cut through elastic at top.
13. When instructed, put on ice vest and pull up PC's; tape zipper on outer pair.
14. Second pair neoprene gloves taped over first PC's.
15. Second cloth coverall taped to second bootie.
16. Pair of yellow gloves taped to outer PC's.
17. Additional protective clothing (if required), i.e., wet suits, wet suit bottoms, aprons, etc.
18. Respirator belt with battery/blower pack (radio & digital pouches, if required).
19. Digital dosimeter in pouch on hip and one self-reader (high range) attached to either arm.
20. Skull cap.
21. Mask; turn on MSA (if powered respirator is used).
22. Radio equipment (if required); mike and earphone, (Tape wires to PC's - do not wrap around belt. Ensure freedom of movement of head without pulling on earphone).

8.0 (Continued)

Protective Clothing Dress Out
Sequence (With Ice Vest)

23. Attach TLD inside first hood (if required).
24. First cloth hood.
25. Second cloth hood - taped to outer PC's.
26. Attach small light (if required).
27. BZA sampler attached to belt in back; do not turn on until just prior to actual entry.
28. Check and adjust equipment:
 1. Test radio with Command Center; volume should be "higher than normal" if working on El. 305'
 2. If picking up digital dosimeter in ante-room, be sure to test by pushing "read" button; red light should light-up for at least two seconds.

10.0 Contamination Control/RIR Lessons Learned

1. Observe all step-off pads.
2. Wear extra yellow boots in case you need to enter the airlock more times than anticipated. (Four pairs are required by dress-out procedure).
3. Be conscious of your own protective clothing; be alert for suit becoming wet and for rips in gloves or wet suits; be careful to avoid coming in contact with contaminated surfaces with your body.
4. Bag all contaminated items immediately after use or removal. Rebag items again when entering airlock and ante-room.
5. Be careful to avoid putting yourself into any unusual positions by climbing on or over anything, pulling cable, or kneeling down on the floor unless it has been identified as part of your task and your clothing requirements have been adjusted to protect you.
6. Allow the ante-room support personnel to undress you without helping them outside of their instructions to you. This will help to keep your gloves clean and intact.
7. While undressing in the ante-room or frisking out, be careful to avoid touching yourself or anything which may be contaminated on bare skin. This includes the hose of your purifier and the ante-room door.

Note: If skin contamination is discovered while frisking out, a Skin Contamination Record (4170) must be completed by the HP who will assist in decontaminating you, followed by a whole body count. In addition, a critique is normally called by Radiological Engineering (ALARA) and a Radiological Investigative Report (RIR) is written to summarize lessons learned and corrective actions. Inform Command Center if you become contaminated.
8. Wear extra yellow gloves or take several pairs with you when you enter the Reactor Building so that if your gloves rip or become very dirty you can pull on or peel off a pair as needed. Extra gloves are needed when climbing to the polar crane. Work gloves are required if job requires heavy physical work.
9. Be aware of what the anteroom personnel are doing and make sure they change their gloves periodically to prevent any contaminations. Refer questions to the Ante Room HP Tech.
10. Laundered protective clothing previously used in Radiologically controlled areas is not to be used for training. For this purpose, only new PC's and specifically designated boots, respirators, etc. may be used for mockups outside RWP areas.

SAFETY WORK PRACTICES
A. HEAT STRESS EXPOSURE

These requirements establish work time guidelines for workers exposed to hot environments before a rest period is given for recovery from heat stress.

Work time guidelines reflect the actual time protective clothing and/or respiratory protection are worn while performing work assignments and does not include suiting up, unsuiting or going to and/or from the work location. Breaks should follow exposure to heat stress. Duration of breaks, extent of clothing removal, and the area where breaks are taken, shall be at the discretion of supervisory personnel.

The following definitions apply:

Anti-C's	Paper or cotton coveralls, cotton hood, rubber boots, and gloves.
Impermeable Clothing	Rain suits, water resistant clothing.
Respiratory Protection	Negative pressure full-facepiece respirator, SCBA or supplied-air respirator.
Supplied Air Hood or Suits	Hood or suit with at least 6 cubic feet per minute continuous air flow.
Temperature	Ambient temperatures at a relative humidity 75% at the work location.

If an extension of the work time guidelines identified herein is required, due to the nature or criticality of the task being performed, permission must be obtained from the supervisor in charge of the job.

Employee heat stress briefing, when required, should be arranged through and provided by the Site Safety and Health Department.

When work is planned in hot environments where relative humidities are known to be greater than 90%, the schedule for Anti-C's under Impermeable Clothing with Respiratory Protection shall be utilized.

When temperatures exceed 120°F or where hot radiant heat surfaces are encountered, direction shall be provided by the Supervisor - Safety and Health for personal protective equipment.

When an individual feels discomfort from heat stress, he/she must immediately notify the person in charge and leave the area.

Heat Stress Exposure

HEAT STRESS - TEMPERATURE AND PERMISSABLE LIMITS

<u>Protective Equipment</u>	<u>Temperature</u>	<u>Guidelines For Work Time</u>
<u>Conventional Work Clothing</u>	Less than 100°F 100 - 100°F 110 - 120°F	None 2 Hrs. 45 Min.
<u>Anti-C's (Only)</u>	80 - 90°F 90 - 100°F 100 - 110°F 110 - 120°F	3 Hrs. 2 Hrs. 1 Hr. 30 Min.
<u>Anti-C's Under Impermeable Clothing</u>	80 - 90°F 90 - 100°F 100 - 110°F 110 - 120°F	1.5 Hrs. 1 Hr. 30 Min. 15 Min.
<u>Anti-C's (Only) With Respiratory Protection</u>	Less than 80°F 80 - 90°F 90 - 100°F 100 - 110°F 110 - 120°F	4 Hrs. 2 Hrs. 1.5 Hrs. 1 Hr. 30 Min.
<u>Anti-C's Under Impermeable Clothing With Respiratory Protection</u>	70 - 80°F 80 - 90°F 90 - 100°F 100 - 120°F	1 Hr. 45 Min. 30 Min. 15 Min.
<u>Anti-C's With or Under Supplied Air Hood/Suit</u>	80 - 100°F 100 - 110°F 110 - 120°F	4 Hrs. 2 Hrs. 1 Hr.

By: _____

R. G. Ritthamel 12-1-81
R. G. Ritthamel
Manager - Industrial Safety
and Health

GENERAL ENTRY TRAINING

<u>SECTION</u>	<u>PAGE</u>
1. Organization Chart and Telephone Numbers	2
2. Entry Team Requirements and Training	3
3. Reactor Building Exit Criteria	4
4. Conditions Inside the Reactor Building w/Elevation Maps	5
5. Personnel Airlock Drawings and Operation Description	10
6. Equipment	17
7. RWP Requirements/Minimum Protective Clothing and Dosimetry/ Whole Body Count/Bioassay Requirements	20
8. Dress Out Procedure/Checklists	24
9. Communication with Command Center	29
10. Contamination Control/RIR Lessons/Skin Contaminations	30
11. Undress Procedure	31
12. Ante-Room Layout/Support Personnel/Conditions	32
13. Safety Work Practices (Heat Stress Exposure/Confined Spaces)	34
14. Casualty Procedure for High Radiation In Containment	44
15. Casualty Procedure for Fire In Containment	47
16. Casualty Procedure for Personnel Injury or Sickness In Containment	55
17. Fire Protection	59
18. Debriefing	62
19. Typical Entry Day Summary	63
20. Typical Entry Day Schedule	64

1. ORGANIZATION CHART

PHONE #'s

Bechtel: CAC Supervisor - Paul Bengel x8834
Vince Gilbert x4092
Dan Machiela x8603

First Aid (Physicals/Respirator Classes -
by appointment - x8450)
Rad Services (Respirator Fit Test - Trl. 157
Mon. or Wed. 9:00 - 12:00 - x8532)

D-A3-16

2.0 ENTRY REQUIREMENTS

Current RWP Training

Current Whole Body Count

Current Respirator Physical

Current MSA Fit Test - if the MSA purifier is used, otherwise current Scott fit is acceptable. (Glasses must be obtained if required)

MSA Purifier Training - only if MSA purifier is used, one time qualification; may be completed during week of training.

Reactor Building Training includes:

1. General Entry Training or GET refresher, as applicable.
2. Work Package Training
3. Airlock door training
4. Walkthru (may be omitted in some cases)
5. Final mockup (may be full dress/partial dress or heat stress test)

NOTE: Entry team members must sign training sheet for each phase of training.

Personal Requirements/Suggestions:

- a. Protection of valuables - each person is responsible for his own valuables.
- b. Tennis shoes - it is suggested that you wear an old pair of tennis shoes during your entry to prevent possible loss of good shoes via contamination.
- c. Change of under clothes, towel, soap, shampoo and comb - for use after your mock-up or entry.
- d. Bring this outline to training and mockup sessions for your use and notes.

3.0 REACTOR BUILDING EXIT CRITERIA

- A. Sickness and/or fatigue - affected individual to be escorted to the airlock as quickly as possible. All team members do not have to exit unless individual who is exiting cannot be readily replaced and is required to perform team tasks.
All team members are responsible for informing the Command Center of any feeling of sickness or heat stress. In addition, team members are responsible for monitoring the well being of other entry personnel and informing the Command Center of suspected illness or fatigue. USE THE BUDDY SYSTEM WHILE IN THE CONTAINMENT! You must be escorted out by another team member if you exit under this criteria.
- B. Dose Pull Point - as specified by the daily entry schedule. Each individual is responsible for monitoring the dosimeter and exiting at the specified pull point.
- C. Communication - Total loss of communication with team. If team member can hear the Command Center and make himself understood via CCTV, activities may continue. If team members try to contact the Command Center and do not get any response, they should stay in sight of a CCTV camera as much as possible, pick up their equipment and exit the Reactor Building.
- D. Radiation Detection Gear - loss of radiation dose rate instrumentation to the degree that personnel dose rate levels cannot be determined. Each team member will have a digital dosimeter and a pencil dosimeter with which to monitor his dose. In the event of failure of the digital dosimeter: 1) read pencil dosimeter; 2) call Command Center; 3) ask if exit is required.
- E. Respirator - failure of respirator to perform properly. Removal of the respirator while in the reactor building is acceptable in case of failure of the unit or sickness.
- F. As ordered by the Command Center.
- G. Failure of building lighting.
- H. Use of Ice Vests - ice vests will be used for tasks involving extreme physical exertion or of long duration. In order to avoid over stressing individuals involved in these types of tasks, a 60 minute time limit has been set from the time the individual notifies the Command Center that all the ice in his vest has melted until the time he exits from the Reactor Building.

For all exits, the prime criterion is the safety of the individuals. All other team members do not have to exit if they are in sight of another entry team member and/or a CCTV camera so that the Command Center can be made aware of their locations.

If an emergency arises, notify the Command Center and wait for instructions.

1.0 CONDITIONS INSIDE THE REACTOR BUILDING

<u>Radiation Dose Rates</u>	60 mRem/hr	- 28 Rem/hr
	100 mRad/hr	- 200 Rad/hr

Refer to dose rate maps (Make special note of dose rates and hot spots in your work area).

Typical hot spots include but are not limited to:

Elevation 305'

Enclosed Stairwell and elevator
Open Stairwell
Holes in Floor
Drains
Air Coolers
Hatches

ELEVATION 347'

IncCore Instrumentation Table

Highlight low dose areas and highlight high dose or exclusion areas on maps.

Stay times for entry team members varies from 30 minutes to 3.5 hours.

Airborne Activity (After Purge)

<u>TYPE</u>		<u>AVERAGE CONCENTRATION</u>	<u>MPC</u>
Particulate	Cs ¹³⁷	1.2E-8	1 E-8
	Cs ¹³⁴	1.2E-9	1 E-8
	Sr ⁹⁰	5.0E-10	1 E-9
		Less than 1E-6	1 E-9
Inert Gas	K ⁸⁵	1.2E-7	1 E-5
Tritium	H ³	↓ 1.2E-7	5 E-6

MPC = Maximum permissible concentration per 10 CFR 20

If isotope being measured is not yet known, 1 E-9 is MPC (assumed to be most restrictive, i.e. Strontium 90) and appropriate respiratory protection should be worn.

Purge remains on during the reactor building entry under most conditions.

Respirator must be working in reactor building and in C.C.C. in accordance with RWP. Respirator may be removed from exiting entry personnel during approved undress sequence even if air is greater than MPC.

Protection Factor

- MSA Purifier 1000
- Particulate Mask 50
- For tritium, any device other than self contained air = 1.0

Loose Surface Contamination

Levels vary from 10^5 dpm/100 cm² to 7.5×10^6 dpm/100 cm²

Noise

Noise level on E1. 305' is substantial (approximately 85-90 db) due to air coolers. Noise level on E1. 347' is relatively low in comparison.

Lighting

An area of poor lighting exists on E1. 305' northeast quadrant by CFT "A" (see page 6).

Step-Off Pads

1. Prior to entering airlock from reactor building, place boots and any extra external gloves in trash drum near ramp.
2. Prior to entering ante room from airlock; place 1 pair of boots in bag in airlock.
3. After exiting the ante room - final pair of boots and gloves at control point.

General Arrangements and Equipment Locations

(See Attached Maps)

PHOTOGRAPHS

See previous entry photography (Make special note of photographs of your work area). Photographs are kept in Trailer 105 Room and may be reviewed upon request.

Camera Locations

(See Attached Maps)

Enclosed Stairwell Lighting

The lights in the enclosed stairwell are temporary lights which have been strung down from E1. 347' between the handrails. The on/off switch is tie-wrapped to the handrail in the center of the stairs. Since access to E1. 347' is via the open stairwell and access to the elevator machinery room or polar crane ladder is via the enclosed stairwell, these lights have been left on and should NOT be turned on/off unless ordered by Command Center.

(NOTE: Area at E1. 305' inside enclosed stairwell is 28 r/hr gamma).

This area is now roped off to traffic between E1. 305' and E1. 347'. The light bulbs are burnt out and will not be replaced until dose rates can be reduced in this area.

PLAN EL. 347'-6"

POLAR CRANE POSITION

5.0 AIRLOCK

To be operated by operations department and other authorized (trained) personnel only.

Both doors are locked when not in use.

Unlocking of inner door requires stationing of security at both exits.

Inner and outer doors are interlocked to prevent the opening of both doors at once.

Interlock may be defeated by mechanical means in airlock (see figure).

Doors swing (1) into airlock and (2) into reactor building.

Do not allow door to swing open by itself; hold it as it opens to avoid "banging".

Be careful not to step or bump the airlock door seal surface.

When closing doors, make sure handwheel is turned to stop in "open" direction.

Always wipe door seal down with "spot check" prior to last closing operation.

Door Operation (per 2104.-4.55)

To open:

1. rotate handwheel 3/4 turn to crack open equalizing valve; handwheel directions are specified above the handwheel.
2. allow pressure to equalize; note differential pressure by placing hand near air outlet pipe above handwheel.
3. rotate handwheel a second 3/4 turn until the mechanical stop is felt*
4. hold door and push open slowly until it is completely open.

To close:

1. swing door to near closed
2. insure door latch rollers are fully retracted; do so by turning handwheel in open direction until mechanical stop is felt
3. close door and turn handwheel in shut direction until mechanical stop is felt.

*NOTE: Inner Door requires more rotations of handwheel to open/close door.

D-A3-25

REACTOR BUILDING AIRLOCK INTERLOCK OPERATION

Restoring Airlock.

1. Obtain seal to seal interlock cabinet.
2. Enter airlock per section 5.5
3. Insure both doors are closed.

NOTE: Reference Figures 1 and 2 for detailed drawing of interlock system.

4. Remove clamp knob (#48) and open cover (#52).
5. Press down on camyoke (#49) until it is parallel with shaft as in Figure 1 and interlock disks are together.
6. Close cover (#52) screw in clamp knob (#48) and apply seal.
7. Notify Shift Foreman that interlock is in force and seal is applied.

Violating the interlock system.

1. Obtain Shift Supervisor/Foreman approval prior to violating interlock.

Enter airlock per section 5.5.

NOTE: See Figures 1 and 2 for detailed drawing of interlock system.

2. Break seal and remove clamp knob (#48).
3. Open hinged cover (#52) and remove tape from camyoke, if present. Pull or push on camyoke (#49) until yoke is perpendicular to the shaft.

Upper interlocking disk (#50) should slide toward camyoke violating interlock as in Figure 2.

4. Close cover and start clamp knob (#48) into hole. Do not turn in fully and do not apply seal.
5. Notify Shift Supervisor/Foreman that interlock is violated.

1630.2
Revision 1
12/27/77

INTERLOCK ENGAGED

fig. 1:

- 48 CLAMP KNOB
- 49 CAM YOKE
- 50 UPPER INTERLOCKING DISK
- 51 LIMIT SWITCH
- 52 HINGED COVER
- 53 UPPER INTERLOCK DISK SHAFT
- 54 STOP RING
- 55 COMPRESSION SPRING
- 56 LOWER INTERLOCK DISK
- 57 GEAR BACKLASH ADJ.
- 58 MITER GEAR SET
- 59 LOWER INTERLOCK DISK SHAFT

INTERLOCK DISENGAGED

6.0 EQUIPMENT

CAG Equipment

Radio/Microphone/Earphones*
Small Lights
Spotlights
Cameras*
Data Sheets/Clipboard/Maps/Etc.

HP FOREMAN

RO-2A*
E-530*
RO-7*
Teletector*
Dosimeters
BZA Personnel Air Sampler
Digital Dosimeters

RAD ENGINEERING

TLD's and dosimetry placement

EQUIPMENT FOR ENTRY TASKS

Tools	Rope
Meters	Ramps
Buckets	Carts
Well Wheels	Ladders
	Grease Guns

Others as needed

SPECIALIZED EQUIPMENT*

Safety Equipment
High Reach Scissors Lift
Raymond Forklift
Spider Lift Platform
Tugger)
Chainfall) On Lifting Rig

*Special training required prior to use.

READ/TEST

OUT BATT

0165

ON

mR

TOP VIEW DIGITAL DOSIMETER

ANTENNA

RED TRANSIT LIGHT

CHANNEL SELECTOR 1 or 3

VOLUME CONTROL

ω/UP

TOP VIEW MOTOROLA RADIO

SCALE OF 0 TO 500 mR SRPD

SCALE OF 0 TO 1 R SRPD

SCALE OF 0 TO 1 R SRPD

SCALE OF 0 TO 5 R SRPD

SPOTLIGHT

REAR VIEW

SIDE VIEW

ON OFF ON

7.0 Minimum RWP Requirements

1. Two sets of cloth PC's with corresponding number of gloves and booties. Wet suits or other additional protective clothing determined by team member activities.
2. Rubber boots/personal shoes.
3. Battery powered MSA Air Purifier Masks, Air Hoods, or Particulate Face Mask. (MSA Air Purifier unless otherwise specified).
4. TLD's - See following sheets.
5. Self-Reading Dosimetry - each man will carry one pencil dosimeter outside the PC's and two pencil dosimeters inside the PC's. Digital dosimeters will also be utilized by all entry personnel.

It is very important that you know the scale and millirem/division of the pencil dosimeters that you are assigned as you may be asked to give the Command Center a reading from your wrist dosimeter while in the Reactor Building (See attached page).

Inter-Office Memorandum

Date October 19, 1981

Subject Minimum Protective Clothing and Dosimetry
Required for Entries into the Reactor Building

9240-223
SOM #007 C, Revision 3

To SOM Manual Holders

Location TMI-II Nuclear Station
Bldg. 222

The following defines the minimum protective clothing and dosimetry requirements for entry into the Reactor Building

Protective Clothing

PROTECTIVE CLOTHING	QUANTITY
Cotton Coveralls	See Note 1
Wet Suit	See Note 1
Cotton Hoods	See Note 1
Cotton Gloves	1 Pair
Neoprene Gloves	1 Pair
Rubber Gloves	1 Pair (Note 2)
Inside Boot Liners	2 Pair
Firemans Boots/Tingley Boots	1 Pair
Plastic Shoe Covers	2 Pair (Note 2)
Full Face Neg. Pres. Resp.	1 (Note 3)

Note 1: If the task involves possible exposure to radioactive liquids, liquid protection is mandatory. If the task involves possible exposure to high levels of dry particulate activity, contamination protection is mandatory. "Wet Suit" protective clothing is suitable to provide liquid and contamination protection. This may be provided by wet suit pants, tops, apron or plastic wrappings as appropriate. Individuals entering the Reactor Building shall wear as a minimum two layers of protective clothing (i.e., cotton coveralls plus wet suit or two cotton coveralls, etc.).

A0000648

Note 2: Additional as required dependent on number of step-off pads or tasks being performed.

Note 3: Depending on task and/or anticipated airborne activity levels additional protection type respiratory equipment to be determined.

External Dosimetry

DOSIMETRY TYPE	LOCATION	REMARKS
TLD	Chest	Worn on front of body near center of chest
TLD	Right Thigh	Worn on front of thigh approximately 6" above knee
SRPD	Chest	Low Range (Note 1) and High Range (Note 1), worn near center of chest
SRPD	Forearm	High range worn outside all protective clothing

Note 1: The low range SRPD shall be selected such that the individuals anticipated exposure shall not exceed 3/4 of full scale. The high range SRPD shall be selected such that the individuals anticipated exposure shall not exceed 1/2 of full scale. The high range and low range SRPD may have the same range.

TLD's are to be placed beneath protective clothing with the open (beta) window facing away from the body surface. Open window shall not be taped or otherwise obscured.

Additional dosimetry such as finger rings, wrist TLDs, forehead TLDs, ankle TLDs or digital dosimeters may be needed depending on task being performed. Radiological Technical Support will determine these needs.

Specific dosimetry required for each individual will be defined on the dosimetry placement sheet attached to the RWP for the entry.

Internal Dosimetry

1. All individuals entering the Reactor Building shall be equipped with an operating breathing zone air sampler.
2. All individuals entering the Reactor Building shall collect a urine sample the day following the entry and shall submit the sample for analysis the next working day following the entry.
3. The individual(s) with the highest assigned MPC-hours for an entry shall be analyzed with the whole body counter prior to the end of the next working day.

JAF/PER/JWB/lmc

J. M. Brasher, Director
Radiological Controls

ENTRY # _____ - TEAM MEMBER CHECKLIST

NAME _____ SS# _____ AGE _____

Dose Record: (Dose Assessment Report Dated __/__/__)

Dose for Week _____ Dose Estimate _____

Dose for Qtr. _____ Dose Extension To: _____

Dose for Year _____

		SIGN-OFF/INITIAL	
I. PERSONNEL EQUIPMENT REQUIRED:	SERIAL # AND/OR CAL. DUE DATE	DRESSOUT AREA	CONTROL POINT
TLD'S: CHEST _____			
R. THIGH _____			
OTHERS _____			
SRPD'S: CHEST (HR) _____			
(TYPE) _____			
(LR) _____			
FOREARM _____			
RESPIRATOR/PURIFIER (CIRCLE) _____			
DIGITAL* _____			
BZA* _____			
RO-2A/TELETECTOR* _____			
RADIO* _____			

2. Dress Requirements:

PC'S: 1 Pair _____ 2 Pair _____ Other _____

(Includes gloves, boots, hoods, etc per dress out procedure).

Wet Suit: Full _____ Bottoms _____ Sleeves _____ Apron _____

Ice Vest _____

Safety Equipment* _____

*May be put on or obtained in Anteroom - Control Point to verify.

Protective Clothing Dress Out Sequence
(Without Ice Vest)

1. Underwear and socks.
2. TLDs: a Finger rings and wrist TLDs (if required) facing palm side of hand.
3. Personal shoes.
4. Ankle TLDs (if required).
5. Two pairs plastic booties over personal shoes - each taped around ankles loosely.
6. One pair cloth PC's with chest and thigh TLD attached - taped over second booties.
7. Third pair of plastic booties taped to first PC's.
8. Two self-readers (low range and high range) taped to chest areas on first PC's.
9. One pair cotton gloves.
10. One pair neoprene gloves under first PC's.
11. Second pair neoprene gloves taped over first PC's.
12. Second cloth coverall taped to third bootie, tape zipper.
13. Pair of yellow gloves taped to outer PC's.
14. Rubber boots, fastened, and taped to outer PC's.
15. Additional protective clothing (if required), i.e., wet suits, wet suit bottoms, aprons, etc.
16. Four sets of non-skid booties; cut through elastic at top.
17. Respirator belt with battery/blower pack (radio & digital pouches, if required).
18. Digital dosimeter in pouch on hip and one self-reader (high range) attached to either arm.
19. Skull cap.
20. Mask; turn on MSA (if powered respirator is used).
21. Have smoke test performed.
22. Radio equipment (if required) mike and earphone. (Tape wires to PC's - do not wrap around belt. Ensure freedom of movement of head without pulling on earphone).

8.0 (Continued)

Protective Clothing Dress Out
Sequence (Without Ice Vest)

23. Attach TLD inside first hood (if required).
24. First cloth hood; tuck under several PC.
25. Second cloth hood - taped to outer PC's.
26. Proceed to control point for RWP sign-on and equipment check.
27. BZA sampler attached to belt in back with head located near MSA pack.
28. Check and adjust equipment:
 1. Test radio with Command Center; volume should be "higher than normal" if working on El. 305'
 2. Test digital dosimeter; turn unit on and push "read" button; four zeros should appear in window and red light should light for at least 2 seconds.
29. Proceed into Ante Room when directed to do so by Command Center.
30. Obtain equipment required for task and small light in Ante Room.

Protective Clothing Dress Out Sequence
(With Ice Vest)

1. Underwear and socks
2. TLD's: a. Finger rings and wrist TLD's (if required), facing palm side of hand.
3. Personal shoes
4. Ankle TLD's (if required).
5. Two pairs plastic booties over personal shoes -- Each taped around ankles loosely.
6. One pair cloth PC's with chest and thigh TLD attached - taped over booties.
7. Third pair of plastic booties taped to first PC's.
9. Two self-readers (low range and high range) taped to chest area on first PC's.
10. One pair cotton gloves.
11. Rubber boots, fastened, and taped to outer PC's.
12. Four sets of non-skid booties; cut through elastic at top.
13. When instructed, put on ice vest and pull up PC's; tape zipper on outer pair.
14. Second pair neoprene gloves taped over first PC's.
15. Second cloth coverall taped to third bootie, tape zipper.
16. Pair of yellow gloves taped to outer PC's.
17. Additional protective clothing (if required), i.e., wet suits, wet suit bottoms, aprons, etc.
18. Respirator belt with battery/blower pack (radio & digital pouches, if required).
19. Digital dosimeter in pouch on hip and one self-reader (high range) attached to either arm.
20. Skull cap.
21. Mask; turn on MSA (if powered respirator is used).
22. Have smoke test performed.

8.0 (Continued)

Protective Clothing Dress Out Sequence (With Ice Vest)

23. Radio equipment (if required); mike and earphone, (Tape wires to PC's - do not wrap around belt. Ensure freedom of movement of head without pulling on earphone).
24. Attach TLD inside first hood (if required).
25. First cloth hood, tuck under second PC.
26. Second cloth hood - taped to outer PC's.
27. Proceed to control point for RWP sign-off and equipment check.
28. BZA sampler attached to belt in back with head located near MSA pack. Control point to verify operation.
29. Check and adjust equipment:
 1. Test radio with Command Center; volume should be "higher than normal" if working on El. 305'.
 2. Test Digital Dosimeter; turn unit on and push "read" button, four zeros should appear in window and red light should light for at least 2 seconds.
30. Proceed into Ante Room when directed to do so by Command Center.
31. Obtain equipment required for task and small light in Ante Room.

9.0 Communication with Command Center

In order to effectively communicate with the command center, the following methods are to be used:

- 1) Always initiate transmission with: "(Your name) to Base; (Message)"
- 2) End transmission with: "...., Over"
- 3) Always give numbers individually i.e. 123 is "One, two, three" not "one hundred twenty three"
- 4) When speaking do not run words together, i.e. pronounce each word individually "....digital, is, one, four, two, over"
- 5) Do not shout, speak in a normal voice
- 6) Do not attempt to transmit while anyone else is transmitting - we will not receive you
- 7) When your digital dosimeter reading is requested, you will receive the following message: "Base to (your name); We need your digital, over"

Your reply should be: "(Your name) to Base: my digital, is, two, four, seven, over"

(Leading zero's do not need to be included)

The base will confirm your response with: "Base to (Your name); Roger, we copy two, four, seven, over"

NOTE: If communication via radio is difficult to understand, the digital readings can be given via the CCTV System by giving the readings in sequence with your fingers and the command center will repeat them to you on the radio as you are giving the numbers.

- 8) Polar Crane Communication - at least one radio must be worn and operational at all times (exact scenario to be discussed at team briefing and will be incorporated in each polar crane work package).

RADIO PATH

INTERCOM PATH

10.0 Contamination Control/RIR Lessons Learned

1. Observe all step-off pads.
2. Wear extra yellow boots in case you need to enter the airlock more times than anticipated. (Four pairs are required by dress-out procedure).
3. Be conscious of your own protective clothing; be alert for suit becoming wet and for rips in gloves or wet suits; be careful to avoid coming in contact with contaminated surfaces with your body.
4. Bag all contaminated items immediately after use or removal. Rebag items again when entering airlock and ante-room.
5. Be careful to avoid putting yourself into any unusual positions by climbing on or over anything, pulling cable, or kneeling down on the floor unless it has been identified as part of your task and your clothing requirements have been adjusted to protect you.
6. Allow the ante-room support personnel to undress you without helping them outside of their instructions to you. This will help to keep your gloves clean and intact.
7. While undressing in the ante-room or frisking out, be careful to avoid touching yourself or anything which may be contaminated on bare skin. This includes the hose of your purifier and the ante-room door.

Note: If skin contamination is discovered while frisking out, a Skin Contamination Record (4170) must be completed, by the HP who will assist in decontaminating you, followed by a whole body count. In addition, a critique is normally called by Radiological Engineering (ALARA) and a Radiological Investigative Report (RIR) is written to summarize lessons learned and corrective actions. Inform Command Center if you become contaminated.
8. Wear extra yellow gloves or take several pairs with you when you enter the Reactor Building so that if your gloves rip or become very dirty you can pull on or peel off a pair as needed. Extra gloves are needed when climbing to the polar crane. Work gloves are required if job requires heavy physical work.
9. Be aware of what the anteroom personnel are doing and make sure they change their gloves periodically to prevent any contaminations. Refer questions to the Ante Room HP Tech.
10. Laundered protective clothing previously used in Radiologically controlled areas is not to be used for training. For this purpose, only new PC's and specifically designated boots, respirators, etc. may be used for mockups outside RWP areas.

Ante Room Support Personnel

Upon entering the CCC from the airloc, a variety of people will be there to assist you. They are people who have been trained to do this job and you should follow their directions during the unsuiting process. There will be at least one assistant in the CCC to help you during some of the more awkward undress steps and assistance will be provided via the glove parts. Be patient during the undress sequence as the orderly removal of equipment and PC's will prevent the loss of equipment and reduce the possibility of skin contaminations.

If you do not feel well upon exiting the airlock, tell one of these persons and they will expedite your exit from the Ante Room.

There will be at least one HP in the Ante Room. His job is to be familiar with, and maintain under control, the radiological conditions in the ante-room. This includes collecting dosimetry and BZA heads, running air samples and reporting their results, doing smear and radiation surveys, and monitoring work done on the ante room RWP.

Another HP will man the control point outside the ante room. His job is to keep the records on the RWP's and account for TLD's dosimeters. He also assists all entering personnel with RWP requirements, assists ante room personnel by handling material across the step-off pad, and assists exiting personnel in frisking out. Both HP's report to the HP foreman and have full authority on decisions made within this area of responsibility, so follow any instructions they give you.

ANTE ROOM LAYOUT

TWO INNER WALL

CCC LAYOUT

AREA ONE INNER WALL

CCC LAYOUT

TECH SHEET

USE OF ANTE ROOM TENTED ENCLOSURE

CONTAMINATION CONTROL CORRIDOR (CCC)

1.0 DESCRIPTION

The Ante Room tented enclosure is an engineering effort to reduce the need for respirators and maintain contamination control in the Ante Room during the processing out of entry teams. Refer to attachment 1 for sketches.

2.0 GENERAL

- 2.1 The Ante Room tented enclosure is designed to facilitate unsuiting of personnel exiting the TMI-2 Containment Building with a minimum number of support personnel in respirators.
- 2.2 One person in a respirator will normally be inside the tented enclosure in area one while personnel are unsuiting; to assist, remove air sampler heads and wipe down equipment portals for bag removal.
- 2.3 Glove ports are available for personnel outside the enclosure to provide supporting activities such as holding respirators and removing equipment.
- 2.4 Prior to utilizing the Ante Room tented enclosure the entry personnel will have been trained on the mock up.
- 2.5 Each team will normally undress using the "Buddy" system and place equipment and Anti-C's in designated receptacles. A mirror is available for individuals unsuiting separately.
- 2.6 Teams should unsuit on an item for item basis, i.e., team member A removes hood, team member B removes hood, etc.
- 2.7 When ready to exit containment building, remove one pair of nonskid boots and gloves external to RWP yellow gloves at step off pad (SOP) #1. Deposit in drum near inner drum ramp. Work gloves may be placed in tool box.

2.8 Proceed into airlock; remove 1 pair non-skids at SOP #2 and deposit in bag in airlock.

3.0 DETAILED INSTRUCTION - NORMAL EXIT

3.1 Entering Corridor

NOTE: If you have a question about unsuiting ask an attendant or come to a CCC window.

3.1.1 Place equipment coming out in transfer box in the door of the CCC. All items except trash should be identified, marked and bagged. Place trash in large portal just inside outer CCC door.

3.1.2 Enter enclosure to your right. Remove plastic shoe covers down to rubber boots and place in plastic and trash portal. First person go to station #2; second person go to station #1. Identify yourself to the area one attendant. He will tell you to unsuit as "A", "B", "C", or "D" and will inform HP.

3.2 Dosimeters/BZA's

3.2.1 Remove digital dosimeter from pouch and place in your dosimetry/BZA bag.

3.2.2 Remove self reading dosimeter - Pocket Dosimeter - (SRPD) from arm and place in your dosimetry/BZA bag with your digital dosimeter. Be careful not to jar the dosimeters.

3.2.3 Permit assistant in corridor to remove and bag the sample head from your BZ air sampler. Cut tube 4 inches below head. Ensure that it is placed in your dosimetry/BZA bag. Place Dosimetry/BZA bag in transfer box.

3.3 External Equipment

- 3.3.1 Remove respirator belt, being careful not to drop any gear or pull on respirator face piece.
- 3.3.2 Disconnect Motorola Radio from microphone, if worn, and remove from the pouch and gently place in radio portal with antenna going into portal last. Hand radio to teammate carefully, if portal is not in your location. Assistant may ask to hold your radio in area one for re-use.
- 3.3.3 Remove the BZ air sampler motor from your equipment belt being careful not to pull on respirator face piece and place in designated portal. Hand BZA motor to team member for disposal.

NOTE: Individual working in glove portals or assistant within CCC, may assist in any or all of the unsuiting steps.

- 3.3.4 Remove safety harness, if worn, and hang on hook in area one.

3.4 Protective Clothing - Outer Layer

- 3.4.1 Assist your teammate in removing plastic hood if worn, then allow teammate to assist you. Repeat for first cloth hood.
- 3.4.2 Insert plastic hoods in trash and plastic portal at your position. Insert cloth hoods in portal for PC's.

NOTE: Cut plastic down back or sides with safety scissors.

- 3.4.3 Roll rainsuits carefully back upon themselves and place into trash and plastic portal at your station when removed.
- 3.4.4 Carefully remove rubber boots, obtaining assistance as required. Insert rubber boots into labeled portal. If rubber boot portal is at teammates location, carefully hand rubber boots to teammate for disposal.

3.4.5 Remove outer (yellow rubber) gloves and place in rubber boot portal. If portal is not at your location hand gloves to teammate for disposal. Obtain clean rubber gloves from wall holder and put on to avoid ripping of neoprene gloves.

3.4.6 Assist as required to remove outer Anti-C's from your teammate. Obtain assistance as required to remove your remaining outer Anti-C's. Place cloth Anti-C's in cloth Anti-C portal.

NOTE: Unsuit down to single coveralls, respirator and hood. It is important to keep respirator and one complete set of Anti-C's on in first chamber.

3.5 Proceed into Area Two

3.5.1 Proceed to door at step off pad #3 with power purifier and motor assembly belt.

3.5.2 Check that other doors are closed, then open door and sit on chair with feet on contamination side of step off pad.

3.5.3 Hand power purifier motor assemble to assistant, remove outer shoe covers, place feet on the step off pad and hand shoe covers to assistant for disposal.

NOTE: The door must be closed while undressing in area two.

3.5.4 Move to appropriate location by team member. A&C go to station #4, B&D go to station #3.

3.5.5 Place respirator motor on chair.

3.5.6 Remove outer gloves and place in rubber glove portal.

3.5.7 Obtain clean rubber gloves from holder on wall and put on.

3.6 Dosimetry

3.6.1 Remove self reading dosimeters and place in your Dosimetry/TLD Bag.

3.7 Cloth Hood

3.7.1 Remove cloth hood, providing/receiving assistance as required.

3.8 Respirator

3.8.1 Remove respirator face piece, being careful not to rub face piece or hose against PC's or skin.

3.8.2 Turn power off on motor assembly.

3.8.3 Remove microphone from face piece by plug end. Insert microphone into designated portal for motorola radio microphones.

3.8.4 Change gloves and remove respirator glasses, if worn, and place in proper portal.

3.8.5 Obtain respirator face piece bag from wall opposite portal and insert respirator face piece into it.

NOTE: Do not remove hose from purifier unit.

3.8.6 Close bag (over hose) with tape.

3.8.7 Obtain respirator assembly bag from wall opposite portals and place motor assembly in bag. Place respirator face piece in separate bag, directly on top of motor assembly and seal bag with tape.

3.8.8 Insert respirator gently into designated portal. Place station #3 chair back by SOP #3.

3.9 Protective Clothing - Inner Layer and TLD's

3.9.1 Remove tape from cloth Anti-C's

3.9.2 Dispose of tape in trash portal.

3.9.3 Remove rubber goves and place in portal labeled rubber gloves.

3.9.4 Remove cloth Anti-C's, turning outside out, and place on wall hook.

3.9.5 Put on clean gloves, and remove TLD's in their holders, from coveralls and place in your Dosimetry/TLD bag and then place bag into transfer box.

3.9.6 Place Anti-C's in cloth Anti-C portal.

3.10 Special Equipment

3.10.1 If wearing Earmark radios, ice vests, etc., under PC's, Do Not remove unless directed to do so. Remove each item and place in bag if required to do so.

NOTE: Bags are on wall opposite portals.

3.10.2 Seal each "specialty equipment" bag and carefully insert into the portal labeled specialty equipment.

3.11 Exiting C.C.C.

3.11.1 Verify that other doors and portals are closed, then open CCC exit door.

3.11.2 Exit across SOP #4 by removing one pair of booties and place in trash portal. You should also discard any additional gloves put on in area two. You should still be wearing one pair of booties and gloves.

3.11.3 Close and latch door and proceed to SOP #5. Exit across SOP #5.

4.0 EMERGENCY EXIT DUE TO ILLNESS, FATIGUE, INJURY OR AT THE COMMAND CENTER

4.1 In the event of an emergency situation, notify the Command Center and teammates, if possible, immediately of the nature and severity of the emergency. Respond to Command Center instructions.

4.2 Follow the instructions of the HP Tech and Lead Ante Room Attendant upon exiting the airlock.

4.3 Upon exit from the Ante Room, follow Shift Supervisor, Safety Department or HP Foreman's instructions, as appropriate.

SAFETY WORK PRACTICES

A. HEAT STRESS EXPOSURE

These requirements establish work time guidelines for workers exposed to hot environments before a rest period is given for recovery from heat stress.

Work time guidelines reflect the actual time protective clothing and/or respiratory protection are worn while performing work assignments and does not include suiting up, unsuiting or going to and/or from the work location. Breaks should follow exposure to heat stress. Duration of breaks, extent of clothing removal, and the area where breaks are taken, shall be at the discretion of supervisory personnel.

The following definitions apply:

Anti-C's	Paper or cotton coveralls, cotton hood, rubber boots, and gloves.
Impermeable Clothing	Rain suits, water resistant clothing.
Respiratory Protection	Negative pressure full-facepiece respirator, SCBA or supplied-air respirator.
Supplied Air Hood or Suits	Hood or suit with at least 6 cubic feet per minute continuous air flow.
Temperature	Ambient temperatures at a relative humidity 75% at the work location.

If an extension of the work time guidelines identified herein is required, due to the nature or criticality of the task being performed, permission must be obtained from the supervisor in charge of the job.

Employee heat stress briefing, when required, should be arranged through and provided by the Site Safety and Health Department.

When work is planned in hot environments where relative humidities are known to be greater than 90%, the schedule for Anti-C's under Impermeable Clothing with Respiratory Protection shall be utilized.

When temperatures exceed 120°F or where hot radiant heat surfaces are encountered, direction shall be provided by the Supervisor - Safety and Health for personal protective equipment.

When an individual feels discomfort from heat stress, he/she must immediately notify the person in charge and leave the area.

HEAT STRESS - TEMPERATURE AND PERMISSABLE LIMITS

<u>Protective Equipment</u>	<u>Temperature</u>	<u>Guidelines For Work Time</u>
<u>Conventional Work Clothing</u>	Less than 100°F 100 - 100°F 110 - 120°F	None 2 Hrs. 45 Min.
<u>Anti-C's (Only)</u>	80 - 90°F 90 - 100°F 100 - 110°F 110 - 120°F	3 Hrs. 2 Hrs. 1 Hr. 30 Min.
<u>Anti-C's Under Impermeable Clothing</u>	80 - 90°F 90 - 100°F 100 - 110°F 110 - 120°F	1.5 Hrs. 1 Hr. 30 Min. 15 Min.
<u>Anti-C's (Only) With Respiratory Protection</u>	Less than 80°F 80 - 90°F 90 - 100°F 100 - 110°F 110 - 120°F	4 Hrs. 2 Hrs. 1.5 Hrs. 1 Hr. 30 Min.
<u>Anti-C's Under Impermeable Clothing With Respiratory Protection</u>	70 - 80°F 80 - 90°F 90 - 100°F 100 - 120°F	1 Hr. 45 Min. 30 Min. 15 Min.
<u>Anti-C's With or Under Supplied Air Hood/Suit</u>	80 - 100°F 100 - 110°F 110 - 120°F	4 Hrs. 2 Hrs. 1 Hr.

By: _____

R. G. Ritthamel 12-1-81
R. G. Ritthamel
Manager - Industrial Safety
and Health

WORKING IN HOT ENVIRONMENTS

Heat is a naturally occurring stress under which human beings have evolved over the ages and to which each of us is exposed at least periodically during our lives. Industrial heat exposure, however, frequently is much greater than that encountered in the natural environment. Hot industries also involve hard physical work which adds to the total heat stress. The effect or consequences of heat stress in the work environment can be seen in decreased worker productivity, increased accident rates, illnesses, and fatalities. The primary concern of this discussion is the control of heat stress, the prevention of heat-related illness and death.

The body is continually producing heat every second that it lives. This heat comes from the breakdown of food that the body uses to supply the energy it needs to support its life processes. About 75% of the energy consumed by the body ends up in the form of heat which in turn heats up the body. Increased physical activity produces even more body heat. To maintain a normal acceptable body temperature, this heat must be brought to the skin surface and exchanged with the air surrounding the body. The physiological process which maintains the balance between heat production and heat removal is a complex one involving the central nervous system, the circulatory system, the skin, and the muscles. The situation is similar to the working system for the automobile engine. In the engine, energy and heat are produced in the block. Water is pumped through the block where it absorbs heat, then through the radiator, where the heat is exchanged with the atmosphere. The rate of circulation is controlled by a thermostat, which opens when the engine is hot. Similarly, in the body the blood carries heat from the core of the body to the skin. The amount of blood flowing to the skin can be increased or decreased. The rate of heat loss can be increased if necessary by wetting the skin with sweat. When water evaporates, the water molecules absorb a large quantity of heat. The heat gained by the water molecules as they evaporate is lost from the wetted skin surface. Under conditions of excessive heat stress, this evaporative cooling becomes the major avenue for achieving heat balance. The body's cooling system is remarkably efficient and can adjust to steady work in hot environments. This adjustment is called acclimatization and is usually completed in a week. Despite the adaptability of the body's cooling system, it can be overloaded by certain extremes in environmental conditions and physical activity.

Heat stress problems arise when the body produces more heat than it can get rid of. When this happens, a variety of illnesses can occur depending on the duration and severity of stress and the effectiveness of steps taken to relieve the stress. These include:

Heat Exhaustion

Heat exhaustion is caused by an insufficient blood flow to the brain because too much blood has been diverted to the skin in an effort to cool the body. During heat exhaustion, body temperature is usually normal and the skin is cool, wet, and pale. The major symptoms are giddiness, headache, weakness, fainting, vomiting, and a rapid, weak pulse. Rest in a cool environment and fluid replacement will result in full recovery. This type of heat illness is usually caused by inadequate fluid intake to make up for the body water lost in the sweat.

(Continued)
Working in Hot Environments

Dehydration

The water lost from the body as sweat must be replaced by drinking water if dehydration is to be prevented. Dehydration rapidly leads to decreases in performance and work capacity and to heat exhaustion. Sweat production of 8 to 10 quarts each working day is not uncommon in hot industries. This means that water must be replaced at the rate of at least 1 quart each hour. When sweating is heavy, a better practice is to drink about a cup of cool (not cold) water every 10-20 minutes throughout the work day.

Heat Stroke

Heat stroke results from a high body temperature that is caused by a failure of the body's cooling system. The high body temperatures accompanying heat stroke can be fatal if they are not lowered. Usually, collapse and coma with high body temperature are the first symptoms, and the victims skin may be red, hot, and dry. Treatment consists of rapid reduction of the body temperature by immersion in ice bath, alcohol spray, or fans and wet sheets. Age, obesity, lack of physical fitness, and hard physical work are factors that increase the chances of heat stroke. Heat stroke is a serious medical emergency and requires speedy medical attention to save the victims life.

Heat Cramps

Heat cramps result from excessive loss of salt in the sweat without adequate replacement. Heat cramps involve mainly the hand, arm, leg, and abdominal muscles. Heat cramps are not very common and occur mostly when sweating is heavy, water replacement is adequate, but salt intake is low. A little salt added to the drinking water or the food is an effective treatment and prevention of heat cramps. For heat adjusted (acclimatized) workers the usual diet contains enough salt because their sweat is low in salt. Moderation is needed when increasing salt intake because too much salt actually reduces heat tolerance, and for persons with high blood pressure, increased salt intake can actually aggravate the condition to a dangerous level. Drinking Gatoraid is the best and safest way to maintain fluid and salt balance at the same time.

The conditions found at TMI are normally within the range that your body's heating/cooling system can handle. The range limits may be exceeded when doing hard work during hot weather or when wearing protective clothing in hot contaminated areas. When necessary, the safety department will measure the environmental conditions in a hot area to see if control measures must be instituted. The early symptoms of heat stress are:

Weakness
Extreme Fatigue
Dizziness

Nausea
Headache
Thirst

More advanced symptoms are:

Arm, leg, and stomach
muscle spasms
Irregular or increased heartbeat

Extreme Thirst
Fainting

(Continued)
Working in Hot Environments

If you note early signs of heat stress, notify your supervisor. The immediate treatment is to:

Rest in a cool place

Drink small amounts of cool water frequently

If symptoms continue, get medical help from First Aid

Don't expect to work at your normal pace for the first few days in a hot area. If your body is allowed to accustom itself to heat stress areas gradually (acclimatization), within a week or so you will be able to stand a full shift of hard work in a hot area with few ill effects. If you have any further questions about heat stress, contact the First Aid office.

B. CONFINED SPACES

1.0 GENERAL:

- 1.1 The purpose of this procedure is to establish guidelines to insure the protection and health of personnel who work in, about, and in connection with, confined spaces.
- 1.2 It is further intended to make employees aware of hazards involved and give essential training in the use of test methods and protection equipment necessary in hazardous or toxic environments.
- 1.3 These requirements are applicable to all areas at a GPU Nuclear facility that meet the definition of a confined space.
- 1.4 These requirements do not specify radiological work requirements or precautions, as they are the responsibility of the Radiological Controls Department and have separate procedures.

2.0 RESPONSIBILITIES:

- 2.1 Supervisors are responsible for:
 - 2.1.1 Identification of any work area that meets the definition of a confined space.
 - 2.1.2 Discussing questionable areas with the Safety & Health Department to confirm if a work area meets the definition of a confined space.
 - 2.1.3 Ensuring that employees are informed of the hazards and/or rescue requirements specified on the Confined Space Permit.
 - 2.1.4 Familiarizing all workers who will enter the space with the hazards of the same and assure that all personnel are trained and able to use respiratory protection and other personal protective equipment as specified on the permit.
 - 2.1.5 Discussing a suitable plan for the emergency rescue of disabled personnel with the workers prior to entry.
- 2.2 Safety & Health Department is responsible for:
 - 2.2.1 Deciding what precautions are necessary to safeguard workers entering confined spaces.
 - 2.2.2 Performing air sampling of confined spaces for oxygen and combustible gas concentrations and, when necessary, for toxic materials prior to entry.

2.2.3 Authorizing the Confined Space Permit.

2.2.4 Providing all air sampling instruments required to test confined spaces.

2.2.5 Instructing the supervisor regarding what conditions and precautions are covered in the Confined Space Permit.

2.2.6 Monitoring the work practice to be sure that it is effective.

2.2.7 Posting the Confined Space Permit at the entrance to the confined space prior to entry.

3.0 DEFINITIONS:

3.1 "Confined space" means any space having a limited means of access which is subject to the accumulation of toxic or flammable contaminants or has an oxygen deficient atmosphere.

3.2 Confined or enclosed spaces include, but are not limited to, excavations, storage tanks, process vessels, bins, boilers, ventilation ducts, sewers, manholes, underground vaults, pipeline tunnels and open top spaces more than four feet in depth.

4.0 PRECAUTIONS:

4.1 Entry of personnel into oxygen deficient atmospheres, atmospheres with explosive gas mixtures or toxic atmospheres shall not be permitted without the appropriate respiratory protection.

5.0 PROCEDURES FOR ENTRY AND WORK IN CONFINED SPACES:

5.1 Confined Space Permit

5.1.1 The Safety & Health Department shall issue the Confined Space Permit.

5.1.2 Personnel may enter the confined spaces under the following conditions:

5.1.2.1 When a Confined Space Permit issued by the Safety & Health Department has been posted at the entrance to the confined space.

5.1.2.2 When the conditions and requirements of this Safe Work Practice, as specified in Section 5.5 (Emergency Entry into Confined Spaces), are met.

- 5.1.3 Permits shall be valid for the time specified on the permit.
- 5.1.4 With monitoring devices installed, operations shall be discontinued if oxygen level drops below 19.5% or combustible gases exceed 20% of their lower explosive limit. This condition shall terminate the permit.
- 5.1.5 Upon completion of work, the supervisor shall sign off the permit, and return it to the Safety & Health Department.

5.2 Procedure for Obtaining a Permit

- 5.2.1 Supervisors shall consult with the Safety & Health Department if there is any question as to whether a work area is a confined space; the decision of the Safety & Health Department shall be final.
- 5.2.2 The Safety & Health Department shall, when notified, perform the following:
 - 5.2.2.1 Review the past Confined Space Permits issued to determine if toxic materials may be present in the atmosphere.
 - 5.2.2.2 Sample the confined space atmosphere for oxygen and combustible gas, and if necessary, for toxic materials.
 - 5.2.2.3 Specify on the Confined Space Permit when ventilation, air monitoring, emergency equipment, and/or a stand-by person are required.

5.3 Requirement for Entry and Work in Confined Spaces

- 5.3.1 Air samples shall be taken by the Safety & Health Department prior to entry into a confined space.
- 5.3.2 Employees shall not enter a confined space until air sampling results establish that the oxygen concentration is between 19.5% and 21% and the combustible gas concentration is between 0% and 20% of the lower explosive level (LEL).
- 5.3.3 When initial air sampling results indicate that the oxygen concentration is below 21% or combustible gases are present, mechanical ventilation shall be utilized and retesting shall be performed by the Safety & Health Department.

- 5.3.4 The Safety & Health Department shall specify when continuous ventilation and/or monitoring are required when retesting indicates oxygen concentrations are above 19.5% but below 21% and combustible gases below 20% but above 0% of the LEL.
- 5.3.5 The Safety & Health Department shall specify when a stand-by rescue person, mechanical ventilation and/or continuous monitoring is required for the confined space.
- 5.3.6 When rescue equipment is required it shall be located outside the confined space and be immediately available for use in case of an emergency. This equipment may include safety belt(s), lifeline(s) and emergency self-contained breathing equipment.
- 5.3.7 When a stand-by rescue person is required this person shall be capable of communicating with all workers in the confined space during the entire entry.
- 5.4 Emergency entry into a confined space without a permit may be authorized by the shift foreman under the following conditions:
 - 5.4.1 An attempt has been made to contact the Safety & Health Department.
 - 5.4.2 The job supervisor was not able to contact the Safety & Health Department.
 - 5.4.3 When in the case of an extreme emergency, entry is required in a confined space containing flammable gas or vapor without an atmospheric test, precautions shall be taken to ensure ignition does not occur.
 - 5.4.4 When an emergency situation arises, only workmen equipped with a supplied-air respirator with an auxiliary self-contained breathing apparatus or SCBA, safety harness, safety line, other necessary protective equipment, and in communication with the rescue person may enter a confined space without prior testing.
 - 5.4.5 A stand-by person shall be stationed outside the confined space for rescue purposes and shall have the same equipment specified in Section 5.5.4.
 - 5.4.6 The Safety & Health Department shall be notified the next regular working day following the emergency entry of the details of the entry.

6.0 AIR MONITORING EQUIPMENT:

- 6.1 All air monitoring instruments used shall have audio and visual alarms which are set at 19.5% for oxygen and 20% (LEL) for combustible gases as methane.

By: _____

R. G. Ritthamel
R. G. Ritthamel

Manager - Industrial Safety & Health

CASUALTY PROCEDURE

FOR

HIGH RADIATION CONDITION IN CONTAINMENT

This procedure supplements procedure

2202-1.7

HIGH RADIATION CONDITION IN CONTAINMENT

HIGH RADIATION CONDITION DETECTED BY ENTRY PERSONNEL (Entry in Progress)

NOTE: For purposes of this document, the following shall be considered high radiation conditions:

1. An unanticipated increase in the general area background, detected by hand-carried instruments, by a factor of five from the most recently recorded previous survey information.
2. An unanticipated increase in the general area background, detected by hand-carried instruments, by a factor of five during the entry.

Entry Personnel shall:

1. Report readings to Command Center.
2. Move to a lower radiation area if any.
3. Proceed to personnel airlock as directed by Command Center.
4. Entry team leader report status and location of all team members.

Command Center shall:

1. Notify all personnel in containment of high radiation.
2. Order all personnel to exit building, unless it is determined that high radiation conditions were caused by ongoing activities and an evaluation is made by Radiological Controls which concludes that an evacuation is not necessary.
3. Notify the Control Room.
4. Notify the HP Foreman.
5. Notify the Ante Room.

Control Room shall:

1. Respond in accordance with Unit II Emergency Procedure 2202-1.7 using procedure requirements applicable to readings reported by the Command Center which would be appropriate, if containment building radiation monitor HP-R-213 had detected the reported radiation levels.

Ante Room shall (if so directed by the Command Center):

1. Record and report all exiting personnel.
2. Secure any entry preps and clear Ante Room to receive exiting personnel.

HIGH RADIATION CONDITION DETECTED BY THE CONTROL ROOM
(Entry in Progress)

NOTE: HP-R-213 is the only area radiation monitor currently operational in containment. HP-R-211, 212 and 214 are not operational.

Control Room shall:

1. Respond in accordance with Unit II Emergency Procedure 2202-1.7.
2. Notify Command Center of readings and location.
3. Direct Command Center to evacuate containment if required.

Command Center shall:

1. Notify all entry personnel.
2. Order all personnel to exit the building if so directed by the Control Room.
3. Notify HP Foreman.
4. Notify Ante Room.

Entry Personnel shall (if so directed by the Command Center):

1. Secure work - de-energize equipment.
2. Team leaders report status and location of team members.
3. Exit the building.

Ante Room shall (if so directed by Command Center):

1. Record and report all exiting personnel.
2. Secure any entry preps and clear Ante Room to receive exiting personnel.

CASUALTY PROCEDURE

FOR

FIRE IN CONTAINMENT

This procedure supplements procedure

2202-3.1

FIRE IN CONTAINMENT

When Fire is detected by Entry Personnel:

Entry Personnel shall:

1. Notify Command Center - Fire Elevation _____ Fire Elevation _____
(Fill in blanks with appropriate elevation).

Followed by location, type, size

Example:

Location - 5' from In-Core Instrumentation Chase.

Type - Electrical, Trash, Chemical

Size - Small (can be extinguished with fire extinguisher)

Large (Cannot)

2. If in your judgement you can put the fire out and have the equipment to do so, then put it out, otherwise, leave and assemble to the Personnel Airlock # _____. (Airlock unaffected by fire)
3. Prior to leaving check to make sure no one is left in area. Entry team leaders are to report location and status of team members to Command Center.
4. Secure your equipment.
5. Do not, at anytime, endanger yourself except to prevent injury to another team member.

Command Center shall:

1. Notify all personnel in containment.
2. Notify the Control Room.
3. Notify HP Foreman.
4. Notify Ante Room.
5. Order all personnel not in vicinity of fire to proceed to Airlock via _____ stairwell and stand by to assist.
(Fill in blanks with airlock and stairwell unaffected by fire)
6. Direct entry personnel as required.
7. Maintain visible contact, if possible, via CCTV.
8. Maintain radio contact.

Command Center shall : (con't)

9. Monitor fire with CCTV if possible.

Note: In the event of fire, the Control Room shall assume control. The Command Center responsibility is limited to evacuation of personnel and provision of support as requested by the Control Room.

Control Room shall:

1. Initiate action in accordance with Unit II Emergency Procedure 2202-3.1, Fire.
2. Establish direct communications with Command Center (Main intercom/console when available).
3. If electrical, de-energize nearest breaker feeder.
4. Pressurize fire main in containment.
5. Secure purge.
6. Make arrangements to have plant fire extinguishers staged to the Ante Room to provide extinguishers to fight the fire for 45 minutes.

Ante Room shall:

1. Stage fire extinguishers to Airlock.
2. If personnel are in process of undress - expedite.
3. If personnel are in process of entry, secure entry (Entry personnel remove one set of booties and leave Ante Room. Muster in corridor).
4. Station man near intercom.
5. Station man in Airlock - Man Page Channel 1.
6. Remove excess equipment from Ante Room.
7. Prepare to aid fire brigade.
8. Provide two (2) two-way radios for fire brigade use (no setcoms).
9. Log and report all personnel exiting and entering the building.

HP Foreman shall:

1. Take charge in Ante Room/staging area for HP matters only.
2. Direct HP Support to #1 Airlock and Man Page Channel 1.

Safety/First Aid shall:

- 1. Standby to assist - if personnel are injured.**
- 2. Notify First Aid.**

Fire Brigade shall:

- 1. Assemble as directed by Control Room.**
- 2. Fire Brigade will enter the containment at the direction of the Control Room.**
- 3. Command Center will assist as requested.**

FIRE IN CONTAINMENT

When Fire is detected by the Command Center:

Entry Personnel shall:

1. Secure work and de-energize electrical equipment. Assemble at Airlock as directed by Command Center. Exit when directed. Team leaders report status and location of all team members.
2. Do not, at anytime, endanger yourself except to prevent injury to another team member.
3. If in the area, and fire extinguishers are available and in your judgement you can put out the fire, do so; otherwise leave area via route specified and exit as directed by the Command Center.

Command Center shall:

1. Notify all personnel in containment.
2. Notify the Control Room.
3. Notify HP Foreman.
4. Notify Ante Room.
5. Order all personnel not in vicinity of fire to proceed to Airlock _____ via _____ stairwell and stand by to assist. (Fill in blanks with airlock and stairwell unaffected by fire)
6. Direct entry personnel as required.
7. Maintain visible contact, if possible, via CCTV.
8. Maintain radio contact.
9. Monitor fire with CCTV, if possible.

NOTE: In the event of fire, the Control Room will assume control. The Command Center responsibility is limited to evacuation of personnel and provision of support as requested by the Control Room.

Control Room shall:

1. Initiate action in accordance with Emergency Procedure 2202-3.1, Fire.
2. Establish direct communications with Command Center (Main intercom/console when available.)
3. If electrical; de-energize nearest feeder breaker.
4. Pressurize fire main in containment.

Control Room shall: (con't)

5. Secure purge.
6. Make arrangements to have plant fire extinguishers staged to the Ante Room to provide extinguishers to fight the fire for 45 minutes.

Ante Room shall:

1. Stage fire extinguishers to Airlock.
2. If personnel are in process of undress - expedite.
3. If personnel are in process of entry, secure entry (Entry personnel remove one set of booties and leave Ante Room. Muster in corridor).
4. Station man near intercom.
5. Station man in Airlock - Man Page Channel 1.
6. Remove excess equipment from Ante Room.
7. Prepare to aid fire brigade.
8. Provide two (2) two-way radios for fire brigade use (no setcoms).
9. Log and report all personnel exiting and entering the building.

HP Foreman shall:

1. Take charge in Ante Room/staging area for HP matters only.
2. Direct HP Support to #1 Airlock and Man Page Channel 1.

Safety/First Aid shall:

1. Standby to assist - if personnel are injured.
2. Notify First Aid.

Fire Brigade shall:

1. Assemble as directed by Control Room.
2. Fire Brigade will enter the containment at the direction of the Control Room.
3. Command Center will assist as requested.

FIRE IN CONTAINMENT

When fire is detected by the Control Room:

Entry Personnel shall:

1. Secure work and de-energize electrical equipment. Assemble at Airlock as directed by Command Center. Exit when directed. Team leaders report status and location of all team members.
2. Do not, at anytime, endanger yourself except to prevent injury to another team member.
3. If in the area, and fire extinguishers are available and in your judgment you can put out the fire, do so, otherwise leave area via route specified and exit as directed by the Command Center.

Command Center shall:

1. Notify all personnel in containment.
2. Notify HP Foreman.
3. Notify Ante Room.
4. Order all personnel not in vicinity of fire to proceed to Airlock _____ via _____ stairwell and stand by to assist. (Fill in blanks with airlock and stairwell unaffected by the fire.)
5. Direct entry personnel as required.
6. Maintain visible contact, if possible, via CCTV.
7. Maintain radio contact.
8. Monitor the fire via CCTV if possible.

NOTE: In the event of fire, the Control Room will assume control. The Command Center responsibility is limited to evacuation of personnel and provision of support as requested by the Control Room.

Control Room shall:

1. Notify Command Center, fire in containment.
2. Initiate action in accordance with Emergency Procedure 2202-3.1, Fire.
3. Establish direct communications with Command Center (main intercom/console if available).

Control Room shall: (con't)

4. If electrical, de-energize nearest feeder breaker.
5. Pressurize fire main in containment.
6. Secure purge.
7. Make arrangements to have plant fire extinguishers staged to the Ante Room to provide extinguisher to fight the fire for 45 minutes.

Ante Room shall:

1. Stage fire extinguishers to Airlock.
2. If personnel are in process of undress - expedite.
3. If personnel are in process of entry, secure entry (Entry personnel remove one set of booties and leave Ante Room. Muster in corridor.)
4. Station man near intercom.
5. Station man in Airlock - Man Page Channel 1.
6. Remove excess equipment from Ante Room.
7. Prepare to aid fire brigade.
8. Provide two (2) two-way radios for fire brigade use (no setcoms).
9. Log and report all personnel exiting and entering the building.

HP Foreman shall:

1. Take charge in Ante Room/staging area for HP matters only.
2. Direct HP Support to #1 Airlock and Man Page Channel 1.

Safety/First Aid shall:

1. Standby to assist - if personnel are injured.
2. Notify First Aid.

Fire Brigade shall:

1. Assemble as directed by Control Room.
2. Fire Brigade will enter the containment at the direction of the Control Room.
3. Command Center will assist as required.

CASUALTY PROCEDURE
FOR
Personnel Injury or Sickness
In Containment

This procedure supplements procedure 1054.16

PERSONNEL INJURY OR SICKNESS

When an injured or sick individual is found by entry personnel, the Command Center or the Control Room,

HP Foreman shall:

1. Take charge in the Ante Room/staging area for HP matters only.
2. Send an additional HP for duty in the Ante Room.
3. Provide recommendation for best use of available personnel from a radiological viewpoint.
4. Make preparations to receive and monitor contaminated personnel.
5. Log and report all exiting personnel.

Safety/First Aid shall:

1. Maintain representation in the Command Center.
2. Provide rescue team as soon as practicable.
3. Make recommendations on rescue action, evacuation, respirator removal when information is available.

Control Room shall:

1. Initiate action in accordance with procedure 1054.16, Contaminated Injuries/Radiation Overexposure.
2. Establish direct communications with the Command Center.
3. Muster the rescue and assistance team and stand by to assist.

Command Center shall:

1. Request information on the condition of the individual concerned.
2. Notify other personnel in containment, the Ante Room, Control Room, the HP Foreman and Safety/First Aid.
3. Secure all non essential work including entrance into containment by teams for purposes other than rescue or assistance.
4. Verify locations and stations of ALL entry personnel.

Command Center continued:

5. Direct Ante Room assistance team to enter, if required.
6. Insure communications have been established in key locations
(containment, Ante Room, Control Room, HP Foreman)
7. Based on Safety recommendations, render assistance with Ante Room team.

Ante Room shall:

1. Quickly undress any team members exiting.
2. Station one man at the intercom.
3. Assistance team prepare to enter and stand by for instructions in
Airlock. Man page, channel 1.
4. Secure any routine work.
5. Hold any team ready for entry in stand by.
6. Remove excess equipment from Ante Room.

Entry Personnel shall:

1. Determine the condition of the individual and nature of injuries;
question him if he is conscious.
2. Inform the Command Center of these facts by fastest available means,
have one man in sight of CCTV camera, if possible. A status report
should include:

Name of individual, location, description of injury and condition
(conscious, unconscious, bleeding, breathing problems, electric
shock, heat stress, able to walk, etc.)

3. Entry team leaders report status and location of team members.
4. Await further instructions.
5. Do not move the individual without permission of the Command Center.

Entry Personnel shall: (Continued)

6. If the individual is having difficulty in breathing, the respirator may be removed. Caution must be exercised in removing the respirator in order to avoid additional injury to the individual. If breathing difficulty is not evident, do not remove the respirator without permission from the Command Center.

17. Fire Protection

Fire Protection standards have been upgraded in the containment. This includes the following measures:

- (1) Replacement and test of fire hoses on El. 305' and El. 367' (See p. 6, 7 for location).
- (2) Installation of portable fire extinguishers in the ante room, El. 305' and El. 347' (See p 7, 8 for locations)
- (3) Log of transient combustibles maintained by Command Center; use of fire resistant materials where possible.
- (4) Monitoring containment following entry with CCTV.
- (5) Training of entry personnel on Casualty Procedures and use of Fire Extinguishers.
- (6) Training of Fire Brigades on Containment conditions.
- (7) Welding, cutting, burning, soldering shall be controlled per 1410-Y-26 with fire watches in radio contact with the Command Center.

Use of Fire Extinguisher:

- (1) Transport extinguisher to area needed
- (2) Break seal holding hose in place
- (3) Charge extinguisher by pressing down where indicated
- (4) Red plunger will pop up when ready for use.
- (5) Squeeze applicator nozzle to direct chemicals on fire.

Protection for family, workers, and/or possessions was your goal in purchasing an Ansul extinguisher. To reach the goal, two more things are needed.

First, everyone must be educated. They must know where to find the extinguisher, what fires it can and cannot put out, and they must know how to use it.

Second, the extinguisher must be properly maintained in the right place, ready to use when needed.

The National Fire Protection Association produces a pamphlet which contains vital information for extinguisher owners. The pamphlet is N.F.P.A. No. 10, "Standard For Portable Extinguishers," and may be purchased from National Fire Protection Association, 410 Atlantic Avenue, Boston, Massachusetts 02110.

The extinguisher is a container of fire extinguishing agent. It uses a source of energy (e.g. pressure stored in the container) to expel the agent and combat the fire. Every extinguisher has symbols and numbers to indicate the type and size fire the extinguisher should be used on. To interpret that information, refer to appropriate portion of this brochure.

Installation begins with a check to see that your extinguisher is properly charged, with the safety seals intact. If anything indicates possible discharge, have your unit serviced immediately. If, in unpacking and checking your extinguisher, you accidentally discharge even the slightest amount of agent, have your unit serviced: partial discharge can cause the extinguisher to slowly lose all of its pressure.

Choose the location of your extinguisher carefully. The extinguisher should be near the type of fire hazard indicated on the nameplate, and should be clearly visible from the hazard area. Locate your extinguisher so that the fire will not keep you from reaching it. When reviewing the nameplate information, note any temperature limits and choose your location accordingly. Also place the extinguisher near an exit to avoid the possibility of trapping the fire fighter.

The mounting bracket height should allow easy removal of the extinguisher. Remember also that rust can be your worst enemy; be sure the bracket holds the extinguisher, especially the base, away from moisture. Remember that the extinguisher is a heavy device that requires solid support to be safe.

Instruction and training are vital for effective use of an extinguisher. In the excitement of a fire situation, the uninitiated layman is much less likely to perform effectively than is an instructed person.

In case of a fire, evacuate the occupants of the hazard area and call the fire department. Then use your training and nameplate information to help ascertain if you can effectively deal with the type and size of fire you have.

If you decide to fight the fire:

1. Maintain the proper distance (6 to 8 feet for most dry chemical hand portable extinguishers).
2. Try to position yourself so that the wind blows the fire away from you.
3. Pull the safety pin, or release any safety locks on the unit.
4. Hold your extinguisher firmly and begin spraying the agent at the near edge of the fire. (Most Ansul devices have a "trigger" to squeeze at the handle or the nozzle. Refer to nameplate on your extinguisher, and know how to activate your unit BEFORE the need arises.)*
5. Move the stream rapidly side to side covering the entire width of the fire.
6. Advance slowly as your extinguisher pushes the fire back. Try to maintain the optimum distance from the front edge of the fire.
7. After the fire is out, step back and watch for possible reignition.

*Drawings, elsewhere on this brochure, illustrate basic types of fires and methods of fighting them.

In fighting a fire or cleaning up after, try to avoid prolonged close contact with dry chemical extinguishing agent. The agent is not toxic, but prolonged contact may result in temporary eye or respiratory irritation.

Following a fire, there are three things to do immediately. The first is to secure the area so the fire won't start again.

Then clean up the debris. Avoid damage to the surrounding area and equipment by sweeping or vacuuming dry chemical and fire debris promptly. Finally, regardless of how much extinguishing agent was used, a recharge is required immediately. Refill should be done only by an authorized Ansul distributor. The refill agent must be the same as originally used. Improper filling can result in inoperable/dangerous units.

NOTE: Never incinerate an extinguisher. When discarding an extinguisher, remember it is a pressure vessel that could explode if incinerated. Discharge fully; remove caps, valves, etc.; dispose of safely.

Inspection is a check that should be performed at least monthly. Where conditions indicate the need, it may be performed much more often. Refer to N.F.P.A. No. 10 for more detailed information.

Inspect/Correct List

1. Extinguisher
 - ☐ Proper Place
 - ☐ Visible
 - ☐ Accessible
 - ☐ Clean
 - ☐ Physical Damage
 - ☐ Corrosion/Rust
 - ☐ Proper Pressure
 - ☐ Proper Amount of Agent (Weight/Heft)
2. Nameplate
 - ☐ Legible
3. Safety Seals/Indicators
 - ☐ Intact/Proper Position
4. Hose
 - ☐ Cracked/Cut/Worn
 - ☐ Couplings Intact
5. Nozzle
 - ☐ Clear of Obstructions
 - ☐ Trigger Operates Smoothly
6. Mounting Bracket
 - ☐ Firmly Attached
7. Inspection Record
 - ☐ Dated and Initialed

Maintenance is required periodically (see nameplate) just as it is with any important mechanical device. Refer to N.F.P.A. No. 10 for instructions. The following should be included in any maintenance procedure.

Clean and examine the surface thoroughly. Avoid dust and corrosion by cleaning and repainting wherever paint chips or imperfections are found. If rust or corrosion is found to have attacked any extinguisher part, see your Ansul distributor immediately.

Protect your investment in fire safety with proper training, proper placement, and proper maintenance.

Coast Guard Approvals

For extinguishers with U.S. Coast Guard approval, the approval is valid only with the bracket specified on the extinguisher nameplate.

Basic Dry Chemical Extinguisher Technique

Spill Fire

Gravity Fed Fire

Symbols

Every Ansul extinguisher displays one or more of the Underwriters Laboratories and National Fire Protection Association symbols on its nameplate. Each symbol indicates the type of fire (fuel) on which the extinguisher may be safely and effectively used.

Use "A" rated extinguishers on ordinary fires: wood, paper, cloth, rubber, many plastics, etc. **CAUTION:** Burning plastics may release toxic fumes.

Use "B" rated extinguishers on flammable liquids, gases and greases: motor oil, paint thinner, dry cleaning agents, gasoline, propane, natural gas, etc.

Use "C" rated extinguishers when live electrical equipment is involved, to prevent possible shock or electrocution.

"D" rated extinguishers are for use on metal fires such as sodium and magnesium. More specific information will be found on the nameplate.

NOTE: Use these extinguishers only as indicated by the symbols. Improper application can be hazardous. Example: Water (Class A) applied to an electrical (Class C) fire could shock or kill the fire fighter.

Each extinguisher nameplate shows the Underwriters Laboratories rating granted for that extinguisher. The rating system includes letters (discussed in the "Symbols" section) and numbers.

Ratings

Ordinary Class A Ratings: The number preceding the "A" indicates the number of 1½ gallon containers (of water, soda acid, or foam) that the extinguisher is equivalent to in fire fighting capacity.

Class B Ratings: The number preceding the "B" indicates the relative fire extinguishing potential of the extinguisher when used on a flammable liquid fire. For details regarding extinguisher placement consult NFPA-10, "Standard for Portable Extinguisher."

Class C and D Ratings: Neither "C" nor "D" ratings have numbers with them. The agent is only classified as acceptable for "C" or "D" applications. Additional information may be available on the extinguisher nameplate.

Example: An extinguisher rated 4-A:20-B:C — is roughly equal to four 1½ gallon containers of Class A agent (or five gallons); is rated for a 20 square foot Class B fire when used by a non-expert; the agent is safe for use in electrical fires; and the agent should not be used on burning metal (no "D" rating is indicated).

ANSUL THE ANSUL COMPANY, MARINETTE, WI 54143
PART OF WORMWORLD INTERNATIONAL GROUP

Important Information for Fire Extinguisher Owners

DEBRIEFING

Each individual debriefed should be prepared to answer the following questions at a minimum:

- (1) What was accomplished on work as compared to the plan?
(Answer should allow mockup of work package and note any additional tasks performed).
- (2) Did you notice any differences between plant configuration and the documentation you used to prepare for the work?
- (3) Was your training adequate?
- (4) Were equipment and manning satisfactory for the job?
- (5) Did you notice any safety problems?

Any additional comments should be referred to your Task Coordinator or Job Foreman.

TYPICAL ENTRY DAY SUMMARY

1. Report to assembly area.
2. Review schedule for the day, noting your scheduled time for dressing and dose pull point.
3. Attend pre-job briefing for your work package and the RWP briefing; record name on attendance sheets.
4. Stand by until you are notified to dress; if you leave for any reason obtain permission from Bechtel or designated coordinator for logistics.
5. Dress when called; an assistant will complete the dressing checklist.
6. Check in at control point with dressing checklist; read RWP and note requirements, sign on RWP (RWP's if applicable; each time you switch RWP's in containment you must give a final dosimeter readings).
7. Test radio and enter ante room when directed.
8. Inventory equipment and notify Command Center when ready to enter airlock.
9. Enter airlock when directed.
10. Notify Command Center when ready for entry.
11. Enter reactor building when directed and perform work.
DO NOT OPEN INNER DOOR UNLESS DIRECTED BY COMMAND CENTER.
12. Exit when work is complete or other exit criteria are established. You do not need permission to open airlock doors unless door interlock is defeated.
13. Undress in ante room and frisk out. If you become contaminated inform the Command Center.
14. Sign off RWP.
15. Take schedule break, lunch, etc. ; replace body fluids.
16. Attend scheduled debrief; if in doubt as to time or place call individual concerned on the daily schedule.
17. Satisfy any bioassay or whole body count requirements.
18. HP's document surveys at next available opportunity and submit to HP Foreman.
19. All personnel insure bioassay bottles are returned to Admin Building - Room 133 (Ext. 8473).

APRIL 28, 1982

C

① HP SURVEY

② AIRLOCK INSPECTION

③ REPAIR CCN #6, B

④ TEST SMOKE DETECTORS

⑤ INSTALL IN-CORE PUMP

⑥ TRASH REMOVAL

NOTE ON THIS SCHEDULE:

- A) BRIEFING TIME
- B) DRESS OUT START TIME
- C) DOSE ESTIMATE & PULL POINT
- D) DEBRIEF TIME / LOCATION / DEBRIEFER

D-A3-84

ATTACHMENT D-4

PRE-JOB BRIEFING OUTLINE

PRE-JOB BRIEFING OUTLINE

A pre-job briefing shall be conducted prior to initiating work per this Work Package. This briefing shall be scheduled to occur within two hours of crew entry into the Containment Building. The purpose of the pre-job briefing is to reinforce important aspects of the formal training program and it should not be construed to be a substitute for formal training. The following items shall be discussed with personnel preparing to enter the Containment Building to perform work per this Work Package:

- (1) Administrative control of the work
- (2) Scope and purpose of this entry
- (3) Conditions which dictate an exit from the Containment Building
- (4) Emergency Procedures
- (5) Communications
- (6) ALARA considerations
- (7) Contamination control
- (8) Individual and team responsibilities
- (9) Reinforcement of techniques for specific, difficult operations as determined in Training Program.
- (10) A review of the type questions which will be asked during debriefing..

Page 3 of 3

TYPE: ☐ GENERAL ENTRY TRAINING REV. _____
☒ WORK PACKAGE _____ TITLE: _____
☒ BRIEFING SUBJECT: JOB BRIEFING
 OTHER _____

[illegible]

Training Time: _____ HRS

ORIGINAL ~~IN~~ Master Lesson Plan
COPY TO: ~~IN~~ Individual Qualification Record Folder

EXHIBIT 2

JOB BRIEFING CHECKLIST

- ✓
- ☐ 1. Reason for job brief (10 CFR 19).
 - ☐ 2. Discuss exact work location, including access and egress routes.
 - ☐ 3. Review work to be accomplished, ensuring workers are familiar with and capable of performing the intended operation and expected results.
 - ☐ 4. Ensure the availability of necessary tools and equipment prior to entry into work area.
 - ☐ 5. Emphasize the performance of as much work as possible outside the radiologically controlled areas.
 - ☐ 6. Ensure workers are familiar with the work associated documents including sign off requirements.
 - ☐ 7. Review methods of disposition of contaminated waste and equipment.
 - ☐ 8. Discuss emergency actions to be taken if contingencies arise, including exit routes.
 - ☐ 9. Review exit criteria.
 - ☐ 10. Discuss communications required.
 - ☐ 11. Emphasize workers should contact command center for unusual conditions.
 - ☐ 12. Discuss authorizations for entry of Reactor Building.
 - ☐ 13. Review workers dose pull points and Daily Entry Schedule.
 - ☐ 14. Review radiological conditions of work area.
 - ☐ 15. Discuss limits and precautions.
 - ☐ 16. Status of closed circuit television system.
 - ☐ 17. List any specific items requiring discussion not described above:

EXHIBIT 2

CONTAINMENT ENTRY JOB BRIEFING

1. Work Package _____ WP NO. _____
2. Task Supervisor: _____
3. Task Supervisor complete Work Package Briefing using page 2 as a guide; check applicable items discussed.

Comments:

4. Radiological Controls complete any required radiological briefing; check applicable item discussed on page 2.

Comments:

5. Authorized additional work items not covered in Work Package:

6. Task Supervisor complete page 3; attendees sign

7. Completed

_____ Task Supervisor	_____ Date	_____ Time
--------------------------	---------------	---------------

_____ Radiological Control	_____ Date	_____ Time
-------------------------------	---------------	---------------

8. Task Supervisor forward to Entry Supervisor

9. Reviewed/Approved:

_____ Entry Supervisor	_____ Date	_____ Time
---------------------------	---------------	---------------

ATTACHMENT D-5
POST-JOB DEBRIEFING OUTLINE

POST-JOB DEBRIEFING OUTLINE

The post-job debriefing is intended to assimilate, as quickly as possible after performance, descriptive information of conditions as they exist within the Containment Building, adequacy of planning, adequacy of equipment, and other information which might be useful to improve future operations. Questions asked during the debriefing shall include, but not be limited to the following:

- (1) Was the hands on training adequate?
- (2) Did you feel sick at any time during the entry?
- (3) Did you feel fatigued at any time during the entry?
- (4) Did you have any difficulty in communicating with the Command Center or each other?
- (5) Did you notice any tripping hazards not properly identified?
- (6) Did you notice any overhead hazards not properly identified?
- (7) Were the hot spots properly marked?
- (8) Was the lighting adequate?
- (9) Did you find the floors or stairs slippery?
- (10) Did you notice any rips in your PC's?
- (11) Did you experience heat stress?
- (12) Did the cooling vest help?
- (13) Were there any obstructions which prevented you from following the prescribed path?
- (14) Did you experience any breathing difficulties?
- (15) Do you feel a safety harness would be desirable?
- (16) Were any of the drains plugged?
- (17) Did you experience any difficulty in seeing because of fogging?
- (18) Did the shut-off valve work properly?
- (19) Did you notice any wearing out of the nozzle?

- (20) Did you experience any clogging of the nozzle?
- (21) Did you feel that you were burned or otherwise made uncomfortable by the hot water?
- (22) Did you experience excessive splashing?
- (23) Qualitatively, which pressure and flow rate do you feel did the best job?
- (24) Was the spray wand of adequate length?
- (25) Was the spray nozzle hard to handle at the high pressure and high flow rate?
- (26) Would a shoulder rest be helpful for the gun?
- (27) Did any of the hoses kink or become unwieldy?
- (28) Did you experience any inadvertent uncoupling of the hoses or nozzles?
- (29) Did you have difficulty in operating the wet vacuum?
- (30) Was the water floor scrubber difficult to handle?

In addition to the above questions, a critique of individual performance should be conducted utilizing the videotapes where possible. Particular attention should be directed to adequacy of techniques used.

DEBRIEFING QUESTIONS*
(NEW GENERALIZED FORMAT)

1. What was accomplished on the work package (WP) as compared to the plan?
2. Did you perform additional work not related to your work package?
(Procedure should allow markup of work package and notes on any additional tasks performed.)
3. Did you notice any differences between plant configuration and the documentation you used to prepare for the work (drawings, WP, etc.)?
4. Were there any abnormal occurrences?
5. Was your training adequate?
6. Were equipment and personnel satisfactory for the job?
7. Did you notice any safety problems?
8. Do you have any other comments?
9. Do you have any recommendations which will improve the Containment Entry Program?

*Each entry team number should be asked debriefing questions.

ATTACHMENT D-6
HEAT STRESS PROGRAM

Heat Stress Control Program
Three Mile Island Nuclear Station
GPU Nuclear Corporation

Prepared By:
B. A. Parfitt
J. S. Schork

Introduction

Individuals who work in the nuclear power plants are exposed to a variety of chemical and physical stresses. One of the most significant physical stresses to which workers are exposed is a result of working in hot environments. The most obvious sources of heat stress are high air temperatures and radiant heat sources inherent to an operating power plant. Another more subtle, and less easily defined, source of heat stress results from the use of heavy protective clothing required to protect workers from radioactive contamination. Even at relatively low ambient temperatures, heavy protective clothing reduces heat losses through the normal mechanisms of radiation, convection, and sweat evaporation. Impermeable clothing, frequently used to protect workers from the high level contamination resulting from the Unit II accident, is particularly effective in reducing heat loss since it eliminates the evaporative cooling normally provided by the sweat process. Individuals who must work for extended time periods in this type of clothing tend to store heat generated during work activities, resulting in an increase in body temperature and an increased risk of developing a heat related illness. Recognizing this problem, the GPU Nuclear Safety and Health Department has implemented a comprehensive program designed to reduce the occurrence of heat related illnesses through the use of worker training, physiological testing, administrative controls, and personal cooling garments. The following is a brief description of the current program and some potential modifications to the program which are currently under study.

Training

A fundamental part of any program aimed at controlling exposure to chemical and physical stresses is employee training. This is particularly important with regard to heat stress. Individual response to heat is so highly variable that even the most sophisticated heat stress index cannot eliminate the possibility that a heat related illness will occur. Because of this individual variability, the ultimate decision as to when work can no longer be performed safely in a hot environment rests with the worker's evaluation of his own condition. It has always been the policy of GPU Nuclear that when a worker begins to feel ill while working in a hot environment, the individual is to immediately remove himself from that environment and notify his supervisor. However, in order for an individual to properly assess his condition, he must have a fundamental understanding of how the body regulates heat, the early symptoms of heat related illnesses, the potential consequences of those illnesses, first aid procedures used to treat heat related illness, and preventive measures which can be taken to reduce the possibility of developing a heat related illness. Providing the worker with this information is the major goal of our training program.

Attachment 1 is a copy of our employee training handout on heat stress. It has been distributed and verbally presented at plant and contractor safety meetings. In addition, it has been incorporated into the training program which all personnel are required to receive prior to making a Unit II Reactor Building entry. Worker feedback from this training has been excellent. There have been several instances where personnel have been able to note early symptoms of heat related illness and were able to terminate their entry prior to the onset of any debilitating effects from the heat.

Physiological Testing

Because working in a hot environment places a great deal of stress on a worker and reaction to this stress can be significantly affected by a number of health problems, it is essential that some type of screening process occur prior to placing personnel in positions which involve exposure to heat stress. By eliminating exposures to individuals who have a higher risk of developing a heat related illness because of other health problems, the risk of injury or illness due to work in hot environments is reduced for the general workforce as well as the individual.

All workers at Three Mile Island, whose job duties require the use of respiratory protection devices, must pass a physical examination administered by a physician at the Site Medical Department. Although this examination is intended primarily to ensure that individuals are physically capable of wearing respiratory protection it does provide us with a basic overview of the individual's general health. In addition, since heavy and impermeable protective clothing is almost exclusively used in conjunction with respiratory protection, this physical examination provides us with a mechanism of evaluating those individuals most severely exposed to heat stress. The examination consists of the gathering of a brief health history, pulmonary function and cardiovascular measurements, and a hands on examination by a physician. Particular emphasis is placed on detecting pulmonary and cardiovascular abnormalities which may affect the individual's ability to safely wear respiratory protection. Such abnormalities would, of course, also increase the risk of ill effects during exposure to heat. The format and criteria utilized in this physical can be found in Attachment 2.

Impermeable clothing is used most extensively to protect personnel entering the Unit II Reactor Building from high levels of radioactive contamination. Due to the large heat stress placed on individuals who must wear this type of clothing and the potential delays and complications in providing treatment to individuals who may become ill in this environment, it was felt that additional testing to screen individuals who may be unusually susceptible to heat stress would be advantageous. Although no definitive test for doing this currently exists, research of literature pertaining to the subject indicates that two parameters which would be indicative of heat storage within the body which can be measured are body core temperature and heart rate recovery.^(1,4)

Rectal temperature is the most effective means of determining body core temperature. However, rectal temperatures are difficult to obtain at an industrial site. For this reason many investigators use oral temperature as an indication of deep body heat storage, using an oral temperature of 37.6°C (99.6°F) to correspond with a deep body temperature of 38°C (100.4°F).^(1,4) This is the criteria we have utilized in our program. The procedure utilized in performing heat stress susceptibility testing is found in Attachment 3.

The pulse rate of a worker reflects the combined demands of environmental heat, work level, elevation of body temperature and cardiovascular fitness. Initially high heart rates which recover quickly during rest are indicative of a high metabolic rate but little heat storage. High heart rates which fail to recover during the rest period indicate that in

addition to demands created by the work output, an additional stress is placed on the cardiovascular system in trying to shed stored heat. Therefore the amount of heart rate recovery is a good indication of how much heat storage occurred during a given work period.

The test consists of having a worker walk at a comfortable pace for one hour while wearing impermeable clothing similar to that worn in the actual containment entry. The individual then performs a moderate walking and step climbing exercise for one hour, simulating a 150 kcal/hr metabolic rate. With average winter temperatures of 65°F in the exercise area, calculation of the heat stress incurred using the method developed by Kamon et. al.⁽³⁾ shows that 58.17 kcal of heat would be stored resulting in an expected oral temperature rise of 1°F for an average person. After the exercise, the individual is instructed to remove the protective clothing and oral temperature and recovery heart rates are measured. An oral temperature exceeding 100.4°F and a heart rate which does not recover by 10 beats per minute during the three minute recovery period indicates that abnormally high heat storage occurred, and the individual's thermoregulatory mechanisms are substandard. Such individuals have an increased risk of incurring a heat related illness and are disqualified from performing work in the containment building while wearing impermeable clothing. Additionally, an irregular pulse rate is also a disqualifying criteria as it indicates that the combination of work load and heat load placed too much stress on the circulatory system. Disqualification resulting from this test only excludes the individual from wearing impermeable clothing in the containment building. He may perform tasks in the building which do not require the use of impermeable clothing.

This testing program provides a reliable method of screening individuals with high susceptibility to heat stress, however, its major drawback is the length of time required to perform it. This time factor limits the use of this screening test to the containment entry program.

A much more convenient test would be one of short duration which could be administered at the site medical facility. We are currently working with Dr. Elizier Kamon of Penn State University to develop such a test, and to use data collected in our current program to evaluate its effectiveness. The availability of a quick, simple test will allow us to expand the program to other projects requiring significant exposures to heat stress.

Administrative Controls

The most common method of regulating exposure to heat stress is through the utilization of administrative controls. This is particularly true in nuclear power plants where work locations change on a daily basis. In addition, manipulating environmental conditions to promote greater body heat loss is of limited benefit since massive changes would be required before heat exchanges through protective clothing would be significantly affected. Although no definitive heat stress guideline currently exists, particularly with regard to protective clothing, we have developed guidelines to assist supervisors and workers in judging how long work can safely be performed in hot environments.

The guidelines currently being utilized are contained within the GPU Nuclear-Heat Stress Exposure Safe Work Practice (Attachment 6). The guidelines are based on operational experience with protective clothing coupled with theoretical considerations adapted from the Heat Stress Index developed by Belding and Hatch. Although the guidelines are not a rigorous mathematical model of the heat transfer which occurs during the use of protective clothing they have been beneficial in that the few heat related illnesses which have occurred have been isolated and usually traceable to a pre-existing medical condition. As new guidelines and methods of evaluating heat stress become available our guidelines will be reevaluated and modified as necessary.

One of the newest and most promising methods of evaluating heat stress has been recently developed by Dr. Elizier Kamon of Penn State University.⁽³⁾ Dr. Kamon uses mathematical equations to describe the different types of heat transfer which occur between an individual and the surrounding environment. What makes this method particularly useful in our application is the inclusion of factors which describe the effect of protective clothing on this heat transfer. Initial comparison of our guidelines with Dr. Kamon's method is favorable; for the most part our guidelines are more conservative. However, there are some instances where significant discrepancies exist. This is to be expected since our guidelines must be simple and general to find practical field use. There are also some problems with Dr. Kamon's method in regard to accurately choosing the insulating values for different types of protective clothing and incorporating the additional stress placed on a worker utilizing respiratory protection. We are continuing to work with Dr. Kamon to resolve these problems and to incorporate his method into a more comprehensive yet field-usable set of guidelines.

Personal Cooling Systems

Early into the TMI Recovery Program for the Unit II Reactor Building it was realized that the high levels of loose radioactive contamination would require the use of extensive protective clothing by entry personnel. While there was no doubt that layered protective clothing would protect workers from becoming contaminated, it was recognized that these same layers of clothing would impose a potentially serious heat stress burden.

Initial methods used to prevent workers from becoming ill as a result of heat stress incurred while wearing protective clothing concentrated on three basic techniques:

1. Medical screening of personnel prior to Reactor Building entries
2. Education of workers in the recognition of the hazards and symptoms of heat related illness.
3. Imposition of work time limits

While these methods did provide protection for the workers, they were less than completely successful. Some members of early entry teams terminated their tasks prematurely due to heat stress. Some personnel completed their assigned tasks but became slightly ill upon exiting the Reactor Building. One person suffered extensive dehydration and required short term hospitalization (one day).

After each heat stress incident, action was taken to further protect workers. Some protective clothing requirements were reduced, work time limits were shortened, and attempts were made to acclimate workers to heat stress by conducting pre-entry mock-up simulations of assigned tasks. Each of these actions did provide a better margin of safety for workers exposed to heat stress, however, problems still remained.

The loosening of protective clothing requirements created an increased risk of having personnel contaminated with radioactive material. Work time limits were reduced to the point that they severely hindered productivity and ALARA objectives. Task simulations became so extensive that the time spent preparing for an entry required a 3-4 week lead time. The methods in use had reached the limits of their ability to protect workers from heat stress.

Clearly, the problem was: How can we protect a heavily clothed worker who must perform work in an expeditious manner from becoming overheated. After a review of current technology, it was determined that the utilization of body cooling systems was the most effective means of controlling heat stress imposed by protective clothing.

Body cooling systems can be divided into two basic categories:

Body Cooling Devices
Body Cooling Garments

Body cooling devices produce a flow of cool air which is introduced close to the skin to remove body heat through convection and increased sweat evaporation. The most common body cooling device is the Vortex tube.

Vortex body cooling devices have been utilized in several industries where protective clothing is utilized in hot environments. In an effort to determine the feasibility of using these devices at TMI, they were tested in the small scale decontamination experiment conducted in May, 1981. The cooling effect produced by the Vortex tube successfully protected the workers from heat stress, however, there were several logistical and operational problems which hindered extensive use of these devices. The part of the Vortex tube located outside the protective clothing became contaminated with radioactive material and was not able to be decontaminated. In addition, the volume of service air required to operate the Vortex tubes is very large. The plant service air system is not large enough to supply compressed air to several workers utilizing these tubes at one time. Finally, the umbilical nature of the hoses supplying air to these systems restricted mobility and location of workers.

The sum of the logistical and operational problems associated with Vortex tubes directed our attention to body cooling garments. Three types of body cooling garments were examined. Two garments, the "Cool Vest" manufactured by ILC Dover Inc., and the "Cool Head" manufactured by Life Support Systems, act on the same basic principal. They consist of close fitting garments through which water is pumped, dumping body heat into frozen ice or chemical packs. The major disadvantages of these systems are their cost, inability to decontaminate the garments and pumps, and the need for regular pump maintenance.

The last type of body cooling garment examined is an ice vest-type garment that has 60-80 pockets into which small packets of ice are placed. As the skin temperature increases, heat flows into the ice packets, eventually melting the ice. The amount of heat consumed in this process is equal to the heat of fusion of the weight of ice utilized. This garment, developed under an EPRI grant, is manufactured by Ergocon. Ergocon is headed by Dr. Elizier Kamon, Penn State University, the developer of the ice vest and author of numerous articles and publications concerning the evaluation and control of heat stress. The ice vest was found to be the most useful of the three body cooling garments. It is cheaper, simpler to maintain, and easier to use on a continuing basis.

Six prototype ice vests were ordered and placed into use during the summer of 1981. They have proved to be very useful in diminishing our heat stress problems. While the heat sink provided by the ice packets is limited, it is large enough to allow most tasks to be completed with as many layers of protective clothing as is necessary. Recently, Dr. Kamon visited TMI to perform a field evaluation of the ice vest. Heart rates and rectal temperatures were measured during a pre-entry mock-up without the vest and during an actual entry with the vest. The results of this testing can be found in Attachments 4 and 5. Rectal temperature stayed consistently lower during use of the ice vest while heart rate fluctuated due to differences in work load. Subjective comments provided by workers utilizing the vest also indicate they have been successful.

We are still working on the logistical and operational problems of using the ice vests throughout TMI. The plastic packets of ice tend to crack and leak. The rip stop nylon vests have become unraveled after several washings. The cleaning of the vests on a regular basis is somewhat of a problem since there is no clean non-contaminated laundry at TMI at this time. We are continuing attempts at solving these problems and hope to extend the use of ice vests to other projects at our facilities.

Conclusions

The program we have established for controlling heat stress is based on the best knowledge currently available. We are constantly studying new evaluation and control techniques and expect to modify the program as new information becomes available. Although it has been an effective program, there is always room for improvement. The more effective the program becomes, the more expeditiously and safely workers can perform the clean up of TMI Unit II and other maintenance tasks at our facilities.

References

- 1) Fuller, Frank H. and Smith, Paul E. Jr., "Evaluation of heat stress in a hot workshop by physiological measurements," American Industrial Hygiene Association Journal, Vol. 42, No. 1, pp. 32-37. 1981
- 2) The Industrial Environment, It's Evaluation and Control, National Institute for Occupational Health and Safety, U.S. Department of Health, Education, and Welfare. 1973
- 3) Kamon, E. and Ryan, C., "Effective heat strain index using pocket computer," American Industrial Hygiene Association Journal, Vol. 42, No. 8, pp. 661-615. 1981
- 4) Mihal, C. P. Jr., "Effects of heat stress on physiological factors for industrial workers performing routine work and wearing impermeable vapor - barrier clothing," American Industrial Hygiene Association Journal, Vol 42, No. 2, pp. 97-103. 1981

ATTACHMENT 1

WORKING IN HOT ENVIRONMENTS

Heat is a naturally occurring stress under which human beings have evolved over the ages and to which each of us is exposed at least periodically during our lives. Industrial heat exposure, however, frequently is much greater than that encountered in the natural environment. Hot industries also involve hard physical work which adds to the total heat stress. The effect or consequences of heat stress in the work environment can be seen in decreased worker productivity, increased accident rates, illnesses, and fatalities. The primary concern of this discussion is the control of heat stress, the prevention of heat-related illness and death.

The body is continually producing heat every second that it lives. This heat comes from the breakdown of food that the body uses to supply the energy it needs to support its life processes. About 75% of the energy consumed by the body ends up in the form of heat which in turn heats up the body. Increased physical activity produces even more body heat. To maintain a normal acceptable body temperature, this heat must be brought to the skin surface and exchanged with the air surrounding the body. The physiological process which maintains the balance between heat production and heat removal is a complex one involving the central nervous system, the circulatory system, the skin, and the muscles. The situation is similar to the working system for the automobile engine. In the engine, energy and heat are produced in the block. Water is pumped through the block where it absorbs heat, then through the radiator, where the heat is exchanged with the atmosphere. The rate of circulation is controlled by a thermostat, which opens when the engine is hot. Similarly, in the body the blood carries heat from the core of the body to the skin. The amount of blood flowing to the skin can be increased or decreased. The rate of heat loss can be increased if necessary by wetting the skin with sweat. When water evaporates, the water molecules absorb a large quantity of heat. The heat gained by the water molecules as they evaporate is lost from the wetted skin surface. Under conditions of excessive heat stress, this evaporative cooling becomes the major avenue for achieving heat balance. The body's cooling system is remarkably efficient and can adjust to steady work in hot environments. This adjustment is called acclimatization and is usually completed in a week. Despite the adaptability of the body's cooling system, it can be overloaded by certain extremes in environmental conditions and physical activity.

Heat stress problems arise when the body produces more heat than it can get rid of. When this happens, a variety of illnesses can occur depending on the duration and severity of stress and the effectiveness of steps taken to relieve the stress. These include:

Heat Exhaustion

Heat exhaustion is caused by an insufficient blood flow to the brain because too much blood has been diverted to the skin in an effort to cool the body. During heat exhaustion, body temperature is usually normal and the skin is cool, wet, and pale. The major symptoms are giddiness, headache, weakness, fainting, vomiting, and a rapid, weak pulse. Rest in a cool environment and fluid replacement will result in full recovery. This type of heat illness is usually caused by inadequate fluid intake to make up for the body water lost in the sweat.

Working in Hot Environments

Dehydration

The water lost from the body as sweat must be replaced by drinking water if dehydration is to be prevented. Dehydration rapidly leads to decreases in performance and work capacity and to heat exhaustion. Sweat production of 8 to 10 quarts each working day is not uncommon in hot industries. This means that water must be replaced at the rate of at least 1 quart each hour. When sweating is heavy, a better practice is to drink about a cup of cool (not cold) water every 10-20 minutes throughout the work day.

Heat Stroke

Heat stroke results from a high body temperature that is caused by a failure of the body's cooling system. The high body temperatures accompanying heat stroke can be fatal if they are not lowered. Usually, collapse and coma with high body temperature are the first symptoms, and the victims skin may be red, hot, and dry. Treatment consists of rapid reduction of the body temperature by immersion in ice bath, alcohol spray, or fans and wet sheets. Age, obesity, lack of physical fitness, and hard physical work are factors that increase the chances of heat stroke. Heat stroke is a serious medical emergency and requires speedy medical attention to save the victims life.

Heat Cramps

Heat cramps result from excessive loss of salt in the sweat without adequate replacement. Heat cramps involve mainly the hand, arm, leg, and abdominal muscles. Heat cramps are not very common and occur mostly when sweating is heavy, water replacement is adequate, but salt intake is low. A little salt added to the drinking water or the food is an effective treatment and prevention of heat cramps. For heat adjusted (acclimatized) workers the usual diet contains enough salt because their sweat is low in salt. Moderation is needed when increasing salt intake because too much salt actually reduces heat tolerance, and for persons with high blood pressure, increased salt intake can actually aggravate the condition to a dangerous level. Drinking Gatorade is the best and safest way to maintain fluid and salt balance at the same time.

The conditions found at TMI are normally within the range that your body's heating/cooling system can handle. The range limits may be exceeded when doing hard work during hot weather or when wearing protective clothing in hot contaminated areas. When necessary, the safety department will measure the environmental conditions in a hot area to see if control measures must be instituted. The early symptoms of heat stress are:

Weakness	Nausea
Extreme fatigue	Headache
Dizziness	Thirst

More advanced symptoms are:

Arm, leg, and stomach muscle spasms	Extreme Thirst
Irregular or increased heartbeat	Fainting

Working in Hot Environments

If you note early signs of heat stress, notify your supervisor. The immediate treatment is to:

Rest in a cool place

Drink small amounts of cool water frequently

If symptoms continue, get medical help from First Aid

Don't expect to work at your normal pace for the first few days in a hot area. If your body is allowed to accustom itself to heat stress areas gradually (acclimatization), within a week or so you will be able to stand a full shift of hard work in a hot area with few ill effects. If you have any further questions about heat stress, contact the First Aid office.

Safety & Health Department

Medical Examination: RESPIRATORY CLEARANCE REPORT

Effective Date:

Page 1 of 2

PURPOSE

To annually physiologically qualify an individual to wear respiratory protection.

APPLICABILITY

All personnel, including non-GPU Nuclear personnel, required to wear respiratory protection.

SCHEDULING AND NOTIFICATION

The Safety & Health Department shall schedule upon receipt of notification from supervision that such examinations are due.

EXAMINATION CRITERION

Examination performed to meet the requirements of NUREG 0041 and 29 CFR 1910.134.

DISQUALIFYING CRITERIA

EARS:	Ruptured Eardrum Otitis Media Any infection noted on ear canals. Eardrums cannot be visualized due to excessive wax.
THYROID:	Enlargement History of thyroid disorder
HEART:	Abnormal rhythm Tachycardia > 100 at rest Murmurs Blood Pressure $> 140/90$
LUNGS:	FVC $< 75\%$ of predicted value FEV ₁ $< 75\%$ of predicted value History of chronic lung disease, emphysema, TB, asthma and under no physician's care at this time.

QUALIFYING CRITERIA

Eardrum Intact No present infection noted
Normal size
Normal rate ≤ 100 Asymptomatic Blood Pressure $\leq 140/90$
FVC $\geq 75\%$ FEV ₁ $\geq 75\%$

Medical Program

Safety & Health Department

Medical Examination: RESPIRATORY CLEARANCE REPORT

Effective Date:

Page 2 of 2

MEDICAL OPINION AND DETERMINATION

Shall be determined by the examining physician in accordance with established company criteria.

FORMS AND TESTS TO BE COMPLETED

GPUN A0000878 (initial)
GPUN A0001173 (annual update)
GPUN A0000882
Spirometry Graph

RECORDS

Maintained by the Safety & Health Department for thirty years post termination of employee. Hard copy for one year and microfiche thereafter.

Concurred: _____
Physician's signature

Respiratory Physical Examination Health History

Name _____ Height _____ in. _____ cm. Weight _____ lbs.
(Please Print)

Age _____ Pulse _____ B/P _____ Sex _____ Race _____

A. History:

Yes No

1. Have you ever been told you have or had a lung disease? _____
2. Do you usually cough first thing in the morning? _____
3. Do you usually cough during the day or at night? _____
4. Do you usually bring up any phlegm first thing in the morning? _____
5. Do you usually bring up any phlegm during the day or at night? _____
6. Are you ever short of breath? When? _____
 - a. Hurrying on level ground? _____
 - b. Walking up a slight hill? _____
 - c. Walking up your own pace on level ground? _____
7. Do you ever get wheezing or whistling sounds in your chest? _____
8. Do you currently smoke tobacco? _____
 - a. If yes, how much? _____ packages a day, etc. _____
 - b. If no, have you ever previously smoked tobacco? _____

B. Past Medical History:

1. Did you ever have any serious illnesses? _____
If yes, What and When _____
2. Did you ever have any operations? _____
If yes, What and When _____
3. Are you allergic to any foods, medications, or substances? _____
If yes, What _____
4. Do you take any medications at this time? _____
If so, What _____

C. Occupational History:

1. Have you ever worked in any of the following:
 - a. Foundry? _____
 - b. Stone quarry or mineral mining? _____
 - c. Asbestos mill, processing or handling asbestos? _____
 - d. Cotton Flex or Hemp mill? _____
 - e. In close proximity to other dusts or chemical fumes? _____

D. Vision:

1. Do you need corrective lenses to see? _____
2. Are they needed for reading? _____
3. Do you have bifocal lenses? _____
4. Was your last eye examination within two years? _____

E. Cardiac History:

1. Have you ever had high blood pressure? _____
2. Have you ever been told you had heart disease? _____
3. Have you ever had a heart attack? _____

If so, When _____

F. Heart _____ H. Heart _____

G. Thyroid and Neck _____ I. Lungs _____

Employee's Signature _____

Respiratory Health History Update

Name _____ SS# _____

	Yes	No
A. Has there been any significant change in your health since the last exam? If so, what type of change? _____	_____	_____
B. Have you ever had any tests involving radioisotopes?	_____	_____
C. Have you ever been or had a tendency to be claustrophobic?	_____	_____
D. Are you taking any medication at present? If so, what? _____	_____	_____
E. Are you a smoker? Were you a smoker? If you stopped smoking, when did you stop? _____	_____ _____ _____	_____ _____ _____
F. Is there any reason you should not be qualified to wear a respirator? If so, what? _____	_____	_____
G. Have you seen a physician for any ailments, illnesses, or injuries in the past year?	_____	_____

Employee's Signature _____

HEENT _____ Heart _____

WT _____ BP _____ P _____

Thyroid & Neck _____ Lungs _____

Physician's Signature _____

Subject: Physician Respiratory Examination Report

To: J. K. Venet, R. N.

☐ Based on the evidence obtained in this screening, in the examiner's opinion, the following person can wear a respirator or other breathing device while exercising duties, subject to successful completion of a respirator training program.

Name: _____

S. S. No. _____

Date: _____

Company: _____

☐ The above named individual is disqualified from wearing a respirator at this time due to the following reason(s).

Doctor: _____

Date: _____

A0000882

ATTACHMENT 3
PROCEDURE FOR CONDUCTING
HEAT STRESS SUSCEPTIBILITY TESTING
FOR TMI UNIT II CONTAINMENT ENTRIES

The following procedure is to be utilized during heat stress susceptibility testing conducted prior to containment entries. By ensuring that all personnel use the same technique, our results should remain consistent.

1. Only workers wearing complete wetsuits (full tops and bottoms) should be monitored for heat stress.
2. The worker should be instructed to walk through the TMI Unit II Turbine Building at a comfortable pace for one hour while wearing the following protective clothing:
 - 2 Pair Cotton Coveralls
 - 1 Plastic Rain Suit
 - 1 Cloth Hood
 - 1 Pair Rubber Gloves
 - 1 Pair Plastic Booties
 - 1 Full Face Respirator with HEPA Filter
3. Upon completion of the exercise, the worker should be instructed to remove all protective clothing down to the first set of coveralls. The first set of P.C.'s should be unzipped to allow heat to escape. Removal of boots is not necessary.
4. When the worker has finished the desuiting phase outlined in Item 3, he should then be instructed to sit down and the oral thermometer should be inserted. This starts the three-minute clock.
5. The pulse rate should then be taken during the last 30-second period of each of the three minutes. These readings will be labeled P_1 , P_2 , P_3 .
6. At the end of the three-minute period, the oral thermometer should be read.
7. The following criteria shall be utilized in determining if the worker has adequately recovered from the heat stress incurred.

ORAL TEMPERATURE	$P_1 - P_3$	ACTION REQUIRED
Less than 100.4	Greater than or equal to 10 beats/min	Qualifies - Minimal Strain Incurred
Less than 100.4	Less than 10 beats/min	Qualifies - No Time Extensions
Greater than 100.4	Greater than or equal to 10 beats/min	Qualifies - No Time Extensions
Greater than 100.4	Less than 10 beats/min	Disqualified from Task

8. Heart rate recovery criteria of 10 BPM assumes a P_3 greater than 90 BPM. A P_3 of less than 90 BPM indicates no significant strain and a 10 BPM recovery would not be expected.
9. When a worker's oral temperature exceeds 100.4°F and the pulse does not recover by 10 BPM during the three-minute period, it means that he is not qualified to perform work in the Containment Building while wearing a wet suit.
10. Extremely abnormal conditions, i.e, temperature greater than 101.5°F or a heart rate above 120 BPM 10 minutes after being undressed, shall be brought to the attention of the Health Services Administrator.
11. When warm weather arrives the duration of the exercise will be adjusted, based on temperatures in the Turbine Building.

ATTACHMENT 4

HEAT STRESS EXPERIMENT

D-A6-19

ATTACHMENT 5

HEAT STRESS EXPERIMENT

D-A6-20

ATTACHMENT 6
HEAT STRESS EXPOSURE

These requirements establish work time guidelines for workers exposed to hot environments before a rest period is given for recovery from heat stress.

Work time guidelines reflect the actual time protective clothing and/or respiratory protection are worn while performing work assignments and does not include suiting up, unsuiting or going to and/or from the work location. Breaks should follow exposure to heat stress. Duration of breaks, extent of clothing removal, and the area where breaks are taken, shall be at the discretion of supervisory personnel.

The following definitions apply:

ANTI-C'S	Paper or cotton coveralls, cotton hood, rubber boots, and gloves.
IMPERMEABLE CLOTHING	Rain suits, water resistant clothing.
RESPIRATORY PROTECTION	Negative pressure full-facepiece respirator, SCBA or supplied-air respirator.
SUPPLIED AIR HOOD OR SUITS	Hood or suit with at least 6 cubic feet per minute continuous air flow.
TEMPERATURE	Ambient temperature at a relative humidity of 75% at the work location.

If an extension of the work time guidelines identified herein is required, due to the nature or criticality of the task being performed, permission must be obtained from the supervisor in charge of the job.

Employee heat stress briefing, when required, should be arranged through and provided by the Site Safety & Health Department.

When work is planned in hot environments where relative humidities are known to be greater than 90%, the schedule for Anti-C's under Impermeable Clothing with Respiratory Protection shall be utilized.

When temperatures exceed 120°F or where hot radiant heat surfaces are encountered, direction shall be provided by the Supervisor - Safety & Health for personal protective equipment.

When an individual feels discomfort from heat stress, he/she must immediately notify the person in charge and leave the area.

HEAT STRESS - TEMPERATURE WORK LIMITS

<u>PROTECTIVE EQUIPMENT</u>	<u>TEMPERATURE</u>	<u>GUIDELINES FOR WORK TIMES</u>
Conventional Work Clothing	Less than 100°F 100 - 110°F 110 - 120°F	None 2 hours 45 minutes
Anti-C's (only)	80 - 90°F 90 - 100°F 100 - 110°F 110 - 120°F	3 hours 2 hours 1 hour 30 minutes
Anti-C's under Impermeable Clothing	80 - 90°F 90 - 100°F 100 - 110°F 110 - 120°F	1.5 hours 1 hour 30 minutes 15 minutes
Anti-C's (only) with Respiratory Protection	Less than 80°F 80 - 90°F 90 - 100°F 100 - 110°F 110 - 120°F	4 hours 2 hours 1.5 hours 1 hour 30 minutes
Anti-C's under Impermeable Clothing with Respiratory Protection	70 - 80°F 80 - 90°F 90 - 100°F 100 - 120°F	1 hour 45 minutes 30 minutes 15 minutes
Anti-C's with or under Supplied Air Hood/Suit	80 - 100°F 100 - 110°F 110 - 120°F	4 hours 2 hours 1 hour

By: _____

R. G. Ritthamel
Manager - Industrial Safety & Health

ATTACHMENT D-7
TRAINING PROGRAM EFFECTIVENESS EVALUATION

TRAINING PROGRAM EFFECTIVENESS EVALUATION

1. Is the objective being accomplished in a reasonable amount of time?
2. Is any work being repeated because workers do not understand or lack ability to perform a task? Do observations of workers from the command center also indicate this?
3. Is feedback on all problems being provided by workers?
4. Are problems a result of poor training?
5. Is a follow-up system used to correct known deficiencies? It is responsive to needs?
6. Is all training conducted against a prescribed standard?
7. Are standards maintained by:
 - o Control of lesson plan content?
 - o Use of qualified instructors?
 - o Periodic monitoring by training administrator?
 - o Revisions to lesson plans when required?
8. Are periodic audits conducted to evaluate the training system?
9. Is time set aside to develop and improve training standards?

ATTACHMENT D-8
TRAINING HOURS ESTIMATE BY MANPOWER SOURCE

TRAINING HOURS ESTIMATE BY MANPOWER SOURCE

Manpower Source	General Entry Training	Technique Development	Basic Decon Course	Radiation Instruments & Data	Special Equipment ^a	Safety Training	Work Package Classroom	Walk-Through	Full Mock or Prove Out	Heat Stress ^b	Special Respiration	Data Sheets	Final Briefing & Debriefing	Total Estimate by Source
HP Technicians														
First entry	4	0	NA	0	a	1	4	0	3	b	1	2	2	17
Thereafter	1	0	NA	0	a	0	2	2	0	b	0	2	2	9
With polar crane	NA	NA	NA	NA	1	8	NA	NA	NA	NA	NA	NA	NA	9
With data collection	0	0	0	0	a	0	2	1	0	b	0	2	2	7
Client maintenance														
First entry	4	4	NA	NA	a	1	4	4	4	b	1	1	2	25
Thereafter	1	4	NA	NA	a	0	4	2	0	b	0	1	2	14
With polar crane	NA	NA	NA	NA	1	8	NA	NA	NA	b	NA	NA	NA	9
Building trades														
First entry	4	16	NA	NA	a	1	4	4	4	b	1	1	2	37
Thereafter	1	16	NA	NA	a	0	4	2	0	b	0	1	2	26
With polar crane	NA	NA	NA	NA	1	8	NA	NA	NA	b	NA	NA	NA	9
As entry support technicians	1	40	NA	8	1	16	0	NA	NA	3	4	4	0	77 ^c
Remote reporters/volunteers for decontamination:														
One team/package	4	0	28	NA	a	1	4	4	4	b	1	0	2	48
Follow-on personnel	4	0	28	NA	a	1	2	2	0	3	1	0	2	43
Additional work packages	0	0	0	NA	a	0	2	2	0	0	0	0	2	6
With polar crane	NA	NA	NA	NA	1	8	NA	NA	NA	NA	NA	0	NA	9
For data collection only	4	0	NA	8	a	1	4	NA	NA	b	1	2	2	22

TRAINING HOURS ESTIMATE BY MANPOWER SOURCE (Continued)

Manpower Source	General Entry Training	Technique Develop- ment	Basic Decon Course	Radi- ation Instru- ments & Data	Special Equip- ment	Safety Training	Work Package Class- Room	Walk- Through	Full Mock or Prove Out	Heat Stress	Special Respir- ation	Data Sheets	Final Briefing & Debriefing	Total Estimate by Source
Contractors														
First entry	4	0	NA	8 ^d	a	1	2	2	4	b	1	1	2	25
Thereafter	1	0	NA	8 ^d	a	0	2	2	0	b	0	1	2	16
With polar crane	NA	NA	NA	NA	1	8	NA	NA	NA	NA	NA	NA	NA	9

a. Time to train depends on equipment and need:

Forklift - 2 hours
High reach - 2 hours
Portable videotape - 8 hours
Camera - 2 hours.

b. A heat stress test is also required if a full plastic wet suit is worn.

c. Entry support technicians are trained to provide a wide range of tasks:

Dress personnel
Undress personnel
Prepare and decontaminate equipment
Take data
Remove radwaste
Transport radioactive waste
Other miscellaneous logistics functions.

d. May not be required; depends on contractor function.

DO NOT MICROFILM
THIS PAGE

APPENDIX E
ORGANIZATION AND SUPPORT

CONTENTS

ORGANIZATIONAL RESPONSIBILITIES	E-1
APPROVAL, PLANNING, AND EXECUTION OF THE DECONTAMINATION EXPERIMENT	E-3
PROCEDURES AND OPERATING INSTRUCTIONS WRITTEN TO SUPPORT DECONTAMINATION	E-5
ENGINEERING CHANGES TO SUPPORT DECONTAMINATION	E-8
SPECIAL SUPPORT EQUIPMENT	E-9
RADIOLOGICAL CONTROLS DEPARTMENT SUPPORT	E-12
UNIT 2 OPERATIONS AND MAINTENANCE DEPARTMENT SUPPORT	E-16
INDUSTRIAL SAFETY AND HEALTH DEPARTMENT SUPPORT	E-17
BUILDING TRADES	E-19

ATTACHMENTS

E-1	ORGANIZATIONAL INTERFACE FOR OVERALL DECONTAMINATION EXPERIMENT
E-2	ORGANIZATIONAL INTERFACE FOR DECONTAMINATION TASKS
E-3	BNOC PROJECT CONSTRUCTION ORGANIZATION
E-4	WORK PACKAGE PLANNING AND EXECUTION SEQUENCE BY BNOC CONSTRUCTION
E-5	ACCESS TO AND WORK PERFORMED IN THE CONTAINMENT BUILDING
E-6	CASUALTY PROCEDURE FOR HIGH RADIATION CONDITION IN-CONTAINMENT
E-7	CASUALTY PROCEDURE FOR FIRE IN-CONTAINMENT
E-8	CASUALTY PROCEDURE FOR PERSONNEL INJURY OR SICKNESS IN-CONTAINMENT

APPENDIX E - ORGANIZATION AND SUPPORT

ORGANIZATIONAL RESPONSIBILITIES

An outline of the various organization responsibilities follows.

Client (GPU)

- o Review and approve all work scope, finding, and milestone schedules
- o Maintain license regulatory responsibilities for radiological protection and technical specification compliance to include:
 - Radiological controls
 - Radiological engineer
 - Dosimetry
 - Respiratory protection
- o Site sample analysis
- o Approval of procedures
- o Operations Department assistance and interface
- o Maintenance Department assistance and interface
- o Radwaste handling and shipping
- o Industrial safety and health

Department of Energy Contractor (EG&G)

- o Propose research tasks
- o Fund those tasks approved
- o Supply contracted equipment and services

Technical Planning and Guidance (BNI)

- o Define data acquisition program tasks
- o Issue decontamination tasks and sequence plan through GPU

Prime Contractors for Recovery

Engineering (BNoC)

- o Provide engineering required for support system
- o Procure material
- o Provide technical guidance to Project Construction Group

Project Construction

- o Execute the decontamination plan
- o Ensure safe operations
- o Install services and support systems
- o Coordinate and schedule entries

APPROVAL, PLANNING, AND EXECUTION OF THE DECONTAMINATION EXPERIMENT

Approval and Funding for Scope of Work

After a scope of work was negotiated, review, approval, and funding of the Decontamination Experiment proceeded as illustrated by Attachment E-1.

Planning

Individual decontamination and data acquisition tasks were planned through the preparation and approval of data acquisition sample packages. The overall plan required testing of several decontamination methods and equipment. Plans took into account the lessons learned from the previous decontamination experiments of containment entries 4, 5, and 10.

The organizational interface and sequence for these tasks are represented in Attachment E-2. Following receipt of the sample packages, Engineering

Change Memorandums (ECMs), or other forms of technical direction, BNoC Construction drafted work packages for execution.

Execution

The BNoC Project Construction Organization is illustrated by Attachment E-3. The responsibilities of the various groups within the organization, under the direction of the Field Construction Manager, were outlined as follows:

- o Field Engineering was responsible for work packages and procurement associated with the installation of special equipment and related services.
- o Cost and Schedule tracked all funding-related information and issued the following schedules:
 - Milestone schedule
 - Two-week look-ahead schedule
 - Daily entry schedule
- o The Containment Access Group was responsible for the overall conduct of entries. It provided review, training, processing, and approval functions for each work package.
- o The Decontamination Group was responsible for writing and carrying out all Decontamination Experiment work packages not otherwise assigned to Field Engineering.

- o The Contracts Coordinator was responsible for coordination of building trades personnel. This included review of all affected work packages and related techniques.

Work Package

The work package planning and execution sequence is illustrated by Attachment E-4. In the course of the experiment, about 62 work packages were executed using this process between entries 17 through 56.

PROCEDURES AND OPERATING INSTRUCTIONS WRITTEN TO SUPPORT DECONTAMINATION

Several procedures were required to support the decontamination experiment.

These procedures include the following:

- o Containment Access Procedure
- o Containment casualty procedures for high radiation exposure, fire, and personal injury or sickness
- o Radiological and safety evaluation
- o Special operating procedures for the decontamination service systems and testing of the fire water system
- o Test procedure for decontamination service penetration R-561
- o Operating instructions for decontamination systems

All procedures had to be approved prior to commencement of the affected entry.

Containment Access Procedure

The Containment Access Procedure is included in Attachment E-5. This procedure provided all administrative controls for entry implementation, including:

- o Entry schedules and approvals
- o Limitations and precautions
- o Upgraded fire protection requirements
- o Command center organization and responsibilities
- o Requirements for casualty procedures
- o Control room interface

Casualty Procedures

Casualty procedures are included as Attachments E-6 through E-8. These procedures supplemented existing site procedures for the three casualties covered. Responsibilities for a projected casualty were assigned to:

- o Command center
- o Anteroom

- o Entry teams
- o Control room
- o Other support personnel

Radiological and Safety Evaluation

This document was prepared by BNoC Project Engineering. It evaluated the planned activities of the Decontamination Experiment for impact in the following areas:

- o Effluents released to the environment
- o Occupational exposure (man-rem estimate)
- o Radioactive waste management
- o Industrial safety
- o Nuclear safety evaluation in accordance with 10 CFR 50.59

Other Procedures and Instructions

Special operating procedures were temporary in nature and were written whenever a temporary rather than permanent procedure was required. Examples include:

- o Operating plant system interface valves in a temporary system, such as decontamination water and its connection to penetration R-561
- o Post-installation test procedures for new systems
- o One-time tests on permanent plant systems, such as the post-accident operability test performed on the containment fire water system

Operating instructions were prepared by BNoC Construction with technical direction from BNoC Engineering. They describe the methods for operation of temporary systems outside the plant system interfacing valves.

ENGINEERING CHANGES TO SUPPORT DECONTAMINATION

Several ECMs were written by BNoC Project Engineering and approved for installation. They include:

- o ECM 950 120 V service at elevations 305' and 347'-6"
- o ECM 951 Support structure for aerial work platform
- o ECM 952 Electrical supply for aerial work platform

- o ECM 958 Electrical supply to hot water heater
- o ECM 960 Containment penetration for radio equipment
- o ECM 963 Containment penetration for high pressure water supply
- o ECM 964 Electrical supply to high pressure pump
- o ECM 975 Alternate to electric supply for hot water heater

Installation of these ECMs was required prior to the commencement of flushing operations.

SPECIAL SUPPORT EQUIPMENT

Several types of special equipment were brought into the containment or installed as part of the experiment. These items include:

- o Spider work platform
- o New radio system
- o High reach scissors lift work platform
- o Forklifts
- o Elevation 347-6" lifting service

Spider Work Platform

This is an electrohydraulic device capable of lifting two to four personnel or 1100 pounds of equipment from elevation 347'-6" to the polar crane walkway at elevation 426'. The installation of this device was necessary to provide rapid ascent and descent of workers and to allow for safe decontamination of the polar crane. Plans to expand the lifting capability to include elevation 305' were not completed. Ascent time to the crane from elevation 347'-6" was about 4 minutes; climbing took about 20 minutes. Skin contaminations resulting from use of the climbing technique were significantly reduced after the lifting device was installed. In addition, crane working time was extended about 1 hour per man as a result of time and endurance savings.

New Radio Systems

During the experiment an attempt was made to install an improved radio system. The proposed system offered several functional improvements and greater reliability, and provided clear reception in preliminary tests. It operated at a lower power level and could be worn inside protective clothing. Installation in the containment required additional antennas to be installed at penetration R-507, with the remaining equipment being placed outside the containment. After the antenna installation was complete, several tests were conducted with the following general results:

- o Reception in the containment was satisfactory in all areas tested: elevations 305', 347'-6", and 367'; and the polar crane.
- o Reception in the command center varied from satisfactory to unacceptable, depending on the location of the individual. Areas near R-507

(40 percent of elevation 305' and 25 percent of elevation 347'-6") were satisfactory; the remaining areas appeared as "dead spots" with no reception at all.

- o In-containment reception was improved with linear amplification of the command center signal; returning signals were unamplified and attenuated by the containment structure.
- o Subsequent operations during the experiment were performed using the existing radio system.
- o Decontamination operations were impacted by use of the existing radio system. The radio problems increased the number of man-hours by approximately 5 percent. In addition, a loss of decontamination coverage or "holidays" occurred in the surface decontamination because of the frequent and inaudible radio transmissions, which resulted in interrupted work.

High Reach Scissors Lift Work Platform

This is a self-propelled, battery-operated access platform with a maximum platform height of 15 feet which was placed in the containment for use during the decontamination test. The platform had an integral battery charger and a battery capacity of 250 amp-hours. The platform moved at 5 miles per hour when lowered below 10 feet and at 2.5 miles per hour when fully extended. The platform was controlled either by an operator on the platform or from the ground, and when fully lowered, it was 41 inches above floor level. The platform had a lifting capacity of 750 pounds and an overreach length of 2.5 feet.

The platform was used on several occasions to work on or to inspect areas where scaffolding would normally have had to be installed.

Forklifts

Two forklifts were purchased for use in the experiment. They are battery-powered and self-propelled with a 4000-pound lifting capacity. One unit was placed in the containment. The other unit was used in the anteroom and for training. The forklifts were used successfully to move lead and other heavy objects into the containment.

Elevation 347' Lift Device

This unit was designed and fabricated on site by BNoC Construction. It is a multipurpose frame device capable of lifting deck plates, grating, or other objects that weigh up to 1500 pounds. A lead counterweight provides stability, and the device is mounted on wheels for greater mobility. Less human effort is required to lift loads as a result of the installation of a "tugger" electric winch which raises loads slowly by electric power. Lifting speed is about 15 feet per minute. The lift device was carried into the containment in sub-assemblies and put together on elevation 347'-6".

RADIOLOGICAL CONTROLS DEPARTMENT SUPPORT

The Radiological Controls Department was responsible for compliance with regulations affecting radiation protection. The following sections describe interfaces and responsibilities within the department related to the Decontamination Experiment.

Radiological Engineering

Radiological Engineering was responsible for ensuring that when work was done in radiation areas the resulting exposure is as low as reasonably achievable (ALARA). For containment entries, the following tasks were required:

- o Conduct ALARA review of each Radiation Work Permit (RWP)
- o Specify and coordinate required dosimetry
- o Specify when radiological hold points, measurements, or samples were required
- o Track entry radiological data for trends
- o Specify follow-up action for radiological problems
- o Write radiological procedures
- o Track radiological exposure by assignment of ALARA review number and use of computer system

Radiological Field Operations

Radiological Field Operations, through the use of health physics (HP) technicians, was responsible for identifying radiological conditions throughout the plant and for providing radiological coverage when required by the RWP. The following tasks were required:

- o Administer RWPs, including screening individuals for the necessary qualification prerequisites

-
- o Provide entry HP technicians for initial air sample analyses of particulate matter and tritium, as well as general surveys of all containment areas when radiological conditions were not known or were expected to change; provide HP technicians to obtain tritium samples during flushing operations
 - o Support HP technicians to conduct briefings and monitor RWP control point and anteroom
 - o Support HP technicians to inspect, issue, and decontaminate the following radiological support equipment:
 - Radiological survey instruments
 - Air sampling devices
 - Dosimeters
 - Breathing zone air sampler
 - Other miscellaneous support items
 - o Control issue of keys to high radiation areas
 - o Perform requested radiological surveys to support movement of trash, equipment, and samples
 - o Escort radioactive material when required
 - o Perform routine radiological surveys of anteroom, decontamination room, dressing area, and training area

Dosimetry

Dosimetry was responsible for the following tasks:

- o Issue and read thermoluminescent dosimeters
- o Track exposure histories
- o Record bioassay results
- o Record whole body count results

Respiratory Protection

Respiratory Protection was responsible for the following tasks:

- o Issue respiratory training standards
- o Supply and decontaminate respiratory devices
- o Issue and monitor radiological procedures related to respiratory protection.

Command Center

Command center representation was maintained by the Containment Access Procedure, Attachment E-5, Section 4.4.5.3.

UNIT 2 OPERATIONS AND MAINTENANCE DEPARTMENT SUPPORT

For the Decontamination Experiment, operations or maintenance technicians or supervisors were provided through a group coordinator on an individual task basis.

Operations

The related duties for Operations include:

- o Chair and publish the Plan of the Day, which scheduled and set priorities for all site activities
- o Carry out required containment plant surveillance activities through BNoC Project Construction
- o Provide plant operator for decontamination water and service air (special operating procedure)
- o Provide plant operators to complete protection of plant equipment
- o Operate plant systems
- o Control issue of plant keys through the shift supervisor/foreman
- o Perform air lock leak tests, as required
- o Comply with other Technical Specifications, as appropriate
- o Direct emergency actions

- o Provide an Operations supervisor for entries, as required by Attachment E-5, Section 4.4.5.4

Maintenance

The related duties for Maintenance include:

- o Repair or replace plant system components
- o Provide maintenance and improvement program for closed-circuit television system (CCTV)
- o Provide instrumentation and controls shop support for command center electrical equipment, radios, and portable CCTV hardware
- o Provide temporary services system for plant tie-in installation
- o Provide services to the Decontamination Group for decontamination of tools and equipment; provide radwaste disposal and interim radwaste storage support

INDUSTRIAL SAFETY AND HEALTH DEPARTMENT SUPPORT

The Safety Department was responsible for or assumed the duties for the following during the Decontamination Experiment:

- o Screen incoming personnel for respiratory qualifications
- o Specify safety requirements necessary to support work packages

- o Administer the heat stress test in accordance with the published requirements contained in Attachment D-6 (Heat Stress Control Program) of Appendix D, Training and Safety
- o Publish training standards and lesson plans for safety issues; provide or qualify instructors to teach safety procedures
- o Perform safety inspections
- o Write safety procedures
- o Supply safety equipment
- o Conduct body-cooling experiments and other development programs to improve entry performance
- o Supply industrial hygiene equipment, such as oxygen/combustible gas monitors
- o Provide paramedic when needed

The command center was manned by a Safety Representative as required by Attachment E-5, Section 4.4.5.6.

During entry 53, the Safety Department supplied three personnel to perform the mechanical floor scrubber test. Their participation was part of a controlled experiment to measure the benefits of the ice jacket for body cooling. In several other entries, the Safety Department supplied inspectors or safety escorts for installation of the spider work platform.

BUILDING TRADES

The building trades provided manpower for technique development and work package execution for installation and repair services. The following sections outline the experiment contributions by trade.

Laborer

The laborer trade supplied in-containment manpower for trash removal, data taking, equipment movement, and other miscellaneous tasks.

Out of containment, the laborers served as support technicians for a variety of tasks, including:

- o Maintain training area and dressing area cleanliness
- o Stock consumable materials
- o Stage and move equipment
- o Support training
- o Dress personnel
- o Unsuit personnel in anteroom
- o Prepare equipment for entry into containment
- o Decontaminate equipment and anteroom

Ironworker

The ironworker trade supplied manpower for the following:

- o Spider work platform installation and maintenance
- o Rigging services
- o Fabrication of equipment

Carpenter

The carpenter trade supplied manpower for the following:

- o Installation of high reach work platform and forklift
- o Rigging services
- o Trash removal
- o Scaffolding
- o Out-of-containment fabrication and construction, including contamination control corridor, air lock mock-up, and other support facilities

Electrician

The electrician trade supplied manpower for the following:

- o Spider work platform electrical installation and maintenance
- o Electrical component replacement
- o Polar crane inspection

ATTACHMENT E-1
ORGANIZATIONAL INTERFACE
FOR
OVERALL DECONTAMINATION EXPERIMENT

ATTACHMENT E-1

ORGANIZATION INTERFACE FOR OVERALL DECONTAMINATION EXPERIMENT APPROVAL, FUNDING, AND MILESTONE SCHEDULE

- ① PROPOSAL
- ② REVIEW FOR IMPACT/FEASIBILITY/TECHNICAL CONTENT
- ③ RESPONSE TO PROPOSAL BY BNoC/BNI
- ④ RESPONSE TO DOE BY GPU
- ⑤ FUNDING AUTHORIZATION AND SCOPE DEFINITION
- ⑥A TECHNICAL ENGINEERING DIRECTION
- ⑥B SEQUENCE RESTRAINTS FOR DECONTAMINATION PLAN
- ⑦ PROPOSED MILESTONE SCHEDULE
- ⑧ APPROVE MILESTONE SCHEDULE
- ⑨ BEGIN IMPLEMENTATION

ATTACHMENT E-2
ORGANIZATIONAL INTERFACE
FOR
DECONTAMINATION TASKS

ATTACHMENT E-2

ORGANIZATION INTERFACE FOR DECONTAMINATION TASKS

ATTACHMENT E-3

BNOC PROJECT CONSTRUCTION ORGANIZATION

ATTACHMENT E-3

BNOC PROJECT CONSTRUCTION ORGANIZATION

ATTACHMENT E-4

WORK PACKAGE PLANNING AND EXECUTION SEQUENCE

BY

BNOC CONSTRUCTION

ATTACHMENT E-4

WORK PACKAGE PLANNING AND EXECUTION SEQUENCE BY BNOC CONSTRUCTION

TECHNICAL DIRECTION FROM PROJECT ENGINEERING

ATTACHMENT E-5
ACCESS TO AND WORK PERFORMED IN
THE CONTAINMENT BUILDING

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

Responsible Office

Plant Admin (4100)

Applicability

All Activities Conducted in the Containment Building

Effective Date

May 4, 1982

LIST OF EFFECTIVE PAGES

CONTROLLED COPY FOR
USE IN UNIT II ONLY

Page	Revision	Page	Revision	Page	Revision
1.0	0				
2.0	0				
3.0	0				
4.0	0				
5.0	0				
6.0	0				
7.0	0				
8.0	0				
9.0	0				
10.0	0				
11.0	0				
12.0	0				
13.0	0				
14.0	0				
15.0	0				
16.0	0				
17.0	0				
18.0	0				
19.0	0				
20.0	0				
21.0	0				
22.0	0				

Command Center

	Signature	Title/Division/Department	Date
Originator	<i>W. Kelly</i>	Manager, Plant Admin	4/15/82
Reviewed by	<i>M. R. Grist</i>	Recovery Prgms. Ops and Const. Dir.	4/15/82
	<i>J. E. L...</i>	Supervisor - TMI-2 Licensing	4/16/82
	<i>[Signature]</i>	Director - TMI-2 Rad Controls	4/16/82
	<i>[Signature]</i>	Supervisor - Health and Safety	4/16/82
	<i>[Signature]</i>	Quality Assurance	4/20/82
	<i>[Signature]</i>	PORC	4/21/82
	<i>[Signature]</i>	BNOC Field Construction Manager	5/4/82
	<i>[Signature]</i>		4.16.82
Approved by	<i>[Signature]</i>	Director Site Operations	5/4/82
	<i>[Signature]</i>	Director - Recovery Prgms. Office	5/4/82

FOR USE IN UNIT II ONLY

Revision
0

0

FOR USE IN UNIT II ONLY

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADI-3240.1

Title

Access To and Work in the Containment Building

<u>SECTION</u>	<u>TITLE</u>	<u>PAGE</u>
1.0	<u>PURPOSE</u>	4.0
2.0	<u>APPLICABILITY/SCOPE</u>	4.0
3.0	<u>DEFINITIONS</u>	4.0
4.0	<u>PROCEDURE</u>	4.0
4.1	Documents and Approvals	4.0
4.1.1	Schedules	4.0
4.1.2	GPU Approvals	5.0
4.1.3	In Containment Activities	5.0
4.1.4	Unscheduled Entries	5.0
4.2	Limitations and Precautions	6.0
4.2.1	Exposure Rates	6.0
4.2.2	Emergency Lighting	6.0
4.2.3	Minimum Number of Personnel (Polar Crane)	6.0
4.2.4	Minimum Number of Personnel (Out of Contact)	7.0
4.2.5	Activity Review	7.0
4.2.6	Water for Decontamination Uses	7.0
4.2.7	Tools and Equipment	8.0
4.2.8	Worker Training	8.0
4.2.9	Digital Dosimeters	8.0
4.2.10	Radiological Controls	8.0
4.2.11	Ante - Room Personnel	10.0
4.2.12	Containment Building Purging	10.0
4.2.13	Purge and Stack Effluent Monitors	10.0
4.2.14	Air Lock Door	11.0
4.3	Fire Protection	11.0
4.3.1	Precautions	11.0
4.3.2	Requirements	11.0
4.4	Planning and Implementation	11.0
4.4.1	Scheduling	11.0
4.4.2	Training	13.0
4.4.3	Notification	14.0
4.4.4	Execution	14.0
4.4.5	Command Center Organization	15.0
4.4.6	Casualty Procedures	20.0
4.5	Control Room Interface	20.0

FORM 1000-POL-1318 (1-3-80)

FOR USE IN UNIT II ONLY

Revision
No.

0

FOR USE IN UNIT II ONLY

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

<u>SECTION</u>	<u>TITLE</u>	<u>PAGE</u>
5.0	<u>RESPONSIBILITIES</u>	20.0
6.0	<u>REFERENCES</u>	20.0
7.0	<u>ATTACHMENTS</u>	22.0 21

FORM 1000 PDR 12/81 1-2 (M 81)

FOR USE IN UNIT II ONLY

Revision
No.

0

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure ManualProcedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

1.0 PURPOSE

To describe the procedural requirements which govern access to containment and work inside containment.

2.0 APPLICABILITY/SCOPE

2.1 Applicability - This procedure is applicable to all activities conducted in the containment.

2.2 Scope - Activities that fall within the scope of this procedure are:

- a. Any activity scheduled in the containment for preparation for or performance of authorized Recovery tasks.
- b. Data Acquisition activities.
- c. Normal Plant Maintenance, Operations, and Surveillance.
- d. Routine Corrective or Preventive Maintenance on specialty equipment in containment for Recovery or Data Acquisition Tasks.
- e. Housekeeping activities in containment.
- f. Unscheduled Containment Building entries.

3.0 DEFINITIONS

None

4.0 PROCEDURE

4.1 Documents and Approvals

4.1.1 Schedules

All scheduled activities to be conducted in the Containment Building shall be incorporated into a Field Summary schedule (revised monthly) prepared by Bechtel Northern Corporation (BNoC) and approved by the GPU Recovery Programs Operations and Construction Director. GPU approval of the schedule signifies approval to implement the scheduled activities subject to availability of the following properly approved documents where required:

- 4.1.1.1 Engineering Change Memorandum/Authorization (ECM/ECA).
- 4.1.1.2 Maintenance Job Ticket or Preventive Maintenance Check Sheet.
- 4.1.1.3 Procedure or Work Package.
- 4.1.1.4 Radiological Engineering Review.
- 4.1.1.5 Radiation Work Permit (RWP).

FOR USE IN UNIT II ONLY

Revision
No.

0

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

4.1.2 GPU Approvals

Approvals of the above documents shall be in accordance with existing GPU procedures. Guidelines for determining the need for these documents are provided below:

4.1.2.1 Any addition of, connection to, deletion of, or replacement with unlike kind of any facility, structure, system, circuit, or component of or to the existing plant shall be accomplished under an ECM/ECA. A Maintenance Job Ticket is required when a system or part of a system is being repaired, removed or replaced with like kind.

4.1.2.2 Activities involving the following require procedures and/or work packages to be submitted for GPU approval:

- Securing, tagging or opening any plant component or system.
- Operation of any plant component or system (i.e. pump, valve, etc.)
- Requires an interface with TMI-1.
- As required by TMI-2 Technical Specifications Sections 3.4, 3.6, 6.5.1.6 and 6.8. (NRC approval where required per Section 6.8)
- When deemed necessary by the Bechtel Northern Field Construction Manager due to task complexity.

4.1.2.3 All activities require a radiological review in accordance with RCP 4045, Radiological Review and an RWP in accordance with RCP 4122, Radiation Work Permit.

4.1.3 In Containment Activities

All activities in containment will be described in a work package prepared by BNoC Construction. Work packages shall comply with all requirements of this procedure and, when required, be approved in accordance with paragraph 4.1.2.

4.1.4 Unscheduled Entries

Unscheduled entries may be conducted to accommodate unanticipated circumstances or conditions:

4.1.4.1 Normal unscheduled entries may be conducted with the approval of the Recovery Programs Operations and Construction Director. These entries shall be made in accordance with all requirements of this procedure with the exception of scheduling requirements.

FOR USE IN UNIT II ONLY

Revision
No.

0

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

4.1.4.2 Expedited entries may be made to obtain data on plant status or to correct plant conditions where there is no immediate jeopardy to personnel or plant safety. The purpose of performing an expedited entry is to reduce the time required to enter containment. The primary concern is personnel safety. Precautions normally taken to protect personnel and equipment from radioactive contamination and for controlling the spread of radioactive contamination may be reduced with the concurrence of the Radiological Controls Shift Foreman and Radiological Engineering. The description of the activities to be conducted may be included in the RWP instead of in a work package or procedure. All other requirements of this procedure apply except scheduling. Expedited entries require the approval of the Director, TMI-2.

4.1.4.3 Emergency entries may be conducted when there is or appears to be immediate jeopardy to personnel or plant safety. The approval of the Manager, Plant Operations or the Operations Shift Foreman is required for an emergency entry. All requirements of this procedure are waived for emergency entries. The entry shall be under the direction and control of the Operations Shift Foreman or his designated representative. RCP 4122, Radiation Work Permit, requiring Radiological Controls escort applies. At the option of the Operations Shift Foreman, all or a portion of the Command Center Organization (See Paragraph 4.4.5) may be mobilized to assist in control of the entry. The Operations Shift Foreman is responsible for notification to the NRC that an emergency entry is being initiated.

Fire emergency entries shall be conducted per 2202-3.1 - Fire.

4.2 Limitations and Precautions

In addition to the limitations and specifications included via the formal document review process required for each document (See section 4.1), the following shall be applied to all work in containment as appropriate:

4.2.1 All personnel will work in an area with the exposure rate set by a qualified Radiological Controls technician.

4.2.2 All personnel will be equipped with emergency flashlights unless emergency lighting is available in containment.

4.2.3 A minimum of three (3) personnel will be on the polar crane when work is being performed on the crane and the Spider Shafter is not available. Two people are required with the Spider Shafter available. If the Spider Shafter becomes inoperable while only two persons are on the crane, they shall either descend immediately in accordance with procedure 2104-9.1 or a third person shall immediately ascend to the crane.

FORM 1000 PCL 1218 1-2 M 811

FOR USE IN UNIT II ONLY

Revision

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

- 4.2.4 A minimum of two personnel, each equipped with radios, will be used for tasks that require team members to be continuously out-of-sight of the Command Center for greater than 30 minutes, in a greater than/equal to 1 R/hr radiation field or require extensive climbing. The following are examples of these proposed two man areas:
- 4.2.4.1 Inside either D-Ring
 - 4.2.4.2 Refueling Canal
 - 4.2.4.3 In-core instrumentation Tunnel
- 4.2.5 Any activity inside containment shall be reviewed by BNoC to insure safety related equipment and systems are not jeopardized; assistance is available from Site Operations for this review.
- 4.2.6 Water used for decontamination flushing operations shall be less than or equal to the following limits:
- 4.2.6.1 H-3 1.0 μ Ci/ml
 - 4.2.6.2 CS-134 1.0 X 10⁻³ μ Ci/ml
 - 4.2.6.3 CS-137 1.6 X 10⁻³ μ Ci/ml
 - 4.2.6.4 Sr-89 8.0 X 10⁻⁴ μ Ci/ml
 - 4.2.6.5 Sr-90 2.7 X 10⁻⁵ μ Ci/ml
 - 4.2.6.6 Cl less than 2.0 ppm
 - 4.2.6.7 Boron greater than 1700 ppm
- 4.2.7 Tools and equipment taken into the Containment Building shall be logged in and out on a log maintained by BNoC in the Command Center. Radwaste and samples removed from containment shall be controlled by BNoC until they have been moved to a waste staging area or controlled storage. Bechtel National is responsible to insure that samples are shipped as soon as practicable.
- 4.2.8 Workers shall be trained on all specialty equipment they will be using and emergency equipment which may be used in the containment. This training shall include equipment operation, associated usage techniques, equipment safety, electrical shock and associated personnel safety (Section 4.4.2). Training records shall be maintained by BNoC.

FORM 1000 PUN-1219 (1-2-80)

FOR USE IN UNIT II ONLY

Revision
No.

0

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

4.2.9 Digital dosimeters will be required for all personnel in containment under any of the following conditions:

4.2.9.1 Any individual entering containment whose exposure upon entering is greater than 2 rem for the quarter.

4.2.9.2 Any individual entering containment whose exposure upon entering is greater than 4 rem for the year.

4.2.9.3 Any individual working in an area where dose rates are greater than 1R/hour.

4.2.9.4 Any individual entering a High Radiation Area shall (a) use a continuously indicating dose rate device or (b) use a dose rate integrating device which alarms at a preset dose level or (c) assure that a radiological control technician provides periodic radiation surveillance with a dose rate monitoring instrument. The NRC shall be notified by Radiological Controls if any individual enters the Reactor Building without a dose integrating device which alarms at a preset dose level.

In addition, self reading dosimeters will be worn by all individuals entering the containment building.

4.2.10 The radiological controls applied for containment entry shall be in accordance with approved procedures. The applicable procedures include but are not limited to the following:

4.2.10.1 Use of Digitals

RCP 4122 Radiation Work Permit

RCP 4123 Self Reader Dosimeter Usage and Record Keeping

4.2.10.2 Bioassay and Whole Body Count

RCP 4238 Bioassay Program

SOM No. 7 Minimum Protective Clothing and Dosimetry
Required for Entries into the Reactor Building

SOM No. 11 Tritium Exposure Control

4.2.10.3 BZA's

RCP 4101 Air Sample Counting, Handling, and Actions

RCP 4104 Air Sampling Procedure

SOM No. 7 Minimum Protective Clothing and Dosimetry
Required for Entries into the Reactor Building

FOR USE IN UNIT II ONLY

Revision
No.

0

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

4.2.10.4 Air Monitoring

RCP 4100 Radiological Surveys
RCP 4101 Air Sample Counting, Handling, and Actions
RCP 4104 Air Sampling Procedure
RCP 1631.2 Sampling of Reactor Building (Unit II only)

4.2.10.5 General Dosimetry

RCP 4200 TLD Assignment, Issue, and Data Handling
SOM No.7 Minimum Protection Clothing and Dosimetry
Required for Entries into the Reactor Building

4.2.10.6 Surveys

RCP 4100 Radiological Surveys
RCP 4102 Radiation Surveys

4.2.10.7 Dose Extensions

RCP 4015 Administrative and Emergency Exposure and Contamination Limits

4.2.10.8 High Radiation Area Access

RCP 4161 Control of Locked High Radiation Areas

4.2.10.9 Administration

RCP 4122 Radiation Work Permit
RCP 4045 Radiological Review

4.2.10.10 Protective Clothing

RCP 4125 Use of Anti-Contamination Clothing
RCP 4025 Selection, Prescription and Use of Respiratory Protection

In addition to the approved procedures, guidance for Reactor Building activities is in the Radiological Controls Department Standing Order Manual (SOM 6, 7 and 11).

Activities in the Reactor Building are unique in nature; the initial applied radiological control techniques will be very conservative to insure adequate personnel protection. As

FORM 1000-POL 1218 1-2 88 611

FOR USE IN UNIT II ONLY

Revision
No.

0

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

experience is gained and radiological conditions are changed the Radiological Control techniques will be modified, always insuring the adequate protection of personnel. Because of these changing conditions, a qualified Radiological Controls representative shall be constantly present in the Command Center monitoring and evaluating the activities in the Reactor Building.

Additionally, these changing conditions preclude a commitment to a specific radiological control methodology to be applied. Radiological Controls personnel shall apply the most appropriate techniques in accordance with good radiological control practices. NRC shall be briefed on proposed changes to radiation protection measures in the Reactor Building.

- 4.2.11 Ante-Room personnel shall be trained for in-containment personnel assistance activities and will be utilized for personnel assistance where required by personnel in containment. These Ante-Room personnel are immediately available for entry when personnel assistance is required. Certain activities may require trained backup teams to be trained, fully dressed and available for immediate entry during in-containment operations. The need for these backup teams will be determined by BNOc on a case by case basis.
- 4.2.12 Containment Building purging shall be in accordance with Procedure 2104-4.91, Reactor Building Purge using the Modified Purge System. Engineered features will be used to the maximum extent practicable to minimize airborne concentrations. In the event that the purge system is not available prior to an entry or becomes unavailable during an entry, an evaluation shall be made by GPUN Radiological Controls. If it is decided to continue without purging, the NRC shall be notified by GPUN Radiological Controls. This notification shall be made prior to an entry if an entry is not in progress.
- 4.2.13 If purging is in progress, Purge and Stack effluent monitors will be operable and monitored during entries with any alarm conditions immediately relayed to the Command Center.
- 4.2.14 THE OUTER AIRLOCK DOOR CAN BE OPENED ONLY IF THE INNER DOOR IS CLOSED, UNLESS THE INTERLOCK HAS BEEN DEFEATED. Command Center personnel should be aware of this and provide special attention when only one individual is entering containment so that prompt action can be taken in the event of injury. The length of time that the inner door is open should be minimized.

FOR USE IN UNIT II ONLY

Revision
No.

0

Title

Access To and Work in the Containment Building

4.2.15 When containment atmosphere is known or suspected to be immediately dangerous to life or health (IDLH atmosphere is any atmosphere that has less than 16 percent oxygen by volume or any atmosphere that is combustible or toxic), personnel entering containment shall wear self contained breathing apparatus. If no emergency or casualty is in progress, microphones and earpieces shall be worn for radio communications. In the case of emergency or casualty, communication equipment requirements shall be based on the available time, available equipment and the task involved; however, some form of communications is required.

4.3 Fire Protection

4.3.1 Precautions

4.3.1.1 Transient combustibles shall be minimized and shall be controlled per Plant Procedure AP 1034. Transient combustibles shall be logged into and out of containment in the log kept by BNoC in the Command Center.

4.3.1.2 Welding, cutting, burning, soldering, etc., shall be controlled per Plant Procedure MP 1410-Y-26. In addition, fire watches will be equipped with radios and in contact with the Command Center.

4.3.1.3 Wood used in containment shall be fire retardant treated, preferably the pressure treated type fire retardant. If possible, non-combustible materials should be used in place of wood.

4.3.1.4 Personnel should be alert for fires and signs of fire during entries. All fires and signs of fire shall be reported to the Command Center and investigated as soon as possible.

4.3.2 Equipment Requirements

4.3.2.1 Fire extinguishers (4) with an A:B:C rating will be on light-weight, portable racks, two extinguishers to a rack. One rack on 305' elevation and one on 347' elevation. There will be additional extinguishers in the Ante-Room and plant extinguishers will also be available.

4.3.2.2 If the Containment Building Fire Detection System is inoperable, the Reactor Building shall be monitored by Plant Operations via the CCTV system, for fires or signs of fire, hourly for four hours after an entry plus at least twice in the ensuing 20 hour

FORM 1000-POL-1218 1-2 811

Title

Access To and Work in the Containment Building

period. Examinations shall be timed so that they occur at least once each shift. Any indication of fire shall be reported to the Control Room immediately for proper action. Time of monitoring and results shall be recorded and the record retained in the Control Room.

4.3.2.3 Hose reels on 305' and 347' elevations shall be in service. Nozzles and hose reel valves will be shut, outside containment isolation valve, FS-V639, will be shut and inside containment isolation valve, FS-V640, will be left open. FS-V639 shall be opened during entries requiring:

4.3.2.3.1 Cutting, welding, burning, soldering, etc.

4.3.2.3.2 Water spraying.

4.3.2.3.3 Use of flammable liquids.

4.3.2.3.4 The use of or generation of large quantities of combustibles.

4.3.2.3.5 Any condition for which Plant Operations determines the hose reels should be in service.

4.4 Planning and Implementation

4.4.1 Scheduling - Prior to scheduling an activity, a review by Bechtel Construction will be made to determine the following to the maximum extent possible:

4.4.1.1 When services (if required) will be available.

4.4.1.2 If the in containment time to do the task is available.

4.4.1.3 The task does not conflict with any other task currently scheduled.

4.4.1.4 Personnel are available to do the task, i.e., the proper mix of trades, etc.

4.4.1.5 The equipment necessary to do the task is or will be available.

4.4.1.6 The extent of training requirements.

4.4.1.7 Regulatory requirements are properly addressed and satisfied.

Upon satisfactory review of these items, the activity will be placed on the Field Summary Schedule and tracked until completion. When scheduled, BNOc will assign a responsible field engineer to the task.

Revision
 No.

0

FOR USE IN UNIT II ONLY

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.

4300-ADM-3240.1

Title

Access To and Work in the Containment Building

4.4.2 Training

4.4.2.1 Training for containment activities will be conducted at 3' different levels.

4.4.2.1.1 Overall RWP qualification provided by GPU's training department per RCP 4021 - Training Requirements.

4.4.2.1.2 General containment familiarization provided by Bechtel Construction, which include as a minimum:

4.4.2.1.2.1 Latest Radiological conditions.

4.4.2.1.2.2 Organization, command and control.

4.4.2.1.2.3 General access requirements.

4.4.2.1.2.4 Casualty procedures.

4.4.2.1.2.5 Equipment orientation including radiological (e.g. digital dosimeters), safety (e.g., Fire Extinguishers) and task related devices.

4.4.2.1.2.6 Heat stress.

4.4.2.1.2.7 TV and radio Communications.

4.4.2.1.2.8 Anticontamination and respiratory protection regime in effect.

4.4.2.1.3 Work Package training provided by Bechtel Construction will consist of one or more of the following as determined by BNoC Construction:

4.4.2.1.3.1 Walk thru's and briefings.

4.4.2.1.3.2 Dry Runs (Fully dressed per proposed RWP Requirements).

4.4.2.1.3.3 Mockups if necessary per RCP 4030 - Mockup Training and Job Briefings.

4.4.2.1.3.4 Selected task-specific techniques training.

4.4.2.2 Each work package will be reviewed by BNoC Construction to determine the level of training and mockup necessary. In addition, individuals who have demonstrated thru prior work (within the last 3 months) their endurance and heat stress acclimation do not have to repeat that part of the training.

FORM 1000 PMA-1218 (1-2-80)

FOR USE IN UNIT II ONLY

Revision
No.

0

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

4.4.2.2.1 Training will comply with RCP 4030 - Mockup Training and Job Briefings.

4.4.3 Notification

BNoC thru participation in the Plan of the Day (POD) meetings, will provide participating parties with the following:

4.4.3.1 Containment Activities Scheduled for the following day.

4.4.3.2 Estimated Waste and Water Processing Requirements.

4.4.3.3 Two week look ahead schedule of containment activities to enhance support and eliminate interferences.

The Field Summary Schedule and the two week Look Ahead Schedule are issued for information.

4.4.3.4 The NRC will be notified by GPUN prior to all entries except where extenuating circumstances exist and prior notification is not possible. NRC notification to include briefing of any deviation from this procedure.

4.4.4 Execution

4.4.4.1 All activities in the containment will be controlled from the Command Center. The CAG will coordinate the daily sequence schedule and insure work package compliance, equipment staging and personnel readiness. An overall daily schedule, issued by BNoC, showing all activities will be available in the Command Center.

4.4.4.2 The Job Supervisor will insure all prerequisites are complete and system status, services etc., are as required in the work packages. Prior to allowing entry the Entry Coordinator will have a copy of the following documents associated with each authorized task.

4.4.4.2.1 RWP

4.4.4.2.2 Work Package

4.4.4.2.3 Associated Procedures

4.4.4.3 The Job Foreman/Supervisor will inform the Entry Coordinator of the teams readiness to dress, and implement the daily schedule. At this point the CAG will control the movement of work teams

FOR USE IN UNIT II ONLY

Revision
No.

n

FOR USE IN UNIT II ONLY

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

until they exit the Unit 2 Containment. Performance of work will be supervised by the task supervisor. Containment entries will be conducted in accordance with Unit 2 Operation Procedures 2104-4.55, Reactor Building Entry.

4.4.5 Command Center Organization

The CAG Entry Supervisor is in overall charge of an entry. An Entry Coordinator will direct the details of the entry i.e., when to dress, sign-off prerequisites, etc.

Only the CAG Entry Supervisor may change the scope of work or otherwise modify the entry as long as it is consistent with the RWP and the Radiological Review (4045).

The Operations, Safety, and Radiological Control representatives have the authority to stop activities in the containment if conditions affecting their scope of responsibility warrant.

The following are the responsibilities and authorities of the Command Center Personnel:

4.4.5.1 CAG Entry Supervisor (ES)

4.4.5.1.1 Insure proper control is exercised in the Command Center (i.e., procedures are being followed, extraneous conversation or excess people are not allowed).

4.4.5.1.2 Act on recommendation and observation of the Operations, Safety and Radiological Control representatives. In the event of a conflict between Safety, Radcon or Operations considerations, the Entry Supervisor will determine the course of action to be followed. Stop work authority of Safety, Radcon or Operations overrides this determination.

4.4.5.1.3 Direct changes in the entry scenario, for example:

4.4.5.1.3.1 Deletion of planned activity.

4.4.5.1.3.2 Changes in sequence of events.

4.4.5.1.3.3 Authorizes the conduct of optional activities covered by the scenario or work package so long as time, dose, and personal stamina permit.

FORM 1000-POL-1218 (1-2-80 011)

FOR USE IN UNIT II ONLY

Revision
No.

0

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit

Administrative Procedure Manual

Procedure No.

4300-ADM-3240.1

Title

Access To and Work in the Containment Building

4.4.5.1.3.4 Termination of the entry or task. For example:

1. Radiological precautions are not adequate for the situation encountered.
2. Any of the following exit criteria met:

(1) Exit Criteria.

For exits, the prime criteria is the safety of the individuals. All other team members do not have to exit if they are in sight of another entry team member and/or a CCTV camera so that the Command Center can be made aware of their locations.

(1)(1) Sickness and/or fatigue - affected individual will be escorted to the airlock. All team members do not have to exit unless leaving individual cannot be readily replaced and is required to perform team tasks.

(1)(2) Dose Pull Point - to be specified by Radiological Engineering.

(1)(3) Communication - total loss of communication with team.

If team member can hear Command Center and make himself understood via CCTV, activity may continue. If team members try to contact the command center and do not get any response, they should stay in sight of CCTV camera, as much as possible, pick up their equipment and exit the Reactor Building.

(1)(4) Radiation Detection Gear - loss of radiation dose instrumentation to the degree that personnel dose rate levels cannot be determined.

(1)(5) Respirator - failure of respirator to perform properly.

(1)(6) Failure of building lighting.

(1)(7) Any emergency declared by the Control Room or the Operations Supervisor.

FOR USE IN UNIT II ONLY

Revision

7/6

0

FOR USE IN UNIT II ONLY

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

3. Physical configuration not in accordance with drawing to such an extent it invalidates the procedure and the training.
- 4.4.5.1.3.5 Changes to tasks within the scope of approved procedures as recommended by Task Supervisor.
- 4.4.5.1.3.6 Add minor tasks to team activities such as reconnecting CCTV cables that do not require a procedure or add significantly to the stay time (Not to exceed 10 minutes), with the concurrence of the Operations, Safety and Radiological Controls representatives.
- 4.4.5.1.4 Report containment building entrance and exit to the Control Room Operator and keep the Control Room informed on activities in containment.
- 4.4.5.2 Entry Coordinator and/or Entry Supervisor
 - 4.4.5.2.1 Insure all preparations and prerequisites are completed prior to executing the entry. This includes but is not limited to:
 - 4.4.5.2.1.1 RWP's processed including radiological reviews.
 - 4.4.5.2.1.2 Containment Entry Procedure prerequisites.
 - 4.4.5.2.1.3 Command Center manned.
 - 4.4.5.2.2 Console operator (The entry coordinator normally functions as the console operator).
 - 4.4.5.2.2.1 Maintain communications with designated personnel.
 - 4.4.5.2.2.2 Log significant reports. Make verbal reports to Entry Supervisor.
 - 4.4.5.2.2.3 Track actual vs. planned team progress. Make verbal reports to Entry Supervisor on significant variations.
 - 4.4.5.2.2.4 Inform entry team of scenario changes as directed by the Entry Supervisor.
 - 4.4.5.2.2.5 Video tape entry team activities.

FORM 1050-POL-1218-1-2-80-11

FOR USE IN UNIT II ONLY

Revision
No.

0

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

4.4.5.3 Radiological Controls Representative

NOTE: The Radiological Controls Representative shall be a Radiological Engineering Supervisor, a Radiological Engineer or a Radiological Controls Foreman.

4.4.5.3.1 Monitor entry progress.

4.4.5.3.2 Advise Entry Supervisor of potential radiological problems.

4.4.5.3.3 Recommend to Entry Supervisor suitable actions relevant to radiological controls.

4.4.5.3.4 If in the opinion of the radiological controls representative proper radiological controls are not being exercised, he is to provide specific directions with respect to radiological controls to the Entry Supervisor to remedy the situation including termination of that part of the entry.

4.4.5.3.5 Track exposure and advise Entry Supervisor of remaining stay time(s).

4.4.5.4 Operations Supervisor

For each entry, an operations supervisor will be in the Command Center to consult with the Entry Supervisor as follows:

4.4.5.4.1 Based on the information provided, advise or recommend actions to the Entry Supervisor.

4.4.5.4.2 Provide directions for the technician in containment when it involves Plant Safety.

4.4.5.4.3 If in the opinion of the operations supervisor proper controls over plant operations are not being exercised, he is to provide the entry supervisor with specific directions to remedy the situation including termination of that part of the entry.

4.4.5.4.4 In any type of emergency involving plant systems or safety of the plant, the Operations Supervisor in the Command Center will take charge with directions from the Control Room Duty Supervisor.

4.4.5.5 Task Supervisor

The Task Supervisor will be present in the Command Center during the task execution to supervise his assigned task(s). If

FOR USE IN UNIT II ONLY

Revision
No.

FOR USE IN UNIT II ONLY

GPU Nuclear

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

difficulties arise in the completion of his task, he is to advise the CAG entry supervisor on means to correct the situation. If deemed necessary, the task supervisor will be asked to communicate directly with the entry team.

4.4.5.6 Safety Representative

As determined by the Site Supervisor, GPUN TMI Safety and Health, a Safety Representative may be in the Command Center to monitor activities of the various team members via CCTV for signs of heat stress and/or violation of safety criteria. If in the opinion of the Safety representative proper health and safety controls are not being exercised, he is to provide the entry supervisor with specific directions to remedy the situation including termination of that part of the entry.

4.4.5.7 Prior to the start of and during the entry the following essential positions will be manned:

BNoC Entry Supervisor

BNoC Entry Coordinator

BNoC or GPUN Task Supervisor (as needed for specific task)

GPUN Radiological Controls

GPUN Operations Supervisor

GPUN Safety (if specified by the Site Supervisor, GPUN TMI Safety and Health)

- NOTES:**
1. The Site Supervisor, GPUN TMI Safety and Health shall notify the CAG Supervisor of those tasks for which a Safety Representative is required.
 2. At the option of the Entry Supervisor, the Task Supervisor may replace the Entry Coordinator during performance of a task; both are not required at the same time.

4.4.6 Casualty Procedures

The following Site Procedures have specific Casualty Procedures for in-containment activities. Copies of these procedures shall be available in the Command Center.

4.4.6.1 SOP R-2-82-007 Procedure for Rescue of Personnel From Polar Crane

FOR USE IN UNIT II ONLY

Revision

0

FOR USE IN UNIT II ONLY

TMI-2 Unit
Administrative Procedure Manual

Procedure No.
4300-ADM-3240.1

Title

Access To and Work in the Containment Building

4.4.6.2 Procedure 2202-3.1 Fire

4.4.6.3 Procedure 1054.16 Contaminated Injuries/Radiation Overexposure

4.4.6.4 Procedure 2202-1.7 Excessive Radiation Levels

4.5 Control Room Interface

A CCTV console and intercom is to be installed in the control room for monitoring containment entry activities. The Command Center will be in charge of all entry activities and an operations supervisor will normally be present in the Command Center. The control room is not expected to participate in the conduct of the entries and will use the console to monitor in-containment activities; however if any Control Room indications show a situation that could potentially upset Reactor Building conditions, this information shall be communicated to the Command Center immediately.

Installation or operation of the CCTV and intercom in the control room is not a prerequisite for containment building entry.

In the event of an emergency in the containment which involves plant equipment and could therefore impact plant status, all activities in the containment will be secured. The operations supervisor in the Command Center will assume control of Reactor Building activities, with directions from the Control Room Duty Supervisor, to return plant status to normal. Command Center personnel will assist as necessary to control the emergency. Non-qualified personnel will not be used to control emergencies.

If qualified personnel are in the containment building as part of the day's activities, they may be utilized to recover from any emergency. All other personnel in containment will be directed to exit the building.

5.0 RESPONSIBILITIES

Responsibilities are as presented within Section 4.0 of this procedure.

6.0 REFERENCES

6.1 Procedure 4000-ADM-3040.3, "Engineering Change Authorization"

6.2 Procedure RCP 4045, "Radiological Review of Work Instructions"

6.3 Procedure RCP 4122, "Radiation Work Permit"

6.4 Procedure RCP 4123, "Self Reader Dosimeter Usage and Record Keeping"

6.5 Procedure RCP 4238, "Bioassay Program"

FOR USE IN UNIT II ONLY

Revision
No.

0

Title

Access To and Work in the Containment Building

- 6.6 Procedure RCP 4101, "Air Sample Counting, Handling and Actions"
- 6.7 Procedure RCP 4104, "Air Sampling Procedures"
- 6.8 Procedure RCP 4100, "Radiological Surveys"
- 6.9 Procedure RCP 4200, "TLD Assignment, Issue and Data Handling"
- 6.10 Procedure RCP 4015, "Administrative and Emergency Exposure and Contamination Limits"
- 6.11 Procedure 2104-4.91, "Reactor Building Purge Using the Modified Purge System"
- 6.12 Procedure AP 1034, "Control of Combustible Materials"
- 6.13 Procedure MP 1410-Y-26, "Welding, Cutting, Grinding and Open Flamework Procedure for Fire Safety"
- 6.14 Procedure RCP 4052, "Selection, Prescription and Use of Respiratory Protection"
- 6.15 Procedure RCP 4125, "Use of Anti-Contamination Clothing"
- 6.16 Procedure 1631.2, "Sampling of Reactor Building"
- 6.17 Procedure RCP 4021, "Training Requirements"
- 6.18 Procedure RCP 4030, "Mock Up Training and Job Briefings"
- 6.19 Operations Procedure 2104-4.55, "Reactor Building Entry"
- 6.20 Special Operating Procedure R-2-82-007, "Procedure for Rescue of Personnel from Polar Crane."
- 6.21 Procedure 2202-3.1, "Fire"
- 6.22 Procedure 1054.16, "Contaminated Injuries/Radiation Overexposure"
- 6.23 Procedure 2202-1.7, "Excessive Radiation Levels"
- 6.24 Procedure 1407-1, Unit 2 Corrective Maintenance Procedure

7.0 ATTACHMENTS

None

ATTACHMENT E-6
CASUALTY PROCEDURE
FOR

HIGH RADIATION CONDITION IN-CONTAINMENT

This procedure supplements Procedure 2202-1.7

HIGH RADIATION CONDITION IN CONTAINMENT

HIGH RADIATION CONDITION DETECTED BY ENTRY PERSONNEL (Entry in Progress)

NOTE: For purposes of this document, the following shall be considered high radiation conditions:

1. An unanticipated increase in the general area background, detected by hand-carried instruments, by a factor of five from the most recently recorded previous survey information.
2. An unanticipated increase in the general area background, detected by hand-carried instruments, by a factor of five during the entry.

Entry Personnel shall:

1. Report readings to Command Center.
2. Move to a lower radiation area if any.
3. Proceed to personnel airlock as directed by Command Center.
4. Entry team leader report status and location of all team members.

Command Center shall:

1. Notify all personnel in containment of high radiation.
2. Order all personnel to exit building, unless it is determined that high radiation conditions were caused by ongoing activities and an evaluation is made by Radiological Controls which concludes that an evacuation is not necessary.
3. Notify the Control Room.
4. Notify the HP Foreman.
5. Notify the Ante Room.

Control Room shall:

1. Respond in accordance with Unit II Emergency Procedure 2202-1.7 using procedure requirements applicable to readings reported by the Command Center which would be appropriate, if containment building radiation monitor HP-R-213 had detected the reported radiation levels.

Ante Room shall (if so directed by the Command Center):

1. Record and report all exiting personnel.
2. Secure any entry preps and clear Ante Room to receive exiting personnel.

HIGH RADIATION CONDITION DETECTED BY THE CONTROL ROOM
(Entry in Progress)

NOTE: HP-R-213 is the only area radiation monitor currently operational in containment. HP-R-211, 212 and 214 are not operational.

Control Room shall:

1. Respond in accordance with Unit II Emergency Procedure 2202-1.7.
2. Notify Command Center of readings and location.
3. Direct Command Center to evacuate containment if required.

Command Center shall:

1. Notify all entry personnel.
2. Order all personnel to exit the building if so directed by the Control Room.
3. Notify HP Foreman.
4. Notify Ante Room.

Entry Personnel shall (if so directed by the Command Center):

1. Secure work - de-energize equipment.
2. Team leaders report status and location of team members.
3. Exit the building.

Ante Room shall (if so directed by Command Center):

1. Record and report all exiting personnel.
2. Secure any entry preps and clear Ante Room to receive exiting personnel.

ATTACHMENT E-7
CASUALTY PROCEDURE
FOR
FIRE IN-CONTAINMENT

This procedure supplements Procedure 2202-3.1

FIRE IN CONTAINMENT

When Fire is detected by Entry Personnel:

Entry Personnel shall:

1. Notify Command Center - Fire Elevation _____ Fire Elevation _____
(Fill in blanks with appropriate elevation).

Followed by location, type, size
Example:
Location - 5' from In-Core Instrumentation Chase.
Type - Electrical, Trash, Chemical
Size - Small (can be extinguished with fire extinguisher)
Large (Cannot)
2. If in your judgement you can put the fire out and have the equipment to do so, then put it out, otherwise, leave and assemble to the Personnel Airlock # _____. (Airlock unaffected by fire)
3. Prior to leaving check to make sure no one is left in area. Entry team leaders are to report location and status of team members to Command Center.
4. Secure your equipment.
5. Do not, at anytime, endanger yourself except to prevent injury to another team member.

Command Center shall:

1. Notify all personnel in containment.
2. Notify the Control Room.
3. Notify HP Foreman.
4. Notify Ante Room.
5. Order all personnel not in vicinity of fire to proceed to Airlock via _____ stairwell and stand by to assist.
(Fill in blanks with airlock and stairwell unaffected by fire)
6. Direct entry personnel as required.
7. Maintain visible contact, if possible, via CCTV.
8. Maintain radio contact.

Command Center shall : (con't)

9. Monitor fire with CCTV if possible.

Note: In the event of fire, the Control Room shall assume control. The Command Center responsibility is limited to evacuation of personnel and provision of support as requested by the Control Room.

Control Room shall:

1. Initiate action in accordance with Unit II Emergency Procedure 2202-3.1, Fire.
2. Establish direct communications with Command Center (Main intercom/console when available).
3. If electrical, de-energize nearest breaker feeder.
4. Pressurize fire main in containment.
5. Secure purge.
6. Make arrangements to have plant fire extinguishers staged to the Ante Room to provide extinguishers to fight the fire for 45 minutes.

Ante Room shall:

1. Stage fire extinguishers to Airlock.
2. If personnel are in process of undress - expedite.
3. If personnel are in process of entry, secure entry (Entry personnel remove one set of booties and leave Ante Room. Muster in corridor).
4. Station man near intercom.
5. Station man in Airlock - Man Page Channel 1.
6. Remove excess equipment from Ante Room.
7. Prepare to aid fire brigade.
8. Provide two (2) two-way radios for fire brigade use (no setcoms).
9. Log and report all personnel exiting and entering the building.

HP Foreman shall:

1. Take charge in Ante Room/staging area for HP matters only.
2. Direct HP Support to #1 Airlock and Man Page Channel 1.

Safety/First Aid shall:

1. Standby to assist - if personnel are injured.
2. Notify First Aid.

Fire Brigade shall:

1. Assemble as directed by Control Room.
2. Fire Brigade will enter the containment at the direction of the Control Room.
3. Command Center will assist as requested.

FIRE IN CONTAINMENT

When Fire is detected by the Command Center:

Entry Personnel shall:

1. Secure work and de-energize electrical equipment. Assemble at Airlock as directed by Command Center. Exit when directed. Team leaders report status and location of all team members.
2. Do not, at anytime, endanger yourself except to prevent injury to another team member.
3. If in the area, and fire extinguishers are available and in your judgement you can put out the fire, do so; otherwise leave area via route specified and exit as directed by the Command Center.

Command Center shall:

1. Notify all personnel in containment.
2. Notify the Control Room.
3. Notify HP Foreman.
4. Notify Ante Room.
5. Order all personnel not in vicinity of fire to proceed to Airlock via _____ stairwell and stand by to assist. (Fill in blanks with airlock and stairwell unaffected by fire)
6. Direct entry personnel as required.
7. Maintain visible contact, if possible, via CCTV.
8. Maintain radio contact.
9. Monitor fire with CCTV, if possible.

NOTE: In the event of fire, the Control Room will assume control. The Command Center responsibility is limited to evacuation of personnel and provision of support as requested by the Control Room.

Control Room shall:

1. Initiate action in accordance with Emergency Procedure 2202-3.1, Fire.
2. Establish direct communications with Command Center (Main intercom/console when available.)
3. If electrical; de-energize nearest feeder breaker.
4. Pressurize fire main in containment.

Control Room shall: (con't)

5. Secure purge.
6. Make arrangements to have plant fire extinguishers staged to the Ante Room to provide extinguishers to fight the fire for 45 minutes.

Ante Room shall:

1. Stage fire extinguishers to Airlock.
2. If personnel are in process of undress - expedite.
3. If personnel are in process of entry, secure entry (Entry personnel remove one set of booties and leave Ante Room. Muster in corridor).
4. Station man near intercom.
5. Station man in Airlock - Man Page Channel 1.
6. Remove excess equipment from Ante Room.
7. Prepare to aid fire brigade.
8. Provide two (2) two-way radios for fire brigade use (no setcoms).
9. Log and report all personnel exiting and entering the building.

HP Foreman shall:

1. Take charge in Ante Room/staging area for HP matters only.
2. Direct HP Support to #1 Airlock and Man Page Channel 1.

Safety/First Aid shall:

1. Standby to assist - if personnel are injured.
2. Notify First Aid.

Fire Brigade shall:

1. Assemble as directed by Control Room.
2. Fire Brigade will enter the containment at the direction of the Control Room.
3. Command Center will assist as requested.

FIRE IN CONTAINMENT

When fire is detected by the Control Room:

Entry Personnel shall:

1. Secure work and de-energize electrical equipment. Assemble at Airlock as directed by Command Center. Exit when directed. Team leaders report status and location of all team members.
2. Do not, at anytime, endanger yourself except to prevent injury to another team member.
3. If in the area, and fire extinguishers are available and in your judgment you can put out the fire, do so, otherwise leave area via route specified and exit as directed by the Command Center.

Command Center shall:

1. Notify all personnel in containment.
2. Notify HP Foreman.
3. Notify Ante Room.
4. Order all personnel not in vicinity of fire to proceed to Airlock _____ via _____ stairwell and stand by to assist. (Fill in blanks with airlock and stairwell unaffected by the fire.)
5. Direct entry personnel as required.
6. Maintain visible contact, if possible, via CCTV.
7. Maintain radio contact.
8. Monitor the fire via CCTV if possible.

NOTE: In the event of fire, the Control Room will assume control. The Command Center responsibility is limited to evacuation of personnel and provision of support as requested by the Control Room.

Control Room shall:

1. Notify Command Center, fire in containment.
2. Initiate action in accordance with Emergency Procedure 2202-3.1, Fire.
3. Establish direct communications with Command Center (main intercom/console if available).

Control Room shall: (con't)

4. If electrical, de-energize nearest feeder breaker.
5. Pressurize fire main in containment.
6. Secure purge.
7. Make arrangements to have plant fire extinguishers staged to the Ante Room to provide extinguisher to fight the fire for 45 minutes.

Ante Room shall:

1. Stage fire extinguishers to Airlock.
2. If personnel are in process of undress - expedite.
3. If personnel are in process of entry, secure entry (Entry personnel remove one set of booties and leave Ante Room. Muster in corridor.)
4. Station man near intercom.
5. Station man in Airlock - Man Page Channel 1.
6. Remove excess equipment from Ante Room.
7. Prepare to aid fire brigade.
8. Provide two (2) two-way radios for fire brigade use (no setcoms).
9. Log and report all personnel exiting and entering the building.

HP Foreman shall:

1. Take charge in Ante Room/staging area for HP matters only.
2. Direct HP Support to #1 Airlock and Man Page Channel 1.

Safety/First Aid shall:

1. Standby to assist - if personnel are injured.
2. Notify First Aid.

Fire Brigade shall:

1. Assemble as directed by Control Room.
2. Fire Brigade will enter the containment at the direction of the Control Room.
3. Command Center will assist as required.

ATTACHMENT E-8
CASUALTY PROCEDURE
FOR
PERSONNEL INJURY OR SICKNESS IN-CONTAINMENT

This procedure supplements Procedure 1054.16

PERSONNEL INJURY OR SICKNESS

When an injured or sick individual is found by entry personnel, the Command Center or the Control Room,

HP Foreman shall:

1. Take charge in the Ante Room/staging area for HP matters only.
2. Send an additional HP for duty in the Ante Room. .
3. Provide recommendation for best use of available personnel from a radiological viewpoint.
4. Make preparations to receive and monitor contaminated personnel.
5. Log and report all exiting personnel.

Safety/First Aid shall:

1. Maintain representation in the Command Center.
2. Provide rescue team as soon as practicable.
3. Make recommendations on rescue action, evacuation, respirator removal when information is available.

Control Room shall:

1. Initiate action in accordance with procedure 1054.16, Contaminated Injuries/ Radiation Overexposure.
2. Establish direct communications with the Command Center.
3. Muster the rescue and assistance team and stand by to assist.

Command Center shall:

1. Request information on the condition of the individual concerned.
2. Notify other personnel in containment, the Ante Room, Control Room, the HP Foreman and Safety/First Aid.
3. Secure all non essential work including entrance into containment by teams for purposes other than rescue or assistance.
4. Verify locations and stations of ALL entry personnel.

Command Center continued:

5. Direct Ante Room assistance team to enter, if required.
6. Insure communications have been established in key locations
(containment, Ante Room, Control Room, HP Foreman)
7. Based on Safety recommendations, render assistance with Ante Room team.

Ante Room shall:

1. Quickly undress any team members exiting.
2. Station one man at the intercom.
3. Assistance team prepare to enter and stand by for instructions in
Airlock. Man page, channel 1.
4. Secure any routine work.
5. Hold any team ready for entry in stand by.
6. Remove excess equipment from Ante Room.

Entry Personnel shall:

1. Determine the condition of the individual and nature of injuries;
question him if he is conscious.
2. Inform the Command Center of these facts by fastest available means,
have one man in sight of CCTV camera, if possible. A status report
should include:

Name of individual, location, description of injury and condition
(conscious, unconscious, bleeding, breathing problems, electric
shock, heat stress, able to walk, etc.)

3. Entry team leaders report status and location of team members.
4. Await further instructions.
5. Do not move the individual without permission of the Command Center.

Entry Personnel shall: (Continued)

6. If the individual is having difficulty in breathing, the respirator may be removed. Caution must be exercised in removing the respirator in order to avoid additional injury to the individual. If breathing difficulty is not evident, do not remove the respirator without permission from the Command Center.

DO NOT MICROFILM
THIS PAGE

APPENDIX F
PHOTOGRAPHS AND VIDEOTAPE RECORDINGS
OF THE DECONTAMINATION EXPERIMENT

CONTENTS

PHOTOGRAPHS	F-1
VIDEOTAPING	F-4

ATTACHMENT F-1	GENERAL PHOTOGRAPHS AND DESCRIPTIONS (Photographs F-1 Through F-20)
----------------	--

APPENDIX F - PHOTOGRAPHS AND VIDEOTAPE RECORDINGS
OF THE DECONTAMINATION EXPERIMENT

PHOTOGRAPHS

The successful use of still cameras to document the conditions of specific areas and items is a major accomplishment of the entry program. Photographs were used to characterize the general condition of the reactor building as well as to identify specific problem areas (see Attachment F-1). The photographs proved a valuable planning and training aid to task planners and entry personnel.

Equipment

The equipment used to photograph the inside of the reactor building consisted of 35 mm SLR cameras (Nikon FE, Pentax LX, and Nikonas III), each equipped with an autowinder and standard lens (28, 35, or 50 mm or telephoto/zoom lens). The flash units (Vivitar 285 or Metz 60 CT-1) had Nikad rechargeable batteries in an internal or belt-type pack. Kodacolor film (ASA 100 or ASA 400) was used most of the time. Ultraviolet haze type filters were used to protect the lens and the eyepieces for the viewfinder from contamination. The cameras and flash units were completely covered, except for the lens and viewfinder, in a handmade, tight-fitting plastic bag which allowed the user to focus and operate the shutter freely. All other settings were preset and locked down in accordance with the requirements of lighting, distance, and film speed for the task. Only one case of severe radiation fogging occurred.

The process of bagging the camera and flash units to prevent contamination took approximately 2 man-hours per camera. Some manufactured camera containments were tested but without the success of the handmade type. Unbagging the camera after use required more time and careful handling to prevent contamination of the camera and film.

Development and Distribution of Photos

The film was developed and 8- x 10-inch prints were made by the Bechtel Photo Lab and EG&G. The photographs were assigned numbers prior to reproduction through use of the proof sheet. These numbers were made a permanent part of each negative and print.

The numbers were assigned by two methods. The first method was to number the photographs by entry number, camera number (arbitrarily assigned), and negative number (i.e., Entry 36, 1-29). This provided easy documentation of the photographs; in addition, a map could be drawn to show the location and angle of the photographs. The second method was used in a reactor building characterization task with a camera and a 250-shot film pack. The reactor building was broken down into areas, and the areas were photographed from designated locations. The photographs were then numbered by entry number, area, location number, and photograph number taken at the position (i.e., Entry 26, Area 12A, 7.4). Documentation for the second method was more confusing than for the first method since it was difficult to keep track of the total number of photographs, but the advantage of the second method was that the location and angle were specified.

Problems Encountered

Diverse problems were encountered in obtaining good quality photographs. The source of the problems ranged from the photographers themselves to the development of the film. One of the major difficulties arose from the fact that personnel taking the photographs were unfamiliar with 35 mm cameras and their operation. Training for these people was usually limited to showing them (a) the camera's settings, (b) how to focus the camera and operate the shutter, (c) how to determine when the flash was ready, and (d) how to tell if the camera was jammed. A short time was spent on practicing how to focus the camera while wearing a respirator, a problem which varied among individuals and was almost impossible to correct. A couple of practice photographs were also

taken. Any training beyond this point was limited by the inability of the photographer to manipulate the other settings or effect minor repairs because of the anticontamination bag surrounding the camera.

Another major problem involved equipment malfunction or breakage. The task would have to be scrubbed whenever the camera jammed, flash stopped functioning, settings were bumped off from the proper location, or any part of the camera or flash was broken. The camera and/or flash would then have to be unbagged, decontaminated, repaired, and then rebagged prior to reuse. The problem of breakage was most frequently encountered, especially breakage of the flash units - it was difficult to impress upon "non-photographers" that careful handling of 35 mm cameras is required.

It was also difficult to impress upon inexperienced photographers the type of photographs the camera was set up to take and the fact that almost any other type of photograph would not turn out. Adding to these problems was the fact that the photographic assignment was, for the most part, an add-on task to an individual's main body of work rather than a primary concern. This circumstance only emphasized the weak areas in training and execution.

Development and distribution of the photographs proved to be yet another major problem, primarily because of the amount of time required to make prints and slides, to copy negatives (ensuring that they were numbered and oriented correctly), to collate the copies, and to make distribution. Each set of photographs had its own special requirements: some needed date and number of required copies; others could be handled without regard for numbering or making the required distribution.

Lessons Learned

The lessons learned from the work accomplished to date are important to note so that future performance can be improved. Although the photographic equipment used was excellent, cameras employing a fixed focus would probably be

easier to use, in some cases provide better photographs, and make preparations easier. All photographic documentation, processing, and distribution should be handled by one group to eliminate confusion. The same group should also be responsible for obtaining extra copies or reprints. All negatives should be kept in a central location where they can be protected from loss or damage. The Bechtel Photo Lab is the most logical choice for this storage location. A log in/out system should be instituted to prevent loss of photographs or sets of photographs that are available for use by more than one group.

When quick turnaround of photographs was required, the best method proved to be making up the required sets without numbering them and making the standard distribution of the numbered prints later. This method got the photographs out as quickly as possible and still allowed control of the distribution. When the photographs are not required immediately, distribution could be held up and all prints numbered for documentation.

More time spent on selection and training of personnel would have been well worth the costs involved and would have helped minimize problems. Training should include actual taking of photographs under varied conditions with subsequent discussion of the results and suggestions for improvement. It should be noted that while a general photographic survey is very useful, it does not provide details or show orientation of specific objects. Several photographs from various angles need to be taken to document these items.

VIDEOTAPING

The installation of the CCTV camera system prior to the start of the Decontamination Experiment provided the ability to characterize the reactor building and allowed documentation of the decontamination work performed. In addition to the black-and-white videotapes obtained through the CCTV system, color videotapes were made of specific work tasks with a portable video camera and recorder. The videotapes will facilitate training and orientation of personnel for future reactor building entries.

Equipment

Equipment used in the videotaping operations is comprised of a permanently installed CCTV system: a black-and-white, low-light, Sony hand-held camera tied into the main CCTV system, and a color Hitachi hand-held camera connected to a portable Sony videotape recorder (VTR).

The main CCTV system consists of eight cameras which can be panned, tilted, zoomed in and out, and focused from a remote control panel. Images from two cameras at a time can be recorded on Sony VTRs. The cameras themselves are black and white with low-light requirements; therefore, no additional lighting outside normal building lighting is needed. The VTRs can use either a Sony XCA 60-minute tape or a 20-minute tape. The Sony camera was used to cover areas outside the view area of the main CCTV system. The Hitachi camera was used to film specific work tasks in color. Because it was not low-light sensitive, the Hitachi camera required additional lighting to obtain the desired results. The preparation of the hand-held equipment used in the reactor building was similar to the preparation of 35 mm cameras. The cameras and tape decks were completely bagged (except for the lenses) to prevent contamination of the components and tapes.

Distribution

A distribution system for videotapes was never developed prior to the Decontamination Experiment. As a consequence, the tapes were simply numbered by entry and sequence and stored for later distribution. Similarly, the tapes obtained in the characterization and in the decontamination work were held for later editing and distribution. If any tape was requested for special use, it was loaned without hesitation.

Problems Encountered

Problems with the video equipment during the Decontamination Experiment caused the loss of documentation of the work mostly because of breakdowns in the main CCTV cameras. Since there was no overlap of coverage areas between cameras, the loss of a camera meant the loss of coverage in the area around that camera. Repairs of the cameras were dictated by the availability of spare parts.

Other problems included the requirement for additional lighting and the bulky VTR that were necessary when the Hitachi camera was in use, and problems with the cabling required to transmit the signal out of the reactor building when the Sony camera was used.

Lessons Learned

The lessons learned from the use of the video equipment and taping done remotely and locally cover the entire scope of the task. The equipment used both inside and outside the reactor building should be as simple and easily repairable as possible without loss of quality. The simplicity of the equipment will also facilitate its preparation for use in the reactor building. In addition, sufficient equipment must be on hand to use for training and repairs to avoid loss of coverage of tasks.

Another lesson learned is that general coverage by videotaping is not sufficient to show details of most equipment because taping angles do not provide the best view.

Improvements can be made in the handling of videotapes. The tapes should be labeled with the tasks covered so that the tapes do not have to be reviewed and labeled later. This will also expedite the editing process in the future. Duplicates of the tapes should be made as soon as possible and stored separately from the originals to minimize chances of loss or damage. A sign in/out log should also be maintained to prevent loss of the tapes.

ATTACHMENT F-1
GENERAL PHOTOGRAPHS AND DESCRIPTIONS

ATTACHMENT F-1

GENERAL PHOTOGRAPHS AND DESCRIPTIONS

Photographs F-1 to F-8

These are examples of the areas that could not be cleaned with the spin jet because of the lack of operating room. Residual debris in these areas contributed to area radiation levels.

Photograph F-9

This is an area on elevation 305' where a 2000 psi and low flow rate technique was used. As the photograph shows, the cleaning was not effective where the pressure and flow rate were below the optimum for effective decontamination results.

Photograph F-10

The equipment hatch and floor around it on elevation 305' were cleaned with 6000 psi and 24 gpm water pressure and flow rate. Note the difference in effectiveness between this combination and the one illustrated by Photograph F-9.

Photograph F-11

In this area the outline of where the spin jet operated is visible, as are the portions not adequately cleaned. If the pressure used here had been increased and the worker rate slowed, the floor would be cleaner. In training on similar surfaces in the auxiliary building, there was a very fine line between the pressure that adequately cleaned and the pressure that stripped the paint.

Photograph F-12

This area in front of the open stairwell on elevation 305' was a major source of recontamination due to the heavy traffic.

Photograph F-13

This photograph shows that the diamond plate has some oxidation but is fairly clean overall. There are some floor areas not effectively cleaned where wheel marks are visible in the debris. Also, the primer is exposed in spots due to traffic and wear.

Photograph F-14

The steel grating on elevation 347'-6" was cleaned fairly well. However, during the flushing, water and debris went through the grating onto elevation 305'.

Photograph F-15

This is an example of surface deposition sample points for pre- and post-decontamination. Note that the borings have been painted.

Photographs F-16 and F-17

During the flushing activities, junction boxes and critical components of the reactor head service structure were protected with yellow herculite.

Photograph F-18

Pump and heater equipment set up for training is shown.

Photograph F-19

Air lock No. 2 and contamination control corridor for mock-up are shown.

Photograph F-20

Command center monitors during decontamination operations are shown.

ENTRY 56 AREA 12B-5

PHOTOGRAPH F-1

ENTRY 56 AREA 7B-9

PHOTOGRAPH F-2

ENTRY 56 AREA 7C-10

PHOTOGRAPH F-3

ENTRY 56 AREA 7A-13

PHOTOGRAPH F-4

ENTRY 56 AREA 12B-4

PHOTOGRAPH F-5

ENTRY 56 AREA 12A-3

PHOTOGRAPH F-6

ENTRY 56 AREA 12A-9

PHOTOGRAPH F-7

ENTRY 56 AREA 12A-25

PHOTOGRAPH F-8

ENTRY 56 AREA 12C-4

PHOTOGRAPH F-9

ENTRY 56 AREA 12A-2

PHOTOGRAPH F-10

PHOTOGRAPH F-11

ENTRY 56 AREA 12A-7

PHOTOGRAPH F-12

ENTRY 56 AREA 12A-22

PHOTOGRAPH F-13

ENTRY 56 AREA 7A-20

PHOTOGRAPH F-14

ENTRY 56 AREA 7A-16

PHOTOGRAPH F-15

ENTRY 56 AREA 12C-11

PHOTOGRAPH F-16

PHOTOGRAPH F-17

PUMP AND HEATER FOR TRAINING

AIRLOCK NO. 2 MOCKUP

PHOTOGRAPH F-19

PHOTOGRAPH F-20

DO NOT MICROFILM
THIS PAGE

APPENDIX G

VIDEOTAPE AND WORK PACKAGE LISTING

APPENDIX G - VIDEOTAPE AND WORK PACKAGE LISTING

<u>Entry</u>	<u>Date</u>	<u>Tape Numbers</u>	<u>Work Package Numbers</u>
10	5-14-81	1-1, 2-1	
18	10-29-81	1-1, 1-2, 1-3, 1-4, 2-1, 2-2	1, 9, 11, 18
24	12-9-81	1-1, 1-2, 1-3, 1-4, 1-5, 1-6, 2-1, 2-2, 2-3, 2-4	2, 5, 11, 21, 31, 40
25	10-15-81	1-1, 1-2, 1-3, 1-4, 1-5, 1-6, 2-1, 2-2	2, 17, 36, 40, 42
27	1-5-82	1-1, 1-2, 2-1	2, 25, 40, WPG-1
33	2-4-82	1-2, 1-3, 2-1, 2-2	2, 26, 66, 69, 70, NRC-1
34	2-16-82	1-1, 1-2, 1-3, 1-4, 2-1, 2-2	2, 20, 66, 71, 72, 75
39	2-25-82	1-1, 1-2, 1-3, 1-4, 1-5, 1-6, 2-1, 2-2, 2-3, 2-4	2, 34, 38, 41, 46, 71, 77, 78, 79
40	2-26-82	1-1, 1-2, 1-3, 1-4, 1-5, 1-6, 1-7, 2-1, 2-2, 2-3, 2-4	2, 20, 47, 68, 73

VIDEOTAPE AND WORK PACKAGE LISTING
(Continued)

<u>Entry</u>	<u>Date</u>	<u>Tape Numbers</u>	<u>Work Package Numbers</u>
41	3-2-82	1-1, 1-2, 1-3, 2-1, 2-2	2, 47, 66
42	3-3-82	1-1, 1-2	2, 31
43	3-4-82	1-1, 1-2, 1-3, 1-4, 1-5, 1-6, 2-2	2, 47, 53
44	3-5-82	1-1, 2-1	2, 53
45	3-8-82	1-1, 1-2, 1-3, 2-1	2, 49, 53
46	3-10-82	1-1, 1-2, 1-3, 1-4, 1-5, 2-1, 2-2	2, 49, 50
47	3-11-82	1-1, 1-2, 1-3, 1-4, 1-5, 2-1	2, 49, 51
48	3-12-82	1-1, 1-2, 1-3, 1-4, 1-5, 1-6, 2-1	2, 51
49	3-15-82	1-1, 1-2, 1-3, 1-4, 2-1, 2-2	2, 47, 51, 90
50	3-17-82	1-1, 1-2, 1-3, 1-5, 2-1, 2-2, 2-3	2, 47, 51, 52

VIDEOTAPE AND WORK PACKAGE LISTING
(Continued)

<u>Entry</u>	<u>Date</u>	<u>Tape Numbers</u>	<u>Work Package Numbers</u>
51	3-18-82	1-1, 1-2, 2-1	2, 93
52	3-19-82	1-1, 1-2, 2-1	2, 47
53	3-24-82	1-1, 1-2, 1-3, 1-4, 2-1, 2-2, 2-3, 2-4	2, C0001, D100, M0001, 54, 80, 81
54	3-25-82	1-1, 2-1; 2-2, 2-3, 2-4, 2-5	2, 85, 86, 92, D101
55	3-26-82	2-1, 2-2, 2-3, 2-4, 2-5, 2-6, 2-7	2, 54, 81, 85, 86, C0001, E0002, D101
56	3-31-82	2-1, 2-2, 2-3, 2-4	2, 53, D0001, D100, E0002

WORK PACKAGES

<u>Work Package Number</u>	<u>Title</u>	<u>Gross Decontamination Experiment Data Acquisition Task Number</u>
1	Area Cleanup	
2	HP Survey	
3	Electrical Power Walkdown	
4	Pull Small Grating	
5	Equipment Protections	
6	Decontamination Photos	
7	Insulation Removal	
8	Snubber Inspection	
9	Videotape	
10	Reinstall 561 Blank	
11	HPR-212	
12	AHV-74	
13	AHV-6	
14	Biological Samples	

WORK PACKAGES (Continued)

<u>Work Package Number</u>	<u>Title</u>	Gross Decontamination Experiment Data Acquisition Task Number
15	Liquid Sample at Polar Crane	
16	Sump Refill Line	
17	Surface Deposition	
18	Gamma Spectrometer	
19	Radio System	
20	120-Volt Service (ECM 950)	
21	Transient Combustible Control Inventory	
22	Install Portable CCTV Cameras	
23	Polar Crane Walkdown	
24	Polar Crane Inspection	
25	Supports for Spider at Polar Crane and Install Lift Rig	
26	Power to Spider/Operational Test	

WORK PACKAGES (Continued)

<u>Work Package Number</u>	<u>Title</u>	<u>Gross Decontamination Experiment Data Acquisition Task Number</u>
27	Pull Hatch	
28	Stage Spider	
29	Operation of High Reach	
30	Move Beams	
31	CCTV Work	
32	Ramp	
33	Stage High Reach	
34	Load Test Spider Supports in Containment	
35	CAG Inspection and Radio Test	
36	Hydrogen Burn Samples	
37	Provide Access Platform at Elevation 347'-6"	

WORK PACKAGES (Continued)

<u>Work Package Number</u>	<u>Title</u>	<u>Gross Decontamination Experiment Data Acquisition Task Number</u>
38	Safety Equipment for Spider	
39	Constant Air Monitors	
40	Characterization Survey	
41	Install Hoses and Test	
42	Shut Ventilation Dampers to Elevation 282'	
43	HPR-214 Inspection	
44	Snubber Removal	
45	Cable Samples	
46	Decontaminate Water (ECM 963)	
47	LP Elevation 305'	1, 3, 4, 5
48	Decontaminate Stairwell	2
49	LP Elevation Missile Shields, D-Rings	4, 5
50	LP Elevation 347'-6"	4

WORK PACKAGES (Continued)

<u>Work Package Number</u>	<u>Title</u>	<u>Gross Decontamination Experiment Data Acquisition Task Number</u>
51	HP Elevation 347'-6"	4
52	HP Elevation 305'	6
53	LP Elevation Polar Crane	
54	Strippable Coatings (Elevation 347'-6")	4
55	Spider Lift Electrical Inspection	
56	Load Test and Welding Inspections for Spider Supports (Out of Containment)	
57	Install Goosenecks	
59	Move Resin Column	
60	New Temperature Lights on Elevation 305'	
61	Emergency Lights	
62	Electrical Status 480 V Systems	

WORK PACKAGES (Continued)

Work Package Number	Title	Gross Decontamination Experiment Data Acquisition Task Number
63	Refueling Canal Lights	
64	Remove HPR-214	
65	Pre-head Lift Exam No. 1 (Tool Inventory)	
66	Replace Fire Hoses	
NRC-1	NRC Inspection	
68	Equipment Protection on Polar Crane	
69	Remove RM-16 (Radiation Detectors)	
70	Identify Contents of 55-Gallon Drums on Elevation 347'-6"	
71	Gamma Spectrometer Rigging	
72	Gamma Spectrometer on Elevation 347'-6"	
73	Relocate CCTV Camera and Additional Lighting at Refueling Canal	
74	Fire Detection System	

WORK PACKAGES (Continued)

<u>Work Package Number</u>	<u>Title</u>	<u>Gross Decontamination Experiment Data Acquisition Task Number</u>
75	Containment Physical Characteristics; Supply Photos	
76	Remove Pendant From P.C.	
77	Decontamination Safety Inspection	All
78	Quarterly Inspection of P.C. Equipment	
79	Replace and Protect Lifting Equipment for ALARA Considerations	
80	Mechanical Floor Scrubber	4
81	Strippable Coating on Elevation 305'	5
82	Special O ₂ and H ₂ Gas Monitoring	
83	Combustible Gas Monitoring	
84	Install Landing Platform on Elevation 305'	
85	Post-Decontamination Surface Deposition	

WORK PACKAGES (Continued)

<u>Work Package Number</u>	<u>Title</u>	<u>Gross Decontamination Experiment Data Acquisition Task Number</u>
86	Post-Decontamination Containment Characterization	
87	Load Test Second Lift Rig	
88	Hydro "Orange Duck" NLB Pump Without Pulsation Damper	
89	Videotaping of Decontamination Operations	
90	Move Items from Elevation 347'-6" Storage Area	
91	Relocate Cameras to Elevation 347'-6"	
92	Incore Photographs	
93	Trash Removal	
D-100	Post-Test Photographs - Work Packages 49, 51, 52	4, 6
D-101	Videotaping in Reactor Building	

DO NOT MICROFILM
THIS PAGE

APPENDIX H
EXPERIMENTAL DESIGN AND METHODOLOGY

CONTENTS

EXPERIMENTAL DESIGN	H-1
EXPERIMENTAL MEASUREMENT METHODOLOGIES	H-7
RECOMMENDATIONS	H-8

TABLE H-1 Data Acquisition Specified in Sample Packages for
Gross Decontamination Experiment

ATTACHMENTS

H-1	TECHNIQUE SHEET - RO-2 AND RO-2A USE
H-2	TECHNIQUE SHEET - SWIPE SURVEY
H-3	DATA ANALYSIS

APPENDIX H - EXPERIMENTAL DESIGN AND METHODOLOGY

The purpose of this appendix is to detail the experimental design and methodology used to evaluate the efficacy of the decontamination techniques that were the subject of this experiment. The appendix is divided into separate sections addressing the experimental design and the experimental measurement methodologies.

EXPERIMENTAL DESIGN

In order to evaluate those techniques used to perform gross decontamination of the reactor building, a design was necessary to collect the needed data. Designs available for characterization studies give some guidance as to the necessary number and types of measurements. Any design applied for the specific purposes within the reactor building has to be tempered by the heterogeneity of the contamination and surface types, and by the time and dose constraints on workers in the containment.

The discussion on experimental design is divided into five sections: scope and purpose, relationship to the entry program and the large-scale decontamination experiment, design, implementation, and evaluation of design and its implementation.

Scope and Purpose

The scope of the data acquisition design included all flushing, scrubber, and strippable coating decontamination techniques as they were tested on the several reactor building surfaces, including special equipment items. The purpose of the data acquisition design was to allow comparison of the decontamination techniques used, in terms of removed contamination. The optimal techniques were to be identified by reactor building surface.

Relationship to Entry Program and to Large-Scale Decontamination Test

The design for data acquisition was based in part on the data acquisition results from the reactor building entry program and from the large-scale decontamination test. The objective of data acquisition during the initial reactor building entry program was to evaluate the probable mechanism of contamination and to characterize the radiological conditions of the reactor building surfaces.

Data and sample locations, which might elucidate the array of radiological conditions on the different reactor building surfaces, were identified. Many of these sample locations were repeatedly measured/sampled in order to determine changes in radiological conditions with time.

Data/sample locations designated for use in the large-scale decontamination test were marked so that they could be reevaluated after the test. The data/sample collection methods were used to define exact procedures for further characterization of the building, and for data acquisition tasks within the Gross Decontamination Experiment. For example, repeated measurements could be reproducible only if the orientation of the data acquisition technician was repeatedly the same with respect to walls, equipment, etc.

Experimental Design

The design used for data/sample collection was a simple extension of those points designated for reactor building characterization. The points designated were chosen to represent the array of surface/equipment types in the building. The design was minimal because of the constraints discussed below.

Intent of the Design

The sample/data points chosen were scattered over vertical and horizontal diamond plate and concrete surfaces, and on exposed surfaces of equipment

items. The points were scattered in areas known to be in the contamination pathway and areas only contaminated by secondary deposition.

The intent of the design was to furnish a before- versus after-decontamination technique comparison of removable and fixed contamination at the sample/data collection points. These data would then allow technique efficiencies to be compared by surface/equipment type.

Constraints

In order to rigorously evaluate the decontamination techniques used, a large data base was required. The problems in establishing a rigorous data base included:

- o Heterogeneity of reactor building surfaces and coatings
- o Irregular geometry of equipment surfaces
- o Heterogeneity of the contamination pathway and resulting deposition patterns
- o Difficulty in measurements made in an environment of multiple sources, changing patterns of resuspension and deposition, and high relative humidity

There were several constraints in obtaining data required to assess the efficiency of decontamination techniques. Consequently, the minimal data base to compare techniques was obtained. Constraints on the data acquisition tasks for the gross decontamination experiment included:

- o Number of worker man-hours available to support the data acquisition tasks
- o Man-rem available to support the data acquisition tasks

- o Cost of radiological analysis
- o Cost of data synthesis and interpretation

The impact of these constraints on the ability to statistically compare decontamination techniques should not be underestimated. In order to satisfy statistical criteria, it would be necessary to obtain many more data than were able to be designated for the gross decontamination experiment.

Sample/Data Point Designations

Sample/data points were designated within each treatment area. For the most part, these points were designated by the sample packages and were those used in the reactor building characterization. Detailed maps of sample/data point locations for specific treatment areas are shown in the next section. Table H-1 shows the types of data/samples requested for the two principal elevations. This table does not discriminate between surfaces of different materials or coatings, however. While designated points were dominately on concrete surfaces, the number of points certainly represents a minimum data base, even for these surfaces.

When work packages were prepared, some sample/data points were designated for more intensive evaluation. The rationale for these additions was the necessity to compare statistically before/after treatment measurements on at least one reactor building surface. Since it was unclear whether surfaces other than floors would be treated, additional data points were designated on floor surfaces as the work packages were prepared. The designation was made of at least one location in each treatment area near the middle of the area. At this location, not only would area and contact readings be made at the point, but at the ends of 1-meter intervals in a metric cross pattern. This resulted in five sets of measurements at these locations, rather than one set.

TABLE H-1. DATA ACQUISITION SPECIFIED IN SAMPLE PACKAGES FOR GROSS DECONTAMINATION EXPERIMENT

<u>Decontamination Technique</u>	<u>Number of Observations</u>		
	<u>Area Readings</u>	<u>Contact Readings</u>	<u>Swipe Samples</u>
<u>Low Pressure Flush</u>			
140 F, 15 gpm	4	19	19
140 F, 25 gpm	40	150	150
Ambient, 25 gpm	7	17	17
Ambient, 15 gpm	5	26	29
<u>High Pressure Flush</u>			
Ambient, 4000 psi, 5 gpm	1	9	9
Ambient, 4000 psi, 15 gpm	1	5	5
Ambient, 4000 psi, 25 gpm	1	11	11
Ambient, 6000 psi, 5 gpm	2	9	9
Ambient, 6000 psi, 15 gpm	1	14	14
Ambient, 6000 psi, 25 gpm	7	34	34
140 F, 2000 psi, 5 gpm	1	9	9
140 F, 2000 psi, 15 gpm	2	9	9
140 F, 2000 psi, 25 gpm	2	17	17

While the number of data points was thus increased appreciably, allowing more rigorous statistical treatment, the impact on man-hour and dose expenditure was minimal due to the proximity of the measurements.

Problems and Limitations in the Design

The problems in interpretation due to omission of data have been discussed in other sections and will not be treated here. However, there were certain

problems inherent in the data acquisition design that limit interpretations. These problems include:

- o The random pattern of sample points made representative area characterization difficult.
- o Too few data/sample points were designated on specific reactor building/equipment surfaces to allow adequate statistical evaluation.
- o The design did not address combination treatment effects, and these cannot be statistically differentiated.

Implementation of Experimental Design

The data acquisition tasks were implemented fairly successfully. Data/sample points were permanently marked and procedures dictated instrument orientation in order to allow reproducible measurements to be made.

Approximately 90 percent of the data specified for acquisition during operations were successfully obtained. This value does not include data omitted from work during operations by decisions made to expedite decontamination.

The greatest difficulty in implementation was in obtaining air samples. Equipment failures led to use of only the GPU radiological engineering air radioactivity data base. Another difficulty was in obtaining reproducible swipes because of the vastly changing surface moisture conditions during different operations of the experiment.

EXPERIMENTAL MEASUREMENT METHODOLOGIES

Instrumental Measurements

Area and contact radiation measurements were primarily made using the Eberline RO-2A. This instrument is tolerant of variable environmental conditions, can measure gamma and beta-gamma radiation, and is accurate in the range of values observed in the TMI reactor building. Several instruments were evaluated before the RO-2A was chosen for routine use (Walker et al, 1981).

Instrument measurements in-containment were difficult to obtain due to surface geometries and multiple radiation sources. Procedures were developed to minimize these impacts on data quality (see Attachment H-1).

Swipe Samples and Analysis

Swipe samples were taken to determine the relative amount of removable contamination and to determine isotopic composition of this removable fraction.

The procedure for taking swipes is shown in Attachment H-2. Swipes were analyzed on site by GPU staff.

Air Samples and Analysis

Although other samples were to be taken, due to equipment failures only the GPU air data are available. Particulates and tritium were measured in the morning and periodically during operations. In addition, breathing zone analyzers (BZAs) were used by workers during operations.

Personnel for Data Acquisition

During training and during the experiment it became apparent that qualified radiological control technicians were more efficient and accurate in data

acquisition tasks than other personnel. Familiarity with instruments, radiological conditions in-containment, and radio equipment, was necessary to ensure data quality.

Data acquisition tasks were monitored from the command center and points skipped were noted. Usually, full data acquisition tasks were completed. While some problems occurred in tracking data and samples, information integrity was largely preserved.

RECOMMENDATIONS

There are several recommendations which can be made as a result of the data acquisition activities supporting the Gross Decontamination Experiment.

- o The experimental design used should be based on Regulatory Guide 1.86 and on standard methods developed and available for radiological characterizations of building surfaces.
- o Planning should directly address the level of data required to meet the objectives of the experiment. Any confounding of effects due to experimental design or number of data points should be identified early.
- o Measurement methodologies should be carefully planned, and equipment should be checked and calibrated frequently.
- o Personnel qualified in data acquisition should be dedicated to these tasks. Training should be adequate to ensure implementation consistent with the purpose and goal of the work.
- o Data interpretation methods should be specified, and the adequacy of proposed data should be determined prior to the start of the experiment.

- o Changes in data acquisition during operations should be minimized.

ATTACHMENT H-1. TECHNIQUE SHEET - RO-2 AND RO-2A USE

DESCRIPTION

Radiation reading techniques must be such that a consistent reading will be obtained by various individuals involved in data collection. These techniques provide for a consistent method for placement of both the instrument and the data collector to reduce the magnitude of the variables contributed by shielding introduced by the body of the data collector, and to eliminate variables introduced by instrument location.

GENERAL

- o Instruments will have been calibrated within 90 calendar days of use.
- o Beta factors greater than 4.1 or less than 3.8 will not be acceptable for use in data collection.
- o Immediately prior to use, the instrument batteries will be checked and must be good for the instrument to be used.
- o Prior to being taken into the containment building, the instrument will be enclosed in a single, clear, poly bag. The bag will be sealed but will allow room for the operator to change the scale selector switch.
- o During readings involving contact with horizontal surfaces, the bottom of the instrument will be wiped, as necessary, with maslin cloths to prevent contamination buildup.

DETAILED INSTRUCTIONS

General Area Readings

- o Locate each survey point as listed in the data collection sheet.
- o Mark the surface at the points indicated with a number and by outlining the instrument while it is pointing directly away from the D-ring (if not previously marked).
- o Mark an arrow inside the outline pointing directly away from the D-ring, with the tail forming a 90-degree angle with the base of the R0-2A outline.
- o Mark the right side of the R0-2A with a large dot measured 2 inches from the back of the meter and 2 inches up from the bottom of the meter.
- o Stand at the tail of the arrow, centering the body behind the arrow.
- o Place the meter stick at the point of the arrow; hold it with the left hand.
- o Holding the R0-2A with the window closed and away from the body, place the right side of the R0-2A horizontally across the top of the meter stick with the dot centered over the meter stick.
- o The R0-2A meter face should be to the left of the meter stick.
- o Record the general area radiation reading on the data collection sheet.

Contact Surface Readings

- o Locate each survey point as listed on the data collection sheet.
- o Mark the surface of the survey point by outlining the instrument while it is pointing directly away from the D-ring wall (if not previously marked).
- o Mark an arrow inside the outline with the tail forming a 90-degree angle with the base of the RO-2 or RO-2A outline, with the arrow pointing directly away from the D-ring wall.
- o Position the body behind the tail of the arrow, located in the marked survey point, and center the body behind the arrow.
- o Open the window on the RO-2 or RO-2A and position the instrument within the marked outline, with the instrument meter scale aligned with the head of the arrow.
- o Obtain a reading for window open and record on the data collection sheet for the survey point.
- o Close the window on the RO-2 or RO-2A.
- o Position the instrument on the same survey point as described in item 3.2.6 with the window closed.
- o Obtain the closed window reading and record the data on the data collection sheet.

NOTE: Allow adequate time for the instrument reading to stabilize before recording the reading. (~10 seconds).

NOTE: If the meter reading is at the extreme low end of the scale,
select the next lower multiplier on the range selector switch.

ATTACHMENT H-2. TECHNIQUE SHEET - SWIPE SURVEY

DESCRIPTION

This technique describes how to conduct a swipe survey for data collection during the Decontamination Experiment.

GENERAL

- o Swipe survey locations will be numbered and marked using a template and a black indelible marker on all painted surfaces.
- o Swipe survey locations will be numbered and marked using a low- or no-chloride marker and a template on stainless steel surfaces.
- o Swipes will be individually numbered and will have numbered plastic bags.
- o Swipes will be taken within a marked 100 cm² area.

SMEAR COLLECTION

- o Package smears and label both the smear and package by data acquisition survey point number and containment entry number (i.e., 32-1, etc.).
- o Mount packaged smears on a ring holder in sequential order.
- o During movement into the containment and while in the containment, be careful not to contaminate the smears by touching, brushing, dropping, etc.

- o When ready to use a smear, remove the smear and package from the ring holder.
- o Carefully hold the smear package without touching the smear surface or internal packaging surfaces.
- o Holding the packaging in one hand, apply the face of the smear to the marked area where data are being collected and firmly swipe the entire 100 cm² surface using only one hand.
- o Close the smear folder which was held open, and insert the folder with the smear into the plastic bag.
- o Fold the plastic bag over the smear folder until all excess plastic has been wrapped around the smear folder.
- o Placing the loose end of the package down, insert the used smear into the used smear holder.
- o Repeat the above steps until all smear data collection is completed.
- o Upon exit from the containment, take the entire used smear container, with smears bagged, and label the bag with the entry number and area surveyed. Then carefully place the bagged smears into the shielded sample drum in the anteroom.

NOTE: Take caution not to contaminate with your gloves.

NOTE: Notify the command center if you loose a swipe.

NOTE: During debriefing, make known any swipes you feel may be cross contaminated.

ATTACHMENT H-3. DATA ANALYSIS

In order to evaluate the techniques tested, several decontamination reduction factors were calculated for each data point. The different DFs were based on area gamma, contact gamma and beta, and smearable pre- and post-test readings (see sample calculation below). Due to location (confined spaces, for example) or observed procedures, certain data points on the floor surfaces were not felt to be representative of the techniques used. Therefore, these points were eliminated from final analysis. Figures H-1 and H-2 identify and locate the points considered representative of the techniques for elevations 305' and 347'-6", respectively. The following sample calculation shows how the pre- and post-test readings were evaluated and DFs computed.

Sample Calculation

Area 1 LP Flush - Elevation 305' (from test data - Reference 1)

<u>Pre-test Location</u>	<u>Area Gamma (mrem)</u>	<u>Contact Gamma (mrem)</u>	<u>Contact Beta (mrem)</u>	<u>Cs-137 + Cs-134 Swipes (dpm/100 cm²)</u>
1 (Floor)	240	320	1060	5.13×10^6
12 (Floor)	170	286	2026	5.10×10^6
15 (Pipe)	200	200	380	-

<u>Post-test Location</u>	<u>Area Gamma (mrem)</u>	<u>Contact Gamma (mrem)</u>	<u>Contact Beta (mrem)</u>	<u>Cs-137 + Cs-134 Swipes (dpm/100 cm²)</u>
1	220	290	1930	5.37×10^6
12	107.6	146	539.6	4.62×10^6
15	-	100	228	0.417×10^6

Activity Removed (difference in contact gamma). The gamma measurements can be correlated to estimate the activity removed using the conversion factor 28 mrem/hr/ μ Ci/cm² (Reference 2). Remaining activity is estimated using the final contact beta measurements and the conversion factor 7.99 rem/hr/ μ Ci/cm² (Reference 2).

For Location 1, Δ gamma = 320 - 290 = 30 mrem/hr

$$\frac{30 \text{ mrem/hr}}{28 \text{ mrem/hr}/\mu\text{Ci/cm}^2} = 1.07 \mu\text{Ci/cm}^2$$

$$\text{Final beta} = \frac{1.930 \text{ rcm/hr}}{7.99 \text{ rem/hr}/\mu\text{Ci/cm}^2} = 0.241 \mu\text{Ci/cm}^2$$

<u>Location</u>	<u>Δ Gamma (contact)</u>	<u>Cesium Removed ($\mu\text{Ci/cm}^2$)</u>	<u>Final Beta (mrem/hr)</u>	<u>Cesium Remaining ($\mu\text{Ci/cm}^2$)</u>
1	30	1.07	1930	0.241
12	140	5	539.6	0.067
15	100	3.57	228	0.029

A Relative Decontamination Factor (RDF) is calculated by dividing total cesium (cesium removed + cesium remaining) by cesium remaining.

<u>Location</u>	<u>RDF</u>
1	$\frac{1.07 + 0.241}{0.241} = 10.8$
12	$\frac{5 + 0.067}{0.067} = 75.6$
15	$\frac{3.57 + 0.029}{0.029} = 124$

By swipes: $\frac{\text{Average floor pre-test}}{\text{Average floor post-test}} = \text{Decontamination Factor}$

$$\text{DF} = \frac{5.115 \times 10^6}{4.995 \times 10^6} = 1.02$$

Area dose reduction:

$$\frac{\text{pre-average area gamma} - \text{post-average area gamma}}{\text{pre-average area gamma}} = \frac{205 - 163.8}{205} = 20\%$$

Area Exposure Reduction Factor (ERF):

$$\frac{\text{pre-average area gamma}}{\text{post-average area gamma}} = \frac{205}{163.8} = 1.25$$

From operational parameter data (Reference 1):

$$\begin{array}{ll} 229 \text{ gallons used} & 229/989 \text{ ft}^2 = 0.24 \text{ gal/ft}^2* \\ 19 \text{ minutes total flush time} & 19/939 \text{ ft}^2 = 0.02 \text{ min/ft}^2* \end{array}$$

Dosimeter Readings:

Worker #1	173 mrem	
Worker #2	170 mrem	171.7 average dose
Worker #3	172 mrem	

$$\frac{171.7}{19 \text{ min}} \times \frac{60 \text{ min}}{1 \text{ hr}} = 542 \text{ mrem/hr}$$

$$\frac{171.7}{939} = 0.183 \text{ mrem/ft}^2$$

Sample Work Sheet

Table H-2 shows the sample work sheet that was developed for each test and what items were used to distinguish between the tests. The $\mu\text{Ci/cm}^2$ of average activity removed and remaining were not used as absolute values, but as separators between the various tests. The RDFs calculated from these numbers, however, did correlate with the surface deposition DFs.

Decontamination Factor

The DF used in the report is a measure of the efficiency for:

- o A particular process (e.g., low pressure flushing)

*Floor area for Area I is 939 square feet (from area calculations, Reference 3).

- o A particular application (e.g., particulate radioactive material as measured by swipe testing)
- o A particular iteration of that process (e.g., third flush).

in decontaminating or removing a contaminant from a given matrix. The contaminant is defined both in terms of the nature of the contaminant and the method by which it was measured before and after the process. To be directly compared, all facets of the DF determination were the same.

Methods. DF is expressed as:

- o Amount of activity removed
- o Amount of residual activity
- o Fraction of activity removed.

Where the RDF was determined by a direct measurement, care was used in evaluating the possible interference of ambient radiation fields.

Where DFs for a given situation can vary from segment to segment on the same material or situation due to a large number of variables, such as a wall or other large surface area, an average DF and the range of DF values were calculated. In complex systems, or areas of the "metric star," individual local DFs were used as appropriate.

Note: "Exposure Reduction Factor" is the ratio of the original exposure rate at a location to the final exposure rate after attempts at decontamination. The term ERF must not be confused with DF. They can differ for at least two reasons:

1. ERF is based on the item decontaminated, and there may be other uncleaned areas or sources nearby that contribute to the exposure rate. One could conceivably have a real DF of 100 or 1000 in an area, and the ERF could be 4 due to shine.

2. The source may consist of mixed beta and gamma emitters. The first decontamination may decrease the dirt covering the fixed activity, resulting in high beta fields. It may also preferentially remove one of the contaminants, changing the character of the field. The choice of selecting the method for RDFs was made based on these considerations.

Calculation References

1. Raw data from Decontamination Experiment (see Appendix C).
2. TDR 068, GPU Document, 1980.
3. Floor area calculations.

Key:

* Area Readings

A Air Samples

△ Overheads

□ Horizontal Surfaces

○ Vertical Surfaces

Plan El. 305'-0''

Figure H-1. Elevation 305' representative data points.

Key:

* Area Readings

□ Horizontal Surfaces

Vertical Surfaces

Figure H-2. Elevation 347'-6'' representative data points.

TABLE H-2. SAMPLE WORK SHEET (SUMMARY - ELEVATION 305')

Area	Surface	Area Dose Reduction (ERF) ^a	Average Cesium Activity ($\mu\text{Ci}/\text{cm}^2$)		RDF	Swipes - Cesium (dpm/100 cm^2)		Water Use (gal/ft ²)	Worker Rate (min/ft ²)	Worker Exposure Rates	
			Removed	Remaining		Final x 10 ⁶	DF			mrem/hr	mrem/ft ²
I LP 20 gpm Ambient	Floor	1.25/20%	3.03	0.154	20.7	4.995	1.02	0.24	0.02	542	0.183
	Stainless Steel	-	3.57	0.029	124	0.417	-	-	-	-	-
II LP 23 gpm 118 F	Floor	1.14/12%	2.29	0.466	5.91	1.058	13.3	0.144	0.012	817	0.16
	Stainless Steel	-	-	0.143	-	0.335	18.9	-	-	-	-
III LP 23 gpm 96 F	Floor	1.50/33%	44.6	0.691	65.5	6.09	0.89	0.22	0.019	154	0.048
IV LP 17 gpm 110 F	Floor	1.37/27%	6.21	0.23	28.0	8.19	2.38	0.205	0.017	515	0.146
X HP 14 gpm 2000 psi	Floor	0.9/0%	0.71	0.024	30.6	0.189	24.4	0.39	0.040	211	0.014
	Stainless Ambient Steel	-	0	0.019	1	0.460	0.91	-	-	-	-

a. Area dose reduction = $\frac{\text{average pre-test area gamma} - \text{average post-test area gamma}}{\text{average pre-test area gamma}}$

DO NOT MICROFILM
THIS PAGE.

APPENDIX I

GAMMA SPECTROMETER RESULTS

PRE-AND-POST DECONTAMINATION GAMMA-RAY
SCANS OF TMI-2 CONTAINMENT SURFACES,
ELEVATIONS 305 AND 347 FEET

E. D. Barefoot
J. E. Cline
J. A. Daniel
D. G. Keefer
T. L. McVey
E. A. Schlomer
C. D. Thomas, Jr.

April 22, 1982

SCIENCE APPLICATIONS, INC.

NUCLEAR ENVIRONMENTAL SERVICES

3 Choke Cherry Road, Rockville, Maryland 20850, (301) 977-4480

CONTENTS

SUMMARY.	1
MEASUREMENT TECHNIQUES AND DETECTOR CALIBRATION.	2
MEASUREMENTS AND RESULTS	7
REFERENCES	16
APPENDICES	18
Appendix A - Model of Detector Calibration for Extended Sources	18

TABLES

1. Gamma-Ray Energies and Source Intensities for Detector Calibration Standard	5
2. On-Axis and Off-Axis Distances at which Calibration Measurements were made.	6
3. Listing of Areas of TMI-2 Containment, Elevations 305- and 347-foot for which Measurements were made of the Surface Contamination by Gamma-Ray Scanning	12
4. Net ¹³⁷ Cs Counting Rates and Surface Contamination Levels for the Gamma-Ray Scans.	15

FIGURES

1. Mark I SAI Gamma Scanner	3
2. Sketch of Collimator Shielding	4
3. Gamma-Ray Detection Efficiency Curves For Floor Scans.	9
4. Floor Plan of TMI-2 Reactor Building 305' Elevation Showing Measurement Locations.	10
5. Floor Plan of TMI-2 Reactor Building 347' Elevation Showing Measurement Locations.	11
6. Portion of Gamma-Ray Pulse-Height Spectrum	13
7. Portion of Pulse-Height Spectrum Showing Gamma-Ray Peaks	14
A1. Schematic Drawing of Detector Model.	19
A2. Two Dimensional Sketch of Oblique Scan Geometry.	22
A3. Two Dimensional Sketch Showing Definition of Integration Variables.	24

PRE-AND-POST DECONTAMINATION GAMMA-RAY SCANS OF TMI-2
CONTAINMENT SURFACES, ELEVATIONS 305 AND 347 FOOT

1. SUMMARY

The SAI collimated gamma-ray detector scanned surfaces of the TMI-2 Containment Building floors and walls both before and after the decontamination experiments in mid March 1982. The surface contamination at five locations each on the 305-foot and 347-foot elevations were measured in the scans. The pre-decontamination measurements were made on December 16, 1981 and February 16, 1982, respectively, for the 305- and 347-foot elevations; the post-decontamination measurements were made on March 25 and March 26, 1982. Most of the measurements showed contamination levels for ^{137}Cs that were less than $1 \mu\text{Ci}/\text{cm}^2$. A few areas showed levels that were below the minimum detectable limits. In some cases, the level of activity after decontamination was above that measured before decontamination.

2. MEASUREMENT TECHNIQUES AND DETECTOR CALIBRATION

The SAI collimated gamma-ray spectrometer ("gamma-ray camera") was designed specifically for scanning reactor piping and components to determine the concentration of each radionuclide in these items. It is used with a method of analysis and calibration developed^{1,2} by SAI for use with sources of abnormal or extended geometry. This or similar collimators have been used³⁻¹⁴ in previous scans of reactor system components.

A photograph of the detector and collimator assembly is shown in Figure 1. Removable stepped plugs are inserted into the open end of the collimator. Used in the present measurements are a plug with a 1-cm diameter hole and a solid plug used for background measurements. Figure 2 shows a cross-sectional view of the collimator shielding. The assembly can be rotated to aim at any angle from 0° to 180° with respect to a perpendicular to the floor. The frame is mounted on eight-inch diameter wheels for easy movement. An 8% efficient (relative to 3"x3" NaI(Tl)) hyperpure germanium detector was used in the assembly. The nitrogen retention time of the detector dewar is about eight hours. The detector preamplifier is a portion of the detector assembly. Detector bias supply, amplifier, and system low-voltage power supply are mounted on the collimator cart. Multichannel analyzer (MCA) and input-output devices (printer and magnetic tape unit) are placed separately from the cart; as much as 500 feet of signal cable can connect the MCA with the amplifier.

Calibration of the detector-collimator system used the techniques discussed in References 1 and 2. A certified mixed-isotope point-source standard was used to measure both on-axis and off-axis detector response. Energies and intensities of the gamma-rays emitted by this standard are listed in Table 1. Measurements were made at several distances along the symmetry axis of the detector and at several distances off axis at a fixed distance along the detector. The values of these distances are given in Table 2.

Distances along the detector symmetry axis are measured from the cap of the detector cryostat. The distance of 12.76-cm is the distance to the outside of the collimator. The diameter of the hole in the collimator is 1-cm and measurements were made to angles off-axis that were equivalent to twice that subtended by the collimator hole. Data from the calibration measurements were fit to obtain the values for the parameters describing the detector response (as in the detector model of Reference 2). We used these values to

Figure 1. MARK I SAI GAMMA SCANNER

Figure 2. Sketch of Collimator Shielding

TABLE 1. GAMMA-RAY ENERGIES AND SOURCE INTENSITIES
FOR DETECTOR CALIBRATION STANDARD

<u>Gamma-Ray Energy (keV)</u>	<u>Intensity Gamma-Rays per Second</u>
88	1345
122	1034
166	1001
279	2453
392	2919
514	5146
662	7817
898	8597
1173	9547
1332	9559
1836	9165

TABLE 2. ON-AXIS AND OFF-AXIS DISTANCES AT WHICH
CALIBRATION MEASUREMENTS WERE MADE

Distance Along Detector Symmetry Axis (cm)	Distance Off Detector Symmetry Axis (cm)
12.76	0
12.76	0.1
12.76	0.2
12.76	0.3
12.76	0.4
12.76	0.6
12.76	0.7
12.76	0.8
12.76	1.0
17.26	0
22.76	0
30.96	0

calculate detection efficiencies for the geometries of the experiment. Figure 3 shows the calculated detection efficiencies for the configuration as a function of collimator angle and of gamma-ray energy.

3. MEASUREMENTS AND RESULTS

The measurements were of five areas of the TMI-2 Reactor Containment Building 305-foot and five areas of the 347-foot elevations. They included both wall and floor measurements. Figure 4 shows a floor plan of the 305-foot elevation and Figure 5 shows a similar plan of the 347-foot elevation. Figures 4 and 5 also show the locations of where gamma-ray measurements were made. Table 3 gives descriptions of these locations.

Pre-decontamination measurements on the 305-foot elevation were made in an entry December 16, 1981 and those on the 347-foot elevation were made February 16, 1982. Post decontamination measurements were made on March 25 and March 26, 1982, respectively for the 305-foot and 347-foot elevations. Entries into containment were through the personnel air lock on the 305-foot elevation. Access to the 347-foot level was by a hoist through the equipment hatch. The cart was rolled into position and the collimator aimed at the surface to be scanned. The collimator was aligned to an angle of 45° for the floor scans so as to eliminate any effects from the intense radiation on the 281-foot level that passes through the concrete floors. The multichannel analyzer (MCA) was located in a clean area in the service building. Amplified signals from the detector were transmitted to the MCA through a containment penetration cable and approximately two-hundred feet of RG 59/U coaxial cable.

Two spectra were collected at each location, one with the 1-cm diameter collimator hole and one with the solid plug for background determinations. Figures 6 and 7 show typical spectra taken with these two configurations. These spectra were taken during a previous entry. The peaks shown are from the nuclides ^{134}Cs and ^{137}Cs . In all of the scans of the TMI-2 containment, these were the only nuclides whose presence was observed. There was no evidence for the presence of either ^{60}Co or ^{144}Ce in any of the spectra. Lower estimates for the concentration of these nuclides are a factor of 10^{-5} below that for ^{137}Cs at the positions measured.

Table 4 shows the results of the pre- and post-decontamination scans for both the 305-foot and the 347-foot elevation. The table gives the net counting

rate for the 662-keV peak from ^{137}Cs . The net counting rate is determined by subtracting the integral of the counting rate in the peak from this gamma-ray in the spectrum taken with the solid plug from that taken with the 1-cm collimator. The results expressed in terms of $\mu\text{Ci}/\text{cm}^2$ are also shown in the table. The uncertainties in the values are the propagated statistical uncertainties.

Figure 3. Gamma-Ray Detection Efficiency Curves

Figure 5. Floor Plan of TMI-2 Reactor Building 347' Elevation Showing Measurement Locations

TABLE 3. LISTING OF AREAS OF TMI-2 CONTAINMENT, ELEVATIONS 305' 347' FOR WHICH MEASUREMENTS WERE MADE BY GAMMA-RAY SCANNING OF THE SURFACE CONTAMINATION BEFORE AND AFTER SPRAY DECONTAMINATION

Area Designation	Description of Area
13	Area of containment wall, approximately two feet above the floor. Northeast corner near "A" core-flood-tank.
H7	Floor area under core-flood-tank "A".
V9	Surface of "D-ring" wall near #2 stairwell.
34	Area of floor near "B" core-flood-tank and six feet out from edge of "D-ring".
H5	Floor area under core-flood-tank "B".
33	Floor area in northeast corner about 180° opposite the open stairwell.
H10	Floor area near the open hatch.
149	Floor area close to "D-ring" near the open stairwell.
H9	Floor area close to the liner wall near the open stairwell.
36	Wall surface of "D-ring" opposite the elevator.
36-A	Floor surface at location 36.

Figure 6. PORTION OF GAMMA-RAY PULSE-HEIGHT SPECTRUM

Figure 7. PORTION OF PULSE-HEIGHT SPECTRUM SHOWING GAMMA-RAY PEAKS

TABLE 4. NET ^{137}Cs COUNTING RATES AND SURFACE CONTAMINATION
LEVELS ON 305- AND 347-FOOT ELEVATIONS IN THE TMI REACTOR
CONTAINMENT BUILDING BEFORE AND AFTER SPRAYING

<u>305-Foot Elevation</u>				
<u>Area Designation</u>	Net ^{137}Cs Counting Rate (c/s)		^{137}Cs Surface Contamination ($\mu\text{Ci}/\text{cm}^2$)	
	12/16/81 Before <u>Spraying</u>	3/25/82 After <u>Spraying</u>	12/16/81 Before <u>Spraying</u>	3/25/82 After <u>Spraying</u>
13	<0.6	1.5 $\pm$ 0.4	<0.2	0.5 $\pm$ 0.2
H7	4.5 $\pm$ 0.5	1.7 $\pm$ 0.5	0.96 $\pm$ 0.10	0.4 $\pm$ 0.2
V9	1.7 $\pm$ 0.9	<1.6	0.5 $\pm$ 0.3	<0.6
34	4.1 $\pm$ 0.8	25 $\pm$ 1	0.9 $\pm$ 0.2	5.3 $\pm$ 0.4
H5	<1.5	Not Measured	<0.3	Not Measured
<u>347-Foot Elevation</u>				
<u>Area Designation</u>	Net ^{137}Cs Counting Rate (c/s)		^{137}Cs Surface Contamination ($\mu\text{Ci}/\text{cm}^2$)	
	2/16/82 Before <u>Spraying</u>	3/26/82 Before <u>Spraying</u>	2/16/82 Before <u>Spraying</u>	3/26/82 After <u>Spraying</u>
33	0.69 $\pm$ 0.33	5.1 $\pm$ 0.4	<0.14	1.1 $\pm$ 0.2
H10	2.40 $\pm$ 0.38	3.8 $\pm$ 0.5	0.5 $\pm$ 0.16	0.8 $\pm$ 0.2
149	4.69 $\pm$ 0.40	9.6 $\pm$ 0.3	0.97 $\pm$ 0.17	2.0 $\pm$ 0.1
H9	4.10 $\pm$ 0.40	Not Measured	0.85 $\pm$ 0.17	Not Measured
36	0.59 $\pm$ 0.34	<1.0	<0.20	<0.3
36-A	4.64 $\pm$ 0.37	Not Measured	0.96 $\pm$ 0.15	Not Measured

REFERENCES

1. J. E. Cline, A Technique of Gamma-Ray Detector Absolute Efficiency Calibration For Extended Sources, Computers in Activation Analysis and Gamma-Ray Spectroscopy, DOE Symposium Series 49, CONF-780421, 1979.
2. J. E. Cline and P. G. Voillequé, Germanium Spectrometer Calibration Procedures, Volume 2, ISPO-80, SAI-139-79-501-RV, Program For Technical Assistance to IAEA Safeguards, November 1979.
3. C. D. Thomas, Jr., J. E. Cline, P. Roy, Radiation Measurements in Steam Generator "B" at the Palisades Nuclear Station, March 1980.
4. J. E. Cline, P. G. Voillequé, C. D. Thomas, Jr., Gamma-Ray Measurements of the TMI-2 Containment Surfaces by Scans Through the Equipment Hatch, June 1979.
5. J. E. Cline, C. D. Thomas, Jr., P. G. Voillequé, E. Walker, T. Menzel, Gamma-Ray Measurements in Containment Penetration R-605 at TMI-2, August 1979.
6. J. E. Cline, C. D. Thomas, Jr., E. Walker, Gamma-Ray Measurements in Containment Penetration R-626 at TMI-2, September 1979.
7. C. D. Thomas, Jr., J. E. Cline, T. Fritz, J. Tate, Gamma-Ray Measurements Through the Inner Door of the Personnel Airlock at TMI-2, March 1980.
8. J. E. Cline, D. S. Cameron, D. A. Keefer, Gamma-Ray Measurements in the Reactor Building at the J. A. Fitzpatrick Power Plant, February 1981.
9. J. E. Cline, C. D. Thomas, Jr., J. A. Daniel, E. A. Schlomer, D. Keefer, M. Pavelek, Measurements of Activities in the Reactor Coolant Bleed Tanks at TMI-2, August 1981.
10. J. E. Cline, C. D. Thomas, Jr., D. S. Cameron, John R. Cooper, J. E. Tarpinian, Measurement of Surface Contamination Levels on Designated Floor Areas on Elevation 305', TMI-2 Reactor Building, SAI-139-81-01-RV, September 1981.
11. D. S. Cameron, E. D. Barefoot, C. D. Thomas, Jr., J. E. Cline, Measurements of Contamination on Containment Coolers C, D, and E and Surface Contamination on a Designated Floor Area on Elevation 305', TMI-2 Reactor Building, SAI-139-81-06-RV, November 1981.
12. J. E. Cline and D. S. Cameron, Gamma-Ray Scans of Selected Control-Rod Blades and Fuel Flow Channels in Oyster Creek Fuel Pool, SAI-139-81-09-RV, December 21, 1981.

13. E. D. Barefoot, D. S. Cameron, J. E. Cline, J. A. Daniel, D. G. Keefer, E. A. Schlomer, C. D. Thomas, Jr., Pre-Decontamination Gamma-Ray Surface Scans in TMI-2 Containment Building 305' Elevation, SAI-139-81-10-RV, December 21, 1981.
14. E. D. Barefoot, J. E. Cline, J. A. Daniel, D. G. Keefer, E. A. Schlomer, C. D. Thomas, Jr., Pre-Decontamination Gamma-Ray Surface Scans in TMI-2 Containment Building 347' Elevation, SAI-139-82-02-RV, March 1982.

APPENDIX A

MODEL OF DETECTOR CALIBRATION FOR EXTENDED SOURCES

A semi-empirical model can mathematically describe the response of a Ge detector. The model can then be used to calculate detection efficiencies for this detector. The principal difficulty is describing the detector response to sources located away from the symmetry axis of the normally cylindrical detector. The model describes the detector as a point located along the symmetry axis within the volume of the detector. The location of this point relates to the average depth of interaction of the gamma ray within the detector material (penetration depth) and therefore varies with gamma-ray energy. The detector response is a function of both source-detector distance along the detector axis and of the angle subtended by this axis and a direct path from the source to the detector. The function of angle takes into account the collimator used with the detector; values of the function parameters are empirically determined. Using the response function, the response of the detector can be described for a specific sample volume element. Gamma-ray detection efficiency of the entire sample is then obtained by integrating this response function over the sample volume. The integration includes gamma-ray self attenuation within the sample.

Figure A1 schematically represents the geometry of the calculations for a cylindrical or spherical sample. A two-dimensional slice through the sample is shown. The equation describing the efficiency, ϵ , for the detection of a gamma-ray of energy, E , emitted from the volume element, ΔV , inside the source, is:

$$\epsilon(E) = \frac{\epsilon_I(E) \times (H(D) \times e^{-(\mu_C(E)t + \mu_S(E)d)}}{4\pi[(P(E) + D + T + R - r \cos \theta)/\cos(G(\phi, E))]^2} \quad (1)$$

where

- $\epsilon(E)$ = a detector and an energy dependent normalization parameter called the intrinsic efficiency
- $P(E)$ = the effective penetration depth (location of 'point' detector) inside the detector cryostat
- ϕ = the angle subtended by a line between the source element and the detector symmetry axis

Figure A1. Schematic drawing of detector model. (A two-dimensional slice through the sample) Source element is located within the source at radius, r , and angle, θ . Gamma rays from that element travel to the detector (point $P(E)$) at an angle, ϕ , through a distance, d , of the source and t of the holder.

$G(\phi, E)$ = a function describing the response of the detector to sources located off-axis (for a pure $1/R^2$ response, $G(\phi, E) = \phi$); this function also describes the off-axis attenuation by the collimator
 D = the distance from the face of the cryostat to the nearest edge of the sample container
 $H(D)$ = a function that describes the fractional "area" of the detector surface illuminated by the source element located on the symmetry axis (restricted by collimation)
 $\mu_c(E)$ and
 $\mu_s(E)$ = the linear gamma-ray attenuation coefficients of the container and source material, respectively
 t and
 d = the linear distances traversed in reaching the detector 'point' by gamma-rays from the volume element through the container and source material, respectively
 T = the thickness of the container wall
 R = the radius of the sample (for cylinder or sphere)
 r and
 θ = the radius and angle coordinates of the volume element in a sample-based coordinate system.

Sample height (perpendicular to the plane of the figure) enters by quadrature in the calculation of ϕ , t , and d . An integral is taken over the volume of the source to obtain the detection efficiency for the entire source.

The functional form used to describe $G(\phi, E)$ is a power series in ϕ :

$$G(\phi, E) = G_0(E) + G_1(E) \phi + G_2(E) \phi^2.$$

The coefficients $G_0(E)$, $G_1(E)$, and $G_2(E)$, and the penetration factor $P(E)$ are second-order power series in the log of the energy, of the form:

$$Y(E) = Y_0 + Y_1 (\ln E) + Y_2 (\ln E)^2.$$

The form of the absorption coefficients, μ , is:

$$(\ln \mu) = A + B (\ln E) + C (\ln E)^2.$$

The function, $H(D)$ is given by:

$$H(D) = \left(\frac{h(D+p)}{R_D D} \right)^2, \quad h < \frac{DR_D}{D+p}$$

and

$$H(D) = 1, \quad h \geq \frac{DR_D}{D+p},$$

where

p = distance from face of the cryostat to face of the detector ingot

h = radius of collimator hole, and

R_D = radius of the detector.

DETECTOR EFFICIENCY CALCULATION FOR OBLIQUE INCIDENCE ON SURFACES OF UNIFORM SOURCE STRENGTH

Figure A2 shows the geometry of a horizontal surface being scanned obliquely by a collimated detector. The area scanned is an oblique cross-section of a cone, i.e., an ellipse on the surface. Referring to Figure A2, the major and minor radii of the ellipse are given by:

$$r_{\text{major}} = H_v \left[\tan \alpha \left(1 + \tan^2 \theta \right) \left(\frac{1}{1 - \tan^2 \theta \tan^2 \alpha} \right) \right] \quad (2)$$

and

$$r_{\text{minor}} = H_v \frac{\tan \alpha}{\cos \theta} \quad (3)$$

where

$$\tan u = \frac{2d}{t}$$

d = diameter of collimator, and

t = thickness of collimator.

Figure A2. Two Dimensional Sketch of Oblique Scan Geometry

Using the formalism of the calibration technique, the proper concentration of activity on the surface can be determined through an efficiency based on an integration of a point kernel over the entire surface being scanned. Since the detector response function falls very rapidly as the area falls outside the collimator aperture, it is necessary only to integrate over an area beyond which the detector response falls to a negligible amount. Let us arbitrarily (and conservatively) choose this to be a square area whose sides have a length of:

$$W = 2.0 r_{\text{major}} \quad (4)$$

Using Equations 1, 2 and 4 and Figures A2 and A3, the efficiency for the detection of gamma rays emitted from a surface element,

$$ds = dw \times dw_1$$

at X_0 ; w and w_1 can be given by:

$$\epsilon(E) = \frac{\epsilon_I(E) \times H(D) \, ds}{4\pi \left[\left(P(E) + X_0/\sin\theta - \left(\frac{W}{2} - w \right) \sin\theta \right) / \cos(G(\phi, E)) \right]^2} \quad (5)$$

where

$$\tan \phi = \frac{\left\{ (w/2 - w_1)^2 \cos^2 \theta + w_1^2 \right\}^{1/2}}{H_V / \cos \theta + (w/2 - w) \sin \theta}$$

$\epsilon(I)$ = intrinsic efficiency

$P(E)$ = penetration depth

ϕ = angle between the surface element and the detector symmetry axis extended

$G(\phi)$ = function describing "effective angle" to axis

X_0 = distance along surface from vertical projection of detector axis to intersection of symmetry axis with the surface:

$$X_0 = H_V \tan \theta$$

W = width of surface area being computed

Figure A3. TWO DIMENSIONAL SKETCH SHOWING DEFINITION OF INTEGRATION VARIABLES

$$W = 2.0 H_v \left[\frac{\tan \alpha (1 + \tan^2 \theta)}{1 - \tan^2 \theta \tan^2 \alpha} \right]$$

$H(D)$ = collimator factor or fraction of detector surface exposed

$$H(D) = \left(\frac{h(D+P)}{R_d D} \right)$$

where

h = radius of collimator

p = distance from end of collimator to end of germanium ingot

R_d = radius of germanium ingot

D = distance from end of cryostat to projection of surface element on detector axis

$$D = P(E) \times X_o / \sin \theta - \left(\frac{W}{2} - w \right) \sin \theta$$

Integrating the function over the area defined by w ,

$$\epsilon(E) = \frac{\epsilon_I(E)}{2\pi} \int_{-W/2}^{W/2} \int_0^{W/2} \frac{H(D) dw_1 dw}{[(P(E) + X_o / \sin \theta - (\frac{W}{2} - w) \sin \theta) / \cos(G(\phi, E))]^2} \quad (6)$$

The function is symmetric in w_1 , therefore

$$\epsilon(E) = \frac{\epsilon_I(E)}{4\pi} \int_{-W/2}^{W/2} \int_{-W/2}^{W/2} \frac{H(D) dw dw_1}{[(P(E) + X_o / \sin \theta - (\frac{W}{2} - w) \sin \theta) / \cos(G(\phi, E))]^2} \quad (7)$$

Substitute a summation for the integrals.

$$dw \Rightarrow \Delta w_1 = \frac{W}{J}, \quad w = \frac{(2j-1)}{2J} W$$

$$dw_1 \Rightarrow \Delta w_1 = \frac{W}{2K}, \quad w_1 = \frac{(2k-1)}{2K} \frac{W}{2}$$

$$\epsilon(E) = \frac{\epsilon_I(E)}{2\pi} \sum_{j=1}^J \sum_{k=1}^K \frac{H(D) \left(\frac{W^2}{2JK} \right)}{\left[(P(E) + x_0 / \sin \theta - \left(\frac{W}{2} - \frac{(2j-1)}{2J} W \right) \sin \theta) / \cos(G(\phi, E)) \right]^2} \quad (8)$$

$$\phi = \tan^{-1} \left(\frac{w \left\{ \left[\left(\frac{(2j-1)}{2J} - 1/2 \right) \cos \theta \right]^2 + \left(\frac{(2k-1)}{4K} \right)^2 \right\}^{1/2}}{H_v \tan \theta + W \left(\frac{2j-1}{2J} - 1/2 \right)} \right) \quad (9)$$

$$W = 2.0 H_v \left[\frac{\tan \alpha (1 + \tan^2 \theta)}{1 - \tan^2 \theta \tan^2 \alpha} \right] \quad (10)$$