OCT 10 1991

**SUPERCLEAN COAL-WATER SLURRY COMBUSTION
TESTING IN AN OIL-FIRED BOILER**

Semiannual Technical Progress Report
for the Period 02/15/1991 to 08/15/1991

DOE/PC/88697--T4

DE92 004583

By

**Bruce G. Miller, Co-Principal Investigator
Joel L. Morrison, Research Associate
Jiangyang Xie, Graduate Research Assistant
Peter M. Walsh, Faculty Associate
Harold H. Schobert, Co-Principal Investigator
Alan W. Scaroni, Project Manager**

October 1, 1991

Work Performed Under Cooperative Agreement No. DE-FC2289PC88697

For
U.S. Department of Energy
Pittsburgh Energy Technology Center
Pittsburgh, Pennsylvania

By
The Combustion Laboratory
The Pennsylvania State University
University Park, Pennsylvania

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by the United States Government. Neither the United States Government nor the United States Department of Energy, nor any of their employees, nor any of their contractors, subcontractors, or their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

TABLE OF CONTENTS

		<u>Page</u>
1.0	INTRODUCTION	1
2.0	PHASE I: DESIGN, PERMITTING, AND TEST PLANNING	2
3.0	PHASE II: CONSTRUCTION AND START UP.....	2
3.1	Task 1. Host Site Readiness/Boiler Retrofit	2
3.2	Task 2. SCCWS Preparation	4
3.2.1	Selection of the SCCWS Preparation Process	4
3.2.2	Atomization and Combustion Testing of Laboratory Prepared SCCWS	6
3.2.3	Full-Scale SCCWS Production Run	7
3.2.4	Combustion Test of KVS Prepared SCCWS	8
4.0	PHASE III: DEMONSTRATION AND EVALUATION	8
4.1	Task 1. Test Burn	8
4.1.1	Subtask 1b. Slagging/Fouling Propensity; Corrosion Characteristics	8
4.1.2	Subtask 1c. Erosion Characteristics	9
5.0	MISCELLANEOUS ACTIVITIES	13
6.0	NEXT QUARTER ACTIVITIES	13
7.0	REFERENCES	13
8.0	ACKNOWLEDGEMENTS.....	14

1.0 INTRODUCTION

The Pennsylvania State University is conducting a superclean coal-water slurry (SCCWS) program for the United States Department of Energy (DOE) and the Commonwealth of Pennsylvania with the objective of determining the capability of effectively firing SCCWS in an industrial boiler designed for oil. Penn State has entered into a cooperative agreement with DOE to determine if SCCWS (a fuel containing coal with less than 3.0% ash and 0.9% sulfur) can effectively be burned in an oil-designed industrial boiler without adverse impact on boiler rating, maintainability, reliability, and availability. The project will provide information on the design of new systems specifically configured to fire these clean coal-based fuels. The project consists of three phases: (1) design, permitting, and test planning, (2) construction and start up, and (3) demonstration and evaluation. The boiler testing will determine if the SCCWS combustion characteristics, heat release rate, fouling and slagging behavior, corrosion and erosion limits, and fuel transport, storage, and handling characteristics can be accommodated in an oil-designed boiler system. In addition, the proof-of-concept demonstration will generate data to determine how the properties of SCCWS and its parent coal affect boiler performance. Economic factors associated with retrofitting and operating boilers will be identified to assess the viability of future oil-to-coal retrofits.

The project consists of three phases as previously mentioned. Following is an outline of the project tasks that comprise the three phases:

Phase I: Design, Permitting, and Test Planning

- Task 1. Design
- Task 2. Permitting
- Task 3. Test Planning

Phase II: Construction and Start Up

- Task 1. Host Site Readiness/Boiler Retrofit
- Task 2. SCCWS Preparation
- Task 3. Performance Prediction
- Task 4. Shakedown Testing

Phase III: Demonstration and Evaluation

- Task 1. Test Burn
 - Subtask 1.a. SCCWS combustion performance
 - Subtask 1.b. Slagging/fouling propensity; corrosion characteristics
 - Subtask 1.c. Erosion characteristics
 - Subtask 1.d. Fuel transport, storage, and handling characteristics
- Task 2. Evaluate Retrofit Economics
- Task 3. Final Report

Penn State began a coal-water fuel (CWF) research and development program in 1984 with the ultimate goal of facilitating the replacement of petroleum-based fuel with a coal-based fuel in oil-fired (designed) boilers. The Pennsylvania legislature appropriated funds in 1984 for the construction of a demonstration CWF boiler with a capacity of approximately 15,000 lbs steam/h on the main campus of Penn State at University Park. The project goal was to conduct a demonstration of the use of CWF derived from Pennsylvania coal in an environmentally acceptable manner, while evaluating the effects on boiler performance of long-term firing with CWF. From a commercialization viewpoint, the motivation for the project was to demonstrate the technical feasibility of retrofitting existing oil-fired units to burn CWF, particularly in the commercial and light-industrial sectors. Funding each year since 1984 has allowed for fuel procurement and the installation of a nominally rated 1,000 lb steam/h (2 million Btu/h) Cleaver-Brooks A-frame watertube boiler [1] to investigate: the effect of boiler operating parameters on combustion performance [2]; automation of the firing of slurry fuels, particularly with respect to start up and shutdown procedures but also in optimizing boiler performance [3]; testing candidate CWFs; and providing the necessary research support and training prior to start up of the demonstration unit. The SCCWS demonstration will be conducted on the demonstration boiler.

Accomplishments this period are presented in Sections 2.0, 3.0, 4.0, and 5.0 for Phases I, II, and III, and miscellaneous activities, respectively. Section 6.0 outlines the activities planned for the next semiannual period. References are contained in Section 7.0. The status of the project schedule is given in Figures 1 through 4 with a description of the milestones contained in Table 1.

2.0 PHASE I: DESIGN, PERMITTING, AND TEST PLANNING

No work was conducted this quarter on Phase I. Phase I has been completed with the exception of identifying operating procedures (a portion of Task 3). These will be formulated at a later date.

3.0 PHASE II: CONSTRUCTION AND START UP

3.1 Task 1. Host Site Readiness/Boiler Retrofit

The building addition (boiler room) to the East Campus Steam Plant was completed and the majority of the equipment was delivered and installed during the previous semiannual reporting period [5]. Details of the boiler and auxiliary equipment have been given elsewhere [5,6]. Items that were installed this reporting period include: induced draft and forced draft fans; auxiliary duct-mounted burner; CWF piping from the CWF feed pump to the CWF heater, CWF heater bypass, and the boiler; electrical wiring of the control panel, instrumentation, and boiler control system; ducting from the forced draft fan to the air preheater, between the air preheater and the boiler, and from the boiler to the bagfilter and induced draft fan; and 16,000 gallon (~80 hour) capacity CWF storage tank and associated piping.

The piping system was constructed to facilitate one-man operation to unload the CWF delivery tanker (from Kennedy Van Saun) into either the storage tank or 2,000 gallon capacity day tank, transfer CWF from the storage tank to the day tank, recycle the storage tank or delivery tanker, flush all lines with water, and flush the delivery tanker with water.

Tampella Power Corporation conducted a boiler boilout in June to clean the boiler prior to setting up the burner and cure the refractory. The burner set-up on high fire (full load) firing natural gas was delayed due to equipment problems and installation. The induced draft fan was oversized for the system and new sheaves were machined to reduce the fan speed (and hence capacity). There was a delay in completing the control system for the auxiliary duct-mounted burner, a missing control valve has been ordered and will be installed in September; the baghouse is to be completed the end of August; and the CWF pump controller was damaged during the boilout (water was sprayed on the controller) and required repair (and is to be installed during the last week of August). The high-fire test on natural gas is planned for the last week of August.

The flue gas analyzers (CO, CO₂, O₂, SO₂, and NO_x), data acquisition system, and personal computer were received and installed in the laboratory trailer. Equipment installed for the emissions monitoring system and data acquisition include:

- Model 755 Oxygen analyzer
- Model 870 NDIR Carbon Monoxide analyzer
- Model 870 NDIR Carbon Dioxide analyzer
- Model 880 NDIR Sulfur Dioxide analyzer
- Model 10A/R chemiluminescent NO-NO_x analyzer
- Model HF200 Heatless Air Drier
- Model PD-1024 Sample Drier
- Model 55SX IBM computer
- IBM ExecuJet printer
- 16-channel master measurement module with A/D converter
- 16-channel thermocouple input module
- 16-channel analog input multiplexer
- VIEWDAC software

The data acquisition system will log the flue gas composition and the following temperatures, pressures, and flow rates:

Pressures

- CWF at atomizing nozzle (gun)
- CWF at pump
- Atomizing air
- High-pressure steam
- Boiler draft
- Natural gas
- Flue gas pressure drop across air preheater
- Flue gas pressure drop across bag filter

Flow Rates

- Natural gas

- CWF
- Combustion air
- Atomizing air/steam
- Steam

Temperatures

- Ambient air
- High-pressure steam
- Air preheater inlet (combustion air)
- Air preheater outlet (combustion air)
- Air preheater inlet (flue gas)
- Air preheater outlet (flue gas)
- steam calorimeter
- CWF storage tank
- CWF heater inlet
- CWF heater outlet
- Feed water
- Combustion air (windbox)
- Baghouse inlet
- Baghouse outlet

Other

- CWF storage tank level
- CWF day tank level
- Boiler drum water level

Conduit has been installed and wires pulled from the sensors to the control panel and to the data acquisition system in the trailer. Final connections will be made after the facility is officially turned over to Penn State.

3.2 Task 2. SCCWS Preparation

As previously reported, Penn State's intention was to purchase the SCCWS from a commercial vendor. However, after discussions with DOE following minimal interest by vendors, a decision was made to work directly with a coal company/coal preparation facility rather than a commercial vendor to make the SCCWS.

3.2.1 Selection of the SCCWS Preparation Process

In the previous semiannual report, the coal selection process and preliminary SCCWS formulation were discussed [5]. This section will review the coal selection and detail the procedure used in the SCCWS formulation.

The overall philosophy used in the selection process was to identify a coal that would require minimal cleaning by delineating sources with inherently low sulfur and ash contents. A total of six potential coal sources were identified using the 1989 Keystone Directory [7] which summarizes individual Pennsylvania mining companies (e.g. annual tonnages produced, coal quality, wash plants). Three of the sources were examined further to evaluate which of the sources could be washed to meet the aforementioned coal specifications. From these three sources, the Brookville Coal from Lawrence County, Pennsylvania was selected based on the washability

performance. Perry Brothers Coal Company of Sharon, Pennsylvania will supply the Brookville coal for this project from their Richardson mine located in Lawrence County, Pennsylvania. Reddinger Coal Cleaning Company, Distant, Pennsylvania will use heavy media cyclones to produce the superclean coal feedstock. Figure 5 presents the location of this coal source which is superimposed on a generalized bituminous coal volatile matter map for Pennsylvania. The map also shows the location of Kennedy Van Saun (KVS) where the clean coal will be slurried to produce the SCCWS.

The SCCWS specifications for the 1,000-hour demonstration are as follows: 1) greater than 50 wt.% solids, 2) less than 1,000 cp @ 50 sec⁻¹ and 25° C, and 3) a particle size distribution of 99.5% passing 200 µm. Preparing SCCWS can be divided into the following components: 1) batch-scale testing to determine the optimum SCCWS formulation, 2) small-scale production run to characterize the proposed SCCWS formulation with respect to atomization and combustion performance, and 3) full-scale production run. The batch-scale testing was completed in March 1991.

Batch-Scale Testing

Batch-scale testing was conducted to generate small quantities of slurry for characterization with respect to solids loading, viscosity, and particle size distribution. The methodology used to develop an optimized SCCWS formulation is an ongoing three part process. This three part process entails determining the amount of dispersant agent needed to minimize viscosity, maximizing solids loading, and determining the stabilizer requirements.

Determining Dispersant Dosages

Determining the optimum amount of a dispersing agent was achieved by varying dispersant concentration (e.g. 0.1 to 1.25 wt.% solids on a dry coal basis) while maintaining a constant solids loading and a similar particle size distribution to determine the concentration of dispersant which minimized viscosity. The resulting slurry was characterized with respect to viscosity, particle size distribution, and solids loading.

The dispersing agent used was an ammonium based sulfonated naphthalene condensate (A-23M, 41% solids). Batch tests were conducted using a ten-inch diameter ball mill, 60 wt.% solids loading, and 80 to 90 % of the coal smaller than 71.4 µm with a D(v, 0.5) between 25 and 20 µm. (D (v, 0.5) is the volume mean diameter) Figure 6 summarizes the measured viscosities as a function of dispersant concentration and shows that viscosity is minimized when using approximately 1 wt.% dispersant agent.

Maximizing Solids Loading

After the optimum dispersant concentration was determined, solids loading was varied to determine changes in viscosity as a function of solids loading. Grinding times were adjusted to produce similar particle size distributions among the various slurry samples. As solids loading

was increased, the viscosity was monitored to determine the loading where viscosity increased significantly. Results are presented in Figure 7 and do not show any abrupt changes in viscosity as a function of solids loading; however, a knee in the curve is observed in the 57-59 wt. % solids loading range. A solids loading of slightly less than 59%, 58.5% to be exact, was selected as the optimum solids loading. This value was selected in order to reduce the possibility of producing a SCCWS with unacceptable viscosity should the solids loading increase slightly during full-scale production.

Determining Stabilizer Dosage

After determining the dispersant concentration and solids loading, stability tests were conducted using Flocon 4800C (xanthan gum) as the stabilizer. Stability, here defined as settling during storage, was determined using a penetrometer. A stable SCCWS is one where $\geq 80\%$ penetration is achieved after 21 days of quiescent storage. The stability results are shown in Figure 9. Figure 10 summarizes the effect of stabilizer concentration on apparent viscosity. A stabilizer concentration of 400 ppm active solids (dry coal basis) was selected as an optimum stabilizer dosage for the production run.

Small-Scale Production Run

A small-scale production run using a 12" x 24" wet overflow ball mill was conducted to verify batch-scale results and generate SCCWS to perform atomization and combustion tests in Penn States atomization test facility (ATF) and 1,000 lb steam/h watertube research boiler, respectively. Details of the ATF and boiler are given elsewhere [2, 4]. Solids loading was constantly monitored using a CEM AVC-80 microwave solids and moisture analyzer.

3.2.2 Atomization and Combustion Testing of Laboratory Prepared SCCWS

Atomization tests were performed to ensure that the SCCWS will adequately atomize. The atomization tests were conducted using the internal-mix atomizer which is routinely used on Penn State's research boiler (See reference 3 for details). A droplet size of $\leq 80 \mu\text{m}$ has been chosen as the atomization criterion. The atomization characteristics of the newly formulated SCCWS (PSU-Brookville Seam) are shown in Figure 10. The SCCWS exhibited good atomization. Figure 10 also contains the atomization results of several SCCWSs obtained from commercial vendors. The atomization tests were conducted using the internal-mix atomizer which is routinely used on Penn State's research boiler (See reference 4 for details). The PSU-Brookville Seam SCCWS compares favorably with those previously tested at Penn State.

A combustion test was conducted in the research boiler to evaluate the combustion performance of the newly formulated SCCWS. The SCCWS was fired at 246 lb/h (2,048,000 Btu/h) with an atomizing air/fuel mass flow (A/F) ratio of 0.23 and ~4% excess oxygen. The

combustion air was preheated to ~310°F. The PSU-Brookville Seam SCCWS exhibited good combustion characteristics with ~97% carbon burnout in the fly ash.

3.2.3 Full-Scale SCCWS Production Run

Over the last reporting period, approximately 100 tons of Brookville seam coal has been cleaned, transported to KVS, and approximately 4,000 gallons of SCCWS prepared. The coal was sized at Perry Brothers to -1.25" x 0.25" and then transported to the Reddinger coal cleaning facility. The Brookville seam coal was cleaned in two 24" heavy media cyclones operating at a specific gravity of 1.30. Media density was monitored by nuclear density gauges. This cleaning run produced a clean coal product with an ash and total sulfur level of 3.42% (db) and 0.71 % (db), respectively, with a yield of approximately 65%. The clean coal feedstock was then transported to KVS and 4,000 gallons of SCCWS prepared. The schematic of the KVS coal-water slurry preparation facility can be found elsewhere [5].

Based upon the bench-scale SCCWS results, the following SCCWS formulation was used in the first KVS production run: 1) solids loading 58.5 wt. %, 2) dispersant (A-23M) concentration of 1.00 wt. % active solids on a dry coal basis, and 3) stabilizer (Flocon 4800C) concentration of 0.04 wt. % active solids on a dry coal basis. A particle size distribution with a D (v, 0.5) of 23 μm with approximately 85% less than 74 μm (as determined by a Malvern particle and droplet analyzer) was targeted during the production run. Tables 2-4 summarize the solids loading, particle size distribution, viscosity of the SCCWS, and the operating conditions such as feed rates of the coal and additives during the first SCCWS production run. Ball mill coal feed rates were adjusted during the first day of the production run (Table 2) to ascertain the appropriate feed rate to produce the desired particle size distribution. Upon determining the coal feed rate, the 4,000 gallons of SCCWS was prepared and transported to the SCCWS demonstration facility at Penn State in a 5,600 gallon stainless steel tank truck. The SCCWS was then pumped into a 16,000 gallon storage tank. The SCCWS is currently being recirculated weekly to minimize settling.

The SCCWS was analyzed after it was received at Penn State and the ash and sulfur values were 4.18 and 0.85% (dry basis), respectively. These values are higher than those measured in the washed parent coal, which was sampled from the clean coal pile at Reddinger Coal, before shipping to KVS. Possible explanations for this increase are:

- 1) Unrepresentative sample (~400 lbs) collected at Reddinger Coal Company,
- 2) Contamination of the washed coal product during truck loading at Reddinger Coal Company, or
- 3) Contamination of the SCCWS at KVS by using a Perry Brothers washed coal (6.25% ash, d.b.) in establishing ball mill feed rates and/or due to mill start-up (rust). A washed coal from Perry Brothers was used as start-up coal at KVS because there was

not sufficient washed coal product from Reddinger Coal Company to set up the mill and conduct a SCCWS production run.

Regardless of the source, this was an unexpected result. In an attempt to prevent this from reoccurring, the following steps are being taken for future SCCWS production:

1) Request Perry Brothers Coal Company to provide a -1 x 0.25" parent coal. They have recently modified their semiportable coal sizing facility to produce this size fraction. The coal shipped to Reddinger Coal Company was approximately -1 x 0.5" because they did not have a 0.25" screen in their sizing facility. A cleaner washed product should be produced provided the overall coal quality does not change.

2) Reiterate the importance of keeping the coal stockpile isolated from other adjacent coal stockpiles at the Reddinger coal-cleaning facility.

3) Ball mill feed rates have been established, therefore, nonspecification coal will not be fed into the system.

4) Request that KVS discard the SCCWS from the first two hours of each start-up production run. If this was a contributing factor in the contamination, it will be less of a problem as the 24 hour production runs begin (less start-up time involved).

3.2.4 Combustion Test of KVS Produced SCCWS

A combustion test was conducted in the research boiler to evaluate the combustion performance of the SCCWS produced by KVS. This was done to ensure that the characteristics of the SCCWS were similar to the fuel produced during the laboratory-scale formulation and combustion testing. Table 5 contains the proximate and ultimate analysis, particle size distribution, and viscosity of the SCCWS. The SCCWS was fired at 200 lb/h (1,665,000 Btu/h) varying the A/F ratio from 0.25 to 0.36 and ~5% excess oxygen. The combustion air was preheated to 356°F. A very stable flame was produced and the carbon burnout in the fly ash was ~94% for both A/F ratios tested; the SCCWS performed very well.

4.0 Phase III: DEMONSTRATION AND EVALUATION

4.1 Task 1. Test Burn

4.1.1 Subtask 1b. Slagging/Fouling Propensity; Corrosion Characteristics

Work was done this reporting period developing the matrix of corrosion and deposition experiments. Corrosion and deposition tests will be conducted on three levels -- bench-scale, laboratory-scale, and demonstration boiler tests. Five alloys have been identified for which the corrosion/deposition characteristics will be measured. These are grades 304, 316, 321, 347 and 800H steels. The compositions of these alloys are summarized in Table 6. Types 304 and 316 are seamless, cold drawn, and annealed tubes of 2 inch outside diameter. These will be used as sample coupons attached to a deposition/corrosion probe which will undergo a 1000-hour test in

the demonstration boiler. All five alloys were also ordered in the form of bar stock rounds of 1 inch diameter, which will be used to produce samples for the bench-scale and laboratory tests. In the bench-scale tests, samples of the five alloys will be immersed in fly ash gathered from previous firings of the test fuel. All samples have been polished and photo-micrographs are being taken in order to identify the microstructure of the various alloys. The alloy samples will be then heated to approximately 1100° C in order to evaluate the effects of extreme "forcing" conditions on the alloy samples. The results of this work will provide an evaluation of the "worst case" corrosion behavior of the alloys exposed to ash. The laboratory tests involve heating of the samples, coated with ash, in the presence of simulated flue-gas atmosphere for a matrix of various times and temperatures. A specialty gas mixture has been ordered, to have a composition as close as possible to that predicted for SCCWS combustion in the demonstration boiler. Corrosion of samples from all the tests will be evaluated with the help of scanning electron microscopy and quantitative metallography in an effort to quantify corrosion in terms of metal penetration/wastage, using pit depth measurements. Dr. Paul Howell, Professor of Metals Science and Engineering, has agreed to provide assistance and advice in interpretation of metallography data.

In addition to the alloys described above, alloy steels of types 304 and 316 seamless tubes were alonised (alonising is a surface treatment involving the vacuum diffusion of aluminium onto the alloy surface to a depth of 40 micrometers). Specimens of these alonised steels will also be used as samples for the corrosion probe in the demonstration boiler and in the laboratory-scale tests, and will allow making a qualitative evaluation of the difference in corrosion/deposition characteristics for the alonised and un-alonised forms of alloys. Further, the adhesive strength of the deposit and/or film on the steel and the nature of the surface exposed after the deposit has been removed, will be examined in order to determine the kind of surface re-exposed in a boiler when the deposit is removed after a soot-blowing operation.

4.1.2 Subtask 1c. Erosion Characteristics

A series of tests were conducted for the measurement of erosion and degradation of carbon steel in the research boiler. The technique used in the tests has been described in a previous report [5]. In this report, the major effort is concentrated on the analysis of test results.

Tests

All the tests were conducted under stable operating conditions during CWF combustion. A micronized CWF prepared by OXCE Fuel Company was burned in the research boiler during these tests. The as-received compositional analysis for the fuel is given in Table 7. The higher heating value of the fuel was 8,935 Btu/lb. The particle size distribution is such that the sizes 2.9, 9.4, and 23.9 μm correspond to the cumulative volumes 10, 50, and 90%, respectively, of particles less than the indicated size. Both gas and solid composition in the flue gas are listed in Table 8.

The data with an approximate sign ($\sim$) were based on calculations from the element balances, but the others were directly measured.

In the convective section of the research boiler, where the ash erosion probe was inserted, the flue gas temperature was 693 K, and the particle concentration was 3.426 g/m^3 (actual) as found by weighing the ash collected in the hoppers of the convective section and baghouse, or 3.822 g/m^3 , from a calculation based on the ash balance.

Ash samples were observed under a Scanning Electron Microscope (SEM). As shown in Figure 11, different kinds of ash particles were collected in the deposit on the probe surface (Figure 11-a) and from the baghouse after the convective section (Figure 11-b). The former have sizes similar to the fuel particles, but the latter, consisting of agglomerates of many particles, have sizes about 20 times larger.

The latest version of the ash erosion probe is shown in Figure 12. It has a cut out which is mounted with a small sample of tube (38 mm x 20 mm). The test material is ASTM 192 carbon steel. All samples were polished to a roughness less than $0.5 \mu\text{m}$, and both ends were protected by graphite tape in order to provide a reference surface for the erosion profile measurement. Each sample was tested for 2 hours under the small jet of gas which entrains the ambient flue gas and particles. The jet nozzle was 1.63 mm inside diameter, and it was located 13.53 mm from the sample surface. The parameters which were varied during the tests included metal temperature (450-650 K), jet velocity (100-300 m/s), jet gas oxygen content (0-100 vol% O_2), and erosive particle type (CWF ash and sand). After each test, the profile of the metal sample was measured using a profilometer. An SEM equipped with energy-dispersive X-ray analysis (EDXRA) was used for the microscopic observations and composition analysis of the sample surface. The test results are discussed in the following subsections.

Effect of Metal Temperature

Figure 13 shows the profiles of the tube samples tested at different metal temperatures (650, 550, and 450 K) but using the same jet gas (21 vol% O_2), and jet velocity (200 m/s). The zero point on the horizontal coordinate is the point on the sample just under the jet axis; and the zero point on the vertical coordinate is the original surface of the polished sample. After a two hour test, the height of the surface on all samples has increased as the result of deposition or oxidation. With a decrease in metal temperature, the surface under the jet center changes dramatically from convex, as shown in Figures 13-a and 13-b, to concave as in Figure 13-c. This change corresponds to a transition from deposition to erosion. The maximum erosion loss was $2 \mu\text{m}$, as shown in Figure 13-c.

Microscopic observations and composition analyses of sample surfaces are given in Figures 14 to 16. With a decrease in the temperature, the particles depositing at the center become smaller, and the location of the deposit is moved from the center to a surrounding ring. The

composition in the center shows a decrease in the sodium, silica, aluminum, and calcium content of the deposit as temperature decreased, until the bare corroded surface containing only oxygen, sulfur, and iron was observed in Figure 16-b.

Spalling of the oxide layer occurred on the sample tested at 650 K. Figure 13-a shows the discontinuity in the profile at two symmetrical points located at about 12 mm from the center, while the vertical coordinate indicates a thickness of 6 μm . The detailed analysis of this spalling oxide layer is shown in Figure 17. The spot, S1 labeled in Figure 17-a, was brown in color. The compositional analyses in Figures 17-b and 17-c show that some micrometer-size ash particles were embedded in the metal surface. The constitution of the oxide substrate in Figure 17-d reveals sulfur penetration through the surface oxide. It is uncertain whether the thermal stress or the sulfidation was the cause of the spallation. Generally, sulfur is suspected to affect the adherence of oxide to the metal surface and the chemical stability of the oxide itself, thus sulfidation may accelerate the wastage of metal.

In any case, metal temperature greatly influences the mechanical properties of the metal itself, the physical interaction between the metal surface and solid particles, and/or the chemical reaction between metal and sulfur-containing flue gas.

Effect of Jet Velocity

Figure 18 shows the effect of different jet velocities (300, 200, and 100 m/s). At 300 m/s jet velocity (Figure 18-a), a small "w" shaped erosion profile was formed on the surface under the center of the jet. This shape is the result of the competition between the concentration of particles diffusing toward the jet center and the velocities of the particles which are accelerated by jet entrainment. With decrease in jet velocity, the center region becomes convex due to deposition, as shown in Figure 18-b, and finally a large "w" shaped deposit is formed, as shown in Figure 18-c, as a result of the velocity distribution in the jet.

Microscopic observations on both the eroded surface at 300 m/s jet velocity and the deposit on the surface at 100 m/s jet velocity are shown in Figures 19 and 20, respectively. Figure 19-a shows the eroded center area filled with particle collision craters. According to the platelet mechanism [8], erosion occurs by deformation first generating craters, followed by the fracture of the crater lips. However in Figure 19-b, a quite different structure of hole appears on the thick oxide, about 10 mm away from the center, which indicates a different mechanism causing oxide wastage. Figure 20-a is the deposit surface where there is some flaking-off of deposit at the intermediate ring about 4 mm away from the center. Some more detail is shown in Figure 20-b. It seems that when the deposit is removed by impinging particles or by the gas jet, the corroded and cracking metal surface beneath the deposit may also be removed, then bare metal is exposed to the corrosive flue gas, and corrosion and erosion will continue. Corrosion-erosion interaction at elevated temperature is a very special mechanism. It may dominate the erosion process where the

gas or particle velocity is low, and therefore be less erosive, so the effect of corrosion becomes important. For the measurement of erosion, a long-term test at low jet velocity is desirable.

Effect of Jet Gas Composition

Different jet gases (nitrogen, air, and oxygen) were used to determine the effect of metal oxidation on erosion. The sample temperature was 550 K, and the jet velocity was 300 m/s. At this high velocity, ash particles could form little deposit on the metal surface, so the expansion of sample surface is caused entirely by metal oxidation. As shown in Figure 21, with increasing oxygen content of the jet gas, the expansion of the sample surface right under the center of the jet has apparently increased; but in contrast, the "w" shape of the eroded surface has shrunk. This indicates that the metal oxide has a higher resistance to erosion, and that the oxide formed in the highly oxidizing atmosphere of pure oxygen has a much larger erosion resistance than bare steel. However, the rapid expansion of oxide implies poor resistance to further oxidation and the possibility of surface spallation.

Figure 22 shows the microscopic structures of eroded metal surfaces under nitrogen and oxygen jets. In the nonoxidizing nitrogen jet, the eroded surface shown in Figure 22-a has many craters that seem to have been formed by colliding particles. Although these craters are much more shallow than those formed in the air jet, as shown in Figure 19-a, they could still be connected with the platelet deformation mechanism. In the pure oxygen jet, the eroded surface, in Figure 22-b, seems more easily explained by the delamination theory [9] which emphasizes crack propagation and nucleation dominating the removal of surface material. The above results show that metal oxidation changes the mechanical properties of the surface layer and alters the erosion mechanism.

Effect of Erosive Particle Constitution

This test was intended to measure the effect of particle erosivity. It was carried out when the research boiler was configured to burn the particle-laden offgas from a circulating fluidized-bed gasifier firing CWF. Fine sand particles were entrained from the gasifier into the flue gas of the research boiler. The test result is compared with the erosion by pure CWF ash particles, as shown in Figure 23. The much enlarged "w" shape in Figure 23-b indicates a great increase in erosion by the sand particles in the flue gas. Figure 24 shows the ash mixture containing angular sand particles and the corresponding eroded surface. The gouges on the metal surface were probably caused by the plowing action of particles, where parts of the surface material were removed by cutting [10]. In fact, this mechanism is the most efficient way to remove ductile metal when the impinging particles have quite high hardness relative to the target material. However, in the erosion caused by soft, agglomerated carbon and ash particles, the different appearance of the eroded surface, shown in Figure 19-a, seems to indicate that the cutting mechanism was not important.

Summary

The major results are summarized in Table 9. With decrease in metal temperature and increase in jet velocity, the process occurring on the surface changed from deposition to erosion. The erosion rate was highly affected by the jet gas composition and other conditions influencing oxidation. The oxidized metal surface had higher resistance to erosion than the bare metal surface.

The erosion mechanism is not clear. It may change from one mechanism to another with changes in metal temperature, jet velocity, jet gas composition, or erosive particle constitution. The final conclusion on the mechanism of erosion by CWF ash needs to be determined from further tests.

5.0 MISCELLANEOUS ACTIVITIES

The 7th Annual Coal Preparation, Utilization, and Environmental Control Contractors Conference hosted by DOE PETC was attended July 15-18, 1991. A paper was prepared for presentation entitled "Superclean Coal-Water Slurry Combustion Testing in an Oil-Fired Boiler," by Bruce G. Miller, Joel L. Morrison, and Alan W. Scaroni.

6.0 NEXT SEMIANNUAL PERIOD ACTIVITIES

The SCCWS formulation will be completed. Boiler items that need to be completed include the repair of the CWF pump controller and installation of the auxiliary duct mounted burner control system.

The boiler burner will be set-up on high fire during the last week of August. Data firing natural gas will be collected the last week of August and the first week of September. Shakedown on SCCWS will follow with the 1,000-hour demonstration beginning in mid September.

Two pieces of work will be emphasized regarding erosion. Erosion tests will be conducted on the demonstration boiler, continuing the work on the effects of the parameters discussed in Section 4.2.2, long-term operation, and work with samples of chromium steel. In addition, the calculations of the jet flow field and particle diffusion describing the particle concentration and velocity, leading to a fit to the erosion profile, will be performed.

7.0 REFERENCES

- [1] Kinneman, W.P., R.T. Wincek, B.G. Miller, A.W. Scaroni, and R.G. Jenkins, "Conversion of a 1000 lb/h Steam Boiler to Fire Coal Water Slurry Fuel," Thirteenth Int. Conf. on Coal and Slurry Tech., Denver, Colorado, p.725 (April 12-15, 1988).
- [2] Miller, B.G., R.T. Wincek, A.W. Scaroni, W.P. Kinneman, and R.G. Jenkins, "Combustion of CWSF in a 1000 lb Steam/h Watertube Boiler," Thirteenth Int. Conf. on Coal and Slurry Tech., Denver, Colorado, p. 119 (April 12-15, 1988).
- [3] Wincek, R.T., W.P. Kinneman, B.G. Miller, A.W. Scaroni, D. Shefet, and F. Kal, "Combustion Control System for a Coal-Water Slurry Fuel-Fired Boiler," AIChE Spring National Meeting, Houston, Texas (April 2-6, 1989).

- [4] Miller, B.G., P.M. Walsh, J.T. Elston, and A.W. Scaroni, "Superclean Coal-Water Slurry Combustion Testing in an Oil-Fired Boiler," Quarterly Technical Progress Report for the Period 11/15/1990 to 02/15/1990, Pittsburgh Energy Technology Center, Pittsburgh, Pennsylvania, April 6, 1990, DE-FC2289PC88697.
- [5] Miller, B.G., J.L. Morrison, J.T. Elston, P.M. Walsh, H.H. Schobert, and A.W. Scaroni, "Superclean Coal-Water Slurry Combustion Testing in an Oil-Fired Boiler," Semiannual Technical Progress Report for the Period 08/15/1990 to 02/15/1991, Pittsburgh Energy Technology Center, Pittsburgh, Pennsylvania, May 15, 1991, DE-FC2289PC88697.
- [6] Miller, B.G., and Alan W. Scaroni, "Superclean Coal-Water Slurry Combustion Testing in an Oil-Fired Boiler," 6th Annual Coal Preparation, Utilization, and Environmental Control Contractors Conference, Pittsburgh, Pennsylvania, August 6-9, 1990.
- [7] Keystone Directory, Maclean Hunter Publishing Company, p. 1284 (1989).
- [8] Levy, A.V., "The Erosion of Metal Alloys and Their Scales," Conference: Corrosion/Erosion-Wear of Materials in Emergent Fossil Energy Systems, Ed. A.V. Levy, Berkely, California, NACE, 1982, pp.298-376.
- [9] Suh, N.P., "The Delamination Theory of Wear," *Wear*, 25, 1973, pp. 11-124.
- [10] Finnie, I., "Erosion of Surfaces by Solid Particles," *Wear*, 1960, pp. 87-103.

8.0 ACKNOWLEDGMENTS

The authors wish to acknowledge the following personnel for their contributions to the project during this reporting period:

- David Clark - Undergraduate Assistant
- John T. Elston - Research Assistant
- Scott Britton - Research Technologist
- William P. Kinneman - Research Assistant
- Carl Martin - Laboratory Mechanic
- Sarma V. Pisupati - Research Associate
- Roger Poe - Research Assistant
- Suneeta Shamanna - Graduate Research Assistant
- Ronald T. Wincek - Research Assistant

TABLE 1
MILESTONE DESCRIPTION

<u>Phase I</u>	<u>Description</u>	<u>Planned Completion Date</u>	<u>Planned Completion Date</u>
Task 1, No. 1	Identify equipment and diagnostic instrumentation	09/15/89	09/15/89
Task 2, No. 1	Review present permit	09/15/89	09/15/89
Task 3, No. 1	Develop SCCWS specifications, identify operating procedures, prepare detailed test plan	10/15/89	
<u>Phase II</u>			
Task 1, No. 1	Building/boiler construction and installation let for bids	10/18/89	10/18/89
Task 1, No. 2	Building/boiler construction and installation awarded	12/31/89	03/23/90
Task 1, No. 3	Prepare site, install boiler and auxiliary equipment	04/01/91	09/30/90
Task 2, No. 1	Identify coal for SCCWS preparation	09/30/90	
Task 2, No. 2	Prepare SCCWS for demonstration	04/01/91	
Task 3, No. 1	Predict boiler performance	06/15/91	
Task 4, No. 1	Shakedown boiler and auxiliary equipment	04/31/91	
Task 4, No. 2	Generate baseline data on gas	05/31/91	
<u>Phase III</u>			
Task 1, No. 1	Perform demonstration	03/01/92	
Subtask 1a, No. 1	300-hour demonstration milestone	07/31/91	
Subtask 1a, No. 2	600-hour demonstration milestone	09/30/91	
Subtask 1a, No. 3	1000-hour demonstration milestone	11/30/91	
Subtask 1a, No. 4	Redefine SCCWS specifications	01/15/92	
Subtask 1b, No. 1	Develop deposition and corrosion test plan	10/15/89	10/15/89
Subtask 1b, No. 2	Design suction pyrometer	06/01/90	08/01/90
Subtask 1b, No. 3	Construct suction pyrometer	10/01/90	10/01/90
Subtask 1b, No. 4	Deposition characterization equipment design and specification	01/01/91	02/15/91
Subtask 1b, No. 5	Acquisition of baseline data for spectroscopic analysis of deposits; acquisition of baseline data for corrosion of tubes by ash components	08/31/91	
Subtask 1b, No. 6	Accelerated corrosion testing; coupon testing in boiler	11/30/91	
Subtask 1b, No. 7	On-line deposition analysis	12/31/91	
Subtask 1b, No. 8	Complete deposition testing (auxiliary spectroscopic testing); complete corrosion modeling; complete deposition modeling	01/15/92	
Subtask 1c, No. 1	Develop erosion test plan	10/15/89	10/15/89
Subtask 1c, No. 2	Complete research boiler erosion evaluation	08/01/90	08/01/90
Subtask 1c, No. 3	Full-scale erosion technique decision	10/01/90	10/01/90
Subtask 1c, No. 4	Design probe for full-scale erosion study	01/01/91	02/15/91
Subtask 1c, No. 5	Construct erosion probe	05/01/91	
Subtask 1c, No. 6	Complete erosion modeling	01/15/92	
Subtask 1d, No. 1	Identify viscometer	10/15/89	10/15/89
Subtask 1d, No. 2	Complete preliminary viscosity and stability tests	08/15/90	09/15/90
Subtask 1d, No. 3	Complete viscosity and stability tests	01/15/92	
Task 2, No. 1	Complete economic evaluation	01/15/92	
Task 3, No. 1	Complete final report	03/01/92	

Table 2. KVS Coal-Water Slurry Fuel Production Run for July 22, 1991

Time	PSU Id #	Solids Loading (wt. %)	Particle Size Distribution			Viscosity		pH	Ball Mill Operating Conditions		
			D(V,0.5)	-71.4 μ m	-200 mesh	100 s-1	Brkfld		Dry Coal	A-23	4800C
11:00	01	53.55	38.4	71.9	86.85	97	120	7.28	4816	1.04	0.00
11:30	02	53.57	36.6	73.9		138					
12:00	03md	58.67	44.7	66.7		414					
12:00	03p	57.00	27.5	80.4	74.96	190	180	6.77	5130	1.01	0.00
Mill Shutdown to Empty Off-Spec. Material											
16:00	04	57.25	26.7	79.0	82.46	194	224	6.70	3776	1.01	0.00
16:30	05	57.79	31.2	75.6		251					
17:00	06	58.33	34.0	73.4	78.19	276	280	6.67	3993	0.97	0.00
17:30	07	58.28	33.2	72.6		292					
18:00	08	59.11	32.3	73.1	76.83	293	300	6.70	3933	1.11	0.00

Comments:

- Solids loading were determined using a CEM Microwave Moisture Analyzer
- Particle size distributions were determined using a Malvern Series 2600C Droplet and Particle Sizer (-200 mesh determined by KVS)
- Viscosities were determined using a Bohlin Visco 88BV (c25 cup and bob) (Brkfld viscosities were determined using a Brookfield "RVT" using a spindle #5 after 3 minutes)
- pH's were determined by KVS
- Ball mill conditions were reported by KVS
Dry coal feed rate expressed in lbs/hr
Dispersant (A-23M) and stabilizer (Flocon 4800 C) concentrations expressed as wt.% active solids/dry coal basis

Table 3. KVS Coal-Water Slurry Fuel Production Run for July 23, 1991

Time	PSU Id #	Solids Loading (wt. %)	Particle Size Distribution			Viscosity		Ball Mill		
			D(V,0.5)	-71.4 μ m	-200 mesh	100 s-1	Brkfld	pH	Dry Coal	Operating Conditions A-23 4800C
10:00	Start-up									
10:30	09	60.54	20.5	83.4		492			2280	0.84 0.00
11:00	10	60.09	20.5	82.3	85.34	481	416	6.67	2123	1.08 0.00
11:30	11	58.36	21.0	83.5		311				
11:30	Feed system blockage									
11:50	Resume feeding									
12:00	Begin feeding "clean coal" to ball mill									
12:30	12	53.50	22.7	83.8		127				
13:00	01	55.19	24.3	80.8	85.73	187	184	6.88	2123	1.07 0.00
13:00	Begin adding stabilizer									
14:00	02	57.86	25.6	80.2	84.34	323	332	6.99	2351	0.97 0.033
14:30F	03	57.68	25.0	79.4		382				
14:30	04	58.30	24.5	81.7		398				
15:00F	06	58.02	24.5	81.9	85.01	601	580	7.00	2223	0.95 0.045
15:00	05	59.30	22.5	83.6		420				
15:30F	07	58.44	23.2	81.8		703				
15:30	08	59.10	16.7	90.7		455				
16:00	Begin pumping CWSF into transport tanker									
16:00F	09	59.06	22.3	82.3		665				
16:00	10	59.51	18.7	85.8	83.71	503	676	6.94	2009	1.11 0.041
16:30F	11	59.15	23.5	81.8		783				
17:00F	12	59.25	22.6	82.4		736				
17:00	13	59.00	24.4	79.7	85.36	397	684	6.93	2237	1.03 0.036
17:30F	15	59.22	20.1	85.8		738				
17:30	14	58.59	26.0	77.8		397				
18:00F	17		18.1	89.3		755				
18:00	16	58.28	24.5	80.7	85.38	386	720	6.95	2194	0.94 0.041

Table 5. Analysis of SCCWS Produced at KVS

<u>Proximate Analysis (wt%, dry)</u>		<u>Particle Size Distribution^a (μm)</u>	
(Moisture	39.89)	D (v, 0.1)	5.0
Volatile Matter	34.72	D (v, 0.5)	23.3
Ash	4.18	D (v, 0.9)	97.2
Fixed Carbon	61.10	(-71.4 μm	82.1%)
<u>Ultimate Analysis (wt%, daf)</u>		<u>Viscosity (cp)</u>	
Carbon	83.14	@ 50/s	662
Hydrogen	5.47	@ 100/s	636
Nitrogen	1.58		
Sulfur	0.89		
Oxygen	8.92		
<u>Higher Heating Value (Btu/lb, dry)</u>			
13,850			

^aThe D(v, 0.1), D(v, 0.5), and D(v, 0.9) values are the particles where, respectively, 10, 50, and 90% of the particles, by volume, are less than the indicated size.

Table 6. Composition of Alloys Selected for Corrosion/Deposition Studies

	304	316	321	347	800H
C	.046	.017	-	.015	.08
Si	.41	.38	-	.18	.15
Mn	1.69	1.71	1.75	1.46	.98
P	.022	.023	-	.022	-
S	.023	.007	-	.007	<.001
Cr	18.18	17.22	17.25	17.15	19.62
Ni	9.47	12.9	10.25	8.75	31.65
Mo	-	2.56	-	.2	-
Co	-	-	.75	.13	-
Cu	-	-	-	.43	-
Ti	-	-	-	-	.54
Al	-	-	-	-	.32
Nb	-	-	-	.62	-
Ta	-	-	-	.02	-

Table 7. OXCE Fuel Analysis

Constituent	Ultimate Analysis (wt.% as received)	Proximate Analysis (wt.% as received)
Moisture	39.2	39.2
Ash	1.9	1.9
Volatile Matter		21.6
Fixed Carbon		37.3
Carbon	51.3	
Hydrogen	3.2	
Nitrogen	0.9	
Sulfur	0.5	
Oxygen	3.0	

Table 8. Flue Gas Data

Constituent	Convective Section	Baghouse
GAS		
O ₂	2.90 vol%	5.53 vol%
CO ₂	9.51 vol%	8.13 vol%
H ₂ O	~13.67 vol%	~11.68 vol%
N ₂	~73.45 vol%	~74.26 vol%
CO	4104 ppm	3508 ppm
NO _x	202 ppm	117 ppm
SO ₂	412 ppm	352 ppm
SOLID (wt. %)		
Carbon	69.06	68.17
Hydrogen	1.67	1.55
Nitrogen	1.36	1.33
Sulfur	~0.94	~1.18
Oxygen	~26.97	~27.77

Table 9. Summary of Metal Degradation

Metal Temperature K	Jet Velocity m/s	Jet Gas Oxygen %O ₂	Degradation Results
650	200	21	Cracked oxide and deposition
550	200	21	Oxidation and deposition
450	200	21	Erosion (1.0 $\mu\text{m/h}$)
550	300	21	Erosion (2.2 $\mu\text{m/h}$)
550	200	21	Oxidation and deposition
550	100	21	Maximum deposition
550	300	0	Maximum erosion (3.7 $\mu\text{m/h}$)
550	300	21	Erosion (2.2 $\mu\text{m/h}$)
550	300	100	Erosion (2.0 $\mu\text{m/h}$)

FIGURE 1. 1989 Milestone Schedule

FIGURE 2. 1990 Milestone Schedule

FIGURE 3. Phase I and II 1991 and 1992 Milestone Schedule

FIGURE 4. Phase III 1991 and 1992 Milestone Schedule

Figure 6. Viscosity as a Function of Dispersant Concentration

Figure 7. Viscosity as a Function of Solids Loading

Figure 8. SCCWS Stability

Figure 9. Viscosity as a Function of Stabilizer Concentration

Figure 10. Internal Atomization Results for Micronized CWSFs and SCCWSs

a. deposited particles

b. erosive particles

Figure 11. Solid Particles in the Flue Gas of Micronized CWF

Figure 12. Ash Erosion Probe

Figure 13. The Sample Profiles Tested Under Different Metal Temperatures

a. surface under jet center

b. center point composition

Figure 14. Sample Surface Under Jet Center Tested at 650 K, 200 m/s, 21 %O₂

a. surface under jet center

b. center point composition

Figure 15. Sample Surface Under Jet Center Tested at 550 K, 200 m/s, 21 %O₂

a. surface under jet center

b. center point composition

Figure 16. Sample Surface Under Jet Center Tested at 450 K
200 m/s, 21 %O₂

a. spalling oxide

b. S1 point composition

Figure 17 a and b. Microscopic Structure and Composition of a Spalling Oxide
650 K, 200 m/s, 21 %O₂

a. 300 m/s b. 200 m/s c. 100 m/s

Figure 18. Sample Profiles Tested Under Different Jet Velocities

a. eroded center surface

b. cracking hole at 10 mm away from center

Figure 19. Local Surfaces on the Sample Tested at
550 K, 300 m/s, 21 %O₂

a. deposited surface under jet center

b. cracking chips on the loop 4 mm away from center

Figure 20. Local Surfaces on the Sample Tested at
550 K, 100 m/s, 21 %O₂

a. nitrogen b. air c. oxygen

Figure 21. The Sample Profiles Tested Under Different Jet Gases

a. center surface under nitrogen jet

b. center surface under oxygen jet

Figure 22. Eroded Metal Surfaces Under Nitrogen and Oxygen Jet
550 K, 300 m/s, 0/100 %O₂

a. CWS ash without sand

b. CWS ash with sand

Figure 23. Sample Profiles Tested Under Different Erosive Particles

a. ash mixture with angular sand

b. eroded sample surface

Figure 24. Particles and Eroded Surface Tested at 550 K, 300 m/s, 21 %O₂ with Sand

END

**DATE
FILMED**

2 / 11 / 92