DOE/BC/14246--T10

MICROBIAL FIELD PILOT STUDY

CONTRACT DE-FG22-89BC14246

DOE/BC/14246--T10

University of Oklahoma
Norman, OK 73019

DE92 004433

CONTRACT DATE

November 22, 1988

ANTICIPATED COMPLETION

June 30, 1992

PRINCIPAL INVESTIGATORS

R. M. Knapp, M. J. McInerney, D. E. Menzie

PROJECT MANAGER

Rhonda L. Patterson
Bartlesville Project Office

REPORTING PERIOD

July 1, 1992 - September 30, 1992

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

OBJECTIVE

The objective of this project is to perform a microbial enhanced oil recovery field pilot test in the Southeast Vassar Vertz Sand Unit (SEVVSU) in Payne County, Oklahoma. Indigenous, anaerobic, nitrate-reducing bacteria will be stimulated to selectively plug flow paths which have been preferentially swept by a prior waterflood. This will force future flood water to invade bypassed regions of the reservoir and increase sweep efficiency. During this quarter an additional tracer study was performed in the field to determine pre-treatment flow paths and the first nutrients were injected.

SUMMARY OF TECHNICAL PROGRESS

DETERMINATION OF PHYSICAL, BIOLOGICAL, AND BIOCHEMICAL CHARACTERISTICS OF THE PILOT AREA:

Microbiological/Biochemical Characteristics

Baseline microbiological and biochemical analyses were completed on the reservoir pilot and 1A regions of the reservoir prior to injection of the ammonium nitrate and molasses. After injection, the biochemical analyses were carried out weekly and the microbial counts were done monthly.

The microbial counts were determined using media specific for sulphate reducing bacteria (SRB), molasses/nitrate (M/N) fermenting bacteria as well as general aerobic and anaerobic bacterial counts (PCBa and PCBan, respectively). In all cases the baseline cell count in the injection brine was significantly higher than those of

the production wells in both the pilot and 1A areas. Results of samples analyzed since injection cannot be presented here due to the long term nature of these assays.

Physical and biochemical analyses were conducted on each of the brine samples including pH, surface tension, sulphide determination, carbohydrate determination, nitrate determination, volatile fatty acid (VFA) determination and chemical oxygen demand (COD) determination. The results indicated no significant alteration in the pH or surface tension of each of the wells tested throughout this quarter. Sulphide concentrations measured during this quarter were, however, significantly higher than those measured previously (reservoir average of 270ppm as opposed to 50ppm) and were shown to continuously increase to a reservoir average of almost 500ppm at the end of the quarter (Figure 1). Measured carbohydrate and nitrate concentrations were not noted to vary significantly in the pilot or 1A production wells even after injection of the ammonium nitrate and molasses, however, injection occurred just before the end of the quarter. A decrease was noted in the average COD of the production well samples (from 1500ppm to 1000ppm) during the same time period. This was mainly due to a drop in the COD of 1A-9 from 3,000ppm to 1,200ppm, similar decreases were not noted in any of the other wells sampled.

FIELD ACTIVITIES

Tracer Study

A second tracer study was initiated in the Southeast Vassar Vertz Sand Unit as shown in Figure 2. To the west, Wells 7-1, 5-1,

and 5-2, the target wells in the Microbial Field Pilot Study, were produced at a total rate of 600 bbl. per day while 300 bbl. per day of water was being injected into Well 7-2. This policy was adopted to insure a significant pressure sink to the west and encourage injected fluids to migrate in that direction.

Two fluorescent dyes (fluorescein and rhodamine WT) were tested. The pilot tracer study was initiated with fluorescein as the rhodamine WT was adsorbed to a crushed sample of the Vassar reservoir sandstone. Fluorescein effluent in the production wells was determined by measurement of absorbance at 489 nm (the wavelength of maximum absorbance for fluorescein in the visible region) and confirmed by fluorescence on irradiation with UV light.

On August 5th, 1991, five hundred grams of sodium fluorescein were injected into Well 7-2 during a forty minute period. Samples of fluid were taken daily at the surrounding production wells.

As with the tracer test run in the first quarter of 1991, the tracer was detected in the northeast. The 7-5 and 7-3 wells immediately to the southeast and northeast of 7-2 are injectors. The 7-3 was accepting approximately 400 bbl/day of injection brine and the 7-5 just under 200. The tracer followed a path that bypassed these injectors and arrived at the 1A-1, 1A-5, and 1A-9 wells 18 days after initial tracer injection. Twenty-four days after injection, tracer was detected at the 1A-7 well. Interestingly, wells 1A-1, 1A-3, and 1A-6 all had a low concentration (not visible) of sodium fluorescein, whereas the 1A-7 had a strong concentration of tracer. The 1A-7 is further to the

east than the other three wells.

Interpretation of the results is necessarily qualitative in nature. There appears to be either a fracture system or a very high permeability flow path running from the vicinity of the 7-2 to the northeast. The transmissivity of this path is sufficiently high that even with the pressure reductions immediately to the west of the 7-2 flow was manifested to the northeast. Further, there appear to be at least two channels. One runs toward the northeast and is also a flow path for the 7-5 and 7-3 wells. This tracer was diluted by the water from the other injection wells and uniformly distributed over the region of the 1A-1, 1A-5, and 1A-9, hence the uniform arrival time and low concentrations. A second path arrives further east and does not receive additional water from the other two injection wells. This is the path that supplied the response in the 1A-7 well.

The attempt to divert the flow back to the west was somewhat successful. The original tracer study arrived at the 1A wells within 14 days. The increased drawdown to the west inhibited that arrival by at least 4 days. This indicates that part of the injected fluid has probably moved to the west.

Nutrient Injection

On August 26th, 1991 41,500 lbs. of ammonium nitrate was delivered to the SEVVSU and combined with 300 bbl. of Vassar brine. The resultant mixture was 369 bbl. at 18.7% ammonium nitrate by volume. On August 29th a pre-flush consisting of 38 bbl of nitrate mixture was injected into the regular SEVVSU injection stream to

inhibit sulfate reducing bacteria and stimulate nitrate reducing bacteria in the region to be flooded.

On September 26th, 1991 twelve tons of 79.5 brix molasses was delivered to location. This was mixed with the brine-ammonium nitrate to achieve a 46% molasses, 46% brine, 8% ammonium nitrate solution by volume. On September 27th, 36 bbl of this mixture was injected into the injection stream of Well 7-2. The injection rates were balanced so that the combined fluid in the tubing and at the injection sand face was 20% molasses. This was followed with Vassar brine to lower the molasses concentration to 2%.

A significant increase in injection rate occurred at the well during nutrient injection. This is attributed to the increased hydrostatic head caused by increased fluid density during injection.

Future Plans

Injection of the remaining 74 bbl of nutrient mixture will be accomplished in two batches during early October. After a brine spacer is pumped to flush nutrient from the near wellbore area, a pressure falloff test on the injection well will be performed. Injection into Well 7-2 will be stopped to allow metabolism of the nutrients injected and increase microbacterial populations. Additional nutrient injections are planned for the next quarter. Eventually another tracer test will be performed to determine if the flow paths in the reservoir have been altered.

Figure 1. Vassar Reservoir Sulphide Concentration. Absence of a bar indicates missing data.

- ▲ INJECTION WELL (Active)
- ◡ INJECTION WELL (Inactive)
- PRODUCING WELL (Active)
- PRODUCING WELL (Inactive)

SULLIVAN AND COMPANY
TULSA, OKLAHOMA

S.E. VASSAR VERTZ SAND UNIT
PAYNE COUNTY, OKLAHOMA

FIGURE 2 WELL SITES

END

**DATE
FILMED**

01 / 23 / 92,