AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

1 of 1

Appendix SET-TMP-PT of the
Experiment Operating Specification for the Savannah River
One-Fourth Linear Scale, One-Sixth Sector,
Tank/Muff/Pump (TMP) Separate Effects Tests (SET)
Experiment Series

T. J. Boucher and J. L. Anderson (INEL)
J. S. Bollinger (WSRC)
J. D. Sterrett (Reece Engr. Assoc.)

Authors:

J. L. Anderson
J. L. Anderson

5-21-93

Date

Authors:

T. J. Boucher for J. S. Bollinger
J. S. Bollinger

5-25-93

Date

Authors:

T. J. Boucher
T. J. Boucher

5/21/93

Date

Reviewed:

K. G. Condie
K. G. Condie, INEL SET Project Manager

5/25/93

Date

Approved:

D. C. Mecham
D. C. Mecham, Exp. Programs Unit Manager

5/21/93

Date

MASTER

CB

**Appendix SET-TMP-PT of the
Experiment Operating Specification for the Savannah River
One-Fourth Linear Scale, One-Sixth Sector,
Tank/Muff/Pump (TMP) Separate Effects Tests (SET)
Experiment Series**

by

J. S. Bollinger
(Westinghouse Savannah River Company)

J. D. Sterrett
(Reece Engineering Associates)

J. L. Anderson
T. J. Boucher
(Idaho National Engineering Laboratory)

May, 1993

Prepared for the
U.S. Department of Energy
Idaho Operations Office
Under DOE Contract No. DE-AC07-76ID01570
and
Westinghouse Savannah River Company

CONTENTS

1. INTRODUCTION	1
2. FACILITY CONFIGURATION	5
2.1 System Protection	12
3. EXPERIMENT OPERATION.....	16
3.1 Prerequisites	16
3.2 Initial and Boundary Conditions	17
3.3 Measurement Requirements	18
3.4 Measured or Computed Parameter Requirements	42
3.5 Experiment Termination Criteria	47
3.6 Post Testing Operational Checks.....	47
3.7 Experiment Acceptance Criteria.....	48
4. REFERENCES	49
Appendix A - General Guidance for SET 1/4 Linear Scale Bingham Pump Single-Phase and Two-Phase, Two-Component Complete Characterization Tests	A-1
Appendix B - Test Matrix Tables for SET Phase III Tests From NES-CDG-920181 ..	B-1
Appendix C - Test Matrix Tables for SET Phase III Tests From NES-CDG-920241, Revision 1	C-1

FIGURES

1.	SET Facility in the Tank/Muff/Pump Short Discharge Configuration (Mod-TMPSD) for Pump/System Forward Flow Tests	6
2.	SET Facility in the Tank Bypass Short Discharge Configuration (Mod-TBSD) for Pump/Pump Suction Forward Flow Tests.....	7
3.	SET Facility in the Bingham Pump Reverse Flow Configuration (Mod-BPRF) for Pump Reverse Flow Tests.....	8
4.	Piping and Instrumentation Drawing (PID) for INEL SET Facility in the Tank/Muff/Pump Short Discharge (Mod-TMPSD) Configuration.....	9
5.	Piping and Instrumentation Drawing (PID) for INEL SET Facility in the Tank Bypass Short Discharge (Mod-TBSD) Configuration	10
6.	Piping and Instrumentation Drawing (PID) for INEL SET Facility in the Bingham Pump Reverse Flow (Mod-BPRF) Configuration.....	11
A-1.	Complete Pump Characteristics for a Typical Double-Suction Centrifugal Pump as Reported by A. J. Stepanoff.....	A-3
A-2.	Example Pump Characteristic Curves Showing Relationship Between Homologous Parameters and Stepanoff Curve (Figure A-1) Zones	A-4
A-3.	Example Pump Homologous Head Curves Showing Relationship Between Homologous Head Parameters and Stepanoff Curve (Figure A-1) Zones	A-5
A-4.	Example Pump Homologous Torque Curves Showing Relationship Between Homologous Torque Parameters and Stepanoff Curve (Figure A-1) Zones.....	A-6
A-5.	Skeleton Test Matrix for the Four Pump Characteristic Curve Quadrants.....	A-8

TABLES

1.	P&ID Drawings	13
2.	General System Configuration	13
3.	General Control System Configuration.....	14
4.	General Configuration Drawings.....	14
5.	Hydraulic Resistance Compensating Orifices for the SET Mod-TMPSD Configuration.....	15
6.	Pre-Testing Operational Checks.....	16
7.	SET Tank/Muff/Pump Short Discharge (Mod-TMPSD) Experiment Instrumentation Grouped by Subsystem	19

TABLES

8.	SET Tank Bypass Short Discharge (Mod-TBSD) Experiment Instrumentation Grouped by Subsystem	31
9.	SET Bingham Pump Reverse Flow (Mod-BPRF) Experiment Instrumentation Grouped by Subsystem	37
10.	Critical Parameters for SET-TMP-PT Single-Phase Bingham Pump Tests Grouped by Subsystem	43
11.	Critical Parameters for SET-TMP-PT Two-Phase Bingham Pump Tests Grouped by Subsystem	44
12.	Possible Methods of Obtaining Critical Parameters	45
13.	Post-Testing Operational Checks.....	47
A-1.	Explanation of Stepanoff Curve Zones in Terms of Normalized Pump Homologous Parameters	A-7
A-2.	Repeat Two-Phase Integral System Characterization with Pump Suction Air Injection Tests.....	A-11
B-3.	Single-Phase Liquid 1/4 Scale Formal Bingham Pump Quadrant One, Speed-to-Flow Ratio ≤ 1 Tests.....	B-2
B-5.	Single-Phase Liquid 1/4 Scale Formal Bingham Pump Free Rotor Hydraulic Characterization Tests.....	B-4
C-1.	Two-Phase Air-Water 1/4 Scale Formal Integral Tests - Pump Discharge Break with and without Simulated AC Pump Motor Trip.....	C-2
C-2.	Controlled Drain Pump Discharge Break Formal Integral Tests.....	C-4
C-3.	Hold Point Pump Discharge Break Formal Integral Tests	C-5
C-4.	Controlled Drain Pump Discharge Break with De-energized Pump Motor - Formal Integral Tests	C-7
C-5.	Hold Point Pump Discharge Break with De-energized Pump Motor - Formal Integral Tests	C-8

1. INTRODUCTION

This document is Appendix SET-TMP-PT of the Experiment Operating Specification (EOS) for the third set of experiments in the Savannah River One-Fourth Linear Scale, One-Sixth Sector, Separate Effects Tests (SET) experiment series. It contains information on experiment operation and facility configuration necessary to meet the key objectives stated in the tank-muff-pump one-fourth linear scale Bingham pump formal test matrix definition letter[1]. In addition, general guidance is included to meet expanded objectives of providing complete characterization of the pump for all modes of operation (partially defined in a letter defining pump suction and maximum flow rate characterization tests[2]). Finally, information necessary to complete testing initiated as part of Phase II testing is also included[3 thru 6].

The Savannah River One-Fourth Linear Scale, One-Sixth Sector, Tank-Muff-Pump (TMP) Separate Effects Tests (SET) are being conducted by the Idaho National Engineering Laboratory (INEL) to investigate Savannah River Site (SRS) production reactor tank, muff, pump suction, and pump hydraulic response phenomena for large break loss-of-coolant accident (LBLOCA) scenarios. The test series consists of experiments representing a range of hydraulic conditions and geometries which bound those anticipated for LBLOCAs in SRS reactors. Data from these experiments will be examined to identify important hydraulic phenomena with the objective of providing data for benchmarking code calculations. Information obtained from the SET series will also expand the SRS data base on reactor LBLOCA events. Due to inherent scaling distortions and facility limitations, the results of experiments in the SET series will not be precise replications of full-scale Savannah River Site production reactor (SRSPR) response. The experiments will, however, provide hydraulic behavior sufficiently representative of full-scale SRSPR behavior to preserve important hydraulic phenomena and satisfy test objectives. Subsequent references in this document to simulating a full-scale SRSPR are restricted to the design of the experiment rather than the quantitative results expected.

The one-fourth linear scale Bingham pump will be characterized over a broad range of single-phase liquid and two-phase, two-component, air-water flow conditions in the SET-TMP-PT tests. Initial definition of Phase III testing needs focused primarily on pump characterization for SRS reactor prototypic conditions[1]. However, further consideration has resulted in a change in emphasis which puts greater focus on pump characterization for all modes of operation. Such testing will satisfy the requirements for SRS reactor prototypic condition pump characterization as well as provide a significant data base on scaled two-phase, two-component pump performance for all modes of operation. This data base will prove very beneficial for a wide range of applications

including general thermal-hydraulic computer code pump modeling as well as SRS production reactor pump modeling.

The various modes of pump operation can be described in several manners. However, for Phase III pump testing, the typical centrifugal pump characteristics discussed by Stepanoff[7] will be utilized. Appendix A provides a brief description of the pump characteristics discussed by Stepanoff along with a brief discussion on the correlation of the Stepanoff curves to the general homologous pump curves and the homologous head and torque curves. As shown in Figure A-1, the various modes of operation have been identified by zone and lettered A thru H. The intent of Phase III pump testing will be to provide single and two-phase pump characterization for all modes of operation identified in the figure for a range of pump speeds, pump suction pressures and pump inlet volumetric flow qualities (β). Based on the nomenclature identified in Appendix A, the following Bingham pump tests will be conducted as part of the SET-TMP-PT test series:

- Forward rotation, forward flow, normal pump (Zone A - positive head and torque) two-phase pump characterization and formal tests. (This zone was well characterized for single-phase conditions during Phase II testing).
- Forward rotation, reverse flow, energy dissipation (Zone B - positive head and torque) single and two-phase pump characterization and formal tests.
- Reverse rotation, reverse flow, normal turbine (Zone C - positive head and torque) single and two-phase pump characterization and formal tests.
- Reverse rotation, reverse flow, energy dissipation (Zone D - positive head and negative torque) single and two-phase pump characterization and formal tests.
- Reverse rotation, forward flow, reverse rotation pump (Zone E - positive head and negative torque) single and two-phase pump characterization and formal tests.
- Reverse rotation, forward flow, energy dissipation (Zone F - negative head and negative torque) single and two-phase pump characterization and formal tests.
- Forward rotation, forward flow, reverse flow turbine (Zone G - negative head and negative torque) single and two-phase pump characterization and formal tests.
- Forward rotation, forward flow, energy dissipation (Zone H - negative head and positive torque) single and two-phase pump characterization and formal tests.
- Dead-head, forward rotation, no flow (boundary between zones A and B) and reverse rotation, no flow (boundary between zones D and E) single-phase pump tests.

- Locked-rotor, no rotation, forward flow (boundary between zones F and G) and no rotation, reverse flow (boundary between zones B and C) single and two-phase pump tests.
- Zero head, forward rotation, forward flow (boundary between zones A and H) and reverse rotation, forward flow (boundary between zones E and F) single and two-phase pump tests.
- Zero torque, forward rotation, forward flow (boundary between zones G and H) and reverse rotation, reverse flow (boundary between zones C and D) single and two-phase pump tests.
- Free-rotor (de-energized motor), forward flow single-phase pump formal tests.
- Simulated pump discharge break draindown formal tests with and without AC motor trip.
- Simulated pump discharge break draindown formal tests with pump motor de-energized (free rotor).
- Simulated pump discharge break single and two-phase hold point formal tests.
- Simulated pump discharge break single and two-phase hold point formal tests with pump motor de-energized (free rotor).
- Two-phase air-water pump suction pressure sensitivity characterization and formal tests.

As noted above, pump characterization and formal tests will be performed to determine whether the pump suction absolute pressure has a significant impact on pump performance. Tests conducted by Babcock and Wilcox Company (B&W) for the Electric Power Research Institute (EPRI) for a 1/3-scale Bingham pump with air-water flow conditions incorporated extensive redundant tests at several pump suction pressures[8, 9]. Suction side pressures in the B&W tests ranged from 5 to 95 psig although most of the tests were performed at pressures exceeding 30 psig. B&W test results indicated suction side pressure to have only second order impacts on two-phase pump performance. This may not be the case, however with the 1/4-scale SET Bingham pump, which is a radial flow pump with a specific speed of $1176 \text{ rpm(US gpm)}^{1/2}/\text{ft}^{3/4}$ whereas the specific speed of the 1/3-scale B&W pump was $4317 \text{ rpm(US gpm)}^{1/2}/\text{ft}^{3/4}$, characteristic of a mixed flow machine. Comparisons of EPRI pump test data at high specific speeds with the Semiscale test data (specific speed of $926 \text{ rpm(US gpm)}^{1/2}/\text{ft}^{3/4}$) indicate that both single and two-phase pump performance is significantly impacted by the specific speed of the pump[10]. Pump suction pressure characterization testing is therefore being performed in the SET-TMP-PT test program to provide adequate characterization of pressure sensitivities.

The SET-TMP-PT tests will be performed to thoroughly map pump performance as a function of the normalized total (air and liquid) flow rate, the normalized pump speed, and the volumetric

quality of the suction-side flow in all four operating quadrants with the emphasis on quadrant one. The testing will include multiple homologous variable data points with the individual points being generated at different pump speed and flow rate conditions. These data will be used to determine whether two-phase pump performance follows the single-phase pump performance affinity relationships. Test points will be concentrated at values of the suction side volumetric quality at which pump head degradation and recovery are expected to occur. The volumetric quality of these test points will be shifted as dictated by the results of the tests. Extensive tests have already been performed to characterize single-phase liquid pump performance for quadrant one. However, additional single phase tests will be performed in the remaining three quadrants to provide the complete single-phase homologous curves for utilization in analyzing the two-phase results.

An important objective of the tests will be to determine the flow regimes present in the entrance to the Bingham pump over the range of conditions tested since the two-phase air-water pump performance may change dramatically in transitioning from one flow regime to another.

A number of Phase II two-phase steady-state hold point tests will be repeated with the tank bypass, short pump discharge geometry (Mod-TBSD) and pump suction air injection. Data from these counterpart tests will be compared to the Phase II test results to investigate the sensitivity of the pump response to the method of air introduction and the pump suction and discharge geometries.

Tests will be performed with the pump rotor locked in place to characterize the single and two-phase losses across the pump with flow in the normal direction. The pump geometry is such that the locked rotor resistance will be somewhat sensitive to the impeller position. Hence, the sensitivity to impeller position will be investigated by performing similar single-phase tests for several impeller positions. Also, the position of the rotor shaft (and therefore the impeller) will be noted for the locked rotor tests. Similar tests will involve de-energizing the Bingham pump motor and performing tests with the impeller free to rotate with single and two-phase normal pump flow. This data will be used to quantify the hydraulic resistance through the Bingham pump for both single and two-phase flow with the pump impeller free to rotate. The resulting data will be used to determine the pump hydraulic resistance so that ECS LOCA scenarios for the pump discharge break may be simulated in which both the AC and DC pump drive motors have been shut down.

Second quadrant single-phase liquid test results will also be useful for analyzing the SRSPR pump suction break ECS LOCA scenario. The pump suction break ECS LOCA scenario involves a postulated pipe break at the pump suction flange such that the pump suction sees an atmospheric

pressure boundary condition. The scenario would initially begin with the Bingham pump in K-Reactor running at rated speed (AC motor operation). Following the pipe rupture, the system would rapidly depressurize and the moderator tank would drain. The discharge side of the pump on the ruptured pipe would see a time varying pressure boundary condition as the accident progressed. At some point in the scenario, the AC pump motor would be tripped off-line and the pump speed would decrease to approximately 1/3 of the rated speed (DC motor operation). In simulating the pump suction break accident, it is critically important to accurately predict the break flow rates. This requires having homologous pump curves for the quadrant two energy dissipation (positive pump rotation with back flow through the pump) region which are currently unavailable for the Bingham pumps used in K-Reactor. Single-phase pump data will be taken for four normalized pump speeds (α) ranging from about 0.3 to about 1.0 and at normalized flow rates (v) ranging from 0.05 to about 1.0.

The remainder of this appendix is divided into two major sections. Section 2, "Facility Configuration," defines the required SET system configurations for the various SET-TMP-PT tests. The final section, "Experiment Operation," details system operational requirements for each set of SET-TMP-PT tests.

2. FACILITY CONFIGURATION

The facility configuration required for the pump characterization tests (SET-TMP-PT) is the One-Fourth Linear Scale, One-Sixth Sector Separate Effects Tests (SET) system in the Tank/Muff/Pump Short Discharge (SET Mod-TMPSD), Tank Bypass Short Discharge (SET Mod-TBSD) and Bingham Pump Reverse Flow (SET Mod-BPRF) configurations, as shown in Figures 1 thru 6. The SET facility is capable of simulating: a sector (one-sixth) of the L-Reactor moderator tank (including assemblies); an L-Reactor tank muff; an L-Reactor tank exit nozzle; L-Reactor pump suction piping (Systems 1, 5 or 6); an L-Reactor Bingham pump; and, L-Reactor pump discharge piping (System 5). With the exception of the Bingham pump all key components are constructed primarily from transparent materials which allow flow visualization. In the SET Mod-TMPSD configuration, the L-Reactor moderator tank, L-Reactor tank muff, L-Reactor tank exit nozzle, L-Reactor System 5 pump suction geometry, an L-Reactor Bingham pump and a portion of the first vertical section of the L-Reactor System 5 pump discharge geometry are simulated. A flow control valve is installed between the 1/4 scale pump discharge vertical section termination point and the liquid storage tank. In the SET Mod-TBSD configuration, a portion of the L-Reactor System 5 pump suction geometry, an L-Reactor Bingham pump and a portion of the first vertical section of the L-Reactor System 5 pump discharge geometry are simulated. A flow

Figure 1. SET Facility in the Tank/Muff/Pump Short Discharge Configuration (Mod-TMPSD) for Pump/System Forward Flow Tests.

Figure 2. SET Facility in the Tank Bypass Short Discharge Configuration (Mod-TBSD) for Pump/Pump Suction Forward Flow Tests.

Figure 3. SET Facility in the Bingham Pump Reverse Flow Configuration (Mod-BPRF) for Pump Reverse Flow Tests.

Figure 5. Piping and Instrumentation Drawing (PID) for INEL SET Facility in the Tank Bypass Short Discharge (Mod-TBSD) Configuration.

Figure 6. Piping and Instrumentation Drawing (PID) for INEL SET Facility in the Bingham Pump Reverse Flow (Mod-BPRF) Configuration.

control valve is installed between the 1/4 scale pump discharge termination point and the liquid storage tank. In the SET Mod-BPRF configuration the supply pump is connected to the scaled Bingham pump discharge in order to produce reverse flow through the pump. A flow control valve is installed between the 1/4 scale pump suction termination point and the liquid storage tank. Basically, the SET facility consists of fluid systems (pipes, pumps, tanks, heat exchanger, heater, etc.), control systems (pumps, valves, and instrument air), and an experimental measurement system (transducers, amplifiers, digital data system). Further details of these subsystems may be found in Reference 11.

Table 1 lists the P&ID drawings applicable to the SET-TMP-PT tests. The general system configuration for the SET-TMP-PT tests is outlined in Table 2. The configuration for the general control system is outlined in Table 3 and Table 4 lists the general configuration drawings for the SET-TMP-PT test configurations. Hydraulic resistance compensating orifices used for the tests are outlined in Table 5.

Additional system configuration requirements for certain pump modes of operation are:

- Pump motor wiring must be re-configured (2 of 3 phases reversed) for reverse rotation tests.
- A speed control device must replace the motor for pump turbinizing mode operations.
- A lever arm must be attached to the shaft to prevent rotation for pump locked rotor tests.

2.1 System Protection

The integrity of the SET facility for Phase III tests in the SET Mod-TMPSD configuration is preserved with rupture disks. The two rupture disks connected to the moderator sector tank provides sufficient pressure and vacuum relief capacity to protect the system. A drain is located in the test cell floor and all equipment in the test cell are located at an elevation above the floor and sufficiently remote from the moderator sector tank rupture disk piping to protect against water damage due to failure of moderator tank rupture disks.

The integrity of the SET facility for Phase III tests in the SET Mod-TBSD and Mod-BPRF configurations is preserved without rupture disks or relief valves. All three of these configurations are limited to test loop, scaled Bingham pump and supply system piping and do not include the moderator tank or transition elbow. Since the design pressures for the test loop, scaled Bingham pump and supply system piping are well above the dead head pressure of the liquid supply and 1/4 linear scale Bingham pumps, no pressure protection is required.

Table 1. P&ID Drawings	
Drawing Number	Drawing Title
438994	1/4 Scale Separate Effects Test Piping and Instrumentation Diagram (Subset of Piping and Instrumentation shown on P&ID)

Table 2. General System Configuration	
Basic Fluid System Configuration	SET Mod-TMPD, SET Mod-TBSD, SET Mod-BPRF
Major fluid systems used	Test loop; liquid supply system; liquid injection system; air supply system; air injection system
Simulated Pump Suction Geometry	System 5 (EG&G Drawing 438933) for SET Mod-TMPD. Second horizontal and second vertical sections of System 5 (EG&G Drawing 438933) for SET Mod-TBSD. Second vertical section of System 5 (EG&G Drawing 438933) for SET Mod-BPRF.
Simulated Pump	1/4 linear scale Bingham pump for all tests.
Simulated Pump Discharge Geometry	First vertical section up to expansion joint of System 5 (EG&G Drawing 442955) for SET Mod-TMPD and SET Mod-TBSD. All vertical and 45° sections up to entrance to horizontal section of System 5 (EG&G Drawing 442955) for SET Mod-BPRF.

Table 3. General Control System Configuration	
General Control System Configuration	SET Mod-TMPD, SET Mod-TBSD, SET Mod-BPRF
Major control systems used	Liquid storage tank heater; liquid storage tank heat exchanger; liquid supply pump speed; liquid supply bypass flow; air supply system flow; 1/4 scale Bingham pump speed; 1/4 scale pump discharge exit flow.

Table 4. General Configuration Drawings		
Drawing Number	Revision	Drawing Title
438042		Moderator Tank Front Panel Assembly
438046		Moderator Tank Side Panel Assemblies
437726		Moderator Tank Tube Assembly and Detail
438918		Moderator Tank Angle Assemblies and Details
438919		Moderator Tank Angle Assembly and Details
438929		Pipe Spool Assemblies
438933		Loop 5 with Pump Piping Installation
438936		Transition Elbow Assembly
436299		Muff Assembly
438928		Elbow Assemblies
439003		Air Manifold Assemblies
439031		Water Manifold Assemblies
439032		Water Manifold Assemblies
438907		Water Storage Tank Assembly
438938		Muff Storage Cask and Source Holder Assemblies and Details
432982		Muff Densitometer Wafer Assembly
439043		6" Wafer Densitometer
439045		5" Wafer Densitometer
439044		4" Wafer Densitometer
442955		Pump Discharge Spool and Elbow Arrangement
442956		Pump Discharge Spools and Flange Details
442957		Pump Discharge Elbows

Table 5. Hydraulic Resistance Compensating Orifices for the SET Mod-TMPSD Configuration

Loop Isolation Valve Simulator:

Orifice ID	13.84 cm (5.45 inches)
Part No.	438926-10
Geometry	Square Edged
Simulated Loop Isolation Valve Full Open Loss Factor (K)	.1285
Calculated Orifice Loss Factor (K)	.1282

3. EXPERIMENT OPERATION

This section provides the detailed operating requirements for the SET-TMP-PT tests. Included are prerequisites (pretest activities), test matrices (boundary and initial conditions), and required measured or computed parameters.

3.1 Prerequisites

Operations to be performed prior to initiating tests each day are listed in Table 6.

Table 6. Pre-Testing Operational Checks	
	Items To Be Checked
1. Check liquid levels - drain conditions	1/4 scale pump suction piping. 1/4 scale pump discharge piping.
2. Check densitometers - drain conditions	Horizontal section of 1/4 scale pump suction piping. Second vertical section of 1/4 scale pump suction piping. First vertical section of 1/4 scale pump discharge piping.
3. Leak check - liquid full conditions	1/4 scale pump suction piping, 1/4 scale pump discharge piping, liquid storage tank, liquid supply system and separator standpipe system.
4. Check liquid levels, densitometers - full conditions	Same items as checked in 1 and 2 above.
5. Flow checks - well bled/vented liquid full condition	Turbine flowmeters, thermal mass flowmeters, differential pressures.

In addition to the daily pre-testing operational checks, water quality checks should be made periodically with a surface tensiometer and precision hydrometers to ascertain the surface tension and specific gravity, respectively for the water in the storage tank. As a minimum, the checks should be made whenever the liquid storage tank inventory is replaced or the storage tank liquid temperature is changed for a series of tests.

3.2 Initial and Boundary Conditions

The initial and boundary conditions for the SET-TMP-PT tests are outlined in References 1 thru 4 and on the test matrix tables shown in Appendices B and C.

Appendix A contains the general guidance for single-phase and two-phase pump characterization tests which satisfy the key objectives stated in References 1 and 2 (including pump suction air injection counterparts to Phase II moderator tank assembly air injection and air aspiration tests) as well as the expanded objectives of providing complete characterization of the pump for all four quadrants as follows:

- The key variables for these tests will be pump speed, total volumetric flow rate, pump inlet volumetric flow quality (β), and pump inlet pressure.
- Testing will be performed for a range of pump speeds such that normalized speeds (α) ranging from about 0.1 to about 1.2 are adequately characterized to ascertain pump speed sensitivities.
- Testing will also be performed for a range of pump inlet volumetric flow qualities (β) ranging from 0 to about 0.9 to characterize pump degradation and pump resistance characteristics with the major emphasis on qualities in the region of rapid pump head degradation. The volumetric flow quality for the two-phase air injection tests is defined as $\beta = [Q_{\text{air}} / (Q_{\text{liquid}} + Q_{\text{air}})]$ where the air density is based on pump inlet conditions (P_7 and TF_7 for forward flow tests and P_8 and TF_8 for reverse flow tests).
- Pump inlet pressures ranging from about 125 to about 300 kPa will be investigated to characterize pump inlet pressure sensitivity effects.
- Testing will be reviewed, modified and performed as necessary to provide adequate characterization of the 1/4 scale Bingham pump for all modes of operation under single and two-phase conditions, including pump speed and pump inlet pressure sensitivity effects. Test results will be reviewed on a weekly basis to ascertain additional data needs to complete the characterization tests. The results of the review will provide a basis for testing performed in the following week.
- For tests requiring reverse pump rotation, pump motor wiring will be re-configured (2 of the 3 phases reversed) to drive the pump in reverse rotation.

- For tests requiring turbinizing mode operation of the pump, the pump motor will be removed and the pump will be connected to a speed control device.
- For tests investigating pump locked rotor characteristics, rotation is prevented by attaching a lever arm which locks the pump shaft thereby preventing rotation of the pump impeller. The position of the rotor shaft will be noted.

Appendix B (Tables B-3 and B-5) contains single-phase pump tests identified in Tables 3 and 5 of Reference 3 which were originally specified as part of Phase II testing but had to be delayed until Phase III due to limitations in achieving the specified conditions in the Phase II configuration. Forward and reverse flow locked rotor resistance and zero head and torque tests identified in Reference 3 will be performed as part of the single-phase pump characterization testing. Tests which address the conditions and objectives specified in Reference 3, Tables 4 and 6 will be performed under a different nomenclature which will be identified in posttest reports.

Pump discharge break studies originally identified in Reference 4 as part of Phase II testing were also delayed until Phase III due to Phase II configuration limitations on achieving specified conditions. These tests are identified in Appendix C (Tables C-1 thru C-5) for inclusion in Phase III testing.

The ranges of variables identified for tests identified as additional characterization tests in Reference 2 (Tables 1 thru 5) will be adequately covered as part of the two-phase pump characterization testing. Tests which address the conditions and objectives specified in the reference tables will be performed under a different nomenclature which will be identified in posttest reports.

3.3 Measurements Requirements

This section contains the overall requirements for experimental measurements for the SET-TMP-PT Phase III pump characterization tests. Tables 7, 8 and 9 contain the desired instruments, grouped by subsystem, for tests using the tank/muff/pump short discharge (Mod-TMP-SD, Figures 1 and 4), tank bypass short discharge (Mod-TBSD, Figures 2 and 5) and the Bingham pump reverse flow (Mod-BPRF, Figures 3 and 6) geometries, respectively. Information given includes the measurement type and location, measurement range, and the manufacturer specified accuracies. These manufacturer specified accuracies should not be considered the measurement uncertainty. Actual measurement uncertainties will be included in the

Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem

1. Building Atmosphere Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 103.4 ± 0.108 kPa (0 to 15 ± 0.016 psia)	P_ATM	Building Atmosphere Pressure
273 to 373 ± 0.2 K (32 to 212 ± 0.4 °F)	TF_ATM	Building Atmosphere Temperature
5 to 100 % (± 3% of reading)	RH_ATM	Building Atmosphere Relative Humidity
2. Moderator Tank Air Vent Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 5.0 ± 0.025 kPad (0 to 20 ± 0.010 inches)	DP_TK_VT	Moderator Tank Air Vent Differential Pressure
-1500 to +1500 ± 15 SLPM (-396 to +396 ± 4 gpm)	Q_A_TV_H	Moderator Tank Air Vent High Range Volumetric Flow Rate
-100 to +100 ± 1 SLPM (-26.4 to +26.4 ± 0.3 gpm)	Q_A_TV_L	Moderator Tank Air Vent Low Range Volumetric Flow Rate
0 to 103.4 ± 0.108 kPa (0 to 15 ± 0.016 psia)	P_TK_VT	Moderator Tank Air Vent Pressure
273 to 373 ± 0.2 K (32 to 212 ± 0.4 °F)	TF_A_OUT	Moderator Tank Air Vent Temperature on Atmospheric Side of Flowmeter
5 to 100 % (± 3% of reading)	RH_A_OUT	Moderator Tank Air Vent Relative Humidity on Atmospheric Side of Flowmeter

Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem
(Continued)

3. Moderator Tank Assemblies Air Injection Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
273 to 373 $\pm$ 0.2 K (32 to 212 $\pm$ 0.4 °F)	TF_A_IN	Moderator Tank Assemblies Air Temperature for Total to ALL Air Banks
237.9 to 430.9 $\pm$ 0.5 kPa (22 to 50 $\pm$ 0.08 psig)	P_A_IN	Moderator Tank Assemblies Air Pressure for Total to ALL Air Banks
150 to 1500 $\pm$ 15 SLPM (39.6 to 396 $\pm$ 4 gpm)	Q_A_BT_H	Moderator Tank Assemblies Air High Range Volumetric Flow for Total to ALL Air Banks
52 to 300 $\pm$ 3 SLPM (13.7 to 79.2 $\pm$ 0.8 gpm)	Q_A_BT_L	Moderator Tank Assemblies Air Low Range Volumetric Flow for Total to ALL Air Banks
30 to 162 $\pm$ 3 SLPM (7.9 to 42.8 $\pm$ 0.8 gpm)	Q_A_B1_H	Moderator Tank Assemblies Air High Range Volumetric Flow for Bank 1 (Sector I)
3 to 30 $\pm$ 0.3 SLPM (0.79 to 7.90 $\pm$ 0.08 gpm)	Q_A_B1_L	Moderator Tank Assemblies Air Low Range Volumetric Flow for Bank 1 (Sector I)
30 to 324 $\pm$ 3 SLPM (7.9 to 85.6 $\pm$ 0.8 gpm)	Q_A_B2_H	Moderator Tank Assemblies Air High Range Volumetric Flow for Bank 2 (Sector II)
5 to 50 $\pm$ 0.5 SLPM (1.32 to 13.2 $\pm$ 0.13 gpm)	Q_A_B2_L	Moderator Tank Assemblies Air Low Range Volumetric Flow for Bank 2 (Sector II)
65 to 650 $\pm$ 7.5 SLPM (17.2 to 172 $\pm$ 2 gpm)	Q_A_B3_H	Moderator Tank Assemblies Air High Range Volumetric Flow for Bank 3 (Sector III)
13 to 100 $\pm$ 1.0 SLPM (3.4 to 26.4 $\pm$ 0.3 gpm)	Q_A_B3_L	Moderator Tank Assemblies Air Low Range Volumetric Flow for Bank 3 (Sector III)

Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem (Continued)

3. Moderator Tank Assemblies Air Injection Instrumentation (Continued)			
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description	
50 to 550 ± 5 SLPM (13.2 to 145 ± 1.3 gpm)	Q_A_B4_H	Moderator Tank Assemblies Air High Range Volumetric Flow for Bank 4 (Sector IV)	
19 to 100 ± 1.0 SLPM (5.0 to 26.4 ± 0.3 gpm)	Q_A_B4_L	Moderator Tank Assemblies Air Low Range Volumetric Flow for Bank 4 (Sector IV)	
30 to 324 ± 3 SLPM (7.9 to 85.6 ± 0.8 gpm)	Q_A_B5_H	Moderator Tank Assemblies Air High Range Volumetric Flow for Bank 5 (Sector V)	
11 to 50 ± 0.5 SLPM (2.9 to 13.2 ± 0.13 gpm)	Q_A_B5_L	Moderator Tank Assemblies Air Low Range Volumetric Flow for Bank 5 (Sector V)	
4. Moderator Tank Assemblies Liquid Injection Instrumentation			
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description	
568 to 4542 ± (5.7 + 0.50% of reading) LPM [150 to 1200 ± (1.5 + 0.50% of reading) gpm]	Q_W_BT_H	Moderator Tank - Assemblies Liquid - High Range Volumetric Flow - Total to ALL Banks	
178 to 1893 ± (1.9 + 0.50% of reading) LPM [47 to 500 ± (0.5 + 0.50% of reading) gpm]	Q_W_BT_L	Moderator Tank - Assemblies Liquid - Low Range Volumetric Flow - Total to ALL Banks	
57 to 367 ± (0.49 + 0.50% of reading) LPM [15 to 97 ± (0.13 + 0.50% of reading) gpm]	Q_W_B1_H	Moderator Tank Assemblies Liquid High Range Volumetric Flow - Bank 1 (Sector I)	
11.3 to 57 ± (0.06 + 0.50% of reading) LPM [3 to 15 ± (0.02 + 0.50% of reading) gpm]	Q_W_B1_L	Moderator Tank Assemblies Liquid Low Range Volumetric Flow - Bank 1 (Sector I)	
170 to 734 ± (1.70 + 0.50% of reading) LPM [45 to 194 ± (0.45 + 0.50% of reading) gpm]	Q_W_B2_H	Moderator Tank Assemblies Liquid High Range Volumetric Flow - Bank 2 (Sector II)	
18.9 to 227 ± (0.23 + 0.50% of reading) LPM [5 to 60 ± (0.06 + 0.50% of reading) gpm]	Q_W_B2_L	Moderator Tank Assemblies Liquid Low Range Volumetric Flow - Bank 2 (Sector II)	

Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem (Continued)

4. Moderator Tank Assemblies Liquid Injection Instrumentation (Continued)			
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description	
170 to 1461 $\pm$ (1.9 + 0.50% of reading) LPM [45 to 386 $\pm$ (0.5 + 0.50% of reading) gpm]	Q_W_B3_H	Moderator Tank Assemblies Liquid High Range Volumetric Flow - Bank 3 (Sector III)	
53 to 227 $\pm$ (0.23 + 0.50% of reading) LPM [14 to 60 $\pm$ (0.06 + 0.50% of reading) gpm]	Q_W_B3_L	Moderator Tank Assemblies Liquid Low Range Volumetric Flow - Bank 3 (Sector III)	
170 to 1245 $\pm$ (1.9 + 0.50% of reading) LPM [45 to 329 $\pm$ (0.5 + 0.50% of reading) gpm]	Q_W_B4_H	Moderator Tank Assemblies Liquid High Range Volumetric Flow - Bank 4 (Sector IV)	
57 to 227 $\pm$ (0.23 + 0.50% of reading) LPM [15 to 60 $\pm$ (0.06 + 0.50% of reading) gpm]	Q_W_B4_L	Moderator Tank Assemblies Liquid Low Range Volumetric Flow - Bank 4 (Sector IV)	
170 to 734 $\pm$ (1.70 + 0.50% of reading) LPM [45 to 194 $\pm$ (0.45 + 0.50% of reading) gpm]	Q_W_B5_H	Moderator Tank Assemblies Liquid High Range Volumetric Flow - Bank 5 (Sector V)	
34.1 to 227 $\pm$ (0.23 + 0.50% of reading) LPM [9 to 60 $\pm$ (0.06 + 0.50% of reading) gpm]	Q_W_B5_L	Moderator Tank Assemblies Liquid Low Range Volumetric Flow - Bank 5 (Sector V)	
11.3 to 57 $\pm$ (0.06 + 0.50% of reading) LPM [3 to 15 $\pm$ (0.02 + 0.50% of reading) gpm]	Q_W_B2_9	Moderator Tank Assemblies SparJet Liquid Volumetric Flow - Bank 2 (Sector II), Position 9	

**Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem
(Continued)**

5. Moderator Tank Instrumentation			
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description	
0 to 116.8 ± 0.6 cm (0 to 46 ± 0.24 inches)	L_1_03	Moderator Tank Collapsed Liquid Level - Assembly 03 in Flow Zone 1 (Sector I)	
0 to 116.8 ± 0.6 cm (0 to 46 ± 0.24 inches)	L_2_14	Moderator Tank Collapsed Liquid Level - Assembly 14 in Flow Zone 2 (Sector II)	
0 to 116.8 ± 0.6 cm (0 to 46 ± 0.24 inches)	L_3_24	Moderator Tank Collapsed Liquid Level - Assembly 24 in Flow Zone 3 (Sector III)	
0 to 116.8 ± 0.6 cm (0 to 46 ± 0.24 inches)	L_4_50	Moderator Tank Collapsed Liquid Level - Assembly 50 in Flow Zone 4 (Sector IV)	
0 to 116.8 ± 0.6 cm (0 to 46 ± 0.24 inches)	L_5_84	Moderator Tank Collapsed Liquid Level - Assembly 84 in Flow Zone 5 (Sector V)	
0 to 116.8 ± 0.6 cm (0 to 46 ± 0.24 inches)	L_5_96	Moderator Tank Collapsed Liquid Level - Assembly 96 in Flow Zone 5 (Sector V)	
0 to 116.8 ± 0.6 cm (0 to 46 ± 0.24 inches)	L_5_99	Moderator Tank Collapsed Liquid Level - Assembly 99 in Flow Zone 5 (Sector V)	
0 to 3113.8 ± 4.4 N (0 to 700 ± 1.0 lbf)	F_TK_1	Moderator Tank Weight at Apex	
0 to 3113.8 ± 4.4 N (0 to 700 ± 1.0 lbf)	F_TK_2	Moderator Tank Weight at Outside Corner	
0 to 3113.8 ± 4.4 N (0 to 700 ± 1.0 lbf)	F_TK_3	Moderator Tank Weight at Outside Corner	
0 to 137.9 ± 0.17 kPa (0 to 20 ± 0.02 psia)	P_TK_TOP	Moderator Tank Top Center Pressure	
0 to 151.7 ± 0.17 kPa (0 to 22 ± 0.02 psia)	P_TK_BOT	Moderator Tank Bottom Center Pressure	

Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem (Continued)

5. Moderator Tank Instrumentation (Continued)		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 11.4 ± 0.034 kPa (0 to 46 ± 0.14 inches)	DP_TKC_H	Moderator Tank Center - Bottom to Top Differential Pressure
0 to 5.0 ± 0.017 kPa (0 to 20 ± 0.07 inches)	DP_TKC_L	Moderator Tank Center - Bottom to 20 inch Elevation Differential Pressure
0 to 11.4 ± 0.034 kPa (0 to 46 ± 0.14 inches)	DP_TKO_H	Moderator Tank Outer Edge Region - Bottom to Top Differential Pressure
0 to 5.0 ± 0.06 kPa (0 to 20 ± 0.10 inches)	DP_TKO_L	Moderator Tank Outer Edge Region - Bottom to 20" Elevation Differential Pressure
0 to 0.069 ± 0.017 kPa (0 to 0.01 ± 0.0025 psid)	DP_TK_CO	Moderator Tank Bottom Center to Muff Inlet Differential Pressure
6. Muff Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 7.58 ± 0.017 kPa (0 to 1.1 ± 0.0025 psid)	DP_MUFF	Muff Inlet to Muff Outlet Nozzle Elbow Flange Differential Pressure
0 to 172.4 ± 0.17 kPa (0 to 25 ± 0.02 psia)	P_1	Muff Outlet Pressure
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_1	Muff Outlet Fluid Temperature
0 to 9.52 cm (0 to 3.75 inches)	L_MUFF_O	Muff Outlet Horizontal Segment Liquid Level

Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem (Continued)

7. Pump Suction Instrumentation			
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description	
0 to 8.9 ± 0.034 kPad (0 to 36 ± 0.14 inches)	DP_1_3	Differential Pressure from Muff Outlet Nozzle Elbow Flange to First Horizontal Elbow Flange	
0 to 3.45 ± 0.017 kPad (0 to 0.5 ± 0.0025 psid)	DP_3_4	Differential Pressure from First Horizontal Elbow Flange to Upstream of Valve Simulator	
0 to 3.45 ± 0.017 kPad (0 to 0.5 ± 0.0025 psid)	DP_4_6	Differential Pressure from Upstream of Valve Simulator to End of Horizontal Sections	
0 to 2.14 ± 0.017 kPad (0 to 8.63 ± 0.07 inches)	DP_6_7	Differential Pressure from End of Horizontal Sections to Pump Suction Inlet	
0 to 1.0	VOID_V_1	Void Fraction in First Vertical Section of Pump Suction Piping	
0 to 1.0	VOID_V_2	Void Fraction in First Vertical Section of Pump Suction Piping	
0 to 1.0	VOID_V_3	Void Fraction in First Vertical Section of Pump Suction Piping	
0 to 1.0	VOID_V_4	Void Fraction in First Vertical Section of Pump Suction Piping	
0 to 1.0	VOID_V_5	Void Fraction in First Vertical Section of Pump Suction Piping	
0 to 1.0	VOID_V_6	Void Fraction in First Vertical Section of Pump Suction Piping	

Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem (Continued)

7. Pump Suction Instrumentation (Continued)		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
273 to 373 $\pm$ 2.2 K (32 to 212 $\pm$ 4.0 °F)	TF_3	Fluid Temperature in First Vertical Section of Pump Suction Piping (near Densitometer)
0 to 1.0	VOID_H_1	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 1.0	VOID_H_2	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 1.0	VOID_H_3	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 1.0	VOID_H_4	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 1.0	VOID_H_5	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 1.0	VOID_H_6	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 14.60 cm (0 to 5.75 inches)	L_HORZ	Liquid Level in Second Horizontal Segment of Pump Suction Piping (Computed Parameter)

Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem (Continued)

7. Pump Suction Instrumentation (Continued)		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 172.4 $\pm$ 0.2 kPa (0 to 25 $\pm$ 0.03 psia)	P_7	Pressure in Second Vertical Segment of Pump Suction Piping (near Pump Suction Densitometer)
273 to 373 $\pm$ 2.2 K (32 to 212 $\pm$ 4.0 °F)	TF_7	Fluid Temperature in Second Vertical Segment of Pump Suction Piping (near Pump Suction Densitometer)
0 to 1.0	VOID_P_1	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_2	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_3	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_4	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_5	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_6	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 14.60 cm (0 to 5.75 inches)	L_PMP_S	Liquid Level in Second Vertical Segment of Pump Suction Piping (Computed Parameter)

**Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem
(Continued)**

8. Scaled Bingham Pump Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 517.1 ± 1.3 kPa (0 to 75 ± 0.2 psid)	DP_7_8H	High Range Differential Pressure Across Scaled Bingham Pump
0 to 74.65 ± 0.37 kPa (0 to 300 ± 1.5 inches)	DP_7_8L	Low Range Differential Pressure Across Scaled Bingham Pump
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_SI	Scaled Bingham Pump - Suction Inboard Pressure
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_SO	Scaled Bingham Pump - Suction Outboard Pressure
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_VI	Scaled Bingham Pump - Volute Inner Path Pressure
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_VO	Scaled Bingham Pump - Volute Outer Path Pressure
0 to 785.4 radians/s (0 to 7500 rpm) [± 1% of reading]	S_PUMP	Scaled Bingham Pump Shaft Speed
0.2 to 226 ± 0.3 N-m (0.2 to 167 ± 0.25 ft-lbf)	T_PUMP	Scaled Bingham Pump Shaft Torque
0 to 177.5 kW (0 to 238.0 hp) [± 1% of computed value based on S_PUMP and T_PUMP accuracies]	W_PUMP	Scaled Bingham Pump Shaft Work (Computed Parameter)
0 to 200 ± ### amps	I_PMP_M	Scaled Bingham Pump Motor Current
0 to 500 ± ### volts	V_PMP_M	Scaled Bingham Pump Motor Voltage
0 to 173.2 ± ## kW (0 to 232.3 ± ## hp) [accuracy based on I_PMP and V_PMP accuracies]	W_PMP_M	Scaled Bingham Pump Motor Power (Computed Parameter)
.019 to 18.9 LPM (0.005 to 5 gpm)	Q_W_BR	Scaled Bingham Pump Bearings Cooling Water Volumetric Flow Rate
.019 to 18.9 LPM (0.005 to 5 gpm)	Q_W_SEAL	Scaled Bingham Pump Seal Water Volumetric Flow Rate

Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem (Continued)

9. Pump Discharge Instrumentation			
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description	
0 to 689.5 ± 0.7 kPa (0 to 100 ± 0.1 psia)	P_8	Pressure in First Vertical Segment of Pump Discharge Piping (near Pump Discharge Densitometer)	
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_8	Fluid Temperature in First Vertical Segment of Pump Discharge Piping (near Pump Discharge Densitometer)	
0 to 1.0	VOID_D_1	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	
0 to 1.0	VOID_D_2	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	
0 to 1.0	VOID_D_3	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	
0 to 1.0	VOID_D_4	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	
0 to 1.0	VOID_D_5	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	
0 to 1.0	VOID_D_6	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	

Table 7. SET Tank/Muff/Pump Short Discharge (Mod-TMPD) Experiment Instrumentation Grouped by Subsystem (Continued)

10. Storage Tank Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 9.7 ± 0.06 kPa (0 to 39 ± 0.25 inches)	DP_STR	Storage Tank Top to Bottom Differential Pressure
0 to 99.1 cm (0 to 39 inches)	L_STR	Storage Tank Liquid Level (Computed from DP_STR)
273 to 373 K (32 to 212 °F)	TF_W_STR	Storage Tank Fluid Temperature
0 to 283.9 LPM (0 to 75 gpm)	Q_W_CC	Storage Tank Cooling Coil Water Volumetric Flow Rate
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_CC_IN	Storage Tank Cooling Coil Water Inlet Fluid Temperature
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_CC_OU	Storage Tank Cooling Coil Water Outlet Fluid Temperature
11. Supply Pump Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 689.5 ± 1.7 kPa (0 to 100 ± 0.25 psid)	DP_SP	Differential Pressure Across Supply Pump
0 to 172.4 ± 0.2 kPa (0 to 25 ± 0.03 psia)	P_SP_IN	Supply Pump Inlet Pressure
0 to 500 ± 0.517 kPa (0 to 60 ± 0.075 psig)	P_SP_OUT	Supply Pump Discharge Pressure
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_SP_OU	Supply Pump Discharge Fluid Temperature

Table 8. SET Tank Bypass Short Discharge (Mod-TBSD) Experiment Instrumentation Grouped by Subsystem

1. Building Atmosphere Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 103.4 $\pm$ 0.108 kPa (0 to 15 $\pm$ 0.016 psia)	P_ATM	Building Atmosphere Pressure
273 to 373 $\pm$ 0.2 K (32 to 212 $\pm$ 0.4 °F)	TF_ATM	Building Atmosphere Temperature
5 to 100 % ($\pm$ 3% of reading)	RH_ATM	Building Atmosphere Relative Humidity
2. Air Injection Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
273 to 373 $\pm$ 0.2 K (32 to 212 $\pm$ 0.4 °F)	TF_A_IN	Air Temperature for Air Injected into Loop
237.9 to 430.9 $\pm$ 0.5 kPa (22 to 50 $\pm$ 0.08 psig)	P_A_IN	Air Pressure for Air Injected into Loop
150 to 1500 $\pm$ 15 SLPM (39.6 to 396 $\pm$ 4 gpm) [Expected to read reliably up to 25 to 30% beyond the stated range]	Q_A_BT_H	Loop Main Air Injection Train High Range Volumetric Flow
52 to 300 $\pm$ 3 SLPM (13.7 to 79.2 $\pm$ 0.8 gpm)	Q_A_BT_L	Loop Main Air Injection Train Low Range Volumetric Flow
150 to 1500 $\pm$ 15 SLPM (39.6 to 396 $\pm$ 4 gpm) [Expected to read reliably up to 25 to 30% beyond the stated range]	Q_A_AX_H	Loop Auxiliary Air Injection Train High Range Volumetric Flow

**Table 8. SET Tank Bypass Short Discharge (Mod-TBSD) Experiment Instrumentation Grouped by Subsystem
(Continued)**

3. Liquid Injection Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
568 to 4542 ± (5.7 + 0.50% of reading) LPM [150 to 1200 ± (1.5 + 0.50% of reading) gpm]	Q_W_BT_H	Loop Liquid Injection Train High Range Volumetric Flow
178 to 1893 ± (1.9 + 0.50% of reading) LPM [47 to 500 ± (0.5 + 0.50% of reading) gpm]	Q_W_BT_L	Loop Liquid Injection Train Low Range Volumetric Flow
4. Pump Suction Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 2.14 ± 0.017 kPad (0 to 8.63 ± 0.07 inches)	DP_6_7	Differential Pressure from End of Horizontal Sections to Pump Suction Inlet
0 to 1.0	VOID_H_1	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 1.0	VOID_H_2	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 1.0	VOID_H_3	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 1.0	VOID_H_4	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 1.0	VOID_H_5	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 1.0	VOID_H_6	Void Fraction in Second Horizontal Segment of Pump Suction Piping
0 to 14.60 cm (0 to 5.75 inches)	L_HORZ	Liquid Level in Second Horizontal Segment of Pump Suction Piping (Computed Parameter)

Table 8. SET Tank Bypass Short Discharge (Mod-TBSD) Experiment Instrumentation Grouped by Subsystem (Continued)

4. Pump Suction Instrumentation (Continued)		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 689.5 $\pm$ 0.7 kPa (0 to 100.0 $\pm$ 0.1 psia)	P_7	Pressure in Second Vertical Segment of Pump Suction Piping (near Pump Suction Denisometer)
273 to 373 $\pm$ 2.2 K (32 to 212 $\pm$ 4.0 °F)	TF_7	Fluid Temperature in Second Vertical Section of Pump Suction Piping (near Pump Suction Denisometer)
0 to 1.0	VOID_P_1	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_2	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_3	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_4	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_5	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_6	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 14.60 cm (0 to 5.75 inches)	L_PMP_S	Liquid Level in Second Vertical Segment of Pump Suction Piping (Computed Parameter)

**Table 8. SET Tank Bypass Short Discharge (Mod-TBSD) Experiment Instrumentation Grouped by Subsystem
(Continued)**

5. Scaled Bingham Pump Instrumentation			
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description	
$\pm 517.1 \pm 1.3$ kPad ($\pm 75 \pm 0.2$ psid)	DP_7_8H	High Range Differential Pressure Across Scaled Bingham Pump	
$\pm 74.65 \pm 0.37$ kPad ($\pm 300 \pm 1.5$ inches)	DP_7_8L	Low Range Differential Pressure Across Scaled Bingham Pump	
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_SI	Scaled Bingham Pump - Suction Inboard Pressure	
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_SO	Scaled Bingham Pump - Suction Outboard Pressure	
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_VI	Scaled Bingham Pump - Volute Inner Path Pressure	
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_VO	Scaled Bingham Pump - Volute Outer Path Pressure	
0 to 785.4 radians/s (0 to 7500 rpm) [$\pm 1\%$ of reading]	S_PUMP	Scaled Bingham Pump Shaft Speed	
0.2 to 226 ± 0.3 N-m (0.2 to 167 ± 0.25 ft-lbf)	T_PUMP	Scaled Bingham Pump Shaft Torque	
0 to 177.5 kW (0 to 238.0 hp) [$\pm 1\%$ of computed value based on S_PUMP and T_PUMP accuracies]	W_PUMP	Scaled Bingham Pump Shaft Work (Computed Parameter)	
0 to $200 \pm \#\#$ amps	I_PMP_M	Scaled Bingham Pump Motor Current	
0 to $500 \pm \#\#$ volts	V_PMP_M	Scaled Bingham Pump Motor Voltage	
0 to $173.2 \pm \#\#$ kW (0 to $232.3 \pm \#\#$ hp) [accuracy based on I_PMP and V_PMP accuracies]	W_PMP_M	Scaled Bingham Pump Motor Power (Computed Parameter)	
.019 to 18.9 LPM (0.005 to 5 gpm)	Q_W_BR	Scaled Bingham Pump Bearings Cooling Water Volumetric Flow Rate	
.019 to 18.9 LPM (0.005 to 5 gpm)	Q_W_SEAL	Scaled Bingham Pump Seal Water Volumetric Flow Rate	

Table 8. SET Tank Bypass Short Discharge (Mod-TBSD) Experiment Instrumentation Grouped by Subsystem (Continued)

6. Pump Discharge Instrumentation			
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description	
0 to 689.5 ± 0.7 kPa (0 to 100 ± 0.1 psia)	P_8	Pressure in First Vertical Segment of Pump Discharge Piping (near Pump Discharge Denzitometer)	
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_8	Fluid Temperature in First Vertical Segment of Pump Discharge Piping (near Pump Discharge Denzitometer)	
0 to 1.0	VOID_D_1	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	
0 to 1.0	VOID_D_2	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	
0 to 1.0	VOID_D_3	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	
0 to 1.0	VOID_D_4	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	
0 to 1.0	VOID_D_5	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	
0 to 1.0	VOID_D_6	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)	

**Table 8. SET Tank Bypass Short Discharge (Mod-TBSD) Experiment Instrumentation Grouped by Subsystem
(Continued)**

7. Storage Tank Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 9.7 ± 0.06 kPad (0 to 39 ± 0.25 inches)	DP_STR	Storage Tank Top to Bottom Differential Pressure
0 to 99.1 cm (0 to 39 inches)	L_STR	Storage Tank Liquid Level (Computed from DP_STR)
273 to 373 K (32 to 212 °F)	TF_W_STR	Storage Tank Fluid Temperature
0 to 283.9 LPM (0 to 75 gpm)	Q_W_CC	Storage Tank Cooling Coil Water Volumetric Flow Rate
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_CC_IN	Storage Tank Cooling Coil Water Inlet Fluid Temperature
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_CC_OU	Storage Tank Cooling Coil Water Outlet Fluid Temperature
8. Supply Pump Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 689.5 ± 1.7 kPad (0 to 100 ± 0.25 psid)	DP_SP	Differential Pressure Across Supply Pump
0 to 172.4 ± 0.2 kPa (0 to 25 ± 0.03 psia)	P_SP_IN	Supply Pump Inlet Pressure
0 to 689.5 ± 0.7 kPa (0 to 100 ± 0.1 psia)	P_SP_OUT	Supply Pump Discharge Pressure
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_SP_OU	Supply Pump Discharge Fluid Temperature

Table 9. SET Bingham Pump Reverse Flow (Mod-BPRF) Experiment Instrumentation Grouped by Subsystem

1. Building Atmosphere Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 103.4 ± 0.108 kPa (0 to 15 ± 0.016 psia)	P_ATM	Building Atmosphere Pressure
273 to 373 ± 0.2 K (32 to 212 ± 0.4 °F)	TF_ATM	Building Atmosphere Temperature
5 to 100 % (± 3% of reading)	RH_ATM	Building Atmosphere Relative Humidity
2. Air Injection Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
273 to 373 ± 0.2 K (32 to 212 ± 0.4 °F)	TF_A_IN	Air Temperature for Air Injected into Loop
237.9 to 430.9 ± 0.5 kPa (22 to 50 ± 0.08 psig)	P_A_IN	Air Pressure for Air Injected into Loop
150 to 1500 ± 15 SLPM (39.6 to 396 ± 4 gpm) [Expected to read reliably up to 25 to 30% beyond the stated range]	Q_A_BT_H	Loop Main Air Injection Train High Range Volumetric Flow
52 to 300 ± 3 SLPM (13.7 to 79.2 ± 0.8 gpm)	Q_A_BT_L	Loop Main Air Injection Train Low Range Volumetric Flow
150 to 1500 ± 15 SLPM (39.6 to 396 ± 4 gpm) [Expected to read reliably up to 25 to 30% beyond the stated range]	Q_A_AX_H	Loop Auxiliary Air Injection Train High Range Volumetric Flow

**Table 9. SET Bingham Pump Reverse Flow (Mod-BPRF) Experiment Instrumentation Grouped by Subsystem
(Continued)**

3. Liquid Injection Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
568 to 4542 $\pm$ (5.7 + 0.50% of reading) LPM [150 to 1200 $\pm$ (1.5 + 0.50% of reading) gpm]	Q_W_BT_H	Loop Liquid Injection Train High Range Volumetric Flow
178 to 1893 $\pm$ (1.9 + 0.50% of reading) LPM [47 to 500 $\pm$ (0.5 + 0.50% of reading) gpm]	Q_W_BT_L	Loop Liquid Injection Train Low Range Volumetric Flow
4. Pump Suction Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 689.5 $\pm$ 0.7 kPa (0 to 100.0 $\pm$ 0.1 psia)	P_7	Pressure in Second Vertical Segment of Pump Suction Piping (near Pump Suction Densitometer)
273 to 373 $\pm$ 2.2 K (32 to 212 $\pm$ 4.0 $^{\circ}$ F)	TF_7	Fluid Temperature in Second Vertical Section of Pump Suction Piping (near Pump Suction Densitometer)
0 to 1.0	VOID_P_1	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_2	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_3	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_4	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_5	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)
0 to 1.0	VOID_P_6	Void Fraction in Second Vertical Segment of Pump Suction Piping (near Pump Suction Flange)

**Table 9. SET Bingham Pump Reverse Flow (Mod-BPRF) Experiment Instrumentation Grouped by Subsystem
(Continued)**

5. Scaled Bingham Pump Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
$\pm 517.1 \pm 1.3$ kPa ($\pm 75 \pm 0.2$ psid)	DP_7_8H	High Range Differential Pressure Across Scaled Bingham Pump
$\pm 74.65 \pm 0.37$ kPa ($\pm 300 \pm 1.5$ inches)	DP_7_8L	Low Range Differential Pressure Across Scaled Bingham Pump
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_SI	Scaled Bingham Pump - Suction Inboard Pressure
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_SO	Scaled Bingham Pump - Suction Outboard Pressure
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_VI	Scaled Bingham Pump - Volute Inner Path Pressure
0 to 689.5 ± 0.7 kPa (0 to 100.0 ± 0.1 psia)	P_PMP_VO	Scaled Bingham Pump - Volute Outer Path Pressure
0 to 785.4 radians/s (0 to 7500 rpm) [$\pm 1\%$ of reading]	S_PUMP	Scaled Bingham Pump Shaft Speed
0.2 to 226 ± 0.3 N-m (0.2 to 167 ± 0.25 ft-lbf)	T_PUMP	Scaled Bingham Pump Shaft Torque
0 to 177.5 kW (0 to 238.0 hp) [$\pm 1\%$ of computed value based on S_PUMP and T_PUMP accuracies]	W_PUMP	Scaled Bingham Pump Shaft Work (Computed Parameter)
0 to $200 \pm \#\#\%$ amps	I_PMP_M	Scaled Bingham Pump Motor Current
0 to $500 \pm \#\#\%$ volts	V_PMP_M	Scaled Bingham Pump Motor Voltage
0 to $173.2 \pm \#\%$ kW (0 to $232.3 \pm \#\%$ hp) [accuracy based on I_PMP and V_PMP accuracies]	W_PMP_M	Scaled Bingham Pump Motor Power (Computed Parameter)
.019 to 18.9 LPM (0.005 to 5 gpm)	Q_W_BR	Scaled Bingham Pump Bearings Cooling Water Volumetric Flow Rate
.019 to 18.9 LPM (0.005 to 5 gpm)	Q_W_SEAL	Scaled Bingham Pump Seal Water Volumetric Flow Rate

**Table 9. SET Bingham Pump Reverse Flow (Mod-BPRF) Experiment Instrumentation Grouped by Subsystem
(Continued)**

6. Pump Discharge Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 689.5 $\pm$ 0.7 kPa (0 to 100 $\pm$ 0.1 psia)	P_8	Pressure in First Vertical Segment of Pump Discharge Piping (near Pump Discharge Densitometer)
273 to 373 $\pm$ 2.2 K (32 to 212 $\pm$ 4.0 °F)	TF_8	Fluid Temperature in First Vertical Segment of Pump Discharge Piping (near Pump Discharge Densitometer)
0 to 1.0	VOID_D_1	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)
0 to 1.0	VOID_D_2	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)
0 to 1.0	VOID_D_3	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)
0 to 1.0	VOID_D_4	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)
0 to 1.0	VOID_D_5	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)
0 to 1.0	VOID_D_6	Void Fraction in First Vertical Section of Pump Discharge Piping (near Pump Discharge Flange)

Table 9. SET Bingham Pump Reverse Flow (Mod-BPRF) Experiment Instrumentation Grouped by Subsystem
(Continued)

7. Storage Tank Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 9.7 ± 0.06 kPa (0 to 39 ± 0.25 inches)	DP_STR	Storage Tank Top to Bottom Differential Pressure
0 to 99.1 cm (0 to 39 inches)	L_STR	Storage Tank Liquid Level (Computed from DP_STR)
273 to 373 K (32 to 212 °F)	TF_W_STR	Storage Tank Fluid Temperature
0 to 283.9 LPM (0 to 75 gpm)	Q_W_CC	Storage Tank Cooling Coil Water Volumetric Flow Rate
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_CC_IN	Storage Tank Cooling Coil Water Inlet Fluid Temperature
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_CC_OU	Storage Tank Cooling Coil Water Outlet Fluid Temperature
8. Supply Pump Instrumentation		
Measurement Range and Manufacturer Specified Accuracy	DAS Tag Identification	Description
0 to 689.5 ± 1.7 kPa (0 to 100 ± 0.25 psid)	DP_SP	Differential Pressure Across Supply Pump
0 to 172.4 ± 0.2 kPa (0 to 25 ± 0.03 psia)	P_SP_IN	Supply Pump Inlet Pressure
0 to 689.5 ± 0.7 kPa (0 to 100 ± 0.1 psia)	P_SP_OUT	Supply Pump Discharge Pressure
273 to 373 ± 2.2 K (32 to 212 ± 4.0 °F)	TF_SP_OU	Supply Pump Discharge Fluid Temperature

data report for the tests. The manufacturer specified accuracies have only been included to give an indication of the best potential measurement uncertainty. In most instances the actual measurement uncertainty will be on the order of 2 to 3 times greater than the manufacturer specified accuracy. Although the DAS tag identification shown for void fraction measurements is "VOID_#_#", the actual measured parameter is the densitometer beam detector count rate from which the void fraction is computed. Hence, the actual DAS tag identification for void fraction measurements is "CNT_#_#" which has units of counts/second while the actual void fraction is a computed parameter designated by "VOID_#_#".

The SET test loop is intended to provide flow visualization information in conjunction with the standard data acquisition activities. Provisions for recording flow visualization are provided by several means. Several process video cameras are available for observing and recording general flow phenomena in the test loop and liquid storage tank. Several high speed video cameras are also available for observing and recording high speed images of flow phenomena in the test loop. Finally, a variable shutter speed camera is also available for capturing still images of flow phenomena.

3.4 Measured or Computed Parameter Requirements

Those parameters (measured or computed) essential to satisfying the test objectives specified in References 1 through 4 have been identified as critical parameters. The critical parameters for single-phase Bingham pump tests are shown on Table 10 while those for two-phase Bingham pump tests are shown on Table 11. As noted in the tables, a number of the parameters may be obtained by several methods. Tests should not be performed without at least one method of obtaining the critical parameters. If the primary critical parameter is unavailable for a test, a redundant critical parameter may be substituted and testing continued provided that both cognizant EG&G and WSRC personnel agree that the redundant critical parameter provides sufficient accuracy. If cognizant WSRC personnel are not available for consultation, testing can be continued and data will be reviewed to assess the potential need to re-perform the test.

The possible methods of obtaining critical parameters are shown on Table 12. The primary method of obtaining critical parameters will vary between tests depending upon the nature of the test.

Table 10. Critical Parameters for SET-TMP-PT Single-Phase Bingham Pump Tests Grouped by Subsystem

- I. Pump Suction Liquid Injection Parameters:
 - 1. Temperature of injected water.
 - 2. Total volumetric flow rate of injected water.
 - II. Pump Suction Piping Parameters:
 - 1. Absolute pressure.
 - III. Scaled Bingham Pump Parameters:
 - 1. Pump suction inboard and outboard pressures.
 - 2. Pump volute inner and outer path pressures.
 - 3. Pressure drop across pump.
 - 4. Pump shaft speed.
 - 5. Pump shaft torque.
 - 6. Pump shaft work.
 - 7. Pump motor current.
 - 8. Pump motor power.
 - IV. Pump Discharge Piping Parameters:
 - 1. Absolute pressure.
-

Note: Parameters may be either computed or directly measured. A number of the parameters may be obtained by several methods. Tests should not be performed without at least one method of obtaining the critical parameters.

Table 11. Critical Parameters for SET-TMP-PT Two-Phase Bingham Pump Tests Grouped by Subsystem

I. Pump Liquid and Air Injection Parameters:

(Pump suction for forward flow, pump discharge for reverse flow)

1. Temperature of injected liquid.
2. Total volumetric flow rate of injected liquid.
3. Density of injected air.
4. Mass flow rate of injected air.

II. Pump Suction Piping Parameters:

1. Absolute pressure.
2. Fluid temperature.
3. Pressure drop across last 90° elbow and last vertical section - (Only for forward flow).
4. Void fraction in last horizontal section of pipe - (Only for forward flow).
5. Void fraction in last vertical section of pipe (vertical section connected to pump).

III. Scaled Bingham Pump Parameters:

1. Pump suction inboard and outboard pressures.
2. Pump volute inner and outer path pressures.
3. Pressure drop across pump.
4. Pump shaft speed.
5. Pump shaft torque.
6. Pump shaft work.
7. Pump motor current.
8. Pump motor power.

IV. Pump Discharge Piping Parameters:

1. Absolute pressure.
2. Fluid temperature.
3. Void fraction in first vertical section pipe (vertical section connected to pump).

Note: Parameters may be either computed or directly measured. A number of the parameters may be obtained by several methods. Tests should not be performed without at least one method of obtaining the critical parameters.

Table 12. Possible Methods of Obtaining Critical Parameters			
Critical Parameter	Primary Method	Alternate Method 1	Alternate Method 2
Pump suction injected air mass flowrate	Q_A_BT_F or L		
Pump suction injected water temperature	TF_SP_OU	TF_7 or TF_8	TF_8 or TF_7
Pump suction injected water volumetric flowrate	Q_W_BT_H or L		
Pump suction air injection volumetric flow rate	Q_A_BT_H or L, Q_A_AX_H, P_7 and TF_7		
Pump suction absolute pressure	P_7	P_8 and DP_7_8H or L	
Pump suction fluid temperature	TF_7		
Pump suction last 90° elbow and last vertical section ΔP	DP_6_7		
Pump suction horizontal section void fraction	VOID_H_1 through 6		
Pump suction vertical section void fraction	VOID_P_1 through 6	DP_6_7, P_7 and TF_7	

Table 12. Possible Methods of Obtaining Critical Parameters (Continued)			
Critical Parameter	Primary Method	Alternate Method 1	Alternate Method 2
Pump suction inboard and outboard pressures	P_PMP_SI and P_PMP_SO		
Pump volute inner and outer path pressures	P_PMP_VI and P_PMP_VO		
Pump ΔP	DP_7_8H or L	P_7 and P_8	P_PMP_SI or P_PMP_SO and P_PMP_VI or P_PMP_VO
Pump shaft speed	S_PUMP		
Pump shaft torque	T_PUMP		
Pump shaft work	W_PUMP		
Pump motor current	I_PMP_M		
Pump motor power	W_PMP_M		
Pump discharge absolute pressure	P_8	P_7 and DP_7_8H or L	
Pump discharge fluid temperature	TF_8		
Pump discharge vertical section void fraction	VOID_D_1 through 6		

3.5 Experiment Termination Criteria

Experiment termination prior to completion of test objectives may be necessary under abnormal conditions. The test will be terminated under unusual, emergency or safety-related conditions. Otherwise, the experiments can be stopped when the conditions specified in the test matrix table have been satisfied.

3.6 Post Testing Operational Checks

Following completion of daily testing activities, the operations listed in Table 13 should be performed. These operations will provide valuable information for posttest analysis and system operability considerations.

Table 13. Post-Testing Operational Checks	
1. Status	Test day testing has been completed.
2. Perform post testing operational checks and take post testing data.	<ol style="list-style-type: none">1. Prepare the data acquisition system as necessary to obtain the post testing data.2. Fill the test loop. Obtain liquid level and densitometer data.3. Drain and vent the test loop. Obtain liquid level and densitometer data.4. Inspect the facility for and record all leakage points or unusual configuration/operation conditions.
3. Secure the facility	<ol style="list-style-type: none">1. Secure the fluid systems.2. Start or continue data processing operations.

3.7 Experiment Acceptance Criteria

After completion of the experiment, an evaluation will be performed to determine the acceptability of the experiment based on satisfaction of objectives. The following criteria will be applied to determine if all of the experiment objectives were met:

1. Initial values and parameters critical to meeting experimental objectives are within the tolerances specified.
2. Proper performance of experimental instrumentation and recording of data to insure that the experimental results can be analyzed and the experiment objectives met.

4. REFERENCES

1. J. S. Bollinger and J. D. Sterrett ltr. to C. A. Nash, *Phase 3 Tank/Muff/Pump (TMP) 1/4-Scale Formal Bingham Pump Test Matrix*, Savannah River Site, NES-CDG-930006, January 18, 1993.
2. J. S. Bollinger ltr. to C. A. Nash, *Summary of Phase 3 Pump Testing at the 1/4-Scale Separate Effects Test Facility (SET) and Description of Additional Characterization Tests*, Savannah River Site, NES-CDG-930053, March 10, 1993.
3. J. S. Bollinger ltr. to C. A. Nash, *Tank/Muff/Pump (TMP) Integral Single-Phase Pump Test Matrix*, Savannah River Site, NES-CDG-920181, October 9, 1992.
4. J. S. Bollinger ltr. to C. A. Nash, *Pump Discharge Break Studies - Second Tank/Muff/Pump (TMP) Testing Phase*, Savannah River Site, NES-CDG-920241, Rev. 1, January 15, 1992.
5. T. J. Boucher and J. S. Bollinger, "Appendix SC-TMPS-IT of the Experiment Operating Specification for the Savannah River One-Fourth Linear Scale, One-Sixth Sector Tank/Muff/Pump (TMP) Separate Effects Tests (SET) Experiment Series," EGG-NE-10379, WSRC-TR-92-383, Revision 0, September 1992.
6. T. J. Boucher and T. K. Larson, "Quick Look Report for Phase II of the Savannah River One-Fourth Linear Scale, One-Sixth Sector Tank/Muff/Pump (TMP) Separate Effects Tests (SET) Experiment Series," EGG-NRE-10721, Revision 0, March 1993.
7. A. J. Stepanof., *Centrifugal and Axial Flow Pumps*, Second Edition, John Wiley & Sons, Inc., 1957.
8. R. W. Winks, *One-Third-Scale Air-Water Pump Program, Test Program and Pump Performance*, EPRI NP-135, Electric Power Research Institute, Palo Alto, CA, July, 1977.
9. W. G. Kennedy, et. al., *Pump Two-Phase Performance Program, Volume 2: Steady-State Tests*, NP-1556, Volume 2, Electric Power Research Institute, Palo Alto, CA, September, 1980.
10. P. S. Karmath and W. L. Smith, *Two-Phase Performance of Scale Models of a Primary Coolant Pump*, EPRI NP-2578, Electric Power Research Institute, Palo Alto, CA, September, 1982.
11. J. S. Bollinger and T. J. Boucher, "Experiment Operating Specification for the Savannah River One-Fourth Linear Scale, One-Sixth Sector Tank/Muff/Pump (TMP) Separate Effects Tests (SET) Experiment Series," WSRC-TR-92-91, Revision 0, February 1992.

Appendix A

General Guidance for SET 1/4 Linear Scale Bingham Pump Single-Phase and Two-Phase, Two-Component Complete Characterization Tests

The performance of a pump can be characterized in several manners. As described in Stepanoff[7], complete pump characteristics can be presented by constant head and torque contours as a function of normalized speed and normalized flow (Figure A-1). As shown on the figure, compilation of pump characteristics in this manner allows for clear definition of operating conditions based on the zero head and zero torque lines as well as the direction of pump rotation and pump flow (the four axes). Using these lines, Stepanoff defined eight different zones of pump operation designated by the letters A thru H (Figure A-1). These eight zones may be described as follows:

- Zone A - Forward rotation, forward flow, normal pump (positive head and torque)
- Zone B - Forward rotation, reverse flow, energy dissipation (positive head and torque)
- Zone C - Reverse rotation, reverse flow, normal turbine (positive head and torque)
- Zone D - Reverse rotation, reverse flow, energy dissipation (positive head and negative torque)
- Zone E - Reverse rotation, forward flow, reverse rotation pump (positive head and negative torque)
- Zone F - Reverse rotation, forward flow, energy dissipation (negative head and negative torque)
- Zone G - Forward rotation, forward flow, reverse flow turbine (negative head and negative torque)
- Zone H - Forward rotation, forward flow, energy dissipation (negative head and positive torque)

Complete characterization of the 1/4 linear scale Bingham pump will therefore require testing for all eight of these operating zones.

Another widely accepted method of presenting complete pump characterization curves is based upon pump affinity laws which collapse the constant normalized head (h) and torque (β) versus normalized speed (α) and normalized flow (v) contours of Figure A-1 down to two sets of eight curves (one set for the head and one set for the torque). This is accomplished using homologous parameters which further normalize the head (h) and torque (β) by dividing by α^2 or v^2 and plotting against v/α or α/v . Figure A-2 shows the relationship between the Stepanoff curve (Figure A-1) zones and the homologous normalizing parameters for the pump characteristic curves while Figures A-3 and A-4 show the relationships between the Stepanoff curve (Figure A-1) zones and the pump homologous head and homologous torque parameters. As shown on the figures, the criteria for selection of the normalizing parameter (α or v) is as

Figure A-1. Complete Pump Characteristics for a Typical Double-Suction Centrifugal Pump as Reported by A. J. Stepanoff.

Key to labels HAN, HVN, BAN, BVN, etc. on homologous head and torque curves:

- H -> Head function (function with h in the numerator)
- B -> Hydraulic torque function (function with β in the numerator)
- A -> Function with α in denominator
- V -> Function with v in denominator, used when $|v/\alpha| > 1$
- N -> Normal pumping quadrant with forward flow and speed
- D -> Dissipation quadrant with reverse flow and forward speed
- T -> Normal turbine quadrant with reverse flow and speed
- R -> Reverse pumping quadrant with forward flow and reverse speed

where:

- $h = \text{pump total dynamic head} / \text{rated pump total dynamic head} = \text{TDH} / \text{TDH}_{\text{Rated}}$
- $\beta = \text{pump hydraulic torque} / \text{rated pump hydraulic torque} = T / T_{\text{Rated}}$
- $\alpha = \text{pump speed} / \text{rated pump speed} = \omega / \omega_{\text{Rated}}$
- $v = \text{pump volumetric flow} / \text{rated pump volumetric flow} = Q / Q_{\text{Rated}}$

Examples:

- HAN -> h/α^2 vs. v/α for forward flow and speed
- BVD -> β/v^2 vs. α/v for reverse flow and forward speed

Figure A-2. Example Pump Characteristic Curves Showing Relationship Between Homologous Parameters and Stepanoff Curve (Figure A-1) Zones.

Key to labels HVN-A, HVN-H, HVN-G, etc. on homologous head curves:

The nomenclature for the homologous head regions on this figure is:

Homologous head parameter region-Stepanoff curve zone

For example, HVN-A signifies either a portion or all of the homologous head HVN curve and either a portion or all of the Stepanoff curve zone A.

Hence, the entire homologous head HVN curve is represented by the curves HVN-A, HVN-H and HVN-G while on the Stepanoff curve the homologous head HVN curve would represent a portion of zone A and all of zones H and G.

Figure A-3. Example Pump Homologous Head Curves Showing Relationship Between Homologous Head Parameters and Stepanoff Curve (Figure A-1) Zones.

Key to labels BVN-A, BVN-H, BVN-G, etc. on homologous torque curves:

The nomenclature for the homologous torque regions on this figure is:

Homologous torque parameter region-Stepanoff curve zone

For example, BVN-A signifies either a portion or all of the homologous torque BVN curve and either a portion or all of the Stepanoff curve zone A.

Hence, the entire homologous torque BVN curve is represented by the curves BVN-A, BVN-H and BVN-G while on the Stepanoff curve the homologous torque BVN curve would represent a portion of zone A and all of zones H and G.

Figure A-4. Example Pump Homologous Torque Curves Showing Relationship Between Homologous Torque Parameters and Stepanoff Curve (Figure A-1) Zones.

follows: for flow-to-speed ratio absolute values $(|v/\alpha|) \leq 1$, the speed ratio squared (α^2) is used as the normalizing parameter and the flow-to-speed ratio (v/α) is used as the abscissa; for flow-to-speed ratio absolute values $(|v/\alpha|) > 1$, the flow ratio squared (v^2) is used as the normalizing parameter and the speed-to-flow ratio (α/v) is used as the abscissa. Using this technique, the points on the Stepanoff curve (Figure A-1) which represent the intersection of the head (h) and torque (β) contours and a line of constant v/α or α/v become single points on the homologous head and torque curves, respectively. Thus, the homologous head and torque curves provide a much simpler method of representing the complete pump characteristics and predicting single-phase pump performance.

Further understanding of the relationship between the Stepanoff curve (Figure A-1) zones and the pump homologous curve regions may be gained by examining Table A-1 which provides an explanation of the Stepanoff curve zones in terms of the normalized pump homologous parameters. The overlap of the homologous curves and the Stepanoff curve zones shown in Figures A-2 thru A-4 are also evident in the table.

Fig. A-1 Zone	Speed Ratio α	Flow Ratio v	Head Ratio h	Torque Ratio β	α/v or v/α	h/α^2 or h/v^2	β/α^2 or β/v^2	Charac. Curves (α vs. v) Quadrant	Homol. Head Curve Regions	Homol. Torque Curve Regions
A	+	+	+	+	+	+	+	I	HAN HVN	BAN BVN
B	+	-	+	+	-	+	+	II	HAD HVD	BAD BVD
C	-	-	+	+	+	+	+	III	HVT HAT	BVT BAT
D	-	-	+	-	+	+	-	III	HAT	BAT
E	-	+	+	-	-	+	-	IV	HAR	BAR
F	-	+	-	-	-	-	-	IV	HAR HVR	BAR BVR
G	+	+	-	-	+	-	-	I	HVN	BVN
H	+	+	-	+	+	-	+	I	HVN	BVN

Previous works on two-phase pump characterization [8 thru 11] have presented and/or correlated results using the pump homologous head and torque curves. The above discussion has shown the direct relationship between these homologous curves and the Stepanoff curves for single-phase conditions. However, for two-phase conditions other variables such as pump void fraction or volumetric flow quality may prevent the Stepanoff curves from collapsing to the homologous head and torque curves as neatly as for single-phase conditions. Hence, it would

seem prudent to outline a testing scheme which establishes the two-phase head and torque conditions on pump characteristic curves (similar to the Stepanoff curve) with the emphasis on constant flow-to-speed ratio (v/α) or constant speed-to-flow ratio (α/v) lines. This should allow for evaluation of the appropriateness of collapsing the two-phase curves in a manner similar to the single-phase curves.

The objective for the Phase III pump characterization tests is to provide complete characterization of the 1/4 linear scale Bingham pump for two-phase, two-component conditions in all four pump characteristic curve quadrants. The existing data base on pump two-phase performance is not adequate to allow for apriori determination of sensitivities to the various boundary conditions (flow-to-speed or speed-to-flow ratios, pump speeds, pump inlet pressures, and void fractions or volumetric flow qualities). Hence, the skeleton test matrix shown in Figure A-5 has been developed for these tests. It is intended to provide general guidance on the range of flow-to-speed or speed-to-flow ratios and pump speeds to be examined for the four pump characteristic curve quadrants.

Figure A-5. Skeleton Test Matrix for the Four Pump Characteristic Curve Quadrants.

The points identified in Figure A-5 provide a skeleton test matrix which will be filled in based upon the results of the experiments. As testing progresses, the sensitivities to the various boundary conditions will be examined and further test points will be specified (within the limitations of the test rig and support equipment capabilities) which provide for adequate characterization of the complete pump curves.

At each point a range of volumetric flow qualities between 0 and 90% (within the limits of the support equipment capabilities) will be investigated. Since the greatest sensitivity to volumetric flow quality is anticipated to occur at lower flow qualities, a smaller increment (2.5%) will be used between 0 and 20%. A volumetric flow quality of 25% will also be investigated and for volumetric flow qualities between 30 and 90%, a larger increment (10%) will be used. This forms the general guidance for the volumetric flow qualities to be investigated. However, for all regions of significant sensitivity such as the steep pump head degradation region in the normal pump operation quadrant, additional volumetric flow qualities will be investigated as necessary.

For certain points a range of pump inlet pressures between 125 and 400 kPa (18.1 and 58.0 psia) will be examined. Since the major concern for pump inlet pressure effects relates to air compressibility effects, more emphasis will be placed upon characterizing the pressure sensitivity effects in the normal pump quadrant than the other quadrants. Further, the initial testing will focus on pressure sensitivity effects closer to the pump normal operating conditions ($v/\alpha = 1$). Pressure sensitivities at other first quadrant points will be investigated until adequately characterized. For the other pump homologous quadrants a similar approach will be taken. However, it is anticipated that pressure sensitivity effects will either be less significant or unimportant for the other three quadrants and will therefore require fewer multiple pressure test points.

The following general notes are applicable for all of these test points:

For all forward flow tests, the tank bypass, short discharge geometry (Mod-TBSD, Figures 2 and 5) will be used.

For all reverse flow tests, the Bingham pump reverse flow geometry (Mod-BPRF, Figures 3 and 6) will be used.

For all reverse pump rotation tests, the pump motor wiring will be re-configured (2 of the 3 phases reversed) to drive the pump in reverse rotation.

For all turbinizing operation tests, the pump motor will be replaced by a pump speed control device.

For all locked rotor tests, a lever arm will be attached to the shaft to prevent rotation of the pump rotor. The position of the rotor shaft will also be noted.

For all tests data are to be sampled for a minimum of 1/2 minute or one complete cycle of oscillatory behavior.

For all tests, the pump inlet conditions should be set to achieve the desired pressure, total volumetric flow rate and volumetric flow quality after the pump speed is set.

The objectives for all of these tests is to provide complete characterization of the 1/4 linear scale Bingham pump for single-phase and two-phase, two-component conditions for all four pump homologous curve quadrants.

An additional concern for pump response sensitivity relates to effects of pump discharge geometries and methods of air introduction. Hence, ten integral system tests performed as part of Phase II testing were selected to be repeated in the Phase III tests. The objectives of these tests (Table A-2) are to verify that two-phase, air-water pump performance with air injected directly into the pump suction pipe and not quite prototypic pump suction and discharge geometries is the same as pump performance with air introduced via the moderator tank assemblies or ingestion at the tank exit muff and prototypic suction and discharge geometries. The latter of the two being more prototypic of actual conditions in a Savannah River Site production reactor.

Table A-2. Repeat Two-Phase Integral System Characterization with Pump Suction Air Injection Tests

SET Test Number	Pump Speed	Pump DeltaP	Pump Suction Pressure	Liquid Flow Rate	Air Flow Rate	Flow/Speed Ratio, v/α
RTPSA1 [AC4M63]	210.9 ± 1.0 rad/s [2014 ± 10 rpm]	102.7 ± 2 kPa [14.9 ± 0.3 psid]	88.8 ± 5 kPa [12.9 ± 0.7 psia]	982.5 ± 49.1 lpm [259.5 ± 13.0 gpm]	113.4 ± 5.7 slpm [30.0 ± 1.5 sgpm]	0.373
RTPSA2 [AC4M65]	211.5 ± 1.0 rad/s [2020 ± 10 rpm]	61.3 ± 2 kPa [8.9 ± 0.3 psid]	85.4 ± 5 kPa [12.4 ± 0.7 psia]	552.6 ± 27.6 lpm [146.0 ± 7.3 gpm]	61.9 ± 3.1 slpm [16.4 ± 0.8 sgpm]	0.210
RTPSA3 [AC4M67]	211.6 ± 1.0 rad/s [2021 ± 10 rpm]	37.0 ± 2 kPa [5.4 ± 0.3 psid]	85.0 ± 5 kPa [12.3 ± 0.7 psia]	192.0 ± 9.6 lpm [50.7 ± 2.5 gpm]	15.6 ± 0.8 slpm [4.1 ± 0.2 sgpm]	0.070
RTPSA4 [AF1IT5]	210.8 ± 1.0 rad/s [2013 ± 10 rpm]	40.1 ± 2 kPa [5.8 ± 0.3 psid]	86.1 ± 5 kPa [12.5 ± 0.7 psia]	465.0 ± 23.2 lpm [122.8 ± 6.1 gpm]	64.9 ± 3.2 slpm [17.1 ± 0.9 sgpm]	0.182
RTPSA5 [AF2IT2]	211.4 ± 1.0 rad/s [2019 ± 10 rpm]	41.1 ± 2 kPa [6.0 ± 0.3 psid]	86.2 ± 5 kPa [12.5 ± 0.7 psia]	460.2 ± 23.0 lpm [121.6 ± 6.1 gpm]	50.6 ± 2.5 slpm [13.4 ± 0.7 sgpm]	0.174
RTPSA6 [FRFIT11]	211.4 ± 1.0 rad/s [2019 ± 10 rpm]	47.2 ± 2 kPa [6.8 ± 0.3 psid]	86.1 ± 5 kPa [12.5 ± 0.7 psia]	500.0 ± 25.0 lpm [132.1 ± 6.6 gpm]	59.6 ± 3.0 slpm [15.7 ± 0.8 sgpm]	0.191
RTPSA7 [FRFIT13]	211.5 ± 1.0 rad/s [2020 ± 10 rpm]	32.9 ± 2 kPa [4.8 ± 0.3 psid]	85.8 ± 5 kPa [12.4 ± 0.7 psia]	352.0 ± 17.6 lpm [93.0 ± 4.6 gpm]	40.0 ± 2.0 slpm [10.6 ± 0.5 sgpm]	0.134
RTPSA8 [FRFIT19]	60.6 ± 1.0 rad/s [579 ± 10 rpm]	31.2 ± 2 kPa [4.5 ± 0.3 psid]	88.6 ± 5 kPa [12.8 ± 0.7 psia]	474.8 ± 23.7 lpm [125.4 ± 6.3 gpm]	1.32 ± 0.07 slpm [0.35 ± 0.02 sgpm]	0.555
RTPSA9 [FRFIT19A]	60.6 ± 1.0 rad/s [579 ± 10 rpm]	27.4 ± 2 kPa [4.0 ± 0.3 psid]	85.7 ± 5 kPa [12.4 ± 0.7 psia]	482.9 ± 24.1 lpm [127.6 ± 6.4 gpm]	2.97 ± 0.15 slpm [0.78 ± 0.04 sgpm]	0.566
RTPSA10 [FRFIT22A]	68.9 ± 1.0 rad/s [658 ± 10 rpm]	31.4 ± 2 kPa [4.6 ± 0.3 psid]	85.5 ± 5 kPa [12.4 ± 0.7 psia]	301.3 ± 15.1 lpm [79.6 ± 4.0 gpm]	0.90 ± 0.05 slpm [0.24 ± 0.01 sgpm]	0.310

Notes:

All tests use tank bypass, 'short' pump discharge piping (Mod-TBSD) configuration (Figures 2 and 5).

Tests RTPSA1 thru 3 use demineralized water at 295 ± 3 K [22 ± 3 °C].

Tests RTPSA4 thru 10 use demineralized water at 296 ± 3 K [23 ± 3 °C].

Air should be injected into the pump suction pipe to obtain the specified pump inlet air flow based on the pump inlet air density. Data are to be sampled for a minimum of 3 minutes or one complete cycle of oscillatory behavior.

Pump discharge valve [FCV-PEX] should be set to obtain the specified pump differential pressure.

Liquid and air injection system controls should be adjusted to obtain the specified pump suction pressure.

Integral counterpart tests shown in brackets.

Pump speed, pump differential pressure, pump suction pressure, and liquid and air volumetric flow rates are based on values measured in the counterpart integral tests.

Flow-to-speed ratio, v/α , was determined from parameters measured during the counterpart integral tests.

Test objectives:

Verify that two-phase, air-water pump response with air injected directly into pump suction pipe and not quite prototypic suction and discharge geometries is similar to that with air introduced via moderator tank assemblies or ingestion and prototypic suction and discharge piping.

Photographic Information:

Focus process cameras on the vertical section of pump suction piping near pump and the horizontal pipe section just upstream. Take 30 second snapshot for each test.

Appendix B
Test Matrix Tables for SET Phase III Tests
From NES-CDG-920181

Table B-3. Single-Phase Liquid 1/4 Scale Formal Bingham Pump Quadrant One, Speed-to-Flow Ratio ≤ 1 Tests

SET Test Number	Pump Speed	Liquid Flow Rate	Tank Level	Temperature	Speed Ratio, α	Flow Ratio, ν	Speed/Flow Ratio, α/ν
SPDBP5	2010 $\pm$ 40 rpm	3963 $\pm$ 197 lpm [1047 $\pm$ 52 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	1.005	1.340	.750
SPDBP6	2010 $\pm$ 40 rpm	4244 $\pm$ 212 lpm [1121 $\pm$ 56 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	1.005	1.436	.700
SPDBP7	2010 $\pm$ 40 rpm	4573 $\pm$ 227 lpm [1208 $\pm$ 60 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	1.005	1.546	.650
SPDBP8	2010 $\pm$ 40 rpm	4951 $\pm$ 246 lpm [1308 $\pm$ 65 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	1.005	1.675	.600
SFDBP9	2010 $\pm$ 40 rpm	5402 $\pm$ 269 lpm [1427 $\pm$ 71 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	1.005	1.827	.550
SPDBP13	1500 $\pm$ 30 rpm	3695 $\pm$ 186 lpm [976 $\pm$ 49 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	.750	1.250	.600
SPDBP14	1500 $\pm$ 30 rpm	4437 $\pm$ 223 lpm [1172 $\pm$ 59 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	0.750	1.500	.500
SFDBP17	1000 $\pm$ 20 rpm	2464 $\pm$ 125 lpm [651 $\pm$ 33 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	0.500	.833	.600
SFDBP18	1000 $\pm$ 20 rpm	2956 $\pm$ 148 lpm [781 $\pm$ 39 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	0.500	1.000	.500

Notes: Tests SPDBP5 thru 7, 13, 17, 18 and 24 thru 26 use simulated K14.1 core loading and system 5 pump suction geometry (EG&G Drawing 438933) with the 'short' pump discharge piping (Mod-TMPSD) configuration (Figures 1 and 4).
Tests SPDBP8, 9, 14, 19 and 20 use tank bypass and system 5 pump suction geometry with the 'short' pump discharge piping (Mod-TBSD) configuration (Figures 2 and 5).

Flow zone liquid flow distribution is arbitrary. No air is to be injected.

Data are to be sampled for a minimum of 3 minutes or one complete cycle of oscillatory behavior.

Pump discharge valve [FCV-PEX] should be set to obtain the specified liquid flow rate once the specified pump speed is set.

Test objectives: Characterize the 1/4 scaled Bingham pump for single-phase quadrant one, speed-to-flow ratio ≤ 1 operation, i.e. positive rotational speed, positive flow and hydraulic torque, and negative pump head.

Table B-3. Single-Phase Liquid 1/4 Scale Formal Bingham Pump Quadrant One, Speed-to-Flow Ratio ≤ 1 Tests (Continued)

SET Test Number	Pump Speed	Liquid Flow Rate	Tank Level	Temperature	Speed Ratio, α	Flow Ratio, ν	Speed/Flow Ratio, α/ν
SPDBP19	560 $\pm$ 11 rpm	920 $\pm$ 45 lpm [243 $\pm$ 12 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	.280	.311	.900
SPDBP20	560 $\pm$ 11 rpm	1033 $\pm$ 53 lpm [273 $\pm$ 14 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	.280	.350	.800
SPDBP24	560 $\pm$ 11 rpm	1272 $\pm$ 64 lpm [336 $\pm$ 17 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	.280	.431	.650
SPDBP25	560 $\pm$ 11 rpm	1382 $\pm$ 68 lpm [365 $\pm$ 18 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	.280	.467	.600
SPDBP26	560 $\pm$ 11 rpm	1507 $\pm$ 76 lpm [398 $\pm$ 20 gpm]	101.6 $\pm$ 1.3 cm [40 $\pm$ 0.5 in.]	296 $\pm$ 3 K [23 $\pm$ 3 °C]	.280	.509	.550

Notes: Tests SPDBP5 thru 7, 13, 17, 18 and 24 thru 26 use simulated K14.1 core loading and system 5 pump suction geometry (EG&G Drawing 438033) with the 'short' pump discharge piping (Mod-TMPD) configuration (Figures 1 and 4).

Tests SPDBP 8, 9, 14, 19 and 20 use tank bypass and system 5 pump suction geometry with the 'short' pump discharge piping (Mod-TBSD) configuration (Figures 2 and 5).

Flow zone liquid flow distribution is arbitrary. No air is to be injected.

Data are to be sampled for a minimum of 3 minutes or one complete cycle of oscillatory behavior.

Pump discharge valve [FCV-P&A] should be set to obtain the specified liquid flow rate once the specified pump speed is set.

Test objectives: Characterize the 1/4 scaled Bingham pump for single-phase quadrant one, speed-to-flow ratio ≤ 1 operation, i.e. positive rotational speed, positive flow and hydraulic torque, and negative pump head.

Table B-5. Single-Phase Liquid 1/4 Scale Formal Bingham Pump Free Rotor Hydraulic Characterization Tests

SET Test Number	Tank Level	Liquid Flow Rate	Temperature	Flow Ratio v
SPFRP1	101.6 ± 1.3 cm [40 ± 0.5 in.]	379 ± 19 lpm [100 ± 5 gpm]	296 ± 3 K [23 ± 3 °C]	.128
SPFRP2	101.6 ± 1.3 cm [40 ± 0.5 in.]	568 ± 30 lpm [150 ± 8 gpm]	296 ± 3 K [23 ± 3 °C]	.192
SPFRP3	101.6 ± 1.3 cm [40 ± 0.5 in.]	757 ± 38 lpm [200 ± 10 gpm]	296 ± 3 K [23 ± 3 °C]	.256
SPFRP4	101.6 ± 1.3 cm [40 ± 0.5 in.]	946 ± 49 lpm [250 ± 13 gpm]	296 ± 3 K [23 ± 3 °C]	.320
SPFRP5	101.6 ± 1.3 cm [40 ± 0.5 in.]	1136 ± 57 lpm [300 ± 15 gpm]	296 ± 3 K [23 ± 3 °C]	.384

Notes: All tests use simulated K14.1 core loading and system 5 pump suction geometry (EG&G Drawing 438933) with the 'short' pump discharge piping (Mod-TMPD) configuration (Figures 1 and 4).
Flow zone liquid flow distribution is arbitrary. No air is to be injected.
Bingham pump drive motor should be de-energized for these tests with the pump impeller free to rotate.
Data are to be sampled for a minimum of 3 minutes or one complete cycle of oscillatory behavior.
Pump discharge valve [FCV-PEX] should be set to obtain the specified liquid flow rate once the specified pump speed is set.

Test objectives: Characterize the single-phase pump hydraulic loss with pump driver de-energized and impeller free to rotate.

Appendix C
Test Matrix Tables for SET Phase III Tests
From NES-CDG-920241, Revision 1

Table C-1. Two-Phase Air-Water 1/4-Scale Formal Integral Tests - Pump Discharge Break Test with and without Simulated AC Pump Motor Trip								
SET Test Number	Pump Speed	Time of AC Motor Trip	Initial Tank Level	Zone 1 Liquid Flow % of Total	Zone 2 Liquid Flow % of Total	Zone 3 Liquid Flow % of Total	Zone 4 Liquid Flow % of Total	Zone 5 Liquid Flow % of Total
PDBIT1	2010 ± 10 rpm	No Trip	101.6 ± 1.3 cm [40 ± 0.5 in.]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
PDBIT2	600 ± 10 rpm	No Trip	101.6 ± 1.3 cm [40 ± 0.5 in.]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
PDBIT3	560 ± 10 rpm	No Trip	101.6 ± 1.3 cm [40 ± 0.5 in.]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
PDBIT4	2010 ± 10 rpm	1 second	101.6 ± 1.3 cm [40 ± 0.5 in.]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
PDBIT5	2010 ± 10 rpm	2 second	101.6 ± 1.3 cm [40 ± 0.5 in.]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
Notes: For PDBIT tests install 1/4-linear scale prototypic nine vane muff (EG&G Drawing 436299). All tests use simulated K14.1 core loading. All tests use System 5 pump suction geometry (EG&G Drawing 438933) in the TMP with the 'short' discharge piping (Mod-TMPSD) configuration (Figures 1 and 4). Tests to be performed with demineralized water at 296 ± 3 K [23 ± °C]. No air is to be injected in assembly end fittings. All flow zone liquid flows are percent of total. Sparjet liquid flow is 1 ± 0.1 % of total liquid flow. Tank vent valve set to obtain the correct scaled air flow resistance. DAS acquisition rate to be increased to at least 25 HZ for the duration of each test. Pump discharge valve [FCV-PEX] should be set so that the pump discharge pressure is approximately atmospheric. Pump discharge valve to remain in initial position for duration of test. Test to be terminated when apex tank level reaches 2 to 3 inches. Tests to be initiated by abruptly terminating flow to the moderator tank and simulating the coastdown of the 1/4-scale Bingham pump. The pump coastdown data for 1989 L Reactor test AC2S12 should be used (NES-CDG-920093). Simulated AC motor trip to be initiated at specified times following termination of liquid flow to the moderator tank.								
Test objectives:		Investigate the system response to a pump discharge break simulated LOCA with and without AC pump motor trip.						
Photographic Information:		Focus high speed cameras on the vertical section of pump suction piping near pump and the horizontal pipe section just upstream. Set cameras to run for entire test. Focus process cameras on the remaining sections of piping and on the muff and side of tank. Record process video for duration of test.						

Table C-1. Two-Phase Air-Water 1/4-Scale Formal Integral Tests - Pump Discharge Break Test with and without Simulated AC Pump Motor Trip (Continued)								
SET Test Number	Pump Speed	Time of AC Motor Trip	Initial Tank Level	Zone 1 Liquid Flow % of Total	Zone 2 Liquid Flow % of Total	Zone 3 Liquid Flow % of Total	Zone 4 Liquid Flow % of Total	Zone 5 Liquid Flow % of Total
PDBIT6	2010 ± 10 rpm	3 second	101.6 ± 1.3 cm [40 ± 0.5 in.]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
PDBIT7	2010 ± 10 rpm	4 second	101.6 ± 1.3 cm [40 ± 0.5 in.]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
PDBIT8	2010 ± 10 rpm	5 second	101.6 ± 1.3 cm [40 ± 0.5 in.]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
Notes: For PDBIT tests install 1/4-linear scale prototypic nine vane muff (EG&G Drawing 436299). All tests use simulated K14.1 core loading. All tests use System 5 pump suction geometry (EG&G Drawing 438933) in the TMP with the 'short' discharge piping (Mod-TMPSD) configuration (Figures 1 and 4). Tests to be performed with demineralized water at 296 ± 3 K [23 ± °C]. No air is to be injected in assembly end fittings. All flow zone liquid flows are percent of total. Sparjet liquid flow is 1 ± 0.1% of total liquid flow. Tank vent valve set to obtain the correct scaled air flow resistance. DAS acquisition rate to be increased to at least 25 HZ for the duration of each test. Pump discharge valve [FCV-PEX] should be set so that the pump discharge pressure is approximately atmospheric. Pump discharge valve to remain in initial position for duration of test. Test to be terminated when apex tank level reaches 2 to 3 inches. Tests to be initiated by abruptly terminating flow to the moderator tank and simulating the coastdown of the 1/4-scale Bingham pump. The pump coastdown data for 1989 L Reactor test AC2S12 should be used (NES-CDG-920093). Simulated AC motor trip to be initiated at specified times following termination of liquid flow to the moderator tank.								
Test objectives:			Investigate the system response to a pump discharge break simulated LOCA with and without AC pump motor trip.					
Photographic Information:			Focus high speed cameras on the vertical section of pump suction piping near pump and the horizontal pipe section just upstream. Set cameras to run for entire test. Focus process cameras on the remaining sections of piping and on the muff and side of tank. Record process video for duration of test.					

Table C-2. Controlled Drain Pump Discharge Break Formal Integral Tests

SET Test Number	Initial Tank Apex Region Liquid Level	Pump speed	Zone 1 Liquid Flow % of Total	Zone 2 Liquid Flow % of Total	Zone 3 Liquid Flow % of Total	Zone 4 Liquid Flow % of Total	Zone 5 Liquid Flow % of Total
DBCDI1	101.6 ± 1.3 cm [40 ± 0.5 in.]	210.5 ± 1 rad/s [2010 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBCDI2	101.6 ± 1.3 cm [40 ± 0.5 in.]	157.1 ± 1 rad/s [1500 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBCDI3	101.6 ± 1.3 cm [40 ± 0.5 in.]	104.7 ± 1 rad/s [1000 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBCDI4	101.6 ± 1.3 cm [40 ± 0.5 in.]	58.6 ± 1 rad/s [560 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %

Notes:

For DBCDI tests install 1/4-linear scale prototypic nine vane muff (EG&G Drawing 436299).

All tests use simulated K14.1 core loading. All tests use System 5 pump suction geometry (EG&G Drawing 438933) in the TMP with the 'short' discharge piping (Mod-TMPSD) configuration (Figures 1 and 4).

All tests use demineralized water at 296 ± 3 K (23 ± 3 °C) with the tank vent valve set to its full open position. No air injection.

Tests are terminated when tank center level reaches 7.6 cm [3.0 inches].

All flow zone liquid flows are percent of total. Sparjet flow is 1 ± 0.1 % of total liquid flow.

For all tests, drain is performed by gradually decreasing total liquid flow to maintain average drain rate.

The drain rate should be set to 2-3 inches per minute in the single-phase (no air) drain region. Prior to air ingestion, the drain rate should be reduced to 1/4 - 1/2 in/min or the minimum drain rate for which facility control can be maintained.

Pump discharge valve [FCV-PEX] should be set so that the pump discharge pressure is approximately atmospheric. Pump discharge valve to remain in initial position for duration of test.

Important Visual Observations:

The apex, mid-point, and zone 5 incipient air ingestion tank levels should be recorded in the log.

Test objectives:

Characterize two-component air-water hydraulics as a function of tank level for several different pump speeds.

Photographic Observations:

The process cameras should be focused to encompass as much of the pump suction piping as possible. A process camera should be focused on the lower portion of the tank and the muff/transition elbow. Process camera tapes (VCR) should be made for the duration of the drain and refill tests. Selected 30 second time slices should be made of the pump suction piping (wide angle view), transition elbow, and tank side using the high speed camera system. Still photographs of initial air ingestion, observed flow regimes, and flow regime transitions are desired.

Table C-3. Hold Point Pump Discharge Break Formal Integral Tests

SET Test Number	Tank Apex Region Liquid Level	Pump speed	Zone 1 Liquid Flow % of Total	Zone 2 Liquid Flow % of Total	Zone 3 Liquid Flow % of Total	Zone 4 Liquid Flow % of Total	Zone 5 Liquid Flow % of Total
DBHPI1	101.6 ± 1.3 cm [40 ± 0.5 in.]	210.5 ± 1 rad/s [2010 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI2	76.2 ± 1.3 cm [30 ± 0.5 in.]	210.5 ± 1 rad/s [2010 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI3	50.8 ± 1.3 cm [20 ± 0.5 in.]	210.5 ± 1 rad/s [2010 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI4	25.4 ± 1.3 cm [10 ± 0.5 in.]	210.5 ± 1 rad/s [2010 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI5	20.3 ± 1.3 cm [8 ± 0.5 in.]	210.5 ± 1 rad/s [2010 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI6	15.2 ± 1.3 cm [6 ± 0.5 in.]	210.5 ± 1 rad/s [2010 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI7	10.2 ± 1.3 cm [4 ± 0.5 in.]	210.5 ± 1 rad/s [2010 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI8	101.6 ± 1.3 cm [40 ± 0.5 in.]	58.6 ± 1 rad/s [560 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %

Notes:

For DBHPI tests install 1/4-linear scale prototypic nine vane muff (EG&G Drawing 436299).

All tests use simulated K14.1 core loading. All tests use System 5 pump suction geometry (EG&G Drawing 438933) in the TMP with the 'short' discharge piping (Mod-TMPSD) configuration (Figures 1 and 4).

All flow zone and sparjet flows are percent of total flow. Sparjet liquid flow is 1.0 ± 0.1 % for all tests. Tank vent valve set to obtain correct scaled air flow resistance.

All tests use demineralized water at 296 ± 3 K [23 ± 3 °C]. Data are to be sampled for a minimum of 3 minutes or one complete cycle of oscillatory behavior.

Pump discharge valve [FCV-PEX] should be set so that the pump discharge pressure is approximately atmospheric. Pump discharge valve to remain in initial position for duration of test.

Test objectives: Characterize the liquid and air flow rates for a pump discharge simulated pipe break as a function of tank apex level and pump speed.

Photographic Information:

For two-phase tests conditions only: High speed video recording for 30 seconds of the vertical and horizontal pump suction pipe sections (wide angle views), side of tank, and muff/transition elbow. Still photographs of muff vane region from the side, pump suction piping, transition elbow, and tank side.

Table C-3. Hold Point Pump Discharge Break Formal Integral Tests (Continued)

SET Test Number	Tank Apex Region Liquid Level	Pump speed	Zone 1 Liquid Flow % of Total	Zone 2 Liquid Flow % of Total	Zone 3 Liquid Flow % of Total	Zone 4 Liquid Flow % of Total	Zone 5 Liquid Flow % of Total
DBHPI9	76.2 ± 1.3 cm [30 ± 0.5 in.]	58.6 ± 1 rad/s [560 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI10	50.8 ± 1.3 cm [20 ± 0.5 in.]	58.6 ± 1 rad/s [560 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI11	25.4 ± 1.3 cm [10 ± 0.5 in.]	58.6 ± 1 rad/s [560 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI12	17.8 ± 1.3 cm [7 ± 0.5 in.]	58.6 ± 1 rad/s [560 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI13	15.2 ± 1.3 cm [6 ± 0.5 in.]	58.6 ± 1 rad/s [560 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI14	12.7 ± 1.3 cm [5 ± 0.5 in.]	58.6 ± 1 rad/s [560 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHPI15	10.2 ± 1.3 cm [4 ± 0.5 in.]	58.6 ± 1 rad/s [560 ± 10 rpm]	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %

Notes:

For DBHPI tests install 1/4-linear scale prototypic nine vane muff (EG&G Drawing 436299). All tests use simulated K14.1 core loading. All tests use System 5 pump suction geometry (EG&G Drawing 438933) in the TMP with the 'short' discharge piping (Mod-TMPSD) configuration (Figures 1 and 4).

All flow zone and sparjet flows are percent of total flow. Sparjet liquid flow is 1.0 ± 0.1 % for all tests.

Tank vent valve set to obtain correct scaled air flow resistance.

All tests use demineralized water at 296 ± 3 K [23 ± 3 °C].

Data are to be sampled for a minimum of 3 minutes or one complete cycle of oscillatory behavior.

Pump discharge valve [FCV-PEX] should be set so that the pump discharge pressure is approximately atmospheric. Pump discharge valve to remain in initial position for duration of test.

Test objectives: Characterize the liquid and air flow rates for a pump discharge simulated pipe break as a function of tank apex level and pump speed.

Photographic Information: For two-phase tests conditions only: High speed video recording for 30 seconds of the vertical and horizontal pump suction pipe sections (wide angle views), side of tank, and muff/transition elbow. Still photographs of muff vane region from the side, pump suction piping, transition elbow, and tank side.

Table C-4. Controlled Drain Pump Discharge Break with De-energized Pump Motor - Formal Integral Tests

SET Test Number	Initial Tank Apex Region Liquid Level	Pump speed	Zone 1 Liquid Flow % of Total	Zone 2 Liquid Flow % of Total	Zone 3 Liquid Flow % of Total	Zone 4 Liquid Flow % of Total	Zone 5 Liquid Flow % of Total
DBDFR1	111.8 ± 1.3 cm [44 ± 0.5 in.]	See Notes	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %

Notes: For DBDFR tests install 1/4-linear scale prototypic nine vane muff (EG&G Drawing 436299). All tests use simulated K14.1 core loading. All tests use System 5 pump suction geometry (EG&G Drawing 438933) in the TMP with the 'short' discharge piping (Mod-TMPSD) configuration (Figures 1 and 4). All tests use demineralized water at 296 ± 3 K [23 ± 3 °C] with the tank vent valve set to its full open position. No air injection. Tests are terminated when tank center level reaches 7.6 cm [3.0 inches]. All flow zone liquid and air flows are percent of total. Sparjet flow is 1 ± 0.1 % of total liquid flow. For all tests, drain is performed by gradually decreasing total liquid flow to maintain average drain rate. The drain rate should be set to 2-3 inches per minute in the single-phase (no air) drain region. Prior to air ingestion, the drain rate should be reduced to 1/4 - 1/2 inches/minute or the minimum drain rate for which facility control can be maintained. Pump discharge valve [FCV-PEX] should be set so that the pump discharge pressure is approximately atmospheric. Pump discharge valve to remain in initial position for duration of test. The variable speed motor should be de-energized prior to performing this test. Note carefully if the pump impeller continues to rotate during this test.

Test objectives: Characterize single and two-phase pump behavior for pump discharge break conditions with both the AC and DC pump motors tripped.

Photographic Observations: The process cameras should be focused to encompass as much of the pump suction piping as possible. A process camera should also be focused to encompass the lower portion of the tank and the muff/transition elbow. Process camera tapes (VCR) should be made for the duration of the drain and refill tests.

Table C-5. Hold Point Pump Discharge Break with Pump Motor De-energized - Formal Integral Tests

SET Test Number	Tank Apex Region Liquid Level	Pump speed	Zone 1 Liquid Flow % of Total	Zone 2 Liquid Flow % of Total	Zone 3 Liquid Flow % of Total	Zone 4 Liquid Flow % of Total	Zone 5 Liquid Flow % of Total
DBHFR1	111.8 ± 1.3 cm [44 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHFR2	101.6 ± 1.3 cm [40 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHFR3	76.2 ± 1.3 cm [30 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHFR4	50.8 ± 1.3 cm [20 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHFR5	38.1 ± 1.3 cm [15 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHFR6	25.4 ± 1.3 cm [10 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %

Notes:

For DBHFR tests install 1/4-linear scale prototypic nine vane muff (EG&G Drawing 436299).

All tests use simulated K14.1 core loading. All tests use System 5 pump suction geometry (EG&G Drawing 438933) in the TMP with the 'short' discharge piping (Mod-TMPSD) configuration (Figures 1 and 4).

All zone and sparjet flows are percent of total flow. Sparjet liquid flow is 1.0 ± 0.1 % for all tests.

Tank vent valve set to obtain correct scaled air flow resistance.

All tests use demineralized water at 296 ± 3 K [23 ± 3 °C].

Data are to be sampled for a minimum of 3 minutes or one complete cycle of oscillatory behavior.

Pump discharge valve [FCV-PEX] should be set so that the pump discharge pressure is approximately atmospheric. Pump discharge valve to remain in initial position for duration of test.

The variable speed motor should be de-energized prior to performing these tests.

Note carefully whether the pump impeller continues to rotate after steady state test conditions have been reached. If it remains stationary, the impeller should be rotated at a few rpm while test data is recorded.

Test objectives:

Characterize single and two-phase pump behavior for pump discharge break conditions with both the AC and DC pump motors tripped.

Photographic Information:

For two-phase conditions only: High speed video recording for 30 seconds of the vertical and horizontal pump suction pipe pipe sections (wide angle views), side of tank, and muff/transition elbow. Still photographs of muff vane region from the side, pump suction piping, transition elbow, and tank side.

Table C-5. Hold Point Pump Discharge Break with Pump Motor De-energized - Formal Integral Tests (Continued)

SET Test Number	Tank Apex Region Liquid Level	Pump speed	Zone 1 Liquid Flow % of Total	Zone 2 Liquid Flow % of Total	Zone 3 Liquid Flow % of Total	Zone 4 Liquid Flow % of Total	Zone 5 Liquid Flow % of Total
DBHFR7	20.3 ± 1.3 cm [8 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHFR8	17.8 ± 1.3 cm [7 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHFR9	15.2 ± 1.3 cm [6 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHFR10	50.8 ± 1.3 cm [20 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHFR11	10.2 ± 1.3 cm [4 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %
DBHFR12	7.6 ± 1.3 cm [3 ± 0.5 in.]	N/A	12 ± 1.2 %	16 ± 1.6 %	31 ± 3.1 %	26 ± 2.6 %	14 ± 1.4 %

Notes:

For DBHFR tests install 1/4-linear scale prototypic nine vane muff (EG&G Drawing 436299).

All tests use simulated K14.1 core loading. All tests use System 5 pump suction geometry (EG&G Drawing 438933) in the TMP with the 'short' discharge piping (Mod-TMPSD) configuration (Figures 1 and 4).

All zone and sparjet flows are percent of total flow. Sparjet liquid flow is 1.0 ± 0.1 % for all tests.

Tank vent valve set to obtain correct scaled air flow resistance.

All tests use demineralized water at 296 ± 3 K [23 ± 3 °C].

Data are to be sampled for a minimum of 3 minutes or one complete cycle of oscillatory behavior.

Pump discharge valve [FCV-PEX] should be set so that the pump discharge pressure is approximately atmospheric. Pump

discharge valve to remain in initial position for duration of test.

The variable speed motor should be de-energized prior to performing these tests.

Note carefully whether the pump impeller continues to rotate after steady state test conditions have been reached. If it remains stationary, the impeller should be rotated at a few rpm while test data is recorded.

Test objectives:

Characterize single and two-phase pump behavior for pump discharge break conditions with both the AC and DC pump motors tripped.

Photographic Information:

For two-phase conditions only: High speed video recording for 30 seconds of the vertical and horizontal pump suction pipe pipe sections (wide angle views), side of tank, and muff/transition elbow. Still photographs of muff vane region from the side, pump suction piping, transition elbow, and tank side.

**DATE
FILMED**

9/20/93

END

[REDACTED]