DOE/SF/16306--34

DE93 005795

COLORADO STATE UNIVERSITY PROGRAM FOR
DEVELOPING, TESTING, EVALUATING AND OPTIMIZING
SOLAR HEATING AND COOLING SYSTEMS

Received by OSTI

JAN 14 1993

PROJECT STATUS REPORT FOR THE MONTHS OF
MARCH THROUGH NOVEMBER 1992

Prepared for the

U.S. Department of Energy
Conservation and Solar Applications
Under Grant DE-FG02-86-SF16306

Submitted by

Solar Energy Applications Laboratory
Colorado State University

January, 1993

January 7, 1993

Report No: SF-16306-34

Report Period: 1 March 1992 to 30 November 1992

PROJECT TITLE:

Developing, Testing, Evaluating and Optimizing Solar Heating and Cooling Systems

GRANT NUMBER: DE-FG02-86-SF16306

GRANTEE NAME: Solar Energy Applications Laboratory
Colorado State University
Fort Collins, Colorado 80523

GRANT PERIOD: 1 June 1986 to 28 February 1993

GENERAL STATUS:

1. Project Objective:

The objective is to develop and test various integrated solar heating, cooling and domestic hot water systems, and to evaluate their performance.

2. Technical Approach:

Systems composed of new, as well as previously tested, components are carefully integrated so that effects of new components on system performance can be clearly delineated. The SEAL-DOE program includes six tasks which have received funding for the 1992-93 twelve-month period. These include: (1) a project measuring the performance of unique solar system components, (2) a project to develop a methodology for determining annual performance ratings of solar domestic hot water systems, (3) a project that will identify, analyze, design, build, and experimentally evaluate SDHW systems incorporating advanced concepts and components, (4) a liquid desiccant cooling system development project, (5) a project that will perform TRNSYS simulations to determine potential energy savings for desiccant cooling systems, especially in humid climates, and (6) a management task. The objectives and progress in each task are described in this report.

List of Co-Sponsors

Co-sponsors for parts of the above research program include:
Colorado State University
American Solar Network
Energy, Mines and Resources
Sun Utility Network
Danish Technical University

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

forced and natural convection heat transfer correlations. The PV powered DC pump model is empirical. The current-voltage characteristics of the PV-powered pump is predicted based on manufacturer's performance data for each component and a curve fit for the variation of collector flow rate versus insolation is generated.

The validity of the models developed could not be confirmed from empirical data available from the component manufacturers or from the technical literature.

Solar system performance simulations for several combinations of solar tank, PV-panel/DC-pumps, and domestic hot water demands were compared with the performance of a more conventional system incorporating an AC pump and counterflow heat exchanger. Simulation results were provided to SRCC to assist with the SMUD program certification process. Details of this modeling effort are documented in a technical paper submitted for the 1993, ASME/ASES/SOLTECH Solar Energy Conference to be held in April, 1993 in Washington, DC (attached).

CSU has acquired an 80-gallon, wrap-around heat exchanger tank. This tank is being prepared for test in the Generic Systems test stand in Solar House II at CSU. Initial experiments will test the validity of the overall system performance predictions provided to the SRCC. Key assumptions including the use of a natural convection correlation for a constant temperature, vertical flat plate in an infinite medium and assumptions about the degree of stratification in the tank will be examined. This initial test program will guide the development of a more detailed research program to investigate the operation of natural convection solar heat exchangers. Initial test results are expected by mid-December, 1992.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

*conf paper cycled
separately. ds*

UNIQUE SOLAR SYSTEM COMPONENTS

Research Team: Dr. Douglas C. Hittle, Co-Task Leader
Dr. Jane H. Davidson, Co-Task Leader
Dr. George O.G. Löf, Senior Advisor
Jeffrey A. Miller, Graduate Research Assistant

Introduction:

Several solar system suppliers use unique combinations of heat exchangers and storage tanks. For example, a wrap-around storage tank has a pipe that wraps around all or part of the tank and transfers heat via that pipe to the storage fluid. Other unique systems include mantle heat exchangers and in-tank heat exchangers. There are very little experimental data on the performance of these systems. It is difficult to estimate system performance because models for unique combinations of heat exchangers and tanks are not available and are not verified. The interaction between the heat exchanger and stratification in the storage tank is unknown.

Proposed New Work:

Under this task, we propose to carry out an experimental investigation of the performance of unique storage tank heat exchanger combinations. The overall objective of the activity is to develop and verify models for these unique heat exchangers to permit an estimate of their impact on solar energy system performance.

We will use existing experimental facilities constructed under the Generic Systems research program to experimentally investigate the performance of several of these tank-heat exchanger combinations. To do this, fully instrumented tanks will be installed in the research facility and data will be collected under a variety of operating conditions.

Models of this tank will also be developed based on first principles.

Experimental data and models will be provided to our colleagues for use in estimating system performance and developing procedures for rating systems under the OG300 process.

During this grant period, we will begin to evaluate the performance of wrap-around heat exchanger-tank combinations.

While modeling efforts can be initiated with the budget specified, an equipment grant from DOE will be required to permit the modification of the experimental set-up, purchase tanks/heat exchangers to test, and fully instrument these tanks.

Progress:

A simple model has been developed to simulate the performance of a unique solar domestic hot water system which incorporates a wrap-around heat exchanger and a PV-powered pump. The TRNSYS, Type 4, stratified solar storage tank model has been modified to account for heat transfer from an integrated wrap-around heat exchanger. The model is developed from existing

RATING AND CERTIFICATION OF DOMESTIC WATER HEATING SYSTEMS

Research Team: Dr. Jane H. Davidson, Task Leader
David Adams, Graduate Research Assistant
Steve Kenny, Graduate Research Assistant
Alison Mason, Graduate Research Assistant

Goals:

The two primary goals of Colorado State University's generic systems research program are: 1) to develop a methodology for determining annual performance ratings of solar domestic hot water systems (SDHWS), and 2) to produce a standard for certifying solar swimming pool systems. This work is a joint effort of Colorado State University, University of Wisconsin, Solar Rating and Certification Corporation, and National Renewable Energy Laboratory. This proposal covers the time period from March 1, 1992 through February 28, 1993. Major tasks to be accomplished are: 1) complete construction and instrumentation of Colorado State University indoor solar simulator, 2) experimentally resolve issues surrounding simulation of in-collector storage (ICS) hot water heating systems, 3) initiate experimental analyses of thermosiphon systems.

Proposed Research

Experiments on the NEG ICS system will be conducted to resolve questions posed during the 1992 SOLTECH meeting by the Generic Systems team. Specific issues to be addressed are optical efficiency, reflectivity and heat loss. Incident angle modifiers will be simulated using three-dimensional Monte Carlo ray tracing and geometric modeling. Final experimental plans will be coordinated with Jay Burch of NREL.

Progress:

Solar Simulator

The Solar Simulator is in the final stages of construction and should be available for collector testing by December. The space frame is in place and only requires lamp installation and electrical hookup before it is completely operational. Figure 1 shows a schematic of the space frame. Instrumentation of the NEG internal-collector storage solar collector is complete. A rotating and tilting frame to hold the collectors is also installed in the laboratory. The cold water temperature supply and load control system, as specified in ASHRAE Standard 95-1987, is also complete.

The problem of uniformly irradiating the collector plane with 28 light sources, while satisfying collimation requirements, has been solved. ASHRAE standard 93-1986 requires "the uniformity of irradiance shall be such that the highest and lowest measure of values of irradiance shall not deviate from the average value by more than $\pm 10\%$." The requirement for collimation states "that at least 90% of the energy received at any point in the collector test plane shall have emanated from a region of the solar simulator contained within a subtended angle of 20° or less." In order to simulate the output of 28 1000 W Thorn Compact Source Iodine (CSI) lamps, radiation flux measurements from a single lamp are numerically combined. Simply

Figure 1- Schematic of Solar Simulator Space Frame

placing the lamps in a uniform grid is not sufficient to satisfy the requirements of uniformity and collimation. For example, with a lamp-to-lamp spacing of 0.447m in an array of four by seven lamps located 2.90m from the collector plane, average irradiance is 1195 W/m² with a uniformity of +19% and -15% over an irradiated area of 1.22 m by 2.44 m. The non-uniformity problem can be solved by reducing the area on the collector plane affected by each lamp.

In an effort to reduce the edge effects from a single lamp, several varieties of box and tube "collimators" were tested. The dimensions of the boxes and tubes, as well as their inside surfaces, were varied. Results indicate that the ASHRAE specifications for uniformity and collimation can be obtained with a four by seven lamp array with each lamp pointed through a 0.3m diameter by 1.22m long circular tube coated on the inside with a 90% reflective surface. With a lamp-to-lamp spacing of 0.447m and a lamp face-to-collector plane spacing of 3.35m, average irradiance is 1209 W/m² with a uniformity of +8% and -7%. However, with this design, radiation level is *extremely* sensitive to bulb orientation. Rotating the bulb less than 3mm results in as much as a 50% change in output at a single point. In other words, repeatability of these measurements cannot be assured. Building a device with 28 of these super-sensitive tubes would be impractical.

The tube collimator was also tested using a white diffuse surface rather than a reflective surface. In this case, output is not especially sensitive to the aiming of the lamp and the results are repeatable; however, the uniformity requirement cannot be met. With a lamp-to-lamp spacing of 0.447m in an array of four by seven lamps located 3.35m from the collector plane, average irradiance is 965 W/m² with a uniformity of +11% and -13%. Uniformity numbers can probably be improved by decreasing the lamp-to-collector distance. This hypothesis was not pursued because a better method of reducing bulb edge effects was found.

Although the use of the tubes provides a means by which uniformity can be obtained, the presence of 28 1.22m-long tubes attached to each lamp assembly would be burdensome, both aesthetically and mechanically. For this reason, an alternative approach has always been desired. By placing a sheet of opaque material with holes drilled so that some of the light from the lamps can pass through to the collector, irradiance levels at the collector can be controlled to achieve uniformity and collimation. In fact, irradiance levels are equivalent to those obtained with a white tube. Figure 2 is a sketch of the geometric effect of using this shadow-board technique. The reduction of edge effects is accomplished by shadowing the output of the bulb of one lamp from the point of maximum flux of its neighbor. The lamp-to-collector spacing is distance A. In order to restrict the irradiated area to a circle of radius O measured from the centerline of the lamp, an opaque plane with a hole of radius x must be placed distance y from the lamp. Distance O is set at 0.447m which is the lamp-to-lamp distance. Length A can be varied depending on the desired irradiance level on the collector. Dimensions x and y are functions of O and A due to the simple geometric relationship. They are completely arbitrary as long as the ratio of x to y equals that of O to A.

The effectiveness of the shadow-board was established by measuring and comparing irradiance of a single lamp through four different-diameter

Figure 2- Schematic of "Shadow Board" idea

holes. The output of the shadow-board is compared to the output of the lamp with a white collimating tube in Figure 3. The data show that the vertical irradiance profile of a shadow-board with $x = 0.15\text{m}$, $y = 1.11\text{m}$, is identical to that of a white collimator tube with radius equal to x and length equal to 1.22m . In both cases, lamp face-to-collector distance is 3.35m . The insensitivity of the irradiance profile to the variables x and y is illustrated in Figure 4. It can be seen that the output is virtually identical for the four hole radii (x) tested at $A = 2.90\text{m}$.

Figure 5 shows an irradiance flux map of a single lamp using the shadow-board. These data are obtained with $A = 3.05\text{m}$, $x = 0.15\text{m}$, and $y = 1.02\text{m}$. With this arrangement, a square array of four by seven lamps results in an average irradiance of 1048 W/m^2 with a uniformity of $\pm 10\%$.

ICS Progress Report

Description of ICS System Test Facility

The ICS system test apparatus consists of a cold water supply preparation system, the collector and solar storage tank to be tested (in our case this is one unit--the NEG ICS), an auxiliary water heater, and a load and calibration tank at the hot water supply outlet.

The cold water supply preparation system, shown in Figure 6, consists of two water storage tanks with heating elements, a recirculation pump, and necessary instrumentation to insure good temperature control. The system is capable of supplying water at a specified temperature to within $\pm 1^\circ\text{C}$.

The collector is mounted on a stand capable of rotating about both vertical and horizontal axes.

The data acquisition and test control system consists of a 386-based microcomputer, a 12-bit A/D board and necessary relay I/O boards to control system pumps and valves. The program, which is an adaptation of a Basic code written in 1989 to operate the Generic Systems Test Facility at CSU, interfaces with the data acquisition hardware and automatically records data (temperatures and flow rates) at specified intervals. The program also monitors the equipment for proper operation, and shuts the system down if an unsafe condition arises. Test procedures are written into batch files and run automatically without user input. Visual displays of the system operation are available at user request.

The collector has been instrumented, as shown in Figure 7, to measure temperatures both inside the tubes and on outside pipe walls of the manifold. Two thermocouples are mounted in one center tube--one near the top, the other near the bottom--and one thermocouple is mounted in the middle of the adjacent center tube. A novel approach was required to install thermocouples in the storage tubes. The thermocouples used were made by Omega, and are set in insulating ceramic, encased in steel. The two outer tubes were cut from the manifold and slid off of the small diameter inner tube (cold water inlet). The thermocouples were mounted on a hinged arm secured to the inner tube, and laid flat while the outer tube was slid back over the inner supply tube. Once the outer tube was back in place, the thermocouple casings were pulled straight, raising the hinged arm so that the tip of each thermocouple

Figure 3 Comparison of the vertical irradiance profile of a 0.3m diameter x 1.22m long white tube to the profile obtained with a shadow-board located 1.11m from lamp with a 0.3m diameter hole. Lamp-to-collector distance is 3.35m. As expected the output is identical.

Figure 5 Irradiance (W/m^2) flux map of a single 1000W CSI Lamp measured from a distance of 3.05m. A shadow board with a 0.30m diameter hole centered on the bulb was placed 0.96m in front of the lamp. The grid spacing is 55.5mm. The data from this flux map was used in a computer simulation to show that an array of four by seven lamps results in an average irradiance of 1048 W/m^2 with a uniformity of $\pm 10\%$. The irradiated area is 1.22m x 2.44m.

FOR THERMOPILE INTERCONNECTION DETAIL SEE DRAWING 88021702
FOR LIGHTING CIRCUIT SEE DRAWING 88021703 & 88021704
FOR CONTROL SCHEMATIC (LADDER DIAGRAM) SEE DRAWING 88021705

SYSTEM CONSISTS OF TWO
BANKS OF FOUR ICS COLLECTORS.
(INDIVIDUAL ICS*
SHOWN FOR CLARITY).

Figure 6

[illegible]

Fig 7 NEG SUN Family Collector

is well into the flow. The outer tube was soldered back to the manifold. Six regular T-type thermocouples are installed on the outside of the manifold, one between each set of four inlets and four outlets to the collector tubes.

The testing plan for determining the overall loss coefficient (UA) of the system has been implemented in the software.

Tank Stratification with a Flexible Manifold

Introduction

Both experimental (Fanney and Klein, 1988; Davis and Bartera, 1975; Lavan and Thompson, 1976; Wildin and Truman, 1989) and analytical (Wuestling, 1983; Sharp and Loehrke, 1979; Jesch and Braun, 1983) research show that the level of stratification in a solar storage tank is a critical factor in designing an effective solar hot water system. The purpose of this study is to experimentally determine the level of tank stratification that can be maintained using a constant, forced flow strategy for circulating water.

Methods of increasing stratification include: operating the system with flow rates low enough to only turn over the storage tank once a day (the "single-pass" strategy), isothermal operation, and use of stratification enhancing distribution manifolds. Wuestling (1983) predicts that a constant flow system with a fully stratified storage tank will outperform similar systems using variable volume storage and/or constant outlet temperature control strategies. Single-pass control strategies are very promising in terms of tank stratification, but low flow rates can reduce collector performance.

The most thorough studies on stratification enhancing return tubes have been conducted at Colorado State University (Loehrke *et al.*, 1979; Gari and Loehrke, 1982; Carlson, 1990). Design of these devices is based on matching the pressure gradients of the manifold fluid and the tank fluid to prevent inflow or outflow from the manifold until the fluid returning from the collector reaches the location in the tank where tank temperature equals return fluid temperature. Most rigid porous manifolds include vertical resistance elements (orifice plates) which prevent mixing. Although some systems with rigid manifolds show improvements in energy output over similar systems with conventional inlet tubes (Fanney and Klein, 1988; Davidson *et al.*, 1992), this type of stratification manifold is difficult, if not impossible, to design to operate effectively over a range of operating temperatures and flow rates. Flexible manifolds are more promising because the pressure gradients in the tank and the manifold are matched continuously by variations in the cross-sectional area of the manifold. At points in the tank, where the pressure is higher in the tank than in the manifold, inflow is prevented because the manifold simply collapses. However, outflow is possible once the manifold fluid reaches the tank depth at which its density equals the tank fluid density. At this point, the manifold expands, and the fluid exits to the tank (Gari and Loehrke, 1982). Although there are preliminary data on this type of manifold operating in water tanks, performance data have not been obtained under realistic operating conditions. Nor have design guidelines specifying size and material selection been developed.

In this study substantial progress has been made toward establishing design guidelines and establishing the effectiveness of an orlon flexible manifold under varying operating conditions. Stratification levels of a storage tank operated with a conventional return drop tube, a rigid porous manifold and several flexible manifolds are compared.

Experimental Facility

The experimental facility, shown in Figure 8, is located in Solar House III of the Solar Energy Applications Laboratory. Components include: an insulated, clear plastic, 372-liter water storage tank, a 310-liter electric water heater used to supply variable temperature water to the tank (simulating collector return water in a direct system), and a cold mains water supply. The UA value of the solar storage tank is $3.0 \text{ W/}^\circ\text{C}$.

Tank stratification is quantified by measuring vertical temperature profiles. Twenty-one copper-constantan, special limit T-type thermocouples ($+(0.5^\circ\text{C}$ or 0.4 percent, whichever is greater)) are used to sense water temperature. Nineteen thermocouples are mounted in a thermocouple tree in the hot water storage tank. One thermocouple measures the temperature of water entering the storage tank, and one thermocouple monitors the ambient air temperature.

A turbine type flowmeter is used to measure the volumetric flow rate of the water entering the storage tank (calibration standard error = 0.0033).

Experimental Procedure

Three experimental testing schemes are used to determine how well each inlet design performs under different operating conditions. In each test, as water enters the storage tank from the inlet at the top of the tank, water is drained from the bottom of the tank at the same flow rate. Tank temperature profiles, inlet water temperature, and inlet flow rate are measured and recorded at one-minute intervals throughout the length of the test.

Scheme I is conducted with both constant inlet temperature (50°C) and flow rate (0.07 liters/s). The storage tank is initially filled with 15 - 20°C water. Test duration is 90 minutes, the time necessary to turn over the tank.

Like Scheme I, Scheme II is begun with the tank filled with cold water, and the flow rate is held constant at 0.07 liters/s. However, in order to simulate more realistic operating conditions, temperature entering the storage tank is varied. Inlet temperature is controlled as shown in Table 1. Test duration is once again 90 minutes.

Scheme I initial and final temperature profiles - conventional inlet

Figure 8

Table 1. Scheme II inlet temperature as a function of time.

<u>Test time(min)</u>	<u>Inlet temperature(°C)</u>
0 - 10	50
10 - 20	40
20 - 30	30
30 - 40	30
40 - 50	40
50 - 60	50
60 - 70	40
70 - 80	30
80 - 90	40

In Scheme III the upper half of the tank is filled with hot (50-55 °C) water and the bottom half is filled with cold (15-20 °C) water. Water is input to the tank at a constant flow rate (0.07 l/s) and a constant intermediate temperature (30-35 °C). The length of the test is 48 minutes which is sufficient time for the cold water to be removed from the tank (assuming no mixing occurs).

Results

Fabrics used to make flexible manifolds must withstand prolonged exposure to water at temperatures in excess of 60 °C. Most natural fibers are unable to retain their strength under these conditions. The synthetic materials used in this study (nylon, orlon, dacron) do not degrade when heated to 120 °C for long periods. The effect of water on the strength of these materials is also negligible. Cotton on the other hand begins to turn yellow after several hours at 120 °C and decomposes markedly at 150 °C. In addition, tensile strength of cotton declines markedly after prolonged periods of water exposure (Cook, 1964).

Preliminary study of thirteen fabrics (three cotton/polyester blends, six polyamides (nylon), three polyesters (dacron), and one polyacrylonitrile fiber (orlon)) operating under Scheme III identified a best choice manifold for further study. Manifold diameters of 7.3 cm and 8.9 cm were evaluated. In these preliminary tests, a 7.3-cm diameter orlon manifold produced the best tank stratification.

The importance of properly selecting the manifold fabric cannot be overemphasized. In general, the materials which perform most effectively are those which are easily stretched in both directions. This property is associated with double-knit fabrics. For all practical purposes, woven fabrics do not stretch and are thus unsuitable for stratification manifolds. In an effort to quantify the physical properties of fabrics that work well, bursting strength of two fabrics that worked well were measured according to ASTM standard procedures and compared to bursting strengths of two fabrics that did not result in tank stratification. Results are shown in Table 2. Low bursting strength of the two best materials is not a cause of concern, since the forces on a manifold due to its expansion as water flows from the manifold into the tank are small relative to the fabric's bursting strength. Woven fabrics with high bursting strength do not expand and contract enough to control flow into and out of the manifold. Other properties of fabrics which may be of interest include porosity, elongation and elastic recovery.

Table 2. Bursting Strength

<u>Material</u>	<u>Bursting Strength (lbs)</u>	<u>Strati- fication</u>	<u>Comments</u>
Spun double-knit orlon® Type 42 (S/860)	42	good	Visibly contracts and expands
Double-knit cotton- polyester blend	69	good	Visibly contracts and expands
Texturized, double-knit jersey dacron® 56 (S/720)	160	poor	No visible change
Texturized, double-knit nylon (S/314)	175	poor	No visible change

Tank temperature vertical profiles of the tank operating under Schemes I, II and III with a conventional drop tube, the rigid porous manifold, and the orlon flexible manifold are compared in Figures 8 through 16. These figures show tank temperature profiles at the beginning of each test and at the end of the testing period. The ordinate of each plot is a dimensionless tank height H equal to distance from the bottom of the tank divided by total tank height (1.22m). Inlet temperature from the simulated collector to the tank is indicated for both constant temperature operating Schemes I and II.

In all cases, tank stratification is greatest with the flexible manifold. Numerous parameters have been suggested to quantify the degree of tank stratification. However, previously suggested parameters fail to rank the choices relative to either the maximum possible level of stratification or to a totally mixed tank. We are currently in the process of developing a dimensionless parameter which accomplishes such a ranking and may also be used to compare stratification when draws are considered.

For now, the best method of comparing the various tank inlet options is to compare the energy stored in the tank at the end of the testing period as compared to the initial energy level. The differences in performance of the three inlet designs is most apparent in the data obtained from the Scheme III tests in which the tank was initially thermally stratified in two layers and then water was introduced at an intermediate temperature. The data of Figure 14 indicate that with the conventional inlet, the tank is completely mixed at the end of the test. With the rigid manifold, some level of stratification remains in the upper quadrant of the tank. Remarkably, under the same operating conditions, the flexible manifold maintains nearly perfect stratification even with a relatively high flow rate.

This study will be completed by December 1, 1992.

Scheme I initial and final temperature profiles - rigid manifold

Figure 9

Scheme I initial and final temperature profiles - orlon flexible manifold

Figure 10

Scheme II initial and final temperature profiles - conventional inlet

Figure 11

Scheme II initial and final temperature profiles - rigid manifold

Figure 12

Scheme II initial and final temperature profiles - orlon flexible manifold

Figure 13

Scheme III initial and final temperature profiles - conventional inlet

Figure 14

Scheme III: initial and final temperature profiles - orlon flexible manifold

Figure 16

ADVANCED SOLAR DOMESTIC HOT WATER (SDHW) SYSTEMS

Research Team: Dr. William S. Duff, Task Leader
Dr. George O.G. Löf, Senior Advisor
Dr. Jane H Davidson, Faculty
Charles Smith, Research Staff
Arun Menon, Graduate Research Assistant

Background:

A research project funded by the Department of Energy to identify, analyze, design, build, and experimentally evaluate advanced SDHW systems is currently underway at the Colorado State University Solar Energy Applications Laboratory. The objective of this project is to substantially lower costs and improve performance of SDHW systems that are commercially viable in the United States. As a means of identifying many promising materials, components, and concepts, this project is participating as the United States SDHW installation in the International Energy Agency (IEA) Task on Advanced Solar Energy Systems (Task XIV). Results from the project, as well as results from the IEA Task XIV activities, will be disseminated to the United States solar energy industry.

Research Program:

This is a multi-year research project which is programmed through the end of 1994.

A number of SDHW systems designs will be optimized for low initial cost, high performance, high reliability, low maintenance, and low operating cost. Component sizing, freeze protection, overheating prevention, material selection, good practice in overall system integration and operation, and consumer acceptance are addressed.

Experiments will be performed both indoors, in the Colorado State University solar simulator, and outdoors. Component and system performance prediction models will be developed and/or validated, as appropriate, by the experiments. The resultant models will be used to extrapolate performance to different climates and to variations on component and system designs.

Progress:

Experimental evaluation activities of this project were programmed to begin in early summer 1992. The initiation of the experimentation phase of the project was contingent on a capital equipment grant from DOE. The DOE capital equipment funding that was provided to Colorado State University was inadequate to fund the Generic Systems, heat exchanger/storage interaction, and Advanced Solar DHW Systems work. An agreement was reached between the SEAL director and DOE to allocate the DOE capital equipment grant funds to the Generic Systems/solar simulator and heat exchanger/storage interaction work and to provide adequate funds to accomplish the Advanced Solar DHW work as a first priority in the subsequent DOE/SEAL contract that is to begin March 1, 1993.

It was then decided to go forward with a modest variant of the Advanced Solar DHW System experimental activity with provision of an additional small

sum (\$1500 to \$2500) for construction of three side-by-side solar DHW systems and for basic instrumentation and limited data acquisition.

The three systems being addressed by modeling and experimentation through February 1993 are marked by an asterisk (*). Systems that are expected to be added for the March 1993 through February 1994 contract period are indicated by a double asterisk (**).

- o American Solar Network (ASN) SDHW system with load side internal heat exchanger and unpressurized storage (*)
- o Cost/Performance Optimized version of ASN SDHW System (**)
- o Optimized Matched Flow (MF) (SDHW systems where the flow to the solar storage is matched to the load and storage volume) version of the ASN SDHW System
 - o Collector Side Internal Heat Exchanger and Conventional Pressurized Storage
 - o Variable Flow Strategy (**)
 - o Constant Low Flow - No Stratification Enhancement Device (*)
 - o Constant Low Flow with Stratification Manifold (**)
- o American Energy Technologies (AET) or SunEarth Conventional SDHW System (**)
- o Cost/Performance Optimized Version of AET or SunEarth Conventional System
- o Optimized MF version of the AET or Sun Earth SDHW System
 - o Side Arm Heat Exchanger (**)
 - o Internal Heat Exchanger
 - o Variable Flow Strategy
 - o Constant Low Flow - No Stratification Enhancement Device
 - o Constant Low Flow with Stratification Manifold
 - o Wrap-Around Heat Exchanger
 - o Mantle Storage (**)
- o Thermodynamics Micro Flow SDHW System (*)
- o SDHW Systems from Other United States Manufacturers
 - o Conventional System
 - o Cost/Performance Optimized Versions
 - o Optimized MF Versions
- o Integral Collector Storage (ICS) System (*)
- o Copper Cricket (**)
- o Solar Hart (**)

A Thermodynamics solar DHW system has already been obtained through donation, and donations of the ASN and integral collector storage systems have been solicited. The limited experimental program is scheduled to start with installation of the three systems in October 1992.

Additional simulation models of the solar DHW systems have been built and validated with experimental data, and additional cases using Monte-Carlo three-dimensional/constructive solid geometry have been run for the integral storage collector. Results and anticipated results are detailed in the attached abstracts of papers submitted for presentation at the February 1993 ASES/ASME/Soltech Conference.

Other accomplishments relate to the International Energy Agency Solar Heating and Cooling Program Advanced Solar Energy Systems Program. Details for these activities are attached.

EFFECT OF BACK PLANE DIMENSIONS AND OTHER DESIGN FEATURES ON INTEGRAL COLLECTOR STORAGE EVACUATED TUBE COLLECTOR PERFORMANCE

William S. Duff
Arun Menon

Solar Energy Applications Laboratory
Colorado State University
Fort Collins, Colorado

ABSTRACT

This paper deals with the performance of an integral storage evacuated tube collector (ICS-ETC). The ICS-ETC, because of the tubular cover and absorber geometry, has incident angle modifiers (IAM) that are substantially greater than one for many radiation incidence angles. In contrast, flat plate collector IAM's are less than or equal to one at all radiation incident angles. Thus it was thought essential to establish the effects of other design details on optical performance.

Three-dimensional Monte Carlo ray tracing is used to determine the optical performance of these asymmetric solar collectors, with constructive solid geometry (CSG) being used as the means for modeling the collector shape. The ray tracing algorithm involves the tracing of individual photons through the geometry, and thereby provides a means of obtaining the fraction of absorbed radiation. CSG allows the generation of complex collector shapes by means of combining simple primitive objects.

It has been found that the performance of such a collector is significantly enhanced by the use of a diffuse reflecting surface behind the collector tubes. Inter-tube spacing and the number of tubes also plays a part in the edge-tube and shading effects. In order to determine advantageous geometries for a given collector configuration, the effects of the following were investigated:

- o back plane reflectance
- o back plane width
- o inter-tube spacing
- o back plane-tube spacing

It was found that each of the above factors significantly affects the performance of ICS-ETC's. For instance, reflector design can improve performance by more than 30 percent. The paper details this and other factors that can be used effectively in the design of such collectors.

MODELING AND VALIDATION OF INTEGRAL COLLECTOR STORAGE EVACUATED TUBULAR COLLECTOR PERFORMANCE

William S. Duff

**Solar Energy Applications Laboratory
Colorado State University
Fort Collins, Colorado**

ABSTRACT

An integral collector storage evacuated tubular collector (ICS-ETC) is modeled using a lumped capacitance approach. Daily performance is then calculated for two versions of the ICS-ETC system and several sets of real weather data from two different locations by means of simulation using biaxial incidence angle modifiers (IAM). Results are compared to the actual performance of the ICS-ETC during the same time periods.

The two versions of the ICS-ETC are the original NEG Sun Family solar DHW system marketed in Japan and the current Sun Family system marketed in the United States and Japan. The two versions differ mainly in the fluid inventory in the manifolds and the manifold insulation. Data sets for weather and actual ICS-ETC system experiment and test performance come from the Florida Solar Energy Center in Cocoa Beach, Florida and Colorado State University in Fort Collins, Colorado.

The simulation is ISFH from the Institute für Solarenergieforschung. The ISFH simulation uses a detailed component type TRNSYS-like approach for detailed performance analyses and a day-by-day approach for accurate fast performance prediction based on regression models established by the detailed simulation. The ICS-ETC IAM's are developed by means of a ray tracing and constructive solid geometry approach developed by Duff, Knappmiller, and Menon.

Simulation model predictions compare within a few percent to experiment and test performance in most cases.

INCREASED AVAILABILITY OF RADIATION FOR INTEGRAL COLLECTOR STORAGE EVACUATED TUBE COLLECTORS

**William S. Duff
Arun Menon**

**Solar Energy Applications Laboratory
Colorado State University
Fort Collins, Colorado**

ABSTRACT

The increased availability of radiation for integral collector storage evacuated tube collectors (ICS-ETC) over flat plate collectors (FPC) is determined. The ICS-ETC is modeled as a rectangular box with four active surfaces for accepting insolation as compared with just one active surface for the FPC. Available radiation on each of the four modeled surfaces (front, back, and the two sides) is calculated and the sum of these provides an estimate of the available radiation for an ICS-ETC. The radiation available on a FPC is that on the front surface. The analysis was performed on a monthly and hour-by-hour basis for different cities with different latitudes and climates and for different collector orientations.

A daily (hour-by-hour) analysis allows comparison between good and bad days, while a monthly analysis allows determination of the effects of seasonal variation. The orientation of the collector was also varied by using different combinations of the collector slope and surface azimuth. The ground reflectance was also varied. The results were compared with those obtained using the ISFH simulation program (Institut für Solarenergieforschung, Hanover, Germany), using two different radiation processors (Liu & Jordan and ISFH2). Typical results show a 40 to 90 percent increase in available radiation for an ICS-ETC over a FPC.

The Klein and Theilacker (K-T) method is used to determine the average daily or monthly radiation on the surfaces. The K-T model assumes that both sky and ground-reflected diffuse radiation are isotropic. Circumsolar radiation and horizon brightening, not accounted for in the K-T model, could be accommodated in the approach of this paper by using a more elaborate daily radiation model.

COLORADO STATE UNIVERSITY UNITED STATES TASK XIV ACTIVITIES

Task Activities from January through July 1992:

EPDM Absorber: A UV-protected polycarbonate collector with an EPDM absorber has been on the market for four years. The passive system designed into the collector vents the collector at temperatures above about 55 C above ambient. Above these temperatures outgassing of EPDM oils will occur. These oils will collect on the polycarbonate glazing, but will eventually go away after five or six months. With each outgassing cycle, the amount of oils released becomes less and less. The EPDM absorber can undergo hundreds of outgassing cycles without deterioration. The passive venting system will prevent outgassing. At the operating temperatures of the vented system, the inexpensive EPDM absorber has been judged by the Solar Rating and Certification Corporation (SRCC) to be durable beyond the SRCC 15-year lifetime requirement.

A fin efficiency factor of 0.682 is obtained using a heat conductivity factor for EPDM of 0.132 W/m-K , a fin thickness of 0.8 mm, a collector overall heat loss coefficient of $8 \text{ W/m}^2\text{K}$, a tube-to-tube centerline distance of 18 mm, and a fin width of 9 mm. The inner diameter of the EPDM tubes is 0.5 mm. For laminar flow the fluid-to-tube wall heat transfer coefficient is taken as $100 \text{ W/m}^2\text{K}$, giving a collector efficiency factor of 0.781. For highly turbulent flow, the fluid-to-tube wall heat transfer coefficient is taken as $1000 \text{ W/m}^2\text{K}$, giving a collector efficiency factor of 0.835. For a fluid-to-tube wall heat transfer coefficient of $100 \text{ W/m}^2\text{K}$, the collector efficiency factor is 0.820. For a copper absorber plate 0.4 mm thick, tube spacing of 50 mm, tube outer diameter of 0.7 mm, tube inner diameter of 0.5 mm and the rest of the dimensions the same, the fin efficiency factor is 0.985 and the collector efficiency is 0.788 for laminar flow and .961 for highly turbulent flow.

Polycarbonate Cover: Lexan, the trade name for General Electric polycarbonate material, begins to melt at 135 C. The passive venting system restricts operation of the collector to temperatures far below this. An ASTM durability test was applied to a 15-year-old Orlando UV unprotected skylight. In the ASTM test, a 4.5 kg metal ball was dropped from above the normal testing height of 2.1 m, a height that would destroy many other plastic materials, without damage to the skylight. General Electric UV protected polycarbonate is guaranteed for full clarity for ten years and is expected to retain full clarity beyond 15 years.

Heat Exchange, Flow Control, and Stratification: Internal helix and wrap-around heat exchangers and photovoltaic-driven pumping are currently under investigation. Both modeling and experimentation are being conducted. The Generic Systems indoor test facility is being converted to accommodate the tank/heat exchanger combinations. A flow visualization tank with instrumentation for flow rates and layer temperatures has been built. The investigations are still at a preliminary stage.

Integral Collector Storage Modeling: An ISFH-based simulation of the Sunfamily tank-in-evacuated tube integral collector storage SDHW system (ICS-ETC) has been developed. The SDHW subsystems designs were translated into analytical performance prediction models using the ISFH collector, storage, and piping design routines, a tank mixing model for determining storage temperatures during draws, a thermal loss analysis based on collector

manifold geometry, and a solid modeling-based ray tracing routine for determining incidence angle modifiers. The model was validated against two sets of data: the one acquired by FSEC in 1992 and another by Colorado State University in 1987. The various analytical tools and simulation can be used to determine the performance of various size Sunfamily systems in different climates and under differing loads, as well as the impact of design changes and mounting options on performance. I will bring some results to the meeting.

Integral Collector Storage Overnight Losses: The NEG Sunfamily ETC-ICS system has been tested by two official United States Solar Rating and Certification Corporation laboratories: the Canadian National Solar Test Facility, Ortech near Toronto, and the Florida Solar Energy Center (FSEC). Ortech performed its test in 1991 and, due to several problems, an acceptable rating was not obtained. Ortech's thermal loss test produced a thermal loss coefficient of 5.2 W/K for the two-module Sunfamily product. FSEC tested the Sunfamily ICS-ETC in early summer of 1992. The test indicated excellent performance and an official rating is expected shortly. Data from the initial four-day FSEC test was obtained, including the outlet temperature profiles during draws. A two-node tank mixing model with unequal node volumes produced a good match for the outlet temperature profiles. The mixing model was used to establish the average temperature of the tank after the last draw of the day (17:40), which took place after energy collection had ceased. The difference between this value and the tank temperature before collection and draw the next morning (8:00) was in turn used to calculate the overnight losses and validate the previous thermal loss coefficient estimate. Using this estimate of the thermal loss coefficient and an overnight ambient temperature of 21.1 C, the following the overnight losses were calculated:

Date	Energy Collected (MJ)	Temperatures (C)		Overnight Losses (MJ)		
		8:00	17:40	Calculated	5.2 W/K	Difference
3/2/92	48.6		80.5	8.02	8.00	-0.02
3/3/92	46.1	35.2	79.4	8.87	7.32	-1.55
3/4/92	33.6	32.6	66.9	4.53	6.05	+1.52
3/5/92	31.1	31.5				

Integral Collector Storage Load Timing: Some load timing results are given below for a 227 liter daily draw in Miami:

Draw Pattern	Energy Collected (MJ/m ² -day)		
	Boston	Miami	Albuquerque
All at 8:00	7.1(-4%)	9.9(-8%)	11.1(-9%)
In Thirds at 8:00, 12:00, and 17:30	7.4	10.8	12.2
All at 17:30	9.3(+26%)	11.9(+8%)	13.9(+14%)

Task Activities Planned for the Next Six Months:

Integral Collector Storage Incidence Angle Modifiers: The effects of tube spacing, reflector design, and material properties on optical and thermal performance will be assessed.

Thermodynamics Microflow SDHW System: The system will be installed and evaluated.

American Solar Network SDHW System: The system will be installed and evaluated.

NEG Sunfamily Integral Collector Storage SDHW System: The system will be installed and evaluated.

**SUMMARY OF ACCOMPLISHMENTS AND LESSONS LEARNED
TASK XIV ADVANCED SOLAR DOMESTIC HOT WATER WORKING GROUP
FOR JANUARY THROUGH JUNE 1992**

William S. Duff, Working Group Leader

1. COLLECTOR AND ABSORBER

The efficiency of the Netherland's low flow absorber has been optimized on pipe diameter, serpentine configuration, and fin efficiency factor. The 6 mm diameter tubing seems to give the best results. This design has no problem draining down. The cost/performance ratio of this collector is better than that of conventional collectors.

The properties of the ASN system's EPDM absorber and polycarbonate cover and aspects of its passive venting features were reported by the United States. The passive venting system will reliably prevent outgassing of EPDM oils and deterioration of polycarbonate cover. The EPDM absorber is durable beyond 15 years. Collector efficiency factors of 0.781 for laminar flow and 0.835 for turbulent flow were determined. Additional detailed justification was brought to the meeting and made available to the participants.

Switzerland felt that the matter of coatings and substrates was not part of the Task XIV work. Therefore, no report was made. Bilateral discussions are welcomed.

Switzerland has used a MTI absorber. There was some consideration to making a fin-tube absorber by an extrusion process. The had group expressed concern that this will lead to much too high material content and therefore a too high a price. The status of this item was not reported.

2. PIPING

The Netherland's piping investigation is not complete. An 8 mm ID has been selected. Price and durability criteria are being applied to find a better alternative to steel and copper tubes.

Germany examined different concepts of lifeline piping, focusing on the mixing of cold supply and hot return. First conclusions show the Canadian design to be quite adequate.

Canada's Thermodynamics has had problems with the "old" lifeline tubing with temperature and pressure exceeding the allowed limits. Copper tubing is being used until a suitable alternative can be found.

3. STORAGE TANK/HEAT EXCHANGER

A study on mantle and helix heat exchangers was carried out by the Netherlands. No significant differences in efficiencies were found.

The Netherlands is concerned about the destratification of tanks observed in Switzerland's tests. It is felt that the major cause for a lack of more than modest efficiency improvements in the matched flow systems is substantial mixing in the bottom of the tank. Before conducting side-by-side tests on various matched

flow systems, researchers feel it is essential to improve storage so as to achieve optimal stratification.

Denmark developed and validated a computer simulation model for the mantle tank system. Annual performance of different matched flow designs was calculated. Side-by-side tests of the mantle, helix, and side-arm tank/heat exchanger combinations was carried out. Experience from the operation of matched flow systems was described. Maximum temperatures of matched flow systems for the summer holidays have been calculated. The Thermodynamics system was installed and testing on it began.

Denmark feels that an "ideal" storage/heat exchanger combination can increase performance of a currently marketed system by 20 percent. Cost and reliability should be the primary considerations in design of matched flow storage. Matched flow systems can operate with high performance and reliability in normal use, but optimum design and installation is necessary. A small thermal bridge and a high flow rate when high temperatures are reached are measures that can reduce the problem of overheating.

In the United States efforts had been planned to examine the impact on performance of internal helix and wrap-around heat exchangers and stratification manifolds. A new investigation of an existing ASN-based system with an unpressurized storage and load side heat exchanger will replace the internal helix activity. This system will be tested with and without the Colorado State University stratification manifold.

Switzerland is testing two normal flow and two matched flow designs. One of the matched flow systems uses the new Swiss heat exchanger/stratification device. The first phase of the testing revealed no significant difference among the two matched flow systems and the base case normal flow system. The three systems were within four percent. The other normal flow system, the Zonne system, showed decidedly lower performance.

Germany observed problems with the general system design and component behavior in side-by-side testing of a matched flow and normal flow system. The six-square-meter collector areas originally used caused significant recirculation. Reducing collector areas to three and one-half square meters caused unstable flow in the external heat exchanger with consequent lowered heat exchanger UA values. At the lowered mass flow rates the stratification manifold seemed unable to transport hot water through the cold tank layers without mixing.

4. AUXILIARY

The Netherlands carried out further work on the development of an integrated gas auxiliary. Since this activity is not a formal part of Task XIV, details cannot be reported.

5. PUMP

The Netherlands has collected sufficient information on the Bosch pump to be close to a recommendation for using it in matched flow applications.

Canada has completed phase I of the work. The new eight-ampere amplifier was built and tested. The pump was hydraulically tested at SCL at Queens University. Its approximate power consumption was measured.

Phase II has started for Canada. The pump and controller designs are essentially finished. In many cases the design minimizes parasitic power losses

and back leakage by having one component perform two functions. Calculations indicate that five watt operation is possible, but the power budget is tight.

The United States is still interested in testing the intermittent pump concept that the Netherlands investigated.

6. CONTROL UNIT

The control study has provided the Netherlands with sufficient information to adapt existing control units to the matched flow principle.

Canada explained the fundamentals on which its control algorithm is based, as well as some of the implementation considerations.

United States work on radiation switching, variable flow, and control strategies has been slowed by reduced funding and the diversion of effort to support the development of the new United States rating and certification activity.

The level of collaboration in this activity has not been defined.

7. MEDIUM

The Netherlands will be using water and eight-mm ID piping.

The United States obtained and circulated an article on the use of potassium carbonate. Potassium carbonate is still seen as a viable option.

8. SYSTEM

Because many systems issues are addressed as part of the component discussions, please see the sections above.

Canada provided the ThermoDynamics system to Denmark, the United States, and the Netherlands for testing.

An issue that is germane to system performance reporting is the fact that there are two different definitions of solar fraction being used. One was to divide the difference between load and auxiliary energy by the load. The other was to divide solar delivered by the sum of solar and auxiliary. The different measures of performance may lead to different conclusions. If two tanks are used, solar storage plus the conventional DHW tank, as is commonplace in North America, the options become even more varied.

In its testing of four systems, Switzerland found the values of the two solar fraction definitions to be within four percent. This is a smaller difference than was presumed.

9. DAILY AND DAY-TO-DAY LOAD PROFILES AND SENSITIVITY ANALYSES

In its status report, Germany provided an example of a day-to-day load variation situation where a matched flow system would perform worse than a normal flow system.

The issue of the effects of day-to-day SDHW load variation on the optimum design of conventional and matched flow systems has not yet been completely resolved.

10. FORMAT AND REPORTING

A subgroup was assigned to develop mandatory explicit definitions of system and subsystem performance parameters so as to enable unambiguous communications when reporting results within the Task. The results of the subgroup's efforts is to be incorporated into the Task XIV Monitoring Guidelines.

11. CONCEPT TXIV MATCHED FLOW

Most of the of participants' contributions on what they concluded to be the most desirable specifications for an ideal matched flow system were sent to the United States and the Netherlands in time to be evaluated before the Hameln meeting. The concepts differed so substantially that it was not possible to assemble them into one or two systems. Thus, a comprehensive listing of submitted concepts and components was distributed to the Working Group Participants.

For the Hameln meeting, Switzerland presented an interesting ideal matched flow concept involving an unpressurized storage and a load side heat exchanger.

12. TASK XIV MATCHED FLOW SDHW SYSTEMS REPORT

It is expected that the matched flow technical work will be finished within one year and that the participant contributions to the report will be submitted within one and a half years. The report will be directed toward the solar industry and will be structured to address the issues of greatest interest to industry.

Outline for Matched Flow Report:

- i. IEA SHAC Program
- ii. Task XIV
- iii. Advanced SDHW Subtask
- iv. Subtask Participants
- I. Matched Flow Explanation
- II. Objectives
- III. Approach and Rationale
- IV. Results

For Each Important Component, Subsystem, and Concept --

Component: For Example, Pump or Mantle Heat Exchanger

Diagram:

Analysis:

- o Experiments
- o Modeling

Lessons Learned

V. Conclusions

Appendices:

Task XIV Matched Flow Systems

Task XIV Reference Systems

Participant Summaries of Their Research

- A. The Netherlands
- B. Switzerland
- C. Canada
- D. Denmark
- E. Spain
- F. The United States
- G. Germany

13. COPPER CRICKET COOPERATION

The United States and the Netherlands are interested in cooperating on an investigation of the Copper Cricket SDHW system. A bilateral project has been started between the United States Sage Corporation and the Netherlands with testing of alternative components. There is interest at Colorado State University in testing these systems. However, United States funds are limited.

14. INTEGRAL COLLECTOR STORAGE SOLAR DHW SYSTEMS

The Netherlands presented a paper reporting on its modeling and testing of a German ICS system.

The United States presented results for modeling load timing for Boston, Miami, and Albuquerque and overnight losses based on an FSEC test in Florida for the tank-in-evacuated tube integral collector storage solar DHW system.

15. SPANISH PARTICIPATION IN THE ADVANCED SOLAR DHW WORKING GROUP

Spain will prepare documentation on its candidate advanced solar DHW system using the Task XIV Format. The documentation is to be received by the other Advanced Solar DHW Working Group participants by December 1, 1992. Based on the documentation, Spain's entry into the Advanced Solar DHW Working Group will be formally acted on at the next Task meeting.

16. TESTING AND CERTIFICATION

Art Brooks will distribute the OG300 document to the Advanced Solar DHW Working Group Participants.

LIQUID DESICCANT COOLING SYSTEM DEVELOPMENT

Research Team: Terry G. Lenz, Task Leader
Shailesh Potnis, Graduate Research Assistant

Background:

The long-term goal of our cooling research is to develop low first-cost, low operating-cost, dependable, solar-driven, liquid-based cooling systems. At Colorado State we have substantial background in both absorption chiller and open-cycle liquid desiccant research, so that we can realistically pursue the above long-term goal.

Objective:

Primary objectives of this project include the development, testing, and performance evaluation for a liquid desiccant cooling system on Solar House II at Colorado State. Our existing experimental cooling system comprises solar collectors, two simple packed-bed contactors (a dehumidifier and a regenerator), heat exchangers, blowers, pumps, air pre-conditioning equipment, and data-acquisition hardware.

Work Plan:

1. Complete the TOH water diffusivity laboratory studies for concentrated aqueous LiBr solutions.
2. Complete the regenerator mass transfer studies.
3. Analyze the mass transfer/diffusivity data to obtain dimensionless mass transfer relations.
4. Begin installing final heat exchangers, duct work, and auxiliary equipment for Solar House II cooling capability.
5. Provide quarterly progress reports and a final technical report for our liquid desiccant system task.

Progress:

Water Diffusivity Studies

To convert the results of the condensation rate and evaporation rate studies into the form of dimensionless numbers such as the Sherwood number and the Reynolds number, it is essential to obtain the diffusivity of water in LiBr solution. Experiments are being conducted to determine this diffusivity at different concentrations of LiBr solution.

A constant temperature bath (Haake, Model D8-G), with temperature control accuracy of $\pm 0.02^\circ\text{C}$, was purchased to maintain a uniform temperature in the diffusivity apparatus and eliminate thermal diffusion.

The diffusivity apparatus was designed using the specifications discussed in earlier reports. The precision capillary used to join the two flasks was purchased from Wilmad Glass. Pyrex glass was used as the material of construction for the two flasks.

After carrying out the preliminary runs, some changes were made in the apparatus [Figure 17] and the procedure. Teflon stoppers were used in both the flasks instead of only one flask to allow stirring, to prevent leakage of TOH in the capillary and to permit determining the precise time of diffusion. Air-tight Teflon caps were employed instead of plastic caps to prevent contamination of bath water due to vapors from the apparatus. It was also observed that the air column trapped between the Teflon cap and the solution in the tube above the flask helps to prevent bulk flow. An extra 10 μ l of water was added to the flask containing LiBr solution in pure water, to flush the capillary initially. Since this volume is negligible (0.1%) compared to the volume of the entire apparatus, this addition does not cause any significant disturbance. However, the added volume helps in preventing the bulk flow and leaks in the capillary. Total radiation activity to be used per experiment was reduced from 2 MBq to 0.37 MBq due to the limitation of counting capacity of the Liquid Scintillation Counter. Use of this reduced activity was found to give reliable and sufficiently high readings after a corresponding increase in the duration of the experiment (from 7 hours to 20 hours).

Using the modified apparatus and following the new procedure, water diffusivities were determined for concentrations ranging from 0.5M to 10M, at 25°C. Their comparison with the published results is given in Figure 18. However, as these results are very sensitive to leaks, bulk flows, stopper movements and mixing, additional experiments are being conducted to reproduce and confirm these results.

Structured Packing Studies

The height of the structured packing in the dehumidifier was increased to 22 inches by stacking a layer of packing above the earlier packing. The packings were arranged to give cross flow and obtain efficient mixing. The nozzle manifold was turned up with only the nozzles facing down to maintain the distance between the nozzles and the packing constant. Condensation rate studies were carried out with this increased height of packing, and the slope of the graph of condensation rate versus the solution flow rate was found to be 0.82 [Figure 19]; this was very close to the values obtained for the earlier packings (0.8). This value of the slope also suggested that the dehumidifier was again operating under well-mixed, nearly turbulent conditions for the liquid flow, as was determined earlier for random packings. However, the condensation rates were found to be significantly higher ($\approx$ 50%) than those obtained with the structured packings of one-foot height and lower than ($\approx$ 50%) than those obtained from the random packings of one-foot height.

The Wilson's plot obtained from this graph was again found to be a straight line with intercept 0.0032 [Figure 20]. This small value of the intercept again suggests that the gas phase mass transfer resistance was negligible, as it was for the earlier random packings studies and the Lewis number was greater than one, unlike that for the air/water operations.

Structured packing (Munter's CELDEK) was next installed in the regenerator, and the bed height was maintained at one foot to match the bed height of the random packing used earlier. Evaporation rate studies were carried out using these packings, and the slope of the graph of evaporation rate versus the solution flow rate was found to be 0.837 [Figure 21], which again was close to the value obtained for random packings (0.82). This slope also suggested that the regenerator was operated under well-mixed, nearly turbulent conditions for liquid flow. However, the values of the evaporation rates were found to be significantly lower than those obtained for the random packings (less than half).

Fig.17 Apparatus for measuring diffusion of water in LiBr solution

Figure 18.
Diffusivity of water in LiBr solution.

Figure 19

Figure 20

Figure 21

A straight line was obtained for the Wilson's plot constructed using this regenerator data [Figure 22] and the intercept was found to be 0.03. The value of the intercept suggests that the gas phase mass transfer resistance was negligible in the regenerator and the Lewis number was greater than one, unlike that for air/water operations and in agreement with our findings for the dehumidifier.

Figure 22

ANALYSIS OF ADVANCED SOLID DESICCANT SOLAR COOLING SYSTEMS

Research Team:

Dr. Douglas C. Hittle, Task Leader
Dr. George O.G. Löf, Senior Advisor
Ihsan Abbud, Graduate Research Assistant

Background:

Research on solar cooling with solid desiccant systems began with the ASK Energymaster unit in the summer of 1987. The first system employed a process known as the Pennington cycle. All of the conditioned air for cooling was supplied from the outside. It was dehumidified, and cooled by heat exchanger, then by evaporative cooling. This cycle exhibited the expected cooling capacity for the unit (3 tons), and a COP of 1.0. The following year an advanced cycle (SENC) was introduced which provides sensible cooling in the recirculated house air duct and yields a higher COP. The COP increased to approximately 1.5; however the capacity dropped substantially to the range of 1.0 to 1.5 tons.

The 1988 experiments were aimed primarily at increasing the capacity of the SENC cycle. The best available commercial cooling tower was not suited for this application. It provided too little residence time for the cooling water and wasted much of the dehumidifying effect provided by the ASK. The cooling tower was rebuilt with new packing, improved water distribution, and provisions for greater air and water flow adjustments. The duct cooling coil was also increased in size by 50 percent to better match the increased cooling tower capacity. Although these changes resulted in some improvement in the cooling capacity, the desired 3-ton target was not reached.

During 1989, important information was generated from an analysis based upon the tests of previous years [1]. The analysis employed a TRNSYS computer model with values of specific engineering parameters based on the actual equipment used in the experiments. This work revealed that some earlier modeling used unrealistic performance values for components and thus explained partially the shortfall in experimental performance. Most important, the analysis revealed some improvement recommendations which involve adjustments in air flow, cooling water flow, and desiccant wheel speed. It was also shown that the cooling capacity could be significantly increased with modest increases in regeneration temperature. A major item identified in this study was a shortfall in the experimental cooling tower capacity.

In August of 1990 a meeting of Colorado State, ASK, and Texas A&M experts was held to review the status of the solid desiccant cooling project and offer recommendations for its future course. The findings of the Colorado State analysis were confirmed by this group. Evaluation of the results showed, moreover, that the desiccant wheel had not been dehumidifying up to specifications, and that there had been physical loss of the desiccant material itself. The desiccant wheel was resupplied with the proper quantity of lithium chloride.

Wheel speed and air flow adjustments were also performed. These improvements were tested for short periods and only with respect to ASK unit performance (not the overall system performance), due to limited time and funding. These tests indicated that significant improvement in overall cycle performance is possible, both for the Pennington and SENC processes.

Based on these results we began to analyze and model advanced, high efficiency cooling cycles. During the prior grant period, we developed simulation models (using TRNSYS) for promising systems.

Proposed New Work:

During the current grant period, we propose to perform annual simulations of various systems in various locations (especially populated areas) to determine potential energy savings of desiccant cooling and to optimize system design.

Results from this work will help determine the market potential for solar desiccant cooling and allow us to set performance and cost goals.

Progress:

Progress of the solar cooling task between March and November, 1992 included the following:

1. Developed a TRNSYS model for a complete open solar solid desiccant cooling cycle (Pennington cycle-see Figure 22), utilizing:
 - a. Constant temperature (variable flow rate) solar collection strategy. The collection stops at + 5°C of the collector operating temperature of 88°C.
 - b. Flat plate solar water collectors.
 - c. Stratified tank that may be used down to - 5°C below the collector operating temperature.
 - d. Constant flow rate load pump.
 - e. BLAST simulated sensible cooling data of a residential building in Los Angeles, California.
 - f. Latent cooling data were scheduled, and it is ignored whenever the cooling system is off.
 - g. ARI conditions ratings, for outdoor ambient air of 35°C dry bulb temperature and humidity ratio of 0.0143 kg/kg, and indoor air of 26.7 °C dry bulb temperature and humidity ratio of 0.011 kg/kg.
 - h. High efficiency desiccant cycle components (evaporative coolers, heat exchanger wheel, counter flow heat exchanger, blowers .. etc.).
2. Optimization of some important parameters (regeneration/process flow rate ratio, regeneration temperature, coefficient of performance (COP)) of a 3-ton desiccant cycle using ARI conditions rating system mentioned above.
3. Normalized the desiccant system simulation so that cooling capacity is selected by specified supply air flow rate.

Figure 22. Pennington (Ventilation) Cycle.

4. Sized the solar system (i.e. collector area, tank size, pumps) on the basis that 50% of the seasonal energy needed for the desiccant system is supplied by solar energy for Los Angeles area. For this purpose, only the control scheme of paragraph 5a below was adapted to run the desiccant system.
5. Utilized two different control strategies to run the desiccant system through a cooling season in a Los Angeles building:
 - a. A simple ON/OFF controller actuated by room temperature. The whole desiccant air conditioning system runs whenever cooling is required.
 - b. A more complex controller, in which the desiccant wheel and energy source are used only when evaporative coolers and heat exchanger wheel can no longer meet the load.
6. The conclusion is that the control strategy in 5b improved the performance of the system, whether the simulation was daily or seasonal, over the control strategy mentioned in 5a.
 - a. **Fractional reduction in purchased energy.** The ratio of the amount of solar energy used by the desiccant system to the total energy needed by the desiccant system to regenerate the desiccant wheel. Using the control scheme in 5b, the seasonal fractional reduction in purchased energy improved to 86% over 50% for the one in 5a. However, for a designing day, it improved to 64% over 38%, respectively.
 - b. **Thermal coefficient of performance COP_{th} .** The ratio of the enthalpy difference between the supply and return air integrated over the day or year and the amount of energy supplied to regenerate the desiccant wheel. Using the control scheme in 5b, the seasonal COP_{th} improved to 2.35 over 0.55 for the control scheme in 5a. For a design day, it improved to 0.96 over 0.56, respectively.
 - c. **Electrical coefficient of performance COP_{el} .** The ratio of the integrated enthalpy difference between the supply and return air and the amount of electrical energy used by the motors of the pumps and fans of the whole system. For the control scheme in 5b the COP_{el} shows a drop to 9 from 11.5 for the one in 5a. That is because the fans run longer to achieve the same amount of cooling in the control scheme of 5b than of 5a.

MANAGEMENT AND COORDINATION OF COLORADO STATE/DOE PROGRAM

Research Team:

Dr. Douglas C. Hittle, Director
Dr. O.G. George Löf, Senior Advisor
Janice Stapleman, Administrative Assistant

Objective:

Coordinate SEAL-DOE task efforts, provide assistance to DOE, and attend programmatic meetings as requested by DOE.

Work Plan

1. Collaborate with leaders of the five technical tasks in coordination of SEAL program.
2. Organize team and sub-team planning sessions necessary for the conduct of the tasks.
3. Provide and manage necessary facilities and services to leaders and personnel involved in each task.
4. Provide timely quarterly reports on all tasks as required by contract.
5. Maintain fiscal control of program.
6. Attend meetings and technical reporting sessions as requested by DOE.
7. Assist DOE in developing multi-year program plans.
8. Respond to DOE requests for information on solar equipment and its operation, for review of reports, and for panel and committee participation.
9. Provide technical consultation from director and senior advisor to task leaders and research personnel.

Deliverables

1. Quarterly reports will be submitted as required.
2. Special reports will be submitted when necessary, as stipulated in the contract.

Progress:

Director Doug Hittle traveled to DOE-HQ in Washington May 5-7 to meet with DOE officials regarding Solar Cooling Program planning.

June 15-17 a Heating/Cooling Program Coordination meeting was held at the American Solar Energy Society meeting in Cocoa Beach Florida. Doug Hittle, Jane Davidson and Bill Duff from Colorado State met with DOE officials, representatives of the Solar Rating and Certification Corporation, and participants from the University of Wisconsin.

On July 22, SEAL hosted a meeting of solar researchers to share results of DOE research. Attending were representatives of Colorado State, the National Renewable Energy Laboratory, the Solar Rating and Certification Corporation, and the University of Wisconsin.

On November 9, a Heating Program Planning meeting was held at the American Society of Mechanical Engineers in Anaheim. Attending were Director Doug Hittle of SEAL and representatives of the National Renewable Energy Laboratory, the Solar Rating and Certification Corporation, and the University of Wisconsin.

Throughout this report period SEAL researchers participated in various conference calls to discuss the SRCC certification program needs and research tasks.

Coordination of research activities continued on the five research tasks under the DOE grant, and accounts were maintained and updated. Financial and technical reports were submitted as required.

END

**DATE
FILMED**

2 / 2 / 93