PNL--8390

DE93 007616

BURIED WASTE INTEGRATED DEMONSTRATION PROGRAM

**DOE COMPLEX BURIED WASTE
CHARACTERIZATION ASSESSMENT**

**P. S. Kaae
G. M. Holter
S. M. K. Garrett**

January 1993

**Prepared for
the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830**

**Pacific Northwest Laboratory
Richland, Washington**

RECEIVED
JAN 23 1993
PACIFIC NORTHWEST LABORATORY

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED *JP*

EXECUTIVE SUMMARY

The work described in this report was conducted by Pacific Northwest Laboratory^(a) to provide information to the Buried Waste Integrated Demonstration (BWID) program. The information in this report is intended to provide a complex-wide planning base for the BWID to ensure that BWID activities are appropriately focused to address the range of remediation problems existing across the U.S. Department of Energy (DOE) complex.

This report contains information characterizing the 2.1 million m³ of buried and stored wastes and their associated sites at six major DOE facilities. Approximately 85% of this waste is low-level waste, with about 12% TRU or TRU mixed waste; the remaining 3% is low-level mixed waste. In addition, the report describes soil contamination sites across the complex.

Some of the details that would be useful in further characterizing the buried wastes and contaminated soil sites across the DOE complex are either unavailable or difficult to locate. Several options for accessing this information and/or improving the information that is available are identified in the report.

This document is a companion to Technology Needs for Remediation: Hanford and Other DOE Sites, PNL-8328 (Stapp 1993).

(a) Pacific Northwest Laboratory is operated for the U.S. Department of Energy by Battelle Memorial Institute under Contract DE-AC06-76RLO 1830.

ACKNOWLEDGMENTS

This report could not have been completed without the expertise of many other people. The authors would like to express their appreciation to Owen Kruger, Westinghouse Hanford Company, for his support on this project. The authors would also like to acknowledge the efforts of our editor, Sheila Bennett; text processors, Cheri Pestes and Rose Urbina; and especially the following Pacific Northwest Laboratory staff members whose research is included in this document:

L. L. Armacost
K. J. Beverlin
C. L. Blackburn^(a)
M. S. Peffers
J. L. Scott
S. M. Short
D. C. Stapp
D. L. Stiles
J. K. Young

(a) Boeing Computer Services, Richland, Washington.

CONTENTS

EXECUTIVE SUMMARY	iii
ACKNOWLEDGMENTS	v
1.0 INTRODUCTION	1.1
2.0 SUMMARY	2.1
2.1 SUMMARY CHARACTERIZATION OF DOE COMPLEX BURIED WASTE SITES	2.1
2.2 SUMMARY CHARACTERIZATION OF OTHER SITES WITH SOIL CONTAMINATION	2.11
2.3 RECOMMENDATIONS FOR IMPROVED CHARACTERIZATION TO SUPPORT THE BURIED WASTE INTEGRATED DEMONSTRATION	2.12
3.0 DOE COMPLEX BURIED WASTE SITE CHARACTERIZATION	3.1
3.1 BURIED WASTE CHARACTERISTICS	3.1
3.1.1 Overall Complex-Wide Summary	3.1
3.1.2 Site-Specific Information	3.4
3.2 CHARACTERISTICS OF BURIED WASTE STRUCTURES	3.30
3.2.1 Overall Complex-Wide Summary	3.30
3.2.2 Site-Specific Information	3.31
4.0 OTHER CONTAMINATED SITES FOR WHICH BURIED WASTE TECHNOLOGIES MAY BE APPLICABLE	4.1
4.1 OVERALL COMPLEX-WIDE SUMMARY	4.2
4.2 SITE-SPECIFIC INFORMATION	4.3
4.2.1 Idaho National Engineering Laboratory	4.4
4.2.2 Hanford	4.4
4.2.3 Savannah River	4.5
4.2.4 Los Alamos	4.7
4.2.5 Oak Ridge	4.7

4.2.6	Rocky Flats	4.8
4.2.7	Other DOE Sites	4.8
5.0	INFORMATION SOURCES AND CONTACTS	5.1
5.1	INFORMATION SOURCES	5.1
5.2	REFERENCES	5.1
5.3	BIBLIOGRAPHY	5.2
5.4	INFORMATION CONTACTS	5.4
6.0	GLOSSARY	6.1
APPENDIX A	- INEL BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS	A.1
APPENDIX B	- HANFORD BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS	B.1
APPENDIX C	- SAVANNAH RIVER BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS	C.1
APPENDIX D	- LOS ALAMOS BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS	D.1
APPENDIX E	- OAK RIDGE BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS	E.1
APPENDIX F	- ROCKY FLATS BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS	F.1
APPENDIX G	- OTHER BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS	G.1

FIGURES

2.1	Total Waste Volumes by Waste Type	2.3
2.2	Total Waste Volumes by Facility	2.3
2.3	Total TRU Volumes by Facility	2.4
2.4	Total LLW Volumes by Facility	2.4
2.5	Total LLMW Volumes by Facility	2.5
2.6	Total Volumes by Burial Structure Type	2.6
2.7	Total TRU Volumes by Burial Structure Type	2.7
2.8	Total LLW Volumes by Burial Structure Type	2.7
2.9	Total LLMW Volumes by Burial Structure Type	2.8
2.10	Total Waste Volumes by Time Period	2.9
2.11	Total TRU Volumes by Time Period	2.9
2.12	Total LLW Volumes by Time Period	2.10
2.13	Total Pre-1970 TRU Volumes	2.10
3.1	Total Waste Volumes by Waste Type at INEL	3.9
3.2	Total Waste Volumes by Waste Type at Hanford	3.13
3.3	Total Waste Volumes by Waste Type at Savannah River	3.17
3.4	Total Waste Volume by Waste Type at Los Alamos	3.22
3.5	Total Waste Volumes by Waste Type at Oak Ridge	3.26
3.6	Total Waste Volumes by Waste Type at Rocky Flats	3.29

TABLES

2.1	Total Waste Volumes Throughout the DOE Complex	2.1
2.2	Contaminated Soil Volumes Throughout the DOE Complex for Which Buried Waste Technologies May Be Applicable	2.11
3.1	Volumes of Radioactive Solid Waste by DOE Facility	3.2
3.2	Physical Characteristics of TRU Waste by DOE Facility	3.3
3.3	Physical Characteristics of LLW and LLMW by DOE Facility	3.3
3.4	Hazardous Constituents by DOE Facility	3.4
3.5	Volumes of Radioactive Solid Waste by Structure Type at INEL	3.9
3.6	Physical Characteristics of TRU Waste at INEL	3.10
3.7	Physical Characteristics of LLW and LLMW at INEL	3.10
3.8	Hazardous Constituents of LLMW at INEL	3.10
3.9	Volumes of Radioactive Solid Waste by Structure Type at Hanford	3.13
3.10	Physical Characteristics of TRU Waste at Hanford	3.14
3.11	Physical Characteristics of LLW and LLMW at Hanford	3.14
3.12	Hazardous Constituents of LLMW at Hanford	3.14
3.13	Volumes of Radioactive Solid Waste by Structure Type at Savannah River	3.17
3.14	Physical Characteristics of TRU Waste at Savannah River	3.18
3.15	Physical Characteristics of LLW and LLMW at Savannah River	3.18
3.16	Hazardous Constituents of LLMW at Savannah River	3.18
3.17	Volumes of Radioactive Solid Waste by Structure Type at Los Alamos	3.22
3.18	Physical Characteristics of TRU Waste at Los Alamos	3.23
3.19	Physical Characteristics of LLW and LLMW at Los Alamos	3.23
3.20	Hazardous Constituents of LLMW at Los Alamos	3.23

3.21	Volumes of Radioactive Solid Waste by Structure Type at Oak Ridge	3.26
3.22	Physical Characteristics of TRU Waste at Oak Ridge	3.27
3.23	Physical Characteristics of LLW and LLMW at Oak Ridge	3.27
3.24	Hazardous Constituents of LLMW at Oak Ridge	3.27
3.25	Volumes of Buried Radioactive Solid Waste by Structure Type at Rocky Flats	3.29
3.26	Physical Characteristics of TRU Waste at Rocky Flats	3.30
3.27	Physical Characteristics of LLW and LLMW at Rocky Flats	3.30
3.28	Hazardous Constituents of LLMW at Rocky Flats	3.30
4.1	Site Types and BWID Site Categories	4.2
4.2	Other Contaminated Sites Throughout the DOE Complex	4.3
4.3	Waste Types at Other Contaminated Sites Throughout the DOE Complex	4.4
4.4	Waste Types at Other Contaminated Sites at the INEL Facility	4.5
4.5	Waste Types at Other Contaminated Sites at the Hanford Facility	4.6
4.6	Waste Types at Other Contaminated Sites at the Savannah River Facility	4.6
4.7	Waste Types at Other Contaminated Sites at Los Alamos	4.7
4.8	Waste Types at Other Contaminated Sites at Oak Ridge	4.8
4.9	Waste Types at Other Contaminated Sites at Other DOE Facilities	4.9
5.1	Information Contacts for BWID Characterization Information	5.5

1.0 INTRODUCTION

Over the last five decades, the U.S. Department of Energy (DOE) and its predecessor agencies have operated numerous facilities through the U.S. for a wide range of purposes. Activities at these facilities included nuclear weapons research, development, and production, as well as the peaceful use of nuclear power.

Operating these various facilities has resulted in producing various types of wastes, often including radioactive materials or mixtures of radioactive and hazardous materials. Some of the solid wastes are buried or stored for future disposal at various DOE sites. Other activities, such as onsite disposal of contaminated wastewater, have resulted in soil contamination at some facilities, with characteristics similar to those of the buried waste sites.

During FY 1990, the DOE Office of Technology Development (OTD) initiated a series of Integrated Demonstrations (IDs) throughout the DOE complex. These IDs are intended to focus technology research, development, demonstration, testing, and evaluation efforts in specific areas of need relative to waste operations and environmental remediation.

Among the IDs being carried out by OTD is the Buried Waste Integrated Demonstration (BWID) being conducted at the Idaho National Engineering Laboratory (INEL). The BWID is aimed at developing and demonstrating technologies applicable to the remediation of sites throughout the DOE complex that contain buried wastes. These buried wastes include radioactive wastes, hazardous wastes, and mixed radioactive/hazardous wastes; but nonradioactive, nonhazardous wastes are not included in the scope of this effort. The associated buried waste sites include various structures such as trenches, pits, shafts, landfills, caissons, and other site-specific designs.

Many of the technologies being developed to address buried waste structures could potentially apply to other sites with soil contamination, including above-ground liquid impoundments, below-ground liquid impoundments/disposal units, and other contaminated soil sites that may have resulted from such things as spills.

This report is a compilation of information characterizing the buried and stored wastes and their associated structures across the DOE complex. Also included is similar information for other contaminated soil sites for which the same types of remediation technologies may be applicable. The information in this report is intended to provide a complex-wide planning base for the BWID to ensure that BWID activities are appropriately focused to address the range of problems existing within the DOE complex.

Chapter 2.0 of this report summarizes the overall results of the research and provides recommendations for further actions that would improve this assessment. More detailed characterization information on buried waste sites and on other contaminated soil sites for which similar technologies may be applicable is presented in Chapters 3.0 and 4.0, respectively. Chapter 5.0 delineates the major information sources and contacts used in developing this report. Chapter 6.0 contains a glossary, to minimize possible confusion over the terms, acronyms, and abbreviations used in the report. Detailed information on buried waste sites and contaminated soil sites at the various DOE installations are included in the appendixes.

2.0 SUMMARY

This chapter provides a brief summary of the overall results of this study, including recommendations for further actions that could be undertaken to improve this assessment.

2.1 SUMMARY CHARACTERIZATION OF DOE COMPLEX BURIED WASTE SITES

Through the end of 1991, the DOE complex had about 3.1 million cubic meters of buried radioactive and/or hazardous solid wastes contained in underground and above-ground storage and disposal locations throughout the country.

The total volumes of waste, broken down by appropriate regulatory categories, are shown by major DOE facility in Table 2.1. The reported volumes do not include tank waste volumes or projected volumes from complex-wide decontamination and decommissioning (D&D) activities. Additional details about the volumes presented in the table are described in subsequent sections of this report.

For this table, and throughout this report, transuranic (TRU) waste is defined as including mixed TRU waste (i.e., TRU waste with contamination by hazardous components), because both types of waste are destined for disposal

TABLE 2.1. Total Waste Volumes Throughout the DOE Complex^(a)

Facility	LLW Volume (m ³)	LLMW Volume (m ³)	TRU Volume (m ³)	Other Waste (m ³)	Total Volume (m ³)
INEL	171,500	27,000	94,600		293,000
Hanford	581,500	10,800	116,900	120	709,300
Savannah River	616,700	9,000	8,600		634,200
Los Alamos	210,200	300	21,500		232,100
Oak Ridge (X-10)	205,100	1,300	7,000		213,400
Rocky Flats		8,500	900		9,400
Others	935,000	49,900	2,100		987,000
DOE Site-Wide Total	2,720,000	106,800	251,600	120	3,078,500
(a) Numbers have been rounded. Volumes from Other DOE sites were taken from the Integrated Database (IDB) (DOE 1991).					

in the Waste Isolation Pilot Plant (WIPP) repository. Wastes generated prior to segregation of TRU wastes from other wastes, but suspected of meeting the 100 nCi/g alpha contamination criteria for classification as TRU, are also included with the TRU.

The numbers reported in Table 2.1 are drawn primarily from the DOE Integrated Database (IDB) (DOE 1991). Additional corroborating information was drawn from documentation obtained from the various site contacts. Where data were not readily available to complete various entries in the table, estimates were made; the bases for these estimates are described in Section 3 and the Appendixes.

As shown in the table, there are about 3.1 million m³ of solid wastes at the various DOE facilities around the country. The information presented in this report focuses on six major DOE sites: Hanford, INEL, Oak Ridge (X-10), Los Alamos, Rocky Flats, and Savannah River. As shown in Figure 2.1, about 85% of the waste at these six sites is low-level waste (LLW), with about 12% of TRU or TRU mixed waste. Only about 107,000 m³ of low-level mixed wastes (LLMW), or about 3% of the total, have been buried or stored at the various sites since 1986. As shown in Figure 2.2, the sites with the largest volumes of buried wastes include Hanford (34%) and Savannah River (30%).

Basic information about the engineering designs and geologic profiles for the waste burial facilities at the various sites are included in Section 3.2, which also includes overview information on the climatic conditions at the sites. The site characteristics information is important in determining the technologies that can be applied to the buried wastes at the various sites.

Climatic and geologic conditions at the various sites are of two generic types: a dry western site with a significant depth to groundwater, and a humid eastern site with substantial annual rainfall and groundwater levels that are relatively near the surface.

The distribution by DOE facility of the total TRU wastes is shown in Figure 2.3; corresponding information for LLW and LLMW is shown in Figures 2.4 and 2.5, respectively.

FIGURE 2.1. Total Waste Volumes by Waste Type

FIGURE 2.2. Total Waste Volumes by Facility

FIGURE 2.3. Total TRU Volumes by Facility

FIGURE 2.4. Total LLW Volumes by Facility

FIGURE 2.5. Total LLMW Volumes by Facility

Almost half of the TRU waste is at Hanford. INEL is the second largest TRU site, with the remaining four facilities sharing a total of about 15% of the TRU waste.

Of the LLW, Hanford and Savannah River each have about a third of the total, with the remaining third shared fairly equally by Oak Ridge, Los Alamos, and INEL. The quantity of LLW at Rocky Flats is undetermined, and therefore Rocky Flats was excluded from the figure.

Almost half of the LLMW at the six facilities is contained at INEL. Hanford, Savannah River, and Rocky Flats each have about a sixth of the total. Oak Ridge and Los Alamos report minimal amounts of LLMW.

The wastes at the various facilities are buried or stored in several different types of structures, including trenches, pits, buildings, storage pads; or in other structures specific to each DOE site. These structure types are defined further in Section 3.

The major burial structure used throughout the DOE complex is the trench. As shown in Figure 2.6, of the total waste volumes at the six major

FIGURE 2.6. Total Volumes by Burial Structure Type

DOE sites considered in this study, 75% are buried in trenches. Pits account for about 22%. Only a small portion of the waste is stored in buildings, on storage pads, or in other structures.

As shown in Figure 2.7, only a little more than half of the TRU waste is in trenches. The bulk of the remaining TRU waste is split about evenly between pits and storage pads.

The distribution of the LLW among the various types of structures, as shown in Figure 2.8, is very similar to that for the overall waste volumes (as shown previously in Figure 2.6). This is consistent with the fact that the majority of the wastes are LLW.

Almost half of the LLMW is in pits, as shown in Figure 2.9. Another third of the LLMW is in buildings, with most of the remaining LLMW in trenches.

FIGURE 2.7. Total TRU Volumes by Burial Structure Type

FIGURE 2.8. Total LLW Volumes by Burial Structure Type

FIGURE 2.9. Total LLMW Volumes by Burial Structure Type

The information on waste burials was also analyzed by time period in which the actual burials took place. The results of this analysis are shown in Figures 2.10, 2.11, 2.12, and 2.13.

Figure 2.10 shows that almost half of the buried wastes were accumulated prior to 1970, a little over a third of the wastes were accumulated during the period 1970 to 1985, and less than a fifth of the wastes were accumulated in the period from 1986 through 1990. A similar pattern is indicated for LLW, as shown in Figure 2.12.

A different trend is in evidence for TRU waste, on the other hand, as illustrated in Figure 2.11. Almost three-quarters of the TRU or suspected TRU waste was buried prior to 1970. Because TRU wastes were not segregated prior to 1970, these results are based on calculations (described later in Section 3 of this report) and are generally consistent with information presented in the IDB.

As shown in Figure 2.13, 60% of the TRU wastes buried prior to 1970 is buried at Hanford; 32% is buried at INEL; the remaining 8% is distributed fairly evenly among Oak Ridge, Los Alamos, and Savannah River.

FIGURE 2.10. Total Waste Volumes by Time Period

FIGURE 2.11. Total TRU Volumes by Time Period

FIGURE 2.12. Total LLW Volumes by Time Period

FIGURE 2.13. Total Pre-1970 TRU Volumes

2.2 SUMMARY CHARACTERIZATION OF OTHER SITES WITH SOIL CONTAMINATION

DOE has a number of areas on the various sites with soil contamination resulting from past operations, and for which technologies that deal with buried waste may be applicable. These areas are summarized here to indicate the additional volumes of waste materials that may be used as justification for developing buried waste technologies.

A total of 4.7 million cubic meters of contaminated soils is contained in above-ground liquid impoundments, below-ground liquid impoundments/disposal units, and other contaminated soil sites for which data are currently available. The volumes of contaminated soils, broken down by type of contaminated soil sites, is shown by DOE site in Table 2.2. Further details about the types of contamination and the configuration of the sites are included in Section 4.

Note that the volumes of materials included in Table 2.2 (4,700,000 m³) are about 1.5 times the volumes of buried waste throughout the DOE complex (3,100,000 m³). This indicates that considering these other sites is important in determining the needs and incentives for developing buried waste technologies, because they represent a greater volume than the actual buried waste

TABLE 2.2. Contaminated Soil Volumes Throughout the DOE Complex for Which Buried Waste Technologies May Be Applicable^(a)

Facility	Above-Ground Liquid Impoundments (m ³)	Below-Ground Liquid Impoundments/ Disposal (m ³)	Other Contaminated Soil Sites (m ³)	Total Volumes (m ³)
INEL	870,000	35		870,000
Hanford	1,700,000	260,000	37,000	2,000,000
Savannah River	110,000			110,000
Los Alamos	35,000	280	1,500,000	1,540,000
Oak Ridge	140,000	620		140,000
Rocky Flats				
Other Sites	22,500	180	2,100	24,000
DOE Complex Total	2,900,000	260,000	1,500,000	4,700,000

(a) Numbers have been rounded.

sites. In addition, because data are currently unavailable for the majority of such sites, their importance could be understated by the current volume information.

The sites with the largest volumes of contaminated soils of this type are Hanford and Los Alamos. Key assumptions used in developing the information in Table 2.2 are described in Section 4.

Basic information about the engineering designs and geologic profiles for the various contaminated soil sites are included in Section 4.2. These site characteristics are important in determining the technologies that can be applied at these sites.

2.3 RECOMMENDATIONS FOR IMPROVED CHARACTERIZATION TO SUPPORT THE BURIED WASTE INTEGRATED DEMONSTRATION

The information presented in this report was assembled from various sources, as identified in Section 5. Many of the sources did not have all of the information that was needed for this report, and there is some lack of consistency among the various sources. Additionally, there are much larger databases on waste types and characteristics than were realistically possible to access in this characterization effort.

Furthermore, some of the details that would be useful in further identifying the particular information needs are either unavailable or difficult to locate. For example, to form a complete picture of the needs, it is desirable to correlate site contents (volume, waste classification, physical characteristics, hazardous characteristics, and handling category) with specific site design parameters (such as depth of overburden, depth to groundwater, depth to bedrock, and angles of repose for native sediments, waste materials, and fill). However, such a detailed correlation would be very time-consuming, and the availability of adequate, trustworthy data is in doubt.

Several activities could be conducted to improve the characterization information to support the BWID. These are briefly described below.

- Workshops could be held with representatives from the various DOE facilities to present the current results and to seek their assistance and knowledge to help refine the information. The workshops

would be focused on providing improved information in those categories for which it is most needed. Such a set of workshops could be held, and the results incorporated, over a three- to four-month period, at a relatively modest cost to the BWID.

- Most DOE facilities are involved in some form of overall site strategy development and site characterization activity. Generally, there is considerably more waste type and volume information than was readily available for this investigation. Although contacts have been developed during this assessment, it may take involvement by cognizant individuals at each facility, or a visit by members of this characterization effort, to access this larger body of knowledge. This effort is essential to validate and/or refine the data summarized in this report and expand the level of detail to include correlations to D&D activities, tank waste, and contaminated soil remediation efforts.
- Each DOE facility could designate a representative to supply characterization data to the BWID. This would provide a single point of contact at each facility and would streamline the process of obtaining additional data and verifying data already collected.
- It would also be desirable to identify and coordinate with other DOE-complex data collection efforts that may overlap with the BWID data collection requirements. In addition to the IDB, there are many other data compilation efforts under way by various DOE components, both at the national level and at individual sites. Coordinating the various efforts should reduce the number of different requests being handled for similar types of data, while ensuring improved consistency.

3.0 DOE COMPLEX BURIED WASTE SITE CHARACTERIZATION

This section addresses those structures in which solid, radioactive waste (in containers) is buried or stored throughout the DOE complex. Examples of these structures include trenches, pits, shafts, caissons, landfills, storage pads, and storage buildings. These burial structures are not used consistently throughout the DOE complex; for example, caissons are unique to the Hanford Site.

3.1 BURIED WASTE CHARACTERISTICS

The following subsections address the waste volumes, characteristics, and basic assumptions on which the information presented is based.

3.1.1 Overall Complex-Wide Summary

Approximately 2.1 million cubic meters of radioactive solid wastes have been buried or stored through 1990 at the six sites included in this assessment. A breakdown of this total volume is given in Table 3.1.

Prior to 1970, TRU and LLW were commonly commingled in the same burial structure at many DOE facilities. During this time, TRU was defined as having a radionuclide content greater than 10 nCi/g. Waste buried during this time is designated in Table 3.1 as pre-1970 waste.

Beginning in 1970, TRU-bearing wastes were packaged and sealed in containers and segregated from LLW in retrievable storage trenches. In 1982, the lower radionuclide content limit for TRU was revised to 100 nCi/g. Consequently, certain assumptions must be made to quantify the volume of waste that is likely to be LLW and what is suspected to be TRU. These assumptions vary by facility.

The Resource Conservation and Recovery Act (RCRA), enacted in 1986, established the mixed waste classification to account for solid waste that is contaminated with an RCRA regulated (i.e., hazardous) waste. Volumes of buried and/or stored low-level mixed waste (LLMW) and transuranic mixed waste (TRUM) are included in this assessment; no assumptions are made to estimate the volume of buried mixed wastes prior to 1986.

TABLE 3.1. Volumes of Radioactive Solid Waste by DOE Facility^(a)

Facility	Pre-1970			1970 - 1985			1986 - 1990				Pre-1970 - 1990	
	LLW	Suspect TRU	LLW	LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total	Total
Hanford	283,800	109,000	207,900	6,800		100	89,800	10,800	1,100	20	709,300	
Savannah River	177,600	4,300	284,400	3,200			154,700	9,000	1,100		634,200	
INEL	60,600	57,100	99,400	28,100			11,500	27,000	9,400		293,000	
ORNL (x-10)	157,900	6,200	39,200	600			8,000	1,300	200		213,400	
Rocky Flats								8,500	900		9,400	
Los Alamos	85,300	4,800	101,500	5,700			23,400	300	11,100		232,100	
Grand Totals	765,100	181,400	732,200	44,400	100	100	287,400	56,900	23,700	20	2,091,300	

(a) Shaded areas are estimates. See Appendixes for methodology.

Buried waste can be further delineated by identifying its various physical characteristics. Among the physical attributes included in this assessment for TRU are absorbed liquids or sludges (sludges), combustibles, non-combustibles, particulates, filters, and other physical characteristics. A breakdown of these physical characteristics is shown in Table 3.2. The volumes in this table were derived from the IDB.

Among the physical attributes included in this assessment for LLW and LLMW are biological materials, contaminated equipment, debris, dry solids, sludges, and other physical characteristics. A breakdown of these physical characteristics is shown in Table 3.3. The volumes in this table were derived from the IDB.

TABLE 3.2. Physical Characteristics of TRU Waste by DOE Facility (m³)

	Sludges	Combustibles	Non-Combustibles	Particulates	Filters	Other	Total
INEL	17,900	27,500	19,100	3,800	2,600	23,600	94,600
Hanford	1,100	50,400	56,000	3,500	1,100	4,800	116,900
Savannah River		6,000	2,600				8,500
Los Alamos	2,200	2,900	5,200	4,300	500	6,500	21,600
Oak Ridge (X-10)	3,000	2,400	1,500	20	200	50	7,100
Rocky Flats	300	100	400	10	10	50	900
Total	23,700	89,600	84,700	11,700	4,400	35,000	249,200

TABLE 3.3. Physical Characteristics of LLW and LLMW by DOE Facility (m³)^(a)

	Bio-logical	Contaminated Equipment	Debris	Dry Solids	Solidified Sludges	Other	Total
INEL			3,600			194,800	198,400
Hanford	3,200	123,700	23,000	430,600	300	11,500	592,300
Savannah River		222,800		402,800			625,600
Los Alamos	400	53,800	12,500	143,600		200	210,500
Oak Ridge (X-10)	32,500	75,400	8,100	64,000	22,300	3,900	206,300
Rocky Flats				8,500			8,500
Total	36,100	475,700	47,200	1,049,500	22,600	210,400	1,841,500
(a) Volumes in shaded areas are estimates. See appendixes for methodology.							

Hazardous constituents of the buried waste are also important to quantify for this assessment. However, since mixed wastes were not regulated until 1986, only limited characterization information is available from each of the DOE facilities. Table 3.4 shows the hazardous constituents that are known to contaminate the wastes buried or retrievably stored since 1986.

3.1.2 Site-Specific Information

3.1.2.1 Idaho National Engineering Laboratory (INEL)

There are four radioactive waste disposal or storage areas at the Idaho National Engineering Laboratory (INEL). This report contains brief descriptions of three of those areas, the SL-1 Burial Ground, the Idaho Chemical Processing Plant calcined solid storage facilities, and the Argonne National Laboratory Radioactive Scrap and Waste Facility, and a more detailed account of the Radioactive Waste Management Complex (RWMC), which contains most of the waste. Estimated volumes are for the total buried waste at INEL.

The waste at INEL is classified as routine or non-routine. The routine waste consists of INEL-generated combustibles, such as protective clothing, decontamination materials, wood, and cardboard. Routine waste has been packed in cardboard boxes and dumped into the trenches and pits or compacted in the trenches. Since 1971, routine waste has been compacted into bales and placed in fiberboard boxes with plastic liners before being buried. INEL-generated, routine combustibles constitute the major portion of waste at INEL (90%).

TABLE 3.4. Hazardous Constituents by DOE Facility

	Ignitable	Reactive	Corrosive	Toxic	Listed RCRA Wastes	PCBs	Total
INEL	300		0	400	23,800	2,400	27,000
Hanford	700	3,700	60	4,600	1,600	30	10,800
Savannah River	0		100	300	8,600		9,000
Los Alamos	10	0	20	60	200		300
Oak Ridge (X-10)	50		0	60	1,200		1,300
Rocky Flats	0			40	8,400	10	8,500
Total	1,100	3,700	200	5,500	43,800	2,500	56,800

The non-routine waste consists of waste with greater than 500 mR/hr at three feet, has plutonium/thorium source material, or is a liquid or a slurry. Prior to the late 1960s, this waste was buried in 2 x 2 x 3 ft boxes or 30-gallon garbage bags. A standard burial method for non-routine waste starting in the late 1960s consisted of steel boxes with open ends placed in narrow trenches and filled with waste. When the boxes were full, the waste was covered with soil, and the steel box was lifted out of the trench.

Low-level waste, which consists primarily of routine waste, is further categorized as contaminated trash, process waste, contaminated equipment, and activated metals.

Several container types have been used over the years. Cardboard boxes and plastic wrappings were used routinely until about 1974. Containers at INEL have included 30-, 40-, and 55-gallon drums, cardboard boxes, and wooden boxes up to 105 x 105 x 214 in.; no containers were used for larger individual items, which were treated as loose trash. Large amounts of plastic have been used to line containers. Polyethylene sheet plastic and drum liners, polyvinyl chloride sheets and liners, plastic jugs, and other plastic containers of unknown composition have all been used.

The major means of burying and storing waste at INEL are trenches, pits, storage pads, and soil vault rows. Soil vault rows were mentioned in the Draft Environmental Impact Statement (INEL 1976), but no description was provided. Storage pads are mostly above-ground for TRU wastes; exceptions are the earlier pads where the wastes were stacked, covered with fire-retardant plywood and nylon reinforced polyvinyl, and then covered with two to three feet of soil. The sides were also covered with soil. Storage pads are 3-in.-thick asphalt over a 4-in. gravel base.

The SL-1 Burial Ground was constructed to receive the waste from a 1961 accidental excursion at the Stationary Low Power Test Reactor (SL-1), which produced some highly radioactive contaminated debris. There is one trench, 6 x 495 x 10 ft deep; and two pits, one 12 x 495 x 10 ft deep and one 20 x 400 x 10 ft deep. One item buried here is the non-decontaminated reactor, which was covered with lead shielding and soil. Most of the dismantled building, contaminated equipment, and decontamination waste were interred directly in

the SL-1 burial ground. Although no estimate of the total waste buried was found, an estimated 750 m³ of contaminated soil and gravel have been associated with the site.

The Idaho Chemical Processing Plant (ICPP) calcined solid storage facilities consist of underground storage bins for solid calcined products (mixed waste). The facility was designed to hold 2,200 m³ of waste when full; through 1974, 1,220 m³ of waste had been reported stored in stainless steel bins inside reinforced concrete vaults. Most of the later references used for this study concentrate on TRU waste and do not mention the ICPP storage facility.

Argonne National Laboratory (ANL) Radioactive Scrap and Waste Facility is a 388 x 448 ft storage structure that uses holes with steel liners for storing TRU wastes. The steel liners are fabricated from Schedule 10 pipe and are 12.33 ft long with a 16-in. outside diameter and 1/4-in. thick walls. The liner bottoms are welded closed; and waste is placed in the liner, which is then filled with concrete and sealed closed. Some of the liners may be filled with gravel instead of concrete. The construction allows for easy retrieval of the liners from the holes.

Waste in this facility consists primarily of waste metal from fuel handling and refabrication operations. By 1974, approximately 60 m³ had been received. Approximately 1,080 holes can be accommodated here.

RWMC Waste - A wide variety of wastes have been buried at the RWMC, including Rocky Flats Plant (RFP) process-generated waste such as sludges, evaporation salts, plutonium-contaminated equipment, and fire cleanup waste; INEL waste, which is mostly routine combustibles; and a small amount of waste from other locations. The wastes include nitrate salts, PCB-contaminated oils and sludges, nitric acid absorbed in combustibles, magnesium oxide crucibles, contaminated styrene polymer-based ion exchange resins, refractory material, empty drums, beryllium, copper molds, asbestos, lead, and mercury. Hazardous and radioactive-only contaminated liquids were disposed of freely and in containers.

LLW and TRU waste were commingled in the pits and trenches until 1970, although, starting in 1957, pits were generally used for RFP TRU and trenches were generally used for INEL LLW.

Pit 3 contains 10 jet engines and six boxes of intermediate-level waste (ILW). The ILW is packaged in drums and centered in the boxes, which are then filled with cement. Each box weighs from 12,000 to 14,000 pounds (6-7 tons).

Pit 10 contains fire debris from Rocky Flats that was decontaminated prior to shipment to INEL. Some of the equipment was dismantled, and some plutonium was retrieved. Fire debris containers and equipment were dumped from the side of the pit and covered with soil. Pit 10 also contains a 12,000-gallon cylindrical metal tank contaminated with mixed fission products.

From 1952 to 1963, drums and wooden crates were stacked. From 1963 to 1969, containers were not stacked; stacking was reinstituted in 1969 to save space.

Some early retrieval tests were performed at INEL in the 1970s, and the results were not very encouraging. In 1971, before markers were removed for additional soil coverage, drums were discovered outside the pit markers. Stacked drums buried 12 years were generally in poor condition. However, randomly buried drums that had been in the ground for three to seven years were more difficult to retrieve, and all of those retrieved had been damaged by heavy equipment during leveling and grading operations. One-quarter of the retrieved randomly buried drums were open; a wooden box that had been buried for five years was in poor condition. A later retrieval effort found removable alpha contamination up to one million counts per minute (cpm) and loose alpha contamination of 100,000 cpm.

The last retrieval effort, performed from 1976 to 1978, found alpha contamination levels exceeding two million cpm; two-thirds of the retrieved drums were severely breached, and 6% of the drums were leaking free liquids.

In addition to the potentially high contamination (items emitting up to 12,000 R/hr have been buried here) and poor condition of containers, three other factors affect retrieval of buried waste at the RWMC.

- Unknown locations. Although some records exist on waste locations, the records are incomplete, pit markers have been removed and reset over the years making boundaries unsure, and random dumping has allowed items to move before being covered. During retrieval tests in the 1970s, several drums were found outside pit boundaries.
- Reactivity. The debris is mixed in the trenches and pits, making it potentially reactive.
- Basalt Base. RWMC is constructed on a basalt base. The bottom of the pits and trenches lay only two to five feet above the basalt, making retrieval from the pits and trenches more difficult, since equipment must get below the waste. Retrieving contaminated "soil" is extremely difficult, or impossible, if contaminated basalt must be retrieved. The basalt is reportedly contaminated to a maximum depth of 240 feet.

Figure 3.1 shows the makeup of the solid waste buried and stored at INEL. Fifty-nine percent of the total volume is LLW, 32% is TRU, and 9% is LLMW stored at the site since 1986. A summary characterization of waste at INEL is provided in Tables 3.5 through 3.8. The volumes shown in Table 3.5 are based upon a qualitative assessment of the best available information found during this study, primarily upon the IDB. Estimates varied among different sources, possibly because of different assumptions on soil contamination. Some sources reported total waste volumes that included contaminated soils. The IDB estimates did not include any contaminated overburden. The assumptions used to generate the estimates shown in the table are given in Appendix A.

Tables 3.6 and 3.7 describe the physical characteristics of the TRU and LLW at INEL. The hazardous constituents of the mixed waste are delineated in Table 3.8.

3.1.2.2 Hanford

At the Hanford Site, three different areas, the 100, 200, and 300 Areas, contain approximately 709,200 m³ of buried and retrievably stored radioactive solid wastes. Burial practices and usage of each area are slightly different.

100 Areas. Beginning in 1944, land burial was used in the 100 Areas "to dispose of solid, low-level radioactive waste associated with reactor operations" (Miller and Wahlen 1987). Solid wastes were buried in 28 different

FIGURE 3.1 Total Waste Volumes by Waste Type at INEL

TABLE 3.5. Volumes of Radioactive Solid Waste (m³) by Structure Type at INEL (a)

Structures	Pre-1970			1971 - 1985			1986 - 1990				Pre-1970 - 1990	
	LLW	Suspect TRU	LLW	LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total	Total
Trenches	16,300	3,900	1,900								22,200	
Pits	44,300	53,200	97,500				11,500	27,000			233,400	
Storage Pads					28,100				9,400		37,500	
Total	60,600	57,100	99,400		28,100		11,500	27,000	9,400		293,000	

(a) Volumes in shaded cells are estimated values. See Appendix A for methodology.

TABLE 3.6. Physical Characteristics of TRU Waste at INEL (m³)^(a)

	Sludges	Combustibles	Non-Combustibles	Par-ticulates	Filters	Other	Total
Trenches	700	1,100	800	200	100	1,000	3,900
Pits	10,000	15,500	10,800	2,200	1,500	13,300	53,200
Storage Pads	7,100	10,900	7,600	1,500	1,000	9,400	37,500
Total	17,900	27,500	19,100	3,800	2,600	23,600	94,600
(a) Volumes in shaded cells are estimated values. See Appendix A for methodology.							

TABLE 3.7. Physical Characteristics of LLW and LLMW at INEL (m³)^(a)

	Bio-logical	Contaminated Equipment	Debris	Dry Solids	Solidified Sludges	Other	Total
Trenches			300			17,900	18,200
Pits			3,200			176,900	180,100
Storage Pads							
Total			3,600			194,800	198,400
(a) Volumes in shaded cells are estimated values. See Appendix A for methodology.							

TABLE 3.8. Hazardous Constituents of LLMW at INEL (m³)^(a)

	Ignitable	Reactive	Corrosive	Toxic	Listed RCRA Wastes	PCBs	Total
Trenches							
Pits	300		0	400	23,800	2,400	27,000
Storage Pads							
Total	300		0	400	23,800	2,400	27,000
(a) Volumes in shaded cells are estimated values. See Appendix A for methodology.							

locations called burial grounds. The majority of the waste generated from reactor operations was placed in seven burial grounds, one for the KE and KW reactors and one for each of the other six reactors at the 100 Areas.

Combustible and noncombustible materials were not segregated until 1954. After 1955, combustibles were burned in trenches; this practice was stopped

after 1966. Disposal of solid waste in the 100 Areas was discontinued sometime between 1966 and 1973, when centralization of the burial grounds at the 200 Areas began.

Most of the waste buried in the 100 Areas is metal, none of which was specially packaged or treated prior to disposal.

200 Areas. Radioactive waste has also been buried in the 200 Areas since 1944; these areas continue to be active burial sites for solid waste generated at Hanford and offsite facilities. The waste has been generated from reactor operations, chemical processing and separations, research and development (R&D) activities, and other DOE programs. Waste contamination includes fission products, induced activation products, and TRU isotopes.

Between 1944 and 1970, LLW and TRU waste were not segregated prior to burial. However, since 1970, TRU has been segregated and retrievably buried. Prior to 1987, waste contaminated with hazardous constituents (e.g., mixed radioactive waste) was buried; since then, however, mixed waste has been stored above ground in buildings located in the 200 Areas.

Various waste forms have been buried in the 200 Areas. These include ion exchange resins, asbestos, contaminated equipment, laboratory waste, hot cell waste, and miscellaneous wastes such as contaminated paper, rubber, plastic, and glass. Submarine reactor compartments from the U.S. Navy are also buried in the 200 Areas; these are believed to be included in the LLMW volumes reported in this assessment.

The wastes buried in the 200 Areas have been disposed of in a variety of packages including 55-gallon drums; cardboard, wooden, or metal boxes; concrete cases, or plastic wrap.

300 Area. Burial of radioactive waste was started in the 300 Area in 1943. The largest volume of waste was generated from the fuel fabrication operations. Waste also came from the Plutonium Recycle Test Reactor, life-science activities, R&D activities, and support facilities.

Figure 3.2 shows the makeup of the solid waste buried and stored at Hanford. Eighty-two percent of the total volume is LLW, 16% is TRU, and 2% is LLMW stored at the site since 1986. A summary characterization of waste at Hanford is provided in Tables 3.9 through 3.12. The volumes shown in Table 3.9 are based upon a qualitative assessment of the best available information found during this study, primarily upon the IDB. The assumptions used to generate the estimates shown in the table are given in Appendix B.

Tables 3.10 and 3.11 describe the physical characteristics of the TRU and LLW at Hanford. The hazardous constituents of the mixed waste are delineated in Table 3.12.

3.1.2.3 Savannah River Site (SRS)

There are 40 waste sites at the Savannah River Site that have or might have received LLW or LLMW. The 40 waste sites consist of basins, burning and rubble pits, the Ford Building waste site, the TNX burial ground, and the central radioactive waste burial grounds. This section of the report concentrates on the central radioactive burial grounds, where the major portion of buried radioactive solid waste is located. Mixed waste stored in buildings outside the central radioactive waste burial grounds is not covered in this report.

There is one central radioactive waste burial area with three different burial grounds (sites) within it. Each site has been assigned a building number: 643-G, 643-7G, and 643-28G. Burial practices and use are slightly different at each site.

Savannah River Site has segregated its LLW for burial. Wastes with less than 300 mR/hr at 3 in. and less than 10 nCi/g of TRU contaminants are labeled "low-level waste." Wastes with more than 300 mR/hr at 3 in. and less than 10 nCi/g of TRU contaminants are labeled "intermediate-level waste." Wastes with no beta-gamma emitters and with TRU radionuclides less than 10 nCi/g are labeled "trench alpha waste." The Savannah River labeling of LLW is used in the following paragraphs, except where noted. TRU waste was defined as waste having TRU at greater than 10 nCi/g until 1986 at Savannah River; reported TRU

FIGURE 3.2 Total Waste Volumes by Waste Type at Hanford

TABLE 3.9. Volumes of Radioactive Solid Waste (m³) by Structure Type at Hanford^(a)

	Pre-1970			1971 - 1985			1986 - 1990			Pre-1970 - 1990	
	LLW	Suspect TRU	LLW	LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total
Structures											
Trenches	283,800	109,000	207,900	6,600	20	100	89,800	8,600	600	20	706,400
Caissons									20		50
Storage Pads								400			400
Storage Buildings				200				1,900	400		2,500
Total	283,800	109,000	207,900	6,800		100	89,800	10,800	11,000	20	709,300

(a) Volumes in shaded cells are estimates. See Appendix B for methodology.

TABLE 3.10. Physical Characteristics of TRU Waste at Hanford (m³)^(a)

	Sludges	Combustibles	Non-Combustibles	Par-ticulates	Filters	Other	Total
Trenches	1,100	50,100	55,700	3,500	1,100	4,800	116,200
Caissons	0	20	20	0	0	0	50
Storage Pads							
Storage Buildings	10	300	300	20	10	30	600
Total	1,100	50,400	56,000	3,500	1,100	4,800	116,900
(a) Volumes in shaded areas are estimates. See Appendix B for methodology.							

TABLE 3.11. Physical Characteristics of LLW and LLMW at Hanford (m³)^(a)

	Bio-logical	Contaminated Equipment	Debris	Dry Solids	Solidified Sludges	Other	Total
Trenches	3,200	123,700	23,000	429,400	300	10,400	590,000
Caissons							
Storage Pads				200		200	400
Storage Buildings				1,000		900	1,900
Total	3,200	123,700	23,000	430,600	300	11,500	592,300
(a) Volumes in shaded areas are estimates. See Appendix B for methodology.							

TABLE 3.12. Hazardous Constituents of LLMW at Hanford (m³)^(a)

	Ignitable	Reactive	Corrosive	Toxic	Listed RCRA Wastes	PCBs	Total
Trenches	600	3,000	50	3,700	1,300	30	8,600
Caissons							
Storage Pads	20	100	0	200	50	0	400
Storage Buildings	100	600	10	800	300	10	1,900
Total	700	3,700	60	4,600	1,600	30	10,800
(a) Volumes in shaded areas are estimates. See Appendix B for methodology.							

quantities may include waste now classified as LLW (<100 nCi/g). Solid radioactive waste has been segregated by activity (e.g., LLW, ILW, trench alpha waste, or TRU waste) since the central radioactive waste site started receiving waste.

643-G. This 76-acre site was used from 1952 through 1972 and is the original central radioactive waste site. Solid wastes were buried in 26 different burial locations, of which 12 contain ILW, eight contain trench alpha waste, and six contain LLW. Until 1965, TRU waste was buried in plastic bags and cardboard boxes in earthen trenches designated specifically for this waste; it is subject to leaching if contacted by water-saturated soil. Waste disposed of in 643-G includes contaminated equipment, reactor hardware and resins, spent lithium-aluminum targets, tritiated oils, tritiated mercury, laboratory operational waste, plutonium process waste from other DOE facilities, and debris from U.S. military plane crashes. Lead, mercury, and cadmium have also been placed in this burial ground.

643-7G. This 119-acre site, north of and contiguous to the original 643-G site, has been receiving generated waste since 1969. It is an active LLW burial site, consisting of 25 burial locations (of which 16 make up 643-28G) and including trenches, greater confinement disposal boreholes, TRU waste pads, a mixed waste pad, and two storage buildings. Types of waste buried in 643-7G include contaminated equipment, laboratory operational waste, spent lithium-aluminum targets, reactor hardware or resins, and shipments from offsite.

643-28G. This 56-acre site is a closure site within 643-7G defined in 1986 to be closed as a mixed waste management facility. It has received materials defined as hazardous by the Resource Conservation and Recovery Act (RCRA); however, it may contain "pockets" of TRU contamination. The solid wastes were buried in 16 different burial locations, of which 10 have trench alpha waste, three have LLW, and three have ILW. Inventory of 643-28G includes lead, mercury, and cadmium solid waste, various pieces of process equipment, tritiated oil in absorbent, scintillation fluids, filter paper take-up rolls, and PCB-contaminated materials.

Figure 3.3 shows the makeup of the solid waste buried and stored at Savannah River. Ninety-eight percent of the total volume is LLW, 1% is TRU, and 1% is LLMW stored at the site since 1986. A summary characterization of waste at Savannah River is provided in Tables 3.13 through 3.16. The volumes shown in Table 3.13 are based upon a qualitative assessment of the best available information found during this study, primarily upon the IDB. The assumptions used to generate the estimates shown in the table are given in Appendix C.

Tables 3.14 and 3.15 describe the physical characteristics of the TRU and LLW at Savannah River. The hazardous constituents of the mixed waste are delineated in Table 3.16.

3.1.2.4 Los Alamos Site

Fifteen different areas have been used for waste disposal at the Los Alamos Site; at least nine may have radioactive solid waste. Some areas have used slightly different burial practices and have been used for different wastes. The nine areas presented in this document are Areas A, B, C, D, E, F, G, T, and Y. Two other areas, W and X, list coolant tanks, which were to be entombed as of 1979, and nuclear reactor vessels, which were planned for removal to Area G. It is assumed in this study that these activities have taken place.

No source was found giving the breakdown of physical characteristics of the waste by volume or waste class. However, radioactive wastes are categorized at Los Alamos as routine or non-routine, and the general physical characteristics of the waste buried in each area are generally known. Most of the waste is routine, consisting of laboratory trash (mostly combustible), equipment, chemicals, oil, animal tissue, chemical treatment sludge, cement paste, hot cell waste, and classified materials. Non-routine waste consists of building debris, large equipment items, and soil or rock removed during site cleanup. Waste may be contaminated with TRU, uranium, fission products, induced activities, or tritium. Wastes contaminated with fission products, tritium, or induced activities make up only 1-3% of the total waste volume.

FIGURE 3.3 Total Waste Volumes by Waste Type at Savannah River

TABLE 3.13. Volumes of Radioactive Solid Waste (m^3) by Structure Type at Savannah River^(a)

	Pre-1970			1971 - 1985				1986 - 1990				Pre-1970 - 1990	
	LLW	Suspect TRU	LLW	LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total		
Structures													
Trenches	177,600	4,300	280,800	200			154,700				617,600		
Storage Pads			3,600	2,900					1,100		7,600		
Storage Buildings								9,000			9,000		
Total	177,600	4,300	284,400	3,200			154,700	9,000	1,100		634,200		

(a) Volumes in shaded areas are estimates. See Appendix C for methodology.

TABLE 3.14. Physical Characteristics of TRU Waste at Savannah River (m³)^(a)

	Sludges	Combustibles	Non-Combustibles	Par-ticulates	Filters	Other	Total
Trenches		3,200	1,400				4,500
Storage Pads		2,800	1,200				4,000
Storage Buildings							
Total		6,000	2,600				8,500
(a) Volumes in shaded areas are estimates. See Appendix C for methodology.							

TABLE 3.15. Physical Characteristics of LLW and LLMW at Savannah River (m³)^(a)

	Bio-logical	Contaminated Equipment	Debris	Dry Solids	Solidified Sludges	Other	Total
Trenches		218,300		394,800			613,100
Storage Pads		1,300		2,300			3,600
Storage Buildings		3,200		5,800			9,000
Total		222,800		402,900			625,600
(a) Volumes in shaded areas are estimates. See Appendix C for methodology.							

TABLE 3.16. Hazardous Constituents of LLMW at Savannah River (m³)^(a)

	Ignitable	Reactive	Corrosive	Toxic	Listed RCRA Wastes	PCBs	Total
Trenches							
Storage Pads							
Storage Buildings	0		100	300	8,600		9,000
Total	0		100	300	8,600		9,000
(a) Volumes in shaded areas are estimates. See Appendix C for methodology.							

Several container types are used at Los Alamos. Again, no information was found on container types by volume of waste or waste class, although some containers are known to be used for only one waste class. Cardboard boxes and/or plastic bags are used for trash. Radioactive oils are absorbed on solids and placed in metal containers. Equipment and building debris are in wooden crates. Tritium-containing wastes are in asphalt-coated, sealed metal

drums if the concentration is greater than 20 nCi/m³, and completely encased in asphalt if the concentration is greater than 100 Ci/m³. Non-TRU trash is compacted before burial, and the bale is placed directly into the pit. Retrievable TRU is in 55-gallon drums lined with 90-mil, high-density polyethylene or wooden crates coated with 3.2 mm of fire-retardant, fiberglass-reinforced polyester. TRU sludge (non-retrievable) < 10 nCi/g is packaged in 5-mil plastic and sealed in 55-gallon drums. High-activity TRU is stored in concrete casks holding two 30-gallon drums in shallow pits. Retrievable cement paste is pumped into vertical welded, galvanized, corrugated metal pipe sections with 1-ft-thick cement caps at each end.

Area A. Area A was used from 1945 to 1946 for disposal of chemical waste and probably contains no TRU waste. Two storage tanks, 12 ft in diameter; 62 ft, 10 in. long; and containing semisolid precipitate in the bottoms, are buried on concrete piers in Area A. This area was used again between 1969 and 1978 for burying demolition debris.

Area B. Area B was used between 1944 and 1948. All types of waste were buried in this area, including chemical materials such as gas cylinders containing HCl, H₂S, and HF. Ninety percent of the waste consists of paper, rags, rubber gloves, glassware, and small apparatus placed in cardboard boxes and sealed with masking tape. The rest of the material is metal, e.g., air ducts and large metal apparatus, wrapped in paper. There is also some wood, several live batteries, and contaminated or toxic chemicals. At least one truck is buried in this area. Area B also contains a shallow trench for disposal of hazardous material. Material disposed of in the hazardous trench includes old bottles of organics, ethers, and solvents.

Area C. Area C was used from 1948 to 1974 for laboratory waste, building debris, sludge from waste treatment plants, uncontaminated classified materials, and tuballoy chips. Routine trash was buried in cardboard boxes, 5-mil plastic bags, and 55-gallon drums. An experiment with plastic bags and cardboard boxes showed unburied cardboard boxes deteriorated much faster than the 5-mil plastic bags.

There is also a separate chemical pit in Area C that contains "a variety of chemicals; pyrophoric metals; hydrides and powders; sealed vessels

containing sodium potassium alloy or compressed gases; and equipment not suitable for salvage, public dump, or contaminated dump have been placed in the pit. No high explosives have ever been placed in this pit. Normal uranium powders and hydrides have been disposed of in this pit" (LANL 1987). There are also plutonium contaminated objects and about 200 full or partially full gas cylinders in the chemical pit.

In Area C, there are 107 vertical shafts used for wastes with larger quantities of radioactivity. Half the shafts contain TRU wastes. Some of the shaft waste has been placed in sealed "Dural" containers within sealed steel containers.

Area D. Area D was used in 1948 and 1952 for underground testing of explosives containing short-lived ^{210}Po (polonium). The waste in Area D is not the typical waste found in radioactive burial structures but consists of two chambers used to test subsurface explosives with ^{210}Po . The sizes of the explosion chambers vary by document. A 1977 source reports the chamber in Shaft 2 is a 14-ft-wide, octagonally shaped chamber with a 12-ft ceiling (Rogers 1977). A 1990 source states the chamber in Shaft 1 is 16 x 18 x 11 ft high, and the chamber in Shaft 2 is 18 x 18 x 16 ft high (LANL 1990). Possible contaminants varied even within the same report. The shafts were shored up with 2 x 12 in. timbers. The door to each chamber is constructed of steel filled with wood.

Area E. Area E was used between 1949 and the mid-1960s. Area E contains one chamber, similar to those found in Area D, and solid wastes including polonium-beryllium fired targets, a can full of beryllium dust immersed in kerosene, and miscellaneous hot materials.

Area F. Area F was active from 1946 to the early 1950s. There is no reliable source of information on waste buried in this area. High explosives have been buried here; some alpha contamination is present; but Area F was mainly used for disposal of toxic compounds. Beta-gamma emitters, equipment, and/or material contaminated with high explosives may also be buried in Area F.

Area G. Area G became active in 1957 and is still active. This area is the largest burial ground at Los Alamos. There is some TRU waste buried in Area G, but most of the waste is considered LLW.

Some of the materials that can be found in Area G include plutonium mixed with sand, TRU sludge mixed with cement, asbestos- and PCB-contaminated wastes, tritium wastes, demolition debris, depleted uranium chips, contaminated oil, "Cancer Suspect Research" waste, building debris, sections of filter plenums, and pieces of heavy equipment such as dump trucks. After 1971, 55-gallon drums (lined with 10-mil liners) of sludge and plutonium-contaminated equipment have been retrievably stored and stacked in the pits.

Routine laboratory waste was buried in cardboard boxes, 5-mil plastic bags, or 55-gallon drums. Retrievable TRU is found in fiberglass-coated crates as well as 55-gallon drums. Wastes with radiolytic gas formation are placed in 30-gallon drums within casks sealed with asphalt materials.

Area T. Area T was used from 1945 to 1967 and is classified as part of the liquid disposal operation. Area T contains treated liquid waste residues mixed with cement in 62 shafts, and retrievable TRU waste mixed with cement and pumped into corrugated metal piping. Fifty-six of the 62 shafts in Area T contain TRU.

Untreated liquid waste from plutonium processing and treated liquid waste containing LLW were deposited in four beds which have since had the bottom material removed and have been filled to ground level.

Area Y. Area Y has been in service since 1966. It contains high explosives, contaminated waste, and uranium.

Figure 3.4 shows the makeup of the solid waste buried and stored at Los Alamos. Ninety-one percent of the total volume is LLW, 9% is TRU, and less than 1% is LLMW stored at the facility since 1986. A summary characterization of waste at Los Alamos is provided in Tables 3.17 through 3.20. The volumes shown in Table 3.17 are based upon a qualitative assessment of the best available information found during this study, primarily upon the IDB. The assumptions used to generate the estimates shown in the table are given in Appendix D.

FIGURE 3.4 Total Waste Volumes by Waste Type at Los Alamos

TABLE 3.17. Volumes of Radioactive Solid Waste (m^3) by Structure Type at Los Alamos^(a)

Structures	Pre-1970		1971 - 1985			1986 - 1990				Pre-1970 - 1990
	LLW	Suspect TRU	LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total
Trenches			100	1,900				1,200		3,200
Pits	85,300	4,800	101,300	1,900		23,400		1,200		217,900
Shafts			100	1,900				1,200		3,200
Storage Pads							300	7,600		7,900
Total	85,300	4,800	101,500	5,700		23,400	300	11,100		232,100

(a) Volumes in shaded areas are estimates. See Appendix D for methodology.

TABLE 3.18. Physical Characteristics of TRU Waste at Los Alamos (m³)^(a)

	Sludges	Combustibles	Non-Combustibles	Particulates	Filters	Other	Total
Trenches	300	400	700	600	70	900	3,100
Pits	800	1,100	1,900	1,600	200	2,400	7,900
Shafts	300	400	700	600	70	900	3,100
Storage Pads	800	1,000	1,800	1,500	200	2,300	7,600
Total	2,200	2,900	5,200	4,300	500	6,500	21,600
(a) Volumes in shaded areas are estimates. See Appendix D for methodology.							

TABLE 3.19. Physical Characteristics of LLW and LLMW at Los Alamos (m³)^(a)

	Bio-logical	Contaminated Equipment	Debris	Dry Solids	Solidified Sludges	Other	Total
Trenches	0	20	10	60		0	90
Pits	400	53,600	12,500	143,200		230	210,000
Shafts	0	20	10	60		0	90
Storage Pads	0	80	20	200		0	300
Total	400	53,800	12,500	143,600		200	210,500
(a) Volumes in shaded areas are estimates. See Appendix D for methodology.							

TABLE 3.20. Hazardous Constituents of LLMW at Los Alamos^(a)

	Ignitable	Reactive	Corrosive	Toxic	Listed RCRA Wastes	PCBs	Total
Trenches							
Pits							
Shafts							
Storage Pads	10	0	10	60	200		300
Storage Buildings							
Total	10	0	10	60	200		300
(a) Volumes in shaded areas are estimates. See Appendix D for methodology.							

Tables 3.18 and 3.19 describe the physical characteristics of the TRU and LLW at Los Alamos. The hazardous constituents of the mixed waste are delineated in Table 3.20.

3.1.2.5 Oak Ridge Site

The areas that contain buried radioactive solid waste at the Oak Ridge facility include the Solid Waste Storage Area (SWSA) 1, SWSA 2, SWSA 3, SWSA 4, SWSA 5, and SWSA 6. Records for the amounts and types of radio-nuclides present in SWSAs 1 and 2 do not exist, and both sites are now closed. The wastes buried in SWSA 2 have since been removed.

Records of waste buried in SWSAs 3, 4, and part of 5 were destroyed by a fire in 1957.^(a) Therefore, information on the waste buried in these areas is extremely limited. However, SWSAs 3, 4, and 5 are known to have several shallow trenches for TRU and LLW disposal.

SWSA 5 contains most of the TRU waste storage facilities at Oak Ridge. Contact-handled (CH) TRU waste in drums and boxes is stored in below-grade facilities constructed of concrete blocks. Retrievable remote-handled (RH) TRU in concrete casks is stored in a bunker. Non-retrievable RH TRU in casks is buried in trenches.

TRU waste at Oak Ridge has many different forms. Contact-handled TRU consists of paper, glass, plastic, shoe covers, and other miscellaneous waste from glovebox operations, and is usually stored in 55-gallon drums and 4 x 4 x 6-ft boxes. This RH TRU waste consists of paper, glass, plastic tubing, and other miscellaneous waste from cell waste, HEPA filters, and discarded equipment. Remote-handled (RH) TRU is typically contained in cylindrical concrete casks 4.5 ft in diameter and 7.5 ft high; smaller containers such as 3-gallon plastic buckets, 1-gallon paint cans, and 5-gallon metal cans are also used to package this waste before it is placed into the concrete casks.

SWSA 6 has been used since 1969. It is an active disposal site for LLW and contains both above-grade and below-grade disposal units. Below-grade

(a) Letter, R. C. Mason (ORNL) to D. L. Stiles (PNL). March 20, 1992.
"Request for ORNL Waste Characterization Data for BWID Project."

disposal units used at Oak Ridge include silos, double-walled pipe wells, pipe-lined auger hole wells, and trenches. Beginning in 1986, certain solid waste management practices were initiated in SWSA 6; some areas of SWSA 6 were remediated under RCRA interim status closure and greater confinement disposal techniques were implemented. Current plans are to phase out below-grade disposal in SWSA 6 by December 1993 and begin closure of the site.

LLW at Oak Ridge has several different forms. LLW consists of compactible waste such as plastic bags, paper, light-gauge metal, and glass. Non-compactible LLW consists of heavy-gauge metal items and wood. Contact-handled (CH) LLW is also made up of solidified sludges, biological material, and debris contaminated with asbestos.

The above-grade disposal structure used at Oak Ridge is called a tumulus. Containerized LLW is loaded into rectangular vaults, stacked, placed on a curbed concrete pad, and covered with natural materials. Beginning in 1994, LLW will be disposed only in the above-grade tumulus Interim Waste Management Facility (IWMF). The IWMF will be closed in the early 2000s and new LLW disposal facilities are expected to begin operation (Martin Marietta 1991).

Figure 3.5 shows the makeup of the solid waste buried and stored at Oak Ridge (X-10). Ninety-six percent of the total volume is LLW, 3% is TRU, and 1% is LLMW stored at the site since 1986. A summary characterization of waste at Oak Ridge (X-10) is provided in Tables 3.21 through 3.24. The volumes shown in Table 3.21 are based upon a qualitative assessment of the best available information found during this study, primarily upon the IDB. The assumptions used to generate the estimates shown in the table are given in Appendix E.

Tables 3.22 and 3.23 describe the physical characteristics of the TRU and LLW at Oak Ridge (X-10). The hazardous constituents of the mixed waste are delineated in Table 3.24.

3.1.2.6 Rocky Flats Site

The Rocky Flats Site currently has two isolated areas containing buried solid waste: the 900 Area and the Original Plant Site outside the

FIGURE 3.5 Total Waste Volumes by Waste Type at Oak Ridge (X-10)

TABLE 3.21. Volumes of Radioactive Solid Waste (m^3) by Structure Type at Oak Ridge (X-10)^(a)

	Pre-1970		1971 - 1985		1986 - 1990				Pre-1970 - 1990	
	LLW	Suspect TRU	LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total
Structures										
Trenches	157,900	6,200	39,200	60		7,100				210,400
Auger Holes & Wells ^(b)										
Tumulus						900				900
Buildings & Bunkers				600			1,300	200		213,400
Total	157,900	6,200	39,200	600		8,000	1,300	200		213,400

(a) Volumes in shaded areas are estimates. See Appendix E for methodology.
(b) No documentation was found for quantifying waste volumes in auger holes and wells; this waste is included in trench volumes.

TABLE 3.22. Physical Characteristics of TRU Waste at Oak Ridge (X-10) (m³)^(a)

	Sludges	Combustibles	Non-Combustibles	Particulates	Filters	Other	Total
Trenches	2,700	2,100	1,300	20	100	40	6,300
Auger Hoes & Wells							
Tumulus							
Buildings & Bunkers	400	300	200	0	20	0	800
Total	3,000	2,400	1,500	20	200	50	7,100

(a) Volumes in shaded areas are estimates. See Appendix E for methodology.

TABLE 3.23. Physical Characteristics of LLW and LLMW at Oak Ridge (X-10) (m³)^(a)

	Bio-logical	Contaminated Equipment	Debris	Dry Solids	Solidified Sludges	Other	Total
Trenches	32,300	74,600	7,900	63,600	21,900	3,900	204,100
Auger Holes & Wells ^(b)							
Tumulus	100	300	40	300	100	20	900
Buildings & Bunkers		500	200	400	200	50	1,300
Total	32,500	75,400	8,100	64,000	22,300	3,900	206,300

(a) Volumes in shaded areas are estimates. See Appendix E for methodology.
(b) No documentation was found for quantifying waste volumes in auger holes and wells. This waste is included in trench volumes.

TABLE 3.24. Hazardous Constituents of LLMW at Oak Ridge (X-10) (m³)^(a)

	Ignitable	Reactive	Corrosive	Toxic	Listed RCRA Wastes	PCBs	Total
Trenches							
Auger Holes & Wells							
Tumulus							
Buildings & Bunkers	50		0	60	1,200		1,300
Total	50		0	60	1,200		1,300

(a) Volumes in shaded areas are estimates. See Appendix E for methodology.

security-fenced area. All other waste that was buried at the facility was removed during an onsite radiometric survey performed from 1975 to 1983 by Rockwell International Corporation.

The 900 Area and the Original Plant Site contain waste buried in trenches, landfills and pits. The burial trenches, which were used from 1954 to 1968, contain depleted uranium, flattened depleted-uranium-contaminated drums, and sanitary sewer sludge; the waste is assumed to be LLMW.

The pits were used from 1956 to 1965 for burning depleted-uranium-contaminated oils. These pits were closed and covered in place; the types and amounts of hazardous substances that may remain in these structures is unknown, but it is assumed that this waste is LLMW.

Two landfills exist at the Rocky Flats. The original onsite landfill was used from 1952 to 1968 for disposal of general plant wastes, but approximately 44 lb of depleted uranium was also buried here (DOE 1986). The landfill has an estimated volume of 56,500 m³. The present landfill was placed in service in 1968 and receives an estimated 9 million lb of waste annually. Records show that this landfill received about 2200 lb of sanitary sewage sludge between 1968 and 1970 that potentially contains heavy metals and radioactivity.

All solid radioactive wastes currently generated at the RFP are packaged for treatment, decontaminated, or placed in drums to be shipped to an offsite DOE facility. Figure 3.6 shows the makeup of the solid waste buried and stored at Rocky Flats. Ninety percent of the total volume is TRU, and 10% is LLMW stored at the site. A summary characterization of waste at Rocky Flats is provided in Tables 3.25 through 3.28. The volumes shown in Table 3.25 are based upon a qualitative assessment of the best available information found during this study, primarily upon the IDB. The assumptions used to generate the estimates shown in the table are given in Appendix F.

Tables 3.26 and 3.27 describe the physical characteristics of the TRU and LLW at Rocky Flats. The hazardous constituents of the mixed waste are delineated in Table 3.28.

FIGURE 3.6 Total Waste Volumes by Waste Type at Rocky Flats

TABLE 3.25. Volumes of Buried Radioactive Solid Waste (m³) by Structure Type at Rocky Flats^(a)

	Pre-1970			1971 - 1985			1986 - 1990			Pre-1970 - 1990	
Structures	LLW	Suspect TRU		LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total
Trenches (b)	(b)										
Storage Buildings								8,500	900		9,400
Total								8,500	900		9,400

(a) Volumes in shaded areas are estimates. See Appendix F for methodology.
(b) Trenches were used between 1954 and 1968. No volumes are reported in the IDB (DOE 1991).

(a) Volumes in shaded areas are estimates. See Appendix F for methodology.

(b) Trenches were used between 1954 and 1968. No volumes are reported in the IDB (DOE 1991).

TABLE 3.26. Physical Characteristics of TRU Waste at Rocky Flats (m³)^(a)

	Sludges	Combustibles	Non-Combustibles	Par-ticulates	Filters	Other	Total
Trenches							
Storage Buildings	300	10	400	10	10	50	900
Total	300	100	400	10	10	50	900
(a) Volumes in shaded areas are estimates. See Appendix F for methodology.							

TABLE 3.27. Physical Characteristics of LLW and LLMW at Rocky Flats (m³)^(a)

	Bio-logical	Contaminated Equipment	Debris	Dry Solids	Solidified Sludges	Other	Total
Trenches							
Storage Buildings				8,500			8,500
Total				8,500			8,500
(a) Volumes in shaded areas are estimates. See Appendix F for methodology.							

TABLE 3.28. Hazardous Constituents of LLMW at Rocky Flats (m³)^(a)

	Ignitable	Reactive	Corrosive	Toxic	Listed RCRA Wastes	PCBs	Total
Trenches							
Storage Buildings	0			40	8,400	10	8,500
Total	0			40	8,400	10	8,500
(a) Volumes in shaded areas are estimates. See Appendix F for methodology.							

3.2 CHARACTERISTICS OF BURIED WASTE STRUCTURES

This section addresses the environment within which the waste is contained as it relates to retrieval or in situ management techniques, and will include information on such things as typical trench profiles, overburden amounts, and possible plumes within the sediment.

3.2.1 Overall Complex-Wide Summary

This section identifies the major buried waste sites across the DOE complex. General information will be presented for each of the sites, e.g.,

typical trench designs and overburden amounts. This information will make possible a better understanding of the similarities and differences of the site-specific information presented in the following section.

3.2.2 Site-Specific Information

3.2.2.1 Idaho National Engineering Laboratory

The Radioactive Waste Management Complex (RWMC) contains the major amount of radioactive solid waste at INEL. The RWMC is 154 acres in area, and the burial ground within RWMC covers 88 acres. The average annual rainfall at INEL is 8.5 in., and the water table is 200-600 ft below the surface.

The soils consist mainly of silts, clays, and sands, with some gravel. In general, 85% of the sediments are clayey silts. Surface sediments range from 0-23 ft deep, and the average elevation is 5010 ft above sea level.

Pits and trenches are the primary burial structures. A basalt layer underlies the burial ground, allowing a maximum depth of 20 ft for burial. Some pits are only 5 ft deep. Trenches and pits are generally excavated to bedrock and then backfilled 2-5 ft to level off the bottom.

Pits are quite large and have various shapes and dimensions. Trenches range from 100 to 1800 ft in length, 5 to 8 ft in width, and average 12 ft in depth.

3.2.2.2 Hanford

100 Areas. Some of the small burial grounds in the 100 Areas consist of a single trench or pit. Pieces of equipment with high dose rates were generally placed in narrow, deep trenches and partially covered with earth fill. Small crib pits (e.g., 8 x 8 ft pits made from railroad ties) and vertical steel pipes and culverts approximately 5 to 6 ft in diameter were often used for disposing of small reactor hardware with high dose rates.

All radioactive solid waste in the 100 Areas has been covered with a minimum of 4 ft of clean soil stabilized with gravel. Herbicides are used to keep deep-rooted plants from growing over the burial grounds.

Burial trenches are approximately 20 ft deep. The water table in the 100 Areas varies from 55 to 80 ft in some parts to approximately 33 ft in others.

200 Areas. Solid wastes are buried in trenches and caissons in the 200 Areas. Caissons primarily consist of a below grade, vertical silo approximately 12 ft high by 6 ft in diameter. Caissons are used for disposal of high-activity LLW and high-activity TRU.

Waste in the 200 Areas is also buried in two types of trenches: a V-trench and an industrial trench. V-trenches at Hanford are typically 16 ft deep with a base 0 to 16 ft wide. Slopes of this type of trench vary from 1:1 to 1.5:1; they are covered with a minimum of 8 ft of soil. An industrial trench can be as deep as 50 ft and has a wide bottom, typically 16 to 100 ft wide. Approximately 8 ft of soil is used to cover the waste buried in this type of trench; 4 ft of soil is used if the waste is to be retrieved later.

300 Area. The unsaturated zone is approximately 40 ft deep, with sand to silty sand and gravelly sand making up the top layer (approximately 9 ft deep) and sandy granule-pebble and sandy cobble-boulder gravel beneath it to the saturated zone.

3.2.2.3 Savannah River Site

Forty waste sites at the Savannah River Site have or might have received LLW or mixed waste. The 40 waste sites consist of basins, burning and rubble pits, the Ford Building waste site, the TNX burial ground, and the central radioactive waste burial grounds. This section of the report concentrates on the central radioactive burial grounds, where the major portion of buried radioactive solid waste is located.

The central radioactive burial grounds are located in Area G, between Areas F and H. There are three major radioactive burial grounds: the initial, now inactive, burial ground, 643-G; the active LLW burial ground, 643-7G; and the inactive mixed waste landfill, 643-28G, which is entirely within the boundaries of 643-7G. The burial grounds are on relatively level land, 300 ft above sea level.

The soil underlying the burial grounds consists of 1000 ft of mostly unconsolidated sands, sandy clays, and clays. Principal surface and near-surface soil is clayey sands consisting of about one-third clay.

The mean water table is 40 ft below ground and has a mean fluctuation of 2 ft, although fluctuations as great as 7 ft have been observed. The average annual rainfall is 47 in. Groundwater is at least 10 ft below the bottom of the radioactive waste trenches.

Cardboard and fiberboard boxes were used as final disposition containers until 1983 and were used in all three burial grounds. Rigid metal containers have been used in most cases since 1983 to allow for stacking. Rigid containers have included 55-gallon drums, 90-ft³ metal boxes, 45-ft³ boxes, and engineered (various sizes) boxes.

643-G. Radioactive wastes were buried in standard trenches in 643-G with 10 ft of soil between trenches. Standard trenches are normally 20 ft deep and 20 ft wide with various lengths (different sources report the longest trenches as 300 m and 300 ft long). The sides of the standard trenches are generally vertical.

Wastes were segregated by activity and buried in separate locations within the burial ground. Accurate records are maintained on the contents, radiation levels, and storage location of all waste. The locations of trenches are also documented.

Disposed wastes were generally in plastic bags, cardboard boxes, or bulk. Wastes were not stacked and were generally covered with a minimum of 4 ft of overburden.

Between 1965 and 1972, TRU waste was segregated by activity. Waste containing radionuclides at less than 0.1 Ci/package was buried unencapsulated in a segregated area until 1974. Wastes with TRU radionuclides at more than 0.1 Ci/package have either been placed in prefabricated concrete containers, with inside dimensions of 6 ft in diameter and 6.5 ft in height and with 6-in.-thick walls, called culverts; or encapsulated in concrete. Culverts were buried under a minimum of 4 ft of soil with a polyvinyl chloride sheet placed over the waste, 1 ft under the soil surface. The general package used

in culverts was 90-mil-thick polyethylene containers inside galvanized steel drums. TRU wastes with more than 0.1 Ci/package that did not fit in culverts were encapsulated in a concrete pour called a monolith.

643-7G. 643-7G consists of standard trenches, engineered low-level trenches (ELLTs), greater confinement disposal (GCD) boreholes, and storage pads. ELLTs are 22 ft deep with various widths and lengths, and generally have sloped (1:1) walls. Waste containers (e.g., metal boxes and drums) are stacked in ELLTs, unlike standard trenches where waste is dumped. ELLTs hold LLW (Savannah River LLW and ILW) primarily in carbon steel engineered boxes stacked four high in step fashion. Space between the sloped walls and stacked waste is filled with 55-gallon drums, bulky containerized waste, or dirty soil. Savannah River started using ELLTs in 1985.

Before 1985, the burial practices (e.g., containers, trenches) and treatment of TRU were identical to those used for 643-G. Since 1985, LLW has been buried in ELLTs in carbon steel engineered boxes or drums, and trench alpha waste has been buried in standard trenches (with depths of up to 27 ft since 1987) with 6 ft of gravel added to the bottom of the trenches for drainage. Low-level bulky items continued to be buried in standard trenches after 1985.

In 1974, TRU waste (greater than 10 nCi/g) started to be stored above ground in polyethylene-lined drums of 3/8-in. carbon steel on concrete pads. These were covered with a minimum of 4 ft of soil until 1985. Bulky TRU has been stored in carbon steel boxes on concrete pads or in standard trenches (high-activity) with a minimum of 6 ft of gravel in the bottom of the trench.

As of 1991 ILW, both containerized and non-containerized, is still disposed of in standard trenches, as is non-containerized LLW.

Some GCD facilities have been built for demonstration and are to be used for ILW. No waste had been stored in GCD facilities as of August 1991.

643-28G. 643-28G is an inactive closure facility for mixed waste located within the boundaries of 643-7G. There are a number of individual standard burial trenches and two container storage buildings.

3.2.2.4 Los Alamos National Laboratory

There are 15 different areas that have been used for waste disposal at Los Alamos; at least nine may contain radioactive solid waste. All 15 areas are located atop mesas underlain by a minimum of 250 feet of volcanic tuff. Average rainfall is 18 in. per year, and the water table is 600-1200 ft below the Pajarito Plateau, where Los Alamos is located. All waste is buried below the soil level in the volcanic tuff.

Pits and shafts are the two major burial structures. Pits generally range from 400-600 ft long, 25-100 ft wide, and 25-40 ft deep, and have very steep sloped sides (e.g., of the reported slopes in Area G, slopes range from 1:4 to 1:12). Shafts are generally 2-8 ft in diameter and 25-60 ft deep, and may be lined or unlined. Pits have a minimum of 3 ft of mounded tuff over 3 ft of excavated tuff for an overburden. Shafts are usually filled with tuff and capped with a 3-ft concrete cap (to ground level) with an additional 3 ft of mounded concrete added above ground.

Waste is generally thrown into the burial pits, except for sludge drums that have been stacked in the pits since 1971 for possible retrieval. Early practice was to fill the pit with waste and then cover with tuff. Wastes are now layered in the pits with 6 in. of backfill placed over each layer.

Area A. Area A has nine disposal pits and two storage tanks. The pits used in the 1940s are 12 ft deep and 15 ft wide. The pit used for building debris in the 1960s and 1970s is 22 ft deep. The other dimensions of the debris pit differ with different reports. The tanks in Area A are 12 ft in diameter and 62 ft, 10 in. long. The tanks are in 12-ft-deep pits on 4-ft, 10-in. concrete piers (2 ft below pit bottom). Sand fills the space below the tanks and packed earth fills the pit to ground level. Loose earth was used to 1.5 ft above the tanks and then capped with an 8-in. slab of concrete, with another 1.5 ft of earth placed over the slab.

Area B. Area B contains at least five (the actual number is unknown) pits with estimated depths of 12 to 20 ft. Pits in Area B were filled with waste prior to backfilling. Subsidence was filled with clean concrete and dirt from construction sites. There is a chemical disposal trench 2 ft wide,

40 ft long, and 3 ft deep. The western two-thirds of the area has been covered with asphalt and is being used as a public rental storage area. Approximately 3 ft of additional covering was added in 1984.

Area C. Four pits measure 610 x 40 x 18 ft deep, one is 110 x 705 x 18 ft deep, one is 100 x 505 x 23 ft deep, and a chemical pit is 25 x 180 x 12 ft deep. There are also 107 shafts ranging from 1 to 2 ft in diameter and from 10 to 25 ft deep. The 1-ft-diameter shafts are lined with 1 ft of concrete.

The pits are covered with 6 in. to 3 ft of topsoil over 1.5 ft of tuff.

Area D. Area D was used for underground explosives testing. Two shafts, one 20 x 30 x 45 ft deep and another 6 x 8 x 46 ft deep, were constructed. Shaft sides were shored up with 2 x 12 in. timbers. Chambers for explosives testing were placed in the bottom of the shafts, which were then backfilled prior to testing.

Area E. Area E was used for underground explosives testing and radioactive solid waste burial. There is one underground chamber similar to those discussed for Area D. There are six pits in Area E: Pits 1 through 4 are shallow, 6-7 ft deep. Pit 1 is 15 x 75 ft, Pit 2 is 15 x 45 ft, Pit 3 is approximately 5 ft in diameter, and Pit 4 is 15 x 100 ft. Pits 5 and 6 are 12 x 80 ft and 12 x 63 ft, respectively, and have no waste reported.

Area F. Very little reliable information exists for Area F. Area F is reportedly composed of shallow pits and trenches ranging in size from 2 x 2 x 4 ft deep to 40 x 70 x 4 ft deep.

Area G. Area G is an active burial ground containing waste pits, shafts, three trenches, and two tanks. There are at least 30 pits in Area G; some large pits are 100 x 600 x 25 ft deep. Smaller pits are of various sizes, but the general range is from 100 to 600 ft long, 25 to 100 ft wide, and 25 to 40 ft deep.

Most of the TRU waste is currently stored on four asphalt pads measuring 40 x 408 ft. Uncertified TRU waste packages, drums, and crates are stacked 12 to 16 ft high. As the waste accumulates, the tops and sides are covered with plywood, and the entire stack is enclosed with nylon-reinforced vinyl

sheeting. The stack is then covered with 3 to 6 ft of tuff to create an artificial mound. A burial pit for TRU waste storage was handled in a similar manner.

Most of the LLW within the area is in pits, shafts, and trenches, and on pads of varying dimensions. Maximum land usage has been achieved by leaving minimal space between burial structures and by placing TRU and LLMW storage pads and buildings on top of older LLW burial pits.

Pit 9 is used for storing retrievable TRU. The bottom of Pit 9 has been graded and paved with asphalt.

Pit 19 has alpha contamination and "Cancer Suspect Research" waste. The alpha-contaminated waste on the bottom of the trench was covered with a plastic liner and 6 in. of tuff to keep the alpha contamination from spreading to the cancer research waste.

Use of disposal shafts in Area G started in 1966. Shafts range from 1 to 6 ft in diameter and from 25 to 60 ft in depth. Lined, 3-ft-diameter shafts have a 12 in. diameter, 1-ft-thick metal tube as a liner, with cement surrounding the liner.

Three trenches hold casks of wastes that have emitted or are emitting nuclear heat or radiation or are forming radiolytic gas. All three trenches are 13 ft wide; A and B are 6 ft deep, and C is 8 ft deep. A and B have 2-ft-deep, 3-ft-diameter holes augured into the bottom of the trenches. Concrete casks, each holding two 30-gallon drums, are placed in each hole and sealed with an asphalt material; they are arranged in arrays of 20 casks. Arrays are separated by 5 ft of crushed tuff. Each array is covered with corrugated "Q-Decking." The hole is backfilled with tuff to the cask rims. After the "Q-Decking" has been put in place, another 3 ft of crushed tuff is used as covering. Trench A contains 120 casks; trenches B and C contain 100 casks each.

Area T. Area T has 15-65-ft deep shafts with diameters ranging from 6 to 8 ft for liquid waste mixed with cement. Fifty-six of the 62 shafts contain TRU. Retrievable TRU is mixed with cement and pumped into 20 ft x 30 in.

sections of corrugated metal pipe and placed vertically in a 120 x 24 x 19 ft deep pit. Each end of the pipes has a 1-ft concrete cap.

The 115 absorption beds in Area T are 120 x 20 x 4 ft deep. The beds have had the material at the bottom removed and have been filled with 2 ft of stone, 6 in. of gravel, 6 in. of sand, and 12 in. of earth.

3.2.2.5 Oak Ridge National Laboratory

The geologic formations present at the Oak Ridge Reservation are of sedimentary origin, either limestone, dolomite, sandstone, or shale. The rock is covered by a mantle of residual alluvial and colluvial material up to 100 ft thick. The water table fluctuates from 1 to 67 ft below the surface. The average annual precipitation measured in the Oak Ridge vicinity is 54.4 in.; the average snowfall is 10.4 in.

Burial structure description data has primarily been compiled for SWSA 6. SWSA 6 has used a variety of techniques for disposal, of which most are positioned below grade. These include concrete silos, wells in silos, double-walled pipe wells, lined auger holes, and unlined trenches. The tumulus is the only above-grade disposal structure used in the SWSA 6.

All RH LLW > 1 rem/h is shipped to SWSA 6 in shielded, bottom-unloading casks and disposed of in the various types of wells. The type of well facility used depends largely upon the configuration of the waste package.

Concrete silos are used for most CH LLW and some RH LLW less than 1 rem/hr and are located in separate areas of SWSA 6. These silos are constructed of two 16-gauge, corrugated steel pipes, one 8 ft and the other 9 ft in diameter. The smaller pipe is placed concentrically inside the larger pipe, and both are placed vertically in a trench. The annular space between the two pipes is filled with concrete. The pipes range from 14 to 20 ft in length, depending upon the depth of the water table at a given location. A wire-reinforced, 12-in.-thick concrete pad is poured in the bottom of the silo. The silos are aligned in clusters within a trench. The depth of the trench is always located and dug with its lowest point a minimum of 2 ft above the maximum water table elevation.

Fill dirt is placed around the silos, leaving the tops of the silos at grade. More fill is added as required to compensate for settling; this facilitates water runoff away from the silo. The silo is capped with a 12-in.-thick, steel-reinforced concrete cap, and used for CH and RH LLW.

Concrete silos with containment wells are a modified version of the concrete silo described above and are used for disposal of RH LLW (> 1 rem/hr). Seven to eleven 20-in.-diameter by 20-ft-long cast iron pipes are placed vertically in a geometric array within the 8-ft inside diameter of the concrete silo. The annular space between the outside surface of the cast iron pipes and the inside surface of the concrete silos is filled with concrete. A 12- to 18-in. concrete base is poured into each pipe. Each pipe is filled to within 3 ft of the surface with waste and sealed with concrete.

Double-walled pipe wells are used for some RH LLW (1 rem/hr) contained in 55-gallon drums. These wells are constructed of two 11-gauge, corrugated steel drainage pipes 20 ft long placed in a drilled auger hole; one pipe is 36 in. in diameter and the other is 30 in. in diameter. The 30-in.-diameter pipe is placed concentrically inside the 36-in.-diameter pipe, with the tops of the pipes at ground level. The bottom of the well is a minimum of 2 ft above the maximum water table elevation. The space between the two pipes is filled with a concrete grout. A wire-reinforced, 12-in.-thick concrete plug is poured in the bottom of the well.

Only radioactive waste packaged in a 55-gallon drums is placed in the double-walled pipe well. The maximum radiation reading over the top of an open well must not exceed 200 mrem/hr. No limits exist on the amount of radioactive material placed in the well provided the radiation reading at the top is not exceeded. When the well is filled, it is capped with a 12-in.-thick, 48-in. outside diameter concrete collar. After closing and capping the well, the radiation reading over the top of the well must be less than 2.5 mrem/hr.

Pipe-lined auger hole wells are also used to dispose of some very high-activity RH LLW. These are constructed of a 3/4-in.-thick cast iron pipe vertically centered in a drilled auger hole; the surrounding space is backfilled

with dirt. The pipes are 20 ft long and have an inside diameter of 20 in. A 12-in.-thick concrete plug is poured in the bottom of the auger hole.

Very high-activity (> 1 rem/hr) RH LLW in waste containers 20 in. in diameter are placed in these wells. After an auger hole is filled, the hole is capped with a 12-in.-thick, 48-in. outside diameter concrete collar. After closing and capping the hole, the radiation reading over the top of the hole must be less than 2.5 mrem/hr.

Trenches are used for disposal of biological waste. The trenches are approximately 50 ft long and 10 ft wide; the depth depends upon the water table elevation. The lowest point in the trench is at least 2 ft above the known maximum water table elevation. Spacing between adjacent trenches is at least 5 ft. Trenches are graded to slope to one end at a rate of approximately 0.5 in./ft. Surface water drainage is controlled by separate ditching around the trench that conforms to existing topographic conditions. Trenches are sectioned by removable steel plates to improve efficiency of land usage and prevent sidewall collapse.

An open landfill in the northeast area of SWSA 6 is used for disposal of materials that register no external radiation but cannot be certified as free of contamination. This disposal area covers approximately one acre. Soil is used to cover the waste after disposal.

The above-grade disposal structure used at Oak Ridge is called a tumulus. Rectangular vaults approximately 7 ft, 10 in. long are filled with containerized LLW. The void spaces are filled with concrete before the lid is placed on the vault and sealed. Vaults are stacked on a curbed concrete pad and covered with natural materials. The pad is approximately 60 x 90 ft, an average of 12 in. thick, and constructed of high-density concrete reinforced with epoxy-coated steel. A total of 510 vaults have been filled and placed on two tumulus pads. Beginning in 1994, LLW will be disposed only in the above-grade tumulus Interim Waste Management Facility (IWMF). The IWMF will be closed in the early 2000s, and new LLW disposal facilities are expected to begin operation. (Martin Marietta 1991).

3.2.2.6 Rocky Flats Plant

The Rocky Flats Plant currently has two isolated areas containing buried solid waste: the 900 area and the Original Plant Site outside the security-fenced area. All other waste that was buried at the site was removed during an onsite radiometric survey performed from 1975 to 1983 by Rockwell International Corporation.

The plant is located on a geological bench that slopes to the east at an average gradient of 95 ft per mile. The land consists of stony soils made up of gravel and cobbles intermixed with sand and clay. The environment is arid with minimal rainfall, drying winds, and a porous gravel sediment.

4.0 OTHER CONTAMINATED SITES FOR WHICH BURIED WASTE TECHNOLOGIES MAY BE APPLICABLE

This chapter addresses those sites at the six DOE facilities at which containerized wastes were not buried, but whose site characteristics are such that the technologies needed for retrieval and remediation of buried waste structures may generally be applicable. Examples of such sites include cribs, ditches, ponds, and basins.

The data used to summarize the information contained in this section were gathered from environmental release records for each DOE facility. These environmental releases, or release sites, include any site where spilling, leaking, discharging, leaching, or dumping of contaminants into the environment has occurred. The data quantifying the volumes of contaminated soils associated with these releases are based upon the size of the release site; additional volume of soils that may be associated with the release are not included. Therefore, the volumes reported in this section may understate the actual volume of contaminated soils.

Because each of the individual DOE facilities included in this assessment is at a different stage in developing the data required for this assessment, the completeness of the information summarized for each facility varies. Data for some of the facilities are quite limited and, at times, inconsistent with other facilities, because each has a different definition for a release site. For example, some sites only provide data on release sites that meet the EPA's definition of a Solid Waste Management Unit (SWMU). An SWMU is defined as "any discernable unit at which solid wastes have been placed at a time, irrespective of whether the unit was intended for the management of solid or hazardous wastes. Such units include any area at a facility where solid wastes have been routinely and systematically released" (55 FR 30808) (proposed subpart S to the RCRA regulations in 40 CFR 264). Areas that treated or stored source, special nuclear, or by-product material as defined under the Atomic Energy Act are specifically excluded as required by federal regulations under RCRA (40 CFR 261.4(a)(4)). Both Los Alamos and the Hanford

Site include all release sites from which or to which radioactive materials have been released. Consequently, the release sites identified by these two installations is more expansive.

For purposes of this assessment, a release site is defined as the lowest level of available information on an SWMU. These inconsistencies were resolved by identifying a common set of site and waste categories and then mapping each facility's categories into the BWID site categories delineated in Table 4.1.

Additional information was gathered for the contaminants associated with each of the release sites. Unfortunately, these data are limited because few of the release sites have been fully characterized. The waste categories used to describe the various sites include LLW, LLMW, TRU, TRUM, mixed heavy metals, mixed organics, and mixed heavy metals and organics. Definitions of these terms are provided in the glossary.

4.1 OVERALL COMPLEX-WIDE SUMMARY

An estimated 4.7 million m³ of contaminated soils are contained in above-ground liquid impoundments, below-ground liquid impoundments and disposal units, and other contaminated soil sites. An additional 1 million m³ of nonradioactive contaminated sites have been identified to date. However, only

TABLE 4.1. Site Types and BWID Site Categories

Complex-Wide Contaminated Site Types	BWID Site Categories
Contaminated soils Pu-contaminated soils	Contaminated soils
Ponds Ditches Basins	Above-ground liquid impoundments
Cribs	Below-ground liquid impoundments, disposal units

the radioactive contaminated soil sites are included in this preliminary assessment. The volumes of waste associated with each of these sites were given in Table 2.2.

At the time this report was compiled, volume and characterization information was found for nearly 30% of the contaminated sites across the DOE complex. Therefore, the volumes reported in this assessment are only for those sites that have been characterized, and could substantially understate the total volumes. This information is summarized in Table 4.2.

4.2 SITE-SPECIFIC INFORMATION

Only 506 of the 1795 sites are characterized well enough to assess the waste types (i.e., LLW, TRU, LLMW, TRUM, mixed heavy metals, mixed heavy metals and organics, nonradioactive hazardous materials, or nonradioactive nonhazardous materials) at each of the sites included in this assessment. Table 4.3 shows a breakdown for each of the sites and associated waste types. Approximately 70% of the total volume is LLMW, 18% is mixed heavy metals and organics, 8% of the waste is LLW, and 4% is made up of the remaining waste types.

Further details for total volume of waste at each of the DOE facilities are provided in the following sections.

TABLE 4.2. Other Contaminated Sites Throughout the DOE Complex

	Total Sites Contaminated	No. of Sites With Data	Volume (m ³) ^(a)
Above-Ground Liquid Impoundment	343	178	2,900,000
Below-Ground Liquid Impoundment	550	266	270,000
Contaminated Soils	902	62	1,600,000
TOTAL	1,795	506	4,700,000
(a) Volumes reported are for sites with data and have been rounded. Volumes have not been extrapolated to include sites without data.			

TABLE 4.3. Waste Types at Other Contaminated Sites Throughout the DOE Complex (Volumes in m³)

Waste Category	Above-Ground Liquid Impoundment	Below-Ground Liquid Impoundment	Contaminated Soils
LLW	350,000	53,000	2,200
TRU	3,000	230	
LLW/TRU	2,200	160	
LLMW	1,600,000	205,000	1,600,000
TRUM	140,000	11,008	
Mixed Heavy Metals	14,000	1	
Mixed Heavy Metals and Organics	860,000	10	
Mixed Organics	160	4	

4.2.1 Idaho National Engineering Laboratory (INEL)

INEL has identified a total of 27 contaminated soil sites. The 19 sites that have been characterized account for approximately 870,000 m³ of contaminated soils in the DOE complex. A large portion of these are above-ground liquid impoundments that are contaminated with mixed heavy metals and organics. Data on these release sites were obtained from the Environmental Restoration Program Waste Management Unit Information for INEL.^(a)

Table 4.4 shows a breakdown for each of the site types at INEL and the various waste types known to be present. Appendix A contains a table illustrating how INEL's site categories were mapped into the BWID categories developed for this document.

4.2.2 Hanford

The Hanford Site has identified a total of 751 contaminated soil sites. The 330 that have been characterized account for approximately 2,000,000 m³ of contaminated soils. Most of these sites are above-ground liquid

(a) Letter from Jerry Lyle (DOE-ID) to Steve Short (PNL) dated August 27, 1991.

TABLE 4.4. Waste Types at Other Contaminated Sites at the INEL Facility (Volumes in m³)

	Above-Ground Liquid Impoundment	Below-Ground Liquid Impoundment	Contaminated Soils
LLW	110	4	
TRU			
LLW/TRU			
Mixed Heavy Metals	14,000	1	
Mixed Heavy Metals and Organics	860,000	10	
LLMW	120	15	
Mixed Organics	160	4	
TRUM			

impoundments contaminated with LLMW. Data on these release sites were obtained from the Hanford Site Waste Management Units Report (DOE 1989), Hanford Site Waste Information Data System (1991) and the Environmental Site Information system available from the Waste Information Network (WIN).

Table 4.5 shows a breakdown for each of the site types at the Hanford Site and the various waste types known to be present. Appendix B contains a table showing how Hanford's site categories were mapped into the BWID categories developed for this document.

4.2.3 Savannah River

The Savannah River Site has identified a total of 21 contaminated soil sites. The 18 sites that have been characterized account for approximately 100,000 m³ of contaminated soils. All of these are above-ground liquid impoundments contaminated with LLW. Data on these release sites were obtained from the Environmental Restoration Information System available on the WIN system and Waste Management Units-Savannah River Site (WSRC 1989).

Table 4.6 shows a breakdown for each of the site types at the Savannah River Site and the various waste types known to be present. Appendix C

TABLE 4.5. Waste Types at Other Contaminated Sites at the Hanford Facility (Volumes in m³)

	Above-Ground Liquid Impoundment	Below-Ground Liquid Impoundment	Contaminated Soils
LLW	240,000	53,000	90
TRU			
LLW/TRU			
Mixed Heavy Metals			
Mixed Heavy Metals and Organics			
Mixed LLW	1,500,000	200,000	37,000
Mixed Organics			
Mixed TRU	4,000	11,000	

TABLE 4.6. Waste Types at Other Contaminated Sites at the Savannah River Facility (Volumes in m³)

	Above-Ground Liquid Impoundment	Below-Ground Liquid Impoundment	Contaminated Soils
LLW	110,000		
TRU			
LLW/TRU			
Mixed Heavy Metals			
Mixed Heavy Metals and Organics			
Mixed LLW			
Mixed Organics			
Mixed TRU			

contains a table showing how Savannah River's site categories were mapped into the BWID categories developed for this document.

4.2.4 Los Alamos

Los Alamos has identified 626 contaminated soil sites. The 118 sites that have been characterized account for approximately 1,540,000 m³ of contaminated soils. Most of these sites are contaminated with LLMW. Data on these release sites were obtained from Los Alamos National Laboratory Solid Waste Management Units Report (LANL 1990).

Table 4.7 shows a breakdown for each of the site types at Los Alamos and the various waste types known to be present. Appendix D contains a table showing how Los Alamos site categories were mapped into the BWID categories developed for this document.

4.2.5 Oak Ridge

The Oak Ridge Site (X-10) has identified 76 contaminated soil sites. The 17 sites that have been characterized account for approximately 140,000 m³

TABLE 4.7. Waste Types at Other Contaminated Sites at Los Alamos (Volumes in m³)

	Above-Ground Liquid Impoundment	Below-Ground Liquid Impoundment	Contaminated Soils
LLW		15	4
TRU			
LLW/TRU			
Mixed Heavy Metals			
Mixed Heavy Metals and Organics			
Mixed LLW	34,000	250	1,540,000
Mixed Organics			
Mixed TRU	1,100	10	

of contaminated soils. Most of these are above-ground liquid impoundments. Data on these release sites were obtained from Oak Ridge Reservation SWMU Sites Database.

Table 4.8 shows a breakdown for each of the site types at Oak Ridge and the various waste types known to be present. Appendix E contains a table showing how Oak Ridge's site categories were mapped into the BWID categories developed for this document.

4.2.6 Rocky Flats

No contaminated soil sites are currently identified at Rocky Flats.

4.2.7 Other DOE Sites

Approximately 24,000 m³ of contaminated soils have been identified at other DOE sites, including Argonne National Laboratory, Fernald, Nevada Test Site, Pinellas, and the K-25 and Y-12 Sites at Oak Ridge. Above-ground liquid impoundments have been characterized and account for approximately 22,000 m³ of contaminated soils. Table 4.9 shows a breakdown for each of the site types

TABLE 4.8. Waste Types at Other Contaminated Sites at Oak Ridge (X-10) (Volumes in m³)

	Above-Ground Liquid Impoundment	Below-Ground Liquid Impoundment	Contaminated Soils
LLW	3,000		
TRU	3,000	230	
LLW/TRU	2,200	160	
Mixed Heavy Metals			
Mixed Heavy Metals and Organics			
Mixed LLW	6,200	230	
Mixed Organics			
Mixed TRU	130,000		

**TABLE 4.9. Waste Types at Other Contaminated Sites at
Other DOE Facilities (Volume in m³)**

	Above-Ground Liquid Impoundment	Below-Ground Liquid Impoundment	Contaminated Soils
LLW	22,000	120	2,100
TRU			
LLW/TRU		60	
Mixed Heavy Metals			
Mixed Heavy Metals and Organics			

at each of these sites and the various waste types known to be present. Appendix G contains a table showing how "Other DOE Sites" contaminated soil categories were mapped into the BWID categories developed for this document.

5.0 INFORMATION SOURCES AND CONTACTS

This section identifies the major information sources and contacts used in developing this report.

5.1 INFORMATION SOURCES

The major sources of information used to develop this report are listed below. Not all of the documents listed here are cited in the text. Many were used as background and supplementary material. These information sources were supplemented by contacts with various personnel throughout the DOE complex and are identified in the following section.

5.2 REFERENCES

55 FR 30800. 1990. Federal Register. Vol. 55, No. 145.

Idaho National Engineering Laboratory (INEL). 1976. Draft Environmental Impact Statement. ERDA-1536, Waste Management Operations, INEL, Idaho Falls, Idaho.

Los Alamos National Laboratory (LANL). 1987. Los Alamos National Laboratory Input for the Comprehensive Implementation Plan for DOE Defense Buried TRU Waste. LANL, Los Alamos, New Mexico.

Los Alamos National Laboratory (LANL). 1990. Los Alamos National Laboratory Solid Waste Management Units Report. LAUR 90-3400 Volumes I to IV, Los Alamos, New Mexico.

Martin Marietta Energy Systems, Inc. 1991. Oak Ridge National Laboratory Waste Management Plan. ORNL/TM-11433/R1, Oak Ridge, Tennessee.

Miller, R. L., and R. K. Wahlen. 1987. Estimates of Solid Waste Buried in 100 Area Burial Grounds. WHC-EP-0087, Westinghouse Hanford Company, Richland, Washington.

Rogers, M. A. 1977. History and Environmental Setting of LANL Near-Surface Land Disposal Facilities for Radioactive Waste (Areas A, B, C, D, E, F, G, and T): A Source Document. Los Alamos National Laboratory, Los Alamos, New Mexico.

Stapp, D. C. 1993. Technology Needs for Remediation: Hanford and Other DOE Sites. PNL-8328, Pacific Northwest Laboratory, Richland, Washington.

U.S. Department of Energy (DOE). 1986. Comprehensive Environmental Assessment and Response Program Phase I: Installation Assessment Rocky Flats Plant. DOE/NBM-6011476, DOE Field Office, Albuquerque, New Mexico.

U.S. Department of Energy (DOE). 1989. Hanford Site Waste Management Units Report. DOE/RL 88-30 Volumes 1 and 2, DOE Field Office, Richland, Washington.

U.S. Department of Energy (DOE). 1991. Integrated Data Base for 1991: U.S. Spent Fuel and Radioactive Waste Inventories, Projections and Characteristics. DOE/RW-0006 Rev. 7, DOE, Washington, D.C.

5.3 BIBLIOGRAPHY

Anderson, B. C., J. D. Anderson, J. A. Demiter, D. R. Duncan, and D. C. McCann. 1990. Contact-Handled Transuranic Waste Characterization Based on Existing Records. WHC-EP-0225, Westinghouse Hanford Company, Richland, Washington.

Arrenholz, D. A., et al. 1991. Brief Analysis and Description of Transuranic Wastes in the Subsurface Disposal Area of the Radioactive Waste Management Complex at INEL. EGG-WTD-9438 Rev. 1, Idaho National Engineering Laboratory, Idaho Falls, Idaho.

Arrenholz, D. A., et al. 1991. Historical Report of Transuranic Waste Pits and Trenches at the Subsurface Disposal Area of the Radioactive Waste Management Complex at the INEL. WTD-91-027, Idaho National Engineering Laboratory, Idaho Falls, Idaho.

Bates, L. D. 1983. Radioactive Solid Waste Storage and Disposal at Oak Ridge National Laboratory, Description and Safety Analysis. ORNL/TM-8201, Union Carbide Corporation, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Brown, M. C. 1992. Quarterly Briefing Book on Environmental and Waste Management Activities. WHC-SP-0434-13, Westinghouse Hanford Company, Richland, Washington.

Bullock, M. G., et al. 1987. Implementation Plans for Buried Transuranic Waste and Stored Special-Case Waste at the Idaho National Engineering Laboratory. EGG-WT-7610, Idaho National Engineering Laboratory, Idaho Falls, Idaho.

Coobs, J. H., and J. R. Gissel. 1986. History of Disposal of Radioactive Wastes Into the Ground at Oak Ridge National Laboratory. ORNL/TM-10269, Martin Marietta Energy Systems, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Dorian, J. J., and R. U. Richards. 1978. Radiological Characterization on the Retired 100 Areas. UNI-946, United Nuclear Inc., Richland, Washington.

E. I. duPont de Nemours & Co. 1988. Safety Analysis - 200 Area Savannah River Plant Burial Grounds Operations. DPSTA-200-10 Supp. 8, E. I. duPont de Nemours & Co., Savannah River Laboratory, Aiken, South Carolina.

E. I. duPont de Nemours & Co. 1989. Draft Savannah River Site Environmental Impact Plan. DPSP-87-121-2-1, E. I. duPont de Nemours & Co., Aiken, South Carolina.

Jaegge, W. J., N. L. Kolb, B. B. Looney, I. W. Marine, O. A. Towler, and J. R. Cook. 1987. Environmental Information Document, Radioactive Burial Grounds. DPST-85-694, E. I. duPont de Nemours and Co., Aiken, South Carolina.

Los Alamos Scientific Laboratory (LASL). 1979. Final Environmental Impact Statement for Los Alamos Scientific Laboratory Site. Los Alamos, New Mexico.

National Research Council. 1985. The Management of Radioactive Waste at the Oak Ridge National Laboratory: A Technical Review. National Academy of Sciences.

Rocky Flats Plant. 1990. Inactive Waste Unit Summary Sheets for Rocky Flats Plant, Revision No. 1. Rocky Flats Plant, Golden, Colorado.

Savannah River Plant. 1977. Final Environmental Impact Statement. ERDA-1537, Waste Management Operations, Savannah River Plant, Aiken, South Carolina.

Sutherland, A., et al. 1987. Performance Assessment of Closure Alternatives for the 643-G Site. Rogers & Associates Engineering Corporation, Salt Lake City, Utah.

Trabalk, J.R. 1987. Buried TRU Wastes and TRU-Contaminated Soils at ORNL Remedial Action Program Sites: Program Strategy and Long-Range Planning. ORNL/RAP-8, Martin Marietta Energy Systems, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

U.S. Department of Energy (DOE). 1979. Defense TRU Waste - Alternatives for Long-Term Management of Defense TRU Waste at the Savannah River Plant. DOE/SR-WM-79-1, DOE, Aiken, South Carolina.

U.S. Department of Energy (DOE). 1987. Final Environmental Impact Statement, Waste Management Activities for Groundwater Protection, Savannah River Plant. DOE/EIS-0120, DOE, Aiken, South Carolina.

U.S. Department of Energy (DOE). 1989. Low-Level Burial Grounds Dangerous Waste Permit Application. DOE/RL 88-20 Volume 1, DOE Field Office, Richland, Washington.

U.S. Department of Energy (DOE). 1989. Low Level Burial Grounds, Dangerous Waste Permit Application. DOE/RL 88-20, DOE Field Office, Richland, Washington.

U.S. Department of Energy (DOE). 1990. Remedial Investigation/Feasibility Study Work Plan for the 300-FF-5 Operable Unit, Hanford Site, Richland, Washington. DOE/RL 89-14, DOE Field Office, Richland, Washington.

U.S. Department of Energy (DOE). 1990. Department of Energy Waste Information. DOE/HWP-97, DOE, Washington, D.C.

U.S. Department of Energy (DOE). 1991. Environmental Restoration and Waste Management Site-Specific Plan for the Richland Operations Office. DOE/RL-91-25, DOE Field Office, Richland, Washington.

U.S. Department of Energy (DOE). 1991. Final Phase II RCRA Facility Investigation Remedial Investigation. Environmental Restoration Program, DOE Rocky Flats Office, Golden, Colorado.

U.S. Department of Energy (DOE). 1992. Final Environmental Impact Statement, Defense Waste Processing Facility, Savannah River Plant. DOE/EIS-0082, DOE, Aiken, South Carolina.

Vigil, M. J. 1989. Subsurface Disposal Area (SDA) Waste Identification (1952-1970) Emphasis. EGG-WM-8727-Rev. 1, EG&G Idaho, Inc., Idaho Falls, Idaho.

Westinghouse Hanford Company (WHC). 1989. Characterization Study of Low-Level Mixed Waste in Retrievable Storage Units. WHC-EP-0245, WHC, Richland, Washington.

Westinghouse Hanford Company (WHC). 1989. Stored, Contact-Handled Transuranic Waste Characterization at the Hanford Site. WHC-EP-0223, WHC, Richland, Washington.

Westinghouse Hanford Company (WHC). 1991. Summary of Radioactive Waste Received in 200 Areas During Calendar Year 1990. WHC, Richland, Washington.

Westinghouse Savannah River Company (WSRC). 1989. Waste Management Units - Savannah River Site. WSRC-RP-89-898 Vol. 1 and 2, WSRC, Aiken, South Carolina.

Westinghouse Savannah River Company (WSRC). 1990. Savannah River Site Environmental Report. WSRC-IM-9128, WSRC, Aiken, South Carolina.

Westinghouse Savannah River Company (WSRC). 1991. Savannah River Site's Site Specific Plan. WSRC-RP-91-596, WSRC, Aiken, South Carolina.

5.4 INFORMATION CONTACTS

Table 5.1 provides a listing of the various people throughout the DOE complex who have provided input to this report or who have been identified as contacts for additional site-specific information.

TABLE 5.1. Information Contacts for BWID Characterization Information

Contact Name	Site	Telephone Number
Lee Norland Buried Waste Program Manager	INEL	208-526-8552
Jim Bischoff Operations Manager/Radioactive Waste Management Complex	INEL	208-526-2766
Jim Macanally	INEL	208-526-2835
Darlene Hagel	Hanford	509-376-4394
Serena Galstad Computer Support/Solid Waste Engineering	Hanford	509-376-4020
Jim Anderson	Hanford	509-376-4359
Ed Derr EM-7 Waste Management Group	Los Alamos	505-665-6151
E-Li Chen EM-7 Waste Management Group	Los Alamos	505-665-3961
Barry Drennon	Los Alamos	505-665-6496
Ray Garde	Los Alamos	505-668-7391
Mike Ray	Los Alamos	505-665-6496
James Cook	Savannah River	803-725-8183
B. D. Helton	Savannah River	803-725-5802
Jim Stumbaugh	Savannah River	803-557-1134
Joe Riddell	Savannah River	803-557-8765
Toni Moore	Rocky Flats	303-966-3005
Allan Schubert	Rocky Flats	303-966-5251
Jeff Gilpin (Y-12)	Oak Ridge	615-574-6809
TJ Abraham	Oak Ridge	615-574-3378
Darrell Daugherty (X-10)	Oak Ridge	615-574-8996
Jack Watson (K-25)	Oak Ridge	615-574-6795
Joe Haymore (K-25)	Oak Ridge	615-574-6795
Nelson Lingle (K-25)	Oak Ridge	615-576-5580

TABLE 5.1. (contd)

Contact Name	Site	Telephone Number
Sidney Garland (X-10)	Oak Ridge	615-574-8581
Doug Turner (X-10)	Oak Ridge	615-576-2017
Willy Brown (Y-12)	Oak Ridge	615-574-2369
Ron Dierolf (Paducah)	Oak Ridge	502-441-6319
Dennis Cope (Paducah)	Oak Ridge	502-441-6129
Terry Acox (Portsmouth)	Oak Ridge	614-897-2331
Richard Snyder (Portsmouth)	Oak Ridge	614-975-2322
Jim Bailey	Oak Ridge	615-576-4489
Jerome Miller	Oak Ridge	615-544-3680
Gary Conner (K-25)	Oak Ridge	615-574-9019
Clayton Gist (X-10)	Oak Ridge	615-576-6821
Norman Golchert	Argonne	708-252-3912
Kim Shippard	Livermore	510-294-1475
Wally Quaider	Fernald	513-738-6160
Robin Madisson	Nevada Test Site	702-295-2834
Jim Griffin	Mound	513-865-3831
Kim Fraiser	Mound	513-865-3748
Jim Brangon	Pinellis	813-541-8805

6.0 GLOSSARY

This glossary contains explanations of the terms, acronyms, and abbreviations used in this report.

ANL	Argonne National Laboratory
Buried waste:	Solid waste, usually but not always containerized, placed in subsurface locations and covered with overburden for the purpose of disposal or extended storage
BWID	Buried Waste Integrated Demonstration
CH TRU	Contact-handled transuranic (waste)
cpm	counts per minute
D&D	Decontamination & decommissioning
DOE	U.S. Department of Energy
ELLT	Engineered low-level trenches
EPA	U.S. Environmental Protection Agency
GCD	greater confinement disposal
Hazardous waste:	Under RCRA, any solid, liquid or combination of solid or liquid wastes, which, because of its physical, chemical or infectious characteristics, may pose a hazard when improperly managed. States (e.g., Washington) may impose further definition and restriction on hazardous wastes.
HEPA	High-efficiency particulate air (filter)
HLW	High-level waste
ID	Integrated demonstration
IDB	Integrated Data Base (maintained at ORNL)
ILW	Intermediate Level Waste
INEL	Idaho National Engineering Laboratory
In situ	Refers to treatment of contaminated areas in place, without excavation or other removal.
IWMF	Interim Waste Management Facility

LANL	Los Alamos National Laboratory
LLMW	low-level mixed waste
LLW	Low-level waste
ORNL	Oak Ridge National laboratory
OTD	DOE Office of Technology Development
RCRA	Resource Conservation and Recovery Act; regulates management and disposal of hazardous wastes currently generated, treated, stored, disposed or distributed.
Release:	Any occurrence in which a regulated substance is emitted into air, soil or water.
RFP	Rocky Flats Plant
RH TRU	Remote-handled transuranic
SNL	Sandia National Laboratory
Solid waste:	Any garbage, refuse or sludge, including solid, liquid, semisolid or contained gaseous material resulting from industrial, commercial, agricultural and mining operations, and community activities. Within the DOE complex, solid wastes are defined to exclude wastes contained in storage tanks, which are treated separately.
SRS	Savannah River Site
SWMU	Solid Waste Management Unit
TRU	Transuranic (waste)
TRUM	Transuranic mixed (waste)
WIPP	Waste Isolation Pilot Plant

APPENDIX A

INEL BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

APPENDIX A

INEL BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

<u>Provided Structure Categories</u>	<u>BWID Structure Categories</u>
Unplanned Releases	Contaminated Soil
Acid Pond	Above-Ground Liquid Impoundment
Cooling Tower Basin	
Disposal Pond	
Ditch	
Drainage Pond	
Evaporation Pond	
Lagoon	
Leach Field	
Leach Pond	
Pond	
Retention Basin	
Waste Pond	
Acid Pit	Below-Ground Liquid Impoundment/ Subsurface Disposal Unit
Disposal Well	
French Drain	
Injection Well	
Neutralization Pits	
Neutralization Sump	
Valve Pit	

Table A.1 contains an explanation of the methodology used in arriving at the estimated volumes of waste buried and/or stored at INEL.

TABLE A.1. Volume of Radioactive Solid Waste (m³) by Structure Type at INEL

Structures	Pre-1970		1971 - 1985			1986 - 1990				Pre-1970 - 1990
	LLW	Suspect TRU	LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total
Trenches	16,300 ^(a)	3,900 ^(b)	1,900 ^(c)							22,200
Pits	44,300 ^(d)	53,200 ^(e)	97,500 ^(g)			11,500 ^(h)	27,000 ⁽ⁱ⁾			233,400
Storage Pads				28,100 ^(j)				9,400		37,500
Total	60,600	57,100	99,400	28,100		11,500	27,000	9,400		293,000

(a) Approximately 53 trenches were filled by 1970 (EG&G 1992, p. A-5). Most of the remaining volume, or approximately 43 trenches, are assumed to contain LLW (Arrenholtz 1991, p. 9). This value is calculated by assuming a volume of 380 m³ per trench, so that a volume of 16,340 m³ was placed in the trenches. The value of 380 m³/trench was obtained by dividing the total amount of waste in trenches 1-10 by 10 (Arrenholtz 1991, p. 33).

(b) This calculation is based on data in Arrenholtz (1991). The calculation assumes that trenches 1-10 contain 3795 m³ of TRU (Table 1 and p. 5), and remaining trenches contain 123 m³ of TRU (p. 9).

(c) Approximately five trenches were filled between 1970 and 1985 (EG&G 1992, Table A.1). The volume of the trenches is not known, but it is assumed to be 1900 m³. Half the waste is assumed to be LLW and the other half is assumed to be suspect LLW.

(d) According to the DOE (1991, p. 112), 84,600 m³ of LLW was stored at INEL until 1975. The author assumed that 6,000 m³ per year (or 24,000 m³) was stored after 1970, so this amount is subtracted from the total. The amount estimated to be in trenches (16,340 m³) was also subtracted from the total to obtain a value of 44,260 m³.

(e) This value was calculated by subtracting the amount in trenches (3,918 m³) from the total of 57,100 obtained from the IDB (DOE 1991, p. 85).

(f) A total of 132,500 m³ is listed in the IDB (DOE 1991, p. 112). Pre-1970 LLW (60,600 m³) and the amount in trenches (950 m³) is subtracted from the total.

(g) A total of 27,536 m³ is listed in the IDB (DOE 1991, p. 87). The amount in trenches (950 m³) is subtracted from the total.

(h) According to EG&G (1992, Table A.1), only pit 18 received waste after 1986. The value obtained from the IDB (DOE 1991, p. 112) is assumed to have been placed in this pit.

(i) According to EG&G (1992, Table A.1), only pit 18 received waste after 1986. The value obtained from the IDB (DOE 1991, p. 206) is assumed to have been placed in this pit.

(j) The value is from the IDB (DOE 1991, p. 87). After 1970, all TRU was stored above ground on pads. Pad 3 is covered with a building, but it is still considered to be a pad (DOE 1988, pp. 4-27 to 4-31). The volume reported in the IDB (DOE 1991) was assumed to be for 20 years. Approximately 25% of the volume was assumed to be generated after 1985.

REFERENCES

Anderson, B. C., et al. 1990. Contact-Handled Transuranic Waste Characterization Based on Existing Records. WHC-EP-0225 Rev. 1, Westinghouse Hanford Company, Richland, Washington.

Arrenholtz, D. A., and J. L. Knight. 1991. Historical Report of Transuranic Waste Pits and Trenches at the Subsurface Disposal Area of the Radioactive Waste Management Complex at INEL. WTD-91-027, Idaho National Engineering Laboratory, EG&G Idaho Inc., Idaho Falls, Idaho.

EG&G Idaho, Inc. 1992. Thermal Processing System Concepts and Considerations for RWMC Buried Waste. EGG-WTD-10058, EG&G Idaho Inc., Idaho Falls, Idaho.

U.S. Department of Energy (DOE). 1988. Environmental Survey Preliminary Report. DOE/EH/OEV-22-P, DOE Idaho Field Office, Idaho Falls, Idaho.

U.S. Department of Energy (DOE). 1991. Integrated Data Base for 1991: U.S. Spent Fuel and Radioactive Waste Inventories, Projections, and Characteristics. DOE/RW-0006 Rev. 7, U.S. Department of Energy, Washington, D.C.

APPENDIX B

HANFORD BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

APPENDIX B

HANFORD BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

<u>Provided Structure Categories</u>	<u>BWID Structure Categories</u>
Unplanned Release	Contaminated Soil
Ditch	Above-Ground Liquid Impoundment
Pond	
Basin	
Sand Filter	
Trench	
Brine Pit	Below-Ground Liquid Impoundment/ Subsurface Disposal Unit
Crib	
Diversion Box	
Drain Field	
French Drain	
Receiving Well	
Reverse Well	
Silo	
Sump	
Valve Pit	

Table B.1 contains an explanation of the methodology used in arriving at the estimated volumes of waste buried and/or stored at Hanford.

TABLE B.1. Volumes of Radioactive Solid Waste (m³) by Structure Type at Hanford

Structures	Pre-1970			1971 - 1985			1986 - 1990				Pre-1970 - 1990	
	LLW	Suspect TRU		LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total	
Trenches	283,800 (a)	109,000 (b,c)		207,900 (a)	6,500 (d,e)	100 (f)	89,800 (a)	8,500 (g)	600 (h)	20 (i)	706,400	
Caissons					20 (i)				20 (i)		50	
Storage Pads								400 (m)			400	
Storage Buildings					200 (j)			1,900 (k)	400 (l)		2,500	
Total	283,800	109,000		207,900	6,500	100	89,800	10,800	11,000	20	709,300	

(a) This data was obtained from an internal memo written by F. M. Coony (WMC). "Hanford LLW Update to 1992 IDB, Rev.1." All LLW is assumed to be in trenches.

(b) This value is taken from the IDB (DOE 1991, p. 85). All pre-1970 TRU is assumed to be in trenches.

(c) Pre-1970 TRU includes soil mixed with solid TRU. It does not contain 32,000 m³ of soil contaminated with liquid TRU (DOE 1991, p.86).

(d) This value is derived from the total amount reported in the IDB (DOE 1991, p.87).

(e) This value is calculated by subtracting the containerized volumes and the TRU placed in trenches after 1986 (487 m³) from a total of 7,866 m³.

(f) This value is taken from Bergsman (1992, p. 86). Irradiated fuel is placed in shielded and sealed containers in 200 Area trenches.

(g) This value is taken from the IDB (DOE 1991, p. 206). The amount of LLMW assumed to be in buildings and storage pads is subtracted from the value in the IDB to calculate the amount in trenches.

(h) Values for this time period are calculated by adding the volumes of trenches with disposal dates after 1985 as listed in Anderson et al. (1990, Table 5.2). If only a portion of the trench was used during this time period, the volume was distributed evenly over the entire operational period of the trench, so that only waste deposited after 1985 was included in the total.

(i) Calculations based on data in Anderson (1991). Caissons assumed to contain TRU. Volume distributed evenly between two time periods. Includes caissons in the 200 Area only.

(j) Volumes for 212N and 212P Buildings from Anderson (1991, p. 55).

(k) See non-TRU volumes for 213W Compactor, CWC facilities, flammable storage module in Anderson (1991, p.32).

(l) See TRU volumes for TRUSAF and CWC facilities in Anderson (1991, p.56).

(m) See volumes for mixed waste storage pad in Anderson (1991).

REFERENCES

Anderson, J. D., D. C. McCann, and B. E. Poremba. 1991. Summary of Radioactive Solid Waste Received in the 200 Areas During Calendar Year 1990. WHC-EP-0125-3, Westinghouse Hanford Company, Richland, Washington.

Anderson, B. C., et al. 1990. Contact Handled TRU Waste Characterization Based on Existing Records. WHC-EP-0225, Westinghouse Hanford Company, Richland, Washington.

Bergsman, K. H. 1992. Hanford Irradiated Fuel Inventory Baseline. WHC-SD-CP-TI-175 Rev.0, Westinghouse Hanford Company, Richland, Washington.

U.S. Department of Energy (DOE). 1991. Integrated Data Base for 1991: U.S. Spent Fuel and Radioactive Waste Inventories, Projections, and Characteristics. DOE/RW-0006 Rev. 7, DOE, Washington, D.C.

APPENDIX C

SAVANNAH RIVER BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

APPENDIX C

SAVANNAH RIVER BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

<u>Provided Structure Categories</u>	<u>BWID Structure Categories</u>
General Surface Soil General Surface Soil Conatamination	Contaminated Soil
Above-Ground Liquid Impoundment Above-Ground Storage Facility	Above-Ground Liquid Impoundment
Below-Ground Liquid Impoundment Industrial Waste System Septic System	Below-Ground Liquid Impoundment/ Subsurface Disposal Unit

Table C.1 contains an explanation of the methodology used to arrive at the volumes of waste stored and/or buried at Savannah River.

TABLE C.1. Volumes of Radioactive Solid Waste (m³) by Structure Type at Savannah River

Structures	Pre-1970			1971 - 1985			1986 - 1990			Pre-1970 - 1990	
	LLW	Suspect TRU	Other	LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total
Trenches	177,600 (a)	4,300 (b)		280,800 (a)	200 (b)		154,700 (c)				617,600 (d)
Storage Pads				3,600	2,900 (e)				1,100 (e)		7,600 (d)
Storage Buildings								9,000 (f)			9,000 (d)
Total	177,600 (a)	4,300 (b)		284,400 (a)	3,200		154,700	9,000	1,100		634,200

(a) DuPont (1988) reports annual LLW rates of 22,420, 22,063, and 25,823 m³ for 1983, 1984, and 1985, respectively. The annual rate for 1971-1985 was assumed to be double the annual rate from 1952-1970, or 18,698³ and 9,349 m³/yr, respectively. These assumed numbers agree with the IDB (DOE 1991, p. 112), which gives a total of 201,400 m³ (20,000 m³/yr) with only 7,900 m³ produced in 1976.

(b) The numbers reported in the IDB (DOE 1991) were distributed using the distribution reported in DOE (1979).

(c) From the IDB (DOE 1991).

(d) Total breakdown results from adding annual breakdown. Percentages disagree with IDB (DOE 1990), which listed no LLMW in buildings. IDB numbers appear to be erroneous since TRU and LLMW generated during 1986-1990 is almost 2% of the total volume, which is greater than the 1% listed in the IDB for storage pad waste.

(e) Assuming a constant annual rate for TRU from 1971-1990, and given totals of 3,332 m³ (retrievably stored)(DOE 1991) and 238 m³ (in trenches) (DOE 1979).

(f) Assumed handled like TRU but stored in buildings (duPont 1988, pp. 3-2, 3-38, 3-39).

REFERENCES

DuPont de Nemours and Co. 1988. Safety Analysis - 200 Area, Savannah River Plant, Burial Ground Operations. DPSTSA-200-10 SUPP-8, duPont de Nemours and Co., Aiken, South Carolina.

U.S. Department of Energy (DOE). 1979. Defense TRU Waste - Alternatives for Long-Term Management of Defense Transuranic Waste at the Savannah River Plant. DOE/SR-WM-79-1, DOE Savannah River, Aiken, South Carolina.

U.S. Department of Energy (DOE). 1991. Integrated Data Base for 1991: U.S. Spent Fuel and Radioactive Waste Inventories, Projections, and Characteristics. DOE/RW-0006 Rev. 7, DOE, Washington, D.C.

APPENDIX D

LOS ALAMOS BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

APPENDIX D

LOS ALAMOS BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

<u>Provided Structure Categories</u>	<u>BWID Structure Categories</u>
Burning Pad	Contaminated Soil
Contaminated Soil	
Flash Pad	
Outfall	
Pu-contaminated soil	
Above-Ground Liquid Impoundments	Above-Ground Liquid Impoundment
Absorption Bed	
Ditch	
Leach Field	
Pond	
Sand Filter	
Sludge Drying Bed	
Surface Impoundment	
Trench	
Trough	
Acid Pit	Below-Ground Liquid Impoundment/ Subsurface Disposal Unit
Caissons	
Catch Basins	
Chlorinator	
Contact Chamber	
Decontamination Holes	
Decontamination Pits	
Drain Line	
Drainfield	
Dry Well	
Feed Line	
Manhole	
Seepage, Setting, and Septic Pits	
Sewer Line	
Sludge Drying Pit	
Subsurface Liquid Waste Disposal Unit	
Sump	

Table D.1 contains an explanation of the methodology used to arrive at the estimated volumes of buried and/or stored waste at Los Alamos.

TABLE D.1. Volumes of Radioactive Solid Waste (m³) by Structure Type at Los Alamos

Structures	Pre-1970		1971 - 1985				1986 - 1990				Pre-1970 - 1990	
	LLW	Suspect TRU	LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total		
Trenches			100	1,900 (a)				1,200 (a)		3,200		
Pits	85,300 (b)	4,800 (b)	101,300 (c)	1,900 (a)		23,400 (c)		1,200 (a)		217,900		
Shafts			100	1,900 (a)				1,200 (a)		3,200		
Storage Pads							300 (d)	7,600 (e)		7,900		
Total (f)	85,300	4,800	101,500	5,700		23,400	300	11,100		232,100		

(a) Assumed to be evenly distributed among structures used for buried TRU.
(b) All early waste assumed to be buried in pits (Rogers 1977).
(c) All LLW assumed buried in pits up to 1979 (LASL EIS 1979).
(d) Assumed stored in similar manner as TRU.
(e) Assumed all "stored waste" is on pads (DOE 1991).
(f) Total waste volumes were computed for each time period from Rogers (1977). The LLW and TRU distributions for the pre-1970 and 1971-1985 time periods were distributed using the proportion of total waste volume for the time period to the overall total waste volume. LLW, LLMW, and TRU totals for 1986-1990 were developed before the earlier time period volumes were distributed. The LLW (1986-1990) is from the IDB (DOE 1990). LLMW was assumed to be after RCRA went into effect (1985). TRU (1986-1990) was computed by subtracting the LLW and LLMW volumes from the total waste for the time period.

REFERENCES

Final Environmental Impact Statement for Los Alamos Scientific Laboratory Site. 1979. Los Alamos, New Mexico.

Rogers, M. A. 1977. History and Environmental Setting of LASL Near-Surface Land Disposal Facilities for Radioactive Waste (Areas A, B, C, D, E, F, G, and I): A Source Document. Los Alamos Scientific Laboratory, Los Alamos, New Mexico.

U.S. Department of Energy (DOE). 1991. Integrated Data Base for 1991: U.S. Spent Fuel and Radioactive Waste Inventories, Projections, and Characteristics. DOE/RW-0006 Rev. 7, DOE, Washington, D.C.

APPENDIX E

OAK RIDGE BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

APPENDIX E

OAK RIDGE BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

<u>Provided Structure Categories</u>	<u>BWID Structure Categories</u>
Unplanned Release	Contaminated Soil
Lagoon	Above-Ground Liquid Impoundment
Pond	
Retention Basin	
Drain Line	Below-Ground Liquid Impoundment/ Subsurface Disposal Unit
Neutralization Unit	
Storage Vault	

Table E.1 contains an explanation of the methodology used to arrive at the estimated volumes of buried and/or stored waste at Oak Ridge.

TABLE E.1. Volumes of Radioactive Solid Waste (m³) by Structure Type at Oak Ridge (X-10)

Structures	Pre-1970		1971 - 1985			1986 - 1990				Pre 1970 - 1990
	LLW	Suspect TRU	LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other	Total
Trenches	157,900(a)	6,200(b)	39,200(c)	60(d)		7,100(e)				210,400
Auger Holes & Wells(f)										
Tumulus						900(g)				900
Buildings & Bunkers				600(g)			1,300(h)	200(g)		213,400
Total	157,900	6,200	39,200	600		8,000	1,300	200		213,400

(a) This figure was calculated by subtracting the 6,200 m³ of TRU waste (Martin Marietta 1991) from the 164,070 m³ of total buried waste through 1970 (Bates 1983).

(b) This figure was estimated in Martin Marietta (1991).

(c) The total amount of buried waste between 1971 and 1985 was estimated from annual burial records (Bates 1983) and the total volumes buried at ORNL [(letter, R. C. Mason (ORNL) to D. L. Stiles (PNL), May 20, 1992. "Request for ORNL Waste Characterization Data for the BWID Project"). Approximately 648 m³ of TRU were buried or stored during this time (Martin Marietta 1991), the remainder is assumed to be LLW.

(d) This total was estimated from the volume of RH TRU assumed to be nonretrievable and buried (Martin Marietta 1991).

(e) The total amount of buried waste between 1986 and 1990 was estimated from annual burial records (Bates 1983) and the total volume buried at ORNL [(letter, R. C. Mason (ORNL) to D. L. Stiles (PNL), May 20, 1992. "Request for ORNL Waste Characterization Data for the BWID Project"). Approximately 910 m³ of LLW were put into tumulus storage (Martin Marietta 1991). The estimated values of TRU/TRUM (Martin Marietta 1991) and LLMW (DOE 1991) stored during this time were also subtracted from this total to estimate this value.

(f) Available documentation is insufficient to estimate volume of waste placed in auger holes and wells. Therefore, those volumes have been estimated as 0; the total waste is reported as buried in trenches.

(g) This value estimated from statistics provided in Martin Marietta (1991).

(h) This value estimated in the Integrated Data Base (DOE 1991).

REFERENCES

Bates, L. D. 1983. Radioactive Solid Waste Storage and Disposal at Oak Ridge National Laboratory, Description and Safety Analysis. ORNL/TM-8201, Union Carbide Corporation, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Martin Marietta Systems, Inc. 1991. Oak Ridge National Laboratory Waste Management Plan. ORNL/TM-11433/R1, Oak Ridge, Tennessee.

U.S. Department of Energy (DOE). 1991. Integrated Data Base for 1991: U.S. Spent Fuel and Radioactive Waste Inventories, Projections and Characteristics. EOE/RW-0006 Rev. 7, DOE, Washington, D.C.

APPENDIX F

ROCKY FLATS BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

APPENDIX F

ROCKY FLATS BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

No contaminated soil structures are currently identified at Rocky Flats.

Table F.1 contains the methodology used to arrive at the estimated volumes of waste buried and/or stand at Rocky Flats.

TABLE F.1. Volumes of Buried Radioactive Solid Waste (m³) by Structure Type at Rocky Flats

Structures	Pre-1970			1971 - 1985			1986 - 1990			Pre-1970 - 1990
	LLW	Suspect TRU		LLW	Suspect TRU	Other	LLW	LLMW	TRU/TRUM	Other
Trenches	(a)									
Storage Buildings								8,500	900	
Total	(a)							8,500	900	
(a) Trenches were used between 1954 and 1968 for disposal of approximately 125,000 kg of sanitary sewage sludge contaminated with uranium and plutonium, and approximately 300 flattened empty drums contaminated with uranium and plutonium. The IDB (DOE 1991) shows no LLW buried at Rocky Flats.										
(b) Volume does not include waste identified in trenches (see footnote a). Volumes reported are taken from the IDB (DOE 1991).										

REFERENCES

U.S. Department of Energy (DOE). 1991. Integrated Data Base for 1991: U.S. Spent Fuel and Radioactive Waste Inventories, Projections, and Characteristics. DOE/RW-0006 Rev. 7, DOE, Washington, D.C.

APPENDIX G

OTHER BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

APPENDIX G

OTHER BURIED WASTE STRUCTURE CHARACTERIZATION DETAILS

<u>Provided Structure Categories</u>	<u>BWID Structure Categories</u>
Contaminated Soil General Surface Soil Contamination Nuclear Weapons Safety Experiment Unplanned Release Waste Pile	Contaminated Soil
Above-Ground Liquid Impoundment Decontamination Pond Ditch Lagoon Leachfield Pond Subsidence Crater Trench	Above-Ground Liquid Impoundment
Below-Ground Liquid Impoundment Drain Line Industrial Waste System Injection Well Septic System Subsurface Liquid Waste Disposal Unit Sump Waste Handling Area Wastewater Treatment Unit	Below-Ground Liquid Impoundment/ Subsurface Disposal Unit

DISTRIBUTIONNo. of
CopiesNo. of
CopiesOFFSITE

12 DOE/Office of Scientific and
Technical Information

11 Idaho National Engineering
Laboratory
Idaho Falls, ID 83415
ATTN: K. M. Kostelnik (10)
S. K. Merrill

2 Westinghouse Savannah River
Company
Aiken, SC 29808
ATTN: B. D. Helton
J. Stumbaugh

2 Los Alamos National Laboratory
Los Alamos, NM 87545
ATTN: E. Derr
E-Li Chen

2 Oak Ridge National Laboratory
P.O. Box 2008, Bldg 3047
Oak Ridge, TN 37831-6023
ATTN: D. Daugherty (2)

Toni Moore
Rocky Flats Plant
Golden, CO 80402

ONSITE

DOE Richland Field Office

D. E. Trader, A5-90

15 Westinghouse Hanford Company

M. R. Adams H4-55
J. D. Berger L0-18
J. O. Honeyman B1-31
D. M. Johnson H1-79
O. L. Kruger H5-33
A. L. Pajunen H5-49
J. G. Riddelle H1-79
R. J. Roberts N3-13
J. C. Womack L0-18

Environmental
Data Management
Center (6) H4-22

38 Pacific Northwest Laboratory

L. L. Armacost K6-61
S. Q. Bennett K7-90
C. M. Blackburn K6-61
J. A. Dirks K6-61
L. L. Fassbender K6-61
S. M. Garrett K6-61
G. M. Holter (2) K7-97
P. S. Kaae (10) K6-61
J. F. Keller L6-13
D. K. Kreid K1-22
G. W. McNair K7-90
M. S. Peffers K7-97
M. E. Peterson P7-41
W. A. Ross P7-41
J. L. Scott P7-39
D. A. Seaver K6-61
S. M. Short K7-94
B. L. Smith (2) K6-40
D. C. Stapp K7-97
D. L. Stiles K6-61
R. C. Walling K7-97

Publishing Coordination
Technical Report Files (5)

END

**DATE
FILMED**

3 / 16 / 93