290
9/24/84 JS (1)

DR-0419-7

DOE/ID/12201-T2
(DE84013685)

HYDROPOWER

FIELD TEST OF ULTRA-LOW HEAD HYDROPOWER
PACKAGE BASED ON MARINE THRUSTERS

Final Report

December 1983

Work Performed Under Contract No. FC07-80ID12201

Energy Research & Applications, Inc.
Santa Monica, California

U. S. DEPARTMENT OF ENERGY

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available from the National Technical Information Service, U. S. Department of Commerce, Springfield, Virginia 22161.

Price: Printed Copy A04
Microfiche A01

Codes are used for pricing all publications. The code is determined by the number of pages in the publication. Information pertaining to the pricing codes can be found in the current issues of the following publications, which are generally available in most libraries: *Energy Research Abstracts (ERA)*; *Government Reports Announcements and Index (GRA and I)*; *Scientific and Technical Abstract Reports (STAR)*; and publication NTIS-PR-360 available from NTIS at the above address.

FIELD TEST OF ULTRA-LOW HEAD
HYDROPOWER PACKAGE BASED ON MARINE THRUSTERS

SITE COMPLETION REPORT

FINAL REPORT

DECEMBER 1983

Cooperative Agreement No. DE-FC07-80ID12201/M005

Energy Research & Applications, Inc.

1820 Fourteenth Street • Santa Monica, California 90404

TABLE OF CONTENTS

	<u>Page</u>
1.0 PROJECT OVERVIEW	1
1.1 Project Roles and Responsibilities	2
1.2 Site Parameters and ULHH Package Selection	3
2.0 ENGINEERING DESIGN	7
2.1 Site Design	7
2.2 Hydraulic Package Design	13
2.3 Conclusions	17
3.0 ULHH PACKAGE FABRICATION	18
3.1 Fabrication Methods	19
3.2 Quality Control	19
3.3 Assembly and "Go together" Check	20
3.4 Conclusions	22
4.0 COMPONENT PROCUREMENT, COST CONTROL AND SCHEDULING	23
4.1 Component Description	23
4.2 Procurement and Cost of Thruster Package Components	23
4.3 Procurement and Cost of Test Equipment	26
4.4 Conclusions	28
5.0 THRUSTER HYDRAULIC SECTION INSTALLATION	30
5.1 Conclusions	30
6.0 SITE MODELING AND RESULTING RECOMMENDED MODIFICATIONS	32
6.1 ER&A Modeling	32
6.2 HRS Modeling	32
6.3 Conclusions and Results	32
7.0 TESTING	40
7.1 First Article Configuration Testing	40
7.2 Installed Performance Evaluation	41
7.3 Conclusions	41
8.0 BASELINE ENVIRONMENTAL CONDITIONS AT STONE DROP	42
8.1 Regional Geology	42
8.2 Environmental Setting	43
8.3 Conclusion	44

LIST OF TABLES

	<u>Page</u>
Table 2-1 Average monthly flow in Main Canal.	9
4-1 Thruster package costs	25
4-2 Test package costs	27
4-3 ULHH installation at Stone Drop - cost breakout	29
6-1 Summary of model conditions and results	35

LIST OF FIGURES

	<u>Page</u>
Figure 1 Installation of ultra-low head hydropower package based on marine thruster	4
2 MID folded plate weir under construction at Stone Drop	6
3 Schematic map of MID system	8
4 Stone Drop site layout	11
5 Original trash rack of welded pipe	12
6 Reworked trash racks	12
6a Closer view of final trash rack	12
7 Installed hydraulic section showing hard points	15
8 Bolt up prior to shipping	21
9 Complete unit on truck for delivery to site	21
10 Complete ER&A ULHH unit in place, prior to finishing civil works	31
11a Hydraulic jump and head loss	34
11b Stoplog wall vortex	34
11c Turbulent discharge	34
12 Test Run #1: Original configuration plus widened canal	36

13	Test Run #3: Columns removed and vortex-dispersing grid in place prior to placing training wall	36
14	Test Run #4: Stoplog wall removed	37
15	Test Run #6: Training wall in place	37
16	HRS recommended modifications to MID Stone Drop inlet structure	38
17	Stone Drop outlet modifications	39

1.0 PROJECT OVERVIEW

The work provided for under the referenced agreement between the U.S. Dept. of Energy and ER&A is the design, fabrication, assembly, installation, and field test of the first full-scale operating hydropower package (turbine, transmission and generator) based on ER&A's design which incorporates a marine thruster as the hydraulic prime mover. (Marine thrusters are primarily used for the maneuvering of large ships such as oil tankers, or other off-shore applications such as service barges and oil rig positioning.) The engineering and research which produced this design was performed, in part, under prior versions of this cooperative agreement. The installation has been accomplished on the main canal of the Modesto Irrigation District.

The critical problem encountered in the prior Research & Development phase was the analytical determination of thruster-as-turbine performance without data. Characterization of each unit of every manufacturer from which even minimal data was obtained resulted in the identification of two lines of equipment for which the calculated effective heads matched the 3 meter regime we were originally contracted to investigate. Fortunately, the standard unit sizes of these equipment lines were also complementary over a power range of approximately 50 HP to 1100 HP.

Other elements of the ULHH package were selected or designed according to criteria of least cost for reliable function. This included configuring a transmission from catalog components, designing the turbine diffuser as part of the civil works, and even to selecting and specifying cost-effective materials from a wide range of candidates.

The result of this prior phase of the project was the design of three hydropower package configurations: generally for horizontal, vertical or syphon applications, as determined by site-specific requirements. Based on comparison of concept designs as done by others for actual ultra-low head sites, installed cost reduction of up to 50% was calculated. The hardware package costs were, on the average, only 30% of the cost of conventional equipment for this head range.

The intent of this project was to determine whether the marine thruster package concept could be applied in practice, what the performance as a hydroturbine actually was, and whether the significant equipment cost reductions identified in the R&D phase of this project could be realized during test and evaluation under operational field conditions.

ER&A completed a contract modification with DOE for this activity contingent on locating a suitable test site and arranging for the balance of the funding for a full scale low-head hydropower unit installation.

DOE specified ER&A as their prime contractor for project accomplishment. Responsibility for civil works construction and grid electrical interface was assumed by MID. This was logical since MID owns and operates both the canal and the power grid; therefore could effect these changes internally.

1.1 Project Roles and Responsibilities

ER&A then negotiated a contract with the Modesto, California Irrigation District to develop their Stone Drop site on the District's Main Canal using the marine thruster-based low head package. Under this contract, ER&A's responsibilities were:

- 1) Design, procurement, fabrication and assembly of the ultra-low head hydropower (ULHH) package;
- 2) Prepare a layout of final package design and configuration including all dimensions and specifications necessary to fit the ULHH package to the site;
- 3) Supervise and direct the installation of the ULHH package at the site;
- 4) Perform startup and testing of the ULHH package, following installation, including provision of test instrumentation and equipment.

The Modesto Irrigation District's responsibilities were:

- 1) Engineering necessary to modify the site to accept the ULHH package and preparation of final drawings and specifications for the site modification;
- 2) Perform all site modifications and associated civil, electrical, and mechanical work required for installation of the ULHH package at the site.

The contract also provides for joint review of the final engineering drawings and specifications of both the ULHH package design and the site modifications in order to ensure compatibility.

The Modesto Irrigation District is one of few (3-4) California irrigation districts that is also a retail electrical utility. Hydroelectric power developed by the ULHH package at Stone Drop is fed directly into their adjacent transmission line to offset wholesale power purchases from Pacific Gas & Electric Co. The District is the site owner and has ownership of the fully-developed site and hydropower equipment upon completion. ER&A retained limited visitation and display rights under the contract.

ER&A's primary responsibility under the DOE cooperative agreement is to provide a performance report and test data on the marine thruster-based ULHH package installation. DOE was to monitor, evaluate and, as appropriate, make recommendations regarding the project progress and accomplishment of the objectives. The primary objective was to determine if ER&A's package design, using a standard marine thruster operating in a power-producing mode, actually worked in a field installation.

1.2 Site Parameters and ULHH Package Selection

The engineering data developed during phase one of this activity indicated that of the eleven different sized packages designed, a Harbormaster BT550 thruster with a runner diameter of 60" was the properly sized unit for this site. This thruster is a standard item of manufacture by the Mathewson Corporation of Quincy, Massachusetts. "Harbormaster" is the thruster trade name and indicates the primary and original application of marine thrusters: ship maneuvering in harbors or other restricted environments (see also Figure 1).

It was the original intention for the Stone Drop site to be developed in two phases. The first phase was accomplished under this project with the installation of a single unit on the south side of the Main Canal, which runs generally from east to west. Following test and evaluation of the ULHH package, a second unit was to be installed by MID on the north side of the drop. Size of the second unit was to be determined after test results were calculated and analyzed.

Transformer, switchgear and related electrical grid interface components were sized and installed to accommodate complete site development up to its approximately 900 KW theoretical capacity.

The BT550 size unit was selected as prime mover based on a calculated through flow of 500 cfs at a head of 16 feet. The basic thruster consists of a shrouded Kaplan propeller blade connected to a sealed right angle drive fixed ratio gearbox. The power output shaft from the gearbox (normally the propeller drive in marine use) is therefore at 90° to the direction of flow. Theoretical power potential of this size ULHH package at a calculated thruster efficiency of 61% is 415 KW.

All of the ULHH packages had been characterized for a design point of 10 feet net head, pursuant to the goals of DOE's ultra-low head hydropower cost reduction program. In the engineering of this specific package for the Stone Drop site, it was determined that the higher head resulted in torque that was beyond the continuous duty limitation of the standard Harbormaster thruster gearbox.

Due to this discovered torque limitation (albeit at a head over 50% greater than the original design point), the realizable output of the unit was recalculated to be a maximum of 400 KW.

Figure 1 shows a representation of the ULHH package configuration designed for this site including thruster-turbine section, pulley-drive transmission, and matched generator.

Package design and site modification layout were begun by ER&A in October 1981. Thruster procurement and hydraulic section fabrication were initiated shortly thereafter.

The hydraulic section incorporating the thruster was delivered by ER&A to the Stone Drop site in January 1982. This section was installed as an integral part of the powerhouse during construction of the upstream and

Figure 1. Installation of Ultra-Low Head Hydropower Package Based on Marine Thruster.

downstream walls.

Procurement of long lead time components, identified as the generator and flow entry control gate, was also initiated.

Prior to site modification for installation of the ULHH package, MID also constructed a folded plate weir in the canal upstream of the Drop. (See Figure 2)

Figure 2. MID folded plate weir under construction at Stone Drop.

2.0 ENGINEERING DESIGN

2.1 Site Design

2.1.1 Site Description

Stone Drop site is an integral part of the MID irrigation distribution system, and is located on the Lower Main Canal (see Figure 3, Schematic Map of MID System) in the San Joaquin Valley of California approximately 20 miles east of the City of Modesto in Stanislaus County.

"As built" drawings were not available for the Stone Drop structure. Topographic plan drawings and profile sketches found in "Feasibility Assessment Report" done by CH2M Hill (Nov. 1978) were not sufficient for engineering and design purposes. ER&A staff made the full measurements and topographic survey of the existing facilities and developed an accurate plan of the site as of Fall 1982 that was the basis for engineering design of the ULHH package installation. A new, MID-designed pleated weir was designed and constructed to complete the site configuration according to prior MID plans, which aided headwater elevation control.

Stone Drop consists of a concrete structure located within the concrete-lined main canal at a drop in the water surface of about 16 feet. The concrete is in good condition and has been well-maintained. The surface has been recoated, and minor repairs are evident. Some erosion is occurring at the water line where high velocities occur.

The only significant cracking is occurring at a horizontal cold joint. There is evidence that the structure originally incorporated radial gates and/or stop logs. The exposed banks show no signs of leakage. There are no rock outcroppings or boulders in evidence, and the native soils appear to be dense, sandy, silty clay.

Geomorphology, geologic structures, geologic formations and seismicity were well covered in the Feasibility Assessment Report by CH2M Hill. (pg. 7 and 8). The same "Report" hydrological data and power heads were the basis for ER&A equipment selection for the power-generating installation. Flow data are shown in Table 2-1.

2.1.2 Site Design Approach - Design Data

After rigorous analysis of existing hydrological data and additional MID Stone Drop water delivery records, the ER&A ULHH package based on a BT-550 marine thruster was selected for the "first phase" of development. A second phase of development is also proposed through additional installation of yet another ULHH package on the opposite bank of the canal.

Slight modifications from the original horizontal configuration (described in Final Report of "Design of Low-cost Ultra-low Head Hydropower Package" - August, 1981) were made to accommodate site-specific requirements at Stone Drop.

FIGURE 3
SCHEMATIC MAP OF MID SYSTEM

Table 2-1

AVERAGE MONTHLY FLOW IN MAIN CANAL

<u>Month/Yr.</u>	<u>1967</u>	<u>1968</u>	<u>1969</u>	<u>1970</u>	<u>1971</u>	<u>1972</u>	<u>1973</u>	<u>1974</u>	<u>1975</u>	<u>1976</u>	<u>10 Year Ave.</u>
January	--	--	--	--	--	--	--	--	--	696	70
February	--	--	11	--	--	--	--	--	--	327	34
March	48	193	37	312	312	640	18	361	271	631	282
April	307	681	521	753	631	404	495	406	682	516	540
May	753	496	909	766	537	409	739	789	769	589	676
June	783	621	924	814	642	483	748	767	804	642	723
July	948	679	991	873	771	626	848	810	884	707	814
August	812	474	871	692	697	493	799	793	781	530	694
September	565	290	656	397	311	493	425	542	460	398	454
October	409	116	237	137	242	197	107	182	169	--	180
November	--	--	--	--	--	--	5	149	337	--	49
December	--	--	--	--	--	--	73	244	227	--	54

The left bank (looking downstream) of the existing Stone Drop structure was selected for design and construction of the ULHH installation. Drawing MID-10001 shows the layout and conceptual design of the installation. The concept leaves the Drop facilities undisturbed and required minimum civil works for installation. The new folded weir designed by MID staff is part of the intake facility and will help to maintain a practically constant head of water with very little variation regardless of flow in the canal. The installation concept consists of three major structures, as shown in Figure 4.

- 1) Intake structure
- 2) Powerhouse
- 3) Discharge (outlet) structure

2.1.3 Intake Structure

The intake structure consists of an intake gate, intake penstock, trash rack and stoplogs.

- 1) Intake gate (Rodney Hunt type) is a heavy duty 66 inch sluice gate. Intake center line is at Elev. 87.07 feet. Bottom of intake canal floor was lowered to Elev. 83.67 feet. The gate is mounted on the wall thimble, and operates by a hydraulic cylinder automatically or by manual control. Top of the head wall is at Elev. 100.67 feet. Six feet upstream, stoplog slots are provided to permit maintenance of the gate.
- 2) The original MID-designed trash rack consisted of a welded pipe construction which is shown in Figure 5. The rack completely enclosed the forebay which is covered with a concrete slab, also visible in Figure 5. The rack design had a pipe spacing somewhat greater than desirable, especially at the forward section which experiences direction of water flow normal to the rack. The side rack spacing was considered less critical since it primarily experiences oblique flow. Under full flow condition, this original trash rack vibrated significantly. Redesign and replacement were recommended. After the test phase, this item was reworked as shown in Figure 6.

2.1.4 Powerhouse Structure

The powerhouse layout was made to accommodate the ULHH package in horizontal configuration, using the existing wall of the drop as well as the upstream wing wall and a portion of the downstream wing wall. Demolition of a portion of the downstream wing wall and the end of the upstream wall, together with excavation were necessary for powerhouse construction. Dimensionally accurate conceptual designs of powerhouse layout and elevations were submitted to MID for final site engineering to their utility-grade requirements. MID's engineering designs followed ER&A layout related to critical dimensions and elevations but the powerhouse was designed much larger than normally necessary for this kind of small hydro installation. The design includes an underground structure with roof top at ground level, resulting in a low-profile visual environment.

NOTES:- TRASH RACK IS NOT SHOWN IN THE SECTIONS B-B TO E-E FOR CLARITY
*) FOR TEMPORARY USE DURING THE TESTS

**PRELIMINARY PRINT
NOT TO BE USED
FOR CONSTRUCTION**

Figure 11. Stone Drop site layout.

MODESTO IRRIGATION DISTRICT STONE DROP ULNH INSTALLATION					SPECIFICATION	
PART NO.	NO. REQUIRED	REVISIONS			DESCRIPTION	
TOLERANCES (EXCEPT AS NOTED)	NO.	DATE	BY		ER&A Energy Research & Applications Inc.	
DECIMAL	1				PRELIMINARY LAYOUT FOR SITE PREPARATION	
FRACTIONAL	2					
ANGULAR	3				DRAWN BY	MATERIAL
	4				CHK'D	DATE
	5				TRACED	APPROV
						DRAWING NO. MID-C-1000

Figure 5. Original trash rack of welded pipe.

Figure 6. Reworked trash racks.

Figure 6a. Closer view of final trash rack.

The entire powerhouse is made of reinforced concrete following the California seismic standards. The east wall defines the joint between the concrete penstock and steel inlet section of the thruster package.

A Dresser coupling was provided to seal the steel pipe intake hydraulic section of the package as well as for construction tolerances and expansion/contraction anticipated to occur during the dry season when the hydro installation is not in operation. The Dresser coupling was not included in the original package configuration (Design of ULHH Package Final Report). Thruster support was also designed differently than developed in the original concept. It was determined that for larger units (such as a BT-550) it is more economical to build a concrete cradle support with steel hard points and straps to mount the thruster. This allows easier installation and maintenance as well as facilitating taking the thruster section in and out during the testing period. The generator is installed on rail beams mounted in the concrete floor. This arrangement makes it easier to move the generator to different positions (such as for belt drive or direct drive) during test, and need not be duplicated on future ULHH installations.

The draft tube of the unit is connected with the discharge structure through the west wall at 5' - 11 5/8" below the steel intake pipe elevation, inclined 30° from the horizontal reference (the original concept angle of inclination was 45°). This modification of the original is an improvement made to eliminate one additional turn in the discharge structure and, at the same time, simplify the hydraulic section of the ULHH package. Further improvements could be made in the thruster hydraulic sections on future units according to site-specific conditions.

2.1.5 Discharge (Outlet) Structure

The discharge (outlet) structure was designed and built differently by MID than was conceived by ER&A. The concept of the discharge structure was based on a concrete diffuser controlling discharge flow and velocity after exiting the thruster hydraulic section, into an afterbay stilling pool. This approach was chosen to eliminate hydraulic jump and assure draft tube recovery capacity. MID construction of the discharge structure eliminated the stilling pool because of hazard concerns.

The diffuser section was also constructed with an abrupt transition from round to square section at the interface of the steel thruster hydraulic section to the concrete diffuser. This condition resulted in an abrupt step at the entrance to the diffuser, which was anticipated to cause flow separation. Therefore, the transition was reworked to add fillets to the square concrete section, eliminating the step. The "as built" angle of divergence is 22°, which is greater than the classical maximum of 15° for flow discharge structures. Energy recovery was, consequently, decreased.

2.2 Hydraulic Package Design

2.2.1 Thruster Modification

The thruster is modified by attachment of convergent-divergent cones to the ends of the thruster tunnel to achieve a transition from the thruster diameter to the larger draft tube diameters. The cones are welded

directly to the shroud of the thruster and include integral flanges which are drilled for bolt attachment to the draft tube flanges. The cones are fabricated from corrosion resistant steel (ASTM A-242-79 Type 1, COR-TEN steel). The flanges are fabricated from rolled stock of ASTM A-36 low carbon steel and protected by a cold galvanized paint. The draft tube assemblies are fabricated in much the same manner from COR-TEN plate stock and low-carbon steel flanges.

A key design feature which translates to cost reduction at several points from manufacture to site installation is the modular elbow which can apply to inlet and outlet structures for each unit configuration. Similarly the convergent and divergent cones are identical for each size unit. The cone and elbow flange assemblies are match drilled to assist in assembly and disassembly of the hydraulic section components as required. The flanges are joined by thirty 3/4" diameter structural bolts. Twenty-eight of the flanges holes are large tolerance holes to permit ease of assembly, while two holes are close tolerance holes to provide registry and tolerance control. The flanges are joined by a neoprene gasket to provide a hydraulic seal. The draft tube was constructed of 3/16" (.1875) COR-TEN steel which is heavier gauge than the actual structural requirements of only 1/8" stock.

The increased wall thickness was provided principally to provide handling rigidity; to avoid potential distortion or damage of the sections in transit, storage, or installation. The gauge, as specified, for the hydraulic wall sections provided a good tradeoff for structural integrity and greater portability. This was made evident on installation when the entire steel tube section with thruster was lifted over a 20 foot wall with a large mobile crane. At the time, it had not been entirely bolted together at all flange bolt holes but no distortion, twisting, or deformation occurred. The weight of this unit was approximately 6500 lbs. when lifted into place.

2.2.2 Thruster Structural Support

A number of design alternatives were investigated for the structural support of the thruster, including two steel fabrications and one consisting of hard points cast into a concrete base. The concrete base with the hard points (Figure 7) was selected on the basis of lowest cost and maximum rigidity. However, this design choice created the potential for more difficult dimensional tolerance control between the thruster package and the civil works. The potential tolerance problems were avoided by casting the base and hard points after the thruster hydraulic section was set in position.

2.2.3 Generator Selection

An 800 horsepower generator has been elected for the Stone Drop installation. This is more absolute power capacity than is required for this particular thruster's calculated horsepower output. A close examination of the efficiency versus percent load of the generator component revealed that over a percentage point in efficiency could be gained with a larger unit operated at a partial load of approximately 75%.

Figure 7. Installed hydraulic section showing hard points.

For the generator cost differential, there is a significant energy production advantage over the project life in utilization of the larger unit.

Since one of the primary objectives of this development program was to determine the efficiency and performance characteristics of the thruster as a turbine, it was required that a transmission system be provided which has variable speed characteristics. In order to accommodate this transmission system, it was necessary that the generator be provided with slide rails and that the facility interface permit generator installation at a multiple number of positions relative to the thruster gearbox output shaft.

2.2.4 Transmission Design

In order to conduct the performance efficiency test, it is necessary that the unit be operated at a range of thruster speeds for various specific heads. In order to load the thruster at various speeds a number of options were examined. For example, pony brakes, water brakes, and the generator wired to a water-cooled resistance load bank were evaluated, as well as the finally selected method of a transmission design driving a generator tied to the grid as a load. The transmission design was selected to provide a range of speeds both above and below the expected maximum efficiency speeds at each operating head. Therefore, the final transmission design consists of a set of pulleys and a belt with four different speed ranges of approximately 10% increments ranging from 80% to 110% of the expected maximum efficiency speed. Upon completion of the performance testing, the decision was then made on the most effective final transmission design. The selected operational configuration consisted of a drive selection of a 22.4 inch diameter pulley on the jack shaft and 16" diameter pulley on the generator. The pulleys were fabricated of ductile iron to obtain adequate strength for runaway conditions. The transmission design and test activity is a non-recurring effort which is required only to obtain engineering data on the prototype unit.

The transmission design was significantly complicated by the test requirements and hopefully can be installed as a direct drive without pulleys or belts in future installations of this size unit. In any event the transmission system would be no more complex than a single speed correction with one set of pulleys resulting in significantly reduced design time for future similar installations.

During the design phase it was brought to our attention that other hydropower sites have experienced problems on shut-down in that a high efficiency unit tends to free-wheel for an extended period. Therefore, a brake consisting of a disc and caliper was initially included in the transmission design to stop rotation of the assembly after the cessation of hydraulic flow. The brake installation was thought particularly desirable for the test phase to permit rapid change-over of the drive mechanism without the delay of waiting for the unit to come to a stop. During testing decay time was found to be manageable, and thus the brake is not included as part of the final configuration.

2.3 Conclusions

The increased complexity of the powerhouse was driven by limited space availability at the site for location of electrical equipment, and provision for live load capability on the powerhouse roof structure. Specifically for a typical site installation the powerhouse columns and roof structure would be simplified. The civil design concept which permits installation of the fabricated hydraulic package as a unit, followed by casting the draft tube sections into the upstream and the downstream walls, is advantageous. This significantly reduces the interface tolerance concerns.

A cost-effective design approach for the hydraulic section has been achieved which is reflected by an acquisition cost significantly lower than the budgeted estimate. Establishment of these design policies and tradeoffs will also be reflected in lower costs of the engineering effort for subsequent units.

An efficient solution to the thruster support structure was achieved which resulted in lower cost and avoidance of interface tolerance difficulties. The generator selection for each specific unit should be examined with appropriate trade-offs of size versus partial load efficiencies to achieve the maximum life-cycle electric energy production.

3.0 ULHH PACKAGE FABRICATION

The BT-550 thruster section was ordered from the manufacturer, Harbormaster Division of Matthewson Corp., in Boston, Massachusetts. The interim delivery time allowed the opportunity to review and finalize all design work and start fabrication of parts not directly attached to the thruster section. It was determined best to have the thruster at the fabrication shop before making the modifying cone sections.

Once the most efficient thruster model on which to base an ULHH package at Stone Drop was determined and the package engineered we addressed the problem "How do you actually make it?" The package design described the materials and methods. Our main goal was to reduce the amount of time-consuming and costly steps in package fabrication, and selection of materials.

The convergent/divergent cones attached to the ends of the tunnel thruster were specified to be highly corrosion resistant Cor-Ten (USS) steel. The penstock and elbow sections were also specified in this material for homogenous welding throughout. However, the thicker flange stock was called out in low carbon steel, then coated by a protective paint.

A key design feature which translates into cost reduction at several points, from manufacture through site installation, is the modular elbow which can apply to inlet and outlet structures for each unit configuration. Similarly, the convergent and divergent cones are identical for each size unit. The cones and elbows are manufactured with flanges for assembly with gaskets and structural bolts. With the very low pressure encountered in this ultra-low head regime, even conventional 0.5 inch bolts and industrial rubber gaskets exceed design requirements. Similarly, wall thicknesses of only 0.011 inch could withstand the pressures but were too fragile for welding and handling. The maximum pressure differential expected will not exceed two atmospheres (29.4 psi) which is handled by a 0.188 inch wall thickness for even the largest diameter ER&A hydropower package.

Cor-Ten-A steel by U.S. Steel Corp. (ASTM A242-79 Type 1 and ASTM A606-75 Type 4) is specified for the non-thruster hydraulic portion of the package due to a favorable tradeoff between corrosion resistance (which is four times that of carbon steels), structural strength and cost compared to a number of other materials considered, including some non-metallic candidates.

Cost Comparisons/Materials

Approximated costs from 1982 pricing by steel service centers:

SS 304 1/4" Plate: \$1.35 to \$2.09/lb
Cor-Ten 1/4" Plate: .4665 to .4865/lb
Ex-Ten 50 1/8" Plate: .4265 to .4465/lb
A35 L.C. 10GA: .304 to .306/lb

The gauge we specified for the butt wall sections (.1875 or 3/16") thick provided us with a good tradeoff in having structural integrity and much greater portability, as described in Section 2.2.1.

The first stage of construction concentrated on the upstream and downstream steel pipe sections. Since these would be embedded in the concrete walls of the powerhouse, the civil works could begin with these items cast in place. While the civil works progressed, the thruster arrived from the manufacturer and was modified by the addition of flanged cones. Once this was completed, it was intended to send the remaining parts to Modesto and the whole unit would be bolted together on-site.

The fact that the site was not ready for the intake section of the penstock changed that plan. ER&A finished the entire hydraulic section of the package and shipped it to site as a complete unit instead.

3.1 Fabrication Methods

Standard shop rolling, shearing, and welding techniques were used throughout, eliminating as much as possible more expensive machining processes such as heavy milling, boring, stress relieving, heat treating, etc.

This overall simplification of the thruster package ensures the relative ease of constructing and installing units world-wide particularly in less industrialized countries or at remote U.S. sites.

The steel plates used were standard sizes, sheared to a round dimension for handling ease. A cutting line was then transferred by hand to each "gore" section of the hydraulic tube from a heavy paper pattern that was realized from a computer-generated layout. The paper pattern was basically the only "tooling" device manufactured for this project. After tracing, the sheets were flame cut by electric eye robot cutters that maintained a $\pm 1/16"$ tolerance. Each gore was then rolled, tack welded on longitudinal seams and checked for diameter tolerances. Then, the corresponding gores were mated to form the respective elbows. Centerline marks on each end of each gore aided aligning and helped to insure centerline trueness.

All tubes were rolled to a finished dimension of 66" I.D. We chose an inside dimension in order to mate with standard cast reinforced concrete pipe which is made to the same controlling dimension.

Hand grinding of a bevel on both sides of welded seams preceeded the welding.

3.2 Quality Control

Multiple diagonal measurements checked the datum angles and parallelism. Any weld build-up of over 1/4" was ground and flared.

The flanges were rolled from flat bar stock and became the critical part of each section end. These were carefully checked for tolerance

compliance. After butt welding, the flange was remeasured; then the bolt holes drilled on a large radial drill. These flanges consisted of six flanges drilled with 30 equally spaced bolt holes on each and two left undrilled. The latter were used as stiffeners for the tube sections to be embedded in concrete. All flanges measured within $\pm 1/64$ " which exceeded our acceptable tolerance of $\pm 1/16$ ".

The height of the weld contour on inside seams exceeded the "ideal" of a perfectly smooth surface. We calculated, however, that the incidental induced drag from weld build-up was not great enough to warrant the added expense of grinding the seams flush.

After each tack weld of elbows and other large parts, engineers from ER&A made on-site inspections prior to a sign-off or go ahead to complete that component. Inspection included checks of angularity, flatness, and all other datum checks. Particular attention was given to the flange bolt hole arrangements to insure clocking and installation match-up.

After full inside and outside welding on a hydraulic section, there followed a penetrant dye check. This method was quick, economical and sufficient to identify most weld problems. Any indications of requirement for re-welding were marked and recorded. That area was ground by hand, welded, and dye checked again. We also determined that if any leaks or cracks were found at the site that field welding with the specified low hydrogen rod would be simple and efficient if repairs were necessary.

The thruster arrived at our fabricator's shop on December 20th, 1981, four weeks ahead of schedule. Immediately, dimensions were taken to determine if there was any deformation or other damage during shipping and to update our manufacturing drawings to match the actual product. No deformation due to shipping was discovered and work began on the thruster modification after first removing the propeller from its shaft. It was found necessary to fabricate a "puller" to assist in removal of the propeller.

3.3 Assembly and "Go Together" Check

The modification involved welding a cone with drilled flange onto each end of the thruster to which the other hydraulic sections would be attached. The thruster protective point was ground away from the weld joint areas; a carefully measured and rolled cone section was attached to each open end. Flanges were then clamped onto the cone ends and carefully measured for datum lines and parallelism. Flanges were tack welded and remeasured, then final weld passes made on all seams. The cone/thruster seam interface was ground flat to match the thruster shroud inside contour.

After final welding and dye checks the sections and elbows were all brought together for a bolt up (See Figure 8) of the entire system prior to shipping to MID. This bolt up provided a check of product and tolerancing and also revealed situations that may be encountered assembling a unit in the field. It was found desirable to install all bolts

Figure 8. Bolt up prior to shipping.

Figure 9. Complete unit on truck for delivery to site.

loosely during assembly, before cinching any tight.

After the unit was broken back down to its individual sections, all pieces were cleaned up and prepared for a heavy coat of shop primer inside and outside. This coating provides weather resistant protection for up to 6 months outdoors without a final overcoat.

The prop was put back on before shipping, and the prop-pulling tool was made part of the fabricated deliverables. All sections were inspected and accepted for shipment to site, and reinspected as secured on the flat bed for transport. The shipping configuration is shown in Figure 9.

3.4 Conclusions

A manufacturing method and sequence was developed and demonstrated that is applicable to subsequent units. It resolved many questions regarding tolerances and dimensional control techniques which are effective for cost reduction, while meeting project requirements.

4.0 COMPONENT PROCUREMENT, COST CONTROL AND SCHEDULING

4.1 Component Description

The procurement of equipment components for field test of the ULHH installation can be broken into three functional groups:

- 1) Thruster package
- 2) Site development equipment
- 3) Test instrumentation

The thruster package components are the power generating and related items:

Thruster Package

Thruster and lube tank
Generator and slide rails
Hydraulic sections
Cradle support
Dresser coupling
Gaskets
Brake
Transmission and supporting structure
Transmission guard

Related site specific items interfaced with the thruster package to render it functional:

Site Development Equipment

Gate and frame
Gate thimble
Gate controls

The test instrumentation was put together so that the package could be easily transported to the test site. A listing of these components is as follows:

Test Package

Electrical, tachometer and pressure readout and data recording equipment
Pitot grid
Manometer boards
Transmission variations
Blade enhancement modifications

4.2 Procurement and Cost of Thruster Package Components

The procurement of the components became a larger task than originally predicted because of detail design improvements and coordination of MID's requirements. The initial versus final costs reflect these changes and requirements which are shown in Table 4-1.

The initial thruster planned for the Stone Drop site head and flow was to be Harbormaster's BT-450 thruster; however, after re-evaluating the flow for the thruster at the predicted 16 foot head with a flow of 500 cfs, the BT-550 was chosen. Upon evaluation of Harbormaster's manufacturing drawing, ER&A determined that a tighter tip clearance between the blade and the shroud would increase the system efficiency. This change is reflected as an increased thruster cost in Table 4-1.

The generator order was time consuming and required specification refinements to insure compatibility with MID's grid interface and MID's plan to maximize utilization of surplus equipment, such as switchgear and transformer.

The originally estimated generator for the 10 foot head was a 400 HP unit @ 440 V. After re-evaluation of the thruster size and predicted head, an 800 HP, 1200 RPM, 2300 volt Louis Allis induction generator with slide base was ordered. After MID review, a synchronous generator was requested. This choice was eventually determined not optimum in terms of cost, efficiency, and delivery. Finally, per MID's request, the order was changed to a 4160 volt, induction generator with an enlarged terminal box. Upon manufacturer's engineering review, roller bearings were specified instead of standard ball bearings.

To maintain schedule in effect as of March 1982, ER&A authorized overtime to Louis Allis to achieve the generator delivery of April 12th, the scheduled installation date. All of these items; increased capacity, higher voltage, enlarged terminal box, roller bearings and overtime increased the final cost for the generator.

The horizontal ULHH package hydraulic sections were designed by ER&A and sent out to bid. The bid was awarded to Lane and Roderick, Gardena, California, who was low bidder at \$7,751.32. Upon finalization of manufacturing drawings and a review of the design, the thickness of the sheet was increased from 8 gauge to a 3/16" thickness. This increased the bid by \$2,144.27, which was still low bid. In addition, for ease of tracking, Lane and Roderick was awarded fabrication of the additional thruster ancillary equipment, such as pillow block and cradle supports, to manufacture at a cost of \$1,689.45. To complete the hydraulic section, a dresser coupling, gaskets and miscellaneous bolts, nuts and gasket cement were ordered. The dresser coupling was made at Steel Exchange, Inc., the gaskets at "O" Rings, Inc., and the miscellaneous bolts, nuts and cement were available catalog items. These costs are reflected in the final hydraulic section cost shown in Table 4-1.

The thruster package was modified to include a brake for emergency as well as testing purposes. The design required purchase of a caliper brake and hydraulic actuator and machining a shaft and disc part by JPC Engineering at a total of \$2,419.00.

The support/transmission accessories consisted of jackshaft, pillow block, base plates and related bushings ordered from Kaman Bearing. The jackshaft had the keyway and length explicitly specified but the other

Table 4-1

THRUSTER PACKAGE COSTS
ORIGINAL INSTALLATION FOR TESTING

<u>Item & Related Equipment</u>	<u>Original Estimate</u>	<u>Final Cost</u>
Thruster	\$ 27,700	\$30,954
Generator	12,968	26,310
Hydraulic Section incl. cradle support Dresser coupling gaskets & bolts	22,961	15,689
Brake	0	2,419
Transmission Components incl. supporting structure & guard	8,025	2,820
	<hr/>	<hr/>
	\$ 71,654	2,350*
		\$80,542

*Forecast cost to complete

accessories were regular catalog items.

MID procured the inlet gate. The 66 inch gate, thimble and controls were manufactured by Rodney Hunt. In February, 1982, to maintain schedule, ER&A had a temporary gate design drawn, bid and ready for fabrication by Richwell Steel. However, this plan was abandoned because MID negotiated an earlier quoted schedule from Rodnbey Hunt which was satisfactorily compatible with MID's revised schedule.

4.3 Procurement and Cost of Test Equipment

The test equipment was assembled from commercially available components. The cost of the equipment is shown on Table 4-2. The digital panel instruments (DPIs) were manufactured by Newport Electronics and all possessed tri-state binary coded data (BCD) output ability. The electrical meters and the tachometer were all connected by a common bus through a sequencing board to a Newport printer for recording. All Newport instruments and supporting transducers were procured thru EIL Instruments, who also provided calibration of the matched sets. The pressure measuring equipment consisted of a grid of pitot tubes, and 8 piezometric taps at two locations on the hydraulic section. The pressure was measured by a Statham pressure transducer, with the multiple pressure taps being multiplexed by a Scanivalve. The pressure transducer output was visually displayed on a Newport DPI and recorded together with the multiplexed port location by a Newport printer.

The specific components of the readout and data recording panel are as follows:

- 3 Voltage Transducers
- 3 Voltage DPIs
- 3 Amperage Transducers
- 3 Amperage DPIs
- 1 $2\frac{1}{2}$ Element Wattage Transducer
- 1 Wattmeter DPI
- 1 Pulse Generating Tachometer
- 1 RPM Indicating DPI
- 1 Statham Pressure Transducer
- 1 Scanivalve Controller
- 1 Pressure Indicating DPI
- 1 Scanivalve Decoder with BCD Output
- 2 Newport Printers

The pitot grid and manometer were designed by ER&A. Ford Walters was contracted to fabricate the pitot grids, and the actual tubing installation was completed by ER&A. Procurement and assembly of the manometers was performed by ER&A, as well.

Necessary tools were purchased to aid in the testing procedure and transmission changeouts. These included a come-along, strap wrench, hydraulic wedge and miscellaneous sockets and nylon slings.

The transmission variations were determined after much discussion

Table 4-2

TEST PACKAGE COSTS

<u>Item & Related Equipment</u>	<u>Original Costs (\$)</u>	<u>Final Costs (\$)</u>
Test Equipment:	\$10,000	
Data Recording		\$11,114
Test Panel		715
Manometer		519
Pitot grid		1,186
Tools		948
Transmission	0	3,433
Blade Modification	0	440
	<hr/>	<hr/>
	\$10,000	\$18,355

between vendors and design team to satisfy the required loading and testing constraints. Finally, all were purchased from Kaman Bearing.

The blade modification, based on ER&A design, was performed by Pitchometer Propeller Co. in Alameda, California. At a quoted price of \$240.00 for the grinding and \$200.00 for shipping, the modification required only a few days.

4.4 Conclusions

The thruster package and site development equipment are representative of recurring equipment items for future installations. The test equipment, however, represents a non-recurring expense (see Table 4-3).

The development of sources and potential sources will be assessed for future package component procurement.

Table 4-3

ULHH INSTALLATION AT STONE DROP - COST BREAKOUT

Direct Construction Costs	\$411,000
20% Contingency	82,200
	<u>\$493,200</u>
ER&A Project Management	\$ 27,000
Testing	81,000
Travel and Per Diem	17,280
	<u>\$618,480</u>

Direct Construction Costs

Powerhouse	\$ 58,000
Head and Flow Control Weir	26,750
Penstock (Inlet)	15,250
Turbine-Generator Set	145,000
Assoc. Electrical Equipment incl. Grid Interface	131,000
Misc. Mechanical Equipment	12,000
Transmission & Land Rights	23,000
Subtotal	<u>\$411,000</u>
Less Turbine-Generator	145,000
	<u>\$266,000 - MID Cost</u>

Recurring costs are defined simply as those necessary for the construction of site modifications, thruster-based hydropower package and grid interface. Any projection of cost decreases due to advancement on the learning curve have been discounted due to individual characteristics of sites and the propability that the work would be done by different entities.

Site-specific engineering and package engineering costs are also reflected at actual expenditures and included in recurring costs.

Non-recurring costs include testing of this first article configuration, extensive travel and per diem in test phase, and project contract management. Test equipment was designed and packaged by ER&A; leased to MID.

Direct recurring costs are developed as follows:

Direct Construction Costs:	\$266,000
Turbine-Generator Unit:	145,000
Engineering (Site and package):	50,000
	<u>\$461,000</u>

Non-recurring costs are identified as:

Testing, Including ER&A-Supplied Test Equipment and Test Plan Development:	\$ 81,000
Contracts & Project Management:	27,000
Travel and Per Diem:	(approximately) 12,000
	<u>\$120,000</u>

5.0 THRUSTER HYDRAULIC SECTION INSTALLATION

The hydraulic sections and the modified thruster were shipped on a flat bed truck as three major sections plus the Dresser coupling, forward tube section, cradle support and transmission support. A trial go-together check of thruster and hydraulic sections was performed successfully at the Waterford Yard of MID by MID and ER&A personnel. Inspection and go-together revealed that no transportation or handling damage was incurred. The three major sections were transported to the site and assembled, then positioned as a unit (6,500 lbs.) in the partially completed civil works (see Figure 10). The short steel transition section was first cast into the east wall, then the assembled sections were suspended from the overhead beam of the powerhouse as a unit while the alignment was achieved using the transition section in the east (forward) wall as a datum. Concrete forms were then completed for the west wall into which the hydraulic section was cast. The support cradle was then positioned and concrete forms installed to cast the cradle in place.

The only difficulty encountered was the need for cribbing inside the front of the straight hydraulic section. The cribbing was installed to "round out" the tube to permit installation of the Dresser coupling. The out-of-round condition resulted only from elastic gravity deflection and did not represent handling damage or lack of manufactured quality. Future designs should consider a rounding ring on sections having more than one diameter of length.

Due to the nature of the testing planned for the Stone Drop installation, multiple generator and transmission support locations were required. These were achieved by hole patterns in steel beams embedded in the concrete generator floor. In addition, a larger than normal electrical trench was installed to accommodate the wiring for multiple generator positions.

5.1 Conclusions

The hydraulic section installation was accomplished with a minimum of difficulty, confirming the desirability of installation as a complete single unit. Interface tolerance problems were almost totally avoided with this technique.

Figure 10. Complete ER&A ultra-low head hydropower unit in place, prior to finishing civil works.

6.0 SITE MODELING AND RESULTING RECOMMENDED MODIFICATIONS

Upon completion of construction at the Stone Drop site, opening the flow control gate revealed some operational problems.

The final civil works configuration (See Figure 11) had the following effects:

- 1) Hydraulic jump at the upstream end of the folded weir, with an observed head loss of approximately one foot.
- 2) Formation of a vortex at the inside edge of the stoplog support wall.
- 3) Uneven, turbulent flow discharge at the diffuser outlet.
- 4) Significant trashrack vibration at most flow levels.

Of these conditions, 2) above was viewed as most critical as the vortex resulted in an air entrainment through the thruster hydraulic section.

Since removal of the stoplog support wall was unacceptable to the District, alternative corrections to the vortex formation were considered. On September 16, 1982, ER&A recommended a training wall from the stoplog wall to the weir, with radiused end points where it tied into the existing structures. A number of other options were discussed including a surface grate to break up the vortex and widening the canal.

6.1 ER&A Modeling

ER&A offered to model the alternative site reconfigurations on a cost-shared basis with MID. MID instead contracted with Hydro Research Science for the modeling activity. ER&A proceeded with independent site modeling and model operation and constructed a model basin in its shop area and replicated the Stone Drop site configuration on a 1:20 scale. The results of both HRS' funded and ER&A's unfunded efforts indicated the training wall was the correct solution. Details of the ER&A modeling are outlined in Table 6-1.

6.2 HRS Modeling

The HRS modeling activity was completed some time after ER&A's first model tests. It resulted in a design recommendation of the training wall from the weir to the stoplog wall and two horizontal vanes in the inlet to the turbine, as shown in Figure 16.

ER&A then duplicated the HRS design recommendation in its existing model. No further positive effect was observed from the addition of the vanes. Restriction of the inlet area with resulting velocity increase would, in fact, have a negative effect on turbine performance.

6.3 Conclusions and Results

Based on results of model tests, ER&A concluded that a training wall, as described, and moderate increase in cross section of the inlet area (to

maintain approximately 150 sq. ft.) would eliminate both the critical flow and vortex conditions on the upstream side of the installation.

It was decided to make the inlet modifications and observe the effects of same before addressing a diffuser fix; in fact, to see if the diffuser flow would stabilize when air entrainment was eliminated.

MID elected to install the horizontal inlet vanes as well as the wall, and modify the canal bank to a vertical configuration.

Figure 11a. Hydraulic jump and head loss.

Figure 11b. Stoplog wall vortex.

Figure 11c. Turbulent discharge.

Table 6-1

SUMMARY OF MODEL CONDITIONS AND RESULTS

RUN #	CONDITIONS MODELED	RESULTS
1 (design flow)	Widened inlet channel, other features as-built. and Opened vent tube atop hydraulic section and removed trashrack	Hydraulic jump and critical channel flow eliminated; .615 ft. equiv. head loss; vortex (see Figure 12) Air entrainment; smoother flow but vortex
2 (design flow)	Same as final #1 run and removed inlet roof support columns.	Minor flow smoothing; vortex, air entrainment, and head loss (1.25 ft. equiv.)
3 (design flow)	Same as #2 plus training wall and grid and Low flow	Vortex eliminated but grid height critical (See Figure 13) Jump and critical flow returned
4 (full flow)	Same as #1 plus truncated weir and Stoplog wall removed	Smooth flow to inlet area, vortex, weir nose head loss eliminated. Minor vortices (Figure 14), smooth draft tube flow
5 (design flow)	Same as #4	Same as 4 but more head loss
6 (design flow)	Same as #4, then reintroduced stoplog wall and weir nose and Training Wall Added	Vortex re-introduced Vortex eliminated (Figure 15)

Figure 12. Original configuration plus widened canal (Test Run #1).

Figure 13. Columns removed and vortex-dispersing grid in place prior to placing training wall (Test Run #3).

Figure 14. Stoplog wall removed (Test Run #4).

Figure 15. Training wall in place (Test Run #6).

Figure 16. HRS recommended modifications to MID Stone Drop inlet structure.

Figure 17. Stone Drop Outlet Modifications

TABLE I: VELOCITIES AT DRAFT TUBE OUTLET (FPS)

VELOCITY PROFILE FACING UPSTREAM

Note:

1. 40% MODIFICATIONS INSTALLED
2. 4 TURBINE = 350 CFS

NO.	REVISION	DATE	MODESTO IRRIGATION DISTRICT
			STONE DRIPS OUTLET MODIFICATIONS
		DATE: 1-4-85	DWG. BY: J.S.
		SCALE: 1/2"=1'-0"	APP. BY:
		DWG. NO. 10000	APP. BY:
		Q.O. NO. 26-323	

7.0 TESTING

The testing activity can be categorized into two levels of testing: 1) first article performance characterization, and 2) installed performance evaluation. A description of the specific tests performed and the identification of test support equipment required to accomplish the testing is defined in the Test Plan. Test results are described in the Test Report.

7.1 First Article Configuration Testing

The "first article" testing is performed for the first installation of a turbine type (or size) or when hydraulic flow conditions of a special character exist which would be a significant departure from prior experience. The first article testing may or may not include a system enhancement effort. The first article testing includes a performance evaluation of the thruster/turbine over a range of hydraulic heads and turbine speeds. This type of testing should be performed on any new installation of any new thruster/turbine which has not been characterized or when significant departure from previous hydraulic flow configurations are encountered. The object of the tests are to establish the best operating efficiency point (turbine speed) for this particular installation and obtain other engineering data for future installation of this specific type of ULHH unit at other hydraulic heads and sites.

The performance evaluation consists of measurement of power generated at a range of hydraulic heads, and a range of turbine speeds. The purpose is to fully characterize the turbine characteristics.

In addition to the normal performance characterization derived by a first article test, the Stone Drop installation also explored the comparative performance of the thruster blade facing forward versus the blade facing downstream. At question is the effectiveness of the supporting struts as straightening vanes. Also, the thruster package normally is provided with a symmetrical blade contour having a very blunt edge, since a thruster must operate in both forward and reverse thrust modes. As a turbine, only one direction of operation is required, therefore a separate test activity was performed to evaluate improvement achievable by blade enhancement, especially contouring the leading edge.

Evaluation of system modification to enhance the efficiency of the installation is accomplished in the System Enhancement phase. Modifications may consist of hydraulic flow and physical structures enhancement as well as turbine/generator modifications.

The specific tests performed are described in the MID Installation Test Plan. Briefly, performance (flow, power, and hydraulic losses) is evaluated at four turbine speeds at three hydraulic heads, i.e., twelve test conditions. In addition, free flow (no power) or runaway conditions and load disconnect response test with automatic hydraulic gate closure were performed. Testing was also to include direct drive by direct coupling of the generator to the turbine (comparable to 1:1 belt and pulley transmission coupling) to evaluate transmission efficiency. This configuration was later deleted.

7.2 Installed Performance Evaluation

The purpose of this testing is to evaluate installed performance. These are the tests also performed on the subsequent installation of turbine types which have been previously characterized. Flow and generated power measurements are evaluated at operating condition(s). This effort includes full system functional and operational check-out.

The installed performance evaluation should be performed on every installation to evaluate performance (power vs. flow) for the particular hydraulic flow conditions, including head variation where applicable. This represents the minimum testing to be performed on subsequent installations of thruster/turbines which have been characterized.

7.3 Conclusions

The first article configuration testing activity should be regarded as a non-recurring activity for the BT550 thruster-based applications; and recurring activity for initial installation of other configurations.

8.0 BASELINE ENVIRONMENTAL CONDITIONS AT STONE DROP

The environmental effects of installing and operating a hydropower plant at Stone Drop on the Modesto Irrigation District Main Canal were addressed in a 1978 feasibility study performed primarily by CH2M Hill.¹ This DOE-funded study examined several equipment options for power production at Stone Drop. The study concluded that the environmental effects of 1) installing hydropower equipment and, 2) operating a run-of-river plant in an existing irrigation canal were not significant. In fact, the alternative of not constructing the project could have more direct impact on the region than the proposed project because the irrigation district would still need equivalent electricity to satisfy customer demand. The alternative sources at the time of the feasibility study included a new gas turbine peaking plant, a new nuclear plant, and additional hydropower capacity on natural watercourses.

Figure 2 (Section 1.0) shows Stone Drop and its surroundings. The following verbal description of the Regional Geology and Environmental Setting is taken directly from the CH2M HILL study (pp. 7, 8, 34 and 35):

8.1 Regional Geology

8.1.1 Geomorphology

The site lies within the "dissected uplands" physiographic unit (Ref. 1, p. 7) of the Great Valley geomorphic province. This area is intermediate between low-lying alluvial plains and fans of the San Joaquin Valley and the more deeply dissected and topographically higher Sierra Nevada foothills. The dissected uplands have a width of about 14 miles in this area and local relief as great as 150 feet. Within the uplands the Tuolumne River has developed two terraces and is trenched about 200 feet (Ref. 1, p. 8).

8.1.2 Geologic Structures

The most important structural feature in this area is the southwestward slope of the Sierra Nevada basement complex which locally underlies the valley sediments. This slope is a consequence of the uplifting of the eastern edge of the Sierra block; overlying sedimentary rocks and deposits reflect this southwestward inclination and homoclinally dip southwestward.

8.1.3 Geologic Formations

Two geologic formations underlie the Stone Drop and Modesto Reservoir sites, and a third formation outcrops nearby.

- o Mehrten Formation. The Mehrten formation is of Pliocene age (5 to 10 million years old) and underlies the Modesto Reservoir and probably the dam. It consists of fluvial deposits of sandstone, conglomerate, tuff and tuff breccia (indurated mudflow), siltstone, and claystone. A distinguishing feature of this

formation is the large amount of andesitic volcanic material that occurs in most of its deposits. U.S. Bureau of Reclamation tests wells indicate the Mehrten may be about 450 feet thick in this area.

- o Continental Deposits. Unconsolidated nonmarine sediment of Plio-Pleistocene age (1 to 5 million years old) crops out surrounding the Stord Drop site and to the south of the reservoir. These deposits are younger than the Mehrten formation and may locally overlie them where the Mehrten does not crop out. The continental deposits consist of poorly sorted gravel, sand, silt, and clay ranging from a few feet to 450 feet in thickness.
- o Older Alluvium. The older alluvium is unconsolidated interbedded gravel, sand, silt, and clay of Pleistocene and Holocene age (a few thousand to 2 million years old). It outcrops to the south and west of the reservoir site. In some low-lying areas, it overlies the slightly older and generally finer-grained continental deposits.

8.1.4 Seismicity

The sites lie within a region of historically low seismicity. The nearest fault considered potentially active is the Bear Mountains fault which is part of the Foothills fault system. This fault lies approximately 16 miles northeast of the site and, along with other major faults of the Foothill fault system, is considered to be capable of generating a Maximum Credible Earthquake (MCE) of Richter Magnitude 6.5. If such an MCE occurred on the Bear Mountain fault at a distance of 16 miles from the site, a maximum bedrock acceleration of 0.21 g could be expected at the site, with a duration of strong ground motion (acceleration greater than 0.05 g) of 15 seconds and a predominant period of 0.3 second.

8.2 Environmental Setting

8.2.1 Topography

The terrain surrounding the Modesto Main Canal and reservoir is generally rolling hills with the elevation rising to the east at a rate of 10 feet per mile.

8.2.2 Vegetation and Wildlife

The surrounding area has been converted to agricultural or irrigated pasture land. The canal banks are overgrown by non-native weed communities. There are several rare and endangered plant species listed for Stanislaus County. None, however, are known to exist within the project area.²

The canal area does not support a high diversity of wildlife species. Those that are present are indigenous to the grassy plains and agricultural areas found nearby. Rare and endangered species in Stanislaus County include the blunt-nosed leopard lizard, the kit fox, and

the giant garter snake. None of these are known to exist in the project area.³

8.2.3 Water Quality

The quality of the water in the Modesto Main Canal is generally excellent. Most reservoir releases are clear and dissolved oxygen concentration is high. The major sources of suspended sediment in the canal are mountain uplands and agricultural fields.

8.2.4 Land Uses

The Stanislaus County General Plan⁴ classifies the area along the Modesto Main Canal as "Agriculture." Current zoning regulations for Stanislaus County show the project sites zoned as "Exclusive Agriculture - (A-1210)."

8.2.5 Socio-Economics

Most businesses in the county are directly or indirectly related to the production of agricultural commodities. The economic stability of the region is highly dependent on the irrigation deliveries of the main canal as well as the generation of hydroelectric power from the Don Pedro Dam.

The population in this rural area is low and scattered. However, the present and projected growth patterns of Modesto and Waterford indicate a development trend toward the Modesto Reservoir and foothills to the east. There are no wildlife refuges located near either of the two project sites.

8.2.6 Air Quality

While air pollution is a regional problem in Stanislaus County, levels have generally improved over the past several years as a result of stricter vehicle emission standards and a greater proportion of cars with emission control devices. This trend can be expected to continue as more restrictive emission controls are brought on line, at least until the absolute number of vehicles in the region overcome the gains made through a per unit reduction.

8.2.7 Cultural Resources

According to the California State Office of Historic Preservation (SHPO)⁵ there are no known archaeologic, paleontologic, or historic sites in the project area. There are no historical landmark or points of interest near the project sites that are currently included in the National Register of Historic Places, the Inventory of Points of Historical Interest, or the California State Historic Landmarks Publications.

8.3 Conclusion

The CH2M HILL study evaluated possible environmental effects of site development using the same categories distinguished for the description of the environmental setting. Under no category was any significant impact

cited. ER&A found no evidence justifying any other conclusion.

The issue of algae blooms in the irrigation canal has been raised by ER&A engineers. Pleated weirs used on the MID system can impound water long enough to permit algae to grow. At the Stone Drop location, the District installed a pleated weir to regulate head more precisely. The hydropower installation will draw water from one side of the new weir. Engineers at ER&A agree that operation of the power plant will prevent the ponding which promotes algae growth on that side of the weir.

ER&A engineers have also observed fish in relict ponds in the canal during the dry season. The fish are likely escapees from upstream hatcheries. These canal fish are not considered an important resource; in fact the District discourages fishing in its canals.

References

- 1 CH2M HILL 1978. Lower Main Canal Hydro Stations Feasibility Assessment Report. Prepared for Modesto Irrigation District under MID's DOE Cooperative Agreement # EW-78-F-07-1783. Sacramento, California.
- 2 Stanislaus Area Association of Governments, Modesto, California. Environmental Resources Management Element(s), adopted November 1974 and February 1975.
- 3 California Department of Fish and Game, Region IV, Fresno, California
- 4 Stanislaus County, Modesto, California, Stanislaus County General Plan, 1966.
- 5 California Department of Parks and Recreation, State Office of Historic Preservation, Sacramento, California.