DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DOE/CS/89031--T1

DE87 005783

GEOTEC ENGINEERING CONCEPT STUDY

March 1984

Prepared for:

Naval Facilities Engineering Command
Naval Weapons Center,
China Lake, CA

Contract N62474-83-R-5307

TRW Energy Development Group
Redondo Beach, CA

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

TABLE OF CONTENTS

	PAGE
1.0 INTRODUCTION	1
2.0 RESOURCE AND SITE ASSESSMENT AND VERIFICATION	4
2.1 Task Scope	4
2.2 GEOTEC Plant System Site	4
2.3 Geothermal Resource Verification	9
2.4 Geofluid Reinjectivity	9
3.0 ENVIRONMENTAL ASSESSMENT	12
3.1 Assessment Objective	12
3.2 Production Well Sites	12
3.3 Geofluid Disposal	12
3.4 Seawater Line Routes	13
4.0 GEOTEC CYCLE DEFINITION AND SELECTION	14
4.1 Potential GEOTEC Cycles	14
4.2 Design Optimization Program (DOP)	21
4.3 Comparison of Single and Dual Binary Cycle Performances	22
5.0 ISOBUTANE SINGLE BINARY POWER CYCLE SENSITIVITY ANALYSES	29
5.1 Sensitivity of Isobutane Single Binary Cycle . .	29
6.0 GEOTEC SYSTEM DESIGN	34
6.1 Design Basis	34
6.2 Power Cycle Description	34
6.3 Seawater System Design	43
6.4 GEOTEC Electric Power System	52

7.0	GEOTEC PLANT SYSTEM COST ESTIMATE	56
7.1	Scope of GEOTEC Plant System Cost Estimate . . .	56
8.0	OPERATION AND MAINTENANCE PLANNING	59
8.1	Objective of Operating and Maintenance Planning .	59
8.2	Manpower Requirements	59
8.3	Maintenance	59
9.0	GEOTEC PLANT SYSTEM CONSTRUCTION AND DEPLOYMENT PLANNING	66
9.1	Project Schedule	66
9.2	Long Lead Items	66
10.0	RECOMMENDATIONS	69
	REFERENCES	70

LIST OF FIGURES

No.	TITLE	PAGE
2-1	Northern Portion of Adak Island	5
2-2	Andrew Volcano Across Andrew Lake	6
2-3	Proposed GEOTEC Plant System Siting	7
2-4	North Shore of Andrew Lake Near GEOTEC Plant Site	8
2-5	Solubility of Silica Materials	11
4-1	Flash Binary Cycle	15
4-2	Single Binary Cycle	17
4-3	Dual Binary Cycle	20
4-4	Comparison of Single and Dual Binary Cycle Geothermal Fluid Requirements	25
5-1	Sensitivity of Single Binary Cycle GEOTEC Plant to Wellhead Temperature	30
5-2	Sensitivity of SBC GEOTEC Plant to Well Flow	31
5-3	Sensitivity of SBC to Well Drawdown	31
6-1	Major Elements of GEOTEC System	36
6-2	GEOTEC Brine Lines	37
6-3	Plot Plan	39
6-4	Pipe Makeup Facility	45
6-5	Pipe Pulling Operation	46
6-6	Proposed Pipeline Route and Trench Cross Sections	48
6-7	Pump Station Onshore of Andrew Bay	50
6-8	Detail of FR Pipeline	51
6-9	Electric Power Distribution and Transmission Scheme	53
6-10	GEOTEC Power Lines	54
8-1	All-Resident Plant Staffing Scenario	60
8-2	Off-Island Plant Staffing Scenario	61
9-1	Adak GEOTEC Plant Project Schedule	67

LIST OF TABLES

No.	TITLE	PAGE
1-1	GEOTEC Study Tasks	3
4-1	Properties of Candidate Single Binary Cycle Fluids . .	18
4-2	Plant Design Constraints and Operating Conditions . .	24
4-3	GEOCOST Comparison of Single and Dual Binary Cycles .	27
5-1	Single Binary Cycle GEOTEC Plant System Design Characteristics	33
6-1	Design Features of Offshore Seawater Pipeline	47
6-2	GEOTEC Electric Plant Power Balance	55
7-1	GEOTEC Plant Cost Summary - 7 F Seawater Rise	57
7-2	GEOTEC Plant Cost Summary - 20 F Seawater Rise . . .	58
8-1	Inspection and Maintenance Cycles	63
8-2	GEOTEC Spares Requirements	64
9-1	Long Lead Items	68

1. INTRODUCTION

The U.S. Navy, under the leadership of the Geothermal Utilization Division of the Naval Weapons Center (NWC) and the Naval Civil Engineering Laboratory (CEL) has been evaluating the use of renewable energy resources to provide military installations' electric and thermal energy needs. One aspect of that evaluation involves the use of lower grade (120 - 200 C) geothermal heat sources in conjunction with seawater cooling and ocean thermal energy conversion (OTEC) technology to increase electric generation efficiency. The combination of geothermal and OTEC technologies has been termed Geothermal - Enhanced Ocean Thermal Energy Conversion (GEOTEC).

To pursue the GEOTEC option, NWC and CEL have collaborated with the U.S. Department of Energy (DoE), Division of Ocean Energy Technology, and the Applied Physics Laboratory (APL) of The Johns Hopkins University. The results of these efforts can be found in references 1 and 2, in which projected performance levels of conceptual GEOTEC systems have been analyzed as functions of major design and site-specific parameters such as geothermal resource temperature, geofluid flow rates, and well drawdown, and geofluid reinjection temperature and injectivity.

Reference 2 discusses the geothermal potential of eleven military sites. Of these the Naval Station at Adak, Alaska appears to be a prime candidate in view of its high probability of having a viable geothermal resource, the Station's lack of firm commercial electric power, the age of the present base's generating system, and the relatively high logistical cost of supplying fossil fuels to the island. Reference 3 examined the potential of a pure geothermal power system for the Station which could produce electricity and/or space heating.

Reference 4 addressed the installed cost of a GEOTEC plant for Adak, and described in very conceptual terms the design of such an installation. The study showed that GEOTEC can be an attractive electric power system for that site.

This report presents the results of a more detailed conceptual design study for a GEOTEC plant on Adak. The study, Geothermal Enhanced Ocean Energy Conversion (GEOTEC), was conducted by the Energy Development Group of TRW Inc. for NWC under contract N62474-83-R-5307, during the period from August 1983 to March 1984. In conducting the study TRW engaged the services of the following subcontractors:

Gibbs and Hill	Geofluid system and power plant design, and cost estimation
Woodward-Clyde Consultants	Geothermal resource verification and environmental concerns

Hawaiian Dredging
and Construction

Overland seawater pipeline and power
plant installation and cost estimation

R.J. Brown and
Associates

Offshore seawater system design and
costing

The objective of the GEOTEC Program was to develop a design concept for implementation at Adak Island using geothermal heat and cold seawater for the generation of 12 Mw (net) electricity for the Naval Station. The design concept was to be based upon existing geothermal and OTEC technologies. The plant was to be assumed to operate on a utility-system basis, with a controlled output and appropriate safety features. Plant availability of 90% was a design goal. The plant design had to incorporate modularity, and consider the operational and maintenance aspects of a remote site in terms of logistical supply, redundancy, maintenance personnel, and spares. Subsystems, pre-assembled at a U.S. west coast site, were to be used to the maximum degree possible.

Specific design study data and results were identified in the contract Statement of Work, shown in Appendix A. The Statement of Work also identified site-specific characteristics which were to be taken into account during the study. Certain of these characteristics, such as geofluid temperature, flow rate, and well drawdown had sufficient uncertainty so that they were to be treated parametrically. Other site-specific data such as climatology, bathymetry, topography, port and road facilities, etc. were supplied as part of the government-furnished data.

The report is presented in two volumes. Volume 1, is structured about the nine major tasks identified by TRW in its proposal to NWC as shown in Table 1-1, and report contains narratives which describe the initial data sets available, the assumptions and their rationale, and the methodology employed, and major results and conclusions. Additionally this volume contains a set of recommendations the TRW design team believes should be carried out in support of GEOTEC power development at Adak.

Volume 2 consists of original contract material, reports delivered to TRW by the subcontractors, engineering calculations, computer model descriptions and sample printouts, and major project maps, drawing and diagrams. Much of this material is referred to in Volume 1.

TABLE 1-1
GEOTEC STUDY TASKS

Task 1	Resource and Site Assessment/Verification
Task 2	Environmental Assessment
Task 3	Power Cycle Definition
Task 4	Power Cycle Analysis
Task 5	GEOTEC System Sensitivity Analyses
Task 6	System Design
Task 7	System Cost Estimation
Task 8	Operation and Maintenance Planning
Task 9	System Construction and Deployment

2.0 RESOURCE AND SITE ASSESSMENT AND VERIFICATION

2.1 Task Scope

The resource and site assessment task was undertaken to determine the degree of uncertainties in the those site-specific data bases which could influence plant system design. Primary attention was focused on review of available NWC-supplied data with respect to the geothermal resource and the ocean environment.

2.2 GEOTEC Plant System Site

Adak Island is a member of the Andreonof Island Chain in the Aleutian Chain, located at 177 west longitude and 52 north latitude, approximately midway between mainland Alaska and Siberia. The island is about 30 miles long (north-south) and 20 miles wide. Adak Naval Station occupies the northern third with the remainder administered by the Bureau of Fish and Wild Life as part of the Aleutian Islands National Wildlife Refuge.

There are approximately 5000 civilian and military personnel at the Station. Aviation fuel is used for heating and electricity. Electricity is produced by diesel-generators which are reportedly at or beyond their service life.

An aerial view of the northern portion of the island can be seen in Figure 2-1. Mt. Adagdak dominates the northern-most part of the island: its snow-covered flanks are clearly visible in the photo. To the south of Mt. Adagdak lies the remains of Andrew Volcano. Andrew Lake, a fresh water lake which drains Mt. Adagdak and Mt. Moffet to the south, is separated from Andrew Bay and the Bering Sea by a land spit. To the east and south lies the main military and civilian areas of Adak Naval Station, consisting of an air field, port facilities, military installations and civilian residences. The photograph in Figure 2-2 shows Andrew Volcano looking toward the north across Andrew Lake.

The proposed site of the GEOTEC plant is shown in the map of Figure 2-3. The plant will lie on the northern shore of Andrew Lake, at the end of the valley between Adak Volcano and Mt. Adagdak. Geothermal reconnaissance work performed during the 1970's and early 1980's showed that the best geothermal potential lay in the northern part of the island.

Geothermal wells are assumed to be located along the valley through which Pollitt Road, the major north-south access road, runs. The description of the GEOTEC system site supplied in the data package from the Navy called for a seawater pump station to be located on the shore of Andrew Bay, just below Adak Volcano. Figure 2-4 is a photograph of Andrew Lake looking to the south. Mt. Moffet is to the left, and the GEOTEC plant location would be to the right at the foot of Andrew Volcano.

FIGURE 2-1 NORTHERN PORTION OF ADAK ISLAND

FIGURE 2-2 ANDREW VOLCANO ACROSS ANDREW LAKE

FIGURE 2-3 PROPOSED GEOTEC PLANT SYSTEM SITING

FIGURE 2-4 NORTH SHORE OF ANDREW LAKE NEAR GEOTEC PLANT SITE

2.3 Geothermal Resource Verification

The geothermal resource verification task was conducted by review of geotechnical, geochemical and geothermal data and reports supplied by NWC. To augment the review and gain first hand information from those Navy personnel and consultants who had participated in establishing the data base, interviews and discussions were held at NWC. The report of the interview and resource evaluation procedure can be found in Appendix B.

Drawing from that report, the following conclusions were made.

1. A wellhead temperature of 180 C is reasonable and should be taken as the baseline value for system design. It is highly unlikely that geofluid temperatures in excess of 200 C will be found at the depths considered in this study, e.g. 5000 feet.

2. A nominal discharge rate of 1000 gpm at 656 foot drawdown is reasonable; however both of these characteristics may be lower by 50 % or greater by 100 %. The lower flowrate value is likely to be realized in view of probable tight subsurface formations.

3. The geofluid reservoir is probably fed by the ocean, and the geothermal brine will be dominated by salt at ocean concentration levels.

The reference report strongly recommends that an exploration well drilling program be carried out in order to validate the design basis before proceeding to a refined conceptual design or preliminary design phase.

2.4 Geofluid Reinjectivity

According to the Statement of Work, two injection wells are to be assumed to be located about 0.2 miles south of the GEOTEC plant site near the junction of Pollitt and Davis Roads. No data exists to define the reinjectivity of the subsurface at that location. The Statement of Work suggests a lower reinjection temperature of 75 C.

Silica is a common precipitate in geothermal systems and may clog heat transfer equipment and reinjection wells. In the latter case, swabbing of the wells may correct the problem; however, in extreme cases the reinjection wells may have to be abandoned and new wells drilled. In other geothermal projects poor or dry production wells may be used for reinjection wells. The proposed layout at Adak would not support this approach.

Data from the verified hot springs on the eastern shore of Andrew Bay show silica concentrations of about 220 ppm. According to reference 2, samples from these springs have been diluted with seawater and it is highly likely that production well brines will have higher silica concentrations.

Figure 2-5 shows the solubility of various silica forms in water as a function of solution temperature. While the amorphous forms of silica are soluble down to 50 C, the more common forms of silica found in geothermal brines have solubilities below the Adak values for temperatures below 100 C. For this reason, 100 C was chosen as a nominal reinjection temperature, e.g. the minimum heat exchanger geofluid exit temperature.

(It has been pointed out in reference 7 that the silica precipitation problem may be reduced due to the dependence on pH and the short transit time of the brine through the brinelines. It is our belief that the presumption of reduced precipitation probability is not in keeping with a conservative set of assumptions for the system. The influence of a lower reinjection temperature on plant system cost is briefly discussed in Section 5. It is felt that the results shown in that section indicate that the overall GEOTEC plant system costs would not be significantly changed, within the accuracy of the cost estimation process, with the use of a lower reinjection temperature.)

FIGURE 2-5 SOLUBILITY OF SILICA MATERIALS

3.0 ENVIRONMENTAL ASSESSMENT

3.1 Assessment Objective

The objective of the environmental assessment task was to determine the extent to which GEOTEC plant design would be driven by consideration of the Adak environment and the adverse impacts which the plant's operation might cause. Discussion of some of these effects can be found in Appendix C.

3.2 Production Well Sites

Figure 2-3 shows the location of production wells as defined by the Navy. These well sites lend themselves to a geofluid collection system which will lie in a line along Pollitt Road. Because of the proximity to the road, access to the drill pads will be relatively simple and the impact on the environment due to the need for additional roads will be minimal.

3.3 Geofluid Disposal

Reinjection wells represent additional costs for the GEOTEC system in terms of their drilling and outfitting, as well as introducing added maintenance costs, and increasing the energy required to reinject spent brine into the subsurface formations. One approach to eliminate the need for reinjection wells would be to discharge the geofluid directly into an open body of water such as Sitkin Sound or Andrew Bay. An ocean discharge approach was identified as an option in reference 3. In that study, Bruce suggested that if the composition of the geofluid were similar to the surrounding seawater, the warmth of the discharge could have a beneficial effect by increasing the fish and shellfish population.

NWC and CEL project personnel were consulted and this approach was rejected in view of the possibility of toxic trace materials in the geofluid and concern over possible problems during project permitting.

A second approach considered the case in which GEOTEC-warmed seawater would be mixed with spent brine, cooling and diluting it before discharge into the sea. This technique would not only eliminate the need for reinjection wells, but would also eliminate the need for a separate brine disposal line. The dilution of brine in seawater would be sufficiently high to preclude silica precipitation in the seawater disposal line. This concept was rejected as introducing potential environmental problems similar to the direct geofluid disposal concept.

For the above reasons the concept of using reinjection wells was retained.

3.4 Seawater Line Routes

The Statement of Work defined the location of the seawater intake to be near the northwest corner of the land spit between Andrew Bay and Andrew Lake. The intake was to take seawater in from Andrew Bay. Several sites for disposal of heated seawater were suggested; Andrew Bay, Sitkin Sound and Clam Lagoon. The potential seawater pipeline routes were shown in Figure 2-3.

Andrew Lake was suggested by the study team as an alternate source for cold water for the plant's cooling system. Andrew Lake appears to be a fresh water body fed from runoff from the surrounding mountains. There was little data on the biological and hydrological properties of the lake. Among the advantages of using Andrew Lake water are; reduced corrosion of the cooling water handling system, lowered construction costs due to the elimination of a seawater intake structure capable of resisting ocean wave conditions, and a shortened seawater pipeline.

Lowering of Andrew Lake's level and intrusion of salt water were judged to be possible consequences of using Andrew Lake as a cold water source and it was dropped from further consideration.

Clam Lagoon was rejected as a seawater disposal site because of its low flushing and mixing action: it was judged to have more severe environmental limitations than Andrew Bay.

Only limited data on the wave conditions in Sitkin Sound was available. It was suggested by Navy personnel that, due to the more protected nature of the northeast side of the island and the shorter fetch of the prevailing winds, Sitkin Sound would have significantly lower wave heights against which the seawater pipeline would have to be designed than Andrew Bay.

A seawater pipeline into Sitkin Sound is approximately twice the length of a pipeline to Andrew Bay. A Sitkin Sound pipeline would have about five more road crossings, and would have to cross or skirt the sensitive military area at Zito Point. Consideration of these factors led to selection of Andrew Bay as the site for both seawater intake and outfall pipes systems.

4.0 GEOTEC CYCLE DEFINITION AND SELECTION

4.1 Task Objectives

The objectives of the power system definition task portion of the study were to select specific candidate GEOTEC power system concepts, and to select one cycle on which to base the conceptual design of the GEOTEC system for Adak.

The methodology used in the task included:

- o identification of potential power system concepts,
- o imposition of site-dependent parameters on the concepts in order to eliminate those systems incompatible with the Adak environment,
- o modification of a system optimization program (ODOP) which had previously been used for OTEC system tradeoff analyses to include geothermal subsystems and multiple working fluid loops,
- o use of the modified program to assess the relative performance of candidate cycles, and
- o use of standardized subsystem cost models to evaluate the cost differences among candidate GEOTEC systems.

4.1 Potential GEOTEC cycles

Three generic types of power cycles were initially selected as candidates for GEOTEC use:

- o flash binary,
- o single binary, and
- o dual binary.

4.1.1 Flash Binary Cycle

The flash binary cycle, shown in Figure 4-1, generates steam by the homo-enthalpic expansion of pressurized liquid geofluid in a flash tank. Flashed steam drives a steam turbine; the expanded steam is condensed and pumped back to a pressure level where it is combined with the remainder of the geofluid stream for reinjection.

Non-flashed geofluid transfers sensible heat to another working fluid loop vaporizing the working fluid which in turn then drives a non-aqueous-vapor turbine. The second working fluid is also condensed by cold seawater. Flashing of the geofluid

FIGURE 4-1 FLASH BINARY CYCLE

reduces the temperature of the remaining brine, thereby decreasing the temperature potential of the non-aqueous working fluid portion of the cycle.

The flash binary cycle was rejected on the following grounds. Flash systems currently in use in geothermal projects rely on wellhead temperatures in excess of 200 C (reference 5). Below that temperature the choice is to leave the geofluid pressurized, extracting only sensible heat by heat transfer to a secondary working fluid thereby eliminating the need for a flash tank and vapor separator, and a concentrated brine treatment system.

It was also judged that the permeability of the geothermal formations was probably sufficiently low (a drawdown of at least 656 feet at 1000 gpm) so as to require well pumps to prevent downhole flashing.

4.1.2 Single Binary Cycle

The single binary cycle is shown in simplified form in Figure 4-2. Geofluid heat is transferred to a closed loop working fluid system. The heat vaporizes the working fluid and the expanding vapor drives a turbine. Expanded vapor is condensed by cold seawater and re-pumped to the evaporator. Heated seawater is rejected, and cooled brine is reinjected.

A number of fluids were examined as candidate single binary fluids. These fluids were selected from the Monsanto study of working fluids for solar-to-electric energy conversion, reference 6, in which the Rankine cycle efficiencies of 11 working fluids were evaluated for their Rankine cycle efficiencies when used between heat source/rejection of interest to solar-electric conversion.

Of relevance to the GEOTEC study is the reference's evaluation of cycle efficiencies for a heat source temperature of 177 C (350 F) and heat sink temperatures between 66 and 121 C (150 and 250 F). While the reference study did not calculate Rankine cycle efficiencies at the seawater heat sink temperature of this study, about 5 C, its results are indicative of the relative cycle efficiencies which could be achieved at lower heat rejection temperatures.

A comparison of selected non-aqueous fluids with water is shown in Table 4-1. Toluene, Freon 113, isobutane, and water were judged to be acceptable working fluid candidates according to their efficiencies. Toluene's toxicity, while greater than the other fluids, was judged to be low enough for the fluid to be considered further.

Freon 113 was rejected from consideration because the 180 C nominal heat source temperature is close to the point at which Freon loses chemical stability.

FIGURE 4-2 SINGLE BINARY CYCLE

TABLE 4-1 PROPERTIES OF CANDIDATE SINGLE BINARY CYCLE FLUIDS

FLUID	CRITICAL TEMP °C	CRITICAL PRESSURE ATMOS	THERMAL STAB LIMIT °C	EXPANSION PROCESS	RANKINE CYCLE EFFICIENCY		EXPLOSIVE LIMITS IN AIR %		OSHA EXPOSURE STD PPM	DISASTER HAZARD	ODOR
					180/70	180/120	HI	LO			
WATER	374	218.0	566	WETTING	5.9	3.0					
ISOBUTANE	135	37	232	DRYING	8.3	4.1	8.5	1.9	NOT TOXIC	DANGEROUS WITH OXIDIZ+ ING AGENTS	ASPHYXIAN
TOLUENE	319	40.5	480	DRYING	16.0	7.7	7.0	1.3	TWA-200	MOD, DANGER, EMITS TOXIC FUMES	BENZENE-LIKE

As shown in the table, toluene is a better choice than either isobutane or water in terms of cycle efficiency. To assure that toluene-based equipment was available, Sunstrand Corporation was contacted. Sunstrand had built several toluene turbines under DoE-sponsorship during the 1970's for solar and waste heat recovery programs. The largest machine that they produced was 0.75 Mwe. With the close of those programs, and the lack of a market for non-aqueous fluid bottoming cycle systems, Sunstrand elected not to pursue this market any further, and to the best of their knowledge no manufacturer would be willing to build the larger toluene turbines (5-10 Mwe) that would be needed for Adak. On the basis of the lack of turbomachinery for the GEOTEC system, toluene was dropped from further consideration.

Of the remaining fluids, water and isobutane, reference 6 shows that isobutane has almost twice the cycle efficiency of water in the restricted temperature range of that reference's work. Simple hand calculations of system efficiencies for the heat addition and rejection temperatures of this study show isobutane to have a higher efficiency, although by not the same margin as calculated in the Monsanto study.

Isobutane turbines have been built in sizes in excess of 1 Mwe: a 70 Mwe machine is currently undergoing shakedown for a Heber, California geothermal project. With the assurance that isobutane turbomachines would be available, isobutane was chosen as the working fluid for subsequent single binary cycle analyses.

(Ammonia was also considered as a working fluid for a single binary system. In many respects ammonia is similar to water, e.g., relatively low molecular weight and high ratio of heat-of-vaporization to specific heat, qualities necessary for good Rankine cycle performance. However, it was rejected from further consideration as a single binary cycle fluid since at the expected heat source temperature, ammonia's vapor pressure is over 500 psi, and according to heat exchanger manufacturers, would require prohibitively expensive tube-in-shell heat exchangers.)

(It is noted that during the preparation of this report, APL in reference 7 evaluated water, ammonia, isobutane and propane as candidates for single binary cycles.* Their results showed water, isobutane and ammonia enjoying higher efficiencies for a geofluid temperature of 180 C. At lower -120 to 140 C- heat source temperatures, ammonia and propane were the fluids of choice.)

4.1.3 Dual Binary Cycle

A dual binary cycle is shown schematically in Figure 4-3. Heat is transferred from pressurized geothermal fluid to an upper Rankine cycle, which produces electrical power and rejects its cycle heat to a lower or bottoming Rankine cycle. The dual binary cycle attempts to improve overall efficiency when compared to a

FIGURE 4-3 DUAL BINARY CYCLE

single binary cycle by employing thermodynamic working fluids which are matched to narrow temperature differences. The obvious disadvantages of the dual binary cycle concept lie in its additional complexity, pumps, heat exchangers, and added irreversible temperature drops.

Two combinations of working fluids were selected for screening as potential dual binary cycle candidates, water/ammonia and isobutane/ammonia. Ammonia was selected as the most attractive bottoming cycle working fluid for reasons given in the previous section, and on the basis of experience developed in its application to OTEC technology. Water and isobutane were chosen as the topping cycle working fluids for reasons given in Section 4.1.2.

Simple thermodynamic calculations were conducted to assess the relative dual binary cycle efficiencies of the two combinations assuming 180 C geothermal fluid wellhead and 100 C reinjection temperatures. In both sets of calculations the same minimum heat exchanger pinch points (15 F) were used, and the topping cycle's working fluid temperature drop through the topping cycle was sufficient to add heat to the ammonia (bottoming cycle) at a temperature low enough to keep the ammonia evaporator's pressure below 500 psia. These calculations showed the water/ammonia system to have a higher cycle efficiency than isobutane/ammonia (10.0% vs 8.7%). Based upon the above, water/ammonia was selected for further analysis as the dual binary cycle working fluid pair.

4.2 Design Optimization Program (DOP)

During the conceptualization of any system, assumptions, choices, and decisions are made which influence the design of the system. It is desirable to have a consistent methodology for making design decisions in order to maximize some criteria on which the system will be measured. This is the purpose of a DOP.

A DOP is an optimization routine for assessing a design concept. The DOP is composed of two major elements, a pre-processor and an optimization program. The former mathematically describes the performance of the system in terms of physical equations such as heat, mass, and dynamic balances. These sets of equations, defining the processes of the system, serve as inputs to a non-linear optimization program called Generalized Reduced Gradient. In this study the DOP is called GRG2. A more complete description of the basis and construction of the DOP may be found in Appendix D.

It is important to keep in mind that a DOP contains a systems level description of an isolated or particular design concept, e.g., one that is defined by a particular set of physical relationships and constraints. Some of the relationships and constraints, and therefore design decisions, must be made without recourse to the DOP computer model. DOP's by themselves

cannot compare different systems automatically, nor can they assess the reality of physical characteristics and constraints assigned to system models. The role of the DOP is to determine the best set of system variables subject to physical constraints, and system considerations such as cost.

After a DOP model is written and verified it can be used in two ways. First the model leads the system designer to a region of multivariant design space which is reasonable, that is, it fulfills all of the subsystem physical processes, satisfies all required equalities such as heat balances and pressure drops, and stays within constraints such as size, weight, etc.

Once the region of acceptable system design variable values has been established, an objective function such as cost or performance-at-fixed-cost may be minimized or maximized. The system designer can then employ the DOP model to evaluate sensitivity of the objective function to changes in system parameters such as heat source temperature, pressure drops in geofluid loops, component efficiencies, and heat exchanger design.

With these purposes in mind DOP models for both the single and dual binary cycles were developed. Much of the GEOTEC DOP model was based upon previous experience with DOP applied to OTEC design studies.

4.3 Comparison of Single and Dual Binary Cycle Performances

The water/ammonia dual binary cycle was compared to the isobutane single binary cycle as a function of geofluid wellhead temperature, assuming in all cases a 100 C reinjection temperature, 656 feet of drawdown, and the assumptions of the following section.

4.3.1 Assumptions and Constraints

A number of assumptions and physical constraints were placed on the DOP models. They are as follows:

1. Geofluid gathering system flow losses - The site of the GEOTEC plant at the southern end of Pollitt Road is below the elevation of proposed geothermal wells pads 1, 2 and 3. The gravitational head gain in the geothermal fluid as it flows to the plant is assumed to be equal to the pipeline pressure losses in the geothermal gathering system, and therefore those losses are not included in the model of parasitic loads.

2. Reinjection pressure - In the absence of reinjection well characterization, a reinjection wellhead pressure had to be assumed to ensure spent geofluid can be disposed. A conservative value of 50 psi was assumed.

3. Evaporator shell-side pressure - Tube-in-shell heat exchangers are assumed for both evaporators and condensers, with the working fluid on the shell side. Evaporator pressure levels are not allowed to exceed 500 psia in order to stay within guidelines suggested by heat exchanger manufacturers.

4. Pinch points - Pinch point temperature differences, that is the minimum difference between two fluids at the same station within a heat exchanger, were restricted to 15 F.

5. Geofluid gathering system temperature drop - A drop in the geofluid temperature from well head to GEOTEC plant of 2.8 C (5 F) was used. This value was assigned after consultation with geothermal pipeline insulation suppliers. Calculations supporting that temperature drop are found in Appendix E.

6. Equipment and component efficiencies -

Turbine (product of isentropic and mechanical efficiencies)	78.5%
Generator	97.0%
Working fluid pumps	80.0%
Seawater pumps	75.0%
Geofluid downhole pumps	40.0%

These efficiencies were derived from performance data of vendors and previous experience of the study team members on geothermal and OTEC projects.

7. Seawater pipeline pressure losses - The losses in the seawater lines are important parasitic drains on the output of the GEOTEC plant. Seawater losses were estimated by calculating the head losses in the 1.2 mile long feed and return lines, restricting the seawater flow to 6 feet/second. Appendix F contains the calculations for the seawater pipeline pressure drop.

The complete set of plant design constraints and operational conditions is shown in Table 4-2.

4.3.2 DOP Comparison of Single and Dual Binary Cycles

The results, shown in Figure 4-4, show that the isobutane single binary system requires slightly less geofluid at nominal well head conditions. As the well head temperature decreases the single binary cycle's advantage increases.

An explanation for the relative behavior of the two cycles is as follows. It is generally recognized that Rankine cycle efficiency at fixed heat source and rejection temperatures is increased if heat is added near the critical point of the working fluid. Cycle efficiency is also increased if the working fluid has a high ratio of heat of vaporization to specific heat.

TABLE 4-2 PLANT DESIGN CONSTRAINTS AND OPERATIONAL CONDITIONS

- 1. GEOFLUID FRICTIONAL LOSSES FROM PRODUCTION WELLS TO PLANT ARE APPROXIMATELY EQUAL TO GRAVITATIONAL HEAD GAIN**
- 2. REINJECTION PRESSURE OF 50 PSIA**
- 3. EVAPORATOR SHELL-SIDE PRESSURE $\leq$ 500 PSIA**
- 4. MINIMUM PINCH POINTS OF 15°F**
- 5. 5°F DROP FROM WELLHEAD TO PLANT**
- 6. MINIMUM REINJECTION TEMPERATURE OF 212°F**
- 7. 7° F MAXIMUM RISE IN SEAWATER TEMPERATURE**
- 8. MAXIMUM SEAWATER VELOCITY 6 FEET/SEC**

FIGURE 4-4 COMPARISON OF SINGLE AND DUAL BINARY CYCLE GEOTHERMAL FLUID REQUIREMENTS

The working fluid should have an isentropic saturated vapor pressure line so that it will neither superheat during expansion and thus require desuperheating, nor should it form moisture droplets which will affect turbine operation.

The choice of water as the upper working fluid of the dual binary cycle is justified in that it has a high ratio of heat of vaporization to specific heat. However the temperature of heat addition of the GEOTEC system is far below water's critical point. Furthermore, water is a wetting fluid (steam tends to condense upon isentropic expansion) and should be superheated to prevent droplets in the turbine. Superheating at the relatively low evaporator temperature and pressure will produce a "thin" vapor, requiring a large, e.g. low specific power, machine similar to the final stages of a conventional steam turbine.

Ammonia would be used at or near its critical point, but at the geofluid's temperature an ammonia evaporator would exceed the evaporator design pressure criteria. Using ammonia as a bottoming cycle reduces that problem, but tends to reduce the contribution of the ammonia cycle to overall dual binary cycle efficiency. As the geofluid wellhead temperature decreases, the efficiency of the water portion of the dual binary cycles decreases, shifting more of the burden for cycle performance to the ammonia portion. At the lower end of the heat addition temperature range thermodynamic consideration drives toward the elimination of the topping portion of the dual binary cycle and the use of a single fluid.

4.3.3 GEOCOST Comparison of Single and Dual Binary Cycles

The two candidate cycles were compared on the basis of relative costs of the variable portions of their cost makeups. The models used for cost comparison were taken from and used in accordance with GEOCOST methods of reference 8. GEOCOST models represent composites of unit costs of equipment and subsystems drawn from various sources. As such their absolute values may be questioned and must be backed up during design by vendor and supplier quotes. However, use of GEOCOST ensures a consistency in the comparison of systems in the early tradeoff period.

Table 4-3 summarizes the major cost comparison highlights of the GEOCOST analysis presented in greater detail in Appendix G. The analysis ignored the small differences in geothermal flow rates (and the associated small differences in seawater flow rates) shown in Figure 4-4, in order to isolate brine and seawater system costs. The omission discounts the cycle efficiency advantage of the single binary cycle. On the basis of the GEOCOST analysis, the single binary cycle would be the less expensive.

TABLE 4-3 GEOCOST COMPARISON OF SINGLE AND DUAL BINARY CYCLES

	SINGLE BINARY CYCLE ISOBUTANE (\$000)	DUAL BINARY CYCLE			
		WATER	AMMONIA		
			(\$000)		
EVAPORATORS	2500	1700		4490	
TURBOGENERATORS	3590	4600		1690	
CONDENSERS	730	2300		960	
PIPING AND INSULATION	2020	970		8190	
FEED PUMPS	4500	280		300	
INSTRUMENTATION AND CONTROL	900	800		1000	
BUILDING AND STRUCTURES	2420		2800		
INDIRECT EXPENSES, DESIGN FEES, AND CONTINGENCIES	6660	4260	1120	6650	
TOTAL VARIABLE COST	<u>23320</u>	14910	3320	23280	<u>41510</u>

4.3.4 Qualitative Comparison of Single and Dual Binary Cycles

The qualitative comparison of the single and dual binary cycles includes consideration of factors which might otherwise be ignored on purely thermodynamic or first cost grounds.

The single binary cycle offers major advantages in plant maintenance, and spares and logistical supply pipelines. Elimination of different power loops will, for example, lead to economies in the sharing of parts, and reduce the number of personnel used for operation and maintenance. Auxiliary systems such as lubrication, working fluid purity control, and safety will be less complex. System control should be simpler.

5. ISOBUTANE SINGLE BINARY POWER CYCLE SENSITIVITY ANALYSES

5.1 Sensitivity of Isobutane Single Binary Cycle

The cost sensitivity of the isobutane single binary cycle to the major geothermal well characteristics - temperature, draw-down, and flowrate were studied by applying cost algorithms to the performance characteristics of heat exchangers, turbines, pumps and wells as follows:

- o Production geothermal wells - \$2M/well
- o Reinjection wells - \$1M/well
- o Heat exchangers - \$40/sq.ft.
- o Turbine-generators - $\$M = 1.055 + 0.00228$ (mass flow rate of isobutane)

Other plant costs such as electrical distribution, indirect costs, and plant structure were kept constant as GEOCOST showed their variation with size or capacity to be small or directly proportional to capital costs. The seawater system and brine distribution system costs were also held constant. The design and cost of the seawater system, as discussed in Section 6, is heavily driven by fixed costs for mobilization and deployment. Likewise, the variation in brine distribution system costs due to variation in overall performance were judged to be small within the bounds of uncertainty of the above-mentioned major subsystems.

The algorithms were added to DOP and the optimization program run with system cost set as the objective function to be minimized at fixed net plant output of 12 Mwe. The starting point for all calculations was the set of system design characteristics - heat exchanger design, temperature and pressure drops, etc.- found in Section 4 to produce 12 Mwe. The results of the runs are shown in Figures 5-1, 5-2, and 5-3: they represent the minimum cost of those variables of a GEOTEC system for each set of well-head conditions.

As expected wellhead temperature has the most pronounced effect on system cost. As temperature falls, the flow rate of the geofluid must increase, increasing the number (cost) of geothermal wells and increasing the parasitic losses for brine pumping, working fluid circulation, and seawater pressure losses in the condensers.

The effect of a reduced reinjection temperature on the plant cost of the isobutane single binary cycle was examined at the nominal wellhead conditions. When the reinjection temperature falls to 80 C from 100 C, the geothermal fluid flow rate decreased by about 25%. The plant system cost only decreased by about 10%, reflecting the relative leverage that variable costs

FIGURE 5-1 SENSITIVITY OF SINGLE BINARY CYCLE
GEOTEC PLANT TO WELLHEAD TEMPERATURE

FIGURE 5-2 SENSITIVITY OF SBC GEOTEC PLANT TO WELL FLOW

FIGURE 5-3 SENSITIVITY OF SBC TO WELL DRAWDOWN

have on total system cost. The major cost saving of the GEOTEC system would be in the wells and heat exchangers.

The characteristics and subsystem design values resulting from the cost optimization of the isobutane single binary system at nominal well head conditions are shown in Table 5-1. These values were the basis for the conceptual design of the next section.

TABLE 5-1 SINGLE BINARY CYCLE GEOTEC PLANT SYSTEM DESIGN CHARACTERISTICS

GEOFLUID CONDITIONS

BRINE FLOW RATE	2,325,600 POUNDS/HR
NUMBER OF PRODUCTION WELLS	5
WELL DRAWDOWN	656 FT
BRINE LINE PRESSURE DROP	50 PSI
WELL HEAD TEMPERATURE	356°F
BRINE TEMPERATURE DROP	5°F
NUMBER OF REINJECTION WELLS	3
REINJECTION TEMPERATURE	212°F

SEAWATER CONDITIONS

TOTAL SEAWATER INTAKE FLOW	45,792,000 POUNDS/HR
SEAWATER FLOW TO GEOTEC PLANT	15,264,000 POUNDS/HR
SEAWATER INTAKE TEMPERATURE	41°F
SEAWATER OUTFALL TEMPERATURE	48°F
SEAWATER TEMPERATURE RISE THRU GEOTEC PLANT	20°F

ISOBUTANE CONDITIONS

ISOBUTANE FLOW RATE	1,972,800 POUNDS/HR
ISOBUTANE EVAPORATION TEMPERATURE	269°F
ISOBUTANE CONDENSING TEMPERATURE	76.3°F

ISOBUTANE POWER CYCLE

EVAPORATORS

NUMBER OF UNITS	2
HEAT RATE PER UNIT	1.64×10^8 BTU/HR
NUMBER OF TUBES PER UNIT	8000
LENGTH OF TUBES	28.6 FT

CONDENSERS

NUMBER OF UNITS	2
HEAT RATE PER UNIT	1.53×10^8 BTU/HR
NUMBER OF TUBES PER UNIT	8000
LENGTH OF TUBES	20.6

TURBINE-GENERATOR OUTPUT (2 UNITS)	16.8 Mwe
ISOBUTANE FEED PUMP ELECTRICAL INPUT (2 UNITS)	2.2 Mwe
GEOFLUID PUMPS ELECTRICAL INPUT	1.7 Mwe
SEAWATER PUMPS ELECTRICAL INPUT	0.7 Mwe
PLANT AUXILIARIES	0.2 Mwe
NET PLANT POWER	12.0 Mwe

6. GEOTEC SYSTEM DESIGN

6.1 Design Basis

Figure 6-1 presents the major elements of the GEOTEC plant system design for the single binary isobutane system. Included in the figure are the geothermal brine handling system, the isobutane power system subsystems, and the seawater cooling system. Other subsystems required to support plant operation such as the off-gas flare system and closed loop cooling water subsystem are shown. A more complete process flow diagram can be found in Volume 2.

The process flow diagram is based upon the previously-described system optimization, and utilizes experience gained in previous plant system designs for geothermal plants.

6.2 Power Cycle Description

6.2.1 Geothermal Brine Handling System

The geothermal brine handling system consists of the elements required to bring geothermal brine from the producing well to the power plant and then reinject spent brine back into the subsurface formation. A plot plan of the wells' and brinelines' locations is shown in Figure 6-2. Each drill pad will contain up to two wells.

Five wells, each producing 1000 gpm, are required for the 12 Mwe plant. Each well will utilize a downhole brine pump to lift the brine from the assumed well drawdown level of 656 feet, and provide 50 psi well head pressure at the reinjection wells to pump the spent brine back into the formation. The production wells were assumed to have a mean elevation about 80 feet above the reinjection wells. This additional head was included as a driver for the brine flow. Additional brine booster pumps are not required.

A 5 F drop was used for the temperature loss from the well head to the power plant. This loss in geothermal brine temperature was calculated from insulation manufacturer's data and pipe dimensions and lengths for the pipeline consistent with the calculated brine line pressure losses.

Pressure surges and severe water hammers will be absorbed by a nitrogen-charged accumulator. Brine drain pumps will be located near the reinjection wells to remove brine from the lines when the plant is down for extended servicing and there is a chance of brine freezeup in the lines.

The brine pipelines will incorporate thermal expansion loops

placed every 400 feet. Pipeline flexibility and support spacing will be in accordance with ANSI-B31.1 Power Piping Code.

6.2.2 Isobutane System

Isobutane will be evaporated at 500 psia and 270 F in two, spray-type, tube-in-shell evaporators at a rate of 986,000 pounds/hour. Spray type evaporators were chosen over pool-type boilers for the former's smaller size and lower holdup volume.

Isobutane vapor will flow through the isobutane turbines and discharge into the condensers at 110 F and 50 psia with 34 F of superheat. The vapor will be desuperheated and condensed in seawater-cooled, tube-in-shell condensers.

Isobutane condensate will drain from each condenser to vertical, multistage can-type condensate pumps, which will deliver the condensate to the spray heads of the evaporators. Condensate bypass lines will recirculate isobutane back to the condensers in order to control the liquid level in the condenser hot wells. Reflux pumps will take liquid isobutane from reservoirs at the base of each evaporator and deliver it to the condensate streams from the condenser condensate pumps. The combined streams will be delivered to the evaporators' spray heads to ensure the evaporator tubes do not dry out.

The explosion potential, lack of immediate availability, and cost of isobutane require that both liquid and vapor be recovered before maintenance is conducted. Furthermore, leakage from seals and contamination of the working fluid are likely. An isobutane loading and unloading system will be used to charge and/or replenish isobutane and to receive isobutane from the power cycle if the isobutane must be removed from the loop. The loading and unloading system will contain means for evacuating the isobutane power loop components and removing air and noncondensable gases.

The loading and unloading system will consist of vapor recovery compressors, aftercondensers, recovery and transfer pumps, water and contaminant filters, and storage tanks. The storage system will be sized to contain the entire holdup of both isobutane loops, plus makeup. The loading and unloading system will be housed in a modular 20x40 foot building adjacent to the main power building. All equipment foundations and as much equipment as possible within size and weight constraints will be pre-installed in the modular loading and unloading building prior to shipping.

6.2.3 GEOTEC Power Plant

The GEOTEC power plant will be located on the northeast shore of Andrew Lake near the junction of Pollitt and Davis roads. The power plant will be connected to the remainder of the GEOTEC plant system by the geothermal fluid gathering system,

FIGURE 6-1 MAJOR ELEMENTS OF GEOTEC SYSTEM

FIGURE 6-2. GEOTEC BRINE LINES

geothermal reinjection system, seawater system, and the electrical grid of the Station.

The component subsystems will be modularized to a degree which recognizes the limitations of logistics of shipping and construction at Adak. To this end, particular attention was paid to designs which could be palletized and easily assembled on site. The following is a description of the building and equipment within the boundaries of the power plant site. The plant's layout can be seen in the large drawing in Volume 2; a reduced form of that drawing can be found in Figure 6-3.

Power Plant Building:

An insulated, structural steel building with a metal roof was selected over alternatives such as air-inflated and clam-shell types. The building will house all power generating equipment, spare parts storage, plant control room, offices, laydown areas, and truck loading area.

Power Generating System:

The power generating system consists of two mirror image, 8.36 Mwe isobutane turbine-generator sets, complete with their accessories and auxiliaries.

Two units were chosen to service the load instead of a single or a larger number of units. The choice was made after consideration of the military mission-critical load (6 Mwe for 24 hours), and the availability of two existing 4 Mwe diesel-generator units which could be brought on line in the event one of the isobutane units were down.

Several turbine-generator vendors were solicited for design, performance, and cost data, in keeping with the system defined in Section 5. Elliot Co., Mafi-Trench, Mitsubishi, Rotoflow, and Toshiba submitted technically acceptable proposals. The design presented by Mafi-Trench was used in the power plant layout because its efficiency was comparable to the others, was most compact, and was cost competitive with the other turbine quotations. A more complete description of the Mafi-Trench unit can be found in Appendix H.

Evaporators and Condensers:

Tube-in-shell heat exchangers were selected for both the isobutane evaporators and condensers. Two identical evaporators will be used for each turbine-generator set. The split evaporator approach was taken for reasons of shipping weight restrictions as well as the efficient use of space for tube maintenance at the site. Because of a dockside lifting crane weight restriction of 30 tons, the evaporators will be shipped with the waterboxes and

tubesheets disassembled from the shells.

Tubes, tube sheets, and water boxes will be of 316L stainless steel, proven in several geothermal applications. The shells, internal baffles and tube supports will be pressure vessel grade carbon steel.

A single condenser will serve each turbine-generator. The condensers will have side entries for turbine exhaust, and will include hot well sumps to feed the condensate pumps. The condensers will share a common tube laydown area for tube removal and installation.

The condenser shell material will be the same as the evaporators. Titanium was selected for the tubes and titanium-clad carbon steel will be used for the tubesheets. Titanium was chosen not only for its corrosion resistance, but its anti-fouling tendency. The titanium tubes will be welded to the tube sheets.

Isobutane Pumps:

Liquid isobutane will be circulated through the power loops by high head, canned multi-stage vertical centrifugal pumps. Standard pump materials will be used, and the drive motors will be explosion proof.

Responses to requests for isobutane pump quotations were received from Peerless Pump and Peabody-Floway. The Peerless design was used for the design layout and cost estimation.

Instrumentation and Control:

Instrumentation and control of the GEOTEC plant will be similar to that which is used in contemporary manned binary geothermal power plants. The control system will have the following features:

- o control will be self-contained and self-adjusting,
- o utilize alarms for operator attention and will initiate shutdown if there is no operator response,
- o all start up controls will be in the control room,
- o local interruption controls will be located for immediate operator response at key points in the plant, and
- o distant facilities such as brine and seawater pumps will be monitored from the plant control room with periodic inspection in the field.

Instrumentation and control signals will be carried by

either hard wire or radio. Final determination will be made during preliminary design.

Start up and shut down will be manual. A single operator will sequentially start up electrical auxiliaries, mechanical subsystems, seawater pumps, geothermal brine pumps, isobutane feedpumps, and finally the turbine-generators. The single operator philosophy is chosen to minimize manning needs. Start up power will be supplied from a back-up diesel-generator backfeeding through the power grid.

To shut down, the start up sequence will be reversed except one or more brine pumps will continue to operate to prevent silica precipitation. For long periods of shut down, the brine lines will be pumped out, and the wells shut-in.

Cooling Water System:

Seawater will be used in the plant for condensing isobutane and as a heat sink for auxiliary cooling. Fresh water auxiliary cooling is provided by heat exchanging closed loop fresh cooling water with the effluent of the condensers. Fresh water cooling was selected for cooling of the turbine-generator lubrication loop and cooling of miscellaneous loads such as air compressors, isobutane loading and unloading compressors, and aftercoolers so as to reduce biofouling and permit use of lower cost standard materials of construction.

Flare System:

The flare system will be used to eliminate flammable gases vented from the power loop which are not recovered in the isobutane loading and unloading subsystem. The flare system must be sized according to environmental and combustibility factors such as burning rates. At this point there is insufficient information on which to base the flare system design; however, among the factors to be considered in preliminary design are;

- o vent rates of gases,
- o ability to flare in the high winds of Adak, and
- o flaring noise, thermal radiation, and local levels of combustion products.

Gas Purge:

Nitrogen will be used for purging all equipment containing isobutane and for surge suppression in the brine production system accumulators. Due to the large amount of nitrogen which will be required for purging during maintenance, a liquid nitrogen storage, vaporization and distribution system will be

required. The nitrogen system will be housed in the isobutane loading and unloading building.

Heating, Ventilation, and Air Conditioning:

Heating and ventilation will be required in all areas within the power plant proper and within the loading and unloading building. Air conditioning will be installed in the control room of the plant for use during the summer months, and to control humidity in sensitive plant areas. The switchgear and motor control center will require ventilation based upon limiting the rise in room ambient temperature to manufacturers' specifications without additional cooling.

The plant control room, offices, and switchgear/MCC rooms will be positively pressurized to prevent isobutane intrusion. The plant's operating floor and auxiliary equipment and storage areas will have exhaust fans for temperature and ventilation control. Additionally, rapid response fans will be provided to react to large isobutane leakages.

Fire Protection System:

Automatic wet pipe sprinkler systems will be installed throughout the power plant's operating area and adjacent buildings. Fire hose headers will be located around building perimeters. Carbon dioxide extinguisher systems will be installed around the turbine-generators; halon systems will be used in the control and switchgear/MCC rooms.

The fire protection water supply pumps will be electrically-driven with diesel-driven pump backup, and will be located in an adjacent fire pump building. The pump house will be shipped pre-assembled. Water for the sprinkler system will be fed from a storage tank also shipped pre-assembled.

Other Miscellaneous Power Plant Systems:

- o compressed air for instrumentation, valve operators, and air-operated tools,
- o sump pumps for spills and leakage hosedown and clean up and,
- o a 30 ton bridge crane.

Potable water and waste water discharge hookups will be made to the existing nearby RDF facility.

6.3 Seawater System Design

6.3.1 Seawater Pipeline Design Bases

The rationale for the seawater intake and outfall pipelines into Andrew Bay was described in Section 3. The oceanographic and geophysical data supporting the design of the pipelines was limited to the exhibits of the Statement of Work and information from informal discussions with NWC and CEL project personnel. To this set of data the following assumptions had to be assigned:

- o There are no measureable thermal gradients in the bay and therefore there is no reason to set the intake or outfall depths on the basis of reaching a more attractive thermal sink or discharge layer.
- o There is no basis for setting the horizontal separation distance between the intake and outfall due to prevailing currents which might cause thermal short circuiting.

Additional design constraints were set by the Alaskan State Board of Water Resources. This information was provided well into the study and could not be incorporated in time to affect the design process.

- o No discharge temperature shall be greater than 25 C above ambient water temperature. (The team had arbitrarily selected 3.9 C)
- o Pipelines must lie at least 10 feet below the mean water level.
- o Outfalls must be at least 400 feet from the shoreline.

In terms of performance, the pipeline must be designed to carry about 100,000 gpm of seawater at low pressure loss. The pipeline must also withstand 100 year storm conditions, a criteria established by the design team.

6.3.2 Offshore Seawater Pipeline Design

Appendix I presents a conceptual design study report for the pipelines. In that report, the design wave conditions for Andrew Bay are developed using a hindcast analysis of data for the Navarin Basin in the Bering Sea. Based upon that data the 100 year wave is expected to be 40 feet in height.

The hindcast analysis was also used to predict the height of the maximum wave expected during the probable construction period, the summer months. This wave height, 10 feet, influences the design of the pipeline deployment process and construction site.

The above data lead to the following design criteria:

- o The seawater intake and outfall structures should be located outside the 100-year surf zone.
- o The seawater intake structure should be in at least 50 feet of water to prevent air entrainment due to breaking waves.
- o The pipelines should be trenched and buried to resist wave and current-induced forces.
- o The approach angle of waves will be less than 45 degrees which will tend to reduce the wave-induced loads.

The report in Appendix I addresses 3 foot diameter pipelines. This size was selected early in the study before the concepts for the seawater system were developed, and the Board of Water Resources seawater pipeline requirements were received. The diameter was raised to 6 feet in order to limit the offshore pipeline velocity to 6 feet/second, consistent with a concept in which the full seawater flow would be routed to the GEOTEC plant, and the rise in seawater temperature would be limited to 7 F. The change in material costs of the pipes, corrosion, and weighting subsystems scale with pipe diameter: installation costs are fixed by mobilization/demobilization costs. Offshore pipeline costs have been revised in the GEOTEC Plant System Cost Estimate, Section 7, from those quoted in Appendix I.

The report of Appendix I describes the bottom pull technique for pipeline deployment, a technique commonly and successfully used in Arctic pipelines. The report also defines the mobilization needs and the onshore pipe makeup and construction facilities. Figures 6-4 and 6-5 taken from that report highlight the facilities and assembly and installation techniques.

Table 6-1 summarizes the design features of the intake and outfall pipelines. Figure 6-6 indicates the proposed route and trenching cross sections of the intake pipeline. The outfall pipeline is assumed to lie in the sheet-piled trench with the intake pipe to a distance of 800 feet offshore. At that point, the outfall line would separate from the intake line and run out to a depth of 50 feet in such a way as to minimize the thermal short circuiting potential. An outfall pipeline length of 2500 feet, identical to the intake line, is assumed.

6.3.3 Land-side Seawater System

The land-side seawater system consists of a pump station on the shore of Andrew Bay at the southern side of Andrew Volcano, and a seawater pipeline along Davis Road which takes cold water to the GEOTEC plant and returns heated water back to the pump station.

The pump station consists of concrete seawater connections

FIGURE 6-4 PIPE MAKE UP FACILITY

FIGURE 6-5 PIPE PULLING OPERATION

TABLE 6-1 DESIGN FEATURES OF OFFSHORE SEAWATER PIPELINE

INTAKE PIPELINE	OUTFALL PIPELINE
<ul style="list-style-type: none">● 6 FT PIPE DIAMETER (<7 FPS)● 2500 FT SHORE TO INTAKE● 50 FT DEPTH INTAKE● TRENCHED AND BURIED● SHEET PILE 800 FT THROUGH SURF ZONE● STEEL PIPE BALLASTED WITH CONCRETE COATING● COATINGS AND SACRIFICIAL ANODES FOR CORROSION PROTECTION	<ul style="list-style-type: none">● 6 FT PIPE DIAMETER● 2500 FT SHORE TO OUTLET● 50 FT DEPTH OUTLET● TRENCHED AND BURIED● SHEET PILE THROUGH SURF ZONE (SHARED WITH INTAKE LINE)● STEEL PIPE BALLASTED WITH CONCRETE COATING● DIFFUSER TYPE OR PREPARED TRENCH OUTLET

FIGURE 6-6

to the intake and outfall pipes and concrete pump bays. The bays have settling areas in which particulate matter can settle out, and trash racks and traveling screens to protect the pumps and heat exchangers of the plant.

Two concepts for pumping the seawater to the plant were examined. In each case the maximum allowable rise in seawater temperature was set at 7 F. The first concept employed a pumping system which circulated all the cooling seawater to the plant and back to sea. This concept, while the simplest, requires the maximum pumping power to move the water nearly 2.4 miles (1.2 miles each way). The calculations in Appendix F show the parasitic power for seawater pumps flowing approximately 100,000 gpm - the amount required to restrict the rise in the seawater loop temperature to 7 F - to be 1.8 Mwe.

The second concept involves shunting a portion of the cold seawater across the pump station to the heated return line from the GEOTEC plant. In this concept a smaller amount of water is sent to the plant and has a larger temperature rise across the condensers of the plant. In order to have the same overall temperature rise in the discharge flow to the sea, the shunted water is mixed with the return cooling it for disposal. Keeping the same temperature rise as in the first case, only 1/3 the seawater is pumped to and from the GEOTEC plant, reducing the parasitic load to about 1/3 the original value. This concept was selected for the final design. A plan view of the pump station is shown in Figure 6-7.

The main circulating pumps will have a total head capacity of 64 feet at a flow rate of 33,000 gpm. They and the smaller shunt pumps will receive their control, power, and remote status sensing from the GEOTEC plant by cables strung along the seawater pipeline.

A simple shelter will be erected over the pumps, screens and controls area. The shelter will provide limited protection from rain, snow, and winds. Means for periodic dredging of the pump forebay settling area may be provided as necessary. It is expected that some of the construction facilities required for the seaward portions of the seawater pipeline may also be used in the construction of the pump station.

Once it leaves the pump station the seawater flows through a 4 foot diameter, reinforced plastic pipeline. The pipeline is buried in a prepared trench as indicated in Figure 6-8. Both feed and return pipelines are in a common trench. The trench will also house the power feeds for the pump station pumps, as well as the instrumentation and control lines for monitoring and controlling the pump station from the GEOTEC plant.

The reinforced plastic pipeline will be assembled using bell and socket connections to minimize on-site installation and reduce labor times and exposure needed for the pipe connections and setup.

- (S) - SHUNT PUMPS: 2EA @ 31,800 GPM
 (F) - FEED PUMPS: 3EA (1EA STANDBY) @ 15,150 GPM

Title		PUMP STATION ONSHORE OF ANDREW BAY		Drawing	
Drawn by		HDC		Signed by	
Scale		Date		Revision	
		FEB 1, 1984		N6274-83-C-5307	
GEOTEC ENGINEERING/CONCEPT STUDY					
TRW Energy Development Group					
Gibbs & Hill		Woodward-Clyd Consultants		Hawaiian Dredging & Construction	
				RJ Brown & Associates	

FIGURE 6-7

Title DETAIL OF 4 FT ID FR PIPELINE		Drawing
Drawn by HDC	Signed by	Revision
Scale	Date FEB 2 1984	N6274-83-C-6307
GEOTEC ENGINEERING/CONCEPT STUDY TRW Energy Development Group		
Gibbs & Hill	Woodward-Clyde Consultants	Hawaiian Dredging & Construction
		RJ Brown & Associates

FIGURE 6-8

6.4 GEOTEC Electric Power System

The GEOTEC electric power system consists of those elements required to deliver power to the Naval Station grid and to service the needs of the GEOTEC system itself. The system consists of the bulk generation system, switchyard, auxiliary power, and DC power. The electric power conditioning and distribution system which sends conditioned power from the plant are shown schematically in Figure 6-9. Figure 6-10 shows the routes of the power lines serving the island and the outlying portions of the GEOTEC system. Table 6-2 shows the apportionment of plant gross power output.

Bulk electric power will be generated by two, 6.9 KV turbine-driven generators, assembled on skids as single units for ease of installation. The generators will be equipped with automatic voltage regulators and circuit breakers. Within the switchgear room and motor control center of the plant the power will be split to service the various loads.

The distribution plan for the plant's output was based upon load center and transmission line capacity data supplied by the Navy. Two (2) Mwe will be delivered at 6.9 KV over 1.25 mile long, above-ground lines to the PRD east of the plant. Auxiliary power for the seawater pumps and geothermal brine pumps will be sent at 6.9 KV to the respective loads. The remaining 10 Mwe will be sent to diesel-electric power plant #5 over 13.8 KV above-ground lines. All main power lines will be supported on 2-pole wood "H" frame structures. Disconnects, circuit breakers, and 6.9 to 13.8 KV transformers will be installed in the switchyard.

Because of the large motors of the seawater and brine pumps, located remote from the plant, the auxiliary voltage was set at 6.9 KV. The 6.9 KV auxiliary power will be fed from 6.9 KV switchgear.

The plant accessory systems will be fed from a 6.9 KV to 480 V stepdown transformer within the switchgear and motor control center room. During those periods when the GEOTEC plant is down for service, the plant's auxiliary loads will be backfed from D-E plant #5 through the main power transformer. This power feed will also serve during plant startup and shut down.

A 125 VDC distribution system will be installed to furnish primary power for circuit breakers, instrumentation and control, and backup for critical loads. Station-type batteries, continually charged from the plant's AC system will be provided.

FIGURE 6-9 ELECTRIC POWER DISTRIBUTION AND TRANSMISSION SCHEME

FIGURE 6-10

Title		GEOTEC POWER LINES		Drawing	
Drawn by		GIBBS & HILL		Signed by	
Scale		Date		Revision	
				N8274-03-C-4307	
GEOTEC ENGINEERING/CONCEPT STUDY					
TRW Energy Development Group					
Gibbs & Hill		Woodward-Clyde Consultants		Howell Dredging & Construction	
				RJ Brown & Associates	

TABLE 6-2 GEOTEC ELECTRIC PLANT POWER BALANCE

GROSS GENERATOR POWER OUTPUT	2X 8360 kW	= 16720 kW	
NET POWER TO ISLAND		12000 kW	
			<hr/>
POWER AVAILABLE FOR POWER PLANT AUXILIARIES		4720 kW	
IN-PLANT AUXILIARIES:			
• CONDENSATE PUMPS	2 X 1237	= 2474 BHP	
• REFLUX PUMPS	2 X 1.9	= 4 BHP	
• AUX CW PUMPS		= 51 BHP	
• LUBE OIL SYSTEM	2 X 10	= 20 BHP	
• FIRE PUMP		= 140 BHP	
BRINE DISTRIBUTION SYSTEMS:			
• DOWNHOLE WELL PUMPS	5 X 358	= 1790 BHP	
SEAWATER DISTRIBUTION SYSTEM:			
• SEAWATER DISTRIBUTION PUMPS	2 X 365	= 730 BHP	
• SEAWATER DILUTION PUMPS	2 X 403	= 806 BHP	
SUBTOTAL		6015 BHP	4490 kW
			<hr/>
POWER AVAILABLE FOR BALANCE-OF-PLANT			230 kW

7. GEOTEC PLANT SYSTEM COST ESTIMATE

7.1 Scope of GEOTEC Plant System Cost Estimate

The GEOTEC plant system cost estimate includes the design, construction, installation and checkout costs incurred in bringing the GEOTEC plant on-line within the schedule of Section 9. The cost of the system is composed of the following elements;

- o geothermal production and reinjection wells,
- o geothermal brine gathering and disposal systems,
- o seawater systems, and
- o power plant.

While GEOCOST was used in the earlier DOP modeling analyses the cost estimate for the selected GEOTEC concept was based upon the specific design described in the previous section, and therefore includes design- and site-specific forcing functions.

The cost estimation of major subsystems was performed by team members knowledgeable in specific areas. Each member used cost estimating techniques particular to their firm's procedures. Rather than forcing a common cost estimation format on them, each was left to use their own method. The results of their cost estimate studies can be found in Appendix J.

A summary of the plant system cost breakdown is shown in Table 7-1. All costs are reflected to Adak and assume the schedule of Section 9. The costs for geothermal and reinjection wells were estimated as multiples of typical CONUS geothermal well costs.

Table 7-2 presents a cost estimate for the GEOTEC system, assuming that the seawater system is designed as a once-through system, without the shunt pumps, and allowing the seawater temperature to be 20 F above ambient at the discharge. The major savings are in the reduced size of the offshore seawater pipeline, elimination of the shunt pump, and reduction in the pump station size,

TABLE 7-1
GEOTEC PLANT COST SUMMARY - 7 F SEAWATER RISE
(\$000)

POWER PLANT

EVAPORATORS	3940
TURBINE-GENERATORS	2740
CONDENSERS	1450
CONDENSATE PUMPS	1530
REFLUX PUMPS	100
PIPING AND INSULATION	3080
INSTUMENTATION AND CONTROL	1560
PLANT AUXILIARIES	2380
ELECTRICAL SUPPORT AND SWITCHGEAR	2230
PLANT BUILDING AND SITE PREPARATION	6160
ELECTRIC POWER DISTRIBUTION LINES	4550
TOTAL POWER PLANT	29,720

GEOHERMAL SYSTEM

PRODUCTION WELLS	10,000
REINJECTION WELLS	3000
BRINE PUMPS	5080
BRINE PIPELINES	6150
TOTAL GEOHERMAL SYSTEM	24,230

SEAWATER SYSTEM

OFFSHORE PIPELINES	9450
ONSHORE PUMP STATION	7140
SEAWATER PUMPS	390
LAND PIPELINES	1810
TOTAL SEAWATER SYSTEM	18,790

INDIRECT FIELD EXPENSES	5530
BUILDING AND ENVIRONMENTAL PERMITS	1500
ENGINEERING AND DESIGN	5600
CONTRACTORS FEES AND CONTINGENCIES	9260
TOTAL OTHER EXPENSES	21,890

GEOTEC PLANT COST	94,630
--------------------------	---------------

TABLE 7-2
 GEOTEC PLANT COST SUMMARY - 20 F SEAWATER RISE
 (\$000)

POWER PLANT			
EVAPORATORS			
TURBINE-GENERATORS			
CONDENSERS			
CONDENSATE PUMPS			
REFLUX PUMPS			
PIPING AND INSULATION			
INSTUMENTATION AND CONTROL			
PLANT AUXILIARIES			
ELECTRICAL SUPPORT AND SWITCHGEAR			
PLANT BUILDING AND SITE PREPARATION			
ELECTRIC POWER DISTRIBUTION LINES			
TOTAL POWER PLANT			29720
GEOHERMAL SYSTEM			
PRODUCTION WELLS			
REINJECTION WELLS			
BRINE PUMPS			
BRINE PIPELINES			
TOTAL GEOHERMAL SYSTEM			24230
SEAWATER SYSTEM			
OFFSHORE PIPELINES	7680		
ONSHORE PUMP STATION	6180		
SEAWATER PUMPS	180		
LAND PIPELINES	1810		
TOTAL SEAWATER SYSTEM			15850
INDIRECT FIELD EXPENSES	5310		
BUILDING AND ENVIRONMENTAL PERMITS	1500		
ENGINEERING AND DESIGN	5370		
CONTRACTORS FEES AND CONTINGENCIES	8890		
TOTAL OTHER EXPENSES			21070
GEOTEC PLANT COST			90870

8. OPERATION AND MAINTENANCE PLANNING

8.1 Objective of Operating and Maintenance Planning

Power plant operation and maintenance planning addresses the number and qualifications of personnel to manage, operate and service the power plant, and a scheduled maintenance program which includes provisions for spare parts, and the logistical and service support for the plant.

8.2 Manpower Requirements

The categories of labor are required to operate and maintain the GEOTEC plant:

- o plant manager - The plant manager has overall responsibility for the running of the plant, supervision of plant operators and maintenance personnel, and the coordination of work which might be done by outside contractors.

- o operator - Plant operators are responsible for shift operations, reporting and recording of critical data defining the performance of the plant, inspection, and coordination with maintenance personnel.

- o maintenance - Maintenance personnel are responsible for inspection and maintenance of plant system equipment and establishment of spare parts inventory.

Two manning plans are possible with final selection to be made based on the owner/operator basis for the plant, and availability of qualified personnel. The first scenario assumes all plant personnel are either resident on Adak or are willing to relocate. The second scenario assumes only the plant manager is an Adak resident with all other plant personnel rotated from other points in Alaska or the continental U.S. In the latter case the personnel would work on a continuous basis for 28 days before rotation. This procedure was adopted for other Arctic projects such as the North Slope drilling project.

The two personnel schedules are shown in Figures 8-1 and 8-2. The first plan is preferred because of the lower annual manhours, elimination of rotation costs, and availability of all plant personnel in emergencies.

8.3 Maintenance

The availability goal of the GEOTEC plant is 90%. The mission-critical load of the plant is 6 Mwe, which must be supported for a minimum of 24 hours. According to NWC and CEL, the peak load of 12 Mwe occurs in the winter months and drops off in the summer. The yearly averaged load is 10 Mwe.

		M	T	W	TH	F	S	S	M	T	W	TH	F
DAY	MGR	→	→	→	→	→			→	→	→	→	→
DAY	AST MGR + HLPR			→	→	→	→	→			→	→	→
DAY	PLT OPTR	→	→	→	→	→	→	→	→	→	→	→	→
SWING	PLT OPTR			→	→	→	→				→	→	→
SWING	PLT OPTR	→	→			→	→	→	→	→			→
GRAVE- YARD	PLT OPTR	→	→	→	→	→			→	→	→	→	→
GRAVE- YARD	PLT OPTR	→	→	→			→	→	→	→	→		

3-8 HR SHIFTS/DAY
1280 MAN HOURS/28 DAYS

FIGURE 8-1 ALL RESIDENT PLANT STAFFING SCENARIO

		M	T	W	TH	F	S	S	M	T	W	TH	F	S	S	
DAY	MGR	→						→								
DAY	MAINT (AST MGR) + HLPR	→														
DAY	PLANT OPTR	→														
NIGHT	PLANT OPTR	→														
NIGHT	PLANT OPTR AST	→														

1-8 HR SHIFT/DAY FOR MANAGER

2-12 HR SHIFTS/DAY FOR ALL OTHERS (28 DAY ROTATION)

1504 MAN HOURS/28 DAYS

FIGURE 8-2 OFF-ISLAND STAFFING SCENARIO

The planned maintenance schedule assume the existing two, 4 Mwe diesel-generators will be placed on standby service and will be called upon to provide mission-critical loads in emergencies and to pick up a portion of the load during planned outages when one of the 6 Mwe isobutane power loops is down. Each of the two loops will be shut down for two weeks to perform scheduled maintenance during August and September. During these periods of reduced geofluid flow, brine distribution and seawater systems will also have their scheduled maintenance. Table 8-1 presents the type and interval of planned maintenance activities.

Due to the remoteness of the site adequate spares must be stored at the plant or in a centralized storage site on Adak. A list of the type and number of major spare parts is shown in Table 8-2.

TABLE 8-1
INSPECTION AND MAINTENANCE CYCLES

<u>ITEM</u>	<u>I AND M FREQUENCY</u>		
	Less Than 1 Year	1 Year	2 Years
Turbine-Generator	S		X
Lube Oil Skid	S	X	
Evaporator		X	
Condenser		X	
SW/Aux CW HX		X	
Brine Pumps	W	X	
Brine Valves		X	
Seawater Pumps	W		X
Aux Cooling Water Pumps	S		X
Seawater Valves	W		
Condensate Pumps	S		X
Isobutane Valves and Piping			X
Compressed Air Skid	W		X
Flare System	M		
HVAC	M	X	
Fire Projection	M		
Crane	M		
Transformers and Switchgear	W	X	

S = Visual inspection each shift, minor maintenance as required
 W = Weekly inspection, add/replace lubricants, coolants, etc. as required
 M = Monthly inspection, add/replace lubricants, coolants, etc. required and perform functional test
 X = Shutdown and overhaul

TABLE 8-2 GEOTEC SPARES REQUIREMENTS

TURBINE GLAND SEAL PACKING	2 SETS
TURBINE-GENERATOR JOURNAL BEARINGS	
#1 BEARING (TURBINE)	2 SETS
#2 BEARING (GENERATOR)	2 SETS
#3 BEARING (GENERATOR)	2 SETS
THRUST BEARING PADS	1 SET
VALVES	
MAIN STOP VALVE (MSV)	1 SET
GOVERNING VALVE (GV)	1 SET
TEFLON RING OF MSV AND GV	1 SET EA.
GASKET O-RING FOR GOVERNING SYSTEM	8 SETS
VALVES FOR OIL AND DRAIN LINE	2 SETS
BEARINGS FOR EACH OIL PUMP	2 SETS
OIL FILTER	4 SETS
BOLTS AND NUTS	EACH SIZE 30%

TABLE 8-2 (CONT)

PUMPS:

IMPELLER

ONE SPARE FOR
EACH TYPE OF
PUMP

MECHANICAL SEALS

2 SETS EA. PUMP

SHAFT BEARINGS

1 SET EA. PUMP

WEAR RINGS & TRIM

1 SET EA. PUMP

VALVES:

SEALS AND TRIM

2 SETS EA. TYPE

GENERATOR:

BEARING (2 PCS)

1 SET

PACKING (FOR ONE GEN SET)

1 SET

SILICON DIODE

4 PCS

FUSE

2 PCS

AUX. MOTORS:

CARBON BUSHES

2 SETS

BEARINGS

1 SET EA. MOTOR

LOW VOLTAGE SWITCHGEAR

1 SET

GENERATOR PANELS

TURBINE SUPERVISORY INSTRUMENTATION

9. GEOTEC PLANT SYSTEM CONSTRUCTION AND DEPLOYMENT PLANNING

9.1 Project Schedule

A preliminary schedule for the design, construction and checkout of the system can be found in Figure 9-1. The schedule assumes that barge operations take place during 5 months of the year, and that well drilling, construction of the seawater pipelines, and other major civil work will be curtailed during the winter months. According to the schedule, first turbine roll is about 3 1/3 years after contract go-ahead.

9.2 Long Lead Items

The installation schedule of Figure 9-1 assumes the timely delivery and shipment of key power system elements to Adak. Table 9-1 summarizes the major long lead items and their estimated time from receipt of order to delivery in Seattle, Washington, the assumed point of marshalling and barge loading for Adak.

FIGURE 9-1 ADAK GEOTEC PLANT PROJECT SCHEDULE

TABLE 9-1 LONG LEAD ITEMS

ITEM	MONTHS TO SEATTLE
TURBINE-GENERATOR LUBE OIL SKID	18
EVAPORATOR	9
CONDENSER	9
SW/AUX CW HEAT EXCHANGER	4
BRINE PUMPS	12
OFF SHORE PIPE	4
SEA WATER PUMPS	12
ONSHORE FR PIPE	6
AUX COOLING WATER PUMPS	4
CONDENSATE PUMPS	6
COMPRESSED AIR SKID	4
FLARE SYSTEM	12
HVAC	6
FIRE PROTECTION SYSTEM	6
CRANE	12
MAIN TRANSFORMER	12
AUX TRANSFORMER	9
SWITCHGEAR	6
PLANT PIPING VALVES AND SUPPORTS	6-9
BRINE PIPING AND VALVES	6

10. RECOMMENDATIONS

The following are the recommended actions to continue the development of GEOTEC power on Adak:

1. An exploratory drilling program should be instituted to define the true nature of the geothermal resource at the Naval Station. This program should include flow production testing, injectivity determination, and evaluation of geofluid properties.
2. An oceanographic program should be carried out to define the bathymetry, geotechnical, and ocean wave and current environment of Andrew Bay and Sitkin Sound.
3. The environmental permitting and licensing requirements for the Adak project should be defined.
4. In view of the leverage that a more efficient single binary cycle could have on plant economics, effort should be directed at understanding the cost and time-framework for development of megawatt size toluene Rankine turbomachinery.
5. Owner/operator scenarios should be explored which will provide attractive returns to private investors. These scenarios should include estimates of the value of purchased electricity to the Navy, tax credits allowed to investors, availability of federal loan guarantee programs, and methods of private operation of an energy facility on federal property.

REFERENCES

1. Dugger, G.L., Perini, L.L., and Richards, D., "Hybrid Geothermal-Ocean Thermal Energy Conversion (GEOTEC) Power Plant Analyses and Cost Estimates", paper no. AEO-82-114, 5th Miami Conference on Alternative Energy Sources, Miami Beach, Fla., December 1982
2. Dugger, G.L., Perini, L.L., Richards, D., Whelan, J.A., and Ritzcova, "Geothermal-Enhanced OTEC (GEOTEC) Resources and Plant Performance Estimates", Oceans '82 MTS-IEEE Conference and Exposition, Washington, D.C., September 1982
3. Bruce, J.L., "Economic Feasibility Study of the Geothermal Project for the Naval Station Adak, Alaska", Naval Weapons Center Technical Memorandum 3750, China Lake, Ca., January 1979
4. Perini, L.L., Richards, D. and Dugger, G.L., "GEOTEC Plant Performance Using Steam/Ammonia Dual-Binary Cycle", Quarterly Report on Ocean Energy Systems, Johns Hopkins University, Applied Physics Laboratory Report no. JHL/APL OQR/83-1, January-March 1983, page 9
5. Chemistry and Geothermal Systems, Ellis, J.A. and Mahon, W.A.J., Academic Press, New York, N.Y., 1977
6. Miller, D.R., "Rankine Cycle Working Fluids for Solar-to-Electrical Energy Conversion", Monsanto Corporation Report no. UC-13, MRC-SL-399, under Contract no. 58-5556, Sandia Laboratories, January 1974
7. Perini, L.L., and Dugger, G.L., "GEOTEC Plant Performance and Cost Estimates Using Binary Cycles", Quarterly Report on Ocean Thermal Energy Conversion, Johns Hopkins University Applied Physics Laboratory, Auhust-December 1983 (Draft)
8. Schulte, S.C., "Capital Cost Models for Geothermal Power Plant and Fluid Transmission Systems", Battelle Pacific Northwest Laboratory Report no. PNL-2307, UC-66, September 1977