MARTIN MARIETTA

**ENVIRONMENTAL
RESTORATION
PROGRAM**

**Functional Requirements of the
Borrow Area and Haul Route for the
Waste Area Grouping Projects at
Oak Ridge National Laboratory,
Oak Ridge, Tennessee**

MANAGED BY
MARTIN MARIETTA ENERGY SYSTEMS, INC.
FOR THE UNITED STATES
DEPARTMENT OF ENERGY

UCN-17560 (6 7-91)

ENERGY SYSTEMS

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Gilbert/Commonwealth, Inc.
Knoxville, Tennessee

contributed to the preparation of this document and should not be considered an eligible contractor for its review.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from 615-576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

Environmental Restoration Division
ORNL Environmental Restoration Program

**Functional Requirements of the Borrow Area and Haul Route
for Waste Area Grouping Projects at Oak Ridge
National Laboratory, Oak Ridge, Tennessee**

Date Issued—September 1992

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Prepared by
Engineering Division
Martin Marietta Energy Systems, Inc.

Prepared for
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
under budget and reporting code EW 20

OAK RIDGE NATIONAL LABORATORY
Oak Ridge, Tennessee 37831-6285
managed by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U.S. DEPARTMENT OF ENERGY
under contract DE-AC05-84OR21400

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

APPROVALS

Functional Requirements of the Borrow Area and Haul Route for the
Waste Area Grouping Projects at Oak Ridge National Laboratory,
Oak Ridge, Tennessee
(ORNL/ER-85)

D. G. Miller
D. G. Miller (Preparer)

4-15-92

Date

D. L. Garrett
D. L. Garrett (Reviewer)

4/15/92

Date

A. G. Oaks
A. G. Oaks (Reviewer)

4/24/92

Date

M. W. Kohring
M. W. Kohring (Reviewer)

5-11-92

Date

R. L. Mlekodaj
R. L. Mlekodaj (Reviewer)

5/6/92

Date

D. L. Kirby
D. L. Kirby (Reviewer)

5-4-92

Date

F. C. Kornegay
F. C. Kornegay (Reviewer)

5/11/92

Date

T. F. Scanlan
T. F. Scanlan (Reviewer)

5/12/92

Date

M. A. Woody
M. A. Woody (Reviewer)

5/13/92

Date

S. D. Van Hoesen
S. D. Van Hoesen

5/14/92

Date

S. B. Garland II
S. B. Garland II

5/14/92

Date

CONTENTS

EXECUTIVE SUMMARY	v
1. INTRODUCTION AND PURPOSE	1
1.1 BACKGROUND	1
1.2 PURPOSE	1
2. PROJECT DEFINITION	2
3. MISSION	3
4. REQUIREMENTS AND SPECIAL ISSUES	5
4.1 REQUIREMENTS AND SPECIAL CONSTRAINTS	5
4.1.1 Overall Requirements	5
4.1.2 Borrow Area Requirements	5
4.1.3 Haul Route Requirements	5
4.2 UNCERTAINTIES	6
4.3 INTERFACES AND INTERFACE REQUIREMENTS	6
4.4 SPECIAL ANALYSES	7
4.5 HUMAN FACTORS	7
4.6 MAINTENANCE ISSUES	7
4.7 CRITICAL SYSTEMS	7
4.8 TESTING REQUIREMENTS	7
5. CONFIGURATION CONTROL PLAN	9

EXECUTIVE SUMMARY

This report describes the mission and functional requirements for the development of a borrow area and the associated haul route to support closure and/or remediation of Waste Area Grouping (WAG) 6 and other WAGs at Oak Ridge National Laboratory. This document specifies the basic functional requirements that must be met by the borrow area and haul route developed to produce low-permeability soil for the covers or caps at WAG 6.

1. INTRODUCTION AND PURPOSE

1.1 BACKGROUND

In 1969 Oak Ridge National Laboratory (ORNL) began placing solid waste in Solid Waste Storage Area (SWSA) 6. The waste included radioactive, suspect radioactive, and hazardous waste materials. SWSA 6 has now been incorporated into Waste Area Grouping (WAG) 6, which includes the nearby Emergency Waste Basin and Explosives Detonation Trench.

WAG 6 is being remediated under the Comprehensive Environmental Response, Compensation, and Liability Act. It is likely that the remediation method used will employ the diversion of near-surface water and the placement of multilayered, low-permeability closure caps. The covers or caps will consist of a minimum of 24 in. of low-permeability soil, a synthetic liner, a geotextile drainage layer, a filter fabric, and 18 in. of soil with a vegetative cover.

1.2 PURPOSE

The purpose of this project is to develop areas where suitable low-permeability soil can be obtained for use in the remediation of WAG 6 (350,000 yd³) and in all anticipated WAG remediation at ORNL (2 million yd³). The associated best haul route will need to be developed in order that the low-permeability soil may be moved to a laydown area or to WAG 6. Development includes exploration of the area, design, cost data, construction, and operations.

2. PROJECT DEFINITION

This project will develop borrow areas and haul routes to provide suitable soil for fill material and for the construction of low-permeability caps anticipated to be required for WAG 6 remediation and other ORNL WAG remediation projects.

3. MISSION

The mission of the project is to provide sufficient amounts of suitable low-permeability soil for fill material and for use in constructing caps. The borrow area and haul route will provide long-range support in connection with the remediation of other WAG projects. The organization of the Project Team is provided in Fig. 1.

Fig. 1 Project Team Organization

4. REQUIREMENTS AND SPECIAL ISSUES

4.1 REQUIREMENTS AND SPECIAL CONSTRAINTS

4.1.1 Overall Requirements

1. A borrow area and haul route are required to deliver approximately 30,000 yd³ and 350,000 yd³ of low-permeability soil to the WAG 6 site in 1993 and 1994-1997, respectively, and 2×10^6 yd³ to other ORNL WAG sites in the next several years.
2. National Environmental Policy Act (NEPA)/DOE Order 5440.1C requires the preparation of an environmental impact assessment prior to the initiation of any government action that may significantly affect the environment. Executive orders have mandated that federal agencies avoid development, modification, or occupancy of floodplains and wetlands when practical alternatives exist. Construction in flood plains or on wetlands shall comply with 10 CFR 1022 and NEPA regulations.

4.1.2 Borrow Area Requirements

1. The engineering evaluations written in the Baseline Design Report state that low-permeability soil will be required for the WAG 6 caps. Soil from the selected borrow area shall be capable of providing an in-place permeability lower than that of the surrounding soil by CERCLA definition. Permeability levels near 1×10^{-7} cm/sec will satisfy this requirement.
2. The fill material shall be placed per the density and compaction requirements defined in the construction specifications.
3. Excavation of the soil will follow a staged development plan with erosion control features that will minimize runoff and create a site suitable for future development after borrow activities have ceased.
4. The borrow area and haul route development shall minimize disturbances to sensitive species of plants and animals and provide for appropriate erosion and sedimentation control features. Topsoil from the undeveloped borrow areas shall be stockpiled and preserved in a designated location for future use in landscaping the borrow area after it is closed. Marketable timber will be harvested from the site and sold through the Oak Ridge Reservation forest management program.
5. Interrelationships between existing facilities and aesthetic compatibility shall be considered during selection and construction of the borrow area and haul route.

4.1.3 Haul Route Requirements

1. The haul route to be developed shall be a gravel road and where possible, shall have a 30-ft-wide roadbed with drainage ditches on each side. Where obstruction such as wells, etc. are present, the architect-engineer should consider a single-lane roadbed with appropriate turnouts or other suitable adjustments to avoid removal of or damage to

these obstructions. An area approximately 50 ft wide has been designated for new road width clearing and right-of-way. The haul route shall be located in a way that minimizes dust and sound disturbance as well as construction costs. Excavation in contaminated areas shall be minimized.

2. The haul route should, as much as possible, accommodate the needs of all ORNL WAG remediation projects and be integrated with long-range planning for other ORNL activities.
3. The design load for the haul route will be based on the selected transport vehicles at full capacity. The design load shall be HS20-40 wheel loading under all weather conditions. The haul route shall be required to be traversable by fully loaded 15-ton 3-axle dump trucks under all Oak Ridge weather conditions. The haul route will include appropriate design changes that would be necessary to accommodate R35 Euclid truck traffic.
4. Precautions shall be taken to safeguard against hazardous operations and the consequences of potential accidents in adjacent facilities. This is pertinent to the haul routes involving White Oak Lake and the surrounding potentially contaminated areas. The area beyond the construction area shall not be disturbed.
5. Traffic control measures shall be implemented to minimize interference between construction activities and local vehicular and pedestrian traffic. Work zone traffic control plans shall be implemented and shall include necessary barricades, detours, and standard signage. Such plans shall comply with American National Standards Institute D6.1.

4.2 UNCERTAINTIES

1. The exact location and design of the borrow area and haul route will be determined after the completion of appropriate geotechnical testing and approvals by DOE.
2. Haul routes may pass through contaminated areas, and the extent of the contamination must then be evaluated.
3. The hauling contractor will be responsible for operating and maintaining the borrow area and haul route.

4.3 INTERFACES AND INTERFACE REQUIREMENTS

1. Haul routes should interface minimally with public roadways and traffic.
2. Haul routes passing through contaminated areas need to be coordinated through Health Physics.
3. Because proposed routes may pass environmentally sensitive areas, they will require permits and coordination with governing agencies. Hauling on public roads from on or

off site can cause public safety and perception problems and will therefore require coordination with governing and affected agencies.

4. Hauling operations and soil acquisitions from a borrow area shall be coordinated with ongoing work and future operations.

4.4 SPECIAL ANALYSES

1. A Risk Assessment Plan, a Health and Safety Plan, a Quality Assurance Plan, and a Waste Management Plan will be prepared during the Title I and Title II design efforts.
2. An Environmental Assessment is currently being prepared, and initial geotechnical evaluations have recently been completed.
3. System Safety Engineering will prepare a Safety Review.
4. A Project Management Plan for the WAG 6 remediation is currently being prepared.
5. Haul routes passing over utility lines, bridges, weirs, and culverts will require an engineering analysis to determine the need for preventing damage.

4.5 HUMAN FACTORS

The development of the borrow area and haul route shall be designed to maximize the safety and health of operating and maintenance personnel. Where applicable, personnel training such as SARA/OSHA training shall be performed in accordance with regulatory requirements.

4.6 MAINTENANCE ISSUES

1. Haul routes will require periodic maintenance.
2. Erosion control must be provided at the borrow area, along any newly developed haul route, and at any designated laydown area.

4.7 CRITICAL SYSTEMS

No critical systems are associated with this project.

4.8 TESTING REQUIREMENTS

Geotechnical testing (including laboratory testing) and reserve studies (volumetric calculations) must be completed on the selected site. Testing to qualify the borrow soil will include triaxial permeability tests on representative soil samples. The soil samples will be

remolded at appropriate densities and moisture contents. The testing will be performed at a soils laboratory under controlled test conditions. If a borrow area does not have an adequate quantity of borrow material or the borrow material will not meet the required permeability, the site will be discarded along with any haul route alternatives from that borrow site.

5. CONFIGURATION CONTROL PLAN

- Configuration control will be in accordance with the WAG 6 Configuration Management Plan.
- ,

DISTRIBUTION

1. W. D. Barton	25. D. G. Miller
2. L. D. Bates	26. A. G. Oaks
3. P. Baxter	27-28. P. T. Owen
4. D. T. Bell	29. N. Prudent
5. R. B. Cook	30. K. P. Rice
6. R. M. Collins	31. G. E. Rymer
7. S. Defalco	32. A. W. Saulsbury
8. M. F. P. Delozier	33. T. F. Scanlan
9. C. K. Ford	34. P. A. Schrandt
10. S. B. Garland	35. N. V. Shamblin
11. D. L. Garrett	36. B. G. Shockley
12. C. D. Goins	37. K. B. Swain
13. K. G. Greer	38. S. D. Van Hoesen
14. P. J. Halsey	39. D. R. Watkins
15. L. Holder	40. R. K. White
16. J. Hughey	41. M. A. Woody
17. R. L. Jeffers	42. A. N. Wylie
18. B. L. Kimmel	43. Central Research Library
19. F. C. Kornegay	44-48. ER Document Management Center
20. R. B. Knott	49. Laboratory Records Dept.
21. V. Legg	50. ORNL Patent Section
22-24. D. M. Matteo	
-
51. Office of Assistant Manager for Energy Research and Development, DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8600
 52. P. Chatterji, Ebasco, Inc. 111 Union Valley Road, Oak Ridge, TN 37830-8045
 - 53-54. R. L. Nace, Branch Chief, Nonenrichment Facilities, Oak Ridge Program Division, Office of Eastern Area Programs, Office of Environmental Restoration, EM-423, Trevion 2, U.S. Department of Energy, Washington, DC 20585
 - 55-56. S. S. Perkins, DOE Oak Ridge Field Office, Information Resource Center, 105 Broadway, Oak Ridge, TN 37830
 57. S. P. Riddle DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8541
 - 58-59. R. C. Sleeman, DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8540
 60. D. W. Swindle, Radian Corporation, 120 South Jefferson Circle, Oak Ridge, TN 37830
 - 61-62. H. M. Thron, Chief, Enrichment Facilities, Oak Ridge Program Division, Office of Eastern Area Programs, Office of Environmental Restoration, EM-423, Trevion 2, U. S. Department of Energy, Washington, DC 20585.
 63. Gilbert/Commonwealth, Inc., Suite 200 1055 Commerce Park Drive, Oak Ridge, TN 37830
 - 64-65. Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831

**DATE
FILMED
01/20/93**