WSRC-RP-90-1328

**EVALUATIONS OF 105-K REACTOR BUILDING FLOOR
SLAB FREQUENCIES AND BASEMAT STRESSES (U)**

by R. L. Bandyopadhyay

Westinghouse Savannah River Company
Savannah River Site
Aiken, South Carolina 29808

WSRC-RP--90-1328

DE93 005208

Other Authors:

This paper was prepared in connection with work done under Contract No. DE-AC09-89SR18035 with the U. S. Department of Energy. By acceptance of this paper, the publisher and/or recipient acknowledges the U. S. Government's right to retain a nonexclusive, royalty-free license in and to any copyright covering this paper, along with the right to reproduce and to authorize others to reproduce all or part of the copyrighted paper.

MASTER

Received by OST

DEC 31 1992

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

EVALUATIONS OF 105-K REACTOR BUILDING FLOOR SLAB FREQUENCIES AND BASEMAT STRESSES (U)

DECEMBER, 1990

UNCLASSIFIED
DOES NOT CONTAIN
UNCLASSIFIED CONTROLLED
NUCLEAR INFORMATION

ADC

& RO:

C. J. Banick
C.J. Banick, Asst. Class. Off.

Date: *12/16/92*

PREPARED

R. L. Bandyopadhyay 12/90

R. L. Bandyopadhyay, Group Leader
Seismic Structural Engineering

APPROVED

M. E. Maryak

M. E. Maryak, Manager
Seismic Structural Engineering

APPROVED

M. W. Barlow

M. W. Barlow, Manager
Seismic Engineering

APPROVED

J. D. Cohen 18 Dec 90

J. D. Cohen, Manager
Systems Engineering

WSRC-RP-90-1328

**EVALUATIONS OF 105-K REACTOR
BUILDING FLOOR SLAB FREQUENCIES
AND BASEMAT STRESSES (U)**

DECEMBER, 1990

SEISMIC STRUCTURAL ENGINEERING

TASK FORCE

**R. L. Bandyopadhyay
R. C. Chen
J. S. Mulliken**

WSRC-RN-90-1328
REVISION 0
DECEMBER, 1990
PAGE 1 OF 14

TABLE OF CONTENTS

ITEM	PAGE
1.0 Objective	3
2.0 Description of Procedures	3
2.1 Frequency Calculation	3
2.1.1 Slab Dimensions	3
2.1.2 Boundary Conditions	4
2.1.3 Loads	4
2.1.4 Aspect Ratio	4
2.1.5 Analysis	5
2.1.6 Computer Program	6
2.1.7 Discussion of Results	6
2.2 Basemat Stresses	9
2.2.1 Codes and Standards	9
2.2.2 Assumptions	10
2.2.3 Parameters	11
2.2.4 Evaluation	11
3.0 Conclusion	12
3.1 Frequency	12
3.2 Basemat Evaluation	12
4.0 References	13

1.0 OBJECTIVE

This report describes the evaluation of natural frequencies of the concrete floor slabs in the K Reactor. The evaluation of the floor frequencies at elevation 34 ft and below is required to demonstrate that the floor frequencies of the Reactor Building are sufficiently high. This will provide confidence in the interim position that the structural amplification of the vertical motion are approximately in the same order or less than the structural amplification of the horizontal motion. Consequently, this evaluation determines the acceptability of using horizontal floor response spectra or two thirds of the horizontal floor response, on a case by case basis, as an interim estimate of the vertical motions in the K Reactor for restart.

Basemat stresses in the Process area are also tabulated in this report. Both evaluations are required for Reactor Restart.

2.0 DESCRIPTION OF PROCEDURES

2.1 FREQUENCY CALCULATION

The frequency of a slab depends on various parameters. These parameters are discussed below.

2.1.1 SLAB DIMENSIONS

All pertinent information was collected from the drawings for the K Reactor Process Building.

2.1.2 BOUNDARY CONDITIONS

All boundary conditions were taken from the drawings. The drawings were carefully examined and the boundary conditions for the slabs were classified as simply supported, fixed or continuous. In addition all the reinforcement details were checked at the fixed or continuous edges to verify adequate lap lengths. Where lap lengths were not sufficient or sufficient dowels were not provided, the edges were taken as simply supported.

2.1.3 LOADS

For dead loads, the weight of concrete is taken as 150 lbs/ft³. Live load is assumed to be 100 lbs/ft² in the operating floors and 40 lbs/ft² on the roof area (EL 27.5 ft and EL 34.0 ft).

2.1.4 ASPECT RATIO

Aspect ratio is the ratio between the long span and the short span of a slab and determines whether a slab is acting as one way slab or two way slab. All the drawings were examined in detail to determine the aspect ratios from slab dimensions. If this ratio was two or greater, the slab was considered one way, otherwise two way slab was considered. The reinforcement details, lap lengths, dowels etc. were examined to verify the one way/two way slab configuration.

2.1.5 ANALYSIS

The frequency for a one way slab is given by:

$$frequency = \frac{1.2769}{2\pi} \sqrt{\frac{g}{\delta}}$$

(Reference 1)

where :

δ = maximum deflection for the slab

g = acceleration due to gravity

Therefore the maximum deflection for each slab must also be calculated. This was performed using the deflection formulas in the beam section of the AISC manual (Ref 2).

Frequency for a two way slab was calculated by the following equation :

$$frequency = \frac{\lambda^2}{2\pi a^2} \sqrt{\frac{Eh^3}{12\gamma(1-\nu^2)}}$$

(Reference 3)

where :

λ = dimensionless frequency parameter determined by boundary conditions using table 11-4 of reference 3

a = appropriate span length determined by the boundary conditions and geometry using table 11.4 of reference 3.

E = modulus of elasticity

γ = mass per unit area

h = thickness of slab

ν = poisson's ratio with consistency of units in accordance with table 3-1, page 10 of ref 3.

2.1.6 COMPUTER PROGRAM

A FORTRAN program (Ref 4) was written to calculate the natural frequency of the concrete slabs using the above two equations. A formatted input file containing reference nodes, thicknesses, spans, and boundary conditions must be specified to run the program. This information is used to perform a one way or two way slab analysis, whichever is appropriate according to the data given in the input file. Two output files containing information for each slab such as elevations, reference nodes, thickness, span, corresponding support conditions, and frequency will result from the computer run. One of the output files will list all slabs and corresponding information that were analyzed by one way analysis, and the other will contain slabs which were analyzed as two way slabs.

The computer program was verified by alternate calculations for various slabs, taken at random. A sample of the output is shown on page 14.

2.1.7 DISCUSSION OF RESULTS

A total of 64 slab segments were considered. The following table shows the summary of the results.

Frequency	No. of slab segments	Percentage
> 33 Hz	49	76.6
> 20 Hz	58	90.6
> 16 Hz	61	95.3

Slab locations and frequencies are shown below :

Location	No. of slab segments	Frequency Range
-20.0 ft	16	57 to 1489 hz
0.0 ft	25	66 to 641 hz 1 seg. @ 24 hz
15.0 ft	8	25 to 175 hz 1 seg. @ 16.25 hz
16.0 ft	1	20 hz
21.0 ft	1	33 hz
26.33 ft	4	21, 28, 31, 74 hz
27.5 ft	1	14.33 hz
34.0 ft	8	14.61 to 498 hz

A comparison of the horizontal and vertical SSI modes (see references 7 and 8) show that they are both about 2.5 hz. The radiation damping for both directions of motion is also expected to be comparable. The fundamental horizontal fixed base frequency of the K Reactor is 6.9 hz, and the second mode frequency is 12.47 hz. The fundamental vertical fixed base mode of the Reactor is about 18 hz, which represents the global dynamic behavior determined by the mass of the building and the vertical frequency of the walls. The lowest out-of-plane slab frequency below elevation 0.0 ft is above 33 hz.

It may be postulated that the amplifications due to SSI modes will be similar for the horizontal and vertical directions of motion. This will result in vertical floor response spectra at the base of the dynamic model (elev. -20.0 ft) that are approximately two third of the horizontal floor response spectra, with the spectral amplifications centered primarily in the frequency range of 2.5 hz. Floor response spectra amplifications between elevations -20.0 ft and 0.0 ft are expected to be less than amplifications in the horizontal direction because the separation of SSI and fixed base building frequencies is wider in the vertical direction than in the horizontal direction. Based on this reasoning, the vertical floor response spectra below elevation 0.0 ft are expected to be about two-thirds of the horizontal floor response spectra at comparable elevations.

Most of the equipment to be seismically qualified in the K Reactor are below elevation 0.0 ft. However, there are a few pieces of equipment which are at elevations 15 ft and 34 ft. Most of the floor panels at these elevations have out of plane fundamental frequencies of 33 hz or higher. Only three slab segments have frequency less than 16 hz and the frequencies are as follows :

Elevation ft	Reference Grid	Dimension ft	Thick in	Freq hz
EL 27.50	AL-DL / 7-8	34 x 51	30	14.33
EL 34.00	BR / 5-6	54 x 59	42	14.75
EL 34.00	BR- / 103-1	36 x 37.75	24	14.61

These low frequencies resulted from either one of the conditions listed below or a combination of them :

- a) small thickness of the slabs compared to the spans,
- b) simply supported boundary condition of one or more edges.

The slab @ EL 27.50 ft is in the Stack building and it has been analyzed and found satisfactory (Ref 5). The other two slabs are roof slabs where no major equipment are located.

It is our considered opinion that significant slab amplifications of vertical motions are not expected at these two elevations, because there is still significant separation between the fundamental out-of-plane slab frequencies and vertical SSI modes. Hence, horizontal floor response spectra at these elevations may be used as an interim estimate of vertical motions for qualification of equipment.

2.2 BASEMAT STRESSES

The basemat stresses were evaluated for the combined effect of dead, live and seismic loads.

2.2.1 CODES AND STANDARDS

ACI 349-85 and ACI 349R-85 : Code Requirements for Nuclear Safety Related Concrete Structures (ACI 349-85) and Commentary - ACI 349R-85, American Concrete Institute, Detroit, Michigan.

2.2.2 ASSUMPTIONS

The evaluation of the basemat is a complex one. For the purpose of this report the following assumptions are made:

- A) The Process Building is modelled as a stick model, similar to the stick model for the C Reactor (Ref 6). The K Reactor is identical to the C Reactor.
- B) The mat - 170 ft x 250 ft - is considered 170 ft x 170 ft for simplicity of computation.
- C) Dead loads were taken from the report on C Reactor (Ref 6).
- D) Seismic shear forces were taken from the report on K Reactor (Ref 7).
- E) An eccentricity of 9 ft, 5% of the least dimension of 170 ft, were considered for dead and live loads.
- F) Live loads were taken as 100 lbs/sq.ft.
- G) The mat is considered rigid and the maximum bearing pressure is calculated at the end of the basemat.
- H) This bearing pressure is then applied to a few critical portions of the base mat. It is emphasized that every slab of the basemat was not analyzed, but only a few critical segments chosen by engineering judgement. This approach is considered conservative as the maximum bearing pressure, which itself was calculated conservatively, is used to evaluate the slabs irrespective of locations.

2.2.3 PARAMETERS

The following design parameters were considered for evaluation:

Allowable concrete stress, $f_c' = 2,500$ psi

Allowable steel stress, $f_t = 40,000$ psi

The reinforcement details and slab thicknesses were taken from the K reactor drawings.

2.2.4 EVALUATION

The most critical of the load combinations of $1.4DL + 1.7LL$ or $DL + LL + SE$ were considered for the design. The base mat thickness varies from 8 ft. to 10 ft. and the minimum thickness of 8.0 ft. was considered for the evaluation. In the critical sections, shear reinforcement in the form of stirrups have been used, and where appropriate, strengths of shear reinforcements have been considered for shear capacities.

The critical Demand/Capacity ratio is given below :

Moment, $D/C = 0.87$

Shear, $D/C = 0.86$

3.0 CONCLUSION

3.1 FREQUENCY

The frequencies of three segments out of a total of 64 segments fall below 16 hz. One segment is in the Stack building, while the other two are roof area, and no major equipment is mounted there. Based on this evaluation, it may be concluded that the floor slabs will behave in a rigid-like manner and structural amplifications of the vertical motion will be no larger than the structural amplifications of the horizontal motion and horizontal floor response spectra are a conservative estimate of the vertical floor response spectra in the K Reactor building.

3.2 BASEMAT EVALUATION

The Demand-Capacity ratios, by very conservative calculation, are well under 1.0 and therefore quite adequate to resist dead, live, and seismic forces.

4.0 REFERENCES

1. Roark, Raymond J. and Young, Warren C. : Formulas for Stress and Strain, Fifth Edition, McGraw-Hill.
2. Manual of Steel Construction, American Institute of Steel Construction, Chicago.
3. Blevins, Robert D. : Formulas for Natural Frequency and Mode Shape, Van Nostrand Reinhold.
4. Calculation no., S-CLC-K-00014 : Evaluation of 105K Reactor Building Floor Slab Frequencies and Base Mat Stresses.
5. URS / John A. Blume & Associates : Phases I, II and III of the Comprehensive Seismic Analysis and Evaluation of the 105K Exhaust Stack Building at the Savannah River Site, December, 1989.
6. John A. Blume & Associates : Seismic Analysis of Buildings 105C and 105R and associated systems and equipment of the Savannah River Plant, Vol II, January, 1969.
7. URS / John A. Blume & Associates : Floor Acceleration Response Spectra for Updated DBE and Reg. Guide 1.60 Seismic Input : Building 105K, Savannah River Plant.
8. EQE Engineering : Seismic Analysis of The Vertical Tube Storage system Monorail Support Frames in Building 105-L, 105-K, and 105-P at The Savannah River Plant ; Soil-Structure Interaction Analyses of Buildings 105-L, 105-K and 105-P; September 1989.

ELEVATION 16.00						
REFERENCE NODES	THICKNESS	SPAN	SUPPORT	SPAN	SUPPORT	FREQUENCY
CR-CBT 8-9	2.0000	24.000	SIMPLE-SIMPLE	34.000	SIMPLE-SIMPLE	20.12
ELEVATION 21.00						
REFERENCE NODES	THICKNESS	SPAN	SUPPORT	SPAN	SUPPORT	FREQUENCY
DL-BL 6-7	1.5000	18.500	CONTINUOUS-SIMPLE	28.000	CONTINUOUS-SIMPLE	32.55
ELEVATION 26.33						
REFERENCE NODES	THICKNESS	SPAN	SUPPORT	SPAN	SUPPORT	FREQUENCY
AR-BR N/A	2.0000	23.000	CONTINUOUS-SIMPLE	45.000	CONTINUOUS-SIMPLE	27.73
AL-BL 6-7	2.5000	31.000	CONTINUOUS-SIMPLE	51.000	CONTINUOUS-SIMPLE	20.50
ELEVATION 27.50						
REFERENCE NODES	THICKNESS	SPAN	SUPPORT	SPAN	SUPPORT	FREQUENCY
AL-DL 7-8	2.5000	34.000	SIMPLE-SIMPLE	51.000	CONTINUOUS-SIMPLE	13.39
ELEVATION 34.00						
REFERENCE NODES	THICKNESS	SPAN	SUPPORT	SPAN	SUPPORT	FREQUENCY
BR 5-6	3.5000	54.000	CONTINUOUS-CONTINUOUS	59.000	SIMPLE-SIMPLE	14.02
AR-BR 7-8	2.0000	30.000	CONTINUOUS-SIMPLE	30.000	CONTINUOUS-SIMPLE	23.29
BR- 103-1	2.0000	36.000	SIMPLE-SIMPLE	37.750	CONTINUOUS-SIMPLE	13.47
AAR-BR 103.5-1	3.0000	43.000	CONTINUOUS-CONTINUOUS	48.000	CONTINUOUS-SIMPLE	19.67
BL-AAL 103.5-101	3.0000	43.000	CONTINUOUS-SIMPLE	48.000	CONTINUOUS-SIMPLE	16.44
-BL 102-1	2.0000	28.000	CONTINUOUS-SIMPLE	32.500	SIMPLE-SIMPLE	21.80
ELEVATION 48.00						
REFERENCE NODES	THICKNESS	SPAN	SUPPORT	SPAN	SUPPORT	FREQUENCY
AAL-AAR -103	2.5000	47.000	CONTINUOUS-CONTINUOUS	63.000	CONTINUOUS-CONTINUOUS	13.23
AAL-AAR 1-2	5.0000	31.000	CONTINUOUS-SIMPLE	62.000	CONTINUOUS-CONTINUOUS	42.43

END

**DATE
FILMED**

4 / 20 / 93