NOTICE

**CERTAIN DATA
CONTAINED IN THIS
DOCUMENT MAY BE
DIFFICULT TO READ
IN MICROFICHE
PRODUCTS.**

EGG-PRP-10372
JULY 27, 1992

INFORMAL REPORT

SAFETY ANALYSIS REPORT FOR PACKAGING FOR
THE IDAHO NATIONAL ENGINEERING LABORATORY
TRA TYPE I SHIPPING CONTAINER AND
TRA TYPE II SHIPPING CAPSULE

BRADLEY J. HAVLOVICK

*Managed
by the U.S.
Department
of Energy*

*Work performed under
DOE Contract
No. DE-AC07-76ID01570*

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

This document contains new concepts or the author(s) interpretation of new calculations and/or measurements; accordingly, EG&G Idaho, Inc. is required by the United States Government to include the following disclaimer:

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights. References herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

EGG-PRP--10372

DE93 001918

**SAFETY ANALYSIS REPORT FOR PACKAGING
FOR THE
IDAHO NATIONAL ENGINEERING LABORATORY
TRA TYPE I SHIPPING CONTAINER
AND
TRA TYPE II SHIPPING CAPSULE**

Bradley J. Havlovick

Published July 27, 1992

Prepared for the
U. S. Department of Energy
Under DOE Idaho Field Office
Contract DE-AC07-76ID01570

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

ABSTRACT

The TRA Type I Shipping Container and TRA Type II Shipping Capsule were designed and fabricated at the Idaho National Engineering Laboratory as special form containers for the transport of non-fissile radioisotopes and fissile radioisotopes in exempt quantities. The Type I container measures 0.75" outside diameter and 3.000" long. The Type II capsule is 0.495" outside diameter and 2.000" long. The container and capsule were tested and evaluated to determine their compliance with Title 49 Code of Federal Regulations 173, which governs packages for special form radioactive material. This report is based upon those tests and evaluations. The results of those tests and evaluations demonstrate the container and capsule are in full compliance with the special form shipping container regulations of 49 CFR 173.

TABLE OF CONTENTS

	<u>PAGE</u>
ABSTRACT.....	i
ACRONYMS.....	iv
1.0 GENERAL INFORMATION.....	1
1.1 INTRODUCTION.....	1
1.2 PACKAGE DESCRIPTION.....	4
1.2.1 Packaging.....	4
1.2.2 Contents of Packaging.....	5
2.0 STRUCTURAL EVALUATION.....	7
2.1 STRUCTURAL DESIGN.....	7
2.2 WEIGHTS AND CENTERS OF GRAVITY.....	7
2.3 MECHANICAL PROPERTIES OF MATERIALS.....	7
2.4 GENERAL STANDARDS FOR ALL PACKAGES.....	9
2.5 STANDARDS FOR TYPE B AND LARGE QUANTITY PACKAGING...	9
2.6 NORMAL CONDITIONS OF TRANSPORT (NCT).....	10
2.7 HYPOTHETICAL ACCIDENT CONDITIONS (HAC).....	10
2.8 SPECIAL FORM.....	11
3.0 THERMAL EVALUATION.....	13
3.1 DISCUSSION.....	13
3.2 SUMMARY OF THERMAL PROPERTIES OF MATERIALS.....	13
3.3 TECHNICAL SPECIFICATIONS OF COMPONENTS.....	13
3.4 THERMAL EVALUATION FOR NCT.....	13
3.5 THERMAL EVALUATION FOR HAC.....	13
4.0 CONTAINMENT.....	15
4.1 CONTAINMENT BOUNDARIES.....	15
4.2 REQUIREMENTS FOR NCT.....	15
4.3 REQUIREMENTS FOR HAC.....	15
5.0 SHIELDING EVALUATION.....	16
6.0 CRITICALITY EVALUATION.....	17
7.0 OPERATING PROCEDURES.....	18
7.1 PROCEDURES FOR LOADING CAPSULES.....	18
7.2 PREPARATION OF AN EMPTY PACKAGE FOR TRANSPORT.....	18

	<u>PAGE</u>
8.0 ACCEPTANCE TESTS AND MAINTENANCE.....	19
8.1 ACCEPTANCE TESTS.....	19
8.2 MAINTENANCE PROGRAM.....	21
9.0 QUALITY ASSURANCE.....	22

LIST OF FIGURES

Fig. 1.1 TRA Type I Shipping Container (Dwg. No. 435974).....	2
Fig. 1.2 TRA Type II Shipping Capsule (Dwg. No. 436956).....	3
Fig. 2.1 Container/Capsule Centers of Gravity.....	8

LIST OF TABLES

Table 1.1 Material Chemical Requirements.....	5
Table 2.1 Mechanical Properties of Container/Capsule Mat'l....	7
Table 3.1 Thermal Properties of Materials.....	14

REFERENCES

References.....	23
-----------------	----

APPENDICES

Appendix A.....	24
-----------------	----

ACRONYMS

ASM	American Society for Metals
ANSI	American National Standards Institute
ASME	American Society of Mechanical Engineers
ASTM	American Society for Testing and Materials
CFR	Code of Federal Regulations
DOE	U. S. Department of Energy
DOP	Detailed Operating Procedure
DOT	U. S. Department of Transportation
HAC	hypothetical accident conditions
IAEA	International Atomic Energy Agency
INEL	Idaho National Engineering Laboratory
NCT	normal conditions of transport
NRC	U. S. Nuclear Regulatory Commission
ORNL	Oak Ridge National Laboratory
PRP	Power Reactor Programs
SFSC	special form shipping container
TRA	Test Reactor Area

SAFETY ANALYSIS REPORT FOR PACKAGING FOR THE SPECIAL FORM CERTIFICATION OF TRA TYPE I SHIPPING CONTAINER AND TRA TYPE II SHIPPING CAPSULE

1. GENERAL INFORMATION

1.1 INTRODUCTION

The TRA Type I Shipping Container and TRA Type II Shipping Capsule were designed and fabricated at the Idaho National Engineering Laboratory (INEL) in 1991. The container and capsule were tested to demonstrate they meet DOT requirements for special form. The container and capsule are designed to provide the primary containment of non-fissile radioactive materials and fissile radioactive materials in exempt quantities to be transported inside a DOT/NRC licensed package.

Department of Transportation (DOT), Ref. 1., Nuclear Regulatory Commission (NRC), Ref. 2., and International Atomic Energy Agency (IAEA), Ref. 3., regulations require special form containers and capsules must not break or shatter when subjected to:

- 1) an impact test; a free fall onto a flat, horizontal, essentially unyielding surface from a height of not less than 9 meters (30 feet),
- 2) a percussion test; an impact from a steel billet weighing 1.4 kg. (3 pounds) being dropped from 1 meter (3.3 feet), and
- 3) a bending test; an impact from a steel billet weighing 1.4 kg. (3 pounds) being dropped upon the free end of the rigidly clamped specimen from a height of 1 meter (3.3 feet).

The containers and capsules must not melt or disperse when subjected to:

- 1) a heat test; heating of the specimen to 800° C (1472° F).

American National Standards Institute (ANSI), Ref. 4., provides guidelines for leak tests on radioactive material shipping packages.

Engineering drawings of the TRA Type I Shipping Container and TRA Type II Shipping Capsule are provided in Figure 1.1 and Figure 1.2.

NOTES:

1. WELD PER ASME B&PV CODE SECTION IX WITH VISUAL INSPECTION, NO CRACKS OR LINEAR INDICATIONS ALLOWED. LIQUID PENETRANT INSPECTION PER ASME B&PV CODE SECTION III CLASS II.
2. ALL MACHINED SURFACES TO BE $32/\sqrt{\text{ }}$. NOT NECESSARY TO MACHINE ITEM 6 SURFACE.
3. FINAL ASSEMBLY WELDING AND LEAK TESTING COMPLETED PER TRA HOT CELL FACILITY DETAILED OPERATING PROCEDURE 9.5 (COBALT PROCESSING).
4. SLIGHT INTERFERENCE FIT WITH ITEMS 4 & 5 .000 TO .015.
5. SLIGHT INTERFERENCE FIT WITH ITEMS 6 & 7 .000 TO .015.
6. UNLESS OTHERWISE SPECIFIED 4 PLACE DECIMALS SHALL HAVE A TOLERANCE OF: .XXXX = $\pm .0005$.

4 DETAIL

5 DETAIL

-1 ASSEMBLY

VIEW A
SCALE: 4/1

NOTES:

1. FINAL ASSEMBLY WELDING AND LEAK TESTING COMPLETED PER TRA HOT CELL DETAILED OPERATING PROCEDURE 9.6 (IRRIDIUM PROCESSING).
2. SURFACE ROUGHNESS $32/\sqrt{\text{IN}}$ UNLESS OTHERWISE NOTED.
3. PROVIDE SLIGHT INTERFERENCE FIT WITH ITEMS 3 & 4 .000-.015.
4. UNLESS OTHERWISE SPECIFIED 4 PLACE DECIMALS SHALL HAVE A TOLERANCE OF: .XXXX = $\pm .0005$.

D

C

B

A

-1 ASSEMBLY

3 DETAIL

Figure 1.2 TRA Type II Shipping Capsule

1.2 PACKAGE DESCRIPTION

1.2.1 Packaging

The TRA Type I Shipping Container (see Figure 1.1) is fabricated from stainless steel stock. The container assembly consists of a liner with plug and a capsule with two plugs. The liner fits inside the capsule. The container is assembled by placing the plugged liner filled with a radioisotope, inside a capsule, and plugging both ends of the capsule. The plug of the liner is held in place by an interference fit. The plugs of the capsule are welded in place in accordance with INEL Welding Procedure, Ref. 5., which meets the requirements of ASME Boiler and Pressure Vessel Code Section IX, 1989 edition up to and including W89 addenda.

The liner, liner plug, and capsule plug are fabricated from 3/4" diameter 304L stainless steel bar that conforms to ASTM A276 specifications. The liner measures 2.000" in length with an outside diameter of 0.615"-0.620" and an inside diameter of 0.5464" - 0.5474". The liner is cylindrical shaped externally and internally with a right circular cone at the bottom of the internal cylinder portion. The low point angle of the right circular cone is 120°. The liner plug is 0.375" long with an outside diameter of 0.5469"-0.5474".

The capsule is fabricated from 3/4" outside diameter tube of 304L stainless steel that conforms to ASME SA213 specifications. The tube has wall thickness of 0.035". The capsule length is 3.000". The capsule plug measures 0.375" long and has an outside diameter that will create an interference fit with the capsule equal to 0.0001"-0.0004".

Table 1.1, "Chemical Requirements", is provided to show chemical composition of 304L stainless steel.

The TRA Type II Shipping Capsule (see Figure 1.2) is fabricated from stainless steel stock. The capsule is fabricated from round bar material by boring a cylinder out of the bar along the long axis from one end, but leaving the other end intact. It is assembled by plugging the radioisotope filled capsule on the open end. The plug of the capsule is welded in place in accordance with INEL Welding Procedure, Ref. 6., which meets the requirements of ASME Boiler and Pressure Vessel Code Section IX, 1989 edition up to and including W90 addenda.

The capsule and plug are fabricated from 1/2" diameter 410 stainless steel bar that conforms to ASTM A276 specifications. The capsule has a length of 2.000", outside diameter of 0.490"-0.495" and an inside diameter 0.4214" - 0.4224". The capsule is cylindrical shaped externally and internally with a right circular cone at the bottom of the internal cylinder portion. The low point angle of the right circular cone is 120°. The plug is 0.250" long with a outside diameter of 0.4219"-0.4223". Table 1.1, "Chemical Requirements", is provided to show chemical composition of 410 Stainless Steel.

Table 1.1 Material Chemical Requirements

Type	ASTM A276 304L SS	ASTM A276 410 SS	ASME SA-213 304L SS
Composition, %			
Carbon, max.	0.03	0.15	0.040
Manganese, max.	2.00	1.00	2.00
Phosphorus, max.	0.045	0.040	0.040
Sulfur, max.	0.030	0.030	0.030
Silicon, max.	1.00	1.00	0.75
Chromium	18.00-20.00	11.50-13.50	18.0-20.0
Nickel	8.00-12.00		8.00-13.0
Other Elements	N 0.10 max		

1.2.2 Contents of Packaging

The TRA Type I Shipping Container and the TRA Type II Shipping Capsule are designed for the shipment of non-fissile and fissile exempt quantity radioisotopes in solid form. These special form containers/capsules meet the testing requirements of DOT, NRC and IAEA.

The projected radioisotopes to be shipped in the special form shipping containers will include, but not limited to:

<u>RADIONUCLIDE</u>	<u>PHYSICAL FORM</u>	<u>CHEMICAL FORM</u>	<u>MAXIMUM CONTENT PER CONTAINER</u>
Americium-241	Oxide	AmO ₂	50 Ci
Americium-243	Oxide	AmO ₂	3 Ci
Cesium-137	Chloride	CsCl	375 Ci
Cobalt-60	Metal		5,000 Ci
Curium-244	Oxide	CmO ₂	1,000 Ci
Iridium-192	Metal		5,000 Ci
Neptunium-237	Oxide	NpO ₂	0.01 Ci

<u>RADIONUCLIDE</u>	<u>PHYSICAL FORM</u>	<u>CHEMICAL FORM</u>	<u>MAXIMUM CONTENT PER CONTAINER</u>
Plutonium-238	Oxide	PuO_2	250 Ci, or less than 15 grams
Plutonium-239	Oxide	PuO_2	0.900 Ci, or less than 15 grams
Plutonium-240	Oxide	PuO_2	3.40 Ci
Plutonium-241	Oxide	PuO_2	1,500 Ci, or less than 15 grams
Plutonium-242	Oxide	PuO_2	0.06 Ci
Promethium-147	Oxide	Pm_2O_3	5,000 Ci
Strontium-90	Fluoride	SrF_2	450 Ci
Strontium-90	Oxide	SrO	450 Ci
Strontium-90	Titanate	$\text{SrO}(\text{TiO}_2)_x$ where $x \geq 0.5$	450 Ci
Thorium-230	Oxide	ThO_2	0.30 Ci
Uranium-233	Oxide	U_3O_8	0.14 Ci, or less than 15 grams
Uranium-233	Metal		0.14 Ci, or less than 15 grams
Uranium-234	Oxide	U_3O_8	0.09 Ci

2. STRUCTURAL EVALUATION

2.1 STRUCTURAL DESIGN

The designs of the TRA Type I Shipping Container and TRA Type II Shipping Capsule allow for use of each only once. The radioactive material can only be removed from the container/capsule by destructively breaking the container/capsule open.

2.2 WEIGHTS AND CENTERS OF GRAVITY

The TRA Type I Shipping Container and TRA Type II Shipping Capsule are cylindrical in shape with flat ends when assembled. Figure 2.1 shows cross-sectional views of each.

The weight of the TRA Type I Shipping Container when empty is 4.06 ounces with the center of mass, when empty, located 1.507 inches from the end, as shown in Figure 2.1.

The weight of the TRA Type II Shipping Capsule when empty is 0.73 ounces. The center of mass, when empty, is 1.065 inches from the non-welded end as shown in Figure 2.1.

2.3 MECHANICAL PROPERTIES OF MATERIALS

The properties of the materials used to fabricate the containers and capsules are listed in Table 2.1. The properties are from Ref. 7.

Table 2.1 Mechanical Properties of Container/Capsule Material

Type	304L SS	410 SS
Property		
Yield Stress, Psi	25,000	40,000
Ultimate Strength, Psi	70,000	70,000
Modulus of Elasticity, Psi	28.3×10^6	29.2×10^6
Coef. of Expansion, In/In/°F	8.46×10^{-6}	5.92×10^{-6}
Elongation, %	40	20
Density, Lb/In ³	0.283	0.283
Poisson's Ratio	0.3	0.3

Figure 2.1
Container/Capsule Centers of Gravity

2.4 GENERAL STANDARDS FOR ALL PACKAGES

Part 173.403 of Ref. 1. defines packaging for radioactive materials as "the assembly of components necessary to ensure compliance with the packaging requirements of 49 CFR Part 173 Subpart I. It may consist of one or more receptacles, absorbent materials, spacing structures, thermal insulation, radiation shielding and devices for cooling or absorbing mechanical shocks. The conveyance, tie-down system, and auxiliary equipment may sometimes be designated as part of the packaging."

Since the TRA Type I Shipping Container and TRA Type II Shipping Capsule will be shipped inside a DOT/NRC licensed package, General Standards for all Packages are applicable to the entire package of cask plus capsules.

The capsules and containers, although only a part of the packaging, comply with General Design Requirements specified in 49 CFR 173.411. These requirements state:

- a) the package can be easily handled,
- b) the package can be manually handled if the gross weight is 22-110 pounds,
- c) the package can be safely handled by mechanical means if the gross weight is 110 pounds or more,
- d) the lifting attachments of the package (if any) do not impose unsafe stresses on the package,
- e) the external surfaces of the package must be easily decontaminated,
- f) the outer layer of the package should avoid pockets or crevices where water might collect, and
- g) any feature added to the package for transport will not reduce the safety of the package.

The capsules and containers also comply with Standard Requirements for all Packages as described by 49 CFR 173.24. These requirements state that under conditions normal to transportation:

- a) there will be no significant release of hazardous materials to the environment,
- b) the effectiveness of the packaging will not be reduced, and
- c) there will be no mixture of gases in the package which could cause an explosion.

2.5 STANDARDS FOR TYPE B AND LARGE QUANTITY PACKAGING

Part 71.51 of Ref. 2 identifies Additional Requirements for Type B Packages. A Type B Package must insure the following will not occur under Normal Conditions of Transport:

- a) there will be no loss or dispersal of radioactive contents,
- b) there will be no significant increase in external radiation levels, and
- c) there will be no reduction in the effectiveness of the packaging.

Under Hypothetical Accident Conditions a Type B Package must insure the following does not occur:

- a) there will be no escape of radioactive materials, and
- b) there will be no external radiation dose rate exceeding one rem per hour at one meter from the external surface of the package.

Part 173.403 of Ref. 1. defines special form radioactive materials as "radioactive material which satisfies the following conditions: (1) it is either a single solid piece or is contained in a sealed capsule that can be opened only by destroying the capsule; (2) the piece or capsule has at least one dimension not less than 5 millimeters; and (3) the piece or capsule satisfies the test requirements of 49 CFR 173.469."

The TRA Type I Shipping Container and TRA Type II Shipping Capsule satisfy all three conditions listed above; thus, they are special form containment for radioactive materials by definition.

2.5 NORMAL CONDITIONS OF TRANSPORT

The structural integrities of the container and capsule are demonstrated by passing tests for special form radioactive material discussed in Section 2.8, "Special Form."

Part 71.71 of Ref. 2. discusses in detail Normal Conditions of Transport. The discussion pertains to evaluating package designs. The TRA Type I Shipping Container and TRA Type II Shipping Capsule are not complete packages by definition until they are properly placed inside a DOT/NRC licensed package. Once the capsules or containers are placed in DOT/NRC licensed packaging the total package assures integrity of the contents. The Safety Analysis Report for Packaging for the licensed package accounts for the special form shipping containers.

2.7 HYPOTHETICAL ACCIDENT CONDITIONS

The structural integrities of the container and capsule are demonstrated by passing tests for special form radioactive material discussed in Section 2.8, "Special Form."

Part 71.73 of Ref. 2. discusses in detail Hypothetical Accident Conditions. The discussion pertains to evaluating package designs. The TRA Type I Shipping Container and TRA Type II Shipping Capsule are not complete packages by definition until they are properly placed inside a DOT/NRC licensed package. Once the capsules or containers are placed in approved DOT/NRC packaging the total package assures integrity of the contents. The Safety Analysis Report for Packaging for the DOT/NRC licensed packaging accounts for the special form shipping containers.

2.8 SPECIAL FORM

Department of Transportation (DOT), Ref. 1., Nuclear Regulatory Commission (NRC), Ref. 2., and International Atomic Energy Agency (IAEA), Ref. 3., regulations require special form containers and capsules must not break or shatter when subjected to an impact test, a percussion test, and a bending test. The containers and capsules must not melt or disperse when subjected to a heat test. American National Standards Institute (ANSI), Ref. 4., has established the leak testing methods for verifying container integrity following the above mentioned tests.

In each of the following tests the containers/capsules should contain a solid (non-radioactive) form of the radioactive material to be shipped. This is done to realistically represent the mass of the actual material.

Each container/capsule must be tested in accordance with Title 49 CFR 173.469(b)(1). This is an impact test, or drop test of not less than 30 feet onto a target that is an unyielding surface.

Each container/capsule must be tested in accordance with Title 49 CFR 173.469(b)(2). This is a percussion test where the containers/capsules are struck by a billet that creates a force equal to the free fall of 1.4 kilograms (3 pounds) through 1 meter (3.3 feet). The billet must strike the containers/capsules in a manner that creates maximum damage. The containers/capsules must be placed on a sheet of lead, less than 1 inch thick and 3.5-4.5 on the Vickers hardness scale.

The container/capsule must be tested in accordance with Title 49 CFR 173.469(b)(3). This is a bending test. This test applies only to long, slender sources with a length of 10 centimeters (4 inches) or more, and with a length at least 10 times the minimum width. In this case, the containers/capsules, are exempt from this test because their lengths are less than 10 centimeters (4 inches) and their lengths are less than 10 times the minimum width.

Each container/capsule must be tested in accordance with Title 49 CFR 173.469(b)(4). This is a heat test where the container/capsule must be heated in air to a temperature of not less than 800° C (1472° F), held at that temperature for 10 minutes and then allowed to cool.

The container/capsule can be tested in accordance with Title 49 CFR 173.469(c)(2). This is a leaching assessment method for encapsulated material. The test involves immersing the capsule in heated water for four hours and then checking the activity of the water. In this case, since the containers/capsules will not have radioactive material in them the activity of the water will not indicate any leaks, if any.

When the leaching assessment method is not used, a leak test can be substituted. Each container/capsule can be tested in accordance with Title 49 CFR 173.469(a)(4). This is a test for leaktightness. Each container/capsule must demonstrate leaktightness of 10^{-4} torr-liter/second (1.3×10^{-4}

atm-cm³/second) based on air at 25° C (77° F) and one atmosphere differential pressure. Since the containers/capsules were filled with a non-radioactive material the leach assessment could not be performed and a test for leaktightness was substituted. This alternative method for testing leaktightness is allowed by 49 CFR 173.469(a)(4).

The TRA Type I Containers and TRA Type II Capsules demonstrated a leaktightness well in excess of the minimum requirements established by 49 CFR 173.469 (1.3 x 10⁻⁴ atm-cm³/sec.). For greater detail of the test results, see Section 8.1, Acceptance Tests.

3. THERMAL EVALUATION

3.1 DISCUSSION

The TRA Type I Shipping Container and TRA Type II Shipping Capsule were designed for shipment of solid form non-fissile radioisotopes and fissile radioisotopes in exempt quantities in DOT/NRC licensed packaging.

This section documents the thermal characteristics of the Type I Container and Type II Capsule.

3.2 SUMMARY OF THERMAL PROPERTIES OF MATERIALS

The thermal properties of the 304L and 410 stainless steels used to fabricate the container/capsule are compiled in Table 3.1

3.3 TECHNICAL SPECIFICATIONS OF COMPONENTS

The components of the TRA Type I Shipping Container are fabricated from 304L stainless steel bar stock and tubing and conform to standards ASTM A276 and ASME SA213, respectively; similarly, the TRA Type II Shipping Capsule is fabricated from 410 stainless steel bar stock that conforms to ASTM A276. The weld filler metal and welding standards that apply to the container and capsule conform to the American Welding Society (AWS) standards. The AWS standards have been developed in accordance with the rules of the American National Standards Institute (ANSI).

The mechanical properties for the container and capsule materials are compiled in Table 2.1 and the thermal properties for the container and capsule materials are compiled in Table 3.1.

3.4 THERMAL EVALUATION FOR NORMAL CONDITIONS OF TRANSPORT

The TRA Type I Shipping Container and TRA Type II Shipping Capsule will be shipped inside a DOT/NRC licensed package. The thermal integrity is demonstrated by passing tests for special form radioactive material discussed in Section 2.8, "Special Form."

3.5 THERMAL EVALUATION FOR HYPOTHETICAL ACCIDENT CONDITIONS

The TRA Type I Shipping Container and TRA Type II Shipping Capsule will be shipped inside a DOT/NRC licensed package. The thermal integrity is demonstrated by passing tests for special form radioactive material discussed in Section 2.8, "Special Form."

Table 3.1 Thermal Properties of Materials

TEMP (°F)	THERMAL COND. (BTU/HR-Ft-°F)	THERMAL COND. (BTU/HR-Ft-°F)
	304L SST	410 SST
70	15.2	8.6
100	15.3	8.7
200	15.5	9.3
300	15.6	9.8
400	15.8	10.4
500	15.8	10.9
600	15.9	11.3
700	15.9	11.8
800	15.9	12.2
900	15.9	12.7
1000	15.8	13.2
1100	15.6	13.6
1200	15.3	14.0
1300	15.1	14.5
1400	15.0	14.9
1500	15.1	15.3
Specific Heat (BTU/lb-°F)	0.12	0.11
Melting Temp (°F)	2550-2650	2700-2790

4. CONTAINMENT

4.1 CONTAINMENT BOUNDARIES

Closure for the special form containers/capsules is provided by fusion welding components together. The containers/capsules have no mechanism to be opened without destroying the container/capsule. The TRA Type I Shipping Container maintains one weld and one interference fit between the radioactive material and the outside of the container while the TRA Type II Shipping Capsule has one weld between the radioactive material and outside the capsule. By passing the Special Form tests described in Section 2.8 the containers/capsules have demonstrated their effectiveness for containment.

4.2 REQUIREMENTS FOR NORMAL CONDITIONS OF TRANSPORT

Test specimens of the special form containers/capsules have been tested for leaktightness to ANSI N14.5-1987, Ref. 4., following each of the tests (impact test, percussion test, bending test and heat test) required in 49 CFR 173. To satisfy 49 CFR 173, the containers/capsules must demonstrate leaktightness of 1.3×10^{-4} atm-cm³/s.

4.3 REQUIREMENTS FOR HYPOTHETICAL ACCIDENT CONDITIONS

Containment under Hypothetical Accident Conditions is assured by the facts the containers/capsules are shipped inside a DOT/NRC licensed package, and they have demonstrated special form leaktightness in accordance with 49 CFR 173.

5. SHIELDING EVALUATION

The TRA Type I Shipping Container and TRA Type II Shipping Capsule are special form containment for radioactive materials. They are designed to be shipped in a DOT/NRC licensed package. Shielding is a function of the package rather than the containers/capsules; therefore, this section is not applicable.

6. CRITICALITY EVALUATION

The TRA Type I Shipping Container and TRA Type II Shipping Capsule are designed to provide the primary containment of non-fissile and fissile exempt quantity radioactive materials to be transported inside a DOT/NRC licensed package. Since fissile material as defined by 10 CFR 71 will not be transported in the containers/capsules, a criticality evaluation is not necessary for the packages.

7. OPERATING PROCEDURES

The safe use of the TRA Type I Shipping Container and TRA Type II Shipping Capsule is assured through the use of Detailed Operating Procedures (DOP). The DOP's provide step-by-step instructions for handling, opening, closing and leak testing these Special Form Shipping Containers (SFSC).

49 CFR 173.469(a) states, each capsule specimen to be tested shall be fabricated so that it is representative of the actual capsule which will transport the proposed radioactive content. The containers and capsules used to satisfy the Special Form tests described in Section 2.8 were inspected by certified inspectors in accordance with EG&G Drawings 435974 and 436956; similarly, so will the containers and capsules that will be used to ship the radioisotopes.

7.1 PROCEDURES FOR LOADING CAPSULES

The process of loading radioisotopes into the Type I Shipping Container and Type II Shipping Capsule would be controlled by the end user; however, the closure of the containers and capsules is controlled by the design depicted on EG&G Idaho Drawing Nos. 435974 and 436956, respectively.

One capsule plug of TRA Type I Shipping Container must be welded and visually inspected in accordance with ASME Boiler and Pressure Vessel (B & PV) Code Section IX, and liquid penetrant inspected per ASME B & PV Code Section III Class II (See Figure 1.1). The final closure welding uses INEL Welding Procedure Specification S4.1, Ref. 5, (via TRA Hot Cell Facility Detailed Operating Procedure 9.5). This is a welding procedure for austenitic stainless steel (3XX class) that meets the requirements of the ASME B & PV Code Section IX, 1989 edition up to and including W89 addenda.

The final closure welding of TRA Type II Shipping Capsule uses INEL Welding Procedure Specification S4.7, Ref. 6, by way of TRA Hot Cell Facility Detailed Operating Procedure 9.6 (See Figure 1.2). This is a welding procedure for ferritic stainless steel (410 class) that meets the requirements of the ASME B & PV Code Section IX, 1989 edition up to and including W90 addenda.

7.2 PREPARATION OF AN EMPTY PACKAGE FOR TRANSPORT

Prior to being used, the containers and capsules are nothing other than stainless steel "components" and would require no special preparation if they were to be transported. Because, the filled containers and capsules must be cut open to release the contents inside and are not reusable, they are disposed of following use. Again, there would be little need to transport the containers and capsules as "empty packages".

8. ACCEPTANCE TESTS AND MAINTENANCE

8.1 ACCEPTANCE TESTS

The TRA Type I Shipping Container and TRA Type II Shipping Capsule were tested at the Idaho National Engineering Laboratory on January 28 - 30, 1992.

The Detailed Operating Procedure (DOP) used to perform the certification tests on the SFSC's is DOP 4.8.47. The DOP requires the performer to sign-off each step when completed. Test progression is not permitted unless the previous step is completed and signed-off. Throughout the testing process, equipment identification numbers and their most recent calibration dates are recorded. The DOP goes to great detail to insure accurate test results are achieved. This DOP was reviewed and approved in accordance with the requirements of the Power Reactor Program Department of EG&G Idaho, Inc.

The test performed met the requirements of Code of Federal Regulations, Title 49, Part 173.469 (tests described in Section 2.8) and are documented by the Site Work Release RI078 and DOP No. 4.8.47. The completed DOP No. 4.8.47 is included in Appendix A.

The tests were to use nine Type I Containers and nine Type II Capsules. For each type, three each were used for the Impact, Percussion, and Heat tests. The eighteen specimens were fabricated and inspected to meet the requirements of the respective drawings. The fabrication and inspection process is document by Site Work Release RI063, which is included in Appendix A.

The containers/capsules were loaded with a solid (non-radioactive) form of the radioactive material to be shipped. This is done to realistically represent the mass of the actual material. The only welding machine available to accomplish welding the containers and capsules closed, was inside the TRA Hot Cells. This situation created the potential of airborne radioactive contamination becoming entrapped within the welds. After the specimens were welded and decontaminated, only one of the eighteen specimens was indicating any radioactive contamination. Specimen #4 indicated radioactive contamination entrapped within the weld, but nothing on the external surfaces. The welding processes performed are documented by letter DCS-1-92 entitled, "SPECIAL FORM SHIPPING CONTAINER CERTIFICATE OF CONFORMANCE", which is included in Appendix A.

At the onset of the testing process the eighteen specimens were placed in a pressure chamber (not simultaneously) and subjected to 250 psig of helium for minimum of 25 minutes. If there were any leaks in the specimens the helium would be forced to the inside of the specimens.

Following depressurization, the specimens were surveyed by a Health Physicist (HP) for radiological readings. All the specimens except #4 showed no radioactive sources. Specimen #4 indicated radioactive contamination on the external surfaces of the specimen. With more than one specimen available for

each test (Impact, Percussion and Heat), further use of specimen #4 was not absolutely necessary. For the sake of safety, the contaminated specimen was eliminated from any further testing. Consequently, when the Heat test was performed there were three Type II Capsules and only two Type I Containers to be tested.

Following the HP survey, the specimens were placed in an alcohol bath so excessive or "gross" leaks could be determined. If a specimen had a gross leak, it could lose all the helium from inside before the specimen could be put into the helium detection chamber to test for more sensitive leaks, if any existed. Without checking for gross leaks, a specimen with a gross leak that released all the helium from inside before getting to the helium detection chamber may appear to have no leak.

Following the alcohol bath, all specimens were dried using absorbent cloth. One at a time, the specimens were placed in the vacuum chamber where a vacuum was drawn (See Section 2.8 for description of test requirements). The air and any helium present in the vacuum chamber was passed through a gas chromatograph. The results for each specimen were recorded using the sensitivity of the calibrated chromatograph as a reference point.

Once the initial leak tests were completed, three Type I Containers and three Type II Capsules were used to perform the Impact test. These six specimens were dropped from the mezzanine in the Material Test Reactor (MTR) Building at TRA. A piece of stainless steel plate, that measured 15" x 19" x 1/4", was placed upon the concrete floor of the MTR Building. The six specimens, after being released from minimum height of 30', struck the plate at various orientations. Small indentations were noticeable upon visual inspection of the six specimens.

The next test segment was the performance of the Percussion test. Three more Type I Containers and three more Type II Capsules were used to perform this test. The six specimens were struck by a steel billet having a flat face equal to 1" diameter and 1/8" radius corner. The height the billet was released from was 40". Each specimen was placed upon a piece of 1/4" thick lead sheet. Three different orientations were used with each type of container and capsule. The first orientation placed the specimens, lying on their sides, upon the piece of 1/4" thick lead sheet and the billet struck the specimens midway along their long axes.

The second orientation had the specimens' long axes tilted at an angle of 14° from the vertical. This angle locates the upper-most edge directly above the lowest-most edge of the specimens. The specimens were held at this position with the aid of a wooden block. The billet was dropped upon the weld area of the specimens.

The final orientation placed the specimens with their long axes in the vertical direction and the billet struck the end of the specimens.

The last part of the testing sequence prior to final leak testing was the heat test. A heat oven in the TRA machine shop was used to heat the specimens. A

Type K thermocouple was welded onto the end of one of the Type I Containers. The Type I was chosen over the Type II because of its larger mass. The larger mass would take longer to heat up than the smaller mass. The oven was pre-heated to approximately 1500° F as indicated on the oven's temperature indicator. The door to the oven was then opened and three Type II Capsules and one Type I Container were placed in the oven using a small wire basket and tongs. The second Type I Container (with thermocouple attached) was inserted through the closed oven door via an access hole. The thermocouple temperature readout device was placed adjacent to the oven. Once the temperature, as indicated by the thermocouple, reached 1472°F (800°C) a stopwatch was started. This temperature was maintained for 10 minutes. Once the 10 minutes had passed, the specimens were removed from the oven and allowed to cool to room temperature.

The last test was the final leak test. The execution of this leak test was performed exactly like the initial leak test.

The Type I Containers and Type II Capsules demonstrated a leaktightness well in excess of the minimum requirements established by 49 CFR 173.469 (1.3×10^{-4} atm-cm³/sec.). The largest value detected during the final leak tests was 2.27×10^{-7} atm-cm³/sec.

8.2 MAINTENANCE PROGRAM

Once the containers and capsules are closed by welding, they can only be opened by destructively breaking them open; thus, they can be used only once. Since each container and capsule are used only once, there are no components that require periodic or routine maintenance.

9. QUALITY ASSURANCE

DOE Order 5700.6C, Ref. 9., establishes Quality Assurance requirements for the Department of Energy; similarly, Title 10 CFR 50, Appendix B, Ref. 10., establishes Quality Assurance criteria for nuclear power plants and fuel reprocessing plants. Ref. 10. defines quality assurance as "all those planned and systematic actions necessary to provide adequate confidence that a structure, system, or component will perform satisfactorily in service". The 18-criteria structure of Ref. 10. is as follows:

1. Organization
2. Quality Assurance Program
3. Design Control
4. Procurement Document Control
5. Instructions, Procedures, and Drawings
6. Document Control
7. Control of Purchased Material, Equipment, and Services
8. Identification and Control of Materials, Parts, and Components
9. Control of Special Processes
10. Inspection
11. Test Control
12. Control of Measuring and Test Equipment
13. Handling, Storage, and Shipping
14. Inspection, Test, and Operating Status
15. Nonconforming Materials, Parts, or Components
16. Corrective Action
17. Quality Assurance Records
18. Audits

The American Society of Mechanical Engineers (ASME) has overall responsibility of nuclear power quality assurance standards. An American National Standard entitled, "ANSI/ASME NQA-1, Quality Assurance Program Requirements for Nuclear Power Plants", Ref. 11., was first issued in 1979. ANSI/ASME NQA-1 meets and clarifies the criteria of Ref. 10.

The EG&G Idaho, Inc. quality program was developed using Ref. 11. as a requirements document. Procedures enclosed in the EG&G Idaho, Inc. Quality Manual, Ref. 12., are directly based upon the current requirements of Ref. 11.

REFERENCES

1. Code of Federal Regulations, Title 49, Part 173, "Transportation."
2. Code of Federal Regulations, Title 10, Part 71, "Nuclear Regulatory Commission."
3. International Atomic Energy Agency, Safety Series No. 6, 1973, Revised Edition.
4. American National Standards Institute, N14.5-1987, "For Radioactive Materials - Leakage Tests on Packages for Shipment."
5. Idaho National Engineering Laboratory Welding Procedure Specification S4.1, Rev. 5, Welding of Austenitic Stainless Steel.
6. Idaho National Engineering Laboratory Welding Procedure Specification S4.7, Rev. 0, Welding of Ferritic Stainless Steel.
7. ASME Boiler & Pressure Vessel Code, Section III, Appendix I, 1989 Addenda, December 1989.
8. ASM Metals Handbook, Volume 3, Ninth Edition.
9. Department of Energy Order 5700.6C, "Quality Assurance."
10. Code of Federal Regulations, Title 10, Part 50 Appendix B, "Nuclear Regulatory Commission."
11. ANSI/ASME NQA-1, Quality Assurance Program Requirements for Nuclear Power Plants.
12. EG&G Idaho, Inc. Quality Manual.

Appendix A

CHED: NO. P09PM147-A SITE WORK RELEASE # RI078 PAGE 1
G&G IDAHO, INC. M PLNR: D.J.CAWLEY
FIELD CHANGE #: CHARGE NO: 124210024
HORT TITLE: SHIPPING CAPSULE CERTIFICATION TESTS
ATE RQSTD: 05/15/91 DATE REQUIRED: 03/15/92 NEED EVENT: N7A

REA: TRA SUB-AREA: MTR BLDG: 603 RM: NA EQ ID: NA
EQUESTOR: M.J.SHERICK EXT: 6-4212 HOUR LIMIT: 16.0 BY DJC
WR INPUT BY: W.F.LEWIS EXT: 6-4423

AFETY RVW RQD: Y INITIALS: MJS OTH SAF DOC: N PRIORITY: 53 TAGOUT: N
AD-CON RVW RQD: Y INITIALS: IH RVW RQD: N INITIALS:
WP RQD: N ALARA EVAL: N SSWP RQD: N RHA RQD: N ECL RQD: N

UAL RVW RQD: Y INITIALS: MJS QUAL LEVEL: A CLEAN CODE: N

EQ MGR RVW: M.J.SHERICK 05/30/91 MATERIAL LIST INCLUDED: N
UAL RVW: J.B.MONCUR 05/24/91
OP CHECKOUT REQ'D: N

AF RVW: T.D.HOSKINS 06/11/91
AD-CON RVW: S.T.LAFLIN 01/06/92
H RVW: / /

UD MGR RVW: M.J.SHERICK 05/30/91
AC MGR RVW: W.F.LEWIS 09/25/91

UP'R. APPR'L: *Jack H Taylor* -DATE: 1/28/92 COMPLETED DT-INITIALS
OB-DESCRIPTION:

PERFORM TESTS DESCRIBED IN DOP 4.8.47.

THE CAPSULES TO BE USED IN ALL TESTS ARE BEING SUPPLIED BY THE END
CUSTOMER, GENE KANEMOTO, EXTENSION 6-4053.

IT IS DESIRED TO CONDUCT THE INITIAL LEAK TEST ON ONE DAY, PERFORM THE
IMPACT TEST, PERCUSSION TEST, AND THE HEAT TEST ON A SECOND DAY AND
FINISH WITH THE FINAL LEAK TEST ON A THIRD DAY. THE LEAK TEST PERSONNEL
ARE NEEDED ONLY ON THE FIRST AND THIRD DAYS. THE IMPACT, PERCUSSION AND
HEAT TEST PERSONNEL ARE NEEDED ON THE SECOND DAY ONLY.

THIS SWR IS CONTROLLED BY A DSP AND DOP 4.8.7.

SWR CLOSEOUT REVIEW/APPROVAL

EQUESTOR: *MJA* DATE: 2/3/92
ESP FOREMAN: J.H.TAYLOR *Jack H Taylor* DATE: 2/3/92
JAL SUPERVISOR: *JCS O'Brien* DATE: 2/21/92
AC SUPERVISOR: *D. K. O'Brien* DATE: 2/26/92

RAFT	INSTR	MACH	WELD	HP	SUPV	QUAL	O/E
JURS	4.0	8.0	4.0	0.1	0.1	0.1	0.1
ATE CMPLD	/ /	2/29/92	1/29/92	/ /	/ /	1/29/92	/ /

DESCRIPTION (CONTINUED)

ALL WORK WILL BE PERFORMED IN A RADIOLOGICALLY CLEAN AREA.

DOP NUMBERS

DOP NO	REVN	DOP NO	REVN	DOP NO	REVN
4.8.47	09/11/91				

DRAWINGS

DRAWING	REV	DRAWING	REV	DRAWING	REV
NA					

NCR'S

NCR	REV	NCR	REV	NCR	REV
NA					

FCF'S

FCF	REV	FCF	REV	FCF	REV
NA					

OTHER FORMS

ONE

Detailed SWR Procedure

SWR RIC78

NOTE: This procedure requires verbatim compliance to the sequence and content of the integrated work instructions. Any deviations, unless they're explicitly identified in the integrated work instructions require prior approval through the use of a SWR Field Change Sheet.

Q NO CRAFT

1.00 SUPV

IT IS THE JOB SUPERVISOR'S RESPONSIBILITY TO ASSURE THAT ALL APPLICABLE SAFETY EQUIPMENT IS USED/WORN BY THE PERSONNEL PERFORMING WORK ON THIS SWR.

IT IS THE INDIVIDUALS RESPONSIBILITY TO ASSURE THAT THE RULES OF SAFETY SET FORTH IN THE TRA SAFETY MANUAL AND APPLICABLE DOCUMENTS ARE STRICTLY ADHERED TO.

9.00

PLANNING SEQUENCES CAN BE WORKED IN SEQUENCE AS DIRECTED BY REQUESTOR AND/OR BRAD HAVLOVICK (6-8254).

10.00

HP

INITIAL AND DATE:

efly
1/28/92

PROVIDE HP ASSISTANCE TO SURVEY CAPSULES AS SPECIFIED IN THE DOP AND TEST PROCEDURES.

15.00

QUAL

INITIAL AND DATE:

1/29/92

PROVIDE QUALITY ASSISTANCE FOR THE LEAK TESTING PER SWR AND ATTACHED DOP.

LEAK TEST WILL REQUIRE LEAK TEST EQUIPMENT DESCRIBED IN DOP 4.8.47. FINAL LEAK TESTS ARE REQUIRED BY QUALITY AND LEAK DETECTOR OPERATOR.

20.00

QUAL

INITIAL AND DATE:

1/29/92

PROVIDE QUALITY ASSISTANCE FOR THE IMPACT TEST PER SWR AND ATTACHED DOP.

IMPACT TEST WILL REQUIRE NO MATERIALS OTHER THAN PROVIDED BY GENE KANEMOTO AND BRAD HAVLOVICK. THE EXECUTION OF THE TEST WILL REQUIRE A PHOTOGRAPHER, A QUALITY INSPECTOR AND A SAFETY OBSERVER.

30.00

O/E

INITIAL AND DATE:

1/29/92

PROVIDE ASSISTANCE FOR THE PERCUSSION TEST PER SWR AND ATTACHED DOP. THE PERCUSSION TEST WILL REQUIRE EQUIPMENT THAT ERV GRAFWALLNER HAS FROM OTHER PERCUSSION TESTS HE PERFORMED. THE LEAD SHEET AND WOODEN BLOCKS FOR TILTING TWO CAPSULES ARE PROVIDED BY BRAD HAVLOVICK. THE BILLET HAS BEEN FABRICATED BUT REQUIRES INSPECTION WHICH INCLUDES DIMENSIONAL AND WEIGHT MEASUREMENTS. ERV GRAFWALLNER'S EXTENSION IS 6-4142. PERSONNEL REQUIRED FOR THE PERCUSSION TESTS INCLUDE A QUALITY INSPECTOR, A PHOTOGRAPHER, AND ERV GRAFWALLNER OR ERV'S ALTERNATE.

SEQ NO CRAFT

40.00 INSTR

INITIAL AND DATE: *Paul/for Jack* 1 / 29 / 92

PROVIDE INSTRUMENT ASSISTANCE TO CONDUCT HEAT TEST PER SWR AND ATTACHED DOP.

THE HEAT TEST WILL REQUIRE A HEAT OVEN THAT IS AVAILABLE AT THE TRA MACHINE SHOP AND A THERMOCOUPLE WITH A READOUT DEVICE. PERSONNEL REQUIRED INCLUDES A HEAT OVEN OPERATOR, QUALITY INSPECTOR, AND AN INDIVIDUAL TO FABRICATE AND INSTALL THE THERMOCOUPLE ONTO A CAPSULE.

INSTRUMENT PERSONNEL TO SUPPLY THERMOCOUPLE AND READOUT DEVICE, AND ASSIST IN READING TC WHEN REQUIRED.
TC TO BE METAL-CLAD TYPE K.

41.00 MACH

INITIAL AND DATE: *Paul D. Southworth* PD 1 / 29 / 92

PROVIDE MACHINIST SUPPORT TO CONDUCT HEAT TEST PER SWR AND PER ATTACHED DOP.

42.00 SUPV

INITIAL AND DATE: *GE* GE 1 / 29 / 92

WELD SUPERVISOR TO VERIFY THAT WELDOR IS CERTIFIED TO WELD TO INEL WELD PROCEDURE S2.0. *CF 1/29/92*

THIS WELD IS A B- WELD.

43.00 WELD

INITIAL AND DATE: *GE* GE 1 / 29 / 92

WELD THERMOCOUPLE(S) SUPPLIED BY INSTRUMENT SHOP TO THE CAPSULE(S) AS DIRECTED BY THE REQUESTOR. WELD TO INEL WELD PROCEDURE S2.0, USING WELD FILLER MATERIAL ER-308L. *CF 1/29/92*

THIS WELD IS A QUALITY LEVEL B- WELD.

A SWP AND A HOT WORK PERMIT WILL BE REQUIRED IF ANY WELDING IS DONE OUTSIDE OF AN APPROVED WELDING AREA.

TRAMO SUPPORT GROUP

CRAFT OPERATON SEQUENCE SHEET

LANNER:

SWR: R I 078

OB TITLE:

TOTAL CRAFT HOURS: 16

	10 WORKING HOURS/DAYS									
	1	2	3	4	5	6	7	8	9	10
CARPENTER										
ELECTRICIAN										
FITTER										
INSTRUMENTS			4							
JANITORS										
INSULATORS										
MACHINISTS			4	4						
MECHANICS										
EQUIPMENT OPERATORS										
PAINTERS										
SHEETMETAL										
TOOL CRIB										
WELDORS			4							
YARDMEN										
ASBESTOS WORKER										
QUALITY INSPECTOR	/									
SAFETY ENGINEER										
INDUSTRIAL HYGIENIST										
HEALTH PHYSICS										
JOB SUPERVISOR										
oPer. / Engr.	1	/								

OTE: SPECIFY ANY SPECIAL EQUIPMENT REQUIRED TO COMPLETE THE WORK COVERED BY THIS SWR.

SHIPPING CAPSULE CERTIFICATION TEST ITIN. 2Y

<u>WHEN</u>	<u>WHERE</u>	<u>ACTIONS</u>	<u>RESPONSIBLE PERSONS</u>
1/28/92 -8:30 A.M.	TRA 689, Lab 98	Engrave numbers on specimens. Photograph the specimens. Perform Initial Leak Test. Have HP survey specimens.	Mike Oates (Mike provide engraver) Rick Romero (Rick provide camera, film) Mike Oates, Kelly Oliver (Mike provide test equipment) Rusty Grant (HP provide equipment)
1/29/92 -8:30 A.M.	TRA 603, (MTR Bldg)	Setup Impact test scenario. Photograph Impact test scenario. Perform Impact Test. Have HP survey specimens. Photograph the specimens.	Brad Havlovick (Brad provide safety ribbon, warning signs, target, tape measure) Rick Romero (Rick provide camera, film) Brad Havlovick, Kelly Oliver Rusty Grant (HP provide equipment) Rick Romero (Rick provide camera, film)
-10:00 A.M.	TRA 604, Lab 106	Setup Percussion test scenario. Weigh and Measure Billet. Photograph Test scenario. Perform Percussion Tests. Have HP survey specimens. Photograph the specimens.	Erv Grafwallner (Erv provide clamps, PVC pipe, wax string, billet, tape measure) Brad Havlovick (Brad provide lead sheet, capsule prop) Kelly Oliver (Kelly provide weigh and measuring instruments) Rick Romero (Rick provide camera, film) Erv Grafwallner, Kelly Oliver Rusty Grant (HP provide equipment) Rick Romero (Rick provide camera, film)
-2:00 P.M.	TRA 653, Mach. Shop	Attach thermocouple to specimen. Perform Heat Test. Have HP survey specimens. Photograph the specimens.	Rusty Grant (Welder provide equipment) Brad Havlovick (Brad provide thermocouple, display unit) Jack Taylor, Kelly Oliver (Jack provide heat oven) Rusty Grant (HP provide equipment) Rick Romero (Rick provide camera, film)
1/30/92 -8:30 A.M.	TRA 689, Lab 98	Perform Initial Leak Test. Have HP survey specimens.	Mike Oates, Kelly Oliver (Mike provide test equipment) Rusty Grant (HP provide equipment)

Completed DOP Reviewed	
Date	Initials

POWER REACTOR PROGRAMS
DETAILED OPERATING PROCEDURE
TITLE PAGE

MISCELLANEOUS EXPERIMENT PROCEDURES

Title

4.8.47	RADIONUCLIDE SHIPPING CAPSULE CERTIFICATION	
DOP Number	Subject	
September 11, 1991		
Issue Date	Last Interval Review	SWR, WR, OR Letter Number
N/A		
Reactor(s)	Cycle Number and or Date	Experiment Number or Loop Design

APPROVED

REVIEWED

See DRR 40625	N/A	N/A
R & IS Manager	BAPL	KAPL
N/A	N/A	
TRA Landlord Operations Manager	ATR Experiments Manager	

DOP Requires:	Yes
Attachments	X
Blanks Filled In	X

Verification of Reviews\Approvals Completed Released by FAS for Publication
<i>S. J. Moran</i>

Procedure Field Change Approvals/Reviews

APPROVALS

R & IS Management	X		
-------------------	---	--	--

Reviews

RS&E Support (Mechanical)		Rad Con	X
RS&E Support (Electrical)		Quality	X
Reactor Safety Analysis (RSA)		Safety and Operations Review Committee (SORC) - For Relevance See PRP SP Manual SP 10.1.1.3	X
ATR Experiments		TRA Maintenance Operations (TRAMO)	X
BAPL		HCL Job Supervisor	
KAPL		Rigging Expert (JS Steps Only)	
Safety & Environmental Compliance	X		

Subject: 4.8.47 -- Radionuclide Shipping Capsule Certification

ISSUE DATE	NO. OF PAGES	DRR NO.
09-11-91	24	40625

DOCUMENT REVISION REQUEST

1 OPER NO. _____ PAGE 1 OF _____

2 REQUESTER B. J. HAYLOVICK	3 DRR DATE 8-17-91	4 DRR NO. 40625
5 DOCUMENT NO. (IF APPLICABLE) DOP 4.3.47		DOCUMENT TITLE RADIOISOTOPE SHIPPING CAPSULE CERTIFICATION
6 CHECK APPLICABLE BLANK PERMANENT CHANGE ☒ TEMPORARY CHANGE _____ BULLETIN _____		7 MANAGER APPROVAL DATE _____

8 PRINT OR TYPE PROPOSED CHANGE — NUMBER EACH CHANGE SEQUENTIALLY IN 1ST COLUMN AND RECORD PAGE AND STEP OR PARAGRAPH NUMBER FOR EACH CHANGE

9 FOR WRITER'S USE

ITEM	PAGE	STEP OR PARA	INSTRUCTIONS: REWRITE PARAGRAPH(S) OR FOR EACH EXTENSIVE CHANGES ATTACH REVISED COPY AND STATE "REVISE PER ATTACHED COPY." FOR NEW DOCUMENT, ATTACH ROUGH DRAFT AND STATE "PREPARE NEW (SP, DOP, ETC.) PER ATTACHED DRAFT."
1	ALL	ALL	THIS IS A NEW DOCUMENT. PREVIOUS PROCEDURE DOES NOT EXIST.

USE CONTINUATION SHEET AS REQUIRED
NEXT ANTICIPATED NEED FOR DOCUMENT WITH THIS REVISION INCORPORATED: DATE/EVENT _____

10. JUSTIFICATION (REASON FOR CHANGE — NUMBER TO CORRESPOND TO ITEM NO. ABOVE)
CAPSULES MUST BE TESTED AND CERTIFIED PRIOR TO USE OF SHIPPING RADIOISOTOPES

11. OTHER DOCUMENTATION AFFECTED:		
DOC. NO.	DRR NO.	DATE COMPLETED

12. ORIGINATING DRR NO: _____

13 REVIEW								
NAME/SIGNATURE	ORG.	DATE	NAME/SIGNATURE	ORG.	DATE	NAME/SIGNATURE	ORG.	DATE
<i>[Signature]</i>	6240	8/14/91				<i>[Signature]</i>	QUALITY	
<i>[Signature]</i>	6500	8/24/91				<i>[Signature]</i>	INDUSTRIAL SAFETY	8/24/91
<i>[Signature]</i>	6210	8/28/91	x 4221			<i>[Signature]</i>	INDEPENDENT REVIEW	8/4/91
<i>[Signature]</i>	6210	8/28/91					FIRE PROTECTION	
				INDUSTRIAL HYGIENE			ENVIRONMENTAL	
14. COMMENTS: APPROVED BY DRC COMPLETED							15. ADDITIONAL DRRS IN THIS DOCUMENT REVISION	
16. DOCUMENT CONTROLLER <i>[Signature]</i>		17. RELEASE CONTROLLER <i>[Signature]</i>		18. RELEASE DATE: 8/17/91		19. DRR COMPLETED DATE: SEP 11 1991		

ISSUED: September 11, 1991 PAGE 1
TITLE: Miscellaneous Experiment Procedures
SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

REFERENCES

Code of Federal Regulations:
Title 49 Code of Federal Regulations 173.469, "Tests for Special Form Radioactive Materials".

DOE Orders:
DOE Order 1540.2, "Hazardous Material Packaging for Transport - Administrative Procedures".

Drawings:
435974--TRA Type I Shipping Container
436956--ATR Type II Shipping Capsule
438917--ATR Percussion Test Billet

International Atomic Energy Agency Safety Series No. 6, "Regulations for the Safe Transport of Radioactive Material", 1973 Revised Edition.

American National Standards Institute Standard N14.5-1987, "American National Standard for Leakage Tests on Packages for Shipment of Radioactive Materials".

Engineering Design File Serial Number RSCC-004, Project Number 015462, "Energy Applied to Specimen from Percussion Billet".

D. K. Morton letter to B. J. Havlovick, DKM-4-91, Worst Case Orientation For Radionuclide Shipping Capsule Testing.

GENERAL

The intent of these tests are to demonstrate the capsules meet DOT requirements for special form. The tests comply with the following requirements: Leak test complies with Title 49 CFR 173.469 (a) (4); Impact test complies with Title 49 CFR 173.469 (b) (1); Percussion test complies with Title 49 CFR 173.469 (b) (2); and Heat test complies with Title 49 CFR 173.469 (b) (4). The specimens contain a metallic form equivalent of the radioactive material to create a realistic test scenario. The capsules will contain low-level radioactivity from entrapment of airborne radioactive material present in the "Hot Cell" during the welding process.

The leak test procedure will be used before and after the impact, percussion, and heat tests to verify what degree the capsules are sealed. Helium Back Pressurizing Test Method of ANSI Standard N14.5-1987 (paragraph A3.9, page B-12) will be the method used. This procedure applies to sealed sources that cannot be filled with helium during final closure. The items must be able to withstand the selected external pressure without damage.

TITLE: Miscellaneous Experiment ProceduresSUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

In this procedure, the helium enters the test item through any leak and is detected subsequently when the test item is placed in vacuum and the helium flows from the leak. The vacuum chamber is connected to a mass spectrometer leak detector. The mass spectrometer leak detector locates leaks by detecting a concentration of helium. It is necessary to use a calibrated leak to prove that the mass spectrometer leak detector can detect a leak in the test item with the required sensitivity.

To conduct the required tests this procedure utilizes eighteen capsule specimens and is divided into the following subsections:

USE
INITIAL LEAK TEST 1-18
IMPACT TEST 1-3, 10-12
PERCUSSION TEST 5-7, 13-15
HEAT TEST 6, 9, 16-18
FINAL LEAK TEST 1-3, 5-18

To complete this procedure a designated individual is responsible to verify each step has been completed. The abbreviations listed here identify the individuals:

(DO) Detector Operator
(TE) Test Engineer
(CO) Chamber Operator

(QI) Quality Inspector
(BO) Billet Operator

MATERIAL AND EQUIPMENT

1. Nine Type II capsule specimens (capsule length = 2.000"). These specimens should be filled with a metallic form equivalent of the radioactive material and plugs welded in place in accordance with EG&G Dwg. No. 436956.
2. Nine Type I capsule specimens (capsule length = 3.000"). These specimens should be filled with a metallic form equivalent of the radioactive material and plugs welded in place in accordance with EG&G Dwg. No. 435974.
3. Leak Detection equipment capable of sensitivities equal to 10^{-4} torr-l/s (1.3×10^{-4} atm-cm³/s) or greater.
4. Container (approximately 1 pint in volume) or equal, one pint of methyl alcohol to utilize as alcohol bath for specimens.
5. Camera and film.
6. Safety Ribbon and "Restricted Area" warning signs.
7. Tape measure, minimum of 30'.
8. Target, one piece of steel plate, 1/4" thick, 4' x 4'.
9. Hard hats and eye protection for each observer of the Impact test.
10. An elevated platform (30 feet elevation).
11. Percussion Billet fabricated in accordance with EG&G Dwg. No. 438917.
12. Six pieces of lead sheet, less than 1" thick, 4" x 4". The hardness of the lead must be between 3.5 - 4.5 on the Vickers scale.
13. Wax string or equal, approximately 24".

ISSUED: September 11, 1991 PAGE 3
TITLE: Miscellaneous Experiment Procedures
SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

14. Clear PVC 1-1/2" Schedule 40 Pipe, approximately 48" long.
15. Clamps to hold PVC pipe.
16. Hanging device to suspend billet in a stable manner prior to free fall.
17. Tape measure, minimum of 40".
18. Eye protection for personnel observing Percussion Test.
19. Wedge of lead, plastic, or wood to prop capsules on edge. See Figure 2, page 17.
20. Heat Chamber capable of sustaining air temperatures in excess of 800° C for more than 10 minutes.
21. Thermocouple with temperature display unit.
22. Clock to measure 10 minutes.
23. Personal Protective Equipment for Heat oven operator: eye protection, insulated gloves, and tongs.
24. Vibrating etching tool.

SPECIFIC PRECAUTIONS

1. As stated in the GENERAL section, the specimens contain NO radioactive material by design, but contain low-level radioactivity by entrapment of airborne radioactive material into the weld on the plugs.
2. ANSI Standard N14.5-1987 paragraph A2.4 states: For leaks expected to be smaller than 10^{-8} atm-cm³/s, wetting of the test item before the leakage test should be avoided whenever possible. When wetting cannot be avoided, the test item is to be dried thoroughly before the test. Due to the high pressures used in the pressure chamber, a system approved by EG&G Quality and/or Safety Engineering must be used. The system should incorporate gas regulators and relief valves; in addition, the chamber should be located in a room constructed of concrete or cinder blocks. This room should be off limits to all personnel during the pressurization process. All operations during the pressurization process must be done remotely.
3. Safety ribbon and warning signs must create a drop area for the Impact Test that cannot be entered by unauthorized personnel.
4. Personnel in area adjacent to drop area for Impact Test should be equipped with hard hats and eye protection.
5. Observing personnel in area of Percussion Test should be equipped with eye protection.
6. Specimens and oven will be hot after the Heat Test. Care must be exercised to avoid burns. Use of personal protective equipment such as tongs, insulated gloves, eye protection and other protective clothing is emphasized.

ISSUED: September 11, 1991 PAGE 4

TITLE: Miscellaneous Experiment Procedures

SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

PREREQUISITES

- ✓ 1. Specimens have been filled with non-radioactive material. This material should be equal in density to the radioactive material intended for shipment within the specimens. HP shall survey specimens prior to performing initial leak test.
- ✓ 2. Specimens have been numbered upon one end plug, using a vibrating etching tool.

The following numbering sequence should be used:

Type I: #1, Type I: #2, Type I: #3,

Type I: #4, Type I: #5, Type I: #6,

Type I: #7, Type I: #8, Type I: #9,

Type II: #10, Type II: #11, Type II: #12,

Type II: #13, Type II: #14, Type II: #15,

Type II: #16, Type II: #17, Type II: #18.

- ✓ 3. Specimens have been photographed.

PROCEDURE

Procedure Started: Time 10:43 Date JAN 28, 1992

INITIAL LEAK TEST

- 160
20
50
1. (TE) Have all Prerequisites been verified?
 2. (QI) A QD inspector certified for leakage tests covered by ANSI Standard N14.5-1987 must be present during the leakage tests performed. Is a certified inspector present?

TITLE: Miscellaneous Experiment ProceduresSUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

3. (QI) Record Equipment Data:

Component Name	I.D. #	Latest Calibration Date
Pressure Gauge:	706548	7-3-91 EXP 6-4-16-92
Pressure Chamber:	417838-1	6-24-91 EXP 6-24-92
Detection Chamber:	815519	1-28-92 1-28-92
Other: He std. 3.43×10^6 - 706682		10-22-90 EXP 10-22-92
Secondary Other: Pressure Gauge	706680	10-24-91 EXP 8-7-92
Other:		
Other:		
Other:		

1-28-92

(DO) All leakage tests are to be performed by qualified operators. Qualifications are based on both training and experience the operator has with the equipment. Record number of hours/days/years (whichever is most applicable) of combined training and experience the operator has on the test equipment to be used:

Operator	Training/Experience
<u>[Signature]</u> MASTER TECHNICIAN SST PHYSICS	12 YEARS

1-28-92

(DO) Place specimens #1-#3 into the pressurization chamber.

1-28-92

(DO) Initiate the pressurization process in accordance with the manufacturer's equipment operating manual.

1-28-92

(DO) Pressurize the chamber to 250 psig.

1-28-92

(QI) Record time when pressurization process stabilizes at 250 psig.

Time of Day: 12:29 (a.m.) (p.m.) (circle one) (Record data for specimens #1-#3 here)

Time of Day: 1:57 (a.m.) (p.m.) (circle one) (Record data for specimens #4-#6 here)

Time of Day: 12:29 (a.m.) (p.m.) (circle one) (Record data for specimens #7-#9 here)

#10 thru 18

ISSUED: September 11, 1991 PAGE 6

TITLE: Miscellaneous Experiment Procedures

SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

INITIAL P = 254.3 ^{BJH}
Final P = 253.5 ^{BJH}
Time of Day: 11 : 11 (a.m.) (p.m.) (circle one) (Record data for specimens #10-#12 here)

Time of Day: 11 : 11 (a.m.) (p.m.) (circle one) (Record data for specimens #13-#15 here)

Time of Day: 11 : 11 (a.m.) (p.m.) (circle one) (Record data for specimens #16-#18 here)

Twenty-five (25) minutes while pressure is held at 250 psig must elapse before proceeding.

11 9. (DO) Initiate de-pressurization in accordance with the manufacturer's equipment operating manual.

1-28-92 10. (QI) Record time when de-pressurization process is at 0 psig.

Time of Day: 1 : 45 (a.m.) (p.m.) (circle one) (Record data for specimen #1-#3 here) ^{27 Oct 92 5:15 PM}

Time of Day: 1 : 45 (a.m.) (p.m.) (circle one) (Record data for specimens #4-#6 here) ^{5:46 Oct 92 1:45 P}

Time of Day: 1 : 45 (a.m.) (p.m.) (circle one) (Record data for specimens #7-#9 here)

Time of Day: 12 : 19 (a.m.) (p.m.) (circle one) (Record data for specimens #10-#12 here)

Time of Day: 12 : 19 (a.m.) (p.m.) (circle one) (Record data for specimens #13-#15 here)

Time of Day: 12 : 19 (a.m.) (p.m.) (circle one) (Record data for specimens #16-#18 here)

11 11. (DO) Remove the specimens from the pressurization chamber.

BJH 12. (TE) Have HP survey specimens after removal from pressurization chamber.

BJH 13. (DO) Submerge the specimens (one at a time) into a methyl alcohol bath, to detect for "gross leaks". If bubbling occurs (disregard bubbles that obviously are just setting on the surface of the specimen), enter under "Results" below, the location upon the specimen where bubbles originate and there is no need to proceed to the detection chamber with that particular specimen. If no bubbling occurs, proceed to the next step. ^{and one following de-pressurization 200 d Contaminated #4 is dropped with heat BJH}

BJH 14. (TE) Have HP survey specimens after removal from methyl alcohol bath and dried. Alcohol bath could become contaminated.

Container #4 was deleted due to radiological reading only. The deletion of #4 has nothing to do with its ability or inability to satisfy the leak test ^{BJH}

ISSUED: September 11, 1991 PAGE 7

TITLE: Miscellaneous Experiment Procedures

SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

- 1.28-12* 15. (DO) Remove specimens from the methyl alcohol bath and thoroughly dry the specimens.
- 1.28-12* 16. (DO) Transfer the specimens (one at a time) to the detection chamber in accordance with proper equipment procedures.
- 1.28-12* 17. (DO) Initiate the detection process in accordance with manufacturer's equipment operating manual. The specimens must be leak tested to a minimum of 10^{-3} torr-l/s (1.3×10^{-4} atm-cm³/s) to be acceptable.

18. (QI) Record test results:

Specimen:	Sensitivity:	Results:
#1	2.45×10^{-9}	7.35×10^{-9}
#2	2.45×10^{-9}	3.67×10^{-9}
#3	2.45×10^{-9}	3.92×10^{-9}
#4	Deleted @	12.5 page 6
#5	2.45×10^{-9}	3.19×10^{-9}
#6	2.45×10^{-9}	3.67×10^{-9} $< 2.45 \times 10^{-9}$
#7	2.45×10^{-9}	3.67×10^{-9}
#8	2.45×10^{-9}	$< 2.45 \times 10^{-9}$
#9	2.45×10^{-9}	$< 2.45 \times 10^{-9}$
#10	2.45×10^{-9}	3.43×10^{-9}
#11	2.45×10^{-9}	$< 2.45 \times 10^{-9}$
#12	2.45×10^{-9}	$< 2.45 \times 10^{-9}$
#13	2.45×10^{-9}	$< 2.45 \times 10^{-9}$
#14	2.45×10^{-9}	$< 2.45 \times 10^{-9}$
#15	2.45×10^{-9}	$< 2.45 \times 10^{-9}$
#16	2.45×10^{-9}	$< 2.45 \times 10^{-9}$
#17	2.45×10^{-9}	$< 2.45 \times 10^{-9}$
#18	2.45×10^{-9}	$< 2.45 \times 10^{-9}$

ISSUED: September 11, 1991 PAGE 8

TITLE: Miscellaneous Experiment Procedures

SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

- BSH 19. (TE) Have HP shall survey specimens after removal from detection chamber.
- 11/12/92 20. (DO) Return to Step 5 and repeat using the next three specimens in the numbered sequence.
- BSH 21. (TE) The specimens must demonstrate leaktightness of:

10^{-4} torr-l/s

or

1.3×10^{-4} atm-cm³/s

based on air at 25° C (77° F) and one atmosphere differential pressure. If any capsule cannot demonstrate leaktightness equal or greater than these values do not use it in any further tests.

Initial Leak Test Completed:

[Signature]
Leak Detector Operator

1-28-92

Date

K.S. Oliver

Certified QD Inspector

Stamp No.

10-95

Expiration Date

1-28-93

Date

Bradley J. Havlicek

Test Engineer

1-28-92

Date

IMPACT TEST

Procedure Started: Time 9:57 Date 1-29-92

- BSH 22. (TE) Secure drop area with safety ribbon.
- BSH 23. (TE) Post Warning Signs at each accessible direction to drop area.
- BSH 24. (TE) Place target in position upon solid surface, such as concrete.
Target Description: SS 1/4" PLATE, 15" x 19"
- BSH 25. (TE) Securely position tape measure in position alongside target, yet not in way of drop area.
- BSH 26. (TE) Have test scenario photographed.
- BSH 27. (TE) From the elevated platform area, suspend the specimen directly above the target, at a height not less than 30' above the target.

ISSUED: September 11, 1991PAGE 9TITLE: Miscellaneous Experiment ProceduresSUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

1-29-92

28. (QI) Height of drop = 30' 1"
- BSH 29. (TE) Release specimen, allowing it to free fall onto the target.
- BSH 30. (TE) If specimen remains upon the target, remove dropped specimen from target. Have HP survey specimens after drop is completed.
- BSH 31. (TE) Return to Step 24 and repeat using the next specimen until specimens #1-#3 & #10-#12 have been dropped.
- BSH 32. (TE) Have the specimens used in this Impact Test photographed.
- BSH 33. (TE) Describe all visible changes to the capsules.

#10 small flat area on ^{edge} solid end
#11 small flat area on edge of rough end
#12 nothing noticeable
#1 small flat area on edge of welded end
#2 three flat areas along side
#3 three flat areas along side

Impact Test completed:

K.S.O. Cin

Quality Assurance Inspector

Date

Bradley J. Harbick

Test Engineer

Date

1-29-92

1-29-92

PERCUSSION TEST

Procedure Started: Time 10:20 Date 1-29-92

1-29-92

34. (QI) Weigh the billet body. Weight_{Body} = 1.232 Kg
- 1-29-92
35. (QI) Weigh the billet faces.

(Weight_{Face} + Weight_{Body} = Total Weight)Weight₁ = 151.39g Total Weight₁ = 1.383 KgWeight₂ = 151.63g Total Weight₂ = 1.384 KgWeight₃ = 151.88g Total Weight₃ = 1.384 KgWeight₄ = 151.89g Total Weight₄ = 1.384 KgWeight₅ = 151.56g Total Weight₅ = 1.384 KgWeight₆ = 151.91g Total Weight₆ = 1.384 Kg

TITLE: Miscellaneous Experiment ProceduresSUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

1-27-92

36. (QI) Inspect the billet in accordance with attached EG&G Drawing No. 438917. Issue a green tag for the billet when completed.

37. (TE) Test the lead sheet for proper hardness. If all six pieces of lead came from the same sheet of lead, testing only one piece is required.

Vickers Hardness = 4.86^{MHV} based on average of 10 readings

38. (TE) Record nominal thickness of lead sheet.

Thickness = 1/4"

39. (BO) Securely fasten clear PVC pipe to edge of bench or table with lower end 9-10 inches above a smooth solid surface.

40. (BO) Securely position the billet hanging device over the centerline of the PVC pipe.

41. (BO) Securely position tape measure alongside PVC pipe, yet not in way of specimen position.

NOTE: Use Step 42 for Type I (#4) capsule specimen only. *#7 substituted for #4 because #4 deleted at step 12.5 page 6*

42. (BO) Place an unused piece of lead sheet directly below the lower end of the PVC pipe. Place upon the lead sheet, in a horizontal position, one specimen. See Fig 1. The specimen must be struck midway along its length. Resume procedure with Step 48.

NOTE: Use Step 43 for Type I (#5) capsule specimen only.

43. (BO) Place an unused piece of lead sheet directly below the lower end of the PVC pipe. Place upon the lead sheet, in the tilted position, one specimen. Use a wedge of lead, plastic or wood to serve as a prop. See Fig 2. The desired point of contact for the billet upon the specimen is along the edge where the end plug is welded to the tubular shell. Resume procedure with Step 48.

NOTE: Use Step 44 for Type I (#6) capsule specimen only.

44. (BO) Place an unused piece of lead sheet directly below the lower end of the PVC pipe. Place upon the lead sheet, in a vertical position, one specimen. See Fig 3. The desired point of contact for the billet upon the specimen is the top surface of the specimen. Resume procedure with Step 48.

ISSUED: September 11, 1991 PAGE 11
TITLE: Miscellaneous Experiment Procedures
SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

NOTE: Use Step 45 for Type II (#13) capsule specimen only.

- E. G. / 47* 45. (B0) Place an unused piece of lead sheet directly below the lower end of the PVC pipe. Place upon the lead sheet, in a horizontal position, one specimen. See Fig 1. The specimen must be struck midway along its length. Resume procedure with Step 48.

NOTE: Use Step 46 for Type II (#14) capsule specimen only.

- E. G. / 47* 46. (B0) Place an unused piece of lead sheet directly below the lower end of the PVC pipe. Place upon the lead sheet, in the tilted position, one specimen. Use a wedge of lead, plastic or wood to serve as a prop. See Fig 2. The desired point of contact for the billet upon the specimen is along the edge where the end plug is welded to the tubular shell. Resume procedure with Step 48.

NOTE: Use Step 47 for Type II (#15) capsule specimen only.

- E. G. / 47* 47. (B0) Place an unused piece of lead sheet directly below the lower end of the PVC pipe. Place upon the lead sheet, in a vertical position, one specimen. See Fig 3. The desired point of contact for the billet upon the specimen is the top surface of the specimen. Resume procedure with Step 48.

NOTE: The following steps apply to all specimens.

- 1-29-92*
692
25
67 48. (QI) Suspend the billet from the billet hanging device using the wax string or equal. The billet must strike the specimens with a force equivalent to the free fall of 1.4 kg (3 lbs.) through 1 meter (3.3 ft.). The height from the upper most point of the specimen to the face surface of the billet must equal or exceed the value calculated from the formula included below:

Height of Drop = Potential Energy / mg

where: Height = unknown, Ft (meter)

Potential Energy = 9.9000 Lbs-Ft (1400 meter-grams)

m = mass of billet, slugs (grams)

g = 32.1529 Ft/s² (9.8002 m/s²)

TITLE: Miscellaneous Experiment Procedures

SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

49. (QI) Height of billet, = 46"(QI) Height of billet₂ = 39.9"(QI) Height of billet₃ = 39.9"(QI) Height of billet₄ = 39.9"(QI) Height of billet₅ = 39.9"(QI) Height of billet₆ = 39.9"BSH

50. (TE) Have test scenario photographed. NOTE: This step is for documentation purposes and is required for only two specimens.

BSH

51. (BO) Apply a flame to the wax string or equal, allowing the billet to free fall upon the specimen. Do not use scissors to cut wax string. Use of scissors could deflect billet and create contact between the billet and the clear PVC pipe.

BSH

52. (TE) Have test scenario photographed following free fall to document location billet strikes specimen.

BSH53. (TE) Have HP survey specimens after percussion test. NOTE: This step is required for all specimens. N/A

54. (QI) Examine face end of billet. If face is dented, nicked or anything other than flat, change the end piece. Return to the step that directs use of next specimen and repeat until specimens #4-#6 & #13-#15 have been tested.

BSH

55. (TE) Have the specimens used in this Percussion Test photographed.

BSH

56. (TE) Describe all visible changes to the capsules.

#5 Weld area flattened slightly
#6 No noticeable change
#7 Side indented by billet
#13 Side indented by billet
#14 No noticeable change
#15 No noticeable change

Percussion Test completed:

E. H. Chapman
Billet Operator1/29/92
DateE. S. O. S. in
Quality Assurance Inspector 1-29-92
DateBradley J. Harlock
Test Engineer1-29-92
Date

Fig 1. Billet striking mid-point of capsule in horizontal position.

Title: Miscellaneous Experiment Procedures

Subject: 4.8.47 -- Radionuclide Shipping Capsule Certification

Fig 2. Billet striking edge of plug/tubular shell of capsule in tilted position.

Title: Miscellaneous Experiment Procedures

Subject: 4.8.47 -- Radionuclide Shipping Capsule Certification

Fig 3. Billet striking top of capsule in vertical position.

ISSUED: September 11, 1991 PAGE 16

TITLE: Miscellaneous Experiment Procedures

SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

HEAT TEST

Procedure Started: Time 12:35 Date 1-29-92

1-29-92
57. (QI) Record Equipment Data:

Component Name	I.D. #	Latest Calibration Date
Thermocouple:	<u>Part # K280248U</u>	<u>00-15-29036-5</u> NEW PURCHASE
Display Unit:	<u># 215690</u>	<u>12-10-91 EXP 8-30-92</u> CALIBRATED TO ICE POINT REFERENCE
Other: LOW LIMIT THERMISTAT	<u>N/A</u>	<u>1-14-92 EXP 1-14-93</u>
Other: HIGH LIMIT THERMISTAT	<u>N/A</u>	<u>1-14-92 EXP 1-14-93</u>
Other: TEMP. CHART	<u>N/A</u>	<u>1-18-92 EXP 1-18-93</u>
Other: TEMP CHART	<u>N/A</u>	<u>1-19-92 EXP 1-22-93</u>

1-29-92
58. (CO) Place specimens into heat chamber.

BSH
59. (TE) Have the thermocouple attached onto the end plug of one Type I capsule specimen. Since the Type I capsule specimen is larger than the Type II capsule specimen (and should heat slower) the Type I capsule specimen will serve as the specimen for temperature verification.

1-29-92
P.D.J.
60. (CO) Initiate the heating process in accordance with manufacturer's equipment operating manual.

1-29-92
61. (QI) Record time when thermocouple reading is minimum 800° C (1472° F).

Time of Day: 1 : 21 : 00 (a.m.) (p.m.) (circle one)

Ten minutes (+30 seconds, -0 seconds) while thermocouple reading equals or exceeds 800° C (1472° F) must elapse before terminating the test.

1-29-91
P.D.J.
62. (CO) Terminate the heating process in accordance with proper equipment procedures after 10 minutes (+30 seconds, -0 seconds) at 800° C (1472° F).

1-29-92
63. (QI) Record time when heating is terminated.

Time of Day: 1 : 32 : 23 (a.m.) (p.m.) (circle one)

TITLE: Miscellaneous Experiment ProceduresSUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

1-29-92
64. (CO) After specimens have cooled (to approximately 35° C or 95° F), remove specimens from heat chamber in accordance with standard operating procedures for the equipment. Use personal protective clothing, insulated gloves, eye protection and tongs to prevent any possible burns. *dec not needed B. J. 1-29*

1-29-92
65. (QI) Record time when specimens are removed from heat chamber.

Time of Day: 1:32:23 (a.m.) (p.m.) (circle one)

BJA 66. (TE) Have HP survey specimens after removal from heat chamber. Photograph the specimens used in this heat test. *Not needed*

BJA 67. (TE) Have the specimens used in this Heat Test photographed.

BJA 68. (TE) Describe all visible changes to the capsules.

all capsules changed very dark in color.

Heat Test completed:

Paul D. Southworth 1-29-92
Heat Chamber Operator Date

K.S. O. S. in 1-29-92
Quality Assurance Inspector Date

Bradley J. Harbuck 1-29-92
Test Engineer Date

FINAL LEAK TEST

Procedure Started: Time 9:28 AM Date 1-30-92

1-30-92
69. (QI) A QD inspector certified for leakage tests covered by ANSI Standard N14.5-1987 must be present during the leakage tests performed. Is a certified inspector present?

1-30-92
70. (QI) Record Equipment Data:

Component Name	I.D. #	Latest Calibration Date
----------------	--------	-------------------------

Pressure Gauge:	<u>706548</u>	<u>7-3-91 EXP 4-16-92</u>
-----------------	---------------	---------------------------

Pressure Chamber:	<u>417836-1</u>	<u>6-24-91 EXP 6-24-92</u>
-------------------	-----------------	----------------------------

TITLE: Miscellaneous Experiment ProceduresSUBJECT: 4.8.47 -- Radionuclide Shipping Capsule CertificationDetection Chamber: 215519 NOT REQ'DOther: He Std. 3.4340⁻⁶ 706682 10-23-90 EXP 10-23-92Other: Secondary Pressure Range 706680 10-24-91 EXP 8-7-92

Other: _____

Other: _____

Other: _____

- 1.30.92 71. (DO) All leakage tests are to be performed by qualified operators. Qualifications are based on both training and experience the operator has with the equipment. Record number of hours/days/years (whichever is most applicable) of combined training and experience the operator has on the test equipment to be used:

<u>Operator</u>	<u>Training/Experience</u>
<u>M. J. [Signature]</u>	<u>MASTER TECHNICIAN 12+ YEARS</u>

- 1.30.92 72. (DO) Place specimens #1-#3 into the pressurization chamber.

- 1.30.92 73. (DO) Initiate the pressurization process in accordance with the manufacturer's equipment operating manual.

- 1.30.92 74. (DO) Pressurize the chamber to 250 psig.

- 1-30-92 75. (QI) Record time when pressurization process stabilizes at 250 psig.

$P_L = 255.2$
 $P_i = 253.6$ Time of Day: 10:18 (a.m.) (p.m.) (circle one) (Record data for specimens #1-#3 here) #4 deleted at Step 12.5 page

Time of Day: 10:18 (a.m.) (p.m.) (circle one) (Record data for specimens ~~#4~~ #6 here) #5 9:47 a.m.

Time of Day: 10:18 (a.m.) (p.m.) (circle one) (Record data for specimens ~~#7~~ #9 here) #7 9:47 a.m.

$P_i = 254.4$ Time of Day: 9:47 (a.m.) (p.m.) (circle one) (Record data for specimens #10-#12 here)

$P_i = 254.2$ Time of Day: 9:47 (a.m.) (p.m.) (circle one) (Record data for specimens #13-#15 here)

Time of Day: 9:47 (a.m.) (p.m.) (circle one) (Record data for specimens #16-#18 here)

Twenty-five (25) minutes while pressure is held at 250 psig must elapse before proceeding.

TITLE: Miscellaneous Experiment ProceduresSUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

- 1-30-92 76. (DO) Initiate de-pressurization in accordance with the manufacturer's equipment operating manual.
- 1-30-92 77. (QI) Record time when de-pressurization process is at 0 psig.

Time of Day: 10 : 47 (a.m.) (p.m.) (circle one) (Record data for specimen #1-#3 here)

Time of Day: 10 : 47 (a.m.) (p.m.) (circle one) (Record data for specimens #4-#6 here) #5 + #6 #4 deleted at Step 125f

Time of Day: 10 : 47 (a.m.) (p.m.) (circle one) (Record data for specimens #7-#9 here) #7 + #9 #8 10 : 13 a.m.

Time of Day: 11 : 13 (a.m.) (p.m.) (circle one) (Record data for specimens #10-#12 here)

Time of Day: 10 : 13 (a.m.) (p.m.) (circle one) (Record data for specimens #13-#15 here)

Time of Day: 10 : 13 (a.m.) (p.m.) (circle one) (Record data for specimens #16-#18 here)

- 1-30-92 78. (DO) Remove the specimens from the pressurization chamber.

- 1-30-92 79. (TE) Have HP survey specimens after removal from pressurization chamber. N/A

- 1-30-92 80. (DO) Submerge the specimens (one at a time) into a methyl alcohol bath, to detect for "gross leaks". If bubbling occurs (disregard bubbles that obviously are just setting on the surface of the specimen), enter under "Results" below, the location upon the specimen where bubbles originate and there is no need to proceed to the detection chamber with that particular specimen. If no bubbling occurs, proceed to the next step.

- 1-30-92 81. (TE) Have HP survey specimens after removal from methyl alcohol bath and dried. Alcohol bath could become contaminated. N/A

- 1-30-92 82. (DO) Remove specimens from the methyl alcohol bath and thoroughly dry the specimens.

- 1-30-92 83. (DO) Transfer the specimens (one at a time) to the detection chamber in accordance with proper equipment procedures.

- 1-30-92 84. (DO) Initiate the detection process in accordance with manufacturer's equipment operating manual. The specimens must be leak tested to a minimum of 10^{-4} torr-l/s (1.3×10^{-4} atm-cm³/s) to be acceptable.

TITLE: Miscellaneous Experiment ProceduresSUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

1-30-92

85. (QI) Record test results:

Specimen:	Sensitivity:	Results:
#1	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#2	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#3	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#4	3.79 x 10⁻⁹	DELETED AT STEP 12.5 page 6
#5	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#6	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#7	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#8	3.79×10^{-9}	3.27×10^{-8}
#9	3.79×10^{-9}	2.27×10^{-7}
#10	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#11	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#12	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#13	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#14	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#15	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#16	3.79×10^{-9}	4.55×10^{-9}
#17	3.79×10^{-9}	$< 3.79 \times 10^{-9}$
#18	3.79×10^{-9}	$< 3.79 \times 10^{-9}$

 $3.79 \times 10^{-9} \times 60$

Note TC attache to #9 Caps. and Magnesium oxide, TC probably had He atoms.

B574 86. (TE) Have HP survey specimens after removal from detection chamber. N/A

1-30-92 87. (DO) Return to Step 72 and repeat using the next three specimens in the numbered sequence.

ISSUED: September 11, 1991 PAGE 21

TITLE: Miscellaneous Experiment Procedures

SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

Final Leak Test completed:

<u><i>M. C. Oates</i></u>		<u>1-30-92</u>	
Leak Detector Operator		Date	
<u>K. S. Oliver</u>		<u>11-93</u>	<u>1-30-92</u>
Certified QD Inspector	Stamp No.	Expiration Date	Date
<u><i>Bradley J. Havlicek</i></u>		<u>1-30-92</u>	
Test Engineer		Date	

TITLE: Miscellaneous Experiment Procedures

SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

TITLE: Miscellaneous Experiment Procedures

SUBJECT: 4.8.47 -- Radionuclide Shipping Capsule Certification

NOTES

1. REMOVE ALL BURRS AND SHARP EDGES
2. MARK BULLET ASSEMBLY PER STD FORM-202 WITH 48017-1 ASSEMBLY
3. SECURE ITEM 3 TO ITEM 1 WITH ITEM 6 PER MANUFACTURER'S INSTRUCTIONS

-1 ASSEMBLY

(C) DETAIL

(C) DETAIL

ITEM	QTY	DESCRIPTION	UNIT	REMARKS
1	1	1/4 ZUNC-20 8 75	INCHES	
2	1	1/4 ZUNC-20 8 50	INCHES	
3	1	1/4 ZUNC-20 8 75	INCHES	
4	1	1/4 ZUNC-20 8 50	INCHES	
5	1	1/4 ZUNC-20 8 75	INCHES	
6	1	1/4 ZUNC-20 8 50	INCHES	
7	1	1/4 ZUNC-20 8 75	INCHES	
8	1	1/4 ZUNC-20 8 50	INCHES	
9	1	1/4 ZUNC-20 8 75	INCHES	
10	1	1/4 ZUNC-20 8 50	INCHES	
11	1	1/4 ZUNC-20 8 75	INCHES	
12	1	1/4 ZUNC-20 8 50	INCHES	
13	1	1/4 ZUNC-20 8 75	INCHES	
14	1	1/4 ZUNC-20 8 50	INCHES	
15	1	1/4 ZUNC-20 8 75	INCHES	
16	1	1/4 ZUNC-20 8 50	INCHES	
17	1	1/4 ZUNC-20 8 75	INCHES	
18	1	1/4 ZUNC-20 8 50	INCHES	
19	1	1/4 ZUNC-20 8 75	INCHES	
20	1	1/4 ZUNC-20 8 50	INCHES	
21	1	1/4 ZUNC-20 8 75	INCHES	
22	1	1/4 ZUNC-20 8 50	INCHES	
23	1	1/4 ZUNC-20 8 75	INCHES	
24	1	1/4 ZUNC-20 8 50	INCHES	
25	1	1/4 ZUNC-20 8 75	INCHES	
26	1	1/4 ZUNC-20 8 50	INCHES	
27	1	1/4 ZUNC-20 8 75	INCHES	
28	1	1/4 ZUNC-20 8 50	INCHES	
29	1	1/4 ZUNC-20 8 75	INCHES	
30	1	1/4 ZUNC-20 8 50	INCHES	
31	1	1/4 ZUNC-20 8 75	INCHES	
32	1	1/4 ZUNC-20 8 50	INCHES	
33	1	1/4 ZUNC-20 8 75	INCHES	
34	1	1/4 ZUNC-20 8 50	INCHES	
35	1	1/4 ZUNC-20 8 75	INCHES	
36	1	1/4 ZUNC-20 8 50	INCHES	
37	1	1/4 ZUNC-20 8 75	INCHES	
38	1	1/4 ZUNC-20 8 50	INCHES	
39	1	1/4 ZUNC-20 8 75	INCHES	
40	1	1/4 ZUNC-20 8 50	INCHES	
41	1	1/4 ZUNC-20 8 75	INCHES	
42	1	1/4 ZUNC-20 8 50	INCHES	
43	1	1/4 ZUNC-20 8 75	INCHES	
44	1	1/4 ZUNC-20 8 50	INCHES	
45	1	1/4 ZUNC-20 8 75	INCHES	
46	1	1/4 ZUNC-20 8 50	INCHES	
47	1	1/4 ZUNC-20 8 75	INCHES	
48	1	1/4 ZUNC-20 8 50	INCHES	
49	1	1/4 ZUNC-20 8 75	INCHES	
50	1	1/4 ZUNC-20 8 50	INCHES	

EG-8
 PERMANENT RECORD
 ASSEMBLY AND INSTRUCTIONS
 1/11/91

SCHED. NO. F09PM147-A

SITE WORK RELEASE # RI063

EG&G IDAHO, INC.

FIELD CHANGE #: 1 2 3

PAGE 1

PLNR: J.R.AUBREY

SHORT TITLE: FAB SPECIAL FORM SHIPPING CONTAINERS

CHARGE NO: 121210002

DATE RQSTD: 03/06/91

DATE REQUIRED: 04/15/91

NEED EVENT: 041591

AREA: TRA

SUB-AREA: MTR

BLDG: 653

RM: SHOPS EQ ID: NA

REQUESTOR: M.J.SHERICK

EXT: 6-4212

HOUR LIMIT:

44.0 BY JRA

SWR INPUT BY: M.J.SHERICK

EXT: 6-4212

SAFETY RVW RQD: Y

INITIALS: MJS

OTH SAF DOC: N

PRIORITY: 07

TAGOUT: N

RAD-CON RVW RQD: N

INITIALS:

IH RVW RQD: N

INITIALS:

SWF RQD: N

ALARA EVAL: N

SSWF RQD: N

RHA RQD: N

ECL RQD: N

QUAL RVW RQD: Y

INITIALS: MJS

QUAL LEVEL: B+

CLEAN CODE: C

REQ MGR RVW: M.J.SHERICK

03/06/91

MATERIAL LIST INCLUDED: Y

QUAL RVW:

C.D.COOPER

03/12/91

OP CHECKOUT REQ'D: N

SAF RVW:

J.C.BATIE

03/12/91

NA

RAD-CON RVW:

IH RVW:

BUD MGR RVW: M.J.SHERICK

03/06/91

FAC MGR RVW: M.C.SMITH

03/20/91

COMPLETED DT-INITIALS

SUP'R. APPR'L:

DATE: 4/9/91

JOB-DESCRIPTION:

FABRICATE ALL THE PARTS TO SUPPLY 12 EACH CONTAINERS FOR CERTIFICATION.
DELIVER THE COMPLETED CONTAINERS TO GENE KANEMOTO AT TRA628.
BUILD PER EG&G DRAWINGS 436956, REV. A AND 435974, REV. A.

THIS SWR IS TO BE CONTROLLED BY A DETAILED SWR PROCEDURE.

SWR CLOSEOUT REVIEW/APPROVAL

REQUESTOR:

DATE: 8/29/91

RESP FOREMAN: B.A.BRIGGS

DATE: 8/20/91

QUAL SUPERVISOR:

DATE: 11/18/91

FAC SUPERVISOR:

DATE: 11/19/91

CRAFT

MACH

WELD

QUAL

HOURS

DATE CMPLD

38.0

6.0

7/10/91

DATE PRINTED: 03/26/91

PRINTOUT NUMBER:

8

DOP NUMBERS

DOP NO	REV	DOP NO	REV	DOP NO	REV

DRAWINGS

DRAWING	REV	DRAWING	REV	DRAWING	REV
6956	A	435974			

NCR'S

NCR	REV	NCR	REV	NCR	REV

FCF'S

FCF	REV	FCF	REV	FCF	REV

OTHER FORMS

D7022

4. QUALITY ASSURANCE PROVISIONS

4.1 Inspection and Acceptance Criteria. Verification that the process has been complied with shall constitute acceptance to the level specified. Components that do not meet the requirements of this standard shall be subject to rejection. When an invoked cleaning level cannot be verified by one of the following inspections, the process for controlling the cleanliness of the part to the required level shall be specified and approved before use. | A

4.1.1 Level A. The item shall be inspected to the requirements of Levels D and C. If found acceptable, a minimum of 200 cm³ of the last portion of the final flush or rinse fluid from all cleaned surfaces of the item shall be accepted as clean to Level A when the particle count and size in the final flush or rinse fluid does not exceed the limits specified in Table II.

4.1.2 Level B. The item shall be inspected to the requirements of Levels D and C. If found acceptable, a minimum of 200 cm³ of the last portion of the final flush or rinse fluid from all cleaned surfaces of the item shall be accepted as clean to Level B when the particle count and size in the final flush or rinse fluid does not exceed the limits specified in Table II.

4.1.3 Level C. The item shall be inspected to the requirement of Level D. If found acceptable, it shall be wiped with a hard filter paper, or a white lint-free cloth or tissue moistened with acetone or alcohol. The item shall be accepted as clean to Level C when there is no discoloration of the wiping cloth or when the surface is free of physical contaminants revealed by the wipe test. Adherent metal oxides, other than iron oxide, shall not be considered a contaminant unless so designated. Illumination in inspection areas shall provide a glare-free light intensity of at least 100 ft. candles on the surfaces being inspected.

4.1.4 Level D. The item shall be examined visually under a concentrated light source. It shall be accepted as clean to Level D when it is visually free from grease, cutting oils, loose particles, chips and other materials not forming a part of the finished item.

4.2 Records. The supplier or cleaning organization shall maintain a current and complete file of all records of inspection, examination, and monitoring data pertaining to cleaning and cleanliness control. | A

4.3 Access. Inspection personnel shall have access to any area where work associated with cleaning and cleanliness control is performed, and to all records pertaining to the cleaning or cleanliness of items invoked by this standard.

REQUESTOR: M J SHERICK

6-4212

PLANNER: JOHN R AUBREY

6-4287

DB TITLE: FAB SPECIAL FORM SHIPPING CONTAINERS.

SWR NUMBER: RI063

TOTAL MATERIAL COST

0.00

CHARGE NUMBER: 121210002

O = ORIGINATOR P = PLANNER

MATL REQUIRED: 00/00/00

ITEM NO	QTY	UNIT	QL	DRAWING	FURN	REQUISITION	QA	STORAGE	MATERIAL
				ITEM REV	BY	QD CODE NO	STAMP DATE	LOCATION	COST
ON ORD PARTL READY									
1	1	EA.	B+	435974	0	91A0277	4-10-91	MACH. SHOP	0.00
				7	NC				X

ESC BAR ROUND STAINLESS STEEL TYPE 304L ASTM-A-276 3/4" DIA. CRFT MACH

USE MATERIAL LEFT FROM RI059

2	1	EA.	B+	435974	0	91A0318	4-10-91	PIPE R1-2	0.00
				6	NC				X

ESC TUBE, 3/4" X .035 WALL, 304L SSTL, ASME SA213

CRFT MACH

3	1	EA.	B+	435974	0	91A0276	4-10-91	MACH. SHOP	0.00
				4,5	NC				X

ESC BAR ROUND STAINLESS STEEL TYPE 304L ASTM-A-276 5/8" DIA. CRFT MACH

USE MATERIAL LEFT FROM RI059

4	1	EA.	B+	436956	0	91A0278	4-10-91	MACH. SHOP	0.00
				3,4	NC				X

ESC BAR ROUND STAINLESS STEEL TYPE 410 ASTM-A-276 5/8" DIA. CRFT MACH

USE MATERIAL LEFT FROM RI059

5	1	AR.	B+	435974	P	NA	7-9-91	TOOL CRIB	0.00
				8	NC				X

ESC WELD FILLER METAL ER308

CRFT WELD

6	24	EA.	B-	NA	0	NA		MACH. SHOP	0.00
				NA	NC	NA			X

ESC PLASTIC CONTAINERS

CRFT WELD

Detailed SWR Procedure

SWR RI063

NOTE: This procedure requires verbatim compliance to the sequence and content of the integrated work instructions. Any deviations, unless they're explicitly identified in the integrated work instructions require prior approval through the use of a SWR Field Change Sheet.

Q NO CRAFT

10.00 QUAL
INITIAL AND DATE: 4/10/91

VERIFY THE QUALITY LEVEL B+ MATERIALS ON THE ATTACHED MATERIAL LIST EXCEPT THE WELD FILLER METAL WHICH WILL BE VERIFIED ON THE FORM 005.

10.50 MACH
INITIAL AND DATE: *ADS* 4/26/91

BUILD THE PARTS TO SUPPLY 12 EACH OF THE FOLLOWING ASSEMBLIES PER THE ATTACHED DRAWINGS 436956, REV. A AND 435974, REV. A. CLEAN ALL FABRICATED PARTS WITH A CLEAN CLOTH DAMPENED WITH ALCOHOL OR ACETONE.

11.00 QUAL
INITIAL AND DATE: 7/9/91

VERIFY THE DIMENSIONS ARE WITHIN THE DRAWING TOLERANCES.

12.00 QUAL
INITIAL AND DATE: 7/9/91

CF EXP 7-29-91

VERIFY WELDER QUALIFIED TO INEL WELD PROCEDURE SPECIFICATION S-4.1. GENERATE FORM 005.

13.00 WELD
INITIAL AND DATE: *SW* 7/10/91

see FC #3
WELD ITEM SEVEN TO ITEM SIX, ONE PLACE, FOR EACH OF THE CAPSULE ASSEMBLIES PER THE ATTACHED DRAWING 435974, REV. A USING INEL WELD PROCEDURE SPECIFICATION S-4.1 WITH WELD FILLER METAL ER308.

5210

14.00 WELD
INITIAL AND DATE: *SW* 7/10/91

CLEAN ALL PARTS TO CLEANLINESS LEVEL C REQUIREMENTS. WIPE CLEAN WITH A CLOTH DIPPED IN ALCOHOL.

14.50 QUAL
INITIAL AND DATE: 7/10/91

VERIFY FABRICATED PARTS CLEAN TO STD7022 LEVEL C.

15.00 WELD
INITIAL AND DATE: *QJL* 7/10/91

PACKAGE EACH ASSEMBLY IN INDIVIDUAL PLASTIC CONTAINERS.

CHED. NO. P09PM071

ANNING SHEET FOR RI063

03/26/91

EQ NO CRAFT

16.00

WELD

INITIAL AND DATE:

JK 2/10/91

DELIVER THE FINISHED CONTAINERS TO GENE KANEMOTO AT TRA-628.

FE: 05/29/91 SWR FIELD CHANGE PAGE: 1
=====

NO.: RI063	FC#: 1	TITLE: FAB SPECIAL FORM SHIPPING CONTAINERS.
ARGE#: 121210002	RQSTR: MJ SHERICK	DATE: 04/18/91 PH: 6-4212
REQ: N	PROCESSED BY: _____	DATE: __/__/__

----- TYPE OF CHANGE -----
CANCEL _ HRS X DUE DATE _ QUAL _ SFTY _ NCR _ DWG X PLNG _ OTHER _

UPDATE INFO:	CRAFT	HRS	CRAFT	HRS	CRAFT	HRS	CRAFT	HRS
	MACH	30.0		0.0		0.0		0.0
		0.0		0.0		0.0		0.0

APPROVALS			
ALITY:	CD COOPER	DATE:	04/18/91
ETY:	JC BATIE	DATE:	04/23/91
CON SAFETY:		DATE:	__/__/__
SAFETY:		DATE:	__/__/__
QUESTING MANAGER:	MJ SHERICK	DATE:	04/18/91
GET MANAGER:	MC SMITH	DATE:	05/29/91
ILITY MANAGER:	MC SMITH	DATE:	05/29/91

=====

STIFICATION:
ED DRAWING NOTE

ANGE DESCRIPTION:
CORPORATE REV B OF DRAWINGS 436956 AND 435974 INTO THE WORK PACKAGE.

=====

Change Form Serial Number

Prepared By *AKS*

Date *4/12/91*

Reason For Change

Change TOLERANCE

TYPE OF CHANGE AND DOCUMENT

DCN ☒ ADGN ☐ DCN ☐ Pre-Released ADGN ☐ Void After ☐

Master Facility Drawing ☐
MFD Key Drawing ☐
Other Drawing ☒

PROGRAM OR PROJECT AUTHORIZATION

1-12-91 *Lawrence E. Lawrence for R.T. Service*

Item

IDAHO NATIONAL ENGINEERING LABORATORY DRAWING CHANGE FORM

Sheet *1* of *1*

APPROVAL	DATE	APPROVAL	DATE
<i>[Signature]</i>	<i>4/10/91</i>	<i>[Signature]</i>	<i>4/12/91</i>
<i>[Signature]</i>	<i>4-15-91</i>	<i>[Signature]</i>	<i>4/12/91</i>
<i>[Signature]</i>	<i>4/10/91</i>	<i>[Signature]</i>	<i>4/12/91</i>
<i>[Signature]</i>	<i>4-15-91</i>		

INDEX CODE NUMBER

Area	Dwg. Type	Cl.	Orig.	Serial
<i>533</i>	<i>0670</i>	<i>47</i>	<i>220</i>	<i>1</i>

Drawing Number

436956

Revision

B

Drawing Title

*ATR
TYPE II Shipping Capsule
ASSEMBLY AND DETAILS*

1. ADD NOTE: 4 UNLESS OTHERWISE SPECIFIED 4 PLACE DECIMALS

SHALL HAVE A TOLERANCE OF:

.XXXX = ± .0005

18
1D

Date 4/12/91

Reason For Change

CHANGE TOLERANCE

TYPE OF CHANGE AND DOCUMENT

DCR ☐ ADCN ☒ DCN ☐ Pre-Released ADCN ☐ Valid After ☐Master Facility Drawing ☐MFD Key Drawing ☐Other Drawing ☒

PROGRAM OR PROJECT AUTHORIZATION

Date 4-11-91 John H. Hansen for J.R. Nasser

Zone

Item

18

1. ADD NOTE :

6. UNLESS OTHERWISE SPECIFIED 4 PLACE
DECIMALS SHALL HAVE A TOLERANCE OF:

. XXXX =

± .0005

IDAHO NATIONAL ENGINEERING LABORATORY

DRAWING CHANGE FORM

Sheet 1 of 1

APPROVAL

DATE 4/12/91 APPROVAL W. D. L. DATE 4/12/91DATE 4-15-91 APPROVAL W. D. L. DATE 4/12/91DATE 4/12/91 APPROVAL W. D. L. DATE 4/12/91DATE 4-15-91 APPROVAL W. D. L. DATE 4/12/91DATE 4-15-91 APPROVAL W. D. L. DATE 4/12/91

INDEX CODE NUMBER

Area 5330670 Dwg. Type 47220 CL 47220 Orig. 47220 Serial 47220

Drawing Number

435974

Revision

B

Number of Sheets

Drawing Title

TRA
TYPE I Shipping Container
ASSEMBLY AND DETAILS

DATE: 05/29/91

SWR FIELD CHANGE

PAGE: 1

=====

IR NO.: RI063	FC#: 2	TITLE: FAB SPECIAL FORM SHIPPING CONTAINERS.
ARGE#: 121210002	RQSTR: MJ SHERICK	DATE: 05/24/91 PH: 6-4212
OF REQ: N	PROCESSED BY: _____	DATE: __/__/__

=====

----- TYPE OF CHANGE -----

CANCEL _ HRS X DUE DATE _ QUAL _ SFTY _ NCR _ DWG X PLNG _ OTHER _

IS UPDATE INFO:	CRAFT	HRS	CRAFT	HRS	CRAFT	HRS	CRAFT	HRS
	MACH	40.0	_____	0.0	_____	0.0	_____	0.0
	WELD	10.0	_____	0.0	_____	0.0	_____	0.0

===== APPROVALS =====

QUALITY:	JB MONCUR	DATE: 05/24/91
SAFETY:	TD HOSKINS	DATE: 05/28/91
AD-CON SAFETY:	_____	DATE: __/__/__
I SAFETY:	_____	DATE: __/__/__
REQUESTING MANAGER:	MJ SHERICK	DATE: 05/24/91
BUDGET MANAGER:	MJ SHERICK	DATE: 05/24/91
ACILITY MANAGER:	MC SMITH	DATE: 05/29/91

=====

JUSTIFICATION:
DRAWING CHANGE

CHANGE DESCRIPTION:
INCORPORATE REV C OF DWG.#436956 AND 435974 INTO THE WORK PACKAGE.

=====

CHANGE DOCUMENT SERIAL NUMBER	PREPARED BY <i>[Signature]</i>
DATE 5/23/71	
REASON FOR CHANGE <i>Design Change</i>	
TYPE OF CHANGE AND DOCUMENT	
DCR	ADCN
☒	☐
DCN	PRE-RELEASED ADCN
☒	☐
VOID AFTER	
MASTER FACILITY DRAWING	SPECIFICATION
☐	☐
MFD KEY DRAWING	OTHER DOCUMENT
☐	☐
OTHER DRAWING	
☒	
CHANGE AUTHORIZATION J.E. Brauer by B.J. Henner DATE 5/23/71	

IDaho NATIONAL ENGINEERING LABORATORY			
DOCUMENT CHANGE NOTICE			
SHEET 1 OF 1			
DESIGN	DESIGN ACTIVITY	MFG ENGR	
<i>[Signature]</i>	B.J. Henner		
CHECKED	STRESS	QUALITY	TELEPH
<i>[Signature]</i>		<i>[Signature]</i>	
INCORP	MATERIALS PROCESSES	REQUESTER	
		<i>[Signature]</i>	
RELEASE DATE	TELEPH		
5/23/71	<i>[Signature]</i>		

INDEX CODE NUMBER			
AREA	DWG TYPE	CL	ORIG
533	0670	47	220
DOCUMENT NUMBER			REVISION
435974			C
NUMBER OF SHEETS			
1			
DOCUMENT TITLE			
TRA			
TYPE I SHIPPING CONTAINER			
ASSEMBLY AND DETAILS			

18

4

1 Change Note

WAS: .0001 TO .0005

IS: .000 - .015

18

5

2 Change Note

WAS: .0001 TO .0004

IS: .000 - .015

CHANGE DOCUMENT SERIAL NUMBER	PREPARED BY <i>[Signature]</i>		
REASON FOR CHANGE <i>Design Change</i>	DATE 5/23/91		
TYPE OF CHANGE AND DOCUMENT			
DCR	ADCN	DCN	PRE-RELEASED ADCN
☐	☒	☐	☐
VOID AFTER			
MASTER FACILITY DRAWING ☐ SPECIFICATION ☐			
MFD KEY DRAWING ☐ OTHER DOCUMENT ☐			
OTHER DRAWING ☒			
CHANGE AUTHORIZATION			
J.E. Brasier by B.J. Henner			
DATE 5/23/91			

IDAHO NATIONAL ENGINEERING LABORATORY
DOCUMENT CHANGE NOTICE

SHEET 1 OF 1

INDEX CODE NUMBER			
AREA	DWG TYPE	CL	ORIG
5330670	47220		
DOCUMENT NUMBER			REVISION
436956			C
NUMBER OF SHEETS			
1			
DOCUMENT TITLE			
ATR			
TYPE II SHIPPING CAPSULE			
ASSEMBLY AND DETAILS			

APPROVALS			
DESIGN	DESIGN ACTIVITY	MFG ENGR	
<i>[Signature]</i>	B.J. Henner		
CHECKED	STRESS	QUALITY	
<i>[Signature]</i>		<i>[Signature]</i>	
INCOMP	MATERIALS PROCESSES	REQUESTER	
RELEASE DATE	REVISION	REVISION	
5/23/91			

1 CHANGE NOTE 3

WAS: .0001 - .0004

IS: .000 - .015

2. Change TITLE

WAS: ATR

IS: TRA

DATE: 07/12/91

SWR FIELD CHANGE

PAGE: 1

SWR NO.: RI063 FC#: 3 TITLE: FAB SPECIAL FORM SHIPPING CONTAINERS.
CHARGE#: 121210002 RQSTR: JR AUBREY DATE: 07/10/91 PH: 6-4287
CF REQ: N PROCESSED BY: _____ DATE: __/__/__

----- TYPE OF CHANGE -----
CANCEL _ HRS _ DUE DATE _ QUAL _ SFTY _ NCR _ DWG _ PLNG X OTHER _

RS UPDATE INFO:	CRAFT	HRS	CRAFT	HRS	CRAFT	HRS	CRAFT	HRS
	MACH	2.0	_____	0.0	_____	0.0	_____	0.0
	WELD	1.0	_____	0.0	_____	0.0	_____	0.0

===== APPROVALS =====	
QUALITY:	CD COOPER
SAFETY:	JC BATIE
AD-CON SAFETY:	_____
I SAFETY:	_____
REQUESTING MANAGER:	JR AUBREY
BUDGET MANAGER:	JR AUBREY
FACILITY MANAGER:	JE BRASIER

DATE:	07/10/91
DATE:	07/10/91
DATE:	____/____/____
DATE:	____/____/____
DATE:	07/12/91
DATE:	07/12/91
DATE:	07/10/91

JUSTIFICATION:
OLD PROCEDURE INCORRECT.

CHANGE DESCRIPTION:
SEE ATTACHED PLANNING SHEET.

=====

SEQ NO CRAFT

12.00 WELD

INITIAL AND DATE: SW 7/10/91CHANGE INEL WELD PROCEDURE SPECIFICATION TO S-2.0 for 7/11/91

13.00 WELD

INITIAL AND DATE: SW 7/10/91CHANGE INEL WELD PROCEDURE SPECIFICAT4ION TO S-2.0 for 7/11/91

WELD INSPECTION REPORT

PART 1 (Mandatory for Quality Level A and B Work)

¹ Joint No. NUM0013 ² SWR No. RI063 ³ Dwg No. 435974 Rev. C

⁴ WPS No. S2.0 Rev. 9 ⁵ Tack Welder Code CF ⁶ Date 7-9-91

Base Components: SWR M/L Item Numbers ⁷ 6 to 7 *exp 7-29-91*

Filler Material: ⁸ Insert _____ Q.A. No. _____
Filler Rod .035 308 87A0876

Fit Checked (Y/N) ⁹ _____

¹⁰ NDE Method Required	¹¹ Proc.	¹² Acc. Criteria
☒ VT CP9.6	<u>I</u>	<u>I</u>
☒ PT CP9.3	<u>III</u>	<u>II</u>
☐ RT CP9.1		
☐ MT CP9.4		
☐ UT CP9.5		

¹³ Layer or Repair	¹⁴ Welder Code	¹⁵ VT A/R	PT A/R	RT A/R	MT A/R	UT A/R	¹⁶ Examiner Stamp/Date
<u>Final 1-6 CF</u>	<u>CF</u>	<u>A</u>	<u>A</u>				<u>9 July 91</u>
<u>Final 7-13 CF</u>	<u>CF</u>	<u>A</u>	<u>A</u>				<u>9 July 91</u>

¹⁷ Reviewed/Accepted By: Orin S. Marcum Date 7 July 91

Remarks _____

PART 2 (Mandatory for Quality Level A and B Work)

¹⁸ Preheat & Interpass Temperature 770 NA

¹⁹ Backing Gas Purge, O₂, & Dewpoint < 0 FW

END

**DATE
FILMED**

2 1221 93