DOE/PC/90156--3

DE93 000598

**DEVELOPMENT AND TESTING OF A COMMERCIAL-SCALE
COAL-FIRED COMBUSTION SYSTEM - PHASE III**

**Quarterly Technical Progress Report No. 3
Report Period: April 1, 1991 to June 30, 1991**

**By
A.F. Litka and R.W. Breault**

October 1991

Work Performed Under Contract No. DE-AC22-90PC90156

**Prepared for
PETC Project Manager: Mr. Douglas Gyorke
Pittsburgh Energy Technology Center
U.S. Department of Energy
P.O. Box 10940
Pittsburgh, Pennsylvania 15236-0940**

**Prepared by
Tecogen Inc.
45 First Avenue
P.O. Box 9046
Waltham, Massachusetts 02254-9046**

MASTER

TABLE OF CONTENTS

1. INTRODUCTION	1
2. PROJECT STATUS	7
2.1 COMPONENT DESIGN	7
2.2 COMPONENT FABRICATION	10
2.3 COMPONENT DESIGN TESTING	14
3. PLANNED ACTIVITIES	20
4. SUMMARY	21

LIST OF ILLUSTRATIONS

1.1	Process Flow Diagram	4
1.2	Work Breakdown Structure for Entire Project	5
2.1	Combustor/Transition Box Assembly	8
2.2	Combustor, Transition Chamber and Boiler Arrangement	9
2.3	Slurry Production Facility	11
2.4	Slurry Preparation Facility Configuration	12
2.5	Photograph of the Test Setup	13
2.6	Modified Delavan Delta Atomizer	15
2.7	Spatial Distribution of Slurry Spray	18
2.8	Size Distribution of Slurry Spray	19

LIST OF TABLES

1.1	Performance Goals	3
2.1	Analyses of Coal-Water Slurry and Its Parent Coal	17

1. INTRODUCTION

Coal is the most plentiful energy resource in the United States, and in 1987 it provided approximately one third of the quads of total energy consumed in the United States. Its use, however, has been largely restricted to utility power generation since World War II for environmental and economic reasons.

Within the commercial sector, oil and natural gas are the predominant fuels used to meet the space-heating needs of schools, office buildings, apartment complexes, and other similar structures. In general, these buildings require firing rates of 1 to 10 million Btu/hr. The objective of this program is to demonstrate the technical and economic viability of a coal-fired combustion system for this sector.

The development program includes all aspects of the process, from fuel selection and preparation to pollution control and waste disposal. In attempting to restore coal to small users such as residential and commercial space heating, it is important to recognize that fuel form is an important consideration because of its impact on handling and emissions. Ease of handling is an important criterion at the small sizes since complex equipment will add greatly to the overall system costs. Furthermore, manpower is not available to perform manual functions or keep complex equipment working. Emission levels, if not currently regulated, can be expected to be regulated at low levels in the future. The levels considered acceptable will be reduced over time, following the current environmental trends. Preparation and use of a coal-water slurry fuel can aid in meeting these criteria. Coal-water slurry eliminates the need to use dry pulverized coal with its attendant handling and dusting problems as well as its explosive potential. In addition, coal-water slurry is amenable to coal washing since coal cleaning technologies are generally water-based processes requiring fine grinding of the coal. For these reasons, the program objective will be met through the development of a coal-water slurry fired system.

Although the coal-water slurry fuel used commercially will be manufactured by coal companies or fuel suppliers at regional facilities and transported to the user much as is done today with oil, the program includes the construction of a slurry production facility. In this way, all aspects of the fuel's use – from coal selection to combustion properties – can be evaluated and an economic evaluation of the process can be carried out.

The commercial-scale coal-water slurry (CWS)-fired space heating system will be a scale-up of a CWS-fired residential warm-air heating system developed by Tecogen under contract to the Department of Energy, Pittsburgh Energy Technology Center. This system included a patented nonslagging combustor known as IRIS, for Inertial Reactor with Internal Separation. This combustion technology,

which has demonstrated high combustion efficiency using CWS fuels at input rates of 100,000 Btu/hr, will be scaled to operate at 2 to 5 million Btu/hr. Along with the necessary fuel storage and delivery, heat recovery, and control equipment, the system will include pollution control devices to meet targeted values of NO_x , SO_2 , and particulate emissions. In general, the system will be designed to match the reliability, safety, turndown, and ignition performance of gas or oil-fired systems. Table 1.1 summarizes the performance goals of the system, and Figure 1.1 is a process flow diagram of the system.

The successful development and future marketability of the heating system requires a strong, dedicated team with expertise in a broad range of areas including coal-water slurry preparation, coal combustion, pollution control, component manufacture, and systems integration. Such a team has been assembled and includes the following organizations: Tecogen, Donlee Technologies, AMAX Coal, and Southern Illinois University.

Tecogen is the prime contractor and is responsible for overall program management, combustor development, and integration of the subsystem components and installation of the system at the field test site. AMAX has extensive experience in coal-water slurry preparation and serves as the principal coal supplier. Donlee Technologies is responsible for the boiler/heat exchanger design and manufacture. Donlee has over 70 years' experience in the commercial boiler business and is a potential commercializer of the technology. Southern Illinois University (SIU) is the host for the field test portion of the program. The heating system will provide space heating at the SIU Coal Research Center.

The development program has been divided into 3 stages which cover a time span of 39 months. During the first stage, scheduled for 14 months, the program will focus on component development. The second stage, which covers a 10-month period, will focus on proof-of-concept testing. The final stage is scheduled to last 15 months and will focus on testing all the components as an integrated system in an actual installation. Figure 1.2 shows the work breakdown structure for the program.

This report documents the work carried out in the third quarter of the program. Activities focused on the detailed design and fabrication of the major system components. Component design testing was also conducted to evaluate component performance before integration into the final system configuration and to evaluate design variations. In particular, preliminary combustor testing was conducted to provide early verification of combustor scale-up, and slurry atomizers were characterized to ascertain their spray pattern and atomization quality.

TABLE 1.1
PERFORMANCE GOALS

• Thermal Input	– 4 million Btu/hr
• Thermal Efficiency	– >80%
• Combustion Efficiency	– >99%
• Emissions	– 1.2 lb SO ₂ /MMBtu
0.3 lb NO _x /MMBtu
0.03 lb Part./MMBtu
• Turndown	– 3:1
• Ignition	– Fully automatic startup with system purge and ignition verification
• Reliability/Safety	– Comparable to oil-fired commercial boilers
• Ash Removal	– Dust free and automatic or semi-automatic
• Routine Maintenance	– Less than one manhour per day and an additional two manhours per week
• Service Life	– >20 years

Figure 1.1 Process Flow Diagram

Figure 1.2 Work Breakdown Structure for Entire Project

During the previous quarters, work concentrated on the definition of the overall system configuration and the determination of the key parameters to be considered in the combustor design. A preliminary heat balance was developed to define the overall process and to size system components and piping. Coal properties were evaluated and predictions made for the CWS properties capable of being achieved with the selected coals.

Combustor scaling laws were developed. This allowed the data base that has been established with the residential combustor to provide guidelines for the scale-up of this combustor technology to larger sizes. In particular, particle separation, reaction rate kinetics, pressure drop, and residence times were evaluated.

2. PROJECT STATUS

During the third quarter of this program, work continued on component design, and component fabrication was initiated. In addition, component design testing was conducted to evaluate component operation before integration into the complete space heating system.

2.1 COMPONENT DESIGN

Combustor/Transition Chamber

Figure 2.1 shows the details of the combustor/transition box assembly. The combustor will consist of two sections, a 24-inch-long upper chamber and a 36-inch-long lower chamber. Each section is refractory lined with a double jacketed water-cooled steel shell. These chambers will be lined with 2 inches of abrasion resistant refractory. Resulting combustor inner diameter is 21.5 inches. Each section has a rectangular air inlet that measures 3 inches by 8 inches. Removable steel-encased refractory wedges will be used to set the inlet air gaps and corresponding inlet velocities. The combustor roof will also be a water-cooled section made up of stayed parallel plates with internal baffling. The roof is designed for 4 inches of refractory and includes penetrations for slurry and fuel oil atomizers, a pilot, and viewport.

The transition chamber will consist of an upper cover, a shell, and a lower cover. The shell will be a refractory-lined, double-jacketed, water-cooled cylinder with an external diameter of 48 inches, an overall length of 48 inches, and three inches of wall refractory. The covers will have stayed parallel plates with internal baffling and 4 inches of refractory. The lower combustor section will be bolted to the transition chamber upper cover, and the cover will support the combustor. The lower cover will have a 6-inch bottom ash drop-out port. The shell will have a 12-inch side ash clean-out port, a viewport, and boiler connection.

The combustor/transition chamber will be separately supported and an expansion joint will be used between the transition chamber and boiler. Figure 2.2 shows the combustor, transition chamber, and boiler arrangement along with the support structure for each. The base of the boiler stand will be used to support the water pumps, fuel pumps, piping, etc.

Figure 2.1 Combustor/Transition Box Assembly

Figure 2.2 Combustor, Transition Chamber and Boiler Arrangement

Baghouse

A Flex-Kleen Model 100BVBC36III Dust Collector will be used for particulate control. The unit's performance at specified conditions is detailed below:

Gas Flow:	4500 lb/hr (1840 acfm @ 450°F)
Gas Temperature:	300 to 500°F
Inlet Dust Loading:	80 lb/hr
Outlet Dust Loading:	0.12 lb/hr
Dust Type:	Coal Ash and Sorbent (30% Coal Ash, 70% combination sodium bicarbonate and sodium sulfite)
Dust Size:	90% less than 325 mesh
Gas Composition (vol):	13% CO ₂ , 13% H ₂ O, 70% N ₂ , 3% O ₂ , 0.16% SO ₂
Pressure:	+/- 17 inches w.c.
Operating Pressure Drop:	6 inches w.c.

The collector will have thirty six 100-inch-long bags with a cloth surface area of 457 sq. ft. The bags will be made from P84 fabric, a nonflammable and thermostable organic fibre with a maximum use temperature of 500°F. The dust collector has been designed to handle the combined ash and sorbent flow rates.

Slurry Preparation Facility

Figure 2.3 is a flow diagram for the slurry production facility. The slurry has been designed to accept crushed coal from the mine and produce slurry with a 50 to 65 percent solids loading and a mean coal particle size of approximately 12 microns. The system will be able to process coal at a rate of 300 pounds per hour. The coal will be ground using a dry hammer mill with integral classifier. Two cyclones will be used in series, the first operating dry and the second wet to collect the fine coal particles. The water introduced at the wet cyclone will be the main source of water for the slurry. Secondary water addition will be made at the mixing tanks, if required, to achieve the desired slurry properties. Dispersant and stabilizer will also be added at the mixing tank. Figure 2.4 is a configuration drawing of the equipment.

2.2 COMPONENT FABRICATION

Combustor fabrication was completed and the combustor was integrated into the Tecogen industrial-scale combustion facility to permit preliminary evaluation testing. Figure 2.5 is a photograph of the test setup. The combustor is connected directly to a water quench exhaust system.

Fabrication of the boiler, baghouse, and transition chamber was initiated during this period.

Figure 2.3 Slurry Production Facility

Figure 2.4 Slurry Preparation Facility Configuration

Figure 2.5 Photograph of the Test Setup

2.3 COMPONENT DESIGN TESTING

Component design testing was conducted to provide engineering data on component design activities and to verify component operation before full system integration.

To assess the particle retention ability of the combustor design, cold flow visualization tests were performed utilizing the Tecogen industrial combustor. The combustor cover was replaced with Plexiglas for easy viewing, and the industrial combustor was modified to match the commercial-scale combustor design with respect to partition location. Placing the partition flush with the bottom of the air inlet produced a drastic effect on the combustor's ability to retain particulates. The partition diameter was varied from 8 to 14 inches to determine the optimum opening size and ledge width. At an air inlet velocity of approximately 200 ft/sec, a 10-inch inner partition diameter was found to have the best particle retention capability. Retention capability was measured by what percentage of injected material remained on the partition upon rapid shutdown of the air flow after a fixed time of operation.

Several coal water slurry combustion tests were made to verify the operation of the scaled-up combustor. Initial tests were done with the combustor upper chamber mounted on top of the existing Tecogen industrial combustor. After that, complete combustor testing was performed.

Initial tests revealed that most of the slurry/coal particles were projected past the upper partition using a Delavan Delta Swirl-Air Combustion Air Atomizing Nozzle with an included spray angle of 120 degrees. This left insufficient burning coal particles in the upper section with corresponding low primary zone temperatures. Modifications were made to the atomizer to increase the spray angle. An adjustable pintle plate was installed with a larger diameter to deflect the slurry in a more radial direction. Figure 2.6 shows the final atomizer configuration. Slurry spray tests were made to observe the spray pattern and to set the pintle plate gap based on qualitative observation of the spray pattern and droplet size. At a gap of 0.03 inches good atomization was observed with a nearly flat spray angle (180° included angle).

Combustion tests with the modified atomizer resulted in a much larger quantity of slurry droplets and burning coal particles in the upper section with corresponding higher chamber temperatures. Approximately 1000 pounds of slurry were burned. Post-run inspection revealed a small amount of material buildup on the upper partition. This material was very light and easily disturbed. For this test the primary air inlet velocity was 90 ft/sec with a slot width of 1.5 inches.

Figure 2.6 Modified Delavan Delta Atomizer

The slot width was decreased to 0.75 inches to increase the velocity in the upper section. At a thermal input of 3.2 MMBtu/hr and primary and secondary air inlet velocities of 140 and 110 ft/sec, respectively, the combustor ran well with no evidence of buildup on the partitions. An upper chamber gas temperature of greater than 1900°F was maintained. Between the partitions, the gas temperature reached 2600°F.

In additional combustor testing, the combustor was operated at thermal input rates as high as 4.2 MMBtu/hr. Based on gas analysis measurements, combustion efficiencies greater than 95 percent were achieved. Combustor exit gas temperatures of approximately 2450°F were measured.

The slurry used for the combustion testing as well as the atomization tests was an Upper Elkhorn Number 3 seam parent coal slurry with approximately a 65 percent coal loading. Table 2.1 lists the slurry properties. Combustor heat rejection to the combustor cooling water was 12 to 15 percent of the thermal input. This cooling water will be recirculated from the boiler in the integrated system.

Slurry atomization tests were made to characterize the performance of the modified Delavan/Delta atomizer. Spatial distribution, spray cone angle, and size distributions measurements were made at two pintle plate gap settings and two slurry flow rates. These settings were chosen based on visual observations of the slurry spray pattern. Figure 2.7 and 2.8 are representative of the results. Figure 2.7 gives the spatial distribution of the spray with respect to the spray angle. It is clearly seen that the peak occurs at 65 to 70° which corresponds to a maximum spray cone angle of 130 to 140°. The spray is effectively a hollow cone with a cone angle between 90 and 150°. Figure 2.8 gives the size distribution of the slurry droplets at the optimized pintle gap setting and atomizing air flow. At the optimal setting the atomization is relatively poor, with an arithmetic mean diameter of 252 microns and a Sauter mean diameter of 484 microns.

Successful operation of the combustor with this relatively poor atomization shows the inherent ability of the IRIS combustor technology to retain large droplets in the upper zone of the combustor and thereby provide sufficient residence time for water evaporation and coal particle burnout. It is evident from the spray results, and visually observed during the hot combustor tests, that a large fraction of the slurry reaches the wall of the combustor in the upper combustor zone. At high flow rates a slight nonuniformity in the circumferential distribution was measured, and this nonuniformity increased as the flow rate was decreased, reaching a point where atomization became unstable.

TABLE 2.1
ANALYSES OF COAL-WATER SLURRY
AND ITS PARENT COAL

PROPERTIES OF PARENT COAL	
Type: Deeply-Cleaned Micronized Coal	
Bed: West Virginia Upper Elkhorn No. 3	
Size: Mean Diameter of 12 μ m	
<u>Proximate Analysis (% wt dry):</u>	
Moisture	0.72%
Volatile Matter	35.05%
Fixed Carbon	63.45%
Ash	1.50%
Sulfur	0.63%
Heating Value	14,756 Btu/lb
<u>Ultimate Analysis (% wt):</u>	
Carbon	86.83%
Hydrogen	5.14%
Oxygen	3.64%
Nitrogen	1.54%
Sulfur	0.63%
CWF PROPERTIES	
Solid Loading, % wt	65-67
Viscosity, cp @ 100/s	<1,000/110
Specific Gravity @ 60°F	1.2
Heating Value, Btu/lb	9,930

Figure 2.7 Spatial Distribution of Slurry Spray

Figure 2.8 Size Distribution of Slurry Spray

3. PLANNED ACTIVITIES

During the next reporting, component integration will be carried out. Support structures for the boiler, baghouse, and transition chamber will be fabricated and the major system components placed in position and connected. Combustor testing will continue to further evaluate combustor performance.

4. SUMMARY

During the third quarter of the program, work concentrated on the construction of the major system components, i.e., combustor, boiler, baghouse, and transition chamber. Component design testing of the combustor was conducted to verify the combustor scale-up. The combustor was successfully operated at input rates in excess of 4 MMBtu/hr.

END

**DATE
FILMED**

12 / 29 / 92