**DESIGN OF GASIFIERS TO OPTIMIZE
FUEL CELL SYSTEMS**93
1000**QUARTERLY TECHNICAL PROGRESS REPORT No. 9**

COVERING PERIOD 10/1/92 TO 12/31/92

DOE/MC/27227--3345

DE93 013991

DISCLAIMER

This report was prepared as a part of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Submitted by:

**ENERGY RESEARCH CORPORATION
3 Great Pasture Road
Danbury, CT 06813
G. Steinfeld, Program Manager**

Submitted to:

**U.S. Department of Energy
Morgantown Energy Technology Center
3610 Collins Ferry Road
Morgantown, WV 26507-0880
Justin Beeson/COR**

**Contract No.
DE-AC21-90MC27227**

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

TABLE OF CONTENTS

1. Project Summary	1
2. Overview of Activities this Quarter	2
3. Experimental Testing	2
3.1 Task 4.2 Experimental Studies	3
3.2 Task 4.3 Experimental Assessment	9
4.0 Schedule	10

PROJECT SUMMARY

RECEIVED
ACQUISITION SERVICES
93 JAN 19 AM 9:06

TITLE: DESIGN OF GASIFIERS TO OPTIMIZE FUEL CELL SYSTEMS

CONTRACT NUMBER: DE-AC21-90MC27227

CONTRACTOR: ENERGY RESEARCH CORPORATION
3 Great Pasture Road
Danbury, CT 06813

PERIOD OF PERFORMANCE: September 28, 1990 to September 28, 1993

OBJECTIVE: To configure coal gasification/carbonate fuel cell systems that can significantly improve the economics, performance, and efficiency of electric power generation systems.

CONTRACT TASKS: Status
as of 12/31/92

TASK 1.	Project work plan	completed
TASK 2.	Gasifier/Fuel Cell System Design Studies	completed
Task 2.1	Design studies	completed
Task 2.2	Technical/Economic analysis	completed
TASK 3.	Program Assessment	completed
TASK 4.	Experimental Studies	in progress

2.0 OVERVIEW OF ACTIVITIES FOR THIS QUARTER

During this quarter a poster session was presented at the Fuel Cell Seminar held in late November.

Work on Task 4.2, Experimental Studies, was completed this quarter, using a subscale experimental reactor. Agglomeration of Illinois #6 was observed in uncatalyzed testing, but catalyzed coal did not agglomerate. There were some difficulties in closing material balances, and there was scatter in data obtained. Experimental data is being assembled for interpretation in the final report under preparation.

3.0 EXPERIMENTAL TESTING

The activities in this task are designed to evaluate experimentally the performance of the gasification catalysts chosen for the system study in the first year of this effort. The objectives of this task have been broken down as follows:

1. To experimentally characterize the performance of the previously recommended gasification catalysts for integrated gasification carbonate fuel cell systems as identified in the system study performed during Tasks 1,2,and 3. The catalysts which will be tested include potassium carbonate, limestone and taconite in dry form as well as a coal-impregnated with soluble salts of potassium, calcium and iron.
2. To evaluate the degree to which SO_2 in a recycled stream, and or sulfur in the feed, can be captured by the selected calcium or iron containing catalyst at the operation conditions in the catalytic gasifier.
3. To carry out tests under simulated conditions approaching the preferred final process design conditions identified in the system study.

Experimental testing is conducted at the University of North Dakota/Energy & Environmental Research Center with program management and technical input from ERC.

The first phase of experimental testing consists of a cost-effective minimum scale screening by Thermogravimetric Analysis (TGA). The results of these tests are used to predict the overall reactivity and to recommend conditions for the bench scale (IBG) testing (i.e., temperatures, catalyst loading, residence time) which are used in the second phase of the experimental testing.

In the second phase of experimental testing, the Integrated Bench Scale Reactor (IBG) tests Illinois No. 6 coal in a pressurized batch gasifier at conditions as close as possible to the system conditions defined in the first year of this effort. Test results will be compared and used to assess the design assumptions of the system study.

3.2 TASK 4.20 EXPERIMENTAL STUDIES

The experimental matrix for Integrated Batch Gasifier (IBG) Testing has been completed. An initial baseline IBG run was performed using washed Illinois No. 6 coal and subsequent runs used a 15 wt.% potassium-impregnated Illinois #6 coal feed. Analysis of the coal feeds and ash are listed in Table 1.

Table 1 PROXIMATE AND ULTIMATE ANALYSIS OF WASHED AND POTASSIUM-IMPREGNATED ILLINOIS #6 COAL

Proximate Analysis, wt%	EPRI TAG	Washed Illinois #6 Coal	Potassium-Impregnated Illinois #6 Coal
Moisture	12.0	13.8	4.6
Fixed Carbon	39.0	42.4	28.6
Volatiles	33.0	31.5	44.5
Ash	16.0	12.3	22.3
Total	100.0	100.0	100.0

Ultimate Analysis, wt%	EPRI TAG	Raw Illinois #6 Coal	Potassium-Impregnated Illinois #6 Coal
Moisture	12.0	13.8	4.6
H	3.7	3.5	3.8
C	57.5	56.5	58.4
N	0.9	1.0	1.1
S	4.0	3.1	2.4
O	5.8	9.8	7.4
Ash	16.0	12.3	22.3
Cl	0.1	---	---
Total	100.0	100.0	100.0

**Table 1 PROXIMATE AND ULTIMATE ANALYSIS OF WASHED AND
POTASSIUM-IMPREGNATED ILLINOIS #6 COAL
(cont.)**

Ash Analysis, wt %	EPRI TAG	Washed Illinois #6 Coal	Potassium-Impregnated Illinois #6 Coal
Silica, SiO ₂	45.0	48.93	27.29
Alumina, Al ₂ O ₃	18.0	18.29	21.55
Ferric Oxide, Fe ₂ O ₃	20.0	13.92	5.17
Titanic Oxide, TiO ₂	1.0	---	---
Calcium Oxide, CaO	7.0	6.93	1.38
Magnesia, MgO	1.0	1.39	0.82
Sodium Oxide, Na ₂ O	0.6	1.33	0.31
Potassium Oxide, K ₂ O	1.9	1.89	26.24
Sulfur Trioxide SO ₃	3.5	6.18	17.20
Phosphorous Pentoxide, P ₂ O ₅	0.2	---	---
Undetermined	1.8	1.14	0.03
	100.0	100.00	100.00

The proximate and ultimate analysis of the "as received" washed coal available for testing at EERC compares reasonably well with the average analysis for EPRI TAG Representative East Central Illinois #6¹, although the coal tested is somewhat lower in ash (12.3 wt % vs. 16.0 wt %).

Analysis of the potassium impregnated Illinois #6 only indicates that the potassium addition, and subsequent drying skews the data, with potassium contributing to the volatiles and ash figures. The ash analysis indicates an increase in potassium oxide for the catalyzed coal as expected. The increased sulfur in the ash, if accurate, may be an indication of potassium reaction with sulfur compounds in the coal, and stabilization in the ash.

A schematic of the IBC is shown in Figure 1. To initiate a run, the system is brought up to temperature. During warm-up, steam and nitrogen are added at flow rates approximating the predetermined fluidization velocity. When the system reaches ~100 °C below the target temperature, the steam is turned off and the char collection pots and condensate pots are drained. Once the target temperature is reached and allowed to stabilize for ~1/2 hour, the coal feed in the feed hopper is sealed and purged with nitrogen. The feed gas is switched to a nitrogen/hydrogen/steam mixture while the system is pressurized. When operating pressure has been reached, the feed hopper valve opens and the coal feed is forced into the gasifier by a high pressure nitrogen purge.

¹EPRI Technical Assessment Guide P-4463-SR Vol 1, page 2-10, Dec. 1986.

Figure 1 INTEGRATED BENCH-SCALE GASIFIER SCHEMATIC

Reaction progress is monitored by charting the relative concentrations of CO_2 , CO and CH_4 in the product gas versus time. The relative compositions are determined by a Fourier Transform InfraRed (FTIR) analyzer in 20 second sampling intervals. This data is also used to determine reactivity measurements. An example of the FTIR spectra for one run is shown in Figure 2. The double ridge shows the CO and CO_2 absorbance spectra; the smaller ridge to their left is the CH_4 spectra. The ripples to the far right indicate water, while those on the far left indicate undefined heavier organics. Gas chromatograph (GC) analyses are also performed on gas bag samples.

When the carbon consumption is ~90% complete (indicated by the FTIR), the run is terminated. The discharge valve is opened and the reactor contents are dumped into the char pot. The solids in the char pot are dried overnight in a nitrogen-blanketed oven and used for proximate, ultimate and XRFA analyses and leaching tests.

A total of ten IBC runs were conducted at temperatures ranging from 650°C to 750°C and at pressures extending from atmospheric to 150 psig. Table 2 lists the IBC run numbers and corresponding IBC conditions.

Table 2 IBC EXPERIMENTAL MATRIX

Temperature, °C	Pressure, psig		
	Atmospheric	50	150
650	IBC-018	IBC-029	IBC-028
700	IBC-017*	IBC-021 IBC-022 IBC-023	---
750	---	IBC-024 IBC-025	IBC-027

* Raw (washed) Illinois No.6 Coal Feed Used.

Reactivity is determined using the FTIR analysis; this process is illustrated in Figure 3. The CO_2 absorbance data is more dominant than either the CH_4 or CO absorbance data and therefore was used to measure the rate of carbon consumption. The integral of the CO_2 absorption curve is an indication of the amount of unreacted carbon; the maximum slope defines the carbon consumption. The intercept of this line is offset indicating the time lag for the cold, injected coal feed to reach reaction temperature. Two rescaled versions of this integral line representing the fixed carbon (FC) and the total carbon (TC) loss are also shown. When the integral approximates a well-behaved exponential function, a straight line (designated "reactivity") is drawn with an empirical slope and intercept adjusted to fit the maximum slope of each of the three curves. The slope of this line is reported as the reactivity. This method for obtaining reactivity is referred to as the "Tangent Slope Method".

This method is valid to the extent that the curve approached a consistent zero to second order exponential. However, due to erratic gas velocity, inconsistent sample gas flow to the FTIR, and/or incomplete/erratic fluidization, the effective reactivity may fluctuate during a run. An example of this is Run IBC-029, shown in Figure 4. The CO_2 absorbance trace is a series of ~4 peaks, suggesting that the reaction stopped and started several times. When integrated and matched to an exponential function by a least squares fitting procedure, a curve resulted with a mathematical form of:

Figure 2 STACKED TIME SERIES OF FTIR SPECTRA
IBG-024

Figure 3 FTIR OF CO₂ ABSORPTION PLOT, INTEGRAL CURVE AND REACTIVITY

Figure 4 WHOLE EXPONENTIAL CURVE FIT TO ERRATIC FTIR CO₂ ABSORBANCE RUN IBG-029

$$Y = e^{-(t-t_0)k/60}$$

where the initial slope, k , would be tangent to the early point of inflection in a "well-behaved" second order curve. The constant, t_0 , is a delay factor indicating the time required for the cold feed to reach reaction temperature. The slope is multiplied by 60 to convert into the conventional reactivity units of 1/h. This reactivity should be identical to the result that would have been obtained by the tangent slope method. This method of calculating reactivity is defined as the "Whole Exponential Curve Fitting Method".

3.2 TASK 4.30 EXPERIMENTAL ASSESSMENT

The reactivities obtained in the batch gasification testing are listed in Table 3. The variation of reactivity with temperature is as expected for determinations using the same method. The uncertainty in comparison of such data by slightly different methods is apparent. Ignoring the data for IBC-029 (650 °C, 50 psig) the data fits a consistent and expected pattern: reactivity increases with temperature and pressure.

Table 3 REACTIVITIES OF POTASSIUM-IMPREGNATED ILLINOIS NO. 6 COAL
k, (1/h)

Temperature, °C	Pressure, psig		
	Atmospheric	50	150
650	NP*	3.87***	4.03***
700	0.15**	0.60 - 1.80	----
750	----	2.58	11.38***

*Reactivity determination not possible.

**Raw Illinois No 6 coal used, k determined from manually recorded CO content in the product gas.

***Reactivity determined by exponential curve fitting method.
Unless otherwise noted, all other reactivities determined by tangent line method.

The IBC ash samples were leached in water, dried and weighed, and submitted for Loss on Ignition (LOI) and XRFA analyses. Potassium recovery based on the total potassium present in the residual ash/char sample is listed in Table 4. Ash plugs accumulated in the top screen of the reactor when runs were performed in succession, these plugs were analyzed separately and are indicated in the table by 21/23, 24/25, and 27/29. The data indicates that potassium recovery of 39-71% were achieved by water leaching alone. It is anticipated, however, that total potassium recovery in excess of 90% can be achieved with pH adjustment.

Table 4 POTASSIUM RECOVERY FROM LEACHED GASIFIER RESIDUE

Temperature, °C	Pressure, psig			
	50		150	
	Run Number	Potassium Recovery, %	Run Number	Potassium Recovery, %
650	IBG-029 27/29	38.94 77.86	IBG-028	57.58%
700	IBG-021 IBG-022 IBG-023 21/23	70.48 64.15 65.50 66.97	---	---
750	---	---	IBG-027	68.47

The reactivity and potassium recovery data will be assessed further and submitted in the final report which is being prepared.

4.0 SCHEDULE

The schedule is shown in Figure 5 and the milestones are defined in the following table.

TITLE Design of Gasifiers to Optimize Fuel Cell Systems		REPORTING PERIOD 12/01/92 - 12/31/92	IDENTIFICATION NUMBER DE-AC21-90MC27227
PARTICIPANT NAME AND ADDRESS Energy Research Corporation 3 Great Pasture Road Danbury, CT 06813		START DATE 9/28/90	
		COMPLETION DATE 9/28/93	

TASK #	ACTIVITY	1990				1991				1992				1993				PLANNED % COMPLETE	ACTUAL % COMPLETE
		S	F	J	D	M	O	M											
100	Project Work Plan																	100%	100%
	Gasifier/Fuel Cell System Design Studies																		
	Design Studies																		
211	Evaluate Disposable Catalyst Options (EERC)																	100%	100%
212	Evaluate High Methane vs. High Hydrogen Gasification																	100%	100%
213	Design Case 1 - Recoverable Gasification Catalyst																	100%	100%
214	Design Case 2 - Disposable Catalyst/cold cleanup																	100%	100%
215	Design Case 3 - Disposable Catalyst/hot cleanup																	100%	100%
	Technical Economic Analysis																		
221	High Methane vs. High Hydrogen Cost Estimate and Review																	100%	100%
222	Case 1 Cost Estimates and Review																	100%	100%
223	Case 2 Cost Estimates and Review																	100%	100%
224	Case 3 Cost Estimates and Review																	100%	100%
	Program Assessment																		
310	Evaluate Systems Configured and Compare																	100%	100%
320	Compare Fuel Cell Systems to Competing Systems																	100%	100%
330	Topical Report																	100%	100%
	Experimental Studies																		
410	Work Plan For Experimental Studies																	100%	100%
420	Experimental Studies																	100%	100%
430	Experimental Program Assessment																	70%	100%

PLANNED	ACTUAL	ESTIMATED
SIGNATURE OF PARTICIPANT'S PROJECT MANAGER AND DATE 1/15/93		

RECEIVED
 JAN 19 93
 9:06
 ACQUISITION SERVICES

Table 5 KEY MILESTONES

- a. Submit Project Plan to DOE/COR.
- b. Begin literature survey on gasification catalysts (EERC).
- c. Complete literature survey on gasification catalysts (EERC).
- c'. Complete draft report on gasification catalysts (EERC).
- c". Complete final report on gasification catalysts (EERC).
- d. Begin evaluation of high methane vs. high hydrogen gasification (Fluor).
- e. Complete evaluation of high methane vs. high hydrogen gasification (Fluor).
Choose one approach for further evaluation.
- f. Begin design of recoverable gasification catalyst system (Case 1).
- g. Begin design of disposable gasification catalyst system with cold cleanup (Case 1).
- h. Begin design of disposable gasification catalyst system with hot cleanup (Case 3).
- i. Complete Case 1, recoverable gasification catalyst.
- j. Complete Case 2, disposable gasification catalyst with cold cleanup.
- k. Complete Case 3, disposable gasification catalyst with cold cleanup.
- l. Complete comparison of fuel cell systems configured.
- m. Complete comparison of fuel cell systems with competing systems.
- n. Submit topical report to METC.
- o. Submit work plan for Experimental Studies.
- p. Begin TGA studies to screen candidate gasification catalysts.
- q. Begin bench scale fluid bed testing of selected catalysts.
- r. Submit draft final report to METC.
- s. Submit approved final report to METC.

END

DATE
FILMED

6 / 14 / 93