**SCALEUP TESTS AND SUPPORTING RESEARCH
FOR THE DEVELOPMENT OF DUCT INJECTION TECHNOLOGY**

Topical Report No. 7

Task 4.1: Testing of First Generation Mathematical Model Predictions

Topical Report No. 8

Task 4.2: Testing of Second Generation Mathematical Model Predictions

Contract DE-AC22-88PC88851

DOE/PC/88851--T3

**Duct Injection Test Facility
Muskingum River Power Plant
Beverly, Ohio**

DE93 008942

Prepared by:

**Larry G. Felix
John P. Gooch
of
Southern Research Institute**

and

**Michael G. Klett
Atef G. Demian
of
Gilbert/Commonwealth, Inc.**

Submitted by:

**Southern Research Institute
Post Office Box 55305
Birmingham, AL 35255**

and

**Gilbert/Commonwealth, Inc.
Post Office Box 1498
Reading, PA 19603**

**September 18, 1992
SRI-ENV-92-634-6715-T4**

1.0 INTRODUCTION

Gilbert/Commonwealth (G/C) and Southern Research Institute have completed a project under DOE sponsorship entitled "Scaleup Tests and Supporting Research for the Development of Duct Injection Technology". The project included extensive modifications to DOE's Duct Injection Test Facility (DITF) located at the Muskingum River Plant of Ohio Power Company. A comprehensive test program was performed at the facility to evaluate SO₂ removal and overall process operability with duct injection of slaked lime slurries and dry injection of calcium hydroxide powder with humidification. Detailed results from the project are presented in the following reports:

- Topical Report No. 1 -- Literature Review
- Topical Report No. 2 -- Evaluation of System Performance
- Topical Report No. 3 -- Scale-Up Testing
 - Advanced Configurations
 - Process Controls
 - Failure Modes
 - Waste Characterization

Project Final Report

The purposes of this report are: 1) to satisfy a contractual requirement for a separate topical report concerning the subject of mathematical model validation, and 2) to briefly describe the status of the model development and validation effort.

2.0 DISCUSSION

The Scope of Work for this project was written based on the assumption that first and second generation models would be available for validation during the course of the experimental program. The original plan consisted of performing separate test series specifically dedicated to model validation for two separate models. However, the models were not available, and it was necessary to change the approach to the development and validation effort. It was decided to use all process data obtained at the DITF pilot plant in the development effort for a second-generation model. This model development effort is being performed under separate contract by United Engineers and Babcock & Wilcox Company.

In view of this change in plans, a separate report which contains only model validation data is no longer appropriate. All process data to be used in the modeling effort are contained in the topical reports listed above, and these reports, together with electronic data files, have been provided to UEC/B&W.

The mathematical process model development task is being performed by Babcock & Wilcox under subcontract to United Engineers. The objective of the task is to develop a second generation computer model which can be readily used to predict the performance of a duct injection system for a specific plant. The approach to the task includes extending the first generation computer models developed under a DOE-sponsored Radian contract. These models consist of the DIAN3D duct injection computer model developed by CHAM, and the ESP model developed by ADA. The DITF data is being used in the development of an SO₂ capture prediction model which will be added to DIAN3D.

Earlier work on the Duct Injection program included correlations of SO₂ removal as a function of process conditions which were developed by Bechtel and by General Electric as a part of their separate projects.

Bechtel's correlation was developed for the Confined Zone Dispersion Process, and is shown in Table 2-1.

General Electric's correction was developed for in-duct scrubbing using a rotary atomizer in an earlier project performed at the DITF. General Electric's correlation is shown in Table 2-2.

In the current model development effort underway at B&W, Dr. Peter Harriott is evaluating a correlation to predict SO₂ removal at the duct spray dryer exit, or at the precipitator entrance. This correlation is shown in Table 2-3.

Comparisons are made between predictions of SO₂ removal derived from each of the above described correlations and two selected low- and high-SO₂ removal experiments performed at the DITF. These experiments were performed using slurry injection with recycle, and were selected because the process conditions represent SO₂ removal and calcium utilization values for duct injection which are believed to be economically competitive with other SO₂ control options (see Table 2-4).

Table 2-5 compares the B&W, Bechtel, and General Electric correlation predictions, respectively, with SO₂ removal achieved at the DITF. The Bechtel correlation predicts the SO₂ removal within 1.8% for the low Ca/S case (relative basis), and within 6.7% for the high Ca/S case. The General Electric Correlation also indicates good agreement with DITF experimental data at the ESP outlet with either set of constants shown on the left-side of Table 2-2. However, the GE correlation significantly over-predicts the SO₂ removals which were measured at the DITF ESP inlet. The B&W correlation shows good agreement with the DITF results at the ESP inlet.

A comparison of electrostatic precipitator performance as measured at the DITF with predictions using three different mathematical models is presented in the Project Final Report and Topical Report No. 3. This comparison illustrates that none of the models are useful in anticipating the conditions causing or predicting the results of electrically-induced reentrainment caused by low resistivity of ash-sorbent mixtures.

3.0 CONCLUSIONS

- The correlations developed during the course of the proof-of-concept projects performed by Bechtel and General Electric provide reasonably accurate predictions of SO₂ removal measured at the DITF ESP outlet for two important process conditions.
- Since significant amounts of SO₂ removal were measured across both the ESP and fabric filter at the DITF for all process conditions, the comprehensive process model now under development should include the capability for predicting SO₂ removal in the downstream particulate control system.
- A significant effort is needed to develop a method of anticipating the onset of and quantifying the results from electrical reentrainment of low-resistivity ash-sorbent mixtures in electrostatic precipitators downstream from a duct injection process.

Table 2-1. Bechtel Correlation of SO₂ Data at the ESP Outlet for Slurry Injection Tests with Calcitic Lime at the Campbell Site¹.

The correlation has the following form:

$$SO_{2rem} = K * (NWIR)^a * (Wt\%)^b * (Avg. SO_2)^c * (AST)^d$$

NWIR, Avg.SO₂, and AST are defined as:

$$NWIR = \frac{(1 - Wt\%) * V}{Q}$$

$$Avg. SO_2 = \frac{(SO_{2i} + SO_{2o})}{2}$$

Where

SO_{2rem} = Fraction of SO₂ removed at the ESP outlet
 NWIR = Normalized Water Injection Rate, gal/kscf
 V = Volumetric slurry flow, gallons per minute
 Q = Inlet flue gas flow rate at, kscfm
 Wt% = Solids in slurry, weight %
 Avg.SO₂ = Average SO₂ concentration, ppmv, wet basis
 AST = Approach to saturation, °F

and

K = 24.4
 a = 0.65
 b = 0.45
 c = -0.4
 d = -0.4

1. Bechtel National, Inc., "Desulfurization of Flue Gas by the Confined Zone Dispersion Method," Final Report to the Department of Energy, Contract DE-AC22-85PC81009, April 1988 (Draft).

Table 2-2. GE Correlation of SO₂ Data at the ESP Outlet for Slurry Injection Tests with a Rotary Atomizer at the DITF².

The correlation has the following form:

$$SO_{2rem} = 100 * (1 - e^{-aX^b})$$

X is defined as:

$$X = (Ca / S) * \ln \left(\frac{(T_i - T_{as})}{(T_f - T_{as})} \right)$$

Where

SO_{2rem} = SO₂ removal, %
 Ca/S = Dry stoichiometric ratio, mole/mole
 T_i = Flue gas temperature at the system inlet, °F
 T_{as} = Adiabatic saturation temperature, °F
 T_f = Flue gas temperature at the system outlet, °F

and for the ESP outlet

a = 0.50
 b = 0.675

or, for at the point where all of the slurry droplets have evaporated (the ESP inlet for this work)

a = 0.34
 b = 0.81

-
2. E. A. Samuel, K. R. Murphy, A. G. Demian, "A 12-MW Pilot Study of In-Duct Scrubbing (IDS) Using a Rotary Atomizer," Final Report to the Department of Energy, Contract DE-AC22-85PC81010, January, 1989 (draft).

Table 2-3. B&W Correlation of SO₂ Data at the ESP Inlet for DITF Slurry Injection Tests³.

The correlation has the following form:

$$SO_{2rem} = 100 * (1 - e^{(-NTU)})$$

$$NTU = \left[\frac{B1 * (Ca / S)}{(B2 * SO_{2i} + Ca / S)} \right] * \ln \left[\frac{T_i - T_{as}}{T_f - T_{as}} \right]$$

Where

SO _{2rem} =	SO ₂ removal at ESP inlet, %
NTU =	Number of Transfer Units
Ca/S =	Overall calcium to sulfur ratio, mole/mole
SO _{2i} =	SO ₂ concentration at duct inlet, ppm dry
T _i =	Flue gas temperature at duct inlet, °F
T _{as} =	Adiabatic Saturation Temperature, °F
T _f =	ESP inlet temperature, °F

and B1 and B2 are empirical constants.

$$B1 = 0.9708318$$

$$B2 = 0.0010912$$

3. Private communication with Dr. William Oberjohn, B&W Alliance Research Center, Alliance, Ohio, July 20, 1992.

Table 2-4. Test Cases for Predictive Correlations.

Parameter	Units	Low Ca/S Test Case	High Ca/S Test Case
Test Number		82-SR-01	69-SR-03
Date		2/13/92	11/15/91
Overall Ca/S Ratio	--	1.31	2.35
System Inlet			
Flue Gas Flow	dscfm	30781	32400
SO ₂ Level	ppm, dry	2033	2045
Flue Gas Temperature	°F	308	305
Saturation Temperature	°F	130	129
Water Content	%	8.80	8.63
ESP Inlet			
SO ₂ Removal	%	41.6	65.5
SO ₂ Level (at inlet O ₂)	ppm, dry	1148	663
Flue Gas Temperature	°F	171	153
Water Content	°F	12.2	12.6
Slurry Flow Rate	gpm	11.6	14.7
Slurry Solids	Wt. %	32.97	31.48
ESP Outlet			
SO ₂ Removal	%	54.5	88.3
SO ₂ Level (at inlet O ₂)	ppm, dry	924	239
Flue Gas Temperature	°F	171	164

Table 2-5. Predicted SO₂ Removal at the DITF from B&W, Bechtel, and GE Correlations.

Test Condition	SO ₂ Removal, %			
	Measured ¹	B&W Correlation ²	BechtelCorrelation ³	GE Correlation ⁴
Low Ca/S Ratio				
ESP Inlet	41.6	41.1	--	45.6
ESP Outlet	54.5	--	53.5	57.2
High Ca/S Ratio				
ESP Inlet	65.5	62.7	--	75.1
ESP Outlet	88.3	--	82.4	84.5

1. See Table 2-4
2. See Table 2-3
3. See Table 2-1
4. See Table 2-2

END

**DATE
FILMED**

4 / 12 / 93