PNL-8551
RETURN TO J.W. CAMMANN
- 2750E / D276 / 200E / 3-2531 -

**Preliminary Evaluation of the
Gaseous Effluent Sampling
Systems at the 291-A-1,
296-A-1, and 296-A-2
Stacks—Purex Plant**

June 1976

Battelle
Pacific Northwest Laboratories

MASTER

ds
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

PRELIMINARY EVALUATION OF THE GASEOUS EFFLUENT
SAMPLING SYSTEMS AT THE 291-A-1, 296-A-1, AND 296-A-2
STACKS -- PUREX PLANT

J.A. GLISSMEYER
L.C. SCHWENDIMAN

PARTICULATE & GASEOUS WASTE RESEARCH
ATMOSPHERIC SCIENCES DEPARTMENT

JUNE, 1976

Battelle
Pacific Northwest Laboratories
Richland, Washington

CONTENTS

LIST OF FIGURES.	iii
LIST OF TABLES	iii
I. INTRODUCTION	1
II. 291-A-1 STACK EFFLUENT SAMPLING SYSTEMS	3
Description of 291-A-1 Sampling Systems	3
196-Foot Level Inventory Sample	3
50-Foot Level Monitor Sample	5
50-Foot Level Back-up Inventory Sample.	12
Preliminary Evaluation of Sampling Systems	12
Sampling System Operation	13
Sample Aliquot Selection	16
Performance of Sampling Systems	21
Monitoring Instrumentation.	25
III. 296-A-1 STACK EFFLUENT SAMPLING SYSTEMS.	31
Description of 296-A-1 Sampling Systems	31
296-A-1 Inventory Sample	31
296-A-1 Monitoring Sample	34
Preliminary Evaluation of Sampling Systems	36
Sampling System Operation	38
Sample Aliquot Selection	39
Performance of Sampling Systems	41
Monitoring Instrumentation.	44
IV. 296-A-2 STACK EFFLUENT SAMPLING SYSTEM	48
Description of 296-A-2 Sampling System	48
Preliminary Evaluation of Sampling System	51
Sampling System Operation	51
Sample Aliquot Selection	52
V. SUMMARY OF PRELIMINARY EVALUATIONS	57
Areas in Compliance.	57
General	57
Monitoring Systems, 296-A-1, 291-A-1 Stacks	58
Monitoring System, 296-A-1.	58
291-A-1 Stack Probes.	58
Areas not in Compliance	58

CONTENTS (Continued)

General	58
Monitoring Systems, 291-A-1 and 296-A-1 Stacks	60
296-A-1 and 296-A-2 Stacks.	61
291-A-1 Stack	61
296-A-1 Stack	62
VI. RECOMMENDATIONS FOR CORRECTIVE ACTION.	63
General Recommendations	63
Monitoring Systems - 291-A-1 and 296-A-1 Stacks	66
291-A-1 Stack.	66
296-A-1 and 296-A-2 Stacks	67
VII. CONCLUSION	68
NOMENCLATURE.	69
REFERENCES	70
APPENDIX A	A-1
APPENDIX B	B-1
APPENDIX C	C-1

LIST OF FIGURES

1	Process Area Ventilation System.	4
2	196-ft and 50-ft Level Sampling Probes	6
3	Sampler Piping From 291-A-1 Stack to Sampling Building	7
4	196-ft Level Inventory Sample Piping in 292-A Building	8
5	50-ft Level Monitor and Back-up Inventory Sample Piping in 292-A Building.	10
6	Block Diagram at 291-A-1 Stack Monitor Instrumentation	11
7	296-A-1 Stack Sampling Systems	32
8	296-A-1 Stack Inventory Sampling System	33
9	296-A-1 Stack Monitor Sampling System.	35
10	296-A-1 Stack Monitor Instrument Block Diagram.	37
11	296-A-2, West Sample Gallery Hood Exhaust, Stack	49
12	296-A-2 Stack Particulate Inventory Sampling System	50

LIST OF TABLES

1	Minimum Required Flowrates	20
2	Particulate Extraction Bias of 291-A-1 Effluent Sampling Probes	22
3	Percent Delivery of Monodispersed Aerosols Through Sample Delivery Lines, 291-A-1 Stack	24
4	Combined Estimate of Percent Penetration of Monodispersed Aerosols to the Collection Filter, 291-A-1 Stack	25
5	Particulate Extraction Bias of 296-A-1 Stack Effluent Sampling Probes	41
6	Percent Delivery of Monodispersed Aerosols Through Sampler Piping, 296-A-1 Stack.	42

LIST OF TABLES (Continued)

7	Combined Estimate of Percent Penetration of Monodispersed Aerosols to the Collector, 296-A-1 Stack	43
8	Particulate Extraction Bias of 296-A-2 Stack Effluent Sampling Probe.	54
9	Percent Monodispersed Aerosol Delivery Through Sampling Probe, 296-A-2 Stack	55

PRELIMINARY EVALUATION OF THE GASEOUS EFFLUENT SAMPLING SYSTEMS AT THE 291-A-1, 296-A-1, AND 296-A-2 STACKS -- PUREX PLANT

I. INTRODUCTION

The particulate effluent sampling and monitoring systems at three Purex Plant Stacks, 291-A-1, 296-A-1, 296-A-2, are the subjects of this evaluation for compliance with Atlantic Richfield Hanford Company's Interim Criteria for such systems (Appendix A). This evaluation is part of a larger study, sponsored by ARHCO and conducted by Battelle-Northwest, of gaseous effluent sampling systems in ARHCO operated facilities. The conclusions and recommendations of this report are considered preliminary because the conclusions have not been experimentally verified and because of the many uncertainties about system characteristics.

In the following three parts the sampling and monitoring systems at each of the stacks will be described and evaluated. The main points of the evaluations will then be summarized. Following that, the recommendations for corrective action will be outlined. For the reader's convenience, the appendices include copies of the Interim Criteria and the ARHCO emergency procedures referred to in this report.

The part covering the 291-A-1 stack is more detailed than the parts covering the other two stacks because the requirements

of the Interim Criteria are discussed in greater detail there. It is assumed that by the time the reader encounters the sections covering the 296-A-1 and 296-A-2 stacks that he is reasonably familiar with the evaluation criteria.

II. 291-A-1 STACK EFFLUENT SAMPLING SYSTEMS

Description of 291-A-1 Sampling Systems

The 291-A-1 stack is the main exhaust stack at the Purex Plant and is 200-ft tall. It consists of a tapered outer concrete chimney which supports an inner cylindrical stainless steel stack which has an inside diameter of 7ft. This stack exhausts the bulk of the ventilation air that has passed through the process areas of the plant and the two parallel glass wool filter beds (see Figure 1). The ventilation system has two electric supply fans, three electric exhaust fans and a steam turbine emergency exhaust fan. By using different combinations of supply and exhaust fans the ventilation flowrate is varied according to the status of the plant. Currently the plant is operated in the "minimum safe" status as shown in Figure 1 and the flowrate is about 81,000 CFM according to the most recent ARHCO Vent and Balance measurements. There is a stack flow monitor which input is part of a pitot tube bank at the stack base. The flowrate is read on a strip chart recorder in the 202-A building power control room and recently indicated a flowrate of 93,000 CFM.

There are three particulate samples being collected from the 291-A-1 stack: an inventory (or record) sample from the 196-ft level, a back-up inventory sample from the 50-ft level and a monitor sample from the 50-ft level. Both inventory sample filters are changed every Thursday, and oftener if there is an abnormal release. Both inventory samples are sent to the 222-S air sample counting room for analysis.

196-Foot Level Inventory Sample

The inventory or record sample (EDP Code 552) is a subsample of a larger sample airstream withdrawn from the stack at the

PROCESS AREA VENTILATION SYSTEM

SYSTEM OPERATING REQUIREMENTS

1. NORMAL (ALL CANYON CELL COVERS IN PLACE).
     1 SUPPLY FAN DELIVERING 141,000 cfm
     3 ELECTRIC EXHAUST FANS REMOVING 112,000 cfm
 2. MAXIMUM (ONE OR TWO CELL COVER REMOVED FROM ONE CELL).
     1 SUPPLY FAN DELIVERING 118,000 cfm
     3 ELECTRIC EXHAUST FANS REMOVING 141,000 cfm
 3. MINIMUM SAFE (ALL CELL COVERS IN PLACE, ONE SUPPLY FAN OFF).
     1 SUPPLY FAN DELIVERING 70,000 cfm
     3 or 3 1/2 ELECTRIC EXHAUST FANS REMOVING 94,000 cfm
 4. EMERGENCY (ALL CELL COVERS IN PLACE, OPERATION CONTAINED).
     1 SUPPLY FAN STOPPING
     1 TURBINE GIVEN FAN EXHAUSTING 61,000 cfm

FIGURE 1
Process Area Ventilation System

196-ft level. The probe in the stack consists of five nozzles, with each located in one of five equal annular areas (Figure 2). The larger or primary sample airstream passes through approximately 233-ft of straight 2-in. pipe, the equivalent of about twelve 90° bends and one gate valve to a manifold in the 292-A sampling building (Figures 3 and 4). The manifold is divided by another gate valve into intake and exhaust sides.

Because of the pressure drop caused by the manifold gate valve the subsample is withdrawn from the intake side of the manifold through a 90° bend, a gate valve and another 90° bend to an in-line filter holder containing a 47-mm diameter HV-70 asbestos fiber filter. After the particulates are filtered from the subsample the airstream passes through a rotameter and on to the exhaust side of the primary sampling stream manifold. The vacuum source for the sampling system is a steam powered air ejector in the 292-A building.

The primary sample airstream flowrate is measured with an orifice meter and manometer just downstream of the exhaust manifold. The subsample flowrate is measured by the rotameter. The design flowrate for the primary sample stream is 50 CFM and the rotameter in the subsample airstream reads 0.5 SCFM. The orifice meter manometer reads 33-in. of water differential pressure.

To prevent moisture condensation in the primary sampling lines, the piping is steam lagged between the stack and the sampling building. There is no indication of the temperature and pressure of the sample airstreams.

50-Foot Level Monitor Sample

Like the record sample, the monitor sample is a subsample of a primary airstream which originates at the 50-ft level of the stack. The primary sample intake probe is identical to that described previously and shown in Figure 2.

FIGURE 2
196-ft and 50-ft Level Sampling Probes

PIPING SUMMARY

50 ft. LEVEL SAMPLER:
 SEVEN 90° BENDS
 ONE 76° BEND
 TWO 45° BENDS
 348 in. HORIZONTAL
 380 in. VERTICAL

196 ft. LEVEL SAMPLER:
 SEVEN 90° BENDS
 ONE 74° BEND
 TWO 45° BENDS
 368 in. HORIZONTAL
 2140 in. VERTICAL

ALL PIPING EXCEPT PROBES
 IS 2 in. SCHEDULE 40

FIGURE 3
 Sampler Piping From 291-A-1 Stack
 to Sampling Building

PIPING SUMMARY

2 in. SCHEDULE 40 PRIMARY LINES:

THREE 90° BENDS
TWO 30° BENDS
290 in. HORIZONTAL

SUBSAMPLE LINES:

ONE 90° BEND	0.308 in. ID NOZZLE
ONE 90° BEND	1/2 in. SCHEDULE 40 PIPE
12 in. HORIZONTAL	1/2 in. SCHEDULE 40 PIPE
4 in. VERTICAL	1/2 in. SCHEDULE 40 PIPE

FIGURE 4

196-ft Level Inventory Sample Piping in 292-A Building

The primary sample passes through approximately 71-ft of straight 2-in. pipe, one gate valve and the equivalent of eleven 90° bends. The primary sample airstream also passes through a manifold like that described previously. From this manifold both the monitor and back-up record subsamples are obtained (see Figure 5). The monitor sample is withdrawn from the manifold through a 90° bend and then passes through a gate valve, rotameter, two elbows, a length of 1-in. Tygon tubing with bends in it, and into a moving filter tape device (Victoreen Model 790 Tape Sampler). The rotameter reads 0.9 SCFM.

The particulates are collected on spots on the 4-in. wide asbestos fiber filter tape (HV-70). The tape drive advances the filter every thirty minutes exposing a fresh spot on the filter. While the sample is being collected on one spot, the previously exposed spot is counted by the detector for a 3-min. period.

After the collector/detector, the sample airstream then passes back to the exhaust side of the manifold. The vacuum for the sampling system is provided by a steam powered air ejector and the primary sample stream flowrate is measured by an orifice meter and manometer downstream of the exhaust manifold. The primary sample airstream is designed for a flowrate of 50 CFM, however, the manometer is not currently operational. The primary sample piping between the stack and the 292-A building is steam lagged; however, there is no temperature or pressure indication for the sample airstream.

The monitoring instrumentation is diagramed in Figure 6. The detection instrument is an alpha scintillator and photo-multiplier and the discriminator is set to admit energy pulses greater than 2 MeV to the count rate meter. The count rate meter has full scale linear ranges of 10 to 10^5 c/sec and is

PIPING SUMMARY

MONITOR SAMPLE	BACK-UP INVENTORY SAMPLE
2 in. SCHEDULE 40 PRIMARY LINES: - TWO 90° BENDS 122 in. HORIZONTAL - SUBSAMPLE LINES: - ONE 90° BEND - THREE 90° BENDS - TWO 90° BENDS 14 in. HORIZONTAL 10 in. VERTICAL	2 in. SCHEDULE 40 PRIMARY LINES: - SAME AS FOR MONITOR SAMPLE BUT AN ADDITIONAL 12 in. HORIZONTAL - SUBSAMPLE LINES: - ONE 90° BEND - ONE 90° BEND 12 in. HORIZONTAL 4 in. VERTICAL

FIGURE 5

50-ft Level Monitor and Back-up Inventory Sample Piping in 292-A Building

FIGURE 6
Block Diagram of 291-A-1 Stack Monitor Instrumentation

normally set on the 0-200 c/sec range. The high release level alarm is activated by the recorder when the reading is 60% of scale (or normally 120 c/sec). The high-level alarm is a panel light in the dispatcher's office in the 202-A building. The portion of the monitoring instrumentation in the control room and dispatcher's office is supplied by emergency power and the collector/detector tape head has emergency power available (Appendix B).

50-Foot Level Back-up Inventory Sample

The back-up inventory sample serves as a comparison for the 196-ft level inventory sample. The back-up inventory sample is a subsample of the same 50-ft level primary sample airstream from which the monitor sample is obtained (see page 9 and Figures 2, 3 and 5).

The subsample passes through a 0.308-in. ID nozzle, a 90° bend, a gate valve and another 90° bend to a modified Hanford design in-line filter holder.^[4] The filter holder was designed for a 4 x 8 in. filter, but a plastic sheet with a 4-in. diameter cutout has been taped over the filter support. A 4-in. diameter HV-70 filter is placed over the cutout and collects the particulates. From the filter the sample is then piped to the exhaust side of the manifold.

A differential pressure gauge is connected across the 4 x 8 filter holder to serve as a flowmeter. The device is reportedly calibrated with a filter in place, so when the pressure drop is about 7-in. of water the flowrate is 5 CFM.

Preliminary Evaluation of Sampling Systems

This preliminary evaluation of the 291-A-1 stack sampling systems will address the effects of the operation of the

sample collection equipment, the selection of sample aliquots and the performance of the sample collection devices upon the representativeness* of the collected samples. The compliance of the sample monitoring instrumentation with the Interim Criteria will then be considered.

Sampling System Operation

The elements of the sampling system operation which affect the representativeness of the collected samples are: 1) the use of separate inventory and monitor samples, 2) the control of condensation in the sample delivery piping, 3) the measurement of sample and stack flowrates, and 4) the continuity of sampling under various conditions.

Inventory and Monitor Samples. The detector/filter geometry required for the monitor usually hinders the collection of a representative sample. The Interim Criteria require that an inventory sample be collected separate from the monitor sample (Sampling Criterion No. 5). The use of the 196-ft level inventory sample and the 50-ft level back-up inventory sample exceeds this requirement.

Condensation in Sample Delivery Piping. The condensation of moisture in the piping which extracts and delivers the particulate sample to the filter can cause significant deposition

---

*A representative sample withdrawn from the bulk gas is one in which the particulate concentration equals the average particulate concentration in the effluent airstream. Also, the size distribution of particulates in a representative sample air-stream is the same as in the total effluent. Finally, a collected particulate sample is representative when the mass, divided by the amount of sample air from which it was collected, equals the average particulate concentration of the effluent. By collected we mean separated from the sample airstream (by a filter, usually) and held for observation. Since perfectly representative samples cannot be guaranteed, the interim criteria define allowable deviation from ideally representative. [5,p.5]

and subsequent uncontrolled washout of sampled particulates. This results in uncertainty as to the source of radioactive particles collected on the filter and is to be avoided (Sampling Criterion No. 6). All of the sample delivery lines between the stack and the 292-A sample building are steam lagged in an attempt to maintain a sample temperature above the sample air dewpoint. Because moisture on sample filters has not been observed it is concluded that moisture condensation is not a serious problem here.

Measurement of Sample and Stack Flowrates. The accurate measurement of effluent and sample flowrates is necessary because both flowrates enter into the calculations of release concentration and total release. The accuracy of sample airstream flow measurements is certainly questionable with regard to all the subsample and primary sample airstreams.

The rotameters in use in the 196-ft level inventory subsample line and the 50-ft level monitor subsample line were factory calibrated to measure airflow at standard conditions (70°F, 29.92-in. mercury). However, the lack of a recalibration and proper temperature and pressure indicators show that no effort is made to correct the rotameter readings for the actual conditions under which they are used. There is also evidence of corrosion and deterioration of the rotameters which casts further doubt upon the reliability of the readings.

The differential pressure meter associated with the 50-ft level back-up inventory sample has reportedly been calibrated for a flowrate of 5 CFM. There is, however, no markings or calibration posted so that the flowrate can be adjusted accurately. Also, it is doubtful that the calibration was performed with the conditions of actual use accounted for. Also, there is no pressure or temperature instrumentation in

the sampling line to indicate if corrections to the readings are necessary. Finally, the differential pressure measuring method as applied here is questionable because of the inferior mounting of the HV-70 filter in the modified filter holder.

The measurement of airflow in both primary sampling lines has apparently become ignored. It is assumed that the orifice meters were calibrated at one time; however, there are no calibrations posted or marked on the U-tube manometers used to measure the orifice differential pressure. Also, the manometer used with the orifice meter in the 50-ft level primary sampling line is inoperable.

The continuous or frequent stack flow measurement is important in the case of the 291-A-1 stack because the stack flow can be changed considerably. A knowledge of changing stack flows is not only important for total release and concentration calculations but also for adjustments to sample flowrates to maintain isokinetic sampling. The stack airflow measurements performed by the ARHCO Vent and Balance Subsection probably have satisfactory accuracy. However, the readings of the stack flow monitor in the power control room do not compare well with the Vent and Balance readings because only one portion of the array of pitot tubes at the stack base is used for the measurement. The portion of the pitot tube array used and its calibration should be reviewed.

In order to address some of the remaining topics in this section on the 291-A-1 stack it will be assumed that the rotameter readings are correct, the back-up inventory sample flowrate is 5 CFM and the primary sample airflows are 50 CFM. These flowrates and the stack flowrate will be further assumed to be measured at the common standard conditions for volume flowrate, i.e., 70°F and 29.92-in. of mercury. Thus, the conclusions reached will not be exact, but will indicate sampling problem areas.

Continuous Sampling. It is required that the stack airflow be sampled as long as any of the exhaust fans are operating. Therefore, the sampling vacuum source should have as many back-up systems as the stack exhaust fans (Sampling Criterion No. 7). The only back-up fan in case of an electrical power outage is the steam driven turbine fan. There is no emergency electrical power to the exhaust fans. The operation of the sampling vacuum is independent of electrical power and dependent only on the steam supply; should normal supply be interrupted the 200-E Powerhouse has a standby boiler. Thus, the sampling system vacuum is operable as long as the steam turbine fan is operable, unless of course there is a steam leak or ejector malfunction in the sampling building. There is no alarm to indicate a loss of vacuum due to a vacuum system malfunction.

Sample Aliquot Selection

The size of the sample aliquot (or volume of sampled air as determined by the sample flowrate and collection interval) and the location of sample extraction are the important considerations in the choice of the sample aliquot. Under the heading "Sampling Location", the choice of extraction locations for both monitor and inventory samples will be discussed. However, in the discussion of sample aliquot size only the inventory sample will be considered, leaving the consideration of monitor sample aliquot size to the discussion entitled "Monitor Sensitivity and Range." This separation is made because the requirements of aliquot size are different for the two samples. The sample aliquots of the inventory and monitor samples are governed by Sampling Criterion No. 1 and Monitoring Criterion No. 1, respectively.

Sampling Location. One requirement for collecting inventory and monitor samples that are representative of the effluent is that they be extracted from locations where the particulate concentrations are representative (or an average) of the effluent (Sampling Criterion No. 4). The 50-ft level and 196-ft level probes are about 7 and 28 stack diameters respectively, from the effluent entrance to the stack and about 21 and 0.6 stack diameters respectively from the effluent discharge. Thus, neither of these sampling probes are located at sufficient distances from major airflow disturbances as suggested by the ANSI standard, N13.1^[6,p.26] (10-stack diameters downstream and 5-stack diameters upstream from significant airflow disturbances). However, the existing locations may not seriously inhibit representative sample extraction and are certainly better located than the probes at the other stacks considered in this report. As for the sub-sample probes, they are as well located as can be expected for the geometry of the manifolds.

A point in favor of the existing stack probes is that there is an inlet nozzle located in each of five equal cross-sectional areas perpendicular to the direction of airflow (see Figure 2). This is in accordance with the suggestions of the ANSI standard.^[6,p.27]

Inventory Sample Aliquot Size. The major factors determining the size of the inventory sample aliquot are the lowest average concentration level that must be measured, the required accuracy of the measurement, the time period over which the concentration must be averaged and the analytical technique. Sampling Criterion No. 1 defines (or assumes knowledge of) these factors.

Sampling Criterion No. 1 requires that the lowest average concentration measureable must be at least as low as

6×10^{-14} $\mu\text{Ci/cc}$ * of ^{239}Pu ; this concentration being the most restrictive of those for ^{90}Sr and ^{239}Pu in the ARHCO emergency procedures (Appendix C) or ERDA requirements.^[7] The criterion also states that the averaging time period is 24-hrs. The required accuracy is not stated but $\pm 10\%$ at the 95% confidence level will be assumed for this report as a reasonable accuracy to work with.

The current analytical technique used in the 222-S counting room for air samples has been outlined in detail elsewhere.^[8,9] A Beckman Wide Beta II Analyzer is used as the counting instrument. Alpha emitter background level is as high as 0.2 c/min (measured over five minutes) and the sample counting time is one minute.

The equation used for the calculation of released alpha-emitter concentration is:

$$\frac{\mu\text{Ci}}{\text{cc}} = \text{long-lived net c/min} \times \frac{1}{0.296 \text{ c/d}^{**}} \times \frac{\text{min}}{\text{sample flowrate, ft}^3} \times \frac{\text{ft}^3}{28,317 \text{ cc}} \times \left(\frac{1}{0.7^{***}} \right) \times \frac{1}{1440 \text{ min.}^\dagger} \times \frac{\mu\text{Ci} \cdot \text{min}}{2.22 (10^6) \text{ d}} \quad (1).$$

The calculation assumes that an ideally representative sample is collected. This equation can be rearranged as follows so that the minimum sample flowrate required for measuring a given concentration can be calculated once the net count rate necessary for a given counting accuracy is set.

*The volume will be assumed to be measured at standard conditions.

**The counting efficiency for ^{239}Pu is 0.296 counts per disintegration.

***The value of 0.7 is an estimate of the effects of radioactive particle imbedment, absorbence by the HV-70 asbestos fiber filter and collection efficiency.

†The duration of the sampling period is one day or 1440-min.

$$\text{Sample flowrate, CFM} = \frac{\text{net long-lived c/min}}{\text{concentration, } \mu\text{Ci/cc}} \times 5.33 (10^{-14}) \quad (2)$$

The net long-lived count is derived from two successive gross counts which are spaced at least five hours apart to account for the natural background from the radon daughters. [8] The following equation is frequently used to estimate the 95% confidence intervals when there are greater than fifty total counts: [10]

$$\text{Interval limit} = 1.96 \sqrt{\frac{\text{net c/min} + \text{background c/min}}{\text{sample counting time}} + \frac{\text{background c/min}}{\text{background counting time}}} \quad (3)$$

It can be shown that for a 95% confidence level accuracy of $\pm 10\%$ that a derived net count rate of at least 380 c/min is required with the current analytical procedure.

Inserting the required net long-lived count rate and concentration into equation 2 the minimum required sample flowrate can be calculated. Table 1 shows both the required flowrates for various concentrations and the measureable concentrations at the current assumed inventory sample flowrates.

The table shows that the ^{239}Pu 24-hr concentrations measureable at the assumed accuracy with the existing sample flowrates are two to three orders of magnitude greater than required by the criterion. Clearly, it is impractical to measure the required concentration using the existing laboratory procedure. For example, assume the sample counting time is lengthened from one minute to an hour. Equation 2 then shows that a net count rate of only 8 c/min (a total of 480 counts)

TABLE 1

Minimum Required Flowrates

<u>Reference</u>	<u>Alpha-Emitter Concentration $\mu\text{Ci/cc}^*$</u>	<u>Required Flowrates For Measurements at 95% Confidence Level, $\pm 10\%$ Accuracy, SCFM*</u>
Table II ^[7]	6.0×10^{-14}	338
Table I ^[7]	2.0×10^{-12}	10
Class I Emergency	2.8×10^{-12}	7.2
1/2-Class I Emergency	1.4×10^{-12}	14.5
196-ft Level Inventory	4.1×10^{-11}	0.5
50-ft Level Inventory	4.1×10^{-12}	5

*The flowrates and volumes are assumed to be at standard conditions.

†The Class I Action Level concentration is calculated as follows assuming the most restrictive case of maximum stack airflow, 126,000 SCFM. The weekly release limit for ^{239}Pu is taken from the emergency procedure in Appendix C.

$$\text{Class I } ^{239}\text{Pu Concentrations} = 1/10 \times 10^{-3} \text{ Ci/wk} \times \text{min}/126,000 \text{ ft}^3$$

$$\times \text{wk}/10,080 \text{ min} \times \text{ft}^3/28,320 \text{ cc}$$

$$\times 10^6 \mu\text{Ci/Ci} = 2.8 (10^{-12}) \mu\text{Ci/cc}$$

is necessary for the assumed accuracy. The minimum flowrate required to measure a 24-hr ^{239}Pu concentration of $6 \times 10^{-14} \mu\text{Ci/cc}$ is then reduced from 338 SCFM to 7.1 SCFM. Although this reduced flowrate is still higher than any of the existing sample flowrates it is a much more practical target than 338 SCFM.

It must also be realized that the sample flowrates calculated above are only minimums, because only the accuracy of counting statistics is accounted for and the collected sample is assumed to be ideal.

Performance of Sampling Systems

Under this heading the effects upon the representativeness of the collected samples caused by extraction, sample particulate delivery from probe to filter, and filter collection efficiency will be discussed.

Extraction. Extraction is defined as separating the sample airstream from the airstream approaching the probe nozzle. The act of extraction can cause a bias in the concentration of particulates in the sample airstream relative to the particulate concentration of the approach airstream. The degree of bias is a function of particle size, isokinesis* and nozzle design. The effect of particle size and isokinesis upon concentration bias can be estimated by calculations. [11]

For each of the three sampling systems at the 291-A-1 stack there are two opportunities for an extraction bias to occur because each sample is extracted from the stack and then extracted from the primary sample airstream manifold. In each instance the extraction is performed nonisokinetically; however, the primary samples are extracted nonisokinetically because the standby condition effluent flowrate is below what the two stack probes were designed for. Table 2 shows the bias in the concentration (or number) of sampled particulates for each instance of sample extraction and for various sizes of particulates. The flowrates assumed are also mentioned in the table and these assumptions have been explained earlier (pages 15-17).

The combined bias of a particular sample caused by non-isokinetic extraction is estimated by multiplying the bias caused by the stack probe by the bias caused by the sub-sample probe. For example, the bias in concentration of 10 μ m AED particles in the back-up inventory sample due to extraction

---

*The ratio of air velocity just inside the nozzle orifice to the air velocity approaching the nozzle orifice.

TABLE 2

Particulate Extraction Bias of 291-A-1
Effluent Sampling Probes

<u>Particle Size μm AED*</u>	<u>Stack Probes</u>	<u>196-ft Level Inventory Subsample</u>	<u>50-ft Level Monitored Subsample</u>	<u>50-ft Level Inventory Subsample</u>
0.5	1.00	1.01	1.00	1.00
1	1.00	1.02	1.00	.99
2	.99	1.08	1.02	.95
5	.96	1.36	1.07	.77
8	.91	1.64	1.12	.59
10	.88	1.78	1.15	.51

Sample
Flowrate   10 CFM   0.5 CFM   0.9 CFM   5 CFM

Assumed Stack Airflow 81,000 CFM.

Assumed Conditions 70°F, 14.7 psia.

*The AED, or aerodynamic equivalent diameter is defined as the diameter of a hypothetical particle of unit density (water) which has the same settling velocity as a given particle. AED is the most important parameter in describing the aerodynamic behavior of particles.

effects is calculated as $0.83 \times 0.51 = 0.45$. This means that because of extraction effects alone the back-up inventory sample will collect less than 50% of the 10 μ m AED particles than would be representative for the aliquot.* Of the three samples

*It must be noted that the bias calculated for the stack probes is for a stack flowrate of 81,000 SCFM. With the effluent airflow at full capacity the bias is much less pronounced because the sample and stack air velocities will be more closely matched. Thus, at full capacity the combined biases will be less severe.

collected, the monitored sample is the only one for which the combined extraction effects result in an unbiased sample (and that is only because the two biases cancel each other).

Delivery and Collection. The other factors, affecting the representativeness of the collected samples are the losses of particles inside sampler piping and the penetration of particles through the collection filter.

Each of the three samples are collected on HV-70 filter paper. The collection efficiency of this type of filter for 0.3 μm DOP test aerosol is reported to be about 98%^[6] at the face velocities of the current systems. The collection efficiency for the particle sizes under consideration, therefore, is herein taken to be 100% (which would mean that there is no adverse effect on the representativeness of the collected samples).*

The effect of deposition of particles in piping upon the sample representativeness can be estimated as outlined in a previous report.^[11] Table 3 shows the calculated fractional delivery of various sized monodispersed aerosols through the piping of each of the three sampling systems. The assumed flowrates and conditions are the same as those shown in Table 2.

The table shows that the fractional delivery through the piping is very poor for particles larger than 2 μm AED. The major contributors to loss of particles are the lengthy primary sample transport piping and bends. Although not accounted for by calculations, the valves, fittings and rotameters between sample probes and filters will also cause considerable losses of particles.

*The actual collection efficiency of the filter is in question and an overall filter efficiency of 70% is assumed by ARHCO. This efficiency also includes some correction for self absorption and particle imbedment as well. The rationale behind the choice of a 70% efficiency is not documented.

TABLE 3

Percent Delivery of Monodispersed
Aerosols Through Sample Delivery Lines,
291-A-1 Stack

<u>Particle Size μm AED</u>	<u>196-ft Level Inventory Sample</u>	<u>50-ft Level Monitor Sample</u>	<u>50-ft Level Back-up Inventory Sample</u>
0.5	97	99	98
1	88	94	91
2	60	78	69
5	3	20	9
8	<1	1	<1
10	<1	<1	<1

Another way that the loss of particles adversely affects representative sampling is that the accumulated radioactive particles in the piping can be a considerable secondary source of particles as they can possibly become resuspended at some later time. The collection of resuspended radioactive particles can give false indications of the actual radioactive particle concentration of the effluent.

The following table shows the combined effects of extraction caused bias and fractional delivery of particulates. The combined effect is calculated by multiplying the bias by the fractional delivery for each sample and particle size.

TABLE 4

Combined Estimate of Percent Penetration
of Monodispersed Aerosols to the Collection Filter,
291-A-1 Stack

<u>Particle Size μm AED</u>	<u>196-ft Level Inventory Sample</u>	<u>50-ft Level Monitor Sample</u>	<u>50-ft Level Back-up Inventory Sample</u>
0.5	98%	99%	98%
1	90	94	90
2	64	79	65
5	4	21	7
8	<1	1	<1
10	<1	<1	<1

The table shows clearly that none of the 291-A-1 stack sampling systems meet the criterion that 90% of 10 μm AED particles in the sample aliquot must be collected on the filter.*

Monitoring Instrumentation

In this evaluation of the monitoring instrumentation the topics of sensitivity and range, alarms, and continuous operation and maintenance will be addressed.

Sensitivity and Range. The monitoring instrumentation for the 291-A-1 stack radioactive particulate effluent is set

*It must be noted that when the plant is operating the stack airflow is much higher. Thus, the combined penetrations of particles to the filter estimated in Table 4 will be slightly higher. This is because of the decreased extraction bias at the stack probes (see footnote on page 22). However, the improvement is insignificant because of the severe deposition of the large particles.

to monitor collected alpha-emitters with energy greater than 2 MeV. The alpha-emitters are usually assumed to be ^{239}Pu inasmuch as that is the isotope expected; however, the collected of radon-thoron daughters may contribute some background.

The monitoring instrumentation is required to detect above background an activity release at least as low as one-half that required for a Class I Action Level (Monitoring Criterion No. 1). Also the instrumentation must have enough range to detect a release at least as great as one hundred times the Class II Action Level (Monitoring Criterion No. 10). Both Class I and Class II Action Levels are concerned with the detection of a 24-hour average ^{239}Pu release concentration of $2.8 (10^{-12}) \mu\text{Ci/cc}$ or a 24-hr total release of $1/7 \times 1/10$ of the weekly limit (see Table 1 and Appendix C).

To be able to exactly assess the compliance of the monitoring instrumentation with these criteria it is necessary to know both the detector efficiency with the HV-70 filter and the usual background contribution from radon-thoron daughters and other contaminants; however, these facts have not been determined. The analysis is further complicated by the fact that the collection filter is changed every thirty minutes (by the moving tape drive) and the sample flowrate is uncertain. Thus, a definitive analysis of compliance with the criteria cannot be made here; however, making certain assumptions about the system an analysis can be made that is indicative of the situation.

First, it will be assumed that the sample flowrate is 0.9 SCFM, the release level in question is uniform during the 24-hr period, the counting efficiency of the detector is 10% and an ideally representative sample is collected. With these

assumptions the detected count rate at the end of the 30-min collection period for a release corresponding to one-half of a Class I Action Level can be calculated as follows:

$$\begin{aligned} \text{detected count rate} &= \frac{1}{2} \times 2.8 (10^{-12}) \mu\text{Ci/cc}^* \times 0.1 \text{ c/d} \\ &\quad \times 0.9 \text{ ft}^3/\text{min} \times 30 \text{ min} \times 2.2 (10^6) \\ &\quad \text{d/min} \cdot \mu\text{Ci} \times 28,320 \text{ cc/ft}^3 \\ &= 0.24 \text{ c/min or } 0.004 \text{ c/sec} \end{aligned} \quad (4)$$

Similarly, for a hypothetical uniform release of one-hundred times the Class II Action Level occurring uniformly during a day, the detected count rate at the end of the 30-min collection period is calculated as follows:

$$\begin{aligned} \text{detected count rate} &= 100 \times 2.8 (10^{-12}) \mu\text{Ci/cc} \times 0.1 \text{ c/d} \\ &\quad \times 0.9 \text{ ft}^3/\text{min} \times 30\text{-min} \times 2.22 (10^6) \\ &\quad \text{d/min} \mu\text{Ci} \times 28,320 \text{ cc/ft}^3 \\ &= 48 \text{ c/min or } 0.79 \text{ c/sec}^{**} \end{aligned} \quad (5)$$

A recent observation of the count rate meter showed a counting rate of 25-35 c/sec, which may be attributable to background. Thus, these preliminary calculations indicate that the existing monitoring system may not provide sufficient sensitivity to detect the two release levels considered, because the calculated counting rates would scarcely be noticed

---

*This concentration from Table 1 was calculated for the most restrictive case; i.e., when the stack airflow is at the maximum. At the present stack flow of 81,000 CFM the concentration is $4.3 (10^{-12}) \mu\text{Ci/cc}$ and the detected count rate for an ideally representative sample is then 0.006 c/sec.
 **Again, at the present stack flowrate the Class I Action Level concentration is higher and the detected count rate is then 1.2 c/sec.

above what may be the background on the count rate scale or recorder. This also holds true even for the current lower stack flow.

Although it is clear that the present instrumentation has sufficient range, the apparent sensitivity is not sufficient. The actual counting efficiency and background level need to be determined and this question reevaluated. The use of a 30-min sample collection time and low flowrate certainly inhibit achieving the required sensitivity.*

Alarms. The Monitoring Criteria require two types of alarms associated with the monitoring instrumentation. Monitoring Criterion No. 7 requires "fail-safe" alarms for instrument malfunction and loss of vacuum; however, such an alarm is absent from the 291-A-1 monitoring system. Also, an alarm is required when a Class II Action Level release occurs (Monitoring Criterion No. 7)**. The present alarm is actuated when 120 cps

---

*It is interesting to compare the hypothetical calculated count rates for a release level of $1/2 \times$ Class I Action Level for both the 291-A-1 and 291-Z-1 stacks. The 291-Z-1 stack is one which also is monitored for alpha emitting particulates. The hypothetical calculated count rate for $1/2 \times$ Class I Action Level at 291-A-1 is 0.24 c/min (equation 4) while at 291-Z-1 it is 66 c/min (see page 14 of reference No. 5). This nearly three-hundred fold difference is mainly due to four reasons: (1) the Class I Action Level is $1/10 \times$ the weekly limit of ARH-220^[12] at 291-Z-1, and $1/7 \times 1/10 \times$ the same weekly limit at 291-A-1; (2) differences in effluent flowrates; (3) differences in sample flowrates; and (4) differences in sample collection time. These differences, each of which seems minor when considered by itself, are quite significant when combined. It is also interesting to note that with the instrumentation at 291-Z-1 the 66 c/min was noticeable above background, but with the instrumentation at 291-A-1 the 66 c/min may go unnoticed.

**This requirement is ambiguous because a Class II Action Level can only be determined after two successive 24-hr periods (see the definition in Appendix C). However, the interpretation assumed is that the alarm must actuate when the average release concentration exceeds $2.8 (10^{-12}) \mu\text{Ci/cc}$. Thus, at the end of the 30-min collection period the alarm must actuate at 0.008 c/sec (see equation 4)!

is detected, which is much too high. If the present alarm were actuated at the end of the 30-min sample collection period the magnitude of the release would be:

$$\begin{aligned} 30\text{-min release} &= 120 \text{ c/sec} \times 10 \text{ d/c} \times \mu\text{Ci-min}/2.22(10^6)\text{d} \\ &\times 60 \text{ sec/min} \times 81,000 \text{ CFM}/0.9 \text{ CFM} \end{aligned}$$

$$30\text{-min release} = 3(10^3) \mu\text{Ci or } 0.003 \text{ Ci}$$

That thirty minute release would thus be three times the weekly limit for ^{239}Pu stated in the emergency procedure in Appendix C. A Class IV Emergency would occur if that 30-min average release rate (i.e., if the alarm tripped just at the end of each 30-min collection period) lasted for two hours or more!

The Monitoring Criteria also require that the alarms are visual and audible in a continuously occupied area (Monitoring Criterion No. 9). The location where the alarms are located, the dispatcher's office, is not continuously occupied at the present time.

Maintenance and Continuous Monitoring. The continued operation of the monitoring instrumentation during a power outage, when the steam turbine exhaust fan is operating, is insured by the availability of emergency electrical power. However, because the detector only monitors the collected sample for three minutes after the sample is collected for a 30-min period the actual monitoring is not continuous. Thus, this system does not satisfy the criterion of continuous monitoring (Monitoring Criterion No. 3).

To insure continuous and uniform operation and sensitivity of the instrumentation the criteria require periodic source response checks, counting efficiency checks and calibrations

(Monitoring Criterion No. 11); however, only the source response checks are currently performed on a routine basis (semi-annually when the plant is on standby and more frequently when the plant is operating).

This concludes the preliminary evaluation of the 291-A-1 stack sampling systems. The evaluation is summarized later in the report and followed by recommendations for corrective action.

III. 296-A-1 STACK EFFLUENT SAMPLING SYSTEMS

Description of 296-A-1 Sampling Systems

The 296-A-1 stack exhausts filtered ventilation air from the Plutonium Recovery Room (PR Room), N-cell and Q-cell.^[13] The stack flowrate (measured September 10, 1975) is 4900 CFM. The effluent is normally exhausted from one side of a two-unit filter box by a single fan and then passes through a transition and up the stack (see Figure 7). The fan is equipped with an emergency electrical power supply; a spare exhaust fan (drawing from the other side of the two-unit filter box) is also available. The ventilation can also be shunted to the West Sample Gallery Hood Exhaust Fan and 296-A-2 stack when filters are being changed in the filter box or when both fans are inoperable.

The effluent is sampled twice, once for a monitor sample (EDP Code 540) and once for an inventory sample (EDP Code 541). The monitor sample is extracted from the stack while the inventory sample is extracted from the duct leading from the filter box to the main fan (see Figure 7). Particulate samples are collected on 47-mm diameter HV-70 filters and are usually changed on Tuesdays. The sample filters are changed more often if an abnormal release is observed. Both samples are sent to the 222-S air sample counting room for analysis and the inventory sample serves as the record sample. The following discussions present further details concerning the two sampling systems.

296-A-1 Inventory Sample

The 296-A-1 stack inventory sampling system, shown in Figure 8, consists of a probe located in the 19-1/2-in. ID duct between the filter box and main fan. An in-line filter

FIGURE 7
 296-A-1 Stack Sampling Systems

FIGURE 8
 296-A-1 Stack Inventory Sampling System

holder is short coupled to the probe. There are no blueprints showing the actual configuration and dimensions of the probe inside the duct. Just outside of the duct the tubing measures 3/8-in. OD; therefore, for the rest of the report it will be assumed that the probe is made from 3/8-in., 18 gauge tubing which has a 0.277-in. ID. Following the filter holder is a rotameter which reads 2 SCFM.

The vacuum for the system is supplied by the 202-A building air sample vacuum system. The air sample vacuum system is powered by a single vacuum pump with another pump on standby. The pump supplies a vacuum pressure of 15-in. of mercury. There is a pump failure alarm in the dispatcher's office and emergency electrical power is available to the pumps.

The sample delivery tubing is traced with heating tape from the duct to the filter holder. Although the heating tape is currently disconnected, no condensation has been observed on the sample filters.

296-A-1 Monitoring Sample

The 296-A-1 stack radioactive particulate monitoring system is shown in Figure 9. The sampling probe is located on the stack centerline 32-ft below the top of the 24-in. diameter stack. The sample airstream passes through approximately 30-ft of 1/2-in., 18 gauge tubing and 6-90° bends to a Hanford design collector/detector^[16] located in the P.R.V. Room adjacent to the stack. The filtered sample airstream then passes through a rotameter (which reads 2 SCFM) and is exhausted to the 202-A building air sample vacuum system described above. The air sample piping is electrically heat traced from the stack to the P.R.V. Room and is thermostatically controlled; however, the control point temperature is unknown.

MONITOR SAMPLE PIPING SUMMARY

TWO	45° BENDS	0.37 in. ID TUBING
SIX	90° BENDS	0.37 in. ID TUBING
43 in.	HORIZONTAL	0.37 in. ID TUBING
318 in.	VERTICAL	0.37 in. ID TUBING

FIGURE 9

296-A-1 Stack Monitor Sampling System

A block diagram of the monitoring instrumentation is shown in Figure 10. Inside the collector/detector is a photomultiplier tube with an alpha scintillator fixed to the end of the photomultiplier tube and positioned a short distance from the collection face of the filter paper. The signal from the photomultiplier tube is preamplified, amplified and passed to a single channel analyzer with a window of 3.5 to 10 MeV. The single channel analyzer output goes to a count rate meter which has full scale ranges from 10^2 to 10^6 counts per minute and is normally set on the 0-1000 cpm scale. The count rate meter output goes to a moving strip chart recorder on which an alarm is set to actuate at 75% of full scale. The recorder full scale corresponds with the full scale setting of the count rate meter; thus, the alarm normally actuates at 750 cpm. The alarm is a light located in the 202-A building dispatcher's office. The counting efficiency of the monitoring detector has not been determined but should be about 10%. The instrumentation has a semi-annual source check while the plant is on standby. The source check is performed more frequently when the plant is operating. [19]

Preliminary Evaluation of Sampling Systems

This preliminary evaluation of the effluent sampling and monitoring systems at the 296-A-1 stack will proceed in the same manner as the evaluation of the Purex main stack samples. The effects of the system operation, sample size, sampling location, sample extraction, delivery and collection upon the representativeness of the collected particulate samples will be addressed first. Then the compliance of the monitoring instrumentation with the Interim Criteria will be discussed.

FIGURE 10

296-A-1 Stack Monitor Instrument Block Diagram

Sampling System Operation

Inventory and Monitor Samples. As has been explained earlier it is required that separate monitor and inventory particulate samples of the effluent be collected. The use of the existing inventory and monitor samples satisfy this requirement during normal operation of the exhaust fan. However, in the event the main exhaust fan is disabled and the standby exhaust fan is in use there is no inventory sample obtained from the effluent (see Figure 8). The reasons are that the only inventory sample is withdrawn from the duct between the filter box and main exhaust fan. A better location for the inventory sample extraction would be above the "wye" at the stack base so an inventory sample is obtained regardless of which exhaust fan is in use.

Condensation in Sample Delivery Piping. Moisture condensation on filters from both sampling systems has not been observed; thus, satisfying the Sampling Criteria. Even though the heat tracing on the inventory sample is not used it is in place in case condensation does occur.

Measurement of Stack and Sample Flowrates. As pointed out earlier the accurate measurement of both stack and sample flowrates is necessary for calculations of radioactive particulate release levels and for obtaining isokinetic sampling. The present procedure for occasional stack airflow measurements by the Vent and Balance subsection is probably adequate as long as the stack flowrate does not vary greatly. However, the routine measurement technique for sample airflows is inadequate.

Both rotameters are factory calibrated to read in units of SCFM as long as they are used at standard conditions. However, both rotameters are located on the vacuum side of the collection filters and are not properly instrumented to allow correction of the readings for the actual conditions of temperature and pressure. (The error in using an uncorrected airflow reading can easily be as much as 25% with the rotameter under a vacuum pressure of about 15-in. of mercury.) However, since the corrected sample flowrates are unknown, the assumed flowrates of 2 SCFM will be used later in this report.

Continuous Sampling. The 296-A-1 stack sampling systems meet the requirement of having as many back-up power supplies as the stack exhaust fans.

Sample Aliquot Selection

In discussing the choice of sample aliquot the topics of inventory and monitor sample extraction location and inventory sample size will be addressed. The topic of monitor sample size will be considered later under the heading of "Monitor Sensitivity and Range".

Sampling Location. Neither of the probes for the inventory or monitor samplers are positioned in the duct or stack at locations from which representative samples are likely to be obtained. The monitor sample probe is located only five duct diameters from a major bend in the stack, and the inventory sample probe is located even closer to a 90° bend in the duct. The flow velocity profiles are usually highly irregular at such locations, and it does not seem likely that a representative particulate sample can be collected by a single nozzle probe located on the duct and stack centerlines without some experimentation to prove otherwise.

Inventory Sample Aliquot Size. The size of the inventory sample aliquot (or volume of sampled air) has a major effect on the amount of radioactive particles collected on the sample filter, which in turn affects the accuracy of the subsequent sample analysis. The factors which set a minimum sample aliquot are stated or implied by Sampling Criterion No. 1. (The reader is referred to Pages 17 to 20 for a more detailed development of this subject.)

The Sampling Criterion requires that an average ^{239}Pu concentration of $6 \times 10^{-14} \mu\text{Ci/cc}$ must be measureable with "appropriate accuracy" using a sample collected for 24-hr and analyzed with the current technique.^[8,9] Minimum sample flowrates were calculated with the assumptions that the analysis be accurate at the 95% confidence level to $\pm 10\%$, and that the collected samples are ideally representative. It was shown that with the present laboratory procedure a sample flowrate of 338 SCFM is required to measure a $6 \times 10^{-14} \mu\text{Ci/cc}$ ^{239}Pu concentration with a 24-hr sample. This unreasonably high flowrate can be reduced considerably to 7.1 SCFM if the sample counting time is increased to one hour. Of course, if the counting time is increased or the criteria altered to permit a longer collection interval, the sample flowrate can be reduced even more.

With the present assumed flowrate of 2 SCFM and the present analytical procedure employing a one minute count, an average release of $1.0 \times 10^{-11} \mu\text{Ci/cc}$ of ^{239}Pu can be measured at the assumed accuracy. Because of the combination of current sample flowrate and analytical procedure the Interim Criteria, as interpreted, are not satisfied.

Performance of Sampling Systems

Extraction. The bias of particulate concentration in the sample airstream, relative to a representative sample, caused by nonisokinetic sampling can be estimated by calculations^[11]. Because of the uncertainty about the actual inventory probe design, the airflow velocities at the inlet nozzle locations and the sample flowrates, such calculations will only be approximate. The assumptions used here concerning probe design and flowrates have already been mentioned (pages 34 and 38). The following table shows the approximate particulate concentration bias for several particle sizes caused by extraction effects for both sampling systems.

TABLE 5
Particulate Extraction Bias of 296-A-1
Stack Effluent Sampling Probes

<u>Particle Size</u> <u>μm, AED</u>	<u>Monitor Sample</u> <u>Probe</u>	<u>Inventory Sampler</u> <u>Probe</u>
0.5	1.00	1.00
1	1.00	.99
2	.98	.96
5	.91	.83
8	.83	.71
10	.79	.66

For both samplers, the extraction velocity is higher than the stack or duct average air velocities. Thus, as shown in the table the concentrations of the larger particle sizes are less in the sample airstream than in the airstream approaching the nozzles. This is particularly significant for particles larger than 5 μm, AED.

Delivery and Collection. The concentration of various sizes of particulates is further modified by delivery to the collection filter and the efficiency of the collection filter. However, as mentioned earlier, the collection efficiency of the HV-70 collection filter has been assumed to be 100% (see page 23) and, therefore, has small effect on the sample representativeness when compared to the extraction bias and particle deposition.

The effect of particulate losses caused by sample transport from the inlet nozzle to the filter can be estimated as outlined in an earlier report.^[11] Table 6 shows the estimated fractional delivery of various sizes of monodispersed aerosols to the collection filter. Particle losses in pipe joints and the collector/detector cavities are not accounted for here.

TABLE 6

Percent Delivery of Monodispersed Aerosols
Through Sampler Piping, 296-A-1 Stack

<u>Particle Size</u> <u>μm, AED</u>	<u>Monitor</u> <u>Sample</u>	<u>Inventory</u> <u>Sample</u>
0.5	98%	99%
1	91	98
2	69	92
5	9	59
8	<1	26
10	<<1	12

The low fractional delivery of the monitor sample to the collector is due mainly to the several bends and the distance from the probe to the collector. The inventory sample fractional delivery is low, mainly because the tubing is too small for the flowrate.

The combined effect of extraction and deposition caused biases upon the representativeness of the sample reaching the collector can be estimated by simply multiplying the two effects, the product of which is shown in Table 7.

TABLE 7

Combined Estimate of Percent Penetration
of Monodispersed Aerosols to the Collector, 296-A-1 Stack

<u>Particle Size</u> <u>μm, AED</u>	<u>Monitor</u> <u>Sample</u>	<u>Inventory</u> <u>Sample</u>
0.5	98%	99%
1	91	97
2	68	88
5	8	49
8	<<1	18
10	<<1	8

The table shows that a low percentage of particles larger than 5 μm AED that approach the probe nozzle will reach the collection surface. Of course these estimates are subject to the limitations of the many assumptions made regarding flowrate, pipe size (in case of the inventory sample) and the calculational models themselves. However, these estimates indicate that the two sampling systems do not conform to the requirements of the criteria concerning representative particulate sampling.

Monitoring Instrumentation

Sensitivity and Range. The monitor instrumentation is set to detect alpha radiation in the range of 3.5 to 10 MeV. Because the levels of ^{239}Pu which must be detected with the monitor are defined, the instrumentation will be evaluated for sensitivity and range in terms of that isotope.

As mentioned before (page 26), the monitoring instrumentation must have enough sensitivity and range to detect above background and monitor 24-hr average release levels* equivalent to $1/2 \times$ Class I and $100 \times$ Class II action levels. To eliminate some of the variables affecting monitor performance the following assumptions are made: 1) stack flowrate of 4900 SCFM, 2) sample flowrate of 2 SCFM, 3) a counting efficiency of 10%, and 4) an ideally collected sample. With these assumptions the detected counting rates for the two release levels can be calculated.

Both Class I and Class II action levels are concerned with releases showing a single day's trend toward a weekly release of 10^{-5} Ci of ^{239}Pu (see Appendix C). Such a weekly release is equal to a concentration of

$$\begin{aligned} \text{concentration} &= \frac{10^{-5} \text{ Ci}}{\text{wk}} \times \frac{\text{min}}{4900 \text{ ft}^3} \times \frac{\text{ft}^3}{28,320 \text{ cc}} \times \frac{\text{wk}}{10,080 \text{ min}} \\ &\quad \times \frac{10^6 \mu\text{Ci}}{\text{Ci}} \\ &= \frac{7.1 (10^{-12}) \mu\text{Ci}}{\text{cc}} \end{aligned} \quad (5)$$

*A 24-hr averaging period is used because the Class I and Class II action levels are defined around 24-hr intervals.

The detected count rate for the 1/2 x Class I Action Level is then:

$$\begin{aligned}
 \text{detected count rate} &= \frac{1}{2} \times \frac{7.1 (10^{-12}) \mu\text{Ci}}{\text{cc}} \times \frac{2 \text{ ft}^3}{\text{min}} \\
 &\quad \text{(1/2 x Class I action level)} \\
 &\quad \times \frac{28,320 \text{ cc}}{\text{ft}^3} \times \frac{2.22 (10^6) \text{ d}}{\mu\text{Ci} \cdot \text{min}} \\
 &\quad \times 1440 \text{ min} \times 0.1 \frac{\text{c}}{\text{d}} \\
 &= 64 \frac{\text{c}}{\text{min}} \tag{6}
 \end{aligned}$$

The background count rate was recently observed to be in the range of 10-30 c/min. Thus, the monitoring instrumentation is sensitive enough to detect a 1/2 x Class I Action Level release above background if the assumptions made are valid.

The detected count rate for the 100 x Class II Action Level is then:

$$\begin{aligned}
 \text{Detected count rate} &= 100 \times \frac{7.1 (10^{-12}) \mu\text{Ci}}{\text{cc}} \times \frac{2 \text{ ft}^3}{\text{min}} \\
 &\quad \times \frac{28,320 \text{ cc}}{\text{ft}^3} \times \frac{2.22 (10^6) \text{ d}}{\mu\text{Ci} \cdot \text{min}} \\
 &\quad \times 1440 \text{ min} \times 0.1 \frac{\text{c}}{\text{d}} \\
 &= 13,000 \text{ c/min} \tag{7}
 \end{aligned}$$

This counting rate is well below the maximum of 10^6 c/min for the instrumentation. Thus the range of the monitoring instrumentation is sufficient if the assumptions made are valid.

Alarms. There are several types of alarms the monitoring system is required to include. First, the system is required to alarm when a Class II action level average concentration has been reached during a 24-hr period. By calculations similar to those above and with the same assumptions about flowrates, sample representativeness and counting efficiency, the alarm should be activated when 130 c/min are measured at the end of the day. The present alarm level of 750 c/min is considerably higher.

The other required alarms are for loss of vacuum and instrument malfunction. The instrument malfunction alarm is absent from this monitoring system but there is a loss of vacuum alarm at the source of vacuum supply. It would be worth checking to see if the loss of vacuum alarm actuates when there is a leak at the collector/detector which might possibly be caused by improperly retightening the filter holder or improperly made up fittings.

The existing alarms are actuated in the 202-A building dispatcher's office. Neither of the alarms are audible, but both are panel lights. Also, the dispatcher's office is not continuously occupied.

Maintenance and Continuous Monitoring. The monitoring system is supplied with a sufficient number of back-up power systems to conform with the requirement of Monitoring Criterion No. 4. These back-up systems insure continuous monitoring as long as the stack exhaust fans operate.

It is also required (Monitoring Criterion No. 11) that the detection instrumentation be calibrated and checked for counting efficiency and response on a quarterly basis. The present instrumentation was last calibrated in November, 1973 (according to a sticker on the instrumentation). A source check is

conducted semiannually when the plant is on standby and more frequent when the plant is operating. The detector counting efficiency is not known. Therefore, the present maintenance program is only partly in compliance with the criterion.

This concludes the evaluation of the 296-A-1 stack sampling system. Later in this report the evaluation is summarized and recommendations for corrective action are outlined.

IV. 296-A-2 STACK EFFLUENT SAMPLING SYSTEM

Description of 296-A-2 Sampling Systems

The 296-A-2 stack exhausts the filtered hood exhaust from the 202-A building West Sample Gallery; and also, under certain conditions mentioned earlier (page 31), the PR Room, and N and Q cells. The air flowrate was recently determined (September, 1975) to be 2800 CFM. The one particulate sample (EDP 542) of the effluent is withdrawn from the elbow of an 18-in. diameter duct between the filter box and fan as shown in Figures 11 and 12. There is no blueprint showing the sampling probe details; however, it is assumed that the probe is a curved tube pointing into the airstream. Outside the duct the tube has a 9/16-in. OD; therefore, for this report it will be assumed that the probe and delivery tube is made from 1/4-in. schedule 40 pipe with a 0.364-in. ID.^[20] Short coupled to the probe mounting flange is an in-line filter holder. A 47-mm diameter HV-70 filter is used to collect the particulate sample and is changed every Tuesday and sent to the 222-S building for analysis.

After the particles are collected, the sample airstream passes through a rotameter. The rotameter currently reads off-scale (greater than 6 SCFM), but the sample flowrate is assumed to be 2 SCFM for release calculations. The vacuum for the sampler is provided by the 202-A building air sample vacuum supply already described (page 34).

The short sample delivery piping is traced with heating, tape which is currently disconnected. Condensation on the sample collection filter has not been observed.^[22] Apparently, the effluent temperature is sufficient to prevent condensation.

FIGURE 11
 296-A-2, West Sample Gallery Hood Exhaust, Stack

FIGURE 12
296-A-2 Stack Particulate Inventory Sampling System

There are blueprints^[23] which show that design-work was completed in 1971 for a monitored sampling system in the 296-A-2 stack. The system was never built; however, the designed system would probably have been poorer than the current system in terms of sampling performance.

Preliminary Evaluation of Sampling System

This preliminary evaluation of the particulate effluent sampling system at the 296-A-2 stack will address the effects of system operation; size of the sample; sampling location; and sample extraction, delivery and collection upon the representativeness of the collected particulate samples.

Sampling System Operation

Inventory and Monitor Sampling. It has apparently been decided that constant monitoring of the West Sample Gallery Hood Exhaust is not necessary at this time. It would, however, be worthwhile to reevaluate the need for constant monitoring when the Purex operation is reactivated.

Condensation in Sample Delivery Piping. Although there is some provision for heat tracing in severe weather to prevent the condensation of water in the sampler piping, condensation has not been observed to be a problem.

Measurement of Stack and Sample Flowrate. The knowledge of stack and sample flowrates is necessary for the calculation of radioactive particulate release levels and the design and operation of the sampling system. The present procedure for measuring the stack airflow is satisfactory since the airflow is not expected to vary; however, the measurement of sample flowrate is totally inadequate.

The present rotameter, mounted in the sample vacuum line, is not operated at its calibrated conditions nor instrumented to allow correction of the flow reading. Also, the considerable corrosion of the rotameter float and float guide-rod causes rough and sticky movement of the float. It is expected that the flowrate measurement error is quite significant. Although the current flowmeter reading is off-scale (greater than 6 SCFM) a flowrate of 2 SCFM will be assumed for the calculations of sampling performance in this report. (This is the design flowrate and it is doubtful that the vacuum system will handle a flowrate that is much larger.)

Continuous Sampling. Both the 296-A-2 stack exhaust fan and the sample vacuum systems have the same number of emergency electrical power systems, thus satisfying the requirement of Criterion No. 7. However, there is only a visual alarm in the dispatcher's office that signals a loss of vacuum at the vacuum pumps. It should be determined if a vacuum leakage at the samples also actuates the alarm. There is no audible alarm and the dispatchers office is not continuously occupied.

Sample Aliquot Selection

Sampling Location. The present location for sampling the 296-A-2 stack effluent is a poor choice for extracting a representative sample. As can be seen in Figure 12 the probe is located in a 90° bend of the duct. It is likely that the particulate flow through the bend will be concentrated around the outside radius of the bend and the particulate concentration at the duct centerline is not likely to be representative of the effluent.

The only alternative locations for a sampling probe are on the stack. One possibility is to locate the sampling probe and collector in the stack at the roofline of the 202-A building. Thus, samples could be changed and equipment serviced from the roof (the location is not above a cell where "shine" through the roof is a hazard when the cell covers are removed). Another possibility is to run a properly sized pipe from a probe in the stack, through the 202-A building wall, and to the stairwall which is opposite the stack.^[23] Samples could then be changed and other servicing performed from the stairwell.

Inventory Sample Aliquot Size. The size of the inventory sample aliquot (or sample volume) has a major effect upon the effluent radioactive particulate concentration that is measurable with a given accuracy. The Sampling Criterion No. 1 requires that a ²³⁹Pu particulate concentration of 6×10^{-14} $\mu\text{Ci/cc}$ must be measureable with appropriate accuracy, using the current analytical technique and using a 24-hr sample. With the assumptions of an ideally collected sample and a desired counting accuracy of $\pm 10\%$, 95% confidence level, the minimum sample size necessary can be calculated. (The reader is referred to the more detailed development on pages 17-21.) It has been shown that even with a sample counting time of one hour, that a flowrate of 7.1 SCFM is required to collect in 24-hrs a sufficient amount of ²³⁹Pu bearing particles for the analysis of the required concentration. Thus, the present design flowrate of 2 SCFM is inadequate to permit the measurement of the required concentration in the required time with the assumptions made about accuracy.

Performance of Sampling System

Extraction. Assuming a sample flowrate of 2 SCFM, a stack flowrate of 2800 SCFM, a probe nozzle opening 0.364-in. ID, and a uniform velocity distribution with average velocity at the probe nozzle (an unlikely situation considering the location), the bias in the sample caused by nonisokinetic extraction of the sample can be estimated. (The model for sampling bias has been described in another report.^[11]) In this case, the sampling system operates at a velocity higher than required for isokinetic conditions. The resulting estimated biases are shown in Table 8 for particulates of various sizes.

TABLE 8
Particulate Extraction Bias of
296-A-2 Stack Effluent Sampling Probe

<u>Particle Size</u> <u>μm, AED</u>	<u>Bias</u>
0.5	1.00
1	1.00
2	.98
5	.91
8	.83
10	.79

The table shows that the concentration of particulates larger than 2 μm AED in the sample airstream is lower than in the effluent approaching the nozzle. Because the effluent velocity at the probe is probably lower than average, the biases will be more pronounced than as calculated.

Delivery and Collection. The concentrations of the various sized particulates will be further modified by deposition in the curved sampling probe. An estimate of the fractional delivery of particulates through the sampling probe is shown in Table 9.

TABLE 9

Percent Monodisperse Aerosol Delivery Through
Sampling Probe, 296-A-2 Stack

<u>Particle Size μm, AED</u>	<u>Percent Fractional Delivery Through Probe</u>	<u>Combined Percent Delivery Through Probe</u>
0.5	100	100
1	99	99
2	96	94
5	76	69
8	50	42
10	33	26

The table shows that even with a sample delivery system as simple and short as this one there is a suprisingly small fractional delivery of the larger particles. This is because the ID of the piping is too small for the flowrate and the piping is horizontal rather than vertical. Also shown in the table is the combined percent delivery through the probe accounting both for particle deposition and extraction bias.

The collection efficiency of the filter can also modify the collected sample. However, the collection efficiency of the HV-70 filter paper is assumed to be essentially 100% for this report (see page 23) and has no significant effect upon the representativeness of the collected sample.

The values for extraction bias and fractional delivery of particulates through the sampling system admittedly are not exact because of the many assumptions made in their calculation. However, they do indicate that the existing sampling system does not collect samples which are as representative of the particulate effluent as required in Sampling Criteria No. 2 and 4.

This concludes the evaluation of the 296-A-2 stack effluent sampling system. The evaluations of this system plus the 291-A-1 and 296-A-1 sampling systems are summarized in the next part of the report. Preliminary recommendations for corrective action are given in Part VI.

V. SUMMARY OF PRELIMINARY EVALUATIONS

In this part the preceding preliminary evaluations of effluent sampling and monitoring systems at the three Purex Plant stacks are summarized. Those areas of the systems found to be in compliance with the Interim Criteria are listed first followed by a listing of areas not in compliance. In each of the lists the comments applicable to all of the sampling and monitoring systems will be grouped under the heading "General". The comments applicable to one or more systems in particular will be grouped under other headings as appropriate.

Areas In Compliance

General

1. Moisture condensation in the sample delivery lines and on collection filters is not a serious problem. All the sampling systems have heat tracing either available or in constant use in case condensation becomes a problem in severe weather. However, only the 296-A-1 stack monitor sample delivery line has thermostatically controlled heating to maintain a constant temperature in cold weather and to conserve energy in warm weather.
2. The number of back-up power supplies for vacuum systems and monitoring instrumentation is equal to the number of back-up power systems for the exhaust fans at each stack.

Monitoring Systems, 296-A-1, 291-A-1 Stacks

3. At the two stacks where there are radioactive particulate effluent monitors, the monitor sample is obtained separately from the inventory samples.

Monitoring System, 296-A-1

4. The monitoring instrumentation at the 296-A-1 stack is equipped with a functioning recorder to document the counting rate detected by the monitor.
5. The monitoring instrumentation for the 296-A-1 stack seems to have sufficient sensitivity and range for alpha-emitters; however, this conclusion depends on the assumptions that were necessary for the evaluation (see No. 7 under Areas Not in Compliance).

291-A-1 Stack Probes

6. The stack sample extraction probes are designed to extract equal portions of the total sample from each of five equal annular areas of the stack. The number of sampled areas is not exactly as many as specified in the ANSI Standard N13.1, but should be sufficient.

Areas Not In Compliance

General

1. None of the six collected samples are likely to be representative of radioactive particulates in the effluents, especially for particulates larger than 2 μ m AED. The reasons for this major deficiency are as follows:

- a. Sample extraction locations are not chosen at recommended locations in the stacks. In all cases the extraction locations are too near to major airflow disturbances. This problem is most severe for the 296-A-1 and 296-A-2 stacks.
  - b. In all cases there is significant sample bias caused by improper extraction of sample air-streams (or nonisokinetic sampling). The bias caused in samples collected from the 291-A-1 stack will be slightly less pronounced when the plant is operating and the ventilation exhaust airflow is at its designed maximum.
  - c. The evaluations indicate that there are significant losses of sampled particulates in sample delivery lines. This is the case even for such short sampling systems as the inventory samples of the 296-A-1 and 296-A-2 stacks (see page 56 for an explanation).
2. The inventory sample flow rates are too low and the sample counting times are too short to allow measurement of the ERDA Manual Chapter 0524, Appendix, Annex A concentration of ^{239}Pu using a 24-hr sample and with a counting accuracy as assumed (page 28).
  3. Sample flowrate measurement is completely inadequate in all cases. The rotameters are used under conditions for which they are not calibrated and there are no provisions made for correcting readings or recalibration. There are no posted calibrations for the orifice meters for measuring primary sample flowrates in the 291-A-1 stack sampling systems. The flow measurements by pressure difference across the sample filter holder, used for the 291-A-1 stack back-up inventory

sample, is unacceptable because of variations in filter characteristics and inferior mounting of the filter. The flowmeters at the 296-A-2 stack sampler and 291-A-1 50-ft level primary sample airstream are essentially inoperable.

4. There are no set standard conditions used for sample and stack flowrate measurements. This allows significant errors and inconsistencies in release concentration calculations.
5. None of the existing sampling and monitoring system alarms are audible or are located in a continuously occupied area.
6. There is considerable suspicion of variability in the characteristics of the HV-70 collection filters. There are; however, no assembled findings concerning collection efficiency, self absorption characteristics and quality control for the filter medium. There is also no stated rationale for the 70% correction factor for filter efficiency that is used in the release calculations (see page 18). All these uncertainties make it difficult to assess the effect of the filter upon the representativeness of the collected samples.

Monitoring Systems - 291-A-1 and 296-A-1 Stacks

7. The questions of monitor sensitivity and range are only approximately assessed in the evaluations because of the uncertainties of counting efficiencies and background levels. There are no regular determinations or checks of monitor calibration and counting efficiency. The source response checks are not currently frequent enough (they are currently semiannual rather than quarterly).

8. High level release alarms are set at counting rates that are too high to indicate a Class I action level ²³⁹Pu concentration.
9. There are no instrument malfunction alarms.
10. The stack airflow monitoring is inadequate at the two stacks. There are operating conditions where the exhaust flowrates can change. At the 291-A-1 stack the existing monitor does not correspond well with ARHCO Vent and Balance airflow measurements. At the 296-A-1 stack there is no exhaust flow monitor; although, the exhaust airflow is likely to change when the standby fan is used.

296-A-1 and 296-A-2 Stacks

11. The configurations of the inventory sample probes at these two stacks are unknown; thus, requiring additional assumptions in the evaluation of the inventory sampling systems.

291-A-1 Stack

12. The modified in-line filter holder for the back-up inventory sample does not have an acceptable seal around the mounted filter.
13. There is no loss of vacuum alarm for any of the sampling systems at this stack.
14. The evaluation of the monitor indicates that the sample collection time and flowrate are insufficient for the required monitor sensitivity (this conclusion is subject to the limitations of the assumptions made, see Item No. 7 under "Areas Not in Compliance"). Also, the monitoring is not continuous.

15. Although there is a strip chart recorder for the effluent monitor detector count rate, the chart drive is not functioning.

296-A-1 Stack

16. In the event the standby exhaust fan is used, there is no inventory sample of the effluent.

VI. RECOMMENDATIONS FOR CORRECTIVE ACTION

In this section recommendations are given for correcting the deficient areas of the particulate effluent sampling programs at the three stacks. Those recommendations applicable to all three sampling systems are given under the "General Recommendations" heading. Additional recommendations for particular sampling systems are given under other appropriate headings.

General Recommendations

1. A decision should be made regarding the required accuracy of the measurement of ERDA Manual Chapter 0524 Table II concentration levels. It would also be worthwhile to review the need for measuring those concentration levels with a 24-hr sample. It has been assumed in this report that a 24-hr sample is used and the required analytical accuracy is $\pm 10\%$ at the 95% confidence level. Calculations using these assumptions show that flowrates and counting times must be increased considerably for all inventory samples. Thus, once the above decision is made, the changes in sampling rate and counting time should be reevaluated commensurate with that decision.
2. A decision must be reached regarding the choice of conditions of air temperature and pressure to be used in calculating release concentrations and in measuring stack and sample airflows. Flowrates and air volumes should then be reported in terms of those conditions. One of the commonly accepted definitions of "standard conditions" would be a convenient choice; for example, 70°F and 29.92-in. of mercury.

3. The measurement of sample flowrates must be upgraded. Either mass flow instruments, flow controllers or other properly instrumented flowmeters should be used to allow flow measurements corrected for the standard conditions chosen above.
4. The collected samples must be more representative of the radioactive particulate effluents. The Interim Criteria and the ANSI Standard N13.1 should be followed in the design of improved sample collection systems. The following items should be incorporated into the redesigned systems:
  - a. Sample extraction probes (particularly at the 296-A-1 and 296-A-2 stacks) should be moved to where there are no major airflow disturbances for at least ten stack-diameters upstream and five stack-diameters downstream of the probes. Sample probes should extract the sample from as many locations in the stack as required by the ANSI Standard N13.1. If other locations are used they should be experimentally proven to allow the extraction of representative samples.
  - b. The extraction caused biases should be eliminated by using properly designed probe nozzles and by maintaining isokinetic sampling. Procedures should be developed for changing sampling flowrates to maintain isokinetic conditions even when the effluent flowrates change significantly (a change greater than 20%).
  - c. Where possible use in-stack filter holders for inventory samples. Filter holders short coupled to the probe may also be acceptable if the probe is designed to pass a representative sample.

- d. For monitor samples the collector/detector should be short coupled to the probe.
  - e. Choose pipe sizes and flowrates to decrease the loss of particulates in sampling system piping between the probe and the collector. Guides are available to aid in the necessary calculations.^[6,11]
  - f. Reduce the distances from probe inlets to collectors.
  - g. Eliminate as many airflow disturbances (such as bends, fittings, valves and rotameters) between the probe and collectors as possible.
  - h. Allow for occasional cleaning of sample delivery lines and accounting for deposited radioactive particulates.
  - i. When a suitable technique becomes available, conduct experiments to validate or pretest sample collection equipment for adequate aerosol penetration.
5. All the alarms should be audible as well as visual and they should also be located in a continuously occupied area.
6. The rationale behind the use of the 70% value for the HV-70 filter efficiency needs to be brought to light. Previous studies of the collection efficiency, self absorption and quality control of the HV-70 filter should be gathered and documented. Then the use of the 70% value and the filter should be reviewed. It may be advantageous to select some type of reinforced membrane filter which has improved and more consistent characteristics.

Monitoring Systems - 291-A-1 and 296-A-1 Stacks

7. The counting efficiency and background levels of the monitoring devices should be determined. Once these values are determined the sensitivity above background and range of the instruments should then be reevaluated. The background may need to be reduced or discriminated and the sample flowrate and collection periods increased.
8. After the above evaluation, the high level release alarms should be reset to conform with the Monitoring Criteria.
9. Instrument malfunction alarms need to be incorporated into the systems. These may simply consist of a low level or zero scale alarm.
10. Implement a program to check radioactive particulate monitor calibration, source response, counting efficiency and alarms on a quarterly basis.
11. The stack flow monitoring must be upgraded. At the 291-A-1 stack the monitor must be recalibrated. A stack flow monitor should be installed at the 296-A-1 stack to show any changes in flowrate when the standby fan is in use.

291-A-1 Stack

12. Incorporate loss of vacuum alarms into the improved sampling systems.
13. Have the strip chart recorder checked and made operable.
14. Even though the evaluation of the monitoring instrumentation was based on several assumptions, it seems likely that whatever the actual counting

efficiency is, the monitor cannot have the required sensitivity with a thirty minute collection period. To lengthen the collection period and to provide continuous monitoring it seems best to replace the moving tape monitor with a stationary filter collector/detector. The replacement monitor should be proven to allow better than 90% penetration of 10 μ m AED particles to the filter.

296-A-1 and 296-A-2 Stacks

15. As mentioned in recommendation No. 4a new sample extraction locations must be obtained. For these two stacks there is the possibility of taking advantage of the stacks' location relative to the 202-A building. In both instances it seems feasible to locate the sampling stations at the building roofline, allowing the sampling systems to be quite compact. Sample filters and equipment could then be conveniently serviced from the roof. An alternative with similar advantages is to have short sample delivery lines run through the building wall to the crane cab gallery (296-A-1 stack) or to a stairwell (296-A-2 stack).^[23] For either alternative, several safety matters will need to be considered.

VII. CONCLUSION

In the evaluations of radioactive particulate sampling and monitoring systems at the three stacks in question it has been found that the systems do not comply with many of the Interim Criteria or good sampling practices. Many of the major deficiencies are the same as those found at other facilities and include:

1. probable considerable loss of sample particulates before collection,
2. sample air volumes too small and sample counting time too short to allow accurate measurements of certain specified radioactive particulate concentrations,
3. inadequate methods for measuring sample flowrates,
4. sample extraction locations where it is difficult to extract representative samples, and
5. the great difficulty in obtaining reliable information about sampling systems.

Other significant deficiencies are listed in the evaluation summary. Also outlined in the report are several recommendations for corrective action. Incorporating these recommendations into improved sample collection and monitoring systems will result in systems which better comply with the Interim Criteria and good sampling practices.

NOMENCLATURE

AED	Aerodynamic Equivalent Diameter
c	counts
cc	cubic centimeter
CFM	cubic feet per minute
Ci	Curie
d	distintegration
ft	feet
ft ³	cubic feet
ID	inside diameter
in.	inch
MeV	mega (million) electron volts
mm	millimeter
min	minute
OD	outside diameter
sec	second
SCFM	standard cubic feet per minute (@ 70°F, atmospheric pressure)
wk	week
μCi	micro (10 ⁻⁶) curie
μm	micro (10 ⁻⁶) meter (micron)

REFERENCES

1. Drawings in possession of L. C. Schwendiman, Battelle-Northwest, Richland, WA.
2. Drawing BKC-4100-F-13, sheets 0, 8, 9, Blaw-Know Co., and Drawing C-6938-2, Rust Engineering Co., CVI File No. 8264, Atlantic Richfield Hanford Company, Richland, WA.
3. Drawing H-2-55028, Heat and Vent Plan and Sections Equipment and Piping - Stack Gas Sampling Facilities, Atlantic Richfield Hanford Company (ARHCO) Engineering Files.
4. Drawing H-2-24543, In-line Air Sampler Assembly and Details, ARHCO Engineering Files.
5. L. C. Schwendiman, J. A. Glissmeyer, Preliminary Evaluation of the Gaseous Effluent Sampling and Monitoring Systems at the 291-Z-1 and 296-Z-3 Stacks - Plutonium Finishing Facility, Letter report to D. J. Carrell, ARHCO, (April, 1976).
6. American National Standards - ANSI N13.1-1969, Guide to Sampling Airborne Radioactive Materials in Nuclear Facilities, American National Standards Institute, New York, NY, (1969).
7. ERDA Manual Chapter 0524. Appendix, Annex A (November, 1968).
8. Emergency and Holiday Coverage of 222-S Counting Room, Technical Services Section, Laboratory Operations Procedure No. ECOVCR-01A, ARHCO, (October, 1973).
9. An Outline of Environmental Air Sample Analysis, ARH-869 ARHCO, (October, 1968).
10. W. L. Nicholson, Battelle-Northwest, Richland, WA, private communication, April 1976.
11. L. C. Schwendiman, G. E. Stegen, J. Mishima, J. A. Glissmeyer, Interim Report: An Analysis of the Gaseous Effluent Sampling System - 225-B, Waste Encapsulation and Storage Facility, BNWL-B-408, Battelle-Northwest, Richland, WA (April, 1975).

12. Radiation Protection Standard, Disposal of Radioactive Materials, ARH-220, ARHCO, Richland, WA., November 1974.
13. Drawing H-2-59555, Ventilation Flow Diagram, "Q" Cell, ARHCO Engineering Files.
14. Drawing H-2-59561, Ventilation Exhaust Fan Arrangement, N, Q, and PR Cells, ARHCO Engineering Files.
15. Drawing H-2-66017, As-built PR Exhaust Fan Installation EF-2-5, ARHCO Engineering Files.
16. Drawing H-2-66039, Alpha Air Monitor Head Assembly, ARHCO Engineering Files.
17. Drawing H-2-64517, PR Stack Monitor Sampling Installation, ARHCO Engineering Files.
18. Drawing H-2-64516, PR Stack Monitoring Plan and Block Diagram, ARHCO Engineering Files.
19. B. G. Powauke, ARHCO, Richland, WA, private communication, May 24, 1976.
20. J. H. Perry, ed., Chemical Engineer's Handbook 4th ed., McGraw-Hill, New York, NY, p. 6-45, 1969.
21. Drawing H-2-52328, Heat and Vent. - Plan and Sections - Ductwork - Canyon Lobby, Storage Room and Outside at West End of Building, ARHCO Engineering Files.
22. J. G. Greer, ARHCO, Richland, WA, private communications April 1976.
23. Drawing H-2-66168, West Hood Exhaust Particulate Sample - Monitor, 2-sheets, ARHCO Engineering Files.

APPENDIX A

**Interim Radioactive Gaseous Effluent
Sampling and Monitoring Criteria
For Atlantic Richfield Hanford Company Facilities**

INTERIM RADIOACTIVE
GASEOUS EFFLUENT SAMPLING AND MONITORING CRITERIA
FOR ATLANTIC RICHFIELD HANFORD COMPANY FACILITIES

INTRODUCTION

To ensure that gaseous radioactive releases to the environment are kept as low as practicable, it is necessary to sample all of the radioactive or potentially radioactive gaseous effluent streams in the 200 Areas. Specific gaseous effluent streams that have the potential for release of large quantities of radioactive materials must also be monitored by radiation detection instrumentation.

The criteria listed below are intended to be used as guidelines to aid in the design of new systems or the upgrading of existing systems. It is highly desirable that new or upgraded systems be able to meet or nearly approach as many of the following criteria as is practicable.

SAMPLING CRITERIA

The term "sampling" applies to the extraction, transport and collection of a sample of the radionuclides present in the gaseous effluent stream on a collection media suitable for subsequent laboratory analysis. Gaseous effluent sampling systems shall:

1. extract in a 24-hour period a representative fraction of the effluent stream such that an activity release at least as low as the concentration guides given in ERDA Appendix 0524, Annex A, Table II can be measured with appropriate accuracy upon subsequent laboratory analysis.*
2. be designed, fabricated, and operated so that the particles extracted and transported to the collector will be representative to the degree that particles 10 micrometers and smaller in the sample collected will be at least 90 percent of the 10 micrometer and smaller particles in the same volume of a truly representative sample. At least 90 percent of the radioactive gases withdrawn shall be collected on the media selected or delivered to the activity sensing chamber in flow through monitors.
3. operate in a continuous mode, except for short periods when the sample collection media is being changed, whenever the facility is exhausting to the atmosphere.
4. extract samples of particles and gases that are a representative aliquot of the actual effluent stream.

* If one half of the Class I Action Level in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility) is less than the Table II concentration guides, use one half of the Class I Action Level from the appropriate Emergency Procedure as the basis for this criterion.

5. collect at least two samples, one of which will be designated and used exclusively as an inventory sample.
6. shall provide particulate and gaseous samples that have not been adversely affected by condensation of moisture.
7. be equipped with a vacuum system for sample extraction that has the same number of back-up power systems as the exhaust fans of the facility. The vacuum system shall be provided with an alarm that is activated upon the loss of vacuum.
8. provide an inventory sample which is an accurate aliquot, within a factor of two, of the absolute radioactive materials of the effluent stream. (Note: This statement relates only to the sample extraction and delivery capability, not to the accuracy of detection and measurement.)
9. provide inventory samples with less than 25 percent variation from the mean of several similar samplings at the 95 percent confidence level.
10. have at least an annual check to ensure that variation in effluent characteristics (particle size, mass activity concentrations, etc.) have not changed significantly.

MONITORING CRITERIA

The term "monitoring" applies to the use of radiation detection instrumentation to measure the amount of radioactivity collected by the collection media. Gaseous effluent monitoring systems shall:

1. monitor the samples collected (except for the designated inventory sample) as detailed in items 1-10 under Sampling Criteria. The monitoring system shall be able to detect an activity release at least as low as one half that required for the Class I Action Level listed in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
2. detect the radiation from radionuclides in the effluent stream with appropriate sensitivity for the radiation emitted.
3. operate in a continuous mode, except for short periods while samples are being changed, whenever the facility is exhausting to the atmosphere.
4. be equipped with the same number of back-up power systems as the exhaust fans of the facility.
5. incorporate a permanent recorder to document the level of radioactivity measured by the radiation detection instrument.

11/14/75
DJC:bac

6. be provided with a "fail-safe" system that alarms when a malfunction occurs in the radiation detection instrument or upon loss of vacuum.
7. alarm at a pre-set "trip" point that is consistent with a Class II Action Level as specified in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
8. be able to detect a Class II Action Level as specified in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility) in less than 24 hours.
9. alarm visually and audibly in a continuously occupied area for both the "fail-safe" alarm(s) and the emergency alarm(s).
10. be equipped with sufficient range to detect activity levels up to 100 times the Class II Action Level in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
11. have the radiation detection instrumentation calibrated on at least a quarterly basis.

APPENDIX B

ARHCO Emergency Procedure: ARH-222-2.1.7
Purex Plant - Loss of Electricity

EMERGENCY PROCEDURE

ISSUED BY THE MANAGER	SUBJECT	CLASSIFICATION	
Purex - UO ₃ Standby	PUREX PLANT - LOSS OF ELECTRICITY	ARH-222	
2.1.7 <u>LOSS OF ELECTRICITY</u> A. <u>Introduction</u> The Purex Plant is normally fed by a two-line 13.8 kv electrical distribution system from the 251 Building, substation A-8. If power fails on either of the two lines, the tie breakers in the east switchgear room automatically close, restoring normal power in a few seconds. A third emergency line from 252-E substation supplies Purex via the 282-E Powerhouse. If emergency power to the powerhouse fails, the emergency generator automatically starts, supplying emergency power to Purex within 15 to 20 seconds. P. <u>Immediate Action</u> The supervisor will contact the electrician and the power operator. Operations shall check status of process electrical equipment, and restart as necessary. C. <u>Loss of Power on Line C8L8</u> 1. Breaker E8X209 senses the loss of power and drops out. 2. Bus breaker E8X210 automatically closes in 2 seconds, tying bus #1 to bus #2. At this time, all "non-automatic starting" equipment, normally fed from bus #1, has to be manually restarted. 3. In the event the automatic feature of E8X210 fails, an electrician has to turn the keyed "normal-bypass" switch to bypass and manually close E8X210. 4. Contact electrical dispatcher, phone 2-2321. Ask permission to parallel Line 5 and Line 8. 5. With restoration of power to Line C8L8, an electrician makes certain the E8X210 keyed switch is in the bypass position, then closes breaker E8X209 momentarily, paralleling bus #1 and bus #2. The electrician then opens switch E8X210, restoring the keyed switch to the normal position.			
DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
11/4/74	2/15/70	1 OF 5	2.1.7

EMERGENCY PROCEDURE

D. Loss of Power on Line C8L5

1. Breaker E8X214 senses the loss of power and drops out.
2. Bus breaker E8X210 automatically closes in two seconds, tying bus #2 to bus #1. At the same time, bus breaker E8X225 opens and emergency breaker E8X223 closes, supplying emergency power to the emergency bus.

At this time, all "non-automatic starting" equipment has to be manually restarted.

3. In the event the automatic feature of E8X210 fails, the procedure is the same as paragraph 3 of procedure C (Line C8L8).
4. Contact electrical dispatcher, phone 2-2321. Ask permission to parallel Line 5 and Line 8.
5. Upon restoration of power on line C8L5, an electrician makes certain the E8X210 keyed bypass switch is in the bypass position, then closes breaker E8X214, momentarily paralleling bus #2 and bus #1. The electrician then opens E8X210 and restores the keyed switch to "normal" position.
6. The electrician will then notify the Operation shift supervisors and the shift power operator of a brief outage of equipment operating from the emergency bus. After receiving permission to return to normal, the electrician will set breaker, E8X223 control switch to the "manual" position, open E8X223, close E8X225, and return E8X223 control switch to the "automatic" position. This removes the emergency bus from the incoming emergency line and restores it to its normal position, i.e., being fed from normal bus #2.

E. Loss of Power on Lines C8L8, C8L5 and EL859

1. Breakers E8X209 and E8X124 sense the loss of power and drop out. Bus breaker E8X210 automatically closes after two seconds, but both normal buses are dead.

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
11/4/74	2/15/70	2 OF 5	NO. 2.1.7

EMERGENCY PROCEDURE

2. Bus breaker E8X225 opens at the same time E8X214 opens and E8X223 closes but since line E8L59 is also de-energized, the building is completely without electrical power. However, when E8L59 de-energizes, the powerhouse emergency generator starts up immediately. After a 15-second delay the powerhouse breaker E8X64 closes, feeding power from the emergency generator through the powerhouse breaker E8X66 to the 202-A E8X223 breaker and the emergency bus.
3. Upon restoration of power on Lines C8L8 and C8L5, the return to normal is identical to paragraphs #5 of procedures C and D, and paragraph #6 of procedure D.
4. After the complete return to normal of 202-A power, the electrician will call the powerhouse shift supervisor and notify him that 202-A is back to normal.

F. Extended Outage of Lines C8L8 and C8L5

In case of extended outages on lines C8L8 and C8L5, emergency power may be provided to any motor control center in the building by using a proper switching sequence.

The electrician must be extremely careful to follow the proper sequence. If too much load is added, the powerhouse emergency generator could become overloaded or the powerhouse breaker E8X66 could drop out, causing a power loss of extended duration.

1. Open all normal 480 volt feeder breakers in the east and west switchgear rooms, except the breaker feeding the motor control center associated with the equipment to be operated.
2. Open all normal 2300 volt breakers in the east switchgear room except the one feeding the 2300 to 480 volt bus to be energized.
3. Rack down both E8X209 and E8X214 breakers. E8X210 bus breaker is closed with the power failure and is in the ready position.
4. Operate keyed "normal-Bypass" switch of breaker E8X225 to bypass position and close E8X225. This supplies emergency power to both bus #2 and bus #1.

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
11/4/74	2/15/70	3 OF	NO. 2.1.7

G. Emergency Power Circuit

The following equipment is on the emergency power circuits:

1. One Instrument Air Compressor (either)
2. Building Emergency Lighting
3. MCC #1 - Motor Control Center #1
  - a. One Lab Exhaust Fan (either)
  - b. F-16 Agitator
  - c. Instrument Power & Emergency Lighting to 203-A and 211-A
  - d. Breathing Air Compressor
  - e. 291-A Emergency Lighting
  - f. Rectifiers for Centrifuge DC Brake Power
4. MCC #3 - Motor Control
  - a. One Sample Gallery Vacuum Pump (either)
  - b. Pump R5-1
  - c. Instrument Receptacle (exterior south wall 202-A)
  - d. Rectifiers for Centrifuge DC Brake Power
  - e. White Room Exhaust Fan
  - f. PR Exhaust Fan - EF2-7A
5. Motor Control Center #60
  - a. Agitator U-5
  - b. Pump U5-1
  - c. Pump U5-2
  - d. 206-A Lighting
  - e. Agitator U-7

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
11/4/74	2/15/70	4 OF 5	NO. 2.1.7

EMERGENCY PROCEDURE

6. Instrument Power Panels (at both ends of building)

H. Automatic Restart Equipment

The following equipment has an automatic restart feature. The pump selector switch must be set in the proper position.

1. Pumps G5-1 and G5-2
2. Pumps G7-1 and G7-2
3. Pumps R5-1 and R5-2

PREPARED BY JW Beck DATE 11-1-74
REVIEWED BY Jim Nech DATE 11-4-74
APPROVED &
ISSUED BY J.D. McIntosh DATE 11-4-74

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
11/4/74	2/15/70	5 OF 5	NO. 2.1.7

APPENDIX C

ARHCO Emergency Procedure: ARH-222-2.1.12
Radioactive Gaseous Discharges, Purex Plant

ISSUED BY THE MANAGER Purex UO ₂ Standby	SUBJECT RADIOACTIVE GASEOUS DISCHARGES PUREX PLANT		
A. <u>Introduction</u> Gases discharged from various Purex Plant stacks are monitored for radioactivity. Some of the emissions are measured and recorded continuously while others are monitored by periodic counts of air samples. Laboratory measurements are used for final determination and record on all stack samples. Certain actions and notifications are required in the event of a significant discharge of radioactivity. B. <u>Gaseous Discharge - Radioactivity Level Determination</u> First indication that a release of radioactive material to the atmosphere may have occurred will come from a monitoring instrument alarm or preliminary radiation instrument reading on a stack air sample. Operating supervision is to be notified at the first indication of an abnormal reading or alarm and will proceed to determine actions as outlined in Section C, below. Tables 1 and 2 attached provide some information to assist in preliminary evaluation of release levels. C. <u>Action Required</u> 1. <u>Supervisor's Responsibilities</u> a. Upon receiving an alarm the responsible supervisor will immediately investigate to determine if the alarm is due to high radioactivity or due to instrument malfunction. b. The supervisor will request replacements of the air sample and an immediate count of the sample by Radiation Monitoring. c. The supervisor will notify his management if the alarm is found to be due to a radioactivity level that exceeds the levels described in Section D, below. d. The supervisor will initiate an investigation to determine the source of radioactive emissions.			
DATE ISSUED: 1/06/76	SUPERSEDES ISSUE DATED: 2/16/73	PAGE 1 of 5	EMERGENCY PROCEDURE NO. 2.1.12

- e. The supervisor will keep management informed throughout the progress of his investigations. He will consult with management upon the course of action to resolve the problem. He will prepare a written report of the investigation and findings.

2. Radiation Monitoring Responsibilities

Radiation Monitoring will provide assistance by changing air samples, counting samples, and evaluating data.

3. Operations Technical Support

Operations Technical Support will provide assistance as required during the investigation, isolation and resolution of problems.

4. Management Responsibilities

- a. Purex - UO₃ Standby Section management will provide guidance as required during the investigation, isolation and resolution of problems.
- b. The Manager Purex - UO₃ Standby will determine when environmental discharges warrant defining the situation as being in the emergency category.
- c. Purex - UO₃ Standby management will implement activities required of personnel under emergency conditions.
- d. The Manager Purex - UO₃ Standby will communicate all information to Departmental management required under emergency conditions.

D. Situation Definitions and Actions

1. Class I

Definition

Daily environmental discharge exceeds ten percent of the release level values specified in Section 5 of Radiation Protection Standards ARH-220 (see table 2, attached) and returns to less than ten percent within 48 hours.

Action

Notify plant and department management. Investigate to determine the cause. Document investigation and conclusions.

DATE ISSUED: 1/06/76	SUPERSEDES (ISSUE DATED): 2/16/73	PAGE 2 OF 5	EMERGENCY PROCEDURE NO 2.1.12

PUREX OPERATIONS

2. Class II

Definition

Daily environmental discharge exceeds ten percent of the release level values in Section 5 of Radiation Protection Standards for more than 48 hours.

Action

Notify plant, department and division management. Investigate to determine the cause. Document the investigation and conclusions.

3. Class III - An Emergency

Definition

Environmental discharge exceeds the release level value in Section 5 of Radiation Protection Standards,

Action

Notify plant, department, division management and the Energy Research and Development Administration. Promptly investigate to determine the cause and corrective action.

4. Class IV - An Emergency

Definition

Environmental discharge that exceeds ten times the release level values in Section 5 of Radiation Protection Standards.

Action

Notify plant, department, division management and the Energy Research and Development Administration. Investigate promptly to determine the cause and corrective actions. If control cannot be immediately established or the discharge has exceeded 100 times the release level values, the facility shall be shut down. Document the investigation and conclusions. Take positive action to prevent recurrence.

PREPARED BY FR Lohdefinck DATE 12-19-75
REVIEWED BY KL Engelhardt DATE 23 Dec 75
APPROVED BY John Wilson DATE 1-2-76
APPROVED & ISSUED BY J. D. M. [Signature] DATE 1-6-76

DATE ISSUED: 1/06/76	SUPERSEDES ISSUE DATED: 2/16/73	PAGE 3 OF 5	EMERGENCY PROCEDURE NO 2.1.12

TABLE 1
PUREX STACK EMISSION CALCULATIONS

Identi- fication	Location	Sample Flow Rate (CFM)	Stack Flow Rate (CFM)	CONVERSION FACTORS		
				GM (Ci per c/m)	CP (Ci per mrad/hr	Alpha Detector (Ci per d/m
E-1 (PRSM)	PR Room, Q Cell, N Cell	2	4 900	3×10^{-8}	2×10^{-4}	1×10^{-9}
E-2	West Sample Gallery Hoods	2	2 900	2×10^{-8}	1×10^{-4}	7×10^{-10}
E-3	East Sample Gallery Hoods	2	3 600	2.5×10^{-8}	1.5×10^{-4}	8×10^{-10}
E-4	293-A Moto-aire Pump	2	3 700	2.5×10^{-8}	1.5×10^{-4}	8×10^{-10}
E-5A	Lab. West Duct	2	15 300	1×10^{-7}	6×10^{-4}	3.5×10^{-9}
E-5B	Lab. East Duct	2	12 400	8×10^{-8}	5×10^{-4}	3×10^{-9}
E-6	East Sample Gallery and U Cell	2	14 500	1×10^{-7}	6×10^{-4}	3.5×10^{-9}
E-7	West Sample Gallery and R Cell	2	20 000	1.5×10^{-7}	7×10^{-4}	5×10^{-9}
E-8	White Room	2	20 000	1.5×10^{-7}	7×10^{-4}	5×10^{-9}
BT-2	Burial Tunnel (Moto-aire Pump)	2	7 000	5×10^{-8}	2.5×10^{-4}	1.5×10^{-9}
E-7-4	200 ft. Stack	5	99 000	5×10^{-7}	5×10^{-4}	$9 \times 10^{-9*}$
FSB	200 ft. Stack	0.5	99 000	2.5×10^{-6}	1.5×10^{-3}	9×10^{-8}

*Determine disintegration rate of the entire sample.

Example:

CP reading on E-7-4 stack sample = 100 mrad/hr
 Total emission during sample period = $100 \text{ mrad/hr} \times 5 \times 10^{-4} \frac{\text{Ci}}{\text{mrad/hr.}}$
 = 0.05 Ci

DATE ISSUED: 1/06/76	SUPERSEDES ISSUE DATED: 2/16/73	PAGE 4 OF 5	EMERGENCY PROCEDURE NO 2.1.12

TABLE 2
GASEOUS WASTES
(Ref. ARH-220)

Gaseous radioactive wastes (mists or gases) shall be controlled so that the amounts released will be kept as small as practicable and should not average greater than the following amounts:

<u>Radionuclide</u>	<u>AMOUNT IN CURIES PER WEEK</u>	
	<u>Released from 200 ft. Stack</u>	<u>Released from Shorter Stacks or Vents</u>
^{90}Sr	0.1	0.01
^{131}I	.03	.003
Plutonium (total)	0.001	0.0001
Uranium (natural)	0.004	0.0004
Total of all others (excluding ^3H , ^{14}C , and noble gases)	.5	.05

In addition, the total amount of ^{131}I released from all 200 Area sources shall not exceed 1.0 curies per calendar quarter.

NOTE: ERDA Manual Chapter 0510 release levels are a factor of ten higher than those above.

END

**DATE
FILMED**

7/21/93