625
5/8/81
T.S.

(2)

1h. 2661

MASTER

DOE/ET/28443-T1

GEOHERMAL LOOP EXPERIMENTAL FACILITY
Final Report

April 1980

Work Performed Under Contract No. AC03-76ET28443

San Diego Gas & Electric
San Diego, California

U. S. DEPARTMENT OF ENERGY
Geothermal Energy

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

DISCLAIMER

"This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof."

This report has been reproduced directly from the best available copy.

Available from the National Technical Information Service, U. S. Department of Commerce, Springfield, Virginia 22161.

Price: Printed Copy A99
Microfiche A01

GEOTHERMAL LOOP EXPERIMENTAL FACILITY

Final Report

APRIL, 1980

**San Diego Gas & Electric
P. O. Box 1831
San Diego, California 92112**

**Prepared for the
Department of Energy
Under Contract No. DE-AC03-76ET28443
(Formerly EY-76-C-03-1137)**

FINAL REPORT
GEOTHERMAL LOOP EXPERIMENTAL FACILITY

TABLE OF CONTENTS

	<u>PAGE</u>
ABSTRACT	
ACKNOWLEDGEMENTS	
1.0 INTRODUCTION	
1.1 Site and Reservoir Description-----	1-1
1.2 Project Objectives-----	1-1
1.3 Participation and Funding-----	1-2
1.4 Evolution of Plant Designs and Operating Modes-----	1-2
2.0 EXECUTIVE SUMMARY AND CONCLUSION	
2.1 Binary Process-----	2-1
2.2 Flash/Binary Process-----	2-1
2.3 Two Stage Flash Process-----	2-4
2.4 Reactor Clarifier/Media Filter-----	2-5
2.5 Miscellaneous Activities-----	2-6
2.6 Recommendations-----	2-7
3.0 EARLY WELL FLOW AND FIELD TESTING	
3.1 Well Flow Tests-----	3-1
3.2 Field Tests-----	3-2
4.0 DESCRIPTION OF PLANT DESIGNS	
4.1 Four-Stage, Flash/Binary Cycle Design-----	4-1
4.2 Two-Stage, Flash-Cycle Design-----	4-2
4.3 Clarifier/Filter System Design-----	4-2
5.0 HISTORY OF PLANT CONSTRUCTION & START-UP ACTIVITIES	
5.1 Four-Stage, Flash/Binary Cycle-----	5-1
5.2 Two-Stage, Flash Cycle-----	5-5
5.3 Clarifier/Filter System-----	5-6
6.0 PLANT AND RESERVOIR OPERATIONS	
6.1 Overall Plant Performance-----	6-1
6.2 Production and Injection Wells-----	6-3

TABLE OF CONTENTS (Cont'd)

	<u>PAGE</u>
7.0 1976-1977 GLEF TEST PROGRAM (Four-Stage, Flash/Binary Cycle Operation)	
7.1 Operation Stability of the Flash/Binary Process; Plant Response to Transients and Upsets-----	7-2
7.2 Overall Heat and Mass Balance of the Plant under Baseline Operating Conditions-----	7-9
7.3 Clean-Tube Heat Transfer Coefficients with Water as the Binary Fluid-----	7-12
7.4 Purity of Vapor; Scrubber Performance-----	7-13
7.5 Scale Prevention-----	7-15
7.6 Materials and Component Evaluation-----	7-16
7.7 Effect of Noncondensable Gases on the Heat Transfer Coefficient-----	7-17
7.8 Continued Monitoring of Heat Transfer Coefficients and Fouling Resistance in Multi-Stage Heat Exchangers-----	7-17
7.9 Restoration of Clean-Tube Heat Transfer Coefficients-----	7-18
7.10 Operational Stability of the Flash/Binary Process during Isobutane Runs-----	7-19
7.11 Overall Heat and Mass Balance Baseline for Isobutane Runs-----	7-20
7.12 Condenser Performance with Isobutane as the Binary Fluid-----	7-20
7.13 Heat Transfer and Pressure Drop Performance of Isobutane in and around the Critical Region-----	7-21
7.14 Performance of Liquid Isobutane Exchangers, E-1A, B, C, and E-5-----	7-21
7.15 Determination of Nonequilibrium and Boiling Point Elevation-----	7-22
7.16 Comparison of Flashing Devices and Mist Eliminators-----	7-23
7.17 Analysis of Turndown Capability of the Flash Process-----	7-23
7.18 Long-Term Run under Baseline Conditions-----	7-24
7.19 References-----	7-25
8.0 1978-1979 GLEF TEST PROGRAM (Two-Stage, Flash-Cycle Operation)	
8.1 Scale Removal-----	8-1
8.2 Scaling Rate and Scale Properties-----	8-21
8.3 Scale Control Additives-----	8-30
8.4 Corrosion/Erosion-----	8-47

TABLE OF CONTENTS (Cont'd)

	<u>PAGE</u>
8.5 Evaluation of Tested Metallic Materials for Plant Applications-----	8-57
8.6 Plant Components and Instrumentation-----	8-66
8.7 Brine Chemistry-----	8-98
8.8 H ₂ S Abatement-----	8-108
8.9 Steam Separation-----	8-116
8.10 Injection Effluent Processing-----	8-117
8.11 Makeup Water Injection Compatibility-----	8-131
8.12 Well-Casing Materials-----	8-135
8.13 Injection Studies-----	8-143
8.14 Well Test Data Reduction-----	8-165
8.15 Scale Control-Inhibitors-----	8-166
 9.0 SUPPORTING ACTIVITIES	
9.1 Feasibility and Risk Study-----	9-1
9.2 Cooling Water Chemical Treatment-----	9-7
9.3 Scale Resistant Coatings-----	9-9
9.4 First Order Leveling Survey of GLEF Vicinity-----	9-11
9.5 FMC H ₂ S ABATEMENT-----	9-12
9.6 HYDRODYNAMICS SCALE DISINTEGRATOR-----	9-13
9.7 NON-CONDENSIBLE GAS CONTENT OF NILAND BRINES-----	9-14
9.8 PROPOSED DIRECT CONTACT HEAT EXCHANGER TESTING-----	9-17
9.9 SURGE CONTROL STUDY-----	9-20
9.10 VISUAL OBSERVATIONS OF INTERIOR OF SECOND STAGE FLASH VESSEL-----	9-22
9.11 CONDENSATE ACIDIFICATION-----	9-24

APPENDICES

LIST OF FIGURES

<u>FIGURE</u>		<u>PAGE</u>
1-1	AERIAL PHOTOGRAPH OF GLEF-----	1-1
1-2	GLEF SITE LOCATION-----	1-1
1-3	GLEF PLOT PLAN-----	1-1
1-4	GLEF HISTORY-----	1-2
3.2-1	1974 GEOTHERMAL FIELD TEST PRODUCTION AND INJECTION SYSTEM FLOW DIAGRAM-----	3-4
4.1-1	GLEF PROCESS SCHEMATIC, FOUR STAGE, FLASH/ BINARY CYCLE-----	4-1
4.2-1	GLEF TWO STAGE, FLASH/BINARY PROCESS FLOW DIAGRAM-----	4-2
4.3-1	TWO STAGE, FLASH-CYCLE PROCESS SCHEMATIC WITH CLARIFIER FILTER-----	4-3
4.3-2	GLEF CLARIFIER FILTER INSTALLATION PROCESS FLOW DIAGRAM-----	4-3
4.3-3	REACTOR CLARIFIER (V-17)-----	4-3
4.3-4	SVG SAND FILTER (V-18)-----	4-3
4.3-5	THICKENER (V-22)-----	4-4
4.3-6	PLATE AND FRAME FILTER PRESS (F-1)-----	4-4
5.1-1	FOUR STAGE FLASH/BINARY START-UP SCHEDULE--	5-3
5.3-1	CLARIFIER/FILTER INSTALLATION AND START-UP SCHEDULE-----	5-6
6.1-1	GLEF 1976-1979 AVAILABILITY BY MONTHS-----	6-2
6.2-1	GEOTHERMAL WELL-----	6-3
6.2-2	BAKER, MODEL M, DRILLABLE BRIDGE PLUG-----	6-3
6.2-3	WOOLSEY NO. 1 WELL-----	6-3
6.2-4	WOOLSEY NO. 1 WELL-----	6-3
7-1	FLOW DIAGRAM WITH SELECTED MEASUREMENT LOCATIONS INDICATED-----	7-5
7-2	PRESSURE OF INCOMING GEOTHERMAL FLUID (P1-1)-----	7-5
7-3	PRESSURE IN FLASH VESSEL V-1 (P1-2)-----	7-5
7-4	PRESSURE AT OUTLET OF SCRUBBER V-8 (P1-5)--	7-5
7-5	PRESSURE IN FLASH VESSEL V-7 (P2-1)-----	7-5
7-6	PRESSURE IN FLASH VESSEL V-14 (P3-1)-----	7-5
7-7	PRESSURE IN FLASH VESSEL V-11 (P4-1)-----	7-5
7-8	TEMPERATURE OF INCOMING GEOTHERMAL FLUID (T1-1)-----	7-5
7-9	VAPOR TEMPERATURE AT OUTLET OF FLASH VESSEL V-1 (T1-3)-----	7-5
7-10	TEMPERATURE AT OUTLET OF SCRUBBER V-8 (T1-7)	7-5
7-11	OUTLET TEMPERATURE FOR HEAT EXCHANGER E-2 (T1-10)-----	7-5
7-12	VAPOR TEMPERATURE AT OUTLET OF FLASH VESSEL V-7 (T2-1)-----	7-5

LIST OF FIGURES (Cont'd)

<u>FIGURE</u>		<u>PAGE</u>
7-13	OUTLET TEMPERATURE FOR HEAT EXCHANGER E-1A (T2-4)-----	7-5
7-14	VAPOR TEMPERATURE AT OUTLET OF FLASH VESSEL V-14 (T3-1)-----	7-5
7-15	OUTLET TEMPERATURE FOR HEAT EXCHANGER E-1B (T3-4)-----	7-5
7-16	VAPOR TEMPERATURE AT OUTLET OF FLASH VESSEL V-11 (T4-1)-----	7-5
7-17	OUTLET TEMPERATURE FOR HEAT EXCHANGER E-1C (T4-4)-----	7-5
7-18	PRESSURE DOWNSTREAM FROM CIRCULATION PUMP (P1-10)-----	7-5
7-19	PRESSURE AT OUTLET OF HEAT EXCHANGER E-3 (P1-7)-----	7-5
7-20	TEMPERATURE UPSTREAM FROM HEAT EXCHANGER E-5 (T1-15)-----	7-5
7-21	TEMPERATURE AT OUTLET OF HEAT EXCHANGER E-5 (T4-5)-----	7-5
7-22	TEMPERATURE AT OUTLET OF HEAT EXCHANGER (T4-6)-----	7-5
7-23	TEMPERATURE AT OUTLET OF HEAT EXCHANGER E-1B (T3-5)-----	7-5
7-24	TEMPERATURE AT OUTLET OF HEAT EXCHANGER E-1A (T2-5)-----	7-5
7-25	TEMPERATURE AT OUTLET OF HEAT EXCHANGER E-3 (T1-9)-----	7-5
7-26	TEMPERATURE OF INCOMING COOLING WATER (T5-1)-----	7-5
7-27	TEMPERATURE OF COOLING WATER AT CONDENSER OUTLET (T5-2)-----	7-5
7-28	PRESSURE OF INCOMING GEOTHERMAL FLUID FROM WOOLSEY NO. 1 (P1-1)-----	7-8
7-29	PRESSURE IN FLASH VESSEL V-1 (P1-2)-----	7-8
7-30	PRESSURE OF INCOMING GEOTHERMAL FLUID FROM MAGMAX NO. 1 (P1-3)-----	7-8
7-31	PRESSURE IN FLASH VESSEL V-4 (P1-4)-----	7-8
7-32	PRESSURE AT OUTLET OF SCRUBBER V-8 (P1-5)---	7-8
7-33	PRESSURE IN FLASH VESSEL V-7 (P2-1)-----	7-8
7-34	PRESSURE IN FLASH VESSEL V-14 (P3-1)-----	7-8
7-35	PRESSURE IN FLASH VESSEL V-11 (P4-1)-----	7-8
7-36	TEMPERATURE OF INCOMING GEOTHERMAL FLUID FROM WOOLSEY NO. 1 (T1-1)-----	7-8
7-37	VAPOR TEMPERATURE AT OUTLET OF FLASH VESSEL V-1 (T1-3)-----	7-8
7-38	TEMPERATURE OF INCOMING GEOTHERMAL FLUID FROM MAGMAX NO. 1 (T1-4)-----	7-8
7-39	VAPOR TEMPERATURE AT OUTLET OF FLASH VESSEL V-4 (T1-6)-----	7-8
7-40	TEMPERATURE AT OUTLET OF SCRUBBER V-8 (T1-7)-----	7-8

LIST OF FIGURES (Cont'd)

<u>FIGURE</u>		<u>PAGE</u>
7-41	OUTLET TEMPERATURE FOR HEAT EXCHANGER E-2 (T1-10)-----	7-8
7-42	VAPOR TEMPERATURE AT OUTLET OF FLASH VESSEL V-7 (T2-1)-----	7-8
7-43	OUTLET TEMPERATURE FOR HEAT EXCHANGER E-1A (T-2-4)-----	7-8
7-44	VAPOR TEMPERATURE AT OUTLET OF FLASH VESSEL V-14 (T3-1)-----	7-8
7-45	OUTLET TEMPERATURE FOR HEAT EXCHANGER E-1B (T3-4)-----	7-8
7-46	VAPOR TEMPERATURE AT OUTLET OF FLASH VESSEL V-11 (T4-1)-----	7-8
7-47	OUTLET TEMPERATURE FOR HEAT EXCHANGER E-1C (T4-4)-----	7-8
7-48	PRESSURE DOWNSTREAM FROM CIRCULATION PUMP (P1-10)-----	7-8
7-49	PRESSURE AT OUTLET OF HEAT EXCHANGER E-3 (P1-7)-----	7-8
7-50	TEMPERATURE UPSTREAM FROM HEAT EXCHANGER E-5 (T1-15)-----	7-8
7-51	TEMPERATURE AT OUTLET OF HEAT EXCHANGER E-5 (T4-5)-----	7-8
7-52	TEMPERATURE AT OUTLET OF HEAT EXCHANGER E-1C (T4-6)-----	7-8
7-53	TEMPERATURE AT OUTLET OF HEAT EXCHANGER E-1B (T3-5)-----	7-8
7-54	TEMPERATURE AT OUTLET OF HEAT EXCHANGER E-1A (T2-5)-----	7-8
7-55	TEMPERATURE AT OUTLET OF HEAT EXCHANGER E-3 (T1-9)-----	7-8
7-56	TEMPERATRE OF INCOMING COOLING WATER (T5-1)-----	7-8
7-57	TEMPERATURE OF COOLING WATER AT CONDENSER OUTLET (T5-2)-----	7-8
7-58	FLOW DIAGRAM WITH VARIABLES USED FOR PARTIAL PLANT HEAT BALANCE-----	7-10
7-59	FIRST STAGE SCRUBBER PERFORMANCE-----	7-13
7-60	SECOND STAGE SCRUBBER PERFORMANCE-----	7-13
7-61	THIRD STAGE SCRUBBER PERFORMANCE-----	7-13
7-62	FOURTH STAGE SCRUBBER PERFORMANCE-----	7-13
8.1-1	SCALE IN SECOND STAGE DRAIN LINE-----	8-3
8.1-2	SCALE IN SECOND STAGE DRAIN LINE-----	8-3
8.1-3	SCALE IN SECOND STAGE DRAIN LINE-----	8-3
8.1-4	HYDROBLASTING A GLEF FLASH VESSEL-----	8-5
8.1-5	GLEF HYDROBLASTER-----	8-5
8.1-6	TYPICAL EQUIPMENT CONFIGURATION FOR HYDROBLASTING GLEF BRINE PIPING-----	8-5
8.1-7	TYPICAL EQUIPMENT USED FOR PIGGING-----	8-10
8.1-8	GIRARD POLLY PIG-----	8-11

LIST OF FIGURES (Cont'd)

<u>FIGURE</u>		<u>PAGE</u>
8.1-9	GIRARD POLLY PIG-----	8-11
8.1-10	T. D. WILLIAMSON WIRE BRUSH PIG (USED)-----	8-11
8.1-11	T. D. WILLIAMSON WIRE BRUSH PIG (USED)-----	8-11
8.1-12	DAMAGED POLLY PIG-----	8-13
8.1-13	DAMAGED POLLY PIG FIRST TO SECOND STAGE----	8-13
8.1-14	DAMAGED POLLY PIG FIRST TO SECOND STAGE----	8-13
8.2-1	SCALE-CONTROL TEST SYSTEM-----	8-22
8.2-2	SCHEMATIC DIAGRAM OF GLEF SCALE SAMPLING POINTS-----	8-24
8.2-3	DISSOLUTION OF WPL SCALE (WOOLSEY, PRODUCTION LINE) BY VARIOUS REAGENTS-----	8-25
8.2-4	DISSOLUTION OF W-1A-IN SCALE (WOOLSEY, FIRST STAGE) BY VARIOUS REAGENTS-----	8-25
8.2-5	DISSOLUTION OF W-1A-DS SCALE (WOOLSEY, FIRST STAGE) BY VARIOUS REAGENTS-----	8-25
8.2-6	DISSOLUTION OF W-2A-DS SCALE (WOOLSEY, SECOND STAGE) BY VARIOUS REAGENTS-----	8-25
8.2-7	DISSOLUTION OF W-V15-OUT SCALE (WOOLSEY, ATMOSPHERIC RECEIVER) BY VARIOUS REAGENTS--	8-25
8.2-8	DISSOLUTION OF WELLHEAD SCALE (MAGMAMAX) BY VARIOUS REAGENTS-----	8-25
8.2-9	DISSOLUTION OF V4 SCALE (MAGMAMAX, FIRST STAGE) BY VARIOUS REAGENTS-----	8-25
8.2-10	DISSOLUTION OF V4D SCALE (MAGMAMAX, FIRST STAGE) BY VARIOUS REAGENTS-----	8-25
8.2-11	DISSOLUTION OF V11T SCALE (MAGMAMAX, SECOND STAGE) BY VARIOUS REAGENTS-----	8-25
8.2-12	DISSOLUTION OF V11 SCALE (MAGMAMAX, SECOND STAGE) BY VARIOUS REAGENTS-----	8-25
8.2-13	DISSOLUTION OF V11D SCALE (MAGMAMAX, SECOND STAGE) BY VARIOUS REAGENTS-----	8-25
8.2-14	DISSOLUTION OF V15D SCALE (MAGMAMAX, ATMOSPHERIC RECEIVER) BY VARIOUS REAGENTS--	8-25
8.3-1	SCALE CONTROL TEST SYSTEM-----	8-31
8.4-1	MATERIALS TESTED FOR CORROSION/EROSION-----	8-47
8.4-2	GLEF PARTIAL FLOW DIAGRAM SHOWING LOCATION AND IDENTIFICATION OF VARIOUS TEST SPOOLS-----	8-49
8.6-1	PLANT COMPONENTS AND INSTRUMENTATION-----	8-66
8.6-2	GLEF FOUR STAGE FLASH/BINARY PROCESS FLOW DIAGRAM-----	8-66
8.6-3	GLEF TWO STAGE FLASH/BINARY PROCESS FLOW DIAGRAM-----	8-66
8.6-4	BRINE TANK INJECTION PUMP (P-13)-----	8-68
8.6-5	BRINE TANK INJECTION PUMP (P-13) SHAFT-----	8-68
8.6-6	BRINE TANK INJECTION PUMP (P-13) SHAFT-----	8-68

LIST OF FIGURES (Cont'd)

<u>FIGURE</u>		<u>PAGE</u>
8.6-7	CLARIFIER FEED PUMP (P-16A) VIBRATION READINGS-----	8-69
8.6-8	CLARIFIER FEED PUMP (P-16B) IMPELLER-----	8-70
8.6-9	MANUAL GATE VALVES (BRINE SYSTEM)-----	8-75
8.6-10	DISMANTLED GATE VALVES (BRINE SYSTEM)-----	8-75
8.6-11	DISMANTLED GATE VALVES (BRINE SYSTEM)-----	8-75
8.6-12	MANUAL GATE VALVES BRINE SYSTEM-----	8-75
8.6-13	"RED" VALVE PINCH VALVE-----	8-78
8.6-14	GALIGHER PINCH VALVE-----	8-79
8.6-15	PRESSURE VALVE (PCV-300) BRINE SYSTEM-----	8-81
8.6-16	PRESSURE VALVE (PCV-301) BRINE SYSTEM-----	8-81
8.6-17	LEVEL VALVE (LCV-712) BRINE SYSTEM-----	8-83
8.6-18	STRAHMAN HAND OPERATED SAMPLING VALVE-----	8-85
8.6-19	SAFETY RELIEF VALVES DISMANTLED-----	8-89
8.6-20	SAFETY RELIEF VALVES DISMANTLED-----	8-89
8.6-21	SAFETY RELIEF VALVES DISMANTLED-----	8-89
8.6-22	SAFETY RELIEF VALVES DISMANTLED-----	8-89
8.6-23	CONDENSATE PUMP (P-14)-----	8-94
8.6-24	COOLING WATER PUMP (P-3)-----	8-96
8.6-25	COOLING WATER PUMP (P-3)-----	8-96
8.7-1	TRAVERSING SAMPLE PROBE-----	8-99
8.8-1	EXPERIMENTS CONDUCTED WITH SMALL, SINGLE STAGE, COUNTERCURRENT FLOW CONTACTOR-----	8-109
8.8-2	RESULTS WITH COOLED EFFLUENT (25°C)-----	8-110
8.8-3	RESULTS WITH BRINE EFFLUENTS NEAR CLARIFICATION TEMPERATURES (85°C)-----	8-110
8.10-1	CLARIFIER/FILTER INSTALLATION PROCESS FLOW DIAGRAM-----	8-118
8.10-2	SOLIDS CONTACT REACTOR CLARIFIER-----	8-123
8.10-3	CLARIFIER FLOWS-----	8-124
8.10-4	SETTLING RATE VS SUSPENDED SOLIDS IN REACTION ZONE-----	8-124
8.10-5	SILICA IN SOLUTION IN CLARIFIER EFFLUENT VS SUSPENDED SOLIDS IN REACTION ZONE-----	8-124
8.10-6	SUSPENDED SOLIDS-----	8-125
8.10-7	SILICA IN SOLUTION-----	8-125
8.10-8	SUSPENDED SOLIDS ACROSS SVG FILTER-----	8-126
8.11-1	EXPERIMENTAL ARRANGEMENT FOR SALTON SEA ADDITION TESTING-----	8-131
8.11-2	CLARIFIER REACTOR-----	8-131

LIST OF FIGURES

<u>FIGURE</u>		<u>PAGE</u>
8.12-1	THICKNESS OF SCALE ON TEST STRING SURFACE VS. DEPTH IN WELL FOR API TEST STRING TESTED IN WOOLSEY NO. 1-----	8-138
8.12-2	INDICATED PENETRATION RATE VS. DEPTH FOR J55, N80, AND C75 FOR API TEST STRING TESTED IN WOOLSEY NO. 1-----	8-139
8.13-1	CLARIFIER INFLUENT INCUBATION TEST RESULTS (90°C) AUGUST 1, 1967-----	8-149
8.13-2	CLARIFIER EFFLUENT INCUBATION TEST RESULTS (86-88°C) AUGUST 1, 1979-----	8-149
8.13-3	GRAVITY FILTER EFFLUENT INCUBATION TEST RESULTS (86-88°C) AUGUST 1, 1979-----	8-149
8.13-4	EFFECT OF POLYMER ON STABILITY OF CLARIFIER INFLUENT (85-90°C) AUGUST 1-2, 1979-----	8-150
8.13-5	SLUDGE CONTACT DESTABILIZATION OF SILICA IN CLARIFIER INFLUENT (85-90°C) AUGUST 1-2, 1979-----	8-150
8.13-6	EFFECT OF POLYMER ON SLUDGE CONTACT DESTABILIZATION OF SILICA (85-90°C) AUGUST 1-2, 1979-----	8-150
8.13-7	MEMBRANE FILTRATION TESTS OF CONDITIONED BRINE MAGMA POWER CLARIFIER-FILTRATION SYSTEM AUGUST 8, 1979-----	8-151
8.13-8	8 MICRON MEMBRANE FILTRATION TEST RESULTS FOR CONDITIONED BRINE FROM MAGMA POWER'S CLARIFIER-FILTER SYSTEM (AUGUST 8, 1979)---	8-151
8.13-9	PERMEABILITY OF KAYENTA SANDSTONE TO CONDITIONED BRINE FROM THE MAGMA POWER CLARIFIER-FILTRATION SYSTEM-----	8-152
8.13-10	CORE SAMPLE EXPOSED TO CONDITIONED BRINE PRODUCED BY THE 10 MW CLARIFIER FILTRATION SYSTEM-----	8-153
8.13-11	BARKMAN AND DAVIDSON - TYPE FILTRATION CURVE FOR KAYENTA SANDSTONE SHOWING INVASION-----	8-157
9.3-1	TEST OF CORRECO 700 SCALE RESISTANT COATING-----	9-9
9.4-1	LOCATION OF BENCHMARKS-----	9-11
9.8-1	HEAT BALANCE DIAGRAM FOR THE LIQUID- LIQUID PREHEATER CYCLE-----	9-17
9.8-2	DIRECT CONTACT PREHEATER-----	9-18
9.9-1	PROPOSED SURGE TANK FOR GLEF-----	9-21
9.10-1	SECOND STAGE FLASH VESSEL (V-11) SHOWING POSITION OF VIEW PORTS-----	9-22

LIST OF TABLES

<u>TABLE</u>		<u>PAGE</u>
7-1	PRESSURES AND TEMPERATURES DURING TEST RUN 7/7/77 THROUGH 7/11/77-----	7-5
7-2	PRESSURES AND TEMPERATURES DURING TEST RUN 1/4/78 AND 1/5/78-----	7-8
7-3	PARTIAL PLANT HEAT BALANCE RESULTS-----	7-10
7-4	NONEQUILIBRIUM ALLOWANCE-----	7-22
8.1-1	CLEANING TECHNIQUES VERSUS AREAS USED-----	8-1
8.1-2	RESULTS OF PIGGING AT GLEF-----	8-12
8.2-1	COMPOSITION OF SCALES FOR THE GLEF AFTER OPERATION WITH BRINE FROM WOOLSEY NO. 1 and MAGMAMAX NO. 1-----	8-25
8.2-2	COMPOSITION OF GLEF SCALES AFTER OPERATION WITH BRINE FROM WOOLSEY NO. 1 AND MAGMAMAX NO. 1 AS DETERMINED BY X-RAY DEFFRACTION ANALYSIS-----	8-25
8.2-3	MAGMAMAX NO. 1 SCALE DISSOLUTION RESULTS---	8-25
8.2-4	WOOLSEY NO. 1 SCALE DISSOLUTION RESULTS---	8-25
8.2-5	WOOLSEY NO. 1 SCALE HARDNESS AND SCALING RATES-----	8-26
8.2-6	MAGMAMAX NO. 1 SCALING RATES-----	8-26
8.3-1	SCALING RATES OF UNTREATED BRINE MEASURED DURING THE NOVEMBER/DECEMBER TEST SERIES (MAGMAMAX NO. 1 WELL)-----	8-36
8.3-2	PROPRIETARY ADDITIVES TESTED IN NOVEMBER- DECEMBER, 1978 TEST SERIES-----	8-36
8.3-3	PERFORMANCE OF EIGHT PROPRIETARY ADDITIVES AS ANTISCALANTS IN MAGMAMAX NO. 1 BRINE----	8-36
8.3-4	CORROSION RATES OF MILD STEEL (AISI 1018) IN ADDITIVE-TREATED BRINE MEASURED BY THE LINEAR POLARIZATION RESISTANCE TECHNIQUE-----	8-37
8.3-5	ADDITIONAL PROPRIETARY ADDITIVES TESTED AS SILICA PRECIPITATION INHIBITORS-----	8-38
8.3-6	MEASUREMENTS OF CONCENTRATION OF "DISSOLVED SILICA" IN BRINE DURING SEEDING EXPERIMENT-----	8-40
8.3-7	SCALING RATES OF UNTREATED BRINE AND BRINE TREATED BY THE AUSTRAL-ERWIN PROCESS (MAGMAMAX NO. 1 WELL)-----	8-41
8.3-8	ELEMENTAL ANALYSES OF SCALES DEPOSITED ON TEFLON TFE COUPONS AT 210°C FROM BRINE TREATED WITH VARIOUS ADDITIVES (MAGMAMAX NO. 1 BRINE; 4.1 Mol/Chloride)-----	8-43

LIST OF TABLES (Cont'd)

<u>TABLE</u>		<u>PAGE</u>
8.3-9	ELEMENTAL ANALYSIS OF SCALES DEPOSITED ON TEFLON TFE COUPONS AT 125°C FROM BRINE TREATED WITH VARIOUS ADDITIVES (MAGMAMAX NO. 1 BRINE; 4.1 Mol/Chloride)---	8-43
8.4-1	CORROSION RATES OF COUPONS-----	8-52
8.4-2	CORROSION OF TEST SPOOLS-----	8-53
8.4-3	PLANT EQUIPMENT WALL THICKNESS CHANGES-----	8-53
8.4-4	CLARIFIER FILTER SYSTEM WALL THICKNESS CHANGES-----	8-53
8.5-1	IDENTIFICATION, COMPOSITIONS, AND HEAT TREATMENTS OF MATERIALS TESTED IN 720 HR ACIDIFIED BRINE CORROSION AND STRESS CORROSION TEST-----	8-58
8.5-2	ACIDIFIED BRINE CORROSION AND STRESS CORROSION TEST RESULTS: CARBON AND LOW TO INTERMEDIATE ALLOY (LESS THAN 11%) STEELS-----	8-61
8.5-3	ACIDIFIED BRINE CORROSION AND STRESS CORROSION TEST RESULTS: MARTENSITIC AND FERRITIC STAINLESS STEELS-----	8-61
8.5-4	ACIDIFIED BRINE CORROSION AND STRESS CORROSION TEST RESULTS: AUSTENITIC STAINLESS STEELS-----	8-61
8.5-5	ACIDIFIED BRINE CORROSION AND STRESS CORROSION TEST RESULTS: HIGH NICKEL AND HIGH COBALT MATERIALS-----	8-61
8.5-6	OBSERVATIONS ON METALLURGICAL STRUCTURE AND CRACK MORPHOLOGY FOR CERTAIN OF THE STRESS CORROSION TESTED SPECIMENS-----	8-61
8.5-7	TIME-DEPENDENT CORROSION RATES OF STEELS EXPOSED TO WELLHEAD BRINE--MAGMAMAX NO. 1 WELL-----	8-63
8.7-1	ELEMENT OR COMPOUND ANALYZED, ANALYTICAL PROCEDURE AND EXPECTED VARIANCE-----	8-100
8.7-2	TYPICAL MOLAR CONCENTRATION FOR FOUR STAGE FLASH CONFIGURATION (MAGMAMAX NO. 1)--	8-103
8.7-3	TYPICAL MOLAR CONCENTRATION FOR TWO STAGE FLASH CONFIGURATION (MAGMAMAX NO. 1)--	8-103
8.7-4	TYPICAL MOLAR CONCENTRATION FOR FOUR STAGE FLASH CONFIGURATION (WOOLSEY NO. 1)--	8-103
8.7-5	TYPICAL MOLAR CONCENTRATION FOR TWO STAGE FLASH CONFIGURATION (WOOLSEY NO. 1)--	8-103
8.7-6	ELEMENTAL RANGE FOR WELLHEAD BRINE AT MAGMAMAX NO. 1-----	8-104
8.7-7	ELEMENTAL RANGE FOR WELLHEAD BRINE AT WOOLSEY NO. 1-----	8-104

LIST OF TABLES (Cont'd)

<u>TABLE</u>		<u>PAGE</u>
8.7-8	AVERAGE IONIC CONCENTRATION (PPM) IN THE STEAM FOR MAGMAMAX NO. 1 FLUID (NOV. 1978-DEC. 1978)-----	8-104
8.7-9	AVERAGE IONIC CONCENTRATION (PPM) IN THE STEAM FOR WOOLSEY NO. 1 FLUID (JAN. 1979-MAR. 1979)-----	8-104
8.7-10	NONCONDENSIBLE GASES FROM MAGMAMAX NO. 1 WELLHEAD-----	8-104
8.7-11	TYPICAL SCALE ANALYSIS FROM THE FOUR STAGE FLASH SYSTEM USING THE TOTAL DIGESTION PROCEDURE-----	8-105
8.7-12	TYPICAL SCALE ANALYSIS FROM THE FOUR STAGE FLASH SYSTEM USING TOTAL DIGESTION PROCEDURE-----	8-105
8.7-13	TYPICAL SCALE ANALYSIS FROM THE FOUR STAGE FLASH SYSTEM USING THE TOTAL DIGESTION PROCEDURE-----	8-105
8.7-14	TYPICAL SCALE ANALYSIS FROM THE FOUR STAGE FLASH SYSTEM USING THE TOTAL DIGESTION PROCEDURE-----	8-105
8.7-15	TYPICAL SCALE ANALYSIS FROM THE TWO STAGE FLASH SYSTEM USING THE SELECTIVE LEACHING METHOD-----	8-106
8.7-16	TYPICAL SCALE ANALYSIS FROM THE TWO STAGE FLASH SYSTEM USING THE SELECTIVE LEACHING METHOD-----	8-106
8.7-17	TYPICAL SCALE ANALYSIS FROM THE TWO STAGE FLASH SYSTEM USING THE SELECTIVE LEACHING METHOD-----	8-106
8.7-18	TYPICAL SCALE ANALYSIS FROM THE TWO STAGE FLASH SYSTEM USING THE SELECTIVE LEACHING METHOD-----	8-106
8.7-19	TYPICAL SCALE ANALYSIS FROM THE TWO STAGE FLASH SYSTEM USING THE SELECTIVE LEACHING METHOD-----	8-106
8.8-1	H ₂ S SCRUBBING DATA AND EFFICIENCIES USING LOW TEMPERATURE (25-30°C) BRINE EFFLUENT (WOOLSEY NO. 1 FLUID)-----	8-110
8.8-2	H ₂ S SCRUBBING DATA AND EFFICIENCIES USING HOT (80 ± 5°C) BRINE EFFLUENT (MAGMAMAX NO. 1 FLUID)-----	8-110
8.8-3	LEAD AND ZINC CONCENTRATION IN SCRUBBER BRINES-----	8-111
8.10-1	CHEMICAL ANALYSIS OF SPENT GEOTHERMAL BRINE FROM THE GLEF-----	8-117
8.10-2	FILTER PRESS CAKE ELEMENTAL ANALYSIS-----	8-127

LIST OF TABLES (Cont'd)

<u>TABLE</u>		<u>PAGE</u>
8.11-1	COMPARISON OF TEST RESULTS-----	8-132
8.11-2	ELEMENTAL ANALYSIS OF SLUDGE (80% GEOTHERMAL BRINE 20% SALTON SEA)-----	8-132
8.11-3	TEST RESULTS-----	8-132
8.12-1	SUMMARY OF API MATERIAL ANALYSIS AND PROPERTIES-----	8-137
8.12-2	SUMMARY OF API TESTING STRING MAKEUP-----	8-137
8.12-3	SUMMARY OF WOOLSEY NO. 1 WELL OPERATIONAL HISTORY DURING THE API STRING TEST PERIOD FROM JANUARY 16 TO MARCH 26, 1979-----	8-137
8.12-4	WOOLSEY NO. 1 BRINE PROPERTIES AND COMPOSITION-----	8-137
8.12-5	SUMMARY OF RESULTS OF METALLURGICAL CHARACTERIZATION OF API TEST STRING MATERIALS-----	8-138
8.12-6	J55 CORROSION MEASUREMENTS-----	8-138
8.12-7	N80 AND C75 CORROSION MEASUREMENTS-----	8-139
8.13-1	RESULTS OF INCUBATION TESTS (AUGUST 1, 1979)-----	8-148
8.13-2	EFFECT OF 20 PPM (WT) PAE-HCL POLYMER ON PRECIPITATION OF DISSOLVED SILICA FROM CLARIFIER INFLUENT (90°C) (AUGUST 2, 1979)-----	8-148
8.13-3	EFFECT OF 20 PPM (WT) PAE-HCL POLYMER ON SLUDGE CONTACT REMOVAL OF DISSOLVED SILICA FROM CLARIFIER INFLUENT (90°C) (AUGUST 1, 1979)-----	8-148
8.13-4	0.4 MICRON MEMBRANE FILTRATION TEST RESULTS FOR CONDITIONED BRINE FROM MAGMA POWER'S CLARIFIER-FILTER SYSTEM (AUGUST 8, 1979)-----	8-148
8.13-5	1.0 MICRON MEMBRANE FILTRATION TEST RESULTS FOR CONDITIONED BRINE FROM MAGMA POWER'S CLARIFIER-FILTER SYSTEM (AUGUST 8, 1979)-----	8-148
8.13-6	PREFILTERED 0.4 MICRON MEMBRANE FILTRATION TEST RESULTS FOR CONDITIONED BRINE FROM MAGMA POWER'S CLARIFICATION-FILTER SYSTEM (AUGUST 8, 1979)-----	8-148
8.13-7	8 MICRON MEMBRANE FILTRATION TEST RESULTS FOR CONDITIONED BRINE FROM MAGMA POWER'S CLARIFIER-FILTER SYSTEM (AUGUST 8, 1979)---	8-148
8.13-8	PREFILTERED 8 MICRON MEMBRANE FILTRATION TEST RESULTS FOR CONDITIONED BRINE FROM MAGMA POWER'S CLARIFIER-FILTER SYSTEM (AUGUST 8, 1979)-----	8-148
8.13-9	KAYENTA SANDSTONE CORE TEST RESULTS-----	8-149

LIST OF TABLES (Cont'd)

<u>TABLE</u>		<u>PAGE</u>
8.13-10	BASIS FOR HALF LIFE CALCULATIONS-----	8-151
8.13-11	RESULTS OF MEMBRANE FILTRATION AND CORE TESTS OF GRAVITY FILTER EFFLUENT-----	8-152
8.13-12	CHEMICAL ANALYSIS OF WATERS-----	8-153
8.13-13	SALTON SEA WATER HEATING EXPERIMENTAL RESULTS-----	8-153
8.13-14	FILTRATION PROPERTIES OF WATERS-----	8-154
8.13-15	SALTON SEA WATER-BRINE MIXTURE REHEATING---	8-155
8.13-16	CHEMICAL ANALYSIS SALTON SEA MIXTURES-----	8-156
8.13-17	EFFECT OF SLUDGE CONTACT ON DISSOLVED SILICA-----	8-157
8.13-18	RESULTS OF PROCESSED MAKEUP WATER 0.45 MICRON MEMBRANE FILTRATION TEST-----	8-157
8.13-19	RESULTS OF PROCESSED MAKEUP WATER KAYENTA CORE TEST-----	8-157
9.1-1	COMPARISON OF FLASHED STEAM AND BINARY PROCESSES-----	9-3
9.4-1	BENCHMARK ELEVATIONS-----	9-11
9.5-1	FMC H ₂ S TEST RESULTS-----	9-12

LIST OF APPENDICES

APPENDIX

- A COMPLETION TECHNOLOGY REPORT
- B LAWRENCE BERKELEY LABORATORY REPORT GLEF
PERFORMANCE DATA
- C SCREENING ANTI-SCALANTS FOR USE IN THE
GLEF
- D SURGE CONTROL STUDY FOR GLEF
- E APPLICABLE REPORTS FOR THE GLEF
- F CLARIFIER OPERATIONS DATA SHEETS

LIST OF TERMS

GLEF	-	Geothermal Loop Experimental Facility
KGRA	-	Known Geothermal Resource Area
SDG&E	-	San Diego Gas & Electric Company
NARCO	-	New Albion Resource Company
LLL	-	Lawrence Livermore Laboratory
LBL	-	Lawrence Berkeley Laboratory
DOE	-	Department of Energy
TDS	-	Total Dissolved Solids
PPM	-	Parts Per Million
MAGMA	-	Imperial Magma
ASTM	-	American Society for Testing Materials
ASME	-	American Society of Mechanical Engineers
PSIG	-	Pounds Per Square Inch Gauge
PSIA	-	Pounds Per Square Inch Absolute
TDH	-	Total Discharge Head
B/D	-	Barrels per Day
MD	-	Millidarcys
HP	-	Horsepower
GPM	-	Gallons Per Minute
V	-	Volt

ABSTRACT

Research at the San Diego Gas & Electric (SDG&E)/ U. S. Department of Energy (DOE) cofunded Geothermal Loop Experimental Facility was successfully concluded in September of 1979. In 13,000 hours of operation over a three and one half year period, the nominal 10 megawatt electrical equivalent GLEF provided engineers and researchers from SDG&E, national laboratories, government agencies and industry the opportunity to identify problems in working with highly saline geothermal fluids and to develop solutions that could be applied to a commercial geothermal power plant producing electricity.

This report covers a seven and one half year period beginning in April, 1972, with early well flow testing and ending in September, 1979, with the completion of extensive facility and reservoir operations. During this period, the facility was designed, constructed and operated in several configurations. This report is intended as a comprehensive reference document, addressing or referencing documentation of all the key areas investigated.

ACKNOWLEDGEMENTS

SDG&E would like to acknowledge a number of individuals and organizations that contributed to this Project.

The United States Department of Energy and its predecessor, the Energy Research and Development Administration (ERDA), cofunded and supported the facility with SDG&E. Both Mr. Martin Scheve and Mr. Anthony Adduci were among the many DOE personnel who contributed to the success of the project.

Lawrence Berkeley Laboratory (LBL) and Lawrence Livermore Laboratory (LLL) provided direct support and assisted in data collection and reduction. Moreover, LLL undertook and successfully completed a comprehensive environmental baseline study of the entire Imperial Valley. Mr. Robert Fulton of LBL, Mr. Roland Quong and Mr. Paul Phelps, both of LLL, were especially helpful in meeting the objectives and goals of this project.

The U.S. Bureau of Mines shared the data it collected regarding metallurgy and mineral recovery at its side stream facility at the site. Mr. Don Bauer and Mr. Frank McCawley were most helpful in these efforts.

Mr. Frank Enos, Mr. Fred Delamarter, and many other Westec employees made significant contributions to the successful operation of the facilities at the site.

Imperial Magma/New Albion Resource Company (NARCO) provided the hot brines to the facility as well as injection of the spent brines. Mr. Thomas Hinrichs and Mr. John Featherstone of Magma and Mr. Jim Nugent and D. K. Mulliner of NARCO played key roles in assuring compatible resource - facility operations.

The Ben Holt Company accomplished the majority of the architect and engineering tasks for this project. Mr. Ben Holt and Mr. Fred Torn were among those who contributed to the success of the project.

Mr. Ted Fick, Mr. Fred Schoepflin and others of Bechtel National Inc. contributed to the test program definition and data analysis. Both Bechtel National and Ben Holt Companies also contributed to the feasibility and risk study.

Scott Construction Company, C. F. Braun and Southwest Chemical Corporation all provided major sub-contract services in an effective manner.

The Imperial Irrigation District provided water and power to the GLEF while its staff offered encouragement and advice.

Over the years, the representatives of Imperial County government as well as the County Board of Supervisors offered encouragement, advice and guidance.

The individuals involved from San Diego Gas & Electric in the preparation of the final report were:

G. Anastas+
H. K. Bishop
C. H. Haas
W. H. Hanenburg+
G. J. Hoaglin+
W. O. Jacobson+
J. P. Kozic
D. G. Newell
L. G. VanWagenen+

Space does not permit the identification of all the other organizations and individuals that assisted in the successful planning, construction and operation of the GLEF. We have mentioned only a few here. A project of this size requires the cooperation, support and encouragement of many organizations and individuals. To all those that contributed to the cooperative effort which was the GLEF, thank you.

Note: + identifies the team that accomplished the final editing, coordination, layout, etc. that molded the Final Report of the Geothermal Loop Experimental Facility.

1.0 INTRODUCTION

This section presents an overview of the Geothermal Loop Experimental Facility (GLEF) Project. An aerial photograph of the site and the facility is shown in Figure 1-1.

1.1 SITE AND RESERVOIR DESCRIPTION

The GLEF is located at the Niland (or Salton Sea) Known Geothermal Resource Area (KGRA) on the southern shore of the Salton Sea near the town of Niland in southeastern California (Figure 1-2). The site location was selected following the successful exploration, drilling and well flow testing by Magma Power Company and San Diego Gas & Electric's (SDG&E) subsidiary, New Albion Resources Company (NARCO). Results of these early tests are detailed in Section 3.0.

Imperial Magma, a subsidiary of Magma Power Company, and NARCO jointly supplied geothermal fluid (brine) to the facility. The source of brine was from two of the exploratory wells, Magmamax No. 1 and Woolsey No. 1 (Figure 1-3). These are located near the test site and are thought to be near the center of the geothermal anomaly. The brine was flowed through the plant and then injected into the reservoir approximately one mile away through one of two exploratory wells used for injection, Magmamax No. 2 or No. 3.

1.2 PROJECT OBJECTIVES

The primary objective of the GLEF was two-fold: First and foremost: to determine the technical and economic feasibility of generating electricity from high salinity brines and second, to further establish the capacity and characteristics of the Niland Known Geothermal Resource Area. Originally these objectives were to be met by the design (See Section 4.1), construction, and start-up (See Section 5.1), and a 15 month operation of the facility. The approach was essentially to operate the facility as a pilot plant. This approach allowed operation and maintenance activities to mature after an initial period of learning, debugging, modifications and optimizations typical of pilot plant operations.

This operational concept was subsequently modified in order to obtain additional design information. Long term pilot plant type of operation was to be deferred until after a series of tests (See Section 7.0) were accomplished. These tests were directed at obtaining further data in areas where significant design uncertainty existed. Bechtel Corporation defined the areas of plant design uncertainty and developed a test plan to obtain further data in these areas. Supporting objectives were established and reviewed at regular intervals. As a result of these reviews, changes to the supporting objectives evolved. The Bechtel Holt feasibility study (See Section 9.1) resulted in many changes.

Figure 1-1 Geothermal Loop Experimental Facility in Niland, California

Figure 1-2 Geothermal Loop Experimental Facility (GLEF) Site Location

Figure 1-3 SDG&E Geothermal Pilot Plant Plot Plan

The study was authorized after operating and test data indicated unexpected results. The study used these results to evaluate the process selection, identify remaining areas of major uncertainty and recommend tests or activities to reduce the uncertainties. Based on this study, the facility and process was modified and further operation and testing accomplished.

Although these effects related directly to the conditions at this resource and site, many of the results may have applications at other geothermal resources. Materials, hardware and equipment that can withstand the high temperature, high salinity brines at this site should be able to withstand more moderate conditions. However, these materials, hardware and equipment may not be optimum for other applications.

1.3 PARTICIPATION AND FUNDING

The major GLEF costs were shared jointly by San Diego Gas & Electric and the U. S. Department of Energy (DOE), formerly the U. S. Energy Research and Development Administration (ERDA).

In addition to sharing the funding necessary for the GLEF operations, DOE made available the support of two national laboratories. In particular, the Lawrence Livermore Laboratory installed two side stream brine test facilities on site and provided direct technical support of the GLEF. Lawrence Berkeley Laboratory supported data collection and analysis activities. In addition, the U. S. Bureau of Mines provided additional support by establishing a side stream materials test facility at the site to identify the most suitable materials for geothermal power plant operation. The facility was later adapted to evaluate brine mineral recovery potential.

Reservoir related costs were primarily provided by Imperial Magma and New Albion Resource Co. (NARCO). This included a side stream facility to evaluate brine effluent treatment processes.

1.4 EVOLUTION OF PLANT DESIGNS AND OPERATING MODES

In order to enable the reader to better understand changes and modifications, this section briefly traces the history of the GLEF from initial well flowing to project termination. Figure 1-4 depicts the evolution of plant designs, construction and operating mode.

In 1972, the first well flow tests were conducted by NARCO and Magma Power to determine reservoir characteristics such as mass flow, temperature, stability and mineral content of the geothermal brine from the exploration wells. The results of these tests were encouraging. Brine temperatures

Figure 1-4 GLEF History

were relatively hot, and salinity was less than previous experience. Results were sufficient to justify further testing and process design to determine an appropriate energy conversion cycle for a power plant. Both the flash cycle and binary cycle were considered. In the binary cycle, geothermal heat is transferred from hot brine to a secondary working fluid by means of heat exchangers. The heated secondary fluid expands to drive a turbine-generator. The flash cycle was rejected because the high measured non-condensable gas content of the brines seriously reduced the cycle efficiency. The reduced salinity was expected to result in reduced scaling characteristics. For these reasons the binary cycle was selected for the initial design and field testing.

In 1973, a series of field test were conducted to support the design of the binary conversion cycle. Unfortunately, a rapid decline in heat exchanger performance resulting from scaling demonstrated a need to reevaluate the cycle design. A flash/binary process (See Section 4.1) was chosen as the basis for facility design modifications and additional field testing. Design modifications were to use as much of the original design as possible in order to minimize cost.

In March of 1974, SDG&E resumed field testing at Niland using reduced size models of the new flash/binary design. The 1974 test program confirmed the decision to modify the design, construction and operation of the GLEF in a four-stage, flash/binary cycle configuration.

In May of 1975, the design was completed and construction of the GLEF began. Start-up operations were initiated and in June, 1976, the facility was dedicated.

In the fall of 1976 while debugging and initial operation was being accomplished, a test program was developed to provide additional basic information necessary for the design of a commercial flash/binary geothermal plant. The primary objective of the program was to develop binary heat exchanger heat transfer design data under a variety of conditions.

Several tests from the 1976-77 test program (See Section 7.0) were attempted during this time period. Unexpected operational problems and data primarily related to heavy scaling in the brine system, process oscillations, supply problems with one of the wells (Woolsey No. 1), low noncondensable gas content, led to many aborted tests. Testing and operational data, however, was collected and many problems resolved. Analysis and review indicated a major reevaluation of the project was required.

By the fall of 1977, a major reexamination of the cycle and the test program was initiated. The Bechtel/Holt

feasibility study was initiated to reconsider the energy conversion process and to recommend further activities, if required. The study was completed in early 1978, concluding that a two-stage, flash cycle process as the most appropriate cycle for the commercial development at the Niland KGRA. Modification of only the brine system at the GLEF was recommended in conjunction with further operation and testing. Consequently, in April, 1978, the GLEF shutdown and the brine portion of the plant was converted to a double-flash system (See Section 4.2). The GLEF began operation in the two-stage flash cycle configuration in July, 1978. During the spring of 1979, the GLEF was shutdown to install a brine effluent treatment system (See Section 4.3). During the summer of 1979, installation was completed and operation resumed (See Section 5.3). In September 1979, the operation was terminated. During this period of two stage flash operation, a test plan was pursued which included the testing of an effluent brine treatment system (clarifier/filter) (See Section 8.0). The generally successful operation of the clarifier/filter was the last major testing program conducted at the GLEF site, however, side stream testing and other activities continued into 1980.

Many documents and reports were produced as a result of the GLEF project and are listed in Appendix E. Other reports were produced by other participants and are separately documented.

2.0 EXECUTIVE SUMMARY AND CONCLUSIONS

The GLEF project produced a large amount of information. The information was not always what was expected, and required a flexible approach to handle these developments. Process design began with a binary cycle which was modified into a flash/binary cycle and eventually converted into a dual flash cycle with brine effluent treatment. Construction activities were required to quickly adapt available equipment, not specifically designed for geothermal applications, to site conditions. Operational plans changed from a simple long term pilot plant approach into an optimistic test plan to develop additional detailed process design data from the facility, but was finally limited to obtaining data to reduce critical uncertainties and risk areas. Each of the basic phases (design, construction and operation) of the project for each process design (binary, four stage flash/binary, two stage flash, and the addition of a reactor clarifier media filter system) will be addressed separately in this discussion.

2.1 BINARY PROCESS

2.1.1 DESIGN

In order to expedite the development of these geothermal resources, the original GLEF process design (binary process) was prepared based on short term well flow test data, and laboratory analysis of brines. Subsequent field testing of a scale model of this process design showed that it would encounter heavy scaling after only a few days of operation.

Several factors were concluded to have contributed to this original process design failure. These factors included: the short term well flow tests may not indicate longer term trends, standard rather than field laboratory analysis may not reveal scaling and precipitation reactions, the transport and handling of the brine samples may have resulted in contamination, and the instrumentation which is not specifically designed for geothermal wells or brine conditions may lead to additional errors.

2.2 FLASH/BINARY PROCESS

2.2.1 DESIGN

A four-stage flash/binary cycle was selected for the GLEF process design, as constructed. This design was based on well flow and field test data. Cycle efficiency, when compared to flash, and operability, when compared to binary, were the significant selection criteria. Subsequent operation of the plant in this configuration showed significant differences between design and actual conditions. The

significant differences included reduced noncondensable gas content of produced brine, heavy brine system scaling with related equipment and instrumentation problems, limited areas of erosion/corrosion, reduced geothermal steam fouling of heat exchangers, and brine effluent injection well difficulties.

Some differences between pilot plant operation and small sized field tests or short term well flow tests are to be expected and in fact is the reason for the construction of a pilot plant rather than a full sized power plant, several conclusions can be reached as to the probable causes of the observed differences. Causes of the less than expected noncondensable gas content may be changes in production well brine chemistry with time, unrepresentative fluids at less than full well flow, or measurement errors.

Brine scaling appears to be a complex dynamic phenomenon, difficult to simulate on reduced size field testing. Full parameterization of this phenomenon has not been accomplished, but residence time and brine flow configuration appear to be significant parameters in addition to temperature, pressure and brine composition.

Severe corrosion had been observed at the Niland KGRA by others. Field testing identified brine oxygen and external corrosion as the primary causes of observed corrosion. GLEF process design therefore eliminated open tanks (direct exposure to air) and improved protection from external corrosion. The observed limited areas of erosion/corrosion, in the GLEF's internal brine system, indicates that oxygenation was somewhat more systematic than expected (priming of production wells with fresh water, air in leakage, and exposure during maintenance) but probably not unmanageable.

Only minor fouling was observed at the GLEF whereas some heat exchanger fouling was observed during field testing. This was attributed to field test upset conditions. Process design changes appear to have contributed to the apparently reduced fouling observed at the GLEF.

Injection of effluent brines was accomplished rather easily during field testing. Short term well flow testing also did not indicate any injection difficulties. However, extended operation at full flow and/or core flushing tests are apparently required to properly evaluate injectivity of effluent brines.

2.2.2 CONSTRUCTION

After the required permits were obtained, original GLEF construction required approximately nine months. It should be noted that long lead items had been previously ordered. This activity did not result in major difficulties. However, typical of any major construction activity, the activity did not proceed without any difficulty. These difficulties included poor soil conditions in conjunction with a high water table, insufficient local heavy construction labor force and field modifications of available equipment. However, none of these factors were serious impediments to construction. It was concluded that construction of a geothermal facility in this area is feasible.

2.2.3 OPERATION

The original plan for the GLEF was to operate as a baseload pilot plant for 15 months, in order to evaluate technical performance, reliability and cost. This was subsequently modified to a test program to gather detailed design data, prior to baseload operation.

Acquisition of the detailed design data was generally not achieved. The three primary causes of this deficiency appear to be: 1) the early termination of the test program, 2) operational problems primarily associated with brine scaling and 3) an inability of the installed process instrumentation to meet the accuracy required under actual operating conditions.

Operation and testing in this configuration did result in several important conclusions:

- o Relatively clean flashed steam can be produced from the saline brines using gravity separators and scrubbers over a wide range of conditions.
- o Scale and corrosion of flashed steam is nominal.
- o Process is inherently stable, even with large inlet brine oscillations.
- o Scale deposition occurs throughout the process, but is heaviest at the lower temperature and pressure stages and lines.
- o Noncondensable gases removed amounted to a few tenths of a percent by weight of brine.
- o Availability factors of at least 60% can be achieved.
- o Installed instrumentation and controls were adequate for a process control but inadequate for accurate data collection.

- o Available equipment, as modified, functioned in the environment, but improved reliability was desirable for a commercial plant.

2.3 TWO STAGE FLASH PROCESS

2.3.1 DESIGN

Design modification for a two stage flash cycle with a provision for effluent treatment was based upon GLEF operating and test data and a broad feasibility and risk evaluation. Subsequent facility modification and operation identified several differences between design and actual conditions. Significant differences included: increased scaling and oxygenation of effluent brines, and increased TDS in second stage steam flow. Oxygenation factors similar to those observed during four-stage flash/binary operation appear to be present in the brine effluent treatment system. Reduced steam quality appears to be related to marginal separator/scrubber design resulting from the use of existing equipment.

2.3.2 CONSTRUCTION

Extensive field fitting was required for this facility modification. Difficulties included insufficient local construction labor force, distance from ready sources of supply and reduced productivity during summertime conditions. Again, none of these factors were serious impediments to construction.

2.3.3. OPERATION

Operation in the two stage flash configuration was limited to testing of critical areas of uncertainty, primarily associated with brine handling. A majority of the planned testing was accomplished prior to project termination.

Important conclusions can be summarized as follows:

- o Scale rates remain difficult to predict, but increase in lower temperature portions of the process.
- o Several scale removal techniques were successfully demonstrated.
- o Improved control of inlet brine oscillations is required and appears to be feasible.
- o Acceptable capacity factors appear to be feasible with added flash trains.

- o Instrumentation techniques to measure brine pressure and temperature were successfully demonstrated and successful flow instrumentation appears to be feasible.
- o Initial brine system mild steel corrosion data appears to be variable, and related to oxygenation.

2.4 REACTOR CLARIFIER/MEDIA FILTER

2.4.1 DESIGN

The reactor clarifier/media filter process design used to treat the effluent brines prior to injection was based upon preliminary analysis, laboratory test data, and pilot scale field tests by Imperial Magma in conjunction with Envirotech. Short term operation indicates several areas where performance was not as expected. The thickener served more as a sludge holding tank than a true thickener. The settling rates and filter performance were also somewhat different than expected. Preliminary conclusion was that total exclusion of the air was not accomplished and produced oxidation reactions in the brine. Instrumentation and control problems were also present. However, none of these problems appear to be insurmountable.

Short term results were generally promising, but inconclusive. Injectivity of effluent brines appears to have been adversely impacted by oxidation reactions in the brine. The short operational time also precluded confirmation of injectivity. Correction of observed problems and an extended operation would be required in order to confirm the process.

2.4.2 CONSTRUCTION

Addition of the clarifier/filter system again provided construction difficulties similar to previous experience. A large quantity of fill was required to avoid high water table soil conditions. Field adaption of available equipment was also required. Again, none of these factors were serious impediments to construction.

2.4.3 OPERATION

Operation of clarifier/filter system was limited to less than 1000 hours, prior to project termination. Important conclusions are summarized as follows:

- o Supersaturation of silica in effluent brines can be quickly removed by a reactor/clarifier.
- o Most of the resulting suspended solids can be removed by settling/filtering.

- o Oxygen must be carefully excluded in order to prevent further reaction and generation of suspended solids.
- o Solid waste, predominantly silica, produced from the filter press is readily transportable.
- o Process is relatively stable.
- o Less than 1000 hours of operation was insufficient to confirm injectivity of effluent, but appears feasible if oxygen can be excluded.

2.5 MISCELLANEOUS ACTIVITIES

Lawrence Livermore Laboratories, the U. S. Bureau of Mines, and Magma operated side stream facilities in conjunction with this project. Basic research on brine reactions, chemistry and corrosion was accomplished. Research on mineral recovery and the application of the reactor clarifier concept to other portions of the process continued beyond the main facility termination. Important conclusions, to date, with respect to these other activities are as follows:

- o Heavy brine scaling is primarily a result of the precipitation of colloidal silica particles adhering to solid surfaces.
- o Produced brine is a reducing agent, lacking in available oxygen. Without oxygen, the heavy saline brines are not expected to be excessively corrosive to mild steel.
- o Alternate materials of construction can also be used. (See Sections 8.4, 8.5 and 9.3).
- o Alternate methods of reducing or controlling scale are feasible. (See Sections 8.1, 8.3, 8.15).
- o An economical method to remove H_2S from the noncondensable gas stream was identified and tested (See Section 8.8) and an alternate method tested (See Section 9.5).
- o Preliminary testing of Salton Sea processing for injection showed promising results. (See Section 8.11).
- o Design data developed for an effluent treatment system appears to be feasible. (See Section 8.10).

- o Reservoir injectivity and production evaluations were accomplished and appears to be capable of supporting commercial power production. (See Section 8.13, 3.2, 3.3).
- o No induced subsidence was detected. (See Section 9.4).
- o Acceptable quality steam can be produced (See Section 7.4) with nominal amounts of noncondensable (See Section 9.7).

2.6 RECOMMENDATIONS

Although significant risks remain, commercial production of electric power from Niland brines on a commercial basis appears to be economically and technically feasible. The undertaking of this commercial task by Magma Power is planned. Specific recommendations are included in each section, where appropriate. Other general design recommendations are as follows:

- o Provide an adequate space and design flexibility for the unexpected. A geothermal reservoir, to some extent, will forever remain uncertain.
- o Process design should provide acceptable performance over a range of expected conditions, rather than a most likely set of conditions.
- o Streamlining the brine handling portion of the process should produce multiple benefits of reduced maintenance, reduced oxygenation potential and improved reliability.
- o Provide maintenance access to remove scale throughout the brine handling system as no online system appeared to be 100% effective.
- o Although available equipment and mild steel appear to be generally acceptable, redundancy or special materials of construction is recommended in critical areas.
- o Provide for protection of critical components during transients and plant upsets.

General construction recommendations are as follows:

- o Because geothermal sites generally do not occur close to major urban centers, construction planning should include adequate transportation, on site storage, spares and other provisions typical of construction outside of major metropolitan areas.

- o In the Imperial Valley, provision for soil conditions and reduced productivity during summertime conditions is recommended.

General operation and maintenance recommendations are as follows:

- o A close working relationship between plant and field operations is essential.
- o Since a geothermal power plant resembles a chemical process plant in many respects, chemical laboratory data should provide important inputs for process control.
- o Because absolute solutions are not yet and may never be available for some operational problems, such as scaling, periodic reviews and evaluations of alternative techniques is recommended.

Further development and testing is recommended especially in the following areas:

- o On line scale control and removal brine.
- o Brine mineral recovery.
- o Brine flow instrumentation, controls and pumps.

3.0 EARLY WELL FLOW AND FIELD TESTING

Significant exploration activities of the Salton Sea (or Niland) KGRA had been accomplished prior to Magma/NARCO or SDG&E activities. Early (1920's) efforts to produce power were abandoned primarily because of the availability of inexpensive alternatives.

Significant work was done during the 1960's by Morton Salt Company and a group consisting of Southern California Edison, Southern Pacific Land Company and Phillips Petroleum. These efforts attempted to combine mineral and salt recovery from the brines along with power production. Efforts were again hampered or unsuccessful because of brine handling problems and availability of lower cost alternatives. These previous activities generally obtained brines from depths in excess of 4,000 feet with temperatures of approximately 600°F (315°C) and a total dissolved solids (TDS) content of approximately 300,000 parts per million (ppm).

Other prior activities in the area involved the production of carbon dioxide (CO₂). Shallow wells were drilled in the northeast section² of the KGRA which commercially produced large amounts of CO₂. Flooding by the rising Salton Sea and other economic problems eventually caused cessation of this commercial CO₂ production.

Magma/NARCO exploration activities generally limited the depth of the wells to less than 4,000 feet. This was done with the expectation that temperatures might be somewhat reduced, but salinity and brine handling difficulties were expected to be reduced significantly. In addition, selection of the specific exploration area benefited from prior exploration. Some additional amount of noncondensable gases (carbon dioxide) was also viewed as possible at the shallower depths because of the proximity to the previously produced CO₂ field.

3.1 WELL FLOW TESTS

In April, 1972, Magma/NARCO began flowing the first exploratory geothermal wells drilled in this specific area and at the shallower depths. One production well was flowed at the Niland site for about 10 days to obtain preliminary data about the fluid characteristics from the reservoir. After priming, the well successfully flowed without pumping. Brine temperature and pressure at the production wellhead averaged 375°F (190°C) and 150 psig. During this flow test, the geothermal brines which were produced were injected back into the reservoir through a second exploratory 2400 foot deep well located about 1/4 mile away.

The results of the flow test indicated the average production of the well was, on the average, 400,000 lb/hr total mass flow. Measurement at the wellhead showed that this was made up of 324,000 lb/hr of liquid, 64,000 lb/hr of steam, and 12,000 lb/hr of noncondensable gases, or approximately 81% liquid and dissolved solids, 16% steam, and 3% by weight of noncondensable gases. During the test period the wellhead temperature and pressure remained stable at 375°F (190°C) and 150 psig. Chemical analysis indicated that the total dissolved solids in the well fluids averaged 225,000 ppm consisting primarily of sodium, calcium and potassium salts. The high mass flow rates and the indicated bottom-hole temperature of 510°F (266°C) at a depth of only 2250 feet. were most encouraging.

Based on these tests and the data generated, SDG&E concluded that further development was justified. In order to expedite development, SDG&E concurrently proceeded with a preliminary design of a pilot plant (GLEF), and field testing to obtain further data on critical portions of the process.

Preliminary engineering considered a direct steam-turbine cycle similar to that in operation at the neighboring Cerro Prieto geothermal field in Mexico. This cycle was rejected because of the relatively high volume of noncondensable gases which seriously reduced the cycle efficiency. Preliminary engineering resulted in the selection of a modified binary cycle which would use vapor and liquid brine heat exchangers to transfer the geothermal heat energy to a binary or working fluid such as isobutane.

3.2 FIELD TESTS

Concurrent with the preliminary engineering and the difficulty associated with predicting the behavior of these brines from laboratory tests, field tests were scheduled. These field tests were carefully designed to simulate the phase separation and heat transfer conditions which would exist in the full-scale GLEF that was being engineered. The heat exchangers and other equipment used in these field tests were 1/20th-scale versions of the proposed facility equipment. This series of field tests was initiated in April, 1973, with the primary purpose to determine whether brine and vapor heat exchangers could be operated on brines from the Niland wells for a reasonable period of time without excessive fouling of the heat transfer surfaces.

3.2.1 1973 FIELD TESTS

For the 1973 field test program, production of geothermal fluids from the well was held to a test flow of 20,000 lb/hr and brine, steam, and noncondensable gases entered the separator at 150 psig. Steam and noncondensable gases exited at the top of the separator and passed through the shell side of the steam heat exchanger. Brine, leaving

the bottom of the separator, flowed through the tube side of the brine heat exchanger. The temperature of both the steam and the brine was approximately 375°F (190°C). Distilled water was used for the heat-exchanger binary fluid (in place of isobutane) in order to simplify the test procedure. The dissolved solids in the geothermal brine flowing through the brine heat exchanger ranged from 200,000 to 245,000 ppm. Dissolved solids in the steam at the exit of the test separator were 40,000 to 80,000 ppm. Both the steam heat exchanger and brine heat exchanger heat-transfer performance declined to unacceptable levels in about 100 hours of operation.

Inspection of the brine heat exchanger tubes and header, which were exposed to the geothermal brine for only about 100 hours, showed a scale build-up which averaged 0.060 inches thick. Amorphous deposits near the tube end were considerably thicker. The major constituents of these scale deposits within the brine heat exchanger were silica (SiO_2 , 38%), iron sulfide (FeS , 23%), and lead sulfide (PbS , 11%). Inspection of a steam heat exchanger tube exposed to the geothermal steam for about 100 hours showed a layer of scale approximately .045 inches thick. The heavy scaling of the steam heat exchangers was attributed to the high carry-over of brine the was concluded to be a result of an under-sized separator design and a lack of a mist eliminator or scrubber downstream of the separator.

Scaling within pipelines which handled brine was also observed. During the 1973 tests, pipe sections were removed from the brine line after various exposure times in order that observations could be made of the pipe. A maximum of a one inch scale build-up was observed in an injection pipe spool removed after six months of intermittent brine handling service. The brine process pipe was above ground and was not insulated to reduce heat loss and the brine was exposed to air in the injection pump sump prior to pumping back into the reservoir.

Neither the mild carbon steel process piping nor the titanium heat exchanger tubing showed signs of corrosion during or after these tests. These findings were determined by metalographic inspection of the materials and by chemical analysis of the scale.

Two methods of cleaning scale from heat exchanger tubes worked successfully but were costly. Hydrojetting with high-pressure water and chemical cleaning with a caustic or acid solution was used to remove scale. Caustic solution cleaning proved to be the most effective and fastest method. The hydrojetting method was estimated to be twice as costly as the chemical cleaning, primarily due to the high labor cost. However, even chemical cleaning is considered unacceptable if it has to be done for heat exchanger surface every 100 hours.

These 1973 field tests identified several areas where design modifications were required before a process could be designed which would effectively extract heat from the Niland geothermal fluids. It was demonstrated that separated steam heat exchange would require clean steam obtained by improved separator design and steam scrubbing downstream of the separator. Liquid brine heat exchange appeared to present a much more difficult problem and a new process design was concluded to be required. To extract brine heat that would otherwise be lost by bypassing the brine around the heat exchange process equipment, a multi-stage brine flash/binary system was designed to generate additional quantities of steam and thereby extract additional heat from the fluid stream. In addition, piping within the facility was to be insulated and exposure to air prevented. This was expected to minimize scaling. This new system utilizing the multistage flash/binary process would essentially leave all of the fouling-forming products in the brine. The brine would be contained in large-diameter equipment and vessels where moderate scale deposition could be tolerated with only a minor loss of process efficiency.

3.2.2 1974 FIELD TESTS

In March, 1974, SDG&E resumed field test work at the Niland geothermal field using reduced size models of the new design. These tests were conducted for six months to evaluate the new flash/binary design. The brine and steam flow from the geothermal well was directed through separators, with the steam flowing through steam scrubbers and steam heat exchangers. Two stages of steam-flash were tested. The primary goal of the 1974 test program was to determine if the new separators and the scrubbers could clean the steam sufficiently to eliminate or minimize fouling problems experienced during the 1973 test program.

The flow diagram for the 1974 test is shown in Figure 3.2-1. The flow of geothermal fluid from the producing well was to be controlled at rates ranging from approximately 50,000 to 100,000 lb/hr at various times during the test program to map the separator performance. The geothermal fluids from the producing well entered the first-stage separator at 150 psig and 370°F (188°C) for this flow range. Approximately 5,000 to 12,000 lb/hr of steam flowed out of the first-stage separator to a scrubber where it was cleaned and then directed through the shell of the steam heat exchanger. The remaining brine flowed from the bottom of the first-stage separator to the second-stage separator which was operated at 50 psig. An average of 2300 to 6000 lb/hr of steam flowed from the top of the second-stage separator to the second scrubber, where it was cleaned, and then flowed through the tubes of the second stage heat exchanger. These tests were generally successful.

Figure 3.2-1 1974 Geothermal Field Test Production & Injection System Flow Diagram

The 1974 field tests at the Niland geothermal field demonstrated that the technology could be developed to handle the Niland brines for purposes of effective heat exchange. Heat exchanger fouling appeared to be acceptable. Scaling in the brine system was observed but was not as severe as previous tests. Temperature of effluent brines was maintained in a range between 150°F (65°C) and 180°F (82°C) by adding 10% irrigation water to cool the hot spent brine to prevent cavitation in the injection pump. At the start of the 1974 tests, the injected geothermal brine flow averaged 90,000 lbs/hr at an average temperature of 165°F (74°C). Initially the injection-pump discharge pressure required was nearly 400 psig, but after 16 hours of continuous pumping, the injection pressure dropped and brine flowed into the injection well by gravity. During the 6-month test program, injection by gravity flow could be maintained an average of six days before injection pressure gradually rose, requiring another short period of pumping. The flow varied between 60,000 and 120,000 lbs/hr.

Based upon the 1974 field testing program, SDG&E directed the Ben Holt Company of Pasadena to proceed with the engineering of a four-stage, flash/binary cycle for the GLEF. (See Section 4.2).

4.0 DESCRIPTION OF PLANT DESIGNS

As mentioned in Section 1.4 of this report, the GLEF experienced several major design changes from the original binary cycle design. These configurations are described in this section.

4.1 FOUR-STAGE, FLASH/BINARY DESIGN

The four stage, flash/binary process was selected for the GLEF as a result of the 1974 field test program and engineering studies. It was chosen to combine some of the features of both the flash and binary cycles. The system was designed on a pilot-scale.

A turbine generator was not included in the plant (GLEF), but provisions were made for future addition, if this proved to be economic. Space was also provided for other activities, such as H₂S treatment and component testing, if required. These provisions were viewed as secondary to the primary purpose of establishing the feasibility of the basic four stage flash/binary process.

Figure 4.1-1 shows the process schematic with an expansion valve simulating the turbine. Although the brines were flashed at four conditions of temperature and pressure, a total of five steam separators were used. Two first stage separators operated in parallel sharing the large first stage steam flow. Each of the first stage separators were designed to handle the mass flow from one producing well. The total brine flow from both first stage separators was directed to the second, third and fourth stage separators in series. Steam produced by the flashing brine then flowed through four steam scrubbers, (one for each stage). The scrubbed steam and first stage steam condensate was then directed through a series of heat exchangers. In this process all of the steam generated was condensed. In addition to the small amount of condensate used for inplant process purging, the condensed steam was then either recombined with the cooled brine and injected into the reservoir, if required for reservoir related considerations (See Section 6.0), or used as makeup water for the evaporative cooling provided. Evaporative cooling ponds rather than cooling towers, were chosen to minimize capital costs.

The binary fluid, designed to be isobutane, passed through each of the heat exchangers in series, leaving the first stage heat exchanger as a superheated fluid. It then passed through an expansion valve which simulated the pressure drop of a 10 MW turbine. The binary vapor was then condensed in shell and tube heat exchangers cooled with water from an open spray evaporative cooling pond. The liquid isobutane then flowed in a closed loop to an accumulator, which supplied the binary circulation pumps, thus completing the cycle.

Figure 4.1-1 GLEF Process Schematic Four Stage Flash/Binary Cycle

Figure 4.2-1 GLEF Two Stage Flash Binary Process Flow Diagram

The noncondensable gases which remained after the steam was condensed, were dispersed to the atmosphere through a 130 foot high vent stack. The stack was expected to disperse the small H_2S component of the noncondensable gases to acceptable ground-level concentrations.

The brine from the last stage steam separator was pumped to the reservoir through a single injection line leading to two injection wells located approximately one mile from the facility.

4.2 TWO STAGE, FLASH CYCLE DESIGN

Based on the recommendations of the Bechtel/Holt Feasibility Study (Ref. Section 9.1), the decision was made to modify only the brine portions of the GLEF to simulate a two-stage flash cycle. A process schematic is shown in Figure 4.2-1. This modification was accomplished to allow testing and operation of brine portion of the plant to reduce the major risks identified in the study. Steam handling was not felt to be a critical area of risk for a commercial power plant. Therefore, most existing piping in the binary and steam systems was left intact. Instead, only the liquid brine piping and flash vessel controls were modified so that two flash "trains" operating at flash cycle conditions were created; one for each of the two production wells. Brine "test sections" were also added to provide access for the investigation of alternative brine handling methods without shutdown of the facility. The flash train normally used with Woolsey No. 1 production well was designated as the "A" train. The other, normally used with production well Magmamax No. 1, was designated the "B" train. In addition, the two trains were interconnected upstream of the first stage flash vessel so that the supply wells could be interchanged. Provisions for adding a brine effluent treatment system at atmospheric pressure was included.

The binary system was to be used only as a means to condense the steam produced from the brine. A process schematic is shown in Figure 4.2-1. The GLEF was shutdown for this modification in April, 1978, and started up in the two-stage flash configuration in late July, 1978.

4.3 CLARIFIER/FILTER SYSTEM DESIGN

The Bechtel/Holt Feasibility Study (See Section 9.1) included an identification of the need for treatment of the effluent brine in the two-stage, flash cycle configuration. In February, 1978, NARCO/Magma and Lawrence Livermore Laboratory began conducting a separate series of tests of equipment to remove suspended solids efficiently from the brine prior to injection. One of the objectives was to overcome the relatively slow precipitation rate of super-saturated silica in solution in the brine. This dissolved

supersaturated silica precipitated slowly preventing complete removal of suspended solids forming materials from the brine. This incomplete removal would increase the probability of silica precipitating in the injection well or in the reservoir itself, causing potential reservoir damage.

The brine effluent treatment system selected for the GLEF was based on testing by Magma in cooperation with Envirotech Corporation. The system was based on a clarifier/filter process. This process is similar to that currently being used in water and sewage treatment industries. In order to verify the initial tests on a larger scale, partially based on a study by Completion Technology, Appendix A, and evaluate the impact of treated brines on full injection well performance, SDG&E, DOE, Magma, and NARCO decided in mid-1978 to build a treatment facility at the GLEF based on this process. Figure 4.3-1 shows the GLEF's two-stage, flash-cycle process schematic with the clarifier/filter system included. Figure 4.3-2 shows the clarifier/filter system process schematic by itself.

A reactor clarifier was used to accelerate the precipitation of silica through rapid mixing and seeding with previously precipitated silica particles. Figure 4.3-3 shows a cutaway view of the clarifier. This system decreases the effluent brine supersaturation with respect to silica and heavy metals and removes the precipitated materials to produce a liquid suitable for well injection.

Brine at 625,000 lbs/hr was pumped from an existing atmospheric flash tank, V-15, by two parallel clarifier feed pumps, P-16A & B. A flow control valve was manipulated by an existing level controller on V-15. This existing system maintained flow in much the same manner it had originally, consequently, flow to the clarifier did not alter operation of the existing plant.

The reactor clarifier, V-17, provided a residence time (20 minutes) for the formation and settling of solids. At 224°F (106°C) influent, 687 gpm recycle flow, 1250 gpm total flow, 204.3 lbs/hr suspended solids, 385 ppm silica, and a pH of 5.6 the reactor clarifier using 0.56 gpm/ft² upflow velocity and a settling rate of 2.1 gpm/ft² produced an effluent at 216°F (102°C), 93 ppm suspended solids, 193 ppm silica, at a pH of 5.2. This effluent flowed by gravity to a sand and anthracite media filter, V-18 (Figure 4.3-4), and further reduced the temperature to 209°F (98°C), suspended solids to 5 ppm, silica to 190 ppm, and the pH to 5.0. The effluent from the media filter flowed to the brine surge tank, V-19, where it was pumped by the injection pump, P-17, at a pressure up to approximately 500 psig to an injection well.

Figure 4.3-1 Two-Stage Flash-Cycle Process Schematic with Clarifier Filter

Figure 4.3-2 GLEF Clarifier/Filter Installation Process Flow Diagram

**RAKE & TURBINE
DRIVE MECHANISM**

**EFFLUENT
LAUNDER**

**RADIAL
PICK UP
LAUNDER**

**INNER
LAUNDER**

TURBINE

**REACTION
WELL**

**RECIRCULATION
DRUM**

**INLET
FEED**

**ROTATING
DRUM**

**RAKE
ARMS**

Figure 4.3-3 V-17 Reactor/Clarifier

Figure 4.3-4 V-18 SVG Sand Filter

Sludge flowed from the reactor clarifier after settling to the bottom in a cone shaped area below foundation level. The temperature was 200°F (93°C) and an underflow of solids of 6.5-20%. Approximately 3,710 lbs/hr of sludge flowed by gravity to a thickener, V-22 (Figure 4.3-5) where the sludge was concentrated to 10 percent solids by weight. The sludge from the thickener was pumped to a plate and frame filter press, F-1, (Figure 4.3-6) where a cake is produced at the rate of 257 lbs/hr (357 lbs/hr during V-20 drain). The filter press was operated approximately every three hours for the necessary length of time and automatically shutdown. The filter press was then manually opened and the cake, 71% solids by weight, dropped into transportable bins, V-21.

The effluent brine from the thickener, V-22, and the plate filter, F-1, both flowed into the backwash holding tank, V-20.

The media filter, V-18B, was to be backwashed once every 24 hours. To accomplish this without disrupting flow through the plant, three media filter compartments were provided so one could be washed once every eight hours. The remaining two carried the full flow for the approximate 20 minute backwash operation.

The backwash compartment V-18A, was filled in four hours by 80 gpm of brine effluent from the media filter. This metering was accomplished by a flow orifice/splitter box which is part of the media filter system, V-18. The backwash operation consisted of a seven minute drain, followed by an air blowdown, then a 5-1/2 minute backwash. The backwash fluid flowed by gravity from the backwash compartment, V-18A, up through the media filter compartment to be backwashed, V-18B, and then flowed by gravity into the backwash holding tank, V-20. A rising level in V-20 activated the return pump, P-19, which pumped the backwash brine containing approximately 1.14 weight percent suspended solids to the clarifier, V-17, influent line. This rate drains the holding tank in four hours. Consequently at this drain flow rate, the backwash cycle can be reduced to four hours, if required. Furthermore, the return pump, P-19, and associated piping sized for 160 gpm so the cycle time could be further reduced to two hours, if necessary, subject to maximum total flowrate of approximately 1,600 gpm into the reactor clarifier, V-17.

During the four hour drain period, 56.7 lbs/hr of suspended solids were added to the clarifier by the backwash brine to the 204.3 lbs/hr suspended or precipitating solids entering the clarifier in the influent brine. Consequently, during the four hour drain period, the cake produced contains 232 lbs/hr suspended solids, compared with 167 lbs/hr otherwise.

Figure 4.3-5 V-22 Thickener

Figure 4.3-6 Plate and Frame Filter Press

Of the 204.3 lbs/hr (or 261 lbs/hr during V-20 drain) suspended solids entering the clarifier, 27.3 lbs/hr (or 29.3 lbs/hr) leave in the effluent brine and 167 lbs/hr (or 232 lbs/hr) leave in the sludge. The majority of solids leaving in the clarifier effluent brine are removed in the media filter and subsequently backwashed to the holding tank, V-20, and then to the clarifier, V-17, during the drain period.

5.0 HISTORY OF PLANT CONSTRUCTION & START-UP ACTIVITIES

5.1 FOUR-STAGE, FLASH/BINARY CYCLE

Construction

As discussed in Section 1.4, the four-stage, flash/binary cycle was the first plant configuration at the Niland site. Ground was broken in May, 1975, and grading, excavation, and the construction of earth berms commenced. Earth berms were to form the spray ponds used for plant cooling. Twenty acres of the 40 acres purchased were set aside for the plant, cooling ponds, and potential additions.

The major features of the site were the settling pond, the cooling water spray/storage pond, the process area, where the flash and binary cycle plant equipment is located, and the paved access road (Figure 1-3). About 30,000 cubic yards of native soil and 2,000 cubic yards of imported crusher-run-base was required to form the ponds and process pad. Compaction in the berms and in the process area approximately was 88% (with 14% moisture) and 96%, respectively.

Ponds and process pad preparation was undertaken simultaneously. As the earth was excavated to form the ponds it was hauled and deposited in the process area. This activity continued until the 60,000 square foot process pad area was built up to the required elevation. It was expected that the excavation of the ponds would present some problems due to the high water table in this area of the Valley, but the soil preparation required was uncertain (drying required, pumping under loads, etc.). Actual conditions made moisture control and machinery movement difficult. Moisture in the soil averaged about 30% up to 18 inches below existing grade. Because of these conditions the finish grade of the process area pad elevation and the bottom elevations of the ponds was raised 1.5 feet from the design elevations after verification of sufficient supply and drainage of water. This decision resulted in a substantial cost savings.

Conventional earth moving equipment was utilized, however, the earth movers were limited to a capacity of 20 cubic yards. This size was marginal since the machine had to be pulled out of the mud on numerous occasions. Earth bridges, windrows and mats were required continuously during the work. Windrows allowed the soil to dry to the proper moisture content before compaction. The earth bridges and mats supported the 2 cubic yard backhoe which performed the excavation. It was necessary to handle the excavated soil three times, equivalent to moving 90,000 cubic yards, as a result of the wet soil conditions. In spite of the earth bridges, a D-8 Caterpillar tractor lost traction and it was necessary to move the soil with a much lighter D-4 unit.

As the ambient temperature climbed to the 90°F (32°C) to 100°F (38°C) range, construction activities were hampered by insufficient soil moisture. The high ambient temperature caused the moisture level to drop below the required 14% and water trucks were needed to add water for the proper moisture content and compaction.

Finish grading operations were performed with a blade for the level areas such as the process areas, road and undeveloped land within the site boundaries. A Grade-All was used on the sides of the containment berms for the ponds. The site preparation described above required 42 days. Six men and five machines were the maximum size crew in operation at any one time.

In June, 1975, the Scott Company set up operations at the GLEF site to begin the erection of the test loop and the brine production and injection pipelines. This phase of the construction required 9 months.

The first phase in the test facility construction was foundation installation. Approximately 800 cubic yards of concrete was poured for pump pits, vessel and heat exchanger foundations, pipe supports, transformer, switch house, and other miscellaneous pads.

Pits for the vertical centrifugal pumps were the most difficult part of the foundation pouring. The high water table forced the sub-contractor to use a special construction method. A water well rig was used to drill an oversized hole which was immediately lined with reinforced concrete pipe with a diameter substantially larger than the barrel of the pump. Then a prefabricated steel liner was centered in this pipe and concreted in place to serve as the normal pump can. The sole purpose of the outer concrete pipe was to reinforce and stabilize the surrounding earth such that the critical alignment of the pump could be performed. The deepest pump pit was 23 feet, of which approximately 16 feet was submerged in mud and water. A large crane was used to hold the concrete pipe at the proper vertical elevation while the concrete was poured. Four pump pits were constructed in this manner.

Following the completion of foundation work, the mechanical phase of construction was started with the installation of the separators, scrubbers and heat exchangers. Underground electric distribution from the switch house was installed in corrosion resistant (PVC) conduit since the soil had a high salt content. Because the plant was designed to handle a flammable binary fluid, isobutane, rigid conduit was required above grade in the main plant areas.

Once the vessels and heat exchangers were set, the process piping was installed. Mild carbon steel pipe, ASTM

A-53 and A-106, Grade B, was used. Much of the piping fabrication was performed in Scott Company's weld shop and the spools field-erected. Both the field welds and shop welds were inspected by random radiography with interpretation of the film to Section VIII of the ASME code. All secondary (isobutane) system welds were x-rayed and all vessels and heat exchangers conformed to Section VIII of the ASME code for unfired pressure vessels. The isobutane accumulator and piping system conformed to the applicable sections of the California Safety Orders. All structural steel and steel work conformed to the American Institute of Steel Construction for steel buildings and bridges. The electrical installation conformed with the National Electrical Code.

The construction methods for piping installed in the process area were standard for the construction industry. However, one rather unique method of installing piping was used for one mile of 10 inch and 14 inch pipe required in the spray pond. A helicopter service was employed to set this piping because the bottom of the pond would not support a two-ton capacity fork lift, which would have been used under normal circumstances. Also, the configuration of the berms due to steepness of grade would have required the use of a crane as well. The entire spray pond piping system was positioned in four hours using one helicopter and four men.

During the mechanical portion of construction, electrical conduit and cable installations were in progress. The millwright work, fireproofing, and instrument calibration were phased in during the latter stages of the mechanical work. Insulation and painting were the final phases of construction to be initiated. Removable insulation pads were employed on flanges and valves to facilitate the removal of equipment for inspection and maintenance.

In March, 1976, the construction of the facility was essentially completed. The total cost of engineering, equipment and construction was approximately \$4 million.

Start-Up

With the successful completion of the pressure tests, each system was turned over to SDG&E's start-up crew, under the direction of a start-up engineer, to begin system cleanout and equipment checks in placing each of the test loop systems in operation.

A start-up critical path chart (Figure 5.1-1) was formulated to aid the operators and various construction trades in start-up planning. The numbers displayed are only for task identification and are not necessarily sequential.

Figure 5.1–1. Four Stage, Flash Binary Start-up Schedule

Initial start-up operations actually began in December, 1975, when the settling pond was filled with irrigation water obtained from the Imperial Irrigation District. During this operation coagulant, Nalco 605, was added to the incoming water. The coagulant feed rate was adjusted to give a 5.0 ppm dose which reacted with particulates in the settling pond.

Following this start-up activity the electrical system was uneventfully energized and pump motors were inspected for proper rotation. Electrical protective devices were also checked and tested.

After the electrical system was energized and checked the cooling water system was placed into operation, beginning with the cooling water circulation pump (4160v, 900 hP, 21,000 gpm). During this operation, cooling water was circulated through the isobutane condensers and returned to the spray pond through the spray heads. The designed discharge pressure of the pump was approximately 45 psig. Sub-systems associated with the circulating water pump and spray pond were chlorine injection, pH control, chemical feed, and utility water supply. Each of these sub-systems were placed in service with minor instrument and feed rate adjustments. This water treatment process was similar to that used at the Imperial Irrigation District fossil fueled power plant in El Centro, California.

At this time the cooling water, water treatment, compressed air, utility water, and electrical systems were fully operational. Approximately 15 acre feet of cooling water was stored in the pond with a chlorine residual of about 0.4 ppm, and a pH of 7.6. This pH was optimum for the use of Nalco 7350 non chromate corrosion inhibitor.

The chemical cleaning system was filled with condensate to flush and clean out the chemical cleaned piping and controls. The chemical cleaning system was ultimately expected to remove scale from the separators, heat exchangers, and injection lines as required during the operation of the test loop. The chemical cleaning system was quite simple with the feed pump being the only critical piece of machinery. During start-up, however, this system was used to store about 25,000 gallons of pure water for cleanout, initial operation of the condensate system, and purge water system.

The condensate and purge water systems pumps were placed into operation with strainers in their suction lines to remove weld beads, sludge and dirt from the system's piping and vessels as the condensate was circulated. The purpose of the purge water system was to provide purging water to instrument lines, the injection pump seals and control valve packings. This purging prevented the intrusion

of geothermal brine and the deposition of mineral scale on critical parts. Two pumps were installed in this system; one for standard use in normal operation and a second on stand-by.

The binary system was charged with distilled water in lieu of isobutane, because of several factors; it reduced maintenance and operating costs, also allowed for safety of personnel during preliminary plant operation and orientation into a new technology.

The brine system was flushed, prior to the introduction of brine. One of the production wells was primed (fresh water pumped into wells to displace brine, remaining in the well bore until heated). Initial brine flow commenced in May, 1976, with formal dedication occurring in June, 1976.

5.2 TWO-STAGE, FLASH CYCLE

Construction

SDG&E Construction Department was used to accomplish these modifications. Mechanical, primarily piping, was the major trade involved. Since existing vessels and piping was used to the maximum extent possible, field rather than shop fabrication predominated.

Because of control problems observed during four-stage flash binary operation, below grade brine drain lines were specified. The previous overhead drain piping resulted in flashing prior to control valves. Covered trenches were installed to allow access to below grade piping.

Construction difficulties included the high water table and soil conditions previously mentioned and maintaining field weld quality control. Screens and shelters were used to prevent windblown dust or sand from contaminating field welds. Field welds were x-rayed upon completion. Because of field fits, and a rapid schedule, close interfacing between engineering was required and accomplished.

Start-Up

A sequence of start-up operations similar to the four-stage, flash/binary configuration was used. Very few difficulties were encountered during checkout, flushing or related activities.

Brine was introduced into the "A" train from Magmamax No. 1 in July 1978. Outside of minor adjustments, few difficulties were encountered.

5.3 CLARIFIER/FILTER SYSTEM

Construction

The only reasonable area available on site for the magnitude of this equipment (clarifier is 55 feet in diameter, gravity feeding a 26 foot diameter filter, with auxiliary thickener, filter press, surge tank, pumps, etc.), was also the lowest elevation on the GLEF site. Because of the previous problems discussed with soil conditions associated with a high water table (designed for two feet below grade), a large amount of fill material was brought in. Also, system design required extra reinforcement in the area of pipe supports and equipment foundations due to stringent seismic standards regarding system integrity.

Because the clarifier/filter system was added downstream of the GLEF plant process area strict coordination and scheduling with plant operating personnel was necessary to tie both systems together. This required a scheduled plant shutdown and system draining.

Start-up

Upon the completion of pressure tests and sign-off by the construction crew, each system was turned over to the SDG&E start-up crew, under the direction of a start-up supervisor, to begin system cleanout, instrument calibration, and equipment mechanical and electrical checkout.

A start-up critical path chart was established (Figure 5.3-1) and used to aid plant personnel and construction personnel in following the overall construction and start-up schedule. Start-up activities were broken down into four systems; Brine Injection System, Brine Clarification System, Brine Media Filter System, and Brine Sludge Removal and Filter Cake System.

The Brine Injection System was the first system checked out and prepared for normal operation by start-up personnel. The brine surge tank, V-19, was hydrostatically tested and all piping and valves were pressure tested successfully. The brine injection pump motor, P-17, was checked for proper rotation and vibration readings were taken on the pump and motor to aid the millwrights in their aligning the pump properly. Instrumentation calibration was difficult due to control valve difficulties. This system was designed for 1700 gpm maximum flow, however, control valves in this system were not designed for minimum flows of as low as 350 gpm or for swings in flow from 350-1700 gpm. To lower the pressure drop across the valves, new valve trims and orifices were installed. These modifications didn't eliminate the problem entirely but did bring the valves performance into a range that was tolerable and

Figure 5.3-1 Clarifier/Filter Installation and Start-Up Schedule

allowed normal operation with limitations. Other problems encountered dealt with purge water to the bearings of P-17. Several pressure regulators failed and needed replacing. After these problems were alleviated the system was given a final test run and satisfied design conditions.

The start-up crew then began start-up activities on the Brine Media Filter System. Prior to system sign off and turnover to start-up crew, construction personnel successfully completed at hydrostatic test of the backwash tank V-18A and media filters, V-18B, also the backwash holding tank, V-20. All piping, valves and related equipment were pressure tested satisfactorily. Start-up of this system was routine, with system flushing, establishment of electricity to equipment, calibration of instrumentation, and final checkout of the clarifier return pump, P-19 for proper motor rotation and general operation. Minor difficulties were encountered in the hydrostatic testing of mentioned vessels due to water source being over 1000 feet away. This required a large portable pump with sufficient head to pump this distance then up 15 feet to the manhole on top of each vessel. A large pump was not available hence, a much smaller pump was used and required several days to fill vessels.

The Brine Clarification System was the next system signed over to the start-up crew by construction. The reactor clarifier, V-17, was hydrostatically tested and system valves and piping were pressure tested. All equipment tested satisfactorily with the exception of two manual gate valves on the clarifier outlet which leaked through the packing glands. These packings were tightened and the leaks stopped and system start-up continued. Routine activities such as electrical hookup and instrumentation calibration were completed with only minor problems such as control tubing needing cleaning prior to installation due to environment of the area. (i.e. blowing sand, rain, and heat).

With the three mentioned systems ready for operation, (Brine Sludge Removal and Filter Cake System wasn't started up until a sludge blanket was established in the clarifier) a closed loop was established from the atmospheric flash tank, V-15, bypassing the clarifier, V-17, and the media filter, V-18 A & B, and flowed to the brine surge tank, V-19. From V-19, using the brine injection pump, P-17, flow continued back to V-15 via the brine injection line and an old discharge line from the original injection pump. This closed loop enabled start-up personnel to test all aspects of the clarifier/filter system under near normal operating conditions. Control valves were the points of interest during this run. All control valves were tested and were calibrated accordingly. This closed loop testing proved successful in allowing equipment and instrumentation to be fine tuned and aided in identifying potential problems. One point of concern was the discharge

control valves or level control valves downstream of the clarifier feed pumps P-16A & B. These valves were pinch valves and were incapable of handling the differential pressure across them. Start-up personnel had to manually manipulate these valves during normal operation and eventually had to throttle closed a manual gate valve downstream to reduce the differential pressure. Eventually these valves were replaced with ball type control valves.

On May 29, 1979 brine flow was introduced to the clarifier to begin establishing a sludge blanket which is a vital step in the removal of supersaturated silica from the brine. To do this the clarifier was filled with brine and through internal circulation with a mixing turbine a sludge blanket was formed. This operation required 10 days after which brine flow was re-established to the clarifier and normal operation commenced. During the filling of the clarifier with brine, sludge was trucked in from Magma's settling tanks at one of the injection wells to begin start-up of the Brine Sludge Removal and Filter Cake System. Sludge was pumped into the thickener vessel, V-22, from a truck and then pumped by the sludge pump, P-18, to the filter press, F-1. The filter press then pressed the sludge into a cake-like rectangle which was then dumped into a dump truck. Problems encountered with this system were mostly in the electronic equipment. Logic changes had to be made for complete process operation as well as rerouting of circuits. The suction hose of P-18 collapsed during operation and had to be replaced with one that was reinforced and capable of withstanding this type of operation under a vacuum.

Start-up personnel turned over clarifier/filter system equipment to GLEF and Magma operating personnel in July, 1979, at which point start-up activities were completed.

6.0 PLANT AND RESERVOIR OPERATIONS

6.1 OVERALL PLANT PERFORMANCE

6.1.1 FOUR-STAGE FLASH/BINARY CYCLE

Upon completion of the facility startup in 1976, on through April 1978, the GLEF operated in a four-stage flash/binary cycle configuration. A total of 7419 hours of operation were attained in this mode.

The GLEF experienced a number of operating problems that hindered the conduct of the 1976-1977 test program (See Section 7.0). These were primarily caused by scale formation in the areas of the plant exposed to liquid brine. Brine piping and vessels became clogged or restricted, shutoff and control valves became inoperable, pressure instrumentation taps scaled over, thermowells became coated with an insulating layer of scale, flowmeters became clogged, and scale formation on rotating hardware caused frequent injection pump failures. Other problems included control system oscillations, off design operating conditions as well as equipment and other difficulties typical of initial operation of a pilot plant.

A number of modifications and operating strategies were attempted during this period to solve these problems. Brine injection pump bearing materials were modified and purged with clean fluid (condensate). In addition, a spare pump was fabricated. A variety of scale removal techniques were attempted including chemicals, high pressure water blasting (Hydroblasting), high volume fluid flushing, mechanical scraping, pigging, brine treatment (acidification), magnetic fields (scale disintegration), mechanical shock, coatings, increasing equipment clearances, reducing flow obstructions, and replacement of failed equipment with more successful equipment or with designs successful in handling related problems an industrial application (slurry flows, scale, etc.). A control system stability analysis was accomplished and control sensors and control strategy modified. Selected control valves and instrumentation were replaced with equipment matched to the observed rather than design conditions. Instrumentation modifications included adding buffer areas or fluids, purging, replacement of sensors, frequent cleaning and calibration, and relocation of sensors.

Some of these attempts to solve the observed problems were complete failures (scale disintegrator and mechanical shock, for example). Others were partially successful in some applications but failed in others (for example purging in a small confined area was partially successful, but not in large areas). Other techniques were partially successful. The most promising techniques were

incorporated in the subsequent 1978-79 test plan which attempted to reduce the uncertainties associated with the observed problems and anticipated solutions (See Section 8.0).

As in any pilot plant operation, the operating solutions derived are not necessarily optimum. However, the solutions did allow the plant to operate in order to define operating conditions and problems and allow some optimization of techniques to handle these conditions and problems.

The success in slowly overcoming these operating problems during the four stage flash/binary configuration is shown in Figure 6.1-1. Average availability during the first six months of 1977 (after start-up operations complete), was less than 40%. The average availability during the final six full months of operation in this configuration prior to shut down for modifications in mid April, 1978, was approximately 60%.

6.1.2 TWO-STAGE FLASH

The GLEF operated in a two stage cycle configuration from July, 1978, through the termination of the project in September, 1979. About 5300 operating hours were accumulated in this mode. During the spring/summer of 1979, the facility was shutdown to add a clarifier/filter system.

A number of operating problems were experienced while operating in the two stage flash configuration. The primary problem was the increased amount of scale observed in the second stage and atmospheric flash vessels. Other difficulties included instrumentation unreliability, brine carry over in the steam, and miscellaneous difficulties associated with the initial operation of systems and equipment.

The 1978-1979 test program (See Section 8.0) addresses the performance of selected equipment and systems under these conditions. As observed in Figure 6.1-1, availability during the initial operation in the two stage flash configuration was significantly improved when compared to the initial four-stage flash binary operation (average of approximately 60% during the first six full months following the first modification). Initial operation after clarifier/filter system treatment was not long enough for direct comparison, but the availability does not appear to be significantly different from previous experience.

Because of the generally acceptable initial performance, progressive age of the facility, modifications, use of existing equipment and only partial simulation of the process, longer term operation in this configuration was not

- AVAILABILITY = NO. OF HOURS OF PLANT OPERATION/TOTAL NO. OF HOURS IN THE MONTH.
- PLANT SHUTDOWN FOR MAJOR OVERHAUL.
- △ PLANT SHUTDOWN FOR DISMANTLING.

Figure 6.1-1 Niland Geothermal Loop Experimental Facility
1976, 1977, 1978 & 1979 Availability by Months

expected to yield results comparable to the cost required in operating the facility. Operating and test data, although incomplete in some areas, was sufficient to allow Magma Power to pursue commercial size facilities at this resource.

6.2 PRODUCTION AND INJECTION WELLS

6.2.1 Production Wells

In March, 1976, Imperial Magma, began tests to gather baseline well data. These tests consisted of temperature, pressure, ultrasonic and caliper measurements.

Flow test apparatus were set up at Magmamax No. 3, one of the wells eventually used for brine injection. After the first temperature survey it was apparent the lowest 400 feet of the well was plugged and as a result the initial flow tests were aborted. (A typical diagram of a Geothermal production well is shown in Figure 6.2-1). High pressure nitrogen was used to prime Magmamax No. 3 and with the flow the deposition in the casing was freed successfully.

During September and October, 1976, various attempts to achieve steady production of brine from Woolsey No. 1 for GLEF operation were unsuccessful. Although well flow was started, it declined within a few hours to such a low value that GLEF operations could not be sustained.

It appeared that the flow decline was caused by a steel plug which had moved up in the Woolsey No. 1 well from a depth of 2375 feet (about 25 feet from well bottom) to about 1900 feet and blocked flow from the perforations.

The metal plug was a remnant of a Baker, Model M, Drillable Bridge Plug (Figure 6.2-2). This type of plug is used by well drillers when they wish to perform various types of work on oil or geothermal wells. In the case of Woolsey No. 1 the plug was used when Imperial Magma drilled the well deeper and installed 1000 feet of 7 5/8 inch well casing to the original 12 3/4 inch bore (Figure 6.2-3).

Imperial Magma remedied this problem by pushing the plug to the well bottom with a small drilling rig and set another plug down on top of the first to hold it at that depth in the well (Figure 6.2-4).

During this time Magmamax No. 1 was flowed intermittently with no difficulties for chemical data and a test run with combined condensate.

On November 24, 1976, operation resumed with the production of geothermal brine from Woolsey No. 1. Woolsey No. 1 produced approximately 298,000 lbs/hr at 120 psig at the wellhead. This was not sufficient flow to conduct flow

Figure 6.2-1 Geothermal Well

Figure 6.2-2 Baker, Model M, Drillable Bridge Plug

Figure 6.2-3 Woolsey No. 1 Well

Figure 6.2-4 Woolsey No. 1 Well

tests for one or two well conditions. Both the delivered flow and pressure were below the design values of 400,000 lbs/hr and 150 psig for the plant. Woolsey No. 1 was flowed, however, for two weeks to gather limited chemical, scale, and pertinent operating data.

The inadequacy of the Woolsey No. 1 production well to produce was discussed by SDG&E and Imperial Magma. It was decided in February, 1977, to deepen the well to approximately 3490 feet in an attempt to provide the 400,000 lbs/hr that was necessary. Magmamax No. 1 was brought on for GLEF operations until Woolsey could be remedied.

After the well had been deepened, GLEF operation was again attempted with Woolsey No. 1 as the production well and Magmamax No. 3 as the injection well. Over 15 attempts were made to flow Woolsey before steady flow could be achieved. However, a wellhead pressure of 200 psig and temperature of 400°F (204°C) indicated the well could be used for GLEF operation. During these operations, injection pressures increased as the Woolsey No. 1 flow increased. An attempt to inject into Magmamax No. 2 was aborted in mid February also due to a high backpressure on the well.

During April and May, 1977, Woolsey No. 1 was used as the primary production well injecting into Magmamax No. 3, however, one well baseline tests were still being hampered by high injection well back pressure. Woolsey No. 1 continued to be used until September, 1977, when two well operation adding Magmamax No. 1 was attempted with less than satisfactory results.

In October, 1977, a temperature survey was taken in Woolsey No. 1 indicating a variation in the temperature profile. A spinner survey in November, 1977, was run on Woolsey No. 1 and indicated a fluid loss at the 1,370 foot level caused by a hole in the casing. An attempt to repair the hole with a cement squeeze proved futile when another hole developed during a pressure test. A 6 5/8" tie back liner was hung from the 854 foot to the 1821 foot level to aid in blocking off the holes. The well casing on Woolsey No. 1 was also milled and scraped to remove the scale.

Magmamax No. 1 became the primary production well at this point due to problems encountered with Woolsey No. 1. The Magmamax No. 1 wellhead valve was removed and a caliper log indicated approximately 1/2" of scale for the first 900 feet. This scale was milled off and the casing was scraped. After the well was cleaned, 1 1/4" tubing was hung in the well to allow flowing pressure and temperature observations to be made.

Magmamax No. 2, normally a spare injection well, was flow tested for 350 hours at three different flow rates: a low flow of 400 GPM, a medium flow of 600 GPM, and a high flow of 900 GPM. At the high flow condition, the wellhead temperature and pressure was 407°F (208°C) and 280 psig. The well had every indication of being capable of producing at a much higher flowrate.

As previously mentioned Magmamax No. 1 became the primary production well until June, 1979, with little or no problems encountered.

Woolsey No. 1 was used as the production well to start the GLEF after completion of the installation of the clarifier/filter system in July, 1979. The pressure and temperature at the plant boundary were 150 psi and 320°F (160°C). The flow was approximately 400 GPM which was lower than expected. Possibly the reduced casing size of 6 5/8" or an obstruction at the 1900 foot level discovered during a temperature log caused the low flow.

The GLEF was operated on Magmamax No. 1 for the major part of June, 1979. Prior to June 13, the flow was 550 GPM with a plant boundary pressure of 250 psi. Several earthquakes took place June 12 and 13. On the evening of the 13th, the well cleaned itself of sand that had built-up in the well bottom. The pressure came up to 285 psi and the flow increased.

After a sludge blanket was established in the clarifier, operation on two well was established and continued until final plant shutdown in mid September, 1979.

6.2.2 INJECTION WELLS

Attempted injection into the Magmamax No. 3 (previously used for nearly all injection up to this point) was aborted after 200 hours of intermittent operations due to a high back pressure and low flowrates in February, 1977. The wellhead pressure was approximately 450 psig with a flowrate of 400 gpm. After notification of Imperial Magma, Magmamax No. 3 was isolated (to allow data gathering) and facility operation was attempted using Magmamax No. 2 for injection. Operation was immediately aborted due to high back pressure. Imperial Magma then applied approximately 800 psig to the wellhead to hydrofracture the formation using a separate pump. Facility operation was again attempted. Wellhead pressures of approximately 360 psig were observed with injection flowrates of approximately 500 gpm (less than one well design flowrate).

Magmamax No. 3 was purged with nitrogen. This operation consisted of vaporizing liquid nitrogen, at several thousand psig, injected through a tubing and a nozzle to the

bottom of the well. The rising bubbles of nitrogen displaced the fluid and reduced the hydrostatic pressure in the well, causing flow of formation brine into holding tanks. A significant amount of solids, apparently scale, was carried with the fluid to the holding tank (i.e., backflushing well). Attempted operation of the facility with Magmamax No. 3 did not show any significant improvements in injectivity, hence, the GLEF was shutdown pending further remedial actions. The loss of capability of Magmamax No. 3 well to receive spent brine from the GLEF caused continued efforts to be undertaken by Imperial Magma during March, 1977, to improve flow rates.

Several possible theories for the increased flow resistance at the injection well were proposed: (1) reaction of the Woolsey fluid with the existing fluid in the injection well, (2) solidification of materials in the injection well during the February shutdown, (3) residual scale from the GLEF cleaning which migrated to the injection well, which might have caused (4) plugging of the permeable zones of the reservoir near the well forcing the brine flow into other less permeable zones, (5) plugging of well slots, and (6) changes in the reservoir characteristics.

Because of the lack of complete injection data (temperatures, pressures and flow rates), no firm conclusions were drawn. However, during the hydrofracture and backflushing operations in February, a significant amount of solids were observed in the well casing which could have contributed to the increased flow resistance. Based on this observation remedial actions undertaken by Imperial Magma included (1) running a sawtooth bit to clean out the entire injection well; (2) pressure washing the perforations with a four cup pressure washer; (3) flushing the perforations with a 5% solution of caustic in fresh water; (4) running an injection test to 1600 gpm; (5) installation of strainers on the injection line with backflush provisions.

After cleaning, the initial operation of the injection well seemed satisfactory. Well head pressure was about 180 psig at a brine flow of about 340 gpm. This gradually increased to 225 psig at the same flow rate.

During start-up of the GLEF, the discharge brine was routed to a storage tank. A significant amount of residual solids from the GLEF clean-up was collected in the tanks. After the start-up, brine flow was directed through the strainers before it was injected into the well. Two strainers were installed so that when differential pressure across one strainer became too great, flow was switched to the second strainer and the first strainer back flushed. Initial operations of the strainer system seemed to be satisfactory. However, toward the end of April, 1977, flushing could not provide an acceptable reduction in the

pressure differential across the strainers. Repeated laborious handscraping of the strainers was necessary to remove the accumulated scale deposit.

Spinner surveys, used to determine the injection zones in the well, were run in March, May, and August, 1977. The surveys revealed that the injection zones had increased between March and May, and then decreased between May and August. The rework of the well in March accounted for the increase of injection zones. The decrease from May to August, was evidence for actual slot or sand face plugging either by scaling of particle embedment.

In June, 1977, the well was bailed which consisted of removing the sediment from the bottom of the well. Also in June, a section of tubing was installed from the surface to a depth of 2970 feet to determine the scaling rates downhole. After 47 days of injection (not continuously flowing), the scale on the tubing was 1/16 to 1/8 of an inch thick of varying hardness depending on the location. The scale on the tubing was found to be softer on the bottom slotted portions compared to the upper joints.

Instruments were installed in April, 1977, for recording pressures, temperatures, and flowrates. Also, in April strainers were installed at the wellhead to remove the large particles from the brine. The strainers improved brine injection, but increased the operations cost. The increase was due to the frequent cleaning of the strainers. Other methods for solid controls were being investigated to prevent injection well problems, since it appeared that suspended solids in the effluent brine substantially contributed to injection well problems.

Before shutdown in October, 1977, Magmamax No. 3 performed well at injection pressures varying between 350 and 375 psig. In December, Magmamax No. 3 was acidized to reduce a 475 psig wellhead pressure. Injection pressures declined to a moderate 280 to 300 psig, at flow rates of 400 to 600 gallons per minute. Although the injection pressure decreased after the acid job, the actual effects of the acid on the well and formation were now known.

In November, 1977, installation of a six settling tank system was completed by Imperial Magma adjacent to Magmamax No. 3. The tanks aided in removing suspended solids previously entering the injection well with only a 5°F brine temperature loss. Due to the buffering effect of the tanks, flow measurements from Magma's injection pump were extremely smooth and accurate at about 800 gallons per minute. Although the settling tanks were succeeding in reducing the saturation of silica in the brine being injected at the Magmamax No. 3 wellhead, it appeared that the system was only a partial solution to the settling and

scaling problems of injection. As sludge formed, desilters were briefly used but proved uneconomical due to the restricted size of particles removed. In late December the settling tank system was shut down in order to clean the build-up of sludge in the tanks, which ranged from 4 feet in the first tank to 18 inches in the fourth tank. There was no build-up in the sixth tank.

The strainers installed at Magmamax No. 3 had a tendency to collapse due to scaling. Since higher strength 8-5/8 inch by 24 foot steel strainers were installed and pressure drop monitored, no collapsing occurred.

The settling tanks appeared to be effective in reducing the suspended solids to approximately 100 ppm and the silica to close to saturation. About 1 1/4 tons/day of solids were being removed in the settling tanks. However, injection well plugging was still being indicated so in March, 1978, a pilot reactor clarifier was tested on a side stream from the atmospheric flash vessel. The objective of the test was to see if the clarifier could reduce the amount of suspended solids and dissolved silica in the brine prior to injection in the Magmamax No. 3 well.

The clarifier generally produced excellent results both reducing the quantity of suspended solids and reducing the concentration of silica remaining in solution at the injection well. Suspended solids were reduced from a range of 130 to 160 ppm in, to a range of 20 to 50 ppm out. Silica in solution was reduced from a super-saturated level of 300 ppm in, to a slightly sub-saturated level of 170 ppm out at 180°F (82°C). The effluent from the clarifier performed very satisfactorily when injected by Lawrence Livermore Laboratory through sandstone cores representative of the Niland reservoir. The clarifier also handled sludge concentrations for thickening and removal. The clarifier was not as effective on Magmamax No. 2 fluids as it had been on Magmamax No. 1 effluent, however, performance was still significantly more effective than that of the settling tanks.

In July, 1978, a high back pressure on Magmamax No. 3 brought about a change to using Magmamax No. 2 as the primary injection well. Very little back pressure was noted on Magmamax No. 2 until just before a plant shutdown after the first run on the two stage design, when the back pressure climbed to 40 psig. Part of this pressure build-up could have been due to a low injection flow allowing the well column fluid to heat up, creating a back pressure.

The settling tanks were being emptied of sludge which was being pumped from the pilot clarifier. A considerably larger amount of sludge was collected with the GLEF

in a two stage flash mode in comparison with the four stage flash. The shorter fluid resident time caused the precipitation of sludge to take place after fluid left the plant.

Magmamax No. 2 continued to be used as the primary injection well until July, 1979, at which time IW-5 was used to test the injectivity of the effluent fluid from the full scale clarifier/filter.

It was decided to drill a new injection well, IW-5, into a shallow zone below the caprock. The injection fluid was the brine from the new clarifier and mixed media filter. This fluid tested the shallow injection formation and the injectivity of the clarified brine.

The new injection well (IW-5) was drilled to 1500 feet in February 1979 with a slotted liner extending from 1100 to 1500 feet. The well was flow and injection tested in March, 1979, to determine the chemical composition of the brine prior to using the well for injection. The injection test proved the well was capable of accepting brine at maximum design output of the clarifier/filter. IW-5 was used as the injection well utility final plant shutdown in September, 1979.

7.0 1976-1977 GLEF TEST PROGRAM (Four-Stage, Flash/Binary Cycle Operation)

Introduction

In the fall of 1976, a test program (Ref. 7.19-1) was established to provide additional basic information necessary for the design, construction, and operation of a commercial flash/binary geothermal power plant. The test program addressed technical areas anticipated to be critical to the process based on early well and small scale field testing. The major objective of the program was to develop heat transfer data under a variety of conditions. Heat transfer was judged to be the major critical area because of brine carryover experienced in the past, the anticipated large noncondensable gas content, and the first geothermal application of a pilot plant size scrubber of this design. This test program contained detailed descriptions for 18 tasks addressing the anticipated critical areas.

Efforts to accomplish this test program were frustrated by a series of difficulties and eventually a process change. This resulted in only a small portion of these tests being accomplished. The primary cause of these difficulties is the unexpectedly heavy brine scale. In addition to affecting the process and operation, the heavy scale lead to inaccurate, unreliable and incomplete data.

Brine flow data was the most difficult parameter to measure. Orifice meters, venturi meters, pitot tubes and annubars were tried without success. Scale would quickly plug pressure taps and alter flow dynamics. These instruments were purged with condensate but did not significantly improve the results. Two types of ultrasonic flow meters were also tried, but with only partial success. Later efforts are described in Section 8, 1978-79 Test Program.

Errors in temperature measurements were also a problem. Scale would form over the sensor well partially insulating the sensor from the brine flow. As the scale thickness increases, the response time slows and errors increase to the point where the data is not useful.

Pressure data was the least troublesome, but scale would eventually plug pressure taps. As scale nearly closed the pressure tap, response times would also be affected. Intermediate fluids, and purging were not totally successful in preventing these problems. Close coupling of the pressure sensor was also unsuccessful.

Withdrawing a sample to analyze the brine also proved troublesome. Scale and flashing of the hot brines blocked sampling ports and fouled sample lines and heat exchangers. The unstable (supersaturated) brine required careful and rapid analysis for accurate results.

These instrumentation and data collection problems resulted in data reduction difficulties. Lawrence Berkeley Laboratory provided data reduction assistance and attempted to develop a computer program to accept, check and reduce data from the GLEF. This effort is detailed in Appendix B. In general, although significant progress was made, the lack of sufficiently accurate data prevented the successful use of this tool.

Other operating difficulties also hampered the test program data collection activities. Initially, poor plant reliability forced tests being aborted prior to completion, requiring a retest. All of the design conditions (noncondensable gas content, isobutane binary fluid, two well production flow) could not be met. Large fluctuations in conditions could not be controlled. However, by the fall of 1977 enough data had been gathered to indicate that the cycle required reexamination. A feasibility study was undertaken to reconsider the type of energy conversion process most appropriate at the Niland reservoir and to define new test objectives. Subsequent to the acceptance of the study in April, 1978, the plant was shut down for conversion to simulate a two-stage, flash steam process (See Section 8.0 1978-1979 GLEF Test Program) and the 1976-77 test program was terminated prior to loading the binary system with isobutane.

The difficulties, plus an early cancellation of this test program resulted in many of the planned tests not being accomplished. All of the planned tests are discussed for completeness. If the testing that was planned could have been accomplished, additional information on the flash binary process would have been available. However, after the conclusion was reached that this process was not appropriate for the resource, the data would not have contributed to reaching the primary objective of defining the technical and economic feasibility of commercial power production.

The purpose of this Section is to summarize the objectives, general test procedures, analysis of the limited results obtained and conclusions of those tasks partially accomplished (See Sections 7.1, 7.2, 7.4, 7.5, 7.6 and 7.15). The objectives and procedures are given as originally planned.

7.1 OPERATIONAL STABILITY OF THE FLASH/BINARY PROCESS; PLANT RESPONSE TO TRANSIENTS AND UPSETS

7.1.1 OBJECTIVES

To establish operational emergency procedures. To verify the structural adequacy of the plant during upsets. To determine the behavior of flashing brine in flash drums, conditions of foaming, stratification, flooding, or blow-through. To establish methods of controlling the flash

process both using the heat exchange process, and independently of the heat exchange process. To determine how to control the level of liquid in the main condenser. To determine the response of the plant to various postulated upset conditions while the binary system is charged with distilled water.

7.1.2 GENERAL TEST PROCEDURES

Task was to be divided into the following three subtasks:

- Subtask A - Control of flash process and heat exchanger condensing temperatures.
- Subtask B - Control of flooding in the main binary system condensers.
- Subtask C - Simulation of upset conditions.

Subtask A - Control of Flash Process and Heat Exchanger Condensing Temperatures

Butterfly valves ahead of the heat exchangers were adjusted to obtain desired operating flash pressures in all of the flash drums. Valves downstream of the heat exchangers (in the condensate lines) were adjusted to control the level of condensate in the heat exchangers. Pressure of the vapor downstream of the butterfly valves was measured and recorded. This subtask was to be performed for the baseline operating conditions and then repeated for a range of flashing temperatures, flashing over equal temperature differences, flashing over equal pressure differences, and elimination of level control.

Subtask B - Control of Flooding in the Main Condensers

Reduction of cooling water flow. Valves in the cooling water line were to be used to reduce the flow of cooling water after stable operating conditions for the baseline mode have been attained. The change in level of the condensate in the condenser was to be observed and recorded.

Reduction in cooling water spray. Valves in the cooling water line were to be opened so that full flow of cooling water is restored. Additional valves were to be used to bypass some of the spray nozzles and permit a portion of the cooling water to flow directly from the condensers to the spray pond without spraying. The change in condensate level in the condensers was to be observed and recorded.

Bypass of one condenser shell. Use of all the spray nozzles was to be restored with the full flow of circulating water. Valve was to be closed on the tubeside of one of the two condensers so that all of the condensation will take place

in the other condenser. The change in level in the active condenser was to be observed and recorded.

Subtask C - Simulation of Upset Conditions

Brine flow of 400,000 lb/hr from two wells. The system was to be operated in the baseline temperature-pressure conditions with 400,000 lb/hr of brine flow from two wells. Flow rates and temperatures at critical points in the system were to be recorded.

Brine flow of 800,000 lb/hr from two wells. The system was to be operated in the baseline temperature-pressure conditions with 800,000 lb/hr of brine flowing from two wells. Flow rates and temperatures at critical points in the system were to be recorded.

Reduction in brine flow. The system was to be operated in the baseline mode with two wells flowing. The valves at the production wells or in the brine production lines were to be closed rapidly. The transient response of the plant system to the perturbation caused by the rapid shutdown was to be detected by taking continuous temperature, pressure, and flow measurements at various preselected locations throughout the system. These instruments were connected to the data logger for displaying changes in conditions.

Outage of brine injection pump. The system was to be operated in the baseline mode with two wells flowing. Electrical power to the brine injection pump was to be suddenly terminated. Continuous measurements of temperature, pressure, and flow will be taken at various preselected points throughout the system. Where manual operation of valves is required to prevent flooding of vessels, the plant operators were to perform the required manual functions.

7.1.3 ANALYSIS OF RESULTS

Many test runs were attempted with respect to this test. In this section, two typical test runs are discussed to demonstrate process stability according to Subtask A. The first test run discussed here was with one well flowing and started on July 7, 1977. The primary purpose was to demonstrate plant stability at baseline operating conditions. During this test run, the geothermal fluid was supplied by Woolsey No. 1 production well. The second test run discussed in this section was begun on January 4, 1978 with two production wells (Woolsey No. 1 and Magmamax No. 1) supplying geothermal fluid to the plant.

The approach used, in the analysis was to trace the flow of the geothermal fluid through the various process vessels while observing the pressures and temperatures for unstable behavior. Then the same procedure was applied to

the binary fluid circuit. From approximately 100 measurements recorded each hour, 30 were selected as indicators of plant stability. The location of these measurements are shown schematically on the plant flow diagram in Figure 7-1.

In early tests, a large portion of the 30 indicators showed large magnitude, complex oscillations. Modification of the original control system (on-off control strategy to proportional control) reduced some of the observed oscillations. Various corrective instrumentation techniques (damping pots and fluids, relocation of sensors, electrical grounding, etc.) were used in conjunction with process changes (manual control, reducing flow rates, changing flash conditions, etc.) with partial success. The selected two test runs are representative of test data collected during this period.

Test data was collected on an automatic data logger. This allowed periodic digital sampling of all 100 measurements. However, periodic digital sampling of data with large magnitude complex oscillations does not provide a consistent set of data for analysis. This inherent limitation of the digital data collection system (each measurement sequentially sampled with a single data point) proved to be a difficult obstacle. Handlogged data, including analog charts, was in the process of being integrated with time slice digital data reduction (multiple digital samples of each critical measurement sequentially programmed into the automatic data logger) when the test program was terminated.

The oscillations were present, to some degree, in all of the geothermal fluid supply measurements. The oscillations were apparently then transmitted to other portions of the plant. This general phenomenon observed from many of the tests, resulted in a separate surge study, documented in Section 9.0. Specific test evaluation of plant stability assumed these oscillations as process disturbances and attempted to determine whether or not the set of processes making up the flash/binary pilot plant dampened out the oscillations so that acceptable steady state operation of a binary turbine generator could be attained.

One Well Flow. For the test run from July 7 to July 11, 1977, the geothermal fluid was supplied by the Woolsey No. 1 production well. Observations regarding the data are summarized in Table 7-1, and the pressure and temperature plots as functions of time are shown in Figures 7-2 through 7-27.

Early in the test run, from the start on July 7 until midday July 8, the plant was being brought to steady state conditions. During this period, pressure/temperature transients were observed. This is not uncommon during a startup period. From midday on July 8 through July 10 a

Figure 7-1 Flow Diagram with Selected Measurement Locations Indicated.

Table 7-1 Pressures and Temperatures During Test Run
7/7/77 Through 7/11/77

GEOTHERMAL FLUID PRESSURES AND TEMPERATURES				
MEASUREMENT DESIGNATION	FIGURE NO.	MEAN	ENVELOPE	COMMENTS
P1-1	2-2	75 psig	± 15 psi	Pressure of the incoming geothermal fluid from Woolsey No. 1. Data are scattered with no apparent pattern. Pressure indication drops off after 7/10/77 to large negative values indicating probable error in instrument zero. See last comment for P1-2.
P1-2	2-3	152 psig	± 3 psi	Pressure in flash vessel V-1 [1] [2] The mean indication of 152 psig is not consistent with means of 75 psig for P1-1 and 395 psig for P1-5 which are upstream and downstream from P1-2; this indicates that two of these three (probably P1-1 and P1-5) pressure indicating are not calibrated correctly.
P1-5	2-4	395 psig	± 3 psi	Pressure at outlet of scrubber V-8 [1] [2] See last comment for P1-2.
P2-1	2-5	58 psig	± 4 psi	Pressure in flash vessel V-7 [1] [2]
P3-1	2-6	29 psia	± 1 psi	Pressure in flash vessel V-14 [1] [2]
P4-1	2-7	23 psia	---	Pressure in flash vessel V-11. There are periods of erratic behavior during part of each day indicating suspected transducer or cable malfunction.
T1-1	2-8	384°F	± 4°F	Temperature of incoming geothermal fluid [1] [2]
T1-3	2-9	370°F	± 5°F	Temperature of vapor at outlet of first flash vessel V-1 [1] [2]
T1-7	2-10	363°F	± 2°F	Temperature at outlet of scrubber V-8 [1] [2]
T1-10	2-11	205°F	± 15°F	Temperature at outlet from heat exchanger E-2 [1] [2] [3]
T2-1	2-12	294°F	± 4°F	Temperature of vapor at outlet of flash vessel V-7 [1] [2]
T2-4	2-13	176°F	± 10°F	Temperature at outlet of heat exchanger E-1A [1] [2] [3]
T3-1	2-14	253°F	± 3°F	Temperature of vapor at outlet of third flash vessel V-14 [1] [2]
T3-4	2-15	129°F	± 10°F	Temperature at outlet of heat exchanger E-1B [1] [2] [3]
T4-1	2-16	206°F	± 4°F	Temperature of vapor at outlet of fourth flash vessel V-11 [1] [2]
T4-4	2-17	110°F	± 3°F	Temperature at outlet of heat exchanger E-1C [1] [2] [3]
P1-10	2-18	25 psig	± 8 psi	Pressure downstream from circulation pump [1] [2]

**Table 7-1 Pressures and Temperatures During Test Run
7/7/77 Through 7/11/77 (Continued)**

BINARY FLUID PRESSURES AND TEMPERATURES				
MEASUREMENT DESIGNATION	FIGURE NO.	MEAN	ENVELOPE	COMMENTS
P1-7	2-19	---	---	Pressure leaving heat exchanger E-3. The pressure indication fluctuates widely. The high pressure indications are in phase with the cooling water diurnal temperature cycle. The magnitude of the negative indications is as great as 150 psig which is physically impossible; therefore, faulty instrument performance is indicated.
T1-15	2-20	89°F	± 3°F	Temperature upstream from heat exchangers (and downstream from the condenser) ① ② ④
T4-5	2-21	96°F	± 4°F	Temperature at outlet of heat exchanger E-5. ① ② ④
T4-6	2-22	118°F	± 5°F	Temperature at outlet of heat exchanger E-1C. ① ② ④
T3-5	2-23	147°F	± 5°F	Temperature at outlet of heat exchanger E-1B. ① ② ④
T2-5	2-24	210°F	± 10°F	Temperature at outlet of heat exchanger E-1A. ① ② ④
T1-9	2-25	247°F	± 7°F	Temperature at outlet of heat exchanger E-3. ① ②

COOLING WATER TEMPERATURES				
MEASUREMENT DESIGNATION	FIGURE NO.	MEAN	ENVELOPE	COMMENTS
T5-1	2-26	89°F	± 3°F	Temperature of incoming cooling water. The temperature increases from 77°F on 7/7/77 to an average daily temperature of 89°F on 7/9/77 and 7/10/77, and it has a diurnal cycle of ± 3°F.
T5-2	2-27	101°F	± 3°F	Temperature of cooling water at condenser outlet. This temperature follows the same pattern as T5-1 with a higher average daily temperature and the same magnitude diurnal cycle as for the incoming cooling water.

- ① The pressure (or temperature) is steady from midday 7/8/77 through 7/10/77.
- ② The pressure (or temperature) drops abruptly after 7/10/77.
- ③ The scatter is much greater than for the geothermal fluid upstream from the heat exchanger. This results from a cooling water diurnal cycle which is transmitted to the secondary fluid and in turn to the geothermal fluid downstream from the heat exchangers.
- ④ The pressure (or temperature) cycles in phase with the incoming cooling water diurnal temperature cycle.

Figure 7-2 Pressure of Incoming Geothermal Fluid (P1-1)

Figure 7-3 Pressure in Flash Vessel V-1 (P1-2)

Figure 7-4 Pressure at Outlet of Scrubber V-8 (P1-5)

Figure 7-5 Pressure in Flash Vessel V-7 (P2-1)

Figure 7-6 Pressure in Flash Vessel V-14 (P3-1)

Figure 7-7 Pressure in Flash Vessel V-11 (P4-1)

Figure 7-8 Temperature of Incoming Geothermal Fluid (T1-1)

Figure 7-9 Vapor Temperature at Outlet of Flash Vessel V-1 (T 1-3)

Figure 7-10 Temperature at Outlet of Scrubber V-8 (T1-7)

Figure 7-11 Outlet Temperature for Heat Exchanger E-2 (T1-10)

Figure 7-12 Vapor Temperature at Outlet of Flash Vessel V-7 (T2-1)

Figure 7-13 Outlet Temperature for Heat Exchanger E-1A (T2-4)

Figure 7-14 Vapor Temperature at Outlet of Flash Vessel V-14 (T3-1)

Figure 7-15 Outlet Temperature for Heat Exchanger E-1B (T3-4)

Figure 7-16 Vapor Temperature at Outlet of Flash Vessel V-11 (T4-1)

Figure 7-17 Outlet Temperature for Heat Exchanger E-1C (T4-4)

Figure 7-18 Pressure Downstream from Circulation Pump (P1-10)

Figure 7-19 Pressure at Outlet of Heat Exchanger E-3 (P1-7)

Figure 7-20 Temperature Upstream from Heat Exchanger E-5 (T1-15)

Figure 7-21 Temperature at Outlet of Heat Exchanger E-5 (T4-5)

Figure 7-22 Temperature at Outlet of Heat Exchanger (T4-6)

Figure 7-23 Temperature at Outlet of Heat Exchanger E-1B (T3-5)

Figure 7-24 Temperature at Outlet of Heat Exchanger E-1A (T2-5)

Figure 7-25 Temperature at Outlet of Heat Exchanger E-3 (T1-9)

Figure 7-26 Temperature of Incoming Cooling Water (T5-1)

Figure 7-27 Temperature of Cooling Water at Condenser Outlet (T5-2)

period of steady state operation was achieved during which the pressures and temperatures were controlled with smaller magnitude oscillations. After July 10, the pressures and temperatures dropped abruptly reflecting plant shutdown activity beginning at midnight July 10.

The mean and envelope values of the variables given in Table 7-1 were obtained from the plotted data over the time interval of steady-state operation from midday July 8 through July 10. Since the Magmamax No. 1 well was not flowing, the pressure and temperature records associated with that stream (P1-3, P1-4, T1-4, and T1-6) are not shown in the illustrations for this test run.

The geothermal fluid pressure indication at the plant inlet, Figure 7-2 was of doubtful validity due to instrument problems with both zero and span, so the mean inlet pressure indication of 75 psig is considered to have been erroneous. Manually hand logged data indicated approximately 118 psi inlet pressure. The inlet pressure envelope from the datalogger of ± 15 psi was equally suspect and was considered only as a qualitative indication of pressure fluctuations in the inlet geothermal fluid. No pattern of pressure variation with time was apparent from this pressure record. However, subsequent data and analysis (See Section 9.0) was successful in evaluating similar conditions.

Once the geothermal fluid entered the first flash vessel, the pressures were relatively steady with data envelopes of ± 4 psi or less in this vessel and downstream of the first flash vessel (Figures 7-3 through 7-6).

Two of the pressure indications downstream from the first flash vessel are suspected of being erroneous. First, the average of 395 psig at the outlet of steam scrubber V-8, Figure 7-4 was much higher than the 152 psig indication in the flash vessel upstream from it, Figure 7-3. Since the temperature measurement at the flash vessel, Figure 7-9 agreed for phase equilibrium conditions with the pressure indication, the flash vessel pressure indication was considered as correct, and the scrubber outlet pressure indication was assumed to be in error. The second suspect pressure is that in flash vessel V-11, Figure 7-7. The evidence indicated either transducer or cable malfunction. Furthermore, the mean value of 23 psig did not agree with the phase equilibrium conditions with measured temperature of 206°F (97°C) at the outlet of that vessel, Figure 7-16. Comparison with manually hand logged data also showed discrepancies with the digital data logger measurements. These two pressure indications were therefore assumed to be erroneous.

The temperatures of the geothermal fluid were steady within an envelope of $\pm 5^\circ\text{F}$ or less for all points upstream from the heat exchangers, Figures 7-8, 7-9, 7-10,

7-12, 7-14, and 7-16. Downstream from the heat exchangers the geothermal fluid temperature envelope was $+ 3^{\circ}\text{F}$ to $+ 15^{\circ}\text{F}$, Figures 7-11, 7-13, 7-15 and 7-17. This was a result of a diurnal temperature cycle in the cooling water, Figure 7-26. This cycle was transmitted from the cooling water to the geothermal fluid via the binary fluid.

The pressure indicated at the outlet of the binary fluid circulation pump was 25 psig with an envelope of ± 8 psig, Figure 7-18. Rapid pressure fluctuations at a pump outlet are normal; however, this envelope was two to three times the magnitude usually observed due to pump fluctuations. Additional fluctuations were thought to be related to the flow variations caused by 2 phase binary fluid (distilled water) expanding across the valve which simulated the binary turbine.

The pressure indication for the binary fluid leaving the last heat exchanger (E-3) fluctuated widely, Figure 7-19. The high pressure indications were in phase with the cooling water diurnal temperature cycle, Figure 7-26. The magnitude of the negative indications was as great as 150 psig which was physically inconsistent, thus rejected. The nature and reasons for the erroneous indications were not evident from the analysis. Other tests also showed pressure fluctuations in phase with the cooling water diurnal temperature cycle.

The temperatures in the binary fluid circuit reflected the cooling water diurnal temperature cycle with envelopes of $\pm 3^{\circ}\text{F}$ at the first heat exchanger (E-5) inlet, Figure 7-15 to $\pm 10^{\circ}\text{F}$ at the outlet of heat exchanger of E-1A, Figure 7-24. Even though the temperature cycling of the binary fluid increased as the fluid flowed through the heat exchangers, the process was stable because the cycling amplitude did not increase with time, Figures 7-10 through 7-25.

The cooling water temperature at the condenser inlet, Figure 7-26 increased from 77°F (25°C) on July 7, to an average daily temperature of 89°F (32°C) on July 9 and 10. It had a diurnal cycle with magnitude equal to $\pm 3^{\circ}\text{F}$. At the condenser outlet the cooling water temperature was 12°F greater, Figure 7-27. The diurnal temperature cycle of the condenser outlet was present with the same $\pm 3^{\circ}\text{F}$ magnitude as at the inlet. The slow increase in temperature was thought to reflect the time required to bring the millions of gallons present in the evaporative ponds to equilibrium. Brine flow data was unuseable for reasons previously discussed. Binary flow data was generally consistent with the pump discharge pressures observed.

Two Well Flow. For the test run on January 4 and 5, 1978, both Woolsey No. 1 and Magmamax No. 1 production

wells were supplying geothermal fluid to the plant. Observations regarding the data are summarized in Table 7-2, and the pressure and temperature plots as functions of time are shown in Figures 7-28 through 7-57.

The geothermal fluid pressure indications were steady except for the inlet streams from the wells. The incoming geothermal fluid streams (P1-1 for Woolsey No. 1 and P1-3 for Magmamax No. 1) data scatter was apparent on the plots, Figures 7-28 and 7-20, but no particular pattern of data trend was detected. The observed scatter was probably due to two-phase flow disturbances in the supply lines and production wells (See Section 9.0). The remaining pressure data in the geothermal fluid streams were steady within ± 2 psig, Figures 7-29, 7-21 through 7-35.

The temperature indications for the geothermal fluid were steady within $\pm 4^{\circ}\text{F}$, Figures 7-36 through 7-44 and 7-46, except at the outlet of heat exchangers E-1B and E-1C, Figures 7-45 and 7-47. At those locations the geothermal fluid was a liquid, and its temperature increased during the test run. This increasing temperature trend was probably caused by the increasing cooling water temperature, Figure 7-56. The increasing cooling water temperature was transmitted through the binary system to the geothermal fluid.

The indicated pressure in the binary fluid downstream from the circulation pump was fairly steady within ± 5 psig with an average value of 121 psig during the test run, Figure 7-48. This pressure was considerably greater than the pressure of 25 psig for the test run discussed above for flow from one well only and inconsistent with the hand logged data indicating a defective pressure measurement.

The pressure indication for the binary fluid leaving the heat exchanger E-3 was also apparently erroneous, Figure 7-49. The magnitude of the negative indications was as great as 220 psig which is physically inconsistent, thus rejected. The nature and reasons for the erroneous indications were not evident from the analysis.

The temperatures in the binary fluid stream, Figures 7-50 through 7-54, reflected an increase in the cooling water temperature, Figure 7-56, except at the outlet of heat exchanger E-3, Figure 7-55. At this location the binary fluid (distilled water) was expected to be a mixture of liquid and vapor while at all the upstream locations, where the increasing temperature trend was apparent, it was liquid.

Summary of Two Test Runs. The tests which were physically realizable were completed. Full two well (800,000 lb/hr) flow was not fully accomplished due to plant and production well limitations. Single condenser operation

**Table 7-2 Pressures and Temperatures During Test Run
1/4/78 and 1/5/78**

GEOTHERMAL FLUID PRESSURES AND TEMPERATURES				
MEASUREMENT DESIGNATION	FIGURE NO.	MEAN	ENVELOPE	COMMENTS
P1-1	2-28	195 psig	± 12 psi	Pressure of incoming geothermal fluid from Woolsey No. 1. Data are scattered with no apparent pattern.
P1-2	2-29	145 psig	± 2psi	Pressure in flash vessel V-1.
P1-3	2-30	170 psig	± 20 psi	Pressure of incoming geothermal fluid from Magmamax No. 1. Data are scattered with no apparent pattern.
P1-4	2-31	145 psig	± 2 psi	Pressure in flash vessel V-4.
P1-5	2-32	145 psig	± 2psi	Pressure at outlet of scrubber V-8.
P2-1	2-33	48 psig	± 2 psi	Pressure in flash vessel V-7.
P3-1	2-34	30 psia	± 1 psi	Pressure in flash vessel V-14.
P4-1	2-35	14 psia	± 1psi	Pressure in flash vessel V-11.
T1-1	2-36	390°F	± 1°F	Temperature of Incoming geothermal fluid from Woolsey No. 1.
T1-3	2-37	312°F	± 1°F	Temperature of vapor leaving flash vessel V-1.
T1-4	2-38	147°F	± 1°F	Temperature of Incoming geothermal fluid from Magmamax No. 1.
T1-6	2-39	371°F	± 1°F	Temperature of vapor leaving flash vessel V-4.
T1-7	2-40	365°F	± 1°F	Temperature at outlet of scrubber V-8.
T1-10	2-41	277°F	± 1°F	Temperature at outlet of heat exchanger E-2.
T2-1	2-42	298°F	± 2°F	Temperature of vapor leaving flash vessel V-7.
T2-4	2-43	278°F	± 2°F	Temperature at outlet of heat exchanger E-1A.
T3-1	2-44	258°F	± 4°F	Temperature of vapor leaving flash vessel V-14.
T3-4	2-45	174°F	± 3°F	Temperature at outlet of heat exchanger E-1B. Temperature has an increasing trend during test run. [1]
T4-1	2-46	213°F	± 2°F	Temperature of vapor leaving flash vessel V-11.
T4-4	2-47	124°F	± 5°F	Temperature at outlet of heat exchanger E-1C. Temperature increases from 119°F to 129°F during test run. [1]

**Table 7-2 Pressures and Temperatures During Test Run
1/4/78 and 1/5/78 (Continued)**

BINARY FLUID PRESSURES AND TEMPERATURES				
MEASUREMENT DESIGNATION	FIGURE NO.	MEAN	ENVELOPE	COMMENTS
P1-10	2-18	121 psig	± 5 psi	Pressure downstream from circulation pump.
P1-7	2-49	---	---	Pressure leaving heat exchanger E-3. The magnitude of the negative indications is as great as 220 psig which is physically impossible; therefore, faulty instrument performance is indicated.
T1-15	2-50	83°F	± 5°F	Temperature upstream from heat exchangers (and downstream from the condensers) Temperature increases from 78°F to 88°F during test run. ^[1]
T4-5	2-51	105°F	± 5°F	Temperature at outlet of heat exchanger E-5. Temperature increases from 100°F to 109°F during test run. ^[1]
T4-6	2-52	158°F	± 8°F	Temperature at outlet of heat exchanger E-1C. Temperature increases from 154°F to 163°F during test run. ^[1]
T3-5	2-53	201°F	± 3°F	Temperature at outlet of heat exchanger E-1B. Temperature increases from 198°F to 204°F during test run. ^[1]
T2-5	2-54	276°F	± 2°F	Temperature at outlet of heat exchanger E-1A. Temperature increases from 275°F to 278°F during test run. ^[1]
T1-9	2-55	275°F	± 2°F	Temperature at outlet of heat exchanger E-3.

COOLING WATER TEMPERATURES				
MEASUREMENT DESIGNATION	FIGURE NO.	MEAN	ENVELOPE	COMMENTS
T5-1	2-56	83°F	± 5°F	Temperature of incoming cooling water. Temperature increases from 78°F to 88°F during test run.
T5-2	2-57	100°F	± 6°F	Temperature of cooling water at condenser outlet. Temperature increases from 94°F to 106°F during test run. ^[1]

^[1] The temperature at this location reflects the cooling water temperature (T5-1) increase during the test run.

Figure 7-28 Pressure of Incoming Geothermal Fluid from Woolsey No. 1 (P1-1)

Figure 7-29 Pressure in Flash Vessel V-1 (P1-2)

Figure 7-30 Pressure of Incoming Geothermal Fluid from Magmamax No. 1 (P1-3)

Figure 7-31 Pressure in Flash Vessel V-4 (P1-4)

Figure 7-32 Pressure at Outlet of Scrubber V-8 (P1-5)

Figure 7-33 Pressure in Flash Vessel V-7 (P2-1)

Figure 7-34 Pressure in Flash Vessel V-14 (P3-1)

Figure 7-35 Pressure in Flash Vessel V-11 (P4-1)

Figure 7-36 Temperature of Incoming Geothermal Fluid from Woolsey No. 1 (T1-1)

Figure 7-37 Vapor Temperature at Outlet of Flash Vessel V-1 (T1-3)

Figure 7-38 Temperature of Incoming Geothermal Fluid from Magmamax No. 1 (T1-4)

Figure 7-39 Vapor Temperature at Outlet of Flash Vessel V-4 (T1-6)

Figure 7-40 Temperature at Outlet of Scrubber V-8 (T1-7)

Figure 7-41 Outlet Temperature for Heat Exchanger E-2 (T1-10)

Figure 7-42 Vapor Temperature at Outlet of Flash Vessel V-7 (T2-1)

Figure 7-43 Outlet Temperature for Heat Exchanger E-1A (T-2-4)

Figure 7-44 Vapor Temperature at Outlet of Flash Vessel V-14 (T3-1)

Figure 7-45 Outlet Temperature for Heat Exchanger E-1B (T3-4)

Figure 7-46 Vapor Temperature at Outlet of Flash Vessel V-11 (T4-1)

Figure 7-47 Outlet Temperature for Heat Exchanger E-1C (T4-4)

Figure 7-48 Pressure Downstream from Circulation Pump (P1-10)

Figure 7-49 Pressure at Outlet of Heat Exchanger E-3 (P1-7)

Figure 7-50 Temperature Upstream from Heat Exchanger E-5 (T1-15)

Figure 7-51 Temperature at Outlet of Heat Exchanger E-5 (T4-5)

Figure 7-52 Temperature at Outlet of Heat Exchanger E-1C (T4-6)

Figure 7-53 Temperature at Outlet of Heat Exchanger E-1B (T3-5)

Figure 7-54 Temperature at Outlet of Heat Exchanger E-1A (T2-5)

Figure 7-55 Temperature at Outlet of Heat Exchanger E-3 (T1-9)

Figure 7-56 Temperature of Incoming Cooling Water (T5-1)

Figure 7-57 Temperature of Cooling Water at Condenser Outlet (T5-2)

resulted in damage to the condenser (high pressure drop buckled a baffle in cooling water portion), after repair, single condenser testing was deleted. Reductions in cooling water flow, water spray and brine flow were limited by operational constraints. Outage of brine injection pump was a frequent data point although unplanned in most instances.

Test data did show, however, the ability of the system to accept transient variations in operating conditions, verified the majority of the plant's structural integrity and cycle process flow.

7.1.4 CONCLUSIONS

Although large fluctuations in inlet brine conditions were observed, the geothermal vapor pressures and temperatures upstream from the heat exchangers were relatively steady during the test runs initiated on July 7, 1977, and January 4, 1978. Pressure fluctuations in the inlet geothermal fluid stream were dampened and did not seriously affect the binary fluid stream. Downstream from the heat exchangers, the geothermal fluid experienced temperature transients due to temperature changes induced by the cooling water entering the binary condensers.

The valid binary fluid temperatures and pressures reached relatively stable conditions except for transient effects caused by cooling water temperature changes and two phase expansion across the valve simulating the turbine.

The binary system was not unstable during limited changes in cooling water flow, brine flow, or spray configuration. No unusual transients were observed in the process of normal or emergency shutdowns. When brine flows were reduced to approximately 10 to 20% of design conditions, control and other difficulties were observed.

Process problems, not considering instrumentation, major equipment or operational problems previously discussed, involved two phase expansion across a valve (which should not be a problem using the design fluid, isobutane) and large inlet brine oscillations (See Section 9.0). Relatively simple proportional and/or manual control valves were otherwise shown to be capable of acceptable process control, again not considering operational problems previously discussed.

7.2 OVERALL HEAT AND MASS BALANCE OF THE PLANT UNDER BASELINE OPERATING CONDITIONS

7.2.1 OBJECTIVE

To establish a uniform calculational procedure, with built-in cross checks, to provide a basis for consistent data reduction.

7.2.2 GENERAL TEST PROCEDURE

Measurements of fluid flow, temperatures, pressures, and concentrations were to be used to develop the overall mass balance. Once the overall mass balance was developed, the overall heat balance would be derived. A computer program was to be developed to allow rapid evaluation of test data.

7.2.3 ANALYSIS OF RESULTS

Several overall plant heat and mass balances were completed. Results were not consistently within the 10% accuracy range specified in the test plan. The major reason for the inaccuracy was identified as the inability to reliably measure brine flow rates. Other reasons included plant and well limitations resulting in off design conditions, accuracy limitations of commercial instrumentation and oscillations in inlet brine conditions. Measures to improve instrumentation and oscillations under these conditions is described elsewhere in this report.

In order to minimize the effect of the observed inaccuracies, an effort to create a computer program to reduce the data was directed towards substituting indirectly measured values for inaccurate or unavailable data. This approach, however, deleted some or all cross checks on the remaining data base. Although a computer program was generated, initial results indicated additional site data and data collection would be required to adequately cross check results.

The test plan called for overall plant heat and mass balance calculations for all tests with a goal of $\pm 10\%$ maximum discrepancy in the heat and mass balances. Because of problems previously discussed, complete overall plant heat and mass balance calculations could not be performed. However, in most of the test runs, the binary fluid flow rate and the cooling water flow rate were measured with sufficient confidence to support partial plant heat balance calculation for the binary fluid circuit. This partial plant heat balance consists of comparing the heat transferred to the cooling water with the heat transferred by the binary fluid in heat exchangers E-5, E-1C, E-1B, E-1A, E-2, and E-3. The plant flow diagram with the variables used for the partial plant heat balance is shown in Figure 7-58. The heat rates were calculated and could be applied to the fluid from either geothermal well.

The results of partial plant heat balance calculations for test runs from July and August, 1977, are shown in Table 7-3. For the tests starting July 7 and July 18, the flow rate data for the binary fluid were not reliable. Therefore, the partial plant heat balance calculation was

Figure 7-58 Flow Diagram with Variables Used for Partial Plant Heat Balance.

Table 7-3 Partial Plant Heat Balance Results

<u>Test Start Date</u>	<u>Cassette No.</u>	<u>Data Used In Calculation</u>	<u>Discrepancy</u>
7/7/77	14	Binary fluid flow data not reliable	--
7/18/77	15	Binary fluid flow data not reliable	--
7/26/77	17	avg of 24 hrs; starting 7/29, 7:58	+11%
7/31/77	18	avg of 24 hrs; starting 8/4, 12:57	+23%
8/9/77	20	avg of 24 hrs; starting 8/12, 6:57	+3%

not accomplished for these tests. No reason for this reliability problem was discovered. For each of the other three tests, the data were averaged over 24 hours of apparent steady state operation to obtain typical results. Of these three test runs, one of them (the test starting August 9) produced partial plant heat balance results meeting the $\pm 10\%$ maximum discrepancy criterion in the test plan (3%), one (the test starting July 26) had $+11\%$ discrepancy, but a third (test starting July 31) showed a discrepancy of $+23\%$.

To determine the cause of the large discrepancy for the run starting July 31, the data plots for all three runs were examined, and the random data scatter was analyzed by comparing the standard deviation of each variable for each of the three test runs. However, similar variances were found for the three runs. Data trends were also similar for all three test runs. The cause of the 23% discrepancy was not determined.

The analysis of the data scatter revealed a large random disturbance in the binary fluid flow data (F3-3). The standard deviation of the mean was 5 - 8% of the average flow rate for each of the three test runs. This standard deviation of the mean is quite large and indicates a need to obtain smoother flow or flow data from the binary fluid loop. For comparison purposes, this scatter may be compared with the standard deviation of the mean equal to less than 1% of the average flow rate for the cooling water. It was theorized that two-phase flow disturbances across the expansion valve was contributing to the scatter. Variations in pressure were consistent with this conclusion.

An area for improving heat balance measurement was identified. The original instrumentation for the GLEF included measurements of inlet and outlet temperatures and pressures across the heat exchangers. This is common for process or pilot plant control. However, rather than measuring inlet temperature and outlet conditions and subtracting one from the other, a direct differential measurement would significantly improve accuracy. This would be especially beneficial where the differential is small (as is the case for the cooling water inlet and outlet conditions) since small percentage error in measuring either condition causes a large percentage error in the calculated difference. Direct reading differential measurements were in the process of being installed upon termination of this test program.

7.2.4 CONCLUSIONS

The complete plant heat and mass balance calculations could not be performed because of inadequate flow rate measurements for the geothermal fluid. A partial plant heat and mass balance computation procedure was developed for operation with either geothermal well supplying fluid to the

plant. This partial plant heat and mass balance allowed comparison of the heat gained by the binary fluid (transferred from the geothermal fluid) to the heat transferred to the cooling water. Heat balance discrepancies for three test runs were +3%, +11%, and +23% for a 24-hour period of steady state operation. The first two (+3% and +11% discrepancies) were generally acceptable in view of the $\pm 10\%$ discrepancy target figure given in the test plan. However, the +23% discrepancy was not consistent with expectations. The data set was reviewed to determine the explanation for such a large difference. It was theorized that general instrumentation inaccuracy was at least partially responsible for this discrepancy, especially cooling water temperatures. Additional instrumentation, backup and improved data reduction procedures were expected to improve results. 10% target may have been an overly optimistic goal for the facility as originally designed and instrumented.

7.3 CLEAN-TUBE HEAT TRANSFER COEFFICIENTS WITH WATER AS THE BINARY FLUID (Task not completed)

7.3.1 OBJECTIVES

To determine the clean-tube coefficients of the first stage exchangers, (E-2 and E-3,) the second stage exchanger, (E-1A) the third stage exchanger, (E-1B) the fourth stage exchanger, (E-1C) and the condensate cooler (E-5). Compare these results with the predictions of analytical methods.

7.3.2 GENERAL TEST PROCEDURE

The overall heat transfer coefficients for the clean tubes was to be determined from a heat and mass balance around the heat exchangers and measurements of operating conditions. Task 3 was divided into the following three subtasks:

- o Subtask A related to Exchangers E-1A, E-1B, E-1C
- o Subtask B related to Exchanger E-5
- o Subtask C related to Exchangers E-2 and E-3

7.3.3 ANALYSIS OF RESULTS

Initial review of the data indicated that the accuracy of installed instrumentation and plant conditions were not suited for meaningful results. Using water instead of isobutane as the binary fluid especially with one well flow, resulted in smaller temperature changes across each heat exchanger (at a given binary flow rate). The accuracy of temperature data required to calculate heat transfer coefficients was therefore beyond the capability of actual plant instrumentation.

Several improvements and modifications, such as more frequent calibrations and bypassing one heat exchanger to increase the temperature drop across remaining heat exchangers, proved to be inadequate. Test was therefore deferred, pending improved instrumentation, or conditions.

7.4 PURITY OF VAPOR; SCRUBBER PERFORMANCE

7.4.1 OBJECTIVES

To evaluate the performance of the scrubbers by measuring the purity of the outlet vapor as a function of its purity at the inlet, the vapor velocity, and the flow of condensate wash. To measure pressure drop as a function of the above parameters.

7.4.2 GENERAL TEST PROCEDURE

The plant was to be started and operated at the baseline operating conditions using the control techniques that were established in Task 1 (using distilled water as the binary fluid). Brine flow rate was to be varied to control the volume of flashed vapor, and hence, the vapor velocity in the scrubber, by making the necessary adjustments to the appropriate valves. While holding the brine flow rate constant, pressure changes between flash stages were adjusted to control vapor velocities and pressure while measuring the level of carryover in the vapor. Measurements were to be taken for four different flow rates, and for each of these cases, three sets of flash pressures were to be run. Furthermore, for each of these 12 test runs, the condensate wash flow rate was to be varied four-fold. As a result, vapor purity and pressure drop was to be plotted for 48 different data points.

7.4.3 ANALYSIS OF RESULTS

The most carefully controlled scrubber performance tests were conducted in August, 1977, and in early October, 1977. The results of these tests are shown in Figures 7-59 through 7-62 where outlet sodium (Na) concentration in ppm is plotted against inlet concentration for each of the four scrubbers. Since the TDS in the steam is assumed to be caused primarily by brine entrainment (carryover), and Na constitutes 20 - 25% of the total dissolved solids (TDS) for the brine from the Woolsey No. 1 and Magmamax No. 1 production wells, the TDS of the steam is four to five times as great as the concentration reported here in ppm Na. The brine carryover assumption has been previously verified by comparing the ratios of solids (primarily chloride salts) in the steam to the brine ratio of solids. The ratios are essentially equivalent.

Figure 7-59 First Stage Scrubber Performance

Figure 7-60 Second Stage Scrubber Performance

Figure 7-61 Third Stage Scrubber Performance

Figure 7-62 Fourth Stage Scrubber Performance

For the first stage scrubber, the inlet Na concentration varied up to 200 ppm during the tests while the outlet concentration of Na was 3.5 ppm or less (Figure 7-59). This showed excellent scrubber performance over a wide range of inlet solids concentration. Changes to inlet wash water flow rate had no detectable effect on scrubber performance. It appears that satisfactory 1st stage steam purification can be accomplished without the use of inlet wash water.

For the second stage scrubber, the maximum inlet concentration during the tests was 10.3 ppm Na (Figure 7-60) which was too low to allow a conclusion to be drawn about scrubber performance under more severe operating conditions. However, outlet concentrations were acceptable under these conditions.

For the third stage scrubber, the maximum inlet Na concentration was 29 ppm with an outlet Na concentration of 4.4 ppm Na or less (Figure 7-61). This result was again satisfactory, but was not conclusive because of the low range of inlet concentrations. The performance for the scrubber over a wide range of inlet concentrations was not established by the tests.

For the fourth stage scrubber, the maximum inlet concentration during the tests was 45 ppm Na (Figure 7-62). The results were erratic with one test showing 4.5 ppm Na at the outlet for 45 ppm Na inlet concentration and another showing 44 ppm Na at both the inlet and the outlet. Both of the tests were conducted with a zero wash water flow rate. Several theories have been advanced. Foaming of Niland brines has been observed at other locations and may have contributed to the erratic results noted. Upset conditions may deposit scale which may dissolve and contribute to erratic results. Scale disposition may also block or disturb geometry within the scrubber. In summary, no conclusion was reached concerning the scrubbing effectiveness of the fourth stage scrubber. However, the test results in Figure 6-62 did indicate that the wash water flow rate had no effect on scrubber effectiveness and most of the data points were acceptable.

Because of instrumentation problems, the data measured were insufficient to determine vapor velocity in the scrubbers. Scrubber performance as a function of vapor velocity and is needed for design of full-scale plant equipment. However, related flow rate data (binary and cooling water) and heat and mass balance calculations indicates that vapor velocities should have been in the range of expected values.

7.4.4 CONCLUSIONS

Test was essentially completed, except that conditions were limited by plant and well limitations. Results showed that scrubbers did improve steam purity under a variety of condition, but performance was variable and essentially independent of wash water flow rate.

It was theorized that condensation liquid and removal within the scrubbers acted as an independent source of wash water. This was confirmed by measurements at the wash water drain which showed flowrates in excess of inlet flowrates. This at least partially explains the performance essentially independent of wash water flow rate.

The scrubber test results can be summarized as follows:

- o The first stage scrubber performance was good. An outlet concentration of 3.5 ppm Na or less was achieved with inlet concentration up to 200 ppm Na. This represents a removal efficiency of better than 98%.
- o Scrubbing effectiveness for the second, third and fourth stage scrubbers was not established by the tests, but outlet concentrations were generally acceptable.
- o Data from both the first and fourth stage scrubbers showed no detectable effect from the flow rate of wash water.

Since vapor velocity could not be accurately determined from the test results to date, establishing the relationships of scrubber efficiency and pressure drop to vapor velocity was not accomplished. However, pressure drop and performance was generally acceptable.

7.5 SCALE PREVENTION

7.5.1 OBJECTIVES

To characterize scales from the geothermal brine and to define and test methods of scale prevention. To characterize the brine and effluent and identify suspended solids. To develop and test treatments for the effluent geothermal brine, if required. If scale prevention testing showed promise testing at the (full size) GLEF was anticipated.

7.5.2 GENERAL TEST PROCEDURE

The detailed scale prevention test program is included in Report No. UCID-17209 of Lawrence Livermore

Laboratory (LLL), in accordance with the agreement between LLL and DOE. Testing primarily utilized the LLL side stream facility and laboratory facilities to sample, treat, and analyze results in the brine system.

7.5.3 ANALYSIS OF RESULTS AND CONCLUSIONS

These tests were conducted and reported separately by Lawrence Livermore Laboratory. Results indicated that acidification of the brine reduces the scale and suspended solids in the effluent brines. Scale and suspended solids in the effluent brine were identified as predominantly silica. Scale formation was theorized, based on inspection and analysis, to result from micron sized amorphous silica particles adhering to each other and surfaces. Brine effluent treatment was identified as raising the pH.

Results of this effort were included in the feasibility and risk study (See Section 9.0). Although testing showed a significant scale prevention potential of brine acidification, total system cost comparison showed no advantage when compared to untreated brine, and full facility testing was deferred.

7.6 MATERIALS AND COMPONENT EVALUATION

7.6.1 OBJECTIVES

To extend the corrosion test results of the Geothermal Loop Experimental Facility at Niland to the flash/binary process. To test materials for corrosion rate under conditions of exposure to untreated and acidified geothermal brines and to evaluate test results. To evaluate substitute materials for any components undergoing excessive corrosion in the plant.

7.6.2 GENERAL TEST PROCEDURE

The materials and component evaluation test program is included in Report No. UCID-17209 of Lawrence Livermore Laboratory, in accordance with the agreement between LLL and DOE.

7.6.3 ANALYSIS OF RESULTS AND CONCLUSIONS

These tests were conducted and reported separately by Lawrence Livermore Laboratory. A variety of materials and components were exposed to untreated and acidified brines in LLL side stream facility which simulated the GLEF flash binary process. Materials for both untreated and acidified brine applications were selected and identified for further definition of scaling rates, pitting, etc.

Results were incorporated in the feasibility and risk study (See Section 9.0). Acidified brines required higher cost materials of construction to maintain acceptable corrosion rates.

7.7 EFFECT OF NONCONDENSIBLE GASES ON THE HEAT TRANSFER COEFFICIENT (Task not accomplished)

7.7.1 OBJECTIVE

To determine the effect of the concentration of noncondensable gases on the heat transfer performance of exchangers E-2 and E-3. To compare and correlate the effect with theoretical predictions.

7.7.2 GENERAL TEST PROCEDURES

The heat transfer coefficient of binary heat exchangers was expected to be a function of the amount of noncondensable gases present as well as flows and physical properties. The outlet temperature from exchanger E-2 was to be varied by adjusting the temperature controller on V-6. This was to result in changing the flow from V-1, thus changing the heat load and the concentration of noncondensable gas in exchangers E-2 and E-3. Three temperature settings on V-1, of approximately 230°F (110°C), 250°F (121°C), and 270°F (132°C), were to provide a range of noncondensable gas concentrations for analysis. The actual settings were expected vary somewhat from the above values after the results of Task 1 and Task 3 are reviewed.

7.7.3 ANALYSIS OF RESULTS

No significant results were obtained. The amount of noncondensable gases was well below expected values, combined with the insufficiently accurate data from the pilot plant type instrumentation lead to deferral of this task. Laboratory testing with closely controlled conditions was recommended if detailed effect of noncondensable gases on heat transfer coefficient data is required.

7.8 CONTINUED MONITORING OF HEAT TRANSFER COEFFICIENTS AND FOULING RESISTANCE IN MULTI-STAGE HEAT EXCHANGERS (Task not completed)

7.8.1 OBJECTIVES

To determine the extent of deterioration of heat exchanger performance with time as fouling occurs. To determine how the residual fouling resistance changes with time and to measure the residual fouling resistance by comparison with the clean tube coefficients determined in Task 3.

7.8.2 GENERAL TEST PROCEDURE

The test procedure involved was to repeat the tests specified in Task 3 at intervals during the period of plant operation and testing. For each test, the binary side would be adjusted as nearly as possible to the same conditions of temperature, pressure, and flow as in the Task 3 tests. This should have resulted in increasingly higher vapor inlet pressures for E-2, E-3, and E-1A, B, C as the surface area fouls and performance deteriorates. Steam flows and overall heat transfer coefficients will be calculated from test measurements and plotted against onstream time.

7.8.3 ANALYSIS OF RESULTS AND CONCLUSIONS

Data from existing GLEF instrumentation using water as the binary fluid was not usable. All of the GLEF heat exchangers were designed for use with isobutane. All of the heat exchangers, except E-2 and E-3 used available equipment. This resulted in significantly oversized heat exchanger surface area. The use of water as a binary working fluid resulted in a large excess capacity. Detection of any but the most drastic changes in heat transfer coefficients were not possible under these conditions. Testing was therefore deferred.

Performance of GLEF heat exchangers was generally acceptable. Heat exchanger performance data concurred with other test results (heat and mass balance, scrubber performance, etc.). Maintenance inspections generally showed little scale but some system corrosion product (iron oxide) accumulations in heat transfer surface area (tubes). This is not unexpected and the amounts were not unusual.

Although test was inadequate to define the fouling and quantify the impact on heat transfer coefficients, data did show that if steam purity is maintained, no drastic impacts of fouling or scale build-up were observed.

7.9 RESTORATION OF CLEAN-TUBE HEAT TRANSFER COEFFICIENTS (Task not completed)

7.9.1 OBJECTIVES

To obtain clean heat transfer surfaces after operation with water as the binary fluid, but before operation with isobutane. To demonstrate the effectiveness of various cleaning procedures for cleaning heat transfer surfaces.

7.9.2 GENERAL TEST PROCEDURES

Various methods are available for cleaning inside and outside tube surfaces. These procedures include mechanical

cleaning methods like hydroblasting, chemical cleaning by circulation of corrosion inhibited acids, bases, or other solutions, and vapor-phase onstream cleaning by injecting gases such as CO_2 , SO_2 , or NH_3 while operating. Effectiveness of cleaning method used was to be evaluated based upon the change (before and after cleaning) in heat transfer coefficient.

7.9.3 ANALYSIS OF RESULTS

Because of the lack of valid heat transfer coefficient data, no quantitative results were obtained. In addition, because of generally acceptable heat exchanger performance and little scale accumulation, little cleaning was required. Although some portions of the heat transfer tubing were cleaned, using hydroblast and chemical techniques, definitive conclusions concerning the best cleaning method could not be drawn. No significant problems were observed with the cleaning methods used.

7.10 OPERATIONAL STABILITY OF THE FLASH/BINARY PROCESS DURING ISOBUTANE RUNS (Task not completed)

7.10.1 OBJECTIVES

To establish methods of controlling the flash process using the heat exchange process, and independently of the heat exchange power while the system is charged with isobutane. To evaluate the stability of plant operation when operating in the baseline mode with isobutane as the working fluid. To develop plant start-up and shutdown procedures for the isobutane case.

7.10.2 GENERAL TEST PROCEDURES

The same methods of control that were to be established in Task 1 for controlling the flash process were to be used for the isobutane baseline test run. Flow of brine into the pilot plant was to be from two wells at approximately 800,000 lb/hr. Pressure upstream of the main bypass valve was to be controlled to design condition (about 500 psia), which was slightly below the critical point. Three more cases were to be run, with pressures controlled to 550 psia (supercritical case), 525 psia (critical case), and 450 psia (subcritical case), respectively. Finally, an additional subcritical case was to be run with brine and isobutane flow rates reduced to about 60 percent of the baseline flow rates. For all five test runs, measurements of pressure and temperature were to be taken at key points in the isobutane system at hourly intervals.

7.10.3 ANALYSIS OF RESULTS

No significant data was collected because the test program was terminated prior to loading the binary system with isobutane. However, preliminary efforts did begin to develop plant startup, operating, and shutdown procedures using isobutane, safety reviews, lists of equipment and modifications required, and obtaining the regulatory approvals required.

7.11 OVERALL HEAT AND MASS BALANCE BASELINE FOR ISOBUTANE RUNS (Task not completed)

7.11.1 OBJECTIVES

To establish the overall heat and mass balance of the plant from plant measurements while operating the plant in the baseline mode with isobutane as the working fluid.

7.11.2 GENERAL TEST PROCEDURE

Similar to Task 2

7.11.3 ANALYSIS OF RESULTS

Because isobutane was not loaded prior to GLEF conversion to a two-stage flash configuration, this test was not accomplished.

7.12 CONDENSER PERFORMANCE WITH ISOBUTANE AS THE BINARY FLUID (Task not completed)

7.12.1 OBJECTIVES

To determine the overall heat transfer coefficient and the isobutane condensing coefficient on exchangers E-4A and 4B. To measure the shellside and tubeside pressure drop. To compare the measured heat transfer and pressure drop results with the theoretical predictions.

7.12.2 GENERAL TEST PROCEDURE

The overall heat transfer coefficient for clean-tube conditions was to be determined from a heat and mass balance around the condenser and measurement of operating conditions. Pressure differentials across the condenser were to be measured and recorded. This task was to consist of four tests: two isobutane flows, each with two levels of superheat.

7.12.3 ANALYSIS OF RESULTS

This test was not accomplished prior to test plan termination.

7.13 HEAT TRANSFER AND PRESSURE DROP PERFORMANCE OF ISOBUTANE IN AND AROUND THE CRITICAL REGION (Task not completed)

7.13.1 OBJECTIVES

To obtain heat transfer coefficients, pressure drop data, and behavioral information of isobutane in the critical and near-critical region in exchangers E-2 and E-3. To measure shellside and tubeside pressure drops. To compare and correlate experimental results with predictive models.

7.13.2 GENERAL TEST PROCEDURE

The overall heat transfer coefficient for clean-tube conditions was to be determined from a heat and mass balance around the exchangers E-2 and E-3 and measurement of operating conditions. The procedure was to be as outlined in Task 3.

Pressure differentials across the shellside and tubeside of each exchanger was to be measured and recorded.

This task was to consist of eight basic tests: two isobutane flows, each flow at four different pressure levels.

7.13.3 ANALYSIS OF TEST RESULTS

This test was not accomplished prior to test plan termination.

7.14 PERFORMANCE OF LIQUID ISOBUTANE EXCHANGERS, E-1A, B, C and E-5 (Task not completed)

7.14.1 OBJECTIVES

To determine the overall heat transfer coefficients and the isobutane liquid heat transfer coefficients. To measure the shellside and tubeside pressure drops. To compare the measured heat transfer and pressure drop results with theoretical predictions.

7.14.2 GENERAL TEST PROCEDURES

The overall heat transfer coefficients for clean-tube conditions was to be determined from a heat and mass balance around the exchangers and measurements of operating conditions. Pressure differentials across the shellside and tubeside of each exchanger was to be measured and recorded.

7.14.3 ANALYSIS OF RESULTS

This test was not accomplished prior to termination.

7.15 DETERMINATION OF NONEQUILIBRIUM AND BOILING POINT ELEVATION

7.15.1 OBJECTIVES

To measure the nonequilibrium allowance (the approach to equilibrium) and boiling point elevation.

7.15.2 GENERAL TEST PROCEDURE

The plant was to be stabilized at the test conditions and the brine and vapor temperatures in each flash drum and heat exchangers was to be subtracted from equilibrium saturated water/vapor conditions.

7.15.3. ANALYSIS OF RESULTS

Data were recorded for conditions designated as Tests 5 and 6 in this test program. Some typical results are presented in Table 7-4 where the nonequilibrium allowance data were calculated from average values of pressure and temperature over seven-hour time periods. The expected boiling point elevation information was taken from the data prepared by the Denver Research Corporation for mixtures of KCl, CaCl_2 , and NaCl salts (Ref. 7.19-2).

The main observation concerning the results presented in Table 7-4 is that every value for nonequilibrium allowance was negative. One theory was that scale was forming on the temperature probes, creating an insulating barrier leading to lower temperature readings. Accuracy limitations of commercial instrumentation can also lead to significant errors of this sensitive parameter. Since the calculation of nonequilibrium allowance was based on measurements of both brine temperature and vapor pressure, small discrepancies in either of these values may have caused the incongruous negative results.

To obtain valid results, a thorough study and corrections would be required for all the supporting measurement and data reduction techniques and equipment. Since a sizeable expenditure of effort was likely to be required, and lack of results would not significantly impact primary objectives, further testing was deferred.

7.15.4 CONCLUSIONS

Test data was collected and analyzed. The accuracy of the data was not sufficient to give acceptable results. Expecting acceptable results, when subtracting two values of similar magnitude, from pilot plant type instrumentation, in a scaling environment, was optimistic. Efforts to improve data accuracy were not successful in the time prior to test plan termination.

Flash Vessel	Data Record		Pressure Psia	Brine Temperature F	Saturation Temperature F	Boiling Point Elevation F	Nonequilibrium Allowance F
	Date	Time Period					
V-1	7/27/77	0:58 - 7:58	126.8	352.6	345.4	12.8	- 5.6
	7/30/77	0:58 - 7:58	123.1	350.0	343.2	12.4	- 5.6
V-7	7/27/77	0:58 - 7:58	103.5	320.1	330.3	12.8	-23.0
	7/30/77	0:58 - 7:58	104.9	320.2	331.3	12.8	-23.7
V-14	7/27/77	0:58 - 7:58	62.1	299.5	295.0	12.6	- 8.1
	7/30/77	0:58 - 7:58	64.3	300.2	297.3	12.7	- 9.8
V-11	7/27/77	0:58 - 7:58	15.4	215.5	214.7	6.8	- 6.0
	7/30/77	0:58 - 7:58	18.7	221.0	224.8	7.4	-11.2

Table 7-4 Nonequilibrium Allowance

The results that were obtained were significantly different from expected. The explanation(s) for this anomaly appear to be related to instrumentation limitations and scale build-up. A preliminary evaluation of the potential worth of the information versus the probable cost to determine nonequilibrium allowance and boiling point elevation resulted in deferral of this task.

7.16 COMPARISON OF FLASHING DEVICES AND MIST ELIMINATORS (Task not completed)

7.16.1 OBJECTIVES

To determine the alternatives to the presently installed flashing impingement baffles for reducing entrainment of brine in the vapor and for increasing operational stability. To determine if mesh separators or hook-and-vane separators can eliminate the need for scrubbers. To verify the pressure drop and efficiency of alternate separators.

7.16.2 GENERAL TEST PROCEDURES

This task was to involve three basic steps of vessel modification. These are,

- o Install an orifice in the end of the existing pipe discharging into the vessel.
- o Redirect the discharge end of the pipe with the orifice to discharge toward the liquid and at a level near the vapor liquid interface.
- o Size and install mesh separator pads in the flash drums.

7.16.3 ANALYSIS OF RESULTS

No testing was performed. Because of the generally acceptable scrubber performance (See Section 7.4), this test was deferred.

7.17 ANALYSIS OF TURNDOWN CAPABILITY OF THE FLASH PROCESS (Task not completed)

7.17.1 OBJECTIVES

Determine minimum stable plant operating rate with isobutane, and pinpoint the specific plant hardware design items that are responsible for these limitations.

7.17.2 GENERAL TEST PROCEDURES

Reduce brine and isobutane flowrate in increments of 20% of design. Process conditions, stability and efficiency were to be recorded and analyzed.

7.17.3 ANALYSIS OF RESULTS

Specific test procedure was not accomplished due to test plan termination prior to isobutane operation. However, during operation with water as the binary fluid, turndown of the plant brine and binary fluid systems was accomplished. Operation at approximately 10 to 20% of brine design flowrate was not inherently unstable, but oscillations were significant.

7.18 LONG-TERM RUN UNDER BASELINE CONDITIONS (Task not completed)

7.18.1 OBJECTIVES

To determine the ability of the Niland Geothermal Plant to operate as a pilot plant with isobutane over a long period of time at established conditions representative of commercial power plant conditions.

7.18.2 TEST CONDITIONS

The plant was to be restored to its original clean condition. The operating conditions for the long-term run were to be the optimum set of conditions as established by all the preceding test runs. The optimum test conditions were to be those that result in stable operation, good performance, a minimum of required maintenance, and a minimum of unscheduled downtime.

7.18.3 ANALYSIS OF RESULTS

This testing was terminated as a result of the Feasibility Study.

7.19 REFERENCES

- 7.19-1 Awerbuch, L. et al, (Bechtel Corporation, San Francisco, CA), Detailed Test Program for the Niland Geothermal Test Facility, P.O. GTF-00049, #12012, September 1976.
- 7.19-2 Rogers, A. N., Letter to San Diego Gas & Electric, Subject: BPE and non-equilibrium determination, September 23, 1977.
- 7.19-3 Harrar, J. E. (LLL, California), LLL Geothermal Energy Development Program, Highlights Report, LLL Report ATHS/ISP 17, U.S. ERDA Contract W-7405-ENG-48, September 1978.
- 7.19-4 Quong, R., Schoepflin, F., and Stout, N. D., (LLL, California), Conditioning of Geothermal Brine Effluent for Injection - Use of Coagulants, LLL Report UCID-17716, U.S. ERDA Contract W7405-ENG-48, February 1978.
- 7.19-5 Chan, M., Tewhey, J., and Owen, Lawrence B., (LLL, California) "Process Dependent Characteristics of Scale from the GLEF Injection Line", LLL Geothermal Energy Development Program Highlights Report, Earth Sciences Feb. 14, 1978, LLL Report ATHS/ISP-11, U.S. ERDA Contract W 7450-ENG-48.
- 7.19-6 Otto, C. H. and Hill, J. H., (LLL, California) Sampling and Characterization of Suspended Solids in Brine from Magmamax #11 Well, LLL Rport UCRL-79007, U.S. ERDA Contract W 7405-ENG-48, June 1977.
- 7.19-7 Tardiff, George E., (LLL, California) Using Salton Sea Geothermal Brines for Electrical Power: A Review of Progress in Chemistry and Material Technology - 1976 Status, LLL Report UCRL-79468, U.S. ERDA Contract W 7405-ENG-48, May 1977.
- 7.19-8 Quong, R., (LLL, California) Scaling Characteristics in the Geothermal Loop Experimental Facility at Niland, California, LLL Report UCRL-5216, U.S. ERDA Contract W 7405-ENG-48, 1976.
- 7.19-9 Grens, J. Z. and Owens, Lawrence B., (LLL, California), Field Evaluation of Scale Control Methods: Acidification, LLL Report, U.S. ERDA Contract W 7405-ENG-48.
- 7.19-10 Owen, L. B. and Tardiff, G. E., ed. (LLL, California), LLL Geothermal Energy Development Program, LLL Report ATHS/ISP-17, U.S. ERDA Contract W7405-ENG-48, September 1978.

- 7.19-11 Bechtel National, Inc. and The Ben Holt Company,
Feasibility and Risk Study of a Geothermal Power
Plant at the Salton Sea KGRA, San Francisco and
Pasadena, California, May 10, 1978.
- 7.19-12 Awerbuch, L. et al, (Bechtel Corporation, San
Francisco, CA) Detailed Test Program for the
Niland Geothermal Test Facility, P.O. GTF-00049,
#12012, September 1976.

8.0 1978-1979 GLEF TEST PROGRAM (Two-Stage, Flash-Cycle Operation)

8.1 SCALE REMOVAL

Principal Investigators: D. G. Newell, C. A. Soderlund
(SDG&E)

8.1.1 OBJECTIVES

The objective of this test is to qualitatively evaluate the technical and economic effectiveness of various techniques for removing scale from brine piping, flash vessels and plant control components. Recommendations will be made of the best technique, or combination of techniques for use in various locations in a power plant. (Table 8.1-1)

The techniques evaluated are:

Chemical Cleaning (off-line cleaning, See Section 8.1.3)

Hydroblasting (off-line cleaning, See Section 8.1.4)

Hydroblasting (on-line cleaning, See Section 8.1.5)

Pigging (on-line cleaning, See Section 8.1.6)

Cavitation cleaning, which is similar to hydroblasting except that a specially designed nozzle in conjunction high pressure water supply is used to induce cavitation in the water jet and hence improve the cleaning efficiency, was tested at the GLEF by Daedalean Associates, Incorporated under a separate contract to DOE. The results of their work was reported separately to DOE.

8.1.2 BACKGROUND

The GLEF extracts heat energy from the saline and mineralized brines of the Niland reservoir by flashing relatively pure steam from the liquid brine. In this process, the temperature of the liquid brine is decreased and the concentration of minerals dissolved in the brine increases. Both of these actions cause the solubility limits of some of the various mineral species in the brine to be exceeded. The resulting precipitates form scale of varying composition. Scale forms in the process vessels, equipment, and piping at different rates depending on several factors including the temperature of the fluid. In general, metal sulfides predominate in scale that forms at higher temperature regions of the process, while silica predominates at lower temperatures regions. The metallic scales are very hard and difficult to remove, but form at a relatively slow rate. The silica scales, on the other hand, are usually quite soft and are easier to remove but form at a rapid rate. See Scaling Rate and Scale Properties, Section 8.2, and Brine Chemistry,

Table 8.1-1 Cleaning Techniques vs. Areas Used

SECTION TESTED	PIGGING	HYDROBLAST			CAVITATION CLEANING	
		w/Acid Cleaning	Only	Offline	Online	Offline
Lines						
Production			✓			✓
P-16A Suction			✓	✓		✓
1st-2nd Stage Drain Line	✓	✓	✓	✓	✓	
2nd-3rd Stage Drain Line		✓	✓			
3rd-4th Stage Drain Line		✓	✓			
Injection Line	✓	✓	✓			
Clarifier Feed	✓			✓		
Vessels						
1st Stage			✓			
2nd Stage			✓			
3rd Stage			✓			
4th Stage			✓			

Section 8.7 for discussions on the rate of scale formation, physical characteristics, and chemical composition of the scale in more detail.

As the scale builds up inside piping, flash vessels, control valves, and other plant components, the ability to handle the brine flow decreases to the point where the facility must be shut down for cleaning. At the GLEF, these shutdowns usually occurred before 1500 operating hours were achieved.

The Feasibility Study (See Section 9.1) concluded that a power plant should include redundant flash trains, so that one train could be taken out of service for cleaning without impacting full capacity of plant operation. Consequently, off-line as well as on-line descaling techniques needed to be assessed for technical and cost effectiveness.

This test was conducted to compile the information needed to compare the various scale removal techniques selected for use at the GLEF.

8.1.3 EVALUATION OF CHEMICAL CLEANING (Off-Line Cleaning)

8.1.3.1 Description of Chemical Cleaning

All chemical cleaning at the GLEF was performed by Southwest Chemical Company. The technique was based on work done in early field testing and was first used at the GLEF in November, 1976, to clean the brine piping between the first and second stage separators (in the four stage flash/binary configuration). It was later refined and used to remove the types of scale that formed in all other sections of GLEF piping. Chemical cleaning was also extensively used later to remove scale from plant components such as control valves, pumps, gate valves, etc.

The process of chemically cleaning a section of GLEF brine piping consisted of isolating the section of line to be cleaned, circulating a mixture of inhibited acids and chelating agent through the system for several hours. The section was then drained, rinsed, and the residual chemical neutralized. Chemical cleaning of plant components was generally accomplished by disassembling and removing the component and immersing components in successful chemical cleaning solutions in the shop. An alternate method of cleaning was by circulating the chemicals through the component in place.

The type of chemical used depended on the type of scale present. Generally, a mixture of chemicals consisting of primarily hydrochloric acid and chelating agents was used. Predominantly silica scales sometimes required the use of hydrofluoric-based acids or a heated caustic solution.

Because of the large volume of scale to be removed, (Figures 8.1-1 through 8.1-3), chemical cleaning of systems was normally used in conjunction with flushing or hydroblasting. Complete consumption or removal of the scale solely using chemicals would have been excessively expensive. By limiting the function of the chemicals to softening and/or loosening the scale, cost of chemicals could be reduced and subsequent mechanical removal made relatively simple.

8.1.3.2 Results of Chemical Cleaning

Chemical cleaning was found to be generally effective, but time consuming technique for softening geothermal scales. Flushing and rinsing were usually not sufficient to remove all scale from a surface. This procedure was generally followed by hydroblasting to remove the softened scale remaining after rinsing. During the early stages of GLEF operation, chemical softening was the only method of removing some of the harder scales that formed in the brine piping. However, as hydroblasting techniques became more refined, even the hardest scales could be removed by hydroblasting alone. Since the costs of chemical-softening any large volume of piping were also quite high and required subsequent hydroblasting, chemical-softening of brine piping was discontinued after mid-1978.

Chemical cleaning of disassembled plant components was used with good results. Under controlled shop conditions, the difficulties of handling large volumes of acids and caustic were minimized. Chemical cleaning resulted in removing scale from areas where clearance was minimal, but required removal, disassembly, reassembly and installation time and labor.

In-situ cleaning of plant components was used in an attempt to free a sticking control valve or descale the injection pump without removal and disassembly. The results of these attempts were generally encouraging, in that they helped prolong the operating time of the component before it had to be torn down and overhauled. However, the cleaning process appeared to be incomplete and required that the component be isolated from the process. The soaking, neutralizing, and rinsing times required were significant. In most cases, it would have been faster to replace the scaled component with a spare, thus reducing plant downtime.

8.1.3.3 Cost of Chemical-Cleaning

The costs of acid cleaning were significant for cleaning sections, unless redundancy was present, the entire brine-handling process had to be shut down (with resulting loss of revenue in a power plant) for the period necessary to chemically soften the scale as well as for subsequent hydroblast. For component cleaning the set-up and tear-down times for the equipment (as used at the GLEF) were usually

Figure 8.1-1 Scale In 2nd Stage Drain Line

Figure 8.1-2 Scale in 2nd Stage Drain Line

Figure 8-1-3 Scale In 2nd Stage Drain Line

longer than the time required for chemical circulation. The process also was labor-intensive, with attention at all times to ensure safe handling. The handling of large volumes of acid or caustic required careful planning and control of access. This made it difficult to schedule other maintenance activities in the area concurrent with chemical-cleaning and thereby increased cost.

The costs of chemically-cleaning any section of piping will depend on the thickness and type of scale; however, the costs of chemical cleaning at the GLEF can be used to provide a baseline estimate for the purposes of comparison with other cleaning techniques. An example of the cost of chemical-cleaning is provided for a 100 feet of 10 inch brine piping that was operated for approximately 1,000 hours and had accumulated a 2 inch thick layer of a predominantly silica (i.e. soft) scale, is shown as follows:

Labor: (mh is manhours)

16 mh disassembly	
18 mh setup	
148 mh circulate chemical	
8 mh rinse and neutralize	
16 mh reassembly	
106 mh Total x \$18/mh =	\$1,908.00

Material & Equipment:

400 gallons of chemicals (including neutralizing agent) @ \$2.00/gal = \$800.00

Total Cost/1000 hours of operation: \$2,708

The cost of chemical cleaning is compared with other scale removal methods in Section 8.1.7 "Comparison of Scale Removal Techniques."

8.1.3.4 Conclusions on Chemical Cleaning

Chemical treatment of brine pipe sections is an effective means of removing or softening very hard scales to be more easily removed by hydroblasting. However, as hydroblasting techniques were improved at the GLEF, the use of chemical softening was not required. Due to the high cost and problems with handling the chemicals, the use of chemical cleaning in brine piping was discontinued. Its use is not recommended for removing heavy scale from large piping sections except in areas where scale is thin and removal is complete or where hydroblasting cannot be used due to convoluted piping runs or obstructions.

Chemically cleaning scale from specific plant components that were removed from the system was shown to be effective and reliable. The extent of disassembly required varied with each component. Such items as spare gate valves,

control valves, and pumps can be disassembled and soaked in the cleaning solutions in a controlled environment without presenting the difficulties of handling the solution in the field and without interfering with operation of a power plant. This method appears to be especially valuable where a component is small with tight clearances between moving parts and full removal is required.

In-situ chemical cleaning of components did not prove to be a reliable method of fully removing scale. However, the method achieved partial success with limited testing and future work may result in an effective method.

8.1.4 EVALUATION OF HYDROBLASTING (Off-Line Cleaning)

8.1.4.1 Description of Off-Line Hydroblasting

Hydroblasting uses the kinetic energy of a high velocity water jet to remove scale or other undesirable material adhering to a surface. A high pressure pump is used to supply water to a nozzle designed to generate high velocities and concentrate the fluid jet into a small area. Flow rates in the hydroblasting system used at the GLEF were typically about 13 gpm and nozzle throat diameters ranged from .020 to .050 inches. The velocity of the water jet that impinges on the surface to be cleaned was approximately 1,000 to 1,100 ft/sec.

The majority of hydroblasting activities at the GLEF was performed by Southwest Chemical Company. Vessels and components were cleaned using a hand-held wand with a nozzle at its tip that produced a fan-shaped spray pattern. Figures 8.1-4 and 8.1-5 show the equipment typically used to clean the inside of a flash vessel and exterior of plant equipment.

To clean the inside of brine pipelines, a "mole" at the end of high pressure hose containing several nozzles was generally winched slowly through the pipe breaking the scale loose with high pressure water. The mole was rotated by either mechanical or hydraulic means. Figure 8.1-6 shows the equipment used for this operation. The travel rate of the mole was set by the thickness and hardness of the scale to be removed. In general, the thinner and softer the layer of scale, the faster the mole could be advanced.

The sequence for hydroblasting a section of brine piping was to: 1) remove blank flanges from access ports, if required. Access was also available if valves or spool pieces from either end of the section of line were removed; 2) string the winching cable through the section of pipe; 3) slowly winch the mole through the pipe, hydroblasting the scale while rotating the cleaning nozzles; 4) rinse the debris from the piping; 5) inspect; 6) remove the mole and winch cable and 7) replace access flanges. The amount of

Figure 8.1-4 Hydroblasting a GLEF Flash Vessel

Figure 8.1-5 GLEF Hydroblaster

Figure 8.1-6 Typical Equipment Configuration for Hydroblasting GLEF Brine Piping

time consumed in these activities varied depending on the length of pipe to be cleaned; and its configuration; as well as the type and thickness of the scale. However, rigging and rinsing times were generally greater than the amount of time spent hydroblasting.

8.1.4.2 Results of Off-Line Hydroblasting

Hydroblasting without prior chemical softening, was first used at the GLEF in early 1977 to remove softer scale from the injection piping. Between that time and project termination, hydroblasting was used on virtually every section of the brine piping. The hand-held hydroblaster was used extensively to clean the interiors of large flash vessels as well as most components in the GLEF such as valves, pumps, etc.

The results achieved were, on the whole, excellent. Complete removal of any type of scale could be achieved if the nozzle could be positioned so that the surface to be cleaned was within the effective range of the water jet. Occasionally, small areas of piping could not be completely cleaned because of poor accessibility.

There was, however, a considerable learning period, during which time several changes were made to nozzle configuration and the brine piping for access and drainage. As initially designed, the GLEF contained many long, convoluted piping runs with very few areas where the pipe could be disassembled at flanges. This caused many difficulties in rigging the winching cable and resulted in delays when the cleaning mole became stuck. Over a period of time, most of these trouble spots were located and sufficient access ports installed so that the lines could be cleaned. A piping configuration of up to four 90° elbows was found to be the approximate limit for effective cleaning. Long radius elbows were also found to reduce problems.

Another significant problem was rinsing, or flushing the scale residue. Residue would frequently block the mole, if care was not taken. The nozzle geometry had to both break and displace the scale. Again, a learning process was required.

8.1.4.3 Costs of Off-Line Hydroblasting

To allow a comparison of the costs of off-line hydroblasting with other scale removal techniques, an estimate will be made of the cost of cleaning a section of scaled brine piping, given the following assumptions:

- o Section to be cleaned is 100' long, 10 inch diameter;

- o Scale forms at injection line temperature 220°F (104°C) and is a relatively soft, predominantly silica scale;
- o 2 inch of scale are present on pipe walls after 1,000 hours of operation.
- o Pipeline is relatively straight.

The cost estimate summarized below is based on actual experience at the GLEF. It assumes that a three man crew is used, mole feed rates are unchanged from prevailing levels, that a source of water is available for hydroblasting, and that a means of disposal of the water is nearby.

Labor: (mh means manhours)

16 mh piping access disassembly

5 mh rigging

9 mh hydroblasting

3 mh rinsing

16 mh reassembling pipeline

49 mh total x \$18/hr = \$882.00

Equipment:

4 mh hydroblast unit @ \$80/hr = \$320.00

5.5 mh crew truck @ \$3.50/hr = 19.25

Total Cost: \$1,221.25

The costs of hydroblasting individual plant components cannot be generalized, since the type of component and the ease of access to it will determine how much time is spent on the job.

8.1.4.4 Conclusions on Off-Line Hydroblasting

The technical effectiveness of off-line hydroblasting has been amply demonstrated in the three years of experience with the technique at the GLEF. Every type of scale observed was removed from inside brine piping or from the surface of plant components. However, the desirability of selecting the technique on a commercial basis will depend on its costs. Providing access for hydroblasting for backup use in systems seems prudent.

The cost-effectiveness of off-line hydroblasting in a geothermal power plant will be largely dependent on the geometric configuration and accessibility of the piping to be cleaned. The amount of scale had a smaller influence on costs. Experience at the GLEF has demonstrated that: 1) the number of piping bends should be minimized; 2) long radius elbows should be used whenever possible; 3) ports or other access should be positioned to limit 90° bends, and 4) adequate water supply and drainage should be provided.

These actions greatly reduce the time and effort required to hydroblast brine piping.

8.1.5 EVALUATION OF HYDROBLASTING (On-Line Cleaning)

8.1.5.1 Description of On-Line Hydroblasting

On-line hydroblasting is similar to off-line hydroblasting except that the piping section or component is not removed from service. The major difference is that, since brine is flowing in the pipeline to be cleaned, some means of introducing the cleaning hardware and advancing the nozzles through the piping without leaking brine must be devised. At the time of project termination, techniques were being developed by Southwest Chemical Co. and Daedalean Associates, Inc. Although not always successful, results should not be directly compared to off-line results because of the limited experience.

The equipment used to seal the on line brine system from the high pressure water supply consisted of a packing gland or feed through mounted in a blank flange. A cleaning nozzle was mounted on the end of a straight, small diameter pipe or lance which was inserted through the packing gland.

In one configuration, the flange was attached to a valve aligned with the straight section of pipe to be cleaned. The valve was opened and the cleaning lance manually advanced into the scaled piping. The nozzles were rotated so that the water jets reached all areas of the piping. When the lance reached the end of its travel, it was withdrawn, the valve closed, and the flange removed from the valve.

Components were also modified by adding hydroblast nozzles. A thermal well, gate valve, and injection pump were periodically subjected to high pressure water impingement from these nozzles.

8.1.5.2 Results of On-Line Hydroblasting

The amount of experience with this cleaning technique at the GLEF was not adequate to conclusively evaluate it. On-line hydroblasting was used in two sections. The first was an attempt to keep the four to five feet of 12 in. pipe in the clarifier feed pump (P-16A and P-16B) suction lines free of the large volumes of soft silica scale that formed. The second, incorporating cavitation nozzles attempted to clean a few feet of first to second stage drain line. Most of the inspections of the test sections showed that some of the scale was removed, however, scale still remained.

The cavitation nozzles system performed somewhat better than the noncavitating system. This system did

remove all scale in the test section under nonflowing brine conditions.

Component scale removal was also partially successful. Some scale was removed, but not all. The thermal well test was the most successful leaving portions of metal exposed to the brine.

8.1.5.3 Costs of On-Line Hydroblasting

The total cost of operating on-line hydroblasting was higher than the cost of off-line hydroblasting, primarily due to the frequency, lengthy set-up times and special tooling required. However, on-line cleaning is still in its infancy, so costs should become lower as improvements are made in the equipment and handling techniques. Therefore, a comparison of the costs of on-line hydroblasting with other techniques would not be valid at this time and is not included in this report.

8.1.5.4 Conclusions on On-Line Hydroblasting

The difficulties encountered in removing scale with this technique are apparently due to the nature of the hydroblasting process and the new application. The water jet produced concentrates a great deal of energy into a very small area. Consequently, the water jet is most effective within a narrow range. The moving brine tends to dissipate the energy unless the nozzles are carefully positioned.

The packing gland that was used apparently did not allow precise positioning of the nozzles relative to the pipe walls. In addition, because the system was not inspected prior to each cleaning operation the thickness of the scale to be removed was not known. Consequently, the cleaning operation was conducted "blind".

On-line hydroblasting is a technique that might be useful in removing scale build-up from critical areas of brine piping without shutting the plant down. However, the technique is still in its infancy and needs to be further developed before it can be relied upon to remove scale accumulations dependably. Improvements are needed in methods of controlling the nozzle location within the pipe and ascertaining its effectiveness.

This technique appears to have limitations. Because of the cleaning lance that was used to advance the nozzles through the packing gland, the pipe must be straight. This limits the application to straight piping that can be cleaned to the length of the lance that can be handled in the area surrounding the pipe to be cleaned. One method that could be used to overcome this problem would be to install the nozzles on the end of a strong, coiled spring steeltube of the type used in the well service industry or

self propelled moles. However, this would add to the cost. The usefulness of on-line hydroblasting can be significantly increased if a means could be developed to maneuver hydroblasting nozzles around piping bends with brine flowing through the pipeline.

Component cleaning appears to have a good potential for success although not fully demonstrated at the GLEF. Critical instrumentation, control sensors, static or rotating seals could be kept operational by this technique.

If large sections are to be cleaned using this technique, the impact of the debris generated on downstream equipment must also be evaluated. Large sections of scale broken loose could easily cause major problems in an on-line plant.

8.1.6 EVALUATION OF PIGGING (On-Line Cleaning)

8.1.6.1 Description of Pigging Operation

Pigging is an on-line technique for removing pipeline scale that has been used for years in the petroleum and chemical process industries. It was first used at the GLEF in June, 1977, to prevent the accumulation of scale in the injection pipeline.

The equipment required for pigging at the GLEF shown in Figure 8.1-7. A launcher is used that is one or two pipe diameters larger than the process piping so the pig can be easily inserted. A pig is pushed to the front of the launcher, a spacing spool (to ensure that the pig is forced to the front of the launcher) inserted behind the pig and the launcher sealed. Next, the launcher block valve is opened completely. A source of pressure higher than in the line to be pigged is used to launch the pig. While the required launching pressure will depend on the launcher configuration and type of pig used, pressures 20 psi higher than the line pressure were usually adequate at the GLEF. Brine from the nearest source higher in pressure than the line to be pigged was used, which generally provided pressure much higher than the minimum required for launching). The launching valve was then opened. A successful launch was evidenced by the sound of the pig entering the line and by observing pressure drops on the launcher gauges. A pig signal indicator that shows visual, electrical, or pneumatic indication of pig passage are commercially available. However, these other indicators were not used at the GLEF due to the problems caused by scale formation on any intrusions into the flow stream. Once the pig entered the brine piping, the launching valve was closed, followed by the launcher block valve. The pressure in the launcher was reduced by opening the ambient bleed valve so that the end cap could be safely opened prior to the next launching.

PIG LAUNCHER

PIG RETRIEVER

Figure 8.1-7 Typical Equipment Used for Pigging

Once in the process piping, a blockage forms between the pig and the walls of the pipe, producing a pressure drop that propels the pig through the line. The scale on the pipe walls was generally removed by mechanical abrasion. Unless it encountered an obstruction, the pig traveled at a speed slightly less than the average fluid velocity.

Once the pig reached the end of the pipeline, it was retrieved using equipment nearly identical to that in the launcher. Well before the pig reached the retriever, the flow was diverted through the retriever by: 1) inserting a spacing spool into the retriever; 2) closing and sealing the end cap; 3) closing the ambient bleed valve; 4) opening the retriever outlet valve; 5) opening the retriever block valve; and 6) closing the brine line block valve. The arrival of the pig was detected by the sounds, and by observing the build-up in pressure in the receiver gauge or by a pig signal indicator. The flow was returned to normal: by 1) opening the brine flow block valve; 2) closing the retriever block valve; 3) closing the retriever outlet valve; and 4) opening the retriever ambient bleed valve. Once the pressure was reduced to ambient, the pig was removed by: 5) opening the end cap.

The entire pigging operation typically required one or two men for about one-half hour for launching and retrieving plus the transit time in the piping system.

8.1.6.2 Description of Pigs Used at the GLEF

The term "pig" is used here to identify any device that is inserted into and propelled by fluid pressure through a pipeline for the purpose of removing scale accumulation on the pipe wall. In the simplest terms, the pig is an object capable of forming a seal against the inside wall of the pipe sufficient to cause a pressure drop large enough to force it to move with the flow stream. Some mechanism for mechanically removing the scale must also be included.

Two different manufacturers supplied the GLEF with two styles of pigs. Girard Polly-Pig, Inc. of Houston supplied its version of the Polly-Pig, a cylindrically shaped, dense polyurethane foam core coated with solid polyurethane and usually wrapped with an abrasive surface (wire brushes or carbide grit) for scale removal. Figures 8.1-8 and 8.1-9 show the various types of Polly-pigs used at the GLEF. In addition, Girard also supplied uncoated lightweight foam swabs that were launched occasionally to remove debris from the piping or to provide a more effective seal behind a stuck Polly-pig.

Figures 8.1-10 and 8.1-11 show one of the two models of "articulated" pigs that were tested at the GLEF. These were manufactured by T. D. Williamson Co. of Signal

Figure 8.1-8 Girard Polly Pig

Figure 8.1-9 Girard Polly Pig

Figure 8.1-10 T.D. Williamson Wire Brush Pig (Used)

Figure 8.1-11 T.D. Williamson Wire Brush Pig (Used)

Hill, Ca. These devices consist of two short pigs connected by a universal joint and a steel spring. This joint allows the pig to flex and therefore pass through piping bends more easily. The articulated pigs extensively used metals for structural portions and are therefore more durable than the Polly-pig. Elastomeric materials are used for the cups to provide an effective seal with the pipe wall. These can be replaced when they deteriorate sufficiently to degrade performance. Wire brushes on the Model WCK-3 and plastic scrapers on the Model WCB-3 are held against the pipe walls with a flat spring to remove the scale.

8.1.6.3 Results of Pigging

Between June, 1977 and plant shut down in September, 1979, pigging was evaluated in three locations of the GLEF and in two different brine environments. Table 8.1-2 shows the conditions under which each type of pig was used.

Injection Piping

The first location in which pigging was evaluated was the injection pipeline from the GLEF injection pump discharge to the open settling tanks located near Magmamax No. 3, a distance of about 4000 feet. The 10 inch pipeline also contained five standard 10 inch gate valves, 40 standard radius 90° elbows and eight 10 inch 45° elbows. In addition, four 10 inch 90° tees and several smaller diameter tees branched off the main line. A flat piece of bar stock was placed across the entrance to each branch to prevent the pig from being deflected into the wrong line. After hydroblasting the entire injection line in May, 1977, to remove accumulated scale, a program of pigging was established. Except for a relatively thin layer, this line was kept virtually free of scale from June, 1977, to July, 1979 by pigging. After July, the brine was treated by the clarifier/ filter system and pigging was halted because the rate of scale formation was substantially reduced.

During the first several months that pigging was attempted in the injection line, substantial damage was done to almost every pig. The GLEF injection pipeline was not designed for pigging and consequently numerous line obstructions were present. Over a period of time, most of these obstructions were located and removed. Weld beads, thermowells that had previously been abandoned in place, and sharp corners on the branches of piping tees all caused damage to the pigs. Once the obstructions were removed and the branches of tees were blocked with guide bars, damage to the pigs decreased.

All four types of pigs (Girard wire brush and carborundum strap Polly-Pigs and T. D. Williamson Models WCK-3 and WCB-3 articulated pigs), were used in the injection pipeline. The Polly-Pigs were used exclusively from

Table 8.1-2 Results of Pigging at GLEF

	INJECTION LINE 4000 ft. long Temperature: 220°F Avail. Press.: 550 psig	CLARIFIER FEED LINE 245 ft. long Temperature: 220°F Avail. Press.: 48 psig	1ST TO 2ND STAGE BRINE LINE 90 ft. long Temperature: 360°F Avail. Press.: 330 psig
GIRARD POLLY PIG	Pipe kept free of almost all scale build up	Pipe kept free of almost all scale build up	Pig incapable of withstanding temperatures: Failed completely
T.D. WILLIAMSON ARTICULATED PIG	Pipe kept free of almost all scale build up	Polyurethane cups used worked well	Polyurethane cups deteriorated severely due to temperature. Viton cups did not deteriorate as rapidly, but had short service life due to softening

June, 1977, to March, 1978. After that time, they were used alternately with the articulated pigs. The wire brush and carborundum strap Polly-Pigs were usually launched alternately into the injection line and were very effective in removing the small amounts of scale that formed between the daily pigging operations. Each Polly-pig typically had a useful life of five launchings before requiring replacement. After that time, abrasion from patches of hard scale that were left in the line by hydroblasting, cuts and gouges caused by weld beads and slag, and normal frictional wear deteriorated the dense polyurethane coating to the point where further use would result in disintegration of the pig (Figure 8.1-12 through 8.1-14). The articulated pigs were more durable due to their mostly metal construction. However, the Model WCB-3 scraper pig was not very effective in removing scale and was easily damaged. The WCK-3 wire brush pig was reused many times at the GLEF with periodic replacements of the elastomeric cups used to provide a seal with the pipe wall. As with the Polly-Pig, the cups were damaged primarily by weld beads and hard scale patches. Urethane cups were initially used in the injection line, with good results. Later in the program of evaluation, Viton cups were installed on the pig for evaluation in the higher temperature of the 1st stage drain piping. This material was also used in the injection line but was not required for the relatively low temperatures there.

The articulated pigs had more difficulty traversing the pipeline than did the Polly-pigs. The articulated pigs were more likely to become caught on pipe obstructions and their segmented spring loaded brushes (or scrapers) would occasionally penetrate into a branch line and become stuck. In such instances, a Polly-pig, or foam swab, whose non-segmented construction reduced its chances of becoming stuck in the branch line, would be launched behind the articulated pig to form a more effective seal. This was usually sufficient to dislodge the articulated pig, but usually caused damage to both pigs.

Foam swabs were used initially to remove sediment from the piping that was previously dislodged by a pig. However, little sediment was left to remove with the swabs. They were more effectively used to provide a better seal behind caught pigs. Because of their lightweight construction the swabs were invariably damaged after one launching and were discarded.

Clarifier Feed Line

The clarifier feed line contained brine at the same conditions as the injection line (about 220°F or 104°C). The section of piping that was pigged began at the discharge of the clarifier feed pumps (P-16A and B) and ended near the inlet to the clarifier/filter (V-17). The total pipe run was 245 feet long and contained eight 10 inch diameter x 3R

Figure 8.1-12 Damaged Polly Pig

Figure 8.1-13 Damar Polly Pig-1st-2nd Stage

Figure 8.1-14 Damaged Polly Pig-1st-2nd Stage

elbows and two 10 inch WKM through conduit block valves. In addition, three 10 inch diameter tees branched off the main line with a single guide bar blocking the branch of each one.

Pigging of this line began with clarifier operation in June, 1979, and continued on a daily basis until plant shutdown in September, 1979. The line was designed with long radius elbows and care was taken to minimize flow obstructions in the construction of the piping. Consequently, this section of line was kept essentially free of scale with only infrequent damage to the pigs other than that caused by normal wear.

1st to 2nd Stage Brine Piping

This pigging system was installed at the time of conversion from the four stage flash/binary cycle to the two stage flash cycle in July, 1978. The section of the piping that was pigged began at the outlet of the 1st stage B train flash vessel (V-4) and ended just upstream of the control valve (LCV-714) near the inlet of the 2nd stage flash vessel (V-11). The total pipe run was 90 feet long and contained two 10 inch diameter x 3R elbow, and four 10 inch standard gate valves. In addition, three 10 inch diameter tees branched off the main line with a single guide bar blocking the branch of each. At the point where the pig was diverted to the receiver, a 45° branch was used. The pigs were guided into the branch by a bar placed across the run of the pipe. This configuration produced a sharp-edged corner which had a high potential to damage the pigs.

The pigs used at the GLEF were not suited for application in brine environment, 360°F (182°C) saturated liquid brine. The polyurethane Polly-pigs melted during the one or two minute trip through the pipeline. An articulated pig was then tried. The mostly metal construction allowed it to transit the pipe without disintegrating. However, its polyurethane cups did soften from the heat and were badly damaged.

At this point, further pigging was postponed until a higher temperature elastomer could be obtained for use in the cups of the articulated pig. A Viton material was obtained from the manufacturer and installed on the pig. The initial run of the pig indicated that the Viton was capable of withstanding the temperature. However, the Viton also softened considerably and was easily damaged on subsequent runs by line obstructions. Because of this damage, pigging of the first to second stage drain line was discontinued until another, more durable elastomer could be found.

At the time the GLEF shut down in September, 1979, no available material had been found that would withstand the 360°F (182°C) temperatures and maintain its strength.

8.1.6.4 Costs of Pigging

The cost-effectiveness of pigging will depend on the exact conditions under which a pig must function (line size, length, number and type of bends, obstructions in the line, etc.), as well as the durability and price of the particular pig used. However, in order to compare the cost of pigging with other scale removal techniques, the following conditions will be assumed: 1) the line to be pigged is 100 feet long and was designed for pigging; 2) the cost of the launching and receiving equipment is negligible on a per use basis; 3) a predominantly silica (i.e. soft) scale forms in the piping at the rate of 2 in. per 1000 hours of operation, 4) the line is pigged once per day; 5) each pig (costing \$150 each) is used for ten launchings before being replaced (this is a conservative figure anticipated from the observed lifetime of five launchings in a 4000 feet line not designed for pigging) and 6) the total labor required each day for pigging is 1 manhour. The cost of pigging the line during 1000 hours of operation can then be determined as follows:

Labor: 1 mh/day x \$15/hr x 1000/24 = \$ 625.00

Material: 1 pig/10 days x \$150/pig x
1000/24 = \$ 625.00

Total Cost of Pigging/
1000 hours of Operation: \$1250.00

The cost of pigging is compared with other scale removal techniques in Section 8.1.7 "Comparison of Scale Removal Techniques".

8.1.6.5 Conclusions on Pigging

Experience at the GLEF has shown that commercially available pigs can virtually eliminate scale accumulation in a properly designed piping system containing Niland brines at 220°F (104°C). The lifetime of a pig under such conditions will depend upon the type of pig used, and the difficulty it encounters in negotiating the piping system. The average lifetime for the pigs used in the injection pipeline (which was not designed for pigging) was 5 launchings for the Girard Polly-pig. The T. D. Williamson WCK-3 articulated pigs survived slightly more launching before the sealing cups needed to be replaced. The lifetime of these same pigs in the clarifier feed line (which was designed for pigging) was considerably longer because less damage resulted from obstructions in the piping. Also, pigs that used wire brushes to remove scale were more effective than scraper-type pigs on the soft injection line scale.

The success of pigging in the higher temperature brines of the first to second stage piping 360°F (182°C) was only marginal. Viton material that was used in the sealing

cups of the T. D. Williamson articulated pigs softened at these temperatures and was easily damaged in transit. Discussions with vendors produced no suitable materials for use at these temperatures.

If pigging is to be used extensively at temperatures much higher than 220°F (104°C), a elastomeric material must be found that will retain its strength and durability at the planned operating temperatures. Alternatively, a pig might be designed without elastomeric materials of construction perhaps an overlapping fan-type configuration of high temperature plastics with sufficient flexibility to provide an adequate seal with the pipe wall.

Pigging can be used to the best advantage in a piping system that has been designed for that purpose. A pig can be held up and/or damaged by obstructions in the line. Thermowells, branching tees or line restrictions can hinder the pigging operation. Consequently, the piping should have no instrumentation protruding into the flow stream, no sharp-edged restrictions, and as few restrictions of any type as possible. When tees are required, the line to be pigged must be in the run of the tee and not the branch. A 45° branch at an acute angle to the path of the pig is preferable. To prolong the life of the pig, a bar across the line to the branch of the tee is required. A branch with a smaller diameter than the line being pigged is also highly desirable. The piping should also be as straight as possible, as elbows tend to deform the pig, reducing its useful life. Where bends in the piping are required, long radius elbows will extend pig life and help prevent it from becoming stuck.

8.1.7 Comparison of Scale Removal Techniques

Three of the scale removal techniques discussed above vary widely in cost as shown in the estimates for removing 2 inches of soft silica scale (or in the case of pigging, preventing that scale build-up) from a 100 foot long, relatively straight brine pipeline. In summary, these costs are:

Chemical Cleaning (Off-line)	\$2,708/1000 hr
Hydroblasting (Off-line)	\$1220/1000 hr
Hydroblasting (On-line)	Not estimated*
Pigging (on-line)	\$1250/1000 hr.

Pigging would be the preferred method of scale removal for this line because its use does not require that the piping system be isolated from the brine flow.

*On line hydroblasting is not suited for cleaning long sections of piping at this time, so its costs were not estimated.

However, no single technique can be recommended to the exclusion of the others. Each has its own strengths and weaknesses. The selection of the best to use will depend upon the specific conditions present in the piping system to be cleaned. To aid the designer of geothermal brine piping systems, the strengths and weaknesses of each technique are listed below.

CHEMICAL CLEANING

Strengths:

- o Can clean convoluted, not readily accessible, sections of piping or plant components containing restrictions that would prevent other techniques from being used.
- o Can be used to soften very hard scales for easier removal by other techniques.
- o Can be used to clean plant components such as control valves, pumps, etc. off-site.
- o Can be used to clean plant components in site (after isolation from the brine flow).

Weaknesses:

- o Piping section to be cleaned must be isolated, thereby shutting down power plant unless redundant systems are installed.
- o Cost of cleaning large volumes of scale in piping systems are prohibitive, due to high cost of chemicals.
- o In interval between cleanings, scale accumulations restrict flow in pipeline.
- o Scale removal is not usually complete with chemical cleaning alone.
- o Handling chemicals poses potential occupational safety hazard.
- o Access must be restricted to area surrounding piping being cleaned, thereby making coincident maintenance of nearby components difficult.
- o Waste handling and disposal costs may be significant.

OFF-LINE HYDROBLASTING

Strengths:

- o Can remove 100% of accessible scale deposits.
- o Less expensive than chemical cleaning.
- o Can be used for cleaning plant components as well as brine piping.

Weaknesses:

- o Piping section to be cleaned must be isolated thereby shutting down power plant unless redundant systems are installed.
- o Line must be opened up so that cable can be rigged inside pipe.
- o Cannot easily tolerate restrictions in pipeline (an increasing number of piping bends impedes the nozzle's advance).
- o Substantial number of access posts are needed, thereby increasing initial cost of piping system.
- o In interval between cleanings, scale accumulations obstruct flow in pipeline.

ON-LINE HYDROBLASTING

Strengths:

- o Can be used on an operating piping system.
- o Can be used on specific, critical areas of piping system or on specific plant components.
- o May be less costly than chemical cleaning.
- o If used frequently, can keep piping section free of scale build-up.

Weaknesses:

- o At present stage of development, use is limited to short, straight piping sections or to specific areas of plant components.
- o Scale removal may not be complete due to difficulty in precisely directing nozzle jet.
- o Has not been developed to same extent as other techniques.

PIGGING

- Strengths:
- o Can be used on an operating piping system.
 - o As length of pipeline to be cleaned increases, cost per unit length goes down.
 - o Prevents scale build-up (i.e., pipeline is essentially always free of scale).
- Weaknesses:
- o With presently available pigs, use is limited to about 220°F (104°C) brine lines.
 - o Cannot tolerate obstructions in flow stream (such as thermowells) and pigs are likely to be damaged by branching lines.

8.1.8 OVERALL CONCLUSIONS

The operation of the GLEF provided an opportunity to investigate alternative means of scale removal. The techniques developed and refined should have broad applicability to other geothermal reservoirs other than Niland. The following recommendations are based on SDG&E's experiences.

Chemical cleaning is of marginal value and should not be used to clean brine piping except as a last resort. A well-designed piping system should include provisions for use of other cleaning techniques. Chemical cleaning can be used to remove scale from plant components in-situ, but again, should be used as a last resort. The merits of chemically cleaning disassembled plant components need to be weighed case-by-case to determine desirability.

Off-line hydroblasting is proven technique for removing scale deposits from brine piping and disassembled plant components. However, because it requires shutting the facility down or building redundant systems, its use should be limited to critical sections that cannot be cleaned by pigging (such as piping near control valves and the control valves themselves) or as a backup.

On-line hydroblasting has not been developed sufficiently for widespread application in a power plant. However, because it is an on-line technique, it could be used to keep critical portions of plant piping free of scale. Brine piping systems should be designed with eventual incorporation of this techniques in mind.

Pigging should be the scale removal technique of choice for power plants because it is an on-line techniques. With additional development work, pigs capable of withstanding temperatures above 220°F (104°C) should be developed. Once this temperature limitation is overcome, pigging should be incorporated into every possible area of plant piping.

8.2 SCALING RATE AND SCALE PROPERTIES

Principal Investigators: Suzanne B. Deutscher, Roland Quong,
Donna M. Ross, Jackson E. Harrar
(Lawrence Livermore Laboratories)

8.2.1 OBJECTIVES

The objectives of this test were to measure the amount of scale that formed in various sections of the GLEF and to evaluate the mineralogical and mechanical properties of that scale in connection with the effort required to remove it. This information will be used to help size piping and vessels, and to indicate the frequency of cleaning for the 50 MW power plant proposed for the Niland reservoir.

Scaling rates will be measured at the approximate conditions present in each of the following areas:

1. Production line piping;
2. 1st to 2nd stage piping;
3. 2nd stage to atmospheric flash drum piping;
4. Atmospheric receiver drain line;
5. Injection line piping.

Scale samples from each of these areas will be analyzed for mineralogical properties, as well as for mechanical properties such as hardness, adherence to wall, etc. In addition to obtaining scaling rates and conducting scale analyses, various chemical solvents will be tested as a means of enhancing scale removal with possible on-line application.

8.2.2 BACKGROUND

Deposition of scale in separators, piping, and critical components continued unabated at the GLEF as a result of flashing Niland brines. The removal of scale from GLEF piping and components became a time consuming and costly plant maintenance item. Although acidification of the brine to help control scaling had been successfully demonstrated, accompanying effects such as accelerated corrosion characterized this method as too risky for the current application. An alternative and promising chemical method for scale control was the use of organic inhibitors. This method is extensively evaluated in Section 8.3. However, until a scale control method was successfully demonstrated both technically and operationally, it was necessary to periodically descale the plant. The chemical and physical properties of the scale and the rate at which it forms dictated the selection of methods and frequency of removal. Methods of removal are evaluated in Section 8.1. The properties of the scale and the rate of deposition were evaluated in this section of the test program. Much of the previous work at the GLEF on scaling rate and scale properties remains

applicable (See Ref. 8.2-1 through 8.2-3). However, the effects of the changeover to a 2 stage flash process and of the use of brine from the reworked Woolsey No. 1 yet were to be determined.

8.2.3 TEST DESCRIPTION AND PROCEDURE

8.2.3.1 Test Materials and Equipment

Testing was carried out at the GLEF. At the GLEF, 4 feet long scaling spools of the same material and diameter as the lines in which they are located were the test specimens. Spools were located in the separator drain lines, the atmospheric flash tank drain line and in an unpigged portion of the injection line downstream of the clarifier-filter system. The spools were horizontal and easily accessible. Where spools were not available, the plant piping by necessity will be used to satisfy the test objectives. No additional plant equipment is required assuming flowrate, temperature, and pressure are being measured and recorded at reasonable frequencies throughout the plant.

Chemical methods of scale removal were tested using conventional laboratory equipment. If such a chemical was to be discovered, on-line tests were to be conducted at the LLL 2-stage flash system. Figure 8.2-1 is a schematic diagram of this system which included a control channel with scale from testing of scale control additives as described in Section 8.3. Removal of this scale was the basis for the on-line scale removal test by chemical methods.

8.2.3.2 Test Prerequisites

In order to conduct an on-line test of a chemical for scale removal, at least one channel of the LLL test system (Figure 8.2-1) was to have been scaled during conduct of Test No. 3.0 (See Section 8.3). Otherwise, there are no other tests which need to be performed prior to or in conjunction with this test.

8.2.3.3 Test Conditions

At the GLEF, constant (and preferably full design) flow and temperature was to be maintained in the plant during the operational period between each inspection of the spools. Flow variations of no more than $\pm 10\%$ from the mean were desirable, but $\pm 20\%$ was acceptable. Temperature within $\pm 5\%$ of the mean was required. Flashing in liquid drain lines should be minimized. Flow from Magmamax No. 1 and Woolsey No. 1 was to be restricted to their respective trains. During the test period, scale in the lines upstream and downstream of the spool sections was not to be disturbed. If scale removal is necessary, then the spools themselves should also be cleaned.

Figure 8.2-1 Scale-Control Test System

8.2.3.4 Required Data & Observations

Data was to be obtained from the scaling spools located in the production line, in the drain lines of each separator stage, in the atmospheric receiver drain line, and in the unpigged portion of the injection line. During each inspection period, scale thickness hardness, adherence, and density was to be measured/observed and recorded. Scale thickness at different points along the spool perimeter was to be measured using rulers and micrometers. Scale hardness was to be measured by using an ASTM Shore A, D, & O Hardness apparatus. Adhesion was defined as the lateral force per unit contact area to dislodge a piece of scale from a surface. Density will be determined by combined gravimetric and volumetric measurements on a sample. Scale mineralogy was determined by X-ray diffraction analysis. Occasional chemical analysis by X-ray fluorescence, emission spectroscopy, or atomic absorption was expected to be necessary.

Corresponding plant operational data was also to be recorded. These include the usual plant data such as flowrate, temperature, and pressure at each and every flash stage, and brine chemical composition and pH.

The type and amount of chemicals used in the scale dissolution/removal tests was to be recorded along with a narrative of effectiveness. The on-line tests were to require measurement of scale thickness at the start of the test and again at the completion of the test. The rate of chemical usage was to be documented.

8.2.3.5 Test Duration

A 30-day test period with fluid flowing from Magmamax No. 1 and Woolsey No. 1 through their respective trains either simultaneously or separately was required. A second 30 day period was expected to be allowed for reruns. An additional 30 days was expected to be allowed for data analyses and preparation of results. The scale removal test at the LLL facility was anticipated to be completed within 2 days.

8.2.4 RESULTS

8.2.4.1 Expected Results

The data obtained from the GLEF was to provide at the minimum scaling rate and scale properties, both chemical and mechanical for a 2-stage flash process utilizing Magmamax No. 1 and Woolsey No. 1 brines.

Evaluation of scale removal techniques (See Section 8.1) is an important part of this test program. Knowledge of scale mineralogy, hardness, adherence, and density may influence removal methods. If a chemical for scale dissolution

is found, then adopting this for on-line scale removal may be possible.

It was expected that these data will enable designers to make a more accurate estimate of scaling rate and scale properties in a 50 MW plant and hence reduce the risk of having an inadequate scale maintenance program and the associated uncertainty.

8.2.4.2 Data and Observations

Experimental Procedures

After the operation of the GLEF with Magmamax No. 1 brine for 1351 hours, ending in September 1978, six samples of scale were removed from various points in the plant as shown in Figure 8.2-2. In March 1979, after 904 hours of operation with Woolsey No. 1 brine, 5 samples of scale were removed, the locations of which are also shown in Figure 8.2-2.

These samples represent scale deposited during two major periods of GLEF operation. Intermediate shutdowns for scale thickness measurements and sampling were not scheduled because of other higher priority tests and hence are not available. Scaling rates were determined by thickness measurements of scale in pipes at the GLEF and from scale samples. Scale properties measurements and dissolution tests were carried out with the above described samples. Also included in the dissolution experiments was a sample of Magmamax No. 1 wellhead scale obtained early 1978.

The samples designated V-11 Top and V-11 were taken, respectively, from above and below the brine level of the second stage separator. The appearance of the scales ranged from very wet and soft (V-11) to very hard and dry (wellhead). The scales were rinsed, dried in a vacuum desiccator, and ground with a mortar and pestle.

A 1-gram sample of the prepared scale was mixed with 100 ml of the solution of interest, using a polyethylene-coated overhead stirrer. Stirring continued throughout the experiment. Solutions run at 176°F (80°C) were allowed to warm before addition of the scale and were kept warm during the experiment with hot plates. After the allotted time had elapsed (1, 4, or 24 hours) the mixtures were filtered through tared Whatman No. 541 filter paper. The filtrates were collected and the residues rinsed and allowed to dry for 2 days. A blank was run with each set by omitting the addition of the scale. The dried filter papers containing the residues were weighed, the amount of dissolution calculated, and the residues together with the filtrates reserved for further analysis.

Figure 8.2-2 Schematic Diagram of the Geothermal Loop Experimental Facility. Scale Sampling Points are Indicated on the Diagram.

8.2.4.3 Results

The scales can be divided into three general types: from the wellhead (or production line in the case of the Woolsey scales), from the first stage separators, V-4 and V-1, and from the 2nd stage separators, V-11 and V-14. The V-15 atmospheric receiver scales fit into the 2nd stage separator group. The analyses of these scales are given in Tables 8.2-1 and 8.2-2. These data indicate that wellhead and production line scales are primarily lead sulfide (PbS) with small amounts of silica (SiO_2) and ferric oxide (Fe_3O_4). V-1 and V-4 scales are mainly SiO_2 , Fe_3O_4 , and some PbS ; while V-11, V-14 and V-15 scales are mostly SiO_2 . Silica in all the scales is amorphous.

The results of the dissolution experiments are given in Tables 8.2-3 and 8.2-4. Figures 8.2-3 through 8.2-14 are plots of percentages of a specific scale dissolved versus the type of reagent used. The reagents selected were based on existing knowledge of the mineralogy of scale deposited at the GLEF. The concentrations used would be considered "safe" in an in-plant situation. In addition to common laboratory solvents, a solution of inhibited acrolein (2-propenal) marketed as Magnatreat M by Magma Corp. was tested on V4 scales. Magnatreat M is used to remove iron sulfide deposited at the formation surface in oil-field injection wells. In all cases the Magnatreat was less effective than water.

Scaling rates were determined by dividing scale thickness by total operating time. Scaling rates may actually vary considerably from the onset of exposure of a clean surface to brine to a point in time when heavy scaling has occurred. Scaling rates may be very low during an initial induction period when, for example, a pipe surface is relatively smooth and noncorroded. After the surface is scaled, a constant scaling rate should prevail. However, as the scale layer thickens and the open cross section of the pipe is reduced, the brine flow dynamics began to change significantly toward more turbulence and larger temperature and pressure losses. This results in an accelerated rate of scaling, that quickly leads to a required shutdown for cleaning.

The hardness of the Woolsey scales were measured with a Type A durometer, an instrument which conforms to ASTM 2240-75 specifications. The hardest scales are the galena based scales deposited in the production line preceding the first flash stage. The hardness of scales decrease progressively further downstream. Beyond the atmospheric receiver, the scales were too soft to be measured on the A-scale durometer. Although these scales have the consistency of mud, they do deposit as a coherent layer in the equipment and piping.

Table 8.2-1 Composition of Scales for the GLEF After Operation With Brine from Woolsey No. 1 and Magmamax No. 1

Concentration, Wt %, in scale from:

904 hours Operation with Woolsey No. 1 brine Sampled in March 1979						1361 hours with Magmamax No. 1 brine Sampled in September 1978						
Element	WPL	W1A-in	W1ADS	W2ADS	WV15OUT	Wellhead	V4	V4D	V11TOP	V11	V11D	V15
SiO ₂ ^b	0.15	33.0	40.4	78.7	52.6	4	25.8	23.6	66.4	57.2	70.3	63.8
Sb	7.1	0.22	0.41	0.15	0.28	12	2.6	2.0	0.32	0.24	0.28	0.86
Cl ^b	0.12	2.6	2.0	1.1	3.4	-	3.5	2.5	0.89	4.8	3.2	3.8
K ^b	0.08	1.6	1.1	0.76	2.0	-	1.6	1.7	0.58	1.09	0.96	0.89
Ca ^b	0.20	3.3	1.6	1.1	4.5	0.2	3.6	2.4	1.08	2.9	4.4	1.9
Ti ^b	-	-	-	-	-	0.03	-	-	0.01	0.008	0.07	0.08
Mn ^b	0.41	2.0	2.5	0.33	0.37	0.03	1.2	1.1	0.67	0.16	0.65	0.06
Fe ^b	≥8.2	≥13.	≥14.	2.0	1.8	0.07	17.7	11.6	12.5	0.88	0.68	0.92
Cu ^b	0.25	0.42	0.43	0.08	0.18	0.02	0.28	0.10	0.38	0.05	0.04	0.32
Zn ^b	0.11	0.11	0.13	0.12	0.13	0.70	1.02	0.26	0.17	0.07	0.15	0.06
Rb ^b	0.10	0.02	0.01	0.008	0.01	-	-	-	-	0.004	0.004	0.005
Sr ^b	.00	0.07	0.03	0.05	0.09	trace	0.11	0.07	0.02	0.05	0.04	0.04
Ag ^b	-	-	-	-	-	0.34	0.12	0.09	0.01	0.01	0.01	0.009
Sb ^b	-	-	-	-	-	trace	0.04	0.01	0.12	0.01	0.005	0.006
Ba ^a	0.1	0.15	0.2	0.6	0.4	-	0.1	0.05	0.03	0.02	0.3	0.3
Pb ^b	≥20.0	1.0	2.3	0.12	0.40	~.76	15.1	16.0	3.6	0.50	0.48	0.32
As ^b	0.19	0.09	0.12	0.05	0.02	-	-	-	<0.2	<0.04	<0.01	≤0.01
Na ^a	0.2	5	2	1	.5	-	5	2	2	10	10	10
Al ^a	0.1	0.4	0.5	0.15	0.05	-	1.0	0.05	0.5	0.03	0.05	0.05
Mg ^a	0.04	0.5	0.5	0.04	0.02	-	1.0	0.04	0.3	0.04	0.03	0.01
Ba	0.005	0.04	0.04	0.05	0.04	-	0.03	0.05	0.02	0.05	0.07	0.07
Be ^a	0.001	0.008	0.015	0.015	0.004	-	0.01	0.008	0.005	0.005	0.005	0.005
Mo ^a	0.01	0.01	0.01	nd<0.003	nd<0.003	-	0.01	0.003	0.003	nd<0.003	nd<0.003	nd<0.003
Zr ^a	nd<0.001	0.01	0.01	nd<0.001	nd<0.001	-	<0.01	<0.005	<0.005	nd<0.001	nd<0.001	nd<0.001
Cr ^a	0.01	<0.003	<0.003	<0.003	<0.003	-	0.003	nd<0.003	0.003	nd<0.003	nd<0.003	nd<0.003
Co ^a	0.003	0.001	0.001	nd<0.001	nd<0.001	-	0.01	0.001	0.001	<0.0003	<0.0003	<0.003
Ni ^a	0.01	0.003	0.005	0.0005	0.0005	-	0.01	0.01	0.01	nd<0.0003	0.0003	0.0003
Cd ^a	nd<0.01	nd<0.01	nd<0.01	nd<0.01	nd<0.01	-	0.005 ^b	nd<0.01	nd<0.01	nd<0.01	nd<0.01	nd<0.01

Elements not detected in any sample
 Bi < 0.003 Sn < 0.003
 Nb < 0.003 V < 0.001

^a by emission spectroscopy
^b by x-ray fluorescence
 nd = not detected

Table 8.2-2 Composition of GLEF Scales After Operation with Brine from Woolsey No. 1 and Magmamax No. 1 as Determined by X-Ray Defraction Analysis

Mineral	Woolsey No. 1					Magmamax No. 1						
	WPL	W1AIN	W1ADS	W2ADS	WV15OUT	Wellhead	V4	V4D	V11TOP	V11	V11D	V15
Amorphous Silica, SiO ₂	nd	major	major	major	major	nd	minor	trace	major	major	major	major
Halite, NaCl	nd	major	major	minor	minor	nd	major	major	minor	major	major	major
Barite, BaSO ₄	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd
Galena, PbS	major	trace	trace	nd	nd	major	major	major	minor	trace	minor	minor
Montmorillonite Complex Al ⁺⁺⁺ Silicate	nd	nd	nd	nd	nd	minor	minor	minor	trace	nd	nd	nd
Fluorite, CaF ₂	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd
Sylvite, KCl	nd	nd	nd	trace	nd	nd	nd	nd	nd	minor	nd	minor
Magnetite, Fe ₃ O ₄	nd	nd	nd	nd	nd	nd	trace	nd	major	nd	nd	nd
Laurionite, Pb(OH)Cl	trace	nd	nd	nd	nd	trace	nd	trace	trace	nd	nd	nd

nd = none detected

Table 8.2-3 Magmamax No. 1 Scale Dissolution Results

Solvent	Time	Temp. °C	% Scale Dissolved						
			V15D	V4D	V11TOP	V11D	V11	V4	Wellhead
0.2M HNO_3 + 0.1M HCl	1 hr	23	19.2	35.3	12.3	29.3	22.3	39.4	13.6
	24 hr	23	24.7	58.7	11.5	--	29.4	58.0	10.4
	1 hr	80	20.7	58.8	21.0	28.0	24.3	61.3	11.0
0.05M EDTA + 0.5M NaOH	1 hr	23	23.0	10.8	7.9	27.0	26.2	15.9	6.5
	24 hr	23	23.3	19.8	10.6	33.4	24.8	22.2	9.01
	1 hr	80	68.4	17.7	10.9	56.5	29.8	19.0	4.6
0.5M HCl	1 hr	23	19.4	25.1	8.7	29.3	23.8	31.5	4.9
	24 hr	23	21.7	56.3	19.4	32.2	26.7	58.7	9.7
	1 hr	80	53.8	29.6	24.3	30.1	25.5	60.7	10.1
0.5M NaOH	1 hr	23	20.6	8.0	7.9	24.0	24.8	14.8	3.4
	24 hr	23	17.3	9.5	5.4	18.7	18.6	15.6	3.8
	1 hr	80	62.3	10.5	7.9	26.9	22.2	16.3	--
0.1M HF	1 hr	23	33.1	32.5	14.9	31.0	27.5	32.4	7.7
	24 hr	23	34.8	40.5	27.8	38.5	34.2	46.7	11.9
	1 hr	80	31.7	36.0	21.6	29.2	28.3	38.8	12.5
0.1M HF + 0.5M HNO_3	1 hr	23	28.5	58.2	22.1	37.6	30.2	49.2	10.5
	1 hr	80	35.6	76.9	33.8	40.2	36.8	77.2	77.4
0.5M HNO_3 + 0.5M HAc	1 hr	23	22.5	26.0	10.1	29.7	28.6	27.4	4.5
	24 hr	23	23.0	57.8	14.9	32.7	27.5	55.8	52.4
	1 hr	80	20.6	58.2	15.5	31.1	26.2	58.8	75.4
0.13M H_2O_2 + 0.5M HCl	1 hr	23	21.9	24.8	7.8	29.9	25.6	28.4	9.3
	24 hr	23	21.1	47.6	15.5	30.6	25.1	53.3	20.8
	1 hr	80	21.2	60.3	18.0	28.5	25.1	59.7	50.8
H_2O	1 hr	23	18.3	7.5	4.5	22.1	22.5	14.8	0.9
	24 hr	23	19.7	8.5	3.1	22.1	24.6	15.0	0.8
	1 hr	80	18.6	8.8	11.1	21.6	23.3	15.4	0.8

Table 8.2-4 Woolsey No. 1 Scale Dissolution Results

Solvent	Time	Temp. °C	% Scale Dissolved				
			W-PL	W1AIN	W1ADS	W2ADS	WV15OUT
0.2 MHNO_3^+ 0.5 MNCI	1 hr	23	11.4	28.9	12.1	14.5	45.3
	24 hr	23	24.6	49.2	32.5	16.2	47.8
	4 hr	80	45.5	57.1	45.6	15.8	50.2
0.05 MEDTA^+ 0.5 MNaOH	1 hr	23	9.3	16.9	0.1	11.6	47.0
	24 hr	23	18.2	19.5	4.4	18.0	52.1
	4 hr	80	12.3	23.0	5.4	49.4	85.9
0.5 MHC1	1 hr	23	20.6	37.3	19.2	15.2	46.4
	24 hr	23	25.3	53.2	46.3	16.4	47.8
	4 hr	80	38.1	59.4	48.0	17.6	67.1
0.5 MNaOH	1 hr	23	11.8	17.2	3.4	14.0	42.6
	24 hr	23	11.0	17.5	3.2	6.2	44.0
	4 hr	80	15.4	20.0	7.7	55.7	58.4
0.1 MHF	1 hr	23	15.7	54.4	40.8	25.5	--
	24 hr	23	23.4	57.1	33.5	27.2	62.1
	4 hr	80	24.1	65.0	28.9	29.8	64.0
0.1 MHF^+ 0.5 MHNO_3	1 hr	23	23.1	59.5	43.1	24.9	62.2
	24 hr	23	38.7	76.9	63.6	28.4	65.4
	4 hr	80	87.9	--	59.9	26.3	63.9
0.5 MHNO_3^+ 0.5 MHAc	1 hr	23	10.9	27.5	10.2	12.8	46.0
	24 hr	23	21.4	43.5	22.6	12.7	48.8
	4 hr	80	78.4	50.0	37.0	17.7	48.9
0.13 MH_2O_2^+ 0.5 MHCL	1 hr	23	12.5	25.8	10.0	13.3	47.5
	24 hr	23	24.2	42.3	23.6	15.9	48.4
	4 hr	80	41.8	58.2	44.5	19.5	45.4
H_2O	1 hr	23	1.8	12.4	1.8	12.0	44.6
	24 hr	23	2.7	19.3	2.2	11.9	44.3
	4 hr	80	3.8	20.5	3.6	12.6	45.8

Figure 8.2-3 Dissolution of WPL Scale (Woolsey, Production Line) by Various Reagents

Figure 8.2-4 Dissolution of W-1A-In Scale (Woolsey, 1st Stage) by Various Reagents

Figure 8.2-5 Dissolution of W-1A-DS Scale (Woolsey, 1st Stage) by Various Reagents

Figure 8.2-6 Dissolution of W-2A-DS Scale (Woolsey, 2nd Stage) by Various Reagents

Figure 8.2-7 Dissolution of W-V15-OUT Scale (Woolsey, Atmospheric Receiver) by Various Reagents

Figure 8.2-8 Dissolution of Wellhead Scale (MagmaMax) by Various Reagents

Figure 8.2-9 Dissolution of V4 Scale (Magmamax 1st Stage) by Various Reagents

Figure 8.2-10 Dissolution of V4D Scale (MagmaMax, 1st Stage) by Various Reagents

Figure 8.2-11 Dissolution of V11T Scale (Magmamax, 2nd Stage) by Various Reagents

Figure 8.2-12 Dissolution of V11 Scale (MagmaMax, 2nd Stage) by Various Reagents

Figure 8.2-13 Dissolution of V11D Scale (Magmamax, 2nd Stage) by Various Reagents

Figure 8.2-14 Dissolution of V15D Scale (MagmaMax, Atmospheric Receiver) by Various Reagents

The hardness of the Magmamax scales were not measured, but they appear to be quite similar to the Woolsey scales.

The significance of scale hardness is open to interpretation. Hardness may be an important property in assessing the relative ease of scale removal by mechanical techniques. Scale adhesion is another property that may be germane to the ease of scale removal. However, we were unable to adopt a method which we felt would give reproducible data.

Scaling rate and hardness data for Woolsey No. 1 scales are given in Table 8.2-5 and scaling rate data for Magmamax No. 1 scales are given in Table 8.2-6.

Scaling rates are highest in areas downstream of the second flash stage and are about a factor of 10 lower in the production line leading to the first flash stage. Fortunately where the scaling rates are high, the scale is quite soft (when still moist) and presumably the easiest to remove by mechanical means.

8.2.4.4 Comparison of Actual and Expected Results

Although some discrepancies in the data does exist, there are some general conclusions that can be made with respect to the type of reagent tested best suited for dissolving a particular type of scale.

For scales consisting of predominately amorphous silica, hot sodium hydroxide (NaOH) is effective. NaOH in combination with EDTA, a known complexing agent for metals, was even more effective than NaOH alone. At room temperature none of the reagents tested was effective, except perhaps for 0.1 hydrofluoric acid (HF) which slightly attacked the scale. A more concentrated HF leach might have been beneficial, but would not be practical from safety considerations in an actual plant application. Not unexpectedly, NaOH or NaOH-EDTA combinations had little or no effect on galena or iron-rich scales.

Hydrochloric acid (HCL) had some effect on iron-rich scales consisting in part of magnetite or perhaps a complex iron-rich amorphous silica. Temperature seemed to enhance dissolution. Neither HCL nor nitric acid (HNO_3), nor combinations of the two acids, had much effect on silica rich scales.

HCL alone was not sufficient to dissolve the galena rich scales. Addition of an oxidant, either hydrogen peroxide (H_2O_2) or nitric acid (HNO_3), however, enhanced the effectiveness² considerably. The best combinations for dissolving galena rich scales were HNO_3 with HF or acetic acid at 176°F (80°C). Apparently sulfide is oxidized, and

Table 8.2-5 Woolsey No. 1 Scale Hardness and Scaling Rates

Sample I.D.	Sample Location	Hardness (Type A durometer)	Scaling rate mils/hr (linear)
W-PL	Production line	97	0.22
W-1A-IN	1st stage inlet	76	0.26
W-1A-DS	1st stage drain	58	1.0
W-2A-DS	2nd stage drain	44	1.7
W-V15-OUT	Atm. receiver drain	0	not measurable from sample

Table 8.2-6 Magmamax No. 1 Scaling Rates

<u>Sample I.D</u>	<u>Sample Location</u>	<u>Scaling Rate mils/hr (linear)</u>
WH	wellhead	nd
--	1st stage inlet	0.1 - .2
V4	1st stage, below liquid level	nd
V4D	1st stage drain	0.2 - .4
V11	2nd stage, below liquid level	nd
V11D	2nd stage drain	0.74 - 1.9
V11T	2nd stage, above liquid level	nd
V15D	Atm. receiver drain	1.5 - 3.0

nd = not determined

further dissolution is aided by formation of a lead acetate complex. HF may help overall dissolution by reacting with silica which has been suggested as being the matrix material that cements the high temperature forming scales.

Based on these scale dissolution test results, an in-place scale cleaning test was conducted in the 1st stage separator (Wellhead conditions and hence PbS scale) at the LLL Niland test facility. Immediately following separator use, combined 0.5 MHNO_3 and 0.5 MHAc (acetic acid) was injected into the lower section of the separator while still hot. After 20 hours of soaking, no appreciable effects were apparent, except for a marginal softening of the scale. Poor results may have been due to cooling of the solvent (there were no means for temperature maintenance) and insufficient solvent to scale ratio.

The results of these in-place tests indicate the problems that will be encountered in an actual application. The foremost difficulty will be slow rate of dissolution owing to the very low surface to mass ratio provided by a thick scale layer. All of the laboratory tests were conducted with scale samples that were finely ground in a constantly agitated solution. Furthermore, maintenance of temperature will require a separate heating system for the reagents or for the plant components. Another concern is the large amount of scale material in a layer deposited on pipe walls compared with the volume available to be occupied by the reagent. Repeated soakings would be necessary.

The laboratory measurements, conducted at near optimum conditions did not reveal an outstanding and fast dissolving reagent that under much less favorable power plant conditions seemingly be of some utility. A combination of chemical and mechanical cleaning methods may be most effective. However, the added improvement by use of chemicals may be marginal and greatly overshadowed by their cost, corrosivity, and safety hazards.

8.2.5 CONCLUSIONS AND RECOMMENDATIONS

The scaling rates have been determined at critical locations in the GLEF in both the Magmamax No. 1 and Woolsey No. 1 trains. The rates are not substantially different from data acquired during earlier 4-stage flash operation. Scale deposition rates particularly downstream of the 2nd stage are sufficiently high (1.5"/month) to require shutdown and scale removal at frequent intervals of perhaps 1 month. Scaling rates downstream of the 1st stage are approximately 0.5-1.0"/month and would require less frequent maintenance. Wellhead and production line scaling rates are 0.2"/month and will require much less frequent maintenance, but a greater effort because of the hardness and tenacity of the predominately galena-rich material.

Scale removal based on an in-situ method using chemicals alone would require temperature maintenance of the solvent circulation loops and sufficient time for dissolution of all the scale. In the 3-50% train design, proposed in the feasibility study (Bechtel National Inc. and The Ben Holt Co., 1978), one train is isolated for a period of time for cleaning and maintenance. If this period is sufficiently long to permit continuous circulation and recirculation of solvent, scale removal without mechanical assistance may be effective. Tests with exposed spool pieces containing the principal types of scales typically deposited at the GLEF and the reagents identified in this study could be useful in final evaluation of the technical and economic merits of scale removal by chemical dissolution.

8.2.6 REFERENCES

- 8.2-1 SDG&E/DOE Geothermal Loop Experimental Facility (GLEF). Bimonthly and Quarterly Reports, SAN/1137-1-9, 1976, 1977, 1978.
- 8.2-2 Quong, R., H. K. Bishop, J. H. Hill, Scale and Solids Deposition in the SDG&E/US ERDA GLEF at Niland, California, Geothermal Resources Council, Transactions, 1, May 1977, (249).
- 8.2-3 Quong, R., Scaling Characteristics in the GLEF, Lawrence Livermore Laboratory Report UCRL-52162, November 1976.

8.3 SCALE CONTROL ADDITIVES

Principal Investigators: J. E. Harrar, F. E. Locke, L. E. Lorensen, R. Quong, C. H. Otto, Jr., W. P. Frey, S. B. Deutscher, E. O. Snell, and R. Lim (Lawrence Livermore Laboratories)

8.3.1 OBJECTIVES

The objective of this test was to determine the possible retarding or eliminating scale formation in a two-stage flash system through the addition of proprietary scale inhibiting chemicals or sludge particles to the brine. If these techniques were shown to have a beneficial effect, the cost per unit mass of brine treated was to be estimated. This technique, if successful, may greatly reduce the cost of power from the 50 MW power plant proposed for the Niland reservoir.

In addition, the consequences of successful scale inhibition on corrosion and erosion of plant components, effluent treatment, injection well lifetime, etc., were to be addressed qualitatively through observations and analysis of the treated brine.

8.3.2 BACKGROUND

The deposition of scale from Niland brines continued to be a critical problem in equipment. Frequent shutdowns for cleaning significantly reduced plant availability and contributed to high maintenance costs. Development of a scale control method would have major engineering and cost impact on a 50 MW geothermal power plant. Initial bench tests carried out at 194°F (90°C) have shown that several compounds were quite promising inhibitors in acidified brine and in initially acidified brine that subsequently was raised to pH 5.8 by calcite addition (See Ref. 8.3-1). Some in-line screening tests at the LLL test facility in which organic additives were injected into the 392°F (200°C) unmodified brine steam discharged from the wellhead separator indicate scale deposition is indeed inhibited through the use of certain organic compounds (See Ref. 8.3-2). However, the brevity and the small number of tests did not permit quantitative conclusions to be made.

Injection of seed particles was also to be tested as a means of providing a large and active surface area for scale deposition, thereby minimizing deposition on pipes and components. Tests with effluent brine have demonstrated that silica precipitation can be greatly accelerated by contacting the brine with large quantities of preprecipitated solids.

Additional tests were expected to be necessary should additives prove to be effective in scale inhibition. These were 1) the need to develop methods for destabilizing the brine for effluent treatment and solids removal purposes, and 2) abatement of possible increased corrosion rates from the use of scale control additives themselves. Both of these supplementary tasks are important and will require test and evaluation, but are beyond the scope of this test.

8.3.3 TEST DESCRIPTION AND PROCEDURE

8.3.3.1 Test Materials and Equipment

These tests were conducted at the LLL test facility which operates independently of the GLEF. Figure 8.3-1 illustrates schematically the system for scale control testing. In addition to the brine handling equipment necessary to duplicate the GLEF process, analytical chemistry support facilities are also available.

Proprietary scale control additives were prepared in the appropriate feed concentrations and injected into the high temperature brine stream discharged from the wellhead separator. An additional flash stage dropped the temperature to 257°F (125°C).

The effect of the additives on scaling rates was to be determined from scaling spools, coupons, screens, and tubing. Several side stream methods designed to shorten the time required to screen the additives were also tested. These methods include passing the brine through screens in series, capillary tubes, and beds of spherical steel balls to provide high surface area for scale deposition and hence large changes in silica concentration in the brine. The magnitude of this change in silica concentration used as a measure of additive effectiveness. Chemical and mechanical properties of the scale were also to be determined.

For the seeding tests, precipitated solids (sludge) was obtained from Magma Power's clarifier/filter facility.

For evaluation of stability of the brine, samples of effluent were collected, held at temperature in sealed bottles, and monitored for changes in dissolved silica concentration and production of particulates.

8.3.3.2 Test Prerequisites

There were no other tests which needed to be performed prior to or in conjunction with this task.

8.3.3.3 Test Conditions

At the LLL test facility, fluid was supplied from Magmamax No. 1 via a 2" line. It was highly desirable, but

Figure 8.3-1 Scale-Control Test System

not mandatory, that tests at the LLL facility take place simultaneously with GLEF operation, since salinity, silica concentration, temperatures, and pressures are significantly higher at full wellflow conditions. The primary requirements for conducting these tests were adequate flow of production fluid and the availability of an injection well. When the GLEF is operating steadily, the well fluid properties will normally exceed specified minimal values. However, this is not the case when the LLL facility is operating alone through the 2" line. Under these conditions, the chemistry of the separated wellhead fluid must be such that the Cl^- concentration is greater than or equal to 3.1 moles/liter, and the silica concentration is greater than or equal to 420 mg/Kgm. In addition, the temperature and pressure at the wellhead must be greater than or equal to 392°F (200°C) and 250 psia, respectively.

These test conditions downstream of the wellhead separator were adjusted accordingly to meet the test objectives. In general, flowrate variations to the experiment were not expected to exceed $\pm 10\%$ from the set point. Temperature in the two flash stages was to be maintained within $\pm 5\%$ of the set point. The variation in flowrate of additive injected into the brine stream was not exceed $\pm 10\%$ from the set point, which was a function of the additive used, its strength, and feed concentration. The flowrate in each test channel was to be 1.0 ± 0.1 lb/sec; temperature in the wellhead separator 392°F (200°C); pressure in the wellhead separator 250 psia; temperature in the flash separator $257^\circ \pm 41^\circ\text{F}$ ($125 \pm 5^\circ\text{C}$). Unless specifically indicated otherwise, the wellhead separator at the LLL test facility was designated as the 1st stage separator.

8.3.3.4 Required Data and Observations

Spools located in the discharge lines of each separator stage was to be the one source of scale rate data. The spools were to be removed following each test and subsequently examined for scale thickness, hardness, adherence, and density - properties which may have a bearing on scale removal techniques. Scale thickness was to be measured using micrometers. Scale hardness was to be measured using an ASTM Shore A, D + O Hardness apparatus. Adhesion was to be measured by the lateral force per unit contact area to dislodge the scale. Density was to be measured by combined gravimetric and volumetric measurements on a sample. Scale composition, mineralogy, and morphology was to be determined by X-ray fluorescence/ emission spectroscopy, X-ray diffraction, and scanning electron microscopy, respectively.

Scaling coupons attached inside the spools were to supplement these data. Brine discharged from the final stage was to be passed through stainless steel screens as an additional test of scaling potential. A series of screens were also to be used in sidestream tests.

Data was also to be obtained on stability of brine effluent from the last flash stage and inside streams by collecting and holding brine at constant effluent temperature and monitoring changes in silica concentration and total particulate content.

Plant conditions such as temperature, pressure, and flowrate at the wellhead and at each stage were to be monitored and recorded every hour. Additive flowrates were also to be recorded every hour. Brine chemistry was to be monitored for pH, salinity, and silica concentration on a daily basis or more frequently as required.

8.3.3.5 Test Duration

At least 6 commercially available scale control additives were to be tested for a period of 72 hours each to allow sufficient time for a measurable amount of scale to be deposited. The test length was to be shortened if one of the rapid methods described in 8.3.1 was successful. Calgon CL-165, Dearborn Geomate 256, and Drew Drewsperser 747 were to be among the 6 additives tested. The remaining three were to be selected after more companies responded. Scale analyses, interpretation of data, and preliminary reporting of results were to be available about 1 month after test completion.

8.3.4 RESULTS

8.3.4.1 Expected Results

- o The effectiveness of proprietary additives and sludge seeding were to be determined.
- o Scaling rate and scale properties data were to be produced at each test condition.
- o Stability of dissolved silica and production rate of suspended solids in the brine effluent were to be determined.
- o Finally LLL was to assist in selecting the chemical additive and in designing the necessary equipment to conduct a full scale test at the GLEF. This was to include preparation of a test plan required for implementation.

8.3.4.2 Data and Observations

8.3.4.2.1 Observations on Testing Techniques

A major emphasis of this effort was to develop and use techniques of scaling rate measurement that would minimize the time required to evaluate a single additive, but still provide useful information for prediction of performance in

larger facilities and for longer times. After the tests of the various additives, we have made the following observations on the testing techniques:

- o Use of the packed metal-ball column was unsatisfactory, probably because of the difficulty in providing a large surface area for brine contact throughout the columns. However, successful experiments of this type using simulated geothermal brines and other packing materials have been done recently at Oak Ridge (See Ref. 8.3-3) and additional work could be done to optimize the metal column used. However, as discussed below, apparatus such as this, which depends on passing the brine through small orifices with a large surface area of contact, is vulnerable to the suspended solids in the brines that may obscure the "true" scaling rate.
- o Flowing the brine through screens at the high temperature test point (392°F, 200°C) was unsatisfactory because the usual particulate level in the brine tended to plug the screens and obscure the accumulation of "true" scale. This particulate level was very sensitive to plant upsets (e.g., sudden variations in pressure or flow), and hence so was the screen test. At 392°F (200°C) it was generally not a reliable indicator of brine scaling tendency. Better results were required for a definitive measurement. However, there is still an occasional lack of repeatability in this technique which has not always been explainable in terms of plant operating conditions.
- o Use of the 1-inch inside diameter pipe spools, which were epoxy-potted, sectioned, and polished for microscopic examination, appeared to be a reliable semi-quantitative indicator of brine scaling tendency. At least 60-hour exposures were required when these specimens were used. Their disadvantage was the wide variation of scale thickness in a given exposed specimen. In one cross-section, the typical range was a factor of 2 to 4. Longer exposure times would have tended to smooth out this variation. Tubing sections (1/2" and 1/4") exposed in sidestreams at 392°F (200°C) and 257°F (125°C) had the same problem.
- o The most reliable and precise specimens for assessing scaling, at the time of the November/December series, were the pairs of thin, flat coupons. Three materials were used: AISI 1009 mild steel, Teflon TFE, and Hastelloy C-276. The mild steel coupons were mounted on a holder that was held in the flange of the pipe spool. The long dimension

of the coupon projected downstream in the 1-inch pipe. The Teflon and Hastelloy specimens were mounted at right angles to the flow on Petrolite-probe, 2-inch pipe plugs in 2 inch section of pipe. Because excessive scaling or plant upsets leading to high suspended solids levels sometimes created severe obstructions at the steel coupon holder, subsequent tests were done with the steel coupons mounted on 2 inch pipe plugs in the 2 inch line with the Petrolite probes.

- o Another modification to the system that was introduced as experience was gained during the year, was the addition of a third delay stage operating from a 257°F (125°C) sample port. This provided brine at 194°F (90°C) that had been aged 10 minutes since flashing to 257°F (125°C). As expected, specimens placed at the output of the delay stage scaled more heavily than at 257°F (125°C) and this provided a measure of conditions that might be encountered in atmospheric flash and downstream equipment. Tubing (1/4 inch and 1/2 inch diameter) installed at the output of the delay collected thicknesses of scale that could be measured accurately by sectioning in 12-24 hour exposures. Although this technique was not used for any of the proprietary additives tested, it is unlikely, in the light of subsequent work, that the proprietary additives would have had an effect on the 194°F (90°C) scales, because none functioned as a silica precipitation inhibitor.
- o Scale hardness could not be measured as planned because the amount formed was not thick enough for the penetration test. Longer exposure times would be required to obtain suitable specimens. Adhesion also could not be measured quantitatively because a suitable testing technique was not developed in time.

8.3.4.2.2 Results of Proprietary Additive Tests

Most of the tests of the proprietary additives were carried out during November and December of 1978. During that time eight different formulations from eight different companies were tested. The effects of each of these additives were assessed in 3-day runs, during which the full complement of specimens were in place and the stability of the brine at 194°F (90°C) was assessed. Experiments were also done during this time to evaluate the more rapid methods for scaling rate measurement that were proposed, i.e., flowing the brine through screens and columns containing small steel balls.

All of the results of the November/December, 1978 test series, with the exception of the chemical analyses of the scale deposits and the results of the examination of the pipe spools, were summarized in a UCID report (See Ref. 8.3-4). The test procedures are also described in more detail in that report.

The major characteristics of the effluent during that period were as follows:

Chloride concentration: 3.60-4.12 Mol/liter

pH: 5.72-5.96

SiO₂ concentration: 425-516 mg/kg

The GLEF operated continuously during this period, except for November 14th, when the brine concentrations dropped to the lower values noted. Wellhead pressures were in the range of 250-315 psia and temperatures were in the range of 408 - 428°F (209-220°C).

Table 8.3-1 lists the values of scaling rate found during two runs with untreated brine. These served as the controls against which the performance of the proprietary additives were measured. It can be seen that, although the roughness of the scale in the pipe makes its thickness measurement uncertain, there is fairly good agreement between the results of the steel pipe and steel coupon specimens. Also, as has been found to be generally true, the apparent scaling rates found for Hastelloy and Teflon are lower than for steel. We believe this is due to two factors: (a) the combined effects of corrosion and scaling on the steel surface vs. only scaling on Teflon and Hastelloy, and (b) less tenacious adhesion of scale on Teflon and Hastelloy. Longer exposure times and thicker scales tend to reduce the differences of scaling rates among the different surfaces.

Table 8.3-2 lists the proprietary additives that were given 3-day tests as antiscalants during the November/December test series. These were selected as a result of an industry-wide solicitation in August of 1978. Table 8.3-3 summarizes the results of testing of these additives. For the scaling rates, only the comparison of the rates for mild steel are given here. The data for Teflon and Hastelloy are in general agreement (See Ref. 8.3-4).

At 410°F (210°C), only the Thermosol APS had a beneficial effect on the scale, but the degree of scale reduction was nearly the same as the experimental uncertainty. As noted, several of the additives increased the deposition of scale, possible as a result of decomposition of the additive itself. At 257°F (125°C), most of the additives appeared to reduce the amount of scale on the coupons, but only two, Drewspers 747 and SC-210, reduced the scale on

Table 8.3-1 Scaling Rates of Untreated Brine Measured During the November/December Test Series. (Magmamax No. 1 Well)

Scaling rate at 210°C, mil/h				
	Coupon			
	<u>Steel Pipe Spool</u>	<u>Steel</u>	<u>Hastelloy</u>	<u>Teflon</u>
Nov. 11-17 ^a	0.014-0.042	0.02	0.01	0.05
Dec. 12-15 ^b	0.030-0.061	0.08	0.02	0.03

Scaling rate at 125°C, mil/h				
	Coupon			
	<u>Steel Pipe Spool</u>	<u>Steel</u>	<u>Hastelloy</u>	<u>Teflon</u>
Nov. 11-17 ^a	0.16-0.28	0.21	0.10	0.11
Dec. 12-15 ^b	0.085-0.31	0.38	0.06	0.09

^a Exposure time: 113h

^b Exposure time: 65h

Table 8.3-2 Proprietary Additives Tested in November-December, 1978 Test Series

<u>Product Name</u>	<u>Company, Address</u>	<u>Chemical Type</u>	<u>Concentration Tested, ppm</u>
Geomate 256	Dearborn Chemical Corp., Lake Zurich, IL	Phosphonate + Polymer	35
CL-165	Calgon Corp., Pittsburgh, PA	Polymer mixture	18
Drewsperser 747	Drew Chemical Corp., Boonton, NJ	Phosphonate + Polymer	15
Betz 419	Betz Laboratories, Trevose, PA	Phosphonate + acrylic Polymer	20
Thermosol APS	Far-Best Corporation, Los Angeles, CA	Polyalkylphosphonate	20
S-404	C-E Natco, Bakersfield, CA	Organic Polymer	18
SC-210	Southwest Specialty Chemicals, Houston, TX	Low molecular weight carboxylic acid	10
Cortron R-16	Champion Chemicals, Anaheim, CA	Filming amine	120, 20

Table 8.3-3 Performance of Eight Proprietary Additives as Antiscalants in Magmamax No. 1 Brine.
(See Table 8.3-2 for Further Details of Additives)

<u>Additive</u>	<u>% Reduction of scale on mild steel</u>				<u>90°C Silica precipitation test</u>
	<u>210°C</u>		<u>125°C</u>		
	<u>Pipe Spool</u>	<u>Coupon</u>	<u>Pipe Spool</u>	<u>Coupon</u>	
Geomate 256	0	0	0	32	Negative ^b
CL-165	0	0 ^a	0	32	Negative
Drewperse 747	0	0 ^a	30	50	Negative
Betz 419	0	0	0	52	Negative
Thermosol APS	30	30	0	50	Negative
S-404	0	0	0	21	Negative
SC-210	0	0 ^a	80	42	Negative
Cortron R-16	0	0	0	0	Negative

^a Significant increase in the deposit.

^b No effect on the rate of precipitation of silica.

both the pipe spool and coupons. These two also showed the lowest rates on Teflon and Hastelloy, but they were not lower than the values for untreated brine. Thus the diminished scaling rates shown by Drewspers 747 and SC-210, as well as some of the other additives, as shown in the data of Table 8.3-3 may be due only to some action as either a corrosion inhibitor or an agent in preventing the adherence of corrosion product.

An indication of the corrosion rates of mild steel in the brine in the presence of these additives was obtained by measurements using the Petrolite Instruments Company linear-polarization resistance (LPR) equipment. The locations of these LPR probes in the brine streams is shown in Figure 8.3-1.

Table 8.3-4 summarizes the data on the corrosion rates of the brines measured by means of the linear polarization resistance technique. The values listed are the levels obtained after about 12-hour of specimen exposure and in all cases these values held nearly steady for the durations of the exposures. It is striking that the corrosion rates at 257°F (125°C) for the untreated brines, and several of the treated brines, were higher than the rates at 410°F (210°C). This may reflect the relative degrees of protection afforded by the corrosion films and scales formed at these temperatures. The higher corrosion rate at 257°F (125°C) in the brine with the Southwest Chemical SC-210, coupled with its lower scaling rate at this temperature (Table 8.3-3) suggests that it may have exhibited some scale inhibition. The higher corrosion rate in the presence of the Cortrom R-16 may be a result of the greater porosity of its scale. It should be realized that complete scale inhibition may result in much higher corrosion rates than are usually observed for scaling brines. In the case of acidification with HCl, it is not only the pH lowering that is responsible for increased corrosion rates, but also the absence of protective silica scale.

In our "standard" precipitation test, (See Ref. 8.3-5) in which the effluent brine, previously treated with the candidate additive in the plant, is held at 194°F (90°C) to follow the kinetics of the precipitation of silica, we found that none of the proprietary additives had any effect. This was in contrast to the effect of several generic compounds that had been discovered earlier (See Ref. 8.3-1). In the November/December test series, one of these compounds, Natrosol 250LR (Hercules hydroxyethyl-cellulose) was included with the proprietary additives for evaluation. In-plant injection revealed that it did inhibit the precipitation of silica at 194°F (90°C), but it too failed to significantly retard the formation of scales at higher temperatures.

All of the results of this test series, taken as a whole, led us to the conclusion that none of the proprietary

Table 8.3-4 Corrosion Rates of Mild Steel (AISI 1018) in Additive-Treated Brine Measured by the Linear Polarization Resistance Technique

	<u>Corrosion rate, mpy</u>	
	<u>210°C</u>	<u>125°C</u>
Control A	9	14
Control B	7	15
Geomate 256	3	15
CL-165	5	2
Drewspers 747	7	15
Betz 419	7	4
Thermosol APS	7	5
S-404	5	3
SC-210	5	25-60
Cortron R-16	7	25

additives, except possibly Southwest Chemical's SC-210, merited further attention as geothermal scale inhibitors.

8.3.4.2.3 Precipitation Tests of Additional Proprietary Additives

Work subsequent to the November/December, 1978 test period was devoted mostly to investigations of compounds whose identities were known, i.e., generic compounds. However, the state of the art in water treatment was still advancing, and periodically other proprietary additives and mixtures came to our attention that appeared to be worthwhile evaluating. None of these were subjected to a complete scale-abatement test, but a number were subjected to plant injection and measurement by the precipitation-inhibition test. These additional compounds, together with other pertinent information, are listed in Table 8.3-5. None of these compounds showed any activity toward silica at 194°F (90°C).

Polysperse Plus was of particular interest because experiments conducted at the GLEF by Paul Henry of NUS Corporation (See Section 8.15) indicated its inhibited silica precipitation. It failed in two trials at our facility and, although his experimental approach was somewhat different than ours, it has never been determined why these results were in disagreement.

As can be seen from the identities of the proprietary compounds in Tables 8.3-2 and 8.3-5 most of the materials are the anionic-type polymers traditionally used in various water treatment applications. Although they represent the industry's best guess as to effective antiscalants for hypersaline geothermal brine, in our tests they have certainly not appeared promising. In contrast, as discussed below, cationic polymers have emerged from our generic chemicals testing as definite economic possibilities for scale control.

8.3.4.2.4 Experiment with Sludge Seeding to Retard Scale Formation

Another approach to scale control that has been attempted by other investigators for other geothermal brines (See Ref. 8.3-6) is to add to the fluid a finely divided solid upon which the scale-forming compound deposits in preference to the plant surfaces. The rationale is similar to the addition of seed crystals to promote precipitation in crystallization processes. Although the scale with which we are dealing is predominantly amorphous silica, by providing a large ratio of seed-to-plant-surface area, reduction of the degree of supersaturation and hence the scaling tendency of the brine should be attainable. Also, to be a viable technique, the seed substance must remain fluidized and pass through the plant equipment with minimal holdup.

Table 8.3-5 Additional Proprietary Additives Tested as Silica Precipitation Inhibitors

<u>Additive</u>	<u>Company, Address</u>	<u>Chemical type</u>	<u>Concentration tested, ppm</u>
Polysperse Plus	Betz Laboratories Trevose, PA	?	20
Geomate 259	Dearborn Chemical Lake Zurich, IL.	?	40
XFS-43075	Dow Chemical Midland, Mich.	?	40
XD-30469.00	Dow Chemical Midland, Mich.	copolymer of acrylic acid & hydroxyethylacrylate	20
Darex 41s	W.R. Grace Lexington, Mass.	carboxylated polyelectrolyte	20
Visco 3744	Nalco Chemical Houston, Tex.	acrylic polymer + surfactant	20
Belclene 200	Ciba-Geigy Ardsley, N.Y.	low M.W. carboxylic acid	20
Pyronate 40	Witco Chemical New York, N.Y.	low M.W. alkyl aryl sulfonate	20

For Salton Sea geothermal brines the ideal seed material would be colloidal silica. Closely approaching such material is the wet sludge obtained from the sedimentation of the effluent brine from the GLEF prior to injection. This sludge is of mud-like consistency and is a finely divided precipitate composed primarily of silica, with lesser amounts of iron compounds and metal sulfides, i.e., all of the usual ingredients of geothermal scale. Using sludge as a seed material appeared promising because earlier work (See Ref. 8.3-7 and 8.3-8) on developing an effluent process for this brine demonstrated the effectiveness of pre-precipitation solids contact as a means of rapidly promoting the precipitation of silica.

A short experiment of seeding for scale control was conducted during the November/December series as a prelude to a longer-duration, more extensive test. In this experiment a suspension of wet sludge containing 20% by weight solids was metered into the 410°F (210°C) brine in the same manner as the chemical additives. This sludge contained, in addition to the compounds mentioned above, small amounts of BaSO_4 and CaSO_4 ; these were present because of the addition of Salton Sea water in the pilot clarifier tests conducted by the Imperial Magma Company (See Section 8.11). After an initial short period without additive flow to establish brine silica levels, the sludge feed rate was controlled for one hour at 0.30 gpm and then for 22 hours at 0.15 gpm. At 0.15 gpm, assuming 10 micro-meter spherical seed particles and a 1-inch inside diameter pipe diameter, a 10:1 particle-to-pipe surface area ratio is obtained.

Since the usual chemical feed pumps cannot be used for slurries, a Moyno progressive-cavity type pump was used for pumping the sludge, and for this short test no difficulties were experienced. Sludge flow rate was measured manually by a volume displacement technique.

In the measurement of scaling rate it was found that screens could not be used because they were rapidly plugged by the accumulation of the suspended sludge. A screen at the 257°F (125°C) brine sample port plugged in less than an hour. Similarly, there was an accumulation of sludge on the test coupons, especially at corners and attachment points, making it difficult to distinguish scale from sludge deposits. The Petrolite probe in 257°F (125°C) brine was so heavily covered with sludge that no estimates of either scale thickness or possible erosion on the Teflon or Hastelloy coupons could be made. The apparent amount of scale accumulated on the mild steel coupons was estimated (See Ref. 8.3-4), but the values are very inaccurate because of the accumulation of sludge and the short duration of the run.

Perhaps a better indicator of the potential of the technique was the lack of scale on the pipe spools. On

examination of these specimens, only corrosion product was seen, although the shortness of the run mitigates the conclusions somewhat.

A superior measurement method for detecting the effect of seeding may lie in our measurements of the levels of silica in the brine during the experiment. These data, shown in Table 8.3-6 were obtained, with one exception, as follows. The test brine (quite dark colored in appearance) was flowed dropwise onto a filter crucible connected to a vacuum flask in such a manner that a minimum time of contact with the sludge filter cake was obtained. Hydrochloric acid was placed in the filter flask to immediately acidify the filtrate and prevent further precipitation of the silica. The silica in the filtrate was determined by atomic absorption spectrophotometry. Using this technique it was found that (Table 8.3-6) seeding reduced the level of dissolved (particle size 1 m) silica from 453 to 431 and 416 mg/kg at 410°F (210°C), which is probably not a significant change, but from 516 to 306 mg/kg at 257°F (125°C), which is substantial reduction in the degree of supersaturation.

This measurement technique, however, may not be completely valid. Because of the extremely rapid reaction of dissolved silica with the seed silica at low temperatures, it is possible that some of the decrease in the concentration of silica occurred as the brine was being filtered. Thus an additional experiment was tried in which the brine at 257°F (125°C) was captured first in acid and then filtered. This yielded the value of 396 mg/kg, higher than before, but still significantly lower than the starting value of 516 mg/kg.

Corrosion rates estimated by the LPR technique during the seeding experiment yielded values of 10 and 14 mpy and 410°F (210°C) and 257°F (125°C), respectively, which are not significantly different from the rates found for untreated brine.

From these limited data it appeared that (a) the reduction in dissolved silica at low temperature 257°F (125°C) is sufficient to warrant further tests, (b) a still lower concentration of sludge than used here might be just as effective, and (c) different test surface configurations will have to be devised to measure scaling rates in the presence of sludge.

In this relatively short duration experiment, several inches of sludge accumulated in the bottom of the second stage separator, indicating that process equipment may require special design features to accommodate sludge injection as a means of scale control.

Table 8.3-6 Measurements of Concentration of "Dissolved Silica" in Brine During Seeding Experiment. (Concentrations of SiO_2 in mg/kg).

210°C			
<u>Before Sludge Addition</u>	<u>After Sludge Addition</u>		
	<u>0.3 gpm</u>	<u>0.15 gpm</u>	
453	431	416	
125°C			
<u>Before Sludge Addition</u>	<u>After Sludge Addition</u>		
	<u>0.3 gpm</u>	<u>0.15 gpm</u>	<u>0.15 gpm^a</u>
516	306	306	396

^a Immediate acidification of sludge-containing brine.

8.3.4.2.5 Test of Austral-Erwin Process for Scale Control

The results of the short test of sludge seeding indicated that it would be very difficult to carry out a longer duration test in the LLL facility, without appreciable modification, which would be definitive in terms of an accurate evaluation of scale abatement. Another proprietary scale control process, devised by R. W. Erwin of the Austral-Erwin Company, had been proposed to us and had shown promise at the Cerro Prieto and Brawley geothermal fields. Thus, because the Austral-Erwin process was technically different from those we had previously tested, and further tests of the seeding technique were not easily implemented, we decided to evaluate the Austral-Erwin process instead.

The Austral-Erwin process involves injecting into the brine a water emulsion of a proprietary mixture of cottonseed oil with small amounts of tall oil and other additives which aid in emulsifying the oils. As carried out in the test of the process at our facility, water was metered at 2 gal/hr and the oil-additive mixture at 0.3 gal/day to form a fine spray at the entrance to the brine (Figure 8.3-1). The resulting concentration of the oil-additive mixture in the brine was 40 ppm.

In theory, the process is said to involve a reaction of the fatty acids in the oils with the calcium of the brine to form a soap. In addition, the surface active compounds thus formed, or present in the emulsion, are supposed to coat the metal of the plant and render it hydrophobic. This surface then would have a tendency to repel colloidal silica, which is hydrophilic in nature, thus retarding its adherence and the formation of scale.

The test of the Austral-Erwin additive was performed from March 9-12, 1979, during which time the GLEF was not operating. The effluent brine characteristics during this period were as follows:

Chloride concentration:	3.52-3.67 Mol/l
pH:	5.83-5.95
Density at 77°F (25°C):	1.141-1.149
SiO ₂ concentration:	461-479 mg/kg

Magmamax No. 1 wellhead pressures and temperatures were 254-309 psia and 397 - 419°F (203-215°C), respectively. As is usual when LLL is the sole user of the well, the brine is less concentrated and scaling rates are lower than when the well is at full flow into the GLEF.

The results of the scaling test are summarized in Table 8.3-7. Comparing the results in Table 8.3-7 for the untreated brine with those in Table 8.3-1 the effect of the lower brine salinity in producing lower scaling rates at 257°F (125°C) is quite evident.

Table 8.3-7 Scaling Rates of Untreated Brine and Brine Treated by the Austral-Erwin Process.
(Magmamax No. 1 Well)

Scaling rates at 210°C, ml/h

	<u>Steel Pipe Spool</u>	<u>Coupon</u>		
		<u>Steel</u>	<u>Hastelloy</u>	<u>Teflon</u>
Untreated ^a	0.07	0.05	0.02	0.02
Austral-Erwin ^b	0.02	0.08	0.10	0.08

Scaling rates at 125°C, ml/h

	<u>Steel Pipe Spool</u>	<u>Coupon</u>		
		<u>Steel</u>	<u>Hastelloy</u>	<u>Teflon</u>
Untreated ^a	0.11-0.16	0.10	0.03	0.04
Austral-Erwin ^b	0-0.96 ^c	0.60	0.10	0.12

^a Exposure time: 88h

^b Exposure time: 65 h

^c See text

Except for one feature of its performance, the effect of the Austral-Erwin process in general was not very satisfactory. As can be seen in Table 8.3-7 only at 410°F (210°C) in the pipe spool was the scaling rate lower for the Austral-Erwin treated brine. Also, in the pipe spool exposed at 257°F (125°C), there was an indication that the scale formed from the treated brine was considerably less adherent since it had flaked off in many places before the specimen could be carefully examined. On the other hand, where the scale was still adhering to the pipe wall, it was quite thick. Scale formed on the flat coupons more rapidly from the treated brine, and the scale at 257°F (125°C) obviously incorporated a considerable amount of the additive. It was quite oily to touch, and samples lost 50-75% by weight on ignition prior to x-ray analysis. A similar oily scale was formed on perforated disks exposed at 257°F (125°C). The delay stage was also operated during these tests, and it was found that there was no decrease in the amount of scale formed at 194°F (90°C) from the Austral-Erwin treated brine compared to the controls. The additive also had no effect on the precipitation rate of silica in the 194°F (90°C) effluent brine.

Thus it appears that the Austral-Erwin process may decrease the adherence of the scale on surfaces such as the pipe spools where there is a high velocity flow without excessive eddies. At points where the flow velocity is lower (e.g., in the 2-inch pipe), and where there is turbulent flow such as around our specimen coupons, the accumulation of solids is increased. In this respect it resembles the sludge seeding process.

A difficulty with this additive may be that one of its components such as the cottonseed oil (which is a mixture of palmitic, oleic, and linoleic fatty acids) may absorb on the silica particles rendering them hydrophobic. They then should have a greater than normal tendency to aggregate and form a precipitate. It is also questionable (but it may not be necessary) that the fatty acids form a salt in the naturally acidic brine. An intermittent treatment scheme was proposed in which the additive would be injected periodically and just long enough to coat the pipe walls, but not so long as to affect all of the nucleating silica, but schedule and funding limitations precluded testing this idea.

8.3.4.2.6 Chemical Analyses of Scales

The scales that were deposited on the coupons were analyzed by x-ray fluorescence and emission spectroscopy to provide additional information on the effects of the brine treatment. Most of the samples that were analyzed were taken from the Teflon coupons so that the effects of substrate corrosion would not be included in the measurements. Scale samples from all three types of coupons were analyzed for the control experiments with untreated brine.

The compositions of the scales are given in Tables 8.3-8 and 8.3-9. Here it can be seen that even the high temperature scale formed at 410°F (210°C) (Table 8.3-8) contains over 50% silica, and the 257°F (125°C) scales (Table 8.3-9) are 80-95% silica. This lends weight to the contention that control of silica deposition is the key to the control of scale in virtually all portions of a geothermal system downstream of the first steam separation.

Few correlations can be made between the elemental analysis data and the quantities and visual appearances of the scales formed as a result of the brine treatments. One ever-present complication is that the concentrations of the constituents of the brine are not monitored all the time, thus an unusual result for the composition of a scale deposited during these short-term tests may represent merely a transient condition in the brine. At 410°F (210°C) (see Table 8.3-8) the most striking feature of the scales that formed is the high concentrations of copper when additives were present compared to when the brine was untreated. The Cortron R-16 scale also contained large amounts of nickel. This scale and several others had a distinctly greenish tint.

These scales were not analyzed by x-ray diffraction analysis, however, the large amounts of iron, copper, and sulfide suggests that the compounds Cu_2S and CuFeS_2 , previously identified in similar scales, (See Ref. 8.3-9 and 8.3-10) are present in these samples. The high sodium, potassium, calcium, and chloride levels, together with the lower silica level in the Drewspers 747 scale show that this scale incorporated some of the brine, and this may be the reason for the observed increase in scaling rate compared to the controls. The additive CL-165 caused the greatest increase in scaling rate at 410°F (210°C), but there is no clue in the analysis to indicate why this occurred. High calcium levels for some of the scales may be due to precipitation of the sparingly soluble calcium phosphonate, since many of these additives are phosphonates.

Among the scales formed at 257°F (125°C) (Table 8.3-9) the Cortron R-16 scale is again quite different from the others. This additive was a mixture containing a filming amine that was designed for corrosion inhibition. A plant upset occurred during its testing, to which we attributed the large accumulation of scale that occurred on the 257°F (125°C) specimens (See Ref. 8.3-4). However, the reverse could be true, i.e., the upset may have occurred because of the high rate of deposition of scale. In any event, the scale was very soft, powdery, easy to remove, and green in appearance. It had higher concentrations of iron, manganese, and chloride than the others.

The Geomate 256 scale was snow white in appearance, as borne out by its low concentration of the metal sulfides.

Table 8.3-8 Elemental Analyses of Scales Deposited on Teflon TFE Coupons at 210°C from Brine Treated with Various Additives. (Magmamax No. 1 Brine, 4.1 Mol/Chloride)

Composition in wt. %											
Element	Controls		Geomate 256	CL-165	Drewperse 747	Betz 419	Thermosol APS	Natco S-404	SW Chem SC-210	Cortron R-16	Sludge
	7-B	12-A	8-A	8-B	9-A	9-B	10-A	10-B	11-A	11-B	12-B
Si as SiO ₂	60	54	49	60	41	54	51	51	51	30	58
Fe	24	18	23	20	17	19	22	21	21	18	24
Ca	1.4	2.2	1.9	1.7	4.2	1.0	1.0	5.4	1.7	5.2	1.4
Cu	0.3	0.3	3.5	1.2	2.1	4.3	3.6	2.3	4.3	9.2	1.9
Ni	<0.01	<0.01	0.01	0.7	0.01	1.4	0.01	0.01	0.01	4.8	1.9
	0.3	7.6	0.2	0.05	0.95	0.4	0.1	0.4	0.05	0.8	0.2
Mn	1.6	1.0	1.1	1.4	0.9	0.8	0.9	1.0	0.9	0.7	1.0
Na	0.9	0.3	0.14	0.14	2.5	0.4	0.07	0.56	0.4	1.2	1.5
K	0.1	0.3	0.2	0.1	1.2	0.2	<0.05	0.3	0.2	0.1	0.1
Zn	0.2	0.2	0.2	0.2	0.2	0.1	0.2	0.2	0.1	0.2	0.07
Cl	<0.2	<0.2	<0.2	<0.2	5.5	<0.2	<0.2	0.6	<0.2	0.4	<0.2
S	<0.1	0.9	2.6	0.9	2.2	2.7	3.4	1.3	2.6	5.6	0.2
Al	0.5	0.4	0.5	0.3	0.4	0.5	0.15	0.3	0.4	0.2	0.1
Ag	0.03	0.04									

Ba, Sr, P, B, Rb, Sb

Cr, Mg, As all <0.1 except 9-A was 5% Mg and 11-B was 0.1% As.

Table 8.3-9 Elemental Analyses of Scales Deposited on Teflon TFE Coupons at 125°C from Brine Treated with Various Additives. (MagmaMax No. 1 Brine; 4.1 Mol/Chloride)

Composition in wt. %												
Element	Controls		Geomate 256	CL-165	Drewspense 747	Betz 419	Thermosol APS	Natco S-404	SW Chem SC-210	Cortron R-16	Sludge	Natrosol 250LR
	7-B	12-A	8-A	8-B	9-A	9-B	10-A	10-B	11-A	11-B	12-B	7-A
Si as SiO ₂	83	94	88	83	98	90	96	96	94	77	47	60
Fe	1.1	1.5	0.56	1.2	0.7	0.9	1.3	0.45	1.0	6.7	2.0	5.5
Ca	0.45	0.5	0.80	0.56	0.3	1.0	0.3	0.4	0.5	2.5	5.9	0.56
Cu	0.59	1.2	0.04	0.25	<0.02	0.05	0.2	0.01	1.6	<0.02	1.1	0.57
N	0.21	0.06	0.02	0.16	0.1	0.1	0.1	0.02	0.1	0.01	0.33	0.33
Mn	0.20	0.2	0.16	0.17	0.2	0.28	0.2	0.15	0.2	1.4	0.41	1.2
Na	0.5	0.4	0.14	0.3	0.3	0.6	0.3	0.2	0.4	0.2	10	0.3
K	0.8	0.4	0.3	0.4	0.2	1.1	0.4	0.3	0.3	0.3	2.0	0.8
Zn	0.13	<0.02	0.08	0.14	0.07	0.12	0.06	0.09	0.3	0.2	0.13	0.21
Cl	0.08	<0.2	1.1	0.4	<0.2	0.6	<0.2	0.1	<0.2	1.4	14	0.4
S	0.3	<0.1	0.0	0.2	<0.1	0.38	<0.1	0.03	0.08	<0.1	0.24	0.3
Al	0.5	1.0	0.18	0.32	0.6	0.24	0.6	0.24	0.55	0.3	0.03	0.5

Ba, Sr, P, B, Rb

Cr, Mg, As all <0.1

The analysis of the scale accumulated on the Teflon coupon during the sludge seeding experiment is also shown in Table 8.3-9. The high levels of sodium potassium, calcium, and chloride show that large amounts of brine were occluded, and the solids probably include much of the sludge itself.

As noted, none of these additives inhibited the precipitation of silica from homogeneous solution. One substance that did was Natrosol 250LR, a Hercules Company hydroxyethylcellulose, and the results of the analysis of its 257°F (125°C) scale are also shown in Table 8.3-9. It appears to be characteristic of such inhibitors that the solids precipitated in their presence contain less silica and more iron than solids formed from untreated brine. The balance of the composition of the solids in such cases has not been established.

8.3.5 CONCLUSIONS AND RECOMMENDATIONS

- o From the results of the tests of proprietary additives, i.e., the chemical mixtures and the Austral-Erwin process, we conclude that none of these brine treatments have a very beneficial effect on the rates of scaling from the brine of Magmamax No. 1 well. Among the chemical additives, Southwest Chemical's SC-210 shows marginal promise, and a modification of the method of addition of the Austral-Erwin additive might be more effective than the one we tested. Its principal effect is in altering the consistency and adherence of the scale.
- o The addition of sludge as a seeding material for accelerating silica precipitation and lowering the levels of silica super-saturation appears to be viable, but the degree of scale abatement brought about by this treatment could not be assessed. If proper equipment can be used to handle the suspended solids levels that exist with this technique, it should be a fairly successful approach to scale control.
- o Although not detailed here, our parallel studies of generic chemical compounds for geothermal scale control have led to a number types of compounds that inhibit the precipitation of silica and scale formation at the lower temperatures (See Ref. 8.3-1 and 8.3-11 through 8.3-13). Cationic polymers and surfactants, and compounds containing large amounts of ethylene oxide are the most promising. Further experiments will be carried out to discover the optimum compounds within the active classes, and other approaches such as combinations of active compounds and combinations of inhibitors with pH adjustment (up or down) will be pursued.

8.3.6 REFERENCES

- 8.3-1 Harrar, J. E., et al., "Effects of Organic Additives on the Formation of Solids from Hypersaline Geothermal Brine", in Trans. Geothermal Resources Council Meeting, Hilo, 1978, pp. 259-262.
- 8.3-2 Harrar, J. E., et al., First On-Line Test of Organic Additives for Scale Control, in LLL Geothermal Energy Development Highlights Reports, ATHS/ISP-17, Sept., 1978.
- 8.3-3 E. G. Bohlmann, R. E. Mesmer, and P. Berlinski, "Kinetics of Silica Deposition from Simulated Geothermal Brines," in Proc. Int. Symp. Oilfield and Geothermal Chem., Houston, 1979.
- 8.3-4 Harrar, J. E., F. E. Locke, C. H. Otto, Jr., S. B. Deutscher, R. Lim, W. P. Frey, R. Quong, and L. E. Lorensen, Preliminary Results of Tests of Proprietary Chemical Additives, Seeding, and Other Approaches for the Reduction of Scale in Hypersaline Geothermal Systems, Lawrence Livermore Rept. UCID-18051 (1979).
- 8.3-5 J. H. Hill, J. E. Harrar, C. H. Otto, Jr., S. B. Deutscher, H. E. Crampton, R. G. Grogan, and V. H. Hendricks, Apparatus and Techniques for the Study of Precipitation of Solids and Silica from Hypersaline Brine, Lawrence Livermore Laboratory Rept. UCRL-52799 (1979).
- 8.3-6 T. E. Lindemuth, E. H. Soule, S. H. Suemoto, and V. G. Van Der Mast, Proceedings of Int. Symp. on Oilfield and Geothermal Chemistry, San Diego, 1977, pp. 173-186.
- 8.3-7 R. Quong, F. Schoepflin, N. D. Stout, G. E. Tardiff, and F. R. McLain, "Processing of Geothermal Brine Effluents for Injection" in Transactions of the Geothermal Resources Council Meeting, Hilo, Hawaii, 1978, pp. 551-554.
- 8.3-8 Van Note, R. H., J. L. Featherstone, B. S. Pawlowski, "A Cost Effective Treatment System for the Stabilization of Spent Geothermal Brines," 2nd Invitational Well-Testing Symposium Proceedings, Berkeley, CA, 1978, pp. 29-33, Report #LBL-8883.
- 8.3-9 A. L. Austin, A. W. Lundberg, L. D. Owen, and G. E. Tardiff, The LLL Geothermal Energy Program Status Report, January 1976-January 1977, Lawrence Livermore Laboratory Rept. UCRL-50046-76 (1977), pp. 58-65, 69-73, 81-83, 100-102.

- 8.3-10 B. J. Skinner, D. E. White, H. J. Rose, and R. E. Mays, Econ. Geology I, 62, 316 (1967).
- 8.3-11 J. E. Harrar, F. E. Locke, L. E. Lorensen, C. H. Otto, Jr., S. B. Deutscher, W. P. Frey, and R. Lim, On-line Tests of Organic Additives for the Inhibition of the Precipitation of Silica from Hypersaline Geothermal Brine, Lawrence Livermore Laboratory Rept. UCID-18091 (1979).
- 8.3-12 J. E. Harrar, F. E. Locke, C. H. Otto, Jr., L. E. Lorensen, and W. P. Frey, On-line Tests of Organic Additives for the Inhibition of the Precipitation of Silica from Hypersaline Geothermal Brine II. Tests of Nitrogen-Containing Compounds, Silanes, and Additional Ethoxylated Compounds, Lawrence Livermore Laboratory Rept. UCID-18195 (1979).
- 8.3-13 J. E. Harrar, F. E. Locke, C. H. Otto, Jr., L. E. Lorensen, W. P. Frey, and E. O. Snell, On-line Tests of Organic Additives for the Inhibition of the Precipitation of Silica from Hyper saline Geothermal Brine III. Scaling Measurements and Tests of Other Methods of Brine Modification, Lawrence Livermore Laboratory Rept. UCID-18238.

8.4 CORROSION/EROSION

Principal Investigators: J. P. Kozic (SDG&E), F. Schoepflin
(Bechtel National, Inc.)

8.4.1 OBJECTIVES

The objective of this test was to measure the rates and types of corrosion/erosion of various materials of construction exposed to the brine and steam conditions that are expected to be experienced in a 50 MW power plant at the Niland reservoir. This information was used to estimate the cost effectiveness of these materials of construction for a 50 MW power plant with a 30 year design life. Various metals and a polymer concrete lined pipe spool were tested in environments typical for the following applications:

1. Production line piping
2. 1st stage flash vessel (liquid, vapor, and liquid/vapor interface regions)
3. 1st to 2nd stage piping
4. 2nd stage flash vessel (liquid, vapor, and liquid/vapor interface regions)
5. 2nd stage to atmospheric flash drum piping
6. Injection line piping
7. Combined steam condensate.

The test consisted of collecting two sets of data. Coupon exposure tests in the flash vessels served as a screening test and for comparison with other data. Short pipe spools of selected materials in the brine, steam, and condensate piping were for more quantitative information on the type and amount of corrosion/ erosion experienced. To compare the test pieces to the facility in general, ultrasonic thickness measurements were made on various plant components.

A graphic representation of the various types of materials tested is shown in Figure 8.4-1.

8.4.2 BACKGROUND

Corrosion of the carbon steel* components of the GLEF and the two vessels clad with stainless steel (V-1 and V-7), which had been in intermittent 4 stage flash/binary operation for about two years, had been noted. Corrosion was found in both the liquid and vapor spaces of the flash

*"Carbon Steel" when used in this section refers to ASME type A53 Grade B Carbon Steel or equivalent.

*MATERIALS TESTED PRIOR TO TEST NO. 4.

Figure 8.4-1 Materials Tested for Corrosion/Erosion

vessels and in the pipe lines. Additional data were required to supplement the information accumulated to date.

The U.S. Bureau of Mines (See Refs. 8.4-1 and 8.4-2) has reported on 15 and 30-day corrosion tests of a number of different metals and alloys. Lawrence Livermore Laboratory (See Ref. 8.4-3) and Stanford Research Institute (See Ref. 8.4-4) have also contributed information. Both the literature and the foregoing data indicated a probability that the materials now used in the GLEF are subject to significant corrosion during the service life of a power plant and that some other materials may be more acceptable alternatives. A study recently completed by Bechtel for LLL concluded that a number of corrosion-resistant alloys as well as new polymers can be applied as a cladding to carbon steel vessels and lines at a cost which would not preclude them from consideration for use in a geothermal power plant of commercial size (See Ref. 8.4-5).

Carbon steel brine supply lines in the GLEF developed deep pits with a tightly adhering layer of scale which had not been disturbed prior to plant modification during the summer of 1978. Most of the corrosion appeared to be caused by oxygen intrusion although some of the attack appeared to be strongly influenced by hydraulic forces (erosion) as evidenced by damage downstream from fittings and by preferential attack in various regions of a single line. These occurrences indicated the need for duplicate tests on specimens in different regions of the GLEF in order to select the respective materials best suited for each environment in the power plant.

For the pipe spools, the alloys specified in Section 8.4.3.1 were supplied either as the solid metal or as cladding on a carbon steel base. Although clad specimens were thought to be the severest test and therefore preferred, the selection of solid alloy versus clad specimens was determined on the basis of cost and availability at the time of procurement. For coupons, clad material was not included because of the likelihood of an electrolytic couple forming between the cladding and the exposed carbon steel at the edges of the coupon thereby negating the test.

Alloys flame-sprayed on carbon steel were not specified in this test plan because of the failure of large flame-sprayed panels exposed in the first and second stage brine flash vessels of the GLEF in preliminary tests. Plastic coated steel was not specified because of reported poor performance in desalination plants and because of the failure of three out of six large fluoropolymer coated panels exposed in the first and second stage brine flash vessels of the GLEF in approximately 1,400 hours of preliminary testing for the temperatures and pressures encountered in the two largest uses of pipe, the production and injection lines, fiber reinforced plastic pipe (FRP), such as fiber glass, would would require unrealistically

thick walls. If scale should adhere to the FRP and pigging be required, the wire wrapping or wire brushes of the pigs could damage the pipe walls and reduce the wall thickness below acceptable limits in a short time. Therefore, FRP was not tested in high temperature, high pressure areas. A single 3 inch FRP spool was installed in the combined condensate line. The fluid area is at low pressure and temperature, and is not prone to scaling.

8.4.3 TEST DESCRIPTION AND PROCEDURE

8.4.3.1 Test Materials and Equipment

Except for the insertion of spools and other test material as noted, the two stage flash GLEF configuration was utilized for this test. The group of tests on elbows was primarily for observation of erosion. The other groups were intended for observation of corrosion.

10 inch diameter schedule 60X removable spool pieces (approximately two feet long each) were installed in the GLEF as shown in Figure 8.4-2. Since there was concern about the safety of piping made from polymer concrete for hot geothermal fluids under pressure, this material was tested as a liner in carbon steel piping. In addition to the spools shown in Figure 8.4-2, a 12 inch diameter carbon steel spool was installed in the first stage steam scrubber outlet and a three (3) inch diameter FRP vinylester spool was installed in the combined steam condensate pipe. To prevent electrolytic action, each spool piece was insulated from adjacent spool pieces and from the pipe line by insulating gaskets of Viton A fluorocarbon elastomer. All bolts passing through the flanges were insulated by using sleeves and washers of teflon FEP.

Coupons

Coupons of the following materials were exposed to fluids from the Magmamax No. 1 well for 1156 hours:

First Stage Flash Vessel

Hastelloy C-276	Carpenter 20CB3
Hastelloy G	Inconel 625
29 Chrom/4 Moly	Incoloy 825
Commercially Pure	Carbon steel
Titanium (TiCp50)	Indusco Ceramic
Polyurethane coated	Epoxy coated carbon steel
carbon steel	Flurocoat 1302 on Carbon steel

Second Stage Flash Vessel

Inconel 625	Indusco Ceramic
Carbon steel	Epoxy coated carbon steel
Fluorocoat 1302 on	
carbon steel

Figure 8.4-2 GLEF Partial Flow Diagram Showing Location and Identification of Various Test Spools

mounted so the center of each coupon was at the brine/steam interface. This was done to expose the coupons to both steam and brine and to observe the effects of the interface. The preparation and assembly of the coupons was in accordance with the pertinent ASTM procedures.

Elbows and Other Plant Components

Ultrasonic thickness measurements* had been periodically made at the following locations in the GLEF:

- o Magmamax No. 1 well head
- o Woolsey No. 1 well head
- o Condensate pump intake piping
- o Binary control valve discharge elbow
- o East and west condensers
- o Tee and 90 elbow in the first stage brine drain to second stage of "A" train and "B" train
- o First stage flash vessel of "A" train and "B" train
- o First stage scrubber
- o Second stage flash vessels A and B trains
- o Second stage scrubber A and B trains
- o Reactor/clarifier feed piping
- o Media filter feed piping
- o Thickener feed Piping
- o Thickener discharge piping
- o Injection piping to IW-5
- o Reactor/clarifier vessel walls
- o Media filter vessel walls
- o Thickener vessel walls

8.4.3.2 Test Prerequisites

To monitor general corrosion rates in the test spool pieces and vessels, it was necessary to be certain that test personnel were qualified to use the ultrasonic thickness measuring equipment at the GLEF to the degree of reproducibility and accuracy specified in the supplier's instruction manual. In addition, they were familiarized with the contents of ASTM Designations E113-67 (Reapproved 1974) and E114-63 (Reapproved 1971).

Data points for ultrasonic thickness measurements were established for each plant component tested. Prior to starting Test No. 4, wall thicknesses of vessels and other components were measured. Where applicable, a section of the external insulation was cut out for access in such a manner as to be readily replaced and to be removable for

*Measurements taken with a Nortec Model NDT-123 ultrasonic thickness tester.

future measurements. Dirt, rust, and paint on the outside was removed before each reading by lightly sanding the surface to bright metal over an area large enough to accommodate the ultrasonic probe. At the desired test location, a circle of diameter equal to the probe face was scribed on the surface of the metal. After each measurement, the area was protected with a light film of heat-resistant grease. The limitations of this procedure are in Section 8.4.5.

The interiors of the test spools were inspected for rust, pits, or other imperfections prior to initial installation.

The test coupons were identified, photographed and their dimensions and weights recorded.

8.4.3.3 Test Conditions

Normal operation of the plant and all of its components were maintained in order to simulate actual power plant conditions. Refer to Section 4.0 for design operating conditions.

8.4.3.4 Required Data

Daily GLEF operating conditions, as well as pertinent data normally observed throughout the plant, were recorded on the plant operating logs.

Ultrasonic wall thickness measurements were performed on the designated plant components during several plant shut downs. At the termination of the test program the spool pieces described in Section 8.4.3.1 were cleaned and inspected. The pitting depth was measured as was the wall thickness.

Coupons were inspected visually whenever the vessels were opened, and were descaled by hydroblasting in a similar manner as the vessel walls. At the end of the test period, the coupons were removed, cleaned, remeasured, reweighed and rephotographed. Pits were characterized with respect to distribution and depth.

8.4.3.5 Test Duration

The spool pieces and components in the "A" Train were exposed to Woolsey No. 1 fluid for 1,510 hours. Those in the "B" train were exposed to Magmamax No. 1 fluid for 1,560 hours. After exposure, the spools were cleaned, inspected, and measured.

After 516 hours of operation the 'B' train was shut down and the vessels opened. At this time the coupons were photographed and most of the scale removed by hydroblasting. This was done to simulate the treatment the

materials may receive in an operating power plant. The 'B' train was returned to service and operated for a total of 1156 hours on Magmamax No. 1 fuel, after which the coupons were removed from the vessels, cleaned, weighed, measured, and photographed.

8.4.4 RESULTS AND OBSERVATIONS

Coupons

The coupons were mounted in such a way that the center of each coupon was at the brine/steam interface. This was done to expose the coupons to both steam and brine conditions as well as to observe the effects of the interface.

Due to variations in the brine level within the vessels, it is difficult to determine whether the scaling and corrosion were due to steam or brine exposure.

After 516 hours of exposure the "B" train flash vessels were opened for inspection and cleaning.

The Indusco ceramic tiles were found in the bottom of the vessels. The adhesive used to bond the ceramic to the carbon steel supports apparently could not stand up to the brine/ steam conditions of the first or second stage. The ceramic was removed from the vessels.

In terms of physical appearance, thickness, and adhesiveness, the scale which deposited on the remaining coupons was indistinguishable from that which deposited on the vessel walls. To simulate normal vessel cleaning procedures, the scale was removed from the coupons by hydro-blasting without removing them from the vessels. The coupons were again inspected to insure that all mounting bolts and brackets were intact. At this time it was observed that the polyurethane coatings were completely removed, and fluorocoat 1302 coatings were beginning to peel at the top and bottom edges. It is not clear whether the coatings were attacked by the geothermal fluids or removed by the hydro-blasting. However, either case is unacceptable for geothermal power plant application. Both of the carbon steel coupons showed signs of overall corrosion, much of which was apparently caused by oxygen attack from atmospheric sources. The vessels had been opened for extended periods of time prior to geothermal fluid exposure and during the inspection and cleaning.

The coupons were exposed for a total of 1168 hours after which they were removed from the vessels, acid cleaned, remeasured, reweighed and rephotographed. The corrosion rates, weight loss and description of each coupon is shown in Table 8.4-1.

Table 8.4-1 Corrosion Rates of Coupons

<u>Material</u>	<u>Location</u>	<u>Corrosion</u>	<u>Weight</u>	<u>Pitting</u>	<u>Comments</u>
		<u>Rate</u> (mils/yr)*	<u>Loss</u> (%)	<u>Max Depth</u> (Mils)	
Hastelloy C-276	1st Stage	0.72	0.096	0	No visible attack
Hastelloy G	1st Stage	0.51	0.121	5	Infrequent random pitting 1 to 5 mils deep, 1/16 inch diameter.
29CR/4mo	1st Stage	3.71	1.383	6	Random shallow pitting 1 to 5 mils deep, 1/16 to 3/16 diameter, more prevalent in steam.
TiCp50	1st Stage	0.17	3.30	20	Severe large shallow pitting 20 mils deep and 1/2 to 1 inch diameter. Gouge on one edge. Attack more prevalent in brine.
Carpenter 20CB3	1st Stage	1.50	0.50	3	Random shallow pitting 1 to 3 mils deep, 1/32 to 3/32 inch diameter.
Inconel 625	1st Stage	0.90	0.18	4	Random shallow pitting 1 to 4 mils deep, more prevalent in steam.
Incoloy 825	1st Stage	1.24	0.13	2	Many small pits in steam fewer in brine, 1 to 2 mils deep, 1/32 inch diameter
Carbon Steel	1st Stage	76.11	16.03	88	Greenish yellow plus reddish brown discoloration, general corrosion on entire surface with uniform pitting. Some areas of severe pitting in brine section.

*Assumes 6570 Operating Hours Per year.

Table 8.4-1 Corrosion Rates of Coupons (Continued)

<u>Material</u>	<u>Location</u>	<u>Corrosion</u> Rate (mils/yr)*	<u>Weight</u> Loss (%)	<u>Pitting</u> Max Depth (Mils)	<u>Comments</u>
Indusco Ceramic	1st Stage	-----	-----	-----	No apparent attack on ceramic although adhesive did not hold (see text). Primer paint removed by cleaning.
Polyurethane Coating on C/S	1st Stage	-----	-----	-----	Coating completely removed by geothermal fluids or by hydroblasting
Epoxy Coating on C/S	1st Stage	-----	-----	-----	Coating cracked due to geothermal fluid exposure and is easily removable by hydroblast cleaning.
Fluorocoat 1302	1st Stage	-----	-----	-----	Coating intact although peeling from carbon steel backing. Adhesive unsuitable for geothermal environment.
Inconel 625	2nd Stage	1.54	0.11	0	No visible attack.
Indusco Ceramic	2nd Stage	-----	-----	-----	Same as first stage.
Carbon Steel	2nd Stage	49.67	6.68	28	Greenish yellow plus reddish brown discoloration, general corrosion entire surface with uniform pitting shallower than in first stage. No local severe pitting.
Epoxy Coated C/S	2nd Stage	-----	-----	-----	Same as 1st Stage.
Fluorocoat 1302 on C/S	2nd Stage	-----	-----	-----	Same as 1st Stage.

All of the metals tested showed some degree of surface discoloration which was probably due to the acidic solution used to remove the scale deposits. With the exception of the Hastelloy C-276, all of the coupons exhibited some degree of pitting. The corrosion rates for all metals except carbon steel were less than 4 mils per year. Much of the corrosion on the carbon steel coupons appeared to be caused by atmospheric oxygen attack as evidenced by iron oxide corrosion products on the surface and within the pits. There is little or no oxygen in the brine.

Spools

The test spools in the Woolsey #1 supply line were exposed for a total of 1510 hours while those in the Magma-max No. 1 supply line were exposed for 1560 hours. The geothermal fluid in both cases is two phase (liquid/vapor). Like the coupons, the scaling rate and consistency appeared to be independent of material of construction. The wall thickness of the spools were measured ultrasonically during several plant shutdowns and again after the final plant shutdown. The spools were then cleaned by chemical soaking and hydroblasting. This was similar to the treatment given to piping and other plant components. After cleaning, the spools were inspected for signs of corrosion and pitting.

Table 8.4-2 shows the average original thickness and final thickness of the test spools.

The polymeric concrete lined spool showed no significant attack by the geothermal fluids, however, the hydroblast cleaning did remove pieces of the lining. If used in plant construction, compatible cleaning techniques would be needed.

Plant Components

Ultrasonic measurements were taken on various pieces of plant equipment. Table 8.4-3 shows the measured metal lost (or gained) in approximately 1500 hours of operation.

Since the clarifier/filter system was installed after construction of the GLEF, the corrosion rates within this system were addressed separately. Table 8.4-4 shows the metal lost from various components of the clarifier/filter system in approximately 1500 hours of brine operation. In addition to the 1500 hours of operation on brine, the system contained highly oxygenated irrigation water for approximately 35 days for start-up. The clarifier was also drained of brine and water washed on one occasion. This contributed to the measured corrosion rates by introducing oxygen to the system. Visual inspection showed little evidence of corrosion, and the primer coat of paint was still generally intact.

Table 8.4-2 Corrosion of Test Spools

Woolsey No. 1 Production Fluid (A-Train)

	Hastelloy	Inconel	Incoloy	Carbon
	C-276	625	825	Steel
Initial Thickness (inches)	0.3845	0.3443	0.3880	0.6460
Final Thickness (inches)	<u>0.3911</u>	<u>0.3420</u>	<u>0.3852</u>	<u>0.6592</u>
Change (inches)	(0.0066)	0.0023	0.0028	(0.0132)

Magmamax No. 1 Production Fluid (B-Train)

	Hastelloy	Inconel	Incoloy	Carbon Steel	
	C-276	625	825	New	Old
Initial Thickness (inches)	0.3903	0.3953	0.3393	0.6825	0.6503
Final Thickness (inches)	<u>0.3945</u>	<u>0.3943</u>	<u>0.3320</u>	<u>0.6685</u>	<u>0.6815</u>
Change (inches)	(0.0042)	0.0010	0.0073	0.0140	.0088

Interstage	A Train		B Train	
	Carbon Steel	317 LM	Carbon Steel	317 Lm
Initial Thickness (inches)	0.3783	0.4212	0.3853	0.4144
Final Thickness (inches)	0.3770	<u>0.4119*</u>		<u>0.4013*</u>
Change (inches)	0.0013	0.0093		0.0131

* Measurements made with caliper. All others by ultrasonics.

Table 8.4-3 Plant Equipment Wall Thickness Changes*

<u>Location</u>	Mils Lost
Woolsey No. 1 Well Head	12
A Train 1st Stage Flash Vessel**	22
A & B Train 1st Stage Steam Scrubber Inlet	21
A & B Train 1st Stage Steam Scrubber	(0.5)
A & B Train 1st Stage Steam Scrubber Outlet	10
A Train 1st Stage Drain to 2nd Stage 90° Elbow	(29.5)
A Train 1st Stage Drain to 2nd Stage Tee	4.5
A Train 2nd Stage Flash Vessel	29.1
A Train 2nd Stage Steam Scrubber Inlet	9
A Train 2nd Stage Steam Scrubber	14.5
A Train 2nd Stage Steam Scrubber Outlet	25
Magmamax No. 1 Well Head	5.3
B Train 1st Stage Flash Vessel**	1
B Train 1st Stage Drain to 2nd Stage 90° Elbow	(3.1)
B Train 1st Stage drain to 2nd Stage Tee	(18)
B Train 2nd Stage Flash Vessel	8
B Train 2nd Stage Steam Scrubber Inlet	5
B Train 2nd Stage Steam Scrubber	(1)
B Train 2nd Stage Steam Scrubber Outlet	7
Condensate Pump Suction	12
Binary Throttling Valve Discharge	16
Condencer Shell East	(1)
Condencer Shell West	(1)

Note: () Indicates Thickness Gained

*approximately 1500 hours of brine operation (Measured Ultrasonically)

**1 point only

Table 8.4-4 Clarifier/Filter System Wall Thickness Changes*

<u>Location</u>	<u>Mils Lost</u>
Clarifier Feed Line	11
Clarifier Tank Walls	9
Clarifier Tank Dome	9
Media Filter Feed Line	19
Media Filter Filter Chamber	2
Media Filter Holding Tank	1
Thickener Feed Pump Inlet	6
Thickener Feed Pump Discharge 4 in. Pipe	12
Thickener Feed Pump Discharge 6 in. Pipe	10
Thickener Tank	5
Reinjection Pipe to IW5	2

*approximately 1500 hours of brine operation (Measured Ultrasonically)

8.4.5 LIMITATIONS OF DATA

Prior to presenting conclusions, the limitations of the test must be addressed.

Short term corrosion may not be a true indicator of material life. A much longer, more precisely controlled test may be in order.

Several factors affected the individual readings obtained which therefore affected the results and conclusions of the test. For a given section of pipe, there was a significant variation in the wall thickness from one point to another. This was especially true for the carbon steel pieces. As an example, the original thickness readings on the new carbon steel spool, installed in the Woolsey production line varied from a low of 487 mils to a high of 694 mils, a variation of nearly 30%. Therefore, it is extremely critical to measure exactly the same point for each set of readings. This would be true regardless of measurement technique. However, this was not always possible since identification marks made on the equipment, particularly carbon steel, quickly became obliterated.

The second major factor is that the ultrasonic transducer head did not have the same radius of curvature as did the equipment being examined. This caused wobbling of the probe making reproducibility a major problem. Fluctuations of 5 to 10 mils or more were common.

The third major error source was confined to the carbon steel samples. Corrosion on the outside surface made it impossible to determine if the measured metal thickness loss was due to external corrosion or to geothermal fluid attack on the internal pipe surfaces. Associated with this is the fact that the plant was shut down in the same order of time as it was in service. During these extended shut downs, many plant components were exposed to the atmosphere. This resulted in significant oxygen attack of carbon steel surfaces as evidenced by the fact that much of the corrosion products observed were oxides of iron. Since there is little or no oxygen in the Niland brines it must be concluded that this attack from the atmosphere is a significant factor.

It is not certain whether scale, which adhered to most GLEF surfaces, acted to protect those surfaces or contributed to corrosion by forming cells of brine against the surfaces.

8.4.6 CONCLUSIONS

Due to the above uncertainties, it is possible to draw only general conclusions.

The measured rate for carbon steel varied throughout the GLEF. No correlation between location, steam/brine temperature or pressure and corrosion rate was found. Most of the corrosion was apparently due to atmospheric oxygen attack. The life of future power plant components should be extended by eliminating air intrusion.

With the exception of the titanium coupon, the highly alloyed materials had little or no corrosion. However, their high installed cost (four to ten times that of carbon steel) makes them unattractive as construction materials for the first Geothermal Power Plant at the Salton Sea KGRA. Carbon steel appears to be most attractive if air intrusion can be systematically avoided, and acceptable corrosion rates in this environment verified. Periodic replacement or critical area upgrading may be required.

8.4.7 REFERENCES

- 8.4-1 Carter, J. P. and Cramer, S. D., "Corrosion Resistance of Some Commercially Available Metals and Alloys to Geothermal Brines". Corrosion Problems in Energy Conversion and Generation, Transactions of the Electrochemical Society, C. S. Tedman, Editor, (1974), p. 240 et. seq.
- 8.4-2 Carter, J. P. and McCawley, F. S., "In-Situ Corrosion tests in Salton Sea Geothermal Brine Environments." Journal of Metals, Vol. 30, p. 11 (March, 1978)
- 8.4-3 Owen L. B. and Tardiff, G. E., editors LLL Geothermal Energy Development Program - Highlights Report, Lawrence Livermore Laboratory, Report No. ATHS/ISP-17, (September, 1978)
- 8.4-4 Syrett, B. C. et. al. Corrosion Chemistry of Geothermal Brines. Part 2: High-salinity Brine, Stanford Research Institute Final Report (Part 2) to National Science Foundation (RANN) and Department of Energy, (December 16, 1977)
- 8.4-5 Investigation of Materials of Construction for Contract with Acidified Niland-type Brines, Bechtel National, Inc. Report to Lawrence Livermore Laboratory under Agreement for Personal Services No. 7037503, (January 30, 1978)
- 8.4-6 The Ben Holt Company Drawing No. 7429-3200-KE-1: Geothermal Test Facility Piping and Instrument Flow Diagram, Revision dated June 8, 1978.

8.5 EVALUATION OF TESTED METALLIC MATERIALS FOR PLANT APPLICATIONS

Principal Investigators: R. D. McCright, A. Goldberg, E. O. Snell, F. E. Lock, R. McLain, W. P. Frey, W. J. Steele, R. Quong, and G. E. Tardiff (private consultant for LLL)

8.5.1 OBJECTIVES

Measure and document the corrosion and stress corrosion of twenty four ferrous (including different conditions of heat treatment) and eleven non-ferrous materials which were exposed in reduced pH Magmamax No. 1 brine and flashed steam at two temperatures for a one-month test period completed by LLL during 1978. An additional objective was to compare these results to corrosion and stress corrosion data obtained by the U. S. Bureau of Mines and LLL using unmodified Magmamax No. 1 brine. Taken together, these results should delineate those materials which would have a high probability of failure in times short compared with desired plant lifetime and those materials which could reasonably be expected to perform well for the 20 to 30 year periods desired. These evaluations would also permit identification of additional work needed to more fully qualify promising materials for geothermal service in Magmamax No. 1-type environments.

8.5.2 BACKGROUND

Inspection of a section of pipe taken from the GLEF surface piping near the wellhead in mid-1978 suggests that at least the higher temperature carbon steel vessel and piping lifetimes will be limited to well below the desired thirty years. Corrosion and stress corrosion data are needed to identify other materials with adequate resistance to perforating forms of corrosion and resistance to environmentally induced delayed failure. Three bodies of information exist from which such data can be obtained:

1. One month corrosion test in reduced pH brine (LLL): these results were obtained in an aggressive low pH environment and can be taken as conservative relative to unmodified brine. This is useful because: a) materials with a tendency toward stress corrosion cracking can be more certainly identified in the relatively short times of exposure in corrosion tests, and b) high performance materials can be identified for application in critical plant components.

2. United States Bureau of Mines Tests - the USBM conducted corrosion and stress corrosion tests in unmodified Magmamax No. 1 brine and flashed steam for periods of up to 45 days. These corrosion coupons are currently being analyzed and results will be reported by the USBM. Certain of the already available USBM results will be cited below.
3. Timed Interval Corrosion Tests (LLL): - LLL is conducting timed interval (up to 6 months exposure) corrosion testing in unmodified Magmamax No. 1 production brine to: a) determine the time dependence of the localized corrosion rate for carbon and low to intermediate alloy steels, and b) determine the level of corrosion resistance possible with Cr-Mo alloy steels. This work is being funded by the Geothermal Technology Development Program of the DOE and results are expected to be available in late 1980. Certain preliminary results will be cited below.

The present task is mainly oriented toward analysis and presentation of the results of the LLL - one month reduced pH brine corrosion test (item 1 above). These results will be presented in the context of materials selections for plant vessels and piping for a plant utilizing unmodified Magmamax No. 1-type brine. Results from the USBM (item 2 above) and other LLL (item 3 above) will be cited where appropriate.

8.5.3 TEST DESCRIPTION AND PROCEDURE

8.5.3.1 Test Materials and Equipment

A small scale, four stage brine flash system was constructed to simulate the brine and vapor (flashed steam) environments existing in the GLEF. The second and third stages (6 foot height x 14 inch diameter with 1 inch brine lines) were each fitted with racks to permit direct exposure tests of both flat weight loss coupons and bent beam stress corrosion cracking specimens in the brine and vapor environments in each stage. The weight loss coupons were nominally 2 inches x 1 inch x 1/16 to 1/8 inch thick. These coupons were glass bead blasted and bolted onto carbon steel support bars using Teflon washers and sleeves for insulation. The stress corrosion cracking coupons were nominally 3 inch x 1/4 inch x .055 to .080 inch thick. Each of the bent beam specimens contained an electron beam fusion weld (about 40 percent penetration) in its center. No pre or post heating of the welded specimens was used. The specimens were bent in a four point bending fixture to give an outer fiber stress of 90% of the yield strength. Insulation was provided by using ceramic loading rods. Table 8.5-1 gives a listing of the alloys tested together with information on processing and heat treatment.

Table 8.5-1 Identification, Compositions, and Heat Treatments of Materials Tested in 720 Hr Acidified Brine Corrosion and Stress Corrosion Test

Carbon and Low to Intermediate Alloy (<11%) Steels

1009, Q+T	:	AISI 1009 quenched and tempered (1175°F)
A106B, AR	:	ASTM-A106 Grade B, as received
Fe-1/2 Mo, WQ	:	ASTM-A204 Grade B, water quenched
Fe-1/2 Mo, WQ+T	:	ASTM-A204 Grade B, water quenched and tempered (1175°F)
Fe-1/2 Mo, AC	:	ASTM-A204 Grade B, air cooled
Fe-1/2 Mo, FC	:	ASTM-A204 Grade B, furnace cooled
4130, Q+T	:	AISI 4130 (.95 Cr, .20 Mo), quenched and tempered
S00-90	:	(.95 Cr, .30 Mo), quenched and tempered
4130-Mo	:	(.95 Cr, .30 Mo), quenched and tempered
Fe-1 Cr-1/2 Mo	:	ASTM-A387 Grade 12, quenched and tempered (1175°F)
Fe-2-1/4 Cr-1 Mo	:	ASTM-A387 Grade 22, quenched and tempered (1175°F)
Fe-5 Cr-1/2 Mo	:	ASTM-A387 Grade 5, quenched and tempered (1175°F)
Fe-9 Cr-1 Mo	:	ASTM-A387 Grade 9, quenched and tempered (1175°F)

Ferritic and Martensitic Stainless Steels

403SS, Q+T	:	AISI 403SS (12 Cr), quenched and tempered
403SS, AR	:	AISI 403SS (12 Cr), as received
410SS, Q+T (1175)	:	AISI 410SS (12 Cr), quenched and tempered (1175°F)
410SS, Q+T (1250)	:	AISI 410SS (12 Cr), quenched and tempered (1250°F)
410SS, Q+T (1100)	:	AISI 410SS (12 Cr), quenched and tempered (1100°F)
422SS, Q+T	:	AISI 422SS (12 Cr, 1 Mo, .8 Ni), quenched and tempered (1175°F)
430SS, ANN	:	AISI 430SS (16 Cr), 1500°F, 1 hr, water quenched and annealed
439SS, AR	:	AISI 439SS (18 Cr, 2 Mo, Ti, stabilized) as received
26-1	:	26 Cr, 1 Mo, as received
26-1, Ti STAB	:	26 Cr, 1 Mo, .3 Ti, as received
29-4	:	29 Cr, 4 Mo, as received
29-4-2	:	29 Cr, 4 Mo, 2 Ni, as received

Table 8.5-1 Identification, Compositions, and Heat Treatments of Materials Tested in 720 Hr Acidified Brine Corrosion and Stress Corrosion Test (Continued)

Austenitic and Duplex Stainless Steels

304SS, AR	:	AISI 304SS (18 Cr, 10 Ni), as received
316L	:	AISI 361L (17 Cr, 2.5 Mo., 12 Ni), 1975 F/20 min/W.Q. & annealed
317LM	:	AISI 317LM (18.5 Cr, 4 Mo, 14.4 Ni, 3 Co), 2000 F, 10 min, oil quench and anneal
α/γ SS	:	duplex austenitic/ferritic stainless steel, 23 Cr, .03 Mo, 8 Ni, 1.7 Mn, as received (supplied by Uddelholm Steel, designation MC 20)
18Cr-9Ni-4Si, AR	:	18 Cr, 9 Ni, 4 Si, duplex structure as received (supplied by United States Steel)

High Nickel/Chromium Alloys

Inconel 600	:	76 Ni, 15 Cr, 8 Fe; 1850°F/20 min, water quenched and annealed
Inconel 718	:	52.5 Ni, 19 Cr, 18 Fe, 3 Mo, 5(Nb + Ta), .4 Ti, .5 Al; 25% Cr + Aged
Carpenter 20Cb-3	:	33 Ni, 20 Cr, 40 Fe, 2.5 Mo, 3.5 Cu, 1(Nb + Ta); 1725°F/20 min/water quenched
Incoloy 800	:	32.5 Ni, 21 Cr, 46 Fe, .4 Cu, .9 Al, .4 Ti; as received

High Nickel/Chromium Alloys with >5% Mo

Alloy 6X	:	24 Ni, 20 Cr, 50 Fe, 6.5 Mo; as received (supplied by Allegheny-Ludlum Corp.)
Hastelloy G	:	47 Ni, 22 Cr, .19 Fe, 7 Mo, 2 Cu, 2(Nb + Ta); as received
Hastelloy B	:	62 Ni, 1 Cr, 5 Fe, 28 Mo, 2.5 Co, .3 V; as received
Hastelloy C276	:	56 Ni, 16 Cr, 5 Fe, 16 Mo, 4 W, 2 Co, 40% CR + 950F/100 hr + 35% CR

240

Table 8.5-1 Identification, Compositions, and Heat Treatments of Materials Tested in 720 Hr
Acidified Brine Corrosion and Stress Corrosion Test (Continued)

Cobalt Containing Alloys

Haynes 25,ANN+A	:	67 Co, 10 Ni, 20 Cr, 3 Fe; annealed + 1100°F/5 hr/air cooled
Haynes 25,CR+A	:	67 Co, 10 Ni, 20 Cr, 3 Fe; 25% cold rolled + 110°F/5 hr/ air cooled
MP35N	:	35 Co, 35 Ni, 20 Cr, 10 Mo; 40% cold rolled + 1425°F/2 hr/air cooled

Q+T - quenched & tempered
AR - as received
WQ - water cooled
AC - air cooled
FC - furnace cooled

8.5.3.2 Test Prerequisites

Brine flow into the small scale flash system must be taken from a sidestream while the well (Magmamax No. 1) is flowing at design flowrate (400,000 lb/hr) so that the chemistry of the brine can be as nearly representative of plant operation as possible. In addition, there must be a minimum of flow interruptions or periods of reduced flow operation.

8.5.3.3 Test Conditions

Hydrochloric acid to be added to the brine inlet to the 2nd stage to reach a target pH of 4*. Flowrate through the system to be targeted at 1 lb/sec to simulate residence time in the GLEF. Target temperature to be 302 and 257°F (150 and 125°C) in the second and third stages, respectively.

8.5.3.4 Required Data and Observations

Wellhead temperature, pressure, and pH in each stage to be determined 12 times daily. Samples for brine chemistry analysis to be taken 4 times over the course of the test period. Corrosion data to be determined includes corrosion weight loss on the 2 inch x 1 inch test coupons and pit depth measurements on both types of coupons. Amount of cracking to be determined by microscopic examination of polished sections of the stress corrosion test coupons. Crack propagation mode to be determined.

8.5.3.5 Test Duration

Test duration was targeted for 720 hours operation with acidified brine.

8.5.4 RESULTS

8.5.4.1 Expected Results

Expected results include weight loss, pit depths, and extent of cracking for each of the materials listed in Table 8.5-1 after exposure for 720 hours to pH 4 Magmamax No. 1 brine.

*One of the test goals was to determine the degree to which scale could be reduced by reduction of pH to 4. Post test examination of the brine lines in the system showed that scale was reduced by factors of 20, 9, and 2.7 at 410°F (210°C), and 257°F (125°C), respectively, relative to observed scaling in the GLEF using unmodified brine. Scale inhibition was adversely affected by prolonged test interruptions and pH excursions to as high as pH 5.6.

8.5.4.2 Data and Observations

Test Conditions - A short exposure to unacidified brine was necessary for system shakedown. The 720 hour portion of the test was carried out in two segments. A brief review of the operational history of the test is given below:

- o 36 hours exposure to unacidified brine.
- o 196 hours exposure to acidified brine prevailing pH 4.5 (December, 1977).
- o specimens removed from separators, excess scale removed (particularly from 3rd stage bottom specimen rack), stored dry for a month, test resumed.
- o 530 hours exposure acidified brine, prevailing pH 4.0 (January and February, 1978).
- o specimens removed, dried, scale and corrosion products removed by grit blasting (25-80 micrometer particles).
- o specimens weighed, pit depths determined, and selected specimens mounted and polished for optical microscope inspection.

Brine pH varied between 3.5 and 4.5 for the majority of the 720 hours exposure time. Based on daily pH measurements it is estimated that about 110 hours was spent in pH excursions above 4.5 to as high as 5.6 and 90 hours spent in excursions below 3.5 to as low as 2.5. Wellhead pressure ranged between 270 and 370 psia and wellhead temperature ranged between 406 and 442°F (208° and 228°C) over the course of the test period.

After the 720 hour test the specimens in the second and third stages were found to be covered with 0.150 inch of a porous and spongy scale consisting primarily of silica. Many of the stress corrosion specimens were found to have fractured with others remaining in their bent beams fixtures as initially installed. Etch markings on the specimens made prior to test permitted identification.

General Corrosion Results - The weight losses experienced by the various alloys were expressed in terms of the corrosion penetration rate (mpy)* and are reported in

*Corrosion and pit penetration rates are based on measurements made after the 720 hour exposure only. It is not known whether or not the results represent steady state rates.

the first four columns of Tables 8.5-2 through 8.5-3. The values were calculated from the weight loss of three different specimens at each location. The precision was within 30%.

Pitting Corrosion - The pitting corrosion results are reported in the second four columns of Tables 2 through 5 in terms of the pit penetration rate (mpy)*. The values reported without parentheses were determined from the 1 inch x 2 inch specimens; those with parentheses were determined from the 3 x 1/4 inch specimens. In both cases the results are based on the deepest measured pit.

Stress Corrosion Cracking (SCC) - The SCC results are reported in the third group of four columns (no cracking) and the fourth group of four columns (severe cracking) in Tables 8.5-2 through 8.5-5. Absence of cracking was determined by microscopic examination of mounted and polished longitudinal sections. The tensile surface of each specimen was examined in the region of the weld nugget (W), the heat affected zone of the weld (H), and the parent metal (P). Crack positions are noted accordingly in Tables 8.5-2 through 8.5-5.

Metallurgical Structure and Crack Morphology - A large number of the stress corrosion cracking specimens were mounted (longitudinal sections) and polished for evaluation of cracking. These specimens were also used to establish microstructure and crack morphology where appropriate. The results of these inspections are reported in Table 8.5-6.

8.5.4.3 Calculations

Apparent General Corrosion Rates - The apparent general corrosion rate was calculated from the weight loss of the specimens. The conventional way to express corrosion rates is in mils/year (mpy). The apparent general corrosion rates listed in Tables 8.5-2 through 8.5-5 were obtained from the formula:

$$\text{mpy} = 534 \frac{w}{DA t}$$

Where: w - weight loss in milligrams
 D - density of alloy in grams/cm³
 A - specimen area in in²
 t - exposure time in hours

*Corrosion and pit penetration rates are based on measurements made after the 720 hour exposure only. It is not known whether or not the results represent steady state rates.

Table 8.5-2 Acidified Brine Corrosion and Stress Corrosion Test Results: Carbon and Low to Intermediate Alloy (< 11%) Steels

Material	Measured General Corrosion Rate mpy				Apparent Pitting Corrosion Rate mpy				Stress Corrosion Cracking Results							
									No Cracking Observed				Severe Cracking Observed			
	150B	150V	125B	125V	150B	150V	125V	125V	150B	150V	125B	125V	150B	150V	125B	125V
1009, Q+T	27	31	15	16	67					W,H,P						
A106B, AR	38	51	15	15	66	(160)						W,H,P				
Fe-1/2 Mo, WQ							(24)				W				H,P	
Fe-1/2 Mo, Q+T							(10)		H,P		H,P	H,P	W		W	W
Fe-1/2 Mo, AC	16	8	8	6	139	(72)	(12)	(59)		H,P	H,P	P		W	W	W,H
Fe-1/2 Mo, FC						(59)				W,H,P						
S00-90							(59)	(22)			H,P	H,P			W	W
Fe-1 Cr-1/2 Mo	17	19	8	7	125			(28)	H,P			H,P	W			W
Fe-2-1/4 Cr-1 Mo	13	17	7	4	45			(24)	H,P			H,P	W			W
Fe-5 Cr-1/2 Mo					106	(79)	(19)			H,P	P			W	W,H	
Fe-9 Cr-1 Mo	10	7	7	3	67		(5)	(24)	H,P		H,P	H,P	W		W	W

Test Environments: 150B - Immersed in brine at 150°C
 150V - In wet vapor (flashed steam) at 150°C
 125B - Immersed in brine at 125°C
 125V - In wet vapor (flashed steam) at 125°C

W - indicates weld nugget
 H - indicates heat affected zone
 P - indicates parent metal

Table 8.5-3 Acidified Brine Corrosion and Stress Corrosion Test Results: Martensitic and Ferritic Stainless Steels

Material	Measured General Corrosion Rate mpy				Apparent Pitting Corrosion Rate mpy				Stress Corrosion Cracking Results							
									No Cracking Observed				Severe Cracking Observed			
	150B	150V	125B	125V	150B	150V	125V	125V	150B	150V	125B	125V	150B	150V	125B	125V
403SS, Q+T					(54)	(84)			H,P	H,P			W	W		
403SS, AR	6	6	2	4	(54)	(61)			W,P	W,H,P			H			
410SS, Q+T (1175°F)	6	5	4	3	122					W,H,P						
410SS, Q+T (1250°F)						(71)				W,H,P						
410SS, Q+T (1100°F)							(2)	(84)		W,H,P				H,P		
422SS, Q+T						(49)	(2)	(2)			W,H,P	W,H,P			W,H	W
430SS, ANN	3	2	2	2	86	(56)			W,H,P	W,H,P						
439SS, AR					(47)	(19)			W,H,P	W,H,P						
26-1	2	1	1	1	108	(17)			W,H,P	W,H,P						
26-1, Ti STAB					71	(94)			W,H,P	W,H,P						
29-4	1	NIL	1	2	NIL	NIL			W,H,P	W,H,P						
29-4-2					1	12			W,H,P	W,H,P						

See footnotes in Table 2 for meaning of notations.

Table 8.5-4 Acidified Brine Corrosion and Stress Corrosion Test Results: Austenitic Stainless Steels

Material	Measured General Corrosion Rate mpy				Apparent Pitting Corrosion Rate mpy				Stress Corrosion Cracking Results							
									No Cracking Observed				Severe Cracking Observed			
	150B	150V	125B	125V	150B	150V	125V	125V	150B	150V	125B	125V	150B	150V	125B	125V
304SS, AR					(59)	(14)		(8)	W,H	W	W,H	W,H,P	P	H,P	P	
18 Cr, 9 Ni, 4 Si, AR	Nil	Nil	Nil	Nil	(12)	(10)	(14)		W,H	W,P	W,H		P*	H	P*	
316L	Nil	Nil	Nil	Nil	(22)	(12)			W,H	W,H,P			P			
317LM	Nil	Nil	Nil	Nil	(14)	(40)			W,H,P	W,H,P						
	Nil	Nil	Nil	Nil	(24)	(19)			W,H	W,H			P*	P*		

See footnotes in Table 2 for meaning of notations.

* Cracking very slight.

Table 8.5-5 Acidified Brine Corrosion and Stress Corrosion Test Results: High Nickel and High Cobalt Materials

Material	Measured General Corrosion Rate mpy				Apparent Pitting Corrosion Rate mpy				Stress Corrosion Cracking Results							
									No Cracking Observed				Severe Cracking Observed			
	150B	150V	125B	125V	150B	150V	125V	125V	150B	150V	125B	125V	150B	150V	125B	125V
Inconel 600	NIL	NIL	NIL	NIL	(4)	(19)	(5)	NIL	W,H,P	W,H,P	W,H,P	W,H,P				
Inconel 718					(NIL)	(NIL)	(59)	(5)	W,H,P	W,H,P	W,H,P	H,P				W
Carpenter 20Cb-3	NIL	NIL	NIL	NIL	(22)	(19)	(5)	(19)	W,H,P	W,H,P	W,H,P	W,H,P				
Incoloy 800					(11)	(5)	(17)	(4)	H,P	W,H,P	W,H,P	W,H,P	W*			
Alloy 6X	NIL	NIL	NIL	NIL	NIL	(1)	NIL	NIL	W,H,P	W,H,P	W,H,P	W,H,P				
Hastelloy G					(7)	(NIL)	(19)	(130)	W,H,P	W,H,P	W,H,P	W,H,P				
Hastelloy B	NIL	NIL	NIL	NIL	(7)	(4)	(8)	(2)	W,H,P	W,H,P	W,H,P	W,H,P				
Hastelloy C276	NIL	NIL	NIL	NIL	(4)	(NIL)	(NIL)	(2)	W,H,P	W,H,P	W,H,P	W,H,P				
Haynes 25-ANN+A					NIL	NIL			W,H,P	W,H,P						
Haynes 25-CR+A					NIL	(6)			W,H,P	W,H,P						
MP35N	NIL	NIL	NIL	NIL	(2)	(4)	NIL	NIL	W,H,P	W,H,P	W,H,P	W,H,P				

See footnotes in Table 2 for meaning of notations.

* Very slight cracking

Table 8.5-6 Observations on Metallurgical Structure and Crack Morphology for Certain of the Stress Corrosion Tested Specimens

<u>Material</u>	<u>Observations</u>
Fe-1/2 Mo, WQ	Untempered martensite in P* and HAZ*, intergranular cracks in P and HAZ.
Fe-1/2 Mo, Q+T	Untempered martensite in W* and HAZ, cracked thru weld, intergranular crack in HAZ.
Fe-1/2 Mo, FC	Ferritic/pearlitic with decarburized layer (parent metal). No cracks.
500-90	Untempered martensite in W and HAZ. Cracked through weld and HAZ
Fe-2 1/4 Cr-1 Mo	Untempered martensite in W and HAZ. Cracked through weld, Intergranular crack in HAZ.
Fe-5 Cr - 1/2 Mo	Untempered martensite in W and HAZ. Cracked through weld. Intergranular cracks in HAZ.
403SS, Q+T	Untempered martensite in W and HAZ. Cracked through W.
403SS, AR	Untempered martensite in W and HAZ. Cracked through HAZ
410SS, Q+T (1100)	Untempered martensite in W and HAZ, tempered martensite in P. Cracked through weld. Intergranular cracks in P.
439SS, AR	Ferritic in W, HAZ, and P. Equiaxed in HAZ and P. Very shallow crack like corrosion intrusions (.001 inch deep).
26 Cr-1 Mo, Ti STAB	Ferritic Equiaxed grains. Very shallow corrosion intrusions. No cracks.
29-4-2	Ferritic. Equiaxed grains. No cracks.
304SS, AR	Austenitic. Equiaxed grains. Transgranular, branching cracks in P and HAZ.
18 Cr, 9 Ni-4SI, AR	Two phase. Transgranular, branching cracks in P.
316L	Austenitic, no apparent sensitization. Braching transgranular cracks.
317LM	Austenitic. Equiaxed grains. No cracks.

Table 8.5-6 Observations on Metallurgical Structure and Crack Morphology for Certain of the Stress Corrosion Tested Specimens (Continued)

α/γ SS	Austenitic/ferritic. Very small crack-like corrosion intrusions.
Inconel 718	Crack along microstructural discontinuously in weld metal.
Carpenter 20Cb-3	Equiaxed grains. Very fine grained (ASTM9), no cracks.
Incoloy 800	Equiaxed grains. No cracks.
Hastelloy B	Equiaxed grains. No cracks.
Hastelloy C276	Equiaxed grains. No cracks.

* P = parent metal, HAZ - Heat Affected Zone, W - weld metal
 WQ = water quenched; Q = quenched; FC = furnace quenched
 STAB = stabilized; AR = as received; T = tempered

The listed rates are averages obtained from three replicate specimens for each test location. The results are based on an assumption of a constant rate of corrosion. The results should, therefore, be used cautiously since corrosion rates may increase or decrease with time.

Apparent Pitting Corrosion Rate - The apparent pitting corrosion rates given in Tables 8.5-2 through 8.5-5 were calculated by multiplying the maximum measured pit depth observed after one months exposure (720 hours) by 12 to give mpy. The results are based on an assumption of a constant rate of corrosion. The results should, therefore, be used cautiously since corrosion rates may increase or decrease with time.

8.5.4.4 Comparison of Actual and Expected Results

Carbons Steels - A review of available general and pitting corrosion results leads to the conclusion that simple carbon steels cannot (with reasonable corrosion allowances) provide thirty year plant lifetimes throughout the plant. For example, the USBM* 30 day general corrosion rate results for 1020 steel in untreated Magmamax No. 1 brine indicates rates of 43, 42, and 39 mpy at 444, 405 and 352°F (229, 207, and 178°C), respectively. These results are reasonably consistent with LLL results of timed interval tests** in untreated wellhead brine which indicate, after the four month exposure interval, rates of 57 and 72 mpy at 428°F (220°C) for AISI 1010 and ASTM A106B carbon steels, respectively. The LLL timed interval tests will be discussed under the section on low to intermediate alloy steels. The present LLL acidified brine results are also consistent with the data cited above giving, for example, corrosion rates of 17 and 38 mpy for AISI 1009 and A106B at 302°F (150°C) and 15 mpy for both steels at 257°F (125°C). These results are in accord with the expectation that the pH 4 brine would not result in corrosion rates dramatically greater than those for untreated brine (pH = 5.7). At pH below 4 however, corrosion rates would be expected to increase exponentially.

Carbon steel could, of course, be considered for brine service on the basis of a periodic replacement program. The data cited above together with pitting corrosion data in BOM Report No. RI 8350 would have to be used to estimate corrosion allowance and replacement frequency.

* Bureau of Mines Report of Investigation/1979-RI 8350

**To be discussed (Table 8.5-2)

Low to Intermediate Alloy Steels

The data in Table 8.5-2 would indicate the low to intermediate alloy steels would at best offer only marginal (factor of 2) improvement in corrosion life in relation to carbon steels. These results are, however, in very marked contrast to results obtained in LLL timed interval tests conducted in untreated Magmamax No. 1 brine. The LLL Timed Interval Corrosion Task is supported by the Geothermal Technology Development Program of the DOE. The objectives of this task include 1) determination of the time dependence of general and pitting corrosion rate of carbon and low to intermediate alloy steels, and 2) to determine the degree of improvement possible in corrosion life using alloy steels based on chromium and molybdenum. Some preliminary results of this task are give in Table 8.5-7. Table 8.5-7 indicates that the low to intermediate alloy steels offer about a factor of 20 improvement in resistance to general corrosion relative to the carbon steels (AISI 1010 and A106B). Also, the alloy steels showed a much reduced tendency to pit in untreated brine/pits 3 mils deep after 4 months). Thus, while low to intermediate alloy steels would have little advantage for handling reduced pH brines, they would offer a large advantage in handling normal pH (5.8) brine. Such low alloy steels, of course, are much less expensive than high alloy steels or nickel base non-ferrous materials. The low to intermediate alloy steels listed in Table 8.5-2 are capable of being heat treated to produce a wide range of strength levels and microstructures. Some of these, including untempered martensite and microstructures corresponding to strength levels above R₂₂ would be expected to be prone to hydrogen induced stress^Ccorrosion cracking. Indeed, the Fe-1/2 Mo, WQ alloy in Table 8.5-2 which consisted of an untempered martensitic microstructure was found to be extensively cracked (intergranular) in the parent metal. Thus, the successful use of such materials depends on proper test heat treatment to eliminate the tendency toward hydrogen induced delayed cracking.

Reference to Table 8.5-2 indicates that welds in the low to intermediate alloy steels can be extremely susceptible to delayed failure due to environmentally promoted cracking. The low pH test conditions aggravate the tendency toward such cracking and tests at low pH are, therefore, useful in delineating and cracking tendency. The welds were made without pre or post heating and resulted in untempered martensite in the weld region (Table 8.5-6). It is, of course, well known that this metallurgical condition is most sensitive to hydrogen induced stress corrosion cracking. Unfortunately, stress corrosion type tests have not been carried out on welded coupons for the series of Cr-Mo type steels listed in Table 8.5-7 as functions of pre and/or post weld heating designed to optimize resistance to environmental cracking. This type of test program would have to be conducted

Table 8.5-7 Time-Dependent Corrosion Rates of Steels Exposed to Wellhead Brine
(~220°C, ~300 psi) -- Magmamax No.1 Well

Material	Corrosion Rate (Mils/Year) After: (4)					Localized Corrosion Tendency
	1 Month	2 Months	3 Months	4 Months	6 Months	
AISI 1010 Carbon Steel	95	73	82	57	65	Heavy mesa-type attack
ASTM A106 B* Carbon Steel	85	56	67	72	53	Mesa-type attack
1/2 Mo Alloy Steel	1.4	4.2	0.7	0.5	0.6	Pits formed, but 2 mils deep
1 Cr-1/2 Mo	1.5	1.9	0.8	0.4	0.6	Pits formed, depth 2 mils
2-1/4 Cr-1 Mo	1.2	2.7	0.7	0.7	0.7	Most pitted of the alloy steels, pit depth 3 mils
5-1/2 Cr-1/2 Mo	1.3	1.3	0.5	0.4	0.5	A few light pits, 1 mil deep
9 Cr-1 Mo	1.5	1.9	0.4	0.4	0.5	Few light pits after 2-mos. exposure 1 mil depth

- (1) Construction pipe steel for 10-inch GLEF production line
- (2) ASTM A204
- (3) ASTM A387
- (4) Data obtained from weight loss of duplicate specimens in 6 o'clock position
(fully immersed in brine)

to properly qualify a weld procedure. Sudden catastrophic failure of pressurized vessels or pipe containing high temperature brines would constitute an enormous hazard. The importance of careful attention to weld procedure and qualification cannot, therefore, be over emphasized.

Martensitic and Ferritic Stainless Steels

As expected, the martensitic stainless steels (403 to 422) are subject to significant pitting corrosion as well as susceptibility to stress corrosion failure as indicated in Table 8.5-3. Such steels would not be suitable for use with brine or vapor (unscrubbed steam). Use of state-of-the-art turbines which are constructed of such materials would depend on reliable delivery of suitably scrubbed steam to the turbine. As indicated in Table 8.5-5, the crack path in the case of the martensitic occurs intergranularly along prior austenite grain boundaries as expected for hydrogen-induced stress corrosion cracking.

The ferritic stainless steels listed in Table 8.5-3 (Type 430 and 26-1 through 29-4-2) exhibit low general corrosion rates, various tendencies toward pitting, and no detectible tendency toward stress corrosion cracking in the parent metal or weld region. Of these, the alloy 29-4 shows the least tendency to pit and would be expected to be the best selection among the ferritics for geothermal brine service. It should be noted that pressure sensing tubing fabricated from the 26-1 alloy failed after one month exposure in the Magmamax No. 1 well because of its tendency toward pitting. Also, careful polishing and close inspection of polished specimens taken from this tubing revealed transgranular, sawtooth cracks at the base of pits indicating a tendency toward transgranular stress corrosion cracking in the 26-1 alloy. The latter observation is consistent with the Bureau of Mines* observations of cracking of 26-1 exposed in Magmamax No. 1 environments at 352°F (178°C) and above. The improved behavior of 29-4 relative to 26-1 is related to the effectiveness of chromium and molybdenum additions in maintaining passivity in chloride containing solutions.

*J. P. Carter and S. D. Cramer, Field Stress Corrosion Tests in Brine Environments of the Salton Sea Known Geothermal Resource Area, presented at NACE Corrosion 1980 Meeting, paper No. 203, Chicago, Illinois, March 3-7, 1980.

Austenitic Stainless Steels - As expected, the austenitic stainless steel as a class are very susceptible to stress corrosion cracking in the parent metal even in cases where no apparent sensitization is present (see for example 316C in Table 8.5-6) the observed cracking was transgranular (Table 8.5-6) as expected for austenitic stainless steels in strong chloride solutions. The apparent greater resistance of 317LM to cracking is related to its higher molybdenum content.

Nickel/Chromium Alloys - Of the nickel/chromium alloys (Inconel 600 through Incoloy 800) in Table 8.5-5, Inconel 600 exhibited the least tendency toward pitting and no detectable tendency toward stress corrosion cracking. The high nickel/chromium alloys containing 5% molybdenum (Alloy 6X through Hastelloy C-276) as a group show greater resistance to pitting corrosion than the former alloys containing lesser molybdenum. Alloy 6X and Hastelloy C-276 exhibit the best performance among the nickel/chromium alloys. Hastelloy C-276 pressure sensing tubing has been successfully used for more than three months in the downwell environment of Magmamax No. 1. No detectible stress corrosion cracking was observed in the high nickel-chromium-molybdenum alloys, as expected.

Cobalt Alloys - The cobalt alloys listed in Table 8.5-5 were tested even though the current cost and availability of cobalt would rule out all but the most limited use of these alloys. These materials performed as well as the best of the nickel/chromium alloys.

8.5.5 CONCLUSIONS AND RECOMMENDATIONS

It is clear that low to intermediate chromium/molybdenum alloy steels offer the potential of substantially longer life than conventional carbon steels for handling of high temperature Salton Sea Geothermal Field (SSGF) brine. The large potential factor of improvement in corrosion resistance would more than offset the added cost of such materials. Care must be taken however, to properly qualify the heat treatment and welding procedure of such materials for Salton Sea geothermal brine service to avoid possible sudden catastrophic failures due to stress corrosion cracking. As indicated in the present study, several high nickel chromium/molybdenum alloys did not reveal any significant tendency toward corrosion damage in the Magmamax No. 1 brine environments used in the present study (29-4, 6X and Hastelloy C-276). Such alloys should be subjected to further qualification testing and considered for critical applications such as vessel cladding, pressure sensing tubing and downwell instrumentation packages.

8.6 PLANT COMPONENTS & INSTRUMENTATION

Principal Investigator: Gregory J. Hoaglin/SDG&E

8.6.1 OBJECTIVES

The objective of this test was to perform a comprehensive survey of selected plant components and instrumentation exposed to various environments throughout the plant cycle. The plant components monitored for their performance included various types of control valves, line block valves, and pumps. The instrumentation included pressure gauges, thermocouples, and flow measuring devices. The components and instrumentation that were tested were those considered possible problem areas for designing future geothermal power plants. The effectiveness of these various types of equipment were analyzed according to the types of environment they were exposed to. The environments of interest to this test were the steam, brine, condensate and cooling water systems. Where possible, engineering changes to improve component/instrumentation life and performance are recommended. The results of this test should be used as a guide in the selection of components and instrumentation for future power plants at the Niland reservoir.

8.6.2 BACKGROUND

Some equipment originally used at the GLEF performed poorly. Primarily, the causes of the failures were related to scale formation or corrosion. Brine control and line block valves had been susceptible to freezing or complete failure because of scale build-up on valve bodies, seating surfaces, and valve stems. Scale deposits caused problems with the workings of pumps - the brine injection pump (P-2) in particular - blockage of gauge taps, and build-up on thermowells. These problems were primarily responsible for sketchy information obtained on operating conditions in various portions of the GLEF brine system.

To ensure reliable operation of a commercial geothermal power plant with such difficult brines, this program was initiated to identify plant components that were capable of long term operation and to document their performance in the GLEF. Also, the components and instrumentation that didn't work were evaluated attempting to determine the cause of the failure in order to aid any further efforts. (Figure 8.6-1).

8.6.3 BRINE SYSTEM

This section includes a list of each individual component tested in the brine system, with descriptions, results, recommendations, and conclusions of each. (Figures 8.6-2 and 8.6-3 show the location of components and which

Figure 8.6-1 Plant Components and Instrumentation

REFERENCE DRAWING	
DRAWING NO.	TITLE

E-4A & B
CONDENSERSV-2
CONDENSATE ACCUMULATOR
114" Ø x 30'-0" T-T

	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14)	(15)	(16)	(17)	(18)	(19)
FLUID	TOTAL	BRINE	BRINE	STEAM	STEAM	BRINE	STEAM	STEAM	STEAM	STEAM	BRINE	STEAM	STEAM	WATER	WATER	WATER	WATER	WATER	STEAM
M LBS/HR.	4107	4103	400	51.6	103.2	348.4	35.9	35.9	35.9	103.2	103.2	312.3	71.8	800	800	800	800	800	7.1
GPM	12.3	12.3	1.2	1.5	3.1	10.3	1.1	1.1	1.1	3.1	3.1	9.4	2.1	24	24	24	24	24	0.2
STEAM M LBS/HR	103.2	51.6	51.6	51.6	103.2	35.9	35.9	35.9	35.9	103.2	103.2	312.3	71.8	800	800	800	800	800	7.1
° F	363	363	363	363	363	363	212	212	212	340	110	242	228	90	121	165	208	228	228
PSIA	130	130	130	130	130	130	21	20	ATMOS.	125	115	20	ATMOS.	150				20	ATMOS.
MM BTU/HR	3098	154.9	154.9	61.3	123.0	93.4	41.5	6.5	6.5	32.2	8.0	52.6	97.0	46.4	70.6	105.8	140.7	231.5	4.2

THE BEN HOLT CO.	
TITLE	GLEF TWO STAGE FLASH BINARY PROCESS FLOW DIAGRAM
CUSTOMER	SAN DIEGO GAS & ELECTRIC CO.
DRAWN BY	JOE POPE
APPROVED	7/20
DATE	3-22-78
DRAWING NO.	7429-09-D-320
REV.	E

Figure 8.6-3 GLEF Two Stage Binary Process Flow Diagram

were tested in the brine system.) Evaluation of each component began as soon as it was installed and continued until it was removed from service unless otherwise noted.

8.6.3.1 Pumps

8.6.3.1.1 Brine Tank Injection Pump (P-13)

Moyno Pump Co.
Model 9PB
Type CDQ-X

Function

This progressing cavity type pump (design conditions: 675 psig, 50 gpm) was used to pump waste geothermal brine at temperatures up to 150-190F, from the plant's brine pond via a 40,000 gallon waste storage tank into the injection well. P-13 was delivered with a tool steel rotor, cast iron casing, and Buna N synthetic rubber stator. It was expected that the pump would be somewhat more capable of withstanding the scaling environment.

Actual Results

P-13 was operated intermittently for a total of 5290 hours. It was disassembled for the first time on May 5, 1978 after concluding the first intermittent service of approximately 1400 hours. Upon disassembly the rotor showed signs of wear as well as significant corrosion and pitting.

The pump was originally designed for 200°F (93°C) fluid. Since the Buna-N-stator was designed to swell when heated, the rotor was undersized to insure the proper clearances were maintained. However, because of the intermittent operation of the brine tank and pond, the fluid temperature never reached the design temperature. The manufacturer recommended increasing the diameter of the rotor to that which would be thermally suitable for a fluid temperature of up to 160°F (71°C). A plasma applied flame spray coating of chromium oxide was applied to the rotor to increase the diameter for improved pump performance. This was also intended to prevent further corrosion of the tool steel base metal. This eliminated continuous pump duty as an option because of the tighter clearances, but allowed a better evaluation of the pump under normal intermittent duty.

On October 29, 1979, this pump was disassembled for a final inspection. Upon disassembly, it was noted the coating was lacking over the majority of the rotor. It appears that the coating was unable to withstand the environment of the brine and eroded away. The bearings were in good condition with some minor corrosion noted. There was

only about 3/8" of light brown medium hard scale detected at the pump discharge. (Figures 8.6-4 through 8.6-6).

This pump was operated in a non-critical service (draining a waste holding tank) and its performance was not monitored closely. For this service, it functioned fairly well.

Conclusions and Recommendations

From the pump's condition, it can be inferred that it would not have functioned well for extended periods of operation. Although this pump operated satisfactorily for 5,290 hours of intermittent service its materials of construction were not well suited for use with the Niland brines and precluded commercial application. In addition, the fact the pump saw intermittent service with low temperature brines rather than more severe service did not expose it to thermal stress or cycling. The following recommendations are based upon the conditions observed:

- o Further testing or research should be accomplished to recommend a rotor material or coating that is the most effective in resisting the wear and chemical attack of the geothermal brine.
- o Increase pumps ability to operate in more severe service.
- o Replace or control creep in the Buna-N-Stator.

The research into the corrosion resistant materials of construction should be successful based on corrosion tests to date at the GLEF. Hastelloy or Inconel should aid in allowing for a suitable lifetime making this pump more feasible. This coupled with the self-cleaning design of the pump make it a possible candidate for use in a commercial plant.

8.6.3.1.2 Clarifier Feed Pumps (P-16A & P-16B)

Ingersoll-Rand Co.
Model 10X8X815 HOC
Group 3

Function

These horizontal split case pumps (design conditions 1600 gpm at 95 feet TDH) were used to pump geothermal brine at a temperature of 228°F (109°C) from the atmospheric flash vessel (V-15) to the clarifier/filter (V-17). Both pumps were single stage centrifugals with 316SS impeller, casing, and shaft. Redundancy of the pumps was necessary to allow for continuous operation in the heavily scaling environment in this section of the brine system.

Figure 8.6-4 Brine Tank Injection Pump (P-13)

Figure 8.6-5 Brine Tank Injection Pump (P-13) Shaft

Figure 8.6-6 Brine Tank Injection Pump (P-13) Shaft

Actual Results

P-16A was operated a total of 852 hours. This pump was originally installed without grouting the pump base to allow for thermal expansion of the pump suction piping. It was originally believed that expansion joints would not work since they would tend to scale and would not expand or contract. As an alternative to expansion joints a means to accommodate the thermal expansion of the suction piping was tried which allowed the pump to move slightly on teflon plates. This proved to be insufficient since heavy vibration was noted when the pump was put in service. Hence, the pump was grouted and realigned with an expansion joint installed in the pump suction line to be monitored and allow for expansion. Vibration readings were taken after the pump was grouted and proved to be successful when a significant decrease in pump vibration was observed (Figure 8.6-7)

Other problems noted with P-16A were primarily caused by the very heavy scaling seen in this environment. The pump suction line was scaling at about 2.5 inches every 200 hours. The pump discharge line experienced a build up of about 1 inch in the same time frame and the pump impeller developed approximately 1/8" to 1/4" of hard scale. Impeller scale had to be removed by hydroblasting. This unusually heavy scale build-up not only caused obvious operational problems but, scale formation in the pump caused some rather unorthodox maintenance practices to be used in attempting to dismantle the pump for cleaning. The pump was designed to be taken apart by removing the impeller from the casing. As long as the casing was not disturbed, the alignment would not change; but where the front plate matches up to the casing, hard scale formed making it very difficult to remove. Hammers, torches, and other harsh methods were used to break through the scale which acted like an adhesive. Obviously, in time these practices would have damaged the pump. The pump would not operate much more than 150-200 hours before it needed to be taken off line due to scale which hindered the pumps ability to pump enough fluid to prevent V-15 from overflowing.

This pump last saw operation on August 18, 1979, after which time final dismantling took place for an inspection. The overall condition of the pump was fair, with the exception of the impeller. This pump could have been used for further operation with a repaired impeller. The impeller was in poor condition with damage evident at the tip of the vanes. This may have been caused by cavitation erosion (induced by flow restrictions from scale build-up in the pump) or by flaws in the impeller casting.

The (P-16B) clarifier feed pump was operated for a total of 547 hours and saw many of the same problems that P-16A did. The pump base was grouted done before this pump

PRE-OVERHAUL

DATE 5/30/79
 TIME OF DAY 11:34
 AMB. TEMP. 102
 TEMP. (IN) 220°F
 TEMP. (OUT) _____
 PRES. (IN) 55" NPSH
 PRES. (OUT) 50 PSI
 RUNNING AMPS 65
 READINGS TAKEN BY
G.J. HOAGLIN & D.J. MAYS

WAS PUMP OVERHAULED? NO
 WAS PUMP HYDRO-BLASTED? NO
 WAS PUMP ACID CLEANED? NO
 OTHER (EXPLAIN) PUMP WAS RUNNING ON BRINE AND HAD
NOT BEEN GROUTED

Figure 8.6-7 Clarifier Feed Pump (P-16A) Vibration Readings

was put into operation so vibration problems were not encountered. This pump also proved very difficult to dismantle due to scale formation much like that seen in P-16A. This pump was used primarily as a back up to P-16A and as such saw less service.

P-16B was in operation on September 13, 1979, the day the plant was shut down and on October 15, 1979, the pump was dismantled to be inspected for this test. The overall condition of the pump like P-16A was fair and could have been returned to service if needed. The shaft, bearings, impellers, and bowl appeared to be in satisfactory condition with no damage or corrosion evident. Upon routine cleaning of deposits of a gray hard scale $3/4$ " to $1\ 1/2$ " in places was noted (heaviest inside the pump housing where fluid velocity was low). (Figure 8.6-8).

Costs

These two pumps initially cost approximately \$8,000 a piece to design, fabricate, and deliver to the jobsite. On the other hand, it cost approximately \$3,400 for both in subcontracted labor and equipment just to keep the pumps free of scale during the 1500 combined hours they were in service.

Conclusions and Recommendations

Cleaning costs quickly reached almost 25% of the initial cost of these pumps. This appears to be quite expensive to operate these pumps in this type of environment and to justify their use for future applications. Further research should be accomplished to establish where continual cleaning and possible use of another type of equipment becomes more cost effective.

Considering the severe service condition, both pumps operated quite well albeit for brief periods, in their service environment. The heavy scale formation necessitated frequent cleaning, fully justifying the use of redundant pumps.

Because of the very severe environment at this location, probably caused by V-15, there has been some discussion as to whether or not the atmospheric flash vessel (V-15), from which these pumps took suction, should be eliminated. If the atmospheric flash vessel is eliminated, the need for these pumps is eliminated and the problems are solved. Improved flash vessel design may also improve outlet conditions. But, if pumps are required for brine under these conditions, the pumps should be selected keeping following recommendations in mind:

Figure 8.6-8 Clarifier Feed Pump (P-16B) Impeller

- o If this type of pump is to be considered for future use a teflon, neoprene, or viton "O" ring should be installed in the horizontal flanges of the pump to ease dismantling made difficult from scale build-up. These materials should be capable of resisting scale.
- o Some means of cleaning the pump on-line should be tested to allow longer run time, in addition to redundant pumps installed.
- o Other pump designs not evaluated at the GLEF in this environment (e.g. the progressing cavity type) should be considered for this application.
- o A horizontal split case type pump would make alignment much easier after dismantling for repair and cleaning.

Aside from minor modifications to ease maintenance on these pumps, the continual shutdown every 150-200 hours of operation needs to be improved upon. Also careful consideration should be given to the cost of this practice of shutdown and teardown of pumps regularly if design can eliminate these pumps or any like them from future consideration.

8.6.3.1.3 Injection Pump (P-17)

Peerless Pump Division
Model 15L6

Function

The purpose of this nine stage vertical centrifugal pump (design condition 475 psig discharge, 0 psig suction, 1700 gpm at 1000 feet TDH) was to inject spent geothermal brine at a minimum temperature of 180°F (82°C) from the plant into the reservoir. This pump was tested in two different environments: pumping unclarified brine and clarified brine. It was designated P-2 in the former service and P-17 in the latter.

Actual Results

This pump, originally designated P-2, was installed in May, 1976, with 9 stages to pump brine from the fourth stage separator to the injection well.

It failed many times during its three years of service as P-2. The scaling environment in its original location caused severe damage to bearings, which lead to many shaft failures. Much effort was expended in an attempt to find a suitable shaft and bearing material.

K Monel, 17-4PH SS, and Hastelloy C-276, were tried as candidate materials for the pump shaft. All the materials failed. The Hastelloy C-276 shaft failure was probably due to pump misalignment rather than a direct material related failure. This pump was moved to the minimally scaling environment downstream of the clarifier system and designated P-17 before different shaft materials could be recommended or tested further.

The bearings were another design problem related to the scaling environment seen by this pump. Carbon/416SS hardened to Rockwell C60 were originally used along with a non-acidified condensate purge to keep bearings flushed and cooled. After the shaft was found to be scored in areas where it rotated in the carbon bearings, the bearings were redesigned without carbon to 416SS hardened to Rockwell C60. This bearing material also proved unsuccessful when the shaft seized in the bearing.

Tungsten-carbide, Teflon with 15% carbon fill, and SAE 660 Bronze were tested on the next run as bearing materials. Both the Tungsten-carbide and Teflon bearings were found severely scored when another shaft failure caused a shutdown. The shaft fractured in the Tungsten-carbide bearing at the sixth bowl when the bearing seized. The SAE 660 Bronze however, appeared to hold up under the conditions of this environment. From that point on, SAE 660 Bronze was used as the bearing material and provided satisfactory enough results to allow the pump to run in regards to bearings.

Purge water must be taken into consideration as a cause or deterrent of bearing failures. Observation has brought about the theory that some sort of bearing purge is necessary and several types were tried: 1) no purge, 2) brine purge, 3) acidified condensate and 4) non-acidified condensate. Purge water was primarily meant to keep scale deposits flushed out of the bearings and keep the bearings cool. The non-acidified condensate did minimize the typical brine scale but at the same time caused a carbonate scale to form which in itself caused probable bearing and shaft failures. This left using acidified condensate, which appeared to work. The acidified condensate allowed longer operation because of its ability to slow scale formation on bearings and shaft material.

If acidified condensate were used in conjunction with early shaft and bearing materials, perhaps the failures would not have occurred. However, further testing is required to prove this theory.

In May, 1979, P-2 was removed from the scaling environment taking direct suction from the plant's atmospheric flash tank (V-15) and reinstalled downstream of the clarifier/filter system that had just been constructed. At this time

the pump was redesignated P-17 and modified to an 8 stage, 1600 gpm, 450 psig discharge, 4.3 psig suction, at 214°F (101°C) to enable its efficient operation in this new application. This transfer and modification was due to the fact the clarifier/filter system was to remove all supersaturated silica and reduce the suspended solids to a point of which little or no scale would be expected. Since scale was the predominate problem with this pumps operation, removal of the scale problem would allow this pump to operate for a much longer period. Prior to pump (P-17) installation, a Hastelloy C-276 shaft was installed in order to allow this material to be tested again.

After 1391 hours of operation, the GLEF operations and testing were terminated. This pump was given a final inspection. The inspection showed only about 1/4" of hard scale formed in the discharge of the pump, which was a significant improvement. The bearings were in satisfactory condition with signs of wear in the final clearance measurements. The impellers and bowls were in good condition, the best they had ever looked. The only questionable factor in this inspection was the lower shaft was bent .090". The reason for the bend in the shaft is unknown. The shaft was repaired before an investigation could be initiated.

Conclusions and Recommendations

This pump was the source of many major problems and plant shutdowns in its operation in a heavily scaling environment. Many shaft and bearing materials were tested, but scale seemed to be a deterring factor of all candidate materials tested, with the exception of the SAE 660 bearing material. The SAE 660 Bronze did scale, but appeared to stand up better to the wear than bearings tested. Conclusions as to what type of shaft material should be used would be difficult because the pump was moved to its final location in a nonscaling environment before more candidates could be tested. The moving of the pump to a non-scaling environment appeared to significantly aid in lengthening operating time because scale did not appear to be a deterring factor in its operation. However, the pump was not operated long enough in this application, due to termination of plant operations and testing, to determine how much longer this pump would have operated in a nonscaling environment versus its original application in a heavily scaling environment. There is some indication from observing this pump's operation in the final configuration that it may have operated for several thousand hours. Scale was a problem with portions of the pump and with its reduction made the operation of the pump more trouble free. However, this pump may still not well suited to be used for any long-term operation in future geothermal power plants. The reasons being the shaft has a tendency to shear due to its length and numerous bearings. Scaled bearings are all potential friction hazards and would probably occur after extended operation.

Although the last operation is a dramatic improvement based on the pumps past performance, long term operation in a commercial power plant is not only based on equipment reliability but ease of maintenance as well. This type of pump falls short in both categories. The pump was tested at full 1600 gpm design flow for only a short period, which makes the possibility of its running several thousand hours continuously only speculative, thus requiring frequent maintenance. Because of its multi stage vertical design, any maintenance that would be required on the pump required complete removal which took a crane and several people 1-2 hours. Complete dismantling is required to allow access to internal parts. This required days to repair this pump sometimes just for minor repairs.

As an alternative a horizontal split case centrifugal pump, with oversized clearances to allow for moderate scale build-up should be considered in further testing. Flow is steady in this type of pump and a comparatively low starting torque is required; therefore direct coupling to the motor is possible, eliminating the need for a more complex coupling. Ease of inspecting or repairing the pump without breaking pipe connections, located in the lower half of the casing, makes this type of pump more easily maintained. The complete rotating element can be lifted out of the casing when the upper casing half is removed. The relatively high speed, rotary motion, and continuous flow makes it possible for this type of pump to obtain high output with light, compact and inexpensive units which are usually available from off the shelf. Hastelloy C-276 or another equally corrosion-resistant material should be considered as a shaft or impeller material after it is determined by metallurgical examination to be capable of longer than a one-year life. Assuring minimum net positive suction head will require careful design (allowing for scale, transients, etc.) and monitoring.

8.6.3.2 Line Block Valves

8.6.3.2.1 Standard Manual Gate Valves

(3"x150# - 12"x150#) and
(3"x300# - 10"x300#), various manufacturers

Function

These valves were used as isolation, shutoff, and bypass valves for plant equipment and instrumentation and as a means of directing brine flow. These particular valves were used in the low and high pressure areas of the brine system as noted by the pressure ratings of the valves.

Actual Results

Manual gate valves in the brine system generally saw a heavily scaling environment. Valves froze in the position due to scale build-up, which often made operation very difficult. The valves that were operable often would not seat because of hard scale or corrosion. Consequently equipment isolation or shutoff was often not achievable. When one of these valves failed and needed repair, a reconditioned spare was installed in its place. At this point the failed valve was removed and immediately replaced with a reconditioned spare and plant operations resumed. The old valve was then repaired and cleaned (normally hydroblasted and/or acid cleaned) then stored to be used as a spare when another valve was removed from service. The valve body's did however resist the attack of this service.

Overall these valves operated poorly in this service environment. However, the mode of replacing valves after failing was a tolerable alternative to allow the plant to stay online. (Figures 8.6-9 through 8.6-12). This practice increased the maintenance costs because the valves were not reliable and required numerous removals.

Conclusions and Recommendations

The standard manual gate valve is simple in design and inexpensive, when compared to other designs tested. Simplicity, cost, and reliability are important factors to be considered when choosing any component. Although these valves were simple in design they were not cost effective nor reliable for long term operation.

This mode of installing a valve and leaving it in service until the plant shutdown or the valve failed to function, which in the case of the GLEF caused a plant shutdown, in itself is fairly standard throughout fossil fired steam power plants standard. But a normal gate valve in a standard steam power plant usually lasts for years before it needs replacing. In contrast the valves at the GLEF did not last much more than a thousand hours and were frequently totally inoperable.

Only a limited effort was attempted with respect to these valves. Much testing has yet to be accomplished in the area of isolation, shutoff, bypass, and flow diversion valves. The possibility also exists that scaling in the brine system could be eliminated or diminished with chemical addition, process change, or by some mechanical means. Another possibility is to incorporate hydroblast nozzles in these valves and periodically remove scale accumulations (See Section 8.1). If either of these is accomplished then there may have been no need to test other types of valves. However, if the need still exists, then further testing will

Figure 8.6-9 Manual Gate Valves (Brine System)

Figure 8.6-10 Dismantled Gate Valves (Brine System)

Figure 8.6-11 Dismantled Gate Valves (Brine System)

Figure 8.6-12 Manual Gate Valves (Brine System)

be required to determine the most reliable, cost effective valves.

However, until a replacement candidate is proven successful, these valves in conjunction with a strong maintenance effort should work fairly well in a full scale geothermal plant, but should not be considered an acceptable alternative only an interim measure. One alternative is the W-K-M POW-R-SEAL gate valve which is discussed in the following section.

8.6.3.2.2 W-K-M Gate Valves

W-K-M Valve Co.
Pow-R-Seal Model

Function: These W-K-M gate valves were used as equipment isolation valves and flow diversion valves in selected points of the plants brine system.

Actual Results

The W-K-M valves tested were installed in the brine production lines from the wellhead to the first stage flash vessel (V-1 and V-4) and in the clarifier feed line from the atmospheric flash vessel (V-15) to the clarifier/filter (V-17). These valves were checked periodically, usually during a prolonged shutdown, for scale, corrosion, and general valve damage.

The W-K-M's operated very well in the scaling brine environments in which they were tested and were never the cause of a plant shutdown. These valves operated from 200 hours to 1,000 hours without failing mechanically. Inspections showed 1/8" of scale build-up on the inlet and outlet of the production line valve and as much as 2" of scale on the inlet and outlet of the clarifier feed line valves. Even with this much scale build-up the valves still opened and closed with little effort. In comparison, a standard gate valve if still operable in the same application, required some mechanical means to aid in opening or closing the valve. Corrosion was minimal in both the production and clarifier/filter feed line valves. Some erosion was detected on the valve seats which was probably due to throttling the brine flow with the valve. This was done on a few occasions usually to aid a control valve not operating properly. The W-K-M's also proved to be able to seat reliably after heavy scaling had occurred. In comparison, a standard gate valve would seldom seat once heavy scaling had occurred.

Because of the split gate design, the W-K-M incorporated a safety relief. This part of the W-K-M valve that didn't fare too well. This little safety valve plugged with scale and didn't appear to be functional. The safety valves

were never tested so it would be speculation to say whether it would, or wouldn't have lifted, if the occasion had ever arisen.

Conclusions and Recommendations

The cost of these valves may eliminate them from being used in future geothermal power plants, however, the fact is they worked and worked well. The only questions as far as operation is concerned, the relief valve scaling and the mode of operation used to open the W-K-M valve after installation in the plant or during normal plant operations.

The relief valve problem could probably be eliminated with some type of online flushing or self cleaning method. This would require additional testing but this application may not require safety valve and shouldn't eliminate the W-K-M from being used. The other potential problem, which in essence is minor, is the mode of opening the W-K-M valve. It must be fully opened to allow the valve to effect its seal wedging the gate and segment against the seats. This is in direct conflict with normal operation of standard manual valves. The mode of operation with standard manual valves is to fully open, then close about one turn to keep from jamming the disc into the valve bonnet. The potential of damaging the WKM Valves seals by not opening all the way can be eliminated with proper instruction and monitoring of operating personnel in this unique mode of operation.

The W-K-M Valves are recommended for use in future geothermal power plants. They have a longer life span compared to standard gate valves and are more capable of standing up to the harsh geothermal brines experienced at the GLEF. Initial costs are very high for these valves but maintenance is expected to be minimal compared to standard gate valves tested at the GLEF in the same environment. In the long run, the W-K-M Valves may be less expensive than standard gate valves. A cost comparison study would be required to determine the cost effectiveness of these valves.

8.6.3.3 Control Valves

8.6.3.3.1 Full opening Pinch Valve

Red Valve Co.
Model Type A

Function

This valve was a 10 inch pinch valve made by Red Valve Co. with a laminated Viton sleeve and equipped with a Model 21 booster relay. This valve was used for flow control to regulate the level in the second stage flash vessel (V-11).

Actual Results

The Red Valve was used as a control valve in the brine system between the 2B separator (V-11) and the atmospheric flash vessel (V-15). Some problems were encountered with the material of the original valve liner which was an EPR material. This material proved to be non-scale resistant because scale seemed to adhere to the liner and would not break off when the liner was flexed. This flexing of the liner is the design characteristic that makes the pinch valve a candidate for use in a scaling application. An EPDM material was tried next and was in use for about 1,379 hours of operation. The valve in both cases worked satisfactorily but upon inspection scale had again adhered to the liner and there were signs of cracking on the outlet side. At this time the liner was replaced with a new one made of Viton. The Viton material was in operation for about 1,200 hours until plant operations and testing were terminated. At this time the valve was again inspected. Very little scale had adhered to the inlet of the liner. The outlet of the liner was also clean. Overall operation with the Viton liner was excellent and the valve could have been returned to reliable service. (Figure 8.6-13).

Conclusions and Recommendations

The Red Valve was one of the more promising components tested at the GLEF. The pinch valve, with the proper design specifications and lining material, has proven to be the best means of flow control in a heavy scaling environment. The lining material that showed has shown the most promise was Viton. Viton doesn't shed scale entirely but, it does shed it to a point where only a traceable layer of soft scale was present after long term operation. More testing could be done on other lining materials, however, this shouldn't be a high priority test. This valve with a Viton liner should be considered for use in a full scale power plant seeing a heavily scaling brine such as that experienced at the GLEF. However, these valves must not be exposed to high pressure drops, abrasion or other severe mechanical stress.

8.6.3.3.2 Splitcase Pinch Valve

Galigher Valve Co.
Delta Model

Function

This 10" pinch valve was used as a control valve to control the level in the second stage flash vessel (V-14).

Figure 8.6-13 "Red" Valve Pinch Valve

Actual Results

This valve saw approximately 1,650 hours of operation in the GLEF brine system. It was used as a control valve for brine flowing from the second stage separator (V-14) to the atmospheric flash vessel (V-15). It was chosen because of its ability to flex or pinch the liner of the valve preventing scale from building up. This valve worked well in this heavy scaling environment.

Upon termination of GLEF operations and testing the Galigher Valve was inspected. The valve inlet had about 2" of scale and 1/4" of scale was found on the valve outlet. The butyl rubber liner had approximately 1/16" of scale in patches adhering to it. There was definite evidence that the flexing of the valve caused scale to break off in patches but not completely (Figure 8.6-14).

Conclusions and Recommendations

Although the valve functioned, this valve would probably prove to be unsuccessful for use as a control valve in a heavy scaling environment because of the inability of the liner to shed scale. The scale in the valve (about 1/16") adhered to the liner, which was made of butyl rubber. Viton is recommended to be tested as a possible liner for the Galigher valve. Viton has proved to be successful when used on the Red Valve Pinch Valve which was tested in the same environment (For results see Section 8.6.3.3.1). Liners were replaced on the Galigher valve on several occasions at a cost of about \$650 each. This may not be cost effective. However, this valve would be recommended if Viton or another scale shedding substitute material is proven and used in place of the butyl rubber liner.

8.6.3.3.3 Pinch Valve (LCV-734)

RKL Valve Co.
Series LAF-ATOP

Function

This 6" RKL Pinch Valve was used as a control valve in the brine system from the clarifier feed pump (P-16B) discharge to the clarifier (V-17).

Actual Results

When we attempted to place this valve in service the valve would not control the brine flow. The valve fluttered causing rapid oscillations in the brine pressure and flow. If left uncorrected, equipment and piping most probably would have been damaged from the water hammering effect that resulted. After discussions with representatives

Figure 8.6-14 Galigher Pinch Valve

of RKL it was determined the valve was oversized. A new valve liner was installed reducing the cross sectional area of the valve throat which was to allow the valve to operate properly. This modification was unsuccessful. A flow restricting orifice was placed in the line, downstream of the valve, to lower the pressure drop across the valve but was only partially successful in allowing the valve to control flow.

After a reasonable effort to optimize this valves performance, we removed it from service and replaced it with a conventional 6" Fisher ball valve. This replacement valve performed satisfactorily for 328 hours. At this time, the GLEF operations and testing were terminated.

Conclusions and Recommendations

The RKL Valve was unable to meet the requirements of this application. If original specifications had been met it may have operated properly but the replacement liner should have solved the problem. It did not. Therefore this valve is not recommended for future use in controlling flow for this type of application.

8.6.3.3.4 Fisher Ball Valve (PCV-300)

Fisher Valve Co.
Type 476U-8-UR-10009

Function

This 6" Fisher Ball Valve was used as a brine control valve in the inlet to the first stage (V-1) separator from the production well.

Actual Results

This valve operated well, the location of the valve brine expanded upon passing through the control valve and then passed through a 12" to 6" reducer nozzle then through an elbow. The elbow eroded severely and cavitation from the pressure drop probably eventually caused the valve to start leaking. The elbow was patched, but this happened several times with the erosion continuing on through welded patches. The valve itself developed a pin hole leak after a period of time (about 2,000 hours). It was repaired and returned to reliable service. The valve was relocated.

Another problem associated with this valve was that scale built-up on the ball, eventually causing the valve to freeze in position. This valve would generally freeze after approximately 1,000 hours of operation. The scale was easily removed by acid cleaning and the valve could have been ready for service the same day, if cleaning facilities were available on site.

The problem of the ball freezing eased when the valve was modified early in the testing. The ball's spherical contour was remachined to its original shape in the valve body and the gate was changed from a "Vee" configuration to a curved configuration. Stellite was then applied to the leading edge of the curve. This polished surface was hoped to minimize scale from building up on the interface between the ball and the seat. This is presumed to have worked when the valve was still operable after about 1,000 hours of operation.

Upon termination of the GLEF operations and testing, this valve was given a final inspection. (Figure 8.6-15). This inspection showed the valve to be in generally good condition. Little scale was detected on the ball (about 1/16"). The valve internals showed minor corrosion and it was evident the valve packing had leaked because salt deposits were noted in the packing gland area. With the exception of the pin hole leak in the valve body, as was noted earlier in this text, the Fisher Ball valve as modified, operated quite well.

8.6.3.3.5 Kamyr Ball Valve (PCV-301)

Kamyr Valve Co.
Model W1-A-06-AAS-AC2-NPA

Function

This 6" Kamyr Ball Valve had a 316SS body, stellite trim and seals. It was designed for a pressure of 300 psi and a temperature of 750°F and was used as a control valve in the piping from the production well to the first stage (V-4) separator.

Actual Results

This Kamyr Ball Valve was used in the first stage of the plant, which wasn't a heavy scaling environment. However, scale is evident in this area of the plant and did cause the valve to stick during operation. This valve normally operated about 700 - 1,000 hours before needing to be removed for cleaning or repair. These times are probably slightly conservative because something else would usually cause a plant shutdown and the valve would be removed and cleaned whether it needed it or not. Generally, the valve did need to be cleaned and probably would not have operated much more than a couple hundred hours more. The scaling in this valve was not on the ball itself but on the interface between the valve and the valve seat. This valve was also coated with the Ecoalube 642 (See LCV-714 Section 8.6.3.3.6). It appeared to work in minimizing scale adhesion to the ball. There was a very minimal amount of hard brittle scale build-up on the ball (about 1/32") (Figure 8.6-16).

Figure 8.6-15 Pressure Valve (PCV-300) Brine System

Figure 8.6-16 Pressure Valve (PCV-301) Brine System

8.6.3.3.6 Kamyr Ball Valve (LCV-714)

Kamyr Valve Co.
Model PDT-06-AS

Function

This 6" Ball Valve had a 316SS ball and valve body. It was used as a level control valve between the first stage (V-4) separator and the second stage (V-11) separator.

Actual Results

This valve was installed in an environment in which heavy scaling was observed. On several occasions this valve froze in position due to scale build-up between the ball and seat. In an effort to control scale buildup, it was decided to coat the ball with stainless steel and remachine it to its design dimensions. It was then sent to E/M Lubricants to be coated, Through a special process with Ecoalube 642. Ecoalube 642 is a solid film lubricant suspension in concentrated form containing molybdenum disulfide. After the application of the Ecoalube 642, the valve was returned to service to test the affect of the heavily scaling environment on this new coating. After 651 hours the valve began sticking which led to the determination that the Ecoalube 642 had not prevented scale from adhering to the ball. However, it may have prevented the ball from freezing completely, but this can only be assumed because the valve was removed and cleaned before complete failure had occurred.

The mode of operating this valve was to operate it until it started sticking or froze completely with scale. It was then removed hydroblasted, and acid cleaned, then placed back in service.

8.6.3.3.7 Fisher Ball Valve (LCV-712)

Fisher Valve Co.
Vee Model

Function

This Fisher ball valve was used to control the level in the second stage separator (V-14).

Actual Results

The Fisher type "Vee" Ball Valve sustained a lot of scaling during its operation at the GLEF. However, it seemed to handle the scale better than other ball valves in similar applications. The "Vee" design of the ball may have broken away scale to keep the ball operational for extended

periods. The only major problems encountered with this valve was some internal erosion caused by cavitation from the pressure drop across the valve (Figure 8.6-17).

Overall this valve operated well giving approximately 1000 hours of operation before being hydroblasted and acid cleaned.

Conclusions Recommendations (All Ball Valves)

These ball valves saw operation in various portions of the brine system with relatively good success. The predominate problem preventing these valves from long term operation was scaling on the interface between the seat and the ball which caused the valve to stick or freeze. The most successful prevention for this was a stellite coating applied after the ball was remachined. But operation was not lengthened enough to allow for much more than 1000 hours and was observed on other valves without stellite.

These valves are generally recommended for use in a high pressure drop, scaling environment if carefully selected and maintained. However, more testing is warranted to lengthen their operating time before freezing or sticking causes a plant shutdown or valve removal. Other ball coatings, self cleaning designs, hydroblasting periodically, and seals should be tested before these valves are put into an environment where long term reliability is necessary.

8.6.3.4 Temperature Measurement

8.6.3.4.1 Thermocouples

Function

Thermocouples in the brine system were used to measure temperature at various points in the system. These temperature measurements were used for process control and data collection.

Actual Results

Temperature measurement in the brine system was extremely difficult, because of the heavy scaling tendencies of the brine. Thermowells became insulated with scale causing erroneous readings. In some cases thermowells became corroded causing cracks which allowed brine to leak through to the thermocouple element. Mechanical damage also broke or bent other thermowells.

Upon termination of GLEF operations and testing an inspection was made of all thermocouples removed from the brine system. This inspection showed most thermocouple elements to be in good useable condition, indicating the

Figure 8.6-17 Level Valve (LCV-712) Brine System

thermowells didn't leak. The thermowells on the other hand were in poor condition with scale buildup on most to a point where any temperature measurement would have been difficult to any degree of accuracy. Most of the thermowells were not severely corroded so that after scale had been cleaned from them they could have been reused.

Conclusions and Recommendations

Thermocouples/thermowells in the brine system did not function well at all. It is apparent they are not well suited for use where heavy scaling is prevalent. Thermowells also interfered with scale removal activities. Therefore standard thermocouples are not recommended for future use in a scaling, corrosive environment such as that experienced at the GLEF, without a means of keeping the thermowells clean while on-line.

The use of hydroblast nozzles strategically aimed at the thermowell, to provide an on-line method of keeping thermowells relatively free of scale is promising. This should prevent the thermocouple/thermowell from being insulated from the flowing brine. Another possibility is thermocouple patches, attached to piping, heavily insulated, and used in pigged or otherwise cleaned lines. Purges and removable probes are other possibilities.

8.6.3.4.2 Hot Tap

Cosasco Division
Grant Oil Tool Company
Retrieveier, Service Valve, Plug
with Temperature Probe, Access
Fitting and Cover

Function

The access fitting and plug with temperature probe were installed in the first to second stage brine drain line. The intent was to periodically remove (attach service valve and retriever, open valve and remove plug, close valve and remove retriever with temperature probe) and clean without system shutdown.

Actual Results

Initial attempts to use this equipment proved very difficult. Brine scale and salts (left after trapped brine, heated by flowing brine, boiled away) made operation of close fitting equipment difficult. In response, Cosasco supplied a corrective plug, which blocked brine from entering a portion of the internal cavity. Just prior to shutdown, one operation, with this corrective plug, was successfully accomplished. Operation was still time consuming but more experience may reduce this factor somewhat.

Conclusions and Recommendations

Cosasco Equipment can probably be used, as modified, in heavily scaling geothermal environments with frequent maintenance to measure critical brine temperatures. However, to incorporate this equipment on all temperature measurements would be costly. Long term reliability has not been established. Use is not recommended, except as a backup, primarily because of the frequent and time consuming maintenance required.

8.6.3.5 Pressure Measurement

8.6.3.5.1 Diaphragm Pressure Gauge and Strahman Hand Operated Sampling Valve

Trident Engineering Co.
Model #SV-1000
Type 1 1/2" x 1 1/4"

Function

This valve had a 600 psi maximum pressure rating and a plunger travel of 4 inches maximum. The material of the wetted parts was 316SS and a bushing made of Monel. The valve was used for brine sampling and pressure measurement under heavy scaling conditions.

Actual Results

Several types of standard pressure instrumentation were previously tried at the GLEF. The common problem was scale over at the brine interface. This valve was used in conjunction with a diaphragm type pressure gauge. It worked quite well in increasing the longevity of accurate pressure measurement. Originally the pressure gauges would fail after relatively short periods of operation due to scale build-up which closed off the throat of the pressure tap. The Strahman Valve's seat design broke away the built-up scale each time the valve was opened or closed. The valve was inspected upon termination of GLEF operation and testing and showed the Strahman Valve was in good condition. A minimal scale build-up was detected but would not have caused interference with pressure indications. There also was some minor corrosion but, overall the valve appeared capable of operating for a longer period of time. (Figure 8.6-18).

Conclusions and Recommendations

This valve was tested in various portions of the brine system and showed very promising results. The Strahman valve essentially eliminated the problem of plugged pressure tap ports and lengthened the time a pressure device indicated properly. However, more testing for long term

Figure 8.6-18 Strahman Hand Operated Sampling Valve

operation to see how long these valves actually would endure before failing. Improved materials and testing for extended materials may be necessary, but the evidence is sufficient to recommend they be considered for use in future geothermal power plants.

8.6.3.6 Flow Measurement

Two types of ultrasonic flowmeters as well as more common flowmeters were tested. Their specific function was to measure brine flow in a heavy scaling environment.

8.6.3.6.1 Clampitron Ultrasonic Flowmeter

Function

The Clampitron Flow Meter By Controlotron Corporation was expected to be a good candidate for use in a scaling environment because of its external mounting design and preliminary testing. All the parts of the element were outside the pipe with no exposure to the flowing brine. This unit utilized two transducers offset along the axis of the pipe angled so they were aimed at each other. Each transducer was capable of alternately transmitting and receiving ultrasonic impulses. In one direction the time required for a pulse to reach its receiver is decreased due to velocity contributed by the flowing liquid. In the other direction the time is increased. Timing is correlated electronically and the resultant time differential is proportional to the velocity of the liquid.

Actual Results

The Clampitron was field tested on the 10" injection line. It proved successful enough to warrant testing for a longer period under normal plant operations to check its longevity of efficiency.

Installation proved to be difficult. Proper installation required careful selection to avoid entrained gases, surging or debris in lines, high temperature cements, and careful alignment. After prolonged testing the Clampitron was found to give consistent, but erroneous readings after scale started building up on the pipe walls after a short period of time (about 100 hours). As the scale increased, this caused the cross sectional area to decrease, thus increasing fluid velocity. Since the instrument was calibrated based on a fixed diameter pipe, the readout was higher than what the actual flow would be in a heavily scaled pipe.

However, the unit was able to transmit a signal through the scaled pipe. Later, use in pigged sections of line improved performance, but pigging operation upset readings.

8.6.3.6.2 Doppler Effect Ultrasonic Flowmeter

Function

Another ultrasonic flow meter that was tested was the Leeds and Northrup "Doppler" Flow Meter. This was tested on the "B" train brine line downstream of a 180 expansion loop.

Actual Results

This meter was able to measure the flow of a liquid solution with at least 40 micron size particles or bubbles. Leeds and Northrup installed and tested their meter for twelve hours and it proved to read erroneously. The GLEF brine was estimated to have only 20 micron size particles or bubbles, which decreased the accuracy of this meter. At this point it was decided to refrain from any further testing.

8.6.3.6.3 Other Flow Meters

Function

A variety of other meters were installed as a means to enable the measurement of steam, brine, and cooling water flows. Brine was the predominate problem area for flow measurement and was considered a higher priority. However, those tested in other environments are also discussed.

Actual Results

The following is a list of flow meters tested and their results according to the environment they were tested in.

Turbine Meters: These were tested in the brine and steam systems. The turbine meters tested in the brine system failed completely. The sensitivity to scale and other foreign material was high. This stopped operation of the meter completely.

The turbine meters tested in the steam system also failed due to corrosion and scaling of the rotary vanes. Minor modifications and relocation could probably result in a working steam flow measurement.

Orifice plates, venturi meters and flow tubes: These devices all depended on precise openings and configurations to produce a velocity/pressure indication.

The typical orifice plate has a carefully machined bore with a sharp upstream edge. These were subject to abrasion as well as scale. An online removable orifice

meter manufactured by Daniels was not generally successful in preventing these problems. These failed in the brine system but worked satisfactory in the steam and cooling water systems.

Venturi meters and flow tubes are manufactured to close tolerances since their accuracies are dependent on shape and throat diameter. These openings and critical surfaces are totally exposed to the flowing liquid and with scale build-up, readings changed drastically. Differential pressure sensing taps were also required with these devices and when exposed to the brine they scaled closed. These flow instruments failed when tested in the brine system.

Pitot tubes: These are used to sense flow impact. The measurement employs small openings facing directly into the stream being measured. Scale and solids tended to pack the inner passages and clog the openings. These meters also have differential pressure sensing taps which are vulnerable to scale. Experience with these meters showed they were not satisfactory for brine service.

Conclusions and Recommendations

Consistent, accurate, and reliable flow measurement at the GLEF, especially in the brine system, was never accomplished. This in turn made proper heat and mass balances difficult. Brine flow was normally approximated from steam flows (if functioning) or other indications, such as wellhead pressures.

Scale was the main problem with all meters that were tested. Unless the scale is eliminated the only means of flow measurement identified was that which can be accomplished by an outside source not in contact with the brine. The only type tested that meets this requirement is the ultrasonic flowmeter. We tested several at the GLEF with disappointing success. The Clampitron did give short term accuracy and should be researched and tested further to possibly recommend some design modifications that might prolong its accuracy. We did use this device in the injection line downstream of the clarifier/filter system which removed most of the scale causing elements. Results were acceptable, however, on this same line an orifice type flow measurement was also generally successful.

Other potential solutions include hydroblast nozzles, pigging, tracers, and other scale control/removal measures. Further research is recommended to find an accurate long term candidate to measure flow in a scaling environment.

8.6.3.7 Miscellaneous Tested Equipment

8.6.3.7.1 Safety Relief Valves

Dresser Industrial Valve and Instrument
Division
Dresser Industries, Incorporated
P. O. Box 1430
Alexandria, LA 71301

Function

These valves were a safety feature required to allow a means of relieving pressure from the flash vessels in case of over pressurization.

Test Duration

These valves were to be used and periodically actuated until GLEF operations and testing were complete. If valve failure occurred it was to be replaced with a new or reconditioned valve as a safety precaution.

Actual Results

The safety relief valves were used to prevent overpressurization of brine flash pressure vessels. Relief pressures were set at the factory and installed in various locations throughout the plant where needed. Upon termination of the plant operations and testing a final disassembly and inspection was made of these valves. They were all in poor condition, if not inoperable. Rust, scale and corrosion was evident throughout. The valve springs were scaled and rusted badly. Blow back rings were eaten away with rust and corrosion and valve drains were also badly corroded (Figure 8.6-19 through 8.6-22).

Conclusions and Recommendations

The cause of the poor condition of these valves is speculative conversion to a two stage configuration and resulting off optimum design may have been a factor. Weeping may have also occurred.

Frequent inspections and periodic overhauling and resetting of safety valves is necessary. Relocation to protect ports from spray or splash is also recommended. It should be pointed out also that the setting of safety valves could be very difficult due to the scaling tendencies of the brine. When the safety valve is lifted, steam and entrained brine passes through the valve. When the valve tries to reseat, scaling or deposits has already started leaving gaps which in turn causes the valve to bleed through under normal operations causing further damage. Therefore, valves should

Figure 8.6-19 Safety Relief Valves (Dismantled)

Figure 8.6-20 Safety Relief Valves (Dismantled)

Figure 8.6-21 Safety Relief Valves (Dismantled)

Figure 8.6-22 Safety Relief Valves (Dismantled)

be reset during maintenance using a clean non-scaling fluid or removing them for thorough maintenance and resetting.

In geothermal brine environments, this equipment has been found to quickly become inoperative. Therefore, a program of careful design, operation and frequent inspection and testing is necessary to insure this equipment remains in serviceable condition.

8.6.3.7.2 Vacuum Pump (VP-1)

The Nash Engineering Company
Model CL-402

Function

This Nash rotary liquid ring vacuum pump was made of cast iron. The rotor and shaft were stainless steel and the pump case and internal parts were ceramic coated. The pump capacity at 1600 RPM and 24 inches Hg (approximately 3.0 psia) was 220 ACFM at inlet conditions based on 30" barometric pressure and 60°F seal water. This pump was used to remove non-condensable gases, primarily from the condensate accumulator vessels.

Actual Results

The original design of the vacuum system provided that during normal operation the pump would be used to evacuate non-condensibles from the 4th stage heat exchanger condensate, hot well (V-13). A second designed duty of this pump was to evacuate air from the Binary Loop prior to charging it with isobutane. A decision was made to startup the GLEF with distilled water in the Binary Loop instead of isobutane which eliminated the latter duty. In order to remove non-condensibles from the condensers and accumulator, the vacuum pump was changed to take suction directly from the accumulator and the condensers were vented directly to the accumulator.

The original vacuum pump at the site was supplied by Kinney. Numerous problems (seal water reaction with noncondensable gases, excessive wear and maintenance) led to replacement with a ceramic coated unit from Nash.

The pump was inspected by Nash on several occasions with only bearings being replaced due to normal wear. Seal water was acidified condensate to minimize reactions with gases. This pump operated for over 10,000 hours of intermittent operation with satisfactory results until GLEF operations and testing were terminated. Only minor use was made of this unit during two stage operation.

Conclusions and Recommendations

The Nash pump was satisfactory and should be considered for use in a future geothermal power plant. However, the design of the non-condensable gas removal system may not require this type of pump.

8.6.4 CONDENSATE SYSTEM

This section includes a list of each individual component tested in the condensate system, with descriptions, results, conclusions, and recommendations of each that was tested. Figure 8.6-3 shows the location of components in the condensate system. Evaluation of each component began as soon as it was installed and continued until it was removed from service (Figure 8.6-1)

8.6.4.1 Pumps

8.6.4.1.1 Purge Water Pump (P-7)

Sunstrand Corporation Fluid Handling Division
Model P-2000
Type P-2BHA

Function

This Sunflo pump (design condition 15 gpm at 1250 feet TDH) was used to supply high pressure steam condensate for bearing purge and seal water flushing to plant equipment and (later) to also supply wash water to the steam scrubbers.

Actual Results

This pump was originally sized too small for the purge water requirements at the plant. With a modification of the discharge diffuser and replacement of the 25 HP motor with a 40 HP motor, the pump was able to keep up with the purge water demands. This pump operated approximately 5,305 hours before being shutdown for final inspection. The final inspection showed the pump had a thin gray film on the pump exterior. The impeller housing was about half full of mud or sludge, which was believed to have fallen off the inside of the piping on the suction side of the pump. The pumps' shaft, bearings, and impellers were all in good condition showing minimum signs of wear. In fact, the overall condition of the pump was good and except for the mud or sludge, could have operated for many hours before requiring a shutdown.

Conclusions and Recommendations

Since it was only one of two pumps capable of supplying enough purge water, this pump performed well with a minimum amount of overhauls and repairs. This pump is recommended for use in a similar application.

8.6.4.1.2 Purge Water Pump (P-7A)

Sunstrand Corporation, Fluid Handling Division

Function

This pump was used to supply high pressure steam condensate for bearing purge and seal water flushing to plant equipment and steam scrubbers. It was designed to the same specifications as P-7 (Section 8.6.4.1.1).

Actual Results

This pump was one of two used to supply purge water for plant equipment. It was significantly undersized to handle the purge water requirement at the plant. For this test it was used in parallel with (P-7) purge water pump. Upon GLEF operations and testing termination, this pump was dismantled for a final inspection.

The inspection showed there was no scale or corrosion. The shaft, bearing, and impellers were in good condition. The pump condition overall was good and could have been operated for an indefinite period of time. However, this pump being undersized, was run only as a backup or to supply any additional flow needed to supplement (P-7) purge water pump.

Conclusions and Recommendations

P-7A as previously stated was significantly undersized for this application. Because of the limited use few conclusions can be made other than the performance during this period was good.

8.6.4.1.3 Condensate Pump (P-9)

Goulds Pump Co.
Model 10
Type HAC VIC

Function

This Goulds motor driven pump was a vertical three stage centrifugal pump (design conditions 230 gpm at 95 feet TDH). It was originally used to pump steam condensate at a temperature of 200F with a suction pressure of -2.0 psig, and a discharge pressure of 37.5 psig (4 stage flash/binary conditions). The pump's impeller, casing ring, impeller rings, and shaft sleeve were made of bronze. The shaft and packing gland were made of carbon steel. The pump casing and nozzle were made of cast iron.

Actual Results

This pump was operated from original plant start-up until plant operations and testing were terminated, with numerous failures. It was also used to pump steam condensate from the fourth stage steam scrubber to the cooling pond.

Scale caused numerous bearing failures under four stage operating conditions. Bearings were frozen with scale and had to be reamed out in order to be used again. The shaft material was changed from 416SS in hopes of lengthening operating life. Journal bearings were coated with 136-F ceramic and impeller and bowl wear ring clearances were corrected. Acidified purge water was piped to the pump bearings to help keep scale build-up to a minimum and provide cooling. These modifications were made prior to startup in the two stage mode based on experience gained from the four stage operation.

This pump saw over 1000 hours of intermittent operation under two stage conditions before plant shutdown in September 1979. This pump was disassembled at that time and inspected. The pump shaft was in good condition. It could have been used for many more hours of operation if needed. However, the pump columns and spiders were fatigued and the bowls were eroded badly. The outside of the pump bowls had about 1/8" thin black film looking somewhat like a heavy mud. The pump impeller was in the worst condition due to erosion and probably would have failed in a relatively short time.

8.6.4.1.4 Condensate Pump (P-10)

Goulds Pump Co.
Model 10
Type HAC VIC

Function

This Goulds pump was a three stage vertical turbine pump. It had bronze impellers, bowl bearings, and impeller wear rings. The column shaft and bowl shaft were made of 416SS. This pump was used to pump steam condensate from the hotwell (V-13) to the cooling pond. It was designed to an application temperature of 200°F, discharge pressure of 37.5 psig, suction pressure of -2.0 psig, and flow of 230 gpm.

Actual Results

This pump saw long term operation (about 3000 hrs) before it was overhauled. At the time it was overhauled it was in a near failing condition as evidenced by the discharge pressure dropping and the hotwell (V-13) not being pumped down at a proper rate. Upon disassembly, the pump purge

connections were found to be broken so that no purge water flowed to the bearings. The pump bowls were also deteriorated, as were the spiders in the columns. The pump was repaired and placed back in service. 188 hours later the No. 4 bearing froze causing another shutdown. Scale was found in the bearing which scored the bearing and journal. Apparently, a loose piece of scale worked its way into the bearing, causing it to freeze up. This was repaired and the pump was again placed into service.

After another 219 hours of operation the GLEF operations and testing were terminated and the pump was given a final inspection. This inspection showed the impellers were worn on one side of the wear ring. The shaft, by looking at journal wear seemed to have a slight runout. The bearings were in fair condition but the bowls were eroded badly.

Conclusions and Recommendations (P-9 & 10)

These pumps were used to pump steam condensate which is an important function to allow the plant to operate for extended periods of time. P-9 and P-10 did not perform reliably due to excessive shutdowns for internal repairs. It is recommended more testing be done on this style of pump with a different bowl material and impeller, such as 316SS. A horizontal, centrifugal, single stage pump should also be considered for this application in a full scale power plant.

8.6.4.1.5 Condensate Pump (P-14)

Ingersoll Rand Co.
Model 3"x2"x6"
Type VO1 VOC

Function

This Ingersoll Rand centrifugal single stage, open impeller, inline pump (design condition 72 gpm at 41 feet TDH) was installed to pump steam condensate out of the second stage heat exchanger (E-1B).

Actual Results

This pump was used in the condensate system for 1,655 hours until the GLEF operations and testing was terminated. Upon the termination of plant activities it was disassembled for a final inspection. The pump had about 1/16" of light brown hard scale inside the housing and impeller arch (Figure 8.6-23). The shaft and bowl were in good condition with a minimal amount of corrosion evident. The impeller fins were bent and broken off as if some hard foreign material had somehow entered the pump.

Figure 8.6-23 Condensate Pump (P-14)

With the exception of the impeller condition this pump was in good condition and still could have operated much longer before a forced shutdown would occur.

Conclusions and Recommendations

If an inline pump required for use in pumping steam condensate, this one appears to be an acceptable choice. Although 1,655 hours of operation is not an especially long period of time to operate without being shutdown final condition was good. Further testing should probably be accomplished. Since other pumps were not tested a comparison cannot be made. Condensate pumps should be exposed to minimum chemical attack if steam quality is good and if proper heat exchanger design principals are taken into consideration. The specifications of the pump should then be relatively easy to establish and meet. Therefore, there should be a several good candidates to choose from and compare.

8.6.5 COOLING WATER

This section includes a list of each individual component tested in the cooling water system, with descriptions, results, conclusions, and recommendations of each that was tested. Figures 8.6-2 and 8.6-3 show the location of components in the cooling water system. Evaluation of each component began as soon as it was installed and continued until it was removed from service.

8.6.5.1 Pumps

8.6.5.1.1 Cooling Water Pump (P-3)

Peerless Pump Division

Function

This pump (design condition 21,000 gpm at 93 feet TDH) was a single stage, vertical hollow shaft, closed impeller, centrifugal pump. It was used to pump circulating water from the cooling pond through the tube side of the condensers to remove heat energy from the plant.

Actual Results

This pump is very similar to those used in standard steam power plants for circulating water through condensers. However, it was seeing an environment that was high in iron and also slightly corrosive because of the source of makeup water. The pump operated for 5,178 hours with one intermediate overhaul and was shutdown upon termination of the GLEF operations and testing. Final dismantling and inspection took place in later 1979. There was approximately 1/8" of

brown, hard, flaky, rust and scale in the pump column above the water line. The shaft, bearings, and pump bowl were in good condition with very little wear and corrosion evident. The impellers were eroded on the inlet tip of the vanes about 1 1/2". The wear rings showed little wear but were pitted severely in areas. This pump was close to requiring a forced shutdown for overhaul (Figures 8.6-24 and 8.6-25).

Conclusions and Recommendations

Taking into consideration the cooling pond was chemically unstable for some time before the final shutdown, its operation was quite good. It was pumping a fluid that was high in chemical activity. Three different water treatment programs had been tried, in addition to dissolved gases and brine carry over in the condensate. The fact that the bronze impeller experienced attack and particle erosion was not unexpected.

Further testing and material selection should be considered if this type pump is to be used taking suction from this type of source. However, this type of pump should be acceptable.

8.6.6 STEAM SYSTEM

This section includes a list of each individual component tested in the steam system, with description results, conclusions, and recommendations of each that was tested. Figures 8.6-2 and 8.6-3 show the location of components in the steam system. Evaluation of each component began as soon as it was installed and continued until it was removed from service.

8.6.6.1 Control Valves

8.6.6.1.1 Valves (PCV-360 and PCV-361)

Masonelian Valve Co.

Function

Masonelian Butterfly Valves were used to control steam flow from the second stage steam scrubbers (V-10 and V-12) to the second stage heat exchangers (E-1B and E-1C) respectively.

Actual Results

Both these valves operated well. There were no major operational problems encountered with either valve. Both valves were given a final inspection upon termination of GLEF operations and testing. Upon disassembly the valves

Cooling Water Pump Shaft and Impeller

Cooling Water Pump Suction Spider

Figure 8.6-24 Cooling Water Pump (P-3)

Impeller Erosion

Impeller Erosion

Discharge Head Corrosion

Figure 8.6-25 Cooling Water Pump (P-3)

looked as good as they operated. The only noticeable attack on the valve was some minor surface scale on the valve disc and body probably due to oxidation from exposure to the air after removal.

Conclusions and Recommendations

As steam valves, these two valves operated well. Scale and corrosion was minimal. The steam quality would be consideration here and may preclude selection if corrosion or scale were excessive. Butterfly valves are not new to the control of steam and therefore, except for the noncondensable gases and carryover this was considered a noncritical test. Other valves would have probably worked just as well in this application.

8.7 Brine Chemistry

Principal Investigator: C. H. Haas (SDG&E)

8.7.1 OBJECTIVES

The objective of this test was to characterize the chemistry of the Niland Geothermal brines. Analysis was performed on liquid brine, steam, noncondensable gases, and condensate under both one and two well flow conditions and two and four stage flash cycle configurations. Scale compositions at critical points in the system were also analyzed.

8.7.2 BACKGROUND

Geothermal brine is a natural fluid with inherent characteristics at the wellhead that cannot readily be altered by the user. In order to design and operate a geothermal power plant, it is necessary to know the properties of the geothermal brine throughout the plant. As the geothermal brine passed through the facility, heat was extracted and the properties of the fluid changed. These varying properties, plus the characteristics of other fluid streams, such as noncondensable gases, steam and condensate were monitored throughout the entire three years of operation.

8.7.3 PROCEDURES

8.7.3.1 Sampling Procedures

Obtaining representative samples of the geothermal fluids at the GLEF was difficult. Many improvements to the sampling techniques were made in order to obtain representative samples. The most successful are discussed in this section.

Stainless steel sample lines with Inconel coolers were found to be an acceptable way of preventing chemical reactions between the geothermal fluid and the sample line. This was demonstrated in August 1978 using the steam entering the first stage scrubber. A stainless steel sample line was installed next to the original mild steel sample line. Severe iron contamination of the samples taken from the mild steel sample system was observed. The iron concentration in the mild steel sample line was ten times higher than that in the stainless steel sample line due to the attack on mild steel. As a result, all of the sample lines were changed to stainless steel and the problem of iron contamination was reduced.

Purging brine sample lines with geothermal fluid is common. However, sample lines became scaled from residual brines. Prior to sampling, brine is flowed for a period of two (2) to five (5) minutes before the sample was taken for chemical analysis. After the sample was drawn, the lines

were purged with cooling water to wash out any residual brine or scale. This technique was incorporated in November 1978, and was found to be very successful in keeping the lines clean. It was continued until the final day of plant operations.

The steam lines were also purged with cooling water. However, in January 1979, sample contamination from leaking purge water valves was suspected and the fresh water purging for the steam lines was discontinued as this application is not as critical.

Traverse sampling of the brine at the GLEF was initiated in November 1978. The traversing (retractable) probe was manufactured by SDG&E and patterned after the probe used by Lawrence Livermore Laboratory (Figure 8.7-1). The upper photo shows the position of the probe when not in use and the lower shows the position of the probe when a sample was to be taken. The probe was installed in the production line before the two phase geothermal fluid entered the first stage separator. Comparison of the samples drawn using the retractable probe with the samples drawn using the conventional flush mounted sample port, indicated that the retractable probe provided a more representative sample.

In January 1979, a second retractable probe was installed in the brine outlet line of the second stage separator. At this location, the scale buildup on the pipe walls was quite severe and by using the traversing probe, a more representative sample could be taken by eliminating the filtering effect of the scale. The filtering effect was due to the sample being drawn through the scale into a wall sample port. This caused unrealistic results in the chemical analyses, particularly for silica. The silica concentrations would drop as much as 200 ppm from the first stage separator brine outlet to the second stage separator brine outlet. The retractable probe was used in the second stage brine to determine the effects of the scale on fluid sampling. It appeared the scale on the pipe walls was filtering out the larger particles, such as silica, and this filtering effect was reflected in the analysis. The use of these retractable probes was continued until the final day of GLEF operations.

Samples of the geothermal fluid were initially taken on a daily basis. However, few variations in composition were observed and after a period of months, the sampling frequency was changed to every other day or once a week. In August 1978, daily sampling was reinstated to precisely establish the effects of modifying the GLEF from the four stage flash system to the two stage flash system. This modification did not change the wellhead properties, but significantly altered the properties of the brine through the GLEF. From November 1978 to March 1979, the samples

RETRACTED POSITION

EXTENDED POSITION

Figure 8.7-1 Traversing Sample Probe

were taken on Mondays, Wednesdays and Fridays, since the two stage brine characteristics were now known.

Scale samples were taken from the production lines, all separators and scrubbers, brine lines between the first and second stage separators, atmospheric flash vessel, reinjection lines and the heat exchangers during GLEF shut downs.

Steam samples were taken before and after the scrubbers in each stage and at the exit of the heat exchangers at the same time as the brine samples were taken.

8.7.3.2 Noncondensable Gases

Noncondensable gas samples were taken periodically between November 1976 and January 1978. The noncondensable gas sampling was resumed again in August 1979.

Noncondensable gas samples were taken at the Magmamax No. 1 wellhead, Woolsey No. 1 wellhead, and the vent gas separator. In August 1979, noncondensable gas samples were taken at the inlet and outlet of the first stage steam scrubber.

8.7.3.3 Scale

Scale samples were taken from pipes, valves, and vessels throughout the GLEF during shut-downs.

8.7.3.4 Analytical Procedures

Analytical Equipment

The chemical analyses at the GLEF facility were performed using the following analytical equipment:

- o Atomic Absorption Spectrophotometer
Manufacturer: Perkin-Elmer
Model: 306
Sensitivity: varies with the element being measured. (Table 8.7-1 for the expected variance for each element).
- o Gas Chromatograph
Manufacturer: Varian
Model: Varian Aerograph - Series 1400
Sensitivity: $\pm 2\%$
- o UV - Visible Spectrophotometer
Manufacturer: Perkin-Elmer
Model: Coleman 295
Sensitivity: varies with the element or compound being measured. (Table 8.7-1 for the expected variance for each element or compound).

Table 8.7-1 Element or Compound Analyzed, Analytical Procedure and Expected Variance

<u>ELEMENT OR COMPOUND</u>	<u>ANALYTICAL PROCEDURE</u>	<u>EXPECTED VARIANCE</u>
Al	Atomic Absorption	± 4%
Ba	Atomic Absorption	± 2%
Ca	Atomic Absorption	± 4%
Cr	Atomic Absorption	± 4%
Co	Atomic Absorption	± 4%
Cu	Atomic Absorption	± 3%
Fe	Atomic Absorption	± 1%
Pb	Atomic Absorption	± 2%
Li	Atomic Absorption	± 1%
Mg	Atomic Absorption	± 3%
Mn	Atomic Absorption	± 3%
Ni	Atomic Absorption	± 4%
K	Atomic Absorption	± 1%
Si	Atomic Absorption	± 1%
Ag	Atomic Absorption	± 4%
Na	Atomic Absorption	± 2%
Sr	Atomic Absorption	± 1%
Sn	Atomic Absorption	± 4%
Zn	Atomic Absorption	± 1%
Alkalinity	Phenolphthalein and Methyl Orange Method	± 4%
Ammonia	Specific Iron Electrode	± 3%
Boron	Carmine Method	± 2%
Chloride	Argentometric Method	± 1%
Chloride	Mercuric Nitrate Method	± 1%
Density	Hydrometer	0.005g/1
pH	pH meter	± 0.01
Sulfate	Turbidimetric Method	± 1%

- o Single Pan Balance
Manufacturer: Sartorius
Model: 2442
Sensitivity: ± 0.05 mg
- o pH Meter
Manufacturer: Orion Research
Model: 701 A / digital ionalyzer
Sensitivity: ± 0.01 unit
- o Conductivity Meter
Manufacturer: YSI
Model: 31
Sensitivity: $\pm 3\%$

Brine Steam Analysis Procedures

The analytical procedures for the GLEF were initially developed in May, 1976. The primary analytical method used was Atomic Absorption Spectrophotometry with standard addition. Standard addition is a process in which a known amount of analyte is added to the sample containing the element to be analyzed. The original unknown sample and the sample with the analyte added are then run on the Atomic Absorption Unit. The results are graphed using the absorption versus the amount of analyte added to determine the amount of the element present in the unknown sample.

After completing a statistical analysis on the established procedures in November and December 1978, some procedures were modified. For example, a comparison study was made using standard addition and without standard addition (direct analysis after dilution). The samples analyzed with standard addition exhibited greater fluctuations which were attributed to the extra dilution steps required by the standard addition procedure. Therefore, the use of standard addition was discontinued.

A very useful procedure when monitoring the geothermal fluids is a cation/anion balance. Simply stated, there exists a ratio between the cations and anions in a solution. In a laboratory, if sodium chloride (NaCl) is added to a beaker of distilled water, the NaCl crystals dissociate to the ionic state of Na^+ (cation) and Cl^- (anion), so for every cation of Na^+ there exists an anion of Cl^- in a ratio of 1:1. In the case of the geothermal fluid, the major cationic components are Na^+ , Ca^{++} , K^+ and the major anionic component is Cl^- . The ratios for these components are 1:1, 1:2 and 1:1, for NaCl, CaCl_2 , and KCl. Using the cation/anion balance, a cross-check of the analytical proce-

dures was possible. The formula used to evaluate the analyses was

$$1 - \frac{(\text{Na}^+ + \text{Ca}^{++} + \text{K}^+)}{\text{Cl}^-} \times 100\% = \pm 10\%$$

where:

Cl^- = chloride concentration
 Na^+ = sodium concentration
 Ca^{++} = calcium concentration
 K^+ = potassium concentration

Since the brine contained other elements at lesser concentrations, the value of $\pm 10\%$ was used to allow for these lesser species. This process indicated an error if the balance was greater than 10% . If this were to happen the analyses would be repeated to determine the source of the error.

Scale Analysis Procedures

Two methods were used for analyzing the scale deposited in the GLEF over the three year operating period.

Total Digestion

During the first two years of operation the total digestion method of scale analysis was used. This method is described as follows:

The scale sample was pulverized with a mortar and pestle to obtain a homogenous sample for analysis. A portion of the crushed scale sample (usually one gram) was placed in a teflon bomb. Hydrochloric acid (HCl), nitric acid (HNO_3), hydrofluoric acid (HF), and boric acid (H_3BO_3) were added to the bomb containing the sample. The bomb was then heated in an oven until the scale was completely digested. 1/100, 1/500, and 1/1,000 dilutions with distilled water were prepared and the elemental composition was obtained using an Atomic Absorption Spectrophotometer.

Selective Leaching

This method of scale analysis was used during the last year of plant operation. The selective leaching method was time consuming and very tedious, but was the only method available for analyzing and identifying chemical compounds in the scale. The selective leaching method was used to differentiate the scale compounds based on their solubilities as follows:

The scale sample was pulverized with a mortar and pestle to obtain a homogenous sample for analysis. A one (1) gram portion was digested in the following manner:

Water Soluble - One (1) gram of scale was placed in 200 ml of distilled water and slowly boiled for a period of two (2) hours. The solution was then filtered through a Whatman No. 42 Filter Paper. The filtrate was analyzed on the Atomic Absorption Unit. The scale remaining on the filter paper was placed into a platinum crucible and ashed at 1652°F (900°C) for 1 1/2 hours. The crucible was cooled in a dessicator and weighed to obtain the amount of water insoluble material in the scale. The difference between the original weight and the water insoluble weight is the amount of water soluble material in the scale.

Acid Soluble - The ashed sample from above was placed in 200 ml of 15% hydrochloric acid (HCl). The solution was boiled for two (2) hours and filtered through a Whatman #42 Filter Paper. The filtrate was then analyzed on the Atomic Absorption Unit. The filter paper with the remaining scale was placed into a platinum crucible and ashed for 1 1/2 hours at 1652°F (900°C). The crucible was then cooled in a dessicator and weighed. The difference in weight between the water insoluble portion and the remaining scale was the acid soluble weight.

Acid Insoluble - The remaining scale from above was fused with sodium carbonate (Na_2CO_3). After the fusion was completed the fused sample was placed in a 200 ml of distilled water. The solution was boiled for two (2) hours and then cooled. The solution was filtered through a Whatman #42 Filter Paper. The filter paper was then washed with 15% hydrochloric acid (HCl). The two solutions were then analyzed on the Atomic Absorption Unit for the Acid Insoluble Components.

8.7.4 RESULTS

8.7.4.1 Molar Concentrations

Throughout the lifetime of the GLEF, the chemistry of the system had been monitored. Tables 8.7-2 through 8.7-5 list typical molar concentrations for the major anions and the cations in the brine and those species that caused the severest scaling problems. Chlorides, sodium, calcium, and potassium are the major ions in the geothermal fluid and iron and silicon caused the severest scaling problems.

Tables 8.7-2 and 8.7-3 list the typical molar concentrations of these ions for Magmamax No. 1 when the plant was operated in the four and two stage flash systems. Tables 8.7-4 and 8.7-5 list the typical molar concentrations of the Woolsey No. 1 well in the four and two stage flash systems. The values in parentheses are estimated values. These values were inserted on those days when the particular ion was not analyzed or on those days when the cation/anion balance exceeded 10% (See Section Brine Steam Analysis Procedures).

Table 8.7-2 Typical Molar Concentration for Four Stage Configuration (MagmaMax No. 1)

<u>DATE</u>	<u>MAGMAMAX NO. 1 PRODUCTION</u>	<u>1ST STAGE BRINE OUT</u>	<u>2ND STAGE BRINE OUT</u>	<u>3RD STAGE BRINE OUT</u>	<u>4TH STAGE BRINE OUT</u>
11 - 23 - 77					
Cl ⁻	(3.472)	(3.891)	(3.929)	(3.968)	(3.739)
Na ⁺	1.979	2.218	2.240	2.262	2.131
Ca ⁺⁺	(0.563)	(0.631)	(0.637)	(0.643)	(0.606)
K ⁺	0.215	0.238	0.243	0.246	0.210
Fe ⁺⁺	2.33x10 ⁻³	2.33x10 ⁻³	2.69x10 ⁻³	2.86x10 ⁻³	2.86x10 ⁻³
Si					
12 - 1 - 77					
Cl ⁻	(3.568)	3.853	3.977	(3.977)	(4.005)
Na ⁺	2.131	2.196	2.218	2.262	2.284
Ca ⁺⁺	0.487	0.574	0.549	(0.649)	0.686
K ⁺	0.207	0.238	0.228	0.251	0.246
Fe ⁺⁺	3.76x10 ⁻³	3.58x10 ⁻³	3.94x10 ⁻³	3.76x10 ⁻³	4.66x10 ⁻³
Si					
12 - 8 - 77					
Cl ⁻	(3.244)	(3.509)	3.701	(3.780)	(3.847)
Na ⁺	(1.849)	2.000	2.110	2.153	2.131
Ca ⁺⁺	0.536	0.474	0.599	0.661	0.624
K ⁺	0.217	0.233	0.243	0.246	0.243
Fe ⁺⁺	3.04x10 ⁻³	3.04x10 ⁻³	4.12x10 ⁻³	3.76x10 ⁻³	4.30x10 ⁻³
Si	9.44x10 ⁻³	6.05x10 ⁻³	9.97x10 ⁻³	8.90x10 ⁻³	1.09x10 ⁻²
12 - 12 - 77					
Cl ⁻	(3.667)	(3.816)	(3.816)	(3.853)	(3.892)
Na ⁺	2.088	2.170	2.175	2.197	2.218
Ca ⁺⁺	(0.594)	0.536	0.524	0.611	0.574
K ⁺	0.215	0.217	0.243	0.256	0.246
Fe ⁺⁺	3.22x10 ⁻³	3.75x10 ⁻³	4.30x10 ⁻³	5.19x10 ⁻³	4.83x10 ⁻³
Si	6.23x10 ⁻³	7.30x10 ⁻³	5.70x10 ⁻³	2.97x10 ⁻²	6.94x10 ⁻³
12 - 16 - 77					
Cl ⁻	(3.472)	(3.463)	(3.436)	(3.396)	(3.472)
Na ⁺	2.131	1.960	1.957	1.936	1.979
Ca ⁺⁺	0.511	0.479	0.526	0.479	0.526
K ⁺	0.205	0.228	0.240	0.217	0.240
FE ⁺⁺	4.48x10 ⁻³	4.20x10 ⁻³	4.48x10 ⁻³	4.30x10 ⁻³	4.48x10 ⁻³
Si	5.87x10 ⁻³	5.97x10 ⁻³	6.59x10 ⁻³	6.41x10 ⁻³	6.76x10 ⁻³

Water Soluble - One (1) gram of scale was placed in 200 ml of distilled water and slowly boiled for a period of two (2) hours. The solution was then filtered through a Whatman No. 42 Filter Paper. The filtrate was analyzed on the Atomic Absorption Unit. The scale remaining on the filter paper was placed into a platinum crucible and ashed at 1652°F (900°C) for 1 1/2 hours. The crucible was cooled in a dessicator and weighed to obtain the amount of water insoluble material in the scale. The difference between the original weight and the water insoluble weight is the amount of water soluble material in the scale.

Acid Soluble - The ashed sample from above was placed in 200 ml of 15% hydrochloric acid (HCl). The solution was boiled for two (2) hours and filtered through a Whatman #42 Filter Paper. The filtrate was then analyzed on the Atomic Absorption Unit. The filter paper with the remaining scale was placed into a platinum crucible and ashed for 1 1/2 hours at 1652°F (900°C). The crucible was then cooled in a dessicator and weighed. The difference in weight between the water insoluble portion and the remaining scale was the acid soluble weight.

Acid Insoluble - The remaining scale from above was fused with sodium carbonate (Na_2CO_3). After the fusion was completed the fused sample was placed in a 200 ml of distilled water. The solution was boiled for two (2) hours and then cooled. The solution was filtered through a Whatman #42 Filter Paper. The filter paper was then washed with 15% hydrochloric acid (HCl). The two solutions were then analyzed on the Atomic Absorption Unit for the Acid Insoluble Components.

8.7.4 RESULTS

8.7.4.1 Molar Concentrations

Throughout the lifetime of the GLEF, the chemistry of the system had been monitored. Tables 8.7-2 through 8.7-5 list typical molar concentrations for the major anions and the cations in the brine and those species that caused the severest scaling problems. Chlorides, sodium, calcium, and potassium are the major ions in the geothermal fluid and iron and silicon caused the severest scaling problems.

Tables 8.7-2 and 8.7-3 list the typical molar concentrations of these ions for Magmamax No. 1 when the plant was operated in the four and two stage flash systems. Tables 8.7-4 and 8.7-5 list the typical molar concentrations of the Woolsey No. 1 well in the four and two stage flash systems. The values in parentheses are estimated values. These values were inserted on those days when the particular ion was not analyzed or on those days when the cation/anion balance exceeded 10% (See Section Brine Steam Analysis Procedures).

Table 8.7-2 Typical Molar Concentration for Four Stage Configuration (Magmamax No. 1)

<u>DATE</u>	<u>MAGMAMAX NO. 1 PRODUCTION</u>	<u>1ST STAGE BRINE OUT</u>	<u>2ND STAGE BRINE OUT</u>	<u>3RD STAGE BRINE OUT</u>	<u>4TH STAGE BRINE OUT</u>
11-23-77					
Cl ⁻	(3.472)	(3.891)	(3.929)	(3.968)	(3.739)
Na ⁺	1.979	2.218	2.240	2.262	2.131
Ca ⁺⁺	(0.563)	(0.631)	(0.637)	(0.643)	(0.606)
K ⁺	0.215	0.238	0.243	0.246	0.210
Fe ⁺⁺	2.33x10 ⁻³	2.33x10 ⁻³	2.69x10 ⁻³	2.86x10 ⁻³	2.86x10 ⁻³
Si					
12-1-77					
Cl ⁻	(3.568)	3.853	3.977	(3.977)	(4.005)
Na ⁺	2.131	2.196	2.218	2.262	2.284
Ca ⁺⁺	0.487	0.574	0.549	(0.649)	0.686
K ⁺	0.207	0.238	0.228	0.251	0.246
Fe ⁺⁺	3.76x10 ⁻³	3.58x10 ⁻³	3.94x10 ⁻³	3.76x10 ⁻³	4.66x10 ⁻³
Si					
12-8-77					
Cl ⁻	(3.244)	(3.509)	3.701	(3.780)	(3.847)
Na ⁺	(1.849)	2.000	2.110	2.153	2.131
Ca ⁺⁺	0.536	0.474	0.599	0.661	0.624
K ⁺	0.217	0.233	0.243	0.246	0.243
Fe ⁺⁺	3.04x10 ⁻³	3.04x10 ⁻³	4.12x10 ⁻³	3.76x10 ⁻³	4.30x10 ⁻³
Si	9.44x10 ⁻³	6.05x10 ⁻³	9.97x10 ⁻³	8.90x10 ⁻³	1.09x10 ⁻²
12-12-77					
Cl ⁻	(3.667)	(3.816)	(3.816)	(3.853)	(3.892)
Na ⁺	2.088	2.170	2.175	2.197	2.218
Ca ⁺⁺	(0.594)	0.536	0.524	0.611	0.574
K ⁺	0.215	0.217	0.243	0.256	0.246
Fe ⁺⁺	3.22x10 ⁻³	3.75x10 ⁻³	4.30x10 ⁻³	5.19x10 ⁻³	4.83x10 ⁻³
Si	6.23x10 ⁻³	7.30x10 ⁻³	5.70x10 ⁻³	2.97x10 ⁻²	6.94x10 ⁻³
12-16-77					
Cl ⁻	(3.472)	(3.463)	(3.436)	(3.396)	(3.472)
Na ⁺	2.131	1.960	1.957	1.936	1.979
Ca ⁺⁺	0.511	0.479	0.526	0.479	0.526
K ⁺	0.205	0.228	0.240	0.217	0.240
FE ⁺⁺	4.48x10 ⁻³	4.20x10 ⁻³	4.48x10 ⁻³	4.30x10 ⁻³	4.48x10 ⁻³
Si	5.87x10 ⁻³	5.97x10 ⁻³	6.59x10 ⁻³	6.41x10 ⁻³	6.76x10 ⁻³

Table 8.7-3 Typical Molar Concentrations for Two Stage Flash Configuration (Maggamax No. 1)

DATE	MAGMAMAX NO. 1 PRODUCTION	1ST STAGE BRINE OUT	2ND STAGE BRINE OUT	REINJECTION
12-8-78				
Cl ⁻	3.131	3.557	3.974	3.974
Na ⁺	1.875	2.101	2.623	2.249
Ca ⁺⁺	0.534	0.594	0.654	0.594
K ⁺	0.195	0.243	0.269	0.243
Fe ⁺⁺	2.17x10 ⁻³	2.47x10 ⁻³	2.58x10 ⁻³	2.69x10 ⁻³
Si	8.22x10 ⁻³	9.79x10 ⁻³	5.48x10 ⁻³	1.06x10 ⁻²
12-11-78				
Cl ⁻	3.216	3.627	4.115	3.974
Na ⁺	1.875	1.949	(2.345)	2.401
Ca ⁺⁺	0.521	0.581	(0.666)	0.639
K ⁺	0.202	0.232	0.232	0.248
Fe ⁺⁺	2.31x10 ⁻³	2.72x10 ⁻³	3.22x10 ⁻³	3.01x10 ⁻³
Si	8.37x10 ⁻³	9.01x10 ⁻³	2.30x10 ⁻³	9.01x10 ⁻³
12-13-78				
Cl ⁻	3.272	3.557	4.115	3.974
Na ⁺	1.910	2.114	(2.344)	2.027
Ca ⁺⁺	0.494	0.551	0.581	0.581
K ⁺	0.183	0.201	0.219	0.219
Fe ⁺⁺	2.33x10 ⁻³	2.38x10 ⁻³	3.29x10 ⁻³	2.67x10 ⁻³
Si	8.65x10 ⁻³	9.40x10 ⁻³	2.71x10 ⁻³	9.15x10 ⁻³
12-15-78				
Cl ⁻	3.216	3.627	4.045	4.045
Na ⁺	1.853	1.988	2.418	2.310
Ca ⁺⁺	0.494	0.546	0.599	0.599
K ⁺	0.208	0.224	0.271	0.256
Fe ⁺⁺	2.60x10 ⁻³	2.81x10 ⁻³	2.86x10 ⁻³	2.65x10 ⁻³
Si	8.26x10 ⁻³	8.79x10 ⁻³	3.67x10 ⁻³	9.72x10 ⁻³
12-18-78				
Cl ⁻	3.216	3.591	4.045	3.974
Na ⁺	1.827	1.992	(2.305)	2.149
Ca ⁺⁺	0.489	0.516	0.555	0.569
K ⁺	0.205	0.239	0.274	0.288
Fe ⁺⁺	2.33x10 ⁻⁵	2.58x10 ⁻³	2.94x10 ⁻³	2.94x10 ⁻³
Si	8.12x10 ⁻⁵	8.83x10 ⁻³	9.86x10 ⁻³	9.86x10 ⁻³

Table 8.7-4 Typical Molar Concentrations for Four Stage Flash Configuration (Woolsey No. 1)

<u>DATE</u>	<u>WOOLSEY NO. 1 PRODUCTION</u>	<u>1ST STAGE BRINE OUT</u>	<u>2ND STAGE BRINE OUT</u>	<u>3RD STAGE BRINE OUT</u>	<u>4TH STAGE BRINE OUT</u>
5-9-77					
Cl ⁻	3.214	3.526	3.702	3.878	4.055
Na ⁺	1.744	1.870	2.049	2.097	2.175
Ca ⁺⁺	0.492	0.524	0.566	0.581	0.599
K ⁺	0.269	0.286	0.307	0.315	0.325
Fe ⁺⁺	4.94x10 ⁻³	3.67x10 ⁻³	4.30x10 ⁻³	4.48x10 ⁻³	4.48x10 ⁻³
Si	5.87x10 ⁻³	4.63x10 ⁻³	5.87x10 ⁻³	5.70x10 ⁻³	6.94x10 ⁻³
5-16-77					
Cl ⁻	3.244	3.596	3.737	3.808	3.914
Na ⁺	(1.849)	(2.050)	(2.132)	2.049	2.112
Ca ⁺⁺	0.479	0.533	0.552	0.569	0.586
K ⁺	0.232	0.259	0.269	0.279	0.297
Fe ⁺⁺	3.94x10 ⁻³	4.10x10 ⁻³	4.30x10 ⁻³	4.39x10 ⁻³	4.57x10 ⁻³
Si	6.05x10 ⁻³	5.30x10 ⁻³	6.23x10 ⁻³	6.41x10 ⁻³	6.94x10 ⁻³
7-3-77					
Cl ⁻	2.931	3.309	3.382	3.531	(3.703)
Na ⁺	(1.670)	(1.888)	1.801	1.903	1.977
Ca ⁺⁺	0.429	0.485	0.510	0.529	0.560
K ⁺	0.199	0.251	0.251	0.258	0.258
Fe ⁺⁺	2.15x10 ⁻³	2.51x10 ⁻³	2.69x10 ⁻³	2.51x10 ⁻³	3.04x10 ⁻³
Si	5.98x10 ⁻³	4.95x10 ⁻³	3.49x10 ⁻³	6.70x10 ⁻³	4.95x10 ⁻³

Table 8.7-5 Typical Molar Concentrations for Two Stage Flash Configuration (Woolsey No. 1)

<u>DATE</u>	<u>WOOLSEY NO.1 PRODUCTION</u>	<u>1ST STAGE BRINE OUT</u>	<u>2ND STAGE BRINE OUT</u>	<u>INJECTION</u>
1 - 22 - 79				
Cl ⁻	2.945	3.295	4.135	4.065
Na ⁺	(1.679)	1.931	2.205	2.236
Ca ⁺⁺	0.417	0.504	0.624	0.684
K ⁺	0.212	0.263	0.317	0.335
Fe ⁺⁺	2.72×10^{-3}	3.80×10^{-3}	4.42×10^{-3}	4.75×10^{-3}
Si	5.80×10^{-3}	7.73×10^{-3}	9.00×10^{-3}	8.79×10^{-3}
1 - 24 - 79				
Cl ⁻	2.874	3.785	4.135	4.206
Na ⁺	1.553	2.114	2.175	(2.398)
Ca ⁺⁺	0.449	0.549	0.649	0.647
K ⁺	0.202	0.269	0.338	0.297
Fe ⁺⁺	2.94×10^{-3}	3.72×10^{-3}	3.99×10^{-3}	3.85×10^{-3}
Si	5.95×10^{-3}	7.83×10^{-3}	8.05×10^{-3}	7.83×10^{-3}
1 - 29 - 77				
Cl ⁻	2.663	3.715	3.644	3.785
Na ⁺	(1.518)	(2.118)	2.118	(2.157)
Ca ⁺⁺	0.447	0.534	0.624	(0.614)
K ⁺	0.149	0.235	0.299	0.256
Fe ⁺⁺	2.99×10^{-3}	4.57×10^{-3}	5.39×10^{-3}	5.21×10^{-3}
Si	5.41×10^{-3}	8.33×10^{-3}	9.86×10^{-3}	9.29×10^{-3}
1 - 31 - 77				
Cl ⁻	3.108	3.580	3.986	3.986
Na ⁺	1.757	2.014	2.240	2.049
Ca ⁺⁺	0.564	0.654	0.744	0.654
K ⁺	0.238	0.256	0.309	0.292
Fe ⁺⁺	4.39×10^{-3}	4.67×10^{-3}	5.86×10^{-3}	5.52×10^{-3}
Si	7.55×10^{-3}	9.83×10^{-3}	1.12×10^{-2}	1.00×10^{-2}
2 - 21 - 79				
Cl ⁻	(3.526)	3.630		4.042
Na ⁺	2.140	1.927		(2.305)
Ca ⁺⁺	0.639	0.581		0.609
K ⁺	0.248	0.274		0.309
Fe ⁺⁺	4.42×10^{-3}	5.10×10^{-3}		5.64×10^{-3}
Si	7.51×10^{-3}	7.90×10^{-3}		8.08×10^{-3}

Average values and ranges of all the major ions found in the geothermal brine at the wellhead during operation of the GLEF are presented in Tables 8.7-6 and 8.7-7.

8.7.4.2 Steam and Noncondensable Gas Analysis

Steam from the geothermal fluids were analyzed for the elemental species in the same manner as the brines. The major species were chlorides, sodium, calcium, potassium and iron. When brine carryover occurred, the other elemental species listed in Tables 8.7-6 and 8.7-7 were detected. In the four stage flash configuration, only the chlorides, sodium, calcium, potassium, iron, ammonia and hydrogen sulfide were found in the steam. The average range of these species during operation of the GLEF is presented in Table 8.7-8 and 8.7-9.

When the plant was modified to the two stage flash configuration, the first stage steam remained virtually unchanged. However, high brine carryover occurred in the second stage. Many attempts to correct this problem were made, but none of them had any significant effect in reducing the carryover. The brine carryover was so severe on some days that up to 50 ppm silica was detected in the second stage steam. Table 8.7-8 and 8.7-9.

After proper sampling and analysis methods were established, little change in the noncondensable gas content was noted during the three year operation. The noncondensable gas content of the brine during the GLEF test was found to be 0.1% to 0.3% of the total well flow. Carbon-dioxide (CO_2) was the major constituent with minor amounts of methane (CH_4), nitrogen (N_2) and hydrogen sulfide (H_2S). Ammonia liberated during the steam separation stage tended to redissolve when the steam condensed. Except for a small increase in nitrogen, no change in noncondensable gas composition was found during the test period (Table 8.7-10).

8.7.4.3 Scale Formation and Composition

The background (Section 8.7.2) of this report indicated a change in the properties of the geothermal fluid when heat was extracted. The heat extracted was in the form of steam, which when liberated from the brine, resulted in supersaturation of many of the elements contained in the brine. When supersaturation occurred, the result was precipitation or scale disposition. In order to effectively deal with the scale deposition problem, the scale deposits were analyzed and identified (See Section Brine Steam Analysis Procedures). This information could be used to develop scale control methods to reduce the amount of scale deposition in the plant, thus, prolonging the plant operating time and increasing the reliability of future power plants.

Table 8.7-6 Elemental Range for Wellhead Brine at Magmamax No. 1

<u>ELEMENT</u>	<u>HIGH</u>	<u>LOW</u>	<u>AVERAGE</u>
Cl	126,000	107,000	112,800
Na	46,500	39,000	41,700
Ca	21,400	16,300	19,400
K	8,130	6,500	7,350
Mn	563	462	520
Sr	430	370	393
Zn	229	184	203
Si	243	159	213
Ba	154	111	130
Li	175	146	156
Fe	145	117	126
Mg	106	88.2	96.7
Pb	38.7	8.0	21.0

Note: All measurements are ppm

Table 8.7-7 Elemental Range for Wellhead Brine at Woolsey No. 1

<u>ELEMENT</u>	<u>HIGH</u>	<u>LOW</u>	<u>AVERAGE</u>
Cl	146,000	94,000	121,000
Na	54,600	29,600	42,700
Ca	28,300	16,700	22,900
K	14,100	5,830	10,200
Mn	903	498	718
Sr	472	292	382
Zn	313	172	256
Si	236	152	204
Ba	195	79	142
Li	197	122	162
Fe	320	152	236
Mg	116	67	87
Pb	68	24	49

Note: All measurements are ppm

Table 8.7-8 Average Ionic Concentrations (ppm) in the Steam for Magmamax No. 1 Fluid (Nov. 1978-Dec. 1978)

	Cl ⁻	Na ⁺	Ca ⁺⁺	K ⁺	Fe ⁺⁺	Si
Steam entering 1st stage scrubber	37.1	7.5	3.4	1.3	0.1	*ND
Steam leaving 1st stage scrubber	17.2	1.8	0.6	0.4	0.1	*ND
Steam entering 2nd stage scrubber	342	171	63.6	32.7	3.4	1.5
Steam entering 2nd stage scrubber	131	51.7	21.5	12.0	0.4	0.1
Combined Condensate	89.5	22.0	10.0	5.1	0.2	*ND

*ND implies none detected

Figure 8.7-9 Average Ionic Concentrations (ppm) in the Steam for the Woolsey No. 1 Fluid (Jan. 1979-Mar. 1979)

	Cl ⁻	Na ⁺	Ca ⁺⁺	K ⁺	Fe ⁺⁺	Si
Steam entering 1st stage scrubber	60.8	18.7	9.3	4.7	0.7	*ND
Steam leaving 1st stage scrubber	17.7	1.5	0.3	*ND	0.1	*ND
Steam entering 2nd stage scrubber	408	160	61.1	20.7	0.5	2.5
Steam leaving 2nd stage scrubber	447	136	67.3	25.7	0.9	*ND
Combined Condensate	225	78.2	30.0	14.0	0.7	*ND

*ND implies none detected

Table 8.7-10 Noncondensable Gases From Magmamax No. 1 Wellhead

	DECEMBER 1976 % OF TOTAL GAS	AUGUST 1979 % OF TOTAL GAS
CO₂	98.14	98.92
CH₄	0.68	0.51
N₂	0.02	0.57
O₂	*ND	*ND
H₂	*ND	*ND

***ND implies none detected**

The major scaling species in the four stage flash system were iron and lead sulfides (FeS and PbS) and silica (SiO₂) (Tables 8.7-11 through 8.7-14). From Tables 8.7-11 through 8.7-14 the approximate trend of these scalants was:

	Iron and lead Sulfide	Silica
first stage separator	80%	20%
second stage separator	60%	40%
third stage separator	40%	60%
fourth stage separator	20%	80%

The assumed mechanism for this trend is:

Iron and lead react instantaneously with hydrogen sulfide (H₂S) to form iron and lead sulfide (FeS and PbS) as follows:

Since this reaction occurs instantly and the solubilities of these compounds in water are extremely low, these species were deposited primarily in the production line and the first stage separator.

Silica (SiO₂) does not form as molecular SiO₂, but as a long chain polymer, so the precipitation of silica takes longer. Meanwhile, the geothermal fluid was flashed in successive stages becoming more and more supersaturated, allowing the polymerization of silica to occur faster. Thus, the scale in the lower pressure stages contain higher concentrations of silica than the scale in the first stage.

The scales in the steam and condensate vessels and lines were made up of calcium carbonate (CaCO₃) and iron sulfide. The iron sulfide scale was formed in the same manner as described above. The calcium carbonate scale most likely formed as follows:

The geothermal fluid contained noncondensable gases. The major constituent of this gas was carbon dioxide (CO₂). The carbon dioxide reacted with the steam to form carbonic acid (H₂CO₃) as illustrated,

The carbonic acid in turn reacted with the calcium carried over in the steam to form calcium carbonate by the following mechanism,

**Table 8.7-11 Typical Scale Analysis from the Four Stage Flash System
Using the Total Digestion Procedure**

First Stage Scale

Date	5/23/77	5/23/77	5/23/77
Location	Below Fluid Level	Floor Debris	Venturi On Outlet
Thickness	0.3-0.5 cm	0.1-2 cm	0.2-0.5 cm
General Appearance Color	redish-brown black porous	black formed by particle conglomeration	black very hard
	Wt%	Wt%	Wt%
Fe	25.25	24.20	22.55
Cu	0.18	0.30	0.21
Zn	0.07	0.15	0.09
Mn	1.53	1.07	1.78
Pb	0.91	8.25	5.60
Ca	1.50	0.85	1.10
Al	0.89	1.64	1.15
Si	16.65	16.65	16.10
Ba	0.13	0.08	1.60
Mg	0.11	0.12	0.08
Na	2.50	0.46	0.78
CO ₃	*ND	*ND	*ND
S as S ⁼	0.25	1.55	0.97

*ND implies none detected

Table 8.7-12 Typical Scale Analysis from the Four Stage Flash System Using Total Digestion Procedure

Second Stage Scale			
Date	5/23/77	5/23/77	5/23/77
Location	Well below Fluid Level	Floor Debris	Venturi On Outlet
Thickness	0.8-1.8 cm	to 2.5 cm	0.7 mm
General Appearance Color	black multi-layered	porous grains built on central portion black	hard black
	Wt%	Wt%	Wt%
Fe	22.55	23.85	21.25
Cu	0.13	0.10	0.50
Zn	0.14	0.22	0.10
Mn	1.10	1.23	2.37
Pb	0.08	0.52	0.05
Ca	2.10	1.15	1.15
Al	0.85	0.75	1.15
Si	17.85	19.20	19.65
Ba	1.04	0.81	0.42
Mg	0.05	0.65	0.43
Na	3.25	1.40	2.05
CO ₃	*ND	*ND	*ND
S	0.45	0.51	0.23

*ND implies none detected

Table 8.7-13 Typical Scale Analysis from the Four Stage Flash System Using the Total Digestion Procedure

Third Stage Scale

Date	5/23/77	5/23/77	5/23/77
Location	Well below Fluid Level	Floor Debris	Venturi On Outlet
Thickness	0.5-1 cm	to 2 cm	1.5 cm
General Appearance Color	porous yet hard black-olive	porous black	hard multi-layered black, green
	Wt%	Wt%	Wt%
Fe	16.65	21.60	3.10
Cu	0.16	0.74	0.41
Zn	0.26	0.16	0.06
Mn	1.07	1.45	0.36
Pb	0.51	0.93	0.26
Ca	1.45	0.95	1.55
Al	0.61	0.87	0.24
Si	18.30	18.70	34.15
Ba	1.20	1.10	0.18
Mg	0.31	0.37	0.12
Na	2.95	1.00	2.60
CO ₃	*ND	*ND	*ND
S	1.26	1.55	0.18

*ND Implies none detected

**Table 8.7-14 Typical Scale Analysis from the Four Stage Flash System
Using the Total Digestion Procedure**

Fourth Stage and Injection Pump Scale

Date	5/27/77	5/27/77	5/27/77
Location	Flash Vessel Wall	P-2 Suction Inlet to First Impeller	P-2 Casing
Thickness	0.5 cm	0.6-1 cm	
General Appearance Color	light olive soft	hard black ochre film	soft porous gray
	Wt%	Wt%	Wt%
Fe	2.95	1.70	2.10
Cu	0.21	19.80	0.24
Zn	0.09	0.09	0.10
Mn	0.24	0.25	0.30
Pb	0.22	0.63	0.18
Ca	0.85	0.55	0.40
Al	0.13	0.28	0.41
Si	31.80	28.70	38.75
Ba	4.10	0.60	1.25
Mg	0.26	0.27	0.47
Na	0.55	0.26	0.20
CO ₃	*ND	*ND	*ND
S	1.20	0.40	0.77

*ND implies none detected

Since the formation of calcium carbonate was pH dependent (formation occurs at a pH of 8 and above) and the brine pH was 5 to 6, no calcium carbonate was found in the brine scales except when high pH condensate was added to the brine. The pH of the steam condensate was 8 and above, so local formation of calcium carbonate would occur.

Thus, when condensed geothermal steam was mixed with the brine, large deposits of calcium carbonate and iron sulfide were found at the point of contact, due to the local increase in pH. As a result, the condensate was used as cooling water make-up rather than being reinjected.

In March, 1978, the plant was modified to a two stage flash system. The scale composition in this new system was approximately the same as that of the four stage flash system. The first stage separator scale contained about 15% silica and 85% iron and lead sulfides. The second stage separator scales contained about 85% silica and 15% iron and lead sulfides. It was hoped that the high silica scales would form downstream of the second stage. This did not happen because of the rapid decrease of the temperature and pressure in the second stage separators (360°F (182°C) and 130 psia to 235°F (113°C) and 210 psia). As a result, rapid formation and deposition of silica occurred in the second stage separator rather than in the atmospheric flash vessel. Using selective leaching and careful analysis, an estimate of the scale compounds was developed. These results are presented in Tables 8.7-15 through 8.7-19. In making these calculations it was assumed that silicon detected in the acid soluble portion of the scale analysis was either sodium silicate (Na_2SiO_3) or potassium silicate (K_2SiO_3). If calcium and silicon was detected in the acid wash of the acid insoluble portion then it was assumed to be there as calcium silicate (CaSiO_3).

8.7.5 CONCLUSIONS

Between November 1978 and March 1979, a statistical analysis was conducted on the elemental concentrations of the geothermal fluid for Magmamax No. 1 and Woolsey No. 1 wells. Comparison of these results with the analytical results over the three year GLEF operating period indicated little change in the wellhead brine composition. Based on this, the geothermal fluid is assumed to be homogenous in the reservoir. The solids content (TDS) of the geothermal fluid was 22-25% by weight with the major species being, in descending order, sodium, calcium and potassium chlorides. In order to draw representative samples of the fluids, a stainless steel/inconel sampling system and retractable probes must be used.

During the heat extraction process, the geothermal fluid temperature dropped from the reservoir temperature of 500°F (260°C) to the injection temperature of 210°F (100°C).

Table 8.7-15 Typical Scale Analysis from Two Stage Flash System
Using the Selective Leaching Method.

1-B SEPERATOR BRINE (OUT)
DATE: 1-8-79

<u>Wt. %</u>		<u>% Fraction</u>	<u>% Total Scale</u>
Al	- 0.64	Water Soluble - 18.0	CaCl ₂ - 2.27
Ba	- 0.00	CaCl ₂ - 12.6	CrCl ₂ - 0.04
Ca	- 0.57	CrCl ₂ - 0.2	FeCl ₂ - 0.20
Cr	- 0.01	FeCl ₂ - 1.1	LiCl - 0.14
Co	- 0.02	LiCl - 0.8	MgCl ₂ - 0.52
Cu	- 0.74	MgCl ₂ - 2.9	MnCl ₂ - 1.60
Fe	- 13.82	MnCl ₂ - 8.9	KCl - 1.19
Pb	- 21.62	KCl - 6.6	NaCl - 12.01
Li	- 0.01	NaCl - 66.7	SrCl ₂ - 0.04
Mg	- 0.34	SrCl ₂ - 0.2	Al ₂ S ₃ - 1.06
Mn	- 1.04		Ca(OH) ₂ - 0.20
Ni	- 0.02	Acid Soluble - 33.0	CuS - 1.12
K	- 0.26	Al ₂ S ₃ - 3.2	Fe ₂ O ₃ - 11.62
Si	- 11.57	Ca(OH) ₂ - 0.6	PbS - 17.32
Ag	- 0.30	CuS - 3.4	Mg (OH) ₂ - 0.33
Na	- 7.73	Fe ₂ O ₃ - 35.2	Mn (OH) ₂ - 0.73
Sr	- 0.01	PbS - 52.5	K ₂ SiO ₃ - 0.03
Sn	- 0.00	Mg (OH) ₂ - 1.0	Ag ₂ O - 0.23
Zn	- 0.13	Mn (OH) ₂ - 2.2	Na ₂ SiO ₃ - 0.10
		K ₂ SiO ₃ - 0.1	ZnS - 0.26
		Ag ₂ O - 0.7	Al ₂ O ₃ - 0.64
		Na ₂ SiO ₃ - 0.3	CaSiO ₃ - 0.49
		ZnS - 0.8	CoS - 0.05
			CuO - 0.20
			Fe ₃ O ₄ - 10.24
		Acid Insoluble - 49.0	PbO - 14.40
		Al ₂ O ₃ - 1.3	MgSiO ₃ - 0.49
		CaSiO ₃ - 1.0	MnSiO ₃ - 0.83
		CoS - 0.1	NiO - 0.05
		CuO - 0.4	SiO ₂ - 21.45
		Fe ₃ O ₄ - 20.9	Ag ₂ S - 0.15
		PbO - 29.4	
		MgSiO ₃ - 1.0	
		MnSiO ₃ - 1.7	
		NiO - 0.1	
		SiO ₂ - 43.8	
		Ag ₂ S - 0.3	

**Table 8.7-16 Typical Scale Analysis from Two Stage Flash System
Using the Selective Leaching Method**

2 - B SEPERATOR (BOTTOM)

DATE: 1-12-79

<u>Wt. %</u>	<u>% Fraction</u>	<u>% Total Scale</u>
Al - 0.04	Water Soluble - 23.4	CaCl ₂ - 6.76
Ba - 0.00	CaCl ₂ - 28.9	LiCl - 0.19
Ca - 1.25	LiCl - 0.8	MgCl ₂ - 0.07
Cr - 0.00	MgCl ₂ - 0.3	MnCl ₂ - 0.33
Co - 0.00	MnCl ₂ - 1.4	KCl - 1.31
Cu - 0.10	KCl - 5.6	NaCl - 14.59
Fe - 0.90	NaCl - 62.3	SrCl ₂ - 0.14
Pb - 0.84	SrCl ₂ - 0.6	ZnCl ₂ - 0.02
Li - 0.01	ZnCl ₂ - 0.1	Ca(OH) ₂ - 0.08
Mg - 0.04		CuS - 0.25
Mn - 0.13		FeS - 1.87
Ni - 0.00		PbS - 1.69
K - 0.33	Acid Soluble - 4.6	Mg(OH) ₂ - 0.04
Si - 32.73	Ca(OH) ₂ - 1.8	Mn(OH) ₂ - 0.17
Ag - 0.02	CuS - 5.5	Na ₂ SiO ₃ - 0.21
Na - 2.71	FeS - 40.4	ZnS - 0.29
Sr - 0.04	PbS - 36.7	Al ₂ O ₃ - 0.07
Sn - 0.15	Mg(OH) ₂ - 0.9	CaSiO ₃ - 0.22
Zn - 0.10	Mn(OH) ₂ - 3.7	CuO - 0.07
	Na ₂ SiO ₃ - 4.6	Fe ₃ O ₄ - 0.79
	ZnS - 6.4	PbO - 0.50
		MgSiO ₃ - 0.14
		MnSiO ₃ - 0.07
		SiO ₂ - 69.85
	Acid Insoluble - 72.0	Ag ₂ S - 0.07
	Al ₂ O ₃ - 0.1	SnSO ₄ - 0.14
	CaSiO ₃ - 0.3	ZnO - 0.07
	CuO - 0.1	
	Fe ₃ O ₄ - 1.1	
	PbO - 0.7	
	MgSiO ₃ - 0.2	
	MnSiO ₃ - 0.1	
	SiO ₂ - 97.0	
	Ag ₂ S - 0.1	
	SnSO ₄ - 0.2	
	ZnO - 0.1	

Table 8.7-17 Typical Scale analysis From Two Stage Flash System Using the Selective Leaching Method

V - 15 (ATMOSPHERIC FLASH VESSEL) OUTLET

DATE: 1-8-79

Wt. %	% Fraction	% Total Scale
Al - 0.06	Water Soluble - 41.6	CaCl ₂ - 14.77
Ba - 0.02	CaCl ₂ - 35.5	CuCl ₂ - 0.04
Ca - 3.78	CuCl ₂ - 0.1	LiCl - 0.25
Cr - 0.00	LiCl - 0.6	MgCl ₂ - 0.08
Co - 0.00	MgCl ₂ - 0.2	MnCl ₂ - 0.29
Cu - 0.19	MnCl ₂ - 0.7	KCl - 2.70
Fe - 0.33	KCl - 6.5	NaCl - 23.20
Pb - 0.14	NaCl - 55.8	SrCl ₂ - 0.17
Li - 0.03	SrCl ₂ - 0.4	ZnCl ₂ - 0.08
Mg - 0.03	ZnCl ₂ - 0.2	Ca(OH) ₂ - 0.25
Mn - 0.12		CuO - 0.45
Ni - 0.02		Fe ₂ O ₃ - 0.62
K - 0.99		PbO - 0.25
Si - 30.70	Acid Soluble - 2.3	Mn(OH) ₂ - 0.08
Ag - 0.01	Ca(OH) ₂ - 10.7	Na ₂ SiO ₃ - 0.58
Na - 6.29	CuO - 19.6	ZnO - 0.08
Sr - 0.06	Fe ₂ O ₃ - 26.8	Al ₂ O ₃ - 0.11
Sn - 0.00	PbO - 10.7	BaSO ₄ - 0.06
Zn - 0.06	Mn(OH) ₂ - 3.6	CaSiO ₃ - 0.22
	Na ₂ SiO ₃ - 25.0	CuO - 0.06
	ZnO - 3.6	Fe ₃ O ₄ - 0.28
		PbO - 0.06
		MgSiO ₃ - 0.06
		MnSiO ₃ - 0.06
		SiO ₂ - 55.20
	Acid Insoluble - 56.1	
	Al ₂ O ₃ - 0.2	
	BaSO ₂ - 0.1	
	CaSiO ₃ - 0.4	
	CuO - 0.1	
	Fe ₃ O ₄ - 0.5	
	PbO - 0.1	
	MgSiO ₃ - 0.1	
	MnSiO ₃ - 0.1	
	SiO ₂ - 98.4	

**Table 8.7-18 Typical Scale Analysis from Two Stage Flash System
Using the Selective Leaching Method**

**P - 2 DISCHARGE
DATE: 1-2-79**

<u>Wt. %</u>	<u>% Fraction</u>	<u>% Total Scale</u>
Al - 0.06	Water Soluble - 34.6	BaCl ₂ - 0.03
Ba - 0.02	BaCl ₂ - 0.1	CaCl ₂ - 9.45
Ca - 2.26	CaCl ₂ - 27.3	CuCl ₂ - 0.03
Cr - 0.00	CuCl ₂ - 0.1	PbCl ₂ - 0.35
Co - 0.01	PbCl ₂ - 1.0	LiCl - 0.17
Cu - 0.26	LiCl - 0.5	MgCl ₂ - 0.07
Fe - 0.41	MgCl ₂ - 0.2	MnCl ₂ - 0.28
Pb - 0.58	MnCl ₂ - 0.8	KCl - 2.11
Li - 0.02	KCl - 6.1	NaCl - 21.90
Mg - 0.03	NaCl - 63.3	SrCl ₂ - 0.14
Mn - 0.10	SrCl ₂ - 0.4	ZnCl ₂ - 0.07
Ni - 0.02	ZnCl ₂ - 0.2	Ca(OH) ₂ - 0.06
K - 0.73		CuO - 0.38
Si - 34.82		Fe ₂ O ₃ - 1.70
Ag - 0.01		PbO - 0.44
Na - 5.55	Acid Soluble - 3.0	Mn(OH) ₂ - 0.03
Sr - 0.04	Ca(OH) ₂ - 2.0	NiO - 0.03
Sn - 0.00	CuO - 12.6	K ₂ SiO ₃ - 0.06
Zn - 0.05	Fe ₂ O ₃ - 56.5	Na ₂ SiO ₃ - 0.26
	PbO - 14.6	AgCl - 0.02
	Mn(OH) ₂ - 1.0	ZnO - 0.03
	NiO - 1.0	Al ₂ O ₃ - 0.12
	K ₂ SiO ₃ - 2.0	CaSiO ₃ - 0.19
	Na ₂ SiO ₃ - 8.8	CuO - 0.06
	AgCl - 0.5	Fe ₃ O ₄ - 0.25
	ZnO - 1.0	PbO - 0.12
		MgSiO ₃ - 0.06
		SiO ₂ - 61.59
	Acid Insoluble - 62.4	
	Al ₂ O ₃ - 0.2	
	CaSiO ₃ - 0.3	
	CuO - 0.1	
	Fe ₃ O ₄ - 0.4	
	PbO - 0.2	
	MgSiO ₃ - 0.1	
	SiO ₂ - 98.7	

**Table 8.7-19 Typical Scale Analysis from Two Stage Flash System
Using the Selective Leaching Method**

(1)			(2)		
<u>Wt. %</u>	<u>% Scale Fraction</u>	<u>% Total Scale</u>	<u>Wt. %</u>	<u>% Scale Fraction</u>	<u>% Total Scale</u>
Water Soluble - 34.4			Water Soluble - 3.4		
Ca - 2.26	NH ₄ Cl - 4.6	NH ₄ Cl - 1.58	Ca - 0.66	NH ₄ Cl - 4.0	NH ₄ Cl - 0.14
Mg - 0.07	CaCl ₂ - 25.5	CaCl ₂ - 8.77	Mg - 0.03	CaCl ₂ - 0.7	CaCl ₂ - 0.02
Na - 5.09	LiCl - 1.8	LiCl - 0.62	Na - 2.36	MgCl ₂ - 0.5	MgCl ₂ - 0.02
K - 0.23	MgCl ₂ - 0.4	MgCl ₂ - 0.14	Fe - 10.51	MnCl ₂ - 4.0	MnCl ₂ - 0.14
K - 0.23	MnCl ₂ - 1.6	MnCl ₂ - 0.55	Pb - 1.97	KCl - 6.3	KCl - 0.21
Li - 0.25	KCl - 0.3	KCl - 0.10	K - 0.17	NaCl - 83.8	NaCl - 2.85
Zn - 0.24	NaCl - 65.6	NaCl - 22.57	Zn - 0.18	ZnCl ₂ - 0.7	ZnCl ₂ - 0.02
Mn - 0.26	ZnCl ₂ - 0.2	ZnCl ₂ - 0.07	Mn - 0.49		CaO - 0.01
Ba - 0.94		BaO - 0.23	Si - 36.95		Fe ₂ O ₂ - 0.95
NH ₃ - 0.25	Acid Soluble - 0.7	CaO - 0.04	NH ₃ - 0.07	Acid Soluble - 1.2	PbO - 0.38
Si - 47.87	BaO - 32.3	Fe ₂ O ₃ - 0.23		CaO - 1.0	MgO - 0.01
	CaO - 6.4	Na ₂ SiO ₃ - 0.17		Fe ₂ O ₃ - 79.0	MnO - 0.03
	Fe ₂ O ₃ - 32.3	ZnO - 0.09		PbO - 9.7	Na ₂ SiO ₃ - 0.07
	Na ₂ SiO ₃ - 24.2	CaSiO ₃ - 0.39		MgO - 0.6	ZnO - 0.11
	ZnO - 4.8	Fe ₃ O ₄ - 0.65		MnO - 2.5	CaSiO ₃ - 0.29
		MgSiO ₃ - 0.06		Na ₂ SiO ₃ - 6.1	Fe ₃ O ₄ - 3.91
	Acid Insoluble - 64.9	MnSiO ₃ - 0.06		ZnO - 1.1	MnSiO ₃ - 0.19
	CaSiO ₃ - 0.6	SiO ₂ - 63.68			SiO ₂ - 90.15
	Fe ₃ O ₄ - 1.0			Acid Insoluble - 95.4	
	MgSiO ₂ - 0.1			CaSiO ₃ - 0.3	
	MnSiO ₃ - 0.1			Fe ₃ O ₄ - 4.1	
	SiO ₂ - 98.1			PbO - 0.8	
	ZnO - 0.1			MnSiO ₃ - 0.2	
				SiO ₂ - 94.5	
				ZnO - 0.1	

(1) 2B Separator (V-11) Bottom (dried)

(2) 2B Separator (V-11) Top (dried)

Pressure above the liquid level also dropped causing steam evolution and an increase in the mineral concentration. Under these conditions, the solubility of the major chloride species of the geothermal fluid was apparently never exceeded. However, the solubility of three minor ionic species was exceeded, namely, iron and lead sulfides and silica. The highly insoluble iron and lead sulfides precipitated almost immediately, which accounted for their presence in the production lines and the first stage flash vessels. Silica, on the other hand, appeared to go through a polymerization step, so its deposition was much slower. As a result, most of the silica was found in the low pressure stages and the injection line.

The pH of the geothermal fluid ranged between 4.8 and 5.5, so carbonate scales were not observed. The only exception occurred when the higher pH condensed steam (8.5-9.0) was recombined with the geothermal brine to evaluate 100% reinjection. This carbonate scale was formed in the recombination vessel, primarily, at the point of contact between the brine and condensed steam. Calcium carbonate was the major specie with minor concentrations of barium and strontium carbonates.

Reliable data from instrumentation is essential for any geothermal facility. This data would enable calculations for heat transfer and mass balance to be made. Detectors in contact with the geothermal fluids should be made of a scale resistant material if available or a rigid maintenance program should be implemented and adhered to in order to insure reliable data.

Improved brine/steam separation will be required to provide steam of reasonable purity (Table 8.7-9). Once the steam has been separated from the brine, it cannot be recombined without allowing for the formation of carbonate scale.

Better scale control methods must be developed in order to increase the operating time of the facility. This scale control might be accomplished either through mechanical means or by use of chemical additives.

8.8 H₂S ABATEMENT

Principal Investigators: R. Quong, K. G. Knauss, N. D. Stout, L. B. Owens and C. H. Otto, Jr. (Lawrence Livermore Laboratories)

8.8.1 OBJECTIVES

The objective of this test was to evaluate the technical feasibility and cost benefits of scrubbing H₂S gas contained in the GLEF non-condensable vent gases with brine effluent. The effect on the clarifier/filter system performance by removal of H₂S with brine effluent was to be considered. Technical advantages and disadvantages, and costs of this technique was to be compared with the Stretford process.

8.8.2 BACKGROUND

Measurable amounts of H₂S are contained in the noncondensable gases when the brines are flashed. It is clear that abatement of H₂S will be necessary to satisfy air quality standards in major future power plant installations. A feasibility and risk study of geothermal power plants at the Salton Sea KGRA (See Ref. 8.8-1) concluded that a 2-stage flash system is the most cost effective process for producing electrical power at the 50 MW level. The studies for plants at Salton Sea KGRA included the relatively high costs for H₂S abatement by the Stretford process. However, the above mentioned alternate method appears technically promising and economically attractive.

Niland brine effluents are uniquely suitable for use as a scrubbing liquid for H₂S. The brines contain relatively high concentrations of metal ions such as lead, zinc, and iron which as sulfides are exceedingly insoluble. Evolution of CO₂ during the flash process results in elevation of the brine pH which also favors heavy metal sulfide precipitation. Preliminary bench tests with Niland effluent brine and noncondensable gases containing H₂S in the vent gas with heavy metal ions in the effluents brine (See Ref. 8.8-5). This alternate method of H₂S abatement appears to be efficient, very simple to operate, and has the potential of providing significant cost savings.

8.8.3 TEST DESCRIPTION AND PROCEDURE

8.8.3.1 Test Materials and Equipment

Bench scale tests were to be carried out at the GLEF utilizing vent gas and brine effluent side streams. Flow rates were to be about 0.1-1.0 liter/min brine flow and up to 6 liters/min noncondensable gas flow, too low to affect GLEF operation.

The H₂S-brine contactor was to consist of 2 inch diameter glass pipe without internal packing or baffles (Figure 8.8-1). Liquid height was to be maintained at approximately 16 inches. Gas flow was in the upward direction in the contactor; liquid flow is downward. Dispersion of gas into fine bubbles was produced by a fritted glass sparger. Most of the plumbing consisted of steel and plastic tubing.

Temperature, pressure, pH, and flow measuring instruments were required. Use of thermocouples for temperature, standard probes and meters for pH, and rotometers for flow was anticipated. Pressure measurement was not critical, but if necessary, any suitable gauge was to be used.

8.8.3.2 Test Prerequisites

These tests were to be performed in conjunction with operation of the GLEF.

8.8.3.3 Test Conditions

A relatively constant flow ($\pm 20\%$) of vent gas through the stack and a continuous source of untreated (upstream of the clarifier/filter system) brine effluent are required for these tests. These conditions were expected to be easily provided by normal GLEF operation. The actual location of the test apparatus was near the base of the GLEF vent gas stack.

8.8.3.4 Required Data and Observations

Data was to be obtained in the gas and brine effluent streams entering and exiting and the test scrubber. Measurements include: concentration on H₂S in the gas stream, concentration of silica, metal ions (Pb, Zn, Fe and others), and particulates in the brine, pH, flow rates, temperature, contact time, and other parameters affecting the process. Samples were to be collected and selectively analyzed by atomic absorption spectrometry. The properties of the contacted brine are particularly important in assessing the effect of the H₂S scrubbing process on clarifier/filter effluent.

Chemical and mineralogical composition of the precipitated solids in the brine were also to be determined as needed. Samples were to be analyzed by x-ray fluorescence and x-ray diffraction. These data and observations were also to be required in the event of a test where vent gas is injected into the 30 gpm pilot clarifier.

Figure 8.8-1 Experiments Conducted with Small, Single Stage, Countercurrent Flow Contactor

8.8.3.5 Test Duration

Each test at a given condition was anticipated to take less than one hour, provided that steady flow conditions have been maintained at the GLEF. Repeat runs at identical conditions were necessary to assess reproducibility of the data. The number of test conditions was to be considerable in order to establish the efficiency of the process over a range of gas/brine ratios, and the effect of effluent temperature. It was anticipated that data acquisition and reduction would be completed in three to four months.

8.8.4 RESULTS

8.8.4.1 Expected Results

The technical feasibility and cost benefits of scrubbing H_2S in the vent gas stream using brine effluent was to be established and compared to the Stretford process. The technical and cost impact on the effluent clarification process was also to be evaluated.

8.8.4.2 Data and Observations

The initial measurements were conducted with cooled second stage effluent as the scrubbing liquid. Data and results are given in Table 8.8-1. Noncondensable gas for these measurements was drawn from a tap on the side of the vent stack. Gas temperature was nominally $118^\circ F$ ($48^\circ C$) at the point of entry to the scrubber, dropping instantaneously to the temperature of the scrubbing medium which in this set of experiments ranged from $77-86^\circ F$ ($25-30^\circ C$). Scrubbing efficiencies, also listed in Table 8.8-1, are based on the measured concentration of H_2S in the noncondensable gas stream entering and existing the scrubber. Runs 1, 5, and 6 were conducted with a gas distribution device which did not produce bubble sizes as fine as the fritted glass sparger used exclusively in the other runs. This apparently was the primary reason for the lower efficiencies.

Table 8.8-2 is a summary of results of tests in which brine effluent from the 2-stage at the GLEF was maintained at a temperature of $176 \pm 91^\circ F$ ($80 \pm 5^\circ C$). Figures 8.8-2 and 8.8-3 are plots of H_2S removal efficiency versus noncondensable gas to brine ratios for cold and hot brine, respectively. High efficiencies, 95%, were obtained across a broad range of gas/brine ratios with cooled brine as the scrubbing liquid. At gas/liquid flow ratios corresponding to 0.3 wt. % noncondensable gas in the brine, the maximum operational characteristics at the GLEF (See Ref. 8.8-4), 98% removal of H_2S was obtained.

With brine maintained at $176 \pm 41^\circ F$ ($80 \pm 5^\circ C$), 96% removal of H_2S at 0.3 wt% gas/liquid flow ratios was

Table 8.8-1 H₂S Scrubbing Data and Efficiencies Using Low Temperature (25-30°C) Brine Effluent (Woolsey No.1 Fluid from the GLEF).

Test #	Flowrate liters/min.		Gas/Brine Ratio, wt%	H ₂ S Concentration in noncondensibles ppm (vol)		Efficiency of H ₂ S Removal, %
	Noncondensable gas	Brine		In	Out	
1	.255	.607	.06	1150	216	81.2
2	.200	.265	.11	800	<1	98.3
3	.315	.265	.12	800	3.3	99.5
4	.290	.320	.13	800	2.9	99.6
5	.280	.242	.17	1250	350.	72.0
6	.280	.242	.17	1140	375.	67.1
7	.315	.265	.17	800	2.	99.7
8	.315	.265	.17	800	3.4	99.6
9	.315	.260	.18	800	4.4	99.5
10	.425	.265	.24	800	7.8	99.0
11	.460	.235	.29	800	10.0	98.8
12	.530	.265	.29	800	9.8	98.8
13	.530	.260	.30	800	9.1	98.9
14	.510	.235	.32	800	9.4	98.8
15	.425	.165 ^a	.38	800	16.5	97.9
16	1.030	.365 ^b	.41	900	13	98.6
17	.770	.265	.43	800	13	98.4
18	1.280	.380	.47	800	14	98.3
19	1.240	.280	.65	800	16.5	97.9
20	1.215	.265	.67	950	16	98.3
21	1.215	.265	.67	800	12.5	98.4
22	1.230	.265	.68	800	15.0	98.1
23	1.215	.180	.99	800	41	94.8
24	1.230	.180	1.00	800	35	95.6
25	1.230	.165	1.10	800	42	94.8
26	1.280	.165	1.14	800	31	96.1

a. pH brine: in 6.0 ; out 4.2

b. pH brine: in 5.6 ; out 4.4

Table 8.8-2 H₂S Scrubbing Data and Efficiencies Using Hot (80 ± 5°C) Brine Effluent (MagmaMax No. 1 Fluid from the GLEF)

TEST NO.	BRINE EFFLUENT			NONCONDENSIBLE GAS			GAS/BRINE RATIO	EFFICIENCY OF
	Flowrate Liters/Min	pH		Flowrate	H ₂ S Conc. ppm (vol)		Wt %	H ₂ S REMOVAL %
		In	Out		In	Out		
27	.640	-	-	.600	1450	37	.14	97.4
28	.640	-	-	.640	1450	54	.15	96.3
29	.420	-	4.6	.420	2100	14	.15	99.3
30	.640	5.50	4.40	.640	1500	60	.15	96.0
31	.640	-	4.40	.640	1100	35	.15	96.8
32	.320	-	-	.600	1450	46	.28	96.8
33	.240	-	4.30	.700	1100	50	.44	95.4
34	.320	-	-	.960	1400	78	.45	94.4
35	.240	-	4.40	.720	2350	210	.45	91.1
36	.140	5.10	4.48	.490	1450	60	.52	95.9
37	.240	-	4.15	.860	1475	170	.54	88.5
38	.240	-	4.18	.860	1500	220	.54	85.3
39	.320	-	-	1.490	1400	650	.70	53.6
40	.140	5.15	4.30	.700	1500	300	.75	80.0
41	.140	5.40	4.30	.700	2500	700	.75	72.0
42	.140	5.35	4.20	.860	2400	1350	.92	43.8
43	.240	-	4.05	1.490	1200	725	.93	39.6
44	.140	5.05	4.30	.900	1600	825	.96	48.4

Figure 8.8-2 Results with Cooled Effluent (25°C) Indicate > 98% Scrubbing Efficiency at Gas/Liquid Flow Ratios Corresponding to 0.3 wt% Noncondensable Gas in Brine

Figure 8.8-3 Results with Brine Effluents Near Clarification Temperatures (85°C) Indicates > 96% Scrubbing Efficiency at Gas/Liquid Flow Ratios Corresponding to 0.3 wt% Noncondensable Gas in Brine

attained. However, the efficiency of removal begins to decline steeply at a gas/liquid ratio above approximately 0.5 wt%. This drop off may be due to insufficient column height, since the highest gas/liquid ratios used were still well below maximum based on stoichiometric considerations. Gas inlet temperatures were running about 109°F (43°C) from the stack at the GLEF.

We observed a significant drop in brine pH from pH 5.1-5.5 to pH 4.1-4.6 following contact with the noncondensable gases. This is consistent with the reaction described below and with absorption of CO₂. In plant applications, some adjustment in effluent clarification operation may be necessary to overcome the retardation of silica precipitation as a result of lowered pH. On the other hand, precipitation of metal sulfides could enhance overall clarifier/ filter operation by improving solids contact and sludge blanket characteristics.

Samples of the effluent entering and exiting the contactor were collected and analyzed by atomic absorption spectrometry for lead and zinc, the two principal metals available for reaction with H₂S. These data are given in Table 8.8-3. The changes in Pb and Zn concentrations were compared with H₂S concentration changes. In most cases much more lead and zinc were consumed than what was indicated by the reduced H₂S concentrations. Apparently Pb and Zn are being removed from solution by precipitation reactions other than by metal sulfide formation. Lead carbonate precipitation is a possibility, but zinc precipitates other than ZnS cannot be identified at these conditions.

8.8.4.3. Calculations

The principal reactions occurring in the scrubber are the absorption of H₂S and dissociation:

followed by precipitation of metal sulfides

where Z is the oxidation number.

The overall Reaction is:

Table 8.8-3 Lead and Zinc Concentration in Scrubber Brines

Run No.	Lead, Pb ⁺² ppm		Zinc, Zn ⁺² ppm	
	In	Out	In	Out
27	n.a.	38	n.a.	329
28	65	61	334	302
29	61	17	329	329
32	63	29	329	318
34	n.a.	61	n.a.	307
35	n.a.	55	n.a.	323
36	n.a.	32	n.a.	329
38	65	22	313	307
39	64	62	329	307
40	61	36	329	329
43	n.a.	62	n.a.	313
44	n.a.	42	n.a.	323

The brines produced at the GLEF contain on the order of 65 ppm Pb, 280 ppm Zn, and 270 ppm Fe, far in excess of the stoichiometric quantity necessary to react with all the H_2S . The reabsorption of H_2S in the spent brine is favorable because of the new equilibrium established between the gas and liquid at lower temperature and higher pH.

The efficiency of H_2S removal in the scrubber test runs were calculated simply from the concentration of H_2S in the noncondensable stream entering, $(H_2S)_i$, and exiting, $(H_2S)_o$, the scrubbing unit:

$$Eff = \left(1 - \frac{(H_2S)_o}{(H_2S)_i} \right) \times 100$$

8.8.4.4 Comparisons of Actual and Expected Results

The results confirm the expectation that scrubbing the vent gas with brine effluent removes gaseous H_2S . This method has been shown to be a technically viable process for abatement of H_2S in geothermal flash processes utilizing brine containing relatively high concentrations of heavy metal ions. Although high efficiency of H_2S removal was demonstrated in a single-stage contractor without internal packing, baffling, or optimization of contractor height, it is clear that some optimization of these options will be desirable should pilot tests ensue.

The adaptation of this technique will impact on the design of the turbine condenser. In order to achieve high overall abatement efficiency, a surface type condenser will be required to minimize the volume of liquid in contact with H_2S in the gas phase and, thereby, maximize the amount of gaseous H_2S to be ultimately scrubbed.

The distribution of H_2S between the gas and liquid phases is not sensitive to the absolute quantity of H_2S , but depends largely on pH and temperature. The distribution is given by Henry's law.

$$\frac{H_2S(ag)}{H_2S(g)} = K = 10^{-1.15} \text{ (@40°C) (See Ref. 8.8-3)}$$

where $H_2S(ag)$ is the concentration of dissolved H_2S in moles/liter and $H_2S(g)$ is the partial pressure of H_2S in atmospheres. At a 104°F (40°C) condensing temperature and

a mass ratio of condensate to brine of 0.2, about 98.8% of the H_2S would be partitioned in the noncondensable gas phase. At condensate pH's greater than 6.2, progressively more of the H_2S will be absorbed in the liquid and less H_2S ejected in the gas phase. Desorption and release of H_2S will then occur should the condensate be used for cooling water makeup. In previous measurements at the GLEF (LLL 1977), the 1st stage condensate pH was approximately 6.2. Lower stage steam condensates had much higher pH's (8.5-9.5) and would readily absorb H_2S . However, only a small fraction of H_2S is retained in the brine after the 1st stage flash. This amount, subsequently desorbed in the lower flash stages and evolved with the low pressure steam, may still pose a problem. For an accurate assessment of specific H_2S abatement requirements, the actual amounts and distribution of H_2S in the various streams need to be precisely determined.

The results and interpretation of these tests also appear in a recently published paper (See Ref. 8.8-3).

A cost study of geothermal power plants at the Salton Sea KGRA was prepared for SDG&E by Bechtel Nat'l Corp., and The Ben Holt Co. The study was based on plants utilizing the Stretford process as the means for H_2S abatement. The Stretford process is also based on the required use of surface type condensers for the same reasons discussed above. The study estimated the capital costs for the Stretford process alone to be \$1,100,000 for a 50 MWe net power plant. The system consists of a scrubber, absorber, reaction tank, equipment for separation and regenerator of the absorbant liquid, and associated pumps, piping, etc.

By comparison the process utilizing brine effluent would be quite simple. The noncondensable and brine effluent are passed through a contractor in a countercurrent flow mode. The scrubber gases are vented as usual, and the effluent pumped to the clarifier for usual spent brine processing. The capital costs should be significantly less than costs for the Stretford process. Significant operating and maintenance cost savings would also be realized.

The potential for combining the H_2S process with clarifier/filter system is also very promising. A brief test at the GLEF by Magma and SDG&E using the reaction chamber of a 30 gpm EIMCO pilot clarifier as the contactor indicated scrubbing efficiencies on the order of 97% (See Ref. 8.8-2). This adaptation of the process combines H_2S abatement with preinjection clarification with minimal added plant costs, and with potential beneficial effects with respect to clarifier/filter efficiency and mineral recovery from the sludge.

8.8.5 CONCLUSIONS AND RECOMMENDATIONS

A simple, efficient, and potentially inexpensive method for removal of H_2S from noncondensable gases evolved in geothermal flash processes has been successfully tested on a small scale in the field. The method consists of scrubbing the noncondensable gases of H_2S with brine effluents which contain relatively high concentrations of Pb, Zn, and Fe such as those of the Salton Sea and Brawley Geothermal Fields in the Imperial Valley, California. For plant applications, noncondensable including H_2S would be ejected from a surface steam condenser (necessary to minimize the volume of liquid in contact with H_2S) and scrubbed with effluent brine just prior to preinjection clarification. The metal sulfide precipitates are removed in the clarification step and the noncondensibles, less H_2S , are vented as usual.

This method eliminates the need for chemical absorbants and the equipment and costs required for absorbant regeneration. The capital costs should be but a small fraction of the estimates for the Stretford process. Further significant reduction in costs can be realized if the scrubber/contractor shells can be eliminated by utilizing the reaction chamber of the clarifier as the contractor. Tests of this application on the 10 MW clarifier/filter or in a separate scrubber sized for 1 well flow are recommended to provide H_2S abatement efficiency data and to determine what effect the reduced pH effluent may have on injection and clarifier performance.

8.8.6 REFERENCES

- 8.8-1 Bechtel National Inc., and The Ben Holt Company, Feasibility and Risk Study of a Geothermal Power Plant at the Salton Sea KGRA, prepared for the San Diego Gas & Electric Co., May 10, 1978.
- 8.8-2 Featherstone, J.L., GLEF Technical Review Committee Meeting, San Diego, CA, May 1979.
- 8.8-3 Helgeson, H. C., Thermodynamics of Hydrothermal Systems at Elevated Temperatures and Pressures, American Jour. of Science, 267, 729-804, 1969.
- 8.8-4 Jacobson, W.O., GLEF Technical Review Committee Meeting, San Diego, CA., May 1979.
- 8.8-5 Lawrence Livermore Laboratory, LLL Geothermal Energy Development Program, Highlights Report, L.B. Owen & G.E. Tardiff, editors, Report #ATHS/ISP-17, Sept. 1978.
- 8.8-6 Quong, R, K.G. Knauss, N.D. Stout, and L.B. Owen, An Effective H₂S Abatement Process Using Geothermal Brine Effluents, Geothermal Resources Council Annual Meeting, Sept. 24-27, 1979, Reno, Nev., also LLL Rept. #UCRL-83010.

8.9 STEAM SEPARATION

8.9.1 OBJECTIVES

The objective of this test was to determine the effect of impurities in the steam on turbine performance and reliability.

8.9.2 TEST STATUS

This test was not authorized. A proposed scope was not accepted due to funding constraints.

8.10 INJECTION EFFLUENT PROCESSING

Principal Investigator: J. L. Featherstone (Imperial Magma)

8.10.1 OBJECTIVE

The objective of this test was to test the viability of a complete, 10 MW-sized injection brine treatment system that performed precipitation-clarification, filtration and sludge handling, dewatering and disposal. The test was designed to verify various parameters that were established during individual pilot testing of a reactor clarifier, gravity media filter, and a filter press.

8.10.2 BACKGROUND

The chemical analysis of spent non-clarified, Magmamax No. 1 brine at the point of plant effluent is shown in Table 8.10-1. The brine is supersaturated with respect to heavy metals and silica. Precipitation of these components in the injection well, along with plugging of the adjacent formation, has adversely affected the performance of the injection well. The viability of the complete project was in doubt unless cost effective methods can be devised to stabilize the spent brine prior to injection. In early December, 1977, personnel of Imperial Magma and Envirotech Corporation met to discuss methods of treating spent brine to produce a nonscaling liquid suitable for well injection. At this time, it was conceived that auto-precipitation of minerals in the spent brine could be achieved in a solids-contact clarifier, producing an effluent of stable saturation levels of silica and heavy metal sulfides and oxides. Accordingly, a pilot plant reactor clarifier was installed adjacent to the Magmamax No. 3 injection well in February, 1978, and was operated continuously until April 12, 1978. The reactor clarifier proved to be successful in both reducing suspended solids and producing the condition of silica saturation in the effluent. An LLL test of a sand/anthracite pressure filter during April, 1978, proved to be successful in polishing the clarifier effluent. In May, 1978, tests of a pilot-sized filter press by Envirotech and Imperial Magma showed that the sludge could be dewatered easily, producing a filter cake of 65 percent solids by weight. A demonstration plant at the GLEF was subsequently designed and began start-up operation in May, 1979, which included a reactor clarifier, dual media gravity filter, sludge thickener, and filter press to treat the spent brine from the GLEF. This system was designed to demonstrate the process feasibility on a larger scale, and verify the injectability of the effluent. This process has the potential to reduce both the cost and the risk of a commercial power plant at the Salton Sea Geothermal Field.

Table 8.10-1

CHEMICAL ANALYSIS OF SPENT GEOTHERMAL BRINE
FROM THE GLEF

<u>Constituent</u>	<u>Concentration - PPM</u>
Sodium	53,276
Potassium	10,259
Calcium	22,414
Chloride	134,483
Iron	272
Manganese	685
Zinc	207
Lead	53
Copper	1
Barium	129
Silicon as SiO ₂	393
Magnesium	177
Total Dissolved Solids	228,448
Suspended Solids	180
pH	5.6
Temperature Range	200°F (104°C)

8.10.3 TEST DESCRIPTION AND PROCEDURES

8.10.3.1 Test Equipment

The following equipment was used in this test:

- Reactor clarifier - 55 foot diameter
19 foot side wall height
- Dual medial gravity filter - 26 foot diameter
16 foot height
3 cells
- Thickener - 8 foot diameter
- Plate and frame filter press
- Backwash holding tank - 20,000 gallon capacity
- Brine surge tank - 10,000 gallon capacity
- Clarifier feed pumps
- Sludge pump
- Brine injection pump
- Associated piping and valves
- Flow, temperature, pressure and turbidity measurement equipment
- IW-5 injection well

8.10.3.2 Test Description

The supersaturated species and suspended solids in the effluent brine from the GLEF have caused plugging of the injection well and adjacent formation with consequent decrease in capacity and life of the injection well system. The clarifier/filter system decreases the effluent brine supersaturation with respect to silica and heavy metals to produce a non-scaling liquid suitable for well injection (Figure 8.10-1). The reactor clarifier receives flow from the GLEF atmospheric flash tank through two clarifier feed pumps. The reactor clarifier provides residence time for the formation and settling of solids and internal sludge recirculation to accelerate the precipitation reactions. The clarified brine flows by gravity to the dual media filters for polishing and thence to the brine surge tank, where it is pumped into the injection well, IW-5. Sludge flows from the reactor clarifier by gravity to the thickener where the sludge is further concentrated and is then pumped to a filter press. The filter press drops the dewatered sludge cakes into a

Figure 8.10-1 Clarifier/Filter Installation Process Flow Diagram

transportable bin or dump truck. For this test, the dewatered sludge was trucked to San Diego for disposal because an acceptable local disposal site is not currently available. The thickener overflow, the filtrate from the filter press, and media filter backwash brine all flow to the backwash holding tank where they are pumped intermittently back to the clarifier.

8.10.3.3 Test Prerequisites

Small pilot equipment operations, including a reactor clarifier, gravity filter, sludge thickener and a filter press, had been previously carried out at both the Magmamax No. 2 and No. 3 well sites and on the GLEF effluent. Tests at both sites were considered successful and sufficient data was collected to proceed into the 10 Mw-sized demonstration plant operation.

8.10.3.4 Test Conditions

The following conditions were the design points for the injection brine treatment system:

- o Reactor clarifier
 - Brine flowrate - 1600 gpm
 - Upflow velocity - 0.72 gpm/sq. ft.
 - Settling velocity of solids - 1.5 gpm/sq. ft.
 - Optimum solids - concentration in reaction zone - 2.5% by weight
- o Dual media gravity filter system
 - Filtration rate - 3.0 gpm/sq. ft.
 - Filter cycle time - 24 hours
 - Backwash rate - 22 gpm/sq. ft.
 - Suspended solids - 1 to 5 ppm in filter effluent

8.10.4 RESULTS

8.10.4.1 Data and Observations

A summary of the test data is presented in this section. These values are averages of data taken periodically during normal operation of the injection brine treatment system. Daily averages appear in Appendix F.

1. Reactor clarifier

Parameter

Average Measurement

Clarifier influent
(Brine feed)

Temperature - 220°F (104°C)

Turbidity - 35 NTU

Suspended
Solids - 180 ppm

Silica in
Solution - 390 ppm

pH - 5.4

Total Flow - 1205 gpm

GLEF Flow - 525 gpm

Recycle
Flow - 680 gpm

Clarifier Effluent

Temperature - 215°F (102°C)

Turbidity - 15 NTU

Suspended
Solids - 100 ppm

Silica in
Solution - 200 ppm

pH - 5.1

Clarifier Reaction Zone

Suspended
Solids
by wt. - 1.8%

Clarifier Draft Tube

Suspended
Solids
by wt. - 2.7%

Clarification Zone at
point 50" vertically
from bottom of side
wall

Suspended
Solids
by wt. - 0.06%

Upflow velocity

0.51 gpm/sq. ft.

Settling velocity

2.0 gpm/sq. ft.

2. Dual Media Gravity Filter System

Parameter

Average Measurement

Filter feed

Temperature - 215°F (102°C)

Flow - 1370 gpm

Turbidity - 13 NTU

Suspended Solids - 90 ppm

Silica in Solution - 200

pH - 5.1

Filter Effluent

Temperature - 210°F (101°C)

Turbidity - 5 NTU

Suspended Solids - 4-10 ppm

Silica in Solution - 192 ppm

pH - 5.0

Filter backwash

Backwash Cycle Time (automatic mode) - 60 min.

Water wash - 5.5 min.

Air Scour - 3 CFM for 1.5 min.

Suspended Solids:

After 15 seconds - 13,300 ppm

After 5 minutes - 100 ppm

Initial Backwash rate - 18-20 gpm/sq. ft.

2. Dual Media Gravity Filter System (Cont'd)

<u>Parameter</u>	<u>Average Measurement</u>
Media Size	
Coal	Effective size - 1.0 to 1.1 mm Uniformity coefficient - less than or equal to 1.7
Sand	Effective size - 0.44 to 0.55 mm Uniformity coefficient - less than or equal to 1.7
Filter cycle time	8 to 15 hours

3. Thickener

<u>Parameter</u>	<u>Average Measurement</u>
Thickener feed	Suspended solids by weight - 6 to 10%
Thickener under flow	Suspended solids by weight - 10 to 20%
Thickener overflow	Suspended solids by weight - 0.05 to 0.10%

4. Filter Press

<u>Parameter</u>	<u>Average Measurement</u>
Feed	Pressure - 90 psig Temperature - 190°F Suspended solids by weight - 10 to 20%
Filtrate	Suspended Solids - 100 ppm
Cake	Suspended Solids by wt. - 65%
Solids production rate	400 lbs (dry weight) per million lbs. of brine

8.10.4.2 Discussion

The fundamental component of the brine injection processing system is the reactor-clarifier (Figure 8.10-2). The unit operates on the principle of solids contact clarification whereby large volumes of sludge (10-15 times the volume of feed) are recirculated internally through a draft tube/turbine arrangement to a reaction well. Previously precipitated sludge recirculated in this manner comes into intimate contact with the feed stream in the reaction well, providing seed nuclei on which dissolved solids in the feedstream precipitate under controlled conditions of temperature, reaction time and solids concentration. The resultant liquid/solid mixture flows from the reaction well into the clarification compartment where liquids and solids are separated by gravity. Treated liquid overflows into the collection weirs at the surface of the unit. Rake arms are used to move settled solids to a center thickening cone at the bottom of the tank where the thickened sludge is discharged by gravity.

The 55 foot diameter reactor-clarifier was operated from May 27, through September 13, 1979. The total operational times for the equipment are listed below:

<u>Equipment</u>	<u>Start-up Date</u>	<u>Total Operation</u>
Reactor-Clarifier	May 27	1700 hours
Dual Media Gravity Filter	July 26	500 hours
Filter Press	July 4	102 tons (dry weight) of solids
IW-5	July 28	425 hours, ⁶ 14.2 x 10 ⁶ gallons of clarified - filtered brine

It must be emphasized that 1,700 hours of operation on the clarifier represents little more than two months of continuous operation. This is not enough time to fully evaluate many of the operational parameters of the system. However, a number of important trends have emerged and will be discussed.

Because only one-well flow was available, flow from the GLEF averaged only 525 gpm during the test period. For this reason an average of 680 gpm of clarified brine was recycled from the injection pump discharge to the clarifier inlet stream giving a total influent of 1205 gpm. Since the design flow for the reactor-clarifier was based on the full

Figure 8.10-2 Solids Contact Reactor-Clarifier

production design flow from two wells of 1600 gpm (upflow velocity = 0.72 gpm/sq. ft.), the total average influent was only 75% of the reactor-clarifier design point. Weekly average flows appear in Figure 8.10-3. Evidence from the pilot clarifier program indicated that best results with respect to suspended solids in the clarifier overflow were obtained when the sludge blanket was carried considerably above the lower outside edge of the reaction zone. In the operation of the 55 foot diameter unit, it was not possible to carry the sludge blanket at this point. Several factors combined to cause this problem. First, as mentioned above, the design upflow velocity was never achieved. Secondly, the average settling velocity of the suspended solids taken from the reaction zone of the clarifier was found to be 2.1 gpm/sq. ft. as compared to 1.5 gpm/sq. ft. in the pilot test. Using the conservative designer's "rule of thumb" for sizing clarifiers, the 55 foot diameter reactor clarifier is actually sized for 2333 gpm effluent flow (See Note 1). In view of these factors the sludge bed was never properly expanded. The average sludge density was only 0.06% suspended solids at a point 50 inches from the bottom of clarification zone sidewall. The average suspended solids concentration in reactor clarifier effluent was approximately 100 ppm compared to less than 50 ppm for the pilot tests.

The capacity and performance of the reactor clarifier is depended upon the settling rates of precipitated solids; otherwise, clarification would not occur. In accordance with the Kynch Theory, solids in hindered settling exhibit settling velocities inversely proportional to the solids concentration in the zone which they settle. This is verified in Figure 8.10-4. Upflow velocities as high as 2.4 gpm/sq. ft. can be maintained in the reaction zone of the clarifier when approximately 0.5% solids by weight are held in the reaction zone of the clarifier. As these concentrations are increased, upflow rates must be decreased accordingly. In achieving a cost-effective process, there exists a compromise between continuous production of a stable saturated effluent from the reactor clarifier and the maximum permissible upflow rate in the unit. In Figure 8.10-5, it is shown that a solids concentration of 1.35% will produce a saturated effluent with respect to silica (190 ppm). From Figure 8.10-4 it can be seen that a maximum upflow velocity of 2.1 gpm/sq. ft. would be permitted at 1.35% solids. Clarifier manufacturers normally design units at approximately one half the settling velocity at optimum suspended solids

Note 1: effluent flow = $1/2$ (settling velocity) (area of clarification zone)

$$= 1/2 (2.1 \text{ gpm/sq. ft.})(2222 \text{ sq. ft.})$$

$$= 2,333 \text{ gpm}$$

Figure 8.10-3 Clarifier Flows

Figure 8.10-4 Settling Rate vs Suspended Solids in Reaction Zone

Figure 8.10-5 Silica in Solution in Clarifier Effluent vs Suspended Solids in Reaction Zone

loadings. This would give 1.05 gpm/sq. ft. at 1.35% suspended solids as the conservative design point. This data is more optimistic than the pilot test result which gave 0.72 gpm/sq. ft. at a solids concentration in the reaction well of 2.5%. Settling rates were generally higher in the 55 foot diameter reactor clarifier tests. This result can be attributed to a better measurement technique. Chemical settling aids were not added to the clarifier during these tests. As indicated in Figure 8.10-6, the clarifier reduced the average suspended solids from 182 to 100 ppm.

To insure continuous, long term injection of spent geothermal brine at the Salton Sea geothermal resource, it is necessary to remove suspended solids to an acceptable level. Perhaps more importantly, it is necessary that the silica remaining in solution be close to saturation values for the brine temperature at the injection wellhead.

The reactor clarifier performed as an excellent silica reactor (Figure 8.10-7). It brought the average silica in solution down from 390 ppm to a near-saturation 200 ppm. The high degree of supersaturation in this fluid was causing the very high rate of scaling in the second stage and the pre-clarifier injection line of the GLEF. It is also the compelling reason why pre-clarifier injection wells failed within the first six months of continuous injection. The 2 inch x 80 mesh slots of the injection interval of a typical injection well form an ideal area for scale build-up. When these slots are effectively bridged, required injection pressures become excessively high. Of course, other mechanisms related to suspended particles in the injection brine are also at work to cause injection well damage.

The dual media gravity filter was started on July 26, 1979, only after the clarifier was judged to be performing adequately. The filter was operated for a total of 500 hours. Several start-up and operational problems were encountered and are listed below:

1. The slots in the Flexkleen Distribution Nozzles were too large (manufacturer error). This caused a loss of sand filter media during normal operational cycle.
2. The backwash cycle was often interrupted by electrical probes shorting out in the high saline brine. The problem may have been corrected by replacing all electrical probes with pressure switches.
3. Because the backwash cycle was two to three times shorter than design, the brine surge tank (Figure 8.10-1) downstream of the filter was much too small. There are two sizing criteria that

Figure 8.10-6 Suspended Solids

Figure 8.10-7 Silica in Solution

must be satisfied. First, a reasonably constant injection rate should be maintained. Second, the filter backwash water holding tank should be filled in the shortest possible time, so that water is available for another closely following backwash. The existing tank did not adequately compromise these criteria under the operating conditions.

4. Again due to the frequent backwash cycle, the backwash holding tank return pump should have had approximately twice the capacity it did, so that the backwash holding tank could be pumped down more quickly. If inflow can be maintained reasonably constant, this would enable the backwash holding tank to be ready to receive additional dirty backwash water from the filter as soon as possible.

Because of the above-mentioned problems, the filter test data must be viewed as preliminary. Any final evaluation must await further testing. However, several trends have been indicated by the operation thus far.

The purpose of the filter is to remove suspended solids from the reactor clarifier effluent, which had an average suspended solids content of 100 ppm. Periodic grab samples taken by the operators indicated an average suspended solids content of 10 ppm in the filter effluent (Figure 8.10-8). A more accurate and time consuming technique utilizing on-line sampling with a pressurized Millipore filter holder indicated the effluent suspended solids actually ranged from 4 to 10 ppm. Since this technique prevents air contact with the sample, less iron and silica are precipitated. Except for a slightly higher suspended solids content in the effluent (1-5 ppm versus 10 ppm), the filter data is basically consistent with the pilot test results.

In the first week of operation, a cycle time of eight hours was obtained between full filter backwashes. At the end of three weeks of filter operation, the average time between full filter backwash had increased to 15 hours. Backwash of each cell was initiated when one of the three cells of the filter obtained approximately 5 feet of head loss. The three cells backwashed individually in a sequence dictated by head loss. Pilot filters operating under the same conditions operated for 24 hours between full filter backwashes. Two possible reasons for this difference are noted. First of all, the solids loading was twice that of previous smaller scale pilot tests. Secondly, the physical and chemical composition of the suspended solids passing through the filter were different from the pilot test. These finer particles (ferric hydroxide) may have caused a matting problem on the surface of the media. The average

Figure 8.10-8 Suspended Solids Across SVG Filter

filtration rate for the dual media gravity filter was 2.5 gpm/sq. ft. The initial backwash rate was approximately 20 gpm/sq. ft. Upon examination of the media after shutdown, it was noted that approximately 25% of the sand and a lesser amount of the anthracite had been lost during the testing period. No scaling of the media or any section of the dual media filter was evident upon inspection.

The thickener received sludge underflow from the clarifier on an intermittent basis. As the thickener was designed only to be a sludge holding tank for filter press operation, no critical thickener design parameters were established by this test. The thickener feed averaged 6-10% solids by weight. The solids content in the thickener overflow averaged 0.05 to 0.10%. The solids content in the thickener underflow averaged 10 to 20% by weight.

Approximately 100 tons of solids were processed in the filter press during the test period. Cycle time for optimum operation was on the order of 45-50 minutes. Filter cakes of 65% solids by weight were achieved under normal operational conditions. Generally, the unit operated reliably. The full time effort of one man was required to operate the filter press. For summer operation the filter press area should be covered. Based on the measured quantities processed at the filter press, 400 lbs. of solids per million pounds of brine were precipitated on a dry weight basis. A chemical analysis of the filter cake is shown in Table 8.10-2. The cake material is principally silica with significant amounts of iron, calcium, barium and strontium.

The new injection well IW-5 was utilized for only 425 hours during this test. A total of 14,200,000 gallons of brine was injected in IW-5 during this period. On July 28, the first day of brine injection into IW-5, an average of 651 gpm of clarified and filtered brine was injected at a wellhead pressure of 150 psig. This gives an injectivity index of 4.3 gpm/psig. On August 18, the last day of brine injection into IW-5, an average of 437 gpm of brine was injected at a wellhead pressure of 102 psig. This also gives an injectivity index of 4.3 gpm/psig. In a report by L. B. Owen of Lawrence Livermore Laboratories (Ref. 8.10-1), a modified version of the Barkman Davidson method for assessing injectivity was used to assess the injectability of the reactor-clarifier gravity filter effluent. Owen reported that injectability as measured through both membrane filters and Kayenta sandstone cores was poor due to the surface formation of a mat of an iron-rich precipitate. Although no decrease in the injectivity of IW-5 was noted in the short 425-hour test, the chemical composition of the suspended solids in the filter effluent was found to be:

Iron:	45.2%
Silica (SiO ₂)	23.9%

Table 8.10-2

Filter Press Cake Elemental Analysis

<u>Species</u>	<u>Wt. %</u>
Sodium	0.26
Potassium	0.27
Silica	74.4
Iron	5.44
Zinc	0.1
Lead	0.1
Manganese	0.35
Barium	4.80
Calcium	2.29
Strontium	3.02
Sulfur (Total)	2.12
Sulfate	6.38
Chloride	660
Fluoride	192
Carbonate	less than 0.5
Copper	0.5
Chloride	8.6

As shown in Figure 8.10-2, 50-60% of the total flow through the clarifier was recycled from the injection pump discharge. Since several areas of brine-air contact were identified in the system, a large percentage of clarified, filtered brine is exposed to oxygen several times. The reactions of ferrous iron with oxygen and water are given below:

The net result of these reactions is the formation of insoluble ferric hydroxide and a reduction in pH of the brine. The pH reduction across the system is given below:

GLEF Effluent (before recycle addition)	-	pH = 5.4
Clarifier Effluent	-	pH = 5.1
Filter Effluent	-	pH = 5.0

As noted earlier the suspended solids in the dual media gravity filter effluent were principally ferric iron. Although ferric iron precipitates and their relationship to brine-air contact were observed and correctly understood in pilot tests, it did not appear, at that time, to be a serious problem. The pilot tests were run as once through systems without recycle. The pilot filter effluent suspended solids (1 to 5 ppm) were mostly silica with 5 to 10% iron. When the system is operated without recycle, the amount of iron in the filter effluent is expected to be much less. Elimination of as much brine-air contact as possible will also eliminate the precipitation of iron. With the expected elimination of the iron precipitation problem, the processed geothermal brine should be readily injectable. Approximately 1/16 inch of scale was found in the 10 inch discharge piping of the injection pump after 1,700 hours of operation. The six inch recycle line, which experienced higher fluid velocities, had no measureable amount of scale after 1,700 hours of operation. The reactor clarifier internals in particular the turbine and draft tube, sustained less than 1/16 inch of scale in 1700 hours.

Conclusions:

1. The 55 foot diameter reactor clarifier-dual media filter system was generally similar to the preceding pilot system. Preliminary results indicate that the system was successful in producing a stable effluent with respect to silica.
2. A serious iron precipitation problem related to oxygenation of the brine was identified. Elimination of air-brine contact should solve this problem. Special care must be taken with respect to the recycle mode.
3. Higher settling rates for suspended solids were found for the 55 foot diameter reactor clarifier as compared to the 8 foot diameter unit (2.1 vs 1.5 gpm/sq. ft.). A lower number for suspended solids in the 55 foot diameter reaction zone for the saturation of silica (1.3% vs. 2.5%) was also found. This translates into a smaller reactor clarifier for a given power plant size than was projected from the pilot tests.
4. Approximately 400 lbs of dry weight solids require disposal per million pounds of brine.
5. A much longer test period is necessary for a definite statement on the long term injectability of the system effluent.

8.10.5 REFERENCE

- 8.10-1 Owen L, Raber E., Otto C., Murath R., and Allen L., An Assessment of the Injectability of Conditioned Brine Produced by a Reaction Clarification - Gravity Filtration System in Operation at the Salton Sea Geothermal Field, Southern California, LU Report, UCID 18488

8.11 MAKEUP WATER INJECTION COMPATIBILITY

Principal Investigator: J. L. Featherstone (Imperial Magma)

8.11.1 OBJECTIVES

The objective of this test was to establish the technical feasibility of mixing Salton Sea water with geothermal brine in the Eimco pilot plant reactor clarifier.

8.11.2 BACKGROUND

Original plans called for the use of steam condensate from the plant as cooling water makeup. This meant that only 80% of the geothermal fluid that was flowed from producing wells could be injected into the reservoir. The Salton Sea was a readily available source of makeup water. It was hoped that processing a Salton Sea-geothermal brine mixture through a reactor clarifier would remove potential precipitates to the point that the water would become readily injectable, if required.

The materials and equipment used for this test were as follows:

- o Eimco solids contact-reactor clarifier, type HRB, 8' diameter (existing)
- o Gravity dual media filters
- o Filter press (existing)
- o Membrane filtration apparatus (LLL)
- o Core flooding apparatus (LLL)
- o Sludge holding tank - 20,000 gallons (5,000 gallons existing)
- o Makeup water holding tank (20,000 gallons existing)
- o Electrochemical corrosion instruments (to be furnished by LLL)

8.11.3 TEST DESCRIPTION

Brine (clarifier feed) was fed on a side stream from the GLEF to the pilot reactor clarifier into the internal draft tube. Salton Sea water (trucked in from Bombay Beach) was fed into this draft tube and mixed with the brine (Figures 8.11-1 and 8.11-2). This process had a resultant brine residence time in the clarifier of approximately two hours, during which several precipitation reactions occurred (See Section 8.11-4).

Figure 8.11-1 Experimental Arrangement for Salton Sea Addition Testing

Figure 8.11-2 Reactor Clarifier

After passing through the clarifier the effluent (clarified) brine was routed to injection and the remaining solids, in the form of a sludge was collected in a holding tank and dewatered by a filter press. Flow measurements were made during this test on the Salton Sea water with a rotameter and the clarifier effluent flow was measured by volume displacement.

8.11.4 DISCUSSION AND RESULTS

A pilot test, approximately 700 hours in length, was run in November and December, 1978. These tests were conducted on the clarifier effluent to determine its injectability. The solids produced in the clarifier were measured and analyzed. Table 8.11-1 shows the geothermal brine from Magmamax No. 1 contained 21,000 ppm calcium and 140 ppm barium. The Salton Sea water contained high concentrations of sulfate ions (850 ppm). Potentially, 500-1000 ppm of barium and calcium sulfate could precipitate on mixing. The weight % sulfate in the sludge from the clarifier draft tube was found to be 41%. An elemental analysis of the sludge is shown in Table 8.11-2.

The test results from the reactor clarifier, the gravity dual media filter, and the filter press are contained in Table 8.11-3. The clarifier effluent was saturated with respect to both dissolved silica and sulfate species as determined by Lawrence Livermore Laboratory's incubation tests lasting 24 hours (See Ref. 8.11-1). Approximately 48 ppm of suspended solids were contained in the clarifier effluent. Filtration of the clarifier effluent through a dual media-gravity filter (1 foot of sand, 2 feet of anthracite) produced a filter effluent of less than 1 ppm suspended solids as filtered through a 0.45 micron filter. The dry solids from the filter press were 61.5% by weight.

The solids production rate based on dry weight solids was 265 lbs/day for the pilot clarifier. This was a factor of two greater than that obtained from the pilot clarifier tests using geothermal brine only. The only operational problem encountered during the test was scale formation in the draft tube at the point of mixing of Salton Sea water and brine. The precipitation reactions for both silica and sulfate species were evidently very rapid and scale formed very rapidly (Figure 8.11-2). The composition of the scale was found to be similar to the sludge analysis given in Table 8.11-2. Both Envirotech and Imperial Magma believe that this problem could be easily solved by a modified mixing arrangement.

8.11.5 SUMMARY AND CONCLUSIONS

1. A stable, saturated effluent was produced by the reactor clarifier.

Table 8.11-1

COMPARISON OF SELECTED SPECIES

<u>Constituent</u>	<u>Magmamax No. 1</u> <u>Concentration (ppm)</u>	<u>Salton Sea</u> <u>Concentration (ppm)</u>
Ca	21,000	850
Ba	140	0.07
Sr	250	13.5
SiO ₂	400	0.32
Fe	280	0.24
Cl	131,000	14,700
SO ₄	less than 25	8,100
pH	5.4	8.6
TDS	200,000	38,600

Table 8.11-2

ELEMENTAL ANALYSIS OF SLUDGE

(80% GEOTHERMAL BRINE + 20% SALTON SEA)

<u>Constituent</u>	<u>Concentration (ppm)</u>
SODIUM (Na)	3.00%
POTASSIUM (K)	0.57%
LITHIUM (Li)	82 PPM
CALCIUM (Ca)	12.02%
STRONTIUM (Sr)	3.88%
BARIUM (Ba)	10.4%
LEAD (Pb)	1043 PPM
IRON (Fe)	2.06%
MANGANESE (Mn)	922 PPM
ZINC (Zn)	428 PPM
SULFATE (SO ₄)	41.07%
SILICA (SiO ₂)	15.9%
CARBONATE (CO ₃)	ND, Less than 0.05%
CHLORIDE (Cl)	7.83%
SILVER (Ag)	46 PPM

Table 8.11-3

TEST RESULTS

Summary of selected test results (Salton Sea Makeup)

Clarifier

Brine flowrate	21.5 gpm
Salton Sea flowrate	5.5 gpm
Upflow Velocity	0.7 gpm
Temperature of Effluent	190°F (88°C)
Temperature of Brine Feed	215°F (102°C)
Temperature of Salton Sea Feed	60°F (16°C)
Chemical Requirement	None
Solids Production Rate	265 lbs/day

Chemical Data

<u>Constituent</u>	<u>Feed (ppm)</u>	<u>Effluent</u>
SiO ₂	330	220
SO ₄	1620	1110
pH		5.6
Suspended Solids (.45 micron)	200 (brine) 100 (Salton Sea)	48

Gravity Dual Media Filter

Filtration Rate	3 gpm/ft ²
Backwash Rate	20 gpm/ft ²
Air Scour	Required
Suspended Solids (.45 micron)	5 ppm
Membrane Filter Test (.45 micron)	Less than 1 ppm

Filter Press

% Solids in Cake - 61.5%
Bulk Density of Wet Cake - 100 lbs/ft³

2. At least twice the amount of solids were produced when Salton Sea water was added to the brine versus brine alone.
3. A scaling problem existed in the clarifier at the point where Salton Sea water and the brine were mixed.
4. Although a stable effluent was produced by the pilot reactor clarifier, a larger demonstration plant test is necessary to test the actual injectability of this brine mixture. For example the retrograde solubility of CaSO_4 could give problems in the injection formation as the Brine reheats. Also, any detrimental interaction of a chemically altered (through mixing) brine with reservoir matrix materials must be learned through actual injection experience.

8.11-6 REFERENCES

- 8.11-1 Raber et al, "Using Surface Waters for Supplementing Injection at the Salton Sea Field (SSGF), Southern California," Geothermal Resources Council Transactions, Vol. 3, Sept. 1979.

8.12 WELL CASING MATERIALS

Principal Investigators: R. D. McCright, A. Goldberg, E. O. Snell, F. E. Locke, R. McLain, W. P. Frey, W. J. Steele, R Quong, and G. E. Tardiff (private consultant for LLL)

8.12.1 OBJECTIVES

Determine the API grade of carbon steel best suited for well casing application and the composition-dependent variations within API specifications that influence corrosion lifetime. This is expected to lead to API steel specifications for maximum geothermal well casing lifetime.

8.12.2 BACKGROUND

The useful lifetime of carbon steel well casings in the Salton Sea KGRA is expected to be very limited. Downwell corrosion tests of J-55 tubing (State No. 1, Shell Oil Co.), for example, indicate corrosion rates of 100 mils/yr at the top of the well increasing to 2000 mils/hr at the well bottom. In addition, the carbon steel casing in the Sinclair No. 4 well suffered severe enough corrosion attack by a perforation mechanism after about six months of accumulated operation, to cause the operators to abandon the well. No data yet exists on corrosion of carbon steel casing in brine from the upper reservoir in the Salton Sea KGRA. Recent examination of surface piping just downstream of the Magmamax No. 1 Wellhead, however, indicated the presence of a perforating mode of attack and a corrosion rate of 120 mils/yr. It is expected that at least the upper portion of the Magmamax No. 1 well casing is similarly attacked. Present information indicates that carbon steel well casing lifetime will be less than four years even for the upper reservoir.

The great expense of new wells and well recasing leads to the conclusion that even nominal improvement in casing life will have a substantial cost benefit. For example, Reference 8.12-1 concludes that doubling well casing life will have a greater impact on reduction of busbar energy cost (10% reduction) than any other R&D initiative.

8.12.3 TEST DESCRIPTION AND PROCEDURE

8.12.3.1 Test Materials and Equipment

A tubing string consisting of 30' lengths of 1.66" outside diameter tubing joined together by threaded couplings was to be tested downhole in the Woolsey No. 1 well. The materials tested were API J-55 (baseline) N-80 and C-75,

all available in well casing and tubing string. The string was to be designed so that the three materials would be exposed to brine distributed at different depths in the well.

8.12.3.2 Test Prerequisites

Appropriate chemical and metallurgical analyses will be performed to characterize each lot of steel before installation.

8.12.3.3 Test Conditions

Woolsey No. 1 wellflow at design operating conditions was required. Large variations greater than $\pm 10\%$ in the wellflow were not desirable, but will not void the tests. The flash point in the well was to be maintained above one set of sample tubing lengths to provide constant exposure to a two phase fluid. Again, full well flow during as much of the time as possible during the 3 months exposure was desirable.

8.12.3.4 Required Data and Observations

Tubing strings containing lengths of J-55 (base-line) N-80 and C-75 was to be tested downhole in the Woolsey No. 1 well. Three lengths of each material were to be tested at three different depths in the well as a means of obtaining data on the effect of composition and depth on corrosion. Each lot of material tested was to be characterized by chemical and metallurgical analysis. After exposure, the various materials were to be analyzed for the various forms of corrosion (general, pitting, crevice, etc.) using metallurgical analysis methods.

Normal well operating data - flowrate, temperature, and pressure were to be obtained from the GLEF daily log. Data on fluid properties from other activities in the test program were expected to be sufficient for integrating with the corrosion results.

8.12.3.5 Test Duration

The goal was to accumulate 3 months of downwell exposure. Complete analyses and reporting was anticipated to take another 2 months.

8.12.4 RESULTS

8.12.4.1. Expected Results

The corrosion rate and projected lifetime of one to three different API grades of steel exposed to Niland brines at downwell conditions were to be determined. The effect of depth was also to be determined.

The effect of chemical composition, thermo-mechanical histories, and resulting microstructures within each grade was to be evaluated.

Failure mechanism was to be evaluated and reported.

8.12.4.2 Data and Observations

Test Materials - Three grades of random 30-ft. long x 1- $\frac{1}{4}$ inch nominal diameter x 0.140 inch nominal wall API steel tubing were obtained for test and evaluation: J-55, N-80, and C-75. These materials were ordered to API specification 5A (J-55 and N-80) and 5AC (C-75). Table 8.12-1 gives the API specification data, the vendor supplied chemical analysis, and the vendor supplied mechanical property data for the three materials.

API Test String Makeup - The test string was emplaced in Woolsey No. 1 well according to scheme shown in Table 8.12-2 by coupling individual joint lengths together. The joint number, joint length, depth in well, and material designation are given in the table. The J-55 and N-80 joints had externally upset and threaded ends and were coupled together using standard couplings. The C-75 joints had integral threads and were joined to J-55 joints using crossover nipples.

Exposure Duration and Environment - The string was emplaced in Woolsey No. 1 well on January 16, 1979, and removed from the well on March 26, 1979, for a total of 69 days exposure. The well operational history during this test period is summarized in Table 8.12-3. Note that the exposure temperature ranged from 500°F (260°C) (well bottom) to 374°F (190°C) (at the well head) during those periods when the well was flowing. Brine pH as determined on samples taken at well head conditions and cooled to ambient temperature was 5.8. Downhole pH measurements have not been made, however, brine pH is expected to decrease with increasing depth in the well because of the greater solubility of the acidic gases CO₂ and H₂S at high pressures. Calculations by Jackson (See Ref. 8.12-2), for example, for a nearby well (Magmamax No. 1) indicate a well bottom pH of 4.5. Flow environment is two phase above the flash point with about 10% quality at the wellhead. Flow velocity increases greaterly above the flash point to an estimated maximum of 100 ft/sec for the Woolsey No. 1 well.

The chemistry of the Woolsey No. 1 brine is given in Table 8.12-4. The salient features include the high salinity, mildly acidic pH and the low oxidation-reduction potential as indicated by the sulfide ion concentration.

Scale Deposits - The thickness of scale deposited on various joints are plotted as a function of depth in

Table 8.12-1 Summary of API Material Analysis and Properties

J-55 - Ordered to Following API Specification: tubing, grade J-55, API std. 5A, seamless, 1-1/4" nominal, 2.40 lb/ft., EUE IORD, T & C range 2.

Vendor Supplied Chemical Analysis: .31 C, 1.43 Mn, .011 P, .012 S, .06 Si, .13 Mo, bal Fe.

Vendor Supplied Mechanical Properties: Yield strength - 64,000 and 64,500 psi; ultimate tensile strength - 91,400 and 92,050 psi; elongation in 2" - 34 and 30 percent.

Mechanical Properties Required by J-55 Specification: Minimum field strength - 55,000 psi, maximum yield strength - 80,000 psi. Minimum ultimate strength - 75,000 psi.

N-80 - Ordered to Following API Specification: tubing, grade N-80 API std. 5A, 1-1/4" nominal 2.40 lb/ft. EUE, IORD, T & C, range 2.

Vendor Supplied Chemical Analysis: .44 C, 1.60 Mn, .016 P, .018 S, .023 Si, .20 Mo.

Vendor Supplied Mechanical Properties: Yield Strength - 93,000 and 95,100 psi; ultimate tensile strength - 133,700 and 126,300 psi; elongation in 2" - 28 and 28 percent.

Mechanical Properties Required by API Specification: Minimum Yield Strength - 80,000 psi, maximum yield Strength - 110,000 psi; minimum ultimate tensile strength - 100,000 psi.

C-75 - Ordered to following API Specification: tubing, Grade C-75, API Std. 5AC, 1-1/4" nominal 2.33 lb/ft. IORD 1J, Range 2.

Vendor Supplied Chemical Analysis - Same as for N-80 since C-75 was prepared by heat treatment of N80. Meets API chemical requirements for grade C-75, type 1 material.

Table 8.12-1 Summary of API Material Analysis and Properties (continued)

Vendor Supplied Mechanical Properties - Not available. Heat treated to produce C-75 properties.

Mechanical Properties Required by API Specification - Minimum yield strength - 75,000 psi, maximum yield strength - 90,000 psi; minimum ultimate tensile strength - 95,000 psi.

Table 8.12-2 Summary of API Testing String Makeup

Joint* Number	Material	Length (ft)	Depth in Well (ft)
1	J55	33.8	1728
2	N80	31.6	1694
3	J55	33.2	1662
4	C75	34.5	1629
5	J55	31.1	1595
6	J55	34.5	1563
7	J55	34.2	1529
8	J55	34.2	1495
9	J55	33.2	1461
10	J55	34.5	1427
11	J55	34.4	1393
12	J55	34.1	1359
13	J55	34.4	1324
14	J55	34.4	1290
15	J55	34.4	1256
16	J55	34.5	1221
17	J55	34.4	1187
18	J55	32.7	1152
19	N80	33.5	1119
20	J55	31.5	1086
21	C75	34.3	1055
22	J55	34.4	1020
23	J55	34.4	986
24	J55	34.4	952
25	J55	34.4	917
26	J55	34.4	883
27	J55	33.2	848
28	J55	32.7	815
29	J55	34.5	782
30	J55	34.4	748
31	J55	31.5	713
32	J55	34.5	682
33	J55	31.4	647
34	J55	33.9	616
35	J55	34.5	582
36	J55	34.4	548
37	N80	33.5	513
38	J55	34.4	479
39	C75	34.4	445
40	J55	33.2	411
41	J55	34.4	377
42	J55	34.4	332
43	J55	34.1	298
44	J55	33.8	264
45	J55	34.5	230
46	J55	34.4	195
47	J55	34.5	161
48	J55	34.4	127
49	J55	34.5	92
50	J55	34.4	58
51	J55	34.4	13

* first to go into well - joint #1

**Table 8.12-3 Summary of Woolsey No. 1 Well Operational History
During the API String Test Period From January 16
to March 26, 1979.**

Total number hours with brine flow:	904 hours
Total number hours without brine flow:	752 hours
Total string exposure time:	1656 hours
Downhole temperature:	500°F (260°C)
Wellhead pressure (@ plant boundary):	151 psig
Wellhead temperature (@ plant boundary):	366°F (186°C)
Brine flowrate	500 gpm

Table 8.12-4 Woolsey No. 1 Brine Properties* and Composition*.

pH: 5.84 (after flashing and cooling to ambient temperature)
 Density, g/cm³ at 25°C: 1.166
 Chloride, Mol/l : 4.13
 Oxidation - reduction potential: not measured for Woolsey No. 1 brine;
 probably similar to Magmamax No. 1 brine at 237 mV vs. SHE.

<u>Element</u>	<u>Concentration, mg/kg</u>	<u>Element</u>	<u>Concentration, mg/kg</u>
Li	138	B	409
Na	42,400	Al	3
K	6,900	Fe	215
		Mn	607
Mg	81		
Ca	21,700	Cu	2.0
Sr	299	Pb	43
Ba	150	Zn	226
Si as SiO ₂	510	Mo	9
Sulfate	108	As	14
Cd	1.6	V	0.6
Ni	0.4	Zr	0.4
Ti	1.4		

* Brine sampled during February, 1979, after depressurization and cooling to ambient conditions. Approximate total evaporation (flashing) was 20% by weight.

Figure 8.12-1. Scale thickness increased from 25 mils at the bottom of the string to 75 mils at the top of the string. The scale consisted of an adherent but somewhat porous layer of PbS in a calcium carbonate and amorphous iron silicate matrix.

Metallurgical Characterization of the Test

String Materials - Metallurgical sections which were made for corrosion measurements were also used to characterize the metallurgical microstructure of the materials tested. The metallurgical analysis results are summarized in Table 8.12-5. The sections were taken at two locations: an A type located near the upset end of the joint and a B type located in the central region of the joint. Note that the J-55 microstructure consisted of two relatively distinct types: fine grained, normalized ferritic/pearlitic and coarse grained, anneal ferritic/pearlitic. The microstructure of both the C-75 and N-80 consisted of very fine structured tempered martensite.

Corrosion Observations and Data - the surface of the joints were visually scanned for the presence of tubercles. These are nodular growths which form because the iron corrosion product has a greater specific volume than iron. The scale was removed from such tubercle areas and the site of the worst pit was established visually. A specimen was cut from this area such that after mounting and polishing the pit would appear in cross section. A total of about 30 such sections were prepared. Every effort was made to select the worst pit area for sectioning. This was based on the premise that the most useful data would be that which would allow an estimate to be made of the least time of exposure required to cause first breaching of a casing wall. The sections were polished and examined at 15 to 25X. The minimum remaining thickness was measured. The results for the sections are recorded in Table 8.12-6. Very little corrosion was observed in the cases of the N-80 and C-75 sections which were examined. In these cases, it was more accurate to measure the maximum pit depth. These results are recorded in Table 8.12-6.

8.12.4.3 Calculations

J-55: Indicated Penetration Rate - The minimum remaining thickness raw corrosion data listed in Table 8.12-6 was converted by calculation to an indicated penetration rate using the following equation:

$$\text{Indicated Penetration Rate (mpy)} = (T_i - t_r) \times \frac{365}{69}$$

where mpy = mils/year

t_i = initial thickness in mils

t_r = remaining thickness in mils

Figure 8.12-1 Thickness of Scale on Test String Surface vs. Depth in Well for API Test String Tested in Woolsey No. 1.

**Table 8.12-5 Summary of Results of Metallurgical Characterization
of API Test String Materials**

**Joint Numbers and
Section Type ***

Metallurgical Microstructure

J55

3A, 5A, 6A, 7A, 9A, 10B, 12B,
13B, 18B, 27B, 29B, 34B, 40B

Normalized (air cooled) ferritic pearlitic structure with ferrite surrounding prior austenite grain boundaries. Fine grained: 9-10 ASTM grain size number. Slight decarburization up to .003 inch deep.

3B, 6B, 7B, 9B, 11B, 16B, 42B

Annealed (slow cooled) ferritic/pearlitic structure with ferrite surrounding prior austenite grain boundaries. Coarse grained: 2-3 ASTM grain size number. Slight decarburization up to .003 inch deep.

N80

2A, 2B (19 & 37 assumed to be same)

Very fine structured tempered martensite. Slight decarburization up to .003 inch deep.

C75

4A, 4B (21 & 39 assumed to be same)

Very fine structured tempered martensite. Slight decarburization up to .003 inch deep.

Table 8.12-6 J55 Corrosion Measurements

<u>Joint No.</u>	<u>Depth (ft.)</u>	<u>Minimum Wall Remaining (mils)</u>	<u>Indicated Rate of Penetration (mils per yr, mpy)</u>
3A	1662	67	428
3B	1662	102	243
5A	1595	106	222
6A	1564	83	344
6B	1564	106	222
7A	1529	87	323
7B	1529	126	116
8A	1495	39	577
9A	1461	55	492
9B	1461	55	492
10B	1427	118	159
11B	1393	126	116
12B	1358	126	116
13B	1324	130	95
16B	1221	130	95
18B	1152	138	53
27B	848	142	32
29B	782	134	74
34B	616	154	32
40B	411	142	32
42B	332	146	11

365 = days in year

69 = days exposure

The value of t_i or initial thickness used for the J-55 was 148 mils. This was determined by averaging 6 individual micrometer thickness measurements on a length of unexposed J-55 tubing. The results of the above calculation are recorded in Table 8.12-6 and plotted as a function of depth of exposure in Figure 8.12-2.

N-80 and C-75: Indicated Penetration Rate - The procedure used above was also applied to the raw data given for the N-80 and C-75 in Table 8.12-7. In the case of N-80 and C-75, however, the measured pit depth was first used to compute the remaining thickness by taking the difference between the pit depth and the original thickness for N-80 and C-75. The original thickness for this tubing was determined to be 146 mils (average of 6 individual measurements on unexposed tubing). The calculated indicated penetration rates are given in Table 8.12-7 and are also plotted in Figure 8.12-2. As indicated in Table 8.12-7 and Figure 8.12-2, these results correspond to joints which were exposed between 1600 and 1700 feet in depth. No sections were made in the N-80 and C-75 joints which were exposed at about 500 feet and 1100 foot depths. Visual examination of these joints, however, led to the conclusion that the corrosion experienced by these joints was not as severe as that experienced by the joints exposed between 1600 and 1700 feet. Thus, it has been concluded that the maximum penetration rate for the N-80 and C-76 is not greater than the maximum rate indicated for the joints exposed at the 1600 -1700 foot level. The points plotted for the N-80 and C-75 joints exposed at higher levels in Figure 8.12-2 reflects this conclusion. The results in Figure 8.12-2 show that neither grain size nor position of the sample (center of joint vs. near the upset) in the J-55 material correlated with the indicated penetration rate.

8.12.4.4 Comparison of Actual and Expected Results

The indicated penetration rate results for J-55 given in Figure 8.12-2 would rule out J-55 as a reliable material for long life (20 year) production well casing in the Salton Sea KGRA. For example, the results indicate that the first breaching of a 0.5 inch thick casing wall below about 1300 feet by a small diameter pit would occur in about a year; above 1300 feet the time required would be about 5 years. While first breach of the wall by a small pit may not constitute failure, it is an occurrence which signals impending major problems. For example, the continued lateral growth of a pit or link up of many pits could lead to a large hole in the casing, which in turn could lead to degradation of the cement and cement bond and also cause in

Figure 8.12-2 Indicated Penetration Rate vs. Depth for J55, N80, and C75 for API Test String Tested in Woolsey No. 1

Table 8.12-7 N80 and C75 Corrosion Measurements

Joint No.	Depth (ft.)	Depth of Penetration (mils)	Calculated Remaining Thickness (mils)	Indicated Rate of Penetration (mils per year, mpy)
2A - N80	1694	3.0	143	16
2B - N80	1694	2.8	143	15
19 - N80	1119	{ Visual Appearance Indicates Similar to 2A and 2B }		
37 - N80	513			
4A - C75	1629	2.8	143	15
4B - C75	1629	2.1	144	11
21 - C75	1055	{ Visual Appearance Indicates Similar to 4A and 4B }		
39 - C75	445			

leakage of unwanted waters or escape of brine into non-geothermal aquifers. Also, the link-up through-the-thickness pits would seriously reduce the structural integrity of the casing and this could lead to serious safety problems. These results were expected on the basis of other published corrosion rate results for J-55 exposed in Salton Sea Geothermal KGRA Brines (See Ref. 8.12-3). In this case, the corrosion of J-55 was observed to be even more severe because of the greater depth of the well and associated higher temperature and more corrosive brines.

Early downwell corrosion testing on specimens of various unalloyed and low alloy steels led to the conclusion of that small amounts of Mo and other alloying elements provide a substantial improvement in corrosion resistance. The purpose of the present test in part was to determine the extent to which the small amounts of alloying elements present in the higher grade American Petroleum Institute (API) steels would improve corrosion resistance. Qualitatively, an improvement was expected, but it was not possible to quantitatively predict the degree of improvement. Figure 8.12-2 shows that beneficial influence of the greater amounts of Mo and Si in the N-80 and C-75 materials is substantial. The present results indicate that the improvement could be as much as a 20 fold increase in time required for a small pit to just perforate a 500 mil casing wall.

8.12.5 CONCLUSIONS AND RECOMMENDATIONS

It is concluded that J-55 is not suitable for well casing requiring long life but that API Grades N80 and C-75 have the potential of providing long life. Of these, it is recommended that C-75 be given priority for further testing and use. The lower maximum yields strength of C-75 (90,000 vs. 110,000 psi for N80) would reduce or eliminate the susceptibility to delayed failure due to H_2S cracking or stress corrosion cracking. In addition, the API specification for C-75 calls for a minimum alloy content, while alloy content is unspecified for the N-80 material. A quote obtained from an oil field tubular supply company indicates that the cost premium for N-80 and C-75 relative to J-55 are 1.35 X and 1.52 X, respectively. Thus, it does not appear that the cost premium for use of either of these higher API grades is prohibitive.

It is also necessary that confirmatory data be obtained for the better grades of API materials exposed for longer times. The LLL Geothermal Program is being funded by the Geothermal Hydrothermal Technology Group of the DOE to carry out further studies on the use of low alloy steels for the well casing applications. A test string consisting of a variety of low alloy steels including C-75 has been in test in Magmamax No. 1 well. The analysis of the materials in

this string should lead to a much greater understanding of the potential benefits and pitfalls associated with the use of these materials for the well casing and brine handling equipment.

8.12.6 REFERENCES

- 8.12-1 J. G. Leigh, S. M. A. Pond and R. K. Trehan, Cost-benefit analysis of the Federal Geothermal Energy Program: MITRE Corp. Technical Report MTR-7326, 101 psg.
- 8.12-2 LLL Geothermal Energy Program Status Report, January 1976-January 1977, UCRL-50046-76, April, 1977. See article by D. D. Jackson on page 100.
- 8.12-3 R. S. Treseder and Rita Wieland, Down-Hole Corrosion in a Salton Sea Geothermal Well, paper prepared for the 1977 SPE-AIME International Symposium on Oilfield and Geothermal Chemistry, La Jolla, California, June 27-28, 1977, paper number SPE-6613.

8.13 INJECTION STUDIES

Principal Investigators: L. B. Owen, E. Rader, J. Harrar, C. Otto, and R. Netherton

8.13.1 OBJECTIVES

- o Establish the injectability of undiluted effluents produced by a pilot size reactor clarifier gravity filter pre-injection processing system located adjacent to the GLEF.
- o Evaluate the technical and economic feasibility of utilizing Salton Sea Water, Alamo River Water and New River Water as alternate sources for injection makeup.

8.13.2 BACKGROUND

Previous work by LLL and Magma at the Salton Sea KGRA has demonstrated that an effluent processing system consisting of a reactor clarifier and a final pressure filter is capable of yielding an injectable silica under-saturated effluent containing 2 ppm or less suspended particulates greater than 1 micro-meter in diameter. By the summer of 1979, all effluents produced by the GLEF were passed through a pilot clarifier/filter system, sized for 2 well flow, prior to injection. However, data was needed to determine the injectability of processed effluents and the expected useful lifetime of a typical injection well receiving processed brine.

The large-scale utilization of geothermal resources in California's Imperial Valley will necessitate a viable supply of cooling water. However, irrigation waters will probably be unavailable in the quantities ultimately required to satisfy power plant cooling needs. The flash-steam conversion cycle offers a source of clean cooling water in the form of steam condensate. Condensate usage, however, means that a significant mass fraction of produced fluids can not be returned to the production reservoir. In the case of a typical double-flash cycle operating at the Salton Sea KGRA, from 20 to 25 percent of the production fluid will be lost as vapor. Since reservoir pressure maintenance may become a vital issue at some Imperial Valley geothermal resources, the feasibility of using local surface waters for injection makeup should be evaluated.

Within the Imperial Valley, there are three potential surface sources of injection makeup water; the New River, the Alamo River, and the Salton Sea. However, extensive diversion of the waste irrigation waters carried by the New and Alamo Rivers may not be possible in view of the possible detrimental impact on the salinity balance in the Salton Sea. Therefore, our work focused primarily on the utilization of Salton Sea water as source for injection makeup.

The technical feasibility, with respect to injection well and reservoir impairment, of using makeup water was unknown. In the case of partial mixing of makeup water and spent brine, severe problems can be anticipated, because the particulate loading in effluent processing systems may be increased by factors of 2 to 3 times or more as compared to nominal conditions with unmodified production fluids. In addition, the inverse temperature solubility of CaSO_4 , $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$ and CaCO_3 and the possible failure of pre-injection processing to eliminate supersaturation of dissolved species in residual effluents creates the potential for scaling of the injection system and post-injection reservoir impairment as injected effluents begin reheating. Direct injection of ambient temperature Salton Sea or River water has the disadvantages of necessitating independent effluent processing systems for removal of particulates and control of biological activity, increased rates of thermal degradation in the reservoir, accelerated casing corrosion, and potential reservoir impairment as make-up water reheats or partially mixes with in-situ fluids.

The performance characteristics and efficiency of baseline pre-injection effluent processing, consisting of reaction clarification and final gravity filtration, with makeup water additions was also unknown. Primary uncertainties existed in the areas of sludge contact for removal of dissolved supersaturated species, effects of increased suspended solids concentration on unit performance efficiency and flocculation and settling characteristics of sulfate, carbonate, and oxide particulates. Since the process system may also become the last stage for scrubbing H_2S from vent gas emissions (See Section 8.8), effects of heavy metal sulfide particulates on the system performance must also be established.

Required data for optimizing performance of pilot or demonstration brine conditioning systems can best be obtained by bench-scale field tests. This activity was to be closely integrated with the makeup water injection compatibility test (See Section 8.11).

8.13.3 TEST DESCRIPTION AND PROCEDURE

8.13.3.1 Test Materials and Equipment

Injectability of effluents with and without makeup water or heavy metal sulfide additions from the pilot pre-injection process systems located adjacent to the GLEF was to be assessed with on-line membrane filtration and core flooding tests. An automated apparatus, designed and built by LLL was to be located adjacent to the brine processing system (Ref. No. 8.13-1). A second LLL-designed and built manually operated filtration apparatus was to be provided for the use of Magma Power personnel in their evaluation of

the 10 MW sized clarifier (See Ref. 8.13-2). The filtration and core work was to be supplemented with anerobic incubation experiments at injection temperature (167-194°F) (75-90°C). Effluents were to be sealed in nitrogen-pressured glass ampoules and incubated for several days. Periodic measurement of suspended solids was to yield data on the potential for reservoir impairment resulting from post-injection precipitation. Sludge contact with and without chemical additives was also to be evaluated by means of a "hot" jar testing procedure to establish whether reaction clarification can eliminate supersaturated species of silica, carbonate and sulfate from makeup water-brine mixtures.

No modifications to the GLEF or effluent processing system was to be required other than provisions for side-stream brine sampling ports and disposal of small quantities of tested effluent. All bench-scale work was to be carried out in the LLL field test facility.

8.13.3.2 Test Prerequisites

Not applicable.

8.13.3.3 Test Conditions

Evaluation of injectability of pilot-system processed effluents was to require stable uninterrupted operation of the GLEF and the injection processing system for periods of several days. Operational conditions were to be documented carefully. Other task activities were to be completed independently of GLEF operations.

8.13.3.4 Required Data and Observations

Injectivity tests - An automated on-line apparatus of proven design was to be used to obtain filtration and core data in conjunction with Magma's operation of pilot pre-injection processing systems. Filtration data was collected, analyzed and interpreted in accordance with standard methodology (See Ref. 8.13-2 through 8.13-5). Cores and membrane filters were to be operated with and without prefilters to establish their permeability to processed effluents. Standard procedures for geothermal effluent core tests are described by Tewhey et al (See Ref. 8.13-6).

Makeup Water Evaluation - Processing requirements for makeup water was to be established by bench-scale jar and filtration tests (See Ref. 8.13-7). Necessary supporting analytical data on residual supersaturation levels in processed effluents and composition of precipitated solids was also to be obtained.

Anerobic incubation experiments was to be carried out to establish chemical stability of makeup water and

mixtures of makeup water and brine at temperatures between 158 - 194°F (70-90°C) (See Ref. 8.13-8). Similar techniques were to be employed to establish chemical stability of effluents from Magma's 30 GPM pilot pre-injection processing system.

8.13.3.5 Test Duration

Injectivity tests of pre-injection processed effluents were paced by the GLEF operational schedule. Tests were to be indicated whenever clarifier operating conditions changed significantly. Therefore, the ability to perform required tests was to be maintained until the end of the fourth quarter of FY79. Makeup water processing studies was to begin early in FY79 depending upon the availability of brine effluents from the GLEF. Approximately 8 months total field time was to be required to complete the assessment of processing requirements for injection of makeup water and to establish the injectivity of processed effluents.

8.13.4 RESULTS

8.13.4.1 Expected Results

Injectability Tests of Conditioned Brine

The injectivity of processed effluents produced by a pilot clarifier/filter system located adjacent to the GLEF was to be established. Injectivity was to be reported as a function of clarifier/filter operating parameter's with special attention devoted to the effects, if any, of chemical additives. Chemical stability of processed effluents was also to be determined to establish the potential for injection well impairment resulting from post-processing precipitation of silica and other species. Test results were to be used to estimate the useful lifetime of an injection well.

Makeup Water Evaluation

Engineering data describing the effect of makeup water additions to the input fluid of a baseline reaction clarifier/filter system was to be generated. The technical feasibility of a full-scale system for pre-injection processing was to be assessed. Results of parametric studies were to be provided to Magma as a basis for optimization of their brine conditioning evaluation program.

8.13.4.2 Data and Observations

Injectability Tests of Conditioned Brine

A Demonstration Reaction Clarifier -- gravity filtration system with a 1600 GPM throughput capability was in operation at the joint DOE-SDG&E-MAGMA test facility located in the Salton Sea KGRA, Southern California during

the summer of 1979. The system, which was designed to condition spent effluent from a 10 MWe-size geothermal power plant, removes supersaturated dissolved species and residual suspended solids from brine prior to subsurface brine disposal via injection wells. The post-processing chemical stability of conditioned effluents was established by means of anerobic incubation tests at 194°F (90°C). The effect of residual dissolved polymer, that might be used for the purpose of scale control in upstream power plant components on the efficiency of reaction clarification was also evaluated. Membrane filtration and core tests were used to assess the injectability of processed brine.

It was found that the clarifier/filter operational procedures and system design permitted oxygenation of the brine by air intrusion. This resulted in partial stabilization of dissolved silica and precipitation of oxides of iron. As a consequence, conditioned brine injectability was poor. However, elimination of the air intrusion problem would result in a substantial improvement in brine quality.

The clarifier/filter was sized for 1600 GPM throughput, which is adequate to process full flow from two production wells. However, during the evaluation period, it was not possible for the GLEF operators to maintain two well flow because of difficulties with the Woolsey No. 1 production well. As a consequence, the clarifier/filter initially was operated at 50% of its design capacity and, as a result, effluent quality was significantly degraded. The major difficulty was attributed to partial collapse of the sludge blanket.

As an expedient remedial measure, 50 to 60 percent of the clarifier/filter overflow was recycled to boost the average throughput rate in the unit. This procedure resulted in oxygenation of the brine due to air intrusion. Other sources of brine aeration were also subsequently identified. The result of air contamination was precipitation of ferric iron in the form of a hydroxide:

The formation of ferric iron is followed by the hydrolysis reaction:

The net effect was formation of a light flocculant iron-rich precipitate and reduction of brine pH. The pH decrease in turn caused partial stabilization of dissolved silica. Therefore, brine aeration not only resulted in production of new precipitates but also interfered with the ability of the clarifier/filter to reduce dissolved silica to saturation at the processing temperature.

Residual amounts of dissolved polyaminoethylene (20 ppm, by weight), a powerful ant silica precipitant, in brine was shown by means of bench-scale tests at 194°F (90°C), to improve the efficiency of the clarification process where the additive appears to function as a flocculant (See Ref. 8.13-9).

Incubation Tests - Brine incubation tests were carried out under anerobic and isothermal conditions to establish the potential for post processing formation of new suspended solids. Three types of samples were evaluated; clarifier influent, clarifier effluent and gravity filter effluent. Samples were collected in an insulated container and then transferred to 50 ml bottles for incubation at 187 - 194°F (86-90°C). Following incubation for periods ranging from 15 minutes to 48 hours, samples were filtered through 1.0 m Nucleopore membrane filters. The filtrate was stabilized with 1% HCl and then analyzed for total dissolved silica by atomic absorption. Suspended solids concentration was obtained by noting the weight change of the membrane filters. Composition of suspended solids was obtained by subsequent analysis of the filtered solids. Experimental data are summarized in Table 8.13-1.

Polymer Experiments

The effect of 20 ppm (by weight) of PAE·HCl polymer on dissolved silica in clarifier influent was established by incubation tests at 194°F (90°C). A jar testing apparatus was used to study the effect of 20 ppm PAE·HCl polymer on clarifier performance. Brine samples containing the polymer, while maintained at 187-194°F (86-90°C), were mixed at a constant speed of 100 RPM in the presence of 10 volume percent sludge obtained from the clarifier. Aliquots of the mixture were then removed, over a time interval ranging from five minutes to one hour, for subsequent analysis of total dissolved silica by the atomic absorption method described earlier. Experimental data are summarized in Tables 8.13-2 and 8.13-3.

Membrane Filter and Core Tests - All membrane filter tests were performed with 0.4, 1.0 or 8.0 micron pore size Nucleopore membrane filters on as received brine effluent from the gravity filtration system. Additional tests using 0.4 and 8.0 micron membrane filters were also performed with an 1.0 micron pore size Cuno cartridge filter inserted in the sampling line upstream of the membrane filters. All membrane filter tests were carried out at constant differential pressure. The 0.4 and 1.0 micron membrane filter were operated at 50 psi differential pressure and the 8 micron membrane filter tests were run at 10 psi differential pressure. The duration of all filter tests was one-half hour. Membrane filter test results are summarized in Tables 8.13-4 through 8.13-8.

Table 8.13-1 Results of Incubation Tests (August 1, 1979)

Time (Hrs)	CONCENTRATION DISSOLVED SILICA (PPM-WT)				CONCENTRATION SUSPENDED SOLIDS (PPM-WT)		
	Clarifier		Gravity Filter (86-88°C)		Clarifier		Gravity Filter (86-88°C)
	Influent (90°C)	Effluent (86-88°C)			Influent (90°C)	Effluent (86-88°C)	
0	342	202	202		193	80	5.6
0.5	247	200	202		223	81	5.5
1	200	200	200		245	81	5.4
2	200	198	200		283	80	7.8
4	200	198	198		281	82	12.6
8	180	198	198		314	82	19.8
24	157	198	198		346	74	23.3
48	153	198					

Table 8.13-2 Effect of 20 PPM (wt) PAE • HCL Polymer on Precipitation of Dissolved Silica from Clarifier Influent (90°C) (August 2, 1979)

Time (Hrs)	Concentration • Dissolved Silica
0	391
0.5	324
2	234
4	234

Table 8.13-3 Effect of 20 PPM (wt) PAE • HCL Polymer on Sludge Contact Removal of Dissolved Silica from Clarifier Influent (90°C) (August 1, 1979)

Time (Hrs)	Concentration Dissolved Silica (PPM-WT)	
	Raw Clarifier Influent	Polymer-Treated Influent
0	391	391
0.08	247	234
0.17	243	216
0.33	184	168
1.00	165	162

Table 8.13-4 0.4 Micron Membrane Filtration Test Results for Conditioned Brine from Magma Power's Clarifier-Filter System. (August 8, 1979)

<u>TIME</u> <u>(Min)</u>	<u>VOLUME</u> <u>(Litres)</u>	<u>FLOWRATE</u> <u>(L/mins)</u>	<u>TIME</u> <u>(Min)</u>	<u>VOLUME</u> <u>(Litres)</u>	<u>FLOWRATE</u> <u>(L/mins)</u>
0.145	0.2	1.379	15.183	7.2	0.292
0.336	0.4	1.047	15.885	7.4	0.285
0.521	0.6	1.081	16.581	7.6	0.287
0.726	0.8	0.976	17.300	7.8	0.278
0.947	1.0	0.905	18.031	8.0	0.274
1.194	1.2	0.810	18.717	8.2	0.292
1.442	1.4	0.807	19.483	8.4	0.261
1.727	1.6	0.702	20.276	8.6	0.252
2.005	1.8	0.719	21.071	8.8	0.252
2.287	2.0	0.709	21.904	9.0	0.240
2.597	2.2	0.645	22.726	9.2	0.243
2.912	2.4	0.635	23.583	9.4	0.233
3.250	2.6	0.592	24.452	9.6	0.230
3.616	2.8	0.547	25.330	9.9	0.228
3.984	3.0	0.543	26.230	10.0	0.222
4.369	3.2	0.520	27.103	10.2	0.229
4.791	3.4	0.474	28.007	10.4	0.221
5.212	3.6	0.475	28.975	10.6	0.207
5.649	3.8	0.458	29.913	10.8	0.213
6.107	4.0	0.437			
6.547	4.2	0.455			
7.007	4.4	0.435			
7.494	4.6	0.411			
8.001	4.8	0.395			
8.520	5.0	0.385			
9.055	5.2	0.374			
9.634	5.4	0.245			
10.190	5.6	0.360			
10.766	5.8	0.347			
11.348	6.0	0.344			
11.940	6.2	0.338			
12.548	6.4	0.329			
13.195	6.6	0.309			
13.837	6.8	0.312			
14.498	7.0	0.303			

Total Volume = 10.890
Suspended Solids
ppm (by vol) = 10.64
ppm (by wt) = 9.09

Table 8.13-5 1.0 Micron Membrane Filtration Test Results for Conditioned Brine from Magma Power's Clarifier-Filter System (August 8, 1979)

<u>TIME (MIN)</u>	<u>VOLUME (LITRES)</u>	<u>FLOWRATE (L/MIN)</u>	<u>TIME (MIN)</u>	<u>VOLUME (LITRES)</u>	<u>FLOWRATE (L/MIN)</u>
0.132	0.2	1.515	14.395	7.2	0.307
0.268	0.4	1.471	15.057	7.4	0.302
0.424	0.6	1.282	15.736	7.6	0.295
0.601	0.8	1.130	16.428	7.8	0.289
0.802	1.0	0.995	17.124	8.0	0.287
1.020	1.2	0.917	17.783	8.2	0.304
1.249	1.4	0.873	18.501	8.4	0.279
1.507	1.6	0.775	19.245	8.6	0.269
1.772	1.8	0.755	20.008	8.8	0.262
2.060	2.0	0.694	20.772	9.0	0.262
2.330	2.2	0.741	21.541	9.2	0.270
2.642	2.4	0.641	22.321	9.4	0.256
2.971	2.6	0.608	23.082	9.6	0.263
3.305	2.8	0.599	23.898	9.8	0.245
3.665	3.0	0.556	24.772	10.0	0.229
4.051	3.2	0.518	25.527	10.2	0.265
4.439	3.4	0.515	26.399	10.4	0.229
4.854	3.6	0.482	27.262	10.6	0.232
5.282	3.8	0.467	28.138	10.8	0.228
5.727	4.0	0.449	29.071	11.0	0.214
6.172	4.2	0.449	30.002	11.2	0.215
6.621	4.4	0.445			
7.083	4.6	0.433			
7.571	4.8	0.410			
8.067	5.0	0.403			
8.567	5.2	0.400			
9.094	5.4	0.380			
9.621	5.6	0.380			
10.191	5.8	0.351			
10.751	6.0	0.357			
11.268	6.2	0.387			
11.882	6.4	0.326			
12.501	6.6	0.323			
13.121	6.8	0.323			
13.743	7.0	0.322			

Total volume: 11.270

Suspended Solids

ppm (by vol) = 6.09

ppm (by wt) = 5.21

Table 8.13-6 Prefiltered 0.4 Micron Membrane Filtration Test Results for Conditioned Brine from Magma Power's Clarification-Filter System (August 8, 1979)

<u>TIME</u> <u>(MIN)</u>	<u>VOLUME</u> <u>(LITRES)</u>	<u>FLOWRATE</u> <u>(L/MINS)</u>	<u>TIME</u> <u>(MINS)</u>	<u>VOLUME</u> <u>(LITRES)</u>	<u>FLOWRATE</u> <u>(L/MINS)</u>
0.153	0.5	3.268	20.766	37	1.290
0.670	2.0	2.901	21.595	38	1.206
4.002	3.0	3.012	22.399	39	1.244
1.353	4.	2.849	23.248	40	1.178
1.678	5	3.077	24.076	41	1.208
2.139	6	2.170	24.948	42	1.147
2.545	7	2.463	26.681	44	1.154
2.973	8	2.337	27.500	45	1.221
3.387	9	2.416	28.465	46	1.036
3.828	10	2.268	29.353	47	1.126
4.265	11	2.288	30.281	48.4	1.509
4.721	12	2.193			
5.185	13	2.155			
5.662	14	2.096			
6.142	15	2.083			
6.650	16	1.969			
7.165	17	1.942			
7.712	18	1.828			
8.264	19	1.812			
8.843	20	1.727			
9.443	21	1.667			
9.922	22	2.088			
10.664	23	1.348			
11.341	24	1.477			
11.959	25	1.618			
12.656	26	1.435			
13.328	27	1.488			
14.038	28	1.409			
14.733	29	1.439			
15.461	30	1.374			
16.172	31	1.407			
16.924	32	1.330			
17.655	33	1.368			
18.427	34	1.295			
19.191	35	1.309			
19.991	36	1.250			

Total volume = 48.900

Suspended Solids

ppm (by vol) = 0.035

ppm (by wt) = 0.030

Table 8.13-7 8 Micron Membrane Filtration Test Results for Conditioned Brine from Magma Power's Clarifier-Filter System (August 8, 1979)

<u>TIME</u> <u>(MIN)</u>	<u>CUMULATIVE VOLUME</u> <u>(LITRES)</u>	<u>FLOWRATE</u> <u>(LITRES/MIN)</u>
0.200	0.2	1.000
0.315	0.4	1.739
0.558	1.0	2.469
0.806	1.5	2.016
1.245	2.0	1.139
2.258	2.5	0.494
2.622	2.6	0.275
3.365	2.8	0.269
4.193	3.0	0.242
5.224	3.2	0.194
6.364	3.4	0.175
7.441	3.6	0.186
8.792	3.8	0.148
10.150	4.0	0.147
11.463	4.2	0.152
12.933	4.4	0.136
14.411	4.6	0.135
15.870	4.8	0.137
17.525	5.0	0.121
19.275	5.2	0.114
21.065	5.4	0.112
22.875	5.6	0.111
24.750	5.8	0.107
26.860	6.0	0.095
28.600	6.2	0.115
30.400	6.4	0.111

Total volume: 6.420

Suspended Solids

ppm (by vol) = 9.4

ppm (by wt) = 8.03

p = 1.17 g/cc

Table 8.13-8 Prefiltered 8 Micron Membrane Filtration Test Results for Conditioned Brine from Magma Power's Clarifier-Filter System (August 8, 1979)

Total volume = 78.170

Suspended solids

ppm (by vol) = 0.01

ppm (by wt) = 0.009

<u>TIME</u> <u>(MIN)</u>	<u>VOLUME</u> <u>(LITRES)</u>	<u>FLOWRATE</u> <u>(L/MINS)</u>	<u>TIME</u> <u>(MIN)</u>	<u>VOLUME</u> <u>(LITRES)</u>	<u>FLOWRATE</u> <u>(L/MINS)</u>
1.500	6	4.000	13.289	42	2.404
1.720	7	4.546	13.731	43	2.262
1.931	8	4.739	14.169	44	2.283
2.149	9	4.587	14.603	45	2.304
2.360	10	4.739	15.030	46	2.342
2.579	11	4.566	15.478	47	2.232
2.809	12	4.348	15.922	48	2.252
3.027	13	4.587	16.373	49	2.217
3.281	14	3.937	16.810	50	2.288
3.517	15	4.237	17.269	51	2.179
3.772	16	3.922	17.711	52	2.262
4.037	17	3.774	18.177	53	2.146
4.307	18	3.704	18.620	54	2.257
4.593	19	3.497	19.092	55	2.119
4.900	20	3.257	19.540	56	2.232
5.204	21	3.290	20.008	57	2.137
5.516	22	3.205	20.458	58	2.222
5.847	23	3.021	20.927	51	2.132
6.179	24	3.012	21.376	60	2.227
6.595	25	2.404	21.854	61	2.092
6.868	26	3.663	22.301	62	2.237
7.239	27	2.695	22.777	63	2.101
7.612	28	2.681	23.234	64	2.188
7.986	29	2.674	23.714	65	2.083
8.363	30	2.653	24.178	66	2.155
8.760	31	2.519	24.679	67	1.996
9.154	32	2.538	25.134	68	2.198
9.552	33	2.513	25.626	69	2.033
9.953	34	2.494	26.101	70	2.105
10.365	35	2.427	26.594	71	2.028
10.774	36	2.445	27.070	72	2.101
11.188	37	2.416	27.554	73	2.066
11.597	38	2.445	28.026	74	2.119
12.024	39	2.342	28.521	75	2.020
12.441	40	2.398	29.007	76	2.058
12.873	41	2.315	29.508	77	1.996
			29.994	78	2.058

For the core test, a one-inch (OD) diameter by four-inch long right circular cylinder of Kayenta sandstone was exposed to brine at 214°F (101°C) and 20 psi differential pressure. Kayenta sandstone is a reasonably good analog of typical upper reservoir sands. The permeability to brine and porosity of the core were 1050 md and 20 percent, respectively. A confining pressure of 500 psi was applied to the core via a heated 212°F (100°C) oil bath. The first 1500 pore volumes (1PV = 10.3 ml) of flow through the core was prefiltered with a 1 micron pore size Cuno cartridge filter. The remainder of the flow to the core was not prefiltered. The core data are summarized in Table 8.13-9.

In general, our automated membrane filter and core test apparatus control system functioned exceedingly well. All system parameters were maintained within ± 2 percent of their set points.

Incubation Test Results -- As shown in Figure 8.13-1, clarifier influent is chemically unstable and appreciable amounts of silica precipitate over a period of 48 hours. Quasi-equilibrium solubility of dissolved silica is 153 ppm (by weight). Although the influent temperature was 214°F (101°C), we completed the incubation test at 194°F (90°C) to avoid the need for more complex autoclave-type experimental apparatus. Since the solubility of silica increases with increasing temperature, it would be desirable to correct the 194°F (90°C) solubility data to yield the actual silica solubility at 214°F (101°C). A complication arises, however, because the solubility of silica is also inversely proportional to brine salinity. We attempted to convert the silica solubility value measured at 194°F (90°C) to the corresponding value at 214°F (101°C) using data provided by Harrar (Ref. Nos. 8.13-8 through 8.13-10) and methods presented in Section 8.13.4.3. Using these procedures, we estimated silica solubility in brine with 4.28 M chloride to be 176 ± 5 ppm at 214°F (101°C).

The effect of the clarification process on dissolved silica and on the chemical stability of the effluent is shown in Figure 8.13-2. A quasi-equilibrium for dissolved silica has been established at 198 ppm. Suspended solids concentration has also been stabilized at between 70-80 ppm, a value equivalent to the nominal concentration of total particulates in the clarifier overflow. We conclude, based on our previous assessment of silica solubility in clarifier influent, that the clarifier effluent remains slightly supersaturated in silica. The apparent stability of the effluent is an artifact resulting from oxygenation of brine caused by recirculation of 50-60 percent of the clarifier overflow and precipitation of ferric iron.

An assessment of the gravity filter effluent, shown in Figure 8.13-3, indicates that dissolved silica is

Table 8.13-9 Kayenta Sandstone Core Test Results

ITEM	MINS	MLITRES	PORE VOL	ML/MIN	DARCIES
31	320	22790	2206.2	38.0	532.0
32	330	23140	2240.1	35.0	490.0
33	340	23470	2272.0	33.0	462.0
34	350	23770	2301.1	30.0	420.0
35	360	24040	2327.2	27.0	378.0
36	370	24290	2351.4	25.0	350.0
37	380	24520	2373.7	23.0	322.0
38	390	24730	2394.0	21.0	294.0
39	400	24930	2413.4	20.0	280.0
40	410	25120	2431.8	19.0	266.0
41	420	25300	2449.2	18.0	252.0
42	430	25480	2466.6	18.0	252.0
43	440	25640	2482.1	16.0	224.0
44	450	25800	2497.6	16.0	224.0
45	460	25940	2511.1	14.0	196.0
46	470	26080	2524.7	14.0	196.0
47	480	26220	2538.2	14.0	196.0
48	490	26350	2550.8	13.0	182.0
49	500	26480	2563.4	13.0	182.0
50	510	26600	2575.0	12.0	168.0
51	520	26720	2586.6	12.0	168.0
52	530	26840	2598.3	12.0	168.0
53	540	26960	2609.9	12.0	168.0
54	550	27080	2621.5	12.0	168.0
55	560	27200	2633.1	12.0	168.0
56	570	27270	2639.9	7.0	98.0
57	580	27380	2650.5	11.0	154.0
58	590	27800	2698.9	50.0	700.0
59	600	28160	2726.0	28.0	392.0
60	610	28470	2756.1	31.0	434.0
61	620	28750	2783.2	28.0	392.0

Table 8.13-9 Kayenta Sandstone Core Test Results (Continued)

ITEM	MINS	MLITRES	PORE VOLS	ML/MIN	DARCIES
1	10	680	65.0	68.0	952.0
2	20	1420	137.5	74.0	1036.0
3	30	2180	211.0	76.0	1064.0
4	40	2930	283.6	75.0	1050.0
5	50	3670	355.3	74.0	1036.0
6	60	4420	427.9	75.0	1050.0
7	70	5170	500.5	75.0	1050.0
8	80	5920	573.1	75.0	1050.0
9	90	6700	648.6	78.0	1092.0
10	100	7450	721.2	75.0	1050.0
11	110	8210	794.8	76.0	1064.0
12	120	8975	868.8	76.5	1071.0
13	130	9720	941.0	74.5	1043.0
14	140	10510	1017.4	79.0	1106.0
15	149	11200	1084.2	76.7	1074.0
16	159	11960	1157.0	76.0	1064.0
17	170	12820	1241.1	78.2	1095.0
18	180	13580	1314.6	76.0	1064.0
19	190	14340	1388.2	76.0	1064.0
20	200	15080	1459.8	74.0	1036.0
21	220	17480	1692.2	69.0	966.0
22	230	18130	1755.1	65.0	910.0
23	240	18740	1814.1	61.0	854.0
24	250	19370	1875.1	63.0	882.0
25	260	19960	1932.2	59.0	826.0
26	270	20580	1992.3	62.0	868.0
27	280	21100	2042.6	52.0	728.0
28	290	21600	2091.0	50.0	700.0
29	300	22000	2129.7	40.0	560.0
30	310	22410	2169.4	41.0	574.0
31	320	22790	2206.2	38.0	532.0

Table 8.13-9 Kayenta Sandstone Core Test Results (Continued)

ITEM	MINS	MLITRES	PORE VOLS	ML/MIN	DARCIES
61	620	28750	2783.2	28.0	392.0
62	625	28860	2793.8	22.0	308.0
63	635	29070	2814.1	21.0	294.0
64	645	29220	2828.7	15.0	210.0
65	655	29400	2846.1	18.0	252.0
66	665	29610	2866.4	21.0	294.0
67	675	29750	2880.0	14.0	196.0
68	685	29890	2893.5	14.0	196.0
69	695	30080	2911.9	19.0	266.0
70	705	30240	2927.4	16.0	224.0
71	715	30370	2940.0	13.0	182.0
72	725	30480	2950.6	11.0	154.0
73	735	30560	2958.4	8.0	112.0
74	765	30755	2977.3	6.5	91.0
75	795	30925	2993.7	5.7	79.8
76	825	31095	3010.2	5.7	79.8
77	855	31335	3033.4	8.0	112.0
78	885	31745	3073.1	13.7	191.8
79	915	31990	3096.8	8.2	114.8
80	945	32100	3107.5	3.7	51.8
81	975	32210	3118.1	3.7	51.8
82	1005	32310	3127.8	3.3	46.2
83	1035	32410	3137.5	3.3	46.2
84	1070	34500	3339.8	59.7	835.8
85	1100	34595	3349.0	3.2	44.8
86	1130	34755	3364.5	5.3	74.2
87	1160	34855	3374.2	3.3	46.2
88	1190	34935	3381.9	2.7	37.8
89	1230	35010	3389.2	1.9	26.6

Figure 8.13-1 Clarifier Influent Incubation Test Results (90°C) August 1, 1967

Figure 8.13-2 Clarifier Effluent Incubation Test Results (86-88°C) August 1, 1979

Figure 8.13-3 Gravity Filter Effluent Incubation Test Results (86-88°C) August 1, 1979

still slightly supersaturated (198 ppm). In addition, a new precipitate, consisting primarily of acid soluble iron oxides, forms over a 24-hour period. We were able to detect precipitation of iron because the bulk of the silica-rich particulates were removed by the gravity-filters. Since the brine was weakly acidic, additional precipitation of silica did not contribute significant amounts of suspended solids during the 24-hour incubation period. However, additional silica would eventually precipitate from solution.

Polymer Experiments - A considerable effort has been devoted to an assessment of potential silica scale inhibitors by LLL geothermal project personnel. One concern relative to the use of silica-inhibitors involves the potential for interference with the subsequent brine clarification process. We have already seen how a potent silica antiscalant like hydrochloric acid (in this case produced indirectly by oxidation of ferrous iron) can interfere with the clarification process. We therefore selected the most potent organic silica antiscalant compound identified to date for evaluation of its effect on sludge-contact removal of silica. Silica precipitation from clarifier influent (at 194°F 90°C) treated with 20 ppm of the hydrochloride salt of polyaminoethylene (PAE·HCl) is significantly retarded (Figure 8.13-4). Results of our bench-scale evaluation of sludge-contact destabilization of dissolved silica 194°F (90°C) in clarifier influent are summarized in Figure 8.13-5. Sludge-contact reduces dissolved silica in brine to near equilibrium in one hour while silica in untreated brine requires about 24 hours to reach the same level.

The effect of 20 ppm of the polymer PAE·HCl on the sludge-contact destabilization of silica is summarized in Figure 8.13-6. Silica in polymer-treated brine is more rapidly removed relative to the nominal rate of silica removal in raw brine contacted with sludge. The accelerating rate of silica precipitation in polymer-treated brine probably results from flocculation of "large" silica particulates by residual dissolved polymer. Thus, one can conclude, at least in the case of PAE·HCl, that polymer treatment of brine for scale control purposes also has the potential for improving the efficiency of the subsequent clarification process.

Brine Injectability Tests - A modified version of a method described by Barkman and Davidson for assessing fluid injectability, based on membrane filtration or core data, was employed to evaluate the injectability of processed effluent (Ref. Nos. 8.13-2 and 8.13-3). In the Barkman and Davidson method, 0.45 micron pore size membrane filters or core samples are exposed to fluid at constant differential pressure. The hydraulic properties of the surface or internal cake formed by deposition of suspended solids or scaling of the porous structure under test are measured and then used

Figure 8.13-4 Effect of Polymer on Stability of Clarifier Influent (85-90°C) August 1-2, 1979

Figure 8.13-5 Sludge Contact Destabilization of Silica in Clarifier Influent (85-90°C) August 1-2, 1979

Figure 8.13-6 Effect of Polymer on Sludge Contact Destabilization of Silica (85-90°C) August 1-2, 1979

to estimate fluid injectability. Analytic models are presented for use in calculating an injection well half-life for various assumed impairment mechanisms. The half-life is defined as the time required for the injection rate to fall to one-half of its initial rate at constant pressure. The most useful impairment models for this geothermal application are wellbore narrowing, which accounts for deposition of solids on the sandface in the injection interval, and invasion which accounts for migration of suspended solids into the injection formation to distances greater than five wellbore radii from the injection well.

In the case of a geothermal reservoir with high porosity (greater than or equal to 20%) and primary and secondary permeability, it is obvious that a 0.45 micron membrane filter cannot be used as a realistic analog of an injection interval. We employed a method described by Champlin et al. (See Section 8.13.4.3) to estimate the average pore diameter of a porous matrix with 20 percent porosity and 500 md permeability (See Ref. 8.13-11). We then selected 8.0 micron membrane filters as conservative analogs of the injection interval. However, additional tests were run with 0.4 micron membrane filters in order to produce comparative data and to obtain data on total suspended solids in the gravity filter effluent. The assumptions used to calculate injection well half-lives are summarized in Table 8.13-10. The methods used to calculate injection well half-lives, based on membrane filtration and core data are summarized in Section 8.13.4.3.1.

Table 8.13-10

Basis for Half-life Calculations

Density filter cake.....	2.0 g/cc
Density brine.....	1.17 g/cc
Density filter cake/density brine.....	1.71
X-sectional area of membrane filter.....	9.62 cm ²
X-sectional area of core.....	5.07 cm ²
Radius well.....	0.325 ft.
Radius core.....	0.0417 ft.
Brine viscosity.....	0.5 cp
Injection interval.....	400 ft.
Injection rate.....	41,143 BLD
Core flow rate.....	0.679 BLD
Formation permeability.....	500 MD
Core permeability.....	1050 MD

Membrane Filtration Test Results - In general, the quality of effluent produced by the large gravity filtration system was poor. It was not possible to pass more than about 10 litres of brine through 0.4, 1.0 or 8.0 micron membrane filters during a 30 minute test interval (Figures 8.13-7 and 8.13-8). The 0.4 and 1.0 micron membrane

BRINE DIRECTLY FROM MAGMA FILTERS

0.4 MICRON: ---
1.0 MICRON: -O-

PREFILTERED BRINE FROM MAGMA FILTERS

0.4 MICRON: -**

Figure 8.13-7 Membrane Filtration Tests of Conditioned Brine Magma Power Clarifier-Filtration System August 8, 1979

Figure 8.13-8 8 Micron Membrane Filtration Test Results for Conditioned Brine from Magma Power's Clarifier-Filter System (August 8, 1979)

filters performed in essentially identical fashion, but a significantly smaller volume was passed through the 8.0 micron. The use of a 1 micron pore size cartridge filter upstream of the membrane filters substantially improved brine quality. Suspended solids data and half-life calculations derived from the membrane filter tests are summarized in Table 8.13-11.

The quality of brine produced by the gravity filters is poor because of a relatively high concentration of suspended particulates in the filter effluent (5-10 ppm) and a tendency for precipitation of iron from the conditioned brine. The estimated half-life of a typical injection well receiving conditioned brine at a rate of 41,143 BD based on the 8 micron membrane filtration test, is about two months. The use of a cartridge prefilter improves the 8 micron based half-life estimate by an order of magnitude (2 years). If we assume that the fine particulates passing through the cartridge filter would invade the injection zone to a distance of 10 feet from the wellbore, the half-life estimate increases by another order of magnitude to more than 80 years. As noted earlier, the poor performance of the brine conditioning system is a result of inadvertent oxygenation of the brine. If the conditioning system were operating at its design optimum, the injectability of the brine would be equivalent to the effluent produced by our small 1 micron pore size cartridge filter.

Core Test Results - The 8 micron membrane filter test data suggested that effluent from the gravity filters would impair a core sample by deposition of suspended solids and precipitation of iron and silica. We anticipated additional silica precipitation would occur when the weakly acidic silica supersaturated effluent was partially neutralized by reaction with carbonate-rich minerals in the core sample. The core was, therefore, initially fed 1 micron cartridge prefiltered brine. As shown in Figure 8.13-9, core permeability remains constant for the first 1550 litres of throughput. Core permeability then began to rapidly decline. The cartridge prefilter was bypassed after about 2600 pore volumes had been passed. At that time, the system was shut-in for less than an hour while the gravity filters were backwashed. When flow resumed, we observed a partial recovery of core permeability. However, permeability rapidly declined. We observed a similar partial recovery of permeability after the core had been shut-in, (at about 3200 pore volumes) for another gravity filter backwashing cycle. Permeability again declined rapidly with resumption of flow. The reason for the apparent recovery of permeability after gravity filter backwashing cycles is not known. Possibly, the quality of filtered brine substantially improves immediately following a backwash cycle.

Table 8.13-11 Results of Membrane Filtration and Core Tests of Gravity Filter Effluent

Filter Size (m)	1 μ m Cuno cartridge prefilter	ΔP (PSI)	Suspended solids (mg/l)	Slope ¹ (L/min)	Intercept (L)	W/Kc (ppm/Md)	Kc (Md)	F (yrs)	$G_{1/2}$	$T_{1/2}$ (Yrs)
0.4	no	50	9.09	2.275	-1.636	24.963	0.364	0.274	0.0161	0.004
1.0	no	50	5.21	2.394	-1.902	22.543	0.231	0.478	0.0102	0.005
0.04	yes	50	0.03	11.907	-17.408	0.911	0.033	82.97	0.0015	0.12
8.0	no	10	8.03	1.033	0.673	24.214	0.332	0.310	0.602	0.19
8.0	yes	10	0.10	21.725	-41.008	0.055	0.182	248.90 248.90	0.0081 0.330	2.01 82.1 ²
Kayenta Sandstone core	yes	20	0.03 ³	0.718	10.590	27.816 0.073	0.001 0.410	82.97 82.97	0.0020 0.743	0.17 ⁴ 61.7 ⁵

1 Linear regression "goodness of fit" R^2 factor 1.00 for all runs.

2 Assumes 10 foot invasion radius.

3 Assumed concentration of suspended solids.

4 Half-life based on first 2500 pore volumes through core.

5 Half-life based on first 1500 pore volumes through core.

Figure 8.13-9 Permeability of Kayenta Sandstone to Conditioned Brine from the Magma Power Clarifier-Filtration System

The core test results are summarized in Table 8.13-11. A pH change was observed across the core. Influent pH was usually about 5.0. The core effluent pH increased to 5.2 - 5.3. For the purposes of half-life calculations, a suspended solids concentration of 0.03 ppm was assumed for the influent. This value for suspended solids was based on results of our 0.4 micron membrane filtration test of pre-filtered brine. The calculated half-life was about two months. A second calculation based on the first 1500 pore volumes of core throughput yield a half-life in excess of 60 years.

Post-mortems on the core established that impairment resulted from deposition of iron- and silica-rich solids on the sandface. The deposits did not penetrate more than an inch into the core. As shown in Figure 8.13-10, no deposits were present on the perforated disc placed on the inlet surface of the core as an analog of a completion liner.

Makeup Water Evaluation

Direct Injection of Ambient Temperature Makeup Water - Chemical analysis of Salton Sea, New River and Alamo River water were determined and are provided in Table 8.13-12. In general, river waters has about 8 times less dissolved sulfate than Salton Sea water. Use of river waters for injection makeup will result in a significant reduction in sulfate precipitation. However, the high particulate loading in river waters relative to Salton Sea water can significantly increase the sludge processing requirements on a clarifier processing system. Furthermore, seasonal changes in flow rate and physical and chemical properties of New and Alamo River waters would also impact processing requirements.

We first evaluated Salton Sea water as a potential source of injection makeup. Sea water samples obtained off Obsidian Butte (Table 8.13-12) were held at temperatures between 77 and 194°F (25 and 90°C) for periods of 1 to 7 days in nitrogen pressurized and sealed glass ampoules. The Sea water was settled overnight and then decanted prior to use in heating experiments. Concentrations of suspended solids were obtained as a function of temperature and incubation time. Relative ease of difficulty of filtration through membrane filters with pore sizes ranging from 0.4 to 5.0 micron was also observed.

Results of the sea water heating experiment are summarized in Table 8.13-13. Samples heated for 24 hours were all difficult to filter regardless of filter pore size (0.4 to 5.0 micron) or solution temperature. Filters plugged after passage of 200 ml or less of solution. Chemical interaction effects between solutions and filters were not responsible for filtration difficulties because filtrates

The core was plugged by a deposit of iron and silica-rich solids that formed on its upper surface. The solids did not form scale on the steel perforated disc placed on the upper surface of the core. The disc was used as an analog of a downhole injection well completion liner.

Figure 8.13-10 Core Sample Exposed to Conditioned Brine Produced by the 10 MW Clarifier-Filtration System

Table 8.13-12

Chemical Analysis of Waters

IONS	New River	Alamo River	Salton Sea*	Salton Sea*	Salton Sea*
Na	880	440	10,000	10,400	11,300
K	39	11	190	302	323
Ca	240	190	940	902	980
Mg	130	97	1,100	1,073	1,147
SO ₄	1,050	840	8,300	8,025	9,016
CO ₃	1.5	1.5	1.3	10	2
HCO ₃	269	180	235	160	187
Cl	1,200	540	14,000	12,719	13,861
Ba				0.1	
0.03					
TDS	4,000	2,400	37,000	35,860	38,332

*Sampled between July and November, 1978.

Table 8.13-13

Salton Sea Water Heating Experimental Results

Membrane Filter Pore Site (micrometer)	Incubation Temperature (C)	Incubation Duration (Days)	Particulate Concentration (PPM-MG/KG)	* Filtration Characteristics
0.4	25	1	6.5	Difficult
0.4	50	1	11.3	Difficult
0.4	75	1	4.5	Difficult
0.4	90	1	7.7	Difficult
1.0	25	1	12.3	Difficult
1.0	25	1	15.8	Difficult
1.0	90	7	19.0	Easy
5.0	25	1	4.5	Difficult

* Difficult = Filter Plugging after Passage of less than or equal to a 200 ML of Solution.

were highly filterable. One sample incubated at 194°F (90°C) for 7 days was easy to filter. These results indicate that fine particulates in Salton Sea water readily plug even relatively coarse 5.0 micron pore size filters. Prolonged incubation at 194°F (90°C) improves filtration properties of sea water either by thermal decomposition of organic particulates or changes in particulate particle size distributions. Ambient temperature Salton Sea water contains 10 ± 5 ppm suspended particulates. Incubation of Salton Sea water at 194°F (90°C) for 24 hours does not significantly alter particulate concentration. However, incubation at 194°F (90°C) for 7 days does increase particulates slightly to 19 ppm.

Computer calculations assuming Salton Sea water of 'typical' composition are in excellent agreement with results of the reheating experiment (See Ref. 8.13-12 and 8.13-13). The maximum concentration of particulates after seven days incubation at 194°F (90°C) was 19 ppm. The computer code predicted 30 to 55 ppm total carbonate solids varying in composition between calcite (CaCO_3) and dolomite ($\text{CaMg}(\text{CO}_3)_2$). If Salton Sea water were prefiltered at ambient temperature 77-95°F (25-35°C) prior to reheating, no sulfate solids would precipitate until the brine was reheated to 212°F (100°C).

Filtration properties of Salton Sea water, New River, and Alamo River are compared in Table 8.13-14. All of the waters have extremely poor filtration properties due to suspended particulates. In addition, the high pH and dissolved carbonate and sulfate content (Table 8.13-1) of these waters suggests a significant potential exists for post injection precipitation of sulfates and carbonates as makeup waters reheat or mix with typical geothermal brine. We concluded that direct injection of makeup waters is not feasible.

Table 8.13-14

Filtration Properties of Waters

Makeup Water	Suspended Solids 1.0 micro-meter (ppm)	pH	Filtration Properties (1.0 Nucleopore Membrane Filter Used)
Salton Sea	25.69	8.19	Very poor (filter plugged after 144 gm H_2O)
New River	132.00	8.40	Poor (Filter plugged after 200 gm H_2O)
Alamo River	557.2	8.25	Very poor (Filter plugged after 200 gm H_2O)

* 1.0 micro-meter filtration simulates efficiency attainable by typical prejection processing systems consisting of reaction clarification and granular media filtration.

Mixing Experiments - Incubation tests were carried out to establish nominal growth rates of suspended particulates in 1:4 mixtures (by weight) of 1 micron prefiltered makeup water (Salton Sea, New River and Alamo River) and unfiltered brine effluent from the LLL test station (Maggamax No. 1 well). Incubation was done at 194°F (90°C) for periods ranging from 15 minutes to 30 days in nitrogen-pressurized and sealed glass ampoules.

Our preliminary experiments utilizing 1:4 mixtures of Salton Sea water and brine are summarized in Table 8.13-15. Samples were incubated at 194°F (90°C) for 24 hours and then filtered with 1.0 μ m membrane filters. All solutions were easy to filter. Normally, 'spent' brine from the LLL test station (Maggamax No. 1 brine) produces between 300 and 350 ppm suspended solids after 1/2 hour incubation at 194°F (90°C). Addition of Salton Sea water to brine increased suspended solids by a factor of at least two. In the absence of excess dissolved sulfate, carbonate and oxygen, the diluting effect of a volume of distilled water significantly retards similar particulate precipitation.

Table 8.13-15

Salton Sea Water - Brine Mixture Reheating
Experimental Results at 194°F (90°C)

Solution	*Incubation Duration (Hrs)	Particulate Concentration (Ppm/Mg/Kg)
Brine	0.5	300-350
Brine Plus Distilled Water (4:1 Mixture)	24	230
Brine Plus Salton Sea Water (4:1 Mixture)	24	612

* Particulate concentration reaches Quasi-Equilibrium after 1/2 hour at 194°F (90°C).

Additional experimental results for incubation of 1:4 mixtures of Salton Sea water-brine and river water-brine are indicated in Table 8.13-16. It is important to note that mixtures of River water and brine attain equilibrium most rapidly. After 1 month, such mixtures produce about the same amount of solids as brine alone. In contrast, 1:4 mixtures of Salton Sea water and brine are still exhibiting large degrees of precipitation after 1 month and at least

three times as many solids (primarily sulfates plus silica) were formed in contrast to River water - brine mixtures. According to the chemical analyses in Table 8.13-16, silica reaches quasi-equilibrium conditions after 4 hours for Salton Sea brine mixtures and after 8 hours for both River water-brine mixtures. Sulfate, however, has not reached equilibrium in either case and is still coming out of solution at 1 months time.

Table 8.13-16

Chemical Analysis Salton Sea Mixtures

<u>Time</u>	<u>1:4 Salton Sea - Brine*</u>			<u>1:4 New River - Brine*</u>		
	SiO ₂	SO ₂	Suspended Solids	SiO ₂	SO ₄	Suspended Solids
15 min.	326	1482	310	352	296	180
4 hrs.	230	1328	464	286	209	258
8 hrs.	230	1289	510	234	276	234

*Concentrations are ppm by wt.

From these experimental results, it can be concluded that use of Salton Sea water for injection makeup will significantly increase sludge dewatering and disposal requirements. Facilities for removal of at least three times the amount of particulate matter relative to brine alone will be required as part of the pre-injection processing system.

Makeup Water Processing Requirement - A series of bench-scale experiments were run to determine the effectiveness of sludge contact on precipitation rates of particulates generated in 1:4 mixtures of Salton Sea water and geothermal brine. A jar testing apparatus was used for these experiments: samples were mixed at a constant speed of 100 RPM at 176-185°F (78-85°C) for times varying from 5 minutes to 2 hours. Turbidity, sulfate and silica measurements were made on the 1.0 micron prefiltered supernatant after allowing approximately two minutes settling time.

Results from the first two experimental runs (Table 8.13-17) show that solutions approached quasi-equilibrium within the first 10 minutes. Turbidity also showed a rapid decrease during the first 5 minute interval as suspended particulates settled. On the basis of these experimental results, we concluded that reaction clarification is a viable and efficient means of stabilizing mixtures of makeup water and brine.

Table 8.13-17

Effect of Sludge Contact on Dissolved Silica and
Sulfate in a 1:4 Mixture of Salton Sea Water-
Geothermal Brine

Time (Min)	Turbidity (Ntu)		PPM SiO		PPM SO ₄	
	Run 1	Run 2	Run 1	Run 2	Run 1	Run 2
0	70	54	326	332	1482	1482
5	2.0	.8	258	221	927	899
10	1.0	.5	220	196	891	865
20	1.0	.4	216	196	891	855
30	1.1	-	203	-	901	-
45	1.0	-	197	-	881	-
60	.80	-	184	-	889	-
120	.55	-	-	-	-	-

Pilot Test Results - Incubation and injectability tests were run on effluents produced by the Imperial Magma Power Company pilot reaction clarifier-granular media preinjection processing system. These tests were performed to establish the isothermal 194°F (90°C) chemical stability and injectability of processed 1:4 mixtures of Salton Sea water and geothermal brine. Incubation test results for times up to 24 hours indicated that processed effluents had achieved a quasi-equilibrium condition. Residual dissolved silica and sulfate concentrations were consistent with results of the bench-scale experiments. Membrane filtration tests (Figure 8.13-11) indicated that processed effluents containing less than 2 ppm suspended solids are potentially injectable. However, results of the core test (Table 8.13-11) indicated that post-injection brine-rock interactions can severely impair injection well performance. The membrane filtration and core test data are provided in Tables 8.13-18, and 8.13-19, respectively.

8.13.4.3 Calculations

Temperature Dependence of Silica Solubility

Data from Harrar et al (Ref. No. 8.13-8) for the temperature dependence of silica solubility in Woolsey No. 1 brine (4.10 M Cl; 1.666 g/cm³) over the interval 122 to 194°F (50 to 90°C) was fit by least squares. The best line through six data points is given by:

$$\text{Dissolved Silica (mg/Kg)} = (1.938)(\text{TC}) - 14.79 \quad (1)$$

The regression coefficient (r^2) was 0.96. Application of equation (1) indicates that an increase in brine temperature

Figure 8.13-11 Barkman and Davidson-Type Filtration Curve for Kayenta Sandstone Showing Invasion

Table 8.13-18 Results of Processed Makeup Water 0.45 μ m Membrane Filtration Test

Time (Min)	Cumulative Volume (Litre)	Flowrate (L/Min)
12	6.417	0.535
20	9.149	0.341
30	12.252	0.310
40	15.498	0.325
50	18.344	0.285

Table 8.13-19 Results of Processed Makeup Water Kayenta Core Test

(Min) Time	Vol (L)	Flowrate (L/min)
5	0.156	0.156
10	0.325	0.034
20	0.548	0.022
30	0.643	0.0095
40	0.704	0.0061
50	0.751	0.0047
60	0.799	0.0048
120	0.981	0.0030
180	1.116	0.0023
240	1.252	0.0023
300	1.373	0.0020
360	1.468	0.0016
420	1.556	0.0015
480	1.650	0.0016
540	1.718	0.0011
600	1.786	0.0011
660	1.840	0.0009
720	1.914	0.0012
780	1.975	0.0010
840	2.022	0.0008
900	2.063	0.0007
960	2.130	0.0011
1020	1.191	0.0010
1080	2.225	0.0006
1140	2.272	0.0008
1200	2.310	0.0008
1260	2.360	0.0007
1320	2.428	0.0006
1380	2.428	0.0006
1440	2.448	0.0003
1500	2.496	0.0008

from 194 - 214°F (90 to 101°C) will cause a corresponding increase in silica solubility from 159.6 to 181 Mg/Kg (12 percent).

Data from Harrar et al (Ref. No. 8.13-10) for the salinity dependence of silica solubility in Magmamax No. 1 and Magmamax No. 2 brine were also fit by least squares. The corresponding relationships between dissolved silica, brine density and brine chloride content at 194°F (90°C) are summarized in equations (2) and (3):

$$\text{Dissolved Silica (mg/Kg)}_{90^{\circ}\text{C}} = (-910.88)(-\text{g/cm}^3) + 1226.62; r^2 = 0.54 \quad (2)$$

$$\text{Dissolved Silica (mg/Kg)}_{90^{\circ}\text{C}} = (-9.97)(\text{Cl-Moles/litre}) + 204.08; r^2 = 0.39 \quad (3)$$

Reservoir Hydraulic Radius Estimates

According to Champlin et al (Ref. No. 8.13-11), the largest diameter particle capable of passing through a given porous medium is about 25 percent smaller than the average pore size given by:

$$M = 4 \left[\frac{\left(\frac{1-\phi}{\phi \times 10^3} \right)^{1/2}}{5K} \right]$$

where M is the mean pore diameter (micro-meter), ϕ is the fractional porosity and K is the permeability (md). We calculated a mean pore diameter, for the injection zone into which GLEF pretreated brine was injected, of 11.3 micro-meter based on a formation porosity and permeability of 20 percent and 500 md, respectively. Using the 25 percent criteria, we selected 8.0 micron membrane filters as conservative analogs of the injection zone.

8.13.4.3.1 Half Life Calculations

Half-Life Calculations - The half-life is computed as the product:

$$T_{1/2} = F \times G_{1/2} \quad \text{Eq. (5)}$$

where F is proportional to the time required to fill one wellbore volume with solids and $G_{1/2}$ is an adjustment factor related to the impairment mechanism. F is independent of the impairment process and is defined as:

$$F_{\text{sec}} = \frac{r_w^2 \cdot h \cdot P_c / P_w}{i_o \cdot W} \quad \text{Eq. (6)}$$

where: r_w = radius of wellbore (m)

h = injection interval length (m)

P_c = density of filter cake (g/cm^3)

P_w = density of water (g/cm^3)

i_o = injection rate (m^3/sec)

w = concentration suspended solids (micro-grams/g)

A more convenient form of equation 6 is:

$$F \text{ yrs} = \frac{1533 \cdot r_w^2 \cdot h \cdot P_c/P_w}{i_o \cdot W} \quad \text{Eq. (7)}$$

where r and h are in feet and i_o is in barrels per day.

The permeability of the filter cake formed by deposition of suspended solids or scaling must be known in order to calculate the $G_{1/2}$ -factor. Filter cake permeability is obtained from a measurement of the water quality ratio. The water quality ratio (W/K_c) is defined as:

$$\frac{W}{K_c} = \frac{1.20 \times 10^5}{S^2} \frac{(P_c/P_w) \cdot A_c^2 \cdot P_t}{(\text{water viscosity (cp)})} \quad \text{Eq. (8)}$$

where:

w = concentration suspended solids (micro-grams/g)

K_c = permeability of filter cake (Md)

P_c = density of filter cake (g/cm^3)

P_w = density of water (g/cm^3)

P_t = Pressure drop across membrane filter or core (Atm)

A_c = area of membrane filter or core exposed to brine (cm^2)

S = slope of linear portion of filtration curve (Ml/min)

S is obtained by regression of the linear portion of the filtration curve plotted in coordinates of cumulative flow (ordinate) vs (time) $^{1/2}$. An example of a typical filtration curve is provided in Figure 8.13-11. The sign of the intercept formed by extrapolation of the linear portion of the filtration curve indicates whether the porous medium under test has been invaded by fine particulates (positive intercept) or whether solids have formed a surface cake (negative intercept).

We calculated $G_{1/2}$ for the case of wellbore narrowing and invasion:

$$\text{wellbore narrowing: } G_{1/2} = 3 \cdot (K_c/K_f) \cdot L_n(r_e/r_w) \quad \text{Eq. (9)}$$

where:

K_f = formation permeability (md)

r_e = radius of effect

r_w = radius of well

$$\text{invasion: } G_{1/2} = 3.2 (K_c/K_f)(r_a/r_w)^2 (\ln(r_e/r_w)) \quad \text{Eq. (10)}$$

where:

ϕ = fractional formation porosity

r_a = invasion radius

We used the following forms of equations 7-10 to evaluate our experimental data:

$$F_{\text{yrs}} = 2.489/W(\mu\text{g/g}) \quad \text{Eq. (11)}$$

$$\frac{W}{K_c} = \frac{2.584 \times 10^6 \cdot \Delta P_t \text{ (PSI)}}{S^2} \quad \text{Eq. (12)}$$

$$\frac{W}{K_c} = \frac{7.170 \times 10^5 \cdot \Delta P_t \text{ (PSI)}}{S^2} \quad \text{Eq. (13)}$$

$$G_{1/2} = 22.13 (K_c/K_f) \quad \text{Eq. (14)}$$

$$G_{1/2} = 906.6 (K_c/K_f) \quad \text{Eq. (15)}$$

8.13.4.4 Comparison of Actual and Expected Results

Injectivity Tests

The injectability of conditioned low temperature 214°F (101°C) effluent produced by a 10 MW equivalent capacity demonstration clarifier/filter system was established. Brine processing was accomplished without the use of chemical aids. However, our bench scale experiments illustrated how certain classes of organic polymers which exhibit anit-silica scaling tendency can also improve the efficiency of the clarification process.

Absolute injectability of the conditioned effluent was poor due to clarifier/filter operational procedures and overall system design which permitted oxygenation of brine during the conditioning process. Air contamination resulted

in post-processing precipitation of iron and partial stabilization of dissolved silica. Core test results suggested that silica would precipitate in the injection formation as a result of brine-rock interactions leading to a slight increase in brine pH. Half-life calculations based on data obtained from membrane filters and a core sample suggested significant injection well impairment could occur within several months assuming effluents are injected into a porous media with primary permeability. The effect of possible fracture flow would increase well life.

Makeup Water Evaluation

Direct injection of makeup waters is not feasible owing to high nominal suspended solids loading. The most likely source of injection makeup is Salton Sea water. Performance data describing the effect of makeup water additions to the influent to a baseline clarifier/filter system were established. The processing system is capable of producing an effluent saturated in dissolved sulfate, carbonate and silica species. However, sludge removal capabilities must be substantially expanded to accommodate the larger-volume of solids (primarily sulfates) produced as a result of 20 percent dilution by makeup water. Membrane filter tests indicated that processed effluent is potentially injectable. However, core test results suggested that post-processing precipitation of silica in the injection interval is possible due to brine-rock interactions which cause a slight increase in brine pH. The pH of influent to the clarification process becomes slightly depressed by addition of oxygen-saturated makeup water and resultant precipitation of ferric iron species.

8.13.5 CONCLUSIONS AND RECOMMENDATIONS

8.13.5.1 Injectivity Tests

The quality of brine effluent produced by a 1600 GPM-capacity demonstration clarifier/filter system was significantly degraded by operational procedures that caused partial oxygenation of the brine. Resulting oxydation of ferrous iron caused a decrease in brine pH and partial stabilization of dissolved silica. The slow formation of flocculant iron-rich precipitates increased the impairment potential of the brine. Our incubation, membrane filtration and core test results suggest that elimination of brine oxygenation would result in production of a highly injectable effluent. The application of organic polymer compounds, such as PAE.HCl, for the purposes of scale inhibition may result in significant improvement in the efficiency of the sludge-contact process for removal of supersaturated silica from brine.

8.13.5.2 Makeup Water Evaluation

Salton Sea water is the best source for injection makeup. Although additional experimental work will be required to more completely assess injectability of Salton Sea water-brine mixtures, our preliminary results indicate that the final effluent pH must not be lower than about 5.6 to avoid post-processing silica precipitation induced by interaction of injected effluents and reservoir matrix materials. It can also be anticipated that premature mass breakthrough of injected effluents, diluted by Salton Sea makeup water additions, to production wells has the potential for significantly worsening scaling problems due to deposition of sulfates. Therefore, injection wells receiving makeup water additions should be located with respect to minimizing potential mass breakthrough problems.

8.13.6 REFERENCES

- 8.13-1 Hasbrouck, R. T., Owen, L. B., and Netherton, R., 1979, An automated system for membrane filtration and core tests: Geothermal Resources Council, Transactions, Vol. 3, pgs. 301-304.
- 8.13-2 Owen, L. B., 1979, Evaluating brine injection for DOE's Strategic Petroleum Reserve Program: Energy and Technology Review, (August), pgs. 1-10.
- 8.13-3 Barkman, J. H. and Davidson, D. H., 1972, Measuring water quality and predicting well impairment: Journ. Petroleum Technology, pgs. 865-872.
- 8.13-4 Owen, L. B., Kasameyer, P. W., Netherton, R., and Thorson, L. D., 1977, Predicting the rate by which suspended solids plug geothermal injection wells: Prog. Third Workshop, Geothermal Reservoir Engineering, Stanford University, pgs. 163-171.
- 8.13-5 Netherton, R. and Owen, L. B., 1978, Apparatus for the field evaluation of geothermal effluent injection: Transactions Geothermal Resources Council, Vol. 2, Section 2, pgs. 487-490.
- 8.13-6 Tewhey, J. D., Chan, M. A., Kasameyer, P. W., and Owen, L. B., 1978, Development of Injection Criteria for Geothermal Resources: Trans., Geothermal Resources Council, Vol. 2, Section 1, pgs. 649-652.
- 8.13-7 Quong, R., Schoepflin, Stout, N. D., Tardiff, G. E., and McLain, F. R., 1978, Processing of Geothermal Brine Effluents for Injection: Trans. Geothermal Resources Council, Vol. 2, pgs. 551-553.
- 8.13-8 Hill, J. H., Harrar, J. E., Otto, C. H., Jr., Deutscher, S. B., Crampton, H. E., Grogan, R. G., and Hendricks, V. H., 1979, Apparatus and techniques for the study of precipitation of solids and silica from hypersaline geothermal brine: Univ. Calif. LLL Rept., UCRL-52799, 9 pgs.
- 8.13-9 Harrar, J. E., Locke, F. E., Otto, C. H., Jr., Lorensen, L. E., Frey, W. P., and Snell, E. O., 1979, On-line tests of organic additives for the inhibition of the precipitation of silica from hypersaline geothermal brine III. Scaling measurements and tests of other methods of brine modification: Univ. Calif., LLL Rept., UCID-18238, 31 pgs.

- 8.13-10 Harrar, J. E., Otto., C. H., Jr., Deutscher, S. B., Ryon, R. W., and Tardiff, G. E., 1979, Studies of brine chemistry, precipitation of solids and scale formation at the Salton Sea Geothermal Field: Univ. Calif., LLL Rept., UCRL-5264), 17 pgs.
- 8.13-11 Champlin, J. D. F., Thomas, R. D., and Brownlow, A. D., 1967, Laboratory testing and evaluation of porous permeable rock for nuclear waste disposal: U.S. Bureau of Mines, Rept. 6926.
- 8.13-12 Wolery, T. J., 1979, Computer simulation of temperature-dependent equilibrium precipitation: Geothermal Resources Council, Transactions, Vol. 3, pgs. 793-796.
- 8.13-13 Raber, E., Owen, L. B., and Harrar, J. E., 1979, Using surface waters for supplementing injection at the Salton Sea Geothermal Field (SSGF), Southern California: Geothermal Resources Council, Transactions, Vol. 3, pgs. 561-564.

8.14 WELL TEST DATA REDUCTION

8.14.1 STATUS

This test has been deleted due to lack of funding.

8.15 SCALE CONTROL AT THE GLEF

Principal Investigators: P. M. Henry (NUS Corporation)

8.15.1 OBJECTIVES

The objective of this test was to quantitatively determine the effectiveness of using scale control additives that are presently available in the market to suppress, control, or retard scale formation in the Niland Geothermal brines. The cost effectiveness of these scale retardation or prevention procedures were defined.

8.15.2 BACKGROUND

The GLEF was entering its third year of operation. The availability of the test facility had been significantly affected by the need to shutdown the plant every 1000 to 1500 hours for removal of accumulated scale from the flash vessels, influent and effluent lines, and from the injection pump. These runs were not continuous. During one run, for example, the GLEF shutdown three times to correct conditions associated with scaling problems, the downtime accounting for about 9% of the total run time of 1373 hours.

One potential method of preventing this downtime was to design a commercial power plant with redundant systems; i.e., 3 separator trains of 50% capacity (2 trains on, 1 train off for cleaning). While there may be merit in designing redundancy in a commercial geothermal power plant to compensate for precipitation of scaling elements, the effectiveness of scale control chemicals should be determined prior to this design effort.

An examination of the vessels and lines after the first two stage flash run revealed a higher scaling rate from the inlet of the second stage to the suction of the injection pump, P-2, than was produced by four stage operation. The first stage flash vessel and its effluent line showed considerably less scale deposition and the physical appearance and chemical constituency of the scale was different than the scale in the second flash vessel and its effluent line. (See Section 8.7, Test No. 7.0: Brine Chemistry). The deposits in the first stage flash vessel were thinner, about 1/8 to 3/8 inch in thickness, and more friable than the deposits in the 2nd stage, where the thicknesses varied from 1 to 2 inches.

The thickness of the deposit at the outlet of the atmospheric flash tank, V-15, was about 3 inches. Thus we have a pattern of increasing scale thickness from the inlet to the outlet of the GLEF. Without scale control additives, the first stage and its drain line could possibly operate for four to six months before cleaning is required.

The brine residence (transit) time in a commercial geothermal power plant would be on the order of ten (10) minutes, similar to the GLEF operation. Thus the GLEF would be the ideal facility for testing the most promising candidate additives after preliminary screening of pre-selected materials.

8.15.3 TEST PROGRAM

To meet the stated objectives, SDG&E contracted with NUS Corporation of Sherman Oaks, California to conduct a program at the GLEF. The NUS report on that program is contained as Appendix C.

8.15.4 CONCLUSIONS

NUS devised a bench test method by which the precipitation rate of silica from geothermal brines can be estimated. A series of tests were conducted using commercially available antiscalants. The results showed that Betz "Polysperse" and Carbowax 14,000 had a tendency to reduce silica precipitation at GLEF operating temperatures. Five drums of Polysperse were purchased for a short trial run at the GLEF, however, due to the need to conduct higher priority tests, the scale inhibitor was not run through the GLEF.

Much of the down time, operating, and maintenance problems experienced at the GLEF were due to scaling in plant components. Similar problems are anticipated for full-sized geothermal power plants at the Salton Sea KGRA. Further investigation into the applicability of chemical additives for scale reduction is warranted.

9.0 SUPPORTING ACTIVITIES

9.1 FEASIBILITY AND RISK STUDY

9.1.1 INTRODUCTION

The primary objective of the feasibility and risk study was to define the most technically feasible and lowest cost near-term energy conversion process for a commercial-scale demonstration power plant at the Salton Sea Known Geothermal Resource Area (KGRA). The study incorporated the GLEF data while operating as a four-stage flash/binary loop. The purpose of the Geothermal Loop Experimental Facility (GLEF) at the Salton Sea KGRA was to obtain data for a commercial power plant. As originally constructed, it utilized the four-stage flash binary energy conversion process. However, the GLEF design was based on certain conditions and assumptions that subsequent data showed to be no longer valid. Therefore, this study was initiated to determine the most appropriate energy conversion process for the demonstration power plant based on current information and to define the future, if any, that GLEF testing needed to obtain critical design information for the type of plant selected.

The study was divided into three phases. Phase I, which is reported herein, was a preliminary assessment. Phase II was to be an updated assessment. It was to be performed following a series of GLEF tests that were to be based on the results of the Phase I study. Phase III was to be a more detailed study that would follow additional GLEF testing based on the Phase II study results, if required.

The Phase I study was jointly performed by Bechtel National, Inc. (Bechtel) and The Ben Holt Company (Holt) for San Diego Gas and Electric Company (SDG&E). Bechtel and Holt were each assigned primary responsibility for different portions of the study. Both were to concur in the other's results. Specific tasks performed by Bechtel included the conceptual designs and costs estimates for the flashed steam energy conversion processes, documentation of the interface parameters, and the research and development recommendations. Tasks performed by Holt included the conceptual designs and cost estimates for the binary energy conversion processes and the risk analyses.

Phases II and III were not initiated due to the limited time available to perform the work and commitment of one of the project participants (Magma) to construct a commercial sized power plant based on current data.

9.1.2 SUMMARY

In order to ensure that the conceptual designs reflected the best data and that the results for the various designs would be comparable, a set of interface and design

parameters were developed for use as the power plant and well field design criteria. Additionally, a standard cost estimating methodology was devised to assure compatibility between the various cost estimates.

The most important design parameters considered were as follows:

- o Net plant output is 50 MW.
- o The plant is located within the Salton Sea KGRA, approximately 2,500 feet west of Gentry Road and 2,000 feet south of Sinclair Road.
- o Steam condensate is used as cooling tower make-up, and injection flow is decreased by this amount.
- o A Stretford unit is provided for removal of H_2S from noncondensable gas discharge.
- o Brine effluent treatment to remove suspended solids from the brine prior to injection or elevated effluent brine temperatures are required to prevent injection well failures.
- o Wellbottom temperature is 500°F (260°C) initially and declines linearly to 482°F (250°C) in 30 years. The process designs are based on 482°F (250°C) brine wellbottom conditions.
- o Total dissolved solids content of the brine is 20 percent, and noncondensable gas content is 0.5% by weight of the total brine flow.
- o Total production flow rate per well is 400,000 lb/hr, declining linearly to 300,000 lb/hr in 30 years. Injection flow rate per well is 600,000 lb/hr and remains constant.
- o The production wells are slant drilled from an island located adjacent to the power plant. Injection wells are slant drilled from an island approximately 3,000 feet from the production well island.
- o Brine scaling rates, scale removal techniques and costs, and materials for use in brine service are based on GLEF or best data available.
- o General operating parameters and costs are based on Geysers or worldwide geothermal plant experience.

Conceptual designs, capital cost estimates, and energy production cost estimates were developed for five

Table 9.1-1

COMPARISON OF FLASHED STEAM AND BINARY PROCESSES

50 MW NET DUAL FLASH ENERGY CONVERSION
SALTON SEA KGRA, NILAND, CALIFORNIA

	Capital Cost ⁽¹⁾ (10 ⁶ \$)		Power Plant	Energy ⁽¹⁾ Production Cost (Mills/kwh)
	Specific Output (Watt hr/lb Brine)	Well Field ⁽²⁾		
Flashed Steam Process				
Unmodified Brine, No Minimum Injection Temperature, with Redundant Flash Vessels	8.90	9.83	38.4	37.6
Unmodified Brine, No Minimum Injection Temperature	8.90	9.83	37.2	44.1
Acidified Brine, No Minimum Injection Temperature	8.90	9.83	38.2	38.5
Unmodified Brine, 300°F Minimum Injection Temperature	8.21	11.00	37.0	46.6
Acidified Brine, 300°F Minimum Injection Temperature	8.21	11.00	39.1	49.3
Binary Process				
Acidified Brine, No Minimum Injection Temperature (Four- Stage Flash)	9.35	9.04	40.35	38.7
Unmodified Brine, No Minimum Injection Temperature (Four- Stage Flash)	9.35	9.04	40.35	38.7
Unmodified Brine, 300°F Minimum Injection Temperature (Two-Stage Flash)	7.65	11.05	38.78	43.7
Acidified Brine, No Minimum Injection Temperature (Liquid/Liquid)	10.54	8.22	43.70	38.7

NOTES: (1) Escalated to first quarter 1982
(2) Cost of wells installed at Year 0

versions of the dual flashed steam energy conversion process and four versions of the binary process. These processes are listed in Table 9.1-1 which compares their performance, capital costs, and energy production costs. Capital costs and energy production costs were escalated to the first quarter of 1982.

The plant capital costs for the binary processes are generally higher than the flashed steam processes. However, since the efficiency of the binary process is somewhat greater, the associated brine requirements and well field capital costs are lower. The result is that busbar energy production costs for comparable versions of the flashed steam and binary processes are the same to within the accuracy of the estimates.

Subsequent to the initial phases of the study, data from acidified brine testing by Lawrence Livermore Laboratories became available. Data showed a lower pH (more acid addition) was required to fully inhibit scaling. In addition, the scale inhibition (assumed 100% effective in study based on early test data) was not completely successful, requiring significant scale removal. These factors would tend to further increase the cost of acidified brine alternatives.

The 300°F (149°C) minimum injection temperature processes were studied as an alternative to using brine settling ponds for solving the brine injection problem. However, the results show that these processes have significantly lower efficiency and higher energy production costs than a process using no minimum injection temperature and including brine settling ponds.

The most cost effective of the binary processes studied is the four-stage flash process with acidified brine. It has an energy production cost of 38.7 mills/kWh. The energy cost for the comparable flashed steam process with acidified brine, 38.5 mills/kWh, is not considered to be significantly different. It should be noted that these costs do not include the increased cost due to factors identified by subsequent LLL tests. An energy production cost of 37.6 mills/kWh, the lowest cost of the processes studied, was estimated for the dual flashed steam process with unmodified brine and three 50 percent capacity flash vessel trains. Since one train is redundant, it can be descaled while the plant is operating at full capacity.

A risk analysis was performed that covers the major uncertainties in the development of a commercial power plant. These risks primarily affect the basic go or no-go decisions. The risks were assessed, and priorities were assigned. The results of this analysis show that brine handling is the most important technical risk. Involved in

this risk are the problems of scale formation, corrosion, and two-phase flow in production wells, injection wells, and plant equipment and instrumentation. If satisfactory means can be found for producing the brine, carrying it through the power plant, and injecting it into the subsurface formation, a power plant project should have a reasonable probability of success. Additional technical risks include noncondensable gases and steam quality, but within expected limits, these problems can be met with known technology.

Environmental risks that were identified include ground subsidence, air pollution by hydrogen sulfide, and disposal of liquid effluents. The long-term availability of cooling water is, another possible risk. It becomes a risk for the flash option only if it is found that the amount of water injected must equal that produced in order to prevent subsidence.

Economic risks involve the need for improved information on capital costs for both the plant and the well field. The existence of an adequate energy source has been reasonably well established. However, the ability to deliver the brine to the plant and to inject the discharged brine into the subsurface formation at acceptable costs have not been demonstrated. Plant availability, or capacity factor, significantly affect the energy production cost.

Further testing at the GLEF was recommended. The test program must demonstrate that brine handling can be accomplished by the use of either an on-line scale cleaning method, standby equipment, or the prevention of scale formation by brine modification techniques. Other risks were identified, but brine handling was of greatest concern.

The results of this study indicated that the most appropriate energy conversion process for the 50 MW (net) demonstration power plant was the two-stage flashed steam process using unmodified brine and three 50 percent trains of flash equipment. This option was the lowest in busbar cost, low in capital cost, and used proven and available equipment to achieve low risk. In addition, since existing geothermal flashed steam power plants have demonstrated that electrical power can be produced commercially, investor confidence is expected to be higher for this process than for the commercially untried flashed binary process. Therefore, it was recommended that the GLEF be modified to simulate this process and that the future testing be directed primarily toward alleviating the risks associated with it. However, effort to develop the option of using modified brine was recommended to be kept open. The most cost effective method for accomplishing this way identified as the Industrial Support Program, which operated a small-scale facility for this purpose at a site adjacent to the GLEF.

Research and development recommendations that were defined were expected to minimize the major identified risks. These recommendations included a series of GLEF tests as well as other activities, such as theoretical studies. The tests assumed that the GLEF would be modified to simulate the two-stage flashed steam power plant defined by the conceptual design developed in this study.

9.1.3 CONCLUSIONS

- o The most appropriate energy conversion process for a commercial scale, 50 MW demonstration power plant is the two stage flashed steam process using unmodified brine and three 50 percent capacity trains of flash vessels. This is based on an analysis that incorporates the latest GLEF and related data and information.
- o The capital cost for the two-stage flashed steam plant using unmodified brine and standby flash equipment was estimated to be \$38.4 million. The capital cost for the corresponding wellfield was \$9.83 million. The busbar energy production cost was 37.6 mills/kWh. These costs include escalation to first quarter 1982 prices.
- o The option of using modified brine should be kept and developed.
- o Plant capital costs are lower for plants incorporating the flashed steam process than for those incorporating the binary process. However, brine requirements and, therefore, well field capital costs are lower for binary plants. The result is that the energy production costs for the flashed steam and binary plants studied are the same to within the accuracy of the estimates.
- o The lowest energy production cost of the alternatives studied for the binary process was 38.7 mills/kWh. Two alternatives, one utilizing the four-stage flash binary process with acidified brine and the other, a liquid/liquid binary process with acidified brine, had this same energy production cost. Future reductions in capital costs (in R&D) may result in an attractive alternative.
- o No insurmountable risks were identified. The most important risks are those associated with brine handling. If satisfactory means can be found for producing the brine, carrying it through the power plant, and injecting it into the subsurface formation, the project will have a reasonable probability of success.

- o The technical, economic, and risk analyses conducted during this study indicate that development should be carried forward.
- o The GLEF should be modified to simulate the two-stage flashed steam process. The test program described in this report should be supported by related studies that were also described.

9.1.4 RECOMMENDATIONS

- o The 50 MW (net) demonstration power plant at the Salton Sea KGRA should be based on the two-stage flashed steam energy conversion process using unmodified brine and redundant flash equipment. The GLEF should be modified and operated to reduce critical risk areas.
- o The overall feasibility study should go forward, at least through Phase II, to improve performance and cost data for the power plant and the well field and to define the best means for overcoming the important risks.
- o The option to use modified brine should be kept open. A small-scale loop, simulating the two-stage flashed steam process with modified brine, should be constructed and operated under the Department of Energy, Industrial Support Program, at the small test facility currently located next to the GLEF.

9.2 COOLING WATER CHEMICAL TREATMENT

9.2.1 PURPOSE

The purpose of this test was to determine the necessary chemical treatments for cooling water systems which used condensed geothermal steam for makeup.

9.2.2 PROCEDURE

For the majority of the period during which the GLEF operated, geothermal steam condensate was used as cooling water make up. Several parameters were monitored on a routine basis. These included corrosion rates, algae and bacterial counts and overall chemistry. Various proprietary chemicals were used to control the water quality. The pressure drop across the condensers (E-4A and E-4B) was monitored and was the primary indicator of fouling caused by corrosion and deposition of sediment and biological growth. Petrolite corrosion probes and small coupons were used to monitor the corrosion rates. Periodically the condenser heads were removed and the tubes inspected for fouling and tube leaks.

9.2.3 RESULTS

The cooling water system at the GLEF was thought to be better understood than the steam production and brine handling systems. As such this test was given a lower priority and documentation was often sketchy. However, general observations could still be made.

Initially the cooling water was drawn from the Imperial Irrigation District's irrigation canal. As this water circulated through the plant, some losses occurred, primarily due to drift and evaporation losses from the pond. Geothermal steam condensate was frequently used to make up these losses. The quality of the condensate varied from good to poor depending on plant operation. If poor separation was occurring in the flash process, high concentrations of contaminants were released to the pond. Iron, calcium, and other species deposited on or corroded the condenser tubes. Ammonia fed the biological growth which also fouled condenser tubes.

Many proprietary chemical treatments were used to control water chemistry including those distributed by Nalco, Zimmite, and Betz. In general, all three companies distribute products for the control of corrosion, scaling, and biological growth and all had some degree of success. Due to the scarcity of documentation it is difficult to draw hard conclusions, however, it appeared that the Betz treatment was based on prior results and was somewhat better than the others. Cost of these programs was significant.

In addition to the proprietary products, chlorine gas was used to control biological growth and H_2S .

9.2.4 CONCLUSIONS AND RECOMMENDATIONS

In any cooling water system, chemical additives are necessary for the control of corrosion, scale, and biological growth. This would be true for cooling towers as well as ponds, although ponds can be more trouble prone in an area with windblown contamination and high solar flux. Ponds may use more water, and are more costly to treat. In the case of a geothermal power plant which uses condensed geothermal steam as make-up, the problems are compounded by possible contamination by geothermal minerals carried over with the steam in the flash process. It would be advantageous in commercial plants of this type to use cooling towers as opposed to ponds, carefully select materials of construction, and to exercise a strict control over condensate quality.

9.3 SCALE RESISTANT COATINGS

9.3.1 PURPOSE

Corrosion Research Co., Inc. (CorReco) of Camus Valley, Oregon manufactures coatings for use in preventing corrosion of metals exposed to adverse environments. CorReco and Union Geothermal at Brawley indicated that CorReco products might also help prevent the formation of scale in geothermal brine piping. Consequently, SDG&E obtained several pipe spools coated with CorReco 700, and evaluated their ability to prevent scale formation in several locations in the GLEF.

9.3.2 PROCEDURE

During 1978 and 1979, five short pipe spools (including one standard 90 elbow) were sent to CorReco for coating with CorReco 700, a phenylmercaptide thermoplastic resin. The GLEF was operating in a two stage flash cycle configuration during this period. In July 1978, the first three spools were exposed to brine flow in the first stage flash vessel drain and injection piping. In March 1979, two more spool pieces were coated and installed in the drain piping of each second stage flash vessel. Exposure time ranged from 690 to about 2000 hours for various spools. Figure 9.3-1 shows the conditions of the test and the results.

9.3.3 RESULTS

In all three of the different brine environments that the coatings were subjected to, no discernable difference was noted between scale thickness on piping coated with CorReco 700 and uncoated piping. One inspection of the injection line spool piece showed a slightly reduced scale thickness. However, it was suspected that a perturbation in the flow caused by a nearby line obstruction was the cause of this difference. This was confirmed by relocating the spool piece. A subsequent inspection showed no difference in scale formation between coated and uncoated piping.

The CorReco coating also appeared to be physically unsuited to the 360°F (182°C) temperature in the first stage flash vessel drain line, as the coating was observed to be separating from the pipe in large sheets during the first inspection of the spool piece after hours of operation. Whether this was caused by the high temperatures or an improper application of the coating could not be ascertained. The coating withstood the lower temperatures in the second stage flash vessel drain line and injection line (245 and 220°F (118 and 104°C) respectively), but was quickly destroyed by the high velocity water jets used in the hydroblasting process to remove scale from the piping.

LOCATION	PIPE SPOOL SIZE	TYPICAL OPERATING CONDITIONS			BEGIN TEST	END TEST	APPROX. EXPOSURE TIME	RESULTS OF TEST
		TEMP (°F)	PRESSURE (psia)	FLOW RATE (9 pm)				
1st Stage "B" Train	10"D x 24"	360	135	~600				<ul style="list-style-type: none"> - No visible reduction in scaling rate in either elbow or straight spool pieces. - Coating peeling off pipe in large sheets at end of exposure.
Drain Line	Standard 90° Elbow	(363)	(130)	(633)	7/78	8/78	690 hrs	
2nd Stage "A" Train								
Drain Line	12"D x 24"	230-245 (242)	27 (20)	~580 (565)	3/79	8/79	750 hrs	<ul style="list-style-type: none"> - No visible reduction in scaling rate. - Hydroblast cleaning of pipe destroyed coating, ending test.
2nd Stage "B" Train								
Drain Line	12"D x 34"	230-245 (242)	27 (20)	~580 (565)	3/79	8/79	650 hrs	<ul style="list-style-type: none"> - No visible reduction in scaling rate. - Hydroblast cleaning of pipe destroyed coating, ending test.
Injection Line	10"D x 24"	220 (228)	14.7-500	~575 (1117)	7/78	3/79	~2000 hrs	<ul style="list-style-type: none"> - Initial inspections indicated reduction in scaling rate. However, subsequent changes in piping configuration showed flow kinetics were apparent cause, not coating. - Coating adhered to pipe wall during entire period of test.

Figure 9.3-1 Test of CorReco 700 Scale Resistant Coating

9.3.4 CONCLUSIONS

CorReco 700 does not inhibit scale formation in piping exposed to the brines of the Niland reservoir. In addition, it does not appear to be suited for withstanding scale removal or use at temperatures of 360°F (182°C) or higher, and/or the technique of bonding the coating to the pipe wall needs to be improved. Use is not recommended.

9.4 FIRST-ORDER LEVELING SURVEY OF GLEF VICINITY

9.4.1 PURPOSE

SDG&E's Conditional Use Permit with the County of Imperial for operation of the GLEF required that an annual survey be conducted of field benchmarks in the vicinity of the GLEF. The purpose of this survey was to record any subsidence that may be occurring near the site with specific attention paid to any subsidence that may be related to geothermal development.

9.4.2 PROCEDURE

Beginning in December, 1976 and each of the following three Decembers, SDG&E survey crews performed a first order, Class I level survey of 18 benchmarks within one mile of the GLEF site. The surveys were conducted in accordance with procedures and occurrences outlined in the U. S. Coast and Geodetic Survey Publication No. 239.

During this period of time two production wells (Magmamax No. 1 and Woolsey No. 1) were in intermittent operation. Two injection wells (Magmamax No. 2 and No. 3) were used to receive about 80% of the production flow.

9.4.3 RESULTS

Figure 9.4-1 shows the locations of the benchmarks with respect to the GLEF. Table 9.4-1 summarizes the elevations of the benchmarks relative to USGS monument C-35. There is a slight downward trend noticeable in the vicinity of the injection wells, while the elevations of the benchmarks near the production wells generally increase and decrease in alternate years. In all cases, except monument C-A-14, the yearly change in elevation does not exceed 5mm. C-A-14 showed a sudden downward jump of 2.6 cm between 1977 and 1978.

9.4.4 CONCLUSIONS

The small elevation changes near the injection wells may be influenced by the proximity of the Salton Sea. If geothermal activity is suspected of impacting subsidence, the ground near an injection well would be expected to rise over time, not fall. The changes in elevation of the monuments near the production wells show no overall trend, either upwards or downwards. The elevation changes are generally consistent with natural subsidence measurements recorded at other areas in the Imperial Valley. Therefore, this data does not seem to indicate a change in land elevation due to injection of geothermal fluids.

Figure 9.4-1 Location of Benchmarks

Table 9.4-1 Benchmark Elevations

BENCHMARK	FINAL ELEVATION (m) *			
	1 12-20-76	2 12-12-77	3 12-6-78	4 11-29-79
C-35	-68.4430	-68.4430	-68.4430	-68.4430
C-A-1	-67.7438	-67.7433	-67.7439	-67.7433
C-A-2	-67.2057	-67.2041	-67.2054	-67.2052
C-A-3	-67.3026	-67.3010	-67.3019	-67.3022
C-A-4	-66.6104	-66.6064	-66.6074	-66.6057
C-A-5	-66.6179	-66.6130	-66.6142	-66.6128
C-A-6	-65.8527	-65.8478	-65.8481	-65.8465
C-A-7	-67.4404	-67.4362	-67.4361	-67.4339
C-A-8	-68.5969	-68.5937	-68.5947	-68.5925
C-A-9	Destroyed			
C-A-10	-68.8254	-68.8269	-68.8293	-68.8297
C-A-11	-69.7154	-69.7173	-69.7192	-69.7196
C-A-12	-69.6129	-69.6149	-69.6173	-69.6178
C-A-3	Disturbed			
C-A-13-1	-69.6250	-69.6258	-69.6262	-69.6262
C-36	-69.4493	-69.4513	-69.4527	-69.4521
C-A-14	-70.0127	-70.0137	-70.0397	-70.0401
C-35	-68.4430	-68.4430	-68.4430	-68.4430

*Below sea level. Benchmark C-35 was used as reference.

9.5 FMC H₂S ABATEMENT

9.5.1 PURPOSE

The purpose of this test was to determine if the FMC H₂S abatement system could be applied to an operating geothermal power plant. This method has previously been tested successfully at the Geysers geothermal field to abate H₂S emissions during drilling operations.

9.5.2 PROCEDURES

FMC Corporation conducted a series of experiments at the GLEF. This report summarizes those tests.

Hydrogen sulfide (H₂S) abatement is achieved by absorption of H₂S into a sodium hydroxide (NaOH) solution and subsequent oxidation by hydrogen peroxide (H₂O₂). Dilute H₂O₂ and NaOH solutions were fed into the scrubbing water entering the first stage steam scrubber. The degree of H₂S abatement was determined using 1/C draeger tubes at the steam outlet of this scrubber.

9.5.3 RESULTS

Table 9.5-1 shows the results of the FMC tests. In the February, 1979 test, 50% H₂S abatement was achieved using a scrubbing solution of 0.15 wt% H₂O₂ and 0.16 wt% NaOH. In July 1979, a solution of 0.38 wt% H₂O₂ and 0.56 wt% NaOH did not improve upon the February tests.

9.5.4 CONCLUSIONS

H₂S emissions can be reduced by the FMC technique. While the degree of abatement was insufficient to eliminate the use of other H₂S abatement techniques, like the Stretford Process, it may be useful as a pretreatment which would reduce the size and costs of operating a Stretford unit, if required.

Due to the apparent success of tests conducted by Imperial Magma, where the gas was introduced to the clarifier, a Stretford unit may not be needed.

Table 9.5-1

FMC H₂ Test Results

<u>Date</u>	<u>Scrubbing % H₂O₂</u>	<u>Water Inlet % NaOH</u>	<u>Abatement %H₂S</u>
2/8/79	0.15	0.16	50.0
7/13/79	0.00	0.16	0.0
7/14/79	0.00	0.35	3.3
	0.38	0.56	50.0
	0.62	0.56	50.0

9.6 HYDRODYNAMICS SCALE DISINTEGRATOR

9.6.1 PURPOSE

The purpose of this test was to evaluate the effectiveness of utilizing an induced magnetic field to control scale formation.

9.6.2 PROCEDURE

A device marketed by the Hydrodynamics Corporation of Gretna, Louisiana under the tradename of Hydrodynamics Scale Disintegrator was installed approximately 300 feet downstream of the injection pump, P-2. This device induced a strong magnetic field in the pipeline which, theoretically, aligned magnetic particles in the flow stream with each other, thereby preventing them from being attracted to the pipe walls. The scale disintegrator was in service for approximately one month, during which several visual inspections were performed.

9.6.3 RESULTS

An inspection was conducted three days after the device was placed in service. No scale had formed within the scale disintegrator while there was a thin layer of scale immediately upstream and downstream of the device.

Latter inspections revealed that scale formed within the device at the same rate as elsewhere with injection line. After approximately one month, testing of the device was discontinued as flow was being blocked by the scale accumulation in this unit.

9.6.4 DISCUSSION AND CONCLUSIONS

The apparent success during the first several days of operation may have been due to outgassing of the plastic liner or preservative applied of the device. Outgassing often occurs when certain organic or plastic type materials are heated. This releases gas which tends to prevent scale from adhering to the surface. After all the gas is evolved, scale can begin to adhere to the pipe.

The magnetic field apparently had no effect on the scale formation. This was probably due to the nature of the predominantly amorphous silica scale normally present in the injection line. Since amorphous silica has no definite crystalline or magnetic structure, the magnetic field did not align the particles and therefore had no effect on scale formation. This device may have a positive affect on the iron sulfide scales found in the production and first stage steam separators however no attempt was made to test in these areas.

9.7 NONCONDENSIBLE GAS CONTENT OF NILAND BRINES

9.7.1 PURPOSE

The purpose of this test was to determine the concentration of noncondensable gases in the geothermal brines utilized at the GLEF. The information gained will be used in the design of a 50 MW geothermal power plant at the Niland reservoir.

9.7.2 BACKGROUND

Test conducted in 1973 concluded that the non-condensable gas content of the Niland brines was approximately 3%. This was based on partial flow test of the Magmamax No. 1 well. The testing began soon after drilling was completed.

During sub scale, partial flow tests in 1974, there were indications that the gas content was something less than 3%, however, this was not verified.

The GLEF design was based on a gas content of 3% (See Section 4.0 for details). Operating experience with the four stage steam separation system again indicated that the gas content was significantly less than 3%.

The above discrepancies may have occurred due to instrumentation problems, unrepresentative sampling, low well flow rates, sampling too soon after drilling, or the possibility of a "gas cap".

When the GLEF was modified to a two stage steam separation system, a program was begun to accurately determine the gas content. Attempts were made to utilize existing plant instrumentation (orifice meter) and pitot tubes. These techniques yielded conflicting results which due to instrumentation problems could not be substantiated. Bomb samples taken by NARCO at the well heads in July, 1979, indicated that the gas content was on the order of 0.1 to 0.2%.

9.7.3 PROCEDURE

A positive displacement gas meter was installed in a bypass loop at the base of the vent gas stack. This stack vented all the noncondensable gases which were generated by the first and second stage flash processes.

Gas flow measurements were taken by flowing the gas stream through a meter and periodically recording meter readings. The meter readings were converted to standard conditions (OOC and 1 ATM) and multiplied by the density of the gas to obtain mass flow. The gas was assumed to be

primarily CO₂ with a standard density of 0.1235 pounds/SCF. For actual gas composition see Section 8.7.

To obtain brine mass flow it was assumed that 20% of the incoming brine was flashed to steam and that the remaining 80% was injected. Expressed mathematically:

$$\text{Injection Flow} = .8 \text{ production flow}$$

or

$$\text{Production flow} = \text{injection flow}/.8$$

or

$$\text{Production flow} = 1.25 \times \text{injection flow}$$

Since the clarifier/filter prevented scaling in the injection line, flow measurements made at this location were assumed to be accurate.

The quantity of noncondensable gas expressed as a percentage of incoming brine was calculated by dividing the gas mass flow by the brine mass flow and multiplying by 100%.

The GLEF was operated on two production wells for the test period.

9.7.4 RESULTS

The results of the four test runs performed are tabulated below:

<u>Run</u>	<u>Brine Flow (Lbs/Min)</u>	<u>Noncondensable Gas Flow (Lbs/Min)</u>	<u>% Noncondensable Gas (Weight %)</u>
1	5614	7.79	0.14
2	6526	6.99	0.11
3	6526	7.66	0.12
4	<u>7017</u>	<u>7.71</u>	<u>0.11</u>
Avg.	6421	7.54	0.12

9.7.5 CONCLUSIONS

The noncondensable gas content of the geothermal brines used at the GLEF was found to average 0.12%. For preliminary power plant design purposes a noncondensable gas content on the order of 0.10% to 0.15% can be assumed. Each

production well for a proposed power plant will need to be tested for noncondensable gas content before the design is finalized.

9.8 Direct Contact Heat Exchanger Testing

Principal Investigators: Piero L. Della Vida, Frederick J. Franz, and Robert S. Weinrich
(Daedalean Associates, Incorporated)

9.8.1 OBJECTIVES (Scope of Work)

The objective of this program was to provide preliminary engineering data for the future evaluation of the technical and economic feasibility of using a direct contact heat exchanger flash-binary cycle at the Niland Reservoir. This work was based on initial cycle studies accomplished by Ben Holt Co. (Ref. 9.8-1). The specific scope of work to be accomplished was as follows:

- Task I - To perform a system analysis for the determination of the optimum flash-binary cycle.
- Task II - To verify the optimum cycle established in TASK I using the model test loop at Daedalean's Springlake Research Center including:
1. Verification of the direct contact heat exchanger's capability of achieving the terminal temperature difference established in the heat balance.
 2. Confirmation of the length that was determined with the available correlation as described in Section 5.2 of DAI's Technical Report PDV-7902-002-TR dated March 1980.
- Task III- To compile a final report documenting the results of the program.

9.8.2 CONCLUSIONS AND RECOMMENDATIONS

It was concluded in the system analysis that the optimum cycle for the Niland direct contact heat exchanger application described herein be similar to the configuration shown in Figure 9.8-1 entitled, "Heat Balance Diagram for the Liquid-Liquid Preheater Cycle". The data obtained at the model test loop generally supports the assumptions made in the system analysis. In particular:

1. The final heat balance for the cycle described in Section 2.5 of DAI's report required, for the direct contact preheater, a 25°F (14°C) approach on the cold side (brine outlet temperature minus isopentane inlet temperature) and a 52°F (29°C) approach on the hot side (brine inlet temperature minus isopentane outlet temperature). Under test conditions a minimum approach of 12°F (7°C), was obtained, meanwhile, the majority of

Figure 9.8-1 Heat Balance Diagram for the Liquid-Liquid Preheater Cycle

the calculated approaches (refer to specific data page in DAI's report) ranged below 30°F (17°C).

2. The Lethan-Kehat correlation has been used to evaluate the column length and a 26.5 foot effective heat transfer length has been selected for a prototype system (See Section 5.2 of DAI's report). The data collected indicates that such a length is adequate. Figure 9.8-2 shows the direct contact preheater design, based on Sakiadis-Johnson correlation for the determination of the column diameter, and the Lethan-Kehat correlation for the determination of the column length, for a unit that utilizes the flow of one well at the Niland Reservoir. Appendix D in DAI's report describes how such a design has been accomplished for a unit that utilizes the flow of one well as well as some preliminary considerations for a 50 MW unit.

The completion of Task I and II in DAI's report have provided a foundation for selecting an optimum flash-binary cycle using a direct contact heat exchanger. Future work required to determine overall feasibility of direct contact heat exchangers for binary-cycle applications at liquid-dominate geothermal reservoirs should include the following:

- o Collection of a greater number of data points to provide a broader data bank to use during design efforts.
- o Study of the influence of the surface tension in the heat transfer mechanism as well as in the fluid mechanics of the phenomenon.
- o Study of the end effects in the direct contact heat exchanger and development of suitable distribution and extraction devices to avoid collateral effects such as carryover or carryunder.
- o Test of direct contact preheaters with actual brine, possibly at high temperature and with high salt content to control the accuracy of the laboratory data and of the predictions based on them.
- o Determination of the effect of droplet size and residence length upon the solubility of the dispersed hydrocarbon phase within a continuous phase of geothermal brine.

Figure 9.8-2 Direct Contact Preheater

9.8.3 REFERENCES

- 9.8-1 "Feasibility Study, Direct Contact Heat Exchanger",
the Ben Holt Co., November 16, 1978, No. 7820.
- 9.8-2 "Geothermal Loop Experimental Facility Direct
Contact Heat Exchanger Program", Daedalean Associates,
Inc., January 1980.

9.9 SURGE CONTROL STUDY

9.9.1 INTRODUCTION

The Geothermal Loop Experimental Facility (GLEF) had a tendency to operate with large oscillations due to pulsing flow of geothermal brine, called surging. Surging is an uneven two-phase produced flow of geothermal fluid caused by the formation of noncondensable gas and steam voids in the liquid brine. This surging can cause: (1) mechanical failure of the system due to transient stresses; (2) fluctuating pressure and flows in the first stage flash vessel and, subsequently, the turbine, with possible detrimental effects on turbine life; and (3) downstream plant fluctuations and undesirable nonsteady behavior of the power plant. A surge control study was initiated in December, 1978, to develop methods to eliminate or at least reduce the surging to create stability in the plant.

9.9.2 OBJECTIVE AND APPROACH

The object of this work was to recommend modifications to the GLEF that will eliminate or substantially reduce surging and pulsation in the well-to-plant pipe system. The recommendation was to be representative of the most desirable method for a 50 MW plant design.

This objective was accomplished by the following procedure.

1. Determining the state of the art for predicting the nature of concurrent two-phase gas and liquid flow; i.e., the flow regime.
2. Applying these predictive methods to the GLEF conditions assuming straight, horizontal pipe.
3. Extending the theory, if required, of these predictive methods to cover more correctly the GLEF configuration.
4. Observing the nature of the flow at the GLEF.
5. Interpreting these observations in terms of the theory developed in Step 3.
6. Determining any unique requirements and recommend design procedures.
7. Applying the procedures to the 50 MW design base case.
8. Applying the procedure to the present GLEF conditions.

9. Preparing a set of recommendations for modifying the GLEF to meet the above objective.

Report documenting the results of the study is attached as Appendix D.

9.9.3 SUMMARY OF RESULTS

A thorough review of two-phase theory as applied to GLEF conditions was accomplished. GLEF design and operating data was collected.

At the GLEF, the production well-to-plant pipeline does not consist of straight horizontal pipe, whereas most the theory is based on straight pipes. The various deviations from straight horizontal pipe through elbows, and vertical loops, increase any tendency to form liquid slugs in the pipeline. With control valve at the end of the pipeline (after liquid slugs separate), an unstable condition could exist because of these liquid slugs.

Several design alternates were investigated, including redesign of the piping. The control valve can be decoupled from the pipeline by a surge tank or control homogenizer, whose function is to provide sufficient gas and liquid capacity to absorb the largest expected slug to produce a mixed or separated flow with a constant liquid-to-gas ratio. In addition, slope changes were also found to be significant. Upward slope of the pipeline will slow down the liquid phase by about 10 percent, but the downward slope will increase the liquid flow by approximately 20 percent. The existing GLEF inclines increased the likelihood of slug formations as compared with horizontal lines.

9.9.4 RECOMMENDATIONS

To solve the existing problem, that is, to assure steady flow into the first stage flash tank and to significantly reduce pipeline motions, several approaches were recommended:

- o Provide a surge tank (Figure 9.9-1).
- o Replace selected sections of the pipeline with a horizontal line leading to the surge tank.
- o Locate the control valve immediately after the surge tank.

Because of the time required to design and construct the surge tanks and associated equipment, these recommendations were not incorporated into the GLEF design.

Figure 9.9-1 Proposed Surge Tank for GLEF

9.10 VISUAL OBSERVATIONS OF INTERIOR OF SECOND STAGE FLASH VESSEL

9.10.1 PURPOSE

The purpose of this test was to visually observe the conditons inside the second stage flash vessel (V-11).

9.10.2 BACKGROUND

Since the conversion of the GLEF to a two stage flash system, the second stage steam quality was poor. At times, the total dissolved solids in the steam condensate from the second stage exceeded 400 PPM by weight. This is much too high to be used in a conventional steam turbine. It was theorized that the poor quality steam was the result of poor separation of steam and brine in the second stage caused by the large pressure drop and surging or that a stable foam was formed in the flash vessel which carried over to the scrubber. Either case could result in brine being carried over to the scrubber. The scrubber was not designed to treat the resulting high inlet loading.

9.10.3 PROCEDURES

Visual observations were used to determine the physical condition within the second stage flash vessel of the "B Train" (V-11). Two sight glasses were installed on V-11 as shown in Figure 9.10-1. A 500 watt lamp was shown through one sight glass while the observer looked through the other.

Observations were performed early in June, 1979, with the GLEF operating on two well flow. The temperature and pressure in V-11 were approximately 235°F (113°C) and 30 psia respectively. The conditions within the vessel were observed several times per day for three or four days. Because the sight glasses scaled over in several days, no further observations were attempted until after they could be cleaned during a GLEF shut down in early July, 1979. At this time, the conditions were again observed for several days until the glasses again scaled over.

9.10.4 RESULTS

Visual observations confirmed that a mist was present in V-11 under normal conditions. Occasionally it became dense enough to obscure the surface of the fluid.

The density of the mist was apparently related to the operation of the control valves on the vessel, however, no strong correlation was found.

Figure 9.10-1 Second Stage Flash Vessel (V-11) Showing Position of View Ports

The brine surface (brine/steam interface) had no evidence of stable foaming. Occasionally some surface bubbling would take place which dissipated in several seconds. There was no visual evidence of bubbles or foam being carried with the steam to the scrubber.

Since the episodes of heavy mist density and bug-bling were short and intermittent, no attempts were made to find a correlation to steam purity.

9.10.5 CONCLUSIONS

The primary cause of high solids concentrations in the second stage steam apparently is small brine droplets in the form of a mist being carried with the steam to the scrubber.

Foaming does not appear to contribute to the high solids concentrations in the second stage steam.

9.11 CONDENSATE ACIDIFICATION

9.11.1 PURPOSE

When geothermal steam condensate was mixed with the brine, additional scale formation had been observed. These observations were found under full condensate recombination (100% injection) and miscellaneous use of condensate as purge water. The purpose of this test was to evaluate the effectiveness of condensate acidification as a method to reduce observed scale formation.

9.11.2 PROCEDURE

Additional scale composition was analyzed. Carbonates were found to compromise a significant proportion of the scale. The pH of the condensate was compared to the brine pH and condensate pH was found to be significantly higher. By adding acid until the condensate pH was reduced to a level comparable to or slightly below the brine (approximately 5.0), carbonate scale was expected to be eliminated.

Hydrochloric acid was metered to the condensate to be acidified. Both automatic controls and manual feeds were accomplished. Periodic samples of condensate pH were taken to verify pH adjustment.

9.11.3 RESULTS

Automatic control was difficult to maintain. Response of the acid metering pump system even after modifications, was not fast enough to react to pH changes. This was primarily the result of the remote location of the metering pump (location based on safety considerations). Fixed feed rate of acid, resulting in average condensate pH reduction to approximately 5.0, was eventually found to result in minimum changes in pH.

Inspection of the GLEF at points where acidified condensate and brine mixed showed significantly reduced scale formation, but carbonate was still found as a component of the scale.

9.11.4 CONCLUSIONS

Acidification of condensate significantly reduced carbonate scale formation when acidified condensate was mixed with the brine. Variations in condensate flowrate and pH combined with facility limitations probably allowed significant excursions from the target pH of 5.0. Acceptable control of condensate pH appears to be a feasible method of reducing carbonate scale formation in the brine upon mixing of the fluids.

**A RISK ANALYSIS OF THE PROPOSED SDG&E
FIFTY MEGAWATT POWER PLANT AT THE NILAND KGRA**

BY:

**R.M. JORDA, Senior Consultant
COMPLETION TECHNOLOGY COMPANY**

**Prepared for San Diego Gas & Electric
August, 1978**

COMPLETION TECHNOLOGY COMPANY

4200 WESTHEIMER RD., SUITE 211 • HOUSTON, TEXAS 77027

713/961-5011 • TELEX: 775781

**A RISK ANALYSIS OF THE PROPOSED SDG&E
FIFTY MEGAWATT POWER PLANT AT THE NILAND KGRA**

BY:

**R. M. JORDA, Senior Consultant
COMPLETION TECHNOLOGY COMPANY**

	Page
Table of Contents	i

TABLE OF CONTENTS

	Page
Introduction and Scope	1
The Influence of Suspended Solids on Injection Well Performance	2
An Example Injection Well, and Its Characteristics	6
Injecting Water Which is Chemically Incompatible with Connate Reservoir Water	11
The Effect of Cooling Connate Water by Injection Water . .	15
The Effect of Dissolved Gases in the Injection Water . . .	15
The Effect of Reservoir Rock Solubilization	18
The Effect of Biological Contamination	19
Corrosion Problems in the Water-Wetted Metals Systems . .	21
The Effects of Fluid Recharge	22
Injection Well Completion Considerations	23
The Risk Analysis	26
Conclusions	27
References	29

A RISK ANALYSIS OF THE PROPOSED SDG&E
FIFTY MEGAWATT POWER PLANT AT THE NILAND KGRA

Introduction and Scope

This study has, as the principle objective, the assessment of specific technical problems at the Niland KGRA relating to subsurface disposal of spent, hypersaline geothermal water and the risks associated with these specific technical problem areas in connection with the proposed SDG&E installation and operation of a 50 megawatt power plant.

The technical problem areas discussed in this study are:

1. The influence of suspended solids on injection well performance.
2. The influence of chemical reaction of dissolved solids in the injection water.
3. The effect of cooling of connate waters by injection waters.
4. The effect of dissolved gases in the injection water.
5. The effect of reservoir rock solubilization on injection well performance.
6. The effect of biological contamination of the waters on the injection system and the injection well.
7. An overall assessment of corrosion problems in the surface water treating system and the injection well.
8. The problem of interference by fluid recharge.
9. Important well completion considerations.

Not included in this study are the effects of (1) convection currents, and (2) thermal recharge because they are beyond the level of effort specified for this study.

The sources of the material in this report include studies prepared under Sandia Laboratories and Lawrence Livermore Laboratories funding, the data collected from water injection studies which include (1) oil field water injection, both for disposal and secondary recovery, (2) subsurface disposal of industrial waste liquids, and (3) subsurface disposal of chemical plant wastes.

A risk/probability analysis at the end of the report contains the likelihood of a problem occurring, and the capability of a particular problem area of defeating the geothermal power recovery project.

There are areas in the report in which total agreement by all concerned readers is unlikely. But a total, in-depth study of all permutations of the problems which might be associated with the proposed 50 MW plant would only delay the project, and it is doubtful that any significant changes in the direction of effort would emerge.

The Influence of Suspended Solids on Injection Well Performance

The Magma Power Company's produced geothermal source waters, when cooled and concentrated by flashing, precipitate an iron-rich, amorphous silica averaging 500 ppm as suspended solids. These waters require the removal of suspended solids to an acceptable level which insures continuous, long term disposal by injection into shallow, layered sand/shale aquifers.

Several approaches have been followed in the treatment of these reinjection brines. These are, in summary:

(1) Inject the brine with no reduction of the solids loading. The result was injection well damage and loss of injectivity.

(2) Inject the brine with treatment consisting of gravity separation of part of the solids (settling tanks). This produced an effluent with a solids loading of 100-150 ppm, and provide apparent sustained, acceptable injection. Why

this high solids loading did not result in damage to the injection well is, at present, conjectural.

(3) Acidify the water to limit the solids loading (a bench-size test). The results are encouraging, but the added cost of acid and special metallurgy in the surface facilities and injection well tubulars may be unacceptable. Also, interruptions in the system flow could be harmful, as the performance of other acidified systems in other industries has demonstrated.

(4) Remove solids by sludge-bed clarification and mixed-media rapid filtration (small pilot test by LLL, with a larger-scale test of the clarifier by Magma Power Co., Sandia Laboratories and CTC). This produced a saturated water in the LLL tests (and a slightly undersaturated water in the Magma et al tests) which, after filtration, resulted in a stable water containing about 1-2 ppm suspended solids.

A stable water nearly free of suspended solids, as produced in the pilot tests, is the usual objective of water treatment systems where injection into non-fractured porous media is the goal. Predicted injection performance at Niland is excellent. Many such systems exist, and actual injection performance is excellent.

It appears that the process side of water treating, excluding blending the Niland waters with make-up waters from the Salton Sea, is about in hand. However, clarifiers and filters, as is the case with other process components, require optimization and reasonable term of testing and performance analysis before full confidence in performance and a full understanding of vulnerable areas can be acquired. This supports the proposal for the installation of a 10 MW clarifier-filter system. In a 50 MW plant, there will be enough problems to iron out in the power recovery system itself without the added burden of optimizing the spent water disposal plant. The investment in a 10 MW water treating plant can be

considered to be equal to purchase of one-fifth of the equipment required in the full scale system. And a 50 MW water disposal system may well end up as being five, 10 MW disposal systems in parallel, in which case the earlier optimization and debugging of the 10 MW clarifier-filter system will be of considerable value.

If Salton Sea water is required as make-up for prevention of subsidence or for any other reason, serious consideration should be directed toward the development of a separate water treating (not injection) system to handle this brine. The Salton Sea brine introduces a new variable component into an otherwise reasonably well-understood system. The character of the Salton Sea water, especially the microbial and dissolved oxygen constituents, will vary seasonally. Rain, dust, and anything else which can fall into, or be dumped into the Salton Sea will cause a variation in the chemical, microbial, and physical character of the water. This can affect plant and injection performance.

Generally, other industries' experience with systems where subsurface waters have been mixed with surface waters (from lakes, rivers, oceans, ponds, bays, gulfs and estuaries) has been bad.

Problems of unwanted solids generation by oxygen contamination, microbial contamination, dissolved solids incompatibility, seasonal variations, and illegal or legal waste dumping are all too common and well known in the petroleum, petrochemical and other industries. Although the nature of the problems of mixing spent brine with Salton Sea water can only be defined through actual tests, the possibility of a two-treatment surface system with the effluent discharged to a common disposal well needs to be assessed. (Figure 1 illustrates the geometry of a single well equipped to handle two injectants.)

Based on the experience of others, the probability of successfully treating the mixed waters in the surface facilities is low, and the risk of factor is high. (More will be said about this later.) The need to study this problem is immediate.

ONE WIDELY USED WELL CONFIGURATION FOR THE SEPARATE INJECTION OF TWO LIQUIDS.

An Example Injection Well, and Its Characteristics

Before proceeding with the rest of the overall technical assessment, an example Niland area injector needs to be described and examined. The formations which overlie the geothermal producing horizon in the Niland area consist of hundreds of feet of alternating layers of sand and shale (or clay). Permeabilities in the sand bodies range from a few millidarcies to a few darcies. The average permeability of the sand members contained in any 500 or 600 foot gross section appears to be at least 300 millidarcies. A gross interval of 600 feet can easily contain 300 net feet of sand which, averaging 300 md, provides a kh of 90,000 md-ft.

A representative injection well appears in Figure 2. Injection is through the casing to minimize friction losses, and the well provides no special sand control completion measures. If necessary, a 4½" gas lift string can be included to facilitate back washing. The gas lift string can also be used for wireline surveys and sampling.

An estimate of well performance, based on the well configuration shown in Figure 2, can be calculated using the following values:

$$r_e = 2000 \text{ ft}$$

$$r_w = 6 \text{ inches}$$

$$\mu = 0.4 \text{ cp}$$

$$\text{static reservoir pressure} = 822 \text{ psi}$$

$$\text{hydrostatic bottom hole pressure} = 904 \text{ psi}$$

If a spectrum of kh values from an estimated maximum of 90,000 md-ft to a minimum of 10,000 md-ft (observed in steady-state behavior of Magmamax #3) is input into a well hydraulic analysis such as an IWPA*, the capacity of the well under conditions ranging from no impairment to 90 per cent impairment can be

* Reference 8, pp 23-35

AN EXAMPLE LOW COST INJECTOR WITH PROVISIONS FOR GAS LIFT CLEANING.
 THE GROSS INTERVAL OF 600 FEET PROVIDES 300 FEET OF NET SAND, k_f AVER-
 AGES 300 md, AND THE kh IS 90,000 md-ft.

Figure 2

simulated (Figure 3). This analysis reflects the reservoir resistance in terms of well hydraulics and flow rates measured at the surface, and is considered to be more definitive than other methods which ignore the reservoir resistance.

In Figure 3, the observed unimpaired capacity of the example well is much higher than values observed in the Niland injection well, Magmamax #3. It should be recalled, however, that Magmamax #3 is a much-abused well, and is known to be impaired.

A recent example of the use of the technique appears in Figure 4, the RIM for a well disposing of industrial waste liquids. Well conductivity is shown as k_e , or effective well bore reflected permeability, md, instead of kh . The performance of this well, which has been in service less than one year, is meticulously documented. A complete reservoir analysis and an exhaustive suite of core flow tests are available for examination. In short, there was little, if any guesswork connected with this injection system.

Because of an insidious creeping failure of a diatomaceous earth filter, and the lack of realization that slowly but steadily increasing injection pump pressure was a warning that impairment was occurring, the well impairment proceeded until the point "A" in Figure 4 was reached. Since no clay-swelling control was used, the effective permeability of the reservoir was $k_e = 150$ md, so point "A" represents an impairment of about 80 per cent. Tests of the water showed that the impairment consisted of uncemented particles of diatomaceous earth filter aid, and the well was cleaned by gas lift. The results of a stabilized, three-rate injection test which was performed after the filter was repaired are shown in points "B-B-B". This illustration is representative of the utility of the RIM when the necessary data are in hand.

The RIM for an example Niland shallow injection well, Figure 3, can be useful in assessing the relationship between well damage and well capacity. For example,

Figure 3

THE REINJECTOR IMPAIRMENT MAP FOR THE EXAMPLE NILAND WELL AT AN INJECTION WATER TEMPERATURE $T=180^{\circ}\text{F}$. FRAC PRESSURE IS JUST UNDER 500 psi SURFACE PRESSURE.

THE RIM FOR AN INDUSTRIAL DISPOSAL WELL REFERRED TO IN THE TEXT. POINT "A" SHOWS THE IMPAIRED CONDITION, AND POINTS "B"- "B"- "B" SHOW A THREE POINT INJECTION TEST AFTER THE WELL WAS REPAIRED.

an unimpaired well taking 25,000 b/d water should show a surface pressure of about 43 psig. If the well bore conductance (kh) is reduced from 90,000 md-ft to 30,000 md-ft, the pump pressure should rise to about 312 psi. Otherwise stated, an impairment of 67 per cent increases surface pressure (and horse power) by about 7.4 fold, but injection continues at a satisfactory rate until the well can be repaired. Beyond this point, impairment can continue to increase until a kh value of about 23,000 md-ft results (75 per cent impairment), at which point any further impairment will reduce the injection rate below the target capacity.

The observations and statements in this section of this report generally track observed behavior over a wide range of injection well geometries and configurations. Where high capacity injection reservoirs exist, only constant and severe irreversible impairment can damage an injector to the point where it is of no further value.

Injecting Water Which is Chemically Incompatible with Connate Reservoir Water

The effects of injecting water into reservoirs having interstitial fluids known to form precipitates when mixed with the injected waters has been studied by major oil companies and in university graduate programs over a period of at least 15 years. When water injection for enhanced oil recovery expanded at a very rapid rate (early 1950's), many such studies were funded in house or through outside sources.

Many samples of waters from reservoirs and from injection water sources, when mixed in glassware, produced veritable blizzards of suspended solids. Such observations do not reflect reservoir behavior, but they nonetheless prompted extensive studies of the incompatibility problem.

Most of the laboratory studies used in linear flow model as shown in Figure 5. Glass tubes, several inches in diameter and several feet long, were packed with

Figure 5

A SCHEMATIC OF THE TYPE OF APPARATUS USED TO INVESTIGATE THE INJECTION OF WATER INTO A POROUS MEDIUM CONTAINING WATER WHICH, WHEN MIXED IN A BEAKER WITH THE INJECTED WATER, FORMS PRECIPITATES.

reservoir sands or glass beads, saturated with water containing (for example) sulfate ion, and then subjected to the flow of water containing (example) barium ion. The reaction of barium ions and sulfate ions to produce barium sulfate precipitate is rapid and certain. However, repeated injection tests which were scaled to a proper dynamic similitude failed to show the precipitation of other than trace amounts of solids. In laminar flow, a "plug" displacement takes place, and the intimate mixing of precipitate-forming ions only occurs at the interface of "connate" and injected waters. Elaborate sampling and permeability measurements failed to detect any significant changes in porosity, permeability, or change in the ionic strength of either the injected or the displaced water.

Some investigators, not totally convinced by data from the linear flow models, constructed more elaborated and expensive radial flow models, but the outcome was the same. Over the years, the laboratory findings have been substantiated in the field. This issue is, in the technical world, no longer considered to be a problem.

On the other hand, precipitation of solids in the pore structure caused by injecting a water which is supersaturated at pore temperature and pressure is widely recognized as a source of severe impairment. It is interesting to note that some early water injection projects in which gross loss of injectivity occurred and in which the impairment was attributed to incompatibility were later found to be cases where supersaturation was the real cause of impairment.

Precipitation due to mineral supersaturation is the phenomenon toward which attention must be directed. The resulting decrease in porosity, accompanied by a predictable decrease in permeability (Figure 6) often causes irreversible damage in water injection wells. This widely recognized phenomenon underscores the desirability of sludgebed clarification to produce effluents which are not supersaturated.

A PERMEABILITY (millidarcies)-POROSITY CURVE
FOR APPROXIMATION ONLY, WHEN SPECIFIC
DATA ARE LACKING. ASSUMES COMPLETE
INTERCONNECTION OF PORES.

Figure 6

The Effect of Cooling Connate Water by Injection Water

As is the case in reservoirs similar to the shallow Niland sands, laminar radial plug flow will most likely occur in the process of injection. The shallow sands are profusely layered (Figure 7). Cooling the sands will not cause precipitation because an almost total displacement of connate water takes place. Cooling the argillaceous beds which separate the sands may cause precipitation within the clay beds, and the exact result of such cooling is not well known. However, the porosity of the clay layers which would be cooled is very small, and the total water volume is therefore small relative to the amount of water in the sand sections. Should gross precipitation of solids occur in the clay layers, the bulk volume of the clay will tend to increase slightly. Depending on the relative strengths of the clay and sand structures, some minor compaction of the sand members may take place.

This problem can be studied using physical or mathematical models. However, there are dozens of similarly interlayered sand/shale reservoirs in Southern and Central California, and in South Louisiana, into which cooler-than-connate waters have been injected for two or three decades with no evidence of significant loss of injectivity which can be attributed to interlayered cooling. The problem, if it exists, is not considered to warrant special consideration at this time.

The Effect of Dissolved Gases in the Injection Water

Dissolved gases do not exist above the few ppm range in the waters at Niland examined to date. Should percent-range amounts of dissolved gases be liberated during injection through a reaction not anticipated at this time, the effect will be to reduce water permeability, thus injectivity, by a predictable amount. Although relative permeability curves for gas/liquids are not available for this study, Figure 8 illustrates the general nature of such data.

An example electric log of a portion of the shallow sands and shales at Niland.

AN ILLUSTRATION OF THE INFLUENCE OF RELATIVE PERMEABILITY
ON THE FLOW OF LIQUID OR VAPOR THROUGH A POROUS MEDIUM.

Figure 8

If, for example, liquid saturation in the reservoir was 84 percent (the dashed line, Figure 8), and the balance (16 percent) was vapor, the permeability to water would be about 70 per cent of the liquid permeability. And kh values would be reduced by this percentage; a kh of 90,000 md-ft would be reduced to 63,000 md-ft. Referring to Figure 3, this would mean that at an injection rate of 25,000 b/d, the reduction in permeability caused by 16 per cent vapor would raise the surface pressure from 43 psi to 75 psi. Removal of the vapor phase would restore the kh, as this type of impairment is reversible. The problem of vapor liberation will only be significant if substantial volumes of vapor are produced.

The Effect of Reservoir Rock Solubilization

Reports from LLL indicate that some of the calcium constituents of the Magmamax #3 injection reservoir dissolve during injection because of the mild acidity of the water. The result of this is an increase in porosity, accompanied by an increase in permeability, both of an unknown magnitude. The acidity is neutralized as calcium dissolves, but the radius of the acidic water, before neutralization, is not known. And the radius will be ever-increasing as all of the acid-soluble components are dissolved radially away from the well bore.

One thousand gallons of dilute by hydrochloric acid at a pH - 2.0 (10^{-2} Molar) can dissolve only 0.02 cubic feet of calcium carbonate. The slightly acidic spent brine at Niland can dissolve only a fraction of this amount of calcite. Overall, the total increase in porosity appears to be minimal, and the amount of additional void space created does not appear to be capable of inducing compaction of the remaining rock.

If compaction is assumed not to occur, the increased porosity can be considered to be a mild form of well stimulation by long-term, very weak acidification.

The probable result of such a process is to increase the k_h in the affected area, and enhance injection. But a quantitative assessment of this has not been made.

To provide some insight to well beneficiation by matrix permeability increase, Figure 9 is included in this report.

The Effect of Biological Contamination

There is no evidence that the type of bacterial activity often found to be associated with subsurface brines exists in the Magma water plant or injection well. In other subsurface source water injection systems, the occurrence and activity of certain anaerobes, especially sp. desulfuricans, have caused water contamination in waters normally devoid of sulfides by generating hydrogen sulfide through the metabolic reduction of sulfate ions. This, in combination with the presence of ferrous ions, usually causes the precipitation of ferrous sulfide, a finely divided solid, the impairment capabilities of which are only too well known. There is no current evidence to support the belief that this type of problem will materialize. But the total exclusion of air contact, as would be the case in a closed (anaerobic) clarifier-filter system might provide a favorable environment for this type of problem. Fortunately, there are many effective, inexpensive bactericides available for brines. These have been developed over 3 decades of progress in combatting this problem, so the potential threat by anaerobes is of little consequence.

The addition of Salton Sea water, on the other hand, can be a source of diverse aerobic and anaerobic micro-and macroorganisms. Experience has shown that long lead-times are required for this type of problem definition and evaluation because of the lengthy culture times required for such studies, and because of the large number of species which must be identified in surface water sources. An effort directed toward at least an exploratory study of potential micro-and

THE EFFECTS OF MATRIX PERMEABILITY IMPROVEMENT ON INJECTION WELL CAPACITY.

macrobiologically generated problem areas should be initiated in the immediate future if a strong probability that the use of Salton Sea water, as make-up, exists.

Corrosion Problems in the Water-Wetted Metals Systems

The corrosion problem in the power recovery system has been examined intensely by LLL. A large effort toward providing suitable metallurgy for an acidified brine in the power plant has delineated many of the problem areas and proposed acceptable solutions to numerous types of corrosive attack. However, there has been relatively little effort directed toward defining the corrosion problems which might be encountered in the spent brine disposal system. Corrosion coupon test data, if it exists, has not been included in the reference material available for this report. Tests data evaluating thin film coatings (less than 0.008" thick), thick film coatings (0.008"-0.015" thick) and linings (fused epoxy, epoxy-coal tar, etc) have not been made available at this writing (if such tests were performed). These two items are specifically mentioned because it is through such an approach that solutions to salt water handling systems are normally developed in other industries.

Localized corrosion has been examined in the power plant, and other sources have reported that the occurrence of pitting erosion is not easily predictable, and that prevention of localized corrosion cannot be incorporated into design considerations. But design methods which have been very effective in preventing localized corrosion do in fact exist,* and a large body of information on salt water corrosion has been made available to the parties involved in the Niland project.** In brief, considerable attention has been directed toward the solution

* Reference 7, pp 20-21

** Reference 7, pp 9-42

of the most critical areas of corrosion, but insufficient data have been gathered for the spent brine treating and injection plant.

Fortunately, the data required to assess the corrosion problem, including the evaluation of coatings and linings, can be obtained in a few months by a coordinated field test approach. The corrosion survey techniques and coating evaluation test procedures are available through companies whose principal business is corrosion control. Often, such tests are performed gratis or for a nominal fee. Quite frequently, brine corrosion is controlled through the use of coatings and linings at the low temperatures ($T < 180^{\circ}\text{F}$) anticipated in the spent brine system, both on the surface and in the injection wells.

If pitting corrosion (other than crevice attack^{*}) is not encountered, the base corrosion rate of hypersaline brines is often less than that of sea water (see Figure 10). In such brines, the high ionic strength tends to subdue ionization at anodic (ferritic) areas of steel, and reduced slab corrosion rates are usually experienced

Pitting corrosion in non-crevice areas appears to be the most potentially damaging type of corrosive attack. Usually, this results in brine systems when patchy, rather than continuous layers of scale or corrosion products are deposited on the metal surfaces. Because the deposition characteristics of scale or corrosion product scale films are often of an uncertain nature, many water plants (and wells) use thin film coatings (spray-bake epoxies, phenol-formaldehydes, etc.), thick film coatings (fluidized bed epoxy powders, fused epoxy, etc.) or linings (cement, vitreous enamels, coal tar-epoxy, etc.).

One exception to the generally observed type of pitting corrosion is a devastating form of this type of attack known as trace oxygen corrosion (TOC).^{**}

* Reference 7, pp 20-21

** Reference 8, pp 45-49

THE CHARACTERISTIC BEHAVIOR OF SLAB CORROSION OF IRON AND STEEL RELATED TO TOTAL DISSOLVED SOLIDS CONTENT OF THE ELECTROLYTE. AS THE IONIC STRENGTH OF THE WATER INCREASES ABOVE THAT OF SEA WATER, THE REDUCED MASS TRANSFER RATE OF FERROUS IONS SUPPRESSES THE CELL REACTION.

Figure 10.

Where this has occurred, water handling systems, from the source to the injection well bottom, have been literally destroyed in a time span of a year or two. TOC is not controllable with inhibitors or cathodic protection, so if TOC is found to be taking place after a plant is on stream, interim protective measures do not work at all. The probability of TOC occurring in a closed clarifier-filter type system is almost nil. However, the presently unknown characteristics of the Salton Sea brine with regards to TOC requires that this problem be evaluated quickly, regardless of whether split or combined treating or injection systems are to be provided. Detecting and treating TOC is a routine corrosion engineering function. The fact that TOC proceeds at an extremely rapid rate requires that it be assessed before a plant is put on stream.

Regardless of how well the water facilities are designed and operated, there will always be maintenance problems with any brine handling system. Usually, the cost of maintenance is acceptably low; but the problem never completely disappears. This is the "name of the game" in brine handling systems, whatever or wherever they might be.

To insure that a reasonably low-maintenance system is provided, the coupon tests for base rate data, and for coating evaluation should be initiated at an early date. And the TOC studies are, of course, an item of the highest priority.

The Effects of Fluid Recharge

Injection for a 50 MW plant will be about 86,000 b/d without makeup, or just under 110,000 b/d with Salton Sea or other makeup, and would correspondingly require either 3 or 4 shallow zone injection wells. Assuming a well as described earlier with 300 net feet of injection sands, operating at 25,000-30,000 b/d per well, $\phi = 0.20$, and a 15 year life span, the interference radius at the end of the 15 years calculated to be $r_e = 2000$ feet. This equates to an injector spacing

of one well per 280 acres. If a 600 foot net injection pay is used, and all other conditions are unchanged, then $r_e = 1425$ feet, and the well spacing is reduced to one well per 160 acres (or four wells per section). If a more dense spacing were required, then injection pressures can be expected to rise slowly when interference occurs. The lease arrangements in the Niland project are not included in this report, but the r_e values generated for the conditions stated can be used to ascertain whether or not an interference problem is anticipated.

Injection Well Completion Considerations

The injection well completion problems which have been reported in the Niland and nearby KGRA locations are twofold. First, the use of non-damaging completion fluids has been sparse. This has resulted in the drilling and completion of injectors which are impaired before injection commences. If the problem is not remedied, water injection can compound the problem by driving the impairment into the rock, instead of removing it. Second, sand control has been either poor or non-existent. In at least one nearby project, the major injection impairment was ascertained to be sand fill caused by back-heaving when injectors were shut in for surface equipment repairs, etc.

The shallow sands in the Niland KGRA are mostly clean, well sorted, well rounded, unconsolidated, fine to medium grain size. These are ideal for injection, but the properties which make them desirable also make the sands vulnerable to damage from improperly selected completion fluids, and susceptible to failure from lack of sand control.

The use of relatively non-damaging completion fluids and sand control methods is neither complicated nor expensive. At least an exploratory assessment of these requirements is in order. Nevertheless, the shallow, large diameter-cased wells with through-casing injection appear to be entirely suitable for the project.

The Risk Analysis

A risk analysis predicated on a 50 MW geothermal power plant at Niland with a clarifier-filter water treating system and shallow injection wells follows, using the following five scenarios:

- 1) No geothermal steam condensate recombination, and successful demonstration of injection for several months into a new well on a 10 MW scale.
- 2) Salton Sea makeup and successful demonstration for several months of injection into a new well on a 10 MW scale.
- 3) Same as scenario No. 1, except without a successful demonstration on a 10 MW scale.
- 4) Same as scenario No. 2, except without a successful demonstration on a 10 MW scale.
- 5) Same as scenario No. 2, except that Salton Sea makeup is treated in a separate surface system, and injected into a dual-zone injection well along with the geothermal brines.

The probabilities that a listed problem will defeat the power generation project have been assigned values as follows:

Low = 0-30 per cent

Medium = 30-70 per cent

High = 70-100 per cent

The priority of any problem-scenario pair is indicated by the probability of defeat capability: Without exception, those marked "high" should be given immediate consideration if that problem-scenario pair is a viable consideration. The construction of a 50 MW plant would not be advisable until the problem had been reduced to an acceptable level. Problems assessed as "Medium" can be considered for evaluation in a field test prior to the construction of a 50 MW plant without risking irreversible or severe damage. The "low" items group problem-scenario

pairs which may present modest operating problems, and need no attention unless they materialize.

Conclusions

Scenarios (1) and (5) have the lowest risk. Scenarios (2) and (3) have a higher, but possibly acceptable risk level. Scenario (4) is a high risk operation, and its adoption is not recommended.

TABLE I - THE RISK ANALYSIS

<u>Problem</u>	<u>Probability of Defeating the Project</u>				
	Scenario Number				
	1	2	3	4	5
1. Loss of injectivity caused by suspended solids	Low	Medium	Medium	High	Low
2. Loss of injectivity caused by injection-reservoir water incompatibility	Low	Low	Low	Low	Low
3. Loss of injectivity caused by injection of supersaturated water	Low	Medium	Low	High	Low
4. Loss of injectivity caused by cooling effects of injection water in the reservoir	Low	Low	Low	Low	Low
5. Loss of injectivity caused by vapor breakout in the injected water	Low	Medium	Low	Medium	Low
6. Loss of injectivity caused by solubilization of reservoir rock	Low	Low	Low	Low	Low
7. Loss of injectivity and other problems caused by biological contamination	Low	Medium	Low	High	Low
8. Severe damage to plant metals by trace oxygen corrosion	Low	Medium	Low	High	Low
9. Severe damage to plant metals by other corrosion failures	Low	Medium	Low	Medium	Low
10. Loss of injectivity through effects of fluid recharge	Low	Low	Low	Low	Low
11. Well failure caused by inadequate completion design	Low	Medium	Low	High	Low

REFERENCES

1. Austin, A. L., et.al., The LLL Geothermal Energy Program Status Report, UCRL*-50046-76, April, 1977.
2. Chan, M. A., et. al., Subsurface Structure of the Southern Portion of the Salton Sea Geothermal Field, UCRL-52354, November, 1977.
3. Goldberg, A., et. al., Pitting Corrosion and Scaling of Carbon Steels in Geothermal Brine, UCRL-79508, August, 1977.
4. Harrar, J. E., et.al., Effects of Organic Additives on the Formation of Solids from Hypersaline Geothermal Brine, UCRL-80970, March, 1978.
5. Harrar, J.E., et.al., Field Electrochemical Measurements of Corrosion Characteristics of Materials in Hypersaline Geothermal Brine, UCRL-52376, December, 1977.
6. Hill, J.H., et.al., Sampling and Characterization of Suspended Solids in Brine from Magmamax #1 Well, UCRL-79007, June, 1977.
7. Jorda, R.M., et.al., State of the Art in Well Completion Technology as Applied to Geothermal Development, Completion Technology Company, Houston, Under Sandia Laboratories Contract #05-6199, October, 1977.
8. Jorda, R.M., An Engineering Study of Water Reinjection for Geothermal Systems, Completion Technology Company, Houston, Under Sandia Laboratories Contract #05-6199, January, 1978.
9. Jorda, R.M., et.al., An analysis of Water Reinjection at the Niland Geothermal Test Site, Completion Technology Company, Houston, Under Sandia Laboratories Contract #05-6199, May, 1978.
10. Jorda, R.M., A Mathematical Model of Damage Collars in Water Reinjection Wells, Completion Technology Company, Houston, Under Sandia Laboratories Contract #05-6199, May, 1978.
11. Jorda, R.M., et.al., A Performance Evaluation of Magma Power Company's Reinjection Well #46-7 at the East Mesa KGRA, California, Completion Technology Company, Houston, Under Sandia Laboratories Contract #13-0336, (to be published October, 1978).
12. Quong, R., Scaling Characteristics in the GLEF at Niland, California, UCRL-52161, November, 1976.
13. Schroeder, R.C., Reservoir Engineering Report for the Magma-SDG&E Geothermal Experimental Site near the Salton Sea, California, UCRL-52094, July, 1976.
14. SPE Proceedings, International Symposium on Oilfield and Geothermal Chemistry, UCSD, June, 1977.

* UCRL refers to reports issued by the Lawrence Livermore Laboratory, University of California, Livermore.

15. Tardiff, G.E., Using Salton Sea Brines for Electrical Power, UCRL-79468, May, 1977.
16. Tewey, J.D. Geologic Characteristics of a Portion of the Salton Sea Geothermal Field, UCRL-52267, April, 1977.
17. Transactions, GRC, Volume II, July, 1978.

LAWRENCE BERKELEY LABORATORY - UNIVERSITY OF CALIFORNIA		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	1 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	
PROGRAM - PROJECT - JOB				
Geothermal Energy				

Niland GLEF Performance Data

TITLE

A Summary of the Data Retrieval and Reduction Programming

INTRODUCTION

This report is a documentation of what has been done related to the programming within Niland GLEF Test Program. The LBL responsibility was to provide computerized computations of various characteristics of the Niland Geothermal Experimental Loop Facility (GLEF), tabulate raw and reduced data and to create a data base for storage of raw and reduced data. Experimental data monitored on the GLEF includes 127 data points. 100 measurements were monitored automatically by a Doric Digitrend data logger at hourly intervals. Fourteen measurements called "hand logged data" were monitored manually at two hours intervals and 13 measurements called "chemistry data" were monitored manually at daily intervals. Data logger data was delivered to LBL on tape recorder cassettes; hand-and-chemistry-data was on special forms. The calculations done in the program are based on a test program, written by Bechtel in Ref. 1.

DATA RETRIEVAL

There are 100 channels on the Doric Datalogger on which to record instrument readings relevant to the test program set up by Bechtel. The Datalogger recorded the measurements of pressure, temperature, flow rates, etc., at various points throughout the facility every hour. Some less sensitive data, e.g., measurements of levels, concentrations, etc. were to be recorded by hand and entered into the sorted data list at LBL. Unfortunately, very few tests had their full complement of values needed to calculate heat and mass balance, heat transfer coefficients, boiling point elevation and other results required by the test program, as outlined by Bechtel and as programmed. However, the programs were written to trap that situation in which the necessary data was unavailable.

The subroutine used to retrieve the data basically allowed selection of data on the basis of seven parameters. These were: the date and time of an experiment, the stage (1 to 5), the stream (steam, brine, condensate, etc.), the measurand, (flow, temperature, pressure, etc.), the equipment (separators, heat exchangers, etc. to which the instruments were attached), and the instrument itself.

To tabulate the readings recorded on the datalogger cassettes, templates were made for 19 tables, each with several columns of related data. Each cassette was stipulated to record one task test only, since no agreement on how to designate the task-subtask-test on the cassette recorder was ever reached. The cassette recorded the date, time, and 99 channels, some of which were spares. Many times some channels were "open", and would be flagged to signal this state. In addition to the cassette, hand-logged data was to accompany the datalogger values, to enable the required computations and tabulations to be done. For most test we received, there was no hand-logged data; the calculations were not done, but the tables were generated, the missing values. Flagging the recorded data, after being screened for validity, was stored with a unique label so that data for a specific experimental run could be retrieved as needed. The original intention to automate retrieval of data sets for any date/time/test set was not implemented, due to the paucity of complete data for most computational

LAWRENCE BERKELEY LABORATORY • UNIVERSITY OF CALIFORNIA.		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	2 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

purposes, and to the curtailment of the test program by SDG&E midway through the program development.

The need to accommodate for surging data in some of the instrument readings led to the development of a program to record many readings of a channel in one time-frame, and to allow the software program to average these readings to give a more reasonable value to the instrument that would be seen by one snapshot value. The tables program was modified to indicate which of the instruments were affected by the sub-interval-scan measurement technique. The permanent storage of the averaged values was not done, since we had only two (experimental) cassettes using the SIS method just before the plant was torn down for re-instrumentation (Jan., 1978).

It is possible for the engineer to retrieve all the readings from the cassette and all hand-logged data for each date/time recorded, and to do the calculations necessary for the Bechtel test programs, then to cycle through all the data, repeating the read-calculate sequence for each "snapshot". It is also possible to scan all the values recorded on one cassette for selected parameters and all times to get a table of values for each desired element over the test duration.

It is of course possible to process multiple cassettes during one computer run by merging the relevant data sets into one unit before beginning your computations. The only difficulty might be having too many date-time combinations for the allotted storage. The program tests for that, however there are three versions of the "PARAMS" data set (which identifies the attributes of each data channel), because the specifications of which instrument is attached to which channel were changed during the GLEF experiments. The various programs, data sets, and parameters are stored on 6250 BPI tape at the LBL Computer Center. Any questions should be directed to B. Levine, Ext. 5650. Questions about the engineering aspect of the GLEF project should be addressed to S. Mitina.

SUBROUTINES DESCRIPTION

In terms of engineering analysis the Bechtel test program is broken into 18 Tasks. In terms of the programming these Tasks fall into two categories:

1. Tasks which simply require a tabulation and display on the computer output of certain measurements specified for a particular task.
2. Tasks which require calculations, mostly thermodynamic, and tabulation and display of the results on the output.

Out of 18 Tasks originally included in the test program (Ref. 1), 14 of them were later deleted. The remaining 4 tasks are:

TASK 1, 2, 4 and 15.

TASK 1 is in the first category and Tasks 2, 4 and 15 in the second. The final

LAWRENCE BERKELEY LABORATORY • UNIVERSITY OF CALIFORNIA		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	3 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

product appears on the computer output in three sets of tables:

- 1) Test conditions
- 2) Test measurements
- 3) Test calculation results. (For Tasks 2, 4, 15)

"Test conditions" tables are a display of measurements recorded during each time interval of those parameters which are set before the plant starts to operate and which are kept stabilized during the test. "Test measurements" tables are a display of those measurements which characterize an actual performance of the plant or different equipment during the test under test conditions specified in task description. These measurements are preselected depending on the objective of a test. (Ref. 1). Because quality of Niland data received by LBL was generally poor and incomplete, an additional "error message" table was created. The purpose of this table is to print out malfunctioned instruments for which measurements were either absent or were not readable by the computer. Tables which display results of calculations are described below for each task. The samples of computer outputs for various tasks are given in Appendix on pages 22 - 28.

The equations used in the program are significantly different from those given in Bechtel test program (Ref. 1). It came as a result of the difference between the actual instrumentation on Niland Plant and that on which the Bechtel equations are based.

TASK 2

Task 2 was specified in Bechtel test program report as an overall heat and mass balance analysis at the plant. It was requested later to analyze behavior of noncondensable gases at the outlet of vessel V-6 (outlet of the plant). Overall heat and mass balance mass flow rate was calculated from:

$$W_1 + W_2 + W_3 + W_4 + W_5 = W_6 + W_7 + W_8 + W_9 + W_{11} \quad (1)$$

Heat flow rate was calculated from:

$$Q_1 + Q_2 + Q_3 + Q_4 + Q_5 = Q_6 + Q_7 + Q_8 + Q_9 + Q_{11} \quad (2) \text{ where}$$

W--- Mass flow rate measured at single measurement point.

Q--- Heat flow rate calculated for single measurement point.

LAWRENCE BERKELEY LABORATORY • UNIVERSITY OF CALIFORNIA		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	4 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

MEASUREMENT POINTS USED IN CALCUATIONS

Point 1	W ₁ - F1-6	Point 6	W ₆ - F4-2
	t ₁ - T1-3		t ₆ - T4-2
	P ₁ - P1-2		X ₆ - S4-1
Point 2	W ₂ - F1-7	Point 7	W ₇ - F4-6
	t ₂ - T1-6		t ₇ - T4-7
	P ₂ - P1-4		P ₇ - P4-4
Point 3	W ₃ - F1-1	Point 8	W ₈ - F1-4
	t ₃ - T1-2		t ₈ - T1-14
	X ₃ - S1-1		
Point 4	W ₄ - F1-2	Point 9	W ₉ - F5-1
	t ₄ - T1-5		t ₉ - T5-2
	X ₄ - S1-2		
Point 5	W ₅ - F5-1	Point 11	W ₁₁ - F1-3
	t ₅ - T5-1		t ₁₁ - T1-12
			P ₁₁ - P1-8

Numerical data for flow rate represent volumetric flow rate for all measurement points:

F1-6, F1-7, F-3 -- CFM
F1-1, F1-2, F5-1, F4-2 -- GPM

To obtain mass flow rate, the fluid density was calculated for each measurement point using subroutine Prop for water vapor (temperature and pressure specified), subroutine Prep for water on the saturation line (only temperature specified), and subroutine Prop for brine in a liquid phase (concentration, pressure and temperature specified).

For measurement point 11, density was calculated as the density of a mixture of saturated water vapor and noncondensable gas (CO₂). Equation (1) p. 2-23 given in Bechtel report could not be used for calculations because it was written on the assumption that the measured flow rate is a mass flow rate.

LAWRENCE BERKELEY LABORATORY • UNIVERSITY OF CALIFORNIA		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	5 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

Instead, the following procedure has been used:

$$\left. \begin{array}{l} P_{H_2O} \\ \rho_{H_2O} \end{array} \right\} \text{ from Prep (T1-12)}$$

$$P_{CO_2} = P_{1-8} - P_{H_2O}$$

$$\rho_{CO_2} \text{ - from Prop (T1-12, } P_{CO_2})$$

$$X_{H_2O} = P_{H_2O} / P_{1-8}$$

$$X_{CO_2} = P_{H_2O} / P_{1-8}$$

$$\rho_{mix} = X_{H_2O} \times \rho_{H_2O} + X_{CO_2} \times \rho_{CO_2}$$

$$\dot{M} = \rho_{mix} \times (F1-3)$$

In addition for noncondensables gases analysis:

$$\dot{W}_{H_2O} = X_{H_2O} \times F1-3$$

$$\dot{W}_{CO_2} = X_{CO_2} \times F1-3$$

$$\dot{M}_{H_2O} = \rho_{H_2O} \times \dot{W}_{H_2O}$$

$$\dot{M}_{CO_2} = \rho_{CO_2} \times \dot{W}_{CO_2}$$

All calculations are done for each data logger time interval. Tables of calculation results on a computer output include:

- 1) Overall heat and mass balance tables which print out calculated value of heat-and mass-flow rate in and out of the plant for each time interval and the percentage of nonbalance.
- 2) Volumetric and mass flow rate of steam and noncondensable gas CO_2 at the outlet of V-6 for each time interval.

LAWRENCE BERKELEY LABORATORY • UNIVERSITY OF CALIFORNIA.		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	6 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

The sample of computer output for task 2 given on pages 24, 27 and flow chart diagram is on Fig. 1 in the appendix.

TASK 4

Task 4 is concerned with scrubber performance analysis.

As described in Bechtel test program this includes:

- 1) Vapor pressure-drop across the scrubber
- 2) Calculated scrubber efficiency
- 3) Calculated vapor velocity across the scrubber

No vapor pressure drop calculation was required, since it was measured at each scrubber by differential pressure gage. Scrubber efficiency is calculated from

$$\Delta S = \frac{TDS_{inlet} - TDS_{outlet}}{TDS_{inlet}}$$

where TDS is concentration of total dissolved solids. For vapor velocity calculations, mixture of H₂O and CO₂ is treated as mixture of ideal gases, where H₂O component is saturated water vapor. Due to the fact that scrubbers V-8, V-9 and V-10 are not provided with flow meters on the vapor side, so called indirect measurements of flow rate have been utilized for vapor velocity calculations.

SCRUBBER V-8

Flows F1-3 (at the outlet of V-6) and F1-4 (at the outlet of E-5) are used in a program to calculate V-8 volumetric flow rate.

The following procedure is used:

- a) Mass flow rate at the outlet of V-6

$$\rho_{H_2O}^{V-6} - \text{from } \underline{\text{Prep}} \text{ at T1-12}$$

$$\rho_{CO_2}^{V-6} - \text{from } \underline{\text{Prop}} \text{ at T1-12, } P_{CO_2} = (P1-8) - P_{H_2O}, NX = 8$$

$$\dot{M}_{V-6} = \rho_{V-6}^{mix} \times F1-3$$

LAWRENCE BERKELEY LABORATORY - UNIVERSITY OF CALIFORNIA		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	7 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

b) Mass flow rate at the outlet of E-5

$\rho_{H_2O}^{E-5}$ from Prep at T1-14

$\rho_{CO_2}^{E-5}$ from Prop at T1-14, P1-6, D1-6, P_{H_2O}

$$\bar{M}_{E-5} = \rho_{E-5}^{mix} \times F1-4$$

$$\bar{M}_{V-8} = \bar{M}_{V-6} + \bar{M}_{E-5}$$

c) Volumetric flow rate and velocity at V-8

$\rho_{H_2O}^{V-8}$ - from Prep at T1-7

$\rho_{H_2O}^{V-8}$ - from Prop at T1-7, P1-5, P_{H_2O}

$$\bar{W}_{V-8} = \bar{M}_{V-8} \div \rho_{V-8}^{mix}$$

$$VEL_{V-8} = \frac{\bar{W}_{V-8}}{AREA_{V-8}}$$

SCRUBBER V-9

Volumetric flow rate for V-9 is measured by flow meter F2-2 located at the outlet of E-1A

$$VEL_{V-9} = \frac{(\bar{W}_{E-1A} \times \rho_{E1-A}) \div \rho_{V-9}}{AREA_{V-9}}$$

LAWRENCE BERKELEY LABORATORY - UNIVERSITY OF CALIFORNIA		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	8 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

Density ρ_{E1-A} is calculated for pure water vapor (no CO_2)

SCRUBBER V-10

Volumetric flow rate for V-10 is measured by flow meter F3-2 located at the outlet of the heat exchanger E-5.

$$VEL_{V-10} = \frac{(\bar{W}_{E-5} \times \rho_{E-5}) \div \rho_{V-10}}{AREA_{V-10}}$$

Density ρ_{E-5} is calculated for pure water (no CO_2)

SCRUBBER V-12

Volumetric flow rate for V-12 is measured at the outlet of V-12 by flow meter F4-3

$$VEL_{12} = \frac{F4-3}{AREA_{V-12}}$$

The crosssectional area of each scrubber is given in Appendix E (Ref. 1). The scrubber efficiency ΔS and vapor velocity VEL are calculated for each time interval in which Niland data was monitored by data logger and printed out in one table in the following order:

$VEL_{V-8}, \Delta S_{V-8}, VEL_{V-9}, VEL_{V-10}, \Delta S_{V-10}, VEL_{V-12}, \Delta S_{V-12}$

VEL - in. cu. ft/min.

ΔS - Dimensionless

Flow chart diagram for Task 4 is given on Fig. 2 in the Appendix

TASK 15

In Bechtel test program task 15 is defined as determination of Non-equilibrium allowance, Boiling Point Elevation and Stage flash down.

LAWRENCE BERKELEY LABORATORY - UNIVERSITY OF CALIFORNIA		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	9 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

Calculation procedure described in Ref. 1 (pages 2-100) is based on the assumption that Boiling Point Elevation (BPE) will be measured by Cottrell Apparatus. This instrument has not been installed. It was found possible as an alternative to estimate BPE and Δ'_b (non-equilibrium allowance) from two available measurements (for each stage): temperature of the brine leaving the stage and stage vapor pressure.

Equations in a program are:

$$\Delta'_b = T_{\text{brine}}^{\text{meas}} - (TS_{\text{vap}} + \text{BPE})$$

$$\text{BPE} = T_{\text{brine}}^{\text{meas}} - (TS_{\text{wat}}), \text{ where}$$

$T_{\text{brine}}^{\text{meas}}$ - bulk brine temperature, measured.

TS_{vap} - The saturated water vapor temperature calculated from subroutine Prep at measured stage vapor pressure.

TS_{wat} - Saturated water (liquid phase) temperature calculated from subroutine Prep at the pressure corresponding to brine temperature $T_{\text{brine}}^{\text{meas}}$ assuming brine being in a saturated liquid phase.

Measurements used for calculations

Vessel V-1 - P1-2, T1-2, S1-1
 Vessel V-4 - P1-4, T1-5, S1-2
 Vessel V-7 - P2-1, T2-2, S2-1
 Vessel V-14 - P3-1, T3-2, S3-1
 Vessel V-11 - P4-1, T4-2, S4-1

Stage flashdown is defined and calculated as a difference in temperatures of a brine leaving two successive stages. The values of BPE, Δ' and stage flashdown are calculated for each time interval in which Niland data was monitored by data logger. The results on the output printed in two tables:

- 1) Stage flashdown
- 2) Boiling point elevation and non-equilibrium allowance.

Examples are in the Appendix. Flow chart diagram for Task 15 is on Fig. 3

LAWRENCE BERKELEY LABORATORY UNIVERSITY OF CALIFORNIA.		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	10 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

The GLEF test program as originally planned placed heavy emphasis on measuring the performance of the steam/working fluid heat exchangers. Because of the major programming effort required to be able to reduce this heat transfer data, LBL began working immediately on Task 3. However, this task was one of the fourteen deleted from the test plan, and our data reduction program for Task 3 was never run with actual field data. But because of the amount of effort expended on this, a description of the Task 3 program is given in the following paragraphs.

TASK 3

Task 3 is designed to determine clean tube heat-transfer coefficients for all heat exchangers (except E4 A&B) based on the real measurements and to compare these results with the predictions of analytical methods.

Specifically for each heat exchanger it is required to be calculated based on the real measurements:

- 1) Heat exchanger duty
- 2) Mean temperature difference
- 3) Overall heat transfer coefficient

Using analytical method:

- 1) Shell and tube heat transfer coefficients
- 2) Fouling and wall resistance
- 3) Overall heat transfer coefficient

Heat exchangers E-1A, E-1B and E-1C are calculated in subtask A of Task 3, heat exchanger E-5--in subtask B and heat exchangers E-2 and E-3 are calculated in subtask C.

Computer code for Task 3 is written in two subroutines:

- 1) Subroutine Task 3AB for E-1A, E-1B, E-1C and E-5.
- 2) Subroutine Task 3C for E-2 and E-3.

All thermodynamic calculations in the program are done by subroutine GEOTHM and transport properties are calculated by subroutine Trans.

The exception is a specific heat $C_p^{CO_2}$ of noncondensable GAS CO_2 .

$C_p^{CO_2}$ was calculated from:

$$C_p^{CO_2} = -0.89286 + 7.2967 \times T^{0.5} - 0.98074 \times T + 5.7835 \times 10^{-3} \times T^2$$

where T is in degree Rankine

LAWRENCE BERKELEY LABORATORY • UNIVERSITY OF CALIFORNIA		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	11 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

(Ref. 3)

The equations given in the report for heat exchangers E-1A, E-1B, E-1 and E-5 provide sufficient basis for mathematical modeling of heat transfer for these heat exchangers. They deal with a single phase flows on both sides of heat exchangers without noncondensables. The equations were programmed in a more or less straight forward way.

For subroutine Task 3C the equation given are sketchy and additional mathematical modeling has been done due to the following factors:

1. The balance equations for E-2 and E-3 are written for mass flow rate known for each measurement point. The real flow meter on Niland measure volumetric flow rates for steam of E-2 and E-3 flow are installed at the outlet of E-5 and V-6.
2. F-correction factor for cross-flow type heat exchanger is given as a graphical three dimensional function which can not be used in computer computations. The appropriate equations for "F" were obtained later from Bechtel.
3. Kern method for heat release curve calculations which are used to determine weighted logarithmic mean temperature difference (LMTD) (Ref. 1 p. 248, Ref. 2) required more information about thermodynamic properties of the fluid, than what actually was available from Niland measurements. For each E-2 and E-3 heat exchanger the only measured values are temperature and pressure at the inlet and at the outlet of the heat exchanger. Since in both heat exchangers we have water vapor condensing at the presence of noncondensable gases this information is insufficient for understanding of the heat and mass-transfer process.

To calculate balance equation for E-2 and E-3 mass flow rate was estimated from:

$$\dot{M}_{\text{steam}} = \frac{(F1-3) \times \rho_{T1-12, P1-8} + (F1-4) \times \rho_{T1-14, (P1-9 + \Delta P1-6)}}{\rho(T1-7, P1-5)}$$

Where,

- $\dot{M}_{\text{steam}}$ - steam mass flow rate through E-2 and E-3
- F1-3 - volumetric flow rate, measured at the outlet of vessel V-6
- T1-12, P1-8 - temperature and pressure, measured at the outlet of V-6
- ρ - density
- F1-4 - volumetric flow rate, measured at the outlet of E-5
- T1-14 - temperature, measured at the outlet of E-5
- $\Delta P1-6$ - pressure drop measured at E-5
- P1-9 - pressure, measured at the inlet of E-5

LAWRENCE BERKELEY LABORATORY • UNIVERSITY OF CALIFORNIA.		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	12 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

The equations used for F-correction factor are for one or more single shell pass exchanger in series.

$$R \neq 1$$

$$P_{n-2n} = \frac{1 - \left(\frac{PR-1}{P-1}\right)^{1/n}}{R - \left(\frac{PR-1}{P-1}\right)^{1/n}}$$

$$P = \frac{t_2 - t_1}{T_1 - t_1}$$

$$R = \frac{T_1 - T_2}{t_2 - t_1}$$

where

n = no. shells series

T = hot fluid

t = cold fluid

$$F_{n-2n} = \frac{\frac{(R^2 + 1)^{1/2}}{R-1} \ln \left(\frac{1-P_{n-2n}}{1-RP_{n-2n}} \right)}{\ln \left\{ \frac{2/P_{n-2n} - 1-R + (R^2+1)^{1/2}}{2/P_{n-2n} - 1-R + (R^2+1)^{1/2}} \right\}}$$

For ABS $(R-1) < .002$

$$P_{n-2} = \frac{P}{n-P(n-1)}$$

$$F_{n-2n} = \frac{\sqrt{2} \left(\frac{P_{n-2n}}{1-P_{n-2n}} \right)}{\ln \left\{ \frac{2/P_{n-2n} - 1-R + (R^2+1)^{1/2}}{2/P_{n-2n} - 1-R - (R^2+1)^{1/2}} \right\}}$$

To calculate heat release curves several assumptions have been made:

1. Mixture of water vapor and CO₂ is a mixture of ideal gases and independent substances.

LAWRENCE BERKELEY LABORATORY • UNIVERSITY OF CALIFORNIA.		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	13 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

2. Pressure drop along the heat exchanger on both sides is equal to zero.
3. Steam entering heat exchanger E-3 is saturated water vapor (no super-heat, no NaCl_2).
4. At each boundary point between two successive increments on the heat release curve the mixture of condensing water vapor and CO_2 is a mixture of the independent components: saturated water vapor, water in saturated liquid phase and CO_2 . The difference from Kern example is that he considers water vapor condensing at each boundary point and treats flow as a two-phase fluid and we assume that part of vapor already condensed on the way from previous boundary point to one which is presently calculated.

This assumption permits calculating heat release curves without knowing enthalpy and quality at each boundary point. The subroutine Task 3 has been written, debugged and run for the design case, but never for the real test because, as was mentioned before, the part of the test program concerning heat exchangers performance analysis was cancelled. The flow chart diagrams for subroutines Task 3AB and Task 3C are on Fig. 4 and 5 in the Appendix.

TASK 1

The purpose of Task 1 in the test program is to analyse operational stability of the flash/binary process; plant response to transients and upsets.

As was mentioned above no calculations were involved in this task. Subroutine Task 1 generates "test conditions" and "test measurements" tables for each subtask and test described in Bechtel report.

LAWRENCE BERKELEY LABORATORY • UNIVERSITY OF CALIFORNIA		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	14 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

REFERENCE

1. Bechtel Corporation, "Detailed Program for the Niland Geothermal Test Facility", Final Report, San Francisco, California, 1976.
2. Donald Q. Kern "Process Heat Transfer", McGraw-Hill Book Company, 1950.
3. Gordon T. Van Wyen, "Fundamentals of Classical Thermodynamics", P. 684, 1973.

LAWRENCE BERKELEY LABORATORY • UNIVERSITY OF CALIFORNIA.		CODE	SERIAL	PAGE
ENGINEERING NOTE		GT11-03	M5236	15 of 32
AUTHOR	DEPARTMENT	LOCATION	DATE	
S. Mitina, B. Levine	Mechanical Engineering	Berkeley	September 18, 1978	

APPENDIX

FIG 1 TASK 2 FLOW CHART DIAGRAM

FIG 2 TASK 4 FLOW CHART DIAGRAM

M5236

Page 18 of 32

FIG 3 TASK 15 FLOW CHART DIAGRAM

FIG. 4. TASK 3AB FLOW-CHART DIAGRAM.

FIG. 6 NILAND GLEF FLOW DIAGRAM

DATA LOGGER POINTS
 T TEMP 30 pt.
 F FLOW 10 pt.
 P PRESSURE 20 pt.
 Δ ΔP 10 pt.
 V VALVE

GEOTHERMAL LOOP EXPERIMENTAL FACILITY DATA LOGGER INSTRUMENTATION (TYPICAL FLOW DIAGRAM)			
SAN DIEGO GAS & ELECTRIC CO.			
DATE: 10/1/77	BY: J. W. S.	REV: 12	BY: B
PROJECT: H.E.R.	NO: 10-16-77	ME: 5500	

TEST CONDITIONS

	V-1	V-4	V-7	V-14	V-11	V-13	E-3
TIME	P1-2	P1-4	P2-1	P3-1	P4-1	P4-4	P1-7
MM.MIN.SEC.	PSIG	PSIG	PSIG	PSIA	PSIG	PSIA	PSIG
TASK 15 SUBTASK-TEST 5							
170707							
11:59:29	72.800	.200	56.140	24.250	22.940	17.470	64.600
12:59:29	42.100	.200	36.240	14.410	22.990	17.940	-15.600
13:59:29	62.900	.200	71.700	33.290	23.000	18.540	-53.200
14:59:29	71.100	-.200	47.710	32.420	13.700	23.800	-71.400
15:59:29	63.600	-.200	69.390	36.780	-1.660	24.000	-75.300
16:59:29	143.300	-.200	65.630	28.840	7.820	24.420	41.200
17:59:29	159.900	-.300	59.460	18.860	-9.850	23.100	77.000
18:59:29	155.000	-.300	58.830	29.090	-14.690	22.210	81.000
19:59:29	159.300	.500	63.330	30.550	-14.570	21.830	84.100
20:59:29	160.700	1.300	58.690	35.860	22.960	21.320	-60.700
21:59:29	164.200	2.000	61.210	30.570	22.960	21.190	-6.700
22:59:29	165.700	2.300	63.570	31.160	22.950	20.770	-70.600
23:59:29	162.600	1.700	67.220	32.780	17.260	20.570	-39.100
170710							
00:59:29	162.200	1.600	65.620	33.320	22.940	20.360	-83.700
01:59:29	159.500	1.800	65.930	32.910	22.940	11.910	-85.800
02:59:29	156.900	2.900	75.030	34.990	22.940	8.870	-92.800
03:59:29	14.900	2.300	1.450	12.980	22.930	8.780	-127.100
04:59:29	137.300	1.500	80.810	37.240	22.920	9.020	-140.200
05:59:29	141.800	1.800	74.440	29.680	22.920	9.270	-147.700
06:59:29	156.500	3.500	62.800	32.080	22.920	12.060	-145.200
07:59:29	167.800	2.100	56.740	28.750	22.930	11.890	-76.800
08:59:29	136.600	1.700	60.440	29.250	22.930	11.820	-24.800
09:59:29	120.900	1.500	59.790	29.360	22.940	11.860	45.500
10:59:29	152.400	1.400	54.820	27.350	4.930	11.950	70.400
11:59:29	144.700	2.600	53.890	27.200	-6.360	11.970	83.000
12:59:29	150.500	1.500	52.030	27.710	11.350	11.980	83.900
13:59:29	151.400	1.400	54.130	27.590	23.020	12.100	81.900
14:59:29	149.900	.600	54.210	28.120	23.010	11.950	82.400
15:59:29	150.200	.400	56.090	28.130	15.410	12.010	80.700
16:59:29	150.700	-.200	54.230	28.440	12.230	12.040	81.000
17:59:29	150.300	.300	51.680	27.880	6.960	12.030	82.800
18:59:29	150.000	.300	57.440	27.130	7.570	12.030	86.600
19:59:29	150.300	-.300	57.470	29.310	22.490	11.920	89.000
20:59:29	153.300	-.500	56.380	29.050	22.970	11.800	90.500
21:59:29	153.200	-.400	57.100	28.730	22.950	11.920	21.900
22:59:29	150.700	-.500	56.700	29.170	22.950	11.880	-44.600
23:59:29	150.200	-.300	57.230	29.330	22.940	11.920	9.000
170705							
00:59:29	150.700	-.200	57.840	29.730	22.940	11.880	-42.700
01:59:29	133.700	-.200	56.580	29.730	22.940	11.900	-3.600
02:59:29	138.600	-.200	57.710	28.770	22.930	11.860	-60.600
03:59:29	153.100	-.200	71.720	34.430	22.930	11.350	-33.500
04:59:29	154.700	-.200	55.780	28.920	22.930	12.080	-78.100

TEST MEASUREMENTS

VESSEL V-1

TIME MM:SS.SEC	F1-6 GPM	T1-3 FAHR	P1-2 PSIG	T1-2 FAHR	S1-1 PPH	N/A FAHR
TASK 15 300 TASK-TEST 5						
770707						
11:55:29	-5999.500	321.000	72.800	322.700	-777.700	
12:55:29	-5999.500	295.400	42.100	287.400	-777.700	
13:55:29	-5999.500	316.200	62.900	319.400	-777.700	
14:55:29	-5999.500	318.600	71.100	322.600	-777.700	
15:55:29	-5999.500	313.800	63.800	318.200	-777.700	
16:55:29	-5999.500	362.200	143.300	376.000	-777.700	
17:55:29	-5999.500	370.500	159.900	376.900	-777.700	
18:55:29	-5999.500	268.700	155.600	375.200	-777.700	
19:55:29	-5999.500	369.500	159.300	377.500	-777.700	
20:55:29	-5999.500	369.200	140.700	377.200	-777.700	
21:55:29	-5999.500	370.200	164.200	378.900	-777.700	
22:55:29	-5999.500	369.000	165.200	378.700	-777.700	
23:55:29	-5999.500	369.300	152.000	377.400	-777.700	
770708						
00:55:29	-5999.500	369.000	162.200	377.000	196923.000	
01:55:29	-5999.500	371.400	159.500	375.500	196923.000	
02:55:29	-5999.500	371.400	158.900	376.600	196923.000	
03:55:29	-5999.500	272.400	14.900	257.000	196923.000	
04:55:29	-5999.500	355.400	137.300	355.000	196923.000	
05:55:29	-5999.500	369.700	161.800	377.400	196923.000	
06:55:29	-5999.500	366.600	154.500	375.100	196923.000	
07:55:29	-5999.500	369.700	140.200	377.100	196923.000	
08:55:29	-5999.500	355.200	136.800	364.700	196923.000	
09:55:29	-5999.500	354.100	126.900	356.400	196923.000	
10:55:29	-5999.500	368.500	153.400	373.600	196923.000	
11:55:29	-5999.500	269.700	149.700	372.700	196923.000	
12:55:29	-5999.500	369.700	150.500	372.700	196923.000	
13:55:29	-5999.500	370.000	151.800	373.100	196923.000	
14:55:29	-5999.500	369.200	149.900	373.100	196923.000	
15:55:29	-5999.500	368.000	150.200	373.300	196923.000	
16:55:29	-5999.500	368.400	150.000	373.300	196923.000	
17:55:29	-5999.500	369.100	150.200	373.000	196923.000	
18:55:29	-5999.500	369.900	150.000	372.900	196923.000	
19:55:29	-5999.500	368.100	153.300	372.300	196923.000	
20:55:29	-5999.500	369.200	153.300	373.100	196923.000	
21:55:29	-5999.500	366.800	153.200	373.400	196923.000	
22:55:29	-5999.500	369.400	150.700	373.700	196923.000	
23:55:29	-5999.500	369.900	150.200	373.600	196923.000	
770709						
00:55:29	-5999.500	369.500	153.700	373.100	-777.700	
01:55:29	-5999.500	359.600	133.900	366.200	-777.700	
02:55:29	-5999.500	368.600	158.600	376.100	-777.700	
03:55:29	-5999.500	367.600	153.100	372.800	-777.700	
04:55:29	-5999.500	369.100	154.700	375.300	-777.700	
05:55:29	-5999.500	369.700	155.400	374.800	-777.700	
06:55:29	-5999.500	369.600	155.100	374.600	-777.700	
07:55:29	-5999.500	370.500	154.800	375.900	-777.700	
08:55:29	-5999.500	369.200	153.800	374.300	-777.700	
09:55:29	-5999.500	369.400	152.100	374.200	-777.700	
10:55:29	-5999.500	367.900	153.300	373.900	-777.700	

FIG. 8 "TEST MEASUREMENTS" TABLE

VOLUMETRIC AND MASS FLOW RATES OF STEAM AND INCONDENSABLES AT THE OUTLET OF V-6

TIME	WAT. VOL. FL.	CO2 VOL. FL.	TCT VOL. FL.	WAT. MAS. FL.	CO2 MAS. FL.	TOT. MAS. FL.
	(	CU. FT. PER HOUR	)	(	LB. PER HOUR	)
770805						
13:57:14	1066.050	18895.950	19962.000	17.362	13333.027	13350.390
14:57:14	1872.581	32297.419	34170.000	31.764	23083.023	23114.787
15:57:14	1246.321	16709.669	19956.000	23.189	12678.861	12702.050
16:57:14	1267.283	21608.717	22896.000	21.788	14999.748	15021.536
17:57:14	1026.115	18751.885	19788.000	16.494	13188.063	13204.557
18:57:14	568.066	18705.934	19614.000	12.872	13352.391	13365.263
19:57:14	658.266	18547.734	19206.000	6.934	13467.647	13474.581
20:57:14	548.654	21619.346	22218.000	5.045	16095.707	16100.752
21:57:14	657.734	30298.266	30996.000	4.981	23119.572	23124.553
22:57:14	456.038	47063.992	48060.000	6.572	35769.930	35776.502
23:57:14	617.639	29754.361	30372.000	3.985	22536.114	22540.099
770806						
00:57:14	455.175	18140.805	18600.000	3.677	13986.554	13990.231
01:57:14	522.657	18223.143	18756.000	4.787	13760.394	13765.181
02:57:14	654.392	25133.698	25788.000	5.269	18922.125	18927.394
03:57:14	457.424	19163.536	19614.000	3.279	14609.473	14612.752
04:57:14	734.318	27561.682	28296.000	6.029	20673.543	20679.572
05:57:14	547.471	16022.529	16570.000	5.049	13438.836	13443.886
06:57:14	621.295	16070.795	16702.000	6.736	13525.412	13532.148
07:57:14	623.735	16165.215	16804.000	6.729	13311.840	13318.569
08:57:14	464.344	23050.656	23520.000	3.076	18059.096	18062.172
09:57:14	464.427	18460.573	18930.000	3.719	14043.726	14047.445
10:57:14	542.818	18848.182	19392.000	4.729	13946.765	13951.495
11:57:14	627.913	18830.087	19458.000	6.327	13809.680	13816.007
12:57:14	777.547	19178.952	19956.000	9.488	14022.095	14031.583
13:57:14	1066.050	18895.950	19962.000	17.362	13333.027	13350.390
770807						
15:57:14	1246.331	16709.669	19956.000	23.189	12678.861	12702.050
16:57:14	1267.263	21608.717	22896.000	21.788	14999.748	15021.536
17:57:14	1026.115	18751.885	19788.000	16.494	13188.063	13204.557
18:57:14	568.066	18705.934	19614.000	12.872	13352.391	13365.263

FIG. 9 TASK 2 CALCULATIONS RESULTS TABLE

STAGE FLASHDOWN

TIME	STAGE 1-2 (T1-5)-(T2-2)	STAGE 2-3 (T2-2)-(T3-2)	STAGE 3-4 (T3-2)-(T4-2)
1107:17			
11:54:29	-187.500	35.700	43.800
12:54:29	-165.100	35.300	23.000
13:54:29	-196.100	43.600	26.500
14:54:29	-185.600	40.200	107.900
15:54:29	-175.800	34.900	64.600
16:54:29	-151.500	46.200	57.400
17:54:29	-85.500	63.500	45.900
18:54:29	-86.700	39.000	66.800
19:54:29	-44.500	40.500	65.900
20:54:29	-86.500	29.600	72.400
21:54:29	-87.600	38.600	64.200
22:54:29	-88.600	39.600	65.200
23:54:29	-92.700	41.100	69.500
1107:14			
00:54:29	-91.200	40.400	70.800
01:54:29	-85.500	36.000	71.200
02:54:29	-95.900	41.900	73.100
03:54:29	-5.200	1.800	32.600
04:54:29	-101.700	42.100	73.400
05:54:29	-106.300	52.000	56.500
06:54:29	-92.800	40.100	61.400
07:54:29	-84.500	39.100	57.100
08:54:29	-36.100	40.600	59.000
09:54:29	-81.500	40.700	59.800
10:54:29	-82.300	40.900	55.500
11:54:29	-187.500	35.700	43.800
12:54:29	-165.100	35.300	23.000
13:54:29	-196.100	43.600	26.500
14:54:29	-185.600	40.200	107.900
15:54:29	-175.800	34.900	64.600
16:54:29	-151.500	46.200	57.400
17:54:29	-85.500	63.500	45.900
18:54:29	-86.700	39.000	66.800
19:54:29	-44.500	40.500	65.900
20:54:29	-86.500	29.600	72.400
21:54:29	-87.600	38.600	64.200
22:54:29	-88.600	39.600	65.200
23:54:29	-92.700	41.100	69.500
1107:11			
00:54:29	-91.200	40.400	70.800
01:54:29	-85.500	36.000	71.200
02:54:29	-95.900	41.900	73.100
03:54:29	-5.200	1.800	32.600
04:54:29	-101.700	42.100	73.400
05:54:29	-106.300	52.000	56.500
06:54:29	-92.800	40.100	61.400
07:54:29	-84.500	39.100	57.100
08:54:29	-36.100	40.600	59.000
09:54:29	-81.500	40.700	59.800
10:54:29	-82.300	40.900	55.500
11:54:29	-187.500	35.700	43.800
12:54:29	-165.100	35.300	23.000
13:54:29	-196.100	43.600	26.500
14:54:29	-185.600	40.200	107.900
15:54:29	-175.800	34.900	64.600

FIG 10 FLASH DOWN TABLES FOR TASK 15

553

554

FIG. 11 BOILING POINT ELEVATION AND NONEQUILIBRIUM ALLOWANCE TABLES FOR TASK 15.

[illegible]

BALANCE OF MASS AND HEAT FL RATES FOR THE PLANT

TIME	HEAT IN BTU/HR	HEAT OUT BTU/HR	DELTA H O/O	FLOW IN LB/HR	FLOW OUT LB/HR	O/O	DELTA FL
13*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
14*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
15*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
16*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
17*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
18*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
19*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
20*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
21*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
22*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
23*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
00*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
01*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
02*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
03*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
04*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
05*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
06*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
07*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
08*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
09*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
10*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
11*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
12*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
13*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
14*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
15*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
16*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
17*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
18*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
19*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
20*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						
21*57*14	THE CIRCUIT IS NOT CONNECTED FOR ONE OR MORE OF THE FOLLOWING INSTRUMENTS T1-3 P1-2 F1-6						

FIG. 12. EXAMPLE OF A TYPICAL ERROR MESSAGE TABLE, 555

TABLE 7. PARAMS ACCORDING TO NOVEMBER, 1977 PROFILE (CHEMISTRY PROFILE-CHANNELS REARRANGED AS NOTED WITH SOMETIMES NOV. 77
 SAME AS JULY 1977 UP TO CONCENTRATIONS (4.115)

1	FL 34	FI-1	1	RTIME	WOOLSEY	64	FL 34	FI-6	1	STEAM	V-1
2	FL 34	FI-2	1	RTIME	V-1	65	FL 34	FI-7	1	STEAM	V-4
3	FL 34	FI-3	1	STEAM	V-1	66	FL 34	FI-8	1	RTIME	V-7
4	FL 34	FI-4	1	RTIME	MAGNANAX	67	FL 34	FI-9	2	COND	E-1A
5	FL 34	FI-5	1	RTIME	V-4	68	FL 34	FI-10	3	RTIME	V-14
6	FL 34	FI-6	1	STEAM	V-4	69	FL 34	FI-11	3	COND	E-1B
7	FL 34	FI-7	1	STEAM	V-4	70	FL 34	FI-12	3	IC4	F-5
8	FL 34	FI-8	1	STEAM	F-3	71	FL 34	FI-13	3	SPARE	SPARE
9	FL 34	FI-9	1	IC4	F-3	72	FL 34	FI-14	4	RTIME	RTIME
10	FL 34	FI-10	1	COND	F-2	73	FL 34	FI-15	4	STEAM	V-12
11	FL 34	FI-11	1	IC4	F-2	74	FL 34	FI-16	5	CH	F-4A/B
12	FL 34	FI-12	1	NON-COND	V-5	75	FL 34	FI-17	1	STEAM	V-8
13	FL 34	FI-13	1	COND	F-5	76	FL 34	FI-18	1	STEAM	F-3
14	FL 34	FI-14	1	COND	F-5	77	FL 34	FI-19	1	IC4	F-3
15	FL 34	FI-15	1	IC4	F-5	78	FL 34	FI-20	1	STEAM	E-2
16	FL 34	FI-16	2	STEAM	V-7	79	FL 34	FI-21	1	IC4	F-2
17	FL 34	FI-17	2	RTIME	V-7	80	FL 34	FI-22	1	COND	F-5
18	FL 34	FI-18	2	STEAM	V-9	81	FL 34	FI-23	1	IC4	F-5
19	FL 34	FI-19	2	COND	F-1A	82	FL 34	FI-24	2	STEAM	V-9
20	FL 34	FI-20	2	IC4	F-1A	83	FL 34	FI-25	2	STEAM	F-1A
21	FL 34	FI-21	3	STEAM	V-14	84	FL 34	FI-26	2	IC4	E-1A
22	FL 34	FI-22	3	RTIME	V-14	85	FL 34	FI-27	3	STEAM	V-10
23	FL 34	FI-23	3	STEAM	V-10	86	FL 34	FI-28	3	STEAM	F-1B
24	FL 34	FI-24	3	COND	E-1A	87	FL 34	FI-29	3	IC4	E-1B
25	FL 34	FI-25	3	IC4	F-1B	88	FL 34	FI-30	4	STEAM	V-12
26	FL 34	FI-26	4	STEAM	V-11	89	FL 34	FI-31	4	STEAM	F-1C
27	FL 34	FI-27	4	RTIME	V-11	90	FL 34	FI-32	4	IC4	E-1C
28	FL 34	FI-28	4	STEAM	V-12	91	FL 34	FI-33	1	STEAM	F-2
29	FL 34	FI-29	4	COND	E-1C	92	FL 34	FI-34	1	COND	F-5
30	FL 34	FI-30	4	IC4	F-1C	93	FL 34	FI-35	5	IC4	F-4A/B
31	FL 34	FI-31	4	IC4	F-1C	94	FL 34	FI-36	5	SPARE	SPARE
32	FL 34	FI-32	4	COND	V-13	95	FL 34	FI-37	5	SPARE	SPARE
33	FL 34	FI-33	5	ATZ	CONTROL	96	FL 34	FI-38	5	SPARE	SPARE
34	FL 34	FI-34	4	RTIME	CONTROL	97	FL 34	FI-39	5	SPARE	SPARE
35	FL 34	FI-35	5	ATZ	AMTENT	98	FL 34	FI-40	5	SPARE	SPARE
36	FL 34	FI-36	5	CH	F-4A/B	99	FL 34	FI-41	5	SPARE	SPARE
37	FL 34	FI-37	5	CH	F-4A/B	100	FL 34	FI-42	5	SPARE	SPARE
38	FL 34	FI-38	5	IC4	F-4A/B	101	FL 34	FI-43	1	COND	V-8
39	FL 34	FI-39	5	IC4	F-4A/B	102	FL 34	FI-44	2	COND	V-9
40	FL 34	FI-40	1	RTIME	WOOLSEY	103	FL 34	FI-45	3	COND	V-10
41	FL 34	FI-41	1	2-PHASE	V-1	104	FL 34	FI-46	4	COND	V-12
42	FL 34	FI-42	1	RTIME	MAGNANAX	105	FL 34	FI-47	4	COND	V-10
43	FL 34	FI-43	1	2-PHASE	V-4	106	FL 34	FI-48	1	RTIME	V-1
44	FL 34	FI-44	1	STEAM	F-3	107	FL 34	FI-49	1	RTIME	V-4
45	FL 34	FI-45	1	IC4	F-3	108	FL 34	FI-50	2	RTIME	V-7
46	FL 34	FI-46	1	NON-COND	V-6	109	FL 34	FI-51	3	RTIME	V-14
47	FL 34	FI-47	1	IC4	F-5	110	FL 34	FI-52	4	RTIME	V-11
48	FL 34	FI-48	2	2-PHASE	V-7	111	FL 34	FI-53	4	RTIME	V-12
49	FL 34	FI-49	2	STEAM	F-1A	112	FL 34	FI-54	4	RTIME	V-13
50	FL 34	FI-50	2	IC4	F-1A	113	FL 34	FI-55	5	IC4	F-4A/B
51	FL 34	FI-51	3	2-PHASE	V-14	114	FL 34	FI-56	5	IC4	F-4A/B
52	FL 34	FI-52	3	STEAM	F-1B	115	FL 34	FI-57	1	RTIME	V-1
53	FL 34	FI-53	4	2-PHASE	V-11	116	FL 34	FI-58	1	RTIME	V-4
54	FL 34	FI-54	4	RTIME	RTIME	117	FL 34	FI-59	2	RTIME	V-7
55	FL 34	FI-55	4	STEAM	F-1C	118	FL 34	FI-60	3	RTIME	V-11
56	FL 34	FI-56	4	COND	V-13	119	FL 34	FI-61	4	RTIME	V-11
57	FL 34	FI-57	5	IC4	F-4A/B	120	FL 34	FI-62	1	STEAM	V-1
58	FL 34	FI-58	5	IC4	V-7	121	FL 34	FI-63	1	STEAM	V-8
59	FL 34	FI-59	5	SPARE	SPARE	122	FL 34	FI-64	2	STEAM	V-7
60	FL 34	FI-60	1	RTIME	V-1	123	FL 34	FI-65	2	STEAM	V-7
61	FL 34	FI-61	1	RTIME	V-4	124	FL 34	FI-66	3	STEAM	V-14
62	FL 34	FI-62	1	NON-COND	V-4	125	FL 34	FI-67	3	STEAM	V-10
63	FL 34	FI-63	1	COND	F-5	126	FL 34	FI-68	4	STEAM	V-11
						127	FL 34	FI-69	4	STEAM	V-11

FIG. 13 "PARAMS" ARRAY

1977
APRIL

CASSETTE

TEST

HANDLOG DATA

CHEMISTRY DATA

M5236

Page 29 of 32

1-4				
5	(3)	NONE	NONE	NONE
6				
7				
8	(4)	NONE	NONE	—
9				
10				
11				
12				
13	(5)	NONE	—	—
14				
15				
16				
17				
18	(7)	NONE	—	—
19				
20				
21				
22	(8)	NONE	—	—
23				
24				
25				
26				
27				
28				
29				
30	(9)	NONE	—	—
1977 MAY				
1				
2				
3				
4				
5				
6				
7				
8-10				
11				
12	(10)	NONE	—	—
13				
14				
15				
16	(11)	NONE	—	—
17				
18				
19				
20	(12)	NONE	—	—
21				
22				
23-31				
1977 JUNE				
1-30				
1977 JULY				
1				
2				
3	(13)	NONE	—	—
4				
5				
6				

1977 JULY	CASSETTE	TEST	HAND LOG: DATA	Chemistry DATA
7		TASK 1A1	65 M5236	Page 30 of 32
8	(14)	TASK 1B3		
9		TASK 2		
10		TASK 15-5		
11				
12				
13				
14				
15	(15)	TASK 1A3		
16				
17				
18				
19	(16)	NONE		
20				
21				
22				
23				
24				
25				
26				
27		TASK 1A2		
28	(17)	TASK 4-5		
29		TASK 15-6		
30				
31		TASK 1A3		
1	(18)	TASK 1A4 TASK 4-4		
2				
3				
4				
5				
6	(19)	TASK 1A5		
7				
8				
9				
10		TASK 4-6		
11	(20)	TASK 1B3		
12				
13				
14				
15				
16	(21)	NONE		
17				
18				
19				
20				
21				
22	(22)	NONE	NONE	NONE
23				
24				
25				
26	(23)	NONE	NONE	NONE
27				
28				
29				
30				
31				
1977 SEPTEMBER				
1				
2				
3	(24)	NONE	NONE	NONE
4				
5				
6				
7				
8				
9				
10	(25)	NONE		NONE
11				

1977
SEPTEMBER

15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30

1977
OCTOBER

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31

1977
NOVEMBER

1-30

1977
DECEMBER

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31

1978
JANUARY

1
2
3
4
5

TEST

HAND LOG DATA

CHEMISTRY DATA

NONE

M5236

Page 31 of 32

⊗
⊗
⊗
⊗
⊗

⊗
⊗
⊗
⊗
⊗

⊗
⊗
⊗

TASK 1 C 1
(WRONG FORMAT)

TASK 1 C 1
(WRONG FORMAT)

7.6.9

1978
JAN

CASSETTE

ICSI

HAND LOG DATA

CHEMISTRY DATA

M5236

Page 32 of 32

8
9
10
11
12
13
14
15
16
17

NONE

NONE

NONE

NONE

1978 31
FEBRUARY

1978 28.
MARCH 1

SCREENING ANTI-SCALANTS

FOR USE IN A GLEF

PREPARED BY

PAUL M. HENRY

NUS CORPORATION

SOUTHWEST ENVIRONMENTAL CENTER

14011 VENTURA BOULEVARD

SHERMAN OAKS, CALIFORNIA 91423

JUNE 1979

TABLE OF CONTENTS

	<u>PAGE</u>
I. SUMMARY	1
II. INTRODUCTION	2
III. DISCUSSION	3
A. DEVELOPMENT OF SCREENING TESTS	3
TABLE 1 - EVALUATION OF TESTS	5
FIGURE 1 - "HOT" TEST APPARATUS	7
B. SELECTING ANTI-SCALANTS	8
C. TESTING ANTI-SCALANTS	9
TABLE 2 - PROPRIETARY ADDITIVES SELECTED FOR TESTING	10
TABLE 3 - INITIAL SCREENING OF ANTI- SCALANTS	13
TABLE 4 - TESTING MOST PROMISING ANTI-SCALANTS	15
TABLE 5 - TESTS WITH VARYING MIXING TIME	16
TABLE 6 - TESTS WITH TWO FEED RATES INCREASED	17
TABLE 7 - RETESTING ALL SUBMITTED ANTI- SCALANTS AT FIVE-MINUTE PERIOD	19
TABLE 8 - RERUN OF ANTI-SCALANTS	20
TABLE 9 - TESTING ADDITIONAL ANTI-SCALANTS	21
TABLE 10 - SCREENING ANTI-SCALANTS BY "HOT" TEST	23
TABLE 11 - SECOND "HOT" TEST	24
TABLE 12 - COMPARISON OF BETZ POLYSPERSE AND CARBOWAX 14,000	26
IV. CONCLUSIONS AND RECOMMENDATIONS	27

I. SUMMARY

San Diego Gas and Electric asked NUS to develop a method for determining quickly if anti-scalants could be used to inhibit silica scale in a GLEF (Geothermal Loop Experimental Facility). This method was then to be used to screen anti-scalants for further testing in this application.

NUS developed several tests and selected two whose combined conditions simulated to a degree those of the GLEF. Selected anti-scalant materials obtained from suppliers were then screened.

The most promising of these materials were further tested and comparative studies were run on the two showing the most favorable results. The one exhibiting the most advantages, Betz Polysperse, was recommended for further testing in a plant trial.

II. INTRODUCTION

Extensive scaling of flash vessels, piping, and pumps in the GLEF (Geothermal Loop Experimental Facility) has long been a problem. Early investigations indicate that adding acid to the brine substantially reduces deposition in geothermal systems, but increases corrosion. Subsequent studies to find alternative solutions indicate that scaling can be reduced by chemical additives produced normally as anti-scalants to prevent precipitation of calcium carbonate.

Because testing and evaluating anti-scalants in the loop test has required considerable time, San Diego Gas and Electric engaged NUS Corporation to determine if methods for rapidly testing anti-scalants could be developed and then, using these tests, to evaluate the anti-scalants for their ability to reduce the rate of silica precipitation without inhibiting the clarification treatment process used on spent brine solutions. The latter requisite is necessary, because residual brine solutions from steam flashing are clarified to remove suspended matter before the brine is reinjected to prevent plugging of the strata. Reinjection is to prevent depletion of the geothermal source and to preclude land subsidence.

This report discusses the development of a screening test and results of the tests on anti-scalants. Composition of the anti-scalants tested and results of the tests are tabulated.

III. DISCUSSION

A. DEVELOPMENT OF SCREENING TESTS

Precipitation of silica and other materials, particularly metal salts, occurs rapidly in the flashing and depressurization process of the GLEF; however, when a cool sample of brine is taken, silica and other materials are stable for varying periods due to their supersaturated condition. Therefore, in developing a screening test to evaluate anti-scalants, it was necessary to use agitation, seeding, oxidation, and depressurization and flashing to cause, if possible, silica precipitation in a short time by simulating to some extent system conditions. Procedures were established using each of these practices.

For a rapid-mixing test, a sample of cooled brine was taken from the well head and 250 ml placed in a high speed blender. The blender was set at medium speed for five minutes. After the mixing, an aliquot (10 ml) of brine was drawn off and run through a 0.45 micron millipore filter. The filtrate was acidified and diluted to 100 ml to be tested for silica on the atomic absorption spectrophotometer. This is the standard procedure used by San Diego Gas and Electric to determine soluble silica. The remaining brine sample was placed in a bottle, the free space purged with nitrogen, and the sample shelved for future visual observation.

For the seeding experiment, a sample of clarifier sludge was taken from the operating clarifier of the GLEF and used to start precipitation. Clarifier

sludge (0.5 ml and 1.0 ml) was introduced into two separate samples of well head brine. In one sample, the bottle was simply inverted to mix the clarifier sludge; the second sample was mixed in the blender for five minutes.

In the method for oxidation, chlorine was introduced into the sample.

In evaluating these procedures, we observed that these tests were run shortly after the GLEF was started up and, therefore, some variation is apparent in constituents of the brine. Blank readings confirmed the variation of silica content; soluble silica ranged from 90 to 290 ppm while total silica varied from about 280 to 370.

The filtered sample tests (Table 1) show that both the rapid-mixing and the sludge-seeding procedures are successful in precipitating soluble silica. However, the reproducibility was poor in all cases. The chlorine procedure was considered unsatisfactory because it precipitated iron, as well as silica.

In deciding between the first two methods, it was observed that clarifier sludge varied in particulate size and concentration. To eliminate these variables and because of time and budget restrictions, we selected the rapid-mixing procedure for the initial screening of anti-scalants.

All selected anti-scalants also had to be subjected to a flashing procedure, because any product to be

TABLE 1
EVALUATION OF TESTS

<u>Sample Date</u>	<u>Sample No.</u>	<u>Additives</u>		<u>Mix Time</u>	<u>Filtered Sample ppm SiO₂</u>
		<u>Description</u>	<u>Concentration</u>		<u>24 hrs</u>
1/23/79	1	Blank	-	0	90
	1a	Blank	-	5	255
	2	1% HCl	pH 1.15	5	370
	3	SiO ₂ Seed	0.5 ml	5	396
	4	SiO ₂ Seed	1 ml	0	178
	5	SiO ₂ Seed	1 ml	5	116
	6	Cl ₂	70 ppm	5	293
	7	Blank	-	5	128
	8	1% HCl	pH ~ 0.6	0	283
	9	Sample Lost			
	10	Sample Lost			
	11	Blank	-	0	291

recommended would have to inhibit silica precipitation and be stable at temperatures incurred in the GLEF.

To evaluate anti-scalants as realistically as possible, we devised a simple "hot" test to subject the brine and anti-scalants to the flashing, depressurization, and temperature drop experienced in the plant. A stainless steel "bomb" was hooked up to a bypass line around the cooler on the Woolsey No. 1 well incoming water. This allowed a cooled sample to be taken for the blank and for acidified samples.

In the "hot" test (Fig. 1), hot brine from the well was allowed to flow through the bomb and the lines until these were hot and the brine was flashing. The brine was then shut off and the bomb allowed to drain. As soon as draining was completed, the bottom valve on the bomb was shut off and the anti-scalant to be tested, introduced into the top of the bomb. This valve was then shut off securing the bomb.

Brine was turned on through the other valving arrangement through the hot sample point to atmosphere and allowed to run until it was hot and flashing. The line to the atmosphere was secured and the bottom valve on the bomb was opened, allowing the brine to be introduced into the bomb. This flow was continued for one minute, the time necessary to pressurize and fill the bomb with approximately 600 ml of brine. After one minute the flow was secured and the top valve was cracked open, allowed flashing.

This was continued for five minutes and the valve was slowly opened to maintain flashing and to drop the

FIGURE 1

"HOT" TEST APPARATUS

pressure to atmospheric. During this period the temperature also dropped from approximately 550°F to 200°F. At the end of the five-minute flashing, the brine remaining in the bomb was collected as rapidly as possible, observed for color, precipitation, and clarity, and taken to the laboratory for testing. An aliquot of this sample was immediately filtered for silica analysis and this filtrate was acidified to prevent further silica precipitation.

B. SELECTING ANTI-SCALANTS

Water treatment vendors were contacted for recommendations of products which might be applicable as anti-scalants in the GLEF. These initial inquiries were made by Fred Schoeflin of the Bechtel Corporation, a consultant to San Diego Gas and Electric. Subsequently, other suppliers were contacted and samples obtained by Paul Henry of NUS.

Lawrence Livermore Laboratories, doing a similar study for another contractor, had also contacted sixteen major chemical suppliers. Practically no duplication of samples was found in those submitted to the Livermore labs and to San Diego Gas and Electric. Natrosol N250 obtained from the Livermore labs is the only product initially evaluated by both NUS and the Livermore labs.

In choosing the anti-scalants, NUS evaluated recommendations of suppliers on the basis of technical data presented, cost of the material, and the effect expected on the operation of the geothermal generating plant and the clarifier-filter operation which precedes the brine reinjection.

Because it is believed that silica influences the adherence of the sulfide scales, even at the higher temperatures encountered in the GLEF first flash vessel, primary attention in the screening of proprietary chemicals were given to the inhibition of silica scales. In the secondary flash vessel and in the reinjection pumping system, the rate of growth of silica-rich scales is much greater than that of other scales. Interestingly, none of the proprietary chemical manufacturers specifically recommended a product to inhibit silica scale. Half the products were for inhibiting calcium scales and for dispersing suspended solids.

Although exact compositions of the anti-scalants selected are not available, it is known that most are phosphonates, polyolesters, polyacrylamids, polyacrylates and combinations and mixtures of these.

Other products not composed of these basic ingredients also were evaluated. One was a hydroxyethylcellulose, one an oil mixture, and the third an amine. The latter two, which supposedly work on the principle of coating metal surfaces to prevent scale adherence, could not be evaluated in this laboratory screening test and were recommended for evaluation in the Lawrence Livermore Laboratories. The 19 anti-scalants selected are listed in Table 2.

C. TESTING ANTI-SCALANTS

Throughout the anti-scalant evaluation, an aliquot of brine being tested, normally 10 ml, was filtered through a 0.45 micron millipore filter, acidified, and diluted

TABLE 2

PROPRIETARY ADDITIVES SELECTED FOR TESTING

<u>Product Name</u>	<u>Company, Address</u>	<u>Chemical Type</u>	<u>Concentration Tested, ppm</u>
Thermasol APS	Far Best Corporation Los Angeles, CA	Polyalkylphosphonate	10
Betz 435 SR	Betz Laboratories Trevose, PA	Phosphonate & Acrylic	25
Betz Polysperse	Betz Laboratories Trevose, PA	Organic Polymer	25
Tretolite SP-252	Tretolite Corporation Brea, CA	-	25
Zimmite ZD-209	Zimmite Corporation Cleveland, OH	Phosphonate	10
Zimmite ZD-205	Zimmite Corporation Cleveland, OH	Phosphonate & Polymer	15
Cortron R16	Champion Chemicals Anaheim, CA	Filming Amine	25
Geomate 256	Dearborn Chemical Company Lake Zurich, IL	Phosphonate & Polymer	25
Geomate 259	Dearborn Chemical Company Lake Zurich, IL	Phosphonate & Organic	25
Dearborn 8010	Dearborn Chemical Company Lake Zurich, IL	Phosphonate	25
Dearborn 823-44	Dearborn Chemical Company Lake Zurich, IL	Phosphonate & Polymer	25

TABLE 2 - CONT.

<u>Product Name</u>	<u>Company, Address</u>	<u>Chemical Type</u>	<u>Concentration Tested, ppm</u>
Southwest SSC 201	Southwest Specialty Chem. Houston, TX	Low M.W. Carboxylic Acid	25
Southwest SSC 224	Southwest Specialty Chem. Houston, TX	Low M.W. Carboxylic Acid	25
Drewplex 502	Drew Chemical Company Chicago, IL	Phosphonate & Polymer	25
Drewperse 747	Drew Chemical Company Chicago, IL	Organic Polymer	25
EN6	Austral-Erwin Holtville, CA	Oil	25
Nalco 7317	Nalco Chemical Company Chicago, IL	Phosphonate & Polymer	25
Nalco 8WT-468	Nalco Chemical Company Chicago, IL	Phosphonate	25
Hercules Natrosol N250	Hercules Powder Company	Hydroxyethylcellulose	20

to 100 ml for testing on the atomic absorption spectrophotometer. In all cases, the silica determination was made on a filtered sample. The balance of the original sample was then placed in a bottle, purged with nitrogen, and shelved for further visual observation of sludge and clarity after setting for an additional period of time.

Before each test, a fresh, cooled brine sample was collected to minimize time-precipitation affect on the test. The sample was observed visually before and after mixing, because the precipitation effect of some anti-scalants was visible. A sludge developed and the settleability of the sludge was observed for the clarifier-filter effect of the anti-scalant. The clarity of the solution above the sludge indicated sludge settleability. In rating settleability, lower numbers on a scale of 10 to 1 indicated the sludge settled well and the solution was clearer. Only when that criterion was made was a silica analysis run on the filtered sample.

In the initial screening of anti-scalants, all selected proprietary chemicals were tested at the recommended dosage of the manufacturer. When no recommendation was given, the dosage was 25 ppm. All anti-scalants were diluted 100 to 1 before being used, because of the small amount needed for each addition.

Because a Livermore Laboratories screening test showed Natrosol N250 to be effective, it was used as a basis of comparison for all anti-scalants evaluated in each series of tests. In the first test (Table 3), Dearborn Geomate 259 showed the lowest loss of silica from solution, indicating silica scale inhibition. Also showing promise was the Nalco 7317.

TABLE 3

INITIAL SCREENING OF ANTI-SCALANTS

Sample Date	Sample No.	Additives		Mix Time	Filtered Sample ppm SiO ₂		Quantity Sludge 24 hrs	Sludge Settleability	
		Description	Concentration		5 min	24 hrs		1 hr	24 hrs
1/24/79	1	Far Best Thermasol APS	10 ppm	5	-	-	1	10	0
	2	Betz 435 SR	25 ppm	5	-	229	3	1	5
	3	Betz Polysperse	25 ppm	5	-	-	1	8	1
	4	Tretolite SP-252	25 ppm	5	-	-	3	8	6
	5	Zimnite ZD-209	10 ppm	5	-	-	3	8	6
	6	Zimnite ZD-205	15 ppm	5	-	255	3	2	6
	7	Champion Cortron R16	25 ppm	5	-	-	2	8	5
	8	Dearborn Geomate 256	25 ppm	5	-	-	2	8	5
	9	Dearborn 8010	25 ppm	5	-	-	1	8	4
	10	Dearborn 823-44	25 ppm	5	-	-	1	8	5
	11	Dearborn Geomate 259	25 ppm	5	-	280	3	0	3
	12	Southwest SSC 201	25 ppm	5	-	203	3	2	4
	13	Southwest SSC 224	25 ppm	5	-	-	2	7	6
	14	Drewplex 502	25 ppm	5	-	-	4	8	4
	15	Drewperse 747	25 ppm	5	-	-	1	6	2
	16	Austral-Erwin EN6	25 ppm	5	-	-	3	10	10
	17	Nalco 7317	25 ppm	5	-	229	5	1	2
	18	Nalco 8WT-468	25 ppm	5	-	-	5	6	4
	19	Natrosol N250	20 ppm	5	-	-	1	10	0
	20	Blank	-	0	383	-	-	-	-

Because these two also rated the best on sludge settleability, they, along with the Natrosol N250, were tested again, but with the time period for silica precipitation shortened to more closely approximate the actual holding time of five to ten minutes at the plant (Table 4). This second test showed that Geomate 259 and Natrosol N250 reduced silica precipitation in five minutes, but the Nalco 7317 did not. The test at 30 minutes, however, looked better for the Nalco 7317. The blank samples showed soluble silica stabilizing at approximately 500 ppm.

Table 5 shows another screening of the same three anti-scalants for a time analysis. Varying the mixing time produced unexpected results; each anti-scalant after being mixed for both five minutes and 30 minutes seemed to cause silica precipitation. A retest a day later to evaluate this unexpected behavior showed the same behavior for the Nalco 7317 and the Natrosol N250, but slight improvement for the Geomate 259.

These three anti-scalants and the Drewsperse 747 were retested (Table 6) keeping the mixing time the same (five minutes) throughout. The Drewsperse 747 and the Natrosol N250 were tried at the higher dosage recommended by the manufacturers' representatives. They did not perform as well as expected at that dosage. Because the Natrosol N250 performed well at the lower concentration, we assumed its poor performance was due to poor solubility at the higher dosage. During this test, a more than 60 ppm

TABLE 4

TESTING MOST PROMISING ANTI-SCALANTS

<u>Sample Date</u>	<u>Sample No.</u>	<u>Additives</u>		<u>Mix Time</u>	<u>Filtered ppm SiO₂</u>		<u>Sludge Quantity</u>	<u>Sludge Settleability</u>	
		<u>Description</u>	<u>Concentration</u>		<u>5 min.</u>	<u>1/2 hr.</u>	<u>1/2 hr.</u>	<u>5 min.</u>	<u>30 min.</u>
1/25/79	1	Blank	-	0	509	-	5	0	0
	2	Blank	-	5	509	483	5	0	2
	3	Nalco 7317	25	5	483	524	5	0	1
	4	Natrosol N250	20	5	575	530	5	0	1
	5	Geomate 259	25	5	552	545	5	0	0

Sludge Quantity 1-10 (Lower numbers favorable)

Sludge Settleability 10-1

TABLE 5

TESTS WITH VARYING MIXING TIME

<u>Sample Date</u>	<u>Sample No.</u>	<u>Additives</u>		<u>Mix Time</u>	<u>Filtered Sample SiO₂</u>	<u>Reduction of SiO₂ Over Blank</u>
		<u>Description</u>	<u>Concentration</u>		<u>5 min</u>	
1/26/79	1	Blank		0	526	
	2	Blank		5	522	
	3	Blank		30	469	
	4	Dearborn Geomate 259	25 ppm	5	456	(-66)
	5	Dearborn Geomate 259	25 ppm	30	416	(-53)
	6	Nalco 7317	25 ppm	5	465	(-57)
	7	Nalco 7317	25 ppm	30	405	(-64)
	8	Natrosol N250	20 ppm	5	469	(-53)
	9	Natrosol N250	20 ppm	30	403	(-66)
Repeat with constant mixing times						
1/27/79	1	Blank	-	0	440	
	2	Blank	-	5	380	
	3	Dearborn Geomate 259	25	5	387	7
	4	Nalco 7317	25	5	321	(-59)
	5	Natrosol N250	20	5	357	(-23)

TABLE 6

TESTS WITH TWO FEED RATES INCREASED

Sample Date	Sample No.	Additives		Mix Time	Filtered Sample ppm SiO ₂		ppm Reduction of SiO ₂ Precipitation Over Blank
		Description	Concentration		5 Min.	1/2 hr.	
1/30/79 17	1	Blank	--	0	370		
	2	Blank	--	0		392	
	3	Blank	--	5	351*		
	4	Blank	--	5		354*	
	5	Dearborn Geomate 259	25	5	433		82
	6	Dearborn Geomate 259	25	5		408	54
	7	Drew 747	100	5	405		54
	8	Drew 747	100	5		354	0
	9	Nalco 7317	25	5	392		(-22)
	10	Nalco 7317	25	5		373	--
	11	Natrosol N250	100	5	416		2
	12	Natrosol N250	100	5		354	--
	13	Blank	--	5	414**		

*Blanks for 5-8

**Blank for 9-12

variation was also noted in the silica blanks from the beginning to the end of the tests.

It was decided to repeat the test using all the anti-scalants tested originally and testing for silica after five minutes (Table 7). Best results on that test were with Geomate 259; Nalco 7317 rated second. Third, with identical results were Natrosol N250, Dearborn 8010, Dearborn 823-44, and Zimmite 205. The latter three, however, showed poor results on earlier sludge settleability tests and were, therefore, again eliminated.

To check the effect of the chemical feed rate, another test was run, varying the concentration of the Geomate 259 and the Nalco 7317 by 10 and 15 ppm while comparing each to the Natrosol N250 whose concentration remained constant at 20 ppm (Table 8). Geomate 259 was more effective at reducing silica precipitation when it was fed at higher concentrations. The reverse effect resulted with the Nalco 7317; it was more effective at lower concentrations, but not as effective as the Geomate 259. During this test, Natrosol N250, at half the feed rate of the Geomate 259, reduced the silica precipitation 60 ppm, the same amount as did the Geomate 259.

Four additional anti-scalants were then received and these were tested along with the Geomate 259 and the Natrosol N250; however, the new additives proved ineffective (Table 9).

On the first series of "hot" tests, all anti-scalant products tested earlier were included. As before, all

RETESTING ALL SUBMITTED
ANTI-SCALANTS AT FIVE-MINUTE PERIOD

Sample Date	Sample No.	Additives		Mix Time	Filtered Sample	ppm Reduction of SiO ₂ Precipitation Over Blank
		Description	Concentration		ppm SiO ₂ 5 min	
1/31	1	Blank	-	-	522	
	2	Blank	-	5	466*	
	3	1% HCl	pH-1	5	522	
	4	Thermasol APS	10	5	453	(-13)
	5	Betz 435 SR	35	5	435	(-31)
	6	Betz Polysperse	35	5	426	(-40)
	7	Tretolite SP 252	20	5	453	(-13)
	8	Zimmite ZD-209	10	5	453	(-13)
	9	Zimmite ZD-205	15	5	443	11
	10	Champion Cortron R16	25	5	443	11
	11	Dearborn Geomate 256	25	5	419	(-13)
	12	Dearborn 8010	25	5	443	11
	13	Dearborn 823-44	25	5	443	11
	14	Dearborn Geomate 259	25	5	466	34
	15	Blank	-	0	477	
	16	Blank	-	5	432**	
	17	Southwest SSC 201	20	5	398	(-34)
	18	Southwest SSC 224	20	5	419	(-13)
	19	Drewplex 502	25	5	409	(-23)
	20	Drewspers 747	25	5	409	(-23)
	21	Nalco 7317	25	5	456	24
	22	Nalco 8WT 468	25	5	432	0
	23	Natrosol N250	20	5	443	11
	24	SiO ₂ Seed	0.5ml	5	432	0

*Blank used for 1-8

****Blank used for 9-24**

TABLE 8

RERUN OF ANTI-SCALANTS

Sample Date	Sample No.	Additives		Mix Time	Filtered Sample	ppm Reduction of SiO ₂ Precipitatic Over Blank
		Description	Concentration		ppm SiO ₂ 5 min	
2/7/79	1	Blank	-	0	366	
	2	Blank	-	5	323*	
	3	1% HCl	pH ~1	0	387	
	4	Dearborn Geomate 259	15	5	357	34
	5	Dearborn Geomate 259	25	5	375	52
	6	Dearborn Geomate 259	40	5	383	60
	7	Blank	-	0	381	
	8	Nalco 7317	25	5	357	34
	9	Nalco 7317	35	5	338	15
	10	Nalco 7317	50	5	338	15
	11	Natrosol N250	20	5	383	60

*Blank used

TABLE 9

TESTING ADDITIONAL ANTI-SCALANTS

<u>Sample Date</u>	<u>Sample No.</u>	<u>Additives</u>		<u>Mix Time</u>	<u>Filtered Sample</u>	<u>ppm Reduction in SiO₂ Precipitation Over Blank</u>
		<u>Description</u>	<u>Concentration</u>		<u>ppm SiO₂ 5 Min</u>	
2/20/79	1	Blank	-	0	417	
	2	1% HCl	pH ~ 1	0	417	
	3	Dearborn Geomate 259	25	5	383	11
	4	Natrosol N250	20	5	394	22
	5	Tretolite SP260	25	5	372	0
	6	Tretolite JWR 0161	25	5	349	(-23)
	7	Buckman SASE	25	5	338	(-34)
	8	Buckman CASI773	25	5	338	(-34)
	9	Blank	0	0	394	
	10	Blank	0	5	372*	

*Blank used

materials were introduced at the manufacturers' recommendations or at 25 ppm and all were diluted at least 100 to 1 before being added to the brine.

A blank sample tested under the same condition described earlier was used to compare anti-scalants tested.

In the first test (Table 10) Betz Polysperse performed well, inhibiting silica precipitation on one run as well as on a second run better than an acidified blank. It also had a definite visible effect on metal sulfides. They were finely dispersed and the sample was easy to filter. The Geomate 259 was only slightly better than the hot blank; the Natrosol N250 caused foaming and this was visible in the flashing from the bomb top. The sample containing the Natrosol N250 also indicated precipitation of some of the metal sulfides.

The "hot" test was repeated (Table 11) of these anti-scalants and others that showed good results on the first run. Again, the Betz Polysperse was first in dispersion and in the inhibition of silica precipitation, although neither it nor the others proved as effective as on the first run. In this test, the Geomate 259 was somewhat better than the Natrosol N250. The Natrosol N250 was about equal to the blank in silica precipitation and again caused foaming and produced a clearer solution.

At this time, the Livermore Laboratories informed San Diego Gas and Electric of a product called Carbowax 14,000, made by Union Carbide, which by their test was

TABLE 10

SCREENING ANTI-SCALANTS BY "HOT" TEST

<u>Sample Date</u>	<u>Sample No.</u>	<u>Additives</u>	<u>Concentration</u>	<u>Filtered Sample ppm SiO₂ 5 min</u>	<u>ppm Reduction in SiO₂ Precipitation Over Blank</u>
2/21	1	Blank	-	357	-
	2	Dearborn Geomate 259	25	368	11
	3	Natrosol 250	20	379	22
	4	Thermosal APS	10	368	11
	5	Betz 435 SR	25	389	32
	6	Betz Polysperse	25	424	67
	7	Southwest SSC 201	25	379	22
	8	Blank	-	357	
	9	Tretolite SP 251	25	368	11
	10	Zimmite ZD-209	10	357	0
	11	Dearborn Geomate 259	10	402	45
	12	Zimmite ZD-205	15	389	32
	13	Champion Cortron R16	25	334	(-23)
	14	Dearborn Geomate 256	25	379	22
	15	Dearborn 8010	25	389	32
	16	Dearborn 823-44	25	359	2
	17	Betz Polysperse	25	419	62
	18	Southwest SSC 224	25	383	26
	19	Drewplex 502	25	419	62
	20	Drewsperser 747	25	383	26
	21	Nalco 7317	25	396	39
	22	Nalco 8WT 468	25	406	49
	23	Versatol TL3	25	396	39
	24	Tretolite SP 260	25	406	49
	25	Tretolite JWR D161	25	383	26
	26	Buchman SASE	25	372	15
	27	Buchman Case 773	25	349	(-8)
	28	1% HCl	pH 1	419	

TABLE 11

SECOND "HOT" TEST

<u>Sample Date</u>	<u>Sample No.</u>	<u>Additives</u>		<u>Filtered Sample</u> <u>ppm SiO₂</u>	<u>ppm Reduction</u> <u>in SiO₂</u> <u>Precipitation</u> <u>Over Blank</u>
		<u>Description</u>	<u>Concentration</u>	<u>5 min</u>	
2/22/79	1	Blank	-	340	
	2	Betz Polysperse	25	374	34
	3	Natrosol N250	20	342	2
	4	Tretolite SP 260	25	347	7
	5	Drewplex 502	25	353	13
	6	Nalco 8WT 468	25	317	(-23)
	7	Dearborn Geomate 259	25	353	13
	8	1% HCl (not filtered)	pH~1	430	

effective in inhibiting silica precipitation and significantly exceeded the effectiveness of Natrosol N250 without having foaming characteristics. In the Livermore dual-channel testing, a one-day run with Carbowax 14,000 indicated significant reduction in the scaling rate at 90°C, but no reduction in the rate at 125°C. To compare the Betz Polysperse with the Carbowax 14,000, it was decided to run the "hot" test and then to incubate the brine at 90°C (the Livermore procedure) for a time comparison (Table 12).

TABLE 12

COMPARISON OF BETZ POLYSERSE
AND CARBOWAX 14,000

<u>Date</u>	<u>Sample No.</u>	<u>Additive</u>		<u>Filtered Sample</u>		
		<u>Description</u>	<u>Concentration</u>	<u>ppm SiO₂</u>		
				<u>5 min.</u>	<u>30 min.</u>	<u>12 hrs.</u>
2/23/79	1	None	-	404	391	261
	2	Betz Polysperse	25 ppm	415	404	274
	3	Carbowax 14,000	20 ppm	415	404	274
	4	1% HCl	pH 1	488	-	-

IV. CONCLUSIONS AND RECOMMENDATIONS

Of the 19 original and the other anti-scalants obtained later while tests were in progress, two appeared to be outstanding in warranting further testing in the loop.

The one chosen by San Diego Gas and Electric is the Betz Polysperse. The decision was based on results of the "hot" tests and its additional advantages of being stable, liquid and easy to use, and more economical.

On the basis of "hot" test results alone, Betz Polysperse and Carbowax 14,000 seemed equally effective. The Carbowax was one of the new anti-scalants recommended near the end of the testing and was, therefore, only "hot" tested.

Others in the group which showed promise are Dearborn Geomate 259, Drewsperser 502, Tretolite SP260, Natrosol N250, and Nalco 7317. Sludge settleability tests indicate that anti-scalants showing the most promise should not interfere with the clarification treatment process preceding brine reinjection.

Favorable results for the Nalco 7317 and Geomate 259 were evidenced in the rapid-mixing procedure/sludge settleability series, while the others gained interest during the "hot" test. We believe that because the "hot" test more closely represented actual loop conditions, those results should be given more weight.

Neither test, however, could be considered to be more than it was intended: a rapid means of screening potential products.

Constituents of the geothermal fluid varied and, consequently, differences even in blanks were noted within tests. For this reason, no comparison could be made from test-to-test; each had to be evaluated separately, because no consistency in results was evident.

Because of the uniqueness of the geothermal process, we recommend that any additional screening of anti-scalants be made in a pilot unit which realistically duplicates flows, temperatures, and holding times of the GLEF. Unless outstanding results are seen in the loop test of the Betz Polysperse, we recommend all those anti-scalants showing promise be retested in the pilot unit.

**SURGE CONTROL STUDY
FOR THE
GEOTHERMAL LOOP EXPERIMENTAL FACILITY**

**THE BEN HOLT CO.
201 SOUTH LAKE AVENUE
PASADENA, CALIFORNIA 91101**

HOLT JOB NO. 7827

13 February 1979

TABLE OF CONTENTS

	<u>Page</u>
INTRODUCTION	1
OBJECTIVE AND APPROACH	2
SUMMARY	3
GLEF FLOW REGIME PREDICTION AND THEORY	3
TWO-PHASE FLOW OBSERVATIONS AT THE GLEF	3
RECOMMENDATIONS FOR 50 MW DESIGN	3
RECOMMENDED GLEF MODIFICATIONS	4
STATE OF THE ART	5
GENERAL LITERATURE ON TWO-PHASE FLOW	5
Figure 1 - G. E. Alves's Description of Two-Phase Flow Regions	6
Table 1 - Literature Search	7
INDUSTRIAL PRACTICE	8
FLOW REGIME PREDICTION	8
Horizontal Pipe	8
Figure 2 - Dukler Flow Regime Chart with Geothermal Two-Phase Flow Data Shown	9
Vertical Pipe	10
Near Horizontal Pipe	12
TWO-PHASE FLOW IN GEOTHERMAL SYSTEMS	12
Otake Experiments	12
New Zealand Experiments	12
Hatchobaru Tests	13
Table 2 - Range of Experimental Data for Hatchobaru Mixed Flow Experiment	14
Table 3 - Calculated Pressure Drops for Hatchobaru Experiment	14
TURBINE DESIGN LIMITATIONS	15

TABLE OF CONTENTS - (Continued)

	<u>Page</u>
GLEF FLOW REGIME PREDICTION AND THEORY	16
LIQUID VOLUME RATIO	16
Figure 3 - Well-To-Plant Pipelines at the GLEF	17
Table 4 - GLEF Pipeline Fluid Conditions	18
Figure 4 - GLEF Flow Conditions on the Dukler Chart	19
Table 5 - Uncertainty in Composition of Two-Phase Flow in the Annular/Mist Region for GLEF Conditions as Demonstrated by Limiting Conditions	20
EFFECT OF PRESSURE	21
EFFECT OF PIPE SIZE	21
EFFECT OF ELBOWS AND BENDS	21
EFFECT OF INCLINATIONS	22
EFFECT OF A CONTROL VALVE	22
Table 6 - Effect of Inclination on Liquid Volume Ratio Assuming Stratified Flow	23
TWO-PHASE FLOW PROCESSES AT THE GLEF	25
OBSERVATIONS, NOVEMBER 12, 1978	25
INTERPRETATION OF OBSERVATIONS	25
Figure 5 - Nature of Flow Pulsing at the GLEF	26
Figure 6 - Elevation View of Pipeline from Magmamax No. 1 Well to GLEF Plant with Approximate Dimensions Shown	27
Figure 7 - Pressure Distribution at III the End of the Liquid Flow Period and at I, the End of the Steam Flow	28
DISCUSSION OF RESULTS	30
COUPLED CONTROL VALVE	30
SURGE TANK	30
Figure 8 - Surge Tank, Design 1	31
Figure 9 - Surge Tank, Design 2	33

TABLE OF CONTENTS - (Continued)

	<u>Page</u>
CONCLUSIONS	34
RECOMMENDATIONS FOR 50 MW PLANT PIPING DESIGN	35
Figure 10 - Flow Regimes for Start-of-Run (SOR) and End-of-Run (EOR) Conditions for the 50 MW Dual Flash Plant	36
RECOMMENDATIONS FOR THE GLEF MODIFICATIONS	38
RECOMMENDED APPROACH	38
APPROACH 2	38
APPROACH 3	38
DESIGN DETAILS FOR THE RECOMMENDED GLEF MODIFICATIONS	39
Figure 11 - Plot Plan Showing Location of Pipeline to be Replaced and Roadway to be Raised	40
Table 7 - Installed Cost for Recommended Modifications to the GLEF	41
APPENDIX A	42
SURGE TANK DESIGN (Design 2)	42
NOMENCLATURE	45
REFERENCES	46

INTRODUCTION

Slugging and/or pulsing flow occurs in the well-to-plant pipe system at the Geothermal Loop Experimental Facility (GLEF). These phenomena can cause: (1) mechanical failure of the system due to the transient stresses; (2) fluctuating pressure in the first stage flash and, subsequently, the turbine, with possible detrimental effects on turbine life; and, (3) downstream plant fluctuations and undesirable nonsteady behavior of the GLEF plant. Consequently, elimination, or at least reduction of this flow behavior is needed.

OBJECTIVE AND APPROACH

The objective of this work is to recommend modifications to the GLEF that will eliminate or substantially reduce slugging and pulsation in the well-to-plant pipe system and, further, to do this in a manner that would be representative of the most desirable method for a 50 MW plant design.

This objective was accomplished by the following stepwise procedure.

1. Determining the state of the art for predicting the nature of cocurrent two-phase gas and liquid flow; i.e., the flow regime.
2. Applying these predictive methods to the GLEF conditions assuming straight, horizontal pipe.
3. Extending the theory of these predictive methods to cover more correctly the GLEF configuration.
4. Observing the nature of the flow at the GLEF.
5. Interpreting these observations in terms of the theory developed in Step 3.
6. Determining recommended design procedures.
7. Applying the procedures to the 50 MW design base case.
8. Applying the procedure to the present GLEF conditions.
9. Preparing a set of recommendations for modifying the GLEF to meet the above objective.

SUMMARY

Analysis of surge control at the GLEF requires a knowledge of the flow patterns which exist in the well-to-plant piping carrying a two-phase steam-liquid mixture. Descriptions of two-phase flow regimes and methods for predicting which regime will occur in straight horizontal pipe are found in the literature. Both the GLEF and 50 MW plant flow conditions are such that steady annular-mist flow would occur in straight horizontal pipe.

GLEF FLOW REGIME PREDICTION AND THEORY

The GLEF well-to-plant pipeline does not consist of straight horizontal pipe, consequently, the effects of various deviations from straight horizontal pipe is developed. Elbows, pipeline slope changes, and vertical loops all increase the tendency for the formation of liquid slugs in a two-phase system. A control valve at the end of the pipeline can create an unstable situation and must be avoided. The valve can be decoupled from the pipeline by a homogenizer, the function of which is to provide sufficient gas and liquid capacity to absorb the largest expected slug and produce a flow with constant liquid-to-gas ratio. Upward inclines at the GLEF increase the liquid holdup about 10 percent and downward ones decrease the holdup about 20 percent. Upward inclines increase the likelihood of slug flow compared with horizontal lines.

TWO-PHASE FLOW OBSERVATIONS AT THE GLEF

Observation of two-phase flow processes at the GLEF and interpretation thereof, based on the above theory, form a consistent picture of the two-phase flow at the GLEF and substantiates the theory developed and described above.

RECOMMENDATIONS FOR 50 MW DESIGN

The 50 MW well-to-plant pipeline should be a single two-phase line appropriately sized and:

1. The control valve should be decoupled by the use of a surge tank.
2. Elbows should be minimized.
3. Angled entries should be used to the header.
4. The number of expansion loops should be minimized.
5. No vertical loops should be used and vertical legs should be minimized.

RECOMMENDED GLEF MODIFICATIONS

The GLEF should be modified by rerouting the Magmamax line from the roadway to the first stage flash, so as to eliminate the vertical loops and a surge tank should be installed immediately preceding the control valve.

STATE OF THE ART

The state of the art was determined by a general literature survey of two-phase flow, by considering current industrial practice based on personal contacts and in-house knowledge, and by a survey of the geothermal literature for two-phase flow.

GENERAL LITERATURE ON TWO-PHASE FLOW

Most literature on the cocurrent two-phase flow of liquid and gas is directed at the prediction of pressure drop. A few papers deal directly with the prediction of the type of flow, e.g. slug, stratified, bubble, or annular-mist, and the literature on pressure drop prediction sometimes discusses flow regime prediction in passing. Alves's description of these flow regimes is shown in Figure 1. The problem of predicting pressure drop is most often considered independently of flow regime. Since the purpose of this work is to deal with methods of eliminating slugging and/or pulsing flow in the GLEF and subsequent plants at the Niland reservoir, and since pressure drop prediction is not crucial to this work, an analysis of the pressure drop prediction literature has not been included in this study. The source and some of the key words examined in detail are listed in Table 1.

Flow regime correlations for predicting the nature of cocurrent two-phase gas-liquid flow have been proposed by Lockhart and Martinelli (1949), Baker (1954), Knowles (1965), and Dukler (1976). Except for Dukler, these correlations were purely empirical, based on a large amount of data, mostly in pipe sizes under 3-1/2 inches and mostly on the air-water system. The Baker correlation is most widely used in the petroleum industry, but Baker's correlation, as well as others, cannot be expected to predict experimental flow patterns outside the data base of the empirical correlation (DeGance and Atherton, 1970).

Dukler (Dukler, 1976) has developed a generalized flow regime map based on a semi-theoretical and similarity analysis. Although still not able to predict the flow regimes adequately for some cases, the Dukler correlation offers a significant improvement because of its theoretical basis over the earlier empirical correlations.

All of the work is limited to straight pipe and the effect of elbows, enlargements, or other wall effects on the flow is not discussed in the literature.

Flow regimes are subject to hysteresis effects (DeGance and Atherton, 1970). The flow regime at any given point is a function not only of the physical conditions at that point, but also of the particular conduit through which it has been flowing; i.e., inclined pipe, elbows, valves, etc. Thus, flow regime maps can never be completely general for all problems.

"1. Bubble flow: Flow in which bubbles of gas move along the upper part of the pipe at approximately the same velocity as the liquid." This type is similar to froth flow where the entire pipe is filled with a froth similar to an emulsion.

"2. Plug flow: Flow in which alternate plugs of liquid and gas move along the upper part of the pipe.

"3. Stratified flow: Flow in which the liquid flows along the bottom of the pipe and the gas flows above, over a smooth liquid-gas interface.

"4. Wavy flow: Flow which is similar to stratified flow except that the gas moves at a higher velocity and the interface is disturbed by waves traveling in the direction of flow.

"5. Slug flow: Flow in which a wave is picked up periodically by the more rapidly moving gas to form a frothy slug which passes through the pipe at a much greater velocity than the average liquid velocity.

"6. Annular flow: Flow in which the liquid forms in a film around the inside wall of the pipe and the gas flows at a high velocity as a central core.

"7. Spray flow: Flow in which most or nearly all of the liquid is entrained as spray by the gas."

Figure 1 G. E. Alves's description of two-phase flow regions (From Baker, 1964). Note that the terms dispersed, spray, and mist are used synonymously throughout this report.

TABLE 1

LITERATURE SEARCH

Sources

Chemical Abstracts 1970 to September, 1978

Nuclear Abstracts 1970 to September, 1978

Books in Print

Library Card Catalogues of

U.C.L.A.

California Institute of Technology

Harvey Mudd College

Principle Headings Searched

Flow

Fluid Mechanics

Petroleum

Petroleum Wells

INDUSTRIAL PRACTICE

The petroleum industry has minimized two-phase flow problems in the field by the use of flash-separators at or near the wellhead. Liquid from the separators is then collected and pumped as a single-phase fluid. This method of dealing with two-phase flow by separating the mixture into single-phase fluids is extended even to offshore wells where in some cases separators are installed at the wellhead itself on the sea floor, and sometimes on the surface platforms.

Slugging into wellhead or field separators can be minimized by properly sized wells and pipelines and/or modifying the flow in some kind of device ahead of the separator such as impingement baffles. Downward sloped lines are sometimes effective in minimizing liquid slugging and entrainment, both because of gravity effects and the lower pressure drop of the inclined line.

In refinery processes, two-phase flow sometimes occurs in column feed lines. An especially significant application is the crude vacuum still furnace-column transfer line. This line is designed for critical flow (analogous to sonic flow for a single-phase fluid) without excessive back pressure in the furnace which could cause cracking of the heavy fractions. Critical flow occurs when the energy available to move the fluid along the pipe (potential energy) is totally consumed by acceleration (kinetic energy) and is not available for frictional dissipation. Using semi-empirical equations based on this model, the transfer line diameter can be calculated. At the discharge (column entrance), the regimes of mist flow and slug flow are avoided, since both of these regimes can prevent effective tower operation. These calculations are based on correlations available in the literature but the actual procedures used are generally company proprietary or specific.

In the petroleum industry, pressure drop calculations for two-phase flow in inclined pipelines are made using Baker's correlation (Baker, 1954) or other pressure drop correlations, assuming slug flow for uphill lines and stratified flow downhill.

FLOW REGIME PREDICTION

The effect of gravity on the type of flow is significant because it is gravity that stratifies flow in a horizontal pipe and which causes back-flow in a vertical pipe. Consequently, methods for predicting the type of flow in pipes can be classified into three groups: horizontal, near horizontal and vertical.

Horizontal Pipe

The generalized flow regime map of Dukler for horizontal pipe is shown in Figure 2. The abscissa is given as

Figure 2 Dukler flow regime chart with geothermal two phase flow data.

$$X = \sqrt{\frac{(dP/dx)_L^S}{(dP/dx)_G^S}} \quad (1)$$

where $(dP/dx)_L^S$ and $(dP/dx)_G^S$ designate the pressure drop of the liquid and gas phase respectively flowing alone in the pipe. These pressure drops can be calculated using conventional friction factor relationships (Ludwig, 1960):

$$(dP/dx)_L^S = .0216 f_L \rho_L q_L^2 / D^5 \quad (2)$$

and

$$(dP/dx)_G^S = .000336 f_V W^2 / \rho_G D^5 \quad (3)$$

For turbulent flow where the friction factor curve is flat, over a range of Reynolds number such as in the case under study, f_V and f_L will be equal. With this and substituting Equations 2 and 3 into Equation 1, then

$$X = \sqrt{64.3 \rho_L \rho_G (q_L / W)} \quad (4)$$

Where q_L is the liquid rate, gpm, W is the steam rate, lb/hr, and densities are lb/ft³.

For the boundary between stratified and annular dispersed flow and between these regimes and intermittent (slug) flow, the ordinate is given by a modified Froude number

$$F = \sqrt{\frac{\rho_G}{\rho_L - \rho_G} \frac{u_G^S}{\sqrt{D g_c}}} \quad (5)$$

where u_G^S designates the superficial velocity of the gas flowing alone in the pipe, ft/sec, and D is the pipe diameter, feet.

Vertical Pipe

The methods of Dukler (1961), Orkiszewski (1974 and Wisman (1975) are used in all industries for predicting pressure drop in two-phase vertical

flow (Coury, 1977) but give greatly different solutions to the same problem. Szilas (1975 and Tolivia (1972) discuss pressure drop predictions in vertical geothermal hot water wells. Tolivia (Tolivia, 1972) also analyzed the well flow regime based on the Baker correlation (Baker, 1954) for two Cerro Prieto wells and concluded the system was in a dispersed liquid regime.

Orkiszewski's vertical flow pressure drop correlation is generally considered to be the best by petroleum industry engineers (DeGance and Atherton, 1970) who claim an accuracy to within 10 percent for their physical systems. This correlation also predicts the flow regime, however, the method is restricted to pipe diameters found in oil wells, where 3-1/2 inches is a "large" diameter. Extrapolation of this method beyond about 5 inches diameter is risky and the correlations probably do not retain their accuracy.

For a typical GLEF operating condition of 200,000 lb/hr and 200 psia, the gas-liquid volumetric ratio R_v is 14.1, and the superficial liquid velocity u_L is 1.59 ft/sec. Using these values, the correlation of Grovier, Raddford and Dunn (Perry, 1973) predicts the flow conditions to be in the froth-flow regime where the gas bubbles mix with the liquid in a highly turbulent pattern.

The parameters for the vertical flow regime given by Orkiszewski (1974) are calculated by:

$$N_{lb} = 1.071 - .2218 \mu_{ns}^2/D$$

where

$$u_{ns} = u_G^S + u_L^S = 24.0$$

so that

$$N_{lb} = -151.6$$

$$N_{ls} = 50 + 70 u_{s1} (\rho_1/\sigma)^{1/4} = +120.5$$

$$N_{lm} = 75 + 138 u_{s1} (\rho_1/\sigma)^{1/4} 0.75 = +271.5$$

and

$$N_{gv} = 1.938 u_{sg} (\rho_1/\sigma)^{1/4} = +43.7$$

where N_{1b} , N_{1s} , N_{1m} , are dimensionless bubble; slug- and mist-flow numbers and N_{gv} is a dimensionless gas-velocity-number. Then for the GLEF conditions, $N_{gv} < N_{1s}$ and $u_G/u_{ns} > N_{1b}$ which is Orkiszewski's criteria for the slug flow regime.

Thus, for a typical GLEF condition of 200 psia and 200,000 lb/hr, Orkiszewski's correlation predicts slug flow whereas the Grovier correlation recommended by Perry predicts froth-flow, well out of the slug-flow region. This exemplifies the conclusion that there is no means readily at hand for predicting the type of flow regime for vertical two-phase flow.

Near Horizontal Pipe

Flow in inclined pipes poses special problems in analysis because of the importance of gravitational forces.

The Dukler correlation (Dukler, 1976) briefly treats small deviations from horizontal flow. For the GLEF conditions, Dukler's method shows that for a downward slope the location of the transition boundaries on the flow regime map are altered such that stratified flow is more likely for a downhill slope, and for an upward slope, the location of the transition boundaries are altered such that slug flow would be more likely. Redefining the inclined flow transition boundaries for slopes over 1° with Dukler's equations is not practical. Consequently, the quantitative approach of Dukler for inclined flow is not used further in this work.

TWO-PHASE FLOW IN GEOTHERMAL SYSTEMS

Two-phase flow tests described below using geothermal fluids show that for steam flow rates above 50 ft/sec, the pressure drop can be predicted sufficiently well for engineering purposes and further that the flow can be stable without hammer, vibration or pulsing. The Aikawa patent (Aikawa, 1971) seems to be based on the economic analysis of Hayashida (Hayashida, 1970) and the Otake and Hatchobaru experiments described below. No information is contained in this patent that is useful to the understanding of surging nor the design of a surge control system.

Otake Experiments

Tests in a loop of 8-inch I.D. pipe containing an 80-foot horizontal, an 80-foot 7° inclined section, and a vertical section (using fluids from a cyclone separator) were conducted successfully at steam rates of 50 to 100 ft/sec (Takahashi, 1970). Vibration was experienced during startup depending on the method of handling the valves. The conditions for this series of experiments correspond to the annular-mist flow regime on the Dukler chart as shown in Figure 2.

New Zealand Experiments

James (James, 1970) ran two-phase flow experiments using varying feed ratios of geothermal steam and water in 200 feet of 12-inch pipe

containing a 30'-26'-30' expansion loop. The expansion loop could be mounted vertically or horizontally. At low flow rates, formation of liquid slugs was indicated in the vertical leg, but no significant vibration or hammer was observed. Generally steam rates were above 60 ft/sec and no appreciable vibration, cavitation or water hammer was observed. Above 60 ft/sec of steam the Lockhart-Martinelli pressure drop prediction was reported to give fairly good agreement. As the steam rates dropped below 60 ft/sec, pressure drop measurements became increasingly erratic.

Hatchobaru Tests

Steam-water transmission tests at Hatchobaru (Soda, 1975) in 617 feet of 12-inch pipe demonstrated mist flow without slugging. The range of data is shown in Table 2. The pressure at the pipe exhaust end varied from 41 to 85 psia. The actual pressure drop was not reported and so was calculated. The pressure drop for steam only was calculated assuming a relative roughness e/D of 0.00015 and multiplied by the experimental value of 7 to give the total pressure drop shown in Table 3 for the minimum and maximum flow rates. Combining this with the appropriate exhaust end pressure gives the calculated inlet pressures in Table 2.

Assuming the inlet pressure to the pipe test section is the calculated value of 92 psia, then the vapor specific volume in the pipeline varies from 5.4 to 10 ft^3/lb whereas the Niland system operates with a specific volume between 3.0 at 159 psia and 1.5 at 300 psia. For similar tendency to move to slug flow from the mist flow regime, the vapor velocities should be similar. Thus, using the lowest flow from Soda of 130,000 lb/hr at 6.2 weight % steam and correcting it by the ratio of specific volumes, pipe diameters, and steam fractions, the corresponding lowest flow G at Niland conditions (2.2 ft^3/lb , 10-inch pipe, 12 wt%, steam) in the Hatchobaru pipe configuration; i.e., 617 ft., 7 percent downhill, 1 elbow would be

$$G = 130,000 (7/2.2)(10/12)^2 (6/.12) \\ = 143,600 \text{ lb/hr}$$

Considering the approximations, this indicates that the Niland system should be operating near the transition from mist/annular flow to slug flow. Thus, longer pipe and more bends such as at Niland increase the slugging tendency and raise the transition flow above the 143,000 lbs/hr which is 225 gpm. This is consistent with the observations at Niland.

Coordinates are plotted on the flow regime map, Figure 2 for the high and low flow rate cases of the Hatchobaru tests assuming horizontal pipe. These tests were made using a straight length of 12-inch pipe with a 7° downward slope. The high flow rate coordinates show fully developed annular-dispersed liquid flow and vary near the transition boundary from stratified to the slug flow regime. These points are both consistent with the observations at Hatchobaru.

TABLE 2

RANGE OF EXPERIMENTAL DATA FOR
HATCHOBARU MIXED FLOW EXPERIMENT (SODA, et al., 1975)

<u>Mass Flow Rate, 10³ lbs/hr</u>			<u>Steam</u>	<u>(dp/d) Total</u>
<u>Steam</u>	<u>Liquid</u>	<u>Total</u>	<u>wt %</u>	<u>(dp/d) Steam Only</u>
84	236	320	26.3	4.8 to 9
8	122	130	6.2	3.6 to 10

TABLE 3

CALCULATED PRESSURE DROPS
FOR HATCHOBARU EXPERIMENT

<u>Steam Flow Rate lbs/hr</u>	<u>Estimated Steam Only Pressure Drop psi/100 ft</u>	<u>(dp/d) Total (dp/d) Steam Only</u>	<u>Outlet Pressure psia</u>	<u>Calculated Pressure Drop</u>		<u>Inlet Pressure psia</u>
				<u>per 100 ft psi/100 ft</u>	<u>for 617 ft psi</u>	
84,000	1.22	7*	41	8.4	52	93
8,000	.016	7*	85	0.11	6.8	91

* Typical experimentally determined pressure drop ratio from Table 2.

TURBINE DESIGN LIMITATIONS

Turbine manufacturers do not have specifications for allowable short term variations in feed pressure to turbine nor any readily available knowledge of what might be allowable. This is not surprising since steam turbines are operated on boilers with relatively large gas capacities so that steam pressure must be without any short term fluctuations.

NEMA Standard 11-13-1969, SM 22-4.04 "Variations from Rated Steam Conditions" does state that the turbine inlet pressure swings "beyond 105 percent of rated pressure shall not aggregate more than 12 hours per 12-month operating period." However, this is probably not directed at short term pressure fluctuations with periods of about 10 seconds such as exhibited at the GLEF and so does not apply.

Thus, there is no information readily available to establish a specification for allowable pressure fluctuation in the first stage flash vessel. However, a ± 1 psi fluctuation of 10 second period in the first stage vessel will be damped by the line to the turbine and the governor controlled throttle valve and even if not damped would not have noticeable effect on the turbine loading. Consequently, ± 1 psi was arbitrarily selected as the design criteria in subsequent sections of the report.

GLEF FLOW REGIME PREDICTION AND THEORY

Woolsey and Magmamax wells have been used to provide geothermal fluid to the GLEF plant via the pipelines shown in Figure 3. The Woolsey well pipeline has a downhill slope with expansion loops and enters the plant via several vertical and horizontal lengths of pipe. The Magmamax line has an uphill slope, and also enters the plant via several changes of direction and elevation with alternating vertical and horizontal lengths of pipelines. Both lines are 10-inch heavy duty pipe with 9-3/4 inches inside diameter with a cross sectional area of 0.518 ft². The brine-stream flow rate is assumed to be 400,000 lbs/hr. The Woolsey line operates at 200 psig; Magmamax at 300 psig. A summary of the pipeline conditions for the two wells is presented in Table 4. Values of the coordinates X and F as calculated from Equations 4 and 5 are also given in Table 4. The last four items in the table, namely the volumetric fluid ratio, actual velocities in the pipe, and the F parameter are given assuming horizontal pipe and annular flow. These conditions are plotted on the Dukler chart, Figure 4.

For horizontal flow in straight pipe, the Dukler correlation predicts that the flow in both pipelines would be in the annular-dispersed liquid regime, although the Magmamax coordinates especially, lie almost on the boundary of the transition to slug flow. Also plotted in Figure 4, are the coordinates for:

1. The 10-inch pipe with 200,000 lbs/hr (400 gpm)
2. A 20-inch pipe with 400,000 lbs/hr (800 gpm)
3. A 20-inch pipe with 200,000 lbs/hr (400 gpm)

As seen from Figure 4, the lower flow rate in the 10-inch lines places the operating point very near the transition boundary of stratified and annular flow.

The probable GLEF operation lies within the area bounded by the 400 gpm and 800 gpm flow rates and by the 200 psig and 300 psig pressures. According to the flow regime map, GLEF operation would be expected to be in the annular-dispersed liquid regime.

No method exists for predicting whether the flow will be annular or mist. If annular, the liquid flow in this large pipe will tend to stratify due to gravity and the transition from stratified to annular flow will in fact be a gradual one and not the sharp boundary indicated.

LIQUID VOLUME RATIO

Table 5 shows the relative liquid volumes and actual phase velocities assuming stratified flow, annular flow, and mist flow. For stratified flow, the relative height of the liquid layer h_L/D is given by the Dukler (1976) correlation and the relative liquid volume and phase velocities

Figure 3 Well-to-plant pipelines at the GLEF showing elevations. Elevations are in fact relative to the elevation of the line entering the loop section leading to the plant. The elevations have not been verified and are probably not accurate. Note that the Woolsey line has several significant changes from up to down slope whereas the Magmamax line is essentially all uphill.

TABLE 4

GLEF PIPELINE FLUID CONDITIONS

The Assumed Fluid Flow Rate is 400,000 lb/hr

	Pressure, psig		
	200	265	300
$T, ^\circ\text{F}$	414	426	439
$\rho_G, \text{lb/ft}^3$	0.448	0.591	0.660
$\rho_L, \text{lb/ft}^3$	62.2	61.7	61.2
$W_G, \text{lb/hr}$	40,800	31,600	26,800
$Q_G, \text{ft}^3/\text{sec}$	25.3	14.8	11.3
$W_L, \text{lb/hr}$	359,200	368,400	373,200
$Q_L, \text{ft}^3/\text{sec}$	1.60	1.66	1.69
q_L, gpm	720	745	760
$\Delta P_L^S, \text{psi/100 ft}$	0.23	0.24	0.25
$\Delta P_G^S, \text{psi/100 ft}$	0.40	0.18	0.12
$u_G^S, \text{ft/sec}$	48.8	28.7	21.8
$u_L^S, \text{ft/sec}$	3.1	3.2	3.3
$X, \text{ from Eq. 4}$	0.75	1.14	1.45
For Horizontal Pipe:			
$F, \text{ from Eq. 5}$	0.81	0.55	0.45
For Annular Flow and Horizontal Pipe:			
V_L/V_T	0.22	0.29	0.32
$u_G, \text{ft/sec}$	62.6	40.4	32.1
$u_L, \text{ft/sec}$	14.1	11.0	10.2

Figure 4 GLEF Flow Conditions on the Dukler Chart.

TABLE 5

UNCERTAINTY IN COMPOSITION OF TWO-PHASE FLOW
IN THE ANNULAR/MIST REGION FOR GLEF CONDITIONS
AS DEMONSTRATED BY LIMITING CONDITIONS

	Line Pressure, psig		
	<u>200</u>	<u>265</u>	<u>300</u>
<u>Stratified Flow</u>			
h_L/D	0.37	0.45	0.49
A_G, ft^2	0.344	0.293	0.266
A_L, ft^2	0.174	0.225	0.252
$(V_L/V_T)_S = A_L/(A_L+A_G)$	0.336	0.434	0.486
$u_G, \text{ft/sec}$	73.6	50.7	42.4
$u_L, \text{ft/sec}$	9.2	7.4	6.7
<u>Annular Flow</u>			
$(V_L/V_T)_A = 0.67(V_L/V_T)_S$	0.22	0.29	0.32
$u_G, \text{ft/sec}$	62.6	40.4	32.1
$u_L, \text{ft/sec}$	14.1	11.0	10.2
<u>Mist Flow</u>			
$(V_L/V_T)_M = Q_L/(Q_L+Q_G)$	.059	.101	.130
$u_G, \text{ft/sec}$	52.0	31.8	25.0
$u_L, \text{ft/sec}$	52.0	31.8	25.0

are calculated from this value. Assuming the shear force ratio of stratified to annular flow is approximately $\pi/2$ or about 1.5. An approximation of the relative liquid volume for the annular flow case would be $1/1.5$ times the V_L/V_T ratio calculated for stratified flow. Table 5 shows the actual velocities based on this liquid volume ratio. For mist flow, the liquid and steam velocities are the same where the liquid particles are entrained in the vapor phase and carried along with it. The relative liquid volume for this case is simply the ratio of the liquid volumetric flow rate to the total liquid plus steam volumetric flow rate.

The most probable form of the flow for the GLEF conditions is an annular or annular partially stratified flow. Thus, the liquid volume ratio V_L/V_T is shown in Table 4 for this condition. However, at lower pressures and higher velocities, the flow will contain a higher fraction of mist and be less annular in nature.

EFFECT OF PRESSURE

As shown in Figure 4, the effect of increasing pressure is to shift the coordinates from the annular flow regime toward the slug flow region. This is because at higher pressures, the percent steam is reduced until ultimately, the ratio of liquid to steam becomes high enough that the liquid begins to drop out of the steam and builds up on the pipe walls in sufficient volume to form slugs of liquid.

EFFECT OF PIPE SIZE

The effect of changing pipe size at the GLEF is demonstrated in Figure 4 by the plot of the same fluid rates and conditions for 20-inch pipe. This drops the region of operation into the stratified flow regime but does not affect the distance on the chart to the slug flow regime. Decreasing the pipe diameters would raise the region of operation and increase the fraction of mist in the line.

EFFECT OF ELBOWS AND BENDS

The effect of elbows, tees, bends and expansion loops in the lines may be approximated by altering the transition boundary "B" in Figure 4. This boundary is based on an average liquid equal to 50 percent of the pipe diameter, and the assumption that, at higher gas rates, waves would form which would completely fill the pipe, thus creating a slug of liquid. Discontinuities in the straight pipe line, such as elbows, etc. would tend to increase the effective liquid level so that this incipient slugging would occur at an actual liquid level less than 50 percent of the pipe diameter. The dashed boundary "B" in Figure 4 is based on a liquid level of 25 percent of the pipe diameter and shows that, if this were the true effective liquid level at incipient slugging, both the Woolsey and Magmamax lines would fall well into the intermittent slug flow regime.

EFFECT OF INCLINATIONS

Dukler's method shows that for a downward slope the location of the transition boundaries are altered such that stratified flow occurs for the downward sloping Woolsey line, and for the upward sloping Magmamax line, the location of the transition boundaries are altered such that slug flow would be predicted.

To estimate the nature of the flow in the real case containing bends, valves, and slope and elevation changes, the volume ratio of liquid in the pipe is needed. No adequate means for estimating this is available in the literature, however, an estimate can be made by a force balance on the liquid assuming stratified flow.

As the pipe inclination increases, or decreases, the effect of gravitational force on the liquid increases from zero for horizontal pipe. For an inclined pipe, the gravitational force plus the frictional drag force of the pipe wall on the liquid is equal to the frictional drag of the steam on the liquid at the liquid-gas interface. Since the pipe wall frictional drag on the liquid is known for the horizontal case and will be the same for the inclined case corrected for the flow area of the inclined case, the above force balance can be solved to give an estimate of h_L/D and therefore the liquid volume ratio V_L/V_T . These values are given in Table 6.

Note that this analysis assumes stratified flow for the GLEF conditions which is probably not correct. As discussed above, the bulk of the evidence indicates that the system is in the annular-mist flow regime. Nevertheless, the information in Table 6 gives an indication of the amount of liquid holdup in the pipe as a function of the inclination because the GLEF conditions correspond to annular rather than mist flow and the annulus is distorted by gravity into a partially stratified layer.

Since the slope of the pipelines at the GLEF are generally less than 0.01, the values in Table 6 show that the liquid volume ratio can be expected to increase by less than 10 percent for an upward slope and decrease less than 20 percent for a downward slope from the horizontal value. Thus, the downward slope will tend to be stratified and the upward slope slug flow compared with the horizontal line.

On the Dukler chart, Figure 4, this can be visualized as moving the X coordinate to the left for downward slopes and to the right for upward slopes. For example, the first expansion loop in the Woolsey line has a rise of about 3 feet in 20 feet or about 8° . From Table 6, even assuming steady flow, this loop would cause the liquid height h_L/D to exceed 0.50 and shift the flow regime into the slug flow region.

EFFECT OF A CONTROL VALVE

The control valve drops the wellhead pressure of 200 to 300 psig to the first-stage flash pressure of 130 psig. This requires a relatively

TABLE 6
EFFECT OF INCLINATION ON LIQUID VOLUME RATIO
ASSUMING STRATIFIED FLOW

Slope* ft/100 ft	Angle*	Liquid Height, h_L/D		Liquid Volume Ratio, V_L/V_T	
		200 psi	300 psi	200 psi	300 psi
12.2	7.0	0.56	0.68	0.58	0.72
3	1.6	0.46	0.58	0.45	0.60
1	0.6	0.41	0.53	0.38	0.54
0	0	0.37	0.49	0.33	0.48
-1	-0.6	0.34	0.41	0.31	0.38
-3	-1.6	0.30	0.33	0.25	0.29
-12.2	-7.0	0.24	0.25	0.18	0.19

*A positive angle slopes uphill, negative downhill.

large restriction, i.e., a partially closed 6-inch ball valve in the GLEF installation. For such a restriction the ratio of the volumetric flow rate of an all steam phase at 200 psig to an all liquid phase is 100:1 for the same pressure drop. Since the GLEF installation has a U shaped loop preceding the valve, liquid will collect in the section leading to the valve and eventually block the valve. When this happens the flow rate almost stops until all the liquid is removed. Then steam which has collected in the upper portion reaches the valve and the volumetric flow rate is increased by a factor of 100. Eventually another liquid block reaches the valve and the flow rate essentially stops. This causes expansion and compression in the gas phase of the pipeline leading to the valve with alternating acceleration and deceleration of the liquid phase. This condition gives rise to formation of slugs.

The conclusion is that a control valve coupled at the end of a two-phase flow pipeline can be an unstable system.

TWO-PHASE FLOW PROCESSES AT THE GLEF

Observations at the GLEF and interpretation thereof, form a coherent description of the two-phase flow at the GLEF and substantiates the theory developed in the preceding section.

OBSERVATIONS, NOVEMBER 12, 1978

Observations of the well-to-plant pipeline taken on November 12, 1978, are summarized in Figure 5. The GLEF plant had been shut down for cleaning and was started on November 9. The estimated flow rate on November 12 was 600 gpm total fluid which is 300,000 lbs/hr. All observed fluctuations exhibited a 10-second period which was constant throughout the period of observation. Over a carefully timed 2-minute interval, the period was always exactly 10 seconds.

The uppermost chart in Figure 5 shows the horizontal motion perpendicular to the centerline in the overhead section of the pipe at the point 2 shown in Figure 6. The observed amplitude was about 1/16 to 1/4 inch with a period of 10 seconds coinciding with an observed sound level shown in the second line of Figure 5. The observed sound was strongest at the valve and diminished with distance but was still audible at the elbow at the road-plant driveway intersection. The third line of Figure 5 shows the pressure fluctuation at the point 3, Figure 6. Again the pattern was repeated regularly. The pressure at the wellhead indicated on the LLL line gauge fluctuated from 263 to 266 psi with a 10 second period.

INTERPRETATION OF OBSERVATIONS

These observations can be interpreted in terms of the flow processes as follows.

There is a vertical loop in the line just preceding the control valve shown as point B in the elevation drawing Figure 6. When liquid reaches the valve at the point 1, or even if there is a temporary rise in the volume % liquid because of flow fluctuations, then the flow through the valve diminishes and liquid drains due to momentum and gravity from A to B thus creating a liquid block, process I.

This causes the steam flow to immediately drop to zero in this section of pipe. The flow rates at the valve are shown graphically in Figure 5. It takes 4 seconds for all this liquid to flow through the valve, process II. During this process the liquid drains out of the vertical loop D-A-B to the points D and B. Also, during this time, due to the momentum of the fluid flowing from the well, the steam in the pipe from the wellhead 4 to the valve 1 is compressed as shown in Figure 7. As a result of this compression 11 ft³ of steam from the well are absorbed in the pipe section due to the pressure rise and 33 ft³ are condensed

* See Figure 6 for locations.

FIGURE 5 Nature of flow pulsing at the GLEF. Magmamax No. 1 well flowing at an estimated rate of 300,000 lb/hr.

Figure 6 Elevation view of pipeline from Magmamax No. 1 well to GLEF plant with approximate dimensions shown. Observation points are indicated by the circled numbers. During Process 4, 18 ft³ of steam is vaporized and the pressure drops in the pipe section E to D. During Process 4, 18 ft³ of steam is vaporized and the pressure drops in the pipe section E to D.

Figure 7 Pressure distribution at III the end of the liquid flow period and at I, the end of the steam flow.

on the now subcooled liquid. If all the liquid were heated to the boiling point corresponding to the local pressure rise, 58 ft^3 of steam could be condensed, but only 33 ft^3 are condensed to absorb the 44 ft^3 of steam flowing into this pipe section from the well in 4 seconds. Thus, the well flow is almost constant even though the steam flow at the valve drops to zero.

After all the liquid which drained from the elevated pipe section A-B, has flowed through the valve, the elevated section of pipe D-B is full of steam only and this begins to flow through the valve, process III in Figure 5.

The steam flow part of the cycle, process IV, lasts for 6 seconds. Initially, pure steam which accumulated in the elevated portion flows through at a high rate, accelerating the fluid in the pipeline. Eventually, increasing amounts of liquid reach the valve slowing down the flow. The pocket of liquid collected at D, due to drainage during the liquid flow process, will reach the valve C and possibly explain the pressure blip shown in Figure 5 observed at point 3 about 8 seconds into the cycle. This acceleration of the liquid contributes to the formation of slugs of liquid. The vibration of the pipe shows this increases until the liquid block, process I, occurs, when sufficient liquid reaches the valve C. During the steam flow process, 42.5 ft^3 steam flow from the elevated section, 50.5 ft^3 from 172 feet of pipe upstream from this section and 18 ft^3 are vaporized from the liquid due to the dropping pressure. This is shown in Figure 7 and totals 111 ft^3 , which over the 10 second cycle gives the required 11.1 ft^3 steam per second.

DISCUSSION OF RESULTS

The experiments of James show that a vertical section in a pipeline carrying a two-phase mixture can cause the formation of liquid slugs. Conversely, Soda's experiments with a $7\frac{1}{4}$ downhill sloping straight pipeline followed by a valve apparently gives stable flow. However, whether other pressures, steam-to-liquid ratios, and physical configurations of a line and valve without vertical sections also would give stable slug-free flow is doubtful, because of the nature of the action of a valve coupled to a line with two-phase flow. The experiments and theory of Taitel and Dukler (Taitel, 1978) show that slug flow can also occur during transients, even if the flow would otherwise be in another regime.

The use of the Dukler chart shows that for steady flow at the GLEF conditions in a straight horizontal pipe, the flow would be in the annular-mist regime. However, the presence of elbows, vertical sections, and a coupled valve all contribute to nonsteady behavior and surging.

COUPLED CONTROL VALVE

Because the volumetric flow rate of steam is about 100 times that of brine through an orifice with the same pressure drop, coupling the valve to the feed line amplifies any unsteady behavior and is, therefore, the most important factor in the periodic flow behavior at the GLEF. Any change in the volumetric ratio of steam to liquid entering the valve, causes a corresponding change in flow rate. This, in turn, can cause further changes in steam-to-liquid ratio, thus creating an unstable situation.

The observations of flow conditions at Niland are consistent with varying flow rates through the valve entering the first stage flash. Thus, an important factor in improving the GLEF operation and in designing a 50 MW plant is to decouple the control valve from the feed line. This can be done by the use of a surge tank.

SURGE TANK

Two surge tank designs were considered. Design 1, shown in Figure 8, controls surging by providing liquid and vapor capacity and by providing separate liquid and vapor lines to the first stage flash vessel. Liquid flow from the surge tank to the flash vessel is controlled by a level control valve on the surge tank level. The combination of liquid capacity in the surge tank and the proper setting of throttling range and reset speed on the control valve will substantially eliminate liquid flow variation to the flash vessel. Steam flow from the surge tank to the flash vessel is controlled by a pressure control valve on surge tank pressure. Variations in steam flow will be dampened by the vapor capacities of both the surge tank and flash vessel and by proper settings of the throttling range and reset speed. The volume of the

FIGURE 8
SURGE TANK, DESIGN 1

surge tank is determined by the size and frequency of the surges in the brine supply to the tank. The design method outlines in Appendix A for Design 2 can also be used for Design 1.

The surge tank Design 2 is shown in Figure 9. The outlet port of the surge tank is designed so that the ratio of liquid-to-gas flow rates in the outlet is constant. The outlet port operates by high velocity gas sweeping the liquid into the outlet conduit, where, in a properly sized port and conduit, flow will be in the mist flow regime.

The worst case the surge tank must handle is alternating slugs of pure gas and pure liquid at the inlet. During the period of all liquid flow, the gas capacity of the surge tank is of sufficient size to provide the required gas flow without significant drop in surge tank pressure. The design equations for the surge tank are discussed in Appendix A.

As shown in Appendix A, for the GLEF and the 50 MW plant flow conditions to meet the above requirements, the surge tank diameter is given by

$$D^3 > 1430 V_L^3 / V_S$$

where V_L is the liquid slug volume and V_S is the vapor space volume in the first stage flash tank. This diameter will result in ± 1 psi maximum pressure swings in the first stage flash tank due to slugging in the pipeline.

FIGURE 9

SURGE TANK, DESIGN 2

CONCLUSIONS

1. The flow regime for the Niland conditions in a long horizontal pipe would be a longitudinally homogenous two-phase fluid, probably partially mist and partially annular-stratified flow without slugs, providing no instabilities are introduced.
2. Flow instabilities, that is, nonsteady behavior, can be introduced by:
 - a. Changes in the slope of the pipeline causing accumulation of liquid, particularly when flow is already unsteady,
 - b. Vertical sections, particularly at steam flow rates below 60 ft/sec,
 - c. Elbows, which promote separation of liquid droplets from the gas, piling up the liquid and thus increasing the tendency to the formation of slugs, and
 - d. A control valve or any restricting orifice at the end of a line containing two-phase flow, creating unstable system.
3. Surge problems at the Niland GLEF are a result of the pipeline configuration (sloped line, elbows, vertical sections) and the control valve being directly coupled at the end of the line. A modified, horizontal line with the valve decoupled from the line (for example, by the insertion of a surge tank between the line and valve) will reduce surging in the two-phase pipeline supplying the GLEF.

RECOMMENDATIONS FOR 50 MW PLANT PIPING DESIGN

The fluid conditions in the well-to-plant pipeline are based on the flow rates given in the Bechtel/Holt report (Bechtel, 1978) for the 50 MW dual flash, no minimum injection temperature case. At end-of-run conditions, the flow rates given for the 50 MW plant are:

steam	586,690 lb/hr
N.C.	28,098
brine	5,032,960

giving a total fluid flow rate of 5,647,748 lb/hr. Well production is 300,000 lb/hr-well at 150 psig and 380°F.

Fluid properties in the pipeline are estimated to be

Pressure, psig	150
Temperature, °F	380
y, wt % steam	10.5
ρ_L , lb/ft ³	63.6
ρ_G , lb/ft ³	0.355

Location of flow points on the Dukler flow regime map is given by the X and F coordinates defined previously. The parameter X is dependent only on the physical properties and percent steam as given by Equation 4. For the above conditions $X = 0.64$. The parameter F is given by Equation 5. Values of F for 42-inch and 36-inch pipe handling (1) the total fluid rate (5,647,748 lb/hr); and (2) the total fluid rate less two wells (5,047,748 lb/hr) along with the F value for an 8-inch pipe handling 400,000 lb/hr (SOR) and 300,000 lb/hr (EOR) are:

<u>Pipe ID, inches</u>	<u>Flow Rate, lb/hr</u>	<u>F</u>
8	400,000	1.53
8	300,000	1.15
36	5,647,748	0.70
36	5,047,748	0.63
42	5,647,748	0.36
42	5,047,748	0.32

These coordinates are plotted on the Dukler flow regime map in Figure 10. All points are well away from the intermittent slugging region and lie for the most part in the annular dispersed liquid region. This is consistent with the stable operation shown in the Hatchobaru tests discussed. These points also fall generally within the range of the GLEF tests. Consequently, the GLEF operation in a 10-inch line should model the results to be expected in the 50 MW plant. Therefore, the above conclusions apply to the 50 MW piping design. Thus, the 50 MW design can successfully use a single pipeline carrying two-phase flow.

Figure 10

Flow regimes for start-of-run (SOR) and end-of-run (EOR) conditions for the 50 MW dual flash plant. Line pressure is 150 psig and the total flow rate is 5,647,748 lbs/hr.

The recommendations for the two-phase pipelines are:

1. The control valve, if any, should be decoupled from the pipeline by the use of a surge tank between the pipeline and the valve.
2. Elbows should be minimized and where used should be extra large radius.
3. Angled entries rather than Tee's should be used for joining each well's output to the header.
4. The number of expansion loops should be minimized, and where used should be horizontal with the same slopes as the main line and should have large radius bends.
5. No vertical legs should be used. If vertical legs are unavoidable, the volume of the sections between the legs should be minimized, as well as the volume of the legs themselves.

The surge tank size will depend on the magnitude and frequency of slugging, but is expected to be about 5 feet in diameter by 15 feet long.

RECOMMENDATIONS FOR THE GLEF MODIFICATIONS

An important consideration in selecting the approach for controlling surging at the GLEF is that the approach should represent the proposed 50 MW design basis, so that the results will model as nearly as possible to the 50 MW piping design. Consequently, a further study of the theory for the GLEF and collection and interpretation of additional two-phase flow data from the GLEF is recommended.

To solve the existing problem, that is, to assure steady flow into the first stage flash tank and to significantly reduce pipeline motions, several approaches are possible.

RECOMMENDED APPROACH

Including the consideration that the results of the GLEF modifications represent the 50 MW design, the recommended approach is:

1. Provide a surge tank, using Design 1.
2. Replace the vertical sections in the plant with a horizontal line leading to the surge tank.
3. Locate the control valve immediately after the surge tank.

Although calculations indicate a smaller size would be sufficient, a tank diameter about 3 times the 10 inch inlet pipe diameter is probably a practical minimum. A surge tank of about 3 feet diameter by 6 feet should be adequate.

This modification will require repiping the line from the roadway into the first stage flash tank and some modification of the roadway itself to permit elevation of the pipeline to delete vertical legs.

APPROACH 2

Deleting the requirement that the GLEF should represent the 50 MW system, then the vertical legs could be left in place. A surge tank about 5 feet in diameter by 15 feet long would be installed just prior to the valve entering the first stage flash tank. This approach minimizes the re-piping required, however, it does require finding space for a much larger vessel than the recommended approach. For this reason, and also because this approach does not represent the 50 MW design, it is not recommended.

APPROACH 3

Various configurations involving partial reduction of the vertical loop and a homogenizer vessel size between the ones for the above two cases can be considered. However, the difference in cost between such a modification and that for the recommended approach is probably not sufficient to justify this less desirable approach.

DESIGN DETAILS FOR THE RECOMMENDED GLEF MODIFICATIONS

The Magmamax line 10-inch-BR2-BA from the edge of the roadway to the first stage flash tank should be rerouted so as to eliminate the existing vertical loop shown in Figure 6 and a homogenizer installed. This is shown in the simplified plot plan, Figure 11.

Preferably, the new pipeline should maintain the elevation and slope of the existing line along the plant roadway. This will necessitate modification of the roadway and possibly other changes. Alternatively, but less desirably, the pipeline could drop down below the existing grade for minimum horizontal and vertical distances to go under the existing roadway. If this is done, 45° long radius el's are preferred.

The cost of this recommended modification depends somewhat on the details, particularly the approach to the roadway situation. Assuming that the line is maintained level, that the roadway is raised 2 feet to go over this, and that no other piping changes are required because of the roadway change, then the cost might be as shown in Table 7.

Figure 11 Plot plan showing location of pipeline to be replaced and roadway to be raised. Note that other changes may be required depending on clearance requirements.

TABLE 7**INSTALLED COST FOR RECOMMENDED MODIFICATIONS
TO THE GLEF**

<u>Item</u>	<u>Amount</u>
Surge Tank	\$13,000
Pipeline	14,000
Roadway	8,000
Engineering (including meetings and reports)	15,000
TOTAL	\$50,000

APPENDIX A
SURGE TANK DESIGN
 (Design 2)

The surge tank, Figure 9, provides three functions:

1. Gas capacitance,
2. Liquid capacitance, and
3. Steady outlet vapor to liquid ratio.

The liquid surface area is minimized by using a shaped outlet port such as the rectangular port shown in Figure 9. The width of the port is selected so that the height H of the opening for vapor flow is a reasonable maximum. This maximizes the allowable variation in liquid height dH and so minimizes the size of the surge tank.

If β is the allowable pressure rise over the first stage flash pressure P_s and V_s is the gas volume space in the first stage flash vessel, then the allowable variation dQ_{HG} is flow rate of gas from the surge tank to the flash vessel is:

$$dQ_{HG} < V_s \beta / t_G P_s \quad (A-1)$$

Where use was made of the relationship

$$dV = \beta (V_s / P_s) \quad (A-2)$$

and where t_G is the pulse time during which the flow is perturbed by the amount dQ_{HG} .

The variation dQ_{HG} in outlet gas flow rate from the surge tank is due to perturbations in pressure and liquid level:

$$dQ_{HG} = (\delta Q_{HG} / \delta P_H) dP_H + (\delta Q_{HG} / \delta H) dH \quad (A-3)$$

which, for a perturbation around the operating point can be written as

$$dQ_{HG} = (Q_{HG} / P_H) dP_H + (Q_{HG} / H) dH \quad (A-4)$$

If dP_H and dH are the maximum excursions, Figure 9, then for the pulse time t_G the average variation in Q_{HG} is given by $1/2 dQ_{HG}$ given by Equations A-3 and A-4.

By material balances around the surge tank during the pulse time t_L

$$dP/P = Q_G t_L / V_H \quad (A-5)$$

and

$$dH/H = V_s / H A_H \quad (A-6)$$

Where V_H is the gas capacity and A_H is the liquid surface area in the surge tank. Since the slug will be moving with a velocity equal to the gas velocity,

$$t_L = V_L / Q_G \quad (A-7)$$

The pulse time for gas flow is

$$t_G = t_L (Q_G / Q_L)$$

or using Equation A-7

$$t_G = V_L / Q_L \quad (A-8)$$

Combining the above Equations with the inequality Equation A-1

$$dH/H + dP/P < 2V_s Q_L / V_L P Q_{HG} \quad (A-9)$$

and

$$V_L / V_H + V_L / H A_H < 2V_s Q_L / V_L P Q_{HG} \quad (A-10)$$

For a horizontal vessel with $L/D = 3$ the volume of gas space will be about one-half the total volume so

$$V_H = 3\pi D^3 / 8 \quad (A-11)$$

The liquid surface area will be equal to $3D^2$ and H will be about one-third the diameter so that

$$HA_H = D^3 \quad (A-12)$$

Using Equations A-11 and A-12, Equation A-10 can be solved to give the approximate diameter of the surge tank.

$$D^3 > P_s Q_{HG} V_L^2 / \beta V_S Q_L \quad (A-13)$$

For the 50 MW and GLEF flow conditions with P_s of 130 psig, Q_{HG}/Q_L is 22 so that Equation A-13 becomes

$$D^3 > 2,860 V_L^2 / \beta V_S \quad (A-14)$$

If the pressure swing is to be limited to ± 1 psi, β is 2 and Equation A-15 becomes

$$D^3 > 1,430 V_L^2 / V_S \quad (A-15)$$

NOMENCLATURE

A	Area, ft ²
D	diameter, ft
f	friction factor
F	defined by Equation 5
g _c	gravitational constant 32.2 ft/sec ²
G	mass flow rate, lb/hr
h	height, ft
H	height of steam portion of exhaust port, ft
P	pressure, psia
q	volumetric flow rate, gpm
Q	volumetric flow rate, ft ³ /sec
t	time, sec
T	temperature, °F
u	velocity, ft/sec
V	volume, ft ³
V*	volume of liquid slug, ft ³
W	mass flow rate of steam, lbs/hr
x	distance, ft
y	steam fraction, weight %

Greek Symbols

β	pressure rise, psia
ρ	density, lbs/ft ³

Subscripts

A	annular
G	gas, vapor or steam phase
H	surge tank
i	interface, gas-liquid
L	liquid or brine phase
M	mist
s	separator
S	Stratified
V	vapor or steam phase

Superscripts

s	superficial
---	-------------

REFERENCES

1. Aikawa, K., et al., "Transporting Means and Equipment for Jet Energy of Geothermal Power Plant," U. S. Patent 3,605,403, September 20, 1971.
2. Aikawa, K. and M. Soda, "Advanced Design in Hatchobaru Geothermal Power Station," Second United Nations Symposium on the Development and Use of Geothermal Resources, San Francisco, May 20-29, 1975.
3. Baker, O., "Simultaneous Flow of Oil and Gas," Oil and Gas Journal, pp. 185-195 (July 26, 1954).
4. Bechtel National, Inc. and The Ben Holt Co., "Feasibility and Risk Study of a Geothermal Power Plant at the Salton Sea KGRA," March 10, 1978.
5. DeGance, A., and W. Atherton, "Chemical Engineering Aspects of Two-Phase Flow," Chemical Engineering, in eight parts: March 23, April 20, May 4, August 10 and November 2, 1970, and February 22, 1971.
6. Dukler, A. E., et al., AIChE Journal, 10, pp. 44-51 (1961)
7. Dukler, A. and M. Hubbard, "A Model for Gas-Liquid Slug Flow in Horizontal and Near Horizontal Tubes," Ind. Eng. Chem., Fundam, 14, pp. 337-347 (1975).
8. Dukler, A., et al., "Frictional Pressure Drop in Two-Phase Flow: A. A comparison of Existing Correlations for Pressure Loss and Holdup," AIChE Journal, 10, pp. 38-43 (1964).
9. Dukler, A., et al., "Frictional Pressure Drop in Two-Phase Flow: B. An approach Through Similarity Analysis," 10, pp. 44-51 (1964).
10. Hayashida, T., "Cost Analysis on the Geothermal Power," United Nations Symposium on the Development and Utilization of Geothermal Resources, Piza, 2 pp. 950-957 (1970).
11. James, R., "Factors Controlling Borehole Performance," United Nations Symposium of the Development and Utilization of Geothermal Resources, Piza, 2, pp. 1502-1515 (1970).
12. James, R., et al., "Flow of Steam Water Mixtures Through a 12-inch Diameter Pipeline: Test Results," United Nations Symposium on the Development and Utilization of Geothermal Resources, 2, pp. 1581-1587 (1970).
13. Knowles, C. R., "The Effect of Flow Patterns on Pressure Loss in Multiphase Horizontal Flow," M.S. Thesis, University of Texas, Austin (1965).

REFERENCES - (Continued)

14. Lockhart, R. W. and R. C. Martinelli, "Proposed Correlations of Data for Isothermal Two-Phase, Two-Component Flow in Pipes," Chemical Engineering Progress, 45, pp. 39 (1949).
15. Ludwig, E. E., "Flow of Fluids," Chemical Engineering, pp. 162-208, (June 13, 1960).
16. Orkiszewski, J., J. Pet. Tech., pp. 903-914 (August, 1974)
17. Perry, J. H., and C. H. Chilton, Chemical Engineers' Handbook, Figure 5-33, McGraw-Hill (1973).
18. Soda, M., et al., "Experimental Study on Transient Phenomena in Steam-Water Mixtures Flowing Through a Large Pipe for Geothermal Power Stations," Second United Nations Symposium on the Development and Use of Geothermal Resources, San Francisco, pp. 1789-1795 (1970).
19. Szilas, A. and F. Patsch, "Flow in Geothermal Hot Water Wells," Geothermics, 4, pp. 79-88 (1975).
20. Taitel, Y. and A. Dukler, "A Model for Predicting Flow Regime Transitions in Horizontal and Near Horizontal Gas-Liquid Flow," AIChE Journal, 22, pp. 47-55 (1976).
21. Taitel, Y. and A. Dukler, "Transient Gas-Liquid Flow in Horizontal Pipes: Modeling the Flow Pattern Transitions," AIChE Journal, 24, pp. 920-934 (1978).
22. Toliva, E., "Flow in Geothermal Wells (An Analysis Study)," Geothermics, 1, pp. 141-145 (1972).
23. Takahashi, Y., et al., "An Experiment Pipeline Transportaion of Steam-Water Mixtures at Otake Geothermal Field," United Nations Symposium on the Development and Use of Geothermal Resources, San Francisco, 2, pp. 882-891 (1970).

APPLICABLE REPORTS FOR THE GLEF

The following is a list of documents produced for SDG&E related to the GLEF. Other related documents were produced under separate contracts and are not included here.

1973 Geothermal Field Test Report, San Diego Gas & Electric.

1974 Geothermal Field Test Report, San Diego Gas & Electric.

San Diego Gas & Electric, Pioneering Geothermal Test Work in the Imperial Valley of Southern California, USA, G. L. Lombard and J. M. Nugent.

Design Guide for Geothermal Test Facility, San Diego Gas & Electric, G. L. Lombard, August 20, 1974.

Feasibility Study for Sulfur Elimination Geothermal Test Facility, Niland, California, The Ben Holt Company, November 26, 1974.

50,000 kw Geothermal Demonstration Plant Niland KGRA Imperial Valley, California San Diego Gas & Electric May 10, 1975.

"Heat Exchanger Test with Moderately Saline Geothermal Brine", G. L. Lombard, San Diego Gas & Electric, August, 1975.

Geothermal Loop Experimental Facility Bi-Monthly Reports - September and November, 1976, January, March, May, July, 1977, San Diego Gas & Electric.

Geothermal Loop Experimental Facility Quarterly Reports - October, 1977, January, April, July, October, 1978, January, April, July, 1979, San Diego Gas & Electric.

Geothermal Loop Experimental Facility Annual Reports - October, 1977, October, 1978, San Diego Gas & Electric.

Detailed Test Program for the Niland Geothermal Test Facility Final Report Bechtel Corporation, September, 1976.

Brine Reinjection Pump Report January, 1977, San Diego Gas & Electric Company.

"Start-up and Test Operations of the Geothermal Loop Experimental Facility", G. L. Lombard, San Diego Gas & Electric, February, 1977.

"Recent Operational Experience at the SDG&E/ERDA Niland Geothermal Loop Experimental Facility", (GRC, Transactions, Vol. 1), W. O. Jacobson, San Diego Gas & Electric May, 1977.

"Scaling and Corrosion in an Experimental Geothermal Power Plant", H. K. Bishop, San Diego Gas & Electric and J. R. Bricarello, Westec Inc., June, 1977.

"Operation of a Geothermal Loop Experimental Facility", W. O. Jacobson, San Diego Gas & Electric, November, 1977.

"Performance of a 10 MWe Geothermal Energy Conversion Test Facility", W. O. Jacobson, San Diego Gas & Electric, December, 1977.

Feasibility and Risk Study of a Geothermal Power Plant at the Salton Sea KGRA, Bechtel National Inc., and The Ben Holt Company, May 10, 1978.

Some technical Risks in Geothermal, T. R. Fick, A. Renton, A. N. Rogers, Bechtel National Inc., EPRI 2nd Geothermal Scale conference, June 20-23, 1978 TAOS N.M.

Feasibility Study Direct Contact Heat Exchanger, The Ben Holt Co., November 16, 1978, Holt Job No. 7820.

Surge Control Study for the Geothermal Loop Experimental Facility, The Ben Holt Company, December 14, 1978.

"Operational Experience at the SDG&E/ERDA Niland Geothermal Loop Experimental Facility", G. L. Lombard, San Diego Gas & Electric.

"Operational History of the Geothermal Loop Experimental Facility at the Salton Sea KGRA", W. O. Jacobson, San Diego Gas & Electric, 1978.

"Geothermal Loop Experimental Facility Update", W. O. Jacobson, San Diego Gas & Electric, 1978.

"Geothermal Loop Experimental Facility Update", W. O. Jacobson, San Diego Gas & Electric, 1979.

Geothermal Energy A Varied and Challenging Resource, February 2, 1979, Bechtel National, Inc.

Geothermal Loop Experimental Facility Direct Contract Heat Exchanger Program, Daedalean Associates, Inc., January, 1980.

**The Development of a Cavitating Descaling Technique for
On-Line Geothermal Pipe and Component Cleaning and
Scale Removal, Stephen C. Howard and William H. Bohl,
Daedalean Associates, Inc., January, 1980.**

Monthly Status Reports, San Diego Gas & Electric.

Monthly Status Reports, Bechtel National, Inc.

GLEF PROCESS SHEET 1 OF 2

		WEEK OF MAY 27, 1979							
CLARIFIER INFLUENT	DATE	27	28	29	30	31	1	2	AVG
TEMPERATURE °F					218	218	218	217	218
TOTAL FLOW					999	1010	995	1009	1003
RECYCLE FLOW					604	629	612	622	617
SILICA PPM								371	371
SUSPENDED SOLIDS							55	274	165
BARIUM (BA)							189		189
IRON (FE)							347		347
LEAD (PB)							70.3		70.3
SULFATE (SO ₄)							82		82
PH (R-C 155")							5.53		5.53
NTU							73		73

CLARIFIER EFFLUENT								AVG
TEMPERATURE				193	212	215	215	209
TOTAL FLOW (C-2)				999	1010	995	1009	1003
SILICA PPM						198	220	209
SUSPENDED SOLIDS						80	248	164
TURBIDITY (NTW)						27	12.7	20
BARIUM (BA)						168		168
IRON (FE)						319		319
LEAD (PB)						64.9		64.9
SULFATE (SO ₄)						68		68
PH						5.12		5.12

CLARIFIER								AVG
UPFLOW VELOCITY - GPM/FT ²				.45	.45	.45	.45	.45
TURBINE SETTING				2.5	3	3	3	3
RAKE SETTING				1.5	2	2	2	2
RAKE TORQUE %						2	2	2
% SOLIDS - REACTION ZONE						.1486	.3045	.2265
% SOLIDS - DRUM TUBE								
% SOLIDS - 16" LEVEL						.06		.06
% SOLIDS - 50" LEVEL						.01		.01
% SOLIDS - 104" LEVEL								
% SOLIDS - 158" LEVEL								
SETTLING RATE (GPM/FT ²)								

THICKENER								AVG
WEIR OVERFLOW % SOLIDS								
TEMPERATURE °F								
BULK DENSITY LBS/FT ³								
UNDERFLOW % SOLIDS								

• PLANT OR ITEM NOT IN SERVICE
REMARKS:

GLEF PROCESS SHEET 2 OF 2

		WEEK OF MAY 27, 1979						
		27	28	29	30	31	1	2
SVG INFLUENT	DATE							AVG
CYCLE TIME HRS. # 1 CELL								
# 2 CELL								
# 3 CELL								
SUSPENDED SOLIDS								
TURBIDITY NTU								
SILICA PPM								
TEMPERATURE °F								
FLOW GPM								
PH								
SVG EFFLUENT								AVG
SUSPENDED SOLIDS MG/L								
TURBIDITY NTU								
SILICA PPM								
TEMPERATURE °F								
FLOW GPM								
PH								
FILTER BED PRESSURE DROP/HR								
FILTER PRESS								AVG
FEED								
PRESSURE PSIG								
TEMPERATURE °F								
% SOLIDS BY WT.								
FILTRATE								
SUSPENDED SOLIDS MG/L								
TURBIDITY NTU								
FILTER CAKE								
% SOLIDS								
BULK DENSITY LB/CUFT ³								
INJECTION PUMP								AVG
DISCHARGE PRESSURE PSIG					468	446	475	478
								467
INJECTION WELLHEAD								AVG
TEMPERATURE °F					193	200	205	210
PRESSURE PSIG					468	468		376
FLOW GPM					395	381	383	387
SILICA PPM								386
SUSPENDED SOLIDS MG/L								
INJECTIVITY GPM/PSIG								

GLEF PROCESS SHEET 1 OF 2

		WEEK OF JUNE 3, 1979							
CLARIFIER INFLUENT	DATE	3	4	5	6	7*	8*	9*	AVG
TEMPERATURE °F		217	208	220	225				217
TOTAL FLOW		1009	1110	1172	1173				1116
RECYCLE FLOW		622	625	632	632				628
SILICA PPM		371	371	383	374				375
SUSPENDED SOLIDS			94	64	135				98
BARIUM (BA)			213						213
IRON (FE)			358						358
LEAD (PB)			71						71
SULFATE (SO ₄)			63						63
PH (R-C 155")			5.05						5.05
NTU		25	57	85	93				65
CLARIFIER EFFLUENT									AVG
TEMPERATURE		215	215	214	213				214
TOTAL FLOW (C-2)		1009	1110	1172	1173				1116
SILICA PPM		223	222	219	213				219
SUSPENDED SOLIDS			64	116	93				91
TURBIDITY (NTW)			24	24	23				24
BARIUM (BA)			152						152
IRON (FE)			334						334
LEAD (PB)			66						66
SULFATE (SO ₄)			49						49
PH			4.57						4.57
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²		.45	.50	.53	.53				.50
TURBINE SETTING		3	3	3.5	4				3.4
RAKE SETTING		2	2	3.5	4				2.9
RAKE TORQUE %				2	3				2.5
% SOLIDS - REACTION ZONE			.3353	.44	.75				.51
% SOLIDS - DRUM TUBE			.2						.2
% SOLIDS - 16" LEVEL			.35						.35
% SOLIDS - 50" LEVEL			.05						.05
% SOLIDS - 104" LEVEL			0						0
% SOLIDS - 158" LEVEL			0						0
SETTLING RATE (GPM/FT ²)		1.42	2.7		3				2.4
THICKENER									AVG
WEIR OVERFLOW % SOLIDS		*	*	*	*	*	*	*	*
TEMPERATURE °F		*	*	*	*	*	*	*	*
BULK DENSITY LBS/FT ³		*	*	*	*	*	*	*	*
UNDERFLOW % SOLIDS		*	*	*	*	*	*	*	*

* PLANT OR ITEM NOT IN SERVICE
REMARKS:

GLEF PROCESS SHEET 2 OF 2

		WEEK OF JUNE 3, 1979							
SVG INFLUENT	DATE	3	4	5	6	7*	8*	9*	AVG
CYCLE TIME HRS. # 1 CELL									
# 2 CELL									
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
FILTER BED PRESSURE DROP/HR									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG									
TEMPERATURE °F									
% SOLIDS BY WT.									
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS									
BULK DENSITY LB/CUFT ³									
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG		485	456	468	464				468
INJECTION WELLHEAD									AVG
TEMPERATURE °F		210	211	212	211				211
PRESSURE PSIG		378	440	460	409				421
FLOW GPM		387	485	540	541				488
SILICA PPM									
SUSPENDED SOLIDS MG/L									

GLEF PROCESS SHEET 1 OF 2

		WEEK OF JUNE 10, 1979							
CLARIFIER INFLUENT	DATE	10*	11	12	13	14	15	16	AVG
TEMPERATURE °F			191	215	212	213	212	212	209
TOTAL FLOW			1039	1141	1158	1148	1130	1209	1138
RECYCLE FLOW			539	639	636	632	622	674	624
SILICA PPM					388	353	373	350	366
SUSPENDED SOLIDS				260	725	693	187	219	417
BARIUM (BA)				144		199	171		171
IRON (FE)				156		298	296		250
LEAD (PB)				53		68	66.2		62
SULFATE (SO ₄)						23			23
PH (R-C 155")				5.72	5.39	5.5	5.48		5.52
NTU									
CLARIFIER EFFLUENT									AVG
TEMPERATURE			205	211	215	215	215	216	213
TOTAL FLOW (C-2)			1039	1141	1158	1148	1130	1209	1138
SILICA PPM				112	196	213	193	225	188
SUSPENDED SOLIDS				30	73	75	101	90	74
TURBIDITY (NTW)									
BARIUM (BA)				147		168	157		157
IRON (FE)				144		234	275		218
LEAD (PB)				51		59	64.9		58
SULFATE (SO ₄)						7			7
PH				5.16	5.39	5.2	5.06		5.2
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²			.47	.51	.52	.52	.51	.54	.51
TURBINE SETTING			4	4	4	4	4	4	4
RAKE SETTING			3	4	4	4	4	4	3.8
RAKE TORQUE %			2	2	3	5	8	15	5.8
% SOLIDS - REACTION ZONE				1.36	1.0	.5	1.12	.2	.84
% SOLIDS - DRUM TUBE				.30		.65	2.20		1.05
% SOLIDS - 16" LEVEL				.58		1.34	1.49		1.14
% SOLIDS - 50" LEVEL				.04		.05	.05		.046
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)								1.9	1.9
THICKENER									AVG
WEIR OVERFLOW % SOLIDS			*	*	*	*	*	*	*
TEMPERATURE °F			*	*	*	*	*	*	*
BULK DENSITY LBS/FT ³			*	*	*	*	*	*	*
UNDERFLOW % SOLIDS			*	*	*	*	*	*	*

* PLANT OR ITEM NOT IN SERVICE
REMARKS:

GLEF PROCESS SHEET 2 OF 2

		WEEK OF JUNE 10, 1979							
SVG INFLUENT	DATE	10*	11	12	13	14	15	16	AVG
CYCLE TIME HRS. # 1 CELL									
# 2 CELL									
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
FILTER BED PRESSURE DROP/HR									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG									
TEMPERATURE °F									
% SOLIDS BY WT.									
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS									
BULK DENSITY LB/CUFT ³									
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG		506	467	462	465	495	470		478
INJECTION WELLHEAD									AVG
TEMPERATURE °F		188	210	211	212	213	215		208
PRESSURE PSIG		350	395	377	352	395	355		371
FLOW GPM		500	502	522	516	508	535		514
SILICA PPM									
SUSPENDED SOLIDS MG/L									
INJECTIVITY GPM/PSIG									

GLEF PROCESS SHEET 1 OF 2

		WEEK OF JUNE 17, 1979							
CLARIFIER INFLUENT	DATE	17	18	19	20*	21*	22*	23*	AVG
TEMPERATURE °F		210	212	193					205
TOTAL FLOW		1259	1260	1284					1268
RECYCLE FLOW		740	736	708					728
SILICA PPM		370	395						383
SUSPENDED SOLIDS		183	223						203
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH (R-C 155")			5.23						5.23
NTU									

CLARIFIER EFFLUENT									AVG
TEMPERATURE		216	214	211					214
TOTAL FLOW (C-2)		1259	1260	1284					1268
SILICA PPM		205	202						204
SUSPENDED SOLIDS		105	125						115
TURBIDITY (NTW)		24	25	32					27
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH			4.81						4.81

CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²		.57	.57	.58					.57
TURBINE SETTING		4.3	5	5					4.8
RAKE SETTING		4	4	4					4
RAKE TORQUE %		10	13	9					10.7
% SOLIDS - REACTION ZONE		1.98	2.16	2.79					2.31
% SOLIDS - DRUM TUBE			1.93						1.93
% SOLIDS - 16" LEVEL			.55						.55
% SOLIDS - 50" LEVEL			.15						.15
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)		1.54	2.03	2.13					1.9

THICKENER									AVG
WEIR OVERFLOW % SOLIDS									
TEMPERATURE °F									
BULK DENSITY LBS/FT ³			98.3						98.3
UNDERFLOW % SOLIDS									

* PLANT OR ITEM NOT IN SERVICE
REMARKS:

GLEF PROCESS SHEET 2 OF 2

		WEEK OF JUNE 17, 1979							
		17	18	19	20*	21*	22*	23*	AVG
SVG INFLUENT	DATE								
CYCLE TIME HRS. # 1 CELL									
# 2 CELL									
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
FILTER BED PRESSURE DROP/HR									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG									
TEMPERATURE °F									
% SOLIDS BY WT.									
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS									
BULK DENSITY LB/CUFT ³									
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG		453	455	495					468
INJECTION WELLHEAD									AVG
TEMPERATURE °F		214	216	212					214
PRESSURE PSIG		358	360	365					361
FLOW GPM		519	524	576					540
SILICA PPM									
SUSPENDED SOLIDS MG/L									
INJECTIVITY GPM/PSIG									

GLEF PROCESS SHEET 1 OF 2

		WEEK OF JUNE 24, 1979							
CLARIFIER INFLUENT	DATE	24*	25*	26*	27*	28	29	30	AVG
TEMPERATURE °F						214	208		211
TOTAL FLOW						1171	1143	1194	1169
RECYCLE FLOW						650	653	651	651
SILICA PPM								361	361
SUSPENDED SOLIDS									
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH (R-C 155")									
NTU									
CLARIFIER EFFLUENT									AVG
TEMPERATURE						169	207		188
TOTAL FLOW (C-2)						1171	1143	1194	1169
SILICA PPM								263	263
SUSPENDED SOLIDS								494	494
TURBIDITY (NTW)						18	19.2	29.7	22.3
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH									
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²						.53	.51	.54	.53
TURBINE SETTING						3.3	3.7	4	3.7
RAKE SETTING						4	4	4	4.0
RAKE TORQUE %						8	11.6	14	11.2
% SOLIDS - REACTION ZONE								0.1	0.1
% SOLIDS - DRUM TUBE									
% SOLIDS - 16" LEVEL									
% SOLIDS - 50" LEVEL									
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)									
THICKENER									AVG
WEIR OVERFLOW % SOLIDS									
TEMPERATURE °F									
BULK DENSITY LBS/FT ³									
UNDERFLOW % SOLIDS									

* PLANT OR ITEM NOT IN SERVICE
REMARKS:

GLEF PROCESS SHEET 2 OF 2

		WEEK OF JUNE 24, 1979							
SVG INFLUENT	DATE	24*	25*	26*	27*	28	29	30	AVG
CYCLE TIME HRS. # 1 CELL									
# 2 CELL									
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
FILTER BED PRESSURE DROP/HR									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG									
TEMPERATURE °F									
% SOLIDS BY WT.									
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS									
BULK DENSITY LB/CUFT ³									
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG						487	489	490	489
INJECTION WELLHEAD									AVG
TEMPERATURE °F						132	161		146
PRESSURE PSIG						236	293	336	288
FLOW GPM						521	490	543	518
SILICA PPM									
SUSPENDED SOLIDS MG/L									
INJECTIVITY GPM/PSIG									

GLEF PROCESS SHEET 1 OF 2

		WEEK OF JULY 1, 1979							
CLARIFIER INFLUENT	DATE	1	2	3	4	5*	6*	7	AVG
TEMPERATURE °F								224	224
TOTAL FLOW		1161	1155	1114	1107			1166	1141
RECYCLE FLOW		640	635	629	630			639	635
SILICA PPM			395	388	398				394
SUSPENDED SOLIDS					222			203	212
BARIUM (BA)				154					154
IRON (FE)				293					293
LEAD (PB)				71					71
SULFATE (SO ₄)				42					42
PH (R-C 155")				5.5				5.65	5.6
NTU					36			19	36
CLARIFIER EFFLUENT									AVG
TEMPERATURE				223	218			223	220
TOTAL FLOW (C-2)		1161	1155	1114	1107			1166	1141
SILICA PPM			260	198	189				210
SUSPENDED SOLIDS			57	118	117			143	106
TURBIDITY (NTW)		27	12.7	13	12.4			15	16.3
BARIUM (BA)				126					126
IRON (FE)				283					283
LEAD (PB)				71					71
SULFATE (SO ₄)				28					28
PH				5.6				5.4	5.6
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²		.52	.52	.50	.49			.52	.51
TURBINE SETTING		4	4.5	5	5.25			5.25	4.7
RAKE SETTING		4	4	4	4			4	4
RAKE TORQUE %		17.2	14.3	7.9	9.2			8	12.2
% SOLIDS - REACTION ZONE		.07	.09	1.47	1.47			1.97	1.45
% SOLIDS - DRUM TUBE									
% SOLIDS - 16" LEVEL									
% SOLIDS - 50" LEVEL									
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)								1.76	1.99
THICKENER									AVG
WEIR OVERFLOW % SOLIDS									
TEMPERATURE °F									
BULK DENSITY LBS/FT ³									
UNDERFLOW % SOLIDS									

* PLANT OR ITEM NOT IN SERVICE

REMARKS: FILTER PRESS 9.3 TONS DRY 7-4

GLEF PROCESS SHEET 2 OF 2

		WEEK OF JULY 1, 1979							
SVG INFLUENT	DATE	1	2	3	4	5	6	7	AVG
CYCLE TIME HRS. # 1 CELL									
# 2 CELL									
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
FILTER BED PRESSURE DROP/HR									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG									
TEMPERATURE °F									
% SOLIDS BY WT.				67					67
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS									
BULK DENSITY LB/CUFT ³				100					100
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG	496	498	501	506				512	500
INJECTION WELLHEAD									AVG
TEMPERATURE °F			221	220				221	221
PRESSURE PSIG	304	306	287	270				272	291
FLOW GPM	521	520	485	477				527	506
SILICA PPM									
SUSPENDED SOLIDS MG/L									
INJECTIVITY GPM/PSIG									

GLEF PROCESS SHEET 1 OF 2

		WEEK OF JULY 8, 1979							
CLARIFIER INFLUENT	DATE	8	9	10	11	12	13	14	AVG
TEMPERATURE °F		225	223	226	225	224	224	225	225
TOTAL FLOW		1128	1104	993	1097	1094	1107	1093	1088
RECYCLE FLOW		630	603	514	577	589	563	567	577
SILICA PPM			374					430	402
SUSPENDED SOLIDS		203					126	114	148
BARIUM (BA)			133						133
IRON (FE)			288						288
LEAD (PB)			62						62
SULFATE (SO ₄)			47						47
PH (R-C 155")		5.6	5.7						5.65
NTU		13	17						15
CLARIFIER EFFLUENT									AVG
TEMPERATURE		222	222						222
TOTAL FLOW (C-2)		1128	1104	993	1097	1094	1107	1093	1088
SILICA PPM			184					198	191
SUSPENDED SOLIDS		143					87	91	107
TURBIDITY (NTW)		14	14	29	22	16	14	14	17.6
BARIUM (BA)			122						122
IRON (FE)			236						236
LEAD (PB)			59						59
SULFATE (SO ₄)			23						23
PH		5.3	5.4						5.35
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²		.51	.50	.45	.49	.49	.50	.49	.49
TURBINE SETTING		5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25
RAKE SETTING		4	4	4	4	2	2	2	3.1
RAKE TORQUE %		8	9	11	11	5	4	4	7.4
% SOLIDS - REACTION ZONE		1.9	2.1	1.7	1.32	1.56	1.78	1.43	1.68
% SOLIDS - DRUM TUBE			2.44		2.2				2.3
% SOLIDS - 16" LEVEL			2.59						2.59
% SOLIDS - 50" LEVEL			.11						.11
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)		2.2	1.8	1.7		2.2	2.58	1.9	2.1
THICKENER									AVG
WEIR OVERFLOW % SOLIDS									
TEMPERATURE °F									
BULK DENSITY LBS/FT ³									
UNDERFLOW % SOLIDS		15.6	34.7						25.1

* PLANT OR ITEM NOT IN SERVICE

REMARKS: 7/12 - SVG START-UP - RAKE SETTING CHANGE

GLEF PROCESS SHEET 2 OF 2

		WEEK OF JULY 8, 1979							
SVG INFLUENT	DATE	8	9	10	11	12	13	14	AVG
CYCLE TIME HRS. # 1 CELL									
# 2 CELL									
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU						.81	.5		.66
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
FILTER BED PRESSURE DROP/HR									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG									
TEMPERATURE °F									
% SOLIDS BY WT.				20.1	36.1				28.1
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS		70							70
BULK DENSITY LB/CUFT ³		101							101
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG		510	512	531	505	505	508	502	510
INJECTION WELLHEAD									AVG
TEMPERATURE °F		221	217	208	212	212	211	211	213
PRESSURE PSIG		276	269	231	280	295	295	302	278
FLOW GPM		498	501	479	520	505	544	526	510
SILICA PPM									
SUSPENDED SOLIDS MG/L									
INJECTIVITY GPM/PSIG									

GLEF PROCESS SHEET 1 OF 2

		WEEK OF JULY 15, 1979							
CLARIFIER INFLUENT	DATE	15	16	17	18	19*	20	21	AVG
TEMPERATURE °F		224	224	223	222		223	223	223
TOTAL FLOW		1084	1104	1154	1121		1171	1371	1168
RECYCLE FLOW		568	522	606	606		654	828	631
SILICA PPM		412	453	328	477			361	406
SUSPENDED SOLIDS		100	135	86				121	110
BARIUM (BA)			143		152				148
IRON (FE)			248		270				259
LEAD (PB)			58.9		64				61
SULFATE (SO ₄)					60				60
PH (R-C 155")			5.47		5.54				5.5
NTU									
CLARIFIER EFFLUENT									AVG
TEMPERATURE		210	215	218	215		197	214	212
TOTAL FLOW (C-2)		1084	1104	1150	1121		1171	1371	1168
SILICA PPM		190	179	164	175			172	176
SUSPENDED SOLIDS		76	112	48				57	73
TURBIDITY (NTW)		13	14	11	13		15	14	13
BARIUM (BA)			117		136				127
IRON (FE)			240		273				257
LEAD (PB)			51.9		55				53.5
SULFATE (SO ₄)					29				29
PH			5.03		5.08				5.05
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²		.49	.5	.52	.5		.53	.62	.53
TURBINE SETTING		5.25	5.28	5.25	5.25		5.25	5.5	5.3
RAKE SETTING		2	3	3	3		3.5	3.5	3
RAKE TORQUE %		4	5	5	5		11	4	6
% SOLIDS - REACTION ZONE		1.1	1.7	1.97	1.2		.94	2.1	1.5
% SOLIDS - DRUM TUBE			4.42		5.31				4.9
% SOLIDS - 16" LEVEL			1.74		1.96				1.85
% SOLIDS - 50" LEVEL			.05		.03				.04
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)		2.06	1.71	1.87	1.9			2.25	2.0
THICKENER									AVG
WEIR OVERFLOW % SOLIDS									
TEMPERATURE °F									
BULK DENSITY LBS/FT ³									
UNDERFLOW % SOLIDS									

* PLANT OR ITEM NOT IN SERVICE
REMARKS:

GLEF PROCESS SHEET 2 OF 2

07/15/79 11:46

		WEEK OF JULY 15, 1979							
SVG INFLUENT	DATE	15	16	17	18	19*	20	21	AVG
CYCLE TIME HRS. # 1 CELL									
# 2 CELL					8				8
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU					4.5				4.5
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG BACKWASH									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU					30				30
FLOW GPM					21				21
BACKWASH CYCLE TIME-MIN.					4.75				4.75
AIR SCOUR CFM					3		3	3	3
REMOVAL EFFICIENCY									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG		100	100	100	100			87	97
TEMPERATURE °F					192			170	181
% SOLIDS BY WT.									
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS									
BULK DENSITY LB/CUFT ³									
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG		605	519	490	512		604	481	502
INJECTION WELLHEAD									AVG
TEMPERATURE °F									
PRESSURE PSIG		195	185	200	180		253	285	216
FLOW GPM		516	582	548	515		517	543	537
SILICA PPM									
SUSPENDED SOLIDS MG/L									
INJECTIVITY GPM/PSIG		2.6	3.2	2.7	2.9		2.0	1.9	2.6

GLEF PROCESS SHEET 1 OF 2

		WEEK OF JULY 22, 1979							
CLARIFIER INFLUENT	DATE	22	23	24	25	26**	27	28	AVG
TEMPERATURE °F		223	224	224	224	223	223	222	223
TOTAL FLOW		1390	1374	1369	1305	1291	1451	1463	1378
RECYCLE FLOW		842	857	863	769	768	864	879	835
SILICA PPM		372						372	372
SUSPENDED SOLIDS		103						165	134
BARIUM (BA)								175	175
IRON (FE)									
LEAD (PB)								72.6	72.6
SULFATE (SO ₄)								66	66
PH (R-C 155")								5.5	5.5
NTU									
CLARIFIER EFFLUENT									AVG
TEMPERATURE		215	215	215	205	214	215	215	213
TOTAL FLOW (C-2)		1390	1374	1369	1305	1291	1451	1463	1378
SILICA PPM		185						185	185
SUSPENDED SOLIDS		73						92	83
TURBIDITY (NTW)		13	14	14	14	13	12	12	13
BARIUM (BA)		145						150	148
IRON (FE)		279							279
LEAD (PB)		68						67.7	67.9
SULFATE (SO ₄)		33						35	34
PH		5.1						5.1	5.1
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²		.63	.62	.62	.59	.58	.65	.66	.62
TURBINE SETTING		5.5	5.5	5.5	5.5	5.5	5.5	5.5	5.5
RAKE SETTING		3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
RAKE TORQUE %		5	5	5	4	4	5	5	5
% SOLIDS - REACTION ZONE		1.80	2.3			0.7	1.1	1.47	1.47
% SOLIDS - DRUM TUBE									
% SOLIDS - 16" LEVEL									
% SOLIDS - 50" LEVEL									
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)		2.4	1.9	1.75		1.21	2.34	2.17	1.96
THICKENER									AVG
WEIR OVERFLOW % SOLIDS									
TEMPERATURE °F									
BULK DENSITY LBS/FT ³									
UNDERFLOW % SOLIDS									

* PLANT OR ITEM NOT IN SERVICE
REMARKS: **START UP DATE

GLEF PROCESS SHEET 2 OF 2

		WEEK OF JULY 22, 1979							
		22	23	24	25	26**	27	28	AVG
SVG INFLUENT	DATE								
CYCLE TIME HR	# 1 CELL					4	6.75	15	8.58
	# 2 CELL					3.5	12.5	9.5	7.8
	# 3 CELL					6	9.7	9.5	8.4
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F	SAME AS CLARIFIER EFFLUENT								
GLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS								4.0	4.0
TURBIDITY NTU									
SILICA PPM								191	191
TEMPERATURE °F									
FLOW GPM								4.9	4.9
PH									
FILTER BED PRESSURE DROP/HR									
SVG BACKWASH									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FLOW GPM									
BACKWASH CYCLE TIME-MIN.						4.5	4.5	4.5	4.5
AIR SCOUR CFM						3.2	3.5	3.2	3.3
REMOVAL EFFICIENCY									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG		90	93	85	90	94	N.W.	N.W.	90
TEMPERATURE °F		168	163	170	170	173	"	"	169
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG		488	490	493	486	492	480	471	486
INJECTION WELLHEAD									AVG
TEMPERATURE °F									
PRESSURE PSIG		192	194	190	175	187	190	205	190
FLOW GPM		548	517	506	535	523	587	584	543
SILICA PPM									
SUSPENDED SOLIDS MG/L									
INJECTIVITY		2.9	2.7	2.7	3.1	2.8	3.1	2.9	2.9

GLEF PROCESS SHEET 1 OF 2

		WEEK OF JULY 29, 1979							
CLARIFIER INFLUENT	DATE	29	30	31	1	2	3	4	AVG
TEMPERATURE °F		223	223	224	224	224	224	224	224
TOTAL FLOW		1407	1325	1291	1274	1264	1361	1270	1313
RECYCLE FLOW		756	760	767	763	751	743	750	756
SILICA PPM			389				375		382
SUSPENDED SOLIDS (PPM)			160	151	141		145		149
BARIUM (BA)			147		158				153
IRON (FE)			329		318				324
LEAD (PB)			72		77				75
SULFATE (SO ₄)			62		77	55			65
PH (R-C 155")			5.7		5.6	5.6	5.6		5.6
CLARIFIER EFFLUENT									AVG
TEMPERATURE		215	216	215	215	215	216	215	215
TOTAL FLOW (C-2)		1407	1325	1291	1274	1264	1361	1270	1313
SILICA (PPM)			205				200		203
SUSPENDED SOLIDS (PPM)			90	103	94	80	92		92
TURBIDITY (NTW)			13	11	13	14	14	14	13
BARIUM (BA)			132		132				132
IRON (FE)			329		321				325
LEAD (PB)			70.3		73				72
SULFATE (SO ₄)			44		50	35			43
PH			5.2		5.0	5.1	5.3		5.2
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²		.63	.60	.58	.57	.57	.61	.57	.59
TURBINE SETTING		5.5	5.5	5.5	5.5	5.5	5.5	5.5	5.5
RAKE SETTING		3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
RAKE TORQUE %		5	4	5	5	4	4	5	5
% SOLIDS - REACTION ZONE		2.1	2.54	1.56	1.90	2.6	2.6		2.2
% SOLIDS - DRUM TUBE			3.06			3.1			3.1
% SOLIDS - 16" LEVEL			1.13			2.8			2.0
% SOLIDS - 50" LEVEL			0.05			0.1			0.08
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)		1.9	2.2		2.1	2.1	2.0	2.8	2.2
THICKENER									AVG
WEIR OVERFLOW % SOLIDS									
TEMPERATURE °F									
BULK DENSITY LBS/FT ³									
UNDERFLOW % SOLIDS									

* PLANT OR ITEM NOT IN SERVICE
REMARKS: P = 1.18

GLEF PROCESS SHEET 2 OF 2

		WEEK OF JULY 29, 1979							
SVG INFLUENT	DATE	29	30	31	1	2	3	4	AVG
CYCLE TIME HR # 1 CELL		12	25	20	16	19	23	22	20
# 2 CELL		10	10.5	20	14	18	14	15	15
# 3 CELL		8	14	8.5	20	9	14	21	14
SUSPENDED SOLIDS (PPM)			90	103	94		92		93
TURBIDITY NTU			13	11	13	14	14	14	13
SILICA (PPM)			205				200		203
TEMPERATURE °F									
GLOW GPM									
PH			5.2			5.1	5.3		5.2
SVG EFFLUENT									AVG
SUSPENDED SOLIDS (PPM)			2.5	1.7	6.1	15.7	15.9	10.0	8.7
TURBIDITY NTU									
SILICA PPM			217				205		211
TEMPERATURE °F									
FLOW GPM									
PH			5.0			4.8	5.1		5.0
FILTER BED PRESSURE DROP/HR									
SVG BACKWASH									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FLOW GPM									
BACKWASH CYCLE TIME-MIN.		4.5	4.5	4.5	4.5	4.5	5.5	5.5	4.8
AIR SCOUR CFM		3.1	3.1	3.3	3.1	3.1	3.0	3.1	3.1
REMOVAL EFFICIENCY									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG		95	85	93	95	86	73	88	88
TEMPERATURE °F		173	160	195	179	190	187	189	182
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG		463	468	474	486	476	465	480	473
INJECTION WELLHEAD									AVG
TEMPERATURE °F		207	207	206	206	208	208	208	207
PRESSURE PSIG		150	130	120	146	129	122	117	131
FLOW GPM		651	565	524	511	513	618	520	557
SILICA PPM									
SUSPENDED SOLIDS MG/L									
INJECTIVITY GPM/PSIG		43	4.3	4.4	3.5	4.0	5.1	4.4	4.3

GLEF PROCESS SHEET 1 OF 2

		WEEK OF AUGUST 5, 1979							
CLARIFIER INFLUENT	DATE	5	6	7	8	9	10	11	AVG
TEMPERATURE °F		224	224	224	224	224	224	223	224
TOTAL FLOW		1294	1303	1306	1274	1300	1177	1226	1268
RECYCLE FLOW		775	774	762	756	755	751	785	765
SILICA PPM					403		404	400	402
SUSPENDED SOLIDS (PPM)				139	99	472	128	119	191
BARIUM (BA) MG/L							152		152
IRON (FE)							288		288
LEAD (PB)							71		71
SULFATE (SO ₄)				62	86	71	55		68
PH (R-C 155")				5.6	5.7	5.5	5.5		5.6
NTU									

CLARIFIER EFFLUENT									AVG
TEMPERATURE		215	215	215	215	215	215	215	215
TOTAL FLOW		1294	1303	1306	1274	1300	1177	1226	1268
SILICA PPM					213		187	200	200
SUSPENDED SOLIDS				99	106	100	97	155	111
TURBIDITY		13	14	13	14	13	13	14	13
BARIUM (BA)							129		129
IRON (FE)							285		285
LEAD (PB)							66		66
SULFATE (SO ₄)				42	42	42	35		40
PH				5.3	5.3	5.1	5.2		5.2

CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²		.58	.59	.59	.61	.62	.57	.59	.59
TURBINE SETTING		6.5	5.5	5.5	5.5	5.5	5.5	5.5	5.6
RAKE SETTING		3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
RAKE TORQUE %		5	5	5	5	5	5	5	5
% SOLIDS - REACTION ZONE				2.8	3.4	3.8	4.1	4.0	3.6
% SOLIDS - DRUM TUBE				3.0	3.6	4.0	4.7		3.8
% SOLIDS - 16" LEVEL				3.2	3.5	3.6	3.8		3.5
% SOLIDS - 50" LEVEL				0.08	0.06	0.04	0.06		0.06
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)		2.0	1.5	1.3			1.06	1.2	1.4

THICKENER								AVG
WEIR OVERFLOW % SOLIDS								
TEMPERATURE °F								
BULK DENSITY LBS/FT ³								
UNDERFLOW % SOLIDS					15.1			15.1

• PLANT OR ITEM NOT IN SERVICE

** NOT TRUE TURBIDITY READING ON AUG. 7, 8, & 9.

REMARKS: CLARIFIER UNDERFLOW - 6.1 %

GLEF PROCESS SHEET 2 OF 2

		WEEK OF AUGUST 5, 1979							
SVG INFLUENT		5	6	7	8	9	10	11	AVG
DATE									
CYCLE TIME HR # 1 CELL		18	21	11	17	14	14	14	16
# 2 CELL		14	16	12	22	14	13	19	16
# 3 CELL		15	13	13	15	15	18	19	15
SVG EFFLUENT									AVG
SUSPENDED SOLIDS PPM				11.7	8.4	14.0	13.8	15.6	12.7
TURBIDITY NTU	**	6.9	4.8					7.0	6.2
SILICA PPM				206		189	184		193
TEMPERATURE °F		208	208	206	210	211	211	210	209
FLOW GPM									
PH				5.1	4.9	4.9			5.0
FILTER BED PRESSURE DROP/HR # 1 CELL		.9	1.0	0.1	1.0	0.7	0.7	0.8	0.7
# 2 CELL		.6	.5	0.6	1.1	1.1	0.7	0.4	0.7
# 3 CELL		.9	1.1	0.3	0.3	1.0	1.1	0.8	0.8
SVG BACKWASH									AVG
SUSPENDED SOLIDS MG/L				13,309					
TURBIDITY NTU									
FLOW GPM									
BACKWASH CYCLE TIME-MIN.		5.5	5.5	5.5	5.5	5.5	5.5	5.5	5.5
AIR SCOUR PSIG		3.2	3.2	3.1	3.2	3.2	3.1	3.2	3.2
REMOVAL EFFICIENCY									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG		86	58	88	90	90	90	90	85
TEMPERATURE °F		187	187	193	191	193	180	189	189
% SOLIDS BY WT.						15.1			15.1
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG		479	480	477	482	479	504	454	479
INJECTION WELLHEAD									AVG
TEMPERATURE °F		207	208	210	210	209	208	206	208
PRESSURE PSIG		116	117	118	114	122	107	109	115
FLOW GPM		519	529	544	518	545	426	441	503
SILICA PPM									
SUSPENDED SOLIDS MG/L									
INJECTIVITY GPM/PSIG		4.5	4.5	4.6	4.5	4.5	4.0	4.1	4.4

GLEF PROCESS SHEET 1 OF 2

		WEEK OF AUGUST 12, 1979							
CLARIFIER INFLUENT	DATE	12	13	14	15	16	17	18*	AVG
TEMPERATURE °F		223	224	223	224	222	222		223
TOTAL FLOW		1289	1315	1316	1306	1314	1358		1316
RECYCLE FLOW		857	878	875	883	916	921		888
SILICA PPM					394	440			417
SUSPENDED SOLIDS PPM					121	318			220
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)			55						55
PH (R-C 155")					5.6				5.6
NTU									

CLARIFIER EFFLUENT								AVG
TEMPERATURE		215	215	215	215	215	213	215
TOTAL FLOW		1289	1315	1316	1306	1314	1358	1316
SILICA PPM					196	215		206
SUSPENDED SOLIDS PPM					86	60		73
TURBIDITY (NTU)		15	14	14	13	13	12	14
BARIUM (BA)								
IRON (FE)								
LEAD (PB)								
SULFATE (SO ₄)			35					35
PH					5.3			5.3

CLARIFIER								AVG
UPFLOW VELOCITY - GPM/FT ²		0.58	0.59	0.59	0.59	0.59	0.61	0.59
TURBINE SETTING		5.5	5.5	5.5	5.5	5.5	5.5	5.5
RAKE SETTING		3.5	3.5	3.5	3.5	3.5	3.5	3.5
RAKE TORQUE %		7	4	4	4	5	5	5
% SOLIDS - REACTION ZONE		2.7	2.8	2.8	2.8	2.8	2.8	2.8
% SOLIDS - DRUM TUBE			4.0	4.2				4.1
% SOLIDS - 16" LEVEL			3.3	3.5				3.4
% SOLIDS - 50" LEVEL			0.06	0.07				0.06
% SOLIDS - 104" LEVEL								
% SOLIDS - 158" LEVEL								
SETTLING RATE (GPM/FT ²)		1.4	1.4	1.5	1.4	1.4	1.3	1.4

THICKENER								AVG
WEIR OVERFLOW % SOLIDS								
TEMPERATURE °F								
BULK DENSITY LBS/FT ³								
UNDERFLOW % SOLIDS				22.4	14.2			18.3
THICKENER FEED (U. UNDERFLOW)				6.6	5.8			6.2

* PLANT OR ITEM NOT IN SERVICE

** 9.4 PPM SUSPENDED SOLID THROUGH A 0.4 μ NUCLEOPORE FILTER - 12.2 (l) OF BRINE FILTERED (8-16-79).
REMARKS:

GLEF PROCESS SHEET 2 OF 2

		WEEK OF AUGUST 12, 1979							
SVG INFLUENT	DATE	12	13	14	15	16	17	18	AVG
CYCLE TIME HR # 1 CELL		14	12	19	13	16	15		15
# 2 CELL		14	18	17	16	19	17		17
# 3 CELL		16	7	19	17	16	16		15
SUSPENDED SOLIDS	**		10.8	7.0	13.2	9.4			10.1
TURBIDITY NTU		15	14	14	13	13	12		14
SILICA PPM									
TEMPERATURE °F		215	215	215	215	215	213		215
GLOW GPM		1377	1315	1404	1394	1402	1446		1390
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU		7	7	6	5	6			6
SILICA PPM			186	192	192	201			193
TEMPERATURE °F		210	209	209	210	210	210		210
FLOW GPM		1377	1315	1404	1394	1402	1446		1390
PH									
FILTER BED PRESSURE DROP/HR				5.0	5.0				5.0
SVG BACKWASH									AVG
BACKWASH CYCLE TIME-MIN.		5.5	5.5	5.5	5.5	5.5	5.5		5.5
AIR SCOUR CFM		3.2	3.2	3.2	3.1	3.3	3.4		3.2
FILTER PRESS									AVG
FEED									
PRESSURE PSIG		90	91	91	90	90	90		90
TEMPERATURE °F		200	189	190	190	186	191		191
% SOLIDS BY WT.					22.4	14.2			18.3
FILTRATE									
SUSPENDED SOLIDS MG/L					161	42			102
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS					61.3	76.8			69.1
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG		444	494	452	500	502	502		482
INJECTION WELLHEAD									AVG
TEMPERATURE °F		205	205	207	206	205	203		205
PRESSURE PSIG		110	105	103	100	100	102		103
FLOW GPM		432	437	441	423	398	437		428
SILICA PPM									
SUSPENDED SOLIDS MG/L									
		3.9	4.2	4.3	4.2	4.0	4.3		4.2

GLEF PROCESS SHEET 1 OF 2

		WEEK OF AUGUST 19, 1979							
CLARIFIER INFLUENT	DATE	19*	20*	21*	22*	23*	24*	25*	AVG
TEMPERATURE °F									
TOTAL FLOW									
RECYCLE FLOW									
SILICA PPM									
SUSPENDED SOLIDS									
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH (R-C 155")									
NTU									
CLARIFIER EFFLUENT									AVG
TEMPERATURE									
TOTAL FLOW (C-2)									
SILICA PPM									
SUSPENDED SOLIDS									
TURBIDITY (NTW)									
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH									
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²									
TURBINE SETTING									
RAKE SETTING									
RAKE TORQUE %									
% SOLIDS - REACTION ZONE									
% SOLIDS - DRUM TUBE									
% SOLIDS - 16" LEVEL									
% SOLIDS - 50" LEVEL									
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)									
THICKENER									AVG
WEIR OVERFLOW % SOLIDS									
TEMPERATURE °F									
BULK DENSITY LBS/FT ³									
UNDERFLOW % SOLIDS									

• PLANT OR ITEM NOT IN SERVICE
REMARKS:

GLEF PROCESS SHEET 2 OF 2

		WEEK OF AUGUST 19, 1979							
SVG INFLUENT	DATE	19*	20*	21*	22*	23*	24*	25*	AVG
CYCLE TIME HRS # 1 CELL									
# 2 CELL									
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
FILTER BED PRESSURE DROP/HR									
SVG BACKWASH									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FLOW GPM									
BACKWASH CYCLE TIME-MIN.									
AIR SCOUR CFM									
REMOVAL EFFICIENCY									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG									
TEMPERATURE °F									
% SOLIDS BY WT.									
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS									
BULK DENSITY LB/CUFT ³									

GLEF PROCESS SHEET 1 OF 2

		WEEK OF AUGUST 26, 1979							
CLARIFIER INFLUENT	DATE	26*	27*	28*	29*	30*	31*	1*	AVG
TEMPERATURE °F									
TOTAL FLOW									
RECYCLE FLOW									
SILICA PPM									
SUSPENDED SOLIDS									
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH (R-C 155")									
NTU									
CLARIFIER EFFLUENT									AVG
TEMPERATURE									
TOTAL FLOW (C-2)									
SILICA PPM									
SUSPENDED SOLIDS									
TURBIDITY (NTW)									
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH									
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²									
TURBINE SETTING									
RAKE SETTING									
RAKE TORQUE %									
% SOLIDS - REACTION ZONE									
% SOLIDS - DRUM TUBE									
% SOLIDS - 16" LEVEL									
% SOLIDS - 50" LEVEL									
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)									
THICKENER									AVG
WEIR OVERFLOW % SOLIDS									
TEMPERATURE °F									
BULK DENSITY LBS/FT ³									
UNDERFLOW % SOLIDS									

• PLANT OR ITEM NOT IN SERVICE
REMARKS:

GLEF PROCESS SHEET 2 OF 2

WEEK OF AUGUST 26, 1979									
SVG INFLUENT	DATE	26*	27*	28*	29*	30*	31*	1*	AVG
CYCLE TIME HRS # 1 CELL									
# 2 CELL									
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
FILTER BED PRESSURE DROP/HR									
SVG BACKWASH									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FLOW GPM									
BACKWASH CYCLE TIME-MIN.									
AIR SCOUR CFM									
REMOVAL EFFICIENCY									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG									
TEMPERATURE °F									
% SOLIDS BY WT.									
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS									
BULK DENSITY LB/CUFT ³									

GLEF PROCESS SHEET 1 OF 2

		WEEK OF SEPTEMBER 2, 1979							
CLARIFIER INFLUENT	DATE	2*	3*	4*	5	6	7	8	AVG
TEMPERATURE °F					223	225	225	225	224
TOTAL FLOW					1078	1146	1136	1110	1118
RECYCLE FLOW					686	756	756	735	733
SILICA PPM									
SUSPENDED SOLIDS									
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH (R-C 155")									
NTU									
CLARIFIER EFFLUENT									AVG
TEMPERATURE					214	216	216	216	216
TOTAL FLOW					1078	1146	1136	1110	1118
SILICA PPM									
SUSPENDED SOLIDS									
TURBIDITY									
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH									
CLARIFIER									AVG
UPFLOW VELOCITY - GPM/FT ²					.49	.52	.51	.50	.50
TURBINE SETTING					4.6	6	6	6	5.6
RAKE SETTING					3	4	4	4	3.8
RAKE TORQUE %					3	6	5.5	6	5.1
% SOLIDS - REACTION ZONE									
% SOLIDS - DRUM TUBE									
% SOLIDS - 16" LEVEL									
% SOLIDS - 50" LEVEL									
% SOLIDS - 104" LEVEL									
% SOLIDS - 158" LEVEL									
SETTLING RATE (GPM/FT ²)									
THICKENER									AVG
WEIR OVERFLOW % SOLIDS									
TEMPERATURE °F									
BULK DENSITY LBS/FT ³									
UNDERFLOW % SOLIDS									

• PLANT OR ITEM NOT IN SERVICE
REMARKS:

GLEF PROCESS SHEET 2 OF 2

		WEEK OF SEPTEMBER 2, 1979							
	DATE	2*	3*	4*	5	6	7	8	AVG
SVG INFLUENT									
CYCLE TIME HRS. # 1 CELL									
# 2 CELL									
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
FILTER BED PRESSURE DROP/HR									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG									
TEMPERATURE °F									
% SOLIDS BY WT.									
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS									
BULK DENSITY LB/CUFT ³									
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG									
INJECTION WELLHEAD									AVG
TEMPERATURE °F									
PRESSURE PSIG									
FLOW GPM					392	390	380	375	384
SILICA PPM									
SUSPENDED SOLIDS MG/L									
INJECTIVITY GPM/PSIG									

GLEF PROCESS SHEET 1 OF 2

		WEEK OF SEPTEMBER 9, 1979							
CLARIFIER INFLUENT	DATE	9	10	11	12	13	14*	15*	AVG
TEMPERATURE °F		225	225	224	225	224			225
TOTAL FLOW		1093	1095	1116	1212	1152			1134
RECYCLE FLOW		728	726	721	715	663			711
SILICA PPM									
SUSPENDED SOLIDS									
BARIUM (BA)									
IRON (FE)									
LEAD (PB)									
SULFATE (SO ₄)									
PH (R-C 155")									
NTU									

CLARIFIER EFFLUENT								AVG
TEMPERATURE		216	216	216	217	216		216
TOTAL FLOW		1093	1095	1116	1212	1152		1134
SILICA PPM								
SUSPENDED SOLIDS								
TURBIDITY								
BARIUM (BA)								
IRON (FE)								
LEAD (PB)								
SULFATE (SO ₄)								
PH								

CLARIFIER								AVG
UPFLOW VELOCITY - GPM/FT ²		.49	.49	.50	.55	.52		.51
TURBINE SETTING		6	6	6	6	6		6
RAKE SETTING		4	4	4	4	4		4
RAKE TORQUE %		5	5	6	8	8		6.4
% SOLIDS - REACTION ZONE								
% SOLIDS - DRUM TUBE								
% SOLIDS - 16" LEVEL								
% SOLIDS - 50" LEVEL								
% SOLIDS - 104" LEVEL								
% SOLIDS - 158" LEVEL								
SETTLING RATE (GPM/FT ²)								

THICKENER								AVG
WEIR OVERFLOW % SOLIDS								
TEMPERATURE °F								
BULK DENSITY LBS/FT ³								
UNDERFLOW % SOLIDS								

* PLANT OR ITEM NOT IN SERVICE
REMARKS:

GLEF PROCESS SHEET 2 OF 2

		WEEK OF SEPTEMBER 9, 1979							
SVG INFLUENT	DATE	9	10	11	12	13	14*	15*	AVG
CYCLE TIME HRS. # 1 CELL									
# 2 CELL									
# 3 CELL									
SUSPENDED SOLIDS									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
SVG EFFLUENT									AVG
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
SILICA PPM									
TEMPERATURE °F									
FLOW GPM									
PH									
FILTER BED PRESSURE DROP/HR									
FILTER PRESS									AVG
FEED									
PRESSURE PSIG									
TEMPERATURE °F									
% SOLIDS BY WT.									
FILTRATE									
SUSPENDED SOLIDS MG/L									
TURBIDITY NTU									
FILTER CAKE									
% SOLIDS									
BULK DENSITY LB/CUFT ³									
INJECTION PUMP									AVG
DISCHARGE PRESSURE PSIG									
INJECTION WELLHEAD									AVG
TEMPERATURE °F									
PRESSURE PSIG									
FLOW GPM		365	369	395	497	489			423
SILICA PPM									
SUSPENDED SOLIDS MG/L									