WSRC-TR--92-503-1

DE93 005206

SRS Scientific and Technical Abstracts

July-September 1992

Westinghouse Savannah River Company
Savannah River Site
Aiken, SC 29808

Developed during the course of work under contract no. DE-AC09-89SR18035

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

About this report

Introduction

Scientific and technical information is one of the Department of Energy's most valuable resources. For this information to be of maximum value, it must be communicated and disseminated among various parties who can put the information to some productive use, often a use that was not originally envisioned by the information's generators or authors.

This compendium is part of a series of efforts underway at SRS to communicate the information products of the site to audiences inside and outside of SRS, DOE, and governmental agencies, thereby maximizing the value of our taxpayer-supported work.

Content and organization of this document

This document focuses on the scientific and technical information (STI) reports, articles, and presentations generated at the site by various authors and organizations of Westinghouse Savannah River Company and its subcontractors. Abstracts of these STI products are contained within this document.

The abstracts have been compiled as they originally appeared in the source reports. No changes to the content have been made except as necessary to correct errors of spelling, to reduce abstract length, or to ensure that the information is unclassified.

The abstracts are organized according to information categories ("UC" categories) established by the Department of Energy's Office of Scientific and Technical Information (OSTI). When reports fall into more than one category, their abstract is included as an entry in the most applicable section of this document.

Each abstract entry contains, when available, the source reports's title, the author(s), the text of the abstract, the document number, and the organization code of the authoring organization. This information is included as originally submitted on the source report's record indexing form, document approval form, and report cover page.

In addition to a contents page organized by UC category, a subject index is included at the back of this document.

Updates, copies, and questions

This document will be updated twice annually by the Technical Information Management group. You can receive additional printed copies (or text files on computer disk) and you can be added to the distribution list for future updates by contacting Technical Information Management or Technical Publications in 703-43A. To obtain copies of the full reports referenced in each entry, contact the Document and Records Management group in 773-52A.

If you have questions about how this document was prepared, contact Technical Publications. Questions about the content of the abstracts (or their source reports) should be directed to the author(s) or the authoring organization.

Contents

UC-700 General, Miscellaneous, and Progress Reports	1
UC-701 Chemistry	3
UC-702 Environmental Sciences	7
UC-703 Geosciences	17
UC-704 Materials	19
UC-705 Mathematics and Computer Sciences	23
UC-706 Engineering, Equipment, and Instruments	29
UC-707 Health and Safety	47
UC-708 Biological Sciences	51
UC-711 Chemical Separation Processes for Plutonium and Uranium	53
UC-712 Inertial Confinement Fusion	55
UC-713 Radioisotope and Radiation Applications	57
UC-714 Criticality Studies	59
UC-715 Technology - Feed Materials	61
UC-721 Defense Waste Management	63
UC-722 Transportation of Nuclear Materials	75
UC-731 Nuclear Materials Production	77
UC-732 Special Isotope Separation (Plutonium)	79
UC-733 Nuclear Raw Materials	81
UC-741 Chemical High Explosives	83
UC-742 Applications of Explosions	85
UC-743 Nuclear Propulsion Systems	87
UC-744 Aerospace Nuclear Safety	89
Index	91

UC - 700

General, Miscellaneous, and Progress Reports

Fifty Years of Waste Siting Postponement

Author

Herbert Inhaber

Abstract

Fifty years ago when Enrico Fermi produced the first controlled nuclear chain reaction, he almost certainly realized he had created a material that could not be disposed of in ordinary ways. While records of radioactive waste disposal of the Curies, Becquerel, and others in the pre-Stagg Field era are scattered, it appears likely that most of the waste material they produced was handled as ordinary garbage. There do not seem to be specific sites devoted to pre-1942 nuclear waste. This year marks five decades of attempts to solve the nuclear waste siting problem. By some measures, the solution is no closer than it was many years ago. If an attempt to find a site had been made in the late 1940s and 1950s, it would have been greeted with much less public outcry than today.

Report Number

WSRC-MS-92-333

Authoring Organization

L1510

of work and requires the principal investigator (PI) to submit a task technical plan and a task quality assurance for the task. The universities do not have a QA manual or a common set of procedures for doing research. This situation causes each PI to develop a plan addressing the subcontract QA requirements and the associated supporting procedures. A need for a SCUREF QA manual addressing the details and procedures for the subcontract was identified by university researchers participating in SCUREF activities.

Report Number

WSRC-MS-92-327

Authoring Organization

L0130

QA In Research — Science or Fiction?

Author

Larry G. Harmon, Catherin M. Bens

Abstract

Westinghouse Savannah River Company (WSRC) has a cost sharing research agreement with South Carolina Universities Research and Education Foundation (SCUREF) to provide research and development opportunities for environmental restoration and waste management as well as technology transfer. Specific areas of R&D include: in-situ remediation, waste minimization, development of closure standards, waste site characterization, and ecological & health risk assessment. SCUREF universities are: Clemson University, Medical University of South Carolina, South Carolina State University, and University of South Carolina — Aiken and Columbia campuses. The WSRC/SCUREF agreement is a single WSRC subcontract that places work with SCUREF through individual Task Orders. Each task order has a specific scope

UC - 701

Chemistry

Chemistry Compatibility of FOME-ADD™ with Dilute Nitric and Oxalic Acids(U)

Author

S. B. Clark and P. A. Toole

Abstract

No indications of incompatibilities between FOME-ADD™ and dilute nitric acid (<10%) or oxalic acid were observed in small-scale laboratory tests using anticipated operating conditions. Therefore, recommendations for tests of the re-designed foam generating equipment include trials with dilute nitric or oxalic acids using manufacturer-suggested quantities of FOME-ADD™. To ensure that no incompatibilities between FOME-ADD™ and nitric or oxalic acids occurs on a larger scale, the temperature and physical appearance of the mixtures should be monitored and recorded in the unpressurized stainless steel mixing tank during testing.

Report Number

WSRC-RP-92-243

Authoring Organization

L3200

Estimated Steady-State Compositions of Supernatant Liquid During Sludge Washing (U)

Author

D. T. Hobbs

Abstract

Steady-state hydroxide, pH, carbonate and bicarbonate levels have been estimated for supernatant liquids during sludge washing and storage. These compositions were needed in order to prepare synthetic solutions for determining inhibitor requirements. The steady-state pH was plotted versus the nitrate concentration and fitted to a logarithmic expression of the form, $\text{pH} = 10.23 \times [\text{NO}_3^-]^{0.0178}$ where $[\text{NO}_3^-]$ is the concentration of nitrate in moles/liter. Similar expressions were also developed for calculating the concentrations of carbonate and bicarbonate as a function of the nitrate concentration.

Report Number

WSRC-RP-91-1138

Authoring Organization

L3200

Gross Alpha/Beta Determination by Liquid Scintillation Counting (U)

Author

J. D. Leyba

Abstract

Liquid scintillation counting (LSC) is used to assay liquid samples for both gross alpha and gross beta (including tritium) activity in order to declare these samples "clean". This method provides several advantages over traditional gross assay techniques including easy sample preparation, no sample self-absorption, short counting times, acceptable lower limits of detection (LLD's), and convenient sample disposal.

Report Number

WSRC-TR-92-79

Authoring Organization

L2200

Gadolinium as a Safety System for Reactors

Author

S.B. Wyrick

Abstract

Gadolinium (Gd) is a rare earth element used at the Savannah River Site as a supplemental safety system to inhibit neutron activity in reactor moderator water. Gd is a strong neutron absorber which, upon absorption of a neutron, produces the next heavier stable isotope of Gd. To inhibit neutron activity, Gd nitrate can be injected into the reactor which produces a concentration of Gd on the order of 150,000 parts per billion (ppb). The limit to which Gd can be tolerated in the reactor without adversely affecting performance is approximately 300 ppb. Routine analytical methods have a lower limit of detection (LLD) of about

100 ppb. The LLD of the ICP-MS method (taking into account a 1/40 dilution) is approximately 0.5 ppb and is useful in detecting potential leaks of Gd into the reactor.

Report Number

WSRC-MS-92-326

Authoring Organization

L2220

Pyrophoricity of Uranium (U)**Author**

H.B. Peacock

Abstract

Uranium metal is pyrophoric and is capable of self-ignition in air provided conditions are favorable. Based on the data in this report, spontaneous ignition of spherical particles larger than 1/16 inch in diameter would not be expected to occur in air at room temperature (25°C).

The rate at which the uranium surface oxidizes in air, balanced against the rate at which the heat of reaction is lost to the surroundings, determines whether spontaneous ignition can occur. Heat loss to the surrounding environment depends on the thermal conductivity of the uranium including the oxide coating, and on the temperature gradient.

The ignition temperature for uranium metal particles is a function of particle geometry, size, or specific surface area, heating rate, gas composition as well as the quantity and distribution of powder within a storage container. The most important variable, however, affecting the ignition temperature for single samples was found by Schnizlein and Bingle to be the specific surface area (surface area per gram) of the uranium particles.

The ignition temperatures calculated from ANL data for 1/16, 1/4, and 1/2 inch diameter spherical particles are 333, 375, and 399°C, respectively. The accuracy is believed to be about $\pm 10\%$, which is based on theoretical and experimental results.

Report Number

WSRC-TR-92-106

Authoring Organization

L8200

UC - 702

Environmental Sciences

**First Quarter 1992 Sanitary Landfill
Groundwater Monitoring Data (U)****Author**

C. Y. Thompson

Abstract

In reference to the Sanitary Landfill Operating Permit (DWP-087A), only analytical data would be submitted for this quarter. The data tables presented for this quarter are copies of draft analytical results and therefore do contain errors. These errors will be corrected when the finalized data is received from the laboratory.

Report Number

WSRC-TR-92-285

Authoring Organization

W4020

**F- and H- Area Sewage Sludge Application
Sites Groundwater Monitoring Report,
Fourth Quarter 1991 (U)****Author**

Environmental Resources

Abstract

During fourth quarter 1991, the four wells at the F-Area Sewage Sludge Application Site (FSS wells) and the three wells at the H-Area Sewage Sludge Application Site (HSS wells) were sampled and analyzed for pH, specific conductance, chloride, nitrate and nitrite as nitrogen, sodium, and total dissolved solids as required by South Carolina Department of Health and Environmental Control Construction Permit 12,076. None of these analytes were detected at levels above the primary drinking water standard (PDWS) or Savannah River Site (SRS) Flag 2 criteria during fourth quarter. The F-Area Sewage Sludge Application Site wells also were analyzed for a number of other constituents. Tritium and lead exceeded their PDWS in samples from three and one of the wells, respectively. Total organic halogens and manganese each exceeded SRS Flag 2 criteria at two wells. No constituents analyzed at the H-Area Sewage Sludge Application Site exceeded the PDWS or Flag 2 criteria in any of the three wells.

Report Number

WSRC-TR-92-57

Authoring Organization

W4020B

**K-Area and Par Pond Sewage Sludge
Application Sites Groundwater
Monitoring Report, Fourth Quarter 1991
(U)****Author**

Environmental Restoration

Abstract

Eleven sewage sludge application sites at the Savannah River Site (SRS) were originally the subject of a research program, begun in 1980, using domestic sewage sludge to reclaim borrow pits and to enhance forest productivity at SRS. As part of this research program, wastewater sludge was applied to the K-Area Sewage Sludge Application Site and Par Pond Sewage Sludge Application Site in 1981. These sites received a second and last application of sludge in 1988. The monitoring wells at the K-Area and Par Pond Sewage Sludge Application Sites are sampled quarterly as part of the SRS groundwater monitoring program and to comply with SCDHEC Construction Permit 13,173. During fourth quarter 1991, samples from three monitoring wells at the K-Area site and three monitoring wells at the Par Pond site were analyzed for specific conductance, pH, chlordane, chloride, nitrate as nitrogen, nitrite as nitrogen, sodium, and total dissolved solids. This report describes monitoring results that exceeded the U.S. Environmental Protection Agency primary drinking water standards (PDWS) and the SRS flagging criteria.

Report Number

WSRC-TR-92-58

Authoring Organization

W4020B

Porflow Modeling of Nitrate Release from a Saltstone Vault (U)

Author

A. D. Yu

Abstract

At the Savannah River Site (SRS), low-level decontaminated salt solution generated from the In-Tank Precipitation process will be solidified with cement/slag/flyash and disposed in concrete vaults at the Saltstone Disposal Facility. Among the hundreds of contaminants in the Saltstone, nitrate presents the greatest threat to the groundwater because of its high concentration (0.25 g/cc) in the saltstone and low drinking water limit (44 mg/L). The design criterion for SDF is a slow, controlled release over thousands of years which benefits from the low saltstone hydraulic conductivity (1.0×10^{-11} cm/sec) and low nitrate diffusivity (5.0×10^{-9} cm²/sec). The performance objective is to meet the EPA Drinking Water Standard of 10 mg/L of NaNO₃ as nitrogen, or 44 mg/L as NaNO₃, in the groundwater at the SDF boundary. This paper covers a modeling study of nitrate migration in the unsaturated zone for the Radiological Performance Assessment (PA) of SRS's Saltstone Disposal Facility. The PA addresses the performance requirements mandated by DOE Order 5820.2A.

Report Number

WSRC-MS-92-302

Authoring Organization

L3230

Structure of the Nocturnal Boundary Layer Over a Complex Terrain (U)

Author

M. J. Parker

Abstract

The structure of the nocturnal boundary layer (NBL) over a complex terrain is presented. Observations were made during the third night of Project STABLE (Weber and Kurzeja, 1991), whose main goal was to study turbulence and diffusion over the complex terrain of the Savannah River Site near Augusta, Georgia. The passage of a mesoscale phenomenon, defined as a microfront with an explana-

tion of the nomenclature used, and a composite structure of the NBL over a complex terrain are presented. The spatial extent of the microfront was at least 30-50 km, but forcing is not well understood. The microfront occurred without the presence of a synoptic scale cold front, under clear conditions, and with no discernable discontinuity in a microbarograph pressure trace. The structure of the NBL over the complex terrain at SRS differed from the expected homogeneous terrain NBL. A composite of the NBL exhibited dual low level wind maxima, dual inversions, and a persistent elevated turbulent layer. The persistent elevated turbulent layer, with a spatial extent of at least 30 km, was observed for the entire night. Internal gravity waves were observed in the stable layers above and below the persistent elevated turbulent layer. The persistent adiabatic layer may have resulted from shear instability which caused the internal gravity waves to break.

Report Number

WSRC-MS-92-325

Authoring Organization

L3720

Numerical Simulations of the Transport and Diffusion During the 1991 Winter Validation Study Along the Range in Colorado

Author

Jerome D. Fast and B. Lance O'Steen

Abstract

The main objective of this study was to compare the observed surface concentrations from a tracer released during one evening of the 1991 ASCOT field study with those predicted by the RAMS and LPDM models. The ability of RAMS to predict small-scale circulations influenced by terrain, such as drainage flows, has been examined to explain the transport and diffusion of the simulated plume.

Report Number

WSRC-MS-92-318

Authoring Organization

L3720

A Comparison of the WIND System Atmospheric Models and MATS Data

Author

Jerome D. Fast, Stephen Berman, and Robert P. Addis

Abstract

The objective of this study is to evaluate the performance of two of the WIND System Atmospheric Models, PUFF/PLUME and 2DPUF. The performance of the models is based on dispersion characteristics that are important in emergency response situations, such as plume direction, concentration, width, and arrival time.

Report Number

WSRC-MS-92-319

Authoring Organization

L3720

Closure Systems at the Savannah River Site: A Reflective Overview with Future Applications (U)

Author

S.R. McMullin

Abstract

The Savannah River Site (SRS) recently closed three hazardous waste sites. Each of these sites was covered with a closure cap to impede infiltration. Each closure cap was designed differently, offering a unique opportunity to compare design considerations and performance. Evaluations of the different designs offer lessons learned which will improve future closures. Specific areas discussed include: the consideration of all the cap elements into an integrated design; the inclusion of geosynthetics with clay to improve the permeability characteristics and provide redundancy; the integration of the drainage area and vegetative cover into one functional design element, minimizing hydrostatic head and desiccation.

Report Number

WSRC-MS-92-308

Authoring Organization

W4020

An Overview of Treatment and Characterization Technologies for Environmental Remediation at the SRS (U)

Author

D.L. Holt and B.T. Butcher

Abstract

The Environmental Restoration Department (ERD) at the Savannah River Site (SRS) has the responsibility to remediate waste sites and groundwater to standards as determined by federal and state authorities. This mission requires that certain programmatic interfaces within the ERD, Savannah River Technology Center (SRTC, formerly Savannah River Laboratory), the Department of Energy Headquarters (DOE-HQ) Office of Technology Development (OTD), and commercial contractors be utilized to ensure cost-effective remediation technologies are used. This paper provides a synopsis of a select cross-section of the treatment and characterization technologies currently being pursued by ERD. Environmental Restoration Technology (ERT) Department's future role in providing the necessary technologies for waste sites and groundwater remediation is also discussed.

Report Number

WSRC-RP-92-578

Authoring Organization

W4020

Tritium Uptake by Fish in a Small Stream (U)

Author

D.. Eaton and C.E. Murphy, Jr.

Abstract

The tritium concentration in the water from freeze drying and water from combustion of the organic fraction was measured in the tissue of fish (large-mouth bass), stream macrophytes, and streamside vegetation at five sampling locations in Four Mile Creek on the Savannah River Site (SRS). Four Mile Creek has elevated tritium concentration, largely from migration of water through the soil from adjacent seepage basins which received industrial waste water containing tritium. The stream water and the vegetation, through the food chain, are

thought to be two sources of tritium reaching the fish. Comparison of the tritium concentration of the organic fraction of fish flesh and of the sources of tritium, indicates that the fish flesh approaches a steady - state concentration between the concentration of the different sources. On average the concentration of tritium in the water of combustion from fish flesh is somewhat lower than the tritium concentration in the water from freeze-drying but greater than the concentration in the water of combustion of organic matter in the vegetation at the base of the food chain.

Report Number
WSRC-TR-92-193

Authoring Organization
L3610

Heavy Rainfall at the SRS in July, August, and October of 1990

Author
R.P. Addis and R. J. Kurzeja

Abstract
The Savannah River Site experienced very intense rainfalls on July 25, August 22, October 10-12, and October 22-23, 1990. The July 25 rainfall inundated the 700 area with 5.2 inches of rain during a three-hour period and flooded the basement of building 773-A. A statistical analysis indicates that this rainfall event has a recurrence interval of over 100 years. The August 22 rainfall totaled 4.97 inches during a three-hour period at the SRS Climatology Site (in the center of the SRS) and 7.39 inches for a 12-hour period. This rainfall exceeded the 100-year recurrence interval for three- and twelve-hour durations. The October 10-12 rainfalls occurred during the passage of two tropical storms, Klaus and Marco, within a 48-hour period. Although these storms were not as intense as the ones in July and August, they caused 48-hour rainfall amounts that exceeded the 100-year storm amounts at several locations. The October 22-23 rainfall was due to the passage of a cold front and caused rainfalls at the SRS of approximately 5 inches over a 12-hour period. This rainfall and that of October 10-12 resulted in the wettest month in SRS history. This report compares rainfall from these storms with previous storms and with 100-year rainfall estimates.

Report Number
WSRC-TR-92-136

Authoring Organization
L3720

Barometric Pumping of Burial Trench Soil Gases Into the Atmosphere at the 740-G Sanitary Landfill

Author
D.E. Wyatt

Abstract
Air under four groundsheets at the 740-G Landfill, which restricted dilution and mixing, was sampled and analyzed for the light hydrocarbons, C₁-C₄. Selected samples were analyzed for a number of volatile organic species. The results of this study confirm that during periods of decreasing barometric pressure, all components of the burial trenches migrate through the soil cover into the near surface atmosphere. It is suggested that these data be further studied to determine the amounts of these volatile species which are injected into the atmosphere by barometric pumping at this and other burial grounds both at SRS and in the public sector.

Report Number
WSRC-RP-92-877

Authoring Organization
W4030A

Soil and Gas Investigations at the Sanitary Landfill

Author
D.E. Wyatt

Abstract
A soil gas survey was performed at the 740-G Sanitary Landfill during December 1990. The survey monitored the presence and distribution of the C₁-C₄ hydrocarbons; the C₅-C₁₀ normal paraffins; the aromatic hydrocarbons, BTXE; selected chlorinated hydrocarbons; and mercury. Significant levels of several of these contaminants were found associ-

ated with the burial site. In the northern area of the landfill, methane concentrations ranged up to 63% of the soil gas and were consistently high on the western side of the access road. To the east of the access road in the northern and southern area high concentrations of methane were encountered but were not consistently high. Methane, the species found in highest concentration in the landfill, was generated in the landfill as the result of biological oxidation of cellulose and other organics to carbon dioxide followed by reduction of the carbon dioxide to methane. Distributions of other species are the result of burials in the landfill of solvents or other materials.

Report Number:
WSRC-RP-92-878

Authoring Organization:
W4030A

K-Area Acid/Caustic Basin Groundwater Monitoring Report - 1991 Annual (U)

Author

Environmental Restoration and C.Y. Thompson

Abstract

The monitoring wells at the K-Area/Caustic Basin are sampled quarterly as part of the Savannah River Site (SRS) Groundwater Monitoring Program to comply with South Carolina Hazardous Waste Management Regulations. During fourth quarter 1991, samples from seven monitoring wells at the K-Area Acid/Caustic Basin were analyzed for turbidity, pH, specific conductance, major ions, total organic halogens, total organic carbon, total dissolved solids, radionuclides, pesticides, herbicides, and other constituents. Monitoring results that exceeded the U.S. Environmental Protection Agency primary drinking water standards (PDWS) and the SRS flagging criteria and turbidity standards are the focus of this report. Wells KAC 6 and 7 at the K-Area Acid/Caustic Basin did not yield four well volumes prior to sampling; both KAC 6 and 7 produced 9 gallons prior to purging dry. The samples collected from these wells may not, therefore, be representative groundwater samples. No constituents exceeded the PDWS at the K-Area Acid/Caustic Basin during fourth quarter 1991. Iron exceeded the Flag 2 criterion in well KAC 7, with a value of 1,390 µg/L. Total organic halogens

exceeded the Flag 2 criterion in well KAC 7 with a value of 55 µg/L. Downgradient-to-sidegradient well KAC 7 contained elevated levels of total organic halogens as well as elevated iron when compared to upgradient wells. No priority pollutants (EPA, 1990) were detected above the PDWS or Flag 2 criteria in wells KAC 1 (upgradient) and KAC 3 (downgradient). During fourth quarter 1991, wells KAC 1, 3, and 4 had turbidity values of fewer than 5 NTU. No well exceeded the standard of 50 NTU. Water-table elevations at the K-Area Acid/Caustic Basin indicate that groundwater flow direction is toward the west to southwest; flow has been generally toward the west to southwest for at least 12 quarters. The screen in well KAC 4 is submerged, which may affect the accuracy of the potentiometric contour map and complicates the determination of the groundwater flow direction.

Report Number
WSRC-TR-92-61

Authoring Organization
W4020

P-Area Acid/Caustic Basin Groundwater Monitoring Report (U) - 1991 Annual

Author

Environmental Restoration, C.Y. Thompson

Abstract

During fourth quarter 1991, samples from the PAC monitoring wells at the P-Area Acid/Caustic Basin were analyzed for indicator parameters, turbidity, major ions, volatile organic compounds, radionuclides, and other constituents. Monitoring results that exceeded the U.S. Environmental Protection Agency primary drinking water standards (PDWS) and the Savannah River Site (SRS) flagging criteria and turbidity standards during the quarter, with summary results for the year, are presented in this report. No constituent exceeded the PDWS at the P-Area Acid/Caustic Basin during fourth quarter 1991. Iron exceeded the Flag 2 criterion in downgradient wells PAC 3 and 6 and in sidegradient-to-downgradient well PAC 2. Manganese exceeded the Flag 2 criterion in downgradient wells PAC 3, 5, and 6. Iron and manganese were not elevated in upgradient wells. No priority pollutant (EPA, 1990) exceeded the PDWS or Flag 2 criteria in wells

PAC 4 and PAC 5. None of the PAC wells exceeded the SRS turbidity standard. No constituents exceeded the PDWS in PAC wells at the P-Area Acid/Caustic Basin during the year.

Report Number
WSRC-RP-92-62

Authoring Organization
W4020B

F-Area Acid/Caustic Basin Groundwater Monitoring Report - 1991 Annual (U)

Author
Environmental Restoration, C.Y. Thompson

Abstract
During fourth quarter 1991, samples from the FAC monitoring wells at the F-Area Acid/Caustic Basin were analyzed for indicator parameters, turbidity, major ions, volatile organic compounds, radionuclides, and other constituents. Monitoring results that exceeded the U.S. Environmental Protection Agency primary drinking water standards (PDWS) and the Savannah River Site (SRS) flagging criteria and turbidity standards during the quarter, with summary results for the year, are presented in this report. During fourth quarter 1991, tetrachloroethylene, total radium, and trichloroethylene exceeded the PDWS in wells FAC 3 and 4. Gross alpha and manganese exceeded standards in well FAC 4, and total organic halogens exceeded the Flag 2 criterion in wells FAC 3, 5, and 6. No priority pollutants (EPA, 1990) exceeded the PDWS or Flag 2 criteria in wells FAC 5 and FAC 6. Only wells FAC 4 and 8 did not exceed the SRS turbidity standard. Constituents that exceeded the PDWS appeared exclusively in sidegradient-to-downgradient well FAC 3 or in sidegradient well FAC 4. Downgradient well FAC 6 contained elevated levels of total organic halogens; however, elevated levels of this constituent also appeared in sidegradient well FAC 5 and in sidegradient-to-upgradient well FAC 3. During 1991, gross alpha, tetrachloroethylene, total radium, or trichloroethylene exceeded the PDWS in at least one sample each quarter in wells FAC 3 and 4, but not in other FAC wells.

Report Number
WSRC-TR-92-59

Authoring Organization
W4020B

Mixed Waste Management Facility (MWMF) Groundwater Monitoring Report (U) - 1991 Annual

Author
Environmental Restoration, C.Y. Thompson

Abstract
During fourth quarter 1991, tritium, trichloroethylene, tetrachloroethylene, chloroethene (vinyl chloride), total radium, mercury, and lead exceeded the U.S. Environmental Protection Agency primary drinking water standards (PDWS) in groundwater samples from monitoring wells at the Mixed Waste Management Facility (MWMF) and adjacent facilities. Tritium and trichloroethylene were the most widespread contaminants; 55 (49%) wells exhibited elevated tritium activities, and 24 (21%) wells exhibited elevated trichloroethylene concentration. Levels of manganese, total organic halogens, nickel, iron, 1,1-dichloroethane, aluminum, nonvolatile beta, and trichlorofluoromethane that exceeded Flag 2 criteria were found in one or more wells beneath the MWMF. Manganese and total organic halogens were the primary contaminants. Downgradient wells in the three hydrostratigraphic units at the MWMF contained elevated levels of tritium, trichloroethylene, tetrachloroethylene, total radium, chloroethene (vinyl chloride), lead, mercury, manganese, total organic halogens, nickel, iron, 1,1-dichloroethane, aluminum, nonvolatile beta, or trichlorofluoromethane. Upgradient wells contained no elevated constituents except well BGO 1D, which contained elevated manganese. During 1991, groundwater samples from 81 (72%) of the monitoring wells at the MWMF and adjacent facilities contained elevated levels of the following contaminants: tritium, trichloroethylene, tetrachloroethylene, total radium, lead, chloroethene (vinyl chloride), 1,1-dichloroethylene, gross alpha, silver, benzene, endrin, nitrate, cadmium, carbon tetrachloride, mercury, or barium. The elevated constituents were found most frequently in Aquifer Zone IIB₂ (Water Table) and Aquifer Zone IIB₁ (Barnwell/McBean) wells. However, 12 Aquifer Unit IIA

(Congaree) wells contained elevated levels of tritium, trichloroethylene, tetrachloroethylene, total radium, lead, barium, gross alpha, nonvolatile beta, or mercury.

Report Number
WSRC-TR-92-56

Authoring Organization
W4020B

H-Area Acid/Caustic Basin Groundwater Monitoring Report - 1991 Annual (U)

Author
Environmental Restoration, C.Y. Thompson

Abstract
During fourth quarter 1991, samples from the HAC monitoring wells at the H-Area Acid/Caustic Basin were analyzed for indicator parameters, turbidity, major ions, volatile organic compounds, radionuclides, and other constituents. Monitoring results that exceeded the U.S. Environmental Protection Agency primary drinking water standards (PDWS) and the Savannah River Site (SRS) flagging criteria and turbidity standards during the quarter, with summary results for the year, are presented in this report. During fourth quarter 1991, tritium activities exceeded the PDWS in wells HAC 1, 2, 3, and 4. Iron and manganese exceeded Flag 2 criteria in well HAC 3, and specific conductance exceeded the Flag 2 criterion in well HAC 2. No priority pollutants (EPA, 1990) exceeded the PDWS or Flag 2 criteria in wells HAC 2 and 4. None of the HAC wells exceeded the SRS turbidity standard. Tritium activities were of similar magnitude in downgradient and upgradient wells. Iron, manganese, and specific conductance were elevated in at least one of the downgradient wells but not in the upgradient wells. During 1991, elevated tritium activities were found in all four HAC wells every quarter. Elevated total radium occurred in well HAC 2 during third quarter.

Report Number
WSRC-TR-92-60

Authoring Organization
W4020B

Laboratory Testing of Passive Chemical Fixation for In-Situ Remediation of Metals Contamination in the F and H Area Seepage Basins (U)

Author
S.B. Clark

Abstract
Experiments have been completed to predict the effect of changing geochemical conditions resulting from passive chemical fixation on the sorption of toxic metals (Pb, Cd, Cr, and Hg) and radionuclides (Tc-99 and Np-237) to F Area seepage basin sludge. Laboratory studies indicate that toxic metals and radionuclides are more highly sorbed to the seepage basin sludge under the alkaline, reducing conditions likely to result from the use of passive chemical fixation during closure. Under these conditions, the sludge/solution distribution coefficient, K_d , increases from 2 to 300 mL/g compared to K_d 's determined under toxic conditions in the higher oxidation state, anionic species (Cr and Tc) demonstrated the most significant increase in K_d , which is likely the result of reduction to lower oxidation states and the subsequent formation of cationic species. These results indicate that modeling of contaminant transport or determination of risk from these contaminants using previously reported distribution coefficients may not be representative of the actual system resulting from remediation of the area via passive chemical fixation.

Report Number
WSRC-RP-92-298

Authoring Organization
L2300

A Comparison of the WIND System Atmospheric Models and MATS Data (U)

Author
J. Fast, S. Berman, and R. Addis

Abstract
The results produced by two of the WIND System atmospheric models, PUFF/PLUME and 2DPUF, were compared with a select group of eight MATS experiments to determine the performance of the

Laboratory Testing of Passive Chemical Fixation for In-Situ Remediation of Metals Contamination in the F and H Area Seepage Basins (U)

Author

S.B. Clark

Abstract

Experiments have been completed to predict the effect of changing geochemical conditions resulting from passive chemical fixation on the sorption of toxic metals (Pb, Cd, Cr, and Hg) and radionuclides (Tc-99 and Np-237) to F Area seepage basin sludge. Laboratory studies indicate that toxic metals and radionuclides are more highly sorbed to the seepage basin sludge under the alkaline, reducing conditions likely to result from the use of passive chemical fixation during closure. Under these conditions, the sludge/solution distribution coefficient, K_d , increases from 2 to 300 mL/g compared to K_d 's determined under toxic conditions in the higher oxidation state, anionic species (Cr and Tc) demonstrated the most significant increase in K_d , which is likely the result of reduction to lower oxidation states and the subsequent formation of cationic species. These results indicate that modeling of contaminant transport or determination of risk from these contaminants using previously reported distribution coefficients may not be representative of the actual system resulting from remediation of the area via passive chemical fixation.

Report Number

WSRC-RP-92-298

Authoring Organization

L2300

A Comparison of the WIND System Atmospheric Models and MATS Data (U)

Author

J. Fast, S. Berman, and R. Addis

Abstract

The results produced by two of the WIND System atmospheric models, PUFF/PLUME and 2DPUF, were compared with a select group of eight MATS experiments to determine the performance of the models. Three of the MATS experiments employed

TRAC vehicle sampling and the remaining five used a line of fixed samplers. The performance of the models was based on certain dispersion characteristics that are important in emergency response situations. Both PUFF/PLUME and 2DPUF were executed with the same source term and meteorological data. When the numerical results from the models were compared to the observed values from the MATS experiments, it was found that 2DPUF produced concentrations and plume widths that were closer to the observed values than PUFF/PLUME. Both models did not produce any bias in the values of the concentration when individual data concentrations. 2DPUF did not exhibit any bias in the peak and total concentrations. When wind direction errors were removed, 80-84% of the concentrations from PUFF/PLUME and 88% of the concentrations from 2DPUF were within a factor of 10 of the observed values. In some instances, both models were able to predict concentration values that were comparable to a more complex, three-dimensional model called MATHEW-ADPIC. Considering all of the possible uncertainties associated with dispersion modeling, PUFF/PLUME and 2DPUF performed reasonably well. The differences between the dispersion forecasts made by PUFF/PLUME and 2DPUF and the observed surface tracer concentration are very similar to many other emergency response models based on the Gaussian assumption.

Report Number

WSRC-RP-91-1209

Authoring Organization

L3720

Evaluation of the WIND System Atmospheric Models: An Analytic Approach

Author

J.D. Fast

Abstract

An analytical approach was used in this study to test the logic, coding, and the theoretical limits of the WIND System atmospheric models. In this method, dose or concentration estimates predicted by the models were compared to the analytic solutions to evaluate their performance. The results

from AREA EVACUATION and PUFF.PLUME were very nearly identical to the analytic solutions they are based on, and the evaluation procedure demonstrated that these models were able to reproduce the theoretical characteristics of a puff or a plume. The dose or concentration predicted by PUFF/PLUME was always within 1% of the analytic solutions. Differences between the dose predicted by 2 DPUF and its analytic solution were substantially greater than those associated with PUFF/PLUME, but were usually smaller than 6%. This behavior was expected because PUFF/PLUME solves a form of the analytic solution of a single puff, and 2DPUF performs an integration over a period of time for several puffs to obtain the dose. Relatively large differences between the dose predicted by 2DPUF and its analytic solution were found to occur close to the source under stable atmospheric conditions. WIND System users should be aware of these situations in which the assumptions of the WIND System atmospheric models may be violated so that dose predictions can be interpreted correctly. The WIND System atmospheric models are similar to many other dispersion codes used by the EPA, NRC, and DOE. If the quality of the source term and meteorological data is high, relatively accurate and timely forecasts for emergency response situations can be made by the WIND System atmospheric models.

Report Number

WSRC-RP-91-1208

Authoring Organization

L3720

UC-703
Geosciences

UC-704

Materials

Safety Rod Latch Inspection (U)

Author

D. R. Leader

Abstract

During an attempt to raise control rods from the 100 K Reactor in December, one rod could not be withdrawn. Subsequent investigation revealed that a small "button" in the latch mechanism had broken off of the "lock plunger" and was wedged in a position that prevented rod withdrawal. Concern that this failure may have resulted from corrosion or some other metallurgical problem resulted in a request that Savannah River Technical Center examine six typical latch mechanisms from the 100 L Reactor by use of radiography and metallography. During the examination of the L-Area latches, a failed latch mechanism from the 100 K reactor was added to the investigation. Fourteen latches that had a history of problems were removed from K-Area and sent to SRL for inclusion in this study the week after the original seven assemblies were examined, bringing the total of latch assemblies discussed in this report to twenty one. Results of the examination of the K-Area latch that initiated this study are not included in this report.

Report Number

WSRC-TR-92-90

Authoring Organization

L8200

J-Integral of Circumferential Crack in Large-Diameter Pipes

Author

W. Gi, Y.J. Chao, M.A. Sutton, P.S. Lam, and G.E. Mertz

Abstract

Large-diameter, thin-walled pipes are encountered in low-pressure nuclear power piping systems. Fracture parameters, such as K and J , associated with postulated cracks are needed to assess the safety of the structure (e.g., prediction of the onset of the crack growth and the stability of the crack). The Electric Power Research Institute (EPRI) has completed a comprehensive study on cracks in pipes and handbook-type of data is available.

However, for some large-diameter, thin-walled pipes the needed information is not included in the handbook. This paper reports our study on the circumferential cracks in large-diameter, thin-walled pipes ($r/t=30$ to 40) under remote bending or tension loads. Elastic-plastic analysis using finite element method was performed to determine the elastic and fully plastic J values for various pipe/crack geometries. Ramberg-Osgood nonlinear material model is used. The strain hardening values range from 3 to 10. The half crack angles are from 0.06π to 0.5π . Results are tabulated for use with the EPRI estimate scheme. Verification of the results are provided through direct comparison with finite element analysis and elastic solutions.

Report Number

WSRC-MS-92-320

Authoring Organization

L8210

Rapid Quenching of Molten Lithium-Aluminum Jets in Water

Author

G. A. Greene, D. H. Cho, M. L. Hyder, D. K. Allison, and P. G. Ellison

Abstract

The Westinghouse Savannah River Company operates the "K" production reactor at the Savannah River Site in South Carolina. This is a heavy-water-moderated- and -cooled reactor designed for the efficient production of radioisotopes, including tritium. Operation is restricted to temperatures below the boiling point of the coolant at atmospheric pressure; this permits the fuel and many components to be fabricated from aluminum and its alloys. Control rods for the K reactor are grouped in assemblies of seven rods, called "septifoils". The control rods are fabricated of aluminum-lithium alloy, typically about 3 weight percent lithium, clad in a thin aluminum jacket. Safety analysis of potential problems in reactor operation identified a class of incidents in which problems might arise in the control rod cooling system, leading to inadequate cooling and coolant boiling inside a septifoil housing. The result would be voiding of a large part of the space inside the housing, and loss of cooling for part of the cooling

rods. Seepage of moderator through the bottom fitting should maintain some depth of water in the bottom of the housing. A particular concern identified was that overheated cooling rods might partially melt, so that the resulting molten metal could drain into the water at the bottom of the housing. If the resulting melt-water mixture underwent a vapor explosion, it might burst the thin septifoil housing and damage the nearby fuel assemblies. Literature data indicated that molten aluminum-lithium alloy could give energetic explosions under certain conditions. However, the experiments in the literature were artificially triggered; it was not clear that self-triggering of vapor explosions was likely under the conditions of interest. The experiments described here were undertaken to investigate this question, and to characterize any explosions that might occur.

Report Number

WSRC-MS-92-288

Authoring Organization

L1530

Al Corrosion in SRS Storage Basins**Author**

M.C. Thompson and T.S. Rudisill

Abstract

SRS has many years of experience with storage of aluminum-clad fuels and targets in two different types of storage basins: the reactor disassembly basins and the Receiving Basin for Offsite Fuels (RBOF). The basins have different water chemistry resulting in different rates of aluminum corrosion in the basins. Consequently, the length of time that Al-clad fuels or targets can be stored safely depends on the basin where the material is stored. On the basis of SRS experience, Al-clad fuels cannot be stored for more than 18 months in a reactor disassembly basin without leaking, but can be stored for at least 10 years in a basin such as RBOF. In one case, plutonium was leached from targets into reactor basin water, demonstrating that long term storage could lead to loss of fissile material control. Taiwanese Research Reactor (TRR) fuel is a special case in which the Taiwanese have experienced problems with corrosion of the fuel and have used dry storage to prevent contamination of their basin. TRR fuel is known to leak in less than

four years; therefore, TRR fuel should not be stored in any water basin for more than four years. All Al-clad fuels currently stored in the reactor basins should be removed and reprocessed or placed in dry storage as soon as possible.

Report Number

WSRC-TR-92-187

Authoring Organization

L2100

Permeation Rates for RTF Metal Hydride Vessels (U)**Author**

J.E. Klein

Abstract

This report estimates the rate of tritium permeation from RTF metal hydride vessels into the RTF NH&CS. The impact these permeation rates has on the tritium activity in the NH&CS are discussed. These data were requested for determining the set point of the NH&CS Karne chamber.

Report Number

WSRC-TR-92-258

Authoring Organization

L2610

Constant Extension Rate Tensile Tests on 304L Stainless Steel in Simulated Hazardous Low-Level Waste (U)**Author**

B.J. Wiersma

Abstract

New waste tanks that handle hazardous low-level waste are to be constructed in H Area. The candidate material for the tanks is AISI Type 304L (304L) stainless steel. Constant extension rate tensile (CERT) tests were conducted to assess the susceptibility of 304L to stress-corrosion cracking (SCC) in these waste solutions. The tests demonstrated that 304L was not susceptible to SCC in simulated wastes. Based on these tests and previous pitting corrosion studies, 304L is a suitable material of

construction for the new tanks. Comparison tests in the same simulants were performed on A537 carbon steel (A537), a material that is similar to material of construction for the current tanks. Stress-corrosion cracking was indicated in two of the simulants. If carbon steel tanks are used to handle the hazardous low-level wastes, inhibitors such as nitrite or hydroxide will be necessary to prevent corrosion.

Report Number
WSRC-TR-92-229

Authoring Organization
L8200

Helium Bubble Distributions in Reactor Tank Repair Specimens- Part I (U)

Author
M.H. Tosten and P.A. Kestin

Abstract
Transmission electron microscopy (TEM) was employed to characterize the microstructure and helium bubble distributions in Type 304 stainless steel used as substrate material for low heat input gas metal arc (GMA) weld overlays. Helium-free and helium-containing specimens were examined in both the welded and unwelded conditions. The bubble distributions in the helium-bearing plates were characterized according to bubble size, spacing, and location within the material. The results of this study showed that a well-developed helium bubble microstructure was present in the test specimens prior to GMA welding. Additionally, the temperature excursion and stresses experienced during (and after) welding did not significantly affect the pre-existing helium bubble distributions at distances 2.3 mm and greater below the weld fusion line.

Report Number
WSRC-TR-91-141

Authoring Organization
L8200

Analysis of Deposit from K-Reactor Heat Exchanger 4A

Author
E.W. Baumann

Abstract
Characterization of deposits from the reactor system provides a means of directly assessing corrosion and chemistry condition within the system. The recent analysis of debris vacuumed from the bottom of K-Reactor tank provided information and reassurance about the conditions within the tank that would affect corrosion or moderator chemistry. Further opportunity for surveillance within the reactor system was recognized when solid deposits were found on the moderator side of the K-Reactor heat exchanger 4A that failed in December 1991. A sample of deposited material from the face of the tube sheet at the inlet end was removed under the direction of equipment engineering section personnel. The material was analyzed by the analytical development section by techniques used earlier for the K-tank debris. Elemental content was determined by Scanning Electron Microscopy/Energy Dispersive Spectroscopy (SEM/EDS). Total chlorine content was determined by neutron activation analysis. Crystalline components were identified by x-ray diffraction, and radionuclidic content characterized by alpha pulse height analysis, beta counting, scintillation counting, and gamma spectroscopy. This document reports the results of these analyses.

Report Number
WSRC-TR-92-139

Authoring Organization
L2200

UC - 705

Mathematics and Computer Sciences

Software Usability Testing: Do Evaluator Intervention and Task Structure Make Any Difference?

Author

Joseph E. Held and David W. Biers

Abstract

The purpose of the present study was to evaluate the effect of evaluator intervention, task structure, and user experience on the user's subjective evaluation of software usability. The study employed a $2 \times 2 \times 2$ factorial between-subjects design with two levels of Evaluator Intervention (Intervention vs. Non-Intervention), two levels of Task Structure (Guided-Exploration [free-form] vs. Standard Laboratory), and two levels of User Experience (Novice, Experienced). The users were asked to learn to use and subjectively evaluate a restricted subset of 12 common word processing features over four hours of participation. Day 1 was a training day and Day 2 was a test day. The major finding was that the user's subjective impression of the software was affected by both user Experience and evaluator Intervention. For difficult-to-use word processing features, experienced users rated the features as more difficult to use under the intervention than non-intervention condition. For naive users, this difference was in the opposite direction but not significant. The same pattern of results was obtained for the subjective rating of ease of learning, overall evaluation of the software, and confidence in context of attribution theory. The effect of structure, although not as prevalent, interacted with user experience in the evaluation of screen features and system capabilities. The relative lack of task structure effects was attributed to the difficulty in implementing free-form learning and the number of problems encountered in use of the software under Guided Exploration which counteracted any of its benefits.

Report Number

WSRC-MS-92-309

Authoring Organization

L7100

Information Technology... The 90's Agenda at Westinghouse Savannah River

Author

R.L. Adams

Abstract

What is Westinghouse Savannah River Company? How does WSRC and the SRS information environment compare? What are the customer's key issues? What is the SRS gameplan? What are the key technologies? Is there synergy for Westinghouse?

Report Number

WSRC-MS-92-337

Authoring Organization

B2000

Data Acquisition System Time Measurement Capabilities Using Workbench™ Software (U)

Author

D.A. Coutts

Abstract

There is an increasing interest in the ability to measure transient behavior in the Heat Transfer Laboratory (HTL). To accomplish this, the timing system behavior for the Data Acquisition Systems (DAS) must be evaluated. This report discusses the evaluation of a DAS timing system using WorkBench™ software in a Macintosh II environment. It also describes a method that can be successfully used to calibrate the timing system associated with the DAS.

Report Number

WSRC-TR-92-210

Authoring Organization

L1200

GAM-HEAT - A Computer Code to Compute Heat Transfer in Complex Enclosures

Author

R.E. Cooper and J.R. Taylor

Abstract

The GAM-HEAT code was developed for heat transfer analyses associated with postulated Double-Ended Guillotine Break Loss-of-Coolant Accidents (DEGBLOCA) resulting in a drained reactor vessel. In these analyses the gamma radiation resulting from fission product decay constitutes the primary source of energy as a function of time. This energy is deposited into the various reactor components and is re-radiated as thermal energy. The code accounts for all radiant heat exchanges within and leaving the reactor enclosure. The SRS reactors constitute complex radiant exchange enclosures since there are many assemblies of various types within the primary enclosure and most of the assemblies themselves constitute enclosures. GAM-HEAT accounts for this complexity by processing externally generated view factors and connectivity matrices as discussed below, and also accounts for convective, conductive, and advective heat exchanges. The code is structured such that it is applicable for many situations involving heat exchange between surfaces within a radioactively passive medium

Report Number

WSRC-TR-91-372

Authoring Organization

L1200

GRISSET Certification Package

Author

J.J. Taylor and G.R. Cefus

Abstract

GRISSET 1.0, which was previously approved software, has been revised to take greater advantage of the J80 system. The primary change has allowed GRISSET to utilize a greater range of two-character alpha-numeric mnemonics. The availability of additional mnemonics will allow the code to manipulate a greater number of axial layers and unique control positions. To support the increased

flexibility the modifications have allowed, the user interface has also been updated. These code modifications have led to the creation of a new version of the GRISSET code. The new version is GRISSET 1-1. This document is the certification package for GRISSET 1-1.

Report Number

WSRC-TR-92-102

Authoring Organization

L1100

FRIMHX Verification and Validation Summary Report

Author

E.F. Trumble

Abstract

As part of the software quality assurance requirements, the reactor analyses codes used for the calculation of key reactor operating and safety parameters require formal verification and validation. The GRIMHX code is used in such applications. Previous documentation exists discussing the verification and validation of GRIMHX: this document summarizes the past efforts in this area and combines them with recent new analyses performed by WSRC and Westinghouse Hanford Company. As such, this document is the most up-to-date compilation of verification and validation information pertaining to the GRIMHX code. The new validation work emphasized two separate features. The first concerned validation of GRIMHX using GLASS produced cross sections for a variety of reactor operating conditions such as shutdown, critical, and at-power operation. The second feature explored was code validation independent of the GLASS code. Many of the code features such as mesh points, determination of convergence criteria, and core symmetry selections were explored. The new validation effort emphasized matching both the k-effective values and three-dimensional flux distributions against selected benchmark problems.

Report Number

WSRC-TR-91-358

Authoring Organization

L1100

Verification, Validation, and Benchmarking Report for AXLIB4: A Processor to Generate JOSHUA Records of Axial Power Shaper Versus Time (U)

Author

T.T. Le

Abstract

AXLIB4 is a transient one-dimensional diffusion theory calculation written to provide JOSHUA records of assembly axial power shapes versus time at start and end of subcycle while safety rods are falling during a scram. The WIGGLE program provides the diffusion theory calculation. AXLIB4 is not a stand-alone code and is connected to LLAP² through an EXECUTE statement and JOSHUA interface libraries. The input data are passed to AXLIB4 from a driver routine (LLAP) and from interface JOSHUA records linking the code to the driver routine database. This report concerns the verification and validation of AXLIB4. The verification was performed to determine if AXLIB4 was using the correct theory and that all the subroutines function as required. The validation was performed by comparing the results of the code with the analytical solutions of test problems. The first test problem is a heterogeneous calculation using a pre-accident power profile (includes end-fittings); this problem is designed to test the calculation of total and decay heat assembly powers input versus time, and the initial power shape calculation. The second test problem is a homogeneous problem designed to test the initial and transient power shape calculational ability. These two test problems and their analytical solutions are repeated from the Benchmarking Report for WIGGLE. Since the results of these two benchmark solutions were identical to the analytical solutions, it is the conclusion of this study that AXLIB4 was correctly implemented and is ready to submit to SCMS.

Report Number

WSRC-TR-91-430

Authoring Organization

L1100

Validation of GRIMHX Calculations of Safety Rod Worths, Rev. 1 (U)

Author

R.L. Webb and R.C. Okafor

Abstract

Reviews, both onsite and offsite, have identified several errors and/or inconsistencies in the MCNP calculations reported in the original version of this report. That has necessitated the re-execution of all of the MCNP and GRIMHX calculations. However, it must be mentioned that the conclusions of the original memorandum are still valid - that is, the GLASS/GILDA/GRIMHX methodology for calculating safety rod worths under different flux shapes has been validated by comparison against MCNP calculations. Two problem areas in the original calculations were identified. A problem related to the MCNP setup of the axial dimension was discovered, and RPG personnel detected inconsistencies in material temperatures used between the GLASS and MCNP calculations. The GLASS calculations assumed temperatures appropriate for full power (2400 MW) operations, though isotopic cross sections for those temperatures do not exist in the MCNP data library. All GLASS and MCNP calculations were re-execution with all temperatures set at 300K. A comparison of the latest GRIMHX and MCNP calculations shows better agreement than reported in the original study. A significant change though is that GRIMHX is no longer always conservative relative to MCNP. In the original comparisons, GRIMHX values for safety rod worths were always smaller (i.e., conservative) than the values computed by MCNP. Given the statistical nature of MCNP, one would expect the MCNP results to bracket those of GRIMHX; and that is exactly what is observed in the latest calculations. But there is an acceptable level of agreement between the two methodologies, and it is concluded that MCNP validates the GLASS/GILDA/GRIMHX calculations.

Report Number

WSRC-RP-89-1248

Authoring Organization

L1100

SHIELD Certification Package (U)

Author

C. Boman

Abstract

In response to a Department of Energy (DOE) request to verify that the tools used at the Savannah River Site to develop technical specifications for operations are valid, Westinghouse Savannah River Company committed to certify all computer codes used in critical calculations at the site. The certification procedures were prepared and reported. Certification as applied to existing computer codes includes the verification and validation process, placing the code in configuration control, establishing user qualification standards and training requirements. All software intended for use in critical calculations must be certified. This report is intended to fulfill the requirements for the certification of SHIELD, SHLDED, GEDIT, GENPRT, FIPROD, FPCALC, and PROCES modules of the SHIELD system built February 1992. These modules are used for burnup, cooling, separate, and edit calculations. This certification package only satisfies the certification requirements for the SHIELD, SHLDED, GEDIT, GENPRT, FIPROD, FPCALC, and PROCES modules of the SHIELD system. It is not certification of the complete SHIELD system. Complete certification will follow at a later date.

Report Number

WSRC-TR-92-078

Authoring Organization

L1100

A Standard Set of Test Problems for SHIELD (U)

Author

C. Boman

Abstract

A standard set of test problems has been assembled for the SHIELD code, in accordance with the verification and validation process. The test problems are designed to only test the SHIELD, SHLDED, GEDIT, GENPRT, FIPROD, FPCALC, and PROCES modules of the SHIELD system. Together with the modules source code, the test

problems have been secured in the Scientific Code Management System (SCMS) data sets on the IBM, under the J80 version of the JOSHUA data base system. The test problems are to be executed any time a change has been made to any of the above mentioned SHIELD modules, in order to ensure consistency in code results. For some coding changes, it may be necessary to only run a subset of the test problems; this decision is to be made by the computer proprietor. The input for the J80 test problem set is stored on the IBM in the STD data set. The JCL required to execute the test problems on the IBM 3090 under J80 is stored along with the output of the test problems in the Scientific Code Management System in the data set USCS.SCMS.T-EST. The purpose of this report is to establish the credibility of the test problem set developed, and to provide instructions to run the test problems.

Report Number

WSRC-TR-92-075

Authoring Organization

L1100

SHIELD Verification and Validation Action Matrix Summary (U)

Author

C. Boman

Abstract

WSRC-RP-90-26, *Certification Plan for Reactor Analysis Computer Codes (U)*, describes a series of action items to be completed for certification of reactor analysis computer codes used in technical specifications development and for other safety and production support calculations. Validation and verification are integral parts of the certification process. This document identifies the work performed and documentation generated to satisfy these action items for the SHIELD, SHLDED, GEDIT, GENPRT, FIPROD, FPCALC, and PROCES modules of the SHIELD system. It is not certification of the complete SHIELD system. Complete certification will follow at a later date. Each action item is discussed with the justification for its completion. Specific details of the work performed are not included in this document but can be found in the references. The validation and verification effort the SHIELD, SHLDED, GEDIT, GENPRT,

FIPROD, FPCALC, and PROCES modules of the SHIELD system computer code is completed.

Report Number
WSRC-TR-92-077

Authoring Organization
L1100

SHIELD Verification and Validation Report

Author
C. Boman

Abstract

This document outlines the verification and validation effort for the SHIELD, SHLDED, GEDIT, GENPRT, FIPROD, PFCALC, and PROCES modules of the SHIELD system code. Along with its predecessors, SHIELD has been in use at the Savannah River Site (SRS) for more than ten years. During this time the code has been extensively tested and a variety of validation documents have been issued. The primary function of this report is to specify the features and capabilities for which SHIELD is to be considered validated, and to reference the documents that establish the validation. In particular, *The SHIELD System User's Manual*, summarizes and quantifies most of the validation documents referenced herein. This verification and validation report only satisfies the requirements for the SHIELD, SHLDED, GEDIT, GENPRT, FIPROD, FPCALC, and PROCES modules of the SHIELD system. It is not a verification and validation of the complete SHIELD system. Complete verification and validation will follow at a later date. The modules being certified are SHIELD, SHLDED, GEDIT, GENPRT, FIPROD, FPCALC, and PROCES. These modules are a set of computational modules that provide an accurate calculation of:

1. Reactor irradiation or burnup
2. Isotopic inventory from spontaneous decay
3. Isotopic inventory changes from fuel cycle processes;
4. Editing.

The system is designed to be applicable to all parts of the nuclear fuel cycle.

Report Number
WSRC-TR-92-076

Authoring Organization
L1100

GRIMHX Benchmarking Report (U)

Author
E.F. Trumble

Abstract

A series of benchmark and validation problems for GLASS and GRIMHX were selected to supplement existing verification and validation efforts. The problems selected serve to better define the range of applicability of the two computer codes. These benchmarks, performed with controlled versions of the GLASS and GRIMHX codes on the Hanford VAX computers, were used to validate not only GRIMHX, but also the GLASS - GRIMHX combination. A series of problems looking at various operating and shutdown states of the reactor, considering changes in fuel and control elements, bulk moderator, and core temperatures were evaluated. Detailed description of the cases and a complete output for all the calculations are provided as a permanent part of the analysis records.

Report Number
WSRC-TR-91-359

Authoring Organization
L1100

UC - 706

Engineering, Equipment, and Instruments

Recommendation to Replace PVC Disposable Shoe Cover with Alternative Materials (U)

Author

A.E. Slaught and W.N. Rankin

Abstract

An alternative for disposable shoe covers currently fabricated from PVC (polyvinyl chloride) was investigated to minimize disposal costs. Plans are to incinerate these items for disposal. The exhaust from the incineration of PVC must be processed through a sodium hydroxide scrubber to remove the chlorides. A substantial cost savings (\$700K/yr) would be expected from replacing these supplies with similar items fabricated from a material that contains no chlorides. Out of the seventeen shoe covers evaluated, we recommend the Rich Industry's polyethylene shoe cover. These shoe covers are both incinerable and disposable. They have a relatively high coefficient of friction and puncture resistance. In addition a reduction of 200,000 gal/yr of CIF Blowdown would be realized. Plans are to continue to investigate non-PVC alternatives.

Report Number

WSRC-RP-91-878

Authoring Organization

L3200

Failure of Latch Mechanism for Motion Control of Safety Rods (U)

Author

W. Yau and D.R. Leader

Abstract

During safety rod tests in K Reactor prior to startup, one safety rod could not be lifted because the "button" broke off and became lodged in the mechanism. Examination of the failed latch assembly along with other assemblies from both K Area and L Area revealed several missing buttons as well as severely deformed "jaw hanger extensions". Based on our study of the latch mechanism, the modifications to the "safety rod extension", and the operating history of the machine, this report describes the causes of the observed dam-

age with experimental evidence and calculations to support the findings.

Report Number

WSRC-RP-92-112

Authoring Organization

L3100

Heat Exchanger Restart Evaluation (U)

Author

J.M. Morrison, C.W. Hirst, and T.F. Lentz

Abstract

On December 24, 1991, the K Reactor was in the shutdown mode with full AC process water flow and full cooling water flow. Safety rod testing was being performed as part of the power ascension testing program. The results of cooling water samples indicated tritium concentrations higher than allowable. Further sampling and testing confirmed a process water system to cooling water system leak in heat exchanger 4A (HX 4A). The heat exchanger was isolated and the plant shutdown. Heat exchanger 4A was removed from the plant and moved to C Area prior to performing examinations and diagnostic testing. This included locating and identifying the leaking tube or tubes, eddy current examination of the leaking tube and a number of adjacent tubes, visually inspecting the leaking tube from both the inside as well as the area surrounding the identified tube. The leaking tube was removed and examined metallurgically to determine the failure mechanism. In addition ten other tubes that either exhibited eddy current indications or would represent a baseline condition were removed from heat exchanger 4A for metallurgical examination. Additional analysis and review of heat exchanger leakage history was performed to determine if there are any patterns which can be used for predictive purposes. Compensatory actions have been taken to improve the sensitivity and response time to any future events of this type. The results of these actions are summarized.

Report Number

WSRC-TR-92-97, Rev. 1

Authoring Organization

T3110

Statistical Analysis of Test Data for APM Rod Issue (U)

Author

T.B. Edwards, S.P. Harris, and C.P. Reeve

Abstract

The uncertainty associated with the use of the K-Reactor axial power monitors (APMs) to measure roof-top-ratios is investigated in this report. Internal heating test data acquired under both DC-flow conditions and AC-flow conditions have been analyzed. These tests were conducted to simulate gamma heating at the lower power levels planned for reactor operation. The objective of this statistical analysis is to investigate the relationship between the observed and true roof-top-ratios (RTR) values and associated uncertainties at power levels within this lower operational range. Conditional on a given, known power level, a prediction interval for the true RTR value corresponding to a new, observed RTR is given. This is done for a range of power levels. Estimates of total system uncertainty are also determined by combining the analog-to-digital converter uncertainty with the results from the test data.

Report Number

WSRC-TR-92-259

Authoring Organization

L1100

Hydraulic Characteristics of the Type Q Septifoil (U)

Author

M.A. Shaddy, Jr.

Abstract

The current type J septifoil has been modified to ensure that the control rods are adequately cooled during drained tank operation in the ECS phase of a DEGB LOCA. The eleven rows of holes distributed axially along the housing of the type J septifoil have been removed, and all of the coolant flowing through the septifoil exits through slots and holes near the top of the septifoil housing. This configuration of slots and holes ensures that there will be adequate coolant flow along the entire length of the septifoil under low flow conditions of

a design basis LOCA. The modification of the slot and hole pattern in the septifoil housing distinguishes the type Q septifoil from the type J. This report documents design calculations that are used to predict the hydraulic behavior of the type Q septifoil. A model that predicts the hydraulic performance of an individual septifoil is herein presented. A model that predicts the hydraulic performance of the whole septifoil flow distribution system is also presented. This model is used to predict LOCA septifoil flows.

Report Number

WSRC-TR-91-612

Authoring Organization

L1200

Response of DWPF Thermal Flowmeters to Composition Change - Effect on O₂ Determination in Salt Process Cell (U)

Abstract

Thermal flowmeters have been installed in the Salt Process Cell to measure in-cell process flows. In conjunction with purge flow meters in the third level corridor, it was planned to use these meters to estimate the air inleakage and O₂ concentration in each vessel system. The attached report discusses the errors in determining *a priori* correction factors in a very complicated process requiring fairly precise knowledge of the vapor composition and the meter characteristics.

Report Number

WSRC-TR-92-0069

Authoring Organization

L3100

Bases for Pump Pit Requirements Calculations (U)**Author**

R.A. Jacobs

Abstract

A task team is preparing the process requirements for the interarea transfer pump pits. The team is developing requirements to prevent flammable mixtures from forming and requires values to use on the generation of various components such as benzene, hydrogen, and N_2O . The purpose of this report is to document values to be used and to provide sample calculations using these values. There are no recommendations contained in this document.

Report Number

WSRC-RP-92-0302

Authoring Organization

L3100

Re-Evaluating the 1962 Mark VI-B Dynamic Tests Regarding Reactivity Coefficients**Author**

Toby Burnett and N.T. Hightower, III

Abstract

The 1962 Mark VI-B rod tests have been re-evaluated. A significantly lower (more negative) coolant coefficient is now ascribed to that test, -1 pcm/Deg-C vs. the previously reported +2 pcm/Deg-C. The change from the previous value is because of revisions to delayed neutron constants and accounting for spatial effects. The new value is in reasonable agreement with the currently calculated value of -2 pcm/Deg-C, considering measurement and calculational uncertainties.

Therefore, we conclude that the current analytic models for physics and transient analysis methodology (GLASS, FRIMHX & TRIMHX, and MARY) are fully consistent with 1962 test observations, and that there is no basis for assigning a calculational bias or increasing uncertainty allowances.

Report Number

WSRC-TR-91-395

Authoring Organization

L1500

Topical Report on the Characterization of CWS and WRS Piping in 105-K Building**Author**

Nazie A. Sheikh and Phillip M. Garrett

Abstract

The purpose of this report was to document the piping configuration and flow rates of the Cooling Water and Water Removal System for conducting flooding analyses using LOPA conditions. Detailed information about the Cooling Water and Water Removal Systems was compiled and documented. The characterization of the Cooling Water System including piping configurations in the subject buildings and system flow rate capacities under forced flow and gravity flow conditions. Pumping capacities for the Water Removal System - 40' elevation sump pumps were evaluated and the piping configuration for other appropriate pumps were characterized. Some details of the recirculation building were documented.

Report Number

WSRC-TR-92-51

Authoring Organization

L1530

Reverse Osmosis Performance with Solutions Containing Tri-n-butyl Phosphate (U)**Author**

J.L. Siler

Abstract

Tests were conducted to determine whether the reverse osmosis (RO) units at the F/H Effluent Treatment Facility (ETF) could be made to process solutions containing tri-n-butyl phosphate (TBP). It was desired to test whether operation at a feed pH other than neutral would improve performance.

Test results indicate that little improvement in the water flux can be expected at other pH values. Flux losses approached 35-50% after nine cycles of processing feed containing TBP and insoluble metals. However, salt increased from 20 to 44-49 (at 90% water recovery) after processing TBP. Sodium rejection was measured to be >99.5% (DF=200) in several instances. The water flux was restored to pre-fouled levels by chemically cleaning the membrane with a pH=1.8 oxalic acid solution at 200 psi and 30°C. The flux losses observed could not be tolerated with the present ETF system. The possibility of higher feed salt content (perhaps 100,000 mg/L as compared to 1,500-2,000 mg/L nominal) would result in insufficient processing capability. Additional membranes and pumping capacity would be required. However, the increased salt rejection would be a benefit, in light of the poor DFs typically observed at the ETF. Pilot-scale RO testing in the ETF would enable a more realistic evaluation to be made of the DF benefits from addition of small quantities of TBP in the RO inlet. The potential gain in salt DF and elimination of the biofouling problem would reduce operation costs (due to reduced RO cleaning and downtime) and help offset the capital costs for additional membrane area.

Report Number
WSRC-RP-91-1058

Authoring Organization
L3200

A Comparison of Reverse Osmosis Membrane Cleaning Methods (U)

Author
J.L. Siler

Abstract
Testing was conducted at TNX to evaluate the reverse osmosis (RO) cleaning methods in use at the F/H Effluent Treatment Facility (ETF). The present ETF membrane cleaning protocol involves a low-pressure-no-permeation method using NaOH. This work has examined the effectiveness of the present ETF method, due to the lack of improvement following the cleanings sometimes observed. This study has evaluated both low pressure (15-20 psi with no permeation) and high pres-

sure (200 psi with permeation) cleaning methods with sequential cleanings using NaOH and Filmtec alkaline cleaner. The importance of the cleaning sequence with these two chemicals was also examined. The amount of flux which could be restored was found to be very dependent upon the sequence in which the cleaning steps were performed. The NaOH-then-Filmtec sequence returned the clean water flux to pre-fouled conditions or better and substantially improved the DFs; whereas, a Filmtec-then NaOH sequence restored only 90% of the pre-fouled flux values and only slightly improved the DFs. No significant differences were observed between cleaning operations at low or high pressure. Interim Waste Technology recommends that the ETF use a two-step cleaning process of NaOH followed by the Filmtec alkaline cleaner. This cleaning method should restore performance to pre-fouled conditions.

Report Number
WSRC-RP-92-56

Authoring Organization
L3200

Uniformity of Material in the SME and MFT (U)

Abstract
The DWPF will satisfy the product consistency specification in the Waste Acceptance Preliminary Specifications through control of the chemical composition of the glass product. This control will be achieved by ensuring that each batch of feed in the Slurry Mix Evaporator (SME) will produce glass that satisfies the specification. To this end, a sampling system (including equipment and administrative controls) has been designed that will provide representative samples of each process batch. An analytical system (including instruments, analytical methods, and laboratory procedures) has been developed that will provide accurate and reproducible determinations of the chemical compositions of each process batch. A Product Composition Control System (PCCS) has been developed that will combine the analytical data with other process information to determine whether each SME batch will produce glass which satisfies the specification. However, these systems will fail if the SME or the Melter Feed Tank (MFT)

does not provide a uniform process batch. The purpose of this report is to determine what degree of uniformity can be expected of material in the SME and MFT. These vessels were designed based on a design development process which had proven successful for similar hard-to-mix feeds in the past. This process resulted in a design of the SME and MFT agitation systems which was intended to provide highly uniform melter feed material. Based on the results of extensive tests in prototypic equipment, the SME and MFT designs have met this design goal.

- Under normal operating conditions (agitation of a 50 wt% solids melter feed slurry at 130 rpm), there is no discernible dependence of slurry composition on level within the vessel.
- Even at somewhat dilute conditions (40 wt% solids slurry), the chemical composition of process batches in the SME and MFT will vary by < 4 percent (on a relative basis).

Report Number
WSRC-TR-92-284

Authoring Organization
L3100

Supporting Analyses Reactor Components Response to the Gamma Heating Accident (U)

Author
J.K. Thomas

Abstract
Current accident analyses show that some reactor components would be subjected to high temperatures due to gamma heating after the core coolant level has dropped during the ECS phase of a hypothetical LOCA event. Based upon initial analyses, the components of concern were identified as the reactor tank, the Mark 60B blanket assemblies, the safety rod thimbles (guide tubes), and the safety rods. At the request of the Reactor Restart Division, the Materials Technology Section initiated a task to address the response of these components during the gamma heating accident. The main areas examined were structural integrity and materials compatibility. This report summarizes the supporting analyses performed for the task.

Report Number
WSRC-RP-92-303

Authoring Organization
L8200

Reactor Components Response to the Gamma Heating Accident (U)

Author
J.K. Thomas

Abstract
Some reactor components may be subjected to high temperatures due to gamma heating after the core coolant level has dropped during the ECS phase of a hypothetical LOCA event. Based upon initial analyses, the components of concern were identified as the reactor tank, the Mark 60B blanket assemblies, the safety rod thimbles (guide tubes), and the safety rods. The Materials Technology Section initiated a task to address the structural and materials response of these components under the conditions predicted for the gamma heating accident. This report summarizes the final results for the task. This report does not address the reactor safety implications. Therefore, the identification of temperatures or reactor powers at which these effects are predicted to take place should not be considered as recommended reactor power limits.

Report Number
WSRC-RP-92-304

Authoring Organization
L8200

Appendix SC-TMPS-GF of the Experiment Operating Specifications for the Savannah River One-fourth Scale, One-sixth Sector, Tank/Muff/Pump (TMP) Separate Effects Test (SET) Exp. Series

Author
T.J. Boucher and J.S. Bollinger

Abstract

This document is Appendix SC-TMPS-GF of the Experiment Operating Specification (EOS) for the first set of experiments in the Savannah River One-fourth Linear Scale, One-sixth Sector, Separate Effects Tests (SET) experiment series. It contains detailed information on experiment operation and facility configuration necessary to meet the series objectives stated in the main EOS body. The Savannah River One-fourth Linear Scale, One-sixth Sector, Tank-Muff-Pump (TMP) Separate Effects Tests (SET) experiment series will be conducted by the Idaho National Engineering Laboratory (INEL) to investigate Savannah River Site (SRS) production reactor tank. Muff, pump suction and pump hydraulic response phenomena for large break loss-of-coolant accident (LBLOCA) scenarios. The test series consists of experiments representing a range of hydraulic conditions and geometries which bound those anticipated for LBLOCAs in SRS reactors. Data from these experiments will be examined to identify important hydraulic phenomena with the objective of providing data for benchmarking code calculations. Information obtained from the SET series will also expand the SRS data base on reactor LBLOCA events. Due to inherent scaling distortions and facility limitations, the results of experiments in the SET series will not be precise replications of full-scale Savannah River Site production reactor (SRSPR) response. The experiments will, however, provide hydraulic behavior sufficiently representative of full-scale SRSPR behavior to preserve important hydraulic phenomena and satisfy test objectives.

Report Number

WSRC-TR-92-95

Authoring Organization

L1200

Experiment Operating Specifications for the Savannah River One-fourth Linear Scale, One-sixth Sector, Tank-Muff-Pump (TMP) Separate Effects Test (SET) Experiment Series**Abstract**

This test matrix has been constructed to address the specific needs of the RELAP5 modeling effort

at SRS. These needs were identified by performing benchmarking calculations to single and two-phase two-component air-water hydraulic data from the 1989 L Reactor tests. This benchmarking work revealed areas for improvement in the capability of RELAP5 to predict the onset of air ingestion and the amount of air ingested at the tank exit muff. The benchmarking work indicated that the two-phase interfacial drag models for the tank, tank exit muff, and pump suction piping are inappropriate. It was not practical to take detailed data in the L Reactor testing; data needed to improve the RELAP5 weaknesses cited above. The 1/4 SET facility was thus constructed to provide data needed to improve the air-water RELAP5 modeling capabilities. Two-phase two-component air water pump data is currently not available for the SRS Bingham process flow pumps. Transient pump behavior is important in modeling the trip of the AC pump motors in the simulated loss-of-coolant accident. Correctly modeling the system response to the AC motor trip requires an accurate simulation of the transient void distribution in the external piping and the two-phase transient performance of the Bingham pump from AC to DC motor driven operation. In putting together the matrix, we have adopted the philosophy that the more representative the 1/4 SET tests can be made to actual reactor conditions, the more useful the data will be in improving and validating RELAP5 models. The matrix is therefore very similar in some respects to the 1989 L Reactor test matrix.

Report Number

WSRC-TR-92-91

Authoring Organization

L1200

A Mobile Autonomous Robot for Radiological Surveys**Author**

A.M. Dudar, D.G. Wagner, and G.D. Teese

Abstract

The Robotics Development Group at the Savannah River Site is developing an autonomous robot (SIMON) to perform radiological surveys of potentially contaminated floors. The robot scans floors at a speed on one-inch/second and stops, sounds an

alarm, and flashes lights when contamination in a certain area is detected. The contamination of interest here is primarily alphas and beta-gamma. The contamination levels are low to moderate. The robot, a Cybermotion K2A base, is radio controlled, uses dead reckoning to determine vehicle position, and docks with a charging station to replenish its batteries and calibrate its position. It uses an ultrasonic ranging system for collision avoidance. In addition, two safety bumpers located in the front and the back of the robot will stop the robot's motion when they are depressed. Paths for the robot are preprogrammed and the robot's motion can be monitored on a remote screen which shows a graphical map of the environment.

Report Number
WSRC-MS-92-305

Authoring Organization
L8113

Continuous Tritium Effluent Water Monitor at the Savannah River Site

Author
K.J. Hofstetter and H.T. Wilson

Abstract
A continuous monitor for tritium in water has been installed in the secondary cooling water effluent from the K Reactor at the Savannah River Site (SRS). The monitor is designed to provide early detection of a small leak of the tritiated heavy water moderator and facilitate rapid isolation procedures. The tritium detector consists of an analysis cell containing 0.1-0.25-mm-diameter beads of plastic scintillator interposed between two photomultiplier tubes and standard fast-slow coincidence electronics. A small portion of the effluent stream is first filtered through a series of cartridge filters (0.2 μm final filter) and then chemically treated by ion exchange resin and activated charcoal before reaching the cell. Flow through the detector is $\approx 3 \text{ mL/min}$. The Tritium Effluent Water Monitor (TEWM) will alarm if the tritium in the outfall exceeds 1500 pCi/mL during a 10-minute counting interval. The installation and performance of the TEWM are discussed.

Report Number
WSRC-MS-92-163

Authoring Organization
L2411

Robotics Site Report

Author
F.M. Heckendorn

Abstract
Classic Robots and Teleoperators; Mobile Robots and Pipe Crawlers; Remote Video; Miscellaneous Developments; and DOE-OTD Robotics Programs

Report Number
WSRC-MS-92-317

Authoring Organization
L8113

Specialized Video Systems for Use in Waste Tanks (I)

Author
E.K. Anderson, C.W. Robinson, and F.M. Heckendorn

Abstract
The Robotics Development Group at the Savannah River Site is developing a remote video system for use in radioactive waste storage tanks at the Savannah River Site, as a portion of its site support role. Viewing of the tank interiors and their associated annular spaces is an extremely valuable tool in assessing their condition and controlling their operation. Several specialized video systems have been built that provide remote viewing and lighting, including remotely controlled tank entry and exit. Positioning all control components away from the facility prevents the potential for personnel exposure to radiation and contamination. The video systems include camera, zoom lens, camera aiming, and vertical deployment while entering through a 125-mm-(5")-diameter opening. A special attribute of the systems is they never get larger than the entry hole, during camera aiming, etc., and can always be retrieved. The latest systems are

easily deployable to a remote setup point and can extend down vertically 15 meters (50 ft). The systems are expected to be a valuable asset to tank operations.

Report Number
WSRC-MS-92-203

Authoring Organization
L8113

Confirmatory Inspections of 42-Inch Cooling Water System (CWS) Inlet Header - P and L Reactors (U)

Author
D.M. Barnes

Abstract
This report evaluates inservice inspection results which address a concern regarding the possible occurrence of single-phase (water) erosion corrosion in the Savannah River Site Cooling Water System carbon steel inlet headers for the heat exchangers. Thickness measurements taken at selected locations in P and L Reactor Cooling Water System inlet headers confirm the previous analyses conclusion that the Cooling Water System inlet header is not susceptible to gross wall thinning due to erosion corrosion. The results of these thickness measurements provide verification of previous analytical work which considered the parameters that influence erosion corrosion, compared to the Savannah River Site Cooling Water System operating conditions. Thus, the CWS inlet piping in the K Reactor is not susceptible to erosion corrosion. The data confirm the conclusion that wall thinning due to erosion corrosion is not occurring in the Cooling Water System inlet header piping and are provided as information relating the Near-Term Structural Integrity Assessment of the 42-inch Cooling Water System Inlet Headers. The K-Reactor inspection results will be equivalent to the inspection results for P and L Reactors due to the similarity in water chemistry, temperature, materials of construction, and hydrodynamic conditions.

Report Number
WSRC-TR-92-105

Authoring Organization
L8200

Decontamination Using Electropolishing (U)

Author
W.N. Rankin

Abstract
Electropolishing of equipment is being developed as a method to reduce decontamination solution waste. Electropolishing removes fixed contamination. In addition, it can be used to prepare a metal surface to minimize the sites where particles of contamination can become entrapped. Electropolished surfaces pick up only 10% of the contamination that an unpolished surface does. Electropolished surfaces are also much easier to decontaminate (95% less decontamination solution needed). Electropolishing can be done through immersion or in-situ (wand) techniques. SRTC is currently working with a vendor to develop a nitric acid-based electropolishing technique that will be compatible with site waste disposal and is consulting with Battelle Pacific Northwest Laboratories.

Report Number
WSRC-RP-92-107

Authoring Organization
L3200

Analysis of Debris Vacuumed from K-Reactor Tank

Author
E.W. Baumann

Abstract
During the ultrasonic (UT) inspection of K-Reactor tank in the spring of 1990, solid material (termed debris) was seen on the bottom of the tank. When the UT inspection was complete, a specially designed underwater vacuum cleaner was used to

collect the accumulation at 17 monitor pin positions. This material was sent to SRTC for characterization as an action item of the Reactor Corrosion Mitigation Committee. Acquisition of this debris provided an opportunity to obtain first-hand information about conditions within the tank that affect corrosion conditions or moderator chemistry. The purpose of this report is to describe the results of the analyses and the implications of what was found.

Report Number
WSRC-TR-92-027

Authoring Organization
L2200

Waste Tank Cooling Coil Leakage Calculations (U)

Author
L.O. Dworjany

Abstract

A high activity waste tank cooling coil supply line cracked on September 12, 1991, at the H-Area East pump house, draining the cooling water to the ground. This raised the possibility of draining high-activity waste to the ground by siphon action through the submerged cooling coils since some of the cooling water supply lines are located up to 40 ft below waste tank liquid level. The following documentation summarizes conclusions and provides details of flow calculation presented earlier during the incident investigation.

- No plausible reason for a simultaneous rupture of the supply line and the cooling coils inside the tank was identified. Both seismic stresses and water hammer produce relatively low stresses on the cooling coils. A hypothetical simultaneous rupture of the cooling coils inside the tank and the supply line below ground could result in 100 to 200 gpm waste discharge to the ground.
- Waste discharge from a possible cooling coil corrosion leak would be limited to 20 gal/12-hr shift under maximum possible siphon, based on operating procedures for cooling water make-up which call for coil isolation when a cooling water

loss of 40 gal/shift is identified. This level of discharge is within the existing envelope of accident consequences for Waste Tank Form SAR.

Report Number
WSRC-RP-91-1253

Authoring Organization
L3200

Analysis of the Gang Rod Withdrawal Transient at Subcritical and Low Power Conditions for the K-14.1 Mark 2

Author
D.N. Wayne, C.E. Morgan, Jr., et.al.

Abstract

During start-up, the 66 safety rods are fully withdrawn from the reactor prior to control rod movement. The control rods in a septifoil within a gang are then withdrawn sequentially to achieve criticality, increase reactor power, and control flux shape/power distribution. The gang rod withdrawal accident is postulated to occur when a single gang of full length control rods is withdrawn from the reactor in an uncontrolled manner and at a continuous maximum postulated speed of 135 veeder units/min during start-up. This accident can be initiated by a faulty pistol-grip switch, a control computer error, or a B-module malfunction. The removal of a neutron absorber as a gang of control rods is withdrawn adds positive reactivity, causing a reactor power increase. A safety analysis was performed for this transient to determine if this design basis event can be successfully mitigated by the reactor's engineered safety features for the K-14.1 Mark 22 Charge. The resulting reactivity excursion was analyzed with the MARY Version 3.02 computer code to predict the reactor's transient response. Three reactor signals, the Log N period monitors, the High Level Flux Monitors, and the Very High Temperature trip by the Safety Computers, were relied upon to actuate the insertion of the safety rod. In the event of safety rod failure, the automatic backup shutdown logic of the safety computers initiates a series of tests (i.e., the period snubbing current, Rise, Ramp, or Drop tests) to activate the supplementary safety system to inject a liquid neutron poison into the core to shut down the reactor.

Report Number

WSRC-TR-91-0653

Authoring Organization

L7100

Effect of Inoperable Thermocouples on the Non-LOCA Analyses (U)**Author**

S.B. Rabin, I.V. Paik

Abstract

In the existing correlation used to determine effluent temperature measurement uncertainty for the non-LOCA transient analyses, it was assumed that 40 of the 432 Mark-22 assemblies had only three working thermocouples. The latest analysis completed and discussed within this report uses a Monte Carlo technique of random thermocouple failures, thereby allowing more than one failure per assembly. It also allowed 12 thermocouples to randomly fail open during operation. These open failures will remain undetected during reactor operation and therefore add conservatism to the technical specification limit of 40 allowable inoperable thermocouples. The modes of failure will be discussed in more detail later in this document.

Report Number

WSRC-TR-92-109

Authoring Organization

L7100

A Summary Report of the Consequences of Large CWS Expansion Joint Failure (U)**Author**

W.L. Daugherty and R.F. Miller

Abstract

Finite element analysis has shown that a 360° break in the 36 inch Cooling Water System (CWS) expansion joint (EJ) bellows can lead to an opening width of 1.6 inch following a dynamic rupture, with the 190 pumps on. This result also includes a one inch as-installed bellows extension based on drawing dimensions. This would result in a leak

rate of 25,400 gpm through an opening area of 190 in², based on results provided by the Nuclear Engineering Section. The water removal capacity of the sump pumps is approximately 14,000 gpm. After the 190 pumps are turned off, the leak rate would be 9,500 gpm from an opening 1.3 inches wide. The calculated flow rate is considered conservative due to conservative assumptions such as: no fluid frictional losses, instantaneous rupture, and the potential stiffness contribution of equalizing rings that were not simulated. Recent measurements taken of the 42 inch EJ bellows revealed that it is extended almost two inches beyond its design length. This affects the opening area in the event of bellows rupture as bellows extension or compression directly adds to the opening width. In this case an opening width of 2.6 inches is predicted, which would lead to a flow rate of 47,500 gpm, much greater than the water removal system capacity. Even after the 190 pumps have been tripped, gravity will cause a flow of about 24,000 gpm until further operator action is taken. This analysis examines the effect of dynamic rupture, variation in material properties, lateral loading and the effect of bellows pre-extension on bellows structural response in the event of bellows rupture. The consequences of tie rod failure and a probabilistic assessment of leak rates are presented.

Report Number

WSRC-TR-92-286

Authoring Organization

L8200

Overview of 1985 L-Area AC Flow Tests**Author**

T.B. Edwards, D.A. Eghbali, E.P. Shine and M.L. Liebmann

Abstract

An extensive study of the data from the 1985 L-Area AC Flow Tests was recently completed. The purpose of that study was to provide corroborating technical information as to the quality, fitness for use, of these experimental data. This report provides highlights from that study: an overview of the tests and their data, a description of the instrumentation used, an explanation of the data qualification methods employed to review the

data, and the important conclusions reached from the study.

Report Number
WSRC-TR-92-134

Authoring Organization
L1100

Uninstrumented Assembly Airflow Testing in the Annular Flow Distribution Facility (U)

Author
A.L. Kielpinski

Abstract
Two-phase, air-water tests were performed in the Annular Flow Distribution (AFD) facility, located at Babcock and Wilcox, Alliance, Ohio. The tests formed a part of the experimental data used in analyzing the thermal-hydraulic consequences of the Emergency Cooling Phase of a large-break, Loss of Coolant Accident (ECS-LOCA). A set of assembly airflow tests was performed in the AFD facility, on a dummy Mark 22 assembly which had previously undergone similar testing in the A-Tank of SRL's Heat Transfer Laboratory. These tests were part of an investigation of apparent airflow differences between comparable testing at the AFD facility and the HTL. It had been hypothesized that the differences were due to the presence of instrumentation in the original AFD assembly. The new tests were performed although analysis showed the instrumentation effects to be negligible. In this report, the new, uninstrumented assembly data are compared both to the data from the instrumented AFD assembly and to the A-Tank data. The new data agree with previous AFD data and disagree with the A-Tank data. This refutes the hypothesis that the presence of the instrumentation caused differences in airflow.

Report Number
WSRC-TR-92-29

Authoring Organization
L1200

Four-Foot Septifoil Cooling Experiment Unrestricted Inlet/Outlet Case

Author
D.J. Foti, H.W. Randolph, G.T. Geiger, D.T. Verebelyi and L.A. Wooten

Abstract
An experimental apparatus was designed and assembled incorporating five simulated control rods four feet long, joule-heated inside a five-foot length of a type "Q" septifoil. The septifoil segment had normal top and bottom fittings. The septifoil was positioned inside a steel tank which simulated the reactor vessel. Water in the tank was circulated through a heat exchanger which was used to maintain tank temperature at 70°C. The apparatus was arranged to allow the septifoil to draw water in from both the bottom and top inlets. External restrictions were minimized by the design. Electrical power of 10 Kw to 67 Kw was fed to the simulated rods from a DC power supply. Computer data acquisition was accomplished using "LabView" software programmed to match the configuration of the experiment along with scanning digital voltmeters and requisite signal sensors. Two video camcorders were used to provide video records of the experiment. All data acquisition sensors and data logging were done with M&TE Category 1 requirements.

Report Number
WSRC-TR-92-45

Authoring Organization
L7100

Method for Keeping RBOF Waste within EPA pH Limits for Nonhazardous Waste (U)

Abstract
Solutions with a pH of > 12.5 are considered RCRA hazardous waste (characteristic corrosive). The Receiving Basin for Offsite Fuel (RBOF) currently adjusts its waste to a pH > 12.5 to inhibit corrosion of the waste tanks. As of May 8, 1992, this waste will be banned from land disposal (third-third) and will exceed waste management acceptance criteria. RBOF proposed, as a solution to this prob-

lem, to buffer the waste with a carbonate/bicarbonate buffer to a pH > 10, then use nitrite as the corrosion inhibitor. A pH of ≥ 10 is necessary for corrosion inhibition at a NO₂ concentration of 0.86 M. RBOF proposed to monitor the pH with a pH meter, backed up by Alizarin Yellow indicator. A worst-case scenario in which the caustic feed blocked and only acid was released into the tank was used to determine the amount of buffer salts needed.

Report Number
WSRC-RP-92-340

Authoring Organization
L2100

Comparison of Burnout Risk (BOR) and Flow Instability Limits for Non-LOCA Application

Author
I.K. Paik and S.B. Rabin

Abstract
The purpose of this study is to compare the critical heat flux ratio to the saturation temperature ratio and the onset of significant void ratio from which the flow instability limits are based. Also it is to show that for the non-LOCA design basis events, which are analyzed for Chapter 15 of the updated K-Reactor SAR, the possibility of local burnout is negligible if the FI limit is met. Furthermore, no explicit BOR design limit need be established for non-LOCA safety analyses. Therefore, there is no need to explicitly evaluate BOR for non-LOCA analyses.

Report Number
WSRC-TR-92-291

Authoring Organization
L1500

Foam Application of Oxalic Acid as a Decontamination Waste Minimization Tool (U)

Author
K.D. Peterson

Abstract
The use of foam in applying decontamination solutions has proven to be an effective waste minimization strategy. Initial trials in 299-H indicated a 70% reduction in waste volume. An overpressurization of the equipment during a decon operation, however, indicated the need to better define chemical compatibility and to develop inherently safer equipment. A foamer system with an open solution vessel and 1:1 ratio pneumatically actuated pump was modified, tested, and found to operate satisfactorily. Laboratory tests indicate no significant incompatibilities between the foam agent and oxalic or dilute nitric acid solutions. Oxalic acid/foam agent compatibility was verified in the foamer vessel for concentrations up to four weight percent. It is recommended, however, that one weight percent oxalic acid be used in plant decon operations. The defoamer used previously is no longer in production. A new defoamer remains to be tested. Limited use of the foamer in 299-H can now be initiated. Long term use of foam and its impact on waste tank processes is being reviewed.

Report Number
WSRC-RP-92-361

Authoring Organization
L3200

Coolability of a Control Rod which has Melted and Foamed in Septifoil Outer Housing

Author

D.A. Walkowiak

Abstract

During a Loss of Control Rod Cooling (LCRC) event, the control rods which are in the affected septifoil can be postulated to melt. Melting of a control rod which has been irradiated creates a special concern since the entrapped gases expand rapidly and cause the melt to manifest itself initially in a foamed state. The foamed material then contacts the septifoil outer housing and the inner septifoil web material, where heat is conducted out of the foamed material. A second concern relating to the foamed melt is that its thermal conductivity is greatly reduced from that of the solid material, and also that of the non-foamed liquid. The purpose of this report is to address how, even in the presence of decreased thermal conductivity, the foamed melt may aid in cooling the control rod material.

Report Number

WSRC-TR-91-545

Authoring Organization

L1500

Materials and Mechanical Design Analysis of Boron Carbide Reactor Safety Rods - Final Report

Author

James C. Marra

Abstract

The purpose of this task was to analyze the materials and mechanical design bases for the new boron carbide safety rod. These analyses included examination of the irradiation response of the materials, chemical compatibility of component materials, moisture considerations for the boron carbide pellets and susceptibility of the rod to corrosion under reactor environmental conditions. A number of issues concerning the mechanical behavior were also addressed. These included: safety rod

dynamic response in scram scenarios, flexibility and mishandling behavior, and response to thermal excursions associated with gamma heating. A surveillance program aimed at evaluating the integrity of the safety rods following actual operating conditions and justifying life extension for the rods was also proposed. Based on the experimental testing and analyses associated with this task, it is concluded that the boron carbide safety rod design meets the materials and mechanical criteria for successful operational performance.

Report Number

WSRC-TR-92-173

Authoring Organization

L8200

Savannah River Reactor Process Water Heat Exchanger Tube Structural Integrity Margin (U)

Author

G.E. Mertz, D.M. Barnes, and R.L. Sindelar

Abstract

Twelve process water heat exchangers are designed to remove heat generated in the reactor tank. Each heat exchanger has approximately 9000, 1/2" diameter x 0.049" thick tubes. Minimum structural tubing requirements and the leak rate through postulated tubing defects are developed in this report. A comparison of the structural requirements and the defect size calculated to produce leak rates of 0.5 lbs/day demonstrate adequate structural margins against gross tube rupture.

Report Number

WSRC-TR-92-72

Authoring Organization

L8200

Analysis of K-Area Core Samples for K-Area Formation Stabilization Work (U)

Author

C.A. Langston

Abstract

Foundation stabilization work in K-Area has been recently completed by Bechtel, Inc. This effort involved pumping cement and cement-sand grout into unconsolidated sediments under K-Area. Subsequent to stabilization, core samples were collected to document the extent of grout flow in the area. Samples of this core were examined by SRTC personnel in support of the grouting program at the request of Bechtel personnel. This report summarizes the results of the SRTC study.

Report Number

WSRC-RP-92-756

Authoring Organization

L3200

Compliance Review for the UNH Storage Tank (U)

Author

J.M. Low

Abstract

The purpose of Project S-04257, USF-UNH 150,000 Gallon Storage Tank, is to provide interim storage for the liquid uranyl nitrate (UNH) product from H-Canyon until the UNH can be processed in the new Uranium Solidification Facility (Project S-2052). NPSR was requested by Project Management and DOE-SR to perform a design compliance review for the UNH Storage Tank to support the Operational Readiness Review (ORR) and the Operational Readiness Evaluation (ORE), respectively. The project was reviewed against the design criteria contained in the DOE Order 6430.1A, General Design Criteria. This report documents the results of the compliance review.

Report Number

WSRC-TR-92-251

Authoring Organization

L7200

Modifications to K-Reactor Power Limits for Open Monitor Pin Thermocouple Failures

Abstract

This report gives the correction to the power limits for up to two open mode thermocouple failures in an assembly. The impact of the failed thermocouples on the trip setpoints used in the accident analyses were not addressed. Modifications to trip setpoints should be done separately for each accident.

Report Number

WSRC-TR-92-80

Authoring Organization

L1200

Supplementary Safety System Topical Report

Author

R.L. Garrett, I.K. Paik and L.A. Wooten

Abstract

This report is a collection of the documentation for the Supplementary Safety System (SSS) utilized in the development of the K-Reactor safety analysis. This report will examine the available empirical data, experimental and analytical studies applied to develop and justify the current system safety analysis for the K-14.1 reactor charge. In addition to this overview, the applicable restart issues and related startup tests will be presented with results of each appropriate issue also detailed.

Report Number

WSRC-TR-92-125

Authoring Organization

L1530

Fault Tree Analysis of Project 5-4404, Upgrade Canyon Exhaust System

Author

E.V. Brown, C.R. Lux, and J.M. Low

Abstract

Fault tree analysis was used to determine and compare the failure rates (frequency) of the existing F & H Area exhaust systems with the proposed exhaust system and specific proposed exhaust system alternatives. The failure rate for each existing canyon exhaust system is about 2.7×10^{-6} per hour, or once every 42 years. The dominant failure mode for this scenario is failure of the stack liner at a 0.04 g earthquake and pluggage of the exhaust system. The failure rate for each proposed canyon exhaust system is 2.7×10^{-8} per hour, or once every 4200 years. The dominant failure mode in this scenario is failure of both normal and emergency power.

Report Number

WSRC-TR-92-306

Authoring Organization

L7200

Static Pipe Rupture Analysis of Specific Cooling Water Inlet Headers in K and L Reactors

Author

NA

Abstract

Subtask 6 of Task 91-002-1, "Near-Term Structural Integrity Assessment of CWS Inlet Headers", is concerned with the occurrence of a double ended guillotine break (DEGB) in the inlet headers. The purpose of this Subtask is to study the behavior of Cooling Water System (CWS) inlet header piping under the action of postulated pipe rupture forces and to determine if the displacements of the two ends of the pipe would result in a DEGB with full double-ended flow area. This report presents the results of a pipe break analysis for the CWS inlet headers, including the connecting supply lines. Four break locations were selected for analysis for each of the two headers. The present analysis is intended to predict the inlet header separation in the unlikely event that a postulated break were to

occur. For the postulated conditions, the stresses in the CWS inlet headers, connecting 24" supply lines and supports are not the focus of the present analysis and therefore, have not been evaluated. The dimensions and parameters used for the computer models were based on the models developed by Seismic Engineering employing as-built configurations. The computer code, AUTOPIPE, was used to perform the pipe-break analysis. The maximum hydraulic forces were calculated conservatively and were applied to the severed ends of the header as a static load. The analysis and evaluation show that the K Reactor inlet headers pipe motion due to certain postulated breaks will result in separation equivalent to a 70% of full double-ended flow area. Since the K and L Reactors are essentially identical, the results for the K-Reactor inlet headers are applicable to the L-Reactor inlet headers.

Report Number

WSRC-TR-91-608

Authoring Organization

L8200

Emergency Cooling Water System Roll Anchor Modification Analysis (U) Task Number 91-056-1

Author

N.K. Gupta

Abstract

The roll anchors prevent excessive uplift of the reactor plenum during Loss-of-Pumping-Accident (LOPA). Failure of roll anchors could impair the structural integrity of the process water system (PWS) piping which is the source of cooling water to the reactor during LOPA. These structural components are designed for a loading of 100,000 lbs (100 kips) each, which corresponds to a reactor tank pressure under the top shield of approximately 21 psig. However, recent hydraulic calculations by SRL show that with five ECS sources (headers; and ECS A, ECS B, and booster pumps) on line, ECS valves closed, and reactor building flooded to elevation 0'-0", the maximum pressures in the reactor tank could reach 30 psig. Such a high reactor tank pressure could result in overloading roll anchors well above their design loading of 100 kips each. Therefore, a reanalysis of the existing

roll anchor designs was carried out to calculate the structural capacity of these structural components. The analysis shows that the existing roll anchors will be able to withstand a plenum uplift force corresponding to reactor tank pressure under the top shield of approximately 23.1 psig. As a result, efforts were made to reduce the tank pressure by changing the ECS valves alignment. It is found that with valves open, the reactor tank pressure under the top shield drops to 20.58 psig, which is well below the 23.1 psio limit for ensuring the structural integrity of the roll anchors. The maximum pressure of 20.58 psig includes consideration of various uncertainties in the TRAC computer code model. The roll anchor reanalysis in this report is based on the acceptance criteria given in Seismic Engineering Procedure 24. It is found that each roll anchor design is capable of withstanding an uplift load of 118 kips. At this loading, the weak elements are the roller axles which will fail in shear.

Report Number

WSRC-TR-91-454

Authoring Organization

L8200

Results of the Air Inleakage Test Demonstrated at the PHEF for the Salt Process Cell (U)**Author**

H.B. Shah and R.A. Jacobs

Abstract

Air leaks into the salt processing cells (SPC) vessels because they are maintained at a slight negative pressure with respect to the cell. The Process Operating Procedure (POP) #27-355-506 was written at DWPF to measure air inleakage of the PRFT, PR, OE, and OECT. DWPF requested SRTC to demonstrate the Air Inleakage Test at the PHEF. The purpose of implementing the test at the PHEF was:

- determine if the existing DWPF Process Operating Procedure (POP) algorithm provides a reliable tool to conduct the test

- if the existing method proves to be inadequate, to develop a new method to conduct the test.

The existing POP did not perform satisfactorily during PHEF demonstrations. Although its failure was in part due to the small molecular difference between air and the PHEF inertant (nitrogen), the POP is not expected to be adequate even with CO₂ as the inertant. Two tests were conducted at the PHEF using a new method with promising results. The method and test results are summarized in this report.

Report Number

WSRC-RP-92-351

Authoring Organization

L3100

UC-707
Health and Safety

Releases from the Cooling Water System in the Waste Tank Farm (U)

Author

W.C. Perkins and C.R. Lux

Abstract

Recently, a cooling-water header broke in the H-Area Waste Tank farm, releasing contaminated water down a storm sewer that drains to the creek. A copy of the Occurrence Report is attached. As part of the follow-up on this incident, the NSPR Section was asked by Waste Management Technology to perform a probabilistic analysis of the following cases:

- A large break in the header combined with a large break in a cooling coil inside a waste tank
- Large break in the header combined with a leak in a cooling coil inside a waste tank
- A large break in the header combined with a very small leak in a cooling coil inside a waste tank

This report documents the results of the analysis of these cases.

Report No.

WSRC-TR-91-562

Authoring Organization

L7200

Safety Analysis for Seismic Motion of Control Rods Accounting for Rod Misalignment

Author

W.L. Osmin and Ingle K Paik

Abstract

The purpose of this report is to provide a summary of the results of three safety analyses performed by the SRL Safety Analysis Group (SAG) to assess the safety impact of control rod motion induced by a Design Basis Earthquake (DBE). RIMP Issue 505 addressed concerns related to the response of the control rod drive system during a seismic event. A potentially significant effect was the vertical motion (lifting) induced in the rods by the side-

sway (bowing or whipping) of the rod support system (rack extensions and guide plates). This effect was analyzed by the SRS Seismic Engineering Group to determine the maximum vertical displacement caused by a Design Basis Earthquake with a 0.2 g ground acceleration. Seismic Engineering analyses were performed to predict (a) the maximum vertical upward displacement of the control rods during a DBE and (b) the expected time history of the associated oscillations.

Report No.

WSRC-TR-91-662

Authoring Organization

L7100

Analysis of the Reactivity Effects for the Loss-of-Control Rod Cooling Transient

Author

Hightower, Morgan, and Easterling

Abstract

During fueling activities, control septifoils are occasionally replaced or otherwise removed. Past operating history of the Savannah River Site production reactors indicates that the septifoils may be improperly installed upon replacement, resulting in an unseated septifoil. Three methods are used to assure that septifoils are installed properly in the reactor:

- Pressure check of the up-flow pin
- Helium bubble 'glove test'
- Inspection of the bottom of the septifoils with a video camera

Despite administrative controls and post-installation testing, there exists a possibility that the reactor can attain operating power levels with an unseated septifoil. In the unseated condition, forced convection cooling to the septifoil is lost and only natural convection flow due to the buoyancy effects of the heated coolant is present. However, a bounding calculation based on the maximum reactivity increase resulting from a loss of forced control rod cooling was performed in order to establish the allowable power levels for the K-reactor.

Report No.

WSRC-TR-91-618

Authoring Organization

L1500

A Graded Approach to Safety Documentation at Processing Facilities**Author**

M.L. Cowen

Abstract

Westinghouse Savannah River Company (WSRC) has over 40 major Safety Analysis Reports (SARs) in preparation for non-reactor facilities. These facilities include nuclear material production facilities, waste management facilities, support laboratories and environmental remediation facilities. The SARs for these various projects encompass hazard levels from high to low, and mission times from startup, through operation, to shutdown. All of these efforts are competing for scarce resources, and therefore some mechanism is required for balancing the documentation requirements. Three of the key variables useful for the decision making process are depth of safety analysis, urgency of safety analysis, and resource availability.

Report No.

WSRC-MS-92-286

Authoring Organization

L2710

Analysis of Production Reactor Response During a Postulated Loss-of-River Water Event Using CONTAIN/SR (U)**Author**

Kevin O'Kula

Abstract

The CONTAIN/SR computer code, developed at the Savannah River Technology Center and Sandia National Laboratories for Probabilistic Safety Assessment (PSA) applications, is used to analyze K-Reactor plant conditions following a design

basis earthquake to assist post-accident recovery planning. The postulated event, a Loss-of-River Water (LORW) accident, requires analysis of the K-Reactor confinement system assuming seismic event-caused loss of forced air flow through radiologically controlled (RCAs) and other building areas, including adjoining personnel and auxiliary equipment zones. The CONTAIN/SR code calculations predict the expected environment in the K-Reactor building with a seismically qualified flow path for natural circulation, under design basis conditions specifying a 50 gal/min leak of tritiated heavy water. Despite loss of active fan flow, preferential air flow patterns are calculated to flow from "clean" areas towards the RCAs. Ventilation characteristics of the building reduce tritiated water vapor concentrations to habitable levels, assuming plastic suits and clean breathing air supplies are available. Unprotected dose rates to recovery workers in the heat exchanger zone of the building will range from 120 mrem/hour to 780 mrem/hour, depending on evaporation conditions near spilled heavy-water pools. It is concluded habitability issues for recovery are not driven by temperature concerns in reactor building zones. However, the results indicate radiological suits with cool air supplies will assure adequate conditions for operators and recovery teams, and mitigate tritium uptake hazards from splashing or other direct contact mechanisms.

Report No.

WSRC-MS-92-026

Authoring Organization

L1510

A Multi-Disciplinary Assessment of Operation Action Time for Mitigating a Postulated Accident**Author**

J.A. Buczek, C.E. Morgan, C.C. Fields, and N.T. Hightower, III

Abstract

Mitigation of the postulated Loss of Heat Sink Accident for the Savannah River Site K Reactor requires operator action to place the plant in a water conservation configuration. In August 1991, concerns were raised about the allowances in the

safety analyses for operator action times in an unpowered scenario, where several valves would be manually closed. WSRC management conservatively decided to include explicit consideration of a seismic initiator for this scenario, which introduced the additional concern that operator actions could be hindered by tritium from flange leakage.

The tasks completed to resolve this concern included:

- Revisions to the accident analyses
- Re-assessments of initiating event frequencies
- Re-assessments of seismic qualifications of piping systems
- Justification of extended time-usage of tritium protection suits
- Assessment of environmental conditions in the reactor building
- Human factor considerations (including drills and timing trials)
- Evaluation of revisions to technical specifications and procedures
- Evaluations of alternative methods of implementing water conservation and cooling essential equipment
- Design and fabrication of a diesel-powered emergency breathing air system

The revised analyses concluded that the powered case documented in the Safety Analysis Report is limiting and that all acceptance criteria are met.

Report No.

WSRC-MS-92-198

Authoring Organization

L1530

Integrated Safety Analysis for Nuclear Processes at the Savannah River Site

Author

W.S. Durant

Abstract

The Savannah River Site has performed risk-based safety analyses for the nuclear processes for approximately 20 years. The attached slides summarize the history, approach, criteria, documentation, technology, and controls associated with this program.

Report No.

WSRC-MS-92-314

Authoring Organization

L7200

UC - 708

Biological Sciences

Results of the F/H Effluent Treatment Facility Biological Monitoring Program, July 1987 - July 1991 (U)

Author

Winona L. Specht

Abstract

As required by the South Carolina Department of Health and Environmental Control (SCDHEC) under NPDES Permit SC0000175, biological monitoring was conducted in Upper Three Runs Creek to determine if discharges from the F/H Effluent Treatment Facility have adversely impacted the biotic community of the receiving stream. Data included in this summary report encompass July 1987 through July 1991. The F/H ETF was designed to treat wastewater at the rate of 235 gpm. Due to a reduction in process operations in F and H Areas, the F/H ETF has never operated at more than about 25% of design capacity and it is not anticipated that the F/H ETF will operate at more than 25% of design capacity in the foreseeable future. As originally designed, the F/H ETF was not expected to remove all of the mercury from the wastewater; therefore, SCDHEC specified that studies be conducted to determine if mercury was bioaccumulating in aquatic biota. Subsequent to approval of the biological monitoring program, an ion exchange column was added to the F/H ETF specifically to remove mercury, which eliminated mercury from the F/H ETF effluent.

Report Number

WSRC-RP-92-923

Authoring Organization

L3610

UC - 711

Chemical Separation Processes
for
Plutonium and Uranium

FB-Line Resin Testing Final Report

Author

C.J. Bannochie

Abstract

The Dowex 50W-X8 and 50W-X12 resin samples are both strong acid cation materials in the hydrogen form. Each material has a water retention capacity characteristic of its respective marketed degree of cross-linking. Dowex 21K gives confirmatory responses to tests for a strong anion exchange resin in the nitrate form. All three resins have the manufacturer's specified ionic type and form, and the Dowex 50W resins have characteristic water retention capacities. These tests conclude that the ion exchange resins in use in FB-Line meet the approved safety document criteria for cross-linking, ionic form, and resin type.

Report Number

WSRC-TR-92-22

Authoring Organization

L2108

UC-712

Inertial Confinement Fusion

UC- 713

Radioisotope and Radiation Applications

**Cassini Pu-238 Program, Specifications for
Plutonium Oxide Powder, General
Purpose Heat Source Fuel (U)****Author**

James W. Barber

Abstract

This fuel specification defines the chemical and physical requirements for plutonium-238 isotope in the plutonium dioxide powder form. Westinghouse Savannah River Company will provide plutonium oxalate 3+ precipitation method to Los Alamos National Laboratory (LANL). A temperature above $740^{\circ}\text{C} \pm 60^{\circ}\text{C}$ for 3 ± 0.5 hours will be used to calcine the oxalate precipitate.

Report Number

WSRC-TR-92-132

Authoring Organization

SE1333

UC-714

Criticality Studies

UC-715

Technology - Feed Materials

UC - 721

Defense Waste Management

Limits for the New DWPF Melter Off-Gas Jumper I.O.

Author

A.S. Choi

Abstract

In order to minimize solids deposition in the off-gas line between the primary film cooler and the quencher, SRTC recommended earlier that a new DWPF melter off-gas jumper be built which would increase the off-gas velocity from less than 40 ft/s under the original design to at least 55 ft/s, excluding the melter air inleakage. Two design changes proposed for the new jumper were:

(1.) relocation of the entry point for the melter pressure control air from the current position near the quencher to near the film cooler exit, and (2.) reduction of the inside diameter of the jumper from 8.22 to 7.156 inches. The objective of this study was to confirm the optimum I.D. proposed earlier and determine the upper and lower limits for the optimum I.D. to initiate the actual design process. Based on more conservative bases for optimization used in this study, it was determined that the design limits for the new jumper I.D. is $7.15 \leq \text{I.D.} \leq 7.25$ inches.

Report Number

WSRC-TR-92-31

Authoring Organization

L3100

Applicability of the Sludge Processing Technical Standard to Type IV Waste Tanks with High Fluoride Concentration (U)

Author

P.E. Zapp

Abstract

Type IV waste tanks which contain ballast water (tanks 17, 18, 19, 20, and 24) have solution compositions that are generally within the database developed for corrosion protection of the sludge processing tanks. Therefore the technical standard regarding tank chemistry limits during sludge processing is applicable to the Type IV tanks. However, Tank 20 contains levels of fluoride higher

than those treated in the sludge processing database. To confirm the applicability of the sludge processing technical standard, cyclic potentiodynamic polarization scans for pitting susceptibility were run in a simulant of the Tank 20 contents. The nitrite inhibitor level specified by the standards did inhibit pitting corrosion in the simulant. Pitting was inhibited also at the same nitrite level but with 30 percent higher concentrations of chloride, fluoride, and sulfate. Thus the sludge processing technical standard has been shown to provide corrosion protection to type IV tanks containing ballast water.

Report Number

WSRC-TR-92-175

Authoring Organization

L8200

Material Balance for the In-Tank Precipitation Process with Late Washing (U)

Author

D.D. Walker

Abstract

A new In-Tank Precipitation (ITP) material balance which includes the proposed Late Washing option has been calculated. The major effects of this new option are:

- The volume of liquid going to the Saltstone is increased by 924,000 gallons per year (13% increase).
- The concentration of liquid of sodium tetraphenylborate going to Saltstone increased by 72%.
- The volume of 10 wt% precipitate slurry increases slightly (8000 gallons per cycle or 6%). Assuming a two year storage period in Tank 49, the volume in storage increases by only 48,000 gallons.
- The storage capacity required for the late wash-water is approximately 103,000 gallons (assuming 2-month intervals between additions to Tank 48).

- The late washwater will contain 0.59 Ci Cs-137 per liter. This is greater than the level allowed in transfers to Tank 22 (limit = 0.16 Ci/L or 0.6 Ci/gal).
- Sodium tetraphenylborate requirements increase by 29% attributable to Late Washing.

Other recent process changes have also been included in this material balance. In addition, the results for two other flowsheets are described. In one flowsheet, the nitrite level assumed to be present in Tank 49 is 50% of the reference flowsheet described above, and in the other, the DWPF workoff rate is assumed to be higher than the ITP production rate for washed precipitate slurry.

Report Number

WSRC-RP-92-396

Authoring Organization

L3200

Chemical Compatibility of DWPF Canistered Waste Forms (U)**Author**

J.R. Harbour

Abstract

The Waste Acceptance Preliminary Specifications (WAPS) require that the contents of the canistered waste form are compatible with one another and the stainless steel canister. Item 3.9 of the WAPS follows: 3.9 Chemical Compatibility specifications. The contents of the canistered waste form shall not lead to internal corrosion of the canister such that there will be an adverse effect on normal handling during storage, and on an abnormal occurrence such as a canister drop accident. The producer shall describe the method of demonstrating compliance in the WCP. Corrosion, chemical interactions, and any reaction products generated within the canistered waste forms after exposure to temperatures up to the glass transition temperature shall be discussed in WQR.

Report Number

WSRC-TR-92-308

Authoring Organization

L3100

Basic Data Report: Canister Penetration System with Relative Humidity and Pressure Sensors (U)**Author**

J.R. Harbour

Abstract

This work originates from a task assignment. This basic data report is for design and fabrication of a canister penetration system for use in these experiments. The basic system was designed and fabricated as a result of a previous task assignment and three associated task plans. The new system, which will be used on canistered waste forms produced during the DWPF Startup Test Program, will be a modification of the previous system. Hence the seven items identified in the next paragraph have been previously designed, fabricated, and tested but will be required as part of the overall system. The canister penetration system to be designed and fabricated shall consist of (1.) a device which can penetrate the canister above the glass line while preventing the mixing of the air within the canister with the air in the environment, (2.) a sensor for measuring the relative humidity and dew point of the air within the canister, (3.) a sensor for detecting the pressure of the system before penetration and the pressure of the canister and system after penetration, (4.) a vacuum system for evacuating the canister penetration system, (5.) a connecting port to a mass spectrometer for on line analysis of the air within the free volume, (6.) a number of valves and joints (fittings) which make up the interconnecting plumbing, and (7.) a calibrated container for use in measuring the free volume. All of these items are deliverables.

Report Number

WSRC-RP-92-371

Authoring Organization

L3100

The First Canister Storage Building (U)**Author**

L. Lee

Abstract

The first canister storage building could become a permanent waste canister storage building if a

moderate to strong earthquake hit the site. To avoid this possibility from happening I recommend that we remove the existing plenum and draft tubes from the building.

Report Number
WSRC-RP-92-757

Authoring Organization
L3100

Determination of Process Conditions for the DWPF Melter Off-Gas HEME Spray Nozzle

Author
L. Lee

Abstract
DWPF-Technical asked SRTC to determine operating conditions for the melter off-gas HEME spray nozzles, which have a capacity 3 to 4 times that specified in the Basic Data Report (BDR). Two operating ranges are specified in the attached report by L.M. Lee.

- 0.8 - 1.3 gph water and 20 - 30 psig air, which is at the low end of the recommended range for the current DWPF nozzles.
- 0.25 - 0.35 gph water and 10 - 18 psig air, which is consistent with the DWPF BDR.

The higher range is being recommended for Cold Chemical Runs to improve HEME flushing and minimize modifications. The higher water rate has the potential to increase the pressure drop across the HEME's to an unacceptable level. However, based on industrial experience this risk is judged to be minimal. The SRTC tests show that if lower water rates are required, the existing nozzles will produce an acceptable spray. However, modification of the water delivery systems to ensure accurate delivery at the lower rate is required.

Report Number
WSRC-RP-91-1215

Authoring Organization
L3100

Aspects of the DWPF Melter Significant to Waste Acceptance

Author
M.J. Plodinec

Abstract
The repository program has established quality assurance requirements which are to be applied to activities and items which affect compliance with the Waste Acceptance Preliminary Specifications (WAPS). In this report, the aspects of the melter which are significant to meeting the WAPS are identified. Based on the Waste Form Compliance Plan (WCP), the melter plays a significant role in satisfying specification 1.3 (Product Consistency) by ensuring that feed material is sufficiently vitrified before the glass is poured into the canister. As discussed below, the aspects of the melter system important for meeting the WAPS are:

- The administrative controls and process instrumentation which will be used to assure that glass pouring is not initiated at melt temperatures < 950°C.
- The composition and rate of degradation of the glass contact refractory. Thus, these are the aspects of the DWPF melter system to which the controls in RW-0214 must be applied.

Report Number
WSRC-RP-92-323

Authoring Organization
L3100

DWPF Saltstone Study: Effects of Thermal History on Leach Index and Physical Integrity – Part II, Final Report (U)

Author
E.G. Orebaugh

Abstract
This report summarizes the observations made during the curing and testing of DWPF simulated saltstones which have been cured under isothermal conditions in sealed glass envelopes at temperatures from ambient to 95°C. This study was performed to evaluate the effect of curing at and

around temperatures representing conditions created within large pours of grout.

Report Number

WSRC-RP-92-568

Authoring Organization

L3200

WM 93 Symposium - Topic 8 Waste Minimization - Management of New Production Reactor Waste Streams

Author

W.R. McDonnell and J.L. Newman

Abstract

As the first DOE materials production reactor projected for construction and operation in many years, the New Production Reactor (NPR) presents unique opportunities for innovation in waste management practice. If sited at the Savannah River Site, moreover, the waste processing procedures supporting a heavy water reactor operation must be compatible with existing and near-term projected general site facilities. The purpose of this paper is to present the challenge facing NPR in creating innovative waste minimization/pollution prevention alternatives to traditional nuclear production waste generation practices.

Report Number

WSRC-MS-92-310X

Authoring Organization

N2100

Factors Affecting the Rate of Hydrolysis of Phenylboronic Acid in Lab-Scale Precipitate Reactor Studies

Author

C.J. Bannochie, J.C. Marek, R.E. Eibling, M.A. Baich

Abstract

Removing aromatic carbon from an aqueous slurry of cesium-137 and other alkali tetraphenylborates by acid hydrolysis will be an important step in preparing high-level radioactive waste for vitrification

at the Savannah River Site's Defense Waste Processing Facility (DWPF). Kinetic data obtained in bench-scale precipitate hydrolysis reactors suggest changes in operating parameters to improve product quality in the future plant-scale radioactive operation. The rate-determining step is the removal of the fourth phenyl group, i.e. hydrolysis of phenylboronic acid. Efforts to maximize this rate have established the importance of several factors in the system, including the ratio of copper (II) catalyst to formic acid, the presence of nitrite ion, reactions of diphenylmercury, and the purge gas employed in the system.

Report Number

WSRC-MS-92-324

Authoring Organization

L2100

Durability of Glasses from the HG-DOPED Integrated DWPF Melter System (IDMS) Campaign

Author

C.M. Jantzen

Abstract

The Integrated DWPF Melter System (IDMS) is designed and constructed to be a 1/9th scale prototype of the full scale Defense Waste Processing Facility (DWPF) melter. The IDMS facility is the first engineering scale melter system capable of processing mercury and flowsheet levels of halides and noble metals. In order to determine the effects of mercury on the feed preparation process, the off-gas chemistry, glass melting behavior, and glass durability, a three-run mercury (Hg) campaign was conducted. The glasses produced during the Hg campaign were composed of Batch 1 sludge, simulated precipitate hydrolysis aqueous product (PHA) from the Precipitate Hydrolysis Experimental Facility (PHEF), and Frit 202. The glasses were produced using the DWPF process/product models for glass durability, viscosity, and liquids. The durability model indicated that the glasses would all be more durable than the glass qualified in the DWPF Environmental Assessment (EA). The glass quality was verified by performing the Product Consistency Test (PCT) which was designed for glass durability testing in the DWPF.

Report Number
WSRC-RP-91-371

Authoring Organization
L3100

Supercritical Water Oxidation Technology for DWPF(U)

Author
J.T. Carter, J.A. Gentilucci

Abstract
At the request of the Savannah River Operations High Level Waste Division office, DWPF and SRTC personnel have reviewed two potential applications for supercritical water oxidation technology in the DWPF. WSRC considers the technology to be ranked second (behind the detoxifier) for benzene destruction.

Report Number
WSRC-RP-92-252

Authoring Organization
L3100

IDMS Process Hazards Review Addendum

Author
J.R. Zamecnik

Abstract
DWPTS plans to test a new flowsheet for the DWPF Chemical Process Cell (CPC) in the Integrated DWPF Melter System (IDMS). This flowsheet will use nitric acid in place of formic acid to adjust the pH of the alkaline simulated high level waste (HLW) sludge. The potential hazards are (1.) unexpected mixing of concentrated nitric acid with concentrated formic acid in the feed delivery system; and (2.) the mixing of nitric and formic acids in the process. The first hazard is mitigated by flushing the formic acid feed delivery system prior to the introduction of nitric acid; the second is not a hazard since both acids will exist at concentrations much lower than those that would be hazardous.

Report Number
WSRC-PH-92-005

Authoring Organization
L3100

Characterization of the Defense Waste Processing Facility (DWPF) Environmental Assessment (EA) Glass Standard Reference Manual (U)

Author
C.M. Jantzen

Abstract
Liquid high-level nuclear waste at the Savannah River Site (SRS) will be immobilized by vitrification in borosilicate glass. The glass will be produced and poured into stainless steel canisters in the Defense Waste Processing Facility (DWPF). Other waste form producers, such as West Valley Nuclear Services (WVNS) and the Hanford Waste Vitrification Project (HWVP), will also immobilize high-level radioactive waste in borosilicate glass. The canistered waste will be stored temporarily at each facility for eventual permanent disposal in a geologic repository. The Department of Energy has defined a set of requirements for the canistered waste forms, the Waste Acceptance Preliminary Specifications (WAPS). The current Waste Acceptance Preliminary Specification (WAPS) 1.3, the product consistency specification, requires the waste form producers to demonstrate control of the consistency of the final waste form using a crushed glass durability test, the Product Consistency Test (PCT). In order to be acceptable, a waste glass must be more durable during PCT analysis than the waste glass identified in the DWPF Environmental Assessment (EA). In order to supply all the waste form producers with the same standard benchmark glass, 1000 pounds of the EA glass was fabricated. The chemical analyses and characterization of the benchmark EA glass are reported. This material is now available to act as a durability, analytic, and/or redox Standard Reference Material (SRM) for all waste form producers.

Report Number

WSRC-TR-92-346

Authoring Organization

L3100

Method of Calculation of Heat Generation Rates for DWPF Glass (U)**Author**

M.J. Plodinec

Abstract

The Waste Acceptance Preliminary Specifications (WAPS) require estimates of the heat generation rate of DWPF waste glasses. Estimates of the heat generation rates of projected glass compositions are to be reported in the Waste Form Qualification Report. Similar estimates for actual production glasses are to be reported in the production records. In this report, a method of calculating the heat generation rate from the radionuclide inventory is provided. Application of the method to the DWPF design basis glass indicates that the heat generation rate can be accurately estimated from the Sr-90, Y-90, Cs-137, Ba-137m, and Pu-238 contents alone.

Report Number

WSRC-RD-92-2

Authoring Organization

L3100

Effect of Late Washing on Saltstone Leaching Parameters (U)**Author**

E.G. Orebaugh

Abstract

Saltstone waste forms have been prepared from mixtures of reference salt solution and synthetic late wash wastes. Initially waste forms were made up containing one and two times the amount of late wash wastes expected to be blended with reference salt wastes. These specimens were cured for 28 days at ambient temperature before being sectioned and leached according to the ANS 16.1 pro-

ocol. At this time, eight of the ten leachage changes (first two weeks of the 90 day procedure) have been made and analyzed. The protocol allows evaluation of the diffusion coefficient and the leach index to be estimated from the results of the first seven leachage analysis. These estimates have been made and they show no significant difference compared to reference case saltstones prepared, cured, and leached concurrently with these test wastes.

Report Number

WSRC-RP-92-610

Authoring Organization

L3200

Effect of Late Washing on Saltstone TCLP Compliance (U)**Author**

E.G. Orebaugh

Abstract

Saltstone waste forms have been prepared from mixtures of reference salt solution and synthetic late wash wastes. Initially waste forms were made up containing one and two times the amount of late wash wastes expected to be blended with reference salt wastes. These first specimens have passed the required TCLP testing without difficulty as was expected from the analysis of the synthetic late wash wastes used in their preparation.

Report Number

WSRC-RP-92-649

Authoring Organization

L3200

Sodium Tetraphenylborate Solution Stability - A Long Term Study (U)**Author**

M.J. Barnes

Abstract

Long term stability of aqueous alkaline solutions of sodium tetraphenylborate (NaTPB) has been investigated. The focus of the investigation is on the relative stabilities of NaTPB solutions exposed to

varying temperatures and copper concentrations over an extended period of time. Additionally, vendor-supplied samples, incubated at 40°C, were stored for more than a year without decomposing. Collected data demonstrates that in the absence of elevated copper concentrations, NaTPB solutions will remain stable for periods of one to two years (at a minimum) at maximum expected operating conditions (<40°C). Additionally, biuret, (H₂NCO)₂NH, was tested as an additive to prevent copper-induced decomposition without success.

Report Number

WSRC-RP-92-786

Authoring Organization

L3200

DWPF Ammonium Ion Analysis**Author**

R.E. Eibling

Abstract

The attached report documents SRTC's recommended method to perform analyses for ammonium ion in DWPF process streams. Also included are the technical basis supporting the recommended analytical technique, the accuracy and precision of the method, known interferences and maintenance details. Additional development work is planned to identify an improved method requiring less maintenance.

Report Number

WSRC-RP-92-775

Authoring Organization

3100

Waste Drums in GCD(U)**Author**

A.D. Yu and J.R. Cook

Abstract

At the request of Waste Management Technology, Interim Waste Technology has modeled and determined the acceptable inventory limits for the disposal of less than 100 nCi/g transuranic waste drums in the Greater Confinement Disposal (GCD)

based on the passive-active neutron (PAN) assay of 1,697 drums. Our recommendations are:

1. All transuranic waste drums must be reassayed in order to determine if they can be disposed in the GCD Trench
2. Only less than 100 nCi/g drums can be disposed in GCD
3. Waste produced from the HB-Line must be re-assayed for Np-237 content. Drums with more than 0.010 g of Np-237 should be excluded from GCD disposal;
4. Drums containing mixed wastes cannot be disposed in GCD.

Report Number

WSRC-TR-92-41

Authoring Organization

L3200

Measured Leak Rates of the Temporary Seals in DWPF Canistered Waste Forms after Three Years of Onsite Storage**Author**

J.B. Harbour and T.J. Miller

Abstract

In the summer of 1990 a study was carried out to determine the internal pressure, relative humidity, and chemical composition of the gas within the free volume of four canistered waste forms produced at TNX in May of 1988 (Ref. 1). Three of these canistered waste forms were sealed only by temporary seals and subsequently stored in the TNX "boneyard" with no protection. The fourth canister was sealed by upset resistance welding. All three canisters with temporary seals were decontaminated by aqueous frit blasting. It was important to remeasure the leak rates of these seals to ensure that leaktightness had not deteriorated during canister handling and storage prior to the time the experiments were performed. This paper details the results of two separate measurements of the leak rates of these seals.

Report Number

WSRC-TR-92-171

Authoring Organization

L3100

Minimum Benzene Equivalents in Precipitate Feed to the DWPF Salt Processing Cell**Author**

M.A. Baich

Abstract

Experience from pilot scale process simulations of the precipitate hydrolysis process has demonstrated that a minimum precipitate feed benzene equivalent will be required to avoid operational difficulties with decanters in the Salt Processing Cell (SPC). The source of benzene in the precipitate feed is compromised of various tetraphenylborate solids, phenylboric acid, and dissolved benzene. However, since the potassium tetraphenylborate solids are by far the greatest source of benzene in the precipitate feed (nominally >7.5 wt%), the development of a minimum benzene equivalent was based only on the potassium tetraphenylborate component of the feed. It is recommended that the minimum potassium tetraphenylborate concentration in the precipitate feed to the SPC be established at 6.8 wt%. This concentration of potassium tetraphenylborate will ensure sufficient benzene is produced in each precipitate reactor (PR) cycle to offset the maximum projected benzene losses to the vessel vent system and still accommodate the quantity of organic high boilers anticipated to be produced during a PR batch. This limit is conservative in that a nitrite content of 0.20 molar was assumed for the feed (nominally <0.08 molar) and benzene losses to the process vessel vent system was maximized. If the proposed nitrite limit of 0.01 molar in the precipitate feed is approved, the minimum potassium tetraphenylborate concentration in the precipitate feed could be as low as 4.5 wt.%.

Report Number

WSRC-RP-92-0143

Authoring Organization

L3100

Radioactive Demonstration of DWPF Product Control Strategy (U)**Author**

M.K. Andrews and N.E. Bibler

Abstract

The effectiveness of the product and process control strategies that will be utilized by the Defense Waste Processing Facility (DWPF) was demonstrated during a campaign in the Shielded Cells Facility (SCF) of the Savannah River Technology Center (SRTC). The remotely operated process included the preparation of the melter feed, vitrification in a slurry-fed 1/100th scale melter, and analysis of the glass product both for its composition and durability. The campaign processed approximately 10 kg (on a dry basis) of radioactive sludge from Tank 51. This sludge is representative of the first batch of sludge that will be sent to the DWPF for immobilization into borosilicate glass. Additions to the sludge were made based on calculations using the Product Composition Control System (PCCS). Analysis of the glass produced during the campaign showed that a durable glass was produced with a composition similar to that predicted using the PCCS.

Report Number

WSRC-TR-92-217

Authoring Organization

L3100

Organics in the Chemical Processing Cell and Their Potential Effects on the DWPF Operation (U)**Author**

N.D. Hutson

Abstract

Based on observations made during the operation of the Integrated DWPF Melter System (IDMS), aromatic organics entering the DWPF Chemical Processing Cell (CPC) can be expected to distribute throughout the CPC Process Vessel Vent System (PVVS) and Mercury Purification Cell (MPC). The potential impacts to the operation of the DWPF are discussed.

Report Number
WSRC-TR-92-0006

Authoring Organization
L3110

Errors of DWPF Frit Analysis - Final Report (U)

Author
R.F. Schumacher

Abstract
Glass frit will be a major raw material for the operation of the Defense Waste Processing Facility. The frit will be controlled by certificate of conformance and a confirmatory analysis by a commercial laboratory. The following effort provides additional quantitative information on the variability of frit analyses at two commercial laboratories. Identical samples of IDMS Frit 202 were chemically analyzed at two commercial laboratories and at three different times over a period of four months. Similar samples were analyzed once by SRTC's ADS laboratory. The vendor also supplied an analysis for one of the samples. The variability of the oxide determinations was shown to be critical to the frit acceptance process. All of the laboratories provided reasonable good chemical analyses. However, the CELS laboratory consistently provided a better level of precision. The standard deviations of the Monarch analyses for individual elements were two to ten times greater than the CELS analyses. The variabilities of the results were analyzed and it was concluded that a single CELS laboratory analysis was sufficient to confirm the certification of SRL Frit 202 with a high level of confidence. The Monarch analyses were more variable and twice as many analyses would be required to obtain similar levels of confidence. It is strongly suggested that the CELS laboratory be used as a sole source supplier of the chemical analyses for DWPF Frit until such time as it is shown that other laboratories can provide levels of analytical precision.

Report Number
WSRC-RP-92-37

Authoring Organization
L3100

Formation Rate of Ammonium Nitrate in the Off-Gas Line of SRAT and SME in DWPF (U)

Author
L. Lee

Abstract
A mathematical model for the formation rate of ammonium nitrate in the off-gas line of the Sludge Receipt and Adjustment Tank (SRAT) and the Slurry Mixed Evaporator (SME) in DWPF has been developed. The formation rate of ammonium nitrate in the off-gas line depends on pH temperature, volume and total concentration of ammonia and ammonium ion. Based on a typical SRAT and SME cycle in DWPF, this model predicts the SRAT contributes about 50 lbs. of ammonium nitrate while SME contributes about 60 lbs. of ammonium nitrate to the off-gas line.

Report Number
WSRC-RP-92-346

Authoring Organization
L3100

Final Wash Precipitate Feed Simulants for DWPF Cold Chemical Runs

Author
J.C. Marek

Abstract
Precipitate feed simulant specifications for Defense Waste Processing Facility (DWPF) Cold Chemical Runs are revised in this report. All previous specifications of precipitate feed simulants for DWPF Cold Chemical Runs (CCRs) are superseded by this document. The revision is needed to (1.) eliminate use of hydroxylamine nitrate (HAN) in the precipitate process operation, (2.) simulate the projected composition of the precipitate feed to DWPF produced by final washing to reduce the nitrite concentration to $\leq 0.01M$ without washing the simulated feed, (3.) delete organic trim chemical additions to the precipitate feed, and (4.) specify an additive to prevent foaming of the precipitate. Two specifications are provided to operate the Salt Processing Cell (SPC) with mercury (Tests 5 and 6)

and without mercury (Tests 1 - 4) in the precipitate feed.

Report Number
WSRC-RP-92-703

Authoring Organization
L3100

shows no disposal containers exceeded 100 grams of U-235.

Report Number
WSRC-RP-91-1207

Authoring Organization
L3200

Evaluation of the DWPF Chemical Process Cell Sample Condenser

Author
J.R. Zamecnik

Abstract
An on-line analysis system for hydrogen is being added to the Chemical Processing Cell (CPC) in DWPF to ensure that the process does not operate above the lower flammable limit (LFL). The method chosen to measure hydrogen during cold runs is gas chromatography (GC). In order for the GCs to analyze the offgas exiting the SRAT and SME condensers, an additional condenser is required to reduce the dew point of the sample to below the lowest ambient temperature expected so that no liquid water will enter the GCs. This temperature was chosen to be 10°C.

Report Number
WSRC-TR-92-255

Authoring Organization
L3100

Quantities of Uranium-235 Buried in Disposal Boxes 1983-1991 (U)

Author
J.R. Cook

Abstract
IWT was asked to determine the distribution of the quantity of enriched uranium per disposal box (B-25) of the years 1983-1991 to provide input to an uptake of the E Area Safety Analysis. This information was considered important since the issue of criticality is an important concern in safety analyses. Information found in the COBRA database

UC- 722

Transportation of Nuclear Materials

Technical Problems Encountered During Certification of a Type B (Plutonium) Package (U)

Author

R.J. Gromada and E.K. Opperman

Abstract

Westinghouse Savannah River Company (WSRC) is the packaging designer for the 5320 Type (B) PuO₂/AmO₂ Packaging (DPSU79-124-1, "Safety Analysis Report - Packages"). The predecessor to the 5320 Packaging introduced in 1980, was originally developed in 1973 for shipping plutonium and americium. The 5320 Packaging has undergone numerous design changes since 1980 to meet changing packaging and transportation regulations. During the current certificate renewal process, WSRC experienced significant technical problems with the packaging design. This paper will discuss the technical problems associated with the design, the technical challenges they presented and the design solutions that were implemented to meet current Department of Energy (DOE) regulations.

Report Number

WSRC-MS-92-311

Authoring Organization

L2720

UC-731

Nuclear Materials Production

UC-732

Special Isotope Separation
(Plutonium)

UC-733
Nuclear Raw Materials

UC-741
Chemical High Explosives

UC-742

Applications of Explosions

UC-743
Nuclear Propulsion Systems

UC-744

Aerospace Nuclear Safety

Index

Numerics

1,1-dichloroethane 13
105-K Building 32
2DPUF 10, 14, 15
304L Stainless Steel 21

A

AC Flow tests
 L Area 39
Accident
 postulated 49
Accident analyses 43
AC-flow 31
Acid hydrolysis 67
Acid/Caustic Basin 12
 F Area 13
 H Area 14
 P Area 12
Activity
 alpha/beta determination 4
 neutron 4
Alizarin Yellow 41
Alloys
 aluminum 20
Alpha 13
 counting 22
 determination 4
Aluminum 13
 corrosion 21
 molten 20
Americium 76
Ammonium ion 70
Ammonium nitrate 72
Anion exchange resin 54
Annular flow 40
Aqueous frit blasting 70
Aromatic carbon 67
Aromatic hydrocarbons 11
Aromatic organics 71
ASCOT 9
Assay techniques 4
Atmosphere
 simulations 9
Atmospheric models 10, 14, 15
AUTOPIPE 44
Axial power 26
Axial power monitors 31
AXLIB4 26

B

B-25 73
Ballast water 64
Barium 13
Barometric Pumping
 of Burial Trench Soil Gases 11
Benzene 13, 32, 68, 71
Beta 13
 determination 4
 counting 22
bicarbonate 4
Bingham pumps 35
Bioaccumulation 52
Biofouling 33
Biological monitoring program 52
Biological sciences 51
Boron Carbide 42
Borosilicate glass 68, 71
Borrow pits 8
Buffer 41
Buffer salts 41
Burial trench 11
Burnout Risk (BOR) 41
Burnup 27

C

Cadmium 13
Calcine 58
Camera 36
Canister 65, 66, 68
Canistered wasteforms 70
Canyon 44
Carbon
 aromatic 67
Carbon dioxide 12
Carbon steel 22
Carbon tetrachloride 13
Carbonate 4
Cassini 58
Cement 43
Cement-sand grout 43
CERT 21
Cesium 67
Chemical fixation 14, 15
Chemical Process Cell 68, 73
Chemical Processing Cell 71
Chemical separation processes 53
Chemistry 3, 4, 22
 in storage basins 21
 moderator 38
 of moderator 22

offgas 67
waste tank 64
Chlordane 8
Chloride 8, 64
Chlorinated hydrocarbons 11
Chloroethene 13
Chromatography
gas 73
Circumferential crack
in piping 20
Climatology site 11
Closure cap 10
COBRA 73
Computer code certification 27
Computer code verification 27
Computer sciences 23
Consolidated Incineration Facility 30
CONTAIN/SR 49
Contaminant transport 14, 15
Contamination 37
alpha/beta 36
Control rod 20, 31, 38, 40, 42, 48
cooling 20
Convergence criteria 25
Coolant coefficient 32
Cooling 27
Cooling coil 48
Cooling coil leakage 38
Cooling water flow 30
Cooling Water System 32, 37, 44
in Tank Farm 48
inlet headers 44
expansion joint 39
Copper 67, 70
Core
K Reactor 43
Core samples
K Area 43
Core symmetry 25
Core temperatures 28
Corrosion 22, 38, 42, 64, 65
in SRS Storage Basins 21
RBOF 40
Corrosion inhibitor 41
Counting
alpha, beta, liquid scintillation 22
Cracking
stress corrosion 21
Criticality studies 59

D

Data acquisition system 24
DC-flow 31
Decay heat 26
Decontamination 37, 41
Defense waste management 63
Defense Waste Processing Cell 71
Defense Waste Processing Facility 31, 33, 45, 64,
65, 66, 67, 68, 70, 71, 72
Design basis earthquake 48, 49
Detoxifier 68
Dew point
measuring 65
Diffraction
X-ray 22
Diffusion 9
atmospheric 9
Diphenylmercury 67
Dispersion
atmospheric 15
Disposal boxes 73
Dissolved solids 8, 12
Double-Ended Guillotine Break 25, 31, 44
Drinking water 8

E

Earthquake 44, 66
K Reactor 49
Eddy current 30
Effluent Treatment Facility
F/H 32, 33, 52
Electropolishing 37
Emergency breathing air system 50
Emergency cooling system 31, 34, 44
Emergency response 16
Endrin 13
Energy dispersive spectroscopy 22
Engineering 29
Enriched uranium 73
Environmental remediation 10
Environmental sciences 7
Equipment 29
Explosions
vapor 21

F

F Area 44
Acid/Caustic Basin groundwater 13
seepage basins 14, 15

F/H Effluent Treatment Facility 32, 33, 52
Fault Tree Analysis 44
FB-Line 54
Feed materials 61
Film cooler 64
FIPROD 27
Fish
 tritium uptake 10
Flag 2 criteria 8, 12, 13
Flagging criteria 8, 12, 13, 14
Flow instability 41
Flowmeters
 thermal 31
Fluoride 64
 in waste tanks 64
Flux distributions 25
Flyash 9
Foam 41
FOME-ADD 4
Forest
 productivity and sludge 8
Formic acid 67, 68
Four Mile Creek 10
FPCALC 27
Fracture parameters 20
FRIMHX 25, 32
Frit 72
Frit-202 72
Frit blasting 70
Fuel 28
 aluminum clad 21
 assemblies 21
Fusion 55

G

Gadolinium 4
GAM-HEAT 25
Gamma heating 42
Gamma heating accident 34
Gamma radiation 25
Gamma spectroscopy 22
Gang rod 38
Gas chromatography 73
Gas metal arc welding 22
GEDIT 27
General purpose heat source 58
GENPRT 27
Geosciences 17
GILDA 26
GLASS 25, 26, 28, 32
Glass 66, 67, 69, 71, 72
 composition, durability 71

Glass durability test 68
Glass standard 68
Greater Confinement Disposal 70
GRIMHX 26, 28
GRISET 25
Groundwater 9
 F- and H-Area sewage sludge sites 8
 F-Area Acid/Caustic Basin 13
 H-Area Acid/Caustic Basin 14
 K Area 12
 K Area, Par Pond 8
 mixed waste management facility 13
 P-Area Acid/Caustic Basin 12
 P-Area Acid/Caustic Bassin 12
 remediation 10
 Sanitary landfill 8
Grout 43, 67

H

H Area 21, 38, 44, 48
 Acid/Caustic Basin Groundwater 14
 seepage basins 14, 15
H Canyon 43
Halides 67
Halogens 12, 13
 organic, in drinking water 8
Hazardous low-level waste
 simulated 21
Hazardous waste 10
HB Line 70
Health 47
Heat exchanger 30, 40, 42, 49
 K Reactor 22
 leakage history 30
Heat source 58
Heat transfer 25
Heat Transfer Laboratory 24, 40
Heavy water
 tritiated 49
Heavy water reactor 67
Helium bubble 22, 48
HEME 66
Herbicides 12
High activity waste tank 38
High-level waste 68
Human factors 50
Hydraulic conditions 35
Hydraulics 31, 44
Hydrocarbons 11
Hydrogen 32, 73

Hydrolysis 67
Hydroxide 4, 22
Hydroxylamine nitrate 72

I

IDMS 67, 68, 71
Inertial confinement 55
Instruments 29
In-Tank precipitation 9, 64
Interarea transfer pump pits 32
Ion exchange 52, 54
Ion exchange resin 36
Iron 12, 13, 14
Isotopic cross sections 26
Isotopic inventory 28

J

J80 system 25
J-integral 20
JOSHUA 26

K

K Area 8, 30, 43
 acid/caustic basin groundwater 12
K Reactor 20, 30, 31, 32, 36, 44, 48
 heat exchanger 22
 LOPA 32
 loss-of-heat-sink 49
 power limits 43
 safety analysis 41, 43
 tank 37
Kanne chamber 21

L

L Area 30
L Reactor 20, 35, 37, 44
LabView 40
L-Area AC Flow Tests 39
Largemouth bass 10
Latch mechanism 20, 30
Leaching 66
Lead 8, 13
Leak rate
 in cooling water system 39
 in reactor heat exchanger tubes 42
Leaks
 Gadolinium into reactor 5
Liquid scintillation counting 4

Lithium
 molten 20
Lithium-Aluminum
 molten jets 20
Loss of Control Rod Cooling (LCRC) event 42
Loss-of-coolant accident 25, 31, 35, 40
Loss-of-cooling Accident 34
Loss-of-Heat Sink Accident 49
Loss-of-pumping accident 32, 44
Loss-of-riverwater
 in reactor 49
lower flammable limit 73
Low-level waste
 simulated 21

M

Macrophytes 10
Manganese 8, 12, 13, 14
Mark-22 38, 39, 40
Mark-60B 34
Mark VI-B 32
MARY 32, 38
Mass spectrometer 65
Materials 19
 nuclear 77
Mathematical model 72
Mathematics 23
MATHEW- ADPIC 15
MATS 10, 14, 15
Melter 66, 67, 68, 71
 feed 71
 feed material 34
Melter Feed Tank 33
Mercury 11, 13, 52, 67, 71
Mesh points 25
Metal hydride vessels 21
Metallurgical examination
 of heat exchanger tubes 30
Metallurgy 20
Metals
 contamination 14, 15
 in seepage basins 14, 15
 noble 67
Meteorological data 16
Methane 12
Microfront 9
Microscopy
 scanning electron 22
 transmission electron 22
Mixed Waste Management Facility 13
Mnemonics 25
Modeling 9

Moderator 28
Moderator chemistry 22, 38
Monte Carlo technique 39

N

Neptunium 70
Neutron
 activity 4
Neutron poison 38
New Production Reactor 67
Nickel 13
Nitrate 4, 8, 9, 13, 72
Nitric acid 4, 41, 68
Nitrite 8, 22, 41, 67
Nitrite inhibitor 64
Nitrogen 8
Nocturnal boundary layer 9
Nuclear fuel cycle 28
Nuclear material
 transportation 75
Nuclear materials production 77
Nuclear waste 2

O

Offgas 72
Off-Gas HEME Spray Nozzle 66
Off-Gas jumper 64
Organic carbon 12
Organic halogens 8, 12, 13
Organics 71
Osmosis 32, 33
Oxalic acid 4, 33, 41
Oxidation
 water 68

P

P Area
 Acid/Caustic Basin groundwater 12
P Reactors 37
Packaging 76
Par Pond 8
Paraffins
 normal 11
Permeation rates 21
Pesticides 12
PHEF 45
Phenylboric acid 71
Phenylboronic Acid 67
Photomultiplier tubes 36

Pipe
 rupture 44
Piping
 circumferential cracking 20
 configurations in K Reactor 32
 systems 20
Pitting 64
Plastic suits 49
PLUME 10, 14, 15
Plume
 simulated 9
Plutonium 21, 53
 transportation 76
Plutonium oxide powder 58
Porflow 9
Postulated accident mitigation 49
Potassium tetraphenylborate 71
Potentiodynamic 64
Power levels 31, 48
Power limits
 K Reactor 43
Precipitate 67
Precipitate feed 71, 72
Precipitate Hydrolysis Experimental Facility 67
Pressure
 measuring 65
Primary drinking water standards 8, 12, 13, 14
Probabilistic Safety Assessment 49
PROCES 27
Process hazards 68
Process vessel
 vent system 71
Process water flow 30
Process water heat exchanger 42
Process water system 44
Processing facilities
 safety documentation 49
Product Composition Control System 33, 71
Production
 nuclear materials 77
Pu-238 Program 58
PUFF 10, 14, 15
Pulse height analysis 22
Pump Pit 32
Purge gas 67
Pyrophoricity
 of uranium 5

Q

Quality Assurance 2
Quencher 64
Quenching
 of molten lithium-aluminum jets 20

R

Radiation
 gamma 25
Radiation applications 57
Radioactive sludge 71
Radioactive waste 67
Radiography 20
Radioisotope 57
Radiological suits 49
Radiological surveys 35
Radiologically controlled areas
 and earthquakes 49
Radionuclide inventory 69
Radionuclides
 in groundwater 12, 13, 14
 in seepage basins 14, 15
Radium 13, 14
Rainfall 11
RAMS 9
RBOF 40
Reactivity coefficients 32
Reactivity effects 48
Reactivity excursion 38
Reactor
 analysis codes 25
 axial power monitors 31
 components 34
 control rods 31
 disassembly basins 21
 heat exchanger 42
 heat exchangers 30
 irradiation or burnup 28
 LOCA 35
 plenum 44
 power levels 31, 48
 powers 34
 safety 26, 27, 28
 safety analysis 38, 48, 49
 safety rods 30, 42
 safety system 4
 scram 26
 Taiwanese Research Reactor 21

 tank 34, 44
 tank repair 22
 transient 48
Reactor vessel
 simulated 40
Receiving Basin for Offsite Fuel 21, 40
RELAP5 35
Relative humidity
 measuring 65
Releases
 in the Tank Farm 48
Remediation
 in situ, of metals 14, 15
Replacement Tritium Facility 21
Research
 and quality assurance 2
Resin 54
Reverse osmosis 32, 33
Robot 35
Robotics 36
Rod tests 32
RTF 21

S

Safety 47
Safety analyses 50
Safety Analysis 20, 48, 50
 K Reactor 41
 reactor 38
Safety Analysis Reports 49
Safety Computers 38
Safety documentation 49
Safety rod 20, 26, 30, 34, 38
 boron carbide 42
Safety system 4
Salt Process Cell 31, 45
Salt Processing Cell 71, 72
Saltstone 64, 66, 69
Saltstone leaching 69
Saltstone vault 9
Sampling
 techniques for alpha/beta 4
Sanitary Landfill 11
 groundwater monitoring 8
Scanning electron microscopy 22
Scientific Code Management System 27
Scintillation counting 22
Scintillator 36
Scram 26, 42
SCUREF 2
Seepage basins
 F and H Area 14, 15

Seismic event 49
Seismic qualifications
 of piping 50
Seismic stress 38
Separation
 chemical 53
Septifoil 20, 40, 42
 type J 31
 Type Q 40
Septifoils 48
Sewage 8
Sewage Sludge 8
SHIELD 27, 28
Shielded Cells Facility 71
SHLDED 27
Shoe cover 30
Silver 13
SIMON 35
Simulant
 precipitate feed 72
Simulations
 atmospheric 9
Sludge 4, 8, 14, 15, 64, 71
 washing 4
Slurry 67
Slurry composition 34
Slurry Mix Evaporator 33
SME 72, 73
Sodium 8, 33
Sodium tetrphenylborate 64, 69
Software usability testing 24
Soil gas 11
Source term 16
Specific conductance 14
Spectrometry
 mass 65
Spectroscopy
 energy dispersive 22
 gamma 22
SRAT 72, 73
STABLE 9
Stainless steel 21, 22
Steel
 carbon 22
Storage basins
 and corrosion 21
Stress-corrosion cracking 21
Sulfate 64
Sump pumps 39
Supernatant liquid 4
Supplementary Safety System 43

T

Taiwanese Research Reactor 21
Tank 20 64
Tank 22 65
Tank 48 64
Tank 49 64
Tank 51 71
Tank chemistry 64
Tank Farm 48
Technical standard
 sludge processing 64
Technology
 feed materials 61
Tensile tests 21
Tetrachloroethylene 13
Tetraphenylborate 64, 67, 69, 71
Thermal flowmeters 31
Thermocouple 39, 43
Tie rod 39
TNX 33, 70
Toxic metals 14, 15
TRAC 15
Transient analysis 32
Transient behavior 24
Transmission electron microscopy 22
Transport
 atmospheric 9
 of contaminants 14, 15
Transport and diffusion 9
Transportation 75
Trichloroethylene 13
Trichlorofluoromethane 13
TRIMHX 32
Tri-n-butyl Phosphate 32
Tritiated heavy water 49
Tritium 4, 8, 13, 14
 leakage 50
 permeation 21
 uptake 49
 uptake in fish 10
Tritium effluent water monitor 36
Tropical storms
 Klaus and Marco 11
Turbidity 14
Turbidity standards 12, 13, 14
Turbulence 9
Type "Q" septifoil 40
Type 304 stainless steel 22
Type B package 76
Type J septifoil 31
Type Q septifoil 31

U

Ultrasonic inspection 37
Upper Three Runs Creek 52
Uranium 53, 73
 pyrophoricity of 5
Uranium Solidification Facility 43
Uranyl Nitrate storage tank 43
Usability testing 24

V

Vacuum system 65
Vapor explosions 21
Video camcorders 40
Video camera 48
Video systems 36
Vinyl chloride 13
Vitrification 67, 68, 71
Volatile organic compounds 13, 14
Volatile organic species 11

W

Waste
 defense 63
 hazardous sites, closure 10
 mixed waste management facility 13
 simulated hazardous low-level 21
 sludge washing 4
 treatment and characterization 10
 vitrification 67
 processing 4
Waste Acceptance Preliminary Specifications 33, 65,
 66, 68, 69
Waste drums 70
Waste Form Compliance Plan 66
Waste minimization 41, 67
Waste Siting 2
Waste tanks 21, 36, 64
 cooling coil leakage 38
 corrosion 40
 high activity 38
 use of foam 41
Waste Tank Farm 48
Wasteforms 65
Wastewater 52
 sludge 8
Water hammer 38
Water oxidation 68
Welding
 gas metal arc 22

WIGGLE 26
WIND 10, 14, 15
Word processing software 24
WorkBench™ software 24

X

X-ray diffraction 22

END

**DATE
FILMED**

3 / 16 / 93