ADVANCED WATER-COOLED PHOSPHORIC ACID

FUEL CELL DEVELOPMENT

TECHNICAL PROGRESS REPORT NO. 17

A QUARTERLY REPORT for JULY, AUGUST, SEPTEMBER 1989

Contract DE-AC21-88MC24221

FCR-10669

Prepared for

U.S. Department of Energy
Morgantown Energy Technology Center
P.O. Box 880, 3610 Collins Ferry Road
Morgantown, WV 26505-0880

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

P.O. Box 739
195 Governors Highway
South Windsor, Connecticut 06074

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

TABLE OF CONTENTS

Section	Page
PROGRAM HIGHLIGHTS	iv
I. INTRODUCTION	1-1
II. STATUS	2-1

PROGRAM HIGHLIGHTS

- One hundred fifty (150) electrolyte reservoir plates (ERP's) were carbonized for the small area short stack.
- A process was developed which allows thin (1-2 mil) matrix to be applied to full-size electrodes using a curtain coater.
- Full size cooler samples were molded with and without cooler tube arrays.
- Two alternative cooler hoses were evaluated and found to be acceptable based on 1400-hours of testing at simulated conditions.

I. INTRODUCTION

The Advanced Water Cooled Phosphoric Acid Fuel Cell Development program is being conducted by International Fuel Cells Corporation (IFC) to improve the performance and minimize the cost of water cooled, electric utility phosphoric acid fuel cell stacks.

The program adapts the existing on-site Configuration B cell design to electric utility operating conditions and introduces additional new design features. Task 1 consists of the conceptual design of a full-scale electric utility cell stack that meets program objectives. Tasks 2 and 3 develop the materials and processes required to fabricate the components that meet the program objective. The design of the small area and three 10-ft² short stacks is conducted in Task 4. The conceptual design also is updated to incorporate the results of material and process developments, as well as results of stack tests conducted in Task 6. Fabrication and assembly of the short stacks is conducted in Task 5 and subsequent tests are conducted in Task 6. The Contractor expects to enter into a contract with The Electric Power Research Institute (EPRI) to assemble and endurance test the third 10-ft² short stack. The management and reporting functions of Task 7 provide DOE/METC with program visibility through required documentation and program reviews.

This report describes the cell design and development effort that is being conducted to demonstrate by subscale stack test, the technical achievements made toward the above program objectives.

II. STATUS

TASK I - CONCEPTUAL DESIGN

Objectives

The objective of this task is to define the conceptual design for a cell stack having a performance level of at least 175-W/ft² and a manufactured cost of less than \$400/kW. The stack must be capable of operating for a minimum of 40,000 hours at electric utility conditions.

Activity

This activity has been completed.

TASK 2 – COMPONENT DEVELOPMENT

Subtask 2.1 – Materials Development

Objectives

The objectives of this subtask are to provide an improved substrate, verify the stability of low cost substrate and electrolyte reservoir materials at pressurized cell operating conditions, and increase the thermal conductivity of the electrolyte reservoir.

Activity

Three alternative substrates were catalyzed for evaluation testing in 2 inch x 2 inch cells. Prior lab test data as well as the 2 x 2 cell test results for Vendor A substrate show that performance fully meets requirements. Cell test results from the other two substrates are incomplete.

Subtask 2.2 – Single Cell Testing

Objectives

The objectives of this subtask are to test subscale cells to evaluate improvements in cell components consisting of substrates, electrolyte reservoir plates, catalyst and matrix; verify performance and endurance of components fabricated for short stacks; optimize the hydrophobicity of catalyst layers made for operation at power densities of 200 WSF or greater; evaluate a higher performing laboratory catalyst for this application, and define the permissible range of operating conditions.

Activity

Cells tested this period are listed in Table 2.2–1.

The voltages of cells 4315 and 4327 did not change during this period. Recent performance and gain data are given in Table 2.2.–2.

Table 2.2.1. Subscale Cells Tested This Quarter

<u>Cell #</u>	<u>Anode</u>	<u>Cathode</u>	<u>Test Purpose</u>
4315	0.27 mg HYCAN –sintered at 640°F	0.53 mg GSB-18 (4 mil pinch)	Effect of anode sinter temp. and cell “pinch” on performance
4327	0.28 mg HYCAN	0.49 mg GSB-18	To test cell with wet-proofed cathode ERP
4338	0.29 mg HYCAN	0.50 mg GSB-18	Evaluate electrode sub- strates from alternative vendors
4339	0.29 mg HYCAN	0.50 mg GSB-18	
4340	0.29 mg HYCAN	0.51 mg GSB-18	
4341	0.29 mg HYCAN	0.51 mg GSB-18	
4347	0.27 mg HYCAN	0.49 mg GSB-18	
4348	0.28 mg HYCAN	0.50 mg GSB-18	
4342	0.26 mg HYCAN	0.51 mg GSB-18	Evaluate electrode catalyst layers with wettability control features
4343	0.25 mg HYCAN	0.48 mg GSB-18	
4344	0.26 mg HYCAN	0.52 mg GSB-18	
4345	0.26 mg HYCAN	0.48 mg GSB-18	
4360	0.26 mg HYCAN	0.51 mg GSB-18	
4361	0.26 mg HYCAN	0.50 mg GSB-18	
4362	0.26 mg HYCAN	0.50 mg GSB-18	
4363	0.25 mg HYCAN	0.50 mg GSB-18	

Table 2.2-2. Performance and Gain Data for Builds 4315 and 4327					
Cell #	Hours	Performance (V) at 300 ASF/415°F	Gains at 300 ASF (mV)		
			O₂	H₂	iR (mV)
4315	2200	0.599			
	2890	0.578	134	27	28
	3760	0.578			
4327	2192	0.608			
	2854	0.611	112	26	24
	3062	0.612			

The difference in performance between the two builds is accounted for by the differences in hydrogen and oxygen gains.

Builds 4338, 4339, 4340 and 4341 contain electrodes on a new substrate (Vendor A). Last month the response of the cells to electrolyte additions, which raised the fill of the ERP's to 50-60%, was investigated. The two builds (4338 and 4339) with ERP's at both the anode and cathode showed increasing hydrogen gains with increasing fill. The two cells (4340 and 4341) in which the cathode ERP's are wetproofed exhibited much greater overall losses. These losses were mainly due to increased oxygen gains. In the present reporting period the same cells were subjected to a shutdown and restart employing procedures similar to those used for on-site powerplants. The results are summarized in Table 2.2-3.

**Table 2.2-3. Shutdown Losses –
Build 4338 through 4341**

Cell #		Hours	Cell Voltage	Gains @ 300 ASF (mV)	
				O ₂	H ₂
4338	Pre S/D	1811	0.619	112	21
	Post S/D	1879	0.610 (9)	115 (3)	27 (6)
4339	Pre S/D	1805	0.615	104	21
	Post S/D	1873	0.607 (8)	109 (5)	25 (4)
4340	Pre S/D	1780	0.582	131	27
	Post S/D	1848	0.556 (26)	145 (14)	41 (14)
4341	Pre S/D	1762	0.603	114	26
	Post S/D	1831	0.580 (23)	127 (13)	35 (9)

The shutdown procedure was designed primarily to avoid corrosion of the cathode by keeping the cell voltages below 0.8V, but this does not prevent the individual electrodes from experiencing large swings in potential. As the table shows, all four cells suffered performance losses as a result of this exercise. Diagnostics revealed that there was an increase in both the hydrogen and oxygen gains and that the sum of the increases in these gains matches the observed losses in the voltages of the cells.

Diagnostic tests on cells 4347 and 4348, with Vendor B substrates confirmed that both were suffering from reactant crossover. The cells were shutdown.

Four cells (4342, 4343, 4344, 4345) have completed a program to evaluate new electrode catalyst layers. The final operations included a wet-up cycle simulating preparation of stack shipment. The results of the wet-up cycle are shown in Table 2.2-4. The results of the acid addition are shown in Table 2.2-5. Figure 2.2-1. shows how the oxygen and hydrogen gains changed with time. It is clear that the primary cause of decay is the cathode. The anodes appear to be stable; only a small increase in hydrogen gain is seen when the acid fill of the cells is increased from 35% to 45%. Performance histories for the cells are shown in Figure 2.2-2.

Since the cathodes were the main cause of decay, new cathodes were fabricated with hydrophobicities intermediate between those in cells 4344 and 4345. Cells containing the new cathodes have been started and the initial performances are given in Table 2.2-6. The cells will follow the same test program as the earlier cells: high current density excursions, shutdown cycles, wet-up cycle and acid fill increase.

Table 2.2-4. Effect of Wet-up on Performance

Cell No.	Performance @ 300ASF (mV) (Pre/Post - Shutdown Cycles)		
	Cell Voltage	Oxygen Gain	Hydrogen Gain
4342	548/548	139/136	25/24
4343	566/551	127/139	23/23
4344	596/581	114/119	21/21
4345	581/576	108/107	22/21

Table 2.2-5. Effect of Acid Addition on Performance

Cell No.	Performance @ 300ASF (mV) (Pre/Post - Acid Addition)		
	Cell Voltage	Oxygen Gain	Hydrogen Gain
4342	543/524	137/144	24/35
4343	558/554	139/136	23/27
4344	583/573	119/127	21/27
4345	576/561	107/114	21/32

Table 2.2-6. New Cell Initial Performance

Cell No.	Load Time - Hrs.	Cell Voltage @ 300 ASF - (mV)
4360	164	634
4361	211	636
4362	181	627
4363	133	641

Figure 2.2-1. Hydrogen and Oxygen Gains at 300 ASF

Figure 2.2-2. Subscale Cells Performance

TASK 3 - PROCESS DEVELOPMENT

Subtask 3.1 - Substrates

Objectives

The objectives of this subtask are to develop the process technologies required to produce electrode substrates and electrolyte reservoir plates that meet the technical requirements and cost objectives established in the conceptual design.

Activity

One hundred fifty full size substrate precursors were carbonized and are awaiting graphitization.

The ERP's that were subjected to an experimental one step heat treatment appear to be in satisfactory condition. These parts are now being characterized to establish their physical properties for comparison with requirements.

Subtask 3.2 – Integral Separator

Objectives

The objective of this subtask is to develop the process technology to fabricate integral separators, up to 10-ft² in size, that meet the technical requirements and cost objectives established in the conceptual design.

Activity

The examination of ISP configurations is continuing. Data from numerous lab tests is being accumulated and reviewed for ISP effectiveness against acid electrolyte transfer between cells. Laboratory attempts to achieve acid transfer in the laboratory fabricated ISP's remains unsuccessful. Lab sample ISP gas diffusion, permeability and dye penetrant testing has shown that changes in the ISP structure can result from repeated thermal cycling; however, to date these samples remain effective electrolyte barriers.

The continuing test program now includes alternate ISP design configurations which are believed to offer improvements over the baseline configuration. These configurations are being tested in parallel with the baseline design.

The full size ISP fabrication effort has been initiated. Material and tooling is being prepared. Initial trials will enable fabrication of full size samples of promising subscale approaches and will provide manufacturing experience with various alternatives being considered.

Subtask 3.3 – Seals and Matrix

Objectives

The objective of this subtask is to develop the technology to fabricate higher integrity seals and matrices that meet the technical requirements and cost objectives established in the conceptual design.

Activity

Electrode/ERP Edge Seals

Work on polymeric edge seals continues. The quarter started with an approach to coat a polymer solution into the edge seal region of an electrolyte reservoir plate (ERP). Component testing with edge seals formed with polymeric solutions shows that edge abrasion results in loss of sealing ability. Table 3.3–1 shows that low electrolyte fill levels yield unacceptable bubble pressures after 0.100 inches of the seal has been removed. The coating approach was eliminated from consideration.

**Table 3.3–1. Abraded Edge Seal Bubble Pressures
Polymer Seal Formed with Solution**

Electrolyte Fill	Lower Solids Solution	Higher Solids Solution
10% Fill	B.P. = 0 PSID	B.P. = 0 PSID
20% Fill	B.P. = 0 PSID	B.P. = 2 PSID
30% Fill	B.P. = 2 PSID	B.P. = 4 PSID
50% Fill	B.P. = 10 PSID	B.P. = 16 PSID

The approach currently being pursued involves machining a channel in the seal region and filling the channel with extruded fluorcarbon polymer. The fluorcarbon polymer is the same as the one being tested in the endurance cell reported above. The first set of samples made to evaluate this concept used a bead of polymer compounded with a blowing agent to expand the polymer during the cure cycle. The choice of an expandable polymer allowed for conventional component processing and stack assembly. The seal created with the expandable polymer shows promise when the channel dimension is reduced to put the unexpanded polymer in compression. Putting the unexpanded polymer in compression eliminates the need to use an expandable formulation and samples made with the solid polymer are showing good room temperature and 400°F sealing. Fabrication and stack assembly considerations are being addressed. Effort is now being directed to define the groove dimension and polymer formulation best suited to a compressive seal. Table 3.3-2 shows the results of break through testing on recent sub-scale samples.

Table 3.3-2. Summary of Polymer Edge Seal Break Through Pressure

Material	Channel Dimen.	Percent Allowable Expansion	Mating Surfaces Painted	Cure Dimension Above Channel	Cure Temp. Deg F	Cure Pressure	DRY		10% ACID FILL	
							Break Through Pressure		Bubble Pressure Room Temp.	Bubble Pressure 400F
							Room Temp.	400F		
Expandable Polymer	0.95" x 0.110"	33	No	0	400F	50 pli	0		0	
Expandable Polymer	0.95" x 0.110"	33	No	0	400F	50 pli	0		0	
Expandable Polymer	0.95" x 0.110"									
Expandable Polymer	0.95" x 0.110"	21	No	0	400F	50 pli	0		0	
Expandable Polymer	0.95" x 0.90"	9	Yes	0	400F	50 pli	0		1 psi	
Expandable Polymer	0.95" x 0.85"	3	Yes	0	400F	100 pli	0		0	
Expandable Polymer	0.95" x 0.80"	-3	No	0	400F	100 pli	0	5 psi	0	11 psi
Expandable Polymer	0.95" x 0.80"	-3		.002	400F	100 pli	0	5 psi	0	
Expandable Polymer	0.95" x 0.63"	-24	No	.008	400F	50 pli	0		0	16 psi
Expandable Polymer	0.95" x 0.65"	-21	No	.010	400F	10 pli	6 psi	12 psi	0	
Solid Polymer	0.95" x 0.65"	-15	No	.005	400F	50 pli	15 psi	25 psi	0	
Solid Polymer	0.95" x 0.70"	-10	No	.002	400F	50 pli	22 psi	43 psi	0	

Three formulations of the fluorocarbon polymer have been compounded and extruded to make subscale samples. The formulations were selected to address compressive set and thermal expansion. They are listed in Table 3.3-3.

Table 3.3-3. Formulations of Fluorocarbon Polymer				
	Fluorocarbon Elastomer	Carbon Filler	Curing Agent	Relative Expansion
A	100	15	15	4
B	100	30	15	3
C	100	45	15	1

A two inch by two inch endurance bench cell was started to confirm the electrochemical compatibility of the polymer in direct contact with an electrode. Diagnostics didn't show any problems, and it continues to run with normal performance and decay.

Matrices

A curtain coater trial has been run with submicron SiC ink. The ink includes a dispersant. The dispersant forms an ink with a viscosity of 350 – 400 cps. The ink formed a curtain and didn't have a foaming problem with the high solids content. Previous experience with submicron SiC inks have suffered from a foaming problem that precluded it's use.

Although we micropulverized the SiC before mixing the ink, the ink was gritty. Parts coated at the maximum belt speed (required to get a 1 mil thick matrix) were spotty and unacceptable.

More development work is required to define the solids content and viscosity to successfully coat electrodes with a thin matrix on the curtain coater using submicron ink.

Subtask 3.4 – Advanced Coolers

Objectives

The objective of this subtask is to develop material and process technology to fabricate coolers in sizes that meet the technical requirements and cost objectives established in the conceptual design.

Activity

Three full size coolers with arrays and two coolers without arrays were molded previously. Four out of the five samples were post baked. The results are summarized in Figure 3.4–1.

Figure 3.4–1. Full-Scale Molding Trial Results			
Cooler #	Component Description	Molding Notes	Post Baking Results
1	Graphite and Resin	–	No cracks or blisters
2	Graphite and Resin	–	No cracks or blisters
3	Graphite and Resin with Array	Bumps over tube	Cracks over tube
4	Graphite and Resin with Array	–	Not Post Baked
5	Graphite and Resin with Array	–	No cracks or blisters

Full size cooler #4 was cross sectioned in the as-molded condition to evaluate the tube to composite contact. Photomicrographs showed a 0.001” gap between the tube and composite over most of the tube circumference.

Cooler #5 was molded with a tube array treated to enhance the bonding between the tube and composite. This treatment was conceived to eliminate the gap at the tube and composite interface to improve thermal performance. The treatment was evaluated in subscale 6-inch by 6-inch coolers. Results are shown in Figure 3.4–2.

**Figure 3.4-2. Thermal Performance Comparison
Subscale 6 inch x 6 inch Coolers**

Description	Thermal Resistance Hr Ft² °F/Btu
Goal	8.00×10^3
Array Without Treatment	12.30×10^3
Array With Treatment	8.05×10^3

Photomicrographs of the treated tube array in subscale composites show no gap at the tube and composite interface. A subscale 6 x 6 inch cooler with a treated tube array was thermal cycled three times to 400°F. IR increased about 10% as shown in Figure 3.4-3.

A test to measure tube to composite electrical resistance was developed as a means to evaluate material and process changes in subscale cooler development trials. Electrical resistance tends to increase with increasing thermal resistance as shown in Figure 3.4-4.

Figure 3.4-3. Thermal Resistance as Function of Thermalcycling for Molded Cooler Number 34

Figure 3.4-4. Molded Cooler Thermal Resistance Vs. Tube to Holder IR

TASK 4 – STACK DESIGN

Objectives

The objective of this task is to update the full-scale conceptual design and to define designs for one small area development stack and three 10-ft² subscale stacks.

Activity

The drawings for both reactant flow distribution pipes which are installed in the air and fuel inlet manifolds of the small area development stack were revised.

A series of drawings of the solid graphite cooler holder assembly and details showing alternate manufacturing techniques which provide acid protection for the cooler is being worked concurrently with the development and evaluation activities being conducted in subtask 3.4.

TASK 5 – FABRICATION**Subtask 5.1 – Repeat Components****Objectives**

The objective of this effort is to fabricate the repeat components for one small area development stack and three 10-ft² subscale stacks each consisting of approximately 30 cells. These stacks will be of the Configuration B cell design. The repeat components consist of the substrates, electrodes, electrolyte reservoir plates, and cooler assemblies.

Activity

No activity scheduled during this report period.

Subtask 5.2 – Non-Repeat Components

Objectives

The objective of this effort is to fabricate the non-repeat components for the small area development stack and three 10-ft² subscale stacks of approximately 30 cells each. These stacks will be of the Configuration B cell design. The non-repeat components consist of reactant manifolds, coolant manifolds, axial load system, power take-off hardware and pressure containment vessel.

Activity

Two new types of cooler connecting hoses are being evaluated to reduce hose costs and to qualify an additional supplier. One new hose assembly type being tested is fabricated with a modified dielectric hose formulation. All other hose materials and the connecting system are identical to the baseline assembly. The second type of hose assembly employs an alternative dielectric concept and connectors. Four hoses of each type are being tested at approximate stack operating conditions.

After 1400 hours of testing the hoses were inspected and found to be in satisfactory condition. The test was then restarted. Presently, the hoses have accumulated 2300 hours.

Alternative reactant manifold coatings are being evaluated to reduce coating costs and to qualify additional suppliers. The coating types presently being evaluated consist of a low-cost PFA coating and ceramic coatings.

An alternative PFA coating vendor was identified. Peel tests of the new coating indicate strengths of about 4 pounds per linear inch (PLI) as an average prior to the steam test. After the steam test the peel strengths were measured and found to be about 2 PLI. The steam test did not cause any delamination of the coating. The PFA layer varied from 2 to 11 mils.

The evaluation of ceramic coatings as an alternative to PFA coatings is continuing. A series of coating samples are being tested at various temperatures. The corrosion rate of these samples have been found to be temperature dependant. At cell stack operating conditions the corrosion rate of these materials are too great for consideration as a replacement for the baseline PFA manifold coatings. The final set of samples are being evaluated at 250°F for possible use in application in other areas within the powerplant.

Subtask 5.3 – Stack Assembly**Objectives**

The objective of this effort is to assemble the small area development stack and two 10-ft² subscale stacks of Configuration B cells for testing at 120 psia. The third 10-ft² subscale stack will be assembled and tested under an anticipated EPRI program.

Activity

No activity scheduled during this report period.

TASK 7 – MANAGEMENT AND DOCUMENTATION

Objectives

The objective in this task is to provide the program management necessary to maintain technical and budget control of the program activities, and to provide adequate documentation of its progress per contract requirements.

Activity

The following reports were submitted during the quarter:

- Monthly Technical Progress Report No. 13 for May (FCR-10421) was issued on July 26, 1989.
- Quarterly Technical Progress Report No. 14 for April-June (FCR-10498) was issued on August 24, 1989.
- Monthly Technical Progress Report No. 15 for July (FCR-10544) was issued on August 28, 1989.
- Cost Management Report No. 14 for June (FCR-10497) was issued on May 18, 1989.
- Cost Management Report No. 15 for July (FCR-10543) was issued on August 14, 1989.
- Cost Management Report No. 16 for August (FCR-10587) was issued on September 21, 1989.

END

**DATE
FILMED**

3 / 30 / 93