WSRC-RP-92-991

**WASTE ACCEPTANCE AND THE DWPF STARTUP TEST
PROGRAM: IMPACTS OF PROCESS CHANGES - (U)**

by M. J. Plodinec

Westinghouse Savannah River Company
Savannah River Site
Aiken, South Carolina 29808

Other Authors:

Received by OSTI
JAN 21 1993

This paper was prepared in connection with work done under Contract No. DE-AC09-89SR18035 with the U. S. Department of Energy. By acceptance of this paper, the publisher and/or recipient acknowledges the U. S. Government's right to retain a nonexclusive, royalty-free license in and to any copyright covering this paper, along with the right to reproduce and to authorize others to reproduce all or part of the copyrighted paper.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

WESTINGHOUSE SAVANNAH RIVER COMPANY
SAVANNAH RIVER LABORATORY

WSRC-RP-92-991
Revision 0

KEY WORDS: Waste Ac-
ceptance, late washing,
Qualification Runs, ni-
tric acid flowsheet,
sludge-only operation

August 24, 1992

TO: E. W. HOLTZSCHEITER

FROM: M. J. PLODINEC

**WASTE ACCEPTANCE AND THE DWPF STARTUP TEST PROGRAM:
IMPACTS OF PROCESS CHANGES (u)**

CC: L. M. Papouchado, 773-A
M. D. Boersma, 704-T
J. T. Carter, 704-1T
L. F. Landon, 704-T
R. A. Jacobs, 704-T
C. T. Randall, 704-T
Glass Technology Group (10)
SRL Records (4)

**WASTE ACCEPTANCE AND THE DWPF STARTUP TEST PROGRAM:
IMPACTS OF PROCESS CHANGES**

INTRODUCTION AND SUMMARY

The DWPF is currently carrying out a Startup Test Program which will lead to radioactive operations in the facility. The objective of a significant portion of this program is to demonstrate that the DWPF can reliably make glass which satisfies DOE's product specifications.¹ This objective will be achieved through a series of integrated process campaigns using feeds of various compositions (the Qualification Runs).² During these campaigns, the DWPF Glass Product Control Program³ (GPCP) will be used to ensure that glass is made which meets specifications. The GPCP uses a correlation between glass composition and leach test results to determine whether a particular batch of feed will make acceptable glass (i.e., glass which will meet the specifications).

Currently, the DWPF process is undergoing several changes intended to enhance its reliability, most notably the late washing process. An important question has been raised about the impact of process changes such as this on the Startup Test Program. The importance of this question is magnified by the certainty of future changes in the composition of waste generated at SRS.

As is discussed below, the Glass Product Control Program is designed to allow the DWPF (and the Tank Farm) to make any process changes which are needed, as long as the following conditions are met:

- The correlation between composition and leach test results can be applied to the feed in the Slurry Mix Evaporator. In the case of late washing, this condition is met, since the chemical composition of the glass will not change significantly from those which have already been tested.
- The material properties of the feed slurries and the glass do not stray outside the design boundaries of the melter, the Slurry Mix Evaporator (SME), and the Melter Feed Tank (MFT). Again, in the case of late washing, this condition is met.

Thus, late washing will not require any changes in the Startup Test Program related to Waste Acceptance. Changes to more closely mimic the late washing or sludge-only feeds may be prudent in terms of operator familiarity and facility operations, but are not required to meet product specifications.

GLASS PRODUCT CONTROL PROGRAM

The DWPF will use the Glass Product Control Program to ensure that

the glass produced satisfies DOE's product specifications. The specification of greatest importance is the product consistency specification, which requires that the DWPF consistently produce a glass which is more durable than the glass identified in the Environmental Assessment for the DWPF.⁴ Thus, the GPCP is heavily weighted toward glass durability (however, it also includes re-reporting activities).

Bases for the Glass Product Control Program

The GPCP rests on four basic postulates:

- The only variable which the DWPF can control which affects glass durability is its chemical composition. This is based on extensive work both by SRTC and by other laboratories world-wide.⁵ The DWPF has chosen to control the glass composition through control of the feed composition.
- Variations in waste composition are likely, which will fall outside the range of compositions currently projected for DWPF production. Waste generation processes will change in the future, because of the changing mission of SRS. The waste generated will contain greater concentrations of actinides, and as well as chemicals used in canyon clean-up processes, which have not yet been developed. As a result, it is not possible to identify or qualify all of the compositions which will be fed to the DWPF. However, it is possible to qualify a methodology which will allow the DWPF to process very different wastes in the future without having to requalify the entire DWPF system. This methodology is embodied in the GPCP. Thus, the Qualification Runs are designed to qualify the GPCP, and not the compositions tested during the campaigns.
- Samples of feed slurries taken from the SME and the MFT are representative of the slurries themselves. If the samples are representative of the material in the SME or the MFT, then they can be used to determine whether the feed slurry will produce glass which will meet product specifications. Testing at TNX has provided the technical basis for this.^{6,7} However, the Qualification Runs will confirm the TNX results for the equipment in the facility, and quantify errors due to the sampling and analysis systems, and due to process variability.
- Once a batch of feed is determined to be acceptable (i.e., will produce a glass which will satisfy product specifications), it will not become unacceptable. An acceptable SME batch will be mixed with a heel of acceptable material in the MFT, which will in turn be mixed with acceptable material in the melter. If the properties of the materials are within the design boundaries of the equipment, then there should be no way for the two materials (heel and fresh batch) to form an unacceptable product.⁸ However,

there has been no direct demonstration that this will be the case for the DWPF. Thus, establishing that the composition will not become unacceptable after it is determined to be acceptable is another objective of the Qualification Runs. The most stringent test of this will occur when the composition of the feed changes (e.g., going from "HM" to "Purex").

Program Elements

The Glass Product Control Program can be thought of as being made up of three elements: qualification of waste, ensuring feed acceptability, and reporting.

Qualification of waste for DWPF processing. The considerations above imply that the first part of the GPCP must be qualification of the incoming waste, i.e., demonstrating that the GPCP can be applied. This will be accomplished by showing that the waste can be processed in the facility, and can be controlled using the current correlation between composition and leach test results. Thus, the GPCP requires characterization of samples of the sludge batch and precipitate batch (i.e., samples of actual waste) prior to processing.

This will be accomplished as follows. Samples of actual waste will be brought to SRTC, and the chemical and radiochemical composition of these waste samples will be determined. Using the current correlation between glass composition and leach test results, SRTC will then determine whether these wastes can be combined with the frit currently being used by the DWPF to produce a glass which satisfies the specifications.

If there is a blend of sludge, frit and precipitate which satisfies the product specification, SRTC will then process the waste samples in the same manner as in the DWPF. The sludge and PHA will be mixed with frit and vitrified to produce a glass which should satisfy the specification. This glass will be subjected to the specified leach test to ensure that the predicted behavior is realized in practice, and that the glass does in fact satisfy the product consistency specification. In the unlikely event that no blend of the current frit and wastes satisfies the specification, or if the range of such blends is too restrictive for DWPF processing, then SRTC will reformulate the frit.

SRTC will also characterize the rheological properties of the waste to ensure that they are within the design envelope of the SME and MFT. If they are not, SRTC will be responsible for developing means to ensure that the feed does not segregate during processing.

In addition, for each sludge batch, a variability study will be performed, which establishes the applicability of the correlation

between the leach test results and the chemical composition for that sludge batch. If the relationship does not apply over the entire range of possible compositions, then the DWPF will either constrain the process to operate only within the region over which the relationship does apply, or will require that SRTC develop a new relationship for that sludge batch.

The purpose of this study is to look for any interactions between the process and a particular sludge batch which would impact glass durability. As an example, a highly reduced sludge may precipitate metals, thus removing them from the glass phase. This is not modeled in the current correlation between composition and leach test results. The DWPF could choose either to restrict the amount of reductant to avoid metal formation, or to have SRTC include this effect in the correlation between composition and leach test results.

Characterization of the initial sludge is currently scheduled to begin by October, 1992.

Ensuring feed acceptability. Samples of each process batch of feed in the SME will be taken using the DWPF sampling system. For each process batch, the chemical composition of the feed slurry will be used to predict the leach test results of the glass. If the process batch would produce glass which would not satisfy the product consistency specification, the process batch will be held in the SME, and its composition adjusted and re-analyzed. Once it is established that the process batch will produce glass which satisfies the specification, the process batch will be transferred to the Melter Feed Tank, and then to the melter. Qualification of the waste is thus a necessary preamble, because the determination of acceptability can be questioned unless the correlation has been shown to be valid for that composition, and the material properties (particularly rheological properties) have been verified.

Reporting. This element includes reporting the glass chemical and radiochemical composition, and the predicted leach test results. Confirmation of the reported values will be provided by characterization of glass samples. This element of the GPCP is not dependent on prior processing, and thus is not discussed further here. Further detail on the entire program is available in Volume 6 of the Waste Form Qualification Report.³

STARTUP TEST PROGRAM

The most important objective of the DWPF Startup Test Program in terms of meeting the product specifications is to demonstrate the ability to reliably produce an acceptable product during actual production. This constitutes qualification of the GPCP.

The GPCP will be qualified through production of simulated canni-

stered waste forms in prototypic manner, during the Qualification Runs. The Qualification Runs are based on the thesis that if the composition / leach test correlation has been used properly to judge the acceptability of the feed, the only possible cause of failure of the GPCP is segregation of the feed. This will occur only if the rheology of the material is not consistent with good mixing in the process vessels. Thus, the purpose of varying the feed composition during the Startup Test Program is to test a range of rheological properties, particularly for the melter, and not to qualify a set of compositions.

The DWPF could have pursued an alternative course. Rather than qualifying a methodology for handling any waste composition, the DWPF could have tried to qualify a series of compositions, corresponding to each of the different types of wastes to be processed. This approach has the following drawbacks:

- It requires a great deal more information about the waste compositions than is currently available. Getting the additional information necessary would entail additional Tank Farm sampling, and increased exposure of personnel.
- It reduces the ability of both the DWPF and the Tank Farm to make process modifications when needed. Although hard to measure, this would exact a heavy price in terms of hindering operating flexibility.
- It consumes resources which are not available. As an example of this approach in practice, the French qualify a single composition at a time. To do so, they generally have performed full-scale testing of over 150 different compositions. When the waste changes, they go through the entire program again (twice at Marcoule, once at La Hague). This approach is simply not practical for the DWPF.

PROCESS CHANGES

Several potential process changes are being considered at the present time. These include late washing of the tetraphenylborate precipitate, substitution of nitric acid for part of the formic acid used in the DWPF, and initial radioactive operations with sludge alone. In addition, future Separations canyon operations (particularly decommissioning and decontamination) are likely to produce waste much different than the current contents of the waste tanks in the Tank Farm. In the following sections, the impacts of each of these on DWPF Waste Acceptance is briefly discussed.

Late Washing. The late washing flowsheet is aimed at removing nitrate and nitrite from the precipitate before it is delivered to the DWPF. The composition of the glass to be produced is within

the set of those which have already been shown to be acceptable, and for which the current composition / leach test correlation is valid. The rheological properties of the slurries in the SME and MFT are primarily set by the sludge, and are relatively invariant to the PHA. The viscosity of the glass can be adjusted to be within the design envelope of the melter. Thus, late washing will not significantly affect DWPF Waste Acceptance, and will require no changes in the Qualification Runs.

Nitric Acid. The nitric acid flowsheet is aimed at reducing the potential for hydrogen generation by substituting nitric acid for part of the formic acid used in the DWPF. This flowsheet also provides more flexibility in avoiding overly reducing melter feeds. This process change does not affect the glass composition, so glass durability and viscosity should be unaffected. However, this change could affect slurry rheology. Thus, SRTC is characterizing the rheology of slurries produced according to this flowsheet. Assuming that the nitric acid flowsheet does not produce SME and MFT slurries outside the design envelope of these vessels (which is very likely), then no changes in the Qualification Runs will be necessary.

Sludge-Only Operation. This process change can be implemented by either substituting simulated PHA for actual radioactive material, or by compensating for the loss of PHA by modifying the frit. For both options, the glass produced will be within the set of those which have already been shown to be acceptable, and for which current composition / leach test correlation is valid. Neither option should affect glass viscosity. Again, since slurry rheology is primarily set by the sludge, sludge-only operation should not affect slurry rheology. Thus, neither option will affect DWPF Waste Acceptance, and nor require changes in Qualification Runs.

It should be noted that both options will require the DWPF to conduct operations in a different manner than during normal sludge / precipitate processing. In the case of the simulated PHA, the simulant will have to be procured in large quantities, and introduced into the process (probably through the Salt Cell). If a modified frit is used, most of the Salt Cell operations will be bypassed. In both cases, this will not impact DWPF Waste Acceptance, because the GPCP only goes back as far as the SME. Thus, it may be prudent to carry out this modified mode of operation during the Startup Test Program to ensure operator familiarity and reliable facility operations, but it is not required to meet product specifications.

Future Waste from Separations. The GPCP was originally formulated to facilitate future changes in Separations canyon operations. It is expected that when the canyons are decommissioned, cleanout will produce wastes much higher in actinide content, and containing species from cleaning agents. It is not possible to identify

these compositions at the present time.

However, there is high confidence that the GPCP will be able to assure production of an acceptable product from such wastes. As has been described above, SRTC is responsible for determining whether waste from future operations satisfies the two criteria listed in the Introduction. Because the current glass composition / leach test and viscosity correlations are based on "first principles," they are more likely to apply to different wastes than empirical models. If a certain waste composition will not satisfy the criteria, then there are several clearcut options available. If the composition / leach test or composition / viscosity correlations do not hold over the entire range of possible compositions, then the DWPF can simply limit the waste loading to the range of applicability of the correlations. If necessary, SRTC could simply develop new correlations specific to that type of waste. If the waste produces a melter feed slurry which is outside the design limits of the SME or the MFT, then adjustment of slurry rheology can be rather easily accomplished in several ways (variation of waste loading, addition of thickeners or thinners, chemical adjustments).

CONCLUSIONS

The Glass Product Control Program has been formulated to allow the DWPF (and the Tank Farm) maximal flexibility in process modification. During the Qualification Runs, the DWPF will establish that the GPCP will reliably produce an acceptable product. DWPF process changes currently being considered will most likely produce glass which obeys the current composition / leach test correlation, and feed slurries whose rheological properties are within the design envelopes of process vessels. Thus, these process changes will not require any changes in the DWPF Qualification Runs program.

ACKNOWLEDGEMENT

I am grateful to Joe Gentilucci, Roy Jacobs, and, of course, Sharon Marra for providing useful comments, criticisms, and suggestions.

REFERENCES

1. Waste Acceptance Preliminary Specifications for Vitri-fied High-Level Waste Forms, DRAFT, July, 1991.
2. DWPF Waste Form Compliance Plan, Revision 1, USDOE Document WSRC SW4-6, Westinghouse Savannah River Co., Aiken, SC (1992).
3. S. L. Marra, M. J. Plodinec, DWPF Glass Product Control

August 24, 1992

8

WSRC-RP-92-991

Program, USDOE Report WSRC-IM-91-116-6, *Draft*, March, 1992.

4. U. S. Department of Energy, **Environmental Assessment - Waste Form Selection for SRP High-Level Waste**, USDOE Report DOE/EA 0179, Washington DC (1982).

5. W. T. Goldston and M. J. Plodinec, "The DWPF Strategy for Producing an Acceptable Product," in **Ceramic Transactions - Nuclear Waste Management IV, 23**, G. G. Wicks, et al. (eds.), 443-52 (1991).

6. M. J. Plodinec, "Uniformity of Material in the SME and MFT," USDOE Report WSRC-TR-92-284, May 29, 1992.

7. W. J. Jenkins, "Precision and Accuracy of the SME Prototypic Sampler," USDOE Report WSRC-RP-91-214, February 12, 1991.

8. M. J. Plodinec, **Reporting the Chemical Composition of the DWPF Product**, USDOE Report WSRC-IM-91-116-2, *DRAFT B*, June, 1992.

**DATE
FILMED**

4 / 28 / 93